

# SpaceX Starlink Satellite Broadband Communications for ITS Pilot

Providing broadband to rural ITS field equipment

# WHAT IS THE NEED?


Reliable high-bandwidth rural communications have been a significant challenge since early deployments of Intelligent Transportation Systems (ITS) at Caltrans. While there is an effort to install fiber-optic broadband services on select rural highways throughout the state, the effort will take years before it's useable, won't be installed on every rural state highway, and will be located in areas highly susceptible to damage from wildfire, floods and landslides. Reliable communications are critical to the perceived reliability of ITS Elements for the traveling public. ITS Elements cease to function as intended when communications systems fail. This poses a problem is rural areas where ITS Elements are deployed to mitigate the effects of non-reoccurring congestion due to snow, fire, floods, and other major incidents. Caltrans needs to find an alternative reliable high-bandwidth wireless communications option that is less susceptible to weather induced incidents.

### WHAT ARE WE DOING?

We are proposing to procure, install, operate, and evaluate four SpaceX Starlink satellite broadband communication services for various ITS Elements in District 2. Most rural Caltrans field sites selected have been impacted by the lack of available high-bandwidth communications options. These ITS field sites include infrastructure related to changeable message signs, video sites, and roadside weather information systems. This project will evaluate the procurement, construction, installation, integration, operation, and maintenance of four selected sites in rural regions of the state.

# WHAT IS OUR GOAL?

To provide a reliable, cost-effective broadband communications solutions to field sites located in remote rural areas of the State.



# NOVEMBER 2023

Project Title:

SpaceX Starlink Satellite Broadband Communications for ITS Pilot

Task Number: 4059

Start Date: August 15, 2022

Completion Date: April 30, 2025

Task Manager: Sean Campbell Senior Transportation Engineer Electrical (Specialist) sean.campbell@dot.ca.gov



DRISI provides solutions and knowledge that improves California's transportation system

# WHAT IS THE BENEFIT?

As heavy snow, wildfires, floods, and other major incidents continue to impact terrestrial infrastructure, having an alternative high bandwidth communications option in rural areas will be crucial. Satellite broadband satellite services link to fixed, low earth orbit satellites. Satellite services do not rely on terrestrial infrastructure, providing immunity to the incidents described above. With throughputs of up to 20 Gbps, satellite broadband offers enough bandwidth for the most bandwidth intensive TMS applications.

### WHAT IS THE PROGRESS TO DATE?

- The research team has contracted with AHMCT to provide research on the SpaceX Starlink system. The contract was executed in Fall 2022.
- District 2 has selected three hub locations and 10 field locations. Based on Starlink availability, the project team will eventually select one hub location and four field locations.
- The research team created an "issues and features" document providing insight on various Starlink kits, equipment, and features and documenting known issues with equipment.
- The research team visited the selected hub site and two field sites to test Starlink equipment procured to date and determine what additional mounting equipment would be necessary. The team's uplink/downlink test results were very promising at each site.
- The team has procured mounting equipment and lightning suppression equipment that will be used to mount the dish to the CCTV poles/communication towers. Testing has begun on the interface of the lightning suppression and the Starlink cabling to see what impact the additional equipment has on the Starlink equipment.
- Discussions with the Caltrans SatCom team about how we are using Starlink are ongoing.
- Equipment has been procured, including four flat high-priority kits and one high-priority kit. Mounting kits and piece parts to complete the installations have also been procured.
- Equipment to five field sites has been deployed.

Preliminary results are very promising and at this point have not had any significant issues or problems with the equipment.

- The research team will continue to work with Caltrans in the evaluation of the equipment.
- The technical advisory panel had indicated the need for a no-cost time extension for this project, which will now run until April 2025.

# **IMAGES**



Image 1: Starlink high-performance antenna (left side of image) after installation at the Redding Fiber Hub – Image Source - AHMCT



Image 2: Starlink high-performance flat antenna after installation – Image Source – AHMCT

The contents of this document reflect the views of the authors, who are responsible for the facts and accuracy of the data presented herein. The contents do not necessarily reflect the official views or policies of the California Department of Transportation, the State of California, or the Federal Highway Administration. This document does not constitute a standard, specification, or regulation. No part of this publication should be construed as an endorsement for a commercial product, manufacturer, contractor, or consultant. Any trade names or photos of commercial products appearing in this document are for clarity only.



SpaceX Starlink Satellite Broadband Communications for ITS Pilot





Image 3: Starlink high-performance flat antenna after installation – Image Source – AHMCT