

Capital Preventive Maintenance Project Initiation Document

To Request Programming in the 2016 SHOPP And Provide Project Approval

On Route 17 in Santa Cruz County

Between 0.10 miles North of Santos Village Road (PM 6.0)

And Santa Clara County Line (PM 12.55)

I have reviewed the right of way information contained in this Project Initiation Document and the R/W Data Sheet attached hereto, and find the data to be complete, current and accurate:



JAMIE LUPO

Acting, CHIEF, CENTRAL REGION RIGHT OF WAY


APPROVAL RECOMMENDED:



DOUGLAS P. HESSING

PROJECT MANAGER


APPROVED:



TIMOTHY M. GUBBINS
DISTRICT 5 DIRECTOR

12/16/14
DATE

Vicinity Map



On Route 17 in Santa Cruz County

Between 0.10 miles North of Santos Village Road (PM 6.0)

And Santa Clara County Line (PM 12.55)

This Capital Preventive Maintenance Project Initiation Document has been prepared under the direction of the following registered civil engineer. The registered civil engineer attests to the technical information contained herein and the engineering data upon which recommendations, conclusions, and decisions are based.



MICAELA GARCIA
REGISTERED CIVIL ENGINEER

11/6/14

November 2014
DATE



Table of Contents

1.	Introduction and Background.....	1-2
2.	Recommendation	2
3.	Purpose and Need Statement.....	2
4.	Existing Facility, Deficiencies and Traffic Data	3-4
5.	Corridor and System Coordination.....	5
6.	Alternatives.....	5-7
7.	Transportation Management.....	7
8.	Project Estimate.....	8
9.	Funding/Programming.....	9
10.	Schedule.....	9
11.	Risks.....	10
12.	FHWA Coordination.....	10
13.	Project Reviews.....	10
14.	Project Personnel.....	11
15.	Attachments.....	11

1. INTRODUCTION AND BACKGROUND

Project Description:

This project is located on Route 17, in Santa Cruz County, from 0.10 miles North of Santos Village Road (PM 6.0) to the Santa Clara County Line (PM 12.55). The existing highway for this location consists of dense graded Asphalt Concrete (AC) with a layer of Open Grade Asphalt Concrete (OGAC) for lanes and shoulders. The OGAC layer will have to be removed. Also, the section of roadway with High Friction Surface Treatment (HFST) placed between PM 9.4 and PM 9.6 in the southbound direction will be restored. This project proposes to cold plane 0.30 foot thick layer and overlay the existing lanes and shoulders with a 0.20 foot thick layer of dense graded Hot Mix Asphalt (HMA) and a 0.10 foot thick layer of OGAC. Heavily distressed pavement locations on traveled lanes and shoulders will be repaired by cold planing and replacing with 0.40 foot thick dense graded HMA prior to the overlay. The existing OGAC, plus 0.20 foot thick layer of existing AC pavement will be cold planed before placing the overlay to avoid impacts to the existing median barrier and inlets. The new Pavement Safety Edge Treatment will be implemented in this project.

Throughout the project length, the Metal Beam Guardrail (MBGR) and associated End Treatments will be upgraded to current standards. Vegetation control-minor concrete will be placed at the MBGR locations as a permanent vegetation control treatment. AC Dike will be reconstructed to current standard and shoulder backing will be applied to needed locations. There are no Americans with Disabilities Act (ADA) curb ramps within the limits of this project. Where applicable, existing drainage inlets will be raised to the new finish grade.

The current construction capital cost is \$12,654,000. No additional Right of Way will be required for this project. Potholing to identify existing utilities maybe required during the PS&E phase. Current cost associated with potholing is \$6,250. This project is proposed for programming in the 2016 SHOPP Pavement Preservation Program 20.XX.201.121.

See the Cost estimate for specific work items included in this project.

Project Limits	05-SCr-17 PM 6.0/12.55
Current Capital Outlay Support Estimate	\$2,879,000
Current Capital Outlay Construction Estimate	\$12,654,000
Current Capital Outlay Right-of-Way Estimate	\$6,250
Funding Source	20.XX.201.121
Funding Year	2018/2019
Type of Facility	4-Lane Conventional Highway
Number of Structures	N/A
Environmental Determination or Document	CE: CEQA/NEPA CEQA July 24, 2014 NEPA July 24, 2014
Legal Description	In and near Scotts Valley from 0.6 mile north of Granite Creek Road OC to Santa Clara County Line.
Project Development Category	5

2. RECOMMENDATION

It is recommended that this project be approved and authorization be granted to proceed to the design phase using HMA and a layer of OGAC.

3. PURPOSE AND NEED

Purpose:

The purpose of this project is to improve the ride quality and extend the service life of the existing pavement.

Need:

Route 17 is classified as a Rural Principal Arterial, High Emphasis Route and Terminal Access Route in Santa Cruz County. Route 17 runs north and south, and sustains high traffic volumes throughout the year. The pavement within the project limits is exhibiting distress and unacceptable ride quality, which, if left uncorrected, will continue to deteriorate.

4. EXISTING FACILITY, DEFICIENCIES AND TRAFFIC DATA

4A. Roadway Geometric Information

Facility Location	Min Curve Radius	Through Traffic Lanes			Paved Shoulder Width		Median Width	Additional Paved Width for Bicycle Lane or Other
		Num of Lanes	Lane Width (ft)	Type Flexible, Rigid, or Composite	Left (ft)	Right (ft)		
6.0/12.55	485	4	11-12	Flexible	0-8	3-8	4-34	N/A

Remarks:

This Project has been identified and developed as a Capital Preventive Maintenance (CAPM) candidate per Design Information Bulletin 81-01. As such, the scope of the project does not intend to change and/or upgrade existing geometric features.

4B. Condition of Existing Facility (Repeat for each homogeneous segment):

1) Traveled Way Data

PMS Category (1-29) 10 Priority Classification (.1-.4) 0.3

International Roughness Index (IRI) 125

***Rigid Pavement:**

***Flexible Pavement:**

* From latest PMS-Pavement Condition Inventory Survey Data.

3rd Stage Cracking % N/A Alligator B Cracking % 1.5%

Faulting N/A Patching % 0.7%

Joint Spalls N/A Rutting None

Pumping N/A Bleeding None

Corner Breaks % N/A Raveling None

Locations(s) of subsurface or ponded surface-water problem:

Drainage issues at a couple of shoulder locations will be addressed by grinding the asphalt shoulder and grading to drain to existing drainage inlets or culvert.

2) Pedestrian Facility Data

Facility Type and Location(s) <i>(Station, post mile or other reference point)</i>	Meets ADA Standards? <i>(Yes or No for each listed location)</i>	If Facility does not meet ADA Standards, what feature(s) are not ADA compliant? <i>(List features per location)</i>	Status of Each Noncompliant Location Use the following statements, as appropriate: <ul style="list-style-type: none"> • <i>Will be corrected as part of this project;</i> • <i>Will not be corrected because it is technically infeasible to correct; an ADA exception has been processed.</i>
Sidewalks: <i>(List locations as appropriate)</i>	N/A	N/A	N/A
Curb Ramps: None	N/A	N/A	N/A

Remarks: None.

4C. Structures Information

There are no structure vertical clearances within the project limits that will be affected. At all the structures (Sidehill Viaducts), the existing layer of asphalt concrete will be replaced.

4D. Vehicle Traffic Data

Construction Year ADT 55,468 (For 2017)

DHV 5380 % Trucks 2.7%

Remarks:

None.

Safety Review Date: 04/07/14

Remarks: None.

5. CORRIDOR AND SYSTEM COORDINATION

There is a project (05-0T980_) that will construct concrete barrier, a soil nail wall, and sidehill viaduct as part of shoulder widening on Route 17 from PM 8.2 to PM 10.1. This project is scheduled for construction in the spring of 2016. This CAPM project is compatible with the future concept of this route.

6. ALTERNATIVES

6A. CAPM strategy:

This project proposes to overlay the existing lanes and shoulders with a 0.20 foot thick layer of dense graded HMA and a 0.10 foot layer of OGAC. Heavily distressed pavement locations on the traveled lanes and shoulders will be repaired by cold planing and replacing with 0.40 foot thick dense graded HMA. The existing pavement will be cold planed to a depth of 0.30 foot, before placing the HMA and OGAC overlay. In addition High Friction Surface Treatment will be installed in the southbound lanes around Laurel Curve (PM 9.4 to 9.6) on top of the overlay. This project does not create any deviations from design standards. No design exceptions are required for this project.

Life Cycle Cost analysis

No Life Cycle Cost Analysis was performed as per HQ Pavement Program.

Enhancements

The following Design Information Bulletin (DIB) 81-01 recommended enhancements are incorporated into this project:

- Metal Beam Guard Rail and associated End Treatments will be reconstructed as necessary to meet current standards.
- AC Dike, where necessary, will be reconstructed to meet current standards. Dike (Type A) may be used in cut sections with slopes steeper than 3:1 and where existing conditions do not allow for construction of the wider Type D or E dikes.
- Replace existing traffic stripe and pavement markings to meet current standards.
- Shoulder backing material shall be specified and used at edge of pavements to eliminate drop-offs.
- Paving of the pullouts which are in poor condition.

Date of Traffic Operational Review Report March 6, 2014.

6B. Environmental compliance:

The Categorical Exemption document for the California Environmental Quality Act (CEQA) was received on July 24, 2014. The Categorical Exclusion document for the National Environmental Policy Act (NEPA) Compliance was received on July 24, 2014. See Attachment D for the conditions of the environmental clearance.

6C. Hazardous waste disposal site required? If yes, where are sites?

No hazardous waste disposal site is required for this project.

6D. Other agencies involved (permits/approvals from Fish and Game, Corps of Engineers, Coastal Commission, etc.):

There is no anticipated involvement by other state or federal agencies for this project.

6E. Material and/or disposal site need and availability?

Not applicable for this project.

6F. Roadside design and management:

The project is within existing State Right of Way. Appropriate roadside management will be implemented and specification for the project will contain provisions that will ensure worker protection.

6G. Right of way and utility issues:

Additional Right of Way is not required. Due to the nature of the proposed work, no utility conflicts are anticipated. Potholing to identify existing utilities, maybe required during the PS&E phase. Current cost associated with potholing is \$6,250 (Attachment E)

6H. Railroad involvement:

There is no railroad involvement in this project.

6I. Recycled materials:

Not applicable to this project.

6J. Local and regional input:

Not applicable to this project.

6K. What are the consequences of not doing this entire project?

We would anticipate higher pavement preservation costs in the future in addition to unacceptable ride quality if this project is not completed.

7. TRANSPORTATION MANAGEMENT

7A. Transportation Management Plan

This project will require a Traffic Management Plan (TMP) to minimize and manage traffic delays during construction operations of the project. Night work is anticipated to minimize disruptions. Lane closures will be necessary. Signing, including portable changeable message signs and a Public Awareness Campaign will be used to inform the public of current and upcoming construction activities. Construction Zone Enhanced Enforcement Program (COZEEP) will be used for this project.

Bike use in this location of Route 17 is a shared roadway. During construction roadway bike use will be maintained through traffic control.

7B. Vehicle Detection Systems

An existing vehicle detection loop system near post mile 12.4 will be replaced with a Microwave Vehicle Detection Systems (MVDS).

8. PROJECT ESTIMATE

	Lane- miles/Number	Estimate
Pavement Work		
Total Lane-Miles of CAPM Work	<u>26.2</u>	
HMA Pavement	<u>41,400 Tons</u>	<u>\$4,770,000</u>
OGAC	<u>17,000 Tons</u>	<u>\$2,130,000</u>
Tack Coat	<u>220 Tons</u>	<u>\$176,000</u>
Cold Plane (0.30')	<u>240,000 SQ Yd</u>	<u>\$721,000</u>
Digouts	<u>LS</u>	<u>\$954,000</u>
AC Price Fluctuation Index	<u>LS</u>	<u>\$267,000</u>
Other (Shoulder Backing, New Dike, Drainage & Minor Concrete- Vegetation Control)	<u>LS</u>	<u>\$452,000</u>
COSTS	SUBTOTAL	<u>\$9,470,000</u>

Non-pavement Work	(Yes/No)	Estimate
Does the Project Include:		
Railroad Agreements (List work required.)	<u>No</u>	<u> </u>
Traffic Control	<u>Yes</u>	<u>\$120,000</u>
Rumble Strips	<u>No</u>	<u> </u>
Correct Superelevation/ Cross slope Correction	<u>No</u>	<u> </u>
Traffic Items	<u>Yes</u>	<u>\$541,000</u>
Reconstruct MBGR (6,800)	<u>Yes</u>	<u>\$224,000</u>
Terminal End Sections (13)	<u>Yes</u>	<u>\$32,000</u>
Loop Detectors/Electrical Work	<u>Yes</u>	<u>\$125,000</u>
Stormwater	<u>Yes</u>	<u>\$30,000</u>
Other (RE Office, COZEEP, Public Awareness, & Message Signs)	<u>Yes</u>	<u>\$461,000</u>
COSTS	SUBTOTAL	<u>\$1,533,000</u>
	SUM OF	
	SUBTOTALS	<u>\$11,003,000</u>
	15% Contingency	<u>\$1,651,000</u>
TOTAL	PROJECT COST	<u>\$12,654,000</u>

9. FUNDING/PROGRAMMING

It has been determined that this project is eligible for federal-aid funding.

Capital Outlay Support and Project Estimates

Project Cost Component	Fiscal Years				Total
	2016/17	2017/18	2018/19	2019/20	
R/W Capital	\$7	0	0	0	\$7
Constr. Capital	0	0	\$15,381	0	\$15,381
PS&E Support	\$1,806	0	0	0	\$1,806
R/W Support	0	\$58	0	0	\$58
Constr. Support	0	0	\$1,474	0	\$1,474
Total Project Cost	\$1,813	\$58	\$16,855	0	\$18,726

Note: All costs X \$1,000. Support categories are the same as those identified by SB 45. Support Costs escalated at 3% per year. Construction Capital escalated at 5% per year. Support Cost ratio: 21% (All Support Costs divided by the sum of the escalated Construction Capital and escalated R/W Capital).

10. SCHEDULE

Project Milestones		Scheduled Delivery Date
PROGRAM PROJECT	M015	07/01/2016
PA&ED	M200	12/15/2014
PROJECT PS&E	M377	02/01/2018
RIGHT OF WAY CERTIFICATION	M410	05/15/2018
READY TO LIST	M460	07/17/2018
AWARD	M495	01/02/2019
APPROVE CONTRACT	M500	01/16/2019
CONTRACT ACCEPTANCE	M600	10/15/2019
END PROJECT	M800	01/16/2020

Note: This project will use AADD and will not be sent to HQ until Funds Certification.

11. RISKS

A Risk Management Plan has been developed by the Project Team. The primary risk to this project is a possible increase in HMA prices. The majority of the estimate for this project is HMA. An increase in this item could greatly increase the project cost. A summary of the risks are listed in the Risk Register (Attachment J).

12. FHWA COORDINATION

This project is considered to be an Assigned Project in accordance with the current Federal Highway Administration (FHWA) and Department of Transportation (Caltrans) Joint Stewardship and Oversight Agreement.

13. PROJECT REVIEWS

Scoping team field review	Date	<u>4/07/14</u>
Scoping team field review attendance roster attached.		
District Program Advisor	<u>Kelly McClain</u>	Date <u>4/07/14</u>
Headquarters SHOPP Program Advisor	<u>Leo Mahserelli</u>	Date <u>4/07/14</u>
District Maintenance	<u>Tom Barnett</u>	Date <u>2/19/14</u>
Headquarters Design Coordinator		Date _____
Project Manager	<u>Doug Hessing</u>	Date <u>1/28/14</u>
District Environmental	<u>Jason Wilkinson</u>	Date _____
District Safety Review	<u>Scott Morris</u>	Date <u>4/07/14</u>
District Storm Water	<u>Pete Riegelhuth</u>	Date <u>5/30/14</u>
District Traffic Operations	<u>Scott Morris</u>	Date <u>3/06/14</u>
Other		Date _____

14. PROJECT PERSONNEL

Name	Position	Phone Number
Douglas P. Hessing	Project Manager	805-549-3175
Roberto Banda	Design Manager	559-243-3526
Micaela Garcia	Project Engineer	559-243-3523
Matt Fowler	Senior Environmental Planner	805-542-4603
Jason Wilkinson	Environmental Generalist	805-542-4663
Marshall Garcia	Right of Way	805-549-3471

15. ATTACHMENTS (23)

- A. Title Sheet
- B. Typical Cross Sections
- C. Pavement Condition Survey Inventory Data
- D. Environmental Determination/Document
- E. Right of Way Data Sheet
- F. Scoping Team Field Review Attendance Roster
- G. Storm Water Data Report
- H. Transportation Management Plan
- I. Document Distribution List
- J. Risk Register


INDEX OF PLANS

STATE OF CALIFORNIA
 DEPARTMENT OF TRANSPORTATION
 PROJECT PLANS FOR CONSTRUCTION ON
STATE HIGHWAY
 IN SANTA CRUZ COUNTY
 FROM 0.1 MILE NORTH OF SANTAS VILLAGE Rd
 TO SANTA CLARA COUNTY LINE

TO BE SUPPLEMENTED BY STANDARD PLANS DATED 2010



BEGIN CONSTRUCTION
 Sta "A" 10+00 PM 6.0



END CONSTRUCTION
 Sta "A1" 345+84 PM 12.55

SUMMIT RD SEPARATION
 BP No. 37-0343
 PM SCL 0.1

DIR#	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET TOTAL SHEETS
05	SCR	17	6.0/12.55	

LOCATION MAP

DESIGN ENGINEER	ROBERTO BANDA
PROJECT MANAGER	DOUGLAS HESSING

NO SCALE

THE CONTRACTOR SHALL POSSESS THE CLASS (OR CLASSES) OF LICENSE AS SPECIFIED IN THE "NOTICE TO BIDDERS."

CONTRACT No.	05-1F7604
PROJECT ID	0500020286

PLANS APPROVAL DATE _____ DATE _____
 PROJECT ENGINEER _____ REGISTERED CIVIL ENGINEER
 REGISTERED CIVIL ENGINEER

PLANS APPROVAL DATE _____ DATE _____
 PROJECT ENGINEER _____ REGISTERED CIVIL ENGINEER
 REGISTERED CIVIL ENGINEER

THE STATE OF CALIFORNIA OR ITS
 DEPARTMENT OF TRANSPORTATION SHALL NOT BE
 RESPONSIBLE FOR ANY ERRORS OR OMISSIONS OR
 COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.








DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
05	SCR	17	6.0/12.55	2	XXX

REGISTERED CIVIL ENGINEER
 DATE
 PLANS APPROVAL DATE
 THE STATE OF CALIFORNIA OR ITS OFFICERS
 THE AUTHORITY TO COMPLETE THESE DRAWINGS
 COPIES OF THIS PLAN SHEET

ABBREVIATIONS:
 IETW INSIDE EDGE OF TRAVELED WAY
 ISM IMPORTED SUB-BASE MATERIAL
 RHMA-G RUBBERIZED HOT MIX ASPHALT, (GAP GRADED)
 RHMA-O RUBBERIZED HOT MIX ASPHALT, (OPEN GRADED)

PAVEMENT CLIMATE REGION
 CENTRAL COAST

NOTES:
 1. DIMENSIONS OF THE PAVEMENT STRUCTURES (STRUCTURAL SECTIONS) ARE SUBJECT TO TOLERANCES SPECIFIED IN THE STANDARD SPECIFICATIONS.
 2. SUPERELEVATION AS SHOWN OR AS DIRECTED BY THE ENGINEER.
 3. EXACT LOCATIONS AND TYPE OF HMA DIKE, MGS, VEGETATION CONTROL, SHOULDER BACKING AND RUMBLE STRIPS ARE SHOWN ON THE SUMMARY OF QUANTITIES SHEETS.
 4. MAINTAIN SIDE GUTTER



ROUTE 17
 PM 6.7-6.9
 PM 7.3-7.5
 PM 8.6-8.7
 PM 9.0-9.1
 PM 9.4-9.5
 PM 10.6-10.7
 PM 11.3-11.8

ROUTE 17
 PM 6.0-5.7
 PM 6.9-7.0
 *PM 7.0-7.3
 PM 7.5-8.2
 *PM 8.2-8.9
 *PM 9.4-10.5
 *PM 10.6-11.2
 PM 11.7-12.5

EXISTING UTILITY FACILITIES ARE NOT SHOWN ON THE PLANS

RELATIVE BORDER SCALE
 0 1 2 3
 IS IN INCHES

TYPICAL CROSS SECTIONS X-1
 NO SCALE

PROJECT NUMBER & PHASE
 UNIT 1469

05000202861

Caltrans Maintenance Program 2011 Pavement Condition Survey Inventory Caltrans Drive Order

District 5, SCR, Rte 017, PM 6.0 - 12.55

District 5 County SCR Route 017

Begin PM - End PM	Length	LaneMi. (Est.)	Type	AADT (,000)	MSL	Alligator Cracking		Rutting, Bleeding		Slab Cracking		Faulting		Patching		Ride, IRI	Priority	Skid	Defect
						A %	B %	C (Y/N)?	1st %	3rd %	Corner %	Area %	Poor Cond.?	Area %	Poor Cond.?				
5,000	- 6,000	1,000	MLD	57	1	4,000	0	0	0	0	0	0	0	0	0	10	108	99	NO DISTRESS OBSERVED
L1	F-DG	0														5	71	99	NO DISTRESS OBSERVED
L2	F-DG	0														7	96	99	NO DISTRESS OBSERVED
R1	F-DG	0														5	66	99	NO DISTRESS OBSERVED
R2	F-DG	0																	
6,000	- 7,050	1,050	MLD	56	1	4,200	0	0	0	0	0	0	0	0	0	15	126	99	NO DISTRESS OBSERVED
L1	F-DG	0														21	150	32	ALL. A, NO B, OPEN CRKS
L2	F-DG	18														7	96	99	NO DISTRESS OBSERVED
R1	F-DG	0														22	154	99	NO DISTRESS OBSERVED
R2	F-DG	0																	
7,050	- 7,224	0,174	MLD	56	1	0,696	0	0	0	0	0	0	0	0	0	16	131	99	NO DISTRESS OBSERVED
L1	F-DG	0														20	147	7	HIGH ABC
L2	F-DG	12	35													10	105	99	NO DISTRESS OBSERVED
R1	F-DG	0														7	93	99	NO DISTRESS OBSERVED
R2	F-DG	0																	
7,224	- 7,980	0,756	MLD	56	1	3,024	0	0	0	0	0	0	0	0	0	15	124	99	NO DISTRESS OBSERVED
L1	F-DG	0														25	167	7	HIGH ABC
L2	F-DG	12	35													10	106	99	NO DISTRESS OBSERVED
R1	F-DG	0														28	178	5	RIDE
R2	F-DG	0																	
7,980	- 8,000	0,020	MLD	56	1	0,080	0	0	0	0	0	0	0	0	0	N/A	99	99	NO DISTRESS OBSERVED
L1	F-DG	0														N/A	N/A	7	HIGH ABC
L2	F-DG	12	35													N/A	N/A	99	NO DISTRESS OBSERVED
R1	F-DG	0														N/A	N/A	32	NO ALL. A, LOW ALL. B
R2	F-DG	0	2																
8,000	- 9,000	1,000	MLD	56	1	4,000	0	0	0	0	0	0	0	0	0	11	111	99	NO DISTRESS OBSERVED
L1	F-DG	0														20	144	32	ALL. A, NO B, OPEN CRKS
L2	F-DG	2	0													13	117	99	NO DISTRESS OBSERVED
R1	F-DG	0														18	139	32	NO ALL. A, LOW ALL. B
R2	F-DG	0	2																

*Surface type of 'EB' is Enhanced Binder.
 California Department of Transportation, Maintenance Program, Pavement Management Information Branch, Phone (916) 595-4586

Collection Date: 03/08/2013
 Printed: 02/24/2014

Caltrans Maintenance Program 2011 Pavement Condition Survey Inventory Caltrans Drive Order

District 5
 County SCR
 Route 017
 Begin PM 9,000

District 5, SCR, Rte 017, PM 6.0 - 12.55

District 5 County SCR Route 017

Begin PM - End PM	Length	LaneMi. (Est.)	Lane Surface Type	Alligator Cracking		Rutting, Bleeding	Type	AADT (,000)	MSL		Ride, IRI	Priority	Skid	Defect
				A %	B %				Slab Cracking 1st %	3rd %				
9,000 -	0.570	2.280	F-DG	0	0		MLD	56	1		12	115	33	MISC. UNSEALED CRACKS
L1			F-DG	0	0						18	139	33	MISC. UNSEALED CRACKS
L2			F-DG	0	0						13	117	99	NO DISTRESS OBSERVED
R1			F-DG	0	0				9		15	127	32	NO ALL. A, LOW ALL. B
R2			F-DG	0	2									
9,570 -	0.380	1.520	F-DG	0	0		MLD	56	1		5	77	33	MISC. UNSEALED CRACKS
L1			F-DG	0	0						5	85	33	MISC. UNSEALED CRACKS
L2			F-DG	0	0						5	76	99	NO DISTRESS OBSERVED
R1			F-DG	0	0						11	110	99	NO DISTRESS OBSERVED
R2			F-DG	0	0									
9,950 -	10.213	1.052	F-DG	0	0		MLD	56	1		5	73	99	NO DISTRESS OBSERVED
L1			F-DG	0	0						11	110	32	LOW A & B, OPEN CRKS
L2			F-DG	9	2						7	94	99	NO DISTRESS OBSERVED
R1			F-DG	0	0						8	97	99	NO DISTRESS OBSERVED
R2			F-DG	0	0									
10,213 -	11.000	0.787	F-DG	0	0		MLD	56	1		6	89	99	NO DISTRESS OBSERVED
L1			F-DG	0	0						15	127	32	LOW A & B, OPEN CRKS
L2			F-DG	9	2						5	87	99	NO DISTRESS OBSERVED
R1			F-DG	0	0						9	102	99	NO DISTRESS OBSERVED
R2			F-DG	0	0									
11,000 -	11.900	0.900	F-DG	0	0		MLD	56	1		9	101	99	NO DISTRESS OBSERVED
L1			F-DG	0	0						33	195	5	RIDE
L2			F-DG	0	0						14	121	99	NO DISTRESS OBSERVED
R1			F-DG	0	0						22	155	99	NO DISTRESS OBSERVED
R2			F-DG	0	0									
11,900 -	12.000	0.100	F-DG	0	0		MLD	56	1		5	88	99	NO DISTRESS OBSERVED
L1			F-DG	0	0						21	148	99	NO DISTRESS OBSERVED
L2			F-DG	0	0						12	115	99	NO DISTRESS OBSERVED
R1			F-DG	0	0						19	140	99	NO DISTRESS OBSERVED
R2			F-DG	0	0									

*Surface type of 'EB' is Enhanced Binder.
 California Department of Transportation, Maintenance Program, Pavement Management Information Branch, Phone (916) 595-4586

Collection Date: 03/08/2013
 Printed: 02/24/2014

District 5
 County SCR
 Route 017
 Begin PM 12.000

Caltrans Maintenance Program 2011 Pavement Condition Survey Inventory Caltrans Drive Order

District 5, SCR, Rte 017, PM 6.0 - 12.55

District 5 County SCR Route 017

Lane	Surface Type	Alligator Cracking			Length	LaneMi. (Est.)	Rutting, Bleeding	Type	AADT (,000)	MSL	Faulting		Patching Area %	Ride, IRI	Priority	Skid	Defect
		A %	B %	C (Y/N)?							1st %	3rd %					
12.000	-	12.553	0.553	0	2.212	MLD	56	1				8	20	145	33		MISC. UNSEALED CRACKS
L1	F-DG	0	0										20	147	32		ALL. A, NO B, OPEN CRKS
L2	F-DG	14	0										13	117	99		NO DISTRESS OBSERVED
R1	F-DG	0	0										11	111	99		NO DISTRESS OBSERVED
R2	F-DG	0	0														

CATEGORICAL EXEMPTION/CATEGORICAL EXCLUSION DETERMINATION FORM

05 - SCr - 17	6.0 - 12.6	1F760 [0514000051]	N/A
Dist.-Co.-Rte. (or Local Agency)	P.M./P.M.	E.A/Project No.	Federal-Aid Project No. (Local Project)/Project No.

PROJECT DESCRIPTION: (Briefly describe project including need, purpose, location, limits, right-of-way requirements, and activities involved in this box. Use Continuation Sheet, if necessary.)

The purpose of the project is to improve ride quality and extend the service life of the existing pavement. The project proposes to overlay dense grade hot mix asphalt in and near Scott's Valley on Route 17 mainline in Santa Cruz County between post miles 6.0 and 12.6. This project proposes to overlay the existing pavement with 0.20' rubberized asphalt concrete pavement. Where required, up to 3 feet of shoulder backing will be placed, drainage inlets will be raised to grade, dikes will be reconstructed, and non-standard metal beam guard rail will be upgraded. In areas where there is existing concrete barrier in the median, the existing pavement will be cold planed at 0.20' and replaced with 0.20' asphalt concrete pavement. The project is needed to repair deteriorating pavement and poor ride quality.

CEQA COMPLIANCE (for State Projects only)

Based on an examination of this proposal and supporting information, the following statements are true and exceptions do not apply (See 14 CCR 15300 et seq.):

- If this project falls within exempt class 3, 4, 5, 6 or 11, it does not impact an environmental resource of hazardous or critical concern where designated, precisely mapped and officially adopted pursuant to law.
- There will not be a significant cumulative effect by this project and successive projects of the same type in the same place, over time.
- There is not a reasonable possibility that the project will have a significant effect on the environment due to unusual circumstances.
- This project does not damage a scenic resource within an officially designated state scenic highway.
- This project is not located on a site included on any list compiled pursuant to Govt. Code § 65962.5 ("Cortese List").
- This project does not cause a substantial adverse change in the significance of a historical resource.


CALTRANS CEQA DETERMINATION (Check one)

Exempt by Statute. (PRC 21080[b]; 14 CCR 15260 et seq.)

Based on an examination of this proposal, supporting information, and the above statements, the project is:

Categorically Exempt. Class 1. (PRC 21084; 14 CCR 15300 et seq.)

Categorically Exempt. General Rule exemption. [This project does not fall within an exempt class, but it can be seen with certainty that there is no possibility that the activity may have a significant effect on the environment (CCR 15061[b][3].)]

<p>Jason Wilkinson Print Name: Environmental Branch Chief</p> <p> Signature Date: 7/23/14</p>	<p>Doug Hessing Print Name: Project Manager/DLA Engineer</p> <p> Signature Date: 7/24/14</p>
---	---

NEPA COMPLIANCE

In accordance with 23 CFR 771.117, and based on an examination of this proposal and supporting information, the State has determined that this project:



- does not individually or cumulatively have a significant impact on the environment as defined by NEPA and is excluded from the requirements to prepare an Environmental Assessment (EA) or Environmental Impact Statement (EIS), and
- has considered unusual circumstances pursuant to 23 CFR 771.117(b).

CALTRANS NEPA DETERMINATION (Check one)

23 USC 326: The State has determined that this project has no significant impacts on the environment as defined by NEPA, and that there are no unusual circumstances as described in 23 CFR 771.117(b). As such, the project is categorically excluded from the requirements to prepare an environmental assessment or environmental impact statement under the National Environmental Policy Act. The State has been assigned, and hereby certifies that it has carried out the responsibility to make this determination pursuant to Chapter 3 of Title 23, United States Code, Section 326 and a Memorandum of Understanding dated June 07, 2013, executed between the FHWA and the State. The State has determined that the project is a Categorical Exclusion under:

- 23 CFR 771.117(c): activity (c)(___)
- 23 CFR 771.117(d): activity (d)(1)
- Activity ___ listed in Appendix A of the MOU between FHWA and the State

23 USC 327: Based on an examination of this proposal and supporting information, the State has determined that the project is a CE under 23 USC 327.

<p>Jason Wilkinson Print Name: Environmental Branch Chief</p> <p> Signature Date: 7/23/14</p>	<p>Doug Hessing Print Name: Project Manager/DLA Engineer</p> <p> Signature Date: 7/24/14</p>
---	---

Date of Categorical Exclusion Checklist completion: _____ Date of ECR or equivalent: _____

Briefly list environmental commitments on continuation sheet. Reference additional information, as appropriate (e.g., CE checklist, additional studies and design conditions).

CATEGORICAL EXEMPTION/CATEGORICAL EXCLUSION DETERMINATION FORM
Continuation Sheet

05 - Scr - 17	6.0 - 12.6	1F760 [0514000051]	N/A
Dist.-Co.-Rte. (or Local Agency)	P.M./P.M.	E.A/Project No.	Federal-Aid Project No. (Local Project)/Project No.

Continued from page 1:

Biology

In order to avoid impacts to nesting birds, a pre-construction survey shall be conducted by a Caltrans biologist, no more than two weeks prior to vegetation disturbance if vegetation disturbance is scheduled to occur between February 15 and September 1.

Active bird nests shall not be disturbed, and eggs or young birds covered by the Migratory Bird Treaty Act and California Fish and Game Code shall not be killed, destroyed, injured, or harassed at any time. If an active bird nest is found in a tree proposed to be removed or trimmed, Caltrans will coordinate with CDFW to determine an appropriate buffer based on the habits and needs of the species. The nest area would be avoided until the nest is vacated and the juveniles have fledged.

All grindings and asphaltic-concrete waste shall be stored within previously disturbed areas absent of habitat and at a minimum of 150 feet from any culvert, wash, pond, vernal pool, or stream crossing.

The resident engineer or their designee shall be responsible for implementing these conservation measures and shall be the point of contact.

Memorandum**To:** Doug Hessing**Date:** 4/9/2014**Attn:** Roberta Banda**File:** CD 05 EA 1F760K Alt 1
Co SCR RTE 17**From:** Department of Transportation
Division of Right of Way Central Region**DESCRIPTION:**

This CAPM project will perform pavement preservation and repair work to the mainline, ramps, shoulders, and at-grade intersections.

Subject: RIGHT OF WAY DATA SHEET

We have completed an estimate of the right of way costs for the above-referenced project based on the Right of Way Data Sheet Request Form dated 3/14/2014

The following assumptions and limiting conditions were identified:**Appraisal****Utility**

Project Engineer states, in the Right of Way Data Sheet Request Form: 5. Utility permit search completed YES (X), Utility involvement and /or relocation NOT REQUIRED (X), Potholing required YES (X). It is recommended that utility verification plans be provided by design so that utility verifications can be requested from utility owners. Utility verifications will allow for a pothole request to be developed as soon as possible. If relocation is necessary it can take from 9 to 18 months after positive location is finished to develop relocation plans and complete the physical relocation work. Any adjustment of facilities, including adjusting utility covers to grade, constitutes involvement and full R/W Utility process would be necessary before project could be certified. Avoid and protect in place all existing buried and aerial utility facilities in the project area. Comply with USA alert requirements, including at construction sign locations.

Right of Way Lead Time will require a minimum of 18 months after we receive Certified Appraisal Maps and/or Utility Conflict Plans, obtained necessary environmental clearance and applicable freeway agreements have been approved.



JOHN T. MAGORIAN, Sr. Right of Way Agent
San Luis Obispo Field Office
(805) 549-3002

Right Of Way Cost Estimate

	Current Year 2014	Contingency Rate	Right of Way Escalation Rate	Escalated Year 2016
Acquisition:	\$0	25%	5%	\$0
Mitigation:	\$0	25%	5%	\$0
State Share of Utilities:	\$6,250	25%	5%	\$6,891
Expert Witness:	\$0	25%	5%	\$0
Relocation Assistance:	\$0	25%	5%	\$0
Demolition and Clearance:	\$0	25%	5%	\$0
Title and Escrow:	\$0	25%	5%	\$0
Ad Signs:	\$0	25%	5%	\$0
Total Current Value:	\$6,250			\$6,891

If RW Cost Est fields are blank, Costs = \$0

Estimated Construction Contract Work (CCW):

R/W LEAD TIME/Mo. 18

Cost Break Down	
Pot Hole	5,000
Mitigation	
Land	
Bank	
Permit Fees	

RR Involvement

Railroad Facilities or Right of Way Affected?	no
Const/Maint Agreement:	no
Service Contract:	no
Right of Entry:	no
Clauses:	no
Estimated Lead-time	0 mon

Parcel Data

# of Parcel Type X:		
# of Parcel Type A: less than \$10,000 non-complex		
# of Parcel Type B: more than \$10,000 non-complex		
# of Parcel Type C: complex, special valuation		
# of Parcel Type D: most complex and time consuming		# of Duals Needed:
Totals:	0	Totals: 0

of Excess Parcels:

Misc R/W Work

# of RAP Displacements:	0
# of Clearance/Demos:	
# of Const Permits:	
# of Condemnations:	

Utilities

U4-1: Owner Expense	
U4-2: State Expense, Conventional no Fed Aid	10
U4-3: State Expense, Freeway no Fed Aid	
U4-4: State Expense, both with Fed Aid	
U5-7: Utility verification, no relocation/potholing	
U5-8: Utility verification, w/ some relocation/potholing	
U5-9: Utility verifications, relocation/potholing required	10

Parcel Area

Total R/W Required:

Total Excess Area:

General Description of R/W and Excess Lands Required (zoning, use, major improvements, critical or sensitive parcels, etc.):

General Description of Utility Involvement:

SR 17 is designated conventional highway throughout the project area. Generally utility company facilities would be in place by encroachment permit and relocation would be at company expense.

Is there a significant effect on assessed valuation: No

Were any previously unidentified sites with hazardous waste or material found: No

Are RAP displacements required: No

# of single family:	# of multi-family:	# of business/nonprofit:	# of farms:
---------------------	--------------------	--------------------------	-------------

Sufficient replacement housing will be available without last resort housing:

Are material borrow or disposal sites required: No

Are there potential relinquishments or abandonments: No

Are there any existing or potential airspace sites: No

Are environmental mitigation parcels required: No

Data for evaluation provided by:


Estimator:

Railroad Liaison Agent: sah 3/26/2014

Utility Relocation Coordinator: John T. Magorian 3/18/2014

I have personally reviewed this Right of Way Sheet and all supporting information. I find this Data Sheet complete and current, subject to the limiting conditions set forth.

Date
ENTERED PMCS 4/9/2014
BY: Rodney Tabarez


JOHN T. MAGORIAN
Sr. Right of Way Agent, Right of Way



Dist-County-Route: 05-SCR-17
 Post Mile Limits: 6.0/12.55
 Project Type: Santa Cruz CAPM
 Project ID (or EA): 05-1400-0051-K (05-1F760K)
 Program Identification: (SHOPP) 2.XX. 201-121
 Phase: PID
 PA/ED
 PS&E

Regional Water Quality Control Board(s): Central Coast, Region 3

- 1. Is the project required to consider incorporating Treatment BMPs? Yes No
- 2. Does the project disturb 5 or more acres of soil? Yes No
- 3. Does the project disturb more than 1 acre of soil and not qualify for the Rainfall Erosivity Waiver? Yes No
- 4. Does the project potentially create permanent water quality impacts? Yes No
- 5. Does the project require a notification of ADL reuse Yes No

If the answer to any of the preceding questions is "Yes", prepare a Long Form – Storm Water Data Report.

Estimate Construction Start Date: January 1, 2019 Construction Completion Date: August 1, 2019
 Separate Dewatering Permit (if yes, permit number) Yes Permit # _____ No
 Erosivity Waiver Yes Date: _____ No

This Short Form – Storm Water Data Report has been prepared under the direction of the following Licensed Person. The Licensed Person attests to the technical information contained herein and the data upon which recommendations, conclusions, and decisions are based. Professional Engineer or Landscape Architect stamp required at PS&E.

Gilberto Baca 5/30/2014
 Gilberto Baca, Registered Project Engineer Date
 I have reviewed the stormwater quality design issues and find this report to be complete, current and accurate:

(Stamp Required for PS&E only) *FOR Andrew Pochwatka* 5/30/2014
 Andrew Pochwatka, Regional SW Coordinator or Designee Date

CENTRAL REGION PROJECT REPORT DISTRIBUTION LIST

Division / Program / Office	Project Type	D5	
FHWA	<u>Designated high profile projects only. Refer to Stewardship Agreement</u>	Dominic Hoang	1
HQ Division of Design	All Projects	<u>Design Report Routing</u>	1
HQ Division of Engineering Serv	All Projects	Division of Engineering Services (electronic copy OK)	1
HQ Environmental	All Projects	Bob Pavlik	1
HQ Maintenance	HA22	Leo Mahserelli	1
HQ SHOPP Program Advisor	For other prog	<u>HQ Advisors List</u>	
Project Manager	All Projects	Project Manager	1
Design Manager	All Projects	Design Manager	2
Resident Engineer	All Projects	Resident Engineer	1
District Maintenance	All Projects	Lance Gorman	1
	SHOPP	Kelly McClain	1
District Traffic Management	All Projects	Jacques Van Zeventer	1
District Traffic Operations	All Projects	Paul McClintic	1
District Traffic Safety	SCr	Scott Morris	1
Region Materials	All Projects	Glenn Johnson	1
Region Environmental	All Projects	Susan Schilder	1
Region Traffic Design	All Projects	Mohammed Qatami	1
Region Landscape	All Projects	Dennis Reeve	1
Region Right of Way	All Projects	Patrick Mason	1
District Planning	All Projects	Claudia Espino	1
PPM	All Projects	Linda Araujo	1
Surveys	All Projects	Jeremy Villegas	1
	Mon/SC/SBt	Bob Fredricks	1
HQ DES/OPPM	Proj w/Structures	Andrew T S Tan	1
District Records	All Projects	Pat Duty (electronic copy only)	0
TOTAL COPIES			District 5 = 24

STATE OF CALIFORNIA • DEPARTMENT OF TRANSPORTATION
RISK REGISTER CERTIFICATION (ACCOUNTABILITY CHECKPOINTS) FORM
 PPM-0001 (REV 07/2013)

The risk register is to be approved and signed-off by the District Deputies* listed below for all scalability levels. By signing this form, you are certifying that you have reviewed the risks documented in the register and agree that they have been managed to the extent possible by the PDT.

Project Information: Capital Project Major Maintenance Project (Check One) Total Estimated Cost: \$ _____

Project ID/District-EA: 0514000051/05-1F760

Project Description: Pavement Preservation/N Route 17 CAPM

Project Manager (PM): DOUG HESSING

Project Risk Manager (For Risk Level 3 Projects): _____

No Risk Register Certification Required -- Check box if project is less than \$1 million in total cost and risk register not prepared. Sign below and submit this form with PID, PA&ED, PS&E submittal, and RE Handoff File (as applicable).

Project Manager Signature: _____ Date: _____

PA&ED (Required for Capital Projects Only)

DOUG HESSING
Project Manager *Doug Hessing* Date: 12-9-14

For CHRISTINE COX-KOVACEVICH
Chief, Central Region Environmental *Christine Cox-Kovacevich* Date: 12-4-14

BRIAN EVERSON
Chief, Central Region Project Development *Brian Everson* Date: 12/5/14

SARA VON SCHWIND
Deputy District Director, Program/Project Management *Sara von Schwind* Date: 12.15.14

Prior to PS&E (Required for Capital Projects and Major Maintenance Projects)

DOUG HESSING
Project Manager _____ Date: _____

BRIAN EVERSON
*Chief, Central Region Project Development _____ Date: _____

MARK DER MATOIAN
Chief, Central Region Construction _____ Date: _____

JAIME LUPO
Acting Chief, Central Region Right of Way _____ Date: _____

CHRISTINE COX-KOVACEVICH
**Chief, Central Region Environmental _____ Date: _____

SARA VON SCHWIND
Deputy District Director, Program/Project Management _____ Date: _____

*or Deputy District Director, Maintenance & Operations signature for HM Projects designed by the District Maintenance Division
 **or Deputy District Director, Transportation Planning signature for HM Projects environmentally cleared by the District Environmental Stewardship Branch

PROJECT RISK MANAGEMENT PLAN

Dist - E.A		Co-Rte-PM			Project Name				Project Manager		Telephone Number		Date	Version/Draft			
05-1F760_		SCr-17-PM 6.0/12.55			Santa Cruz 17 North CAPM				Doug Hessing		(805) 549-3386		12/4/2014	PID			
PROJECT RISK MANAGEMENT PLAN																	
Priority	Identification					Qualitative Analysis				OPTIONAL Quantitative Analysis			Risk Response Plan		Monitoring and Control		
	Status	ID #	Date Identified Project Phase	Functional Assignment	Threat/Opportunity Event	Risk Trigger	Type	Probability	Impact	Risk Matrix	Probability (%)	Impact (\$ or days)	Effect (\$ or days)	Strategy	Response Actions including advantages and disadvantages	Responsibility (Risk Manager)	Last date changes made to risk and Comments
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(14) = (12)x(13)	(15)	(16)	(17)	(18)
Active	1	8/8/2014	PID	Environmental	Sensitive species mitigation required	Sensitive species found in or near project limits	Schedule	Low	Moderate		30%			Avoidance	Permits and Mitigation could be required	Matt Fowler	This could even require a higher level document- If work will occur that results in impacts (take) to listed species or unanticipated impacts to jurisdictional waters during construction, additional coordination on the project will be required between the ECL and biologist and Construction, resulting in negative impacts to the project scope. A substantial amount of additional ECL hours will be required to support Activity 270.
Active	2	8/8/2014	PID	Design	Project scope changes requiring additional site reviews	Scope changes requiring additional site reviews	Schedule	Low	Moderate		30%			Avoidance	develop appropriate scope during the PID phase.	Jason Wilkinson	If project scope changes requiring additional site reviews, additional hours will be required, negatively impacting the project scope and possibly schedule. Additional hours will possibly be required for Activity's 205, 255., and 280
Active	3	8/8/2014	PID	Design	Work that requires surveys is identified.	Work that requires surveys is identified.	Schedule	Low	Moderate		30%			Acceptance	If surveys are required hours will be added to the workplan and a PCR may need to be processed to allow the work	Roberto Banda/Jennifer Wilson	If surveys are required and the support work pushes or may push the 1 phase or 3 phase support budget a PCR may be required prior to completing the work. This could result in an impact to both schedule and budget.
Active	4	10/30/2014	PID	Design	During monitoring of PS&E phase expenditures and percent complete, the estimate to complete exceeds the baseline programmed amount.	The estimate to complete exceeds the base line programmed amount.	Schedule	Moderate	Moderate		50%			Acceptance	Task Managers must monitor their tasks and identify any potential overruns prior to overrunning the budget. If an overrun is anticipated a PCR can be processed to change the programmed amount prior to overrunning the budget and prior to the RTL year.	Roberto Banda	Task Managers and Supervisors need to monitor the hours staff spends on the project and insure they are appropriate and planned in the project. Cost overruns must be identified prior to exceeding the budget and prior to the delivery year (RTL Year).
Active	5	10/30/2014	PID	Construction	Construction phase overrun over 120% prior to the close out of the project.	The estimate to complete exceeds the base line programmed amount.	Quality	Moderate	High		50%			Avoidance	Construction phase resources will be reevaluated at the 95% CR stage and a PCR processed prior to the CTC vote of the request for funds if needed.	Jennifer Wilson	Task managers and supervisors need to monitor the hours staff spends on the project and insure they are appropriate and planned in the project. Cost overruns must be identified prior to exceeding the budget and corrective action identified.
Active	6	11/30/2014	PID	Design	Increase in construction capital due to increase in hot mix asphalt prices	Construction estimate becomes larger than the programmed amount.	Cost	Moderate	Moderate		50%			Acceptance	The hot mix asphalt price should be checked prior to the RTL year so a PCR can be processed to increase the programmed amount if the capital estimate is higher than the programmed amount.	Roberto Banda	12/4/2014