



EAST SONORA

State Route 108 Bypass

INFORMATION SHEET

State Route 108 E. Sonora Bypass, Stage II Project

September, 2011

Project Purpose: The purpose of the project is to reduce local traffic congestion in East Sonora and for inter-regional traffic on State Route 108.

Project Background: Stage I of the East Sonora Bypass was completed in 2002 from the Sanguinetti Overhead to 0.3 mile west of Peaceful Oak Road (Post Mile R1.9/R4.0). Stage II would construct a 2-lane expressway from 0.3 miles west of Peaceful Oak Road to just west of Via Este Road (Post Mile R4.0/R6.0). Stage III would complete construction of the 2-lane expressway on a new alignment to the existing 4-lane section of Highway 108 near Sunshine Road (Post Mile R6.9).

Project Description: Stage II of the East Sonora Bypass proposes to construct a 2-lane expressway from 0.3 miles west of Peaceful Oak Road to Via Este Road (PM R4.0/R6.0). The scope of work includes a partial interchange at Peaceful Oak Road, a grade separation at Mono Way (existing Highway 108, PM R5.1) and a temporary at-grade "T" intersection connecting Mono Way to the new expressway at PM R5.6. The 2-lane expressway would continue as a temporary connection and merges with the existing Highway 108 near Via Este Road (PM R6.0). A frontage road connecting existing Highway 108 with both Seaborn Road and Waif-Mine Road would also be constructed to provide access to parcels that would be cut-off by the new alignment. The future Stage III of the bypass would remove the temporary connection (PM R5.6/R6.0) and a grade separation would replace the Mono Way temporary intersection (PM R5.6). Stage III would complete construction of the 2-lane expressway on the new alignment to the existing 4-lane section of Highway 108 near Sunshine Road (PM R6.9).

Cost: Approximately \$65,920,000.

Funding Source: Corridor Mobility Improvement Account (CMIA), Regional Improvement Program (RIP), and Interregional Improvement Program (IIP).

Project Timeline:
HQ Final Design for Stage II - January, 2010
Ready to List - May, 2010
Received Project Funding Approval - January, 2011
Project Advertised for Construction - August, 2011
Award Construction Contract - November, 2011
Begin Construction - Spring, 2012
Completion of Construction - June, 2014

For more information, please contact:

Joy Pinne, Project Manager, at (209) 948-7854, or e-mail at joy_pinne@dot.ca.gov.