

Memorandum

*Flex your power!
Be energy efficient!*

To: MR. DAVE KLEIN
Engineering Services
Office of Structure Office Engineer

Date: September 30, 2008

File: 11-Sd-15-KP 44.67
11-2T0811
9th Ave. UC (Widen)
Br. No. 57-0808R/L

From: DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
Geotechnical Services
Office of Geotechnical Design South 2

Subject: Addendum to the Foundation Report

The Division of Bridge Design, Bridge Design Branch 14, had requested a final foundation report for widening of the Ninth Avenue Undercrossing on Interstate Route 15 located in Escondido in San Diego County. This is an Addendum to the Foundation Report dated July 26, 2007. A construction note was added dated October 3, 2007. The purpose of the addendum is to clarify the construction note involving CIDH piles to be constructed on 2.5B (the maximum diameter of the piles) center-to-center spacing, as requested by the Designer. All other aspects of the July 26, 2007 Foundation Report are still applicable.

When CIDH piles are to be constructed at a center-to-center spacing of 2.5B, the following construction consideration is to be required:

Within a support location, no piles shall be constructed (e.g. drilled or concrete poured) immediately adjacent to recently constructed CIDH piles until the adjacent (recently constructed) CIDH piles have cured for a minimum period of 48 hours.


KLEIN
9/30/08
Page 2

9th Ave. UC Widen
57-0808R/L
11-2T0811

If you have any questions or need additional information, please call Bill Levine at 916-227-0505 or Angel Perez-Cobo at 916-227-7167.



Bill Levine
Engineering Geologist
Geotechnical Design-South 2
Design Branch A



Angel Perez-Cobo
Senior Engineer
Geotechnical Design-South 2
Design Branch A

cc: APerez-Cobo
R.E. Pending File
Specs & Estimates
Proj Mgmt
BLevine
File

