

El Dorado 50, Segment 2 – Lake Tahoe Airport to US 50/SR 89 Junction Water Quality Improvement Project

EL DORADO COUNTY, CALIFORNIA
DISTRICT 3 – ED – 50 PM 73.7 / 75.4
03-1A7320

Initial Study with Proposed Negative Declaration



November 2007

Prepared by the
State of California Department of Transportation



GENERAL INFORMATION ABOUT THIS DOCUMENT

What's in this document:

The California Department of Transportation (Caltrans) has prepared this Initial Study (IS), which examines the potential environmental impacts of a project to improve water quality runoff along the segment of U.S. Highway 50 (US 50) from the Lake Tahoe Airport to the "Y" junction of US 50 and State Route 89 (SR 89) in the City of South Lake Tahoe, California. The document describes why the project is being proposed, alternatives for the project, the existing environment that could be affected by the project, the potential impacts from each of the alternatives, and the proposed avoidance, minimization and/or mitigation measures.

What you should do:

- Please read this Initial Study. Additional copies of this document as well as the technical studies are available for review at the Caltrans North Region Office of Environmental Management, 2800 Gateway Oaks Drive, Sacramento, CA 95833.
- We welcome your comments regarding the proposed project. Please send written comments via postal mail to Jody L. Brown, Chief, Environmental Branch, Attention: Christopher Carlton, Caltrans District 3, 2800 Gateway Oaks Drive, Sacramento, CA 95833. Comments can be submitted via e-mail to christopher_carlton@dot.ca.gov.
- Submit comments by the deadline: December 12, 2007.

What happens next?

After comments are received from the public and reviewing agencies, Caltrans and FHWA may: (1) give environmental approval to the proposed project, (2) undertake additional environmental studies, or (3) abandon the project. If the project is given environmental approval and funding is appropriated, the Department could design and construct all or part of the project.

For individuals with sensory disabilities, this document can be made available in Braille, in large print, on audiocassette, or on computer disk. To obtain a copy in one of these alternate formats, please call or write to Caltrans, attn: Christopher Carlton, Office of Environmental Management, 2800 Gateway Oaks Dr., Sacramento, CA 95833; (916) 263-5911 Voice, or use the California Relay Service TTY number, 1 (800) 735-2929.


In El Dorado County, California,
On U.S. Highway 50 (US 50) from the Lake Tahoe Airport (PM 73.7) to the "Y" junction of US 50 and State
Route (SR) 89 in the City of South Lake Tahoe (PM 75.4)

INITIAL STUDY with PROPOSED NEGATIVE DECLARATION

Submitted Pursuant to: Division 13, California Public Resources Code

THE STATE OF CALIFORNIA
Department of Transportation

November 9 2007
Date of Approval


John D. Webb, Chief
Office of Environmental Services - South
California Department of Transportation

Proposed Negative Declaration (ND)

Project Description

The California Department of Transportation (Caltrans) proposes to improve the quality of storm water runoff for the segment of United States Highway 50 (US 50) between the Lake Tahoe Airport and the “Y” junction of US 50 and State Route (SR) 89 in the City of South Lake Tahoe, California. The project will involve installing slope stability and protection measures and installing drainage facilities to collect, treat, and direct storm water runoff from the highway. The project is needed to meet National Pollutant Discharge Elimination System (NPDES) permit requirements and address planned water quality improvements that are part of the Lake Tahoe Basin Environmental Improvement Program (EIP).

Determination

This proposed Negative Declaration (ND) is included to give notice to interested agencies and the public that it is Caltrans’ intent to adopt an ND for this project. This does not mean that Caltrans’ decision regarding the project is final. This ND is subject to modification based on comments received by interested agencies and the public.

Caltrans has prepared an Initial Study for this project, and pending public review, expects to determine from this study that the proposed project would not have a significant effect on the environment for the following reasons:

The proposed project would have no effect on land use, growth, population and housing, recreation, relocations, farmland, airport or air traffic patterns, energy, cultural resources, floodplains, wild or scenic rivers, Coastal Zones, mineral resources, or climate change.

In addition, the proposed project would have no adverse effect on public services, utilities, transportation and traffic, visual resources, hydrology, water quality, geology and soils, hazardous waste, air quality, noise, or biological resources.

John D. Webb, Chief
Office of Environmental Services - South
California Department of Transportation

Date

Summary

The California Department of Transportation (Caltrans), in conjunction with the Federal Highway Administration (FHWA), proposes to provide containment and/or treatment of storm water runoff on United States Highway 50 (US 50) from the Lake Tahoe Airport to the “Y” junction of US 50 and State Route 89 (SR 89) in the City of South Lake Tahoe, California. This project is one of eight similar improvements proposed on segments of US 50 and SR 89 in the Lake Tahoe Basin (three on US 50 and five on SR 89). Each proposed project within these segments would have logical termini and independent utility, and would likely be individually funded and constructed over a number of years. This Initial Study (IS) addresses Segment 2 of US 50 (Lake Tahoe Airport to the US 50/SR 89 junction).

The proposed project will implement water quality improvement measures to comply with National Pollutant Discharge Elimination System (NPDES) permit requirements and address planned water quality improvements identified in the Lake Tahoe Basin Environmental Improvement Program (EIP) and the Lahontan Regional Water Quality Control Board’s (LRWQCB’s) 1995 *Water Quality Control Plan for the Lahontan Region, North and South Basins* (Basin Plan). Both plans require retrofitting the state highway system to stabilize eroding slopes and meet specific storm water collection, treatment, and transport standards by 2008. The project would be constructed seasonally over a multiyear period.

Caltrans is the lead agency for the project, pursuant to the California Environmental Quality Act (CEQA). As of July 2007, Caltrans has been delegated the responsibility for certain reviews and approvals formerly performed by the FHWA, including the approval of Categorical Exclusions in accordance with the National Environmental Policy Act (NEPA). If it is determined that the project would have no significant adverse environmental impacts, Caltrans will approve a Negative Declaration under CEQA and a Categorical Exclusion under NEPA.

S.1 Purpose and Need

The purpose of the proposed project is to implement NPDES permit requirements and water quality elements of the Lake Tahoe Basin EIP that relate to Segment 2 of US 50.

The NPDES requirements arise from goals and objectives to improve the quality of water at Lake Tahoe. The Tahoe Regional Planning Agency (TRPA) is responsible in part for attaining and maintaining established environmental threshold carrying

capacities that protect the unique values of the Lake Tahoe Basin, including water quality, wildlife, vegetation, soil conservation, fisheries, noise, recreation, air quality, transportation, historic resources, scenic resources, and community design. The TRPA's goals are implemented through its Code of Ordinances, which regulates all proposed projects and activities within the Lake Tahoe Basin. In addition, a 1997 federal agency partnership with California and Nevada, TRPA, and the Washoe Tribal Government affirmed a commitment to manage and protect the Lake's natural resources, achieve environmental thresholds, and adopt and fund the EIP. The EIP contains specific projects, including many that involve California highways in the Lake Tahoe Basin.

Caltrans was issued a Statewide NPDES Permit from the State Water Resources Control Board (SWRCB) in 1999. The Statewide Permit requires that storm water/urban runoff collection, treatment, and/or infiltration disposal facilities be designed, installed, and maintained for the discharge of storm water runoff from all impervious surfaces generated by the 20-year, 1-hour design storm within the Lake Tahoe Hydrologic Unit. According to the permit, all Caltrans facilities within the Lake Tahoe Hydrologic Unit must be retrofitted to comply with this requirement by 2008. The permit also incorporates provisions of the Basin Plan. The Basin Plan contains requirements that apply to Caltrans highways and projects, including effluent limitations for storm water discharges (i.e., storm water and snowmelt runoff from the state's highways). Essentially, all storm water runoff from Caltrans highways must be managed within the state rights-of-way or, if infeasible, treated to meet applicable standards and effluent limitations contained in the Basin Plan unless the LRWQCB approves alternative mitigation.

S.2 Alternatives

Within the proposed limits on US 50, the project would construct various water quality and drainage improvements designed to site-specific conditions (e.g., soil, drainage, and topography) and right-of-way availability, while avoiding or minimizing environmental impacts along Segment 2 of US 50. These would include the following:

- The existing roadway drainage system will be enhanced by adding Portland Cement Concrete (PCC) or Asphalt Concrete (AC) curbs and gutters at the edges of shoulders and rehabilitating and constructing new drainage inlets and culverts. These features will convey runoff to underground sand collection vaults, sand collection traps, infiltration basins, and meandering ditches for treatment.

- With concurrence from LRWQCB and TRPA, spreading of runoff will be proposed where feasible in Stream Environment Zone (SEZ) areas. Sheet flow will be enhanced in areas where it is determined to provide better runoff treatment than drainage collection facilities.
- Maintenance pullouts will be constructed at sand collection vaults where feasible.
- Existing shoulders will be spot widened where necessary for water conveyance facilities.
- Drainage outfalls will be reconstructed to reduce erosion and convey runoff.
- Erosion control measures will be incorporated on all eroding slopes within the state right-of-way. To provide additional water quality improvements, unvegetated dirt areas adjacent to the shoulder will be landscaped to promote vegetation growth and discourage vehicles from entering. Erodible slopes will also be flattened and protected. Rock slope protection will be used where appropriate.
- A uniform depth AC overlay will be placed over the existing pavement. Failed pavement sections will be dug out and replaced.
- Sand traps and sand vaults will be installed within the project limits.

Only minor right-of-way acquisitions or easements will be necessary to construct the project. Driveways for private residences or commercial buildings may need to be modified during construction. These driveway modifications would require coordination with the affected property owners if a change in property access could occur. If driveway modifications require work outside of the state right-of-way, Permits to Enter would be required. The project's purpose is to improve the quality of storm water runoff and will not change the existing highway alignment, expand capacity, or add travel or bicycle lanes. Construction is anticipated to require two to three seasons to complete. Construction will require temporary reduction in lane widths and possible periodic lane closures and traffic delays. Following construction, and between seasons of construction, erosion control and slope stability measures will be applied.

The No Build Alternative would not construct the proposed improvements and would not comply with the NPDES permit or implement the elements of the EIP. Caltrans is required to comply with the NPDES permit issued by the SWRCB and could be in violation of permit requirements if the proposed project were not constructed.

S.3 Permits and Approvals Needed

In addition to NEPA and CEQA compliance, the project is subject to other federal, state, and local laws, policies, and guidelines that are addressed in this IS. Applicable regulatory consultation or approvals may be needed from the following agencies:

- U.S. Army Corps of Engineers (USACE) – Nationwide Permit authorization
- State Historic Preservation Officer (SHPO) – Concurrence on finding that the project does not affect historic resources and Section 106 requirements are satisfied
- California Department of Fish and Game (CDFG) – Streambed Alteration Agreement permit
- Lahontan Regional Water Quality Control Board (LRWQCB) – Section 401 Certification/NPDES; potential exemption to the Basin Plan, which prohibits disturbance in a Stream Environment Zone
- TRPA
- City of South Lake Tahoe (encroachment permit)
- El Dorado County (encroachment permit)

This IS addresses the proposed project’s potential to have adverse impacts on the environment. Potential impacts and mitigation/minimization measures are summarized in Table S-1.

Table S-1 Summary of Impacts and Avoidance, Minimization, and Mitigation Measures

Potential Impact	Impact Summary	Avoidance/Minimization/Mitigation
Land Use	<ul style="list-style-type: none"> Residents and businesses of the South Lake Tahoe area and travelers on US 50 could experience temporary effects from construction-related disruptions and delays. The project includes minimal new impervious surfaces that may not be exempt from TRPA Bailey land coverage limits. Final surface area coverage will be defined and provided to TRPA to determine Coverage Verification. 	<ul style="list-style-type: none"> Traffic management measures (see TT-1).
Community Impacts	<ul style="list-style-type: none"> Construction and maintenance of infiltration basins and other facilities will require minor acquisition of property or easements. Compensation for any property acquisition would be based on fair market value. Intermittent traffic delays could affect community institutions such as schools and local agencies. Construction near properties, driveways, and access roads could cause temporary, minor disruptions to residents, owners, or occupants. 	<ul style="list-style-type: none"> CI-1: Potentially affected individuals and institutions in the local area will be notified and informed of project scheduling/activities. A public involvement plan will be developed. CI-2: Access to properties, driveways, or access roads along US 50 will be maintained during construction.
Utilities/Emergency Services	<ul style="list-style-type: none"> Relocation of some utilities may be required for construction of proposed facilities. Access to US 50 for the South Lake Tahoe Fire Department and the Lake Valley Fire Protection District and Forest Service will be maintained during construction. Emergency vehicles, including fire, police, and ambulance, will be provided access through construction zones. 	<ul style="list-style-type: none"> UE-1: Any need for utility relocation will be identified during final project design. If a need to relocate utilities is identified, Caltrans will coordinate these activities with the utility service providers. No further mitigation required for emergency services.
Traffic and Transportation	<ul style="list-style-type: none"> Traffic flow and access to existing parcels will not be permanently impacted by this project, but may be affected temporarily during construction. There is a potential for construction delays to interfere with through traffic and scheduled Lake Tahoe Unified School District and BlueGO transit service in the project area. The project will not change bicycle access/use on US 50, except for intermittent delays during construction. 	<ul style="list-style-type: none"> TT-1: Traffic management during construction will include development of lane closure plans, and provide information and notice of construction activities that may impede traffic or access.

Table S-1 Summary of Impacts and Avoidance, Minimization, and Mitigation Measures (continued)

Potential Impact	Impact Summary	Avoidance/Minimization/Mitigation
Visual/Aesthetics	<ul style="list-style-type: none"> • Infiltration basins will require some tree removal. • Drainage maintenance pullouts may require cut and fill, ground disturbance, and vegetation removal. • Sand traps and vaults will be added, but these features are mostly underground and should not be readily visible. • New rock slope protection at culvert outlets and new curbs and gutters may initially contrast with surroundings. • • Minor cut and fill will be required for spot shoulder widening. • Trees will be removed to accommodate project features; removal will comply with TRPA requirements. 	<ul style="list-style-type: none"> • VA-1: Measures will be implemented for specific project features, including design of infiltration basins to minimize tree removal; revegetation of rock slope protection; and coloration of sand traps, sand vaults, and curbs to match surroundings. • VA-2: General design measures will be implemented including temporary and permanent erosion control measures. • VA-3: Project improvements will consider TRPA scenic thresholds and incorporate design elements or improvements that do not degrade current values.
Cultural Resources	<ul style="list-style-type: none"> • Archaeological resources have the potential to be affected by the proposed project. With the implementation of avoidance measures, no impacts are anticipated. 	<ul style="list-style-type: none"> • CR-1: If cultural resources are identified during construction activities, all work will stop until a qualified archaeologist can assess the discovery. • CR-2: If human remains are discovered, activities shall cease and the County Coroner contacted will be contacted. The Native American Heritage Commission will be contacted if appropriate.
Hydrology and Floodplains	<ul style="list-style-type: none"> • The project is within Federal Emergency Management Agency (FEMA) zones designated as having minimal flood hazard but would not alter the floodplain or flows. 	<ul style="list-style-type: none"> • No additional avoidance measures are necessary.
Water Quality and Storm Water Runoff	<ul style="list-style-type: none"> • Vegetation clearing and construction work will increase risk of erosion and sedimentation during and for a short time following construction. • Proposed project features will have a beneficial long-term effect by improving the quality of runoff leaving the state right-of-way. 	<ul style="list-style-type: none"> • WS-1: Erosion control and pollution prevention measures will be incorporated into the project. • WS-2: If construction encounters groundwater or may involve non-storm water discharges, consultation with the LRWQCB or California Department of Toxic Substances Control may be appropriate.

Table S-1 Summary of Impacts and Avoidance, Minimization, and Mitigation Measures (continued)

Potential Impact	Impact Summary	Avoidance/Minimization/Mitigation
Soils, Soils Conservation, Geology, and Seismicity	<ul style="list-style-type: none"> • New drainage features will create additional hard coverage. • Construction of certain project features on unstable soils or steep slopes could increase the potential for erosion and slope instability. 	<ul style="list-style-type: none"> • SC-1: Caltrans would purchase land coverage credits pursuant to the TRPA Code of Ordinances. • SC-2: Proposed structures could require geotechnical investigation if they are located on potentially unstable soils and could present landslide, rockfall, liquefaction, or erosion hazards.
Hazardous Waste and Materials	<ul style="list-style-type: none"> • Aerially deposited lead (ADL) may be present in roadside soils. • Construction activity in proximity to potential contamination sites may encounter contaminated soil or groundwater. • Thermoplastic roadway striping may contain hazardous materials. 	<ul style="list-style-type: none"> • HZ-1: A version of the Caltrans Non Standard Special Provisions (N-SSP #07-330) may apply to handling of ADL soils, but requires verification. • HZ-2: If any soil disturbance activities are planned adjacent to potentially contaminated site, investigation may be required to determine if contamination is present. • HZ-3: Any removal of yellow thermoplastic lane striping must be performed in accordance with a Lead Compliance Plan and disposed of in an appropriate landfill.
Air Quality	<ul style="list-style-type: none"> • Dust and particulate emissions would temporarily increase during construction, and construction equipment would generate diesel emissions. 	<ul style="list-style-type: none"> • AQ-1: Dust control practices will be required of the contractor. • AQ-2: Measures can be implemented to reduce emissions from construction equipment.
Noise	<ul style="list-style-type: none"> • Project construction activities could intermittently exceed City of South Lake Tahoe and TRPA noise threshold levels. Project construction is exempt from the South Lake Tahoe and TRPA Noise Ordinance if construction activities occur between the daytime hours of 8:00 a.m. and 6:30 p.m. The contractor will be restricted to these time periods unless a variance to this ordinance is obtained. 	<ul style="list-style-type: none"> • NO-1: Caltrans Standard Specifications Section 7-1.011 and other construction noise measures to limit exposure and noise generation will be followed.
Natural Communities	<ul style="list-style-type: none"> • No sensitive natural communities exist within the ESL. Therefore, no project-related impacts are anticipated. 	<ul style="list-style-type: none"> • No additional avoidance measures are necessary.

Table S-1 Summary of Impacts and Avoidance, Minimization, and Mitigation Measures (continued)

Potential Impact	Impact Summary	Avoidance/Minimization/Mitigation
<p>Wetlands and Waters of the United States, and Stream Environment Zones</p>	<ul style="list-style-type: none"> • Approximately 0.01 acre of wetlands could be permanently affected by construction of proposed cut and fill slopes, basins, and pullouts. • A total of <0.06 acre of potentially jurisdictional wetlands and other waters of the U.S. would be permanently affected by proposed construction activities. • A total of 0.16 acre of SEZs within the ESL would be permanently affected by basin construction. 	<ul style="list-style-type: none"> • WE-1: Impacts to wetlands, other waters of the U.S., and SEZs will be mitigated on-site if possible. Detailed wetland mitigation plans will be developed in consultation with the USACE. • WE-2: General avoidance/minimization measures and best management practices (BMPs; see Section 2.15.4) will be implemented, including establishing ESA boundaries, providing erosion control, and limiting vegetation removal.
<p>Special-Status Plant Species</p>	<ul style="list-style-type: none"> • No sensitive plant species were found within the ESL during the biological field surveys. No direct or indirect effects are expected. 	<ul style="list-style-type: none"> • No additional avoidance measures are necessary.

Table S-1 Summary of Impacts and Avoidance, Minimization, and Mitigation Measures (concluded)

Potential Impact	Impact Summary	Avoidance/Minimization/Mitigation
<p>Special-Status Animal Species</p>	<ul style="list-style-type: none"> • Marginal foraging habitat exists within the ESL. However, effects to wildlife habitat will be avoided or minimized. 	<ul style="list-style-type: none"> • AN-1: Preconstruction surveys will be conducted in the ESL to verify that nesting is still absent for northern goshawk, blue grouse, waterfowl, and peregrine falcon. Active nesting would require construction restrictions during nesting season. TRPA and Forest Service annual survey data will be reviewed for new occurrence data. • AN-2 and AN-3: General avoidance/minimization measures and BMPs (see Section 2.17.4) will be implemented to avoid potential effects to avian species and mammals, respectively. • AN-4: Preconstruction surveys for Sierra Nevada snowshoe hare will be conducted in riparian areas where nest depressions may be within the ESL. Where nest depressions are identified, construction within 250 feet will be prohibited from February 1 to July 1 and restricted to daylight hours.
<p>Threatened and Endangered Species</p>	<ul style="list-style-type: none"> • Potentially suitable habitat for Sierra Nevada red fox, a state-listed threatened species, exists within the project area. Caltrans has determined that the species is not present in the project area. 	<ul style="list-style-type: none"> • TE-1: Preconstruction surveys will verify absence of Sierra Nevada red fox in the ESL. If active dens are found, a 250-foot buffer will be imposed, and construction will be prohibited from February 1 to May 31.
<p>Invasive Species</p>	<ul style="list-style-type: none"> • No established infestation of noxious weeds was detected in the project ESL. 	<ul style="list-style-type: none"> • General avoidance/minimization measures and BMPs HA-03 (Construction Equipment Weed Control) and HA-05 (Weed-Free Erosion Control Seed Mix/Stock) (see Section 2.20) will be required to avoid potential infestation of noxious weed material to the project site.

Table of Contents

Cover Sheet	i
Proposed Negative Declaration (ND)	iii
Summary	v
Table of Contents	xv
List of Figures	xviii
List of Tables	xix
List of Acronyms and Abbreviations	xx
Chapter 1. Proposed Project	1-1
1.1. Location and Route Description	1-1
1.2. Project Purpose	1-2
1.3. Need for the Proposed Improvements	1-2
1.3.1. Background	1-2
1.3.2. Tahoe Regional Planning Agency	1-2
1.3.3. Executive Order and State and Regional Commitments	1-7
1.3.4. National Pollutant Discharge Elimination System Permit Requirements	1-7
1.4. Proposed Build Alternative	1-8
1.4.1. Description	1-8
1.5. No Build Alternative	1-10
1.6. Alternatives Considered but Eliminated from Further Discussion	1-11
1.7. Permits and Approvals Needed	1-11
Chapter 2. Affected Environment, Environmental Consequences, and Avoidance, Minimization, and/or Mitigation Measures	2-1
Human Environment	2-2
2.1. Land Use	2-2
2.1.1. Affected Environment	2-2
2.1.2. Impacts	2-5
2.1.3. Avoidance, Minimization and/or Mitigation Measures	2-6
2.2. Community Impacts	2-6
2.2.1. Regulatory Setting	2-6
2.2.2. Affected Environment	2-7
2.2.3. Impacts	2-7
2.2.4. Avoidance, Minimization and/or Mitigation Measures	2-8
2.3. Utilities/Emergency Services	2-8
2.3.1. Affected Environment	2-8
2.3.2. Impacts	2-9
2.3.3. Avoidance, Minimization and/or Mitigation Measures	2-9
2.4. Traffic and Transportation Facilities	2-10
2.4.1. Regulatory Setting	2-10
2.4.2. Affected Environment	2-10
2.4.3. Impacts	2-11
2.4.4. Avoidance, Minimization and/or Mitigation Measures	2-13
2.5. Visual and Aesthetics	2-14
2.5.1. Regulatory Setting	2-14
2.5.2. Affected Environment	2-15
2.5.3. Impacts	2-17
2.5.4. Avoidance, Minimization and/or Mitigation Measures	2-20
2.6. Cultural Resources	2-22
2.6.1. Regulatory Setting	2-22

2.6.2.	Affected Environment	2-23
2.6.3.	Impacts	2-27
2.6.4.	Avoidance, Minimization and/or Mitigation Measures.....	2-27
Physical Environment.....		2-28
2.7.	Hydrology and Floodplains	2-28
2.7.1.	Regulatory Setting.....	2-28
2.7.2.	Affected Environment	2-28
2.7.3.	Impacts	2-29
2.8.	Water Quality and Storm Water Runoff.....	2-29
2.8.1.	Regulatory Setting.....	2-29
2.8.2.	Affected Environment	2-32
2.8.3.	Impacts	2-35
2.8.4.	Avoidance, Minimization and/or Mitigation Measures.....	2-38
2.9.	Soils, Soil Conservation, and Geology.....	2-39
2.9.1.	Regulatory Setting.....	2-39
2.9.2.	Affected Environment	2-40
2.9.3.	Impacts	2-41
2.9.4.	Avoidance, Minimization and/or Mitigation Measures.....	2-42
2.10.	Hazardous Waste / Materials.....	2-43
2.10.1.	Regulatory Setting.....	2-43
2.10.2.	Affected Environment	2-44
2.10.3.	Impacts	2-44
2.10.4.	Avoidance, Minimization and/or Mitigation Measures.....	2-45
2.11.	Air Quality.....	2-45
2.11.1.	Regulatory Setting.....	2-45
2.11.2.	Affected Environment	2-46
2.11.3.	Impacts	2-48
2.11.4.	Avoidance, Minimization and/or Mitigation Measures.....	2-49
2.12.	Climate Change	2-50
2.12.1.	Regulatory Setting.....	2-50
2.12.2.	Affected Environment	2-51
2.12.3.	Conclusion.....	2-51
2.13.	Noise	2-52
2.13.1.	Regulatory Setting.....	2-52
2.13.2.	Affected Environment	2-53
2.13.3.	Impacts	2-54
2.13.4.	Avoidance, Minimization and/ or Mitigation Measures.....	2-57
Biological Environment		2-58
2.14.	Natural Communities	2-58
2.14.1.	Regulatory Setting.....	2-58
2.14.2.	Affected Environment	2-59
2.14.3.	Impacts	2-59
2.14.4.	Avoidance, Minimization and/or Mitigation Measures.....	2-59
2.15.	Wetlands and Other Waters of the U.S., and Stream Environment Zones.....	2-59
2.15.1.	Regulatory Setting.....	2-59
2.15.2.	Affected Environment	2-61
2.15.3.	Impacts	2-62
2.15.4.	Avoidance, Minimization and/or Mitigation Measures.....	2-62
2.16.	Plant Species	2-63
2.16.1.	Regulatory Setting.....	2-63
2.16.2.	Affected Environment	2-64

2.16.3. Impacts.....	2-65
2.16.4. Avoidance, Minimization and/or Mitigation Measures	2-65
2.17. Animal Species	2-65
2.17.1. Regulatory Setting	2-65
2.17.2. Affected Environment	2-67
2.17.3. Impacts.....	2-70
2.17.4. Avoidance, Minimization and/or Mitigation Measures	2-71
2.18. Threatened and Endangered Species	2-73
2.18.1. Regulatory Setting	2-73
2.18.2. Affected Environment	2-74
2.18.3. Impacts.....	2-74
2.18.4. Avoidance, Minimization and/or Mitigation Measures	2-75
2.19. Invasive Species.....	2-75
2.19.1. Regulatory Setting	2-75
2.19.2. Affected Environment	2-76
2.19.3. Impacts.....	2-76
2.19.4. Avoidance, Minimization or Mitigation Measures	2-76
2.20. Avoidance, Minimization, and Mitigation Measures for Biological Resources	2-76
2.21. Vector Control	2-80
Cumulative Impacts	2-80
2.22. Cumulative Impacts of Proposed Project and Other Future Actions	2-80
2.22.1. Regulatory Setting	2-80
2.22.2. Affected Environment	2-81
2.22.3. Impacts.....	2-85
2.22.4. Avoidance, Minimization, and Mitigation Measures	2-88
Chapter 3. Comments and Coordination.....	3-1
3.1. Consultation and Coordination Performed for the Program EIR.....	3-1
3.2. Public Participation and Coordination.....	3-2
Chapter 4. List of Preparers	4-1
Chapter 5. Distribution List	5-1
Chapter 6. References	6-1
Chapter 7. List of Technical Studies	7-1
Appendix A Project Plans	A-1
Appendix B CEQA Checklist	B-1
Appendix C Tahoe Regional Planning Agency Initial Environmental Checklist.....	C-1
Appendix D Glossary of Technical Terms.....	D-1
Appendix E Title VI Policy Statement	E-1
Appendix F U.S. Fish and Wildlife Service Species List.....	F-1
Appendix G Avoidance and/or Minimization Summary	G-1

List of Figures

Figure 1-1	Vicinity Map	1-3
Figure 1-2	Project Study Area	1-5
Figure 2.8-1	Water Bodies Near US 50 Segment 2	2-33

List of Tables

Table S-1	Summary of Impacts and Avoidance, Minimization, and Mitigation Measures.....	ix
Table 2.6-1	Resources Located within the APEs.....	2-25
Table 2.10-1	Potential Contamination Sites within the US 50 Segment 2 Project Limits.....	2-44
Table 2.11-1	Federal and California Ambient Air Quality Standards	2-47
Table 2.13-1	Typical Daytime Noise Levels Estimated from Average Daily Traffic	2-54
Table 2.13-2	Typical Noise Levels in the Environment	2-54
Table 2.13-3	Typical Ranges of Energy Equivalent Noise Levels at 50 Feet, in dBA Leq, at Construction Sites.....	2-55
Table 2.13-4	Maximum Noise Levels from Construction Equipment at 50 Feet	2-56
Table 2.20-1	General Avoidance and Minimization Measures, and Best Management Practices	2-77
Table 2.22-1	Planned Caltrans EIP Projects, 2005–2012	2-82
Table 2.22-2	Approved and Proposed Projects in South Lake Tahoe	2-84
Table 2.22-3	EIP Projects Beneficial to Wildlife and Fisheries Resources in the South Lake Tahoe Area	2-87

List of Acronyms and Abbreviations

208 Plan	<i>Water Quality Management Plan for the Lake Tahoe Region</i> (TRPA 1988)
AADT	average annual daily traffic
AC	Asphalt Concrete
ADL	aerially deposited lead
Basin Plan	<i>Water Quality Control Plan for the Lahontan Region, North and South Basin</i> (LRWQCB 1995)
BMP	best management practice
Caltrans	California Department of Transportation
CARB	California Air Resources Board
CDFG	California Department of Fish and Game
CEQA	California Environmental Quality Act
CESA	California Endangered Species Act
CFR	Code of Federal Regulations
CGS	California Geologic Survey
CNDDB	California Natural Diversity Data Base
CNEL	Community Noise Equivalent Level
CNPS	California Native Plant Society
CO	carbon monoxide
CRHR	California Register of Historical Resources
CWA	Clean Water Act
dBA	A-weighted decibel
EIP	(Lake Tahoe Basin) Environmental Improvement Program
EIR	Environmental Impact Report
ESA	environmentally sensitive area
FESA	Federal Endangered Species Act
FHWA	Federal Highway Administration
Forest Service	(U.S. Department of Agriculture) Forest Service
L_{eq}	average A-weighted decibel level during a measurement period
L_{max}	maximum noise level during a measurement period
LRWQCB	Lahontan Regional Water Quality Control Board
LTBMU	(U.S. Department of Agriculture Forest Service) Lake Tahoe Basin Management Unit
LTHU	Lake Tahoe Hydrologic Unit
LTUSD	Lake Tahoe Unified School District
MCE	maximum credible earthquake
mg/L	milligram(s) per liter
MOU	Memorandum of Understanding
NAHC	Native American Heritage Commission
NEPA	National Environmental Policy Act
NO ₂	nitrogen dioxide

NO _x	oxides of nitrogen
NPDES	National Pollutant Discharge Elimination System
N-SSP	Caltrans Non Standard Special Provisions
NTU	Nephelometric Turbidity Units
O ₃	ozone
PAS	Plan Area Statement
Pb	lead
PCC	Portland Concrete Cement
PM	post mile
PM _{2.5}	particulate matter less than 2.5 microns in diameter
PM ₁₀	particulate matter less than 10 microns in diameter
ppm	part(s) per million
PSR	Project Study Report
ROG	reactive organic gas
RWQCB	Regional Water Quality Control Board
SEZ	stream environment zone
SHPO	State Historic Preservation Officer
SO ₂	sulfur dioxide
SR 89	State Route 89
Statewide Permit	Caltrans National Pollutant Discharge Elimination System Permit Order No. 99-06-DWQ, No. CAS000003
SWPPP	Storm Water Pollution Prevention Plan
SWRCB	State Water Resources Control Board
TMDL	total maximum daily load
TMP	Traffic Management Plan
TRPA	Tahoe Regional Planning Agency
US 50	U.S. Highway 50
USACE	U.S. Army Corps of Engineers
USC	U.S. Code
USDA	U.S. Department of Agriculture
USEPA	U.S. Environmental Protection Agency
USFWS	U.S. Fish and Wildlife Service
USGS	U.S. Geological Survey
V:H	vertical to horizontal
VMT	vehicle miles traveled
“Y”	Intersection of US 50 and SR 89 in South Lake Tahoe

Chapter 1. Proposed Project

The California Department of Transportation (Caltrans) proposes to improve the quality of storm water runoff for a segment of United States Route 50 (US 50) in the Lake Tahoe Basin. The El Dorado 50, Segment 2 – Lake Tahoe Airport to US 50/SR 89 Junction Water Quality Improvement Project (the project) will involve installing slope stability and protection measures, and installing facilities to collect and direct storm water runoff from the state highway and right-of-way. The project is needed to meet National Pollutant Discharge Elimination System (NPDES) permit requirements and to address planned improvements and changes that are part of the Lake Tahoe Basin Environmental Improvement Program (EIP). Figure 1-1 shows the project vicinity.

Caltrans is the lead agency for the project, pursuant to the California Environmental Quality Act (CEQA). As of July 2007, Caltrans has been delegated the responsibility for certain reviews and approvals formerly performed by the FHWA, including the approval of Categorical Exclusions in accordance with the National Environmental Policy Act (NEPA). If it is determined that the project would have no significant adverse environmental impacts, Caltrans will approve a Negative Declaration under CEQA and a Categorical Exclusion under NEPA.

1.1. Location and Route Description

The project is located in El Dorado County approximately 1.5 miles south of Lake Tahoe. The proposed project limits extend for approximately 1.7 miles along US 50 from the Lake Tahoe Airport to the “Y” junction of US 50 and SR 89 in the City of South Lake Tahoe, California (Figure 1-2). The project limits are within the City of South Lake Tahoe except for approximately 0.25 mile at the southern limit, which is an unincorporated area. This segment of US 50 is relatively flat. Lands along this segment are primarily divided into individual private parcels, both developed and undeveloped. The Lake Tahoe Airport is adjacent to this segment on the east.

The proposed project is one of eight segments of US 50 and SR 89 in El Dorado County where similar water quality improvements are proposed. This project is also referred to as “US 50 Segment 2.”

1.2. Project Purpose

The purpose of the project is to implement NPDES requirements and water quality elements of the Lake Tahoe Basin EIP that relate to US 50 between the Lake Tahoe Airport and the “Y” junction of US 50 and SR 89 in the City of South Lake Tahoe. In meeting this purpose, the project will apply current roadway design standards where feasible.

1.3. Need for the Proposed Improvements

1.3.1. Background


The Lake Tahoe Basin EIP, approved in 1998, included elements that would improve the quality of storm water runoff to Lake Tahoe. The Lake Tahoe region has experienced environmental degradation for the past 100 years, most notably in the lake’s water clarity and the health of the basin’s forestlands. The lake’s clarity, which reflects water quality, has become the primary measure of the basin’s environmental health and has steadily declined over the past several decades.

The objective of the Lake Tahoe Basin EIP is to achieve the environmental threshold carrying capacities required by Public Law 96-551 and adopted for the Tahoe Region in 1982 by the Tahoe Regional Planning Agency (TRPA).

Both the EIP and the Lahontan Regional Water Quality Control Board’s (LRWQCB’s) 1995 *Water Quality Control Plan for the Lahontan Region, North and South Basins* (Basin Plan), as referenced in Caltrans’ Statewide NPDES Permit, are linked in time and purpose in the area of water quality. Both require retrofitting the state highway system to stabilize eroding slopes and meet specific storm water collection, treatment, and transport standards by 2008.

1.3.2. Tahoe Regional Planning Agency

The TRPA was created with the authority to plan, oversee, and regulate development within the bi-state Tahoe region, which includes the state highways. Environmental threshold carrying capacities were established for Lake Tahoe by Public Law 96-551 and adopted for the Lake Tahoe Region in 1982. The Tahoe Regional Planning Compact charges TRPA with attaining and maintaining these environmental threshold carrying capacities to protect the unique values of the Lake Tahoe Basin. The nine categories of environmental thresholds are as follows:



URS Corporation L:\Projects\Caltrans_TO47_Tahoe_Segment_2\IMXD\Current Working Documents\Study_Map_Figure_1.mxd cxbente061207





U.S. Highway 50 - Segment 2
ED-50 PM 73.7/75.4

Lake Tahoe Basin - TO 47

Study Vicinity Map

Figure
1-1



U.S. Highway 50 - Segment 2
ED-50 PM 73.7/75.4
Lake Tahoe Basin - TO 47

Figure 1-2:
Project Study Area

- Water Quality
- Wildlife
- Vegetation
- Soil Conservation
- Fisheries
- Noise
- Recreation
- Air Quality/Transportation
- Scenic Resources/Community Design

The TRPA's *Regional Plan for the Lake Tahoe Basin: Goals and Policies* (TRPA 2004) establishes the overall approach to meeting the threshold standards. Various elements of the Regional Plan address specific environmental and planning topics, and TRPA's Plan Area Statements and Community Plans identify goals for specific land use areas throughout the Tahoe Basin. The plans and policies are ultimately implemented through the TRPA Code of Ordinances, which regulates all proposed projects and activities.

1.3.3. Executive Order and State and Regional Commitments

Presidential Executive Order 13057, issued on July 26, 1997, declared the Lake Tahoe Region an area of national environmental concern. Executive Order 13057 created a federal partnership of five cabinet-level agency secretaries and called for a Memorandum of Agreement between the federal partnership, the States of California and Nevada, the TRPA, and the Washoe Tribal Government to facilitate coordination and cooperation. The Memorandum of Agreement was subsequently signed by the Governor of California, and it affirmed a commitment to manage and protect Lake Tahoe's natural resources; to achieve and maintain the previous environmental thresholds; and to adopt, fund, and implement the EIP. The \$908 million EIP was adopted by TRPA in February 1998. Continued state funding for the EIP since 1999 reaffirms California's commitment to protecting and restoring the environmental quality of Lake Tahoe.

The EIP identifies restoration, capital improvement, and operational modification work in eight of the nine environmental threshold areas. Approximately 83 EIP projects involve California highways in the Tahoe Basin. Caltrans has capital funding involvement with approximately 28 highway projects and is the lead agency for 20 projects, including proposed water quality improvements on US 50.

1.3.4. National Pollutant Discharge Elimination System Permit Requirements

In 1987, the Clean Water Act (CWA) was amended to include Section 402(p), which established a framework for regulating municipal and industrial storm water discharges under the NPDES. Caltrans was issued a Statewide NPDES Permit (Order No. 99-06-

DWQ, NPDES No. CAS000003; Statewide Permit) from the State Water Resources Control Board (SWRCB) on July 15, 1999. The Statewide Permit incorporates the provisions of the Basin Plan, which contains additional requirements that have historically applied to Caltrans permits. The Basin Plan includes numerical effluent limitations for storm water discharges within the Lake Tahoe Hydrologic Unit (LTHU).

The Statewide Permit requires storm water/urban runoff collection, treatment, and/or infiltration disposal facilities to be designed, installed, and maintained for the discharge of storm water runoff from all impervious surfaces generated by the 20-year, 1-hour design storm within the LTHU. All Caltrans facilities within the LTHU must be retrofitted to comply with this requirement by 2008. If site conditions do not allow for adequate on-site disposal, all site runoff must be treated to meet applicable effluent limits and/or receiving water limitations specified in the Basin Plan. The Regional Water Quality Control Board Executive Officer may approve alternative mitigation measures.

Caltrans developed and the SWRCB approved a Storm Water Management Plan that identifies appropriate best management practices (BMPs) to be implemented on projects as site conditions allow. The *Storm Water Quality Handbook: Project Planning and Design Guide* (Caltrans 2007a) was developed to give additional guidance to designers in considering and implementing these BMPs on all projects. The project would improve storm water quality by implementing source control and treatment BMPs as approved in the *Storm Water Quality Handbook*. Source controls include, but are not limited to, preservation of existing vegetation, use of flow conveyance systems, and slope/surface protection systems (vegetated and hard surfaces). Treatment controls to be considered include, but are not limited to, infiltration basins, and sand traps and vaults. Additional drainage systems will be constructed as part of the project to augment these BMPs.

This section describes the proposed project and the No Build Alternative.

1.4. Proposed Build Alternative

1.4.1. Description

The intent of the project is to treat or otherwise improve the quality of storm water runoff that drains from the state right-of-way. To achieve this, the project would construct various water quality and drainage improvements designed to site-specific conditions (e.g., soil, drainage, and topography) and right-of-way availability, while avoiding or minimizing environmental impacts along US 50 Segment 2. The proposed improvements, shown in the maps in Appendix A, consist of the following:

- The existing roadway drainage system will be enhanced by adding Portland Cement Concrete (PCC) or Asphalt Concrete (AC) curbs and gutters at the edges of shoulders and rehabilitating and constructing new drainage inlets and culverts. These features will convey runoff to underground sand collection vaults, sand collection traps, infiltration basins, and meandering ditches for treatment.¹
- With concurrence from LRWQCB and TRPA, spreading of runoff will be proposed where feasible in Stream Environment Zone (SEZ) areas. Sheet flow will be enhanced in areas where it is determined to provide better runoff treatment than drainage collection facilities.
- Maintenance pullouts will be constructed at sand collection vaults where feasible.
- Existing shoulders will be spot widened where necessary for water conveyance facilities.
- Drainage outfalls will be reconstructed to reduce erosion and convey runoff.
- Erosion control measures will be incorporated on all eroding slopes within the state right-of-way. To provide additional water quality improvements, unvegetated dirt areas adjacent to the shoulder will be landscaped to promote vegetation growth and discourage vehicles from entering. Erodible slopes will also be flattened and protected. Rock slope protection will be used where appropriate.
- A uniform depth AC overlay will be placed over the existing pavement. Failed pavement sections will be dug out and replaced.
- Sand traps and sand vaults will be installed within the project limits.

Most of the improvements can be installed within the existing state right-of-way. Some proposed facilities, such as the new infiltration basins, might require minor acquisition of property or easements to construct and maintain. The project does not involve realignment, expansion, or changes to the existing highway travel lanes other than to accommodate the construction of the proposed water quality improvements.

Construction work will be completed seasonally. The project may require two to three seasons to complete. Periodically, construction may require lane closures to accommodate sufficient and safe work areas. These closures will result in temporary traffic delays, although emergency response vehicles will always have priority access through the work area. Following construction, and between seasons of construction, erosion control and slope stability measures will be applied.

¹ **Sand collection vaults and traps** temporarily detain runoff and capture sand that was applied to icy or snowy roadways to provide traction (Caltrans 2007c). **Infiltration basins** are excavated shallow basins that capture and detain rainfall and snowmelt runoff to remove particles and pollutants before the runoff infiltrates into the ground below.

Utility relocations may be required for construction of the proposed facilities. This may include relocation of above- or below-ground utilities outside of a widened right-of-way.

The proposed Build Alternative was developed by a multidisciplinary team involved in many steps of design and environmental review. A conceptual set of improvements was first identified in 2003 for the Project Study Report (PSR; Caltrans 2003a) and was evaluated for environmental considerations both in the PSR and in a Draft Program Environmental Impact Report (Draft Program EIR; Caltrans 2007b). Some of the proposed improvements were subsequently relocated or eliminated based on design or environmental considerations, such as where proposed drainage features or construction areas might adversely affect biological or known cultural resources. The resulting changes to the design that were incorporated into the proposed Build Alternative avoid nearly all impacts to sensitive resources along this segment. The proposed project will therefore improve the quality of storm water runoff along US 50 while avoiding any substantial environmental or community impacts. No other alternatives were identified that achieve the purpose of the project with minimal impact.

After the public circulation period, all comments will be considered, and Caltrans will make the final determination of the project's effect on the environment.

1.5. No Build Alternative

The No Build Alternative would consist of not implementing the proposed project. Caltrans is required to comply with the Statewide NPDES Permit issued by SWCRB and could be in violation of the requirements of this permit if the proposed project were not constructed.

The No Build Alternative could result in a failure to meet TRPA environmental thresholds for water quality designated in the EIP. This alternative would not address the environmental problems facing the Lake Tahoe Basin, and therefore is not considered a viable alternative.

The No Build Alternative would have a lesser amount of temporary impacts to water resources compared to construction of the proposed project; however, the No Build Alternative would result in a greater amount of water quality deterioration over the long term compared to the proposed project.

1.6. Alternatives Considered but Eliminated from Further Discussion

Although no formal alternatives other than the proposed Build Alternative have been developed, several considerations have been made about the placement of water quality improvement features throughout the project limits. Many potential locations for infiltration basins have been rejected due to topography, soil properties, possible conflict with SEZs or wetlands, conflict with utilities, or presence of cultural resources.

Basin locations were selected based on the following criteria:

- At or near the discharge point of runoff from state right-of-way
- Downgradient from the discharge point of runoff from state right-of-way
- Flat or gently sloping topography
- Undeveloped
- Not in an obvious SEZ
- Not in a floodplain
- Accessible by construction and maintenance equipment
- Greater than 100 feet upgradient or 10 feet downgradient of structural foundations
- Not above a known underground hazardous waste plume

The proposed improvements are also based on recent research and testing of a range of technologies and treatment measures that could be implemented along the state highways to comply with project requirements. Pilot facilities for runoff treatment have been designed and implemented in the Tahoe Basin and elsewhere in California, and development and testing are still under way. The *Storm Water Quality Handbooks: Project Planning and Design Guide* (Caltrans 2007a) identifies BMPs that are approved for implementation, and new technologies and treatments are being developed and tested through pilot programs. The proposed improvements are limited to approved BMPs, but new technologies will be considered if they are approved for implementation within the time frame of development of the project.

1.7. Permits and Approvals Needed

Permits would be required from local, state, and federal agencies depending on the jurisdiction of each agency. The following agencies may require permits for approval or review:

Agency	Permit/Approval	Status
U.S. Army Corps of Engineers (USACE)	<ul style="list-style-type: none"> • Section 404 permit. 	<ul style="list-style-type: none"> • Draft wetland delineation completed and will be provided to USACE for review/verification. • Permit application will be submitted during final design phase.
State Historic Preservation Officer (SHPO)	<ul style="list-style-type: none"> • Section 106 National Historic Preservation Act Consultation. 	<ul style="list-style-type: none"> • Records review and resource inventory completed. • SHPO concurrence with findings of eligibility and avoidance.
California Department of Fish and Game (CDFG)	<ul style="list-style-type: none"> • Section 1602 Permit/Streambed Alteration. 	<ul style="list-style-type: none"> • Permit application will be submitted during final design phase.
LRWQCB	<ul style="list-style-type: none"> • Section 401 Certification/NPDES. • May require an exemption to the Basin Plan, which prohibits disturbance in an SEZ. 	<ul style="list-style-type: none"> • Permit application will be submitted during final design phase. • Application for exemption, if needed, will be submitted during final design phase.
TRPA	<ul style="list-style-type: none"> • Permit. 	<ul style="list-style-type: none"> • Permit application will be submitted during final design phase.
City of South Lake Tahoe	<ul style="list-style-type: none"> • Encroachment permit. 	<ul style="list-style-type: none"> • Permit application will be submitted during final design phase.
El Dorado County	<ul style="list-style-type: none"> • Encroachment permit. 	<ul style="list-style-type: none"> • Permit application will be submitted during final design phase.

Chapter 2. Affected Environment, Environmental Consequences, and Avoidance, Minimization, and/or Mitigation Measures

This section evaluates the environmental resource areas potentially affected by the proposed project and presents measures to avoid or minimize those impacts. The environmental resource discussions presented in this chapter are based on the technical studies cited at the beginning of each discussion and listed in Chapter 7. Avoidance and minimization measures are summarized in Appendix G. The technical studies are available for review at the Caltrans North Region Office of Environmental Management, 2800 Gateway Oaks Drive, Sacramento, California, 95833, and at the District 3 Office, 703 B Street, Marysville, California, 95901.

As part of the scoping and environmental analysis for the project, the following environmental issues were considered but no adverse impacts were identified. Consequently, these issues are not discussed further.

- **Growth:** The proposed project is limited to improvements necessary to meet NPDES permit requirements and elements of the Lake Tahoe Basin EIP that relate to this segment of US 50. No changes would be made to the highway that could affect through-traffic or change access to any land or parcels. These actions would not create additional infrastructure or change highway levels of service, and therefore would not change or induce growth or development. None of the improvements proposed would remove any existing barriers to growth. As a result, the project would have no impact on growth.
- **Energy:** Permanent traffic conditions will not be affected by the project, as there will be no changes in capacity, operation, or circulation. Consequently, there would be no change in the consumption of energy with or without the project. Temporary construction may result in some traffic delays and increased inefficiency but the effect is considered minor in terms of overall energy consumption.
- **Relocation:** No housing units or commercial businesses would be acquired or relocated as a result of this project.
- The project does not occur within or adjacent to the following land uses or resources: farmland, a wild or scenic river, the state Coastal Zone, or an area of

known or important mineral resources. Therefore, the project would have no effect on these resources.

Human Environment

Sections 2.1 through 2.4 present the existing conditions; potential impacts from the proposed project; and avoidance, minimization, and/or mitigation measures related to land use, the community, emergency services, and traffic in the project vicinity. The following discussions are based on the Community Impact Assessment prepared for this project.

The regional study area for community impacts is the South Lake Tahoe Census County Division, which encompasses the residential and commercial areas along US 50 within the project limits in South Lake Tahoe. This division includes the year 2000 Census Tract 304.02.

Direct project effects have the potential to occur within the existing state right-of-way. Direct effects may also occur in construction easements and locations where minor acquisition of parcels or portions of parcels may be needed for proposed drainage improvements that extend outside of the existing right-of-way.

2.1. Land Use

2.1.1. Affected Environment

2.1.1.1. Existing and Future Land Use

The northern portion of the project limits around the “Y” junction of US 50 and SR 89 includes a mixture of commercial, tourist, residential, institutional, and public service uses. The area adjacent to and south of the “Y” is primarily residential, with single-family and multi-family housing, a large trailer park, and minimal commercial use. According to TRPA planning documents, both the commercial district at the “Y” junction and the adjacent area to the south are at approximately 80 percent build-out.

The southern portion of the project limits includes the Lake Tahoe Airport, a concrete batch plant, old borrow areas, and miscellaneous commercial uses. This area is proposed for rehabilitation to provide compatible commercial and city administrative uses as defined in the Lake Tahoe Airport layout plan. The airport will continue to provide commercial and general aviation service in accordance with adopted goals, policies, and environmental constraints.

There are no State Park lands within the project limits.

2.1.1.2. Consistency with Federal, State, Regional and Local Plans

This segment of US 50 is within the Tahoe Valley unit of the Forest Service's Lake Tahoe Basin Management Unit (LTBMU). A resource management emphasis for this unit included in the *Land and Resource Management Plan* (Forest Service 1988) is on meeting the recreation and scenic use demands of the resident and visiting population of the area. Along US 50, there is an emphasis on maintaining a scenic travel corridor. The TRPA's *Regional Plan for the Lake Tahoe Basin* (TRPA 1987) identifies environmental threshold carrying capacities to protect and enhance the quality of Lake Tahoe and other natural resources in the region. A key goal of the plan is to reduce sediment, nutrient, and other pollution into Lake Tahoe from surface runoff and other sources to maintain and improve the water quality of the lake and its contributing rivers and streams.

The TRPA has defined Plan Area Statements (PASs) throughout the Tahoe Basin that describe each planning area, include planning statements and considerations, and list special policies and details about permitted uses. The following summarizes the four planning areas crossed by the project and the permissible transportation uses identified in each area's PAS:

- The South "Y" Plan area (PAS #110) is the commercial and public service area around the US 50/SR 89 intersection in the City of South Lake Tahoe. It includes two special sub-areas that distinguish alternate allowed uses. Special Area #1 is proposed as the preferred area for industrial uses. Special Area #2 is proposed as the preferred area for multi-family residential, professional offices, and hospital-related uses. The South "Y" Plan supports the continued function as a regional commercial area but should be improved for more efficient use. Transportation routes are listed as a permissible use. The TRPA recommends the creation of a community plan as the preferred method of guiding new development.
- The Bonanza Plan area (PAS #114) is north of the Lake Tahoe Airport and includes land west of US 50 and a portion of US 50 itself. The land use classification for the Bonanza Plan is residential. The area includes single-family residences, apartments, and a large trailer park. The PAS includes Special Areas #1 and #3, each of which has specific permissible uses. The PAS notes that the US 50 corridor in this Plan Area is in need of restoration. Transportation routes are listed as a permissible use in PAS #114.

- The Airport Plan area (PAS #116) is located between Meyers and South Lake Tahoe along US 50. The area contains the Lake Tahoe Airport, a small single-runway airport, as well as an adjacent portion of US 50. The Airport Plan classifies land use within the area as commercial/public service. Transportation routes are considered a permissible use, and the area is considered a multimodal transportation node.
- The Country Club Meadow Plan area (PAS #119) follows the Upper Truckee River from a point near the airport to the bridge at the Echo Summit grade. The land use classification of PAS #119 is recreation. Transportation routes, including transit stations and terminals, are permissible under the provisions for a special use.

In addition, two TRPA thresholds apply to recreation:

- R1: It shall be the policy of the TRPA governing body in development of the regional plan to preserve and enhance the high-quality recreational experience, including preservation of high-quality undeveloped shore zone and other natural areas. In developing the regional plan, the staff and governing body shall consider provisions for additional access, where lawful and feasible, to the shore zone and high-quality undeveloped areas for low-density recreational uses.
- R2: It shall be the policy of the TRPA governing body in development of the regional plan to establish and ensure a fair share of the total basin capacity for outdoor recreation is available to the general public.

The City of South Lake Tahoe, through its General Plan, has adopted the TRPA PASs in lieu of traditional zoning (City of South Lake Tahoe 2003). Where there is a conflict between the General Plan and a TRPA PAS, the most restrictive applies, which in the majority of cases is the PAS. The following primary areas of the General Plan would apply to the project:

- Land use policies, which are guided by the TRPA PASs
- Improvement of water quality of Lake Tahoe
- Noise thresholds, which are guided by the TRPA PASs.

2.1.1.3. Park and Recreation Uses

The economic base of the Lake Tahoe region is tourism and recreation. US 50 is an important regional transportation corridor linking many communities and services that are outside of the project area, including the City of South Lake Tahoe;

recreational uses in El Dorado County; the casinos in Stateline (Douglas County, Nevada); camping, hiking, and cross-country skiing along the shoreline; and the Toiyabe National Forest.

2.1.2. Impacts

US 50 is a main thoroughfare for the residents and businesses of the South Lake Tahoe area, as well as the regional access road for destinations south and north of the area. The proposed project would have no permanent effects on land use planning or the City of South Lake Tahoe. Residents and businesses of the South Lake Tahoe area and travelers on US 50 could experience temporary effects from construction-related disruptions and delays.

Long-Range Planning

The project is consistent with the LTBMU *Land and Resource Management Plan*, TPRA *Regional Plan for the Lake Tahoe Basin*, and City of South Lake Tahoe General Plan. These plans share the common goal of water quality protection and improvement in the Lake Tahoe Basin. The project will include measures outlined in Section 2.5.4 to avoid or minimize effects to the scenic qualities along this corridor. No long-range planning impacts would occur.

Economic Conditions

Commercial development exists along US 50 within the project limits. Access to public services and businesses in the project area may be temporarily compromised due to construction-related activities. However, as construction activities proceed along the highway, any single location within the project segment will only be affected for a limited amount of time. Traffic access through the planned construction areas, though potentially periodically delayed, will remain available.

Recreation Use

No trailhead or camping access is provided along US 50 Segment 2, therefore the project would not affect those recreation uses. Two bicycle trails cross US 50 within Segment 2; however, access to these bicycle trails will be maintained during construction. Motorists traveling to ski resorts and casinos at Stateline may experience temporary effects from construction-related traffic delays.

TRPA Considerations

Consistency with Local and Regional Plans

No inconsistencies with long-range TRPA land use plans are identified. The project will not affect the amount of housing or the need for future housing in the Tahoe

Region, impact any schools, or result in the need for changed or new government services.

The project does not conflict with the four TRPA PASs that cross or are adjacent to US 50 within the project limits, and would not expand or intensify any existing non-conforming use. The South “Y,” Bonanza, Airport, and Country Club Meadows PASs identify transportation routes as permissible uses, and this project will have no effect on this current designation. This water quality improvement project will not change the location or capacity of the highway.

The project will not result in a decrease or loss of high-quality natural areas for outdoor recreation or access to those areas. Therefore, the project is consistent with TRPA Thresholds R1 and R2.

TRPA Transfer of Land Coverage

According to Chapter 20.3.B(8) of the TRPA Code of Ordinances, transfer of land coverage for water quality control facilities may be permitted under certain circumstances, including when a project affects the minimum land coverage necessary. Elements of the proposed project will create new impervious surfaces that are not exempt from the Bailey land coverage limits (Section 2.9.3). The total surface area is minimal and will be determined once final coverage areas are defined and TRPA performs the Coverage Verification. This verification will be performed by comparing coverage calculation maps, submitted by Caltrans, to 1972 aerial photographs. Any coverage, soft or hard, that existed before 1972 is not recognized by TRPA.

2.1.3. Avoidance, Minimization and/or Mitigation Measures

Avoidance and minimization measures for potential impacts related to temporary, periodic travel delays during construction are addressed in Section 2.4.4.

2.2. Community Impacts

2.2.1. Regulatory Setting

Under CEQA, consideration of economic and/or social changes only occurs when they result in a physical change to the environment (CEQA Guidelines Sections 15064(f) and 15382).

2.2.2. Affected Environment

Community development along or near this segment of US 50 is concentrated in the City of South Lake Tahoe. Development consists of year-round and seasonally used residences as well as general retail and commercial services, including lodging and vacation rentals, for the large number of recreational and seasonal visitors to the South Lake Tahoe area.

2.2.3. Impacts

US 50 will follow the same alignment and serve the same function following project construction. The project has been designed to avoid any impacts to housing or buildings, and consequently no residential or business relocations are necessary.

Construction and maintenance of some proposed facilities, such as the new infiltration basins, would require minor acquisition of property or easements. Parcels where easements or right-of-way acquisition is needed have been identified as privately owned and City of South Lake Tahoe property. Portions of parcels needed for basin construction along US 50 Segment 2 are generally located in the following areas: 1) in the vicinity of Lake Tahoe Airport; 2) on the east side of “G” Street near Mile Marker 56; 3) along US 50 where the lane configuration changes from two to four lanes; 4) on the east side of “B” Street; and 5) at the southeast quadrant of the US 50/SR 89 junction. None of these encroachments would affect the continued use of the existing roads or properties. Compensation for any property acquisition would be based on fair market value, and no adverse environmental impacts are identified associated with acquisition.

The project may cause intermittent traffic delays in the limited area of active construction. These delays could affect individual residents within the project limits as well as community institutions such as schools and local agencies.

In addition, construction activities may occur in close proximity to properties, driveways, and access roads, potentially causing temporary, minor disruptions to residents, owners, or occupants in those areas.

TRPA Considerations

There are no established TRPA thresholds directly related to community impacts, population or housing. The TRPA Initial Environmental Checklist (Appendix C) addresses housing in item 12 and public service impacts in item 14. This project will not alter the composition of housing or result in the need for changed or new schools or government services in the area, so there will be no impact.

2.2.4. Avoidance, Minimization and/or Mitigation Measures

The following describes community planning and coordination measures to avoid or minimize temporary and/or intermittent construction impacts to the community.

Additional measures are discussed in Section 2.4.4.

CI-1 Public Outreach

To provide public and motorist information on the project activities, a public involvement plan will be prepared and implemented that provides for communication and outreach measures specific to this segment of US 50. Information will be provided to potentially affected individuals and institutions in the local area, such as business and property owners, school districts, local agencies, and the Lake Tahoe Airport. If appropriate, the plan will provide for public informational meetings, events, and specific stakeholder coordination to notify and coordinate with the public about construction activities that might affect the community.

CI-2 Public and Private Property Access

Access to properties, driveways, or roads along US 50 will be maintained during construction but may be limited or reduced. Notification to occupants (or responsible parties) will be made whenever a property would be directly affected by construction activities.

2.3. Utilities/Emergency Services

2.3.1. Affected Environment

The South Lake Tahoe Fire Department has jurisdiction over most of US 50 Segment 2. In the southernmost portion of the project limits, a 0.25-mile section is within the jurisdiction of the Lake Valley Fire Protection District, which has jurisdiction over the unincorporated areas of El Dorado County. The U.S. Department of Agriculture Forest Service (Forest Service) provides fire protection for the National Forest lands surrounding the project area.

The California Highway Patrol and the El Dorado County Sheriff provide police protection in the unincorporated section of US 50 Segment 2 (Caltrans 2004). The South Lake Tahoe Police Department provides law enforcement in the rest of the project area, which is within the South Lake Tahoe city limits.

Barton Memorial Hospital serves the region and is located near the northernmost end of US 50 Segment 2, just east of the “Y” intersection of US 50 and SR 89 (Barton

HealthCare 2006). Access to the hospital would be maintained at all times during construction.

Electrical service in the project area is provided by Sierra Pacific Power. The Southwest Gas Corporation provides natural gas service to the project area. Water supply and wastewater treatment is provided by the South Tahoe Public Utility District.

2.3.2. Impacts

Emergency vehicles are exempt from road and lane closures; every effort would be made to allow police and fire vehicles to pass through construction zones without delay. Project-related construction activities and related effects on traffic are expected to have minimal effects on emergency services.

Relocation of some utilities may be required for construction of the proposed facilities. This could include relocation of aboveground or belowground utilities outside of a widened roadway shoulder or right-of-way. The study area includes areas outside of the roadway and right-of-way, and although the specific needs for any utility relocation will not be defined until the final design of this segment, the relocations are expected to be within the areas evaluated in this report. This will be verified during the final design.

TRPA Considerations

The project would not affect fire, police, or other emergency services as these vehicles will be allowed through any construction area. The South Lake Tahoe Fire Department and the Lake Valley Fire Protection District and Forest Service stations on Keetak Drive in Meyers will be able to continue to access US 50.

2.3.3. Avoidance, Minimization and/or Mitigation Measures

Avoidance and minimization measures for potential utility relocations during construction are described below. As emergency vehicles will be allowed passage through any construction zone, no additional avoidance, minimization, and/or mitigation measures are proposed for emergency services.

UE-1 Coordinate Final Design and Construction Activities with Utility Service Providers

Any need for utility relocation will be identified during final design of the project. If a need to relocate utilities is identified, Caltrans will coordinate these activities with the utility service providers.

2.4. Traffic and Transportation Facilities

2.4.1. Regulatory Setting

Caltrans directs that full consideration should be given to the safe accommodation of pedestrians and bicyclists during the development of federal-aid highway projects (see 23 Code of Federal Regulations [CFR] 652). It further directs that the special needs of the elderly and the disabled must be considered in all federal-aid projects that include pedestrian facilities. When current or anticipated pedestrian and/or bicycle traffic presents a potential conflict with motor vehicle traffic, every effort must be made to minimize the detrimental effects on all highway users who share the facility.

The CEQA Checklist (see Appendix B) includes potential issues that could lead to a significant impact pursuant to CEQA. Potential issues include substantially increasing traffic relative to existing load and capacity; exceeding a Level of Service standard; changing air traffic patterns; substantially increasing hazards; resulting in inadequate emergency access, resulting in inadequate parking capacity; or conflicting with adopted alternative transportation plans, policies, or programs.

Caltrans is committed to carrying out the 1990 Americans with Disabilities Act by building transportation facilities that provide equal access for all persons. The same degree of convenience, accessibility, and safety available to the general public will be provided to persons with disabilities.

2.4.2. Affected Environment

2.4.2.1. Traffic

US 50 Segment 2 is a two-lane/four-lane highway that provides access to the City of South Lake Tahoe and recreation opportunities in the region. At the intersection of US 50 and Sawmill Road, one mile south of the southern project limit, the eastbound annual average daily traffic (AADT) count is 13,000 with a peak-month average of 16,100. The westbound AADT for the intersection is 13,700 with a peak-month average of 18,000. At the US 50/SR 89 junction at the northern project limit, the eastbound AADT count is 33,000 with a peak-month average daily traffic count of 39,500. The westbound AADT is 19,500 with a peak month average of 27,000 (all AADT figures are for 2006; Caltrans 2007c). This location often experiences congestion as well as a shortage of parking.

2.4.2.2. Transit and School Bus Service

BlueGO is a coordinated public/private transit system serving the South Lake Tahoe area. Two lines operated by the BlueGO system pass through Segment 2. BlueGO bus Route A passes through 2 blocks of US 50 south of the US 50/SR 89 junction and provides direct service from the South “Y” Transit Station to the Stateline casino/hotel area. BlueGO bus Route H crosses Segment 2 near its midpoint along US 50 and provides non-direct service from the South “Y” Transit Station to the Stateline casino/hotel resort area.

School bus service is provided in South Lake Tahoe by the Lake Tahoe Unified School District. The Bijou routes primarily serve residences along or near US 50 Segment 2, including routes 11, 17, 21, and 22 (depending on the time of day and grade level served) (LTUSD 2006). Construction activities could cause temporary delays to school bus service, and bus schedules could be affected. Delays in any one location would be temporary, as the active work areas within each segment would move as construction is completed. One-lane travel in each direction would be maintained during construction activity where multiple lanes and shoulder width allow.

2.4.2.3. Access/Circulation and Parking

US 50 provides access to public, tourist, and commercial services; secondary roads; and residential areas between the Lake Tahoe Airport and the US 50/SR 89 junction. Numerous existing roadside shoulders and pullouts exist along this segment of US 50, both paved and unpaved, that can be used for parking. These pullouts are visible on the maps in Appendix A; however, there are no public parking signs or designated public parking areas along the entire segment.

2.4.2.4. Bicycle and Pedestrian Facilities

There are no designated Class I, II, or III bicycle facilities or pedestrian paths on US 50 between the Lake Tahoe Airport and the US 50/SR 89 junction, nor are bicycle or pedestrian improvements planned within the project area. However, two bicycle trails cross US 50 within Segment 2, one at “B” Street and the other at “C” Street in South Lake Tahoe.

2.4.3. Impacts

Traffic flow and access to existing parcels will not be permanently affected by this project. Temporary lane and road closures will be required where work is to be performed near or within traffic lanes. To expedite the construction process,

temporary lane and road closures may also be required to provide work space and road access for construction activities.

Temporary effects from traffic delays will be caused by the lane closures. Wherever possible, at least one lane in each direction will remain open. This may be achieved by using temporary lane width reductions where two-way traffic will be slowed. If available, wide highway shoulders may also be used as temporary travel lanes. However, where work must occur within or near a travel lane and alternative lanes are unavailable, temporary full lane closures may be necessary. Under these circumstances, traffic will be temporarily stopped in one or both directions and traffic will move in alternating one-way directions until the lane can be safely reopened. The location of necessary lane closures at any given time will shift as work progresses.

Additionally, Caltrans is planning to install a Traffic Operations System. Elements of this system, if constructed before this project, may provide additional public information and help reduce construction-related congestion.

Construction may inconvenience communities such as South Lake Tahoe and Meyers by creating traffic delays and temporarily impeding access to and from both US 50 and SR 89. Further, drivers could seek alternate routes through neighborhoods in the South Lake Tahoe area to avoid delays on US 50. For example, D Street circumvents the “Y” to the south and provides access to Lake Tahoe Boulevard (which becomes US 50 northeast of the “Y”). In addition, drivers could avoid delays on US 50 by taking Sawmill Road to Lake Tahoe Boulevard north to the “Y” junction. Increased traffic along these roads would have a temporary impact on local residences.

There is a potential for temporary effects from delays to school bus service when or if construction activities overlap in location and time with bus schedules. Delays in any one location would be temporary, as the active work area would shift as construction is completed.

The project will not adversely affect or change bicycle use on US 50. However, bicyclists may experience temporary effects related to potential intermittent delays during construction as discussed above.

TRPA Considerations

The project will not result in any permanent change in traffic volumes or patterns. Construction and its related staging could involve temporary use of some existing roadside pullouts.

Bicycle facilities are neither funded for nor included in this project. Pavement will be spot widened along some areas of the highway where work is planned for drainage improvements, but future widening along the entire corridor will be necessary to accommodate the bicycle facilities included in TRPA planning.

2.4.4. Avoidance, Minimization and/or Mitigation Measures

TT-1 Traffic Management Plan (TMP)

A TMP will be developed for the US 50 Segment 2 final design phase. The TMP outlines construction requirements and restrictions to minimize traffic delays and maximize safety within the construction areas. It will include strategies for public and motorist information, incident management, construction, demand management, and alternate routes (if available or practical). For example, a construction season map will be published each year to inform the public, local businesses, and local agencies of planned construction locations and activities. Elements of the TMP for this segment would typically include the following.

- During the peak summer travel season between July 1 and Labor Day, no lane closures would be allowed after noon on Fridays, or on weekends or holidays during this period. Work planned outside the highway travel lanes that does not impede normal traffic flow would not be subject to this restriction.
- Lane closure charts will be developed for each area of work to address any planned temporary lane changes or closures. These charts and schedules will be made available for public notification and information.
- Lane closures will be limited to 0.6 mile in length or less.
- Maximum delays caused by a single closure will be limited to 10 minutes for construction projects and 15 minutes for maintenance work. The cumulative delay for a given corridor will be limited to 30 minutes.
- Bicycle and pedestrian access will be maintained through construction zones whenever possible and as appropriate.
- Construction schedules and anticipated locations of construction activities will be coordinated with the local school district with regard to school bus schedules and bus stops. Every effort will be made to allow continued school bus access around construction areas to avoid or minimize delays in the daily bus schedules. If necessary, Caltrans will work with the school district to identify any temporary periods when unavoidable delays may occur, to allow the school district to temporarily adjust bus schedules.

2.5. Visual and Aesthetics

2.5.1. Regulatory Setting

The *LBTMU Land and Resource Management Plan* (Forest Service 1988) established Visual Quality Objectives, thresholds for development coverage on National Forest lands in the Tahoe Basin. These include the following designations:

- Preservation on 27 percent of land area
- Retention on 65 percent of land area
- Partial retention on 4 percent of land area
- Modification on 3 percent of land area
- Maximum modification on 1 percent of land area

CEQA establishes that it is the policy of the state to take all action necessary to provide the people of the state “with...enjoyment of aesthetic, natural, scenic and historic environmental qualities” (California Public Resources Code [PRC] Section 21001[b]).

The California Legislature created a Scenic Highway Program in 1963. Its purpose is to preserve and protect scenic highway corridors from change, which would diminish the aesthetic value of the lands adjacent to highways. The state laws governing the Scenic Highway Program are found in the Streets and Highways Code, Section 260 et seq.

The following TRPA Thresholds apply to scenic resources:

- **SR-1 Travel Route Rating:** The travel route rating threshold tracks long-term, cumulative changes to views seen from major roadways in urban and natural landscapes in the region and to the views seen from Lake Tahoe looking toward shore. To secure threshold attainment, all travel routes with a 1982 score of 15.5 (for roadway units) or 7.5 (for shoreline units) or greater must maintain their scores, and all travel routes with a 1982 score of 15 (roadway) or 7 (shoreline) or less must improve their scores until the score is reached.
- **SR-2 Scenic Quality Rating:** The scenic quality rating threshold protects specific views of scenic features of Tahoe’s natural landscape that can be seen from major roadways and from the lake. To secure threshold attainment, all 1982 scenic quality scores must be maintained.
- **SR-3 Public Recreation Areas and Bike Trails:** The public recreation area threshold protects the view shed from public recreation areas and certain bicycle

trails. To secure threshold attainment, all 1993 scenic quality scores must be maintained.

- SR-4 Community Design: The community design threshold is a policy statement that applies to the built environment. Design standards and guidelines found in the Code, the Scenic Quality Improvement Program, and in the adopted Community Plans provide specific implementation direction. To secure threshold attainment, design standards and guidelines must be widely implemented to improve travel route ratings and produce built environments compatible with the natural, scenic, and recreational values of the region.

Additionally, TRPA has standards for Scenic Restoration within the Plan Area Statements that exist along the project route. Project features must take these Plan Area Statements into account.

2.5.2. Affected Environment

2.5.2.1. Visual Environment

The proposed project is located in the Lake Tahoe Basin, which is considered to have high scenic values. US 50 in the project limits is an officially designated State Scenic Highway. The highway facility is a major corridor that connects Northern California to Nevada and states beyond. US 50 is heavily used at times by both recreational and local traffic.

The project limits contain two distinct sections. The first section is from Airport Road to F Street. The existing roadway is a two-lane facility (one lane in each direction), with shoulders ranging from 0 to 4 feet. The land use along this segment is a combination of industrial, residential, and heavily forested open space. The open space includes vacant (undeveloped) parcels and the Lake Tahoe Airport. The second section is from F Street to the US 50/SR 89 junction in the City of South Lake Tahoe. The existing roadway is a four-lane facility (two lanes in each direction) with a center two-way left-turn lane. The land use along this portion of US 50 is predominantly tourist-oriented retail and mixed commercial, with motels, gas stations, restaurants, and shops.

Many large trees exist along the roadside throughout the project limits. Native vegetation ties the roadside to the surrounding landscape pattern and provides a buffer that screens landowners, recreational users, and motorists from undesirable views.

The project limits contain few off-highway vistas and views. Near the southern end of the project area, motorists on US 50 have a brief glimpse of the peaks beyond the

Lake Tahoe Airport. Shortly thereafter, trees quickly close in around the roadway. Motorists' views are limited to the immediate roadside for the remainder of the project limits.

2.5.2.2. TRPA Scenic Resources

The TRPA is charged with protecting Lake Tahoe and the Basin for the benefit of current and future generations. The 1980 revised Compact (see Section 1.3.2) gave TRPA authority to adopt and enforce environmental quality standards. These standards were designed to achieve desired thresholds and adopted in 1982.

Any visual impact assessment prepared for roadway projects in the Tahoe Basin must consider TRPA's Scenic Resource Inventory. The TRPA has inventoried and rated roadway segments throughout the basin to determine scenic resource values from roadway vantage points. This visual assessment has two categories: Travel Route Ratings and Scenic Quality Ratings.

The TRPA assigned each roadway unit with a numerical threshold rating based on a scoring system. Travel Route Threshold Ratings ranged from 7 (lowest) to 27 (highest). To meet the thresholds, all travel routes with a 1982 score of 15.5 (roadway) or greater must maintain those scores, and all travel routes with a 1982 score of 15 (roadway) or less must improve their scores until the threshold score is reached. Ratings of Scenic Quality for Roadway Units assessed visual features for a composite score averaging unity, vividness, variety, and intactness. Scoring was from 1 to 3, with 1 being the lowest. Both assessment scores were updated in 2001.

The following TRPA roadway units fall within the limits of the proposed project.

- Roadway Unit 35, AL Tahoe; STA 957 to 981. 2001 Composite Threshold Score = 7.5, Overall Scenic Quality Rating = 1. Entering the City of South Lake Tahoe from the south, "Motel/resort development begins and intensifies up to the Route 50 intersection with Route 89 (the 'Y'). No mid-distance or long-distance views are readily available in this area" (TRPA 1982).
- Roadway Unit 36, Airport Area; STA 889 to 957. 2001 Composite Threshold Score = 10.5, Overall Scenic Quality Rating = 2. Entering the project limits from the south, "Flat open foreground views of runway areas are backed by an expanse of large scale mountains to the east that include the ridgelines and slopes of the Cold Creek and Trout Creek watersheds. North of the airport, pine forests enclose the roadway with minor development on both sides for about 0.5 mile, on both sides of the South Lake Tahoe city limits" (TRPA 1982).

Both Roadway Units 35 and 36 fail to meet the TRPA minimum attainment threshold. Although the composite threshold score for Roadway Unit 35 has increased from its 1982 rating of 7, the roadway has not reached its attainment score of 15.5 due to “roadway distractions” and “man-made features.” The composite threshold score for Roadway Unit 36 has decreased from its 1982 rating of 15 due to the level and type of development in this roadway unit. Design recommendations that address TRPA scenic thresholds are outlined in subsequent sections.

2.5.3. Impacts

The visual assessment primarily considers new human-made components introduced into the project site. Some of the proposed project features will introduce additional roadside distractions and human-made features to the roadway, which would be visible to surrounding residences and businesses and could affect scenic quality on US 50. The assumption is that replacement of an existing drainage facility in kind is not changing the environment and will not warrant discussion. Work that is anticipated, but for which exact dimensions are unknown, will be discussed in general terms.

This segment is located on a designated State Scenic Highway, where the objective is to maintain the existing visual quality and not cause this segment to degrade in scenic value. Although visual impacts would result from the project features described below, with the implementation of design features and measures to minimize harm, this project will not:

- Have a substantial adverse effect on a scenic vista, or
- Substantially damage scenic resources, including, but not limited to trees and historic buildings.

Infiltration Basins

Disturbance is expected from construction of infiltration basins due to their size and potential to require tree removal. The extent of tree removal will be minimized with the use of irregularly shaped basins. Up to 17 infiltration basins ranging in size from 0.05 acre to 2.42 acres are proposed. This may require removal of more than 50 trees.

Drainage Maintenance Pullouts

Seven paved pullouts for maintenance vehicles will be constructed near highway facilities that require maintenance. Pullouts are typically 15.75 feet wide, 163 feet long adjacent to the roadway shoulder, and 45 feet long on the backside. Three pullouts will include a ramp leading to four proposed basins. Where possible, pullouts

will be located in areas that are sufficiently level and large enough to accommodate them in order to avoid site disturbance. Minimal cut and fill may be required. Ground disturbance and/or vegetation removal may be required to construct the basin access ramps.

Sand Traps and Sand Vaults

Sand traps are buried PCC rectangular structures topped by metal lids that are slightly below grade. A slotted opening below the lid collects sand that washes off the roadbed in wet weather. Sand vaults are rectangular multichambered PCC units that are larger than sand traps. Constructed at-grade, sand vaults can be used in locations with vehicle traffic. They have metal grates over the chambers as well as access hatches for maintenance. Highway maintenance staff periodically cleans out the sand traps and vaults.

Sand traps and vaults are primarily underground with only a small percentage of the structure visible. Although they are constructed features and foreign to the surrounding environment, sand traps and vaults are not readily visible to the traveling public. They are located below the level of the traveled way and tend to be visible only if traveling at extremely low speed or walking/bicycling along the highway shoulder. Sand traps are usually surrounded by rock slope protection.

Rock Slope Protection (End Treatment of Culverts)

Outlets of existing culverts will receive rock slope protection “end treatments” at an undetermined number of locations throughout the project limits. End treatments will slow the velocity of water leaving culverts to reduce scour and promote infiltration. The end treatments will be constructed from rock riprap placed below the culvert outlet. The rock riprap will consist of a number of rocks arranged at grade, in a tight cluster. The riprap will be visible due to the color variation between the rocks and the surrounding forest floor, the lack of similar natural rock outcroppings in the vicinity, and the hard unnatural lines created at the boundary of the treatments.

A minimal amount of ground-level vegetation may be removed for the placement of the treatments. The end treatments will be located below the level of the roadway and will be minimally visible from the traveled way. Over time, the end treatments will collect silt, debris, and vegetation, blending them into the surrounding environment. The type, length, width, and number of the end treatments vary depending on the size and predicted flow of the culvert as well as the topography of the land on which the

treatment is placed. Where possible, the most visually appropriate treatment size will be selected.

Revegetation of Bare or Erodible Areas

Revegetation of bare or erodible areas is proposed at an undetermined number of locations throughout the project limits. The proposed revegetation will help to stabilize and/or repair bare or erodible areas that result from off-highway parking and cut/fill slopes. Revegetation will include one or more of the following, as determined by the Caltrans Landscape Architect: compost, native permanent erosion control seed mix, containerized plants, pine needle straw, and temporary irrigation systems. If required, natural barriers such as logs or boulders will be used to deter off-highway parking. By better blending the bare or erodible areas with the natural environment, revegetation will have a positive effect on the overall visual quality of this roadway segment.

Curbs and Gutters

New curbs and gutters are proposed along the entire project limits. The proposed curb and gutter system will help to direct storm water to appropriate treatment locations. The proposed system will be a modified Caltrans Standard Type E curb constructed of PCC or AC.

Installation of a curb and gutter system can create a visual impact if it contrasts with the surrounding roadside environment in terms of texture, angularity, and color. Concrete can be light in color and reflective when first installed, causing the curb and gutter to stand out when viewed next to the asphalt roadway and natural roadside. The weathering process that dulls the colors could take several years.

Where curbs and gutters are replaced, like and kind replacement is appropriate.

Shoulder Widening

Shoulders will be spot widened where necessary to accommodate the installation of the proposed concrete curb and gutter system. Minor cut and fill may be required to construct the proposed roadway shoulders.

Slopes will be minimized to the extent possible. Where feasible, all slopes will maintain a maximum slope of 1:4 to 1:2 (vertical:horizontal). Cut/fill slopes will be revegetated. If required, rock slope protection would be applied to slopes steeper than 1:2 (V:H). Rock slope protection will be revegetated.

LTBMU Visual Quality Objectives

The project will not result in a noticeable change for purposes of development coverage and LTBMU Visual Quality Objectives. Trees and vegetation will be removed, which will be replaced where landscaping or vegetation planting is feasible. Changes in pavement and shoulder coverage will occur along US 50.

TRPA Considerations

No views of Lake Tahoe or other scenic vistas will be affected by the project. The project is consistent with TRPA height and design standards and the TRPA Scenic Quality Improvement Program and Design Review Guidelines (TRPA 1989a, 1989b). The TRPA roadway units within the project limits currently do not meet TRPA minimum attainment thresholds. With implementation of avoidance and minimization measures to reduce effects to existing views, vegetation, and terrain, the project is not expected to further degrade the TRPA threshold ratings.

Rock slope protection will have an initial moderate adverse effect on scenic vistas that will subside as new vegetation matures and creates a more natural effect. The project features will not substantially degrade the existing visual character or quality of the area and surroundings with implementation of the measures proposed in Section 2.5.4.

Each tree that must be removed to accommodate project features will be reviewed with TRPA to ensure compliance with Scenic Thresholds and Plan Area Statements and to identify additional mitigation measures that will be necessary. Regulations and guidelines outlined in Chapter 71 (Tree Removal) of the TRPA Code of Ordinances will be followed when identifying trees to be removed.

2.5.4. Avoidance, Minimization and/or Mitigation Measures

VA-1 Measures for Specific Project Components

Measures to minimize impacts associated with the following project components are listed below.

- **Infiltration basins.**
 - Each basin will be designed specifically for its site. The basin shape will be designed to maximize infiltration and minimize tree removal. Where feasible, basins will be irregularly shaped around trees. However, if it is determined that it is not feasible to maintain the long-term health of a tree, then the tree will be removed as part of basin construction.

- Infiltration basins will be designed without harsh angles and will integrate features into surroundings through the use of curvilinear forms and contour grading.
- All disturbed areas associated with basin construction will be revegetated using seeding, container planting, pine needle mulch, and temporary irrigation where required.
- Logs and boulders, as appropriate, will be integrated into the basin design.
- Infiltration basins will avoid the use of concrete or rock slope protection lining.
- **Maintenance pullouts.**
 - Where possible, the infiltration basin access ramps will be routed to minimize ground disturbance and vegetation removal.
- **Sand traps and sand vaults.**
 - Sand traps will be installed in the least visible locations feasible.
 - Sand trap structures will be painted or powder coated with an approved Standard Federal Color (Brown #30045 or Green #34108). The specific color will be selected to match the color of any existing elements in the immediate area.
 - All disturbed areas associated with sand trap installation will be revegetated using seeding, container planting, and/or pine needle straw.
 - Visible portions of sand vaults should be designed so that the tops of the structures can be paved over, leaving only the maintenance access visible.
 - Visible portions of sand vaults will be painted or powder coated with an approved Standard Federal Color that matches the color of existing elements in the immediate area.
- **Rock slope protection (end treatment of culverts).**
 - The selected rocks will include indigenous sizes, shapes, materials, and colors wherever feasible. Edges will have irregular shapes.
 - Culvert end treatments will be treated with environmentally benign stains to induce a weathered appearance that blends elements into the existing landscape.
 - Where required, containerized native plantings will be used to strategically blend into the landscape, and/or screen, culvert end treatments from view.
- **Curbs and gutters.**
 - Any new curbs and gutters will be colored an earth tone to help blend the curbs into the existing roadside.

VA-2 General Design and Construction Measures

- Temporary erosion control measures will be used in all disturbed areas during construction to minimize permanent impacts.
- Permanent erosion control measures will be used in all disturbed areas during construction. All disturbed areas will receive a permanent seed mix composed of native plant species indigenous to the area. In addition, if required, a follow-up revegetation project will install containerized plants to supplement seeding. All removed plantings will be replaced in kind. All native vegetation removed will be replaced in ratios determined by Caltrans Environmental and Landscape Architecture Offices.
- All small trees, tree limbs, shrubs and other woody debris generated during clearing and grubbing operations will be chipped and stockpiled for future use as erosion control and in areas designated for revegetation.
- Compost will be incorporated where feasible.
- Any water quality improvement ditches required will be earthen- or rock-lined whenever possible.
- If required, fences used to limit access to basins or other highway features will be made of logs or wood rails to support visual continuity along the corridor.

VA-3 TRPA Scenic Values

Caltrans roadway and drainage improvements will consider TRPA scenic thresholds and incorporate design elements or improvements that do not degrade current values. Scenic values will be enhanced to the extent possible within the scope of the proposed work.

2.6. Cultural Resources

2.6.1. Regulatory Setting

“Cultural resources” as used in this document refers to all historical and archaeological resources, regardless of significance. Laws and regulations dealing with cultural resources include the following.

The National Historic Preservation Act of 1966, as amended, sets forth national policy and procedures regarding historic properties, defined as districts, sites, buildings, structures, and objects included in or eligible for the National Register of Historic Places (NRHP). Section 106 of National Historic Preservation Act requires federal agencies to take into account the effects of their undertakings on such properties and to allow the Advisory Council on Historic Preservation (Advisory

Council) the opportunity to comment on those undertakings, following regulations issued by the Advisory Council on Historic Preservation (36 CFR 800). On January 1, 2004, a Section 106 Programmatic Agreement among the Advisory Council, FHWA, SHPO, and Caltrans went into effect for Caltrans projects, both state and local, with FHWA involvement. The Programmatic Agreement takes the place of the Advisory Council's regulations (36 CFR 800), streamlining the Section 106 process and delegating certain responsibilities to Caltrans.

The Archaeological Resources Protection Act applies when a project may involve archaeological resources located on federal or tribal land. The Archaeological Resources Protection Act requires that a permit be obtained before excavation of an archaeological resource on such land can take place.

Historical resources are considered under CEQA and under PRC Section 5024.1, which established the California Register of Historical Resources (CRHR). PRC Section 5024 requires state agencies to identify and protect state-owned resources that meet NRHP listing criteria. It further specifically requires Caltrans to inventory state-owned structures in its rights-of-way. Sections 5024(f) and 5024.5 require state agencies to provide notice to and consult with the SHPO before altering, transferring, relocating, or demolishing state-owned historical resources that are listed on or are eligible for inclusion in the NRHP or are registered or eligible for registration as California Historical Landmarks.

The TRPA Initial Environmental Checklist identifies issues that may be deemed significant pursuant to the TRPA Code of Ordinances. These issues include alteration of a significant archaeological or historic site, adverse effects to a prehistoric or historic building, structure or object, physical changes that would affect unique cultural ethnic values, or restriction of historic or pre-historic religious or sacred uses within the affected area.

Chapter 29 of the TRPA Code of Ordinances sets forth provisions for the protection of both known and newly discovered cultural and historical resources.

2.6.2. Affected Environment

Two Areas of Potential Effects (APEs), one for historical resources and another for archaeological resources, were defined to evaluate the presence of cultural resources in the project area and their potential to be affected by the project.

The APE for historical resources includes the right-of-way of US 50 Segment 2 and an Environmental Study Limit (ESL) identified as the area for potential construction impacts. Consistent with procedures for determining the study area for the “built environment,” the historical resources APE also encompasses entire parcels, except where the parcels are large and vacant.

The archaeological APE was defined to encompass all areas that might be disturbed by project construction. As such, the APE was defined to correspond with the boundaries of the ESL.

2.6.2.1. Records/Archival Review

Historical Resources

Records searches were conducted at the North Central Information Center at California State University, Sacramento in 2006 and 2007, and sources of information were reviewed that list or cite known or potential historic properties and historical resources. These sources included the NRHP, Office of Historic Preservation (OHP) Determinations of Eligibility for the NRHP, California Inventory of Historic Resources, California Historical Landmarks, and California Points of Historical Interest. In addition, research was conducted at the California State Library in Sacramento, Caltrans Transportation Library in Sacramento, Shields Library at the University of California Davis, El Dorado County Offices in South Lake Tahoe, South Lake Tahoe Historical Society Museum in South Lake Tahoe, North Lake Tahoe Historical Society in Tahoe City, El Dorado County Public Library – South Lake Tahoe Branch, and the Lake Tahoe Community College Library. In March 2006, letters requesting input or knowledge about any historic properties in the APE were sent to the South Lake Tahoe Historical Society and Museum, North Lake Tahoe Historical Society, El Dorado County Historical Society, Tahoe Heritage Foundation, and Tahoe Maritime Museum.

Archaeological Resources

A California Historical Resources Information System records search was completed for the APE at the North Central Information Center at California State University, Sacramento on April 25, 2007. The records search included a review of all recorded archaeological sites, historic structures, and other known cultural resources within the archaeological APE and the surrounding half-mile radius, as well as a review of reports for all known cultural resources studies conducted within the half-mile search radius. Other references consulted included the NRHP; CRHR; OHP Historic Property Directory; Caltrans Bridge Inventory; California State Historical Landmarks

listing; California Inventory of Historic Resources; California Points of Historical Interest; Historic Hot Spots (Hoover); California Place Names (Gudde); and historic maps, including the General Land Office plat maps for Township 12 North, Range 18 East.

In addition, records searches were conducted with the Forest Service to determine if any additional previously recorded resources would be affected by the project. Research included cultural resources formally recorded on California Department of Parks and Recreation records, as well as informally recorded resources identified by the North Central Information Center and records provided by the LTBMU.

All accessible portions of the archaeological APE were subject to intensive pedestrian survey in 2005 through 2007.

2.6.2.2. Records Search/Field Survey Results

No additional cultural resources were identified as a result of the pedestrian survey conducted in 2007.

Three cultural resources were identified within the historical and/or archaeological APEs, as shown in Table 2.6-1.

Table 2.6-1 Resources Located within the APEs

Site Designations	Component	Site Description	Recorded by	Date Recorded*
"Isolate Mile Marker 56"	Historic	Granite mile marker; originally erected in the 1900s or 1930s	C. McMorris, JRP	2006*
"Old Highway 89 / Old Placerville Road / Site 1 / Historic US 50, Segment 3"	Historic	Portion of "Old Highway 89", specifically "Segment 3"; this is a 700-foot segment of a 20-foot wide partially paved road	S. Dexter, CCC & C. McMorris, JRP	2005*
1151 Emerald Bay Road	Historic	1.17-acre parcel with one 1955 commercial building and a shed	C. McMorris, JRP	2007

* Previously recorded resource

The three cultural resources are described below.

- Isolate Mile Marker 56 is a granitic mile marker monument measuring 20 inches across the face, 8 inches deep, and 36 inches exposed above the soil. Only a rectangular area on the face is smooth, where an arrow and "56 MILES" is engraved. The arrow points toward the westbound direction of traffic. This resource has been determined ineligible for the NRHP (JRP 2007).

- Old Highway 89 / Old Placerville Road / Site 1 / Historic US 50, Segment #3 is a segment of “Old Highway 89,” specifically identified as “Segment 3.” This portion of the resource is a 700-foot segment of a 20-foot-wide partially paved road. It appears that this resource retains little integrity of its original design. This resource has been determined ineligible for the NRHP (JRP 2007).
- 1151 Emerald Bay Road contains one commercial building adjacent to Emerald Bay Road and a shed. The property has served as a retail/service operation, office, or restaurant since the main building was constructed in 1955. Although the buildings retain some historic integrity to their possible period of significance in the 1950s, the property is not historically significant. This resource has been determined ineligible for the NRHP (JRP 2007).

Portions of an additional site were previously identified within the APE. “CA-ELD-2206-H” is described as an apparently modern house foundation destroyed in a fire in approximately 1996. However, Julia Green, a Caltrans Archaeologist who meets the Professionally Qualified Staff Standards in Section 106 Programmatic Agreement Attachment 1 as a Co-PI Historical Archaeology, has determined that this property meets the criteria for Section 106 Programmatic Agreement Attachment 4 (Properties Exempt from Evaluation). Therefore, this property is not considered a historical resource under CEQA and requires no further treatment (URS 2007b).

Thirteen previously recorded cultural resources were identified within a half-mile of the archaeological APE. Of the prehistoric sites identified within a half-mile of the APE, seven are milling stations with concomitant midden and lithic debris (e.g., CA-ELD-999, STPUD-2, -3, and -5). The remaining historical sites are early transportation corridors, historic trash scatters, or habitation sites (e.g., CA-ELD-2240H, MTHP-2, and STPUD-12, respectively).

2.6.2.3. Native American Consultation

Native American consultation for the project was completed in two rounds. A records search of the Sacred Lands File was conducted during the first round. According to the Native American Heritage Commission (NAHC), the Sacred Lands File did not list any sites that are located within the immediate project area. The NAHC provided a list of seven Native American individuals and organizations that might have information pertinent to the project, or might have concerns regarding the proposed project. Caltrans sent letters and maps to the contacts provided by the NAHC on February 24, 2006. Field visits were conducted on August 18 and 30, 2006, with individuals who wanted additional information about the project.

During the second round of Native American consultation, the Sacred Lands File was consulted to determine if any additional information had been obtained by the NAHC. No sites were identified within the project area. This information was provided to Caltrans, and in August 2007, a second letter was sent to the individuals identified by the NAHC. Based on the response and interest from the Washoe Tribe, additional field visits to the project area are being scheduled.

2.6.2.4. Potential for Subsurface Resources

Prehistoric archaeological sites have been documented within and around the project area, such as the Visitor Center Site near the City of South Lake Tahoe (Martin 1998) that was primarily occupied during the early Holocene, roughly 7,500 to 10,000 years ago. Although this site did not contain buried soils, it indicates that landscapes in the project area were stable enough at various periods throughout the Holocene to preserve evidence for human occupation.

Because of the nature of episodic deposition due to flooding and stream movement, buried soils may occur adjacent to soils that do not have a buried profile, and the aerial extent is likely discontinuous. Landforms in the project area that have the potential to contain buried soils are valleys, including the floodplain and abandoned and recent stream terraces.

2.6.3. Impacts

Archaeological resources located within the project APE have the potential to be affected by the proposed project; however, with implementation of the avoidance measures outlined in Section 2.6.4, no temporary or permanent impacts are anticipated.

TRPA Considerations

No impacts pursuant to Chapter 29 of the TRPA Code of Ordinances have been identified.

2.6.4. Avoidance, Minimization and/or Mitigation Measures

CR-1 Discovery of Archaeological Resources

No further archaeological work is necessary within the APE. Additional surveys would be required if the project changes to include areas not previously surveyed. The project does not warrant the completion of a formal discovery plan based on the absence of recorded, reported, or identified archaeological sites in and adjacent to resources during construction. If cultural materials are discovered during construction, all earth-moving activity within and around the immediate discovery

area will be diverted until a qualified archaeologist can assess the nature and significance of the find. TRPA will also be contacted if any cultural materials are identified during construction.

CR-2 Discovery of Human Remains

If human remains are discovered, California Health and Safety Code Section 7050.5 states that further disturbances and activities shall cease in any area or nearby area suspected to overlie remains, and the County Coroner contacted. Pursuant to PRC Section 5097.98, if the remains are thought to be Native American, the coroner will notify the NAHC, which will then notify the Most Likely Descendent. At this time, the person who discovered the remains will contact Jody Brown, Caltrans Environmental Branch Chief, so that Caltrans may work with the Most Likely Descendent on the respectful treatment and disposition of the remains. Further provisions of PRC Section 5097.98 are to be followed as applicable.

Physical Environment

2.7. Hydrology and Floodplains

2.7.1. Regulatory Setting

Federal, state, and local laws, regulations, and guidelines require that planning for future development and specific projects consider floodplain hazards and risks. This includes the potential planning and placement of community development within mapped 100-year flood hazard zones, and placement of structures within 100-year flood hazard areas that might impeded or redirect flood flows.

Potential significant issues identified by the TRPA Initial Environmental Checklist include potential exposure due to the project to water-related hazards such as seiches or floods.

2.7.2. Affected Environment

The project is located in the Lake Tahoe Basin and the connecting upper Truckee River Canyon. The Lake Tahoe Basin is an intermountain basin formed by the faulting of the rocks of the Sierra Nevada to the west and the Carson Range on the east. Within the study area, US 50 traverses flat topography with an average elevation of approximately 6,000 feet.

No major surface water bodies lie within the project limits. The Upper Truckee River crosses US 50 nearly a mile south and at least 0.25 mile east of the project limits. The Lake Tahoe Airport is between the river and US 50. Three ephemeral/man-made drainages, two ephemeral/natural waterways, and one perennial/intermittent waterway were identified within the ESL. These potentially jurisdictional features are discussed further in Section 2.15.2.2.

2.7.3. Impacts

According to Federal Emergency Management Agency (FEMA) Flood Insurance Rate Maps (Community-Panel Numbers 0650600010B and 0600400388B), the project is located within Zone “C.” Zone “C” is defined as an area of minimal flood hazard from the principal source of flooding in the area that is outside of the 0.2 percent annual chance floodplain (FEMA 1978, 1983). The proposed project would not alter the floodplain or flows within any of the surface water resources. Moreover, the project will not affect growth within any floodplain area, as it will not change the highway location, capacity, or access to or from the highway with respect to any undeveloped area in a floodplain.

TRPA Considerations

This project is proposed to comply with TRPA’s EIP for this segment of US 50, and its primary purpose is to improve the quality of storm water runoff. The project will result in discharge to surface waters, but effects to drainage patterns will be minor and will be limited to directing runoff into new drainage basins and other facilities. Drainage basins are intended to substantially contribute to containing runoff on-site, consistent with the TRPA criteria of containing a 20-year, 1-hour storm event.

Implementing the proposed improvements will increase the infiltration of storm water runoff into groundwater. The project will not result in water-related hazards such as seiches or floods.

2.8. Water Quality and Storm Water Runoff

2.8.1. Regulatory Setting

2.8.1.1. State

Section 303 of the federal CWA requires states to adopt water quality standards for all surface waters of the United States. Where multiple uses exist, water quality standards must protect the most sensitive use. The State Water Resources Control Board (SWRCB) and the Regional Water Quality Control Boards are responsible for ensuring implementation of and compliance with provisions of the Federal CWA and

California's Porter-Cologne Water Quality Control Act. Section 401 of the CWA requires water quality certification from the SWRCB or from a Regional Water Quality Control Board (RWQCB) when the project requires a CWA Section 404 permit to dredge or fill within a water of the United States.

Along with CWA Section 401, CWA Section 402 establishes the NPDES permit for the discharge of any pollutant into waters of the United States. The U.S. Environmental Protection Agency (USEPA) has delegated administration of the NPDES program to the SWRCB and nine RWQCBs. The SWRCB and RWQCB also regulate other waste discharges to land within California through the issuance of waste discharge requirements under authority of the Porter-Cologne Water Quality Act.

The SWRCB has developed and issued a Statewide NPDES Permit to regulate storm water discharges from all Caltrans activities on its highways and facilities. Caltrans construction projects are regulated under the Statewide Permit, and projects performed by other entities on Caltrans right-of-way (encroachments) are regulated by the SWRCB's Statewide General Construction Permit. All construction projects require a Storm Water Pollution Prevention Plan (SWPPP) to be prepared and implemented during construction.

The project area is within the jurisdiction of the LRWQCB. The LRWQCB has the authority to implement water quality protection standards through the issuance of permits for discharge to waters at locations within its jurisdiction. In addition, the governments of Nevada and California, as well as the United States, have identified the Lake Tahoe area as an Outstanding National Resource Water. Accordingly, projects and facilities in the hydrologic unit that drains to Lake Tahoe, identified as the LTHU, must satisfy more stringent requirements than in most other parts of the United States. In addition to LRWQCB requirements, TRPA, whose jurisdiction covers the entire LTHU, regulates environmental conditions through the TRPA Code of Ordinances. The LRWQCB regulates activities within wetlands and waters of the U.S. and TRPA SEZs.

Water quality objectives for the Lake Tahoe drainage basin apply to the Upper Truckee River and its tributaries and are specified in Basin Plan prepared by the LRWQCB. The Basin Plan establishes water quality objectives and implementation programs to meet stated objectives and to protect the beneficial uses of water in the LTHU.

2.8.1.2. Regional

Tahoe Regional Planning Agency

TRPA is designated by California and the USEPA as the areawide water quality planning agency under Section 208 of the CWA. It adopted a bi-state plan entitled the *Water Quality Management Plan for the Lake Tahoe Region* (208 Plan; TRPA 1988). Most appropriate provisions of the 208 Plan, however, are incorporated into the Basin Plan.

TRPA water quality thresholds are as follows:

- WQ1: Decrease sediment load as required to attain turbidity values not to exceed 3 Nephelometric Turbidity Units (NTU) in littoral Lake Tahoe. In addition, turbidity shall not exceed 1 NTU in shallow waters of Lake Tahoe not directly influenced by stream discharges.
- WQ2: Average Secchi depth, December–March, shall not be less than 33.4 meters.
- WQ3: Annual mean phytoplankton primary productivity shall not exceed 52 gC/m²/yr. California: algal productivity shall not be increased beyond levels recorded in 1967–1971, based on a statistical comparison of seasonal and annual mean values.
- WQ4: Attain a 90th percentile value for suspended sediment of 60 milligrams per liter (mg/L).
- WQ5: Dissolved inorganic nitrogen, 0.5 mg/L; dissolved phosphorous, 0.1 mg/L; dissolved iron, 0.5 mg/L; suspended sediment, 250 mg/L.
- WQ6: Surface water infiltration into the groundwater shall comply with the Uniform Regional Run Off guidelines. For total nitrogen, 5 mg/L; total phosphorous, 1 mg/L; total iron, 4 mg/L; turbidity, 200 NTU; and grease and oil, 40 mg/L.
- WQ7: For other lakes in California/Nevada, the standards are the same as the tributary standards.

For Caltrans projects, a Memorandum of Understanding (MOU) between TRPA and the LRWQCB acknowledges that LRWQCB is the lead regulator for water quality. LRWQCB water quality thresholds can be found in the Basin Plan. The LRWQCB numeric effluent limits for runoff discharged to infiltration systems mirrors TRPA Threshold WQ-6. The LRWQCB numeric effluent limits for surface discharges are similar to TRPA Threshold WQ-5 but also place limits of 20 NTU for turbidity and 2.0 mg/L for grease and oil.

If the project requires permits from the LRWQCB for 401 Water Quality Certification to comply with any necessary USACE or RWQCB permit, or for a discharge related to pavement cutting/grinding operations, any requirements defined in those permits will be implemented as part of the project.

El Dorado County

The following are the goals and policies established in the El Dorado County General Plan (2004) that provide guidance for development in the county specific to water resources.

- Stream and lake embankments shall be protected from erosion, and streams and lakes shall be protected from excessive turbidity.
- Projects requiring a grading permit shall have an erosion control program approved, where necessary.
- For projects that would result in the discharge of material to or that may affect the function and value of river, stream, lake, pond, or wetland features, the application shall include a delineation of all such features. For wetlands, the delineation shall be conducted using the USACE Wetland Delineation Manual.
- Until standards for buffers and special setbacks are established in the Zoning Ordinance, the county shall apply a minimum setback of 100 feet from all perennial streams, rivers, lakes, and 50 feet from intermittent streams and wetlands. These interim standards may be modified in a particular instance if more detailed information relating to slope, soil stability, vegetation, habitat, or other site- or project-specific conditions supplied as part of the review for a specific project demonstrates that a different setback is necessary or would be sufficient to protect the particular riparian area at issue. For projects where the county allows an exception to wetland and riparian buffers, development in or immediately adjacent to such features shall be planned so that impacts on the resources are minimized. If avoidance and minimization are not feasible, the County shall make findings, based on documentation provided by the project proponent, that avoidance and minimization are infeasible.
- Natural watercourses shall be integrated into new development in such a way that they enhance the aesthetic and natural character of the site without disturbance.


2.8.2. Affected Environment

2.8.2.1. Surface and Groundwater Resources

As described in Section 2.7.2, there are no major water bodies within the project limits. The Upper Truckee River crosses US 50 nearly a mile south of this project and

is separated from US 50 by the Lake Tahoe Airport. Figure 2.8-1 shows the locations of the water bodies within the project vicinity.

Figure 2.8-1 Water Bodies Near US 50 Segment 2



No waterways in this study area are listed in the CWA's 303(d) list of Water Quality Limited Segments. Lake Tahoe has been classified as impaired by sediment and nutrient inputs, of which road sand and highway runoff are major constituents. Road sand from Caltrans operations and highway runoff including nitrogen and phosphorus are recognized sources of lake pollution.

Groundwater levels range from 1.3 to 69.8 feet below ground surface in the Upper Truckee and Trout Creek watersheds (USGS 1996). Groundwater levels vary depending on rainfall, snowmelt, pumping, construction activities, and water levels in Lake Tahoe and the Upper Truckee River.

Depending on the time of year, seepage may be encountered in rock fractures or road cuts. Seepage and groundwater conditions will vary based on rainfall, snowmelt, seasonal and diurnal cycles, pumping, construction activities, and water levels in Lake Tahoe and the Upper Truckee River. Project-related construction activities have the potential to result in additional groundwater seepage, which could mobilize fine sediment.

Groundwater is the primary source of drinking water within the project area. The South Tahoe Public Utility District provides drinking water to the project area.

2.8.2.2. Beneficial Uses of Surface Water

Beneficial uses are critical to water quality management in California. State law defines beneficial uses of California's waters that may be protected against quality degradation to include (but not be limited to): "domestic; municipal; agricultural and industrial supply; power generation; recreation; aesthetic enjoyment; navigation; and preservation and enhancement of fish, wildlife, and other aquatic resources or preserves" (California Water Code Section 13050[0]). Protection and enhancement of existing and potential beneficial uses are the primary goals of water quality planning. Substantial points concerning the concept of beneficial uses include the following:

- All water quality problems can be stated in terms of whether there is water of sufficient quantity or quality to protect or enhance beneficial uses.
- Beneficial uses do not include all of the reasonable uses of water. For example, disposal of wastewaters is not included as a beneficial use. This is not to say that disposal of wastewaters is a prohibited use of waters of the state; it is merely a use that cannot be satisfied to the detriment of beneficial uses. Similarly, the use of water for the dilution of salts is not a beneficial use, although it may, in some cases, be a reasonable and desirable use of water.
- The protection and enhancement of beneficial uses require certain quality and quantity objectives to be met for surface water and groundwater.
- Fish, plants, and other wildlife, as well as humans, use water beneficially.

Section 305(b) of the CWA mandates biennial assessment of the nation's water resources. These water quality assessments are used to identify and list waters that do not meet water quality standards. The resulting list is referred to as the 303(d) list. The CWA also requires states to establish a priority ranking for these impaired waters, and to develop and implement total maximum daily loads (TMDLs). A TMDL specifies the maximum amount of a pollutant that a water body can receive

and still meet water quality standards. Section 303(d)-listed water bodies within the project area include the Upper Truckee River and its tributary, Big Meadow Creek.

Upper Truckee River

The Truckee River was first included on the 1992 Section 303(d) list for impairment due to excessive sedimentation. The Truckee River and its tributaries are highly valued by the local and visiting communities. Much of the region's economic productivity depends upon the river's high quality, naturally functioning, and aesthetic water resources.

According to the Basin Plan, the Truckee River supports the following beneficial uses:

- Municipal and domestic supply
- Agricultural supply
- Groundwater recharge
- Water contact recreation
- Non-contact water recreation
- Commercial and sport fishing
- Freshwater replenishment
- Hydropower generation
- Cold freshwater habitat
- Wildlife habitat
- Rare, threatened or endangered species
- Migration of aquatic organisms
- Spawning, reproduction, and development
- Water quality enhancement
- Flood peak attenuation/flood water storage.

Increased sedimentation has been linked to the impairment of these beneficial uses (CCPDR, LRWQCB, and TRWC 2002).

2.8.3. Impacts

The potential impacts to surface waters would be temporary and would generally occur during construction activities near or directly within waterways.

The goal of the proposed project is to improve the quality of the storm water runoff from the highway before it reaches the waterways within the vicinity of US 50, with the overall goal to improve the water quality of Lake Tahoe. The lake is the receiving

water body of the majority of the existing waterways within the project limits. The proposed project also has the potential for adverse effects from the installation of the proposed facilities and roadway improvements. The following sections summarize the potential for adverse effects.

Construction Impacts

The project will involve construction of infiltration basins and installation of sand traps and other drainage facilities. As a result of these proposed project activities, vegetation clearing and excavation would take place directly alongside the existing roadway and extending outward where infiltration basins are installed. There would be an increased potential for soils exposed during construction activity to be transported to adjacent surface water bodies and/or open drainage channels that cross the roadway, either by wind erosion or storm runoff. The major categories of construction impacts are discussed below.

Vegetation Removal and Excavation Activities

Construction activities would require equipment staging areas and stockpiling of materials, access to the construction site, site clearance, and grading and excavation. This work would take place within and along the existing roadway, within areas where the shoulders provide sufficient room, within the state right-of-way, or within temporary construction easements. Where vegetation is cleared and grading/excavation is necessary, the potential for soil erosion is increased. Areas most vulnerable to erosion include sections of the roadway with side slopes in steep terrain. Eroded soils that leave the construction sites would have an adverse effect on existing water quality. These activities would be subject to the Caltrans NPDES permit, which applies to all construction activities exceeding 1 acre in size. The permit requires a SWPPP that contains specific erosion control measures, which apply throughout the construction period. These requirements would minimize erosion during the construction period.

Erosion at Drainage Channels and Culverts

Annual and seasonal drainages within the project area intersect or run along US 50. Culverts beneath the roadway currently convey flow in most of these channels from reaches uphill of the roadway to reaches downhill of the roadway. Existing culverts along this roadway segment are planned for replacement as needed. This would require excavation of an existing culvert and replacement at the same location, or installation of a new culvert directly adjacent, with redirection of the stream flow after completion of the installation. There is a potential for addition of sediment to the

water from excavations in and around stream banks and during backfill of soil materials.

Creation of Additional Sources of Polluted Runoff

The water released or coming out of the proposed basins and storm water collection facilities would have reduced sediments and pollutant concentrations. However, where storm water runoff is collected or is more concentrated, there is an increased potential for erosion, such as areas of exposed soils or basin outlets. To avoid these effects, the soil and erosion protection measures discussed in Section 2.8.4 would be incorporated into the project design.

The project would not increase traffic volumes, as it would not increase the roadway capacity of US 50, and therefore would not affect total pollutant emissions or loadings related to vehicle emissions.

Section 303(d) Water Body Impacts/Avoidance

No waterways within the project limits are listed in the CWA's 303(d) list of Water Quality Limited Segments. The Upper Truckee River is outside of the project limits and separated from US 50 by the Lake Tahoe Airport. The project will improve the quality of storm water runoff from the highway and will not adversely affect the Upper Truckee River or any other listed Section 303(d) water bodies. The project SWPPP will contain BMPs for erosion and sediment control as necessary to avoid or minimize any increased erosion potential during construction.

Potential Impacts to Groundwater

The project would include features such as sand traps and infiltration basins that capture surface water runoff, and retain or temporarily detain the water flow within the state right-of-way to remove sediments and pollutants. These facilities would improve surface water quality leaving the right-of-way, but would also increase the amount of surface water that percolates to groundwater through infiltration. The allowable pollutant levels in this infiltrating water could be bound by TRPA Threshold WQ6, which establishes standards for allowable levels of total nitrogen, total phosphorus, total iron, turbidity, and grease and oil in surface discharge to groundwater.

Overall, the proposed project would not adversely affect pollutant loads in groundwater. The proposed improvements will divert, collect, and treat storm water runoff from road surfaces that would otherwise directly infiltrate or percolate into the Tahoe area aquifers. Implementing the proposed project would increase the amount of

sediment-entrained pollutants that would be filtered out of surface water in sand traps and infiltration basins or meandering ditches; this would help reduce or remove these pollutants from entering groundwater. Pollutants added to groundwater from percolation from new infiltration basins would be a minor source because the streams that recharge groundwater aquifers in the Tahoe area receive substantial water from sources outside of the project limits (i.e., the general watershed, outside of the right-of-way and roadway surfaces of US 50) in comparison to the area actually affected within the proposed right-of-way. Therefore, the project would not affect pollutant loads in groundwater.

TRPA Considerations

The project will provide storm water treatment along US 50. Newly installed drainage facilities will capture many pollutants before they enter area waterways. No adverse effects are anticipated.

2.8.4. Avoidance, Minimization and/or Mitigation Measures

The project would have a beneficial effect on the quality of storm water runoff; however, as for any major construction project, there is the potential for some adverse effects. Avoidance and minimization of water quality impacts are conditions of the NPDES permit, TRPA permit, and LRWQCB, El Dorado County, and Caltrans requirements. Implementation details for these measures will be developed and incorporated into project design and operations prior to project startup, and into the project SWPPP. With proper implementation of these measures, temporary and permanent construction-related water quality impacts will be avoided or minimized.

WS-1 Construction Measures

Soil erosion protection measures are recommended at sites with cross-culverts that are proposed for replacement or widening. Geotextile fabrics and erosion control blankets/mats are suggested BMPs that can be installed. In addition, a line of stacked sandbag/gravel bag berms can be placed along the channel banks to intercept and slow the flow of sediment-laden sheet flow runoff on road surfaces.

In addition, the following measures would be applied:

- TRPA and LRWQCB regulations limit grading to 3 cubic yards from October 15 to May 1 of each year. Unless a variance is obtained, construction activities will conform to this requirement.
- Pollution prevention measures will be implemented to protect surface water quality degradation to the existing surface water resources within the US 50

project limits, and to prevent erosion of bare soils and potential non-point source pollutant contribution.

Other construction BMPs may be considered where proposed modifications or grading of slopes may increase runoff and expose soils. Diversion of runoff may be considered during construction where it is necessary to direct storm water flow around a construction site. Temporary dewatering of a construction site may be necessary to remove accumulated storm water runoff.

WS-2 Groundwater Measures

The project is not anticipated to encounter groundwater, as excavation work should be minimal. However, if construction encounters groundwater or may involve non-storm water discharges, consultation with the LRWQCB or California Department of Toxic Substances Control may be appropriate. A project-specific Waste Discharge Permit may be required if substantial dewatering will take place.

2.9. Soils, Soil Conservation, and Geology

2.9.1. Regulatory Setting

The CEQA Checklist (Appendix B) identifies potential issues that could lead to a significant impact pursuant to CEQA, including soil erosion and location on unstable or expansive soils. Topographic and geologic features are also protected under CEQA.

The following TRPA Thresholds apply to soil conservation:

- SC1: The TRPA threshold for soil conservation requires that impervious coverage comply with the coverage coefficients defined in the *Land-Capability Classification of the Lake Tahoe Basin, California-Nevada: A Guide to Planning* (Bailey 1974). Additional land coverage is monitored on a project basis and recorded in square feet. Coverage may be utilized directly or by coverage transfers within a related project area. An excess coverage mitigation program is in place to gradually reduce existing land coverage.
- SC2: TRPA policy requires the preservation of existing naturally functioning SEZ lands in their natural hydrologic condition; the restoration of all disturbed SEZ lands in undeveloped, un-subdivided lands; and the restoration of SEZ lands that have been identified as disturbed, developed or subdivided to obtain a 5 percent total increase in the area of naturally functioning SEZ lands.

2.9.2. Affected Environment

2.9.2.1. Soils and Soil Conservation

US 50 traverses many soil associations within the project study limits (USDA 1974). The soils are: Elmira gravelly loamy coarse sand, 0 to 9 percent slopes (EbC); Elmira-Gefo loamy coarse sands, 0 to 5 percent slopes (EfB); Elmira loamy coarse sand, wet variant (Ev); Gefo gravelly loamy coarse sand, 2 to 9 percent slopes (GeC); Jabu coarse sandy loam, 0 to 9 percent slopes (JaC); Jabu sandy loam, moderately fine subsoil variant, 0 to 9 percent slopes (JgC); and Pits and Dumps (Px).

Land capability districts (LCDs) have been determined for all areas within the Tahoe Basin. Land capability is “the level of use an area can tolerate without sustaining permanent (environmental) damage through erosion or other causes” (Bailey 1974).

A review of published data such as California Geologic Survey (CGS) publications and U.S. Department of Agriculture Natural Resources Conservation Service soil surveys, a review of previous site explorations, and a site reconnaissance were conducted for the proposed project. No subsurface exploration or laboratory testing was performed.

2.9.2.2. Geology and Seismic

Human-Made and Natural Features

US 50 was constructed with cuts and fills. Existing cuts are in hard rock (granite), glacial till, or mixed hard rock and glacial till. The existing highway crosses numerous drainages of varying size with associated culverts and bridges.

Site Geology

The project area is located on Quaternary-aged lake deposits, glacial till deposits, and Mesozoic granitic rocks (CGS 1987). Depth to competent bedrock varies throughout the project limits.

Naturally occurring asbestos is not found in the project area (CGS 2000a, 2000b; Caltrans 2001).

Faulting and Seismicity

The Lake Tahoe Fault is located northwest of US 50 Segment 2 (Caltrans 1996). This fault could produce a maximum credible earthquake (MCE) of magnitude 6.5. The MCE from this fault would result in a peak horizontal bedrock acceleration of approximately 0.4 g (g = acceleration due to gravity) in the area (Caltrans 2003b).

2.9.3. Impacts

New drainage features will create additional hard coverage and changes to the existing landscape. However, these changes are not expected to result in substantial impacts pursuant to CEQA or TRPA. The existing geology has been considered during the project design process. Areas that are not suitable for water quality treatment features, either due to incompatible terrain or existence of wetlands, marshes, and/or SEZs, were eliminated from consideration.

2.9.3.1. Soils and Soil Conservation

TRPA Considerations

TRPA's primary concern regarding soils is potential creation of additional coverage.

In accordance with Chapter 20.3.B(8) of the TRPA Code of Ordinances, the proposed infiltration basins will create impervious coverage that is exempt from the Bailey land coverage limits. Coordination with TRPA on similar storm water quality projects determined that maintenance access areas adjacent to these structures are not exempt.

The addition of asphalt concrete and the placement of structures during the installation of drainage improvements and construction of maintenance pullouts are expected to increase impervious land coverage within the project area. Revegetation of these areas may be infeasible because these areas will be converted to "hard" impervious surfaces. In addition, areas of SEZ land, LCD 1b, will be disturbed by additional coverage (fills and structures).

Construction of infiltration basins, basin access routes, and culvert outfall areas will require vegetation removal but will be revegetated with native plants and grasses upon completion. Vegetation removal and subsequent revegetation by applying appropriate (non-impervious) erosion control materials will be determined by the Caltrans Landscape Architecture branch in conjunction with TRPA.

Additionally, existing soft coverage areas (typically compact unvegetated soils) within the project area are proposed to be restored by applying appropriate (non-impervious) erosion control materials, as determined by the Caltrans Landscape Architecture branch in conjunction with TRPA.

TRPA is concerned about how to prevent new coverage from being created as a result of the project, because there is a potential for soft coverage to increase. In areas where spot shoulder widening is planned, automobiles may continue to park off pavement and create new areas of compacted dirt and disturbance to adjacent lands.

To help prevent autos from creating new areas of coverage, rock-embedded berms may be incorporated, to the extent feasible, just outside of the clear recovery zone. Other methods that will be installed closer to the edge of pavement to prevent parking will include bollards and landscaping.

2.9.3.2. Geology and Seismic

If located on potentially unstable soils, proposed structures that could present landslide, rockfall, liquefaction, or erosion hazards could require geotechnical investigation. Geotechnical investigations of the proposed infiltration basins have already been completed.

TRPA Considerations

The TRPA Parcel Evaluation System does not apply to this water quality improvement project. The project will require minor grading to develop drainage basins, install sand traps, and stabilize slopes.

The excavation of slopes will be necessary at some locations. Soil conservation measures will be employed as necessary. The project will not result in the modification of a channel of a river or stream, sandy beach, or lake bed, nor will it increase exposure of people or structures to geologic hazards.

2.9.4. Avoidance, Minimization and/or Mitigation Measures

SC-1 Purchase of Land Coverage Credits

Land coverage credits would be purchased to offset the increased pavement area that would result from the proposed construction of maintenance pullouts. According to TRPA Code Section 20.3C(3), land transfers to provide coverage for low-capability lands, LCDs 1-3, must be permanently retired as set forth in TRPA Code Section 20.3C(7). Caltrans is not on the TRPA individual parcel system and is creating coverage within state right-of-way or within land on which highway agreements exist. Any land transfer would be performed under the guidance of the California Tahoe Conservancy, a State of California land bank administration agency. Caltrans has existing coverage credits at the Conservancy's land bank via a Memorandum of Understanding dated October 18, 2000.

SC-2 Geotechnical Investigations

Proposed structures could require geotechnical investigation if they are located on potentially unstable soils and could present landslide, rockfall, liquefaction, or erosion hazards. The results of such investigations would be used in the design of individual project elements to ensure that there would be no adverse effects.

2.10. Hazardous Waste / Materials

2.10.1. Regulatory Setting

Hazardous materials and hazardous wastes are regulated by many state and federal laws. These laws include not only specific statutes governing hazardous waste but also a variety of laws regulating air and water quality, human health, and land use.

The primary federal laws regulating hazardous wastes/materials are the Resource Conservation and Recovery Act of 1976 and the Comprehensive Environmental Response, Compensation and Liability Act of 1980. The purpose of the latter act, often referred to as Superfund, is to clean up contaminated sites so that public health and welfare are not compromised. The Resource Conservation and Recovery Act provides for “cradle to grave” regulation of hazardous wastes. Other federal laws include:

- Community Environmental Response Facilitation Act of 1992
- CWA
- Clean Air Act
- Safe Drinking Water Act
- Occupational Safety and Health Act
- Atomic Energy Act
- Toxic Substances Control Act
- Federal Insecticide, Fungicide, and Rodenticide Act.

In addition to the acts listed above, Executive Order 12088, Federal Compliance with Pollution Control, mandates that necessary actions be taken to prevent and control environmental pollution when federal activities or federal facilities are involved.

Hazardous waste in California is regulated primarily under the authority of the Federal Resource Conservation and Recovery Act of 1976 and the California Health and Safety Code. Other California laws that affect hazardous waste are specific to handling, storage, transportation, disposal, treatment, reduction, cleanup and emergency planning.

Worker health and safety and public safety are key issues when dealing with hazardous materials that may affect human health and the environment. Proper disposal of hazardous material is vital if it is disturbed during project construction.

TRPA does not maintain any thresholds for hazardous waste. The TRPA Initial Environmental Checklist questions whether the project will result in the risk of hazardous material spills or exposure to health hazards.

2.10.2. Affected Environment

As described in the Initial Site Assessment for the proposed project (Caltrans 2007d), a hazardous waste evaluation was conducted and involved the following:

- A review of the project plans and aerial mapping
- Discussions with the Project Engineer and Environmental Coordinator on project work scope
- A site field review
- An Environmental Data Resources (EDR), Inc. (an environmental information database) records search
- Discussions with regulatory agencies.

2.10.3. Impacts

The hazardous waste evaluation identified the potential for contamination along US 50 within the project limits. Soils contaminated with aerially deposited lead (ADL) may exist within and near the state right-of-way due to the past use of leaded fuels. The areas of primary concern in relation to highway facilities are soils along routes with historically high vehicle emissions due to large traffic volumes, congestion, or stop-and-go conditions. ADL from vehicle emissions would have been deposited prior to 1986 when nearly all lead was removed from gasoline in California. A Preliminary Site Investigation for ADL was conducted in June 2004. ADL was detected at non-hazardous levels.

Table 2.10-1 lists the sites within the project limits (just south of the US 50/SR 89 junction) that have been identified as having potential contamination.

Table 2.10-1 Potential Contamination Sites within the US 50 Segment 2 Project Limits

Site Name	Address	Issue
Unknown Source at North Highway 50/89 Junction	Unknown Source at Highway 50/89 Junction	TCE/PCE Plume in groundwater
Former South Y Shell	1020 Emerald Bay Road	Fuel contamination
Former National Car Rental	1101 Emerald Bay Road	Fuel contamination
American Oil Gas Station	1140 Emerald Bay Road	Fuel contamination

Construction activities within these areas have the potential to encounter contaminated soil or groundwater.

The project contractor will likely use staging areas for equipment and materials, which can pose a threat to soil or water contamination if not contained. The presence of these materials along a state highway or used during construction are not unusual, but must be handled appropriately prior to or during construction.

The Project Study Report (Caltrans 2003a) also identified the removal and disposal of yellow thermoplastic lane striping, which may contain heavy metals, as a potential hazard.

TRPA Considerations

Changes in the potential for risks of spills would only be associated with project construction, and the construction contractors will be required to comply with all regulatory and Caltrans safety requirements. The project would not create any potential new health hazards.

2.10.4. Avoidance, Minimization and/or Mitigation Measures

HZ-1 Lead-Contaminated Soils

Because ADL was found to exist at non-hazardous levels, a modified version of Caltrans Non Standard Special Provisions (N-SSP # 07-330) will be included for this project. The N-SSP addresses the need for a lead compliance plan and other factors. This process would be performed during the Plans, Specifications and Estimates stage.

HZ-2 Subsurface Soil Contamination

If any soil disturbance activities are planned during construction adjacent to the sites identified above as having potential contamination, a site investigation may be required to determine if any contamination is present.

HZ-3 Disposal of Removed Materials

Any removal of yellow thermoplastic lane striping must be performed in accordance with a Lead Compliance Plan and disposed of at a Class I disposal facility.

2.11. Air Quality

2.11.1. Regulatory Setting

CEQA requires consideration of whether a project could conflict with or obstruct implementation of an air quality plan, cause or substantially contribute to an exceedance of any air quality standard, result in a cumulative net increase in any

criteria air quality pollutant, or expose people to substantial pollutant concentrations or odors.

Air quality regulations applicable to this project are established through both the Federal Clean Air Act of 1990 and the California Clean Air Act of 1988, as amended. The USEPA regulates compliance with federal standards. The California Air Resources Board (CARB) promulgates the state air quality standards and oversees the activities of the local Air Quality Management and Air Pollution Control Districts. The TRPA has regional jurisdiction over air quality in the bi-state Lake Tahoe Air Basin. The TRPA regulates most air pollutant sources with the exceptions of motor vehicles, locomotives, aircraft, agriculture (forestry) equipment, and marine vessels. State and local government projects, as well as those funded by the private sector, are subject to the requirements of the TRPA.

The following TRPA thresholds would apply to the current project:

- AQ1: Carbon monoxide levels shall not exceed the TRPA 8-hour 6.0 parts per million (ppm) standard.
- AQ2: Ozone levels shall not exceed the TRPA 1-hour standard of 0.08 ppm.
- AQ3: Particulate matter concentrations shall not exceed the California and federal standards for 24-hour concentrations and the annual average.
- AQ4: TRPA's regional and sub-regional visibility standards shall not be violated. In addition, for regional and sub-regional visibility, wood smoke concentrations shall be reduced 15 percent below the 1981 levels and for sub-regional visibility suspended soil particles shall be reduced 30 percent below the 1981 levels.
- AQ7: Vehicle Miles Traveled (VMT) shall be reduced 10 percent below 1981 levels.
- AQ8: Dissolved inorganic nitrogen load on Lake Tahoe from atmospheric sources shall be reduced by approximately 20 percent of the 1973–1981 annual average.

2.11.2. Affected Environment

Air Quality Standards

Applicable federal and state air quality standards have been established for six criteria pollutants: carbon monoxide (CO), nitrogen dioxide (NO₂), ozone (O₃), particulate matter, lead, and sulfur dioxide (SO₂). These standards are summarized in Table 2.11-1.

Current Air Quality Regulatory Status in the Project Area

The USEPA classifies air basins (or portions thereof) as “attainment,” “nonattainment,” or “unclassified” for each criteria air pollutant, based on whether or

not the National Ambient Air Quality Standard has been consistently achieved. The USEPA has classified the Lake Tahoe Air Basin as being in attainment of the federal standards for all of the criteria pollutants.

Table 2.11-1 Federal and California Ambient Air Quality Standards

Pollutant	Averaging Time	Federal ^a	State
Ozone (O ₃)	1 Hour	None ^d	0.09 ppm
	8 Hour	0.08 ppm	0.07 ppm ^c
Particulate Matter (PM ₁₀)	24 Hour	150 µg/m ³	50 µg/m ³
	Annual Average	50 µg/m ³	20 µg/m ³
Fine Particulate Matter (PM _{2.5})	24 Hour	65 µg/m ³	None
	Annual Average	15 µg/m ³	12 µg/m ³
Carbon Monoxide (CO)	1 Hour	35 ppm	20 ppm
	8 Hour	9 ppm	9.0 ppm
Nitrogen dioxide (NO ₂)	1 Hour	None	0.25 ppm
	Annual Average	0.053 ppm	None
Lead (Pb)	30 days	None	1.5 µg/m ³
	Calendar Quarter	1.5 µg/m ³	None
Sulfur Dioxide (SO ₂)	1 Hour	None	0.25 ppm
	3 Hour	0.5 ppm ^b	NA
	24 Hour	0.14 ppm	0.04 ppm
	Annual Average	0.03 ppm	None
Sulfates	24 Hour	None	25 µg/m ³
Hydrogen Sulfide	1 Hour	None	0.03 ppm
Visibility-Reducing Particles	8 Hour	None	Extinction coefficient of 0.23 per km
Vinyl Chloride	24 Hour	None	0.01 ppm

Source: CARB 2005

Notes:

- a. Primary National Ambient Air Quality Standard unless otherwise noted
- b. Secondary National Ambient Air Quality Standard
- c. Approved by CARB on April 2005
- d. 1-hour ozone standard revoked June 5, 2005, except for areas that do not yet have an effective date for their 8-hour designations.

µg/m³ = microgram(s) per cubic meter

ppm = parts per million

California has established its own ambient air quality standards for criteria air pollutants that are, in general, more stringent than the federal standards. Of the criteria pollutants that have been classified, the Lake Tahoe Air Basin is in attainment of the California ambient air quality standards except for the California 24-hour standard for particulate matter less than 10 microns in diameter (PM₁₀). The Lake Tahoe Air Basin has not been classified for visibility-reducing particles and hydrogen sulfide because insufficient data are available to determine whether or not the pollutant concentrations are in attainment of the regulatory standards. In the past, there have been exceedances of the California 8-hour ozone standard. However, the Lake Tahoe Air Basin is still classified as being in attainment of the 8-hour ozone standard because the exceedances have not been frequent or significant enough to change the basin's attainment status.

The TRPA, along with the Nevada Division of Environmental Protection and CARB, maintains ambient air quality monitoring stations at numerous locations throughout the air basin. The stations are used to monitor the concentration of criteria pollutants and to assist in the classification of the attainment status of the air basin.

The TRPA has adopted a regional transportation plan–air quality plan (TRPA 1992) that focuses on attaining the federal and state air quality standard. Within the plan, TRPA has established a set of air quality thresholds that tend to be equivalent to or more stringent than the federal and state air quality standards.

No TRPA standards have been set for NO₂ and SO₂. However, the concentrations of these criteria pollutants must still comply with federal and state ambient air quality standards.

Existing Air Quality

The two air quality monitoring stations nearest the project limits are at Echo Summit and at the Lake Tahoe Airport. Monitoring data from 2003 through 2005 show that ambient O₃ levels had recorded exceedances of the state and TRPA O₃ standards, but the violations of the standards were not large or frequent enough for the USEPA or CARB to classify the Lake Tahoe Air Basin as being in nonattainment of these standards. The 24-hour state PM₁₀ standard was exceeded in 2003 in the South Lake Tahoe area for about 6 days, resulting in a classification of nonattainment. There were no exceedances of this standard in 2004 or 2005, and there have been no violations of the federal or state standards for PM_{2.5} for the last 5 years.

2.11.3. Impacts

Potential Project Impacts to Air Quality

Potential air quality impacts from the project would be limited to construction activities. Dust emissions from construction would result from earthmoving and heavy equipment use, including land clearing, ground excavation, cut and fill, and general roadbed construction activities. Excavation and earthwork would be necessary for installation of pavement, basins, water collection and control devices, and similar facilities. The contractors may use controlled blasting where existing rock prevents or substantially impairs excavation. In addition to particulate emissions, combustion emissions from construction equipment would occur. All of these activities and effects would be temporary. Thus, the impacts would be temporary both in time and location.

This project would not increase the total traffic volume in the project area. Following the completion of construction, the existing number of through travel lanes would be the same as prior to construction. Consequently, the project would not introduce any additional permanent vehicular emission sources, and there will be no post-construction effects to air quality.

The project would not affect highway truck or diesel emissions or mobile source air toxics. Although particulate matter may be generated during construction, the project would not affect vehicular PM_{2.5} or PM₁₀ emissions and would not require a particulate matter hot-spot evaluation.

TRPA Considerations

Potential air quality effects are only associated with construction, primarily dust and construction equipment emissions. The project would not affect any TRPA thresholds or air quality standards.

2.11.4. Avoidance, Minimization and/or Mitigation Measures

The proposed project is expected to generate suspended particulate matter from construction activities. The TRPA regulates particulate matter emissions due to construction activities by requiring that projects that involve the creation or relocation of land coverage submit a construction permit that details the dust control measures that would be applied during construction. The construction contractor would be required to apply for and to obtain the two TRPA permits (Erosion Control and Linear Public Service Project). The following measures will be implemented to avoid or minimize construction-related air quality effects.

AQ-1 Control Dust from Construction Activities

Typical dust control practices that may be required to reduce the amount of dust from construction emissions may include, but are not limited to, the following measures:

- Covering open-bodied trucks when used for transporting materials likely to give rise to airborne dust
- Watering disturbed (graded or excavated) surfaces as necessary, increasing frequency when weather conditions require
- Watering disturbed areas to form a compact surface after grading and earth working; using chemical dust suppressants when watering is not sufficient
- Limiting areas to be cleared to facilities required for the project and necessary equipment and materials stockpile areas

- Limiting the speed of construction equipment and vehicles on unpaved roads when conditions require
- Erosion control planting of exposed slopes after construction; and incorporating standard erosion control measures as part of the contract.

The dust control activities will comply with Section 10 of the Caltrans Standard Construction Specifications (Caltrans 2006a) and will be reviewed and approved of by TRPA.

AQ-2 Reduce Emissions from Construction Equipment

The following measures can reduce pollutant emissions in construction equipment exhaust:

- Keeping engines properly tuned
- Limiting engine idling
- Avoiding unnecessary concurrent usage of equipment.

2.12. Climate Change

2.12.1. Regulatory Setting

While climate change has been a concern since at least 1988 as evidenced by the establishment of the United Nations and World Meteorological Organization's Intergovernmental Panel on Climate Change (IPCC), the efforts devoted to greenhouse gas² (GHG) emissions reduction and climate change research and policy has increased dramatically in recent years. In 2002, with the passage of Assembly Bill (AB) 1493, California launched an innovative and proactive approach to dealing with GHG emissions and climate change at the state level. AB 1493 requires the CARB to develop and implement regulations to reduce automobile and light truck GHG emissions. These regulations will apply to automobiles and light trucks beginning with the 2009 model year.

On June 1, 2005, Governor Arnold Schwarzenegger signed Executive Order S-3-05. The goal of this Executive Order is to reduce California's GHG emissions to: 1) 2000 levels by 2010; 2) 1990 levels by the 2020; and 3) 80 percent below the 1990 levels by the year 2050. In 2006, this goal was reinforced with the passage of AB 32, the Global Warming Solutions Act of 2006. AB 32 sets the same overall GHG emissions

² Greenhouse gases related to human activity include carbon dioxide, methane, nitrous oxide, tetrafluoromethane, hexafluoroethane, sulfur hexafluoride, trifluoromethane (HFC-23), 1,1,1,2-tetrafluoroethane (HFC-134a), and 1,1-difluoroethane (HFC-152a).

reduction goals and mandates that CARB create a plan that includes market mechanisms and implement rules to achieve “real, quantifiable, cost-effective reductions of greenhouse gases.” Executive Order S-20-06 directs state agencies to begin implementing AB 32, including the recommendations made by the state’s Climate Action Team.

Climate change and GHG emissions reduction are also a concern at the federal level; however, at this time, no legislation or regulations have been enacted that specifically address these issues.

2.12.2. Affected Environment

According to a recent white paper by the Association of Environmental Professionals (Hendrix and Cori 2007), “An individual project does not generate enough greenhouse gas emissions to significantly influence global climate change. Global climate change is a cumulative impact; a project participates in this potential impact through its incremental contribution combined with the cumulative increase of all other sources of greenhouse gases.”

Caltrans and its parent agency, the Business, Transportation, and Housing Agency, have taken an active role in addressing GHG emission reduction and climate change. Recognizing that 98 percent of California’s GHG emissions are from the burning of fossil fuels and 40 percent of all human made GHG emissions are from transportation, Caltrans has created and is implementing the *Climate Action Program at Caltrans* (Caltrans 2006b).

One of the main strategies to reduce GHG emissions is to make California’s transportation system more efficient. The highest levels of carbon dioxide from mobile sources, such as automobiles, occur at stop-and-go speeds (0 to 25 miles per hour) and speeds over 55 miles per hour. Relieving congestion by enhancing operations and improving travel times in high-congestion travel corridors will lead to an overall reduction in GHG emissions.

2.12.3. Conclusion

Caltrans recognizes the concern that carbon dioxide emissions raise for climate change. However, modeling and gauging the impacts associated with an increase in GHG emissions levels, including carbon dioxide, at the project level is not currently possible. No federal, state or regional regulatory agency has provided methodology or criteria for GHG emission and climate change impact analysis. Therefore, Caltrans is

unable to provide a scientific or regulatory based conclusion regarding whether the project's contribution to climate change is cumulatively considerable.

Caltrans continues to be actively involved on the Governor's Climate Action Team as CARB works to implement AB 1493 and AB 32. As part of the *Climate Action Program at Caltrans* (December 2006), Caltrans is supporting efforts to reduce vehicle miles traveled by planning and implementing smart land use strategies: job/housing proximity, developing transit-oriented communities, and high-density housing along transit corridors. Caltrans is working closely with local jurisdictions on planning activities; however, Caltrans does not have local land use planning authority. Caltrans is also supporting efforts to improve the energy efficiency of the transportation sector by increasing vehicle fuel economy in new cars and light- and heavy-duty trucks. However, it is important to note that the control of the fuel economy standards is held by the USEPA and CARB. Lastly, the use of alternative fuels is also being considered; Caltrans is participating in funding for alternative fuel research at the University of California Davis.

2.13. Noise

2.13.1. Regulatory Setting

Federal, state, and local laws, regulations, and ordinances provide the basis for analyzing and abating highway traffic noise effects. The intent of these laws is to promote the general welfare and to foster a healthy environment, as summarized in the following subsections.

California Environmental Quality Act

CEQA requires a strictly no-build versus build analysis to assess whether a proposed project will have a noise impact. If a proposed project is determined to have a significant noise impact under CEQA, then CEQA dictates that mitigation measures must be incorporated into the project unless such measures are not feasible.

Tahoe Regional Planning Agency

The TRPA establishes noise limitations in Chapter 23 of the Code of Ordinances. These limitations are applicable to single-event noises from aircraft, marine crafts, motor vehicles, motorcycles, off-road vehicles, and over-snow vehicles. The limitations also apply to community noise levels in the Tahoe Region. TRPA-approved construction is specifically exempted from these provisions provided that construction activities are limited to between the hours of 8:00 a.m. and 6:30 p.m.

In addition, TRPA has established noise thresholds in three categories. Only one applies to this project: Threshold N-3, Community Noise Equivalent Levels (CNELs). TRPA applies different maximum CNELs, measured in A-weighted decibels (dBA) over a 24-hour period, to different land uses. The maximum CNEL is generally 50 dBA for conservation areas, 55 dBA for high-density residential and highway areas, and 60 dBA for commercial areas. CNELs may vary slightly depending on location.

TRPA has also determined maximum CNELs for its Plan Area Statements for specific areas. The four PASs that apply to the regional area crossed by US 50 Segment 2 and the corresponding maximum CNEL dBA levels are:

- PAS #110 – South “Y,” along US 50 corridor: 65 dBA
- PAS #114 – Bonanza, along US 50 corridor: 65 dBA
- PAS #116 – Airport: 65 dBA
- PAS #119 – Country Club Meadow, along US 50 corridor: 65 dBA

CNEL represents an average noise level over a 24-hour period with the addition of 5 dBA to noise generated in the evening and 10 dBA for noise generated during the nighttime period. These noise level additions, or “penalties,” account for higher sensitivity to noise generated during normally very quiet periods.

South Lake Tahoe General Plan

According to the 1999 South Lake Tahoe General Plan, potential noise is limited by the TRPA PASs to specific areas. Within each PAS, a maximum CNEL is established for that PAS or individual uses based on TRPA threshold numerical standards for cumulative noise events as discussed above.

2.13.2. Affected Environment

Within the project limits, existing land uses are predominantly commercial and residential, both of which are typically located at least 100 feet from the roadway center. Existing noise along the project alignment results primarily from vehicular traffic along US 50. Noise generated by operations associated with the Lake Tahoe Airport also contributes to the ambient noise environment within the project limits. Traffic volume data published by Caltrans were used to calculate typical daytime noise levels along this segment of the highway (Table 2.13-1).

**Table 2.13-1 Typical Daytime Noise Levels Estimated from
Average Daily Traffic**

Segment	Segment Description	Typical Daytime Noise Levels at 100 Feet from Roadway Center
US 50 Segment 2	South Tahoe Airport to Junction 50/89	68 dBA L_{eq}

Source: 2005 Annual Average Daily Truck Traffic on the California State Highway System, Department of Transportation, November 2006.

L_{eq} = Noise expressed as the energy average of the A-weighted decibel occurring during a one-hour period.

Common Noise Levels

Table 2.13-2 lists noise levels of common activities in dBA to enable readers to compare the actual and predicted highway noise levels discussed in this section with common activities.

Table 2.13-2 Typical Noise Levels in the Environment

Common Outdoor Noise Source	Noise Level (dBA)	Common Indoor Noise Source
Jet fly-over at 980 feet	120 dBA	Rock concert
	110 dBA	
Pile driver at 70 feet	100 dBA	Night club with live music
	90 dBA	
Large truck pass-by at 50 feet	80 dBA	Noisy restaurant
	70 dBA	Garbage disposal at 3 feet
Gas lawn mower at 100 feet	70 dBA	Vacuum cleaner at 10 feet
Commercial/Urban area daytime		Normal speech at 3 feet
Suburban expressway at 300 feet	60 dBA	Active office environment
Suburban daytime	50 dBA	
Urban area nighttime	40 dBA	Quiet office environment
	40 dBA	
Suburban nighttime		Library
Quiet rural areas	30 dBA	Quiet bedroom at night
	20 dBA	
Wilderness area	20 dBA	
Most quiet remote areas	10 dBA	Quiet recording studio
Threshold of human hearing	0 dBA	Threshold of human hearing

2.13.3. Impacts

Construction Activity and Noise Levels

Construction would generate noise and temporarily increase noise levels at adjacent land uses. These levels are normally highest during the demolition and earthwork phases of construction because of heavy equipment and impact tools required to

complete the work. These phases of construction normally generate the highest noise levels over extended periods of time.

Typical hourly average noise levels resulting from the construction of roadways, sewers, and trenches are about 79 dBA to 88 dBA L_{eq} measured at a distance of 50 feet from the center of the site during busy construction periods. Variations in construction noise levels would occur on a day-to-day basis depending on the activities occurring at the work site. Table 2.13-3 summarizes the typical range of average noise levels that could be expected during project construction phases.

Table 2.13-3 Typical Ranges of Energy Equivalent Noise Levels at 50 Feet, in dBA L_{eq} , at Construction Sites

Phase	Public Works Roads and Highways, Sewers, and Trenches	
	I	II
Ground Clearing	84	84
Excavation	88	78
Foundations	88	88
Erection	79	78
Finishing	84	84

I - All pertinent equipment present at site.

II - Minimum required equipment present at site.

Source: USEPA 1973

Maximum noise levels resulting from individual pieces of equipment range from about 74 dBA to 89 dBA measured at a distance of 50 feet from the construction equipment. Table 2.13-4 summarizes the typical range of maximum noise levels that could be expected with project construction equipment.

Construction-generated noise levels drop off at a rate of about 6 dBA per doubling of distance between the source and receptor. Shielding by buildings or terrain can substantially reduce construction noise levels at distant receptors.

Maximum and average noise levels generated by construction activities would intermittently exceed City of South Lake Tahoe noise standards (see discussion under TRPA Considerations below).

**Table 2.13-4 Maximum Noise Levels from Construction Equipment
at 50 Feet**

Equipment	Maximum Noise Levels at 50 Feet (dBA)
Dozer	88
Excavator	85
Elevating Scraper	89
Backhoe	84
Front End Loader	87
Water Truck	87
Tractor Trailer-20 CY	80
Crane	86
Compactor	82
Paver	85
Welding Machine	74
Generator	84
Drill Rig	88

Sources: National Cooperative Highway Research Program 1999; USEPA 1971.

Construction equipment would likely include air compressors, paving machines, forklift trucks, loaders, pavement grinders, dump trucks, trenching machines, compactors, and backhoes. Typical hourly average noise levels resulting from the construction of roadways, and trenches are about 73 dBA to 82 dBA measured at a distance of 100 feet. Maximum noise levels resulting from individual pieces of equipment range from about 68 dBA to 83 dBA measured at a distance of 100 feet. Hourly average noise levels could exceed 55 dBA L_{eq} within about 500 to 2,200 feet of the construction site during various activities, assuming no excess attenuation resulting from shielding or ground absorption. Maximum noise levels would exceed 75 dBA within approximately 250 feet of the loudest pieces of construction equipment.

Construction noise impacts primarily result when construction activities occur during noise-sensitive times of the day (early morning, evening, or nighttime hours); when the construction occurs in areas immediately adjoining noise-sensitive land uses; or when construction durations last over extended periods of time. Project construction activities are anticipated to affect a particular receiver or group of receivers for a period of time less than one construction season as work progresses along the highway. The impact would be avoided with required standard construction noise control measures at construction sites.

Post-Construction Noise

Noise levels along the project limits would be the same after construction is completed as before. The project will not change highway capacity or traffic flow to

any measurable extent that would have any effect on permanent noise levels. There would be no effects or change to the existing noise environment.

TRPA Considerations

As the project would not contribute any new traffic, it will not change traffic-related noise levels with respect to the TRPA CNEL noise thresholds. The noise thresholds could be exceeded at times of heavy or sustained construction activities. TRPA-approved construction projects are exempt from the TRPA Noise Ordinance if the construction activities occur between the daytime hours of 8:00 a.m. to 6:30 p.m. The contractor will be restricted to these time periods unless a variance to this ordinance is obtained.

2.13.4. Avoidance, Minimization and/ or Mitigation Measures

NO-1 Standard Noise Control Measures

Noise control will conform to the provisions of Section 7-1.01I, “Sound Control Requirements,” of the Caltrans Standard Specifications. Section 7-1.01I requires the Contractor to comply with all local sound control and noise level rules, regulations, and ordinances that apply to any work performed pursuant to the project. The following standard construction noise control measures would be implemented to control construction noise.

- Noise-generating activities will be restricted at the construction site or in areas adjacent to the construction site associated with the project to the hours of 8:00 a.m. to 6:30 p.m.
- Contractors will equip internal combustion engine-driven equipment with intake and exhaust mufflers that are in good condition and appropriate for the equipment.
- Contractors will limit or prohibit idling of internal combustion engines on equipment or vehicles that are not actively involved in construction activities.
- Staging of construction equipment will be avoided within 200 feet of residences and stationary noise-generating construction equipment, such as air compressors and portable power generators, will be located as far as practical from existing noise sensitive receptors.
- If necessary to avoid severe temporary noise impacts, temporary barriers may be used to screen stationary noise generating equipment when located immediately adjacent to noise sensitive land uses. The need for this measure would be determined by the resident engineer.

- A noise disturbance coordinator will be designated who would be responsible for responding to any local complaints about construction noise. The disturbance coordinator would determine the cause of the noise complaint (e.g., starting too early, bad muffler, etc.) and would require that reasonable measures warranted to correct the problem be implemented. A telephone number for the disturbance coordinator will be posted at a conspicuous location at the construction site and included in the notice sent to neighbors regarding the construction schedule.

Biological Environment

2.14. Natural Communities

This section discusses natural communities of concern, focusing on biological communities, not individual plant or animal species. This section also includes information on wildlife corridors and habitat fragmentation. Wildlife corridors are areas of habitat used by wildlife for seasonal or daily migration. Habitat fragmentation involves the potential for dividing sensitive habitat and thereby lessening its biological value.

Habitat areas that have been designated as critical habitat under the Federal Endangered Species Act (FESA) are discussed in Section 2.18. Wetlands and other waters of the U.S. and SEZs are discussed in Section 2.15. TRPA has designated specific habitat types and species of concern, which are addressed throughout the following biological environment discussions.

The study area for biological resources consists of an Environmental Study Limit that represents the estimated area within which the project would be constructed. The ESL limits are shown on the maps in Appendix A.

2.14.1. Regulatory Setting

According to CEQA, significant impacts could result if a project results in long-term degradation of a sensitive plant community or substantial loss of a plant community.

The following TRPA threshold applies to the proposed project:

- V2: Provide for the nondegradation of the natural qualities of any plant community that is uncommon to the region or of exceptional scientific,

ecological, or scenic values. This threshold shall apply but not be limited to 1) deep-water plants of Lake Tahoe; 2) Grass Lake (sphagnum bog); 3) Osgood swamp; and 4) the Freel Peak Cushion Plant community.

2.14.2. Affected Environment

This project segment crosses four habitat and land use types: Jeffrey pine, montane chaparral, sagebrush, and lodgepole pine. The northern portion of the project is primarily urban. The entire project falls within the Upper Truckee River watershed, which ultimately drains into Lake Tahoe.

No CDFG natural communities of special concern or TRPA uncommon plant communities were identified within the ESL during the wetland delineation surveys, wildlife surveys, or botanical surveys. The ESL is generally highly disturbed and characterized by the US 50 roadway shoulder and commercial and residential development.

2.14.3. Impacts

No sensitive natural communities exist within the ESL or project vicinity; therefore, no project-related impacts are anticipated. The proposed project features will not restrict wildlife movement. Work areas will be restored following project completion.

2.14.4. Avoidance, Minimization and/or Mitigation Measures

No impacts to sensitive natural communities are anticipated, so no avoidance, minimization, or mitigation is proposed.

2.15. Wetlands and Other Waters of the U.S., and Stream Environment Zones

2.15.1. Regulatory Setting

Wetlands and other waters are protected under a number of laws and regulations. At the federal level, the CWA (33 USC 1344) is the primary law regulating wetlands and waters. The CWA regulates the discharge of dredged or fill material into waters of the United States, including wetlands. Other waters of the United States include navigable waters, interstate waters, territorial seas and other waters that may be used in interstate or foreign commerce. To classify wetlands for the purposes of the CWA, a three-parameter approach is used that includes the presence of hydrophytic (water-loving) vegetation, wetland hydrology, and hydric soils (soils subject to saturation/inundation). All three parameters must be present, under normal

circumstances, for an area to be designated as a jurisdictional wetland under the CWA.

Section 404 of the CWA establishes a regulatory program that provides that no discharge of dredged or fill material can be permitted if a practicable alternative exists that is less damaging to the aquatic environment or if the nation's waters would be significantly degraded. The Section 404 permit program is run by the USACE with oversight by the USEPA.

Executive Order 11990 also regulates the activities of federal agencies with regard to wetlands. Essentially, this executive order states that a federal agency such as FHWA cannot undertake or provide assistance for new construction located in wetlands unless the head of the agency finds: (1) that there is no practicable alternative to the construction and (2) the proposed project includes all practicable measures to minimize harm.

At the state level, wetlands and waters are regulated primarily by the CDFG and the RWQCBs. Sections 1600–1607 of the California Fish and Game Code require any agency that proposes a project that will substantially divert or obstruct the natural flow of or substantially change the bed or bank of a river, stream, or lake to notify the CDFG before beginning construction. If the CDFG determines that the project may substantially and adversely affect fish or wildlife resources, a Lake or Streambed Alteration Agreement will be required. CDFG jurisdictional limits are usually defined by the tops of the stream or lake banks, or the outer edge of riparian vegetation, whichever is wider. Wetlands under jurisdiction of the USACE may or may not be included in the area covered by a Streambed Alteration Agreement obtained from the CDFG.

The RWQCBs were established under the Porter-Cologne Water Quality Control Act to oversee water quality. The RWQCBs also issues water quality certifications in compliance with Section 401 of the CWA. The LRWQCB, through implementation of its 1995 Basin Plan and authority under Section 401 of the federal CWA, regulates activities within wetlands and waters of the United States and TRPA SEZs. The Basin Plan prohibits new disturbance/coverage within SEZs in the Lake Tahoe Basin. If the project affects SEZs, the LRWQCB would have to make all of the following findings for public service facilities:

- The project is necessary for public health, safety or environmental protection

- There is no reasonable alternative, including spans, that avoids or reduces the extent of encroachment in the SEZ
- Impacts are fully mitigated
- SEZ lands will be restored for the SEZ area developed or disturbed by the project

Although no specific TRPA thresholds exist for wetlands, the TRPA Code of Ordinances protects wetland resources in the region. In addition, the following vegetation threshold is applicable:

- V1: Increase plant and structural diversity of forest communities through appropriate management practices as measured by diversity indices of species richness, relative abundance, and pattern.

2.15.2. Affected Environment

Prior to the preparation of this document, a Draft Program EIR was developed to consider cumulative impacts for eight water quality improvement projects along US 50 and SR 89. At that time, a Wetland Delineation Boundary was studied to inventory the presence of wetlands, USACE jurisdictional waters, other waters of the U.S., and SEZs. The Wetland Delineation Boundary included a broad study area that had a potential for use in the proposed projects as they proceeded further in design.

The current US 50 Segment 2 project includes a more refined Environmental Study Limit, which is used to determine impacts of the proposed project on the previously identified wetland features (including jurisdictional and other waters of the U.S. as well as SEZs) within the more broadly defined Wetland Delineation Boundary.

2.15.2.1. Jurisdictional Wetlands

A total of 2.44 acres of potential jurisdictional wetlands were identified within the Wetland Delineation Boundary during the wetland delineation surveys. A total of 1.76 acres were identified within the ESL. Wetlands occur in forested habitat and chaparral-dominated habitat in the southern portion of the ESL.

2.15.2.2. Jurisdictional Non-Wetland Waters of the U.S

A total of 0.33 acre of non-wetland waters of the U.S. (or other waters of the U.S.) was identified in the both the Wetland Delineation Boundary and the ESL. These resources were characterized as one of the following types according to their origin and amount of water present: ephemeral/man-made drainage, ephemeral/natural waterway, or perennial/intermittent waterway.

2.15.2.3. Stream Environment Zones

Based upon the boundaries of TRPA-approved SEZs, 3.09 acres of SEZs were identified within the ESL. The SEZ area occurs at the north end of the ESL at the intersection of US 50 and B Street in the City of South Lake Tahoe.

2.15.3. Impacts

Jurisdictional Wetlands

Overlaying the project features on the mapped resources obtained from field surveys indicates that approximately 0.01 acre of wetlands could be permanently affected by the construction of proposed cut and fill activities.

Jurisdictional Other Waters of the U.S.

A total of <0.06 acre of potentially jurisdictional other waters of the U.S. will be affected by proposed construction activities within the ESL. Cut and fill activities would permanently affect <0.03 acre. Temporary impacts, which would result from construction activities in close proximity to other waters of the U.S., account for the remaining 0.03 acre. Indirect effects, such as altered hydrology and introduction of non-native plant species, may also result after project construction.

Stream Environment Zones

A total of 0.16 acre of SEZ area within the ESL would be permanently affected by the construction of Basin 60. Neither maintenance turnout paving nor cut-and-fill activities would permanently affect any existing SEZ areas. Temporary impacts of 0.14 acre would result from construction activities around culverts.

TRPA Considerations

With implementation of the measures listed in Section 2.15.4, the proposed project is consistent with Threshold V1 and with TRPA Code elements that protect wetland resources.

2.15.4. Avoidance, Minimization and/or Mitigation Measures

It is determined that there is no practicable alternative to the proposed construction in wetlands and that the proposed action includes all practicable measures to minimize harm to wetlands that may result from such use. The preliminary project plans have been modified and/or revised to remove or change most of the basins and drainage facilities that might affect these resources.

WE-1 On-Site Mitigation

Remaining impacts to wetlands, other jurisdictional waters of the U.S., and SEZs will be mitigated on-site if possible. Detailed wetland mitigation plans will be developed in consultation with the USACE.

WE-2 General Avoidance/Minimization Measures and BMPs

To ensure maximum avoidance, the measures listed below and included in their entirety in Section 2.20 will be followed.

- GE-01: Establishment of Environmentally Sensitive Areas (ESAs)
- GE-02: Construction Clean-up
- GE-03: Construction Scheduling (Project activities in jurisdictional wet areas will occur in the dry season, which is typically between July 15 and October 15 but depends on seasonal conditions)
- WQ-01: Avoidance of Aquatic Resources
- WQ-02: Timing of Aquatic Resource Activities
- WQ-03: Minimizing Disturbance of Aquatic Resources
- WQ-04: Erosion Control
- WQ-05: Prohibition of Construction Materials Entering Aquatic Resources
- WQ-06: On-Site Restoration
- HA-01: Avoidance of Habitat Disturbance
- HA-02: Revegetation of Disturbed Areas
- HA-06: Preservation of Existing Top Soil Layer
- WL-01: Ensure Fish Passage
- WL-02: Limit Vegetation Removal

2.16. Plant Species

2.16.1. Regulatory Setting

The USFWS and CDFG share regulatory responsibility for the protection of special-status plant species. Special-status species are selected for protection because they are rare and/or subject to population and habitat declines. Special status is a general term for species that are afforded varying levels of regulatory protection. The highest level of protection is given to threatened and endangered species; these are species that are formally listed or proposed for listing as endangered or threatened under the FESA and/or the California Endangered Species Act (CESA). Section 2.18 presents detailed information about threatened and endangered species.

This section discusses all other special-status plant species, including CDFG fully protected species and species of special concern, USFWS candidate species, and nonlisted California Native Plant Society (CNPS) rare and endangered plants.

The regulatory requirements for FESA can be found at 16 USC Section 1531, et seq. See also 50 CFR Part 402. The regulatory requirements for CESA can be found at California Fish and Game Code, Section 2050, et seq. Caltrans projects are also subject to the Native Plant Protection Act (California Fish and Game Code Sections 1900–1913) and CEQA (PRC Sections 2100–21177).

The following TRPA thresholds apply to the project area:

- V1: Increase plant and structural diversity of forest communities through appropriate management practices as measured by diversity indices of species richness, relative abundance, and pattern. Provide for promotion and perpetuation of late successional/old growth forests. The goal is to increase late successional/old growth conditions across elevational ranges of the Lake Tahoe Basin forest cover types. Individual trees greater than 30 inches dbh shall also be favored for retention because of their late seral attributes.
- V3: Maintain a minimum number of population sites for each of five sensitive plant species: 1) *Carex paucifructus*; 2) *Lewisia pygmaea logipetala*; 3) *Draba asterophora v. macrocarpa*; 4) *Draba asterophora v. asterophora*; and 5) *Rorippa subumbellata*.

2.16.2. Affected Environment

Special-status plant species that are potentially present in the ESL were identified based on information compiled from the following resources:

- Forest Service Lake Tahoe Basin Management Area Sensitive Species List
- TRPA Goals and Policies Special Interest Species List
- California Natural Diversity Data Base (CNDDDB; April 2007)
- Forest Service 2004 Survey Data
- CNPS Inventory of Rare and Endangered Plants (online edition, v7-06a)
- USFWS Federally Endangered and Threatened Species List

Official species lists obtained from the USFWS for the 12-quad area surrounding the ESL are included in Appendix F. Additionally, documented occurrence data were obtained from the CNDDDB April 2007 database surrounding the ESL (the 7.5-minute USGS within the quadrangles for Markleeville, Carson Pass, Caples Lake, Tragedy

Spring, Minden, South Lake Tahoe, Freel Peak, Woodfords, Emerald Bay, Rockbound Valley, Pyramid Peak, and Echo Lake).

The following sensitive plant species were identified as having a potential to occur within the regional area, and were specifically surveyed for during the studies for this project: creeping barberry (*Berberis aquifolium* var. *reprens*), upswept moonwort (*Botrychium ascendens*), scalloped moonwort (*Botrychium crenulatum*), western goblin (*Botrychium montanum*), Bolander's candle moss (*Bruchia bolanderi*), shore sedge (*Carex limosa*), Oregon fireweed (*Epilobium oregonum*), starved daisy (*Erigeron miser*), American manna grass (*Glyceria grandis*), short-leaved hulsea (*Hulsea brevifolia*), three-ranked hump-moss (*Meesia triquetra*), broad-nerved hump-moss (*Meesia uliginosa*), northern adder's tongue (*Ophioglossum pusillum*), Stebbin's phacelia (*Phacelia stebbinsii*), holly fern (*Polystichum lonchitis*), marsh skullcap (*Scutellaria galericulata*), and felt-leaved (woolly) violet (*Viola tomentosa*).

2.16.3. Impacts

No sensitive plant species were found within the project study area during seasonal surveys completed in 2007. Suitable habitat for special-status plant species within the ESL is marginal due to the high level of human disturbance and development. No direct or indirect effects on special-status plants are expected from the project.

TPRA Considerations

The project is consistent with TRPA Thresholds V1 and V3. As described in Section 2.5.3, tree removal will comply with TRPA Code of Ordinances Chapter 71.

2.16.4. Avoidance, Minimization and/or Mitigation Measures

No special-status plants were identified in the ESL during the 2007 botanical surveys; therefore, no avoidance and minimization measures are proposed.

2.17. Animal Species

2.17.1. Regulatory Setting

Many state and federal laws regulate impacts to wildlife. The USFWS, the National Marine Fisheries Service (NOAA Fisheries), and the CDFG are responsible for implementing these laws. This section discusses potential impacts and permit requirements associated with wildlife not listed or proposed for listing under CESA or FESA. Species listed or proposed for listing as threatened or endangered are discussed in Section 2.18. All other special-status animal species are discussed here,

including CDFG fully protected species and species of special concern, and USFWS candidate species.

Federal laws and regulations pertaining to wildlife include the following:

- NEPA
- Migratory Bird Treaty Act
- Fish and Wildlife Coordination Act

State laws and regulations pertaining to wildlife include the following:

- CEQA
- Sections 1601–1603 of the California Fish and Game Code
- Section 4150 and 4152 of the California Fish and Game Code

The following TRPA thresholds apply to the project area:

- W1: Wildlife protection and maintenance of special interest species viability in the Lake Tahoe region. Provide a minimum number of population sites and disturbance zones for the following species: 1) Northern Goshawk (*Accipiter gentilis*); 2) Osprey (*Pandion haliaetus*); 3) Bald Eagle (*Haliaeetus leucocephalus*); 4) Golden Eagle (*Aquila chrysaetos*); 5) Peregrine Falcon (*Falco peregrinus anatum*); 6) Waterfowl (all open water associated species); and 7) Deer (*Odocoileus hemionus*).
- W2: A non-degradation standard shall apply to wildlife habitat consisting of deciduous trees, wetlands, and meadows while providing for opportunities to increase the acreage of such riparian associations.
- F1: Maintain 75 miles of habitat rated excellent, 105 miles of good, and 38 miles of marginal stream habitat.
- F2: A non-degradation standard shall apply to fish habitat in Lake Tahoe.
- F3: Achieve the equivalent of 5,948 total acres of excellent habitat in Lake Tahoe.
- F4: Until in-stream flow standards are established in the Regional Plan to protect fishery values, a non-degradation standard shall apply to in-stream flows.
- F5: It shall be a policy of the TRPA governing board to seek transfers of existing points of water diversion from streams to Lake Tahoe.

2.17.2. Affected Environment

This section provides information on sensitive wildlife species that are known to occur or may occur in the project vicinity. The following sources were reviewed to help define the potential for sensitive wildlife to occur within or near the project study area:

- USFWS Species List of Federal Endangered and Threatened Species occurring within the twelve 7.5-minute USGS quads surrounding the ESL (included in Appendix F)
- TRPA Goals and Policies Special Interest Species
- California's Fully Protected Animals List
- California's Amphibians, Birds, Fish, Mammals, and Reptile Species of Special Concern
- State and Federally Listed Endangered and Threatened Animals of California
- CNDDDB (April 2007). The 7.5-minute quarter quads included in the CNDDDB and USFWS review are Markleeville, Carson Pass, Caples Lake, Tragedy Spring, Minden, South Lake Tahoe, Freel Peak, Woodfords, Emerald Bay, Rockbound Valley, Pyramid Peak, and Echo Lake.
- Wildlife 2000
- TRPA 2006 goshawk occurrence data

The following wildlife species of concern were either identified or considered to be present within or near the project area. Species listed or proposed for listing as threatened or endangered are discussed in Section 2.18.

Northern Goshawk

The northern goshawk (*Accipiter gentilis*) is a CDFG species of special concern, an LTBMU sensitive species and management indicator species, and a TRPA special-interest species. No northern goshawks were observed during the June 2007 wildlife surveys. The area is not likely to be used for nesting because of the constant human disturbance from US 50, the South Lake Tahoe Airport, and commercial and residential development within the ESL. Marginal foraging habitat may be present in less disturbed areas near the South Lake Tahoe Airport. TRPA has defined a protected activity center (PAC) for the northern goshawk that is associated with a known nest site located approximately 0.25 mile east of the ESL. This PAC covers most of the northern area of the ESL. However, the nest site was recorded in 1981, has not been resurveyed since 1981, and is likely to have been abandoned due to the high level of disturbance in the area. In addition, TRPA does not require an exclusion

zone around this nest since the project occurs within a TRPA Urban Plan Area (Thayer 2007).

Mallards and Waterfowl

Mallards (*Anas platyrhynchos*) and waterfowl species are protected under the MBTA and are designated as LTBMU management indicator species and TRPA special-interest species. Streams and wetlands in the ESL provide marginal habitat for mallards and waterfowl because of human disturbance. Mallards and waterfowl may use areas within the ESL during migration but it is unlikely that they would depend on these areas for foraging, breeding, or nesting.

Blue Grouse

The blue grouse (*Dendragapus obscurus*) is an LTBMU management indicator species. Blue grouse may potentially use the ESL for foraging; however, due to the proximity of US 50 and residential and commercial development, the species is unlikely to breed within the ESL. Suitable habitat for the blue grouse exists in and adjacent to the ESL from the Lake Tahoe Airport up to the residential neighborhood in forests with Douglas firs.

California Spotted Owl

The California spotted owl (*Strix occidentalis occidentalis*) is a CDFG species of special concern and an LTBMU sensitive species and management indicator species. TRPA has designated one home range core area (HRCA) and PAC for California spotted owl in the vicinity of the project, in an area generally described as Tahoe Mountain. The Tahoe Mountain HRCA is located between US 50 and Fallen Leaf Lake, which begins approximately 1 mile west of the ESL and continues west to the eastern shore of Fallen Leaf Lake. However, no California spotted owls were observed during the June 2007 wildlife survey. Limited suitable habitat for foraging exists in the southern portion of the ESL adjacent to forested areas near the South Lake Tahoe Airport.

Bats

California state law protects bats and their occupied roosts from harassment and destruction under California Fish and Game Code Sections 2000, 2002, 2014, and 4150 and in 14 California Code of Regulations 251.1. During the June 2007 habitat surveys, bat refugia was identified within the ESL in forested areas near the airport and throughout the structures found in the urbanized areas.

Sierra Nevada Snowshoe Hare

The Sierra Nevada snowshoe hare (*Lepus americanus tahoensis*) is a CDFG species of special concern. Sierra Nevada snowshoe hares are thought to be relatively uncommon within the project vicinity. Two historical occurrences were documented by the CNDDDB in the project vicinity; however, there are no recent records of the Sierra Nevada snowshoe hare within the ESL. Thickets of brush or riparian cover suitable for snowshoe hare cover, nesting, and foraging are limited within the ESL and occur primarily at the southern end of the project area near the Lake Tahoe Airport, where less development has taken place. Due to heavy human activity and the presence of domestic pets (dogs and cats) in the northern half of the project area, it is unlikely for the Sierra Nevada snowshoe hare to occur.

Sierra Marten

The Sierra marten (*Martes americana*) is an LTBMU sensitive species. CNDDDB and TRPA record occurrences of Sierra marten throughout the Tahoe Basin, but none has been observed within the ESL. No individuals, signs of presence (track, scat, etc.), or sites suitable for marten dens occur within the ESL. Suitable habitat for the Sierra marten is limited in the ESL, but the species may forage in areas of high canopy closure.

Mule Deer

The mule deer (*Odocoileus hemionus*) is an LTBMU management indicator species and a TRPA special interest species. No individuals or signs of mule deer (tracks and scat) were observed in the study area during field surveys, but mule deer are known to occur in the general area. Consequently, mule deer are considered to potentially occur within the ESL.

Black Bear

The black bear (*Ursus americanus*) is an LTBMU management indicator species. No black bear presence (tracks and scat) was observed within the ESL. The urbanized area surrounding the ESL may attract black bears to forage among trash cans and other areas containing human refuse. Bears are known to occur in the general area and are becoming less afraid of human activity. Consequently, black bears are considered to potentially occur within the ESL.

Other Wildlife Species with Potential to Occur

The study area was determined to contain habitat that has the potential to support the following wildlife species. However, no records of sightings exist, and/or no

individuals or signs of presence were sighted during the field surveys. Because potential habitat is present, these species are considered to have the potential to occur. Section 2.17.4 includes measures to verify their absence prior to construction and/or avoid adverse effects.

- Mallards (*Anas platyrhynchos*) and other waterfowl species are protected under the Migratory Bird Treaty Act and are designated as LTBMU management indicator species and TRPA special-interest species. There is a potential for migratory birds to try to nest in vegetation within the study area between March 1 and August 15. Streams and wetlands in the ESL could provide habitat for mallards and waterfowl. Mallards and waterfowl may use the ESL for foraging and migrating.
- Yellow warbler (*Dendroica petechia brewsteri*) is a CDFG species of special concern. Riparian habitat and shrubby vegetation suitable for nesting yellow warblers is present within the study area.
- Peregrine falcon (*Falco peregrinus ssp. anatum*) has been delisted by the federal government but is a fully protected endangered species in the State of California. No occurrences of this species have been recorded within the project vicinity. The ESL contains foraging habitat for this species, but no rocky cliff habitat suitable for peregrine falcon nesting is present in or adjacent to the ESL. No peregrine falcons were observed within the ESL during the June 2007 wildlife surveys.
- American badger (*Taxidea taxus*) is a California species of special concern. No tracks or other signs of presence were observed during the June 2007 wildlife surveys. The ESL contains a small meadow that could provide suitable habitat; however, the high level of human disturbance in the vicinity makes it unlikely that this species would occupy the ESL.

2.17.3. Impacts

The project will involve construction activities along the existing US 50 at locations where drainage facilities and roadway improvements are planned. Impacts to existing vegetation, including trees, will be minimal, but vegetation may be removed where infiltration basins are proposed. As noted in Section 2.5.3, infiltration basins will be designed to minimize tree removal; however, if it is determined to be infeasible to maintain the long-term health of a tree, it will be removed as part of basin construction. Some existing cut and fill slope modifications will be necessary. Other proposed facilities such as the maintenance pullouts and sand traps will be

constructed relatively close to or within already disturbed areas along the shoulders of US 50, and effects to habitat will be avoided or minimal.

TRPA Considerations

With implementation of the avoidance and minimization measures listed in Section 2.17.4, the proposed project is consistent with TRPA Thresholds W1, W2, and F1 through F5.

2.17.4. Avoidance, Minimization and/or Mitigation Measures

The following measures will be taken prior to and during construction to avoid or minimize direct and permanent effects to special-status wildlife and indirect effects to areas adjacent to the study area. Preconstruction surveys will be performed in the ESL where habitat for sensitive species exists to verify species presence/absence and assess the need for additional avoidance and minimization measures. If species are determined to be present, seasonal construction restrictions will be required to avoid breeding seasons and other periods when wildlife species are vulnerable.

Construction contract specifications will include use of ESAs, shown on the maps in Appendix A, construction clean-up, weed control, restrictions on in-stream work, erosion control, and restoration of disturbed SEZs. Measures for specific species identified in Section 2.17.2 are summarized below.

AN-1 Preconstruction Surveys for Avian Species

No nesting of special-status birds was observed during the field surveys. However, potential habitat was identified, and TRPA has recorded habitat or occurrences for some species within or near the project study area. To ensure that species of concern are not using the study area at the time construction proceeds, preconstruction surveys will be performed within the ESL to verify absence. In addition, the preconstruction surveys will include a review of TRPA and Forest Service annual survey data to identify any new occurrences. The following potential buffer areas may be imposed on construction activities to minimize impacts if species are found to be present.

- Northern goshawk: If nesting northern goshawks are identified, construction will be prohibited within a 0.5-mile range of the nest during the breeding season (February 15 to September 15 or until fledging occurs).
- Blue grouse, yellow warbler, waterfowl: If nests are identified, construction activities will be prohibited within 150 feet of the nest during the nesting season (March 1 to August 31). Vegetation removal will be prohibited during the nesting season to minimize the effect to warblers and other migratory birds that have not

yet started nesting. Vegetation that is removed outside of the nesting season will be restored to its preconstruction condition.

- California spotted owl: If nests are identified, construction will be prohibited within 0.25 mile of the nest sites during the nesting season (between March 1 and August 31).
- Peregrine falcon: If nests are found, construction will be prohibited within 0.25 mile of the nest during the nesting season (February 1 to August 15).

AN-2 General Measures and BMPs for Avian Species

The following general avoidance/minimization measures and BMPs are detailed in Section 2.20:

- HA-01: Avoidance of Habitat Disturbance
- HA-02: Revegetation of Disturbed Areas
- WL-02: Limit Vegetation Removal
- WL-03: Migratory Bird Preconstruction Surveys
- WL-04: Raptor and Owl Surveys

AN-3 General Measures and BMPs for Mammals

The following general avoidance/minimization measures and BMPs are detailed in Section 2.20:

- WQ-01: Avoidance of Aquatic Resources
- WQ-03: Minimizing Disturbance of Aquatic Resources
- HA-01: Avoidance of Habitat Disturbance
- HA-02: Revegetation of Disturbed Areas
- WL-02: Limit Vegetation Removal
- WL-05: Roosting, Denning, or Burrowing Mammal Surveys

AN-4 Preconstruction Survey for Sierra Nevada Snowshoe Hare

Project construction activities have the potential to impact forested and riparian areas that may provide cover for Sierra Nevada snowshoe hare. Preconstruction surveys will be conducted for Sierra Nevada snowshoe hare within the ESL in riparian areas where nest depressions may be located. Where Sierra Nevada snowshoe hare nest depressions are identified, construction within 250 feet of these areas will be prohibited between February 1 and July 1, and construction will be limited to daylight hours.

2.18. Threatened and Endangered Species

This section describes the potential of the project to affect species that are listed or proposed for listing under the FESA or CESA.

2.18.1. Regulatory Setting

The primary federal law protecting threatened and endangered species is the FESA (16 USC Section 1531, et seq.; see also 50 CFR Part 402). This act and subsequent amendments provide for the conservation of endangered and threatened species and the ecosystems upon which they depend. Under Section 7 of the FESA, federal agencies such as FHWA are required to consult with the USFWS and NOAA Fisheries to ensure that they are not undertaking, funding, permitting, or authorizing actions likely to jeopardize the continued existence of listed species or destroy or adversely modify designated critical habitat. Critical habitat is defined as geographic locations critical to the existence of a threatened or endangered species. The outcome of consultation under Section 7 is a Biological Opinion or an incidental take permit. Section 3 of the FESA defines take as “harass, harm, pursue, hunt, shoot, wound, kill, trap, capture or collect or any attempt at such conduct.”

California has enacted a similar law at the state level, the CESA (California Fish and Game Code, Section 2050 et seq.). The CESA emphasizes early consultation to avoid potential impacts to rare, endangered, and threatened species and to develop appropriate planning to offset project-caused losses of listed species populations and their essential habitats. The CDFG is the agency responsible for implementing CESA. Section 2081 of the California Fish and Game Code prohibits take of any species determined to be an endangered species or a threatened species. Take is defined in Section 86 of the California Fish and Game Code as “hunt, pursue, catch, capture, or kill, or attempt to hunt, pursue, catch, capture, or kill.” The CESA allows for take incidental to otherwise lawful development projects; for these actions an incidental take permit is issued by CDFG. For projects requiring a Biological Opinion under Section 7 of the FESA, the CDFG may also authorize impacts to CESA species by issuing a Consistency Determination under Section 2080.1 of the California Fish and Game Code.

The following TRPA threshold applies to the project area:

- W1: Wildlife protection and maintenance of special interest species viability in the Lake Tahoe region. Provide a minimum number of population sites and disturbance zones for the following species: 1) Northern Goshawk (*Accipiter*

gentilis); 2) Osprey (*Pandion Haliaeetus*); 3) Bald Eagle (*Haliaeetus leucocephalus*); 4) Golden Eagle (*Aquila chrysaetos*); 5) Peregrine Falcon (*Falco peregrinus anatum*); 6) Waterfowl (all open water associated species); and 7) Deer (*Odocoileus hemionus*).

2.18.2. Affected Environment

Each federal agency will confer with the USFWS and NOAA Fisheries on any action that is likely to jeopardize the continued existence of any proposed species or result in the destruction or adverse modification of proposed critical habitat. The consultation process is designed to assist the federal agency and any applicant in identifying and resolving potential conflicts at an early stage in the planning process. The following consultation and research steps were completed to identify the status and potential to occur for any protected species within or near the project area.

A species list for the project vicinity was obtained from the online database of the Sacramento field office of the USFWS in June 2007. The project vicinity includes the following 12 USGS 7.5-minute topographic quads: Markleeville, Carson Pass, Caples Lake, Tragedy Spring, Minden, South Lake Tahoe, Freel Peak, Woodfords, Emerald Bay, Rockbound Valley, Pyramid Peak, and Echo Lake. The USFWS species list is included in Appendix F.

In addition, LTBMU staff was contacted in May 2007 regarding species presence in the project vicinity and the availability and use of digital occurrence information. Surveys for sensitive species and habitat were conducted in June and August 2007.

Based on review of the species list, consultation, and surveys, the following federal or state-listed species was determined to have the potential to occur in the regional area, and was evaluated for its potential presence within the project limits:

- **Sierra Nevada red fox** (*Vulpes vulpes necator*) – State-listed threatened species; LTBMU sensitive species.

2.18.3. Impacts

No Sierra Nevada red fox were observed within the ESL during the 2007 wildlife surveys. No signs (track, scat, etc.) or sites suitable for Sierra Nevada red fox dens occurred within the ESL. Marginally suitable habitat and prey base are present in the wet meadow near the Lake Tahoe Airport within the ESL and vicinity. However, due to the disturbed urban habitat within the ESL, it is unlikely for the Sierra Nevada red

fox to be present. Sierra Nevada red fox was determined to not be present and therefore would not be affected by the project.

TRPA Considerations

No threatened or endangered species identified in TRPA Threshold W1 were determined to be present in the ESL.

2.18.4. Avoidance, Minimization and/or Mitigation Measures

TE-1 Measures for Sierra Nevada Red Fox

As the project vicinity contains potential habitat for Sierra Nevada red fox, preconstruction surveys for dens will be conducted within the ESL. Construction will be prohibited within 250 feet of an identified active den during the breeding season (February 1 to May 31). Open trenches or other construction features that pose a risk of trapping animals will have escape ramps installed or will be covered at the end of each construction day.

In addition to the above specific measures the following general avoidance and minimization efforts (described in detail in Section 2.20) are applicable for the Sierra Nevada red fox:

- HA-01: Avoidance of Habitat Disturbance
- HA-02: Revegetation of Disturbed Areas
- WL-02: Limit Vegetation Removal
- WL-05: Roosting, Denning, or Burrowing Mammal Surveys (as described above)

2.19. Invasive Species

2.19.1. Regulatory Setting

On February 3, 1999, President Clinton signed Executive Order 13112 requiring federal agencies to combat the introduction or spread of invasive species in the United States. The order defines invasive species as “any species, including its seeds, eggs, spores, or other biological material capable of propagating that species, that is not native to that ecosystem whose introduction does or is likely to cause economic or environmental harm or harm to human health.” FHWA guidance issued August 10, 1999, directs the use of the state’s noxious weed list to define the invasive plants that must be considered as part of the NEPA analysis for a proposed project.

The U.S. Department of Transportation has issued policy guidelines that provide a framework for addressing roadside vegetation management issues for construction

activities and maintenance programs. Region 5 of the Forest Service has implemented the provisions of Executive Order 13112 specific to noxious weed species into its Sierra Nevada Forest Plan, and these measures will be implemented by Caltrans. The Sierra Nevada Forest Plan Amendment (Forest Service 2001) requires a noxious weed risk assessment for any ground-disturbing activities to prevent the spread of noxious weeds into the surrounding area. The assessment would determine if project activities have a low, moderate, or high risk for the spread of noxious weeds (defined as plants designated as noxious by federal or state law).

2.19.2. Affected Environment

No established infestations of noxious weeds were detected in the project ESL.

2.19.3. Impacts

Due to the lack of identified noxious weeds in the ESL and the limited amount of disturbance that will result from project construction, construction-related habitat changes that could increase or encourage noxious weed establishment growth (reduced shade and soil cover) will be minor.

2.19.4. Avoidance, Minimization or Mitigation Measures

The following measures, which are described in Section 2.20, will be implemented to avoid the potential introduction of noxious weed material to the project site:

- HA-03: Construction Equipment Weed Control
- HA-05: Weed-Free Erosion Control Seed Mix/Stock

2.20. Avoidance, Minimization, and Mitigation Measures for Biological Resources

The following proposed avoidance and minimization measures are standard BMPs that have been tailored for the proposed project and project area. Table 2.20-1 does not include species-specific measures. Species-specific measures (such as buffer zone size and duration of construction restrictions) are described in Sections 2.14 through 2.18.

Table 2.20-1 General Avoidance and Minimization Measures, and Best Management Practices

Measure	Responsible for Implementation	Description	Notes
General			
GE-01: Establishment of Environmentally Sensitive Areas (ESAs)	Contractor and Caltrans Resident Engineer	ESAs will be designated and fenced off prior to the beginning of construction activities. No work or equipment operation will take place in ESAs in any construction season.	ESAs will remain in place until all project construction activities have been completed. ESAs are to be determined by a qualified biologist.
GE-02: Construction Clean-up	Contractor	All temporary fill and construction debris will be removed from the ESL after completion of construction activities.	Fill and debris removal will take place upon completion of construction activities.
GE-03: Construction Scheduling	Caltrans Project Management and Contractor	Construction will be timed to avoid impacts to sensitive biological resources.	The exact dates will vary for each resource; see Sections 2.14 through 2.18.
Water Quality			
WQ-01: Avoidance of Aquatic Resources	Contractor and Caltrans Resident Engineer	All work within and near wetlands, other waters of the US, SEZs, and any other wet areas will be avoided where possible.	Areas containing aquatic resources will be fenced off as ESAs until project construction activities have been completed.
WQ-02: Timing of Aquatic Resource Activities	Caltrans Project Management and Contractor	Impacts to wetland and other waters associated with construction activities will be restricted to the dry season.	The dry season typically occurs between July 15 and October 15 but depends upon seasonal conditions.
WQ-03: Minimizing Disturbance of Aquatic Resources	Contractor and Caltrans Resident Engineer	Temporarily disturbed aquatic resources will be returned to preconstruction condition at the end of each construction season.	This may require grading temporary access roads, removing access roads at the end of each construction season, re-contouring stream banks and adjacent areas, covering bare ground with mulch, and/or applying revegetation measures.
WQ-04: Erosion Control	Contractor and Caltrans Resident Engineer	Erosion control will be implemented and in place prior to, during, and after construction to ensure that no silt or sediment enters surface water or channels.	Devices used for erosion control will be weed free as described in measure HA-05.

Table 2.20-1 General Avoidance and Minimization Measures, and Best Management Practices (continued)

Measure	Responsible for Implementation	Description	Notes
WQ-05: Prohibition of Construction Materials Entering Aquatic Resources	Contractor and Caltrans Resident Engineer	Construction material and/or debris are prohibited from entering surface waters or their channels.	Includes all materials related to construction, (e.g., oil, greasy materials, asphalt-concrete, etc.) Materials should not be placed where they have potential to enter aquatic resources.
WQ-06: On-Site Restoration	Contractor and Caltrans Resident Engineer or Biologist	Any permanent impacts to wetlands, other waters of the U.S., SEZs or sensitive habitats will be mitigated through on-site restoration, where possible.	On-site restoration will be completed in coordination with the USACE and/or TRPA.
Habitat			
HA-01: Avoidance of Habitat Disturbance	Contractor and Caltrans Resident Engineer	All disturbances of vegetative/woody habitat will be avoided where possible.	
HA-02: Revegetation of Disturbed Areas	Contractor and Caltrans Resident Engineer (implement in field); Caltrans Landscape Engineer or Biologist (post-construction monitoring).	All disturbed areas will be revegetated with TRPA-approved, appropriate combinations of native species upon completion of construction activities.	The appropriate combinations of native species will be determined by a qualified biologist.
HA-03: Construction Equipment Weed Control	Contractor and Caltrans Resident Engineer.	Construction equipment will be cleaned of potential noxious weed sources before entry into the ESL.	After each exposure to noxious weed sources, construction equipment should be cleaned in a manner that does not facilitate seed dispersal.
HA-04: Equipment Staging	Contractor and Caltrans Resident Engineer.	Construction equipment will be staged in areas where it will not be exposed to noxious weed sources and where materials such as oil, gas, etc. from equipment do not have the potential to impact biological resources.	These areas should be delineated on construction plans and should not impact any biological resources.
HA-05: Weed-Free Erosion Control Seed Mix/Stock	Contractor and Caltrans Resident Engineer (implemented in field); Caltrans Landscape Engineer or Biologist (post-construction monitoring).	Only TRPA-approved plant species will be used in any erosion control seed mix or stock. Certified weed-free straw and weed-free hydroseed mulch will be used for erosion control activities.	

Table 2.20-1 General Avoidance and Minimization Measures, and Best Management Practices (concluded)

Measure	Responsible for Implementation	Description	Notes
HA-06: Preservation of Existing Top Soil Layer	Contractor and Caltrans Landscape Engineer or Biologist	Where excavation is required, the excavated topsoil will be preserved and replaced upon completion of construction activities.	Retention of excavated topsoil should aid in maintaining the existing seed bank and speed revegetation efforts.
Wildlife			
WL-01: Ensure Fish Passage	Contractor and Caltrans Resident Engineer or Biologist	NOAA Fisheries fish screening criteria will be followed when dewatering activities or construction of cofferdams is required. Any fish collected within cofferdams will be counted, measured, and released in appropriate habitat downstream of the project area. Diversion pipes will be screened to prevent the intake of fish.	NOAA Fisheries fish screening criteria include screen openings no larger than 3/32 inch and an approach velocity of less than 0.33 foot per second. Suitable habitat for fish release is to be determined by a qualified biologist.
WL-02: Limit Vegetation Removal	Contractor and Caltrans Resident Engineer	Vegetation removal will be kept to a minimum throughout project construction.	Woody vegetation should be removed between September 1 and October 15 to minimize impacts to wildlife.
WL-03: Migratory Bird Preconstruction Surveys	Caltrans Biologist	Preconstruction surveys for nesting migratory birds will be conducted prior to the start of construction activities.	Surveys will be conducted within the ESL. If nests are found, a 150-foot ESA buffer will be imposed during the nesting season (March 1 to August 31).
WL-04: Raptor and Owl Surveys	Caltrans Biologist	Preconstruction surveys for nesting raptors and owls will be conducted prior to the start of construction activities. TRPA and Forest Service annual survey data will be reviewed for any new occurrences.	If nesting owls are observed within the buffer zone during preconstruction surveys, the appropriate agency will be contacted for further guidance.
WL-05: Roosting, Denning, or Burrowing Mammal Surveys	Caltrans Biologist	Preconstruction surveys will be conducted within 30 days of the start of construction.	Surveys will be conducted within the extent of the ESL. If any sensitive species roosts, dens, or burrows are found, CDFG or USFWS will be contacted for guidance on how to proceed.

2.21. Vector Control

In 1963, El Dorado County formed a service area governed by the Board of Supervisors in response to community complaints about pest mosquitoes. El Dorado County's Tahoe District became a Vector Control District in 1980. The District has a service area of 195 square miles from the crest of the Sierra Nevada mountain range near Echo Summit to the shore of Lake Tahoe in both the City of South Lake Tahoe and unincorporated El Dorado County.

The climate, topography, and plant communities of the Tahoe Basin provide an abundance and variety of larval mosquito habitats. The restoration of SEZs has created additional mosquito habitat. The mosquito population in the Tahoe Basin is most active in the spring and early summer. Each mosquito species has a season when it is most active and a range of preferred hosts. All mosquito species are potential sources of organisms that can cause disease to pets, domestic animals, wildlife, or humans.

Vector control is not addressed in the El Dorado County Ordinance Code; however, the Vector Control District Web site recommends identifying and eliminating all sources of standing water that can support mosquito breeding (El Dorado County Environmental Management 2007).

The proposed project includes infiltration basins that will hold storm water runoff so it can infiltrate into the ground below. These facilities will temporarily hold standing water. Caltrans design requirements impose a 3-day (72-hour) limit on how long a drainage facility can hold standing water (Caltrans 2007a). This criterion will be implemented as part of project design to avoid the potential for the basins to provide breeding habitat for mosquitoes.

Cumulative Impacts

2.22. Cumulative Impacts of Proposed Project and Other Future Actions

2.22.1. Regulatory Setting

Cumulative impacts are those that result from past, present, and reasonably foreseeable future actions, combined with the potential impacts of this project. A

cumulative effect assessment considers the collective impacts posed by individual land use plans and projects. Cumulative impacts can result from individually minor but collectively substantial impacts taking place over a period of time.

Cumulative impacts to resources in the project area may result from residential, commercial, industrial, and highway development, as well as from agricultural development and the conversion to more intensive types of agricultural cultivation. These land use activities can degrade habitat and species diversity through consequences such as displacement and fragmentation of habitats and populations, alteration of hydrology, contamination, erosion, sedimentation, disruption of migration corridors, changes in water quality, and introduction or promotion of predators. They can also contribute to potential community impacts identified for the project, such as changes in community character, traffic patterns, housing availability, and employment.

Section 15130 of the CEQA Guidelines describes when a cumulative impact analysis is warranted and what elements are necessary for an adequate discussion of cumulative impacts. The definition of cumulative impacts under CEQA appears in Section 15355 of the CEQA Guidelines. A definition of cumulative impacts under NEPA appears in 40 CFR 1508.7 of the Council on Environmental Quality Regulations.

2.22.2. Affected Environment

A Draft Program EIR was prepared in June 2007 that addressed the overall impacts associated with proposed water quality improvements on five segments of SR 89 between Luther Pass and Tahoma and three segments of US 50 between Echo Summit and Stateline. The Draft Program EIR evaluated the potential for cumulative effects resulting from the program and other approved and proposed projects along or in the vicinity of these highway segments. In all, 76 projects in the region are planned or under way, ranging from residential and commercial development to bicycle and pedestrian facilities. In addition, projects conducted as part of the Lake Tahoe EIP in areas including air quality/transportation, fisheries, recreation, scenic resources, soil conservation/SEZ, vegetation, water quality, and wildlife projects are planned or under way in the study area for the Draft Program EIR.

This segment of US 50 is within the Upper Truckee River Watershed, which is the cumulative impact study area for this highway segment. This section summarizes the identified projects in the vicinity of US 50 Segment 2 that could have the potential for cumulative environmental impacts.

2.22.2.1. Caltrans EIP Projects

The Caltrans *Lake Tahoe Basin Environmental Improvement Program Delivery Plan* (Caltrans 2005b) has scheduled a number of Lake Tahoe EIP projects to be constructed over the next 5 to 7 years, as shown in Table 2.22-1. Other safety and operational projects are also planned within this time frame, including rock retaining wall and slope erosion control projects at Echo Summit on US 50.

Table 2.22-1 Planned Caltrans EIP Projects, 2005–2012

Project Location	County	Highway
Echo Summit to 1.1 miles east of Echo Summit	El Dorado	50
0.2 miles east of Echo Summit to Meyers Road (EA 1A731)	El Dorado	50
Meyers Road to Incline Road	El Dorado	50
SR 89 North “Y” to Trout Creek (EA-3C380)	El Dorado	50
Trout Creek to Ski Run Boulevard (EA-43601)	El Dorado	50
Ski Run Boulevard to State Line (EA-1A733)	El Dorado	50
US 50 across Echo Summit (EA-1E14U)	El Dorado	50
Alpine County Line to US 50	El Dorado	89
US 50/SR 89 to Cascade Road (ED-1A842)	El Dorado	89
Cascade Road to north of Eagle Falls Viaduct	El Dorado	89
North of Eagle Falls Viaduct to Meeks Creek	El Dorado	89
Meeks Creek to Placer County Line	El Dorado	89
Alpine County line to Placer County line (EA-1A3400)	El Dorado	89
El Dorado County line to Tahoe City (EA-2A920)	El Dorado	89
Tahoe State Park to SR 267	Placer	28
SR 267 to Chipmunk Street	Placer	28
Chipmunk Street to State Line	Placer	28
El Dorado County Line to SR 28	Placer	28
Elizabeth Drive to Sugar Pine Road	Placer	28
SR 28 to Squaw Valley Road	Placer	28
Brockway Summit to 0.6 mile south of Brockway Summit	Placer	267
0.6 mile south of Brockway Summit to Stewart Way	Placer	267
Stewart Way to SR 28	Placer	267

Source: Caltrans 2005b

2.22.2.2. El Dorado County Projects

Several projects in El Dorado County in or near the Upper Truckee Watershed are planned or proposed:

Sawmill Bicycle Path Project

The County of El Dorado is scheduled to construct and maintain the Sawmill bicycle path and bridge over the Upper Truckee River adjacent to the US 50 corridor as part of the *Lake Tahoe Regional Bicycle and Pedestrian Master Plan* (Tahoe Metropolitan Planning Organization 2006).

Dead Tree Removal – US 50 and Sawmill Road

This project would remove dead trees and reduce hazardous fuels on 50 acres in Washoe Meadows State Park. The project will create a defensible fuel profile zone to reduce the threat of a catastrophic wildfire and improve native forest composition and structure.

Angora 3 Erosion Control Project and Angora Creek Fisheries Enhancement Project

El Dorado County proposes to construct and maintain conveyance and storm water treatment facilities to address water quality and erosion issues in the project area. The Angora 3 Erosion Control Project and Angora Creek Fisheries Enhancement Project include the improvement of culverts under Lake Tahoe Boulevard to enhance fish habitat in Angora Creek. Both projects are considered environmental improvements as documented in the Lake Tahoe EIP.

2.22.2.3. City of South Lake Tahoe Projects

The South Lake Tahoe Planning Department was contacted regarding planned and proposed projects within the city limits. Table 2.22-2 lists all approved and proposed projects in South Lake Tahoe.

2.22.2.4. South Tahoe Public Utility District Projects

The South Tahoe Public Utility District was contacted regarding known projects within the vicinity of the El Dorado 50, Segment 2 – Lake Tahoe Airport to US 50/SR 89 Junction Water Quality Improvement Project (Donovan 2006). The service area of the district includes portions of El Dorado County in the Tahoe Basin, SR 89 north to Cascade Lake, SR 89 south to Luther Pass, US 50 east to the Nevada state line, and US 50 west to Echo Lake. The following projects are all located within the city limits of South Lake Tahoe.

Bayview Wellhouse Control Building

This approved project includes upgrading an existing wellhouse at 701 San Francisco Avenue in South Lake Tahoe. Construction for this project begins on May 1, 2006.

Table 2.22-2 Approved and Proposed Projects in South Lake Tahoe

Project	Location	Units (Approximate)	Construction Time Frame	Type
Triangle Project	Bordered by Pioneer Trail, US 50, and Midway Road	6 acres	Dates not available	Commercial, residential, hotels
Redevelopment Project 3	Northwest corner of Lake Tahoe Blvd. and Stateline Ave.	180 units w/ 180 lockouts, 93,448 ft ² convention center, 46,526 ft ² of retail, 30,142 ft ² nightclub/restaurant/bar	May 2007–May 2009	Hotel condos, convention center, retail, restaurant
Marriott TimberLodge Phase 3	4100 Lake Tahoe Blvd.	57 units w/ 52 lockouts	2007 - 2008	Timeshare hotel
Embassy Vacation Resorts Phase 4	901 Ski Run Blvd.	40 units w/ 40 lockouts	Dates not available	Timeshare hotel
Embassy Vacation Resorts Phase 5	1000 Ski Run Blvd.	Mix of hotel and retail	Dates not available	Timeshare hotel/retail
Ski Run Shopping Center	1001 Ski Run Blvd.	16,129 ft ² of floor area existing, 21,310 ft ² after rebuild	Fall 2006–Summer 2008	Demo existing shopping center and rebuild larger center with retail and restaurant
Name not available	Southwest corner of US 50 and Ski Run Blvd.	13,000 ft ² of commercial space and 24 tourist accommodation units	Dates not available	Hotel/retail
Fantasy Inn Project	3696 Lake Tahoe Blvd.	Unspecified development	Dates not available	Not available
South Lake Tahoe South “Y” Intersection Project	Intersection of US 50 and SR 89	Intersection expansion	To begin Summer 2008	Roadway improvement

Bayview Waterline

The approved Bayview Waterline project includes the installation of 3,840 feet of waterline within the shoulders of several city streets in the Al-Tahoe neighborhood of South Lake Tahoe. The project also includes the construction of new fire hydrants and one new well.

US 50 Waterline Replacement Reno Avenue to Meeks Campground

This approved project includes the installation of approximately 5,361 feet of new waterline on US 50 in South Lake Tahoe.

Al-Tahoe Waterline

This approved project includes the upsizing of approximately 4,495 feet of new waterline in the Al-Tahoe neighborhood of South Lake Tahoe.

2.22.2.5. Lake Tahoe Airport

Improvements to the Lake Tahoe Airport have been approved by the Federal Aviation Administration. Planned upgrades include runway reconstruction in 2008–2009 and ramp restructuring in 2010.

2.22.3. Impacts

The following is a qualitative assessment regarding the US 50 Segment 2 project's contribution of impacts to those of other actions in the southern Lake Tahoe area.

The US 50 Segment 2 project would not contribute to permanent cumulative impacts with respect to air quality or noise. Except for occasional maintenance of the proposed drainage basins and runoff drainage facilities, no further ground disturbance would take place after construction is completed. The project is therefore not expected to result in permanent or long-term adverse effects to the physical or biological environment or to community resources.

The projects identified generally consist of bicycle and pedestrian paths, water quality improvement and erosion control projects, and proposed residential construction at various locations, including the City of South Lake Tahoe area. The following summarizes the potential cumulative impacts from the US 50 Segment 2 project and the other projects identified.

2.22.3.1. Vegetation

The US 50 Segment 2 project will require some vegetation removal for site preparation at proposed basins and other drainage facilities. However, the removal of woody vegetation (trees and shrubs) would be the minimum required for construction and would occur only where trees or vegetation along the roadway or basin location cannot be avoided. Any proposed loss of trees should be in conformance with TRPA goals and policies. Similarly, other proposed projects would be expected to minimize tree and vegetation removal. Overall, neither the proposed project nor the other projects identified would be expected to substantially alter the species richness, relative abundance, and pattern of vegetation adjacent to US 50 or southern Lake Tahoe area.

2.22.3.2. Wildlife and Fisheries

Similarly, the removal of vegetation adjacent to US 50 is unlikely to contribute to adverse cumulative impacts to wildlife species, including migratory birds and special-status or management indicator species. The loss of woody vegetation caused by the project in combination with the losses incurred from other past, present, and potential

future projects is unlikely to result in the nonattainment of TRPA environmental threshold carrying capacities for managed wildlife species in the southern Lake Tahoe area. Therefore, the US 50 Segment 2 project is not expected to result in an adverse cumulative impact to wildlife.

The project is not expected to have permanent adverse impacts on the movement of fish and other aquatic organisms along or across SR 89. Potential movement of aquatic organisms may be temporarily affected by construction activities such as dewatering, which may be necessary for the rehabilitation or replacement of culvert and drainage systems within the project area. The proposed project is not expected to create new barriers to aquatic migration.

A number of EIP projects proposed in the southern Lake Tahoe area are expected to have direct beneficial impacts to wildlife and fisheries resources. Table 2.22-3 summarizes EIP projects proposed in the South Lake Tahoe region that are expected to result in direct beneficial impacts to wildlife and fisheries.

Although the TRPA restricts activities that disturb SEZ areas, public service facilities (including highways and their associated facilities) are permissible uses in SEZs under certain conditions; however, measures must be provided for any adverse impacts to lower land classifications, including SEZs. The US 50 Segment 2 water quality improvement project will have minimal impacts to SEZs, and the project design will continue to be refined to further reduce or avoid these impacts. Furthermore, the quality of waters entering SEZ and jurisdictional water systems in the South Lake Tahoe area would be improved as a result of the proposed project.

2.22.3.3. Traffic

As shown in Table 22.2-1, a series of projects are planned for the region that would be constructed within the time frame of the proposed project (2008–2012). The TMP to be developed for the US 50 Segment 2 project will outline construction requirements and restrictions to minimize traffic delays and maximize safety within the construction areas. The TMP will include strategies for public and motorist information, incident management, construction, demand management, and alternate routes (if available or practical). For example, a construction season map will be published each year to inform the public, local businesses, and local agencies of planned construction locations and activities.

**Table 2.22-3 EIP Projects Beneficial to Wildlife and Fisheries Resources
in the South Lake Tahoe Area**

EIP Category	Project Name	EIP Project No.	Expected Environmental Benefit
Fisheries	Meeks Creek Phase II – Stream Habitat Restoration	700	6.5 miles stream improved to excellent
	Habitat Restoration – General Creek Improvements	899	2.9 miles stream improved to good
	Habitat Restoration – Eagle Creek Migratory	900	0.3 miles stream improved to excellent
	Habitat Restoration – Lonely Gulch Creek Improvements	901	2.0 miles stream improved to good
	Habitat Restoration – Tallac Creek Improvements	902	4.1 miles stream improved to good
	Habitat Restoration – Taylor Creek Improvements	903	2.0 miles stream improved to excellent
	Lake Habitat Restoration – CSLT/EI Dorado County	973	48 acres of in-lake fish habitat restored.
Soil Conservation/ SEZ	Restore SEZ – El Dorado County	650	40 acres restored
	General Creek Stream Bank Stabilization Project	936	1 acre restored
	Meeks Bay Marina SEZ Fill Removal and Bank Stabilization	953	0.45 acres restored
Vegetation	Habitat Protection – Tahoe Yellow Cress, Blackwood/County Park	976	0.10 acre protected
	Habitat Protection – Tahoe Yellow Cress, Meeks Bay	978	Not identified
	Habitat Protection – Tahoe Yellow Cress, D.L. Bliss State Park	979	Not identified
	Habitat Protection – Tahoe Yellow Cress, Mouth of Edgewood Creek	980	Not identified
Water Quality	Lower Ward Valley/Pineland Ecp	219	3.2 miles stream improved
	McKinney Tract	558	Not identified
	Fallen Leaf Lake	704	Not identified
	Meeks Bay Campground BMP Retrofit	711	Not identified
	McKinney II	727	3.3 acres improved
	Chambers Lodge	731	4.3 acres improved
	Paradise Flat BMP Retrofit	739	Not identified
	SR 89 South Lake Tahoe “Y” to Placer County Line	995	Not identified
	Ward Gullies	10048	Not identified
Eagle Falls	10049	Not identified	
Wildlife	General Creek Riparian Habitat Enhancement	604	400 acres improved
	Meeks Creek Riparian Habitat Improvement	605	1 mile stream improved to excellent
	Tallac Creek/Marsh Restoration	10044	3 acres improved
	Wildlife Habitat Restoration at Tahoe Basin State Parks	10083	50 acres improved

Construction schedules and anticipated locations of construction activities will be coordinated with the local agencies, including the school district and BlueGO transit,

to minimize disruptions of regularly scheduled service. Any road rehabilitation work scheduled by Caltrans would be coordinated with the water quality improvements, to consolidate construction activities.

2.22.4. Avoidance, Minimization, and Mitigation Measures

Caltrans will undertake a series of water quality improvement projects along other segments of US 50 as well as SR 89. Due to the potential for cumulative construction-related impacts, it will be necessary to inform the public of construction activities and to involve them in Caltrans planning efforts to ensure that project impacts will be minimized.

Caltrans will develop a Public Involvement Plan based on the draft Tahoe Basin Public Communications and Outreach Guidelines. These guidelines outline ways to coordinate public involvement with other agencies, identify interested stakeholders, and suggest strategies for public outreach and communication.

The guidelines describe several different strategies for public communication and outreach, including coordination with local agencies, public meetings and events, membership on boards, outreach at schools, and one-to-one meetings with stakeholders. Caltrans media communication may involve television and radio service announcements, newspaper articles, local newsletters, a website, and direct mailings.

Scheduling of projects will be coordinated to avoid overlapping construction activities within close proximity. Notification will be provided to the community to allow planning for construction activities.

Chapter 3. Comments and Coordination

Early and continuing coordination with the general public and appropriate public agencies is an essential part of the environmental process to determine the scope of environmental documentation, the level of analysis, potential impacts and mitigation measures and related environmental requirements. Agency consultation and public participation for this project have been accomplished through a variety of formal and informal methods, including project development team meetings, interagency coordination meetings, written correspondence and public information meetings held in the Lake Tahoe Area. This chapter summarizes the results of Caltrans' efforts to fully identify, address and resolve project-related issues through early and continuing coordination. After public circulation of this document, any comments will be included in this section and reflected in the Final Environmental Document.

This section describes the consultation and coordination conducted during the environmental review of the project. The improvements proposed for this segment of US 50 were included as elements of the Draft Program EIR, described below, that initiated the consultation and coordination process for this project.

3.1. Consultation and Coordination Performed for the Program EIR

Water quality improvements for three segments of US 50—including Segment 2, the subject of this report—and five segments of SR 89 were first defined in the Project Study Reports (PSRs) for US 50 and SR 89 (Caltrans 2003a, 2003b). Development of the PSRs included initial coordination with the TRPA and LRWQCB with regard to potentially acceptable designs that would meet the water quality requirements mandated for these highways. The work involved joint agency field reviews that resulted in water quality and roadway improvements that were added, eliminated, or relocated to better fit the existing field conditions.

The PSRs were circulated to the TRPA and LRWQCB for review and comment. The *Caltrans Lake Tahoe Basin Environmental Improvement Program Delivery Plan* (Caltrans 2005b) was provided to stakeholders in the Tahoe Basin including TRPA and LRWQCB. In addition, the Caltrans Tahoe Basin Team, which includes Caltrans, TRPA, and LRWQCB representatives, met and coordinated on issues common to the planning, design, construction, and maintenance activities related to the proposed Caltrans projects in the Lake Tahoe Basin. Caltrans staff also participated in monthly

meetings with TRPA to provide input and answer questions on the overall EIP projects. Field reviews with TRPA and LRWQCB staff were conducted on specific segments to illustrate and discuss proposed water quality treatment options.

A Draft Program EIR was prepared to address the eight segments of US 50 and SR 89 defined in the PSRs, including US 50 Segment 2. The Draft Program EIR noted that additional review would be performed for each segment of the project as it is advanced in design. A number of public and agency notice and review steps were completed for the Draft Program EIR. A Notice of Preparation describing the project and planned studies for the EIR was filed with the State Clearinghouse, and comments were received³ that requested or recommended studies, records, and field review; consultation for cultural resources; and evaluation of biological habitat and potential impacts to fish, wildlife, threatened and endangered species, and water quality. These studies were performed for both the Draft Program EIR and this Initial Study (IS) for US 50 Segment 2.

The Draft Program EIR was issued for review in June 2007, and a public meeting was held to receive comments on the document. Comments on the Program EIR that pertain to US 50 Segment 2 were considered in the preparation of this IS.

3.2. Public Participation and Coordination

The mailing list developed for the Draft Program EIR was updated and used for public notification of the availability of this IS. The distribution list is included in Chapter 5.

Copies of this IS were made available for review and comment at the following locations:

Caltrans North Region Office of Environmental Management
2800 Gateway Oaks Drive
Sacramento, CA 95833

Caltrans District 3 Office
703 B Street
Marysville, CA 95901

El Dorado County Public Library
South Lake Tahoe Branch

³ The Program EIR includes copies of all comments and consultation received, and is incorporated by reference.

1000 Rufus Allen Blvd.
South Lake Tahoe, CA 96150

In addition, this IS was posted on the World Wide Web for public review at
<http://www.dot.ca.gov/dist3/departments/envinternet/envdoc.htm>.

Chapter 4. List of Preparers

The Initial Study and its supporting studies were prepared by a multidisciplinary team of environmental and engineering specialists.

Caltrans

The following individuals were involved in management, oversight, and review of the IS and its technical reports.

Jody Brown	Project Management
Christopher Carlton	Project Management
Julia Green	Archaeological Resources
Gail St. John	Architectural History
Michele Lukkarila	Natural Environment and Wetlands
Barbara Procissi	Visual Resources
Sharon Tang	Air Quality
Ben Tam	Noise
Steve Gaytan	TRPA Liaison
Anand Maganti	Water Quality
Andrew Agustinovich	Community Impacts/Land Use
Rajive Chadha	Hazardous Materials

Consultant Team

The following consultant team members were responsible for the preparation of the IS and its technical reports.

URS Corporation

David Fee	Project Management, Environmental Document Coordination
-----------	--

Sarah La Belle	Air Quality, Environmental Document Preparation and Review, TRPA issues, Community Impacts/Land Use
Christine Michalczuk	Archaeological Resources
David Halsing	Water Quality and Storm Water Runoff
Dina Robertson	Wetlands and Natural Resources
Todd Lemein	Wetlands and Natural Resources
Derek Jensen	Natural Resources/Wildlife
Lynn McIntyre	Technical Editing, Document Preparation
Deborah Fournier	Word Processing

Condor Country Consulting

Sean Dexter	Archaeological resources survey and input to the ASR
-------------	--

Illingworth & Rodkin

Michael Thill	Noise Assessment Technical Report
---------------	-----------------------------------

JRP Historical Consulting

Chris McMorris	Historical Resources Technical Report
Steve Wee	Historical Resources Technical Report

Chapter 5. Distribution List

The following agencies, organizations, and individuals received copies of this document or were notified of its availability.

Federal Agencies and Tribal Representatives

Federal Highway Administration
650 Capitol Mall, Suite 4-100
Sacramento, CA 95814

National Marine Fisheries Service
650 Capital Mall, Suite 8-300
Sacramento, CA 95814

U.S. Army Corps of Engineers
Regulatory Branch
1325 J Street
Sacramento, CA 95814-2922

U.S. Department of Interior
Office of Environmental Policy
1849 C Street, NW
Washington, DC 20585

U.S. Department of Agriculture
Natural Resources Conservation
Service
430 G Street, #4164
Davis, CA 95616-4164

U.S. Environmental Protection Agency
75 Hawthorne Street
San Francisco, CA 94105

U.S. Fish and Wildlife Service
2800 Cottage Way, Room W-2605
Sacramento, CA 95825-1846

USDA Forest Service
Lake Tahoe Basin Management Unit
35 College Drive
South Lake Tahoe, CA 96150

Washoe Tribe of CA & NV
919 Highway 395 South
Gardnerville, NV 89410

Lake Tahoe Basin Federal Advisory
Commission (LRFAC)
Ms. A. Rochelle Nason:
Environmental
Lake Tahoe Basin Management Unit
35 College Drive
South Lake Tahoe, CA 96150

State Agencies

Executive Director
Office of Planning and Research
State Clearinghouse
1400 Tenth Street
Sacramento, CA 95814

California Department of
Conservation*
801 K Street, MS 24-01
Sacramento, CA 95814

California Department of Fish and
Game*
District 2: North Central Region
1707 Nimbus Road
Rancho Cordova, CA 95670

California Department of Forestry and
Fire Protection*
Sacramento Headquarters
1416 Ninth Street
P.O. Box 944246
Sacramento, CA 94244

* Agency will receive document through State Clearinghouse.

Office of Historic Preservation*
1416 Ninth Street, Room 1442
Sacramento, CA 95814

California Department of Parks and
Recreation
Resources Management Division
P.O. Box 942896
Sacramento, CA 94296

California Department of Water
Resources*
Reclamation Board
1416 Ninth Street, Room 1601
Sacramento, CA 95814

California Department of Water
Resources*
Environmental Services Office
3251 S Street, Room 111
Sacramento, CA 95816

California Highway Patrol*
Office of Special Projects
2555 1st Avenue
Sacramento, CA 95818

California Office of Emergency
Services*
3650 Schriever Avenue
Mather, CA 95655

California Resources Agency*
1416 Ninth Street, Suite 1311
Sacramento, CA 95814

California Department of General
Services*
Environmental Services Section
1325 J Street, Suite 1910
Sacramento, CA 95814

California Air Resources Board*
Transportation Projects
1102 Q Street
Sacramento, CA 95812

California State Water Resources
Control Board*
Division of Water Quality
P.O. Box 100
Sacramento, CA 95812

California Department of Toxic
Substances Control*
700 Heinz Avenue, Suite 200
Berkeley, CA 94710

California Energy Commission
1516 Ninth Street, MS-29
Sacramento, CA 95814

Native American Heritage
Commission*
915 Capitol Mall, Room 364
Sacramento, CA 95814

Public Utilities Commission*
505 Van Ness Avenue
San Francisco, CA 94102

California State Lands Commission*
100 Howe Avenue, Suite 100 South
Sacramento, CA 95825

Regional Agencies

Tahoe Regional Planning Agency
P.O. Box 5310
Stateline, NV 89449

Lahontan Regional Water Quality
Control Board*
2501 Lake Tahoe Blvd.
South Lake Tahoe, CA 96150

***Local Agencies and
Organizations***

City of South Lake Tahoe
Administrative Center
1901 Airport Rd. Suite 206
South Lake Tahoe, CA 96150

* Agency will receive document through State Clearinghouse.

South Lake Tahoe Public Library
1000 Rufus Allen Blvd.
South Lake Tahoe, CA 96150

California-Tahoe Conservancy
1061 Third Street
South Lake Tahoe, CA 96150

Sierra Nevada Conservancy
11521 Blocker Drive, Suite 205
Auburn, CA 95603

California Conservation Corps
1949 Apache Ave
Meyers, CA 96150

El Dorado County Board of
Supervisors
330 Fair Lane
Placerville, CA 95667

El Dorado County Parks and
Recreation Commission
Jordan Postlewait
3000 Fairlane Court, Ste 1
Placerville, CA 95667

Lake Tahoe Unified School District
Superintendent
1021 Al Tahoe Blvd.
South Lake Tahoe, CA 96151

Lake Tahoe Community College
Board
One College Drive
South Lake Tahoe, CA 96150

Tahoe Heritage Foundation
P.O. Box 8586
South Lake Tahoe, CA 96158

Tahoe Sierra Preservation Council
3000 North Lake Blvd.
Tahoe City, CA 96145

League to Save Lake Tahoe
Rochelle Nason, Exec. Director
955 Emerald Bay Rd
South Lake Tahoe, CA 96150

Sierra Nevada Alliance
P.O. Box 7989
South Lake Tahoe, CA 96158

Tahoe Area Sierra Club
P.O. Box 16936
South Lake Tahoe, CA 96150

Tahoe Chapter California Native Plant
Society
P.O. Box 580
Tahoma, CA 96142

Tahoe Rim Trail Association
948 Incline Way
Incline Village, NV 89451

Lahontan Audubon Society
P.O. Box 2304
Reno, Nevada 89505

El Dorado County Library
Library Director
345 Fair Lane
Placerville, CA 95667

Placerville Mountain Democrat
1360 Broadway, PO Box 1088
Placerville, CA 95667

South Tahoe Newspaper Agency
P.O. Box 10437
South Lake Tahoe, CA 95705

Tahoe Daily Tribune
3079 Harrison Avenue
South Lake Tahoe, CA 96150

Tahoe Mountain News
PO Box 8974
South Lake Tahoe, CA 96158

Federal Elected Officials

Honorable Barbara Boxer
United States Senator
1700 Montgomery Street, Suite 240
San Francisco, CA 94111

Honorable Dianne Feinstein
United States Senator
One Post Street, Suite 2450
San Francisco, CA 94104

John T. Doolittle
4th District, United States
Representative
4230 Douglas Blvd., Suite 200
Granite Bay, CA 95746

State Elected Officials

Dave Cox
1st District, California State Senate
State Capitol, Room 2068
Sacramento, CA 95814

Ted Gaines
California State Assembly, 4th District
1700 Eureka Road, Suite 160
Roseville, CA 95661

Chapter 6. References

- Bailey 1974 R. Bailey. Land-Capability Classification of the Lake Tahoe Basin, California-Nevada: A Guide to Planning. Forest Service, U.S. Department of Agriculture in cooperation with the Tahoe Regional Planning Agency. South Lake Tahoe, CA.
- Barton HealthCare 2006 Barton HealthCare System General Web site. URL: <http://www.bartonhealth.org/>. South Lake Tahoe, CA.
- BlueGO 2006 BlueGO General Web site. URL: <http://www.bluego.org/>. Stateline, NV.
- Caltrans 1996 California Department of Transportation. California Seismic Hazard Map 1996 Based on Maximum Credible Earthquakes (MCE). Office of Earthquake Engineering. Revision 1, July 1996.
- Caltrans 2001 California Department of Transportation. Asbestos Location Map. District 3.
- Caltrans 2003a California Department of Transportation. Project Study Report—Lake Tahoe Basin Environmental Improvement Program: Route 50 in El Dorado County from Meyers Road to Incline Road, from Airport Road to Junction of Routes 89 and 50, and from Ski Run Blvd. to Nevada State Line. District 3, Division of Design and Engineering Services. Design Branch 03-253. Sacramento, CA. September 2003. Approved June 28, 2004.
- Caltrans 2003b California Department of Transportation. Project Study Report—Lake Tahoe Basin Environmental Improvement Program: Route 89 in El Dorado County from the Alpine County line to the Placer County line in Tahoma. District 3, Division of Design and Engineering Services. Design Branch 03-253. Sacramento, CA. November 2003. Approved June 28, 2004.

- Caltrans 2005a California Department of Transportation. 2004 Annual Average Daily Traffic on the California State Highway System. Compiled by Traffic and Vehicle Data Systems. Prepared in cooperation with the U.S. Department of Transportation, Federal Highway Administration. URL: <http://www.dot.ca.gov/hq/traffops/saferesr/trafdata/>.
- Caltrans 2005b California Department of Transportation. Lake Tahoe Basin Environmental Improvement Program Delivery Plan. District 3, Marysville, CA. January.
- Caltrans 2006a California Department of Transportation. Standard Construction Specifications. URL: http://www.dot.ca.gov/hq/esc/oe/specifications/std_specs/2006_StdSpecs/2006_StdSpecs.doc. May.
- Caltrans 2006b California Department of Transportation. Climate Action Program at Caltrans. December 2006.
- Caltrans 2007a California Department of Transportation. *Caltrans Stormwater Quality Handbook: Project Planning and Design Guidelines*. Office of Stormwater Management and Design. May.
- Caltrans 2007b California Department of Transportation. *Draft Program Environmental Impact Report*. El Dorado 50 and 89 Water Quality Improvement Projects, El Dorado County. Prepared for Caltrans by URS Corporation. June.
- Caltrans 2007c California Department of Transportation. Traffic and Vehicle Systems Data Unit. Traffic Volumes (Annual Average Daily Traffic) for all vehicles on California State Highways. URL: <http://traffic-counts.dot.ca.gov/2006all/r044-50i.htm>. Accessed August 2007.
- Caltrans 2007d California Department of Transportation. Initial Site Assessment for Hazardous Waste. 03-ED-50, PM 73.7–75.4, EA 1A732. Memorandum to Isam Tabshouri, Office of Design, from Rajive Chadha, North Region Hazardous Waste Office. July 31, 2007.

- Caltrans 2007e California Department of Transportation. *Visual Impact Assessment*. El Dorado County, CA, 03-ED-50, PM 73.7 to 75.4, EA 03-1A7320. Prepared for California Department of Transportation by James Williamson, North Region Office of Landscape Architecture. September 2007.
- CARB 2005 California Air Resources Board. Air quality data statistics. Aerometric Data Analysis and Management System (ADAM) database. URL: <http://www.arb.ca.gov/adam/welcome.html>.
- CCPDR, LRWQCB and TRWC 2002 Center for Collaborative Policy, Lahontan Regional Water Quality Control Board, and Truckee River Watershed Council. Draft Problem Statement: Truckee River Total Maximum Daily Load (TMDL) for Sediment. Truckee River Hydrologic Unit, Sierra, Nevada, and Placer Counties. November 18, 2002.
- CGS 1987 California Geological Survey. Geologic Map of the Sacramento Quadrangle. Sacramento, CA.
- CGS 2000a California Geological Survey. Map of California Showing Principal Asbestos Deposits. Sacramento, CA.
- CGS 2000b California Geological Survey. A General Guide for Ultramafic Rocks in California – Areas More Likely to Contain Naturally Occurring Asbestos. Open File Report 2000-19. Sacramento, CA.
- City of South Lake Tahoe 2003
1999 City of South Lake Tahoe General Plan.
- El Dorado County 2004
El Dorado County General Plan: A Plan for Managed Growth and Open Roads; A Plan for Quality Neighborhoods and Traffic Relief. Adopted by the Board of Supervisors by Resolution Number 235-2004. Accompanying Environmental Impact Report Certified July 19, 2004 (Resolution Number 234-2004; State Clearinghouse Number 2001082030). Prepared by the El Dorado County Planning Department,

Placerville, CA. URL: <http://co.el-dorado.ca.us/planning/GeneralPlan.html>. July 19.

El Dorado County Environmental Management 2007

Mosquitoes in the Tahoe Area—Precautions Against Mosquito Bites. Environmental Health Division, Vector Control. URL: <http://www.co.el-dorado.ca.us/emd/vectorcontrol/mosquitos.html>. Last updated Tuesday, June 19, 2007.

Forest Service 1988 U.S. Department of Agriculture Forest Service. *Land and Resource Management Plan*. Pacific Southwest Region, Lake Tahoe Basin Management Unit.

Forest Service 1998 U.S. Department of Agriculture Forest Service. Region 5 Sensitive Species List (June 10, 1998 Revision). US Forest Service, Region 5, San Francisco, CA. 1998.

Forest Service 2001 U.S. Department of Agriculture Forest Service. *Sierra Nevada Forest Plan Amendment, Final Environmental Impact Statement and Record of Decision*. U.S. Department of Agriculture Forest Service, Region 5, Vallejo, CA.

Forest Service 2004 U.S. Department of Agriculture Forest Service and Tahoe Regional Planning Agency. Rare plant survey and occurrence data set (provided as a shape file). 2004.

Forest Service 2005 U.S. Department of Agriculture Forest Service. Region 5 Sensitive Species List (Amended). Vallejo, CA. 2005.

Heidecker and Brown 1996

Kelly Heidecker and Jody Brown, Bartholomew & Associates, Inc. *STPUD B-Line Export Pipeline Replacement Project, Cultural Resources Inventory and Evaluation*. Prepared for the South Tahoe Public Utility District, South Lake Tahoe, California, June 1996.

Hendrix and Cori 2007

Hendrix, Michael and Wilson, Cori. *Recommendations by the Association of Environmental Professionals (AEP) on How to Analyze Greenhouse Gas Emissions and Global Climate*

Change in CEQA Documents. March 5, 2007. URL:
[http://www.califaep.org/climate%20change/
Anonymous%202.pdf](http://www.califaep.org/climate%20change/Anonymous%202.pdf).

Illingworth and Rodkin 2007

Draft Noise Report, US 50 Water Quality Improvement Project – South Tahoe Airport to Junction 50/89 (Segment 2). 03-ED-50, PM 73.7 / 75.4, EA 03-1A7320. El Dorado County, CA. Prepared for California Department of Transportation by Illingworth and Rodkin, Inc., Petaluma, CA, under contract to URS Corporation, Oakland, CA. August 2007.

JRP Historical Consulting 2007

Historic Resources Evaluation Report for the Lake Tahoe Basin Environmental Improvement Program. El Dorado 50, Segment 2 – Lake Tahoe Airport to US 50/SR 89 Junction Water Quality Improvement Project. El Dorado County, CA. 03-ED-50, PM 73.7 / 75.4, EA 03-1A7320. Prepared for California Department of Transportation under contract to URS Corporation, Oakland, CA. November 2007.

LRWQCB 1995

California Regional Water Quality Control Board, Lahontan Region. *Water Quality Control Plan for the Lahontan Region, North and South Basins (Basin Plan)*. Adopted March 31, 1995. Amendments effective August 1995 through December 2005. URL: http://www.waterboards.ca.gov/lahontan/BPlan/BPlan_Index.htm.

LTUSD 2006

Lake Tahoe Unified School District general Web site. URL: <http://www.ltusd.k12.ca.us/>. South Lake Tahoe, CA.

Martin 1998

Thomas P. Martin. *Archaeological Test Excavation at the Visitor Center Site, An Early Holocene Site in South Lake Tahoe, California*. Master of Arts Thesis submitted to Sonoma State University.

Mayer and Laudenslayer 1988

K. E. Mayer and W. F. Laudenslayer, Jr., eds. 1988. *A Guide to Wildlife Habitats of California*. State of California,

- Resources Agency, Department of Forestry and Fire,
Sacramento, CA. 1988.
- National Cooperative Highway Research Program 1999
Mitigation of Nighttime Construction Noise, Vibrations, and
Other Nuisances. National Research Council Transportation
Research Board, American Association of State Highway and
Transportation Officials, Federal Highway Administration.
National Academy Press, Washington, D.C.
- NRCS 1995 *Hydric Soils of California*. U.S. Department of Agriculture
National Resource Conservation Service. 1995.
- South Tahoe Public Utility District 2003
South Tahoe Public Utility District B III Export Pipeline
Replacement Project Draft Environmental Impact
Report/Statement. 2003.
- Tahoe Metropolitan Planning Organization 2006
*Lake Tahoe Regional Bicycle and Pedestrian Master Plan,
Final Report*. Final Draft. URL:
http://www.trpa.org/documents/docdwnlds/BIKE_PLAN.pdf
October.
- Thayer 2007 Thayer, Ted, TRPA Wildlife Biologist. Personal
communication with URS biologist regarding northern
goshawk occurrence in vicinity of ESL. September 5, 2007.
- TRPA 1982 Tahoe Regional Planning Agency. Lake Tahoe Basin Scenic
Resource Inventory. Prepared by Wagstaff and Brady for
TRPA. URL: [http://www.trpa.org/documents/about_trpa/
scenic/Scenic_Res_82Brady.pdf](http://www.trpa.org/documents/about_trpa/scenic/Scenic_Res_82Brady.pdf)
- TRPA 1987 Tahoe Regional Planning Agency. *Regional Plan for the Lake
Tahoe Basin*. Tahoe Regional Planning Agency. Stateline, NV.
- TRPA 1988 Tahoe Regional Planning Agency. *Water Quality Management
Plan for the Lake Tahoe Region (208 Plan)*. South Lake Tahoe,
CA.

- TRPA 1989a Tahoe Regional Planning Agency. Regional Plan for the Lake Tahoe Basin: Scenic Quality Improvement Program and Technical Appendices. Stateline, NV. Adopted September 27, 1989.
- TRPA 1989b Tahoe Regional Planning Agency. Regional Plan for the Lake Tahoe Basin: Design Review Guidelines. Stateline, NV. Adopted September 27, 1989.
- TRPA 1992 Tahoe Regional Planning Agency. Regional Transportation Plan/Air Quality Plan. Stateline, NV.
- TRPA 1998 Tahoe Regional Planning Agency. Regional Plan for the Lake Tahoe Basin: Meyers Community Plan. Stateline, NV.
- TRPA 2001 Tahoe Regional Planning Agency. Environmental Improvement Program (EIP Update). The Cooperative Effort to Preserve, Restore, and Enhance the Unique Natural and Human Environment of the Lake Tahoe Region. Zephyr Cove, NV. Adopted April 25.
- TRPA 2004 Tahoe Regional Planning Agency. Regional Plan for the Lake Tahoe Basin: Goals and Policies. URL: <http://www.trpa.org/documents/docdownlds/goals.pdf>. Stateline, NV.
- URS 2007a *Community Impact Assessment, El Dorado 50, Segment 2 – Lake Tahoe Airport to US 50/SR 89 Junction Water Quality Improvement Project, El Dorado County, CA.* 03-ED-50, PM 73.7 / 75.4, EA 03-1A7320. Prepared for California Department of Transportation by URS Corporation, Oakland, CA. October 2007.
- URS 2007b *Historical Property Survey Report.* El Dorado County, CA, 03-ED-50, PM 73.7 / 75.4, EA 03-1A7320. Prepared for California Department of Transportation by URS Corporation, Oakland, CA. October 2007.
- URS 2007c *Water Quality Study, Lake Tahoe Environmental Improvement Program. El Dorado 50, Segment 2 – South Lake Tahoe*

- Airport to Junction US 50/SR 89 Junction Water Quality Improvement Project, El Dorado County, California.* 03-ED-50, PM 73.7 / 75.4, EA 03-1A7320. Prepared for California Department of Transportation by URS Corporation, Oakland, CA. October 2007.
- URS 2007d *US 50 Water Quality Improvement Project – South Tahoe Airport to Junction 50/89 (Segment 2) – Air Quality Evaluation.* Prepared for California Department of Transportation by URS Corporation, Oakland, CA. August 22 2007.
- URS 2007e *Draft Natural Environment Study, El Dorado County, California. El Dorado 50, Segment 2 – Lake Tahoe Airport to US 50/SR 89 Junction Water Quality Improvement Project.* 03-ED-50, PM 73.7 / 75.4, EA 03-1A7320. California Department of Transportation. Prepared for Caltrans by URS Corporation. November 2007.
- URS 2007f *Wetland Delineation Report, El Dorado County, California. El Dorado 50, Segment 2 – Lake Tahoe Airport to US 50/SR 89 Junction Water Quality Improvement Project.* 03-ED-50, PM 73.7 / 75.4, EA 03-1A7320. California Department of Transportation. Prepared for Caltrans by URS Corporation. November 2007.
- URS and Condor Country Consulting 2007
Archaeological Survey Report, Lake Tahoe Basin Environmental Improvement Program, U.S. Highway 50, Segment 2, South Tahoe Airport to Junction US 50/SR 89 Water Quality Improvement Project, El Dorado County, California. 03-ED-50, PM 73.7 to 75.4, EA 03-1A7320. Prepared for California Department of Transportation by URS Corporation, Oakland, CA, and Condor Country Consulting, Martinez, CA. October 2007.
- U.S. Census Bureau. 2000
Decennial Census. URL: <http://www.census.gov>. Washington, DC.

- USDA 1974 U.S. Department of Agriculture. Soil Survey of the Tahoe Basin Area, California and Nevada. U.S. Department of Agriculture Soil Conservation Service and Forest Service in cooperation with University of California Agricultural Experiment Station and Nevada Agricultural Experiment Station. 1974.
- USEPA 1971 U.S. Environmental Protection Agency. Noise from Construction Equipment and Operation, Building Equipment, and Home Appliances. December.
- USEPA 1973 U.S. Environmental Protection Agency. Legal Compilation on Noise, Vol. 1, p. 2-104.
- USGS 1996 U.S. Geological Survey. Surface and Groundwater Characteristics in the Upper Truckee River and Trout Creek Watersheds, South Lake Tahoe, California and Nevada. July-December 1996. Water Resources Investigations Report 00-4001. Timothy G. Rowe and Kip K. Allander.

Chapter 7. List of Technical Studies

Air Quality Evaluation (URS, August 2007)

Archaeological Survey Report (URS and Condor Country Consulting, October 2007)

Community Impact Assessment (URS, October 2007)

Historical Resources Evaluation Report (JRP Historical Consulting, November 2007)

Historic Property Survey Report (URS, October 2007)

Natural Environment Study (URS, November 2007)

Noise Report (Illingworth and Rodkin, August 2007)

Visual Impact Assessment (Caltrans, September 2007)

Water Quality Study (URS, October 2007)

Wetland Delineation Report (URS, November 2007)

Appendix A Project Plans

The following map sheets depict the limits of construction for the proposed project on aerial photograph base maps and include proposed basins, drainage features, and roadway pullouts. Also shown is the study area used for environmental studies.


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
03	ED	50	73.7/75.4		

REGISTERED CIVIL ENGINEER DATE _____
 PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF ELECTRONIC COPIES OF THIS PLAN SHEET.



URS CORPORATION
 1380 LEAD HILL BLVD
 SUITE 100
 ROSEVILLE, CA 95661

CURVE DATA				
No.	R	Δ	T	L
①	1400.00'	19°57'30"	246.33'	487.67'
②	8500.00'	2°07'45"	157.96'	315.88'



BEGIN PROJECT
 PM 73.7
 KP 118.6

PROJECT CONFORM "K" 889+34.38
 BEGIN UNIFORM AC OVERLAY

16.00 L+ "K" 889+34.38
 CONFORM

16.00 R+ "K" 889+34.38
 CONFORM

033-050-011

033-131-021

033-050-061

033-050-111

ALL DIMENSIONS ARE IN FEET
 UNLESS OTHERWISE SHOWN

ESL LAYOUT

SCALE: 1" = 50'

L-1

REVISOR BY DATE

CALCULATED BY DESIGNED BY CHECKED BY

DESIGN OVERSIGHT

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION




Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
03	ED	50	73.7/75.4		

REGISTERED CIVIL ENGINEER DATE _____
 PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF ELECTRONIC COPIES OF THIS PLAN SHEET.



URS CORPORATION
 1380 LEAD HILL BLVD
 SUITE 100
 ROSEVILLE, CA 95661

CURVE DATA				
No.	R	Δ	T	L
④	2700.00'	18°34'16"	441.44'	875.14'



STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
 FILE NAME: \$FILE
 \$Revision: 1
 \$Date: 11/1/2006

DESIGN OVERSIGHT
 CALCULATED/DESIGNED BY
 CHECKED BY
 REVISOR BY
 DATE REVISOR

ALL DIMENSIONS ARE IN FEET UNLESS OTHERWISE SHOWN
ESL LAYOUT
 SCALE: 1" = 50'

L-3


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
03	ED	50	73.7/75.4		

REGISTERED CIVIL ENGINEER DATE _____
 PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF ELECTRONIC COPIES OF THIS PLAN SHEET.



URS CORPORATION
 1380 LEAD HILL BLVD
 SUITE 100
 ROSEVILLE, CA 95661

CURVE DATA				
No.	R	Δ	T	L
⑤	3400.00'	3°54'58"	116.24'	232.39'
⑥	1560.00'	40°04'29"	568.95'	1091.12'



ALL DIMENSIONS ARE IN FEET
 UNLESS OTHERWISE SHOWN

ESL LAYOUT

SCALE: 1" = 50'

L-4

REVISOR BY DATE

CALCULATED BY DESIGNED BY

CHECKED BY

DESIGN OVERSIGHT

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION

FILE NAME: \$FILE

STATE OF CALIFORNIA

STATE OF CALIFORNIA

STATE OF CALIFORNIA


STATE OF CALIFORNIA

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
03	ED	50	73.7/75.4		

REGISTERED CIVIL ENGINEER DATE _____
 PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF ELECTRONIC COPIES OF THIS PLAN SHEET.



URS CORPORATION
 1380 LEAD HILL BLVD
 SUITE 100
 ROSEVILLE, CA 95661



REVISOR BY DATE

REVISOR BY DATE

REVISOR BY DATE

REVISOR BY DATE

DESIGN OVERSIGHT

DESIGN OVERSIGHT

DESIGN OVERSIGHT

DESIGN OVERSIGHT

DESIGN OVERSIGHT

DESIGN OVERSIGHT

ALL DIMENSIONS ARE IN FEET UNLESS OTHERWISE SHOWN

ESL LAYOUT

SCALE: 1" = 50'

L-5




Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
03	ED	50	73.7/75.4		

REGISTERED CIVIL ENGINEER DATE _____
 PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF ELECTRONIC COPIES OF THIS PLAN SHEET.



URS CORPORATION
 1380 LEAD HILL BLVD
 SUITE 100
 ROSEVILLE, CA 95661



Match Line

Match Line

ALL DIMENSIONS ARE IN FEET UNLESS OTHERWISE SHOWN

ESL LAYOUT

SCALE: 1" = 50'

L-6

REVISOR BY DATE

CALCULATED BY DESIGNED BY CHECKED BY

DESIGN OVERSIGHT

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION




Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
03	ED	50	73.7/75.4		

REGISTERED CIVIL ENGINEER DATE _____
 PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF ELECTRONIC COPIES OF THIS PLAN SHEET.



URS CORPORATION
 1380 LEAD HILL BLVD
 SUITE 100
 ROSEVILLE, CA 95661

CURVE DATA				
No.	R	Δ	T	L
⑦	2500.00'	5°00'32"	109.35'	218.56'



ALL DIMENSIONS ARE IN FEET UNLESS OTHERWISE SHOWN

ESL LAYOUT

SCALE: 1" = 50'

L-7

REVISOR BY DATE

CALCULATED BY DESIGNED BY CHECKED BY

DESIGN OVERSIGHT

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans

BORDER LAST REVISED 11/1/2006

RELATIVE BORDER SCALE 15 IN INCHES

USERNAME => DGN FILE => ESL-07.dgn

CU 00000

EA 1A7320

LAST REVISION DATE PLOTTED => 11/6/2007
 TIME PLOTTED => 3:14:11 PM

Appendix B CEQA Checklist

The following checklist identifies physical, biological, social, and economic factors that might be affected by the proposed project. The CEQA impact levels include potentially significant impact, less-than-significant impact with mitigation, less-than-significant impact, and no impact. Please refer to the following for detailed discussions regarding impacts:

- Guidance: Title 14, Chapter 3, California Code of Regulations, Sections 15000 et seq. (http://www.ceres.ca.gov/topic/env_law/ceqa/guidelines/)
- Statutes: Division 13, California Public Resources Code, Sections 21000-21178.1 (http://www.ceres.ca.gov/topic/env_law/ceqa/stat/)

CEQA requires that environmental documents determine significant or potentially significant impacts. In many cases, background studies performed in connection with the project indicate no impacts. A “no impact” reflects this determination.

Supporting documentation of all CEQA checklist determinations is provided in Chapter 2. Documentation of “No Impact” determinations is provided at the beginning of Chapter 2. Discussion of all impacts, avoidance, minimization, and/or mitigation measures is under the appropriate topic headings in Chapter 2.

Potentially significant impact	Less than significant impact with mitigation	Less than significant impact	No impact
--------------------------------	--	------------------------------	-----------

AESTHETICS - Would the project:

- | | | | | |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|
| a) Have a substantial adverse effect on a scenic vista? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| b) Substantially damage scenic resources, including, but not limited to, trees, rock outcroppings, and historic building within a state scenic highway? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| c) Substantially degrade the existing visual character or quality of the site and its surroundings? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| d) Create a new source of substantial light or glare which would adversely affect day or nighttime views in the area? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |

AGRICULTURE RESOURCES - In determining whether impacts to agricultural resources are significant environmental effects, lead agencies may refer to the California Agricultural Land Evaluation and Site Assessment Model (1997) prepared by the California Dept. of Conservation as an optional model to use in assessing impacts on agriculture and farmland. Would the project:

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| a) Convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland), as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, to nonagricultural use? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| b) Conflict with existing zoning for agricultural use, or a Williamson Act contract? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| c) Involve other changes in the existing environment which, due to their location or nature, could result in conversion of Farmland, to nonagricultural use? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

AIR QUALITY - Where available, the significance criteria established by the applicable air quality management or air pollution control district may be relied upon to make the following determinations. Would the project:

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| a) Conflict with or obstruct implementation of the applicable air quality plan? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Potentially significant impact	Less than significant impact with mitigation	Less than significant impact	No impact
--------------------------------	--	------------------------------	-----------

b) Violate any air quality standard or contribute substantially to an existing or projected air quality violation?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

c) Result in a cumulatively considerable net increase of any criteria pollutant for which the project region is nonattainment under an applicable federal or state ambient air quality standard (including releasing emissions which exceed quantitative thresholds for ozone precursors)?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

d) Expose sensitive receptors to substantial pollutant concentration?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

e) Create objectionable odors affecting a substantial number of people?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

BIOLOGICAL RESOURCES - Would the project:

a) Have a substantial adverse effect, either directly or through habitat modifications, on any species identified as a candidate, sensitive, or special-status species in local or regional plans, policies, or regulations, or by the California Department of Fish and Game or U.S. Fish and Wildlife Service?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

b) Have a substantial adverse effect on any riparian habitat or other sensitive natural community identified in local or regional plans, policies, regulations or by the California Department of Fish and Game or U.S. Fish and Wildlife Service?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

c) Have a substantial adverse effect on federally protected wetlands as defined by Section 404 of the Clean Water Act (including, but not limited to, marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

d) Interfere substantially with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native wildlife nursery sites?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

e) Conflict with any local policies or ordinances protecting biological resources, such as a tree preservation policy or ordinance?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

Potentially significant impact	Less than significant impact with mitigation	Less than significant impact	No impact
--------------------------------	--	------------------------------	-----------

f) Conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

CULTURAL RESOURCES - Would the project:

a) Cause a substantial adverse change in the significance of a historical resource as defined in §15064.5?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

b) Cause a substantial adverse change in the significance of an archaeological resource pursuant to §15064.5?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

c) Directly or indirectly destroy a unique paleontological resource or site or unique geologic feature?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

d) Disturb any human remains, including those interred outside of formal cemeteries?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

GEOLOGY AND SOILS - Would the project:

a) Expose people or structures to potential substantial adverse effects, including the risk of loss, injury, or death involving:

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

i) Rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault? Refer to Division of Mines and Geology Special Publication 42.

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

ii) Strong seismic ground shaking?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

iii) Seismic-related ground failure, including liquefaction?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

iv) Landslides?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

b) Result in substantial soil erosion or the loss of topsoil?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

Potentially significant impact	Less than significant impact with mitigation	Less than significant impact	No impact
--------------------------------	--	------------------------------	-----------

c) Be located on a geologic unit or soil that is unstable, or that would become unstable as a result of the project, and potentially result in on- or off-site landslide, lateral spreading, subsidence, liquefaction or collapse?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

d) Be located on expansive soil, as defined in Table 18-1-B of the Uniform Building Code (1994), creating substantial risks to life or property.

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

e) Have soils incapable of adequately supporting the use of septic tanks or alternative waste water disposal systems where sewers are not available for the disposal of waste water?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

HAZARDS AND HAZARDOUS MATERIALS –
Would the project:

a) Create a significant hazard to the public or the environment through the routine transport, use, or disposal of hazardous materials?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

b) Create a significant hazard to the public or the environment through reasonably foreseeable upset and accident conditions involving the release of hazardous materials into the environment?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

c) Emit hazardous emissions or handle hazardous or acutely hazardous material, substances, or waste within one-quarter mile of an existing or proposed school?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

d) Be located on a site which is included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 and, as a result, would it create a significant hazard to the public or the environment?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

e) For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the project result in a safety hazard for people residing or working in the project area?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

f) For a project within the vicinity of a private airstrip, would the project result in a safety hazard for people residing or working in the project area?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

g) Impair implementation of or physically interfere with an adopted emergency response plan or emergency evacuation plan?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

Potentially significant impact	Less than significant impact with mitigation	Less than significant impact	No impact
--------------------------------	--	------------------------------	-----------

h) Expose people or structures to a significant risk of loss, injury or death involving wildland fires, including where wildlands are adjacent to urbanized areas or where residences are intermixed with wildlands?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

HYDROLOGY AND WATER QUALITY - Would the project:

a) Violate any water quality standards or waste discharge requirements?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

b) Substantially deplete groundwater supplies or interfere substantially with groundwater recharge such that there would be a net deficit in aquifer volume or a lowering of the local groundwater table level (e.g., the production rate of pre-existing nearby wells would drop to a level which would not support existing land uses or planned uses for which permits have been granted)?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

c) Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river, in a manner which would result in substantial erosion or siltation on- or off-site?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

d) Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river, or substantially increase the rate or amount of surface runoff in a manner which would result in flooding on- or off-site?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

e) Create or contribute runoff water which would exceed the capacity of existing or planned storm water drainage systems or provide substantial additional sources of polluted runoff?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

f) Otherwise substantially degrade water quality?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

g) Place housing within a 100-year flood hazard area as mapped on a Federal Flood Hazard Boundary or Flood Insurance Rate Map or other flood hazard delineation map?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

h) Place within a 100-year flood hazard area structures which would impede or redirect flood flows?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

i) Expose people or structures to a significant risk of loss, injury or death involving flooding, including flooding as a result of the failure of a levee or dam?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

Potentially significant impact	Less than significant impact with mitigation	Less than significant impact	No impact
--------------------------------	--	------------------------------	-----------

j) Inundation by seiche, tsunami, or mudflow?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

LAND USE AND PLANNING - Would the project:

a) Physically divide an established community?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

b) Conflict with any applicable land use plan, policy, or regulation of an agency with jurisdiction over the project (including, but not limited to the general plan, specific plan, local coastal program, or zoning ordinance) adopted for the purpose of avoiding or mitigating an environmental effect?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

c) Conflict with any applicable habitat conservation plan or natural community conservation plan?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

MINERAL RESOURCES - Would the project:

a) Result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

b) Result in the loss of availability of a locally important mineral resource recovery site delineated on a local general plan, specific plan or other land use plan?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

NOISE - Would the project:

a) Exposure of persons to or generation of noise levels in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

b) Exposure of persons to or generation of excessive groundborne vibration or groundborne noise levels?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

c) A substantial permanent increase in ambient noise levels in the project vicinity above levels existing without the project?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

d) A substantial temporary or periodic increase in ambient noise levels in the project vicinity above levels existing without the project?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

Potentially significant impact	Less than significant impact with mitigation	Less than significant impact	No impact
--------------------------------	--	------------------------------	-----------

e) For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the project expose people residing or working in the project area to excessive noise levels?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

f) For a project within the vicinity of a private airstrip, would the project expose people residing or working in the project area to excessive noise levels?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

POPULATION AND HOUSING - Would the project:

a) Induce substantial population growth in an area, either directly (for example, by proposing new homes and businesses) or indirectly (for example, through extension of roads or other infrastructure)?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

b) Displace substantial numbers of existing housing, necessitating the construction of replacement housing elsewhere?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

c) Displace substantial numbers of people, necessitating the construction of replacement housing elsewhere?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

PUBLIC SERVICES -

a) Would the project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for any of the public services:

Fire protection?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

Police protection?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

Schools?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

Parks?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

Other public facilities?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

Potentially significant impact	Less than significant impact with mitigation	Less than significant impact	No impact
--------------------------------	--	------------------------------	-----------

RECREATION -

a) Would the project increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

b) Does the project include recreational facilities or require the construction or expansion of recreational facilities which might have an adverse physical effect on the environment?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

TRANSPORTATION/TRAFFIC - Would the project:

a) Cause an increase in traffic which is substantial in relation to the existing traffic load and capacity of the street system (i.e., result in a substantial increase in either the number of vehicle trips, the volume to capacity ratio on roads, or congestion at intersections)?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

b) Exceed, either individually or cumulatively, a level of service standard established by the county congestion management agency for designated roads or highways?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

c) Result in a change in air traffic patterns, including either an increase in traffic levels or a change in location that results in substantial safety risks?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

d) Substantially increase hazards due to a design feature (e.g., sharp curves or dangerous intersections) or incomplete uses (e.g., farm equipment)?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

e) Result in inadequate emergency access?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

f) Result in inadequate parking capacity?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

g) Conflict with adopted policies, plans, or programs supporting alternative transportation (e.g., bus turnouts, bicycle racks)?

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	-------------------------------------	--------------------------

UTILITY AND SERVICE SYSTEMS - Would the project:

a) Exceed wastewater treatment requirements of the applicable Regional Water Quality Control Board?

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

Potentially significant impact	Less than significant impact with mitigation	Less than significant impact	No impact
--------------------------------	--	------------------------------	-----------

b) Require or result in the construction of new water or wastewater treatment facilities or expansion of existing facilities, the construction of which could cause significant environmental effects?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Require or result in the construction of new storm water drainage facilities or expansion of existing facilities, the construction of which could cause significant environmental effects?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
d) Have sufficient water supplies available to serve the project from existing entitlements and resources, or are new or expanded entitlements needed?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e) Result in determination by the wastewater treatment provider which serves or may serve the project that it has adequate capacity to serve the project's projected demand in addition to the provider's existing commitments?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f) Be served by a landfill with sufficient permitted capacity to accommodate the project's solid waste disposal needs?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
g) Comply with federal, state, and local statutes and regulations related to solid waste?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

MANDATORY FINDINGS OF SIGNIFICANCE -

a) Does the project have the potential to degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, or cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California history or prehistory?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b) Does the project have impacts that are individually limited, but cumulatively considerable? ("Cumulatively considerable" means that the incremental effects of a project are considerable when viewed in connection with the effects of past projects, the effects of other current projects, and the effects of probable future projects)?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c) Does the project have environmental effects which will cause substantial adverse effects on human beings, either directly or indirectly?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Appendix C Tahoe Regional Planning Agency Initial Environmental Checklist

This appendix presents the TRPA Initial Environmental Checklist for Determination of Environmental Impact. The information in this checklist has also been summarized under the appropriate topic headings in Chapter 2.



INITIAL ENVIRONMENTAL CHECKLIST FOR DETERMINATION OF ENVIRONMENTAL IMPACT

I. Assessor's Parcel Number (APN)/Project Location: *Mostly within Caltrans right-of-way
Other parcels included are:
032-141-041, 032-141-031, 032-192-071, 032-191-061
032-191-041, 032-141-011*

Project Name *El Dorado 50, Segment 2 – Airport Road to the “Y”
Junction of US 50/SR 89* **County/City** *El Dorado County*

Brief Description of Project

The California Department of Transportation (Caltrans) proposes to improve the quality of storm water runoff for the segment of United States Route 50 (US 50) between the South Lake Tahoe Airport and the “Y” at the junction of US 50 and State Route (SR) 89 in the City of South Lake Tahoe. The project will involve installing slope stability and protection measures, and installing facilities to collect and direct storm water runoff from the state highway and right-of-way. The project is needed to meet National Pollutant Discharge Elimination System (NPDES) permit requirements and address planned water quality improvements that are part of the Lake Tahoe Basin Environmental Improvement Program (EIP).

The proposed project is located in El Dorado County approximately 1.5 miles south of Lake Tahoe. The project limits extend for approximately 1.7 miles along a segment of US 50, from the South Lake Tahoe Airport to the “Y” junction of US 50 and SR 89 in the City of South Lake Tahoe, California. This segment of US 50 is relatively flat. Lands along this segment are primarily divided into individual private parcels, both developed and undeveloped. The South Lake Tahoe airport is adjacent to this segment on the east. The project is one of eight segments of SR 89 and US 50 where similar water quality improvements are proposed. This project is also referred to as “US 50 Segment 2.”

The following questionnaire will be completed by the applicant based on evidence submitted with the application. All “Yes” and “No, With Mitigation” answers will require further written comments.

II. Environmental Impacts:

1. Land (See Section 2.9, Soils, Soil Conservation, and Geology, of the Initial Study)

Will the proposal result in:

a. Compaction or covering of the soil beyond the limits allowed in the land capability or Individual Parcel Evaluation System (IPES)?

- Yes No
 No, With Mitigation Data Insufficient

b. A change in the topography or ground surface relief features of site inconsistent with the natural surrounding conditions?

- Yes No
 No, With Mitigation Data Insufficient

c. Unstable soil conditions during or after completion of the proposal?

- Yes No
 No, With Mitigation Data Insufficient

d. Changes in the undisturbed soil or native geologic substructures or grading in excess of 5 feet?

- Yes No
 No, With Mitigation Data Insufficient

e. The continuation of or increase in wind or water erosion of soils, either on or off the site?

- Yes No
 No, With Mitigation Data Insufficient

f. Changes in deposition or erosion of beach sand, or changes in siltation, deposition or erosion, including natural littoral processes, which may modify the channel of a river or stream or the bed of a lake?

- Yes No
 No, With Mitigation Data Insufficient

g. Exposure of people or property to geologic hazards such as earthquakes, landslides, backshore erosion, avalanches, mud slides, ground failure, or similar hazards?

- Yes No
 No, With Mitigation Data Insufficient

2. Air Quality (See Section 2.11, Air Quality, of the Initial Study)

Will the proposal result in:

a. Substantial air pollutant emissions?

- Yes No
 No, With Mitigation Data Insufficient

b. Deterioration of ambient (existing) air quality?

- Yes No
 No, With Mitigation Data Insufficient

c. The creation of objectionable odors?

- Yes No
 No, With Mitigation Data Insufficient

d. Alteration of air movement, moisture or temperature, or any change in climate, either locally or regionally?

- Yes No
 No, With Mitigation Data Insufficient

e. Increased use of diesel fuel?

- Yes No
 No, With Mitigation Data Insufficient

Explanation:

c. Pavement resurfacing would create temporary odors. This effect would be very limited in duration.

e. The use of diesel fuel by construction equipment would be temporary.

3. Water Quality (See Sections 2.7, Hydrology and Floodplains, and 2.8, Water Quality and Storm Water Runoff, of the Initial Study)

Will the proposal result in:

a. Changes in currents, or the course or direction of water movements?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

b. Changes in absorption rates, drainage patterns, or the rate and amount of surface water runoff so that a 20 yr. 1 hr. storm runoff (approximately 1 inch per hour) cannot be contained on the site?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

c. Alterations to the course or flow of 100-yearflood waters

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

d. Change in the amount of surface water in any water body?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

e. Discharge into surface waters, or in any alteration of surface water quality, including but not limited to temperature, dissolved oxygen or turbidity?

- | | | | |
|-------------------------------------|---------------------|--------------------------|-------------------|
| <input checked="" type="checkbox"/> | Yes | <input type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

f. Alteration of the direction or rate of flow of ground water

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

g. Change in the quantity of groundwater, either through direct additions or withdrawals, or through interception of an aquifer by cuts or excavations?

- | | | | |
|-------------------------------------|---------------------|--------------------------|-------------------|
| <input checked="" type="checkbox"/> | Yes | <input type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

h. Substantial reduction in the amount of water otherwise available for public water supplies?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

i. Exposure of people or property to water related hazards such as flooding?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

j. The potential discharge of contaminants to the groundwater or any alteration of groundwater quality?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

k. Is the project located within 600 feet of a drinking water source?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

Explanation:

e. Impacts to drainage patterns will be minor and will be limited to directing runoff into new drainage basins and other facilities. Drainage basins are intended to substantially contribute to containing runoff on-site, consistent with the TRPA criteria of containing a 20-year, 1-hour storm. In addition, the new drainage basins and other facilities will capture many pollutants before they enter area waterways.

g. The project will increase the infiltration of storm water runoff into groundwater.

4. Vegetation (See Section 2.16, Plant Species, of the Initial Study)

Will the proposal result in:

a. Removal of native vegetation in excess of the area utilized for the actual development permitted by the land capability/IPES system?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

b. Removal of riparian vegetation or other vegetation associated with critical wildlife habitat, either through direct removal or indirect lowering of the groundwater table?

- | | | | |
|-------------------------------------|---------------------|--------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input type="checkbox"/> | No |
| <input checked="" type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

c. Introduction of new vegetation that will require excessive fertilizer or water, or will provide a barrier to the normal replenishment of existing species?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

d. Change in the diversity or distribution of species, or number of any species of plants (including trees, shrubs, grass, crops, micro flora and aquatic plants)?

- | | | | |
|-------------------------------------|---------------------|--------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input type="checkbox"/> | No |
| <input checked="" type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

e. Reduction of the numbers of any unique, rare or endangered species of plants?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

f. Removal of stream bank and/or backshore vegetation, including woody vegetation such as willows?

- | | | | |
|-------------------------------------|---------------------|--------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input type="checkbox"/> | No |
| <input checked="" type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

g. Removal of any native live, dead or dying trees 30 inches or greater in diameter at breast height (dbh) within TRPA's Conservation or Recreation land use classifications?

- | | | | |
|-------------------------------------|---------------------|--------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input type="checkbox"/> | No |
| <input checked="" type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

h. A change in the natural functioning of an old growth ecosystem

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

Explanation:

b. Some removal of riparian vegetation may be required. Removal of riparian vegetation will be kept to a minimum. Efforts to restore previously disturbed areas will be attempted where possible.

d. Some trees and vegetation may be removed where basin and other drainage facilities are proposed. Impacts to trees and existing vegetation will be minimized during the design of the drainage facilities.

f. Construction at stream banks and creeks will be minimized.

g. The proper permits will be obtained prior to the removal of any native live, dead or dying trees 30 inches or greater in diameter at breast height (dbh) within land classified for Conservation or Recreation uses.

5. Wildlife (See Sections 2.17, Animal Species, and 2.18, Threatened and Endangered Species, of the Initial Study)

Will the proposal result in:

- a. Change in the diversity or distribution of species, or numbers of any species of animals (birds, land animals including reptiles, fish and shellfish, benthic organisms, insects, mammals, amphibians or microfauna)?
- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |
- b. Reduction of the number of any unique, rare or endangered species of animals?
- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |
- c. Introduction of new species of animals into an area, or result in a barrier to the migration or movement of animals?
- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |
- d. Deterioration of existing fish or wildlife habitat quantity or quality?
- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

6. Noise (See Section 2.13, Noise, of the Initial Study)

Will the proposal result in:

- a. Increases in existing Community Noise Equivalency Levels (CNEL) beyond those permitted in the applicable Plan Area Statement, Community Plan or Master Plan?
- | | | | |
|-------------------------------------|---------------------|--------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input type="checkbox"/> | No |
| <input checked="" type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |
- b. Exposure of people to severe noise levels
- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |
- c. Single event noise levels greater than those set forth in the TRPA Noise Environmental Threshold?
- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

Explanation:

a. The project would not contribute any new traffic, and therefore the project will not change traffic-related noise levels with respect to the TRPA CNEL noise thresholds. The noise thresholds could be exceeded during times of heavy or sustained construction activities. TRPA-approved construction projects are exempt from the TRPA Noise Ordinance if the construction activities occur between the daytime hours of 8:00 a.m. and 6:30 p.m.

7. Light and Glare (See Section 2.5, Visual and Aesthetics, of the Initial Study)

Will the proposal:

- a. Include new or modified sources of exterior lighting?
- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |
- b. Create new illumination, which is more substantial than other lighting, if any, within the surrounding area?
- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |
- c. Cause light from exterior sources to be cast off –site or onto public lands?
- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |
- d. Create new sources of glare through the siting of the improvements or through the use of reflective materials?
- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

8. Land Use (See Section 2.1, Land Use, of the Initial Study)

Will the proposal:

a. Include uses which are not listed as permissible uses in the applicable Plan Area Statement, adopted Community Plan, or Master Plan?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

b. Expand or intensify an existing non-conforming use?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

9. Natural Resources

Will the proposal result in:

a. A substantial increase in the rate of use of any natural resources?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

b. Substantial depletion of any non-renewable natural resource?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

10. Risk of Upset (See Section 2.10, Hazardous Waste/Materials, of the Initial Study)

Will the proposal:

a. Involve a risk of an explosion or the release of hazardous substances including, but not limited to, oil, pesticides, chemicals, or radiation in the event of an accident or upset conditions?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

b. Involve possible interference with an emergency evacuation plan?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

11. Population

Will the proposal:

a. Alter the location, distribution, density, or growth rate of the human population planned for the Region?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

b. Include or result in the temporary or permanent displacement of residents?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

12. Housing

Will the proposal:

- a. Affect existing housing, or create a demand for additional housing?

To determine if the proposal will affect existing housing or create a demand for additional housing, please answer the following questions:

- (1) Will the proposal decrease the amount of housing in the Tahoe Region?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

- (2) Will the proposal decrease the amount of housing in the Tahoe Region historically or currently being rented at rates affordable by lower and very-low-income households?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

- b. Will the proposal result in the loss of housing for lower-income and very-low-income households?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

Number of Existing Dwelling Units: _____
Number of Proposed Dwelling Units: _____

13. Transportation/Circulation (See Section 2.4, Traffic and Transportation Facilities, of the Initial Study)

Will the proposal result in:

- a. Generation of 100 or more new Daily Vehicle Trip Ends (DVTE)?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

- b. Changes to existing parking facilities, or demand for new parking?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

- c. Substantial impact upon existing transportation systems, including highway, transit, bicycle or pedestrian facilities?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

- d. Alterations to present patterns of circulation or movement of people and/or goods?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

- e. Alterations to waterborne, rail or air traffic?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

- f. Increase in traffic hazards to motor vehicles, bicyclists, or pedestrians?

- | | | | |
|--------------------------|---------------------|-------------------------------------|-------------------|
| <input type="checkbox"/> | Yes | <input checked="" type="checkbox"/> | No |
| <input type="checkbox"/> | No, With Mitigation | <input type="checkbox"/> | Data Insufficient |

14. Public Services (See Sections 2.2, Community Impacts, and 2.3, Utilities/Emergency Services, of the Initial Study)

Will the proposal have an unplanned effect upon, or result in a need for new or altered governmental services in any of the following areas?

- a. Fire protection?
 Yes No
 No, With Mitigation Data Insufficient
- b. Police protection?
 Yes No
 No, With Mitigation Data Insufficient
- c. Schools?
 Yes No
 No, With Mitigation Data Insufficient
- d. Parks or other recreational facilities?
 Yes No
 No, With Mitigation Data Insufficient
- e. Maintenance of public facilities, including roads?
 Yes No
 No, With Mitigation Data Insufficient
- f. Other governmental services?
 Yes No
 No, With Mitigation Data Insufficient

15. Energy

Will the proposal result in:

- a. Use of substantial amounts of fuel or energy?
 Yes No
 No, With Mitigation Data Insufficient
- b. Substantial increases in demand upon existing sources of energy, or require the development of new sources of energy?
 Yes No
 No, With Mitigation Data Insufficient

16. Utilities (See Section 2.3, Utilities/Emergency Services, of the Initial Study)

Except for planned improvements, will the proposal result in a need for new systems, or substantial alterations to the following utilities:

- a. Power or natural gas?
 Yes No
 No, With Mitigation Data Insufficient
- b. Communication systems?
 Yes No
 No, With Mitigation Data Insufficient
- c. Utilize additional water which amount will exceed the maximum permitted capacity of the service provider?
 Yes No
 No, With Mitigation Data Insufficient
- d. Utilize additional sewage treatment capacity which amount will exceed the maximum permitted capacity of the sewage treatment provider?
 Yes No
 No, With Mitigation Data Insufficient
- e. Storm water drainage?
 Yes No
 No, With Mitigation Data Insufficient
- f. Solid waste and disposal?
 Yes No
 No, With Mitigation Data Insufficient

17. Human Health (See Section 2.10, Hazardous Waste/Materials, of the Initial Study)

Will the proposal result in:

- a. Creation of any health hazard or potential health hazard (excluding mental health)?
 Yes No
 No, With Mitigation Data Insufficient
- b. Exposure of people to potential health hazards?
 Yes No
 No, With Mitigation Data Insufficient

18. Scenic Resources/Community Design (See Section 2.5, Visual and Aesthetics, of the Initial Study)

Will the proposal:

- a. Be visible from any state or federal highway or from Lake Tahoe?
 Yes No
 No, With Mitigation Data Insufficient
- b. Be visible from any public recreation area or TRPA designated bicycle trail?
 Yes No
 No, With Mitigation Data Insufficient
- c. Block or modify an existing view of Lake Tahoe or other scenic vista seen from a public road or other public area?
 Yes No
 No, With Mitigation Data Insufficient
- d. Be inconsistent with the height and design standards required by the applicable ordinance or Community Plan?
 Yes No
 No, With Mitigation Data Insufficient
- e. Be inconsistent with the TRPA Scenic Quality Improvement Program (SQIP) or Design Review Guidelines?
 Yes No
 No, With Mitigation Data Insufficient

Explanation:

- a. The project would be visible from US 50.

19. Recreation (See Section 2.1, Land Use, of the Initial Study)

Does the proposal:

- a. Create additional demand for recreation facilities?
 Yes No
 No, With Mitigation Data Insufficient
- b. Create additional recreation capacity?
 Yes No
 No, With Mitigation Data Insufficient
- c. Have the potential to create conflicts between recreation uses, either existing or proposed?
 Yes No
 No, With Mitigation Data Insufficient
- d. Result in a decrease or loss of public access to any lake, waterway, or public lands?
 Yes No
 No, With Mitigation Data Insufficient

20. Archaeological/Historical (See Section 2.6, Cultural Resources, of the Initial Study)

a. Will the proposal result in an alteration of or adverse physical or aesthetic effect to a significant archaeological or historical site, structure, object or building?

- Yes No
 No, With Mitigation Data Insufficient

b. Is the proposed project located on a property with any known cultural, historical, and/or archaeological resources, including resources on TRPA or other regulatory official maps or records?

- Yes No
 No, With Mitigation Data Insufficient

c. Is the property associated with any historically significant events and/or sites or persons?

- Yes No
 No, With Mitigation Data Insufficient

d. Does the proposal have the potential to cause a physical change, which would affect unique ethnic cultural values?

- Yes No
 No, With Mitigation Data Insufficient

e. Will the proposal restrict historic or pre-historic religious or sacred uses within the potential impact area?

- Yes No
 No, With Mitigation Data Insufficient

Explanation:

21. Findings of Significance

a. Does the project have the potential to degrade the quality of the environment, substantially reduce the habitat of a fish population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California or Nevada history or prehistory?

- Yes No
 No, With Mitigation Data Insufficient

b. Does the project have the potential to achieve short-term, to the disadvantage of long-term, environmental goals? (A short-term impact on the environment is one, which occurs, in a relatively brief, definitive period of time, while long-term impacts will endure well into the future.)

- Yes No
 No, With Mitigation Data Insufficient

c. Does the project have impacts which are individually limited, but cumulatively considerable? (A project may impact on two or more separate resources where the impact on each resource is relatively small, but where the effect of the total of those impacts on the environmental is significant?)

- Yes No
 No, With Mitigation Data Insufficient

d. Does the project have environmental impacts which will cause substantial adverse effects on human being, either directly or indirectly?

- Yes No
 No, With Mitigation Data Insufficient

On the basis of this evaluation

The proposed project could not have a significant effect on the environment and a finding of no significant effect shall be prepared in accordance with TRPA's Rules of Procedure.

Yes

No

The proposed project could have a significant effect on the environment, but due to the listed mitigation measures which have been added to the project, could have no significant effect on the environment and a mitigated finding of no significant effect shall be prepared in accordance with TRPA's Rules and Procedures.

Yes

No

The proposed project may have a significant effect on the environment and an environmental impact statement shall be prepared in accordance with this chapter and TRPA's Rules of Procedure

Yes

No

Date:

Signature of Evaluator

Title of Evaluator

Appendix D Glossary of Technical Terms

This appendix briefly explains the technical terms and names used in this IS. A list of acronyms appears directly before Chapter 1.

Best Management Practice (BMP)	Any program, technology, process, operating method, measure or device that controls, prevents, removes or reduces pollution.
Basin Plan	A specific plan for control of water quality within one of the nine hydrologic basins of the state under the regulation of a Water Quality Control Board.
Cumulative effects	Project effects that are related to other actions with individually insignificant but cumulatively significant impacts.
Decibel	A numerical expression of the relative loudness of a sound.
Encroachment (floodplain)	An action within the limits of the 100-year floodplain.
Endangered	Plant or animal species that are in danger of extinction throughout all or a significant portion of its range.
Erosion	The wearing away of the land surface by running water, wind, ice, or other geological agents.
Floodplain (100-year)	The area subject to flooding by a flood or tide that has a 1 percent chance of being exceeded in any given year.
Habitat	The place or type of site where a plant or animal naturally or normally lives and grows.
Initial Study (IS)	Environmental review document prepared to comply with CEQA
Initial Site Assessment (ISA)	A Caltrans term for an initial study to determine hazardous waste issues on a project.
L_{eq}	A unit used for evaluation of sound impacts, L_{eq} is the measurement of the fluctuating sound level received by a receptor averaged over a time interval (usually 1 hour).
Level of Service (LOS)	A measurement of capacity of a roadway.

Mitigation	Compensation for an impact by replacement or provision of substitute resources or environments. Mitigation can include avoiding an impact by not taking a certain action, minimizing impacts by limiting the degree of an action, or rectifying an impact by repairing or restoring the affected environment.
Negative Declaration (ND)	Issued upon approval of the environmental review process under CEQA
NPDES	National Pollutant Discharge Elimination System. A permit regulated by the Regional Water Quality Control Board that is required if more than 1 acre of original ground is graded. One condition of this permit is that the contractor must submit a Storm Water Pollution Prevention Plan (SWPPP), which is similar to the Water Pollution Control Plan required by Caltrans' Standard Specification 7-1.01G.
Practicable	An action that is capable of being done after taking into consideration cost, existing technology and logistics in light of overall project purposes.
Receptors	Term used in air quality and noise studies that refers to houses or businesses that could be affected by a project.
Regulatory agency	An agency that has jurisdiction by law.
Responsible agency	A public agency other than the Lead Agency that has responsibility for carrying out or approving a project under CEQA.
Right-of-way	A general term denoting land, property, or interest therein, usually in a strip, acquired for or devoted to transportation purposes.
Riparian	Pertaining to the banks and other adjacent terrestrial (as opposed to aquatic) environs of freshwater bodies, watercourses, estuaries, and surface-emergent aquifers, whose transported freshwater provides soil moisture sufficient in excess of that available through local precipitation to potentially support the growth of vegetation.
RTP	Regional Transportation Plan, prepared by the Metropolitan Transportation Commission (MTC), the regional agency responsible for transportation planning and funding.

Special-status species	Plant or animal species that are either (1) federally listed, proposed for or a candidate for listing as threatened or endangered; (2) bird species protected under the Federal Migratory Bird Treaty Act; (3) protected under state endangered species laws and regulations, plant protection laws and regulations, Fish and Game codes, or species of special concern listings and policies; (4) recognized by national, state, or local environmental organizations (e.g., California Native Plant Society).
STIP	The State Transportation Improvement Program, updated every 2 years, is the California Transportation Commission's priorities for improvements on and off the state highway system.
SWPPP	A Storm Water Pollution Prevention Plan is prepared to evaluate sources of discharges and activities that may affect storm water runoff, and implement measures or practices to reduce or prevent such discharges.
Threatened	A species that is likely to become endangered in the foreseeable future in the absence of special protection.
Waters of the United States	<p>As defined by the USACE in 33 Code of Federal Regulations 328.3(a):</p> <ol style="list-style-type: none">1. All waters that are currently used, or were used in the past, or may be susceptible to use in interstate or foreign commerce, including all waters that are subject to the ebb and flow of the tide;2. All interstate waters including interstate wetlands;3. All other waters such as intrastate lakes, rivers, streams (including intermittent streams), mudflats, sandflats, wetlands, sloughs, prairie potholes, wet meadows, playa lakes, or natural ponds, the use, degradation or destruction of which could affect interstate or foreign commerce, including any such waters:<ol style="list-style-type: none">(i) Which are or could be used by interstate or foreign travelers for recreational or other purposes; or(ii) From which fish or shellfish are or could be taken and sold in interstate or foreign commerce; or(iii) Which are used or could be used for industrial purposes

by industries in interstate commerce;

4. All impoundment of waters otherwise defined as waters of the United States under this definition;

5. Tributaries of waters identified in paragraphs 1-4;

6. The territorial seas;

7. Wetlands adjacent to waters (waters that are not wetlands themselves) identified in paragraphs 1-6.

Wetlands

When used in a formal context, such as in this IS, wetlands are areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances will support, a prevalence of vegetation typically adapted for life in saturated soil conditions. Wetlands generally include swamps, marshes, bogs, and similar areas [33 CFR 328.3(b)].

Appendix E Title VI Policy Statement

STATE OF CALIFORNIA—BUSINESS, TRANSPORTATION AND HOUSING AGENCY

ARNOLD SCHWARZENEGGER, Governor

DEPARTMENT OF TRANSPORTATION
OFFICE OF THE DIRECTOR
1120 N STREET
P. O. BOX 942873
SACRAMENTO, CA 94273-0001
PHONE (916) 654-5266
FAX (916) 654-6608
TTY (916) 653-4086



*Flex your power!
Be energy efficient!*

January 14, 2005

TITLE VI POLICY STATEMENT

The California Department of Transportation under Title VI of the Civil Rights Act of 1964 and related statutes, ensures that no person in the State of California shall, on the grounds of race, color, national origin, sex, disability, and age, be excluded from participation in, be denied the benefits of, or be otherwise subjected to discrimination under any program or activity it administers.

A handwritten signature in black ink that reads "Will Kempton".

WILL KEMPTON
Director

Appendix F U.S. Fish and Wildlife Service Species List

This appendix contains the U.S. Fish and Wildlife Service list of species that might occur within the regional area surrounding the project limits.

SACRAMENTO FISH & WILDLIFE OFFICE
Endangered and Threatened Species
that may be affected by Projects in the
Lake Tahoe Basin

Database Last Updated: August 16, 2007

Report Date: November 12, 2007

Species of Concern - The Sacramento Fish & Wildlife Office no longer maintains a list of species of concern. However, various other agencies and organizations maintain lists of at-risk species. These lists provide essential information for land management planning and conservation efforts. See www.fws.gov/sacramento/es/spp_concern.htm for more information and links to these sensitive species lists.

Listed Species

Fish

Hypomesus transpacificus - delta smelt (T)

Oncorhynchus (=Salmo) clarki henshawi - Lahontan cutthroat trout (T)

Oncorhynchus mykiss - Central Valley steelhead (T)

Oncorhynchus tshawytscha - Central Valley spring-run chinook salmon (T)

Oncorhynchus tshawytscha - winter-run chinook salmon, Sacramento River (E)

Amphibians

Rana aurora draytonii - California red-legged frog (T)

Candidate Species

Amphibians

Bufo canorus - Yosemite toad (C)

Rana muscosa - mountain yellow-legged frog (C)

Mammals

Martes pennanti - fisher (C)

Plants

Rorippa subumbellata - Tahoe yellow-cress (C)

Species with Critical Habitat Proposed or Designated in this Region

None

Key:

- (E) *Endangered* - Listed as being in danger of extinction.
- (T) *Threatened* - Listed as likely to become endangered within the foreseeable future.
- (P) *Proposed* - Officially proposed in the Federal Register for listing as endangered or threatened.
- (NMFS) Species under the Jurisdiction of the [National Oceanic & Atmospheric Administration Fisheries Service](http://www.fws.gov/sacramento/es/spp_lists/regionActionPage.cfm). Consult with them directly about these species.
- *Critical Habitat* - Area essential to the conservation of a species.
- (PX) *Proposed Critical Habitat* - The species is already listed. Critical habitat is being proposed for it.
- (C) *Candidate* - Candidate to become a proposed species.
- (V) Vacated by a court order. Not currently in effect. Being reviewed by the Service.

- (X) *Critical Habitat* designated for this species

Important Information About Your Species List

How We Make Species Lists

We store information about endangered and threatened species lists by U.S. Geological Survey [7½ minute quads](#). The United States is divided into these quads, which are about the size of San Francisco.

The animals on your species list are ones that occur within, **or may be affected by** projects within, the quads covered by the list.

- Fish and other aquatic species appear on your list if they are in the same watershed as your quad or if water use in your quad might affect them.
- Amphibians will be on the list for a quad or county if pesticides applied in that area may be carried to their habitat by air currents.
- Birds are shown regardless of whether they are resident or migratory. Relevant birds on the county list should be considered regardless of whether they appear on a quad list.

Plants on your list are ones that have actually been observed in the area covered by the list.

Surveying

Some of the species on your list may not be affected by your project. A trained biologist or botanist, familiar with the habitat requirements of the species on your list, should determine whether they or habitats suitable for them may be affected by your project. We recommend that your surveys include any proposed and candidate species on your list.

For plant surveys, we recommend using the [Guidelines for Conducting and Reporting Botanical Inventories](#). The results of your surveys should be published in any environmental documents prepared for your project.

Your Responsibilities Under the Endangered Species Act

All animals identified as listed above are fully protected under the Endangered Species Act of 1973, as amended. Section 9 of the Act and its implementing regulations prohibit the take of a federally listed wildlife species. Take is defined by the Act as "to harass, harm, pursue, hunt, shoot, wound, kill, trap, capture, or collect" any such animal.

Take may include significant habitat modification or degradation where it actually kills or injures wildlife by significantly impairing essential behavioral patterns, including breeding, feeding, or shelter (50 CFR §17.3).

Take incidental to an otherwise lawful activity may be authorized by one of two procedures:

- If a Federal agency is involved with the permitting, funding, or carrying out of a project that may result in take, then that agency must engage in a formal [consultation](#) with the Service.
- During formal consultation, the Federal agency, the applicant and the Service work together to avoid or minimize the impact on listed species and their habitat. Such consultation would result in a biological opinion by the Service addressing the anticipated effect of the project on listed and proposed species. The opinion may authorize a limited level of incidental take.
- If no Federal agency is involved with the project, and federally listed species may be taken as part of the project, then you, the applicant, should apply for an incidental take permit. The Service may issue such a permit if you submit a satisfactory conservation plan for the species that would be affected by your project.
- Should your survey determine that federally listed or proposed species occur in the area and are likely to be affected by the project, we recommend that you work with this office and the California Department of Fish and Game to develop a plan that minimizes the project's direct and indirect impacts to listed species

and compensates for project-related loss of habitat. You should include the plan in any environmental documents you file.

Critical Habitat

When a species is listed as endangered or threatened, areas of habitat considered essential to its conservation may be designated as critical habitat. These areas may require special management considerations or protection. They provide needed space for growth and normal behavior; food, water, air, light, other nutritional or physiological requirements; cover or shelter; and sites for breeding, reproduction, rearing of offspring, germination or seed dispersal.

Although critical habitat may be designated on private or State lands, activities on these lands are not restricted unless there is Federal involvement in the activities or direct harm to listed wildlife.

If any species has proposed or designated critical habitat within a quad, there will be a separate line for this on the species list. Boundary descriptions of the critical habitat may be found in the Federal Register. The information is also reprinted in the Code of Federal Regulations (50 CFR 17.95). See our [critical habitat page](#) for maps.

Candidate Species

We recommend that you address impacts to candidate species. We put plants and animals on our candidate list when we have enough scientific information to eventually propose them for listing as threatened or endangered. By considering these species early in your planning process you may be able to avoid the problems that could develop if one of these candidates was listed before the end of your project.

Wetlands

If your project will impact wetlands, riparian habitat, or other jurisdictional waters as defined by section 404 of the Clean Water Act and/or section 10 of the Rivers and Harbors Act, you will need to obtain a permit from the U. S. Army Corps of Engineers. Impacts to wetland habitats require site specific mitigation and monitoring. For questions regarding wetlands, please contact Mark Littlefield of this office at (916) 414-6580.

Updates

Our database is constantly updated as species are proposed, listed and delisted. If you address proposed and candidate species in your planning, this should not be a problem. However, we recommend that you get an updated list every 90 days. That would be February 10, 2008.

Appendix G Avoidance and/or Minimization Summary

This appendix summarizes the avoidance and/or minimization measures discussed in Chapter 2. More detail on these measures is included in the resource area discussions in that chapter.

Land Use

Avoidance and minimization measures for potential impacts related to temporary, periodic travel delays during construction are addressed in Section 2.4.4.

Community Impacts

CI-1 Public Outreach

To provide public and motorist information on the project activities, a public involvement plan will be prepared and implemented that provides for communication and outreach measures specific to this segment of US 50. Information will be provided to potentially affected individuals and institutions in the local area, such as business and property owners, school districts, local agencies, and the Lake Tahoe Airport. If appropriate, the plan will provide for public informational meetings, events, and specific stakeholder coordination to notify and coordinate with the public about construction activities that might affect the community.

CI-2 Public and Private Property Access

Access to properties, driveways, or roads along US 50 will be maintained during construction but may be limited or reduced. Notification to occupants (or responsible parties) will be made whenever a property would be directly affected by construction activities.

Utilities/Emergency Services

As emergency vehicles will be allowed passage through any construction zone, no additional avoidance, minimization, and/or mitigation measures are proposed for emergency services.

UE-1 Coordinate Final Design and Construction Activities with Utility Service Providers

Any need for utility relocation will be identified during final design of the project. If a need to relocate utilities is identified, Caltrans will coordinate these activities with the utility service providers.

Traffic and Transportation Facilities

TT-1 Traffic Management Plan (TMP)

A TMP will be developed for the US 50 Segment 2 final design phase. The TMP outlines construction requirements and restrictions to minimize traffic delays and maximize safety within the construction areas. It will include strategies for public and motorist information, incident management, construction, demand management, and alternate routes (if available or practical). For example, a construction season map will be published each year to inform the public, local businesses, and local agencies of planned construction locations and activities. Elements of the TMP for this segment would typically include the following.

- During the peak summer travel season between July 1 and Labor Day, no lane closures would be allowed after noon on Fridays, or on weekends or holidays during this period. Work planned outside the highway travel lanes that does not impede normal traffic flow would not be subject to this restriction.
- Lane closure charts will be developed for each area of work to address any planned temporary lane changes or closures. These charts and schedules will be made available for public notification and information.
- Lane closures will be limited to 0.6 mile in length or less.
- Maximum delays caused by a single closure will be limited to 10 minutes for construction projects and 15 minutes for maintenance work. The cumulative delay for a given corridor will be limited to 30 minutes.
- Bicycle and pedestrian access will be maintained through construction zones whenever possible and as appropriate.
- Construction schedules and anticipated locations of construction activities will be coordinated with the local school district with regard to school bus schedules and bus stops. Every effort will be made to allow continued school bus access around construction areas to avoid or minimize delays in the daily bus schedules. If necessary, Caltrans will work with the school district to identify any temporary periods when unavoidable delays may occur, to allow the school district to temporarily adjust bus schedules.

Visual Resources

VA-1 Measures for Specific Project Components

Measures to minimize impacts associated with the following project components are listed below.

- **Infiltration basins.**
 - Each basin will be designed specifically for its site. The basin shape will be designed to maximize infiltration and minimize tree removal. Where feasible, basins will be irregularly shaped around trees. However, if it is determined that it is not feasible to maintain the long-term health of a tree, then the tree will be removed as part of basin construction.
 - Infiltration basins will be designed without harsh angles and will integrate features into surroundings through the use of curvilinear forms and contour grading.
 - All disturbed areas associated with basin construction will be revegetated using seeding, container planting, pine needle mulch, and temporary irrigation where required.
 - Logs and boulders, as appropriate, will be integrated into the basin design.
 - Infiltration basins will avoid the use of concrete or rock slope protection lining.
- **Maintenance pullouts.**
 - Where possible, the infiltration basin access ramps will be routed to minimize ground disturbance and vegetation removal.
- **Sand traps and sand vaults.**
 - Sand traps will be installed in the least visible locations feasible.
 - Sand trap structures will be painted or powder coated with an approved Standard Federal Color (Brown #30045 or Green #34108). The specific color will be selected to match the color of any existing elements in the immediate area.
 - All disturbed areas associated with sand trap installation will be revegetated using seeding, container planting, and/or pine needle straw.
 - Visible portions of sand vaults should be designed so that the tops of the structures can be paved over, leaving only the maintenance access visible.
 - Visible portions of sand vaults will be painted or powder coated with an approved Standard Federal Color that matches the color of existing elements in the immediate area.
- **Rock slope protection (end treatment of culverts).**
 - The selected rocks will include indigenous sizes, shapes, materials, and colors wherever feasible. Edges will have irregular shapes.
 - Culvert end treatments will be treated with environmentally benign stains to induce a weathered appearance that blends elements into the existing landscape.
 - Where required, containerized native plantings will be used to strategically blend into the landscape, and/or screen, culvert end treatments from view.
- **Curbs and gutters.**

- Any new curbs and gutters will be colored an earth tone to help blend the curbs into the existing roadside.

VA-2 General Design and Construction Measures

- Temporary erosion control measures will be used in all disturbed areas during construction to minimize permanent impacts.
- Permanent erosion control measures will be used in all disturbed areas during construction. All disturbed areas will receive a permanent seed mix composed of native plant species indigenous to the area. In addition, if required, a follow-up revegetation project will install containerized plants to supplement seeding. All removed plantings will be replaced in kind. All native vegetation removed will be replaced in ratios determined by Caltrans Environmental and Landscape Architecture Offices.
- All small trees, tree limbs, shrubs and other woody debris generated during clearing and grubbing operations will chipped and stockpiled for future used as erosion control and in areas designated for revegetation.
- Compost will be incorporated where feasible.
- Any water quality improvement ditches required will be earthen- or rock-lined whenever possible.
- If required, fences used to limit access to basins or other highway features will be made of logs or wood rails to support visual continuity along the corridor.

VA-3 TRPA Scenic Values

Caltrans roadway and drainage improvements will consider TRPA scenic thresholds and incorporate design elements or improvements that do not degrade current values. Scenic values will be enhanced to the extent possible within the scope of the proposed work.

Cultural Resources

CR-1 Discovery of Archaeological Resources

No further archaeological work is necessary within the APE. Additional surveys would be required if the project changes to include areas not previously surveyed. The project does not warrant the completion of a formal discovery plan based on the absence of recorded, reported, or identified archaeological sites in and adjacent to resources during construction. If cultural materials are discovered during construction, all earth-moving activity within and around the immediate discovery area will be diverted until a qualified archaeologist can assess the nature and significance of the find. TRPA will also be contacted if any cultural materials are identified during construction.

CR-2 Discovery of Human Remains

If human remains are discovered, California Health and Safety Code Section 7050.5 states that further disturbances and activities shall cease in any area or nearby area suspected to overlie remains, and the County Coroner contacted. Pursuant to PRC Section 5097.98, if the remains are thought to be Native American, the coroner will notify the NAHC, which will then notify the Most Likely Descendent. At this time, the person who discovered the remains will contact Jody Brown, Caltrans Environmental Branch Chief, so that Caltrans may work with the Most Likely Descendent on the respectful treatment and disposition of the remains. Further provisions of PRC Section 5097.98 are to be followed as applicable.

Water Quality and Storm Water Runoff

WS-1 Construction Measures

Soil erosion protection measures are recommended at sites with cross-culverts that are proposed for replacement or widening. Geotextile fabrics and erosion control blankets/mats are suggested BMPs that can be installed. In addition, a line of stacked sandbag/gravel bag berms can be placed along the channel banks to intercept and slow the flow of sediment-laden sheet flow runoff on road surfaces.

In addition, the following measures would be applied:

- TRPA and LRWQCB regulations limit grading to 3 cubic yards from October 15 to May 1 of each year. Unless a variance is obtained, construction activities will conform to this requirement.
- Pollution prevention measures will be implemented to protect surface water quality degradation to the existing surface water resources within the US 50 project limits, and to prevent erosion of bare soils and potential non-point source pollutant contribution.

Other construction BMPs may be considered where proposed modifications or grading of slopes may increase runoff and expose soils. Diversion of runoff may be considered during construction where it is necessary to direct storm water flow around a construction site. Temporary dewatering of a construction site may be necessary to remove accumulated storm water runoff.

WS-2 Groundwater Measures

The project is not anticipated to encounter groundwater, as excavation work should be minimal. However, if construction encounters groundwater or may involve non-storm water discharges, consultation with the LRWQCB or California Department of Toxic

Substances Control may be appropriate. A project-specific Waste Discharge Permit may be required if substantial dewatering will take place.

Soils, Soil Conservation, and Geology

SC-1 Purchase of Land Coverage Credits

Land coverage credits would be purchased to offset the increased pavement area that would result from the proposed construction of maintenance pullouts. According to TRPA Code Section 20.3C(3), land transfers to provide coverage for low-capability lands, LCDs 1-3, must be permanently retired as set forth in TRPA Code Section 20.3C(7). Caltrans is not on the TRPA individual parcel system and is creating coverage within state right-of-way or within land on which highway agreements exist. Any land transfer would be performed under the guidance of the California Tahoe Conservancy, a State of California land bank administration agency. Caltrans has existing coverage credits at the Conservancy's land bank via a Memorandum of Understanding dated October 18, 2000.

SC-2 Geotechnical Investigations

Proposed structures could require geotechnical investigation if they are located on potentially unstable soils and could present landslide, rockfall, liquefaction, or erosion hazards. The results of such investigations would be used in the design of individual project elements to ensure that there would be no adverse effects.

Hazardous Waste and Materials

HZ-1 Lead-Contaminated Soils

Because ADL was found to exist at non-hazardous levels, a modified version of Caltrans Non Standard Special Provisions (N-SSP # 07-330) will be included for this project. The N-SSP addresses the need for a lead compliance plan and other factors. This process would be performed during the Plans, Specifications and Estimates stage.

HZ-2 Subsurface Soil Contamination

If any soil disturbance activities are planned during construction adjacent to the sites identified above as having potential contamination, a site investigation may be required to determine if any contamination is present.

HZ-3 Disposal of Removed Materials

Any removal of yellow thermoplastic lane striping must be performed in accordance with a Lead Compliance Plan and disposed of at a Class I disposal facility.

Air Quality

AQ-1 Control Dust from Construction Activities

Typical dust control practices that may be required to reduce the amount of dust from construction emissions may include, but are not limited to, the following measures:

- Covering open-bodied trucks when used for transporting materials likely to give rise to airborne dust
- Watering disturbed (graded or excavated) surfaces as necessary, increasing frequency when weather conditions require
- Watering disturbed areas to form a compact surface after grading and earth working; using chemical dust suppressants when watering is not sufficient
- Limiting areas to be cleared to facilities required for the project and necessary equipment and materials stockpile areas
- Limiting the speed of construction equipment and vehicles on unpaved roads when conditions require
- Erosion control planting of exposed slopes after construction; and incorporating standard erosion control measures as part of the contract.

The dust control activities will comply with Section 10 of the Caltrans Standard Construction Specifications (Caltrans 2006a) and will be reviewed and approved of by TRPA.

AQ-2 Reduce Emissions from Construction Equipment

The following measures can reduce pollutant emissions in construction equipment exhaust:

- Keeping engines properly tuned
- Limiting engine idling
- Avoiding unnecessary concurrent usage of equipment.

Noise

NO-1 Standard Noise Control Measures

Noise control will conform to the provisions of Section 7-1.01I, "Sound Control Requirements," of the Caltrans Standard Specifications. Section 7-1.01I requires the Contractor to comply with all local sound control and noise level rules, regulations, and ordinances that apply to any work performed pursuant to the project. The following standard construction noise control measures would be implemented to control construction noise.

- Noise-generating activities will be restricted at the construction site or in areas adjacent to the construction site associated with the project to the hours of 8:00 a.m. to 6:30 p.m.
- Contractors will equip internal combustion engine-driven equipment with intake and exhaust mufflers that are in good condition and appropriate for the equipment.
- Contractors will limit or prohibit idling of internal combustion engines on equipment or vehicles that are not actively involved in construction activities.
- Staging of construction equipment will be avoided within 200 feet of residences and stationary noise-generating construction equipment, such as air compressors and portable power generators, will be located as far as practical from existing noise sensitive receptors.
- If necessary to avoid severe temporary noise impacts, temporary barriers may be used to screen stationary noise generating equipment when located immediately adjacent to noise sensitive land uses. The need for this measure would be determined by the resident engineer.
- A noise disturbance coordinator will be designated who would be responsible for responding to any local complaints about construction noise. The disturbance coordinator would determine the cause of the noise complaint (e.g., starting too early, bad muffler, etc.) and would require that reasonable measures warranted to correct the problem be implemented. A telephone number for the disturbance coordinator will be posted at a conspicuous location at the construction site and included in the notice sent to neighbors regarding the construction schedule.

Wetlands and Other Waters of the United States

WE-1 On-Site Mitigation

Remaining impacts to wetlands, other jurisdictional waters of the U.S., and SEZs will be mitigated on-site if possible. Detailed wetland mitigation plans will be developed in consultation with the USACE.

WE-2 General Avoidance/Minimization Measures and BMPs

To ensure maximum avoidance, the measures listed below and included in their entirety in Section 2.20 will be followed.

- GE-01: Establishment of Environmentally Sensitive Areas (ESAs)
- GE-02: Construction Clean-up

- GE-03: Construction Scheduling (Project activities in jurisdictional wet areas will occur in the dry season, which is typically between July 15 and October 15 but depends on seasonal conditions)
- WQ-01: Avoidance of Aquatic Resources
- WQ-02: Timing of Aquatic Resource Activities
- WQ-03: Minimizing Disturbance of Aquatic Resources
- WQ-04: Erosion Control
- WQ-05: Prohibition of Construction Materials Entering Aquatic Resources
- WQ-06: On-Site Restoration
- HA-01: Avoidance of Habitat Disturbance
- HA-02: Revegetation of Disturbed Areas
- HA-06: Preservation of Existing Top Soil Layer
- WL-01: Ensure Fish Passage
- WL-02: Limit Vegetation Removal

Special-Status Animal Species

The following measures will be taken prior to and during construction to avoid or minimize direct and permanent effects to special-status wildlife and indirect effects to areas adjacent to the study area. Preconstruction surveys will be performed in the ESL where habitat for sensitive species exists to verify species presence/absence and assess the need for additional avoidance and minimization measures. If species are determined to be present, seasonal construction restrictions will be required to avoid breeding seasons and other periods when wildlife species are vulnerable. Construction contract specifications will include use of ESAs, shown on the maps in Appendix A, construction clean-up, weed control, restrictions on in-stream work, erosion control, and restoration of disturbed SEZs. Measures for specific species identified in Section 2.17.2 are summarized below.

AN-1 Preconstruction Surveys for Avian Species

No nesting of special-status birds was observed during the field surveys. However, potential habitat was identified, and TRPA has recorded habitat or occurrences for some species within or near the project study area. To ensure that species of concern are not using the study area at the time construction proceeds, preconstruction surveys will be performed within the ESL to verify absence. In addition, the preconstruction surveys will include a review of TRPA and Forest Service annual survey data to identify any new occurrences. The following potential buffer areas may be imposed on construction activities to minimize impacts if species are found to be present.

- Northern goshawk: If nesting northern goshawks are identified, construction will be prohibited within a 0.5-mile range of the nest during the breeding season (February 15 to September 15 or until fledging occurs).
- Blue grouse, yellow warbler, waterfowl: If nests are identified, construction activities will be prohibited within 150 feet of the nest during the nesting season (March 1 to August 31). Vegetation removal will be prohibited during the nesting season to minimize the effect to warblers and other migratory birds that have not yet started nesting. Vegetation that is removed outside of the nesting season will be restored to its preconstruction condition.
- California spotted owl: If nests are identified, construction will be prohibited within 0.25 mile of the nest sites during the nesting season (between March 1 and August 31).
- Peregrine falcon: If nests are found, construction will be prohibited within 0.25 mile of the nest during the nesting season (February 1 to August 15).

AN-2 General Measures and BMPs for Avian Species

The following general avoidance/minimization measures and BMPs are detailed in Section 2.20:

- HA-01: Avoidance of Habitat Disturbance
- HA-02: Revegetation of Disturbed Areas
- WL-02: Limit Vegetation Removal
- WL-03: Migratory Bird Preconstruction Surveys
- WL-04: Raptor and Owl Surveys

AN-3 General Measures and BMPs for Mammals

The following general avoidance/minimization measures and BMPs are detailed in Section 2.20:

- WQ-01: Avoidance of Aquatic Resources
- WQ-03: Minimizing Disturbance of Aquatic Resources
- HA-01: Avoidance of Habitat Disturbance
- HA-02: Revegetation of Disturbed Areas
- WL-02: Limit Vegetation Removal
- WL-05: Roosting, Denning, or Burrowing Mammal Surveys

AN-4 Preconstruction Survey for Sierra Nevada Snowshoe Hare

Project construction activities have the potential to impact forested and riparian areas that may provide cover for Sierra Nevada snowshoe hare. Preconstruction surveys will be conducted for Sierra Nevada snowshoe hare within the ESL in riparian areas where nest depressions may be located. Where Sierra Nevada snowshoe hare nest depressions are identified, construction within 250 feet of these areas will be prohibited between February 1 and July 1, and construction will be limited to daylight hours.

Threatened and Endangered Species

TE-1 Measures for Sierra Nevada Red Fox

As the project vicinity contains potential habitat for Sierra Nevada red fox, preconstruction surveys for dens will be conducted within the ESL. Construction will be prohibited within 250 feet of an identified active den during the breeding season (February 1 to May 31). Open trenches or other construction features that pose a risk of trapping animals will have escape ramps installed or will be covered at the end of each construction day.

In addition to the above specific measures the following general avoidance and minimization efforts (described in detail in Section 2.20) are applicable for the Sierra Nevada red fox:

- HA-01: Avoidance of Habitat Disturbance
- HA-02: Revegetation of Disturbed Areas
- WL-02: Limit Vegetation Removal
- WL-05: Roosting, Denning, or Burrowing Mammal Surveys (as described above)

Invasive Species

The following measures, which are described in Section 2.20, will be implemented to avoid the potential introduction of noxious weed material to the project site:

- HA-03: Construction Equipment Weed Control
- HA-05: Weed-Free Erosion Control Seed Mix/Stock