



# Station Four



# 2-Lane North Alternative



### LEGEND

- █ Emergency Walkway
- █ Ramp
- █ Tunnel
- █ Shoulder
- █ Highway
- █ Soundwall

# 3-Lane North Alternative



**LEGEND**

- Emergency Walkway
- Ramp
- Tunnel
- Shoulder
- Highway
- Soundwall

# TUNNEL DESIGN



Horizontal boreholes being drilled in March 2005 near the proposed Oakland Portal




Rock core samples are removed from the drill rigs, reviewed, photographed, and logged. Lab testing yields rock strength and other data needed to design the tunnel support and linings




Historic construction photos and documents of the first 3 Caldecott tunnel bores yields valuable information about the ground conditions that can be expected in the new tunnel

Step 1 – Historical Review and Geotechnical Investigation: Rock and soil samples are taken from proposed alignment – Surface geological formations, faults, and groundwater conditions are reviewed and analyzed




3D CAD model above shows view at Orinda and of tunnel with existing third bore on left and proposed 4th bore on the right


Step 2 – Tunnel Alignment and Interaction: Proposed alignment is refined while potential impact on existing 3rd bore must be considered




Finite element computer modeling is used to determine allowable clearance between the new tunnel and the existing tunnel on ground conditions determined from geologic and historic investigation



Final Step – Engineers and geologists map and interpret actual ground conditions encountered during tunnel construction to ensure appropriate ground support types are placed to meet design requirements



Step 4 – Final Tunnel Lining and Finishes: Waterproofing, final concrete lining, lighting, architectural finishes and safety systems are designed to meet long-term design life of new tunnel



Step 3 – Initial Tunnel Lining and Excavation Design: Full tunnel will be mined in stages (drifts) from top to bottom so smaller areas can be more easily supported with sprayed-on concrete (Shotcrete)

# TUNNEL CONSTRUCTION EQUIPMENT



**DRILL JUMBO:** Large drill jumbos may be used to drill in holes in precise patterns at the face of the excavation. These holes are used for setting small blasting rounds to loosen and excavate very hard rock encountered in the tunnel



**DUMP/HAUL TRUCKS:** 10-20 Cubic Yard rubber tire dump trucks are used for tunnel muck transport



**ROADHEADER:** This equipment will be the primary excavating equipment used in the tunnel to excavate softer rock. It uses a rotating cutter head that grinds the rock away in a controlled manner and conveys the muck to dump trucks behind it for hauling




**ROLLING STEEL FORMS:** Prefabricated steel forms made to the exact final dimensions of the tunnel allow efficient placement of the final concrete lining along the excavated tunnel

# TUNNEL CONSTRUCTION SEQUENCE



Step 1 – Staging Area Preparation: Construction Equipment, trailers, and materials are gathered at each portal and softer earth and rock materials are removed to allow beginning of mined tunneling



BELOW: A mechanical "Roadheader" will be used to cut through most of the rock




Step 2 – Tunnel Excavation: Tunnel is excavated in stages from both the Oakland and Orinda Portals and muck is removed off-site via rubber tire haul trucks



ABOVE: Sprayed-on concrete (Shotcrete) is applied over steel supports to the top of the tunnel to provide temporary support during construction





Step 3 – Tunnel Concrete Lining: Final Concrete Lining is cast-in-place with steel reinforcement to form the final structural surface of the tunnel



Final Step – Tunnel Opens! Final system, quality, and safety checks are performed prior to opening tunnel to traffic





Step 4 – Tunnel Utilities: Lighting, ventilation and other tunnel utilities are installed in tunnel and cross-passages. Final roadway surface is placed



ABOVE: Emergency cross-passengers will be installed every 400 feet to allow safe exit to the 3rd bore in case of emergency

# GEOLOGIC/GEOTECHNICAL STUDIES

## TUNNEL GEOLOGY




### EXPLANATION


#### GEOLOGIC UNITS

Quaternary	
<b>Qls</b>	Landslide
<b>Tm</b>	MORAGA FORMATION: (Volcanic Rocks)
<b>Tor</b>	ORINDA FORMATION: Interbedded Sandstone, Siltstone, Mudstone and Conglomerate (Undifferentiated)
CLAREMONT FORMATION	
<b>Tc</b>	Chert and Shale
<b>Tce</b>	Sandstone
<b>Tcp</b>	Shale and Chert
SOBRANTE FORMATION	
<b>Tss</b>	Sandstone and Shale
<b>Tsp</b>	Sandstone
<b>Tsf</b>	Shale

# CONSTRUCTION STAGING



# CONSTRUCTION STAGING



- **Noise:** provide enclosures for compressors; construct a temporary soundwall; construct noise barriers as first items of work; keep community informed in advance of noisy activities; specify limits on equipment noise; schedule the majority of material deliveries and transport of excavated material to daytime hours, when possible
- **Monitoring:** perform preconstruction surveys of select residences, and if blasting is required, monitor select homes for vibration
- **Dust and Dirt:** apply water or dust palliatives; wet down stockpiles, provide wheel washes and street-sweeping services; seal aggregate and cement silos; follow “Best Management Practices”
- **Community Relations:** provide on-going community coordination and implement construction inquiry response protocol