

Public Information Notice I-238 Widening Project Update

Work Planned for the Month of January 2007

The following is an update of I-238 field work planned for the January 2007:

Freeway Construction	Location	Day/Night Work	Activity
I-880 Northbound and Southbound	Washington to A Street	Daily 7 am-3:30 pm	Clearing, temporary & permanent electrical modifications Storm drain improvements Retaining wall construction
	NB I-880 at Hesperian Widening	Day work	Excavation for abutments and bent footings, pile driving for all foundations, concrete forming and placement.
	NB I-880 at Lewelling Widening	Day work	Excavation for Retaining wall #4, drive piles for retaining wall #4, restripe on-ramp DN2
I-238 Mainline	I-880 – I-580	Day work	Clearing
	NB I-238 to SB I-880 Connector	Day and Night work	Underground removals and electrical demolition and construction, and drainage installation, install crash cushions
	NB I-880 to SB I-238 Connector	Day work	Subgrade & drainage construction, roadway grinding
	Hesperian on ramp to Southbound I-238	Day work	On-ramp DE1 striping, Abutment excavations, wick drain installations, drainage and sewer installation, temp and permanent wall construction
	Kent Avenue Undercrossing	Day work	Guard railing removal, foundation drilling and rebar work
	Ashland Avenue	Day work	Clearing, Wall excavation, foundation drilling and rebar work
	Route 185 On/Off ramp	Day and night work	Install k-rail, grind roadway, temporary lighting, demolish soundwall, construct ramp detour
I-238 /Route 185	Mission Boulevard Separation	Day work Dec 21-Jan 19	Abutment excavations, pile driving, concrete forming & placement
I-238/I-580 Interchange	Castro Valley Undercrossing (and City Street)	Day and night work	Demolish edge of deck and overhang, footing excavation, pile drilling & footing and column forming, install rebar & new drainage
	Strobridge Avenue	Day and night work	Excavate footing for new walls, drill new foundations, form footings, pour wall, demo overhang, form and pour columns & abutments

Note that some night work will be noisy if it includes concrete demolition.