



DRAFT NOVEMBER 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 NORTH REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

Estimated Quantities of Major Construction Items (in English units unless otherwise noted)																						
#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel (LB)	Unique Construction Items	Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Call out # in K (EE that excludes contingencies, state furnished materials & supp work)	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement (Month-Year)	Anticipated Bid Opening Date
15	4A170	SON	128	0.0/3.3	Rehabilitate culverts	Near Cloverdale at Various Locations from the Mendocino County line to 0.4 mi west of north junction with rte 101.	Replace Drainage	96	Misc Concrete 50	26	None	None	None	90	None	None	None	DFG 1602	\$350	60	Nov-09	Dec-09
16	0T145	SOL	37	7.2/10.5	PERFORM HIGHWAY PLANTING AND LANDSCAPING	IN VALLEJO ON RTE 37 FROM THE NAPA RIVER BRIDGE TO DIABLO ST (KP R12.9/R16.9)	Tree, shrubs, groundcover, chainlink gates, irrigation	None	None	None	None	None	None	None	None	None	Planting, irrigation and rock blanket	None	\$1,350	180 WD 750 PED	Nov-09	Dec-09
17	1E470	NAP, SOL, SON	Var	Var	TREAT BRIDGE DECKS WITH METHACRYLATE AND REPLACE JOINT	IN NAPA, SOLANO AND SONOMA COUNTIES AT VARIOUS LOCATIONS	Bridge Decks	25	None	None	None	None	None	None	None	None	None	None	\$740	80	Jan-10	Mar-10
18	0E980	MRN, SON	Var	Var	Replace joint seals and apply deck methacrylate	Various	Bridge Decks	None	None	None	None	None	None	None	None	None	None	None	\$540	110	Jan-10	Mar-10
19	1E730	SON	1	50.6/58.4	BWC Overlay	From Sea walk Dr to Gualala river bridge	BWC overlay	BWC= 5,300 tons	None	None	130	None	None	None	None	None	None	None	\$1,300	50	Feb-10	Apr-10
20	1E6001	MRN	1		BWC Overlay	Near Tomales & Point Reys stations from 2.2 miles north of Point Reys to 0.6 mile north of Tomales Petaluma road.	HMA & BWC overlay	HMA= 1000 tons, BWC= 10,000 tons	None	None	5,000	None	None	None	None	None	None	None	\$2,400	70	Feb-10	Apr-10
21	3A820	MRN	1	0.1	RE-GRADING PAVEMENT AT ACCESSIBLE	MARIN COUNTY	Concrete Sidewalk, Curb ramp	130	75	None	None	90	None	70	None	None	BOLLARD, SITE FURNISHINGS	None	\$319	40 WD 250 PED	Feb-10	Mar-10
22	2S941	SON	128	5.4	Highway Planting Restoration	IN SONOMA COUNTY NEAR GEYSERVILLE AT THE RUSSIAN RIVER BRIDGE	Highway Planting	None	None	None	None	None	None	None	None	None	None	401 (issued 6/16/09) 404 (issued 3/27/09) 1602 (issued 3/26/09)	\$865	864	Feb-10	Mar-10
23	4C350	NAP	128	2.6/4.6	AC Resurfacing	FROM TUBBS LANE TO JUNCTION STATE 29	HMA overlay	HMA=4500	None	None	None	None	None	None	None	None	None	None	\$860	45	Mar-10	Apr-10
24	2A630	SON	1	16.1/19.7	Pave roadway, pave roadside ditches	FROM 0.8 MILE NORTH OF SCOTTY CREEK BRIDGE TO RUSSIAN RIVER BRIDGE	HMA overlay	HMA=2,300	None	None	None	None	None	None	None	None	None	None	\$930	45	Mar-10	Apr-10
25	4A230	SON	37	0.9/2.6	Rehabilitate culverts	IN SONOMA COUNTY ON STATE HIGHWAY 37 FROM PM 0.9 TO PM 2.6	Replace Drainage	40	70	None	None	None	None	None	None	None	PP 600' minor Concrete 210 CY	None	\$400	45	Mar-10	Apr-10

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.



DRAFT NOVEMBER 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 NORTH REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

Estimated Quantities of Major Construction Items (in English units unless otherwise noted)																						
#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel (LB)	Unique Construction Items	Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Call out # in K (EE that excludes contingencies, state furnished materials & supp work)	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement (Month-Year)	Anticipated Bid Opening Date
26	4A881	SON	128	21.7	Environmental Mitigation	in Sonoma County	Mitigation Project	called 9/29	None	None	None	None	None	None	None	None	None	TBD	\$460	50 WD 750 PED	Mar-10	Apr-10
27	4S000	MRN	101	8.8	INSTALL ROCK SLOPE PROTECTION	AT SIR FRANCIS DRAKE BOULEVARD	RSP	None	11	None	None	None	None	None	180	None	4" Plastic Pipe and 4" Perforated Plastic Pipe	None	\$210	20	Apr-10	May-10
28	3S920	MRN	101	3.0	INSTALL ROCK SLOPE PROTECTION (RSP)	IN SAUSALITO, NORTH OF RODEO DRIVE	RSP	None	None	None	None	None	None	None	None	None	4" Plastic Pipe and 4" Perforated Plastic Pipe	None	\$140	20	May-10	Jun-10

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.



DRAFT NOVEMBER 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 EAST REGION

All information presented here is an estimate; it is preliminary and subject to change.*

Estimated Quantities of Major Construction Items (in English units unless otherwise noted)																							
#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel [LB]	Unique Construction Items	Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Call out # in K (EE that excludes contingencies, state furnished materials & supp work)	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement (Month-Year)	Anticipated Bid Opening Date	
1	0060C	CC	680	38.1/41.0, 0.0/1.6	Replacement Planting	In Solano and Contra Costa Counties in Benicia at the 680/780 Separation and in Martinez	Planting, Irrigation and Plant Establishment	None	None	None	None	None	None	None	None	None	None	None	None	\$1,500	200 WD 750 PEP	Oct-09	Nov-09
2	29492	ALA	24	KP 5.3/8.8	Re-align Westbound Route 24 to Northbound Route 13 Connector	In Oakland at Various Locations from Claremont Avenue Undercrossing to 0.2 KM North of Route 13/24 Separation	Ramp Realignment, and Bridge Barrier Rail Fencing	HMA (Type A) = 120 TONN	Concrete Pavement = 1040 M3, Rapid Set Concrete Pavement = 610 M3	None	None	Roadway Excavation = 7750 M3, Roadway Excavation (Type Z-2)(ADL and Naturally Occurring Metals) = 550 M3	None	Lean Concrete Base = 560 M3, Lean Concrete Base (Rapid Setting) = 390 M3, Class 3 Aggregate Base = 52 M3	None	None	None	NPDES Permit	\$3,840	100	Oct-09	Nov-09	
3	29493	ALA	24	KP R8.8	Widen Caldecott Lane & Install Traffic Signal at Kay/Broadway	At Kay Overcrossing	Right hand Turn Lane and Traffic Signal	HMA (Type A) = 110 TONN	None	None	None	Roadway Excavation = 160 M3, Roadway Excavation (Type Y-2)(ADL and Naturally Occurring Metal) = 100 M3	None	Class 3 Aggregate Base = 34 M3, Class 4 aggregate Subbase = 53 M3	None	None	None	NPDES Permit	\$368	95	Oct-09	Nov-09	
4	22859	CC	4	37.9/41.3	SR-4 East Widening from Loveridge to Somersville	in Pittsburg and Antioch	Interchange modification, Freeway Widening, Retaining wall, TOS, Ramp metering, Median Barrier	HMA =91,000 TONN HMA (Base Surfacing) = 840 TONN	31,800 m3	15,583 m3	15,000 m3	Roadway Excavation = 133,000 M3	23,119 m3	Class 3 Aggregate Base = 13,600 M3, Class 4 Aggregate Subbase = 13,420 M3	2,060,272 Kg	None	Railroad Facility, Bridge, E-Bart	404, 401, 1602	\$90,000	750 WD 810 PED	Oct-09	Dec-09	
5	1513C	ALA	580 880	17.7/19.8 3.3/30.9	Install Closed-Circuit TV Cameras	at Various Locations	CCTV Came	None	None	None	None	None	None	None	None	None	Electrical LS	None	2,010	180	Nov-09	Dec-09	
6	25376	ALA	680	4.8/5.2	Environmental Mitigation	in Fremont at Various Locations from 0.5 Mi to 0.3 Mi So of Washington	Earthwork, Drainage, Landscape	None	None	84	360	17,000	None	None	9,430	None	None	4,041,602,401	1,600	130 WD; 880PED	Dec-09	Apr-10	
7	1A521	CC/SAC	160	PM 0.8/1.3-0.0/1.3	Bridge Seismic Retrofit	At and Near Antioch at Antioch Bridge	Bridge Retrofit: Reinf Concrete, Isolation Bearings	HMA (Type A) = 12 TON	None	None	21,000	None	None	Class 3 Aggregate Base = 600 CY	280,000	3,720,000	Isolation Bearings	NPDES Permit; CA Dept of Fish & Game; US Army Corps of Engineers; CRWQCB	\$90,000	560 WD 60 PED	Dec-09	Apr-10	
8	1E430	ALA	13,80,84,238,262,580,680,880,980	various locations	Methacrylate deck, spall repair, and joint seals	at Various Locations	Bridge deck methacrylate	None	None	None	None	None	None	None	None	None	None	None	300	75	Feb-10	Apr-10	
9	1A241	ALA	980/24	1.3/2.0	Paving planting strip on median (eastbound)	in Oakland at Various Locations (Eastbound Only)	HMA & BWC overlay	HMA= 1100 tons, BWC= 3900 tons	None	None	None	None	None	None	None	None	None	None	None	1,310	50	Mar-10	Apr-10
10	44790	ALA	238	0.0/3.3, 3.5/7.8	ROADWAY REHABILITATION	in Hayward, Union City, & Fremont - from No of Rte 238/680 Separation to Junction Rte 92	HMA & BWC overlay	HMA = 5,310 RHMA = 55,400 Asphalt-Rubber Seal Coat=1,060 Replace AC Surfacing=8,150 CY	130	NA	NA	3,020	NA	890	None	None	Sidewalk, curb & gutter Drainage work Electrical work	None	\$16,800	410 (Bid type: Cost + Time)	Mar-10	May-10	
11	0G490	CC	4	31.1	AC resurfacing-route 4 at route160	in Antioch at Route 4/160 Separation	HMA overlay	HMA=270	None	20	50	None	None	None	None	None	None	None	\$340	40	Mar-10	Jun-10	
12	0E990	ALA	238	Various Locations between pm 14.4/16.3	Replace joint seals and apply deck methacrylate	at Various Locations	Bridge deck methacrylate	None	None	8	None	None	None	None	None	None	None	None	\$652	96	Mar-10	Apr-10	
13	1E460	CC	004, 24 80, 60	R10.3/R13.5	Meth deck and joint seals	at Various Locations (29 Bridges)	Bridge deck methacrylate	None	None	None	None	None	None	None	None	None	None	None	\$730	160	Mar-10	May-10	
14	0G150	CC	4	R17.0/R17.8	Drainage system restoration	Near the City of Concord east of Willow Pass Road Undercrossing	27" APC	HMA=1070 tons	None	None	None	None	None	None	None	None	Drainage work	None	\$900	60	Jan-10	Feb-10	

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.



DRAFT NOVEMBER 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 NORTH REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

Estimated Quantities of Major Construction Items (in English units unless otherwise noted)																							
#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel (LB)	Unique Construction Items	Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Call out # in K (EE that excludes contingencies, state furnished materials & supp work)	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement (Month-Year)	Anticipated Bid Opening Date	
15	4A170	SON	128	0.0/3.3	Rehabilitate culverts	Near Cloverdale at Various Locations from the Mendocino County line to 0.4 mi west of north junction with rte 101.	Replace Drainage	96	Misc Concrete 50	26	None	None	None	90	None	None	None	DFG 1602	\$350	60	Nov-09	Dec-09	
16	0T145	SOL	37	7.2/10.5	PERFORM HIGHWAY PLANTING AND LANDSCAPING	IN VALLEJO ON RTE 37 FROM THE NAPA RIVER BRIDGE TO DIABLO ST (KP R12.9/R16.9)	Tree, shrubs, groundcover, chainlink gates, irrigation	None	None	None	None	None	None	None	None	None	None	Planting, irrigation and rock blanket	None	\$1,350	180 WD 750 PED	Nov-09	Dec-09
17	1E470	NAP, SOL, SON	Var	Var	TREAT BRIDGE DECKS WITH METHACRYLATE AND REPLACE JOINT	IN NAPA, SOLANO AND SONOMA COUNTIES AT VARIOUS LOCATIONS	Bridge Decks	25	None	None	None	None	None	None	None	None	None	None	\$740	80	Jan-10	Mar-10	
18	0E980	MRN, SON	Var	Var	Replace joint seals and apply deck methacrylate	Various	Bridge Decks	None	None	None	None	None	None	None	None	None	None	None	\$540	110	Jan-10	Mar-10	
19	1E730	SON	1	50.6/58.4	BWC Overlay	From Sea walk Dr to Gualala river bridge	BWC overlay	BWC= 5,300 tons	None	None	130	None	None	None	None	None	None	None	None	\$1,300	50	Feb-10	Apr-10
20	1E6001	MRN	1		BWC Overlay	Near Tomales & Point Reys stations from 2.2 miles north of Point Reys to 0.6 mile north of Tomales Petaluma road.	HMA & BWC overlay	HMA= 1000 tons, BWC= 10,000 tons	None	None	5,000	None	None	None	None	None	None	None	\$2,400	70	Feb-10	Apr-10	
21	3A820	MRN	1	0.1	RE-GRADING PAVEMENT AT ACCESSIBLE	MARIN COUNTY	Concrete Sidewalk, Curb ramp	130	75	None	None	90	None	70	None	None	BOLLARD, SITE FURNISHINGS	None	\$319	40 WD 250 PED	Feb-10	Mar-10	
22	2S941	SON	128	5.4	Highway Planting Restoration	IN SONOMA COUNTY NEAR GEYSERVILLE AT THE RUSSIAN RIVER BRIDGE	Highway Planting	None	None	None	None	None	None	None	None	None	None	401 (issued 6/16/09) 404 (issued 3/27/09) 1602 (issued 3/26/09)	\$865	864	Feb-10	Mar-10	
23	4C350	NAP	128	2.6/4.6	AC Resurfacing	FROM TUBBS LANE TO JUNCTION STATE 29	HMA overlay	HMA=4500	None	None	None	None	None	None	None	None	None	None	\$860	45	Mar-10	Apr-10	
24	2A630	SON	1	16.1/19.7	Pave roadway, pave roadside ditches	FROM 0.8 MILE NORTH OF SCOTTY CREEK BRIDGE TO RUSSIAN RIVER BRIDGE	HMA overlay	HMA=2,300	None	None	None	None	None	None	None	None	None	None	\$930	45	Mar-10	Apr-10	
25	4A230	SON	37	0.9/2.6	Rehabilitate culverts	IN SONOMA COUNTY ON STATE HIGHWAY 37 FROM PM 0.9 TO PM 2.6	Replace Drainage	40	70	None	None	None	None	None	None	None	PP 600' minor Concrete 210 CY	None	\$400	45	Mar-10	Apr-10	

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.



DRAFT NOVEMBER 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 NORTH REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

Estimated Quantities of Major Construction Items (in English units unless otherwise noted)																						
#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel (LB)	Unique Construction Items	Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Call out # in K (EE that excludes contingencies, state furnished materials & supp work)	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement (Month-Year)	Anticipated Bid Opening Date
26	4A881	SON	128	21.7	Environmental Mitigation	in Sonoma County	Mitigation Project	called 9/29	None	None	None	None	None	None	None	None	None	TBD	\$460	50 WD 750 PED	Mar-10	Apr-10
27	4S000	MRN	101	8.8	INSTALL ROCK SLOPE PROTECTION	AT SIR FRANCIS DRAKE BOULEVARD	RSP	None	11	None	None	None	None	None	180	None	4" Plastic Pipe and 4" Perforated Plastic Pipe	None	\$210	20	Apr-10	May-10
28	3S920	MRN	101	3.0	INSTALL ROCK SLOPE PROTECTION (RSP)	IN SAUSALITO, NORTH OF RODEO DRIVE	RSP	None	None	None	None	None	None	None	None	None	4" Plastic Pipe and 4" Perforated Plastic Pipe	None	\$140	20	May-10	Jun-10

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.



DRAFT NOVEMBER 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 - SOUTH REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

Estimated Quantities of Major Construction Items (in English units unless otherwise noted)																								
EA	CO	Rte.	Postmiles	Project Description	Location(s)	Project Elements (e.g., soundwalls)	Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel (LB)	Structural Steel (LB)	Treat Bridge Deck (SQFT)	Furnish Bridge Deck Treatment material (GAL)	Unique Construction Items	Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Call out # in \$K (EE that excludes contingencies, state furnished materials & supp work)	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement (Month-Year)	Anticipated Bid Opening Date	
29	1E420	SM	280/380	280 - pm 12.7/24.6; 380 - pm 5.5/6.2	Various Locations (9 Bridges)	Joint seals and meth deck	None	None	2	None	None	None	None	None	None	None	None	None	None	None	\$335	44	Oct-09	Dec-09
30	15136	SCL	17/880	Various	Various	Install Closed Circuit TV Cameras	None	None	None	None	None	None	None	None	None	None	None	None	Electrical LS	None	\$870	80	Nov-09	Dec-09
31	15137	SCL	101/237	Various	Various	Install Closed Circuit TV Cameras	None	None	None	None	None	None	None	None	None	None	None	None	Electrical LS	None	\$1,530	125	Oct-09	Dec-09
32	15139	SCL	87/85	Various	Various	Install Closed Circuit TV Cameras	None	None	None	None	None	None	None	None	None	None	None	None	Electrical LS	None	\$940	80	Nov-09	Dec-09
33	15138	SCL/SM	280/680	Various	Various	Install Closed Circuit TV Cameras	None	None	None	None	None	None	None	None	None	None	None	None	Electrical LS	None	\$1,200	100	Nov-09	Dec-09
34	16374	SF	101	8.0/9.8	Doyle Drive Contract 4 - SB Battery Tunnel	Approach to Golden Gate Bridge - in Presidio (GGNRA)	Retaining Walls, At-Grade Detour, Substation, Roadway	17,400 HMA	None	28,566	25,200	44,500	104,533	27,700	7,300,800	2,230,000	None	None	Tunnel - \$84600	301	\$102,557	645	Nov-09	Dec-09
35	1E720	SM	92	7.3/13.9	RHMA Overlay	In & near San Mateo & Foster city from Rte 280/92 separation to 0.3 mile east of Foster city Blvd OC	HMA & RHMA overlay	HMA= 760 tons, RHMA= 22,100 tons	None	None	None	None	None	None	None	None	None	None	None	None	\$3,240	80	Dec-09	Jan-10
36	1E300	SF	101/280	SF-101-3.4/8.3 SF-280-R6.6/R0.6 MRN-101-7.4/R20.9	Replace Joint Seals, Apply Methacrylate, Patch Spalls, Clean	Route 101 - 23rd St Overcrossing to Franklin Ave Overhead; ROUTE 280 - at 18th Street Overcrossing	Joint Seals & Bridge deck Methacrylate	None	None	None	None	None	None	None	None	None	None	None	None	None	\$1,457	69	Jan-10	Mar-10
37	1E740	SM	82	8.6/12.1	BWC Overlay	in San Mateo - from North Road to El Cerrito Avenue/Tilton Avenue	HMA & RHMA overlay	RHMA 5600 tons HMA 220 tons	80	None	None	None	None	None	None	None	None	None	None	None	\$3,340	90	Jan-10	Feb-10
38	1E410	SM	001, 035, 114 const web says 001	various locations	Various Locations (30 Bridges Including 2 Bridges on SM-35 & SM-114)	Treat Bridge Deck with Methacrylate and Repair/Replace Joint Seals	Bridge deck Methacrylate	None	None	None	None	None	None	None	None	215,000	2,400	None	None	None	\$510	80	Jan-10	Mar-10
39	0G470	SCL	280	16.0/17.8	Grind and replace AC at bridge approaches	Robleda Undercrossing to Elena Undercrossing	HMA overlay	HMA 1100 tons	None	None	None	None	None	None	None	None	None	None	None	None	\$303	30	Feb-10	Mar-10
40	24992	SM	82	0.0/15.9	Modify Existing Traffic Signals	El Camino Real from Cambridge Ave. in Menlo Park to Millbrae Avenue in Millbrae	Traffic Signals, Pavement Repl.	HMA=1070 tones	83.7	None	None	57	NONE	60	NONE	913	NONE	NONE	None	None	\$7,835	260	Feb-10	Apr-10
41	1E480	SCL	087	various locations - between 1.3/6.0	Joint seals, joint repair and meth deck.	Various (40 BRIDGES)	Bridge deck Methacrylate	None	None	None	None	None	None	None	None	314,000	3,500	None	None	None	\$1,815	155	Feb-10	Apr-10
42	0A782	SCL	VAR	Various	Upgrade Traffic Barrier and Guard Rail Terminals	Various	MBGR END TREATMENTS	None	None	None	None	None	None	None	None	None	None	None	None	170	\$2,075	170	Mar-10	Apr-10
43	0G480	SCL	880	0.0/4.3	AC resurfacing-route 280 to old baydhore Hwy	from Route 280/880 Separation to Old Bayshore Highway Overhead	HMA overlay	HMA=5570 /RHMA=0	None	None	None	None	None	None	None	None	None	None	None	None	\$950	40	Mar-10	Jun-10

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.



DRAFT NOVEMBER 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 - SOUTH REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

Estimated Quantities of Major Construction Items (in English units unless otherwise noted)																								
	EA	CO	Rte.	Postmiles	Project Description	Location(s)	Project Elements (e.g., soundwalls)	Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel (LB)	Treat Bridge Deck (SQFT)	Furnish Bridge Deck Treatment material (GAL)	Unique Construction Items	Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Call out # in \$K (EE that excludes contingencies, state furnished materials & supp work)	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement (Month-Year)	Anticipated Bid Opening Date
44	1E020	SM/SF	280/1	280 - R5.0 / R24.6; 001 - R0.3 / R7.0	Treat bridge decks with methacrylate	Various Locations	Bridge deck methacrylate	None	None	None	None	None	None	None	None	None	None	None	None	None	\$500	65	Mar-10	May-10
45	1A522	SM	084	See Location	Seismic Retrofit - Dumbarton Bridge	lin San Mateo County at the Dumbarton Bridge (BR #35 - 0038)	Raise & Retrofit Bridge, Const. Pump Plant, Improve Public Access	HMA 4000 tons	NA	6300	1350	700	3000	150	2,100,000	1,250,000	None	None	Raise Steel Sec. of Bridge, Install Isolation Bearing	BCDC, ACOE, RWQCB	\$188,000	810	Mar-10	May-10
46	04080	SF	080	5.4/8.8	Repl 15kv Cable	SFOBB - lower deck	NONE	None	None	None	None	None	None	None	None	None	None	None	15 KV Electrical Cable	TBD	\$800	50 WD (150 DAYS OF DELAY START)	Apr-10	Mar-10

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.