



APRIL 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 SOUTH REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Estimated Quantities of Major Construction Items (in English units unless otherwise noted)										Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Engineer's Estimate	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement Date	Anticipated Bid Opening Date
								Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel (LB)	Unique Construction Items					
27	3A110	SM	101	3.1	INSTALL A STANDBY GENERATOR	AT HENDERSON PUMP HOUSE	Diesel generator, electrical, retaining wall	0	0	50	0	0	100	4,200	0	0	Diesel generator set	None	\$200	90	Advertised 4/6/09	May-09
28	4C360	SCL	101	R9.1/R17.8	REPLACE CONCRETE SLABS	BUENA VISTA OVERCROSSING TO COCHRANE RD OVERCROSSING	Concrete slabs	0	850	0	0	0	0	0	1,550 EA	0	None	None	\$650	40	Advertised 4/6/09	May-09
29	3A560	SCL	152	21.3/22.0	INSTALL SOFT MEDIAN BARRIER	NEAR GILROY FROM 1.7 MILES EAST OF SAN FELIPE RD TO ROUTE 156	Centerline Rumble Strip	900 HMA (A)	0	0	0	0	0	0	0	0	None	None	\$360	60	Advertised 4/13/09	May-09
30	1E180	SCL	152	11.2/19.7	DIGOUT	AT VARIOUS LOCATIONS	None	2,800	0	0	0	8,700 SQYD	0	0	0	0	None	None	\$550	40	Advertised 4/20/09	May-09
31	1E510	SM	1	40.7/46.7	DIGOUT	AT VARIOUS LOCATIONS	None	4,500 tonne	0	0	0	0	0	0	0	0	None	None	\$750	40	Advertised 4/27/09	May-09
32	27202	SCL	280	5.1/7.8	REHABILITATE ROADWAY	FROM CYPRESS AVE PEDESTRIAN OVERCROSSING TO TANTAU AVE OVERCROSSING	Replace and grind concrete pavement, widen ramp shoulders, and other improvements	6,300 HMA 9,900 RHMA	2,350	470	0	7,500	0	50	0	0	None	None	\$10,800	360 WD 120 PED	Advertised 4/27/09	Jun-09
33	1A430	SF	35	1.7	INSTALL TRAFFIC SIGNAL	AT ZOO RD/LAKE MERCED BLVD INTERSECTION	Traffic signal	0	0	120	0	0	0	0	0	0	Traffic signal and lighting	None	\$300	120	May-09	Jun-09
34	04224	SM	92	14.4/18.8	REPLACE 12KV ELECTRIC SWITCHGEARS	SAN MATEO-HAYWARD BRIDGE	Electrical fiber-optic lines, transformers, substations	0	0	0	0	0	0	0	0	300 KG	Specialty electrical work	401, BCDC	\$3,000	350	May-09	June-09
35	3S672	SM	84	13.8 & 16.4	STORM DAMAGE REPAIRS	OLD LA HONDA RD TO FOX HILL RD	Anchored Wire Mesh System (Tecco Mesh)	0	0	0	0	0	0	0	0	0	None	None	\$550	50	May-09	Jun-09
36	15047	SM	280	0/27.4	INSTALL TRAFFIC MANAGEMENT SYSTEM	FROM SANTA CLARA COUNTY LINE TO SAN FRANCISCO COUNTY LINE	CMS CCTV	90	0	20	0	150	50	50	1,950	56,000	None	None	\$1,600	250	Jun-09	Jul-09

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.



APRIL 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 SOUTH REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Estimated Quantities of Major Construction Items (in English units unless otherwise noted)										Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Engineer's Estimate	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement Date	Anticipated Bid Opening Date	
								Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel (LB)	Unique Construction Items						
37	1E390	SCL	35	7.7/14.1	ASPHALT CONCRETE SURFACING	NEAR LOS GATOS FROM BLACK RD TO RTE 35/9 SEPARATION	Replace asphalt concrete pavement with RHMA-G	7,300 RHMA-G	0	0	0	0	0	0	0	0	0	None	None	\$1,200	40	Jun-09	Jul-09
38	0A920	SM	280	13.3/13.6	REPLACE SAFETY ROADSIDE REST AREA	NEAR HILLSBOROUGH AT CRYSTAL SPRINGS SAFETY ROADSIDE REST AREA	Update SRRA - Bring site into ADA compliance, construct new restrooms, CHP sub-station, other site improvements	30	140	60	150	150	100	0	3,000	1,500	Building work (lump sum)	None	\$4,500	250 WD 250 PED	Jul-09	Aug-09	
39	0C901	SCL	101	27.6/40.2	REHABILITATE ROADWAY	IN SAN JOSE NORTH OF SILICON VALLEY BLVD TO GUADALUPE RIVER BRIDGE	None	70,000 HMA 141,000 RHMA	0	190	1,700	0	0	20	0	0	None	None	\$35,500	240	Jul-09	Sep-09	
40	1A500	SF SM	35, 80, 92, 101, 280, 380	Var	UPGRADE EXISTING ATTENUATORS	AT VARIOUS LOCATIONS	Replace sand-filled crash cushions with attenuators	0	0	0	0	0	0	0	0	0	None	None	\$1,400	60	Aug-09	Sep-09	
41	2A050	SCL	152	13.8/14.8	CONSTRUCT LEFT TURN POCKET	FROM 0.9 KM WEST OF PRUNEDALE AVE TO 0.5 KM WEST OF BLOOMFIELD AVE	Left turn pocket, shoulder widening	6,900	0	0	0	2,900	0	0	0	0	None	401, 404	\$1,100	100	Sep-09	Nov 09	

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.

APRIL 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 EAST REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Estimated Quantities of Major Construction Items (in English units unless otherwise noted)										Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Engineer's Estimate	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement Date	Anticipated Bid Opening Date
								Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel (LB)	Structural Steel (LB)	Unique Construction Items					
1	29083	ALA	580	13.2/19.1	CONSTRUCT EASTBOUND HOV, SEGMENT 2	IN LIVERMORE, DUBLIN AND PLEASANTON	Pavement, TOS, soundwall, concrete barrier, retaining wall	441,000 HMA 48,900 RHMA	500	350	0	44,000	1,450	9,000	110,000	0	None	401, 404, 1602	\$52,000	490	Advertised Jan-09	May-09
2	17133	ALA	580 84	Rte. 580: 21.0/24.0 Rte. 84: 46.4/47.2	CONSTRUCT ISABEL AVE/I-580 INTERCHANGE	IN LIVERMORE ON RTE 580 FROM 0.2 KM EAST OF PORTOLA AVE OVERCROSSING TO 0.1 KM EAST OF AIRWAY BLVD OVERCROSSING AND ON RTE 84 FROM 0.3 KM NORTH OF AIRWAY BLVD TO 0.5 KM SOUTH OF PORTOLA AVE	New interchange, new bridges, bridge widening, retaining walls, soundwall	32,000 HMA 13,000 RHMA	0	8,000	195,000	21,000	4,000	31,000	1,024,000	0	None	401, 404, 1602	\$47,000	800	Advertised Jan-09	May-09
3	16542	ALA	880	027.2/028.2	SEISMIC RETROFIT, PHASE-2	IN OAKLAND AT HIGH STR OVERHEAD	Replace bridges, construct roadway, retaining walls, and pumping plant	29,000 tonne	0	21,000 m ³	7,000 m ³	46,000 m ³	10,000 m ³	27,000 m ³	3,900,000 KG	34,000 KG	None	None	\$75,000	1,100	Advertised Apr-09	Jun-09
4	29493	ALA	24	KP 8.8	WIDEN CALDECOTT LANE AT KAY	CALDECOTT LANE AT KAY	Signal at Kay/Broadway and widening of Caldecott Lane	110 tonne	0	0	0	260 m ³	0	90 m ³	0	0	None	None	\$370	95	Advertised Apr-09	Jun-09
5	4A580	ALA	24	1.8/2.8	RESURFACE RAMPS	IN OAKLAND FROM RTE 580/24 SEPARATION TO 52ND STR UNDERCROSSING	None	5,700	0	0	0	0	0	0	0	0	None	None	\$800	90	Advertised Apr-09	Jun-09
6	04224	ALA	92	Var	REPLACE 12KV ELECTRIC SWITCH GEARS	IN ALAMEDA COUNTY	Electrical	0	0	0	0	0	0	0	0	200	Electrical	None	\$3,000	350	May-09	Jun-09
7	29492	ALA	24	KP 7.6/8.8	REPLACE RAMP	WESTBOUND RTE 24 TO NORTHBOUND RTE 13	Ramp replacement, bioswale	120 tonne	1,650 m ³	0	0	8,300 m ³	0	50 m ³	0	0	None	None	\$3,900	100	May-09	Jul-09
8	17790	ALA	880	28.2/28.5	REHABILITATE STRUCTURE	IN OAKLAND AT FRUITVALE AVE SEPARATION OVERHEAD	None	2,300 tonne	0	550 m ³	0	0	0	25 m ³	62,500 KG	0	Polyester concrete	None	\$6,500	250	May-09	Jul-09
9	29491	ALA CC	24	KP 8.2/10 (ALA) KP 0.0/2.7 (CC)	CONSTRUCT TUNNEL, FOURTH BORE	ON RTE 24 AT THE CALDECOTT TUNNEL	Tunnel, retaining walls, soundwall, bioswale, rdwy realignment, OMC building, TOS, groove exist. conc. pvmt, conc. barrier	5,700 tonne	5,800 m ³	2,700 m ³	0	34,000 m ³	12,450 m ³	4,900 m ³	405,300 KG	16,100 KG	OMC building, cross tunnel passages, tunnel portals, tunnel, architectural treatment façade	404, 401, 1602	\$270,000	1,100	May-09	Aug-09

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.



APRIL 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 EAST REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Estimated Quantities of Major Construction Items (in English units unless otherwise noted)										Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Engineer's Estimate	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement Date	Anticipated Bid Opening Date
								Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel (LB)	Unique Construction Items					
10	3A970	ALA	580	KP 14.5	REBULD SCALE HOUSE	IN LIVERMORE ON WB RTE 580 1.2 KM EAST OF VASCO RD AT LIVERMORE WEIGH STATION	Building	15 tonne	0	40 m ³	0	0	50 m ³	25 m ³	Included in concrete	150 KG	Weigh-scale building	None	\$1,550	150	Jul-09	Aug-09
11	04463	ALA SF	80	8.8 /8.9	REPAIR JOINTS--PIERS E5, E8, E12, E15, E16	AT THE SAN FRANCISCO-OAKLAND BAY BRIDGE EAST OF YERBA BUENA ISLAND	Joint Repair	0	0	8	0	0	0	0	1,130	0	All work on toll bridge (steel)	401	\$400	35	Jul-09	Oct-09
12	2R990	ALA	13	10.0/13.6	PERFORM MICROSURFACING	FROM HILLER TO SAN PABLO	None	2,150 tonne	0	0	0	0	0	0	0	0	None	None	\$1,500	45	Jul-09	Sep-09
13	25376	ALA	680	4.7/5.2	ENVIRONMENTAL MITIGATION	IN FREMONT AT VARIOUS LOCATIONS FROM 0.6 MILES TO 0.2 MILES SOUTH OF WASHINGTON BLVD	None	0	0	200 m ³	0	20,000 m ³	80 m ³	0	700 KG	0	Wetland, Riparian, Oak Woodland habitats	401, 404, 1602	\$3,000	250 WD 750 PED	Oct-09	Dec-09

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.



APRIL 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 NORTH REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

CALIFORNIA DEPARTMENT OF TRANSPORTATION

#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Estimated Quantities of Major Construction Items (in English units unless otherwise noted)										Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Engineer's Estimate	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement Date	Anticipated Bid Opening Date	
								Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel (LB)	Unique Construction Items						
14	1E540	SOL	29	0/5.96	RESURFACE ASPHALT CONCRETE	IN VALLEJO FROM RTE 29/80 SEPARATION TO NAPA COUNTY LINE	AC overlay	20,300 RHMA 210 HMA	0	0	0	0	0	0	0	0	0	None	None	\$4,500	90	Advertised Mar-09	May-09
15	0G000	SOL	37	7.2	HIGHWAY PLANTING	IN VALLEJO AT THE GUADALCANAL VILLAGE VIEWING AREA	Planting and fence work	0	0	0	250	230	0	0	0	0	0	Planting and plant establishment	BCDC	\$200	80 WD 750 PED	Advertised Apr-09	May-09
16	1E1901	NAP	29	21.3/29.3	RESURFACE ASPHALT CONCRETE	IN AND NEAR SAINT HELENA FROM 0.4 MILE SOUTH OF DWYER RD TO 0.3 MILE SOUTH OF OAKVILLE GRADE RD AND FROM SULPHUR CREEK TO YORK CREEK	Cold Plane and pave with RHMA-G	4,000 RHMA-G	0	0	0	0	0	0	0	0	0	None	None	\$900	45	May-09	Jun-09
17	0A912	SON	101 121 128	Var	UPGRADE TRAFFIC BARRIERS AND END TERMINALS	AT VARIOUS LOCATIONS	MBGR, end terminals	15	0	81	0	0	90	0	9,600	0	None	None	\$1,700	155	May-09	Jun-09	
18	0A911	SON	1 12 116	Var	UPGRADE TRAFFIC BARRIERS AND END TERMINALS	AT VARIOUS LOCATIONS	MBGR, end terminals	6	0	0	0	0	0	0	0	0	None	None	\$1,700	80	May-09	Jun-09	
19	0A913	SON	12 37 116 121	Var	UPGRADE TRAFFIC BARRIERS AND END TERMINALS	AT VARIOUS LOCATIONS	MBGR, end terminals	5	0	0	0	0	0	0	0	0	None	None	\$950	80	May-09	Jun-09	
20	4A140	MRN	580	3.8/4.8	MODIFY INTERCHANGE	JUNCTION OF I-580 AND US-101 IN SAN RAFAEL	Bridge replacement, auxiliary lane, connector widening	14,000	1,200	2,000	0	7,700	3,800	4,700	356,000	0	None	None	\$12,900	245	Jun-09	Jul-09	
21	0T145	SOL	37	7.2/10.5	PERFORM HIGHWAY PLANTING AND LANDSCAPING	IN VALLEJO ON RTE 37 FROM THE NAPA RIVER BRIDGE TO DIABLO ST (KP R12.9/R16.9)	Tree, shrubs, groundcover, chainlink gates, irrigation systems, rock blanket	0	0	0	0	0	0	0	0	0	Planting, irrigation and rock blanket	None	\$1,350	180 WD 750 PED	May-09	Jul-09	
22	1E380	NAP	29	38.1/48.6	COLD PLANE ASPHALT CONCRETE PLAVEMENT AND PLACE HMA(A)	NEAR CALISTOGA FROM 0.2 MILE NORTH OF SILVERADO TRAIL TO LAKE COUNTY LINE	Cold Plane and pave with HMA(A)	3,550 HMA (A)	0	0	0	0	0	0	0	0	None	None	\$550	45	May-09	Jun-09	
23	29900	SOL	80	6.6/6.8	RESTORE ROADSIDE REST AREA	IN VALLEJO AT THE HUNTER HILL SAFETY ROADSIDE REST AREA	New restroom facility	0	150	1,000	2,500	15	500	270	166,500	20,000	New restroom facility, additive bid	None	\$5,000	300	Jun-09	Aug-09	

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.



APRIL 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 NORTH REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Estimated Quantities of Major Construction Items (in English units unless otherwise noted)										Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Engineer's Estimate	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertise-ment Date	Anticipated Bid Opening Date	
								Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel (LB)	Unique Construction Items						
24	1E220	SON	1	30.5/35.5 50.6/58.5	REPLACE ASPHALT CONCRETE SURFACING	FROM 2.5 MILES SOUTH OF FORT ROSS RD TO TIMBER COVE RD AND FROM SEA WALK DR TO GUALALA RIVER BRIDGE	Replace AC pavement	1,800 HMA (A)	0	0	0	0	0	0	0	0	0	None	None	\$400	45	Jun-09	Jul-09
25	4A450	SOL	80	14.4/0	REPLACE WEIGH SCALES	AT THE EASTBOUND CORDELIA WEIGH STATION	Weigh scales, display signs	0	0	0	0	0	0	0	0	0	Electrical work (lump sum)	None	\$650	150	Jul-09	Aug-09	
26	4A870	SON	128	17.1/24.7	REPLACE BRIDGE	IN SONOMA COUNTY	CIDH piles, bridge components	7 tonne	0	1,120 m ³	370 m ³	0	900 m ³	0	250,000 KG	0	None	None	\$7,300	260	Jul-09	Aug-09	

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.



APRIL 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 SOUTH REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Estimated Quantities of Major Construction Items (in English units unless otherwise noted)										Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Engineer's Estimate	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement Date	Anticipated Bid Opening Date
								Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel (LB)	Unique Construction Items					
27	3A110	SM	101	3.1	INSTALL A STANDBY GENERATOR	AT HENDERSON PUMP HOUSE	Diesel generator, electrical, retaining wall	0	0	50	0	0	100	4,200	0	0	Diesel generator set	None	\$200	90	Advertised 4/6/09	May-09
28	4C360	SCL	101	R9.1/R17.8	REPLACE CONCRETE SLABS	BUENA VISTA OVERCROSSING TO COCHRANE RD OVERCROSSING	Concrete slabs	0	850	0	0	0	0	0	1,550 EA	0	None	None	\$650	40	Advertised 4/6/09	May-09
29	3A560	SCL	152	21.3/22.0	INSTALL SOFT MEDIAN BARRIER	NEAR GILROY FROM 1.7 MILES EAST OF SAN FELIPE RD TO ROUTE 156	Centerline Rumble Strip	900 HMA (A)	0	0	0	0	0	0	0	0	None	None	\$360	60	Advertised 4/13/09	May-09
30	1E180	SCL	152	11.2/19.7	DIGOUT	AT VARIOUS LOCATIONS	None	2,800	0	0	0	8,700 SQYD	0	0	0	0	None	None	\$550	40	Advertised 4/20/09	May-09
31	1E510	SM	1	40.7/46.7	DIGOUT	AT VARIOUS LOCATIONS	None	4,500 tonne	0	0	0	0	0	0	0	0	None	None	\$750	40	Advertised 4/27/09	May-09
32	27202	SCL	280	5.1/7.8	REHABILITATE ROADWAY	FROM CYPRESS AVE PEDESTRIAN OVERCROSSING TO TANTAU AVE OVERCROSSING	Replace and grind concrete pavement, widen ramp shoulders, and other improvements	6,300 HMA 9,900 RHMA	2,350	470	0	7,500	0	50	0	0	None	None	\$10,800	360 WD 120 PED	Advertised 4/27/09	Jun-09
33	1A430	SF	35	1.7	INSTALL TRAFFIC SIGNAL	AT ZOO RD/LAKE MERCED BLVD INTERSECTION	Traffic signal	0	0	120	0	0	0	0	0	0	Traffic signal and lighting	None	\$300	120	May-09	Jun-09
34	04224	SM	92	14.4/18.8	REPLACE 12KV ELECTRIC SWITCHGEARS	SAN MATEO-HAYWARD BRIDGE	Electrical fiber-optic lines, transformers, substations	0	0	0	0	0	0	0	0	300 KG	Specialty electrical work	401, BCDC	\$3,000	350	May-09	June-09
35	3S672	SM	84	13.8 & 16.4	STORM DAMAGE REPAIRS	OLD LA HONDA RD TO FOX HILL RD	Anchored Wire Mesh System (Tecco Mesh)	0	0	0	0	0	0	0	0	0	None	None	\$550	50	May-09	Jun-09
36	15047	SM	280	0/27.4	INSTALL TRAFFIC MANAGEMENT SYSTEM	FROM SANTA CLARA COUNTY LINE TO SAN FRANCISCO COUNTY LINE	CMS CCTV	90	0	20	0	150	50	50	1,950	56,000	None	None	\$1,600	250	Jun-09	Jul-09

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.



APRIL 2009 UPCOMING CONSTRUCTION PROJECTS DISTRICT 4 SOUTH REGION

*All information presented here is an estimate; it is preliminary and subject to change.**

#	EA	CO	Rte.	Postmiles	Project Description	Location	Project Elements (e.g., soundwalls)	Estimated Quantities of Major Construction Items (in English units unless otherwise noted)										Environmental Permits (e.g., 404 USACOE, 401 Water Quality, 1602 Fish & Game, etc.)	Engineer's Estimate	Estimated Working Days (WD) & Plant Establishment Days (PED)	Anticipated Advertisement Date	Anticipated Bid Opening Date	
								Hot Mix Asphalt (HMA) with Rubberized HMA (RHMA) broken out [tons]	Portland Cement Concrete Pavement (CY)	Structural Concrete (incl. Footing and Wall) [CY]	Imported Borrow (CY)	Roadway Excavation (CY)	Structural Excavation (incl. Retaining walls) [CY]	Aggregates (all non-treated Bases) [CY]	Bar Reinforcing Steel [LB]	Structural Steel (LB)	Unique Construction Items						
37	1E390	SCL	35	7.7/14.1	ASPHALT CONCRETE SURFACING	NEAR LOS GATOS FROM BLACK RD TO RTE 35/9 SEPARATION	Replace asphalt concrete pavement with RHMA-G	7,300 RHMA-G	0	0	0	0	0	0	0	0	0	None	None	\$1,200	40	Jun-09	Jul-09
38	0A920	SM	280	13.3/13.6	REPLACE SAFETY ROADSIDE REST AREA	NEAR HILLSBOROUGH AT CRYSTAL SPRINGS SAFETY ROADSIDE REST AREA	Update SRRA - Bring site into ADA compliance, construct new restrooms, CHP sub-station, other site improvements	30	140	60	150	150	100	0	3,000	1,500	Building work (lump sum)	None	\$4,500	250 WD 250 PED	Jul-09	Aug-09	
39	0C901	SCL	101	27.6/40.2	REHABILITATE ROADWAY	IN SAN JOSE NORTH OF SILICON VALLEY BLVD TO GUADALUPE RIVER BRIDGE	None	70,000 HMA 141,000 RHMA	0	190	1,700	0	0	20	0	0	None	None	\$35,500	240	Jul-09	Sep-09	
40	1A500	SF SM	35, 80, 92, 101, 280, 380	Var	UPGRADE EXISTING ATTENUATORS	AT VARIOUS LOCATIONS	Replace sand-filled crash cushions with attenuators	0	0	0	0	0	0	0	0	0	None	None	\$1,400	60	Aug-09	Sep-09	
41	2A050	SCL	152	13.8/14.8	CONSTRUCT LEFT TURN POCKET	FROM 0.9 KM WEST OF PRUNEDALE AVE TO 0.5 KM WEST OF BLOOMFIELD AVE	Left turn pocket, shoulder widening	6,900	0	0	0	2,900	0	0	0	0	None	401, 404	\$1,100	100	Sep-09	Nov 09	

*Please check the Caltrans OE webpage at http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.html for the latest information on contracts.