



Caltrans[®]

**STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION**

**NOTICE TO BIDDERS
AND
SPECIAL PROVISIONS**

**FOR BUILDING CONSTRUCTION ADJACENT TO SOLANO COUNTY IN VALLEJO AT
THE HUNTER HILL SAFETY ROADSIDE REST AREA**

In District 04 On Route 80

Under

Bid book dated June 1, 2009

Standard Specifications dated 2006

Project Plans approved June 25, 2007

Standard Plans dated 2006

Identified by

Contract No. 04-299004

04-Sol-80-6.7

Federal-Aid Project

ACIM-080-2(350)E

Bids open Wednesday, July 15, 2009
Dated June 1, 2009

OSD
IH

SPECIAL NOTICES

- The Department moved the Amendments to the Standard Specifications to the back of the book titled "Notice to Bidders and Special Provisions."
- The Department retitled the "Proposal and Contract" book to "Bid" book and:
 1. Simplified the language
 2. Moved clauses and the contract form from the "Proposal and Contract" book into the Amendments to the Standard Specifications
 3. Standardized the forms
- The Department retitled the "Notice to Contractors" to "Notice to Bidders" and:
 1. Simplified the language
 2. Moved clauses from the "Notice to Contractors" into the Amendments to the Standard Specifications
 3. Standardized instructions for bidders' inquiries
- The Department incorporated boilerplate special provisions into the Amendments to the Standard Specifications.
- The Department is implementing new Disadvantaged Business Enterprise requirements for Underutilized Disadvantaged Business Enterprises (UDBE). Section 2, "Bidding," under subsection titled "Disadvantaged Business Enterprises" and Section 5, "General," under subsection titled "Performance of UDBEs" of these special provisions cover the UDBE requirements.
- The contract award period has been extended for this project.
- See Section 5 of the special provisions for new specifications regarding retentions.
- The Department is implementing new contract requirements for submittal of Small Business Utilization Report forms. See section titled "Small Business Utilization Report" of these special provisions and bid item list.
- The bidder's attention is directed to Section 2, "Proposal Requirements and Conditions," and Section 3, "Award and Execution of Contract," in the special provisions regarding bidding the ADDITIVE ITEM and comparison of bids. Bids must include a lump sum amount for the ADDITIVE ITEM.
- The bidder's attention is directed to Section 5-1.017, "Contract Bonds," in the special provisions regarding bonding.
- The Department has replaced Section 8, "Prosecution and Progress." This replacement affects references in a large number of other specifications. Due to the extent of affected specifications, these references will not be corrected until there is a change in technical content that merits a specification revision. Section 0, "Global Revisions," of the Amendments to the Standard Specifications covers references affected by the Section 8 replacement.

TABLE OF CONTENTS

NOTICE TO BIDDERS	1
COPY OF BID ITEM LIST.....	3
SPECIAL PROVISIONS.....	6
SECTION 1 (BLANK).....	6
SECTION 2 BIDDING.....	6
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS.....	6
2-1.01 GENERAL.....	6
2-1.015 FEDERAL LOBBYING RESTRICTIONS.....	6
2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE).....	7
2-1.03 SMALL BUSINESS ENTERPRISE GOAL.....	8
SECTION 3. AWARD AND EXECUTION OF CONTRACT.....	8
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION, AND LIQUIDATED DAMAGES.....	9
SECTION 5 GENERAL.....	9
SECTION 5-1. MISCELLANEOUS.....	9
5-1.01 PERFORMANCE OF UDBES.....	9
5-1.02 TRAINING.....	10
5-1.03 RETENTION EXCLUSION.....	10
5-1.04 CONTRACT BONDS.....	10
5-1.05 FORCE ACCOUNT PAYMENT.....	10
5-1.06 PARTNERING.....	11
5-1.07 AREAS FOR CONTRACTOR'S USE.....	11
5-1.08 PAYMENTS.....	11
5-1.09 PROJECT INFORMATION.....	12
5-1.10 SOUND CONTROL REQUIREMENTS.....	12
5-1.11 HIGHWAY CONSTRUCTION EQUIPMENT.....	13
5-1.12 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD.....	13
WITHHOLDS.....	14
5-1.13 ENVIRONMENTALLY SENSITIVE AREA.....	14
5-1.14 PRESERVATION OF PROPERTY.....	14
5-1.15 DAMAGE REPAIR.....	15
5-1.16 RELIEF FROM MAINTENANCE AND RESPONSIBILITY.....	15
SECTION 6. (BLANK).....	15
SECTION 7. (BLANK).....	15
SECTION 8. MATERIALS.....	15
SECTION 8-1. MISCELLANEOUS.....	15
8-1.01 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS.....	15
8-1.02 STATE-FURNISHED MATERIALS.....	20
8-1.03 ENGINEERING FABRICS.....	21
SECTION 8-2. CONCRETE.....	21
8-2.01 PORTLAND CEMENT CONCRETE.....	21
SECTION 8-3. WELDING.....	22
8-3.01 WELDING.....	22
WELDING QUALITY CONTROL.....	24
PAYMENT.....	27
SECTION 9. (BLANK).....	27
SECTION 10. CONSTRUCTION DETAILS.....	27
SECTION 10-1. GENERAL.....	27
10-1.01 ORDER OF WORK.....	27
10-1.02 WATER POLLUTION CONTROL.....	28
SAMPLING AND ANALYSIS.....	30
IMPLEMENTATION REQUIREMENTS.....	32
INSPECTION AND MAINTENANCE.....	32
REPORTING REQUIREMENTS.....	32
PAYMENT.....	33

10-1.03 CONSTRUCTION SITE MANAGEMENT	33
SPILL PREVENTION AND CONTROL	34
MATERIAL MANAGEMENT	35
WASTE MANAGEMENT	36
NON-STORM WATER MANAGEMENT	39
PAYMENT	41
10-1.04 STREET SWEEPING	41
10-1.05 TEMPORARY COVER	42
10-1.06 TEMPORARY CONCRETE WASHOUT FACILITY	44
10-1.07 TEMPORARY SILT FENCE	46
10-1.08 TEMPORARY FENCE (TYPE ESA)	47
10-1.09 TEMPORARY DRAINAGE INLET PROTECTION	48
10-1.10 COOPERATION	51
10-1.11 PROGRESS SCHEDULE (CRITICAL PATH METHOD).....	51
10-1.12 TIME-RELATED OVERHEAD	56
10-1.13 OBSTRUCTIONS	58
10-1.14 SMALL BUSINESS UTILIZATION REPORT	59
10-1.15 DUST CONTROL	59
10-1.16 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES	59
10-1.17 CONSTRUCTION AREA SIGNS	60
10-1.18 TEMPORARY CRASH CUSHION MODULE	61
10-1.19 EXISTING HIGHWAY FACILITIES	62
SALVAGE EXISTING SIGN PLAQUES	62
ABANDON SEWER	62
REMOVE FENCE	63
ADJUST MANHOLE TO GRADE	63
REMOVE CONCRETE (MISCELLANEOUS)	63
10-1.20 CLEARING AND GRUBBING	63
10-1.21 EARTHWORK	63
10-1.22 EROSION CONTROL (TYPE D).....	64
10-1.23 FIBER ROLLS	67
10-1.24 IRRIGATION CROSSOVERS	69
10-1.25 IRRIGATION SLEEVE	69
10-1.26 DECOMPOSED GRANITE	69
MATERIALS	69
TEST PLOTS	70
SITE PREPARATION	70
PLACEMENT	71
MEASUREMENT	71
PAYMENT	71
10-1.27 AGGREGATE BASE	71
10-1.28 PILING	72
CAST-IN-DRILLED-HOLE CONCRETE PILES	72
10-1.29 MINOR CONCRETE (MINOR STRUCTURE)	84
10-1.30 STEEL STRUCTURES	84
MATERIALS	84
ROTATIONAL CAPACITY TESTING PRIOR TO SHIPMENT TO JOB SITE	84
INSTALLATION TENSION TESTING AND ROTATIONAL CAPACITY TESTING AFTER ARRIVAL ON THE JOB SITE	88
WELDING	88
MEASUREMENT AND PAYMENT	89
10-1.31 ROADSIDE SIGNS	89
10-1.32 FURNISH SIGN	89
SHEET ALUMINUM	91
RETROREFLECTIVE SHEETING	91
PROCESS COLOR AND FILM	91
SINGLE SHEET ALUMINUM SIGN	91
MEASUREMENT AND PAYMENT	92

10-1.33 PLASTIC PIPE.....	92
10-1.34 CORRUGATED METAL PIPE.....	92
10-1.35 WATER LINE.....	92
GENERAL.....	92
MATERIALS.....	92
INSTALLATION.....	92
TESTING.....	93
MEASUREMENT AND PAYMENT.....	93
10-1.36 SEWER PIPE AND SEWER TERMINAL CLEANOUT.....	93
10-1.37 DRAINAGE INLET MARKER.....	95
10-1.38 WELDED STEEL PIPE.....	96
10-1.39 DRAIN BOX.....	96
10-1.40 SLOPE PROTECTION.....	96
10-1.41 MISCELLANEOUS CONCRETE CONSTRUCTION.....	96
10-1.42 MISCELLANEOUS IRON AND STEEL.....	97
10-1.43 WELDED WIRE FENCE.....	97
10-1.44 CHAIN LINK FENCE.....	98
10-1.45 HANDRAILING.....	98
10-1.46 SITE FURNISHINGS.....	98
10-1.47 ADDITIVE.....	99
SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS.....	99
10-2.01 GENERAL.....	99
PROGRESS INSPECTIONS.....	99
COST BREAK-DOWN.....	100
10-2.02 EXISTING HIGHWAY PLANTING.....	103
MAINTAIN EXISTING PLANTED AREAS.....	103
REMOVE EXISTING PLANTS FOR TRENCHING.....	103
PRUNE EXISTING PLANTS.....	104
10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES.....	104
LOCATE EXISTING CROSSOVERS AND CONDUITS.....	104
REMOVE EXISTING IRRIGATION FACILITIES.....	104
10-2.04 HIGHWAY PLANTING.....	104
HIGHWAY PLANTING MATERIALS.....	104
ROADSIDE CLEARING.....	106
PESTICIDES.....	107
PREPARING PLANTING AREAS.....	108
CULTIVATE.....	108
PLANTING.....	108
LINER PLANTS.....	109
TURF (SOD).....	109
FOLIAGE PROTECTOR.....	110
PLANT ESTABLISHMENT WORK.....	110
10-2.05 IRRIGATION SYSTEMS.....	111
VALVE BOXES.....	111
BALL VALVES.....	111
ELECTRIC AUTOMATIC IRRIGATION COMPONENTS.....	112
ARMOR-CLAD CONDUCTORS.....	113
IRRIGATION SYSTEMS FUNCTIONAL TEST.....	113
PIPE.....	113
SPRINKLERS.....	114
SPRINKLER (TYPE D).....	114
WYE STRAINERS.....	114
FLUSH CAPS.....	114
FILTER ASSEMBLY UNIT.....	114
FINAL IRRIGATION SYSTEM CHECK.....	114
SECTION 10-3. SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS.....	115
10-3.01 DESCRIPTION.....	115
10-3.02 COST BREAK-DOWN.....	115

10-3.03 FOUNDATIONS	115
10-3.04 STANDARDS, STEEL PEDESTALS, AND POSTS	115
10-3.05 CONDUIT	115
10-3.06 PULL BOXES	116
10-3.07 CABLES, CONDUCTORS AND WIRING	116
10-3.08 BONDING AND GROUNDING	116
10-3.09 SERVICE	116
10-3.10 NUMBERING ELECTRICAL EQUIPMENT	116
10-3.11 LUMINAIRES	116
SECTION 11. (BLANK)	116
SECTION 12. BUILDING WORK	116
SECTION 12-1. GENERAL REQUIREMENTS	116
12-1.01 SCOPE	116
12-1.02 ABBREVIATIONS	117
12-1.03 GUARANTEE	117
12-1.04 AREAS FOR CONTRACTOR'S USE	118
12-1.05 COOPERATION	118
12-1.06 SUBMITTALS	118
12-1.07 PROGRESS SCHEDULE	119
12-1.08 SCHEDULE OF VALUES	119
12-1.09 INSPECTION	120
12-1.10 OBSTRUCTIONS	120
12-1.11 PRESERVATION OF PROPERTY	120
12-1.12 UTILITY CONNECTION	120
12-1.13 TEMPORARY UTILITIES	121
12-1.14 SANITARY FACILITIES	121
12-1.15 MEASUREMENT AND PAYMENT	121
12-1.16 PROJECT RECORD DRAWINGS	121
12-1.17 FIELD ENGINEERING	122
12-1.18 ASBESTOS	123
12-1.19 LEAD BASED MATERIALS	123
SECTION 12-2. SITEWORK	124
12-2.01 REMOVING EXISTING FACILITIES	124
12-2.02 ABANDON PORTIONS OF WASTE DISPOSAL SYSTEM	126
12-2.03 REMOVAL AND DISPOSAL OF ASBESTOS	126
12-2.04 LEAD ABATEMENT	128
12-2.05 ROUGH GRADING	131
12-2.06 EARTHWORK FOR BUILDING WORK	132
12-2.07 AGGREGATE BASE	136
SECTION 12-3. CONCRETE AND REINFORCEMENT	137
12-3.01 CAST-IN-PLACE CONCRETE	137
12-3.02 DRILL AND BOND DOWELS	144
12-3.03 ARCHITECTURAL SURFACE (TEXTURED CONCRETE)	145
SECTION 12-4. MASONRY	147
12-4.01 CONCRETE MASONRY UNITS	147
SECTION 12-5. METALS	151
12-5.01 BUILDING MISCELLANEOUS METAL	151
SECTION 12-6. WOOD AND PLASTICS	154
12-6.01 CABINETS	154
SECTION 12-7. THERMAL AND MOISTURE PROTECTION	157
12-7.01 BITUMINOUS WATERPROOFING	157
12-7.02 SHEET WATERPROOFING	158
12-7.03 WATER REPELLENT COATING	160
12-7.04 SEALANTS AND CAULKING	161
12-7.05 THERMOPLASTIC MEMBRANE ROOFING	162
12-7.06 SHEET METAL FLASHING	166
12-7.07 SKYLIGHTS	169
12-7.08 SEALANTS AND CAULKING	170

12-7.09 RETAINING WALL DRAINAGE SYSTEM	171
SECTION 12-8. DOORS AND WINDOWS	172
12-8.01 HINGED DOORS	172
12-8.02 WINDOWS	173
12-8.03 FINISH HARDWARE	175
12-8.04 GLAZING	179
SECTION 12-9. FINISHES	180
12-9.01 CERAMIC TILE	180
12-9.02 PAINTING	186
SECTION 12-10. SPECIALTIES	191
12-10.01 TACKBOARDS	191
12-10.02 METAL TOILET PARTITIONS	192
12-10.03 LOUVERS	193
12-10.04 INFORMATION DISPLAY CASES	194
12-10.05 SIGNS	195
12-10.06 WARDROBE LOCKERS	196
12-10.07 FIRE EXTINGUISHERS AND CABINETS	197
12-10.08 FREE STANDING STEEL SHELVING	198
12-10.09 TOILET ROOM ACCESSORIES	199
SECTION 12-11. (BLANK)	200
SECTION 12-12. (BLANK)	200
SECTION 12-13. (BLANK)	200
SECTION 12-14. (BLANK)	200
SECTION 12-15. MECHANICAL	200
12-15.01 MECHANICAL WORK	200
12-15.02 PIPE, FITTINGS AND VALVES	203
12-15.03 PLUMBING FIXTURES	213
12-15.04 HEATING, VENTILATING AND AIR CONDITIONING EQUIPMENT	218
12-15.05 PLUMBING BOOSTER SYSTEM	220
12-15.06 FIRE PROTECTION SYSTEM	227
SECTION 12-16. ELECTRICAL	230
12-16.01 ELECTRICAL WORK	230
12-16.02 BASIC MATERIALS AND METHODS	231
12-16.03 SERVICE AND DISTRIBUTION	238
12-16.04 ELECTRICAL EQUIPMENT	240
12-16.05 LIGHTING	242
AMENDMENTS TO THE STANDARD SPECIFICATIONS	245

STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to, those indicated below. Applicable Revised Standard Plans (RSP) and New Standard Plans (NSP) indicated below are included in the project plans as Standard Plan sheets.

A10A	Acronyms and Abbreviations (Sheet 1 of 2)
A10B	Acronyms and Abbreviations (Sheet 2 of 2)
A10C	Symbols (Sheet 1 of 2)
A10D	Symbols (Sheet 2 of 2)
A62A	Excavation and Backfill – Miscellaneous Details
A62F	Excavation and Backfill – Metal and Plastic Culverts
A85	Chain Link Fence
RSP A87A	Curbs and Driveways
RSP A88A	Curb Ramp Details
D73	Drainage Inlets
D74C	Drainage Inlets Details
D77A	Grate Details
H1	Planting and Irrigation – Abbreviations
H2	Planting and Irrigation – Symbols
H3	Planting and Irrigation Details
H4	Planting and Irrigation Details
H5	Planting and Irrigation Details
H6	Planting and Irrigation Details
H7	Planting and Irrigation Details
H9	Planting and Irrigation Details
NSP H51	Erosion Control Details (Fiber Roll)
T2	Temporary Crash Cushion, Sand Filled (Shoulder Installations)
T3	Temporary Railing (Type K)
T51	Temporary Water Pollution Control Details (Temporary Silt Fence)
T53	Temporary Water Pollution Control Details (Temporary Cover)
T56	Temporary Water Pollution Control Details (Temporary Fiber Roll)
T59	Temporary Water Pollution Control Details (Temporary Concrete Washout Facility)
RS1	Roadside Signs, Typical Installation Details No. 1
RS2	Roadside Signs – Wood Post, Typical Installation Details No. 2
RS4	Roadside Signs, Typical Installation Details No. 4
S94	Roadside Framed Single Sheet Aluminum Signs, Rectangular Shape
S95	Roadside Single Sheet Aluminum Signs, Diamond Shape
ES-1A	Electrical Systems (Symbols and Abbreviations)
ES-1B	Electrical Systems (Symbols and Abbreviations)
ES-1C	Electrical Systems (Symbols and Abbreviations)
ES-2A	Electrical Systems (Service Equipment)
ES-2C	Electrical Systems (Service Equipment Notes, Type III Series)
ES-2D	Electrical Systems (Service Equipment and Typical Wiring Diagram, Type III – A Series)
ES-6E	Electrical Systems (Lighting Standard, Types 30 and 31)
ES-6F	Electrical Systems (Lighting Standard, Types 30 and 31, Slip Base Plate Details)
ES-7M	Electrical Systems (Signal and Lighting Standards – Details No. 1)
ES-7N	Electrical Systems (Signal and Lighting Standards – Details No. 2)
ES-8	Electrical Systems (Pull Box Details)
ES-10	Electrical Systems (Isofootcandle Diagrams)
ES-11	Electrical Systems (Foundation Installations)
ES-13A	Electrical Systems (Splicing Details)
ES-13B	Electrical Systems (Wiring Details and Fuse Ratings)
ES-15D	Electrical Systems (Lighting and Sign Illumination Control)

NOTICE TO BIDDERS

Bids open Wednesday, July 15, 2009

Dated June 1, 2009

General work description: Rehabilitate safety roadside rest area.

The Department will receive sealed bids for BUILDING CONSTRUCTION ADJACENT TO SOLANO COUNTY IN VALLEJO AT THE HUNTER HILL SAFETY ROADSIDE REST AREA.

District-County-Route-Post Mile: 04-Sol-80-6.7

Contract No. 04-299004

The Contractor must have either a Class A license or Class B license or a combination of Class C licenses which constitutes a majority of the work.

The UDBE Contract goal is 6 percent.

Federal-aid project no.:

ACIM-080-2(350)E

Bids must be on a unit price basis.

Complete the work, including plant establishment work, within 550 working days.

The estimated cost of the project is \$6,314,000.

No prebid meeting is scheduled for this project.

The Department will receive bids until 2:00 p.m. on the bid open date at 1120 N Street, Room 0200, MS 26, Sacramento, CA 95814. Bids received after this time will not be accepted.

The Department will open and publicly read the bids at the above location immediately after the specified closing time.

District office addresses are provided in the Standard Specifications.

Bidders' inquiries may be presented to the Department by following the instructions at:

http://www.dot.ca.gov/hq/esc/oe/project_status/bid_inq.html

The Department posts responses to the questions at the District Web sites.

Questions about alleged patent ambiguity of the plans, specifications, or estimate must be asked before bid opening. After bid opening, such questions will not be treated as bid protests.

Submit your bid with bidder's security equal to at least 10 percent of the bid.

Prevailing wages are required on this Contract. The Director of the California Department of Industrial Relations determines the general prevailing wage rates. Obtain the wage rates at the DIR Web site, <http://www.dir.ca.gov>, or from the Department's Labor Compliance Office of the district in which the work is located.

The federal minimum wage rates for this Contract as determined by the United States Secretary of Labor are available at <http://www.dot.ca.gov/hq/esc/oe/federal-wages>.

If the minimum wage rates as determined by the United States Secretary of Labor differs from the general prevailing wage rates determined by the Director of the California Department of Industrial Relations for similar classifications of labor, the Contractor and subcontractors must not pay less than the higher wage rate. The Department does not accept lower State wage rates not specifically included in the Federal minimum wage determinations. This includes helper, or other classifications based on hours of experience, or any other classification not appearing in the Federal wage determinations. Where Federal wage determinations do not contain the State wage rate determination otherwise available for use by the Contractor and subcontractors, the Contractor and subcontractors must not pay less than the Federal minimum wage rate that most closely approximates the duties of the employees in question.

DEPARTMENT OF TRANSPORTATION

AOO

COPY OF BID ITEM LIST

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
1	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM
2	070013	SMALL BUSINESS UTILIZATION REPORT	EA	10
3	070018	TIME-RELATED OVERHEAD	WDAY	300
4	071325	TEMPORARY FENCE (TYPE ESA)	LF	650
5	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM
6	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM
7	074029	TEMPORARY SILT FENCE	LF	310
8	074032	TEMPORARY CONCRETE WASHOUT FACILITY	EA	7
9	074034	TEMPORARY COVER	SQYD	2,810
10	074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	4
11	074041	STREET SWEEPING	LS	LUMP SUM
12	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
13	150241	ABANDON SEWER	EA	1
14	150605	REMOVE FENCE	LF	520
15	012384	SALVAGE EXISTING SIGN PLAQUES	LS	LUMP SUM
16	152440	ADJUST MANHOLE TO GRADE	EA	1
17	153246	REMOVE CONCRETE (MISCELLANEOUS)	CY	290
18	160101	CLEARING AND GRUBBING	LS	LUMP SUM
19	190101	ROADWAY EXCAVATION	CY	15
20	198001	IMPORTED BORROW	CY	2,550

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
21	012385	DECOMPOSED GRANITE	SQYD	56
22	203016	EROSION CONTROL (TYPE D)	SQYD	1,940
23	203021	FIBER ROLLS	LF	1,250
24	012386	2" WATER LINE	LF	120
25	208738	8" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	140
26	260301	CLASS 3 AGGREGATE BASE	CY	43
27 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	CY	3
28	560248	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	SQFT	12
29	560252	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED)	SQFT	25
30	566011	ROADSIDE SIGN - ONE POST	EA	5
31	566012	ROADSIDE SIGN - TWO POST	EA	1
32	665010	12" CORRUGATED STEEL PIPE	LF	58
33	680207	3" PLASTIC PIPE	LF	37
34	681023	6" PLASTIC PIPE	LF	450
35	012387	4" PLASTIC PIPE	LF	170
36	700617	DRAINAGE INLET MARKER	EA	4
37	012388	4" WELDED STEEL PIPE	LF	150
38	012389	6" WELDED STEEL PIPE	LF	84
39	012390	12" X 12" DRAIN BOX	EA	5
40	012391	2' X 2' DRAIN BOX	EA	5

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
41	717001	4" POLYVINYL CHLORIDE SEWER PIPE	LF	40
42	012392	5" POLYVINYL CHLORIDE SEWER PIPE	LF	200
43	012393	5" POLYVINYL CHLORIDE SEWER PIPE (CLEANOUT)	LF	8
44	719110	SEWER TERMINAL CLEANOUT	EA	3
45	721012	ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B)	CY	1.5
46	012394	ROCK SLOPE PROTECTION FABRIC (TYPE A)	SQYD	13
47	731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	CY	143
48 (F)	750001	MISCELLANEOUS IRON AND STEEL	LB	670
49	012395	WELDED WIRE FENCE	LF	170
50	800360	CHAIN LINK FENCE (TYPE CL-6)	LF	760
51	802520	6' CHAIN LINK GATE (TYPE CL-6)	EA	3
52 (F)	839514	HANDRAILING	LF	42
53	860460	LIGHTING AND SIGN ILLUMINATION	LS	LUMP SUM
54	012396	INSTALL SITE FURNISHINGS	LS	LUMP SUM
55	994650	BUILDING WORK	LS	LUMP SUM

SPECIAL PROVISIONS

SECTION 1 (BLANK)

SECTION 2 BIDDING

SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS

2-1.01 GENERAL

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the Proposal form and the submission of the bid.

Bids must include a lump sum amount for the additive item. The bid price for the additive item establishes the price for the additional Building and Landscaping work, as shown on the plans, titled "Additive."

The amount of the bidder's security required in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications shall be based on the "**TOTAL BASE BID**" set forth on the proposal form.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

The Contractor, sub recipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The Contractor shall carry out applicable requirements of title 49, part 26, Code of Federal Regulations (49 CFR 26) in the award and administration of USDOT-assisted contracts. Failure by the Contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate. Each subcontract signed by the bidder must include this assurance.

Failure of the bidder to fulfill the requirements of the Special Provisions for submittals required to be furnished after bid opening, including but not limited to escrowed bid documents, where applicable, may subject the bidder to a determination of the bidder's responsibility in the event it is the apparent low bidder on a future public works contracts.

2-1.015 FEDERAL LOBBYING RESTRICTIONS

Section 1352, Title 31, United States Code prohibits Federal funds from being expended by the recipient or any lower tier subrecipient of a Federal-aid contract to pay for any person for influencing or attempting to influence a Federal agency or Congress in connection with the awarding of any Federal-aid contract, the making of any Federal grant or loan, or the entering into of any cooperative agreement.

If any funds other than Federal funds have been paid for the same purposes in connection with this Federal-aid contract, the recipient shall submit an executed certification and, if required, submit a completed disclosure form as part of the bid documents.

A certification for Federal-aid contracts regarding payment of funds to lobby Congress or a Federal agency is included in the Proposal. Standard Form - LLL, "Disclosure of Lobbying Activities," with instructions for completion of the Standard Form is also included in the Proposal. Signing the Proposal shall constitute signature of the Certification.

The above-referenced certification and disclosure of lobbying activities shall be included in each subcontract and any lower-tier contracts exceeding \$100,000. All disclosure forms, but not certifications, shall be forwarded from tier to tier until received by the Engineer.

The Contractor, subcontractors and any lower-tier contractors shall file a disclosure form at the end of each calendar quarter in which there occurs any event that requires disclosure or that materially affects the accuracy of the information contained in any disclosure form previously filed by the Contractor, subcontractors and any lower-tier contractors. An event that materially affects the accuracy of the information reported includes:

- A. A cumulative increase of \$25,000 or more in the amount paid or expected to be paid for influencing or attempting to influence a covered Federal action; or
- B. A change in the person(s) or individual(s) influencing or attempting to influence a covered Federal action; or,
- C. A change in the officer(s), employee(s), or Member(s) contacted to influence or attempt to influence a covered Federal action.

2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE)

This project is subject to title 49, part 26, Code of Federal Regulations (49 CFR 26) entitled "Participation by Disadvantaged Business Enterprises in Department of Transportation Financial Assistance Programs." In order to ensure the Department achieves its federally mandated statewide overall DBE goal, the Department encourages the participation of Disadvantaged Business Enterprises (DBEs), as defined in 49 CFR 26 in the performance of contracts financed in whole or in part with Federal Funds. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the award and performance of subcontracts.

Bidders shall be fully informed respecting the requirements of the Regulations. The Regulations in their entirety are incorporated herein by this reference. Attention is directed to the following matters:

- A. A DBE must be a small business concern as defined pursuant to Section 3 of U.S. Small Business Act and relevant regulations promulgated pursuant thereto.
- B. A DBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, vendor of material or supplies, or as a trucking company.
- C. A DBE joint venture partner must be responsible for specific contract items of work, or clearly defined portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DBE joint venture partner must share in the capital contribution, control, management, risks and profits of the joint venture commensurate with its ownership interest.
- D. A DBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
- E. DBEs must be certified by the California Unified Certification Program (CUCP). Listings of DBEs certified by the CUCP are available from the following sources:
 - 1. The Department's web site at <http://www.dot.ca.gov/hq/bep>.
 - 2. The Department's DBE Directory. This Directory may be obtained from the Department of Transportation, Materiel Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520.
- F. When reporting DBE participation, bidders may count the cost of materials or supplies purchased from DBEs as follows:
 - 1. If the materials or supplies are obtained from a DBE manufacturer, count 100 percent of the cost of the materials or supplies. A DBE manufacturer is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications.
 - 2. If the materials or supplies are purchased from a DBE regular dealer, count 60 percent of the cost of the materials or supplies. A DBE regular dealer is a firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications and required under the contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business. To be a DBE regular dealer, the firm must be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question. A person may be a DBE regular dealer in such bulk items as petroleum products, steel, cement, gravel, stone, or asphalt without owning, operating, or maintaining a place of business as provided in this paragraph F.2. if the person both owns and operates distribution equipment for the products. Any supplementing of regular dealers' own distribution equipment shall be by a long-term lease agreement and not on an ad hoc or contract-by-contract basis. Packagers, brokers, manufacturers' representatives, or other persons who arrange or expedite transactions are not DBE regular dealers within the meaning of this paragraph F.2.
 - 3. If the DBE is neither a manufacturer nor a regular dealer, count only the entire amount of fees or commissions charged for assistance in the procurement of the materials and supplies, or fees or transportation charges for the delivery of materials or supplies required on a job site, provided the fees are reasonable and not excessive as compared with fees charged for similar services.
- G. When reporting DBE participation, bidders may count the participation of DBE trucking companies as follows:
 - 1. The DBE must be responsible for the management and supervision of the entire trucking operation for which it is responsible on a particular contract.

2. The DBE must itself own and operate at least one fully licensed, insured, and operational truck used on the contract.
3. The DBE receives credit for the total value of the transportation services it provides on the contract using trucks its owns, insures, and operates using drivers it employs.
4. The DBE may lease trucks from another DBE firm, including an owner-operator who is certified as a DBE. The DBE who leases trucks from another DBE receives credit for the total value of the transportation services the lessee DBE provides on the contract.
5. The DBE may also lease trucks from a Non-DBE firm, including an owner-operator. The DBE who leases trucks from a Non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement. The DBE does not receive credit for the total value of the transportation services provided by the lessee, since these services are not provided by a DBE.
6. For the purposes of this paragraph G, a lease must indicate that the DBE has exclusive use of and control over the truck. This does not preclude the leased truck from working for others during the term of the lease with the consent of the DBE, so long as the lease gives the DBE absolute priority for use of the leased truck. Leased trucks must display the name and identification number of the DBE.

H. Bidders are encouraged to use services offered by financial institutions owned and controlled by DBEs.

2-1.03 SMALL BUSINESS ENTERPRISE GOAL

The Department has established an overall 25 percent small business participation goal. To determine if the goal is achieved, the Department is tracking small business participation on all contracts.

Contractors, subcontractors, suppliers, and service providers who qualify as small business are encouraged to apply for certification as a small business by submitting their application to:

Office of Small Business and DVBE Services
Department of General Services
707 Third Street
West Sacramento, CA 95605
(916) 375-4940 or (800) 559-5529

SECTION 3. AWARD AND EXECUTION OF CONTRACT

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

Requests for relief of bid and bid protests are to be delivered to the following address: Department of Transportation, MS 43, Attn: Office Engineer, 1727 30th Street, Sacramento, CA 95816 or by facsimile to the Office Engineer at (916) 227-6282.

The lowest bid will be determined on the basis of the TOTAL BASE BID + ADDITIVE ITEM if the aggregate total is within the funds available as set forth in the proposal. If the lowest bid (TOTAL BASE BID + ADDITIVE ITEM) exceeds the funds available, the lowest bid will be determined on the basis of the TOTAL BASE BID only.

The estimate for the base items and the additive item is \$5,580,000.

Attention is directed to "Contract Bonds" of these special provisions.

The Contractor will be notified at contract award if the additive item is added to the contract.

The award of the contract, if made, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DVBE participation or has demonstrated, to the satisfaction of the Department, good faith efforts to do so.

The contract shall be executed by the successful bidder and shall be returned, together with the contract bonds and the documents identified in Section 3-1.025, "Insurance Policies," of the Standard Specifications, to the Department so that it is received within 10 business days after the bidder has received the contract for execution. Failure to do so shall be just cause for forfeiture of the proposal guaranty. The executed contract documents shall be delivered to the following address: Department of Transportation MS 43, Attn: Office Engineer, 1727 30th Street, Sacramento, CA 95816.

A "CALTRANS BIDDER - DBE INFORMATION" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to collect data required under 49 CFR 26. Even if no DBE participation will be reported, the successful bidder must execute and return the form.

The bidder's "CALTRANS BIDDER - DBE INFORMATION" form should include the names, addresses and phone numbers of DBE firms that will participate, with a complete description of work or supplies to be provided by each, and the dollar value of each DBE transaction. When 100 percent of a contract item of work is not to be performed or furnished by a DBE, a description of the exact portion of that work to be performed or furnished by that DBE should be included in the DBE information, including the planned location of that work. A bidder certified as a DBE should describe the work it has committed to performing with its own forces as well as any other work that it has committed to be performed by DBE subcontractors, suppliers and trucking companies.

The bidder is encouraged to provide written confirmation from each DBE that the DBE is participating in the contract. A copy of a DBE's quote will serve as written confirmation that the DBE is participating in the contract. If a DBE is participating as a joint venture partner, the bidder is encouraged to submit a copy of the joint venture agreement.

The "CALTRANS BIDDER - DBE INFORMATION" form should be returned to the Department by the successful bidder with the executed contract, contract bonds and the documents identified in Section 3-1.025, "Insurance Policies," of the Standard Specifications.

A Small Business Participation Report will be included in the contract documents to be executed by the successful bidder. The purpose of this form is to collect small business participation data. Even if no small business participation is reported, the successful bidder must execute and return the form.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract, contract bonds and the documents identified in Section 3-1.025, "Insurance Policies," of the Standard Specifications. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 31 percent of payments due the Contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION, AND LIQUIDATED DAMAGES

The first working day is the fifteenth day after contract approval.

The work (except plant establishment work) shall be diligently prosecuted to completion before the expiration of **300 WORKING DAYS**.

The Contractor shall pay to the State of California the sum of \$4,200 per day for each day's delay in finishing the work (except plant establishment work) in excess of the number of working days specified above.

The work (including plant establishment) shall be diligently prosecuted to completion before the expiration of **550 WORKING DAYS**.

The Contractor shall pay to the State of California the sum of \$600 per day for each day's delay in completing the plant establishment work.

In no case will liquidated damages of more than \$4200.00 per day be assessed.

SECTION 5 GENERAL

SECTION 5-1. MISCELLANEOUS

5-1.01 PERFORMANCE OF UDBEs

UDBEs must perform work or supply materials as listed in the Caltrans Bidder - UDBE - Commitment form specified under Section 2, "Bidding," of these special provisions. Do not terminate a UDBE listed subcontractor for convenience and perform the work with your own forces or obtain materials from other sources without prior written authorization from the Department.

The Department grants authorization to use other forces or sources of materials for requests that show any of the following justifications:

1. Listed UDBE fails or refuses to execute a written contract based on plans and specifications for the project.
2. You stipulated that a bond is a condition of executing the subcontract and the listed UDBE fails to meet your bond requirements.
3. Work requires a contractor's license and listed UDBE does not have a valid license under Contractors License Law.
4. Listed UDBE fails or refuses to perform the work or furnish the listed materials.
5. Listed UDBE's work is unsatisfactory and not in compliance with the contract.
6. Listed UDBE delays or disrupts the progress of the work.
7. Listed UDBE becomes bankrupt or insolvent.

If a listed UDBE subcontractor is terminated, you must make good faith efforts to find another UDBE subcontractor to substitute for the original UDBE. The substitute UDBE must perform at least the same amount of work as the original UDBE under the contract to the extent needed to meet the UDBE goal.

The substitute UDBE must be certified as a DBE at the time of request for substitution.

The Department does not pay for work or material unless it is performed or supplied by the listed UDBE or an authorized substitute.

5-1.02 TRAINING

For the Federal training program, the number of trainees or apprentices is 8.

5-1.03 RETENTION EXCLUSION

The Department does not retain moneys from progress payments due to the Contractor for work performed (Pub Cont Code § 7202). The 3rd paragraph in Section 9-1.06, "Partial Payments," of the Standard Specifications does not apply.

5-1.04 CONTRACT BONDS

Attention is directed to Section 3-1.02, "Contract Bonds," of the Standard Specifications and these special provisions.

The payment bond shall be in a sum not less than one hundred percent of the TOTAL BASE BID and the performance bond shall be in a sum not less than fifty percent of the TOTAL BASE BID. The last paragraph of Section 3-1.02, "Contract Bonds," of the Standard Specifications shall apply to the additive item.

5-1.05 FORCE ACCOUNT PAYMENT

Payment for extra work at force account will be determined by either non-subcontracted or subcontracted force account payment unless otherwise specified.

Non-Subcontracted Force Account Payment

When extra work to be paid for on a force account basis is performed by the Contractor, compensation will be determined in accordance with Section 9-1.03, "Force Account Payment," of the Standard Specifications and these special provisions.

The second, third and fourth paragraphs of Section 9-1.03A, "Work Performed by Contractor," of the Standard Specifications shall not apply.

Attention is directed to "Time-Related Overhead" of these special provisions.

To the total of the direct costs for work performed on a force account basis, computed as provided in Section 9-1.03A(1), "Labor," Section 9-1.03A(2), "Materials," and Section 9-1.03A(3), "Equipment Rental," of the Standard Specifications, there will be added the following markups:

Cost	Percent Markup
Labor	28
Materials	10
Equipment Rental	10

The above markups shall be applied to work performed on a force account basis, regardless of whether the work revises the current contract completion date.

The above markups, together with payments made for time-related overhead pursuant to "Time-Related Overhead" of these special provisions, shall constitute full compensation for all overhead costs for work performed on a force account basis. These overhead costs shall be deemed to include all items of expense not specifically designated as cost or equipment rental in conformance with the provisions in Section 9-1.03A(1), "Labor," Section 9-1.03A(2), "Materials," and Section 9-1.03A(3), "Equipment Rental," of the Standard Specifications. The total payment made as provided above and in the first paragraph of Section 9-1.03A, "Work Performed by Contractor," of the Standard Specifications shall be deemed to be the actual cost of the work performed on a force account basis, and shall constitute full compensation therefor.

Full compensation for overhead costs for work performed on a force account basis, and for which no adjustment is made to the quantity for time-related overhead conforming to the provisions in "Time-Related Overhead" of these special provisions, shall be considered as included in the markups specified above, and no additional compensation will be allowed therefor.

Subcontracted Force Account Payment

When extra work to be paid for on a force account basis is performed by a subcontractor approved in conformance with the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, compensation will be determined in accordance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications.

5-1.06 PARTNERING

The State will promote the formation of a "Partnering" relationship with the Contractor in order to effectively complete the contract to the benefit of both parties. The purpose of this relationship is to maintain a cooperative communication and to mutually resolve conflicts at the lowest responsible management level.

The Contractor may request the formation of a "Partnering" relationship by submitting a request in writing to the Engineer after approval of the contract. If the Contractor's request for "Partnering" is approved by the Engineer, scheduling of a "Partnering Workshop," selecting the "Partnering" facilitator and workshop site, and other administrative details shall be as agreed to by both parties. If agreed to by the parties, additional "Partnering Workshops" will be conducted as needed throughout the life of the contract.

The costs involved in providing the "Partnering Workshop" facilitator and workshop site will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost in providing the "Partnering Workshop" facilitator and workshop site in conformance with the provisions in Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor one-half of that cost, except no markups will be allowed.

All other costs associated with "Partnering Workshops" will be borne separately by the party incurring the costs, such as wages and travel expenses, and no additional compensation will be allowed therefor.

The establishment of a "Partnering" relationship will not change or modify the terms and conditions of the contract and will not relieve either party of the legal requirements of the contract.

5-1.07 AREAS FOR CONTRACTOR'S USE

Attention is directed to the provisions in Section 7-1.19, "Rights in Land and Improvements," of the Standard Specifications and these special provisions.

The highway right of way shall be used only for purposes that are necessary to perform the required work. The Contractor shall not occupy the right of way, or allow others to occupy the right of way, for purposes which are not necessary to perform the required work.

No State-owned parcels adjacent to the right of way are available for the exclusive use of the Contractor within the contract limits. The Contractor shall secure, at the Contractor's own expense, areas required for plant sites, storage of equipment or materials, or for other purposes.

No area is available within the contract limits for the exclusive use of the Contractor. However, temporary storage of equipment and materials on State property may be arranged with the Engineer, subject to the prior demands of State maintenance forces and to other contract requirements. Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk, and the State shall not be held liable for damage to or loss of materials or equipment located within such areas.

5-1.08 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount set forth for the contract items of work hereinafter listed shall be deemed to be the maximum value of the contract item of work which will be recognized for progress payment purposes:

- A. Clearing and Grubbing \$6000.00
- B. Progress Schedule (Critical Path Method) \$2000.00

After acceptance of the contract pursuant to the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, payable for a contract item of work in excess of the maximum value for progress payment purposes hereinabove listed for the item, will be included for payment in the first estimate made after acceptance of the contract.

In determining the partial payments to be made to the Contractor, only the following listed materials will be considered for inclusion in the payment as materials furnished but not incorporated in the work:

- A. Pipe (Irrigation Systems)
- B. Fences and Gates
- C. Lighting Standards
- D. Luminaires

5-1.09 PROJECT INFORMATION

The information in this section has been compiled specifically for this project and is made available for bidders and Contractors. Other information referenced in the Standard Specifications and these special provisions do not appear in this section. The information is subject to the conditions and limitations set forth in Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," and Section 6-2, "Local Materials," of the Standard Specifications. Bidders and Contractors shall be responsible for knowing the procedures for obtaining information.

Information attached to the project plans is as follows:

- A. Log of Test Borings, two sheets.

Information included in the Information Handout provided to bidders and Contractors is as follows:

- A. Foundation Report
- B. Asbestos and Lead Based Paint/Material Survey, dated July 25, 2005.

Cross sections are not available for this project.

The District Office in which the work is situated is located at 111 Grand Avenue, Oakland, CA 94612.

Plans of the existing safety roadside rest area may be requested by fax from the Office of Structure Maintenance and Investigations, 1801 30th Street, Sacramento, CA, Fax (916) 227-8357.

Plans of the existing safety roadside rest area available to bidders and Contractors are reproductions of the original contract plans, with significant changes noted, and working drawings, and do not necessarily show normal construction tolerances and variances. Where dimensions of new construction required by this contract are dependent on the dimensions of the existing safety roadside rest area, the Contractor shall verify the controlling field dimensions and shall be responsible for adjusting dimensions of the work to fit existing conditions.

5-1.10 SOUND CONTROL REQUIREMENTS

Sound control shall conform to these special provisions.

The noise level from the Contractor's operations, between the hours of 9:00 p.m. and 6:00 a.m., shall not exceed 86 dBa (Lmax) at a distance of 50 feet, except for the following work:

- A. Remove Concrete from 9:00 p.m to 6:00 a.m., Monday through Friday.

The Contractor shall provide one "Type 1" sound level meter and one acoustic calibrator which will be used by the Department during the life of the contract. The Contractor shall provide training by a person trained in noise monitoring to one Department employee designated by the Engineer. The sound level meter shall be calibrated and certified by the manufacturer or other independent acoustical laboratory prior to delivery to the Department. The Contractor shall provide annual recalibration by the manufacturer or other independent acoustical laboratory. All equipment shall be capable of taking measurements using the A-weighting network and the "slow" response of the sound level meter. The measurement microphone shall be fitted with an appropriate windscreen. All equipment shall be returned to the Contractor at the acceptance of the contract. Equipment damaged by actions of the Department or the public shall be paid for as extra work as provided in Section 4-1.03D for the Standard Specifications.

Each internal combustion engine, used for any purpose on the job or related to the job, shall be equipped with a muffler of a type recommended by the manufacturer. No internal combustion engine shall be operated on the project without the muffler.

The noise level requirement shall apply to the equipment on the job or related to the job, including but not limited to trucks, transit mixers or transient equipment that may or may not be owned by the Contractor. The use of loud sound signals shall be avoided in favor of light warnings except those required by safety laws for the protection of personnel.

Full compensation for conforming to the requirements of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

5-1.11 HIGHWAY CONSTRUCTION EQUIPMENT

The first paragraph of Section 7-1.01D, "Vehicle Code," of the Standard Specifications shall not apply.

Pursuant to the authority contained in Section 591 of the Vehicle Code, the Department has determined that, within such areas as are within the limits of the project and are open to public traffic, the following requirements of the Vehicle Code will apply: the lighting requirements in Section 25803; the brake requirements in Chapter 3, Division 12; the splash apron requirements in Section 27600; and, when operated on completed or existing treated base, surfacing, pavement or structures, except as otherwise provided in Section 7-1.02, "Load Limitations," of the Standard Specifications, the weight limitation requirements contained in Division 15.

5-1.12 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD

This project lies within the boundaries of the San Francisco Bay, Region 2 Regional Water Quality Control Board (RWQCB).

The State Water Resources Control Board (SWRCB) has issued to the Department a permit that governs storm water and non-storm water discharges from the Department's properties, facilities, and activities. The Department's permit is entitled "Order No. 99 - 06 - DWQ, NPDES No. CAS000003, National Pollutant Discharge Elimination System (NPDES) Permit, Statewide Storm Water Permit and Waste Discharge Requirements (WDRs) for the State of California, Department of Transportation (Caltrans)." Copies of the Department's permit are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254, and may also be obtained at:

<http://www.swrcb.ca.gov/stormwtr/caltrans.html>

The Department's permit references and incorporates by reference the current statewide general permit issued by the SWRCB entitled "Order No. 99-08-DWQ, National Pollutant Discharge Elimination System (NPDES) General Permit No. CAS000002, Waste Discharge Requirements (WDRs) for Discharges of Storm Water Runoff Associated with Construction Activity" that regulates discharges of storm water and non-storm water from construction activities disturbing one acre or more of soil in a common plan of development. Sampling and analysis requirements as specified in SWRCB Resolution No. 2001-46 are added to the statewide general permit. Copies of the statewide permit and modifications thereto are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254 and may also be obtained at:

<http://www.swrcb.ca.gov/stormwtr/construction.html>

<http://www.swrcb.ca.gov>

The NPDES permits that regulate this project, as referenced above, are collectively referred to in this section as the "permits."

This project shall conform to the permits and modifications thereto. The Contractor shall maintain copies of the permits at the project site and shall make them available during construction.

The Contractor shall know and comply with provisions of Federal, State, and local regulations and requirements that govern the Contractor's operations and storm water and non-storm water discharges from the project site and areas of disturbance outside the project limits during construction. Attention is directed to Sections 7-1.01, "Laws to be Observed," 7-1.11, "Preservation of Property," and 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The Contractor shall be responsible for penalties assessed on the Contractor or the Department as a result of the Contractor's failure to comply with the provisions in "Water Pollution Control" of these special provisions or with the applicable provisions of the Federal, State, and local regulations and requirements.

Penalties as used in this section shall include fines, penalties, and damages, whether proposed, assessed, or levied against the Department or the Contractor, including those levied under the Federal Clean Water Act and the State Porter-Cologne Water Quality Control Act, by governmental agencies or as a result of citizen suits. Penalties shall also include payments made or costs incurred in settlement for alleged violations of applicable laws, regulations, or requirements. Costs incurred could include sums spent instead of penalties, in mitigation or to remediate or correct violations.

WITHHOLDS

The Department will withhold money due the Contractor, in an amount determined by the Department, up to and including the entire amount of penalties proposed, assessed, or levied as a result of the Contractor's violation of the permits, or Federal or State law, regulations, or requirements. Funds will be withheld by the Department until final disposition of penalties has been made. The Contractor shall remain liable for the full amount of penalties until they are finally resolved with the entity seeking the penalties.

If a regulatory agency identifies a failure to comply with the permits and modifications thereto, or other Federal, State, or local requirements, the Department will withhold money due the Contractor, subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to withhold funds from payments which may become due to the Contractor before acceptance of the contract. Funds withheld after acceptance of the contract will be made without prior notice to the Contractor.
- B. No withholds of additional amounts out of payments will be made if the amount to be withheld does not exceed the amount being withheld from partial payments in accordance with Section 9-1.06, "Partial Payments," of the Standard Specifications.
- C. If the Department has withheld funds, and it is subsequently determined that the State is not subject to the entire amount of the costs and liabilities assessed or proposed in connection with the matter for which the withhold was made, the Department will be liable for interest on the amount withheld for the period of the withhold. The interest rate payable shall be 6 percent per annum.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor, or otherwise access the project site or the Contractor's records pertaining to water pollution control work. The Contractor and the Department shall provide copies of correspondence, notices of violation, enforcement actions, or proposed fines by regulatory agencies to the requesting regulatory agency.

5-1.13 ENVIRONMENTALLY SENSITIVE AREA

An environmentally sensitive area (ESA) shall consist of an area within and near the limits of construction where access is prohibited or limited for the preservation of archeological site or existing vegetation, or protection of biological habitat as shown on the plans. The Engineer will determine the exact location of the boundaries of the ESA. No work shall be conducted within the ESA.

Attention is directed to Section 7—1.01 "Laws to be Observed," and Section 7—1.04 "Permits and Licenses," of the Standard Specifications regarding State and Federal regulations, permits, or agreements which pertain to an ESA.

Prior to beginning work, the boundaries of the ESA shall be clearly delineated by the placement of temporary fence (Type ESA) in conformance with the provisions in "Temporary Fence (Type ESA)" of these special provisions.

Vehicle access, storage or transport of materials or equipment, or other project related activities are prohibited within the boundaries of the ESA.

The Contractor shall mitigate damage or impacts to the ESA caused by the Contractor's operations, at the Contractor's expense. If the Engineer determines mitigation work will be performed by others, or if mitigation fees are assessed the Department, deductions from moneys due or to become due the Contractor will be made for the mitigation costs.

5-1.14 PRESERVATION OF PROPERTY

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications and these special provisions.

Existing trees, shrubs and other plants, that are not to be removed as shown on the plans or specified in these special provisions, and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree replacement shall be 24 inch box and the minimum size of shrub replacement shall be 15-gallon. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips. The chipped material shall be spread within the highway right of way at locations designated by the Engineer.

Replacement planting of injured or damaged trees, shrubs, and other plants shall be completed prior to the start of the plant establishment period. Replacement planting shall conform to the provisions in Section 20-4.05, "Planting," of the Standard Specifications.

5-1.15 DAMAGE REPAIR

Attention is directed to Section 7-1.16, "Contractor's Responsibility for the Work and Materials," and Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications and these special provisions.

When as a result of freezing conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacement work will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. A freezing condition, for the purpose of this specification, occurs when the temperature at or near the affected area has been officially recorded below 32° F and plants have been killed or damaged to the degree described above.

When, as a result of drought conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacements, after water has been restricted or stopped, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. Restriction or shutoff of available water shall not relieve the Contractor from performing other contract work. A drought condition occurs when the Department, or its supplier, restricts or stops delivery of water to the Contractor to the degree that plants have died or deteriorated as described above.

When the provisions in Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications are applicable, the provisions above for payment of costs for repair of damage due to rain, freezing conditions and drought shall not apply.

5-1.16 RELIEF FROM MAINTENANCE AND RESPONSIBILITY

The Contractor may be relieved of the duty of maintenance and protection for those items not directly connected with plant establishment work in conformance with the provisions in Section 7-1.15, "Relief From Maintenance and Responsibility," of the Standard Specifications. Water pollution control, maintain existing planted areas, maintain existing irrigation facilities, transplant trees, and transplant palm trees shall not be relieved of maintenance.

SECTION 6. (BLANK)

SECTION 7. (BLANK)

SECTION 8. MATERIALS

SECTION 8-1. MISCELLANEOUS

8-1.01 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS

The Department maintains the following list of Prequalified and Tested Signing and Delineation Materials. The Engineer shall not be precluded from sampling and testing products on the list of Prequalified and Tested Signing and Delineation Materials.

The manufacturer of products on the list of Prequalified and Tested Signing and Delineation Materials shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

For those categories of materials included on the list of Prequalified and Tested Signing and Delineation Materials, only those products shown within the listing may be used in the work. Other categories of products, not included on the list of Prequalified and Tested Signing and Delineation Materials, may be used in the work provided they conform to the requirements of the Standard Specifications.

Materials and products may be added to the list of Prequalified and Tested Signing and Delineation Materials if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

PAVEMENT MARKERS, PERMANENT TYPE

Retroreflective With Abrasion Resistant Surface (ARS)

1. Apex, Model 921AR (4" x 4")
2. Ennis Paint, Models C88 (4" x 4"), 911 (4" x 4") and 953 (2.75" x 4.5")

3. Ray-O-Lite, Model "AA" ARS (4" x 4")
4. 3M Series 290 (3.5" x 4")
5. 3M Series 290 PSA, with pressure sensitive adhesive pad (3.5" x 4")

Retroreflective With Abrasion Resistant Surface (ARS)

(for recessed applications only)

1. Ennis Paint, Model 948 (2.3" x 4.7")
2. Ennis Paint, Model 944SB (2" x 4")*
3. Ray-O-Lite, Model 2002 (2" x 4.6")
4. Ray-O-Lite, Model 2004 ARS (2" x 4")*

*For use only in 4.5 inch wide (older) recessed slots

Non-Reflective, 4-inch Round

1. Apex Universal (Ceramic)
2. Apex Universal, Models 929 (ABS) and 929PP (Polypropylene)
3. Glowlite, Inc. (Ceramic)
4. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
5. Interstate Sales, "Diamond Back" (Polypropylene)
6. Novabrite Models Cdot (White) Cdot-y (Yellow), Ceramic
7. Novabrite Models Pdot-w (White) Pdot-y (Yellow), Polypropylene
8. Three D Traffic Works TD10000 (ABS), TD10500 (Polypropylene)

PAVEMENT MARKERS, TEMPORARY TYPE

Temporary Markers For Long Term Day/Night Use (6 months or less)

1. Vega Molded Products "Temporary Road Marker" (3" x 4")

Temporary Markers For Short Term Day/Night Use (14 days or less)

(For seal coat or chip seal applications, clear protective covers are required)

1. Apex Universal, Model 932
2. Filtrona Extrusion, Models T.O.M., T.R.P.M., and "HH" (High Heat)
3. Hi-Way Safety, Inc., Model 1280/1281
4. Glowlite, Inc., Model 932

STRIPING AND PAVEMENT MARKING MATERIAL

Permanent Traffic Striping and Pavement Marking Tape

1. Advanced Traffic Marking, Series 300 and 400
2. Brite-Line, Series 1000
3. Brite-Line, "DeltaLine XRP"
4. Swarco Industries, "Director 35" (For transverse application only)
5. Swarco Industries, "Director 60"
6. 3M, "Stamark" Series 380 and 5730
7. 3M, "Stamark" Series 420 (For transverse application only)

Temporary (Removable) Striping and Pavement Marking Tape (6 months or less)

1. Advanced Traffic Marking, Series 200
2. Brite-Line, Series 100
3. Garlock Rubber Technologies, Series 2000
4. P.B. Laminations, Aztec, Grade 102
5. Swarco Industries, "Director-2"
6. Trelleborg Industries, R140 Series
7. 3M Series 620 "CR", and Series A750
8. 3M Series A145, Removable Black Line Mask
(Black Tape: for use only on Asphalt Concrete Surfaces)
9. Advanced Traffic Marking Black "Hide-A-Line"
(Black Tape: for use only on Asphalt Concrete Surfaces)
10. Brite-Line "BTR" Black Removable Tape

(Black Tape: for use only on Asphalt Concrete Surfaces)

11. Trelleborg Industries, RB-140

(Black Tape: for use only on Asphalt Concrete Surfaces)

Preformed Thermoplastic (Heated in place)

1. Flint Trading Inc., "Hot Tape"
2. Flint Trading Inc., "Premark Plus"
3. Ennis Paint Inc., "Flametape"

Ceramic Surfacing Laminate, 6" x 6"

1. Highway Ceramics, Inc.

CLASS 1 DELINEATORS

One Piece Driveable Flexible Type, 66-inch

1. Filtrona Extrusion, "Flexi-Guide Models 400 and 566"
2. Carsonite, Curve-Flex CFRM-400
3. Carsonite, Roadmarker CRM-375
4. FlexStake, Model 654 TM
5. GreenLine Model CGD1-66

Special Use Type, 66-inch

1. Filtrona Extrusion, Model FG 560 (with 18-inch U-Channel base)
2. Carsonite, "Survivor" (with 18-inch U-Channel base)
3. Carsonite, Roadmarker CRM-375 (with 18-inch U-Channel base)
4. FlexStake, Model 604
5. GreenLine Model CGD (with 18-inch U-Channel base)
6. Impact Recovery Model D36, with #105 Driveable Base
7. Safe-Hit with 8-inch pavement anchor (SH248-GP1)
8. Safe-Hit with 15-inch soil anchor (SH248-GP2) and with 18-inch soil anchor (SH248-GP3)

Surface Mount Type, 48-inch

1. Bent Manufacturing Company, Masterflex Model MF-180EX-48
2. Carsonite, "Channelizer"
3. FlexStake, Models 704, 754 TM, and EB4
4. Impact Recovery Model D48, with #101 Fixed (Surface-Mount) Base
5. Three D Traffic Works "Channelflex" ID No. 522248W

CHANNELIZERS

Surface Mount Type, 36-inch

1. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
2. Filtrona Extrusion, Flexi-Guide Models FG300PE, FG300UR, and FG300EFX
3. Carsonite, "Super Duck" (Round SDR-336)
4. Carsonite, Model SDCF03601MB "Channelizer"
5. FlexStake, Models 703, 753 TM, and EB3
6. GreenLine, Model SMD-36
7. Hi-way Safety, Inc. "Channel Guide Channelizer" Model CGC36
8. Impact Recovery Model D36, with #101 Fixed (Surface-Mount) Base
9. Safe-Hit, Guide Post, Model SH236SMA
10. Three D Traffic Works "Boomerang" ID No. 522053W

Lane Separation System

1. Filtrona Extrusion, "Flexi-Guide (FG) 300 Curb System"
2. Qwick Kurb, "Klemmfix Guide System"
3. Recycled Technology, Inc. "Safe-Lane System"
4. Dura-Curb System

CONICAL DELINEATORS, 42-inch

(For 28-inch Traffic Cones, see Standard Specifications)

1. Bent Manufacturing Company "T-Top"
2. Plastic Safety Systems "Navigator-42"
3. Traffix Devices "Grabber"
4. Three D Traffic Works "Ringtop" TD7000, ID No. 742143
5. Three D Traffic Works, TD7500

OBJECT MARKERS

Type "K", 18-inch

1. Filtrona Extrusion, Model FG318PE
2. Carsonite, Model SMD 615
3. FlexStake, Model 701 KM
4. Safe-Hit, Model SH718SMA

Type "K-4" / "Q" Object Markers, 24-inch

1. Bent Manufacturing "Masterflex" Model MF-360-24
2. Filtrona Extrusion, Model FG324PE
3. Carsonite, "Channelizer"
4. FlexStake, Model 701KM
5. Safe-Hit, Models SH824SMA_WA and SH824GP3_WA
6. The Line Connection, Model DP21-4Q
7. Three D Traffic Works ID No. 531702W and TD 5200
8. Three D Traffic Works ID No. 520896W

CONCRETE BARRIER MARKERS AND TEMPORARY RAILING (TYPE K) REFLECTORS

Impactable Type

1. ARTUK, "FB"
2. Filtrona Extrusion, Models PCBM-12 and PCBM-T12
3. Duraflex Corp., "Flexx 2020" and "Electriflexx"
4. Hi-Way Safety, Inc., Model GMKRM100
5. Plastic Safety Systems "BAM" Models OM-BARR and OM-BWAR
6. Three D Traffic Works "Roadguide" Model TD 9304

Non-Impactable Type

1. ARTUK, JD Series
2. Plastic Safety Systems "BAM" Models OM-BITARW and OM-BITARA
3. Vega Molded Products, Models GBM and JD
4. Plastic Vacuum Forming, "Cap-It C400"

METAL BEAM GUARD RAIL POST MARKERS

(For use to the left of traffic)

1. Filtrona Extrusion, "Mini" (3" x 10")
2. Creative Building Products, "Dura-Bull, Model 11201"
3. Duraflex Corp., "Railrider"
4. Plastic Vacuum Forming, "Cap-It C300"

CONCRETE BARRIER DELINEATORS, 16-inch

(For use to the right of traffic)

1. Filtrona Extrusion, Model PCBM T-16
2. Safe-Hit, Model SH216RBM

CONCRETE BARRIER-MOUNTED MINI-DRUM (10" x 14" x 22")

1. Stinson Equipment Company "SaddleMarker"

GUARD RAILING DELINEATOR

(Place top of reflective element at 48 inches above plane of roadway)

Wood Post Type, 27-inch

1. Filtrona Extrusion, FG 427 and FG 527
2. Carsonite, Model 427
3. FlexStake, Model 102 GR
4. GreenLine GRD 27
5. Safe-Hit, Model SH227GRD
6. Three D Traffic Works "Guardflex" TD9100
7. New Directions Mfg, NDM27

Steel Post Type

1. Carsonite, Model CFGR-327 with CFGRBK300 Mounting Bracket

RETROREFLECTIVE SHEETING

Channelizers, Barrier Markers, and Delineators

1. Avery Dennison T-6500 Series (For rigid substrate devices only)
2. Avery Dennison WR-7100 Series
3. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
4. Reflexite, PC-1000 Metalized Polycarbonate
5. Reflexite, AC-1000 Acrylic
6. Reflexite, AP-1000 Metalized Polyester
7. Reflexite, Conformalight, AR-1000 Abrasion Resistant Coating
8. 3M, High Intensity

Traffic Cones, 4-inch and 6-inch Sleeves

1. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
2. Reflexite, Vinyl, "TR" (Semi-transparent) or "Conformalight"
3. 3M Series 3840
4. Avery Dennison S-9000C

Drums

1. Avery Dennison WR-6100
2. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
3. Reflexite, "Conformalight", "Super High Intensity" or "High Impact Drum Sheeting"
4. 3M Series 3810

Barricades: Type I, Medium-Intensity (Typically Enclosed Lens, Glass-Bead Element)

1. Nippon Carbide Industries, CN8117
2. Avery Dennison, W 1100 series
3. 3M Series CW 44

Barricades: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)

1. Avery Dennison, W-2100 Series

Signs: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)

1. Avery Dennison, T-2500 Series
2. Nippon Carbide Industries, Nikkalite 18000

Signs: Type III, High-Intensity (Typically Encapsulated Glass-Bead Element)

1. Avery Dennison, T-5500A and T-6500 Series
2. Nippon Carbide Industries, Nikkalite Brand Ultralite Grade II
3. 3M 3870 and 3930 Series

Signs: Type IV, High-Intensity (Typically Unmetallized Microprismatic Element)

1. Avery Dennison, T-6500 Series
2. Nippon Carbide Industries, Crystal Grade, 94000 Series
3. Nippon Carbide Industries, Model No. 94847 Fluorescent Orange
4. 3M Series 3930 and Series 3924S

Signs: Type VI, Elastomeric (Roll-Up) High-Intensity, without Adhesive

1. Avery Dennison, WU-6014
2. Novabrite LLC, "Econobrite"
3. Reflexite "Vinyl"
4. Reflexite "SuperBright"
5. Reflexite "Marathon"
6. 3M Series RS20

Signs: Type VII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)

1. 3M Series 3924S, Fluorescent Orange
2. 3M LDP Series 3970

Signs: Type VIII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)

1. Avery Dennison, T-7500 Series
2. Avery Dennison, T-7511 Fluorescent Yellow
3. Avery Dennison, T-7513 Fluorescent Yellow Green
4. Avery Dennison, W-7514 Fluorescent Orange
5. Nippon Carbide Industries, Nikkalite Crystal Grade Series 92800
6. Nippon Carbide Industries, Nikkalite Crystal Grade Model 92847 Fluorescent Orange

Signs: Type IX, Very-High-Intensity (Typically Unmetallized Microprismatic Element)

1. 3M VIP Series 3981 Diamond Grade Fluorescent Yellow
2. 3M VIP Series 3983 Diamond Grade Fluorescent Yellow/Green
3. 3M VIP Series 3990 Diamond Grade
4. Avery Dennison T-9500 Series
5. Avery Dennison, T9513, Fluorescent Yellow Green
6. Avery Dennison, W9514, Fluorescent Orange

SPECIALTY SIGNS

1. Reflexite "Endurance" Work Zone Sign (with Semi-Rigid Plastic Substrate)

ALTERNATIVE SIGN SUBSTRATES

Fiberglass Reinforced Plastic (FRP) and Expanded Foam PVC

1. Fiber-Brite (FRP)
2. Sequentia, "Polyplate" (FRP)
3. Intoplast Group "InteCel" (0.5 inch for Post-Mounted CZ Signs, 48-inch or less)(PVC)

Aluminum Composite, Temporary Construction Signs Only

1. Alcan Composites "Dibond Material, 80 mils"
2. Mitsubishi Chemical America, Alpolic 350

8-1.02 STATE-FURNISHED MATERIALS

Attention is directed to Section 6-1.02, "State-Furnished Materials," of the Standard Specifications and these special provisions.

The following materials will be furnished to the Contractor:

- A Concrete Site Furnishings:

1. Water Post
2. Trash Receptacle
3. Recycling Container
4. Benches
5. Picnic Tables
6. Metal Plaques/Sign Monument and Pedestals

8-1.03 ENGINEERING FABRICS

Engineering fabrics shall conform to the provisions in Section 88, "Engineering Fabrics," of the Standard Specifications.

SECTION 8-2. CONCRETE

8-2.01 PORTLAND CEMENT CONCRETE

Portland cement concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

The Department maintains a list of sources of fine and coarse aggregate that have been approved for use with a reduced amount of supplementary cementitious material in the total amount of cementitious material to be used. A source of aggregate will be considered for addition to the approved list if the producer of the aggregate submits to the Transportation Laboratory certified test results from a qualified testing laboratory that verify the aggregate complies with the requirements. Before the testing starts, the aggregate test shall be registered with the Department. A registration number can be obtained by calling (916) 227-7228. The registration number shall be used as the identification for the aggregate sample in correspondence with the Department. Upon request, a split of the tested sample shall be provided to the Department. Approval of aggregate will depend upon compliance with the specifications, based on the certified test results submitted, together with any replicate testing the Department may elect to perform. Approval will expire 3 years from the date the most recent registered and evaluated sample was collected from the aggregate source.

Qualified testing laboratories shall conform to the following requirements:

1. Laboratories performing ASTM Designation: C 1293 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Concrete Proficiency Sample Program and shall have received a score of 3 or better on each test of the previous 2 sets of concrete samples.
2. Laboratories performing ASTM Designation: C 1260 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Pozzolan Proficiency Sample Program and shall have received a score of 3 or better on the shrinkage and soundness tests of the previous 2 sets of pozzolan samples.

Aggregates on the list shall conform to one of the following requirements:

1. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1293, the average expansion at one year shall be less than or equal to 0.040 percent; or
2. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1260, the average of the expansion at 16 days shall be less than or equal to 0.15 percent.

If the aggregates used in the concrete are on the Department's list, the minimum amount of supplementary cementitious material shall conform to the following:

1. If fly ash or natural pozzolan conforming to the provisions in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials," of the Standard Specifications is used, the minimum amount of supplementary cementitious material shall be 15 percent by weight of the total cementitious material; or
2. If silica fume conforming to the provisions in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials," of the Standard Specifications is used, the minimum amount of supplementary cementitious material shall be 7 percent by weight of the total cementitious material.

The limitation on tricalcium silicate (C₃S) content in Type II cement specified in Section 90-2.01A, "Cement," of the Standard Specifications shall not apply.

SECTION 8-3. WELDING

8-3.01 WELDING

GENERAL

Flux cored welding electrodes conforming to the requirements of AWS A5.20 E6XT-4 or E7XT-4 shall not be used to perform welding for this project.

Wherever reference is made to the following AWS welding codes in the Standard Specifications, on the plans, or in these special provisions, the year of adoption for these codes shall be as listed:

AWS Code	Year of Adoption
D1.1	2006
D1.4	2005
D1.5	2002
D1.6	1999

Requirements of the AWS welding codes shall apply unless otherwise specified in the Standard Specifications, on the plans, or in these special provisions. Wherever the abbreviation AWS is used, it shall be equivalent to the abbreviations ANSI/AWS or AASHTO/AWS.

Section 6.1.1.1 of AWS D1.5 is replaced with the following:

Quality Control (QC) shall be the responsibility of the Contractor. As a minimum, the Contractor shall perform inspection and testing of each weld joint prior to welding, during welding, and after welding as specified in this section and as necessary to ensure that materials and workmanship conform to the requirements of the contract documents.

Unless otherwise specified, Sections 6.1.3 through 6.1.4.3 of AWS D1.1, Section 7.1.2 of AWS D1.4, and Sections 6.1.1.2 through 6.1.3.3 of AWS D1.5 are replaced with the following:

The QC Inspector shall be the duly designated person who acts for and on behalf of the Contractor for inspection, testing, and quality related matters for all welding.

Quality Assurance (QA) is the prerogative of the Engineer. The QA Inspector is the duly designated person who acts for and on behalf of the Engineer.

The QC Inspector shall be responsible for quality control acceptance or rejection of materials and workmanship, and shall be currently certified as an AWS Certified Welding Inspector (CWI) in conformance with the requirements in AWS QC1, "Standard for AWS Certification of Welding Inspectors."

The QC Inspector may be assisted by an Assistant QC Inspector provided that this individual is currently certified as an AWS Certified Associate Welding Inspector (CAWI) in conformance with the requirements in AWS QC1, "Standard for AWS Certification of Welding Inspectors." The Assistant QC Inspector may perform inspection under the direct supervision of the QC Inspector provided the assistant is always within visible and audible range of the QC Inspector. The QC Inspector shall be responsible for signing all reports and for determining if welded materials conform to workmanship and acceptance criteria. The ratio of QC Assistants to QC Inspectors shall not exceed 5 to 1.

When the term "Inspector" is used without further qualification, it shall refer to the QC Inspector.

When any work is welded in conformance with the provisions in Section 75, "Miscellaneous Metal," of the Standard Specifications, not including Section 75-1.035, "Bridge Joint Restrainer Units," of the Standard Specifications, Section 6.1.4 of AWS D1.1 is replaced with the following:

The QC Inspector shall be responsible for quality control acceptance or rejection of materials and workmanship and shall be currently certified as an AWS CWI in conformance with the requirements in AWS QC1, "Standard for AWS Certification of Welding Inspectors," or as a Welding Inspector Specialist (WIS) in conformance with the requirements in AWS B5.2, "Specification for the Qualification of Welding Inspector Specialists and Welding Inspector Assistants."

Section 6.14.6, "Personnel Qualification," of AWS D1.1, Section 7.8, "Personnel Qualification," of AWS D1.4, and Section 6.1.3.4, "Personnel Qualification," of AWS D1.5 are replaced with the following:

Personnel performing nondestructive testing (NDT) shall be qualified and certified in conformance with the requirements of the American Society for Nondestructive Testing (ASNT) Recommended Practice No. SNT-TC-1A and the Written Practice of the NDT firm. The Written Practice of the NDT firm shall meet or exceed the guidelines of the ASNT Recommended Practice No. SNT-TC-1A. Individuals who perform NDT, review the results, and prepare the written reports shall be either:

- A. Certified NDT Level II technicians, or;
- B. Level III technicians who hold a current ASNT Level III certificate in that discipline and are authorized and certified to perform the work of Level II technicians.

Section 6.5.4 of AWS D1.5 is replaced with the following:

The QC Inspector shall inspect and approve each joint preparation, assembly practice, welding technique, joint fit-up, and the performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved Welding Procedure Specification (WPS) are met. The QC Inspector shall examine the work to make certain that it meets the requirements of Sections 3 and 6.26. The size and contour of all welds shall be measured using suitable gages. Visual inspection for cracks in welds and base metal, and for other discontinuities shall be aided by strong light, magnifiers, or such other devices as may be helpful. Acceptance criteria different from those specified in this code may be used when approved by the Engineer.

Section 6.6.5, "Nonspecified NDT Other than Visual," of AWS D1.1, Section 7.6.5 of AWS D1.4 and Section 6.6.5 of AWS D1.5 shall not apply.

For any welding, the Engineer may direct the Contractor to perform NDT that is in addition to the visual inspection or NDT specified in the AWS or other specified welding codes, in the Standard Specifications, or in these special provisions. Except as provided for in these special provisions, additional NDT required by the Engineer, and associated repair work, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. Prior to release of welded material by the Engineer, if testing by NDT methods other than those originally specified discloses an attempt to defraud or reveals a gross nonconformance, all costs associated with the repair of the deficient area, including NDT of the weld and of the repair, and any delays caused by the repair, shall be at the Contractor's expense. A gross nonconformance is defined as the sum of planar type rejectable indications in more than 20 percent of the tested length.

When less than 100 percent of NDT is specified for any weld, it is expected that the entire length of weld meet the specified acceptance-rejection criteria. Should any welding deficiencies be discovered by additional NDT directed or performed by the Engineer that utilizes the same NDT method as that originally specified, all costs associated with the repair of the deficient area, including NDT of the weld and of the weld repair, and any delays caused by the repair, shall be at the Contractor's expense.

Repair work to correct welding deficiencies discovered by visual inspection directed or performed by the Engineer, and any associated delays or expenses caused to the Contractor by performing these repairs, shall be at the Contractor's expense.

The Engineer shall have the authority to verify the qualifications or certifications of any welder, QC Inspector, or NDT personnel to specified levels by retests or other means approved by the Engineer.

Inspection and approval of all joint preparations, assembly practices, joint fit-ups, welding techniques, and the performance of each welder, welding operator, and tack welder shall be documented by the QC Inspector on a daily basis for each day welding is performed. For each inspection, including fit-up, Welding Procedure Specification (WPS) verification, and final weld inspection, the QC Inspector shall confirm and document compliance with the requirements of the AWS or other specified code criteria and the requirements of these special provisions on all welded joints before welding, during welding, and after the completion of each weld.

In addition to the requirements specified in the applicable code, the period of effectiveness for a welder's or welding operator's qualification shall be a maximum of 3 years for the same weld process, welding position, and weld type. If welding will be performed without gas shielding, then qualification shall also be without gas shielding. Excluding welding of fracture critical members, a valid qualification at the beginning of work on a contract will be acceptable for the entire period of the contract, as long as the welder's or welding operator's work remains satisfactory.

In addition to the requirements of AWS D1.1, welding procedures qualification for work welded in conformance with that code shall conform to the following requirements:

- A. The travel speed, amperage, and voltage values that are used for tests conducted per AWS D1.1, Section 4.1.1, shall be consistent for each pass in a weld joint and shall in no case vary by more than ± 10 percent for travel speed, ± 10 percent for amperage, and ± 7 percent for voltage as measured from a predetermined target value or average within each weld pass. The travel speed shall in no case vary by more than ± 15 percent when using submerged arc welding.

- B. When a nonstandard weld joint is to be made using a combination of WPSs, a single test may be conducted combining the WPSs to be used in production, provided the essential variables, including weld bead placement, of each process are limited to those established in Table 4.5.

In addition to the requirements of AWS D1.5, Section 5.12 or 5.13, welding procedures qualification for work welded in conformance with that code shall conform to the following requirements:

- A. Unless considered prequalified, fillet welds shall be qualified in each position. The fillet weld soundness test shall be conducted using the essential variables of the WPS as established by the Procedure Qualification Record (PQR).
- B. For qualification of joints that do not conform to Figures 2.4 and 2.5 of AWS D1.5, a minimum of two WPS qualification tests are required. The tests shall be conducted using both Figure 5.1 and Figure 5.3. The test conforming to Figure 5.1 shall be conducted in conformance with AWS D1.5, Section 5.12 or 5.13. The test conforming to Figure 5.3 shall be conducted using the welding electrical parameters that were established for the test conducted conforming to Figure 5.1. The ranges of welding electrical parameters established during welding per Figure 5.1 in conformance with AWS D1.5, Section 5.12, shall be further restricted according to the limits in Table 5.3 during welding per Figure 5.3.
- C. Multiple zones within a weld joint may be qualified. The travel speed, amperage, and voltage values that are used for tests conducted per AWS D1.5 Section 5.13 shall be consistent for each pass in a weld joint, and shall in no case vary by more than ± 10 percent for travel speed, ± 10 percent for amperage, and ± 7 percent for voltage as measured from a predetermined target value or average within each weld pass or zone. The travel speed shall in no case vary by more than ± 15 percent when using submerged arc welding.
- D. For a WPS qualified in conformance with AWS D1.5 Section 5.13, the values to be used for calculating ranges for current and voltage shall be based on the average of all weld passes made in the test. Heat input shall be calculated using the average of current and voltage of all weld passes made in the test for a WPS qualified in conformance with Section 5.12 or 5.13.
- E. Macroetch tests are required for WPS qualification tests, and acceptance shall be per AWS D1.5 Section 5.19.3.
- F. When a nonstandard weld joint is to be made using a combination of WPSs, a test conforming to Figure 5.3 may be conducted combining the WPSs to be used in production, provided the essential variables, including weld bead placement, of each process are limited to those established in Table 5.3.
- G. Prior to preparing mechanical test specimens, the PQR welds shall be inspected by visual and radiographic tests. Backing bar shall be 3 inches in width and shall remain in place during NDT testing. Results of the visual and radiographic tests shall comply with AWS D1.5 Section 6.26.2, excluding Section 6.26.2.2. Test plates that do not comply with both tests shall not be used.

WELDING QUALITY CONTROL

Welding quality control shall conform to the requirements in the AWS or other specified welding codes, the Standard Specifications, and these special provisions.

Unless otherwise specified, welding quality control shall apply when any work is welded in conformance with the provisions in Section 49, "Piling," Section 52, "Reinforcement," or Section 55, "Steel Structures," of the Standard Specifications.

All welding will require inspection by the Engineer. The Contractor shall request inspection at least 3 working days prior to the beginning of welding for locations within California and 5 working days for locations outside of California. The Contractor shall request inspection at:

<http://www.dot.ca.gov/hq/esc/Translab/smbforms.htm>

Continuous inspection shall be provided when any welding is being performed. Continuous inspection, as a minimum, shall include having a QC Inspector within such close proximity of all welders or welding operators so that inspections by the QC Inspector of each welding operation at each welding location does not lapse for a period exceeding 30 minutes.

When joint weld details that are not prequalified to the details of Section 3 of AWS D1.1 or to the details of Figure 2.4 or 2.5 of AWS D1.5 are proposed for use in the work, the joint details, their intended locations, and the proposed welding parameters and essential variables, shall be approved by the Engineer. The Contractor shall allow the Engineer 2 weeks to complete the review of the proposed joint detail locations. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications. Upon approval of the proposed joint detail locations and qualification of the proposed joint details, welders and welding operators using these details shall perform a qualification test plate using the WPS variables and the joint detail

to be used in production. The test plate shall have the maximum thickness to be used in production and a minimum length of 18 inches. The test plate shall be mechanically and radiographically tested. Mechanical and radiographic testing and acceptance criteria shall be as specified in the applicable AWS codes.

The Engineer will witness all qualification tests for WPSs that were not previously approved by the Department. Unless otherwise specified, an approved independent third party will witness the qualification tests for welders or welding operators. The independent third party shall be a current CWI and shall not be an employee of the contractor performing the welding. The Contractor shall allow the Engineer 2 weeks to review the qualifications and copy of the current certification of the independent third party. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications. The Contractor shall notify the Engineer one week prior to performing any qualification tests. Witnessing of qualification tests by the Engineer shall not constitute approval of the intended joint locations, welding parameters, or essential variables.

The Contractor shall designate in writing a welding Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for the quality of welding, including materials and workmanship, performed by the Contractor and subcontractors.

The QCM shall be the sole individual responsible to the Contractor for submitting, receiving, reviewing, and approving all correspondence, required submittals, and reports to and from the Engineer. The QCM shall be a registered professional engineer or shall be currently certified as a CWI.

Unless the QCM is hired by a subcontractor providing only QC services, the QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

Welding inspection personnel or NDT firms to be used in the work shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project, except for the following conditions:

- A. The work is welded in conformance with AWS D1.5 and is performed at a permanent fabrication or manufacturing facility that is certified under the AISC Quality Certification Program, Category Cbr, Major Steel Bridges and Fracture Critical endorsement F, when applicable.
- B. The welding is performed on pipe pile material at a permanent pipe manufacturing facility authorized to apply the American Petroleum Institute (API) monogram for API 5L pipe.

For welding performed at such facilities, the inspection personnel or NDT firms may be employed or compensated by the facility performing the welding provided the facility maintains a QC program that is independent from production.

Prior to submitting the Welding Quality Control Plan (WQCP) required herein, a prewelding meeting between the Engineer, the Contractor's QCM, and a representative from each entity performing welding or inspection for this project, shall be held to discuss the requirements for the WQCP.

The Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 2 copies of a separate WQCP for each subcontractor or supplier for each item of work for which welding is to be performed.

The Contractor shall allow the Engineer 2 weeks to review the WQCP submittal after a complete plan has been received. No welding shall be performed until the WQCP is approved in writing by the Engineer. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

An amended WQCP or any addendum to the approved WQCP shall be submitted to, and approved in writing by the Engineer, for proposed revisions to the approved WQCP. An amended WQCP or addendum will be required for revisions to the WQCP, including but not limited to a revised WPS; additional welders; changes in NDT firms, QC, or NDT personnel or procedures; or updated systems for tracking and identifying welds. The Engineer shall have one week to complete the review of the amended WQCP or addendum. Work affected by the proposed revisions shall not be performed until the amended WQCP or addendum has been approved. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Information regarding the contents, format, and organization of a WQCP, is available at the Transportation Laboratory and at:

<http://www.dot.ca.gov/hq/esc/Translab/smbresources.htm>

After final approval of the WQCP, amended WQCP, or addendum, the Contractor shall submit 7 copies to the Engineer of the approved documents. A copy of the Engineer approved document shall be available at each location where welding is to be performed.

A daily production log for welding shall be kept for each day that welding is performed. The log shall clearly indicate the locations of all welding. The log shall include the welders' names, amount of welding performed, any problems or deficiencies discovered, and any testing or repair work performed, at each location. The daily report from each QC Inspector shall also be included in the log.

The following items shall be included in a Welding Report that is to be submitted to the Engineer within 2 weeks following the performance of any welding:

- A. A daily production log.
- B. Reports of all visual weld inspections and NDT.
- C. Radiographs and radiographic reports, and other required NDT reports.
- D. A summary of welding and NDT activities that occurred during the reporting period.
- E. Reports of each application of heat straightening.
- F. A summarized log listing the rejected lengths of weld by welder, position, process, joint configuration, and piece number.
- G. Documentation that the Contractor has evaluated all radiographs and other nondestructive tests and corrected all rejectable deficiencies, and that all repaired welds have been reexamined using the required NDT and found acceptable.

The following information shall be clearly written on the outside of radiographic envelopes: name of the QCM, name of the nondestructive testing firm, name of the radiographer, date, contract number, complete part description, and all included weld numbers, report numbers, and station markers or views, as detailed in the WQCP. In addition, all interleaves shall have clearly written on them the part description and all included weld numbers and station markers or views, as detailed in the WQCP. A maximum of 2 pieces of film shall be used for each interleave.

Reports of all visual inspections and NDT shall be signed by the inspector or technician and submitted daily to the QCM for review and signature prior to submittal to the Engineer. Corresponding names shall be clearly printed or typewritten next to all signatures. Reports of all NDT, whether specified, additional, or informational, performed by the Contractor shall be submitted to the Engineer.

The Engineer will review the Welding Report to determine if the Contractor is in conformance with the WQCP. Unless otherwise specified, the Engineer shall be allowed 2 weeks to review the report and respond in writing after the complete Welding Report has been received. Prior to receiving notification from the Engineer of the Contractor's conformance with the WQCP, the Contractor may encase in concrete or cover welds for which the Welding Report has been submitted. However, should the Contractor elect to encase or cover those welds prior to receiving notification from the Engineer, it is expressly understood that the Contractor shall not be relieved of the responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase or cover welds pending notification by the Engineer, and in the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

In addition to the requirements in AWS D1.1 and AWS D1.5, second-time excavations of welds or base metal to repair unacceptable discontinuities, regardless of NDT method, and all repairs of cracks require prior approval of the Engineer.

The Engineer shall be notified immediately in writing when welding problems, deficiencies, base metal repairs, or any other type of repairs not submitted in the WQCP are discovered, and also of the proposed repair procedures to correct them. For requests to perform second-time repairs or repairs of cracks, the Contractor shall include an engineering evaluation of the proposed repair. The engineering evaluation, at a minimum, shall address the following:

- A. What is causing each defect?
- B. Why the repair will not degrade the material properties?
- C. What steps are being taken to prevent similar defects from happening again?

The Contractor shall allow the Engineer one week to review these procedures. No remedial work shall begin until the repair procedures are approved in writing by the Engineer. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The QCM shall sign and furnish to the Engineer, a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each item of work for which welding was performed. The certificate shall state that all of the materials and workmanship incorporated in the work, and all required tests and inspections of this work, have been performed in conformance with the details shown on the plans, the Standard Specifications, and these special provisions.

PAYMENT

Full compensation for conforming to the requirements of "Welding" shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

SECTION 9. (BLANK)

SECTION 10. CONSTRUCTION DETAILS

SECTION 10-1. GENERAL

10-1.01 ORDER OF WORK

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

Attention is directed to "Miscellaneous Concrete Construction" of these special provisions regarding constructing a 2' x 2' test panel prior to constructing curb ramps with detectable warning surfaces.

Attention is directed to Section 12-3.03 "Architectural Surface (Textured Concrete)" of these special provisions regarding constructing a 4' x 4' test panel prior to constructing random cedar board texture.

Temporary railing (Type K) and temporary crash cushions shall be secured in place prior to commencing work for which the temporary railing and crash cushions are required.

Attention is directed to "Environmentally Sensitive Area" and "Temporary Fence (Type ESA)" of these special provisions. Prior to beginning work, the boundaries of the Environmentally Sensitive Areas (ESA) shall be clearly delineated in the field. The boundaries shall be delineated by the installation of temporary fence (Type ESA).

Attention is directed to "Water Pollution Control" of these special provisions regarding the submittal and approval of the "Storm Water Pollution Prevention Plan" prior to performing work having potential to cause water pollution.

The first order of work shall be to place the order for the traffic signal equipment. The Engineer shall be furnished a statement from the vendor that the order for the traffic signal equipment has been received and accepted by the vendor.

Prior to commencement of the traffic signal functional test at any location, all items of work related to signal control shall be completed and all roadside signs, pavement delineation, and pavement markings shall be in place at that location.

Some plants required for this project may not be readily available and may have to be grown specifically for this project. Within 30 days after the contract has been approved, furnish to the Engineer a statement from the vendor that the order for the plants to be grown for this contract, including inspection plants and replacement plants, has been received and accepted by the vendor. The statement from the vendor must include the names, sizes, and quantities of plants ordered and the anticipated dates of delivery. Notify the Engineer in writing when the vendor has started to grow the plants.

At least 60 days before planting the plants, furnish the Engineer a statement from the vendor that the order for the plants required for this contract, including inspection plants, has been received and accepted by the vendor. The statement from the vendor must include the names, sizes, and quantities of plants ordered and the anticipated date of delivery.

Place orders for replacement plants with the vendor at the appropriate time so that the roots of the replacement plants are not in a root-bound condition.

At least 60 days before applying seeds, furnish the Engineer a statement from the vendor that the order for the seed required for this contract has been received and accepted by the vendor. The statement from the vendor must include the names and quantity of seed ordered and the anticipated date of delivery.

The Engineer designates ground locations of erosion control by directing the placing of stakes or other suitable markers before application of erosion control materials as specified under "Erosion Control (Type D)," of these special provisions.

Before the start of irrigation work, check for deficiencies of existing plants that are to remain in place as specified under "Maintain Existing Planted Areas" of these special provisions.

Locate existing irrigation water line crossovers and conduits before performing work on the irrigation system as specified under "Locate Existing Crossover and Conduits" of these special provisions.

Unless otherwise shown on the plans or specified in these special provisions, conduits to be jacked or drilled or installed by the open trench method for water line crossovers and sprinkler control crossovers must be installed before the installation of other pipe supply lines.

10-1.02 WATER POLLUTION CONTROL

GENERAL

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, section of these special provisions entitled "Relations With California Regional Water Quality Control Board," and these special provisions.

The Contractor may obtain other National Pollutant Discharge Elimination System (NPDES) permits that apply to activities and mobile operations within or outside of the project limits including asphalt batch plants, material borrow areas, concrete plants, staging areas, storage yards, or access roads.

The Contractor shall perform water pollution control work in conformance with the requirements in the "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual" and addenda in effect on the day the Notice to Contractors is dated. This manual is referred to as the "Preparation Manual." Copies of the Preparation Manual may be obtained from:

State of California
Department of Transportation
Publication Distribution Unit
1900 Royal Oaks Drive
Sacramento, California 95815
Telephone: (916) 445-3520

The Preparation Manual and other references for performing water pollution control work are available from the Department's Construction Storm Water and Water Pollution Control web site at:

<http://www.dot.ca.gov/hq/construc/stormwater/stormwater1.htm>

The Contractor shall designate in writing a Water Pollution Control Manager (WPCM). The Contractor shall submit a statement of qualifications describing the training, work history, and expertise of the proposed WPCM. The qualifications shall include either:

- A. A minimum of 24 hours of Department approved storm water management training described at Department's Construction Storm Water and Water Pollution Control web site.
- B. Certification as a Certified Professional in Erosion and Sediment Control (CPESC).

The WPCM shall be:

1. Responsible for water pollution control work.
2. The primary contact for water pollution control work.
3. Have authority to mobilize crews to make immediate repairs to water pollution control practices.

The Contractor may designate one manager to prepare the SWPPP and a different manager to implement the plan.

STORM WATER POLLUTION PREVENTION PLAN

The Contractor shall submit a Storm Water Pollution Prevention Plan (SWPPP) to the Engineer for approval. The SWPPP shall conform to the requirements in the Preparation Manual, the NPDES permit, and these special provisions. The SWPPP shall be submitted in place of the water pollution control program required by the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications.

The SWPPP shall include water pollution control practices:

- A. For storm water and non-storm water from areas outside of the job site related to construction activities for this contract such as:

1. Staging areas.
2. Storage yards.
3. Access roads.

- B. Appropriate for each season as described in "Implementation Requirements" of these special provisions.
- C. For activities or mobile operations related to all NPDES permits.

The SWPPP shall include a schedule that:

- A. Describes when work activities that could cause water pollution will be performed.
- B. Identifies soil stabilization and sediment control practices for disturbed soil area.
- C. Includes dates when these practices will be 25, 50, and 100 percent complete.
- D. Shows 100 percent completion of these practices before the rainy season.

The SWPPP shall include the following temporary water pollution control practices and their associated contract items of work as shown on the plans or specified in these special provisions:

- A. Temporary Soil Stabilization
 1. Temporary Cover
- B. Temporary Sediment Control
 1. Street Sweeping
 2. Temporary Silt Fence
 3. Temporary Drainage Inlet Protection
- C. Tracking Control
 1. Street Sweeping
- D. Wind Erosion Control
 1. Construction Site Management
- E. Non-Storm Water Management
 1. Construction Site Management
- F. Waste Management and Materials Pollution Control
 1. Construction Site Management
 2. Temporary Concrete Washout Facility

The SWPPP shall include the following contract items of work for permanent water pollution control as shown on the plans or as specified in these special provisions:

- A. Erosion Control (Type D)
- B. Fiber Rolls

Within 20 days after contract approval, the Contractor shall submit 3 copies of the SWPPP to the Engineer. The Contractor shall allow 20 days for the Engineer's review. If revisions are required, the Engineer will provide comments and specify the date that the review stopped. The Contractor shall revise and resubmit the SWPPP within 15 days of receipt of the Engineer's comments. The Engineer's review will resume when the complete SWPPP is resubmitted. When the Engineer approves the SWPPP, the Contractor shall submit 4 copies of the approved SWPPP to the Engineer. The Contractor may proceed with construction activities if the Engineer conditionally approves the SWPPP while minor revisions are being completed. If the Engineer fails to complete the review within the time allowed and if, in the opinion of the Engineer,

completion of the work is delayed or interfered with by reason of the Engineer's delay, the Contractor will be compensated for resulting losses, and an extension of time will be granted, as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Contractor shall not perform work that may cause water pollution until the SWPPP has been approved by the Engineer. The Engineer's review and approval shall not waive any contract requirements and shall not relieve the Contractor from complying with Federal, State and local laws, regulations, and requirements.

If there is a change in construction schedule or activities, the Contractor shall prepare an amendment to the SWPPP to identify additional or revised water pollution control practices. The Contractor shall submit the amendment to the Engineer for review within a time agreed to by the Engineer not to exceed the number of days specified for the initial submittal of the SWPPP. The Engineer will review the amendment within the same time allotted for the review of the initial submittal of the SWPPP.

If directed by the Engineer or requested in writing by the Contractor and approved by the Engineer, changes to the water pollution control work specified in these special provisions will be allowed. Changes may include addition of new water pollution control practices. The Contractor shall incorporate these changes in the SWPPP. Additional water pollution control work will be paid for as extra work in accordance with Section 4-1.03, "Extra work," of the Standard Specifications.

The Contractor shall keep a copy of the approved SWPPP at the job site. The SWPPP shall be made available when requested by a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency, or the local storm water management agency. Requests from the public shall be directed to the Engineer.

SAMPLING AND ANALYSIS

The Contractor shall include a Sampling and Analysis Plan (SAP) in the SWPPP to monitor the effectiveness of the water pollution control practices. The Contractor shall prepare the SAP in conformance with the Preparation Manual.

The Contractor shall designate trained personnel to collect water quality samples. The personnel and training shall be documented in the SAP. Training shall consist of the following elements:

- A. SAP review,
- B. Health and safety review, and
- C. Sampling simulations.

In the SAP the Contractor shall describe the following water quality sampling procedures:

- A. Sampling preparation,
- B. Collection,
- C. Quality assurance and quality control,
- D. Sample labeling,
- E. Collection documentation,
- F. Sample shipping,
- G. Chain of custody,
- H. Sample numbering, and
- I. Precautions from the construction site health and safety plan.

The Contractor shall document sample collection during precipitation.

Samples to be analyzed in the field shall be taken by the Contractor's designated sampling personnel using collection and analysis methods, and equipment calibration specified by the manufacturer of the sampling equipment. Samples to be analyzed by a laboratory, shall be sampled, preserved, and analyzed by a State-certified laboratory in conformance with the requirements in 40 CFR Part 136, "Guidelines Establishing Test Procedures for the Analysis of Pollutants." The Contractor shall identify the State-certified laboratory, sample containers, preservation requirements, holding times, and analysis method in the SAP. A list of State-certified laboratories that are approved by the Department is available at:

<http://www.dhs.ca.gov/ps/ls/ELPA/html/lablist.htm>

Non-Visible Pollutants

This project has the potential to discharge non-visible pollutants in storm water from the construction site. The Contractor shall include in the SAP a description of the sampling and analysis strategy to be implemented on the project for monitoring non-visible pollutants.

In the SAP the Contractor shall identify potential non-visible pollutants that will be present on the construction site associated with the following:

- A. Construction materials and wastes;
- B. Existing contamination due to historical site usage; or
- C. Application of soil amendments, including soil stabilization products, with the potential to alter pH or contribute toxic pollutants to storm water.

The Contractor shall show the locations planned for storage and use of the potential non-visible pollutants on the SWPPP Water Pollution Control Drawings.

The Contractor shall include in the SAP the following list of conditions that require sampling when observed during a storm water inspection:

- A. Materials or wastes containing potential non-visible pollutants are not stored under watertight conditions.
- B. Materials or wastes containing potential non-visible pollutants are stored under watertight conditions, but:
 - 1. A breach, leakage, malfunction, or spill is observed;
 - 2. The leak or spill has not been cleaned up before precipitation; and
 - 3. There is the potential for discharge of non-visible pollutants to surface waters or drainage system.
- C. Construction activities; such as application of fertilizer, pesticide, herbicide, methyl methacrylate concrete sealant, or non-pigmented curing compound; have occurred during precipitation or within 24 hours preceding precipitation, and have the potential to discharge pollutants to surface waters or drainage system.
- D. Soil amendments, including soil stabilization products, with the potential to alter pH levels or contribute toxic pollutants to storm water runoff have been applied, and have the potential to discharge pollutants to surface waters or drainage system (unless independent test data are available that demonstrate acceptable concentrations of non-visible pollutants in the soil amendment).
- E. Storm water runoff from an area contaminated by historical usage of the site has the potential to discharge pollutants to surface waters or drainage system.

The Contractor shall describe in the SAP the schedule for collecting a sample downhill from each non-visible pollutant source and an uncontaminated control sample, during the first 2 hours of discharge from precipitation during daylight hours that result in enough discharge for sample collection. If discharge flows to the non-visible pollutant source, a sample shall be collected immediately downhill from where the discharge enters the Department's right of way. If precipitation occurs again after at least 72 hours of dry weather the Contractor shall take new samples.

In the SAP the Contractor shall identify sampling locations for collecting downstream and control samples, and the reason for their selection. The control sampling location shall be selected so the sample does not come into contact with materials, wastes or areas associated with potential non-visible pollutants or disturbed soil areas. The Contractor shall show non-visible pollutant sampling locations on the SWPPP Water Pollution Control Drawings.

The Contractor shall identify in the SAP the analytical method to be used for downhill and control samples for potential non-visible pollutants on the project.

Analytical Results and Evaluation

The Contractor shall submit a hard copy and electronic copy of water quality analytical results, and quality assurance and quality control data to the Engineer within 5 days of sampling for field analyses, and within 30 days for laboratory analyses. The Contractor shall also provide an evaluation of whether the downhill samples show levels of the tested parameter higher than in the control sample. If downhill or downstream samples show increased levels, the Contractor will assess the water pollution control measures, site conditions, and surrounding influences to determine the probable cause for the increase. As determined by the assessment, the Contractor will repair or modify water pollution control measures to address increases and amend the SWPPP as necessary. Electronic results (in one of the following file formats: .xls, .txt, .csv, .dbs, or .mdb) shall have the following information:

- A. Sample identification number.
- B. Contract number.
- C. Constituent.
- D. Reported value.
- E. Analytical method.
- F. Method detection limit.

G. Reported limit.

The Contractor shall maintain the water quality sampling documentation and analytical results with the SWPPP on the project site until a Notice of Completion has been submitted and approved.

If construction activities or knowledge of site conditions change such that discharges or sampling locations change, the Contractor shall amend the SAP in conformance with this section, "Water Pollution Control."

IMPLEMENTATION REQUIREMENTS

The Contractor shall construct, inspect, maintain, remove, and dispose of the water pollution control practices.

The Contractor's responsibility for SWPPP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications.

If the Contractor or the Engineer identifies a deficiency in the implementation of the approved SWPPP, the deficiency shall be corrected immediately, unless an agreed date for correction is approved in writing by the Engineer. The deficiency shall be corrected before the onset of precipitation. If the Contractor fails to correct the deficiency by the agreed date or before the onset of precipitation, the Department may correct the deficiency and deduct the cost of correcting deficiencies from payments.

If the Contractor fails to conform to the provisions of this section, "Water Pollution Control," the Engineer may order the suspension of work until the project complies with the requirements of this section.

Year-Round

The Contractor shall monitor the National Weather Service weather forecast on a daily basis during the contract. The Contractor may use an alternative weather forecasting service if approved by the Engineer. Appropriate water pollution control practices shall be in place before precipitation.

The Contractor may discontinue earthwork operations for a disturbed area for up to 21 days and the disturbed soil area will still be considered active. When earthwork operations in the disturbed area have been completed, the Contractor shall implement appropriate water pollution control practices within 15 days, or before predicted precipitation, whichever occurs first.

The Contractor shall provide soil stabilization and sediment control practices during the rainy season between October 15 and April 15.

The Contractor shall implement soil stabilization and sediment control practices a minimum of 10 days before the start of the rainy season.

During the defined rainy season, the active disturbed soil area of the project site shall be not more than 5 acres. The Engineer may approve expansions of the active disturbed soil area limit if requested in writing. The Contractor shall maintain soil stabilization and sediment control materials on site to protect disturbed soil areas.

INSPECTION AND MAINTENANCE

The WPCM shall inspect the water pollution control practices identified in the SWPPP as follows:

- A. Before a forecasted storm,
- B. After precipitation that causes site runoff,
- C. At 24-hour intervals during extended precipitation,
- D. On a predetermined schedule, a minimum of once every two weeks outside of the defined rainy season, and
- E. On a predetermined schedule, a minimum of once a week during the defined rainy season.

The WPCM shall oversee the maintenance of the water pollution control practices.

The WPCM shall use the Storm Water Quality Construction Site Inspection Checklist provided in the Preparation Manual or an alternative inspection checklist provided by the Engineer. A copy of the completed site inspection checklist shall be submitted to the Engineer within 24 hours of finishing the inspection.

REPORTING REQUIREMENTS

If the Contractor identifies discharges into surface waters or drainage systems causing or potentially causing pollution, or if the project receives a written notice or order from a regulatory agency, the Contractor shall immediately inform the Engineer. The Contractor shall submit a written report to the Engineer within 7 days of the discharge, notice or order. The report shall include the following information:

- A. The date, time, location, nature of the operation, type of discharge; and the cause of the notice or order.
- B. The water pollution control practices used before the discharge, or before receiving the notice or order.
- C. The date of placement and type of additional or altered water pollution control practices placed after the discharge, or after receiving the notice or order.
- D. A maintenance schedule for affected water pollution control practices.

Annual Certifications

By June 15 of each year, the Contractor shall complete and submit to the Engineer an Annual Certification of Compliance, as contained in the Preparation Manual.

PAYMENT

During each estimate period the Contractor fails to conform to the provisions in this section, "Water Pollution Control," or fails to implement the water pollution control practices shown on the plans or specified elsewhere in these special provisions as items of work, the Department will withhold 25 percent of the progress payment.

Withholds for failure to perform water pollution control work will be in addition to all other withholds provided for in the contract. The Department will return performance-failure withholds in the progress payment following the correction of noncompliance.

The contract lump sum price paid for prepare storm water pollution prevention plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in preparing, obtaining approval of, and amending the SWPPP, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Payments for prepare storm water pollution prevention plan will be made as follows:

- A. After the SWPPP has been approved by the Engineer, 50 percent of the contract item price for prepare storm water pollution prevention plan will be included in the monthly progress estimate.
- B. Forty percent of the contract item price for prepare storm water pollution prevention plan will be paid over the life of the contract.
- C. After acceptance of the contract in conformance with the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, payment for the remaining 10 percent of the contract item price for prepare storm water pollution prevention plan will be made in conformance with the provisions in Section 9-1.07A, "Payment Prior to Proposed Final Estimate."

Storm water sampling and analysis will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. No payment will be made for the preparation, collection, analysis, and reporting of storm water samples where appropriate water pollution control practices are not implemented before precipitation or if a failure of a water pollution control practice is not corrected before precipitation.

Implementation of water pollution control practices in areas outside the highway right of way not specifically provided for in the SWPPP or in these special provisions will not be paid for.

Water pollution control practices for which there are separate contract items of work will be measured and paid for as those contract items of work.

10-1.03 CONSTRUCTION SITE MANAGEMENT

Construction site management shall consist of controlling potential sources of water pollution before they come in contact with storm water systems or watercourses. The Contractor shall control material pollution and manage waste and non-storm water existing at the construction site by implementing effective handling, storage, use, and disposal practices.

Attention is directed to "Water Pollution Control" of these special provisions regarding the Contractor's appointment of a water pollution control manager (WPCM) for the project.

The Contractor shall train all employees and subcontractors regarding:

- A. Material pollution prevention and control;
- B. Waste management;
- C. Non-storm water management;
- D. Identifying and handling hazardous substances; and
- E. Potential dangers to humans and the environment from spills and leaks or exposure to toxic or hazardous substances.

Training shall take place before starting work on this project. New employees shall receive the complete training before starting work on this project. The Contractor shall have regular meetings to discuss and reinforce spill prevention and control; material delivery, storage, use, and disposal; waste management; and non-storm water management procedures.

Instructions for material and waste handling, storage, and spill reporting and cleanup shall be posted at all times in an open, conspicuous, and accessible location at the construction site.

Nonhazardous construction site waste and excess material shall be recycled when practical or disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications, unless otherwise specified.

Vehicles and equipment at the construction site shall be inspected by the WPCM on a frequent, predetermined schedule, and by the operator each day of use. Leaks shall be repaired immediately, or the vehicle or equipment shall be removed from the construction site.

SPILL PREVENTION AND CONTROL

The Contractor shall implement spill and leak prevention procedures when chemicals or hazardous substances are stored. Spills of petroleum products; substances listed under CFR Title 40, Parts 110, 117, and 302; and sanitary and septic waste shall be contained and cleaned up as soon as is safe.

Minor spills involve small quantities of oil, gasoline, paint, or other material that can be controlled by the first responder upon discovery of the spill. Cleanup of minor spills includes:

- A. Containing the spread of the spill,
- B. Recovering the spilled material using absorption,
- C. Cleaning the contaminated area, and
- D. Disposing of contaminated material promptly and properly.

Semi-significant spills are those that can be controlled by the first responder with the help of other personnel. Cleanup of semi-significant spills shall be immediate. Cleanup of semi-significant spills includes:

- A. Containing the spread of the spill;
- B. Recovering the spilled material using absorption if the spill occurs on paved or an impermeable surface;
- C. Containing the spill with an earthen dike and digging up contaminated soil for disposal if the spill occurs on dirt;
- D. Covering the spill with plastic or other material to prevent contaminating runoff if the spill occurs during precipitation; and
- E. Disposing of contaminated material promptly and properly.

Significant or hazardous spills are those that cannot be controlled by construction personnel. Notifications of these spills shall be immediate. The following steps shall be taken:

- A. Construction personnel shall not attempt to cleanup the spill until qualified staff have arrived;
- B. Notify the Engineer and follow up with a written report;
- C. Obtain the services of a spills contractor or hazardous material team immediately;
- D. Notify the local emergency response team by dialing 911 and county officials at the emergency phone numbers kept on the construction site;
- E. Notify the Governor's Office of Emergency Services Warning Center at (805) 852-7550;
- F. Notify the National Response Center at (800) 424-8802 regarding spills of Federal reportable quantities in conformance with CFR Title 40, Parts 110, 119, and 302;
- G. Notify other agencies as appropriate, including:
 - 1. Fire Department,
 - 2. Public Works Department,
 - 3. Coast Guard,
 - 4. Highway Patrol,
 - 5. City Police or County Sheriff Department,
 - 6. Department of Toxic Substances,
 - 7. California Division of Oil and Gas,
 - 8. Cal OSHA, or
 - 9. Regional Water Resources Control Board.

The WPCM shall oversee and enforce proper spill prevention and control measures. Minor, semi-significant, and significant spills shall be reported to the Contractor's WPCM who shall notify the Engineer immediately.

The Contractor shall prevent spills from entering storm water runoff before and during cleanup. Spills shall not be buried or washed with water.

The Contractor shall keep material or waste storage areas clean, well organized, and equipped with enough cleanup supplies for the material being stored. Plastic shall be placed under paving equipment when not in use to catch drips.

MATERIAL MANAGEMENT

Material shall be delivered, used, and stored for this contract in a manner that minimizes or eliminates discharge of material into the air, storm drain systems, or watercourses.

The Contractor shall implement the practices described in this section when taking delivery of, using, or storing the following materials:

A. Hazardous chemicals including:

1. Acids,
2. Lime,
3. Glues,
4. Adhesives,
5. Paints,
6. Solvents, and
7. Curing compounds;

B. Soil stabilizers and binders;

C. Fertilizers;

D. Detergents;

E. Plaster;

F. Petroleum products including:

1. Fuel,
2. Oil, and
3. Grease;

G. Asphalt components and concrete components; and

H. Pesticides and herbicides.

The Contractor shall supply the Material Safety Data Sheet to the Engineer for material used or stored. The Contractor shall keep an accurate inventory of material delivered and stored at the construction site.

Employees trained in emergency spill cleanup procedures shall be present when hazardous materials or chemicals are unloaded.

The Contractor shall use recycled or less hazardous products when practical.

Application of herbicides and pesticides shall be performed by a licensed applicator. The Contractor shall complete the Report of Chemical Spray forms when spraying herbicides or pesticides, and shall submit a copy to the Engineer before application.

Material Storage

The Contractor shall store liquids, petroleum products, and substances listed in CFR Title 40, Parts 110, 117, and 302 in containers or drums approved by the United States Environmental Protection Agency, and place them in secondary containment facilities.

Secondary containment facilities shall be impervious to the materials stored there for a minimum contact time of 72 hours.

Throughout the rainy season secondary containment facilities shall be covered during non-working days and when precipitation is predicted. Secondary containment facilities shall be adequately ventilated.

The Contractor shall keep the secondary containment facility free of accumulated rainwater or spills. After precipitation, or in the event of spills or leaks, accumulated liquid shall be collected and placed into drums within 24 hours. These liquids shall be handled as hazardous waste in accordance with the provisions in "Hazardous Waste" of these special provisions, unless testing determines them to be nonhazardous.

Incompatible materials, such as chlorine and ammonia, shall not be stored in the same secondary containment facility.

Materials shall be stored in the original containers with the original product labels maintained in legible condition. Damaged or illegible labels shall be replaced immediately.

The secondary containment facility shall have the capacity to contain precipitation from a 24-hour-long, 25-year storm; and 10 percent of the aggregate volume of all containers, or all of the volume of the largest container within the facility, whichever is greater.

The Contractor shall store bagged or boxed material on pallets. Throughout the rainy season, bagged or boxed material shall be protected from wind and rain during non-working days and when precipitation is predicted.

The Contractor shall provide sufficient separation between stored containers to allow for spill cleanup or emergency response access. Storage areas shall be kept clean, well organized, and equipped with cleanup supplies appropriate for the materials being stored.

The Contractor shall repair or replace perimeter controls, containment structures, covers, and liners as needed. Storage areas shall be inspected before and after precipitation, and at least weekly during other times.

Stockpile Management

The Contractor shall reduce or eliminate potential air and water pollution from stockpiled material including soil, paving material, or pressure treated wood. Stockpiles shall be located out of floodplains when possible, and at least 50 feet from concentrated flows of storm water, drainage courses, or inlets unless written approval is obtained from the Engineer.

The Contractor may discontinue adding or removing material for up to 21 days and a stockpile will still be considered active.

The Contractor shall protect active stockpiles with plastic or geotextile cover, soil stabilization measures, or with linear sediment barrier when precipitation is predicted. Active stockpiles of cold mix asphalt concrete shall be placed on an impervious surface and covered with plastic when precipitation is predicted.

The Contractor shall protect inactive soil stockpiles with a plastic or geotextile cover, or with soil stabilization measures at all times during the rainy season. A linear sediment barrier around the perimeter of the stockpile shall also be used. During the non-rainy season soil stockpiles shall be covered and protected with a linear sediment barrier when precipitation is predicted. The Contractor shall control wind erosion during dry weather as provided in Section 10, "Dust Control," of the Standard Specifications.

Stockpiles of portland cement concrete rubble, asphalt concrete, asphalt concrete rubble, aggregate base, or aggregate subbase shall be covered with plastic or geotextile, or protected with a linear sediment barrier at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

Stockpiles of cold mix asphalt concrete shall be placed on and covered with impermeable material at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

Stockpiles of pressure treated wood shall be covered with impermeable material and placed on pallets at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

The Contractor shall repair or replace linear sediment barriers and covers as needed or as directed by the Engineer to keep them functioning properly. Sediment shall be removed when it accumulates to 1/3 of the linear sediment barrier height.

WASTE MANAGEMENT

Solid Waste

The Contractor shall not allow litter or debris to accumulate anywhere on the construction site, including storm drain grates, trash racks, and ditch lines. The Contractor shall pick up and remove trash and debris from the construction site at least once a week. The WPCM shall monitor solid waste storage and disposal procedures on the construction site. The Contractor shall provide enough dumpsters of sufficient size to contain the solid waste generated by the project. Dumpsters shall be emptied when refuse reaches the fill line. Dumpsters shall be watertight. The Contractor shall not wash out dumpsters on the construction site. The Contractor shall provide additional containers and more frequent pickup during the demolition phase of construction

Solid waste includes:

- A. Brick,
- B. Mortar,
- C. Timber,
- D. Metal scraps,
- E. Sawdust,
- F. Pipe,
- G. Electrical cuttings,
- H. Non-hazardous equipment parts,

- I. Styrofoam and other packaging materials,
- J. Vegetative material and plant containers from highway planting, and
- K. Litter and smoking material, including litter generated randomly by the public.

Trash receptacles shall be provided and used in the Contractor's yard, field trailers, and locations where workers gather for lunch and breaks.

Hazardous Waste

The Contractor shall implement hazardous waste management practices when waste is generated on the construction site from the following substances:

- A. Petroleum products,
- B. Asphalt products,
- C. Concrete curing compound,
- D. Pesticides,
- E. Acids,
- F. Paints,
- G. Stains,
- H. Solvents,
- I. Wood preservatives,
- J. Roofing tar, and
- K. Materials classified as hazardous by California Code of Regulations, Title 22, Division 4.5; or listed in CFR Title 40, Parts 110, 117, 261, or 302.

Nothing in these special provisions shall relieve the Contractor of the responsibility for compliance with Federal, State, and local laws regarding storage, handling, transportation, and disposal of hazardous wastes.

The WPCM shall oversee and enforce hazardous waste management practices. Production of hazardous materials and hazardous waste on the construction site shall be kept to a minimum. Perimeter controls, containment structures, covers, and liners shall be repaired or replaced when damaged.

The Contractor shall have a laboratory certified by the Department of Health Services (DHS) sample and test waste when hazardous material levels are unknown to determine safe methods for storage and disposal.

The Contractor shall segregate potentially hazardous waste from nonhazardous waste at the construction site. Hazardous waste shall be handled, stored, and disposed of as required in California Code of Regulations, Title 22, Division 4.5, Section 66262.34; and in CFR Title 49, Parts 261, 262, and 263.

The Contractor shall store hazardous waste in sealed containers constructed and labeled with the contents and date accumulated as required in California Code of Regulations, Title 22, Division 4.5; and in CFR Title 49, Parts 172, 173, 178, and 179. Hazardous waste containers shall be kept in temporary containment facilities conforming to the provisions in "Material Storage" of these special provisions.

There shall be adequate storage volume and containers shall be conveniently located for hazardous waste collection. Containers of hazardous waste shall not be overfilled and hazardous wastes shall not be mixed. Containers of dry waste that are not watertight shall be stored on pallets. The Contractor shall not allow potentially hazardous waste to accumulate on the ground. Hazardous waste shall be stored away from storm drains, watercourses, moving vehicles, and equipment.

The Contractor shall clean water based or oil based paint from brushes or equipment within a contained area and shall not contaminate soil, watercourses, or storm drain systems. Paints, thinners, solvents, residues, and sludges that cannot be recycled or reused shall be disposed of as hazardous waste. When thoroughly dry, latex paint and paint cans, used brushes, rags, absorbent materials, and drop cloths shall be disposed of as solid waste.

The Contractor shall dispose of hazardous waste within 90 days of being generated. Hazardous waste shall be disposed of by a licensed hazardous waste transporter using uniform hazardous waste manifest forms and taken to a Class I Disposal Site. A copy of the manifest shall be provided to the Engineer.

Contaminated Soil

The Contractor shall identify contaminated soil from spills or leaks by noticing discoloration, odors, or differences in soil properties. Soil with evidence of contamination shall be sampled and tested by a laboratory certified by DHS. If levels of contamination are found to be hazardous, the soil shall be handled and disposed of as hazardous waste.

The Contractor shall prevent the flow of water, including ground water, from mixing with contaminated soil by using one or a combination of the following measures:

- A. Berms,
- B. Cofferdams,
- C. Grout curtains,
- D. Freeze walls, or
- E. Concrete seal course.

If water mixes with contaminated soil and becomes contaminated, the water shall be sampled and tested by a laboratory certified by the DHS. If levels of contamination are found to be hazardous, the water shall be handled and disposed of as hazardous waste.

Concrete Waste

The Contractor shall implement practices to prevent the discharge of portland cement concrete or asphalt concrete waste into storm drain systems or watercourses.

Portland cement concrete or asphalt concrete waste shall be collected at the following locations and disposed of:

- A. Where concrete material, including grout, is used;
- B. Where concrete dust and debris result from demolition;
- C. Where sawcutting, coring, grinding, grooving, or hydro-concrete demolition of portland cement concrete or asphalt concrete creates a residue or slurry; or
- D. Where concrete trucks or other concrete-coated equipment is cleaned at the construction site.

Sanitary and Septic Waste

Wastewater from sanitary or septic systems shall not be discharged or buried within the Department right of way. The WPCM shall inspect sanitary or septic waste storage and monitor disposal procedures at least weekly. Sanitary facilities that discharge to the sanitary sewer system shall be properly connected and free from leaks.

The Contractor shall obtain written approval from the local health agency, city, county, and sewer district before discharging from a sanitary or septic system directly into a sanitary sewer system, and provide a copy to the Engineer. The Contractor shall comply with local health agency requirements when using an on-site disposal system.

Liquid Waste

The Contractor shall not allow construction site liquid waste, including the following, to enter storm drain systems or watercourses:

- A. Drilling slurries or fluids,
- B. Grease-free or oil-free wastewater or rinse water,
- C. Dredgings,
- D. Liquid waste running off a surface including wash or rinse water, or
- E. Other non-storm water liquids not covered by separate permits.

The Contractor shall hold liquid waste in structurally sound, leak proof containers such as:

- A. Sediment traps,
- B. Roll-off bins, or
- C. Portable tanks.

Liquid waste containers shall be of sufficient quantity and volume to prevent spills and leaks. The containers shall be stored at least 50 feet from storm drains, watercourses, moving vehicles, and equipment.

The Contractor shall remove and dispose of deposited solids from sediment traps as provided in "Solid Waste" of these special provisions, unless determined infeasible by the Engineer.

Liquid waste may require testing to determine hazardous material content before disposal.

Drilling fluids and residue shall be disposed of outside the highway right of way. If the Engineer determines that an appropriate location is available, fluids and residue exempt under California Code of Regulations, Title 23, Section 2511(g) may be dried by infiltration and evaporation in a leak proof container. The remaining solid waste may be disposed of as provided in "Solid Waste" of these special provisions.

NON-STORM WATER MANAGEMENT

Water Control and Conservation

The Contractor shall prevent erosion or the discharge of pollutants into storm drain systems or watercourses by managing the water used for construction operations. The Contractor shall obtain the Engineer's approval before washing anything on the construction site with water that could discharge into a storm drain system or watercourse. Discharges shall be reported to the Engineer immediately.

The Contractor shall implement water conservation practices when water is used on the construction site. Irrigation areas shall be inspected and watering schedules shall be adjusted to prevent erosion, excess watering, or runoff. The Contractor shall shut off the water source to broken lines, sprinklers, or valves, and they shall be repaired as soon as possible. When possible, water from waterline flushing shall be reused for landscape irrigation. Paved areas shall be swept and vacuumed, not washed with water.

Construction water runoff, including water from water line repair, shall be directed to areas to infiltrate into the ground and shall not be allowed to enter storm drain systems or watercourses. Spilled water shall not be allowed to escape water truck filling areas. When possible, the Contractor shall direct water from off-site sources around the construction site, or shall minimize contact with the construction site.

Illegal Connection and Discharge Detection and Reporting

The Contractor shall inspect the construction site and the site perimeter before beginning work for evidence of illegal connections, discharges, or dumping. Subsequently, the construction site and perimeter shall be inspected on a frequent, predetermined schedule.

The Contractor shall immediately notify the Engineer when illegal connections, discharges, or dumping are discovered. The Contractor shall take no further action unless directed by the Engineer. Unlabeled or unidentifiable material shall be assumed to be hazardous.

The Contractor shall look for the following evidence of illegal connections, discharges, or dumping:

- A. Debris or trash piles,
- B. Staining or discoloration on pavement or soils,
- C. Pungent odors coming from drainage systems,
- D. Discoloration or oily sheen on water,
- E. Stains or residue in ditches, channels or drain boxes,
- F. Abnormal water flow during dry weather,
- G. Excessive sediment deposits,
- H. Nonstandard drainage junction structures, or
- I. Broken concrete or other disturbances near junction structures.

Vehicle and Equipment Cleaning

The Contractor shall limit vehicle and equipment cleaning or washing on the construction site to that necessary to control vehicle tracking or hazardous waste. Vehicles and equipment shall not be cleaned on the construction site with soap, solvents, or steam until the Engineer has been notified. The resulting waste shall be contained and recycled, or disposed of as provided in "Liquid Waste" or "Hazardous Waste" of these special provisions, whichever is applicable. The Contractor shall not use diesel to clean vehicles or equipment, and shall minimize the use of solvents.

The Contractor shall clean or wash vehicles and equipment in a structure equipped with disposal facilities. If using a structure is not possible, vehicles and equipment shall be cleaned or washed in an outside area with the following characteristics:

- A. Located at least 50 feet from storm drainage systems or watercourses,
- B. Paved with asphalt concrete or portland cement concrete,
- C. Surrounded by a containment berm, and
- D. Equipped with a sump to collect and dispose of wash water.

When washing vehicles or equipment with water, the Contractor shall use as little water as possible. Hoses shall be equipped with a positive shutoff valve.

Wash racks shall discharge to a recycle system or to another system approved by the Engineer. Sumps shall be inspected regularly, and liquids and sediments shall be removed as needed.

Vehicle and Equipment Fueling and Maintenance

The Contractor shall fuel or perform maintenance on vehicles and equipment off the construction site whenever practical. When fueling or maintenance must be done at the construction site, the Contractor shall designate a site, or sites, and obtain approval from the Engineer before using. The fueling or maintenance site shall be protected from storm water, shall be on level ground, and shall be located at least 50 feet from drainage inlets or watercourses. The WPCM shall inspect the fueling or maintenance site regularly. Mobile fueling or maintenance shall be kept to a minimum.

The Contractor shall use containment berms or dikes around the fueling and maintenance area. Adequate amounts of absorbent spill cleanup material and spill kits shall be kept in the fueling and maintenance area and on fueling trucks. Spill cleanup material and kits shall be disposed of immediately after use. Drip pans or absorbent pads shall be used during fueling or maintenance unless performed over an impermeable surface.

Fueling or maintenance operations shall not be left unattended. Fueling nozzles shall be equipped with an automatic shutoff control. Vapor recovery fueling nozzles shall be used where required by the Air Quality Management District. Nozzles shall be secured upright when not in use. Fuel tanks shall not be topped-off.

The Contractor shall recycle or properly dispose of used batteries and tires.

Material and Equipment Used Over Water

Drip pans and absorbent pads shall be placed under vehicles or equipment used over water, and an adequate supply of spill cleanup material shall be kept with the vehicle or equipment. Drip pans or plastic sheeting shall be placed under vehicles or equipment on docks, barges, or other surfaces over water when the vehicle or equipment will be idle for more than one hour.

The Contractor shall provide watertight curbs or toe boards on barges, platforms, docks, or other surfaces over water to contain material, debris, and tools. Material shall be secured to prevent spills or discharge into water due to wind.

Structure Removal Over or Adjacent to Water

The Contractor shall not allow demolished material to enter storm water systems or watercourses. The Contractor shall use covers and platforms approved by the Engineer to collect debris. Attachments shall be used on equipment to catch debris on small demolition operations. Debris catching devices shall be emptied regularly and debris shall be handled as provided in "Waste Management" of these special provisions.

The WPCM shall inspect demolition sites within 50 feet of storm water systems or watercourses every day.

Paving, Sealing, Sawcutting, and Grinding Operations

The Contractor shall prevent the following material from entering storm drain systems or water courses:

- A. Cementitious material,
- B. Asphaltic material,
- C. Aggregate or screenings,
- D. Grinding or sawcutting residue,
- E. Pavement chunks, or
- F. Shoulder backing.

The Contractor shall cover drainage inlets and use linear sediment barriers to protect downhill watercourses until paving, sealing, sawcutting, or grinding operations are completed and excess material has been removed. Drainage inlets and manholes shall be covered during the application of seal coat, tack coat, slurry seal, or fog seal.

During the rainy season or when precipitation is predicted, paving, sawcutting, and grinding operations shall be limited to places where runoff can be captured. Seal coat, tack coat, slurry seal, or fog seal operations shall not begin if precipitation is predicted for the application or the curing period. The Contractor shall not excavate material from existing roadways during precipitation.

The Contractor shall vacuum up slurry from sawcutting operations immediately after the slurry is produced. Slurry shall not be allowed to run onto lanes open to public traffic or off the pavement.

The Contractor shall collect residue from portland cement concrete grinding operations with a vacuum attachment on the grinding machine. The residue shall not be left on the pavement or allowed to flow across the pavement.

Material excavated from existing roadways may be stockpiled as provided in "Stockpile Management" of these special provisions if approved by the Engineer. Asphalt concrete chunks used in embankment shall be placed above the water table and covered by at least one foot of material.

Substances used to coat asphalt trucks and equipment shall not contain soap, foaming agents, or toxic chemicals.

Thermoplastic Striping and Pavement Markers

Thermoplastic striping and preheating equipment shutoff valves shall work properly at all times when on the construction site. The Contractor shall not preheat, transfer, or load thermoplastic within 50 feet of drainage inlets or watercourses. The Contractor shall not fill the preheating container to more than 6 inches from the top. Truck beds shall be cleaned daily of scraps or melted thermoplastic.

The Contractor shall not unload, transfer, or load bituminous material for pavement markers within 50 feet of drainage inlets or watercourses. All pressure shall be released from melting tanks before removing the lid to fill or service. Melting tanks shall not be filled to more than 6 inches from the top.

The Contractor shall collect bituminous material from the roadway after marker removal.

Pile Driving

The Contractor shall keep spill kits and cleanup material at pile driving locations. Pile driving equipment shall be parked over drip pans, absorbent pads, or plastic sheeting where possible. When not in use, pile driving equipment shall be stored at least 50 feet from concentrated flows of storm water, drainage courses, or inlets. The Contractor shall protect pile driving equipment by parking it on plywood and covering it with plastic when precipitation is predicted. The WPCM shall inspect the pile driving area every day for leaks and spills.

The Contractor shall use vegetable oil instead of hydraulic fluid when practical.

Concrete Curing

The Contractor shall not overspray chemical curing compound. Drift shall be minimized by spraying as close to the concrete as possible. Drainage inlets shall be covered before applying curing compound.

The Contractor shall minimize the use and discharge of water by using wet blankets or similar methods to maintain moisture when curing concrete.

Concrete Finishing

The Contractor shall collect and dispose of water and solid waste from high-pressure water blasting. Drainage inlets within 50 feet shall be covered before sandblasting. The nozzle shall be kept as close to the surface of the concrete as possible to minimize drift of dust and blast material. Blast residue may contain hazardous material.

Containment structures for concrete finishing operations shall be inspected for damage before each day of use and before predicted precipitation. Liquid and solid waste shall be removed from the containment structure after each work shift.

PAYMENT

The contract lump sum price paid for construction site management shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in spill prevention and control, material management, waste management, non-storm water management, and dewatering and identifying, sampling, testing, handling, and disposing of hazardous waste, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.04 STREET SWEEPING

Street sweeping shall be conducted where sediment is tracked from the job site onto paved roads, as described in the approved Storm Water Pollution Prevention Plan (SWPPP) in accordance with "Water Pollution Control" of these special provisions, and as directed by the Engineer.

Street sweeping shall be one of the water pollution control practices for sediment control. The SWPPP shall include the use of street sweeping. Street sweeping shall be performed in accordance with Section 4, SC-7 in the Construction Site Best Management Practices Manual of the Caltrans Storm Water Quality Handbooks.

The number of street sweepers shall be as designated in the approved SWPPP. The Contractor shall maintain at least one sweeper on the job site at all times during the period that sweeping work is required. Sweepers shall be self-loading, motorized, and shall have spray nozzles. Sweepers may include a vacuum apparatus.

Street sweeping shall start at the beginning of clearing and grubbing and shall continue until completion of the project, or as directed by the Engineer. Street sweeping shall be performed immediately after soil disturbing activities occur or offsite tracking of material is observed. Street sweeping shall be performed so that dust is minimized. If dust generation is excessive or sediment pickup is ineffective as determined by the Engineer, the use of water or a vacuum will be required.

At the option of the Contractor, collected material may be temporarily stockpiled in accordance with the approved SWPPP. Collected material shall be disposed of at least once per week.

Material collected during street sweeping operations shall be disposed of in conformance with Section 7-1.13, "Disposal of Material Outside The Highway Right Of Way," of the Standard Specifications.

MEASUREMENT AND PAYMENT

The contract lump sum price paid for street sweeping shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in street sweeping, including disposal of collected material, as shown on the plans, as specified in the Standard Specifications, these special provisions, and as directed by the Engineer.

10-1.05 TEMPORARY COVER

Temporary cover shall be furnished, installed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary cover shall be one of the water pollution control practices for soil stabilization. The SWPPP shall include the use of temporary cover.

MATERIALS

Temporary Cover Fabric

Temporary cover fabric shall be either a geotextile (engineering fabric) or a geomembrane (plastic sheeting) conforming to the following requirements:

1. Geotextile shall be a woven, slit film fabric which is also known as woven tape. The fabric shall be nonbiodegradable, resistant to deterioration by sunlight, and inert to most soil chemicals. Edges of the film fabric shall be selvage or serge to prevent unraveling. The film fabric shall also conform to the following requirements:

Specification	Requirements
Grab tensile strength (one inch grip), pounds, min. ASTM Designation: D4632*	200
Elongation at break, percent, min. ASTM Designation: D4632*	15
Toughness, pounds, min. (percent elongation x grab tensile strength)	3000
Permittivity, l/sec, max. (gallons per minute per square foot) ASTM Designation: D 4491	0.07 (6)
Ultraviolet light stability, percent tensile strength retained after 500 hours, min. ASTM Designation: D 4355 (xenon arc lamp method)	70

* or appropriate test method for specific polymer

2. The geomembrane shall consist of 10 mils thick, single-ply material in conformance with the requirements in ASTM Designation: D 5199.

Temporary cover fabric shall be manufactured from polyethylene, polypropylene, or comparable polymers. The polymer materials may be virgin, recycled, or a combination of virgin and recycled materials. The polymer materials shall not contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance with the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Restrainers

Restrainers for securing the temporary cover fabric on slopes and stockpiles shall consist of one or a combination of the following:

1. Gravel-filled bags used as restrainers shall be knotted, roped, and placed at a maximum of 6 feet apart on the temporary cover fabric as shown on the plans. Gravel-filled bags shall be between 30 pounds and 50 pounds in weight, between 24 inches and 32 inches in length, and between 16 inches and 20 inches in width. Gravel bag fabric shall be nonwoven polypropylene geotextile with a minimum unit weight of 8.0 ounces per square yard. The fabric shall have a minimum grab tensile strength (one-inch grip) of 200 pounds in conformance with the requirements in ASTM Designation: D 4632, and an ultraviolet (UV) stability of 70 percent tensile strength retained after 500 hours in conformance with the requirements in ASTM Designation: D 4355, xenon arc lamp method. Gravel shall consist of noncohesive material between 3/8 inch and 3/4 inch in diameter, free of clay balls, organic matter, and other deleterious material. The openings of gravel-filled bags shall be secured to prevent escape of gravel.
2. Restrainers consisting of a steel anchor with a wooden lath shall be fabricated and placed as shown on the plans. Wooden lath shall conform to the provisions in Section 20-2.12, "Lumber," of the Standard Specifications and shall be fir or pine, 2" x 4" in size, and 8 feet in length. The wooden lath shall be secured to the temporary cover with steel anchors placed 4 feet apart along the lath.

The Contractor may use an alternative restrainer if approved by the Engineer in writing. The Contractor shall submit details for an alternative restrainer to the Engineer before installation. The alternative restrainer shall be installed and maintained in conformance with these special provisions.

INSTALLATION

Temporary cover shall be installed as follows:

1. Temporary cover fabric shall be placed and anchored as shown on the plans.
2. Abutting edges of the temporary cover fabric shall overlap a minimum of 24 inches. Nonabutting edges shall be embedded in the soil a minimum of 6 inches.
3. Restrainers shall be placed at the overlap area and along the toe of the slope. Restrainers outside the overlap areas shall be placed at a maximum spacing of 8 feet.
4. Steel anchors shall be installed to allow the leg of the steel anchor to pierce through the temporary cover fabric into the slope with the crown section securing the wooden lath firmly against the slope.
5. Earthen berm, a linear sediment barrier, shall be constructed adjacent to the toe of the slope with a minimum height of 8 inches and a minimum width of 36 inches. The earthen berm shall be hand or mechanically compacted. Alternative linear sediment barrier may be used if approved by the Engineer in writing.

If the Contractor removes the temporary cover in order to facilitate other work, the temporary cover shall be replaced and secured.

When no longer required as determined by the Engineer, temporary cover shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbances, including holes and depressions, caused by the installation and removal of the temporary cover shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

The Contractor shall maintain the temporary cover throughout the contract to prevent displacement or migration of the material on the slope or stockpiled.

Temporary cover shall be maintained to minimize exposure of the protected area. Restrainers shall be relocated and secured as needed to restrain the temporary cover fabric in place. Temporary cover that breaks free shall be immediately secured. Holes, tears, and voids in the temporary cover fabric shall be patched, repaired, or replaced. When patches or repairs are unacceptable as determined by the Engineer, the temporary cover shall be replaced.

Temporary cover shall be repaired or replaced on the same day when the damage occurs. Damage to the temporary cover resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

MEASUREMENT AND PAYMENT

The quantity of temporary cover to be paid for will be measured by the square yard for the actual area covered.

The contract price paid per square yard for temporary cover shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary cover, complete in place, including trench excavation and backfill, maintenance, and removal of temporary cover, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.06 TEMPORARY CONCRETE WASHOUT FACILITY

Temporary concrete washout facilities shall be constructed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary concrete washout facilities shall be one of the water pollution control practices for waste management and materials pollution control. The SWPPP shall include the use of temporary concrete washout facilities.

MATERIALS

Plastic Liner

Plastic liners shall be single ply, new polyethylene sheeting, a minimum of 10 mils thick and shall be free of holes, punctures, tears or other defects that compromise the impermeability of the material. Plastic liners shall not have seams or overlapping joints.

Gravel-filled Bags

Gravel bag fabric shall be nonwoven polypropylene geotextile (or comparable polymer) and shall conform to the following requirements:

Specification	Requirements
Weight per unit area, ounces per square yard, min. ASTM Designation: D 5261	8.0
Grab tensile strength (one inch grip), kilonewtons, min. ASTM Designation: D 4632*	205
Ultraviolet stability, percent tensile strength retained after 500 hours, ASTM Designation: D 4355, xenon arc lamp method	70

* or appropriate test method for specific polymer

Gravel bags shall be between 24 inches and 32 inches in length, and between 16 inches and 20 inches in width.

Yarn used for binding gravel bags shall be as recommended by the manufacturer or bag supplier and shall be of a contrasting color.

Gravel shall be between 3/8 inch and 3/4 inch in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials.

The opening of gravel-filled bags shall be secured to prevent gravel from escaping. Gravel-filled bags shall be between 30 pounds and 50 pounds in weight.

Straw Bales

Straw for straw bales shall conform to the provisions in Section 20-2.06, "Straw," of the Standard Specifications.

Straw bales shall be a minimum of 14 inches in width, 18 inches in height, 36 inches in length and shall have a minimum weight of 50 pounds. The straw bale shall be composed entirely of vegetative matter, except for binding material.

Straw bales shall be bound by either wire, nylon or polypropylene string. Jute or cotton binding shall not be used. Baling wire shall be a minimum of 16 gage in diameter. Nylon or polypropylene string shall be approximately 0.08-inch in diameter with 80 pounds of breaking strength.

Stakes

Stakes shall be wood or metal. Wood stakes shall be untreated fir, redwood, cedar, or pine and cut from sound timber. They shall be straight and free of loose or unsound knots or other defects which would render them unfit for the purpose intended. Wood stakes shall be a minimum 2" x 2" in size. Metal stakes may be used as an alternative, and shall be a minimum of 0.5-inch in diameter. Stakes shall be a minimum of 4 feet in length. The tops of the metal stakes shall be bent at a 90-degree angle or capped with an orange or red plastic safety cap that fits snugly to the metal stake. The Contractor shall submit a sample of the metal stake and plastic cap, if used, for the Engineer's approval before installation.

Staples

Staples shall be as shown on the plans. An alternative attachment device such as geotextile pins or plastic pegs may be used instead of staples. The Contractor shall submit a sample of the alternative attachment device for the Engineer's approval before installation.

Signs

Wood posts for signs shall conform to the provisions in Section 56-2.02B, "Wood Posts," of the Standard Specifications. Lag screws shall conform to the provisions in Section 56-2.02D, "Sign Panel Fastening Hardware," of the Standard Specifications.

Plywood shall be freshly painted for each installation with not less than 2 applications of flat white paint. Sign letters shown on the plans shall be stenciled with commercial quality exterior black paint. Testing of paint will not be required.

INSTALLATION

Temporary concrete washout facilities shall be as follows:

1. Temporary concrete washout facilities shall be installed before beginning placement of concrete and located a minimum of 50 feet from storm drain inlets, open drainage facilities, and water courses unless determined infeasible by the Engineer. Temporary concrete washout facilities shall be located away from construction traffic or access areas at a location determined by the Contractor and approved by the Engineer.
2. A sign shall be installed adjacent to each washout facility at a location determined by the Contractor and approved by the Engineer. Signs shall be installed in conformance with the provisions in Section 56-2.03, "Construction," and Section 56-2.04, "Sign Panel Installation," of the Standard Specifications.
3. The length and width of a temporary concrete washout facility may be increased from the minimum dimensions shown on the plans upon approval of the Engineer.
4. Temporary concrete washout facilities shall be constructed in sufficient quantity and size to contain liquid and concrete waste generated by washout operations for concrete wastes. These facilities shall be constructed to contain liquid and concrete waste without seepage, spills, or overflow.
5. Berms for below grade temporary concrete washout facilities shall be constructed from compacted native material. Gravel may be used in conjunction with compacted native material.
6. A plastic liner shall be installed in below grade temporary concrete washout facilities.

Details for an alternative temporary concrete washout facility shall be submitted to the Engineer for approval at least 7 days before installation.

When temporary concrete washout facilities are no longer required for the work, as determined by the Engineer, the hardened concrete and liquid residue shall be removed and disposed of in conformance with the provisions in Section 15-3.02, "Removal Methods," of the Standard Specifications. Temporary concrete washout facilities shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary concrete washout facilities shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

Temporary concrete washout facilities shall be maintained to provide adequate holding capacity with a minimum freeboard of 12 inches. Maintaining temporary concrete washout facilities shall include removing and disposing of hardened concrete and returning the facilities to a functional condition. Hardened concrete materials shall be removed and disposed of in conformance with the provisions in Section 15-3.02, "Removal Methods," of the Standard Specifications. Holes, rips, and voids in the plastic liner shall be patched and repaired by taping or the plastic liner shall be replaced. The plastic liner shall be replaced when patches or repairs compromise the impermeability of the material as determined by the Engineer.

Gravel bags shall be replaced when the bag material is ruptured or when the yarn has failed, allowing the bag contents to spill out.

Temporary concrete washout facilities shall be repaired or replaced on the same day the damage occurs. Damage to temporary concrete washout facilities resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

MEASUREMENT AND PAYMENT

Quantities of temporary concrete washout facilities will be measured as units determined from actual count in place.

The contract unit price paid for temporary concrete washout facility shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in constructing a temporary concrete washout facility, complete in place, including excavation and backfill, maintenance, and removal, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.07 TEMPORARY SILT FENCE

Temporary silt fence shall be furnished, installed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary silt fence shall be one of the water pollution control practices for sediment control. The SWPPP shall include the use of temporary silt fence.

MATERIALS

Temporary silt fence shall be either prefabricated or constructed with silt fence fabric, posts, and fasteners.

Silt Fence Fabric

Silt fence fabric shall be geotextile manufactured from woven polypropylene or polymer material. Silt fence fabric may be virgin, recycled, or a combination of virgin and recycled polymer materials. No virgin or recycled polymer materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance to the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Silt fence fabric shall conform to the following requirements:

Specification	Requirements
Width, inches, min.	36
Grab tensile strength (one inch grip), pounds, min. in each direction ASTM Designation: D 4632*	124
Elongation, percent minimum in each direction ASTM Designation: D 4632*	15
Permittivity, 1/sec., min. ASTM Designation: D 4491	0.05
Flow rate, gallons per minute per square foot, min. ASTM Designation: D 4491	10
Ultraviolet stability, percent tensile strength retained after 500 hours, min. ASTM Designation: D 4355 (xenon-arc lamp and water spray weathering method)	70

* or appropriate test method for specific polymer

Posts

Posts for temporary silt fence shall be one of the following:

1. Untreated fir or pine, a minimum of 2" x 2" in size, and 4 feet in length. One end of the post shall be pointed.
2. Steel and have a "U," "T," "L," or other cross sectional shape that can resist failure from lateral loads. The steel posts shall have a minimum weight of 0.8-pound per foot and a minimum length of 4 feet. One end of the steel posts shall be pointed and the other end shall be capped with an orange or red plastic safety cap which fits snugly to the steel post. The Contractor shall submit to the Engineer for approval a sample of the capped steel post before installation.

Fasteners

Fasteners for attaching silt fence fabric to posts shall be as follows:

1. When prefabricated silt fence is used, posts shall be inserted into sewn pockets.
2. Silt fence fabric shall be attached to wooden posts with nails or staples as shown on the plans or as recommended by the manufacturer or supplier. Tie wire or locking plastic fasteners shall be used to fasten the silt fence fabric to steel posts. Maximum spacing of fasteners shall be 8 inches along the length of the steel post.

INSTALLATION

Temporary silt fence shall be installed parallel with the slope contour in reaches not to exceed 500 feet. A reach is considered a continuous run of temporary silt fence from end to end or from an end to an opening, including joined panels. Each reach shall be constructed so that the elevation at the base of the fence does not deviate from the contour more than 1/3 of the fence height.

The silt fence fabric shall be installed on the side of the posts facing the slope. The silt fence fabric shall be anchored in a trench as shown on the plans. The trench shall be backfilled and mechanically or hand tamped to secure the silt fence fabric in the bottom of the trench.

Mechanically pushing 12 inches of the silt fence fabric vertically through the soil may be allowed if the Contractor can demonstrate to the Engineer that the silt fence fabric will not be damaged and will not slip out of the soil resulting in sediment passing under the silt fence fabric.

The maximum post spacing may be increased to 10 feet if the fence is reinforced by a wire or plastic material by prefabrication or by field installation. The field-assembled reinforced temporary silt fence shall be able to retain saturated sediment without collapsing.

Temporary silt fence shall be joined as shown on the plans. The tops of the posts shall be tied together by minimum of 2 wraps of tie wire of a minimum 16-gage diameter. The silt fence fabric shall be attached to the posts at the joint as specified in these special provisions.

When no longer required as determined by the Engineer, temporary silt fence shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. Trimming the silt fence fabric and leaving it in place will not be allowed.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary silt fence shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

Temporary silt fence shall be maintained to provide a sediment holding capacity of approximately 1/3 the height of the silt fence fabric above ground. When sediment exceeds this height or when directed by the Engineer, sediment shall be removed. The removed sediment shall be deposited within the project limits so that the sediment is not subject to erosion by wind or by water.

Temporary silt fence shall be repaired or replaced the same day the damage occurs. Damage to the temporary silt fence resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

MEASUREMENT AND PAYMENT

Quantities of temporary silt fence to be paid for will be determined by the linear foot, measured parallel with the ground slope along the line of the installed temporary silt fence, deducting the widths of openings.

The contract price paid per linear foot for temporary silt fence shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary silt fence, complete in place, including trench excavation and backfill, maintenance, and removal, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.08 TEMPORARY FENCE (TYPE ESA)

Temporary fence (Type ESA) shall be furnished, installed, maintained, and later removed in conformance with the details shown on the plans, as specified in these special provisions and as directed by the Engineer.

MATERIALS

Used materials may be installed provided the used materials conform to these special provisions.

High Visibility Fabric

High visibility fabric shall be machine produced, orange colored mesh manufactured from polypropylene or polyethylene. High visibility fabric may be made of recycled materials. Materials shall not contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. High visibility fabric shall be fully stabilized ultraviolet resistant, shall be a minimum of 4 feet in width with a maximum mesh opening of 2" x 2". High visibility fabric shall be furnished in one continuous width and shall not be spliced to conform to the specified width dimension.

Posts

Posts for temporary fence (Type ESA) shall be of one of the following:

- A. Wood posts shall be fir or pine, shall have a minimum cross section of 2" x 2", and a minimum length of 5.25 feet. The end of the post to be embedded in the soil shall be pointed. Wood posts shall not be treated with wood preservative.

- B. Steel posts shall have a "U," "T," "L," or other cross sectional shape that resists failure from lateral loads. Steel posts shall have a minimum weight of 0.75 pounds per linear foot and a minimum length of 5.25 feet. One end of the steel post shall be pointed and the other end shall have a high visibility colored top.

Fasteners

Fasteners for attaching high visibility fabric to the posts shall be as follows:

- A. The high visibility fabric shall be attached to wooden posts with commercial quality nails or staples, or as recommended by the manufacturer or supplier.
- B. Tie wire or locking plastic fasteners shall be used for attaching the high visibility fabric to steel posts. Maximum spacing of tie wire or fasteners shall be 24 inches along the length of the steel post.

INSTALLATION

Temporary fence (Type ESA) shall be installed as follows:

- A. All fence construction activities shall be conducted from outside the ESA as shown on the plans or as staked.
- B. Posts shall be embedded in the soil a minimum of 16 inches. Post spacing shall be 8 feet maximum from center to center and shall at all times support the fence in a vertical position.
- C. Temporary fence (Type ESA) shall be constructed prior to clearing and grubbing work, shall enclose the foliage canopy (drip line) of protected plants, and shall not encroach upon visible roots of the plants.

When Type ESA temporary fence is no longer required, as determined by the Engineer, the temporary fence shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications, except when reused as provided in this section.

Holes caused by the removal of temporary fence (Type ESA) shall be backfilled in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

Temporary fence (Type ESA) that is damaged during the progress of the work shall be repaired or replaced by the Contractor the same day the damage occurs.

MEASUREMENT AND PAYMENT

Temporary fence (Type ESA) shall be measured and paid for in the same manner specified for fence (Type BW or WM, wood or metal posts) as provided in Section 80, "Fences," of the Standard Specifications.

Full compensation for maintaining, removing, and disposing of temporary fence (Type ESA) shall be considered as included in the contract price paid per linear foot for temporary fence (Type ESA) and no additional compensation will be allowed therefor.

10-1.09 TEMPORARY DRAINAGE INLET PROTECTION

Temporary drainage inlet protection shall be constructed, maintained, and removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in accordance with "Water Pollution Control" of these special provisions, and in accordance with the details shown on the plans and these special provisions.

Temporary drainage inlet protection shall be one of the water pollution control practices for sediment control. The SWPPP shall include the use of temporary drainage inlet protection.

The Contractor shall select the appropriate drainage inlet protection in accordance with the details to meet the conditions around the drainage inlet. Throughout the duration of the contract, the Contractor shall provide protection to meet the changing conditions around the drainage inlet.

Temporary drainage inlet protection shall be Type 3A or 5.

MATERIALS

Gravel-filled Bags

Gravel-filled bag fabric shall be nonwoven polypropylene geotextile or polymer material and shall conform to the following requirements:

Specification	Requirements
Weight per unit area, ounces per square yard, minimum ASTM Designation: D 5261	8.0
Grab tensile strength (one inch grip), pounds, minimum ASTM Designation: D 4632*	200
Ultraviolet stability, percent tensile strength retained after 500 hours minimum ASTM Designation: D 4355, xenon arc lamp method	70

* or appropriate test method for specific polymer

Gravel-filled bags shall be between 24 inches and 32 inches in length, and between 16 inches and 20 inches in width.

Yarn used for binding gravel bags shall be as recommended by the manufacturer or bag supplier and shall be of a contrasting color.

Gravel shall be between 3/8 inch and 3/4 inch in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials. The opening of gravel-filled bags shall be secured to prevent gravel from escaping. Gravel-filled bags shall be between 30 pounds and 50 pounds in weight.

Silt Fence

At the Contractor's option, temporary silt fence shall be prefabricated or constructed with silt fence fabric, posts, and fasteners.

Silt fence fabric shall conform to the following requirements:

Specification	Requirements
Width, inches, minimum	36
Grab tensile strength (one inch grip), pounds, minimum, in each direction ASTM Designation: D 4632 or appropriate test method for specific polymer	124
Elongation, percent, minimum, in each direction ASTM Designation: D 4632 or appropriate test method for specific polymer	15
Permittivity, 1/sec., minimum ASTM Designation: D 4491	0.05
Flow rate, gallons per minute per square foot, minimum ASTM Designation: D 4491	10
Ultraviolet stability, percent, tensile strength retained after 500 hours, minimum ASTM Designation: D 4355 (xenon-arc lamp and water spray weathering method)	70

Silt fence fabric shall be geotextile manufactured from woven polypropylene or polymer material. Silt fence fabric may be made of recycled materials. No materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance to the requirements in ASTM Designation: E 204.

Posts for temporary silt fences shall be one of the following:

- A. Posts shall be untreated fir, redwood, cedar, or pine, shall be cut from sound timber, and shall be straight and free of loose or unsound knots and other defects which would render them unfit for the purpose intended. Wood post shall be a minimum of 2" x 2" in size, and 4 feet in length. The end of the post to be embedded in the soil shall be pointed.
- B. Posts shall be steel and have a "U," "T," "L," or other cross sectional shape that can resist failure from lateral loads. The steel posts shall have a minimum weight of 0.75-pound per foot and a minimum length of 4 feet. One end of the steel posts shall be pointed and the other end shall be capped with an orange or red plastic safety cap which fits snugly to the steel post. The Contractor shall submit to the Engineer for approval a sample of the capped steel post before installation.

Fasteners for attaching silt fence fabric to posts shall be as follows:

- A. When prefabricated silt fence is used, posts shall be inserted into sewn pockets.
- B. Silt fence fabric shall be attached to wooden posts with nails or staples as shown on the plans or as recommended by the manufacturer or supplier. Tie wire or locking plastic fasteners shall be used to fasten the silt fence fabric to steel posts. Maximum spacing of fasteners shall be 8 inches along the length of the steel post.

Sediment Filter Bag

Sediment filter bag fabric shall be geotextile manufactured from woven polypropylene or polymer material. Sediment filter bag fabric may be made from recycled polymer materials. Polymer materials shall not contain biodegradable filler materials and shall conform to the requirements in ASTM Designation: E 204.

Sediment filter bag fabric shall conform to the following requirements:

Specification	Requirements
Grab tensile strength (one inch grip), pounds, minimum in each direction ASTM Designation: D 4632 or appropriate test method for specific polymer	255
Elongation, percent, minimum in each direction ASTM Designation: D 4632 or appropriate test method for specific polymer	15
Permittivity, 1/sec., minimum ASTM Designation: D 4491	1.5
Flow rate, gallons per minute per square foot, minimum ASTM Designation: D 4491	200
Ultraviolet stability, percent tensile strength retained after 500 hours, minimum ASTM Designation: D 4355 (xenon-arc lamp and water spray weathering method)	80

The sediment filter bag shall be sized to fit the catch basin or drainage inlet and shall be complete with lifting loops and dump straps attached at the bottom to facilitate emptying of the sediment filter bag. The sediment filter bags shall have a restraint cord approximately halfway up the bag to keep the sides away from the catch basin walls.

INSTALLATION

Temporary drainage inlet protection shall be installed at drainage inlets in paved and unpaved areas as follows:

- A. Temporary drainage inlet protection shall be installed such that ponded runoff does not encroach on the traveled way or overtop the curb or dike. Gravel-filled bags shall be placed to control ponding and prevent runoff from overtopping the curb or dike.
- B. The bedding area for the temporary drainage inlet protection shall be cleared of obstructions including rocks, clods, and debris greater than one inch in diameter before installation.
- C. A temporary linear sediment barrier shall be installed up-slope of the existing drainage inlet and parallel with the curb, dike, or flow line to prevent sediment from entering the drainage inlet.

Silt Fence

Silt fence shall be installed along the perimeter of the erosion control blanket or geotextile fabric, with the posts facing the drainage inlet. The trench shall be backfilled and tamped to secure the silt fence fabric in the bottom of the trench.

Gravel-filled Bags

Gravel-filled bags shall be stacked to form a gravel bag barrier. The gravel-filled bags shall be placed so that the bags are tightly abutted and overlap the joints in adjacent rows. A spillway shall be created by removing one or more gravel-filled bags from the upper layer of the gravel bag barrier.

Gravel-filled bags shall only be use within shoulder areas when placed behind temporary railing (Type K).

Sediment Filter Bags

Sediment filter bags shall be installed by removing the drainage inlet grate, placing the sediment bag in the opening, and replacing the grate to secure the sediment filter bag in place.

MAINTENANCE

Temporary drainage inlet protection shall be maintained to provide sediment holding capacity and to reduce runoff velocities. Temporary drainage inlet protection shall be repaired or replaced immediately after the damage occurs.

Sediment deposits, trash, and debris shall be removed from temporary drainage inlet protection as needed or when directed by the Engineer. Removed sediment shall be deposited within the project limits so that the sediment is not subject to erosion by wind or by water. Trash and debris shall be removed and disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

At locations where rills and other evidence of concentrated runoff have occurred beneath the drainage inlet protection, the protection shall be adjusted to prevent another occurrence.

Temporary silt fence shall be repaired or replaced when silt fence fabric becomes split, torn, or unraveled. Sagging or slumping silt fence shall be repaired with additional stakes or replaced. Broken or split stakes shall be replaced. Temporary silt fence shall be maintained to provide a sediment holding capacity of approximately 1/3 the height of the silt fence fabric above ground.

Sediment deposits shall be removed when the deposit is 1/3 the height of the gravel bag barrier or one half the height of the spillway; whichever is less.

Gravel-filled bags shall be replaced when the bag material ruptures or when the binding fails.

Sediment filter bags shall be emptied when the restraint cords are no longer visible. Sediment filter bags shall be emptied by placing one inch steel reinforcing bars through the lifting loops. The bag shall be emptied of its contents and rinsed before replacement in the drainage inlet.

REMOVAL

When the temporary drainage inlet protection is no longer required the protection materials shall be removed and disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Holes, depressions, or other ground disturbance caused by the removal of the temporary drainage inlet protection shall be backfilled and repaired in accordance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MEASUREMENT

Quantities of temporary drainage inlet protection will be determined from actual count in place. The protection will be measured one time only and no additional measurement will be recognized.

PAYMENT

The contract unit price paid for temporary drainage inlet protection shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the temporary drainage inlet protection, complete in place, including maintenance, removal of materials, including cleanup and disposal of retained sediment and debris, and backfilling and repairing holes, depressions and other ground disturbance, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

No additional compensation will be made if the temporary drainage inlet protection changes during the course of construction.

10-1.10 COOPERATION

Attention is directed to Section 7-1.14, "Cooperation," and Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

It is anticipated that work by another contractor (Contract No.04-0T2404) to Construct on a State Highway (Pavement Rehabilitation) in Napa and Solano Counties on Route 80 from 1.1 Km (0.7 mi) East of Tennessee Street Overcrossing to American Canyon Overcrossing (PM 3.9 to PM 8.1) may be in progress adjacent to or within the limits of this project during progress of the work on this contract.

10-1.11 PROGRESS SCHEDULE (CRITICAL PATH METHOD)

GENERAL

Summary

Comply with Section 8-1.04, "Progress Schedule," of the Standard Specifications, except you must:

1. Use a computer software to prepare the schedule
2. Furnish compatible software for the Engineer's exclusive possession and use

You are responsible for assuring that all activity sequences are logical and that each schedule shows a coordinated plan for complete performance of the work.

Definitions

The following definitions apply to this section:

contract completion date: The current extended date for completion of the contract shown on the weekly statement of working days furnished by the Engineer as specified in Section 8-1.06, "Time of Completion," of the Standard Specifications.

data date: The day after the date through which a schedule is current. Everything occurring earlier than the data date is "as-built" and everything on or after the data date is "planned."

early completion time: The difference in time between an early scheduled completion date and the contract completion date.

float: The difference between the earliest and latest allowable start or finish times for an activity.

milestone: An event activity that has zero duration and is typically used to represent the beginning or end of a certain stage of the project.

narrative report: A document submitted with each schedule that discusses topics related to project progress and scheduling.

near critical path: A chain of activities with total float exceeding that of the critical path but having no more than 10 working days of total float.

State owned float activity: The activity documenting time saved on the critical path by actions of the State. It is the last activity prior to the scheduled completion date.

time impact analysis: A schedule and narrative report developed specifically to demonstrate what effect a proposed change or delay has on the current scheduled completion date.

time-scaled network diagram: A graphic depiction of a CPM schedule comprised of activity bars with relationships for each activity represented by arrows. The tail of each arrow connects to the activity bar for the predecessor and points to the successor.

total float: The amount of time that an activity or chain of activities can be delayed before extending the scheduled completion date.

Submittals

General Requirements

Submit to the Engineer baseline, monthly updated, and final updated schedules, each consistent in all respects with the time and order of work requirements of the contract. Perform work in the sequence indicated on the current accepted schedule.

Each schedule must show:

1. Calculations using the critical path method to determine controlling activities.
2. Duration activities less than 20 working days.
3. At least 50 but not more than 500 activities, unless authorized. The number of activities must be sufficient to assure adequate planning of the project, to permit monitoring and evaluation of progress, and to do an analysis of time impacts.
4. Each required constraint. Constraints other than those required by the special provisions may be included only if authorized.
5. State-owned float as the predecessor activity to the scheduled completion date.
6. Activities with identification codes for responsibility, stage, work shifts, location, and contract pay item numbers.

You may show early completion time on any schedule provided that the requirements of the contract are met. Early completion time is considered a resource for your exclusive use. You may increase early completion time by improving production, reallocating resources to be more efficient, performing sequential activities concurrently, or by completing activities earlier than planned. You may also submit for approval a VCEP as specified in Section 4-1.035B, "Value Engineering Change Proposal." of the Standard Specifications that will reduce time of construction.

You may show a scheduled completion date that is later than the contract completion date on an update schedule, after the baseline schedule is accepted. Provide an explanation for a late scheduled completion date in the narrative report that is included with the schedule.

State-owned float is considered a resource for the exclusive use of the State. The Engineer may accrue State-owned float by the early completion of review of any type of required submittal when it saves time on the critical path. Prepare a time impact analysis, when requested by the Engineer, to determine the effect of the action as specified in "Time Impact Analysis." The Engineer documents State-owned float by directing you to update the State-owned float activity on the next updated schedule. Include a log of the action on the State-owned float activity and include a discussion of the action in the narrative report. The Engineer may use State-owned float to mitigate past, present, or future State delays by offsetting potential time extensions for contract change orders.

The Engineer may adjust contract working days for ordered changes that affect the scheduled completion date as specified in Section 4-1.03, "Changes," of the Standard Specifications. Prepare a time impact analysis to determine the effect of the change as specified in "Time Impact Analysis" and include the impacts acceptable to the Engineer in the next updated schedule. Changes that do not affect the controlling operation on the critical path will not be considered as the basis for a time adjustment. Changes that do affect the controlling operation on the critical path will be considered by the Engineer in decreasing time or granting an extension of time for completion of the contract. Time extensions will only be granted if the total float is absorbed and the scheduled completion date is delayed one or more working days because of the ordered change.

The Engineer's review and acceptance of schedules does not waive any contract requirements and does not relieve you of any obligation or responsibility for submitting complete and accurate information. Correct rejected schedules and resubmit them within 7 days of notification by the Engineer, at which time a new review period of 7 days will begin.

Errors or omissions on schedules do not relieve you from finishing all work within the time limit specified for completion of the contract. If, after a schedule has been accepted by the Engineer, either you or the Engineer discover that any aspect of the schedule has an error or omission, you must correct it on the next updated schedule.

Computer Software

Submit to the Engineer for review a description of proposed schedule software to be used. After the Engineer accepts the proposed software, furnish schedule software and all original software instruction manuals. All software must be compatible with the current version of the Windows operating system in use by the Engineer. The schedule software must include:

1. Latest version of Primavera SureTrak Project Manager for Windows, or equivalent
2. Latest version of schedule-comparing HST SureChange, or equivalent

If a schedule software equivalent to SureTrak is proposed, it must be capable of generating files that can be imported into SureTrak. The schedule-comparing software must be compatible with schedule software submitted and must be able to compare two schedules and provide reports of changes in activity ID, activity description, constraints, calendar assignments, durations, and logic ties.

The schedule software and schedule-comparing software will be returned to you before the final estimate. The Department will compensate you as specified in Section 4-1.03, "Extra Work," of the Standard Specifications for replacement of software or manuals damaged, lost, or stolen after delivery to the Engineer.

Instruct the Engineer in the use of the software and provide software support until the contract is accepted. Within 15 days of contract approval, provide a commercial 8-hour training session for 2 Department employees in the use of the software at a location acceptable to the Engineer. It is recommended that you also send at least 2 employees to the same training session to facilitate development of similar knowledge and skills in the use of the software. If schedule software other than SureTrak is submitted, then the training session must be a total of 16-hours for each Department employee.

Network Diagrams, Reports, and Data

Include the following with each schedule submittal:

1. Two sets of originally plotted, time-scaled network diagrams
2. Two copies of a narrative report
3. One read-only compact disk or floppy diskette containing the schedule data

The time-scaled network diagrams must conform to the following:

1. Show a continuous flow of information from left to right
2. Be based on early start and early finish dates of activities
3. Clearly show the primary paths of criticality using graphical presentation
4. Be prepared on 34" x 44"
5. Include a title block and a timeline on each page

The narrative report must be organized in the following sequence with all applicable documents included:

1. Transmittal letter
2. Work completed during the period
3. Identification of unusual conditions or restrictions regarding labor, equipment or material; including multiple shifts, 6-day work weeks, specified overtime or work at times other than regular days or hours

4. Description of the current critical path
5. Changes to the critical path and scheduled completion date since the last schedule submittal
6. Description of problem areas
7. Current and anticipated delays:
 - 7.1. Cause of delay
 - 7.2. Impact of delay on other activities, milestones, and completion dates
 - 7.3. Corrective action and schedule adjustments to correct the delay
8. Pending items and status thereof:
 - 8.1. Permits
 - 8.2. Change orders
 - 8.3. Time adjustments
 - 8.4. Noncompliance notices
9. Reasons for an early or late scheduled completion date in comparison to the contract completion date

Schedule submittals will only be considered complete when all documents and data have been submitted as described above.

Preconstruction Scheduling Conference

Schedule a preconstruction scheduling conference with your project manager and the Engineer within 15 days after contract approval. The Engineer will conduct the meeting and review the requirements of this section with you.

Submit a general time-scaled logic diagram displaying the major activities and sequence of planned operations and be prepared to discuss the proposed work plan and schedule methodology that comply with the requirements of this section. If you propose deviations to the construction staging, then the general time-scaled logic diagram must also display the deviations and resulting time impacts. Be prepared to discuss the proposal.

At this meeting, also submit the alphanumeric coding structure and activity identification system for labeling work activities. To easily identify relationships, each activity description must indicate its associated scope or location of work by including such terms as quantity of material, type of work, bridge number, station to station location, side of highway (such as left, right, northbound, southbound), lane number, shoulder, ramp name, ramp line descriptor, or mainline.

The Engineer reviews the logic diagram, coding structure, and activity identification system, and provide any required baseline schedule changes to you for implementation.

Baseline Schedule

Beginning the week following the preconstruction scheduling conference, meet with the Engineer weekly to discuss schedule development and resolve schedule issues until the baseline schedule is accepted.

Submit a baseline schedule within 20 days of contract approval. Allow 20 days for the Engineer's review after the baseline schedule and all support data are submitted. In addition, the baseline schedule submittal is not considered complete until the computer software is delivered and installed for use in review of the schedule.

The baseline schedule must include the entire scope of work and how you plan to complete all work contemplated. The baseline schedule must show the activities that define the critical path. Multiple critical paths and near-critical paths must be kept to a minimum. A total of not more than 50 percent of the baseline schedule activities must be critical or near critical, unless otherwise authorized.

The baseline schedule must not extend beyond the number of contract working days. The baseline schedule must have a data date of contract approval. If you start work before contract approval, the baseline schedule must have a data date of the 1st day you performed work at the job site.

If you submit an early completion baseline schedule that shows contract completion in less than 85 percent of the contract working days, the baseline schedule must be supplemented with resource allocations for every task activity and include time-scaled resource histograms. The resource allocations must be shown to a level of detail that facilitates report generation based on labor crafts and equipment classes for you and your subcontractors. Use average composite crews to display the labor loading of on-site construction activities. Optimize and level labor to reflect a reasonable plan for accomplishing the work of the contract and to assure that resources are not duplicated in concurrent activities. The time-scaled resource histograms must show labor crafts and equipment classes to be used. The Engineer may review the baseline schedule activity resource allocations using Means Productivity Standards or equivalent to determine if the schedule is practicable.

Updated Schedule

Submit an updated schedule and meet with the Engineer to review contract progress, on or before the 1st day of each month, beginning one month after the baseline schedule is accepted. Allow 15 days for the Engineer's review after the updated schedule and all support data are submitted, except that the review period will not start until the previous month's required schedule is accepted. Updated schedules that are not accepted or rejected within the review period are considered accepted by the Engineer.

The updated schedule must have a data date of the 21st day of the month or other date established by the Engineer. The updated schedule must show the status of work actually completed to date and the work yet to be performed as planned. Actual activity start dates, percent complete, and finish dates must be shown as applicable. Durations for work that has been completed must be shown on the updated schedule as the work actually occurred, including Engineer submittal review and your resubmittal times.

You may include modifications such as adding or deleting activities or changing activity constraints, durations, or logic that do not (1) alter the critical path(s) or near critical path(s) or (2) extend the scheduled completion date compared to that shown on the current accepted schedule. Justify in writing the reasons for any changes to planned work. If any proposed changes in planned work will result in (1) or (2) above, then submit a time impact analysis as specified in this section.

Time Impact Analysis

Submit a written time impact analysis (TIA) with each request for adjustment of contract time, or when you or the Engineer consider that an approved or anticipated change may impact the critical path or contract progress.

The TIA must illustrate the impacts of each change or delay on the current scheduled completion date or internal milestone, as appropriate. The analysis must use the accepted schedule that has a data date closest to and before the event. If the Engineer determines that the accepted schedule used does not appropriately represent the conditions before the event, the accepted schedule must be updated to the day before the event being analyzed. The TIA must include an impact schedule developed from incorporating the event into the accepted schedule by adding or deleting activities, or by changing durations or logic of existing activities. If the impact schedule shows that incorporating the event modifies the critical path and scheduled completion date of the accepted schedule, the difference between scheduled completion dates of the two schedules must be equal to the adjustment of contract time. The Engineer may construct and use an appropriate project schedule or other recognized method to determine adjustments in contract time until you provide the TIA.

Submit 2 copies of your TIA within 20 days of receiving a written request for a TIA from the Engineer. Allow the Engineer 15 days after receipt to review the submitted TIA. All approved TIA schedule changes must be shown on the next updated schedule.

If a TIA you submit is rejected, meet with the Engineer to discuss and resolve issues related to the TIA. If agreement is not reached, you are allowed 15 days from the meeting with the Engineer to give notice as specified in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications. Only show actual as-built work, not unapproved changes related to the TIA, in subsequent updated schedules. If agreement is reached at a later date, approved TIA schedule changes must be shown on the next updated schedule. The Engineer withholds remaining payment on the schedule contract item if a TIA is requested and not submitted within 20 days. The schedule item payment resumes on the next estimate after the requested TIA is submitted. No other contract payment is withheld regarding TIA submittals.

Final Updated Schedule

Submit a final update, as-built schedule with actual start and finish dates for the activities, within 30 days after completion of contract work. Provide a written certificate with this submittal signed by your project manager or an officer of the company stating, "To my knowledge and belief, the enclosed final update schedule reflects the actual start and finish dates of the actual activities for the project contained herein." An officer of the company may delegate in writing the authority to sign the certificate to a responsible manager.

PAYMENT

Progress schedule (critical path method) will be paid for at a lump sum price. The contract lump sum price paid for progress schedule (critical path method) includes full compensation for furnishing all labor, material, tools, equipment, and incidentals, including computer software, and for doing all the work involved in preparing, furnishing, and updating schedules, and instructing and assisting the Engineer in the use of computer software, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Payments for the progress schedule (critical path method) contract item will be made progressively as follows:

1. A total of 25 percent of the item amount will be paid upon achieving all of the following:

- 1.1. Completion of 5 percent of all contract item work.
 - 1.2. Acceptance of all schedules and approval of all TIAs required to the time when 5 percent of all contract item work is complete.
 - 1.3. Delivery of schedule software to the Engineer.
 - 1.4. Completion of required schedule software training.
2. A total of 50 percent of the item amount will be paid upon completion of 25 percent of all contract item work and acceptance of all schedules and approval of all TIAs required to the time when 25 percent of all contract item work is complete.
 3. A total of 75 percent of the item amount will be paid upon completion of 50 percent of all contract item work and acceptance of all schedules and approval of all TIAs required to the time when 50 percent of all contract item work is complete.
 4. A total of 100 percent of the item amount will be paid upon completion of all contract item work, acceptance of all schedules and approval of all TIAs required to the time when all contract item work is complete, and submittal of the certified final update schedule.

If you fail to complete any of the work or provide any of the schedules required by this section, the Engineer makes an adjustment in compensation as specified in Section 4-1.03C, "Changes in Character of Work," of the Standard Specifications for the work not performed. Adjustments in compensation for schedules will not be made for any increased or decreased work ordered by the Engineer in submitting schedules.

10-1.12 TIME-RELATED OVERHEAD

The Contractor will be compensated for time-related overhead as described below and in conformance with "Force Account Payment" of these special provisions. The Contractor will not be compensated for time-related overhead for delays to the controlling operations caused by the Engineer that occur prior to the first working day, but will be compensated for actual overhead costs incurred, as determined by an independent Certified Public Accountant audit examination and report.

Attention is directed to "Beginning of Work, Time of Completion and Liquidated Damages," "Force Account Payment," and "Progress Schedule (Critical Path Method)" of these special provisions.

The provisions in Section 9-1.08, "Adjustment of Overhead Costs," of the Standard Specifications shall not apply.

Time-related overhead shall consist of those overhead costs, including field and home office overhead, that are in proportion to the time required to complete the work. Time-related overhead shall not include costs that are not related to time, including but not limited to, mobilization, licenses, permits, and other charges incurred only once during the contract. Time-related overhead shall not apply to subcontractors of any tier, suppliers, fabricators, manufacturers, or other parties associated with the Contractor.

Field office overhead expenses include time-related costs associated with the normal and recurring operations of the construction project, and shall not include costs directly attributable to the work of the contract. Time-related costs of field office overhead include, but are not limited to, salaries, benefits, and equipment costs of project managers, general superintendents, field office managers and other field office staff assigned to the project, and rent, utilities, maintenance, security, supplies, and equipment costs of the project field office.

Home office overhead or general and administrative expenses refer to the fixed costs of operating the Contractor's business. These costs include, but are not limited to, general administration, insurance, personnel and subcontract administration, purchasing, accounting, and project engineering and estimating. Home office overhead costs shall exclude expenses specifically related to other contracts or other businesses of the Contractor, equipment coordination, material deliveries, and consultant and legal fees.

The quantity of time-related overhead associated with a reduction in contract time for cost reduction incentive proposals accepted and executed in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications shall be considered a construction cost attributable to the resultant estimated net savings due to the cost reduction incentive.

If the final increased quantity of time-related overhead exceeds 149 percent of the number of working days specified in the Engineer's Estimate, the Contractor shall, within 60 days of the Engineer's written request, submit to the Engineer an audit examination and report performed by an independent Certified Public Accountant of the Contractor's actual overhead costs. The audit examination and report shall depict the Contractor's project and company-wide financial records and shall specify the actual overall average daily rates for both field and home office overhead for the entire duration of the project, and whether the costs have been properly allocated. The rates of field and home office overhead shall exclude unallowable costs as determined in the Federal Acquisition Regulations, 48 CFR, Chapter 1, Part 31.

Independent Certified Public Accountant's audit examinations shall be performed in conformance with the requirements of the American Institute of Certified Public Accountants Attestation Standards. Audit examinations and reports shall determine if the rates of field office overhead and home office overhead are:

- A. Allowable in conformance with the requirements of the Federal Acquisition Regulations, 48 CFR, Chapter 1, Part 31.
- B. Adequately supported by reliable documentation.
- C. Related solely to the project under examination.

Within 20 days of receipt of the Engineer's written request, the Contractor shall make its financial records available for audit by the State for the purpose of verifying the actual rate of time-related overhead specified in the audit submitted by the Contractor. The actual rate of time-related overhead specified in the audit, submitted by the Contractor, will be subject to approval by the Engineer.

If the Engineer requests the independent Certified Public Accountant audit, or if it is requested in writing by the Contractor, the contract item payment rate for time-related overhead, in excess of 149 percent of the number of working days specified in the Engineer's Estimate, will be adjusted to reflect the actual rate.

The cost of performing an independent Certified Public Accountant audit examination and submitting the report, requested by the Engineer, will be borne equally by the State and the Contractor. The division of the cost will be made by determining the cost of providing an audit examination and report in conformance with the provisions of Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor one-half of that cost. The cost of performing an audit examination and submitting the independent Certified Public Accountant audit report for overhead claims other than for the purpose of verifying the actual rate of time-related overhead shall be entirely borne by the Contractor. The cost of performing an audit examination and submitting the independent Certified Public Accountant audit report to verify actual overhead costs incurred prior to the first working day shall be entirely borne by the Contractor.

The quantity of time-related overhead to be paid will be measured by the working day, designated in the Engineer's Estimate as WDAY. The estimated number of working days is the number of working days, excluding days for plant establishment, as specified in "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions. The quantity of time-related overhead will be increased or decreased only as a result of suspensions or adjustments of contract time which revise the current contract completion date, and which satisfy any of the following criteria:

- A. Suspensions of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications, except:
 - 1. Suspensions ordered due to weather conditions being unfavorable for the suitable prosecution of the controlling operation or operations.
 - 2. Suspensions ordered due to the failure on the part of the Contractor to carry out orders given, or to perform the provisions of the contract.
 - 3. Suspensions ordered due to factors beyond the control of and not caused by the State or the Contractor, for which the Contractor is granted extensions of time in conformance with the provisions of the third paragraph of Section 8-1.07, "Liquidated Damages," of the Standard Specifications.
 - 4. Other suspensions that mutually benefit the State and the Contractor.
- B. Extensions of contract time granted by the State in conformance with the provisions in the fifth paragraph in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and set forth in approved contract change orders, in conformance with the provisions in Section 4-1.03, "Changes," of the Standard Specifications.
- C. Reductions in contract time set forth in approved contract change orders, in conformance with the provisions in Section 4-1.03, "Changes," of the Standard Specifications.

In the event an early completion progress schedule, as defined in "Progress Schedule (Critical Path Method)" of these special provisions, is submitted by the Contractor and approved by the Engineer, the amount of time-related overhead eligible for payment will be based on the total number of working days for the project, in conformance with the provisions in "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions, rather than the Contractor's early completion progress schedule.

The contract price paid per working day for time-related overhead shall include full compensation for time-related overhead, including the Contractor's share of costs of the independent Certified Public Accountant audit of overhead costs requested by the Engineer, as specified in these special provisions, and as directed by the Engineer.

The provisions in Sections 4-1.03B, "Increased or Decreased Quantities," and 4-1.03C, "Changes in Character of the Work," of the Standard Specifications shall not apply to the contract item of time-related overhead.

Full compensation for additional overhead costs incurred during days of inclement weather when the contract work is extended into additional construction seasons due to delays caused by the State shall be considered as included in the time-related overhead paid during the contract working days, and no additional compensation will be allowed therefor.

Full compensation for additional overhead costs involved in performing additional contract item work that is not a controlling operation shall be considered as included in the contract items of work involved and no additional compensation will be allowed therefor.

Full compensation for overhead, other than time-related overhead measured and paid for as specified above, and other than overhead costs included in the markups specified in "Force Account Payment" of these special provisions, shall be considered as included in the various items of work and no additional compensation will be allowed therefor.

Overhead costs incurred by subcontractors of any tier, suppliers, fabricators, manufacturers, and other parties associated with the Contractor shall be considered as included in the various items of work and as specified in Section 9-1.03, "Force Account Payment," of the Standard Specifications.

For the purpose of making partial payments pursuant to the provisions in Section 9-1.06, "Partial Payments," of the Standard Specifications, the number of working days to be paid for time-related overhead in each monthly partial payment will be the number of working days, specified above to be measured for payment that occurred during that monthly estimate period, including compensable suspensions and right of way delays. Working days granted by contract change order due to extra work or changes in character of the work, will be paid for upon completion of the contract. The amount earned per working day for time-related overhead shall be the lesser of the following amounts:

- A. The contract item price.
- B. Twenty percent of the original total contract amount divided by the number of working days specified in "Beginning of Work, Time of Completion and Liquidated Damages," of these special provisions.

After the work has been completed, except plant establishment work, as provided in Section 20-4.08, "Plant Establishment Work," of the Standard Specifications, the amount of the total contract item price for time-related overhead not yet paid will be included for payment in the first estimate made after completion of roadway construction work, in conformance with the provisions in Section 9-1.06, "Partial Payments," of the Standard Specifications.

10-1.13 OBSTRUCTIONS

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Attention is directed to the existence of certain underground facilities that may require special precautions be taken by the Contractor to protect the health, safety and welfare of workers and of the public. Facilities requiring special precautions include, but are not limited to: conductors of petroleum products, oxygen, chlorine, and toxic or flammable gases; natural gas in pipelines greater than 6 inches in diameter or pipelines operating at pressures greater than 60 pounds per square inch (gage); underground electric supply system conductors or cables, with potential to ground of more than 300 V, either directly buried or in a duct or conduit which do not have concentric grounded or other effectively grounded metal shields or sheaths.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	(800) 642-2444 (800) 227-2600
Underground Service Alert-Southern California (USA)	(800) 422-4133 (800) 227-2600

If these facilities are not located on the plans in both alignment and elevation, no work shall be performed in the vicinity of the facilities, except as provided herein for conduit to be placed under pavement, until the owner, or the owner's representative, has located the facility by potholing, probing or other means that will locate and identify the facility. Conduit to be installed under pavement in the vicinity of these facilities shall be placed by the trenching method in conformance with the provisions in "Conduit" of these special provisions. If, in the opinion of the Engineer, the Contractor's operations are delayed or interfered with by reason of the utility facilities not being located by the owner or the owner's representative, the State will compensate the Contractor for the delays to the extent provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications, and not otherwise, except as provided in Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	(800) 642-2444 (800) 227-2600
Underground Service Alert-Southern California (USA)	(800) 422-4133 (800) 227-2600

10-1.14 SMALL BUSINESS UTILIZATION REPORT

Submit a completed Small Business Utilization Report form on or before the following dates for the prior reporting period:

1. January 15th
2. April 15th
3. July 15th
4. October 15th

Submit a completed final Small Business Utilization Report form within 30 days after contract acceptance.

The Department pays \$250 for each report submitted. The contract unit price paid for small business utilization report includes full compensation for doing all the work involved in submitting the completed Small Business Utilization Report form. If you fail to submit a completed form by the specified time, you will not receive payment for that report.

The Department does not adjust payment for an increase or decrease in the quantity of small business utilization reports submitted. Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications does not apply.

The work to complete the final Small Business Utilization Report contract item is excluded from Section 7-1.17, "Acceptance of Contract," of the Standard Specifications.

Failure to submit the Small Business Utilization Report is not considered a performance failure. Section 9-1.053, "Performance Failure Withholds," of the Standard Specifications does not apply.

10-1.15 DUST CONTROL

Dust control shall conform to the provisions in Section 10, "Dust Control," of the Standard Specifications .

10-1.16 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES

Flagging, signs, and temporary traffic control devices furnished, installed, maintained, and removed when no longer required shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Category 1 temporary traffic control devices are defined as small and lightweight (less than 100 pounds) devices. These devices shall be certified as crashworthy by crash testing, crash testing of similar devices, or years of demonstrable safe performance. Category 1 temporary traffic control devices include traffic cones, plastic drums, portable delineators, and channelizers.

If requested by the Engineer, the Contractor shall provide written self-certification for crashworthiness of Category 1 temporary traffic control devices at least 5 days before beginning any work using the devices or within 2 days after the request if the devices are already in use. Self-certification shall be provided by the manufacturer or Contractor and shall include the following:

- A. Date,
- B. Federal Aid number (if applicable),
- C. Contract number, district, county, route and post mile of project limits,
- D. Company name of certifying vendor, street address, city, state and zip code,
- E. Printed name, signature and title of certifying person; and
- F. Category 1 temporary traffic control devices that will be used on the project.

The Contractor may obtain a standard form for self-certification from the Engineer.

Category 2 temporary traffic control devices are defined as small and lightweight (less than 100 pounds) devices that are not expected to produce significant vehicular velocity change, but may cause potential harm to impacting vehicles. Category 2 temporary traffic control devices include barricades and portable sign supports.

Category 2 temporary traffic control devices shall be on the Federal Highway Administration's (FHWA) list of Acceptable Crashworthy Category 2 Hardware for Work Zones. This list is maintained by FHWA and can be located at:

http://safety.fhwa.dot.gov/roadway_dept/road_hardware/listing.cfm?code=workzone

The Department also maintains this list at:

<http://www.dot.ca.gov/hq/traffops/signtech/signdel/pdf/Category2.pdf>

Category 2 temporary traffic control devices that have not received FHWA acceptance shall not be used. Category 2 temporary traffic control devices in use that have received FHWA acceptance shall be labeled with the FHWA acceptance letter number and the name of the manufacturer. The label shall be readable and permanently affixed by the manufacturer. Category 2 temporary traffic control devices without a label shall not be used.

If requested by the Engineer, the Contractor shall provide a written list of Category 2 temporary traffic control devices to be used on the project at least 5 days before beginning any work using the devices or within 2 days after the request if the devices are already in use.

Category 3 temporary traffic control devices consist of temporary traffic-handling equipment and devices that weigh 100 pounds or more and are expected to produce significant vehicular velocity change to impacting vehicles. Temporary traffic-handling equipment and devices include crash cushions, truck-mounted attenuators, temporary railing, temporary barrier, and end treatments for temporary railing and barrier.

Type III barricades may be used as sign supports if the barricades have been successfully crash tested, meeting the NCHRP Report 350 criteria, as one unit with a construction area sign attached.

Category 3 temporary traffic control devices shall be shown on the plans or on the Department's Highway Safety Features list. This list is maintained by the Division of Engineering Services and can be found at:

http://www.dot.ca.gov/hq/esc/approved_products_list/HighwaySafe.htm

Category 3 temporary traffic control devices that are not shown on the plans or not listed on the Department's Highway Safety Features list shall not be used.

Full compensation for providing self-certification for crashworthiness of Category 1 temporary traffic control devices and for providing a list of Category 2 temporary traffic control devices used on the project shall be considered as included in the prices paid for the various items of work requiring the use of the Category 1 or Category 2 temporary traffic control devices and no additional compensation will be allowed therefor.

10-1.17 CONSTRUCTION AREA SIGNS

Construction area signs for temporary traffic control shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to "Furnish Sign" of these special provisions.

Attention is directed to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels. Type III, IV, VII, VIII, or IX retroreflective sheeting shall be used for stationary mounted construction area sign panels.

Unless otherwise shown on the plans or specified in these special provisions, the color of construction area warning and guide signs shall have black legend and border on orange background, except W10-1 or W47(CA) (Highway-Rail Grade Crossing Advance Warning) sign shall have black legend and border on yellow background.

Repair to construction area sign panels will not be allowed, except when approved by the Engineer. At nighttime under vehicular headlight illumination, sign panels that exhibit irregular luminance, shadowing or dark blotches shall be immediately replaced at the Contractor's expense.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	(800) 642-2444 (800) 227-2600
Underground Service Alert-Southern California (USA)	(800) 422-4133 (800) 227-2600

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes. The post hole diameter, if backfilled with portland cement concrete, shall be at least 4 inches greater than the longer dimension of the post cross section.

Construction area signs placed within 15 feet from the edge of the travel way shall be mounted on stationary mounted sign supports as specified in "Construction Area Traffic Control Devices" of these special provisions.

The Contractor shall maintain accurate information on construction area signs. Signs that are no longer required shall be immediately covered or removed. Signs that convey inaccurate information shall be immediately replaced or the information shall be corrected. Covers shall be replaced when they no longer cover the signs properly. The Contractor shall immediately restore to the original position and location any sign that is displaced or overturned, from any cause, during the progress of work.

10-1.18 TEMPORARY CRASH CUSHION MODULE

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety" and "Order of Work", of these special provisions.

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 15 feet or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

At the Contractor's option, the modules for use in sand filled temporary crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or Traffix Sand Barrels manufactured after March 31, 1997, or equal:

1. Energite III and Fitch Inertial Modules, manufactured by Energy Absorption Systems, Inc., 35 East Wacker Drive, Suite 1100, Chicago, IL 60601:
 - 1.1. Northern California: Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, telephone (800) 884-8274, FAX (916) 387-9734
 - 1.2. Southern California: Traffic Control Service, Inc., 1818 E. Orangethorpe, Fullerton, CA 92831-5324, telephone (800) 222-8274, FAX (714) 526-9501
2. Traffix Sand Barrels, manufactured by Traffix Devices, Inc., 220 Calle Pintoresco, San Clemente, CA 92672, telephone (949) 361-5663, FAX (949) 361-9205
 - 2.1. Northern California: United Rentals, Inc., 1533 Berger Drive, San Jose, CA 95112, telephone (408) 287-4303, FAX (408) 287-1929
 - 2.2. Southern California: Statewide Safety & Sign, Inc., P.O. Box 1440, Pismo Beach, CA 93448, telephone (800) 559-7080, FAX (805) 929-5786

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are

furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in pounds for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

Temporary crash cushion modules shall be placed on movable pallets or frames conforming to the dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 12 feet of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions will not be measured nor paid for.

10-1.19 EXISTING HIGHWAY FACILITIES

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Except as otherwise provided for damaged materials in Section 15-2.04, "Salvage," of the Standard Specifications, the materials to be salvaged shall remain the property of the State, and shall be cleaned, packaged, bundled, tagged, and hauled to the District Regional Recycle Center at 3401 Regatta Boulevard, Richmond, California 94804 and stockpiled.

The Contractor shall notify the Engineer and the District Regional Recycle Coordinator, telephone (510) 231-7133 a minimum of 48 hours prior to hauling salvaged material to the Recycle Center.

SALVAGE EXISTING SIGN PLAQUES

Existing sign plaques, where shown on the plans to be salvaged, shall be removed and salvaged.

Salvaged existing sign plaques, shall be hauled to the District Regional Recycle Center at 3401 Regatta Boulevard, Richmond, California 94804 and stockpiled.

ABANDON SEWER

Existing sewer where shown on the plans to be abandoned, shall be abandoned in place or, at the option of the Contractor, the sewer shall be removed and disposed of. Resulting openings into existing structures that are to remain in place shall be plugged with concrete conforming to the provisions in Section 90-10 "Minor Concrete," of the Standard Specifications. The concrete shall contain not less than 505 pounds of cementitious material per cubic yard.

Abandoning sewer in place shall conform to the following:

1. Sewer that intersects the side slopes shall be removed to a depth of not less than 3 feet measured normal to the plane of the finished side slope, before being abandoned.
2. Sewer, 12 inches in diameter and larger, shall, at the Contractor's option, be backfilled with either sand, controlled low strength material or slurry cement backfill conforming to the provisions in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications by any method acceptable to the Engineer that completely fills the sewer. Sand backfill material shall be clean, free draining, and free from roots and other deleterious substances.
3. The ends of sewer shall be securely closed by a 0.5-foot thick tight fitting plug or wall of minor concrete.

Sewers shall not be abandoned until their use is no longer required. The Contractor shall notify the Engineer in advance of any intended sewer abandonment.

If the Contractor elects to remove and dispose of a sewer which is specified to be abandoned, as provided herein, backfill specified for the sewer will be measured and paid for in the same manner as if the sewer had been abandoned in place.

Backfill will be measured by the cubic yard determined from the dimensions of the sewer to be abandoned.

Full compensation for concrete plugs, pipe removal, structure excavation, and backfill (including sand, controlled low strength material or slurry cement backfill) shall be considered as included in the contract price paid for each abandon sewer and no additional compensation will be allowed therefor.

REMOVE FENCE

Existing fence, at the locations shown on the plans to be removed, shall be removed and disposed of.

Full compensation for removing and disposing of wood fence shall be considered as included in the contract price paid per linear foot for remove fence and no separate payment will be made therefor.

ADJUST MANHOLE TO GRADE

Frames and covers of existing manholes, shall be adjusted to grade in conformance with the provisions in Section 15-2.05, "Reconstruction," of the Standard Specifications.

REMOVE CONCRETE (MISCELLANEOUS)

Remove concrete (curb, pathway, ramp, concrete slab, side walk and footing) , where shown on the plans to be removed, shall be removed.

The pay quantities of concrete to be removed will be measured by the cubic yard, measured before and during removal operations.

Concrete removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Concrete within construction limits, both inside and outside the highway right of way, shall be removed, except for curbs and sidewalks adjacent to frontage roads and through city streets.

Where no joint exists between concrete to be removed and concrete to remain in place, the concrete shall be cut on a neat line to a minimum depth of 0.17-foot with a power driven saw before the concrete is removed.

Where concrete has been removed outside the roadway prism, the backfilled areas shall be graded to drain and blend in with the surrounding terrain.

Concrete to be removed which has portions of the same structure both above and below ground will be considered as concrete above ground for compensation.

10-1.20 CLEARING AND GRUBBING

Clearing and grubbing shall conform to the provisions in Section 16, "Clearing and Grubbing," of the Standard Specifications and these special provisions.

Trees shall be removed as shown on the plans.

At locations where there is no grading adjacent to a structure, clearing and grubbing of vegetation shall be limited to 5 feet outside the physical limits of the structure.

Existing vegetation to be preserved, as shown on the plans, shall be protected from injury or damage resulting from the Contractor's operations.

Activities controlled by the Contractor, except cleanup or other required work, shall be confined within the graded areas of the work site.

Nothing herein shall be construed as relieving the Contractor of the Contractor's responsibility for final cleanup of the highway as provided in Section 4-1.02, "Final Cleaning Up," of the Standard Specifications.

10-1.21 EARTHWORK

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

Reinforcement or metal attached to reinforced concrete rubble placed in embankments shall not protrude above the grading plane. Prior to placement within 2 feet below the grading plane of embankments, reinforcement or metal shall be trimmed to no greater than 3/4 inch from the face of reinforced concrete rubble. Full compensation for trimming reinforcement or metal shall be considered as included in the contract prices paid per cubic yard for the types of excavation shown in the Engineer's estimate, or the contract prices paid for furnishing and placing imported borrow or embankment material, as the case may be, and no additional compensation will be allowed therefor.

Imported borrow shall be mineral material including rock, sand, gravel, or earth. The Contractor shall not use man-made refuse in imported borrow including:

- A. Portland cement concrete
- B. Asphalt concrete
- C. Material planed from roadway surfaces

- D. Residue from grooving or grinding operations
- E. Metal
- F. Rubber
- G. Mixed debris
- H. Rubble

Imported borrow will be measured and paid for by the cubic yard and the quantity to be paid for will be computed in the following manner:

- A. The total quantity of embankment will be computed in conformance with the provisions for roadway excavation in Section 19-2.08, "Measurement," of the Standard Specifications, on the basis of the planned or authorized cross section for embankments as shown on the plans and the measured ground surface.
- B. The Contractor, at the Contractor's option, may compact the ground surface on which embankment is to be constructed before placing any embankment thereon. If the compaction results in an average subsidence exceeding 0.25-foot, the ground surface will be measured after completion of the compaction. The Engineer shall be allowed the time necessary to complete the measurement of an area before placement of embankment is started in that area.
- C. The quantities of roadway excavation, structure excavation and ditch excavation, which have been used in the embankment, will be adjusted by multiplying by a specified grading factor of 0.9. No further adjustment will be made in the event that the specified grading factor does not equal the actual grading factor.
- E. The Contractor may propose a plan whereby the Contractor would be paid on the basis of measured settlement in lieu of the allowance specified above. The proposal shall include complete details of the subsidence-measuring devices and a detailed plan of each installation. If the proposed plan is approved by the Engineer, the Contractor, at the Contractor's expense, shall provide, install and maintain the subsidence-measuring devices. The Engineer will take necessary readings to determine the progress of subsidence, if any, and the Contractor shall provide necessary assistance to make the readings.
- F. Installed devices which are determined by the Engineer to have been damaged will not be used for the determination of subsidence for the area the devices represent in the pattern of approved installations. The subsidence of the area represented by that installation shall be considered zero, regardless of the subsidence measured at other installations.
- G. The volumes required as a result of subsidence will be computed by the average-end-area method from the original measurements and the final measurements, including zero subsidence at all points and for all areas as provided herein. It shall be understood and agreed that the subsidence at the point of intersection of the side slopes (and end slopes at structures) with the ground line as established by the original cross sections shall be considered as zero. Unless otherwise agreed to by the Engineer, the subsidence shall be considered as zero at the points on the cross sections 50 feet beyond the beginning and ending of the instrumented area. The computed volumes for such subsidence will be added to the quantities of embankment measured as specified herein.
- H. Detachable elements of the subsidence-measuring devices which can be salvaged without damage to the work shall remain the property of the Contractor and shall be removed from the highway right of way after final measurements are made.

10-1.22 EROSION CONTROL (TYPE D)

Erosion control (Type D) includes applying erosion control materials to embankment and excavation slopes and other areas disturbed by construction activities. Erosion control (Type D) must comply with Section 20-3, "Erosion Control," of the Standard Specifications and these special provisions.

If the slope on which the erosion control to be placed is finished during the rainy season as specified under "Water Pollution Control" of these special provisions, apply erosion control to the slope immediately.

Before applying erosion control materials, prepare soil surface under Section 19-2.05, "Slopes," of the Standard Specifications, except that rills and gullies exceeding 2 inches in depth or width must be leveled. Remove vegetative growth, temporary erosion control materials, and other debris from areas to receive erosion control.

MATERIALS

Materials must comply with Section 20-2, "Materials," of the Standard Specifications and these special provisions.

Seed

Seed must comply with Section 20-2.10, "Seed," of the Standard Specifications. Seed not required to be labeled under the California Food and Agricultural Code shall be tested for purity and germination by a seed laboratory certified by the Association of Official Seed Analysts or by a seed technologist certified by the Society of Commercial Seed Technologists. Measure and mix individual seed species in the presence of the Engineer.

Seed must contain at most 1.0 percent total weed seed by weight.

Deliver seed to the job site in unopened separate containers with the seed tag attached. Containers without a seed tag attached are not accepted. The Engineer takes a sample of approximately 1 ounce or 0.25 cup of seed for each seed lot greater than 2 pounds.

Seed must comply with the following:

Seed		
Botanical Name (Common Name)	Percent Germination (Minimum)	Pounds Pure Live Seed Per Acre (Slope Measurement)
Elymus glaucus (Blue Wildrye, Berkeley)	40	10
Eschscholzia californica (California Poppy)	35	1.5
Hordeum vulgare var UC603 (Barley UC603)	50	62
Nassella pulchra (Purple Needlegrass)	35	10

Seed Sampling Supplies

At the time of seed sampling, provide the Engineer a glassine lined bag and custody seal tag for each seed lot sample.

Straw

Straw must comply with Section 20-2.06, "Straw," of the Standard Specifications and these special provisions.

Straw must be derived from rice.

Straw must be free of plastic, glass, metal, rocks, and refuse or other deleterious material.

Compost

The compost producer must be fully permitted as specified under the California Integrated Waste Management Board, Local Enforcement Agencies and any other State and Local Agencies that regulate Solid Waste Facilities. If exempt from State permitting requirements, the composting facility must certify that it follows guidelines and procedures for production of compost meeting the environmental health standards of Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7.

The compost producer must be a participant in United States Composting Council's Seal of Testing Assurance program.

Compost may be derived from any single, or mixture of any of the following feedstock materials:

1. Green material consisting of chipped, shredded, or ground vegetation; or clean processed recycled wood products
2. Biosolids
3. Manure
4. Mixed food waste

Compost feedstock materials to reduce weed seeds, pathogens and deleterious materials as specified under Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7, Section 17868.3

Compost must not be derived from mixed municipal solid waste and must be reasonably free of visible contaminants. Compost must not contain paint, petroleum products, pesticides or any other chemical residues harmful to animal life or plant growth. Compost must not possess objectionable odors.

Metal concentrations in compost must not exceed the maximum metal concentrations listed in Title 14, California Code of Regulations, Division 7, Chapter 3.1, Section 17868.2.

Compost must comply with the following:

Physical/Chemical Requirements

Property	Test Method	Requirement
pH	*TMECC 04.11-A, Elastometric pH 1:5 Slurry Method, pH Units	6.0–8.0
Soluble Salts	TMECC 04.10-A, Electrical Conductivity 1:5 Slurry Method dS/m (mmhos/cm)	0-10.0
Moisture Content	TMECC 03.09-A, Total Solids & Moisture at 70+/- 5 deg C, % Wet Weight Basis	N/A
Organic Matter Content	TMECC 05.07-A, Loss-On-Ignition Organic Matter Method (LOI), % Dry Weight Basis	30–65
Maturity	TMECC 05.05-A, Germination and Vigor Seed Emergence Seedling Vigor % Relative to Positive Control	80 or Above 80 or Above
Stability	TMECC 05.08-B, Carbon Dioxide Evolution Rate mg CO ₂ -C/g OM per day	8 or below
Particle Size	TMECC 02.02-B Sample Sieving for Aggregate Size Classification % Dry Weight Basis	95% Passing 5/8 inch 70% Passing 3/8 inch
Pathogen	TMECC 07.01-B, Fecal Coliform Bacteria < 1000 MPN/gram dry wt.	Pass
Pathogen	TMECC 07.01-B, Salmonella < 3 MPN/4 grams dry wt.	Pass
Physical Contaminants	TMECC 02.02-C, Man Made Inert Removal and Classification: Plastic, Glass and Metal, % > 4mm fraction	Combined Total: < 1.0
Physical Contaminants	TMECC 02.02-C, Man Made Inert Removal and Classification: Sharps (Sewing needles, straight pins and hypodermic needles), % > 4mm fraction	None Detected

*TMECC refers to "Test Methods for the Examination of Composting and Compost," published by the United States Department of Agriculture and the United States Compost Council (USCC).

Before compost application, provide the Engineer with a copy of the compost producer's compost technical data sheet and a copy of the compost producers Seal of Testing Assurance certification. The compost technical data sheet includes:

1. Laboratory analytical test results
2. Directions for product use
3. List of product ingredients

Before compost application, provide the Engineer with a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Stabilizing Emulsion

Stabilizing emulsion must comply with Section 20-2.11, "Stabilizing Emulsion," of the Standard Specifications and these special provisions.

Stabilizing emulsion:

1. Must be in a dry powder form
2. Must be a processed organic adhesive used as a soil tackifier
3. May be reemulsifiable

APPLICATION

Apply erosion control materials in separate applications in the following sequence:

1. Apply the following mixture with hydroseeding equipment at the rates indicated within 60 minutes after the seed has been added to the mixture:

Material	Pounds Per Acre (Slope Measurement)
Seed	83.5
Fiber	285

Material	Cubic Yards Per Acre (Slope Measurement)
Compost	4

2. Compost may be dry applied at the total of the rates specified in the preceding table and the following table instead of including it as part of the hydro-seeding operations. In areas where the compost is dry applied, all compost for that area must be applied before the next operation.
3. Apply straw at the rate of 2.0 tons per acre based on slope measurements. Incorporation of straw will not be required. Distribute straw evenly without clumping or piling.
4. Apply the following mixture with hydro-seeding equipment at the corresponding rates:

Material	Pounds Per Acre (Slope Measurement)
Fiber	285
Stabilizing Emulsion (Solids)	125

Material	Cubic Yards Per Acre (Slope Measurement)
Compost	4

The ratio of total water to total stabilizing emulsion in the mixture must be as recommended by the manufacturer. Once straw work is started in an area, complete stabilizing emulsion applications in that area on the same working day. The Engineer may change the rates of erosion control materials to meet field conditions.

MEASUREMENT AND PAYMENT

Erosion control (Type D) will be measured by the square yard or by the acre, whichever is designated in the Engineer's Estimate. The area will be calculated on the basis of actual or computed slope measurements.

The contract price paid per square yard or acre for erosion control (Type D) includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying erosion control (Type D) complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.23 FIBER ROLLS

Fiber rolls shall be furnished and installed in conformance with details shown on the plans and these special provisions and as directed by the Engineer.

Fiber rolls shall be installed on excavation and embankment slopes and other disturbed soil areas.

At the option of the Contractor, fiber rolls shall be Type 1 or Type 2.

MATERIALS

Fiber Roll

Fiber roll shall be either:

1. Constructed with a premanufactured blanket consisting of either wood excelsior, rice or wheat straw, or coconut fibers or a combination of these materials. The blanket shall be between 6 feet and 8 feet in width and between 65 feet and 95 feet in length. Wood excelsior shall be individual fibers, of which 80 percent shall be 6 inches or longer in length. The blanket shall have a photodegradable plastic netting or biodegradable jute, sisal, or coir fiber netting on at least one side. The blanket shall be rolled along the width and secured with jute twine spaced 6 feet apart along the full length of the roll and placed 6 inches from the ends of each roll. The finished roll shall be between 8 inches and 10 inches in diameter, a minimum of 20 feet in length, and shall weigh a minimum of 0.5 pound per linear foot. More than one blanket may be required to achieve the finished roll diameter. When more than one blanket is required, blankets shall be jointed longitudinally with an overlap of 6 inches along the length of the blanket.
2. A premanufactured roll of rice or wheat straw, wood excelsior, or coconut fiber encapsulated within a photodegradable plastic or biodegradable jute, sisal, or coir fiber netting. The netting shall have a minimum durability of one year after installation. The netting shall be secured tightly at each end of the roll. Rolls shall be between 8 inches and 12 inches in diameter. Rolls between 8 inches and 10 inches in diameter shall have a minimum weight of 1 pound per linear foot and a minimum length of 20 feet. Rolls between 10 inches and 12 inches in diameter shall have a minimum weight of 3 pounds per linear foot and a minimum length of 10 feet.

Stakes

Wood stakes shall be a minimum of 1" x 1" x 24" in size for Type 1 installation, or a minimum of 1" x 2" x 24" in size for Type 2 installation. Wood stakes shall be untreated fir, redwood, cedar, or pine and cut from sound timber. They shall be straight and free of loose or unsound knots and other defects which would render them unfit for the purpose intended. Metal stakes shall not be used.

Rope

Rope shall be biodegradable, such as sisal or manila, with a minimum diameter of 1/4 inch.

INSTALLATION

Fiber rolls shall be installed as follows:

1. Fiber rolls (Type 1): Furrows shall be constructed to a depth between 2 inches and 4 inches, and to a sufficient width to hold the fiber roll. Stakes shall be installed 24 inches apart along the length of the fiber rolls and stopped at 12 inches from each end of the rolls. Stakes shall be driven to a maximum of 2 inches above, or flush with the top of the roll.
2. Fiber rolls (Type 2): Rope and notched stakes shall be used to restrain the fiber rolls against the slope. Stakes shall be driven into the slope until the notch is even with the top of the fiber roll. Rope shall be knotted at each stake and laced between stakes. After installation of the rope, stakes shall be driven into the slope such that the rope will hold the fiber roll tightly to the slope. Furrows will not be required.
3. Fiber rolls shall be placed as shown on the plans.
4. The bedding area for the fiber rolls shall be cleared of obstructions including rocks, clods, and debris greater than one inch in diameter before installation.
5. Fiber rolls shall be installed approximately parallel to the slope contour.
6. Fiber rolls shall be installed before the application of other erosion control or soil stabilization materials in the same area.

If the intended function of the fiber rolls to disperse concentrated water runoff and to reduce runoff velocities is impaired, the Contractor shall take action to repair or replace the fiber rolls. Split, torn, or unraveling rolls shall be repaired or replaced. Broken or split stakes shall be replaced. Sagging or slumping fiber rolls shall be repaired with additional stakes or replaced. Locations where rills and other evidence of concentrated runoff have occurred beneath the rolls shall be corrected. Fiber rolls shall be repaired or replaced within 24 hours of identifying the deficiency.

MEASUREMENT AND PAYMENT

Quantities of fiber rolls to be paid for will be determined by the linear foot measured along the centerline of the installed roll. Where fiber rolls are joined and overlapped, the overlap will be measured as a single installed roll.

The contract price paid per linear foot for fiber roll shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing fiber rolls, complete in place, including furrow excavation and backfill, repairing or replacing fiber rolls as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Damage to fiber rolls resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

10-1.24 IRRIGATION CROSSOVERS

Irrigation crossovers shall conform to the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications and these special provisions.

Conduits shall be placed in open trenches in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

Conduits shall be corrugated high density polyethylene (CHDPE) pipe. Corrugated high density polyethylene pipe shall conform to the requirements in ASTM Designation: F 405 or F 667, or AASHTO Designation: M 252 or M 294 and shall be Type S. Couplings and fittings shall be as recommended by the pipe manufacturer.

Water line crossovers shall conform to the provisions in Section 20-5.03C, "Water Line Crossovers," of the Standard Specifications.

Sprinkler control crossovers shall conform to the provisions in Section 20-5.027D, "Sprinkler Control Crossovers," of the Standard Specifications.

Installation of pull boxes will not be required.

10-1.25 IRRIGATION SLEEVE

Irrigation sleeves shall be polyvinyl chloride (PVC) plastic pipe and shall conform to the provisions in Section 20-2.15B(1), "Plastic Pipe Supply Line," of the Standard Specifications and these special provisions.

Irrigation sleeves less than 6 inches in diameter shall have a pressure rating (PR) 315.

Irrigation sleeves 6 inches or larger in diameter shall be Schedule 40.

Fittings shall be Schedule 40.

Irrigation sleeves shall be installed where shown on the plans.

Irrigation sleeves shall be installed not less than 1.5 feet below finished grade measured to the top of the sleeve. Sleeves shall extend 6 inches beyond paving. The ends of the sleeve shall be capped until use.

Water line crossovers shall conform to the provisions in Section 20-5.03C, "Water Line Crossovers," of the Standard Specifications. Size of waterline crossover in sleeves shall be as shown on the irrigation plan sheets. The ends of the water line crossover, not immediately connected to irrigation system shall be brought to finished grade and capped until use.

Quantities of irrigation sleeve to be paid will be determined from the slope length designated by the Engineer. Irrigation sleeve placed in excess of the lengths designated will not be paid for.

The contract price paid per linear foot for irrigation sleeve shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in irrigation sleeve, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.26 DECOMPOSED GRANITE

Decomposed granite work shall consist of furnishing, stabilizing, and placing decomposed granite, including site preparation and edging, as shown on the plans and in conformance with these special provisions, and as directed by the Engineer.

MATERIALS

Decomposed Granite

Decomposed granite shall be 1/4" minus material and shall conform to the following:

Grading Requirements (AASHTO T11-82 and T27-82)

Sieve Size	Percent Passing
3/8"	100
No. 4	95-100
No. 8	75-80
No. 16	55-65
No. 30	40-50
No. 50	25-35
No. 100	20-25
No. 200	5-15

The color of decomposed granite shall be gold, tan or light brown.

The Contractor shall submit a 4 lb sample of decomposed granite to the Engineer for approval prior to delivery of materials to the site.

Landscape Fabric

Landscape fabric shall be manufactured from thermally spun bonded polypropylene fabric and shall conform to the following:

Specification	Minimum Requirement
Grab Tensile Strength	130 lb
Grab Elongation	60%
UV Resistance	70% @ 150 hours
Mass	4.3 oz/sqyd

A copy of the manufacturers product sheet together with instructions for installation shall be furnished to the Engineer 5 days before installation.

Staples

Staples shall be 2" wide, 8" in length, and 11 gauge wire.

Solidifying Emulsion

Solidifying emulsion shall be either a water-based polymer, or organic powdered binder specifically manufactured to harden decomposed granite. The solidifying emulsion shall not alter the decomposed granite color. A copy of the manufacturers product sheets together with instructions for application shall be furnished to the Engineer 5 days before application.

A Certificate of Compliance for the solidifying emulsion shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Edging

Edging shall be construction grade lumber, including stakes, and shall conform to sections 20-2.12, "Lumber," and 20-4.04, "Header Boards," of the Standard Specifications.

Edging shall be a minimum nominal 1 x 4. Stakes shall be 1" x 1-1/4" x 12 inches in length.

TEST PLOTS

Decomposed granite for the permanent work shall not be placed on the project prior to approval by the Engineer of a test plots prepared by the Contractor. The Contractor shall construct a test plot at least 3 feet by 6 feet at the site of the same materials proposed for the permanent work.

Additional test plots shall be constructed as directed by the Engineer until a plot is produced which conforms to the requirements herein. In the event more than one test plot is required by the Engineer, each additional test plot will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

SITE PREPARATION

Clearing

Areas to receive decomposed granite shall be cleared of trash and debris. Vegetation shall be removed to the ground. Cleared trash, debris and removed vegetation shall be disposed outside the highway right of way in conformance with Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Prior to decomposed granite installation, the areas shall be cleared as specified under "Clearing and Grubbing" in these special provisions.

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

After clearing, areas to receive landscape fabric shall be excavated to the depth shown on the plans. Where landscape fabric is to be placed adjacent to an existing curb or dike, the subgrade shall be excavated such that the finished landscape fabric elevation adjacent to curb or dike will maintain planned flow lines, slope gradient and contours of the project site. After excavation, areas to receive landscape fabric shall be graded to a smooth, uniform surface and compacted to not less than 90% relative compaction.

Surplus excavated material shall become the property of the Contractor and shall be disposed of outside the highway right of way in conformance with Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Prior to placement of decomposed granite, the soil surface shall be smooth, firm stable and free of rocks, clods, foliage, roots or other material greater than 1 inch in diameter.

PLACEMENT

Landscape fabric shall be placed in areas to receive decomposed granite as recommended by the manufacturer and as specified in these special provisions. Landscape fabric shall be placed loosely with longitudinal and transverse joints overlapped 4 inches and stapled to the subgrade at 6 inches on center. Staples shall be driven perpendicular to the ground surface. Following placement, the fabric shall lay flat, smooth and be in uniform contact with the soil surface, without bulges or wrinkles.

Edging shall be installed to delineate the limits of the decomposed granite areas as shown on the plans and as specified in these special provisions. Edging will not be required between decomposed granite areas and the adjacent face of soundwalls, pavement edges, or rock blanket areas.

Decomposed granite shall be placed in two 1-1/2" layers.

Each layer of decomposed granite shall be raked to evenly blend various material, sizes forming a smooth uniform surface. Decomposed granite shall be moistened sufficiently to obtain the required compaction. Each layer of decomposed granite shall be brought to a relative compaction of not less than 90 percent by compaction equipment such as a double drum roller, single drum roller, or vibratory tamp. After placement of decomposed granite, compaction shall not begin less than 6 hours after placement, nor later than 48 hours.

Decomposed granite areas shall receive a final application of solidifying emulsion as recommended by the manufacturer. The Contractor shall prevent runoff or overspray of solidifying emulsion onto adjacent paved or planting areas.

When work is complete, the surface shall be smooth and uniform; maintaining original flow lines, slope gradient and contours of the project site.

Every 365 days after installation, a dilute topcoat of solidifying emulsion shall be applied at the same rate as the final application at installation, or as otherwise recommended by the manufacturer.

If the top surface of the decomposed granite has in excess of 1/4" of loose aggregate, the loose material shall be redistributed evenly over the surface. These decomposed granite areas shall be moistened to a depth of 1 inch and compacted with a 1200 pound power roller. A dilute top coat of solidifying emulsion shall be applied at the same rate used for the final application at installation or as recommended by the manufacturer.

If cracks develop in the surface of the decomposed granite, loose fines shall be swept into the cracks, watered thoroughly and hand tamped. A final top coat of solidifying emulsion shall be applied at the same rate used for the final application at installation or as recommended by the manufacturer.

MEASUREMENT

Decomposed granite will be measured by the square yard as determined from actual measurements made parallel to the ground slope.

PAYMENT

The contract unit price paid per square yard for decomposed granite shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in decomposed granite, complete in place, including earthwork and test plot as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.27 AGGREGATE BASE

Aggregate base must comply with Section 26, "Aggregate Bases," of the Standard Specifications and these special provisions.

Aggregate base must be Class 3.

Do not store reclaimed asphalt concrete or aggregate base with reclaimed asphalt concrete within 100 feet measured horizontally of any culvert, watercourse, or bridge.

Class 3 aggregate base must comply with:

Grading (Percentage Passing)

Sieve Sizes	1-1/2 inch Maximum		3/4 inch Maximum	
	Operating Range	Contract Compliance	Operating Range	Contract Compliance
2"	100	100		
1-1/2"	90-100	87-100		
1"	----	----	100	100
3/4"	50-85	45-90	90-100	87-100
No. 4	24-45	20-50	35-60	30-65
No. 30	10-25	6-29	10-30	5-35
No. 200	2-11	0-14	2-11	0-14

Quality

Tests	Operating Range	Contract Compliance
Sand Equivalent	25 Min.	22 Min.
Resistance (R-value)	----	78 Min.
Durability Index		35 min

Do not treat aggregate with lime, cement, or other chemical material before the Department performs the Durability Index test. The Engineer does not consider any untreated reclaimed asphalt concrete and portland cement concrete to be treated with lime, cement, or other chemical material for purposes of performing the Durability Index test.

If tests show grading or sand equivalent does not comply with the "Operating Range" specifications but complies with the "Contract Compliance" specifications, you may place aggregate base for the remainder of that day. Do not start another day's work until tests or other information indicate the next day's material complies with the "Operating Range" specifications.

If tests show grading or sand equivalent does not comply with the "Contract Compliance" specifications, remove the aggregate base represented by the tests. If you request and the Engineer approves, that aggregate base may remain in place and the Department reduces payment by \$2.25 per cubic yard for that aggregate base. If both the grading and sand equivalent do not comply with "Contract Compliance" specifications and the base remains in place, the Department only makes one payment reduction.

No single grading or sand equivalent test may represent more than the smaller of 500 cubic yards or one day's production.

The Engineer converts tons to cubic yards for the purpose of reducing payment for noncompliant aggregate base left in place.

The maximum compacted thickness of any 1 layer of aggregate base must not exceed 0.7 foot.

10-1.28 PILING

GENERAL

Piling shall conform to the provisions in Section 49, "Piling," of the Standard Specifications, and these special provisions.

Unless otherwise specified, welding of any work performed in conformance with the provisions in Section 49, "Piling," of the Standard Specifications, shall be in conformance with the requirements in AWS D1.1.

CAST-IN-DRILLED-HOLE CONCRETE PILES

Cast-in-drilled-hole concrete piling shall conform to the provisions in Section 49-4, "Cast-In-Place Concrete Piles," of the Standard Specifications and these special provisions.

The provisions of "Welding" of these special provisions shall not apply to temporary steel casings.

Cast-in-drilled-hole concrete piles 24 inches in diameter or larger may be constructed by excavation and depositing concrete under slurry.

Materials

Concrete deposited under slurry shall have a nominal penetration equal to or greater than 3-1/2 inches. Concrete shall be proportioned to prevent excessive bleed water and segregation.

Concrete deposited under slurry shall contain not less than 675 pounds of cementitious material per cubic yard.

The combined aggregate grading used in concrete for cast-in-drilled-hole concrete piling shall be either the one-inch maximum grading, the 1/2-inch maximum grading, or the 3/8-inch maximum grading and shall conform to the requirements in Section 90-3, "Aggregate Gradings," of the Standard Specifications.

Mineral Slurry

Mineral slurry shall be mixed and thoroughly hydrated in slurry tanks, and slurry shall be sampled from the slurry tanks and tested before placement in the drilled hole.

Slurry shall be recirculated or continuously agitated in the drilled hole to maintain the specified properties.

Recirculation shall include removal of drill cuttings from the slurry before discharging the slurry back into the drilled hole. When recirculation is used, the slurry shall be sampled and tested at least every 2 hours after beginning its use until tests show that the samples taken from the slurry tank and from near the bottom of the hole have consistent specified properties. Subsequently, slurry shall be sampled at least twice per shift as long as the specified properties remain consistent.

Slurry that is not recirculated in the drilled hole shall be sampled and tested at least every 2 hours after beginning its use. The slurry shall be sampled mid-height and near the bottom of the hole. Slurry shall be recirculated when tests show that the samples taken from mid-height and near the bottom of the hole do not have consistent specified properties.

Slurry shall also be sampled and tested before final cleaning of the bottom of the hole and again just before placing concrete. Samples shall be taken from mid-height and near the bottom of the hole. Cleaning of the bottom of the hole and placement of the concrete shall not start until tests show that the samples taken from mid-height and near the bottom of the hole have consistent specified properties.

Mineral slurry shall be tested for conformance to the requirements shown in the following table:

MINERAL SLURRY		
PROPERTY	REQUIREMENT	TEST
Density (pcf) - before placement in the drilled hole - during drilling - before final cleaning - immediately before placing concrete	64.3* to 69.1* 64.3* to 75.0*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/quart) bentonite attapulgate	28 to 50 28 to 40	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8 to 10.5	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - before final cleaning - immediately before placing concrete	less than or equal to 4.0	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 2 pcf. Slurry temperature shall be at least 40°F when tested.		

Any caked slurry on the sides or bottom of hole shall be removed before placing reinforcement. If concrete is not placed immediately after placing reinforcement, the reinforcement shall be removed and cleaned of slurry, the sides of the drilled hole cleaned of caked slurry, and the reinforcement again placed in the hole for concrete placement.

Synthetic Slurry

Synthetic slurries shall be used in conformance with the manufacturer's recommendations and these special provisions. The following synthetic slurries may be used:

PRODUCT	MANUFACTURER
SlurryPro CDP	KB Technologies Ltd. 3648 FM 1960 West Suite 107 Houston, TX 77068 (800) 525-5237
Super Mud	PDS Company c/o Champion Equipment Company 8140 East Rosecrans Ave. Paramount, CA 90723 (562) 634-8180
Shore Pac GCV	CETCO Drilling Products Group 1350 West Shure Drive Arlington Heights, IL 60004 (847) 392-5800
Novagel Polymer	Geo-Tech Drilling Fluids 220 N. Zapata Hwy, Suite 11A Laredo, TX 78043 (210) 587-4758

Inclusion of a synthetic slurry on the above list may be obtained by meeting the Department's requirements for synthetic slurries. The requirements can be obtained from the Offices of Structures Design, P.O. Box 168041, MS# 9-4/11G, Sacramento, CA 95816-8041.

Synthetic slurries listed may not be appropriate for a given site.

Synthetic slurries shall not be used in holes drilled in primarily soft or very soft cohesive soils as determined by the Engineer.

A manufacturer's representative, as approved by the Engineer, shall provide technical assistance for the use of their product, shall be at the site before introduction of the synthetic slurry into a drilled hole, and shall remain at the site until released by the Engineer.

Synthetic slurries shall be sampled and tested at both mid-height and near the bottom of the drilled hole. Samples shall be taken and tested during drilling as necessary to verify the control of the properties of the slurry. Samples shall be taken and tested when drilling is complete, but before final cleaning of the bottom of the hole. When samples are in conformance with the requirements shown in the following tables for each slurry product, the bottom of the hole shall be cleaned and any loose or settled material removed. Samples shall be obtained and tested after final cleaning and immediately before placing concrete.

SlurryPro CDP synthetic slurries shall be tested for conformance to the requirements shown in the following table:

SLURRYPRO CDP KB Technologies Ltd.		
PROPERTY	REQUIREMENT	TEST
Density (pcf) - during drilling - before final cleaning - just before placing concrete	less than or equal to 67.0* less than or equal to 64.0*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/quart) - during drilling -before final cleaning - just before placing concrete	50 to 120 less than or equal to 70	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	6 to 11.5	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - before final cleaning - just before placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 2 pcf. Slurry temperature shall be at least 40°F when tested.		

Super Mud synthetic slurries shall be tested for conformance to the requirements shown in the following table:

SUPER MUD PDS Company		
PROPERTY	REQUIREMENT	TEST
Density (pcf) - before final cleaning - just before placing concrete	less than or equal to 64.0*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/quart) - during drilling - before final cleaning - just before placing concrete	32 to 60 less than or equal to 60	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8 to 10.0	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - before final cleaning -just before placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 2 pcf. Slurry temperature shall be at least 40°F when tested.		

Shore Pac GCV synthetic slurries shall be tested for conformance to the requirements shown in the following table:

Shore Pac GCV CETCO Drilling Products Group		
PROPERTY	REQUIREMENT	TEST
Density (pcf) - before final cleaning - just before placing concrete	less than or equal to 64.0*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/quart) - during drilling - before final cleaning - just before placing concrete	33 to 74 less than or equal to 57	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8.0 to 11.0	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - before final cleaning -just before placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 2 pcf. Slurry temperature shall be at least 40°F when tested.		

Novagel Polymer synthetic slurries shall be tested for conformance to the requirements shown in the following table:

NOVAGEL POLYMER Geo-Tech Drilling Fluids		
PROPERTY	REQUIREMENT	TEST
Density (pcf) - during drilling - before final cleaning - just before placing concrete	less than or equal to 67.0* less than or equal to 64.0*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/quart) - during drilling - before final cleaning - just before placing concrete	45 to 104 less than or equal to 104	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	6.0 to 11.5	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - before final cleaning - just before placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 2 pcf. Slurry temperature shall be at least 40°F when tested.		

Water Slurry

At the option of the Contractor, water may be used as slurry when casing is used for the entire length of the drilled hole. Water slurry shall be tested for conformance to the requirements shown in the following table:

WATER SLURRY		
PROPERTY	REQUIREMENT	TEST
Density (pcf) - before final cleaning - just before placing concrete	63.5*	Mud Weight (Density) API 13B-1 Section 1
Sand Content (percent) - before final cleaning - just before placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, salt water slurry may be used and the allowable densities may be increased up to 2 pcf.		

Construction

The Contractor shall submit a placing plan to the Engineer for approval prior to producing the test batch for cast-in-drilled-hole concrete piling and at least 10 working days prior to constructing piling. The plan shall include complete descriptions, details, and supporting calculations as listed below:

A. Requirements for all cast-in-drilled-hole concrete piling:

1. Concrete mix design, certified test data, and trial batch reports.
2. Drilling or coring methods and equipment.
3. Proposed method for casing installation and removal when necessary.
4. Plan view drawing of pile showing reinforcement and inspection pipes, if required.
5. Methods for placing, positioning, and supporting bar reinforcement.
6. Methods and equipment for accurately determining the depth of concrete and actual and theoretical volume placed, including effects on volume of concrete when any casings are withdrawn.
7. Methods and equipment for verifying that the bottom of the drilled hole is clean prior to placing concrete.
8. Methods and equipment for preventing upward movement of reinforcement, including the Contractor's means of detecting and measuring upward movement during concrete placement operations.

B. Additional requirements when concrete is placed under slurry:

1. Concrete batching, delivery, and placing systems, including time schedules and capacities therefor. Time schedules shall include the time required for each concrete placing operation at each pile.
2. Concrete placing rate calculations. When requested by the Engineer, calculations shall be based on the initial pump pressures or static head on the concrete and losses throughout the placing system, including anticipated head of slurry and concrete to be displaced.
3. Suppliers' test reports on the physical and chemical properties of the slurry and any proposed slurry chemical additives, including Material Safety Data Sheet.
4. Slurry testing equipment and procedures.
5. Methods of removal and disposal of excavation, slurry, and contaminated concrete, including removal rates.
6. Methods and equipment for slurry agitating, recirculating, and cleaning.

In addition to compressive strength requirements, the consistency of the concrete to be deposited under slurry shall be verified before use by producing a test batch. The test batch shall be produced and delivered to the project under conditions and in time periods similar to those expected during the placement of concrete in the piles. Concrete for the test batch shall be placed in an excavated hole or suitable container of adequate size to allow for testing as specified herein. Depositing of test batch concrete under slurry will not be required. In addition to meeting the specified nominal penetration, the test batch shall meet the following requirements:

- A. For piles where the time required for each concrete placing operation, as submitted in the placing plan, will be 2 hours or less, the test batch shall demonstrate that the proposed concrete mix design achieves either a penetration of at least 2 inches or a slump of at least 5 inches after twice that time has elapsed.
- B. For piles where the time required for each concrete placing operation, as submitted in the placing plan, will be more than 2 hours, the test batch shall demonstrate that the proposed concrete mix design achieves either a penetration of at least 2 inches or a slump of at least 5 inches after that time plus 2 hours has elapsed.

The time period shall begin at the start of placement. The concrete shall not be vibrated or agitated during the test period. Penetration tests shall be performed in conformance with the requirements in California Test 533. Slump tests shall be performed in conformance with the requirements in ASTM Designation: C 143/C143M. Upon completion of testing, the concrete shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The concrete deposited under slurry shall be carefully placed in a compact, monolithic mass and by a method that will prevent washing of the concrete. Concrete deposited under slurry need not be vibrated. Placing concrete shall be a continuous operation lasting not more than the time required for each concrete placing operation at each pile, as submitted in the placing plan, unless otherwise approved in writing by the Engineer. The concrete shall be placed with concrete pumps and delivery tube system of adequate number and size to complete the placing of concrete in the time specified. The delivery tube system shall consist of one of the following:

- A. A tremie tube or tubes, each of which are at least 10 inches in diameter, fed by one or more concrete pumps.
- B. One or more concrete pump tubes, each fed by a single concrete pump.

The delivery tube system shall consist of watertight tubes with sufficient rigidity to keep the ends always in the mass of concrete placed. If only one delivery tube is utilized to place the concrete, the tube shall be placed near the center of the drilled hole. Multiple tubes shall be uniformly spaced in the hole. Internal bracing for the steel reinforcing cage shall accommodate the delivery tube system. Tremies shall not be used for piles without space for a 10-inch tube.

Spillage of concrete into the slurry during concrete placing operations shall not be allowed. Delivery tubes shall be capped with a watertight cap, or plugged above the slurry level with a good quality, tight fitting, moving plug that will expel the slurry from the tube as the tube is charged with concrete. The cap or plug shall be designed to be released as the tube is charged. The pump discharge or tremie tube shall extend to the bottom of the hole before charging the tube with concrete. After charging the delivery tube system with concrete, the flow of concrete through a tube shall be induced by slightly raising the discharge end. During concrete placement, the tip of the delivery tube shall be maintained as follows to prevent reentry of the slurry into the tube. Until at least 10 feet of concrete has been placed, the tip of the delivery tube shall be within 6 inches of the bottom of the drilled hole, and then the embedment of the tip shall be maintained at least 10 feet below the top surface of the concrete. Rapid raising or lowering of the delivery tube shall not be permitted. If the seal is lost or the delivery tube becomes plugged and must be removed, the tube shall be withdrawn, the tube cleaned, the tip of the tube capped to prevent entrance of the slurry, and the operation restarted by pushing the capped tube 10 feet into the concrete and then reinitiating the flow of concrete.

When slurry is used, a fully operational standby concrete pump, adequate to complete the work in the time specified, shall be provided at the site during concrete placement. The slurry level shall be maintained within 12 inches of the top of the drilled hole.

A log of concrete placement for each drilled hole shall be maintained by the Contractor when concrete is deposited under slurry. The log shall show the pile location, tip elevation, dates of excavation and concrete placement, total quantity of concrete deposited, length and tip elevation of any casing, and details of any hole stabilization method and materials used. The log shall include a 8-1/2" x 11" sized graph of the concrete placed versus depth of hole filled. The graph shall be plotted continuously throughout placing of concrete. The depth of drilled hole filled shall be plotted vertically with the pile tip oriented at the bottom and the quantity of concrete shall be plotted horizontally. Readings shall be made at least at each 5 feet of pile depth, and the time of the reading shall be indicated. The graph shall be labeled with the pile location, tip elevation, cutoff elevation, and the dates of excavation and concrete placement. The log shall be delivered to the Engineer within one working day of completion of placing concrete in the pile.

After placing reinforcement and prior to placing concrete in the drilled hole, if drill cuttings settle out of the slurry, the bottom of the drilled hole shall be cleaned. The Contractor shall verify that the bottom of the drilled hole is clean.

If temporary casing is used, concrete placed under slurry shall be maintained at a level at least 5 feet above the bottom of the casing. The withdrawal of casings shall not cause contamination of the concrete with slurry.

Material resulting from using slurry shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Acceptance Testing and Mitigation

Vertical inspection pipes for acceptance testing shall be provided in all cast-in-drilled-hole concrete piles that are 24 inches in diameter or larger, except when the holes are dry or when the holes are dewatered without the use of temporary casing to control ground water.

Inspection pipes shall be Schedule 40 polyvinyl chloride pipes with a nominal inside diameter of 2 inches. Each inspection pipe shall be capped top and bottom and shall have watertight couplers to provide a clean, dry and unobstructed 2-inch-diameter clear opening from 3 feet above the pile cutoff down to the bottom of the reinforcing cage.

Inspection pipes shall be placed around the pile, inside the outermost spiral or hoop reinforcement, and 3 inches clear of the vertical reinforcement, at a uniform spacing not exceeding 2 feet 9 inches measured along the circle passing through the centers of inspection pipes. A minimum of 2 inspection pipes per pile shall be used. When the vertical reinforcement is not bundled and each bar is not more than one inch in diameter, inspection pipes may be placed 2 inches clear of the vertical reinforcement. The inspection pipes shall be placed to provide the maximum diameter circle that passes through the centers of the inspection pipes while maintaining the clear spacing required herein. The pipes shall be installed in straight alignment, parallel to the main reinforcement, and securely fastened in place to prevent misalignment during installation of the reinforcement and placing of concrete in the hole.

The Contractor shall log the location of the inspection pipe couplers with respect to the plane of pile cut off, and these logs shall be delivered to the Engineer upon completion of the placement of concrete in the drilled hole.

After placing concrete and before requesting acceptance tests, each inspection pipe shall be tested by the Contractor in the presence of the Engineer by passing a 1.9-inch-diameter rigid cylinder 2 feet long through the complete length of pipe. If the 1.9-inch-diameter rigid cylinder fails to pass any of the inspection pipes, the Contractor shall attempt to pass a 1-1/4-inch-diameter rigid cylinder 4.5 feet long through the complete length of those pipes in the presence of the Engineer. If an inspection pipe fails to pass the 1-1/4-inch-diameter cylinder, the Contractor shall immediately fill all inspection pipes in the pile with water.

The Contractor shall replace each inspection pipe that does not pass the 1-1/4-inch-diameter cylinder with a 2-inch-diameter hole cored through the concrete for the entire length of the pile. Cored holes shall be located as close as possible to the inspection pipes they are replacing and shall be no more than 6 inches inside the reinforcement. Coring shall not damage the pile reinforcement. Cored holes shall be made with a double wall core barrel system utilizing a split tube type inner barrel. Coring with a solid type inner barrel will not be allowed. Coring methods and equipment shall provide intact cores for the entire length of the pile concrete. The coring operation shall be logged by an Engineering Geologist or Civil Engineer licensed in the State of California and experienced in core logging. Coring logs shall include complete descriptions of inclusions and voids encountered during coring, and shall be delivered to the Engineer upon completion. Concrete cores shall be preserved, identified with the exact location the core was recovered from within the pile, and made available for inspection by the Engineer.

Acceptance tests of the concrete will be made by the Engineer, without cost to the Contractor. Acceptance tests will evaluate the homogeneity of the placed concrete. Tests will include gamma-gamma logging. Tests may also include crosshole sonic logging and other means of inspection selected by the Engineer. The Contractor shall not conduct operations within 25 feet of the gamma-gamma logging operations. The Contractor shall separate reinforcing steel as necessary to allow the Engineer access to the inspection pipes to perform gamma-gamma logging or other acceptance testing. After requesting acceptance tests and providing access to the piling, the Contractor shall allow 3 weeks for the Engineer to conduct these tests and make determination of acceptance if the 1.9-inch-diameter cylinder passed all inspection pipes, and 4 weeks if only the 1-1/4-inch-diameter cylinder passed all inspection pipes. Should the Engineer fail to complete these tests within the time allowance, and if in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in inspection, the delay will be considered a right of way delay as specified in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

All inspection pipes and cored holes in a pile shall be dewatered and filled with grout after notification by the Engineer that the pile is acceptable. Placement and removal of water in the inspection pipes shall be at the Contractor's expense. Grout shall conform to the provisions in Section 50-1.09, "Bonding and Grouting," of the Standard Specifications. The inspection pipes and holes shall be filled using grout tubes that extend to the bottom of the pipe or hole or into the grout already placed.

If acceptance testing performed by the Engineer determines that a pile does not meet the requirements of the specifications, then that pile will be rejected and all depositing of concrete under slurry or concrete placed using temporary casing for the purpose of controlling groundwater shall be suspended until written changes to the methods of pile construction are approved in writing by the Engineer.

The Contractor shall submit to the Engineer for approval a mitigation plan for repair, supplementation, or replacement for each rejected cast-in-drilled-hole concrete pile, and this plan shall conform to the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. Prior to submitting this mitigation plan, the Engineer will hold a repair feasibility meeting with the Contractor to discuss the feasibility of repairing rejected piling. The Engineer will consider the size of the defect, the location of the defect, and the design information and corrosion protection considerations for the pile. This information will be made available to the Contractor, if appropriate, for the development of the mitigation plan. If the Engineer determines that it is not feasible to repair the rejected pile, the Contractor shall not include repair as a means of mitigation and shall proceed with the submittal of a mitigation plan for replacement or supplementation of the rejected pile.

If the Engineer determines that a rejected pile does not require mitigation due to structural, geotechnical, or corrosion concerns, the Contractor may elect to 1) repair the pile per the approved mitigation plan, or 2) not repair anomalies found during acceptance testing of that pile. For such unrepaired piles, the Contractor shall pay to the State, \$300 per cubic yard for the portion of the pile affected by the anomalies. The volume, in cubic yards, of the portion of the pile affected by the anomalies, shall be calculated as the area of the cross section of the pile affected by each anomaly, in square yards, as determined by the Engineer, multiplied by the distance, in yards, from the top of each anomaly to the specified tip of the pile. If the volume calculated for one anomaly overlaps the volume calculated for additional anomalies within the pile, the calculated volume for the overlap shall only be counted once. In no case shall the amount of the payment to the State for any such pile be less than \$300. The Department may deduct the amount from any moneys due, or that may become due the Contractor under the contract.

Pile mitigation plans shall include the following:

- A. The designation and location of the pile addressed by the mitigation plan.
- B. A review of the structural, geotechnical, and corrosion design requirements of the rejected pile.
- C. A step by step description of the mitigation work to be performed, including drawings if necessary.
- D. An assessment of how the proposed mitigation work will address the structural, geotechnical, and corrosion design requirements of the rejected pile.
- E. Methods for preservation or restoration of existing earthen materials.
- F. A list of affected facilities, if any, with methods and equipment for protection of these facilities during mitigation.
- G. The State assigned contract number, bridge number, full name of the structure as shown on the contract plans, District-County-Route-Post Mile, and the Contractor's (and Subcontractor's if applicable) name on each sheet.
- H. A list of materials, with quantity estimates, and personnel, with qualifications, to be used to perform the mitigation work.
- I. The seal and signature of an engineer who is licensed as a Civil Engineer by the State of California.

For rejected piles to be repaired, the Contractor shall submit a pile mitigation plan that contains the following additional information:

- A. An assessment of the nature and size of the anomalies in the rejected pile.
- B. Provisions for access for additional pile testing if required by the Engineer.

For rejected piles to be replaced or supplemented, the Contractor shall submit a pile mitigation plan that contains the following additional information:

- A. The proposed location and size of additional piling.
- B. Structural details and calculations for any modification to the structure to accommodate the replacement or supplemental piling.

All provisions for cast-in-drilled-hole concrete piling shall apply to replacement piling.

The Contractor shall allow the Engineer 3 weeks to review the mitigation plan after a complete submittal has been received.

Should the Engineer fail to review the complete pile mitigation submittal within the time specified, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the pile mitigation plan, an extension of time commensurate with the delay in completion of the work thus caused will be granted in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

When repairs are performed, the Contractor shall submit a mitigation report to the Engineer within 10 days of completion of the repair. This report shall state exactly what repair work was performed and quantify the success of the repairs relative to the submitted mitigation plan. The mitigation report shall be stamped and signed by an engineer that is licensed as a Civil Engineer by the State of California. The mitigation report shall show the State assigned contract number, bridge number, full name of the structure as shown on the contract plans, District-County-Route-Post Mile, and the Contractor (and subcontractor if applicable) name on each sheet. The Engineer will be the sole judge as to whether a mitigation proposal is acceptable, the mitigation efforts are successful, and to whether additional repairs, removal and replacement, or construction of a supplemental foundation is required.

10-1.29 MINOR CONCRETE (MINOR STRUCTURE)

Portland cement concrete structure (stairs) shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Full compensation for reinforcing steel bar and vapour barrier (Visqueen) shall be considered as included in the contract price paid for cubic yard of minor concrete (minor concrete) and no additional compensation will be allowed therefor.

10-1.30 STEEL STRUCTURES

Construction of steel structures shall conform to the provisions in Section 55, "Steel Structures," of the Standard Specifications and these special provisions.

Attention is directed to "Welding" in Section 8, "Materials," of these special provisions.

MATERIALS

Structural steel rolled shapes used in electrical light poles shall conform to the Charpy V-notch impact values specified for steel plate in Section 55-2, "Materials," of the Standard Specifications.

ROTATIONAL CAPACITY TESTING PRIOR TO SHIPMENT TO JOB SITE

Rotational capacity tests shall be performed on all lots of high-strength fastener assemblies prior to shipment of these lots to the project site. Zinc-coated assemblies shall be tested after all fabrication, coating, and lubrication of components has been completed. One hardened washer shall be used under each nut for the tests.

The requirements of this section do not apply to high-strength cap screws or high-strength bolts used for slip base plates.

Each combination of bolt production lot, nut lot, and washer lot shall be tested as an assembly.

A rotational capacity lot number shall be assigned to each combination of lots tested. Each shipping unit of fastener assemblies shall be plainly marked with the rotational capacity lot number.

Two fastener assemblies from each rotational capacity lot shall be tested.

The following equipment, procedure, and acceptance criteria shall be used to perform rotational capacity tests on and determine acceptance of long bolts. Fasteners are considered to be long bolts when full nut thread engagement can be achieved when installed in a bolt tension measuring device:

A. Long Bolt Test Equipment:

1. Calibrated bolt tension measuring device with adequate tension capacity for the bolts being tested.
2. Calibrated dial or digital torque wrench. Other suitable tools will be required for performing Steps 7 and 8 of the Long Bolt Test Procedure. A torque multiplier may be required for large diameter bolts.
3. Spacer washers or bushings. When spacer washers or bushings are required, they shall have the same inside diameter and equal or larger outside diameter as the appropriate hardened washers conforming to the requirements in ASTM Designation: F 436.
4. Steel beam or member, such as a girder flange or cross frame, to which the bolt tension measuring device will be attached. The device shall be accessible from the ground.

B Long Bolt Test Procedure:

1. Measure the bolt length. The bolt length is defined as the distance from the end of the threaded portion of the shank to the underside of the bolt head.
2. Install the nut on the bolt so that 3 to 5 full threads of the bolt are located between the bearing face of the nut and the underside of the bolt head. Measure and record the thread stickout of the bolt. Thread stickout is determined by measuring the distance from the outer face of the nut to the end of the threaded portion of the shank.

3. Insert the bolt into the bolt tension measuring device and install the required number of washers, and additional spacers as needed, directly beneath the nut to produce the thread stickout measured in Step 2 of this procedure.
4. Tighten the nut using a hand wrench to a snug-tight condition. The snug tension shall not be less than the Table A value but may exceed the Table A value by a maximum of 2 kips.

Table A

High-Strength Fastener Assembly Tension Values to Approximate Snug-Tight Condition	
Bolt Diameter (inches)	Snug Tension (kips)
1/2	1
5/8	2
3/4	3
7/8	4
1	5
1-1/8	6
1-1/4	7
1-3/8	9
1-1/2	10

5. Match-mark the assembly by placing a heavy reference start line on the face plate of the bolt tension measuring device which aligns with (1) a mark placed on one corner of the nut and (2) a radial line placed across the flat on the end of the bolt or on the exposed portions of the threads of tension control bolts. Place an additional mark on the outside of the socket that overlays the mark on the nut corner such that this mark will be visible while turning the nut. Make an additional mark on the face plate, either 2/3 of a turn, one turn, or 1-1/3 turn clockwise from the heavy reference start line, depending on the bolt length being tested as shown in Table B.

Table B

Required Nut Rotation for Rotational Capacity Tests ^{(a)(b)}	
Bolt Length (measured in Step 1)	Required Rotation (turn)
4 bolt diameters or less	2/3
Greater than 4 bolt diameters but no more than 8 bolt diameters	1
Greater than 8 bolt diameters, but no more than 12 bolt diameters ^(c)	1-1/3

(a) Nut rotation is relative to bolt, regardless of the element (nut or bolt) being turned. For bolts installed by 1/2 turn and less, the tolerance shall be plus or minus 30 degrees; for bolts installed by 2/3 turn and more, the tolerance shall be plus or minus 45 degrees.

(b) Applicable only to connections in which all material within grip of the bolt is steel.

(c) When bolt length exceeds 12 diameters, the required rotation shall be determined by actual tests in a suitable tension device simulating the actual conditions.

6. Turn the nut to achieve the applicable minimum bolt tension value listed in Table C. After reaching this tension, record the moving torque, in foot-pounds, required to turn the nut, and also record the corresponding bolt tension value in pounds. Torque shall be measured with the nut in motion. Calculate the value, T, where $T = [(the\ measured\ tension\ in\ pounds) \times (the\ bolt\ diameter\ in\ inches) / 48]$.

Table C

Minimum Tension Values for High-Strength Fastener Assemblies	
Bolt Diameter (inches)	Minimum Tension (kips)
1/2	12
5/8	19
3/4	28
7/8	39
1	51
1-1/8	56
1-1/4	71
1-3/8	85
1-1/2	103

7. Turn the nut further to increase bolt tension until the rotation listed in Table B is reached. The rotation is measured from the heavy reference line made on the face plate after the bolt was snug-tight. Record this bolt tension.
8. Loosen and remove the nut and examine the threads on both the nut and bolt.

C. Long Bolt Acceptance Criteria:

1. An assembly shall pass the following requirements to be acceptable: (1) the measured moving torque (Step 6) shall be less than or equal to the calculated value, T (Step 6), (2) the bolt tension measured in Step 7 shall be greater than or equal to the applicable turn test tension value listed in Table D, (3) the nut shall be able to be removed from the bolt without signs of thread stripping or galling after the required rotation in Step 7 has been achieved, (4) the bolt does not shear from torsion or fail during the test, and (5) the assembly does not seize before the final rotation in Step 7 is reached. Elongation of the bolt in the threaded region between the bearing face of the nut and the underside of the bolt head is expected and will not be considered a failure. Both fastener assemblies tested from one rotational capacity lot shall pass for the rotational capacity lot to be acceptable.

Table D

Turn Test Tension Values	
Bolt Diameter (inches)	Turn Test Tension (kips)
1/2	14
5/8	22
3/4	32
7/8	45
1	59
1-1/8	64
1-1/4	82
1-3/8	98
1-1/2	118

The following equipment, procedure, and acceptance criteria shall be used to perform rotational capacity tests on and determine acceptance of short bolts. Fasteners are considered to be short bolts when full nut thread engagement cannot be achieved when installed in a bolt tension measuring device:

A. Short Bolt Test Equipment:

1. Calibrated dial or digital torque wrench. Other suitable tools will be required for performing Steps 7 and 8 of the Short Bolt Test Procedure. A torque multiplier may be required for large diameter bolts.
2. Spud wrench or equivalent.
3. Spacer washers or bushings. When spacer washers or bushings are required, they shall have the same inside diameter and equal or larger outside diameter as the appropriate hardened washers conforming to the requirements in ASTM Designation: F 436.

4. Steel plate or girder with a hole to install bolt. The hole size shall be 1/16 inch greater than the nominal diameter of the bolt to be tested. The grip length, including any plates, washers, and additional spacers as needed, shall provide the proper number of threads within the grip, as required in Step 2 of the Short Bolt Test Procedure.

B. Short Bolt Test Procedure:

1. Measure the bolt length. The bolt length is defined as the distance from the end of the threaded portion of the shank to the underside of the bolt head.
2. Install the nut on the bolt so that 3 to 5 full threads of the bolt are located between the bearing face of the nut and the underside of the bolt head. Measure and record the thread stickout of the bolt. Thread stickout is determined by measuring the distance from the outer face of the nut to the end of the threaded portion of the shank.
3. Install the bolt into a hole on the plate or girder and install the required number of washers and additional spacers as needed between the bearing face of the nut and the underside of the bolt head to produce the thread stickout measured in Step 2 of this procedure.
4. Tighten the nut using a hand wrench to a snug-tight condition. The snug condition shall be the full manual effort applied to the end of a 12-inch long wrench. This applied torque shall not exceed 20 percent of the maximum allowable torque in Table E.

Table E

Maximum Allowable Torque for High-Strength Fastener Assemblies	
Bolt Diameter (inches)	Torque (ft-lb)
1/2	145
5/8	285
3/4	500
7/8	820
1	1220
1-1/8	1500
1-1/4	2130
1-3/8	2800
1-1/2	3700

5. Match-mark the assembly by placing a heavy reference start line on the steel plate or girder which aligns with (1) a mark placed on one corner of the nut and (2) a radial line placed across the flat on the end of the bolt or on the exposed portions of the threads of tension control bolts. Place an additional mark on the outside of the socket that overlays the mark on the nut corner such that this mark will be visible while turning the nut. Make 2 additional small marks on the steel plate or girder, one 1/3 of a turn and one 2/3 of a turn clockwise from the heavy reference start line on the steel plate or girder.
6. Using the torque wrench, tighten the nut to the rotation value listed in Table F. The rotation is measured from the heavy reference line described in Step 5 made after the bolt was snug-tight. A second wrench shall be used to prevent rotation of the bolt head during tightening. Measure and record the moving torque after this rotation has been reached. The torque shall be measured with the nut in motion.

Table F

Nut Rotation Required for Turn-of-Nut Installation ^{(a),(b)}	
Bolt Length (measured in Step 1)	Required Rotation (turn)
4 bolt diameters or less	1/3

(a) Nut rotation is relative to bolt, regardless of the element (nut or bolt) being turned. For bolts installed by 1/2 turn and less, the tolerance shall be plus or minus 30 degrees.

(b) Applicable only to connections in which all material within grip of the bolt is steel.

7. Tighten the nut further to the 2/3-turn mark as indicated in Table G. The rotation is measured from the heavy reference start line made on the plate or girder when the bolt was snug-tight. Verify that the radial line on the bolt end or on the exposed portions of the threads of tension control bolts is still in alignment with the start line.

Table G

Required Nut Rotation for Rotational Capacity Test	
Bolt Length (measured in Step 1)	Required Rotation (turn)
4 bolt diameters or less	2/3

8. Loosen and remove the nut and examine the threads on both the nut and bolt.

C. Short Bolt Acceptance Criteria:

1. An assembly shall pass the following requirements to be acceptable: (1) the measured moving torque from Step 6 shall be less than or equal to the maximum allowable torque from Table E, (2) the nut shall be able to be removed from the bolt without signs of thread stripping or galling after the required rotation in Step 7 has been achieved, (3) the bolt does not shear from torsion or fail during the test, and (4) the assembly shall not seize before the final rotation in Step 7 is reached. Elongation of the bolt in the threaded region between the bearing face of the nut and the underside of the bolt head will not be considered a failure. Both fastener assemblies tested from one rotational capacity lot shall pass for the rotational capacity lot to be acceptable.

INSTALLATION TENSION TESTING AND ROTATIONAL CAPACITY TESTING AFTER ARRIVAL ON THE JOB SITE

Installation tension tests and rotational capacity tests on high-strength fastener assemblies shall be performed by the Contractor prior to acceptance or installation and after arrival of the fastener assemblies on the project site. Installation tension tests and rotational capacity tests shall be performed at the job site, in the presence of the Engineer, on each rotational capacity lot of fastener assemblies.

The requirements of this section do not apply to high-strength cap screws or high-strength bolts used for slip base plates.

Installation tension tests shall be performed on 3 representative fastener assemblies in conformance with the provisions in Section 8, "Installation," of the RCSC Specification. For short bolts, Section 8.2, "Pretensioned Joints," of the RCSC Specification shall be replaced by the "Pre-Installation Testing Procedures," of the "Structural Bolting Handbook," published by the Steel Structures Technology Center, Incorporated.

The rotational capacity tests shall be performed in conformance with the requirements for rotational capacity tests in "Rotational Capacity Testing Prior to Shipment to Job Site" of these special provisions.

At the Contractor's expense, additional installation tension tests, tests required to determine job inspecting torque, and rotational capacity tests shall be performed by the Contractor on each rotational capacity lot, in the presence of the Engineer, if:

1. Any fastener is not used within 3 months after arrival on the job site,
2. Fasteners are improperly handled, stored, or subjected to inclement weather prior to final tightening,
3. Significant changes are noted in original surface condition of threads, washers, or nut lubricant, or
4. The Contractor's required inspection is not performed within 48 hours after all fasteners in a joint have been tensioned.

Failure of a job-site installation tension test or a rotational capacity test will be cause for rejection of unused fasteners that are part of the rotational capacity lot.

When direct tension indicators are used, installation verification tests shall be performed in conformance with Appendix Section X1.4 of ASTM Designation: F 959, except that bolts shall be initially tensioned to a value 5 percent greater than the minimum required bolt tension.

When zinc-coated tension control bolts are used, the sheared end of each fastener shall be completely sealed with non-silicone type sealing compound conforming to the provisions in Federal Specification TT-S-230, Type II. The sealant shall be gray in color and shall have a minimum thickness of 50 mils. The sealant shall be applied to a clean sheared surface on the same day that the splined end is sheared off.

WELDING

Table 2.2 of AWS D1.5 is superseded by the following table:

Base Metal Thickness of the Thicker Part Joined, inches	Minimum Effective Partial Joint Penetration Groove Weld Size*, inches
Over 1/4 to 1/2 inclusive	3/16
Over 1/2 to 3/4 inclusive	1/4
Over 3/4 to 1-1/2 inclusive	5/16
Over 1-1/2 to 2-1/4 inclusive	3/8
Over 2-1/4 to 6 inclusive	1/2
Over 6	5/8

* Except the weld size need not exceed the thickness of the thinner part

Dimensional details and workmanship for welded joints in tubular and pipe connections shall conform to the provisions in Part A, "Common Requirements of Nontubular and Tubular Connections," and Part D, "Specific Requirements for Tubular Connections," in Section 2 of AWS D1.1.

The requirement of conformance with AWS D1.5 shall not apply to work conforming to Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

MEASUREMENT AND PAYMENT

The contract price paid per pound for lighting and sign illumination shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and erecting structural steel, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.31 ROADSIDE SIGNS

Roadside signs shall be furnished and installed at the locations shown on the plans or where designated by the Engineer and in conformance with the provisions in Section 56-2, "Roadside Signs," of the Standard Specifications and these special provisions.

The Contractor shall furnish roadside sign panels in conformance with the provisions in "Furnish Sign" of these special provisions.

Wood posts shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications and AWPA Use Category System: UC4A, Commodity Specification A or B.

10-1.32 FURNISH SIGN

Signs shall be fabricated and furnished in accordance with details shown on the plans, the Traffic Sign Specifications, and these special provisions.

Traffic Sign Specifications for California sign codes are available for review at:

<http://www.dot.ca.gov/hq/traffops/signtech/signdel/specs.htm>

Traffic Sign Specifications for signs referenced with Federal MUTCD sign codes can be found in Standard Highway Signs Book, administered by the Federal Highway Administration, which is available for review at:

http://mutcd.fhwa.dot.gov/ser-shs_millennium.htm

Information on cross-referencing California sign codes with the Federal MUTCD sign codes is available at:

<http://www.dot.ca.gov/hq/traffops/signtech/signdel/specs.htm>

Temporary or permanent signs shall be free from blemishes that may affect the serviceability and detract from the general sign color and appearance when viewing during daytime and nighttime from a distance of 25 feet. The face of each finished sign shall be uniform, flat, smooth, and free of defects, scratches, wrinkles, gel, hard spots, streaks, extrusion marks, and air bubbles. The front, back, and edges of the sign panels shall be free of router chatter marks, burns, sharp edges, loose rivets, delaminated skins, excessive adhesive over spray and aluminum marks.

QUALITY CONTROL FOR SIGNS

The requirements of "Quality Control for Signs" in this section shall not apply to construction area signs.

No later than 14 days before sign fabrication, the Contractor shall submit a written copy of the quality control plan for signs to the Engineer for review. The Engineer will have 10 days to review the quality control plan. Sign fabrication shall not begin until the Engineer approves the Contractor's quality control plan in writing. The Contractor shall submit to the Engineer at least 3 copies of the approved quality control plan. The quality control plan shall include, but not be limited to the following requirements:

- A. Identification of the party responsible for quality control of signs,
- B. Basis of acceptance for incoming raw materials at the fabrication facility,
- C. Type, method and frequency of quality control testing at the fabrication facility,
- D. List (by manufacturer and product name) of process colors, protective overlay film, retroreflective sheeting and black non-reflective film,
- E. Recommended cleaning procedure for each product, and
- F. Method of packaging, transport and storage for signs.

No legend shall be installed at the project site. Legend shall include letters, numerals, tildes, bars, arrows, route shields, symbols, logos, borders, artwork, and miscellaneous characters. The style, font, size, and spacing of the legend shall conform to the Standard Alphabets published in the FHWA Standard Highway Signs Book. The legend shall be oriented in the same direction in accordance with the manufacturer's orientation marks found on the retroreflective sheeting.

On multiple panel signs, legend shall be placed across joints without affecting the size, shape, spacing, and appearance of the legend. Background and legend shall be wrapped around interior edges of formed panel signs as shown on plans to prevent delamination.

The following notation shall be placed on the lower right side of the back of each sign where the notation will not be blocked by the sign post or frame:

- A. PROPERTY OF STATE OF CALIFORNIA,
- B. Name of the sign manufacturer,
- C. Month and year of fabrication,
- D. Type of retroreflective sheeting, and
- E. Manufacturer's identification and lot number of retroreflective sheeting.

The above notation shall be applied directly to the aluminum sign panels in 1/4-inch upper case letters and numerals by die-stamp and applied by similar method to the fiberglass reinforced plastic signs. Painting, screening, or engraving the notation will not be allowed. The notation shall be applied without damaging the finish of the sign.

Signs with a protective overlay film shall be marked with a dot of 3/8 inch in diameter. The dot placed on white border shall be black, while the dot placed on black border shall be white. The dot shall be placed on the lower border of the sign before application of the protective overlay film and shall not be placed over the legend and bolt holes. The application method and exact location of the dot shall be determined by the manufacturer of the signs.

For sign panels that have a minor dimension of 48 inches or less, no splice will be allowed in the retroreflective sheet except for the splice produced during the manufacturing of the retroreflective sheeting. For sign panels that have a minor dimension greater than 48 inches, only one horizontal splice will be allowed in the retroreflective sheeting.

Unless specified by the manufacturer of the retroreflective sheeting, splices in retroreflective sheeting shall overlap by a minimum of one inch. Splices shall not be placed within 2 inches from edges of the panels. Except at the horizontal borders, the splices shall overlap in the direction from top to bottom of the sign to prevent moisture penetration. The retroreflective sheeting at the overlap shall not exhibit a color difference under the incident and reflected light.

Signs exhibiting a significant color difference between daytime and nighttime shall be replaced immediately.

Repairing sign panels will not be allowed except when approved by the Engineer.

The Department will inspect signs at the Contractor's facility and delivery location, and in accordance with Section 6, "Control of Materials," of the Standard Specifications. The Engineer will inspect signs for damage and defects before and after installation.

Regardless of kind, size, type, or whether delivered by the Contractor or by a common carrier, signs shall be protected by thorough wrapping, tarping, or other methods to ensure that signs are not damaged by weather conditions and during transit. Signs shall be dry during transit and shipped on pallets, in crates, or tier racks. Padding and protective materials shall be placed between signs as appropriate. Finished sign panels shall be transported and stored by method that protects the face of signs from damage. The Contractor shall replace wet, damaged, and defective signs.

Signs shall be stored in dry environment at all times. Signs shall not rest directly on the ground or become wet during storage. Signs, whether stored indoor or outdoor, shall be free standing. In areas of high heat and humidity signs shall be stored in enclosed climate-controlled trailers or containers. Signs shall be stored indoor if duration of the storage will exceed 30 days.

Screen processed signs shall be protected, transported and stored as recommended by the manufacturer of the retroreflective sheeting.

When requested, the Contractor shall provide the Engineer test samples of signs and materials used at various stages of production. Sign samples shall be 12" x 12" in size with applied background, letter or numeral, and border strip.

The Contractor shall assume the costs and responsibilities resulting from the use of patented materials, equipment, devices, and processes for the Contractor's work.

SHEET ALUMINUM

Alloy and temper designations for sheet aluminum shall be in accordance with ASTM Designation: B 209.

The Contractor shall furnish the Engineer a Certificate of Compliance in conformance with Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for the sheet aluminum.

Sheet aluminum shall be pretreated in accordance to ASTM Designation: B 449. Surface of the sheet aluminum shall be cleaned, deoxidized, and coated with a light and tightly adherent chromate conversion coating free of powdery residue. The conversion coating shall be Class 2 with a weight between 10 milligrams per square foot and 35 milligrams per square foot, and an average weight of 25 milligrams per square foot. Following the cleaning and coating process, the sheet aluminum shall be protected from exposure to grease, oils, dust, and contaminants.

Sheet aluminum shall be free of buckles, warps, dents, cockles, burrs, and defects resulting from fabrication.

Base plate for standard route marker shall be die cut.

RETROREFLECTIVE SHEETING

The Contractor shall furnish retroreflective sheeting for sign background and legend in conformance with ASTM Designation: D 4956 and "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Retroreflective sheeting shall be applied to sign panels as recommended by the retroreflective sheeting manufacturer without stretching, tearing, and damage.

Class 1, 3, or 4 adhesive backing shall be used for Type II, III, IV, VII, VIII, and IX retroreflective sheeting. Class 2 adhesive backing may also be used for Type II retroreflective sheeting. The adhesive backing shall be pressure sensitive and fungus resistant.

When the color of the retroreflective sheeting determined from instrumental testing is in dispute, the Engineer's visual test will govern.

PROCESS COLOR AND FILM

The Contractor shall furnish and apply screened process color, non-reflective opaque black film, and protective overlay film of the type, kind, and product that are approved by the manufacturer of the retroreflective sheeting.

The Contractor shall furnish the Engineer a Certificate of Compliance in accordance to Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for the screened process color, non-reflective opaque black film, and protective overlay film.

The surface of the screened process color shall be flat and smooth. When the screened process colors determined from the instrumental testing in accordance to ASTM Designation: D 4956 are in dispute, the Engineer's visual test will govern.

The Contractor shall provide patterns, layouts, and set-ups necessary for the screened process.

The Contractor may use green, red, blue, and brown reverse-screened process colors for background and non-reflective opaque black film or black screened process color for legend. The coefficient of retroreflection for reverse-screened process colors on white retroreflective sheeting shall not be less than 70 percent of the coefficient of retroreflection specified in ASTM Designation: D 4956.

The screened process colors and non-reflective opaque black film shall have the same outdoor weatherability as that of the retroreflective sheeting.

After curing, screened process colors shall withstand removal when tested by applying 3M Company Scotch Brand Cellophane Tape No. 600 or equivalent tape over the color and removing with one quick motion at 90° angle.

SINGLE SHEET ALUMINUM SIGN

Single sheet aluminum signs shall be fabricated and furnished with or without frame. The Contractor shall furnish the sheet aluminum in accordance to "Sheet Aluminum" of these special provisions. Single sheet aluminum signs shall be fabricated from sheet aluminum alloy 6061-T6 or 5052-H38.

Single sheet aluminum signs shall not have a vertical splice in the sheet aluminum. For signs with depth greater than 48 inches, one horizontal splice will be allowed in the sheet aluminum.

Framing for single sheet aluminum signs shall consist of aluminum channel or rectangular aluminum tubing. The framing shall have a length tolerance of $\pm 1/8$ inch. The face sheet shall be affixed to the frame with rivets of 3/16-inch diameter. Rivets shall be placed within the web of channels and shall not be placed less than 1/2 inch from edges of the sign panels. Rivets shall be made of aluminum alloy 5052 and shall be anodized or treated with conversion coating to prevent corrosion. The exposed portion of rivets on the face of signs shall be the same color as the background or legend where the rivets are placed.

Finished signs shall be flat within a tolerance of $\pm 1/32$ inch per linear foot when measured across the plane of the sign in all directions. The finished signs shall have an overall tolerance within $\pm 1/8$ inch of the detailed dimensions.

Aluminum channels or rectangular aluminum tubings shall be welded together with the inert gas shielded-arc welding process using E4043 aluminum electrode filler wires as shown on the plans. Width of the filler shall be equal to wall thickness of smallest welded channel or tubing.

MEASUREMENT AND PAYMENT

Furnishing signs (except for construction area signs) will be measured by the square foot and the quantity to be paid for will be the total area, in square feet, of the sign panel types installed in place.

The contract price paid per square foot for furnish sign of the types specified in the Engineer's estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in fabricating and furnishing the signs, including fastening hardware, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for furnishing and installing protective overlay on signs shall be considered as included in the contract price paid per square foot for furnish sign of the various types and no separate payment will be made therefor.

10-1.33 PLASTIC PIPE

Plastic pipe shall conform to the provisions in Section 64, "Plastic Pipe," of the Standard Specifications.

10-1.34 CORRUGATED METAL PIPE

Corrugated steel culverts shall conform to the provisions in Section 66, "Corrugated Metal Pipe," of the Standard Specifications and these special provisions.

Corrugated steel pipe shall be fabricated from zinc-coated steel sheet.

10-1.35 WATER LINE

GENERAL

Water lines identified on the plans shall be of the size shown on the plans and conform to the provisions in Section 12-15, "Mechanical," of these special provisions.

All piping insulation and wrapping material shall be in accordance with the requirements specified under "Mechanical Insulation," in Section 12-15, "Mechanical," of these special provisions.

Cathodic protection for underground piping shall be in accordance with the requirements specified under "Cathodic Protection," in Section 12-15, "Mechanical," of these special provisions.

MATERIALS

Materials for water line shall conform to the requirements in Section 12-15 "Pipes, Fittings and Valves" of these special provisions for pipe H2.

The pipe sizes shown on the plans are nominal inside diameter. No change in the pipe size shown on the plans shall be permitted without written permission from the Engineer.

INSTALLATION

Cleaning and Closing of Pipe

The interior of the pipe shall be cleaned before installation. Openings shall be capped or plugged as soon as the pipe is installed to prevent the entrance of foreign material. The caps or plugs shall remain in place until the adjacent pipe sections are to be installed.

Insulation and Cathodic Protection

Insulation and cathodic protection shall be as provided under Section 12-15 "Pipes, Fittings and Valves" of these special provisions.

TESTING

Testing shall be as provided under Section 12-15 "Pipes, Fittings and Valves" of these special provisions.

MEASUREMENT AND PAYMENT

Measurement for water line for each size listed in the Engineer's Estimate shall be made in the same manner as galvanized steel pipe and plastic pipe supply lines in Section 20-5.04, "Measurement," and Section 20-5.05, "Payment," of the Standard Specifications.

Full compensation for furnishing and installing water line, fittings, insulators, cathodic protection; for cleaning, closing, wrapping, and coating pipe; and for pressure testing shall be considered as included in the contract prices paid per linear foot for the sizes of water line involved, and no additional compensation will be allowed therefor.

10-1.36 SEWER PIPE AND SEWER TERMINAL CLEANOUT

This work shall consist of furnishing, installing and constructing a sanitary sewage system and sewer terminal cleanout in accordance with the details shown on the plans and these special provisions.

Sanitary sewage system and sewer terminal cleanout shall include other fittings and appurtenances, not mentioned, which are required for the complete installation and proper operation of the system.

Work which will curtail the use of the existing sewage system shall not be done until the facilities utilizing the system are closed and are no longer required.

Product data:

Materials list for materials to be used shall be submitted for approval and shall include the name of the manufacturer and the source, model number, description, and standard of manufacture.

Manufacturer's descriptive data and catalog cuts shall be submitted for the following:

- Underground tracer tape
- Sewer pipe and fittings
- Sewer pipe adapters
- Drain pipe and fittings
- Coatings
- Cleanouts

QUALITY ASSURANCE

Codes and Standards: All sanitary sewage work shall conform to the applicable portions of the California Plumbing Code (CPC).

Certificates of Compliance: Certificates of compliance shall be furnished for manhole covers and frames in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Underground Tracer Tape: Underground tracer tape shall be permanent, detectable, bright colored, continuous printed plastic tape intended for direct burial service; not less than 2 inches wide; lettering shall read "CAUTION SEWER BURIED BELOW".

PIPES AND FITTINGS

The Contractor shall install pipes and fittings from the following materials, of the weight and class with the joining method as indicated.

Sewer and Drain Pipe: Sewer and drain pipe and fittings shall be polyvinyl chloride (PVC) gravity sewer plastic pipe and fittings conforming to ASTM Designation: D 3034, Standard Dimension Ratio (SDR) 35, with integral bell and bell and spigot rubber gasketed joints or conforming to ASTM Designation: D2665 with solvent welded fittings. Rubber gaskets shall conform to ASTM Designation: F 477. Stainless steel clamps with rubber boots shall not be used.

Sewer Pipe Adapters: Sewer pipe adapters for PVC to cast iron soil pipe or clay piping shall be appropriately sized PVC flexible coupling manufactured for connecting dissimilar pipes. Adapters shall be attached to piping with adjustable stainless steel band clamps with hex tightening screws. Rubber boots will not be allowed. Sewer pipe adapter shall be Indiana Seal; Fernco; or equal.

SEWER MANHOLES

Manhole distribution box riser sections and cones shall be precast, reinforced concrete, conforming to ASTM Designation: C 478, or precast reinforced concrete pipe conforming to ASTM Designation: C 76.

VALVE AND METER BOXES

Valve Box: Valve box shall be precast concrete box with cast iron cover. Cover shall be factory marked "SEWER," "SS," or "SANITARY SEWER" and shall be traffic rated. Valve box shall be Cook Concrete Products, No. 10-T-12; Christy No. G-5C; Brooks, No. 3-RT; or equal with extensions as required.

Meter Box: Meter box shall be precast concrete with cast iron cover. Cover shall be factory marked "SEWER," "SS," or "SANITARY SEWER" and shall be traffic rated. Meter box shall be Bes, No. C9W with C15 cover; Christy, No. B9 with B9C cover; Cook Concrete Products, No. 14 with 14-T cover; or equal.

CLEANOUTS AND VALVES

Cleanout to Grade: Cleanout piping shall terminate with an appropriately sized flexible PVC access cap and stainless steel band coupler with hex tightening screw. Rubber coupling or cap will not be allowed. Access cap shall be Indiana Seal; Fernco; or equal.

Gravity Check Valve: Gravity check valve shall be 4-inch, hub ends, polyvinyl chloride (PVC) body, rated for 125 psi minimum back pressure, no metallic parts, angled viton compound rubber or fluorocarbon compound seat and removable flapper rated for horizontal or vertical usage, unseated pressure opens on contact, full flow design. Valve shall be Flo Control Inc., R and G Sloane, NDS Inc., or equal.

COATINGS

Bituminous Coating: Bituminous coating shall conform to ASTM Designations: D 41 and D 449.

MISCELLANEOUS MATERIALS

Cement Mortar: Cement mortar shall be one part cement to 2 to 3 parts clean plaster or concrete sand mixed with just enough water for suitable consistency.

Epoxy Mortar: Epoxy mortar shall be a commercial quality, trowelable, 3-component epoxy mortar consisting of 2 pourable epoxy components and a chemically resistant aggregate filler of silica quartz sand with a maximum water absorption of 0.1 percent. Epoxy shall have a pull-off strength of not less than 1,000 psi and a 90 percent cure in 24 hours. Epoxy mortar shall be the type that requires no primer as a bonding agent.

INSTALLATION OF IDENTIFICATION

Continuous underground tracer tape shall be installed directly above buried lines and 6 inches to 12 inches below finished grade during backfilling operations.

INSTALLATION OF PIPES AND FITTINGS

Sewer and drain pipe shall be installed upgrade (starting from utility connection back to the construction) unless otherwise permitted by the Engineer.

Closing Abandoned Utilities: Open ends of abandoned underground utilities shall be closed. Sufficiently strong closures, either 6 inches of concrete or pipe cap with concrete thrust block, shall be placed to withstand hydro-static pressure which may result after the pipes are closed.

Sewers Near Water Lines: Sewers near water lines shall be installed below water lines in the same trench, in parallel trenches less than 10 feet apart, or at any crossing.

When water lines cross above a sewer line, a vertical separation of not less than 12 inches shall be maintained between the top of the sewer pipe and the bottom of the water line.

Connections between Differing Pipe Types: Joints between different types of pipes shall be made with sewer pipe adapters intended for that purpose.

Damaged Pipe: Damaged pipe shall be replaced prior to use. Misaligned pipe shall be corrected or replaced prior to use.

Cleaning Pipe: Interior of pipes shall be cleaned of dirt and other materials as the work progresses.

Lines between manholes shall be flushed as necessary to remove collected material.

INSTALLATION OF MANHOLES AND VALVE AND METER BOXES

All joints and penetrations of manholes and valve and meter boxes shall be sealed watertight, inside and outside, with epoxy mortar.

A concrete collar shall be formed and cast in place around each manhole in accordance with the details shown on the plans.

INSTALLATION OF CLEANOUTS

Cleanouts shall be installed 90 degrees to finished grade and shall terminate in a valve box. A concrete pad shall be provided full width of the trench under a wye branch.

Cleanouts to grade shall be a combination of fittings as shown on the plans. Piping and fittings for 4-inch pipe shall be sewer pipe. Piping and fittings for 3-inch pipe and smaller shall be drain pipe.

Collars shall be broom surface finished. Collars shall match existing/finished grade. Compaction prior to form work shall be as specified elsewhere in these special provisions.

APPLICATION OF COATINGS

The interior and exterior surfaces of concrete sewer structures, except the bottom of tanks, shall be completely coated with 2 applications of bituminous coating, applied at a rate of 100 square feet per gallon.

The edge and bottom of manhole cover seat areas shall be coated with a uniform application of heavy duty, waterproof automotive or industrial grease.

FIELD QUALITY CONTROL

Testing Pipes:

All sewer and drain pipes shall be tested for obstructions before covering the pipes by balling and flushing the pipes with an approved commercial sewer cleaning ball. The ball shall be moved slowly through the sewer with a tag line. Four-inch sewer pipe shall be tested by pulling an appropriate sized inflatable plug through the pipe. Obstructions or irregularities shall be removed or repaired.

Sewer and drain pipes shall be tested for leakage for a minimum period of 4 hours by filling with water to an elevation of 4 feet above the average invert of sewer pipe, or to the top of the manholes where less than 4 feet deep. The system shall show no visible leaks, and the leakage rate shall not exceed the rate allowed by the local agency. In the absence of such requirements, leakage shall not exceed one pint per 24 hours, per millimeter diameter, per 100 feet of pipe. Sewer pipes may be tested in sections with the test water progressively passed down the sewers if feasible. Water shall be released at a rate which will not create water hammer or surge in the plugged section of sewer.

In lieu of hydrostatic test with water, the air test method, "Air Test," as outlined in the CPC, may be used.

MEASUREMENT AND PAYMENT

The contract price paid per each sewer terminal cleanout shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing sewer terminal cleanout, complete in place, including furrow excavation and backfill, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract unit price paid per linear foot for different sizes of sewer pipe as specified in the estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing different sizes of sewer pipes, complete in place, including earthwork as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.37 DRAINAGE INLET MARKER

The Contractor shall furnish and install thermoplastic drainage inlet markers in conformance with the details and locations shown on the plans, as specified in these special provisions, and as directed by the Engineer.

The Contractor shall furnish a Certificate of Compliance to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for thermoplastic drainage inlet markers. In addition, a sample of the drainage inlet marker shall be submitted to the Engineer 10 days before placement of the markers.

Thermoplastic drainage inlet markers shall be prefabricated, free of lead and chromium, and conform to AASHTO Designation: M 249 and the requirements as follow. Thermoplastic drainage inlet markers shall be adhered to the surface of the drainage inlet with heat as recommended by the manufacturer of the marker.

Property	Specifications	Requirement
Thickness, inches		0.080-0.160
Legend color (non-reflective)	FHWA's Color Tolerance Chart	Blue or Green (PR Color Number 3 or 4)
Background color (non-reflective)	AASHTO Designation: M 249	White
Skid Resistance	ASTM Designation: E 303	60 BPN

The Contractor shall mechanically clean the surface before placing thermoplastic drainage inlet markers.

Drainage inlet marker will be measured as units determined from actual count in place.

The contract unit price paid for drainage inlet marker shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing drainage inlet markers, complete in place, as shown on the plans, as specified in the Standard Specifications, and these special provisions, and as directed by the Engineer.

10-1.38 WELDED STEEL PIPE

Welded steel pipe shall conform to the provisions in Section 70, "Miscellaneous Facilities," of the Standard Specifications and these special provisions.

Coating and wrapping will not be required.

10-1.39 DRAIN BOX

Drain box, where shown on the plans, shall be constructed in accordance with the details on the plans and these special provisions.

Drain box shall conform to Section 51-1.02 "Minor Structures" of the Standard Specifications. Pipe connections into and out of drain box shall be mortared in accordance with Section 51-1.135, "Mortar" of the Standard Specifications.

Drain box frame and grate and all fasteners shall be galvanized and conform to the provisions in Section 75-1.02, "Miscellaneous Iron and Steel" and Section 75-1.05, "Galvanizing" of the Standard Specifications. Drain box grate shall be fastened to the frame with a minimum of two grate-locking clips secured by tamper resistant hold down bolts.

The contract unit price paid for each drain box shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the drain box, complete in place, including structure excavation and backfill, mortaring of pipe connections, galvanizing frame and grate, and installing the grate locking device as shown on the plans, and as specified in these special provisions.

10-1.40 SLOPE PROTECTION

Slope protection shall be placed or constructed in conformance with the provisions in Section 72, "Slope Protection," of the Standard Specifications and these special provisions.

Rock slope protection fabric shall be woven or nonwoven type fabric, Type A at the option of the Contractor.

10-1.41 MISCELLANEOUS CONCRETE CONSTRUCTION

Minor Concrete shall conform to the provisions in Section 73, "Concrete Curbs and Sidewalks," of the Standard Specifications and these special provisions.

Curb ramp detectable warning surface shall consist of raised truncated domes constructed or installed on curb ramps in conformance with the details shown on the plans and these special provisions. At the option of the Contractor, the detectable warning surface shall be prefabricated, cast-in-place, or stamped into the surface of the curb ramp. The color of the detectable warning surface shall be yellow conforming to Federal Standard 595B, Color No. 33538.

Prefabricated detectable warning surface shall be in conformance with the requirements established by the Department of General Services, Division of State Architect and be attached in conformance with the manufacturer's recommendations.

Cast-in-place and stamped detectable warning surfaces shall be painted in conformance with the provisions in Section 59-6, "Painting Concrete," of the Standard Specifications.

The finished surfaces of the detectable warning surface shall be free from blemishes.

Prior to constructing the cast-in-place or stamping the detectable warning surface, the Contractor shall demonstrate the ability to produce a detectable warning surface conforming to the details shown on the plans and these special provisions by constructing a 24" x 24" test panel.

The manufacturer shall provide a written 5-year warranty for prefabricated detectable warning surfaces, guaranteeing replacement when there is defect in the dome shape, color fastness, sound-on-cane acoustic quality, resilience, or attachment. The warranty period shall begin upon acceptance of the contract.

Full compensation for constructing or furnishing and installing curb ramp detectable warning surfaces shall be considered as included in the contract price paid per cubic yard for minor concrete (miscellaneous construction) and no separate payment will be made therefor.

10-1.42 MISCELLANEOUS IRON AND STEEL

Miscellaneous iron and steel shall conform to the provisions in Section 75, "Miscellaneous Metal," of the Standard Specifications .

10-1.43 WELDED WIRE FENCE

Welded wire fence shall conform to the provisions in Section 80, "Fences," of the Standard Specifications and these special provisions.

SUBMITTALS

The Contractor shall submit the Manufacturer's descriptive data, material specifications and layout drawings for the welded wire fence and accessories for the Engineer's approval.

MATERIALS

General

All ferrous materials shall be new and galvanized. Posts, wire members for fence panels caps, braces and other rolled or formed elements shall be hot-dip galvanized and powder coated after rolling or forming.

Style, finish, and color of each fence post shall match that of the other fence components.

Posts

Tubular steel posts shall conform to ASTM: A500, Grade B, galvanized. Tubing shall be painted and finished to match the post. The nominal thickness of the tubular steel post before galvanizing shall be 1/16". Rainproof caps shall be furnished for tubular posts.

Fence Post Connections

The anchors for securing the fence post connection to the portland cement sidewalk shall be stainless steel adhesive anchors or approved equal.

Steel plates shall conform to ASTM A361A 36M, galvanized. Plates shall be painted and finished to match the post.

Bolts for the stainless steel fasteners (alloys 304 and 316) shall conform to ASTM F593 or ASTM F738M. Washers for the stainless steel fasteners shall conform to ASTM A240 and B18.22M.

Drill holes for the concrete anchors shall be drilled and cleaned in conformance with the anchor manufacturer's requirements.

Panels

Panels shall be Class 1 galvanized wire welded with a regular opening of 2 x 6 conforming to ASTM A185. Welded steel wire shall be minimum, 6-gage (0.192"), Class 1 galvanized wire weighing 0.328 oz/sqft. The wire tensile strength shall be 80,000 to 100,000 psi and a weld shear of 1050 pounds.

The color of the welded wire fence shall be black polyester powder coated to a 100 microns minimum thickness, measured by ASTM D1186 Method.

INSTALLATION

Posts for welded wire steel fence shall be set vertically in footings or sidewalk as shown on the plans.

Fence panels shall be attached to the posts with approved collars, brackets, fasteners, or clips as recommended by the fence manufacturer.

The fence shall be erected in straight lines between angle points and shall conform closely to the horizontal and vertical lines shown on the plans or ordered by the Engineer.

Shims shall be installed between the posts and tube steel connection members, where necessary, to provide a snug tight fitting at the posts.

MEASUREMENT AND PAYMENT

Quantities of welded wire fence to be paid for will be determined by the linear foot from actual measurements of the completed fence, the measurement to be made parallel to the ground slope along the line completed runs of fence, deducting the width of openings.

Full compensation for clearing the line of the fence and disposing of the resulting material, excavating high points in the existing ground between post, excavating holes, disposing of surplus material, and furnishing and placing portland cement concrete footings, and constructing temporary fences for the protection of stock, shall be considered as included in the price paid for the fence and no additional compensation will be allowed therefor.

The contract unit price paid per linear foot for welded wire fence shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing welded wire steel fence, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.44 CHAIN LINK FENCE

Chain link fence shall be Type CL-6 and shall conform to the provisions in Section 80, "Fences," of the Standard Specifications.

10-1.45 HANDRAILING

Handrailing shall be installed as shown on plans and in accordance with the provisions in Section 83-1 "Railings," of the Standard Specifications.

Handrailing shall be painted in accordance with Section 59-1 "Painting – General," and Section 59-3 "Painting Galvanized Surfaces," of the Standard Specifications. Paint for handrailing shall be black commercial quality, suitable for the intended purpose.

Handrailing will be measured and paid for in accordance with Section 83-1.03 and Section 83-1.04 of the Standard Specifications.

The contract price paid per linear foot for handrailing shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in fabricating, painting and installing handrailing, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.46 SITE FURNISHINGS

Site furnishings shall consist of placing concrete picnic tables, benches, trash receptacles, and installing sign monument, sign plaques and water posts at locations as shown on the plans and in conformance with these special provisions. The size of the individual pieces of site furnishing shall be as shown on the plans.

Site furnishings will be State-furnished in accordance with "State-furnished Materials" of these special provisions and will be furnished to the Contractor at the site of the work.

Concrete for the concrete pads and foundations shall conform to Section 90-10, "Minor Concrete," of the Standard Specifications.

Bar reinforcement, of the size and type shown on the plans, conforming to the provisions in Section 52, "Reinforcement," of the Standard Specifications, shall be placed in the concrete footing for sign pedestals as shown on the plans.

Drain rock for water post shall consist of gravel or crushed rock conforming to the following requirements:

Grading Requirements	
Sieve Size	Operating Range
1"	100
3/4"	90-100
No. 4	35-60
No. 30	10-30
No. 200	2-9

The color of drain rock shall be gray.

Edging shall be pressure-treated construction grade lumber, including stakes, and shall conform to sections 20-2.12, "Lumber," and 20-4.04, "Header Boards," of the Standard Specifications.

Edging shall be a minimum 2x4 nominal dimension. Stakes shall be 1" by 1-1/4" and 12 inches in length.

Precast concrete site furnishings shall be placed at the locations as shown on the plans and arranged in an even uniform manner within the designated area of work.

Areas to receive drain rock for the water post shall be cleared of trash and debris. Vegetation shall be removed to the ground. Cleared trash, debris and removed vegetation shall be disposed outside the highway right of way in conformance with Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The splash area for water post shall be filled with drain rock to 1/2" below the top of the wood edging.

Concrete pads and foundations for sign pedestals shall be constructed in accordance with "Miscellaneous Concrete Construction", of these special provisions. The sign pedestals and metal plaques shall be installed into sleeves or slip dowels and secured as shown on the plans and as recommended by the pedestal manufacturer.

Full compensation for concrete pads and foundations shall be considered as included in the contract unit price paid per cubic yard for minor concrete (miscellaneous construction) and no additional compensation will be allowed therefor.

Salvaged metal sign plaque and blue star memorial shall be installed on new precast concrete pedestal and sign monument as shown on the plans.

The contract lump sum price paid for install site furnishing shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in placing concrete picnic tables, benches, trash receptacles, and installing edging, concrete pedestals for blue star memorial, metal signs plaques and water posts, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.47 ADDITIVE

Items of work for Additive shall be performed in conformance with the details shown on the plans and in conformance with these special provisions.

Highway Planting shall conform to "Highway Planting" of these special provisions, except for payment.

Maintenance of existing planted areas shall conform to "Maintain Existing Planted Areas" of these special provisions, except for payment.

Plant establishment shall conform to "Plant Establishment Work" of these special provisions, except for payment.

Irrigation systems shall conform to "Irrigation Systems" of these special provisions, except for payment.

Aggregate base (Class 3) shall conform to "Aggregate Base" of these special provisions, except for payment.

Minor concrete (minor structure) shall conform to "Minor Concrete (Minor Structure)" of these special provisions, except for payment.

Minor concrete (miscellaneous construction) shall conform to "Minor Concrete (Miscellaneous Construction)" of these special provisions, except for payment.

Handrailing shall conform to "Handrailing" of these special provisions, except for payment.

Overhead picnic table cover, picnic area lighting and picnic area sidewalks shall conform to "Building Work" of these special provisions, except for payment.

The contract lump sum price paid for Additive shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in Additive, complete in place, including traffic control and construction area signs necessary for Additive items of work, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS

10-2.01 GENERAL

The work performed in connection with highway planting and irrigation systems shall conform to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications and these special provisions.

When fluctuations of water pressure and water supply are encountered during normal working hours, plants shall be watered at other times, as often, and in sufficient amounts as conditions may require to keep the soil and plant roots moist during the life of the contract.

Full compensation for watering plants outside normal working hours shall be considered as included in the contract lump sum prices paid for highway planting and plant establishment work and no additional compensation will be allowed therefor.

PROGRESS INSPECTIONS

Progress inspections will be performed by the Engineer for completed highway planting and irrigation system work at designated stages during the life of the contract.

Progress inspections will not relieve the Contractor of responsibility for installation in conformance with the special provisions, plans and Standard Specifications. Work within an area shall not progress beyond each stage until the inspection has been completed, corrective work has been performed, and the work is approved, unless otherwise permitted by the Engineer.

The requirements for progress inspections will not preclude additional inspections of work by the Engineer at other times during the life of the contract.

The Contractor shall notify the Engineer, in writing, at least 4 working days prior to completion of the work for each stage of an area and shall allow a minimum of 3 working days for the inspection.

Progress inspections will be performed at the following stages of work:

- A. During pressure testing of the pipelines on the supply side of control valves.
- B. During testing of low voltage conductors.
- C. Before planting begins and after completion of the work specified for planting in Section 20-4.03, "Preparing Planting Areas," of the Standard Specifications.
- D. Before plant establishment work begins and after completion of the work specified for planting in Section 20-4.05, "Planting," of the Standard Specifications.
- E. At intervals of one month during the plant establishment period.

COST BREAK-DOWN

The Contractor shall furnish the Engineer a cost break-down for the contract lump sum items of highway planting and irrigation system. Cost break-down tables shall be submitted to the Engineer for approval within 15 working days after the contract has been approved. Cost break-down tables will be approved, in writing, by the Engineer before any partial payment will be made for the applicable items of highway planting and irrigation system involved.

Attention is directed to "Time-Related Overhead" of these special provisions regarding compensation for time-related overhead.

Cost break-downs shall be completed and furnished in the format shown in the samples of the cost break-downs included in this section. Line item descriptions of work shown in the samples are the minimum to be submitted. Additional line item descriptions of work may be designated by the Contractor. If the Contractor elects to designate additional line item descriptions of work, the quantity, value and amount for those line items shall be completed in the same manner as for the unit descriptions shown in the samples. The line items and quantities given in the samples are to show the manner of preparing the cost break-downs to be furnished by the Contractor.

The Contractor shall determine the quantities required to complete the work shown on the plans. The quantities and their values shall be included in the cost break-downs submitted to the Engineer for approval. The Contractor shall be responsible for the accuracy of the quantities and values used in the cost break-downs submitted for approval.

The sum of the amounts for the line items of work listed in each cost break-down table for highway planting and for irrigation system work shall be equal to the contract lump sum price bid for Highway Planting and Irrigation System, respectively. Overhead and profit shall be included in each individual line item of work listed in a cost break-down table.

No adjustment in compensation will be made in the contract lump sum prices paid for highway planting and irrigation system due to differences between the quantities shown in the cost break-downs furnished by the Contractor and the quantities required to complete the work as shown on the plans and as specified in these special provisions.

Individual line item values in the approved cost break-down tables will be used to determine partial payments during the progress of the work and as the basis for calculating an adjustment in compensation for the contract lump sum items of highway planting and irrigation system due to changes in line items of work ordered by the Engineer. When the total of ordered changes to line items of work increases or decreases the lump sum price bid for either Highway Planting or Irrigation System by more than 25 percent, the adjustment in compensation for the applicable lump sum item will be determined in the same manner specified for increases and decreases in the total pay quantity of an item of work in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.

HIGHWAY PLANTING COST BREAK-DOWN

Contract No. 04-299004

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT
Roadside Clearing	LS	Lump sum		
Prepare Hole	EA	1880		
Foliage Protectors	EA	17		
Cultivate	SQYD	2120		
Soil Amendment	CY	210		
Mulch	CY	240		
Commercial Fertilizer (Granular)	LB	58		
Commercial Fertilizer (Slow Release)	LB	37		
Plant (Group A)	EA	1720		
Plant (Group A2)	EA	130		
Plant (Group B)	EA	22		
Plant (Group M)	EA	3700		
Turf (Sod)	SQFT	1220		

TOTAL _____

IRRIGATION SYSTEM COST BREAK-DOWN

Contract No. 04-299004

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT
Armor-clad Conductors	LS	Lump sum		
1" Electric Remote Control Valve	EA	17		
24-Station Irrigation Controller (Wall Mounted)	EA	1		
1/2" Plastic Pipe (Irrigation Line)	LF	50		
3/4" Plastic Pipe (PR 200) (Supply Line)	LF	3390		
1" Plastic Pipe (PR 200) (Supply Line)	LF	1060		
1 1/4" Plastic Pipe (PR 200) (Supply Line)	LF	490		
1 1/2" Plastic Pipe (PR 200) (Supply Line)	LF	50		
2" Plastic Pipe (PR 200) (Supply Line)	LF	600		
Sprinkler (Type A-6)	EA	44		
Sprinkler (Type B-2)	EA	79		
Sprinkler (Type C-2)	EA	231		
Sprinkler (Type D-1)	LF	2300		
2" Wye Strainer	EA	3		
1" Filter Assembly Unit	EA	3		
1" Manual Control Valve	EA	1		
Ball Valves	EA	5		
3/4" Quick Coupling Valve	EA	4		
Flush Caps	EA	6		

TOTAL _____

10-2.02 EXISTING HIGHWAY PLANTING

In addition to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications, work performed in connection with existing highway planting shall conform to the provisions in "Existing Highway Facilities," of these special provisions.

Replacement planting shall conform to the provisions in "Preservation of Property" of these special provisions.

MAINTAIN EXISTING PLANTED AREAS

Existing planted areas, designated on the plans to be maintained, shall be maintained throughout the life of the contract in conformance with these special provisions.

Attention is directed to "Preservation of Property" of these special provisions.

Existing plants shall be watered in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Existing planted areas to be maintained shall be inspected for deficiencies by the Contractor in the presence of the Engineer. Deficiencies requiring corrective action shall include weeds; dead, diseased, or unhealthy plants; missing plant stakes and tree ties; inadequate plant basins; and other deficiencies needing corrective action to promote healthy plant life. The inspection shall be completed within 15 days after the start of work.

Deficiencies found during the inspection shall be corrected within 15 days after the inspection ends. Correction of deficiencies, as directed by the Engineer, will be paid for as extra work in conformance with the provisions in Section 4-1.03D, "Extra Work," of the Standard Specifications.

After deficiencies have been corrected, the Contractor shall perform work to maintain existing planted areas in a neat appearance and to promote healthy plant growth. The work shall include the following:

- A. Weeds shall be killed before the weeds reach the seed stage of growth or exceed 6 inches in length.
- B. Trash, debris and weeds shall be removed from existing planted areas. Weeds shall be killed prior to removal. Trash, debris and weed removal in ground cover areas shall extend beyond the outer limits of ground cover areas to the adjacent edges of paving, fences and proposed plants and planting areas, and a 6-foot diameter area centered at each existing tree and shrub outside of existing ground cover areas.
- C. Existing plant basins shall be kept well-formed and free of silt. If existing plant basins require repairs, and the plant basins contain mulch, the mulch shall be replaced after the plant basins have been repaired.
- D. When a portion of a new automatic irrigation system is completed, the existing plants to be watered by that portion of the irrigation system shall be watered automatically.
- E. Pesticides for maintaining existing planted areas shall conform to the provisions in "Pesticides" of these special provisions.

The contract lump sum price paid for maintain existing planted areas shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in maintain existing planted areas, complete in place, as shown on the plans, as specified in the standard specifications and these special provisions, and as directed by the Engineer.

REMOVE EXISTING PLANTS FOR TRENCHING

Removing existing plants for trenching shall conform to the provisions in Section 20-5.026, "Remove Existing Plants for Trenching," of the Standard Specifications and these special provisions.

Removing existing plants for trenching work shall consist of removing ground cover, pruning trees and shrubs within trench locations, and disposing of removed ground cover and prunings.

Replacement of removed ground cover within the maximum 6-foot width, as specified in Section 20-5.026, "Remove Existing Plants for Trenching," of the Standard Specifications, will not be required.

Trees and shrubs adjacent to dikes, walks, fences, guard railing, and pavement edges may be pruned back 10 feet from these facilities to facilitate trenching work. When trenching is to be performed adjacent to other trees and shrubs that cannot be avoided, the trees and shrubs may be pruned upon receipt of prior written approval of the Engineer.

Pruning shall include removal of deadwood, suckers, and broken or bruised branches one inch or larger in diameter. Pruning shall conform to the provisions in Section 20-4.055, "Pruning," of the Standard Specifications.

Removed ground cover and pruned materials shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. At the Contractor's option, removed ground cover and prunings may be reduced to chips. Chipped materials shall be spread within the highway right of way where designated by the Engineer.

Shrubs adjacent to dikes, fences, guard railing, and the edge of pavement within the 10-foot pruned area designated above, that in the opinion of the Engineer should be removed after pruning, shall be removed and disposed of. Removing and disposing of the shrubs not otherwise provided for will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

PRUNE EXISTING PLANTS

Existing plants, as determined by the Engineer, shall be pruned. Pruning of the existing plants, except as otherwise provided in these special provisions, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES

The work performed in connection with the various existing highway irrigation system facilities shall conform to the provisions in "Existing Highway Facilities," of these special provisions.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

LOCATE EXISTING CROSSOVERS AND CONDUITS

Existing crossovers and conduits shown on the plans to be incorporated in the new work shall be located in conformance with the provisions for locating conduits in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

Unless otherwise directed by the Engineer, existing crossovers and conduits shown on the plans to be incorporated in the new work shall be located prior to performing work on irrigation systems.

If debris is encountered in the ends of conduits, the debris shall be removed prior to performing other work in the conduits. Removal of debris within the first 3 feet in these conduits shall be at the Contractor's expense. If debris is encountered in the conduits more than 3 feet from the ends of the conduits, the additional debris shall be removed as directed by the Engineer and the removal work will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

REMOVE EXISTING IRRIGATION FACILITIES

Existing irrigation facilities where shown on the plans to be removed, shall be removed. Facilities that are more than 6 inches below finished grade.

Immediately after disconnecting an existing irrigation facility to be removed or abandoned from an existing facility to remain, the remaining facility shall be capped or plugged, or shall be connected to a new or existing irrigation facility.

Facilities to be removed shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

10-2.04 HIGHWAY PLANTING

The work performed in connection with highway planting shall conform to the provisions in Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

HIGHWAY PLANTING MATERIALS

Mulch

Mulch shall be wood chips.

Commercial Fertilizer (Granular)

Commercial fertilizer (granular) for turf (sod) shall be a pelleted or granular form and shall fall within 20 percent of the following guaranteed chemical analysis:

Ingredient	Percentage
Nitrogen	20
Phosphoric Acid	27
Water Soluble Potash	5

Commercial Fertilizer (Slow Release)

Commercial fertilizer (slow release) for plant (Groups A, A2 & B) shall be a pelleted or granular form, shall be slow or controlled release with a nutrient release over an 8-month to 12-month period, and shall fall within the following guaranteed chemical analysis range:

Ingredient	Percentage
Nitrogen	16-21
Phosphoric Acid	6-8
Water Soluble Potash	4-10

Commercial fertilizer (slow release) for turf (sod) shall be a pelleted or granular form, shall be slow or controlled release with a nutrient release over an 2-month to 3-month period, and shall fall within 20 percent of the following guaranteed chemical analysis:

Ingredient	Percentage
Nitrogen	26
Phosphoric Acid	0
Water Soluble Potash	3

Soil Amendment

Soil amendment shall be compost.

The compost producer shall be fully permitted in accordance with requirements of the California Integrated Waste Management Board (CIWMB), Local Enforcement Agencies (LEA) and any other State and Local Agencies that regulate Solid Waste Facilities. If exempt from State permitting requirements, the composting facility shall certify that it follows all guidelines and procedures for production of compost meeting the environmental health standards of Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7.

The compost producer shall be a participant in United States Composting Council’s (“USCC”) Seal of Testing Assurance (“STA”) program.

At Contractor's option, compost shall be derived from any single, or mixture of the following feedstock materials:

- A. Green material consisting of chipped, shredded, or ground vegetation; or clean processed recycled wood products.
- B. Class A, exceptional quality biosolids composts.
- C. Manure.
- D. Mixed food waste.

Feedstock materials shall be composted to reduce weed seeds, pathogens and deleterious materials in conformance with Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7, Section 17868.3

Compost shall not be derived from mixed municipal solid waste. Compost shall not contain paint, petroleum products, herbicides, fungicides or other chemical residues harmful to animal life or plant growth. Compost shall possess no objectionable odors.

Metal concentrations in compost shall not exceed the maximum metal concentrations listed in Title 14, California Code of Regulations, Division 7, Chapter 3.1, Section 17868.2.

Compost shall conform to the following:

Property	Test Method	Requirement
pH	*TMECC 04.11-A Elastometric pH 1:5 Slurry Method pH Units	6.0–8.5
Soluble Salts	TMECC 04.10-A Electrical Conductivity 1:5 Slurry Method dS/m (mmhos/cm)	0-10.0
Moisture Content	TMECC 03.09-A Total Solids & Moisture at 70+/- 5 deg C	30-60

	% Wet Weight Basis	
Organic Matter Content	TMECC 05.07-A Loss-On-Ignition Organic Matter Method (LOI) % Dry Weight Basis	30–65
Maturity	TMECC 05.05-A Germination and Vigor Seed Emergence Seedling Vigor % Relative to Positive Control	80 or Above 80 or Above
Stability	TMECC 05.08-B Carbon Dioxide Evolution Rate mg CO ₂ -C/g OM per day	8 or below
Particle Size	TMECC 02.02-B Sample Sieving for Aggregate Size Classification % Dry Weight Basis	Inches % Passing 5/8 95% 3/8 70%
Pathogen	TMECC 07.01-B Fecal Coliform Bacteria < 1000 MPN/gram dry wt.	Pass
Pathogen	TMECC 07.01-B Salmonella < 3 MPN/4 grams dry wt.	Pass
Physical Contaminants	TMECC 02.02-C Man Made Inert Removal and Classification: Plastic, Glass and Metal % > 4mm fraction	Combined Total: < 1.0
Physical Contaminants	TMECC 02.02-C Man Made Inert Removal and Classification: Sharps (Sewing needles, straight pins and hypodermic needles) % > 4mm fraction	None Detected

*TMECC refers to “Test Methods for the Examination of Composting and Compost,” published by the United States Department of Agriculture and the United States Compost Council (USCC).

Prior to application, the Contractor shall provide the Engineer with a copy of the compost producer's Compost Technical Data Sheet and a copy of the compost producers STA certification. The Compost Technical Data Sheet shall include laboratory analytical test results, directions for product use, and a list of product ingredients.

Prior to application, the Contractor shall provide the Engineer with a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

ROADSIDE CLEARING

Prior to preparing planting and mulch areas, or commencing irrigation trenching operations for planting areas, trash and debris shall be removed from these areas and a distance of 10 feet beyond the edges of those areas. At locations where proposed planting and mulch areas are 12 feet or more from the edges of dikes, curbs, sidewalks, fences, walls, paved shoulders and existing planting to remain or to be maintained, the clearing limit shall be 6 feet beyond the outer limits of the proposed planting or mulch area.

In addition to removing trash and debris, the project area shall be cleared as specified herein:

- A. Existing plants, where shown on the plans to be removed, shall be removed.
- B. At the option of the Contractor, removed trees and shrubs may be reduced to chips. Chipped material shall be spread within the project limits at locations designated by the Engineer. Chipped material shall not be substituted for mulch, nor shall the chipped material be placed within areas to receive mulch.

- C. Weeds shall be killed and removed within proposed ground cover areas and within the area extending beyond the outer limits of the proposed ground cover areas to the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, existing planting and fences. At those locations where proposed ground cover areas are 12 feet or more from the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, and fences, the clearing limit shall be 6 feet beyond the outer limits of the proposed ground cover areas.
- D. Weeds shall be killed and removed within proposed mulch areas and within the area extending beyond the outer limits of the proposed mulch areas to the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, existing planting and fences. At those locations where proposed mulch areas are 12 feet or more from the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, and fences, the clearing limit shall be 6 feet beyond the outer limits of the proposed mulch areas.
- E. Weeds shall be killed and removed within planting areas where plants are to be planted in groups or rows 15 feet or less apart and from within an area extending 6 feet beyond the outer limits of the groups or rows of plants.
- F. Weeds shall be killed and removed within an area 6 feet in diameter centered at each plant location where the plants are to be planted more than 15 feet apart and are located outside of ground cover areas.
- G. Weeds shall be killed and removed within an area 2 feet in diameter centered at each liner plant location where the plants are planted more than 10 feet apart. At locations where liner plants are to be planted less than 10 feet apart, weeds shall be killed and removed within the entire area.
- H. Weeds outside of mulched areas, ground cover, plant basins, and turf (sod) areas shall be controlled by mowing. Limits of mowing shall extend from the weeds to be killed areas out to the edges of pavement, dikes, curbs, sidewalks, and perimeter fences.
- I. Roadside clearing for turf (sod) areas shall also consist of mowing weeds in the areas to be planted until the start of the turf (sod) operation.

After the initial roadside clearing is complete, additional roadside clearing work shall be performed as necessary to maintain the areas, as specified above, in a neat appearance until the start of the plant establishment period. This work shall include the following:

- A. Trash and debris shall be removed.
- B. Rodents shall be controlled.
- C. Weed growth shall be killed before the weeds reach the seed stage of growth or exceed 6 inches in length, whichever occurs first.
- D. Weeds in plant basins, including basin walls, shall be removed by hand pulling, after the plants have been planted.
- F. Areas outside the areas specified to be cleared of weeds shall be mowed.

Weed Control

Weed control shall also conform to the following:

- A. Stolon type weeds shall be killed with glyphosate.
- B. Removed weeds shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.
- C. Areas to be mowed shall be mowed when weed height exceeds 12 inches. Weeds shall be mowed to a height of 2 inches to 6 inches.

Roadside clearing work shall not include work required to be performed as clearing and grubbing as specified in Section 16, "Clearing and Grubbing," of the Standard Specifications.

PESTICIDES

Pesticides used to control weeds shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specifications. Except as otherwise provided in these special provisions, pesticide use shall be limited to the following materials:

- Cacodylic Acid
- Diquat
- Fluazifop-butyl
- Glyphosate
- Isoxaben (Preemergent)
- Sethoxydim

Oxadiazon - 50 percent WP (Preemergent)
Oryzalin (Preemergent)
Trifluralin (Preemergent)
Napropamide (Preemergent)

Granular preemergents may be used when applied to areas that will be covered with mulch, excluding plant basins. Granular preemergents shall be limited to the following materials:

Dichlobenil (Preemergent)
Oxadiazon (Preemergent)

Granular preemergents shall be applied prior to the application of mulch. Mulch applications shall be completed in these areas on the same working day. Photosensitive dye will not be required.

Glyphosate shall be used to kill stolon type weeds.

Oxadiazon shall be of the emulsifiable concentration or wettable powder type, except when Oxadiazon is used under mulch in conformance with these special provisions.

Prior to the application of preemergents, ground cover plants shall have been planted a minimum of 3 days and shall have been thoroughly watered.

A minimum of 100 days shall elapse between applications of preemergents.

Except for ground cover plants, preemergents shall not be applied within 18 inches of plants.

If the Contractor elects to request the use of other pesticides on this project, the request shall be submitted, in writing, to the Engineer not less than 15 days prior to the intended use of the other pesticides. Except for the pesticides listed in these special provisions, no pesticides shall be used or applied without prior written approval of the Engineer.

Pesticides shall not be applied within the limits of the plant basins. Pesticides shall not be applied in a manner that allows the pesticides to come in contact with the foliage and woody parts of the plants.

PREPARING PLANTING AREAS

Plants adjacent to drainage ditches shall be located so that after construction of the basins, no portion of the basin walls shall be less than the minimum distance shown on the plans for each plant involved.

CULTIVATE

Areas to be planted with liners and turf (sod) shall be cultivated.

Immediately prior to cultivation, soil amendment and commercial fertilizer shall be added to the areas to be cultivated. Soil amendment shall be added at the rate shown on the plans and commercial fertilizer (granular) shall be applied at the rate of 3 pounds per 1,000 square feet. Soil amendment and fertilizer shall be thoroughly mixed with the soil.

After cultivation is complete and the irrigation systems have been installed and the plant holes have been excavated and backfilled, no further planting work shall be done in the cultivated areas for a period of 20 days, except the soil shall be kept sufficiently moist to germinate weeds. Weeds that germinate shall be killed.

PLANTING

Backfill material for plant holes shall be a mixture of soil and soil amendment. The quantity of soil amendment shall be as shown on the Plant List. Soil amendment shall conform to the provisions in Section 20-2.03, "Soil Amendment," of the Standard Specifications. Backfill material shall be thoroughly mixed and uniformly distributed throughout the entire depth of the plant hole without clods and lumps.

Commercial fertilizer (slow release) shall be applied or placed at the time of planting and at the rates shown on the Plant List and in conformance with the provisions in Section 20-4.05, "Planting," of the Standard Specifications and these special provisions.

A granular preemergent shall be applied to areas to be covered with mulch outside of plant basins in conformance with the provisions in "Pesticides" of these special provisions.

Mulch placed in areas outside of plant basins shall be spread to a uniform depth of 3 inches.

Mulch shall be spread from the outside of the proposed plant basin to the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, fences, and existing plantings. If the proposed plant material is 12 feet or more from the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, fences, and other existing plantings, the mulch shall be spread 6 feet beyond the outside edge of the proposed plant basins.

Mulch shall not be placed within 3 feet of the centerline of earthen drainage ditches, within 3 feet of the edge of paved ditches, and within 3 feet of the centerline of drainage flow lines.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions regarding functional tests of the irrigation systems. Planting shall not be performed in an area until the functional test has been completed for the irrigation system serving that area.

LINER PLANTS

Liner plants shall be furnished in containers with a minimum size of 2" diameter by 5" deep. Liner plant containers made of biodegradable material shall not be used. All liner plants shall be removed from their containers at the time of planting.

At the option of the Contractor, seedling plants may be furnished in lieu of liner plants. Seedling plants shall be bare root. If the Contractor elects to furnish seedling plants, the plants will be measured and paid for by the unit as plant (Group M).

Liner plants shall not be planted before September 15 nor after April 15 and not until the soil is moist to a minimum depth of 8 inches, unless otherwise approved in writing by the Engineer.

Planting holes for liner plants shall be large enough to accommodate the total length and width of the roots.

TURF (SOD)

Turf (sod) shall be placed on the areas shown on the plans as "Turf."

Sod shall be a mixture of tall fescue and bluegrass varieties, in proportions, of ninety percent tall fescue and ten percent bluegrass, and shall be healthy field grown sod containing not more than 1/2 inch thick thatch. The age of the sod shall be not less than 8 months or more than 16 months.

Sod shall be grown in conformance with California agricultural codes. The sod shall be free from disease, weeds, insects, and undesirable types of grasses and clovers. Soil upon which the sod has been grown shall contain less than 50 percent silt and clay.

Sod shall be machine cut at a uniform soil thickness of 5/8 inch \pm 1/4 inch, not including top growth and thatch.

A Certificate of Compliance for the sod shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Sod shall be protected with tarps or other protective covers during delivery and shall not be allowed to dry out during delivery or prior to placement.

Areas to be planted to sod shall be cultivated in conformance with the provisions in "Cultivate" of these special provisions.

Weeds and debris shall be removed before cultivation and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Soil amendment and commercial fertilizer (granular) shall be applied at the rates in conformance with the provisions in "Cultivate" of these special provisions.

After cultivation, installation of irrigation systems, and excavation and backfilling of plant holes are completed, areas to be planted to sod shall be fine graded and rolled. Areas to be planted to sod shall be graded to drain and shall be smooth and uniform prior to placing sod. Areas to be planted to sod adjacent to sidewalks, concrete headers, header boards, and other paved borders and surfaced areas shall be 1-1/2 inches \pm 1/4 inch below the top grade of the facilities, after fine grading, rolling, and settlement of the soil.

Sod shall be placed so that the ends of adjacent strips of sod are staggered a minimum of 2 feet. Edges and ends of sod shall be placed firmly against adjacent sod and against sidewalks, concrete headers, header boards, and other paved borders and surfaced areas.

After placement of the sod, the entire sodded area shall be lightly rolled to eliminate air pockets and to ensure close contact with the soil. After rolling, the sodded areas shall be watered so that the soil is moistened to a minimum depth of 4 inches. Sod shall not be allowed to dry out.

If irregular or uneven areas appear before or during the plant establishment period, these areas shall be restored to a smooth and even appearance.

When the turf (sod) has reached a height of 6 inches the turf shall be mowed to a height of 2-to 3 inches. Turf (sod) edges, including edges adjacent to sidewalks, concrete headers, header boards, and other paved borders and surfaced areas, shall be trimmed to a uniform edge not extending beyond the edge of turf or the facilities. Mowed and trimmed growth shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. Trimming shall be repeated whenever the edge of turf exceeds one inch.

Mowing and trimming turf (sod) and disposing of mowed material, during the plant establishment period, will be paid for in conformance with the provisions in "Plant Establishment Work" of these special provisions.

FOLIAGE PROTECTOR

Foliage protectors shall be installed in conformance with the details shown on the plans, the provisions in Section 20-2.13A, "Foliage Protector," and Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

Each foliage protector shall be held in place with two round stakes at least 2 inch nominal diameter or square stakes at least 2 inch x 2 inch in cross sectional dimensions. Stakes shall be made of wood and at least 5 feet in length. Support stakes shall be installed vertically, embedded in the soil, and fastened to the wire cylinder at 6 inch maximum centers. Wire cylinder shall be snug against stakes yet loose enough to be raised for application of pesticides or to perform weeding within the plant basin.

Steel stakes shall not be used.

PLANT ESTABLISHMENT WORK

The plant establishment period shall be Type 2 and shall not be less than 250 working days.

If liner planting cannot be performed within the time limits specified under "Liners" of these special provisions and the Engineer determines that the work except liner planting and plant establishment work has been completed, the Engineer will notify the Contractor in writing of the start of the plant establishment period.

Liner planting not performed prior to the start of the plant establishment period shall be performed during the plant establishment period. The work involved in preparing areas to receive liner plants and applying soil amendment and commercial fertilizer shall be in conformance with the provisions in "Planting" and "Cultivation" of these special provisions.

Attention is directed to "Relief From Maintenance and Responsibility" in these special provisions regarding relief from maintenance and protection.

Commercial fertilizer (slow release) shall be applied to trees, shrubs, grasses, and perennials, vines and ground cover during the first week of March and September of each year. Commercial fertilizer shall be applied at the rates shown on the plans and shall be spread with a mechanical spreader wherever possible.

Commercial fertilizer (slow release) shall be applied to turf (sod) during the first week of March and September of each year. Commercial fertilizer shall be applied at the rate of 2.5 pounds per 1,000 square feet and shall be spread with a mechanical spreader wherever possible.

The center to center spacing of replacement plants for unsuitable liner and ground cover plants shall be determined by the number of completed plant establishment working days at the time of replacement and the original spacing in conformance with the following:

ORIGINAL SPACING (Inches)	SPACING OF REPLACEMENT GROUND COVER PLANTS (Inches)		
	Number of Completed Plant Establishment Working Days		
	1-125	126-190	191-End of Plant Establishment
18	18	12	9
36	36	24	18
72	72	48	36

Weeds within plant basins, including basin walls and ground cover, shall be controlled by hand pulling.

Weeds within mulched and ground cover areas and outside of plant basins shall be controlled by killing.

Weeds outside of mulched areas, plant basins, ground cover, the median, and paved areas shall be controlled by mowing. At locations where proposed planting areas are 12 feet or more from the edges of existing plantings to remain and from shoulders, dikes, curbs, sidewalks, fences, and walls, the mowing limit shall be 6 feet beyond the outer limits of the proposed planting area.

Weeds within median areas, pavement, curbs, sidewalk, and other surfaced areas shall be controlled by killing.

Vines shall be trained onto fences and walls.

At the option of the Contractor, plants of a larger container size than those originally specified may be used for replacement plants during the first 125 working days of the plant establishment period. The use of plants of a larger container size than those originally specified for replacement plants shall be at the Contractor's expense.

After 125 working days of the plant establishment period have been completed, replacement of plants, except for ground cover plants, shall be one-gallon size for pot and liner size plants; 5-gallon size for one-gallon size plants; 15-gallon size for 5-gallon size plants; and other plant replacement plants shall be the same size as originally specified.

When ordered by the Engineer, one application of a preemergent pesticide conforming to the provisions in "Pesticides" of these special provisions, shall be applied between 40 working days and 50 working days prior to completion of the plant establishment period. This work will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Wye strainers shall be cleaned at least 15 days prior to the completion of the plant establishment period.

Previously installed filters shall be removed, cleaned and reinstalled at least 15 days prior to the completion of the plant establishment period.

The final inspection shall be performed in conformance with the provisions in Section 5-1.13, "Final Inspection," of the Standard Specifications and shall be completed a minimum of 20 working days before the estimated completion of the contract.

Turf areas shall be mowed in conformance with the provisions in "Turf (Sod)" of these special provisions.

Full compensation for mowing and trimming turf (sod) and disposing of mowed and trimmed material during the plant establishment period shall be considered as included in the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

10-2.05 IRRIGATION SYSTEMS

Irrigation systems shall be furnished and installed in conformance with the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications, except materials containing asbestos fibers shall not be used.

Attention is directed to the provisions in "Obstructions" of these special provisions, regarding work over or adjacent to existing underground facilities. Excavation for proposed irrigation facilities shall not be started until the existing underground facilities have been located.

Method A pressure testing shall conform to the provisions in Section 20-5.03H(1), "Method A", of the Standard Specifications, except leaks that develop in the tested portion of the system shall be located and repaired after each test period when a drop of more than 5 pounds per square inch is indicated by the pressure gage. After the leaks have been repaired, the one hour pressure test shall be repeated and additional repairs made until the drop in pressure is 5 pounds per square inch or less.

VALVE BOXES

Valve boxes shall conform to the provisions in Section 20-2.24, "Valve Boxes," of the Standard Specifications, except as otherwise provided herein.

Valve boxes shall be precast portland cement concrete.

Covers for concrete valve boxes shall be glass fiber reinforced plastic.

Valve boxes shall be identified on the top surface of the covers by branding the appropriate abbreviations for the irrigation facilities contained in the valve boxes as shown on the plans. Valve boxes that contain remote control valves shall be identified by the appropriate letters and numbers (controller and station numbers). The letters and numbers shall be 2 inches in height.

BALL VALVES

Ball valves shall be furnished and installed as shown on the plans and in conformance with these special provisions.

Ball valves shall be manufactured from Chlorinated Polyvinyl Chloride (CPVC) or polyvinyl chloride (PVC) and shall conform to the following:

Specification	Minimum Requirement
Non-shock cold water working pressure for 3/4-inch to 4-inch valves	235 psi
Non-shock cold water working pressure for 6-inch valves	150 psi
Seats	PTFE (Teflon)
O-Ring Seals	EPDM or Viton

Ball valves shall be of the same size as the pipeline which the valves serve, unless otherwise noted on the plans.

Ball valves shall be installed in a valve box.

ELECTRIC AUTOMATIC IRRIGATION COMPONENTS

Irrigation Controllers

Irrigation controllers shall be single, hybrid electromechanical microprocessor based solid-state independent controllers conforming to the following:

- A. Irrigation controllers shall be fully automatic and shall operate a complete 14-day or longer irrigation program.
- B. A dial switch or switches shall be provided on the face of the control panel that will turn the irrigation controller "on" or "off" and provide for automatic or manual operation. Manual operation shall allow cycle start at the desired station and shall allow activation of a single station.
- C. The watering time of each station shall be displayed on the face of the control panel.
- D. The irrigation controller and the low voltage output source shall be protected by fuses, surge protectors or circuit breakers.
- E. The irrigation controller mechanism, panel and circuit board shall be connected to the low voltage control and neutral conductors by means of plug and receptacle connectors located in the irrigation controller enclosure.
- F. Each station shall have a variable or incremental timing adjustment with a range of 0 to 2 hours in one minute increments, or 2 to 12 hours in ten-minute increments.
- G. Irrigation controllers shall be capable of a minimum of 2 program schedules.
- H. Irrigation controllers shall have an output that can energize a remote control valve (master) and a pump start circuit in addition to the normal stations.
- I. Where direct burial conductors are to be connected to the terminals strip, the conductors shall be connected with the proper size open-end crimp-on wire terminals. No exposed wire shall extend beyond the crimp of the terminal and the wires shall be parallel on the terminal strip.

Attention is directed to the provisions in "Electric Service (Irrigation)" of these special provisions regarding electrical power for irrigation controllers and irrigation controller enclosure cabinets.

Attention is directed to the provisions in "Booster Pumps" of these special provisions, regarding electrical power for irrigation controllers.

Electric Remote Control Valves

Electric remote control valves shall conform to the provisions in Section 20-2.23, "Control Valves," of the Standard Specifications and the following:

- A. Valves shall be glass filled nylon, brass, bronze, or cast iron construction.
- B. Glass filled nylon or brass valves shall be angle pattern (bottom inlet) or straight pattern (side inlet) as shown on the plans.
- C. Cast iron valves shall be combination angle pattern (bottom inlet and side inlet) installed as an angle pattern (bottom inlet), as shown on the plans.
- D. Electric remote control valves shall be outfitted with adjustable pressure regulators as shown on the plans. Pressure regulators shall be compatible for use with the electric remote control valves and shall be of the same manufacturer as the electric remote control valves. Pressure regulators shall regulate and maintain the outlet pressure regardless of the incoming pressure. Pressure regulators shall withstand a cold water working pressure of 200 psi. The Contractor shall adjust the pressure regulators to provide proper operation of the irrigation system downstream of the electric remote control valves.

Pull Boxes

Pull box installations shall conform to the provisions in Section 20-5.027I, "Conductors, Electrical Conduits and Pull Boxes," of the Standard Specifications.

Conductors

Low voltage, as used in this section "Conductors," shall mean 36 V or less.

Low voltage control and neutral conductors in pull boxes and valve boxes, at irrigation controller terminals, and at splices shall be marked as follows:

- A. Conductor terminations and splices shall be marked with adhesive backed paper markers or adhesive cloth wrap-around markers, with clear, heat-shrinkable sleeves sealed over the markers.

- B. Non-spliced conductors in pull boxes and valve boxes shall be marked with clip-on, "C" shaped, white extruded polyvinyl chloride sleeves. Marker sleeves shall have black, indented legends of uniform depth with transparent overlays over the legends and "chevron" cuts for alignment of 2 or more sleeves.

Markers for the control conductors shall be identified with the appropriate number or letter designations of irrigation controllers and station numbers. Markers for neutral conductors shall be identified with the appropriate number or letter designations of the irrigation controllers.

The color of low voltage neutral and control conductor insulation, except for the striped portions, shall be homogeneous throughout the entire thickness of the insulation.

Insulation for conductors may be UL listed polyethylene conforming to UL44 test standards with a minimum insulation thickness of 41 mils for wire sizes 10AWG and smaller.

ARMOR-CLAD CONDUCTORS

Armor-clad conductors shall be used in direct burial applications from pull boxes adjacent to irrigation controller to remote control valves and other irrigation facilities in conformance with the details shown on the plans and these special provisions.

Armor-clad conductors shall conform to the following:

- A. Conductors shall be the proper size for the application, and shall be solid, uncoated copper with a conductor size not less than 90 percent of the AWG diameter required.
- B. At the Contractor's option, conductor insulation coverings shall be either of the following:
 - 1. Polyvinyl chloride (PVC) conforming to UL style, Type UF 60°C, 600 V. Average thickness of insulation shall be not less than 60 mils, with a minimum thickness of 54 mils, or
 - 2. UL listed polyethylene conforming to UL44 test standards with a minimum insulation thickness of 41 mils for wire sizes 10AWG and smaller.
- C. Armor shall be a minimum 0.005-inch thick by 0.50-inch wide Type 304 stainless steel tape that is helically wrapped over each conductor with a 33 percent minimum overlap.
- D. Outer jacket for conductors shall be sunlight resistant PVC and shall conform to the Insulated Power Cable Engineer's Association (ICEA) S-61-402, NEMA Standard WC5, and UL Listing 1263. Nominal thickness of the outer jacket shall be 30 mils with a minimum thickness of 24 mils.

IRRIGATION SYSTEMS FUNCTIONAL TEST

Functional tests for the irrigation controllers and associated automatic irrigation systems shall conform to the provisions in Section 20-5.027J, "Testing," of the Standard Specifications and these special provisions.

Tests shall demonstrate to the Engineer, through one complete cycle of the irrigation controllers in the automatic mode, that the associated automatic components of the irrigation systems operate properly. If automatic components of the irrigation systems fail a functional test, these components shall be repaired at the Contractor's expense and the testing repeated until satisfactory operation is obtained.

Associated automatic components shall include, but not be limited to, remote control valves.

Upon completion of work on an irrigation system, including correction of deficiencies and satisfactory functional tests for the systems involved, the plants to be planted in the area watered by the irrigation system may be planted provided the planting areas have been prepared as specified in these special provisions.

PIPE

Plastic Pipe

Plastic pipe supply lines shall be polyvinyl chloride (PVC) 1120 or 1220 pressure rated pipe with the minimum pressure rating (PR) of 200.

Plastic pipe supply lines less than 4 inches in diameter shall have solvent cemented type joints. Primers shall be used on the solvent cemented type joints.

Plastic pipe (irrigation lines) shall be installed on the surface as shown on the plans and in accordance with manufacturer's instructions.

A nonhardening joint compound shall be used in place of the pipe thread sealant tape conforming to the provisions in Section 20-5.03E, "Pipe," of the Standard Specifications. Joint compounds shall be applied in conformance with the manufacturer's recommendations.

SPRINKLERS

Sprinklers shall conform to the type, pattern, material, and operating characteristics listed in the "Sprinkler Schedule" shown on the plans.

SPRINKLER (TYPE D)

Type D sprinklers shall be cylindrical, inline plastic, nonadjustable, pressure compensating emitters with automatic flushing action. Emitter shall be regulated by silicone wafer diaphragms. Emitters shall have the flow rate and operating pressure range shown on the plans.

Emitters shall be integral within the flexible tubing spaced 24" apart and installed as shown on the plans and in conformance with the manufacturer's written instructions. Two copies of the written instructions shall be furnished to the Engineer prior to installation.

Emitters shall be equipped with dual outlet ports which can function as micro air relief valve.

Flexible tubing for the emitters shall be ultraviolet resistant virgin polyethylene plastic containing 2 percent to 3 percent carbon black. The size of the tubing shall be as recommended by the manufacturer of the emitter.

Emitters and discharge ends of tubing shall be held in place, within the basin and in uniform contact with the soil surface, without bulges or kinks approximately 36 inches on center by plastic or metal stakes. Stakes shall be as recommended by the manufacturer of the emitter.

WYE STRAINERS

Wye strainers shall be installed on the upstream side of the electric remote control valves as shown on the plans.

When garden valves are opened, discharge shall be up and out of the valve box.

FLUSH CAPS

Flush caps shall consist of compression fitting with threaded flush cap manufactured by the same company for sprinkler (Type D). Flush caps shall be installed at the ends of supply lines for Type D sprinklers as shown on the plans and in accordance with manufacturer's instructions.

FILTER ASSEMBLY UNIT

A filter assembly unit shall consist of a filter housing, a reusable filter cartridge, a ball valve, fittings, pipe, and valve box as shown on the plans.

Filter assembly units shall withstand a cold water working pressure of 150 psi.

Pressure loss through the filter assembly units shall not exceed the following:

FILTER ELEMENT SIZE (inches)	MAX FLOW RATE (GPM)	PRESSURE LOSS AT MAX FLOW (psi)
1	25	11
1.5	60	3.8
2	120	10.5

Filter housings shall be manufactured of reinforced polypropylene plastic.

Filter cartridges shall be reusable stainless steel and shall be capable of 200 size mesh filtration.

Ball valves in filter assembly units shall be polyvinyl chloride (PVC). The ball seats shall be high molecular weight-high density polyethylene.

FINAL IRRIGATION SYSTEM CHECK

A final check of existing and new irrigation facilities shall be performed not more than 40 working days and not less than 30 working days prior to acceptance of the contract.

The length of watering cycles using potable water measured by water meters for the final check of irrigation facilities will be determined by the Engineer.

Remote control valves connected to new irrigation controllers shall be checked for automatic performance when the controllers are in automatic mode.

Unsatisfactory performance of irrigation facilities installed or modified by the Contractor shall be repaired and rechecked at the Contractor's expense until satisfactory performance is obtained, as determined by the Engineer.

Repair or replacement of existing irrigation facilities due to unsatisfactory performance shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Nothing in this section "Final Irrigation System Check" shall relieve the Contractor of full responsibility for making good or repairing defective work or materials found before the formal written acceptance of the entire contract by the Director.

Full compensation for checking the irrigation systems prior to the acceptance of the contract shall be considered as included in the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

SECTION 10-3. SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS

10-3.01 DESCRIPTION

Lighting and sign illumination shall conform to the provisions in Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications and these special provisions.

Unless shown otherwise, locations of cabinets, standards, foundations, lighting fixtures, conduits, pull boxes, appurtenances and other similar electrical equipment are approximate and may be changed to suit field conditions or as directed by the Engineer.

10-3.02 COST BREAK-DOWN

Cost break-downs shall conform to the provisions in Section 86-1.03, "Cost Break-Down," of the Standard Specifications and these special provisions.

The Engineer shall be furnished a cost break-down for each contract lump sum item of work described in this Section 10-3.

The cost break-down shall be submitted to the Engineer for approval within 15 days after the contract has been approved. The cost break-down shall be approved, in writing, by the Engineer before any partial payment for the items of electrical work will be made.

10-3.03 FOUNDATIONS

Reinforced cast-in-drilled-hole concrete pile foundations for traffic signal and lighting standards shall conform to the provisions in "Piling" of these special provisions, except payment.

10-3.04 STANDARDS, STEEL PEDESTALS, AND POSTS

Standards, steel pedestals, and posts for traffic signal and lighting standards shall conform to the provisions in Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, "Steel Structures" of these special provisions, and the following requirements.

Steel bolts not designated on the plans as high-strength (HS) or stainless steel shall be for general applications and shall conform to the requirements in ASTM Designation: A 307.

Handhole reinforcement rings for standards, steel pedestals, and posts shall be continuous around the handholes.

10-3.05 CONDUIT

Conduit to be installed underground shall be Type 1 or Type 3 unless otherwise specified. .

The conduit in a foundation and between a foundation and the nearest pull box shall be Type 1.

When Type 3 conduit is placed in a trench (not in pavement or under portland cement concrete sidewalk), after the bedding material is placed and the conduit is installed, the trench shall be backfilled to not less than 4 inches above the conduit with minor concrete conforming to the provisions in Section 90-10, "Minor Concrete," of the Standard Specifications, except the concrete shall contain not less than 421 pounds of cementitious material per cubic yard. The remaining trench shall be backfilled to finished grade with backfill material.

Conduit runs shown on the plans to be located behind curbs may be installed in the street, within 3 feet of, and parallel with the face of the curb, by the "Trenching in Pavement Method" in conformance with the provisions in Section 86-2.05C, "Installation," of the Standard Specifications. Pull boxes shall be located behind the curb or at the locations shown on the plans.

After conductors have been installed, the ends of conduits terminating in pull boxes, service equipment enclosures, and controller cabinets shall be sealed with an approved type of sealing compound.

At those locations where conduit is required to be installed under pavement and existing underground facilities require special precautions in conformance with the provisions in "Obstructions" of these special provisions, conduit shall be placed by the "Trenching in Pavement Method" in conformance with the provisions in Section 86-2.05C, "Installation," of the Standard Specifications.

At other locations where conduit is required to be installed under pavement and if a delay to vehicles will not exceed 5 minutes, conduit may be installed by the "Trenching in Pavement Method."

10-3.06 PULL BOXES

Grout shall not be placed in the bottom of new or existing pull boxes.

10-3.07 CABLES, CONDUCTORS AND WIRING

Splices shall be insulated by "Method B".

10-3.08 BONDING AND GROUNDING

Bonding and grounding shall conform to the provisions in Section 86-2.10, "Bonding and Grounding," of the Standard Specifications and these special provisions.

Bonding jumpers in standards with handholes and traffic pull box lid covers shall be attached by a UL listed lug using 3/16-inch diameter or larger brass or bronze bolts and shall run to the conduit or bonding wire in the adjacent pull box. The grounding jumper shall be visible after the standard has been installed and the mortar pad and cap have been placed on the foundation.

Standards without handholes shall have bonding accomplished by jumpers attached to UL listed ground clamps on each anchor bolt.

For slip base standards or slip base inserts, bonding shall be accomplished by jumpers attached to UL listed ground clamps on each anchor bolt, or a UL listed lug attached to the bottom slip base plate with a 3/16-inch diameter or larger brass or bronze bolt.

Equipment bonding and grounding conductors are required in conduits, except when the conduits contain combinations of loop lead-in cable, fiber optic cable, or signal interconnect cable. A No. 8 minimum, bare copper wire shall run continuously in circuits, except for series lighting circuits, where No. 6 bare copper wire shall run continuously. The bonding wire size shall be increased to match the circuit breaker size in conformance with the Code, or shall be as shown on the plans. Conduits to be installed for future conductors, may omit the copper wire.

Bonding of metallic conduits in metal pull boxes shall be by means of bonding bushings and bonding jumpers connected to the bonding wire running in the conduit system.

10-3.09 SERVICE

Type III service equipment enclosures shall be the aluminum type.

Circuit breakers shall be the cable-in/cable-out type, mounted on non-energized clips. All circuit breakers shall be mounted vertically with the up position of the handle being the "ON" position.

The neutral conductor shall run from the service equipment enclosure to the controller cabinet without splicing to any other neutral conductor.

The clearance between the bottom of the lowest circuit breaker and the bottom of the service equipment enclosure for a Type III-A series shall be 24 inches minimum.

Installation of a barrier type terminal block in service equipment enclosures is not required.

10-3.10 NUMBERING ELECTRICAL EQUIPMENT

The placement of numbers on electrical equipment will be done by others.

10-3.11 LUMINAIRES

Ballasts shall be the lag or lead regulator type.

SECTION 11. (BLANK)

SECTION 12. BUILDING WORK

SECTION 12-1. GENERAL REQUIREMENTS

12-1.01 SCOPE

Building work described herein and as shown on the plans shall conform to the requirements of these special provisions and Sections 1 through 9 of the Standard Specifications. Sections 10 through 95 of the Standard Specifications shall not apply to the work in this Section 12 except when specific reference is made thereto.

The building work to be done consists, in general, of demolishing: restroom facility, picnic shelters, pedestrian ramp with structure, kiosk, and interpretive signs; and constructing restroom facility, picnic shelter, building mechanical and electrical work, pedestrian plaza (including ramp, retaining walls, stairs, drainage and planters), kiosk and such other items or details, not mentioned above, that are required by the plans, Standard Specifications, or these special provisions shall be performed, placed, constructed or installed.

12-1.02 ABBREVIATIONS

Section 1-1.02, "Abbreviations," of the Standard Specifications is amended by adding the following:

AAMA	American Architectural Manufacturers' Association
ACI	American Concrete Institute
AGA	American Gas Association
AITC	American Institute of Timber Construction
AMCA	Air Movement and Control Association
APA	American Plywood Association
ARI	American Refrigeration Institute
ASHRAE	American Society of Heating, Refrigeration and Air Conditioning Engineers
CBC	California Building Code (2001 Edition)
CEC	California Electrical Code (2001 Edition)
CMC	California Mechanical Code (2001 Edition)
CPC	California Plumbing Code (2001 Edition)
CS	Commercial Standards (US Department of Commerce)
ESO	Electrical Safety Orders
FGMA	Flat Glass Marketing Association
FM	Factory Mutual
FS	Federal Specification
ICBO	International Conference of Building Officials
NAAMM	National Association of Architectural Metal Manufacturers
NBFU	National Board Fire Underwriters
NEC	National Electrical Code
NFPA	National Fire Protection Association or National Forests Products Association
PEI	Porcelain Enamel Institute
PS	Product Standard (US Department of Commerce)
RIS	Redwood Inspection Service
SCPI	Structural Clay Products Institute
SMACNA	Sheet Metal and Air Conditioning Contractors' National Association
SSPC	Steel Structures Paint Council
TCA	Tile Council of America
TPI	Truss Plate Institute
UBC	Uniform Building Code (1997 Edition)
WCLIB	West Coast Lumber Inspection Bureau (stamped WCLB)
WCLB	Grade stamp for WCLIB
WIC	Woodwork Institute of California
WWPA	Western Wood Products' Association

12-1.03 GUARANTEE

The Contractor hereby unconditionally guarantees that the building work will be done in accordance with the requirements of the contract, and further guarantees the building work of the contract to be and remain free of defects in workmanship and materials for a period of one year from the date of acceptance of the contract, unless a longer guarantee period is required elsewhere in these special provisions. The Contractor hereby agrees to repair or replace any and all building work, together with any other adjacent work which may be displaced in so doing, that may prove to be not in accordance with the requirements of the contract or that may be defective in its workmanship or material within the guarantee period specified, without any expense whatsoever to the Department, ordinary wear and tear and unusual abuse or neglect excepted.

The performance bond for contract price of the building work, shall remain in full force and effect during the guarantee period.

The Contractor further agrees, that within 10 calendar days after being notified in writing by the Department of any building work not in accordance with the requirements of the contract or any defects in the building work, he shall commence and prosecute with due diligence all work necessary to fulfill the terms of this guarantee, and shall complete the work within a reasonable period of time, and, in the event he fails to comply, he does hereby authorize the Department to proceed to have such work done at the Contractor's expense and he shall honor and pay the cost and charges therefor upon demand. The Department shall be entitled to all costs and expenses, including reasonable attorney's fees, necessarily incurred upon the Contractor's refusal to honor and pay the above costs and charges.

12-1.04 AREAS FOR CONTRACTOR'S USE

No area is available within the contract limits for the exclusive use of the Contractor. The Contractor shall arrange with the Engineer for areas to store equipment and materials within the work area.

12-1.05 COOPERATION

Attention is directed to Sections 7-1.14, "Cooperation," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

Work by State forces will be in progress within the contract limits during the working period for this contract.

The Contractor shall comply with all security policies and normal working hours of the State concerning the Hunter Hill Safety Roadside Rest Area.

The Contractor shall plan his work to minimize interference with State forces and the public. Interruptions to any services for the purpose of making or breaking a connection shall be made only after consultation with and for such time periods as directed by the Engineer.

12-1.06 SUBMITTALS

Working drawings, material lists, descriptive data, samples and other submittals specified in these special provisions shall be submitted for approval in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and these special provisions.

Unless otherwise permitted in writing by the Engineer, all submittals required by these special provisions shall be submitted within 35 days after the contract has been approved.

Attention is directed to the provisions in Section 5-1.01, "Authority of Engineer," of the Standard Specifications. The Engineer may request submittals for materials or products where submittals have not been specified in these special provisions, or may request that additional information be included in specified submittals, as necessary to determine the quality or acceptability of such materials or products.

Attention is directed to Section 6-1.05, "Trade Names and Alternatives," of the Standard Specifications. The second indented paragraph of the first paragraph of said Section 6-1.05 is amended to read:

Whenever the specifications permit the substitution of a similar or equivalent material or article, no test or action relating to the approval of such substituted material will be made until the request for substitution is made in writing by the Contractor accompanied by complete data as to the equality of the material or article proposed. Such request shall be made within 35 days after the date the contract has been approved and in ample time to permit approval without delaying the work, but need not be made in less than 35 days after award of the contract.

Work requiring the submittal of working drawings, material lists, descriptive data, samples, or other submittals shall not begin prior to approval of said submittal by the Engineer. Twenty working days shall be allowed for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete his review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications.

Submittals shall be delivered to the locations indicated in these special provisions. If a specific location is not indicated, the submittal shall be delivered to the Division of Structure Design, Documents Unit, Fourth Floor, Mail Station 9-4/4I, 1801 30th Street, Sacramento, California 95816, telephone (916) 227-8252, or the submittals shall be mailed to the Division of Structure Design, Documents Unit, Mail Station 9-4/4I, P. O. Box 942874, Sacramento, California 94274-0001.

Each submission of drawings, material lists and descriptive data shall consist of at least 5 copies. Two copies will be returned to the Contractor either approved for use or returned for correction and resubmittal.

Each separate item submitted shall bear a descriptive title, the name of the project, district, county, and contract number. Plans and detailed drawings shall be not larger than 22" x 36".

The material list shall be complete as to name of manufacturer, catalog number, size, capacity, finish, all pertinent ratings, and identification symbols used on the plans and in the special provisions for each unit.

Parts lists and service instructions packaged with or accompanying the equipment installed in the work shall be delivered to the Engineer at the jobsite. Required operating and maintenance instructions shall be submitted in triplicate.

Manufacturer's warranties for products installed in the work shall be delivered to the Engineer at the jobsite.

Unapproved samples and samples not incorporated in the work shall be removed from State property, when directed by the Engineer.

12-1.07 PROGRESS SCHEDULE

A progress schedule shall be submitted in duplicate for the building work in accordance with the requirements in Section 8-1.04, "Progress Schedule," of the Standard Specifications.

12-1.08 SCHEDULE OF VALUES

The Contractor shall prepare and submit to the Engineer for approval 2 copies of a Schedule of Values within 15 working days of approval of the contract covering each lump sum item for building work. Fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete his review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications.

The Schedule of Values must be accurately divided into sections representing the cost of each separate building or structure. All work that is not part of a separate building or structure, such as excavation, grading, curbs, gutters, sidewalks, paving, sewer and storm drainage and utility distribution lines are to be included under a specific section as General Work and not included in the building or structure cost. Indirect costs and general condition items are to be listed as a separate line item of work. The sections representing each building or structure must be identified as to the building or structure they represent and be broken down to show the corresponding value of each craft, trade or other significant portion of the work. A sub-total for each section shall be provided.

The Schedule of Values shall be approved by the Engineer before any partial payment estimate is prepared.

The sum of the items listed in the Schedule of Values shall equal the contract lump sum price for building work. Overhead, profit and bond premium are to be proportionally distributed across all line items of cost.

12-1.09 INSPECTION

All items covered or all stages of work that are not to remain observable must be inspected and approved before progress of work conceals portions to be inspected. The Contractor shall notify the Engineer not less than 72 hours in advance of when such inspection is needed.

12-1.10 OBSTRUCTIONS

Attention is directed to Sections 7-1.11, "Preservation of Property," 7-1.12, "Responsibility for Damage," 7-1.16, "Contractor's Responsibility for the Work and Materials," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 5 working days prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include but are not limited to the following:

Underground Service Alert
Northern California (USA)
Telephone: 1(800)642-2444

Underground Service Alert
Southern California (USA)
Telephone: 1(800)422-4133

South Shore Utility
Coordinating Council (DIGS)
Telephone: 1(800)541-3447

Western Utilities
Underground Alert, Inc.
Telephone: 1(800)424-3447

12-1.11 PRESERVATION OF PROPERTY

Attention is directed to Sections 7-1.11, "Preservation of Property," 7-1.12, "Responsibility for Damage," 7-1.16, "Contractor's Responsibility for the Work and Materials," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

Operations shall be conducted in such a manner that existing facilities, surfacing, installations, and utilities which are to remain in place will not be damaged. Temporary surfacing, facilities, utilities and installations shall also be protected until they are no longer required. The Contractor, at his expense shall furnish and install piling, sheet piling, cribbing, bulkheads, shores, or whatever means may be necessary to adequately support material carrying such facilities, or to support the facilities themselves and shall maintain such support until they are no longer needed.

12-1.12 UTILITY CONNECTION

The Contractor shall make all arrangements, and obtain all permits and licenses required for the extension of and connection to each utility service applicable to this project, shall furnish all labor and materials necessary for such extensions which are not performed or provided by the utility, and shall furnish and install any intermediate equipment required by the serving utilities.

Upon written request by the Contractor, the State will pay all utility permits, licenses, connection charges, and excess length charges directly to the utility. Such request shall be submitted not less than 45 days before service connections are required.

The costs incurred by the Contractor for the extensions of utilities beyond the limits shown on the plans, and in furnishing and installing any intermediate equipment required by the serving utilities, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Full compensation for any costs incurred by the Contractor to obtain the permits and licenses shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

12-1.13 TEMPORARY UTILITIES

The Contractor may obtain electrical power and water from existing State electrical power and water outlets within the contract limits free of charge for contract operations where such utilities exist, provided that such utility services are in service and are not required by the State for other purposes and subject to the provisions in the section "Cooperation" of these special provisions.

The Contractor shall make his own arrangements to obtain any additional electrical power and water or other utilities required for his operations and shall make and maintain the necessary service connections at his own expense.

When existing utility systems are being modified, periods of shutdown will be determined by the Engineer.

The Contractor shall provide adequate temporary lighting to perform the work and allow the Engineer to inspect the project as each portion is completed.

The Contractor shall provide and pay for telephone service he may require. State telephone facilities shall not be used.

12-1.14 SANITARY FACILITIES

When operational, State sanitary facilities will be available for use by the Contractor's employees, during normal State working hours. Tools shall not be cleaned nor shall cleaning liquids be disposed of in State sanitary facilities or sewers.

During toilet room renovation or other periods when State-owned sanitary facilities are not operational, the Contractor shall provide and pay for wash facilities, drinking water fixtures and a minimum of two temporary toilet units for State forces. Separate toilet facilities shall be provided for Contractor's personnel. Facilities shall include the periodic flushing, waste removal and cleaning of such facilities. Units shall be maintained in a clean and sanitary condition, including a supply of toilet tissue, toilet seat covers, paper towels and paper cups. Waste material shall be disposed of off site in a lawful manner. Temporary toilet units shall be single occupant units of the chemical, aerated recirculation type, properly vented and fully enclosed with a glass fiber reinforced polyester shell or similar nonabsorbent material.

12-1.15 MEASUREMENT AND PAYMENT

The contract lump sum price paid for building work shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the building work, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for any incidental materials and labor, not shown on the plans or specified, which are necessary to complete the buildings and appurtenances shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

12-1.16 PROJECT RECORD DRAWINGS

The Contractor shall prepare and maintain one set of project record drawings, using an unaltered set of original project plans, to clearly show all as-constructed information for the project. As a minimum, the information to be shown shall include 1) any plan clarifications or change orders, 2) locations of any underground utilities, or 3) the location, size, type, and manufacturer of all major products or components selected by the Contractor for use in the work.

All markings shall be placed on the project record drawings using red ink or red pencil. Original figures shall not be eradicated nor written over and superseded material shall be neatly lined out. Additional drawings shall be submitted if the required information cannot be clearly shown on the original set of project plans. The additional drawings shall be not less than 11" x 17" in size and shall have the contract number on each sheet. The Contractor shall sign and date each sheet of the project record drawings to verify that all as-constructed information shown on the drawings is correct.

The Contractor shall periodically review the set of project record drawings with the Engineer during the progress of the work to assure that all changes and other required information are being recorded.

Before completion of the work, the Contractor shall request a review of the project record drawings to determine the completeness and adequacy of them. If the project record drawings are unacceptable, the Contractor shall inspect, measure, and survey the project as necessary to record the required additional information.

The set of completed project record drawings shall be delivered to the Engineer prior to acceptance of the contract.

12-1.17 FIELD ENGINEERING

This section specifies administrative and procedural requirements for field engineering services to be performed by the Contractor.

Lines and Grades:

Attention is directed to Section 5-1.07 "Lines and Grades," of the Standard Specifications.

Such stakes or marks will be set by the Engineer as he determines to be necessary to establish the lines and grades required for the completion of the work shown on the plans and as specified in these special provisions. In general, these will consist of the primary vertical and horizontal control points.

Stakes and marks set by the Engineer shall be carefully preserved by the Contractor. In case such stakes and marks are destroyed or damaged they will be replaced at the Engineer's earliest convenience. The Contractor will be charged for the cost of necessary replacement or restoration of such stakes and marks which in the judgment of the Engineer were carelessly or willfully destroyed or damaged by the Contractor's operations. This charge will be deducted from any moneys due or to become due the Contractor.

All other stakes or marks required to establish the lines and grades required for the completion of the work shall be the responsibility of the Contractor.

Existing utilities and equipment:

The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, the Contractor shall investigate and verify the existence and location of underground utilities and other construction.

Prior to construction, the Contractor shall verify the location and invert elevation at points of connection of sanitary and septic sewers, storm sewer, and water or fire service piping.

Surveys for layout and performance:

The Contractor shall perform all surveys for layout and performance, reduce field notes, and make all necessary calculations and drawings necessary to carry out the work.

The Contractor shall locate and layout site improvements, and other work requiring field engineering services, including pavements, stakes for grading, fill and topsoil placement, utility slopes and invert elevations by instrumentation and similar appropriate means.

Batter boards shall be located and laid out for structures, building foundations, column grids and locations, floor levels and, control lines and levels required for mechanical and electrical work.

Survey accuracy and tolerances:

The tolerances generally applicable in setting survey stakes for foundations, slabs, and underground work shall not exceed the following:

Survey Stakes or Markers	Tolerance
Rough grading or excavation	0.10-foot
Trimming or preparation of subgrade for roadways	0.05-foot
Roadway surfacing, steel or concrete pipe	0.02-foot
Structures or building construction	0.01-foot

Such tolerance shall not supersede stricter tolerances required by the plans or special provisions, and shall not otherwise relieve the Contractor of responsibility for measurements in compliance therein.

12-1.18 ASBESTOS

The Contractor shall take special precautions for that portion of the work which may involve the handling of materials which contain asbestos, either in demolition or construction.

Work known to contain asbestos or asbestos-related materials consists of the following:

1. Interior ceramic tile mortar / grout (white)
2. Exterior rock façade mortar (brown)
3. Roof mastic (black/grey)

Attention is directed to "Removal and Disposal of Asbestos" in Section 12-2, "Sitework," of these special provisions regarding governing codes and requirements for the removal and disposal of materials containing asbestos.

Materials containing asbestos, which are designated on the plans or specified in these special provisions to be removed and disposed of, shall be disposed of away from the premises. The Contractor shall make his own arrangements for disposing of such materials, and shall pay all the costs involved. Said arrangements shall include, but not necessarily be limited to entering into agreements with said disposal site property owners and obtaining all required permits, licenses and environmental clearances. Prior to disposing of any material away from the premises, the Contractor shall furnish to the Engineer satisfactory evidence that the Contractor has entered into agreements with the property owners of the disposal site involved and has obtained said permits, licenses and clearances.

12-1.19 LEAD BASED MATERIALS

The Contractor shall take special precautions for that part of the work which involve the handling of materials which may contain lead, either during demolition or construction.

The lead content of the existing wall tile (yellow) is unknown.

Any work that disturbs the existing tile system may expose workers to health hazards and may (1) produce amounts of material and residue containing heavy metal which exceed the hazardous thresholds established in the California Code of Regulations or (2) produce toxic fumes when heated.

The Contractor shall furnish sampling and testing programs for lead or lead based materials. The program shall be prepared and carried out by an industrial hygienist certified by the American Council of Industrial Hygiene. The number and location of samples shall be as designated by the Engineer.

REPORTING

The sampling report shall be given to the Engineer within 10 days of the sampling.

If the paint system is found to contain safe levels, the Contractor may proceed with work in that area.

If the paint system is found to contain unsafe levels of lead, and when ordered by the Engineer in writing, the Contractor shall proceed with the removal and disposal of the debris.

Attention is directed to “Lead Abatement,” in Section 12-2 of these special provisions regarding governing codes and requirements for the removal and disposal of lead based materials.

The sampling and testing program work done by the certified industrial hygienist, including furnishing the sampling program, sample collection, analysis and reporting, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Any adjustment of contract time will be made in accordance with the provisions of Section 8-1.06, “Time of Completion,” of the Standard Specifications.

Materials containing lead, which are designated on the plans or specified in these special provisions to be removed and disposed of, shall be disposed of away from the premises. The Contractor shall make his own arrangements for disposing of such materials, and shall pay all the costs involved. Said arrangements shall include, but not necessarily be limited to, entering into agreements with said disposal site property owners and obtaining all required permits, licenses and environmental clearances. Prior to disposing of any material away from the premises, the Contractor shall furnish to the Engineer satisfactory evidence that the Contractor has entered into agreements with the property owners of the disposal site involved and has obtained said permits, licenses and clearances.

SECTION 12-2. SITEWORK

12-2.01 REMOVING EXISTING FACILITIES

PART 1 - GENERAL

Scope: This work shall consist of removing and disposing of the existing facilities, including existing buildings and appurtenant structures, ramps, picnic shelters and utilities, including pads and foundations and removal of existing work to gain access to or for new work, in accordance with the details shown on the plans and these special provisions.

General.—The Contractor shall not begin demolition until authorization is received from the Engineer. The work includes demolition, removal of resulting rubbish and debris. Rubbish and debris shall be removed from State property daily, unless otherwise directed, to avoid accumulation at the demolition site. Materials that cannot be removed daily shall be stored in areas specified by the Engineer. The work shall be performed in accordance with applicable sections of State safety ordinances for demolition work.

Related Work.—The Contractor shall conduct demolition procedures with the requirements of “Removal and Disposal of Asbestos”, and “Lead Abatement” elsewhere in these special provisions.

Demolition Plan.—The Contractor shall submit the procedures proposed for the accomplishment of the work. The procedures shall provide for safe conduct of the work, including procedures and methods to provide necessary supports, lateral bracing and shoring when required, careful removal, protection of property which is to remain undisturbed, coordination with other work in progress, and timely disconnection of utility services. The procedures shall include a detailed description of the methods and equipment to be used for each operation, and the sequence of operations. The Contractor shall submit proposed demolition and removal procedures to the Engineer 10 days before work is started for review and approval.

Regulatory and Safety Requirements.—The Contractor shall comply with federal, state, and local hauling and disposal regulations. In addition to the requirements of the “Contract Clauses,” safety requirements shall conform with ANSI A10.6.

Notifications.—The Contractor shall furnish timely notification of demolition to state and regional authorities as required and to the Engineer in writing 10 working days prior to the commencement of work.

PART 2 - PRODUCTS (Not applicable)

PART 3 - EXECUTION

PREPARATION

Dust and Debris Control.—The spread of dust and debris shall be prevented on roadway pavements and the creation of a nuisance or hazard in the surrounding area shall be avoided. The use of water shall not be allowed if it results in hazardous or objectionable conditions such as, but not limited to, ice flooding, or pollution. The area shall be vacuumed and dusted frequently. Pavements shall be swept as often as necessary to control the spread of debris that may result in foreign object damage potential to vehicles.

Existing Work.—Before beginning any demolition work, the Contractor shall survey the site and examine the plans and specifications to determine the extent of the work. Necessary precautions shall be taken to avoid damage to existing items to remain in place. Any damaged items shall be repaired or replaced as approved by the Engineer. The Contractor shall coordinate demolition with all other work and shall construct and maintain shoring, bracing, and supports as required. The Contractor shall ensure that structural elements are not overloaded and shall be responsible for increasing structural supports or adding new supports as may be required as a result of any cutting, removal, or demolition work performed.

Utilities.—Electrical and mechanical services and utilities shall be protected. Where removal of existing utilities and pavement is specified or indicated, approved barricades, temporary covering of exposed areas, and temporary services or connections for electrical and mechanical utilities shall be provided.

Use of Explosives.—Use of explosives will not be permitted.

The limits of removal shall be located and identified. Items to be removed and the interface of items to be removed and items to remain intact shall be identified and marked.

Prior to removing concrete or masonry, a saw cut approximately one inch deep shall be made along the limits of removal on all faces that will be visible in the completed work.

REMOVAL

Removal shall be to the limits shown on the plans. Removal shall be done carefully to minimize damage to the portions to remain. Remaining portions that are damaged by the Contractor's operation shall be restored to original condition at the Contractor's expense.

Existing apparatuses, devices, or accessories which would be functionally impaired by new construction or remodeling shall be moved, brought out to new surfaces, or provided with new access covers, as necessary to restore apparatuses, devices, or accessories to their original usefulness.

Structures.—Existing structures indicated shall be removed to four feet below grade as shown on the plans including underground foundations.

Utilities and Related Equipment.—The existing utilities as indicated shall be removed and terminated in a manner conforming to the nationally recognized code covering the specific utility and approved by the Engineer. When utility lines are encountered that are not indicated on the drawings, the Engineer shall be notified prior to further work in that area. Meters and related equipment shall be removed and delivered to a location in accordance with instructions of the Engineer. If utility lines are encountered that are not shown on drawings, the Engineer shall be contacted for further instructions.

Piping and conduits to be abandoned shall be capped or plugged.

Surfaces that are exposed to view at the limits of removal work shall be patched, bumps shall be removed and depressions filled, and the surface shall be finished to match the existing surroundings. Depressions in concrete less than one inch deep shall be deepened to one inch minimum depth before filling with cement mortar.

Anchor bolts and reinforcement shall be removed.

DISPOSAL

Materials that are to be removed, shall become the property of the Contractor and shall be disposed of away from the premises. Such disposal shall conform to the laws, rules, and regulations of all agencies having jurisdiction at the disposal site.

12-2.02 ABANDON PORTIONS OF WASTE DISPOSAL SYSTEM

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of removing portions and abandoning portions of the existing waste disposal system in accordance with the details shown on the plans and these special provisions.

Codes and Standards: Attention is directed to Section 7-1.01, "Laws to be Observed," of the Standard Specifications.

PART 2 - PRODUCTS (Not applicable)

PART 3 - EXECUTION

Staging of Work: Work that will curtail the use of the waste disposal system shall not be done until the facilities utilizing the system are closed. -

Disposal: Sewage facilities to be abandoned shall be pumped out and the sewage and sediment removed from such facilities shall be disposed of away from the premises. Disposal shall conform to the laws, rules and regulations of the agency having jurisdiction of the disposal site.

Abandoning Facilities:

Each pipe entering or exiting the sewage disposal system to be abandoned shall be closed by a tight fitting plug or wall of concrete not less than 0.5 foot thick. Such concrete shall be commercial quality concrete and shall contain not less than 470 pounds of cement per cubic yard of concrete.

Manhole Frames and Covers: Manhole frames and covers which are to be removed shall become the property of the Contractor and disposed of away from the premises. Such disposal shall conform to the laws, rules, and regulations of all agencies having jurisdiction at the disposal site.

12-2.03 REMOVAL AND DISPOSAL OF ASBESTOS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of removing and disposing of hazardous or asbestos-related materials which are designated on the plans or specified in these special provisions to be removed and disposed of.

Where existing hazardous or asbestos-related materials are to be removed during demolition, construction or alterations, such material shall be treated as hazardous waste, and shall be removed, hauled and disposed of in accordance with all applicable Federal, State and local laws and ordinances.

Codes and standards: Codes which govern removal and disposal of materials containing asbestos include, but are not necessarily limited to the following:

1. California Health and Safety Code, Division 20, Chapter 6.5, Hazardous Waste Control.
2. California Code of Regulations, Title 22, Division 4, Chapter 30, "Minimum Standards for Management of Hazardous and Extremely Hazardous Material," latest revisions, as applicable.
3. California Code of Regulations, Title 8, General Industry Safety Order 5208 Asbestos.
4. Occupational Safety and Health Administration, Part 26 (amended), of Title 29 of the Code of Federal Regulations.

PART 2 - PRODUCTS (Not applicable)

PART 3 - EXECUTION

REMOVAL

Preparation:

Prior to performing operations involving the removal of hazardous waste containing asbestos, the Contractor shall provide written notification to the following agencies:

State Department of Toxic Substances Control
400 P Street
Sacramento, CA 95814
Telephone No. (916) 322-0476

Division of Occupational Safety and Health
2424 Arden Way, Suite 165
Sacramento, CA 95825
Telephone No. (916) 263-2800

The Contractor shall notify Division of Occupational Safety and Health (CAL OSHA) 24 hours prior to performing removal operations of materials containing asbestos.

The Contractor shall notify the Engineer 3 working days in advance of commencement of removal operations of material containing asbestos.

Handling:

The Contractor shall comply with all Federal, State, and local regulations for the removal of material containing asbestos prior to demolition, shall place such removed material in approved plastic containers (double ply, 6-mil minimum thickness, plastic bags) with caution labels affixed to said bags. Such caution labels shall have conspicuous, legible lettering which spells out the following, or equivalent warning:

CAUTION
CONTAINS ASBESTOS FIBERS
BREATHING ASBESTOS DUST MAY
CAUSE SERIOUS BODILY HARM

At the option of the Contractor, the removed materials containing asbestos may be placed directly into a roll off or drop box which shall have the same caution label affixed on all sides.

The Contractor shall comply with all Federal, State and local requirements for safety which shall include providing employees with coveralls (preferably disposable plastic coated), rubber gloves (to be discarded after use), rubber boots (to be washed thoroughly after use), and disposable dust respirators (to cover nose and mouth). The use of goggles shall be optional.

The Contractor shall be responsible for verifying that all employees, who are involved in asbestos removal operations, wear the protective devices enumerated herein during removal operations.

Transporting: All haulers of hazardous waste material shall be currently registered with the State Department of Health Services (DOHS), and shall have a U.S. Environmental Protection Agency Identification Number (U.S. EPA I.D. Number). All vehicles used to transport hazardous waste material shall have affixed to the vehicle a valid Certificate of Compliance issued by DOHS. If a roll off or drop box is utilized, both the drop box and the transporting vehicle must have a valid Certificate of Compliance issued by DOHS.

Disposal:

The Engineer will obtain the required EPA generator identification numbers, and will sign the hazardous waste manifests.

The Contractor shall dispose of all hazardous waste containing asbestos at a Class I, Class II-1, Class II-2, or Class 3 disposal site (old designation), or at a Class I, Class II, or Class 3 disposal site (new designation), which had previously agreed to accept the hazardous waste.

The Contractor shall notify the proper authorities at the disposal site in advance of delivery of hazardous waste containing asbestos to the disposal site.

12-2.04 LEAD ABATEMENT

PART 1 - GENERAL

SUMMARY

Scope: The work shall consist of procedures for removal, and disposal of lead based materials which are specified in these special provisions to be removed and disposed of.

Where existing lead based materials are to be removed during demolition, , such material shall be treated as hazardous waste, and shall be removed, hauled and disposed of in accordance with all applicable Federal, State and local laws and ordinances.

SUBMITTALS

Health and Safety: A Code of Safe Practices, an Injury and Illness Prevention Program, and a Hazard Communication Program in accordance with the provisions of Construction Safety Orders 1509 and 1510 shall be submitted for approval.

QUALITY ASSURANCE

Codes and Standards: Codes which govern removal and disposal of materials containing lead include, but are not limited to the following:

1. California Health and Safety Code, Division 20, Chapter 6.5, "Hazardous Waste Control Act."
2. California Code of Regulations, Title 22, Division 4, Chapter 30, "Minimum Standards for Management of Hazardous and Extremely Hazardous Material."
3. California Code of Regulations, Title 8, General Industry Safety Order, Section 1532.1, Lead.
4. Occupational Safety and Health Administration, Part 26 (amended), of Title 29 of the Code of Federal Regulations.

Compliance Program:

The Contractor shall submit the compliance programs required in subsection (e)(2), "Compliance Program," of said Section 1532.1, "Lead," to the Engineer for approval before starting removal work on the project and at such times when revisions to the program are ordered by the Engineer. The compliance programs shall be prepared by an industrial hygienist certified by the American Council of Industrial Hygiene. The Engineer will notify the Contractor of the approval or rejection of any submitted or revised compliance program in not more than 10 working days.

If measures being taken by the Contractor are inadequate to provide for worker safety and the containment and collection of residue from existing paint systems, the Engineer will direct the Contractor to revise his operations and the compliance program. Such directions will be in writing and will specify the items of work for which the Contractor's compliance programs are inadequate. No further work shall be performed on said items until the compliance programs are adequate and, if required, a revised compliance program has been approved.

The State will not be liable to the Contractor for failure to approve all or any portion of an originally submitted or revised compliance program for worker safety and the containment and collection of residue from existing paint systems, nor for any delays to the work due to the Contractor's failure to submit an acceptable compliance program.

Field Sampling:

The Contractor shall furnish sampling and testing programs for air as applicable. The programs shall be prepared and carried out by an industrial hygienist certified by the American Council of Industrial Hygiene. The number and location of the samples shall be designated by the Engineer.

Air samples, if required, shall be collected during removal operations to measure concentrations of heavy metals and total particulate matter in the ambient air as PM-10 (particulate matter with an aerodynamic diameter less than or equal to 10 micrometers). Air samples shall be collected and analyzed in accordance with the Code of Federal Regulations 40 CFR PART 50, Appendix J, except as follows:

1. Air samples shall be Reference or Equivalent Method PM-10 Samplers as designated by the U. S. Environmental Agency and in accordance with requirements of 40 CFR PART 53.
2. Sampling time each day shall coincide with the time of removal operations but the duration of sampling shall be not less than 8 hours.
3. Immediately following analysis for PM-10, all samples will be analyzed for heavy metal content in accordance with 40 CFR PART 50, Appendix G.

For air sample analysis results, the date and sample location of sample collection, sample number, contract number, and facility name as shown on the contract plans will be required.

For air sample analysis results, the following will be required:

1. Start time, end time and duration of sample collection.
2. Start time and end times of cleaning on the day of sample collection.
3. Concentrations of PM-10 expressed as micrograms PM-10 per standard cubic meter of air.
4. Concentrations of heavy metals expressed as micrograms per standard cubic meter of air.

PART 2 - PRODUCTS (Not applicable.)

PART 3 - EXECUTION

REMOVAL

Notification: The Contractor shall notify the Engineer 3 working days in advance of commencement of removal operations of material containing lead or lead based materials.

Method of Removal:

Painted materials shall be removed using the wet process removal equipment and methods, to a depth required to remove all paint and provide clean substrate suitable for a new finish.

Removed material and water used for removal shall be collected. Removed material shall be separated from water using approved filters.

Handling:

The Contractor shall comply with all Federal, State, and local regulations for the removal of material containing lead prior to demolition, shall place such removed material in approved plastic containers (double ply, 6-mil minimum thickness, plastic bags) with caution labels affixed to said bags. Such caution labels shall have conspicuous, legible lettering which spells out the following, or equivalent warning:

**CAUTION
CONTAINS LEAD**

Temporary storage on the ground of material and residue produced when the existing paint system is disturbed will not be permitted. Material and residue shall be stored in leak proof containers and shall be handled in such a manner that no spillage will occur.

At the option of the Contractor, the removed lead based materials may be placed directly into a roll off or drop box which shall have the same caution label affixed on all sides.

Safety Measures:

The Contractor shall comply with all Federal, State and local requirements for safety which shall include providing employees with coveralls (preferably disposable plastic coated), rubber gloves (to be discarded after use), rubber boots (to be washed thoroughly after use), and respirators.

The Contractor shall be responsible for verifying that all employees, who are involved in removal operations, wear the required protective devices during removal operations.

DISPOSAL

Transporting: All haulers of hazardous waste material shall be currently registered with the State Department of Health Services (DOHS), and shall have a U.S. Environmental Protection Agency Identification Number (U.S. EPA I.D. Number). All vehicles used to transport hazardous waste material shall have affixed to the vehicle a valid Certificate of Compliance issued by DOHS. If a roll off or drop box is utilized, both the drop box and the transporting vehicle must have a valid Certificate of Compliance issued by DOHS.

Disposal:

The Engineer will obtain the required EPA generator identification numbers, and will sign the hazardous waste manifests.

All material and residue produced during removal operations shall be tested and disposed of by the Contractor in California at an approved Class 1 disposal facility in accordance with the requirements of the disposal facility operator.

The Contractor shall notify the proper authorities at the disposal site in advance of delivery of hazardous waste containing lead to the disposal site.

12-2.05 ROUGH GRADING

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of rough grading the site in accordance with the details shown on the plans and these special provisions.

Rough grading shall consist of excavation or removal of above grade material regardless of character and subsurface condition; filling of all holes, swales, embankments, and low points to the elevation shown on the plans or specified; and the preparation of basement material for the placing of other material thereon and the establishment of the grading plane.

Earthwork for building construction shall conform to the requirements specified under "Earthwork for Building Work" in this Section 12-2 of these special provisions.

Grading Material Deficiency: The grading shown on the plans will require approximately 2542 cubic yards of fill material to be supplied by the Contractor.

PART 2 - PRODUCTS

Fill Material:

Material from the excavation that is suitable for the required compaction may be used for filling holes, swales and low points. Fill material shall be free of organic material. Rocks and lumps shall be well distributed with sufficient earth or other fine matrix material to produce a dense, compacted fill that is suitable for the construction and load support intended.

The Contractor shall furnish suitable borrow material to offset any material deficiencies developed from grading work.

PART 3 - EXECUTION

EXCAVATION

Care shall be exercised to avoid disturbing material below and beyond the limits of excavation. When excavation is carried beyond the limits shown on the plans or specified, such excavation shall be replaced in kind and compacted at the Contractor's expense.

Limits of the excavation shall allow for adequate working space for installing materials and as required for safety of personnel. Such working space excavation shall be replaced in kind and compacted at the Contractor's expense.

Excess and waste materials from the excavation shall become the property of the Contractor and be disposed of outside the highway right of way in accordance with the requirements in Section 7-1.13 of the Standard Specifications.

FILL

Subgrade Preparation: Preparation of subgrade material for placing other material thereon shall include fine grading, compaction, reworking as necessary, and preparation of cut, or fill upon which base materials, surfacing, or slabs are to be placed. The upper 8 inches of the subgrade shall have the same compaction as the fill to be placed over it.

Placing: When footings are to be constructed in fill, the fill shall be constructed to the grading plane required for the building construction prior to excavating for the footings. Fill shall be placed and compacted in layers. The loose thickness of each layer before compaction shall not exceed 6 inches.

Water shall be added to the fill material as needed for compaction.

COMPACTION

Relative compaction shall be determined in accordance with California Test 216 or 231. 22

Relative Compaction (95 percent):

In fill relative compaction of not less than 95 percent shall be obtained for a minimum depth of 2.5 feet below finished grade for the width of the paved areas plus 3 feet on each side thereof.

The prism of fill directly underneath the building foundation and sloping downward at 1:1 shall be compacted to 95 percent.

Relative Compaction (90 percent): Relative compaction of not less than 90 percent shall be obtained in all fill except as specified above.

FIELD QUALITY CONTROL

Testing and Inspection: The State will conduct compaction tests during the earthwork operations.

12-2.06 EARTHWORK FOR BUILDING WORK

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of performing earthwork for building work in accordance with the details shown on the plans and these special provisions.

Earthwork for building work shall consist of structure excavation and structure backfill. Structure excavation shall include excavation for all footings, foundations, walls, slabs, tanks, manholes, and trenches. Structure backfill shall include backfilling under slabs; backfilling under and around all footings; backfilling for walls, backfilling for pipes and conduits; backfilling holes resulting from removal of existing facilities. In addition to structure excavation and structure backfill, earthwork for building work shall include any other earthwork, not mentioned, but necessary to complete the building work.

Attention is directed to the Materials Information Handout for information regarding foundation recommendations and reports that were prepared for use during the design of this project.

Attention is directed to the requirements of "Field Engineering" in Section 12-1, "General Requirements," of these special provisions.

QUALITY ASSURANCE

Samples: Samples of sand, gravel, weighing not less than 25 pounds, shall be submitted to the Engineer at the jobsite for approval.

SITE CONDITIONS

Existing Underground Piping and Conduit: The location of existing underground piping and conduit is based on the best records available. Before beginning work, the Contractor shall accurately locate the piping and conduit involved in the work. If the location of the existing piping or conduit deviates from the location shown on the plans by more than 5 feet, or, if no elevations are indicated and the piping or conduit is more than 3 feet below grade, the cost of the additional excavation, backfill, piping or conduit, and removal and replacement of concrete, if any, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Existing Surfaced or Planted Areas:

Existing surfaced or planted areas that are removed, broken or damaged by the Contractor's operations shall be restored to their original condition except as otherwise shown on the plans or specified herein.

Restoration materials shall be equal to or better than the original materials. Surfacing shall be replaced to match the material thickness, grades, and finish of the adjacent surrounding surfaces.

PART 2 - PRODUCTS

BACKFILL MATERIALS

Structure Backfill: Structure and trench backfill shall be free of organic and other deleterious material and shall be suitable for the required compaction. Gravel without sand matrix shall not be used except as free draining granular material beneath slabs and footings.

Sand: Sand shall be clean, washed sand, free from clay or organic material graded such that 100 percent passes the 1/4-inch sieve, 90 percent to 100 percent passes the No. 4 sieve and not more than 5 percent passes the No. 200 sieve size.

Pea Gravel (Naturally Rounded):

Pea gravel (naturally rounded) shall be clean, washed, dry density of not less than 95 pounds per cubic foot, free from clay or organic material and shall conform to the following grading as determined by California Test 202:

Sieve or Screen Size	Percentage Passing
3/4"	100
1/2"	90-100
3/8"	40-70
No. 4	0-15
No. 8	0-3

Pea gravel shall conform to the following requirements:

Test	California Test No.	Test Requirements
Durability Index	229	35 Min.

Crushed Stone:

Crushed stone shall be clean, washed, dry density of not less than 95 pounds per cubic foot, crushed stone or crushed gravel with an angular particle size not less than 1/8 inch or more than 1/2 inch.

Sieve or Screen Size	Percentage Passing
1/2"	100
3/8"	85-100
No. 4	10-30
No. 8	0-3

Crushed stone shall conform to the following requirements:

Test	California Test No.	Test Requirements
Durability Index	229	35 Min.

PART 3 - EXECUTION

PREPARATION AND RESTORATION

Sawcutting: Prior to excavation or trenching, existing finished surfacing shall be removed to saw cut lines, or to existing wood dividers or expansion joints, if any. The saw cut shall be to a neat line and have a depth not less than one inch.

Restoration: Finished surfacing shall be replaced or restored to match the thickness, grades and finish of the adjacent surrounding surfaces.

STRUCTURE EXCAVATION

Unless otherwise noted, all excavation for building work shall be classified as structure excavation.

Footing Excavation:

The bottom of excavation shall not be disturbed. The contractor shall excavate by hand to the final grade. The bottom of concrete footings shall be poured against undisturbed material. Unless otherwise noted, compaction of the bottom of footing excavation is not required unless the material is disturbed. The footing depths shown on the plans shall be changed to suit field conditions when directed by the Engineer. Solid rock at or near required depths shall not be disturbed. Unsuitable material shall be excavated down to firm bearing as directed by the Engineer. Work and materials required because of excavation in excess of the depths shown on the plans, when such excavation has been ordered by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Excavate to the elevations and dimensions within a tolerance of $\pm 1/2$ inch. Limits of the excavation shall allow for adequate working space for installing materials and as required for safety of personnel. Such working space excavation shall be replaced in kind and compacted at the Contractor's expense.

Overdepth excavation for footings shall be backfilled with concrete or such other material recommended by the Contractor and approved by the Engineer. Relative compaction shall be not less than 95 percent.

Excavation for Pipes and Conduits:

Pipes or conduits in the same trench shall have a minimum clear distance between pipes or conduits of 6 inches. Pipes or conduits shall have not less than 2½ feet of cover from top of pipes or conduits to finished grade unless otherwise shown on the plans or specified.

Trenching shall be of sufficient depth to permit placing a minimum depth of 4 inches of compacted sand under all pipes and conduits.

Excavation adjacent to trees shall be performed by hand methods where necessary to avoid injury to trees and roots. Roots 2 inches in diameter and larger shall be protected with heavy burlap. Roots smaller than 2 inches in diameter adjacent to trees shall be hand trimmed. Cuts through roots 1/2 inch in diameter and larger shall be sealed with tree trimmers' asphaltic emulsion. If trenches remain open more than 24 hours, the side of the trench adjacent to the tree shall be shaded with burlap and kept damp. Materials shall not be stockpiled within the drip line of trees.

Dewatering: Excavations shall be kept clear of standing water. Water shall be removed by pumping if necessary. Water removed from excavation shall be carried away from the building site and disposed of in a manner that will not harm State or adjacent property.

STRUCTURE BACKFILLING

Unless otherwise noted, all backfill for building work shall be classified as structure backfill. Backfill shall be placed and compacted in horizontal layers, not more than 6 inches thick prior to compaction, and to the lines and grades shown on the plans or to original ground.

Structure Backfill: After structures are in place and forms are removed, wood and other debris shall be removed from excavations before placing structure backfill.

Backfilling Pipes and Conduits:

Backfill placed under pipe and conduits shall be compacted sand, 4 inches minimum depth. Backfill material placed to a level 6 inches above tops of pipes and conduits shall be sand or fine earth and particles shall not exceed 1/2 inch in greatest dimension. For wrapped, coated, or plastic pipe or conduits, sand shall be used for backfill. Backfill material placed higher than 6 inches above tops of pipes or conduits shall consist of material free of stones or lumps exceeding 4 inches in greatest dimension except:

1. The top 12 inches of backfill under roads, walks or paving shall consist of aggregate base material.
2. The top 6 inches of backfill in planted areas shall consist of topsoil.

Unless otherwise shown on the plans, pipe under roads, with less than 2½ feet of cover over the top of pipe, shall be backfilled with concrete to a level 4 inches above the top of pipe. Concrete for backfill shall be commercial quality concrete containing not less than 564 pounds of cement per cubic yard.

COMPACTION

Relative compaction shall be determined in accordance with California Test 216 or 231.

Unless otherwise noted below, all backfill shall be compacted to a minimum relative compaction of 90 percent.

Unless approved in writing by the Engineer, compaction by jetting or ponding will not be permitted.

Compact Original Ground: Original ground surface under fill with surfacing of concrete and asphalt concrete shall be compacted to a relative compaction of not less than 95 percent for a minimum depth of 6 inches.

Subgrade Preparation:

Preparation of subgrade material for placing aggregate base, surfacing, or slabs thereon shall include fine grading, compaction, reworking as necessary. The upper 6 inches of the subgrade shall have the same compaction as the fill to be placed over it.

The prism of backfill directly underneath the building foundation and sloping downward at 1:1 shall be compacted to 95 percent.

Structure Backfill: Structure backfill shall be compacted to not less than 95 percent relative compaction.

A relative compaction of not less than 95 percent shall be obtained for a minimum depth of 6 inches below the bottom of the excavation before placing select backfill.

Trench Backfill: Trench backfill placed beneath slabs or paved areas shall be compacted to a relative compaction of not less than 95 percent.

DISPOSAL

Surplus Material: Surplus material from the excavation shall be removed and disposed of outside the right-of-way in accordance with Section 7-1.13 of the Standard Specifications.

FIELD QUALITY CONTROL

Inspection: When the excavation is substantially completed to grade, the Contractor shall notify the Engineer. No concrete shall be placed until the foundation has been approved by the Engineer.

Testing: The State will conduct compaction tests during the backfilling and compacting operations.

12-2.07 AGGREGATE BASE

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing, spreading and compacting aggregate base in accordance with the details shown on the plans and these special provisions.

PART 2 - PRODUCTS

Aggregate base:

Aggregate base shall be commercial quality aggregates consisting of broken stone; crushed gravel; natural, clean, rough-surfaced gravel and sand; or a combination thereof.

Aggregate may include reclaimed asphalt concrete, portland cement concrete, lean concrete base, cement treated base or a combination of any of these materials. The amount of reclaimed material shall not exceed 50 percent of the total volume of the aggregate used.

Aggregate base shall conform to the following grading as determined by California Test 202:

Sieve or Screen Size	Percentage Passing
2"	100
1 ½"	90 – 100
1"	
¾"	50 – 85
No. 4	25 – 45
No. 30	10 – 25
No. 200	2 – 9

Aggregate base shall also conform to the following quality requirements:

Tests	California Test No.	Test Requirements
Durability Index	229	35 Min.
Resistance (R-Value)	301	78 Min.
Sand Equivalent	217	22 Min.

PART 3 - EXECUTION

SPREADING AND COMPACTING

Spreading:

Aggregate base shall be placed and compacted to the lines and grades shown on the plans.

Spreading and compacting shall be performed by methods that will produce a uniform base, free from pockets of coarse or fine material.

Compaction: Relative compaction of each layer of compacted base material shall be not less than 95 percent, as determined by California Test 216 or 231.

SECTION 12-3. CONCRETE AND REINFORCEMENT

12-3.01 CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of constructing cast-in-place concrete facilities in accordance with the details shown on the plans and these special provisions.

Whenever the 28-day compressive strength shown on the plans is 3,500 psi or greater, the concrete shall be considered to be designated by compressive strength. The 28-day compressive strengths shown on the plans which are less than 3,500 psi, are shown for design information and are not to be considered a requirement for acceptance of the concrete.

Related Work: Compressive strength concrete shall conform to the requirements in Section 90-9, "Compressive Strength," of the Standard Specifications.

SUBMITTALS

Product Data:

Manufacturer's descriptive data for admixtures, expansion joint material, vapor barrier, hardener, and sealer shall be submitted for approval.

QUALITY ASSURANCE

Certificates of Compliance:

Certificates of Compliance shall be furnished for cement, reinforcement, epoxy products, and admixtures in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

PART 2 - PRODUCTS

CONCRETE MIXES

Concrete (Minor Work):

Commercial quality concrete for concrete curbs, curb ramps, sidewalks, driveways, gutter depressions, new door openings, offsite planters, stairs and collars shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 470 pounds of cement per cubic yard; 0 to 2-inch penetration, inclusive, as determined by California Test 533.

CONCRETE MATERIALS

Cement: Cement shall conform to ASTM Designation: C 150, Types II, or III portland cement; or Type IP (MS) Modified cement. Type IP (MS) Modified shall conform to ASTM Designation: C 595 and shall be comprised of an intimate mixture of Type II Modified cement and not more than 20 percent of a pozzolanic material.

Aggregates:

Fine and coarse aggregates shall be free from deleterious coatings, clay balls and other extraneous materials, and shall meet ASTM C33, crushed limestone or granite from a single source.

Smooth aggregates or gravels shall not be allowed.

Water shall be potable, clean and not detrimental to concrete.

Admixtures: Admixtures used in portland cement concrete shall be included on the Department's current list of approved admixtures, and shall conform to ASTM Designation: C 494, Types A, B, D, F or G for chemical admixtures; ASTM Designation: C 260 for air-entraining admixtures; and ASTM Designation: C 618 for mineral admixtures, except loss on ignition shall not exceed 4 percent. Properties of admixtures shall be uniform in each lot.

FORM MATERIALS

Forms for Exposed Finish Concrete:

Forms for exposed surfaces shall be plywood, metal or other panel type materials. Plywood shall be not less than 5/8 inch thick and without scars, dents, and delaminations. Forms shall be furnished in largest practical pieces to minimize number of joints.

Plywood shall conform to the requirements of U. S. Product Standard PS-1 for Exterior B-B (Concrete Form) Class I.

Forms for edges of slabs shall be nominal 2-inch solid stock lumber, plywood, or metal forms.

Forms for Unexposed Finish Concrete: Forms for unexposed finish concrete surfaces shall be plywood, lumber, metal or other acceptable material.

Forms for Cylindrical Columns or Supports: Forms for cylindrical columns shall be metal, fiberglass reinforced plastic, paper or fiber tubes. Paper or fiber tubes shall be constructed of laminated plies using water-resistant adhesive with wax-impregnated exterior for protection against weather or moisture.

Form Ties: Form ties shall be factory fabricated, removable or snapoff metal ties for use as necessary to prevent spreading of forms during concrete placement.

Form Oil: Form oil shall be commercial quality form oil which will permit the ready release of the forms and will not discolor the concrete.

REINFORCING MATERIALS

Bar Reinforcement: Bar reinforcement shall conform to ASTM Designation: A 615/A 615M, Grade 60 [420], or ASTM Designation: A 706/A 706M, deformed billet steel. Smooth reinforcing bars and dowels may be Grade 40 or Grade 60.

Welded Wire Fabric: Welded wire fabric shall conform to ASTM Designation: A 185.

Bar Supports: Bar supports for reinforcement shall be precast mortar blocks or ferrous metal chairs, spacers, metal hangers, supporting wires, and other approved devices of sufficient strength to resist crushing under applied loads.

Bonding Agent: ASTM C881: Bonding agent shall be two part epoxy adhesive suitable for use on dry and damp surfaces. Provide ICBO report or certified laboratory test report documenting the standard properties of material, type, grade and class to suit requirements and meeting the following minimum requirements:

Bond Strength	ASTM C882	2400 psi
Tensile Strength	ASTM C638	4400 psi
Elongation	ASTM C638	3% max
Compressive Strength	ASTM D695	7500 psi
Slant Shear Strength	ASTM C882	5000 psi

Non-Shrink Grout: No-Shrink Grout shall be premixed compound consisting of non-metallic aggregate, cement, water reducing and plasticizing agents; capable of developing minimum compressive strength of 3000 psi. in 48 hours and 7000 psi in 28 days.

Epoxy Mortars: Epoxy mortar and epoxy mortar surface treatment shall consist of a commercial quality, trowelable mixture consisting of epoxy and sand. Epoxy shall have a pull-off strength of not less than 1,000 psi and a 90-percent cure in 24 hours. Epoxy shall be of the type that requires no primer as a bonding agent.

Sand:

Sand for use in epoxy mortars shall be clean and shall have a moisture content of not more than 0.50-percent when tested in accordance with California Test 226.

Sand for epoxy mortar surface treatment shall be graded such that 100-percent passes the No. 100 sieve.

RELATED MATERIALS

Anchor Bolts, Nuts, and Washers:

Nonheaded anchor bolts shall conform to ASTM Designation: A 36/A 36M, with a minimum hook length of 6.2 diameters.

Headed anchor bolts shall conform to ASTM Designation: A 307.

Threaded rods shall conform to ASTM Designation: A 572.

Nuts shall conform to ASTM Designation: A 563, Grade A.

Washers for anchor bolts shall be commercial quality.

Exposed anchor bolts, nuts, and washers shall be hot dipped galvanized.

Expansion Joint Material: Expansion joint material shall be commercial quality asphalt impregnated pressed fiber sheets, 3/8-inch minimum thickness.

Vapor Barrier: Vapor barrier shall be commercial quality polyethylene sheets not less than 6 mils thick.

Bond Breaker: Bond breaker shall be Type I asphalt saturated organic felt or such other material approved by the Engineer.

Nonskid Abrasive Aggregate: Nonskid abrasive aggregate shall be commercial quality aluminum oxide, silicon carbide, or almandite garnet grit particles; screen size 12-30 or 14-36.

Keyed Construction Joint Forms: Keyed construction joint forms shall be commercial quality, galvanized metal or plastic, factory fabricated construction joint forms. Forms shall produce a rabbeted key type joint.

Mortar: Mortar shall consist of one part cement to 2 parts clean sand and only enough water to permit placing and packing.

Curing Compound: Curing compound shall be a non-pigmented curing compound with fugitive dye conforming to the requirements of ASTM Designation: C 309, Type 1-D, Class A.

Concrete Hardener: Concrete hardener shall be commercial quality water borne penetrating type magnesium fluosilicate, zinc fluosilicate or combination thereof.

Splash Block: Splash blocks shall be precast concrete splash blocks with depressed runoff trough. Splash blocks shall be 12" x 24" x 3½" in size unless otherwise shown on the plans.

ADMIXTURES

Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option to conserve cement or to facilitate any construction operation.

Calcium chloride shall not be used in any concrete.

Admixtures shall be combined with concrete materials by methods that produce uniform properties throughout the concrete.

If more than one admixture is used, said admixtures shall be compatible with each other so that the desirable effects of all admixtures will be realized.

Mineral admixtures may be used to replace up to 15 percent of Type II portland cement provided the weight of mineral admixture used is not less than the weight of cement replaced. Mineral admixtures shall not be used to replace Type IP (MS) Modified or Type III cements. Chemical admixtures may be used to reduce up to 5 percent of the portland cement except that the cement content shall not be less than 470 pounds per cubic yard. When both chemical and mineral admixtures are used with Type II cement, the weight of cement replaced by mineral admixture may be considered as cement in determining the resulting cement content.

When the use of a chemical admixture is specified or is ordered by the Engineer, the admixture shall be used at the rate specified or ordered. If no rate is specified or ordered, or if the Contractor uses a chemical admixture for his own convenience, the admixture shall be used at the dosage normally recommended by the admixture manufacturer.

When air-entrainment is specified or is ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce concrete having the specified or ordered air content as determined by California Test 504. If the Contractor uses air-entrainment for his own convenience, the average air content shall not exceed 4 percent and no single test shall exceed 5½ percent.

Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers shall have sufficient capacity to measure at one time the total quantity required for each batch. If more than one liquid admixture is used in the concrete, a separate measuring unit shall be provided for each liquid admixture and dispensing shall be such that the admixtures are not mixed at high concentrations. When air-entraining admixtures are used with other liquid admixtures, the air-entraining admixtures shall be the first to be incorporated into the mix. Unless liquid admixtures are added to premeasured water for the batch, they shall be discharged to flow into the stream of water so that the admixtures are well dispersed throughout the batch.

BAR REINFORCING STEEL

Bending:

Reinforcing steel bars shall accurately conform to the dimensions shown on the plans.

Bars shall be bent or straightened in a manner that will not crack or break the material. Bars with kinks or improper bends shall not be used.

Hooks, bends and splices shall conform to the provisions of the Building Code Requirements for Reinforced Concrete of the American Concrete Institute.

MIXING AND TRANSPORTING CONCRETE

When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be complete within 1½ hours, or before 250 revolutions of the drum or blades, whichever comes first, after the introduction of cement to the aggregates.

The temperature of mixed concrete, immediately before placing, shall be not less than 50°F nor more than 90°F.

Truck mixers or agitator shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified. The counters shall be of the continuous-registering type, which accurately register the number of revolutions and shall be mounted on the truck so that the Engineer may safely and conveniently inspect them from alongside the truck. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 86°F or above, a time less than 1½ hours may be required.

Each load of concrete for the work shall be accompanied by a trip ticket, a copy of which shall be delivered to the Engineer at the jobsite. The trip ticket shall show volume of concrete, weight of cement and aggregates, quantity of each admixture, quantity of water including water added at the jobsite, time of day the concrete is batched, and revolution counter readings on transit mix trucks at the times the truck is charged and unloaded.

PART 3 - EXECUTION

PREPARATION

Existing Concrete Construction:

Where fresh concrete joins existing or previously placed concrete or masonry, the contact surfaces of the existing or previously placed material shall be roughened, cleaned, flushed with water and allowed to dry to a surface dry condition immediately prior to placing the fresh concrete. The roughened surface shall be as shown on plans, and when not shown shall be no smoother than a wood trowelled surface. Cleaning of the contact surfaces shall remove laitance, curing compounds, debris, dirt and such other substances or materials which would prevent bonding of the fresh concrete.

Abrasive blast methods shall be used to clean horizontal construction joints to the extent that clean aggregate is exposed.

Exposed reinforcing steel located at the contact surfaces which is to be encased in the fresh concrete shall be cleaned to remove any substance or material that would prevent bonding of the fresh concrete.

Forms:

Forms shall be mortar tight, true to the dimensions, lines, and grades shown on the plans, securely fastened and supported, and of adequate rigidity to prevent distortion during placing of concrete.

Forms for exposed surfaces shall be constructed with triangular fillets not less than 3/4" x 3/4" attached so as to prevent mortar runs and to produce smooth straight chamfers at all sharp edges of the concrete.

Form fasteners shall be removable without chipping, spalling, heating or otherwise damaging the concrete surface. Form ties shall be removed to a depth of at least one inch below the surface of the concrete.

The inside surfaces of forms shall be cleaned of all dirt, mortar and foreign material. Forms shall be thoroughly coated with form oil prior to use.

Forms shall not be stripped until at least 40 hours after placing concrete, except soffit forms and supports shall not be released or removed until at least 10 days after placing concrete.

Anchorage and embedded items shall be placed and rigidly secured at their planned locations prior to placing concrete.

Reglets or embedded flashing shall be installed on concrete forms before the concrete is placed.

Redwood dividers shall have 16d galvanized nails partially driven into both vertical faces at 18 inches on center.

Vapor Barrier:

Vapor barrier shall be lapped 6 inches and securely taped at splices. Vapor barrier shall be protected with a 3-inch layer of clean uncompacted sand cover.

Unless otherwise shown on the plans, vapor barrier shall be placed under portions of the floor slab scheduled to receive finish flooring.

Placing Reinforcing Steel:

Reinforcing steel bars shall be accurately placed to the dimensions shown on the plans.

Bar reinforcement conforming to ASTM Designation: A 615/A 615M, Grade 60 [420], or A 706/A 706M shall be lapped at least 60 diameters.

Bars shall be firmly and securely held in position by means of wiring and approved bar supports. The spacing of supports and ties shall prevent displacement of the reinforcing or crushing of supports.

Tie wire shall be clear of concrete formwork and concrete surfaces.

All reinforcing steel shall be in place and inspected before concrete placement begins. Placing of bars on fresh layers of concrete will not be permitted.

Ground Bar: A continuous reinforcing steel bar shall be installed in the building foundation at the location indicated on the plans for the electrical ground bar. The use of epoxy coated reinforcing bar is not permitted. The end of the ground bar shall extend beyond the concrete surface and shall be protected from damage by construction operations.

PLACING CONCRETE

Concrete shall be placed and consolidated by means of internal vibrators to form dense, homogeneous concrete free of voids and rock pockets.

Forms and subgrade shall be thoroughly moistened with water immediately before placing concrete.

Concrete shall be placed as nearly as possible to its final location and the use of vibrators for extensive shifting of the concrete will not be permitted.

Concrete shall be deposited and consolidated in a continuous operation within limits of construction joints, until the placing of the panel or section is completed.

When concrete is to be placed in large areas requiring more than two pours, concrete shall be placed in alternate long strips between construction joints and the final slab infilled.

FINISHING CONCRETE SURFACES

Finishing Unformed Surfaces:

Slabs shall be placed full thickness to finish elevation and leveled to screeds by use of long straightedges. The screeds shall be set to grade at approximately 6-foot centers. After leveling, screeds shall be removed and the surface shall be floated with wooden floats.

Various joints shall be constructed per plans.

The floated surface shall be trowelled with steel trowels. Troweling shall form a dense, smooth and true finish. Walkways, pedestrian ramps, stairs and outdoor slabs for pedestrian traffic shall be given a non-slip broom finish unless a different finish is called for on the plans or in these special provisions.

The application of cement dust coat will not be permitted.

Steel trowel finish and broom finish will not be required for slabs to receive exposed aggregate finish nor for slabs to be covered with ceramic tile.

Concrete floor surfaces to receive ceramic tile shall be floated to grade and then, before final set of the concrete, the floated surfaces shall be roughened with stiff bristled brushes or rakes, to suit the intended finishes.

Finished surfaces of floor slabs shall not deviate more than 1/8 inch from the lower edge of a 10-foot long straight edge.

Finishing Formed Surfaces:

Formed concrete surfaces shall be finished by filling holes or depressions in the surface, repairing all rock pockets, and removing fins. All surfaces of formed concrete exposed to view shall have stains and discolorations removed, unsightly bulges removed, and all areas which do not exhibit the required smooth, even surface of uniform texture and appearance shall be sanded with power sanders or other approved abrasive means until smooth, even surfaces of uniform texture and appearance are obtained.

Cement mortar, patching and finishing materials used to finish exposed surfaces of concrete shall closely match the color of surrounding surfaces.

Nonskid Abrasive Aggregate Finish: Where shown on the plans, walkways shall receive a nonskid abrasive aggregate (grit) finish. The grit shall be applied uniformly at the rate of not less than 0.3 pound per square foot and tamped into the floated concrete surface while the concrete is plastic. The grit shall be buried about 0.7 diameter of each particle into the concrete.

CURING CONCRETE

Freshly placed concrete shall be protected from premature drying and excessive cold or hot temperatures.

Initial curing of floor slabs shall start as soon as free water has disappeared from the concrete surface. The concrete shall be kept continuously wet by application of water for not less than 7 days after the concrete has been placed.

Cotton mats, rugs, carpets, or sand blankets may be used as a curing medium to retain the moisture during the curing period. Curing materials that will stain or discolor concrete shall not be used on surfaces exposed to view.

Prior to placing the curing medium, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing mediums.

Concrete surfaces, other than floor slabs, shall be kept moist for a period of at least 5 days by leaving the forms in place or by covering the exposed surfaces using moist rugs, cotton mats or other curing materials approved by the Engineer.

Concrete curbs, sidewalks, collars, and gutter depressions may be cured with a curing compound.

PROTECTING CONCRETE

Concrete shall not be placed on frozen or frost covered surfaces.

Concrete shall be protected from damage due to rain, freezing or inclement weather, and shall be maintained at a temperature of not less than 40°F for 72 hours. When required by the Engineer, the Contractor shall provide a written outline of his proposed methods of protecting concrete.

Vehicles, equipment, or concentrated loads weighing more than 300 pounds individually and material stockpiles weighing more than 50 pounds per square foot will not be permitted on the concrete within 10 calendar days after placing.

SPECIAL TREATMENTS

Concrete Hardener:

Chemical concrete hardener shall be applied to the floor surfaces shown on the plans, prior to the application of concrete sealer. Surfaces shall be clean and dry before the application of hardener.

The solution shall be applied in accordance with the manufacturer's instructions.

After the hardener has dried, the surface shall be mopped with water to remove encrusted salts.

Concrete Sealer: Concrete sealer shall be applied to the concrete surfaces designated on the plans in accordance with the manufacturer's instructions for heavy duty use. The sealer shall be applied to dry concrete surfaces.

Epoxy Resin Adhesive: Epoxy resin adhesive shall be applied to concrete surfaces shown on the plans. Epoxy resin adhesive shall be mixed and applied in accordance with the manufacturer's recommendations.

Epoxy Mortars:

Epoxy for use as a binder in epoxy mortars shall be thoroughly mixed together before the aggregate is added, and unless otherwise specified, the mix proportions shall consist of one part binder to approximately 4 parts of aggregate, by volume.

All surfaces against which epoxy mortars are to be applied shall be free of rust, paint, grease, asphalt, and loose or deleterious material. Dowels or grout which fail to bond or are damaged before new concrete is placed shall be removed and replaced.

12-3.02 DRILL AND BOND DOWELS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of drilling holes in existing concrete and installing and bonding bar reinforcing steel dowels into such drilled holes in existing concrete in accordance with the details shown on the plans and these special provisions.

PART 2 - PRODUCTS

Bonding Material: The bonding material shall be magnesium phosphate concrete, either single component (water activated) or dual component (with a prepackaged liquid activator), as approved by the Engineer.

Dowels: Dowels shall be bar reinforcing steel, smooth or deformed, as indicated on plans and as specified under "Cast-In-Place Concrete" in Section 12-3, "Concrete and Reinforcement," of these special provisions.

PART 3 - EXECUTION

Installation:

The holes shall be drilled by methods that will not shatter or damage the concrete adjacent to the holes. The diameter of drilled holes shall be 1/2 inch larger than the nominal diameter of the dowels unless otherwise shown on the plans.

Immediately prior to placing the dowels, the holes shall be cleaned of dust and other deleterious materials, and the holes shall be dry.

Sufficient bonding material shall be placed in the hole so that no voids remain after the dowels are inserted.

Dowels which fail to bond or are damaged before new concrete is placed shall be removed and replaced.

Magnesium phosphate concrete shall be formulated for minimum initial set time of 15 minutes and minimum final set time of 25 minutes at 70°F. The materials, prior to use, shall be stored in a cool, dry environment.

Mix water used with water activated material shall be free from oil and impurities and contain not more than 2,000 parts per million as Cl nor more than 1,500 parts per million of sulfate as SO₄.

The quantity of water for single component type or liquid activator for dual component type to be blended with the dry component, shall be within the limits recommended by the manufacturer and shall be the least amount required to produce a pourable batter.

Magnesium phosphate concrete shall not be mixed in containers or worked with tools containing zinc, cadmium, aluminum, or copper metals.

The surface of any dowel coated with zinc or cadmium shall be coated with a colored lacquer before installation of the dowel. The lacquer shall be allowed to dry thoroughly before embedment of said dowels.

12-3.03 ARCHITECTURAL SURFACE (TEXTURED CONCRETE)

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing random cedar board architectural texture for concrete surfaces in accordance with the details shown on the plans and these special provisions.

The random cedar board texture shall be a architectural texture made of deep striations simulating a concrete surface formed with wooden surfaces having horizontally oriented, magnified grain that is very deeply weathered. Striations shall impart a random pattern to the texture.

QUALITY ASSURANCE

A test panel at least 4' x 4' in size shall be successfully completed at a location approved by the Engineer before beginning work on architectural textures. The test panel shall be constructed and finished with the materials, tools, equipment, and methods to be used in constructing the architectural texture. If ordered by the Engineer, additional test panels shall be constructed and finished until the specified finish, texture, and color are obtained, as determined by the Engineer.

The test panel approved by the Engineer shall be used as the standard of comparison in determining acceptability of architectural texture for concrete-surfaces.

REFEREE SAMPLE

The architectural texture shall match the texture, and pattern of the referee sample located at Caltrans, Office of Landscape Architecture, 111 Grand Avenue, Oakland, CA available for inspection by bidders.

PART 2 - PRODUCTS

FORM LINERS

Form liners shall be used for textured concrete surfaces and shall be installed in conformance with the manufacturer's recommendations, unless other methods of forming textured concrete surfaces are approved by the Engineer. Form liners shall be manufactured from an elastomeric material or a semi-elastomeric polyurethane material by a manufacturer of commercially available concrete form liners. No substitution of other types of formliner material will be allowed. Form liners shall leave crisp, sharp definition of the architectural surface. Recurring textural configurations exhibited by repeating, recognizable shadow patterns shall be prevented by proper casting of form liner patterns. Textured concrete surfaces with such recurring textural configurations shall be reworked to remove such patterns as approved by the Engineer or the concrete shall be replaced.

Form liners shall have the following properties:

Description	ASTM Designation:	Range
Elastomeric material		
Shore A hardness	D 2240	20 to 65
Tensile strength (psi)	D 412	130 to 900
Semi-elastomeric polyurethane		
Shore D hardness	D 2240	55 to 65
Tensile strength (psi)	D 2370	2600 minimum

PART 3 – EXECUTION

PREPARATION

Cuts and tears in form liners shall be sealed and repaired in conformance with the manufacturer's recommendations. Form liners that are delaminated from the form shall not be used. Form liners with deformations to the manufactured surface caused by improper storage practices or any other reason shall not be used.

Form liners shall extend the full length of texturing with transverse joints at 8 foot minimum spacing. Small pieces of form liners shall not be used. Grooves shall be aligned straight and true. Grooves shall match at joints between form liners. Joints in the direction of grooves in grooved patterns shall be located only in the depressed portion of the textured concrete. Adjoining liners shall be butted together without distortion, open cracks, or offsets at the joints. Joints between liners shall be cleaned before each use to remove any mortar in the joint.

Adhesives shall be compatible with the form liner material and with concrete. Adhesives shall be approved by the liner manufacturer. Adhesives shall not cause swelling of the liner material.

RELEASING FORM LINERS

Products and application procedures for form release agents shall be approved by the form liner manufacturer. Release agents shall not cause swelling of the liner material or delamination from the forms. Release agents shall not stain the concrete or react with the liner material. For reliefs simulating fractured concrete or wood grain surfaces the application method shall include the scrubbing method using a natural bristle scrub brush in the direction of grooves or grain. The release agent shall coat the liner with a thin film. Following application of form release agent, the liner surfaces shall be cleaned of excess amounts of agent using compressed air. Buildup of form release agent caused by the reuse of a liner shall be removed at least every 5 uses.

Form liners shall release without leaving particles or pieces of liner material on the concrete and without pulling or breaking concrete from the textured surface. The concrete surfaces exposed by removing forms shall be protected from damage.

CURING

Concrete surfaces with architectural texture shall be cured only by the forms-in-place or water methods. Seals and curing compounds shall not be used.

SECTION 12-4. MASONRY

12-4.01 CONCRETE MASONRY UNITS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of constructing reinforced hollow concrete masonry units in accordance with the details shown on the plans and these special provisions.

Water repellent coating shall be applied in accordance with the requirements specified under "Water Repellent Coating" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

PERFORMANCE REQUIREMENTS

Unit Strength: Provide masonry units that develop the following installed compressive strengths (f'm) at 28 days:

Based on net area f'm = 1,500 psi

SUBMITTALS

Product Data: Manufacturer's descriptive data for each type of masonry unit, accessory, and other manufactured products shall be submitted for approval.

Samples: Two samples of masonry units of each color and architectural finish shall be submitted for approval.

QUALITY ASSURANCE

Single Source Responsibility:

Exposed masonry units of uniform color and texture shall be obtained from one manufacturer for each different product required for each continuous surface or visually related surfaces.

Mortar ingredients of uniform quality, including color for exposed masonry, shall be obtained from one manufacturer for each cementitious component and from one source and producer for each aggregate.

Certificates of Compliance: Certificate of Compliance shall be furnished for masonry units, aggregate for grout and transit mixed grout in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

DELIVERY, HANDLING AND STORAGE

Delivery: Masonry materials shall be delivered to the project in an undamaged condition.

Storage and Handling: Masonry units shall be stored and handled in order to prevent deterioration or damage due to moisture, temperature changes, contamination, corrosion or other causes.

PART 2 - PRODUCTS

CONCRETE MASONRY UNITS

Concrete Masonry Units:

Concrete masonry units shall be nominal size, color and architectural finish as shown on plans; hollow load bearing, light weight or medium weight, Grade N, Type II, conforming to ASTM Designation: C 90; standard or masonry units.

Special shapes shall be provided where required for lintels, corners, jambs, sash, control joints, headers, bonding and other special conditions.

MORTAR AND GROUT MATERIALS

Cement:

Cement for mortar shall be Type II, low alkali portland cement conforming to ASTM Designation: C 150; or masonry cement conforming to ASTM Designation: C 91.

Cement for grout shall be Type II portland cement conforming to ASTM Designation: C 150 with maximum 15 percent Class N, F, or C mineral admixture conforming to ASTM Designation: C 618 except that the loss on ignition shall not exceed 4 percent; or Type IP(MS) blended hydraulic cement conforming to ASTM Designation: C 595.

Aggregate:

Aggregate for mortar shall conform to ASTM Designation: C 144, except not more than 10 percent shall pass the No. 100 sieve.

Aggregate for grout shall conform to ASTM Designation: C 404, except 100 percent of the coarse aggregate shall pass the 3/8-inch sieve. Soundness loss shall not exceed 10 percent as determined by California Test 214.

Coloring for Mortar: Coloring for mortar shall be chemically inert, fade resistant mineral oxide or synthetic type.

Lime: Lime shall conform to ASTM Designation: C 207, Type S.

Premixed Mortar or Grout: A premixed packaged blend of cement, lime, and sand, with or without color, that requires only water to prepare for use as masonry mortar or grout may be furnished. Packages of premix shall bear the manufacturer's name, brand, contents, weight, and color identification.

Transit Mixed Grout: Transit mixed grout shall conform to ASTM Designation: C 94, except aggregate shall be as specified herein for aggregate for grout. The minimum compressive strength shall be 2,500 psi at 28 days when tested in accordance with ASTM Designation: C 39. Admixtures, if used, shall conform to ASTM Designation: C 494, Types A, E or F and shall not contain chlorides.

REINFORCEMENT, TIES AND ANCHORING DEVICES

Bar Reinforcement: Bar reinforcement shall conform to ASTM Designation: A 615/A 615 M, Grade 60, or ASTM Designation: A 706/A 706 M.

Anchor Bolts: Anchor bolts shall conform to ASTM Designation: A 36/A 6M with a minimum hook length of 6.2 diameters, and shall be 1/2-inch diameter unless otherwise shown on the plans.

Anchors, Ties, Angles, and Metal Lath: Anchors, ties, angles, and metal lath shall be commercial quality, and shall be galvanized.

Dry Pack: Dry pack to set items into masonry shall be one part portland cement to not over 3 parts of clean sand and with a minimum amount of water for hydration and packing.

PROPORTIONING MORTAR AND GROUT

Mortar shall be proportioned by loose volume and shall have one part cement, one quarter part of hydrated lime and 2¼ to 3 parts aggregate. Mortar shall be tinted with coloring to match the masonry units.

Grout, except transit mixed and packaged premix grout, shall be proportioned by loose volume and shall have one part cement, not more than 1/10 part hydrated lime, 2¼ to 3 parts sand aggregate, and not more than 2 parts gravel aggregate.

Aggregate shall be measured in a damp loose condition.

Grout shall be mixed with sufficient water to produce a mix consistency suitable for pumping without segregation. Slump shall not exceed 9 inches.

PART 3 - EXECUTION

CONSTRUCTION

Masonry units shall be laid in running bond, except as otherwise shown on the plans.

Surfaces of metal, glass, wood, completed masonry, and other such materials exposed to view shall be protected from spillage, splatters and other deposits of cementitious materials from masonry construction. All such deposits shall be removed without damage to the materials or exposed surfaces.

Construction will comply with Section 2104, "Construction," of the CBC. Tolerances specified in Section 2104 shall be in effect unless otherwise shown on the plans.

Where fresh masonry joins concrete or masonry, the contact surfaces of existing material shall be roughened, cleaned and lightly wetted. The roughened surface shall be no smoother than a wood troweled surface. Cleaning shall remove laitance, curing compounds, debris, dirt and any substance which decreases bond to the fresh masonry.

Masonry shall not be erected when the ambient air temperature is below 40°F.

Surfaces of masonry erected when the ambient air temperature exceeds 100°F. shall be kept moist with water for a period of not less than 24 hours. Water shall be uniformly applied with a fog spray at the intervals required to keep the surfaces moist but not to exceed 3 hours unless otherwise approved by the Engineer.

All anchors, bolts, dowels, reglets and other miscellaneous items to be cast into the wall, shall be firmly secured in place before grout is poured.

Laying Masonry Units:

Concrete masonry units shall be laid dry.

During laying of units all cells shall be kept dry in inclement weather by suitably covering incomplete walls. Wooden boards and planks shall not be used as covering materials. The covering shall extend down each side of masonry walls approximately 2 feet.

Chases shall be kept free from debris and mortar.

Bond beam units with an opening at each cross web shall be used at all horizontal reinforcing bars.

Where masonry unit cutting is necessary, all cuts shall be made with a masonry saw to neat and true lines. Blocks with excessive cracking or chipping of the finished surfaces exposed to view will not be acceptable.

Bar Reinforcement:

Bar reinforcement shall be accurately positioned in the center of the cell or as shown on plans and securely held in position with either wire ties or spacing devices near the ends of bars and at intervals not exceeding 192 bar diameters. Wire shall be 16-gage or heavier. Wooden, aluminum, or plastic spacing devices shall not be used. Tolerances for the placement of vertical reinforcement in walls and flexural elements shall be $\pm \frac{1}{2}$ inch. Tolerance for longitudinal reinforcement in walls shall be ± 2 inches.

The minimum spacing for splices in vertical reinforcement for masonry walls shall be 4 feet plus lap.

Bar reinforcement shall not be placed in the plane of mortar joints.

Mortar:

Mortar joints shall be approximately $\frac{3}{8}$ inch wide. Units shall be laid with all head and bed joints filled solidly with mortar for the full width of masonry unit shell. Head joints shall be shoved tight. Exposed joints shall be concave, tooled smooth, unless otherwise shown on the plans.

Mortar that has been mixed more than one hour shall not be retempered.

Mortar placed in joints shall preserve the unobstructed vertical continuity of the concrete filling. Any overhanging mortar projecting more than $\frac{1}{2}$ inch, or other obstruction or debris shall be removed from the inside of such cells.

GROUTING

All cells shall be filled solidly with grout. All grout in the cells shall be consolidated at the time of placement by vibrating and reconsolidated after excess moisture has been absorbed but before plasticity is lost. Slicing with a trowel is not acceptable.

Masonry units may be placed full height of the masonry work before grouting, or they may be placed in increments for individual grout pours.

Cleanouts shall be provided for all grout pours over 5 feet in height. Such cleanouts shall be provided in the bottom course at every cell containing vertical reinforcement. After cell inspection, the cleanouts shall be sealed before filling with grout.

Masonry units shall be placed full height of the grout pour. Grout shall be placed in a continuous pour in grout lifts not exceeding 6 feet. The interruption between placing successive lifts of grout shall be not more than one hour.

Between grout pours, a horizontal construction joint shall be formed by stopping the grout a minimum of $1\frac{1}{2}$ inches below the top of the last course, except if the joint is at a bond beam, it shall be $\frac{1}{2}$ inch below the top of the bond beam unit, or at the top of the wall.

CLEANING AND PROTECTING MASONRY

Splashes, stains or spots on the faces of the masonry exposed to view shall be removed.

Completed masonry shall be protected from freezing for a period of at least 5 days.

FIELD QUALITY CONTROL

Any work not meeting the requirements of section 2105 shall be redone and retested. Sampling, inspecting, reworking and retesting of material will be done at the contractor's expense.

SECTION 12-5. METALS

12-5.01 BUILDING MISCELLANEOUS METAL

PART 1 - GENERAL

Scope: This work shall consist of fabricating, furnishing and installing building miscellaneous metal in accordance with the details shown on the plans and these special provisions.

Building miscellaneous metal shall consist of the following: metal benches, screened vents; handrails; railings; gratings; removable chain guard and post; removable ladder.

Including all anchors, fastenings, hardware, accessories and other supplementary parts necessary to complete the work.

REFERENCES

Codes and Standards: Welding of steel shall be in accordance with American Welding Society (AWS) D 1.1, "Structural Welding Code-Steel" and D 1.3, "Structural Welding Code-Sheet Steel."

SUBMITTALS

Product Data: Submit manufacturer's specifications, anchor details and installation instructions for products used in miscellaneous metal fabrications.

Working Drawings: Working drawings of fabricated items shall be submitted for approval.

QUALITY ASSURANCE

Shop Assembly: Preassemble items in shop to the greatest extent possible to minimize field splicing and assembly. Disassemble units only as necessary for shipping and handling limitations. Clearly mark all units for reassembly and installation.

Inspection and Tests: Materials and fabrication procedures shall be subject to inspection and tests by the Engineer, in mill, shop and field. Such tests will not relieve the Contractor of responsibility of providing materials and fabrication procedures in compliance with specified requirements.

PART 2 - PRODUCTS

MATERIALS

Steel Bars, Plates and Hot-rolled Shapes: Steel bars, plates and hot-rolled shapes shall conform to ASTM Designation: A 36/A 36M.

Galvanized Sheet Steel: Galvanized sheet steel shall conform to ASTM Designation: A 653/A 653M, Grade 33 [230]. Galvanizing shall be G60 [Z180].

Bar Grating : Bar grating shall be commercial quality steel with 1 inch x 1/8 inch bars and ¼ inch square twisted crossbars and shall be fabricated by McNichols, Amico, IKG Industries or equal.

Pipe: Pipe shall be commercial quality standard steel pipe.

Steel Tubing: Steel tubing shall conform to ASTM Designation: A 500, Grade B, or A 501.

Expanded metal: Expanded metal shall be ¾ inch standard 10 gauge galvanized steel with steel "U"-edging. All to receive powder coat finish.

Chain Guard: Chain guard shall be ¼ inch grade 30 proof coil chain, galvanized high test with working load limit of 1,300 lbs.

Latch: Latches shall be ¼ inch latched slip hook with galvanized finish.

Removable Ladder: Removable Ladder shall be aluminum 16 foot extension type, tested for 225 lbs load or greater as fabricated by Werner, Lynn Ladder, Stokes Ladder or equal.

Bolts, Studs, Threaded Rods, Nuts and Washers:

Bolts, studs, threaded rods, and nuts for general application shall conform to ASTM Designation: A 307.

Washers shall be commercial quality.

Fittings: Brackets, bolt, threaded studs, nuts, washers, and other fittings for railings and handrailings shall be commercial quality pipe and fittings.

Expansion Anchors: Expansion anchors shall be ICBO approved for the purpose intended, integral stud type anchor or internally threaded type with independent stud, hex nut and washer.

Powder Driven Anchors: Powder driven anchors shall be plated, spring steel alloy threaded stud type anchors for use in concrete. Spring steel shall conform to ASTM Designation: A 227, Class 1. The diameter, length and type of shank and the number and type of washer shall be as recommended by the manufacturer for the types and thickness of material being anchored or fastened.

Resin Capsule Anchors: Stud anchors for resin capsule anchors shall conform to ASTM Designation: A 307 threaded steel rod with hex nut and washer and sealed glass capsule or cartridge containing an adhesive composed of unsaturated polyester resin and benzol peroxide coated quartz sand. Resin capsule shall be Hilti; Molly; or equal.

Mortar: Mortar shall consist of one part cement, measured by volume, to 2 parts clean sand and only enough water to permit placing and packing.

FABRICATION

Workmanship and Finish:

Workmanship and finish shall be equal to the best general practice in modern shops.

Miscellaneous metal shall be clean and free from loose mill scale, flake rust and rust pitting, and shall be well formed and finished to shape and size with sharp lines and angles. Bends from shearing or punching shall be straightened.

The thickness of metal and details of assembly and support shall give ample strength and stiffness.

Built-up parts shall be true to line and without sharp bends, twists and kinks. Exposed ends and edges of metal shall be milled or ground smooth, with corners slightly rounded.

Joints exposed to the weather shall be made up to exclude water.

Galvanizing: Items indicated on the plans to be galvanized shall be hot-dip galvanized after fabrication. The weight of galvanized coating shall be at least 1½ ounces per square foot of surface area, except drainage grates shall have at least 2 ounces per square foot of surface area.

Powder Coating: Powder coated finished metal shall be cleaned, free of dirt, grease, oil, oxidation, mill scale and other contaminants. The surface must be thoroughly dry before painting with primer coating followed by polyester TGIC powder coating, full gloss smooth. Powder coatings shall be Cardinal, Tiger, Drylac or equal and applied by coating manufacturers approved applicators with facilities capable of coating 8 foot x 4 foot fabricated sections.

Painting: Building miscellaneous metal items not galvanized shall be cleaned and prime painted prior to erection in accordance with the requirements specified for steel and other ferrous metals under "Painting" in Section 12-9, "Finishes," of these special provisions.

Loose Bearing and Leveling Plates: Loose bearing and leveling plates shall be furnished for steel items bearing on masonry or concrete construction, made flat, free from warps or twists, and of required thickness and bearing area. Plates shall be drilled to receive anchor bolts. Galvanize after fabrication.

Steel Pipe Railings and Handrailings:

Pipe handrailing shall consist of handrailing elements supported by metal brackets (wall type) or handrailing elements supported by tubular steel posts (post type).

Ends of railing pipe shall be closed, except for a 1/8-inch diameter weep hole at the low point. Returns shall be made at free ends of hand railing to bring pipe to within ¼ inch of wall or adjoining railing.

Expansion joints shall have pipe sleeves.

All corners on railings shall be rounded. Simple and compound curves shall be formed by bending pipe in jigs to produce uniform curvature; maintain cylindrical cross-section of pipe throughout the bend without buckling, twisting or otherwise deforming exposed surfaces of the pipe.

Wall brackets, end closures, flanges, miscellaneous fitting and anchors shall be provided for interconnections of pipe and attachment of railings and handrails to other work. Inserts and other anchorage devices shall be furnished for connecting railings and handrails to concrete or masonry.

Steel railing shall be powder coated after fabrication. After powder coating, all elements of the railing shall be free of fins, abrasions, rough or sharp edges, and other surface defects and shall not be kinked, twisted or bent.

PART 3 - EXECUTION

GENERAL

Anchorage:

Anchorage devices and fasteners shall be provided for securing miscellaneous metal in-place construction; including threaded fasteners for concrete and masonry inserts, through bolts.

Cutting, drilling and fitting shall be performed as required for installation of miscellaneous metal fabrications. Work is to set accurately in location, alignment and elevation, plumb, level, true and free of rack, measured from established lines and levels.

Loose Leveling and Bearing Plates: Plates shall be set on wedges or other adjustable devices. Anchor bolts shall be wrench tightened after the plates have been positioned and plumbed. Mortar shall be packed solidly between bearing surfaces and plates to ensure that no voids remain.

Steel Pipe Railings and Handrailings:

Railings shall be adjusted prior to anchoring to ensure matching alignment at abutting joints. Secure posts and railing ends to building construction as shown on the plans.

The location of expansion joints shall be in accordance with manufacturer's recommendation except that joints shall be spaced not closer than 15 feet apart and shall be coordinated with joint locations in the support structure.

Exposed connections shall be fitted to form tight, hairline joints.

Resin capsule anchors shall not to be used for anchoring railings and handrailings.

Powder Driven Anchors: Powder driven anchors shall be installed with low velocity powder actuated equipment in accordance with the manufacturer's instructions and State and Federal OSHA regulations.

Resin Capsule Anchors: Resin capsule anchors shall be installed in accordance with the manufacturer's instructions.

DAMAGED SURFACES

Galvanized surfaces that are abraded or damaged at any time after the application of the zinc coating shall be repaired by thoroughly wire brushing the damaged areas and removing all loose and cracked coating, after which the clean areas shall be painted with 2 applications of unthinned zinc-rich primer (organic vehicle type). Aerosol cans shall not be used.

Powder coated surfaces that are abraded or damaged shall be repaired in accordance with the coating manufacturers recommendation for maximum protection.

SECTION 12-6. WOOD AND PLASTICS

12-6.01 CABINETS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing plastic laminated cabinets and plastic laminate tops, splashes and returns as shown on the plans and in these special provisions.

SUBMITTALS

Product Data: Manufacturer's product data for plastic laminates and cabinet hardware shall be submitted for approval.

Samples: Three samples shall be submitted for each of the items shown below:

Plastic laminate, 8" x 10" for each type, color, pattern and surface finish.

Shop Drawings: Shop drawings for cabinets showing location of cabinets, dimensioned plans and elevations, attachment devices and other components shall be submitted for approval. Shop drawings shall bear the "WIC Certified Compliance Label" on the first sheet of the drawings.

QUALITY ASSURANCE

Codes and Standards: Cabinets shall be manufactured and installed in accordance with the Manual of Millwork of the Woodwork Institute of California (WIC) requirements for the grade or grades specified or shown on the plans.

Certificates of Compliance:

Prior to delivery to the jobsite, the cabinet manufacturer shall issue a WIC Certified Compliance Certificate indicating that the products he will furnish for this job and certifying that they will fully meet all the requirements of the grade or grades specified.

WIC Certified Compliance Label shall be stamped on all cabinet work.

Each plastic laminate top shall bear the WIC Certified Compliance Label.

Prior to completion of the contract, a WIC Certified Compliance Certificate for Installation shall be delivered to the Engineer.

DELIVERY, STORAGE AND HANDLING

Protection: Cabinets shall be protected during transit, delivery, storage and handling to prevent damage, soiling and deterioration.

PART 2 - PRODUCTS

ACCEPTABLE MANUFACTURERS

Manufacturers: Subject to compliance with these specifications, high pressure decorative laminates shall be Consoweld Corp.; Formica Corp.; Nevamar Corp.; or equal.

MANUFACTURED UNITS

Cabinets shall be fabricated to the dimensions, profiles, and details shown on the plans with openings and mortises precut, where possible to receive hardware and other items and work.

Fabrication, assembly, finishing, hardware application, and other work shall be completed to the maximum extent possible prior to shipment to the jobsite.

Laminate Clad Cabinets:

Laminate clad cabinets shall be custom grade, flush overlay construction.

Laminate cladding shall be high pressure decorative laminate complying with NEMA LD 3. Color, pattern and finish shall be as shown on the plans. Laminate surface and grade shall be as follows:

Horizontal and vertical surfaces other than tops shall conform to GP-50 (50-mil nominal thickness).

Postformed surfaces shall conform to PF-42 (42-mil nominal thickness).

Laminated Counter Tops and Splashes:

Laminated counter tops and splashes shall be WIC custom grade.

Surface material shall be high pressure laminated plastic conforming to NEMA LD-3, 50-mil thickness.

Unless otherwise shown on the plans, splashes shall be 4 inches high from the surface of the deck. Back splashes shall be continuous formed and coved. Side splashes shall be top set.

Laminated counter tops self edged, counter tops to receive sinks or plumbing fixtures shall have a bullnose.

The underside of tops and backsides of splashes shall be covered with an approved backing sheet.

CABINET HARDWARE AND ACCESSORY MATERIALS

Cabinet hardware and accessory materials shall be provided for cabinets.

Hardware shall be provided with standard US 260 metal plated finish .

Drawer Slides: Drawer slides shall be side mounting full extension with fully enclosed rolling balls and rollers. Concealed slides and bearings, and positive stop. Capacity shall be not less than 75 pounds, except capacity shall be not less than 100 pounds for heavy duty drawers.

Door Guides: Sliding door guides shall be continuous, dual channel, metal guides, top and bottom. Bottom guide shall have crowned track.

Shelf Supports: Shelf supports shall be adjustable, semi-recessed, chrome finished pressed metal, heavy duty standards and support clip, with one inch adjustment increments.

Cabinet Hinges:

Cabinet hinges shall be steel. Length of jamb leaf shall be 2½ inches.
Cabinet hinge manufacturers shall be Stanley, Hager, McKinney, or equal.

Cabinet Catches:

Cabinet catches shall be self aligning magnetic type in aluminum case with zinc plated steel strike.

Cabinet catch manufacturers shall be Stanley, Hager, McKinney, or equal.

Cabinet Pulls:

Cabinet pulls shall be 5/16-inch diameter rod, with 1 5/16-inch projection and 3-inch center to center fastening.

Cabinet pull manufacturers shall be Stanley, Hager, McKinney, or equal.

FABRICATION

Shop Assembly:

Nails shall be countersunk and the holes filled, molds shall be neatly mitered and all joints shall be tight and true.

As far as practicable, work shall be assembled at the mill and delivered to the building ready to be set in place. After assembly, work shall be cleaned and made ready for installation.

All work shall be prepared to receive finish hardware. Finish hardware shall be accurately fitted and securely fastened as recommended by the manufacturer. Finish hardware shall not be fastened with adhesives.

Drawers shall be fitted with dust covers of ¼-inch plywood or hardboard above compartments and drawers except where located directly under tops.

Precut Openings: Openings for hardware, appliances, plumbing fixtures, and similar items shall be precut where possible. Openings shall be accurately located and templates used for proper size and shape. Edges of cutouts shall be smoothed and edges sealed with a water-resistant coating.

PART 3 - EXECUTION

INSTALLATION

Cabinets: Cabinets shall be installed without distortion so that doors and drawers fit openings properly and are accurately aligned. Hardware shall be adjusted to center doors and drawers in openings and to provide unencumbered operation. Installation of hardware and accessory items shall be completed as indicated on the approved drawings.

Laminate Tops: Laminate tops shall be securely fastened to base units and other support systems as indicated on the approved drawings.

Cabinet Hardware:

Doors for cabinets shall be equipped with one pair of hinges and one catch per leaf, unless otherwise shown on the plans. Each door leaf shall be equipped with one pull.

Drawers up to 24 inches wide shall have one pull and drawers over 24 inches wide shall have two pulls.

SECTION 12-7. THERMAL AND MOISTURE PROTECTION

12-7.01 BITUMINOUS WATERPROOFING

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and applying a bituminous waterproofing membrane in accordance with the details shown on the plans and these special provisions.

Bituminous waterproofing membrane shall consist of a coating of primer, a bonded, continuous membrane composed of 2 layers of asphalt saturated glass fabric and 3 moppings of waterproofing asphalt.

SUBMITTALS

Product Data: Manufacturer's descriptive data, installation instructions and recommendations for each waterproofing material shall be submitted for approval.

QUALITY ASSURANCE

The Contractor shall obtain primary materials from a single manufacturer. Secondary materials shall be only as recommended by the primary manufacturer.

Labels: Materials shall be furnished which have factory applied labels affixed to each container or roll of material certifying compliance with ASTM standards specified.

PART 2 - PRODUCTS

Asphalt Primer: Asphalt primer shall be cut-back type conforming to ASTM Designation: D 41.

Waterproofing Asphalt: Waterproofing asphalt shall conform to ASTM Designation: D 449, Type I, suitable for vertical surfaces below grade.

Glass Fiber Fabric: Glass fiber fabric shall conform to ASTM Designation: D 1668, Type I, for woven glass fabric treated with asphalt and weighs about 1.5 pounds per 100 square feet.

Plastic Cement: Plastic cement shall be suitable for use with bituminous materials.

Protection Board: Protection board shall be organic fiberboard treated for resistance to fungus and insects, asphalt impregnated and asphalt coated on both faces; ½ inch thick unless otherwise noted.

PART 3 - EXECUTION

PREPARATION

Protection: Liquid or mastic compounds shall not be permitted to enter or clog drains and conductors. Spillage or migration onto other surfaces of work shall be prevented by masking or otherwise protect adjoining work.

Surface Preparation: All concrete surfaces which are to be waterproofed shall be reasonably smooth and free from holes and projections which might puncture the membrane. The surface shall be dry and thoroughly cleaned of dust and loose materials.

The primer shall be applied to the surface and allowed to dry before applying asphalt.

INSTALLATION

Installation shall comply with manufacturer's instructions, except where more stringent requirements are shown or specified, and except where proper conditions require extra precautions or provisions to ensure satisfactory performance of work.

Application:

No primer or asphalt shall be applied in wet weather, nor when the temperature is below 65°F. Heating shall be in accordance with the manufacturer's instructions.

Multiple-courses of bitumen and felts or fabrics shall be installed in individual courses, unless manufacturer recommends shingle-fashion courses. Courses shall be laid in direction or directions recommended.

Membrane shall be extended as flashing at edges, openings and projections, so as to complete waterproof enclosure as required for leakproof installation.

Protection Board: Protection board shall be set into last course of asphalt before it cools.

12-7.02 SHEET WATERPROOFING

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing a premolded bituminous sheet waterproofing system in accordance with the details shown on the plans and these special provisions.

The premolded membrane waterproofing system shall consist of an adhesive or primer coating, bituminous membrane, drainage composite board with perimeter drain, mastic for sealing the edges of the sheet at corners and drains, and a protective covering attached to the exposed bituminous sheet.

Pre-applied waterproofing system shall consist of a preformed membrane set on the blind side with lapped taped joints, composite board with perimeter drain all set to soil retention system.

SUBMITTALS

Product Data: Manufacturer's descriptive data, installation instructions and recommendations for each waterproofing material shall be submitted for approval.

QUALITY ASSURANCE

Single Source Responsibility: Primary waterproofing materials shall be obtained from a single manufacturer and secondary materials shall be only as recommended by the manufacturer of the primary materials.

Labels: Materials shall be furnished which have factory-applied labels affixed to each container or roll of material certifying compliance with ASTM standards specified.

PART 2 - PRODUCTS

Premolded Membrane: Preformed membrane shall be premolded sheets of bitumen and other compounds, laminated between bituminous saturated felts, reinforced with glass fiber of similar fabrics or mats, coated with bitumen and covered with plastic anti-stick film. Vapor transmission rating shall be not more than 0.005 grains per square foot per hour when tested in accordance with ASTM Designation E 96 and weight approximately 60 pounds per 100 square feet.

Adhesives: Adhesives shall be types of adhesive compounds and tapes recommended by the waterproofing manufacturer, for bonding to substrate, for waterproof sealing of seams in membrane and for waterproof joints between membrane and flashings, adjoining surfaces and projections through membrane.

Primer: Primer shall be type of concrete primer recommended by the manufacturer of the sheet waterproofing.

Protective Covering: Protective covering shall be hardboard, 1/8 inch thick or such other material that will furnish equivalent protection to the preformed membrane. Protective covering shall prevent cutting, scratching, depression or any other damage to the membrane caused by concrete, backfill material or equipment.

Manufacturers: Subject to conformance with waterproofing intent products and systems shall be by Grace Construction Products ('Preprufe', 'Hydroduct; etc.); Bentonite Waterproofing; or equal.

PART 3 - EXECUTION

Preformed membrane waterproofing shall not be applied to any surface until the Contractor is prepared to follow its application with the placing of the protective covering and concrete or backfill within a sufficiently short time that the membrane will not be damaged by workers, equipment, exposure to weathering or from any other cause. Damaged membrane or protective covering shall be repaired or replaced by the Contractor at his expense.

PREPARATION

Surface Preparation: All surfaces which are to receive waterproofing including soil retention system for pre-applied water proofing system, shall be reasonably smooth and free from holes and projections which might puncture the membrane. The surface shall be dry and thoroughly cleaned of dust and loose materials.

Prime Coat:

The primer shall be applied in one coat to the entire area to be sealed by spray or roller methods. The rate shall be as recommended by the primer manufacturer.

All primers shall be thoroughly mixed and continuously agitated during application. Primers and adhesive shall be allowed to dry to a tack free condition prior to placing membrane sheets.

INSTALLATION

Application:

Preformed membrane material shall be placed vertically with each successive sheet lapped to the preceding by a minimum of 3 inches. Horizontal splices shall be lapped by a minimum of 6 inches. Manufacturer's details shall be used where patented systems are used.

Exposed edges of membrane sheets shall have a trowelled bead of manufacturer's recommended mastic applied after the membrane is placed.

Outlet fittings shall be attached to drainage composite board in accordance with manufacturer's instructions and shall be connected to the drainage system in locations shown on plans.

Holes or tears in the preformed membrane sheeting shall be patched with an additional layer of membrane sheet of sufficient size to provide a 5-inch minimum lap outside the edge of the defect or as recommended by the manufacturer.

Protective Covering:

The surface of the waterproofing membrane shall be cleaned free of all dirt and other deleterious material before the protective covering is placed.

The protective covering shall be placed on a coating of adhesive of a type recommended by the manufacturer. The adhesive shall be applied at a rate sufficient to hold the protective covering in position until the concrete or backfill is placed.

12-7.03 WATER REPELLENT COATING

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and applying water repellent coating to concrete surfaces in accordance with the details shown on the plans and these special provisions.

The water repellent coating shall be applied to all exposed concrete wall and interior floor surfaces as shown on the plans.

SUBMITTALS

Product Data: Manufacturer's descriptive data, application instructions and general recommendations for water repellents shall be submitted for approval.

QUALITY ASSURANCE

Codes and Standards: Water repellent coatings shall comply with all rules and regulations concerning air pollution in the State of California.

Certificates of Compliance: Certificates of Compliance shall be furnished with each shipment of water repellent coating materials in accordance with Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

PART 2 - PRODUCTS

Water Repellent Coating: Water repellent coating shall be clear, colorless, water-based sealer. Water repellent coating shall be Hydrozo Inc., Clear Double 7; Euclid Chemical Co., Architectural Seal VOX; Tamms Industries Co., Chemstop; or equal.

PART 3 - EXECUTION

Preparation: All surfaces to receive water repellent coating shall be dry and cleaned by removing contaminants that block pores of the surface. Cleaning methods shall be as recommended by the water repellent manufacturer.

Application:

The water repellent solution shall be applied in accordance with the manufacturer's printed instructions.

The time period between applications of water repellent coating shall be not less than 24 hours.

Protection: Surfaces of other materials surrounding or near the surfaces to receive the water repellent coating shall be protected from overspray or spillage from the waterproofing operation. Water repellent coating applied to surfaces not intended to be waterproofed shall be removed and the surfaces restored to their original condition.

12-7.04 SEALANTS AND CAULKING

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and applying sealants and caulking which are required for this project, but not specified elsewhere, in accordance with the details shown on the plans and these special provisions.

Related Work: Pourable polyurethane joint sealant shall conform to the requirements under "Joint Sealant" elsewhere in this Section 12-7.

QUALITY ASSURANCE

Certificates of Compliance: Certificates of compliance shall be furnished for the sealants and caulking in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

SUBMITTALS

Product Data: Manufacturer's descriptive data and installation instructions for all sealants shall be submitted for approval.

Samples: Color samples of all sealants shall be submitted for approval. Unless otherwise shown on the plans, colors will be selected by the Engineer from the manufacturer's standard colors.

PART 2 - PRODUCTS

MATERIALS

All sealants, primers and accessories shall be non-staining to adjacent exposed surfaces. Products having similar applications and usage shall be of the same type and same manufacturer. Gun consistency compound shall be used unless otherwise required by the job conditions.

Acrylic Sealant: Acrylic sealant shall be one compound, solvent release acrylic sealant.

Butyl Sealant: Butyl sealant shall be one component, skinning type.

Silicone Sealant: Silicone sealant shall be one component, low modulus building sealant. Sealant shall be tack-free in one hour, shall not sag or flow, shall be ozone resistant and capable of 100 percent extension without failure.

Joint Sealant: Joint sealant shall be a two-part, non sag polysulfide base, synthetic rubber sealant formulated from liquid polysulfide polymer.

Backer Rod: Backer rod shall be round, open or closed cell polyurethane. Backer rod shall be sized such that it must be compressed between 25 percent and 75 percent of its uncompressed diameter during installation in the joint.

Neoprene: Neoprene shall conform to the requirements of ASTM Designation: C 542.

PART 3 - EXECUTION

APPLICATION

Unless otherwise shown on the plans, sealants shall be applied in accordance with the manufacturer's instructions.

Silicone sealants shall not be used in locations where painting is required.

Butyl sealants shall not be used in exterior applications, and acrylic sealants shall not be used in interior applications.

Sealants shall be applied in a continuous operation for the full length of the joint. Immediately following the application of the sealant, the sealant shall be tooled smooth using a tool similar to that used to produce concave masonry joints. Following tooling, the sealant shall remain undisturbed for not less than 48 hours.

12-7.05 THERMOPLASTIC MEMBRANE ROOFING

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing fully adhered single-ply sheet roofing system in accordance with the details shown on the plans and these special provisions.

The roof system shall include membrane, bonding adhesive, flashing, fasteners and other materials required, but not necessarily mentioned, which provide a complete and waterproof assembly meeting the performance requirements specified herein.

References: The publications listed below form a part of this specification to the extent reference. The publications are referred to in the text by the basic designation only.

ASTM E 108 (1996) Fire Tests of Roof Coverings
FM A/S4470 (1986; R 1992) Class I Roof Covers
FM DS/1-28 (1996) Wind Loads to Roof Systems and Roof Deck
FM DS/1-29 (1996) Above-Deck Roof Components
FM P7825 (1999) Approval Guide
UL RMSD (1997) Roofing Materials and Systems Directory
UL 790 (1997) Fire Resistance of Roof Covering Materials

PERFORMANCE REQUIREMENTS

General: The roof cover assembly shall prevent the passage of water; and resist specified uplift pressures, thermally induced movement, and exposure to weather without failure. Roofing materials shall be compatible with one another under conditions of service and application required, as demonstrated by roofing membrane manufacturer based on testing and field experience.

Fire Safety: The roof covering assembly shall comply with ASTM E 108 Class 1A or UL 790 Class A classification; and shall be listed as part of Fire-Classified roof deck construction in the UL RMSD or Class I roof deck construction in the FM P7825. UL approved components of the roof covering assembly shall bear the UL label.

Wind Uplift: The roof covering assembly shall be rated Class I-90 in accordance with FM P7825 capable of withstanding an uplift pressure of 90 pounds per square foot.

SUBMITTALS

Product Data: Manufacturer's descriptive data, Factory Mutual test reports, product specifications, storage requirements and installation instructions shall be submitted for approval.

Shop Drawings: Shop drawings for roofing system shall include plans, elevations, sections, details, and attachments to other work. Include base flashings, membrane terminations, and insulations fastening pattern.

Samples: Three samples of the following products shall be submitted for approval:

White roofing sheet 11" x 8 1/2" in two pieces with welded joint.

QUALITY ASSURANCE

Certificates of Compliance: Certificates of compliance shall be furnished for the roofing membrane in accordance with the requirements specified in Section 4-1.04, "Certificates of Compliance," of the Standard Specifications.

Single source responsibility: Roofing materials shall be obtained from a single manufacturer. Secondary materials shall be as recommended by the thermoplastic roofing manufacturer.

Installer's qualification: Membrane roofing installer shall be approved and certified by the thermoplastic roofing manufacturer as qualified to install this type of roofing. A copy of the manufacturer's certification shall be given to the Engineer prior to the installation of any roofing materials.

Pre-roofing conference: After approval of submittals and prior to installation of roofing or associated work, the Contractor shall convene a pre-roofing conference with the installer, roofing manufacturer and the Engineer. Discussions and agreements shall be recorded and copies furnished to each participant. Advance notice of the meeting shall be given in writing to each participant at least 72 hours prior to meeting.

PROJECT CONDITIONS

Weather: The contractor shall not install membrane sheet roofing during high winds or inclement weather, or when there is ice, frost, moisture, or visible dampness on the substrate surface. Unless recommended otherwise by the membrane sheet manufacturer, the contractor shall not install membrane sheet when air temperature is below 40°F of the dew point.

Roofing work shall proceed when existing and forecasted weather conditions permit the work to be performed in accordance with the manufacturer's recommendations and warranty requirements.

DELIVERY, STORAGE AND HANDLING

Delivery storage and handling: Materials shall be delivered to the job site in manufacturer's original unopened packages clearly labeled with manufacturer's name and identification numbers. Materials shall be stored in strict accordance with the manufacturer's printed storage requirements. Material shall be handled in such a manner as to prevent damage and premature curing.

WARRANTY

The Contractor shall furnish the membrane sheet manufacturer's 15 year warranty for the roofing system, including flashings, and accessories. The warranty shall be supplied directly to the Engineer.

The warranty shall state that: When within the warranty period the membrane sheet roofing system becomes non-watertight, splits, tears, or separated at the seams because of defective materials and workmanship, the repair or replacement of defective materials and correction defective workmanship shall be the responsibility of the roofing

manufacturer; When the manufacturer or the manufacturer's approved applicator fail to perform repairs within 72 hours of notifications, emergency repairs performed by others will not void the warranty. Damage to the thermoplastic roofing system by sustained winds having a velocity of 56 miles per hour or less is covered by the warranty.

PART 2 – PRODUCTS

GENERAL

Performance: Roofing materials shall be provided which are recognized to be of generic type indicated and tested to show compliance with indicated performance.

Compatibility: Products which are recommended by the manufacturer shall be fully compatible with the substrates used.

MANUFACTURERS

Available manufacturers: Subject to compliance with the specifications, manufacturers offering products which may be incorporated into the work include, but are not limited to, GAF Roofing Products 'Everguard TPO', Flex Membrane International; Cooley Engineered Membrane; or equal.

MATERIALS

Membrane: Roofing membrane shall be thermoplastic elvaloy alloy of keytone ethylene ester (KEE), polyester reinforced, 45 mil nominal thickness for fully adhered application. Width and length of sheet shall be as recommended by the manufacturer. Color shall be white. Thermoplastic sheet shall have the following values when tested for the listed properties in accordance with the test methods:

Property	Value	Test Method
Thickness, min., in	0.045±10%	ASTM D75
Breaking Strength, min., lbfxlb	285x245	ASTM D 751 A-Grab Method
Elongation, min., percent	30	ASTM D 751 A-Grab Method
Tear Strength, min., lbfxlb (Tongue tear 8in by 8in sample)	124x140	ASTM D 751
Low Temperature Bend at -40 degrees C	Pass	ASTM D 2136
Linear Dimension Change. Max. percent (1 hour at 212°F)	2.0	ASTM D 1204
Ply Adhesion, min. lb-ft	0.33	ASTM D 413 Machine Method
Hydrostatic Resistance, min., psi	390	ASTM D 751 Method A
Ozone Resistance (2 x Magnification)	No cracks	ASTM D 1149 Bent Loop Method. Method B Exposure Method D 5181
Accelerated Weather Resistance. 5,000 Hours (7 x Magnification)	No cracking, or discoloration negligible	ASTM D 2565 Type BH2 or ASTM G 53 Type UVB3
Permeance, max., perms	0.055	ASTM E 96, Procedure BW

AUXILIARY MATERIALS

Bonding Adhesive: Bonding adhesive shall be manufacturer's standard water based type for membrane, and solvent-based for base flashings.

Flashing and flashing accessories: Flashing including perimeter flashing, flashing around roof penetrations, shall be thermoplastic alloy coated metals, thermoplastic membrane, or membrane premolded corners or boots for use around penetrations as recommended as standard by the membrane sheet manufacturer's printed instructions. Thermoplastic alloy coated metal base flashings shall be field fabricated where required. Sheet metal base flashings that will contact membrane shall be turned under 1/2 inch to form a hem.

Miscellaneous accessories: Miscellaneous items shall include but not limited to pourable sealers, preformed cone and vent sheet flashings, preformed inside and outside corner sheet flashings, T-joint covers, termination reglats, fasteners, cover strips and pressure treated nailer strips.

Protection board: Protection board shall be glass ¼ inch, rigid, moisture resistant, glass mat gypsum roof board conforming to ASTM C 1177, 25 flame spread and 450 smoke developed in accordance with ASTM E 84, compressive strength shall be a minimum of 70,000 psf . Protection board shall be: Georgia Pacific (Dens-deck); National Gypsum Company; or equal.

Wood nailers: Wood nailers at joints shall be Douglas fir, pressure treated.

PART 3 – EXECUTION

PREPARATION

General: The roof deck substrate shall be completely installed prior to installation of the roofing membrane. The roof deck shall be swept clean and be free of sharp edges, cracks, debris, oil and grease and otherwise suitably prepared to accept the roofing membrane.

Examination: Examine substrate, areas, and conditions, with installer present, for compliance with the following requirements and other conditions affecting performance of roofing system:

Verify that wood blocking, curbs and nailers are securely anchored to roof deck at penetrations and terminations and that nailers match thickness of insulation.

INSTALLATION

Adhered roofing membrane installation.

General: Install roofing membrane over area to receive roofing according to membrane roofing system manufacturer's written instructions. Unroll roofing membrane and allow to relax before installing.

Install sheet according to ASTM D 5036.

Start installation of roofing membrane in presence of membrane roofing system manufacturer's technical personnel.

Accurately align roofing membrane and maintain uniform side and end laps of minimum dimensions required by manufacturer. Stagger end laps.

Bonding Adhesive: Apply bonding adhesive to substrate and underside of roofing membrane at rate required by manufacturer and allow to partially dry before installing roofing membrane. Do not apply bonding adhesive to splice area of roofing membrane.

Adhesively fasten roofing membrane securely at terminations, penetrations, and perimeter of roofing.

Clean seam areas, overlap roofing membrane, and hot-air weld side and end laps of roofing membrane according to manufacturer's written instructions to ensure a watertight seam installation.

Test lap edges with probe to verify seam weld continuity. Apply lap sealant to seal cut edges of roofing membrane.

Verify field strength of seams a minimum of twice daily and repair seam sample areas.

Repair tears, voids, and lapped seams in roofing membrane that does not meet requirements.

Spread sealant or mastic bed over deck drain flange at deck drains and securely seal roofing membrane in place with clamping ring.

Flashing installation: Install thermoplastic alloy coated metal base prior to installing thermoplastic membrane. Install flashing in accordance with printed application instruction of membrane sheet manufacturer. Fully adhere membrane

base flashing to substrate using bonding adhesive. Extend base flashing not less than 8 inches above roofing surface. Where membrane flashing terminates under a metal reglet, caulk reglet with polyurethane or poly sulfide sealant. Provide premolded corners to complete flashings or curbs, parapets, and other vertical surfaces and prefabricated pipe boots for pipe penetrations where possible. Do not use pitch pockets.

Expansion joints installation: Install prefabricated covers or membrane flashing over the expansion joints in accordance with membrane sheet manufacturer's printed instructions.

FIELD QUALITY CONTROL

Final Roof Inspection: Arrange for roofing system manufacturer's technical personnel to inspect roofing installation on completion and submit report to the Engineer.

Notify the Engineer 2 working days or 72 hours in advance of date and time of inspection.

Repair or remove and replace components of membrane roofing system where test results or inspections indicate that they do not comply with specified requirements.

Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance or replaced or additional work with specified requirements.

PROTECTING AND CLEANING

Protect membrane roofing system from damage and wear during remainder of construction period. When remaining construction will not affect or endanger roofing, inspect roofing for deterioration and damage, describing its nature and extent in a written report, with copies to Resident Engineer.

Correct deficiencies in or remove membrane roofing system that does not comply with requirements, repair substrates, and repair or reinstall membrane roofing system to a condition free of damage and deterioration at time of Substantial Completion and according to warranty requirements.

Clean overspray and spillage from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

12-7.06 SHEET METAL FLASHING

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of fabricating, furnishing and installing sheet metal flashing in accordance with the details shown on the plans and these special provisions.

Sheet metal shall include metal flashings, counterflashings, straps, gutters, downspouts, roof jacks, gravel stops, reglets, copings, scuppers, conductor heads, and screen type vents.

Alternatives: Premolded roof flashings may be used in lieu of sheet metal flashings where shown on the plans.

SUBMITTALS

Product Data: Provide manufactures product and complete installation data for all materials.

Shop Drawings: Plans, sections, elevations or isometric drawings shall be provided for each sheet metal component, and shall show jointing method and attachment to other work.

QUALITY ASSURANCE

Codes and Standards: Sheet metal work shall be in accordance with the requirements in the latest edition of the Sheet Metal and Air Conditioning Contractors National Association (SMACNA) "Standard Practice in Architectural Sheet Metal Work."

PART 2 - PRODUCTS

MATERIALS

Galvanized Sheet Steel: Galvanized sheet steel shall conform to ASTM Designation: A 653/A 653M with G 90 [Z275] coating, not less than 24-gage, unless otherwise shown on the plans. Surfaces to be painted shall not have factory coatings on galvanizing that cannot be removed by paint thinner.

Sheet Aluminum: Sheet aluminum shall be not less than 0.032 inch thick, mill finish, 3003-H14 alloy, conforming to ASTM Designation: B 209M.

Sheet Lead: Sheet lead shall be not less than 0.062 inch thick, conforming to ASTM Designation: B 749.

Premolded Roof Flashing: Premolded flashing shall be premolded neoprene or ethylene propylene diene monomer (EPDM) flashing, resistant to ozone and ultraviolet. Units shall have overlapping tab to flash the seam.

Hardware and Fastenings: Hardware and fastening for premolded roof flashings shall be stainless steel.

Solder: Solder shall conform to ASTM Designation: B 32, Alloy Grade Sn50.

Soldering Flux: Soldering flux shall be acid type, conforming to Federal Specification: O-F-506C, Type I, Form A.

Insect Screen: Insect screen shall be industrial wire cloth and screen, medium grade, 18 mesh, 0.017-inch diameter, 0.039-inch openings, plain weave, galvanized steel conforming to ASTM Designation: E 437.

Lap Joint Sealant: Lap joint sealant for concealed locations shall be a non-drying butyl.

Flashing Cement: Flashing cement shall be a bituminous plastic cement, asbestos free, conforming to ASTM Designation: D 4586, Type II.

Sealant: Sealant for exposed locations shall be a silicone sealant conforming to ASTM Designation: C 920.

Primer: Primer shall be as recommended by the sealant manufacturer.

Coal Tar Paint: Coal tar paint shall be coal-tar epoxy coating conforming to U.S. Corps of Engineers Specification: C-200 or Steel Structures Painting Council Paint Specification: SSPC-16-68T.

FABRICATION

Sheet metal shall be assembled to Sheet Metal and Air Conditioning Contractors National Association Standards.

Sheet metal shall be formed to the sizes, shapes and dimensions shown on the plans or as specified herein with angles and lines straight, sharp and in true alignment. The number of joints shall be kept to a minimum.

Angle bends and folds for interlocking the metal shall be made with full regard for expansion and contraction to avoid buckling or fullness in the metal after it is installed.

Joints in sheet metal work shall be closed watertight unless slip joints are specifically required. Watertight joints shall be mechanically interlocked and then thoroughly soldered for metals other than aluminum. Watertight joints in aluminum or between aluminum and other metals shall be sealed with acrylic sealant.

Sheet metal joints to be soldered shall be cleaned with steel wool or other means, pre-tinned and soldered watertight.

All joints shall be wiped clean of flux after soldering. Acid flux shall be neutralized by washing the joints with sodium bicarbonate.

Flashings shall have a 45 degree drip return at bottom edges. Unless otherwise shown on the plans, counterflashing shall extend not less than 4 inches over roofing or other materials protected by the counterflashing and shall be arranged so that roofing or materials can be repaired without damage to the counterflashing. Where reglets are indicated, counterflashing shall be fastened by lead wedges or snap-in flashing.

PART 3 - EXECUTION

Preparation: Surfaces to receive sheet metal shall be clean, smooth and free from defects.

Protection: Aluminum surfaces to be in contact with concrete, mortar, or dissimilar metals shall be given a heavy coat of coal tar paint.

INSTALLATION

Roof Penetration Flashings:

All pipes, vents and flues passing through roofs shall be made waterproof with flashings of storm collars or counterflashings.

Roof penetration flashings shall be fabricated from galvanized sheet steel, not less than 24-gage. Size and shape shall be as shown on the plans.

On built-up roofing, 2 flashings shall be furnished for each pipe, vent or flue through roof. Flashings shall be constructed so that the lower flashing shall sit directly on the roof deck, with the top flashing set over it on top of the roof felts.

The lower flashing shall be galvanized sheet metal, 24-gage, and extend 6 inches minimum from outside of the pipe in all directions and 1½ inches above the top of the roofing.

The top flashing shall be galvanized sheet steel or sheet lead as shown on the plans.

Hung Gutters:

Hung gutters shall be fabricated from galvanized sheet steel, not less than 22 gage. Gutters shall be size and shape as shown on the plans.

Gutters shall be fabricated in sections not less than 10 feet in length. Use sections as long as practicable for lengths over 10 feet and where practical gutters shall be one piece for the full length of each roof.

Joints shall be lapped at least 1½ inches, rivet and solder watertight. Butt type expansion joints, ¾ inch wide, shall be provided at midpoint between down spouts and where expansion joints occur in the structure.

Downspouts:

Downspouts shall be fabricated from galvanized sheet steel, not less than 22 gage. Size and shape shall be as shown on the plans.

Downspouts shall be installed as shown on the plans, secured to the wall with straps near top, bottom and at intermediate points not more than 8 feet apart. Straps shall extend 2 inches out on wall and be secured with suitable anchors.

The lower end of downspout shall terminate with vertical discharge into drain.

Premolded Roof Flashings: Premolded roof flashings shall be installed in accordance with the manufacturer's instructions.

Roof Edging: Pre-engineered factory fabricated roof edging shall comply with ANSI/SPRI ES-1-98, of 22-gauge steel with powder coat finish and shall have 3 inch maximum face with drip and 4 inch maximum horizontal surface. Exterior and interior corners shall be factory fabricated and finished with each leg a minimum of 18 inches long. Joints shall be butt jointed with 12 inch long counter edging behind that shall maintain a true line and face for each section. All joints shall be water tight. Fasteners and installation shall be per manufactures standards for non exposed fastening and when completed shall be a water light installation.

After metal work is completed and watertight, flashings shall be covered by one of the following methods or as recommended by the roofing material manufacturer. Roofing manufacturer's recommendations shall take preference.

1. The top of the stop flanges and inside the upstanding lip at the joints shall be cleaned with an acid etching detergent, rinsed and dried. A ½-inch thick coat of plastic cement shall be applied on the roof flange and onto the roofing at least 4 inches wide. A ½-inch thick coat of plastic cement shall be applied 4 inches wide on the upstanding lip at the joints.
2. A hot mopping of roofing asphalt or a uniform coating of plastic cement shall be applied, over which shall be laid Type IV asphalt saturated felt strips, 10 inches and 13 inches wide, in 2 layers over the flange of the stops feathered out onto the roofing.

12-7.07 SKYLIGHTS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing tubular skylights in accordance with the details shown on the plans and these special provisions.

SYSTEM DESCRIPTION

Design Requirements:

Skylights shall conform to the requirements on Section 2603.7 of the CBC.

Air Infiltration Test: Air infiltration will not exceed 0.30 cfm/sf aperture with a pressure delta of 1.57 psf across the tube when tested in accordance with ASTM E 283.

Water Resistance Test: No uncontrolled water leakage at 16.5 psf pressure differential when tested in accordance with ASTM E 331.

Uniform Load Test: No breakage, permanent damage to fasteners, hardware parts, or damage to make tubular skylight inoperable, or cause permanent deflection of any section in excess of 1 percent of its span at either a maximum Positive or Negative Load of 100 psf for 14 inch dia unit.

SUBMITTALS

Product Data: Manufacturer's descriptive data and installation instructions shall be submitted for approval.

Samples: A sample of the acrylic or fiberglass plastic and the anodized framing shall be submitted for approval.

QUALITY ASSURANCE

Certificates of Compliance: Certificates of compliance shall be furnished for the skylights in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

PART 2 - PRODUCTS

Skylight:

Skylight shall consist of transparent roof-mounted skylight dome and self-flashing curb, reflective tube, and ceiling level diffuser assembly, transferring sunlight to interior spaces; complying with ICBO/ICC AS-16. All components shall be made and assembled by one manufacturer.

Accessories:

- A. Fasteners: Fasteners shall be same material as metals being fastened, non-magnetic steel, non-corrosive metal of type recommended by manufacturer, or injection molded nylon.
- B. Sealant: Sealant shall be polyurethane or copolymer based elastomeric sealant as provided or recommended by manufacturer.

Skylight shall be: Solatube (14 inch dia.); Sun-tek; or equal.

PART 3 - EXECUTION

Installation: Skylights shall be installed rigidly and securely in accordance with the manufacturer's details and instructions. The installation shall be flashed and shall be weathertight.

Cleaning and Protection: Plastic skylight units shall be cleaned and polished inside and out.

12-7.08 SEALANTS AND CAULKING

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and applying sealants and caulking which are required for this project, but not specified elsewhere, in accordance with the details shown on the plans and these special provisions.

Related Work: Pourable polyurethane joint sealant shall conform to the requirements under "Joint Sealant" elsewhere in this Section 12-7.

QUALITY ASSURANCE

Certificates of Compliance: Certificates of compliance shall be furnished for the sealants and caulking in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

SUBMITTALS

Product Data: Manufacturer's descriptive data and installation instructions for all sealants shall be submitted for approval.

Samples: Color samples of all sealants shall be submitted for approval. Unless otherwise shown on the plans, colors will be selected by the Engineer from the manufacturer's standard colors.

PART 2 - PRODUCTS

MATERIALS

All sealants, primers and accessories shall be non-staining to adjacent exposed surfaces. Products having similar applications and usage shall be of the same type and same manufacturer. Gun consistency compound shall be used unless otherwise required by the job conditions.

Acrylic Sealant: Acrylic sealant shall be one compound, solvent release acrylic sealant.

Butyl Sealant: Butyl sealant shall be one component, skinning type.

Silicone Sealant: Silicone sealant shall be one component, low modulus building sealant. Sealant shall be tack-free in one hour, shall not sag or flow, shall be ozone resistant and capable of 100 percent extension without failure.

Joint Sealant: Joint sealant shall be a two-part, non sag polysulfide base, synthetic rubber sealant formulated from liquid polysulfide polymer.

Backer Rod: Backer rod shall be round, open or closed cell polyurethane. Backer rod shall be sized such that it must be compressed between 25 percent and 75 percent of its uncompressed diameter during installation in the joint.

Neoprene: Neoprene shall conform to the requirements of ASTM Designation: C 542.

PART 3 - EXECUTION

APPLICATION

Unless otherwise shown on the plans, sealants shall be applied in accordance with the manufacturer's instructions.

Silicone sealants shall not be used in locations where painting is required.

Butyl sealants shall not be used in exterior applications, and acrylic sealants shall not be used in interior applications.

Sealants shall be applied in a continuous operation for the full length of the joint. Immediately following the application of the sealant, the sealant shall be tooled smooth using a tool similar to that used to produce concave masonry joints. Following tooling, the sealant shall remain undisturbed for not less than 48 hours.

12-7.09 RETAINING WALL DRAINAGE SYSTEM

Geocomposite Drain

Geocomposite drain shall consist of a manufactured core not less than 0.25 inch thick nor more than 2 inches thick with one or both sides covered with a layer of filter fabric that will provide a drainage void. The drain shall produce a flow rate through the drainage void of at least 2 gallons per minute per foot of width at a hydraulic gradient of 1.0 and a minimum externally applied pressure of 3,500 psf.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for the geocomposite drain certifying that the drain complies with these special provisions. The Certificate of Compliance shall be accompanied by a flow capability graph for the geocomposite drain showing flow rates and the externally applied pressures and hydraulic gradients. The flow capability graph shall be stamped with the verification of an independent testing laboratory.

Filter fabric for the geocomposite drain shall conform to the provisions for filter fabric for underdrains in Section 88, "Engineering Fabrics," of the Standard Specifications.

The manufactured core shall be either a preformed grid of embossed plastic, a mat of random shapes of plastic fibers, a drainage net consisting of a uniform pattern of polymeric strands forming 2 sets of continuous flow channels, or a system of plastic pillars and interconnections forming a semirigid mat.

The core material and filter fabric shall be capable of maintaining the drainage void for the entire height of geocomposite drain. Filter fabric shall be integrally bonded to the side of the core material with the drainage void. Core material manufactured from impermeable plastic sheeting having non-connecting corrugations shall be placed with the corrugations approximately perpendicular to the drainage collection system.

The geocomposite drain shall be installed with the drainage void and the filter fabric facing the embankment. The fabric facing the embankment side shall overlap a minimum of 3 inches at all joints and wrap around the exterior edges a minimum of 3 inches beyond the exterior edge. If additional fabric is needed to provide overlap at joints and wraparound at edges, the added fabric shall overlap the fabric on the geocomposite drain at least 6 inches and be attached thereto.

Should the fabric on the geocomposite drain be torn or punctured, the damaged section shall be replaced completely or repaired by placing a piece of fabric that is large enough to cover the damaged area and provide a 6-inch overlap.

Plastic Pipe

Plastic pipe shall conform to the provisions for pipe for edge drains and edge drain outlets in Section 68-3, "Edge Drains," of the Standard Specifications.

SECTION 12-8. DOORS AND WINDOWS

12-8.01 HINGED DOORS

PART 1 – GENERAL

Scope: This work shall consist of furnishing and installing hinged doors and frames in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Manufacturer's descriptive data, installation instructions for fire rated assemblies and a door schedule shall be submitted for approval. The door schedule shall include a description of the type, location and size of each door and frame.

PART 2 - PRODUCTS

Metal Door:

Metal door shall be flush, seamless steel door factory prepared and reinforced to receive hardware and having cold rolled stretcher leveled sheet steel face sheets not less than 0.060 inch thick (16 gage). Face sheets shall be bonded with thermosetting adhesive to rigid board honeycomb or precured foam core; or face sheets shall be welded to all parts of an assembled grid of cold formed pressed metal stiffeners and framing members located around edges, ends, openings and at all locations necessary to prevent buckling of face sheets. Seams shall be tack welded, filled and ground smooth. Bottom edge and internal stiffeners of grid type core shall have moisture vents. Welds on exposed surfaces shall be ground smooth. Louvered or glazed openings shall be provided where shown on the plans.

Active leaf of double door shall have a full height astragal of 1/8-inch flat bar or folded sheet strip, not less than 0.060 inch thick (16-gage), welded on the outside of the active leaf.

Hollow Metal Doors: Hollow metal doors shall be 16 gauge, flush seamless panel, factory primed and prepped for hardware and shall be manufactured by: Steelcraft (CE16 Series); Ceco Door Products; Republic Builders Products; or equal.

Bullet Resistant Metal Doors: Bullet resistant metal doors shall be UL 752 level 3 bullet resistant, ballistic capture aluminum frame, 16 gauge flush seamless to match metal doors, factory primed and prepped for hardware, and shall be manufactured by: Armortex; Bullet Guard; Ambico Limited; or equal.

Door shall be cleaned and treated by the bonderized process or approved phosphatizing process and then given one factory application of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Door Louvers: Door louvers shall be inverted V-type factory primed, galvanized sheet steel louvers. Exterior door louvers shall not be removable from outside of the building. Louvers at exterior doors shall have inside mounted bronze insect screens.

Louvers shall be cleaned and treated by the bonderized process or approved phosphatizing process and then given one factory application of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Pressed Metal Frame:

Pressed metal frame shall be not less than 0.060-inch thick (16-gage) sheet steel with integral stop, mitered corners, face welded and ground smooth corners. Frames shall be reinforced for all hardware and shall be cleaned and treated by the bonderized process or an approved phosphatizing process and then given one factory application of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Sealants: Sealants shall be ultraviolet and ozone resistant, gun grade polysulfide or polyurethane, multicomponent, Federal Specification: TT-S-227.

PART 3 - EXECUTION

INSTALLATION

Doors and frames shall be installed rigidly, securely, plumb and true and in such a manner that the doors operate freely without rubbing or binding. Clearance between frame and door shall be not more than 1/8 inch. The exterior frame shall be sealed weathertight.

Pressed metal frames shall be secured with clips and anchors as shown on the plans.

Painting: Except for the primer application specified herein, doors and frames shall be cleaned, prepared and painted in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

12-8.02 WINDOWS

PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing windows in accordance with the details shown on the plans and these special provisions.

Windows shall be commercial (C) grade aluminum prime windows unless otherwise shown on the plans.

Windows shall meet the requirement of NAFS-1, "Voluntary Performance Specification for Windows, Skylights, and Glass Doors," and shall meet the C30 (Commercial) product designation unless otherwise shown on the plans. Windows shall be labeled with the AAMA label.

Finish for windows shall be Architectural Class I, powder coat paint finish meeting American Architectural Manufacturer's Association Standard 611 unless otherwise shown on the plans.

Glazing for windows shall be in accordance with the requirements specified under "Glazing" in Section 12-8, "Doors and Windows," of these special provisions.

Certificates of Compliance: Certificates of compliance shall be furnished for all windows in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

SUMITTALS

Manufacturer's descriptive data, installation instructions and schedule shall be submitted for approval.

Manufacturer's descriptive data and installation instructions shall show window elevations, plan views, full size sections, anchoring details to all substrates, anchors and hardware.

Installation schedule shall show location, size and type for each window.

Three samples of a window frame section with powder coat finish shall be submitted for approval.

PART 2 - PRODUCTS

Fixed Windows: Fixed windows shall be non-operable glazed panel inserted into a frame to include muntins, glazing stops, and glazing accessories.

Bullet Resistant Windows: Frames shall have UL listed bullet resistant fiberglass to provide level 3 bullet resistant ballistic capture to the complete frame and shall be manufactured by: Amorex; Bullet Guard; Ambico Ltd; or equal.

Aluminum: Aluminum shall be extruded 6063-T5 aluminum alloy.

Screws, Fasteners and Window Accessories: Screws, fasteners and window accessories shall be non-corrosive metals compatible with aluminum except guides and rollers may be vinyl and nylon respectively. Finish for locks, operators, strikes, keepers and other metal hardware shall match window finish.

Weatherstripping: Weatherstripping shall be continuous, replaceable type, wool pile mounted in metal or double runs of ultraviolet resistant neoprene or vinyl.

Vent Screen: Vent screen shall be aluminum frame with 18 x 14 mesh aluminum screening and polyvinyl-chloride splines. Screen frames shall be removable from interior of building. Finish of screen frame shall match window finish.

Sealant: Sealant shall be single-component, solvent type acrylic, self-leveling, non-sag, conforming to Federal Specification: TT-S-230.

Tape: Tape shall be compatible with sealant; Pecora, "B-44 Extra-Seal;" Pittsburg Plate Glass, "Duribbon;" Protective Treatment, "PTU 606;" Tremco, "440 Tape;" or equal.

PART 3 - EXECUTION

FABRICATION

Frame and sash shall be accurately machined and fitted to hairline joinery that develops the members. Joints shall be factory sealed weathertight.

Inward opening vents without roto-type operators shall be provided with adjustable sliding friction type hold-open assemblies.

Sash shall be removable from the interior only. Sash shall have concealed condensation weeps to the outside.

DELIVERY AND STORAGE

Windows shall be delivered in original, unopened, unbroken containers, wrappings, or bags with labels bearing the brand name, name of manufacturer or supplier, standard of manufacture, and product description.

Windows and accessories shall be stored off the ground, kept dry, fully protected from weather and damage.

INSTALLATION

Window units shall be set straight, level, plumb and in true alignment in prepared openings. Windows shall be centered in openings. Clearance between the window unit and the building framing shall be from 3/16 inch to ¼ inch at the sides and ½ inch at the top. Ventilator sash shall be adjusted after glazing for easy, smooth and proper operation.

The installation shall be flashed and sealed weathertight.

All aluminum surfaces in contact with masonry, steel or other incompatible materials shall be isolated with pressure sensitive tape, zinc chromate primer, bituminous paint or such other material recommended by the window manufacturer and approved by the Engineer.

12-8.03 FINISH HARDWARE

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing hardware items for doors in accordance with the details shown on the plans and these special provisions.

Hardware for special doors and frames, if required, shall be as specified under "Hinged Doors" in Section 12-8 "Doors and Windows," of these special provisions.

Hardware assemblies shall comply with the fire code and the disabled accessibility requirements indicated on the plans and specified in these special provisions.

SUBMITTALS

Manufacturer's technical information and catalog cuts for each item of door hardware and a door hardware schedule shall be submitted for approval prior to installation.

Manufacturer's catalog cuts shall include catalog numbers, material, grade, type, size, function, design, quality and finish of hardware.

The door hardware schedule shall indicate the location and size of door opening, the door and frame material, and the size, style, finish and quantity of the hardware components required.

FINISHES

Hardware shall be provided with standard US 26D metal plated finish or aluminum finish where indicated.

KEYING INSTRUCTIONS

New facilities shall have a building master key system established.

Locks shall have cylinders with figure eight interchangeable cores with six pin barrels. Permanent cores and keys shall be delivered to the Engineer for final installation at completion of project.

The Contractor shall also provide figure eight interchangeable cores for use during construction which shall remain the property of the State.

Key bows shall be stamped "State of California" and "Do Not Duplicate."

PART 2 - PRODUCTS

GENERAL

Door hardware equal in material, grade, type, size, function, design, quality and manufacture to that specified herein may be submitted for approval.

Rotary Hinges:

Rotary hinges shall be continuous geared aluminum heavy duty hinge for the full height of the door, edge mounted with double row of screws and shall conform to BHMA Standard ANSI / BHMA A 156.26-2000 for Cycle Requirements.

Standard weight hinges shall be rotary type, full door length, satin nickel finish:

Hager	ROTON 1200
McKinney	MCK-FM 3700
Stanley	664 HD
or equal.	

Cylindrical Locksets, Latchsets and Privacy Sets:

Cylindrical locksets, latchsets and privacy sets shall be steel chassis, 2 1/8-inch diameter, 2 3/4-inch backset. Door and frame preparation for cylindrical lockset, latchsets and privacy sets shall conform to ANSI A115.1.

Door hardware: ADA approved, lever type, satin chrome finish (626) shall be:

Schlage	("Rhodes", D Series, D80PD, D40S, D10S With B464P deadbolt)
Marks or equal.	

Cylindrical Dead Locks:

Cylindrical dead locks shall have one-inch throw bolt with concealed hardened steel inserts and one-inch diameter bolt housing, 2 3/4-inch backset.

Single cylinder dead lock with inside thumb turn shall be:

Schlage	B464PB660
Ingersol Rand or equal.	

Flush Bolts:

Flush bolts shall be installed at the top and bottom of the inactive leaf of pairs of doors. Provide automatic bolts on UL rated pairs of doors.

Flush bolts for manual operation shall be:

Trimco	3915
Glynn Johnson	FB6
H.B. Ives	457
or equal.	

Door Closers:

Parallel arms for closers shall be installed at outswing exterior doors. Closers shall have sprayed finish to match other hardware on door.

Door closers shall be:

LCN 111
Norton 3501-BF
or equal.

Kickplates:

Kickplates shall be 10 inches in height x 2 inches less than door width x 16-gage.

Kickplates shall be:

Hager 1985
Schlage
or equal.

Wall Bumpers:

Wall bumpers base diameter shall be 2½ inches with a one-inch projection.

Bumpers shall be:

Hager
Trimco 1270 CXMS
or equal.

Threshold Bedding Sealant: Threshold bedding sealant shall conform to Federal Specification: SS-C-153.

Weatherstrip:

Weatherstrip shall conform to the sizes and shapes shown on plans. Assemblies shall be UL listed and shall be provided where shown on the plans or as specified in these special provisions.

Weatherstrip manufacturers shall be Pemko (PK33D), Hagar or equal.

Door Signs and Name Plates: Door signs and name plates shall be as specified under "Signs" in Section 12-10, "Specialties," of these special provisions.

PART 3 - EXECUTION

Doors and Frames: Doors and frames shall be set square and plumb and be properly prepared before the installation of hardware.

INSTALLATION

Hardware items shall be accurately fitted, securely applied, and adjusted and lubricated in accordance with the manufacturer's instructions. Installation shall provide proper operation without bind or excessive play.

Hinges shall be installed with the ends of hinges not more 9 5/8 inches from the top and bottom of the door. Locksets, latchsets, privacy sets shall be 40 5/16 inches from the finished floor. Kickplates shall be mounted on the push side of the doors, one inch clear of door edges.

Thresholds shall be set in a continuous bed of sealant material.

Door controls shall be set so that the effort required to operate doors with closers shall not exceed 5 pounds maximum for exterior doors and interior doors.

Door stops located on concrete surfaces shall be fastened rigidly and securely in place with expansion anchoring devices.

The location and inscriptions for door signs and name plates shall be as shown on the plans.

Hardware, except hinges, shall be removed from surfaces to be painted before painting.

Upon completion of installation and adjustment, the Contractor shall deliver to the Engineer all dogging keys, closer valve keys, lock spanner wrenches, and other factory furnished installation aids, instructions and maintenance guides.

DOOR HARDWARE GROUPS AND SCHEDULE

Hardware groups specified herein shall correspond to those shown on the plans:

GROUP 1 (Doors 21)

- 1 1/2-pair hinges
- 1 each Lockset
- 1 each Closer
- 1 each Threshold
- 1 each Weather Stripping
- 1 each Door Stop
- 2 each Kickplate, each side.

GROUP 2 (Doors 22)

- 1 1/2-pair hinge
- 1 each Privacy latchset
- 1 each door stop

GROUP 3 (Doors 2,11,13,14,17,18,19,23)

- 1 1/2-pair Hinge
- 1 each Closer
- 1 each Dead bolt
- 1 each Latchset
- 1 each Threshold
- 1 each Weather stripping
- 1 each Door Stop
- 1 each Kick plate, each side

GROUP 4 (Doors 1,16)

- 3-pair Hinge
- 1 each Lockset
- 1 each Closer
- 1 each Threshold
- 2 each Weather stripping
- 2 each Door Stop
- 4 each Kick Plate, each side of door
- 1 each Astragal
- 2 Flush Bolts, (top and bottom of passive door)

GROUP 5 (Doors 3,4,12,15,20,24)

- 1 1/2-pair hinge
- 1 each Privacy latchset
- 1 each door stop
- 2 each kick plate, each side of door.

12-8.04 GLAZING

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing glazing in accordance with the details shown on the plans and these special provisions.

Glazing shall consist of glass and acrylic sheets for windows, doors and other glazed openings.

All glass shall conform to ASTM Designation: C 1036 and the classifications specified herein and shall be clear glass except as noted.

All acrylic sheets shall conform to ASTM Designation: D 702, Type III, Grade 3.

Safety glass shall be furnished and installed at all locations designated in Consumer Product Safety Commission's Safety Standard For Architectural Glazing Materials 16 CFR 1201.

SUBMITTALS

A detailed list of glazing materials including glass, sheet, sealants, tapes, setting blocks, shims, compression seals, and glazing channels shall be submitted for approval. The list shall include a schedule of the materials to be used at each location.

LABELS

Each individual pane of heat strengthened or fully tempered glass shall bear an identification label in accordance with ASTM Designation: C 1048.

PART 2 - PRODUCTS

Sheet Glass, Float Glass, or Plate Glass: Sheet glass, float glass, or plate glass shall be Type I, Class 1, Quality q4 or better, double strength for panes to 10 square feet, 3/16 inch thick for panes between 10 and 28 square feet, and ¼ inch thick for panes over 28 square feet, except as otherwise shown on the plans.

Laminated Glass: Laminated glass shall be safety glass, ¼-inch minimum thickness, fabricated from 2 pieces of Type I, Class 1, Quality q4 or better glass fused to plastic interlayers.

Bullet Resistant Glass: Bullet resistant glass shall be multiple laminated glass fused to poly carbonate plastic interlayers; one inch minimum thickness; UL 752 rated for level 3 medium power small arms.

Tinted Glass: Tinted glass shall be bronze; all the same tint.

Insulating Glass Assemblies: Insulating glass assemblies shall be double pane units consisting of 2 pieces of glass separated by a spacer and hermetically sealed with double seal sealants. The entrapped air shall be at atmospheric pressure and maintained in a hydrated condition by a drying agent located in the spacer.

Seals, Caulks, Putties, Setting Blocks, Shims, Tapes, Compression Seals, Felt, Spacers, and Channels: Seals, caulks, putties, setting blocks, shims, tapes, compression seals, felt, spacers, and channels shall be top grade, commercial quality, as recommended by the glass or sheet manufacturer and shall conform to the requirements in the publications of the Flat Glass Marketing Association.

PART 3 - EXECUTION

INSTALLATION

Glazing shall conform to the general conditions and applicable details in the publications of the Flat Glass Marketing Association.

Cut edges of tinted glass shall conform to the recommendations of the glass manufacturer. The glazier shall inspect each edge of tinted glass. Panes with edges that do not conform to the manufacturer's standards for tinted glass edges for sunny elevations shall not be used.

Panes shall be bedded fully and evenly, set straight and square within panels in such a manner that the pane is entirely free of any contact with metal edges and surfaces.

For all panes on the exterior of the building, the glazing on both sides of window panes shall provide a watertight seal and watershed. Seals shall extend not more than 1/16 inch beyond the holding members. A void shall be left between the vertical edges of the panes and the glazing channel. Weep systems shall be provided to drain condensation to the outside.

Panes in assemblies using extruded gasket glazing shall be set in accordance with the assembly manufacturer's instructions using gaskets and stops supplied by the manufacturer.

Laminated glass shall be set on setting blocks.

Whenever welding or burning of metal is in progress within 15 feet of glazing materials, a protective cover shall be provided over exposed surfaces.

REPLACEMENT AND CLEANING

All broken or cracked glass and glass with scratches which reduce the strength shall be replaced before completion of the project.

Panes shall be kept clean of cement and plaster products, cleansers, sealants, tapes and all other foreign material that may cause discoloration, etching, staining, or surface blemishes to the materials.

Excess sealant left on the surface of the glass or surrounding materials shall be removed during the work life of the sealant.

Solvents and cleaning compounds shall be chemically compatible with materials, coatings and glazing compounds to remain. Cleaners shall not have abrasives that scratch or mar the surfaces.

The protective covering on acrylic sheet surfaces shall be left until construction is completed or 2 weeks after glazing, whichever is shorter. The covering shall be removed before adhesives dry sufficiently to adhere to the sheet during removal rather than the protective membrane.

Acrylic sheets shall be protected against scuffs, scratches and marring of the surface during construction and any such damaged sheet shall be replaced or restored to like new condition. Restoration work shall conform to the manufacturer's recommendations.

All panes shall be cleaned just before the final inspection. All stains and defects shall be removed. Paint, dirt, stains, labels (except etched labels), and surplus glazing compound shall be removed without scratching or marring the surface of the panes or metal work.

SECTION 12-9. FINISHES

12-9.01 CERAMIC TILE

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing ceramic and quarry tile in accordance with the details shown on the plans and these special provisions.

Ceramic tile shall include glazed wall tile, patterned porcelain tile, matte porcelain tile, textured porcelain tile, polished porcelain tile, trim tile, setting materials, grouts and such other materials as may be required for a complete installation.

SUBMITTALS

Product Data:

Manufacturer's descriptive data, a list of materials to be used, and installation instructions for all materials required for the work shall be submitted for approval.

Manufacturer's descriptive data shall be submitted for each type of tile, mortar bed materials, bond coat materials and additives, and grout materials and additives.

Materials list and installation instructions shall include all products and materials to be incorporated into the work.

Friction reports shall be submitted for tile products to be used on floors and other pedestrian surfaces.

Samples: Samples shall include 2 individual samples of each type and color of tile and trim to be installed and shall be of the same size, shape, pattern and finish as the tile and trim to be installed.

QUALITY ASSURANCE

Single Source Responsibility: Each type and color of tile, grout and setting materials shall be obtained from a single source.

Master Grade Certificates: Each shipment of tile to the project site shall be accompanied by a Master Grade Certificate issued by the tile manufacturer.

Certificates of Compliance: Certificates of compliance shall be furnished for bond coat materials, setting bed materials and grout in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

DELIVERY, STORAGE AND HANDLING

Delivery: Tile and packaged materials shall be delivered to the job site in sealed, unbroken, unopened containers with the labels intact. Tile containers shall bear the Standard Grade label.

Storage and Handling: Materials shall be stored and handled in such a manner as to prevent damage or contamination by water, freezing or foreign matter.

PROJECT CONDITIONS

Protection: Tile work shall be protected and environmental conditions maintained during and after installation to comply with the reference standards and manufacturer's printed instructions.

Temperatures:

Unless otherwise specified in the manufacturer's installation instructions, the ambient temperature shall be maintained at not less than 50°F nor more than 100°F in tiled areas during installation and for 7 days after completion. Exterior work areas shall be shaded from direct sunlight during installation.

Tile shall not be installed when the temperature of the substrate is greater than 90°F or is frost covered.

illumination: Interior work areas shall be illuminated to provide the same level and angle of illumination as will be available during final inspection.

PART 2 - PRODUCTS

MANUFACTURERS

Available Manufacturers: Subject to compliance with the specifications, tile shall be Daltile Products; Random Linear Brick Joint CY04; Summitville Tiles, Inc.; United States Ceramic Tile Co.; or equal.

GENERAL

Ceramic Tile:

Ceramic tile shall conform to the requirements in ANSI Standard: A137.1, "American National Standard Specifications for Ceramic Tile" for types and grades of tile indicated.

Ceramic tile shall conform to the "Standard Grade" requirements.

Tile Installation Materials: Tile installation materials shall conform to the requirements in ANSI standard referenced with products and materials indicated for setting and grouting.

Tile Color and Size: Tile color and size shall be as shown on the plans.

Slip Resistant Tile: Slip resistant tile shall have sufficient abrasives added such that the static coefficient of friction, wet or dry, shall be not less than 0.6 for walking surfaces and 0.8 for ramps when tested in accordance with ASTM Designation: C 1028.

TILE PRODUCTS

Matte Porcelain Floor Tile:

Matte porcelain floor tile shall be machine made, unpolished, dust pressed natural porcelain clay and shall have a plain face. Tile shall have a nominal thickness of 5/16 inch. Matte porcelain tile shall be slip resistant.

Matte porcelain trim tile shall include cove type base at walls and single piece intersecting cove base at corners.

Textured Porcelain Wall Tile: Textured porcelain wall tile shall be machine made, unpolished, dust pressed natural porcelain clay. Tile shall have less than 0.5 percent water retention and be suitable for exterior use. Tiles shall have a nominal thickness of 5/16 inch. Textured porcelain tile shall be slip resistant.

SETTING MATERIALS

Tile Bond Coat:

Tile bond coat shall be latex-portland cement bond coat. TAC (Tile Council of America) method.

Latex-portland cement mortar bond coat shall be a prepackaged mortar mix, conforming to ANSI Standard: A118.4, incorporating a dry acrylic resin, and to which only water is added at the job site. Mortar shall be suitable for exterior use and be labeled for the type of tile to be installed.

GROUTING MATERIALS

Epoxy Grout: Epoxy grout shall be a 2 part prepackaged epoxy grout conforming to ANSI Standard: A118.3 and suitable for exterior use. Grout shall be labeled for the type of tile to be used.

Tile grout shall be 100% solids epoxy and manufactured by Custom Building Products, Color Fast Industries, Laticrete or equal.

Grout Pigment: Grout pigment shall be chemically inert, fade resistant mineral oxide or synthetic type. Color shall be as shown on the plans.

SEALANTS

Sealant:

Sealant for vertical expansion joints shall be a medium modulus silicone or polyurethane. Sealant for horizontal joints shall be a 2-part polyurethane type material with a Shore Hardness of 35 to 45.

Color of exposed sealants shall match color of grout in tile adjoining sealed joints.

MISCELLANEOUS MATERIALS

Sand: Sand shall be a natural or manufactured sand conforming to ASTM Designation: C 144, except that no more than 10 percent shall pass the No. 100 sieve.

Sealers:

Sealer for unglazed quarry tile shall be water repellent, clear solution of ammonium cementitious compound, silicone base material, or other commercially manufactured sealer.

Sealer for grout shall be a penetrating proprietary compound designed for sealing grout. Silicone sealers shall not be used.

Cement: Cement shall conform to ASTM Designation: C 150, Type I.

Hydrated Lime: Hydrated lime shall conform to ASTM Designation: C 206, Type S, or ASTM Designation: C 207, Type S.

Water: Water shall be clean and potable.

MIXING MORTAR AND GROUT

Mixing: Mortar and grout shall be mixed to comply with the requirements of referenced standards and manufacturers for accurately proportioning of materials, water or additive content, mixing equipment and mixer speeds, mixing containers, mixing time, and other procedures need to produce mortars and grout of uniform quality with optimum performance characteristics for application intended.

PART 3 - EXECUTION

PREPARATION

Concrete, mortar, or masonry substrate surfaces which are to receive a mortar bed shall not vary more than ¼ inch in 8 feet from the required plane and shall be true, plumb at vertical surfaces, and square at intersection edges.

Surfaces to receive a tile bond coat shall be cleaned adequately to assure a tight bond to the applied material. Such cleaning shall leave the surface thoroughly roughened and free from laitance, coatings, oil, sand, dust and loose particles.

Substrates shall be inspected to insure that grounds, anchors, plugs, recessed frames, bucks, drains, electrical work, mechanical work, and similar items in or behind the tile have been installed before proceeding with installation of the tiles.

INSTALLATION

Tile installation shall conform to applicable parts of ANSI 108 Series of the tile installation standards included under "American National Standard Specifications for the Installation of Ceramic Tile" and Tile Council of American, "Handbook for Ceramic Tile Installation."

All tile shall be installed on a bond coat using the TAC method W202-03. The setting bed shall be a prepared, dimensionally stable substrate of concrete or concrete masonry.

The back face of the tile shall be free of paper, adhesives, fiber mesh, resins, or other materials affecting the bond of the tile to the bedding material.

Tile sheets shall have permanent edge bonding or temporary mounting materials on the exposed face. Water soluble or absorbent adhesives shall not be used for edge bonding. Temporary mounting materials shall allow observation during tile setting operations.

Tile work shall extend into recesses and under or behind equipment and fixtures, to form a complete covering without interruptions, except as shown on the plans. Work shall be terminated neatly at obstructions, edges and corners without disrupting pattern or joint alignments.

Intersections and returns shall be accurately formed. Cutting and drilling of tile shall be performed without marring visible surfaces. Cut edges of tile abutting trim, finish or built-in items shall be carefully ground to produce straight aligned joints. Tile shall be closely fit to electrical outlets, piping, fixtures and other penetrations such that plates, collars, or covers overlap the tile.

Tile Bond Coat:

The tile bond coat mortar shall be mixed according to the manufacturer's recommendations. The consistency of the mixture shall be such that ridges formed with the recommended notched trowel shall not flow or slump. Reworking will be allowed provided no water or materials are added. The setting bed surfaces shall be dampened before placing the bond coat as necessary for tile installation, but the setting bed shall not be soaked. The setting bed surfaces for epoxy bond coat shall be dry.

The bond coat shall be floated onto the concrete or concrete masonry surface with sufficient pressure to cover the surface evenly with no bare spots. The surface area to be covered with the bond coat shall be no greater than the area that can be tiled while the bond coat is still plastic. The bond coat shall be combed with a notched trowel as recommended by the manufacturer within 10 minutes before installing tile. Tile shall not be installed on a skinned over bond coat.

Installing Tiles:

Tile shall be installed in accordance with the manufacturer's instructions and shall be set solid and shall be well bonded to the substrate.

Tile set on a tile bond coat shall be installed in accordance with ANSI Standard: A118.6

If tiles are cut, the cuts shall be made with saws. Cut edges shall be rubbed with an abrasive stone to bring the edge of the glaze slightly back from the body of the tile. Cuts shall be accurately made to neatly fit the tile in place. Cut edges shall not be butted against other tile. Cut tile shall be at least half the size of a full size tile.

Tile shall completely cover wall areas behind mirrors and fixtures.

Tile shall be installed so that the finished tile surface does not vary more than 1/8 inch in 8 feet from the finished tile surface shown on the plans. In no case shall there be offsets in adjoining tiles, low spots on finished tile surfaces that can pond water, or finished tile surfaces that are not plumb or true in the completed tile work.

Tiles shall be firmly pressed into the freshly notched bond coat. Tile on interior surfaces shall be tapped and beat into a true surface and to obtain at least 80 percent coverage by the mortar on the back of each tile. Tile on exterior surfaces shall have 100 percent coverage and shall be back-buttered immediately prior to setting the tile.

If tile is face mounted, the paper and glue shall be removed within one hour after tile is installed and all tiles that do not meet the requirements for joints and surface tolerance shall be adjusted or replaced.

Mortar that exudes into the grout spaces between tiles shall be removed to the bottom of tile.

Joints: Joints between tile shall be continuous both vertically and horizontally. Joints shall be straight and of uniform and equal width. Where tiles on adjoining surface are the same size, the joints shall align, one with the other. Joint width shall be as recommended by the tile manufacturer.

Grouting Tile:

Grout shall be mixed, applied and cured in accordance with the manufacturer's recommendations and ANSI Standard: A108.10 for cement grout and ANSI Standard: A108.9 for epoxy grout.

Spacers, strings, ropes, pegs, glue, paper, and face mounting material shall be removed before grouting. Joints between glazed wall tile shall be wetted if they have become dry. Joints for epoxy mortar shall be dry.

Grouting shall not begin until at least 48 hours after installing tile.

A maximum amount of grout shall be forced into the joints between tiles in accordance with the manufacturer's recommendations. The grout shall be finished to the depth of the cushion for cushion edge tile and finished flush with the surface for square edge tile. All gaps and skips in the grout spaces shall be filled.

Mortar or mounting mesh shall not show through the grouted joints.

The finished grout shall have a uniform color and shall be smooth without voids, pinholes or low spots.

Expansion joints shall be kept free of grout or mortar.

Grout shall be protected from freezing or frost for a least 5 days after installation.

Expansion Joints:

Expansion joints shall be installed at the perimeter of all tile floors and at all substrate control joints and changes in the substrate material. Exterior expansion joint spacing shall not exceed 16 feet in any direction.

All expansion joints shall be made with sealant over backer rods. The thickness of sealant at the center of expansion joints shall not exceed the width of the joint. Joint edges shall be primed as recommended by the sealant manufacturer.

Sounding Tile: Tiled surfaces shall be sounded with a metal bar or chain for improperly bonded tile or setting bed. Tile or setting bed that emits a hollow sound shall be replaced.

Replacement: Cracked, chipped, broken, or otherwise defective tiles shall be removed and replaced. All tiles which differ more than 1/16 inch in elevation from adjacent tile edges shall be removed and replaced.

Curing:

After the installation of tile and the grouting of joints, the tile and grout shall be cured by keeping the surface continuously damp for at least 72 hours after grouting. Curing materials shall not stain the tile or grouted joints. Curing methods shall not erode away the grout.

After grouting, horizontal tiled surfaces shall be closed to traffic, and all tiled surfaces shall be kept free from impact, vibration or shock, for at least 72 hours.

CLEANING AND PROTECTION

Cleaning Tile Surfaces:

All exposed tile surfaces shall be cleaned of all grout haze upon completion of grouting. Acids and chemicals used to clean tile shall conform to the tile manufacturer's recommendations. Cleaners shall not be harmful to materials on surfaces of abutting floors, walls, and ceilings. Tile work shall be rinsed thoroughly with clean water before and after using acid or chemical cleaners. After cleaning and rinsing, tile surfaces shall be polished using a soft cloth.

Tile work shall be cleaned and polished again immediately prior to completion of the contract. All dirt, grime, stains, paints, grease, and other discoloring agents or foreign materials shall be removed.

Protection:

After grouting, horizontal tiled surfaces shall be closed to traffic, and all tiled surfaces shall be kept free from impact, vibration or shock, for at least 72 hours after.

Tile surfaces damaged by construction operations shall be retiled.

SCHEDULES

Wall Tile:

Wall tile shall be nominal porcelain tile.

Installation on concrete and masonry shall be on a tile bond with grout, and shall conform to the requirements of Method W 202-03, "Handbook for Ceramic Tile Installation."

Floor Tile: Floor tile shall be nominal 12" x 12" matte porcelain tile installed on a tile bond coat with grout and shall conform to the requirements of Method , "Handbook for Ceramic Tile Installation."

Coved Base Tile: Coved base tile shall match floor tile and shall extend a minimum of 6 inches above the finished floor.

12-9.02 PAINTING

PART 1 - GENERAL

Scope: This work shall consist of preparing surfaces to receive coatings, and furnishing and applying coatings, in conformance with the schedules and details shown on the plans and these special provisions.

The coatings specified in this section are in addition to any factory finishes, shop priming, or surface treatment specified elsewhere in these special provisions.

DEFINITIONS

Detergent Wash: Removal of dirt and water-soluble chemicals by scrubbing with a solution of detergent and water, and removal of all solution and residues with clean water.

Hand Cleaning: Removal of dirt, loose rust, mill scale, excess base material, filler, aluminum oxide, chalking paint, peeling paint, or paint that is not firmly bonded to the surfaces by using hand or powered wire brushes, hand scraping tools, power grinders, or sandpaper and removal of all loose particles and dust prior to coating.

Mildew Wash: Removal of mildew by scrubbing with a solution of detergent, hypochlorite-type household bleach, and warm water, and removal of all solution and residues with clean water.

Abrasive Blasting:

Removal of loosely adhering paint, dirt, rust, mill scale, efflorescence, weak concrete, or laitance, shall be by the use of airborne abrasives. Loose particles, dust, and abrasives shall be removed by blasting with clean, oil-free air.

Abrasives shall be limited to mineral grit, steel grit, or steel shot, and shall be graded to produce the surface profile recommended in the manufacturer's data sheet.

Steam Cleaning: Removal of oil, grease, dirt, or other foreign matter by using steam generated by commercial steam cleaning equipment, from a solution of water and steam cleaning compounds, and removal of all residues and cleaning compounds with clean water.

TSP Wash: Removal of oil, grease, dirt, paint gloss, and other foreign matter by scrubbing with a solution of trisodium phosphate and warm water, and removal of all solution and residues with clean water.

Water Blasting: Removal of dirt, loose scale, chalking, or peeling paint by low-pressure water cleaning. Water blasting shall be performed in conformance with the requirements in SSPC-SP12 and shall produce a surface cleanliness meeting the requirements of SSPC-SP12-WJ4. Equipment used shall have a minimum flow rate of 1.5 GPM. If a detergent solution is used, it shall be biodegradable and shall be removed from all surfaces with clean water.

Protection:

The Contractor shall provide protective devices, such as tarps, screens or covers, as necessary to prevent damage to the work and to other property or persons from all cleaning and painting operations.

Paint or paint stains on surfaces not designated to be painted shall be removed by the Contractor at the Contractor's expense and the original surface shall be restored.

SUBMITTALS

Manufacturer's descriptive data, a materials list, and color samples shall be submitted for approval.

Product descriptive data shall include product description, manufacturer's recommendations for product mixing, thinning, tinting, handling, site environmental requirements, product application, and drying time.

Materials list shall include manufacturer's name, trade name, and product numbers for each type coating to be applied.

Color samples shall be manufacturer's color cards, approximately 2" x 3", for each color of coating shown on the plans.

QUALITY ASSURANCE

Certificates of Compliance: Certificates of Compliance shall be furnished when products are required to conform with the requirements of The Society for Protective Coatings (SSPC) in conformance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

REGULATORY REQUIREMENTS

Coatings and applications shall conform to the rules for control of Volatile Organic Compound (VOC) emissions adopted by the air quality control district in the air basin in which the coatings are applied.

SITE ENVIRONMENTAL REQUIREMENTS

Coatings shall be applied in conformance with the environmental constraints specified in the manufacturer's printed instructions. These conditions shall be maintained until the coating has cured and is ready for recoat.

Continuous ventilation shall be provided during application of the coatings.

Adequate lighting, as determined by the Engineer, shall be provided while surfaces are being prepared for coatings and during coating applications.

DELIVERY, STORAGE, AND HANDLING

Products shall be delivered to the site in sealed, labeled containers and stored in a well-ventilated area at an ambient air temperature of not less than 45°F. Container labeling shall include manufacturer's name, type of coating, trade name, color designation, drying time, and instructions for tinting, mixing, and thinning.

MAINTENANCE STOCK

Upon completion of coating work, a full one-gallon container of each type and color of finish coat and stain used shall be delivered to the location at the project site designated by the Engineer. Containers shall be tightly sealed and labeled with color, texture, and room locations where used, in addition to the manufacturer's standard product label.

PART 2 - PRODUCTS

Products for each coating system shall be from a single manufacturer and shall conform to the requirements in the Detailed Performance Standards of the Master Painters Institute (MPI). Each product shall be shown on the MPI Approved Products List unless otherwise specified in these special provisions.

PART 3 - EXECUTION

INSPECTION

Coatings shall not be applied until surface preparation has been approved by the Engineer. The Contractor shall notify the Engineer at least 3 working days prior to the application of coatings.

SURFACE PREPARATION

Surfaces scheduled to be coated shall be prepared in conformance with the coating manufacturer's printed instructions unless otherwise specified in these special provisions.

Hardware, cover plates, light fixture trim, and similar items shall be removed prior to preparing surfaces for coating. Following the application of the finish coating, the removed items shall be reinstalled in their original locations.

Galvanized Metal:

New surfaces shall be roughened by hand sanding or light abrasive blasting. Galvanizing shall not be removed during cleaning or roughening.

Damaged or corroded areas shall be cleaned and given 2 spot applications of a coating that conforms to the requirements in the Detailed Performance Standards of the MPI, and listed on MPI List "Number 18, Primer, Zinc Rich, Organic."

Steel and Other Ferrous Metals: Surface shall be cleaned in conformance with the requirements in SSPC-SP 1. Surface profile shall be as required for the coating system specified.

Aluminum and Other Non-ferrous Metals: Surface shall be cleaned in conformance with the requirements in SSPC-SP 1.

Concrete : New material shall be cleaned and prepared in conformance with the requirements in SSPC-SP 13. Cracks and voids shall be filled with cement mortar patching material. Concrete shall be cured until the surface moisture is below the level specified in the coating manufacturer's printed instructions.

Previously Coated Surfaces:

Dirt, oil, grease, or other surface contaminants shall be removed by water blasting, steam cleaning, or TSP wash. Minor surface imperfections shall be filled as required for new work. Mildew shall be removed by mildew wash. Chalking paint shall be removed by hand cleaning. The surfaces of existing hard or glossy coatings shall be abraded to dull the finish by hand cleaning or light abrasive blasting. Abrasive blasting shall not be used on wood or non-ferrous metal surfaces.

Chipped, peeling, blistered, or loose coatings shall be removed by hand cleaning, water blasting, or abrasive blasting. Bare areas shall be pretreated and primed as required for new work.

APPLICATION

Coatings shall be applied in conformance with the printed instructions and at the application rates recommended by the manufacturer to achieve the dry film thickness stated in the coating technical data sheet.

Mixing, thinning and tinting shall conform to the manufacturer's printed instructions. After thinning, the coating shall conform to the regulatory requirements in these special provisions.

Coatings shall be applied only when surfaces are dry and properly prepared.

Cleaning and painting shall be scheduled so that dust and other contaminants from the cleaning process will not fall on wet, newly coated surfaces.

Materials required to be coated shall have coatings applied to all exposed surfaces, including the tops and bottoms of wood and metal doors, the insides of cabinets, and other surfaces not normally visible from eye level.

Surface Finish Application:

Each coat shall be applied to a uniform finish. Finished surfaces shall be free of surface deviations and imperfections such as skips, cloudiness, spotting, holidays, laps, brush marks, runs, sags, curtains, ropiness, improper cutting in, overspray, drips, ridges, waves, and variations in color and texture.

Each application of a multiple application finish system shall closely resemble the final color coat, except each application shall provide enough contrast in shade to distinguish the separate applications.

Work Required Between Applications:

Each application of material shall be cured in conformance with the coating manufacturer's printed instructions before applying the succeeding coating.

Stain blocking primer shall be spot applied whenever bleeding substances are visible through the previous application of a coating.

Timing of Applications: The first application of the coating system shall be during the same work shift that the final surface preparation was performed. Additional coats shall be applied as soon as the required drying time of the preceding coat, specified in the coating manufacturer's printed instructions, has been met.

Application Methods:

Coatings shall be applied by brush, roller or spray. Rollers shall be of a type which do not leave a stippled texture in the paint film. Extension handles for rollers shall not be greater than 6 feet in length.

If spray methods are used, surface deviations and imperfections such as overspray, thickness deviations, lap marks, and orange peel shall be considered as evidence the work is unsatisfactory and the Contractor shall apply the remainder of the coating by brush or roller, as approved by the Engineer.

Patches in Previously Coated Surfaces: Where patches are made on surfaces of previously coated walls or ceilings, the entire surface to corners on every side of the patch shall be coated with a minimum of one application of the finish coat.

Finishing Mechanical and Electrical Components:

Shop primed mechanical and electrical components shall be finish coated in conformance with the coating system specified for the substrate material. Louvers, grilles, covers, and access panels on mechanical and electrical components shall be removed and coated separately.

Interior surfaces of air ducts which are visible through grilles or louvers shall be coated with one application of flat black enamel, to limit of the sight line.

Conduit, piping, and other mechanical and electrical components visible in the finished work shall be painted.

Both sides and all surfaces, including edges and back of wood mounting panels for electrical and telephone equipment shall be finish coated before installing equipment.

CLEANING

Upon completion of all operations, the coated surfaces shall be thoroughly cleaned of dust, dirt, grease, or other unsightly materials or substances.

Surfaces marred or damaged as a result of the Contractor's operations shall be repaired, at his expense, to match the condition of the surfaces prior to the beginning of the Contractor's operations.

COATING SYSTEM

The surfaces to be coated shall be as shown on the plans and as specified in these special provisions. When a coating system is not shown or specified for a surface to be finish coated, the coating system to be used shall be as specified below for the substrate material. The number of applications specified for each coating system listed herein is a minimum. Additional coats shall be applied if necessary to obtain a uniform color, texture, appearance, or required dry film thickness.

SYSTEM A - ALUMINUM AND OTHER NON-FERROUS METALS

(in pipe chases, CHP, and janitors storage only)

2 Finish Coats:

Semi-Gloss: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 5, MPI List Number 163

SYSTEM B -INTERIOR CONCRETE

2 Finish Coats:

Semi-Gloss: Latex, Exterior, MPI Gloss Level 5, MPI List Number 11

SYSTEM C- INTERIOR CONCRETE Anti-Graffiti

2 Base Coats:

Clear aliphatic polyurethane

1 Finish Coat:

Clear, nontoxic, sacrificial, nonflammable, water-based coating designed for protecting concrete from graffiti.

SYSTEM D- EXTERIOR CONCRETE Anti-Graffiti

1 Base Coat:

Clear silane and alkoxy silane micro-emulsifiable concentrate.

1 Finish Coat:

Clear, nontoxic, sacrificial, nonflammable, water-based coating designed for protecting concrete from graffiti.

SYSTEM E - PREVIOUSLY COATED INTERIOR SURFACES

2 Finish Coats:

Match Existing Finish.

Flat: Latex, Interior, MPI Gloss Level 1, MPI List Number 53

Eggshell-like: Latex, Interior, MPI Gloss Level 3, MPI List Number 52

Semi-Gloss: Latex, Interior, MPI Gloss Level 5, MPI List Number 54

Gloss: Latex, Interior, MPI Gloss Level 6, MPI List Number 114

SYSTEM F – STEEL, GALVANIZED METALS AND OTHER FERROUS METALS, NON-CORROSIVE ENVIRONMENT (ANTI-GRAFFITI)

1 Prime Coat: alkyd primer

2 Finish Coats: Polyester enamel.

COLOR SCHEDULE

Colors shall be as shown on the plans.

SECTION 12-10. SPECIALTIES

12-10.01 TACKBOARDS

PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing tackboards in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Manufacturer's descriptive data, color and texture samples and installation instructions shall be submitted for approval. Color and texture will be selected by the Engineer after the award of the contract.

PART 2 - PRODUCTS

Tackboards: Tackboards shall be textured plastic coating on cotton-fabric, pressure laminated to ¼-inch thick cork underlayment. Cork underlayment shall be bonded to a ¼-inch thick hardboard backing. Tackboard dimensions shall be 3 foot high by 4 foot wide.

Border Moldings: Border moldings shall be factory applied, extruded clear anodized aluminum trim.

PART 3 - EXECUTION

INSTALLATION

Tackboards shall be installed rigidly, securely, plumb and true, and in accordance with the manufacturer's recommendations for attaching to concrete.

12-10.02 METAL TOILET PARTITIONS

PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing metal toilet partitions in accordance with the details shown on the plans and these special provisions.

Metal toilet partitions shall consist of doors, pilasters, fasteners, anchorages and hardware. Internal reinforcement shall be provided at all fasteners, anchorages, hardware and accessories.

Doors, pilasters, shall have a factory applied, baked on enamel finish consisting of not less than one prime coat over a chemically pretreated base followed by at least one baked on enamel finish coat.

SUBMITTALS

Manufacturer's descriptive data, standard color palette, installation instructions and working drawings shall be submitted for approval.

Colors will be selected from the manufacturer's standard color palette by the Engineer after the award of the contract.

Working drawings shall show the plan layout, door and panel elevations and all details required for the complete installation and anchorage of the partition system.

PART 2 - PRODUCTS

Doors and Pilasters:

Doors and pilasters shall be flush, one-inch minimum thickness, formed of two 0.034-inch (22-gage) minimum thickness, galvanized steel sheets over a honeycomb core. Doors and panels shall have formed edges sealed with a continuous oval crown locking strip, and shall be mitered, welded and finished at the corners.

Doors shall have controlled action hinges, with vertical pintle and ball bearing roller operating on adjustable cams, or moving parts of nylon and stainless steel. Top pivots shall be recessed into edges of doors.

Doors shall be provided with slide bar latch and a combination coat-hat hook and door stop, except as otherwise specified.

Doors on stalls designed for use by the disabled shall be provided with a grip and turn latch, combination coat-hat hook and door stop, and U-shaped door pulls immediately below the latch on the inside and outside of the door.

Pilasters: Pilasters shall be 1¼ inches thick, of the same construction as the doors and panels, except face sheets shall be 0.052 inch for galvanized steel and 0.048 inch for stainless steel (18-gage), with adjustable, leveling base incorporating two 3/8-inch diameter stud expansion anchors with leveling nuts.

Fasteners and Anchorages: Fasteners and anchorages shall be stainless steel with vandal resistant heads.

Hardware: Hardware shall be highly polished chromium plated, cast alloy, or heavy duty anodized aluminum.

PART 3 - EXECUTION

INSTALLATION

Metal toilet pilasters shall be installed rigidly, securely, plumb, and true and in accordance with the manufacturer's recommendations. Tops and bottoms of doors shall align with tops and bottoms of pilasters, and all horizontal lines shall be level.

Pilasters shall be anchored with at least 4 brackets at each wall.

Doors shall not bind during opening and closing. The clearance between the door edges and pilasters shall be uniform, equidistant, and shall not exceed 3/16 inch. Hinges shall be adjusted to hold doors ajar when unlatched. Doors on stalls designed for use by the disabled shall return to the closed position.

Drilling, cutting and fitting of wall finishes shall be concealed by the completed installation.

CLEAN-UP

Toilet doors and pilasters shall be cleaned, polished and free of all defects. Chipped, dented, scratched, or otherwise damaged work shall be replaced at the Contractor's expense.

12-10.03 LOUVERS

PART 1 - GENERAL

Scope: This work consists of furnishing and installing louvers in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Manufacturer's descriptive data and installation instructions shall be submitted for approval.

Shop Drawings: Shop drawings of fabricated items shall be submitted for approval.

Samples: Samples of frame and louver section, 4 inches long, with finish, shall be submitted for approval.

PART 2 - PRODUCTS

Louvers:

Louvers shall be factory fabricated 2" Thin Line storm resistant louver units of extruded aluminum alloy not less than 0.081 inch thick (12-gage) with 0.063 inch thick extruded aluminum 6063 alloy blades, with powder coat finish and removable bronze 16 x 16 mesh insect screens mounted on the inside of the units.

Sill and jamb frames shall be continuously welded and caulked to prevent water penetration.

Blades shall be attached by means of all-weld construction.

Invisible mullions shall be continuous aluminum channels bolted together with neoprene gasketing between.

Manufacturers: Subject to compliance with the specifications, manufacturers shall be Industrial Louvers Inc. (Thin Line Louvers Model 254 FF); Alrolite: Barnett Bates Corp; or equal.

PART 3 - EXECUTION

INSTALLATION

Louvers shall be installed in accordance with the manufacturer's instructions. The completed louver installation shall be weather tight.

Louvers shall be cleaned in accordance with manufacturer's instruction following installation.

12-10.04 INFORMATION DISPLAY CASES

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of fabricating, furnishing and installing information display cases in accordance with the details shown on the plans and these special provisions.

Information display cases shall be completely factory assembled, illuminated units with tackboard and glazed aluminum door and frame and mounted on concrete wall.

SUBMITTALS

Product Data: Manufacturer's descriptive data for the component parts of the display cases shall be submitted for approval.

QUALITY ASSURANCE

PART 2 - PRODUCTS

MATERIALS

Aluminum Door and Frame: Aluminum door and frame shall be heavy, Type 6063-T5 extruded aluminum. Door shall have square profile and frame shall have "Hat Bar" trim. Unit shall be complete with lock, full length piano hinge, glazing and weatherstripping. Glazing shall be ¼ inch clear laminated safety glass.

Tackboard: Tackboard shall be bulletin board grade, self-sealing, ¼-inch thick corkboard glued to the plywood core. Glue shall be for exterior use and shall be compatible with the materials being adhered.

Plywood Core: Plywood core shall be exterior grade plywood as recommended by the display case manufacturer.

Lighting: Lighting shall be as shown on the plans.

Fasteners: Fasteners in contact with redwood shall be aluminum, stainless steel or galvanized steel.

Display cases shall be Visoline 2400.2 Series, The Tablet and Ticket Co. 800 series or equal with display light or equal.

FABRICATION

Shop Assembly: Screws shall be countersunk and the holes filled. Joints shall be neatly mitered and fitted tight and true.

Shop Finishing:

All components shall be shop finished before assembly.

The final finish shall be in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

PART 3 - EXECUTION

INSTALLATION

Information display cases shall be installed in accordance with the manufacturer's recommendations.

Door and lock shall be adjusted, as necessary, after installation for smooth and easy operation.

12-10.05 SIGNS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing signs in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Product Data: Manufacturer's descriptive data for sign materials, colors and graphics, and for fastening hardware and material shall be submitted for approval.

PART 2 - PRODUCTS

Plastic Signs (Permanent Room Identification):

Plastic signs for permanent room identification for other than restrooms shall be scratch resistant, non-static, fire retardant, washable melamine laminate with a non-glare surface, not less than 1/8 inch thick. Letters and numbers shall be upper case Helvetica, one inch in height, 1/32 inch above and integral with sign material, accompanied by Grade 2 Braille.

Grade 2 Braille dots shall be 1/10 inch on center in each cell with 2/10-inch space between cells. Dots shall be raised a minimum of 1/40 inch above the background.

Plastic Sign (Restroom):

Plastic sign for restroom shall be not less than 1/4-inch acrylic plastic. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Male/female symbol and lettering shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Male restroom identification shall be a male symbol on an equilateral triangle with edges 12 inches long and a vertex pointing upward.

Female restroom identification shall be a female symbol on a 12-inch diameter circle.

Unisex restroom identification shall be a male and female symbol on a 12-inch equilateral triangle superimposed on a 12-inch diameter circle.

Accessible Building Entrance Sign:

Accessible building entrance sign shall be not less than 1/8-inch acrylic plastic, not less than 4" x 4" with the international symbol of accessibility.

Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Symbol and border shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Fastening hardware and material: Fastening hardware and material shall be as recommended by the sign manufacturer. Fasteners shall be noncorrosive and tamper proof.

PART 3 - EXECUTION

Inscription: Sign messages shall be as shown on the plans.

INSTALLATION

Plastic signs for room identification and restrooms shall be fastened or secured to clean, finished surfaces in accordance with the sign manufacturer's instructions. Signs shall be installed at a location and height as shown on the plans.

Metal signs shall be attached securely with galvanized or cadmium plated tamper proof fasteners.

Fastening hardware and material shall be installed within the sign as shown on the plans.

12-10.06 WARDROBE LOCKERS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing wardrobe lockers in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Product Data:

Manufacturer's descriptive data, installation instructions, and standard color palette shall be submitted for approval.

Unless otherwise shown on the plans, the color will be selected by the Engineer from the standard color palette after the award of the contract.

PART 2 - PRODUCTS

ACCEPTABLE MANUFACTURERS

Available Manufacturers: Subject to conformance with the contract provisions, metal lockers shall be Art Metal Products; Lyon Metal Products; Republic Storage Systems; or equal.

Lockers:

Double tier lockers shall be standard, factory fabricated steel units. Framing shall be 0.060 inch thick (16-gage) and face sheets shall be 0.024 inch (24-gage), except door face sheets shall be 0.060 inch (16-gage).

Lockers shall be equipped with the following: hat shelf located approximately 10 inches below the top of the wardrobe locker, coat hook, louver vents at top and bottom of door, nonbreakable grip and turn handle, provisions for a padlock, lockbar with 3-point latching contact with door frame and 1 1/2 pair full looped leaf hinges.

The approximate dimensions of the wardrobe lockers shall be 15 inches wide, 18 inches deep and 72 inches high.

Closed Base: Closed base shall be the manufacturer's standard continuous 6-inch base, fabricated of the same material and designed for use with the lockers provided. Bottoms shall be flanged inward for stiffening. Bases shall have the same finish as the locker units.

Top: Top shall be the manufacturer's standard continuous sloping top with end closure as needed, fabricated of the same material and designed for use with the lockers provided. Tops shall have the same finish as the locker units.

FABRICATION

Shop Assembly:

Lockers shall be fabricated square, rigid, and without warp, with metal faces flat and free of dents or distortion.

Frame joints and seams shall be welded. Exposed welds shall be ground smooth. Hinge and latch connections shall be welded or riveted.

Bolts shall be used for assembly and mounting lockers components. Bolt or rivet heads on fronts of locker doors or frame shall not be exposed.

Factory Finish: Lockers shall be chemically pretreated with degreasing and phosphatizing process. Wardrobe lockers shall have a baked enamel finish on all surfaces, exposed and concealed.

PART 3 - EXECUTION

INSTALLATION

Lockers shall be mounted on closed bases at locations shown in accordance with the manufacturer's instructions for plumb, level, rigid, and flush installation.

Wardrobe lockers shall be bolted together at tops and bottoms. The backs of the end lockers shall be bolted to wall with ¼-inch expansion bolts installed near the tops of the wardrobe lockers as recommended by the locker manufacturer.

Trim, sloping tops, and metal filler panels, if required, shall be installed using concealed fasteners to provide flush, hairline joints against adjacent surfaces.

The number of lockers shall be as shown on the plans.

12-10.07 FIRE EXTINGUISHERS AND CABINETS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing fire extinguishers with cabinets or mounting brackets in accordance with the details shown on the plans and these special provisions.

REFERENCES

Fire Extinguishers shall conform to the requirements in California Code of Regulations, Title 19 Division 1, Chapter 3, "Portable Fire Extinguishers."

SUBMITTALS

Product Data: Manufacturer's descriptive data and installation instructions shall be submitted for approval.

QUALITY ASSURANCE

Codes and Standards: Fire extinguishers shall be Underwriters Laboratories or Factory Mutual Laboratories approved for the type, rating and classification of extinguisher specified.

PART 2 - PRODUCTS

MANUFACTURER'S

Acceptable Manufacturers: Subject to contract compliance, manufacturers shall be J. L. Industries; Larsen's Manufacturing; Potter-Roemer; or equal.

COMPONENTS

Fire Extinguisher: Fire extinguisher shall be fully charged, multi-purpose dry chemical type, with charge indicator, hose and nozzle, and attached service record tag. Fire extinguisher shall be of 5 lbs capacity and type rating shall be selected by the Engineer.

Fire Extinguisher Cabinet:

Fire extinguisher cabinet shall be factory fabricated, constructed of steel with a clear plastic panel in a steel door frame, and shall have a baked enamel finish. Color to be selected by the Engineer from the manufacturer's standard colors.

Fire extinguisher cabinet shall be surface mounted.

PART 3 - EXECUTION

INSTALLATION

Fire extinguishers shall be installed in locations and at mounting heights shown on the plans, or if not shown, at a height of 48 inches from the finished floor to the top of the fire extinguisher.

Fire extinguisher cabinets shall be attached to structure, square and plumb, in accordance with the manufacturer's recommendations.

IDENTIFICATION

Cabinet-mounted: Extinguishers in cabinets shall be identified with letter spelling "FIRE EXTINGUISHER" applied to the cabinet door. Letter size, styles, and color shall be selected by the Engineer from manufacturer's standard arrangements.

SERVICING

Fire extinguishers shall be serviced, charged, and tagged not more than 5 days prior to contract acceptance.

12-10.08 FREE STANDING STEEL SHELVING

PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing free standing steel shelving in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Manufacturer's descriptive data, installation instructions and standard color palette shall be submitted for approval. The color will be selected by the Engineer after the award of the contract.

PART 2 - PRODUCTS

Shelving units: Shelving units shall be 36 inches wide x 18 inches deep x 80 inches high and shall be factory fabricated steel with five shelves and supports capable of supporting loads of 25 pounds per square foot of shelf area. Shelves shall not deflect more than 5/16 inch when subjected to the loads specified herein and shall show no permanent deflection after removal of such loads. Shelves shall be supported and attached by means of clips. Studs or bolts shall not be used. Shelves shall be adjustable in vertical increments of 3 inches or less.

Custom shelving unit shall be fabricated as described above and shall be 48 inches wide 18 inches deep by 24 inches high with 3 shelves and supports with finish color to match lockers.

PART 3 - EXECUTION

Free standing steel shelving shall be installed in accordance with the manufacturer's instructions.

12-10.09 TOILET ROOM ACCESSORIES

PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing toilet room accessories in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Manufacturer's descriptive data and installation instructions and details shall be submitted for approval.

PART 2 - PRODUCTS

Toilet Tissue Dispenser: Toilet tissue dispenser shall be three and four roll, surface mounted, stainless steel with satin finish. Dispenser shall utilize standard toilet tissue rolls. One dispenser per toilet stall.

Three roll toilet tissue dispenser shall be: Vandal Stop Products model # OFUX3, Aslin Industries Dispensers or equal for each accessible stall.

Four roll toilet tissue dispenser shall be: Vandal Stop Products model # RD4, Aslin Industries Dispensers or equal for each non-accessible stall.

Waste Receptacle: Waste receptacle shall be State Furnished to the Contractor. Contractor shall be responsible for off loading the trash receptacle from the delivery truck on site and placing where shown on the landscape plans.

Soap Dispenser System: Soap dispenser system shall be wall-mounted and shall have gravity feed, plunger type spouts, and a remote stainless steel liquid soap reservoir equipped with soap level indicator, outlet valves, and brass tubing and fittings. Brass tubing and fittings shall be as recommended by the dispenser manufacturer. The stainless steel and chrome plated brass construction soap dispensing mechanisms shall be capable of delivering fixed amounts of liquid soap in lather form. The vandal resistant valves shall project not more than 3½ inches from the wall and shall not be removable from within the restroom.

Toilet Seat Cover Dispenser: Toilet seat cover dispenser shall be stainless steel, lockable dispenser. Approximate dimensions: 15" x 11½" x 2 3/8" deep. One dispenser per toilet stall.

Napkin Receptacle: Napkin receptacle shall be wall hung, stainless steel napkin receptacle with piano hinges top and bottom and disposable liner. Approximate capacity: one gallon. One receptacle per women's toilet stall.

Mirror, Wall Hung: Mirror, wall hung shall be Number 1 quality, ¼ inch thick, Lexan lense mirror with nonmoisture-absorbing filler. Mirror shall have a heavy gage galvanized steel back and stainless steel frame. The frame shall have a satin finish and shall be mitered and welded and the corners shall be ground smooth. Fasteners shall not penetrate surfaces of the frame exposed to view. Mirror shall conform to Federal Specification: DD-M-411b and shall be guaranteed against silver spoilage for not less than 10 years.

Grab Bars: Grab bars shall be stainless steel, 1½-inch diameter bars with integral mounting flanges concealed under integral escutcheons.

Electric Hand Dryer: Electric hand dryer shall be a surface-mounted, unit with a maximum lockout timer of 35 seconds. Hand dryer shall be mounted on a heavy duty backing plate with 2 chrome plated tamper resistant bolts. The backing plate shall have two 7/8-inch diameter holes for electrical access and shall be bolted to the wall with four thru-wall concealed mounting bolts. Hand dryer cover plate shall be a one piece, heavy duty, rib-reinforced, die-cast zinc alloy, cover plate, painted with an electrostatically applied white epoxy and chip-proof finish paint. Nozzle shall be fixed in the downward air position.

Electric Hand Dryer Motor: The motor shall be 460 watts minimum, series commutated, 20,000 RPM, through-flow discharge blower motor. Dryer shall produce 100 CFM at 130°F, and 5000 linear feet per minute average velocity for 30 seconds. Fan and motor assembly shall be insulated from the housing by a resilient rubber mounting.

Heater: A 900-watt, nichrome wire heating element protected by an automatic resetting high temperature limit control switch that opens when air flow stops, and automatically re-closes when air flow resumes. The heating element shall produce an air temperature of up to 135°F at a distance of 4 inches away from the air outlet, at a 72°F ambient room temperature.

Controls: Hand dryer shall be activated by an infrared optical sensor located adjacent to the air outlet. The hand dryer shall operate as long as hands are under the air outlet for the maximum lockout time of 35 seconds. Under normal conditions of atmospheric temperature, hand dryer shall be able to dry the hands within 15 seconds.

PART 3 - EXECUTION

Toilet room accessories shall be installed in accordance with the manufacturer's recommendations. Fasteners for mounting toilet room accessories shall be concealed and vandal resistant.

Expansion anchors shall be used for mounting accessories on masonry or concrete walls.

Toilet room accessories shall be mounted after painting work has been completed.

All toilet room accessories shall be mounted plumb, secure and rigid. Grab bars shall be supported adequately so the bars will withstand an applied load of 250 pounds at any point.

SECTION 12-11. (BLANK)

SECTION 12-12. (BLANK)

SECTION 12-13. (BLANK)

SECTION 12-14. (BLANK)

SECTION 12-15. MECHANICAL

12-15.01 MECHANICAL WORK

PART 1 - GENERAL

Scope: This work shall consist of performing mechanical work in accordance with the details shown on the plans and these special provisions.

Mechanical work shall include furnishing all labor, materials, equipment and services required for providing heating, ventilating, air conditioning, and plumbing systems.

Earthwork, foundations, sheet metal, painting, electrical, and such other work incidental and necessary to the proper installation and operation of the mechanical work shall be in accordance with the requirements specified for similar type work elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of pipes, ducts, etc., and location of equipment is to be governed by structural conditions and obstructions. Equipment requiring maintenance and inspection is to be readily accessible.

Roof penetrations shall be flashed and sealed watertight in accordance with the requirements specified under "Sheet Metal Flashing" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

SUBMITTALS

Product Data:

A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for plumbing fixtures, and component layout shall be included where applicable.

Manufacturer's descriptive data shall be submitted for the following:

- Pump Skid
- Storage Tank
- Exhaust Fan
- Heat Pump wall mounted air conditioner
- Water closets
- Urinals
- Lavatories and associated faucet and piping trim
- Sink and associated faucet and associated piping trim
- Accessible emergency eye wash
- Mop sink including wall faucet and hose trim
- Drinking fountain
- Liquid soap dispenser with wall soap container
- Utility box
- Electric water heater
- Roof drain
- Overflow roof drain
- Floor drain
- Floor sink
- Double check valve assembly
- Reduced pressure backflow assembly
- Hose bibb

CLOSEOUT SUBMITTALS

Operation and Maintenance Manuals:

Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be indexed and bound in a manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material shall be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

Operation and maintenance manuals shall be submitted for the following equipment:

Pump Skid
Storage Tank
Exhaust Fan
Heat Pump wall mounted air conditioner
Water closets
Urinals
Lavatories and associated faucet and piping trim
Sink and associated faucet and associated piping trim
Accessible emergency eye wash
Mop sink including wall faucet and hose trim
Drinking fountain
Liquid soap dispenser with soap container
Electric water heater
Roof drain
Overflow roof drain
Floor drain
Floor sink
Double check valve assembly
Reduced pressure backflow assembly
Hose bibb
Floor clean out
Surface mounted electric heater

QUALITY ASSURANCE

Codes and Standards: Mechanical work, including equipment, materials and installation, shall conform to the CBC, CMC, and to the California Code of Regulations, Title 8, Chapter 4, Division of Industrial Safety (DIS).

WARRANTY

Warranties and Guarantees: Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

SYSTEM IDENTIFICATION

Piping, Ducts, Valves and Equipment:

Identification of piping, ducts, valves and equipment shall be as shown on the plans or these special provisions:

Above Ground Piping and Ducts: Markers shall be provided on lines which are either exposed or concealed in accessible spaces. For piping systems, except drain and vent lines, indicate the fluid conveyed or its abbreviation; either by preprinted markers or stenciled markings, and include arrows to show the direction of flow. Colors shall comply with ANSI Standard: A13.1. Locate markers at ends of lines, near major branches and other interruptions including equipment in the line, where lines pass through penetrations in floors, walls or ceilings or otherwise pass into inaccessible spaces, and at 50-foot maximum intervals along exposed portions of the lines. Marking of short branches and repetitive branches for equipment connections is not required.

Valves: Valve tags shall be provided on all valves of each piping system, excluding check valves, valves within equipment, faucets, stops and shut-off valves at fixtures and other repetitive terminal units. Provide brass or plastic laminate tags. Prepare and submit a tagged valve schedule, listing each valve by tag number, location and piping service. Valve schedule shall be mounted in a glazed frame at a location approved by the Engineer.

Equipment: All equipment shall be identified with a plastic laminated, engraved nameplate, which bears the unit mark number as indicated on the drawings (for example, AC-4). Provide ½-inch high lettering, white on black background. Nameplates shall be permanently secured to the unit.

PART 2 – PRODUCTS (Not applicable)

PART 3 – EXECUTION (Not applicable)

12-15.02 PIPE, FITTINGS AND VALVES

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing pipes, fittings and valves in accordance with the details shown on the plans and these special provisions. Pipe, fittings and valves shall include such plumbing and piping accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the plumbing and piping systems.

All piping insulation and wrapping material shall be in accordance with the requirements specified under "Mechanical Insulation," in this Section 12-15.

Cathodic protection for underground piping shall be in accordance with the requirements specified under "Cathodic Protection," in Section 12-16, "Mechanical," of these special provisions.

The pipe sizes shown on the plans are nominal inside diameter. No change in the pipe size shown on the plans shall be permitted without written permission from the Engineer.

The pipe and fitting classes and material descriptions shall be as specified herein. No change in class or description shall be permitted without written permission from the Engineer.

QUALITY ASSURANCE

Codes and Standards: Pipe, fittings and valves shall be installed in accordance with the requirements in the CPC, the manufacturer's recommendations and the requirements specified herein.

PART 2 - PRODUCTS

MATERIALS

PIPE AND FITTINGS (Class and Description)

A1: Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with 150 psi galvanized malleable iron banded screwed fittings and galvanized steel couplings. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

A2: Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with black cast iron recessed drainage fittings. For rainwater leaders, neoprene-gasket compression couplings, Smith Blair, Dresser, or equal, may be used. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

A3: Schedule 5 steel pipe conforming to ASTM Designation: A 135 with pressfit fittings and couplings for service as designated.

B1: Schedule 40 black steel pipe conforming to ASTM Designation: A 53, with screwed fittings suitable for working pressure involved, but not less than 175 psi. Fittings shall be listed for fire protection.

B2:

Schedule 40 black steel pipe conforming to ASTM Designation: A 53, with 150 psi black malleable iron banded screwed fittings and black steel couplings.

Steel pipe coating, where required, shall be factory applied plastic. Pipe coating shall be Standard Pipe Protection, X-Tru-Coat (20-mil thickness); Pipe Line Service Corporation, Republic; 3M Company, Scotchkote 205 (12-mil thickness); or equal.

B3: Schedule 80 black steel pipe conforming to ASTM Designation: A 53 grade B, pipe 2 inches in diameter and smaller shall have 3,000 psi WOG socket welding fittings and couplings or 2,000 psi WOG threaded forged steel, ASTM Designation: A 105. Pipe 2½ inches in diameter and larger shall be extra strong weight butt welding fittings and couplings.

C1: Hub and plain end cast iron soil pipe with neoprene gaskets conforming to Cast Iron Soil Pipe Institute's Standard 301. Pipe, fittings and gaskets shall be of one manufacturer.

C2: Hubless cast iron soil pipe with neoprene gaskets, corrugated stainless steel shields and stainless steel clamps conforming to Cast Iron Soil Pipe Institute's Standard 301. Joint materials shall be furnished by pipe manufacturer.

D1: Ductile iron push on joint pipe conforming to AWWA Designation: C151. Fittings shall be push on ductile iron conforming to AWWA Designation: C153. Joints shall be rubber gasketed and designed for a working pressure of 350 psi. Pipe and fittings shall be supplied with bituminous outer coating and cement lining. Pipe shall be listed for fire protection.

H1: Type DWV hard copper tubing conforming to ASTM Designation: B 306, with DWV drainage fittings, stop type couplings and threaded adapters.

H2: Type K hard copper tubing conforming to ASTM Designation: B 88, with wrought copper or cast bronze solder joint pressure fittings, stop type couplings and threaded adapters. Solder shall be lead-free.

H3: Type L hard copper tubing conforming to ASTM Designation: B 88, with wrought copper or cast bronze solder joint pressure fittings, stop type couplings and threaded adapters. Solder shall be lead-free.

H4: Schedule 40 brass pipe conforming to ASTM B43 red brass with cast brass fittings for threaded connections.

J1: Vitrified clay sewer pipe and fittings conforming to ASTM Designation: C 700, with resilient cold joint ends; hot pour joint ends; or hubless type with neoprene gaskets, stainless steel clamps and hexagon head bolts. Cold joints shall conform to ASTM Designation: C 425, Type 1 and shall be made with interlocking, resilient, mechanical compression joint, formed on pipe at factory. When clay pipe is to join cast iron soil pipe, joints shall be made between bell end of clay pipe and spigot end of cast iron soil pipe using gasket and bitumastic joint compound as specified for hot pour joints.

P1: Polyvinyl chloride (PVC) gravity sewer plastic pipe and fittings conforming to ASTM Designation: D 3034, Standard Dimension Ratio (SDR) 35, with integral bell and bell and spigot rubber gasketed joints or conforming to ASTM Designation: D2665 with solvent welded fittings. Rubber gaskets shall conform to ASTM Designation: F 477. Stainless steel clamps with rubber boots shall not be used.

P2: Polyvinyl chloride (PVC) plastic pipe and fittings conforming to ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 200 psi working pressure at 73°F, National Sanitation Foundation approved. Pipe shall have bell ends conforming to ASTM Designation: D 3139 with triple edge rubber sealing ring. For pipe sizes 2-inch diameter and smaller, plain end pipe with solvent welded fittings ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 200 psi may be used.

P3: Polyvinyl chloride (PVC) standard weight pipe and fittings, Schedule 40, conforming to ASTM Designation: D 1785. Pipe shall meet or exceed requirements of National Sanitation Foundation Standard No. 14. Pipe shall have

bell ends conforming to ASTM Designation: D 2672. For pipe sizes 3 inches and smaller, plain end pipe with solvent welded fittings conforming to ASTM Designation: D 2241, may be used.

Unions (for Steel Pipe): Unions (for steel pipe) shall be 250 psi, threaded malleable iron, ground joint, brass to iron seat, galvanized or black to match piping.

Unions (for Copper or Brass Pipe): Unions (for copper or brass pipe) shall be 150 psi cast bronze, ground joint, bronze to bronze seat with silver brazing threadless ends or 125 psi cast brass, ground joint, brass to brass seat with threaded ends.

Unions (for Brass Waste and Flush Pipes): Unions (for brass waste and flush pipes) shall be slip or flange joint unions with soft rubber or leather gaskets. Unions shall be placed on the fixture side of the traps.

Dielectric Waterway: Dielectric waterway shall be a premanufactured unit that incorporates an insulated interior lining at least 3 inches in length between the 2 pipes being connected while maintaining metal to metal contact on the exterior surface. Dielectric water way shall be listed by IAPMO (International Association of Plumbing and Mechanical Officials).

Insulating Union: Insulating union or flange as applicable shall be suitable for the service on which used. Connections shall be constructed such that the 2 pipes being connected are completely insulated from each other with no metal to metal contact. Insulating couplings shall not be used. Insulating union shall be F. H. Maloney; Central Plastics; EPCO; or equal.

Insulating Connection (to Hot Water Tanks): Insulating connection (to hot water tanks) shall be 6-inch minimum, flexible copper tubing with dielectric union (Insulating Union) at each end and designed to withstand a pressure of 150 psi and a temperature of 200°F.

VALVES

Gate Valve (2½-inch and smaller):

Gate valve (2½-inch and smaller) shall be bronze body and trim, removable bonnet and non rising stem, Class 125 and same size as pipe in which installed. Gate valve shall be Crane, 438; Nibco Scott, T-113; Jenkins, 370; or equal.

Gate valve in nonferrous water piping systems may be solder joint type with bronze body and trim. Valve shall be Kitz, 59; Nibco Scott, S-113; Jenkins, 1240; or equal.

Gate Valve (3-inch and larger, above ground): Gate valve (3-inch and larger, above ground) shall be iron body with bronze trim, removable bonnet and non-rising stem, Class 125 and same size as pipe in which installed. Gate valve shall be Crane, 461; Nibco Scott, F-619; Jenkins, 326; or equal.

Gate Valve (3-inch and larger, below ground): Gate valve (3-inch and larger, below ground) shall be AWWA double disc, hub or rubber ring type, removable bonnet and non-rising stem, equipped with operating nuts, 200 psi working pressure, and Tee handle wrench for each valve. Valve shall be Mueller, A-2380; American Valve, Model 28; or equal.

Ball Valve: Ball valve shall be two piece, minimum 400 psi WOG, bronze body and chrome plated or brass ball with full size port. Valve shall be Nibco Scott, T-580; Watts, B-6000; Kitz, 56; or equal.

Check Valve (1½-inch and smaller): Check valve (1½-inch and smaller) shall be silent spring loaded type, threaded bronze body, nylon or teflon disc, beryllium or stainless steel helical spring and shaft, Class 125 and same size as pipe in which installed. Check valve shall be Nibco/Scott, T-480; CPV, 36; Kitz, 26; or equal.

Check Valve (2-inch and larger): Check valve (2-inch and larger) shall be silent wafer type, full faced for installation between 125 psi flanges, iron body with bronze trim, nylon or teflon disc, stainless steel helical spring and shaft, Class 125 and same size as pipe in which installed. Check valve shall be APCO, Series 300; CPV, 10D; Metraflex, Series 900; or equal.

FAUCET AND HYDRANTS

Hose Faucet HB-1, HB-2: Hose faucet (hose bibb) shall be compression type, angle pattern, wall flange (HB-1) at exterior locations or exposed pattern (HB-2), removable brass tee handle with guarded neck, 3/4-inch female outlet thread with hose end pointing straight down, polished chrome for outdoor locations, or nickel plated finish for locations inside building. Hose faucet shall be supplied with an integral or nonremovable threaded outlet vacuum breaker which meets the requirements of the American Society of Sanitary Engineering (ASSE) Standard: 1011. Hose faucet shall be Zurn Z81307, Nibco, ; Chicago, ; or equal.

CLEANOUTS

Cleanout Through Wall: Cleanout through wall shall be cast iron cleanout tee type with polished stainless access plates. Plug shall be countersunk brass or bronze with tapered threads. Cleanout shall be Wade, No. W-8460; Smith, No. 4532; Zurn, No. 1445; or equal.

Cleanout Through Floor:

FCO-1 Cleanout through floor shall have nonslip scoriated nickel bronze access plate and adjustable frame with square pattern top for ceramic tile and round pattern top for other finishes. Where floors are constructed with a membrane, access frame shall be provided with membrane clamping flange. Plug shall be countersunk brass or bronze with tapered threads. Cleanout shall be Wade, W-7000 Series; Smith, 4023 Series; Zurn, No. 1400; or equal.

Cleanout through floors in exterior locations shall be heavy duty, floating pipe type with cast iron cover. Cleanouts shall be Wade, No. W-8300-HF; Smith, No. 4253; Zurn, No. 1474; or equal.

Cleanout to Grade: Cleanout to grade shall be cast iron ferrule type. Plug shall be countersunk brass or bronze with tapered threads. Cleanout to grade shall be Wade, No. W-8450; Smith, 4420; Zurn, No 1440; or equal.

MISCELLANEOUS ITEMS

Water Hammer Arrestor SA-1 and SA-2 : Water hammer arrestor (Shock Arrestor) shall be stainless steel body with bellows . Arrestor compression chambers shall be pneumatically charged. Water hammer arrestors shall be tested and certified in accordance with the Plumbing and Drainage Institute Standard: PDI-WH201 and sized as shown on the plans. SA-1 shall be 3/4" pipe thread connection. SA-2 shall be 1" pipe thread connection.

Compression Stop (Exposed): Compression stop (exposed) shall be metal full free waterway, angle type, ground joint union, non-rising stem, molded rubber seat and wheel handle.

Compression Stop (Concealed): Compression stop (concealed) shall be long neck, built-in compression stops for required wall thickness, loose key and exposed parts polished chromium plated. Supplies shall be Chicago, 1771; California Brass, No. 172; or equal.

Wye Strainer: Wye strainer shall be wye pattern, cast iron body and Type 304 stainless steel or monel strainer screen. The strainer screen shall have an open area equal to at least 3 times the cross sectional area of the pipe in which it is installed and shall be woven wire fabric with 20 mesh or perforated sheet with 0.032-inch maximum diameter holes.

Reduced Pressure Backflow Preventer RPBP-1: Reduced Pressure Backflow preventer shall be factory assembled with 2 check valves, one pressure differential relief valve, 2 ball valves and 4 test cocks. Backflow preventers shall be of the approved type reduced pressure principle devices listed by the County of Los Angeles Department of Health Services, Cross-Connection and Water Pollution Control Section, 2525 Corporate Place, Monterey Park, California 91754, Telephone (213) 881-4140. Watts Series 909M1; Febco model 825Y; Apollo series 40-200, or approved equal.

Double Check ValveDCV-1: Double check valve shall be factory assembled with 2 positive seating check modules with captured springs, y-strainer, 2 ball valves and 4 test cocks. Backflow preventer shall be approved and rubber seat replaceable discs. Watts Series 007; Febco model 850; Apollo series 40-100, or approved equal.

Water Meter: Provided as part of the pre-assembled pump skid package – refer to specification "Plumbing Booster System".

Pipe Hanger (for piping supported from overhead): Pipe hanger (for piping supported from overhead) shall be Grinnell, Model 269; Super Strut, C711; or equal.

Pipe Support (for pipe supported along walls): shall be a combination of anchor bolt attachment using 12 gauge pre-punched 1-5/8" channel strut and pipe clamp assemblies. Strut and clamp assemblies shall be factory coated with electro-plated zinc and zinc dichromate finish; and shall be B-Line, Unistrut, Superstrut series 1200 or approved equal.

Pipe Wrapping Tape and Primer:

Pipe wrapping tape shall be pressure sensitive polyvinyl chloride or pressure sensitive polyethylene tape having nominal thickness of 20 mils. Wrapping tape shall be Polyken, 922; Manville, Trantex VID-20; Scotchrap, 51; or equal.

Pipe wrapping primer shall be compatible with the pipe wrapping tape used.

Floor, Wall, and Ceiling Plates: Floor, wall, and ceiling plates shall be chromium plated steel or plastic plates having screw or spring clamping devices and concealed hinges. Plates shall be sized to completely cover the hole.

Valve Box: Valve box shall be precast high density concrete with polyethylene face and cast iron traffic rated cover marked "WATER," "GAS" or "CO-SS" as applicable. Extension shall be provided as required. Valve box shall be Christy, B3; Brooks Products Company, 3TL; Frazer, 3; or equal. Valve box for domestic well water shut-off valve shall be Christy G-8 with bolt down cover; Brooks; Frazer; or approved equal.

Roof Drain RD-1 : Roof drain shall be cast iron body, with integral flashing clamp and gravel stop with seepage openings, 15-inch nominal polyethylene low profile dome, 3-inch caulk or no-hub outlet, acid resistant epoxy coated finish, vandal proof secure top, and underdeck clamp. Roof drain shall be J. R. Smith, 1010; Zurn, Z-100; Wade, W-3500; or equal.

Overflow Roof Drain OFD-1: Overflow roof drain shall be the same as the roof drain except that a 2" high external cast iron water dam will be added.

Floor Drain FD-1: Floor drain shall be cast iron body and flashing collar, adjustable nickel bronze heavy duty slotted 6-inch square strainer head with seepage openings, acid resistant epoxy coated finish and caulk or no-hub outlet. Floor drain shall be square as shown on the Architectural plans. Floor drain shall be Zurn, Z-415; J. R. Smith, 2005/2010; Wade, W-1100; or equal.

Floor Drain FD-2: Floor drain shall be cast iron body and flashing collar, adjustable nickel bronze non-clog 6" round strainer with sediment bucket, with seepage openings, acid resistant epoxy coated finish, vandal resistant screws and caulk or no-hub outlet. Floor drain shall be Zurn 30000-C, J.R. Smith, Wade, or approved equal.

Floor Sink FS-1: Floor sink shall be cast iron body and square slotted medium duty full grate, vandal resistant screws, with white acid resisting porcelain enamel interior and top complete with aluminum bucket strainer. Floor sink shall be Zurn Z1910; J.R. Smith; Wade; or approved equal.

Trench Drain:

PART 3 - EXECUTION

INSTALLATION

INSTALLATION OF PIPES AND FITTINGS

Pipe and Fittings: Pipe and fittings shall be installed in accordance with the following designated uses:

Designated Use	Pipe and Fitting Class
Domestic water (CW and HW) in buildings Except under-slab sleeved pipe	H3
Domestic Water (CW) in buildings within under-slab sleeved pipe	H2
Domestic water underground within 5 feet of the building	H2
Domestic water underground 5 feet beyond the building (Not the well water supply pipe – see below)	H2
Industrial cold water (Trap primer)	H2
Extended Domestic Well Water piping from existing point of connection to indoor service chase main shut-off valve.	A1
Extended Domestic Well Water piping from main shut-off valve to storage tank	H3
Sanitary drain piping above ground in building	H1, C1, or C2
Sanitary drain and vent piping underground within 5 feet of the building	J1, C1 or C2
Sanitary vent piping above ground in building	A2, H1, C1, or C2
Sanitary drain pipe, 5 feet beyond the building	J1, C1, C2, or P1
Rainwater leaders	A2
Equipment drains and relief valve discharge	H3 or A1
Soap lines through wall to soap dispenser only	H4

Installing Piping:

Water piping shall be installed generally level, free of traps and bends, and arranged to conform to the building requirements.

Vitrified clay pipe shall be installed in accordance with ASTM Designation: C 12, Class C.

Piping installed underground shall be tested as specified elsewhere in these special provisions before backfilling.

Public use areas, offices, rest rooms, locker rooms, crew rooms, training rooms, storage rooms in office areas, hallway type rooms, and similar type use areas shall have concealed piping.

Warehouse rooms, equipment bays, and loft areas shall have exposed piping.

Piping shall not be run in floor fill, except as shown on the plans.

Piping shall be installed parallel to walls. All obstructions shall be cleared, headroom preserved and openings and passageways kept clear whether shown or not. Piping shall not interfere with other work.

Where pipes pass through exterior above ground walls, a clear space around pipe shall be provided. Space shall be caulked water tight with silicone caulk. Where pipes pass thorough below grade walls and concrete assemblies, a pipe sleeve shall be installed that allows 1” of annulus space around the centered inner pipe.

Underground copper pipe shall have brazed joints. Pipe below slab level but in a pit or recessed area shall also be brazed joints. Underground plastic pipe shall be buried with No. 14 solid bare copper wire. Wire ends at pipe ends shall be brought up 8 inches and looped around pipe.

Exposed supply and drain piping in rest rooms shall be chrome finished.

Forty-five degree bends shall be used where offsets are required in venting. Vent pipe headers shall be sloped to eliminate any water or condensation.

Vent piping shall extend a minimum of 8 inches above the roof.

Horizontal sanitary sewer pipe inside buildings shall be installed on a uniform grade of not less than ¼ inch per foot unless shown otherwise on the plans.

Drainage pipe shall be run as straight as possible and shall have easy bends with long turns.

Wye fittings and 1/8 or 1/16 bends shall be used where possible. Long sweep bends and combination Wye and 1/8 bends may be used only for the connection of branch pipes to fixtures and on vertical runs of pipe.

Water pipe near sewers:

Water pipe shall not be installed below sewer pipe in the same trench or at any crossing, or below sewer pipe in parallel trenches less than 10 feet apart.

When a water pipe crosses above a sewer pipe, a vertical separation of at least 12 inches between the top of the sewer and the bottom of the water pipe shall be maintained.

When water and sewer pipe is installed in the same trench, the water pipe shall be on a solid shelf at least 12 inches above the top of the sewer pipe and 12 inches to one side.

Pipe Sleeves:

The Contractor shall provide sleeves, inserts and openings necessary for the installation of pipe, fittings and valves. Damage to surrounding surfaces shall be patched to match existing.

In general, PVC pipe sleeves shall be provided where each pipe passes through concrete floors, footings, walls or ceilings. Inside diameter of sleeves shall be at least ¾ inch larger than outside diameter of pipe. Sleeves shall be installed to provide at least 3/8-inch space all around pipe the full depth of concrete. Space between pipes and pipe sleeves shall be caulked watertight.

For roof drain pipe and roof overflow pipe through exterior concrete wall: pipe shall be cast in-place along with the wall.

For sleeves in which one end is open exposed to view in the breakroom, a multi-link compression seal shall be used with a sleeve made of schedule 10 thin wall 304 stainless steel.

Cutting Pipe: Pipe shall be cut straight and true and the ends shall be reamed to the full inside diameter of the pipe after cutting.

Damaged Pipe: Pipe that is cracked, bent or otherwise damaged shall be removed from the work.

Pipe Joints and Connections:

Joints in threaded steel pipe shall be made with teflon tape or a pipe joint compound that is nonhardening and noncorrosive, placed on the pipe and not in the fittings.

The use of thread cement or caulking on threaded joints will not be permitted. Threaded joints shall be made tight. Long screw or other packed joints will not be permitted. Any leaky joints shall be remade with new material.

Exposed polished or enameled connections to fixtures or equipment shall be made with special care, showing no tool marks or threads.

Cleaning and Closing Pipe: The interior of all pipe shall be cleaned before installation. All openings shall be capped or plugged as soon as the pipe is installed to prevent the entrance of any materials. The caps or plugs shall remain in place until their removal is necessary for completion of the installation.

Securing Pipe: Pipe in the buildings shall be held in place by iron hangers, supports, pipe rests, anchors, sway braces, guides or other special hangers. Material for hangers and supports shall be compatible with the piping or neoprene isolators shall be used. Allowances shall be made for expansion and contraction. Steel pipe shall have hangers or supports every 10 feet. Copper pipe one inch or less in diameter smaller shall have hangers or supports every 6 feet and sizes larger than one inch shall have hangers or supports every 10 feet. Plastic pipe shall have hangers or supports every 3 feet. Cast iron soil pipe with neoprene gaskets shall be supported at each joint. Vertical pipes shall be supported with clamps or straps. Horizontal and vertical piping shall be securely supported and braced to prevent swaying, sagging or flexing of joints.

Hangers and Supports:

Hangers and supports shall be selected to withstand all conditions of loading to which the piping and associated equipment may be subjected and within the manufacturer's load ratings. Hangers and supports shall be spaced and distributed so as to avoid load concentrations and to minimize the loading effect on the building structure.

Hangers and supports shall be sized to fit the outside diameter of pipe or pipe insulation. Hangers shall be removable from around pipe and shall have provisions for vertical adjustment after erection. Turnbuckles may be used.

Materials for holding pipe in place shall be compatible with piping material.

Hanger rods shall be provided with locknuts at all threaded connections. Hanger rods shall be sized as follows:

Pipe Size	Minimum Hanger Rod Diameter
1/2" to 2"	3/8"
2 1/2" to 3 1/2"	1/2"
4" to 5"	5/8"
6"	3/4"

Wrapping and Coating Steel Pipe:

Steel pipe buried in the ground shall be wrapped or shall be plastic coated as specified herein:

1. Wrapped steel pipe shall be thoroughly cleaned and primed as recommended by the tape manufacturer.
2. Tapes shall be tightly applied with 1/2 uniform lap, free from wrinkles and voids with approved wrapping machines and experienced operators to provide not less than 40-mil thickness.
3. Plastic coating on steel pipe shall be factory applied. Coating imperfections and damage shall be repaired to the satisfaction of the Engineer.
4. Field joints, fittings and valves for wrapped and plastic coated steel pipe shall be covered to provide continuous protection by puttying and double wrapping with 20-mil thick tape. Wrapping at joints shall extend a minimum of 6 inches over the adjacent pipe covering. Width of tape for wrapping fittings shall not exceed 2 inches. Adequate tension shall be applied so tape will conform closely to contours of fittings. Putty tape insulation compounds approved by the Engineer shall be used to fill voids and provide a smooth even surface for the application of the tape wrap.

Wrapped or coated pipe, fittings, and filed joints shall be approved by the Engineer after assembly. Piping shall be placed on temporary blocks to allow for inspection. Deficiencies shall be repaired to the satisfaction of the Engineer before backfilling or closing in.

Thrust Blocks:

No thrust blocks are needed for the plumbing on this project.

Union: Unions shall be installed where shown and at each threaded or soldered connection to equipment and tanks. Unions shall be located so piping can be easily disconnected for removal of equipment or tanks. Unions shall be omitted at compression stops.

Dielectric Waterway: Dielectric waterway shall be provided between metal pipes of different material, and between brass or bronze valves and steel piping.

Insulating Union and Insulating Connection:

Insulating union and insulating connection shall be provided where shown and at the following locations:

1. In metallic water, gas and air service connections into each. Insulating connections shall be installed on the exterior of the building, above ground and after shut-off valve.
2. In water, gas and air service connections in ground at point where new metallic pipes connect to existing metallic pipes. Install valve box above insulating connection.
3. At points of connections of copper or steel water pipes to steel domestic water heaters and tanks.
4. At each end of buried ferrous pipe protected by cathodic protection.

Bonding at Insulating Connections: Interior water piping and other interior piping that may be electrically energized and are connected with insulating connections shall be bonded in accordance with the CEC. Bonding shall all be coordinated with electrical work.

Compression Stop: Each fixture, including hose faucets, shall be equipped with a compression stop installed on water supply pipes to permit repairs without shutting off water mains. Ball valves may be installed where shown on the plans or otherwise permitted by the Engineer.

INSTALLATION OF VALVES

Pressure Reducing Valve: A capped tee connection and strainer shall be installed ahead of the pressure reducing valve.

Exterior Valves: Exterior valves located underground shall be installed in a valve box marked "Water." Extensions shall be provided as required.

INSTALLATION OF FAUCETS AND HYDRANTS

Hose Faucet : Faucets shall be installed with outlets 18 inches above finished grade.

INSTALLATION OF CLEANOUTS

Cleanouts:

A concrete pad 18 inches long and 4 inches thick shall be placed across the full width of trench under cleanout Wye or 1/8 bend. Cast iron soil pipe (C1 or C2) and fittings shall be used from Wye to surface. Required clearance around cleanouts shall be maintained.

Cleanout risers outside of a building installed in a surface other than concrete shall terminate in a cleanout to grade. Cleanout to grade shall terminate in a valve box with cover marked "CO-SS". Top of box shall be set flush with finished grade. Cleanout plug shall be 4 inches below grade and shall be located in the box to provide sufficient room for rodding.

Cleanout risers installed in tile and concrete floors, including building aprons and sidewalks, shall terminate in a cleanout through floor.

INSTALLATION OF MISCELLANEOUS ITEMS

Water Hammer Arrestor: Water hammer arrestor shall be installed so that they are vertical and accessible for replacement. Water hammer arrestor shall be installed with access door when in walls or there is no access to ceiling crawl spaces. Access door location shall be where shown on the plans or as approved by the Engineer.

Backflow Preventer:

Backflow preventer assembly shall include a wye strainer, backflow preventer, fittings and pipe. Assembly components shall be the same size as the pipe in which they are installed unless otherwise shown on the plans.

Backflow preventer shall be installed a minimum of 12 inches above ground and shall be the same size as the pipe in which it is installed unless otherwise shown on the plans. For backflow preventers with an intermediate drain outlet, provide a tapered collection cup immediately under the drain and extend a ¾" pipe to the service chase floor drain.

Water Meter: A water meter is being provided as part of the domestic water pump skid package. The field installed pipe serving the meter outlet shall be 40" of straight pipe before any other pipe fitting or change in pipe direction.

Flushing Completed Systems: All completed systems shall be flushed and blown out.

Chlorination:

The Contractor shall flush and chlorinate all domestic water piping and fixtures.

Calcium hypochlorite granules or tablets, if used, shall not be applied in the dry form, but shall first be dissolved into a solution before application.

The Contractor shall take adequate precautions in handling chlorine so as not to endanger workmen or damage materials. All pipes and fittings shall be completely filled with water containing a minimum of 50 ppm available chlorine. Each outlet in the system shall be opened and water run to waste until a strong chlorine test is obtained. The line shall then be closed and the chlorine solution allowed to remain in the system for a minimum of 24 hours so that the line shall contain no less than 25 ppm chlorine throughout. After the retention period, the system shall be drained, flushed and refilled with fresh water.

FIELD QUALITY CONTROL

Testing:

The Contractor shall test piping at completion of roughing in, before backfilling, and at other times as directed by the Engineer.

The system shall be tested as a single unit, or in sections as approved by the Engineer. The Contractor shall furnish necessary materials, test pumps, instruments and labor and notify the Engineer at least 3 working days in advance of testing. After testing, the Contractor shall repair all leaks and retest to determine that leaks have been stopped. Surplus water shall be disposed of after testing as directed by the Engineer.

The Contractor shall take precautions to prevent joints from drawing while pipes and appurtenances are being tested. The Contractor shall repair damage to pipes and appurtenances or to other structures resulting from or caused by tests.

Cathodic Protection Tests: The State will conduct tests at locations where cathodic protection is required to determine compliance with the specified requirements.

General Tests:

All piping shall be tested after assembly and prior to backfill, pipe wrapping, connecting fixtures, wrapping joints and covering the pipe. Systems shall show no loss in pressure or visible leaks.

The Contractor shall test systems according to the following schedule for a period of not less than 4 hours:

Test Schedule		
Piping System	Test Pressure	Test Media
Sanitary sewer and vent	10-foot head	Water
Water	125 psig	Water

During testing of water systems, valves shall be closed and pipeline filled with water. Provisions shall be made for release of air.

Sanitary sewers shall be cleared of obstructions before testing for leakage. The pipe shall be proved clear of obstructions by pulling an appropriate size inflatable plug through the pipe. The plug shall be moved slowly through the pipe with a tag line. The Contractor shall remove or repair any obstructions or irregularities.

Sanitary sewer pipes beyond 5 feet perpendicular to the building shall be tested for leakage for a period of not less than 4 hours by filling with water to an elevation of 4 feet above average invert of sewer or to top of manholes where less than 4 feet deep. The system shall show no visible leaks. The sewer may be tested in sections with testing water progressively passed down the sewer as feasible. Water shall be released at a rate that will not create water hammer or surge in plugged sections of sewer.

Testing Backflow Preventers:

Backflow preventers installed by the Contractor shall be tested at the completion of the supply system installation for proper operation by a certified Backflow Preventer Tester.

The tester shall hold a valid certificate as a Backflow Preventer Tester from the county in which the device to be tested is located or, if the county does not have a certification program for Backflow Preventer Testers, the tester shall have a certificate from one of the following:

1. The American Water Works Association.
2. A county which has a certification program for Backflow Preventer Testers. The certification under which the tester has been certified shall be acceptable to the water purveyor and the local agency having jurisdiction.

Testing for proper operation shall conform to the procedures of the county in which the testing is being performed, or, if such procedures are not available in the county, such tests shall conform to the provisions in the latest edition of the Guidance Manual For Cross Connection Control Program, which is available from the California Department of Health Services, Division of Drinking Water and Environmental Management, 601 N 7th Street, P.O. Box 942732, Sacramento, CA 94234.

The Contractor shall notify the Engineer at least 5 days prior to testing backflow preventers. Such tests shall be satisfactorily completed after installation of the backflow preventer assemblies and before operation of the systems.

One copy of all test results for each backflow preventer shall be furnished to the Engineer.

Full compensation for providing the certified Backflow Preventer Tester and for testing the backflow preventers shall be considered as included in the lump sum price paid for building work and no additional compensation will be allowed therefor.

12-15.03 PLUMBING FIXTURES

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing plumbing fixtures in accordance with the details shown on the plans and these special provisions.

PART 2 - PRODUCTS

General: Plumbing fixtures shall be white in color and shall meet the following requirements:

Water Closet WC-1 (Wall Hung with Flush Valve): Water closet shall be vitreous china, siphon jet, elongated bowl, 1.6 gallons per flush, wall hung, 1½-inch back spud, hidden remote flush valve and solid plastic open front seat with check hinges. Closet and accessories shall be of following types or equal:

WC-1	American Standard	Crane	Kohler
Closet	"Afwall" 2258.125	"Placidus" 3449	"Sifton" K-4460
Seat (except disabled accessible)	Church 1955.CFR	Olsonite 95	"Lustra" K-4670-C
Flush valve	Concealed flush valve within the service chase space, quiet, concealed, diaphragm type, rough brass with dual filter bypass, self-adaptive infrared sensor with indicator light and manual push button over-ride, non-hold open solenoid operator, chrome plate (for a 2-gang electrical box) with vandal resistant screws, 1"IPS wheel handle and stop shut-off valve (ASSE 1037 and ANSI/ASME A112.19.6 compliant), back-pressure vacuum breaker flush connection and spud coupling for 1-1/2" concealed back spud. 3 year warranty Trap primer elbow provided when shown on the floor plans for connection to local floor drain.		
Carrier	Concealed closet chair carrier with 4-inch outlet connection. Zurn; J.R. Smith; Josam; Jonespec; or equal.		

Water Closet WC-2 same as WC-1 except mounted at handicap height. Water closet shall meet or exceed Americans with Disabilities Accessibility Act Guidelines (ADAAG) and ANSI Standards: A117.1 and A112.19.2.

Water Closet WC-3 for CHP restroom, (Floor Mounted with Flush Valve): Water closet shall be vitreous china, floor mounted, siphon jet, elongated bowl, 1½-inch top spud for exposed flush valve, with solid plastic open front elongated seat with check hinges. Closet and accessories shall be of the following types or equal:

	American Standard	Crane	Kohler
Closet	Madera 3043.102	3H701	Highcliff K-4368C
Seat	Olsonite 95	Church 5321.070	"Lustra" K-4670-C
Flush valve	Exposed, diaphragm type, chrome plated, with oscillating handle, integral control stop, adjustable tail piece and vacuum breaker suitable for use with 1½-inch spud water closets.		

Water Closet WC-4 (Wall Hung mounted at handicap height with Flush Valve): Water closet shall be vitreous china, siphon jet, elongated bowl, 1.6 gallons per flush, wall hung, 1½-inch back spud, hidden remote flush valve and solid plastic open front seat with check hinges. Toilet seta shall be elongated bowl type to match water closet dimensions, check type hinge, open front, no cover, solid white plastic construction with antimicrobial agent. Water closet shall meet or exceed Americans with Disabilities Accessibility Act Guidelines (ADAAG) and ANSI Standards: A117.1 and A112.19.2. Closet dimensions shall be 21.5” length (from back wall to front edge of bowl) and accessories shall be of following types or equal:

Flush valve	Concealed flush valve within the service chase space, quiet, concealed, diaphragm type, rough brass with dual filter bypass, self-adaptive infrared sensor with indicator light and manual push button over-ride, non-hold open solenoid operator, chrome plate (for a 2-gang electrical box) with vandal resistant screws, 1”IPS wheel handle and stop shut-off valve (ASSE 1037 and ANSI/ASME A112.19.6 compliant), back-pressure vacuum breaker flush connection and spud coupling for 1-1/2” concealed back spud. 3 year warranty Trap primer elbow provided when shown on the floor plans for connection to local floor drain.
Carrier	Concealed closet chair carrier with 4-inch outlet connection. Zurn; J.R. Smith; Josam; Jonespec; or equal.

Urinal U-1: Urinal shall be vitreous china, 1.0 gallon per flush, wall hung, washout, ¾-inch back spud, integral shields, spreader and trap. Urinal and valve shall be of following types or equal:

	American Standard	Crane	Kohler
Urinal	"Washbrook" 6506.011	7398	ER
Flush valve	Concealed diaphragm type, chrome plated, with oscillating handle, integral control stop, adjustable tail piece and vacuum breaker suitable for use with ¾-inch spud urinals.		

Urinal (Disabled Accessible)U-2: Same as U-1 except mounted to handicap height. Urinal and valve shall meet Americans with Disabilities Accessibility Act Guidelines (ADAAG).

Lavatory (Wall-mounted) L-1: Lavatory shall be vitreous china, with rear overflow, self draining deck, for concealed wall support, vitreous china shroud/knee guard, center hole only to be used for push-button cold-water-only fixture, dimensions 21-1/4” wide extended 22” from wall. Lavatory and accessories shall be of the following types or equal:

	American Standard	Crane	Kohler
Lavatory	“Murro” 0955.000	--	Chablis K-2083-1
Drain	--	--	K-8998
Supplies	Brass Craft FR1711C	--	K 7605P
Faucet	refer to L-1,2,3	--	refer to L-1,2,3
Trap	1¼-inch chromium plated brass bent tube adjustable 17-gage minimum thickness, field cut to fit shroud.		
Carrier	Concealed wall mounted carrier with leveling screws and locking devices; Zurn, J.R. Smith, Josam, Wade, Jonespec, or equal.		

Lavatory (Wall Mount) L-2, L-3 (Family Rooms): same as L-1 except mounted to handicap height. Lavatory shall meet Americans with Disabilities Accessibility Act Guidelines (ADAAG).

Stainless Steel Sink SS-1: Breakroom stainless steel sink, 18 gage seamless drawn 304 stainless steel, self-rimming, 8” deep double bowl, 33” x 22” overall dimension, satin finish, underside sound deadening coating, 3-1/2” drain outlets, each with removable basket strainers with integral stopper. Deck mounted chrome faucet with 9” spout swivel, swivel neck chrome aerator & deck mounted push lever type plastic hand spray assembly, and deck mounted chrome pump action chromed liquid soap dispenser with ½ pint storage bottle. Sink and accessories shall be of the following types or equal:

	Elkay	Just	Weststar
Wash sink	Pacemaker LR-250		
Faucet	LK-4361-F		
Soap Dispenser	LK-313-CR		
Rinse Hose	LK-3717		
Strainer	LK-35		
Trap	1½-inch chromium plated brass exposed bent tube adjustable 17-gage minimum thickness.		
Eye Wash	EEW-1, Emergency Eye Wash, further described below		

Mop Sink MS-1: Mop sink (janitor sink) shall be Terrazzo receptor manufactured of tan and white marble chips cast in white Portland cement set in 16 gauge reinforcing wire to produce a compressive strength of no less than 3000 psi, shoulders shall be no less than 24” high inside and not less than 1-3/4” wide, galvanized steel flange cast integral and extended at least 1” above splash shoulder on two sides, stainless steel protective cap cast on drop front edge, brass cast-in-place drain body, matching flat chrome strainer, exposed terrazzo surfaces ground and polished with all hole/pits to be grouted and sealed. Matching back splash wall guard panels for two side walls. Matching faucet shall be wall mounted rough chrome finished brass, vacuum breaker, double stops for both hot and cold water valves, hose end connection, mop hanging bracket support, 60” extension hose with wall mount toggle clamp, separate wall mount mop hanger bar with 3 toggle support grips, stainless steel hat frame. Sink and accessories shall be of the following types or equal:

	American Standard Florestone	Stern Williams	Swan
Mop sink	Model 95		
Strainer	MR-375		
Faucet	MR-371		

Water Heater (Electric) EWH-1:

Water heater shall be minimum capacity as shown on plans, designed for minimum 125 psig, interlocking (non-simultaneous) or single element, glass lined, and equipped with aluminum/stainless steel or magnesium anodes, cold water drop tube, valved drain, high density R-12 minimum insulation and finished with a steel jacket with baked enamel finish. Water heater shall meet the requirements of the California Energy Commission.

Water heater shall be equipped with an UL labeled, tank mounted pressure and temperature relief valve sized for maximum input. A.O Smith Promax ELJC-20, Bradford White, or approved equal.

Drinking Fountain(Disabled Accessible, Wall Mounted):

Drinking Fountain DF-1: shall be wall mounted, wheelchair accessible. Features shall include dual height, 14 gage 304 stainless steel finish, front facing push button valves, polished chrome-plated forged brass bubbler head, integral basin shank, bubbler guard, anti-squirt vandal resistant head, bowl type strainer with positive rubber seals molded onto a fine 60 micron mesh screen, diaphragm pressure regulator with fully adjustable flow, vandal resistant bottom plate, low profile trap, heavy duty stainless steel covered wall mounting plate. Fountain shall meet ANSI/NSF Standard 61 Section 9, California Proposition 65 and the Federal Safe Drinking Water Act.

Emergency Eyewash and Shower:

Accessible Emergency Eye Wash EEW-1: Sink (SK-1) mounted polished chrome-plated brass single action swing-down to activate eye/face wash, twin water flow heads, ½” slip joint piping connection. Eyewash heads shall be green ABS plastic with integral flip top dust cover that automatically release with flow of water, universal sign 8”x11”. Certified by CSA to meet ANSI Z358.1.

Accessible Emergency Eye Wash EEW-2: Wall mounted eye/face wash with round 11” stainless steel receptor, 16 ga. stainless steel wall support bracket, twin water flow heads supported from one-piece electropolished stainless steel yoke, integral flip top dust covers that automatically release with flow of water, chrome plated brass stay-open ball valve with chrome plated brass face plate flow release handle, chrome plated brass in-line 50x50 mesh strainer with service plug, chrome plated brass 1-1/2” tailpiece, universal sign 8”x11”.

Soap Dispenser (LSD-1): Plunger type dispenser, vandal resistant chrome-plated brass, leak free buna-N o-ring seals, with matching individual wall mounted clear plastic soap dispensing storage containers, minimum ½ pint volume, with 3/8” plastic tubing kit.

PART 3 - EXECUTION

INSTALLATION

All finish for exposed metal on any fixture, including wall flanges, bolts, nuts and washer, shall be polished chrome plated.

Fixtures shall be sealed to wall or floor with silicone caulk bead.

All exposed metal surfaces on fixture supports shall be enameled to harmonize with fixtures.

Wall mounted fixtures shall be installed on concealed chair carriers designed to support weight of fixture from the floor or supported from the concrete backwall, made for the specific fixture to be supported and for the particular installation conditions.

All fixtures, including showers, shall be provided with accessible metal stop valves.

Hot water supply, trap and tailpiece on lavatories shall be wrapped with insulating material.

Flush valves for fixtures designated on the plans as disabled accessible shall be installed so that the valve handle is on the widest side of the toilet space.

FIXTURE MOUNTING HEIGHTS

Unless otherwise noted, fixtures shall be mounted at the heights shown on the Architectural plans.

Service Sink: Service sink double faucet shall be mounted on wall above sink back with spout outlet face 16 inches above service sink rim.

Mop Sink: Mop sink double faucet shall be mounted on wall above sink back with spout outlet face 36 inches above the floor.

Water Heater: Water heater shall be installed on an 18” raised platform specifically used for water heater support, with seismic restraints attached to adjacent concrete wall, inlet ball valve, outlet side water expansion tank braced to wall, insulating connections, and ¾-inch pressure and temperature relief drain pipe with threaded steel pipe braced along the wall and extended to direct flow/release into the adjacent mop sink.

Emergency Eye Wash EEW-1: shall be mounted integral to the break room sink SK-1. Mount sign on wall immediately next to the eyewash unit.

Emergency Eye Wash EEW-2: shall be wall mounted using the factory provided wall support to set the wash water outlet at 36" above floor. Drain outlet from the wash basin shall be 1-1/2" type L copper braced along the wall and extended to the adjacent mop sink.

FIELD QUALITY CONTROL

Testing:

The Contractor shall test piping in accordance with the requirements specified elsewhere in these special provisions.

All installed fixtures shall be tested for proper operation after all plumbing work has been completed.

12-15.04 HEATING, VENTILATING AND AIR CONDITIONING EQUIPMENT AND SYSTEMS

PART 1 - GENERAL

Scope: This work shall consist of furnishing, installing and testing heating, ventilating and air conditioning (HVAC) equipment and systems in accordance with the details shown on the plans and these special provisions. The performance rating and electric service of the HVAC equipment shall be as shown on the plans.

Temperature Controls: Thermostats, relays, timer switches, and other sensor type control devices required for this work shall be furnished and installed by the supplier of the heating, ventilating and air conditioning equipment. All temperature control wiring shall be furnished and installed in accordance with the requirements specified in Section 12-16, "Electrical," of these special provisions.

Codes and Standards:

Equipment and systems shall conform to California State Energy Commission Regulations and, where applicable, shall be American Refrigeration Institute (ARI), American Gas Association (AGA), Sheet Metal and Air Conditioning Contractors National Association, Inc. (SMACNA), and Air Movement and Control Association (AMCA) approved for performance ratings and application shown on the plans.

Any appliance for which there is a California standard established in the Appliance Efficiency Standards may be installed only if the manufacturer has certified to the Commission, as specified in those regulations, that the appliance complies with the applicable standards for that appliance. Space conditioning equipment may be installed only if the manufacturer has certified that the equipment meets or exceeds all applicable efficiency requirements listed in the Energy Efficiency Standards.

PART 2 - PRODUCTS

HEATING AND COOLING UNITS

Heat pump:

Electric resistance heater shall be supplied by the heat pump manufacturer, factory installed and shall be pre-wired for convenient hookup.

Heat Pump (Wall Mounted) HP-1: Heat pump shall be wall mounted, through-the-wall type with backup electrical resistance heating, rotary type compressor, and shall include slide-out chassis design, thermostat, adjustable discharge grilles, multi-speed fan, and integral thermal overload protection. Exterior grille shall be added architectural aluminum grille for added protection from physical abuse.

FANS AND VENTILATORS

Solar Exhaust Fans: Solar roof fans shall be roof mounted solar powered with minimum 10 watt photovoltaic high impact resistant panel. Motor shall be high performance, long lasting with 1.38 volt direct current operation, brushless with double shielded ball bearings, whisper quiet, manufactured to industry standard ISO 9001 certification. Canted fan blade shall be 5 wing polymeric design for high CFM output and low noise. Housing shall be powder coated steel with non corrosive polymeric vent screen and seamless one piece steel flashings to be coordinated with the roofing contractor for leak proof, weather light installation. Solar roof mount exhaust fans shall be Solar Star by Solatube; Cyclone by Ecovantage Energy Inc.; Natural Light by Big Frog Mountain; or equal.

Exhaust Fan (Wall Mounted)EF-1 serving the CHP restroom: Exhaust fan shall be wall mounted, AMCA certified and shall be equipped with grille, metal housing, backdraft damper, centrifugal fan wheel and bird screen. Fan motor and fan assembly shall be isolated from base with rubber vibration isolators. fan motor shall have integral thermal overload protection. Wall exhaust fan shall be Panasonic, Jenn-Air; Carnes; EWDA; Penn; or equal.

Exhaust Fan (Wall Mounted) EF-2 serving the electrical room: Exhaust fan shall be wall mounted, AMCA certified and shall include factory matching support housing, inlet guard screen. Fan shall be isolated from base with rubber-in-shear isolators. Fan motor shall have integral thermal overload protection. Wall fan shall be Greenheck model S-1 12" fan diameter; Penn; Acme; or approved equal.

Surface Mounted Electric Heater (H-1): Surface Mounted Electric heater, 1000 watts capacity, one-piece, permanently lubricated fan powered, 22 gauge case with 18 gage grille, painted white baked enamel frame, surface mounted, integral thermostat, thermal overload, with field conversion kit to reduce output from 2000 watts to 1000 watts.

Ceiling Fan: Ceiling fan shall be Modern Fan Ball, Model # MO-BALBA52ALHLNC; Minka Air Como Model # MF-F603-BN; Montecarlo Studio Model # MC-3SU54BP; or equal. Ceiling fan shall be complete with 3 speed motor, blades, down rod 24 inches long and wall transmitter and receiver control. Housing and blades may be of brushed aluminum, brushed pewter or brushed nickel.

HVAC CONTROLS

AUXILIARY HVAC COMPONENTS

Unless specified herein, all components shall be sized and have the characteristics as shown on the plans.

PART 3 - EXECUTION

INSTALLATION

Heaters:

Electric wall mounted heaters and through-the-wall heat pump shall be attached to the concrete opening with anchor bolts as detailed on the drawings.

Condensate Drains: Condensate draining from the break room wall mounted heat pump is intended to align with the architectural planter box directly underneath the planter box.

FIELD QUALITY CONTROL

Pre-test Requirements:

Before starting or operating systems, equipment shall be cleaned and checked for proper installation, lubrication and servicing.

The Contractor shall replace or revise any equipment, systems or work found deficient during tests.

All automatic operating devices which are pertinent to the adjustment of the aforementioned air systems shall be set and adjusted to deliver the required quantities of air and at temperatures specified by the Engineer. All control work shall be done in collaboration with the control manufacturer's representative.

Project Completion Tests:

The Engineer shall be notified at least 3 working days in advance of starting project completion tests. Completion test shall include operating the thru-the-wall heat pump in the cooling cycle and heating cycle to verify proper operation and air flow. The CHP unit heater will be operated to verify on-off operation as operated by the integral dial thermostat.

12-15.05 PLUMBING BOOSTER SYSTEM

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of the furnishing and installing the packaged booster water pump skid and associated domestic water tank in accordance with the details shown on the plans and these special provisions. All equipment described in this specification is intended to be mounted indoors in a ventilated (wall louvered) chase space concurrently used as the plumbing chase area.

Controls: Conduit and conductors to be installed between the Packaged Booster Water Pump Skid (PS-1), Domestic Water Tank (ST-1), and the existing well water control wiring is intended to be installed by under the electrical contractor portion of the project. All flow control and pump control wiring shall be furnished and installed in accordance with the requirements specified in Section 12-16, "Electrical," of these special provisions.

QUALITY CONTROL

Packaged Booster Water Pump Skid (PS-1) shall be UL listed and approved for potable water service.

Domestic Water Tank (ST-1) shall comply with FDA approved interior coating suitable for potable water service.

Manufacturer of the Packaged Booster Water Pump Skid (PS-1) and Domestic Water Tank (ST-1) shall have successfully manufactured these types of systems for 5 years.

The allowable size of the pump skid PS-1 and water tank ST-1 is limited to the dimensions shown on the mechanical drawings floor plans (and the architectural drawings for the ingress doorway dimensions). The components of the skid and/or tank must be properly positioned so as to facilitate installation and removal of the skid as a whole and allow service clearance for regular service and inspection.

The piping diagrams show on the drawings are diagrammatic and do not include all of the requires components and accessories as detailed in this specification.

Seismic Calculations:

Provide seismic calculations and floor attachment details to show compliance with Seismic zone 4 with a safety factor per Cal Trans standards. The design shall be coordinated with the structural engineers slab thickness and strength.

Separate calculations shall be provided each for the Packaged Booster Water Pump Skid (PS-1) and Domestic Water Tank (ST-1).

Shop Drawings:

Provide shop drawings as described in section .

Provide 6 sets of shop drawings for review/stamping by the engineer-of-record.

Shop drawings shall include: individual factory cut-sheet data for each component used in the system, piping diagram, dimensional diagrams in all 3 views, controls diagrams, controls description of operation using plain language terms, wiring diagram.

Marker arrows will be used throughout the drawings to indicate which specific portion of the factory cut-sheet data applies specific to the project.

Operating Manual:

Manuals shall contain all information needed to operate and maintain all system components provided in the skid package. It shall be presented and arranged in a logical manner for efficient use by the Owner's operating personnel. The information provided shall include, but not be limited to, the following:

1. Equipment mfr, make, model number, size, etc.
2. Dimensional and performance data for specific unit provided.
3. Basic description of operation. This is intended for the non-technical person to understand how the systems works (not intended to describe details of the systems operation).
4. Detailed description of operation. This is intended for the technical user to understand the system operation and to understand the details of how the control system operates. Control values and setpoints are intended to be included in this description.
5. Manufacturers' recommended operating instructions as appropriate.
6. Manufacturers' recommended lubrication and servicing data, including frequency of service, type of service and description of lubricants required.
7. Complete parts list including reordering information, recommended spares and anticipated useful life (if appropriate).
8. Omit extraneous catalog and performance data.
9. Date that the unit was placed into warranty operating service.
10. Copy of the warranty period and contact information for warranty service.

Factory Testing:

After completion of factory assembly of the Water Pump Skid (PS-1), the entire system (with the pressure relief removed) shall be pressure tested to 100 psi and held for 30 minutes. Make corrections to resolve any leaks and retest. Provide a certificate indicating that the pump skid has been tested to be free of any leaks.

PART 2 - PRODUCTS

Domestic Water Storage Tank (ST-1):

Tank shall be horizontal mounted, 42" diameter by 108" overall length, with integral welded steel footings with 550 gallon tank volume. Footings to support the tank 12" from bottom of tank to finished floor (allowing access to install the tank support bolts). Footings shall be carbon steel designed to attach to the mezzanine slab floor using two saddle supports totaling four floor support points. Support points must stay within the plan view dimensions of the tank (cannot extend beyond edge of tank due to possible wall conflicts).

Tank shall be constructed of ASTM A-36 carbon steel.

All interior surfaces of the interior tank/access assembly shall be coated with an FDA approved epoxy suitable for potable water service.

Tank exterior, integral footings and access assembly shall be coated with red oxide primer and grey enamel paint.

Tank shall be provided with tank fitting accessories including: 16" inspection manhole with flanged cover plate with interior facing side coated with FDA approved epoxy suitable for potable water service, fittings for level sensing probe/control, level sight glass, drain, top inlet fill port (to receive a 2" supply water pipe) with stilling well, fitted 3/16" stainless steel mesh screen with mating clamping rings for tank fill air gap connection, fitting for liquid level sensor probe, 3" flanged tank outlet for connection to booster pump system.

Tank pipe connections 3" and larger shall be welded stainless steel with flanged outlet connection. Tank pipe connections 2" and less shall be carbon steel pipe with male pipe threaded connections.

Water Level Controller Assembly

Tank accessories shall include a column type water level controller factory pre-piped for use by the tank level sensor (described under the Packaged Booster Water Pump Skid).

Assembly shall include tank isolation shut-off valve with union connections (to allow removal of sensor column without needing to drain the tank), ½” drain valve hose end connector with brass cap, gasket and retaining chain, NSF approved air vent assembly (to vent trapped air within the tank level column controller pipe).

All piping shall be type L copper with wrought copper fittings. Brass pipe or stainless steel pipe is an acceptable alternate.

Upper tank connection serving this assembly shall be oversized to accommodate the Air Vent/Overflow Assembly. Size shall be minimum 3”.

Water Level Viewing Assembly

Water level viewing gauge glass suitable for potable water factory pre-piped using the tank connections from the Water Level Controller Assembly. Each connection will be provided with a combination union shut-off valve for easy removal/servicing.

Glass assembly shall be protected from breakage using two removable brass guard rods.

Viewing range of water level shall be no less than 2” from the bottom of the tank up through 2” from the top of the tank. Multiple viewing glasses are allowed provided that each assembly includes isolation valves with union connections.

All piping shall be type L copper with wrought copper fittings. Brass pipe or stainless steel pipe is an acceptable alternate.

Air Vent/Overflow Assembly

A tank air vent and overflow assembly shall be provided using the upper tank connection concurrently used by the Water Level Control Assembly. The Air Vent/Overflow device shall be mounted inverted (facing down) and provided with a stainless steel mesh screen outlet of approved size and mesh pattern.

Packaged Booster Water Pump Skid (PS-1):

Pump Skid PS-1 shall be a pre-engineered packaged system for delivering domestic cold water to restroom facilities and the landscape irrigation system.

The pump package shall include welded steel base frame, domestic water pumps, control panel, pump speed controller (VFD), pump logic controller, hydrostatic pressure tank, water totalizing meter, interconnecting piping, pre-wired control panel, discharge safety pressure relief, self sealing pressure tap for field pressure gauge on discharge side of pumps, ¼” threaded connection with brass valve (for field installed pressure gage) on the discharge side of the pumps, and pipe accessories.

Pumps

In-line vertical mount multi-stage type, stainless steel pump body and impellers, designed to operate at variable speeds.

Each pump shall be provided with stainless steel flange connection including associated bolts, washers and nuts.

Pump motors shall meet all NEMA specifications and shall be 3 HP with TEFC frame, designed to operate on VFD applications with variable torque, 1.15 service factor, and non-overloading.

Each pump shall be designed to provide 45 gpm at 65 psi.

Each pump shall be capable of operating at a net pump suction head (NPSH) of 3 feet absolute.

Hydrostatic Pressure Tank:

Tank shall be ASME section VIII for unfired pressure vessels for 125 psi working pressure.

Tank shall have an internal heavy duty butyl rubber bladder permanently separating the tank air from the water side.

Tank volume shall be 70 gallons with an acceptance volume of 52.8 gallons.

Based on an initial tank pressure of 40 lbs and a final pressure of 65 lbs, the drawdown coefficient shall be no less than 0.30. Nominal tank useable gallons shall be 21 gallons.

Tank accessories shall include: lift ring, guarded charging valve using standard 302"-32 connection, 1-1/2" threaded system pipe connection, integral mounting base, factory primed and painted.

Water Totalizing Meter

Water meter shall be Badger; Neptune; Rockwell; Hersey; or approved equal.

Water meter shall meet AWWA Standard C-700-77.

Water meter shall be consisting of three major assemblies: a roll-sealed register, a cast bronze main case, and a nutating disk main measuring chamber.

Roll-sealed register shall provide low torque magnetic drive, impact resistant flat glass lens, 1:1 ratio low flow leak detection, tamper resistant seal pin, date of manufacture and model, and shall totalize water volume using a 6-wheel display for (100,000,000 gallons) U.S. Gallons as the units of measure.

Cast bronze main case shall provide durable corrosion resistance, electrical grounding continuity, and have 2" flanged end connections.

Nutating disc shall provide positive measuring displacement, wide efficiency range with float chamber unaffected by meter position.

Water meter shall be mounted on the discharge side of the pumps and shall create no greater than 1.5 PSID at 45 gpm flow rate.

Control Panel

Control panel shall be NEMA 3R enclosure with UL Listing, provided with all pump skid electrical and electronic components mounted in a single panel. Any code required separation of power and control wiring will be factory designed within the panel.

Mounting location of the control panel onto the pump skid shall be coordinated with the physical arrangement of the room in which it is being installed including 42" access clear in front of the control panel and access to service and/or replace components on the pump skid.

Provide motor overload protection, local-off-remote switch, fused door interlock disconnect.

The controller shall be capable of receiving 2 discrete analog inputs for zone pressure sensing.

Control panel will be provided pre-wired with color coded wiring, wiring arranged in cable path trays and terminal strips. Terminal strip connection points will be provided for all field wired interconnection.

All wiring within the control panel shall terminate on a component/device or a terminal strip – wire splices are not allowed.

Panel door shall be provided with a panel pocket used to store a folded copy of the panel wiring diagram.

Pump Speed Control (VFD)

Each pump will be provided with a VFD control.

VFD shall be pulse width modulation type, microprocessor controlled design, shall have balanced DC link reactors to minimize power line harmonics. VFD without a DC link reactor shall provide a 3% impedance line reactor. VFD shall include output speed display, output voltage display, motor amps display, elapsed time meter, and critical frequency avoidance.

Pump Logic Controller (PLC):

PLC shall function to a proven program that safeguards against damaging hydraulic conditions of pump flow surges and hunting; and shall be capable of performing the following pressure booster functions:

Low suction pressure cutout to protect the pumps against operating with insufficient suction pressure. This function shall reset automatically.

High system pressure cutout to protect the piping system against high-pressure conditions. This function shall require manual reset.

No flow shutdown to turn the pumps off automatically when system demand is low enough to be supplied by the hydro-pneumatic tank. No-flow shutdown shall not require external flow meters, flow switches, nor pressure switches to determine when a low flow conditions exists.

Analog input for a flow sensor shall be provided. This input shall serve as the criteria for the end of the curve protection algorithm.

Pressure Sensor / Transmitters:

Provide factory mounted single point pressure sensor transmitter(s) as part of the pump skid package. Unit shall transmit an isolated 4-20 mA DC signal indicative of process variable to the PLC via standard two wire 24 VDC system. Unit shall have stainless steel wetted parts with one 0.25" male NPT process connection. It shall be protected against radio frequency interference and shall have a watertight, NEMA 4 electrical enclosure with a 0.5" NPT conduit connection. Accuracy shall be within 0.25% of full span.

Liquid Level Sensor:

Sensor shall be intrinsically safe using buoyancy type reed switch devices.

Reed contactor rating shall be compatible with the interface to the control panel.

Sensor shall be mounted using a 2" NPT threaded connection at the top of the tank level pipe assembly (provided as part of the storage tank).

Sensor enclosure shall be NEMA 4X rated, with all polypropylene wetted parts compatible for domestic cold water use.

The sensor length shall match the tank location being served. Each reed switch along the length of the device shall be set at the level needed to perform the control function described in the Sequence of Operation.

Piping

All piping within the Pump Skid (PS-1) shall be type L copper with wrought copper fittings except that the pump suction manifold and the pump discharge pipe manifold shall be stainless steel. Alternate construction is allowed to use stainless steel for all piping and fittings.

Valves (shut-off):

All valves shall be approved for domestic water usage.

Valves ¾" to 3": 3-piece bronze body, full port, 90 degree turn handle.

Valves ¼" to ½": 2-piece bronze body, 90 degree turn handle.

As a minimum, valves shall be located at each pump suction, pump discharge (downstream of check valve), main supply pipe outlet, and supply pipe pressure tap.

Valves (check):

All valves shall be approved for domestic water usage. Valves shall be swing check type mounted vertically. As a minimum, check valves shall be located immediately downstream of each pump discharge.

Steel Base Frame:

Entire base frame shall be constructed from structural steel forms including angle steel, C-channel and box frame. Lifting lugs shall be designed as a part of the base without extending beyond the edges of the base.

Hold-down bolts will be located at each corner of the frame. The holes will be located within the outer edge of the frame (to avoid conflict with the site location wall layout).

Painting:

The entire assembled unit shall be prepared for painting.

Components that shall not be painted include: the water meter, stainless steel components, labels, hydrostatic tank (if already factory painted), entire pump, gage faces, factory painted valve handles, stainless steel components, and components already factory painted (painted with a heavy, industrial coating of epoxy enamel paint, after fabrication).

Sequence of Operation:

The system shall consist of a pump logic controller, with an AFD and a manual bypass switch.

Pressure-sensor transmitter located at the expansion tank shall send a 4-20mA input signal to the pump logic controller. Set point for pump operation against design pressure requirements shall be manually adjustable at controller.

The pump logic controller shall compare the signal to the independent, engineer/user determined set points.

When all set points are satisfied by the process variable, the pump speed shall remain constant at the optimum energy consumption level. If the input from the optional flow sensor indicates that the operating pumps are approaching the end of the curve point, the controller shall automatically stage on the lag pumps as required to bring all pumps back to an acceptable operating point.

The pump logic controller shall continuously scan and compare each process variable to its individual set point and control to the least satisfied zone.

Upon VFD fault(s), the pump controller shall display an alarm condition through a plain English message.

VFD fault indication shall be continuously displayed on the operator interface of the pump logic controller until the fault has been corrected and the controller has been manually reset.

The VFD's shall be capable of being locked out of service and the pump/motors may be manually started across-the-line with motor overload protection.

In the event of the failure of a zone sensor/transmitter, its process variable signal shall be removed from the scan/compare program. Alternative zone sensor/transmitters, if available, shall remain in the scan/compare program for control.

Upon sensor failure a plain English warning message shall be displayed on the operator interface of the pump logic controller.

In the event of failure to receive all zone process variable signals, a user selectable number of the VFD's shall maintain a user adjustable speed, reset shall be automatic upon correction of the zone failure.

PART 3 – EXECUTION

Install the booster skid and storage tank on the mezzanine slab. Provide stainless steel shims with centered hole to provide leveling of each unit.

Prior to drilling any mezzanine deck support points, verify locations with the structural engineer. Drilling through reinforcing steel within the slab is not acceptable without the structural engineers written approval.

Start-Up Service and Warranty.

The system manufacturer or factory trained representative shall provide start-up of the packaged pumping system. This start-up shall include verification of proper installation, system initiation, adjustment and fine tuning. Start-up shall not be considered complete until the sequence of operation, including all set points has been sufficiently demonstrated to the owner or owner's designated representative. This jobsite visit shall occur only after all hook-ups, tie-ins, and terminations have been completed and signed-off on the manufacturer's start-up request form.

Instruction For Owner's Representatives

Following initial operation of equipment and prior to acceptance of the work, the Contractor shall conduct demonstrations of equipment operation and instruction periods for the Owner's representatives during the time balancing work is being performed.

Instruction shall be provided by the qualified factory representative of the equipment being provided.

Representatives of the Owner who will be present at these meetings may include the Owner, Architect, engineer of record, Cal Trans Administrative, Operating and Maintenance personnel.

General Description of Instruction Periods: Each period shall include preliminary discussion and presentation of information from Operation and Maintenance Manuals with appropriate references to drawings, followed by tours of equipment spaces explaining maintenance requirements, access methods, servicing, and maintenance procedures, pressure settings and available system and equipment adjustments.

Duration of Instruction Periods:

Description	Duration
Water Pump Skid (PS-1) and Domestic Water Tank (ST-1):	2 meetings total at 6 hours each

12-15.06 FIRE PROTECTION SYSTEM

PART 1 - GENERAL

This work shall consist of furnishing and installing a complete fire protection underground water storage tank in accordance with the details shown on the plans and these special provisions.

The fire protection underground water storage tank shall include all equipment, accessories and appurtenances necessary for the complete installation and operation of said system.

SUBMITTALS

Working drawings, material lists, descriptive data, and other submittals specified herein shall be submitted for approval in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and these special provisions.

Unless otherwise permitted in writing by the Engineer, all submittals required by these special provisions shall be submitted within 35 days after the Contractor has received notice that the contract has been approved.

Attention is directed to the provisions in Section 5-1.01, "Authority of Engineer," of the Standard Specifications. The Engineer may request submittals for materials or products where submittals have not been specified in these special provisions, or may request that additional information be included in specified submittals, as necessary to determine the quality or acceptability of such materials or products.

Attention is directed to Section 6-1.05, "Trade Names and Alternatives," of the Standard Specifications. The second indented paragraph of the first paragraph of said Section 6-1.05 is amended to read:

Whenever the specifications permit the substitution of a similar or equivalent material or article, no tests or action relating to the approval of such substitute material will be made until the request for substitution is made in writing by the Contractor accompanied by complete data as to the equality of the material or article proposed. Such request shall be made within a time period not to exceed 35 days after the date on which the contract has been approved, shall be made in ample time to permit approval without delaying the work, but need not be made in less than 35 days after award of the contract.

Work requiring the submittal of working drawings, material lists, descriptive data, or other submittals shall not begin prior to approval of said submittal by the Engineer. Fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete his review within the time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications.

Submittals shall be delivered to the locations indicated in these special provisions. If a specific location is not indicated, the submittal shall be delivered to the Division of Structure Design, Documents Unit, Fourth Floor, Mail Station 9-4/4I, 1801 30th Street, Sacramento, California 95816, telephone (916) 227-8252, or the submittals shall be mailed to the Division of Structure Design, Documents Unit, Mail Station 9, P. O. Box 942874, Sacramento, California 94274-0001.

Each submission of drawings, material lists and descriptive data shall consist of at least 5 copies. Two copies will be returned to the Contractor either approved for use or returned for correction and resubmittal.

Each separate item submitted shall bear a descriptive title, the name of the project, district, county, and contract number. Plans and detailed drawings shall not be larger than 22" x 36".

Working drawings shall show complete layout and details of the tank, equipment and materials to be installed.

The material list and descriptive data shall be complete as to name of manufacturer, catalog number, size, capacity, finish, all pertinent performance ratings, and identification symbols used on the plans and in the special provisions for each unit.

The material list and descriptive data submittals shall include, but not necessarily be limited to, the following:

- Fire Protection Underground Water Storage Tank
- Dry Hydrant
- Tank Vent and Fire Water Tank Sight Gage Assembly
- Deadmen
- Anchor Strap and Connector
- Filter Fabric

Parts lists and service instructions packaged with or accompanying the equipment installed in the work shall be delivered to the Engineer at the jobsite.

Before completion of the project, 3 bound identified copies of the operation and maintenance instructions and parts lists for equipment furnished shall be delivered to the Engineer at the jobsite. Manuals that are inadequate or incomplete will be returned and the Contractor shall resubmit adequate and complete manuals at no expense to the State. Manuals shall be included for the following equipment:

- Fire Protection Underground Water Storage Tank
- Tank Vent and Fire Water Tank Sight Gage Assembly

Manufacturer's warranties and guarantees for equipment and materials installed in the work shall be delivered to the Engineer at the jobsite.

MAINTENANCE INSTRUCTIONS

Before completion of the project, one set of maintenance instructions for the tank and other equipment shall be framed, mounted and securely fastened to the interior wall of the pipe chase, at a convenient location approved by the Engineer.

PART 2 - PRODUCTS

Fire Protection Underground Water Storage Tank: The fire storage tank shall be factory-manufactured single-walled fiberglass cylindrical tank meeting AWWA Standard D120 standards. The manufacturer shall include these appurtenances with the storage tank: a tank vent and water sight gage assembly, manway, a dry hydrant, pre-fabricated deadmen or forms, anchor straps, and connectors. The appurtenances shall meet NFPA 1142 standards. The tank capacity and location of appurtenances shall be as shown on the plans. All construction or appurtenance joint(s) shall be above the tank waterline. Adhesives and sealants shall be waterproof, corrosion resistant, and approved for the intended application.

Dry Hydrant: The dry hydrant pipe shall be 6-inch threaded Schedule 40 galvanized steel and PVC pipe with an anodized black aluminum National Hose Thread (NHT) 4½-inch male fire connection fitting with a bright yellow colored lockable cap. The pipes shall be connected using a 6-inch Schedule 80 PVC full coupling. Threaded fittings shall withstand at least 300 foot pounds of torque.

Tank Vent and Fire Water Tank Sight Gage Assembly: The tank vent and fire water tank sight gage shall be an integrated assembly. The sight gage shall be capable of indicating if water level in the tank is full or in need of replenishment. The pipe diameter of the assembly shall be 8 inches with a 10-inch diameter adapter flange. Suitable gasket shall be provided with adapter flange. The pipe material of the assembly shall be Schedule 40 PVC.

Deadmen: The deadmen shall be either pre-fabricated or cast-in-place. The deadmen shall be part of the tank package and pursuant with the tank manufacturer's instructions. The deadmen shall be sized to prevent tank floatation.

Anchor Strap and Connector: The anchor strap shall be fiberglass compatible material and supplied by tank manufacturer. The number and location of straps shall be as specified by tank manufacturer. The connector shall be as recommended by tank manufacturer.

Backfill and Bedding:

Pea Gravel: Pea gravel shall be a mix of rounded particles, sizes between 1/8 inch and 3/4 inch. The pea gravel shall conform to the specifications of ASTM C-33, paragraph 9.1, sizes 6, 67, or 7. No more than 5% by weight of the backfill shall pass through a #8 sieve. The material shall be washed, free-flowing, and free of ice, snow, and debris.

Crushed Stone: Crushed stone shall be a mix of angular particles, sizes between 1/8 inch and 1/2 inch. The crushed stone shall conform to the specifications of ASTM C-33, paragraph 9.1, sizes 7 or 8. No more than 5% by weight of the backfill shall pass through a #8 sieve. The material shall be washed, free-flowing, and free of ice, snow, and debris.

Filter Fabric:

Filter fabric shall be commercial quality, chemically stable, non-biodegradable, ultraviolet stabilized, 100 percent polyester, 100 percent polypropylene or 100 percent combined polyester and polypropylene, nonwoven, needle punched permeable geotextile.

Filter fabric shall be shipped in packaging that shall protect filter fabric from ultraviolet radiation and abrasion during storage, and handling.

Filter fabric shall conform to the following requirements:

Property	Value	Test Designation
Average roll weight	4.0 ounces per square yard, min.	ASTM D 1117
Grab tensile strength, Pounds	MD 120 ±15 XMD 110 ±15	ASTM D 5034, 5035 1 inch grip
Grab elongation	MD 50 min.	ASTM D 5034, 5035
Trapezoidal tear strength, Pounds	MD 50 ±10 XMD 45 ±10	ASTM D 1117
Water passage rate	100 gallons per minute per square foot, min.	ASTM D 4491 (Constant head, 2 inches)
Thickness, mils	55 min.	ASTM D 1777
Permeability, cm per sec.	0.3 cm per sec. ±0.1 cm per sec.	ASTM D 4491 (Constant head, 2 inches)
AOS (Apperture. opening size)	0.21 mm, min.	ASTM D 4751

Miscellaneous Metals: Angle iron, steel supports and other miscellaneous metals required for the water supply system shall be in accordance with the requirements specified in Section 75, "Miscellaneous Metal," of the Standard Specifications.

PART 3 - EXECUTION

INSTALLATION

Fire Protection Water Storage Tank:

Underground fire protection water storage tank, deadmen, and other appurtenances shall be installed in accordance with the plans, these specifications, codes and standards and strict accordance with the manufacturer's installation instructions and as approved by the Engineer.

Water storage tank shall be filled to operating level with clean, fresh water upon completion of construction and testing.

The flanged manway cover shall be bolted securely and adhered with tracer tape along the circular edges of the cover.

Pipe Sleeve: PVC pipe sleeves shall be provided where each pipe passes through concrete wall, footing, or slab. Inside diameter of sleeves shall be at least 3/4 inch larger than outside diameter of pipe. Sleeves shall be installed to provide at least 3/8-inch space all around the pipe along the full depth of concrete. Space between pipes and pipe sleeves shall be silicone caulked watertight.

TESTING

Fire Protection Underground Water Storage Tank:

Before installing the tank, a visual air and soap test shall be conducted in strict accordance with AWWA D120-02 standards, section 5.2.3.2. The maximum test pressure for 10-foot diameter tanks and smaller shall be 5 psig. The maximum test pressure for 12-foot diameter tanks and larger shall be 3 psig.

After installation is completed and before completion of backfilling, each tank shall be filled with water through the dry hydrant (with the 90° fitting removed) to the top of the pipe. Cover the top of pipe to minimize evaporation. Remove cover and measure the water loss after a twenty-four (24) hour period. No tank will be accepted if the water level falls more than 0.5 inches. Repairs or replacements, if necessary, shall be made at the Contractor's expense. The Engineer shall be notified at least 48 hours in advance of starting the testing.

After backfilling and after all tank appurtenances are installed, verify the performance of the tank by having the local fire department pump either 10% of the tank volume or after 2 minutes of pumping, whichever comes first. Refill the tank with water to proper level after this performance test.

SECTION 12-16. ELECTRICAL

12-16.01 ELECTRICAL WORK

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of performing electrical work in accordance with the details shown on the plans and these special provisions.

Electrical work shall include furnishing all labor, materials, equipment and services required to construct and install the complete electrical system shown on the plans and the work of installing electrical connections for the thermostats, motors, and controls specified elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of conduits and other facilities and location of equipment is to be governed by structural conditions and other obstructions, and shall be coordinated with the work of other trades. Equipment requiring maintenance and inspection shall be located where it is readily accessible for the performance of such maintenance and inspection.

Related Work: Earthwork, foundations, sheet metal, painting, mechanical and such other work incidental to and necessary for the proper installation and operation of the electrical work shall be done in accordance with the requirements specified for similar work elsewhere in these special provisions.

CLOSEOUT SUBMITTALS

Operation and Maintenance Manuals:

Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be in a bound manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material will be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

Manuals shall be submitted for the following equipment:

Light Fixtures
Lighting Control Equipment
Electrical Panels

QUALITY ASSURANCE

Codes and Standards: All work performed and materials installed shall be in accordance with the CEC and the California Code of Regulations, Title 8, Chapter 4, "Electrical Safety Orders." .

Warranties and Guarantees: Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

PART 2 - PRODUCTS (Not applicable)

PART 3 - EXECUTION

TESTING

After the electrical system installation work has been completed, the electrical system shall be tested in the presence of the Engineer to demonstrate that the electrical system functions properly. The Contractor shall make necessary repairs, replacements, adjustments and retests at his expense.

12-16.02 BASIC MATERIALS AND METHODS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing conduits, conductors, fittings, and wiring devices in accordance with the details shown on the plans and these special provisions.

Conduits, conductors, fittings, and wiring devices shall include those accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the electrical system.

Related Work:

Roof penetrations shall be flashed and sealed watertight conforming to the requirements specified under "Sheet Metal Flashing" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

SUBMITTALS

Product Data:

A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for recessed junction and pull boxes, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2 - PRODUCTS

CONDUITS AND FITTINGS

Rigid Steel Conduit and Fittings:

Rigid steel conduit shall be threaded, full weight rigid steel, hot-dip galvanized inside and outside with steel or malleable iron fittings. Fittings shall be threaded unless otherwise specified or shown on the plans.

Split or three-piece couplings shall be electroplated, malleable cast iron couplings.

Insulated grounding bushings shall be threaded malleable cast iron body with plastic insulated throat and steel, lay-in ground lug with compression screw.

Insulated metallic bushings shall be threaded malleable cast iron body with plastic insulated throat.

Electrical Metallic Tubing (EMT) and Fittings:

Electrical metallic tubing shall be formed of cold rolled strip steel, electrical resistance welded continuously along the longitudinal seam with zinc coating outside and enamel or lacquer coating inside.

Couplings shall be electroplated, rain and concrete tight, gland compression type, steel body couplings with malleable iron nuts.

Connectors shall be electroplated, rain and concrete tight, gland compression type, steel body connectors with male hub, malleable iron nut and insulated plastic throat.

Flexible Metallic Conduit and Fittings:

Flexible metallic conduit shall be fabricated in continuous lengths from galvanized steel strip, spirally wound and formed to provide an interlocking design.

Fittings shall be electroplated screw-in type with malleable cast iron body and threaded male hub with insulated throat.

Liquid Tight Flexible Metallic Conduit and Fittings:

Liquid tight flexible metallic conduit shall be fabricated in continuous length from galvanized sheet steel, spirally wound and formed to provide an interlocking design with an extruded polyvinyl chloride cover.

Fittings shall be electroplated, malleable cast iron body, with cap nut, grounding ferrule, and connector body with insulated throat.

Rigid Non-metallic Conduit and Fittings:

Rigid non-metallic conduit shall be Schedule 40, high impact, nonconducting, self-extinguishing polyvinyl chloride (PVC) rigid non-metallic conduit for direct underground burial.

Couplings shall be PVC, socket type or thread on one end and socket type on the other end as required for the particular application.

Terminal adapters for adapting PVC conduit to boxes, threaded fittings, or metallic conduit system shall be PVC adapters with threads on one end and socket type on the other end.

CABLES AND CONDUCTORS

Conductors:

Conductors shall be stranded copper wire.

Conductor insulation types unless otherwise shown or specified, shall be as follows:

1. Conductors across hinges of control panel enclosures shall be Type MTW.
2. Conductors shall be type XHHW-2 in wet, underground, and outdoor locations.
3. Conductors shall be type THHN in dry locations.

Wire Connections and Devices: Wire connections and devices shall be pressure or compression type, except that connectors for No. 10 AWG and smaller conductors in dry locations may be preinsulated spring-pressure type.

ELECTRICAL BOXES

Outlet, Device and Junction Boxes:

Unless otherwise shown or specified, boxes shall be galvanized steel boxes with knock-outs and shall be the size and configuration best suited to the application indicated on the plans. Minimum size of outlet, receptacle, switch or junction boxes shall be 4 inches square by 1½ inches deep, except that switch boxes for the installation of single switches and outlet boxes for flush-mounted light fixtures shall be 2" x 3" x 1½" deep.

Multiple switches shall be installed in standard gang boxes, unless otherwise specified or shown on the plans.

Cast metal boxes shall be cast iron boxes with threaded hubs and shall be of the size and configuration best suited to the application shown on the plans.

Flush-mounted boxes shall have stainless steel covers, 0.04 inch thick. Cover screws shall be metal with finish to match cover finish.

Unless otherwise shown or specified, surface-mounted boxes shall have galvanized steel covers with metal screws.

Weatherproof junction boxes shall have cast metal covers with gaskets.

Weatherproof switch and receptacle boxes shall have gasketed covers with gasketed hinged flaps to cover switches and receptacles.

Sectional device plates will not be permitted.

Underground Pull Boxes:

Pull boxes shall be high density reinforced concrete box with ultraviolet inhibitor polyethylene etched face anchored in concrete and fiberglass cover with hold down bolts. The polyethylene and fiberglass material shall be fire resistant and show no appreciable change in physical properties with exposure to the weather. No. 3 1/2 pull box shall be Brooks Products, No. 3 1/2; Christy Concrete Products, N9; or equal. No. 5 pull box shall be Brooks Products No. 5; Christy Concrete Products, N30; or equal.

Traffic rated pull boxes shall be high density reinforced concrete box with steel cover with hold down bolts and bonding strap. Pull box and cover shall be designed for H20 loading. No. 3 1/2 pull box shall have inside dimensions of 19¼ inches by 13¼ inches and No. 5 pull box shall have inside dimensions of 27 1/8 inches by 16 1/8 inches.

RECEPTACLES AND SWITCHES

Ground Fault Circuit Interrupter Receptacles, (GFCI): Ground fault circuit interrupter receptacles shall be NEMA Type 5-20R, feed-through type, ivory color, 3-wire, 20-ampere, 125-volt AC, grounding type, specification grade, duplex receptacle with ground fault interruption. Receptacle shall detect and trip at current leakage of 5 milliamperes and shall have front mounted test and reset buttons.

Duplex Receptacles: Duplex receptacles shall be NEMA Type 5-20R, 3-wire, 20-ampere, 125-volt AC, safety grounding, ivory color, specification grade receptacle suitable for wiring with stranded conductors.

Snap Switches: Snap switches shall be 20-ampere, 120/277-volt AC, quiet type, specification grade, ivory color switch with silver cadmium alloy contacts. Switch shall be suitable for wiring with stranded conductors.

Motion Sensor Wall Switches: Motion sensor wall switches shall be wall-mounted, 3-wire, 1500-watt incandescent or fluorescent, off-auto-on with 2 switches, passive infrared sensor switch with adjustable photocell override and time delay and shall operate on 120/277 volts. The sensor switch shall cover a minimum of 900 square feet of floor area, be suitable for installation in a single gang box, and shall have a field of view of not less than 170 degrees. The time delay setting shall be adjustable from 30 seconds to 20 minutes, initially set at 5 minutes. Light level adjustment shall be adjustable from 20 lux to 200 foot-candles, initially set at 70 foot candles.

Motion Sensor Ceiling Switches: Motion sensor ceiling switches shall be ceiling-mounted, 3-wire, 600-watt incandescent or fluorescent, passive infrared sensor switch with adjustable time delay and shall operate on 120/277 volts. The sensor switch shall be suitable for installation in a single gang box, and shall have a field of view of not less than 360 degrees. The time delay setting shall be adjustable from 30 seconds to 20 minutes, initially set at 5 minutes.

MISCELLANEOUS MATERIALS

Warning Tape: Warning tape shall be 4-inch wide and contain the printed warning "CAUTION ELECTRICAL CONDUIT" in bold 3/4-inch black letters at 30-inch intervals on bright orange or yellow background. The printed warning shall be non-erasable when submerged under water and resistant to insects, acids, alkali, and other corrosive elements in the soil. The tape shall have a tensile strength of not less than 155 pounds per 4-inch wide strip and shall have a minimum elongation of 700 percent before breaking.

Pull Ropes: Pull ropes shall be nylon or polypropylene with a minimum tensile strength of 500 pound-force.

Watertight Conduit Plugs: Watertight conduit plugs shall be a hollow or solid stem expansion plugs complete with inner and outer white polypropylene compression plates and red thermoplastic rubber seal. Seal material shall be non-stick type rubber resistant to oils, salt, and alkaline substances normally available at the construction sites.

Anchorage Devices: Anchorage devices shall be corrosion resistant, toggle bolts, wood screws, bolts, machine screws, studs, expansion shields, and expansion anchors and inserts.

Electrical Supporting Devices:

Electrical supporting devices shall be one hole conduit clamps with clamp backs, hot-dipped galvanized, malleable cast iron.

Construction channel shall be 1 5/8 inches by 1 5/8 inches, 12-gage galvanized steel channel with 17/32-inch diameter bolt holes, 1 1/2 inches on center in the base of the channel.

Ground rod(s): Ground rod(s) shall be a 3/4-inch (minimum) galvanized or copper clad steel rod, 10 feet long.

Telephone Outlet Boxes:

Telephone outlet boxes shall be 4-inch square boxes and plates with modular type telephone outlet. Boxes on stud walls shall have plaster ring.

Plates for flush mounting outlets in finished room shall be Type 430 stainless steel, 0.04 inch thick with satin finish.

PART 3 - EXECUTION

INSTALLATION

Conduit:

Rigid steel conduit shall be used unless otherwise shown on the plans or specified in these special provisions.

Electrical metallic tubing may be used in furred spaces and for exposed work indoors above the switch height.

Unless otherwise specified or shown on the plans, flexible metal conduit shall be used to connect suspended lighting fixtures, motors, HVAC equipment, and other equipment subject to vibration in dry locations.

Unless otherwise specified or shown on the plans, liquid-tight flexible metal conduit shall be used to connect motors, HVAC equipment, and other equipment subject to vibration in wet locations.

Rigid non-metallic conduit shall be used at the locations shown on the plans for direct underground burial 30 inches below grade. All risers and elbows through building floors shall be rigid steel.

Conduit Installation:

Conduit trade sizes are shown on the plans. No deviation from the conduit size shown on the plans will be permitted without written permission from the Engineer.

Conduit shall be concealed unless otherwise shown on the plans.

Conduits shall be tightly covered and well protected during construction using metallic bushings and bushing "pennies" to seal open ends.

Rigid non-metallic conduit bends of 30 degrees or greater shall be factory-made long radius sweeps. Bends less than 30 degrees shall be made using an approved heat box.

A pull rope shall be installed in all empty conduits. At least 3 feet of pull rope shall be doubled back into the conduit at each termination.

Locations of conduit runs shall be planned in advance of the installation and coordinated with the ductwork, plumbing, ceiling and wall construction in the same areas and shall not unnecessarily cross other conduits or pipe, nor prevent removal of ceiling tiles or panels, nor block access to mechanical or electrical equipment.

Where practical, conduits shall be installed in groups in parallel, vertical or horizontal runs and at elevations that avoid unnecessary offsets.

Exposed conduit shall be installed parallel and at right angles to the building lines.

Conduits shall not be placed closer than 12 inches from a parallel hot water or steam pipe or 3 inches from such lines crossing perpendicular to the runs.

All raceway systems shall be secured to the building structures using specified fasteners, clamps and hangers.

All metal conduits, metal conduit risers, and metal conduit elbows in contact with soil or concrete shall be wrapped with a double layer of 20-mil thick pipe wrapping tape. Each individual layer shall be overlapped a minimum of 50%.

Single conduit runs shall be supported by using one hole pipe clamps. Where run horizontally on walls in damp or wet locations, conduit shall be installed with "clamp backs" to space conduit off the surface.

Multiple conduit runs shall be supported with construction channel secured to the building structure. Conduits shall be fastened to construction channel with channel compatible pipe clamps.

Raceways of different types shall be joined using approved couplings or transition fittings.

Expansion couplings shall be installed where conduit crosses a building separation or expansion joint.

All floor and wall penetrations shall be sealed water-tight.

Existing underground conduit to be incorporated into a new system shall be cleaned with a mandrel or cylindrical wire brush and blown out with compressed air.

Conduit Terminations:

Rigid steel conduits shall be securely fastened to cabinets, boxes and gutters using 2 locknuts and specified insulating metallic bushing. Electrical metallic tubing shall be securely fastened to cabinets, boxes and gutters using specified connectors. Conduit terminations at exposed weatherproof enclosures and cast outlet boxes shall be made watertight using specified hubs.

Grounding bushings with bonding jumpers shall be installed on all type of conduits terminating at concentric knockouts and on all conduits containing service conductors, grounding electrode conductor, and conductors feeding separate buildings.

Rigid non-metallic conduits shall be terminated inside the underground pull boxes with an approved conduit bushings or fittings. All conduits shall enter the pull box at an angle of 45 degrees or more.

All future conduits terminated in underground pull boxes or exposed indoor and outdoor shall be provided with watertight conduit plugs.

Warning Tape: Warning tape shall be placed over each conduit in a trench. Each warning tape shall be centered over the conduit and shall be placed over the 6 inches layer of sand covering the conduit as described elsewhere in these special provisions.

Conductor and Cable Installation:

Conductors shall not be installed in conduit until all work of any nature that may cause injury is completed. Care shall be taken in pulling conductors that insulation is not damaged. An approved non-petroleum base and insulating type pulling compound shall be used as needed.

All cables shall be installed and tested in accordance with manufacturer's recommendations.

Splices and joints shall be insulated with insulation equivalent to that of the conductor.

Provide 6 inches of slack at each outlet and device connection. If the outlet or device is not at the end of a run of wire, connection shall be made with correctly colored pigtails tapped to the runs with splices as specified herein.

Branch circuit conductors in panelboards and load centers shall be neatly trained along a path from the breaker terminals to their exit point. The conductors shall have ample length to transverse the path without strain, but shall not be so long as to require coiling, doubling back, or cramming. The path shall transverse the panelboard gutter spaces without entering a gutter containing service conductors and, unless otherwise shown on the plans, without entering the gutter space of any panelboard feeder.

All pressure type connectors and lugs shall be retightened after the initial set.

Splices in underground pull boxes and similar locations shall be made watertight.

Junction boxes in furred or accessible ceiling spaces shall be identified with felt-tip pen denoting the circuits contained in the box.

Conductor Identification:

The neutral and equipment grounding conductors shall be identified as follows:

Neutral conductor shall have a white or natural gray insulation except that conductors No. 4 and larger may be identified by distinctive white marker such as paint or white tape at each termination.

Equipment grounding conductor shall be bare or insulated. If insulated, equipment grounding conductors shall have green or green with one or more yellow stripes insulation over its entire length except that conductors No. 4 and larger may be permanently identified by distinctive green markers such as paint or green tape over its entire exposed insulation.

Ungrounded feeder and branch circuit conductors shall be color coded by continuously colored insulation, except conductors No. 6 AWG or larger may be color coded by colored tape at each connection and where accessible. Ungrounded conductor color coding shall be as follows:

SYSTEM	COLOR CODE
120/240V-Single phase	Black, blue
120/240V-Three phase	Black, orange, blue

Once an insulated circuit conductor, including grounded and ungrounded conductors, is identified with a specific color code, that color code shall be used for the entire length of the circuit.

Where more than one branch circuit enters or leaves a conduit, panel, gutter, or junction box, each conductor shall be identified by its panelboard and circuit number. All control conductors including control conductors of manufacturer supplied and field wired control devices shall be identified at each termination with the wire numbers shown on the plans, approved working drawings, and as directed by the Engineer where deemed necessary. Identification shall be made with one of the following:

1. Adhesive backed paper or cloth wrap-around markers with clear, heat shrinkable tubing sealed over either type of marker.
2. Self-laminating wrap around type, printable, transparent, permanent heat bonding type thermoplastic film markers.
3. Pre-printed, white, heat-shrinkable tubing.

Each terminal block shall have a molded marking strip attached with screws. The identifying numbers of the terminating conductors, as shown on the plans or on the submittal drawings, shall be engraved in the marking strip.

Outlet, Device and Junction Box Installation:

Where exposed threaded steel conduits are connected to an outlet, device, or junction box below switch height, the box shall be a cast metal box. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall be sheet steel boxes. Weatherproof outlet, device and junction boxes shall have cast metal covers with gaskets. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall have standard galvanized covers.

All boxes shall finish flush with building walls, ceiling and floors except where exposed work is called for.

Raised device covers (plaster rings) shall be installed on all boxes concealed in concrete, masonry or stud walls.

No unused openings shall be left in any box. Knockout seals shall be installed as required to close openings.

Outlet, device, and junction boxes shall be installed at the locations and elevations shown on the plans or specified herein. Adjustments to locations may be made as required by structural conditions and to suit coordination requirements of other trades.

Underground Pull Box Installation:

Electrical pull box covers or lids shall be marked "ELECTRICAL." Telephone service pull box covers or lids shall have plain, unmarked covers.

The bottom of pull boxes shall be bedded in 6 inches of clean, crushed rock or gravel and shall be grouted with 1½-inch thick grout prior to installation of conductors. Grout shall be sloped to a one-inch PVC pipe drain hole. Conduit shall be sealed in place with grout.

Top of pull boxes shall be flush with surrounding grade or top of curb. In unpaved areas where pull box is not immediately adjacent to and protected by a concrete foundation, pole or other protective construction, the top of pull box shall be set at plus one inch above surrounding grade. Pull boxes shown on the plans in the vicinity of curbs shall be placed adjacent to the back of curb. Pull boxes shown on the plans adjacent to lighting standards shall be placed on the side of foundation facing away from traffic.

Ground Rod(s) Installation: The ground rod(s) shall be driven vertically until the top is 6 inches above the surrounding surface. When vertical penetration of the ground rod cannot be obtained, an equivalent horizontal grounding system, approved by the Engineer, shall be installed.

Anchorage:

Hangers, brackets, conduit straps, supports, and electrical equipment shall be rigidly and securely fastened to surfaces by means of toggle bolts on hollow masonry; expansion shields and machine screws, or expansion anchors and studs or standard preset inserts on concrete or solid masonry; machine screws or bolts on metal surfaces; and wood or lag screws on wood construction.

Anchorage devices shall be installed in accordance with the anchorage manufacturer's recommendations.

Mounting heights: Electrical system components shall be mounted at the following mounting heights, unless otherwise shown on the plans. The mounting height dimensions shall be measured above the finished floor to the bottom of the device or component.

Thermostats	3'-4" maximum, office areas 4'-0" maximum, hallways
Wall switches	3'-4" maximum
Convenience outlets	2'-0" minimum, office areas 3'-4" minimum, all other areas
Electric water cooler outlet	As recommended by the water cooler manufacturer.
Telephone and radio outlets	2'-0" minimum

12-16.03 SERVICE AND DISTRIBUTION

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing service and distribution equipment in accordance with the requirements of the serving utilities, the details shown on the plans and these special provisions.

Attention is directed to "Utility Connection" in Section 12-1, "General Requirements," of these special provisions regarding arrangements, permits, licenses, charges, fees and costs for utility connections and extensions.

Related Work: Concrete and reinforcement for service pedestal shall conform to the requirements specified for minor work under "Cast-in-Place Concrete," in Section 12-3, "Concrete and Reinforcement," of these special provisions.

SUBMITTALS

Installation Details: The Contractor shall submit complete service installation details to the serving utilities for approval. Prior to submitting installation details to the serving utility, the Contractor shall have said drawings reviewed and stamped "APPROVED" by the Engineer. Submittals shall be approved by the serving utility prior to commencing work.

Product Data:

A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2 - PRODUCTS

Service Equipment: Service equipment shall contain a pull section, metering compartment and service disconnect switch for 240-volt, 300-ampere, 3-phase, 4-wire service.

Enclosure: Enclosure shall be NEMA 1R enclosure. Exterior shall be 12-gage and interior shall be 14-gage sheet steel. All screws, latches, hinge pins and similar hardware shall be stainless steel. Circuit breaker shall be operable with the exterior door open. Exterior door shall be lockable with a padlock. Enclosure finish shall be baked enamel or baked thermosetting polyester finish.

Service Disconnect Switch: Service disconnect switch shall be 3-pole, 240-volt, 400-ampere frame, 300-ampere trip, molded case circuit breaker with AC magnetic trip adjusted to 225 amperes. The interrupting capacity of the circuit breaker shall be 18,000 amperes (symmetrical) at 240-volt. Breaker shall be Cutler-Hammer; Square D; General Electric; or equal.

Lighting and Sign Illumination Service Equipment: This service equipment shall conform to the requirements of the State of California, Department of Transportation Standard Specifications, Section 86-2.11 "Service" and these specifications.

Type III service equipment enclosures shall be the aluminum type.

Circuit breakers shall have a minimum interrupting capacity of 10,000A rms for 120/240 V services.

PART 3 - EXECUTION

Foundation for service pedestal shall be as shown on the plans.

Installation of service and distribution equipment shall be in accordance with the requirements of the serving utilities as shown on the approved installation details.

12-16.04 ELECTRICAL EQUIPMENT

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing panelboards, starters, disconnect switches, transformers, and related accessories in accordance with the details shown on the plans and these special provisions.

Related Work: Anchorage devices shall be as specified under "Basic Materials and Methods" elsewhere in Section 12-16.

SUBMITTALS

Product Data:

A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2 - PRODUCTS

SWITCHBOARD AND PANELBOARDS

Switchboard A: Switchboard A shall be indoor type, consisting of a utility metering section, approximately 36 inches wide and a distribution section approximately 30 inches wide, floor-mounted, factory assembled, 3 phase, 4 wire, 240-volt, AC with 300 ampere main circuit breaker groundable neutral, and molded case branch circuit breakers with as minimum 18,000 amperes symmetrical interrupting rating as shown on the plans. Panel shall be Square D Company, SPEED-D switchboard, Cutler-Hammer, INSTANT switchboard; or equal.

Panelboards B, C, D, E and F: Panelboards B, C, D, E and F shall be indoor type, surface-mounted, factory assembled, 1-phase, 3-wire, 240-volt, AC panelboard at least 20 inches wide with 100-ampere main lugs only, insulated neutral, hinged door and molded case branch circuit breakers with a minimum 10,000 amperes symmetrical interrupting rating as shown on the plans. Panels shall be Square D Company, NQOD; Cutler-Hammer, POW-R-Line ; General Electric, A Series; or equal.

STARTERS

MISCELLANEOUS MATERIALS

Nameplates: Nameplates shall be laminated phenolic plastic with white core and black front and back. Nameplate inscription shall be in capitals letters etched through the outer layer of the nameplate material.

Warning Plates: Warning plates shall be laminated phenolic plastic with white core and red front and back. Warning plates inscription shall be in capitals letters etched through the outer layer of the nameplate material.

Plywood Backing Board: Plywood backing board for mounting electrical or telephone equipment shall be 3/4-inch, APA plywood panels, C-D PLUGGED and touch-sanded, Exposure 1.

PART 3 - EXECUTION

INSTALLATION

Plywood Backing Board:

Plywood backing board shall be securely fastened to walls or other vertical framing.

Surface to be coated shall be cleaned of all dirt, excess materials, of filler by hand cleaning.

Plywood backing board exposed surfaces shall receive the following paint system: one prime coat, alkyd, interior wood primer and 2 finish coats, acrylic, interior enamel, semi-gloss. Color shall match surrounding surfaces, or shall be as directed by the Engineer.

Coatings shall be applied in accordance with the manufacturer's instructions. Each coat shall be applied to a uniform finish, free of skips, brush marks, laps or other imperfections.

Panelboard Installation:

Set cabinets plumb and symmetrical with building lines. Train interior wiring as specified under "Conductor and Cable Installation" in "Basic Materials and Methods" of these special provisions. Touch-up paint any marks, blemishes, or other finish damage suffered during installation. Replace cabinets, doors or trim exhibiting dents, bends, warps or poor fit which may impede ready access, security or integrity.

Mounting height shall be 5½ feet to the highest circuit breaker handle, measured above the finished floor.

Where "Future" or "Space" is indicated on the plans, branch connectors, mounting brackets, and other hardware shall be furnished and installed for future breaker.

A typewritten directory under transparent protective cover shall be provided and set in metal frame inside each cabinet door. Directory panel designation for each circuit breaker shall include complete information concerning equipment controlled, including room number or area designated on the plans.

Equipment Identification:

Equipment shall be identified with nameplates fastened with self-tapping, cadmium-plated screws or nickel-plated bolts.

Nameplate inscriptions shall read as follows:

Item	Letter height, inches	Inscription
Panel A	1/4	PANEL A 120/240V, 225A, 3P-4W
Panel B	1/4	PANEL B 120/240V, 100A, 1P-3W
Panels C, D and E	1/4	SIMILAR TO PANEL B
Panel F	1/4	PANEL F VENDING EQUIPMENT 120/240V, 100A, 1P-3W
Panel LCP	1/4	EXTERIOR LIGHTING CONTROL PANEL 120/240V, 1P-3W

12-16.05 LIGHTING

PART 1 – GENERAL

Scope: This work shall consist of furnishing, installing and connecting all lighting equipment in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Manufacturer's descriptive information, photometric curves, catalog cuts, and installation instructions shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

PART 2 - PRODUCTS

Lighting Fixture Lamps: Lighting fixture lamps shall be type and size as shown on the plans. Lamps shall be General Electric, Phillips, Sylvania, or equal. Fluorescent lamps, unless otherwise noted, shall be 4100K tri-phosphor with a CRI of 70 or greater.

Ballasts: All fixtures shall be equipped with high power factor ballasts suitable for the line voltage and for the type, size and number of lamps required by the fixture. Fluorescent ballasts shall be UL Listed, Class P and ETL Certified ballasts with sound rating A. Fluorescent ballasts shall be high-frequency electronic ballasts with power factor greater than 0.95, nominal ballast factor of 0.88 unless specified otherwise, total harmonic distortion less than 20 percent, crest factor less than or equal to 1.7, complying with ANSI C 62.41 Category A for surge protection, and FCC Part 18 for interference.

Lighting Fixtures: Lighting fixtures shall be as shown on the plans and as specified herein. Outdoor luminaires shall be listed and labeled "Fixture Suitable For Wet Locations."

A: Ceiling-mounted fluorescent fixture with 2-32 watt lamps, 4 foot long, electronic ballast and one-piece, polycarbonate, wrap-around diffuser. Fixture designated as vandal resistant. The fixture shall be Day Brite, Catalog No. SL-W-232-120-EB; Kendall, Catalog No. MLHA 12-48-MW-PP-232-SB; Lithonia, Catalog No. VSE-232-120-GEB; or equal.

A1: This fixture shall be the same as Type A except with emergency ballast for one lamp. The fixture shall be Day-Brite, Catalog No. SL-W-232-120-EB-E5. Kenall, Catalog No. MLHA12-48-MW-PP-232-SB-PEL, Lithonia, Catalog No. VSE-232-120-GEB-EL14DW, or equal.

B: Ceiling mounted compact high pressure sodium fixture with 1-50-watt lamp, one-piece square die cast aluminum housing, low glare high performance luminaire, drop polycarbonate lens, Type V symmetrical distribution, black finish. The fixture shall be Day-Brite, Catalog No. CL1-50S-12-PX-TR, Hydrel, Catalog No. HP3-50S-HSC-SSB-BL, Lithonia, Catalog No. KACM-50S-DPP-120, or equal.

B2: The fixture shall be the same as Type B except with 1-50-watt metal halide lamp. The fixture shall be Day-Brite, Catalog No. CL1-50M-12-PX-TR, Hydrel, Catalog No. HP3-50M-HSC-SSB-BL, Lithonia, Catalog No. KACM-50M-DPP-120, or equal.

C: Wall mounted compact high pressure sodium fixture with 1-50-watt lamp, one-piece trapezoidal die cast aluminum housing, low glare high performance luminaire, drop polycarbonate lens, forward throw distribution, black finish. The fixture shall be Gardco, Catalog No. 111-FT-50S-120-BLP, Lithonia, Catalog No. WST-50S-FT-120-DBLB, Kim, Catalog No. WD14D4-50HPS120-BL-P or equal.

D: Recessed ramp mounted compact high pressure sodium fixture with 1-50-watt lamp, one-piece trapezoidal die cast aluminum housing, low glare high performance luminaire, drop polycarbonate lens, forward throw distribution, black finish. The fixture shall be Gardco, Catalog No. 942-C-50HPS-120-DG-BLP, Lithonia, Catalog No. KL-50S-A-120-DBL, Hydrel, Catalog No. HP3-50S-LFW-RSB-BL or equal.

E1:

Pole mounted, 150-watt, 240-volt, high pressure sodium, cutoff luminaire with integral ballast. The luminaire shall be Gardco, Catalog No. EH14-1-3-150HPS-240-BLA; General Electric, Catalog No. SPMM-15HPS-3-H-1-G-SC3-BL; Lithonia, Catalog No. KSE1-150S-R3-240-SP04-DBLB; or equal.

Pole for luminaire shall be square straight aluminum, have 40,000 psi minimum yield strength, 20-foot height, with 6 inch mast arm. The pole shall be able to withstand stresses produced by steady state wind with velocity of 90 MPH. Pole shall have hand hole with cover plate, base plate and all necessary hardware.

E2: The fixture shall be the same as Type E1 except with two 150-watt luminaire on the same pole. The luminaire shall be Gardco, Catalog No. EH14-2-3-150HPS-240-BLA, General Electric, Catalog No. 2-SPMM-15HPS-3-H-1-G-SC3-BL; Lithonia, Catalog No. 2-KSE1-150S-R3-240-SP04-DBLB; or equal

F: Recessed ground mounted with adjustable optics, tempered glass lens, 50-watt metal halide luminaire with integral ballast. The fixture shall be Hydrel 9100A-MH50-120-mfl-34, Kim, Catalog No. LTV752-WW-50MH120, or equal.

Fused Splices: Fused splices shall be Buss, Type HEX; Elastimold, Style D65; or equal; with standard midget, ferrule, 2-ampere, 240-volt, slow blowing fuses.

Photoelectric Unit, PC: Photoelectric unit shall be cadmium sulfide photoelectric control with capacity of 1000-watt incandescent or 1800-watt inductive or fluorescent load, mounting adapter, and EEI-NEMA twist lock receptacle; Fisher-Pierce, Ripley, or equal.

Lighting Control Station, Panel LCP: Lighting control panel shall consist of a lighting contactors, programmable lighting relays, programmable time clock, line and low voltage terminal blocks and power supply in a surface mounted NEMA-1 enclosure with a hinged door.

Panel shall accept up to eight single pole relays. Relays shall be individual latching relays with 20 Amp load contacts for ballast (including HID, magnetic or electronic type ballasts), tungsten and general purpose loads. Provide isolated auxiliary contacts for pilot light switching. Relays shall use quick connectors and be individually replaceable to facilitate ease of use.

Where indicated, panels shall provide space within the high voltage section of the enclosure to accommodate up to 12 multi-pole contactors. Two sections of DIN rail mounting shall be provided as standard. No field drilling or fabrication shall be required for mounting contactors or other accessories within the enclosure.

The lighting control panel shall provide a stagger up delay, override push buttons, pilot light outputs, and LED status light indicators for each relay or contactor control channel.

The clock shall have a backlight display, user keypad and shall provide 8 channels of time or astronomical control. Preprogrammed lighting control scenarios shall include: scheduled on/off, manual on/scheduled off, manual on/automatic switch sweep off, astronomic or photocell on/off and astronomic or photocell control with scheduled on/off. Time clock shall provide up to 42 holidays, automatic daylight savings adjustment, astronomic coordinates by major cities, and help screens. Program memory shall be non-volatile and clock shall retain time keeping during power outages for at least 48 hours.

The panel shall have 8 universal switch inputs that are low voltage, self-configuring and shall not require programming to accept momentary on/ momentary off switch, push button switch (cycling), maintained switch or 24VDC signals from occupancy sensors, photocells or other interfacing devices.

After-hour interior lighting shut off control shall provide a full duration override time of 1 to 240 minutes with a warning blink five minutes prior to shutting the lighting off. An impending shut off will be cancelled and the override period re-initialized through the operation of any assigned switch input.

After-hour interior lighting shut off control may be by line voltage power interrupt control to automatic control switches. The lighting control relay panel shall provide a warning blink signal to automatic control switches, thus allowing a five-minute delay prior to shutting off lighting. The lighting shut off event may be cancelled by pressing the automatic control switch push button. The lighting control panel time clock shall provide periodic lighting sweep signals to shut off automatic control switches.

Lighting Contactor, LC: Lighting contactor shall be electrically held, 4-pole combination lighting contactor with 120-volt AC coil and 20-ampere, double-break, silver alloy contacts; Square D Company, I.T.E., Cutler-Hammer, or equal.

Terminal Block, TB: Terminal block shall be 20-ampere, 120-volt, molded plastic with two or more mounting holes and two or more terminals in each cast block. The molded plastic shall have a high resistance to heat, moisture, mechanical shock, and electrical potential and shall have a smooth even finish. Each block shall have a molded marking strip attached with screws. Terminal blocks shall have tubular, high pressure clamp connectors.

Concrete: Concrete shall be as specified under Section 12-3, "Concrete and Reinforcement," of these special provisions. The concrete shall be commercial quality portland cement concrete containing not less than 564 pounds of cement per cubic yard.

PART 3 - EXECUTION

Lighting Fixtures:

Lighting fixtures shall be mounted securely in accordance with the manufacturer's recommendations. Mounting methods shall be suitable for the particular type of ceiling or support at each location.

The Contractor shall provide all supports, hangers, spacers, channels, fasteners and other hardware necessary to support the fixtures.

Fixtures shall be set at the mounting heights shown on the plans, except heights shown shall be adjusted to meet conditions.

Ballasts:

All fluorescent fixtures shall be equipped with high power factor ballasts suitable for the line voltage and for the type, size and number of lamps required by fixture. The Contractor has the option to install low voltage dimming control provided that the Contractor submit plans and specifications with appropriate revisions for the low voltage dimming control to the Engineers for approval prior to installation.

All ballasts used in unheated areas inside the building shall be 0°F ballasts or less.

Pole Mounted Luminaires:

In the pull box adjacent to each pole for luminaire, E1 or E2, a fused splice connector shall be installed in each ungrounded conductor between the line and the ballast. The connector shall be readily accessible in the pull box and shall be insulated and made waterproof in accordance with the splice connector manufacturer's recommendations.

Concrete foundations shall be as shown on the plans. Anchor bolts or devices shall be accurately located and positioned to match the holes in the pole base plates. Pole and luminaire orientation shall be as indicated on the plans.

The poles for pole mounted type fixtures shall be mounted rigidly and securely on the foundations as recommended by the fixture and pole manufacturer.

Lighting Control Panel:

The lighting control panel, switches, occupancy sensors, photocells, etc., shall be mounted as indicated on the Plans. All wiring shall be labeled clearly indicating which lighting control panel or device it connects to. Use only properly color-coded, stranded wire as indicated on the drawings.

All relays, contactors, and switches shall be tested after installation to confirm proper operation, and all connected loads shall be recorded on the lighting control schedule for each panel.

The lighting control panel shall be wired to control the power of each load as indicated on the Lighting Control Panel Schedule on the Plans. All power wiring will be identified with the circuit breaker number controlling the load.

Provide system documentation after the equipment has been installed: Lighting control operational summary sheet, programming record sheet, and system Installation and Operation Manual

**AMENDMENTS TO THE STANDARD SPECIFICATIONS
DATED MAY 2006**

1-2 REFERENCES

1-2.01 REFERENCES

A reference within parentheses to a law or regulation is included in the contract for convenience only and is not a comprehensive listing of related laws and regulations. Lack of a reference does not indicate no related laws or regulations exist.

If the version of a referenced document is not specified, use the current version in effect on the date of Notice to Bidders.

A reference to a subsection includes the section's general specifications of which the subsection is a part.

A code not specified as a Federal code is a California code.

1-3 ABBREVIATIONS AND MEASUREMENT UNITS

1-3.01 ABBREVIATIONS

Abbreviations	
Abbreviation	Meaning
AAN	American Association of Nurserymen
AASHTO	American Association of State Highway and Transportation Officials
AISC	American Institute of Steel Construction
AISI	American Iron and Steel Institute
ANSI	American National Standards Institute
APHA	American Public Health Association
API	American Petroleum Institute
AREMA	American Railway Engineering and Maintenance-of-Way Association
ASME	American Society of Mechanical Engineers
ASTM	American Society for Testing and Materials
AWG	American Wire Gage
AWPA	American Wood-Preservers' Association
AWS	American Welding Society
AWWA	American Water Works Association
CIH	Certified Industrial Hygienist
DBE	Disadvantaged Business Enterprise
DVBE	Disabled Veteran Business Enterprise
EIA	Electronic Industries Alliance
ETL	Electrical Testing Laboratories
FHWA	Federal Highway Administration
NETA	National Electrical Testing Association, Inc.
NEMA	National Electrical Manufacturers Association.
PLAC	permit, license, agreement, certification, or any combination of these
SSPC	The Society for Protective Coatings
UL	Underwriters' Laboratories Inc.

1-3.02 MEASUREMENT UNITS

Measurement Units		
Symbols as used in the specifications	Symbols as used in the Bid Item List	Meaning
A	—	amperes
	ACRE	acre
	CF	cubic foot
	CY	cubic yard
--	EA	each
g	--	gram
ksi	--	kips per square inch
	GAL	gallon
h	H	hour
	LB	pound
--	LS	lump sum
	LF	linear foot
	LNMI	lane mile
	MFBM	thousand foot board measure
	MI	mile
	MSYD	thousand station yard
Ω	--	ohm
pcf	--	pounds per cubic foot
s	--	second
	STA	100 feet
	SQFT	square foot
	SQYD	square yard
	TAB	tablet
ton	TON	2,000 pounds
W	--	watt
V	--	volt

1-4 DEFINITIONS

1-4.01 GENERAL

Interpret terms as defined in the contract documents. A construction-industry term not defined in the contract documents has the meaning defined in Means Illustrated Construction Dictionary, Condensed Version, Second Edition.

1-4.02 GLOSSARY

acceptance: Formal written acceptance by the Director of an entire contract that has been completed in all respects in accordance with the plans and specifications and any modifications to them previously approved.

base: Layer of specified material of planned thickness placed immediately below the pavement or surfacing.

basement material: Material in excavation or embankments underlying the lowest layer of subbase, base, pavement, surfacing, or other specified layer to be placed.

bid item: Specific work unit for which the bidder provides a price.

Bid Item List: List of bid items and the associated quantities.

Bid Item List, verified: Bid Item List with verified prices. The Contract Proposal of Low Bidder at the Department's Web site is the verified Bid Item List.

bridge: Structure, with a bridge number, that carries a utility facility, or railroad, highway, pedestrian or other traffic, over a water course or over or under or around any obstruction.

building-construction contract: Contract that has "building construction" on the cover of the Notice to Bidders and Special Provisions.

business day: Day on the calendar except Saturday or holiday.

California Manual on Uniform Traffic Control Devices: The California Manual on Uniform Traffic Control Devices for Streets and Highways (California MUTCD) is issued by the Department of Transportation and is the Federal Highway Administration's MUTCD 2003 Edition, as amended for use in California.

Certified Industrial Hygienist: Industrial hygienist certified in comprehensive practice by the American Board of Industrial Hygiene.

conduit: Pipe or tube in which smaller pipes, tubes, or electrical conductors are inserted or are to be inserted.

contract: Written and executed contract between the Department and the Contractor.

contract bonds: Security for the payment of workers and suppliers furnishing materials, labor, and services and for guaranteeing the Contractor's work performance.

contract item: Bid item.

Contractor: Person or business or its legal representative entering into a contract with the Department for performance of the work.

culvert: Structure, other than a bridge, that provides an opening under a roadway for drainage or other purposes.

day: 24 consecutive hours running from midnight to midnight; calendar day.

deduction: Amount of money permanently taken from progress payment and final payment. Deductions are not retentions under Pub Cont Code § 7107.

Department: Department of Transportation as defined in St & Hwy Code § 20 and authorized in St & Hwy Code § 90; its authorized representatives.

detour: Temporary route for traffic around a closed road part. A passageway through a job site is not a detour.

Director: Department's Director.

Disabled Veteran Business Enterprise: Business certified as a DVBE by the Office of Small Business and DVBE Services, Department of General Services.

divided highway: Highway with separated traveled ways for traffic, generally in opposite directions.

Engineer: Department's Chief Engineer acting either directly or through properly authorized agents; the agents acting within the scope of the particular duties delegated to them.

Federal-aid contract: Contract that has a Federal-aid project number on the cover of the Notice to Bidders and Special Provisions.

fixed costs: Labor, material, or equipment cost directly incurred by the Contractor as a result of performing or supplying a particular bid item that remains constant regardless of the item's quantity.

frontage road: Local street or road auxiliary to and located generally on the side of an arterial highway for service to abutting property and adjacent areas and for control of access.

grading plane: Basement material surface on which the lowest layer of subbase, base, pavement, surfacing, or other specified layer is placed.

highway: Whole right of way or area that is reserved for and secured for use in constructing the roadway and its appurtenances.

holiday:

1. Every Sunday
2. January 1st, New Year's Day
3. 3rd Monday in January, Birthday of Martin Luther King, Jr.
4. February 12th, Lincoln's Birthday
5. 3rd Monday in February, Washington's Birthday
6. March 31st, Cesar Chavez Day
7. Last Monday in May, Memorial Day
8. July 4th, Independence Day
9. 1st Monday in September, Labor Day
10. 2nd Monday in October, Columbus Day
11. November 11th, Veterans Day
12. 4th Thursday in November, Thanksgiving Day
13. Day after Thanksgiving Day
14. December 25th, Christmas Day

If January 1st, February 12th, March 31st, July 4th, November 11th, or December 25th falls on a Sunday, the Monday following is a holiday. If November 11th falls on a Saturday, the preceding Friday is a holiday. Interpret "legal holiday" as "holiday."

informal-bid contract: Contract that has "Informal Bid Authorized by Pub Cont Code §10122" on the cover of the Notice to Bidders and Special Provisions.

Information Handout: Supplemental project information furnished to bidders as a handout.

laboratory: Laboratory authorized by the Department to test materials.

liquidated damages: Amount prescribed in the specifications, pursuant to the authority of Pub Cont Code § 10226, to be paid to the State or to be deducted for each day's delay in completing the whole or any specified portion of the work beyond the time allowed in the specifications.

median: Portion of a divided highway separating the traveled ways for traffic in opposite directions including inside shoulders.

Notice to Bidders: Document that provides a general work description, bidder and bid specifications, and the time and location the Department receives bids.

pavement: Uppermost layer of material placed on the traveled way or shoulders. This term is used interchangeably with surfacing.

plans: Official project plans and Standard Plans, profiles, typical cross sections, working drawings and supplemental drawings, or reproductions thereof, approved by the Engineer, which show the location, character, dimensions and details of the work to be performed. These documents are to be considered as a part of the plans.
In the above definition, the following terms are defined as follows:
Standard Plans: Standard Plans issued by the Department.
project plans: Specific details and dimensions peculiar to the work supplemented by the Standard Plans insofar as the same may apply.

roadbed: Area between the intersection of the upper surface of the roadway and the side slopes or curb lines. The roadbed rises in elevation as each increment or layer of subbase, base, surfacing or pavement is placed. Where the medians are so wide as to include areas of undisturbed land, a divided highway is considered as including 2 separate roadbeds.

roadway: Highway portion included between the outside lines of sidewalks, or curbs, slopes, ditches, channels, waterways, and including all the appertaining structures, and other features necessary to proper drainage and protection.

shoulder: Roadway portion contiguous with the traveled way for accommodation of stopped vehicles, for emergency use, and for lateral support of base and surface courses.

special provisions: Specific clauses setting forth conditions or requirements peculiar to the work and supplementary to these Standard Specifications. The Department's publication titled "Labor Surcharge And Equipment Rental Rates" is part of the special provisions.

specifications: Directions, provisions, and requirements contained in these Standard Specifications, Amendments to the Standard Specifications, and the special provisions. Where the term "these specifications" or "these Standard Specifications" is used in this book, it means the provisions set forth in this book.

State: State of California, including its agencies, departments, or divisions, whose conduct or action is related to the work.

Structure Design: Offices of Structure Design of the Department.

subbase: Layer of specified material of planned thickness between a base and the basement material.

subgrade: Roadbed portion on which pavement, surfacing, base, subbase, or a layer of any other material is placed.

substructure: Bridge portions below the bridge seats, tops of piers, haunches of rigid frames, or below the spring lines of arches. Backwalls and parapets of abutments and wingwalls of bridges are portions of the substructure.

superstructure: Bridge portion except the bridge substructure.

supplemental project information: Information relevant to the project, specified as supplemental project information, and made available to bidders.

surfacing: Uppermost layer of material placed on the traveled way, or shoulders. This term is used interchangeably with pavement.

traffic lane: Portion of a traveled way for the movement of a single line of vehicles.

traveled way: Portion of the roadway for the movement of vehicles, exclusive of shoulders.

total bid: Sum of the item totals as verified by the Department; original contract price.

withhold: Money temporarily or permanently taken from progress payment. Withholds are not retentions under Pub Cont Code § 7107.

work: All the work specified, indicated, shown or contemplated in the contract to construct the improvement, including all alterations, amendments, or extensions to it made by contract change order or other written orders of the Engineer.

1-5 DISTRICTS

District Composition and Office Addresses

District	Counties	Location Address	Mailing Address
1	Del Norte (DN), Humboldt (Hum), Lake (Lak), Mendocino (Men)	1656 UNION ST EUREKA, CA	PO BOX 3700 EUREKA CA 95502
2	Lassen (Las), Modoc (Mod), Plumas (Plu), Shasta (Sha), Siskiyou (Sis), Tehama (Teh), Trinity (Tri)	1657 RIVERSIDE DR REDDING, CA	PO BOX 496073 REDDING CA 96049-6073
3	Butte (But), Colusa (Col), El Dorado (ED), Glenn (Gle), Nevada (Nev), Placer (Pla), Sacramento (Sac), Sierra (Sie), Sutter (Sut), Yolo (Yol), Yuba (Yub)	703 B ST MARYSVILLE, CA	PO BOX 911 MARYSVILLE CA 95901
4	Alameda (Ala), Contra Costa (CC), Marin (Mrn), Napa (Nap), San Francisco (SF), San Mateo (SM), Santa Clara (SCI), Solano (Sol), Sonoma (Son)	111 GRAND AVE OAKLAND, CA	PO BOX 23660 OAKLAND CA 94623-0660
5	Monterey (Mon), San Benito (SBt), San Luis Obispo (SLO), Santa Barbara (SB), Santa Cruz (SCr)	50 HIGUERA ST SAN LUIS OBISPO, CA	50 HIGUERA ST SAN LUIS OBISPO CA 93401-5415
6	Fresno (Fre), Kern (Ker), Kings (Kin), Madera (Mad), Tulare (Tul)	1352 W. OLIVE AVE FRESNO, CA	PO BOX 12616 FRESNO CA 93728-2616
7	Los Angeles (LA), Ventura (Ven)	100 S. MAIN ST LOS ANGELES	100 S MAIN ST LOS ANGELES CA 90012
8	Riverside (Riv), San Bernardino (SBd)	464 W 4TH ST SAN BERNARDINO, CA	464 W 4TH ST SAN BERNARDINO CA 92401-1400
9	Inyo (Iny), Mono (Mno)	500 S MAIN ST BISHOP, CA	500 S MAIN ST BISHOP CA 93514-3423
10	Alpine (Alp), Amador (Ama), Calaveras (Cal), Mariposa (Mpa), Merced (Mer), San Joaquin (SJ), Stanislaus (Sta), Tuolumne (Tuo)	1976 E CHARTER WAY STOCKTON, CA	PO BOX 2048 STOCKTON CA 95201
11	Imperial (Imp), San Diego (SD)	4050 TAYLOR ST SAN DIEGO, CA	4050 TAYLOR ST SAN DIEGO CA 92110-2737
12	Orange (Ora)	3347 MICHELSON DR STE 100 IRVINE, CA	3347 MICHELSON DR STE 100 IRVINE CA 92612-0661

A project with work in District 1, 2, or 3 is a North Region project. For Districts 1, 2, and 3, interpret each reference to the district office as the North Region office. The North Region office address is the District 3 address.

1-6 WEB SITES, ADDRESSES, AND TELEPHONE NUMBERS

Web Sites, Addresses, and Telephone Numbers

Agency, Department Unit, or Reference	Web Site	Address	Telephone No.
Bid Document Unit		MSC 26 BID DOCUMENT UNIT DEPARTMENT OF TRANSPORTATION 1120 N ST RM 200 SACRAMENTO CA 95814-5605	
Department	www.dot.ca.gov		
Department of General Services, Office of Small Business and DVBE Services	www.pd.dgs.ca.gov/smbus/default.htm	OFFICE OF SMALL BUSINESS AND DVBE SERVICES DEPARTMENT OF GENERAL SERVICES 707 3RD ST WEST SACRAMENTO CA 95605-2811	(800) 559-5529 (916) 375-4940
Department of Industrial Relations	www.dir.ca.gov		
Department of Industrial Relations, Division of Apprenticeship Standards		455 GOLDEN GATE AVENUE SAN FRANCISCO, CA 94102	
Office Engineer		MSC 43 OFFICE ENGINEER DEPARTMENT OF TRANSPORTATION 1727 30TH ST SACRAMENTO CA 95816-7005	
Office Engineer– Verified Bid Results	http://www.dot.ca.gov/hq/esc/oe/awards/bidsum_html/6week_list.html		
Offices of Structure Design, Documents Unit		MSC 9-4/4I DOCUMENTS UNIT OFFICES OF STRUCTURE DESIGN DEPARTMENT OF TRANSPORTATION 1801 30TH ST SACRAMENTO CA 95816-7006	(916) 227-8252
Publication Distribution Unit		PUBLICATION UNIT DEPARTMENT OF TRANSPORTATION 1900 ROYAL OAKS DRIVE SACRAMENTO CA 95815-3800	
Transportation Laboratory		MATERIALS AND ENGINEERING TESTING SERVICES AND GEOTECHNICAL SERVICES DEPARTMENT OF TRANSPORTATION 5900 FOLSOM BLVD SACRAMENTO CA 95819-4612	(916) 227-7000
Department's Pre-Qualified Products List	http://www.dot.ca.gov/hq/esc/approved_products_list		

As-built drawings may not show existing dimensions and conditions. Where new construction dimensions are dependent on existing bridge dimensions, verify the field dimensions and adjust dimensions of the work to fit existing conditions.

2-1.04 SMALL BUSINESS ENTERPRISE GOAL

The Department has established an overall 25 percent small business participation goal. To determine if the goal is achieved, the Department is tracking small business participation on all contracts.

Contractors, subcontractors, suppliers, and service providers who qualify as small business are encouraged to apply for certification as a small business by submitting their application to the Department of General Services, Office of Small Business and DVBE Services.

2-1.05 DISADVANTAGED BUSINESS ENTERPRISES

Section 2-1.05, "Disadvantaged Business Enterprises," applies to a Federal-aid contract.
Under 49 CFR 26.13(b):

The contractor, sub recipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate.

- In order to ensure the Department achieves its federally mandated statewide overall DBE goal, the Department encourages the participation of DBEs as defined in 49 CFR 26.

2-1.06 DISABLED VETERAN BUSINESS ENTERPRISES

2-1.06A General

Section 2-1.06, "Disabled Veteran Business Enterprises," applies to a non-Federal-aid contract.
Take necessary and reasonable steps to ensure that DVBEs have opportunity to participate in the contract.
Comply with Mil & Vet Code § 999 et seq.

2-1.06B No Goal

Section 2-1.06B, "No Goal," applies if no DVBE goal is shown in the Notice to Bidders.

The Department encourages bidders to obtain DVBE participation in order to ensure the Department achieves its State-mandated overall DVBE goal.

2-1.06C Goal

Section 2-1.06C, "Goal," applies if a DVBE goal is shown in the Notice to Bidders.

Make work available to DVBEs and select work parts consistent with available DVBE subcontractors and suppliers.

Meet the goal shown or demonstrate that you made good faith efforts to meet this goal.

If a DVBE joint venture is used, submit the joint venture agreement with the Certified DVBE Subcontractor Summary form.

The Department determines a bidder has made good faith efforts if it submits evidence within the specified time that it:

1. Contacted the Office of Small Business and DVBE Services, Department of General Services
2. Advertised in trade media and media focusing on DVBEs unless time limits the Department imposes do not allow the advertising
3. Submitted invitations to bid to potential DVBE contractors
4. Considered available DVBEs

2-1.07 SMALL BUSINESS AND NON-SMALL BUSINESS SUBCONTRACTOR PREFERENCES (GOVT CODE § 14835 ET SEQ. AND 2 CA CODE OF REGS § 1896 ET SEQ.)

2-1.07A General

Section 2-1.07, "Small Business and Non-Small Business Subcontractor Preferences (Govt Code § 14835 et seq. and 2 CA Code of Regs § 1896 et seq.)," applies to a non-Federal-aid contract.

2-1.07B Small Business Preference

The Department allows a bidder certified as a small business by the Office of Small Business and DVBE Services, Department of General Services, a preference if:

1. You completed a Request for Small Business Preference or Non–Small Business Preference form
2. You attached a copy of your Office of Small Business and DVBE Services small business certification to the form
3. The apparent low bidder is not certified as a small business

The small business preference is a reduction for bid comparison in the total bid submitted by the small business subcontractor by the lesser of:

1. 5 percent of the total bid of the apparent low bidder
2. \$50,000

If this reduction results in the small business contractor becoming the low bidder, the contract award is based on the total bid, not the reduced bid.

2-1.07C Non–Small Business Subcontractor Preference

The Department allows a bidder not certified as a small business by the Office of Small Business and DVBE Services, Department of General Services, a preference if:

1. You completed a Request for Small Business Preference or Non–Small Business Preference form
2. The apparent low bidder is not certified as a small business and has not requested preference

The non–small business subcontractor preference is a reduction for bid comparison in the total bid submitted by the non–small business contractor requesting the preference by the lesser of:

1. 5 percent of the total bid of the apparent low bidder
2. \$50,000

If this reduction results in the non–small business contractor becoming the low bidder or a tie with a non-small business apparent low bidder not requesting the preference, the contract award is based on the total bid, not the reduced bid.

2-1.08 DVBE INCENTIVE EVALUATION

The Department applies the Small Business and Non-Small Business preference during bid verification and proceeds with the following evaluation for DVBE incentive.

The Department grants a DVBE incentive to bidders who achieve a DVBE participation of 1 percent or greater of the value of their bid (Mil & Vet Code and Code of Regs § 1896.98 et seq).

The DVBE incentive is a reduction, for bid comparison only, in the total bid submitted by the lesser of:

1. Percentage of DVBE achievement, rounded to 2 decimal places
2. 5 percent of the total bid of the apparent low bidder
3. \$100,000

If the 2nd and 3rd low bids are within the lesser of 5 percent or \$100,000 from the low bid, the Department applies DVBE incentive to the 3 lowest bids and determines if bid ranking changes. New bid ranking cannot displace a small business bidder.

The Department proceeds with awarding the contract to the new apparent low bidder and posts the new verified bid results at its Office Engineer Web site.

2-1.09 PREFERENCE HIERARCHY

If a small business bidder and a non–small business bidder request preferences and the reductions result in a tied bid, the Department awards the contract to the small business bidder.

If a small business bidder and a non–small business bidder request preference and the reductions result in a tied bid, the Department awards the contract to the small business bidder.

If a DVBE bidder and a non-DVBE bidder request preferences and the reduction results in a tied bid, the Department awards the contract to the DVBE bidder.

2-1.10 CALIFORNIA COMPANIES

Under Pub Cont Code § 6107, the Department gives preference to a "California company," as defined, for bid comparison purposes over a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

Complete a California Company Preference form.

The California company reciprocal preference amount is equal to the preference amount applied by the state of the nonresident contractor with the lowest responsive bid unless the California company is eligible for a small business preference or a non-small business subcontractor preference; in which case the preference amount is the greater of the two, but not both.

If the bidder submitting the lowest responsive bid is a California company and with the reciprocal preference, a California company's responsive bid is equal to or less than the original lowest responsive bid, the Department awards the contract to the California company on the basis of its total bid, not the reduced bid used for comparison except as specified in Section 2-1.07, "Preference Hierarchy."

2-1.11 JOB SITE AND DOCUMENT EXAMINATION

Examine the job site and bid documents.

Bid submission is your acknowledgment that you have examined the job site and bid documents and are satisfied with:

1. General and local conditions to be encountered
2. Character, quality, and scope of work to be performed
3. Quantities of materials to be furnished
4. Character, quality, and quantity of surface and subsurface materials or obstacles
5. Requirements of the contract

2-1.12 BID DOCUMENT COMPLETION

2-1.12A General

Complete forms in the Bid book. Submit the forms with your bid except:

1. For the following 2 forms for non-federal-aid non-informal-bid contracts:
 - 1.1. Certified DVBE Summary form. You may submit this form with your bid. If you do not and you are the apparent low bidder or the second or third low bidder, submit it so that it is received at the Office Engineer no later than 4:00 p.m. on the 4th business day after bid opening. If you are not the apparent low bidder or the second or third low bidder, you are not required to submit this form unless the Department asks for it.
 - 1.2. Certified Small Business Subcontractor form. If you are applying for the non-small business subcontractor preference, you may submit this information with your bid. If you do not, submit it so that it is received at the Office Engineer no later than 4:00 p.m. on the 2nd business day after bid opening.
2. On the Subcontractor List you may either submit the percentage of each bid item subcontracted with your bid or fax the percentage to (916) 227-6282 within 24 hours after bid opening.

Except for the percentage of each bid item subcontracted, do not fax submittals.

2-1.12B Bid Item List and Bid Comparison

Submit a bid based on the work item quantities the Department shows in the Bid Item List.

For a lump sum based bid, the Department compares bids based on the total price.

For a unit price based bid, the Department compares bids based on the sum of the item totals.

For a cost plus time based bid, the Department compares bids based on the sum of the item totals and the total bid for time.

2-1.12C Subcontractor List

In the Subcontractor List, list each subcontractor to perform work in an amount in excess of 1/2 of 1 percent of the total bid or \$10,000, whichever is greater (Pub Cont Code § 4100 et seq.). The Subcontractor List must show the name, address, and work portions to be performed by each subcontractor listed. Show work portion by bid item number, description, and percentage of each bid item subcontracted.

2-1.13 BIDDER'S SECURITY

Submit your bid with one of the following forms of bidder's security equal to at least 10 percent of the bid:

1. Cash
2. Cashier's check
3. Certified check
4. Bidder's bond signed by a surety insurer who is licensed in California

Make checks and bonds payable to the Department of Transportation.

If paying with a bidder's bond, you may use the form in the Bid book. If you do not use the form in the Bid book, use a form containing the same information.

2-1.14 BID SUBMITTAL

Submit your bid:

1. Under sealed cover
2. Marked as a bid
3. Identifying the contract number and the bid opening date

If an agent other than the authorized corporation officer or a partnership member signs the bid, file a Power of Attorney with the Department either before opening bids or with the bid. Otherwise, the bid may be nonresponsive.

2-1.15 BID WITHDRAWAL

You or an authorized agent may withdraw a bid before the bid opening date and time by submitting a written bid withdrawal request at the location where the bid was submitted. Withdrawing a bid does not prevent you from submitting a new bid.

After the bid opening time, you cannot withdraw a bid.

2-1.16 BID OPENING

The Department publicly opens and reads bids at the time and place described in the Notice to Bidders. The Department invites bidders or their authorized agents to attend.

2-1.17 BID REJECTION

The Department may reject:

1. All bids
2. A nonresponsive bid

2-1.18 BID RELIEF

For a non-informal-bid contract, the Department may grant bid relief under Pub Cont Code § 5100 et seq. Submit any request for bid relief to the Office Engineer.

For an informal bid contract, the Department does grant bid relief under Pub Cont Code § 5100 et seq.

2-1.19 SUBMITTAL FAILURE HISTORY

The Department considers a bidder's past failure to submit documents required after bid opening in determining a bidder's responsibility.

2-1.20 BID RIGGING

Section 2-1.20, "Bid Rigging," applies to a Federal-aid contract.

The U.S. Department of Transportation (DOT) provides a toll-free hotline to report bid rigging activities. Use the hotline to report bid rigging, bidder collusion, and other fraudulent activities. The hotline number is (800) 424-9071. The service is available Monday through Friday between 11:00 a.m. and 8:00 p.m. and is confidential and anonymous. The hotline is part of the DOT's effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General.

2. Certificate of insurance showing all other required coverages. Certificates of insurance, as evidence of required insurance for the auto liability and any other required policy, shall set forth deductible amounts applicable to each policy and all exclusions that are added by endorsement to each policy. The evidence of insurance shall provide that no cancellation, lapse, or reduction of coverage will occur without 10 days prior written notice to the Department.
3. A declaration under the penalty of perjury by a CPA certifying the accountant has applied GAAP guidelines confirming the successful bidder has sufficient funds and resources to cover any self-insured retentions if the self-insured retention is \$50,000 or higher.

If the successful bidder uses any form of self-insurance for workers compensation in lieu of an insurance policy, it shall submit a certificate of consent to self-insure under Labor Code § 3700.

3-1.06 SMALL BUSINESS PARTICIPATION REPORT

A Small Business Participation Report will be included in the contract documents to be executed by the successful bidder. The purpose of this form is to collect small business participation data. Even if no small business participation is reported, the successful bidder must execute and return the form.

3-1.07 PAYEE DATA RECORD

The Department includes a Payee Data Record in the contract documents to be signed by the successful bidder, the payee. Complete the form.

3-1.08 CALTRANS BIDDER - DBE INFORMATION FORM

Section 3-1.07, "Caltrans Bidder - DBE Information Form," applies to a Federal-aid contract.

The Department includes a Caltrans Bidder - DBE Information form in the contract documents to be signed by the successful bidder.

The purpose of this form is to collect data required under 49 CFR 26.

Sign the form.

The Department encourages you to complete the form.

The Department encourages you to provide written confirmation from each DBE that the DBE is participating in the contract. A copy of a DBE's quote serves as written confirmation. If a DBE is participating as a joint venture partner, the Department encourages you to submit a copy of the joint venture agreement.

3-1.09 CONTRACT EXECUTION

The successful bidder must sign the contract.

Deliver to the Office Engineer:

1. Signed Contract form
2. Contract bonds
3. Documents identified in Section 3-1.05, "Insurance Policies"
4. Small Business Participation Report
5. Payee data record
6. For a Federal-aid contract, Caltrans Bidder - DBE Information form

For a non-informal-bid contract, the Office Engineer must receive these documents before the 10th business day after the bidder receives the contract.

For an informal-bid contract, the Office Engineer must receive these documents before the 5th business day after the bidder receives the contract.

The bidder's security may be forfeited for failure to execute the contract (Pub Cont Code §§ 10181 and 10182).

The following is a copy of the Contract form:

CONTRACT

DES-OE-0103A (NEW 3/2008)



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION
CONTRACT NO. _____

This contract is entered into between the State of California's Department of Transportation and the Contractor named below:

CONTRACTOR'S NAME

The parties agree to comply with the terms of the following exhibits that are by this reference made a part of this contract.

Exhibit A - Bid book dated _____

Exhibit B - Notice to Bidders and Special Provisions dated _____

Exhibit C - Project Plans approved _____

Exhibit D - Standard Specifications dated _____

Exhibit E - Standard Plans dated _____

Exhibit F - Addenda

Exhibits A, B, C, and F are those exhibits identified with the same contract number as this contract.

This contract has been executed by the following parties:

CONTRACTOR

CONTRACTOR'S NAME (if other than an individual, state whether a corporation, partnership, etc.)

BY (Authorized Signature) _____ DATE SIGNED (Do not type) _____

PRINTED NAME AND TITLE OF PERSON SIGNING _____

FEDERAL EMPLOYER IDENTIFICATION NUMBER _____

DEPARTMENT OF TRANSPORTATION

BY (Authorized Signature) _____ DATE SIGNED (Do not type) _____

PRINTED NAME AND TITLE OF PERSON SIGNING _____

ADA Notice For individuals with sensory disabilities, this document is available in alternate formats. For information call (916) 654-6410 or TDD (916) 654-3880 or write Records and Forms Management, 1120 N Street, MS-89, Sacramento, CA 95814.

3. Detailed cost estimate for performing the work under the existing contract and under the proposed change. Determine the estimates under Section 9-1.03, "Force Account Payment."
4. Deadline for the Engineer to decide on the changes.
5. Bid items affected and resulting quantity changes.

The Department is not required to consider a VECP. If a VECP is similar to a change in the plans or specifications being considered by the Department at the time the proposal is submitted or if the proposal is based on or similar to drawings or specifications adopted by the Department before Contract award, the Department does not accept the VECP and may make these changes without VECP payments.

Until the Department approves a change order incorporating the VECP or parts of it, continue to perform the work under the contract. If the Department does not approve a change order before the deadline stated in the VECP or other date you subsequently stated in writing, the VECP is rejected. The Department does not adjust time or payment for a rejected VECP.

The Department decides whether to accept a VECP and the estimated net construction-cost savings from adopting the VECP or parts of it.

The Department may require you to accept a share of the investigation cost as a condition of reviewing a VECP. After written acceptance, the Department considers the VECP and deducts the agreed cost.

If the Department accepts the VECP or parts of it, the Department issues a change order that:

1. Incorporates changes in the contract necessary to implement the VECP or the parts adopted
2. Includes the Department's acceptance conditions
3. States the estimated net construction-cost savings resulting from the VECP
4. Obligates the Department to pay you 50 percent of the estimated net savings

In determining the estimated net construction-cost savings, the Department excludes your VECP preparation cost and the Department's VECP investigation cost, including parts paid by you.

If a VECP providing for a reduction in working days is accepted by the Department, 50 percent of the reduction is deducted from contract time.

If a VECP providing for a reduction in traffic congestion or avoiding traffic congestion is accepted by the Department, the Department pays 60 percent of the estimated net savings in construction costs attributable to the VECP. Submit detailed traffic handling comparisons between the existing contract and the proposed change, including estimates of the traffic volumes and congestion.

The Department may apply an accepted VECP for general use on other contracts.

If an accepted VECP is adopted for general use, the Department pays only the contractor who first submitted the VECP and only to the contracts awarded to that contractor before the submission of the accepted VECP.

If the Department does not adopt a general-use VECP, an identical or similar submitted proposal is eligible for acceptance.

4-1.035C Value Analysis Workshop

Section 4-1.035C, "Value Analysis Workshop," applies to a non-building-work contract with a total bid of over \$5 million.

You may request a value analysis workshop by submitting a request after contract approval.

The Department offers a value analysis workshop to:

1. Identify value enhancing opportunities
2. Consider changes to the contract that will reduce the total cost of construction, construction activity duration, or traffic congestion without impairing the essential functions specified for a VECP in Section 4-1.035B, "Value Engineering Change Proposal."

If the request is authorized, you and the Engineer:

1. Schedule a value analysis workshop
2. Select a facilitator and workshop site
3. Agree to other workshop administrative details

The workshop must be conducted under the methods described in the Department's Value Analysis Team Guide available at:

<http://www.dot.ca.gov/hq/oppd/value/>

4. Developing strategies for timely communication and decision making
5. Solving potential problems at the lowest level before they negatively impact the project
6. Developing a plan for periodic joint evaluation based on the quantified mutual goals

Partnering does not void any contract part.

5-1.012B Partnering Workshop

Section 5-1.012, "Partnering Workshop," applies to a contract with a total bid of over \$1 million.

You may request a partnering workshop by submitting a request after contract approval. After the Engineer receives the request, you and the Engineer:

1. Schedule a partnering workshop
2. Select a partnering facilitator and workshop site
3. Agree to other workshop administrative details

If both parties agree, you and the Engineer conduct additional partnering workshops.

The Department reimburses you for 1/2 of the workshop cost. The workshop cost is the sum of the workshop-facilitator cost and the workshop-site cost. The Department determines the workshop cost based on the facilitator and workshop-site invoice prices minus any available or offered discounts. The Department does not pay you for any other associated costs.

5-1.012C Training in Partnering Concepts

Section 5-1.012, "Training in Partnering Concepts," applies to a contract with a total bid of \$25 million or more.

A trainer conducts a 1-day session of Training in Partnering Concepts locally for the Contractor's and the Engineer's representatives.

Send 2 representatives to the session. One of these 2 must be the assigned representative specified in Section 5-1.06, "Superintendence," of the Standard Specifications.

You and the Engineer cooperatively schedule the session and select the trainer and training site.

Upon your written request, the trainer conducts the session before the initial partnering workshop.

The Department pays for the trainer and the training site.

The Department does not pay for other costs you incur in association with the session.

Add:

5-1.015 RECORDS

5-1.015A General

Reserved

5-1.015B Record Retention

Retain project records from bid preparation through:

1. Final payment
2. Resolution of claims, if any

For at least 3 years after the later of these, retain cost records, including records of:

1. Bid preparation
2. Overhead
3. Payrolls
4. Payments to suppliers and subcontractors
5. Cost accounting

Maintain the records in an organized way in the original format, electronic and hard copy, conducive to professional review and audit.

5-1.015C Record Inspection, Copying, and Auditing

Make your records available for inspection, copying, and auditing by State representatives for the same time frame specified under Section 5-1.015B, "Record Retention." The records of subcontractors and suppliers must be made available for inspection, copying, and auditing by State representatives for the same period. Before contract acceptance, the State representative notifies the Contractor, subcontractor, or supplier 5 business days before inspection, copying, or auditing.

If an audit is to start more than 30 days after contract acceptance, the State representative notifies the Contractor, subcontractor, or supplier when the audit is to start.

5-1.015D Cost Accounting Records

Maintain cost accounting records for the project distinguishing between the following work cost categories:

1. Contract item work
2. Work character changes
3. Force account work
4. Extra work
5. Work performed under protests and claim notifications
6. Overhead
7. Subcontractors, suppliers, owner-operators, and professional services

Cost accounting records must include:

1. Final cost code lists and definitions
2. Itemization of the materials used and corresponding vendor's invoice copies
3. Direct cost of labor
4. Equipment rental charges
5. Workers' certified payrolls
6. Equipment:
 - 6.1. Size
 - 6.2. Type
 - 6.3. Identification number
 - 6.4. Hours operated

5-1.015E Extra Work Bills

Maintain separate records for force account costs.

Submit extra work bills using the Department's Internet extra work billing system.

The Contractor submitting and the Engineer approving an extra work bill using the Internet force account work billing system is the same as each party signing the report.

The Department provides billing system:

1. Training within 30 days of your written request
2. Accounts and user identification to your assigned representatives after a representative has received training

Each representative must maintain a unique password.

Replace Section 5-1.04 with:

5-1.04 CONTRACT COMPONENTS

A component in one contract part applies as if appearing in each. The parts are complementary and describe and provide for a complete work.

If a discrepancy exists:

1. The governing ranking of contract parts in descending order is:
 - 1.1. Special provisions
 - 1.2. Project plans
 - 1.3. Revised Standard Plans

- 1.4. Standard Plans
 - 1.5. Amendments to the Standard Specifications
 - 1.6. Standard Specifications
 - 1.7. Supplemental project information
2. Written numbers and notes on a drawing govern over graphics
 3. A detail drawing governs over a general drawing
 4. A detail specification governs over a general specification
 5. A specification in a section governs over a specification referenced by that section

If a discrepancy is found or confusion arises, request correction or clarification.

Add:

5-1.055 SUBCONTRACTING

5-1.055A General

No subcontract releases you from the contract or relieves you of your responsibility for a subcontractor's work.

If you violate Pub Cont Code § 4100 et seq., the Department may exercise the remedies provided under Pub Cont Code § 4110. The Department may refer the violation to the Contractors State License Board as provided under Pub Cont Code § 4111

Except for specialty item work that is done by subcontract, perform work equaling at least 50 percent of the value of the original total bid with your employees and with equipment owned or rented by you, with or without operators. Specialty items are designated by either an (S) or (S-F) in the verified Bid Item List. When the entire specialty item work is done by subcontract, the value of work will be based on the amount bid for the item. When a portion of a specialty item work is done by subcontract, the value is based on the subcontracted percentage of the amount bid for the item.

Each subcontract must comply with the contract.

Each subcontractor must have an active and valid State contractor's license with a classification appropriate for the work to be performed (Bus & Prof Code, § 7000 et seq.).

Submit copies of subcontracts upon request.

Before subcontracted work starts, submit a Subcontracting Request form.

Do not use a debarred contractor; a current list of debarred contractors is available at the Department of Industrial Relations' Web site.

Upon request, immediately remove and not again use a subcontractor who fails to prosecute the work satisfactorily.

5-1.055B Disadvantaged Business Enterprises

Section 5-1.055B, "Disadvantaged Business Enterprises," applies to a Federal-aid contract.

Use each subcontractor as listed on the Subcontractor List form unless you receive authorization for a substitution.

The Department requests the Contractor to:

1. Notify the Engineer of any changes to its anticipated DBE participation
2. Provide this notification before starting the affected work

Maintain records including:

1. Name and business address of each 1st-tier subcontractor
2. Name and business address of each DBE subcontractor, DBE vendor, and DBE trucking company, regardless of tier
2. Date of payment and total amount paid to each business

If you are a DBE contractor, include the date of work performed by your own forces and the corresponding value of the work.

Before the 15th of each month, submit a Monthly DBE Trucking Verification form.

For a DBE that leases trucks from a non-DBE, count only the fee or commission the DBE receives as a result of the lease arrangement.

If a DBE subcontractor is decertified before completing subcontracted work, the subcontractor must notify you in writing of the decertification date. If a subcontractor becomes a certified DBE before completing subcontracted work, the subcontractor must notify you in writing of the certification date. Submit the notifications. On contract work completion, complete a Disadvantaged Business Enterprises (DBE) Certification Status Change form. Submit the form within 90 days of contract acceptance.

Upon contract work completion, complete a Final Report – Utilization of Disadvantaged Business Enterprises (DBE), First-Tier Subcontractors form. Submit it within 90 days of contract acceptance. The Department withholds \$10,000 until the form is submitted. The Department releases the withhold upon submission of the completed form.

5-1.055C Disabled Veteran Business Enterprises

Section 5-1.055C, "Disabled Veteran Business Enterprises," applies to a non-Federal-aid contract.

If a DVBE goal is shown in the Notice to Bidders:

1. Use each DVBE as shown on the Certified DVBE Summary form unless you receive authorization for a substitution
2. The requirement that DVBEs be certified by the bid opening date does not apply to DVBE substitutions after contract award
3. Maintain records of subcontracts made with certified DVBEs. Include in the records:
 - 3.1. Name and business address of each business
 - 3.2. Total amount paid to each business
4. For the purpose of determining compliance with Pub Cont Code § 10115 et seq.:
 - 4.1. Provide the Department relevant information requested
 - 4.2. Upon reasonable notice and during normal business hours, permit access to its premises for the purpose of:
 - 4.2.1. Interviewing employees
 - 4.2.2. Inspecting and copying books, records, accounts and other material that may be relevant to a matter under investigation

If no DVBE goal is shown in the Notice to Bidders and if you obtain DVBE participation, submit the participating DVBE names and value of work or supplies supplied by each DVBE transaction upon contract completion.

5-1.055D Non-Small Businesses

Section 5-1.055D, "Non-Small Businesses," applies to a non-Federal-aid contract.

Use each subcontractor as shown on the Certified Small Business Listing for the Non-Small Business Preference form unless you receive authorization for a substitution.

The requirement that small businesses be certified by the bid opening date does not apply to small business substitutions after contract award.

Maintain records of subcontracts made with certified small business subcontractors and records of materials purchased from certified small business suppliers. Include in the records:

1. Name and business address of each business
2. Total amount paid to each business

For the purpose of determining compliance with 2 CA Code of Regs § 1896 et seq.:

1. Provide the Department relevant information requested.
2. Upon reasonable notice and during normal business hours, permit access to its premises for the purpose of:
 - 2.1. Interviewing employees
 - 2.2. Inspecting and copying books, records, accounts and other material that may be relevant to a matter under investigation

Replace Section 5-1.07 with:

5-1.07 LINES AND GRADES

The Engineer places stakes and marks under Chapter 12, "Construction Surveys," of the Department's Surveys Manual. Submit your request for Department-furnished stakes:

1. On a Request for Construction Stakes form. Ensure:
 - 1.1. Requested staking area is ready for stakes
 - 1.2. You use the stakes in a reasonable time
2. A reasonable time before starting an activity using the stakes

Establish priorities for stakes and note priorities on the request.

Preserve stakes and marks placed by the Engineer. If the stakes or marks are destroyed, the Engineer replaces them at the Engineer's earliest convenience and deducts the cost.

Replace Section 5-1.116 with:

5-1.116 DIFFERING SITE CONDITIONS (23 CFR 635.109)

5-1.116A Contractor's Notification

Promptly notify the Engineer if you find either of the following:

1. Physical conditions differing materially from either of the following:
 - 1.1. Contract documents
 - 1.2. Job site examination
2. Physical conditions of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in the work provided for in the contract

Include details explaining the information you relied on and the material differences you discovered.

If you fail to notify the Engineer promptly, you waive the differing site condition claim for the period between your discovery of the differing site condition and your notification to the Engineer.

If you disturb the site after discovery and before the Engineer's investigation, you waive the differing site condition claim.

5-1.116B Engineer's Investigation and Decision

Upon your notification, the Engineer investigates job site conditions and:

1. Notifies you whether to resume affected work
2. Decides whether the condition differs materially and is cause for an adjustment of time, payment, or both

5-1.116C Protests

You may protest the Engineer's decision by:

1. Submitting an Initial Notice of Potential Claim within 5 business days after receipt of the Engineer's notification
2. Complying with claim procedures

The Initial Notice of Potential Claim must detail the differences in your position from the Engineer's determination and support your position with additional information, including additional geotechnical data. Attach to the Initial Notice of Potential Claim a certification stating that you complied with Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work."

Promptly submit supplementary information when obtained.

Add:

5-1.15 DISPUTE RESOLUTION

5-1.15A General

Section 5-1.15, "Dispute Resolution," applies to a contract with 100 or more working days.

In the Dispute Resolution Advisor Agreement and in the Dispute Review Board Agreement, interpret a reference to the special provisions as a reference to the Amendments to the Standard Specifications. In the Dispute Review Board Agreement, replace "Proposal and Contract" with "Bid book." Where the section title does not match the section number for a reference, refer to the referenced title.

5-1.15B Dispute Resolution Advisor

Section 5-1.15B, "Dispute Resolution Advisor," applies to a contract from \$3 million to \$10 million.

A dispute resolution advisor, hereinafter referred to as "DRA", is chosen by the Department and the Contractor to assist in the resolution of disputes. The DRA is a part of the contract administrative claims process as specified in the provisions in Section 9-1.04, "Notice of Potential Claim," and Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. The DRA shall not serve as a substitute for filing a protest or a notice of potential claim.

The DRA shall be established by the Department and the Contractor within 30 days of contract approval.

The Department and the Contractor shall each propose 3 potential DRA candidates. Each potential candidate shall provide the Department and the Contractor with their disclosure statement. The disclosure statement shall include a resume of the potential candidate's experience and a declaration statement describing past, present, anticipated, and planned relationships with all parties involved in this contract.

The Department and the Contractor shall select one of the 6 nominees to be the DRA. If the Department and the Contractor cannot agree on one candidate, the Department and the Contractor shall each choose one of the 3 nominated by the other. The final selection of the DRA will be decided by a coin toss between the two candidates.

The Department and the Contractor shall complete and adhere to the Dispute Resolution Advisor Agreement. No DRA meeting shall take place until the Dispute Resolution Advisor Agreement has been signed by all parties, unless all parties agree to sign it at the first meeting.

If DRA needs outside technical services, technical services shall be preapproved by both the Department and the Contractor.

DRA recommendations are nonbinding.

The Contractor shall not use the DRA for disputes between subcontractors or suppliers that have no grounds for a lawsuit against the Department.

DRA replacement is selected in the same manner as the original selection. The appointment of a replacement DRA will begin promptly upon determination of the need for replacement. The Dispute Resolution Advisor Agreement shall be amended to reflect the change of the DRA.

Failure of the Contractor to participate in selecting DRA will result in the withhold of 25 percent of the estimated value of all work performed during each estimate period that the Contractor fails to comply. DRA withholds will be released for payment on the next monthly progress payment following the date that the Contractor has provided assistance in choosing the DRA and no interest will be due the Contractor.

The State and the Contractor shall bear the costs and expenses of the DRA equally.

The DRA shall be compensated at an agreed rate of \$1,500 per day for time spent per meeting either at the start of the project or for a dispute. A member serving on more than one State DRA or Dispute Review Board, regardless the number of meetings per day shall not be paid more than the agreed rate per day. The agreed rate shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel, and incidentals for each day or portion thereof that the DRA is at an authorized DRA meeting.

No additional compensation will be made for time spent by the DRA to review and research activities outside the official DRA meetings unless that time, such as time spent evaluating and preparing recommendations on specific issues presented to the DRA, has been specifically agreed to in advance by the State and Contractor. Time away from the project that has been specifically agreed to in advance by the Department and the Contractor will be compensated at an agreed rate of \$150 per hour. The agreed amount of \$150 per hour shall include all incidentals including expenses for telephone, fax, and computer services.

The State will provide conference facilities for DRA meetings at no cost to the Contractor.

The Contractor shall make direct payments to the DRA for participation in authorized meetings and approved hourly rate charges from invoices submitted.

The State will reimburse the Contractor for the State's share of the costs.

There will be no markups applied to expenses associated with the DRA, either by the DRA or by the Contractor when requesting payment of the State's share of DRA expenses. Regardless of the DRA recommendation, neither party will be entitled to reimbursement of DRA costs from the other party.

The Contractor shall submit extra work bills and include invoices with original supporting documents for reimbursement of the State's share.

The cost of technical services will be borne equally by the State and Contractor. There will be no markups for these costs.

A copy of the "Dispute Resolution Advisor Agreement" to be executed by the Contractor, State and the DRA is as follows:

Form CEM 6206 Rev (04-06-07)

DISPUTE RESOLUTION ADVISOR AGREEMENT

(Contract Identification)

Contract No. _____

THIS DISPUTE RESOLUTION ADVISOR AGREEMENT, hereinafter called "AGREEMENT", made and entered into this _____ day of _____, _____, between the State of California, acting through the California Department of Transportation and the Director of Transportation, hereinafter called the "STATE," _____ hereinafter called the "CONTRACTOR," and _____, the Dispute Resolution Advisor, hereinafter called the "DRA." .

WITNESSETH, that

WHEREAS, the STATE and the CONTRACTOR, hereinafter called the "parties," are now engaged in the construction on the State Highway project referenced above; and

WHEREAS, the special provisions for the above referenced contract provides for the establishment and operation of the DRA to assist in resolving disputes; and

WHEREAS, the DRA is composed of one person, chosen by the CONTRACTOR and the STATE;

NOW THEREFORE, in consideration of the terms, conditions, covenants, and performance contained herein, or attached and incorporated and made a part hereof, the STATE, the CONTRACTOR, and the DRA hereto agree as follows:

SECTION I DESCRIPTION OF WORK

To assist in the timely resolution of disputes between the parties, the contract provides for the establishment and the operation of the DRA. The DRA is to fairly and impartially consider disputes placed before it and provide recommendations for resolution of these disputes to the parties. The DRA shall provide recommendations based on the facts related to the dispute, the contract and applicable laws and regulations. The DRA shall perform the services necessary to participate in the DRA's actions as designated in Section III, Scope of Work.

SECTION II DRA QUALIFICATIONS

DRA shall be knowledgeable in the type of construction and contract documents anticipated by the contract and shall have completed training through the Dispute Review Board Foundation. In addition, it is desirable for the DRA to have served on several State Dispute Review Boards (DRB).

No DRA shall have prior direct involvement in this contract. No DRA shall have a financial interest in this contract or parties thereto, including but not limited to the CONTRACTOR, subcontractors, suppliers, consultants, and legal and business services, within a period 6 months prior to award and during this contract. Exceptions to above are compensation for services on this or other DRAs and DRBs or retirement payments or pensions received from a party that are not tied to, dependent on or affected by the net worth of the party.

DRA shall fully disclose all direct or indirect professional or personal relationships with all key members of the contract.

SECTION III SCOPE OF WORK

The Scope of Work of the DRA includes, but is not limited to, the following:

A. PROCEDURES

The DRA shall meet with the parties at the start of the project to establish procedures that will govern the conduct of its business and reporting procedures in conformance with the requirements of the contract and the terms of this AGREEMENT. The DRA established procedures shall only be implemented upon approval by the parties. Subsequent meetings shall be held only to hear disputes between the parties.

The DRA shall not meet with, or discuss contract issues with individual parties.

State shall provide the DRA with the contract and all written correspondence regarding the dispute between the parties and, if available, the Contractor's supplemental notice of potential claim, and the Engineer's response to the supplemental notice of potential claim.

The parties shall not call the DRA who served on this contract as a witness in arbitration proceedings, which may arise from this contract.

The DRA shall have no claim against the STATE or the CONTRACTOR, or both, from claimed harm arising out of the parties' evaluations of the DRA's opinions.

B. DISPUTE MEETING

The term "dispute meeting" as used in this subsection shall refer to both the informal and traditional dispute meeting processes, unless otherwise noted.

If the CONTRACTOR requests a dispute meeting with the DRA, the Contractor must simultaneously notify the STATE. Upon being notified of the need for a dispute meeting, the DRA shall review and consider the dispute. The DRA shall determine the time and location of the dispute meeting with due consideration for the needs and preferences of the parties, while recognizing the importance of a speedy resolution to the dispute.

Dispute meetings shall be conducted at any location that would be convenient and provide required facilities and access to necessary documentation.

Only the STATE's Resident Engineer or Area Construction Engineer and the CONTRACTOR's or subcontractor's, if the dispute involves a subcontractor, Superintendent or Project Manager may present information at a dispute meeting. There shall be no participation of persons who are not directly involved in the contract or who do not have direct knowledge of the dispute. The exception to this is technical services, as described below:

The DRA, with approval of the parties, may obtain technical services necessary to adequately review the disputes presented, including audit, geotechnical, schedule analysis and other services. The parties' technical staff may supply those services as appropriate. The cost of technical services, as agreed to by the parties, shall be borne equally by the two parties as specified in an approved contract change order. The CONTRACTOR shall not be entitled to markups for the payments made for these services.

At the dispute meeting the DRA may ask questions, seek clarification, and request further clarification of data presented by either of the parties as may be necessary to assist in making a fully informed recommendation. However, the DRA shall refrain from expressing opinions on the merits of statements on matters under dispute during the parties' presentations. Each party will be given ample time to fully present its position, make rebuttals, provide relevant documents, and respond to DRA questions and requests.

There shall be no testimony under oath or cross-examination, during DRA dispute meetings. There shall be no reporting of the procedures by a shorthand reporter or by electronic means. Documents and verbal statements shall be received by the DRA in conformance with the rules and regulations established at the first meeting between the DRA and parties. These established rules and regulations need not comply with prescribed legal laws of evidence.

Failure to attend a dispute meeting by either of the parties shall be conclusively considered by the DRA as indication that the non-attending party considers all written documents and correspondence submitted as their entire and complete argument. The claimant shall discuss the dispute, followed by the other party. Each party shall then be allowed one or more rebuttals at the meeting until all aspects of the dispute are thoroughly covered.

1. TRADITIONAL DISPUTE MEETING:

The following procedure shall be used for the traditional dispute meeting:

- a. Within 5 days, after receiving the STATE's written response to the CONTRACTOR's supplemental notice of potential claim, the CONTRACTOR shall refer the dispute to the DRA, if the CONTRACTOR wishes to further pursue the dispute. The CONTRACTOR shall make the referral in writing to the DRA, simultaneously copied to the STATE. The written dispute referral shall describe the disputed matter in individual discrete segments, so that it will be clear to both parties and the DRA what discrete elements of the dispute have been resolved, and which remain unresolved, and shall include an estimate of the cost of the affected work and impacts, if any, on project completion.
- b. The parties shall each be afforded an opportunity to be present and to be heard by the DRA, and to offer evidence. Either party furnishing written evidence or documentation to the DRA must furnish copies of such information to the other party a minimum of 10 days prior to the date the DRA is scheduled to convene the meeting for the dispute. Either party shall produce such additional evidence as the DRA may deem necessary to reach an understanding and a determination of the dispute. The party furnishing additional evidence shall furnish copies of such additional evidence to the other party at the same time the evidence is provided to the DRA. The DRA shall not consider evidence not furnished in conformance with the terms specified herein.
- c. Upon receipt by the DRA of a written referral of a dispute, the DRA shall convene to review and consider the dispute. The dispute meeting shall be held no later than 25 days after receipt of the written referral unless otherwise agreed to by all parties.
- d. The DRA shall furnish a written report to both parties. The DRA may request clarifying information of either party within 5 days after the DRA dispute meeting. Requested information shall be submitted to the DRA within 5 days of the DRA request. The DRA shall complete its report and submit it to the parties within 10 days of the DRA dispute meeting, except that time extensions may be granted at the request of the DRA with the written concurrence of both parties. The report shall summarize the facts considered, the contract language, law or regulation viewed by the DRA as pertinent to the dispute, and the DRA's interpretation and philosophy in arriving at its conclusions and recommendations and, if appropriate, recommends guidelines for determining compensation. The DRA's written opinion shall stand on its own, without attachments or appendices.
- e. Within 10 days after receiving the DRA's report, both parties shall respond to the DRA in writing signifying that the dispute is either resolved or remains unresolved. Failure to provide the written response within the time specified, or a written rejection of the DRA's recommendation or response to a request for reconsideration presented in the report by either party, shall conclusively indicate that the party(s) failing to respond accepts the DRA recommendation. Immediately after responses have been received from both parties, the DRA shall provide copies of both responses to the parties simultaneously. Either party may request clarification of elements of the DRA's report from the DRA prior to responding to the report. The DRA shall consider any clarification request only if submitted within 5 days of receipt of the DRA's report, and if submitted simultaneously in writing to both the DRA and the other party. Each party may submit only one request for clarification for any individual DRA report. The DRA shall respond, in writing, to requests for clarification within 5 days of receipt of such requests.
- f. Either party may seek a reconsideration of the DRA's recommendation. The DRA shall only grant reconsideration based upon submission of new evidence and if the request is submitted within the 10 day time limit specified for response to the DRA's written report. Each party may submit only one request for reconsideration regarding an individual DRA recommendation.
- g. If the parties are able to settle their dispute with the aid of the DRA's report, the STATE and CONTRACTOR shall promptly accept and implement the settlement of the parties. If the parties cannot agree on compensation within 30 days of the acceptance by both parties of the settlement, either party may request the DRA to make a recommendation regarding compensation.

2. INFORMAL DISPUTE MEETING

An informal dispute meeting shall be convened, only if, the parties and the DRA agree that this dispute resolution process is appropriate to settle the dispute.

The following procedure shall be used for the informal dispute meeting:

- a. The parties shall furnish the DRA with one copy of pertinent documents requested by the DRA that are or may become necessary for the DRA to perform its function. The party furnishing documents shall furnish such documents to the other party at the same time the document is provided to the DRA.
- b. After the dispute meeting has concluded; the DRA shall deliberate in private the same day, until a response to the parties is reached or as otherwise agreed to by the parties.
- c. The DRA then verbally delivers its recommendation with findings to the parties.
- d. After the recommendation is presented, the parties may ask for clarifications.

- e. Occasionally the DRA on complex issues may be unable to formulate a recommendation based on the information given at a dispute meeting. However, the DRA may provide the parties with advice on strengths and weaknesses of their prospective positions, in the hope of the parties reaching settlement.
- f. If the parties are able to settle their dispute with the aid of the DRA's opinion, the STATE and CONTRACTOR shall promptly accept and implement the settlement of the parties.
- g. The DRA will not be bound by its oral recommendation in the event that a dispute is later heard by the DRA in a traditional dispute meeting.

Unless the dispute is settled, use of the informal dispute meeting does not relieve the parties of their responsibilities under Section 5-1.12, "Dispute Resolution Advisor," of the Special Provisions or Subsection, "Traditional Dispute Meeting," of this AGREEMENT. There will be no extension of time allowed for the process to permit the use of the informal dispute meeting, unless otherwise agreed to by the parties.

SECTION IV TIME FOR BEGINNING AND COMPLETION

Once established, the DRA shall be in operation until the day the Director accepts the contract. The DRA shall not begin work under the terms of this AGREEMENT until authorized in writing by the STATE or as agreed to by the parties.

SECTION V PAYMENT

DRA shall be compensated at an agreed rate of \$1,500 per day for time spent per meeting, either at the start of the project or for a dispute. A member serving on more than one State DRA or DRB, regardless the number of meetings per day, shall not be paid more than the agreed rate per day. The agreed rate shall be considered full compensation for onsite time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof that the DRA is at an authorized DRA meeting. No additional compensation will be made for time spent by DRA to review and research activities outside the official DRA meetings unless that time, (such as time spent evaluating and preparing recommendations on specific issues presented to the DRA), has been specifically agreed to in advance by the parties. Time away from the project, which has been specifically agreed to in advance by the parties, will be compensated at an agreed rate of \$150 per hour. The agreed amount of \$150 per hour shall include all incidentals including expenses for telephone, fax, and computer services. The State will provide administrative services such as conference facilities to the DRA.

A. PAYMENT PROCESSING

CONTRACTOR shall make direct payments to DRA for their participation in authorized meetings and approved hourly rate charges, from invoices submitted by the DRA, and technical services.

DRA may submit invoices to the CONTRACTOR for partial payment for work performed and services rendered for their participation in authorized meetings not more often than once per month during the progress of the work. The invoices shall be in a format approved by the parties and accompanied by a general description of activities performed during that billing period. Payment for hourly fees, at the agreed rate, shall not be paid to a DRA until the amount and extent of those fees are approved by the STATE and CONTRACTOR.

B. INSPECTION OF COSTS RECORDS

DRA and the CONTRACTOR shall keep available for inspection by representatives of the STATE and the United States, for a period of 3 years after final payment, the cost records and accounts pertaining to this AGREEMENT. If any litigation, claim, or audit arising out of, in connection with, or related to this contract is initiated before the expiration of the 3-year period, the cost records and accounts shall be retained until such litigation, claim, or audit involving the records is completed.

SECTION VI ASSIGNMENT OF TASKS OF WORK

DRA shall not assign the work of this AGREEMENT.

SECTION VII TERMINATION OF A DRA MEMBER

DRA may resign after providing not less than 15 days written notice of the resignation to the STATE and CONTRACTOR. The DRA may be terminated, by either party, for failing to fully comply at all times with all required employment or financial disclosure conditions of DRA membership in conformance with the terms of the contract and this AGREEMENT. Each party shall document the need for replacement and substantiate the replacement request in writing to the other party and the DRA.

SECTION VIII LEGAL RELATIONS

The parties hereto mutually understand and agree that the DRA in the performance of duties is acting in the capacity of an independent agent and not as an employee of either party.

No party to this AGREEMENT shall bear a greater responsibility for damages or personal injury than is normally provided by Federal or State of California Law.

Notwithstanding the provisions of this contract that require the CONTRACTOR to indemnify and hold harmless the STATE, the parties shall jointly indemnify and hold harmless the DRA from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRA.

SECTION IX CONFIDENTIALITY

The parties hereto mutually understand and agree that all documents and records provided by the parties in reference to issues brought before the DRA, which documents and records are marked "Confidential - for use by the DRA only," shall be kept in confidence and used only for the purpose of resolution of subject disputes, and for assisting in development of DRA findings and recommendations; that such documents and records will not be utilized or revealed to others, except to officials of the parties who are authorized to act on the subject disputes, for any purposes, during the life of this AGREEMENT. Upon termination of this AGREEMENT, said confidential documents and records, and all copies thereof, shall be returned to the parties who furnished them to the DRA. However, the parties understand that such documents may be subsequently discoverable and admissible in court or arbitration proceedings unless a protective order has been obtained by the party seeking further confidentiality.

SECTION X DISPUTES

Disputes between the parties arising out of the work or other terms of this AGREEMENT that cannot be resolved by negotiation and mutual concurrence between the parties or through the administrative process provided in the contract shall be resolved by arbitration as provided in Section 9-1.10, "Arbitration," of the Standard Specifications. Disputes between the DRA and the parties that cannot be resolved by negotiation and mutual concurrence shall be resolved in the appropriate forum.

SECTION XI VENUE, APPLICABLE LAW, AND PERSONAL JURISDICTION

In the event that any party, including the DRA, deems it necessary to institute arbitration proceedings to enforce any right or obligation under this AGREEMENT, the parties hereto agree that such action shall be initiated in the Office of Administrative Hearings of the State of California. The parties hereto agree that all questions shall be resolved by arbitration by application of California law and that the parties to such arbitration shall have the right of appeal from such decisions to the Superior Court in conformance with the laws of the State of California. Venue for the arbitration shall be Sacramento or any other location as agreed to by the parties.

SECTION XII FEDERAL REVIEW AND REQUIREMENTS

On Federal-Aid contracts, the Federal Highway Administration shall have the right to review the work of the DRA in progress, except for private meetings or deliberations of the DRA.

Other Federal requirements in this agreement shall only apply to Federal-Aid contracts.

SECTION XIII CERTIFICATION OF CONTRACTOR, DRA, AND STATE

IN WITNESS WHEREOF, the parties hereto have executed this AGREEMENT as of the day and year first above written.

DRA

By: _____

Title: _____

CONTRACTOR

CALIFORNIA STATE DEPARTMENT
OF TRANSPORTATION

By: _____

By: _____

Title: _____

Title: _____

5-1.15C Dispute Review Board

- Section 5-1.15C, "Dispute Review Board," applies to a contract over \$10 million.

5-1.15C(1) General

To assist in the resolution of disputes or potential claims arising out of the work of this project, a Dispute Review Board, hereinafter referred to as the "DRB," shall be established by the Engineer and Contractor cooperatively upon approval of the contract. The DRB is intended to assist the contract administrative claims resolution process as specified in the provisions in Section 9-1.04, "Notice of Potential Claim," and Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications and these special provisions. The DRB shall not serve as a substitute for provisions in the specifications in regard to filing potential claims. The requirements and procedures established in this section shall be a prerequisite to filing a claim, filing for arbitration, or filing for litigation prior or subsequent to project completion.

The DRB shall be utilized when dispute or potential claim resolution at the project level is unsuccessful. The DRB shall function as specified herein until the day of acceptance of the contract, at which time the work of the DRB will cease except for completion of unfinished reports. No DRB dispute meetings shall take place later than 30 days prior to acceptance of contract. After acceptance of contract, disputes or potential claims which have followed the dispute resolution processes of the Standard Specifications and these special provisions, but have not been resolved, shall be stated or restated by the Contractor, in response to the Proposed Final Estimate within the time limits provided in Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. The State will review those claims in conformance with the provisions in Section 9-1.07B of the Standard Specifications. Following the adherence to and completion of the contractual administrative claims procedure, the Contractor may file for arbitration in conformance with the provisions in Section 9-1.10, "Arbitration," of the Standard Specifications and these special provisions.

Disputes, as used in this section, shall include differences of opinion, properly noticed as provided hereinafter, between the State and Contractor on matters related to the work and other subjects considered by the State or Contractor, or by both, to be of concern to the DRB on this project, except matters relating to Contractor, subcontractor or supplier potential claims not actionable against the Department as specified in these special provisions or quantification of disputes for overhead type expenses or costs. Disputes for overhead type expenses or costs shall conform to the requirements of Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. Whenever the term "dispute" or "disputes" is used herein, it shall be deemed to include potential claims as well as disputes.

The DRB shall serve as an advisory body to assist in the resolution of disputes between the State and the Contractor, hereinafter referred to as the "parties." The DRB shall consider disputes referred to it, and furnish written reports containing findings and recommendations pertaining to those disputes, to the parties to aid in resolution of the differences between them. DRB findings and recommendations are not binding on the parties.

5-1.15C(2) Selection Process, Disclosure and Appointments

The DRB shall consist of one member selected by the State and approved by the Contractor, one member selected by the Contractor and approved by the State, and a third member selected by the first 2 members and approved by both the State and the Contractor. The third member shall act as the DRB Chairperson.

DRB members shall be especially knowledgeable in the type of construction and contract documents potentially anticipated by the contract. DRB members shall discharge their responsibilities impartially as an independent body, considering the facts and circumstances related to the matters under consideration, pertinent provisions of the contract and applicable laws and regulations.

The State and the Contractor shall nominate and approve DRB members in conformance with the terms and conditions of the Dispute Review Board Agreement and these special provisions, within 45 days of the approval of the contract. Each party shall provide written notification to the other of the name of their selected DRB nominee along with the prospective member's complete written disclosure statement.

Disclosure statements shall include a resume of the prospective member's experience and a declaration statement describing past, present, anticipated, and planned relationships, including indirect relationships through the prospective member's primary or full-time employer, to this project and with the parties involved in this construction contract, including but not limited to, relevant subcontractors or suppliers to the parties, parties' principals, or parties' counsel. DRB members shall also include a full disclosure of close professional or personal relationships with all key members of the contract. Objections to nominees must be based on a specific breach or violation of nominee responsibilities or on nominee qualifications under these provisions unless otherwise specified. The Contractor or the State may, on a one-time basis, object to the other's nominee without specifying a reason and this person will not be selected for the DRB. Another person shall then be nominated within 15 days.

The first duty of the State and Contractor selected members of the DRB shall be to select and recommend a prospective third DRB member to the parties for final selection and approval. The first 2 DRB members shall proceed with the selection of the third DRB member immediately upon receiving written notification from the State of their selection, and shall provide their recommendation simultaneously to the parties within 15 days of the notification.

The first 2 DRB members shall select a third DRB member subject to mutual approval of the parties or may mutually concur on a list of potentially acceptable third DRB members and submit the list to the parties for final selection and approval of the third member. The goal in the selection of the third member is to complement the professional experience of the first 2 members and to provide leadership for the DRB's activities.

The third prospective DRB member shall supply a full disclosure statement to the first 2 DRB members and to the parties prior to appointment.

An impasse shall be considered to have been reached if the parties are unable to approve a third member within 15 days of receipt of the recommendation of the first 2 DRB members, or if the first 2 DRB members are unable to agree upon a recommendation within their 15 day time limit. In the event of an impasse in selection of third DRB member the State and the Contractor shall each propose 3 candidates for the third DRB member position. The parties shall select the candidates proposed under this paragraph from the current list of arbitrators certified by the Public Works Contract Arbitration Committee created by Article 7.2 (commencing with Section 10245) of the State Contract Act. The first 2 DRB members shall then select one of the 6 proposed candidates in a blind draw.

No DRB member shall have prior direct involvement in this contract. No member shall have a financial interest in this contract or the parties thereto, within a period of 6 months prior to award of this contract or during the contract, except as follows:

- A. Compensation for services on this DRB.
- B. Ownership interest in a party or parties, documented by the prospective DRB member, that has been reviewed and determined in writing by the State to be sufficiently insignificant to render the prospective member acceptable to the State.
- C. Service as a member of other Dispute Review Boards on other contracts.
- D. Retirement payments or pensions received from a party that are not tied to, dependent on or affected by the net worth of the party.
- E. The above provisions apply to parties having a financial interest in this contract, including but not limited to contractors, subcontractors, suppliers, consultants, and legal and business services.

The Contractor or the State may reject any of the 3 DRB members who fail to fully comply at all times with all required employment and financial disclosure conditions of DRB membership as described in the Dispute Review Board Agreement and as specified herein. A copy of the Dispute Review Board Agreement is included in this section.

The Contractor, the State, and the 3 members of the DRB shall complete and adhere to the Dispute Review Board Agreement in administration of this DRB within 15 days of the parties' concurrence in the selection of the third member. No DRB meeting shall take place until the Dispute Review Board Agreement has been signed by all parties. The State authorizes the Engineer to execute and administer the terms of the Agreement. The person(s) designated by the Contractor as authorized to execute contract change orders shall be authorized to execute and administer the terms of this agreement, or to delegate the authority in writing. The operation of the DRB shall be in conformance with the terms of the Dispute Review Board Agreement.

5-1.15C(3) Compensation

• The State and the Contractor shall bear the costs and expenses of the DRB equally. Each DRB member shall be compensated at an agreed rate of \$1,200 per day if time spent per meeting, including on-site time plus one hour of travel time, is greater than 4 hours. Each DRB member shall be compensated at an agreed rate of \$700 per day if time spent per meeting, including on-site time plus one hour of travel time, is less than or equal to 4 hours. The agreed rates shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof, that the DRB member is at an authorized DRB meeting. No additional compensation will be made for time spent by DRB members in review and research activities outside the official DRB meetings unless that time, (such as time spent evaluating and preparing recommendations on specific issues presented to the DRB), has been specifically agreed to in advance by the State and Contractor. Time away from the project, which has been specifically agreed to in advance by the parties, will be compensated at an agreed rate of \$125 per hour. The agreed amount of \$125 per hour shall include all incidentals including expenses for telephone, fax, and computer services. Members serving on more than one DRB involving the Department, regardless of the number of meetings per day, shall not be paid more than the all inclusive rate per day or rate per hour for an individual project. The State will provide, at no cost to the Contractor, administrative services such as conference facilities and secretarial services to the DRB. These special provisions and the Dispute Review Board Agreement state the provisions for compensation and expenses of the DRB. DRB members shall be compensated at the same daily and hourly rate. The Contractor shall make direct payments to each DRB member for their participation in authorized meetings and approved hourly rate charges from invoices submitted by each DRB member. The State will reimburse the Contractor for the State's share of the costs. There will be no markups applied to expenses connected with the DRB, either by the DRB members or by the Contractor when requesting payment of the State's share of DRB expenses. Regardless of the DRB recommendation, neither party shall be entitled to reimbursement of DRB costs from the other party.

5-1.15C(4) Replacement of DRB Members

Service of a DRB member may be terminated at any time with not less than 15 days notice as follows:

- A. The State may terminate service of the State appointed member.
- B. The Contractor may terminate service of the Contractor appointed member.
- C. Upon the written recommendation of the State and Contractor appointed members for the removal of the third member.
- D. Upon resignation of a member.
- E. The State or Contractor may terminate the service of any member who fails to fully comply with all required employment and financial disclosure conditions of DRB membership.

When a member of the DRB is replaced, the replacement member shall be appointed in the same manner as the replaced member was appointed. The appointment of a replacement DRB member will begin promptly upon determination of the need for replacement and shall be completed within 15 days. Changes in either of the DRB members chosen by the 2 parties will not require re-selection of the third member, unless both parties agree to such re-selection in writing. The Dispute Review Board Agreement shall be amended to reflect the change of a DRB member.

5-1.15C(5) Operation

The following procedure shall be used for dispute resolution:

- A. If the Contractor objects to any decision, act or order of the Engineer, the Contractor shall give written notice of potential claim in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and these special provisions, including the provision of applicable cost documentation; or file written protests or notices in conformance with the provisions in the Standard Specifications and these special provisions.
- B. The Engineer will respond, in writing, to the Contractor's written supplemental notice of potential claim within 20 days of receipt of the notice.
- C. Within 15 days after receipt of the Engineer's written response, the Contractor shall, if the Contractor still objects, file a written reply with the Engineer, stating clearly and in detail the basis of the objection.

- D. Following an objection to the Engineer's written response, the Contractor shall refer the dispute to the DRB if the Contractor wishes to further pursue the objection to the Engineer's decision. The Contractor shall make the referral in writing to the DRB, simultaneously copied to the State, within 21 days after receipt of the written response from the Engineer. The written dispute referral shall describe the disputed matter in individual discrete segments so that it will be clear to both parties and the DRB what discrete elements of the dispute have been resolved, and which remain unresolved, and shall include an estimate of the cost of the affected work and impacts, if any, on project completion.
- E. By failing to submit the written notice of referral to the DRB, within 21 days after receipt of the Engineer's written response to the supplemental notice of potential claim, the Contractor waives future claims and arbitration on the matter in contention.
- F. The Contractor and the State shall each be afforded an opportunity to be present and to be heard by the DRB, and to offer evidence. Either party furnishing written evidence or documentation to the DRB must furnish copies of such information to the other party a minimum of 15 days prior to the date the DRB is scheduled to convene the meeting for the dispute. Either party shall produce such additional evidence as the DRB may deem necessary to reach an understanding and a determination of the dispute. The party furnishing additional evidence shall furnish copies of such additional evidence to the other party at the same time the evidence is provided to the DRB. The DRB shall not consider evidence not furnished in conformance with the terms specified herein.
- G. Upon receipt by the DRB of a written referral of a dispute, the DRB shall convene to review and consider the dispute. The dispute meeting shall be held no earlier than 30 days and no later than 60 days after receipt of the written referral unless otherwise agreed to by all parties. The DRB shall determine the time and location of the DRB dispute meeting, with due consideration for the needs and preferences of the parties while recognizing the paramount importance of a timely hearing of the dispute.
- H. There shall be no participation of either party's attorneys at DRB dispute meetings.
- I. There shall be no participation of persons who are not directly involved in the contract or who do not have direct knowledge of the dispute, including but not limited to consultants, except for expert testimony allowed at the discretion of the DRB and with approval prior to the dispute meeting by both parties.
- J. The DRB shall furnish a report, containing findings and recommendations as described in the Dispute Review Board Agreement, in writing to both the State and the Contractor. The DRB may request clarifying information of either party within 10 days after the DRB dispute meeting. Requested information shall be submitted to the DRB within 10 days of the DRB request. The DRB shall complete its report, including minority opinion, if any, and submit it to the parties within 30 days of the DRB dispute meeting, except that time extensions may be granted at the request of the DRB with the written concurrence of both parties. The report shall include the facts and circumstances related to the matters under consideration, pertinent provisions of the contract, applicable laws and regulations, and actual costs and time incurred as shown on the Contractor's cost accounting records. The DRB shall make recommendations on the merit of the dispute and, if appropriate, recommend guidelines for determining compensation.
- K. Within 30 days after receiving the DRB's report, both the State and the Contractor shall respond to the DRB in writing signifying that the dispute is either resolved or remains unresolved. Failure to provide the written response within the time specified, or a written rejection of the DRB's recommendation or response to a request for reconsideration presented in the report by either party, shall conclusively indicate that the party(s) failing to respond accepts the DRB recommendation. Immediately after responses have been received from both parties, the DRB shall provide copies of both responses to the parties simultaneously. Either party may request clarification of elements of the DRB's report from the DRB prior to responding to the report. The DRB shall consider any clarification request only if submitted within 10 days of receipt of the DRB's report, and if submitted simultaneously in writing to both the DRB and the other party. Each party may submit only one request for clarification for any individual DRB report. The DRB shall respond, in writing, to requests for clarification within 10 days of receipt of such requests.
- L. The DRB's recommendations, stated in the DRB's reports, are not binding on either party. Either party may seek a reconsideration of a recommendation of the DRB. The DRB shall only grant a reconsideration based upon submission of new evidence and if the request is submitted within the 30-day time limit specified for response to the DRB's written report. Each party may submit only one request for reconsideration regarding an individual DRB recommendation.
- M. If the State and the Contractor are able to resolve their dispute with the aid of the DRB's report, the State and Contractor shall promptly accept and implement the recommendations of the DRB. If the parties cannot agree on compensation within 60 days of the acceptance by both parties of the DRB's recommendation, either party may request the DRB to make a recommendation regarding compensation.

- N. The State or the Contractor shall not call DRB members who served on the DRB for this contract as witnesses in arbitration proceedings which may arise from this contract, and all documents created by the DRB shall be inadmissible as evidence in subsequent arbitration proceedings, except the DRB's final written reports on each issue brought before it.
- O. The State and Contractor shall jointly indemnify and hold harmless the DRB members from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRB.
- P. The DRB members shall have no claim against the State or the Contractor, or both, from claimed harm arising out of the parties' evaluations of the DRB's report.

5-1.15C(6) Disputes Involving Subcontractor Potential Claims

For purposes of this section, a "subcontractor potential claim" shall include any potential claim by a subcontractor (including also any pass through potential claims by a lower tier subcontractor or supplier) against the Contractor that is actionable by the Contractor against the Department which arises from the work, services, or materials provided or to be provided in connection with the contract. If the Contractor determines to pursue a dispute against the Department that includes a subcontractor potential claim, the dispute shall be processed and resolved in conformance with these special provisions and in conformance with the following:

- A. The Contractor shall identify clearly in submissions pursuant to this section, that portion of the dispute that involves a subcontractor potential claim or potential claims.
- B. The Contractor shall include, as part of its submission pursuant to Step D above, a certification (False Claims Act Certification) by the subcontractor's or supplier's officer, partner, or authorized representative with authority to bind the subcontractor and with direct knowledge of the facts underlying the subcontractor potential claim. The Contractor shall submit a certification that the subcontractor potential claim is acknowledged and forwarded by the Contractor. The form for these certifications is available from the Engineer.
- C. At DRB dispute meetings involving one or more subcontractor potential claims, the Contractor shall require that each subcontractor involved in the dispute have present an authorized representative with actual knowledge of the facts underlying the subcontractor potential claim to assist in presenting the subcontractor potential claim and to answer questions raised by the DRB members or the Department's representatives.
- D. Failure by the Contractor to declare a subcontractor potential claim on behalf of its subcontractor (including lower tier subcontractors' and suppliers' pass through potential claims) at the time of submission of the Contractor's potential claims, as provided hereunder, shall constitute a release of the State by the Contractor of such subcontractor potential claim.
- E. The Contractor shall include in all subcontracts under this contract that subcontractors and suppliers of any tier (a) agree to submit subcontractor potential claims to the Contractor in a proper form and in sufficient time to allow processing by the Contractor in conformance with the Dispute Review Board resolution specifications; (b) agree to be bound by the terms of the Dispute Review Board provisions to the extent applicable to subcontractor potential claims; (c) agree that, to the extent a subcontractor potential claim is involved, completion of all steps required under these Dispute Review Board special provisions shall be a condition precedent to pursuit by the subcontractor of other remedies permitted by law, including without limitation of a lawsuit against the Contractor; and (d) agree that the existence of a dispute resolution process for disputes involving subcontractor potential claims shall not be deemed to create any claim, right, or cause of action by any subcontractor or supplier against the Department.

Notwithstanding the foregoing, this Dispute Review Board special provision shall not apply to, and the DRB shall not have the authority to consider, subcontractor potential claims between the subcontractor(s) or supplier(s) and the Contractor that are not actionable by the Contractor against the Department.

5-1.15C(7) Dispute Review Board Agreement

A copy of the "Dispute Review Board Agreement" to be executed by the Contractor, State and the 3 DRB members after approval of the contract follows:

DISPUTE REVIEW BOARD AGREEMENT

(Contract Identification)

Contract No. _____

THIS DISPUTE REVIEW BOARD AGREEMENT, hereinafter called "AGREEMENT", made and entered into this _____ day of _____, _____, between the State of California, acting through the California Department of Transportation and the Director of Transportation, hereinafter called the "STATE," _____ hereinafter called the "CONTRACTOR," and the Dispute Review Board, hereinafter called the "DRB" consisting of the following members:

_____,
(Contractor Appointee)

_____,
(State Appointee)

and _____
(Third Person)

WITNESSETH, that

WHEREAS, the STATE and the CONTRACTOR, hereinafter called the "parties," are now engaged in the construction on the State Highway project referenced above; and

WHEREAS, the special provisions for the above referenced contract provides for the establishment and operation of the DRB to assist in resolving disputes; and

WHEREAS, the DRB is composed of three members, one selected by the STATE, one selected by the CONTRACTOR, and the third member selected by the other two members and approved by the parties;

NOW THEREFORE, in consideration of the terms, conditions, covenants, and performance contained herein, or attached and incorporated and made a part hereof, the STATE, the CONTRACTOR, and the DRB members hereto agree as follows:

SECTION I DESCRIPTION OF WORK

To assist in the resolution of disputes between the parties, the contract provides for the establishment and the operation of the DRB. The intent of the DRB is to fairly and impartially consider disputes placed before it and provide written recommendations for resolution of these disputes to both parties. The members of this DRB shall perform the services necessary to participate in the DRB's actions as designated in Section II, Scope of Work.

SECTION II SCOPE OF WORK

The scope of work of the DRB includes, but is not limited to, the following:

A. OBJECTIVE

The principal objective of the DRB is to assist in the timely resolution of disputes between the parties arising from performance of this contract. It is not intended for either party to default on their normal responsibility to amicably and fairly settle their differences by indiscriminately assigning them to the DRB. It is intended that the mere existence of the DRB will encourage the parties to resolve disputes without resorting to this review procedure. But when a dispute that is serious enough to warrant the DRB's review does develop, the process for prompt and efficient action will be in place.

B. PROCEDURES

The DRB shall render written reports on disputes between the parties arising from the construction contract. Prior to consideration of a dispute, the DRB shall establish rules and regulations that will govern the conduct of its business and reporting procedures in conformance with the requirements of the contract and the terms of this AGREEMENT. DRB recommendations, resulting from its consideration of a dispute, shall be furnished in writing to both parties. The recommendations shall be based on facts and circumstances involved in the dispute, pertinent contract provisions, applicable laws and regulations. The recommendations shall find one responsible party in a dispute; shared or "jury" determinations shall not be rendered. The DRB shall make recommendations on the merit of the dispute, and if appropriate, recommend guidelines for determining compensation. If the parties cannot agree on compensation within 60 days of the acceptance by both parties of the DRB's recommendation, either party may request the DRB to make a recommendation regarding compensation.

The DRB shall refrain from officially giving advice or consulting services to anyone involved in the contract. The individual members shall act in a completely independent manner and while serving as members of the DRB shall have no consulting business connections with either party or its principals or attorneys or other affiliates (subcontractors, suppliers, etc.) who have a beneficial interest in the contract.

During scheduled meetings of the DRB as well as during dispute meetings, DRB members shall refrain from expressing opinions on the merits of statements on matters under dispute or potential dispute. Opinions of DRB members expressed in private sessions shall be kept strictly confidential. Individual DRB members shall not meet with, or discuss contract issues with individual parties, except as directed by the DRB Chairperson. Such discussions or meetings shall be disclosed to both parties. Other discussions regarding the project between the DRB members and the parties shall be in the presence of all three members and both parties. Individual DRB members shall not undertake independent investigations of any kind pertaining to disputes or potential disputes, except with the knowledge of both parties and as expressly directed by the DRB Chairperson.

C. CONSTRUCTION SITE VISITS, PROGRESS MEETINGS AND FIELD INSPECTIONS

The DRB members shall visit the project site and meet with representatives of the parties to keep abreast of construction activities and to develop familiarity with the work in progress. Scheduled progress meetings shall be held at or near the project site. The DRB shall meet at least once at the start of the project, and at least once every 4 months thereafter. The frequency, exact time, and duration of additional site visits and progress meetings shall be as recommended by the DRB and approved by the parties consistent with the construction activities or matters under consideration and dispute. Each meeting shall consist of a round table discussion and a field inspection of the work being performed on the contract, if necessary. Each meeting shall be attended by representatives of both parties. The agenda shall generally be as follows:

1. Meeting opened by the DRB Chairperson.
2. Remarks by the STATE's representative.
3. A description by the CONTRACTOR's representative of work accomplished since the last meeting; the current schedule status of the work; and a forecast for the coming period.
4. An outline by the CONTRACTOR's representative of potential problems and a description of proposed solutions.
5. An outline by the STATE's representative of the status of the work as the STATE views it.
6. A brief description by the CONTRACTOR's or STATE's representative of potential claims or disputes which have surfaced since the last meeting.
7. A summary by the STATE's representative, the CONTRACTOR's representative, or the DRB of the status of past disputes and potential claims.

The STATE's representative will prepare minutes of all progress meetings and circulate them for revision and approval by all concerned within 10 days of the meeting.

The field inspection shall cover all active segments of the work, the DRB being accompanied by both parties' representatives. The field inspection may be waived upon mutual agreement of the parties.

D. DRB CONSIDERATION AND HANDLING OF DISPUTES

Upon receipt by the DRB of a written referral of a dispute, the DRB shall convene to review and consider the dispute. The dispute meeting shall be held no earlier than 30 days and no later than 60 days after receipt of the written referral, unless otherwise agreed to by all parties. The DRB shall determine the time and location of DRB dispute meetings, with due consideration for the needs and preferences of the parties while recognizing the paramount importance of speedy resolution of issues. No dispute meetings shall take place later than 30 days prior to acceptance of contract.

Normally, dispute meetings shall be conducted at or near the project site. However, any location that would be more convenient and still provide required facilities and access to necessary documentation shall be satisfactory.

Both parties shall be given the opportunity to present their evidence at these dispute meetings. It is expressly understood that the DRB members are to act impartially and independently in the consideration of the contract provisions, applicable laws and regulations, and the facts and conditions surrounding any dispute presented by either party, and that the recommendations concerning any such dispute are advisory and nonbinding on the parties.

The DRB may request that written documentation and arguments from both parties be sent to each DRB member, through the DRB Chairperson, for review before the dispute meeting begins. A party furnishing written documentation to the DRB shall furnish copies of such information to the other party at the same time that such information is supplied to the DRB.

DRB dispute meetings shall be informal. There shall be no testimony under oath or cross-examination. There shall be no reporting of the procedures by a shorthand reporter or by electronic means. Documents and verbal statements shall be received by the DRB in conformance with acceptance standards established by the DRB. These standards need not comply with prescribed legal laws of evidence.

The third DRB member shall act as Chairperson for dispute meetings and all other DRB activities. The parties shall have a representative at all dispute meetings. Failure to attend a duly noticed dispute meeting by either of the parties shall be conclusively considered by the DRB as indication that the non-attending party considers written submittals as their entire and complete argument. The claimant shall discuss the dispute, followed by the other party. Each party shall then be allowed one or more rebuttals until all aspects of the dispute are thoroughly covered. DRB members shall ask questions, seek clarification, and request further data from either of the parties as may be necessary to assist in making a fully informed recommendation. The DRB may request from either party documents or information that would assist the DRB in making its findings and recommendations including, but not limited to, documents used by the CONTRACTOR in preparing the bid for the project. A refusal by a party to provide information requested by the DRB may be considered by the DRB as an indication that the requested material would tend to disprove that party's position. In large or complex cases, additional dispute meetings may be necessary in order to consider all the evidence presented by both parties. All involved parties shall maintain the confidentiality of all documents and information, as provided in this AGREEMENT.

During dispute meetings, no DRB member shall express an opinion concerning the merit of any facet of the case. DRB deliberations shall be conducted in private, with interim individual views kept strictly confidential.

After dispute meetings are concluded, the DRB shall meet in private and reach a conclusion supported by 2 or more members. Private sessions of the DRB may be held at a location other than the job site or by electronic conferencing as deemed appropriate, in order to expedite the process.

The DRB's findings and recommendations, along with discussion of reasons therefor, shall then be submitted as a written report to both parties. Recommendations shall be based on the pertinent contract provisions, applicable laws and regulations, and facts and circumstances related to the dispute. The report shall be thorough in discussing the facts considered, the contract language, law or regulation viewed by the DRB as pertinent to the issues, and the DRB's interpretation and philosophy in arriving at its conclusions and recommendations. The DRB's report shall stand on its own, without attachments or appendices. The DRB Chairperson shall furnish a copy of the written recommendation report to the DRB Coordinator, Division of Construction, MS 44, P.O. Box 942874, Sacramento, CA 94274.

With prior written approval of both parties, the DRB may obtain technical services necessary to adequately review the disputes presented, including audit, geotechnical, schedule analysis and other services. The parties' technical staff may supply those services as appropriate. The cost of technical services, as agreed to by the parties, shall be borne equally by the 2 parties as specified in an approved contract change order. The CONTRACTOR will not be entitled to markups for the payments made for these services.

The DRB shall resist submittal of incremental portions of information by either party, in the interest of making a fully informed decision and recommendation.

The DRB shall make every effort to reach a unanimous decision. If this proves impossible, the dissenting member shall prepare a minority opinion, which shall be included in the DRB's report.

Although both parties should place weight upon the DRB's recommendations, they are not binding. Either party may appeal a recommendation to the DRB for reconsideration. However, reconsideration shall only be allowed when there is new evidence to present, and the DRB shall accept only one appeal from each party pertaining to an individual DRB recommendation. The DRB shall hear appeals in conformance with the terms described in the Section entitled "Dispute Review Board" in the special provisions.

E. DRB MEMBER REPLACEMENT

Should the need arise to appoint a replacement DRB member, the replacement DRB member shall be appointed in the same manner as the original DRB members were appointed. The selection of a replacement DRB member shall begin promptly upon notification of the necessity for a replacement and shall be completed within 15 days. This AGREEMENT shall be amended to indicate change in DRB membership.

SECTION III CONTRACTOR RESPONSIBILITIES

The CONTRACTOR shall furnish to each DRB member one copy of pertinent documents that are or may become necessary for the DRB to perform their function. Pertinent documents are written notices of potential claim, responses to those notices, drawings or sketches, calculations, procedures, schedules, estimates, or other documents which are used in the performance of the work or in justifying or substantiating the CONTRACTOR's position. The CONTRACTOR shall also furnish a copy of such pertinent documents to the STATE, in conformance with the terms outlined in the special provisions.

SECTION IV STATE RESPONSIBILITIES

The STATE will furnish the following services and items:

A. CONTRACT RELATED DOCUMENTS

The STATE will furnish to each DRB member one copy of Notice to Contractors and Special Provisions, Proposal and Contract, Plans, Standard Specifications, and Standard Plans, change orders, written instructions issued by the STATE to the CONTRACTOR, or other documents pertinent to any dispute that has been referred to the DRB and necessary for the DRB to perform its function.

B. COORDINATION AND SERVICES

The STATE, through the Engineer, will, in cooperation with the CONTRACTOR, coordinate the operations of the DRB. The Engineer will arrange or provide conference facilities at or near the project site and provide secretarial and copying services to the DRB without charge to the CONTRACTOR.

SECTION V TIME FOR BEGINNING AND COMPLETION

Once established, the DRB shall be in operation until the day of acceptance of the contract. The DRB members shall not begin work under the terms of this AGREEMENT until authorized in writing by the STATE.

SECTION VI PAYMENT

A. ALL INCLUSIVE RATE PAYMENT

The STATE and the CONTRACTOR shall bear the costs and expenses of the DRB equally. Each DRB member shall be compensated at an agreed rate of \$1,200 per day if time spent per meeting, including on-site time plus one hour of travel time, is greater than 4 hours. Each DRB member shall be compensated at an agreed rate of \$700 per day if time spent per meeting, including on-site time plus one hour of travel time, is less than or equal to 4 hours. The agreed rates shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof, that the DRB member is at an authorized DRB meeting. No additional compensation will be made for time spent by DRB members in review and research activities outside the official DRB meetings unless that time has been specifically agreed to in advance by the STATE and CONTRACTOR. Time away from the project that has been specifically agreed to in advance by the parties will be compensated at an agreed rate of \$125 per hour. The agreed amount of \$125 per hour shall include all incidentals including expenses for telephone, fax, and computer services. Members serving on more than one DRB involving the State, regardless of the number of meetings per day, shall not be paid more than the all inclusive rate per day or rate per hour for an individual project. The STATE will provide, at no cost to the CONTRACTOR, administrative services such as conference facilities and secretarial services to the DRB.

B. PAYMENTS

DRB members shall be compensated at the same rate. The CONTRACTOR shall make direct payments to each DRB member for their participation in authorized meetings and approved hourly rate charges from invoices submitted by each DRB member. The STATE will reimburse the CONTRACTOR for its share of the costs of the DRB.

The DRB members may submit invoices to the CONTRACTOR for partial payment for work performed and services rendered for their participation in authorized meetings not more often than once per month during the progress of the work. The invoices shall be in a format approved by the parties and accompanied by a general description of activities performed during that billing period. Payment for hourly fees, at the agreed rate, shall not be paid to a DRB member until the amount and extent of those fees are approved by the STATE and CONTRACTOR.

Invoices shall be accompanied by original supporting documents, which the CONTRACTOR shall include with the extra work billing when submitting for reimbursement of the STATE's share of cost from the STATE. The CONTRACTOR will be reimbursed for one-half of approved costs of the DRB. No markups will be added to the CONTRACTOR's payment.

C. INSPECTION OF COSTS RECORDS

The DRB members and the CONTRACTOR shall keep available for inspection by representatives of the STATE and the United States, for a period of 3 years after final payment, the cost records and accounts pertaining to this AGREEMENT. If any litigation, claim, or audit arising out of, in connection with, or related to this contract is initiated before the expiration of the 3-year period, the cost records and accounts shall be retained until such litigation, claim, or audit involving the records is completed.

SECTION VII ASSIGNMENT OF TASKS OF WORK

The DRB members shall not assign the work of this AGREEMENT.

SECTION VIII TERMINATION OF DRB MEMBERS

DRB members may resign from the DRB by providing not less than 15 days written notice of the resignation to the STATE and CONTRACTOR. DRB members may be terminated by their original appointing power or by either party, for failing to fully comply at all times with all required employment and financial disclosure conditions of DRB membership in conformance with the terms of the contract.

SECTION IX LEGAL RELATIONS

The parties hereto mutually understand and agree that the DRB member in the performance of duties on the DRB, is acting in the capacity of an independent agent and not as an employee of either party.

No party to this AGREEMENT shall bear a greater responsibility for damages or personal injury than is normally provided by Federal or State of California Law.

Notwithstanding the provisions of this contract that require the CONTRACTOR to indemnify and hold harmless the STATE, the parties shall jointly indemnify and hold harmless the DRB members from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRB.

SECTION X CONFIDENTIALITY

The parties hereto mutually understand and agree that all documents and records provided by the parties in reference to issues brought before the DRB, which documents and records are marked "Confidential - for use by the DRB only," shall be kept in confidence and used only for the purpose of resolution of subject disputes, and for assisting in development of DRB findings and recommendations; that such documents and records will not be utilized or revealed to others, except to officials of the parties who are authorized to act on the subject disputes, for any purposes, during the life of the DRB. Upon termination of this AGREEMENT, said confidential documents and records, and all copies thereof, shall be returned to the parties who furnished them to the DRB. However, the parties understand that such documents shall be subsequently discoverable and admissible in court or arbitration proceedings unless a protective order has been obtained by the party seeking further confidentiality.

SECTION XI DISPUTES

Disputes between the parties hereto, including disputes between the DRB members and either party or both parties, arising out of the work or other terms of this AGREEMENT, which cannot be resolved by negotiation and mutual concurrence between the parties, or through the administrative process provided in the contract, shall be resolved by arbitration as provided in Section 9-1.10, "Arbitration," of the Standard Specifications.

SECTION XII VENUE, APPLICABLE LAW, AND PERSONAL JURISDICTION

In the event that any party, including an individual member of the DRB, deems it necessary to institute arbitration proceedings to enforce any right or obligation under this AGREEMENT, the parties hereto agree that such action shall be initiated in the Office of Administrative Hearings of the State of California. The parties hereto agree that all questions shall be resolved by arbitration by application of California law and that the parties to such arbitration shall have the right of appeal from such decisions to the Superior Court in conformance with the laws of the State of California. Venue for the arbitration shall be Sacramento or any other location as agreed to by the parties.

SECTION XIII FEDERAL REVIEW AND REQUIREMENTS

On Federal-Aid contracts, the Federal Highway Administration shall have the right to review the work of the DRB in progress, except for private meetings or deliberations of the DRB.

Other Federal requirements in this agreement shall only apply to Federal-Aid contracts.

3. Insufficient maintenance
4. Abuse
5. Unauthorized change
6. Act of God

During the guarantee period, repair or replace each work portion having a substantial defect.

The Department does not pay for corrective work.

During corrective work activities, provide insurance coverage specified for coverage before contract acceptance.

The contract bonds must be in full force and effect until the later of:

1. Expiration of guarantee period
2. Completion of corrective work

If a warranty specification conflicts with Section 6-1.075, "Guarantee," comply with the warranty specification.

During the guarantee period, the Engineer monitors the completed work. If the Engineer finds work having a substantial defect, the Engineer lists work parts and furnishes you the list.

Within 10 days of receipt of the list, submit for authorization a detailed plan for correcting the work. Include a schedule that includes:

1. Start and completion dates
2. List of labor, equipment, materials, and any special services you plan to use
3. Work related to the corrective work, including traffic control and temporary and permanent pavement markings

The Engineer notifies you when the plan is authorized. Start corrective work and related work within 15 days of notice. If the Engineer determines corrective work is urgently required to prevent injury or property damage:

1. The Engineer furnishes you a request to start emergency repair work and a list of parts requiring corrective work
2. Mobilize within 24 hours and start work
3. Submit a corrective work plan within 5 days of starting emergency repair work

If you fail to perform work as specified, the Department may perform the work and bill you.

Add:

6-1.085 BUY AMERICA (23 CFR 635.410)

For a Federal-aid contract, furnish steel and iron materials to be incorporated into the work that are produced in the United States except:

1. Foreign pig iron and processed, pelletized, and reduced iron ore may be used in the domestic production of the steel and iron materials [60 Fed Reg 15478 (03/24/1995)]
2. If the total combined cost of the materials does not exceed the greater of 0.1 percent of the total bid or \$2,500, material produced outside the United States may be used

Production includes:

1. Processing steel and iron materials, including smelting or other processes that alter the physical form or shape (such as rolling, extruding, machining, bending, grinding, and drilling) or chemical composition
2. Coating application, including epoxy coating, galvanizing, and painting, that protects or enhances the value of steel and iron materials

For steel and iron materials to be incorporated into the work, submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications that certifies all production processes occurred in the United States except for the above exceptions.

In Section 7-1.01A replace the 1st clause with:

Work on the job site must comply with Labor Code §§ 1727 and 1770-1815 and 8 CA Code of Regs § 16000 et seq. Work includes roadside production and processing of materials.

In Section 7-1.01A(2) in the 1st paragraph, replace item 3 with:

3. Upon becoming aware of the subcontractor's failure to pay the specified prevailing rate of wages to the subcontractor's workers, the Contractor must diligently take corrective action to stop or rectify the failure, including withholding sufficient funds due the subcontractor for work performed on the public works project.

In Section 7-1.01A(2) replace the 2nd paragraph with:

Pursuant to Section 1775 of the Labor Code, the Division of Labor Standards Enforcement must notify the Contractor on a public works project within 15 days of the receipt by the Division of Labor Standards Enforcement of a complaint of the failure of a subcontractor on that public works project to pay workers the general prevailing rate of per diem wages. If the Division of Labor Standards Enforcement determines that employees of a subcontractor were not paid the general prevailing rate of per diem wages and if the Department did not withhold sufficient money under the contract to pay those employees the balance of wages owed under the general prevailing rate of per diem wages, the Contractor must withhold an amount of moneys due the subcontractor sufficient to pay those employees the general prevailing rate of per diem wages if requested by the Division of Labor Standards Enforcement. The Contractor must pay any money withheld from and owed to a subcontractor upon receipt of notification by the Division of Labor Standards Enforcement that the wage complaint has been resolved. If notice of the resolution of the wage complaint has not been received by the Contractor within 180 days of the filing of a valid notice of completion or acceptance of the public works project, whichever occurs later, the Contractor must pay all moneys withheld from the subcontractor to the Department. The Department withholds these moneys pending the final decision of an enforcement action.

In Section 7-1.01A(2) replace 7th paragraph with:

Changes in general prevailing wage determinations apply to the contract when the Director of Industrial Relations has issued them at least 10 days before advertisement (Labor Code § 1773.6 and 8 CA Code of Regs 16204).

In Section 7-1.01A(3) replace the 2nd paragraph with:

The Department withholds the penalties specified in subdivision (g) of Labor Code § 1776 for noncompliance with the requirements in Section 1776.

In Section 7-1.01A(3) replace the 4th paragraph with:

The Department withholds for delinquent or inadequate payroll records (Labor Code § 1771.5). If the Contractor has not submitted an adequate payroll record by the month's 15th day for the period ending on or before the 1st of that month, the Department withholds 10 percent of the monthly progress estimate, exclusive of mobilization. The Department does not withhold more than \$10,000 or less than \$1,000.

In Section 7-1.01A(3) delete the 5th paragraph.

Delete Section 7-1.01A(6).

Add:

7-1.01K Solid Waste Disposal and Recycling

Submit an annual Solid Waste Disposal and Recycling Report between January 1 and 15 for each year work is performed under the Contract at any time during the previous calendar year. Show the types and amounts of project-generated solid waste taken to or diverted from landfills or reused on the project from January 1 through December 31 of the previous calendar year.

Submit a final annual Solid Waste Disposal and Recycling Report within 5 business days after Contract acceptance. Show the types and amounts of project-generated solid waste taken to or diverted from landfills or reused on the project from January 1 to contract acceptance.

For each failure to submit a completed form, the Department withholds \$10,000.

Add:

7-1.01L Asbestos and Hazardous Substances

- Upon discovery, immediately stop working in and notify the Engineer of areas where asbestos or a hazardous substance is present if the:
 1. Contractor reasonably believes the substance is asbestos as defined in Labor Code § 6501.7 or a hazardous substance as defined in Health & Safety Code §§ 25316 and 25317
 2. Presence is not described in the contract
 3. Substance has not been made harmless

Add:

7-1.01M Archaeological Discoveries

If archaeological materials are discovered at the job site, protect and leave them undisturbed in place and comply with:

1. Pub Res Code §§ 5097.5, 5097.98, and 5097.99
2. 14 CA Code of Regs § 4308
4. Penal Code § 622-1/2
5. Health & Safety Code § 7050.5

Archaeological materials are the remains of past human activity including historic-period archaeological materials and prehistoric Native American archaeological materials. Nonhuman fossils are not archaeological materials unless they show direct evidence of human use or alteration or when found in direct physical association with archaeological materials

Historic-period archaeological materials include cultural remains beginning with initial European contact in California but at least 50 years old and include:

1. Trash deposits or clearly defined disposal pits containing tin cans, bottles, ceramic dishes, or other refuse indicating previous occupation or use of the site
2. Structural remains of stone, brick, concrete, wood, or other building material found above or below ground
3. Human skeletal remains from the historic period, with or without coffins or caskets, including any associated grave goods

Prehistoric Native American archaeological materials include:

1. Human skeletal remains or associated burial goods such as beads or ornaments
2. Evidence of tool making or hunting such as arrowheads and associated chipping debris of fine-grained materials such as obsidian, chert, or basalt
3. Evidence of plant processing such as pestles, grinding slabs, or stone bowls
4. Evidence of habitation such as cooking pits, stone hearths, packed or burnt earth floors
5. Remains from food processing such as concentrations of discarded or burnt animal bone, shellfish remains, or burnt rocks used in cooking

Immediately upon discovering archaeological materials, stop all work within a 60-foot radius of the archaeological materials and notify the Engineer. Archaeological materials discovered are the property of the State. Do not resume work within the 60-foot radius of the discovery until the Engineer gives you written approval. If, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of an archeological discovery or investigation or recovery of archeological materials, you will be compensated for resulting losses and an extension of time will be granted in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Department may use other forces to investigate and recover archaeological materials from the location of the discovery. If ordered by the Engineer furnish labor, material, tools, and equipment to secure the location of the discovery and assist in the investigation or recovery of archaeological materials; the cost of this work will be paid for as extra work as specified in Section 4-1.03D, "Extra Work," of the Standard Specifications.

In Section 7-1.02 in the 2nd paragraph, replace the 4th sentence with:

Trucks used to haul treated base, portland cement concrete, or asphalt concrete shall enter onto the base to dump at the nearest practical entry point ahead of spreading equipment.

In Section 7-1.02 after the 4th paragraph add:

Loads imposed on existing, new, or partially completed structures shall not exceed the load carrying capacity of the structure or any portion of the structure as determined by AASHTO LRFD with interims and California Amendments, Design Strength Limit State II. The compressive strength of concrete (f_c) to be used in computing the load carrying capacity shall be the smaller of the following:

1. Actual compressive strength at the time of loading
2. Value of f_c shown on the plans for that portion of the structure or 2.5 times the value of f_c (extreme fiber compressive stress in concrete at service loads) shown on the plans for portions of the structure where no f_c is shown

In Section 7-1.09 in the 8th paragraph, replace the 1st sentence with:

Signs, lights, flags, and other warning and safety devices and their use shall conform to the requirements set forth in Part 6 of the California MUTCD except where a discrepancy exists between the California MUTCD and the specifications; for discrepancies, comply with the specifications.

In Section 7-1.09 replace the 16th paragraph with:

When vertical clearance is temporarily reduced to 15.5 feet or less, low clearance warning signs shall be placed in accordance with Part 2 of the California MUTCD and as directed by the Engineer. Signs shall conform to the dimensions, color, and legend requirements of the California MUTCD and these specifications except that the signs shall have black letters and numbers on an orange retroreflective background. W12-2P signs shall be illuminated so that the signs are clearly visible.

Add to Section 7-1.09:

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations-The near edge of the excavation is 12 feet or less from the edge of the lane, except:
 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
 2. Excavations less than one foot deep.
 3. Trenches less than one foot wide for irrigation pipe or electrical conduit, or excavations less than one foot in diameter.
 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
 5. Excavations in side slopes, where the slope is steeper than 4:1 (horizontal:vertical).
 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles-The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.

- C. Storage Areas-Material or equipment is stored within 12 feet of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 15 feet from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than one foot transversely to 10 feet longitudinally with respect to the edge of the traffic lane. If the 15-foot minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall be secured in place before starting work for which the temporary railing is required.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Miles Per Hour)	Work Areas
Over 45	Within 6 feet of a traffic lane but not on a traffic lane
35 to 45	Within 3 feet of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 10 feet without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

In Section 7-1.11 in the 2nd paragraph, replace the last sentence with:

The cost of the repairs must be borne by the Contractor and will be deducted.

Replace Section 7-1.12 with:

7-1.12 INDEMNIFICATION AND INSURANCE

The Contractor's obligations regarding indemnification of the State of California and the requirements for insurance shall conform to the provisions in Section 3-1.025, "Insurance Policies," and Sections 7-1.12A, "Indemnification," and 7-1.12B, "Insurance," of this Section 7-1.12.

7-1.12A Indemnification

The Contractor shall defend, indemnify, and save harmless the State, including its officers, employees, and agents (excluding agents who are design professionals) from any and all claims, demands, causes of action, damages, costs, expenses, actual attorneys' fees, losses or liabilities, in law or in equity (Section 7-1.12A Claims) arising out of or in connection with the Contractor's performance of this contract for:

1. Bodily injury including, but not limited to, bodily injury, sickness or disease, emotional injury or death to persons, including, but not limited to, the public, any employees or agents of the Contractor, the State, or any other contractor; and
2. Damage to property of anyone including loss of use thereof; caused or alleged to be caused in whole or in part by any negligent or otherwise legally actionable act or omission of the Contractor or anyone directly or indirectly employed by the Contractor or anyone for whose acts the Contractor may be liable.

Except as otherwise provided by law, these requirements apply regardless of the existence or degree of fault of the State. The Contractor is not obligated to indemnify the State for Claims arising from conduct delineated in Civil Code Section 2782 and to Claims arising from any defective or substandard condition of the highway that existed at or before the start of work, unless this condition has been changed by the work or the scope of the work requires the Contractor to maintain existing highway facilities and the Claim arises from the Contractor's failure to maintain. The Contractor's defense and indemnity obligation shall extend to Claims arising after the work is completed and accepted if the Claims are directly related to alleged acts or omissions by the Contractor that occurred during the course of the work. State inspection is not a waiver of full compliance with these requirements.

The Contractor's obligation to defend and indemnify shall not be excused because of the Contractor's inability to evaluate liability or because the Contractor evaluates liability and determine that the Contractor is not liable. The Contractor shall respond within 30 days to the tender of any Claim for defense and indemnity by the State, unless this time has been extended by the State. If the Contractor fails to accept or reject a tender of defense and indemnity within 30 days, in addition to any other remedy authorized by law, the Department may withhold such funds the State reasonably considers necessary for its defense and indemnity until disposition has been made of the Claim or until the Contractor accepts or rejects the tender of defense, whichever occurs first.

With respect to third-party claims against the Contractor, the Contractor waives all rights of any type to express or implied indemnity against the State, its officers, employees, or agents (excluding agents who are design professionals).

Nothing in the Contract is intended to establish a standard of care owed to any member of the public or to extend to the public the status of a third-party beneficiary for any of these indemnification specifications.

7-1.12B Insurance

7-1.12B(1) General

Nothing in the contract is intended to establish a standard of care owed to any member of the public or to extend to the public the status of a third-party beneficiary for any of these insurance specifications.

7-1.12B(2) Casualty Insurance

The Contractor shall procure and maintain insurance on all of its operations with companies acceptable to the State as follows:

1. The Contractor shall keep all insurance in full force and effect from the beginning of the work through contract acceptance.
2. All insurance shall be with an insurance company with a rating from A.M. Best Financial Strength Rating of A- or better and a Financial Size Category of VII or better.
3. The Contractor shall maintain completed operations coverage with a carrier acceptable to the State through the expiration of the patent deficiency in construction statute of repose set forth in Code of Civil Procedure Section 337.1.

7-1.12B(3) Workers' Compensation and Employer's Liability Insurance

In accordance with Labor Code Section 1860, the Contractor shall secure the payment of worker's compensation in accordance with Labor Code Section 3700.

In accordance with Labor Code Section 1861, the Contractor shall submit to the Department the following certification before performing the work:

I am aware of the provisions of Section 3700 of the Labor Code which require every employer to be insured against liability for workers' compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with such provisions before commencing the performance of the work of this contract.

Contract execution constitutes certification submittal.

The Contractor shall provide Employer's Liability Insurance in amounts not less than:

1. \$1,000,000 for each accident for bodily injury by accident
2. \$1,000,000 policy limit for bodily injury by disease
3. \$1,000,000 for each employee for bodily injury by disease

If there is an exposure of injury to the Contractor's employees under the U.S. Longshoremen's and Harbor Workers' Compensation Act, the Jones Act, or under laws, regulations, or statutes applicable to maritime employees, coverage shall be included for such injuries or claims.

7-1.12B(4) Liability Insurance

7-1.12B(4)(a) General

The Contractor shall carry General Liability and Umbrella or Excess Liability Insurance covering all operations by or on behalf of the Contractor providing insurance for bodily injury liability and property damage liability for the following limits and including coverage for:

1. Premises, operations, and mobile equipment
2. Products and completed operations
3. Broad form property damage (including completed operations)
4. Explosion, collapse, and underground hazards
5. Personal injury
6. Contractual liability

7-1.12B(4)(b) Liability Limits/Additional Insureds

The limits of liability shall be at least the amounts shown in the following table:

Total Bid	For Each Occurrence ¹	Aggregate for Products/Completed Operation	General Aggregate ²	Umbrella or Excess Liability ³
≤\$1,000,000	\$1,000,000	\$2,000,000	\$2,000,000	\$5,000,000
>\$1,000,000 ≤\$5,000,000	\$1,000,000	\$2,000,000	\$2,000,000	\$10,000,000
>\$5,000,000 ≤\$25,000,000	\$2,000,000	\$2,000,000	\$4,000,000	\$15,000,000
>\$25,000,000	\$2,000,000	\$2,000,000	\$4,000,000	\$25,000,000
<ol style="list-style-type: none"> 1. Combined single limit for bodily injury and property damage. 2. This limit shall apply separately to the Contractor's work under this contract. 3. The umbrella or excess policy shall contain a clause stating that it takes effect (drops down) in the event the primary limits are impaired or exhausted. 				

The Contractor shall not require certified Small Business subcontractors to carry Liability Insurance that exceeds the limits in the table above. Notwithstanding the limits specified herein, at the option of the Contractor, the liability insurance limits for certified Small Business subcontractors of any tier may be less than those limits specified in the table. For Small Business subcontracts, "Total Bid" shall be interpreted as the amount of subcontracted work to a certified Small Business.

The State, including its officers, directors, agents (excluding agents who are design professionals), and employees, shall be named as additional insureds under the General Liability and Umbrella Liability Policies with respect to liability arising out of or connected with work or operations performed by or on behalf of the Contractor under this contract. Coverage for such additional insureds does not extend to liability:

1. Arising from any defective or substandard condition of the roadway which existed at or before the time the Contractor started work, unless such condition has been changed by the work or the scope of the work requires the Contractor to maintain existing roadway facilities and the claim arises from the Contractor's failure to maintain;
2. For claims occurring after the work is completed and accepted unless these claims are directly related to alleged acts or omissions of the Contractor that occurred during the course of the work; or
3. To the extent prohibited by Insurance Code Section 11580.04

Additional insured coverage shall be provided by a policy provision or by an endorsement providing coverage at least as broad as Additional Insured (Form B) endorsement form CG 2010, as published by the Insurance Services Office (ISO), or other form designated by the Department.

7-1.12B(4)(c) Contractor's Insurance Policy is Primary

The policy shall stipulate that the insurance afforded the additional insureds applies as primary insurance. Any other insurance or self-insurance maintained by the State is excess only and shall not be called upon to contribute with this insurance.

7-1.12B(5) Automobile Liability Insurance

The Contractor shall carry automobile liability insurance, including coverage for all owned, hired, and nonowned automobiles. The primary limits of liability shall be not less than \$1,000,000 combined single limit each accident for bodily injury and property damage. The umbrella or excess liability coverage required under Section 7-1.12B(4)(b) also applies to automobile liability.

7-1.12B(6) Policy Forms, Endorsements, and Certificates

The Contractor shall provide its General Liability Insurance under Commercial General Liability policy form No. CG0001 as published by the Insurance Services Office (ISO) or under a policy form at least as broad as policy form No. CG0001.

7-1.12B(7) Deductibles

The State may expressly allow deductible clauses, which it does not consider excessive, overly broad, or harmful to the interests of the State. Regardless of the allowance of exclusions or deductions by the State, the Contractor is responsible for any deductible amount and shall warrant that the coverage provided to the State is in accordance with Section 7-1.12B, "Insurance."

7-1.12B(8) Enforcement

The Department may assure the Contractor's compliance with its insurance obligations. Ten days before an insurance policy lapses or is canceled during the contract period, the Contractor shall submit to the Department evidence of renewal or replacement of the policy.

If the Contractor fails to maintain any required insurance coverage, the Department may maintain this coverage and withhold or charge the expense to the Contractor or terminate the Contractor's control of the work in accordance with Section 8-1.08, "Termination of Control."

The Contractor is not relieved of its duties and responsibilities to indemnify, defend, and hold harmless the State, its officers, agents, and employees by the Department's acceptance of insurance policies and certificates.

Minimum insurance coverage amounts do not relieve the Contractor for liability in excess of such coverage, nor do they preclude the State from taking other actions available to it, including the withholding of funds under this contract.

7-1.12B(9) Self-Insurance

Self-insurance programs and self-insured retentions in insurance policies are subject to separate annual review and approval by the State.

If the Contractor uses a self-insurance program or self-insured retention, the Contractor shall provide the State with the same protection from liability and defense of suits as would be afforded by first-dollar insurance. Execution of the contract is the Contractor's acknowledgement that the Contractor will be bound by all laws as if the Contractor were an insurer as defined under Insurance Code Section 23 and that the self-insurance program or self-insured retention shall operate as insurance as defined under Insurance Code Section 22.

In Section 7-1.13 delete the 5th and 6th paragraph.

Add:

7-1.50 FEDERAL LAWS FOR FEDERAL-AID CONTRACTS

7-1.50A General

Section 7-1.50, "Federal Laws for Federal-Aid Contracts," includes specifications required in a Federal-aid construction contract and applies to a Federal-aid contract.

Form FHWA-1273 is included in the contract in Section 7-1.50B, "FHWA-1273." Some contract terms on the form are different than those used in other contract parts as shown in the following table:

FHWA-1273 Terms and Department Equivalencies

FHWA-1273 Term	Equivalent Term Used in Other Contract Parts
SHA	Department
SHA contracting officer	Engineer
SHA resident engineer	Engineer

7-1.50B FHWA-1273

FHWA-1273 Electronic version -- March 10, 1994
with revised Section VI

REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- I. General
- II. Nondiscrimination
- III. Nonsegregated Facilities
- IV. Payment of Predetermined Minimum Wage
- V. Statements and Payrolls
- VI. Record of Materials, Supplies, and Labor
- VII. Subletting or Assigning the Contract
- VIII. Safety: Accident Prevention
- IX. False Statements Concerning Highway Projects
- X. Implementation of Clean Air Act and Federal Water Pollution Control Act
- XI. Certification Regarding Debarment, Suspension, Ineligibility, and Voluntary Exclusion
- XII. Certification Regarding Use of Contract Funds for Lobbying

ATTACHMENTS

- A. Employment Preference for Appalachian Contracts (included in Appalachian contracts only)

I. GENERAL

1. These contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.
2. Except as otherwise provided for in each section, the contractor shall insert in each subcontract all of the stipulations contained in these Required Contract Provisions, and further require their inclusion in any lower tier subcontract or purchase order that may in turn be made. The Required Contract Provisions shall not be incorporated by reference in any case. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with these Required Contract Provisions.
3. A breach of any of the stipulations contained in these Required Contract Provisions shall be sufficient grounds for termination of the contract.
4. A breach of the following clauses of the Required Contract Provisions may also be grounds for debarment as provided in 29 CFR 5.12:
 - Section I, paragraph 2;
 - Section IV, paragraphs 1, 2, 3, 4, and 7;
 - Section V, paragraphs 1 and 2a through 2g.
5. Disputes arising out of the labor standards provisions of Section IV (except paragraph 5) and Section V of these Required Contract Provisions shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the U.S. Department of Labor (DOL) as set forth in 29 CFR 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the DOL, or the contractor's employees or their representatives.
6. **Selection of Labor:** During the performance of this contract, the contractor shall not:
 - a. discriminate against labor from any other State, possession, or territory of the United States (except for employment preference for Appalachian contracts, when applicable, as specified in Attachment A), or
 - b. employ convict labor for any purpose within the limits of the project unless it is labor performed by convicts who are on parole, supervised release, or probation.

II. NONDISCRIMINATION

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

1. **Equal Employment Opportunity:** Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630 and 41 CFR 60) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The Equal Opportunity Construction Contract Specifications set forth under 41 CFR 60-4.3 and the provisions of the American Disabilities Act of 1990 (42 U.S.C. 12101 *et seq.*) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:
 - a. The contractor will work with the State highway agency (SHA) and the Federal Government in carrying out EEO obligations and in their review of his/her activities under the contract.
 - b. The contractor will accept as his operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job training."
2. **EEO Officer:** The contractor will designate and make known to the SHA contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so.
3. **Dissemination of Policy:** All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
 - a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
 - b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
 - c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minority group employees.
 - d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
 - e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.
4. **Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minority groups in the area from which the project work force would normally be derived.
 - a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minority group applicants. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority group applicants may be referred to the contractor for employment consideration.
 - b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he is expected to observe the provisions of that agreement to the extent that the system permits the contractor's compliance with EEO contract provisions. (The DOL has held that where implementation of such agreements have the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Executive Order 11246, as amended.)

- c. The contractor will encourage his present employees to refer minority group applicants for employment. Information and procedures with regard to referring minority group applicants will be discussed with employees.
5. **Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:
- a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
 - b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
 - c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
 - d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with his obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of his avenues of appeal.
6. **Training and Promotion:**
- a. The contractor will assist in locating, qualifying, and increasing the skills of minority group and women employees, and applicants for employment.
 - b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision.
 - c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
 - d. The contractor will periodically review the training and promotion potential of minority group and women employees and will encourage eligible employees to apply for such training and promotion.
7. **Unions:** If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the contractor either directly or through a contractor's association acting as agent will include the procedures set forth below:
- a. The contractor will use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority group members and women for membership in the unions and increasing the skills of minority group employees and women so that they may qualify for higher paying employment.
 - b. The contractor will use best efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
 - c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the SHA and shall set forth what efforts have been made to obtain such information.

- d. In the event the union is unable to provide the contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The DOL has held that it shall be no excuse that the union with which the contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these specifications, such contractor shall immediately notify the SHA.
8. **Selection of Subcontractors, Procurement of Materials and Leasing of Equipment:** The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.
 - a. The contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.
 - b. Disadvantaged business enterprises (DBE), as defined in 49 CFR 23, shall have equal opportunity to compete for and perform subcontracts which the contractor enters into pursuant to this contract. The contractor will use his best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority group and female representation among their employees. Contractors shall obtain lists of DBE construction firms from SHA personnel.
 - c. The contractor will use his best efforts to ensure subcontractor compliance with their EEO obligations.
 9. **Records and Reports:** The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the SHA and the FHWA.
 - a. The records kept by the contractor shall document the following:
 1. The number of minority and non-minority group members and women employed in each work classification on the project;
 2. The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women;
 3. The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and
 4. The progress and efforts being made in securing the services of DBE subcontractors or subcontractors with meaningful minority and female representation among their employees.
 - b. The contractors will submit an annual report to the SHA each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data.

III. NONSEGREGATED FACILITIES

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

- a. By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement or purchase order, as appropriate, the bidder, Federal-aid construction contractor, subcontractor, material supplier, or vendor, as appropriate, certifies that the firm does not maintain or provide for its employees any segregated facilities at any of its establishments, and that the firm does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The firm agrees that a breach of this certification is a violation of the EEO provisions of this contract. The firm further certifies that no employee will be denied access to adequate facilities on the basis of sex or disability.
- b. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, timeclocks, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive, or are, in fact, segregated on the basis of race, color, religion, national origin, age or disability, because of habit, local custom, or otherwise. The only exception will be for the disabled when the demands for accessibility override (e.g. disabled parking).

- c. The contractor agrees that it has obtained or will obtain identical certification from proposed subcontractors or material suppliers prior to award of subcontracts or consummation of material supply agreements of \$10,000 or more and that it will retain such certifications in its files.

IV. PAYMENT OF PREDETERMINED MINIMUM WAGE

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural minor collectors, which are exempt.)

1. General:

- a. All mechanics and laborers employed or working upon the site of the work will be paid unconditionally and not less often than once a week and without subsequent deduction or rebate on any account [except such payroll deductions as are permitted by regulations (29 CFR 3) issued by the Secretary of Labor under the Copeland Act (40 U.S.C. 276c)] the full amounts of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment. The payment shall be computed at wage rates not less than those contained in the wage determination of the Secretary of Labor (hereinafter "the wage determination") which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor or its subcontractors and such laborers and mechanics. The wage determination (including any additional classifications and wage rates conformed under paragraph 2 of this Section IV and the DOL poster (WH-1321) or Form FHWA-1495) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers. For the purpose of this Section, contributions made or costs reasonably anticipated for bona fide fringe benefits under Section 1(b) (2) of the Davis- Bacon Act (40 U.S.C. 276a) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of Section IV, paragraph 3b, hereof. Also, for the purpose of this Section, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraphs 4 and 5 of this Section IV.
- b. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein, provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.
- c. All rulings and interpretations of the Davis-Bacon Act and related acts contained in 29 CFR 1, 3, and 5 are herein incorporated by reference in this contract.

2. Classification:

- a. The SHA contracting officer shall require that any class of laborers or mechanics employed under the contract, which is not listed in the wage determination, shall be classified in conformance with the wage determination.
- b. The contracting officer shall approve an additional classification, wage rate and fringe benefits only when the following criteria have been met:
 1. the work to be performed by the additional classification requested is not performed by a classification in the wage determination;
 2. the additional classification is utilized in the area by the construction industry;
 3. the proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination; and
 4. with respect to helpers, when such a classification prevails in the area in which the work is performed.
- c. If the contractor or subcontractors, as appropriate, the laborers and mechanics (if known) to be employed in the additional classification or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the DOL, Administrator of the Wage and Hour Division, Employment Standards Administration, Washington, D.C. 20210. The Wage and Hour Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

- d. In the event the contractor or subcontractors, as appropriate, the laborers or mechanics to be employed in the additional classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. Said Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- e. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 2c or 2d of this Section IV shall be paid to all workers performing work in the additional classification from the first day on which work is performed in the classification.

3. Payment of Fringe Benefits:

- a. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor or subcontractors, as appropriate, shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly case equivalent thereof.
- b. If the contractor or subcontractor, as appropriate, does not make payments to a trustee or other third person, he/she may consider as a part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided, that the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

4. Apprentices and Trainees (Programs of the U.S. DOL) and Helpers:

a. Apprentices:

- 1. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the DOL, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau, or if a person is employed in his/her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State apprenticeship agency (where appropriate) to be eligible for probationary employment as an apprentice.
- 2. The allowable ratio of apprentices to journeyman-level employees on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate listed in the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor or subcontractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman-level hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.
- 3. Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator for the Wage and Hour Division determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.
- 4. In the event the Bureau of Apprenticeship and Training, or a State apprenticeship agency recognized by the Bureau, withdraws approval of an apprenticeship program, the contractor or subcontractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the comparable work performed by regular employees until an acceptable program is approved.

b. Trainees:

1. Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the DOL, Employment and Training Administration.
2. The ratio of trainees to journeyman-level employees on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.
3. Every trainee must be paid at not less than the rate specified in the approved program for his/her level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman-level wage rate on the wage determination which provides for less than full fringe benefits for apprentices, in which case such trainees shall receive the same fringe benefits as apprentices.
4. In the event the Employment and Training Administration withdraws approval of a training program, the contractor or subcontractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Helpers:

Helpers will be permitted to work on a project if the helper classification is specified and defined on the applicable wage determination or is approved pursuant to the conformance procedure set forth in Section IV.2. Any worker listed on a payroll at a helper wage rate, who is not a helper under an approved definition, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed.

5. **Apprentices and Trainees (Programs of the U.S. DOT):**

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

6. **Withholding:**

The SHA shall upon its own action or upon written request of an authorized representative of the DOL withhold, or cause to be withheld, from the contractor or subcontractor under this contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage requirements which is held by the same prime contractor, as much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the SHA contracting officer may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

7. Overtime Requirements:

No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen, or guards (including apprentices, trainees, and helpers described in paragraphs 4 and 5 above) shall require or permit any laborer, mechanic, watchman, or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman, or guard receives compensation at a rate not less than one-and-one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

8. Violation:

Liability for Unpaid Wages; Liquidated Damages: In the event of any violation of the clause set forth in paragraph 7 above, the contractor and any subcontractor responsible thereof shall be liable to the affected employee for his/her unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory) for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman, or guard employed in violation of the clause set forth in paragraph 7, in the sum of \$10 for each calendar day on which such employee was required or permitted to work in excess of the standard work week of 40 hours without payment of the overtime wages required by the clause set forth in paragraph 7.

9. Withholding for Unpaid Wages and Liquidated Damages:

The SHA shall upon its own action or upon written request of any authorized representative of the DOL withhold, or cause to be withheld, from any monies payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to the contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 8 above.

V. STATEMENTS AND PAYROLLS

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural collectors, which are exempt.)

1. Compliance with Copeland Regulations (29 CFR 3):

The contractor shall comply with the Copeland Regulations of the Secretary of Labor which are herein incorporated by reference.

2. Payrolls and Payroll Records:

- a. Payrolls and basic records relating thereto shall be maintained by the contractor and each subcontractor during the course of the work and preserved for a period of 3 years from the date of completion of the contract for all laborers, mechanics, apprentices, trainees, watchmen, helpers, and guards working at the site of the work.
- b. The payroll records shall contain the name, social security number, and address of each such employee; his or her correct classification; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalent thereof the types described in Section 1(b)(2)(B) of the Davis Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. In addition, for Appalachian contracts, the payroll records shall contain a notation indicating whether the employee does, or does not, normally reside in the labor area as defined in Attachment A, paragraph 1. Whenever the Secretary of Labor, pursuant to Section IV, paragraph 3b, has found that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in Section 1(b)(2)(B) of the Davis Bacon Act, the contractor and each subcontractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, that the plan or program has been communicated in writing to the laborers or mechanics affected, and show the cost anticipated or the actual cost incurred in providing benefits. Contractors or subcontractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprentices and trainees, and ratios and wage rates prescribed in the applicable programs.

- c. Each contractor and subcontractor shall furnish, each week in which any contract work is performed, to the SHA resident engineer a payroll of wages paid each of its employees (including apprentices, trainees, and helpers, described in Section IV, paragraphs 4 and 5, and watchmen and guards engaged on work during the preceding weekly payroll period). The payroll submitted shall set out accurately and completely all of the information required to be maintained under paragraph 2b of this Section V. This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal stock number 029- 005-0014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors.
- d. Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his/her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
 - 1. that the payroll for the payroll period contains the information required to be maintained under paragraph 2b of this Section V and that such information is correct and complete;
 - 2. that such laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR 3;
 - 3. that each laborer or mechanic has been paid not less than the applicable wage rate and fringe benefits or cash equivalent for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.
- e. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 2d of this Section V.
- f. The falsification of any of the above certifications may subject the contractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 231.
- g. The contractor or subcontractor shall make the records required under paragraph 2b of this Section V available for inspection, copying, or transcription by authorized representatives of the SHA, the FHWA, or the DOL, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the SHA, the FHWA, the DOL, or all may, after written notice to the contractor, sponsor, applicant, or owner, take such actions as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

VI. RECORD OF MATERIALS, SUPPLIES, AND LABOR

(As of May 22, 2007, Form FHWA-47 is no longer required.)

VII. SUBLETTING OR ASSIGNING THE CONTRACT

- 1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the State. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635).
 - a. "Its own organization" shall be construed to include only workers employed and paid directly by the prime contractor and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor, assignee, or agent of the prime contractor.
 - b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract as a whole and in general are to be limited to minor components of the overall contract.
- 2. The contract amount upon which the requirements set forth in paragraph 1 of Section VII is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.

3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the SHA contracting officer determines is necessary to assure the performance of the contract.
4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the SHA contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the SHA has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

VIII. SAFETY: ACCIDENT PREVENTION

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the SHA contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).
3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

IX. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by Engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, the following notice shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

NOTICE TO ALL PERSONNEL ENGAGED ON FEDERAL-AID HIGHWAY PROJECTS

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined not more than \$10,000 or imprisoned not more than 5 years or both."

X. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$100,000 or more.)

By submission of this bid or the execution of this contract, or subcontract, as appropriate, the bidder, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any facility that is or will be utilized in the performance of this contract, unless such contract is exempt under the Clean Air Act, as amended (42 U.S.C. 1857 *et seq.*, as amended by Pub.L. 91-604), and under the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251 *et seq.*, as amended by Pub.L. 92-500), Executive Order 11738, and regulations in implementation thereof (40 CFR 15) is not listed, on the date of contract award, on the U.S. Environmental Protection Agency (EPA) List of Violating Facilities pursuant to 40 CFR 15.20.
2. That the firm agrees to comply and remain in compliance with all the requirements of Section 114 of the Clean Air Act and Section 308 of the Federal Water Pollution Control Act and all regulations and guidelines listed thereunder.
3. That the firm shall promptly notify the SHA of the receipt of any communication from the Director, Office of Federal Activities, EPA, indicating that a facility that is or will be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.
4. That the firm agrees to include or cause to be included the requirements of paragraph 1 through 4 of this Section X in every nonexempt subcontract, and further agrees to take such action as the government may direct as a means of enforcing such requirements.

XI. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

1. Instructions for Certification - Primary Covered Transactions:

(Applicable to all Federal-aid contracts - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.
- c. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.
- d. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- e. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the department or agency to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- f. The prospective primary participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," provided by the department or agency entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the nonprocurement portion of the "Lists of Parties Excluded From Federal Procurement or Nonprocurement Programs" (Nonprocurement List) which is compiled by the General Services Administration.
- i. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph f of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

* * * * *

**Certification Regarding Debarment, Suspension, Ineligibility and
Voluntary Exclusion--Primary Covered Transactions**

1. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:
 - a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - b. Have not within a 3-year period preceding this proposal been convicted of or had a civil judgement rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
 - c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1b of this certification; and
 - d. Have not within a 3-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

* * * * *

2. Instructions for Certification - Lower Tier Covered Transactions:

- (Applicable to all subcontracts, purchase orders and other lower tier transactions of \$25,000 or more - 49 CFR 29)
- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
 - b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
 - c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.

- d. The terms "covered transaction," "debarred," "suspended," "ineligible," "primary covered transaction," "participant," "person," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

* * * * *

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Covered Transactions:

1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

* * * * *

XII. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

(Applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 - 49 CFR 20)

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:
 - a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

- b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
3. The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

7-1.50C Female and Minority Goals

To comply with Section II, "Nondiscrimination," of "Required Contract Provisions Federal-Aid Construction Contracts," the Department is including in Section 7-1.50C, "Female and Minority Goals," female and minority utilization goals for Federal-aid construction contracts and subcontracts that exceed \$10,000.

The nationwide goal for female utilization is 6.9 percent.

The goals for minority utilization [45 Fed Reg 65984 (10/3/1980)] are as follows:

Minority Utilization Goals

Economic Area		Goal (Percent)
174	Redding CA: Non-SMSA Counties: CA Lassen; CA Modoc; CA Plumas; CA Shasta; CA Siskiyou; CA Tehama	6.8
175	Eureka, CA Non-SMSA Counties: CA Del Norte; CA Humboldt; CA Trinity	6.6
176	San Francisco-Oakland-San Jose, CA: SMSA Counties: 7120 Salinas-Seaside-Monterey, CA CA Monterey 7360 San Francisco-Oakland CA Alameda; CA Contra Costa; CA Marin; CA San Francisco; CA San Mateo 7400 San Jose, CA CA Santa Clara, CA 7485 Santa Cruz, CA CA Santa Cruz 7500 Santa Rosa CA Sonoma 8720 Vallejo-Fairfield-Napa, CA CA Napa; CA Solano Non-SMSA Counties: CA Lake; CA Mendocino; CA San Benito	28.9 25.6 19.6 14.9 9.1 17.1 23.2
177	Sacramento, CA: SMSA Counties: 6920 Sacramento, CA CA Placer; CA Sacramento; CA Yolo Non-SMSA Counties CA Butte; CA Colusa; CA El Dorado; CA Glenn; CA Nevada; CA Sierra; CA Sutter; CA Yuba	16.1 14.3
178	Stockton-Modesto, CA: SMSA Counties: 5170 Modesto, CA CA Stanislaus 8120 Stockton, CA CA San Joaquin Non-SMSA Counties CA Alpine; CA Amador; CA Calaveras; CA Mariposa; CA Merced; CA Toulumne	12.3 24.3 19.8
179	Fresno-Bakersfield, CA SMSA Counties: 0680 Bakersfield, CA CA Kern 2840 Fresno, CA CA Fresno Non-SMSA Counties: CA Kings; CA Madera; CA Tulare	19.1 26.1 23.6
180	Los Angeles, CA: SMSA Counties: 0360 Anaheim-Santa Ana-Garden Grove, CA CA Orange 4480 Los Angeles-Long Beach, CA CA Los Angeles 6000 Oxnard-Simi Valley-Ventura, CA CA Ventura	11.9 28.3 21.5

	6780 Riverside-San Bernardino-Ontario, CA CA Riverside; CA San Bernardino	19.0
	7480 Santa Barbara-Santa Maria-Lompoc, CA CA Santa Barbara	19.7
	Non-SMSA Counties CA Inyo; CA Mono; CA San Luis Obispo	24.6
181	San Diego, CA: SMSA Counties	16.9
	7320 San Diego, CA CA San Diego	18.2
	Non-SMSA Counties CA Imperial	

For each July during which work is performed under the contract, you and each non-material-supplier subcontractor with a subcontract of \$10,000 or more must complete Form FHWA PR-1391 (Appendix C to 23 CFR 230). Submit the forms by August 15.

7-1.50D Training

Section 7-1.50D, "Training," applies if a training goal is specified in the special provisions.

As part of your equal opportunity affirmative action program, provide on-the-job training to develop full journeymen in the types of trades or job classifications involved.

You have primary responsibility for meeting this training goal.

If you subcontract a contract part, determine how many trainees or apprentices are to be trained by the subcontractor.

Include these training requirements in your subcontract.

Where feasible, 25 percent of apprentices or trainees in each occupation must be in their 1st year of apprenticeship or training.

Distribute the number of apprentices or trainees among the work classifications on the basis of your needs and the availability of journeymen in the various classifications within a reasonable recruitment area.

Before starting work, submit to the Department:

1. Number of apprentices or trainees to be trained for each classification
2. Training program to be used
3. Training starting date for each classification

Obtain the Department's approval for this submitted information before you start work. The Department credits you for each apprentice or trainee you employ on the work who is currently enrolled or becomes enrolled in an approved program.

The primary objective of Section 7-2.04, "Training," is to train and upgrade minorities and women toward journeyman status. Make every effort to enroll minority and women apprentices or trainees, such as conducting systematic and direct recruitment through public and private sources likely to yield minority and women apprentices or trainees, to the extent they are available within a reasonable recruitment area. Show that you have made the efforts. In making these efforts, do not discriminate against any applicant for training.

Do not employ as an apprentice or trainee an employee:

1. In any classification in which the employee has successfully completed a training course leading to journeyman status or in which the employee has been employed as a journeyman
2. Who is not registered in a program approved by the State's State Administrator of Apprenticeship

Ask the employee if the employee has successfully completed a training course leading to journeyman status or has been employed as a journeyman. Your records must show the employee's answers to the questions.

In your training program, establish the minimum length and training type for each classification. The Department and FHWA approves a program if one of the following is met:

1. It is calculated to:
 - 1.1. Meet the your equal employment opportunity responsibilities
 - 1.2. Qualify the average apprentice or trainee for journeyman status in the classification involved by the end of the training period

Replace Section 9-1.05 with:

9-1.05 STOP NOTICE WITHHOLDS

The Department may withhold payments to cover claims filed under Civ Code § 3179 et seq.

Add:

9-1.053 PERFORMANCE FAILURE WITHHOLDS

During each estimate period you fail to comply with a contract part, including submittal of a document as specified, the Department withholds a part of the progress payment. The documents include quality control plans, schedules, traffic control plans, and water pollution control submittals.

For 1 performance failure, the Department withholds 25 percent of the progress payment but does not withhold more than 10 percent of the total bid.

For multiple performance failures, the Department withholds 100 percent of the progress payment but does not withhold more than 10 percent of the total bid.

The Department returns performance-failure withholds in the progress payment following the correction of noncompliance.

Add:

9-1.055 PENALTY WITHHOLDS

Penalties include fines and damages that are proposed, assessed, or levied against you or the Department by a governmental agency or citizen lawsuit. Penalties are also payments made or costs incurred in settling alleged permit violations of Federal, State, or local laws, regulations, or requirements. The cost incurred may include the amount spent for mitigation or correcting a violation.

If you or the Department is assessed a penalty, the Department may withhold the penalty amount until the penalty disposition has been resolved. The Department may withhold penalty funds and notify you within 15 days of the withhold. If the penalty amount is less than the amount being withheld from progress payments for retentions, the Department will not withhold the penalty amount.

If the penalty is resolved for less than the amount withheld, the Department pays interest at a rate of 6 percent per year on the excess withhold. If the penalty is not resolved, the withhold becomes a deduction.

Instead of the withhold, you may provide a bond payable to the Department of Transportation equal to the highest estimated liability for any disputed penalties proposed.

Add:

9-1.057 PROGRESS WITHHOLDS FOR FEDERAL-AID CONTRACTS

Section 9-1.057, "Progress Withholds for Federal-Aid Contracts," applies to a Federal-aid contract.

The Department withholds 10 percent of a partial payment for noncompliant progress. Noncompliant progress occurs when:

1. Total days to date exceed 75 percent of the revised contract working days
2. Percent of working days elapsed exceeds the percent of value of work completed by more than 15 percent

The Engineer determines the percent of working days elapsed by dividing the total days to date by the revised contract working days and converting the quotient to a percentage.

The Engineer determines the percent of value of work completed by summing payments made to date and the amount due on the current progress estimate, dividing this sum by the current total estimated value of the work, and converting the quotient to a percentage. These amounts are shown on the Progress Payment Voucher.

When the percent of working days elapsed minus the percent of value of work completed is less than or equal to 15 percent, the Department returns the withhold in the next progress payment.

In Section 9-1.06 replace the 3rd paragraph with:

For a non-Federal-aid project, the Department retains 10 percent of the estimated value of the work done and 10 percent of the value of materials estimated to have been furnished and delivered and unused or furnished and stored as part security for the fulfillment of the contract by the Contractor, except that at any time after 20 percent of the work has been completed,

In Section 51-1.12D replace the 4th paragraph with:

Expanded polystyrene shall be a commercially available polystyrene board. Expanded polystyrene shall have a minimum flexural strength of 35 psi determined in conformance with the requirements in ASTM Designation: C 203 and a compressive yield strength of between 16 and 40 psi at 5 percent compression. Surfaces of expanded polystyrene against which concrete is placed shall be faced with hardboard. Hardboard shall be 1/8 inch minimum thickness, conforming to ANSI A135.4, any class. Other facing materials may be used provided they furnish equivalent protection. Boards shall be held in place by nails, waterproof adhesive, or other means approved by the Engineer.

In Section 51-1.12F replace the 3rd paragraph with:

Type A and AL joint seals shall consist of a groove in the concrete that is filled with field-mixed silicone sealant.

In Section 51-1.12F in the 6th paragraph, replace the table with:

Movement Rating (MR)	Seal Type
MR ≤ 1 inch	Type A or Type B
1 inch < MR ≤ 2 inches	Type B
2 inches < MR ≤ 4 inches	Joint Seal Assembly (Strip Seal)
MR > 4 inches	Joint Seal Assembly (Modular Unit) or Seismic Joint

In Section 51-1.12F(3)(a) replace the 1st paragraph with:

The sealant must consist of a 2-component silicone sealant that will withstand up to ±50 percent movement.

In Section 51-1.12F(3)(a) replace the 2nd paragraph with:

Silicone sealants must be tested under California Test 435 and must comply with the following:

Specification	Requirement
Modulus at 150 percent elongation	8–75 psi
Recovery	21/32 inch max.
Notch Test	Notched or loss of bond 1/4 inch, max.
Water Resistance	Notched or loss of bond 1/4 inch, max.
Ultraviolet Exposure ASTM Designation: G 154, Table X2.1, Cycle 2.	No more than slight checking or cracking.
Cone Penetration	4.5-12.0 mm

In Section 51-1.12F(3)(a) delete the 3rd and 8th paragraphs.

In Section 51-1.12F(3)(a) replace the 10th paragraph with:

A Certificate of Compliance accompanied by a certified test report must be furnished for each batch of silicone sealant in conformance with the provisions in Section 6-1.07, "Certificates of Compliance."

In Section 51-1.12F(3)(b) replace the 2nd paragraph with:

The preformed elastomeric joint seal must conform to the requirements in ASTM D 2628 and the following:

1. The seal must consist of a multichannel, nonporous, homogeneous material furnished in a finished extruded form.
2. The minimum depth of the seal measured at the contact surface must be at least 95 percent of the minimum uncompressed width of the seal as designated by the manufacturer.

3. When tested in conformance with the requirements in California Test 673 for Type B seals, joint seals must provide a movement rating (MR) of not less than that shown on the plans.
4. The top and bottom edges of the joint seal must maintain continuous contact with the sides of the groove over the entire range of joint movement.
5. The seal must be furnished full length for each joint with no more than 1 shop splice in any 60-foot length of seal.
6. The Contractor must demonstrate the adequacy of the procedures to be used in the work before installing seals in the joints.
7. One field splice per joint may be made at locations and by methods approved by the Engineer. The seals are to be manufactured full length for the intended joint, then cut at the approved splice section and rematched before splicing. The Contractor must submit splicing details prepared by the joint seal manufacturer for approval before beginning splicing work.
8. Shop splices and field splices must have no visible offset of exterior surfaces and must show no evidence of bond failure.
9. At all open ends of the seal that would admit water or debris, each cell must be filled to a depth of 3 inches with commercial quality open cell polyurethane foam or closed by other means subject to approval by the Engineer.

In Section 51-1.12F(3)(b) replace the 7th paragraph with:

The joint seal must be installed full length for each joint with equipment that does not twist or distort the seal, elongate the seal longitudinally, or otherwise cause damage to the seal or to the concrete forming the groove.

In Section 51-1.12F(3)(b) in the 11th paragraph, replace the 1st sentence with:

Samples of the prefabricated joint seals, not less than 3 feet in length, will be taken by the Engineer from each lot of material.

In Section 51-1.12H(1) in the 6th paragraph, replace the 4th and 5th sentences with:

Each ply of fabric shall have a breaking strength of not less than 800 pounds per inch of width in each thread direction when 3" x 36" samples are tested on split drum grips. The bond between double plies shall have a minimum peel strength of 20 pounds per inch.

In Section 51-1.12H(1) in the 8th paragraph, in the table, replace the "Hardness (Type A)" requirements with:

Hardness (Type A)	D 2240 with 2kg mass.	55 ±5
-------------------	-----------------------	-------

In Section 51-1.12H(2) in the 1st paragraph in item A, replace the 1st and 2nd sentences with:

The bearings shall consist of alternating steel laminates and internal elastomer laminates with top and bottom elastomer covers. Steel laminates shall have a nominal thickness of 0.075 inch (14 gage).

In Section 51-1.135 replace the 1st paragraph with:

Mortar shall be composed of cementitious material, sand, and water proportioned and mixed as specified in this Section 51-1.135.

In Section 51-1.135 replace the 3rd paragraph with:

The proportion of cementitious material to sand, measured by volume, shall be one to 2 unless otherwise specified.

In Section 51-1.17 in 4th paragraph, replace the 3rd sentence with:

The surfaces shall have a profile trace showing no high points in excess of 0.25 inch, and the portions of the surfaces within the traveled way shall have a profile count of 5 or less in any 100-foot section.

Add:

51-1.17A Deck Crack Treatment

The Contractor shall use all means necessary to minimize the development of shrinkage cracks.

The Contractor shall remove all equipment and materials from the deck and clean the surface as necessary for the Engineer to measure the surface crack intensity. Surface crack intensity will be determined by the Engineer after completion of concrete cure, before prestressing, and before the release of falsework. In any 500 square foot portion of deck within the limits of the new concrete deck, should the intensity of cracking be such that there are more than 16 feet of cracks whose width at any location exceeds 0.02 inch, the deck shall be treated with methacrylate resin. The area of deck to be treated shall have a width that extends for the entire width of new deck inside the concrete barriers and a length that extends at least 5 feet beyond the furthest single continuous crack outside the 500 square foot portion, measured from where that crack exceeds 0.02 inch in width, as determined by the Engineer.

Deck crack treatment shall include furnishing, testing, and application of methacrylate resin and sand. If grinding is required, deck treatment shall take place before grinding.

51-1.17A(1) Submittals

Before starting deck treatment, the Contractor shall submit plans in conformance with Section 5-1.02, "Plans and Working Drawings," for the following:

1. Public safety plan for the use of methacrylate resin
2. Placement plan for the construction operation

The plans shall identify materials, equipment, and methods to be used.

The public safety plan for the use of methacrylate resin shall include details for the following:

1. Shipping
2. Storage
3. Handling
4. Disposal of residual methacrylate resin and the containers

The placement plan for construction shall include the following:

1. Schedule of deck treatment for each bridge. The schedule shall be consistent with "Maintaining Traffic" of the special provisions and shall include time for the Engineer to perform California Test 342.
2. Methods and materials to be used, including the following:
 - 2.1. Description of equipment for applying the resin
 - 2.2. Description of equipment for applying the sand
 - 2.3. Gel time range and final cure time for the resin

If the measures proposed in the safety plan are inadequate to provide for public safety associated with the use of methacrylate resin, the Engineer will reject the plan and direct the Contractor to revise the plan. Directions for revisions will be in writing and include detailed comments. The Engineer will notify the Contractor of the approval or rejection of a submitted or revised plan within 15 days of receipt of that plan.

In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

51-1.17A(2) Materials

Before using methacrylate resin, a Material Safety Data Sheet shall be submitted for each shipment of resin.

Methacrylate resin shall be low odor and have a high molecular weight. Before adding initiator, the resin shall have a maximum volatile content of 30 percent when tested in conformance with the requirements in ASTM Designation: D 2369, and shall conform to the following:

PROPERTY	REQUIREMENT	TEST METHOD
* Viscosity	25 cP, maximum, (Brookfield RVT with UL adaptor, 50 RPM at 77°F)	ASTM D 2196
* Specific Gravity	0.90 minimum, at 77°F	ASTM D 1475
* Flash Point	180°F, minimum	ASTM D 3278
* Vapor Pressure	1.0 mm Hg, maximum, at 77°F	ASTM D 323
Tack-free Time	400 minutes, maximum at 25°C	Specimen prepared per California Test 551
PCC Saturated Surface-Dry Bond Strength	3.5 MPa, minimum at 24 hours and 21±1°C	California Test 551
* Test shall be performed before adding initiator.		

51-1.17A(3) Testing

The Contractor shall allow 20 days for sampling and testing by the Engineer of the methacrylate resin before proposed use. If bulk resin is to be used, the Contractor shall notify the Engineer in writing at least 15 days before the delivery of the bulk resin to the job site. Bulk resin is any resin stored in containers in excess of 55 gallons.

Before starting production treatment, the Contractor shall treat a test area of approximately 500 square feet that is within the project limits and at a location approved by the Engineer. When available the test area shall be outside of the traveled way. Weather and pavement conditions during the test treatment shall be similar to those expected on the deck. Equipment used for testing shall be similar to those used for deck treating operations.

During test and production deck treatment, test tiles shall be used to evaluate the resin cure time. The Contractor shall coat at least one 4" x 4" commercial quality smooth glazed tile for each batch of methacrylate resin. The coated tile shall be placed adjacent to the corresponding treated area. Sand shall not be applied to the test tiles.

The acceptance criteria for a treated area is as follows:

1. The test tiles are dry to the touch.
2. The treated deck surface is tack free (non-oily).
3. The sand cover adheres and resists brushing by hand.
4. Excess sand has been removed by vacuuming or sweeping.
5. The coefficient of friction is at least 0.35 when tested in conformance with California Test 342.

Deck treatment on the test area shall demonstrate that the methods and materials meet the acceptance criteria and that the production work will be completed within the specified time for maintaining traffic.

If a test or production area fails to meet the acceptance criteria, as determined by the Engineer, the treatment will be rejected, and the treatment shall be removed and replaced until the area complies with the acceptance criteria.

51-1.17A(4) Construction

Equipment shall be fitted with suitable traps, filters, drip pans, or other devices as necessary to prevent oil or other deleterious material from being deposited on the deck.

Before deck treatment with methacrylate resin, the bridge deck surface shall be cleaned by abrasive blasting, and all loose material shall be blown from visible cracks using high-pressure air. Concrete curing seals shall be cleaned from the deck surface to be treated, and the deck shall be dry when blast cleaning is performed. If the deck surface becomes contaminated at any time before placing the resin, the deck surface shall be cleaned by abrasive blasting.

Where abrasive blasting is being performed within 10 feet of a lane occupied by public traffic, the residue including dust shall be removed immediately after contact between the abrasive and the surface being treated. The removal shall be by a vacuum attachment operating concurrently with the abrasive blasting operation.

A compatible promoter/initiator system shall be capable of providing the resin gel time range shown on the placement plan. Gel time shall be adjusted to compensate for the changes in temperature throughout treatment application.

In Section 52-1.07 in the 11th paragraph, replace the table with:

Height Zone (H) (Feet above ground)	Wind Pressure Value (psf)
$H \leq 30$	20
$30 < H \leq 50$	25
$50 < H \leq 100$	30
$H > 100$	35

In Section 52-1.08B(1) in the 2nd paragraph, replace the table with:

Reinforcing Bar Number	Total Slip
4	0.010-inch
5	0.010-inch
6	0.010-inch
7	0.014-inch
8	0.014-inch
9	0.014-inch
10	0.018-inch
11	0.018-inch
14	0.024-inch
18	0.030-inch

In Section 52-1.08B(2) in the 6th paragraph, replace the subparagraph with:

The minimum preheat and interpass temperatures shall be 400° F for Grade 40 bars and 600° F for Grade 60 bars. Immediately after completing the welding, at least 6 inches of the bar on each side of the splice shall be covered by an insulated wrapping to control the rate of cooling. The insulated wrapping shall remain in place until the bar has cooled below 200° F.

In Section 52-1.08(C) in the 3rd paragraph, replace item A with:

- A. Proper facilities, including a calibrated tensile testing machine capable of breaking the largest size of reinforcing bar to be tested.

In Section 52-1.08(C) replace the 5th paragraph with:

Prequalification and production sample splices and testing shall conform to California Test 670 and these specifications.

In Section 52-1.08(C) delete the 6th paragraph.

In Section 52-1.08(C)(2)(a) replace the 5th paragraph with:

If 3 or more sample splices from a production test conform to the provisions in this Section 52-1.08C(2), "Service Splice Test Criteria," all splices in the lot represented by this production test will be considered acceptable.

In Section 52-1.08(C)(3) replace the 2nd paragraph with:

A minimum of 1 control bar shall be removed from the same bar as, and adjacent to, all ultimate prequalification, production, and quality assurance sample splices. The lengths of control bars shall conform to the lengths specified for sample splices in California Test 670. The portion of adjacent bar remaining in the work shall also be identified with weatherproof markings that correspond to its adjacent control bar.

In Section 52-1.08(C)(3) in the 6th paragraph, replace the 2nd sentence with:

In addition, necking of the bar, as defined in California Test 670, shall occur at rupture regardless of whether the bar breaks inside or outside the affected zone.

SECTION 75 MISCELLANEOUS METAL

(Issued 01-18-08)

In Section 75-1.03 replace the 13th paragraph with:

Concrete anchorage devices shall be mechanical expansion or resin capsule types installed in drilled holes or cast-in-place insert types. The anchorage devices shall be selected from the Department's Pre-Qualified Products List at:

http://www.dot.ca.gov/hq/esc/approved_products_list

The anchorage devices shall be a complete system, including threaded studs, hex nuts, and cut washers. Thread dimensions for externally threaded concrete anchorage devices prior to zinc coating, shall conform to the requirements in ANSI Standard: B1.1 having Class 2A tolerances or ANSI Standard: B1.13M having Grade 6g tolerances. Thread dimensions for internally threaded concrete anchorage devices shall conform to the requirements in ASTM A 563.

In Section 75-1.03 replace the 18th paragraph with:

Mechanical expansion anchors shall, when installed in accordance with the manufacturer's instructions and these specifications and tested in conformance with the requirements in California Test 681, withstand the application of a sustained tension test load of at least the following values for at least 48 hours with a movement not greater than 0.035 inch:

Stud Diameter (inches)	Sustained Tension Test Load (pounds)
*3/4	5,000
5/8	4,100
1/2	3,200
3/8	2,100
1/4	1,000

* Maximum stud diameter permitted for mechanical expansion anchors.

Resin capsule anchors shall, when installed in accordance with the manufacturer's instructions and these specifications and tested in conformance with the requirements in California Test 681, withstand the application of a sustained tension test load of at least the following values for at least 48 hours with a movement not greater than 0.010 inch:

Stud Diameter (inches)	Sustained Tension Test Load (pounds)
1-1/4	31,000
1	17,900
7/8	14,400
3/4	5,000
5/8	4,100
1/2	3,200
3/8	2,100
1/4	1,000

At least 25 days before use, the Contractor shall submit one sample of each resin capsule anchor per lot to the Transportation Laboratory for testing. A lot of resin capsule anchors is 100 units, or fraction thereof, of the same brand and product name.

In Section 75-1.03 replace the 20th paragraph with:

The Pre-Qualified Products List for concrete anchorage devices has been developed from data previously furnished by suppliers or manufacturers for each type and size. Approval of additional anchorage device types and sizes is contingent upon the Contractor submitting to the Engineer one sample of each type of concrete anchorage device, manufacturer's

51-1.135, "Mortar," except the mortar shall consist of one part by volume of cementitious material and 3 parts of clean sand and shall contain only sufficient moisture to permit packing. Mortar shall be cured by keeping it damp for 3 days.

In Section 86-2.05C in the 18th paragraph, replace item D with:

- D. The conduit shall be placed in the bottom of the trench, and the trench shall be backfilled with minor concrete conforming to the provisions in Section 90-10, "Minor Concrete." Minor concrete shall contain not less than 590 pounds of cementitious material per cubic yard. Concrete backfill shall be placed to the pavement surface except, when the trench is in asphalt concrete pavement and additional pavement is not being placed, the top 0.10 foot of the trench shall be backfilled with asphalt concrete produced from commercial quality paving asphalt and aggregates.

In Section 86-2.05C in the 23rd paragraph, replace item C with:

- C. Precast concrete conduit cradles shall conform to the dimensions shown on the plans and shall be constructed of minor concrete and commercial quality welded wire fabric. Minor concrete shall conform to the provisions in Section 90-10, "Minor Concrete," and shall contain not less than 590 pounds of cementitious material per cubic yard. The cradles shall be moist cured for not less than 3 days.

In Section 86-2.05C in the 23rd paragraph, replace item G with:

- G. The space around conduits through bridge abutment walls shall be filled with mortar conforming to the provisions in Section 51-1.135, "Mortar," except that the proportion of cementitious material to sand shall be one to 3.

In Section 86-2.07 replace the 5th paragraph with:

Concrete placed around and under traffic pull boxes as shown on the plans shall be minor concrete conforming to the provisions in Section 90-10, "Minor Concrete."

In Section 86-2.08A in the table, replace the "Traffic Signal Controller Cabinet" requirements with:

Traffic Signal Controller Cabinet	Ungrounded Circuit Conductor	Blk	None	CON-1	6
	Grounded Circuit Conductor	Wht	None	CON-2	6

In Section 86-4.06 in the 1st paragraph, replace the 1st sentence with:

Message symbols for pedestrian signal faces shall be white WALKING PERSON and Portland orange UPRAISED HAND conforming to the requirements in the Institute of Transportation Engineers Standards: "Pedestrian Traffic Control Signal Indications" and the "California MUTCD."

In Section 86-4.07 in the 10th paragraph, replace the 2nd sentence with:

The color of "UPRAISED HAND" shall be Portland orange conforming to the requirements of the Institute of Transportation Engineers Standards: "Pedestrian Traffic Control Signal Indications" and the "California MUTCD."

In Section 86-5.01D replace the 1st paragraph with:

When a foundation for a pressure-sensitive vehicle detector is to be removed, the hole left by removing the detector frame and foundation shall be filled with minor concrete, except the roadway surface shall be reconstructed with material to match existing surfacing. Minor concrete shall conform to the provisions in Section 90-10, "Minor Concrete," except that the concrete shall contain not less than 420 pounds of cementitious material per cubic yard for asphalt concrete surfaced roadways and not less than 590 pounds of cementitious material per cubic yard for portland cement concrete surfaced roadways.

Whenever the 28-day compressive strength shown on the plans is greater than 3,600 pounds per square inch, the concrete shall be designated by compressive strength. If the plans show a 28-day compressive strength that is 4,000 pounds per square inch or greater, an additional 14 days will be allowed to obtain the specified strength. The 28-day compressive strengths shown on the plans that are 3,600 pounds per square inch or less are shown for design information only and are not a requirement for acceptance of the concrete.

Concrete designated by compressive strength shall be proportioned such that the concrete will attain the strength shown on the plans or specified in the special provisions.

Before using concrete for which the mix proportions have been determined by the Contractor, or in advance of revising those mix proportions, the Contractor shall submit in writing to the Engineer a copy of the mix design.

Compliance with cementitious material content requirements will be verified in conformance with procedures described in California Test 518 for cement content. For testing purposes, supplementary cementitious material shall be considered to be cement. Batch proportions shall be adjusted as necessary to produce concrete having the specified cementitious material content.

If any concrete has a cementitious material, portland cement, or supplementary cementitious material content that is less than the minimum required, the concrete shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State \$0.25 for each pound of cementitious material, portland cement, or supplementary cementitious material that is less than the minimum required. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract. The deductions will not be made unless the difference between the contents required and those actually provided exceeds the batching tolerances permitted by Section 90-5, "Proportioning." No deductions will be made based on the results of California Test 518.

The requirements of the preceding paragraph shall not apply to minor concrete or commercial quality concrete.

90-2 MATERIALS

90-2.01 CEMENTITIOUS MATERIALS

Unless otherwise specified, cementitious material shall be either a combination of Type II or Type V portland cement and a supplementary cementitious material, or a blended cement.

Cementitious materials used in cast-in-place concrete for exposed surfaces of like elements of a structure shall be from the same sources and of the same proportions.

Cementitious materials shall be protected from moisture until used. Sacked cementitious materials shall be piled to permit access for tallying, inspecting, and identifying each shipment.

Facilities shall be provided to ensure that cementitious materials meeting this Section 90-2.01 are kept separate from other cementitious materials. Sampling cementitious materials shall be in conformance with California Test 125.

The Contractor shall furnish a Certificate of Compliance for cementitious materials in conformance with the provisions in Section 6-1.07, "Certificates of Compliance." The Certificate of Compliance shall indicate the source by name and location (including country, state, and city). If cementitious material is delivered directly to the job site, the Certificate of Compliance shall be signed by the cementitious material supplier. If the cementitious material is used in ready-mixed concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.

90-2.01A Cement

Portland cement shall conform to the requirements in ASTM Designation: C 150 except, using a 10-sample moving average, limestone shall not exceed 2.5 percent. The C_3S content of Type II cement shall not exceed 65 percent.

Blended cement shall conform to the requirements for Portland Blast-Furnace Slag, Cement Type IS (MS) or Portland-Pozzolan Cement, Type IP (MS) in AASHTO Designation: M 240 and shall be comprised of an intimate and uniform blend of Type II or Type V cement and supplementary cementitious material in an amount conforming to the requirements in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials."

In addition, blended cement, Type II portland cement, and Type V portland cement shall conform to the following requirements:

- A. The cement shall not contain more than 0.60-percent by mass of alkalis, calculated as the percentage of Na_2O plus 0.658 times the percentage of K_2O , when determined by methods as required in AASHTO Designation: T 105;
- B. The autoclave expansion shall not exceed 0.50-percent; and
- C. Mortar, containing the cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not expand in water more than 0.010-percent and shall not contract in air more than 0.048-percent, except that when cement is to be used for precast prestressed concrete piling, precast prestressed concrete members, or steam cured concrete products, the mortar shall not contract in air more than 0.053-percent.

Type III portland cement shall be used only as specified in the special provisions or with the approval of the Engineer. Type III portland cement shall conform to the additional requirements listed above for Type II portland cement, except when tested in conformance with California Test 527, mortar containing Type III portland cement shall not contract in air more than 0.075-percent.

90-2.01B Supplementary Cementitious Materials (SCM)

Fly ash shall conform to the requirements in AASHTO Designation: M 295, Class F, and the following:

- A. Calcium oxide content shall not exceed 10 percent.
- B. The available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 311 or the total alkali, as sodium oxide equivalent, shall not exceed 5.0 percent when determined in conformance with the requirements in AASHTO Designation: T 105.
- C. Commingling of fly ash from different sources at uncontrolled ratios is permissible only if the following criteria are satisfied:
 - 1. Sources of fly ash to be commingled shall be on the approved list of materials for use in concrete.
 - 2. Testing of the commingled product is the responsibility of the fly ash supplier.
 - 3. Each fly ash's running average of density shall not differ from any other by more than 0.01-pound per cubic inch at the time of commingling.
 - 4. Each fly ash's running average of loss on ignition shall not differ from any other by more than one percent at the time of commingling.
 - 5. The final product of commingled fly ash shall conform to the requirement in AASHTO Designation: M 295.

Raw or calcined natural pozzolans shall conform to the requirements in AASHTO Designation: M 295, Class N and the following requirements:

- A. Calcium oxide content shall not exceed 10 percent.
- B. The available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 311 or the total alkali, as sodium oxide equivalent, shall not exceed 5.0 percent when determined in conformance with the requirements in AASHTO Designation: T 105.

Ground Granulated Blast Furnace Slag (GGBFS) shall conform to the requirements in AASHTO Designation: M 302, Grade 100 or Grade 120.

Silica Fume shall conform to the requirements of AASHTO Designation: M 307, with reduction in mortar expansion of 80 percent, minimum, using the cement from the proposed mix design.

90-2.01C Required Use Of Supplementary Cementitious Materials

The amount of portland cement and SCM used in portland cement concrete shall conform to the minimum cementitious material content provisions in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," and the following:

- A. If a blended cement conforming to the provisions in Section 90-2.01A, "Cement," is used, the minimum amount of SCM incorporated into the cement shall conform to the provisions in this Section 90-2.01C.
- B. Fly ash or natural pozzolan, silica fume, or GGBFS shall not be used with Type IP or Type IS cements.

Use of SCMs shall conform to the following:

- A. If fly ash or natural pozzolan is used:
 - 1. The minimum amount of portland cement shall not be less than 75 percent by weight of the specified minimum cementitious material content.
 - 2. The minimum amount of fly ash or natural pozzolan shall be:

- a. Fifteen percent by weight of the total amount of cementitious material if the calcium oxide content of fly ash or natural pozzolan is equal to or less than 2 percent by weight;
 - b. Twenty-five percent by weight of the total amount of cementitious material if the calcium oxide content of fly ash or natural pozzolan is greater than 2 percent by weight.
3. The total amount of fly ash or natural pozzolan shall not exceed 35 percent by weight of the total amount of cementitious material to be used in the mix. If Section 90-1.01, "Description," specifies a maximum cementitious material content in pounds per cubic yard, the total weight of portland cement and fly ash or natural pozzolan per cubic yard shall not exceed the specified maximum cementitious material content.
- B. If silica fume is used:
1. The amount of silica fume shall not be less than 10 percent by weight of the total amount of cementitious material.
 2. The amount of portland cement shall not be less than 75 percent by weight of the specified minimum cementitious material content.
 3. If Section 90-1.01, "Description," specifies a maximum cementitious material content in pounds per cubic yard, the total weight of portland cement and silica fume per cubic yard shall not exceed the specified maximum cementitious material content.
- C. If GGBFS is used:
1. The minimum amount of GGBFS shall be either:
 - a. Forty percent of the total cementitious material to be used, if the aggregates used in the concrete are on the Department's list of "Approved Aggregates For Use in Concrete with Reduced Fly Ash."
 - b. No less than 50 percent.
 2. The amount of GGBFS shall not exceed 60 percent by weight of the total amount of cementitious materials to be used.

90-2.02 AGGREGATES

Aggregates shall be free from deleterious coatings, clay balls, roots, bark, sticks, rags, and other extraneous material.

The Contractor shall provide safe and suitable facilities, including necessary splitting devices for obtaining samples of aggregates, in conformance with California Test 125.

Aggregates shall be of such character that it will be possible to produce workable concrete within the limits of water content provided in Section 90-6.06, "Amount of Water and Penetration."

Aggregates shall have not more than 10 percent loss when tested for soundness in conformance with the requirements in California Test 214. The soundness requirement for fine aggregate will be waived, provided that the durability index, D_f , of the fine aggregate is 60 or greater when tested for durability in conformance with California Test 229.

If the results of any one or more of the Cleanness Value, Sand Equivalent, or aggregate grading tests do not meet the requirements specified for "Operating Range" but all meet the "Contract Compliance" requirements, the placement of concrete shall be suspended at the completion of the current pour until tests or other information indicate that the next material to be used in the work will comply with the requirements specified for "Operating Range."

If the results of either or both the Cleanness Value and coarse aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete that is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State \$3.50 per cubic yard for paving concrete and \$5.50 per cubic yard for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

If the results of either or both the Sand Equivalent and fine aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete which is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State \$3.50 per cubic yard for paving concrete and \$5.50 per cubic yard for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

The 2 preceding paragraphs apply individually to the "Contract Compliance" requirements for coarse aggregate and fine aggregate. When both coarse aggregate and fine aggregate do not conform to the "Contract Compliance" requirements, both paragraphs shall apply. The payments specified in those paragraphs are in addition to any payments made in conformance with the provisions in Section 90-1.01, "Description."

No single Cleanness Value, Sand Equivalent, or aggregate grading test shall represent more than 300 cubic yards of concrete or one day's pour, whichever is smaller.

When the source of an aggregate is changed, the Contractor shall adjust the mix proportions and submit in writing to the Engineer a copy of the mix design before using the aggregates.

90-2.02A Coarse Aggregate

Coarse aggregate shall consist of gravel, crushed gravel, crushed rock, reclaimed aggregate, crushed air-cooled iron blast furnace slag or combinations thereof. Crushed air-cooled blast furnace slag shall not be used in reinforced or prestressed concrete.

Reclaimed aggregate is aggregate that has been recovered from plastic concrete by washing away the cementitious material. Reclaimed aggregate shall conform to all aggregate requirements.

Coarse aggregate shall conform to the following quality requirements:

Tests	California Test	Requirements
Loss in Los Angeles Rattler (after 500 revolutions)	211	45% max.
Cleanness Value		
Operating Range	227	75 min.
Contract Compliance	227	71 min.

In lieu of the above Cleanness Value requirements, a Cleanness Value "Operating Range" limit of 71, minimum, and a Cleanness Value "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the coarse aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

- A. Coarse aggregate sampled at the completion of processing at the aggregate production plant had a Cleanness Value of not less than 82 when tested in conformance with the requirements in California Test 227; and
- B. Prequalification tests performed in conformance with the requirements in California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.02B Fine Aggregate

Fine aggregate shall consist of natural sand, manufactured sand produced from larger aggregate or a combination thereof. Manufactured sand shall be well graded.

Fine aggregate shall conform to the following quality requirements:

Test	California Test	Requirements
Organic Impurities	213	Satisfactory ^a
Mortar Strengths Relative to Ottawa Sand	515	95%, min.
Sand Equivalent:		
Operating Range	217	75, min.
Contract Compliance	217	71, min.

- a Fine aggregate developing a color darker than the reference standard color solution may be accepted if it is determined by the Engineer, from mortar strength tests, that a darker color is acceptable.

In lieu of the above Sand Equivalent requirements, a Sand Equivalent "Operating Range" limit of 71, minimum, and a Sand Equivalent "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the fine aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

- A. Fine aggregate sampled at the completion of processing at the aggregate production plant had a Sand Equivalent value of not less than 82 when tested by California Test 217; and
- B. Prequalification tests performed in conformance with California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.03 WATER

In conventionally reinforced concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 1,000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1,300 parts per million of sulfates as SO₄, when tested in conformance with California Test 417. In prestressed concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 650 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1,300 parts per million of sulfates as SO₄, when tested in conformance with California Test 417. In no case shall the water contain an amount of impurities that will cause either: 1) a change in the setting time of cement of more than 25 percent when tested in conformance with the requirements in ASTM Designation: C 191 or ASTM Designation: C 266 or 2) a reduction in the compressive strength of mortar at 14 days of more than 5 percent, when tested in conformance with the requirements in ASTM Designation: C 109, when compared to the results obtained with distilled water or deionized water, tested in conformance with the requirements in ASTM Designation: C 109.

In nonreinforced concrete work, the water for curing, for washing aggregates and for mixing shall be free from oil and shall not contain more than 2,000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, or more than 1,500 parts per million of sulfates as SO₄, when tested in conformance with California Test 417.

In addition to the above provisions, water for curing concrete shall not contain impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.

Water reclaimed from mixer wash-out operations may be used in mixing concrete. The water shall not contain coloring agents or more than 300 parts per million of alkalis (Na₂O + 0.658 K₂O) as determined on the filtrate. The specific gravity of the water shall not exceed 1.03 and shall not vary more than ±0.010 during a day's operations.

90-2.04 Admixture Materials

Admixture materials shall conform to the requirements in the following ASTM Designations:

- A. Chemical Admixtures—ASTM Designation: C 494.
- B. Air-entraining Admixtures—ASTM Designation: C 260.

90-3 AGGREGATE GRADINGS

90-3.01 GENERAL

Before beginning concrete work, the Contractor shall submit in writing to the Engineer the gradation of the primary aggregate nominal sizes that the Contractor proposes to furnish. If a primary coarse aggregate or the fine aggregate is separated into 2 or more sizes, the proposed gradation shall consist of the gradation for each individual size, and the proposed proportions of each individual size, combined mathematically to indicate one proposed gradation. The proposed gradation shall meet the grading requirements shown in the table in this section, and shall show the percentage passing each of the sieve sizes used in determining the end result.

The Engineer may waive, in writing, the gradation requirements in this Section 90-3.01 and in Sections 90-3.02, "Coarse Aggregate Grading," 90-3.03, "Fine Aggregate Grading," and 90-3.04, "Combined Aggregate Gradings," if, in the Engineer's opinion, furnishing the gradation is not necessary for the type or amount of concrete work to be constructed.

Gradations proposed by the Contractor shall be within the following percentage passing limits:

Primary Aggregate Nominal Size	Sieve Size	Limits of Proposed Gradation
1 1/2" x 3/4"	1"	19 - 41
1" x No. 4	3/4"	52 - 85
1" x No. 4	3/8"	15 - 38
1/2" x No. 4	3/8"	40 - 78
3/8" x No. 8	3/8"	50 - 85
Fine Aggregate	No. 16	55 - 75
Fine Aggregate	No. 30	34 - 46
Fine Aggregate	No. 50	16 - 29

Should the Contractor change the source of supply, the Contractor shall submit in writing to the Engineer the new gradations before their intended use.

90-3.02 COARSE AGGREGATE GRADING

The grading requirements for coarse aggregates are shown in the following table for each size of coarse aggregate:

Sieve Sizes	Percentage Passing Primary Aggregate Nominal Sizes							
	1 1/2" x 3/4"		1" x No. 4		1/2" x No. 4		3/8" x No. 8	
	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance
2"	100	100	—	—	—	—	—	—
1 1/2"	88 - 100	85 - 100	100	100	—	—	—	—
1"	X ±18	X ±25	88 - 100	86 - 100	—	—	—	—
3/4"	0 - 17	0 - 20	X ±15	X ±22	100	100	—	—
1/2"	—	—	—	—	82 - 100	80 - 100	100	100
3/8"	0 - 7	0 - 9	X ±15	X ±22	X ±15	X ±22	X ±15	X ±20
No. 4	—	—	0 - 16	0 - 18	0 - 15	0 - 18	0 - 25	0 - 28
No. 8	—	—	0 - 6	0 - 7	0 - 6	0 - 7	0 - 6	0 - 7

In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

Coarse aggregate for the 1 1/2 inch, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," shall be furnished in 2 or more primary aggregate nominal sizes. Each primary aggregate nominal size may be separated into 2 sizes and stored separately, provided that the combined material conforms to the grading requirements for that particular primary aggregate nominal size.

When the one inch, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," is to be used, the coarse aggregate may be separated into 2 sizes and stored separately, provided that the combined material shall conform to the grading requirements for the 1" x No. 4 primary aggregate nominal size.

90-3.03 FINE AGGREGATE GRADING

Fine aggregate shall be graded within the following limits:

Sieve Sizes	Percentage Passing	
	Operating Range	Contract Compliance
3/8"	100	100
No. 4	95 - 100	93 - 100
No. 8	65 - 95	61 - 99
No. 16	X ±10	X ±13
No. 30	X ±9	X ±12
No. 50	X ±6	X ±9
No. 100	2 - 12	1 - 15
No. 200	0 - 8	0 - 10

In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

In addition to the above required grading analysis, the distribution of the fine aggregate sizes shall be such that the difference between the total percentage passing the No. 16 sieve and the total percentage passing the No. 30 sieve shall be between 10 and 40, and the difference between the percentage passing the No. 30 and No. 50 sieves shall be between 10 and 40.

Fine aggregate may be separated into 2 or more sizes and stored separately, provided that the combined material conforms to the grading requirements specified in this Section 90-3.03.

90-3.04 COMBINED AGGREGATE GRADINGS

Combined aggregate grading limits shall be used only for the design of concrete mixes. Concrete mixes shall be designed so that aggregates are combined in proportions that shall produce a mixture within the grading limits for combined aggregates as specified herein.

The combined aggregate grading, except when otherwise specified in these specifications or the special provisions, shall be either the 1 1/2 inch, maximum grading, or the 1 inch, maximum grading, at the option of the Contractor.

Grading Limits of Combined Aggregates

Sieve Sizes	Percentage Passing			
	1 1/2" Max.	1" Max.	1/2" Max.	3/8" Max.
2"	100	—	—	—
1 1/2"	90 - 100	100	—	—
1"	50 - 86	90 - 100	—	—
3/4"	45 - 75	55 - 100	100	—
1/2"	—	—	90 - 100	100
3/8"	38 - 55	45 - 75	55 - 86	50 - 100
No. 4	30 - 45	35 - 60	45 - 63	45 - 63
No. 8	23 - 38	27 - 45	35 - 49	35 - 49
No. 16	17 - 33	20 - 35	25 - 37	25 - 37
No. 30	10 - 22	12 - 25	15 - 25	15 - 25
No. 50	4 - 10	5 - 15	5 - 15	5 - 15
No. 100	1 - 6	1 - 8	1 - 8	1 - 8
No. 200	0 - 3	0 - 4	0 - 4	0 - 4

Changes from one grading to another shall not be made during the progress of the work unless permitted by the Engineer.

90-4 ADMIXTURES

90-4.01 GENERAL

Admixtures used in portland cement concrete shall conform to and be used in conformance with the provisions in this Section 90-4 and the special provisions. Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option as provided herein.

Chemical admixtures and air-entraining admixtures containing chlorides as Cl in excess of one percent by weight of admixture, as determined by California Test 415, shall not be used.

Admixtures shall be uniform in properties throughout their use in the work. Should it be found that an admixture as furnished is not uniform in properties, its use shall be discontinued.

If more than one admixture is used, the admixtures shall be compatible with each other so that the desirable effects of all admixtures used will be realized.

Chemical admixtures shall be used in conformance with the manufacturer's written recommendations.

90-4.02 MATERIALS

Admixture materials shall conform to the provisions in Section 90-2.04, "Admixture Materials."

90-4.03 ADMIXTURE APPROVAL

No admixture brand shall be used in the work unless it is on the Department's current list of approved brands for the type of admixture involved.

Admixture brands will be considered for addition to the approved list if the manufacturer of the admixture submits to the Transportation Laboratory a sample of the admixture accompanied by certified test results demonstrating that the admixture complies with the requirements in the appropriate ASTM Designation and these specifications. The sample shall be sufficient to permit performance of all required tests. Approval of admixture brands will be dependent upon a determination as to compliance with the requirements, based on the certified test results submitted, together with tests the Department may elect to perform.

If the Contractor proposes to use an admixture of a brand and type on the current list of approved admixture brands, the Contractor shall furnish a Certificate of Compliance from the manufacturer, as provided in Section 6-1.07, "Certificates of Compliance," certifying that the admixture furnished is the same as that previously approved. If a previously approved admixture is not accompanied by a Certificate of Compliance, the admixture shall not be used in the work until the Engineer has had sufficient time to make the appropriate tests and has approved the admixture for use. The Engineer may take samples for testing at any time, whether or not the admixture has been accompanied by a Certificate of Compliance.

90-4.04 REQUIRED USE OF CHEMICAL ADMIXTURES

If the use of a chemical admixture is specified, the admixture shall be used at the dosage specified, except that if no dosage is specified, the admixture shall be used at the dosage normally recommended by the manufacturer of the admixture.

90-4.05 OPTIONAL USE OF CHEMICAL ADMIXTURES

The Contractor may use Type A or F, water-reducing; Type B, retarding; or Type D or G, water-reducing and retarding admixtures as described in ASTM Designation: C 494 to conserve cementitious material or to facilitate any concrete construction application subject to the following conditions:

- A. If a water-reducing admixture or a water-reducing and retarding admixture is used, the cementitious material content specified or ordered may be reduced by a maximum of 5 percent by weight, except that the resultant cementitious material content shall be not less than 505 pounds per cubic yard; and
- B. When a reduction in cementitious material content is made, the dosage of admixture used shall be the dosage used in determining approval of the admixture.

Unless otherwise specified, a Type C accelerating chemical admixture conforming to the requirements in ASTM Designation: C 494, may be used in portland cement concrete. Inclusion in the mix design submitted for approval will not be required provided that the admixture is added to counteract changing conditions that contribute to delayed setting of the portland cement concrete, and the use or change in dosage of the admixture is approved in writing by the Engineer.

90-4.06 REQUIRED USE OF AIR-ENTRAINING ADMIXTURES

When air-entrainment is specified or ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce a concrete having the specified air content as determined by California Test 504.

90-4.07 OPTIONAL USE OF AIR-ENTRAINING ADMIXTURES

When air-entrainment has not been specified or ordered by the Engineer, the Contractor will be permitted to use an air-entraining admixture to facilitate the use of any construction procedure or equipment provided that the average air content, as determined by California Test 504, of 3 successive tests does not exceed 4 percent, and no single test value exceeds 5.5 percent. If the Contractor elects to use an air-entraining admixture in concrete for pavement, the Contractor shall so indicate at the time the Contractor designates the source of aggregate.

90-4.08 BLANK

90-4.09 BLANK

90-4.10 PROPORTIONING AND DISPENSING LIQUID ADMIXTURES

Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers for liquid admixtures shall have sufficient capacity to measure at one time the prescribed quantity required for each batch of concrete. Each dispenser shall include a graduated measuring unit into which liquid admixtures are measured to within ± 5 percent of the prescribed quantity for each batch. Dispensers shall be located and maintained so that the graduations can be accurately read from the point at which proportioning operations are controlled to permit a visual check of batching accuracy prior to discharge. Each measuring unit shall be clearly marked for the type and quantity of admixture.

Each liquid admixture dispensing system shall be equipped with a sampling device consisting of a valve located in a safe and readily accessible position such that a sample of the admixture may be withdrawn slowly by the Engineer.

If more than one liquid admixture is used in the concrete mix, each liquid admixture shall have a separate measuring unit and shall be dispensed by injecting equipment located in such a manner that the admixtures are not mixed at high concentrations and do not interfere with the effectiveness of each other. When air-entraining admixtures are used in conjunction with other liquid admixtures, the air-entraining admixture shall be the first to be incorporated into the mix, unless it is demonstrated that a different sequence improves performance.

When automatic proportioning devices are required for concrete pavement, dispensers for liquid admixtures shall operate automatically with the batching control equipment. The dispensers shall be equipped with an automatic warning system in good operating condition that will provide a visible or audible signal at the point at which proportioning operations are controlled when the quantity of admixture measured for each batch of concrete varies from the preselected dosage by more than 5 percent, or when the entire contents of the measuring unit are not emptied from the dispenser into each batch of concrete.

Unless liquid admixtures are added to premeasured water for the batch, their discharge into the batch shall be arranged to flow into the stream of water so that the admixtures are well dispersed throughout the batch, except that air-entraining admixtures may be dispensed directly into moist sand in the batching bins provided that adequate control of the air content of the concrete can be maintained.

Liquid admixtures requiring dosages greater than one-half gallon per cubic yard shall be considered to be water when determining the total amount of free water as specified in Section 90-6.06, "Amount of Water and Penetration."

90-4.11 BLANK

90-5 PROPORTIONING

90-5.01 STORAGE OF AGGREGATES

Aggregates shall be stored or stockpiled in such a manner that separation of coarse and fine particles of each size shall be avoided and the various sizes shall not become intermixed before proportioning.

Aggregates shall be stored or stockpiled and handled in a manner that prevent contamination by foreign materials. In addition, storage of aggregates at batching or mixing facilities that are erected subsequent to the award of the contract and that furnish concrete to the project shall conform to the following:

- A. Intermingling of the different sizes of aggregates shall be positively prevented. The Contractor shall take the necessary measures to prevent intermingling. The preventive measures may include, but are not necessarily limited to, physical separation of stockpiles or construction of bulkheads of adequate length and height; and
- B. Contamination of aggregates by contact with the ground shall be positively prevented. The Contractor shall take the necessary measures to prevent contamination. The preventive measures shall include, but are not necessarily limited to, placing aggregates on wooden platforms or on hardened surfaces consisting of portland cement concrete, asphalt concrete, or cement treated material.

In placing aggregates in storage or in moving the aggregates from storage to the weigh hopper of the batching plant, any method that may cause segregation, degradation, or the combining of materials of different gradings that will result in any size of aggregate at the weigh hopper failing to meet the grading requirements, shall be discontinued. Any method of handling aggregates that results in excessive breakage of particles shall be discontinued. The use of suitable devices to reduce impact of falling aggregates may be required by the Engineer.

90-5.02 PROPORTIONING DEVICES

Weighing, measuring, or metering devices used for proportioning materials shall conform to the requirements in Section 9-1.01, "Measurement of Quantities," and this Section 90-5.02. In addition, automatic weighing systems shall comply with the requirements for automatic proportioning devices in Section 90-5.03A, "Proportioning for Pavement." Automatic devices shall be automatic to the extent that the only manual operation required for proportioning the aggregates, cement, and supplementary cementitious material for one batch of concrete is a single operation of a switch or starter.

Proportioning devices shall be tested as frequently as the Engineer may deem necessary to ensure their accuracy.

Weighing equipment shall be insulated against vibration or movement of other operating equipment in the plant. When the plant is in operation, the weight of each batch of material shall not vary from the weight designated by the Engineer by more than the tolerances specified herein.

Equipment for cumulative weighing of aggregate shall have a zero tolerance of ± 0.5 percent of the designated total batch weight of the aggregate. For systems with individual weigh hoppers for the various sizes of aggregate, the zero tolerance shall be ± 0.5 percent of the individual batch weight designated for each size of aggregate. Equipment for cumulative weighing of cement and supplementary cementitious material shall have a zero tolerance of ± 0.5 percent of the designated total batch weight of the cement and supplementary cementitious material. Equipment for weighing cement or supplementary cementitious material separately shall have a zero tolerance of ± 0.5 percent of their designated individual batch weights. Equipment for measuring water shall have a zero tolerance of ± 0.5 percent of its designated weight or volume.

The weight indicated for any batch of material shall not vary from the preselected scale setting by more than the following:

- A. Aggregate weighed cumulatively shall be within 1.0 percent of the designated total batch weight of the aggregate. Aggregates weighed individually shall be within 1.5 percent of their respective designated batch weights; and
- B. Cement shall be 99 to 102 percent of its designated batch weight. When weighed individually, supplementary cementitious material shall be 99 to 102 percent of its designated batch weight. When supplementary cementitious material and cement are permitted to be weighed cumulatively, cement shall be weighed first to 99 to 102 percent of its designated batch weight, and the total for cement and supplementary cementitious material shall be 99 to 102 percent of the sum of their designated batch weights; and
- C. Water shall be within 1.5 percent of its designated weight or volume.

Each scale graduation shall be approximately 0.001 of the total capacity of the scale. The capacity of scales for weighing cement, supplementary cementitious material, or cement plus supplementary cementitious material and aggregates shall not exceed that of commercially available scales having single graduations indicating a weight not exceeding the maximum permissible weight variation above, except that no scale shall be required having a capacity of less than 1,000 pounds, with one pound graduations.

90-5.03 PROPORTIONING

Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cementitious material and water as provided in these specifications. Aggregates shall be proportioned by weight.

At the time of batching, aggregates shall have been dried or drained sufficiently to result in a stable moisture content such that no visible separation of water from aggregate will take place during transportation from the proportioning plant to the point of mixing. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry weight.

Should separate supplies of aggregate material of the same size group, but of different moisture content or specific gravity or surface characteristics affecting workability, be available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another.

Bulk Type IP (MS) cement shall be weighed in an individual hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer.

Bulk cement and supplementary cementitious material may be weighed in separate, individual weigh hoppers or may be weighed in the same weigh hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer. If the cement and supplementary cementitious material are weighed cumulatively, the cement shall be weighed first.

If cement and supplementary cementitious material are weighed in separate weigh hoppers, the weigh systems for the proportioning of the aggregate, the cement, and the supplementary cementitious material shall be individual and distinct from all other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and independent material-weighing device. The cement and the supplementary cementitious material shall be discharged into the mixer simultaneously with the aggregate.

The scales and weigh hoppers for bulk weighing cement, supplementary cementitious material, or cement plus supplementary cementitious material shall be separate and distinct from the aggregate weighing equipment.

For batches of one cubic yard or more, the batching equipment shall conform to one of the following combinations:

- A. Separate boxes and separate scale and indicator for weighing each size of aggregate.
- B. Single box and scale indicator for all aggregates.
- C. Single box or separate boxes and automatic weighing mechanism for all aggregates.

In order to check the accuracy of batch weights, the gross weight and tare weight of batch trucks, truck mixers, truck agitators, and non-agitating hauling equipment shall be determined when ordered by the Engineer. The equipment shall be weighed on scales designated by the Engineer.

90-5.03A Proportioning For Pavement

Aggregates and bulk supplementary cementitious material for use in pavement shall be proportioned by weight by means of automatic proportioning devices of approved type conforming to these specifications.

The Contractor shall install and maintain in operating condition an electronically actuated moisture meter that will indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched within a sensitivity of 0.5 percent by weight of the fine aggregate.

The batching of cement, supplementary cementitious material, or cement plus supplementary cementitious material and aggregate shall be interlocked so that a new batch cannot be started until all weigh hoppers are empty, the proportioning devices are within zero tolerance, and the discharge gates are closed. The interlock shall permit no part of the batch to be discharged until all aggregate hoppers and the cement and supplementary cementitious material hoppers or the cement plus supplementary cementitious material hopper are charged with weights that are within the tolerances specified in Section 90-5.02, "Proportioning Devices."

If interlocks are required for cement and supplementary cementitious material charging mechanisms and cement and supplementary cementitious material are weighed cumulatively, their charging mechanisms shall be interlocked to prevent the introduction of mineral admixture until the weight of cement in the cement weigh hopper is within the tolerances specified in Section 90-5.02, "Proportioning Devices."

If concrete is completely mixed in stationary paving mixers, the supplementary cementitious materials shall be weighed in a separate weigh hopper and the supplementary cementitious material and cement shall be introduced simultaneously into the mixer proportionately with the aggregate. If the Contractor provides certification that the stationary mixer is capable of mixing the cement, supplementary cementitious material, aggregates, and water uniformly before discharge, weighing the supplementary cementitious material cumulatively with the cement is permitted. Certification shall contain the following:

- A. Test results for 2 compressive strength test cylinders of concrete taken within the first one-third and 2 compressive strength test cylinders of concrete taken within the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength";
- B. Calculations demonstrating that the difference in the averages of 2 compressive strengths taken in the first one-third is no greater than 7.5 percent different than the averages of 2 compressive strengths taken in the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;" and
- C. The mixer rotation speed and time of mixing before discharge that are required to produce a mix that meets the requirements above.

The discharge gate on the cement and supplementary cementitious material hoppers or the cement plus supplementary cementitious material hopper shall be designed to permit regulating the flow of cement, supplementary cementitious material, or cement plus supplementary cementitious material into the aggregate as directed by the Engineer.

If separate weigh boxes are used for each size of aggregate, the discharge gates shall permit regulating the flow of each size of aggregate as directed by the Engineer.

Material discharged from the several bins shall be controlled by gates or by mechanical conveyors. The means of withdrawal from the several bins, and of discharge from the weigh box, shall be interlocked so that not more than one bin can discharge at a time, and so that the weigh box cannot be tripped until the required quantity from each of the several bins has been deposited therein. Should a separate weigh box be used for each size of aggregate, all may be operated and discharged simultaneously.

If the discharge from the several bins is controlled by gates, each gate shall be actuated automatically so that the required mass is discharged into the weigh box, after which the gate shall automatically close and lock.

The automatic weighing system shall be designed so that all proportions required may be set on the weighing controller at the same time.

90-6 MIXING AND TRANSPORTING

90-6.01 GENERAL

Concrete shall be mixed in mechanically operated mixers, except that when permitted by the Engineer, batches not exceeding 1/3 cubic yard may be mixed by hand methods in conformance with the provisions in Section 90-6.05, "Hand-Mixing."

Equipment having components made of aluminum or magnesium alloys that would have contact with plastic concrete during mixing, transporting, or pumping of portland cement concrete shall not be used.

Concrete shall be homogeneous and thoroughly mixed, and there shall be no lumps or evidence of undispersed cementitious material.

Uniformity of concrete mixtures will be determined by differences in penetration as determined by California Test 533, or slump as determined by ASTM Designation: C 143, and by variations in the proportion of coarse aggregate as determined by California Test 529.

When the mix design specifies a penetration value, the difference in penetration, determined by comparing penetration tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed 1/2-inch. When the mix design specifies a slump value, the difference in slump, determined by comparing slump tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed the values given in the table below. Variation in the proportion of coarse aggregate will be determined by comparing the results of tests of 2 samples of mixed concrete from the same batch or truck mixer load and the difference between the 2 results shall not exceed 170 pounds per cubic yard of concrete.

Average Slump	Maximum Permissible Difference
Less than 4"	1"
4" to 6"	1 1/2"
Greater than 6" to 9"	2"

The Contractor shall furnish samples of the freshly mixed concrete and provide satisfactory facilities for obtaining the samples.

90-6.02 MACHINE MIXING

Concrete mixers may be of the revolving drum or the revolving blade type, and the mixing drum or blades shall be operated uniformly at the mixing speed recommended by the manufacturer. Mixers and agitators that have an accumulation of hard concrete or mortar shall not be used.

The temperature of mixed concrete, immediately before placing, shall be not less than 50° F or more than 90° F. Aggregates and water shall be heated or cooled as necessary to produce concrete within these temperature limits. Neither aggregates nor mixing water shall be heated to exceed 150° F. If ice is used to cool the concrete, discharge of the mixer will not be permitted until all ice is melted.

The batch shall be so charged into the mixer that some water will enter in advance of cementitious materials and aggregates. All water shall be in the drum by the end of the first one-fourth of the specified mixing time.

Cementitious materials shall be batched and charged into the mixer by means that will not result either in loss of cementitious materials due to the effect of wind, in accumulation of cementitious materials on surfaces of conveyors or hoppers, or in other conditions that reduce or vary the required quantity of cementitious material in the concrete mixture.

Paving and stationary mixers shall be operated with an automatic timing device. The timing device and discharge mechanism shall be interlocked so that during normal operation no part of the batch will be discharged until the specified mixing time has elapsed.

The total elapsed time between the intermingling of damp aggregates and all cementitious materials and the start of mixing shall not exceed 30 minutes.

The size of batch shall not exceed the manufacturer's guaranteed capacity.

When producing concrete for pavement or base, suitable batch counters shall be installed and maintained in good operating condition at job site batching plants and stationary mixers. The batch counters shall indicate the exact number of batches proportioned and mixed.

Concrete shall be mixed and delivered to the job site by means of one of the following combinations of operations:

- A. Mixed completely in a stationary mixer and the mixed concrete transported to the point of delivery in truck agitators or in nonagitating hauling equipment (central-mixed concrete).
- B. Mixed partially in a stationary mixer, and the mixing completed in a truck mixer (shrink-mixed concrete).
- C. Mixed completely in a truck mixer (transit-mixed concrete).
- D. Mixed completely in a paving mixer.

Agitators may be truck mixers operating at agitating speed or truck agitators. Each mixer and agitator shall have attached thereto in a prominent place a metal plate or plates on which is plainly marked the various uses for which the equipment is designed, the manufacturer's guaranteed capacity of the drum or container in terms of the volume of mixed concrete and the speed of rotation of the mixing drum or blades.

Truck mixers shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified.

When shrink-mixed concrete is furnished, concrete that has been partially mixed at a central plant shall be transferred to a truck mixer and all requirements for transit-mixed concrete shall apply. No credit in the number of revolutions at mixing speed will be allowed for partial mixing in a central plant.

90-6.03 TRANSPORTING MIXED CONCRETE

Mixed concrete may be transported to the delivery point in truck agitators or truck mixers operating at the speed designated by the manufacturer of the equipment as agitating speed, or in non-agitating hauling equipment, provided the consistency and workability of the mixed concrete upon discharge at the delivery point is suitable for adequate placement and consolidation in place, and provided the mixed concrete after hauling to the delivery point conforms to the provisions in Section 90-6.01, "General."

Truck agitators shall be loaded not to exceed the manufacturer's guaranteed capacity and shall maintain the mixed concrete in a thoroughly mixed and uniform mass during hauling.

Bodies of nonagitating hauling equipment shall be constructed so that leakage of the concrete mix, or any part thereof, will not occur at any time.

Concrete hauled in open-top vehicles shall be protected during hauling against rain or against exposure to the sun for more than 20 minutes when the ambient temperature exceeds 75° F.

No additional mixing water shall be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer. If the Engineer authorizes additional water to be incorporated into the concrete, the drum shall be revolved not less than 30 revolutions at mixing speed after the water is added and before discharge is commenced.

The rate of discharge of mixed concrete from truck mixer-agitators shall be controlled by the speed of rotation of the drum in the discharge direction with the discharge gate fully open.

If a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be completed within 1.5 hours or before 250 revolutions of the drum or blades, whichever occurs first, after the introduction of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or if the temperature of the concrete is 85° F or above, the time allowed may be less than 1.5 hours. If an admixture is used to retard the set time, the temperature of the concrete shall not exceed 85° F, the time limit shall be 2 hours, and the revolution limitation shall be 300.

If nonagitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be completed within one hour after the addition of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 85° F or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

Each load of concrete delivered at the job site shall be accompanied by a weighmaster certificate showing the mix identification number, nonrepeating load number, date and time at which the materials were batched, the total amount of water added to the load, and for transit-mixed concrete, the reading of the revolution counter at the time the truck mixer is charged with cement. This weighmaster certificate shall also show the actual scale weights (pounds) for the ingredients batched. Theoretical or target batch weights shall not be used as a substitute for actual scale weights.

Weighmaster certificates shall be provided in printed form, or if approved by the Engineer, the data may be submitted in electronic media. Electronic media shall be presented in a tab-delimited format on a 3 1/2-inch diskette with a capacity of at least 1.4 megabytes. Captured data, for the ingredients represented by each batch shall be "line feed, carriage return" (LFCR) and "one line, separate record" with allowances for sufficient fields to satisfy the amount of data required by these specifications.

The Contractor may furnish a weighmaster certificate accompanied by a separate certificate that lists the actual batch weights or measurements for a load of concrete provided that both certificates are imprinted with the same nonrepeating load number that is unique to the contract and delivered to the jobsite with the load.

Weighmaster certificates furnished by the Contractor shall conform to the provisions in Section 9-1.01, "Measurement of Quantities."

90-6.04 TIME OR AMOUNT OF MIXING

Mixing of concrete in paving or stationary mixers shall continue for the required mixing time after all ingredients, except water and admixture, if added with the water, are in the mixing compartment of the mixer before any part of the batch is released. Transfer time in multiple drum mixers shall not be counted as part of the required mixing time.

The required mixing time, in paving or stationary mixers, of concrete used for concrete structures, except minor structures, shall be not less than 90 seconds or more than 5 minutes, except that when directed by the Engineer in writing, the requirements of the following paragraph shall apply.

The required mixing time, in paving or stationary mixers, except as provided in the preceding paragraph, shall be not less than 50 seconds or more than 5 minutes.

The minimum required revolutions at the mixing speed for transit-mixed concrete shall not be less than that recommended by the mixer manufacturer, but in no case shall the number of revolutions be less than that required to consistently produce concrete conforming to the provisions for uniformity in Section 90-6.01, "General."

When a high range water-reducing admixture is added to the concrete at the job site, the total number of revolutions shall not exceed 300.

90-6.05 HAND-MIXING

Hand-mixed concrete shall be made in batches of not more than 1/3 cubic yard and shall be mixed on a watertight, level platform. The proper amount of coarse aggregate shall be measured in measuring boxes and spread on the platform and the fine aggregate shall be spread on this layer, the 2 layers being not more than one foot in total depth. On this mixture shall be spread the dry cementitious materials and the whole mass turned no fewer than 2 times dry; then sufficient clean water shall be added, evenly distributed, and the whole mass again turned no fewer than 3 times, not including placing in the carriers or forms.

90-6.06 AMOUNT OF WATER AND PENETRATION

The amount of water used in concrete mixes shall be regulated so that the penetration of the concrete as determined by California Test 533 or the slump of the concrete as determined by ASTM Designation: C 143 is within the nominal values shown in the following table. When the penetration or slump of the concrete is found to exceed the nominal values listed, the mixture of subsequent batches shall be adjusted to reduce the penetration or slump to a value within the nominal range shown. Batches of concrete with a penetration or slump exceeding the maximum values listed shall not be used in the work. If Type F or Type G chemical admixtures are added to the mix, the penetration requirements shall not apply and the slump shall not exceed 9 inches after the chemical admixtures are added.

Type of Work	Nominal		Maximum	
	Penetration (inches)	Slump (inches)	Penetration (inches)	Slump (inches)
Concrete Pavement	0 - 1	—	1 1/2	—
Non-reinforced concrete facilities	0 - 1 1/2	—	2	—
Reinforced concrete structures				
Sections over 12 inches thick	0 - 1 1/2	—	2 1/2	—
Sections 12 inches thick or less	0 - 2	—	3	—
Concrete placed under water	—	6 - 8	—	9
Cast-in-place concrete piles	2 1/2 - 3 1/2	5 - 7	4	8

The amount of free water used in concrete shall not exceed 310 pounds per cubic yard, plus 20 pounds for each required 100 pounds of cementitious material in excess of 550 pounds per cubic yard.

The term free water is defined as the total water in the mixture minus the water absorbed by the aggregates in reaching a saturated surface-dry condition.

If there are adverse or difficult conditions that affect the placing of concrete, the above specified penetration and free water content limitations may be exceeded providing the Contractor is granted permission by the Engineer in writing to increase the cementitious material content per cubic yard of concrete. The increase in water and cementitious material shall be at a ratio not to exceed 30 pounds of water per added 100 pounds of cementitious material per cubic yard. Full compensation for additional cementitious material and water added under these conditions shall be considered as included in the contract price paid for the concrete work involved and no additional compensation will be allowed therefor.

The equipment for supplying water to the mixer shall be constructed and arranged so that the amount of water added can be measured accurately. Any method of discharging water into the mixer for a batch shall be accurate within 1.5 percent of the quantity of water required to be added to the mix for any position of the mixer. Tanks used to measure water shall be designed so that water cannot enter while water is being discharged into the mixer and discharge into the mixer shall be made rapidly in one operation without dribbling. All equipment shall be arranged so as to permit checking the amount of water delivered by discharging into measured containers.

90-7 CURING CONCRETE

90-7.01 METHODS OF CURING

Newly placed concrete shall be cured by the methods specified in this Section 90-7.01 and the special provisions.

90-7.01A Water Method

The concrete shall be kept continuously wet by the application of water for a minimum curing period of 7 days after the concrete has been placed.

Cotton mats, rugs, carpets, or earth or sand blankets may be used as a curing medium to retain the moisture during the curing period.

If a curing medium consisting of cotton mats, rugs, carpets, polyethylene sheeting, polyethylene sheeting on burlap, or earth or sand blankets is to be used to retain the moisture, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. The moisture from the nozzle shall not be applied under pressure directly upon the concrete and shall not be allowed to accumulate on the concrete in a quantity sufficient to cause a flow or wash the surface. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing media.

At the option of the Contractor, a curing medium consisting of white opaque polyethylene sheeting extruded onto burlap may be used to cure concrete structures. The polyethylene sheeting shall have a minimum thickness of 4-mil, and shall be extruded onto 10-ounce burlap.

At the option of the Contractor, a curing medium consisting of polyethylene sheeting may be used to cure concrete columns. The polyethylene sheeting shall have a minimum thickness of 10-mil achieved in a single layer of material.

If the Contractor chooses to use polyethylene sheeting or polyethylene sheeting on burlap as a curing medium, these media and any joints therein shall be secured as necessary to provide moisture retention and shall be within 3 inches of the concrete at all points along the surface being cured. When these media are used, the temperature of the concrete shall be monitored during curing. If the temperature of the concrete cannot be maintained below 140° F, use of these curing media shall be disallowed.

When concrete bridge decks and flat slabs are to be cured without the use of a curing medium, the entire surface of the bridge deck or slab shall be kept damp by the application of water with an atomizing nozzle as specified above, until the concrete has set, after which the entire surface of the concrete shall be sprinkled continuously with water for a period of not less than 7 days.

90-7.01B Curing Compound Method

Surfaces of the concrete that are exposed to the air shall be sprayed uniformly with a curing compound.

Curing compounds to be used shall be as follows:

1. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B, except the resin type shall be poly-alpha-methylstyrene.
2. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B.
3. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class A.
4. Nonpigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class B.
5. Nonpigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class A.
6. Nonpigmented curing compound with fugitive dye conforming to the requirements in ASTM Designation: C 309, Type 1-D, Class A.

The infrared scan for the dried vehicle from curing compound (1) shall match the infrared scan on file at the Transportation Laboratory.

The loss of water for each type of curing compound, when tested in conformance with the requirements in California Test 534, shall not be more than 0.28-pounds per square yard in 24 hours.

The curing compound to be used will be specified elsewhere in these specifications or in the special provisions.

If the use of curing compound is required or permitted elsewhere in these specifications or in the special provisions and no specific kind is specified, any of the curing compounds listed above may be used.

Curing compound shall be applied at a nominal rate of one gallon per 150 square feet, unless otherwise specified.

At any point, the application rate shall be within ± 50 square feet per gallon of the nominal rate specified, and the average application rate shall be within ± 25 square feet per gallon of the nominal rate specified when tested in conformance with the requirements in California Test 535. Runs, sags, thin areas, skips, or holidays in the applied curing compound shall be evidence that the application is not satisfactory.

Curing compounds shall be applied using power operated spray equipment. The power operated spraying equipment shall be equipped with an operational pressure gage and a means of controlling the pressure. Hand spraying of small and irregular areas that are not reasonably accessible to mechanical spraying equipment, in the opinion of the Engineer, may be permitted.

The curing compound shall be applied to the concrete following the surface finishing operation, immediately before the moisture sheen disappears from the surface, but before any drying shrinkage or craze cracks begin to appear. In the event of any drying or cracking of the surface, application of water with an atomizing nozzle as specified in Section 90-7.01A, "Water Method," shall be started immediately and shall be continued until application of the compound is resumed or started; however, the compound shall not be applied over any resulting freestanding water. Should the film of compound be damaged from any cause before the expiration of 7 days after the concrete is placed in the case of structures and 72 hours in the case of pavement, the damaged portion shall be repaired immediately with additional compound.

At the time of use, compounds containing pigments shall be in a thoroughly mixed condition with the pigment uniformly dispersed throughout the vehicle. A paddle shall be used to loosen all settled pigment from the bottom of the container, and a power driven agitator shall be used to disperse the pigment uniformly throughout the vehicle.

Agitation shall not introduce air or other foreign substance into the curing compound.

The manufacturer shall include in the curing compound the necessary additives for control of sagging, pigment settling, leveling, de-emulsification, or other requisite qualities of a satisfactory working material. Pigmented curing compounds shall be manufactured so that the pigment does not settle badly, does not cake or thicken in the container, and does not become granular or curdled. Settlement of pigment shall be a thoroughly wetted, soft, mushy mass permitting the complete and easy vertical penetration of a paddle. Settled pigment shall be easily redispersed, with minimum resistance to the sideways manual motion of the paddle across the bottom of the container, to form a smooth uniform product of the proper consistency.

Curing compounds shall remain sprayable at temperatures above 40° F and shall not be diluted or altered after manufacture.

The curing compound shall be packaged in clean 274-gallon totes, 55-gallon barrels or 5-gallon pails shall be supplied from a suitable storage tank located at the jobsite. The containers shall comply with "Title 49, Code of Federal Regulations, Hazardous Materials Regulations." The 274-gallon totes and the 55-gallon barrels shall have removable lids and airtight fasteners. The 5-gallon pails shall be round and have standard full open head and bail. Lids with bungholes will not be permitted. Settling or separation of solids in containers, except tanks, must be completely redispersed with low speed mixing prior to use, in conformance with these specifications and the manufacturer's recommendations. Mixing shall be accomplished either manually by use of a paddle or by use of a mixing blade driven by a drill motor, at low speed. Mixing blades shall be the type used for mixing paint. On-site storage tanks shall be kept clean and free of contaminants. Each tank shall have a permanent system designed to completely redisperse settled material without introducing air or other foreign substances.

Steel containers and lids shall be lined with a coating that will prevent destructive action by the compound or chemical agents in the air space above the compound. The coating shall not come off the container or lid as skins. Containers shall be filled in a manner that will prevent skinning. Plastic containers shall not react with the compound.

Each container shall be labeled with the manufacturer's name, kind of curing compound, batch number, volume, date of manufacture, and volatile organic compound (VOC) content. The label shall also warn that the curing compound containing pigment shall be well stirred before use. Precautions concerning the handling and the application of curing compound shall be shown on the label of the curing compound containers in conformance with the Construction Safety Orders and General Industry Safety Orders of the State.

Containers of curing compound shall be labeled to indicate that the contents fully comply with the rules and regulations concerning air pollution control in the State.

When the curing compound is shipped in tanks or tank trucks, a shipping invoice shall accompany each load. The invoice shall contain the same information as that required herein for container labels.

Curing compound will be sampled by the Engineer at the source of supply, at the job site, or at both locations.

Curing compound shall be formulated so as to maintain the specified properties for a minimum of one year. The Engineer may require additional testing before use to determine compliance with these specifications if the compound has not been used within one year or whenever the Engineer has reason to believe the compound is no longer satisfactory.

Tests will be conducted in conformance with the latest ASTM test methods and methods in use by the Transportation Laboratory.

90-7.01C Waterproof Membrane Method

The exposed finished surfaces of concrete shall be sprayed with water, using a nozzle that so atomizes the flow that a mist and not a spray is formed, until the concrete has set, after which the curing membrane, shall be placed. The curing membrane shall remain in place for a period of not less than 72 hours.

Sheeting material for curing concrete shall conform to the requirements in AASHTO Designation: M 171 for white reflective materials.

The sheeting material shall be fabricated into sheets of such width as to provide a complete cover for the entire concrete surface. Joints in the sheets shall be securely cemented together in such a manner as to provide a waterproof joint. The joint seams shall have a minimum lap of 0.33-foot.

The sheets shall be securely weighted down by placing a bank of earth on the edges of the sheets or by other means satisfactory to the Engineer.

Should any portion of the sheets be broken or damaged before the expiration of 72 hours after being placed, the broken or damaged portions shall be immediately repaired with new sheets properly cemented into place.

Sections of membrane that have lost their waterproof qualities or have been damaged to such an extent as to render them unfit for curing the concrete shall not be used.

90-7.01D Forms-In-Place Method

Formed surfaces of concrete may be cured by retaining the forms in place. The forms shall remain in place for a minimum period of 7 days after the concrete has been placed, except that for members over 20 inches in least dimension the forms shall remain in place for a minimum period of 5 days.

Joints in the forms and the joints between the end of forms and concrete shall be kept moisture tight during the curing period. Cracks in the forms and cracks between the forms and the concrete shall be resealed by methods subject to the approval of the Engineer.

90-7.02 CURING PAVEMENT

The entire exposed area of the pavement, including edges, shall be cured by the waterproof membrane method, or curing compound method using curing compound (1) or (2) as the Contractor may elect. Should the side forms be removed before the expiration of 72 hours following the start of curing, the exposed pavement edges shall also be cured. If the pavement is cured by means of the curing compound method, the sawcut and all portions of the curing compound that have been disturbed by sawing operations shall be restored by spraying with additional curing compound.

Curing shall commence as soon as the finishing process provided in Section 40-1.10, "Final Finishing," has been completed. The method selected shall conform to the provisions in Section 90-7.01, "Methods of Curing."

When the curing compound method is used, the compound shall be applied to the entire pavement surface by mechanical sprayers. Spraying equipment shall be of the fully atomizing type equipped with a tank agitator that provides for continual agitation of the curing compound during the time of application. The spray shall be adequately protected against wind, and the nozzles shall be so oriented or moved mechanically transversely as to result in the minimum specified rate of coverage being applied uniformly on exposed faces. Hand spraying of small and irregular areas, and areas inaccessible to mechanical spraying equipment, in the opinion of the Engineer, will be permitted. When the ambient air temperature is above 60° F, the Contractor shall fog the surface of the concrete with a fine spray of water as specified in Section 90-7.01A, "Water Method." The surface of the pavement shall be kept moist between the hours of 10:00 a.m. and 4:30 p.m. on the day the concrete is placed. However, the fogging done after the curing compound has been applied shall not begin until the compound has set sufficiently to prevent displacement. Fogging shall be discontinued if ordered in writing by the Engineer.

90-7.03 CURING STRUCTURES

Newly placed concrete for cast-in-place structures, other than highway bridge decks, shall be cured by the water method, the forms-in-place method, or, as permitted herein, by the curing compound method, in conformance with the provisions in Section 90-7.01, "Methods of Curing."

The curing compound method using a pigmented curing compound may be used on concrete surfaces of construction joints, surfaces that are to be buried underground, and surfaces where only ordinary surface finish is to be applied and on which a uniform color is not required and that will not be visible from a public traveled way. If the Contractor elects to use the curing compound method on the bottom slab of box girder spans, the curing compound shall be curing compound (1).

The top surface of highway bridge decks shall be cured by both the curing compound method and the water method. The curing compound shall be curing compound (1).

Concrete surfaces of minor structures, as defined in Section 51-1.02, "Minor Structures," shall be cured by the water method, the forms-in-place method or the curing compound method.

When deemed necessary by the Engineer during periods of hot weather, water shall be applied to concrete surfaces being cured by the curing compound method or by the forms-in-place method, until the Engineer determines that a cooling effect is no longer required. Application of water for this purpose will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

90-7.04 CURING PRECAST CONCRETE MEMBERS

Precast concrete members shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing." Curing shall be provided for the minimum time specified for each method or until the concrete reaches its design strength, whichever is less. Steam curing may also be used for precast members and shall conform to the following provisions:

- A. After placement of the concrete, members shall be held for a minimum 4-hour presteaming period. If the ambient air temperature is below 50° F, steam shall be applied during the presteaming period to hold the air surrounding the member at a temperature between 50° F and 90° F.
- B. To prevent moisture loss on exposed surfaces during the presteaming period, members shall be covered as soon as possible after casting or the exposed surfaces shall be kept wet by fog spray or wet blankets.
- C. Enclosures for steam curing shall allow free circulation of steam about the member and shall be constructed to contain the live steam with a minimum moisture loss. The use of tarpaulins or similar flexible covers will be permitted, provided they are kept in good repair and secured in such a manner as to prevent the loss of steam and moisture.
- D. Steam at the jets shall be at low pressure and in a saturated condition. Steam jets shall not impinge directly on the concrete, test cylinders, or forms. During application of the steam, the temperature rise within the enclosure shall not exceed 40° F per hour. The curing temperature throughout the enclosure shall not exceed 150° F and shall be maintained at a constant level for a sufficient time necessary to develop the required transfer strength. Control cylinders shall be covered to prevent moisture loss and shall be placed in a location where temperature is representative of the average temperature of the enclosure.
- E. Temperature recording devices that will provide an accurate, continuous, permanent record of the curing temperature shall be provided. A minimum of one temperature recording device per 200 feet of continuous bed length will be required for checking temperature.
- F. Members in pretension beds shall be detensioned immediately after the termination of steam curing while the concrete and forms are still warm, or the temperature under the enclosure shall be maintained above 60° F until the stress is transferred to the concrete.
- G. Curing of precast concrete will be considered completed after termination of the steam curing cycle.

90-7.05 CURING PRECAST PRESTRESSED CONCRETE PILES

Newly placed concrete for precast prestressed concrete piles shall be cured in conformance with the provisions in Section 90-7.04, "Curing Precast Concrete Members," except that piles in a corrosive environment shall be cured as follows:

- A. Piles shall be either steam cured or water cured. If water curing is used, the piles shall be kept continuously wet by the application of water in conformance with the provisions in Section 90-7.01A, "Water Method."
- B. If steam curing is used, the steam curing provisions in Section 90-7.04, "Curing Precast Concrete Members," shall apply except that the piles shall be kept continuously wet for their entire length for a period of not less than 3 days, including the holding and steam curing periods.

90-7.06 CURING SLOPE PROTECTION

Concrete slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

Concreted-rock slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing," with a blanket of earth kept wet for 72 hours, or by sprinkling with a fine spray of water every 2 hours during the daytime for a period of 3 days.

90-7.07 CURING MISCELLANEOUS CONCRETE WORK

Exposed surfaces of curbs shall be cured by pigmented curing compounds as specified in Section 90-7.01B, "Curing Compound Method."

Concrete sidewalks, gutter depressions, island paving, curb ramps, driveways, and other miscellaneous concrete areas shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

Shotcrete shall be cured for at least 72 hours by spraying with water, by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

Mortar and grout shall be cured by keeping the surface damp for 3 days.

After placing, the exposed surfaces of sign structure foundations, including pedestal portions, if constructed, shall be cured for at least 72 hours by spraying with water, by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

90-8 PROTECTING CONCRETE

90-8.01 GENERAL

In addition to the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," the Contractor shall protect concrete as provided in this Section 90-8. If required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

The Contractor shall protect concrete from damage from any cause, which shall include, but not be limited to: rain, heat, cold, wind, Contractor's actions, and actions of others.

Concrete shall not be placed on frozen or ice-coated ground or subgrade nor on ice-coated forms, reinforcing steel, structural steel, conduits, precast members, or construction joints.

Under rainy conditions, placing of concrete shall be stopped before the quantity of surface water is sufficient to damage surface mortar or cause a flow or wash of the concrete surface, unless the Contractor provides adequate protection against damage.

Concrete that has been frozen or damaged by other causes, as determined by the Engineer, shall be removed and replaced by the Contractor at the Contractor's expense.

90-8.02 PROTECTING CONCRETE STRUCTURES

Structure concrete and shotcrete used as structure concrete shall be maintained at a temperature of not less than 45° F for 72 hours after placing and at not less than 40° F for an additional 4 days.

90-8.03 PROTECTING CONCRETE PAVEMENT

Pavement concrete shall be maintained at a temperature of not less than 40° F for 72 hours.

Except as provided in Section 7-1.08, "Public Convenience," the Contractor shall protect concrete pavement against construction and other activities that abrade, scar, discolor, reduce texture depth, lower coefficient of friction, or otherwise damage the surface. Stockpiling, drifting, or excessive spillage of soil, gravel, petroleum products, and concrete or asphalt mixes on the surface of concrete pavement is prohibited unless otherwise specified in these specifications, the special provisions or permitted by the Engineer.

If ordered by the Engineer or shown on the plans or specified in the special provisions, pavement crossings shall be constructed for the convenience of public traffic. The material and work necessary for the construction of the crossings, and their subsequent removal and disposal, will be paid for at the contract unit prices for the items of work involved and if there are no contract items for the work involved, payment for pavement crossings will be made by extra work as provided in Section 4-1.03D, "Extra Work.". Where public traffic will be required to cross over the new pavement, Type III portland cement may be used in concrete, if permitted in writing by the Engineer. The pavement may be opened to traffic as soon as the concrete has developed a modulus of rupture of 550 pounds per square inch. The modulus of rupture will be determined by California Test 523.

No traffic or Contractor's equipment, except as hereinafter provided, will be permitted on the pavement before a period of 10 days has elapsed after the concrete has been placed, nor before the concrete has developed a modulus of rupture of at least 550 pounds per square inch. Concrete that fails to attain a modulus of rupture of 550 pounds per square inch within 10 days shall not be opened to traffic until directed by the Engineer.

Equipment for sawing weakened plane joints will be permitted on the pavement as specified in Section 40-1.08B, "Weakened Plane Joints."

When requested in writing by the Contractor, the tracks on one side of paving equipment will be permitted on the pavement after a modulus of rupture of 350 pounds per square inch has been attained, provided that:

- A. Unit pressure exerted on the pavement by the paver shall not exceed 20 pounds per square inch;
- B. Tracks with cleats, grousers, or similar protuberances shall be modified or shall travel on planks or equivalent protective material, so that the pavement is not damaged; and
- C. No part of the track shall be closer than one foot from the edge of pavement.

In case of visible cracking of, or other damage to the pavement, operation of the paving equipment on the pavement shall be immediately discontinued.

Damage to the pavement resulting from early use of pavement by the Contractor's equipment as provided above shall be repaired by the Contractor.

The State will furnish the molds and machines for testing the concrete for modulus of rupture, and the Contractor, at the Contractor's expense, shall furnish the material and whatever labor the Engineer may require.

90-9 COMPRESSIVE STRENGTH

90-9.01 GENERAL

Concrete compressive strength requirements consist of a minimum strength that shall be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or the special provisions or are shown on the plans.

The compressive strength of concrete will be determined from test cylinders that have been fabricated from concrete sampled in conformance with the requirements of California Test 539. Test cylinders will be molded and initially field cured in conformance with California Test 540. Test cylinders will be cured and tested after receipt at the testing laboratory in conformance with the requirements of California Test 521. A strength test shall consist of the average strength of 2 cylinders fabricated from material taken from a single load of concrete, except that, if any cylinder should show evidence of improper sampling, molding, or testing, that cylinder shall be discarded and the strength test shall consist of the strength of the remaining cylinder.

When concrete compressive strength is specified as a prerequisite to applying loads or stresses to a concrete structure or member, test cylinders for other than steam cured concrete will be cured in conformance with Method 1 of California Test 540. The compressive strength of concrete determined for these purposes will be evaluated on the basis of individual tests.

When concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete strength to be used as a basis for acceptance of other than steam cured concrete will be determined from cylinders cured in conformance with Method 1 of California Test 540. If the result of a single compressive strength test at the maximum age specified or allowed is below the specified strength but is 95 percent or more of the specified strength, the Contractor shall make corrective changes, subject to approval of the Engineer, in the mix proportions or in the concrete fabrication procedures, before placing additional concrete, and shall pay to the State \$10 for each in-place cubic yard of concrete represented by the deficient test. If the result of a single compressive strength test at the maximum age specified or allowed is below 95 percent of the specified strength, but is 85 percent or more of the specified strength, the Contractor shall make the corrective changes specified above, and shall pay to the State \$15 for each in-place cubic yard of concrete represented by the deficient test. In addition, such corrective changes shall be made when the compressive strength of concrete tested at 7 days indicates, in the judgment of the Engineer, that the concrete will not attain the required compressive strength at the maximum age specified or allowed. Concrete represented by a single test that indicates a compressive strength of less than 85 percent of the specified 28-day compressive strength will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials."

If the test result indicates that the compressive strength at the maximum curing age specified or allowed is below the specified strength, but is 85 percent or more of the specified strength, payments to the State as required above shall be made, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength of the concrete placed in the work meets or exceeds the specified 28-day compressive strength. If the test result indicates a compressive strength at the maximum curing age specified or allowed below 85 percent, the concrete represented by that test will be rejected, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength and quality of the concrete placed in the work are acceptable. If the evidence consists of tests made on cores taken from the work, the cores shall be obtained and tested in conformance with the requirements in ASTM Designation: C 42.

No single compressive strength test shall represent more than 320 cubic yards.

If a precast concrete member is steam cured, the compressive strength of the concrete will be determined from test cylinders that have been handled and stored in conformance with Method 3 of California Test 540. The compressive strength of steam cured concrete will be evaluated on the basis of individual tests representing specific portions of production. If the concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete shall be considered to be acceptable whenever its compressive strength reaches the specified 28-day compressive strength provided that strength is reached in not more than the maximum number of days specified or allowed after the member is cast.

When concrete is specified by compressive strength, prequalification of materials, mix proportions, mixing equipment, and procedures proposed for use will be required prior to placement of the concrete. Prequalification shall be accomplished by the submission of acceptable certified test data or trial batch reports by the Contractor. Prequalification data shall be based on the use of materials, mix proportions, mixing equipment, procedures, and size of batch proposed for use in the work.

Certified test data, in order to be acceptable, shall indicate that not less than 90 percent of at least 20 consecutive tests exceed the specified strength at the maximum number of cure days specified or allowed, and none of those tests are less than 95 percent of specified strength. Strength tests included in the data shall be the most recent tests made on concrete of the proposed mix design and all shall have been made within one year of the proposed use of the concrete.

Trial batch test reports, in order to be acceptable, shall indicate that the average compressive strength of 5 consecutive concrete cylinders, taken from a single batch, at not more than 28 days (or the maximum age allowed) after molding shall be at least 580 pounds per square inch greater than the specified 28-day compressive strength, and no individual cylinder shall have a strength less than the specified strength at the maximum age specified or allowed. Data contained in the report shall be from trial batches that were produced within one year of the proposed use of specified strength concrete in the project. Whenever air-entrainment is required, the air content of trial batches shall be equal to or greater than the air content specified for the concrete without reduction due to tolerances.

Tests shall be performed in conformance with either the appropriate California Test methods or the comparable ASTM test methods. Equipment employed in testing shall be in good condition and shall be properly calibrated. If the tests are performed during the life of the contract, the Engineer shall be notified sufficiently in advance of performing the tests in order to witness the test procedures.

The certified test data and trial batch test reports shall include the following information:

- A. Date of mixing.
- B. Mixing equipment and procedures used.
- C. The size of batch in cubic yards and the weight, type, and source of all ingredients used.
- D. Penetration or slump (if the concrete will be placed under water or placed in cast-in-place concrete piles) of the concrete.
- E. The air content of the concrete if an air-entraining admixture is used.
- F. The age at time of testing and strength of all concrete cylinders tested.

Certified test data and trial batch test reports shall be signed by an official of the firm that performed the tests.

When approved by the Engineer, concrete from trial batches may be used in the work at locations where concrete of a lower quality is required and the concrete will be paid for as the type or class of concrete required at that location.

After materials, mix proportions, mixing equipment, and procedures for concrete have been prequalified for use, additional prequalification by testing of trial batches will be required prior to making changes that, in the judgment of the Engineer, could result in a strength of concrete below that specified.

The Contractor's attention is directed to the time required to test trial batches and the Contractor shall be responsible for production of trial batches at a sufficiently early date so that the progress of the work is not delayed.

When precast concrete members are manufactured at the plant of an established manufacturer of precast concrete members, the mix proportions of the concrete shall be determined by the Contractor, and a trial batch and prequalification of the materials, mix proportions, mixing equipment, and procedures will not be required.

90-10 MINOR CONCRETE

90-10.01 GENERAL

Concrete for minor structures, slope paving, curbs, sidewalks and other concrete work, when designated as minor concrete on the plans, in the specifications, or in the contract item, shall conform to the provisions specified herein.

The Engineer, at the Engineer's discretion, will inspect and test the facilities, materials and methods for producing the concrete to ensure that minor concrete of the quality suitable for use in the work is obtained.

90-10.02 MATERIALS

Minor concrete shall conform to the following requirements:

90-10.02A Cementitious Material

Cementitious material shall conform to the provisions in Section 90-1.01, "Description."

90-10.02B Aggregate

Aggregate shall be clean and free from deleterious coatings, clay balls, roots, and other extraneous materials.

Use of crushed concrete or reclaimed aggregate is acceptable only if the aggregate satisfies all aggregate requirements.

The Contractor shall submit to the Engineer for approval, a grading of the combined aggregate proposed for use in the minor concrete. After acceptance of the grading, aggregate furnished for minor concrete shall conform to that grading, unless a change is authorized in writing by the Engineer.

The Engineer may require the Contractor to furnish periodic test reports of the aggregate grading furnished. The maximum size of aggregate used shall be at the option of the Contractor, but in no case shall the maximum size be larger than 1 1/2-inch or smaller than 3/4-inch.

The Engineer may waive, in writing, the gradation requirements in this Section 90-10.02B, if, in the Engineer's opinion, the furnishing of the gradation is not necessary for the type or amount of concrete work to be constructed.

90-10.02C Water

Water used for washing, mixing, and curing shall be free from oil, salts, and other impurities that would discolor or etch the surface or have an adverse affect on the quality of the concrete.

90-10.02D Admixtures

The use of admixtures shall conform to the provisions in Section 90-4, "Admixtures."

90-10.03 PRODUCTION

Cementitious material, water, aggregate, and admixtures shall be stored, proportioned, mixed, transported, and discharged in conformance with recognized standards of good practice that will result in concrete that is thoroughly and uniformly mixed, that is suitable for the use intended, and that conforms to requirements specified herein. Recognized standards of good practice are outlined in various industry publications such as are issued by American Concrete Institute, AASHTO, or the Department.

The cementitious material content of minor concrete shall conform to the provisions in Section 90-1.01, "Description."

The amount of water used shall result in a consistency of concrete conforming to the provisions in Section 90-6.06, "Amount of Water and Penetration." Additional mixing water shall not be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer.

Discharge of ready-mixed concrete from the transporting vehicle shall be made while the concrete is still plastic and before stiffening occurs. An elapsed time of 1.5 hours (one hour in non-agitating hauling equipment), or more than 250 revolutions of the drum or blades, after the introduction of the cementitious material to the aggregates, or a temperature of concrete of more than 90° F will be considered conditions contributing to the quick stiffening of concrete. The Contractor shall take whatever action is necessary to eliminate quick stiffening, except that the addition of water will not be permitted.

The required mixing time in stationary mixers shall be not less than 50 seconds or more than 5 minutes.

The minimum required revolutions at mixing speed for transit-mixed concrete shall be not less than that recommended by the mixer manufacturer, and shall be increased, if necessary, to produce thoroughly and uniformly mixed concrete.

When a high range water-reducing admixture is added to the concrete at the job site, the total number of revolutions shall not exceed 300.

Each load of ready-mixed concrete shall be accompanied by a weighmaster certificate that shall be delivered to the Engineer at the discharge location of the concrete, unless otherwise directed by the Engineer. The weighmaster certificate shall be clearly marked with the date and time of day when the load left the batching plant and, if hauled in truck mixers or agitators, the time the mixing cycle started.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished to the Engineer, prior to placing minor concrete from a source not previously used on the contract, stating that minor concrete to be furnished meets contract requirements, including minimum cementitious material content specified.

90-10.04 CURING MINOR CONCRETE

Curing minor concrete shall conform to the provisions in Section 90-7, "Curing Concrete."

90-10.05 PROTECTING MINOR CONCRETE

Protecting minor concrete shall conform to the provisions in Section 90-8, "Protecting Concrete," except the concrete shall be maintained at a temperature of not less than 40° F for 72 hours after placing.

90-10.06 MEASUREMENT AND PAYMENT

Minor concrete will be measured and paid for in conformance with the provisions specified in the various sections of these specifications covering concrete construction when minor concrete is specified in the specifications, shown on the plans, or indicated by contract item in the Engineer's Estimate.

90-11 MEASUREMENT AND PAYMENT

90-11.01 MEASUREMENT

Portland cement concrete will be measured in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.

For concrete measured at the mixer, the volume in cubic feet shall be computed as the total weight of the batch in pounds divided by the density of the concrete in pounds per cubic foot. The total weight of the batch shall be calculated as the sum of all materials, including water, entering the batch. The density of the concrete will be determined in conformance with the requirements in California Test 518.

90-11.02 PAYMENT

Portland cement concrete will be paid for in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.

Performance Graded Asphalt Binder

Property	AASHTO Test Method	Specification				
		Grade				
		PG 58-22 ^a	PG 64-10	PG 64-16	PG 64-28	PG 70-10
Original Binder						
Flash Point, Minimum °C	T 48	230	230	230	230	230
Solubility, Minimum % ^b	T 44	99	99	99	99	99
Viscosity at 135°C, ^c Maximum, Pa·s	T 316	3.0	3.0	3.0	3.0	3.0
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 1.00	64 1.00	64 1.00	64 1.00	70 1.00
RTFO Test, ^e Mass Loss, Maximum, %	T 240	1.00	1.00	1.00	1.00	1.00
RTFO Test Aged Binder						
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 2.20	64 2.20	64 2.20	64 2.20	70 2.20
Ductility at 25°C Minimum, cm	T 51	75	75	75	75	75
PAV ^f Aging, Temperature, °C	R 28	100	100	100	100	110
RTFO Test and PAV Aged Binder						
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum G*/sin(delta), kPa	T 315	22 ^d 5000	31 ^d 5000	28 ^d 5000	22 ^d 5000	34 ^d 5000
Creep Stiffness, Test Temperature, °C Maximum S-value, Mpa Minimum M-value	T 313	-12 300 0.300	0 300 0.300	-6 300 0.300	-18 300 0.300	0 300 0.300

Notes:

- Use as asphalt rubber base stock for high mountain and high desert area.
- The Engineer waives this specification if the supplier is a Quality Supplier as defined by the Department's "Certification Program for Suppliers of Asphalt."
- The Engineer waives this specification if the supplier certifies the asphalt binder can be adequately pumped and mixed at temperatures meeting applicable safety standards.
- Test the sample at 3°C higher if it fails at the specified test temperature. G*/sin(delta) remains 5000 kPa maximum.
- "RTFO Test" means the asphaltic residue obtained using the Rolling Thin Film Oven Test, AASHTO Test Method T 240 or ASTM Designation: D 2872. The residue from mass change determination may be used for other tests.
- "PAV" means Pressurized Aging Vessel.

Performance graded polymer modified asphalt binder (PG Polymer Modified) is:

Performance Graded Polymer Modified Asphalt Binder ^a

Property	AASHTO Test Method	Specification Grade		
		PG 58-34 PM	PG 64-28 PM	PG 76-22 PM
Original Binder				
Flash Point, Minimum °C	T 48	230	230	230
Solubility, Minimum % ^b	T 44 ^c	98.5	98.5	98.5
Viscosity at 135°C, ^d Maximum, Pa·s	T 316	3.0	3.0	3.0
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 1.00	64 1.00	76 1.00
RTFO Test , Mass Loss, Maximum, %	T 240	1.00	1.00	1.00
RTFO Test Aged Binder				
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 2.20	64 2.20	76 2.20
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum (delta), %	T 315	Note e 80	Note e 80	Note e 80
Elastic Recovery ^f , Test Temp., °C Minimum recovery, %	T 301	25 75	25 75	25 65
PAV ^g Aging, Temperature, °C	R 28	100	100	110
RTFO Test and PAV Aged Binder				
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum G*/sin(delta), kPa	T 315	16 5000	22 5000	31 5000
Creep Stiffness, Test Temperature, °C Maximum S-value, MPa Minimum M-value	T 313	-24 300 0.300	-18 300 0.300	-12 300 0.300

Notes:

- a. Do not modify PG Polymer Modified using acid modification.
- b. The Engineer waives this specification if the supplier is a Quality Supplier as defined by the Department's "Certification Program for Suppliers of Asphalt."
- c. The Department allows ASTM D 5546 instead of AASHTO T 44
- d. The Engineer waives this specification if the supplier certifies the asphalt binder can be adequately pumped and mixed at temperatures meeting applicable safety standards.
- e. Test temperature is the temperature at which G*/sin(delta) is 2.2 kPa. A graph of log G*/sin(delta) plotted against temperature may be used to determine the test temperature when G*/sin(delta) is 2.2 kPa. A graph of (delta) versus temperature may be used to determine delta at the temperature when G*/sin(delta) is 2.2 kPa. The Engineer also accepts direct measurement of (delta) at the temperature when G*/sin(delta) is 2.2 kPa.
- f. Tests without a force ductility clamp may be performed.
- g. "PAV" means Pressurized Aging Vessel.

SAMPLING

Provide a sampling device in the asphalt feed line connecting the plant storage tanks to the asphalt weighing system or spray bar. Make the sampling device accessible between 24 and 30 inches above the platform. Provide a receptacle for flushing the sampling device.

Include with the sampling device a valve:

