

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

TTY 711

*Flex your power!
Be energy efficient!*

March 9, 2012

10-Ama-88-0.0/5.5

10-264444

Project ID 1000000378

ACNH-P088(058)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN AMADOR COUNTY ABOUT 7 MILES EAST OF CLEMENTS FROM SAN JOAQUIN COUNTY LINE TO ROUTE 124.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Tuesday, March 20, 2012.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, the Bid book and the Federal Minimum Wages with Modification Number 4 dated 03/02/12.

Project Plan Sheets 8, 19, 41, 151 and 153 are revised. Copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 05-1.165, "NONHIGHWAY FACILITIES (INCLUDING UTILITIES)," is added as attached.

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the third paragraph is revised as follows:

"A first order of work shall be to install fence (Type WM, Metal Post)."

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the first sentence of the fifth paragraph is revised as follows:

"No work in the Jackson Creek and Jackson Creek Overflow can begin until June 1, 2012."

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the following paragraph is added after the fifth paragraph:

"No blasting shall be allowed. Hydraulic splitters, pneumatic hammers or other roadway excavation techniques approved by the Engineer shall be used to fracture rock and construct stable final rock cut faces."

Addendum No. 1
Page 2
March 9, 2012

10-Ama-88-0.0/5.5
10-264444
Project ID 1000000378
ACNH-P088(058)E

In the Bid book, in the "Bid Item List," Item 55 is revised, as attached.

To Bid book holders:

Replace page 5 of the "Bid Item List" in the Bid book with the attached revised page 5 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This addendum, attachments and the modified wage rates are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/10/10-264444

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



REBECCA D. HARNAGEL
Chief, Office of Plans, Specifications & Estimates
Office Engineer
Division of Engineering Services

Attachments

5-1.165 NONHIGHWAY FACILITIES (INCLUDING UTILITIES)

The utility owner will relocate a utility shown in the following table before the corresponding date shown:

Utility Relocation and Date of the Relocation

Utility	Location	Date
PG&E (OH Electrical Lines)	Sta. 218+00 to 375+00 Lt	July 31, 2012
AT&T (OH Fiber and Telephone Lines)	Sta. 218+00 to 375+00 Lt	August 31, 2012
Jackson Valley Irrigation District (3" UG Water Line	Sta. 331+00 to 353+00 Lt	September 30, 2012

BID ITEM LIST

10-264444

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41	152390	RELOCATE ROADSIDE SIGN	EA	4		
42	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	33,200		
43	155230	CONCRETE INVERT PAVING	CY	56		
44	157550	BRIDGE REMOVAL	LS	LUMP SUM	LUMP SUM	
45	157560	BRIDGE REMOVAL (PORTION)	LS	LUMP SUM	LUMP SUM	
46	160101	CLEARING AND GRUBBING	LS	LUMP SUM	LUMP SUM	
47	190101	ROADWAY EXCAVATION	CY	26,300		
48	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
49 (F)	192003	STRUCTURE EXCAVATION (BRIDGE)	CY	313		
50	192037	STRUCTURE EXCAVATION (RETAINING WALL)	CY	2,160		
51 (F)	193003	STRUCTURE BACKFILL (BRIDGE)	CY	195		
52	193013	STRUCTURE BACKFILL (RETAINING WALL)	CY	1,200		
53	194001	DITCH EXCAVATION	CY	1,400		
54	198001	IMPORTED BORROW (CY)	CY	6,980		
55	198007	IMPORTED MATERIAL (SHOULDER BACKING)	TON	970		
56	203026	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	10		
57	203029	EROSION CONTROL (POLYMER STABILIZED FIBER MATRIX) (SQFT)	SQFT	297,000		
58	260201	CLASS 2 AGGREGATE BASE	CY	400		
59	390131	HOT MIX ASPHALT	TON	30,900		
60	390140	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TON	18,600		