

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER, MS 43
1727 30TH STREET
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
TTY 711



*Flex your power!
Be energy efficient!*

July 9, 2010

12-Ora-57-18.4/20.9
12-0F0324
Project ID 1200000108

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN ORANGE COUNTY IN FULLERTON AND BREA FROM 0.1 MILE NORTH OF YORBA LINDA BOULEVARD OVERCROSSING TO LAMBERT ROAD UNDERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, July 15, 2010.

This addendum is being issued to revise the Notice to Bidders and Special Provisions, the Bid book, and provide a copy of the Information Handout.

In the Special Provisions, Section 4, "BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES," is replaced as attached.

In the Special Provisions, Section 10-1.015, "CONTRACTOR SUPPLIED BIOLOGIST," is added as attached.

In the Special Provisions, Section 10-1.35, "TIEBACK WALL EARTHWORK," the fifth paragraph is revised as follows:

"Should the Engineer fail to complete the review within 3 weeks and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in working drawings and construction sequence plan review for the retaining wall, the delay will be considered a right of way delay as specified in Section 8-1.09, "Right of Way Delays.""

In the Special Provisions, Section 10-1.35, "TIEBACK WALL EARTHWORK," subsection "MEASUREMENT AND PAYMENTS," the second and third paragraphs are revised as follows:

"Full compensation for working drawings and supplements, and shoring, if required, for tieback wall construction shall be considered as included in the contract price paid per cubic yard for structure excavation (tieback wall) and no additional compensation will be allowed therefor.

Addendum No. 3
Page 2
July 9, 2010

12-Ora-57-18.4/20.9
12-0F0324
Project ID 1200000108

Full compensation for shotcrete used to fill voids created by the removal of cobbles and boulders or other obstructions shall be considered as included in the contract price paid per cubic yard for shotcrete and no additional compensation will be allowed therefor."

In the Bid book, in the "Bid Item List," Items 231 and 232 are added and Item 230 is deleted as attached.

To Bid book holders:

Replace page 14 of the "Bid Item List" in the Bid book with the attached revised page 14 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Attached is a copy of the Information Handout "Retaining Wall Foundation Report – SR-57 Northbound Widening (Northern Segment) Retaining Walls and Sound Walls, Orange County, California" dated May 18, 2010.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This addendum, and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/12/12-0F0324

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

IGNACIO SANCHEZ DEL REAL
Acting Office Chief
Office of Plans, Specifications & Estimates
Office Engineer
Division of Engineering Services

Attachments

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION, AND LIQUIDATED DAMAGES

The 1st working day is the 55th day after contract approval.

Do not start work at the job site until the Engineer approves your submittal for:

1. Contractor Supplied Biologist.
2. Protocols for Species Protection Surveys
3. Pre-Construction Tarplants Survey Report
4. Baseline Progress Schedule (Critical Path Method)
5. Storm Water Pollution Prevention Plan (SWPPP)
6. Notification of Dispute Resolution Advisor (DRA) or Dispute Review Board (DRB) nominee and disclosure statement as specified in Section 5-1.15, "Dispute Resolution," of the Standard Specifications
7. Lead Compliance Plan

If the submittals for Contractor-Supplied Biologist are approved, you may enter the job site only to measure controlling field dimensions and locating utilities. Do not start other work activates until all submittals from the above list are approved and the following information is submitted:

1. Notice of Materials To Be Used.
2. Contingency plan for reopening closures to public traffic.
3. Written statement from the vendor that the order for the sign panels has been received and accepted by the vendor. The statement must show the dates that the materials will be shipped.
4. Written statement from the vendor that the order for electrical material has been received and accepted by the vendor. The statement must show the dates that the materials will be shipped.
5. Written statement from the vendor that the fabrication order for sign structures have been received and accepted by the vendor. The statement must show the dates that the materials will be shipped.

You may start work at the job site before the 55th day after contract approval if:

1. You obtain required approval for each submittal before the 55th day
2. The Engineer authorizes it in writing

The Department grants a time extension if a delay is beyond your control and prevents you from starting work at the job site on the 1st working day.

Complete the work within 725 working days.

10-1.015 CONTRACTOR SUPPLIED BIOLOGIST

GENERAL

Summary

This work includes providing a Contractor supplied biologist to conduct site preconstruction survey to protect regulated species that may be harmed during construction activities.

Submittals

Protocols: Protocols for species protection surveys must be submitted for acceptance within 30 days before beginning survey activities.

Pre-Construction Survey Report: Submit a Pre-Construction Survey Report within 14 days before beginning construction activities.

Incident Report: Submit an Incident Report within 24 hours of the incident.

Qualifications:

Biologists who perform specialized activities must have demonstrated field experience working with the species or performing the specialized task. Biologists who perform specialized activities must meet the following minimum requirements:

Specialized Activity / Species	Requirements
Site survey, Construction Monitoring and Seed Collection / Tarplants	Field Biologist for 3 years

Protocols

Use protocols required in PLACs.

CONSTRUCTION

Pre-Construction Survey

Survey the work area for regulated species within 21 days before beginning construction activities.

Protective Radius

Upon discovery of a regulated species, stop construction activities within a 25-foot radius of the regulated plant discovery. Immediately notify the Engineer. Do not resume activities until receiving written notification from the Engineer.

Notification and Reporting

All reports must include:

PLAC requirement implementation

Name(s) of the biologist(s) conducting biological activity

Date(s) and time(s) of monitoring

Locations and activities monitored

Representative photographs

Findings

When regulated species are observed, reports must recommend actions to protect the regulated species

Name of the biologist who prepared the report

Signature of the biologist certifying the accuracy of the report

The Pre-Construction Survey Report includes:

Detailed observations and locations where regulated species were observed or statement that no regulated species were observed by each biologist

The incident report includes:

Description of any take incident
Species name and number taken
Details of required notifications with contact information
Corrective actions proposed or taken
Disposition of taken species

MEASUREMENT AND PAYMENT

The contract price paid per day for Contractor supplied biologist includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in Contractor supplied Biologist as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

BID ITEM LIST
12-0F0324

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
221	018390	CLOSED CIRCUIT TELEVISION SYSTEM (LOCATION 4)	LS	LUMP SUM	LUMP SUM	
222	018391	TEMPORARY RAMP METERING SYSTEM	LS	LUMP SUM	LUMP SUM	
223	018392	TEMPORARY MICROWAVE VEHICLE DETECTION SYSTEM	LS	LUMP SUM	LUMP SUM	
224	861101	RAMP METERING SYSTEM (LOCATION 1)	LS	LUMP SUM	LUMP SUM	
225	861102	RAMP METERING SYSTEM (LOCATION 2)	LS	LUMP SUM	LUMP SUM	
226	861103	RAMP METERING SYSTEM (LOCATION 3)	LS	LUMP SUM	LUMP SUM	
227	018393	TEMPORARY COMMUNICATION SYSTEM	LS	LUMP SUM	LUMP SUM	
228	018394	COMMUNICATION SYSTEM	LS	LUMP SUM	LUMP SUM	
229	869075	SYSTEM TESTING AND DOCUMENTATION	LS	LUMP SUM	LUMP SUM	
230	BLANK					
231	146001	CONTRACTOR SUPPLIED BIOLOGIST	DAY	2		
232	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID: _____