Federal Fiscal Year 2006/2007 Bridge Preventive Maintenance Program

For the City Of Oakland

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft^2)	Total Particip. Cost	Unit Cost ($/ft^2$)	Federal Share	Running Fed Summary	Local Share	Running Local Share
1	Alameda	City of Oakland	Develop next year's BPMP								1.00	18,000	18,000	15,935	15,935	2,065	2,065
2	Alameda	City of Oakland	33C0028		Adeline Street	UP Rail Track	Just South of 3rd Street	81.1	SD	Repair crack at Abutment, Joint seal replacement, Treat Deck with Methacrylate, repair spalls	63,645.00	2,384,057	37	2,110,606	2,126,541	273,451	275,516
3	Alameda	City of Oakland	33C0393		West Grand Avenue	Wood St	04-ALA-018-0-OAK	95.9	SD	Treat Deck with Methacrylate, repair joint plate	307,031.00	1,544,954	5	1,367,748	3,494,289	177,206	452,722
4	Alameda	City of Oakland	33C0149		E 8th Street	Lake Merritt Channel	E 8th Street & E 7th Street	94.1	SD	Remove AC, Treat Deck, Overlay Deck with AC	15,600.00	226,523	15	200,541	3,694,830	25,982	478,704
5	Alameda	City of Oakland	33C0165		Hegenberger Road	UP Rail Track	.7 Mile North of I -880	89.2	SD	Seal Deck with Methacrylate, Patch spalls at Hinge 1 & 3,Replace jt seal at Abt1,3 & Hg	39,727.00	445,422	11	394,332	4,089,162	51,090	529,794
6	Alameda	City of Oakland	33C0081		Benedict Drive	San Leandro Creek	North of Lake Chabot Road	88.4	SD	Repair AC at approaches, Treat Deck with Methacrylate	7,632.00	135,035	18	119,546	4,208,708	15,489	545,283
7	Alameda	City of Oakland	33C0031		Oakport Street	Tidel Channel	Near 66th Avenue	89.7	SD	Construct metal tubing Type 2 and treat Deck with Methacrylate	5,980.00	130,000	22	115,089	4,323,797	14,911	560,194
8	Alameda	City of Oakland	33C0164		Hegenberger Road	Tidel Channel	0.3 Mile North of Colseum Way	89.1	SD	Treat Deck with Methacrylate	6,945.00	118,744	17	105,124	4,428,921	13,620	573,814
9	Alameda	City of Oakland	33C0045		Oakport Street	Tidal Channel	0.2 Mile North of Roland Way	87.8		Treat Deck with Methacrylate	3,800.00	91,180	24	80,722	4,509,643	10,458	584,272
10	Alameda	City of Oakland	33C0165		Hegenberger Road (Ped. Over	Hegenberger Road	.3 Mile West of SR 185			Patch Rebars, Patch conc. Replace Expan. Jt., Seal Deck	2,898.00	55,970	19	49,550	4,559,193	6,420	590,692
11	Alameda	City of Oakland	33C0153		Olmsted Street	Channel	Btween 66th and 69th Avenue	94.0	SD	Treat Deck with Methacrylate	835.00	36,435	44	32,256	4,591,449	4,179	594,871
Revised BPMP 11/21/06																	