

City of South San Francisco Bridge Preventative Maintenance Program

Jul-11

Priority (Lowest Number is Top Priority)	City Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft ²)	Total Participation Cost	Unit Cost (\$/ft ²)	Federal Share	Running Fed Summary	Local Share	Running Local Share	
1	S SF	S SF	35C0032		Dunman Way	Hickey Boulevard	0.9 Mi S/W Junipero Serra Blvd	95	N/A	Repair Joint Seal	1,500	\$12,000	8.0	\$10,624		\$1,376		
3	S SF	S SF	35C0046		N Access Road	San Bruno Canal	0.1 Mi E/O S Airport Blvd	80.3	SD	Treat deck with methacrylate.	4,280	\$16,000	3.7	\$14,165		\$1,835		
4	S SF	S SF	35C0047		N Access Road	San Bruno Canal	0.2 Mi E/O S Airport Blvd	84.6	N/A	Treat deck with methacrylate.	4,280	\$16,000	3.7	\$14,165		\$1,835		
5	S SF	S SF	35C0048		San Mateo Avenue	Colma Creek	0.2 Mi E/O Linden Avenue	90.8	SD	Treat deck with methacrylate.	2,666	\$16,000	6.0	\$14,165		\$1,835		
2	S SF	S SF	35C0079		Chestnut Avenue	Colma Creek	0.1 Mi S of Commercial Ave	97.2	N/A	Treat deck with methacrylate.	6,705	\$24,000	3.6	\$21,247		\$2,753		
6	S SF	S SF	35C0101		Utah Avenue	Colma Creek	0.25 Mi E/O S Airport Blvd	93.1	SD	Treat deck with methacrylate.	4,867	\$18,000	3.7	\$15,835		\$2,065		
7	S SF	S SF	35C0173		Oyster Point Blvd	UPRR	0.2 Mi W Gateway	94.6	N/A	Treat deck with methacrylate.	38,475	\$64,000	1.7	\$56,659		\$7,341		
											62,773	\$166,000	2.6	\$146,960	0	\$19,040	0	
											Construction	Const	\$166,000.00		\$146,960		\$19,040	
											Preliminary Engineer (25%)	PE	\$41,500.00		\$36,740		\$4,760	
											R/W	R/W	N/A					
											Construction Engineer (15%)	CE	\$24,900.00		\$22,044		\$2,856	
											Total		\$232,400.00		\$205,744		\$26,656	
															(State)		(Local)	