City of Sacramento
Federal Fiscal Year 2012/2013 BPMP

Priority	Project	County Location	Implementing Agency	Bridge Number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (sq ft)	Total Particip. Cost	Unit Cost	Federal Share	Running Fed Share	Local Share	Running Local Share
1	H Street Rehabilation Project	Sacramento	City of Sacramento	24C-0076	24C-0076	H Street	American River		58	FO	Bridge deck treatment, joint seal installation, approach slab installation and repair, add approach slab	21894	$360,000	0.06	$318,708	$318,708	$41,292	$41,292
2	I, J, and Jiboom Street Viaducts Repair	Sacramento	City of Sacramento	24C-0006	24C-0006	Jiboom Street	I and J Street Viaducts	N from I Street Viaduct	33.1	SD	Joint seal installation, repair hinge plates	27200	$72,345	0.38	$64,047	$382,755	$8,298	$49,590
2	I, J, and Jiboom Street Viaducts Repair	Sacramento	City of Sacramento	24C-0364L	24C-0364L	I Street	Jiboom and J Street Viaducts	BTWN I-5 & Sac River	63.1	SD	Repair hinge plates, patch concrete spalling on underside of deck exposed rebar	29000	$72,345	0.40	$64,047	$446,802	$8,298	$57,888
2	I, J, and Jiboom Street Viaducts Repair	Sacramento	City of Sacramento	24C-0364R	24C-0364R	J Street	I and Jiboom Street Viaducts	BTWN I-5 & Sac River	80.6		Clean and install joint seal	18945	$72,345	0.26	$64,047	$510,849	$8,298	$66,186
3	Howe Ave Embankment Control	Sacramento	City of Sacramento	24C-0142L	24C-0142L	Howe Ave	La Riviera	0.25 mi N/O SR 50	52		Rock Slope paving, slope protection	8720	$124,250	0.07	$109,999	$620,848	$14,251	$80,437
3	Howe Ave Embankment Control	Sacramento	City of Sacramento	24C-0142R	24C-0142R	Howe Ave	La Riviera	0.25 mi N/O SR 50	54		Rock Slope paving, slope protection	8720	$124,250	0.07	$109,999	$730,846	$14,251	$94,689
3	Howe Ave Embankment Control	Sacramento	City of Sacramento	24C-0143L	24C-0143L	Howe Ave	University Ave	0.6 mi N/O SR 50	17		Rock Slope paving, slope protection	4520	$124,250	0.04	$109,999	$840,845	$14,251	$108,940
3	Howe Ave Embankment Control	Sacramento	City of Sacramento	24C-0143R	24C-0143R	Howe Ave	University Ave	0.6 mi N/O SR 50	18		Rock Slope paving, slope protection	4520	$124,250	0.04	$109,999	$950,843	$14,251	$123,192

City of Sacramento
Federal Fiscal Year 2013/2014 BPMP

Priority	Project	County Location	Implementing Agency	Bridge Number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (sq ft)	Total Particip. Cost	Unit Cost	Federal Share	Running Fed Share	Local Share	Running Local Share
4	Northgate over NEMDC	Sacramento	City of Sacramento	24C-0099	24C-0099	Northgate Blvd	Natomas East Main Drain Canal	0.1 mi S/O Garden HWY	89.7		Scour countermeasure	22637	$67,500	0.34	$59,758	$1,010,601	$7,742	$130,934
5	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0382L	24C-0382L	Arena Blvd	East Drain Canal	0.9 mi S/O Del Paso Rd	96.6		Clean and install joint seal	3714	$20,956	0.18	$18,552	$1,029,153	$2,404	$133,338
5	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0378	24C-0378	Holiday Grade Rd	K Street	E/O 3rd St	78.9		Clean and install joint seal	3768	$16,991	0.22	$15,042	$1,044,195	$1,949	$135,287
5	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0359	24C-0359	El Camino Ave	UPRR	0.4 mi W/O Rte 51	89.3		Clean and install joint seal	42109	$18,690	2.25	$16,546	$1,060,742	$2,144	$137,430
5	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0353	24C-0353	Arden Way	UPRR	0.3 mi W/O Rte 51	94.4		Clean and install joint seal	25597	$41,534	0.62	$36,770	$1,097,512	$4,764	$142,194
5	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-0122	24C-0122	Pocket Rd	Douglas Drain	2.1 mi W/O Rte 5	85.6		Clean and install joint seal	11625	$32,283	0.36	$28,580	$1,126,092	$3,703	$145,897
5	Joint Seal Repair Project	Sacramento	City of Sacramento	24C-112	24C-112	Marconi	Auburn Blvd	0.2 mi W/O Rte 51	96.1		Clean and install joint seal	28654	$58,336	0.49	$51,645	$1,177,737	$6,691	$152,588