City of Redwood City BPMP - Developed September 2012

Priority (Lowest Number is Top Priority)	County Location	Implementing Agency	Bridge Number	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft^2)	Total Participating Cost	Unit Cost ($/$ft^2$)	Federal Share	Running Fed Summary	Local Share	Running Local Share
1										Develop following Year's BPMP	1.00	$10,000.00	$10,000.00	$ 8,853	$ 8,853	$ 1,147	$ 1,147
2	SM	RDWC	35C0033	N/A	Main Street	Redwood Creek	at Veteran's Blvd	95.1		Methacrylate Deck Seal, Repair Cracked Pier	4,600.00	$25,000.00	$5.43	$ 22,133	$ 30,986	$ 2,868	$ 4,015
3	SM	RDWC	35C0034	N/A	Veteran's Blvd	Redwood Creek	East of Main Street	74.8	FO	Methacrylate Deck Seal, Replace Joint Seal	12,376.00	$60,000.00	$4.85	$ 53,118	$ 84,104	$ 6,882	$ 10,897
4	SM	RDWC	35C0128	N/A	Maple St.	Redwood Creek	North of Lathrop St.	83.1		Repair Deck Soffit Spalls, Seal Abutment Crack	2,250.00	$10,000.00	$4.44	$ 8,853	$ 92,957	$ 1,147	$ 12,044