EL DORADO COUNTY
Bridge Preventative Maintenance Program
Federal Fiscal Year 2013/2014

September 30, 2013

Priority	Implementing Agency	State Bridge No.	Local Agency Bridge No.	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD / FO Status	Work Description	Deck Area (ft^2)	Total Participating Cost	Unit Cost ($/ft^2$)	Federal Share	Running Federal Summary	Local Share	Running Local Share
1	El Dorado County	25C0016	88	Mount Aukum Rd	North Fork Cosumnes River	2.6 mi S of Pleasant Valley Rd	67.5	N/A	Replace joint seals; deck overlay; spot painting.	7110	$ 494,870	$ 70	$ 438,108	$ 438,108	$ 56,762	$ 56,762
2	El Dorado County	25C0102	111	Cosumnes Mine Rd	North Fork Cosumnes River	4 mi N of Grizzly Flat Rd	62.1	FO	Clean debris from abutments, joints, bearings, drains; replace deck boards.	1742	$ 142,602	$ 82	$ 126,245	$ 564,353	$ 16,357	$ 73,119
4	El Dorado County	25C0061	81	Mosquito Rd	South Fork American River	5.6 mi N of U.S. 50	12.5	SD	Replace lower truss chord timbers and transverse timber beams.	2181	$ 190,000	$ 87	$ 168,207	$ 732,560	$ 21,793	$ 94,912
3	El Dorado County	25C0025	56	Happy Valley Rd	Camp Creek	0.5 mi SE of Mt Aukum Rd	16.0	SD	Replace deck boards.	2525	$ 175,000	$ 69	$ 154,927	$ 887,487	$ 20,073	$ 114,985
5	El Dorado County	25C0045	64	Ice House Rd	Jones Fork Silver Creek	12.8 mi N of U.S. 50	70.4	N/A	Replace bearing pads; replace joints; install approach slabs.	2397	$ 734,133	$ 306	$ 649,927	$ 1,537,414	$ 84,206	$ 199,191
N/A	El Dorado County	25C0072	25	Bayne Rd	Dutch Creek	0.46 mi S of Mt Murphy Rd	60.6	FO	Note: Project closure during PE phase requested in August 2013. Total of $1,070 PE funds expended to date.	--	$ 1,070	--	$ 947	$ 1,538,361	$ 123	$ 199,314
Total										**15955**	**$ 1,737,675**		**$ 1,538,361**		**$ 199,314**	