



TOWN OF FAIRFAX

142 BOLINAS ROAD, FAIRFAX, CALIFORNIA 94930
(415) 453 - 1584 / FAX (415) 453-1618

June 20, 2014

Mr. Louis Schuman, PE
Office of Local Assistance – MS 10B
Caltrans District 4
111 Grand Avenue
Oakland, CA 94612-3717

RE: Town of Fairfax BPMP - Federal Project No. BPMP 5277(026)

Dear Mr. Schuman,

Attached please find the latest spreadsheet reflecting the Town of Fairfax's BPMP project cost and other required information. The Town of Fairfax certifies the list has been prepared in accordance with Caltrans Bridge Preventive Maintenance Program Guidelines. The Town requests the approval of the attached list and costs, as well as authorization to continue with Preliminary Engineering.

Sincerely,

FOR GARRETT TOY
Town Manager
Town of Fairfax

Attach.: BPMP Spreadsheet

Federal Fiscal Year 2013/2014 Bridge Preventive Maintenance Program for the Town of Fairfax

Priority (Lowest Number is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft ²)	Total Particip. Cost PE + CON	Unit Cost (\$/ft ²)	Federal Share	Running Fed Summary	Local Share	Running Local Share
1	MRN	Town of Fairfax (FRFX)	Develop next year's BPMP	-	-	-	-	-	-	Develop next year's BPMP	1	\$8,000	\$8,000	\$7,082	\$7,082	\$918	\$918
2	MRN	Town of Fairfax (FRFX)	27C-0143		Marin Road	Fairfax Creek	0.03 mi southwest of Sir Francis Drake Blvd.	58.8 58		1. Replace topped downstream wingwall at Abutment 2 (left looking downstream). Restore riprap. 2. Repair damaged wingwall upstream at abutment 1 3. Repair 2 spalls at the 2 abutments	1,090	\$242,928	\$222.87	\$215,064	\$222,147	\$27,864	\$28,781
3	MRN	Town of Fairfax (FRFX)	27C-0141		Spruce Road	Fairfax Creek	.15 mi southwest of Sir Francis Drake Blvd. & Azalea Ave	63.9 63.9		1. Coldplane AC on deck, apply methacrylate and overlay deck with polyester concrete 2. Replace joint seals (2)	808	\$239,728	\$297	\$212,231	\$434,378	\$27,497	\$56,278
4	MRN	Town of Fairfax (FRFX)	27C-0146		Canyon Road	San Anselmo Cr.	.05 mi southwest of intersection with Cascade Drive	72.8	FO	1. Replace concrete sack wingwall @ abutment 1 (left side looking downstream) with integral R/C wingwall. Repair the downstream wingwall on same side. 2. Strengthen eroded concret at face of abutment 1 3. Clean deck and apply methacrylate to seal the cracks 4. Repair joint seals (2) 5. Repair superstructure concrete spall at northeast rail post	470	\$389,779	\$829	\$345,071	\$779,449	\$44,708	\$100,986