

Federal Fiscal Year 2014/2015 Bridge Preventative Maintenance Program

PM00121

CITY OF ANAHEIM  
BRIDGE PREVENTATIVE MAINTENANCE PROGRAM FY 14-15

PRIORITY	COUNTY LOCATION	AGENCY	BRIDGE NO. FROM	FACILITY INTERSECTED	FACILITY CARRIED	LOCATION	FUNCTIONAL CLASSIFICATION (URBAN)	SUFFICIENCY RATING	SD/FO STATUS	WORK DESCRIPTION	DECK AREA (SQUARE FEET)	TOTAL PARTICIPATORY COSTS	UNIT COST ( \$ / SQUARE FOOT)	FEDERAL SHARE	RUNNING FEDERAL SUMMARY	LOCAL SHARE	LOCAL RUNNING SHARE
1	ORANGE	ANAHEIM		Develop Next Year's BPMP													
	ORANGE	ANAHEIM	55C0509	SANTA ANA RIVER CHANNEL	WEIR CANYON RD	0.4 Miles N/O Route 91 Freeway	OTHER PRINCIPAL ARTERIAL	62.0		JOINT SEAL REPLACEMENT, METHACRYLATE SEAL, PATCH CRACKS	58426.51	\$85,000	\$1.45	\$75,251	\$75,250.50	\$9,749.50	\$9,749.50
	ORANGE	ANAHEIM	55C0510	SANTA ANA RIVER CHANNEL	LAKEVIEW AVE	0.43 Miles N/O Route 91 Freeway	OTHER PRINCIPAL ARTERIAL	75.5	SD	JOINT SEAL REPLACEMENT, METHACRYLATE SEAL	26789.22	\$41,000.00	\$1.53	\$36,297	\$111,547.80	\$4,702.70	\$14,452.20
	ORANGE	ANAHEIM	55C0613	MAGNOLIA AVE (OVERHEAD)	UPRR	300 Feet S/O Route I-5 Freeway	OTHER PRINCIPAL ARTERIAL	70.4	FO	JOINT SEAL REPLACEMENT	12761.69	\$17,000.00	\$1.33	\$15,050	\$126,597.90	\$1,949.90	\$16,402.10
	ORANGE	ANAHEIM	55C0111	SANTA ANA RIVER CHANNEL	TUSTIN AVE	0.3 Miles S/O Route 91 Freeway	OTHER PRINCIPAL ARTERIAL	85.9	SD	METHACRYLATE SEAL	51821.77	\$67,000.00	\$1.29	\$59,315	\$185,913.89	\$7,684.90	\$24,087.11
	ORANGE	ANAHEIM	55C0671	SB DISNEYLAND DRIVE OC	SB DISNEYLAND DR	0.25 Miles S/O Ball Rd.	MINOR ARTERIAL	90.5		JOINT SEAL REPLACEMENT	21850.74	\$9,000.00	\$0.41	\$7,968	\$193,881.59	\$1,032.30	\$25,119.41
	ORANGE	ANAHEIM	55C0675	NB DISNEYLAND DRIVE OC	NB DISNEYLAND DRIVE	0.4 Miles S/O Ball Rd.	MINOR ARTERIAL	69.2	FO	JOINT SEAL REPLACEMENT	5123.62	\$2,000.00	\$0.39	\$1,771	\$195,652.19	\$229.40	\$25,348.81
	ORANGE	ANAHEIM	55C0673	DISNEYLAND FLYOVER/ BALL RD SEP	DISNEYLAND FLYOVER	At Ball Road	MINOR ARTERIAL	80.7		JOINT SEAL REPLACEMENT	13811.17	\$5,000.00	\$0.36	\$4,427	\$200,078.69	\$573.50	\$25,922.31
	ORANGE	ANAHEIM	55C0587	CARBON CANYON CHANNEL	CROWTHER AVE	0.2 Miles W/O Orangethorpe	MINOR ARTERIAL	87.9		METHACRYLATE SEAL	2336.85	\$3,000.00	\$1.28	\$2,656	\$202,739.90	\$344.10	\$26,267.10
	ORANGE	ANAHEIM	55C0469	CARBON CANYON DIVERSION CHANNEL	KRAEMER BLVD	0.1 Miles S/O La Palma Ave.	OTHER PRINCIPAL ARTERIAL	59.5		JOINT SEAL REPLACEMENT	7879.18	\$4,000.00	\$0.51	\$3,541	\$208,055.24	\$458.80	\$26,955.76
TOTALS												\$233,000		\$206,275		\$26,725	