Inyo County

Federal Fiscal Year 2014/2015 Bridge Preventive Maintenance Program

(EDIT Federal Fiscal Year as Needed)

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft^2)	Total Particip. Cost	Unit Cost ($\$/ft^2$)	Federal Share	Running Fed Summary	Local Share	Running Local Share
1			Develop next year's BPMP								1.00	35,000	35,000	30,986	30,986	4,015	4,015
2	http://maps.google.com/maps?/	County of Inyo	48C0014		WHITNEY PORTAL I	LONE PINE CREEK	0.8 MI W OF RTE 395 JCT	60.7		7-Timber railing repair	1,312.96	22,500	17	19,919	50,905	2,581	6,595
3	http://maps.google.com/maps?/	County of Inyo	48C0005		MAZOURKA CYN RI	LOS ANGELES AQUEDU	1.8 MI E OF RTE 395 JCT	85.5		7-Timber railing paint to extend railing life	1,606.34	22,500	14	19,919	70,824	2,581	9,176
4	http://maps.google.com/maps?/	County of Inyo	48C0015		GLACIER LODGE RI	BIG PINE CREEK	3.8 MI W OF ROUTE 395	89.2		13-Embankment erosion control	1,699.83	102,500	60	90,743	161,567	11,757	20,933
5	http://maps.google.com/maps?/	County of Inyo	48C0023		OLD SHERWIN GRA	PINE CREEK	.04 MI S OF BIRCHIM LANE	75.7		13-Embankment erosion control	784.93	72,500	92	64,184	225,752	8,316	29,249
6	http://maps.google.com/maps?/	County of Inyo	48C0002		PINE CREEK RD	PINE CREEK	4 MI W OF RTE 395 JCT	92.1		2 -Methacrylate - Clean and seal deck	1,107.68	66,461	60	58,838	284,590	7,623	36,872
7	http://maps.google.com/maps?/	County of Inyo	48C0021		PINE CREEK RD	PINE CREEK	8.3 MI W OF RTE 395	92.1		2 -Methacrylate - Clean and seal deck	1,171.59	70,295	60	62,233	346,822	8,063	44,934
8	http://maps.google.com/maps?/	County of Inyo	48C0016		GLACIER LODGE RI	BIG PINE CREEK	2.6 MI W OF ROUTE 395	89.3		2 -Methacrylate - Clean and seal deck	1,247.97	74,878	60	66,290	413,112	8,589	53,523
9	http://maps.google.com/maps?/	County of Inyo	48C0047		FIVE BRIDGES ROA	OWENS RIVER	1.6 mi N. of Rte 6	96.8	SD	2 -Methacrylate - Clean and seal deck	3,281.10	147,649	45	130,714	543,826	16,935	70,458