PM00061

EL DORADO COUNTY
Bridge Preventative Maintenance Program
Federal Fiscal Year 2015/2016

September 24, 2015
Updated: October 14, 2015

Priority	Implementing Agency	State Bridge No.	Local Agency Bridge No.	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD / FO Status	Work Description	Deck Area (ft^2)	Total Participating Cost	Unit Cost ($\$/ft^2$)	Federal Share	Running Federal Summary	Local Share	Running Local Share
1	El Dorado County	25C0016	86	Mount Aukum Rd	North Fork Cosumnes River	2.6 mi S of Pleasant Valley Rd	67.5	N/A	Replace joint seals; deck overlay; spot painting.	7110	$ 462,719	$ 65	$ 409,645	$ 409,645	$ 53,074	$ 53,074
2	El Dorado County	25C0102	111	Cosumnes Mine Rd	North Fork Cosumnes River	4 mi N of Grizzly Flat Rd	62.1	FO	Clean debris from abutments, joints, bearings, drains; replace deck boards.	1742	$ 142,602	$ 82	$ 126,245	$ 535,890	$ 16,357	$ 69,431
3	El Dorado County	25C0061	81	Mosquito Rd	South Fork American River	5.6 mi N of U.S. 50	12.5	SD	Replace lower truss chord timbers and transverse timber beams.	2181	$ 190,000	$ 87	$ 168,207	$ 704,097	$ 21,793	$ 91,224
4	El Dorado County	25C0025	59	Happy Valley Rd	Camp Creek	0.5 mi SE of Mt Aukum Rd	36.8	SD	Replace deck boards.	2525	$ 175,000	$ 69	$ 154,927	$ 859,024	$ 20,073	$ 111,297
5	El Dorado County	25C0045	63	Ice House Rd	Jones Fork Silver Creek	12.8 mi N of U.S. 50	65.1	N/A	Replace bearing pads; replace joints; install approach slabs.	2397	$ 734,133	$ 306	$ 649,928	$ 1,508,952	$ 84,205	$ 195,502
6	El Dorado County	25C0036	104	Salmon Falls Rd	New York Creek	1.2 mi N of Green Valley Rd	85.7	N/A	Place multilayer polymer deck overlay.	2640	$ 150,000	$ 57	$ 132,795	$ 1,641,747	$ 17,205	$ 212,707
7	El Dorado County	25C0076	13	Big Cut Rd	Weber Creek	1.2 mi N of Pleasant Valley Rd	88.2	FO	Remove methacrylate surfacing; place multilayer polymer deck overlay.	786	$ 150,000	$ 191	$ 132,795	$ 1,774,542	$ 17,205	$ 229,912
Total										**19,381**	**$ 2,004,454**		**$ 1,774,542**		**$ 229,912**	