

Bracketed section numbers refer to the 2006 *Standard Specifications*.

Section 81 Monuments

4-8101 General

This section describes the work for constructing survey monuments.

4-8102 Before Work Begins

Before work begins, take the following steps:

- Upon delivery of the materials to the job site, material is field inspected and released by the engineer. Complete Form CEM-4102, “Material Inspected and Released on Job.”
- Arrange for necessary control staking when the contractor has submitted the required survey request. Control staking must be sufficient to set the disk to the accuracy required in the specifications.

4-8103 During the Course of Work

Check materials, dimensions, details, finish, and cure for compliance with specifications. Many monuments that existed before construction must be preserved or reset. The surveys unit should perform any resetting. If previously undiscovered monuments are found during construction, request the surveys unit to investigate and handle or recommend action to be taken.

4-8104 Measurement and Payment

The contractor must pay for relocating monuments lost or damaged by the contractor’s operation. See Section 5-1.36 [7-1.11], “Property and Facility Preservation,” in the *Standard Specifications*.

Section 81 Monuments

4-8101 General

4-8102 Before Work Begins

4-8103 During the Course of Work

4-8104 Measurement and Payment