

## Section 81 Monuments

## Section 81 Monuments

### 4-8101 General

This section describes the work for constructing survey monuments.

### 4-8101 General

### 4-8102 Before Work Begins

During this preliminary inspection, take the following steps:

### 4-8102 Before Work Begins

- Upon delivery of the materials to the job site, note whether they are identified by marks or inspection tags (use Form TL-0624, “Inspection Release Tag”) and match the marks or tags against Form TL-0029, “Report of Inspection of Material.” Determine the final acceptability of the frame and cover as outlined in the Table 6-2.1, “Inspection of Fabricated and Manufactured Materials” in Section 6-2, “Acceptance of Manufactured Material and Sampling Methods,” of the *Construction Manual*.
- Arrange for necessary control staking when the contractor has submitted the required survey request. Control staking must be sufficient to set the disk to the accuracy required in the specifications.

### 4-8103 During the Course of Work

Check materials, dimensions, details, finish, and cure for compliance with specifications. Many monuments that existed before construction must be preserved or reset. The surveys unit should perform any resetting. If previously undiscovered monuments are found during construction, request the surveys unit to investigate and handle or recommend action to be taken.

### 4-8103 During the Course of Work

### 4-8104 Measurement and Payment

The contractor must pay for relocating monuments lost or damaged by the contractor’s operation. See section 7-1.11, “Preservation of Property,” in the *Standard Specifications*.

### 4-8104 Measurement and Payment