Attachment 1

Item No.	ITEM	Unit of Measure	Quantity	Engineer's Unit Price Estimate 25% below	Engineer's Unit Price Estimate	Engineer's Unit Price Estimate 50% above	Unit Price	Total
	Item 1-16. **ASBESTOS DISPOSAL**- To be disposed at a State Licensed Public Facility. Unit quotation includes compensation for bags and labels necessary to dispose of asbestos in accordance with the terms of this contract. Payment will be made from quantity of cubic yard shown on manifest from disposal site.							
1	Asbestos Disposal – Payment will be made from quantity of cubic yard shown on the disposal site manifest.	Cubic Yard Manifest Required	500	$ 46.04	$ 61.39	$ 92.09	60.00	30,000.00
2	Asbestos Removal - Exterior stucco or plaster	Square Foot	3,000	$ 1.88	$ 2.51	$ 3.77	2.00	6,000.00
3	Asbestos Removal–Asbestos containing Mastic with attached non-asbestos containing resilient floor covering, tile, moldings or other floor related materials. (Requires removal of both materials)	Square Foot	15,000	$ 1.11	$ 1.48	$ 2.22	1.25	18,750.00
4	Asbestos Removal- Asbestos containing Resilient Floor Covering, Floor Tiles, moldings or other floor related materials w/attached non-asbestos containing Mastic. (Requires removal of both materials)	Square Foot	15,000	$ 1.25	$ 1.67	$ 2.51	1.25	18,750.00
5	Asbestos Removal – Asbestos Containing Paint (ACP) with or without attached materials. Includes removal of ACP by chemical, mechanical or other proper means.	Square Foot	5,000	$ 3.88	$ 5.17	$ 7.76	4.00	20,000.00
6	Asbestos Removal - Asbestos containing Mastic with attached non-asbestos containing paneling, wall treatment, interior/exterior ceiling tiles or other wall/ceiling materials. (Requires removal of both materials)	Square Foot	5,000	$ 1.29	$ 1.72	$ 2.58	1.30	6500.00
7	Asbestos Removal-Asbestos containing materials, Spray-on or hand applied materials or texture on Interior Wall Board, Plaster, wall or ceiling treatment	Square Foot	25,000	$ 1.79	$ 2.38	$ 3.57	3.00	75,000.00
						Total This Page		175,000.00

Attachment 1

Item No.	ITEM	Unit of Measure	Quantity	Engineer's Unit Price Estimate 25% below	Engineer's Unit Price Estimate	Engineer's Unit Price Estimate 50% above	Unit Price	Total
8	Asbestos Removal-Pipe Lagging, Insulation, Insulated Flues, Ducts, Duct Connectors	Linear Foot	100	$ 4.85	$ 6.46	$ 9.96	9.00	900.00
9	Asbestos Removal-Boiler or Vessel Lagging or Insulation	Square Foot	100	$ 5.09	$ 6.79	$ 10.19	10.00	1000.00
10	Asbestos Removal-Roof Felt and Cover Material	Square Foot	15,000	$ 1.59	$ 2.12	$ 3.18	2.00	30,000.00
11	Asbestos Removal-Roof Mastic	Linear Foot	1,500	$ 3.01	$ 4.01	$ 6.02	3.10	4650.00
12	Asbestos Removal-Asbestos containing Cement Siding, interior/exterior ceiling tiles, panels or sheets	Square Foot	5,000	$ 1.26	$ 1.68	$ 2.52	1.50	7500.00
13	Asbestos Removal-Asbestos-Cement Pipe	Linear Foot	500	$ 4.59	$ 6.12	$ 9.18	5.00	2500.00
14	Asbestos Removal-Window Putty, per window.	Each	150	$ 2.01	$ 2.68	$ 4.02	3.00	450.00
15	Asbestos Removal-Fireproofing	Square Foot	500	$ 4.85	$ 6.46	$ 9.69	9.00	4500.00
16	Asbestos Removal-Fire doors	Each	5	$ 11.17	$ 14.89	$ 22.34	12.00	60.00
17	PCB and MERCURY containing fixtures such as but not limited to light fixtures, thermostats, fluorescent light bulbs, etc.	Each Fixture	100	$ 1.28	$ 1.70	$ 2.55	1.50	150.00
18	Backfill, Grading and Berming – includes compensation for backfill material as specified in this Agreement's Exhibit A, Scope of Work.	Ton – Weight Tags Required	100	$ 4.92	$ 6.56	$ 9.84	9.00	900.00
							Total This Page	52610.00

Attachment 1

Item No.	ITEM	Unit of Measure	Quantity	Engineer's Unit Price Estimate 25% below	Engineer's Unit Price Estimate	Engineer's Unit Price Estimate 50% above	Unit Price	Total
19	Masonry Walls – Removal of brick, concrete, cinder-block or rock. Includes removal of footings (backfill material shall be paid by line item #18), re-bar, etc... All labor including handwork, tools and equipment, to remove and properly dispose of walls.	Square Foot	1,000	$ 1.21	$ 1.61	$ 2.42	1.25	1,250.00
20	Debris – Debris is defined as combustible and non-combustible rubbish found on a parcel PRIOR to any demolition and removal operations by Contractor. (Excluding debris in Parcels A, B, C, D and D-1 of this bid proposal sheet.)	Per Ton – Weight Tags Required	100	$ 43.25	$ 57.67	$ 86.51	50.00	5000.00
21	Demo/Remove Fences – Removal of fences. Includes removal of footings (backfill material shall be paid by line item #18), all labor including handwork, tools and equipment, to remove and properly dispose of fences constructed of wood, rock, plastics or wire as specified in Exhibit A, Scope of Work, Section 7, Demolition and Removal in this Agreement.	Linear Foot	500	$ 0.69	$ 0.92	$ 1.38	1.00	500.00
22	Lead Disposal – disposed at a State Licensed Public Facility	Cubic Yard	100	$ 129.25	$ 172.33	$ 258.50	130.00	13,000.00
23	Lead removal – All materials or other surfaces or fixtures. Includes interior/exterior painted materials, windows, paint chips and any other materials, excluding item #24.	Square Foot	100	$ 3.22	$ 4.29	$ 6.44	6.00	600.00
24	Lead Removal – Trim or Molding	Linear Foot	100	$ 3.55	$ 4.73	$ 7.10	7.00	700.00
							Total This Page	21,050.00

Attachment 1

Item No.	ITEM	Unit of Measure	Quantity	Engineer's Unit Price Estimate 25% below	Engineer's Unit Price Estimate	Engineer's Unit Price Estimate 50% above	Unit Price	Total
	Items 25-28. The unit price includes all tasks as specified in Exhibit A, Scope of Work, Section 16 (C), in this Agreement. The unit quotation includes removal and disposal of all of the following, at the discretion of, and as designated by Contract Manager, from the non-residential lot/site: Improvements shall be measured from outside exterior wall dimensions and not from end of roof overhang. Plants, shrubs, trees less than 15 feet in height, excludes fences in line item #21, excludes masonry walls in line item #19, foundations, footings, steps, slab floors, curbing, retaining walls, minor concrete flat work, decks, sheds septic tanks and cesspools, capping of sewer lines, and removal of all interior debris and minor exterior debris. Unit quotation also includes back filling (backfill materials to be paid by line item #18) and grading required as a result of any excavation and as specified in the General Specifications of this contract.							
25	PARCEL A – REMOVAL OF ANY ONE OR TWO-STORY RESIDENCE, DUPLEX OR MOBILE HOME WITH ATTACHED OR DETACHED GARAGES OR CARPORTS FROM A RESIDENTIAL LOT OR SITE.	Square Foot	60,000	$ 3.77	$ 5.03	$ 7.55	3.80	228,000.00
26	PARCEL B – REMOVAL OF NON-RESIDENTIAL COMMERCIAL BUILDINGS AND/OR COVERED AREAS, INCLUDING ATTACHED AND DETACHED GARAGES AND CARPORTS.	Square Foot	100,000	$ 2.61	$ 3.48	$ 5.22	4.00	400,000.00
27	PARCEL C – REMOVAL OF RESIDENTIAL APARTMENT OR HOTEL/MOTEL (COMMERCIAL OR CONVERTED) BUILDINGS WITH ATTACHED OR DETACHED GARAGES OR CARPORTS.	Square Foot	100,000	$ 3.19	$ 4.25	$ 6.38	3.50	350,000.00
28	PARCEL D – REMOVAL OF FOUNDATIONS, FOOTINGS, STEPS, CURBING, PORTLAND CEMENT CONCRETE OR ASPHALTIC CONCRETE FLATWORK, INCLUDING, BUT NOT LIMITED TO, DRIVEWAYS AND WALKWAYS. The unit quotation is based on the square footage of the foundations, footings, steps, and flat work that are not being removed under the specification of Parcels A, B, C and D-1.	Square Foot	25,000	$ 0.67	$ 0.89	$ 1.34	.80	20,000.00
							Total This Page	998,000.00

Attachment 1

Item No.	ITEM	Unit of Measure	Quantity	Engineer's Unit Price Estimate 25% below	Engineer's Unit Price Estimate	Engineer's Unit Price Estimate 50% above	Unit Price	Total
29	PARCEL D-1 – REMOVAL, BACKFILL AND GRADING OF BASEMENTS – The unit quotation includes compensation for backfill material as specified in the Exhibit A of this contract, and removal and disposal of all of the following, at the discretion of, and as designated by Contract Manager: basement walls, floors and footings.	Ton – Weight Tags Required	20,000	$ 1.63	$ 2.17	$ 3.26	1.70	34,000.00
30	IN-GROUND POOL REMOVAL. BACKFILL AND GRADING OF CONCRETE OR PLASTIC LINED IN-GROUND SWIMMING POOLS. The unit quotation includes compensation for backfill material as specified in the General Specifications of this contract, and removal and disposal of all of the following, at the discretion of, and as designated by Contract Manager: Associated spas, decking and related pool equipment. Plants, shrubs, trees less than 15 feet in height, and removal of all debris.	Ton – Weight Tags Required	500	$ 9.08	$ 12.11	$ 18.17	10.00	5000.00
							Total This Page	39,000.00

Attachment 1

Item No.	ITEM	Unit of Measure	Quantity	Engineer's Unit Price Estimate 25% below	Engineer's Unit Price Estimate	Engineer's Unit Price Estimate 50% above	Unit Price	Total
	Item 31-33 Contractor shall prepare the Stormwater Pollution Prevention Plan for task orders which exceed 1 acre of disturbed soil - The SWPPP shall be prepared by a Qualified SWPPP Developer (QSD) as per qualification requirements of State Water Resources Control Board. Plans must be acceptable to the Contract Manager. A QSD shall act as the WPCM (Water Pollution Control Manager) and shall be responsible for the implementation of a SWPPP. The implementer of the BMPs specified in the SWPPP must have the qualifications-certification of a Qualified SWPPP Practitioner (QSP). At the discretion and direction of the Caltrans Contract Manager, the contractor's WPCM (Water Pollution Control Manager) will provide to Caltrans Contract Manager all information for Storm Water Annual Report which includes certifications, monitoring and inspection results, and obtaining Storm Water Annual Report acceptance. Including all information required to submit a Notice of Termination (NOT) such as photos, reports, etc… for each demolition site. Caltrans specifications require that the project specific WPCP be prepared by a Qualified SWPPP Practitioner (QSP). The WPCM responsible for implementation of the WPCP must have the same qualifications as a QSP.							
31	STORM WATER POLLUTION PREVENTION PLAN – To be developed and Implemented in accordance with Caltrans' Statewide Storm Water Permit and General Construction Permit, and acceptable to Caltrans Contract Manager.	Storm Water Pollution Prevention Plan (SWPPP) EACH	10	$ 197.92	$ 263.89	$ 395.84	200.00	2000.00
32	WATER POLLUTION CONTROL PROGRAM (WPCP) – To be developed and implemented in accordance with Caltrans' Statewide Storm Water Permit, and acceptable to Contract Manager for a task order with a disturbed soil area of less than one acre.	WATER POLLUTION CONTROL PROGRAM (WPCP) – EACH	10	$ 156.25	$ 208.33	$ 312.50	160.00	1600.00
33	SWPPP AMENDMENT - An amendment to the original SWPPP to add additional parcels to existing demolition TASK ORDER or PROJECT (EA's) as defined by Caltrans Contract Manager. To be developed in accordance with Caltrans' Statewide Storm Water Permit, and acceptable to Contract Manager. WPCP shall not be amended to add additional parcels. All requirements as noted in item #31 shall be included in this line item.	Each	5	$ 109.17	$ 145.56	$ 218.34	110.00	550.00
							Total This Page	4150.00

Attachment 1

Item No.	ITEM	Unit of Measure	Quantity	Engineer's Unit Price Estimate 25% below	Engineer's Unit Price Estimate	Engineer's Unit Price Estimate 50% above	Unit Price	Total
	Item # 35-40. All erosion control devices shall be properly maintained during all phases of the demolition project until the completion of all demolition activities and all disturbed soil areas have been stabilized. Additional control devices may be required during demolition in order to control erosion and/or offsite sedimentation. All erosion control devices shall be inspected until demolition is complete and the site is stabilized. All temporary control devices shall be removed once demolition is complete and the site is permanently stabilized. Upon completion of each demo task, contractor shall ensure that all disturbed soil areas of demolition site are stabilized prior to submitting the Notice of Termination (NOT). Final stabilization for the purposes of submitting an NOT is satisfied when all soil-disturbing activities are completed							
34	TESTING/SAMPLING of water run-on and run-off. To be developed and Implemented in accordance with Caltrans' Statewide Storm Water Permit and General Construction Permit, and acceptable to Caltrans Contract Manager. The Sampling and Analysis Plan (SAP) and the Rain Event Action Plan (REAP) must be developed, implemented, monitored and documented by the QSD.	Each	5	$ 337.50	$ 450.00	$ 675.00	332.50	1687.50
35	STORMWATER MANAGEMENT-FIBER OR STRAW MATS	Square Foot	1000	$ 14.43	$ 19.24	$ 28.86	14.50	14,500.00
36	STORMWATER MANAGEMENT-FIBER ROLLS	Square Foot	1000	$ 1.19	$ 1.58	$ 2.37	1.20	1200.00
37	STORMWATER MANAGEMENT-HYDRO SEED	Square Foot	1000	$ 8.66	$ 11.54	$ 17.31	8.70	8,700.00
38	STORMWATER MANAGEMENT-SAND OR GRAVEL BAGS	Bag	200	$ 1.34	$ 1.78	$ 2.67	1.35	270.00
39	STORMWATER MANAGEMENT – SILT FENCEING	Linear Foot	1000	$ 2.12	$ 2.83	$ 4.25	2.15	2150.00
40	STORMWATER MANAGEMENT-STRAW BALES	Each	100	$ 4.17	$ 5.56	$ 8.34	4.20	420.00
							Total This Page	28,927.50

Attachment 1

Item No.	ITEM	Unit of Measure	Quantity	Engineer's Unit Price Estimate 25% below	Engineer's Unit Price Estimate	Engineer's Unit Price Estimate 50% above	Unit Price	Total
	Item 41-43. No trees are to be removed except those designated by Contract Manager. Unit Quotation includes removal and disposal of trees 15 feet in height or higher, including rootball, and back filling (backfill materials to be paid by line item #18) and grading resulting excavation.							
41	TREE REMOVAL AND DISPOSAL– Removal of trees in direct conflict with the demolition of structures, as determined by Contract Manager.	Each	25	$ 133.34	$ 177.78	$ 266.67	135.00	3,375.00
42	TREE REMOVAL AND DISPOSAL NOT ASSOCIATED WITH DEMOLITION OF STRUCTURES - Unit Quotation includes removal and disposal of individual and grouped trees (less than 1 acre) and not considered to be part of an orchard by the Caltrans Contract Manager.	Each	25	$ 141.67	$ 188.89	$ 283.34	145.00	3,625.00
43	TREE REMOVAL AND DISPOSAL NOT ASSOCIATED WITH ITEMS 41 & 42 Includes removal and disposal of trees of any kind and size determined to be part of an orchard by the Contract manager.	Acre	10	$ 812.50	$ 1,083.33	$ 1,625.00	820.00	8200.00
44	TIRE REMOVAL AND DISPOSAL – Unit quotation includes the removal of any passenger, truck, tractor or other type of rubber tire including rims and its proper disposal at a State permitted facility for tire disposal.	Each	250	$ 9.29	$ 12.39	$ 18.59	9.50	2375.00
							Total This Page	17,575.00

Attachment 1

Item No.	ITEM	Unit of Measure	Quantity	Engineer's Unit Price Estimate 25% below	Engineer's Unit Price Estimate	Engineer's Unit Price Estimate 50% above	Unit Price	Total
	Item 45-46. Work to be done by a properly licensed contractor. Unit price includes all standard permits, testing, inspections, disposal of all materials associated with water well, excavation, back filling and grading as a result of excavation in and around well casing. Any permits, well testing, inspections, special water well backfill material and any other special requirements by the local governing agency shall be paid with original invoice plus contractor mark up.							
45	ABANDONMENT OF DOMESTIC WATER WELL– Unit quotation includes abandoning a domestic water well up to and including a 12 inch diameter casing in accordance with local, state and federal requirements.	Each	10	$ 2,041.71	$ 2,722.28	$ 4,083.42	2,050.00	20,500.00
46	ABANDONMENT OF IRRIGATION WATER WELL – Unit quotation includes abandoning irrigation water wells, regardless of well casing diameter, in accordance with local, state and federal requirements.	Each	5	$ 3,857.20	$ 5,142.93	$ 7,714.40	3,900.00	19,500.00
	Items 20-21, 25-30, and 47-48. Treated Waste Wood (TWW) shall be handled and disposed of in a composite-lined portion of a solid waste landfill unit that meets all requirements applicable to disposal of municipal solid waste in California. Contractor shall submit to Caltrans Contract Manager a weight tag for disposal of treated wood. One-ton minimum per weight tag. Work includes grading resulting from excavation.							
47	REMOVAL AND DISPOSAL OF ANY VARIETY OF GRAPE VINES – Unit quotation includes removal and disposal of vines, stakes (wood, metal or other), end posts, wire.	Per Each 100 Linear Feet Minimum	100	$ 101.25	$ 135.00	$ 202.50	102.00	10,200.00
48	REMOVAL AND DISPOSAL OF TREATED TIMBER/LUMBER/POLES - Unit quotation includes removal and proper disposal of treated wood products.	Per Ton - Weight Tag Required	2	$ 93.75	$ 125.00	$ 187.50	95.00	190.00
							Total This Page	50,390.00

Attachment 1

Item No.	ITEM	Unit of Measure	Quantity	Engineer's Unit Price Estimate 25% below	Engineer's Unit Price Estimate	Engineer's Unit Price Estimate 50% above	Unit Price	Total
	Items 25-28, 49. Unit quotation includes abandoning any additional septic tank(s) in accordance with local, state and federal requirements, obtaining any necessary permits, pumping of septic material must be performed by a licensed septic pumping service, removal and proper disposal of septic tank (concrete, plastic, wood or other material), backfill (backfill materials to be paid by line item #18) and grade as a result of excavation as specified in the General Specifications of this contract.							
49	ABANDON ADDITIONAL SEPTIC TANK SYSTEM – (Excludes the first septic tank found in Parcels A, B, C and D of this bid proposal).	Each	3	$ 112.50	$ 150.00	$ 225.00	112.50	337.50
50	Remobilization: Cost to stop and restart work (abatement or demolition) due to a delay caused by Caltrans. Requires work to stop and restart on a different calandar day.	Each	1	$ 1,125.00	$ 1,500.00	$ 2,250.00	1,125.00	1,125.00
51	**Special Conditions:** There is no bid item for this work. The Special Conditions is for unforeseen unanticipated work that may occur during this Agreement. If during the demolition services described herein, it is discovered that unanticipated additional work is required in order to complete required work under this Agreement, such work may be completed as directed and approved by the Caltrans Contract Manager. Unanticipated work can include a wide range of unforeseen services that needed to complete a demolition project. All unanticipated work identified must be documented by the Contractor and must be approved by the Caltrans Contract Manager prior to any work being done. Such documentation shall include, but not be limited to, specified labor classifications, materials and equipment, and the number of hours necessary to complete the work for each worker. If additional unanticipated services are required, the Contractor will be reimbursed per Attachment 1A, Budget Detail and Payment Provisions and by the rate(s) that specified in the Rate Sheet, Attachment 1A. The costs of the additional equipment and/or supplies not specified in the Rate Sheet, Attachment 1A, will be reimbursed at actual costs without mark-up and are to be substantiated by an appropriately signed invoice verifying the costs and must be approved in advance in writing by the Caltrans Contract Manager. Reference this Agreement's Exhibit A, Scope of Work, Section 23, Special Conditions							$250,000.00
						Total This Page		251,462.50
						Grand Total (Add Pages 1-10)		$1,638,165.00

(1) The quantities listed in this Bid Proposal are estimates only and are given as basis for comparison of bids. No guarantee is made or implied as to the exact quantity that will be needed.

(2) Item 51 (above) is for unanticipated additional work that is required in order to complete required demolition work under this Agreement (refer to Attachment 1A. Contractor will be reimbursed at cost (including applicable sale tax). All cost is to be substantiated including submission of original signed receipts, and approved by Caltrans Contract Manager. No reimbursement will be made to the Contractor for any services not described in Exhibit A, Scope of Work.

(3) Should any unit price reflect more than 25% below or 50% above the corresponding Engineer's Unit Price Estimate, the bid will be deemed unbalanced and therefore, nonresponsive.

(4) Bid rates shall include labor, transportation, equipment, and disposal costs, as applicable.

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION
SUBCONTRACTING PROVISIONS/LIST
Form ADM 1511 (REV. 4/14)

ATTACHMENT 2

List all subcontractors that will be used in this Agreement. All subcontractors listed below must be used in accordance with the Agreement. This includes, if applicable, compliance with the subcontracting provisions and any Disabled Veteran Business Enterprise (DVBE), Small Business (SB), Micro-Business, and Disadvantaged Business Enterprises (DBE) subcontractors. Attach a copy of the quote on the letterhead of the Certified SB, DVBE, or DBE subcontractor to this form. The quote will serve as written confirmation that the Certified SB, DVBE, or DBE is participating in the contract. If none, bidder to write "NONE" in this space.

NAME	BUSINESS ADDRESS	DESCRIPTION OF PORTION OF WORK WHICH WILL BE DONE BY EACH CONTRACTOR*
Canepa and Son Well Drilling	1438 Cuesta Circle Sonora, CA. 95370	Well Abandonment DIR # 1000009617
Future Environmental Services	10556 Combie Rd #6250 Auburn, CA. 95602	Hazardous Waste Hauler Hazardous Waste Removal DIR # 1000031522
Williams Excavation	2444 E Princeton Ave Fresno, CA. 93704	Hazardous Waste Removal DIR# 1000003066

ATTACHMENT 5
BID/BIDDER CERTIFICATION SHEET

Only an individual who is authorized to bind the bidding firm contractually shall sign the Bid/Bidder Certification Sheet. The signature must indicate the title or position that the individual holds in the firm. This Bid/Bidder Certification Sheet must be signed and returned along with all "required attachments" as an entire package with original signatures. The bid must be transmitted in a sealed envelope in accordance with IFB instructions.

A. Our all-inclusive bid is submitted in a sealed envelope marked "**Bid Submittal - Do Not Open**".
B. All required attachments are included with this certification sheet.
C. The signature affixed hereon and dated certifies compliance with all the requirements of this bid document. The signature below authorizes the verification of this certification.
D. The signature and date affixed hereon certifies that this bid is a firm offer for a 90-day period.

An Unsigned Bid/Bidder Certification Sheet May Be Cause for Bid Rejection

1. Company Name	2. Telephone Number	2a. Fax Number
AFM Enviironmental, Inc.	(916) 374-9526	(916) 374-9527

2b. Email Address AFM ENVIRO @ AOL.COM

3. Address 752 Northpoint Dr #C
West Sacramento, CA. 95691

Indicate your organization type:
4. ☐ Sole Proprietorship | 5. ☐ Partnership | 6. ☑ Corporation

Indicate the applicable employee and/or corporation number:
7. Federal Employee ID No. (FEIN) 68-0330294 | 8. California Corporation No. 1886924

Indicate the Department of Industrial Relations information:
9. Contractor Registration Number 1000011390

Indicate applicable license and/or certification information:

10. Contractor's State Licensing Board Number	11. PUC License Number CAL-T-
689596	
12. Bidder' Name (Print) Alfred Hardwick	13. Title President
14. **Signature**	15. Date 6/28/16

16. Are you certified with the Department of General Services, Office of Small Business and Disabled Veteran Business Enterprise Services (OSDS) as:

a. Small Business Enterprise Yes ☑ No ☐
If yes, enter certification number: 5170

b. Disabled Veteran Business Enterprise Yes ☐ No ☐
If yes, enter your service code below: _____

NOTE: A copy of your Certification is required to be included if either of the above items is checked "**Yes**".

Date application was submitted to OSDS, if an application is pending: _____

17. Are you a Non-Small Business committing to the use of 25% Certified Small Business Subcontractor Participation?
Yes ☐ No ☒

If Yes, complete and return the Bidder Declaration form, GSPD-05-105 with your bid.

STATE OF CALIFORNIA • DEPARTMENT OF TRANSPORTATION

DISADVANTAGED BUSINESS ENTERPRISE (DBE) INFORMATION

Attachment 7

ADM-0227f (Rev. 06/2012) (CONTRACTS FEDERALLY FUNDED IN WHOLE OR IN PART)

PART A – CONTRACTORS INFORMATION (Refer to Instructions on Page 2 of this form. Bidder/Proposer shall ensure all information provided is complete and accurate.)

CONTRACTOR'S BUSINESS NAME	AGREEMENT NUMBER	CONTRACT DOLLAR AMOUNT	DATE
AFM Environmental, Inc.	062254	1,638,165.00	6/28/16

CONTRACTOR'S BUSINESS ADDRESS	CITY	STATE	ZIP CODE
752 Northport Dr #C	West Sacramento	CA	95691

CONTACT PERSON	BUSINESS PHONE	FAX NUMBER	EMAIL ADDRESS
Alfred Hardwick	(916) 374-9526	(916) 374-9527	AFMENVIRO@AOL.COM

PART B – DBE INFORMATION AND DOCUMENTATION (Refer to Instructions in Page 2 of this form. Bidder/Proposer shall verify DBE certifications.) Contractor shall attach a copy of the bid (or price quote) from the DBE (on the DBE's Letterhead) for all DBEs listed below.

(1) Prime and Subcontractors: List Name(s) and addresses of all DBEs that will participate in this Agreement:	(2) Area Code & Phone Number	(3) Tier	(4) Description of Work, Service, or Materiel Supplied	(5) DBE or CUCP Certification Number.	(6) Ownership Code	(7) DBE $ Amount Claimed	(8) % of $ Value Claimed	(9) Caltrans Use Only %
AFM Environmental, Inc 752 Northport Dr #C	(916) 374-9526	Prime	Abatement/ Demolition	27381	1	1,200,000.00	73	
West Sacramento, CA. 95691								

PART C – FOR CALTRANS USE ONLY (Verification Completed by Civil Rights, Office of Business and Economic Opportunity):

PRINT VERIFIER'S NAME AND TITLE	SIGNATURE	DATE	CIVIL RIGHTS STAMP OF APPROVED
DBE PARTICIPATION ☐ YES (%) ☐ NO			

AFM

ENVIRONMENTAL, INC

TIME / EQUIPMENT AND MATERIAL RATES
June 28, 2016
LINE ITEM # 51

PROJECT MANAGER	$195.00 PER HOUR
CONTRACTOR / SUPERVISOR ASBESTOS CERTIFIED	$195.00 PER HOUR
ABATEMENT WORKER	$135.00 PER HOUR
GENERATOR 10K	$140.00 PER DAY
½ TON PICKUP TRUCK	$70.00 PER HOUR
5'X12' PULL BEHIND TRAILER	$100.00 PER DAY
200 GAL WATER WAGON	$300.00 PER DAY
NEGATIVE AIR MACHINE 2K EACH	$125.00 PER DAY
HEAVY EQUIPMENT OPERATOR	$170.00 PER HOUR
WATER TRUCK	155.00 PER HOUR
EXCAVATOR 320 LARGE	$250.00 PER HOUR
BOBCAT OR BACKHOE	$150.00 PER HOUR
TRUCKING 4 HOUR MINIMUM	$180.00 PER HOUR
JACK HAMMER	$50.00 PER HOUR

*752 Northport Drive, # C * West Sacramento, CA 95691 * 800-558-2967 * 916-374-9526 * Fax 916-374-9527*
California Contractors License Number 689596 * DOSH Registration Number 559