All Terrain Drill Rigs

CME-750 Drill, Quantity: 1

Trailer:	Lowboy Trailer
Weight:	28,000#
Dimension:	21'4" (L), 8'0" (W), 8'10" (H, travel)
Drilling:	Auger (200'), Mud Rotary (800')
Rod String:	20' Maximum
Winches:	Main (1), Safety (1), Pulling (2), Wire Line (1)
Hammer:	140#, Automatic Hammer
Sampling:	SPT, Brass Push, Shelby Tube,
	Punch Core, Diamond Core

CS-100 Drill, Quantity: 1

Trailer:	Trans. to Site on Cargo Body Truck
Weight:	10,000#
Dimension:	8' 0" (L), 8' 0" (W), 8' 0" (H, travel)
Drilling:	Mud Rotary (120')
Rod String:	5' Maximum
Winches:	Safety (1)
Hammer:	140#, Safety Hammer
Sampling:	SPT, Brass push, Shelby Tube,
	Punch Core, Diamond Core

CS-1000 Drill, Quantity: 1

Trailer:	Lowboy Trailer
Weight:	20,440#
Dimension:	18'0" (L), 8'0" (W), 12'3" (H travel)
Drilling:	Auger (100'), Mud Rotary (600')
Rod String:	15' Maximum
Winches:	Pulling (2), Wire Line (1)
Hammer:	140# Automatic Hammer
Sampling:	SPT, Brass push, Shelby Tube,
	Punch Core, Diamond Core

All Terrain Drill Rigs

CS-2000 Horizontal Drill, Quantity: 1

Trailer:	Lowboy Trailer
Weight:	22,280#
Dimension:	20'0" (L), 8'0" (W), 12'2" (H travel)
Drilling:	Auger (120'), Mud Rotary (800')
Rod String:	20' Maximum
Winches:	Lifting (2), Wire Line (1)
Hammer:	140# Automatic Hammer
Sampling:	SPT, Brass push, Shelby Tube,
	Punch Core, Diamond Core

PROJECT DELIVERY DIVISION OF ENGINEERING SERVICES

Safety Quality Value