

INDEX OF PLANS

SHEET No.	DESCRIPTION
1	TITLE AND LOCATION MAP
2	LOCATIONS OF CONSTRUCTION
3-4	CONSTRUCTION AREA SIGNS
5-11	TRAFFIC HANDLING DETAILS
12	PAVEMENT DELINEATION DETAILS
13-16	PAVEMENT DELINEATION QUANTITIES
17-20	TRAFFIC CONTROL SYSTEM
21-23	REVISED STANDARD PLANS

STRUCTURE PLANS

24-38	ROUTE 105, 405 & 605 BRIDGES
-------	------------------------------

THE STANDARD PLANS LIST APPLICABLE TO THIS CONTRACT IS INCLUDED IN THE NOTICE TO BIDDERS AND SPECIAL PROVISIONS BOOK.

NOTE:



THE TABLE OF LOCATIONS OF CONSTRUCTION IS SHOWN ON THE LOCATIONS OF CONSTRUCTION SHEET.

**STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION**

**PROJECT PLANS FOR CONSTRUCTION ON
STATE HIGHWAY**

**IN LOS ANGELES COUNTY
AT VARIOUS LOCATIONS**

TO BE SUPPLEMENTED BY STANDARD PLANS DATED 2010



PROJECT MANAGER
CHRISTIAN SAM

DESIGN ENGINEER
MD MUSA

2-12-13
 PROJECT ENGINEER DATE
 REGISTERED CIVIL ENGINEER
Kevin Kwan
 No. 68219
 Exp. 9-30-13
 CIVIL
 STATE OF CALIFORNIA

CONTRACT No. **07-1W4004**
 PROJECT ID **0712000053**

THE CONTRACTOR SHALL POSSESS THE CLASS (OR CLASSES) OF LICENSE AS SPECIFIED IN THE "NOTICE TO BIDDERS."

NO SCALE

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans MAINTENANCE ENGINEERING

FUNCTIONAL SUPERVISOR
 MD MUSA

CALCULATED/DESIGNED BY
 CHECKED BY

KEVIN KWAN
 MD MUSA

REVISED BY
 DATE REVISED

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	2	38

Kevin Kwan 2-12-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

LOCATIONS OF CONSTRUCTION				
Loc No.	ROUTE	POST MILE	BRIDGE No.	DESCRIPTION
1	105	R11.10	53-2662	STATE STREET UC
2	105	R11.56	53-2493	LONG BEACH BOULEVARD UC
3	405	14.92	53-1174	VAN NESS AVENUE UC
4	405	15.98	53-1177	YUKON AVENUE UC
5	405	20.16	53-2387K	EL SEGUNDO OH
6	405	20.18	53-1238	129TH STREET OH
7	405	R21.32	53-2434T	IMPERIAL HIGHWAY ON-RAMP OC (CONNECTOR)
8	405	21.74	53-1242	LENNOX BOULEVARD UC
9	405	23.64	53-1249	LA CIENEGA BOULEVARD NB OC
10	405	25.99	53-1838G	N405-W90 CONNECTOR OC
11	405	26.10	53-1974F	S405-W90 CONNECTOR OC
12	405	27.20	53-1259	CULVER BOULEVARD UC
13	405	27.45	53-1260	WASHINGTON BOULEVARD UC
14	605	R4.71	53-1721	DAIRY VALLEY OH
15	605	R8.23	53-1652	HOXIE OH

LOCATIONS OF CONSTRUCTION

LC-1

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans MAINTENANCE ENGINEERING

FUNCTIONAL SUPERVISOR
 MD MUSA

CALCULATED/DESIGNED BY
 KEVIN KWAN

REVISOR
 MD MUSA

CHECKED BY
 MD MUSA

DATE
 2-12-13

BORDER LAST REVISED 7/2/2010

USERNAME => s122436
 DGN FILE => 71W4001a001.dgn

APPROVED FOR CONSTRUCTION AREA SIGN WORK ONLY

CONSTRUCTION AREA SIGNS (STATIONARY MOUNTED)

SIGN NUMBER	SIGN CODE	PANEL SIZE	SIGN MESSAGE	NUMBER OF POSTS AND SIZE	NUMBER OF SIGNS
(A)	W20-1	48" X 48"	ROAD WORK AHEAD	1-6" x 6"	18
(B)	G20-2	48" X 24"	END ROAD WORK	1-4" x 6"	15
(C)	C40 (CA)	144" X 60"	TRAFFIC FINES DOUBLED IN CONSTRUCTION ZONES	2-6" x 6"	13

NOTES:



- LOCATIONS OF CONSTRUCTION AREA SIGNS SHOWN ARE APPROXIMATE. THE ENGINEER DETERMINES EXACT LOCATIONS.
- "TRAFFIC FINES DOUBLED IN CONSTRUCTION ZONES" SIGNS SHALL BE PLACED APPROXIMATELY 500 FEET IN ADVANCE OF "ROAD WORK AHEAD" SIGNS OR AS THE ENGINEER DETERMINES.
- SEE SHEET LC-1 FOR LOCATIONS OF CONSTRUCTION.

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	3	38

Kevin Kwan 2-12-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER
 KEVIN KWAN
 No. 68219
 Exp. 9-30-13
 CIVIL
 STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



CONSTRUCTION AREA SIGNS

NO SCALE

CS-1



UNIT 1959

PROJECT NUMBER & PHASE

07120000531

LAST REVISION DATE PLOTTED => 27-MAR-2013
 03-25-13 TIME PLOTTED => 1:34


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105,405, 605	Var	5	38

Duke M. Huynh 2-27-13
 REGISTERED CIVIL ENGINEER DATE


3-25-13
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
 DUKE HUYNH
 No. 65591
 Exp. 9-30-13
 CIVIL
 STATE OF CALIFORNIA



SIGN SP-1




ALTERNATE OVERLAY PANELS (TYPICAL)

- NOTES:**(SIGN SP-1)
- SIGNS SHALL HAVE ORANGE RETROREFLECTORIZED BACKGROUND WITH BLACK BORDER AND LETTERS.
 - BOLT HOLES SHALL BE 3/8" DIAMETER.
 - BASE MATERIAL SHALL BE ALUMINUM (MINIMUM 0.06").
 - SIGNS SHALL BE MOUNTED WITH BOTTOMS OF SIGNS A MINIMUM OF 6' ABOVE GROUND.

SIZE	BORDER	MARGIN	LETTER SIZE					CORNER RADIUS
	WIDTH	WIDTH	LINE 1	LINE 2*	LINE 3	LINE 4	LINE 5,6 & 7*	
48"x60"	1 1/4"	3/4"	4E	4D	6E	4D		3"
42"x26"	OVERLAY						3D	1 1/2"

* CONDENSED SPACING IF NECESSARY

SPECIAL ADVANCE NOTICE PUBLICITY SIGN



SIGN SP-3

SPECIAL SIGN FOR EXIT RAMP CLOSURES

- NOTES:** (SIGNS SP-3 & SP-5)
- LETTERS - 6" SERIES D.
 - LETTERS AND BORDERS - BLACK ON RETROREFLECTORIZED ORANGE BACKGROUND.
 - BASE MATERIAL SHALL BE ALUMINUM (MINIMUM 0.06").
 - SIGNS SHALL BE MOUNTED WITH BOTTOMS OF SIGNS A MINIMUM OF 6' ABOVE GROUND.



SIGN SP-5



SIGN SP-4

- NOTES:** (SIGN SP-4)
- LETTERS - 6" SERIES C.
 - LETTERS AND BORDERS - BLACK ON RETROREFLECTORIZED WHITE BACKGROUND.
 - BASE MATERIAL SHALL BE ALUMINUM (MINIMUM 0.06").
 - SIGNS SHALL BE PLACED AT RAMP ENTRANCES IN ADDITION TO SIGNS POSTED IN ACCORDANCE WITH TCS PLANS.


SPECIAL SIGN FOR ENTRANCE RAMP CLOSURES

**TRAFFIC HANDLING DETAILS
 TRAFFIC CONTROL SYSTEM
 FOR RAMP CLOSURES, DETOUR SIGNS
 AND MISCELLANEOUS DETAILS**

SHEET 1 OF 2

NO SCALE

THD-1




SIGN SP-2

NOTES: (SIGN SP-2)


- LETTERS -6" SERIES E.
- LETTERS, BORDER AND ARROW - BLACK ON RETROREFLECTORIZED ORANGE BACKGROUND.
- BASE MATERIAL FOR SIGNS AND ARROWS SHALL BE ALUMINUM (MINIMUM 0.06").
- BELTS (LUGGAGE STRAPS) SHALL BE 1" WIDE BY 48" LONG, MADE OF COTTON OR POLYPROPYLENE WEB MATERIAL.
- SIGNS SHALL BE MOUNTED WITH BOTTOMS OF SIGNS A MINIMUM OF 6' ABOVE GROUND EXCEPT AS OTHERWISE SHOWN ON OTHER TRAFFIC HANDLING DETAILS PLANS.

ABBREVIATION

(CA) CALIFORNIA CODE



SIGN SP-6 (SEE NOTE 1)




SIGN SP-7 (SEE NOTE 1)

NOTES: (SIGNS SP-6 & SP-7)

- IN LIEU OF PLACING SIGNS ON TYPE III BARRICADES, SIGNS, INCLUDING POSTS, MAY BE PLACED INTO THE GROUND OR FASTENED ONTO ELECTROLIERS.
- USE APPROPRIATE ROUTE SHIELD [G26-2(CA), G27-2(CA), G28-2(CA)] AND CARDINAL DIRECTION [NORTH (M3-1), SOUTH (M3-3), EAST (M3-2), WEST (M3-4)]

SPECIAL PORTABLE FREEWAY DETOUR SIGNS



ADJUSTABLE ARROW DETAIL

DIMENSIONS							
A	B	C	D	E	F	G	R
11 1/4"	7 1/4"	3 1/8"	4"	7/8"	13"	7 1/2"	5/8"

SPECIAL PORTABLE FREEWAY DETOUR SIGN

**TRAFFIC HANDLING DETAILS
TRAFFIC CONTROL SYSTEM
FOR RAMP CLOSURES, DETOUR SIGNS
AND MISCELLANEOUS DETAILS**

SHEET 2 OF 2

NO SCALE

THD-2

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
 DT M
 FUNCTIONAL SUPERVISOR DENIS S KATAYAMA
 CHECKED BY
 CALCULATED/DESIGNED BY
 REVISOR BY ALBERT K YU DATE REVISION 7/10
 REVISOR BY JOCELYN C CHIANG

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105,405, 605	Var	7	38

Duke M Huynh 2-27-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE
 No. 65591
 Exp. 9-30-13
 CIVIL
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

NOTES:


- LANE CLOSURES SHALL NOT BE PLACED ON CREST VERTICAL CURVES OR ON HORIZONTAL CURVES.
- PCMS SHALL BE ACTIVATED PRIOR TO TRAFFIC CONTROL ACTIVITIES ON THE HOV LANE.
- A MINIMUM SIGHT DISTANCE OF 1500' SHALL BE PROVIDED IN ADVANCE OF PCMS.
- VEHICLE-MOUNTED SIGN PANELS SHALL BE TYPE III OR IV RETROREFLECTORIZED SHEETING, BLACK ON WHITE OR BLACK ON ORANGE WITH 8" MINIMUM SERIES D LETTERS PER CALTRANS SIGN SPECIFICATIONS.
- PLACE PCMS ON THE MEDIAN SHOULDER WHERE SUFFICIENT ROOM (SUCH AS CHP ENFORCEMENT AREAS) EXISTS.

LEGEND

- V1, V2 SHADOW VEHICLE
- V3 WORK/APPLICATION VEHICLE
- PCMS PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)
- DIRECTION OF TRAVEL
- HOV LANE

ABBREVIATIONS

- FAS FLASHING ARROW SIGN
- IAV IMPACT ATTENUATOR VEHICLE
- CMS CHANGEABLE MESSAGE SIGN
- (CA) CALIFORNIA CODE
- PCMS PORTABLE CHANGEABLE MESSAGE SIGN
- HOV HIGH OCCUPANCY VEHICLE



STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans
DTM
 FUNCTIONAL SUPERVISOR: DENIS S. KATAYAMA
 REVISIONS: JC 7/10
 REVISOR: ALBERT K. YU
 CHECKER: JOCELYN C. CHIANG
 USERNAME => s122436
 DGN FILE => 71w400me003.dgn




LAST REVISION: DATE PLOTTED => 27-MAR-2013
 03-25-13 TIME PLOTTED => 13:35

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105,405, 605	Var	8	38

Duke M Huynh 2-27-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
 DUKE HUYNH
 No. 65591
 Exp. 9-30-13
 CIVIL
 STATE OF CALIFORNIA



ABBREVIATIONS

(CA)	CALIFORNIA CODE
HOV	HIGH OCCUPANCY VEHICLE

NOTES: FOR CASE I AND CASE II

- AT LEAST ONE PERSON SHALL BE ASSIGNED TO FULL TIME MAINTENANCE OF TRAFFIC CONTROL DEVICES ON NIGHT LANE CLOSURES OR DAY-TIME CLOSURES EXCEEDING 1 MILE LENGTH, INCLUDING TAPERS.
- ADVANCE WARNING SIGN INSTALLATIONS SHALL BE EQUIPPED WITH FLAGS FOR DAYTIME CLOSURES. TYPE B HIGH INTENSITY FLASHING WARNING LIGHTS SHALL BE USED ON SP-16 SIGNS DURING NIGHT LANE CLOSURES. FLAGS AND WARNING LIGHTS SHALL BE ATTACHED TO SIGNS AS APPROVED BY THE ENGINEER.
- THE FLASHING ARROW SIGN SHALL BE TYPE I.
- PLACE C30 (CA) SIGNS EVERY 2000' THROUGHOUT THE LENGTH OF LANE CLOSURE.
- A MINIMUM 1500' OF SIGHT DISTANCE SHALL BE PROVIDED WHERE POSSIBLE FOR VEHICLES APPROACHING THE FLASHING ARROW SIGN. LANE CLOSURES SHALL NOT BE PLACED ON CREST VERTICAL CURVES OR ON HORIZONTAL CURVES.
- PORTABLE DELINEATORS PLACED AT ONE-HALF THE SPACING INDICATED FOR TRAFFIC CONES MAY BE USED INSTEAD OF CONES FOR DAYTIME CLOSURES.
- A MINIMUM OF 3 CONES SHALL BE PLACED TRANSVERSELY ACROSS CLOSED LANES WHERE TAPERS END AND EVERY 2000'. TWO TYPE II BARRICADES MAY BE USED INSTEAD OF 3 CONES. THE ALIGNMENT OF CONES OR BARRICADES MAY BE SHIFTED FROM THE TRANSVERSE ALIGNMENT TO PROVIDE ACCESS TO WORK.
- IF AN INGRESS/EGRESS AREA IS WITHIN 5250' UPSTREAM OR DOWNSTREAM OF THE WORK AREA, LANE CLOSURES SHALL BE EXTENDED TO THAT AREA AS SHOWN IN CASE II.
- SIGNS SP-16, 17, 18, AND 19 MAY BE OVERLAID ON EXISTING CARPOOL SIGNS IN MEDIANS AS APPROVED BY THE ENGINEER.
- SIGNS SP-16, 17, 18, AND C30 (CA) SHALL BE BLACK ON ORANGE BACKGROUND. SIGN SP-19 SHALL BE BLACK ON WHITE BACKGROUND. DIAMONDS ON SIGNS SHALL BE WHITE.
- FOR CLOSURE OF LANE(S) ADJACENT TO HOV LANES, SEE CASE II.
- THE MAXIMUM SPACING BETWEEN CONES SHALL BE APPROXIMATELY 50' IN TAPERS AND 100' ON TANGENTS.

LEGEND

●	CONES
⚡	FLASHING BEACON
◇	HOV LANE
←←←	FLASHING ARROW SIGN
⏏	PORTABLE SIGN
→	DIRECTION OF TRAVEL

SIGN PANEL SIZE (MIN)

SP-16	36" X 54"
SP-17	36" X 54"
SP-18	36" X 48"
SP-19	36" X 60"
C30 (CA)	30" X 30"
G20-2	48" X 24"

**TRAFFIC HANDLING DETAILS
TRAFFIC CONTROL SYSTEM
FOR HIGH OCCUPANCY VEHICLE LANES
AT NON-INGRESS/EGRESS AREAS**

**CASE I
NO SCALE**


THD-4

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
 DTM
 Et Caltrans®
 FUNCTIONAL SUPERVISOR: DENIS S. KATAYAMA
 CHECKED BY: JOCELYN C. CHIANG
 REVISIONS: 7/10
 DESIGNED BY: ALBERT K. YU
 DATE: 7/10

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105,405, 605	Var	9	38

Duke M Huynh 2-27-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans
 DT M
 FUNCTIONAL SUPERVISOR DENIS S. KATAYAMA
 CHECKED BY JOCELYN C. CHIANG
 DESIGNED BY ALBERT K. YU
 REVISED BY JC
 DATE REVISED 7/10
 USERNAME => s122436
 DGN FILE => 71w400me005.dgn



- NOTES:**
- SEE CASE I FOR NOTES, LEGENDS AND ABBREVIATIONS FOR THIS SHEET.
 - CLOSURES OF ONE MIXED FLOW TRAFFIC LANE ADJACENT TO HOV LANE SHOWN. MULTIPLE MIXED FLOW LANE CLOSURES ARE SIMILAR.


TRAFFIC HANDLING DETAILS
TRAFFIC CONTROL SYSTEM
FOR HIGH OCCUPANCY
VEHICLE LANES AND ADJACENT FREEWAY LANES
BETWEEN INGRESS/EGRESS AREAS
CASE II
 NO SCALE
THD-5

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105,405, 605	Var	10	38

Duke M Huynh 2-27-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER
 DUKE HUYNH
 No. 65591
 Exp. 9-30-13
 CIVIL
 STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



TYPICAL DETOUR SIGN INSTALLATION ALONG DESIGNATED DETOUR ROUTE

LEGEND

⚡	TEMPORARY SIGN (SP-2)
—	AND/OR DESIGNATED DETOUR ROUTE

➡	DIRECTION OF TRAVEL

- NOTES:**
1. SP-2 SIGNS SHALL NOT BE INSTALLED ON BARRICADES EXCEPT AS OTHERWISE SHOWN.
 2. SIGN LOCATIONS ARE APPROXIMATE. EXACT LOCATIONS WILL BE DETERMINED BY THE ENGINEER.
 3. SP-2 SIGNS SHALL BE POSTED AT SIGNALIZED INTERSECTIONS ALONG THE DESIGNATED DETOUR ROUTE OR 1/2 MILE MAXIMUM APART.

**TRAFFIC HANDLING DETAILS
TRAFFIC CONTROL SYSTEM
FOR DETOUR SIGN INSTALLATION
ALONG DESIGNATED DETOUR ROUTE
SHEET 1 OF 2
NO SCALE**

THD-6







STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION	FUNCTIONAL SUPERVISOR	CALCULATED/DESIGNED BY	REVISOR	DATE
Caltrans	DENIS S. KATAYAMA	ALBERT K. YU JOCELYN C. CHIANG	JC	7/10

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105,405, 605	Var	11	38

Duke M Huynh 2-27-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER
 DUKE HUYNH
 No. 65591
 Exp. 9-30-13
 CIVIL
 STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



TYPICAL DETOUR SIGN INSTALLATION AT OFF-RAMP

- NOTES:**
1. TEMPORARY SIGNS MAY BE STRAPPED ON EXISTING ELECTROLIER, SIGNAL POSTS, OR SIGN POSTS.
 2. OMIT DETAIL A AND DETAIL B FOR FULL FREEWAY CLOSURES.
 3. SEE TRAFFIC HANDLING DETAILS PLAN-TRAFFIC CONTROL SYSTEM FOR RAMP CLOSURES, DETOUR SIGNS AND MISCELLANEOUS DETAILS SHEET 2 OF 2 FOR SP-6.


ABBREVIATIONS
 (CA) CALIFORNIA CODE

- LEGENDS**
- TRAFFIC CONE
 - ↑ TEMPORARY SIGN
 - DIRECTION OF TRAVEL
 - EXISTING OVERHEAD SIGN

**TRAFFIC HANDLING DETAILS
 TRAFFIC CONTROL SYSTEM
 FOR DETOUR SIGN INSTALLATION
 ALONG DESIGNATED DETOUR ROUTE
 SHEET 2 OF 2
 NO SCALE**

THD-7

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
 FUNCTIONAL SUPERVISOR
 DENIS S. KATAYAMA
 DTM
 CALCULATED/DESIGNED BY
 CHECKED BY
 REVISOR BY
 DATE REVISED
 JC
 8/10
 ALBERT K. YU
 JOCELYN C. CHIANG


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	12	38
			2-12-13	DATE	
REGISTERED CIVIL ENGINEER			DATE		
3-25-13			PLANS APPROVAL DATE		
			<small>THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.</small>		

NOTE:


1. FOR DETAIL 13/14 (MODIFIED), APPLY 4" WIDE THERMOPLASTIC TRAFFIC STRIPE ON TOP OF TYPE A NON-REFLECTIVE MARKERS.

LEGEND:


-  TYPE C RED-CLEAR RETROREFLECTIVE MARKER OR TYPE G ONE-WAY CLEAR RETROREFLECTIVE MARKER
-  TYPE H ONE-WAY YELLOW RETROREFLECTIVE MARKER
-  WHITE STRIPE (THERMOPLASTIC)
-  3" BLACK CONTRAST STRIPE (PAINT)
-  4" YELLOW STRIPE (THERMOPLASTIC)
-  2-TYPE G ONE-WAY CLEAR RETROREFLECTIVE MARKERS
-  DIRECTION OF TRAVEL




DETAIL 13/14 (MODIFIED)



INGRESS/EGRESS STRIPING DETAIL



HOV STRIPING DETAIL (DOUBLE DOUBLE YELLOW)



HOV STRIPING DETAIL (DOUBLE YELLOW)

PAVEMENT DELINEATION DETAILS
NO SCALE

PDD-1

NOTE:

1. SEE SHEET LC-1 FOR LOCATIONS OF CONSTRUCTION.

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	13	38

Kevin Kwan 2-12-13
 REGISTERED CIVIL ENGINEER DATE

3-25-13
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

PAVEMENT DELINEATION QUANTITIES															
LOCATION No.	ROUTE	POST MILE	DESCRIPTION	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)				REMOVE THERMOPLASTIC TRAFFIC STRIPE					REMOVE PAINTED TRAFFIC STRIPE		
				Det 25	Det 25A	HOV STRIPING DETAIL		Det 13/14 (Mod)	Det 27B	Det 36	Det 36A	Det 38B		HOV STRIPING DETAIL	
				4" (YELLOW)	4" (YELLOW)	4" (DOUBLE YELLOW)	4" (DOUBLE YELLOW)	4" (BROKEN 36-12) (WHITE)	4" (WHITE)	8" (WHITE)	8" (WHITE)	8" (WHITE)		4" (WHITE)	8" (BROKEN 36-12) (WHITE)
				LF	LF	LF	LF	LF	LF	LF	LF	LF	LF		
1	105	R11.10	STATE STREET UC	340		1,360		850	340				340	680	
2	105	R11.56	LONG BEACH BOULEVARD UC	1,166		2,332		2,332	1,166				292	1,166	
5	405	20.16	EL SEGUNDO OH	234			468	702	234				334		
7	405	R21.32	IMPERIAL HIGHWAY ON-RAMP OC		327			100	327						
8	405	21.74	LENNOX BOULEVARD UC	290	145		580	1,450	435	290		145	290		
10	405	25.99	N405-W90 CONNECTOR OC		930			945	965						
11	405	26.10	S405-W90 CONNECTOR OC		169				169						
12	405	27.20	CULVER BOULEVARD UC	360		720		1,440	360				180	90	
13	405	27.45	WASHINGTON BOULEVARD UC	35		125							35		
14	605	R4.71	DAIRY VALLEY OH	104		208		312	208	104	52		104	104	
15	605	R8.23	HOXIE OH	30		60							30	30	
SUBTOTAL				2,559	1,571	4,537	1,316	8,131	4,204	394	52	145	1,313	382	1,980
TOTAL				9,983				14,621					1,980		

PAVEMENT DELINEATION QUANTITIES

PDQ-1



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	14	38

Kevin Kwan 2-12-13
 REGISTERED CIVIL ENGINEER DATE

3-25-13
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

PAVEMENT DELINEATION QUANTITIES																																		
LOCATION No.	ROUTE	POST MILE	DESCRIPTION	REMOVE PAVEMENT MARKER							REMOVE THERMOPLASTIC PAVEMENT MARKING																							
				Det 13/14 (Mod)	Det 13/14 (Mod)	Det 25	Det 25A	Det 36	Det 38B	HOV STRIPING DETAIL			CAR	POOL	ONLY	◇ (DIAMOND SYMBOL)	TYPE VI ARROW	DIAGONAL	CHEVRON															
				TYPE A (NON-REFLECTIVE)	TYPE G/C (RETROREFLECTIVE)	TYPE H (RETROREFLECTIVE)	TYPE H (RETROREFLECTIVE)	TYPE G (RETROREFLECTIVE)	TYPE G (RETROREFLECTIVE)	4" DOUBLE YELLOW TYPE H (RETROREFLECTIVE)	4" DOUBLE YELLOW TYPE H (RETROREFLECTIVE)	8" (BROKEN 36-12) TYPE G (RETROREFLECTIVE)								EA	EA	EA	SQFT	SQFT	SQFT	SQFT	SQFT	SQFT						
1	105	R11.10	STATE STREET UC	71	20	10						64								42														
2	105	R11.56	LONG BEACH BOULEVARD UC	194	50	26						101		26	17	23	22	33																
5	405	20.16	EL SEGUNDO OH	58	16	6								22																				
7	405	R21.32	IMPERIAL HIGHWAY ON-RAMP OC	8	3		15																											
8	405	21.74	LENNOX BOULEVARD UC	121	32	8	6	14	14				28																					22
10	405	25.99	N405-W90 CONNECTOR OC	79	21		40																											100
11	405	26.10	S405-W90 CONNECTOR OC				8																											
12	405	27.20	CULVER BOULEVARD UC	120	32	10						60		10	34	46	22	11																
13	405	27.45	WASHINGTON BOULEVARD UC			2						10																						
14	605	R4.71	DAIRY VALLEY OH	26	8	4		6					12																					25
15	605	R8.23	HOXIE OH			2							3																					
SUBTOTAL				677	182	68	69	20	14		235	65	36	51	69	44	44	42			125	22												
TOTAL														1,366							397													

PAVEMENT DELINEATION QUANTITIES

PDQ-2

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans MAINTENANCE ENGINEERING

FUNCTIONAL SUPERVISOR: MD MUSA
 CALCULATED/DESIGNED BY: KEVIN KWAN
 CHECKED BY: MD MUSA
 REVISED BY: DATE REVISION

LAST REVISION DATE PLOTTED => 27-MAR-2013
 03-25-13 TIME PLOTTED => 13:36

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans MAINTENANCE ENGINEERING

FUNCTIONAL SUPERVISOR
 MD MUSA

CALCULATED/DESIGNED BY
 KEVIN KWAN

CHECKED BY
 MD MUSA

REVISOR BY
 KEVIN KWAN

DATE REVISION
 DATE REVISION

PAVEMENT DELINEATION QUANTITIES												
LOCATION (No.)	ROUTE	POST MILE	DESCRIPTION	PAVEMENT MARKER							HOV STRIPING DETAIL	
				NON-REFLECTIVE	RETROREFLECTIVE							
				Det 13/14 (Mod)	Det 13/14 (Mod)	Det 25	Det 25A	Det 36	Det 38B			
				TYPE A	TYPE G/C (RETROREFLECTIVE)	TYPE H (RETROREFLECTIVE)	TYPE H (RETROREFLECTIVE)	TYPE G (RETROREFLECTIVE)	TYPE G (RETROREFLECTIVE)	4" DOUBLE YELLOW TYPE H (RETROREFLECTIVE)	4" DOUBLE YELLOW TYPE H (RETROREFLECTIVE)	8" (BROKEN 36-12) TYPE G (RETROREFLECTIVE)
	EA	EA	EA	EA	EA	EA	EA	EA	EA			
1	105	R11.10	STATE STREET UC	71	20	10				64		
2	105	R11.56	LONG BEACH BOULEVARD UC	194	50	26				101		26
5	405	20.16	EL SEGUNDO OH	58	16	6					22	
7	405	R21.32	IMPERIAL HIGHWAY ON-RAMP OC	8	3		15					
8	405	21.74	LENNOX BOULEVARD UC	121	32	8	6	14	14		28	
10	405	25.99	N405-W90 CONNECTOR OC	79	21		40					
11	405	26.10	S405-W90 CONNECTOR OC				8					
12	405	27.20	CULVER BOULEVARD UC	120	32	10				60		10
13	405	27.45	WASHINGTON BOULEVARD UC			2				10		
14	605	R4.71	DAIRY VALLEY OH	26	8	4		6			12	
15	605	R8.23	HOXIE OH			2					3	
SUBTOTAL				677	182	68	69	20	14	235	65	36
TOTAL				677	689							

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	16	38

Kevin Kwan 2-12-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

PAVEMENT DELINEATION QUANTITIES

PDQ-4

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	17	38

REGISTERED CIVIL ENGINEER	12-7-12	DATE
3-25-13	PLANS APPROVAL DATE	





PROFESSIONAL ENGINEER	Gurinderpal Bhullar
No.	C48815
Exp.	9-30-14
CIVIL	

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

NOTES:

Unless otherwise specified in the special provisions, all temporary warning signs shall have black legend on orange background.

California code are designated by (CA). Otherwise, Federal (MUTCD) codes are shown.



NOTES:

- Median lane closures shall conform to the details for outside lane closures except that C20 (CA) (Lt) signs shall be used.
- At least one person shall be assigned to provide full time maintenance of traffic control devices for lane closures.
- Duplicate sign installations are not required:
 - On opposite shoulder if at least one-half of the available lanes remain open to traffic.
 - In the median if the width of the median shoulder is less than 8' and the outside lanes are to be closed.
- Each advance warning sign on each side of the roadway shall be equipped with at least two flags for daytime closure. Each flag shall be at least 16" x 16" in size and shall be orange or fluorescent red-orange in color. Flashing beacons shall be placed at the locations indicated for lane closure during hours of darkness.
- A C14 (CA) "END ROAD WORK" sign, as appropriate, shall be placed at the end of the lane closure unless the end of work area is obvious or ends within a larger project's limits.
- If the W20-1 sign would follow within 2000' of a stationary W20-1 or C11 (CA) "ROAD WORK NEXT _____ MILES", use a C20 (CA) sign for the first advance warning sign.
- Place a C30 (CA) sign every 2000' throughout length of lane closure.
- One flashing arrow sign for each lane closed. The first flashing arrow sign shall be Type I. All others may be either Type I or Type II.
- A minimum 1500' of sight distance shall be provided where possible for vehicles approaching the first flashing arrow sign. Lane closures shall not begin at top of crest vertical curve or on a horizontal curve.
- All cones used for lane closures during the hours of darkness shall be fitted with retroreflective bands (or sleeves) as specified in the specifications.
- Portable delineators, placed at one-half the spacing indicated for traffic cones may be used instead of cones for daytime closures only.
- Unless otherwise specified in the special provisions, a minimum of 3 cones shall be placed transversely across each closed lane and shoulder at each location where a taper across a traffic lane ends and every 2000' as shown on the "Lane Closure" detail. Two Type II barricades may be used instead of the 3 cones. The transverse alignment of the cones or barricades on the closed shoulder may be shifted from the transverse alignment to provide access to the work.
- Unless otherwise specified in the special provisions, the 1700' tangent shown along lane lines shall be used between the 1000' tapers required for each closed traffic lane.
- Unless otherwise specified in the special provisions, the G84 (CA) and W4-1 signs shall be used as shown.
- When specified in the special provisions, a W4-2 "LANE ENDS" symbol sign is to be used in place of the C20 (CA) "RIGHT LANE CLOSED AHEAD" sign.
- The W4-2 "LANE ENDS" symbol sign shown at this location is to be used where the W4-2 sign is used as advance warning as described in Note 15.

SIGN PANEL SIZE (Min)

- A 48" x 48"
- B 54" x 48"

LEGEND

- TRAFFIC CONE
- TRAFFIC CONE (OPTIONAL TAPER)
- † TEMPORARY SIGN
- ⊛ FLASHING ARROW SIGN (FAS)
- ⊞ FAS SUPPORT OR TRAILER
- ⊛ PORTABLE FLASHING BEACON

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

**TRAFFIC CONTROL SYSTEM
FOR LANE CLOSURE ON
FREEWAYS AND EXPRESSWAYS**

NO SCALE

TCS-1

REVISOR BY
DATE

CALCULATED/DESIGNED BY
CHECKED BY

FUNCTIONAL SUPERVISOR

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans

TYPICAL RAMP CLOSURES

SIGN PANEL SIZE (Min)

- A 48" x 48"
- B 48" x 30"
- C 30" x 30"
- D 48" x 48" - SPEED OF 50 mph OR MORE
36" x 36" - SPEED LESS THAN 50 mph
- E 48" x 36"

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	18	38


REGISTERED CIVIL ENGINEER
 12-7-12 DATE
 3-25-13 PLANS APPROVAL DATE
 Gurinderpal Bhullar
 No. C48815
 Exp. 9-30-14
 CIVIL
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

LEGEND


- TRAFFIC CONE
- † TEMPORARY SIGN
- ‡ BARRICADES

NOTES:


- Barricades shall be Type I, II, or III for closures lasting one week or less and Type III for closures lasting longer than one week.
- In addition to placing the C19 (CA) "RAMP CLOSED AHEAD" and C30 (CA) "RAMP CLOSED" signs, black on orange overlay plates with the word "CLOSED" may be mounted, as directed by the Engineer, on all guide signs that refer to the closed ramp. The letter size on the overlay shall be the same as the guide sign.
- Each advance C19 (CA) "RAMP CLOSED AHEAD" sign shall be equipped with at least two flags for daytime closure. Each flag shall be at least 16" x 16" in size and shall be orange or fluorescent red-orange in color.
- All cones used for ramp closures during the hours of darkness shall be fitted with retroreflective bands (or sleeves) as specified in the specifications.
- Portable delineators, placed at one-half the spacing indicated for traffic cones, may be used instead of cones for daytime ramp closures only.
- At least one person shall be assigned to provide full time maintenance of traffic control devices, unless otherwise directed by the Engineer.
- The existing "EXIT" sign in the gore area shall be covered during ramp closures.




EXIT RAMP OR CONNECTOR



EXIT RAMP OR CONNECTOR WITH ADDITIONAL LANE



ENTRANCE RAMP WITH TURNING POCKETS



ENTRANCE RAMP WITHOUT TURNING POCKETS

NOTES:

- Unless otherwise specified in the special provisions, all temporary warning signs shall have black legend on orange background.
- California code are designated by (CA). Otherwise, Federal (MUTCD) codes are shown.

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL SYSTEM FOR RAMP CLOSURE

NO SCALE

TCS-2

REVISOR BY
DATE

CALCULATED/DESIGNED BY
CHECKED BY



FUNCTIONAL SUPERVISOR

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	19	38

REGISTERED CIVIL ENGINEER: *Gurinderpal Bhullar* 12-7-12 DATE
 3-25-13 PLANS APPROVAL DATE
 No. C48815 Exp. 9-30-14 CIVIL
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



SIGN PANEL SIZE (Min)

- A 66" x 36"
- B 54" x 42"

LEGEND

- V1 SIGN VEHICLE
- V2 SHADOW VEHICLE
- V3 WORK/APPLICATION VEHICLE
- FLASHING ARROW SIGN (FAS)
- CMS CHANGEABLE MESSAGE SIGN
- TMA TRUCK-MOUNTED ATTENUATOR

MOVING LANE CLOSURE ON MEDIAN LANE OR OUTSIDE LANE OF MULTILANE HIGHWAYS

NOTES:

- Either a changeable message sign or a SC10 (CA) sign panel and a Type II flashing arrow sign shall be mounted on the rear of sign vehicle V1. A Type II flashing arrow sign shall be mounted on the rear of sign vehicle V1 and used with the SC10 (CA) sign panel. A Type II flashing arrow sign will not be required with the changeable message sign provided the flashing arrow sign symbol is displayed on the changeable message sign board. The changeable message sign shall be sequenced to show the "ROAD WORK AHEAD" message first, followed by the "LANE CLOSED AHEAD" message and then the flashing arrow sign symbol. For median lane closure, the flashing arrow sign symbol shall be reversed with the arrowhead on the right.
- If traffic queues develop, sign vehicle V1 should be positioned upstream from the end of queue. Sign vehicle V1 shall be positioned where highly visible when shoulders are not available.
- A minimum sight distance of 1500' should be provided in advance of sign vehicle V1.
- Sign vehicle V1 should remain at the beginning of horizontal or vertical curves until the other vehicles (V2 and V3) are far enough beyond the curve to resume the minimum sight distance of 1500'.
- Vehicle-mounted sign panels shall be Type III, IV, VII, VIII or IX retroreflective sheeting, black on white, black on orange, or black on fluorescent orange, with 6" minimum series D letters per Caltrans sign specifications.
- Gross Vehicle Weight of shadow vehicle V2 shall be a minimum of 20,000 pounds and shall be equipped with a truck-mounted attenuator. The sign panel shown and a Type II flashing arrow sign shall be mounted on the rear of shadow vehicle V2. For median lane closure the flashing arrow sign symbol shall be displayed with the arrowhead on the right.
- All vehicles used for lane closures shall be equipped with two-way radios, and the vehicle operators shall maintain communication during the work or application operation.
- Where sufficient shoulder width is not available, sign vehicle V1 may encroach into the traffic lane staying as close to the edge of shoulder as practicable. Both V1 and V2 shall be equipped with a truck-mounted attenuator. The Gross Vehicle Weight of V1 and V2 shall be at least 20,000 pounds, respectively.
- When multiple work vehicles are used in close proximity to each other, only one shadow vehicle is required, and spacing between work vehicles shall be minimized in order to deter traffic from entering the closed lane.

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

**TRAFFIC CONTROL SYSTEM
FOR MOVING LANE CLOSURE
ON MULTILANE HIGHWAYS
(OUTSIDE AND MEDIAN LANES)**

NO SCALE

TCS-3


STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
 Et Caltrans®
 FUNCTIONAL SUPERVISOR
 CALCULATED/DESIGNED BY
 CHECKED BY
 REVISED BY
 DATE REVISED

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	20	38

REGISTERED CIVIL ENGINEER *Gurinderpal Bhullar* 12-7-12 DATE
 No. C48815
 Exp. 9-30-14
 CIVIL

3-25-13
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



- LEGEND**
- V1 SIGN VEHICLE
 - V2 SHADOW VEHICLE
 - V3 WORK/APPLICATION VEHICLE
 - FLASHING ARROW SIGN (FAS) IN FLASHING DOUBLE ARROW MODE
 - CMS CHANGEABLE MESSAGE SIGN
 - TMA TRUCK-MOUNTED ATTENUATOR

MOVING LANE CLOSURE ON INTERIOR LANE OF MULTILANE HIGHWAYS

NOTES:

1. A changeable message sign shall be mounted on the rear of sign vehicle V1. The changeable message sign shall be sequenced to show the "ROAD WORK AHEAD" message first, followed by the "INTERIOR LANE CLOSED" message. The message "CENTER LANE CLOSED" may be used in place of the "INTERIOR LANE CLOSED" message.
2. If traffic queues develop, sign vehicle V1 should be positioned upstream from the end of queue. Sign vehicle V1 shall be positioned where highly visible when shoulders are not available.
3. A minimum sight distance of 1500' should be provided in advance of sign vehicle V1.
4. Sign vehicle V1 should remain at the beginning of horizontal or vertical curves until the other vehicles (V2 and V3) are far enough beyond the curve to resume the minimum sight distance of 1500'.
5. Vehicle-mounted sign panels shall be Type III, IV, VII, VIII, or IX retroreflective sheeting, black on white, black on orange, or black on fluorescent orange, with 6" minimum series D letters per Caltrans sign specifications.
6. Gross Vehicle Weight of shadow vehicle V2 shall be a minimum of 20,000 pounds and shall be equipped with a truck-mounted attenuator. The sign panel shown and a Type II flashing arrow sign shall be mounted on the rear of shadow vehicle V2.
7. All vehicles used for lane closures shall be equipped with two-way radios, and the vehicle operators shall maintain communication during the work or application operation.
8. All vehicles shall be equipped with flashing or rotating amber lights.
9. Where sufficient shoulder width is not available, sign vehicle V1 may encroach into the traffic lane staying as close to the edge of shoulder as practicable. Both V1 and V2 shall be equipped with a truck-mounted attenuator. The Gross Vehicle Weight of V1 and V2 shall be at least 20,000 pounds, respectively.
10. When multiple work vehicles are used in close proximity to each other, only one shadow vehicle is required, and spacing between work vehicles shall be minimized in order to deter traffic from entering the closed lane.

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

**TRAFFIC CONTROL SYSTEM
FOR MOVING LANE CLOSURE
ON MULTILANE HIGHWAYS
(INTERIOR LANES)**


NO SCALE **TCS-4**

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
 Functional Supervisor
 Calculated/Designed By
 Checked By
 Revised By
 Date Revised
 USERNAME => s114640
 DGN FILE => tcs16.dgn




LAST REVISION | DATE PLOTTED => 10-DEC-2012
 00-00-00 TIME PLOTTED => 09:45


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	21	38
<i>Roberta L. McLaughlin</i> REGISTERED CIVIL ENGINEER April 20, 2012 PLANS APPROVAL DATE					
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.					




TO ACCOMPANY PLANS DATED 3-25-13




1'-0" GRID 1'-0"
A=25 ft²
TYPE I 18'-0" ARROW




1'-0" GRID 1'-0"
A=31 ft²
TYPE I 24'-0" ARROW




1'-0" GRID 1'-0"
A=14 ft²
TYPE I 10'-0" ARROW




1'-0" GRID 1'-0"
A=15 ft²
TYPE IV (L) ARROW
(For Type IV (R) arrow, use mirror image)




1'-0" GRID 20°
A=42 ft²
TYPE VI ARROW
Right lane drop arrow
(For left lane, use mirror image)




6" GRID 6"
A=3.5 ft²
BIKE LANE ARROW



1'-0" GRID 1'-0"
A=36 ft²
TYPE VIII ARROW



1'-0" GRID 1'-0"
A=27 ft²
TYPE VII (L) ARROW
(For Type VII (R) arrow, use mirror image)



A=33 ft²
TYPE V ARROW

NOTE:
Minor variations in dimensions may be accepted by the Engineer.


STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION
**PAVEMENT MARKINGS
ARROWS**
NO SCALE

RSP A24A DATED APRIL 20, 2012 SUPERSEDES STANDARD PLAN A24A DATED MAY 20, 2011 - PAGE 13 OF THE STANDARD PLANS BOOK DATED 2010.


REVISED STANDARD PLAN RSP A24A

2010 REVISED STANDARD PLAN RSP A24A


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	22	38
<i>Roberta L. McLaughlin</i> REGISTERED CIVIL ENGINEER					
October 19, 2012 PLANS APPROVAL DATE					
<small>THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.</small>					
REGISTERED PROFESSIONAL ENGINEER Roberta L. McLaughlin No. C40375 Exp. 3-31-13 CIVIL STATE OF CALIFORNIA					




BIKE LANE SYMBOL WITHOUT PERSON




BIKE LANE SYMBOL WITH PERSON






INTERNATIONAL SYMBOL OF ACCESSIBILITY (ISA) MARKING




DIAMOND SYMBOL




SHARED ROADWAY BICYCLE MARKING



NUMERALS



BICYCLE LOOP DETECTOR SYMBOL



SHARED ROADWAY BICYCLE MARKING

STATE OF CALIFORNIA
 DEPARTMENT OF TRANSPORTATION
PAVEMENT MARKINGS SYMBOLS AND NUMERALS
 NO SCALE

RSP A24C DATED OCTOBER 19, 2012 SUPERSEDES STANDARD PLAN A24C DATED MAY 20, 2011 - PAGE 15 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP A24C

2010 REVISED STANDARD PLAN RSP A24C


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	23	38

Registered Professional Engineer
 Roberta L. McLaughlin
 No. C40375
 Exp. 3-31-13
 CIVIL
 STATE OF CALIFORNIA

July 20, 2012
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


TO ACCOMPANY PLANS DATED 3-25-13




A=24 ft²




A=27 ft²




A=21 ft²




A=22 ft²




A=14 ft²




A=23 ft²




A=24 ft²



A=20 ft²





A=16 ft²




A=17 ft²


WORD MARKINGS			
ITEM	ft ²	ITEM	ft ²
LANE	24	NO	14
POOL	23	BIKE	21
CAR	17	BUS	20
CLEAR	27	ONLY	22
KEEP	24	FWY	16



A=2 ft²
See Notes 6 and 7



LIMIT LINE (STOP LINE)



DIRECTION OF TRAVEL
YIELD LINE

NOTES:

1. If a message consists of more than one word, it should read "UP", i.e., the first word should be nearest the driver.
2. The space between words should be at least four times the height of the characters for low speed roads, but not more than ten times the height of the characters. The space may be reduced appropriately where there is limited space because of local conditions.
3. Minor variations in dimensions may be accepted by the Engineer.
4. Portions of a letter, number or symbol may be separated by connecting segments not to exceed 2" in width.
5. The words "NO PARKING" pavement marking is to be used for parking facilities. For typical locations of markings, see Standard Plans A90A and A90B.
6. The words "NO PARKING", shall be painted in white letters no less than 1'-0" high on a contrasting background and located so that it is visible to traffic enforcement officials.

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION
**PAVEMENT MARKINGS
WORDS, LIMIT AND YIELD LINES**
NO SCALE

RSP A24E DATED JULY 20, 2012 SUPERSEDES STANDARD PLAN A24E
DATED MAY 20, 2011 - PAGE 17 OF THE STANDARD PLANS BOOK DATED 2010.

REVISED STANDARD PLAN RSP A24E

2010 REVISED STANDARD PLAN RSP A24E

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	24	38
 REGISTERED CIVIL ENGINEER DATE 02-20-13					
3-25-13 PLANS APPROVAL DATE					
The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.					

LEGEND:


- Indicates existing.
- Indicates direction of traffic.
-  Indicates limits of prepare concrete bridge deck surface, furnish and place new 3/4" thick min polyester concrete overlay. Prior to placing new polyester concrete overlay, remove unsound concrete and patch with rapid setting concrete. Polyester concrete shall be placed in one lift. Survey grades of the existing bridge deck surface shall be provided prior to placing the polyester concrete overlay.

NOTE:

For deck repair and spall repair detail, see "MISCELLANEOUS DETAILS NO. 2" sheet.

STANDARD PLANS DATED 2010

SHEET NO.	TITLE
A10A	ABBREVIATIONS (SHEET 1 OF 3)
A10B	ABBREVIATIONS (SHEET 2 OF 3)
A10C	LISTED SYMBOLS (SHEET 1 OF 2)
A10D	LISTED SYMBOLS (SHEET 2 OF 2)
A10E	LINES AND SYMBOLS (SHEET 3 OF 3)
B6-21	JOINT SEALS (MAXIMUM MOVEMENT RATING = 2")





INDEX TO PLANS

SHEET NO.	TITLE
1	GENERAL PLAN NO. 1
2	GENERAL PLAN NO. 2
3	GENERAL PLAN NO. 3
4	GENERAL PLAN NO. 4
5	GENERAL PLAN NO. 5
6	GENERAL PLAN NO. 6
7	GENERAL PLAN NO. 7
8	GENERAL PLAN NO. 8
9	GENERAL PLAN NO. 9
10	GENERAL PLAN NO. 10
11	GENERAL PLAN NO. 11
12	GENERAL PLAN NO. 12
13	MISCELLANEOUS DETAILS NO. 1
14	MISCELLANEOUS DETAILS NO. 2
15	STRUCTURE APPROACH TYPE R(30D)

STATE STREET UC #53-2662
QUANTITIES

	LUMP SUM
PUBLIC SAFETY PLAN	
RAPID SETTING CONCRETE (PATCH)	80 CF
REMOVE CONCRETE DECK SURFACE	31,280 SQFT
REMOVE UNSOUND CONCRETE	80 CF
PREPARE CONCRETE BRIDGE DECK SURFACE	31,500 SQFT
FURNISH POLYESTER CONCRETE OVERLAY	2,000 CF
PLACE POLYESTER CONCRETE OVERLAY	31,500 SQFT



SECTION A-A
NO SCALE

* Limits of remove concrete surfacing 0 inch min to 3/4 inch maximum full width. Grind flush to conform with existing profile.

NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITIES FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.

 DESIGN ENGINEER	DESIGN	BY Gerald Joo	CHECKED Ramesh Patel	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	BRIDGE NO.	ROUTES 105, 405 & 605 BRIDGES GENERAL PLAN NO. 1					
	DETAILS	BY Clayton Tom	CHECKED Gerald Joo	LAYOUT	BY Clayton Tom		CHECKED Gerald Joo		Various				
	QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel	SPECIFICATIONS	BY Steven Seifert		CHECKED Steven Seifert		Varies				
STRUCTURES MAINTENANCE GENERAL PLAN SHEET (ENGLISH) (REV. 09-01-10)						ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	UNIT: 3489	PROJECT NUMBER & PHASE: 0712000053 1	CONTRACT NO.: 07-1W4004	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 01	OF 15

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	25	38
 REGISTERED CIVIL ENGINEER DATE 02-20-13					
3-25-13 PLANS APPROVAL DATE					
The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.					

LEGEND:

- Indicates existing.
- ⇒ Indicates direction of traffic.





Indicates limits of prepare concrete bridge deck surface, furnish and place new 3/4" thick min polyester concrete overlay. Prior to placing new polyester concrete overlay, remove unsound concrete and patch with rapid setting concrete. Polyester concrete shall be placed in one lift. Survey grades of the existing bridge deck surface shall be provided prior to placing the polyester concrete overlay.

NOTE:

For deck damage repair and spall repair detail, see "MISCELLANEOUS DETAILS NO. 2" sheet.

LONG BEACH BOULEVARD UC #53-2493
QUANTITIES

PUBLIC SAFETY PLAN	LUMP SUM
RAPID SETTING CONCRETE (PATCH)	225 CF
REMOVE CONCRETE DECK SURFACE	88,200 SQFT
REMOVE UNSOUND CONCRETE	225 CF
PREPARE CONCRETE BRIDGE DECK SURFACE	88,500 SQFT
FURNISH POLYESTER CONCRETE OVERLAY	5,500 CF
PLACE POLYESTER CONCRETE OVERLAY	88,500 SQFT



SECTION A-A

NO SCALE

* Limits of remove concrete surfacing 0 inch min to 3/4 inch maximum full width. Grind flush to conform with existing profile.

NOTE:

For deck repair detail overlay see "MISCELLANEOUS DETAILS NO. 2" sheet.

LONG BEACH BOULEVARD UC

Br No. 53-2493, Rte 105, PM R11.56
Scale 1"=40'




NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITIES FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.

TONY D. BRAKE DESIGN ENGINEER	DESIGN	BY Gerald Joo	CHECKED Ramesh Patel	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	BRIDGE NO.	ROUTES 105, 405 & 605 BRIDGES GENERAL PLAN NO. 2		
	DETAILS	BY Clayton Tom	CHECKED Gerald Joo	LAYOUT	BY Clayton Tom		Various			
	QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel	SPECIFICATIONS	BY Steven Seifert		Varies			
STRUCTURES MAINTENANCE GENERAL PLAN SHEET (ENGLISH) (REV. 09-01-10)						ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	UNIT: 3489 PROJECT NUMBER & PHASE: 0712000053 1 CONTRACT NO.: 07-1W4004	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES 07-28-12 11-28-12 01-28-13 02-20-13	SHEET 02 OF 15

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	26	38
 REGISTERED CIVIL ENGINEER DATE 02-20-13					
3-25-13 PLANS APPROVAL DATE			The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.		

LEGEND:

- Indicates existing.
- ⇒ Indicates direction of traffic.
- Indicates limits of clean expansion joint and placement of new joint seal.




VAN NESS AVENUE UC

Br No. 53-1174, Rte 405, PM 14.92
 Scale 1"=20'

VAN NESS AVENUE UC #53-1174
 QUANTITIES

CLEAN EXPANSION JOINT	294 LF
JOINT SEAL (MR 1")	294 LF



YUKON AVENUE UC

Br No. 53-1177, Rte 405, PM 15.98
 Scale 1"=20'

YUKON AVENUE UC #53-1177
 QUANTITIES

CLEAN EXPANSION JOINT	340 LF
JOINT SEAL (MR 1/2")	340 LF

NOTE:
 THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITIES FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.

 DESIGN ENGINEER	DESIGN	BY Gerald Joo	CHECKED Ramesh Patel	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD
	DETAILS	BY Clayton Tom	CHECKED Gerald Joo	LAYOUT	BY Clayton Tom
	QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel	SPECIFICATIONS	BY Steven Seifert

STATE OF CALIFORNIA
 DEPARTMENT OF TRANSPORTATION

DIVISION OF MAINTENANCE
 STRUCTURE MAINTENANCE DESIGN

BRIDGE NO. Various
 POST MILE Varies

**ROUTES 105, 405 & 605 BRIDGES
 GENERAL PLAN NO. 3**

STRUCTURES MAINTENANCE GENERAL PLAN SHEET (ENGLISH) (REV. 09-01-10)

ORIGINAL SCALE IN INCHES FOR REDUCED PLANS



UNIT: 3489
 PROJECT NUMBER & PHASE: 0712000053 1 CONTRACT NO.: 07-1W4004


DISREGARD PRINTS BEARING EARLIER REVISION DATES

REVISION DATES	SHEET	OF
01-28-12 01-28-12 01-28-13 02-20-13	03	15

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	27	38
 REGISTERED CIVIL ENGINEER DATE 02-20-13					
3-25-13			PLANS APPROVAL DATE		
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.</small>					


LEGEND:

- Indicates existing.
- ⇒ Indicates direction of traffic.
-  Indicates limits of prepare concrete bridge deck surface and treat bridge deck with high molecular weight methacrylate.
- Indicates limits of clean expansion joint and placement of new joint seal.



EL SEGUNDO OH
 Br No. 53-2387K, Rte 405, PM 20.16
 Scale 1"=20'

EL SEGUNDO OH #53-2387K	
QUANTITIES	
PUBLIC SAFETY PLAN	LUMP SUM
PREPARE CONCRETE BRIDGE DECK SURFACE	3,500 SQFT
TREAT BRIDGE DECK	3,500 SQFT
FURNISH BRIDGE DECK TREATMENT MATERIAL	45 GAL



129TH STREET OH
 Br No. 53-1238, Rte 405, PM 20.18
 No Scale

129TH STREET OH #53-1238	
QUANTITIES	
CLEAN EXPANSION JOINT	23 LF
JOINT SEAL (MR 1/2")	23 LF

NOTE:
 THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITIES FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.

 DESIGN ENGINEER	DESIGN	BY Gerald Joo	CHECKED Ramesh Patel	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD
	DETAILS	BY Clayton Tom	CHECKED Gerald Joo	LAYOUT	BY Clayton Tom
	QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel	SPECIFICATIONS	BY Steven Seifert

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF MAINTENANCE	BRIDGE NO.
	STRUCTURE MAINTENANCE DESIGN	Various
		Varies


ROUTES 105, 405 & 605 BRIDGES GENERAL PLAN NO. 4	
PROJECT NUMBER & PHASE: 0712000053 1 CONTRACT NO.: 07-1W4004	SHEET 04 OF 15

USERNAME => s117283 DATE PLOTTED => 01-MAR-2013 TIME PLOTTED => 06:09

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	28	38
 REGISTERED CIVIL ENGINEER DATE 02-20-13					
3-25-13			PLANS APPROVAL DATE		
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.</small>					

LEGEND:

- Indicates existing.
- ⇒ Indicates direction of traffic.
-  Indicates limits of prepare concrete bridge deck surface and treat bridge deck with high molecular weight methacrylate.



IMPERIAL HIGHWAY ON-RAMP OC (CONNECTOR)

Br No. 53-2434T, Rte 405, PM R21.32
Scale 1"=20'



IMPERIAL HIGHWAY ON-RAMP OC (CONNECTOR)
QUANTITIES

PUBLIC SAFETY PLAN	LUMP SUM
PREPARE CONCRETE BRIDGE DECK SURFACE	10,500 SQFT
TREAT BRIDGE DECK	10,500 SQFT
FURNISH BRIDGE DECK TREATMENT MATERIAL	135 GAL

NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITIES FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.


 DESIGN ENGINEER	DESIGN	BY Gerald Joo	CHECKED Ramesh Patel	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	BRIDGE NO.	ROUTES 105, 405 & 605 BRIDGES GENERAL PLAN NO. 5					
	DETAILS	BY Clayton Tom	CHECKED Gerald Joo	LAYOUT	BY Clayton Tom		CHECKED Gerald Joo		POST MILE				
	QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel	SPECIFICATIONS	BY Steven Seifert		PLANS AND SPECS COMPARED Steven Seifert		Varies				
STRUCTURES MAINTENANCE GENERAL PLAN SHEET (ENGLISH) (REV. 09-01-10)						ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	UNIT: 3489	PROJECT NUMBER & PHASE: 0712000053 1	CONTRACT NO.: 07-1W4004	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 05	OF 15

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	29	38

02-20-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE
 No. C65380
 Exp. 09/30/13
 CIVIL
 STATE OF CALIFORNIA
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

LEGEND:

- Indicates existing.
- ⇒ Indicates direction of traffic.
- ▨ Indicates limits of prepare concrete bridge deck surface and treat bridge deck with high molecular weight methacrylate.



LENNOX BOULEVARD UC #53-1242
QUANTITIES

PUBLIC SAFETY PLAN	LUMP SUM
PREPARE CONCRETE BRIDGE DECK SURFACE	40,000 SQFT
TREAT BRIDGE DECK	40,000 SQFT
FURNISH BRIDGE DECK TREATMENT MATERIAL	500 GAL

LENNOX BOULEVARD UC

Br No. 53-1242, Rte 405, PM 21.74
No Scale




NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITIES FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.

TONY D. BRAKE DESIGN ENGINEER	DESIGN	BY Gerald Joo	CHECKED Ramesh patel	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD
	DETAILS	BY Clayton Tom	CHECKED Gerald Joo	LAYOUT	BY Clayton Tom
	QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel	SPECIFICATIONS	BY Steven Seifert

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF MAINTENANCE STRUCTURE MAINTENANCE DESIGN	BRIDGE NO. Various POST MILE Varies
--	---	--


ROUTES 105, 405 & 605 BRIDGES GENERAL PLAN NO. 6	
---	--

USERNAME => s117283 DATE PLOTTED => 01-MAR-2013 TIME PLOTTED => 06:09

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	30	38
			02-20-13		
REGISTERED CIVIL ENGINEER			DATE		
3-25-13			PLANS APPROVAL DATE		
					
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.</small>					

LEGEND:

- Indicates existing.
- ⇒ Indicates direction of traffic.
- Indicates limits of clean expansion joint and placement of new joint seal.



LA CIENEGA BOULEVARD NORTHBOUND OC

Br No. 53-1249, Rte 405, PM 23.64
Scale: 1"=30'



LA CIENEGA BOULEVARD NORTHBOUND OC #53-1249
QUANTITIES

CLEAN EXPANSION JOINT	100 LF
JOINT SEAL (MR 1")	100 LF


NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITIES FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.

 TONY D. BRAKE DESIGN ENGINEER	DESIGN	BY Gerald Joo	CHECKED Ramesh Patel	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	BRIDGE NO.	ROUTES 105, 405 & 605 BRIDGES GENERAL PLAN NO. 7					
	DETAILS	BY Clayton Tom	CHECKED Gerald Joo	LAYOUT	BY Clayton Tom		CHECKED Gerald Joo		POST MILE				
	QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel	SPECIFICATIONS	BY Steven Seifert		CHECKED Steven Seifert		PLANS AND SPECS COMPARED	Varies			
STRUCTURES MAINTENANCE GENERAL PLAN SHEET (ENGLISH) (REV. 09-01-10)						ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	UNIT: 3489	PROJECT NUMBER & PHASE: 0712000053 1	CONTRACT NO.: 07-1W4004	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 07	OF 15

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	31	38
 REGISTERED CIVIL ENGINEER DATE 02-20-13					
PLANS APPROVAL DATE 3-25-13					
No. C65380 Exp. 09/30/13 CIVIL					
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.</small>					

LEGEND:

- Indicates existing.
- ⇒ Indicates direction of traffic.
- ▨ Indicates limits of prepare concrete bridge deck surface and treat bridge deck with methacrylate.
- Indicates limits of clean expansion joint and placement of new joint seal.




S405-W90 CONNECTOR OC

Br No. 53-1974F, Rte 405, PM 26.10
 Scale 1"=20'

S405-W90 CONNECTOR OC #53-1974F
 QUANTITIES

PUBLIC SAFETY PLAN	LUMP SUM
PREPARE CONCRETE BRIDGE DECK SURFACE	5,000 SQFT
TREAT BRIDGE DECK	5,000 SQFT
FURNISH BRIDGE DECK TREATMENT MATERIAL	65 GAL



CULVER BOULEVARD UC

Br No. 53-1259, Rte 405, PM 27.20
 Scale 1"=20'

CULVER BOULEVARD UC #53-1259
 QUANTITIES

PUBLIC SAFETY PLAN	LUMP SUM
PREPARE CONCRETE BRIDGE DECK SURFACE	28,000 SQFT
TREAT BRIDGE DECK	28,000 SQFT
FURNISH BRIDGE DECK TREATMENT MATERIAL	350 GAL
CLEAN EXPANSION JOINT	180 LF
JOINT SEAL (MR 2")	180 LF

NOTE:
 THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITIES FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.

 DESIGN ENGINEER	DESIGN	BY Gerald Joo	CHECKED Ramesh Patel	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD
	DETAILS	BY Clayton Tom	CHECKED Gerald Joo	LAYOUT	BY Clayton Tom
	QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel	SPECIFICATIONS	BY Steven Seifert

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF MAINTENANCE	BRIDGE NO.
	STRUCTURE MAINTENANCE DESIGN	Various
		Varies

ROUTES 105, 405 & 605 BRIDGES	
GENERAL PLAN NO. 8	
PROJECT NUMBER & PHASE: 0712000053 1	CONTRACT NO.: 07-1W4004

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	32	38


02-20-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE
 No. C65380
 Exp. 09/30/13
 CIVIL
 STATE OF CALIFORNIA
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

LEGEND:

- Indicates existing.
- ⇒ Indicates direction of traffic.
- Indicates limits of clean expansion joint and placement of new joint seal.
- ⊖⊖⊖⊖⊖⊖ Indicates limits of placement of new joint seal.
- * Indicates limits of paving notch extension.

NOTES:

1. For approach slab details, see "STRUCTURE APPROACH TYPE R(30D)" sheet.
2. For deck damage repair detail and spall repair detail, see "MISCELLANEOUS DETAILS NO. 2" sheet.



WASHINGTON BOULEVARD UC #53-1260
QUANTITIES

RAPID SETTING CONCRETE (PATCH)	7	CF
REMOVE UNSOUND CONCRETE	7	CF
AGGREGATE BASE (APPROACH SLAB)	2	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	20	CY
PAVING NOTCH EXTENSION	11	CF
CLEAN EXPANSION JOINT	542	LF
JOINT SEAL (MR 1")	556	LF

WASHINGTON BOULEVARD UC

Br No. 53-1260, Rte 405, PM 27.45
Scale 1"=20'



NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITIES FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.


TONY D. BRAKE DESIGN ENGINEER	DESIGN	BY Gerald Joo	CHECKED Ramesh Patel	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	BRIDGE NO.	ROUTES 105, 405 & 605 BRIDGES GENERAL PLAN NO. 9				
	DETAILS	BY Clayton Tom	CHECKED Gerald Joo	LAYOUT	BY Clayton Tom		CHECKED Gerald Joo		Various			
	QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel	SPECIFICATIONS	BY Steven Seifert		CHECKED Steven Seifert		Varies			
STRUCTURES MAINTENANCE GENERAL PLAN SHEET (ENGLISH) (REV. 09-01-10)						UNIT: 3489	PROJECT NUMBER & PHASE: 0712000053 1	CONTRACT NO.: 07-1W4004	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 09	OF 15

USERNAME => s117283 DATE PLOTTED => 01-MAR-2013 TIME PLOTTED => 06:08
 FILE => 07-1w4001-a-gp09.dgn

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	33	38
 REGISTERED CIVIL ENGINEER DATE 02-20-13					
3-25-13			PLANS APPROVAL DATE		
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.</small>					

LEGEND:

- Indicates existing.
- ⇒ Indicates direction of traffic.
-  Indicates limits of prepare concrete bridge deck surface and treat bridge deck with high molecular weight methacrylate.



DAIRY VALLEY OH
 Br No. 53-1721, Rte 605, PM R4.71
 Scale 1"=20'

DAIRY VALLEY OH #53-1721	
QUANTITIES	
PUBLIC SAFETY PLAN	LUMP SUM
PREPARE CONCRETE BRIDGE DECK SURFACE	11,000 SQFT
TREAT BRIDGE DECK	11,000 SQFT
FURNISH BRIDGE DECK TREATMENT MATERIAL	140 GAL

NOTE:
 THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITIES FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.

 DESIGN ENGINEER	DESIGN	BY Gerald Joo	CHECKED Ramesh Patel	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	BRIDGE NO.	ROUTES 105, 405 & 605 BRIDGES GENERAL PLAN NO. 10				
	DETAILS	BY Clayton Tom	CHECKED Gerald Joo	LAYOUT	BY Clayton Tom		CHECKED Gerald Joo		Various			
	QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel	SPECIFICATIONS	BY Steven Seifert		CHECKED Steven Seifert		Varies			
STRUCTURES MAINTENANCE GENERAL PLAN SHEET (ENGLISH) (REV. 09-01-10)						ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	UNIT: 3489	PROJECT NUMBER & PHASE: 0712000053 1	CONTRACT NO.: 07-1W4004	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 10 OF 15

USERNAME => s117283 DATE PLOTTED => 01-MAR-2013 TIME PLOTTED => 06:08

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
08	RIV	105, 405, 605	Var	34	38


02-20-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE
 No. C65380
 Exp. 09/30/13
 CIVIL
 STATE OF CALIFORNIA
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

LEGEND:

- Indicates existing.
- ⇒ Indicates direction of traffic.
- Indicates location of existing joint seal removal and replacement of new joint seal.
- ▨ Indicates limits of prepare concrete bridge deck surface and treat bridge deck with methacrylate.
- Indicates limits of placement of new joint seal.
- * Indicates limits of paving notch extension.

NOTE:

1. For approach slab details, see "STRUCTURE APPROACH TYPE R(30D)" sheet.



N405-W90 CONNECTOR OC

Br No. 53-1838G, Rte 405, PM 25.99
No Scale

**N405-W90 CONNECTOR OC #53-1838G
QUANTITIES**

PUBLIC SAFETY PLAN	LUMP SUM
PREPARE CONCRETE BRIDGE DECK SURFACE	33,000 SQFT
TREAT BRIDGE DECK	33,000 SQFT
FURNISH BRIDGE DECK TREATMENT MATERIAL	415 GAL
AGGREGATE BASE (APPROACH SLAB)	5 CY
STRUCTURAL CONCRETE APPROACH SLAB (TYPE R)	46 CY
PAVING NOTCH EXTENSION	26 CF
CLEAN EXPANSION JOINT	230 LF
JOINT SEAL (MR 1")	80 LF
JOINT SEAL (MR 2")	184 LF

NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

TONY D. BRAKE DESIGN ENGINEER	DESIGN	BY Gerald Joo	CHECKED Ramesh Patel	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	BRIDGE NO.	ROUTE 105, 405 & 605 BRIDGES GENERAL PLAN NO. 11	
	DETAILS	BY Clayton Tom	CHECKED Gerald Joo	LAYOUT	BY Clayton Tom		CHECKED Gerald Joo		Various
	QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel	SPECIFICATIONS	BY Steven Seifert		CHECKED Steven Seifert		Varies

STRUCTURES MAINTENANCE GENERAL PLAN SHEET (ENGLISH) (REV. 09-01-10) ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0 1 2 3 UNIT: 3489 PROJECT NUMBER & PHASE: 0712000053 1 CONTRACT NO.: 07-1W4004 DISREGARD PRINTS BEARING EARLIER REVISION DATES 07-28-12 11-28-12 01-28-13 02-20-13 11 15

USERNAME => s117283 DATE PLOTTED => 01-MAR-2013 TIME PLOTTED => 06:08

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	35	38


02-20-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE
 No. C65380
 Exp. 09/30/13
 CIVIL
 STATE OF CALIFORNIA
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

LEGEND:

- Indicates existing.
- ⇒ Indicates direction of traffic.
- Indicates limits of clean expansion joint and placement of new joint seal.
- ⊖⊖⊖⊖⊖⊖ Indicates limits of placement of new joint seal.
- * Indicates limits of paving notch extension.

NOTES:

1. For approach slab details, see "STRUCTURE APPROACH TYPE R(30D)" sheet.
2. For deck damage repair detail and spall repair detail, see "MISCELLANEOUS DETAILS NO. 2" sheet.



HOXIE OH

Br No. 53-1652, Rte 605, PM R8.23
Scale: 1"=30'

**HOXIE OH #53-1652
QUANTITIES**

RAPID SETTING CONCRETE (PATCH)	4	CF
REMOVE UNSOUND CONCRETE	4	CF
AGGREGATE BASE (APPROACH SLAB)	2	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	20	CY
PAVING NOTCH EXTENSION	10	CF
CLEAN EXPANSION JOINT	630	LF
JOINT SEAL (MR 1")	435	LF
JOINT SEAL (MR 2")	207	LF

NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITIES FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.

TONY D. BRAKE DESIGN ENGINEER	DESIGN	BY Gerald Joo	CHECKED Ramesh Patel	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	BRIDGE NO.	ROUTES 105, 405 & 605 BRIDGES GENERAL PLAN NO. 12	
	DETAILS	BY Clayton Tom	CHECKED Gerald Joo	LAYOUT	BY Clayton Tom		POST MILE		
	QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel	SPECIFICATIONS	BY Steven Seifert		VARIES		
STRUCTURES MAINTENANCE GENERAL PLAN SHEET (ENGLISH) (REV. 09-01-10)						ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	UNIT: 3489 PROJECT NUMBER & PHASE: 0712000053 1 CONTRACT NO.: 07-1W4004	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES: 07-28-12, 11-28-12, 01-28-13, 02-20-13 SHEET 12 OF 15

JOINT SEAL TABLE

BRIDGE NAME	BRIDGE NUMBER	JOINT SEAL LOCATION		MINIMUM "MR" (INCHES)	APPROX LENGTH (FT)	EXISTING WATERSTOP	APPROX DEPTH TO CLEAN (INCHES)
Van Ness Ave UC	53-1174	Abut 1	PN	1	147	No	12
		Abut 4	PN	1	147	No	12
Yukon Ave UC	53-1177	Abut 1	PN	1/2	170	No	12
		Abut 4	PN	1/2	170	No	12
129TH Street OH	53-1238	Abut 1	PN	1/2	23	No	12
La Cienega Blvd NB OC	53-1249	Hinge 1	DJ	1	50	Yes	12
		Hinge 2	DJ	1	50	Yes	12
Culver Blvd UC	53-1259	Abut 1	PN	2	90	No	12
		Abut 4	PN	2	90	No	12
Washington Blvd UC	53-1260	Abut 1	PN	1	278	No	12
		Abut 2	PN	1	278	No	12
N405-W90 Conn OC	53-1838G	Abut 1	PN	1	34	No	12
		Hinge 1	DJ	2	36	Yes	12
		Hinge 2	DJ	2	56	Yes	12
		Hinge 3	DJ	2	46	Yes	12
		Hinge 4	DJ	2	46	Yes	12
		Abut 10	PN	1	46	No	12
Hoxie OH	53-1652	Abut 1	PN	1	207	No	12
		Hinge 1	DJ	2	207	Yes	12
		Abut 8	PN	1	228	No	12

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	36	38

REGISTERED CIVIL ENGINEER DATE: 02-20-13
 PLANS APPROVAL DATE: 3-25-13
 No. C65380
 Exp. 09/30/13
 CIVIL
 STATE OF CALIFORNIA
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

NOTES:

The following notes apply to JOINT SEAL TYPE A:


Install Joint Seal (MR = 1/2") or Silicone Joint Seal 3" up into curb or barrier rail on the low side of the deck where deck joint aligns with curb or barrier rail joint.

For details not shown see STANDARD PLANB6-21.

The following notes apply to JOINT SEAL TYPE B:

- Seal must satisfy both minimum Movement Rating (MR) and minimum W1 requirements.
- Minimum W1 is the calculated maximum width of the joint based on field measurements. After the joints have been cleaned, minimum W1 is to be recalculated by the Engineer.
- W1 shall be the smaller of the values determined as follows:
 - 0.85 times the manufacturer's designed minimum uncompressed width of the seal.
 - The width of the seal on the third successive test cycle of the pressure deflection test, when compressed to an average pressure of 3.0 PSI.
- Bend Type B joint seal 6 inches up into curb or rail on the low side of the deck where deck joint matches curb or rail joint.

For details not shown see STANDARD PLAN B6-21.




BARRIER RAIL


JOINT SEAL AT LOW SIDE OF DECK

Note: Details shown for illustration purposes only.


For use only where deck joint matches the sidewalk, curb or barrier rail joint.




DIAPHRAGM ABUTMENT




ABUTMENT WITH BACKWALL AND PAVING NOTCH



ABUTMENT WITH BACKWALL



HINGE



BENT OR PIER

JOINT SEAL LOCATION

NO SCALE

NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITY FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.

DESIGN BY: Gerald Joo	CHECKED: Ramesh Patel	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF MAINTENANCE STRUCTURE MAINTENANCE DESIGN	BRIDGE NO. Various	ROUTES 105, 405 & 605 BRIDGES MISCELLANEOUS DETAILS NO. 1
DETAILS BY: Clayton Tom	CHECKED: Gerald Joo			POST MILE	
QUANTITIES BY: Gerald Joo	CHECKED: Ramesh Patel			Varies	


STRUCTURES MAINTENANCE DETAIL SHEET (ENGLISH) (REV. 09-01-10) ORIGINAL SCALE IN INCHES FOR REDUCED PLANS: 0 1 2 3
 UNIT: 3489 PROJECT NUMBER & PHASE: 0712000053 1 CONTRACT NO.: 07-1W4004
 DISREGARD PRINTS BEARING EARLIER REVISION DATES
 REVISION DATES: 07-25-12, 11-26-12, 01-28-13, 02-20-13
 SHEET 13 OF 15

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	105, 405, 605	Var	37	38

02-20-13
 REGISTERED CIVIL ENGINEER DATE
 3-25-13
 PLANS APPROVAL DATE
 No. C65380
 Exp. 09/30/13
 CIVIL
 STATE OF CALIFORNIA
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.


DECK REPAIR NOTES:

- Existing reinforcement shall be protected in place during unsound concrete removal and patching operations.
- It is responsibility of the Contractor to repair any reinforcement that is accidentally cut by saw cutting operations.
- When existing transverse reinforcement is exposed in the deck surface, saw cutting may be waived with the approval of the Engineer.
- The saw cut depth shall not exceed $\frac{3}{4}$ inch or the concrete cover over the top steel reinforcing bars, whichever is less.
- Remove unsound Portland Cement concrete and unsound concrete patches to expose sound, hard concrete substrate. Replace original deck surface with rapid setting concrete patch.



DECK DAMAGE REPAIR DETAIL

Location will be determined by the Engineer. Reinforcement may be encountered during deck concrete removal and is to remain undamaged.



TYPICAL LIMITS OF DECK WORK

NO SCALE

NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL. EXISTING UTILITY FACILITIES HAVE NOT BEEN PLOTTED ON THESE PLANS.

DESIGN	BY Gerald Joo	CHECKED Ramesh Patel
DETAILS	BY Clayton Tom	CHECKED Gerald Joo
QUANTITIES	BY Gerald Joo	CHECKED Ramesh Patel

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

DIVISION OF MAINTENANCE
STRUCTURE MAINTENANCE DESIGN

BRIDGE NO.	Various
POST MILE	Varies

ROUTES 105, 405 & 605 BRIDGES
MISCELLANEOUS DETAILS NO. 2

