STATE OF CALIFORNIA
BUSINESS, TRANSPORTATION AND HOUSING AGENCY
DEPARTMENT OF TRANSPORTATION

# 2008
# CONTRACT COST DATA

## A SUMMARY OF COST BY ITEMS FOR HIGHWAY CONSTRUCTION PROJECTS

© 2008 California Department of Transportation
All Rights Reserved

# 2008
# CONTRACT COST DATA

The *Contract Cost Data* book is published annually by the Department of Transportation, Division of Engineering Services - Office Engineer, Office of Contract Awards and Services. This book includes standard contract items for major highway contracts for which bids were *awarded in 2008.* Some of the units of measure for these items were in U.S. Customary Units (English) and were converted to International System of Units (SI) for this publication. The conversion factors used for this purpose are listed in *Appendix A*. For those who wish to convert back to English units, the appropriate conversion factors are listed in *Appendix B*.

Advertised item quantities have been used as source information. Item quantities may vary from the final quantities incorporated into the completed contract. Prices shown in this tabulation are the mechanically weighted average of the awarded bidders' prices and are affected by location, time, quantity in the job and size of the item (relative to the size of the job). In this book, a six-digit item code has been assigned to each standard contract item and the items are listed numerically.

For assistance, contact Division of Engineering Services - Office Engineer, Office of Contract Awards and Services by e-mail at this address: DES-OE_Contract_Service @dot.ca.gov. The Web site address to download this book is http://www.dot.ca.gov/hq/esc/oe/awards.

Additional copies of this book may be purchased by writing to:

**STATE OF CALIFORNIA**
**DEPARTMENT OF TRANSPORTATION**
**PUBLICATION DISTRIBUTION UNIT**
**1900 Royal Oaks Drive**
**Sacramento, California 95815**
**Telephone (916) 445-3520**

# TABLE OF CONTENTS

INDEX OF ITEM DESCRIPTION ……..A1

CONTRACT ITEM COST DATA……1

APPENDIX A……371
(CONVERSION FACTORS FROM ENGLISH UNITS TO SI UNITS)

APPENDIX B……371
(CONVERSION FACTORS FROM SI UNITS TO ENGLISH UNITS)

# Index of Item Description


| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 0.9 M CHAIN LINK GATE (TYPE CL-1.8) | 802584 |
| 1 1/2" ELECTRIC REMOTE CONTROL VALVE | 206604 |
| 1 1/2" GATE VALVE | 208574 |
| 1 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208265 |
| 1 1/2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE) | 208597 |
| 1 1/2" WYE STRAINER | 208628 |
| 1 1/4" ELECTRIC REMOTE CONTROL VALVE | 206603 |
| 1 1/4" PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208264 |
| 1 1/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE) | 208596 |
| 1" ELECTRIC REMOTE CONTROL VALVE | 206602 |
| 1" GATE VALVE | 208572 |
| 1" PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208263 |
| 1" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE) | 208595 |
| 1" WYE STRAINER | 208626 |
| 1.2 M CAST-IN-DRILLED-HOLE CONCRETE PILING | 490661 |
| 1.2 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET) | 490677 |
| 1.2 M CHAIN LINK GATE (TYPE CL-1.8) | 802585 |
| 1.2 M CHAIN LINK GATE (TYPE CL-1.8, VINYL-CLAD) | 802586 |
| 1.2 M WIRE MESH GATE | 801191 |
| 1.5 M CAST-IN-DRILLED-HOLE CONCRETE PILING | 490663 |
| 1.5 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET) | 490678 |
| 1.8 M CAST-IN-DRILLED-HOLE CONCRETE PILING | 490665 |
| 1.8 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET) | 490679 |
| 1.8 M CHAIN LINK GATE (TYPE CL-1.8) | 802590 |
| 10" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT | 208739 |
| 10" CORRUGATED STEEL FLUME DOWNDRAIN | 691004 |
| 10" FLUME ANCHOR ASSEMBLY | 692364 |
| **0 - 9** | |
| 10" FLUME DOWNDRAIN | 691902 |
| 10" TAPERED INLET | 692104 |
| 100 MM CONDUIT | 208697 |
| 100 MM GALVANIZED STEEL PIPE (SUPPLY LINE) | 208024 |
| 100 MM GATE VALVE | 208494 |
| 100 MM PLASTIC PIPE (EDGE DRAIN OUTLET) | 681141 |
| 100 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208256 |
| 100 MM PLASTIC PIPE UNDERDRAIN | 680272 |
| 100 MM THERMOPLASTIC TRAFFIC STRIPE | 840561 |
| 100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 1.83 M - 0.30 M) | 840567 |
| 100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M) | 840570 |
| 100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M) | 840568 |
| 100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 5.18 M - 2.14 M) | 840571 |
| 100 MM THERMOPLASTIC TRAFFIC STRIPE (RECESSED) | 840572 |
| 100 MM THERMOPLASTIC TRAFFIC STRIPE (RECESSED) (BROKEN 5.18 M - 2.14 M) | 840559 |
| 100 MM THERMOPLASTIC TRAFFIC STRIPE (RECESSED, BROKEN 10.98 M - 3.66 M) | 840573 |
| 100 MM TWO-COMPONENT PAINT TRAFFIC STRIPE | 840575 |
| 100 MM WELDED STEEL PIPE CONDUIT (6.02 MM THICK) | 208796 |
| 1050 MM ALTERNATIVE FLARED END SECTION | 705340 |
| 1050 MM ALTERNATIVE PIPE CULVERT | 620930 |
| 1050 MM ALTERNATIVE PIPE CULVERT (TYPE B) | 620932 |
| 1050 MM CONCRETE FLARED END SECTION | 705228 |
| 1050 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | 664038 |
| 1050 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | 664039 |
| 1050 MM REINFORCED CONCRETE PIPE | 650081 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 1050 MM X 725 MM CORRUGATED STEEL PIPE ARCH (2.01 MM THICK) | 667060 |
| 1050 MM X 725 MM STEEL FLARED END PIPE ARCH SECTION | 705478 |
| 12' CHAIN LINK GATE (TYPE CL-6) | 802580 |
| 12 SINGLEMODE FIBER OPTIC CABLE | 867014 |
| 12" ALTERNATIVE FLARED END SECTION | 705307 |
| 12" ALTERNATIVE PIPE CULVERT | 620060 |
| 12" ANCHOR ASSEMBLY | 692305 |
| 12" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK) | 665112 |
| 12" CORRUGATED STEEL PIPE (.079" THICK) | 665012 |
| 12" CORRUGATED STEEL PIPE DOWNDRAIN | 690110 |
| 12" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK) | 690112 |
| 12" ENTRANCE TAPER | 692005 |
| 12" REINFORCED CONCRETE PIPE | 650010 |
| 12" SLOTTED PLASTIC PIPE | 642110 |
| 12" STEEL FLARED END SECTION | 705007 |
| 1200 MM ALTERNATIVE FLARED END SECTION | 705341 |
| 1200 MM ALTERNATIVE PIPE CULVERT | 620933 |
| 1200 MM CONCRETE FLARED END SECTION | 705229 |
| 1200 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | 664044 |
| 1200 MM PRECAST CONCRETE PIPE INLET | 707135 |
| 1200 MM PRECAST CONCRETE PIPE MANHOLE | 707247 |
| 1200 MM REINFORCED CONCRETE PIPE | 650084 |
| 1200 MM WELDED STEEL PIPE (9.53 MM THICK) | 703698 |
| 1225 MM X 825 MM CORRUGATED STEEL PIPE ARCH (2.77 MM THICK) | 667064 |
| 1225 MM X 825 MM STEEL FLARED END PIPE ARCH SECTION | 705479 |
| 1350 MM REINFORCED CONCRETE PIPE | 650086 |
| 1372 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | 561013 |
| 15 MM PLASTIC PIPE (IRRIGATION LINE) | 208214 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 15" ALTERNATIVE PIPE CULVERT | 620080 |
| 150 MM ALTERNATIVE PIPE UNDERDRAIN | 685062 |
| 150 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | 664002 |
| 150 MM FIRE HYDRANT ASSEMBLY | 993013 |
| 150 MM GATE VALVE | 208495 |
| 150 MM NON-PERFORATED PLASTIC PIPE UNDERDRAIN | 680932 |
| 150 MM PERFORATED PLASTIC PIPE UNDERDRAIN | 680931 |
| 150 MM PERFORATED STEEL PIPE UNDERDRAIN | 680461 |
| 150 MM PLASTIC PIPE | 681066 |
| 150 MM SEWER PIPE (LATERAL) | 717074 |
| 150 MM THERMOPLASTIC TRAFFIC STRIPE | 840562 |
| 150 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK) | 208797 |
| 1500 MM ALTERNATIVE PIPE CULVERT | 620940 |
| 1500 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | 664052 |
| 1500 MM CORRUGATED STEEL PIPE (3.51 MM THICK) | 664053 |
| 1500 MM PRECAST CONCRETE PIPE MANHOLE | 707249 |
| 1500 MM REINFORCED CONCRETE PIPE | 650089 |
| 1524 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | 561015 |
| 16' CHAIN LINK GATE (TYPE CL-6) | 802620 |
| 16' METAL GATE | 801364 |
| 16" CAST-IN-DRILLED-HOLE CONCRETE PILING | 490601 |
| 1600 MM X 1075 MM CORRUGATED STEEL PIPE ARCH (2.77 MM THICK) | 667070 |
| 1650 MM ALTERNATIVE PIPE CULVERT | 620943 |
| 1650 MM REINFORCED CONCRETE PIPE | 650091 |
| 18" ALTERNATIVE FLARED END SECTION | 705311 |
| 18" ALTERNATIVE PIPE CULVERT | 620100 |
| 18" ANCHOR ASSEMBLY | 692307 |
| 18" BITUMINOUS COATED DOWNDRAIN SLIP JOINT | 692237 |
| 18" CONCRETE FLARED END SECTION | 705204 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 18" CORRUGATED STEEL PIPE (.064" THICK) | 665016 |
| 18" CORRUGATED STEEL PIPE (.079" THICK) | 665017 |
| 18" CORRUGATED STEEL PIPE (.109" THICK) | 665018 |
| 18" CORRUGATED STEEL PIPE (.138" THICK) | 665075 |
| 18" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK) | 690116 |
| 18" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK) | 690117 |
| 18" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK) | 690118 |
| 18" ENTRANCE TAPER | 692007 |
| 18" REINFORCED CONCRETE PIPE | 650014 |
| 18" REINFORCED CONCRETE PIPE (CLASS III) | 650311 |
| 18" SLOTTED CORRUGATED STEEL PIPE (.079" THICK) | 665717 |
| 18" SLOTTED CORRUGATED STEEL PIPE (.168" THICK) | 665718 |
| 18" STEEL FLARED END SECTION | 705011 |
| 1800 MM REINFORCED CONCRETE PIPE | 650092 |
| 2 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208267 |
| 2 1/2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE) | 208599 |
| 2" BACKFLOW PREVENTER ASSEMBLY | 208426 |
| 2" ELECTRIC REMOTE CONTROL VALVE | 206605 |
| 2" GATE VALVE | 208575 |
| 2" PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208266 |
| 2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE) | 208598 |
| 2" WYE STRAINER | 208630 |
| 2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING | 490669 |
| 2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET) | 490680 |
| 2.4 M CAST-IN-DRILLED-HOLE CONCRETE PILING | 490671 |
| 2.4 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET) | 490681 |
| 2.4 M CHAIN LINK GATE (TYPE CL-1.8) | 802592 |
| 2.4 M PERMANENT STEEL CASING | 493487 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 2.4 M WIRE MESH GATE | 801194 |
| 20' CHAIN LINK GATE (TYPE CL-6) | 802660 |
| 20 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208249 |
| 20 MM QUICK COUPLING VALVE | 208517 |
| 200 MM ALTERNATIVE PIPE CULVERT | 620902 |
| 200 MM BITUMINOUS COATED STEEL PIPE CONDUIT (1.63 MM THICK) | 208746 |
| 200 MM COLLECTOR SYSTEM (HORIZONTAL DRAIN) | 681592 |
| 200 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT | 208731 |
| 200 MM CORRUGATED STEEL PIPE (1.63 MM THICK) | 664003 |
| 200 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | 664004 |
| 200 MM GATE VALVE | 705952 |
| 200 MM PERFORATED PLASTIC PIPE UNDERDRAIN | 680933 |
| 200 MM PERFORATED STEEL PIPE UNDERDRAIN (1.63 MM THICK) | 680465 |
| 200 MM POLYVINYL CHLORIDE SEWER PIPE | 717077 |
| 200 MM THERMOPLASTIC TRAFFIC STRIPE | 840563 |
| 200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M) | 840574 |
| 200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M) | 840564 |
| 200 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK) | 208798 |
| 24 STATION IRRIGATION CONTROLLER (WALL MOUNTED) | 206753 |
| 24" ALTERNATIVE FLARED END SECTION | 705315 |
| 24" ALTERNATIVE PIPE CULVERT | 620140 |
| 24" ALTERNATIVE PIPE DOWNDRAIN | 698140 |
| 24" ANCHOR ASSEMBLY | 692309 |
| 24" CAST-IN-DRILLED-HOLE CONCRETE PILING | 490603 |
| 24" CONCRETE FLARED END SECTION | 705206 |
| 24" CORRUGATED STEEL PIPE (.064" THICK) | 665022 |
| 24" CORRUGATED STEEL PIPE (.079" THICK) | 665023 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 24" CORRUGATED STEEL PIPE (.109" THICK) | 665024 |
| 24" CORRUGATED STEEL PIPE (.138" THICK) | 665025 |
| 24" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK) | 690122 |
| 24" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK) | 690124 |
| 24" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK) | 690125 |
| 24" CORRUGATED STEEL PIPE ENERGY DISSIPATOR (.064" THICK) | 702616 |
| 24" CORRUGATED STEEL PIPE RISER (.079" THICK) | 703223 |
| 24" DOWNDRAIN SLIP JOINT | 692209 |
| 24" PLASTIC PIPE | 641113 |
| 24" PRECAST CONCRETE PIPE RISER | 707410 |
| 24" REINFORCED CONCRETE PIPE | 650018 |
| 24" REINFORCED CONCRETE PIPE (CLASS II, RUBBER GASKET JOINT) | 652215 |
| 24" STEEL FLARED END SECTION | 705015 |
| 25 MM BACKFLOW PREVENTER ASSEMBLY | 208432 |
| 25 MM ELECTRIC REMOTE CONTROL VALVE | 206611 |
| 25 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208250 |
| 25 MM WYE STRAINER | 208509 |
| 250 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (1.63 MM THICK) | 664081 |
| 250 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT | 208732 |
| 250 MM GATE VALVE | 705953 |
| 250 MM PERFORATED PLASTIC PIPE UNDERDRAIN | 681067 |
| 250 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK) | 208799 |
| 3" BACKFLOW PREVENTER ASSEMBLY | 208428 |
| 3" ELECTRIC REMOTE CONTROL VALVE | 206607 |
| 3" GATE VALVE | 208588 |
| 3" PLASTIC PIPE | 680207 |
| 3" PLASTIC PIPE (EDGE DRAIN OUTLET) | 681107 |
| 3" PLASTIC PIPE (EDGE DRAIN) | 681103 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 3" PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208268 |
| 3" PLASTIC PIPE (PR 315) (SUPPLY LINE) | 208278 |
| 3.0 M CAST-IN-DRILLED-HOLE CONCRETE PILING | 490673 |
| 3.0 M CHAIN LINK GATE (TYPE CL-1.8) | 802595 |
| 3.7 M CHAIN LINK GATE (TYPE CL-1.8) | 802596 |
| 3.7 M WIRE MESH GATE | 801196 |
| 3/4" ELECTRIC REMOTE CONTROL VALVE | 206601 |
| 3/4" GATE VALVE | 208570 |
| 3/4" PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208262 |
| 3/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE) | 208594 |
| 3/4" WYE STRAINER | 208625 |
| 30" ALTERNATIVE PIPE CULVERT | 620180 |
| 30" CAST-IN-DRILLED-HOLE CONCRETE PILING | 490604 |
| 30" CORRUGATED STEEL PIPE (.064" THICK) | 665030 |
| 30" CORRUGATED STEEL PIPE (.079" THICK) | 665031 |
| 30" CORRUGATED STEEL PIPE (.109" THICK) | 665032 |
| 30" PLASTIC PIPE | 641119 |
| 30" REINFORCED CONCRETE PIPE | 650022 |
| 30" STEEL FLARED END SECTION | 705019 |
| 300 MM ALTERNATIVE FLARED END SECTION | 705334 |
| 300 MM ALTERNATIVE PIPE CULVERT | 620904 |
| 300 MM ALTERNATIVE PIPE DOWNDRAIN | 698091 |
| 300 MM ALTERNATIVE PIPE RISER | 708062 |
| 300 MM ANCHOR ASSEMBLY | 692383 |
| 300 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.01 MM THICK) | 664085 |
| 300 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK) | 690273 |
| 300 MM BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (2.01 MM THICK) | 703358 |
| 300 MM CONCRETE FLARED END SECTION | 705220 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 300 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT | 208733 |
| 300 MM CORRUGATED STEEL PIPE | 664008 |
| 300 MM CORRUGATED STEEL PIPE (1.63 MM THICK) | 664009 |
| 300 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | 664010 |
| 300 MM CORRUGATED STEEL PIPE DOWNDRAIN | 690158 |
| 300 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK) | 690160 |
| 300 MM CORRUGATED STEEL PIPE RISER (1.63 MM THICK) | 703267 |
| 300 MM CORRUGATED STEEL PIPE RISER (2.01 MM THICK) | 703268 |
| 300 MM DOWNDRAIN SLIP JOINT | 692245 |
| 300 MM ENTRANCE TAPER | 692088 |
| 300 MM GATE VALVE | 705954 |
| 300 MM PERFORATED STEEL PIPE UNDERDRAIN (2.01 MM THICK) | 680469 |
| 300 MM PIPE DOWNDRAIN | 698507 |
| 300 MM PLASTIC PIPE | 641132 |
| 300 MM REINFORCED CONCRETE PIPE | 650067 |
| 300 MM SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK) | 665729 |
| 300 MM SLOTTED CORRUGATED STEEL PIPE (2.77 MM THICK) | 665730 |
| 300 MM STEEL FLARED END SECTION | 705042 |
| 300 MM TEMPORARY CULVERT | 073026 |
| 300 MM WELDED STEEL PIPE (2.67 MM THICK) | 703542 |
| 300 MM WELDED STEEL PIPE (3.40 MM THICK) | 703543 |
| 300 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK) | 208800 |
| 32 MM ELECTRIC REMOTE CONTROL VALVE | 206612 |
| 32 MM GATE VALVE | 208489 |
| 32 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208251 |
| 32 MM WYE STRAINER | 208510 |
| 36" ALTERNATIVE PIPE CULVERT | 620220 |
| 36" ALTERNATIVE PIPE DOWNDRAIN | 698200 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 36" ALTERNATIVE PIPE INLET | 708021 |
| 36" ANCHOR ASSEMBLY | 692313 |
| 36" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | 561005 |
| 36" CAST-IN-DRILLED-HOLE CONCRETE PILING | 490605 |
| 36" CORRUGATED STEEL PIPE (.079" THICK) | 665036 |
| 36" CORRUGATED STEEL PIPE (.109" THICK) | 665037 |
| 36" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK) | 690137 |
| 36" CORRUGATED STEEL PIPE INLET (.079" THICK) | 700638 |
| 36" CORRUGATED STEEL PIPE INLET (.109" THICK) | 700639 |
| 36" CORRUGATED STEEL PIPE INLET (.138" THICK) | 700640 |
| 36" PRECAST CONCRETE PIPE INLET | 707117 |
| 36" PRECAST CONCRETE PIPE MANHOLE | 707217 |
| 36" REINFORCED CONCRETE PIPE | 650026 |
| 36" STEEL FLARED END SECTION | 705023 |
| 375 MM ALTERNATIVE PIPE CULVERT | 620908 |
| 375 MM CONCRETE FLARED END SECTION | 705221 |
| 375 MM REINFORCED CONCRETE PIPE | 650068 |
| 4' CHAIN LINK GATE (TYPE CL-6) | 802501 |
| 4' CHAIN LINK GATE (TYPE CL-6, SLATTED) | 802504 |
| 4" GALVANIZED STEEL PIPE (SUPPLY LINE ON BRIDGE) | 208046 |
| 4" GATE VALVE | 208589 |
| 4" PLASTIC PIPE (PR 315) (SUPPLY LINE) | 208279 |
| 4" PLASTIC PIPE UNDERDRAIN | 680285 |
| 4" POLYVINYL CHLORIDE SEWER PIPE | 717001 |
| 4" THERMOPLASTIC TRAFFIC STRIPE | 840504 |
| 4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3) | 840523 |
| 4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 17-7) | 840526 |
| 4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12) | 840525 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 6-1) | 840521 |
| 4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED) | 840581 |
| 4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED) (BROKEN 17-7) | 840580 |
| 4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED, BROKEN 36-12) | 840545 |
| 4" TWO-COMPONENT PAINT TRAFFIC STRIPE | 840582 |
| 4.3 M CHAIN LINK GATE (TYPE CL-1.8) | 802671 |
| 4.3 M WIRE MESH GATE | 801272 |
| 4.6 M WIRE MESH GATE | 801273 |
| 4.9 M CHAIN LINK GATE (TYPE CL-1.8) | 802672 |
| 4.9 M METAL GATE | 801371 |
| 4.9 M WIRE MESH GATE | 801274 |
| 40 MM BACKFLOW PREVENTER ASSEMBLY | 208434 |
| 40 MM ELECTRIC REMOTE CONTROL VALVE | 206613 |
| 40 MM GATE VALVE | 208490 |
| 40 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208252 |
| 400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING | 490655 |
| 400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL) | 498027 |
| 400 MM PLASTIC PIPE-LINER | 152666 |
| 42" ALTERNATIVE PIPE CULVERT | 620260 |
| 42" CORRUGATED STEEL PIPE (.109" THICK) | 665042 |
| 42" STEEL FLARED END SECTION | 705027 |
| 42" WELDED STEEL PIPE (.375" THICK) | 703646 |
| 450 MM ALTERNATIVE FLARED END SECTION | 705336 |
| 450 MM ALTERNATIVE PIPE CULVERT | 620909 |
| 450 MM ALTERNATIVE PIPE CULVERT (TYPE A) | 620910 |
| 450 MM ALTERNATIVE PIPE CULVERT (TYPE B) | 620911 |
| 450 MM ALTERNATIVE PIPE DOWNDRAIN | 698162 |
| 450 MM ALTERNATIVE PIPE RISER | 708064 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 450 MM ANCHOR ASSEMBLY | 692385 |
| 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (1.63 MM THICK) | 664089 |
| 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.01 MM THICK) | 664090 |
| 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK) | 690275 |
| 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK) | 690276 |
| 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK) | 690277 |
| 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (3.51 MM THICK) | 690297 |
| 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (3.51 MM THICK) | 703363 |
| 450 MM BITUMINOUS COATED ENTRANCE TAPER | 692095 |
| 450 MM BITUMINOUS COATED SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK) | 665833 |
| 450 MM BITUMINOUS COATED STEEL FLARED END SECTION | 705055 |
| 450 MM CONCRETE FLARED END SECTION | 705222 |
| 450 MM CORRUGATED STEEL PIPE (1.63 MM THICK) | 664014 |
| 450 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | 664015 |
| 450 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | 664016 |
| 450 MM CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK) | 690165 |
| 450 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK) | 690166 |
| 450 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK) | 690167 |
| 450 MM CORRUGATED STEEL PIPE ENERGY DISSIPATOR (1.63 MM THICK) | 702671 |
| 450 MM ENTRANCE TAPER | 692090 |
| 450 MM PLASTIC PIPE | 641134 |
| 450 MM REINFORCED CONCRETE PIPE | 650069 |
| 450 MM REINFORCED CONCRETE PIPE (CLASS III) | 650365 |
| 450 MM REINFORCED CONCRETE PIPE (CLASS IV) | 650470 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 450 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT) | 650127 |
| 450 MM SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK) | 665733 |
| 450 MM STEEL FLARED END SECTION | 705044 |
| 450 MM TEMPORARY CULVERT | 073028 |
| 48 SINGLEMODE FIBER OPTIC CABLE | 867017 |
| 48" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | 561011 |
| 48" CAST-IN-DRILLED-HOLE CONCRETE PILING | 490607 |
| 48" CORRUGATED STEEL PIPE (.064" THICK) | 665045 |
| 48" CORRUGATED STEEL PIPE (.168" THICK) | 665049 |
| 48" DEBRIS RACK CAGE (H=4') | 706607 |
| 48" PRECAST CONCRETE PIPE MANHOLE | 707225 |
| 5' CHAIN LINK GATE (TYPE CL-6) | 802510 |
| 50 MM BACKFLOW PREVENTER ASSEMBLY | 208435 |
| 50 MM ELECTRIC REMOTE CONTROL VALVE | 206614 |
| 50 MM GATE VALVE | 208491 |
| 50 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208253 |
| 500 MM PLASTIC PIPE-LINER | 152667 |
| 525 MM PLASTIC PIPE-LINER | 152668 |
| 525 MM REINFORCED CONCRETE PIPE | 650072 |
| 525 MM X 375 MM ALTERNATIVE PIPE ARCH CULVERT | 625382 |
| 54" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | 561014 |
| 54" CORRUGATED STEEL PIPE (.079" THICK) | 665050 |
| 54" REINFORCED CONCRETE PIPE | 650038 |
| 54" STEEL FLARED END SECTION | 705035 |
| 6' CHAIN LINK GATE (TYPE CL-6) | 802520 |
| 6" ALTERNATIVE PIPE CULVERT | 620002 |
| 6" ALTERNATIVE PIPE RISER | 708031 |
| 6" CORRUGATED STEEL PIPE (.079" THICK) | 665003 |
| 6" GATE VALVE | 208590 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 6" NON-PERFORATED PLASTIC PIPE UNDERDRAIN | 680903 |
| 6" PLASTIC PIPE | 681023 |
| 6" PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208281 |
| 6" SLOTTED CORRUGATED PLASTIC PIPE UNDERDRAIN | 680226 |
| 6" THERMOPLASTIC TRAFFIC STRIPE | 840505 |
| 6" WELDED STEEL PIPE (.134" THICK) | 703509 |
| 6.1 M CHAIN LINK GATE (TYPE CL-1.8) | 802675 |
| 60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | 561016 |
| 60" CAST-IN-DRILLED-HOLE CONCRETE PILING | 490609 |
| 600 MM ALTERNATIVE FLARED END SECTION | 705337 |
| 600 MM ALTERNATIVE PIPE CULVERT | 620913 |
| 600 MM ALTERNATIVE PIPE CULVERT (TYPE A) | 620914 |
| 600 MM ALTERNATIVE PIPE CULVERT (TYPE B) | 620915 |
| 600 MM ALTERNATIVE PIPE CULVERT (TYPE C) | 620916 |
| 600 MM ALTERNATIVE PIPE DOWNDRAIN | 698169 |
| 600 MM ANCHOR ASSEMBLY | 692386 |
| 600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK) | 664097 |
| 600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK) | 690281 |
| 600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (3.51 MM THICK) | 690282 |
| 600 MM BITUMINOUS COATED STEEL FLARED END SECTION | 705056 |
| 600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING | 490657 |
| 600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL) | 498030 |
| 600 MM CONCRETE FLARED END SECTION | 705224 |
| 600 MM CORRUGATED STEEL PIPE (1.63 MM THICK) | 664019 |
| 600 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | 664020 |
| 600 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | 664021 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 600 MM CORRUGATED STEEL PIPE (3.51 MM THICK) | 664022 |
| 600 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK) | 690170 |
| 600 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK) | 690171 |
| 600 MM CORRUGATED STEEL PIPE ENERGY DISSIPATOR (1.63 MM THICK) | 702672 |
| 600 MM PRECAST CONCRETE PIPE RISER | 707470 |
| 600 MM REINFORCED CONCRETE PIPE | 650075 |
| 600 MM REINFORCED CONCRETE PIPE (CLASS III) | 650370 |
| 600 MM REINFORCED CONCRETE PIPE (CLASS IV) | 650476 |
| 600 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT) | 650128 |
| 600 MM SLIDE HEADGATE | 705651 |
| 600 MM STEEL FLARED END SECTION | 705045 |
| 600 MM TEMPORARY CULVERT | 073029 |
| 600 MM WELDED STEEL PIPE CASING (BRIDGE) | 703481 |
| 65 MM GATE VALVE | 208492 |
| 65 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208254 |
| 65 MM PLASTIC PIPE (PR 315) (SUPPLY LINE) | 208289 |
| 675 MM REINFORCED CONCRETE PIPE (CLASS III) | 650373 |
| 700 MM X 500 MM CORRUGATED STEEL PIPE ARCH (2.01 MM THICK) | 667054 |
| 700 MM X 500 MM CORRUGATED STEEL PIPE ARCH (2.77 MM THICK) | 667055 |
| 700 MM X 500 MM STEEL FLARED END PIPE ARCH SECTION | 705476 |
| 71" X 47" CORRUGATED STEEL PIPE ARCH (.109" THICK) | 667041 |
| 72" CAST-IN-DRILLED-HOLE CONCRETE PILING | 490611 |
| 72" PRECAST CONCRETE PIPE MANHOLE | 707241 |
| 75 MM GATE VALVE | 208493 |
| 75 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | 208255 |
| 750 MM ALTERNATIVE FLARED END SECTION | 705338 |
| 750 MM ALTERNATIVE PIPE CULVERT | 620919 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 750 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK) | 664105 |
| 750 MM BITUMINOUS COATED PAVED INVERT CORRUGATED STEEL PIPE (2.01 MM THICK) | 665278 |
| 750 MM CAST-IN-DRILLED-HOLE CONCRETE PILING | 490658 |
| 750 MM CONCRETE FLARED END SECTION | 705226 |
| 750 MM CORRUGATED STEEL PIPE (1.63 MM THICK) | 664027 |
| 750 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | 664028 |
| 750 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | 664029 |
| 750 MM CORRUGATED STEEL PIPE (3.51 MM THICK) | 664030 |
| 750 MM REINFORCED CONCRETE PIPE | 650077 |
| 750 MM REINFORCED CONCRETE PIPE (CLASS IV) | 650478 |
| 750 MM STANDPIPE | 709528 |
| 750 MM STEEL FLARED END SECTION | 705047 |
| 750 MM TEMPORARY CULVERT | 073030 |
| 760 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | 561008 |
| 8 STATION IRRIGATION CONTROLLER (WALL MOUNTED) | 206749 |
| 8" ALTERNATIVE PIPE UNDERDRAIN | 685020 |
| 8" COLLECTOR SYSTEM (HORIZONTAL DRAIN) | 681512 |
| 8" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT | 208738 |
| 8" CORRUGATED STEEL PIPE DOWNDRAIN | 690104 |
| 8" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK) | 690106 |
| 8" ENTRANCE TAPER | 692003 |
| 8" PERFORATED PLASTIC PIPE UNDERDRAIN | 680905 |
| 8" PERFORATED STEEL PIPE UNDERDRAIN (.064" THICK) | 680405 |
| 8" PERFORATED STEEL PIPE UNDERDRAIN (.079" THICK) | 680406 |
| 8" THERMOPLASTIC TRAFFIC STRIPE | 840506 |
| 8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3) | 840508 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12) | 840550 |
| 8" TWO-COMPONENT PAINT TRAFFIC STRIPE | 840584 |
| 8" WELDED STEEL PIPE CONDUIT (.250" THICK) | 208808 |
| 80 MM PLASTIC PIPE | 680256 |
| 80 MM PLASTIC PIPE (EDGE DRAIN OUTLET) | 681137 |
| 80 MM PLASTIC PIPE (EDGE DRAIN) | 681134 |
| 80 MM PLASTIC PIPE (OUTLET) | 680264 |
| 80 MM PLASTIC PIPE UNDERDRAIN | 680271 |
| 80 MM SLOTTED PLASTIC PIPE | 680259 |
| 80 MM SLOTTED PLASTIC PIPE UNDERDRAIN | 680273 |
| 875 MM X 600 MM CORRUGATED STEEL PIPE ARCH (2.01 MM THICK) | 667057 |
| 875 MM X 600 MM STEEL FLARED END PIPE ARCH SECTION | 705477 |
| 900 MM ALTERNATIVE FLARED END SECTION | 705339 |
| 900 MM ALTERNATIVE PIPE CULVERT | 620924 |
| 900 MM ALTERNATIVE PIPE CULVERT (TYPE A) | 620925 |
| 900 MM ALTERNATIVE PIPE RISER | 708068 |
| 900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.01 MM THICK) | 664109 |
| 900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK) | 664110 |
| 900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE INLET (2.01 MM THICK) | 700857 |
| 900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (2.01 MM THICK) | 703369 |
| 900 MM CONCRETE FLARED END SECTION | 705227 |
| 900 MM CORRUGATED STEEL PIPE (1.63 MM THICK) | 664032 |
| 900 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | 664033 |
| 900 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | 664034 |
| 900 MM CORRUGATED STEEL PIPE (3.51 MM THICK) | 664035 |
| 900 MM CORRUGATED STEEL PIPE INLET (1.63 MM THICK) | 700657 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **0 - 9** | |
| 900 MM CORRUGATED STEEL PIPE INLET (2.01 MM THICK) | 700658 |
| 900 MM CORRUGATED STEEL PIPE INLET (2.77 MM THICK) | 700659 |
| 900 MM CORRUGATED STEEL PIPE INLET (3.51 MM THICK) | 700660 |
| 900 MM CORRUGATED STEEL PIPE INLET (4.27 MM THICK) | 700661 |
| 900 MM CORRUGATED STEEL PIPE RISER (2.01 MM THICK) | 703283 |
| 900 MM CORRUGATED STEEL PIPE RISER (2.77 MM THICK) | 703284 |
| 900 MM CORRUGATED STEEL PIPE RISER (3.51 MM THICK) | 703285 |
| 900 MM PRECAST CONCRETE PIPE INLET | 707133 |
| 900 MM PRECAST CONCRETE PIPE MANHOLE | 707244 |
| 900 MM PRECAST CONCRETE PIPE RISER | 707471 |
| 900 MM REINFORCED CONCRETE PIPE | 650079 |
| 900 MM REINFORCED CONCRETE PIPE (CLASS IV) | 650481 |
| 900 MM REINFORCED CONCRETE PIPE RISER | 707479 |
| 900 MM SEWER MANHOLE | 719246 |
| 900 MM STEEL FLARED END SECTION | 705048 |
| 920 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | 561009 |
| 975 MM REINFORCED CONCRETE PIPE | 650080 |
| **A** | |
| ABANDON CULVERT | 150206 |
| ABANDON INLET | 150221 |
| ABANDON MANHOLE | 150224 |
| ABANDON PIPELINE | 150227 |
| ABANDON SEWER | 150241 |
| ABANDON WATER WELL | 150229 |
| ACCESS GATE (SOUND WALL) | 518010 |
| ACCESS OPENING, SOFFIT | 153531 |
| ADJUST DOWNDRAIN | 152436 |
| ADJUST FRAME AND COVER TO GRADE | 152438 |
| ADJUST FRAME AND GRATE TO GRADE | 152439 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **A** | |
| ADJUST INLET | 152430 |
| ADJUST MANHOLE | 152432 |
| ADJUST MANHOLE TO GRADE | 152440 |
| ADJUST METAL BEAM GUARD RAILING | 152500 |
| ADJUST MONUMENT COVER | 152422 |
| ADJUST MONUMENT TO GRADE | 152423 |
| ADJUST PULL BOX | 869042 |
| ADJUST RISER | 152434 |
| ADJUST SEWER CLEANOUT TO GRADE | 152400 |
| ADJUST SEWER MANHOLE | 152475 |
| ADJUST SLOTTED DRAIN TO GRADE | 152555 |
| ADJUST UTILITY COVER TO GRADE | 152469 |
| ADJUST VALVE BOX | 152453 |
| ADJUST WATER METER BOX TO GRADE | 152403 |
| ADJUST WATER VALVE | 152451 |
| ADJUST WATER VALVE COVER | 152452 |
| ADJUST WATER VALVE COVER TO GRADE | 152402 |
| AGGREGATE BASE (APPROACH SLAB) | 260210 |
| ALTERNATIVE FLARED END SECTION | 705300 |
| ALTERNATIVE FLARED TERMINAL SYSTEM | 839585 |
| ALTERNATIVE IN-LINE TERMINAL SYSTEM | 839584 |
| ANCHOR ASSEMBLY | 692301 |
| ANTI-GRAFFITI COATING | 511047 |
| ARCHITECTURAL SURFACE (BARRIER) | 511036 |
| ARCHITECTURAL TREATMENT | 511035 |
| ASBESTOS COMPLIANCE PLAN | 190113 |
| ASBESTOS COMPLIANCE PLAN (NATURALLY OCCURING ASBESTOS) | 190115 |
| ASPHALT BINDER (POLYMER MODIFIED) | 370125 |
| ASPHALT CONCRETE | 390101 |
| ASPHALT CONCRETE | 390104 |
| ASPHALT CONCRETE (LEVELING) | 390107 |
| ASPHALT CONCRETE (OPEN GRADED) | 390106 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **A** | |
| ASPHALT CONCRETE (TYPE A) | 390102 |
| ASPHALT CONCRETE (TYPE A, 12.5-MM MAXIMUM GRADING) | 390146 |
| ASPHALT CONCRETE (TYPE A, 19-MM MAXIMUM GRADING) | 390144 |
| ASPHALT CONCRETE (TYPE B) | 390103 |
| ASPHALT CONCRETE BASE (TYPE A) | 390108 |
| ASPHALT MEMBRANE WATERPROOFING | 540101 |
| ASPHALT TREATED PERMEABLE BASE | 290201 |
| ASPHALTIC EMULSION (CURING SEAL) | 270065 |
| ASPHALTIC EMULSION (FOG SEAL COAT) | 374002 |
| ASPHALTIC EMULSION (PAINT BINDER) | 397001 |
| ASPHALTIC EMULSION (POLYMER MODIFIED) | 374492 |
| ASPHALTIC EMULSION MEMBRANE (BONDED WEARING COURSE) | 390149 |
| ASPHALT-RUBBER BINDER | 370120 |
| **B** | |
| BACKFLOW PREVENTER ASSEMBLY | 208420 |
| BACKFLOW PREVENTER ASSEMBLY BLANKET | 208439 |
| BACKFLOW PREVENTER ASSEMBLY ENCLOSURE | 208421 |
| BALL VALVE | 208683 |
| BAR REINFORCING STEEL | 520101 |
| BAR REINFORCING STEEL (BOX CULVERT) | 520107 |
| BAR REINFORCING STEEL (BRIDGE) | 520102 |
| BAR REINFORCING STEEL (EPOXY COATED) | 520106 |
| BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE) | 520110 |
| BAR REINFORCING STEEL (RETAINING WALL) | 520103 |
| BAR REINFORCING STEEL (SOUND WALL) | 520105 |
| BARRICADE (LEFT IN PLACE) | 120140 |
| BATTERY BACKUP SYSTEM | 860799 |
| BLANK WELL CASING | 760030 |
| BOOSTER PUMP | 209502 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **B** | |
| BOOSTER PUMP ELECTRICAL SYSTEM | 860798 |
| BOOSTER PUMP SYSTEM | 209503 |
| BRIDGE DECK DRAINAGE SYSTEM | 750505 |
| BRIDGE REMOVAL | 157550 |
| BRIDGE REMOVAL (PORTION) | 157560 |
| BRIDGE REMOVAL (PORTION), LOCATION 1 | 157581 |
| BRIDGE REMOVAL (PORTION), LOCATION A | 157561 |
| BRIDGE REMOVAL (PORTION), LOCATION B | 157562 |
| BRIDGE REMOVAL (PORTION), LOCATION C | 157563 |
| BRIDGE REMOVAL (PORTION), LOCATION D | 157564 |
| BRIDGE REMOVAL (PORTION), LOCATION E | 157565 |
| BRIDGE REMOVAL (PORTION), LOCATION F | 157566 |
| BRIDGE REMOVAL (PORTION), LOCATION G | 157567 |
| BRIDGE REMOVAL (PORTION), LOCATION H | 157568 |
| BRIDGE REMOVAL (PORTION), LOCATION I | 157569 |
| BRIDGE REMOVAL (PORTION), LOCATION J | 157570 |
| BRIDGE REMOVAL (PORTION), LOCATION K | 157571 |
| BRIDGE REMOVAL (PORTION), LOCATION L | 157572 |
| BRIDGE REMOVAL (PORTION), LOCATION M | 157573 |
| BRIDGE REMOVAL, LOCATION A | 157551 |
| BRIDGE REMOVAL, LOCATION B | 157552 |
| BUILDING WORK | 994650 |
| BURIED POST ANCHOR | 839528 |
| BUS SHELTER | 995000 |
| **C** | |
| CABLE ANCHORAGE SYSTEM | 692409 |
| CABLE RAILING | 839521 |
| CALIFORNIA ST-10 BRIDGE RAIL | 839740 |
| CAM COUPLER ASSEMBLY | 208562 |
| CAP INLET | 155003 |
| CAP MANHOLE | 155007 |
| CAP REINFORCED CONCRETE BOX OPENING | 155009 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **C** | |
| CAP RISER | 155006 |
| CEMENT TREATED BASE (PLANT-MIXED, CLASS A) | 270011 |
| CHAIN LINK FENCE (TYPE CL-0.9) | 800381 |
| CHAIN LINK FENCE (TYPE CL-0.9, VINYL-CLAD) | 800382 |
| CHAIN LINK FENCE (TYPE CL-1.2) | 800385 |
| CHAIN LINK FENCE (TYPE CL-1.2, VINYL-CLAD) | 800386 |
| CHAIN LINK FENCE (TYPE CL-1.8) | 800391 |
| CHAIN LINK FENCE (TYPE CL-1.8, VINYL-CLAD) | 800392 |
| CHAIN LINK FENCE (TYPE CL-4) | 800320 |
| CHAIN LINK FENCE (TYPE CL-6) | 800360 |
| CHAIN LINK FENCE (TYPE CL-6, SLATTED) | 800365 |
| CHAIN LINK FENCE (TYPE CL-6, VINYL-CLAD) | 800361 |
| CHAIN LINK GATE | 801900 |
| CHAIN LINK RAILING | 833020 |
| CHAIN LINK RAILING (TYPE 3L) | 833023 |
| CHAIN LINK RAILING (TYPE 6) | 833031 |
| CHAIN LINK RAILING (TYPE 7 MODIFIED) | 833033 |
| CHAIN LINK RAILING (TYPE 7) | 833032 |
| CHAIN LINK RAILING (TYPE 7L) | 833034 |
| CHANGEABLE MESSAGE SIGN SYSTEM | 860530 |
| CHANNELIZER (SURFACE MOUNTED) | 120165 |
| CHANNELIZER (SURFACE MOUNTED) (LEFT IN PLACE) | 120166 |
| CLASS 1 CONCRETE (BACKFILL) | 510414 |
| CLASS 1 CONCRETE (BOX CULVERT) | 510413 |
| CLASS 1 CONCRETE (MINOR STRUCTURE) | 510409 |
| CLASS 1 CONCRETE (RETAINING WALL) | 510408 |
| CLASS 1 CONCRETE (STRUCTURE) | 510410 |
| CLASS 1 PERMEABLE MATERIAL | 682020 |
| CLASS 2 AGGREGATE BASE | 260201 |
| CLASS 2 AGGREGATE SUBBASE | 250201 |
| CLASS 2 CONCRETE (BOX CULVERT) | 510129 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **C** | |
| CLASS 2 CONCRETE (HEADWALL) | 510135 |
| CLASS 2 CONCRETE (MINOR STRUCTURE) | 510126 |
| CLASS 2 CONCRETE (RETAINING WALL) | 510133 |
| CLASS 2 CONCRETE (WINGWALLS) | 510138 |
| CLASS 3 AGGREGATE BASE | 260301 |
| CLASS 3 CONCRETE | 510217 |
| CLASS 3 CONCRETE (BACKFILL) | 510220 |
| CLASS 3 PERMEABLE MATERIAL | 682045 |
| CLASS 3 PERMEABLE MATERIAL (BLANKET) | 682049 |
| CLASS 4 AGGREGATE SUBBASE | 250401 |
| CLASS 4 CONCRETE (BACKFILL) | 510314 |
| CLASS 4 CONCRETE (BACKFILL) | 719598 |
| CLEAN AND PAINT STRUCTURAL STEEL | 590115 |
| CLEAN BRIDGE DECK | 153235 |
| CLEAN EXPANSION JOINT | 511118 |
| CLEAN STRUCTURAL STEEL (EXISTING BRIDGE) | 590106 |
| CLEARING AND GRUBBING | 160101 |
| CLOSED CIRCUIT TELEVISION SYSTEM | 860990 |
| COLD PLANE ASPHALT CONCRETE PAVEMENT | 153103 |
| COLD PLANE ASPHALT CONCRETE PAVEMENT (.08' MAXIMUM) | 153109 |
| COLD PLANE ASPHALT CONCRETE PAVEMENT (.10' MAXIMUM) | 153110 |
| COLD PLANE ASPHALT CONCRETE PAVEMENT (.15' MAXIMUM) | 153112 |
| COLD PLANE ASPHALT CONCRETE PAVEMENT (25 MM MAXIMUM) | 153151 |
| COLD PLANE ASPHALT CONCRETE PAVEMENT (30 MM MAXIMUM) | 153152 |
| COLUMN CASING | 550110 |
| COMMERCIAL FERTILIZER (EROSION CONTROL) | 203056 |
| COMMERCIAL FERTILIZER (GRANULAR) | 202030 |
| COMMERCIAL FERTILIZER (PACKET) | 202033 |
| COMMERCIAL FERTILIZER (SLOW RELEASE) | 202031 |
| COMMUNICATION CONDUIT | 860791 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **C** | |
| COMMUNICATION CONDUIT (BRIDGE) | 860792 |
| COMMUNICATION PULL BOX | 869039 |
| COMPOST (EROSION CONTROL) | 203024 |
| COMPOST, INCORPORATE | 203025 |
| CONCRETE (CHANNEL LINING) | 721430 |
| CONCRETE (CONCRETE APRON) | 721431 |
| CONCRETE (CONCRETED-ROCK SLOPE PROTECTION) | 721501 |
| CONCRETE (DITCH LINING) | 721420 |
| CONCRETE (GUTTER LINING) | 721410 |
| CONCRETE (SLOPE PROTECTION) | 721400 |
| CONCRETE BACKFILL | 193118 |
| CONCRETE BACKFILL FAST SETTING | 193117 |
| CONCRETE BARRIER | 839401 |
| CONCRETE BARRIER (TYPE 25 MODIFIED) | 833128 |
| CONCRETE BARRIER (TYPE 25) | 833125 |
| CONCRETE BARRIER (TYPE 25A) | 833126 |
| CONCRETE BARRIER (TYPE 26 MODIFIED) | 833142 |
| CONCRETE BARRIER (TYPE 26) | 833140 |
| CONCRETE BARRIER (TYPE 26R MODIFIED) | 833148 |
| CONCRETE BARRIER (TYPE 27 MODIFIED) | 833187 |
| CONCRETE BARRIER (TYPE 27B MODIFIED) | 833165 |
| CONCRETE BARRIER (TYPE 28) | 833190 |
| CONCRETE BARRIER (TYPE 50 MODIFIED) | 839482 |
| CONCRETE BARRIER (TYPE 60) | 839701 |
| CONCRETE BARRIER (TYPE 60A) | 839702 |
| CONCRETE BARRIER (TYPE 60C) | 839703 |
| CONCRETE BARRIER (TYPE 60D) | 839704 |
| CONCRETE BARRIER (TYPE 60E) | 839705 |
| CONCRETE BARRIER (TYPE 60G) | 839706 |
| CONCRETE BARRIER (TYPE 60GA) | 839707 |
| CONCRETE BARRIER (TYPE 60GC) | 839708 |
| CONCRETE BARRIER (TYPE 60GE) | 839709 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **C** | |
| CONCRETE BARRIER (TYPE 60S) | 839710 |
| CONCRETE BARRIER (TYPE 60SA) | 839711 |
| CONCRETE BARRIER (TYPE 60SC) | 839712 |
| CONCRETE BARRIER (TYPE 60SE) | 839713 |
| CONCRETE BARRIER (TYPE 732 MODIFIED) | 839717 |
| CONCRETE BARRIER (TYPE 732) | 839720 |
| CONCRETE BARRIER (TYPE 732A) | 839721 |
| CONCRETE BARRIER (TYPE 732B) | 839723 |
| CONCRETE BARRIER (TYPE 732R) | 839718 |
| CONCRETE BARRIER (TYPE 736 MODIFIED) | 839727 |
| CONCRETE BARRIER (TYPE 736) | 839725 |
| CONCRETE BARRIER (TYPE 736A) | 839726 |
| CONCRETE BARRIER (TYPE 736B) | 839731 |
| CONCRETE BARRIER (TYPE 736R) | 839728 |
| CONCRETE BARRIER (TYPE 736SV) | 839734 |
| CONCRETE BARRIER (TYPE 742) | 839735 |
| CONCRETE BARRIER (TYPE 742A) | 839736 |
| CONCRETE BARRIER (TYPE 742B) | 839737 |
| CONCRETE BARRIER (TYPE 80) | 839714 |
| CONCRETE BARRIER (TYPE K) | 833080 |
| CONCRETE CLOSURE WALL | 513501 |
| CONCRETE PAVEMENT | 401000 |
| CONCRETE PAVEMENT (RAMP TERMINI) | 401066 |
| CONCRETE PAVEMENT (WEIGH-IN-MOTION) | 401102 |
| CONCRETED-ROCK SLOPE PROTECTION (1/2 TON, METHOD A) | 721506 |
| CONCRETED-ROCK SLOPE PROTECTION (1/2T, METHOD A) | 721519 |
| CONCRETED-ROCK SLOPE PROTECTION (1/4 TON, METHOD A) | 721507 |
| CONCRETED-ROCK SLOPE PROTECTION (1/4 TON, METHOD B) | 721607 |
| CONCRETED-ROCK SLOPE PROTECTION (1/4T, METHOD A) | 721520 |
| CONCRETED-ROCK SLOPE PROTECTION (COBBLE, METHOD B) | 721616 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **C** | |
| CONCRETED-ROCK SLOPE PROTECTION (LIGHT, METHOD B) | 721608 |
| CONDUCTOR CASING | 760025 |
| CONSTRUCTION AREA SIGNS | 120090 |
| CONSTRUCTION SITE MANAGEMENT | 074016 |
| CONTROL AND NEUTRAL CONDUCTORS | 206560 |
| CORE CONCRETE (0 - 50 MM) | 515072 |
| CORE CONCRETE (1 1/2") | 515160 |
| CORE CONCRETE (10") | 515070 |
| CORE CONCRETE (101 MM - 150 MM) | 515074 |
| CORE CONCRETE (151 MM - 200 MM) | 515075 |
| CORE CONCRETE (251 MM - 300 MM) | 515077 |
| CORE CONCRETE (351 MM - 400 MM) | 515079 |
| CORE CONCRETE (51 MM - 100 MM) | 515073 |
| CORRUGATED STEEL FLUME DOWNDRAIN | 691001 |
| CRACK EXISTING CONCRETE PAVEMENT | 415101 |
| CRASH CUSHION (REACT 9CBB) | 839604 |
| CRASH CUSHION (REACT 9SCBS) | 839605 |
| CRASH CUSHION (TYPE CAT) | 839601 |
| CRASH CUSHION (TYPE CAT) BACKUP | 839602 |
| CRASH CUSHION MODULE, SAND FILLED | 839631 |
| CRASH CUSHION, SAND FILLED | 839591 |
| CURB RAMP DETECTABLE WARNING SURFACE | 731656 |
| **D** | |
| DEBRIS RACK | 706500 |
| DECK SEAL | 540100 |
| DELINEATOR (CLASS 1) | 820107 |
| DELINEATOR (CLASS 2) | 820108 |
| DELINEATOR (SPECIAL) | 820105 |
| DEMOLISH BUILDING | 160132 |
| DETECTOR LOOP | 860811 |
| DEVELOP WATER SUPPLY | 170101 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **D** | |
| DIAPHRAGM BOLSTER | 510805 |
| DITCH EXCAVATION | 194001 |
| DOUBLE METAL BEAM BARRIER | 839201 |
| DOUBLE METAL BEAM GUARD RAILING (WOOD POST) | 839220 |
| DOUBLE THRIE BEAM BARRIER | 839310 |
| DOUBLE THRIE BEAM BARRIER (BRIDGE) | 839313 |
| DOUBLE THRIE BEAM BARRIER (STEEL POST) | 839312 |
| DOUBLE THRIE BEAM BARRIER (WOOD POST) | 839311 |
| DOWEL BAR RETROFIT | 406100 |
| DRAINAGE INLET | 707050 |
| DRAINAGE INLET MARKER | 700617 |
| DRAINAGE MANHOLE | 707051 |
| DRAINAGE PUMPING EQUIPMENT | 740500 |
| DRILL AND BOND DOWEL | 511106 |
| DRILL AND BOND DOWEL (CHEMICAL ADHESIVE) | 511110 |
| DRILL AND BOND DOWEL (EPOXY CARTRIDGE) | 511109 |
| DRILL HOLE (HORIZONTAL DRAIN) | 681502 |
| DRILL HOLE (PRESPLITTING) | 190170 |
| DRILL PILOT HOLE | 760021 |
| DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (1219 MM) | 499053 |
| DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (460 MM) | 499025 |
| DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (610 MM) | 499031 |
| DRIVE PILE (CLASS 140) | 490739 |
| DRIVE PILE (CLASS 400) | 491008 |
| DRIVE PILE (CLASS 400) (ALTERNATIVE W) | 491013 |
| DRIVE PILE (CLASS 625 MODIFIED) | 490756 |
| DRIVE PILE (CLASS 625) | 490754 |
| DRIVE PILE (CLASS 625) (ALTERNATIVE V) | 490771 |
| DRIVE PILE (CLASS 625) (ALTERNATIVE W) | 490773 |
| DRIVE PILE (CLASS 900) | 490697 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **D** | |
| DRIVE PILE (CLASS 900) (ALTERNATIVE W) | 490701 |
| DRIVE STEEL PILE (HP 250 X 62) | 490506 |
| DRIVE STEEL PILE (HP 250 X 85) | 490512 |
| DRIVE STEEL PILE (HP 360 X 132) | 490567 |
| DRIVE STEEL PILE (HP 360 X 174) | 490571 |
| DRIVE STEEL PIPE PILE (406 MM) | 490583 |
| DRIVE STEEL PIPE PILE (610 MM) | 490585 |
| DUFF | 202007 |
| DUST CONTROL PLAN | 190114 |
| DUST CONTROL PLAN (NATURALLY OCCURRING ASBESTOS) | 190116 |
| **E** | |
| EARTH RETAINING STRUCTURE | 197020 |
| EARTH RETAINING STRUCTURE, LOCATION A | 197021 |
| EARTH RETAINING STRUCTURE, LOCATION B | 197022 |
| EARTH RETAINING STRUCTURE, LOCATION C | 197023 |
| EARTH RETAINING STRUCTURE, LOCATION D | 197024 |
| ELECTRIC SERVICE (IRRIGATION) | 860797 |
| EMBANKMENT | 198050 |
| END ANCHOR ASSEMBLY (TYPE CA) | 839582 |
| END ANCHOR ASSEMBLY (TYPE SFT) | 839581 |
| END CAP | 839555 |
| END CAP (TYPE A) | 839576 |
| END CAP (TYPE TA) | 839577 |
| END CAP (TYPE TC) | 839578 |
| ENTRANCE TAPER | 692001 |
| EPOXY ADHESIVE (BOND COAT) | 511115 |
| ERECT PRECAST PRESTRESSED CONCRETE BOX GIRDER | 512502 |
| ERECT PRECAST PRESTRESSED CONCRETE GIRDER | 512500 |
| ERECT STRUCTURAL STEEL (BRIDGE) | 550204 |
| EROSION CONTROL | 203015 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **E** | |
| EROSION CONTROL (BLANKET) | 203001 |
| EROSION CONTROL (COMPOST BLANKET) | 203002 |
| EROSION CONTROL (DRILL SEED) | 203012 |
| EROSION CONTROL (HYDRAULIC MATRIX) | 203017 |
| EROSION CONTROL (NETTING) | 203018 |
| EROSION CONTROL (TYPE C) | 203011 |
| EROSION CONTROL (TYPE D) | 203016 |
| EROSION CONTROL, BFM | 203019 |
| ESTABLISH EXISTING PLANTING | 204100 |
| EXPANSION DAM | 519050 |
| EXPOSED AGGREGATE FINISH | 511045 |
| EXTEND 10" CONDUIT | 208907 |
| EXTEND 150 MM CONDUIT | 208908 |
| EXTEND 200 MM CONDUIT | 208909 |
| EXTEND 250 MM CONDUIT | 208910 |
| EXTEND 6" CONDUIT | 208905 |
| EXTEND 8" CONDUIT | 208906 |
| EXTINGUISHABLE MESSAGE SIGN | 860503 |
| **F** | |
| FENCE (TYPE BW, 4-STRAND, METAL POST) | 800008 |
| FENCE (TYPE BW, 4-STRAND, WOOD POST) | 800010 |
| FENCE (TYPE BW, 5 STRAND, METAL POST) | 800007 |
| FENCE (TYPE BW, METAL POST) | 800001 |
| FENCE (TYPE WM AND BW) | 800060 |
| FENCE (TYPE WM, METAL POST) | 800051 |
| FENCE (TYPE WM, MODIFIED) | 800054 |
| FENCE (TYPE WM, WOOD POST) | 800052 |
| FIBER (EROSION CONTROL) | 203014 |
| FIBER OPTIC SPLICE CLOSURE | 867130 |
| FIBER ROLLS | 203021 |
| FILTER ASSEMBLY UNIT | 208560 |
| FILTER FABRIC | 681990 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **F** | |
| FINISHING ROADWAY | 220101 |
| FIRE HYDRANT | 993002 |
| FLASHING ARROW SIGN | 120110 |
| FLASHING BEACON | 860601 |
| FLASHING BEACON (PORTABLE) | 120200 |
| FLASHING BEACON AND LIGHTING | 860603 |
| FLASHING BEACON AND SIGN ILLUMINATION | 860602 |
| FLASHING BEACON SYSTEM | 860604 |
| FLUME ANCHOR ASSEMBLY | 692361 |
| FLUME DOWNDRAIN | 691900 |
| FOLIAGE PROTECTOR | 205051 |
| FRACTURED RIB TEXTURE | 511064 |
| FRAME AND COVER | 750008 |
| FRAME AND GRATE | 750007 |
| FURNISH AND INSTALL DRAIN PIPE (HORIZONTAL DRAIN) | 681501 |
| FURNISH BRIDGE DECK TREATMENT MATERIAL | 540108 |
| FURNISH BRIDGE DECK TREATMENT MATERIAL (LOW ODOR) | 540109 |
| FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (1219 MM) | 499052 |
| FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (460 MM) | 499024 |
| FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (610 MM) | 499030 |
| FURNISH FORMED PANEL SIGN (OVERHEAD) | 560233 |
| FURNISH FORMED PANEL SIGN (ROADSIDE) | 560232 |
| FURNISH LAMINATED PANEL SIGN (1"-TYPE A) | 560244 |
| FURNISH LAMINATED PANEL SIGN (1"-TYPE B) | 560245 |
| FURNISH LAMINATED PANEL SIGN (2 1/2"-TYPE B) | 560246 |
| FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE A) | 560234 |
| FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE B) | 560235 |
| FURNISH LAMINATED PANEL SIGN (63.5 MM-TYPE B) | 560236 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **F** | |
| FURNISH PILING (CLASS 140) | 490738 |
| FURNISH PILING (CLASS 400) | 491007 |
| FURNISH PILING (CLASS 400) (ALTERNATIVE W) | 491012 |
| FURNISH PILING (CLASS 625 MODIFIED) | 490755 |
| FURNISH PILING (CLASS 625) | 490753 |
| FURNISH PILING (CLASS 625) (ALTERNATIVE V) | 490770 |
| FURNISH PILING (CLASS 625) (ALTERNATIVE W) | 490772 |
| FURNISH PILING (CLASS 900) | 490696 |
| FURNISH PILING (CLASS 900) (ALTERNATIVE W) | 490700 |
| FURNISH POLYESTER CONCRETE OVERLAY | 515041 |
| FURNISH PRECAST PRESTRESSED CONCRETE BOX GIRDER (20 M - 25 M) | 512240 |
| FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (20 M-25 M) | 512253 |
| FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (90'-100') | 512278 |
| FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (15 M - 20 M) | 512231 |
| FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (20 M - 25 M) | 512232 |
| FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (25 M - 30 M) | 512233 |
| FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (30 M - 35 M) | 512234 |
| FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (5 M - 10 M) | 512229 |
| FURNISH REMOVABLE SIGN PANEL FRAME WITH SIGN PANELS ATTACHED | 560206 |
| FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY) | 560203 |
| FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY) | 560223 |
| FURNISH SIGN STRUCTURE (LIGHTWEIGHT) | 560213 |
| FURNISH SIGN STRUCTURE (TRUSS) | 560218 |
| FURNISH SIGN STRUCTURE (TUBULAR) | 560208 |
| FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED) | 560251 |
| FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED) | 560248 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **F** | |
| FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED) | 560252 |
| FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED) | 560249 |
| FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-FRAMED) | 560241 |
| FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-UNFRAMED) | 560238 |
| FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-FRAMED) | 560242 |
| FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-UNFRAMED) | 560239 |
| FURNISH STEEL PILING (HP 250 X 62) | 490505 |
| FURNISH STEEL PILING (HP 250 X 85) | 490511 |
| FURNISH STEEL PILING (HP 360 X 132) | 490566 |
| FURNISH STEEL PILING (HP 360 X 152) | 490568 |
| FURNISH STEEL PILING (HP 360 X 174) | 490570 |
| FURNISH STEEL PIPE PILING (406 MM) | 490582 |
| FURNISH STEEL PIPE PILING (610 MM) | 490584 |
| FURNISH STRUCTURAL STEEL (BRIDGE) | 550203 |
| **G** | |
| GABION | 722020 |
| GEOCOMPOSITE DRAIN | 681132 |
| GEOSYNTHETIC PAVEMENT INTERLAYER | 393003 |
| GRATED LINE DRAIN | 703233 |
| GRAVEL BLANKET | 193101 |
| GRIND EXISTING CONCRETE PAVEMENT | 420201 |
| GROOVE EXISTING CONCRETE PAVEMENT | 420102 |
| GUARD RAILING DELINEATOR | 820118 |
| **H** | |
| HANDRAILING | 839514 |
| HEADED BAR REINFORCEMENT | 520120 |
| HEALTH AND SAFETY PLAN | 074018 |
| HEAVY BLAST TEXTURE | 511046 |
| HIGH SPEED WEIGH-IN-MOTION SYSTEM | 861203 |
| HIGHWAY ADVISORY RADIO SYSTEM | 860520 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **H** | |
| HIGHWAY LIGHTING | 860403 |
| HIGHWAY PLANTING | 200001 |
| HOT MIX ASPHALT | 390130 |
| HOT MIX ASPHALT | 390131 |
| HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED) | 390142 |
| HOT MIX ASPHALT (BONDED WEARING COURSE-OPEN GRADED) | 390158 |
| HOT MIX ASPHALT (LEVELING) | 390135 |
| HOT MIX ASPHALT (OPEN GRADED) | 390134 |
| HOT MIX ASPHALT (TYPE A) | 390132 |
| HOT MIX ASPHALT (TYPE B) | 390133 |
| **I** | |
| IMPORTED BORROW | 198001 |
| IMPORTED MATERIAL (SHOULDER BACKING) | 198007 |
| IMPORTED RIVER GRAVEL | 198020 |
| IMPORTED ROCKY MATERIAL | 198021 |
| IMPORTED TOPSOIL | 200101 |
| INDUCTIVE LOOP DETECTOR | 860810 |
| INJECT CRACK (EPOXY) | 511130 |
| INLET FRAME AND GRATE | 750030 |
| INLET GRATE | 750050 |
| INLET GRATE (TYPE 36R) | 750049 |
| INSTALL DRAINAGE INLET MARKER | 700619 |
| INSTALL MEDIAN MILEAGE PANEL | 820180 |
| INSTALL ROADSIDE SIGN (LAMINATED WOOD BOX POST) | 568023 |
| INSTALL ROADSIDE SIGN PANEL ON EXISTING POST | 568017 |
| INSTALL SIGN (MAST-ARM HANGER METHOD) | 568015 |
| INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD) | 568001 |
| INSTALL SIGN OVERLAY | 568007 |
| INSTALL SIGN PANEL ON EXISTING FRAME | 568016 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **I** | |
| INSTALL SIGN PANEL ON EXISTING STRUCTURE | 568020 |
| INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY) | 560204 |
| INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY) | 560224 |
| INSTALL SIGN STRUCTURE (LIGHTWEIGHT) | 560214 |
| INSTALL SIGN STRUCTURE (TRUSS) | 560219 |
| INSTALL SIGN STRUCTURE (TUBULAR) | 560209 |
| INTERCONNECTION CONDUIT AND CABLE | 860703 |
| INTERCONNECTION CONDUIT AND CONDUCTOR | 860701 |
| IRON SULFATE | 202003 |
| IRRIGATION SLEEVE | 208310 |
| IRRIGATION SYSTEM | 208000 |
| ISOLATION CASING | 750041 |
| **J** | |
| JACKED 1050 MM REINFORCED CONCRETE PIPE (CLASS III) | 655370 |
| JACKED 1350 MM REINFORCED CONCRETE PIPE (CLASS IV) | 655464 |
| JACKED 30" WELDED STEEL PIPE (.239" THICK) | 704196 |
| JACKED 600 MM REINFORCED CONCRETE PIPE (CLASS II) | 655256 |
| JACKED 750 MM REINFORCED CONCRETE PIPE (CLASS IV) | 655460 |
| JACKED 900 MM REINFORCED CONCRETE PIPE (CLASS II) | 655258 |
| JOINT SEAL (ASPHALTIC PLUG) | 519133 |
| JOINT SEAL (MR 1 1/2") | 519091 |
| JOINT SEAL (MR 1") | 519088 |
| JOINT SEAL (MR 1/2") | 519081 |
| JOINT SEAL (MR 15 MM) | 519120 |
| JOINT SEAL (MR 2") | 519100 |
| JOINT SEAL (MR 30 MM) | 519117 |
| JOINT SEAL (MR 40 MM) | 519142 |
| JOINT SEAL (MR 50 MM) | 519144 |
| JOINT SEAL (TYPE A) | 519101 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **J** | |
| JOINT SEAL (TYPE AL) | 519102 |
| JOINT SEAL ASSEMBLY (MR 100 MM) | 519128 |
| JOINT SEAL ASSEMBLY (MR 101 MM - 160 MM) | 519129 |
| JOINT SEAL ASSEMBLY (MR 161 MM - 240 MM) | 519130 |
| JOINT SEAL ASSEMBLY (MR 2 1/2") | 519092 |
| JOINT SEAL ASSEMBLY (MR 241 MM - 320 MM) | 519131 |
| JOINT SEAL ASSEMBLY (MR 3 1/2") | 519094 |
| JOINT SEAL ASSEMBLY (MR 3") | 519093 |
| JOINT SEAL ASSEMBLY (MR 321 MM - 400 MM) | 519132 |
| JOINT SEAL ASSEMBLY (MR 4") | 519095 |
| JOINT SEAL ASSEMBLY (MR 5") | 519097 |
| JOINT SEAL ASSEMBLY (MR 6") | 519099 |
| JOINT SEAL ASSEMBLY (MR 60 MM) | 519124 |
| JOINT SEAL ASSEMBLY (MR 70 MM) | 519125 |
| JOINT SEAL ASSEMBLY (MR 80 MM) | 519126 |
| JUTE MESH | 203561 |
| **K** | |
| KILOMETER POST MARKER | 820114 |
| **L** | |
| LEAD COMPLIANCE PLAN | 190110 |
| LEAN CONCRETE BACKFILL | 193119 |
| LEAN CONCRETE BASE | 280000 |
| LIGHTING | 860401 |
| LIGHTING (CITY STREET) | 860402 |
| LIGHTING (LOCATION 1) | 860461 |
| LIGHTING (LOCATION 2) | 860462 |
| LIGHTING (STAGE CONSTRUCTION) | 860415 |
| LIGHTING (TEMPORARY) | 860400 |
| LIGHTING (TUNNEL) | 860420 |
| LIGHTING AND SIGN ILLUMINATION | 860460 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **L** | |
| LIGHTING AND SIGN ILLUMINATION (LOCATION 1) | 860551 |
| LIGHTING AND SIGN ILLUMINATION (LOCATION 2) | 860552 |
| LIGHTING AND SIGN ILLUMINATION (LOCATION 3) | 860553 |
| LIGHTING AND SIGN ILLUMINATION (LOCATION 4) | 860554 |
| LIGHTING CONDUIT (BRIDGE) | 860761 |
| LIGHTWEIGHT CONCRETE | 511001 |
| LIME | 240100 |
| LIQUID ASPHALT (PRIME COAT) | 395000 |
| LIQUID ASPHALT, MC-70 (PRIME COAT) | 395501 |
| LIQUID ASPHALT, SC-70 (PRIME COAT) | 395001 |
| **M** | |
| MAINTAIN EXISTING IRRIGATION FACILITIES | 206401 |
| MAINTAIN EXISTING PLANTED AREAS | 204096 |
| MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION | 860090 |
| MAINTENANCE VEHICLE PULLOUT | 209801 |
| MANHOLE | 719300 |
| MANHOLE (TYPE A) | 719305 |
| MANHOLE FRAME AND COVER | 750010 |
| MANHOLE FRAME AND COVER (PRESSURE) | 750013 |
| MARKER | 820101 |
| MARKER (CULVERT) | 820112 |
| MASONRY BLOCK WALL | 518201 |
| METAL (BARRIER MOUNTED SIGN) | 562002 |
| METAL (RAIL MOUNTED SIGN) | 562004 |
| METAL BEAM GUARD RAILING | 832001 |
| METAL BEAM GUARD RAILING (2.1 M POST) | 832062 |
| METAL BEAM GUARD RAILING (2.1 M WOOD POST) | 832061 |
| METAL BEAM GUARD RAILING (2.4 M POST) | 832063 |
| METAL BEAM GUARD RAILING (7' POST) | 832013 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **M** | |
| METAL BEAM GUARD RAILING (7' WOOD POST) | 832012 |
| METAL BEAM GUARD RAILING (8' POST) | 832014 |
| METAL BEAM GUARD RAILING (ELEMENT) | 832008 |
| METAL BEAM GUARD RAILING (SPECIAL) | 832004 |
| METAL BEAM GUARD RAILING (STEEL POST) | 832002 |
| METAL BEAM GUARD RAILING (WOOD POST) | 832003 |
| METAL CATTLE GUARD (4.3 M) | 558028 |
| METAL MARKER POST | 820109 |
| METAL RAILING | 833000 |
| MICROWAVE VEHICLE DETECTION SYSTEM | 860812 |
| MILEPOST MARKER | 820110 |
| MINOR CONCRETE | 510501 |
| MINOR CONCRETE (BACKFILL) | 510526 |
| MINOR CONCRETE (BACKFILL) | 719589 |
| MINOR CONCRETE (CHANNEL LINING) | 727905 |
| MINOR CONCRETE (CURB AND CURB RAMP) | 731626 |
| MINOR CONCRETE (CURB AND GUTTER) | 731504 |
| MINOR CONCRETE (CURB AND SIDEWALK) | 731505 |
| MINOR CONCRETE (CURB RAMP) | 731623 |
| MINOR CONCRETE (CURB) | 731501 |
| MINOR CONCRETE (CURB, GUTTER, SIDEWALK AND DRIVEWAY) | 731510 |
| MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP) | 731627 |
| MINOR CONCRETE (DITCH LINING) | 727901 |
| MINOR CONCRETE (DRIVEWAY) | 731516 |
| MINOR CONCRETE (EXPOSED AGGREGATE SIDEWALK) | 731512 |
| MINOR CONCRETE (GUTTER DEPRESSION) | 731507 |
| MINOR CONCRETE (GUTTER LINING) | 727906 |
| MINOR CONCRETE (GUTTER) | 731517 |
| MINOR CONCRETE (HEADWALL) | 510535 |
| MINOR CONCRETE (INVERT PAVING) | 510510 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **M** | |
| MINOR CONCRETE (ISLAND PAVING) | 731511 |
| MINOR CONCRETE (MINOR STRUCTURE) | 510502 |
| MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION) | 731502 |
| MINOR CONCRETE (PILE CAP) | 510700 |
| MINOR CONCRETE (PIPE ENCASEMENT) | 510504 |
| MINOR CONCRETE (SIDEWALK) | 731521 |
| MINOR CONCRETE (SLOPE PROTECTION) | 727902 |
| MINOR CONCRETE (SOUND WALL) | 510524 |
| MINOR CONCRETE (STAMPED CONCRETE) | 731519 |
| MINOR CONCRETE (TEXTURED PAVING) | 731530 |
| MINOR HOT MIX ASPHALT | 390136 |
| MISCELLANEOUS IRON AND STEEL | 750001 |
| MISCELLANEOUS METAL | 750500 |
| MISCELLANEOUS METAL (BRIDGE) | 750501 |
| MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE) | 750498 |
| MISCELLANEOUS METAL (RESTRAINER - PIPE TYPE) | 750496 |
| MISCELLANEOUS METAL (RETAINING WALL) | 750502 |
| MOBILIZATION | 999990 |
| MOBILIZATION, DEMOBILIZATION, AND FINAL CLEANUP | 760090 |
| MODIFY FLASHING BEACON | 860615 |
| MODIFY HEADWALL | 152602 |
| MODIFY INLET | 152604 |
| MODIFY INLET TO MANHOLE | 152609 |
| MODIFY LIGHTING | 861503 |
| MODIFY LIGHTING (LOCATION 1) | 861511 |
| MODIFY LIGHTING (LOCATION 2) | 861512 |
| MODIFY LIGHTING (LOCATION 3) | 861513 |
| MODIFY LIGHTING AND SIGN ILLUMINATION | 861504 |
| MODIFY MANHOLE | 152610 |
| MODIFY METAL BEAM GUARD RAILING | 152632 |
| MODIFY RAMP METERING SYSTEM | 861088 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **M** | |
| MODIFY SIGN ILLUMINATION | 860508 |
| MODIFY SIGN STRUCTURE | 152641 |
| MODIFY SIGNAL | 861502 |
| MODIFY SIGNAL (LOCATION 1) | 861491 |
| MODIFY SIGNAL (LOCATION 2) | 861492 |
| MODIFY SIGNAL AND LIGHTING | 861501 |
| MODIFY SIGNAL AND LIGHTING (LOCATION 1) | 861497 |
| MODIFY SIGNAL AND LIGHTING (LOCATION 2) | 861498 |
| MODIFY SIGNAL AND LIGHTING (LOCATION 3) | 861499 |
| MODIFY SIGNAL AND LIGHTING (LOCATION 4) | 861500 |
| MODIFY SIGNAL AND LIGHTING (LOCATION 5) | 861505 |
| MODIFY SIGNAL AND LIGHTING (LOCATION 6) | 861506 |
| MODIFY SIGNAL AND LIGHTING (LOCATION 7) | 861507 |
| MODIFY SIGNAL AND LIGHTING (LOCATION 8) | 861508 |
| MODIFY SIGNAL AND LIGHTING (LOCATION 9) | 861509 |
| MODIFY TRAFFIC MONITORING STATION | 860889 |
| MODIFY TRAFFIC MONITORING STATION (COUNT) | 860890 |
| MOVE-IN/MOVE-OUT (EROSION CONTROL) | 203026 |
| MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL) | 074037 |
| MULCH | 202011 |
| **N** | |
| NO. 5(T) PULL BOX | 869034 |
| NPS 2 SUPPLY LINE (BRIDGE) | 208036 |
| NPS 3 SUPPLY LINE (BRIDGE) | 208038 |
| NPS 4 SUPPLY LINE (BRIDGE) | 208039 |
| **O** | |
| OBJECT MARKER | 820130 |
| OBJECT MARKER (TYPE K) | 820131 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **O** | |
| OBJECT MARKER (TYPE K-1) | 820141 |
| OBJECT MARKER (TYPE L) | 820132 |
| OBJECT MARKER (TYPE L-1) | 820151 |
| OBJECT MARKER (TYPE L-2) | 820152 |
| OBJECT MARKER (TYPE N) | 820133 |
| OBJECT MARKER (TYPE P) | 820134 |
| OBJECT MARKER (TYPE R) | 820135 |
| OBLITERATE SURFACING | 150305 |
| **P** | |
| PAINT CONCRETE SURFACES | 590280 |
| PAINT CURB (2-COAT) | 597401 |
| PAINT PAVEMENT MARKING | 840660 |
| PAINT PAVEMENT MARKING (2-COAT) | 840666 |
| PAINT STRUCTURAL STEEL (EXISTING BRIDGE) | 590111 |
| PAINT TRAFFIC STRIPE | 840653 |
| PAINT TRAFFIC STRIPE (1-COAT) | 840655 |
| PAINT TRAFFIC STRIPE (2-COAT) | 840656 |
| PAINTED STALL LINES AND PAVEMENT MARKINGS | 840651 |
| PAINTED TRAFFIC STRIPE | 840600 |
| PARKING BUMPER (PRECAST CONCRETE) | 842000 |
| PAVEMENT MARKER (NON-REFLECTIVE-RECESSED) | 850121 |
| PAVEMENT MARKER (NON-REFLECTIVE) | 850101 |
| PAVEMENT MARKER (REFLECTIVE) | 850102 |
| PAVEMENT MARKER (REFLECTIVE-SPECIAL TYPE G) | 850103 |
| PAVEMENT MARKER (REFLECTIVE-SPECIAL TYPE H) | 850104 |
| PAVEMENT MARKER (RETROREFLECTIVE) | 850111 |
| PAVEMENT MARKER (RETROREFLECTIVE-RECESSED) | 850122 |
| PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE G) | 850112 |
| PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE H) | 850113 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **P** | |
| PAVEMENT REINFORCING FABRIC | 393001 |
| PAVEMENT TRANSITION TAPER | 416101 |
| PAVING ASPHALT (BINDER, GEOSYNTHETIC PAVEMENT INTERLAYER) | 391007 |
| PAVING ASPHALT (BINDER-PAVEMENT REINFORCING FABRIC) | 391031 |
| PAVING ASPHALT (BINDER-PAVEMENT REINFORCING FABRIC) | 391005 |
| PAVING NOTCH EXTENSION | 510800 |
| PEDESTRIAN BARRICADE | 833077 |
| PERMEABLE MATERIAL | 682001 |
| PERMEABLE MATERIAL (BLANKET) | 682008 |
| PERVIOUS BACKFILL MATERIAL | 193030 |
| PERVIOUS BACKFILL MATERIAL (RETAINING WALL) | 193031 |
| PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA) | 394002 |
| PLACE ASPHALT CONCRETE DIKE | 394001 |
| PLACE ASPHALT CONCRETE DIKE (TYPE A) | 394040 |
| PLACE ASPHALT CONCRETE DIKE (TYPE C) | 394044 |
| PLACE ASPHALT CONCRETE DIKE (TYPE D) | 394046 |
| PLACE ASPHALT CONCRETE DIKE (TYPE E) | 394048 |
| PLACE ASPHALT CONCRETE DIKE (TYPE F) | 394049 |
| PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA) | 394090 |
| PLACE HOT MIX ASPHALT DIKE | 394071 |
| PLACE HOT MIX ASPHALT DIKE (TYPE A) | 394073 |
| PLACE HOT MIX ASPHALT DIKE (TYPE C) | 394074 |
| PLACE HOT MIX ASPHALT DIKE (TYPE D) | 394075 |
| PLACE HOT MIX ASPHALT DIKE (TYPE E) | 394076 |
| PLACE HOT MIX ASPHALT DIKE (TYPE F) | 394077 |
| PLACE POLYESTER CONCRETE OVERLAY | 515042 |
| PLANT (GROUP A) | 204001 |
| PLANT (GROUP A) | 204035 |
| PLANT (GROUP B) | 204002 |
| PLANT (GROUP B) | 204036 |
| PLANT (GROUP F) | 204006 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **P** | |
| PLANT (GROUP G) | 204007 |
| PLANT (GROUP H) | 204008 |
| PLANT (GROUP I) | 204009 |
| PLANT (GROUP K) | 204011 |
| PLANT (GROUP M) | 204013 |
| PLANT (GROUP U) | 204021 |
| PLANT (GROUP U) | 204038 |
| PLANT (GROUP W) | 204017 |
| PLANT (GROUP Z) | 204022 |
| PLANT ESTABLISHMENT WORK | 204099 |
| PLASTIC PIPE LINER (16.00" O.D.) | 152661 |
| PLASTIC PIPE LINER (21.50" O.D.) | 152664 |
| PORTABLE CHANGEABLE MESSAGE SIGN | 128650 |
| PORTABLE DELINEATOR | 120182 |
| PORTLAND CEMENT CONCRETE (PATCH) | 511121 |
| PREPARE AND PAINT CONCRETE | 597600 |
| PREPARE AND STAIN CONCRETE | 597601 |
| PREPARE CONCRETE BRIDGE DECK SURFACE | 153225 |
| PREPARE STORM WATER POLLUTION PREVENTION PLAN | 074019 |
| PREPARE WATER POLLUTION CONTROL PROGRAM | 074017 |
| PRESTRESSING | 500010 |
| PRESTRESSING CAST-IN-PLACE CONCRETE | 500001 |
| PROGRESS SCHEDULE (CRITICAL PATH METHOD) | 070012 |
| PROGRESS SCHEDULE (CRITICAL PATH) | 070010 |
| PRUNE EXISTING PLANTS | 200052 |
| PTFE BEARING | 518050 |
| PTFE SPHERICAL BEARING | 518051 |
| PURE LIVE SEED (EROSION CONTROL) | 203045 |
| **Q** | |
| QUICK COUPLING VALVE | 208649 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **R** | |
| RAIL TENSIONING ASSEMBLY | 839561 |
| RAMP METERING SYSTEM | 861100 |
| RAMP METERING SYSTEM (LOCATION 1) | 861101 |
| RAMP METERING SYSTEM (LOCATION 2) | 861102 |
| RAMP METERING SYSTEM (LOCATION 3) | 861103 |
| RAMP METERING SYSTEM (LOCATION 4) | 861104 |
| RAMP METERING SYSTEM (LOCATION 5) | 861105 |
| RAPID SETTING CONCRETE (PATCH) | 511124 |
| REAMING WATER WELL | 760022 |
| RECONSTRUCT CHAIN LINK FENCE | 151540 |
| RECONSTRUCT CHAIN LINK GATE | 151554 |
| RECONSTRUCT DOUBLE THRIE BEAM BARRIER | 151570 |
| RECONSTRUCT DRAINAGE FACILITY | 151510 |
| RECONSTRUCT FENCE | 151531 |
| RECONSTRUCT FENCE (TYPE BW) | 151536 |
| RECONSTRUCT FENCE (TYPE WM) | 151537 |
| RECONSTRUCT INLET | 151512 |
| RECONSTRUCT METAL BEAM GUARD RAILING | 151572 |
| RECONSTRUCT METAL BEAM GUARD RAILING (7' POST) | 151623 |
| RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST) | 151625 |
| RECONSTRUCT THRIE BEAM BARRIER | 151568 |
| RECONSTRUCT WOOD FENCE | 151534 |
| RECYCLED WATER WARNING SIGNS | 209202 |
| REFINISH BRIDGE DECK | 515020 |
| REINFORCED CONCRETE CRIB WALL (TYPE C) | 513603 |
| REINFORCED CONCRETE CRIB WALL (TYPE D) | 513604 |
| RELAY ENTRANCE TAPER AND PIPE DOWNDRAIN | 152037 |
| RELAY METAL FLARED END SECTION | 152043 |
| RELOCATE CONCRETE BARRIER (TYPE K) | 152372 |
| RELOCATE ELECTROLIER | 861290 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **R** | |
| RELOCATE EXTINGUISHABLE MESSAGE SIGN | 861295 |
| RELOCATE FENCE | 152379 |
| RELOCATE FLASHING BEACON | 861303 |
| RELOCATE GATE | 152381 |
| RELOCATE HYDRANT | 152351 |
| RELOCATE MAILBOX | 152370 |
| RELOCATE MARKER | 152385 |
| RELOCATE ROADSIDE SIGN | 152390 |
| RELOCATE ROADSIDE SIGN (METAL POST) | 152391 |
| RELOCATE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD) | 152393 |
| RELOCATE ROADSIDE SIGN (WOOD POST) | 152392 |
| RELOCATE ROADSIDE SIGN-ONE POST | 152386 |
| RELOCATE ROADSIDE SIGN-TWO POST | 152387 |
| RELOCATE SIGN PANEL | 152396 |
| RELOCATE SIGN STRUCTURE | 152394 |
| RELOCATE WATER METER | 152410 |
| REMODEL INLET | 152703 |
| REMOVABLE BARRIER POST | 839522 |
| REMOVE ASPHALT CONCRETE | 150769 |
| REMOVE ASPHALT CONCRETE DIKE | 150771 |
| REMOVE ASPHALT CONCRETE OVERSIDE DRAIN | 150859 |
| REMOVE ASPHALT CONCRETE SURFACING | 150857 |
| REMOVE BARRICADE | 150645 |
| REMOVE BASE AND SURFACING | 150860 |
| REMOVE BOX CULVERT | 156535 |
| REMOVE BRIDGE MOUNTED SIGN | 150767 |
| REMOVE BRIDGE RAILING | 156579 |
| REMOVE CABLE ANCHOR ASSEMBLY | 150658 |
| REMOVE CABLE BARRIER | 150656 |
| REMOVE CATCH BASIN | 150827 |
| REMOVE CHAIN LINK FENCE | 150608 |
| REMOVE CHANNELIZERS | 150730 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **R** | |
| REMOVE CONCRETE | 153210 |
| REMOVE CONCRETE (CHANNEL) | 153220 |
| REMOVE CONCRETE (CURB AND GUTTER) | 153215 |
| REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK) | 153239 |
| REMOVE CONCRETE (MISCELLANEOUS) | 153246 |
| REMOVE CONCRETE (STRUCTURE) | 153213 |
| REMOVE CONCRETE BARRIER | 153221 |
| REMOVE CONCRETE BARRIER (TYPE 50) | 153230 |
| REMOVE CONCRETE BARRIER (TYPE K) | 153229 |
| REMOVE CONCRETE CURB | 153214 |
| REMOVE CONCRETE CURB AND SIDEWALK | 153216 |
| REMOVE CONCRETE DECK SURFACE | 150870 |
| REMOVE CONCRETE ISLAND (PORTIONS) | 153222 |
| REMOVE CONCRETE PAVEMENT | 150846 |
| REMOVE CONCRETE PAVEMENT AND BASE | 150847 |
| REMOVE CONCRETE SIDEWALK | 153218 |
| REMOVE CONTRAST TREATMENT | 150720 |
| REMOVE CRASH CUSHION | 156585 |
| REMOVE CRASH CUSHION (SAND FILLED) | 156590 |
| REMOVE CULVERT | 150805 |
| REMOVE CURB | 150772 |
| REMOVE DELINEATOR | 151224 |
| REMOVE DOUBLE METAL BEAM BARRIER | 150667 |
| REMOVE DOWNDRAIN | 150823 |
| REMOVE DRAINAGE FACILITY | 150804 |
| REMOVE ENTRANCE TAPER | 150615 |
| REMOVE EXISTING SIGNAL SYSTEM | 861349 |
| REMOVE FENCE | 150605 |
| REMOVE FENCE (TYPE BW) | 150606 |
| REMOVE FENCE (TYPE WM) | 150607 |
| REMOVE FLARED END SECTION | 150668 |
| REMOVE FLASHING BEACON AND LIGHTING | 861490 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **R** | |
| REMOVE GATE | 150620 |
| REMOVE HEADWALL | 150821 |
| REMOVE INLET | 150820 |
| REMOVE IRRIGATION FACILITY | 150685 |
| REMOVE JUNCTION BOX | 150828 |
| REMOVE LIGHTING STANDARD | 868007 |
| REMOVE MANHOLE | 150826 |
| REMOVE MARKER | 150630 |
| REMOVE METAL BEAM BARRIER | 150666 |
| REMOVE METAL BEAM GUARD RAILING | 150662 |
| REMOVE OVERSIDE DRAIN | 150801 |
| REMOVE PAINTED PAVEMENT MARKING | 150712 |
| REMOVE PAINTED TRAFFIC STRIPE | 150711 |
| REMOVE PAVEMENT MARKER | 150722 |
| REMOVE PAVEMENT MARKING | 150713 |
| REMOVE PEDESTRIAN BARRICADE | 150646 |
| REMOVE PIPE | 150806 |
| REMOVE PULL BOX | 869043 |
| REMOVE RAILING | 156572 |
| REMOVE REINFORCED CONCRETE BOX CULVERT | 150825 |
| REMOVE RETAINING WALL | 150829 |
| REMOVE RETAINING WALL (PORTION) | 150830 |
| REMOVE ROADSIDE SIGN | 150742 |
| REMOVE ROADSIDE SIGN (METAL POST) | 150745 |
| REMOVE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD) | 150747 |
| REMOVE ROADSIDE SIGN (WOOD POST) | 150744 |
| REMOVE ROADSIDE SIGN MOUNTED ON MAST ARM | 150741 |
| REMOVE ROADSIDE SIGN PANEL | 150748 |
| REMOVE SIGN | 150740 |
| REMOVE SIGN OVERLAY | 150764 |
| REMOVE SIGN PANEL | 150763 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **R** | |
| REMOVE SIGN PANEL AND REMOVABLE SIGN PANEL FRAME | 150761 |
| REMOVE SIGN STRUCTURE | 150760 |
| REMOVE SINGLE METAL BEAM BARRIER | 150665 |
| REMOVE SLOPE PAVING | 150844 |
| REMOVE SOUND WALL | 153250 |
| REMOVE TERMINAL SECTION | 150659 |
| REMOVE THERMOPLASTIC PAVEMENT MARKING | 150715 |
| REMOVE THERMOPLASTIC TRAFFIC STRIPE | 150714 |
| REMOVE THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING | 150718 |
| REMOVE TRAFFIC STRIPE | 150710 |
| REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING | 150717 |
| REMOVE TREE | 160120 |
| REMOVE UNSOUND CONCRETE | 153223 |
| REMOVE WOOD FENCE | 150604 |
| REMOVE YELLOW PAINTED TRAFFIC STRIPE | 150701 |
| REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING | 150705 |
| REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE | 150704 |
| REPAIR SPALLED JOINTS | 413111 |
| REPAIR SPALLED SURFACE AREA | 515028 |
| REPLACE ASPHALT CONCRETE SURFACING | 390095 |
| REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE) | 401108 |
| REPLACE PULL BOX | 862065 |
| REPLACE VALVE BOX COVER | 208565 |
| RESET CRASH CUSHION | 152315 |
| RESET GATE | 152291 |
| RESET MAILBOX | 152255 |
| RESET MARKER | 152301 |
| RESET MARKERS AND DELINEATORS | 152303 |
| RESET MILEPOST MARKER | 152299 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **R** | |
| RESET OBJECT MARKER | 152300 |
| RESET ROADSIDE SIGN | 152320 |
| RESET ROADSIDE SIGN (ONE POST) | 152316 |
| RESET ROADSIDE SIGN (TWO POST) | 152317 |
| RESET ROADSIDE SIGN (WOOD POST) | 152322 |
| RESET STRUCTURE MOUNTED SIGN | 152329 |
| RESET TEMPORARY RAILING (TYPE K) | 158210 |
| RESHAPE SHOULDER | 190183 |
| RETAINING WALL STEM (TYPE 6) | 513551 |
| RETURN CAP | 839571 |
| RETURN CAP (TYPE TA) | 839572 |
| RIPPED TEXTURE (ROPE) | 511071 |
| ROADSIDE CLEARING | 200002 |
| ROADSIDE PAVING (MISCELLANEOUS AREAS) | 394095 |
| ROADSIDE SIGN - ONE POST | 566011 |
| ROADSIDE SIGN - TWO POST | 566012 |
| ROADSIDE SIGN (METAL POST) | 562007 |
| ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD) | 566013 |
| ROADWAY EXCAVATION | 190101 |
| ROADWAY EXCAVATION (GORE REMOVAL) | 190134 |
| ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS) | 190109 |
| ROADWAY EXCAVATION (SLIDE REMOVAL) | 190130 |
| ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD) | 190107 |
| ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD) | 190108 |
| ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD) | 190105 |
| ROADWAY EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD) | 190106 |
| ROADWAY GRADING | 190135 |
| ROCK BLANKET | 200114 |
| ROCK EXCAVATION | 190161 |
| ROCK SLOPE PROTECTION (1 TON, METHOD A) | 720104 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **R** | |
| ROCK SLOPE PROTECTION (1/2 TON, METHOD A) | 720106 |
| ROCK SLOPE PROTECTION (1/2 TON, METHOD B) | 721006 |
| ROCK SLOPE PROTECTION (1/2T, METHOD A) | 720120 |
| ROCK SLOPE PROTECTION (1/2T, METHOD B) | 721023 |
| ROCK SLOPE PROTECTION (1/4 TON, METHOD B) | 721007 |
| ROCK SLOPE PROTECTION (1/4T, METHOD B) | 721024 |
| ROCK SLOPE PROTECTION (1T, METHOD A) | 720119 |
| ROCK SLOPE PROTECTION (1T, METHOD B) | 721022 |
| ROCK SLOPE PROTECTION (2T, METHOD A) | 720118 |
| ROCK SLOPE PROTECTION (4 TON, METHOD A) | 720102 |
| ROCK SLOPE PROTECTION (4T, METHOD A) | 720117 |
| ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B) | 721010 |
| ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B) | 721011 |
| ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B) | 721012 |
| ROCK SLOPE PROTECTION (FACING, METHOD B) | 721009 |
| ROCK SLOPE PROTECTION (LIGHT, METHOD B) | 721008 |
| ROCK SLOPE PROTECTION FABRIC | 729010 |
| ROOT PROTECTOR | 205061 |
| RUBBERIZED ASPHALT CONCRETE (TYPE G) | 390126 |
| RUBBERIZED ASPHALT CONCRETE (TYPE O) | 390127 |
| RUBBERIZED HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED) | 390157 |
| RUBBERIZED HOT MIX ASPHALT (BONDED WEARING COURSE-OPEN GRADED) | 390159 |
| RUBBERIZED HOT MIX ASPHALT (GAP GRADED) | 390137 |
| RUBBERIZED HOT MIX ASPHALT (GAP GRADED) | 390140 |
| RUBBERIZED HOT MIX ASPHALT (OPEN GRADED HIGH BINDER) | 390139 |
| RUBBERIZED HOT MIX ASPHALT (OPEN GRADED) | 390138 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **R** | |
| RUMBLE STRIP | 394050 |
| **S** | |
| SACKED CONCRETE SLOPE PROTECTION | 725001 |
| SALVAGE CONCRETE BARRIER (TYPE K) | 151274 |
| SALVAGE CRASH CUSHION | 158100 |
| SALVAGE DOUBLE METAL BEAM BARRIER | 151278 |
| SALVAGE DOUBLE THRIE BEAM BARRIER | 151266 |
| SALVAGE FRAME AND GRATE | 151227 |
| SALVAGE GRATE | 151226 |
| SALVAGE METAL BEAM GUARD RAILING | 151272 |
| SALVAGE METAL BRIDGE RAILING | 151270 |
| SALVAGE ROADSIDE SIGN PANEL | 151282 |
| SAMPLING AND ANALYSIS PLAN (NATURALLY OCCURRING ASBESTOS) | 190117 |
| SAND BACKFILL | 193114 |
| SAND COVER | 365001 |
| SCREENINGS (COARSE) | 375023 |
| SCREENINGS (HOT-APPLIED) | 375030 |
| SCREENINGS (MEDIUM FINE) | 375021 |
| SCREENINGS (MEDIUM) | 375022 |
| SEAL COURSE CONCRETE | 510000 |
| SEAL JOINT (EXISTING CONCRETE PAVEMENT) | 413115 |
| SEAL LONGITUDINAL ISOLATION JOINT | 404094 |
| SEAL LONGITUDINAL JOINT | 414091 |
| SEAL PAVEMENT JOINT | 404092 |
| SEAL RANDOM CRACKS | 374206 |
| SEAL TRANSVERSE JOINT | 414101 |
| SEEDING | 204051 |
| SEISMIC MONITORING SYSTEM | 869072 |
| SEWER MANHOLE | 719200 |
| SEWER MANHOLE B | 719202 |
| SEWER MANHOLE FRAME AND COVER | 719190 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **S** | |
| SHATTER CONCRETE | 153540 |
| SHOTCRETE | 530100 |
| SHOULDER BACKING | 190185 |
| SHOULDER RUMBLE STRIP (AC, GROUND-IN INDENTATIONS) | 394054 |
| SHOULDER RUMBLE STRIP (AC, ROLLED-IN INDENTATIONS) | 394052 |
| SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS) | 394053 |
| SHOULDER RUMBLE STRIP (HMA,ROLLED-IN INDENTATIONS) | 394051 |
| SHOULDER RUMBLE STRIP (PCC, GROUND-IN INDENTATIONS) | 401082 |
| SHOULDER RUMBLE STRIP (PCC, ROLLED-IN INDENTATIONS) | 401080 |
| SIGN ILLUMINATION | 860501 |
| SIGNAL AND LIGHTING | 860201 |
| SIGNAL AND LIGHTING | 860301 |
| SIGNAL AND LIGHTING (CITY STREET LOCATION 1) | 860300 |
| SIGNAL AND LIGHTING (CITY STREET LOCATION 2) | 860302 |
| SIGNAL AND LIGHTING (CITY STREET LOCATION 3) | 860303 |
| SIGNAL AND LIGHTING (CITY STREET LOCATION 4) | 860304 |
| SIGNAL AND LIGHTING (CITY) | 860297 |
| SIGNAL AND LIGHTING (LOCATION 1) | 860251 |
| SIGNAL AND LIGHTING (LOCATION 2) | 860252 |
| SIGNAL AND LIGHTING (LOCATION 3) | 860253 |
| SIGNAL AND LIGHTING (LOCATION 4) | 860254 |
| SIGNAL AND LIGHTING (LOCATION 5) | 860255 |
| SIGNAL AND LIGHTING (LOCATION 6) | 860256 |
| SIGNAL AND LIGHTING (LOCATION 7) | 860257 |
| SIGNAL AND LIGHTING (STAGE CONSTRUCTION) | 860298 |
| SIGNAL AND LIGHTING (TEMPORARY) | 860150 |
| SINGLE THRIE BEAM BARRIER | 839301 |
| SINGLE THRIE BEAM BARRIER (STEEL POST) | 839303 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **S** | |
| SINGLE THRIE BEAM BARRIER (WOOD POST) | 839302 |
| SLOPE PAVING (CONCRETE) | 721810 |
| SLOPE PAVING (MASONRY BLOCK) | 721811 |
| SLURRY SEAL | 377501 |
| SNOW POLE MARKER | 820115 |
| SNOWPLOW DEFLECTOR | 519078 |
| SOIL AMENDMENT | 202006 |
| SOIL NAIL ASSEMBLY | 197060 |
| SOUND WALL (BARRIER) (MASONRY BLOCK) | 517961 |
| SOUND WALL (MASONRY BLOCK) | 518002 |
| SPLICE VAULT | 869047 |
| SPOT BLAST CLEAN AND PAINT UNDERCOAT | 590135 |
| SPRINKLER (TYPE A-1) | 208461 |
| SPRINKLER (TYPE A-3) | 208463 |
| SPRINKLER (TYPE A-4) | 208464 |
| SPRINKLER (TYPE A-5) | 208465 |
| SPRINKLER (TYPE A-6) | 208466 |
| SPRINKLER (TYPE A-7) | 208467 |
| SPRINKLER (TYPE A-8) | 208468 |
| SPRINKLER (TYPE B-1) | 208471 |
| SPRINKLER (TYPE B-2) | 208472 |
| SPRINKLER (TYPE C-2) | 208482 |
| SPRINKLER (TYPE C-3) | 208483 |
| SPRINKLER (TYPE D-1) | 208526 |
| SPRINKLER CONTROL CONDUIT (BRIDGE) | 860796 |
| SPRINKLER TYPE C-2 MOD | 208480 |
| STABILIZING EMULSION (EROSION CONTROL) | 203061 |
| STEEL GRADE STAKE | 075021 |
| STEEL SHEET PILING | 490801 |
| STRAW (EROSION CONTROL) | 203003 |
| STREET SWEEPING | 074041 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **S** | |
| STRIPPING EXCAVATION | 190162 |
| STRUCTURAL CONCRETE | 510050 |
| STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ) | 510085 |
| STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N MODIFIED) | 510088 |
| STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N) | 510086 |
| STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R) | 510087 |
| STRUCTURAL CONCRETE, BARRIER SLAB | 510072 |
| STRUCTURAL CONCRETE, BRIDGE | 510053 |
| STRUCTURAL CONCRETE, BRIDGE FOOTING | 510051 |
| STRUCTURAL CONCRETE, PIER COLUMN | 510065 |
| STRUCTURAL CONCRETE, RETAINING WALL | 510060 |
| STRUCTURAL CONCRETE, SOUND WALL | 510061 |
| STRUCTURAL STEEL | 550101 |
| STRUCTURAL STEEL (BRIDGE) | 550102 |
| STRUCTURE BACKFILL | 193001 |
| STRUCTURE BACKFILL (BRIDGE) | 193003 |
| STRUCTURE BACKFILL (CRIB WALL) | 193012 |
| STRUCTURE BACKFILL (CULVERT) | 193004 |
| STRUCTURE BACKFILL (RETAINING WALL) | 193013 |
| STRUCTURE BACKFILL (SLURRY CEMENT) | 193006 |
| STRUCTURE BACKFILL (SOIL NAIL WALL) | 193028 |
| STRUCTURE BACKFILL (SOLDIER PILE WALL) | 193029 |
| STRUCTURE BACKFILL (SOUND WALL) | 193014 |
| STRUCTURE BACKFILL (TIEBACK WALL) | 193026 |
| STRUCTURE EXCAVATION | 192001 |
| STRUCTURE EXCAVATION (BRIDGE) | 192003 |
| STRUCTURE EXCAVATION (CRIB WALL) | 192036 |
| STRUCTURE EXCAVATION (CULVERT) | 192025 |
| STRUCTURE EXCAVATION (PIER COLUMN) | 192031 |
| STRUCTURE EXCAVATION (RETAINING WALL) | 192037 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **S** | |
| STRUCTURE EXCAVATION (ROCK) | 192035 |
| STRUCTURE EXCAVATION (SOIL NAIL WALL) | 192055 |
| STRUCTURE EXCAVATION (SOLDIER PILE WALL) | 192049 |
| STRUCTURE EXCAVATION (SOUND WALL) | 192038 |
| STRUCTURE EXCAVATION (TIEBACK WALL) | 192050 |
| STRUCTURE EXCAVATION (TYPE A) | 192008 |
| STRUCTURE EXCAVATION (TYPE D) | 192020 |
| STRUCTURE EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD) | 192057 |
| STRUCTURE EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD) | 192053 |
| STRUCTURE EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD) | 192054 |
| SUBGRADE ENHANCEMENT FABRIC | 198200 |
| SURVEY MONUMENT | 810110 |
| SURVEY MONUMENT (TYPE A) | 810111 |
| SURVEY MONUMENT (TYPE B) | 810112 |
| SURVEY MONUMENT (TYPE D) | 810116 |
| SYSTEM TESTING AND DOCUMENTATION | 869075 |
| **T** | |
| TACK COAT | 397005 |
| TAPERED INLET | 692101 |
| TEMPORARY ACTIVE TREATMENT SYSTEM | 074015 |
| TEMPORARY CHECK DAM | 074035 |
| TEMPORARY CONCRETE WASHOUT (PORTABLE) | 074042 |
| TEMPORARY CONCRETE WASHOUT BIN | 074043 |
| TEMPORARY CONCRETE WASHOUT FACILITY | 074032 |
| TEMPORARY CONSTRUCTION ENTRANCE | 074033 |
| TEMPORARY COVER | 074034 |
| TEMPORARY CRASH CUSHION | 129110 |
| TEMPORARY CRASH CUSHION MODULE | 129100 |
| TEMPORARY CULVERT | 073000 |
| TEMPORARY DELINEATOR (CLASS 1) | 128201 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **T** | |
| TEMPORARY DRAINAGE INLET PROTECTION | 074038 |
| TEMPORARY EROSION CONTROL | 074023 |
| TEMPORARY EROSION CONTROL BLANKET | 074027 |
| TEMPORARY FENCE | 071301 |
| TEMPORARY FENCE (TYPE BW) | 071302 |
| TEMPORARY FENCE (TYPE CL-1.8) | 071322 |
| TEMPORARY FENCE (TYPE CL-6) | 071321 |
| TEMPORARY FENCE (TYPE ESA) | 071325 |
| TEMPORARY FENCE (TYPE WM) | 071303 |
| TEMPORARY FIBER ROLL | 074028 |
| TEMPORARY FLASHING BEACON | 128660 |
| TEMPORARY GRAVEL BAG BERM | 074031 |
| TEMPORARY HYDRAULIC MULCH | 074051 |
| TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX) | 074040 |
| TEMPORARY HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX) | 074039 |
| TEMPORARY METAL BEAM GUARD RAILING | 121140 |
| TEMPORARY MULCH | 074026 |
| TEMPORARY PAVEMENT MARKER | 120300 |
| TEMPORARY PAVEMENT MARKING | 120150 |
| TEMPORARY PAVEMENT MARKING (PAINT) | 120149 |
| TEMPORARY PAVEMENT MARKING (TAPE) | 120152 |
| TEMPORARY RAILING (TYPE K) | 129000 |
| TEMPORARY RETAINING WALL | 129510 |
| TEMPORARY SIGNAL SYSTEM | 128601 |
| TEMPORARY SILT FENCE | 074029 |
| TEMPORARY SOIL BINDER | 074055 |
| TEMPORARY STRAW BALE | 074030 |
| TEMPORARY STRAW BALE BARRIER | 074036 |
| TEMPORARY SUPPORT | 072006 |
| TEMPORARY TERMINAL SECTION (TYPE K) | 121161 |
| TEMPORARY TRAFFIC SCREEN | 129150 |
| TEMPORARY TRAFFIC STRIPE (PAINT) | 120159 |

| ITEM DESCRIPTION | ITEM CODE |
|---|---|
| **T** | |
| TEMPORARY TRAFFIC STRIPE (TAPE) | 120151 |
| TERMINAL ANCHOR ASSEMBLY (TYPE CA) | 839569 |
| TERMINAL ANCHOR ASSEMBLY (TYPE SFT) | 839568 |
| TERMINAL SECTION (TYPE C) | 839552 |
| TERMINAL SYSTEM (TYPE CAT) | 839566 |
| TERMINAL SYSTEM (TYPE CAT) BACKUP | 839567 |
| TERMINAL SYSTEM (TYPE ET) | 839559 |
| TERMINAL SYSTEM (TYPE SRT) | 839565 |
| TESTING WELL | 760012 |
| THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING | 840519 |
| THERMOPLASTIC PAVEMENT MARKING | 840515 |
| THERMOPLASTIC TRAFFIC STRIPE | 840501 |
| THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE) | 840560 |
| TIE BAR | 406001 |
| TIE BAR (DRILL AND BOND) | 406003 |
| TIEBACK ANCHOR | 500050 |
| TIEDOWN ANCHOR | 500060 |
| TIMBER LAGGING | 575004 |
| TIME-RELATED OVERHEAD | 070018 |
| TRAFFIC CONE | 120119 |
| TRAFFIC CONTROL SURVEILLANCE | 120102 |
| TRAFFIC CONTROL SYSTEM | 120100 |
| TRAFFIC MONITORING STATION | 860930 |
| TRAFFIC MONITORING STATION (COUNT) | 860925 |
| TRAFFIC MONITORING STATION (LOCATION 1) | 860931 |
| TRAFFIC MONITORING STATION (LOCATION 2) | 860932 |
| TRAFFIC MONITORING STATION (LOCATION 3) | 860933 |
| TRAFFIC MONITORING STATION (LOCATION 4) | 860934 |
| TRAFFIC MONITORING STATION (LOCATION 5) | 860935 |
| TRAFFIC MONITORING STATION (LOCATION 6) | 860936 |

| ITEM DESCRIPTION | ITEM CODE | ITEM DESCRIPTION | ITEM CODE |
|---|---|---|---|
| **T** | | | |
| TRAFFIC MONITORING STATION (LOCATION 7) | 860937 | | |
| TRAFFIC MONITORING STATION (LOCATION 8) | 860938 | | |
| TRAFFIC PLASTIC DRUM | 120199 | | |
| TRAINING | 869080 | | |
| TRANSITION RAILING (TYPE DTB) | 839542 | | |
| TRANSITION RAILING (TYPE STB) | 839540 | | |
| TRANSITION RAILING (TYPE WB) | 839541 | | |
| TRANSPLANT PALM TREE | 204031 | | |
| TRANSPLANT TREE | 204030 | | |
| TREAT BRIDGE DECK | 540102 | | |
| TUBULAR HANDRAILING | 833088 | | |
| TUBULAR HANDRAILING (MODIFIED) | 833090 | | |
| TWO-COMPONENT PAINT PAVEMENT MARKING | 840661 | | |
| TYPE II BARRICADE | 120116 | | |
| TYPE III BARRICADE | 120120 | | |
| **U** | | | |
| UNDERDRAIN MARKER | 820111 | | |
| **V** | | | |
| VEGETATION CONTROL (MINOR CONCRETE) | 832070 | | |
| **W** | | | |
| WATER METER | 208304 | | |
| WATER POLLUTION CONTROL | 074020 | | |
| WELDED STEEL PIPE CASING (BRIDGE) | 703450 | | |
| WELL DEVELOPMENT | 760011 | | |
| WELL SCREEN | 760035 | | |
| WILD FLOWER SEEDING | 204053 | | |
| WILDLIFE PASSAGE WAY (TYPE M) | 833073 | | |
| WOOD FENCE | 800701 | | |
| WORK AREA MONITORING | 590301 | | |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **070010** | PROGRESS SCHEDULE (CRITICAL PATH) | LS | 2 | 1 | 1.00 | $10,000.00 | $10,000.00 |
| | | LS | 3 | 2 | 2.00 | $1,823.00 | $3,646.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$4,548.67** | **$13,646.00** |
| | **Item Code 070010 Total No. of Proj.** | | | **3** | | **Total Amount** | **$13,646.00** |
| **070012** | PROGRESS SCHEDULE (CRITICAL PATH METHOD) | LS | 1 | 9 | 9.00 | $5,313.33 | $47,820.00 |
| | | LS | 2 | 4 | 4.00 | $8,182.50 | $32,730.00 |
| | | LS | 3 | 14 | 14.00 | $3,670.00 | $51,380.00 |
| | | LS | 4 | 19 | 19.00 | $3,414.79 | $64,881.00 |
| | | LS | 5 | 8 | 8.00 | $7,593.75 | $60,750.00 |
| | | LS | 6 | 9 | 9.00 | $4,931.11 | $44,380.00 |
| | | LS | 7 | 18 | 18.00 | $4,579.17 | $82,425.00 |
| | | LS | 8 | 6 | 6.00 | $20,633.33 | $123,800.00 |
| | | LS | 9 | 3 | 3.00 | $3,833.33 | $11,500.00 |
| | | LS | 10 | 5 | 5.00 | $8,850.00 | $44,250.00 |
| | | LS | 11 | 11 | 11.00 | $16,579.55 | $182,375.00 |
| | | LS | 12 | 3 | 3.00 | $3,200.00 | $9,600.00 |
| | **Unit Sub Total** | **LS** | | **109** | **109.00** | **$6,934.78** | **$755,891.00** |
| | **Item Code 070012 Total No. of Proj.** | | | **109** | | **Total Amount** | **$755,891.00** |
| **070018** | TIME-RELATED OVERHEAD | LS | 1 | 2 | 2.00 | $160,150.00 | $320,300.00 |
| | | LS | 3 | 4 | 4.00 | $949,375.00 | $3,797,500.00 |
| | | LS | 4 | 9 | 9.00 | $511,000.00 | $4,599,000.00 |
| | | LS | 6 | 2 | 2.00 | $200,500.00 | $401,000.00 |
| | | LS | 8 | 1 | 1.00 | $2,700,000.00 | $2,700,000.00 |
| | | LS | 11 | 1 | 1.00 | $443,000.00 | $443,000.00 |
| | **Unit Sub Total** | **LS** | | **19** | **19.00** | **$645,305.26** | **$12,260,800.00** |
| **070018** | TIME-RELATED OVERHEAD | WDAY | 1 | 7 | 2,865.00 | $1,448.60 | $4,150,250.00 |
| | | WDAY | 2 | 6 | 2,050.00 | $1,763.07 | $3,614,300.00 |
| | | WDAY | 3 | 10 | 2,955.00 | $5,899.53 | $17,433,100.00 |
| | | WDAY | 4 | 6 | 2,100.00 | $692.74 | $1,454,750.00 |
| | | WDAY | 5 | 6 | 1,905.00 | $1,373.44 | $2,616,400.00 |
| | | WDAY | 6 | 6 | 925.00 | $1,982.78 | $1,834,075.00 |
| | | WDAY | 7 | 17 | 5,950.00 | $2,433.54 | $14,479,575.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **070018** | TIME-RELATED OVERHEAD | WDAY | 8 | 6 | 1,635.00 | $2,104.57 | $3,440,970.00 |
| | | WDAY | 9 | 3 | 700.00 | $1,934.29 | $1,354,000.00 |
| | | WDAY | 10 | 5 | 2,020.00 | $1,537.25 | $3,105,250.00 |
| | | WDAY | 11 | 9 | 5,979.00 | $2,801.79 | $16,751,875.00 |
| | | WDAY | 12 | 3 | 820.00 | $447.62 | $367,050.00 |
| | **Unit Sub Total** | **WDAY** | | **84** | **29,904.00** | **$2,360.94** | **$70,601,595.00** |
| | **Item Code 070018 Total No. of Proj.** | | | **103** | | **Total Amount** | **$82,862,395.00** |
| **071301** | TEMPORARY FENCE | M | 1 | 1 | 190.00 | $25.00 | $4,750.00 |
| | | M | 3 | 1 | 26,600.00 | $10.00 | $266,000.00 |
| | | M | 4 | 1 | 86.00 | $46.00 | $3,956.00 |
| | | M | 5 | 1 | 13.00 | $37.50 | $487.50 |
| | | M | 8 | 1 | 290.00 | $24.00 | $6,960.00 |
| | | M | 11 | 1 | 2,600.00 | $32.00 | $83,200.00 |
| | **Unit Sub Total** | **M** | | **6** | **29,779.00** | **$12.27** | **$365,353.50** |
| | **Item Code 071301 Total No. of Proj.** | | | **6** | | **Total Amount** | **$365,353.50** |
| **071302** | TEMPORARY FENCE (TYPE BW) | M | 1 | 1 | 190.00 | $21.00 | $3,990.00 |
| | | M | 9 | 1 | 9,660.00 | $10.00 | $96,600.00 |
| | **Unit Sub Total** | **M** | | **2** | **9,850.00** | **$10.21** | **$100,590.00** |
| | **Item Code 071302 Total No. of Proj.** | | | **2** | | **Total Amount** | **$100,590.00** |
| **071303** | TEMPORARY FENCE (TYPE WM) | M | 3 | 1 | 400.00 | $10.00 | $4,000.00 |
| | | M | 4 | 1 | 750.00 | $15.00 | $11,250.00 |
| | **Unit Sub Total** | **M** | | **2** | **1,150.00** | **$13.26** | **$15,250.00** |
| | **Item Code 071303 Total No. of Proj.** | | | **2** | | **Total Amount** | **$15,250.00** |
| **071321** | TEMPORARY FENCE (TYPE CL-6) | LF | 2 | 2 | 930.00 | $6.08 | $5,655.00 |
| | | LF | 3 | 1 | 460.00 | $2.25 | $1,035.00 |
| | | LF | 7 | 2 | 2,600.00 | $7.85 | $20,410.00 |
| | **Unit Sub Total** | **LF** | | **5** | **3,990.00** | **$6.79** | **$27,100.00** |
| | **Item Code 071321 Total No. of Proj.** | | | **5** | | **Total Amount** | **$27,100.00** |
| **071322** | TEMPORARY FENCE (TYPE CL-1.8) | M | 1 | 1 | 190.00 | $35.00 | $6,650.00 |
| | | M | 3 | 3 | 2,600.00 | $30.42 | $79,100.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **071322** | TEMPORARY FENCE (TYPE CL-1.8) | M | 4 | 1 | 124.00 | $8.00 | $992.00 |
| | | M | 7 | 6 | 5,224.00 | $35.72 | $186,600.00 |
| | | M | 10 | 1 | 250.00 | $10.00 | $2,500.00 |
| | | M | 11 | 4 | 1,920.00 | $39.37 | $75,596.50 |
| | | M | 12 | 1 | 110.00 | $50.00 | $5,500.00 |
| | **Unit Sub Total** | **M** | | **17** | **10,418.00** | **$34.26** | **$356,938.50** |
| | **Item Code 071322 Total No. of Proj.** | | | **17** | | **Total Amount** | **$356,938.50** |
| **071325** | TEMPORARY FENCE (TYPE ESA) | LF | 1 | 4 | 2,890.00 | $4.86 | $14,050.00 |
| | | LF | 2 | 6 | 3,150.00 | $2.78 | $8,770.00 |
| | | LF | 3 | 14 | 28,806.00 | $3.90 | $112,310.00 |
| | | LF | 4 | 1 | 9,940.00 | $1.75 | $17,395.00 |
| | | LF | 5 | 3 | 3,040.00 | $1.94 | $5,910.00 |
| | | LF | 6 | 8 | 9,360.00 | $3.97 | $37,130.00 |
| | | LF | 7 | 3 | 3,510.00 | $3.31 | $11,634.00 |
| | | LF | 8 | 1 | 2,150.00 | $8.00 | $17,200.00 |
| | | LF | 9 | 1 | 130.00 | $5.00 | $650.00 |
| | | LF | 10 | 1 | 2,730.00 | $2.00 | $5,460.00 |
| | | LF | 11 | 5 | 10,200.00 | $3.02 | $30,802.00 |
| | **Unit Sub Total** | **LF** | | **47** | **75,906.00** | **$3.44** | **$261,311.00** |
| **071325** | TEMPORARY FENCE (TYPE ESA) | M | 1 | 6 | 5,655.00 | $7.95 | $44,963.50 |
| | | M | 2 | 5 | 2,220.00 | $9.91 | $21,990.00 |
| | | M | 3 | 7 | 21,390.00 | $7.46 | $159,583.00 |
| | | M | 4 | 15 | 38,368.00 | $6.67 | $255,987.50 |
| | | M | 5 | 13 | 7,473.00 | $10.59 | $79,133.50 |
| | | M | 6 | 2 | 1,380.00 | $12.10 | $16,700.00 |
| | | M | 7 | 3 | 606.00 | $18.41 | $11,159.00 |
| | | M | 8 | 3 | 602.00 | $15.58 | $9,378.00 |
| | | M | 9 | 5 | 13,200.00 | $7.15 | $94,355.00 |
| | | M | 10 | 3 | 1,390.00 | $8.36 | $11,625.00 |
| | | M | 11 | 9 | 10,727.00 | $13.64 | $146,313.00 |
| | | M | 12 | 1 | 1,500.00 | $7.00 | $10,500.00 |
| | **Unit Sub Total** | **M** | | **72** | **104,511.00** | **$8.24** | **$861,687.50** |
| | **Item Code 071325 Total No. of Proj.** | | | **119** | | **Total Amount** | **$1,122,998.50** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **072006** | TEMPORARY SUPPORT | LS | 4 | 1 | 1.00 | $40,000.00 | $40,000.00 |
| | | LS | 11 | 1 | 1.00 | $50,000.00 | $50,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$45,000.00** | **$90,000.00** |
| | **Item Code 072006 Total No. of Proj.** | | | **2** | | **Total Amount** | **$90,000.00** |
| **073000** | TEMPORARY CULVERT | M | 2 | 1 | 18.00 | $575.00 | $10,350.00 |
| | | M | 7 | 1 | 220.00 | $500.00 | $110,000.00 |
| | **Unit Sub Total** | **M** | | **2** | **238.00** | **$505.67** | **$120,350.00** |
| | **Item Code 073000 Total No. of Proj.** | | | **2** | | **Total Amount** | **$120,350.00** |
| **073026** | 300 MM TEMPORARY CULVERT | M | 3 | 1 | 48.00 | $200.00 | $9,600.00 |
| | **Unit Sub Total** | **M** | | **1** | **48.00** | **$200.00** | **$9,600.00** |
| | **Item Code 073026 Total No. of Proj.** | | | **1** | | **Total Amount** | **$9,600.00** |
| **073028** | 450 MM TEMPORARY CULVERT | M | 1 | 1 | 5.00 | $200.00 | $1,000.00 |
| | | M | 3 | 1 | 87.00 | $300.00 | $26,100.00 |
| | | M | 6 | 1 | 51.00 | $140.00 | $7,140.00 |
| | **Unit Sub Total** | **M** | | **3** | **143.00** | **$239.44** | **$34,240.00** |
| | **Item Code 073028 Total No. of Proj.** | | | **3** | | **Total Amount** | **$34,240.00** |
| **073029** | 600 MM TEMPORARY CULVERT | M | 1 | 1 | 52.00 | $125.00 | $6,500.00 |
| | | M | 6 | 1 | 36.00 | $260.00 | $9,360.00 |
| | **Unit Sub Total** | **M** | | **2** | **88.00** | **$180.23** | **$15,860.00** |
| | **Item Code 073029 Total No. of Proj.** | | | **2** | | **Total Amount** | **$15,860.00** |
| **073030** | 750 MM TEMPORARY CULVERT | M | 6 | 1 | 53.00 | $120.00 | $6,360.00 |
| | **Unit Sub Total** | **M** | | **1** | **53.00** | **$120.00** | **$6,360.00** |
| | **Item Code 073030 Total No. of Proj.** | | | **1** | | **Total Amount** | **$6,360.00** |
| **074015** | TEMPORARY ACTIVE TREATMENT SYSTEM | LS | 4 | 1 | 1.00 | $22,000.00 | $22,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$22,000.00** | **$22,000.00** |
| | **Item Code 074015 Total No. of Proj.** | | | **1** | | **Total Amount** | **$22,000.00** |
| **074016** | CONSTRUCTION SITE MANAGEMENT | LS | 1 | 35 | 35.00 | $6,151.57 | $215,305.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **074016** | CONSTRUCTION SITE MANAGEMENT | LS | 2 | 40 | 40.00 | $6,123.47 | $244,938.66 |
| | | LS | 3 | 90 | 90.00 | $14,547.96 | $1,309,316.60 |
| | | LS | 4 | 79 | 79.00 | $5,887.21 | $465,089.28 |
| | | LS | 5 | 53 | 53.00 | $14,698.27 | $779,008.14 |
| | | LS | 6 | 50 | 50.00 | $5,794.40 | $289,720.00 |
| | | LS | 7 | 82 | 82.00 | $12,007.69 | $984,630.18 |
| | | LS | 8 | 59 | 59.00 | $34,007.48 | $2,006,441.08 |
| | | LS | 9 | 16 | 16.00 | $14,232.71 | $227,723.41 |
| | | LS | 10 | 44 | 44.00 | $3,377.73 | $148,620.00 |
| | | LS | 11 | 51 | 51.00 | $26,307.07 | $1,341,660.44 |
| | | LS | 12 | 36 | 36.00 | $7,048.81 | $253,756.99 |
| | **Unit Sub Total** | **LS** | | **635** | **635.00** | **$13,017.65** | **$8,266,209.78** |
| | **Item Code 074016 Total No. of Proj.** | | | **635** | | **Total Amount** | **$8,266,209.78** |
| **074017** | PREPARE WATER POLLUTION CONTROL PROGRAM | LS | 1 | 18 | 18.00 | $882.50 | $15,885.00 |
| | | LS | 2 | 29 | 29.00 | $2,320.67 | $67,299.50 |
| | | LS | 3 | 73 | 73.00 | $1,685.92 | $123,072.00 |
| | | LS | 4 | 56 | 56.00 | $1,582.86 | $88,640.02 |
| | | LS | 5 | 31 | 31.00 | $1,326.90 | $41,134.00 |
| | | LS | 6 | 35 | 35.00 | $1,188.57 | $41,600.00 |
| | | LS | 7 | 61 | 61.00 | $1,148.86 | $70,080.53 |
| | | LS | 8 | 41 | 41.00 | $1,077.37 | $44,172.33 |
| | | LS | 9 | 12 | 12.00 | $1,608.33 | $19,300.00 |
| | | LS | 10 | 37 | 37.00 | $1,135.00 | $41,995.00 |
| | | LS | 11 | 38 | 38.00 | $1,345.06 | $51,112.09 |
| | | LS | 12 | 31 | 31.00 | $1,443.04 | $44,734.18 |
| | **Unit Sub Total** | **LS** | | **462** | **462.00** | **$1,404.82** | **$649,024.65** |
| | **Item Code 074017 Total No. of Proj.** | | | **462** | | **Total Amount** | **$649,024.65** |
| **074018** | HEALTH AND SAFETY PLAN | LS | 1 | 1 | 1.00 | $2,500.00 | $2,500.00 |
| | | LS | 3 | 2 | 2.00 | $1,400.00 | $2,800.00 |
| | | LS | 4 | 3 | 3.00 | $2,141.67 | $6,425.00 |
| | | LS | 5 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | | LS | 7 | 2 | 2.00 | $4,019.00 | $8,038.00 |
| | | LS | 11 | 2 | 2.00 | $3,950.00 | $7,900.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **074018** | HEALTH AND SAFETY PLAN | | LS | 12 | 1 | 1.00 | $6,000.00 | $6,000.00 |
| | | **Unit Sub Total** | **LS** | | **12** | **12.00** | **$2,971.92** | **$35,663.00** |
| | **Item Code 074018** | **Total No. of Proj.** | | | **12** | | **Total Amount** | **$35,663.00** |
| **074019** | PREPARE STORM WATER POLLUTION PREVENTION PLAN | | LS | 1 | 18 | 18.00 | $2,676.39 | $48,175.00 |
| | | | LS | 2 | 11 | 11.00 | $3,949.18 | $43,441.03 |
| | | | LS | 3 | 17 | 17.00 | $3,652.63 | $62,094.73 |
| | | | LS | 4 | 23 | 23.00 | $2,580.43 | $59,350.00 |
| | | | LS | 5 | 22 | 22.00 | $2,503.20 | $55,070.36 |
| | | | LS | 6 | 15 | 15.00 | $1,985.60 | $29,784.00 |
| | | | LS | 7 | 22 | 22.00 | $2,898.86 | $63,775.00 |
| | | | LS | 8 | 18 | 18.00 | $3,092.30 | $55,661.46 |
| | | | LS | 9 | 4 | 4.00 | $5,312.50 | $21,250.00 |
| | | | LS | 10 | 7 | 7.00 | $2,452.86 | $17,170.00 |
| | | | LS | 11 | 13 | 13.00 | $3,500.07 | $45,500.93 |
| | | | LS | 12 | 5 | 5.00 | $2,431.76 | $12,158.81 |
| | | **Unit Sub Total** | **LS** | | **175** | **175.00** | **$2,933.89** | **$513,431.32** |
| | **Item Code 074019** | **Total No. of Proj.** | | | **175** | | **Total Amount** | **$513,431.32** |
| **074020** | WATER POLLUTION CONTROL | | LS | 1 | 1 | 1.00 | $10,000.00 | $10,000.00 |
| | | | LS | 4 | 2 | 2.00 | $5,476.00 | $10,952.00 |
| | | | LS | 7 | 1 | 1.00 | $85,000.00 | $85,000.00 |
| | | **Unit Sub Total** | **LS** | | **4** | **4.00** | **$26,488.00** | **$105,952.00** |
| | **Item Code 074020** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$105,952.00** |
| **074023** | TEMPORARY EROSION CONTROL | | HA | 10 | 2 | 8.00 | $1,972.00 | $15,776.00 |
| | | **Unit Sub Total** | **HA** | | **2** | **8.00** | **$1,972.00** | **$15,776.00** |
| **074023** | TEMPORARY EROSION CONTROL | | M2 | 1 | 3 | 29,970.00 | $0.64 | $19,205.00 |
| | | | M2 | 11 | 4 | 2,147,390.00 | $0.17 | $359,417.00 |
| | | | M2 | 12 | 1 | 4,800.00 | $0.55 | $2,640.00 |
| | | **Unit Sub Total** | **M2** | | **8** | **2,182,160.00** | **$0.17** | **$381,262.00** |
| **074023** | TEMPORARY EROSION CONTROL | | SQYD | 11 | 1 | 96,300.00 | $0.65 | $62,595.00 |
| | | **Unit Sub Total** | **SQYD** | | **1** | **96,300.00** | **$0.65** | **$62,595.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | **Item Code 074023** | **Total No. of Proj.** | | | **11** | | **Total Amount** | **$459,633.00** |
| **074026** | TEMPORARY MULCH | | CY | 2 | 3 | 104.00 | $208.98 | $21,734.23 |
| | | | CY | 4 | 1 | 38.00 | $125.00 | $4,750.00 |
| | | **Unit Sub Total** | **CY** | | **4** | **142.00** | **$186.51** | **$26,484.23** |
| **074026** | TEMPORARY MULCH | | M3 | 2 | 1 | 21.00 | $100.00 | $2,100.00 |
| | | | M3 | 5 | 1 | 69.00 | $87.00 | $6,003.00 |
| | | **Unit Sub Total** | **M3** | | **2** | **90.00** | **$90.03** | **$8,103.00** |
| | **Item Code 074026** | **Total No. of Proj.** | | | **6** | | **Total Amount** | **$34,587.23** |
| **074027** | TEMPORARY EROSION CONTROL BLANKET | | M2 | 1 | 1 | 500.00 | $4.75 | $2,375.00 |
| | | | M2 | 3 | 2 | 34,480.00 | $2.11 | $72,790.00 |
| | | | M2 | 7 | 1 | 188,000.00 | $2.00 | $376,000.00 |
| | | | M2 | 10 | 1 | 410.00 | $20.00 | $8,200.00 |
| | | **Unit Sub Total** | **M2** | | **5** | **223,390.00** | **$2.06** | **$459,365.00** |
| **074027** | TEMPORARY EROSION CONTROL BLANKET | | SQYD | 1 | 1 | 1,210.00 | $4.00 | $4,840.00 |
| | | | SQYD | 3 | 1 | 55.00 | $16.40 | $902.00 |
| | | **Unit Sub Total** | **SQYD** | | **2** | **1,265.00** | **$4.54** | **$5,742.00** |
| | **Item Code 074027** | **Total No. of Proj.** | | | **7** | | **Total Amount** | **$465,107.00** |
| **074028** | TEMPORARY FIBER ROLL | | LF | 1 | 8 | 11,330.00 | $3.30 | $37,400.00 |
| | | | LF | 2 | 14 | 20,560.00 | $3.78 | $77,751.00 |
| | | | LF | 3 | 22 | 165,780.00 | $3.21 | $532,906.60 |
| | | | LF | 4 | 1 | 1,160.00 | $3.65 | $4,234.00 |
| | | | LF | 5 | 4 | 5,540.00 | $4.76 | $26,392.00 |
| | | | LF | 6 | 8 | 17,300.00 | $3.32 | $57,423.00 |
| | | | LF | 7 | 5 | 3,755.00 | $3.14 | $11,785.00 |
| | | | LF | 8 | 3 | 2,900.00 | $4.67 | $13,550.00 |
| | | | LF | 9 | 5 | 19,930.00 | $4.35 | $86,709.00 |
| | | | LF | 10 | 1 | 6,500.00 | $2.10 | $13,650.00 |
| | | | LF | 11 | 5 | 41,324.00 | $1.53 | $63,148.00 |
| | | | LF | 12 | 3 | 15,540.00 | $2.14 | $33,300.00 |
| | | **Unit Sub Total** | **LF** | | **79** | **311,619.00** | **$3.08** | **$958,248.60** |
| **074028** | TEMPORARY FIBER ROLL | | M | 1 | 5 | 13,180.00 | $8.98 | $118,404.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **074028** | TEMPORARY FIBER ROLL | M | 2 | 8 | 6,746.00 | $10.53 | $71,047.00 |
| | | M | 3 | 6 | 81,960.00 | $4.41 | $361,635.00 |
| | | M | 4 | 6 | 11,110.00 | $6.16 | $68,448.00 |
| | | M | 5 | 11 | 24,770.00 | $11.13 | $275,680.00 |
| | | M | 6 | 9 | 12,320.00 | $7.25 | $89,275.00 |
| | | M | 7 | 10 | 31,340.00 | $9.59 | $300,637.00 |
| | | M | 8 | 4 | 1,970.00 | $11.32 | $22,300.00 |
| | | M | 9 | 1 | 1,320.00 | $15.00 | $19,800.00 |
| | | M | 10 | 10 | 7,469.00 | $6.30 | $47,052.00 |
| | | M | 11 | 12 | 257,050.00 | $7.35 | $1,889,795.00 |
| | | M | 12 | 2 | 2,120.00 | $7.33 | $15,545.00 |
| | **Unit Sub Total** | **M** | | **84** | **451,355.00** | **$7.27** | **$3,279,618.00** |
| | **Item Code 074028 Total No. of Proj.** | | | **163** | | **Total Amount** | **$4,237,866.60** |
| **074029** | TEMPORARY SILT FENCE | LF | 1 | 2 | 820.00 | $3.81 | $3,125.00 |
| | | LF | 2 | 3 | 631.00 | $5.36 | $3,383.00 |
| | | LF | 3 | 10 | 18,850.00 | $4.81 | $90,715.70 |
| | | LF | 4 | 3 | 10,530.00 | $1.51 | $15,925.20 |
| | | LF | 5 | 1 | 200.00 | $5.00 | $1,000.00 |
| | | LF | 7 | 5 | 4,790.00 | $3.31 | $15,865.00 |
| | | LF | 8 | 3 | 7,800.00 | $2.98 | $23,232.30 |
| | | LF | 9 | 1 | 270.00 | $2.00 | $540.00 |
| | | LF | 12 | 2 | 500.00 | $4.92 | $2,458.80 |
| | **Unit Sub Total** | **LF** | | **30** | **44,391.00** | **$3.52** | **$156,245.00** |
| **074029** | TEMPORARY SILT FENCE | M | 1 | 5 | 8,080.00 | $8.47 | $68,436.00 |
| | | M | 2 | 5 | 5,400.00 | $13.69 | $73,900.00 |
| | | M | 3 | 6 | 10,290.00 | $10.09 | $103,860.00 |
| | | M | 4 | 17 | 57,829.00 | $6.57 | $379,901.62 |
| | | M | 5 | 9 | 18,950.00 | $6.93 | $131,400.00 |
| | | M | 6 | 1 | 500.00 | $2.00 | $1,000.00 |
| | | M | 7 | 15 | 11,246.00 | $8.97 | $100,839.00 |
| | | M | 8 | 2 | 690.00 | $4.38 | $3,022.50 |
| | | M | 9 | 4 | 2,090.00 | $12.53 | $26,191.00 |
| | | M | 10 | 3 | 12,000.00 | $4.58 | $54,954.00 |
| | | M | 11 | 3 | 5,580.00 | $9.84 | $54,920.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M** | | **70** | **132,655.00** | **$7.53** | **$998,424.12** |
| | **Item Code 074029** | **Total No. of Proj.** | | | **100** | | **Total Amount** | **$1,154,669.12** |
| **074030** | TEMPORARY STRAW BALE | | LF | 3 | 1 | 15,600.00 | $0.25 | $3,900.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **15,600.00** | **$0.25** | **$3,900.00** |
| | **Item Code 074030** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,900.00** |
| **074031** | TEMPORARY GRAVEL BAG BERM | | LF | 1 | 3 | 5,135.00 | $4.83 | $24,825.00 |
| | | | LF | 2 | 3 | 466.00 | $5.63 | $2,622.00 |
| | | | LF | 3 | 6 | 440.00 | $24.16 | $10,630.00 |
| | | | LF | 4 | 1 | 200.00 | $16.00 | $3,200.00 |
| | | | LF | 5 | 1 | 300.00 | $6.27 | $1,881.00 |
| | | | LF | 6 | 2 | 300.00 | $22.00 | $6,600.00 |
| | | | LF | 7 | 5 | 4,410.00 | $19.54 | $86,187.50 |
| | | | LF | 8 | 5 | 3,470.00 | $7.39 | $25,640.00 |
| | | | LF | 9 | 1 | 24.00 | $28.00 | $672.00 |
| | | | LF | 10 | 1 | 100.00 | $15.00 | $1,500.00 |
| | | | LF | 11 | 1 | 240.00 | $2.75 | $660.00 |
| | | | LF | 12 | 4 | 5,520.00 | $4.23 | $23,354.00 |
| | | **Unit Sub Total** | **LF** | | **33** | **20,605.00** | **$9.11** | **$187,771.50** |
| **074031** | TEMPORARY GRAVEL BAG BERM | | M | 1 | 4 | 482.00 | $30.21 | $14,560.00 |
| | | | M | 2 | 2 | 1,460.00 | $23.67 | $34,560.00 |
| | | | M | 3 | 2 | 126.00 | $57.14 | $7,200.00 |
| | | | M | 4 | 3 | 905.00 | $27.04 | $24,475.00 |
| | | | M | 5 | 6 | 418.00 | $47.97 | $20,050.00 |
| | | | M | 7 | 13 | 10,155.00 | $20.00 | $203,135.00 |
| | | | M | 8 | 4 | 208.00 | $39.34 | $8,182.00 |
| | | | M | 12 | 3 | 497.00 | $8.16 | $4,054.00 |
| | | **Unit Sub Total** | **M** | | **37** | **14,251.00** | **$22.19** | **$316,216.00** |
| | **Item Code 074031** | **Total No. of Proj.** | | | **70** | | **Total Amount** | **$503,987.50** |
| **074032** | TEMPORARY CONCRETE WASHOUT FACILITY | | EA | 1 | 14 | 29.00 | $1,785.52 | $51,780.00 |
| | | | EA | 2 | 17 | 54.00 | $1,413.07 | $76,305.72 |
| | | | EA | 3 | 13 | 81.00 | $2,432.63 | $197,043.34 |
| | | | EA | 4 | 5 | 10.00 | $1,780.00 | $17,800.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **074032** | TEMPORARY CONCRETE WASHOUT FACILITY | EA | 5 | 6 | 25.00 | $2,186.00 | $54,650.00 |
| | | EA | 6 | 6 | 20.00 | $1,992.50 | $39,850.00 |
| | | EA | 7 | 14 | 43.00 | $1,584.65 | $68,140.00 |
| | | EA | 8 | 4 | 25.00 | $3,692.00 | $92,300.00 |
| | | EA | 9 | 3 | 54.00 | $542.59 | $29,300.00 |
| | | EA | 10 | 5 | 28.00 | $1,213.21 | $33,970.00 |
| | | EA | 11 | 13 | 210.00 | $2,226.90 | $467,650.00 |
| | | EA | 12 | 3 | 6.00 | $960.00 | $5,760.00 |
| | **Unit Sub Total** | **EA** | | **103** | **585.00** | **$1,939.40** | **$1,134,549.06** |
| **074032** | TEMPORARY CONCRETE WASHOUT FACILITY | LS | 3 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | | LS | 10 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$1,500.00** | **$3,000.00** |
| | **Item Code 074032 Total No. of Proj.** | | | **105** | | **Total Amount** | **$1,137,549.06** |
| **074033** | TEMPORARY CONSTRUCTION ENTRANCE | EA | 1 | 8 | 29.00 | $1,734.48 | $50,300.00 |
| | | EA | 2 | 5 | 19.00 | $2,284.42 | $43,404.00 |
| | | EA | 3 | 17 | 176.00 | $1,749.30 | $307,876.00 |
| | | EA | 4 | 11 | 94.00 | $2,164.89 | $203,500.00 |
| | | EA | 5 | 14 | 42.00 | $2,299.77 | $96,590.20 |
| | | EA | 6 | 8 | 28.00 | $2,677.14 | $74,960.00 |
| | | EA | 7 | 16 | 112.00 | $3,208.75 | $359,380.00 |
| | | EA | 8 | 12 | 26.00 | $3,273.37 | $85,107.70 |
| | | EA | 9 | 1 | 5.00 | $8,000.00 | $40,000.00 |
| | | EA | 10 | 5 | 27.00 | $1,633.33 | $44,100.00 |
| | | EA | 11 | 24 | 216.00 | $4,578.11 | $988,872.48 |
| | | EA | 12 | 5 | 12.00 | $2,783.33 | $33,400.00 |
| | **Unit Sub Total** | **EA** | | **126** | **786.00** | **$2,961.18** | **$2,327,490.38** |
| **074033** | TEMPORARY CONSTRUCTION ENTRANCE | LS | 3 | 1 | 1.00 | $910.00 | $910.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$910.00** | **$910.00** |
| | **Item Code 074033 Total No. of Proj.** | | | **127** | | **Total Amount** | **$2,328,400.38** |
| **074034** | TEMPORARY COVER | LS | 12 | 1 | 1.00 | $1,200.00 | $1,200.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$1,200.00** | **$1,200.00** |
| **074034** | TEMPORARY COVER | M2 | 1 | 2 | 7,110.00 | $3.26 | $23,155.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **074034** | TEMPORARY COVER | | M2 | 2 | 2 | 18,900.00 | $1.85 | $35,028.00 |
| | | | M2 | 3 | 6 | 271,510.00 | $0.29 | $77,510.00 |
| | | | M2 | 4 | 12 | 31,000.00 | $2.93 | $90,789.00 |
| | | | M2 | 5 | 8 | 1,970.00 | $6.94 | $13,675.00 |
| | | | M2 | 6 | 3 | 3,190.00 | $2.18 | $6,957.00 |
| | | | M2 | 7 | 6 | 9,360.00 | $5.93 | $55,500.00 |
| | | | M2 | 8 | 3 | 680.00 | $9.98 | $6,789.00 |
| | | | M2 | 10 | 5 | 7,550.00 | $2.19 | $16,530.00 |
| | | | M2 | 11 | 1 | 1,700.00 | $2.65 | $4,505.00 |
| | | | M2 | 12 | 2 | 5,860.00 | $2.44 | $14,310.00 |
| | | **Unit Sub Total** | **M2** | | **50** | **358,830.00** | **$0.96** | **$344,748.00** |
| **074034** | TEMPORARY COVER | | SQYD | 1 | 1 | 780.00 | $4.00 | $3,120.00 |
| | | | SQYD | 3 | 7 | 69,360.00 | $0.80 | $55,684.00 |
| | | | SQYD | 4 | 1 | 780.00 | $1.00 | $780.00 |
| | | | SQYD | 5 | 1 | 1,080.00 | $1.00 | $1,080.00 |
| | | | SQYD | 7 | 1 | 6,800.00 | $1.65 | $11,220.00 |
| | | | SQYD | 8 | 9 | 4,759.00 | $4.16 | $19,815.54 |
| | | | SQYD | 11 | 1 | 460.00 | $35.00 | $16,100.00 |
| | | | SQYD | 12 | 1 | 1,280.00 | $3.00 | $3,840.00 |
| | | **Unit Sub Total** | **SQYD** | | **22** | **85,299.00** | **$1.31** | **$111,639.54** |
| | **Item Code 074034** | **Total No. of Proj.** | | | **73** | | **Total Amount** | **$457,587.54** |
| **074035** | TEMPORARY CHECK DAM | | EA | 5 | 1 | 7.00 | $260.00 | $1,820.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **7.00** | **$260.00** | **$1,820.00** |
| **074035** | TEMPORARY CHECK DAM | | LF | 1 | 3 | 100.00 | $26.50 | $2,650.00 |
| | | | LF | 2 | 7 | 2,234.00 | $8.04 | $17,968.00 |
| | | | LF | 3 | 7 | 8,236.00 | $8.77 | $72,241.00 |
| | | | LF | 4 | 5 | 590.00 | $38.36 | $22,630.00 |
| | | | LF | 5 | 3 | 330.00 | $17.25 | $5,693.40 |
| | | | LF | 6 | 1 | 150.00 | $4.00 | $600.00 |
| | | | LF | 7 | 2 | 40.00 | $8.75 | $350.00 |
| | | | LF | 8 | 2 | 26,650.00 | $0.60 | $15,950.00 |
| | | | LF | 11 | 2 | 2,020.00 | $2.30 | $4,640.00 |
| | | | LF | 12 | 1 | 900.00 | $5.00 | $4,500.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **LF** | | **33** | **41,250.00** | **$3.57** | **$147,222.40** |
| **074035** | TEMPORARY CHECK DAM | | M | 1 | 2 | 118.00 | $19.24 | $2,270.00 |
| | | | M | 2 | 3 | 332.00 | $74.43 | $24,710.43 |
| | | | M | 3 | 2 | 57.00 | $138.16 | $7,875.00 |
| | | | M | 4 | 10 | 1,169.00 | $18.19 | $21,258.36 |
| | | | M | 5 | 13 | 4,504.00 | $17.33 | $78,042.00 |
| | | | M | 6 | 1 | 32.00 | $18.50 | $592.00 |
| | | | M | 7 | 1 | 6.00 | $50.00 | $300.00 |
| | | | M | 8 | 2 | 680.00 | $19.29 | $13,115.00 |
| | | | M | 10 | 2 | 170.00 | $15.59 | $2,650.00 |
| | | | M | 11 | 10 | 5,851.00 | $22.91 | $134,075.00 |
| | | **Unit Sub Total** | **M** | | **46** | **12,919.00** | **$22.05** | **$284,887.79** |
| | **Item Code 074035** | **Total No. of Proj.** | | | **80** | | **Total Amount** | **$433,930.19** |
| **074036** | TEMPORARY STRAW BALE BARRIER | | LF | 1 | 1 | 1,450.00 | $10.00 | $14,500.00 |
| | | | LF | 2 | 1 | 80.00 | $25.00 | $2,000.00 |
| | | | LF | 3 | 1 | 220.00 | $10.00 | $2,200.00 |
| | | **Unit Sub Total** | **LF** | | **3** | **1,750.00** | **$10.69** | **$18,700.00** |
| **074036** | TEMPORARY STRAW BALE BARRIER | | M | 2 | 1 | 200.00 | $85.00 | $17,000.00 |
| | | | M | 3 | 1 | 4,550.00 | $10.00 | $45,500.00 |
| | | | M | 7 | 2 | 530.00 | $32.17 | $17,050.00 |
| | | | M | 9 | 1 | 50.00 | $10.00 | $500.00 |
| | | **Unit Sub Total** | **M** | | **5** | **5,330.00** | **$15.02** | **$80,050.00** |
| | **Item Code 074036** | **Total No. of Proj.** | | | **8** | | **Total Amount** | **$98,750.00** |
| **074037** | MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL) | | EA | 1 | 3 | 13.00 | $546.15 | $7,100.00 |
| | | | EA | 2 | 1 | 14.00 | $1,000.00 | $14,000.00 |
| | | | EA | 3 | 6 | 56.00 | $397.59 | $22,265.00 |
| | | | EA | 4 | 1 | 6.00 | $750.00 | $4,500.00 |
| | | | EA | 5 | 1 | 9.00 | $550.00 | $4,950.00 |
| | | | EA | 7 | 3 | 19.00 | $1,848.95 | $35,130.00 |
| | | | EA | 8 | 1 | 3.00 | $1,000.00 | $3,000.00 |
| | | | EA | 10 | 2 | 5.00 | $506.00 | $2,530.00 |
| | | | EA | 11 | 11 | 62.00 | $519.35 | $32,200.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| 074037 | MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL) | EA | 12 | 1 | 1.00 | $650.00 | $650.00 |
| | **Unit Sub Total** | **EA** | | **30** | **188.00** | **$671.94** | **$126,325.00** |
| | **Item Code 074037 Total No. of Proj.** | | | **30** | | **Total Amount** | **$126,325.00** |
| 074038 | TEMPORARY DRAINAGE INLET PROTECTION | EA | 1 | 13 | 82.00 | $225.63 | $18,502.00 |
| | | EA | 2 | 6 | 156.00 | $254.17 | $39,650.00 |
| | | EA | 3 | 20 | 705.00 | $300.53 | $211,874.79 |
| | | EA | 4 | 57 | 1,585.00 | $212.70 | $337,122.26 |
| | | EA | 5 | 19 | 399.00 | $340.41 | $135,824.00 |
| | | EA | 6 | 16 | 158.00 | $305.34 | $48,243.00 |
| | | EA | 7 | 34 | 1,298.00 | $282.15 | $366,230.70 |
| | | EA | 8 | 23 | 973.00 | $215.56 | $209,744.00 |
| | | EA | 9 | 3 | 100.00 | $221.00 | $22,100.00 |
| | | EA | 10 | 10 | 177.00 | $244.51 | $43,279.00 |
| | | EA | 11 | 24 | 1,515.00 | $247.29 | $374,643.40 |
| | | EA | 12 | 31 | 788.00 | $167.69 | $132,139.22 |
| | **Unit Sub Total** | **EA** | | **256** | **7,936.00** | **$244.37** | **$1,939,352.37** |
| 074038 | TEMPORARY DRAINAGE INLET PROTECTION | LS | 6 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | | LS | 10 | 1 | 1.00 | $5,530.00 | $5,530.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$5,265.00** | **$10,530.00** |
| | **Item Code 074038 Total No. of Proj.** | | | **258** | | **Total Amount** | **$1,949,882.37** |
| 074039 | TEMPORARY HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX) | M2 | 3 | 1 | 11,500.00 | $2.00 | $23,000.00 |
| | **Unit Sub Total** | **M2** | | **1** | **11,500.00** | **$2.00** | **$23,000.00** |
| 074039 | TEMPORARY HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX) | SQYD | 3 | 1 | 44,000.00 | $1.00 | $44,000.00 |
| | **Unit Sub Total** | **SQYD** | | **1** | **44,000.00** | **$1.00** | **$44,000.00** |
| | **Item Code 074039 Total No. of Proj.** | | | **2** | | **Total Amount** | **$67,000.00** |
| 074040 | TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX) | M2 | 2 | 2 | 42,000.00 | $0.73 | $30,500.00 |
| | | M2 | 3 | 3 | 72,200.00 | $0.78 | $56,575.00 |
| | | M2 | 4 | 4 | 82,770.00 | $1.01 | $83,250.00 |
| | | M2 | 5 | 1 | 129,000.00 | $0.90 | $116,100.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **074040** | TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX) | M2 | 7 | 2 | 311,300.00 | $0.75 | $232,450.00 |
| | | M2 | 8 | 1 | 1,430.00 | $1.25 | $1,787.50 |
| | | M2 | 10 | 2 | 25,700.00 | $1.11 | $28,475.00 |
| | | M2 | 11 | 4 | 92,250.00 | $0.86 | $79,615.00 |
| | **Unit Sub Total** | **M2** | | **19** | **756,650.00** | **$0.83** | **$628,752.50** |
| **074040** | TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX) | SQYD | 3 | 2 | 11,720.00 | $1.22 | $14,336.00 |
| | | SQYD | 7 | 1 | 13,600.00 | $0.65 | $8,840.00 |
| | | SQYD | 8 | 1 | 19,400.00 | $1.00 | $19,400.00 |
| | | SQYD | 12 | 2 | 60,900.00 | $0.66 | $40,100.00 |
| | **Unit Sub Total** | **SQYD** | | **6** | **105,620.00** | **$0.78** | **$82,676.00** |
| | **Item Code 074040 Total No. of Proj.** | | | **25** | | **Total Amount** | **$711,428.50** |
| **074041** | STREET SWEEPING | LS | 1 | 15 | 15.00 | $22,526.67 | $337,900.00 |
| | | LS | 2 | 13 | 13.00 | $16,529.31 | $214,881.00 |
| | | LS | 3 | 44 | 44.00 | $33,426.22 | $1,470,753.54 |
| | | LS | 4 | 56 | 56.00 | $11,533.88 | $645,897.29 |
| | | LS | 5 | 29 | 29.00 | $19,976.58 | $579,320.75 |
| | | LS | 6 | 44 | 44.00 | $11,021.95 | $484,966.00 |
| | | LS | 7 | 74 | 74.00 | $18,989.05 | $1,405,189.86 |
| | | LS | 8 | 41 | 41.00 | $12,657.75 | $518,967.95 |
| | | LS | 9 | 6 | 6.00 | $63,881.34 | $383,288.04 |
| | | LS | 10 | 34 | 34.00 | $12,783.82 | $434,650.00 |
| | | LS | 11 | 31 | 31.00 | $43,743.48 | $1,356,047.97 |
| | | LS | 12 | 25 | 25.00 | $5,936.78 | $148,419.40 |
| | **Unit Sub Total** | **LS** | | **412** | **412.00** | **$19,369.62** | **$7,980,281.80** |
| | **Item Code 074041 Total No. of Proj.** | | | **412** | | **Total Amount** | **$7,980,281.80** |
| **074042** | TEMPORARY CONCRETE WASHOUT (PORTABLE) | EA | 3 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | | EA | 4 | 2 | 36.00 | $1,493.06 | $53,750.00 |
| | | EA | 7 | 1 | 32.00 | $300.00 | $9,600.00 |
| | | EA | 8 | 2 | 2.00 | $1,000.00 | $2,000.00 |
| | | EA | 10 | 1 | 1.00 | $3,200.00 | $3,200.00 |
| | | EA | 12 | 1 | 1.00 | $1,000.00 | $1,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **EA** | | **8** | **73.00** | **$980.14** | **$71,550.00** |
| **074042** | TEMPORARY CONCRETE WASHOUT (PORTABLE) | LS | 1 | 13 | 13.00 | $1,175.38 | $15,280.00 |
| | | LS | 2 | 10 | 10.00 | $1,915.00 | $19,150.00 |
| | | LS | 3 | 23 | 23.00 | $4,321.87 | $99,403.00 |
| | | LS | 4 | 27 | 27.00 | $3,551.82 | $95,899.12 |
| | | LS | 5 | 31 | 31.00 | $1,845.27 | $57,203.25 |
| | | LS | 6 | 22 | 22.00 | $2,421.59 | $53,275.00 |
| | | LS | 7 | 42 | 42.00 | $15,136.74 | $635,743.00 |
| | | LS | 8 | 21 | 21.00 | $2,080.35 | $43,687.30 |
| | | LS | 9 | 5 | 5.00 | $2,483.00 | $12,415.00 |
| | | LS | 10 | 19 | 19.00 | $1,215.79 | $23,100.00 |
| | | LS | 11 | 25 | 25.00 | $5,704.68 | $142,616.97 |
| | | LS | 12 | 26 | 26.00 | $1,236.16 | $32,140.11 |
| | **Unit Sub Total** | **LS** | | **264** | **264.00** | **$4,658.76** | **$1,229,912.75** |
| | **Item Code 074042 Total No. of Proj.** | | | **272** | | **Total Amount** | **$1,301,462.75** |
| **074043** | TEMPORARY CONCRETE WASHOUT BIN | EA | 4 | 6 | 218.00 | $841.40 | $183,425.00 |
| | **Unit Sub Total** | **EA** | | **6** | **218.00** | **$841.40** | **$183,425.00** |
| | **Item Code 074043 Total No. of Proj.** | | | **6** | | **Total Amount** | **$183,425.00** |
| **074051** | TEMPORARY HYDRAULIC MULCH | M2 | 1 | 1 | 11,000.00 | $0.33 | $3,630.00 |
| | | M2 | 11 | 6 | 372,200.00 | $0.41 | $151,805.00 |
| | **Unit Sub Total** | **M2** | | **7** | **383,200.00** | **$0.41** | **$155,435.00** |
| | **Item Code 074051 Total No. of Proj.** | | | **7** | | **Total Amount** | **$155,435.00** |
| **074055** | TEMPORARY SOIL BINDER | SQYD | 3 | 1 | 174,000.00 | $0.05 | $8,700.00 |
| | | SQYD | 7 | 1 | 1,200.00 | $1.50 | $1,800.00 |
| | **Unit Sub Total** | **SQYD** | | **2** | **175,200.00** | **$0.06** | **$10,500.00** |
| | **Item Code 074055 Total No. of Proj.** | | | **2** | | **Total Amount** | **$10,500.00** |
| **075021** | STEEL GRADE STAKE | EA | 1 | 1 | 370.00 | $10.00 | $3,700.00 |
| | **Unit Sub Total** | **EA** | | **1** | **370.00** | **$10.00** | **$3,700.00** |
| | **Item Code 075021 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,700.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **120090** | CONSTRUCTION AREA SIGNS | LS | 1 | 33 | 33.00 | $7,253.18 | $239,355.00 |
| | | LS | 2 | 32 | 32.00 | $9,542.66 | $305,365.00 |
| | | LS | 3 | 69 | 69.00 | $8,234.40 | $568,173.50 |
| | | LS | 4 | 77 | 77.00 | $8,051.70 | $619,980.98 |
| | | LS | 5 | 53 | 53.00 | $8,022.77 | $425,206.68 |
| | | LS | 6 | 48 | 48.00 | $8,178.49 | $392,567.50 |
| | | LS | 7 | 81 | 81.00 | $12,172.92 | $986,006.40 |
| | | LS | 8 | 56 | 56.00 | $11,474.52 | $642,572.84 |
| | | LS | 9 | 16 | 16.00 | $25,481.31 | $407,701.00 |
| | | LS | 10 | 43 | 43.00 | $4,275.29 | $183,837.51 |
| | | LS | 11 | 49 | 49.00 | $15,200.37 | $744,818.16 |
| | | LS | 12 | 35 | 35.00 | $7,994.16 | $279,795.47 |
| | **Unit Sub Total** | **LS** | | **592** | **592.00** | **$9,789.49** | **$5,795,380.04** |
| | **Item Code 120090 Total No. of Proj.** | | | **592** | | **Total Amount** | **$5,795,380.04** |
| **120100** | TRAFFIC CONTROL SYSTEM | LS | 1 | 36 | 36.00 | $77,335.31 | $2,784,071.00 |
| | | LS | 2 | 35 | 35.00 | $81,400.91 | $2,849,032.00 |
| | | LS | 3 | 84 | 84.00 | $115,323.99 | $9,687,214.80 |
| | | LS | 4 | 73 | 73.00 | $75,961.08 | $5,545,158.65 |
| | | LS | 5 | 53 | 53.00 | $74,101.49 | $3,927,378.85 |
| | | LS | 6 | 50 | 50.00 | $77,215.26 | $3,860,763.00 |
| | | LS | 7 | 79 | 79.00 | $160,545.89 | $12,683,125.09 |
| | | LS | 8 | 56 | 56.00 | $80,523.71 | $4,509,328.00 |
| | | LS | 9 | 16 | 16.00 | $86,993.35 | $1,391,893.55 |
| | | LS | 10 | 43 | 43.00 | $38,147.12 | $1,640,326.00 |
| | | LS | 11 | 48 | 48.00 | $144,967.35 | $6,958,432.81 |
| | | LS | 12 | 34 | 34.00 | $41,073.88 | $1,396,511.83 |
| | **Unit Sub Total** | **LS** | | **607** | **607.00** | **$94,288.69** | **$57,233,235.58** |
| | **Item Code 120100 Total No. of Proj.** | | | **607** | | **Total Amount** | **$57,233,235.58** |
| **120102** | TRAFFIC CONTROL SURVEILLANCE | LS | 2 | 1 | 1.00 | $40,000.00 | $40,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$40,000.00** | **$40,000.00** |
| | **Item Code 120102 Total No. of Proj.** | | | **1** | | **Total Amount** | **$40,000.00** |
| **120110** | FLASHING ARROW SIGN | EA | 1 | 1 | 2.00 | $3,500.00 | $7,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **120110** | FLASHING ARROW SIGN | | EA | 12 | 2 | 13.00 | $1,023.08 | $13,300.00 |
| | | **Unit Sub Total** | **EA** | | **3** | **15.00** | **$1,353.33** | **$20,300.00** |
| | **Item Code 120110** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$20,300.00** |
| **120116** | TYPE II BARRICADE | | EA | 1 | 3 | 233.00 | $24.94 | $5,810.00 |
| | | | EA | 2 | 1 | 1.00 | $30.00 | $30.00 |
| | | | EA | 5 | 3 | 10.00 | $125.20 | $1,252.00 |
| | | | EA | 6 | 1 | 72.00 | $51.00 | $3,672.00 |
| | | | EA | 7 | 3 | 32.00 | $48.28 | $1,545.00 |
| | | | EA | 8 | 2 | 206.00 | $54.42 | $11,210.00 |
| | | | EA | 10 | 1 | 7.00 | $35.00 | $245.00 |
| | | | EA | 11 | 1 | 36.00 | $32.00 | $1,152.00 |
| | | | EA | 12 | 1 | 22.00 | $40.00 | $880.00 |
| | | **Unit Sub Total** | **EA** | | **16** | **619.00** | **$41.67** | **$25,796.00** |
| | **Item Code 120116** | **Total No. of Proj.** | | | **16** | | **Total Amount** | **$25,796.00** |
| **120119** | TRAFFIC CONE | | EA | 7 | 1 | 19.00 | $50.00 | $950.00 |
| | | | EA | 12 | 1 | 280.00 | $5.00 | $1,400.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **299.00** | **$7.86** | **$2,350.00** |
| | **Item Code 120119** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,350.00** |
| **120120** | TYPE III BARRICADE | | EA | 1 | 5 | 192.00 | $66.38 | $12,745.00 |
| | | | EA | 2 | 1 | 11.00 | $125.00 | $1,375.00 |
| | | | EA | 3 | 9 | 618.00 | $67.29 | $41,585.00 |
| | | | EA | 4 | 2 | 41.00 | $285.37 | $11,700.00 |
| | | | EA | 5 | 4 | 134.00 | $74.33 | $9,960.00 |
| | | | EA | 6 | 4 | 68.00 | $92.06 | $6,260.00 |
| | | | EA | 7 | 8 | 438.00 | $92.26 | $40,412.00 |
| | | | EA | 8 | 9 | 200.00 | $82.38 | $16,475.00 |
| | | | EA | 9 | 3 | 428.00 | $98.42 | $42,122.00 |
| | | | EA | 10 | 4 | 326.00 | $60.78 | $19,815.20 |
| | | | EA | 11 | 7 | 385.00 | $131.82 | $50,750.00 |
| | | | EA | 12 | 8 | 116.00 | $89.27 | $10,355.00 |
| | | **Unit Sub Total** | **EA** | | **64** | **2,957.00** | **$89.13** | **$263,554.20** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | **Item Code 120120** | **Total No. of Proj.** | | | **64** | | **Total Amount** | **$263,554.20** |
| **120140** | BARRICADE (LEFT IN PLACE) | | EA | 11 | 2 | 55.00 | $120.00 | $6,600.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **55.00** | **$120.00** | **$6,600.00** |
| | **Item Code 120140** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$6,600.00** |
| **120149** | TEMPORARY PAVEMENT MARKING (PAINT) | | LF | 8 | 1 | 230.00 | $2.20 | $506.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **230.00** | **$2.20** | **$506.00** |
| **120149** | TEMPORARY PAVEMENT MARKING (PAINT) | | M2 | 1 | 4 | 623.10 | $38.18 | $23,788.00 |
| | | | M2 | 2 | 1 | 130.00 | $70.00 | $9,100.00 |
| | | | M2 | 3 | 4 | 698.00 | $12.54 | $8,754.00 |
| | | | M2 | 4 | 4 | 431.00 | $26.83 | $11,564.00 |
| | | | M2 | 5 | 1 | 14.00 | $125.00 | $1,750.00 |
| | | | M2 | 7 | 5 | 1,431.00 | $22.29 | $31,900.00 |
| | | | M2 | 8 | 1 | 30.00 | $35.00 | $1,050.00 |
| | | | M2 | 9 | 3 | 532.00 | $18.07 | $9,615.00 |
| | | | M2 | 10 | 1 | 57.00 | $34.00 | $1,938.00 |
| | | | M2 | 11 | 4 | 690.00 | $30.80 | $21,250.00 |
| | | **Unit Sub Total** | **M2** | | **28** | **4,636.10** | **$26.04** | **$120,709.00** |
| **120149** | TEMPORARY PAVEMENT MARKING (PAINT) | | SQFT | 1 | 1 | 72.00 | $10.00 | $720.00 |
| | | | SQFT | 3 | 2 | 294.00 | $4.14 | $1,218.00 |
| | | | SQFT | 7 | 1 | 24.00 | $6.00 | $144.00 |
| | | | SQFT | 8 | 1 | 460.00 | $10.00 | $4,600.00 |
| | | | SQFT | 11 | 1 | 98.00 | $3.00 | $294.00 |
| | | | SQFT | 12 | 6 | 13,390.00 | $1.36 | $18,144.00 |
| | | **Unit Sub Total** | **SQFT** | | **12** | **14,338.00** | **$1.75** | **$25,120.00** |
| | **Item Code 120149** | **Total No. of Proj.** | | | **41** | | **Total Amount** | **$146,335.00** |
| **120150** | TEMPORARY PAVEMENT MARKING | | M2 | 3 | 1 | 140.00 | $35.00 | $4,900.00 |
| | | | M2 | 11 | 1 | 98.00 | $35.00 | $3,430.00 |
| | | **Unit Sub Total** | **M2** | | **2** | **238.00** | **$35.00** | **$8,330.00** |
| | **Item Code 120150** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$8,330.00** |
| **120151** | TEMPORARY TRAFFIC STRIPE (TAPE) | | LF | 3 | 4 | 98,340.00 | $1.39 | $136,580.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **120151** | TEMPORARY TRAFFIC STRIPE (TAPE) | LF | 6 | 4 | 149,000.00 | $0.89 | $131,930.00 |
| | | LF | 7 | 1 | 1,650.00 | $2.30 | $3,795.00 |
| | | LF | 10 | 1 | 4,800.00 | $2.10 | $10,080.00 |
| | | LF | 11 | 2 | 1,870.00 | $2.29 | $4,283.00 |
| | **Unit Sub Total** | **LF** | | **12** | **255,660.00** | **$1.12** | **$286,668.00** |
| **120151** | TEMPORARY TRAFFIC STRIPE (TAPE) | M | 2 | 1 | 20.00 | $32.00 | $640.00 |
| | | M | 3 | 2 | 51,130.00 | $4.35 | $222,218.80 |
| | | M | 4 | 2 | 30,998.00 | $3.02 | $93,680.00 |
| | | M | 5 | 3 | 4,860.00 | $4.94 | $24,015.00 |
| | | M | 7 | 7 | 52,030.00 | $3.61 | $187,965.00 |
| | | M | 11 | 3 | 13,920.00 | $4.60 | $64,080.00 |
| | **Unit Sub Total** | **M** | | **18** | **152,958.00** | **$3.87** | **$592,598.80** |
| | **Item Code 120151 Total No. of Proj.** | | | **30** | | **Total Amount** | **$879,266.80** |
| **120152** | TEMPORARY PAVEMENT MARKING (TAPE) | M2 | 2 | 1 | 2.20 | $310.00 | $682.00 |
| | | M2 | 4 | 3 | 6.60 | $160.00 | $1,056.00 |
| | | M2 | 5 | 2 | 5.50 | $325.20 | $1,788.60 |
| | | M2 | 7 | 1 | 27.00 | $100.00 | $2,700.00 |
| | | M2 | 11 | 1 | 8.00 | $45.00 | $360.00 |
| | **Unit Sub Total** | **M2** | | **8** | **49.30** | **$133.60** | **$6,586.60** |
| **120152** | TEMPORARY PAVEMENT MARKING (TAPE) | SQFT | 1 | 2 | 310.00 | $7.52 | $2,330.00 |
| | | SQFT | 3 | 3 | 2,250.00 | $7.73 | $17,400.00 |
| | | SQFT | 6 | 2 | 770.00 | $23.21 | $17,875.00 |
| | | SQFT | 10 | 1 | 420.00 | $3.65 | $1,533.00 |
| | **Unit Sub Total** | **SQFT** | | **8** | **3,750.00** | **$10.44** | **$39,138.00** |
| | **Item Code 120152 Total No. of Proj.** | | | **16** | | **Total Amount** | **$45,724.60** |
| **120159** | TEMPORARY TRAFFIC STRIPE (PAINT) | LF | 1 | 4 | 60,400.00 | $0.51 | $30,650.00 |
| | | LF | 3 | 6 | 1,040,430.00 | $0.43 | $450,528.00 |
| | | LF | 4 | 1 | 1,100.00 | $4.00 | $4,400.00 |
| | | LF | 6 | 1 | 2,480.00 | $4.00 | $9,920.00 |
| | | LF | 7 | 1 | 1,380.00 | $2.00 | $2,760.00 |
| | | LF | 8 | 3 | 30,830.00 | $0.79 | $24,383.00 |
| | | LF | 11 | 2 | 34,340.00 | $0.64 | $22,128.00 |
| | | LF | 12 | 6 | 1,042,650.00 | $0.18 | $187,710.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **LF** | | **24** | **2,213,610.00** | **$0.33** | **$732,479.00** |
| **120159** | TEMPORARY TRAFFIC STRIPE (PAINT) | M | 1 | 5 | 62,080.00 | $1.29 | $79,990.00 |
| | | M | 2 | 1 | 45,000.00 | $1.00 | $45,000.00 |
| | | M | 3 | 6 | 192,160.00 | $1.07 | $204,948.00 |
| | | M | 4 | 7 | 244,100.00 | $1.34 | $327,605.00 |
| | | M | 5 | 4 | 5,000.00 | $2.60 | $13,006.00 |
| | | M | 6 | 1 | 2,640.00 | $1.30 | $3,432.00 |
| | | M | 7 | 11 | 995,070.00 | $0.56 | $560,552.00 |
| | | M | 8 | 3 | 165,370.00 | $0.79 | $130,392.50 |
| | | M | 9 | 3 | 105,120.00 | $0.36 | $38,308.60 |
| | | M | 10 | 2 | 28,500.00 | $0.74 | $20,999.00 |
| | | M | 11 | 5 | 88,390.00 | $1.17 | $103,510.00 |
| | | M | 12 | 1 | 2,510.00 | $1.80 | $4,518.00 |
| | **Unit Sub Total** | **M** | | **49** | **1,935,940.00** | **$0.79** | **$1,532,261.10** |
| | **Item Code 120159 Total No. of Proj.** | | | **73** | | **Total Amount** | **$2,264,740.10** |
| **120165** | CHANNELIZER (SURFACE MOUNTED) | EA | 1 | 6 | 1,369.00 | $35.62 | $48,765.00 |
| | | EA | 2 | 3 | 654.00 | $38.85 | $25,410.00 |
| | | EA | 3 | 19 | 3,778.00 | $33.55 | $126,751.00 |
| | | EA | 4 | 19 | 2,487.00 | $32.34 | $80,422.50 |
| | | EA | 5 | 16 | 2,638.00 | $30.62 | $80,764.00 |
| | | EA | 6 | 10 | 1,627.00 | $27.64 | $44,968.00 |
| | | EA | 7 | 26 | 5,036.00 | $39.86 | $200,716.04 |
| | | EA | 8 | 9 | 1,445.00 | $25.18 | $36,380.00 |
| | | EA | 9 | 3 | 4,640.00 | $27.08 | $125,660.00 |
| | | EA | 10 | 5 | 1,516.00 | $29.11 | $44,132.00 |
| | | EA | 11 | 3 | 330.00 | $54.83 | $18,095.00 |
| | | EA | 12 | 7 | 578.00 | $41.12 | $23,770.00 |
| | **Unit Sub Total** | **EA** | | **126** | **26,098.00** | **$32.79** | **$855,833.54** |
| | **Item Code 120165 Total No. of Proj.** | | | **126** | | **Total Amount** | **$855,833.54** |
| **120166** | CHANNELIZER (SURFACE MOUNTED) (LEFT IN PLACE) | EA | 5 | 1 | 52.00 | $42.00 | $2,184.00 |
| | | EA | 7 | 2 | 90.00 | $44.33 | $3,990.00 |
| | | EA | 10 | 1 | 20.00 | $26.50 | $530.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **120166** | CHANNELIZER (SURFACE MOUNTED) (LEFT IN PLACE) | EA | 11 | 5 | 643.00 | $49.00 | $31,510.00 |
| | | EA | 12 | 1 | 41.00 | $50.00 | $2,050.00 |
| | **Unit Sub Total** | **EA** | | **10** | **846.00** | **$47.59** | **$40,264.00** |
| | **Item Code 120166 Total No. of Proj.** | | | **10** | | **Total Amount** | **$40,264.00** |
| **120182** | PORTABLE DELINEATOR | EA | 2 | 1 | 39.00 | $30.00 | $1,170.00 |
| | | EA | 11 | 1 | 200.00 | $20.00 | $4,000.00 |
| | **Unit Sub Total** | **EA** | | **2** | **239.00** | **$21.63** | **$5,170.00** |
| | **Item Code 120182 Total No. of Proj.** | | | **2** | | **Total Amount** | **$5,170.00** |
| **120199** | TRAFFIC PLASTIC DRUM | EA | 1 | 2 | 260.00 | $45.19 | $11,750.00 |
| | | EA | 3 | 6 | 1,904.00 | $113.97 | $216,990.00 |
| | | EA | 11 | 5 | 618.00 | $49.46 | $30,569.15 |
| | **Unit Sub Total** | **EA** | | **13** | **2,782.00** | **$93.21** | **$259,309.15** |
| | **Item Code 120199 Total No. of Proj.** | | | **13** | | **Total Amount** | **$259,309.15** |
| **120200** | FLASHING BEACON (PORTABLE) | EA | 1 | 2 | 11.00 | $2,027.27 | $22,300.00 |
| | | EA | 3 | 2 | 6.00 | $13,016.67 | $78,100.00 |
| | | EA | 4 | 1 | 13.00 | $1,000.00 | $13,000.00 |
| | | EA | 5 | 1 | 17.00 | $485.00 | $8,245.00 |
| | | EA | 7 | 1 | 2.00 | $344.00 | $688.00 |
| | | EA | 8 | 3 | 10.00 | $1,361.00 | $13,610.00 |
| | | EA | 9 | 3 | 43.00 | $725.58 | $31,200.00 |
| | **Unit Sub Total** | **EA** | | **13** | **102.00** | **$1,638.66** | **$167,143.00** |
| | **Item Code 120200 Total No. of Proj.** | | | **13** | | **Total Amount** | **$167,143.00** |
| **120300** | TEMPORARY PAVEMENT MARKER | EA | 1 | 5 | 6,254.00 | $6.15 | $38,452.00 |
| | | EA | 2 | 1 | 2,570.00 | $4.00 | $10,280.00 |
| | | EA | 3 | 7 | 125,890.00 | $3.22 | $404,860.00 |
| | | EA | 4 | 7 | 94,230.00 | $3.17 | $298,689.00 |
| | | EA | 5 | 3 | 287.00 | $7.14 | $2,050.00 |
| | | EA | 6 | 5 | 3,425.00 | $3.97 | $13,611.00 |
| | | EA | 7 | 12 | 140,884.00 | $2.73 | $385,187.50 |
| | | EA | 8 | 5 | 25,403.00 | $4.23 | $107,413.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **120300** | TEMPORARY PAVEMENT MARKER | EA | 10 | 3 | 3,099.00 | $2.67 | $8,264.20 |
| | | EA | 11 | 10 | 24,641.00 | $3.76 | $92,545.00 |
| | | EA | 12 | 3 | 4,560.00 | $2.09 | $9,521.00 |
| | **Unit Sub Total** | **EA** | | **61** | **431,243.00** | **$3.18** | **$1,370,872.70** |
| | **Item Code 120300 Total No. of Proj.** | | | **61** | | **Total Amount** | **$1,370,872.70** |
| **121140** | TEMPORARY METAL BEAM GUARD RAILING | LF | 3 | 2 | 113.00 | $84.27 | $9,523.00 |
| | **Unit Sub Total** | **LF** | | **2** | **113.00** | **$84.27** | **$9,523.00** |
| | **Item Code 121140 Total No. of Proj.** | | | **2** | | **Total Amount** | **$9,523.00** |
| **121161** | TEMPORARY TERMINAL SECTION (TYPE K) | EA | 2 | 1 | 1.00 | $9,000.00 | $9,000.00 |
| | | EA | 3 | 1 | 2.00 | $1,200.00 | $2,400.00 |
| | | EA | 4 | 4 | 13.00 | $896.15 | $11,650.00 |
| | | EA | 7 | 2 | 44.00 | $745.91 | $32,820.00 |
| | **Unit Sub Total** | **EA** | | **8** | **60.00** | **$931.17** | **$55,870.00** |
| | **Item Code 121161 Total No. of Proj.** | | | **8** | | **Total Amount** | **$55,870.00** |
| **128201** | TEMPORARY DELINEATOR (CLASS 1) | EA | 1 | 1 | 28.00 | $30.00 | $840.00 |
| | | EA | 3 | 3 | 84.00 | $37.20 | $3,125.00 |
| | | EA | 7 | 2 | 50.00 | $42.96 | $2,148.00 |
| | **Unit Sub Total** | **EA** | | **6** | **162.00** | **$37.73** | **$6,113.00** |
| | **Item Code 128201 Total No. of Proj.** | | | **6** | | **Total Amount** | **$6,113.00** |
| **128601** | TEMPORARY SIGNAL SYSTEM | LS | 1 | 2 | 2.00 | $285,350.00 | $570,700.00 |
| | | LS | 4 | 3 | 3.00 | $46,666.67 | $140,000.00 |
| | | LS | 5 | 4 | 4.00 | $67,873.00 | $271,492.00 |
| | | LS | 11 | 1 | 1.00 | $85,000.00 | $85,000.00 |
| | **Unit Sub Total** | **LS** | | **10** | **10.00** | **$106,719.20** | **$1,067,192.00** |
| | **Item Code 128601 Total No. of Proj.** | | | **10** | | **Total Amount** | **$1,067,192.00** |
| **128650** | PORTABLE CHANGEABLE MESSAGE SIGN | EA | 1 | 22 | 62.00 | $4,589.44 | $284,545.00 |
| | | EA | 2 | 25 | 69.00 | $3,130.43 | $216,000.00 |
| | | EA | 3 | 1 | 2.00 | $1,950.00 | $3,900.00 |
| | | EA | 4 | 24 | 67.00 | $4,575.42 | $306,552.96 |
| | | EA | 8 | 43 | 116.00 | $3,767.02 | $436,974.30 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **128650** | PORTABLE CHANGEABLE MESSAGE SIGN | EA | 9 | 1 | 2.00 | $2,200.00 | $4,400.00 |
| | | EA | 11 | 47 | 219.00 | $7,066.92 | $1,547,654.98 |
| | | EA | 12 | 2 | 4.00 | $1,536.15 | $6,144.58 |
| | **Unit Sub Total** | **EA** | | **165** | **541.00** | **$5,187.01** | **$2,806,171.82** |
| **128650** | PORTABLE CHANGEABLE MESSAGE SIGN | LS | 1 | 14 | 14.00 | $15,035.71 | $210,500.00 |
| | | LS | 2 | 6 | 6.00 | $43,635.50 | $261,813.00 |
| | | LS | 3 | 81 | 81.00 | $12,775.83 | $1,034,842.50 |
| | | LS | 4 | 47 | 47.00 | $8,061.35 | $378,883.30 |
| | | LS | 5 | 51 | 51.00 | $10,172.47 | $518,796.02 |
| | | LS | 6 | 49 | 49.00 | $10,068.22 | $493,343.00 |
| | | LS | 7 | 4 | 4.00 | $8,597.50 | $34,390.00 |
| | | LS | 8 | 4 | 4.00 | $14,143.64 | $56,574.57 |
| | | LS | 9 | 12 | 12.00 | $15,674.17 | $188,090.00 |
| | | LS | 10 | 42 | 42.00 | $6,957.29 | $292,206.00 |
| | | LS | 11 | 1 | 1.00 | $50,000.00 | $50,000.00 |
| | | LS | 12 | 29 | 29.00 | $9,890.15 | $286,814.36 |
| | **Unit Sub Total** | **LS** | | **340** | **340.00** | **$11,194.86** | **$3,806,252.75** |
| | **Item Code 128650** **Total No. of Proj.** | | | **505** | | **Total Amount** | **$6,612,424.57** |
| **128660** | TEMPORARY FLASHING BEACON | LS | 2 | 2 | 2.00 | $8,000.00 | $16,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$8,000.00** | **$16,000.00** |
| | **Item Code 128660** **Total No. of Proj.** | | | **2** | | **Total Amount** | **$16,000.00** |
| **129000** | TEMPORARY RAILING (TYPE K) | LF | 1 | 2 | 920.00 | $49.22 | $45,280.00 |
| | | LF | 2 | 2 | 3,590.00 | $14.05 | $50,435.00 |
| | | LF | 3 | 19 | 474,120.00 | $13.78 | $6,535,139.00 |
| | | LF | 4 | 5 | 60,990.00 | $7.25 | $441,920.00 |
| | | LF | 5 | 3 | 4,000.00 | $22.50 | $89,980.00 |
| | | LF | 6 | 5 | 40,430.00 | $12.90 | $521,453.00 |
| | | LF | 7 | 5 | 10,310.00 | $20.12 | $207,426.40 |
| | | LF | 8 | 7 | 13,170.00 | $23.48 | $309,187.20 |
| | | LF | 11 | 6 | 104,640.00 | $5.40 | $564,820.00 |
| | | LF | 12 | 6 | 17,260.00 | $12.80 | $220,850.00 |
| | **Unit Sub Total** | **LF** | | **60** | **729,430.00** | **$12.32** | **$8,986,490.60** |
| **129000** | TEMPORARY RAILING (TYPE K) | M | 1 | 5 | 10,093.00 | $100.14 | $1,010,725.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **129000** | TEMPORARY RAILING (TYPE K) | M | 2 | 3 | 18,158.00 | $83.01 | $1,507,272.00 |
| | | M | 3 | 7 | 60,490.00 | $39.70 | $2,401,480.00 |
| | | M | 4 | 16 | 211,351.00 | $28.00 | $5,918,137.32 |
| | | M | 5 | 10 | 18,289.00 | $47.75 | $873,332.00 |
| | | M | 6 | 2 | 9,280.00 | $24.09 | $223,560.00 |
| | | M | 7 | 22 | 142,070.00 | $39.44 | $5,603,298.00 |
| | | M | 8 | 4 | 49,030.00 | $22.41 | $1,098,720.00 |
| | | M | 9 | 3 | 860.00 | $113.72 | $97,800.00 |
| | | M | 10 | 4 | 16,230.00 | $29.73 | $482,445.00 |
| | | M | 11 | 11 | 156,828.00 | $28.63 | $4,489,972.80 |
| | | M | 12 | 2 | 1,490.00 | $61.28 | $91,300.00 |
| | **Unit Sub Total** | **M** | | **89** | **694,169.00** | **$34.28** | **$23,798,042.12** |
| | **Item Code 129000 Total No. of Proj.** | | | **149** | | **Total Amount** | **$32,784,532.72** |
| **129100** | TEMPORARY CRASH CUSHION MODULE | EA | 1 | 4 | 248.00 | $338.71 | $84,000.00 |
| | | EA | 2 | 4 | 346.00 | $192.49 | $66,600.00 |
| | | EA | 3 | 22 | 2,290.00 | $246.59 | $564,693.00 |
| | | EA | 4 | 21 | 2,400.00 | $204.11 | $489,856.00 |
| | | EA | 5 | 11 | 944.00 | $159.19 | $150,280.00 |
| | | EA | 6 | 7 | 394.00 | $189.30 | $74,584.00 |
| | | EA | 7 | 23 | 3,858.00 | $207.01 | $798,627.25 |
| | | EA | 8 | 10 | 790.00 | $206.48 | $163,122.54 |
| | | EA | 9 | 3 | 139.00 | $219.86 | $30,560.00 |
| | | EA | 10 | 4 | 482.00 | $161.50 | $77,842.00 |
| | | EA | 11 | 12 | 2,576.00 | $254.00 | $654,313.70 |
| | | EA | 12 | 8 | 347.00 | $203.55 | $70,632.00 |
| | **Unit Sub Total** | **EA** | | **129** | **14,814.00** | **$217.71** | **$3,225,110.49** |
| | **Item Code 129100 Total No. of Proj.** | | | **129** | | **Total Amount** | **$3,225,110.49** |
| **129110** | TEMPORARY CRASH CUSHION | EA | 2 | 1 | 28.00 | $425.00 | $11,900.00 |
| | **Unit Sub Total** | **EA** | | **1** | **28.00** | **$425.00** | **$11,900.00** |
| | **Item Code 129110 Total No. of Proj.** | | | **1** | | **Total Amount** | **$11,900.00** |
| **129150** | TEMPORARY TRAFFIC SCREEN | LF | 3 | 2 | 99,990.00 | $1.52 | $151,600.00 |
| | | LF | 4 | 1 | 4,500.00 | $1.00 | $4,500.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **129150** | TEMPORARY TRAFFIC SCREEN | | LF | 12 | 6 | 13,800.00 | $2.95 | $40,778.00 |
| | | **Unit Sub Total** | **LF** | | **9** | **118,290.00** | **$1.66** | **$196,878.00** |
| **129150** | TEMPORARY TRAFFIC SCREEN | | M | 3 | 1 | 6,940.00 | $14.00 | $97,160.00 |
| | | | M | 4 | 1 | 5,000.00 | $9.50 | $47,500.00 |
| | | | M | 5 | 1 | 1,600.00 | $23.00 | $36,800.00 |
| | | | M | 7 | 1 | 27,700.00 | $15.00 | $415,500.00 |
| | | | M | 8 | 3 | 55,900.00 | $3.98 | $222,530.00 |
| | | | M | 10 | 3 | 11,490.00 | $4.77 | $54,780.00 |
| | | | M | 12 | 1 | 840.00 | $7.00 | $5,880.00 |
| | | **Unit Sub Total** | **M** | | **11** | **109,470.00** | **$8.04** | **$880,150.00** |
| | **Item Code 129150** | **Total No. of Proj.** | | | **20** | | **Total Amount** | **$1,077,028.00** |
| **129510** | TEMPORARY RETAINING WALL | | LF | 1 | 1 | 130.00 | $21.00 | $2,730.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **130.00** | **$21.00** | **$2,730.00** |
| **129510** | TEMPORARY RETAINING WALL | | M2 | 1 | 1 | 780.00 | $225.00 | $175,500.00 |
| | | **Unit Sub Total** | **M2** | | **1** | **780.00** | **$225.00** | **$175,500.00** |
| | **Item Code 129510** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$178,230.00** |
| **150206** | ABANDON CULVERT | | EA | 1 | 3 | 21.00 | $1,041.43 | $21,870.00 |
| | | | EA | 2 | 6 | 20.00 | $1,575.00 | $31,500.00 |
| | | | EA | 3 | 4 | 7.00 | $1,200.00 | $8,400.00 |
| | | | EA | 4 | 6 | 37.00 | $735.14 | $27,200.00 |
| | | | EA | 5 | 4 | 39.00 | $4,659.90 | $181,736.00 |
| | | | EA | 6 | 1 | 5.00 | $320.00 | $1,600.00 |
| | | | EA | 9 | 2 | 7.00 | $1,057.14 | $7,400.00 |
| | | | EA | 11 | 9 | 159.00 | $1,075.13 | $170,946.00 |
| | | **Unit Sub Total** | **EA** | | **35** | **295.00** | **$1,527.63** | **$450,652.00** |
| **150206** | ABANDON CULVERT | | LF | 1 | 1 | 170.00 | $22.00 | $3,740.00 |
| | | | LF | 3 | 1 | 70.00 | $31.00 | $2,170.00 |
| | | | LF | 5 | 1 | 61.00 | $50.00 | $3,050.00 |
| | | | LF | 7 | 1 | 380.00 | $15.00 | $5,700.00 |
| | | | LF | 12 | 3 | 1,850.00 | $21.85 | $40,430.00 |
| | | **Unit Sub Total** | **LF** | | **7** | **2,531.00** | **$21.77** | **$55,090.00** |
| **150206** | ABANDON CULVERT | | M | 2 | 1 | 260.00 | $170.00 | $44,200.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150206** | ABANDON CULVERT | M | 3 | 3 | 248.00 | $94.78 | $23,505.00 |
| | | M | 4 | 3 | 308.00 | $66.55 | $20,496.00 |
| | | M | 6 | 1 | 2.00 | $195.00 | $390.00 |
| | | M | 7 | 2 | 208.00 | $132.86 | $27,635.00 |
| | | M | 8 | 3 | 318.00 | $125.58 | $39,934.00 |
| | | M | 10 | 2 | 3,627.00 | $26.97 | $97,836.50 |
| | | M | 11 | 2 | 103.00 | $51.75 | $5,330.00 |
| | | M | 12 | 1 | 240.00 | $120.00 | $28,800.00 |
| | **Unit Sub Total** | **M** | | **18** | **5,314.00** | **$54.22** | **$288,126.50** |
| | **Item Code 150206 Total No. of Proj.** | | | **60** | | **Total Amount** | **$793,868.50** |
| **150221** | ABANDON INLET | EA | 4 | 2 | 8.00 | $668.75 | $5,350.00 |
| | | EA | 5 | 2 | 2.00 | $1,550.00 | $3,100.00 |
| | | EA | 6 | 1 | 1.00 | $900.00 | $900.00 |
| | | EA | 7 | 1 | 1.00 | $1,400.00 | $1,400.00 |
| | | EA | 11 | 5 | 54.00 | $1,110.56 | $59,970.00 |
| | | EA | 12 | 1 | 10.00 | $500.00 | $5,000.00 |
| | **Unit Sub Total** | **EA** | | **12** | **76.00** | **$996.32** | **$75,720.00** |
| | **Item Code 150221 Total No. of Proj.** | | | **12** | | **Total Amount** | **$75,720.00** |
| **150224** | ABANDON MANHOLE | EA | 10 | 1 | 2.00 | $500.00 | $1,000.00 |
| | | EA | 11 | 2 | 13.00 | $1,419.23 | $18,450.00 |
| | **Unit Sub Total** | **EA** | | **3** | **15.00** | **$1,296.67** | **$19,450.00** |
| | **Item Code 150224 Total No. of Proj.** | | | **3** | | **Total Amount** | **$19,450.00** |
| **150227** | ABANDON PIPELINE | EA | 11 | 1 | 1.00 | $1,700.00 | $1,700.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,700.00** | **$1,700.00** |
| **150227** | ABANDON PIPELINE | M | 7 | 2 | 244.00 | $154.09 | $37,598.00 |
| | | M | 10 | 2 | 5,250.00 | $5.60 | $29,400.00 |
| | | M | 11 | 1 | 270.00 | $25.00 | $6,750.00 |
| | **Unit Sub Total** | **M** | | **5** | **5,764.00** | **$12.79** | **$73,748.00** |
| | **Item Code 150227 Total No. of Proj.** | | | **6** | | **Total Amount** | **$75,448.00** |
| **150229** | ABANDON WATER WELL | EA | 5 | 1 | 1.00 | $4,000.00 | $4,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **150229** | ABANDON WATER WELL | | EA | 6 | 1 | 4.00 | $1,500.00 | $6,000.00 |
| | | | EA | 9 | 1 | 8.00 | $900.00 | $7,200.00 |
| | | | EA | 10 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | | **Unit Sub Total** | **EA** | | **4** | **14.00** | **$1,585.71** | **$22,200.00** |
| | **Item Code 150229** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$22,200.00** |
| **150241** | ABANDON SEWER | | M | 11 | 1 | 720.00 | $22.00 | $15,840.00 |
| | | **Unit Sub Total** | **M** | | **1** | **720.00** | **$22.00** | **$15,840.00** |
| | **Item Code 150241** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,840.00** |
| **150305** | OBLITERATE SURFACING | | M2 | 1 | 2 | 18,400.00 | $1.04 | $19,120.00 |
| | | | M2 | 3 | 2 | 36,840.00 | $1.05 | $38,600.00 |
| | | | M2 | 4 | 2 | 5,141.00 | $4.06 | $20,870.00 |
| | | | M2 | 7 | 2 | 7,350.00 | $10.34 | $75,975.00 |
| | | | M2 | 9 | 1 | 1,260.00 | $5.00 | $6,300.00 |
| | | | M2 | 10 | 1 | 70.00 | $35.00 | $2,450.00 |
| | | **Unit Sub Total** | **M2** | | **10** | **69,061.00** | **$2.36** | **$163,315.00** |
| **150305** | OBLITERATE SURFACING | | SQYD | 1 | 1 | 790.00 | $5.00 | $3,950.00 |
| | | | SQYD | 2 | 1 | 3,520.00 | $0.50 | $1,760.00 |
| | | **Unit Sub Total** | **SQYD** | | **2** | **4,310.00** | **$1.32** | **$5,710.00** |
| | **Item Code 150305** | **Total No. of Proj.** | | | **12** | | **Total Amount** | **$169,025.00** |
| **150604** | REMOVE WOOD FENCE | | LF | 1 | 2 | 1,580.00 | $1.21 | $1,918.00 |
| | | | LF | 4 | 1 | 120.00 | $7.50 | $900.00 |
| | | | LF | 12 | 1 | 30.00 | $21.00 | $630.00 |
| | | **Unit Sub Total** | **LF** | | **4** | **1,730.00** | **$1.99** | **$3,448.00** |
| **150604** | REMOVE WOOD FENCE | | M | 7 | 1 | 27.00 | $20.00 | $540.00 |
| | | **Unit Sub Total** | **M** | | **1** | **27.00** | **$20.00** | **$540.00** |
| | **Item Code 150604** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$3,988.00** |
| **150605** | REMOVE FENCE | | LF | 1 | 2 | 540.00 | $11.81 | $6,380.00 |
| | | **Unit Sub Total** | **LF** | | **2** | **540.00** | **$11.81** | **$6,380.00** |
| **150605** | REMOVE FENCE | | M | 1 | 2 | 4,010.00 | $12.71 | $50,980.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150605** | REMOVE FENCE | M | 2 | 4 | 536.00 | $19.13 | $10,251.84 |
| | | M | 3 | 3 | 24,057.00 | $3.61 | $86,952.00 |
| | | M | 4 | 3 | 1,880.00 | $9.89 | $18,595.00 |
| | | M | 5 | 2 | 10,050.00 | $6.00 | $60,300.00 |
| | | M | 7 | 1 | 34.00 | $40.00 | $1,360.00 |
| | | M | 8 | 1 | 10,100.00 | $4.40 | $44,440.00 |
| | | M | 9 | 1 | 9,120.00 | $6.00 | $54,720.00 |
| | | M | 11 | 3 | 3,890.00 | $14.38 | $55,930.00 |
| | **Unit Sub Total** | **M** | | **20** | **63,677.00** | **$6.02** | **$383,528.84** |
| | **Item Code 150605 Total No. of Proj.** | | | **22** | | **Total Amount** | **$389,908.84** |
| **150606** | REMOVE FENCE (TYPE BW) | M | 1 | 2 | 1,400.00 | $5.69 | $7,960.00 |
| | | M | 5 | 4 | 676.00 | $9.50 | $6,425.00 |
| | | M | 6 | 2 | 1,540.00 | $6.86 | $10,560.00 |
| | | M | 9 | 2 | 24,330.00 | $5.56 | $135,291.00 |
| | | M | 10 | 1 | 4,410.00 | $4.95 | $21,829.50 |
| | **Unit Sub Total** | **M** | | **11** | **32,356.00** | **$5.63** | **$182,065.50** |
| | **Item Code 150606 Total No. of Proj.** | | | **11** | | **Total Amount** | **$182,065.50** |
| **150607** | REMOVE FENCE (TYPE WM) | LF | 2 | 1 | 180.00 | $15.00 | $2,700.00 |
| | | LF | 10 | 1 | 21,200.00 | $1.00 | $21,200.00 |
| | **Unit Sub Total** | **LF** | | **2** | **21,380.00** | **$1.12** | **$23,900.00** |
| **150607** | REMOVE FENCE (TYPE WM) | M | 1 | 1 | 5,200.00 | $6.50 | $33,800.00 |
| | | M | 3 | 1 | 1,100.00 | $20.00 | $22,000.00 |
| | | M | 4 | 1 | 13,500.00 | $4.00 | $54,000.00 |
| | **Unit Sub Total** | **M** | | **3** | **19,800.00** | **$5.55** | **$109,800.00** |
| | **Item Code 150607 Total No. of Proj.** | | | **5** | | **Total Amount** | **$133,700.00** |
| **150608** | REMOVE CHAIN LINK FENCE | LF | 1 | 1 | 180.00 | $3.50 | $630.00 |
| | | LF | 4 | 1 | 200.00 | $7.86 | $1,572.00 |
| | | LF | 5 | 1 | 710.00 | $2.58 | $1,831.80 |
| | | LF | 7 | 1 | 2,430.00 | $2.00 | $4,860.00 |
| | | LF | 10 | 1 | 150.00 | $3.00 | $450.00 |
| | | LF | 11 | 1 | 210.00 | $10.00 | $2,100.00 |
| | | LF | 12 | 3 | 910.00 | $8.73 | $7,948.30 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **LF** | | **9** | **4,790.00** | **$4.05** | **$19,392.10** |
| **150608** | REMOVE CHAIN LINK FENCE | | M | 1 | 2 | 176.00 | $17.92 | $3,154.00 |
| | | | M | 2 | 1 | 1,390.00 | $8.00 | $11,120.00 |
| | | | M | 3 | 2 | 810.00 | $12.47 | $10,100.00 |
| | | | M | 4 | 3 | 1,382.00 | $8.58 | $11,855.00 |
| | | | M | 5 | 2 | 1,777.00 | $11.40 | $20,252.00 |
| | | | M | 6 | 1 | 130.00 | $15.00 | $1,950.00 |
| | | | M | 7 | 8 | 3,291.00 | $18.43 | $60,650.00 |
| | | | M | 10 | 2 | 870.00 | $13.09 | $11,384.80 |
| | | | M | 11 | 6 | 3,970.00 | $20.14 | $79,950.00 |
| | | **Unit Sub Total** | **M** | | **27** | **13,796.00** | **$15.25** | **$210,415.80** |
| | **Item Code 150608** | **Total No. of Proj.** | | | **36** | | **Total Amount** | **$229,807.90** |
| **150615** | REMOVE ENTRANCE TAPER | | EA | 3 | 1 | 1.00 | $500.00 | $500.00 |
| | | | EA | 6 | 1 | 37.00 | $200.00 | $7,400.00 |
| | | | EA | 7 | 1 | 1.00 | $315.00 | $315.00 |
| | | **Unit Sub Total** | **EA** | | **3** | **39.00** | **$210.64** | **$8,215.00** |
| | **Item Code 150615** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$8,215.00** |
| **150620** | REMOVE GATE | | EA | 7 | 3 | 6.00 | $382.50 | $2,295.00 |
| | | | EA | 8 | 1 | 2.00 | $1,000.00 | $2,000.00 |
| | | | EA | 9 | 1 | 10.00 | $290.00 | $2,900.00 |
| | | | EA | 12 | 1 | 3.00 | $500.00 | $1,500.00 |
| | | **Unit Sub Total** | **EA** | | **6** | **21.00** | **$414.05** | **$8,695.00** |
| | **Item Code 150620** | **Total No. of Proj.** | | | **6** | | **Total Amount** | **$8,695.00** |
| **150630** | REMOVE MARKER | | EA | 1 | 2 | 21.00 | $4.90 | $103.00 |
| | | | EA | 2 | 4 | 14.00 | $47.50 | $665.00 |
| | | | EA | 4 | 1 | 9.00 | $5.00 | $45.00 |
| | | | EA | 5 | 4 | 45.00 | $132.56 | $5,965.00 |
| | | | EA | 8 | 1 | 40.00 | $20.00 | $800.00 |
| | | | EA | 9 | 3 | 142.00 | $31.41 | $4,460.05 |
| | | | EA | 10 | 2 | 3.00 | $3.68 | $11.05 |
| | | **Unit Sub Total** | **EA** | | **17** | **274.00** | **$43.97** | **$12,049.10** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 150630 Total No. of Proj.** | | | **17** | | **Total Amount** | **$12,049.10** |
| **150645** | REMOVE BARRICADE | EA | 11 | 2 | 26.00 | $28.38 | $738.00 |
| | **Unit Sub Total** | **EA** | | **2** | **26.00** | **$28.38** | **$738.00** |
| | **Item Code 150645 Total No. of Proj.** | | | **2** | | **Total Amount** | **$738.00** |
| **150646** | REMOVE PEDESTRIAN BARRICADE | EA | 10 | 1 | 3.00 | $230.00 | $690.00 |
| | **Unit Sub Total** | **EA** | | **1** | **3.00** | **$230.00** | **$690.00** |
| | **Item Code 150646 Total No. of Proj.** | | | **1** | | **Total Amount** | **$690.00** |
| **150656** | REMOVE CABLE BARRIER | M | 4 | 1 | 4,470.00 | $12.00 | $53,640.00 |
| | | M | 11 | 2 | 4,610.00 | $9.00 | $41,490.00 |
| | **Unit Sub Total** | **M** | | **3** | **9,080.00** | **$10.48** | **$95,130.00** |
| | **Item Code 150656 Total No. of Proj.** | | | **3** | | **Total Amount** | **$95,130.00** |
| **150658** | REMOVE CABLE ANCHOR ASSEMBLY | EA | 6 | 1 | 3.00 | $370.00 | $1,110.00 |
| | | EA | 11 | 1 | 12.00 | $250.00 | $3,000.00 |
| | **Unit Sub Total** | **EA** | | **2** | **15.00** | **$274.00** | **$4,110.00** |
| | **Item Code 150658 Total No. of Proj.** | | | **2** | | **Total Amount** | **$4,110.00** |
| **150659** | REMOVE TERMINAL SECTION | EA | 2 | 1 | 5.00 | $600.00 | $3,000.00 |
| | | EA | 4 | 1 | 6.00 | $400.00 | $2,400.00 |
| | | EA | 7 | 1 | 3.00 | $524.00 | $1,572.00 |
| | | EA | 12 | 1 | 2.00 | $200.00 | $400.00 |
| | **Unit Sub Total** | **EA** | | **4** | **16.00** | **$460.75** | **$7,372.00** |
| | **Item Code 150659 Total No. of Proj.** | | | **4** | | **Total Amount** | **$7,372.00** |
| **150662** | REMOVE METAL BEAM GUARD RAILING | LF | 1 | 3 | 1,310.00 | $12.05 | $15,780.00 |
| | | LF | 2 | 5 | 5,480.00 | $9.48 | $51,954.00 |
| | | LF | 3 | 20 | 171,748.00 | $6.33 | $1,086,890.00 |
| | | LF | 4 | 8 | 16,348.00 | $7.00 | $114,390.00 |
| | | LF | 5 | 5 | 8,150.00 | $8.39 | $68,370.00 |
| | | LF | 6 | 5 | 2,610.00 | $23.21 | $60,578.00 |
| | | LF | 7 | 5 | 14,775.00 | $8.62 | $127,433.90 |
| | | LF | 8 | 3 | 2,755.00 | $4.84 | $13,335.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150662** | REMOVE METAL BEAM GUARD RAILING | LF | 9 | 1 | 610.00 | $7.10 | $4,331.00 |
| | | LF | 10 | 2 | 200.00 | $15.50 | $3,100.00 |
| | | LF | 11 | 8 | 3,072.00 | $11.93 | $36,657.20 |
| | | LF | 12 | 6 | 5,461.00 | $7.64 | $41,721.00 |
| | **Unit Sub Total** | **LF** | | **71** | **232,519.00** | **$6.99** | **$1,624,540.10** |
| **150662** | REMOVE METAL BEAM GUARD RAILING | M | 1 | 6 | 730.00 | $23.88 | $17,435.00 |
| | | M | 2 | 6 | 4,045.00 | $10.46 | $42,327.20 |
| | | M | 3 | 5 | 5,258.00 | $20.95 | $110,160.00 |
| | | M | 4 | 13 | 19,783.00 | $19.67 | $389,215.80 |
| | | M | 5 | 9 | 2,942.00 | $26.17 | $77,005.00 |
| | | M | 6 | 3 | 544.00 | $34.45 | $18,743.00 |
| | | M | 7 | 15 | 12,627.00 | $17.20 | $217,131.10 |
| | | M | 8 | 3 | 521.00 | $45.53 | $23,720.00 |
| | | M | 9 | 1 | 280.00 | $28.00 | $7,840.00 |
| | | M | 10 | 2 | 180.00 | $30.97 | $5,575.20 |
| | | M | 11 | 9 | 8,725.00 | $22.73 | $198,346.20 |
| | | M | 12 | 1 | 120.00 | $22.00 | $2,640.00 |
| | **Unit Sub Total** | **M** | | **73** | **55,755.00** | **$19.91** | **$1,110,138.50** |
| | **Item Code 150662 Total No. of Proj.** | | | **144** | | **Total Amount** | **$2,734,678.60** |
| **150665** | REMOVE SINGLE METAL BEAM BARRIER | M | 11 | 1 | 600.00 | $25.00 | $15,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **600.00** | **$25.00** | **$15,000.00** |
| | **Item Code 150665 Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,000.00** |
| **150666** | REMOVE METAL BEAM BARRIER | LF | 4 | 1 | 20,000.00 | $8.00 | $160,000.00 |
| | **Unit Sub Total** | **LF** | | **1** | **20,000.00** | **$8.00** | **$160,000.00** |
| **150666** | REMOVE METAL BEAM BARRIER | M | 10 | 1 | 90.00 | $30.00 | $2,700.00 |
| | **Unit Sub Total** | **M** | | **1** | **90.00** | **$30.00** | **$2,700.00** |
| | **Item Code 150666 Total No. of Proj.** | | | **2** | | **Total Amount** | **$162,700.00** |
| **150667** | REMOVE DOUBLE METAL BEAM BARRIER | LF | 3 | 1 | 5,160.00 | $7.00 | $36,120.00 |
| | | LF | 4 | 1 | 643.00 | $8.00 | $5,144.00 |
| | | LF | 5 | 1 | 50.00 | $10.00 | $500.00 |
| | | LF | 7 | 1 | 820.00 | $17.00 | $13,940.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **LF** | | **4** | **6,673.00** | **$8.35** | **$55,704.00** |
| **150667** | REMOVE DOUBLE METAL BEAM BARRIER | | M | 8 | 1 | 13,100.00 | $24.00 | $314,400.00 |
| | | | M | 11 | 2 | 109.00 | $38.17 | $4,160.00 |
| | | **Unit Sub Total** | **M** | | **3** | **13,209.00** | **$24.12** | **$318,560.00** |
| | **Item Code 150667** | **Total No. of Proj.** | | | **7** | | **Total Amount** | **$374,264.00** |
| **150668** | REMOVE FLARED END SECTION | | EA | 1 | 2 | 10.00 | $282.00 | $2,820.00 |
| | | | EA | 2 | 3 | 8.00 | $116.25 | $930.00 |
| | | | EA | 3 | 7 | 43.00 | $212.00 | $9,116.00 |
| | | | EA | 4 | 5 | 56.00 | $122.11 | $6,838.00 |
| | | | EA | 5 | 3 | 17.00 | $782.35 | $13,300.00 |
| | | | EA | 6 | 1 | 3.00 | $275.00 | $825.00 |
| | | | EA | 7 | 2 | 5.00 | $146.00 | $730.00 |
| | | | EA | 10 | 1 | 7.00 | $150.00 | $1,050.00 |
| | | | EA | 12 | 1 | 3.00 | $600.00 | $1,800.00 |
| | | **Unit Sub Total** | **EA** | | **25** | **152.00** | **$246.11** | **$37,409.00** |
| | **Item Code 150668** | **Total No. of Proj.** | | | **25** | | **Total Amount** | **$37,409.00** |
| **150685** | REMOVE IRRIGATION FACILITY | | LS | 3 | 1 | 1.00 | $5,300.00 | $5,300.00 |
| | | | LS | 7 | 1 | 1.00 | $500.00 | $500.00 |
| | | | LS | 11 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$10,266.67** | **$30,800.00** |
| | **Item Code 150685** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$30,800.00** |
| **150701** | REMOVE YELLOW PAINTED TRAFFIC STRIPE | | LF | 1 | 2 | 2,580.00 | $2.80 | $7,220.00 |
| | | | LF | 3 | 2 | 5,050.00 | $2.61 | $13,162.50 |
| | | | LF | 6 | 2 | 44,800.00 | $0.67 | $29,869.00 |
| | | | LF | 7 | 4 | 26,010.00 | $0.57 | $14,905.40 |
| | | | LF | 11 | 10 | 116,510.00 | $0.89 | $103,325.00 |
| | | | LF | 12 | 2 | 4,080.00 | $0.52 | $2,124.20 |
| | | **Unit Sub Total** | **LF** | | **22** | **199,030.00** | **$0.86** | **$170,606.10** |
| **150701** | REMOVE YELLOW PAINTED TRAFFIC STRIPE | | M | 1 | 1 | 2,200.00 | $8.00 | $17,600.00 |
| | | | M | 2 | 1 | 2,950.00 | $4.00 | $11,800.00 |
| | | | M | 3 | 1 | 2,690.00 | $4.70 | $12,643.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150701** | REMOVE YELLOW PAINTED TRAFFIC STRIPE | M | 4 | 2 | 8,400.00 | $1.46 | $12,261.90 |
| | | M | 7 | 3 | 1,770.00 | $4.50 | $7,970.00 |
| | | M | 9 | 2 | 5,370.00 | $1.19 | $6,365.40 |
| | | M | 10 | 2 | 6,730.00 | $1.71 | $11,493.60 |
| | | M | 11 | 2 | 4,700.00 | $4.54 | $21,335.00 |
| | **Unit Sub Total** | **M** | | **14** | **34,810.00** | **$2.91** | **$101,468.90** |
| | **Item Code 150701 Total No. of Proj.** | | | **36** | | **Total Amount** | **$272,075.00** |
| **150704** | REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE | LF | 1 | 5 | 46,980.00 | $2.09 | $98,170.00 |
| | | LF | 2 | 1 | 6,780.00 | $2.20 | $14,916.00 |
| | | LF | 3 | 8 | 15,470.00 | $3.35 | $51,750.00 |
| | | LF | 4 | 23 | 388,820.00 | $0.87 | $340,216.00 |
| | | LF | 5 | 10 | 188,190.00 | $0.49 | $92,667.00 |
| | | LF | 6 | 3 | 47,820.00 | $0.64 | $30,465.00 |
| | | LF | 7 | 15 | 266,950.00 | $0.55 | $147,492.60 |
| | | LF | 8 | 10 | 115,010.00 | $0.73 | $84,148.60 |
| | | LF | 10 | 7 | 57,950.00 | $0.62 | $36,076.50 |
| | | LF | 12 | 17 | 609,500.00 | $0.48 | $290,283.80 |
| | **Unit Sub Total** | **LF** | | **99** | **1,743,470.00** | **$0.68** | **$1,186,185.50** |
| **150704** | REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE | M | 1 | 4 | 10,960.00 | $4.48 | $49,110.00 |
| | | M | 2 | 3 | 4,530.00 | $10.49 | $47,500.00 |
| | | M | 3 | 1 | 5,150.00 | $6.00 | $30,900.00 |
| | | M | 4 | 11 | 69,190.00 | $1.96 | $135,839.90 |
| | | M | 5 | 7 | 24,810.00 | $2.84 | $70,465.00 |
| | | M | 6 | 2 | 5,500.00 | $2.80 | $15,426.00 |
| | | M | 7 | 17 | 218,298.00 | $1.03 | $225,878.00 |
| | | M | 8 | 2 | 23,520.00 | $0.91 | $21,516.00 |
| | | M | 10 | 4 | 13,480.00 | $2.02 | $27,270.00 |
| | | M | 11 | 1 | 800.00 | $6.00 | $4,800.00 |
| | | M | 12 | 4 | 1,670.00 | $3.64 | $6,075.50 |
| | **Unit Sub Total** | **M** | | **56** | **377,908.00** | **$1.68** | **$634,780.40** |
| | **Item Code 150704 Total No. of Proj.** | | | **155** | | **Total Amount** | **$1,820,965.90** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150705** | REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING | M2 | 3 | 1 | 110.00 | $100.00 | $11,000.00 |
| | | M2 | 10 | 2 | 72.00 | $57.03 | $4,105.80 |
| | | M2 | 12 | 1 | 45.00 | $23.00 | $1,035.00 |
| | **Unit Sub Total** | **M2** | | **4** | **227.00** | **$71.10** | **$16,140.80** |
| **150705** | REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING | SQFT | 1 | 2 | 645.00 | $11.78 | $7,600.00 |
| | | SQFT | 2 | 1 | 750.00 | $12.00 | $9,000.00 |
| | | SQFT | 3 | 2 | 149.00 | $38.79 | $5,780.00 |
| | | SQFT | 4 | 1 | 2,300.00 | $3.00 | $6,900.00 |
| | | SQFT | 5 | 2 | 590.00 | $2.55 | $1,507.00 |
| | | SQFT | 6 | 1 | 790.00 | $5.00 | $3,950.00 |
| | | SQFT | 7 | 2 | 4,000.00 | $1.90 | $7,614.00 |
| | | SQFT | 10 | 1 | 110.00 | $2.05 | $225.50 |
| | | SQFT | 11 | 4 | 999.00 | $5.49 | $5,483.43 |
| | **Unit Sub Total** | **SQFT** | | **16** | **10,333.00** | **$4.65** | **$48,059.93** |
| | **Item Code 150705 Total No. of Proj.** | | | **20** | | **Total Amount** | **$64,200.73** |
| **150710** | REMOVE TRAFFIC STRIPE | LF | 2 | 2 | 7,960.00 | $1.65 | $13,097.00 |
| | | LF | 3 | 7 | 170,740.00 | $1.42 | $243,256.00 |
| | | LF | 5 | 1 | 28,200.00 | $0.68 | $19,176.00 |
| | | LF | 6 | 3 | 33,350.00 | $0.85 | $28,285.00 |
| | | LF | 7 | 1 | 5,370.00 | $0.70 | $3,759.00 |
| | | LF | 8 | 3 | 3,807.00 | $0.72 | $2,755.24 |
| | | LF | 11 | 10 | 873,340.00 | $0.30 | $260,632.00 |
| | **Unit Sub Total** | **LF** | | **27** | **1,122,767.00** | **$0.51** | **$570,960.24** |
| **150710** | REMOVE TRAFFIC STRIPE | M | 1 | 1 | 3,080.00 | $2.00 | $6,160.00 |
| | | M | 2 | 1 | 28,100.00 | $1.50 | $42,150.00 |
| | | M | 3 | 3 | 72,013.00 | $2.04 | $146,855.00 |
| | | M | 4 | 2 | 3,740.00 | $1.77 | $6,627.50 |
| | | M | 5 | 1 | 28,000.00 | $1.35 | $37,800.00 |
| | | M | 6 | 1 | 250.00 | $2.00 | $500.00 |
| | | M | 7 | 3 | 6,890.00 | $1.64 | $11,280.00 |
| | | M | 9 | 1 | 15,800.00 | $0.70 | $11,060.00 |
| | | M | 11 | 6 | 336,700.00 | $1.26 | $425,285.00 |
| | | M | 12 | 1 | 1,390.00 | $2.50 | $3,475.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M** | | **20** | **495,963.00** | **$1.39** | **$691,192.50** |
| **150710** | REMOVE TRAFFIC STRIPE | | SQFT | 11 | 1 | 1,480.00 | $1.65 | $2,442.00 |
| | | **Unit Sub Total** | **SQFT** | | **1** | **1,480.00** | **$1.65** | **$2,442.00** |
| | **Item Code 150710** | **Total No. of Proj.** | | | **48** | | **Total Amount** | **$1,264,594.74** |
| **150711** | REMOVE PAINTED TRAFFIC STRIPE | | LF | 1 | 1 | 22.00 | $10.00 | $220.00 |
| | | | LF | 3 | 2 | 263,300.00 | $0.84 | $220,290.00 |
| | | | LF | 4 | 1 | 15,500.00 | $1.00 | $15,500.00 |
| | | | LF | 5 | 2 | 90,700.00 | $0.23 | $21,267.00 |
| | | | LF | 6 | 2 | 25,030.00 | $0.48 | $12,113.00 |
| | | | LF | 7 | 5 | 56,860.00 | $0.23 | $13,102.80 |
| | | | LF | 10 | 1 | 1,770.00 | $2.80 | $4,956.00 |
| | | | LF | 12 | 3 | 51,010.00 | $0.40 | $20,604.40 |
| | | **Unit Sub Total** | **LF** | | **17** | **504,192.00** | **$0.61** | **$308,053.20** |
| **150711** | REMOVE PAINTED TRAFFIC STRIPE | | M | 1 | 1 | 25,000.00 | $1.05 | $26,250.00 |
| | | | M | 2 | 1 | 3,680.00 | $2.00 | $7,360.00 |
| | | | M | 3 | 2 | 48,040.00 | $3.44 | $165,320.00 |
| | | | M | 4 | 4 | 67,620.00 | $1.29 | $86,959.00 |
| | | | M | 5 | 2 | 2,300.00 | $3.08 | $7,095.00 |
| | | | M | 7 | 9 | 777,030.00 | $1.02 | $791,322.00 |
| | | | M | 9 | 2 | 11,020.00 | $1.23 | $13,577.60 |
| | | | M | 10 | 4 | 10,995.00 | $1.32 | $14,474.20 |
| | | **Unit Sub Total** | **M** | | **25** | **945,685.00** | **$1.18** | **$1,112,357.80** |
| | **Item Code 150711** | **Total No. of Proj.** | | | **42** | | **Total Amount** | **$1,420,411.00** |
| **150712** | REMOVE PAINTED PAVEMENT MARKING | | M2 | 1 | 1 | 250.00 | $25.00 | $6,250.00 |
| | | | M2 | 3 | 2 | 104.00 | $34.17 | $3,554.00 |
| | | | M2 | 4 | 2 | 73.00 | $21.36 | $1,559.60 |
| | | | M2 | 5 | 1 | 14.00 | $45.00 | $630.00 |
| | | | M2 | 9 | 1 | 82.00 | $20.00 | $1,640.00 |
| | | | M2 | 10 | 1 | 13.00 | $5.10 | $66.30 |
| | | **Unit Sub Total** | **M2** | | **8** | **536.00** | **$25.56** | **$13,699.90** |
| **150712** | REMOVE PAINTED PAVEMENT MARKING | | SQFT | 4 | 1 | 45.00 | $3.00 | $135.00 |
| | | | SQFT | 7 | 1 | 80.00 | $1.00 | $80.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150712** | REMOVE PAINTED PAVEMENT MARKING | SQFT | 12 | 1 | 1,460.00 | $2.00 | $2,920.00 |
| | **Unit Sub Total** | **SQFT** | | **3** | **1,585.00** | **$1.98** | **$3,135.00** |
| | **Item Code 150712 Total No. of Proj.** | | | **11** | | **Total Amount** | **$16,834.90** |
| **150713** | REMOVE PAVEMENT MARKING | M2 | 1 | 2 | 80.00 | $106.25 | $8,500.00 |
| | | M2 | 2 | 1 | 52.00 | $70.00 | $3,640.00 |
| | | M2 | 3 | 1 | 220.00 | $40.00 | $8,800.00 |
| | | M2 | 4 | 1 | 20.00 | $25.00 | $500.00 |
| | | M2 | 5 | 2 | 172.00 | $25.00 | $4,300.00 |
| | | M2 | 6 | 2 | 153.00 | $76.47 | $11,700.00 |
| | | M2 | 7 | 5 | 832.00 | $16.99 | $14,135.00 |
| | | M2 | 9 | 2 | 180.00 | $22.42 | $4,035.00 |
| | | M2 | 10 | 1 | 78.00 | $60.00 | $4,680.00 |
| | | M2 | 11 | 5 | 383.00 | $17.41 | $6,669.00 |
| | **Unit Sub Total** | **M2** | | **22** | **2,170.00** | **$30.86** | **$66,959.00** |
| **150713** | REMOVE PAVEMENT MARKING | SQFT | 2 | 1 | 23.00 | $49.26 | $1,132.98 |
| | | SQFT | 3 | 2 | 242.00 | $10.87 | $2,630.00 |
| | | SQFT | 4 | 1 | 130.00 | $7.00 | $910.00 |
| | | SQFT | 7 | 2 | 960.00 | $2.14 | $2,055.60 |
| | | SQFT | 8 | 3 | 2,820.00 | $1.92 | $5,420.60 |
| | | SQFT | 11 | 1 | 1,500.00 | $4.00 | $6,000.00 |
| | **Unit Sub Total** | **SQFT** | | **10** | **5,675.00** | **$3.20** | **$18,149.18** |
| | **Item Code 150713 Total No. of Proj.** | | | **32** | | **Total Amount** | **$85,108.18** |
| **150714** | REMOVE THERMOPLASTIC TRAFFIC STRIPE | LF | 1 | 6 | 8,220.00 | $1.65 | $13,591.00 |
| | | LF | 3 | 9 | 79,900.00 | $1.24 | $99,128.00 |
| | | LF | 4 | 19 | 299,370.00 | $0.75 | $223,140.00 |
| | | LF | 5 | 13 | 149,750.00 | $0.45 | $66,727.20 |
| | | LF | 6 | 11 | 214,490.00 | $0.40 | $84,790.60 |
| | | LF | 7 | 14 | 147,870.00 | $0.52 | $76,640.90 |
| | | LF | 8 | 7 | 302,670.00 | $0.33 | $98,579.00 |
| | | LF | 10 | 10 | 109,831.00 | $0.64 | $70,048.00 |
| | | LF | 12 | 20 | 612,110.00 | $0.37 | $224,461.50 |
| | **Unit Sub Total** | **LF** | | **109** | **1,924,211.00** | **$0.50** | **$957,106.20** |
| **150714** | REMOVE THERMOPLASTIC TRAFFIC STRIPE | M | 1 | 1 | 4,500.00 | $0.70 | $3,150.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150714** | REMOVE THERMOPLASTIC TRAFFIC STRIPE | M | 2 | 1 | 800.00 | $2.00 | $1,600.00 |
| | | M | 3 | 1 | 300.00 | $2.00 | $600.00 |
| | | M | 4 | 9 | 121,914.00 | $1.17 | $143,045.00 |
| | | M | 5 | 4 | 2,600.00 | $4.58 | $11,900.00 |
| | | M | 6 | 3 | 9,938.00 | $1.53 | $15,188.00 |
| | | M | 7 | 14 | 129,660.00 | $1.15 | $148,462.80 |
| | | M | 8 | 3 | 117,800.00 | $0.63 | $73,680.00 |
| | | M | 10 | 5 | 12,970.00 | $2.83 | $36,720.40 |
| | | M | 12 | 2 | 820.00 | $2.70 | $2,211.00 |
| | **Unit Sub Total** | **M** | | **43** | **401,302.00** | **$1.09** | **$436,557.20** |
| **150714** | REMOVE THERMOPLASTIC TRAFFIC STRIPE | SQFT | 3 | 1 | 2,900.00 | $6.50 | $18,850.00 |
| | | SQFT | 6 | 2 | 6,510.00 | $0.96 | $6,248.00 |
| | **Unit Sub Total** | **SQFT** | | **3** | **9,410.00** | **$2.67** | **$25,098.00** |
| | **Item Code 150714 Total No. of Proj.** | | | **155** | | **Total Amount** | **$1,418,761.40** |
| **150715** | REMOVE THERMOPLASTIC PAVEMENT MARKING | LF | 12 | 2 | 3,000.00 | $1.06 | $3,173.00 |
| | **Unit Sub Total** | **LF** | | **2** | **3,000.00** | **$1.06** | **$3,173.00** |
| **150715** | REMOVE THERMOPLASTIC PAVEMENT MARKING | M2 | 1 | 1 | 79.00 | $30.00 | $2,370.00 |
| | | M2 | 3 | 1 | 3.00 | $35.00 | $105.00 |
| | | M2 | 4 | 5 | 260.00 | $25.57 | $6,649.00 |
| | | M2 | 5 | 3 | 209.00 | $44.00 | $9,195.00 |
| | | M2 | 6 | 3 | 23.00 | $62.17 | $1,430.00 |
| | | M2 | 7 | 7 | 407.00 | $26.38 | $10,734.65 |
| | | M2 | 8 | 2 | 82.00 | $11.95 | $980.00 |
| | | M2 | 9 | 1 | 16.00 | $20.00 | $320.00 |
| | | M2 | 10 | 5 | 680.00 | $18.10 | $12,309.00 |
| | | M2 | 12 | 1 | 56.00 | $18.00 | $1,008.00 |
| | **Unit Sub Total** | **M2** | | **29** | **1,815.00** | **$24.85** | **$45,100.65** |
| **150715** | REMOVE THERMOPLASTIC PAVEMENT MARKING | SQFT | 1 | 11 | 10,522.00 | $6.14 | $64,557.00 |
| | | SQFT | 2 | 9 | 11,750.00 | $4.36 | $51,273.00 |
| | | SQFT | 3 | 2 | 454.00 | $5.11 | $2,320.00 |
| | | SQFT | 4 | 19 | 17,164.00 | $3.09 | $53,056.60 |
| | | SQFT | 5 | 12 | 33,788.00 | $1.66 | $56,019.10 |
| | | SQFT | 6 | 14 | 14,950.00 | $2.22 | $33,128.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150715** | REMOVE THERMOPLASTIC PAVEMENT MARKING | SQFT | 7 | 9 | 16,958.00 | $1.46 | $24,806.00 |
| | | SQFT | 8 | 11 | 11,220.00 | $2.42 | $27,198.10 |
| | | SQFT | 10 | 14 | 14,151.00 | $2.55 | $36,137.00 |
| | | SQFT | 12 | 16 | 21,350.00 | $1.79 | $38,180.10 |
| | **Unit Sub Total** | **SQFT** | | **117** | **152,307.00** | **$2.54** | **$386,674.90** |
| | **Item Code 150715 Total No. of Proj.** | | | **148** | | **Total Amount** | **$434,948.55** |
| **150717** | REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING | M | 11 | 1 | 46,600.00 | $0.50 | $23,300.00 |
| | **Unit Sub Total** | **M** | | **1** | **46,600.00** | **$0.50** | **$23,300.00** |
| **150717** | REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING | M2 | 11 | 4 | 5,381.00 | $12.57 | $67,625.00 |
| | **Unit Sub Total** | **M2** | | **4** | **5,381.00** | **$12.57** | **$67,625.00** |
| **150717** | REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING | SQFT | 7 | 1 | 85.00 | $5.50 | $467.50 |
| | | SQFT | 11 | 11 | 330,940.00 | $0.75 | $246,752.00 |
| | **Unit Sub Total** | **SQFT** | | **12** | **331,025.00** | **$0.75** | **$247,219.50** |
| | **Item Code 150717 Total No. of Proj.** | | | **17** | | **Total Amount** | **$338,144.50** |
| **150718** | REMOVE THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING | LF | 2 | 1 | 6,030.00 | $1.15 | $6,934.50 |
| | **Unit Sub Total** | **LF** | | **1** | **6,030.00** | **$1.15** | **$6,934.50** |
| **150718** | REMOVE THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING | M2 | 12 | 1 | 60.00 | $27.50 | $1,650.00 |
| | **Unit Sub Total** | **M2** | | **1** | **60.00** | **$27.50** | **$1,650.00** |
| **150718** | REMOVE THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING | SQFT | 3 | 7 | 24,220.00 | $1.73 | $42,006.00 |
| | **Unit Sub Total** | **SQFT** | | **7** | **24,220.00** | **$1.73** | **$42,006.00** |
| | **Item Code 150718 Total No. of Proj.** | | | **9** | | **Total Amount** | **$50,590.50** |
| **150720** | REMOVE CONTRAST TREATMENT | M2 | 4 | 1 | 166.00 | $25.50 | $4,233.00 |
| | **Unit Sub Total** | **M2** | | **1** | **166.00** | **$25.50** | **$4,233.00** |
| **150720** | REMOVE CONTRAST TREATMENT | SQFT | 5 | 2 | 19,320.00 | $0.67 | $13,020.00 |
| | | SQFT | 7 | 1 | 68,630.00 | $0.50 | $34,315.00 |
| | | SQFT | 8 | 1 | 12,471.00 | $0.20 | $2,494.20 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150720** | REMOVE CONTRAST TREATMENT | SQFT | 10 | 1 | 55,200.00 | $0.16 | $8,832.00 |
| | | SQFT | 11 | 1 | 11,500.00 | $0.70 | $8,050.00 |
| | **Unit Sub Total** | **SQFT** | | **6** | **167,121.00** | **$0.40** | **$66,711.20** |
| | **Item Code 150720 Total No. of Proj.** | | | **7** | | **Total Amount** | **$70,944.20** |
| **150722** | REMOVE PAVEMENT MARKER | EA | 2 | 2 | 2,741.00 | $1.10 | $3,020.00 |
| | | EA | 3 | 4 | 8,796.00 | $1.06 | $9,357.00 |
| | | EA | 4 | 39 | 193,787.00 | $1.11 | $215,236.00 |
| | | EA | 5 | 7 | 5,362.00 | $1.16 | $6,246.00 |
| | | EA | 6 | 8 | 5,984.00 | $1.73 | $10,345.00 |
| | | EA | 7 | 36 | 127,414.00 | $0.77 | $98,600.92 |
| | | EA | 8 | 24 | 104,165.00 | $0.64 | $66,372.60 |
| | | EA | 10 | 17 | 11,466.00 | $1.13 | $12,910.30 |
| | | EA | 11 | 1 | 150.00 | $2.00 | $300.00 |
| | | EA | 12 | 22 | 112,874.00 | $0.76 | $85,526.04 |
| | **Unit Sub Total** | **EA** | | **160** | **572,739.00** | **$0.89** | **$507,913.86** |
| **150722** | REMOVE PAVEMENT MARKER | LF | 6 | 2 | 189.00 | $1.50 | $283.00 |
| | **Unit Sub Total** | **LF** | | **2** | **189.00** | **$1.50** | **$283.00** |
| **150722** | REMOVE PAVEMENT MARKER | LS | 3 | 2 | 2.00 | $50,500.00 | $101,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$50,500.00** | **$101,000.00** |
| | **Item Code 150722 Total No. of Proj.** | | | **164** | | **Total Amount** | **$609,196.86** |
| **150730** | REMOVE CHANNELIZERS | EA | 4 | 1 | 1,470.00 | $12.00 | $17,640.00 |
| | | EA | 10 | 1 | 38.00 | $1.05 | $39.90 |
| | | EA | 11 | 5 | 298.00 | $4.89 | $1,456.00 |
| | **Unit Sub Total** | **EA** | | **7** | **1,806.00** | **$10.60** | **$19,135.90** |
| | **Item Code 150730 Total No. of Proj.** | | | **7** | | **Total Amount** | **$19,135.90** |
| **150740** | REMOVE SIGN | EA | 6 | 1 | 18.00 | $100.00 | $1,800.00 |
| | **Unit Sub Total** | **EA** | | **1** | **18.00** | **$100.00** | **$1,800.00** |
| | **Item Code 150740 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,800.00** |
| **150741** | REMOVE ROADSIDE SIGN MOUNTED ON MAST ARM | EA | 2 | 1 | 1.00 | $300.00 | $300.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$300.00** | **$300.00** |
| | **Item Code 150741** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$300.00** |
| **150742** | REMOVE ROADSIDE SIGN | | EA | 1 | 6 | 132.00 | $105.57 | $13,935.00 |
| | | | EA | 2 | 8 | 156.00 | $64.20 | $10,015.00 |
| | | | EA | 3 | 18 | 547.00 | $90.33 | $49,410.50 |
| | | | EA | 4 | 9 | 128.00 | $67.91 | $8,692.00 |
| | | | EA | 5 | 7 | 141.00 | $122.36 | $17,253.00 |
| | | | EA | 6 | 8 | 47.00 | $101.23 | $4,758.00 |
| | | | EA | 7 | 14 | 353.00 | $111.43 | $39,336.00 |
| | | | EA | 8 | 5 | 43.00 | $109.28 | $4,699.00 |
| | | | EA | 9 | 4 | 286.00 | $70.29 | $20,102.00 |
| | | | EA | 10 | 9 | 126.00 | $69.78 | $8,792.60 |
| | | | EA | 11 | 13 | 287.00 | $134.60 | $38,630.00 |
| | | | EA | 12 | 15 | 100.00 | $106.20 | $10,620.00 |
| | | **Unit Sub Total** | **EA** | | **116** | **2,346.00** | **$96.44** | **$226,243.10** |
| | **Item Code 150742** | **Total No. of Proj.** | | | **116** | | **Total Amount** | **$226,243.10** |
| **150744** | REMOVE ROADSIDE SIGN (WOOD POST) | | EA | 1 | 1 | 32.00 | $100.00 | $3,200.00 |
| | | | EA | 4 | 4 | 42.00 | $73.81 | $3,100.00 |
| | | | EA | 5 | 1 | 5.00 | $125.00 | $625.00 |
| | | | EA | 6 | 1 | 9.00 | $100.00 | $900.00 |
| | | | EA | 7 | 2 | 2.00 | $150.00 | $300.00 |
| | | | EA | 8 | 4 | 313.00 | $111.29 | $34,835.00 |
| | | | EA | 12 | 2 | 38.00 | $117.11 | $4,450.00 |
| | | **Unit Sub Total** | **EA** | | **15** | **441.00** | **$107.51** | **$47,410.00** |
| | **Item Code 150744** | **Total No. of Proj.** | | | **15** | | **Total Amount** | **$47,410.00** |
| **150745** | REMOVE ROADSIDE SIGN (METAL POST) | | EA | 7 | 1 | 5.00 | $170.00 | $850.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **5.00** | **$170.00** | **$850.00** |
| | **Item Code 150745** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$850.00** |
| **150747** | REMOVE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD) | | EA | 2 | 1 | 16.00 | $225.00 | $3,600.00 |
| | | | EA | 3 | 3 | 12.00 | $66.67 | $800.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150747** | REMOVE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD) | EA | 4 | 2 | 12.00 | $75.88 | $910.50 |
| | | EA | 7 | 2 | 4.00 | $77.50 | $310.00 |
| | | EA | 12 | 5 | 17.00 | $80.02 | $1,360.36 |
| | **Unit Sub Total** | **EA** | | **13** | **61.00** | **$114.44** | **$6,980.86** |
| | **Item Code 150747 Total No. of Proj.** | | | **13** | | **Total Amount** | **$6,980.86** |
| **150748** | REMOVE ROADSIDE SIGN PANEL | EA | 2 | 1 | 3.00 | $400.00 | $1,200.00 |
| | | EA | 3 | 1 | 6.00 | $500.00 | $3,000.00 |
| | | EA | 4 | 2 | 7.00 | $98.57 | $690.00 |
| | | EA | 7 | 4 | 54.00 | $43.98 | $2,375.00 |
| | | EA | 8 | 2 | 5.00 | $40.00 | $200.00 |
| | | EA | 10 | 1 | 1.00 | $48.00 | $48.00 |
| | | EA | 12 | 7 | 64.00 | $31.95 | $2,044.80 |
| | **Unit Sub Total** | **EA** | | **18** | **140.00** | **$68.27** | **$9,557.80** |
| | **Item Code 150748 Total No. of Proj.** | | | **18** | | **Total Amount** | **$9,557.80** |
| **150760** | REMOVE SIGN STRUCTURE | EA | 2 | 1 | 2.00 | $6,000.00 | $12,000.00 |
| | | EA | 3 | 6 | 24.00 | $6,474.17 | $155,380.00 |
| | | EA | 4 | 5 | 46.00 | $3,677.83 | $169,180.00 |
| | | EA | 5 | 2 | 5.00 | $5,320.00 | $26,600.00 |
| | | EA | 6 | 2 | 2.00 | $7,500.00 | $15,000.00 |
| | | EA | 7 | 8 | 42.00 | $3,349.40 | $140,675.00 |
| | | EA | 8 | 2 | 4.00 | $5,431.25 | $21,725.00 |
| | | EA | 10 | 2 | 2.00 | $3,438.00 | $6,876.00 |
| | | EA | 11 | 6 | 71.00 | $4,711.27 | $334,500.00 |
| | | EA | 12 | 4 | 9.00 | $3,577.78 | $32,200.00 |
| | **Unit Sub Total** | **EA** | | **38** | **207.00** | **$4,416.12** | **$914,136.00** |
| | **Item Code 150760 Total No. of Proj.** | | | **38** | | **Total Amount** | **$914,136.00** |
| **150761** | REMOVE SIGN PANEL AND REMOVABLE SIGN PANEL FRAME | M2 | 7 | 1 | 24.00 | $875.00 | $21,000.00 |
| | **Unit Sub Total** | **M2** | | **1** | **24.00** | **$875.00** | **$21,000.00** |
| | **Item Code 150761 Total No. of Proj.** | | | **1** | | **Total Amount** | **$21,000.00** |
| **150763** | REMOVE SIGN PANEL | EA | 7 | 1 | 3.00 | $700.00 | $2,100.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **150763** | REMOVE SIGN PANEL | | EA | 10 | 1 | 1.00 | $105.00 | $105.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **4.00** | **$551.25** | **$2,205.00** |
| | **Item Code 150763** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,205.00** |
| **150764** | REMOVE SIGN OVERLAY | | EA | 3 | 1 | 1.00 | $515.00 | $515.00 |
| | | | EA | 11 | 1 | 1.00 | $130.00 | $130.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **2.00** | **$322.50** | **$645.00** |
| **150764** | REMOVE SIGN OVERLAY | | M2 | 7 | 2 | 4.50 | $238.89 | $1,075.00 |
| | | | M2 | 11 | 1 | 15.00 | $100.00 | $1,500.00 |
| | | **Unit Sub Total** | **M2** | | **3** | **19.50** | **$132.05** | **$2,575.00** |
| | **Item Code 150764** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$3,220.00** |
| **150767** | REMOVE BRIDGE MOUNTED SIGN | | EA | 2 | 1 | 2.00 | $6,000.00 | $12,000.00 |
| | | | EA | 3 | 3 | 15.00 | $2,466.00 | $36,990.00 |
| | | | EA | 7 | 3 | 5.00 | $3,485.80 | $17,429.00 |
| | | | EA | 8 | 1 | 2.00 | $2,650.00 | $5,300.00 |
| | | | EA | 11 | 1 | 4.00 | $2,500.00 | $10,000.00 |
| | | **Unit Sub Total** | **EA** | | **9** | **28.00** | **$2,918.54** | **$81,719.00** |
| | **Item Code 150767** | **Total No. of Proj.** | | | **9** | | **Total Amount** | **$81,719.00** |
| **150769** | REMOVE ASPHALT CONCRETE | | CY | 8 | 2 | 162.00 | $76.54 | $12,400.00 |
| | | **Unit Sub Total** | **CY** | | **2** | **162.00** | **$76.54** | **$12,400.00** |
| **150769** | REMOVE ASPHALT CONCRETE | | M3 | 3 | 1 | 1,070.00 | $40.00 | $42,800.00 |
| | | | M3 | 4 | 1 | 470.00 | $23.00 | $10,810.00 |
| | | **Unit Sub Total** | **M3** | | **2** | **1,540.00** | **$34.81** | **$53,610.00** |
| **150769** | REMOVE ASPHALT CONCRETE | | SQFT | 5 | 1 | 7,810.00 | $5.72 | $44,673.20 |
| | | | SQFT | 8 | 1 | 830.00 | $7.50 | $6,225.00 |
| | | | SQFT | 12 | 1 | 400.00 | $5.17 | $2,068.00 |
| | | **Unit Sub Total** | **SQFT** | | **3** | **9,040.00** | **$5.86** | **$52,966.20** |
| **150769** | REMOVE ASPHALT CONCRETE | | SQYD | 4 | 1 | 5,100.00 | $0.50 | $2,550.00 |
| | | **Unit Sub Total** | **SQYD** | | **1** | **5,100.00** | **$0.50** | **$2,550.00** |
| | **Item Code 150769** | **Total No. of Proj.** | | | **8** | | **Total Amount** | **$121,526.20** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150771** | REMOVE ASPHALT CONCRETE DIKE | LF | 1 | 6 | 70,390.00 | $2.31 | $162,634.00 |
| | | LF | 2 | 3 | 214.00 | $10.41 | $2,228.00 |
| | | LF | 3 | 14 | 79,850.00 | $1.88 | $150,166.50 |
| | | LF | 4 | 7 | 77,153.00 | $1.10 | $84,798.50 |
| | | LF | 5 | 8 | 72,490.00 | $2.34 | $169,758.00 |
| | | LF | 6 | 5 | 24,180.00 | $1.03 | $24,816.20 |
| | | LF | 7 | 3 | 6,640.00 | $4.11 | $27,315.00 |
| | | LF | 8 | 2 | 1,370.00 | $3.80 | $5,200.00 |
| | | LF | 10 | 2 | 32,080.00 | $0.93 | $29,840.00 |
| | | LF | 11 | 13 | 38,491.00 | $1.71 | $65,658.50 |
| | | LF | 12 | 4 | 31,451.00 | $2.05 | $64,557.00 |
| | **Unit Sub Total** | **LF** | | **67** | **434,309.00** | **$1.81** | **$786,971.70** |
| **150771** | REMOVE ASPHALT CONCRETE DIKE | M | 1 | 2 | 77.00 | $10.77 | $829.00 |
| | | M | 2 | 1 | 30.00 | $20.00 | $600.00 |
| | | M | 3 | 4 | 6,783.00 | $20.34 | $137,935.00 |
| | | M | 4 | 7 | 10,185.00 | $4.54 | $46,269.40 |
| | | M | 5 | 9 | 16,079.00 | $7.75 | $124,599.00 |
| | | M | 6 | 5 | 5,292.00 | $4.19 | $22,192.00 |
| | | M | 7 | 12 | 22,077.00 | $8.63 | $190,583.00 |
| | | M | 8 | 2 | 19,327.00 | $3.90 | $75,345.00 |
| | | M | 10 | 1 | 450.00 | $1.70 | $765.00 |
| | | M | 11 | 4 | 11,183.00 | $1.94 | $21,646.00 |
| | **Unit Sub Total** | **M** | | **47** | **91,483.00** | **$6.79** | **$620,763.40** |
| | **Item Code 150771 Total No. of Proj.** | | | **114** | | **Total Amount** | **$1,407,735.10** |
| **150772** | REMOVE CURB | LF | 10 | 1 | 1,710.00 | $3.30 | $5,643.00 |
| | **Unit Sub Total** | **LF** | | **1** | **1,710.00** | **$3.30** | **$5,643.00** |
| **150772** | REMOVE CURB | M | 7 | 1 | 7,710.00 | $15.00 | $115,650.00 |
| | **Unit Sub Total** | **M** | | **1** | **7,710.00** | **$15.00** | **$115,650.00** |
| | **Item Code 150772 Total No. of Proj.** | | | **2** | | **Total Amount** | **$121,293.00** |
| **150801** | REMOVE OVERSIDE DRAIN | EA | 2 | 1 | 3.00 | $300.00 | $900.00 |
| | | EA | 3 | 1 | 14.00 | $1,000.00 | $14,000.00 |
| | | EA | 4 | 2 | 46.00 | $590.87 | $27,180.00 |
| | | EA | 7 | 1 | 1.00 | $13,570.00 | $13,570.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **150801** | REMOVE OVERSIDE DRAIN | | EA | 8 | 1 | 35.00 | $600.00 | $21,000.00 |
| | | | EA | 11 | 3 | 7.00 | $1,172.86 | $8,210.00 |
| | | | EA | 12 | 2 | 2.00 | $1,870.00 | $3,740.00 |
| | | **Unit Sub Total** | **EA** | | **11** | **108.00** | **$820.37** | **$88,600.00** |
| | **Item Code 150801** | **Total No. of Proj.** | | | **11** | | **Total Amount** | **$88,600.00** |
| **150804** | REMOVE DRAINAGE FACILITY | | EA | 8 | 1 | 2.00 | $500.00 | $1,000.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$500.00** | **$1,000.00** |
| **150804** | REMOVE DRAINAGE FACILITY | | M | 5 | 1 | 6.00 | $449.00 | $2,694.00 |
| | | **Unit Sub Total** | **M** | | **1** | **6.00** | **$449.00** | **$2,694.00** |
| | **Item Code 150804** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$3,694.00** |
| **150805** | REMOVE CULVERT | | EA | 1 | 8 | 35.00 | $1,529.11 | $53,519.00 |
| | | | EA | 2 | 1 | 1.00 | $500.00 | $500.00 |
| | | | EA | 3 | 2 | 16.00 | $3,835.25 | $61,364.00 |
| | | | EA | 4 | 1 | 3.00 | $300.00 | $900.00 |
| | | **Unit Sub Total** | **EA** | | **12** | **55.00** | **$2,114.24** | **$116,283.00** |
| **150805** | REMOVE CULVERT | | LF | 1 | 1 | 1,350.00 | $8.00 | $10,800.00 |
| | | | LF | 2 | 5 | 576.50 | $64.80 | $37,355.00 |
| | | | LF | 3 | 6 | 1,209.00 | $66.65 | $80,576.00 |
| | | | LF | 4 | 3 | 514.00 | $44.26 | $22,750.00 |
| | | | LF | 5 | 1 | 44.00 | $470.00 | $20,680.00 |
| | | | LF | 6 | 3 | 53.00 | $153.21 | $8,120.00 |
| | | | LF | 8 | 1 | 120.00 | $50.00 | $6,000.00 |
| | | **Unit Sub Total** | **LF** | | **20** | **3,866.50** | **$48.18** | **$186,281.00** |
| **150805** | REMOVE CULVERT | | M | 2 | 3 | 106.00 | $106.80 | $11,321.00 |
| | | | M | 3 | 6 | 3,710.00 | $63.30 | $234,850.00 |
| | | | M | 4 | 8 | 2,947.00 | $29.56 | $87,125.00 |
| | | | M | 5 | 3 | 552.00 | $67.54 | $37,280.00 |
| | | | M | 6 | 4 | 437.00 | $60.00 | $26,222.00 |
| | | | M | 8 | 3 | 740.00 | $69.36 | $51,325.00 |
| | | | M | 10 | 3 | 199.00 | $39.87 | $7,933.50 |
| | | | M | 11 | 4 | 1,680.00 | $70.17 | $117,890.00 |
| | | | M | 12 | 1 | 27.00 | $100.00 | $2,700.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M** | | **35** | **10,398.00** | **$55.46** | **$576,646.50** |
| | **Item Code 150805** | **Total No. of Proj.** | | | **67** | | **Total Amount** | **$879,210.50** |
| **150806** | REMOVE PIPE | | LF | 2 | 1 | 690.00 | $12.00 | $8,280.00 |
| | | | LF | 5 | 1 | 58.00 | $39.00 | $2,262.00 |
| | | | LF | 6 | 1 | 220.00 | $30.00 | $6,600.00 |
| | | | LF | 7 | 2 | 200.00 | $38.66 | $7,732.00 |
| | | | LF | 8 | 1 | 2.00 | $200.00 | $400.00 |
| | | | LF | 12 | 1 | 130.00 | $50.00 | $6,500.00 |
| | | **Unit Sub Total** | **LF** | | **7** | **1,300.00** | **$24.44** | **$31,774.00** |
| **150806** | REMOVE PIPE | | LS | 7 | 1 | 1.00 | $500.00 | $500.00 |
| | | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$500.00** | **$500.00** |
| **150806** | REMOVE PIPE | | M | 4 | 4 | 149.00 | $114.82 | $17,108.80 |
| | | | M | 5 | 6 | 605.30 | $65.55 | $39,677.00 |
| | | | M | 6 | 1 | 5.00 | $325.00 | $1,625.00 |
| | | | M | 7 | 11 | 3,868.70 | $51.54 | $199,411.25 |
| | | | M | 8 | 1 | 80.00 | $390.00 | $31,200.00 |
| | | | M | 11 | 1 | 4.80 | $425.00 | $2,040.00 |
| | | | M | 12 | 2 | 38.00 | $282.37 | $10,730.00 |
| | | **Unit Sub Total** | **M** | | **26** | **4,750.80** | **$63.52** | **$301,792.05** |
| | **Item Code 150806** | **Total No. of Proj.** | | | **34** | | **Total Amount** | **$334,066.05** |
| **150820** | REMOVE INLET | | EA | 1 | 6 | 19.00 | $528.95 | $10,050.00 |
| | | | EA | 2 | 8 | 32.00 | $706.25 | $22,600.00 |
| | | | EA | 3 | 9 | 185.00 | $779.08 | $144,130.00 |
| | | | EA | 4 | 14 | 153.00 | $566.48 | $86,671.24 |
| | | | EA | 5 | 5 | 46.00 | $936.57 | $43,082.00 |
| | | | EA | 6 | 5 | 54.00 | $254.72 | $13,755.00 |
| | | | EA | 7 | 7 | 155.00 | $1,411.81 | $218,830.00 |
| | | | EA | 8 | 6 | 94.00 | $1,329.68 | $124,990.00 |
| | | | EA | 9 | 2 | 21.00 | $357.14 | $7,500.00 |
| | | | EA | 10 | 4 | 62.00 | $311.53 | $19,315.00 |
| | | | EA | 11 | 4 | 71.00 | $1,029.86 | $73,120.00 |
| | | | EA | 12 | 3 | 5.00 | $700.00 | $3,500.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **73** | **897.00** | **$855.68** | **$767,543.24** |
| | **Item Code 150820** | **Total No. of Proj.** | | | **73** | | **Total Amount** | **$767,543.24** |
| **150821** | REMOVE HEADWALL | | CY | 8 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | | **Unit Sub Total** | **CY** | | **1** | **1.00** | **$1,000.00** | **$1,000.00** |
| **150821** | REMOVE HEADWALL | | EA | 1 | 6 | 72.00 | $511.53 | $36,830.00 |
| | | | EA | 2 | 6 | 24.00 | $482.58 | $11,582.00 |
| | | | EA | 3 | 8 | 50.00 | $1,076.32 | $53,816.00 |
| | | | EA | 4 | 6 | 62.00 | $898.39 | $55,700.00 |
| | | | EA | 5 | 10 | 29.00 | $1,357.72 | $39,373.80 |
| | | | EA | 6 | 4 | 126.00 | $569.68 | $71,780.00 |
| | | | EA | 7 | 2 | 14.00 | $372.50 | $5,215.00 |
| | | | EA | 8 | 1 | 1.00 | $890.00 | $890.00 |
| | | | EA | 9 | 4 | 31.00 | $991.94 | $30,750.00 |
| | | | EA | 10 | 3 | 5.00 | $816.00 | $4,080.00 |
| | | | EA | 12 | 2 | 6.00 | $1,633.33 | $9,800.00 |
| | | **Unit Sub Total** | **EA** | | **52** | **420.00** | **$761.47** | **$319,816.80** |
| **150821** | REMOVE HEADWALL | | LS | 7 | 1 | 1.00 | $3,000.00 | $3,000.00 |
| | | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$3,000.00** | **$3,000.00** |
| | **Item Code 150821** | **Total No. of Proj.** | | | **54** | | **Total Amount** | **$323,816.80** |
| **150823** | REMOVE DOWNDRAIN | | EA | 1 | 3 | 11.00 | $282.73 | $3,110.00 |
| | | | EA | 2 | 2 | 4.00 | $475.00 | $1,900.00 |
| | | | EA | 3 | 3 | 35.00 | $671.43 | $23,500.00 |
| | | | EA | 4 | 1 | 1.00 | $325.00 | $325.00 |
| | | | EA | 10 | 1 | 2.00 | $250.00 | $500.00 |
| | | **Unit Sub Total** | **EA** | | **10** | **53.00** | **$553.49** | **$29,335.00** |
| **150823** | REMOVE DOWNDRAIN | | LF | 2 | 1 | 130.00 | $17.50 | $2,275.00 |
| | | | LF | 3 | 1 | 180.00 | $26.00 | $4,680.00 |
| | | | LF | 4 | 1 | 100.00 | $50.00 | $5,000.00 |
| | | | LF | 6 | 1 | 1,500.00 | $20.00 | $30,000.00 |
| | | **Unit Sub Total** | **LF** | | **4** | **1,910.00** | **$21.97** | **$41,955.00** |
| **150823** | REMOVE DOWNDRAIN | | M | 3 | 1 | 56.00 | $150.00 | $8,400.00 |
| | | | M | 4 | 1 | 1.00 | $500.00 | $500.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150823** | REMOVE DOWNDRAIN | M | 11 | 1 | 76.00 | $71.00 | $5,396.00 |
| | **Unit Sub Total** | **M** | | **3** | **133.00** | **$107.49** | **$14,296.00** |
| | **Item Code 150823 Total No. of Proj.** | | | **17** | | **Total Amount** | **$85,586.00** |
| **150825** | REMOVE REINFORCED CONCRETE BOX CULVERT | M | 3 | 1 | 20.00 | $200.00 | $4,000.00 |
| | | M | 4 | 1 | 20.00 | $325.00 | $6,500.00 |
| | **Unit Sub Total** | **M** | | **2** | **40.00** | **$262.50** | **$10,500.00** |
| **150825** | REMOVE REINFORCED CONCRETE BOX CULVERT | M3 | 4 | 1 | 2.00 | $1,000.00 | $2,000.00 |
| | **Unit Sub Total** | **M3** | | **1** | **2.00** | **$1,000.00** | **$2,000.00** |
| | **Item Code 150825 Total No. of Proj.** | | | **3** | | **Total Amount** | **$12,500.00** |
| **150826** | REMOVE MANHOLE | EA | 3 | 1 | 3.00 | $1,200.00 | $3,600.00 |
| | | EA | 11 | 1 | 4.00 | $1,200.00 | $4,800.00 |
| | **Unit Sub Total** | **EA** | | **2** | **7.00** | **$1,200.00** | **$8,400.00** |
| | **Item Code 150826 Total No. of Proj.** | | | **2** | | **Total Amount** | **$8,400.00** |
| **150827** | REMOVE CATCH BASIN | EA | 12 | 2 | 4.00 | $1,000.00 | $4,000.00 |
| | **Unit Sub Total** | **EA** | | **2** | **4.00** | **$1,000.00** | **$4,000.00** |
| | **Item Code 150827 Total No. of Proj.** | | | **2** | | **Total Amount** | **$4,000.00** |
| **150828** | REMOVE JUNCTION BOX | EA | 7 | 2 | 2.00 | $1,245.00 | $2,490.00 |
| | **Unit Sub Total** | **EA** | | **2** | **2.00** | **$1,245.00** | **$2,490.00** |
| | **Item Code 150828 Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,490.00** |
| **150829** | REMOVE RETAINING WALL | CY | 4 | 1 | 33.00 | $125.00 | $4,125.00 |
| | **Unit Sub Total** | **CY** | | **1** | **33.00** | **$125.00** | **$4,125.00** |
| **150829** | REMOVE RETAINING WALL | M | 3 | 1 | 360.00 | $78.00 | $28,080.00 |
| | | M | 5 | 1 | 14.00 | $250.00 | $3,500.00 |
| | **Unit Sub Total** | **M** | | **2** | **374.00** | **$84.44** | **$31,580.00** |
| | **Item Code 150829 Total No. of Proj.** | | | **3** | | **Total Amount** | **$35,705.00** |
| **150830** | REMOVE RETAINING WALL (PORTION) | LS | 4 | 1 | 1.00 | $4,500.00 | $4,500.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **150830** | REMOVE RETAINING WALL (PORTION) | LS | 5 | 1 | 1.00 | $10,000.00 | $10,000.00 |
| | | LS | 6 | 1 | 1.00 | $30,000.00 | $30,000.00 |
| | | LS | 12 | 1 | 1.00 | $4,000.00 | $4,000.00 |
| | **Unit Sub Total** | **LS** | | **4** | **4.00** | **$12,125.00** | **$48,500.00** |
| **150830** | REMOVE RETAINING WALL (PORTION) | M | 7 | 1 | 30.00 | $175.00 | $5,250.00 |
| | | M | 11 | 1 | 2,200.00 | $45.00 | $99,000.00 |
| | **Unit Sub Total** | **M** | | **2** | **2,230.00** | **$46.75** | **$104,250.00** |
| **150830** | REMOVE RETAINING WALL (PORTION) | M3 | 2 | 1 | 130.00 | $450.00 | $58,500.00 |
| | | M3 | 4 | 1 | 25.00 | $170.00 | $4,250.00 |
| | | M3 | 7 | 1 | 2.00 | $1,000.00 | $2,000.00 |
| | **Unit Sub Total** | **M3** | | **3** | **157.00** | **$412.42** | **$64,750.00** |
| | **Item Code 150830 Total No. of Proj.** | | | **9** | | **Total Amount** | **$217,500.00** |
| **150844** | REMOVE SLOPE PAVING | LS | 11 | 2 | 2.00 | $2,150.50 | $4,301.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$2,150.50** | **$4,301.00** |
| | **Item Code 150844 Total No. of Proj.** | | | **2** | | **Total Amount** | **$4,301.00** |
| **150846** | REMOVE CONCRETE PAVEMENT | CY | 3 | 1 | 1,550.00 | $90.00 | $139,500.00 |
| | | CY | 6 | 2 | 540.00 | $87.13 | $47,050.00 |
| | **Unit Sub Total** | **CY** | | **3** | **2,090.00** | **$89.26** | **$186,550.00** |
| **150846** | REMOVE CONCRETE PAVEMENT | M2 | 7 | 2 | 22,050.00 | $14.91 | $328,850.00 |
| | **Unit Sub Total** | **M2** | | **2** | **22,050.00** | **$14.91** | **$328,850.00** |
| **150846** | REMOVE CONCRETE PAVEMENT | M3 | 4 | 1 | 500.00 | $20.00 | $10,000.00 |
| | | M3 | 7 | 1 | 130.00 | $43.00 | $5,590.00 |
| | **Unit Sub Total** | **M3** | | **2** | **630.00** | **$24.75** | **$15,590.00** |
| **150846** | REMOVE CONCRETE PAVEMENT | SQYD | 12 | 1 | 160.00 | $22.00 | $3,520.00 |
| | **Unit Sub Total** | **SQYD** | | **1** | **160.00** | **$22.00** | **$3,520.00** |
| | **Item Code 150846 Total No. of Proj.** | | | **8** | | **Total Amount** | **$534,510.00** |
| **150847** | REMOVE CONCRETE PAVEMENT AND BASE | CY | 3 | 1 | 170.00 | $53.00 | $9,010.00 |
| | **Unit Sub Total** | **CY** | | **1** | **170.00** | **$53.00** | **$9,010.00** |
| **150847** | REMOVE CONCRETE PAVEMENT AND BASE | M3 | 3 | 1 | 1,620.00 | $50.00 | $81,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M3** | | **1** | **1,620.00** | **$50.00** | **$81,000.00** |
| | **Item Code 150847** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$90,010.00** |
| **150857** | REMOVE ASPHALT CONCRETE SURFACING | | M2 | 1 | 1 | 1,079.00 | $25.00 | $26,975.00 |
| | | | M2 | 2 | 1 | 515.00 | $35.00 | $18,025.00 |
| | | | M2 | 3 | 2 | 5,754.00 | $12.00 | $69,020.00 |
| | | | M2 | 6 | 1 | 1,042.00 | $30.00 | $31,260.00 |
| | | | M2 | 7 | 3 | 944.50 | $44.70 | $42,221.00 |
| | | | M2 | 8 | 1 | 2,458.00 | $21.00 | $51,618.00 |
| | | **Unit Sub Total** | **M2** | | **9** | **11,792.50** | **$20.28** | **$239,119.00** |
| **150857** | REMOVE ASPHALT CONCRETE SURFACING | | M3 | 3 | 1 | 5,480.00 | $20.00 | $109,600.00 |
| | | | M3 | 4 | 1 | 1,210.00 | $12.00 | $14,520.00 |
| | | | M3 | 8 | 1 | 2,080.00 | $26.75 | $55,640.00 |
| | | **Unit Sub Total** | **M3** | | **3** | **8,770.00** | **$20.50** | **$179,760.00** |
| **150857** | REMOVE ASPHALT CONCRETE SURFACING | | SQFT | 1 | 3 | 67,091.00 | $1.12 | $74,874.70 |
| | | | SQFT | 2 | 3 | 61,986.00 | $1.62 | $100,268.50 |
| | | | SQFT | 3 | 3 | 19,280.00 | $1.87 | $36,035.50 |
| | | | SQFT | 4 | 1 | 137,600.00 | $0.50 | $68,800.00 |
| | | | SQFT | 6 | 1 | 14,020.00 | $1.00 | $14,020.00 |
| | | | SQFT | 7 | 1 | 4,189.00 | $1.00 | $4,189.00 |
| | | | SQFT | 8 | 1 | 16,368.00 | $1.10 | $18,004.80 |
| | | | SQFT | 10 | 2 | 21,210.00 | $1.27 | $26,949.00 |
| | | | SQFT | 11 | 1 | 7,390.00 | $2.20 | $16,258.00 |
| | | | SQFT | 12 | 1 | 225.00 | $9.00 | $2,025.00 |
| | | **Unit Sub Total** | **SQFT** | | **17** | **349,359.00** | **$1.03** | **$361,424.50** |
| **150857** | REMOVE ASPHALT CONCRETE SURFACING | | SQYD | 6 | 1 | 2,900.00 | $3.75 | $10,875.00 |
| | | **Unit Sub Total** | **SQYD** | | **1** | **2,900.00** | **$3.75** | **$10,875.00** |
| | **Item Code 150857** | **Total No. of Proj.** | | | **30** | | **Total Amount** | **$791,178.50** |
| **150859** | REMOVE ASPHALT CONCRETE OVERSIDE DRAIN | | EA | 3 | 2 | 14.00 | $728.57 | $10,200.00 |
| | | | EA | 4 | 1 | 4.00 | $625.00 | $2,500.00 |
| | | | EA | 5 | 1 | 1.00 | $714.00 | $714.00 |
| | | | EA | 7 | 1 | 2.00 | $1,250.00 | $2,500.00 |
| | | | EA | 12 | 2 | 3.00 | $939.33 | $2,818.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **7** | **24.00** | **$780.50** | **$18,732.00** |
| | **Item Code 150859** | **Total No. of Proj.** | | | **7** | | **Total Amount** | **$18,732.00** |
| **150860** | REMOVE BASE AND SURFACING | | CY | 3 | 1 | 96,700.00 | $45.00 | $4,351,500.00 |
| | | | CY | 8 | 1 | 1.00 | $660.00 | $660.00 |
| | | | CY | 11 | 1 | 46.00 | $84.00 | $3,864.00 |
| | | **Unit Sub Total** | **CY** | | **3** | **96,747.00** | **$45.02** | **$4,356,024.00** |
| **150860** | REMOVE BASE AND SURFACING | | M3 | 1 | 2 | 781.00 | $19.30 | $15,070.00 |
| | | | M3 | 4 | 3 | 20,580.00 | $10.53 | $216,660.00 |
| | | | M3 | 5 | 1 | 990.00 | $15.00 | $14,850.00 |
| | | | M3 | 11 | 5 | 4,397.00 | $13.05 | $57,390.00 |
| | | **Unit Sub Total** | **M3** | | **11** | **26,748.00** | **$11.36** | **$303,970.00** |
| | **Item Code 150860** | **Total No. of Proj.** | | | **14** | | **Total Amount** | **$4,659,994.00** |
| **150870** | REMOVE CONCRETE DECK SURFACE | | M2 | 2 | 1 | 507.00 | $55.00 | $27,885.00 |
| | | | M2 | 7 | 1 | 263.00 | $155.00 | $40,765.00 |
| | | | M2 | 11 | 2 | 660.00 | $59.52 | $39,280.00 |
| | | **Unit Sub Total** | **M2** | | **4** | **1,430.00** | **$75.48** | **$107,930.00** |
| **150870** | REMOVE CONCRETE DECK SURFACE | | SQFT | 2 | 1 | 1,447.00 | $7.50 | $10,852.50 |
| | | | SQFT | 3 | 5 | 100,852.00 | $1.54 | $155,408.02 |
| | | | SQFT | 4 | 6 | 151,187.00 | $0.99 | $149,474.80 |
| | | | SQFT | 8 | 1 | 10,304.00 | $1.10 | $11,334.40 |
| | | **Unit Sub Total** | **SQFT** | | **13** | **263,790.00** | **$1.24** | **$327,069.72** |
| | **Item Code 150870** | **Total No. of Proj.** | | | **17** | | **Total Amount** | **$434,999.72** |
| **151224** | REMOVE DELINEATOR | | EA | 1 | 1 | 180.00 | $5.00 | $900.00 |
| | | | EA | 2 | 4 | 88.00 | $44.49 | $3,915.00 |
| | | | EA | 4 | 2 | 90.00 | $11.67 | $1,050.00 |
| | | | EA | 5 | 4 | 77.00 | $14.57 | $1,122.00 |
| | | | EA | 6 | 1 | 250.00 | $10.00 | $2,500.00 |
| | | | EA | 7 | 2 | 111.00 | $13.65 | $1,515.00 |
| | | | EA | 8 | 1 | 26.00 | $25.00 | $650.00 |
| | | | EA | 9 | 4 | 592.00 | $26.76 | $15,844.00 |
| | | | EA | 10 | 1 | 4.00 | $20.00 | $80.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **151224** | REMOVE DELINEATOR | EA | 11 | 3 | 128.00 | $43.16 | $5,525.00 |
| | | EA | 12 | 7 | 614.00 | $13.64 | $8,372.24 |
| | **Unit Sub Total** | **EA** | | **30** | **2,160.00** | **$19.20** | **$41,473.24** |
| | **Item Code 151224 Total No. of Proj.** | | | **30** | | **Total Amount** | **$41,473.24** |
| **151226** | SALVAGE GRATE | EA | 3 | 1 | 53.00 | $100.00 | $5,300.00 |
| | **Unit Sub Total** | **EA** | | **1** | **53.00** | **$100.00** | **$5,300.00** |
| | **Item Code 151226 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,300.00** |
| **151227** | SALVAGE FRAME AND GRATE | EA | 2 | 1 | 3.00 | $110.00 | $330.00 |
| | **Unit Sub Total** | **EA** | | **1** | **3.00** | **$110.00** | **$330.00** |
| | **Item Code 151227 Total No. of Proj.** | | | **1** | | **Total Amount** | **$330.00** |
| **151266** | SALVAGE DOUBLE THRIE BEAM BARRIER | M | 3 | 1 | 1,550.00 | $24.00 | $37,200.00 |
| | **Unit Sub Total** | **M** | | **1** | **1,550.00** | **$24.00** | **$37,200.00** |
| | **Item Code 151266 Total No. of Proj.** | | | **1** | | **Total Amount** | **$37,200.00** |
| **151270** | SALVAGE METAL BRIDGE RAILING | LF | 3 | 1 | 450.00 | $12.00 | $5,400.00 |
| | **Unit Sub Total** | **LF** | | **1** | **450.00** | **$12.00** | **$5,400.00** |
| **151270** | SALVAGE METAL BRIDGE RAILING | M | 4 | 1 | 65.00 | $40.00 | $2,600.00 |
| | | M | 5 | 1 | 96.00 | $57.00 | $5,472.00 |
| | | M | 8 | 1 | 520.00 | $14.00 | $7,280.00 |
| | **Unit Sub Total** | **M** | | **3** | **681.00** | **$22.54** | **$15,352.00** |
| | **Item Code 151270 Total No. of Proj.** | | | **4** | | **Total Amount** | **$20,752.00** |
| **151272** | SALVAGE METAL BEAM GUARD RAILING | LF | 3 | 1 | 2,060.00 | $12.00 | $24,720.00 |
| | | LF | 7 | 1 | 31,000.00 | $8.00 | $248,000.00 |
| | **Unit Sub Total** | **LF** | | **2** | **33,060.00** | **$8.25** | **$272,720.00** |
| **151272** | SALVAGE METAL BEAM GUARD RAILING | M | 4 | 1 | 84.00 | $20.00 | $1,680.00 |
| | | M | 6 | 2 | 246.00 | $40.18 | $9,884.00 |
| | | M | 8 | 2 | 4,310.00 | $21.57 | $92,980.00 |
| | **Unit Sub Total** | **M** | | **5** | **4,640.00** | **$22.53** | **$104,544.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 151272 Total No. of Proj.** | | | **7** | | **Total Amount** | **$377,264.00** |
| **151274** | SALVAGE CONCRETE BARRIER (TYPE K) | LF | 3 | 1 | 60.00 | $7.00 | $420.00 |
| | | LF | 4 | 1 | 160.00 | $5.00 | $800.00 |
| | **Unit Sub Total** | **LF** | | **2** | **220.00** | **$5.55** | **$1,220.00** |
| **151274** | SALVAGE CONCRETE BARRIER (TYPE K) | M | 4 | 3 | 11,570.00 | $17.06 | $197,410.00 |
| | | M | 5 | 1 | 49.00 | $47.35 | $2,320.15 |
| | | M | 7 | 2 | 1,217.00 | $19.52 | $23,760.00 |
| | **Unit Sub Total** | **M** | | **6** | **12,836.00** | **$17.41** | **$223,490.15** |
| | **Item Code 151274 Total No. of Proj.** | | | **8** | | **Total Amount** | **$224,710.15** |
| **151278** | SALVAGE DOUBLE METAL BEAM BARRIER | LF | 8 | 1 | 1,380.00 | $10.00 | $13,800.00 |
| | **Unit Sub Total** | **LF** | | **1** | **1,380.00** | **$10.00** | **$13,800.00** |
| | **Item Code 151278 Total No. of Proj.** | | | **1** | | **Total Amount** | **$13,800.00** |
| **151282** | SALVAGE ROADSIDE SIGN PANEL | EA | 5 | 1 | 4.00 | $150.00 | $600.00 |
| | **Unit Sub Total** | **EA** | | **1** | **4.00** | **$150.00** | **$600.00** |
| | **Item Code 151282 Total No. of Proj.** | | | **1** | | **Total Amount** | **$600.00** |
| **151510** | RECONSTRUCT DRAINAGE FACILITY | EA | 2 | 1 | 1.00 | $1,080.00 | $1,080.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,080.00** | **$1,080.00** |
| **151510** | RECONSTRUCT DRAINAGE FACILITY | LS | 3 | 1 | 1.00 | $2,500.00 | $2,500.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$2,500.00** | **$2,500.00** |
| | **Item Code 151510 Total No. of Proj.** | | | **2** | | **Total Amount** | **$3,580.00** |
| **151512** | RECONSTRUCT INLET | EA | 2 | 1 | 1.00 | $600.00 | $600.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$600.00** | **$600.00** |
| | **Item Code 151512 Total No. of Proj.** | | | **1** | | **Total Amount** | **$600.00** |
| **151531** | RECONSTRUCT FENCE | M | 5 | 1 | 360.00 | $30.00 | $10,800.00 |
| | **Unit Sub Total** | **M** | | **1** | **360.00** | **$30.00** | **$10,800.00** |
| | **Item Code 151531 Total No. of Proj.** | | | **1** | | **Total Amount** | **$10,800.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **151534** | RECONSTRUCT WOOD FENCE | M | 5 | 1 | 34.00 | $190.00 | $6,460.00 |
| | **Unit Sub Total** | **M** | | **1** | **34.00** | **$190.00** | **$6,460.00** |
| | **Item Code 151534 Total No. of Proj.** | | | **1** | | **Total Amount** | **$6,460.00** |
| **151536** | RECONSTRUCT FENCE (TYPE BW) | LF | 1 | 2 | 260.00 | $22.88 | $5,950.00 |
| | | LF | 5 | 1 | 100.00 | $15.00 | $1,500.00 |
| | | LF | 11 | 1 | 70.00 | $25.00 | $1,750.00 |
| | **Unit Sub Total** | **LF** | | **4** | **430.00** | **$21.40** | **$9,200.00** |
| **151536** | RECONSTRUCT FENCE (TYPE BW) | M | 1 | 1 | 35.00 | $55.00 | $1,925.00 |
| | | M | 5 | 1 | 38.00 | $84.00 | $3,192.00 |
| | | M | 6 | 1 | 94.00 | $25.00 | $2,350.00 |
| | **Unit Sub Total** | **M** | | **3** | **167.00** | **$44.71** | **$7,467.00** |
| | **Item Code 151536 Total No. of Proj.** | | | **7** | | **Total Amount** | **$16,667.00** |
| **151537** | RECONSTRUCT FENCE (TYPE WM) | LF | 1 | 1 | 12,250.00 | $4.00 | $49,000.00 |
| | **Unit Sub Total** | **LF** | | **1** | **12,250.00** | **$4.00** | **$49,000.00** |
| | **Item Code 151537 Total No. of Proj.** | | | **1** | | **Total Amount** | **$49,000.00** |
| **151540** | RECONSTRUCT CHAIN LINK FENCE | LF | 1 | 2 | 1,650.00 | $24.55 | $40,500.00 |
| | | LF | 3 | 1 | 400.00 | $11.50 | $4,600.00 |
| | | LF | 7 | 2 | 1,576.00 | $21.80 | $34,360.00 |
| | | LF | 12 | 1 | 70.00 | $24.50 | $1,715.00 |
| | **Unit Sub Total** | **LF** | | **6** | **3,696.00** | **$21.96** | **$81,175.00** |
| **151540** | RECONSTRUCT CHAIN LINK FENCE | M | 3 | 1 | 16.00 | $100.00 | $1,600.00 |
| | | M | 4 | 1 | 16.00 | $180.78 | $2,892.48 |
| | | M | 6 | 1 | 24.00 | $113.00 | $2,712.00 |
| | | M | 7 | 1 | 200.00 | $50.00 | $10,000.00 |
| | | M | 8 | 1 | 12.00 | $310.00 | $3,720.00 |
| | | M | 10 | 1 | 340.00 | $47.65 | $16,201.00 |
| | | M | 11 | 1 | 10.00 | $136.74 | $1,367.40 |
| | **Unit Sub Total** | **M** | | **7** | **618.00** | **$62.29** | **$38,492.88** |
| | **Item Code 151540 Total No. of Proj.** | | | **13** | | **Total Amount** | **$119,667.88** |
| **151554** | RECONSTRUCT CHAIN LINK GATE | EA | 7 | 1 | 1.00 | $1,100.00 | $1,100.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,100.00** | **$1,100.00** |
| | **Item Code 151554 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,100.00** |
| **151568** | RECONSTRUCT THRIE BEAM BARRIER | LF | 4 | 1 | 57,800.00 | $9.20 | $531,760.00 |
| | **Unit Sub Total** | **LF** | | **1** | **57,800.00** | **$9.20** | **$531,760.00** |
| | **Item Code 151568 Total No. of Proj.** | | | **1** | | **Total Amount** | **$531,760.00** |
| **151570** | RECONSTRUCT DOUBLE THRIE BEAM BARRIER | LF | 4 | 1 | 1,660.00 | $11.20 | $18,592.00 |
| | | LF | 5 | 1 | 300.00 | $43.00 | $12,900.00 |
| | **Unit Sub Total** | **LF** | | **2** | **1,960.00** | **$16.07** | **$31,492.00** |
| | **Item Code 151570 Total No. of Proj.** | | | **2** | | **Total Amount** | **$31,492.00** |
| **151572** | RECONSTRUCT METAL BEAM GUARD RAILING | LF | 1 | 4 | 22,470.00 | $13.94 | $313,152.50 |
| | | LF | 2 | 4 | 15,980.00 | $18.19 | $290,714.00 |
| | | LF | 3 | 3 | 5,848.00 | $20.25 | $118,405.00 |
| | | LF | 4 | 2 | 12,290.00 | $10.85 | $133,295.00 |
| | | LF | 5 | 1 | 14,800.00 | $17.00 | $251,600.00 |
| | | LF | 7 | 2 | 1,212.00 | $29.68 | $35,969.04 |
| | | LF | 11 | 2 | 207.00 | $30.91 | $6,399.00 |
| | | LF | 12 | 1 | 4,750.00 | $9.86 | $46,835.00 |
| | **Unit Sub Total** | **LF** | | **19** | **77,557.00** | **$15.43** | **$1,196,369.54** |
| **151572** | RECONSTRUCT METAL BEAM GUARD RAILING | M | 1 | 2 | 38.00 | $102.63 | $3,900.00 |
| | | M | 3 | 1 | 46.00 | $100.00 | $4,600.00 |
| | | M | 5 | 4 | 1,730.00 | $72.14 | $124,795.00 |
| | | M | 7 | 2 | 39.00 | $127.10 | $4,957.00 |
| | **Unit Sub Total** | **M** | | **9** | **1,853.00** | **$74.61** | **$138,252.00** |
| | **Item Code 151572 Total No. of Proj.** | | | **28** | | **Total Amount** | **$1,334,621.54** |
| **151623** | RECONSTRUCT METAL BEAM GUARD RAILING (7' POST) | LF | 1 | 2 | 660.00 | $22.77 | $15,030.00 |
| | | LF | 3 | 3 | 410.00 | $58.49 | $23,980.00 |
| | **Unit Sub Total** | **LF** | | **5** | **1,070.00** | **$36.46** | **$39,010.00** |
| | **Item Code 151623 Total No. of Proj.** | | | **5** | | **Total Amount** | **$39,010.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **151625** | RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST) | LF | 2 | 1 | 420.00 | $35.00 | $14,700.00 |
| | | LF | 3 | 4 | 495.00 | $40.81 | $20,200.00 |
| | **Unit Sub Total** | **LF** | | **5** | **915.00** | **$38.14** | **$34,900.00** |
| **151625** | RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST) | M | 4 | 2 | 900.00 | $63.33 | $57,000.00 |
| | | M | 7 | 2 | 3,360.00 | $55.38 | $186,080.00 |
| | **Unit Sub Total** | **M** | | **4** | **4,260.00** | **$57.06** | **$243,080.00** |
| | **Item Code 151625** | **Total No. of Proj.** | | **9** | | **Total Amount** | **$277,980.00** |
| **152037** | RELAY ENTRANCE TAPER AND PIPE DOWNDRAIN | EA | 3 | 1 | 9.00 | $3,000.00 | $27,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **9.00** | **$3,000.00** | **$27,000.00** |
| | **Item Code 152037** | **Total No. of Proj.** | | **1** | | **Total Amount** | **$27,000.00** |
| **152043** | RELAY METAL FLARED END SECTION | EA | 2 | 1 | 1.00 | $350.00 | $350.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$350.00** | **$350.00** |
| | **Item Code 152043** | **Total No. of Proj.** | | **1** | | **Total Amount** | **$350.00** |
| **152255** | RESET MAILBOX | EA | 3 | 1 | 7.00 | $200.00 | $1,400.00 |
| | | EA | 5 | 1 | 1.00 | $335.00 | $335.00 |
| | | EA | 6 | 1 | 6.00 | $290.00 | $1,740.00 |
| | | EA | 7 | 1 | 3.00 | $400.00 | $1,200.00 |
| | | EA | 8 | 1 | 7.00 | $350.00 | $2,450.00 |
| | | EA | 9 | 2 | 12.00 | $208.33 | $2,500.00 |
| | **Unit Sub Total** | **EA** | | **7** | **36.00** | **$267.36** | **$9,625.00** |
| | **Item Code 152255** | **Total No. of Proj.** | | **7** | | **Total Amount** | **$9,625.00** |
| **152291** | RESET GATE | EA | 1 | 1 | 1.00 | $750.00 | $750.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$750.00** | **$750.00** |
| | **Item Code 152291** | **Total No. of Proj.** | | **1** | | **Total Amount** | **$750.00** |
| **152299** | RESET MILEPOST MARKER | EA | 1 | 2 | 15.00 | $52.80 | $792.00 |
| | | EA | 5 | 2 | 11.00 | $22.82 | $251.00 |
| | | EA | 6 | 1 | 1.00 | $15.00 | $15.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **152299** | RESET MILEPOST MARKER | EA | 10 | 1 | 4.00 | $40.80 | $163.20 |
| | **Unit Sub Total** | **EA** | | **6** | **31.00** | **$39.39** | **$1,221.20** |
| | **Item Code 152299 Total No. of Proj.** | | | **6** | | **Total Amount** | **$1,221.20** |
| **152300** | RESET OBJECT MARKER | EA | 5 | 1 | 2.00 | $250.00 | $500.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$250.00** | **$500.00** |
| | **Item Code 152300 Total No. of Proj.** | | | **1** | | **Total Amount** | **$500.00** |
| **152301** | RESET MARKER | EA | 1 | 1 | 3.00 | $35.00 | $105.00 |
| | | EA | 3 | 1 | 1.00 | $100.00 | $100.00 |
| | **Unit Sub Total** | **EA** | | **2** | **4.00** | **$51.25** | **$205.00** |
| | **Item Code 152301 Total No. of Proj.** | | | **2** | | **Total Amount** | **$205.00** |
| **152303** | RESET MARKERS AND DELINEATORS | EA | 1 | 2 | 72.00 | $47.92 | $3,450.00 |
| | **Unit Sub Total** | **EA** | | **2** | **72.00** | **$47.92** | **$3,450.00** |
| | **Item Code 152303 Total No. of Proj.** | | | **2** | | **Total Amount** | **$3,450.00** |
| **152315** | RESET CRASH CUSHION | EA | 1 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | | EA | 4 | 1 | 1.00 | $250.00 | $250.00 |
| | **Unit Sub Total** | **EA** | | **2** | **2.00** | **$2,625.00** | **$5,250.00** |
| | **Item Code 152315 Total No. of Proj.** | | | **2** | | **Total Amount** | **$5,250.00** |
| **152316** | RESET ROADSIDE SIGN (ONE POST) | EA | 1 | 5 | 30.00 | $238.33 | $7,150.00 |
| | | EA | 4 | 1 | 1.00 | $250.00 | $250.00 |
| | | EA | 5 | 3 | 20.00 | $155.80 | $3,116.00 |
| | | EA | 6 | 1 | 1.00 | $70.00 | $70.00 |
| | | EA | 8 | 2 | 15.00 | $342.00 | $5,130.00 |
| | | EA | 9 | 1 | 1.00 | $150.00 | $150.00 |
| | **Unit Sub Total** | **EA** | | **13** | **68.00** | **$233.32** | **$15,866.00** |
| | **Item Code 152316 Total No. of Proj.** | | | **13** | | **Total Amount** | **$15,866.00** |
| **152317** | RESET ROADSIDE SIGN (TWO POST) | EA | 1 | 4 | 7.00 | $973.57 | $6,815.00 |
| | **Unit Sub Total** | **EA** | | **4** | **7.00** | **$973.57** | **$6,815.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 152317 Total No. of Proj.** | | | **4** | | **Total Amount** | **$6,815.00** |
| **152320** | RESET ROADSIDE SIGN | EA | 1 | 4 | 22.00 | $304.55 | $6,700.00 |
| | | EA | 2 | 5 | 28.00 | $467.86 | $13,100.00 |
| | | EA | 3 | 10 | 121.00 | $241.49 | $29,220.00 |
| | | EA | 4 | 4 | 26.00 | $191.15 | $4,970.00 |
| | | EA | 5 | 14 | 78.00 | $247.78 | $19,327.00 |
| | | EA | 6 | 5 | 84.00 | $164.17 | $13,790.00 |
| | | EA | 7 | 1 | 1.00 | $400.00 | $400.00 |
| | | EA | 8 | 2 | 7.00 | $141.43 | $990.00 |
| | | EA | 9 | 1 | 12.00 | $300.00 | $3,600.00 |
| | | EA | 10 | 5 | 16.00 | $156.44 | $2,503.00 |
| | | EA | 11 | 14 | 107.00 | $270.93 | $28,990.00 |
| | **Unit Sub Total** | **EA** | | **65** | **502.00** | **$246.20** | **$123,590.00** |
| | **Item Code 152320 Total No. of Proj.** | | | **65** | | **Total Amount** | **$123,590.00** |
| **152322** | RESET ROADSIDE SIGN (WOOD POST) | EA | 3 | 1 | 3.00 | $200.00 | $600.00 |
| | | EA | 6 | 1 | 5.00 | $200.00 | $1,000.00 |
| | **Unit Sub Total** | **EA** | | **2** | **8.00** | **$200.00** | **$1,600.00** |
| | **Item Code 152322 Total No. of Proj.** | | | **2** | | **Total Amount** | **$1,600.00** |
| **152329** | RESET STRUCTURE MOUNTED SIGN | EA | 2 | 1 | 1.00 | $600.00 | $600.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$600.00** | **$600.00** |
| | **Item Code 152329 Total No. of Proj.** | | | **1** | | **Total Amount** | **$600.00** |
| **152351** | RELOCATE HYDRANT | EA | 6 | 1 | 3.00 | $4,660.00 | $13,980.00 |
| | | EA | 11 | 1 | 2.00 | $6,500.00 | $13,000.00 |
| | **Unit Sub Total** | **EA** | | **2** | **5.00** | **$5,396.00** | **$26,980.00** |
| | **Item Code 152351 Total No. of Proj.** | | | **2** | | **Total Amount** | **$26,980.00** |
| **152370** | RELOCATE MAILBOX | EA | 2 | 1 | 1.00 | $500.00 | $500.00 |
| | | EA | 5 | 1 | 26.00 | $230.00 | $5,980.00 |
| | | EA | 6 | 1 | 61.00 | $524.00 | $31,964.00 |
| | | EA | 10 | 1 | 8.00 | $310.00 | $2,480.00 |
| | **Unit Sub Total** | **EA** | | **4** | **96.00** | **$426.29** | **$40,924.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 152370 Total No. of Proj.** | | | **4** | | **Total Amount** | **$40,924.00** |
| **152372** | RELOCATE CONCRETE BARRIER (TYPE K) | LF | 4 | 1 | 160.00 | $5.00 | $800.00 |
| | **Unit Sub Total** | **LF** | | **1** | **160.00** | **$5.00** | **$800.00** |
| **152372** | RELOCATE CONCRETE BARRIER (TYPE K) | M | 7 | 1 | 1,180.00 | $16.00 | $18,880.00 |
| | **Unit Sub Total** | **M** | | **1** | **1,180.00** | **$16.00** | **$18,880.00** |
| | **Item Code 152372 Total No. of Proj.** | | | **2** | | **Total Amount** | **$19,680.00** |
| **152379** | RELOCATE FENCE | M | 1 | 1 | 45.00 | $31.00 | $1,395.00 |
| | | M | 6 | 2 | 400.00 | $25.65 | $10,260.00 |
| | **Unit Sub Total** | **M** | | **3** | **445.00** | **$26.19** | **$11,655.00** |
| | **Item Code 152379 Total No. of Proj.** | | | **3** | | **Total Amount** | **$11,655.00** |
| **152381** | RELOCATE GATE | EA | 1 | 1 | 1.00 | $750.00 | $750.00 |
| | | EA | 3 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | | EA | 4 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | **Unit Sub Total** | **EA** | | **3** | **3.00** | **$916.67** | **$2,750.00** |
| | **Item Code 152381 Total No. of Proj.** | | | **3** | | **Total Amount** | **$2,750.00** |
| **152385** | RELOCATE MARKER | EA | 5 | 1 | 2.00 | $90.00 | $180.00 |
| | | EA | 10 | 1 | 3.00 | $25.90 | $77.70 |
| | **Unit Sub Total** | **EA** | | **2** | **5.00** | **$51.54** | **$257.70** |
| | **Item Code 152385 Total No. of Proj.** | | | **2** | | **Total Amount** | **$257.70** |
| **152386** | RELOCATE ROADSIDE SIGN-ONE POST | EA | 1 | 1 | 12.00 | $210.00 | $2,520.00 |
| | | EA | 4 | 2 | 17.00 | $205.88 | $3,500.00 |
| | | EA | 5 | 2 | 2.00 | $212.50 | $425.00 |
| | | EA | 7 | 1 | 2.00 | $200.00 | $400.00 |
| | | EA | 8 | 1 | 3.00 | $90.00 | $270.00 |
| | | EA | 10 | 1 | 1.00 | $250.00 | $250.00 |
| | | EA | 12 | 3 | 14.00 | $248.14 | $3,474.00 |
| | **Unit Sub Total** | **EA** | | **11** | **51.00** | **$212.53** | **$10,839.00** |
| | **Item Code 152386 Total No. of Proj.** | | | **11** | | **Total Amount** | **$10,839.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **152387** | RELOCATE ROADSIDE SIGN-TWO POST | EA | 1 | 2 | 5.00 | $1,368.00 | $6,840.00 |
| | | EA | 4 | 2 | 11.00 | $293.18 | $3,225.00 |
| | | EA | 5 | 1 | 1.00 | $350.00 | $350.00 |
| | | EA | 6 | 1 | 1.00 | $400.00 | $400.00 |
| | | EA | 7 | 1 | 3.00 | $450.00 | $1,350.00 |
| | **Unit Sub Total** | **EA** | | **7** | **21.00** | **$579.29** | **$12,165.00** |
| | **Item Code 152387 Total No. of Proj.** | | | **7** | | **Total Amount** | **$12,165.00** |
| **152390** | RELOCATE ROADSIDE SIGN | EA | 1 | 4 | 9.00 | $337.22 | $3,035.00 |
| | | EA | 2 | 5 | 10.00 | $276.00 | $2,760.00 |
| | | EA | 3 | 9 | 72.00 | $244.86 | $17,630.00 |
| | | EA | 4 | 5 | 83.00 | $184.33 | $15,299.50 |
| | | EA | 5 | 7 | 176.00 | $219.96 | $38,712.87 |
| | | EA | 6 | 6 | 31.00 | $84.13 | $2,608.00 |
| | | EA | 7 | 2 | 2.00 | $326.50 | $653.00 |
| | | EA | 8 | 4 | 25.00 | $263.60 | $6,590.00 |
| | | EA | 9 | 1 | 77.00 | $100.00 | $7,700.00 |
| | | EA | 10 | 8 | 76.00 | $227.51 | $17,290.60 |
| | | EA | 11 | 12 | 140.00 | $292.18 | $40,905.00 |
| | **Unit Sub Total** | **EA** | | **63** | **701.00** | **$218.52** | **$153,183.97** |
| | **Item Code 152390 Total No. of Proj.** | | | **63** | | **Total Amount** | **$153,183.97** |
| **152391** | RELOCATE ROADSIDE SIGN (METAL POST) | EA | 7 | 1 | 6.00 | $200.00 | $1,200.00 |
| | | EA | 8 | 1 | 1.00 | $200.00 | $200.00 |
| | **Unit Sub Total** | **EA** | | **2** | **7.00** | **$200.00** | **$1,400.00** |
| | **Item Code 152391 Total No. of Proj.** | | | **2** | | **Total Amount** | **$1,400.00** |
| **152392** | RELOCATE ROADSIDE SIGN (WOOD POST) | EA | 1 | 1 | 2.00 | $225.00 | $450.00 |
| | | EA | 4 | 2 | 75.00 | $137.60 | $10,320.00 |
| | | EA | 7 | 1 | 1.00 | $150.00 | $150.00 |
| | **Unit Sub Total** | **EA** | | **4** | **78.00** | **$140.00** | **$10,920.00** |
| | **Item Code 152392 Total No. of Proj.** | | | **4** | | **Total Amount** | **$10,920.00** |
| **152393** | RELOCATE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD) | EA | 4 | 3 | 45.00 | $97.22 | $4,375.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **152393** | RELOCATE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD) | EA | 12 | 1 | 2.00 | $90.00 | $180.00 |
| | **Unit Sub Total** | **EA** | | **4** | **47.00** | **$96.91** | **$4,555.00** |
| | **Item Code 152393 Total No. of Proj.** | | | **4** | | **Total Amount** | **$4,555.00** |
| **152394** | RELOCATE SIGN STRUCTURE | EA | 3 | 2 | 3.00 | $8,726.67 | $26,180.00 |
| | | EA | 4 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | | EA | 6 | 1 | 1.00 | $14,000.00 | $14,000.00 |
| | | EA | 11 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | | EA | 12 | 1 | 1.00 | $17,000.00 | $17,000.00 |
| | **Unit Sub Total** | **EA** | | **6** | **7.00** | **$9,597.14** | **$67,180.00** |
| | **Item Code 152394 Total No. of Proj.** | | | **6** | | **Total Amount** | **$67,180.00** |
| **152396** | RELOCATE SIGN PANEL | EA | 2 | 1 | 2.00 | $200.00 | $400.00 |
| | | EA | 11 | 1 | 2.00 | $1,000.00 | $2,000.00 |
| | **Unit Sub Total** | **EA** | | **2** | **4.00** | **$600.00** | **$2,400.00** |
| | **Item Code 152396 Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,400.00** |
| **152400** | ADJUST SEWER CLEANOUT TO GRADE | EA | 1 | 1 | 1.00 | $750.00 | $750.00 |
| | | EA | 12 | 2 | 23.00 | $284.57 | $6,545.00 |
| | **Unit Sub Total** | **EA** | | **3** | **24.00** | **$303.96** | **$7,295.00** |
| | **Item Code 152400 Total No. of Proj.** | | | **3** | | **Total Amount** | **$7,295.00** |
| **152402** | ADJUST WATER VALVE COVER TO GRADE | EA | 1 | 4 | 49.00 | $402.65 | $19,730.00 |
| | | EA | 2 | 1 | 5.00 | $900.00 | $4,500.00 |
| | | EA | 3 | 1 | 47.00 | $350.00 | $16,450.00 |
| | | EA | 4 | 1 | 27.00 | $350.00 | $9,450.00 |
| | | EA | 5 | 2 | 8.00 | $325.00 | $2,600.00 |
| | | EA | 6 | 1 | 13.00 | $350.00 | $4,550.00 |
| | | EA | 7 | 2 | 135.00 | $236.11 | $31,875.00 |
| | | EA | 8 | 1 | 5.00 | $575.00 | $2,875.00 |
| | | EA | 9 | 1 | 20.00 | $600.00 | $12,000.00 |
| | | EA | 10 | 1 | 29.00 | $560.00 | $16,240.00 |
| | | EA | 12 | 3 | 189.00 | $269.35 | $50,907.00 |
| | **Unit Sub Total** | **EA** | | **18** | **527.00** | **$324.81** | **$171,177.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 152402 Total No. of Proj.** | | | **18** | | **Total Amount** | **$171,177.00** |
| **152403** | ADJUST WATER METER BOX TO GRADE | EA | 1 | 1 | 5.00 | $410.00 | $2,050.00 |
| | | EA | 5 | 1 | 5.00 | $675.00 | $3,375.00 |
| | | EA | 9 | 1 | 13.00 | $300.00 | $3,900.00 |
| | **Unit Sub Total** | **EA** | | **3** | **23.00** | **$405.43** | **$9,325.00** |
| | **Item Code 152403 Total No. of Proj.** | | | **3** | | **Total Amount** | **$9,325.00** |
| **152410** | RELOCATE WATER METER | EA | 5 | 1 | 15.00 | $1,000.00 | $15,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **15.00** | **$1,000.00** | **$15,000.00** |
| | **Item Code 152410 Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,000.00** |
| **152422** | ADJUST MONUMENT COVER | EA | 2 | 1 | 1.00 | $900.00 | $900.00 |
| | | EA | 6 | 2 | 2.00 | $650.00 | $1,300.00 |
| | **Unit Sub Total** | **EA** | | **3** | **3.00** | **$733.33** | **$2,200.00** |
| | **Item Code 152422 Total No. of Proj.** | | | **3** | | **Total Amount** | **$2,200.00** |
| **152423** | ADJUST MONUMENT TO GRADE | EA | 6 | 3 | 35.00 | $453.43 | $15,870.00 |
| | | EA | 7 | 1 | 2.00 | $225.00 | $450.00 |
| | **Unit Sub Total** | **EA** | | **4** | **37.00** | **$441.08** | **$16,320.00** |
| | **Item Code 152423 Total No. of Proj.** | | | **4** | | **Total Amount** | **$16,320.00** |
| **152430** | ADJUST INLET | EA | 1 | 7 | 47.00 | $1,310.64 | $61,600.00 |
| | | EA | 3 | 3 | 166.00 | $1,385.54 | $230,000.00 |
| | | EA | 4 | 9 | 125.00 | $1,304.88 | $163,110.00 |
| | | EA | 5 | 8 | 80.00 | $2,375.02 | $190,001.50 |
| | | EA | 7 | 3 | 54.00 | $2,185.70 | $118,028.00 |
| | | EA | 8 | 1 | 18.00 | $1,300.00 | $23,400.00 |
| | | EA | 9 | 2 | 19.00 | $2,534.21 | $48,150.00 |
| | | EA | 10 | 1 | 1.00 | $835.00 | $835.00 |
| | | EA | 11 | 2 | 5.00 | $2,040.00 | $10,200.00 |
| | **Unit Sub Total** | **EA** | | **36** | **515.00** | **$1,641.41** | **$845,324.50** |
| | **Item Code 152430 Total No. of Proj.** | | | **36** | | **Total Amount** | **$845,324.50** |
| **152432** | ADJUST MANHOLE | EA | 7 | 1 | 11.00 | $800.00 | $8,800.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **1** | **11.00** | **$800.00** | **$8,800.00** |
| | **Item Code 152432** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$8,800.00** |
| **152434** | ADJUST RISER | | EA | 2 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,000.00** | **$1,000.00** |
| | **Item Code 152434** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,000.00** |
| **152436** | ADJUST DOWNDRAIN | | EA | 3 | 1 | 1.00 | $1,800.00 | $1,800.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,800.00** | **$1,800.00** |
| | **Item Code 152436** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,800.00** |
| **152438** | ADJUST FRAME AND COVER TO GRADE | | EA | 1 | 5 | 91.00 | $453.85 | $41,300.00 |
| | | | EA | 4 | 3 | 5.00 | $580.00 | $2,900.00 |
| | | | EA | 5 | 1 | 3.00 | $775.00 | $2,325.00 |
| | | | EA | 9 | 4 | 133.00 | $619.55 | $82,400.00 |
| | | | EA | 10 | 5 | 73.00 | $509.59 | $37,200.00 |
| | | | EA | 11 | 2 | 6.00 | $1,400.00 | $8,400.00 |
| | | **Unit Sub Total** | **EA** | | **20** | **311.00** | **$561.17** | **$174,525.00** |
| | **Item Code 152438** | **Total No. of Proj.** | | | **20** | | **Total Amount** | **$174,525.00** |
| **152439** | ADJUST FRAME AND GRATE TO GRADE | | EA | 1 | 1 | 1.00 | $4,000.00 | $4,000.00 |
| | | | EA | 4 | 2 | 16.00 | $578.13 | $9,250.00 |
| | | | EA | 6 | 2 | 17.00 | $1,371.18 | $23,310.00 |
| | | | EA | 11 | 1 | 24.00 | $2,000.00 | $48,000.00 |
| | | **Unit Sub Total** | **EA** | | **6** | **58.00** | **$1,457.93** | **$84,560.00** |
| | **Item Code 152439** | **Total No. of Proj.** | | | **6** | | **Total Amount** | **$84,560.00** |
| **152440** | ADJUST MANHOLE TO GRADE | | EA | 1 | 2 | 9.00 | $633.33 | $5,700.00 |
| | | | EA | 2 | 2 | 10.00 | $604.00 | $6,040.00 |
| | | | EA | 3 | 2 | 143.00 | $608.39 | $87,000.00 |
| | | | EA | 5 | 2 | 12.00 | $752.50 | $9,030.00 |
| | | | EA | 6 | 3 | 44.00 | $899.77 | $39,590.00 |
| | | | EA | 7 | 8 | 225.00 | $446.12 | $100,376.20 |
| | | | EA | 10 | 2 | 51.00 | $561.76 | $28,650.00 |
| | | | EA | 12 | 5 | 144.00 | $344.36 | $49,588.28 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **26** | **638.00** | **$510.93** | **$325,974.48** |
| | **Item Code 152440** | **Total No. of Proj.** | | | **26** | | **Total Amount** | **$325,974.48** |
| **152451** | ADJUST WATER VALVE | | EA | 5 | 1 | 160.00 | $675.00 | $108,000.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **160.00** | **$675.00** | **$108,000.00** |
| | **Item Code 152451** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$108,000.00** |
| **152452** | ADJUST WATER VALVE COVER | | EA | 12 | 1 | 3.00 | $700.00 | $2,100.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **3.00** | **$700.00** | **$2,100.00** |
| | **Item Code 152452** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,100.00** |
| **152453** | ADJUST VALVE BOX | | EA | 1 | 1 | 3.00 | $525.00 | $1,575.00 |
| | | | EA | 2 | 2 | 7.00 | $164.29 | $1,150.00 |
| | | | EA | 10 | 1 | 32.00 | $240.00 | $7,680.00 |
| | | **Unit Sub Total** | **EA** | | **4** | **42.00** | **$247.74** | **$10,405.00** |
| | **Item Code 152453** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$10,405.00** |
| **152469** | ADJUST UTILITY COVER TO GRADE | | EA | 2 | 1 | 67.00 | $400.00 | $26,800.00 |
| | | | EA | 3 | 1 | 3.00 | $500.00 | $1,500.00 |
| | | | EA | 4 | 2 | 27.00 | $332.59 | $8,980.00 |
| | | | EA | 5 | 1 | 3.00 | $400.00 | $1,200.00 |
| | | **Unit Sub Total** | **EA** | | **5** | **100.00** | **$384.80** | **$38,480.00** |
| | **Item Code 152469** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$38,480.00** |
| **152475** | ADJUST SEWER MANHOLE | | EA | 9 | 1 | 2.00 | $500.00 | $1,000.00 |
| | | | EA | 11 | 1 | 3.00 | $2,000.00 | $6,000.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **5.00** | **$1,400.00** | **$7,000.00** |
| | **Item Code 152475** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$7,000.00** |
| **152500** | ADJUST METAL BEAM GUARD RAILING | | LF | 1 | 1 | 480.00 | $15.00 | $7,200.00 |
| | | | LF | 2 | 1 | 28,500.00 | $3.75 | $106,875.00 |
| | | | LF | 3 | 2 | 4,910.00 | $6.41 | $31,480.00 |
| | | | LF | 4 | 1 | 2,160.00 | $7.00 | $15,120.00 |
| | | | LF | 9 | 4 | 12,600.00 | $5.07 | $63,896.50 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **152500** | ADJUST METAL BEAM GUARD RAILING | LF | 12 | 1 | 1,620.00 | $7.10 | $11,502.00 |
| | **Unit Sub Total** | **LF** | | **10** | **50,270.00** | **$4.70** | **$236,073.50** |
| | **Item Code 152500 Total No. of Proj.** | | | **10** | | **Total Amount** | **$236,073.50** |
| **152555** | ADJUST SLOTTED DRAIN TO GRADE | LF | 1 | 1 | 140.00 | $85.00 | $11,900.00 |
| | | LF | 11 | 1 | 55.00 | $200.00 | $11,000.00 |
| | **Unit Sub Total** | **LF** | | **2** | **195.00** | **$117.44** | **$22,900.00** |
| **152555** | ADJUST SLOTTED DRAIN TO GRADE | M | 5 | 1 | 210.00 | $153.00 | $32,130.00 |
| | **Unit Sub Total** | **M** | | **1** | **210.00** | **$153.00** | **$32,130.00** |
| | **Item Code 152555 Total No. of Proj.** | | | **3** | | **Total Amount** | **$55,030.00** |
| **152602** | MODIFY HEADWALL | EA | 6 | 1 | 2.00 | $4,800.00 | $9,600.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$4,800.00** | **$9,600.00** |
| | **Item Code 152602 Total No. of Proj.** | | | **1** | | **Total Amount** | **$9,600.00** |
| **152604** | MODIFY INLET | EA | 2 | 2 | 4.00 | $6,487.50 | $25,950.00 |
| | | EA | 3 | 1 | 1.00 | $3,500.00 | $3,500.00 |
| | | EA | 4 | 3 | 23.00 | $1,913.04 | $44,000.00 |
| | | EA | 7 | 4 | 21.00 | $3,914.29 | $82,200.00 |
| | | EA | 11 | 2 | 7.00 | $2,357.14 | $16,500.00 |
| | **Unit Sub Total** | **EA** | | **12** | **56.00** | **$3,074.11** | **$172,150.00** |
| | **Item Code 152604 Total No. of Proj.** | | | **12** | | **Total Amount** | **$172,150.00** |
| **152609** | MODIFY INLET TO MANHOLE | EA | 4 | 2 | 2.00 | $1,706.35 | $3,412.70 |
| | **Unit Sub Total** | **EA** | | **2** | **2.00** | **$1,706.35** | **$3,412.70** |
| | **Item Code 152609 Total No. of Proj.** | | | **2** | | **Total Amount** | **$3,412.70** |
| **152610** | MODIFY MANHOLE | EA | 2 | 1 | 1.00 | $3,350.00 | $3,350.00 |
| | | EA | 3 | 1 | 14.00 | $2,300.00 | $32,200.00 |
| | | EA | 11 | 1 | 2.00 | $3,900.00 | $7,800.00 |
| | **Unit Sub Total** | **EA** | | **3** | **17.00** | **$2,550.00** | **$43,350.00** |
| | **Item Code 152610 Total No. of Proj.** | | | **3** | | **Total Amount** | **$43,350.00** |
| **152632** | MODIFY METAL BEAM GUARD RAILING | LF | 2 | 1 | 2,170.00 | $15.00 | $32,550.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **LF** | | **1** | **2,170.00** | **$15.00** | **$32,550.00** |
| | **Item Code 152632** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$32,550.00** |
| **152641** | MODIFY SIGN STRUCTURE | | EA | 11 | 3 | 5.00 | $2,480.00 | $12,400.00 |
| | | **Unit Sub Total** | **EA** | | **3** | **5.00** | **$2,480.00** | **$12,400.00** |
| | **Item Code 152641** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$12,400.00** |
| **152661** | PLASTIC PIPE LINER (16.00" O.D.) | | LF | 3 | 1 | 330.00 | $168.00 | $55,440.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **330.00** | **$168.00** | **$55,440.00** |
| | **Item Code 152661** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$55,440.00** |
| **152664** | PLASTIC PIPE LINER (21.50" O.D.) | | LF | 3 | 2 | 1,220.00 | $244.51 | $298,300.00 |
| | | **Unit Sub Total** | **LF** | | **2** | **1,220.00** | **$244.51** | **$298,300.00** |
| | **Item Code 152664** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$298,300.00** |
| **152666** | 400 MM PLASTIC PIPE-LINER | | M | 3 | 1 | 50.00 | $1,100.00 | $55,000.00 |
| | | **Unit Sub Total** | **M** | | **1** | **50.00** | **$1,100.00** | **$55,000.00** |
| | **Item Code 152666** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$55,000.00** |
| **152667** | 500 MM PLASTIC PIPE-LINER | | M | 12 | 1 | 82.00 | $225.00 | $18,450.00 |
| | | **Unit Sub Total** | **M** | | **1** | **82.00** | **$225.00** | **$18,450.00** |
| | **Item Code 152667** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$18,450.00** |
| **152668** | 525 MM PLASTIC PIPE-LINER | | M | 3 | 1 | 76.00 | $1,350.00 | $102,600.00 |
| | | | M | 4 | 1 | 120.00 | $515.00 | $61,800.00 |
| | | **Unit Sub Total** | **M** | | **2** | **196.00** | **$838.78** | **$164,400.00** |
| | **Item Code 152668** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$164,400.00** |
| **152703** | REMODEL INLET | | EA | 4 | 1 | 5.00 | $1,693.20 | $8,466.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **5.00** | **$1,693.20** | **$8,466.00** |
| | **Item Code 152703** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$8,466.00** |
| **153103** | COLD PLANE ASPHALT CONCRETE PAVEMENT | | M2 | 1 | 7 | 32,672.00 | $5.08 | $166,135.00 |
| | | | M2 | 2 | 5 | 32,850.00 | $5.20 | $170,765.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **153103** | COLD PLANE ASPHALT CONCRETE PAVEMENT | M2 | 3 | 7 | 414,810.00 | $1.89 | $784,770.00 |
| | | M2 | 4 | 12 | 353,150.00 | $1.94 | $685,531.00 |
| | | M2 | 5 | 9 | 373,214.00 | $1.66 | $619,508.00 |
| | | M2 | 6 | 7 | 237,180.00 | $1.01 | $239,384.00 |
| | | M2 | 7 | 7 | 143,800.00 | $1.92 | $275,536.00 |
| | | M2 | 8 | 3 | 164,970.00 | $2.48 | $409,411.50 |
| | | M2 | 9 | 4 | 199,940.00 | $2.51 | $502,611.00 |
| | | M2 | 10 | 8 | 156,222.00 | $1.41 | $220,658.00 |
| | | M2 | 11 | 10 | 68,040.00 | $6.45 | $438,520.00 |
| | | M2 | 12 | 4 | 11,680.00 | $3.76 | $43,925.00 |
| | **Unit Sub Total** | **M2** | | **83** | **2,188,528.00** | **$2.08** | **$4,556,754.50** |
| **153103** | COLD PLANE ASPHALT CONCRETE PAVEMENT | SQFT | 1 | 1 | 4,950.00 | $4.00 | $19,800.00 |
| | | SQFT | 2 | 1 | 4,800.00 | $1.00 | $4,800.00 |
| | | SQFT | 5 | 1 | 25,700.00 | $1.00 | $25,700.00 |
| | | SQFT | 7 | 1 | 173,900.00 | $0.14 | $24,346.00 |
| | | SQFT | 10 | 1 | 108,000.00 | $0.16 | $17,280.00 |
| | **Unit Sub Total** | **SQFT** | | **5** | **317,350.00** | **$0.29** | **$91,926.00** |
| **153103** | COLD PLANE ASPHALT CONCRETE PAVEMENT | SQYD | 1 | 17 | 454,460.00 | $1.39 | $632,345.00 |
| | | SQYD | 2 | 17 | 844,170.00 | $0.98 | $826,267.00 |
| | | SQYD | 3 | 22 | 155,022.00 | $3.58 | $554,918.50 |
| | | SQYD | 4 | 17 | 341,350.00 | $2.93 | $1,000,049.10 |
| | | SQYD | 5 | 7 | 67,110.00 | $3.01 | $202,210.00 |
| | | SQYD | 6 | 14 | 222,457.00 | $1.55 | $345,797.00 |
| | | SQYD | 7 | 13 | 583,528.00 | $1.46 | $851,880.00 |
| | | SQYD | 8 | 14 | 2,029,490.00 | $0.67 | $1,352,306.80 |
| | | SQYD | 9 | 6 | 50,150.00 | $5.31 | $266,220.00 |
| | | SQYD | 10 | 11 | 162,010.00 | $2.05 | $331,913.50 |
| | | SQYD | 11 | 11 | 138,900.00 | $3.08 | $428,312.10 |
| | | SQYD | 12 | 10 | 297,370.00 | $1.90 | $565,760.00 |
| | **Unit Sub Total** | **SQYD** | | **159** | **5,346,017.00** | **$1.38** | **$7,357,979.00** |
| | **Item Code 153103** | **Total No. of Proj.** | | **247** | | **Total Amount** | **$12,006,659.50** |
| **153109** | COLD PLANE ASPHALT CONCRETE PAVEMENT (.08' MAXIMUM) | SQYD | 3 | 1 | 277,000.00 | $0.85 | $235,450.00 |
| | **Unit Sub Total** | **SQYD** | | **1** | **277,000.00** | **$0.85** | **$235,450.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 153109 Total No. of Proj.** | | | **1** | | **Total Amount** | **$235,450.00** |
| **153110** | COLD PLANE ASPHALT CONCRETE PAVEMENT (.10' MAXIMUM) | SQFT | 4 | 1 | 5,560.00 | $3.50 | $19,460.00 |
| | | SQFT | 10 | 1 | 9,970.00 | $0.88 | $8,773.60 |
| | **Unit Sub Total** | **SQFT** | | **2** | **15,530.00** | **$1.82** | **$28,233.60** |
| | **Item Code 153110 Total No. of Proj.** | | | **2** | | **Total Amount** | **$28,233.60** |
| **153112** | COLD PLANE ASPHALT CONCRETE PAVEMENT (.15' MAXIMUM) | SQYD | 3 | 1 | 29,100.00 | $1.97 | $57,327.00 |
| | **Unit Sub Total** | **SQYD** | | **1** | **29,100.00** | **$1.97** | **$57,327.00** |
| | **Item Code 153112 Total No. of Proj.** | | | **1** | | **Total Amount** | **$57,327.00** |
| **153151** | COLD PLANE ASPHALT CONCRETE PAVEMENT (25 MM MAXIMUM) | M2 | 3 | 1 | 14,200.00 | $2.00 | $28,400.00 |
| | **Unit Sub Total** | **M2** | | **1** | **14,200.00** | **$2.00** | **$28,400.00** |
| | **Item Code 153151 Total No. of Proj.** | | | **1** | | **Total Amount** | **$28,400.00** |
| **153152** | COLD PLANE ASPHALT CONCRETE PAVEMENT (30 MM MAXIMUM) | M2 | 4 | 1 | 19,300.00 | $1.25 | $24,125.00 |
| | **Unit Sub Total** | **M2** | | **1** | **19,300.00** | **$1.25** | **$24,125.00** |
| | **Item Code 153152 Total No. of Proj.** | | | **1** | | **Total Amount** | **$24,125.00** |
| **153210** | REMOVE CONCRETE | CY | 2 | 3 | 33.90 | $392.04 | $13,290.00 |
| | | CY | 3 | 2 | 53.00 | $265.66 | $14,080.00 |
| | | CY | 4 | 3 | 80.90 | $694.68 | $56,200.00 |
| | | CY | 5 | 1 | 18.00 | $175.00 | $3,150.00 |
| | | CY | 6 | 3 | 1,390.00 | $86.01 | $119,550.00 |
| | | CY | 7 | 3 | 93.00 | $300.86 | $27,980.00 |
| | | CY | 8 | 2 | 34.00 | $245.88 | $8,360.00 |
| | | CY | 10 | 1 | 3.00 | $350.00 | $1,050.00 |
| | | CY | 11 | 6 | 395.20 | $152.13 | $60,120.00 |
| | | CY | 12 | 7 | 247.00 | $224.09 | $55,350.00 |
| | **Unit Sub Total** | **CY** | | **31** | **2,348.00** | **$152.95** | **$359,130.00** |
| **153210** | REMOVE CONCRETE | M3 | 2 | 3 | 219.00 | $153.11 | $33,531.38 |
| | | M3 | 3 | 3 | 234.00 | $71.24 | $16,670.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **153210** | REMOVE CONCRETE | | M3 | 4 | 5 | 196.00 | $139.25 | $27,293.00 |
| | | | M3 | 5 | 2 | 133.00 | $66.17 | $8,800.00 |
| | | | M3 | 6 | 3 | 4,519.00 | $73.97 | $334,252.00 |
| | | | M3 | 7 | 5 | 685.00 | $140.65 | $96,345.00 |
| | | | M3 | 8 | 1 | 3.00 | $350.00 | $1,050.00 |
| | | | M3 | 9 | 2 | 402.00 | $148.51 | $59,700.00 |
| | | | M3 | 10 | 2 | 385.00 | $234.03 | $90,100.00 |
| | | | M3 | 11 | 4 | 1,302.00 | $39.02 | $50,810.00 |
| | | **Unit Sub Total** | **M3** | | **30** | **8,078.00** | **$88.95** | **$718,551.38** |
| **153210** | REMOVE CONCRETE | | SQFT | 8 | 1 | 1,640.00 | $3.30 | $5,412.00 |
| | | **Unit Sub Total** | **SQFT** | | **1** | **1,640.00** | **$3.30** | **$5,412.00** |
| | **Item Code 153210** | **Total No. of Proj.** | | | **62** | | **Total Amount** | **$1,083,093.38** |
| **153213** | REMOVE CONCRETE (STRUCTURE) | | CY | 1 | 1 | 6.00 | $335.00 | $2,010.00 |
| | | **Unit Sub Total** | **CY** | | **1** | **6.00** | **$335.00** | **$2,010.00** |
| **153213** | REMOVE CONCRETE (STRUCTURE) | | M3 | 5 | 1 | 150.00 | $320.00 | $48,000.00 |
| | | | M3 | 7 | 1 | 65.00 | $315.00 | $20,475.00 |
| | | **Unit Sub Total** | **M3** | | **2** | **215.00** | **$318.49** | **$68,475.00** |
| | **Item Code 153213** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$70,485.00** |
| **153214** | REMOVE CONCRETE CURB | | CY | 4 | 1 | 200.00 | $80.00 | $16,000.00 |
| | | **Unit Sub Total** | **CY** | | **1** | **200.00** | **$80.00** | **$16,000.00** |
| **153214** | REMOVE CONCRETE CURB | | LF | 1 | 1 | 160.00 | $13.00 | $2,080.00 |
| | | | LF | 3 | 1 | 720.00 | $6.00 | $4,320.00 |
| | | | LF | 5 | 1 | 300.00 | $23.00 | $6,900.00 |
| | | | LF | 6 | 1 | 130.00 | $12.88 | $1,674.40 |
| | | | LF | 8 | 1 | 230.00 | $5.00 | $1,150.00 |
| | | | LF | 12 | 2 | 1,060.00 | $17.02 | $18,040.00 |
| | | **Unit Sub Total** | **LF** | | **7** | **2,600.00** | **$13.14** | **$34,164.40** |
| **153214** | REMOVE CONCRETE CURB | | M | 3 | 1 | 180.00 | $30.00 | $5,400.00 |
| | | | M | 4 | 2 | 1,120.00 | $18.93 | $21,200.00 |
| | | | M | 6 | 1 | 110.00 | $21.00 | $2,310.00 |
| | | | M | 7 | 6 | 6,089.00 | $17.01 | $103,560.00 |
| | | | M | 11 | 1 | 70.00 | $25.00 | $1,750.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **153214** | REMOVE CONCRETE CURB | M | 12 | 1 | 15.00 | $115.00 | $1,725.00 |
| | **Unit Sub Total** | **M** | | **12** | **7,584.00** | **$17.93** | **$135,945.00** |
| **153214** | REMOVE CONCRETE CURB | M3 | 12 | 1 | 16.00 | $170.00 | $2,720.00 |
| | **Unit Sub Total** | **M3** | | **1** | **16.00** | **$170.00** | **$2,720.00** |
| | **Item Code 153214 Total No. of Proj.** | | | **21** | | **Total Amount** | **$188,829.40** |
| **153215** | REMOVE CONCRETE (CURB AND GUTTER) | LF | 3 | 1 | 340.00 | $10.00 | $3,400.00 |
| | | LF | 5 | 1 | 1,130.00 | $19.05 | $21,526.50 |
| | | LF | 7 | 1 | 9,170.00 | $6.00 | $55,020.00 |
| | | LF | 8 | 2 | 317.00 | $15.87 | $5,030.50 |
| | | LF | 12 | 1 | 390.00 | $17.50 | $6,825.00 |
| | **Unit Sub Total** | **LF** | | **6** | **11,347.00** | **$8.09** | **$91,802.00** |
| **153215** | REMOVE CONCRETE (CURB AND GUTTER) | M | 3 | 2 | 1,952.00 | $11.08 | $21,620.00 |
| | | M | 4 | 1 | 16.00 | $130.00 | $2,080.00 |
| | | M | 5 | 2 | 2,690.00 | $34.57 | $93,000.00 |
| | | M | 7 | 1 | 15,000.00 | $18.00 | $270,000.00 |
| | **Unit Sub Total** | **M** | | **6** | **19,658.00** | **$19.67** | **$386,700.00** |
| **153215** | REMOVE CONCRETE (CURB AND GUTTER) | M3 | 4 | 1 | 16.00 | $30.00 | $480.00 |
| | | M3 | 7 | 1 | 36.00 | $92.00 | $3,312.00 |
| | **Unit Sub Total** | **M3** | | **2** | **52.00** | **$72.92** | **$3,792.00** |
| | **Item Code 153215 Total No. of Proj.** | | | **14** | | **Total Amount** | **$482,294.00** |
| **153216** | REMOVE CONCRETE CURB AND SIDEWALK | CY | 8 | 3 | 68.00 | $157.65 | $10,720.00 |
| | | CY | 10 | 1 | 41.00 | $135.00 | $5,535.00 |
| | | CY | 12 | 1 | 9.00 | $340.00 | $3,060.00 |
| | **Unit Sub Total** | **CY** | | **5** | **118.00** | **$163.69** | **$19,315.00** |
| **153216** | REMOVE CONCRETE CURB AND SIDEWALK | M | 11 | 2 | 1,260.00 | $22.21 | $27,980.00 |
| | **Unit Sub Total** | **M** | | **2** | **1,260.00** | **$22.21** | **$27,980.00** |
| **153216** | REMOVE CONCRETE CURB AND SIDEWALK | M3 | 5 | 1 | 1.90 | $7,600.00 | $14,440.00 |
| | | M3 | 8 | 1 | 60.00 | $262.00 | $15,720.00 |
| | | M3 | 10 | 1 | 29.00 | $225.00 | $6,525.00 |
| | **Unit Sub Total** | **M3** | | **3** | **90.90** | **$403.58** | **$36,685.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | **Item Code 153216** | **Total No. of Proj.** | | | **10** | | **Total Amount** | **$83,980.00** |
| **153218** | REMOVE CONCRETE SIDEWALK | | CY | 7 | 1 | 170.00 | $231.00 | $39,270.00 |
| | | | CY | 8 | 1 | 24.00 | $100.00 | $2,400.00 |
| | | **Unit Sub Total** | **CY** | | **2** | **194.00** | **$214.79** | **$41,670.00** |
| **153218** | REMOVE CONCRETE SIDEWALK | | M | 5 | 1 | 250.00 | $25.00 | $6,250.00 |
| | | | M | 11 | 1 | 300.00 | $15.00 | $4,500.00 |
| | | **Unit Sub Total** | **M** | | **2** | **550.00** | **$19.55** | **$10,750.00** |
| **153218** | REMOVE CONCRETE SIDEWALK | | M2 | 3 | 1 | 20.00 | $10.00 | $200.00 |
| | | | M2 | 4 | 1 | 75.00 | $28.00 | $2,100.00 |
| | | | M2 | 5 | 1 | 3,070.00 | $48.00 | $147,360.00 |
| | | | M2 | 7 | 1 | 50.00 | $30.00 | $1,500.00 |
| | | **Unit Sub Total** | **M2** | | **4** | **3,215.00** | **$47.02** | **$151,160.00** |
| **153218** | REMOVE CONCRETE SIDEWALK | | M3 | 12 | 1 | 48.00 | $170.00 | $8,160.00 |
| | | **Unit Sub Total** | **M3** | | **1** | **48.00** | **$170.00** | **$8,160.00** |
| **153218** | REMOVE CONCRETE SIDEWALK | | SQYD | 1 | 1 | 84.00 | $50.00 | $4,200.00 |
| | | **Unit Sub Total** | **SQYD** | | **1** | **84.00** | **$50.00** | **$4,200.00** |
| | **Item Code 153218** | **Total No. of Proj.** | | | **10** | | **Total Amount** | **$215,940.00** |
| **153220** | REMOVE CONCRETE (CHANNEL) | | M | 11 | 2 | 390.00 | $92.31 | $36,000.00 |
| | | **Unit Sub Total** | **M** | | **2** | **390.00** | **$92.31** | **$36,000.00** |
| **153220** | REMOVE CONCRETE (CHANNEL) | | M3 | 4 | 1 | 34.00 | $150.00 | $5,100.00 |
| | | | M3 | 5 | 2 | 194.00 | $104.02 | $20,180.00 |
| | | | M3 | 7 | 1 | 15.00 | $200.00 | $3,000.00 |
| | | | M3 | 8 | 1 | 11.00 | $175.00 | $1,925.00 |
| | | **Unit Sub Total** | **M3** | | **5** | **254.00** | **$118.92** | **$30,205.00** |
| | **Item Code 153220** | **Total No. of Proj.** | | | **7** | | **Total Amount** | **$66,205.00** |
| **153221** | REMOVE CONCRETE BARRIER | | LF | 3 | 3 | 86,590.00 | $7.54 | $652,500.00 |
| | | | LF | 4 | 1 | 340.00 | $20.00 | $6,800.00 |
| | | | LF | 5 | 1 | 530.00 | $31.00 | $16,430.00 |
| | | | LF | 11 | 1 | 190.00 | $42.00 | $7,980.00 |
| | | | LF | 12 | 1 | 830.00 | $19.00 | $15,770.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **LF** | | **7** | **88,480.00** | **$7.91** | **$699,480.00** |
| **153221** | REMOVE CONCRETE BARRIER | | M | 1 | 1 | 560.00 | $70.00 | $39,200.00 |
| | | | M | 2 | 1 | 460.00 | $55.00 | $25,300.00 |
| | | | M | 3 | 2 | 5,360.00 | $37.29 | $199,870.00 |
| | | | M | 4 | 3 | 3,565.00 | $31.74 | $113,150.00 |
| | | | M | 5 | 2 | 2,960.00 | $22.43 | $66,380.00 |
| | | | M | 7 | 4 | 4,510.00 | $25.46 | $114,825.00 |
| | | | M | 8 | 1 | 2,700.00 | $37.00 | $99,900.00 |
| | | | M | 11 | 3 | 19,890.00 | $27.86 | $554,040.00 |
| | | **Unit Sub Total** | **M** | | **17** | **40,005.00** | **$30.31** | **$1,212,665.00** |
| | **Item Code 153221** | **Total No. of Proj.** | | | **24** | | **Total Amount** | **$1,912,145.00** |
| **153222** | REMOVE CONCRETE ISLAND (PORTIONS) | | CY | 12 | 1 | 0.50 | $700.00 | $350.00 |
| | | **Unit Sub Total** | **CY** | | **1** | **0.50** | **$700.00** | **$350.00** |
| **153222** | REMOVE CONCRETE ISLAND (PORTIONS) | | M3 | 7 | 1 | 24.00 | $92.00 | $2,208.00 |
| | | | M3 | 12 | 1 | 6.00 | $750.00 | $4,500.00 |
| | | **Unit Sub Total** | **M3** | | **2** | **30.00** | **$223.60** | **$6,708.00** |
| **153222** | REMOVE CONCRETE ISLAND (PORTIONS) | | SQYD | 10 | 1 | 440.00 | $15.00 | $6,600.00 |
| | | **Unit Sub Total** | **SQYD** | | **1** | **440.00** | **$15.00** | **$6,600.00** |
| | **Item Code 153222** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$13,658.00** |
| **153223** | REMOVE UNSOUND CONCRETE | | CF | 1 | 1 | 80.00 | $300.00 | $24,000.00 |
| | | | CF | 2 | 1 | 142.00 | $70.00 | $9,940.00 |
| | | | CF | 3 | 8 | 970.00 | $83.86 | $81,345.00 |
| | | | CF | 4 | 9 | 8,597.00 | $41.64 | $357,980.00 |
| | | | CF | 6 | 2 | 47.00 | $387.02 | $18,190.00 |
| | | | CF | 7 | 6 | 2,258.00 | $66.95 | $151,169.00 |
| | | | CF | 8 | 3 | 481.00 | $91.68 | $44,096.00 |
| | | | CF | 10 | 7 | 755.00 | $74.51 | $56,255.00 |
| | | | CF | 11 | 6 | 2,546.00 | $58.96 | $150,104.00 |
| | | | CF | 12 | 3 | 937.30 | $90.62 | $84,937.00 |
| | | **Unit Sub Total** | **CF** | | **46** | **16,813.30** | **$58.17** | **$978,016.00** |
| **153223** | REMOVE UNSOUND CONCRETE | | M3 | 2 | 1 | 20.00 | $2,575.00 | $51,500.00 |
| | | | M3 | 3 | 1 | 1.00 | $8,000.00 | $8,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **153223** | REMOVE UNSOUND CONCRETE | M3 | 8 | 1 | 47.00 | $4,280.00 | $201,160.00 |
| | **Unit Sub Total** | **M3** | | **3** | **68.00** | **$3,833.24** | **$260,660.00** |
| | **Item Code 153223 Total No. of Proj.** | | | **49** | | **Total Amount** | **$1,238,676.00** |
| **153225** | PREPARE CONCRETE BRIDGE DECK SURFACE | M2 | 1 | 1 | 1,202.00 | $8.00 | $9,616.00 |
| | | M2 | 2 | 3 | 19,261.00 | $5.40 | $104,032.00 |
| | | M2 | 3 | 2 | 3,517.00 | $4.50 | $15,834.00 |
| | | M2 | 5 | 1 | 750.00 | $26.00 | $19,500.00 |
| | | M2 | 6 | 1 | 1,617.00 | $9.00 | $14,553.00 |
| | | M2 | 7 | 3 | 1,165.00 | $25.65 | $29,881.00 |
| | | M2 | 8 | 1 | 6,277.00 | $5.20 | $32,640.40 |
| | | M2 | 11 | 2 | 2,825.00 | $13.34 | $37,690.00 |
| | **Unit Sub Total** | **M2** | | **14** | **36,614.00** | **$7.20** | **$263,746.40** |
| **153225** | PREPARE CONCRETE BRIDGE DECK SURFACE | SQFT | 1 | 2 | 37,748.00 | $0.25 | $9,437.00 |
| | | SQFT | 2 | 3 | 257,347.00 | $0.35 | $91,312.65 |
| | | SQFT | 3 | 8 | 158,089.00 | $0.46 | $73,117.22 |
| | | SQFT | 4 | 7 | 218,912.00 | $0.45 | $98,834.00 |
| | | SQFT | 7 | 1 | 4,189.00 | $0.30 | $1,256.70 |
| | | SQFT | 8 | 2 | 50,334.00 | $0.45 | $22,591.00 |
| | | SQFT | 10 | 3 | 34,219.00 | $0.33 | $11,263.70 |
| | | SQFT | 12 | 1 | 10,536.00 | $0.60 | $6,321.60 |
| | **Unit Sub Total** | **SQFT** | | **27** | **771,374.00** | **$0.41** | **$314,133.87** |
| | **Item Code 153225 Total No. of Proj.** | | | **41** | | **Total Amount** | **$577,880.27** |
| **153229** | REMOVE CONCRETE BARRIER (TYPE K) | LF | 11 | 2 | 16,240.00 | $3.19 | $51,840.00 |
| | **Unit Sub Total** | **LF** | | **2** | **16,240.00** | **$3.19** | **$51,840.00** |
| **153229** | REMOVE CONCRETE BARRIER (TYPE K) | M | 4 | 2 | 1,638.00 | $13.69 | $22,428.00 |
| | | M | 8 | 2 | 3,594.00 | $12.45 | $44,760.00 |
| | | M | 10 | 1 | 400.00 | $10.00 | $4,000.00 |
| | | M | 11 | 6 | 13,478.00 | $6.18 | $83,230.00 |
| | **Unit Sub Total** | **M** | | **11** | **19,110.00** | **$8.08** | **$154,418.00** |
| | **Item Code 153229 Total No. of Proj.** | | | **13** | | **Total Amount** | **$206,258.00** |
| **153230** | REMOVE CONCRETE BARRIER (TYPE 50) | LF | 4 | 3 | 1,158.00 | $25.54 | $29,570.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **LF** | | **3** | **1,158.00** | **$25.54** | **$29,570.00** |
| **153230** | REMOVE CONCRETE BARRIER (TYPE 50) | | M | 4 | 2 | 15,770.00 | $10.42 | $164,260.00 |
| | | **Unit Sub Total** | **M** | | **2** | **15,770.00** | **$10.42** | **$164,260.00** |
| | **Item Code 153230** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$193,830.00** |
| **153235** | CLEAN BRIDGE DECK | | M2 | 2 | 1 | 468.00 | $12.00 | $5,616.00 |
| | | | M2 | 3 | 2 | 3,460.00 | $3.12 | $10,782.40 |
| | | | M2 | 4 | 2 | 4,580.00 | $4.00 | $18,320.00 |
| | | | M2 | 7 | 1 | 9,866.00 | $4.00 | $39,464.00 |
| | | | M2 | 8 | 2 | 17,946.00 | $4.55 | $81,665.30 |
| | | | M2 | 11 | 3 | 12,975.00 | $6.73 | $87,280.00 |
| | | **Unit Sub Total** | **M2** | | **11** | **49,295.00** | **$4.93** | **$243,127.70** |
| **153235** | CLEAN BRIDGE DECK | | SQFT | 1 | 3 | 54,048.00 | $0.33 | $17,956.75 |
| | | | SQFT | 2 | 1 | 200,813.00 | $0.12 | $24,097.56 |
| | | | SQFT | 3 | 9 | 489,666.00 | $0.22 | $106,115.63 |
| | | | SQFT | 4 | 8 | 3,208,873.00 | $0.16 | $500,826.12 |
| | | | SQFT | 5 | 2 | 166,328.00 | $0.25 | $41,852.20 |
| | | | SQFT | 6 | 2 | 46,518.00 | $0.30 | $13,955.40 |
| | | | SQFT | 7 | 5 | 911,768.00 | $0.16 | $142,493.80 |
| | | | SQFT | 8 | 4 | 361,027.00 | $0.18 | $66,663.00 |
| | | | SQFT | 10 | 4 | 677,746.00 | $0.15 | $98,337.85 |
| | | | SQFT | 11 | 6 | 1,052,153.00 | $0.17 | $173,937.85 |
| | | | SQFT | 12 | 4 | 400,050.00 | $0.21 | $83,305.00 |
| | | **Unit Sub Total** | **SQFT** | | **48** | **7,568,990.00** | **$0.17** | **$1,269,541.16** |
| | **Item Code 153235** | **Total No. of Proj.** | | | **59** | | **Total Amount** | **$1,512,668.86** |
| **153239** | REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK) | | CY | 4 | 1 | 220.00 | $560.00 | $123,200.00 |
| | | | CY | 7 | 2 | 50.00 | $100.00 | $5,000.00 |
| | | | CY | 8 | 1 | 16.00 | $110.00 | $1,760.00 |
| | | **Unit Sub Total** | **CY** | | **4** | **286.00** | **$454.41** | **$129,960.00** |
| **153239** | REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK) | | LF | 3 | 1 | 290.00 | $20.00 | $5,800.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **290.00** | **$20.00** | **$5,800.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **153239** | REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK) | M | 11 | 1 | 61.00 | $150.00 | $9,150.00 |
| | **Unit Sub Total** | **M** | | **1** | **61.00** | **$150.00** | **$9,150.00** |
| **153239** | REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK) | M3 | 3 | 1 | 6.00 | $370.00 | $2,220.00 |
| | | M3 | 5 | 1 | 45.00 | $294.00 | $13,230.00 |
| | | M3 | 7 | 1 | 240.00 | $130.00 | $31,200.00 |
| | | M3 | 8 | 1 | 1,120.00 | $64.00 | $71,680.00 |
| | | M3 | 11 | 1 | 17.00 | $288.00 | $4,896.00 |
| | **Unit Sub Total** | **M3** | | **5** | **1,428.00** | **$86.29** | **$123,226.00** |
| | **Item Code 153239 Total No. of Proj.** | | | **11** | | **Total Amount** | **$268,136.00** |
| **153246** | REMOVE CONCRETE (MISCELLANEOUS) | CY | 3 | 1 | 8.00 | $150.00 | $1,200.00 |
| | | CY | 4 | 2 | 148.00 | $89.46 | $13,240.00 |
| | | CY | 11 | 1 | 6.00 | $400.00 | $2,400.00 |
| | **Unit Sub Total** | **CY** | | **4** | **162.00** | **$103.95** | **$16,840.00** |
| **153246** | REMOVE CONCRETE (MISCELLANEOUS) | M3 | 1 | 1 | 17.00 | $180.00 | $3,060.00 |
| | | M3 | 2 | 1 | 1.40 | $1,150.00 | $1,610.00 |
| | | M3 | 4 | 1 | 73.00 | $175.00 | $12,775.00 |
| | | M3 | 7 | 1 | 4.00 | $200.00 | $800.00 |
| | | M3 | 8 | 1 | 39.00 | $170.00 | $6,630.00 |
| | | M3 | 12 | 2 | 50.00 | $194.00 | $9,700.00 |
| | **Unit Sub Total** | **M3** | | **7** | **184.40** | **$187.50** | **$34,575.00** |
| | **Item Code 153246 Total No. of Proj.** | | | **11** | | **Total Amount** | **$51,415.00** |
| **153250** | REMOVE SOUND WALL | M | 3 | 1 | 100.00 | $44.00 | $4,400.00 |
| | | M | 11 | 1 | 250.00 | $39.00 | $9,750.00 |
| | **Unit Sub Total** | **M** | | **2** | **350.00** | **$40.43** | **$14,150.00** |
| | **Item Code 153250 Total No. of Proj.** | | | **2** | | **Total Amount** | **$14,150.00** |
| **153531** | ACCESS OPENING, SOFFIT | EA | 7 | 1 | 2.00 | $1,100.00 | $2,200.00 |
| | | EA | 11 | 3 | 35.00 | $1,442.86 | $50,500.00 |
| | **Unit Sub Total** | **EA** | | **4** | **37.00** | **$1,424.32** | **$52,700.00** |
| | **Item Code 153531 Total No. of Proj.** | | | **4** | | **Total Amount** | **$52,700.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **153540** | SHATTER CONCRETE | M2 | 11 | 1 | 2,490.00 | $3.00 | $7,470.00 |
| | **Unit Sub Total** | **M2** | | **1** | **2,490.00** | **$3.00** | **$7,470.00** |
| | **Item Code 153540 Total No. of Proj.** | | | **1** | | **Total Amount** | **$7,470.00** |
| **155003** | CAP INLET | EA | 3 | 2 | 23.00 | $939.13 | $21,600.00 |
| | | EA | 4 | 7 | 101.00 | $1,084.94 | $109,579.20 |
| | | EA | 5 | 4 | 9.00 | $1,477.78 | $13,300.00 |
| | | EA | 7 | 6 | 91.00 | $1,653.44 | $150,463.00 |
| | | EA | 8 | 3 | 23.00 | $1,179.78 | $27,135.00 |
| | | EA | 11 | 8 | 72.00 | $1,655.56 | $119,200.00 |
| | | EA | 12 | 1 | 1.00 | $1,500.00 | $1,500.00 |
| | **Unit Sub Total** | **EA** | | **31** | **320.00** | **$1,383.68** | **$442,777.20** |
| | **Item Code 155003 Total No. of Proj.** | | | **31** | | **Total Amount** | **$442,777.20** |
| **155006** | CAP RISER | EA | 11 | 3 | 18.00 | $1,527.78 | $27,500.00 |
| | **Unit Sub Total** | **EA** | | **3** | **18.00** | **$1,527.78** | **$27,500.00** |
| | **Item Code 155006 Total No. of Proj.** | | | **3** | | **Total Amount** | **$27,500.00** |
| **155007** | CAP MANHOLE | EA | 7 | 1 | 1.00 | $3,000.00 | $3,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$3,000.00** | **$3,000.00** |
| | **Item Code 155007 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,000.00** |
| **155009** | CAP REINFORCED CONCRETE BOX OPENING | EA | 7 | 1 | 1.00 | $1,600.00 | $1,600.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,600.00** | **$1,600.00** |
| | **Item Code 155009 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,600.00** |
| **156535** | REMOVE BOX CULVERT | M3 | 12 | 1 | 1.50 | $2,500.00 | $3,750.00 |
| | **Unit Sub Total** | **M3** | | **1** | **1.50** | **$2,500.00** | **$3,750.00** |
| | **Item Code 156535 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,750.00** |
| **156572** | REMOVE RAILING | M | 7 | 1 | 16.00 | $100.00 | $1,600.00 |
| | **Unit Sub Total** | **M** | | **1** | **16.00** | **$100.00** | **$1,600.00** |
| | **Item Code 156572 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,600.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **156579** | REMOVE BRIDGE RAILING | | LF | 1 | 1 | 80.00 | $32.50 | $2,600.00 |
| | | | LF | 5 | 1 | 150.00 | $18.00 | $2,700.00 |
| | | **Unit Sub Total** | **LF** | | **2** | **230.00** | **$23.04** | **$5,300.00** |
| **156579** | REMOVE BRIDGE RAILING | | M | 5 | 1 | 2.00 | $340.00 | $680.00 |
| | | | M | 7 | 2 | 1,332.00 | $72.25 | $96,240.00 |
| | | **Unit Sub Total** | **M** | | **3** | **1,334.00** | **$72.65** | **$96,920.00** |
| | **Item Code 156579** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$102,220.00** |
| **156585** | REMOVE CRASH CUSHION | | EA | 5 | 1 | 1.00 | $4,285.00 | $4,285.00 |
| | | | EA | 7 | 2 | 3.00 | $1,083.33 | $3,250.00 |
| | | | EA | 8 | 1 | 1.00 | $300.00 | $300.00 |
| | | | EA | 11 | 3 | 5.00 | $3,040.00 | $15,200.00 |
| | | **Unit Sub Total** | **EA** | | **7** | **10.00** | **$2,303.50** | **$23,035.00** |
| | **Item Code 156585** | **Total No. of Proj.** | | | **7** | | **Total Amount** | **$23,035.00** |
| **156590** | REMOVE CRASH CUSHION (SAND FILLED) | | EA | 4 | 4 | 33.00 | $798.48 | $26,350.00 |
| | | | EA | 5 | 5 | 16.00 | $1,356.16 | $21,698.54 |
| | | | EA | 7 | 1 | 1.00 | $728.00 | $728.00 |
| | | | EA | 10 | 1 | 2.00 | $665.00 | $1,330.00 |
| | | | EA | 11 | 1 | 1.00 | $775.00 | $775.00 |
| | | **Unit Sub Total** | **EA** | | **12** | **53.00** | **$960.03** | **$50,881.54** |
| | **Item Code 156590** | **Total No. of Proj.** | | | **12** | | **Total Amount** | **$50,881.54** |
| **157550** | BRIDGE REMOVAL | | LS | 2 | 2 | 2.00 | $175,000.00 | $350,000.00 |
| | | | LS | 3 | 3 | 3.00 | $78,333.33 | $235,000.00 |
| | | | LS | 4 | 2 | 2.00 | $165,000.00 | $330,000.00 |
| | | | LS | 7 | 2 | 2.00 | $97,500.00 | $195,000.00 |
| | | | LS | 8 | 1 | 1.00 | $147,000.00 | $147,000.00 |
| | | | LS | 10 | 1 | 1.00 | $50,000.00 | $50,000.00 |
| | | | LS | 11 | 2 | 2.00 | $262,500.00 | $525,000.00 |
| | | **Unit Sub Total** | **LS** | | **13** | **13.00** | **$140,923.08** | **$1,832,000.00** |
| | **Item Code 157550** | **Total No. of Proj.** | | | **13** | | **Total Amount** | **$1,832,000.00** |
| **157551** | BRIDGE REMOVAL, LOCATION A | | LS | 1 | 1 | 1.00 | $1,100,000.00 | $1,100,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **157551** | BRIDGE REMOVAL, LOCATION A | LS | 2 | 1 | 1.00 | $110,000.00 | $110,000.00 |
| | | LS | 5 | 1 | 1.00 | $85,300.00 | $85,300.00 |
| | | LS | 11 | 1 | 1.00 | $330,000.00 | $330,000.00 |
| | **Unit Sub Total** | **LS** | | **4** | **4.00** | **$406,325.00** | **$1,625,300.00** |
| | **Item Code 157551 Total No. of Proj.** | | | **4** | | **Total Amount** | **$1,625,300.00** |
| **157552** | BRIDGE REMOVAL, LOCATION B | LS | 1 | 1 | 1.00 | $1,200,000.00 | $1,200,000.00 |
| | | LS | 2 | 1 | 1.00 | $3,200,000.00 | $3,200,000.00 |
| | | LS | 5 | 1 | 1.00 | $245,000.00 | $245,000.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$1,548,333.33** | **$4,645,000.00** |
| | **Item Code 157552 Total No. of Proj.** | | | **3** | | **Total Amount** | **$4,645,000.00** |
| **157560** | BRIDGE REMOVAL (PORTION) | LS | 1 | 2 | 2.00 | $34,500.00 | $69,000.00 |
| | | LS | 2 | 1 | 1.00 | $99,000.00 | $99,000.00 |
| | | LS | 3 | 3 | 3.00 | $130,333.33 | $391,000.00 |
| | | LS | 4 | 1 | 1.00 | $124,000.00 | $124,000.00 |
| | | LS | 5 | 1 | 1.00 | $106,900.00 | $106,900.00 |
| | | LS | 6 | 2 | 2.00 | $35,125.00 | $70,250.00 |
| | | LS | 7 | 6 | 6.00 | $73,212.50 | $439,275.00 |
| | | LS | 8 | 1 | 1.00 | $550,000.00 | $550,000.00 |
| | | LS | 10 | 4 | 4.00 | $12,486.40 | $49,945.60 |
| | | LS | 11 | 2 | 2.00 | $5,400.00 | $10,800.00 |
| | | LS | 12 | 1 | 1.00 | $45,500.00 | $45,500.00 |
| | **Unit Sub Total** | **LS** | | **24** | **24.00** | **$81,486.28** | **$1,955,670.60** |
| | **Item Code 157560 Total No. of Proj.** | | | **24** | | **Total Amount** | **$1,955,670.60** |
| **157561** | BRIDGE REMOVAL (PORTION), LOCATION A | LS | 1 | 1 | 1.00 | $100,000.00 | $100,000.00 |
| | | LS | 2 | 1 | 1.00 | $6,600.00 | $6,600.00 |
| | | LS | 3 | 5 | 5.00 | $31,100.00 | $155,500.00 |
| | | LS | 4 | 7 | 7.00 | $50,242.86 | $351,700.00 |
| | | LS | 5 | 1 | 1.00 | $63,200.00 | $63,200.00 |
| | | LS | 6 | 1 | 1.00 | $11,400.00 | $11,400.00 |
| | | LS | 7 | 6 | 6.00 | $19,416.67 | $116,500.00 |
| | | LS | 8 | 1 | 1.00 | $21,000.00 | $21,000.00 |
| | | LS | 10 | 2 | 2.00 | $7,000.00 | $14,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **157561** | BRIDGE REMOVAL (PORTION), LOCATION A | LS | 11 | 5 | 5.00 | $28,100.00 | $140,500.00 |
| | | LS | 12 | 1 | 1.00 | $28,800.00 | $28,800.00 |
| | **Unit Sub Total** | **LS** | | **31** | **31.00** | **$32,554.84** | **$1,009,200.00** |
| **157561** | BRIDGE REMOVAL (PORTION), LOCATION A | M3 | 3 | 1 | 7,452.00 | $120.00 | $894,240.00 |
| | **Unit Sub Total** | **M3** | | **1** | **7,452.00** | **$120.00** | **$894,240.00** |
| | **Item Code 157561 Total No. of Proj.** | | | **32** | | **Total Amount** | **$1,903,440.00** |
| **157562** | BRIDGE REMOVAL (PORTION), LOCATION B | LS | 1 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | | LS | 2 | 1 | 1.00 | $3,800.00 | $3,800.00 |
| | | LS | 3 | 5 | 5.00 | $32,400.00 | $162,000.00 |
| | | LS | 4 | 7 | 7.00 | $37,000.00 | $259,000.00 |
| | | LS | 5 | 1 | 1.00 | $29,700.00 | $29,700.00 |
| | | LS | 6 | 1 | 1.00 | $11,400.00 | $11,400.00 |
| | | LS | 7 | 6 | 6.00 | $24,083.33 | $144,500.00 |
| | | LS | 8 | 1 | 1.00 | $24,000.00 | $24,000.00 |
| | | LS | 10 | 2 | 2.00 | $36,000.00 | $72,000.00 |
| | | LS | 11 | 6 | 6.00 | $22,250.00 | $133,500.00 |
| | | LS | 12 | 1 | 1.00 | $10,400.00 | $10,400.00 |
| | **Unit Sub Total** | **LS** | | **32** | **32.00** | **$27,353.13** | **$875,300.00** |
| | **Item Code 157562 Total No. of Proj.** | | | **32** | | **Total Amount** | **$875,300.00** |
| **157563** | BRIDGE REMOVAL (PORTION), LOCATION C | LS | 1 | 1 | 1.00 | $40,000.00 | $40,000.00 |
| | | LS | 2 | 1 | 1.00 | $43,000.00 | $43,000.00 |
| | | LS | 3 | 3 | 3.00 | $10,833.33 | $32,500.00 |
| | | LS | 4 | 4 | 4.00 | $28,750.00 | $115,000.00 |
| | | LS | 6 | 1 | 1.00 | $24,000.00 | $24,000.00 |
| | | LS | 7 | 3 | 3.00 | $128,333.33 | $385,000.00 |
| | | LS | 10 | 2 | 2.00 | $36,000.00 | $72,000.00 |
| | | LS | 11 | 5 | 5.00 | $28,600.00 | $143,000.00 |
| | **Unit Sub Total** | **LS** | | **20** | **20.00** | **$42,725.00** | **$854,500.00** |
| | **Item Code 157563 Total No. of Proj.** | | | **20** | | **Total Amount** | **$854,500.00** |
| **157564** | BRIDGE REMOVAL (PORTION), LOCATION D | LS | 2 | 1 | 1.00 | $5,950.00 | $5,950.00 |
| | | LS | 4 | 3 | 3.00 | $47,666.67 | $143,000.00 |
| | | LS | 7 | 2 | 2.00 | $148,500.00 | $297,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **157564** | BRIDGE REMOVAL (PORTION), LOCATION D | LS | 10 | 2 | 2.00 | $18,500.00 | $37,000.00 |
| | | LS | 11 | 4 | 4.00 | $20,125.00 | $80,500.00 |
| | **Unit Sub Total** | **LS** | | **12** | **12.00** | **$46,954.17** | **$563,450.00** |
| | **Item Code 157564 Total No. of Proj.** | | | **12** | | **Total Amount** | **$563,450.00** |
| **157565** | BRIDGE REMOVAL (PORTION), LOCATION E | LS | 2 | 1 | 1.00 | $7,400.00 | $7,400.00 |
| | | LS | 4 | 1 | 1.00 | $100,000.00 | $100,000.00 |
| | | LS | 7 | 2 | 2.00 | $40,000.00 | $80,000.00 |
| | | LS | 10 | 2 | 2.00 | $21,000.00 | $42,000.00 |
| | | LS | 11 | 3 | 3.00 | $29,000.00 | $87,000.00 |
| | **Unit Sub Total** | **LS** | | **9** | **9.00** | **$35,155.56** | **$316,400.00** |
| | **Item Code 157565 Total No. of Proj.** | | | **9** | | **Total Amount** | **$316,400.00** |
| **157566** | BRIDGE REMOVAL (PORTION), LOCATION F | LS | 7 | 2 | 2.00 | $35,000.00 | $70,000.00 |
| | | LS | 10 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | | LS | 11 | 1 | 1.00 | $20,000.00 | $20,000.00 |
| | **Unit Sub Total** | **LS** | | **4** | **4.00** | **$23,000.00** | **$92,000.00** |
| | **Item Code 157566 Total No. of Proj.** | | | **4** | | **Total Amount** | **$92,000.00** |
| **157567** | BRIDGE REMOVAL (PORTION), LOCATION G | LS | 7 | 1 | 1.00 | $4,000.00 | $4,000.00 |
| | | LS | 11 | 1 | 1.00 | $10,000.00 | $10,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$7,000.00** | **$14,000.00** |
| | **Item Code 157567 Total No. of Proj.** | | | **2** | | **Total Amount** | **$14,000.00** |
| **157568** | BRIDGE REMOVAL (PORTION), LOCATION H | LS | 7 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$25,000.00** | **$25,000.00** |
| | **Item Code 157568 Total No. of Proj.** | | | **1** | | **Total Amount** | **$25,000.00** |
| **157569** | BRIDGE REMOVAL (PORTION), LOCATION I | LS | 7 | 1 | 1.00 | $14,000.00 | $14,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$14,000.00** | **$14,000.00** |
| | **Item Code 157569 Total No. of Proj.** | | | **1** | | **Total Amount** | **$14,000.00** |
| **157570** | BRIDGE REMOVAL (PORTION), LOCATION J | LS | 7 | 1 | 1.00 | $17,000.00 | $17,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$17,000.00** | **$17,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 157570 Total No. of Proj.** | | | **1** | | **Total Amount** | **$17,000.00** |
| **157571** | BRIDGE REMOVAL (PORTION), LOCATION K | LS | 7 | 1 | 1.00 | $52,000.00 | $52,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$52,000.00** | **$52,000.00** |
| | **Item Code 157571 Total No. of Proj.** | | | **1** | | **Total Amount** | **$52,000.00** |
| **157572** | BRIDGE REMOVAL (PORTION), LOCATION L | LS | 7 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$5,000.00** | **$5,000.00** |
| | **Item Code 157572 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,000.00** |
| **157573** | BRIDGE REMOVAL (PORTION), LOCATION M | LS | 7 | 1 | 1.00 | $4,000.00 | $4,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$4,000.00** | **$4,000.00** |
| | **Item Code 157573 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,000.00** |
| **157581** | BRIDGE REMOVAL (PORTION), LOCATION 1 | LS | 2 | 1 | 1.00 | $40,500.00 | $40,500.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$40,500.00** | **$40,500.00** |
| | **Item Code 157581 Total No. of Proj.** | | | **1** | | **Total Amount** | **$40,500.00** |
| **158100** | SALVAGE CRASH CUSHION | EA | 3 | 1 | 1.00 | $720.00 | $720.00 |
| | | EA | 5 | 1 | 1.00 | $985.00 | $985.00 |
| | **Unit Sub Total** | **EA** | | **2** | **2.00** | **$852.50** | **$1,705.00** |
| | **Item Code 158100 Total No. of Proj.** | | | **2** | | **Total Amount** | **$1,705.00** |
| **158210** | RESET TEMPORARY RAILING (TYPE K) | LF | 1 | 2 | 3,650.00 | $3.00 | $10,950.00 |
| | | LF | 2 | 1 | 400.00 | $5.00 | $2,000.00 |
| | | LF | 11 | 1 | 1,700.00 | $3.80 | $6,460.00 |
| | **Unit Sub Total** | **LF** | | **4** | **5,750.00** | **$3.38** | **$19,410.00** |
| **158210** | RESET TEMPORARY RAILING (TYPE K) | M | 1 | 2 | 5,040.00 | $12.79 | $64,480.00 |
| | **Unit Sub Total** | **M** | | **2** | **5,040.00** | **$12.79** | **$64,480.00** |
| | **Item Code 158210 Total No. of Proj.** | | | **6** | | **Total Amount** | **$83,890.00** |
| **160101** | CLEARING AND GRUBBING | HA | 7 | 1 | 14.00 | $7,500.00 | $105,000.00 |
| | **Unit Sub Total** | **HA** | | **1** | **14.00** | **$7,500.00** | **$105,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **160101** | CLEARING AND GRUBBING | LS | 1 | 13 | 13.00 | $29,165.38 | $379,150.00 |
| | | LS | 2 | 14 | 14.00 | $29,490.79 | $412,871.03 |
| | | LS | 3 | 39 | 39.00 | $48,072.06 | $1,874,810.50 |
| | | LS | 4 | 25 | 25.00 | $51,656.30 | $1,291,407.60 |
| | | LS | 5 | 31 | 31.00 | $26,304.70 | $815,445.80 |
| | | LS | 6 | 18 | 18.00 | $15,572.22 | $280,300.00 |
| | | LS | 7 | 32 | 32.00 | $19,547.91 | $625,533.00 |
| | | LS | 8 | 15 | 15.00 | $21,032.85 | $315,492.78 |
| | | LS | 9 | 5 | 5.00 | $36,000.00 | $180,000.00 |
| | | LS | 10 | 12 | 12.00 | $26,530.92 | $318,371.00 |
| | | LS | 11 | 19 | 19.00 | $94,093.53 | $1,787,777.06 |
| | | LS | 12 | 15 | 15.00 | $33,332.68 | $499,990.26 |
| | **Unit Sub Total** | **LS** | | **238** | **238.00** | **$36,895.58** | **$8,781,149.03** |
| | **Item Code 160101 Total No. of Proj.** | | | **239** | | **Total Amount** | **$8,886,149.03** |
| **160120** | REMOVE TREE | EA | 3 | 1 | 3.00 | $2,665.00 | $7,995.00 |
| | | EA | 4 | 2 | 520.00 | $493.27 | $256,500.00 |
| | | EA | 5 | 1 | 31.00 | $2,500.00 | $77,500.00 |
| | | EA | 8 | 2 | 48.00 | $1,306.25 | $62,700.00 |
| | | EA | 11 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | **Unit Sub Total** | **EA** | | **7** | **603.00** | **$674.45** | **$406,695.00** |
| | **Item Code 160120 Total No. of Proj.** | | | **7** | | **Total Amount** | **$406,695.00** |
| **160132** | DEMOLISH BUILDING | LS | 2 | 1 | 1.00 | $11,841.03 | $11,841.03 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$11,841.03** | **$11,841.03** |
| | **Item Code 160132 Total No. of Proj.** | | | **1** | | **Total Amount** | **$11,841.03** |
| **170101** | DEVELOP WATER SUPPLY | LS | 2 | 7 | 7.00 | $12,357.14 | $86,500.00 |
| | | LS | 3 | 2 | 2.00 | $20,000.00 | $40,000.00 |
| | | LS | 4 | 6 | 6.00 | $17,333.33 | $104,000.00 |
| | | LS | 5 | 1 | 1.00 | $5,500.00 | $5,500.00 |
| | | LS | 8 | 6 | 6.00 | $59,664.21 | $357,985.28 |
| | | LS | 9 | 1 | 1.00 | $40,000.00 | $40,000.00 |
| | | LS | 10 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | | LS | 11 | 10 | 10.00 | $21,787.50 | $217,875.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **LS** | | **34** | **34.00** | **$25,201.77** | **$856,860.28** |
| | **Item Code 170101** | **Total No. of Proj.** | | | **34** | | **Total Amount** | **$856,860.28** |
| **190101** | ROADWAY EXCAVATION | | CY | 1 | 10 | 36,166.00 | $16.64 | $601,790.00 |
| | | | CY | 2 | 11 | 162,770.00 | $9.12 | $1,484,855.00 |
| | | | CY | 3 | 31 | 474,869.00 | $23.07 | $10,956,737.00 |
| | | | CY | 4 | 6 | 4,595.00 | $34.27 | $157,464.80 |
| | | | CY | 5 | 5 | 15,123.00 | $31.85 | $481,597.50 |
| | | | CY | 6 | 12 | 71,528.00 | $18.31 | $1,309,999.50 |
| | | | CY | 7 | 13 | 6,832.20 | $31.96 | $218,353.00 |
| | | | CY | 8 | 6 | 4,832.00 | $25.54 | $123,428.20 |
| | | | CY | 10 | 6 | 1,346.00 | $57.39 | $77,252.00 |
| | | | CY | 11 | 12 | 64,423.00 | $16.85 | $1,085,665.00 |
| | | | CY | 12 | 12 | 28,149.90 | $19.15 | $538,954.85 |
| | | **Unit Sub Total** | **CY** | | **124** | **870,634.10** | **$19.57** | **$17,036,096.85** |
| **190101** | ROADWAY EXCAVATION | | M3 | 1 | 7 | 84,530.00 | $16.06 | $1,357,400.00 |
| | | | M3 | 2 | 6 | 70,620.00 | $32.53 | $2,297,301.40 |
| | | | M3 | 3 | 9 | 2,208,300.00 | $8.77 | $19,373,590.00 |
| | | | M3 | 4 | 17 | 579,914.00 | $13.53 | $7,844,255.20 |
| | | | M3 | 5 | 16 | 379,805.00 | $17.50 | $6,647,055.00 |
| | | | M3 | 6 | 11 | 95,103.00 | $26.00 | $2,472,339.00 |
| | | | M3 | 7 | 22 | 461,254.00 | $32.84 | $15,147,323.00 |
| | | | M3 | 8 | 7 | 103,326.00 | $20.51 | $2,119,645.00 |
| | | | M3 | 9 | 5 | 253,140.00 | $14.92 | $3,777,872.50 |
| | | | M3 | 10 | 11 | 280,220.00 | $8.55 | $2,396,431.00 |
| | | | M3 | 11 | 11 | 2,910,706.00 | $8.21 | $23,895,366.00 |
| | | | M3 | 12 | 2 | 8,400.00 | $18.14 | $152,390.00 |
| | | **Unit Sub Total** | **M3** | | **124** | **7,435,318.00** | **$11.77** | **$87,480,968.10** |
| | **Item Code 190101** | **Total No. of Proj.** | | | **248** | | **Total Amount** | **$104,517,064.95** |
| **190105** | ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD) | | CY | 3 | 2 | 12,070.00 | $101.13 | $1,220,600.00 |
| | | | CY | 7 | 2 | 180.00 | $146.67 | $26,400.00 |
| | | | CY | 11 | 1 | 240.00 | $188.00 | $45,120.00 |
| | | | CY | 12 | 1 | 280.00 | $152.00 | $42,560.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **CY** | | **6** | **12,770.00** | **$104.52** | **$1,334,680.00** |
| **190105** | ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD) | M3 | 1 | 1 | 900.00 | $315.00 | $283,500.00 |
| | | M3 | 2 | 1 | 1,670.00 | $50.00 | $83,500.00 |
| | | M3 | 4 | 4 | 12,600.00 | $177.98 | $2,242,500.00 |
| | | M3 | 5 | 2 | 5,110.00 | $208.70 | $1,066,480.00 |
| | | M3 | 7 | 4 | 12,246.00 | $174.40 | $2,135,720.00 |
| | **Unit Sub Total** | **M3** | | **12** | **32,526.00** | **$178.68** | **$5,811,700.00** |
| | **Item Code 190105 Total No. of Proj.** | | | **18** | | **Total Amount** | **$7,146,380.00** |
| **190106** | ROADWAY EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD) | CY | 7 | 1 | 380.00 | $275.00 | $104,500.00 |
| | | CY | 12 | 1 | 20.00 | $306.00 | $6,120.00 |
| | **Unit Sub Total** | **CY** | | **2** | **400.00** | **$276.55** | **$110,620.00** |
| **190106** | ROADWAY EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD) | M3 | 7 | 1 | 14.00 | $275.00 | $3,850.00 |
| | **Unit Sub Total** | **M3** | | **1** | **14.00** | **$275.00** | **$3,850.00** |
| | **Item Code 190106 Total No. of Proj.** | | | **3** | | **Total Amount** | **$114,470.00** |
| **190107** | ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD) | CY | 12 | 3 | 780.00 | $54.46 | $42,481.70 |
| | **Unit Sub Total** | **CY** | | **3** | **780.00** | **$54.46** | **$42,481.70** |
| **190107** | ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD) | M3 | 4 | 2 | 28,100.00 | $14.08 | $395,600.00 |
| | | M3 | 7 | 3 | 6,685.00 | $23.79 | $159,004.00 |
| | | M3 | 8 | 2 | 7,480.00 | $20.29 | $151,782.50 |
| | **Unit Sub Total** | **M3** | | **7** | **42,265.00** | **$16.71** | **$706,386.50** |
| | **Item Code 190107 Total No. of Proj.** | | | **10** | | **Total Amount** | **$748,868.20** |
| **190108** | ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD) | CY | 8 | 1 | 1,260.00 | $45.00 | $56,700.00 |
| | **Unit Sub Total** | **CY** | | **1** | **1,260.00** | **$45.00** | **$56,700.00** |
| **190108** | ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD) | M3 | 4 | 2 | 39,520.00 | $1.22 | $48,125.00 |
| | **Unit Sub Total** | **M3** | | **2** | **39,520.00** | **$1.22** | **$48,125.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 190108 Total No. of Proj.** | | | **3** | | **Total Amount** | **$104,825.00** |
| **190109** | ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS) | CY | 3 | 2 | 1,330.00 | $58.98 | $78,440.00 |
| | **Unit Sub Total** | **CY** | | **2** | **1,330.00** | **$58.98** | **$78,440.00** |
| **190109** | ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS) | M3 | 3 | 2 | 11,641.00 | $30.62 | $356,400.08 |
| | | M3 | 5 | 1 | 240.00 | $117.00 | $28,080.00 |
| | **Unit Sub Total** | **M3** | | **3** | **11,881.00** | **$32.36** | **$384,480.08** |
| | **Item Code 190109 Total No. of Proj.** | | | **5** | | **Total Amount** | **$462,920.08** |
| **190110** | LEAD COMPLIANCE PLAN | LS | 1 | 24 | 24.00 | $2,881.46 | $69,155.00 |
| | | LS | 2 | 16 | 16.00 | $2,394.75 | $38,315.99 |
| | | LS | 3 | 39 | 39.00 | $2,928.40 | $114,207.48 |
| | | LS | 4 | 52 | 52.00 | $2,839.86 | $147,672.67 |
| | | LS | 5 | 23 | 23.00 | $2,644.39 | $60,821.00 |
| | | LS | 6 | 30 | 30.00 | $2,800.67 | $84,020.00 |
| | | LS | 7 | 49 | 49.00 | $4,223.50 | $206,951.37 |
| | | LS | 8 | 38 | 38.00 | $2,590.20 | $98,427.44 |
| | | LS | 9 | 11 | 11.00 | $2,059.09 | $22,650.00 |
| | | LS | 10 | 35 | 35.00 | $2,569.74 | $89,941.00 |
| | | LS | 11 | 9 | 9.00 | $11,579.16 | $104,212.48 |
| | | LS | 12 | 26 | 26.00 | $2,788.86 | $72,510.36 |
| | **Unit Sub Total** | **LS** | | **352** | **352.00** | **$3,150.24** | **$1,108,884.79** |
| | **Item Code 190110 Total No. of Proj.** | | | **352** | | **Total Amount** | **$1,108,884.79** |
| **190113** | ASBESTOS COMPLIANCE PLAN | LS | 1 | 3 | 3.00 | $5,000.00 | $15,000.00 |
| | | LS | 2 | 1 | 1.00 | $6,000.00 | $6,000.00 |
| | | LS | 3 | 5 | 5.00 | $2,660.00 | $13,300.00 |
| | | LS | 4 | 1 | 1.00 | $3,000.00 | $3,000.00 |
| | | LS | 5 | 1 | 1.00 | $8,050.00 | $8,050.00 |
| | | LS | 7 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | | LS | 8 | 1 | 1.00 | $2,625.00 | $2,625.00 |
| | **Unit Sub Total** | **LS** | | **13** | **13.00** | **$4,075.00** | **$52,975.00** |
| | **Item Code 190113 Total No. of Proj.** | | | **13** | | **Total Amount** | **$52,975.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **190114** | DUST CONTROL PLAN | LS | 1 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | | LS | 3 | 3 | 3.00 | $2,316.67 | $6,950.00 |
| | **Unit Sub Total** | **LS** | | **4** | **4.00** | **$2,237.50** | **$8,950.00** |
| | **Item Code 190114 Total No. of Proj.** | | | **4** | | **Total Amount** | **$8,950.00** |
| **190115** | ASBESTOS COMPLIANCE PLAN (NATURALLY OCCURING ASBESTOS) | LS | 3 | 5 | 5.00 | $4,675.00 | $23,375.00 |
| | | LS | 4 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | | LS | 5 | 1 | 1.00 | $5,500.00 | $5,500.00 |
| | **Unit Sub Total** | **LS** | | **7** | **7.00** | **$4,410.71** | **$30,875.00** |
| | **Item Code 190115 Total No. of Proj.** | | | **7** | | **Total Amount** | **$30,875.00** |
| **190116** | DUST CONTROL PLAN (NATURALLY OCCURRING ASBESTOS) | LS | 3 | 5 | 5.00 | $3,179.00 | $15,895.00 |
| | | LS | 4 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | | LS | 5 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | **Unit Sub Total** | **LS** | | **7** | **7.00** | **$2,842.14** | **$19,895.00** |
| | **Item Code 190116 Total No. of Proj.** | | | **7** | | **Total Amount** | **$19,895.00** |
| **190117** | SAMPLING AND ANALYSIS PLAN (NATURALLY OCCURRING ASBESTOS) | LS | 3 | 1 | 1.00 | $3,800.00 | $3,800.00 |
| | | LS | 5 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$2,900.00** | **$5,800.00** |
| | **Item Code 190117 Total No. of Proj.** | | | **2** | | **Total Amount** | **$5,800.00** |
| **190130** | ROADWAY EXCAVATION (SLIDE REMOVAL) | M3 | 4 | 1 | 180.00 | $70.00 | $12,600.00 |
| | | M3 | 7 | 1 | 1,570.00 | $30.00 | $47,100.00 |
| | **Unit Sub Total** | **M3** | | **2** | **1,750.00** | **$34.11** | **$59,700.00** |
| | **Item Code 190130 Total No. of Proj.** | | | **2** | | **Total Amount** | **$59,700.00** |
| **190134** | ROADWAY EXCAVATION (GORE REMOVAL) | CY | 6 | 1 | 110.00 | $50.72 | $5,579.20 |
| | **Unit Sub Total** | **CY** | | **1** | **110.00** | **$50.72** | **$5,579.20** |
| | **Item Code 190134 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,579.20** |
| **190135** | ROADWAY GRADING | M3 | 7 | 1 | 30.00 | $100.00 | $3,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M3** | | **1** | **30.00** | **$100.00** | **$3,000.00** |
| | **Item Code 190135** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,000.00** |
| **190161** | ROCK EXCAVATION | | CY | 1 | 1 | 11,300.00 | $26.00 | $293,800.00 |
| | | | CY | 2 | 1 | 32,800.00 | $24.00 | $787,200.00 |
| | | | CY | 6 | 1 | 10,500.00 | $39.00 | $409,500.00 |
| | | | CY | 8 | 1 | 16,100.00 | $95.00 | $1,529,500.00 |
| | | **Unit Sub Total** | **CY** | | **4** | **70,700.00** | **$42.72** | **$3,020,000.00** |
| | **Item Code 190161** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$3,020,000.00** |
| **190162** | STRIPPING EXCAVATION | | CY | 8 | 1 | 1,150.00 | $56.00 | $64,400.00 |
| | | **Unit Sub Total** | **CY** | | **1** | **1,150.00** | **$56.00** | **$64,400.00** |
| | **Item Code 190162** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$64,400.00** |
| **190170** | DRILL HOLE (PRESPLITTING) | | LF | 6 | 1 | 19,300.00 | $6.00 | $115,800.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **19,300.00** | **$6.00** | **$115,800.00** |
| | **Item Code 190170** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$115,800.00** |
| **190183** | RESHAPE SHOULDER | | M2 | 8 | 1 | 47.00 | $2,691.00 | $126,477.00 |
| | | **Unit Sub Total** | **M2** | | **1** | **47.00** | **$2,691.00** | **$126,477.00** |
| | **Item Code 190183** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$126,477.00** |
| **190185** | SHOULDER BACKING | | TON | 6 | 1 | 1,270.00 | $20.50 | $26,035.00 |
| | | **Unit Sub Total** | **TON** | | **1** | **1,270.00** | **$20.50** | **$26,035.00** |
| **190185** | SHOULDER BACKING | | TONN | 5 | 1 | 63.00 | $75.00 | $4,725.00 |
| | | **Unit Sub Total** | **TONN** | | **1** | **63.00** | **$75.00** | **$4,725.00** |
| | **Item Code 190185** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$30,760.00** |
| **192001** | STRUCTURE EXCAVATION | | CY | 2 | 4 | 356.00 | $103.40 | $36,810.00 |
| | | | CY | 3 | 1 | 132.00 | $50.00 | $6,600.00 |
| | | **Unit Sub Total** | **CY** | | **5** | **488.00** | **$88.95** | **$43,410.00** |
| **192001** | STRUCTURE EXCAVATION | | M3 | 3 | 1 | 733.00 | $100.00 | $73,300.00 |
| | | | M3 | 7 | 1 | 620.00 | $46.00 | $28,520.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **192001** | STRUCTURE EXCAVATION | M3 | 8 | 1 | 75.00 | $66.00 | $4,950.00 |
| | **Unit Sub Total** | **M3** | | **3** | **1,428.00** | **$74.77** | **$106,770.00** |
| | **Item Code 192001 Total No. of Proj.** | | | **8** | | **Total Amount** | **$150,180.00** |
| **192003** | STRUCTURE EXCAVATION (BRIDGE) | CY | 2 | 1 | 8.00 | $176.00 | $1,408.00 |
| | | CY | 4 | 1 | 235.00 | $80.00 | $18,800.00 |
| | | CY | 7 | 1 | 265.00 | $40.00 | $10,600.00 |
| | | CY | 10 | 1 | 1.50 | $2,000.00 | $3,000.00 |
| | | CY | 12 | 1 | 153.00 | $140.00 | $21,420.00 |
| | **Unit Sub Total** | **CY** | | **5** | **662.50** | **$83.36** | **$55,228.00** |
| **192003** | STRUCTURE EXCAVATION (BRIDGE) | M3 | 1 | 3 | 1,296.00 | $124.09 | $160,815.00 |
| | | M3 | 2 | 4 | 3,504.00 | $148.03 | $518,690.00 |
| | | M3 | 3 | 4 | 7,250.00 | $108.77 | $788,611.00 |
| | | M3 | 4 | 5 | 1,634.00 | $184.00 | $300,658.00 |
| | | M3 | 5 | 2 | 3,118.00 | $47.33 | $147,586.00 |
| | | M3 | 6 | 1 | 35.00 | $200.00 | $7,000.00 |
| | | M3 | 7 | 7 | 4,709.00 | $201.00 | $946,500.00 |
| | | M3 | 8 | 1 | 1,738.00 | $83.00 | $144,254.00 |
| | | M3 | 10 | 2 | 2,600.00 | $90.42 | $235,080.00 |
| | | M3 | 11 | 8 | 29,975.00 | $31.17 | $934,325.00 |
| | **Unit Sub Total** | **M3** | | **37** | **55,859.00** | **$74.89** | **$4,183,519.00** |
| | **Item Code 192003 Total No. of Proj.** | | | **42** | | **Total Amount** | **$4,238,747.00** |
| **192008** | STRUCTURE EXCAVATION (TYPE A) | M3 | 3 | 1 | 3,184.00 | $450.00 | $1,432,800.00 |
| | | M3 | 4 | 1 | 927.00 | $400.00 | $370,800.00 |
| | | M3 | 9 | 1 | 880.00 | $40.00 | $35,200.00 |
| | **Unit Sub Total** | **M3** | | **3** | **4,991.00** | **$368.42** | **$1,838,800.00** |
| | **Item Code 192008 Total No. of Proj.** | | | **3** | | **Total Amount** | **$1,838,800.00** |
| **192020** | STRUCTURE EXCAVATION (TYPE D) | CY | 12 | 1 | 295.00 | $200.00 | $59,000.00 |
| | **Unit Sub Total** | **CY** | | **1** | **295.00** | **$200.00** | **$59,000.00** |
| **192020** | STRUCTURE EXCAVATION (TYPE D) | M3 | 1 | 2 | 885.00 | $1,698.64 | $1,503,300.00 |
| | | M3 | 2 | 3 | 1,105.00 | $1,171.04 | $1,294,000.00 |
| | | M3 | 3 | 3 | 2,143.00 | $91.48 | $196,050.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **192020** | STRUCTURE EXCAVATION (TYPE D) | M3 | 5 | 1 | 600.00 | $140.00 | $84,000.00 |
| | | M3 | 7 | 2 | 2,555.00 | $153.52 | $392,250.00 |
| | | M3 | 11 | 2 | 2,070.00 | $42.90 | $88,800.00 |
| | **Unit Sub Total** | **M3** | | **13** | **9,358.00** | **$380.25** | **$3,558,400.00** |
| | **Item Code 192020 Total No. of Proj.** | | | **14** | | **Total Amount** | **$3,617,400.00** |
| **192025** | STRUCTURE EXCAVATION (CULVERT) | M3 | 4 | 1 | 23.00 | $50.00 | $1,150.00 |
| | | M3 | 7 | 1 | 4,458.00 | $50.00 | $222,900.00 |
| | **Unit Sub Total** | **M3** | | **2** | **4,481.00** | **$50.00** | **$224,050.00** |
| | **Item Code 192025 Total No. of Proj.** | | | **2** | | **Total Amount** | **$224,050.00** |
| **192031** | STRUCTURE EXCAVATION (PIER COLUMN) | CY | 8 | 1 | 1,280.00 | $1,600.00 | $2,048,000.00 |
| | **Unit Sub Total** | **CY** | | **1** | **1,280.00** | **$1,600.00** | **$2,048,000.00** |
| | **Item Code 192031 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,048,000.00** |
| **192035** | STRUCTURE EXCAVATION (ROCK) | CY | 8 | 1 | 3,200.00 | $210.00 | $672,000.00 |
| | **Unit Sub Total** | **CY** | | **1** | **3,200.00** | **$210.00** | **$672,000.00** |
| **192035** | STRUCTURE EXCAVATION (ROCK) | M3 | 10 | 1 | 230.00 | $150.00 | $34,500.00 |
| | **Unit Sub Total** | **M3** | | **1** | **230.00** | **$150.00** | **$34,500.00** |
| | **Item Code 192035 Total No. of Proj.** | | | **2** | | **Total Amount** | **$706,500.00** |
| **192036** | STRUCTURE EXCAVATION (CRIB WALL) | M3 | 5 | 1 | 560.00 | $28.00 | $15,680.00 |
| | **Unit Sub Total** | **M3** | | **1** | **560.00** | **$28.00** | **$15,680.00** |
| | **Item Code 192036 Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,680.00** |
| **192037** | STRUCTURE EXCAVATION (RETAINING WALL) | CY | 4 | 1 | 130.00 | $30.00 | $3,900.00 |
| | | CY | 7 | 1 | 592.00 | $30.00 | $17,760.00 |
| | | CY | 8 | 1 | 450.00 | $75.00 | $33,750.00 |
| | | CY | 12 | 2 | 10,724.00 | $25.58 | $274,364.00 |
| | **Unit Sub Total** | **CY** | | **5** | **11,896.00** | **$27.72** | **$329,774.00** |
| **192037** | STRUCTURE EXCAVATION (RETAINING WALL) | M3 | 1 | 2 | 210.00 | $165.71 | $34,800.00 |
| | | M3 | 2 | 1 | 5,147.00 | $85.00 | $437,495.00 |
| | | M3 | 3 | 3 | 8,652.00 | $42.57 | $368,280.00 |
| | | M3 | 4 | 5 | 33,719.00 | $38.59 | $1,301,147.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **192037** | STRUCTURE EXCAVATION (RETAINING WALL) | M3 | 5 | 5 | 9,587.00 | $55.60 | $533,010.00 |
| | | M3 | 7 | 6 | 44,968.00 | $59.93 | $2,694,845.60 |
| | | M3 | 8 | 1 | 280.00 | $230.00 | $64,400.00 |
| | | M3 | 9 | 1 | 2,610.00 | $13.00 | $33,930.00 |
| | | M3 | 10 | 1 | 1,560.00 | $180.00 | $280,800.00 |
| | | M3 | 11 | 8 | 96,791.00 | $54.45 | $5,269,817.00 |
| | **Unit Sub Total** | **M3** | | **33** | **203,524.00** | **$54.14** | **$11,018,524.60** |
| | **Item Code 192037 Total No. of Proj.** | | | **38** | | **Total Amount** | **$11,348,298.60** |
| **192038** | STRUCTURE EXCAVATION (SOUND WALL) | M3 | 7 | 1 | 80.00 | $120.00 | $9,600.00 |
| | **Unit Sub Total** | **M3** | | **1** | **80.00** | **$120.00** | **$9,600.00** |
| | **Item Code 192038 Total No. of Proj.** | | | **1** | | **Total Amount** | **$9,600.00** |
| **192049** | STRUCTURE EXCAVATION (SOLDIER PILE WALL) | CY | 1 | 1 | 1,070.00 | $50.00 | $53,500.00 |
| | **Unit Sub Total** | **CY** | | **1** | **1,070.00** | **$50.00** | **$53,500.00** |
| **192049** | STRUCTURE EXCAVATION (SOLDIER PILE WALL) | M3 | 1 | 2 | 412.00 | $118.87 | $48,976.00 |
| | | M3 | 4 | 2 | 1,100.00 | $35.31 | $38,840.00 |
| | | M3 | 5 | 1 | 270.00 | $25.00 | $6,750.00 |
| | | M3 | 7 | 1 | 78.00 | $80.00 | $6,240.00 |
| | | M3 | 11 | 4 | 2,395.00 | $35.73 | $85,580.00 |
| | **Unit Sub Total** | **M3** | | **10** | **4,255.00** | **$43.80** | **$186,386.00** |
| | **Item Code 192049 Total No. of Proj.** | | | **11** | | **Total Amount** | **$239,886.00** |
| **192050** | STRUCTURE EXCAVATION (TIEBACK WALL) | M3 | 3 | 1 | 1,270.00 | $47.00 | $59,690.00 |
| | | M3 | 4 | 2 | 428.00 | $277.15 | $118,620.00 |
| | | M3 | 11 | 1 | 865.00 | $290.00 | $250,850.00 |
| | **Unit Sub Total** | **M3** | | **4** | **2,563.00** | **$167.44** | **$429,160.00** |
| | **Item Code 192050 Total No. of Proj.** | | | **4** | | **Total Amount** | **$429,160.00** |
| **192053** | STRUCTURE EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD) | M3 | 7 | 1 | 1,376.00 | $200.00 | $275,200.00 |
| | **Unit Sub Total** | **M3** | | **1** | **1,376.00** | **$200.00** | **$275,200.00** |
| | **Item Code 192053 Total No. of Proj.** | | | **1** | | **Total Amount** | **$275,200.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **192054** | STRUCTURE EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD) | M3 | 7 | 1 | 483.00 | $340.00 | $164,220.00 |
| | **Unit Sub Total** | **M3** | | **1** | **483.00** | **$340.00** | **$164,220.00** |
| | **Item Code 192054 Total No. of Proj.** | | | **1** | | **Total Amount** | **$164,220.00** |
| **192055** | STRUCTURE EXCAVATION (SOIL NAIL WALL) | CY | 2 | 1 | 16.00 | $300.00 | $4,800.00 |
| | **Unit Sub Total** | **CY** | | **1** | **16.00** | **$300.00** | **$4,800.00** |
| **192055** | STRUCTURE EXCAVATION (SOIL NAIL WALL) | M3 | 4 | 3 | 1,311.00 | $64.15 | $84,096.00 |
| | | M3 | 5 | 1 | 940.00 | $12.50 | $11,750.00 |
| | | M3 | 7 | 1 | 60.00 | $80.00 | $4,800.00 |
| | | M3 | 8 | 1 | 53.00 | $297.00 | $15,741.00 |
| | | M3 | 11 | 3 | 890.00 | $115.65 | $102,925.00 |
| | **Unit Sub Total** | **M3** | | **9** | **3,254.00** | **$67.40** | **$219,312.00** |
| | **Item Code 192055 Total No. of Proj.** | | | **10** | | **Total Amount** | **$224,112.00** |
| **192057** | STRUCTURE EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD) | M3 | 7 | 2 | 451.00 | $31.57 | $14,240.00 |
| | **Unit Sub Total** | **M3** | | **2** | **451.00** | **$31.57** | **$14,240.00** |
| | **Item Code 192057 Total No. of Proj.** | | | **2** | | **Total Amount** | **$14,240.00** |
| **193001** | STRUCTURE BACKFILL | CY | 2 | 2 | 84.00 | $151.07 | $12,690.00 |
| | | CY | 3 | 1 | 82.00 | $80.00 | $6,560.00 |
| | **Unit Sub Total** | **CY** | | **3** | **166.00** | **$115.96** | **$19,250.00** |
| **193001** | STRUCTURE BACKFILL | M3 | 3 | 1 | 415.00 | $200.00 | $83,000.00 |
| | **Unit Sub Total** | **M3** | | **1** | **415.00** | **$200.00** | **$83,000.00** |
| | **Item Code 193001 Total No. of Proj.** | | | **4** | | **Total Amount** | **$102,250.00** |
| **193003** | STRUCTURE BACKFILL (BRIDGE) | CY | 2 | 1 | 6.00 | $309.00 | $1,854.00 |
| | | CY | 4 | 1 | 99.00 | $50.00 | $4,950.00 |
| | | CY | 7 | 1 | 179.00 | $140.00 | $25,060.00 |
| | | CY | 8 | 1 | 1,914.00 | $80.00 | $153,120.00 |
| | | CY | 10 | 1 | 1.50 | $600.00 | $900.00 |
| | | CY | 11 | 1 | 5.00 | $1,512.00 | $7,560.00 |
| | | CY | 12 | 1 | 268.00 | $163.00 | $43,684.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **CY** | | **7** | **2,472.50** | **$95.91** | **$237,128.00** |
| **193003** | STRUCTURE BACKFILL (BRIDGE) | | M3 | 1 | 3 | 946.00 | $130.25 | $123,215.00 |
| | | | M3 | 2 | 4 | 1,859.00 | $79.25 | $147,325.00 |
| | | | M3 | 3 | 4 | 6,379.00 | $186.46 | $1,189,460.00 |
| | | | M3 | 4 | 5 | 1,673.00 | $141.63 | $236,944.00 |
| | | | M3 | 5 | 2 | 3,014.00 | $70.66 | $212,974.00 |
| | | | M3 | 6 | 1 | 11.00 | $400.00 | $4,400.00 |
| | | | M3 | 7 | 7 | 4,018.00 | $84.89 | $341,070.00 |
| | | | M3 | 8 | 1 | 2,247.00 | $90.00 | $202,230.00 |
| | | | M3 | 9 | 1 | 865.00 | $80.00 | $69,200.00 |
| | | | M3 | 10 | 2 | 4,130.00 | $33.78 | $139,497.00 |
| | | | M3 | 11 | 9 | 20,451.00 | $55.49 | $1,134,788.00 |
| | | **Unit Sub Total** | **M3** | | **39** | **45,593.00** | **$83.37** | **$3,801,103.00** |
| | **Item Code 193003** | **Total No. of Proj.** | | | **46** | | **Total Amount** | **$4,038,231.00** |
| **193004** | STRUCTURE BACKFILL (CULVERT) | | M3 | 4 | 1 | 161.40 | $135.00 | $21,789.00 |
| | | | M3 | 7 | 1 | 365.00 | $220.00 | $80,300.00 |
| | | **Unit Sub Total** | **M3** | | **2** | **526.40** | **$193.94** | **$102,089.00** |
| | **Item Code 193004** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$102,089.00** |
| **193006** | STRUCTURE BACKFILL (SLURRY CEMENT) | | CY | 3 | 2 | 153.00 | $391.18 | $59,850.00 |
| | | | CY | 9 | 1 | 0.60 | $1,900.00 | $1,140.00 |
| | | **Unit Sub Total** | **CY** | | **3** | **153.60** | **$397.07** | **$60,990.00** |
| **193006** | STRUCTURE BACKFILL (SLURRY CEMENT) | | M3 | 4 | 1 | 93.00 | $108.47 | $10,087.71 |
| | | | M3 | 5 | 1 | 410.00 | $130.00 | $53,300.00 |
| | | | M3 | 10 | 1 | 16.00 | $105.00 | $1,680.00 |
| | | **Unit Sub Total** | **M3** | | **3** | **519.00** | **$125.37** | **$65,067.71** |
| | **Item Code 193006** | **Total No. of Proj.** | | | **6** | | **Total Amount** | **$126,057.71** |
| **193012** | STRUCTURE BACKFILL (CRIB WALL) | | M3 | 5 | 1 | 1,040.00 | $25.50 | $26,520.00 |
| | | **Unit Sub Total** | **M3** | | **1** | **1,040.00** | **$25.50** | **$26,520.00** |
| | **Item Code 193012** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$26,520.00** |
| **193013** | STRUCTURE BACKFILL (RETAINING WALL) | | CY | 4 | 1 | 130.00 | $50.00 | $6,500.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **193013** | STRUCTURE BACKFILL (RETAINING WALL) | CY | 7 | 1 | 632.00 | $40.00 | $25,280.00 |
| | | CY | 8 | 1 | 975.00 | $140.00 | $136,500.00 |
| | | CY | 12 | 2 | 15,870.00 | $19.75 | $313,398.00 |
| | **Unit Sub Total** | **CY** | | **5** | **17,607.00** | **$27.36** | **$481,678.00** |
| **193013** | STRUCTURE BACKFILL (RETAINING WALL) | M3 | 1 | 2 | 145.00 | $77.59 | $11,250.00 |
| | | M3 | 2 | 1 | 4,494.00 | $90.00 | $404,460.00 |
| | | M3 | 3 | 3 | 7,444.00 | $53.80 | $400,489.00 |
| | | M3 | 4 | 5 | 25,773.00 | $49.96 | $1,287,602.50 |
| | | M3 | 5 | 5 | 9,527.00 | $49.20 | $468,731.00 |
| | | M3 | 7 | 6 | 35,525.00 | $57.47 | $2,041,604.00 |
| | | M3 | 8 | 1 | 140.00 | $180.00 | $25,200.00 |
| | | M3 | 9 | 1 | 1,970.00 | $22.00 | $43,340.00 |
| | | M3 | 10 | 2 | 3,850.00 | $40.42 | $155,600.00 |
| | | M3 | 11 | 8 | 118,114.00 | $51.43 | $6,074,925.00 |
| | **Unit Sub Total** | **M3** | | **34** | **206,982.00** | **$52.73** | **$10,913,201.50** |
| | **Item Code 193013** **Total No. of Proj.** | | | **39** | | **Total Amount** | **$11,394,879.50** |
| **193014** | STRUCTURE BACKFILL (SOUND WALL) | M3 | 7 | 1 | 70.00 | $100.00 | $7,000.00 |
| | **Unit Sub Total** | **M3** | | **1** | **70.00** | **$100.00** | **$7,000.00** |
| | **Item Code 193014** **Total No. of Proj.** | | | **1** | | **Total Amount** | **$7,000.00** |
| **193026** | STRUCTURE BACKFILL (TIEBACK WALL) | M3 | 3 | 1 | 163.00 | $57.00 | $9,291.00 |
| | | M3 | 4 | 2 | 32.00 | $342.28 | $10,953.00 |
| | | M3 | 11 | 1 | 44.00 | $650.00 | $28,600.00 |
| | **Unit Sub Total** | **M3** | | **4** | **239.00** | **$204.37** | **$48,844.00** |
| | **Item Code 193026** **Total No. of Proj.** | | | **4** | | **Total Amount** | **$48,844.00** |
| **193028** | STRUCTURE BACKFILL (SOIL NAIL WALL) | CY | 2 | 1 | 8.00 | $200.00 | $1,600.00 |
| | **Unit Sub Total** | **CY** | | **1** | **8.00** | **$200.00** | **$1,600.00** |
| **193028** | STRUCTURE BACKFILL (SOIL NAIL WALL) | M3 | 4 | 3 | 40.00 | $183.15 | $7,326.00 |
| | | M3 | 5 | 1 | 115.00 | $100.00 | $11,500.00 |
| | | M3 | 8 | 1 | 11.00 | $370.00 | $4,070.00 |
| | | M3 | 11 | 3 | 80.00 | $319.38 | $25,550.00 |
| | **Unit Sub Total** | **M3** | | **8** | **246.00** | **$196.93** | **$48,446.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 193028 Total No. of Proj.** | | | **9** | | **Total Amount** | **$50,046.00** |
| **193029** | STRUCTURE BACKFILL (SOLDIER PILE WALL) | CY | 1 | 1 | 735.00 | $50.00 | $36,750.00 |
| | | CY | 8 | 1 | 22.00 | $2,000.00 | $44,000.00 |
| | **Unit Sub Total** | **CY** | | **2** | **757.00** | **$106.67** | **$80,750.00** |
| **193029** | STRUCTURE BACKFILL (SOLDIER PILE WALL) | M3 | 1 | 2 | 119.00 | $111.38 | $13,254.00 |
| | | M3 | 4 | 2 | 108.00 | $31.90 | $3,445.00 |
| | | M3 | 5 | 1 | 60.00 | $88.00 | $5,280.00 |
| | | M3 | 7 | 1 | 17.00 | $240.00 | $4,080.00 |
| | | M3 | 11 | 4 | 195.00 | $153.13 | $29,860.00 |
| | **Unit Sub Total** | **M3** | | **10** | **499.00** | **$112.06** | **$55,919.00** |
| | **Item Code 193029 Total No. of Proj.** | | | **12** | | **Total Amount** | **$136,669.00** |
| **193030** | PERVIOUS BACKFILL MATERIAL | M3 | 1 | 1 | 15.00 | $88.00 | $1,320.00 |
| | | M3 | 2 | 1 | 413.00 | $225.00 | $92,925.00 |
| | | M3 | 3 | 2 | 12.00 | $226.67 | $2,720.00 |
| | | M3 | 7 | 1 | 358.00 | $125.00 | $44,750.00 |
| | | M3 | 11 | 1 | 70.00 | $123.00 | $8,610.00 |
| | **Unit Sub Total** | **M3** | | **6** | **868.00** | **$173.19** | **$150,325.00** |
| | **Item Code 193030 Total No. of Proj.** | | | **6** | | **Total Amount** | **$150,325.00** |
| **193031** | PERVIOUS BACKFILL MATERIAL (RETAINING WALL) | M3 | 1 | 1 | 17.00 | $75.00 | $1,275.00 |
| | | M3 | 3 | 2 | 1,312.00 | $84.59 | $110,985.00 |
| | | M3 | 4 | 3 | 588.00 | $92.13 | $54,175.00 |
| | | M3 | 5 | 2 | 97.50 | $84.15 | $8,205.00 |
| | | M3 | 7 | 2 | 2,577.00 | $109.72 | $282,750.00 |
| | | M3 | 10 | 1 | 340.00 | $120.00 | $40,800.00 |
| | | M3 | 11 | 8 | 7,238.00 | $90.94 | $658,252.00 |
| | **Unit Sub Total** | **M3** | | **19** | **12,169.50** | **$95.03** | **$1,156,442.00** |
| | **Item Code 193031 Total No. of Proj.** | | | **19** | | **Total Amount** | **$1,156,442.00** |
| **193101** | GRAVEL BLANKET | M3 | 11 | 1 | 2,290.00 | $65.00 | $148,850.00 |
| | **Unit Sub Total** | **M3** | | **1** | **2,290.00** | **$65.00** | **$148,850.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | **Item Code 193101** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$148,850.00** |
| **193114** | SAND BACKFILL | | CY | 2 | 3 | 122.00 | $152.11 | $18,557.00 |
| | | | CY | 3 | 3 | 38.00 | $184.21 | $7,000.00 |
| | | | CY | 7 | 1 | 88.00 | $200.00 | $17,600.00 |
| | | | CY | 11 | 2 | 138.00 | $112.26 | $15,492.00 |
| | | | CY | 12 | 1 | 15.00 | $80.00 | $1,200.00 |
| | | **Unit Sub Total** | **CY** | | **10** | **401.00** | **$149.25** | **$59,849.00** |
| **193114** | SAND BACKFILL | | M3 | 2 | 3 | 130.00 | $278.85 | $36,250.00 |
| | | | M3 | 3 | 2 | 27.00 | $238.89 | $6,450.00 |
| | | | M3 | 4 | 5 | 425.00 | $172.75 | $73,420.00 |
| | | | M3 | 5 | 2 | 390.00 | $25.44 | $9,920.00 |
| | | | M3 | 6 | 1 | 14.00 | $205.00 | $2,870.00 |
| | | | M3 | 7 | 2 | 36.70 | $163.08 | $5,985.00 |
| | | | M3 | 8 | 2 | 68.00 | $259.41 | $17,640.00 |
| | | | M3 | 9 | 2 | 50.00 | $201.20 | $10,060.00 |
| | | | M3 | 10 | 1 | 440.00 | $40.00 | $17,600.00 |
| | | | M3 | 11 | 8 | 2,460.00 | $163.14 | $401,329.00 |
| | | **Unit Sub Total** | **M3** | | **28** | **4,040.70** | **$143.92** | **$581,524.00** |
| | **Item Code 193114** | **Total No. of Proj.** | | | **38** | | **Total Amount** | **$641,373.00** |
| **193117** | CONCRETE BACKFILL FAST SETTING | | M3 | 4 | 1 | 22.00 | $400.00 | $8,800.00 |
| | | **Unit Sub Total** | **M3** | | **1** | **22.00** | **$400.00** | **$8,800.00** |
| | **Item Code 193117** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$8,800.00** |
| **193118** | CONCRETE BACKFILL | | CY | 6 | 1 | 5.00 | $175.00 | $875.00 |
| | | **Unit Sub Total** | **CY** | | **1** | **5.00** | **$175.00** | **$875.00** |
| **193118** | CONCRETE BACKFILL | | M3 | 4 | 3 | 330.00 | $196.85 | $64,960.00 |
| | | | M3 | 6 | 1 | 36.00 | $450.00 | $16,200.00 |
| | | | M3 | 10 | 1 | 38.00 | $167.00 | $6,346.00 |
| | | **Unit Sub Total** | **M3** | | **5** | **404.00** | **$216.60** | **$87,506.00** |
| | **Item Code 193118** | **Total No. of Proj.** | | | **6** | | **Total Amount** | **$88,381.00** |
| **193119** | LEAN CONCRETE BACKFILL | | CY | 1 | 1 | 1,043.00 | $110.00 | $114,730.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **193119** | LEAN CONCRETE BACKFILL | | CY | 8 | 1 | 20.00 | $120.00 | $2,400.00 |
| | | **Unit Sub Total** | **CY** | | **2** | **1,063.00** | **$110.19** | **$117,130.00** |
| **193119** | LEAN CONCRETE BACKFILL | | M3 | 1 | 2 | 286.00 | $294.18 | $84,136.00 |
| | | | M3 | 4 | 2 | 102.00 | $240.20 | $24,500.00 |
| | | | M3 | 5 | 1 | 140.00 | $220.00 | $30,800.00 |
| | | | M3 | 7 | 2 | 19.00 | $326.32 | $6,200.00 |
| | | | M3 | 11 | 5 | 3,335.00 | $167.88 | $559,890.00 |
| | | **Unit Sub Total** | **M3** | | **12** | **3,882.00** | **$181.74** | **$705,526.00** |
| | **Item Code 193119** | **Total No. of Proj.** | | | **14** | | **Total Amount** | **$822,656.00** |
| **194001** | DITCH EXCAVATION | | CY | 1 | 3 | 960.00 | $15.55 | $14,930.00 |
| | | | CY | 2 | 3 | 98.00 | $49.24 | $4,826.00 |
| | | | CY | 3 | 3 | 1,570.00 | $16.53 | $25,955.00 |
| | | | CY | 6 | 1 | 45.00 | $100.00 | $4,500.00 |
| | | | CY | 7 | 2 | 91.00 | $65.22 | $5,935.00 |
| | | | CY | 10 | 1 | 250.00 | $21.00 | $5,250.00 |
| | | | CY | 11 | 1 | 120.00 | $42.00 | $5,040.00 |
| | | **Unit Sub Total** | **CY** | | **14** | **3,134.00** | **$21.20** | **$66,436.00** |
| **194001** | DITCH EXCAVATION | | M3 | 1 | 2 | 4,320.00 | $11.11 | $48,000.00 |
| | | | M3 | 2 | 3 | 1,280.00 | $14.82 | $18,969.20 |
| | | | M3 | 3 | 2 | 26,600.00 | $5.14 | $136,600.00 |
| | | | M3 | 4 | 6 | 4,980.00 | $31.42 | $156,485.53 |
| | | | M3 | 5 | 3 | 329.00 | $58.04 | $19,096.00 |
| | | | M3 | 6 | 1 | 160.00 | $51.00 | $8,160.00 |
| | | | M3 | 7 | 3 | 348.00 | $26.72 | $9,300.00 |
| | | | M3 | 8 | 3 | 1,690.00 | $44.53 | $75,250.00 |
| | | | M3 | 9 | 4 | 990.00 | $16.96 | $16,790.00 |
| | | | M3 | 11 | 6 | 6,375.00 | $12.37 | $78,845.00 |
| | | | M3 | 12 | 1 | 860.00 | $20.00 | $17,200.00 |
| | | **Unit Sub Total** | **M3** | | **34** | **47,932.00** | **$12.20** | **$584,695.73** |
| | **Item Code 194001** | **Total No. of Proj.** | | | **48** | | **Total Amount** | **$651,131.73** |
| **197020** | EARTH RETAINING STRUCTURE | | SQYD | 2 | 1 | 140.00 | $495.00 | $69,300.00 |
| | | **Unit Sub Total** | **SQYD** | | **1** | **140.00** | **$495.00** | **$69,300.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 197020 Total No. of Proj.** | | | **1** | | **Total Amount** | **$69,300.00** |
| **197021** | EARTH RETAINING STRUCTURE, LOCATION A | M2 | 11 | 2 | 1,455.00 | $598.25 | $870,450.00 |
| | **Unit Sub Total** | **M2** | | **2** | **1,455.00** | **$598.25** | **$870,450.00** |
| | **Item Code 197021 Total No. of Proj.** | | | **2** | | **Total Amount** | **$870,450.00** |
| **197022** | EARTH RETAINING STRUCTURE, LOCATION B | M2 | 11 | 2 | 2,640.00 | $540.00 | $1,425,600.00 |
| | **Unit Sub Total** | **M2** | | **2** | **2,640.00** | **$540.00** | **$1,425,600.00** |
| | **Item Code 197022 Total No. of Proj.** | | | **2** | | **Total Amount** | **$1,425,600.00** |
| **197023** | EARTH RETAINING STRUCTURE, LOCATION C | M2 | 11 | 2 | 4,265.00 | $539.59 | $2,301,350.00 |
| | **Unit Sub Total** | **M2** | | **2** | **4,265.00** | **$539.59** | **$2,301,350.00** |
| | **Item Code 197023 Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,301,350.00** |
| **197024** | EARTH RETAINING STRUCTURE, LOCATION D | M2 | 11 | 1 | 980.00 | $490.00 | $480,200.00 |
| | **Unit Sub Total** | **M2** | | **1** | **980.00** | **$490.00** | **$480,200.00** |
| | **Item Code 197024 Total No. of Proj.** | | | **1** | | **Total Amount** | **$480,200.00** |
| **197060** | SOIL NAIL ASSEMBLY | LF | 2 | 1 | 322.00 | $170.00 | $54,740.00 |
| | **Unit Sub Total** | **LF** | | **1** | **322.00** | **$170.00** | **$54,740.00** |
| **197060** | SOIL NAIL ASSEMBLY | M | 4 | 3 | 5,005.00 | $102.27 | $511,874.00 |
| | | M | 5 | 1 | 3,030.00 | $93.00 | $281,790.00 |
| | | M | 7 | 1 | 36,370.00 | $70.00 | $2,545,900.00 |
| | | M | 8 | 1 | 256.00 | $160.00 | $40,960.00 |
| | | M | 11 | 3 | 2,395.00 | $150.86 | $361,300.00 |
| | **Unit Sub Total** | **M** | | **9** | **47,056.00** | **$79.52** | **$3,741,824.00** |
| | **Item Code 197060 Total No. of Proj.** | | | **10** | | **Total Amount** | **$3,796,564.00** |
| **198001** | IMPORTED BORROW | CY | 1 | 2 | 480.00 | $43.06 | $20,670.00 |
| | | CY | 3 | 8 | 18,088.00 | $24.40 | $441,426.00 |
| | | CY | 4 | 1 | 2,490.00 | $6.00 | $14,940.00 |
| | | CY | 5 | 2 | 143.00 | $118.18 | $16,900.00 |
| | | CY | 6 | 3 | 8,350.00 | $25.08 | $209,400.00 |
| | | CY | 7 | 5 | 535.00 | $67.36 | $36,039.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **198001** | IMPORTED BORROW | CY | 8 | 2 | 2,800.00 | $2.86 | $8,020.00 |
| | | CY | 9 | 1 | 270.00 | $37.50 | $10,125.00 |
| | | CY | 11 | 1 | 46.00 | $84.00 | $3,864.00 |
| | | CY | 12 | 2 | 1,045.00 | $27.27 | $28,500.00 |
| | **Unit Sub Total** | **CY** | | **27** | **34,247.00** | **$23.06** | **$789,884.00** |
| **198001** | IMPORTED BORROW | M3 | 1 | 3 | 240,370.00 | $19.18 | $4,611,400.00 |
| | | M3 | 2 | 1 | 140.00 | $100.00 | $14,000.00 |
| | | M3 | 3 | 4 | 1,252,190.00 | $10.49 | $13,134,620.00 |
| | | M3 | 4 | 4 | 20,165.00 | $6.90 | $139,074.00 |
| | | M3 | 5 | 3 | 4,820.00 | $18.73 | $90,300.00 |
| | | M3 | 6 | 4 | 41,630.00 | $14.24 | $592,680.00 |
| | | M3 | 7 | 11 | 124,075.00 | $9.90 | $1,228,120.00 |
| | | M3 | 8 | 1 | 2,800.00 | $36.90 | $103,320.00 |
| | | M3 | 9 | 4 | 127,670.00 | $12.56 | $1,602,935.00 |
| | | M3 | 10 | 4 | 210,040.00 | $14.31 | $3,004,982.50 |
| | | M3 | 11 | 4 | 1,271,650.00 | $9.21 | $11,715,350.00 |
| | | M3 | 12 | 1 | 3,590.00 | $20.00 | $71,800.00 |
| | **Unit Sub Total** | **M3** | | **44** | **3,299,140.00** | **$11.01** | **$36,308,581.50** |
| **198001** | IMPORTED BORROW | TON | 2 | 1 | 14,610.00 | $12.00 | $175,320.00 |
| | | TON | 3 | 1 | 1,400.00 | $25.00 | $35,000.00 |
| | | TON | 11 | 2 | 86.00 | $164.09 | $14,112.00 |
| | **Unit Sub Total** | **TON** | | **4** | **16,096.00** | **$13.94** | **$224,432.00** |
| | **Item Code 198001** **Total No. of Proj.** | | | **75** | | **Total Amount** | **$37,322,897.50** |
| **198007** | IMPORTED MATERIAL (SHOULDER BACKING) | CY | 3 | 1 | 11,300.00 | $49.00 | $553,700.00 |
| | **Unit Sub Total** | **CY** | | **1** | **11,300.00** | **$49.00** | **$553,700.00** |
| **198007** | IMPORTED MATERIAL (SHOULDER BACKING) | M3 | 1 | 2 | 270.00 | $107.22 | $28,950.00 |
| | | M3 | 2 | 2 | 890.00 | $77.70 | $69,150.00 |
| | | M3 | 3 | 1 | 340.00 | $75.00 | $25,500.00 |
| | | M3 | 5 | 1 | 6,760.00 | $26.00 | $175,760.00 |
| | **Unit Sub Total** | **M3** | | **6** | **8,260.00** | **$36.24** | **$299,360.00** |
| **198007** | IMPORTED MATERIAL (SHOULDER BACKING) | TON | 1 | 13 | 13,361.80 | $37.66 | $503,236.00 |
| | | TON | 2 | 14 | 30,037.00 | $26.81 | $805,177.00 |
| | | TON | 3 | 7 | 4,673.00 | $36.99 | $172,835.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **198007** | IMPORTED MATERIAL (SHOULDER BACKING) | TON | 4 | 8 | 14,631.00 | $19.97 | $292,199.00 |
| | | TON | 5 | 9 | 13,180.00 | $36.58 | $482,076.00 |
| | | TON | 6 | 8 | 10,470.00 | $38.66 | $404,727.50 |
| | | TON | 7 | 2 | 481.00 | $32.02 | $15,400.00 |
| | | TON | 9 | 6 | 10,120.00 | $49.41 | $499,990.00 |
| | | TON | 10 | 5 | 8,340.00 | $32.48 | $270,910.00 |
| | | TON | 11 | 3 | 1,260.00 | $42.43 | $53,464.50 |
| | | TON | 12 | 1 | 540.00 | $26.00 | $14,040.00 |
| | **Unit Sub Total** | **TON** | | **76** | **107,093.80** | **$32.81** | **$3,514,055.00** |
| **198007** | IMPORTED MATERIAL (SHOULDER BACKING) | TONN | 1 | 2 | 320.00 | $63.13 | $20,200.00 |
| | | TONN | 2 | 1 | 14.00 | $250.00 | $3,500.00 |
| | | TONN | 4 | 5 | 17,410.00 | $22.38 | $389,630.00 |
| | | TONN | 5 | 4 | 98.00 | $167.74 | $16,438.50 |
| | | TONN | 6 | 3 | 20,570.00 | $6.63 | $136,335.00 |
| | | TONN | 9 | 1 | 76.00 | $15.00 | $1,140.00 |
| | | TONN | 10 | 3 | 3,750.00 | $35.07 | $131,525.00 |
| | **Unit Sub Total** | **TONN** | | **19** | **42,238.00** | **$16.54** | **$698,768.50** |
| | **Item Code 198007 Total No. of Proj.** | | | **102** | | **Total Amount** | **$5,065,883.50** |
| **198020** | IMPORTED RIVER GRAVEL | CY | 1 | 1 | 90.00 | $90.00 | $8,100.00 |
| | **Unit Sub Total** | **CY** | | **1** | **90.00** | **$90.00** | **$8,100.00** |
| **198020** | IMPORTED RIVER GRAVEL | M3 | 3 | 1 | 19.00 | $182.77 | $3,472.63 |
| | **Unit Sub Total** | **M3** | | **1** | **19.00** | **$182.77** | **$3,472.63** |
| | **Item Code 198020 Total No. of Proj.** | | | **2** | | **Total Amount** | **$11,572.63** |
| **198021** | IMPORTED ROCKY MATERIAL | M3 | 1 | 1 | 80.00 | $150.00 | $12,000.00 |
| | **Unit Sub Total** | **M3** | | **1** | **80.00** | **$150.00** | **$12,000.00** |
| | **Item Code 198021 Total No. of Proj.** | | | **1** | | **Total Amount** | **$12,000.00** |
| **198050** | EMBANKMENT | CY | 4 | 1 | 120.00 | $50.00 | $6,000.00 |
| | **Unit Sub Total** | **CY** | | **1** | **120.00** | **$50.00** | **$6,000.00** |
| **198050** | EMBANKMENT | M3 | 7 | 1 | 1,490.00 | $220.00 | $327,800.00 |
| | | M3 | 11 | 1 | 53,700.00 | $5.00 | $268,500.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M3** | | **2** | **55,190.00** | **$10.80** | **$596,300.00** |
| | **Item Code 198050** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$602,300.00** |
| **198200** | SUBGRADE ENHANCEMENT FABRIC | | M2 | 2 | 1 | 9,310.00 | $2.00 | $18,620.00 |
| | | | M2 | 3 | 1 | 75.00 | $30.00 | $2,250.00 |
| | | | M2 | 4 | 1 | 740.00 | $8.50 | $6,290.00 |
| | | **Unit Sub Total** | **M2** | | **3** | **10,125.00** | **$2.68** | **$27,160.00** |
| **198200** | SUBGRADE ENHANCEMENT FABRIC | | SQYD | 1 | 1 | 7.00 | $200.00 | $1,400.00 |
| | | | SQYD | 3 | 1 | 7,810.00 | $2.00 | $15,620.00 |
| | | **Unit Sub Total** | **SQYD** | | **2** | **7,817.00** | **$2.18** | **$17,020.00** |
| | **Item Code 198200** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$44,180.00** |
| **200001** | HIGHWAY PLANTING | | LS | 1 | 3 | 3.00 | $12,600.00 | $37,800.00 |
| | | | LS | 2 | 4 | 4.00 | $40,665.75 | $162,663.00 |
| | | | LS | 3 | 4 | 4.00 | $55,000.00 | $220,000.00 |
| | | | LS | 4 | 4 | 4.00 | $35,250.00 | $141,000.00 |
| | | | LS | 5 | 14 | 14.00 | $51,673.83 | $723,433.67 |
| | | | LS | 6 | 5 | 5.00 | $53,100.00 | $265,500.00 |
| | | | LS | 7 | 15 | 15.00 | $30,026.67 | $450,400.00 |
| | | | LS | 8 | 5 | 5.00 | $23,490.00 | $117,450.00 |
| | | | LS | 9 | 1 | 1.00 | $3,100.00 | $3,100.00 |
| | | | LS | 10 | 1 | 1.00 | $13,260.00 | $13,260.00 |
| | | | LS | 11 | 10 | 10.00 | $67,035.36 | $670,353.63 |
| | | | LS | 12 | 8 | 8.00 | $17,454.00 | $139,632.00 |
| | | **Unit Sub Total** | **LS** | | **74** | **74.00** | **$39,791.79** | **$2,944,592.30** |
| | **Item Code 200001** | **Total No. of Proj.** | | | **74** | | **Total Amount** | **$2,944,592.30** |
| **200002** | ROADSIDE CLEARING | | LS | 3 | 1 | 1.00 | $4,722.06 | $4,722.06 |
| | | | LS | 4 | 3 | 3.00 | $7,786.33 | $23,359.00 |
| | | | LS | 5 | 1 | 1.00 | $2,500.00 | $2,500.00 |
| | | | LS | 6 | 3 | 3.00 | $42,422.79 | $127,268.36 |
| | | | LS | 8 | 2 | 2.00 | $11,250.00 | $22,500.00 |
| | | | LS | 10 | 1 | 1.00 | $15,700.00 | $15,700.00 |
| | | | LS | 11 | 4 | 4.00 | $23,625.00 | $94,500.00 |
| | | | LS | 12 | 1 | 1.00 | $96,228.03 | $96,228.03 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **LS** | | **16** | **16.00** | **$24,173.59** | **$386,777.45** |
| | **Item Code 200002** | **Total No. of Proj.** | | | **16** | | **Total Amount** | **$386,777.45** |
| **200052** | PRUNE EXISTING PLANTS | | LS | 3 | 2 | 2.00 | $9,494.56 | $18,989.12 |
| | | | LS | 5 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | | | LS | 6 | 1 | 1.00 | $20,000.00 | $20,000.00 |
| | | | LS | 7 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | | | LS | 8 | 2 | 2.00 | $5,350.00 | $10,700.00 |
| | | | LS | 12 | 1 | 1.00 | $20,171.00 | $20,171.00 |
| | | **Unit Sub Total** | **LS** | | **8** | **8.00** | **$12,107.52** | **$96,860.12** |
| | **Item Code 200052** | **Total No. of Proj.** | | | **8** | | **Total Amount** | **$96,860.12** |
| **200101** | IMPORTED TOPSOIL | | CY | 1 | 2 | 380.00 | $52.05 | $19,780.00 |
| | | | CY | 2 | 1 | 25.00 | $80.00 | $2,000.00 |
| | | | CY | 3 | 1 | 2,440.00 | $44.00 | $107,360.00 |
| | | | CY | 8 | 2 | 2,032.00 | $28.35 | $57,600.00 |
| | | **Unit Sub Total** | **CY** | | **6** | **4,877.00** | **$38.29** | **$186,740.00** |
| **200101** | IMPORTED TOPSOIL | | M3 | 1 | 1 | 100.00 | $85.00 | $8,500.00 |
| | | | M3 | 2 | 2 | 3,030.00 | $76.00 | $230,290.00 |
| | | | M3 | 3 | 1 | 580.00 | $20.00 | $11,600.00 |
| | | | M3 | 5 | 3 | 1,802.00 | $38.04 | $68,540.00 |
| | | | M3 | 6 | 1 | 350.00 | $65.00 | $22,750.00 |
| | | | M3 | 11 | 4 | 3,170.00 | $49.15 | $155,810.00 |
| | | | M3 | 12 | 1 | 290.00 | $100.00 | $29,000.00 |
| | | **Unit Sub Total** | **M3** | | **13** | **9,322.00** | **$56.48** | **$526,490.00** |
| | **Item Code 200101** | **Total No. of Proj.** | | | **19** | | **Total Amount** | **$713,230.00** |
| **200114** | ROCK BLANKET | | M2 | 2 | 1 | 750.00 | $45.00 | $33,750.00 |
| | | | M2 | 3 | 2 | 3,510.00 | $77.85 | $273,240.00 |
| | | | M2 | 6 | 1 | 1,640.00 | $76.00 | $124,640.00 |
| | | | M2 | 7 | 1 | 110.00 | $158.13 | $17,394.30 |
| | | | M2 | 8 | 1 | 4,070.00 | $85.00 | $345,950.00 |
| | | | M2 | 11 | 1 | 40.00 | $200.00 | $8,000.00 |
| | | **Unit Sub Total** | **M2** | | **7** | **10,120.00** | **$79.35** | **$802,974.30** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **200114** | ROCK BLANKET | | SQYD | 10 | 1 | 850.00 | $39.00 | $33,150.00 |
| | | | SQYD | 12 | 2 | 740.00 | $99.32 | $73,496.70 |
| | | **Unit Sub Total** | **SQYD** | | **3** | **1,590.00** | **$67.07** | **$106,646.70** |
| | **Item Code 200114** | **Total No. of Proj.** | | | **10** | | **Total Amount** | **$909,621.00** |
| **202003** | IRON SULFATE | | KG | 11 | 2 | 3,540.00 | $1.43 | $5,065.20 |
| | | **Unit Sub Total** | **KG** | | **2** | **3,540.00** | **$1.43** | **$5,065.20** |
| **202003** | IRON SULFATE | | LB | 8 | 1 | 320.00 | $1.89 | $604.80 |
| | | | LB | 11 | 2 | 1,130.00 | $1.56 | $1,767.00 |
| | | | LB | 12 | 1 | 260.00 | $0.55 | $143.00 |
| | | **Unit Sub Total** | **LB** | | **4** | **1,710.00** | **$1.47** | **$2,514.80** |
| | **Item Code 202003** | **Total No. of Proj.** | | | **6** | | **Total Amount** | **$7,580.00** |
| **202006** | SOIL AMENDMENT | | CY | 3 | 1 | 100.00 | $56.54 | $5,654.00 |
| | | | CY | 4 | 1 | 20.00 | $30.00 | $600.00 |
| | | | CY | 6 | 1 | 6.00 | $22.00 | $132.00 |
| | | | CY | 12 | 1 | 37.00 | $10.60 | $392.20 |
| | | **Unit Sub Total** | **CY** | | **4** | **163.00** | **$41.58** | **$6,778.20** |
| **202006** | SOIL AMENDMENT | | M3 | 4 | 1 | 140.00 | $69.34 | $9,707.60 |
| | | | M3 | 6 | 1 | 68.00 | $62.00 | $4,216.00 |
| | | **Unit Sub Total** | **M3** | | **2** | **208.00** | **$66.94** | **$13,923.60** |
| | **Item Code 202006** | **Total No. of Proj.** | | | **6** | | **Total Amount** | **$20,701.80** |
| **202007** | DUFF | | HA | 9 | 2 | 52.00 | $6,511.54 | $338,600.00 |
| | | **Unit Sub Total** | **HA** | | **2** | **52.00** | **$6,511.54** | **$338,600.00** |
| **202007** | DUFF | | M2 | 5 | 3 | 20,300.00 | $0.86 | $17,506.30 |
| | | | M2 | 7 | 3 | 124,700.00 | $0.76 | $94,510.00 |
| | | | M2 | 9 | 2 | 30,010.00 | $2.00 | $60,010.00 |
| | | | M2 | 10 | 3 | 8,300.00 | $3.86 | $32,000.00 |
| | | | M2 | 11 | 2 | 62,440.00 | $5.26 | $328,440.00 |
| | | **Unit Sub Total** | **M2** | | **13** | **245,750.00** | **$2.17** | **$532,466.30** |
| **202007** | DUFF | | SQYD | 2 | 1 | 1,550.00 | $5.00 | $7,750.00 |
| | | | SQYD | 3 | 4 | 3,730.00 | $5.51 | $20,562.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **202007** | DUFF | SQYD | 5 | 1 | 1,560.00 | $12.00 | $18,720.00 |
| | | SQYD | 8 | 1 | 1,770.00 | $5.00 | $8,850.00 |
| | | SQYD | 11 | 1 | 20.00 | $120.00 | $2,400.00 |
| | **Unit Sub Total** | **SQYD** | | **8** | **8,630.00** | **$6.75** | **$58,282.00** |
| | **Item Code 202007 Total No. of Proj.** | | | **23** | | **Total Amount** | **$929,348.30** |
| **202011** | MULCH | CY | 3 | 6 | 833.00 | $53.65 | $44,688.60 |
| | | CY | 4 | 2 | 1,534.00 | $9.91 | $15,196.00 |
| | | CY | 5 | 2 | 28.00 | $70.36 | $1,970.00 |
| | | CY | 6 | 1 | 50.00 | $32.33 | $1,616.50 |
| | | CY | 7 | 1 | 2.00 | $345.00 | $690.00 |
| | | CY | 8 | 1 | 1,280.00 | $36.93 | $47,270.40 |
| | | CY | 10 | 1 | 150.00 | $30.10 | $4,515.00 |
| | | CY | 11 | 2 | 4,720.00 | $24.09 | $113,685.50 |
| | | CY | 12 | 1 | 151.00 | $25.20 | $3,805.20 |
| | **Unit Sub Total** | **CY** | | **17** | **8,748.00** | **$26.68** | **$233,437.20** |
| **202011** | MULCH | M3 | 3 | 1 | 61.00 | $95.00 | $5,795.00 |
| | | M3 | 4 | 1 | 260.00 | $33.43 | $8,691.80 |
| | | M3 | 5 | 1 | 15.00 | $165.00 | $2,475.00 |
| | | M3 | 6 | 1 | 9,570.00 | $27.00 | $258,390.00 |
| | | M3 | 7 | 3 | 4,300.00 | $43.17 | $185,620.00 |
| | | M3 | 10 | 1 | 3.00 | $155.00 | $465.00 |
| | | M3 | 11 | 2 | 2,340.00 | $37.57 | $87,919.50 |
| | **Unit Sub Total** | **M3** | | **10** | **16,549.00** | **$33.20** | **$549,356.30** |
| | **Item Code 202011 Total No. of Proj.** | | | **27** | | **Total Amount** | **$782,793.50** |
| **202030** | COMMERCIAL FERTILIZER (GRANULAR) | LB | 8 | 1 | 320.00 | $1.89 | $604.80 |
| | **Unit Sub Total** | **LB** | | **1** | **320.00** | **$1.89** | **$604.80** |
| | **Item Code 202030 Total No. of Proj.** | | | **1** | | **Total Amount** | **$604.80** |
| **202031** | COMMERCIAL FERTILIZER (SLOW RELEASE) | KG | 4 | 1 | 170.00 | $3.64 | $618.80 |
| | | KG | 6 | 1 | 820.00 | $2.00 | $1,640.00 |
| | | KG | 11 | 2 | 6,620.00 | $1.28 | $8,470.00 |
| | **Unit Sub Total** | **KG** | | **4** | **7,610.00** | **$1.41** | **$10,728.80** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **202031** | COMMERCIAL FERTILIZER (SLOW RELEASE) | LB | 4 | 1 | 34.00 | $1.00 | $34.00 |
| | | LB | 11 | 2 | 1,510.00 | $1.68 | $2,544.20 |
| | | LB | 12 | 1 | 7,250.00 | $0.53 | $3,842.50 |
| | **Unit Sub Total** | **LB** | | **4** | **8,794.00** | **$0.73** | **$6,420.70** |
| | **Item Code 202031 Total No. of Proj.** | | | **8** | | **Total Amount** | **$17,149.50** |
| **202033** | COMMERCIAL FERTILIZER (PACKET) | EA | 3 | 1 | 3,330.00 | $0.22 | $715.95 |
| | | EA | 6 | 2 | 7,190.00 | $0.22 | $1,593.40 |
| | | EA | 10 | 1 | 1,870.00 | $0.15 | $280.50 |
| | | EA | 11 | 4 | 93,250.00 | $0.47 | $43,744.00 |
| | **Unit Sub Total** | **EA** | | **8** | **105,640.00** | **$0.44** | **$46,333.85** |
| | **Item Code 202033 Total No. of Proj.** | | | **8** | | **Total Amount** | **$46,333.85** |
| **203001** | EROSION CONTROL (BLANKET) | M2 | 2 | 1 | 370.00 | $9.00 | $3,330.00 |
| | | M2 | 3 | 4 | 19,380.00 | $2.08 | $40,350.00 |
| | | M2 | 5 | 3 | 5,250.00 | $4.40 | $23,116.00 |
| | | M2 | 8 | 1 | 5,500.00 | $2.10 | $11,550.00 |
| | | M2 | 9 | 3 | 18,840.00 | $4.22 | $79,440.80 |
| | | M2 | 10 | 1 | 200.00 | $7.00 | $1,400.00 |
| | | M2 | 11 | 1 | 5,100.00 | $5.00 | $25,500.00 |
| | | M2 | 12 | 1 | 3,000.00 | $9.00 | $27,000.00 |
| | **Unit Sub Total** | **M2** | | **15** | **57,640.00** | **$3.67** | **$211,686.80** |
| **203001** | EROSION CONTROL (BLANKET) | SQYD | 1 | 1 | 360.00 | $5.25 | $1,890.00 |
| | | SQYD | 2 | 2 | 10,750.00 | $5.48 | $58,875.00 |
| | | SQYD | 3 | 4 | 2,330.00 | $9.58 | $22,310.00 |
| | | SQYD | 6 | 4 | 5,710.00 | $7.38 | $42,134.00 |
| | | SQYD | 8 | 1 | 1,550.00 | $2.96 | $4,588.00 |
| | **Unit Sub Total** | **SQYD** | | **12** | **20,700.00** | **$6.27** | **$129,797.00** |
| | **Item Code 203001 Total No. of Proj.** | | | **27** | | **Total Amount** | **$341,483.80** |
| **203002** | EROSION CONTROL (COMPOST BLANKET) | CY | 1 | 1 | 6.00 | $914.00 | $5,484.00 |
| | | CY | 3 | 3 | 205.00 | $113.93 | $23,356.00 |
| | | CY | 4 | 1 | 8.00 | $400.00 | $3,200.00 |
| | **Unit Sub Total** | **CY** | | **5** | **219.00** | **$146.30** | **$32,040.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **203002** | EROSION CONTROL (COMPOST BLANKET) | M2 | 3 | 1 | 440.00 | $10.00 | $4,400.00 |
| | **Unit Sub Total** | **M2** | | **1** | **440.00** | **$10.00** | **$4,400.00** |
| **203002** | EROSION CONTROL (COMPOST BLANKET) | M3 | 1 | 1 | 3.50 | $658.00 | $2,303.00 |
| | | M3 | 5 | 5 | 720.00 | $97.38 | $70,115.00 |
| | | M3 | 6 | 1 | 49.00 | $225.00 | $11,025.00 |
| | **Unit Sub Total** | **M3** | | **7** | **772.50** | **$108.02** | **$83,443.00** |
| | **Item Code 203002 Total No. of Proj.** | | | **13** | | **Total Amount** | **$119,883.00** |
| **203003** | STRAW (EROSION CONTROL) | TONN | 5 | 1 | 20.00 | $500.00 | $10,000.00 |
| | | TONN | 10 | 1 | 130.00 | $918.00 | $119,340.00 |
| | **Unit Sub Total** | **TONN** | | **2** | **150.00** | **$862.27** | **$129,340.00** |
| | **Item Code 203003 Total No. of Proj.** | | | **2** | | **Total Amount** | **$129,340.00** |
| **203011** | EROSION CONTROL (TYPE C) | ACRE | 6 | 1 | 1.30 | $5,000.00 | $6,500.00 |
| | **Unit Sub Total** | **ACRE** | | **1** | **1.30** | **$5,000.00** | **$6,500.00** |
| **203011** | EROSION CONTROL (TYPE C) | HA | 6 | 1 | 15.00 | $5,200.00 | $78,000.00 |
| | | HA | 9 | 2 | 52.00 | $7,001.92 | $364,100.00 |
| | **Unit Sub Total** | **HA** | | **3** | **67.00** | **$6,598.51** | **$442,100.00** |
| **203011** | EROSION CONTROL (TYPE C) | M2 | 7 | 1 | 3,130.00 | $6.00 | $18,780.00 |
| | | M2 | 9 | 2 | 21,310.00 | $2.02 | $43,002.00 |
| | | M2 | 10 | 2 | 38,860.00 | $1.00 | $38,860.00 |
| | **Unit Sub Total** | **M2** | | **5** | **63,300.00** | **$1.59** | **$100,642.00** |
| **203011** | EROSION CONTROL (TYPE C) | SQYD | 6 | 1 | 680.00 | $18.00 | $12,240.00 |
| | **Unit Sub Total** | **SQYD** | | **1** | **680.00** | **$18.00** | **$12,240.00** |
| | **Item Code 203011 Total No. of Proj.** | | | **10** | | **Total Amount** | **$561,482.00** |
| **203012** | EROSION CONTROL (DRILL SEED) | ACRE | 5 | 1 | 15.00 | $4,960.00 | $74,400.00 |
| | **Unit Sub Total** | **ACRE** | | **1** | **15.00** | **$4,960.00** | **$74,400.00** |
| **203012** | EROSION CONTROL (DRILL SEED) | HA | 5 | 1 | 11.00 | $7,000.00 | $77,000.00 |
| | | HA | 10 | 1 | 7.00 | $5,535.00 | $38,745.00 |
| | **Unit Sub Total** | **HA** | | **2** | **18.00** | **$6,430.28** | **$115,745.00** |
| **203012** | EROSION CONTROL (DRILL SEED) | M2 | 3 | 2 | 3,300,000.00 | $0.20 | $660,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M2** | | **2** | **3,300,000.00** | **$0.20** | **$660,000.00** |
| | **Item Code 203012** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$850,145.00** |
| **203014** | FIBER (EROSION CONTROL) | | KG | 1 | 1 | 1,490.00 | $1.00 | $1,490.00 |
| | | | KG | 5 | 1 | 76,400.00 | $1.00 | $76,400.00 |
| | | | KG | 10 | 1 | 18,000.00 | $0.71 | $12,780.00 |
| | | | KG | 11 | 1 | 63,400.00 | $0.70 | $44,380.00 |
| | | **Unit Sub Total** | **KG** | | **4** | **159,290.00** | **$0.85** | **$135,050.00** |
| | **Item Code 203014** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$135,050.00** |
| **203015** | EROSION CONTROL | | SQYD | 1 | 1 | 500.00 | $5.00 | $2,500.00 |
| | | **Unit Sub Total** | **SQYD** | | **1** | **500.00** | **$5.00** | **$2,500.00** |
| | **Item Code 203015** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,500.00** |
| **203016** | EROSION CONTROL (TYPE D) | | ACRE | 1 | 1 | 0.40 | $7,000.00 | $2,800.00 |
| | | | ACRE | 2 | 7 | 20.50 | $5,835.24 | $119,622.50 |
| | | | ACRE | 3 | 1 | 1.00 | $8,000.00 | $8,000.00 |
| | | | ACRE | 5 | 1 | 1.50 | $6,200.00 | $9,300.00 |
| | | | ACRE | 6 | 2 | 5.70 | $3,517.54 | $20,050.00 |
| | | | ACRE | 8 | 2 | 6.30 | $19,613.49 | $123,565.00 |
| | | | ACRE | 10 | 1 | 0.10 | $30,930.00 | $3,093.00 |
| | | | ACRE | 11 | 1 | 0.50 | $3,420.00 | $1,710.00 |
| | | **Unit Sub Total** | **ACRE** | | **16** | **36.00** | **$8,003.90** | **$288,140.50** |
| **203016** | EROSION CONTROL (TYPE D) | | CY | 3 | 2 | 779.00 | $17.39 | $13,550.00 |
| | | **Unit Sub Total** | **CY** | | **2** | **779.00** | **$17.39** | **$13,550.00** |
| **203016** | EROSION CONTROL (TYPE D) | | HA | 1 | 1 | 15.00 | $8,333.00 | $124,995.00 |
| | | | HA | 2 | 4 | 12.40 | $6,450.56 | $79,987.00 |
| | | | HA | 4 | 7 | 34.50 | $7,901.32 | $272,595.40 |
| | | | HA | 5 | 1 | 0.80 | $4,000.00 | $3,200.00 |
| | | | HA | 6 | 3 | 25.80 | $5,182.02 | $133,696.00 |
| | | | HA | 8 | 1 | 3.00 | $3,500.00 | $10,500.00 |
| | | | HA | 10 | 1 | 4.70 | $8,125.00 | $38,187.50 |
| | | **Unit Sub Total** | **HA** | | **18** | **96.20** | **$6,893.56** | **$663,160.90** |
| **203016** | EROSION CONTROL (TYPE D) | | M2 | 1 | 3 | 131,300.00 | $1.01 | $133,260.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **203016** | EROSION CONTROL (TYPE D) | | M2 | 2 | 2 | 6,100.00 | $2.57 | $15,700.00 |
| | | | M2 | 3 | 5 | 114,670.00 | $1.56 | $178,726.00 |
| | | | M2 | 4 | 12 | 141,580.00 | $0.93 | $131,549.00 |
| | | | M2 | 5 | 13 | 79,330.00 | $2.27 | $179,983.50 |
| | | | M2 | 6 | 2 | 15,290.00 | $1.41 | $21,537.80 |
| | | | M2 | 7 | 8 | 27,890.00 | $1.95 | $54,382.80 |
| | | | M2 | 8 | 3 | 6,990.00 | $1.63 | $11,361.00 |
| | | | M2 | 10 | 3 | 8,300.00 | $3.58 | $29,700.00 |
| | | | M2 | 11 | 12 | 885,360.00 | $1.35 | $1,196,933.00 |
| | | | M2 | 12 | 1 | 4,760.00 | $0.60 | $2,856.00 |
| | | **Unit Sub Total** | **M2** | | **64** | **1,421,570.00** | **$1.38** | **$1,955,989.10** |
| **203016** | EROSION CONTROL (TYPE D) | | SQFT | 3 | 1 | 3,400.00 | $1.00 | $3,400.00 |
| | | | SQFT | 5 | 1 | 580.00 | $3.60 | $2,088.00 |
| | | | SQFT | 7 | 1 | 990.00 | $2.90 | $2,871.00 |
| | | | SQFT | 12 | 1 | 85,500.00 | $0.10 | $8,550.00 |
| | | **Unit Sub Total** | **SQFT** | | **4** | **90,470.00** | **$0.19** | **$16,909.00** |
| **203016** | EROSION CONTROL (TYPE D) | | SQYD | 1 | 6 | 24,350.00 | $1.45 | $35,400.00 |
| | | | SQYD | 2 | 6 | 2,680.00 | $5.80 | $15,532.50 |
| | | | SQYD | 3 | 13 | 23,880.00 | $3.09 | $73,772.50 |
| | | | SQYD | 4 | 3 | 4,140.00 | $3.33 | $13,788.10 |
| | | | SQYD | 5 | 5 | 14,740.00 | $1.99 | $29,276.80 |
| | | | SQYD | 6 | 2 | 4,020.00 | $2.56 | $10,299.00 |
| | | | SQYD | 7 | 3 | 18,080.00 | $0.62 | $11,208.10 |
| | | | SQYD | 8 | 2 | 2,260.00 | $2.35 | $5,318.80 |
| | | | SQYD | 10 | 1 | 3,540.00 | $4.00 | $14,160.00 |
| | | | SQYD | 11 | 2 | 46,470.00 | $0.70 | $32,730.00 |
| | | | SQYD | 12 | 1 | 2,300.00 | $7.26 | $16,698.00 |
| | | **Unit Sub Total** | **SQYD** | | **44** | **146,460.00** | **$1.76** | **$258,183.80** |
| | **Item Code 203016** | **Total No. of Proj.** | | | **148** | | **Total Amount** | **$3,195,933.30** |
| **203017** | EROSION CONTROL (HYDRAULIC MATRIX) | | M2 | 11 | 4 | 48,800.00 | $2.90 | $141,609.20 |
| | | **Unit Sub Total** | **M2** | | **4** | **48,800.00** | **$2.90** | **$141,609.20** |
| **203017** | EROSION CONTROL (HYDRAULIC MATRIX) | | SQYD | 3 | 4 | 229,190.00 | $0.54 | $123,168.00 |
| | | | SQYD | 8 | 1 | 1,380.00 | $2.31 | $3,187.80 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **203017** | EROSION CONTROL (HYDRAULIC MATRIX) | | SQYD | 11 | 1 | 110.00 | $15.00 | $1,650.00 |
| | | **Unit Sub Total** | **SQYD** | | **6** | **230,680.00** | **$0.55** | **$128,005.80** |
| | **Item Code 203017** | **Total No. of Proj.** | | | **10** | | **Total Amount** | **$269,615.00** |
| **203018** | EROSION CONTROL (NETTING) | | M2 | 4 | 15 | 23,445.00 | $4.28 | $100,297.30 |
| | | | M2 | 5 | 2 | 1,720.00 | $7.73 | $13,300.00 |
| | | **Unit Sub Total** | **M2** | | **17** | **25,165.00** | **$4.51** | **$113,597.30** |
| **203018** | EROSION CONTROL (NETTING) | | SQYD | 2 | 1 | 220.00 | $12.95 | $2,849.00 |
| | | | SQYD | 3 | 4 | 5,170.00 | $3.27 | $16,890.00 |
| | | | SQYD | 4 | 6 | 2,678.00 | $15.10 | $40,426.00 |
| | | | SQYD | 6 | 1 | 1,480.00 | $4.90 | $7,252.00 |
| | | **Unit Sub Total** | **SQYD** | | **12** | **9,548.00** | **$7.06** | **$67,417.00** |
| | **Item Code 203018** | **Total No. of Proj.** | | | **29** | | **Total Amount** | **$181,014.30** |
| **203019** | EROSION CONTROL, BFM | | SQYD | 3 | 1 | 2,110.00 | $2.00 | $4,220.00 |
| | | **Unit Sub Total** | **SQYD** | | **1** | **2,110.00** | **$2.00** | **$4,220.00** |
| | **Item Code 203019** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,220.00** |
| **203021** | FIBER ROLLS | | LF | 1 | 2 | 2,150.00 | $3.96 | $8,510.00 |
| | | | LF | 2 | 2 | 330.00 | $5.86 | $1,935.00 |
| | | | LF | 3 | 4 | 2,860.00 | $4.13 | $11,816.00 |
| | | | LF | 4 | 3 | 4,980.00 | $1.99 | $9,920.00 |
| | | | LF | 5 | 1 | 1,350.00 | $4.70 | $6,345.00 |
| | | | LF | 6 | 2 | 3,330.00 | $3.37 | $11,220.00 |
| | | | LF | 8 | 1 | 3,740.00 | $2.46 | $9,200.40 |
| | | | LF | 11 | 8 | 68,340.00 | $1.64 | $111,880.60 |
| | | **Unit Sub Total** | **LF** | | **23** | **87,080.00** | **$1.96** | **$170,827.00** |
| **203021** | FIBER ROLLS | | M | 1 | 3 | 8,190.00 | $9.62 | $78,796.00 |
| | | | M | 4 | 18 | 112,383.00 | $6.17 | $693,356.25 |
| | | | M | 5 | 10 | 12,135.00 | $10.37 | $125,900.00 |
| | | | M | 9 | 1 | 2,470.00 | $17.00 | $41,990.00 |
| | | | M | 10 | 1 | 6,970.00 | $5.18 | $36,104.60 |
| | | | M | 11 | 13 | 128,380.00 | $6.97 | $894,819.00 |
| | | **Unit Sub Total** | **M** | | **46** | **270,528.00** | **$6.92** | **$1,870,965.85** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 203021 Total No. of Proj.** | | | **69** | | **Total Amount** | **$2,041,792.85** |
| **203024** | COMPOST (EROSION CONTROL) | M3 | 1 | 1 | 2.00 | $75.00 | $150.00 |
| | | M3 | 11 | 1 | 160.00 | $700.00 | $112,000.00 |
| | **Unit Sub Total** | **M3** | | **2** | **162.00** | **$692.28** | **$112,150.00** |
| | **Item Code 203024 Total No. of Proj.** | | | **2** | | **Total Amount** | **$112,150.00** |
| **203025** | COMPOST, INCORPORATE | M2 | 4 | 2 | 17,080.00 | $8.11 | $138,456.00 |
| | | M2 | 11 | 2 | 12,520.00 | $4.49 | $56,240.00 |
| | **Unit Sub Total** | **M2** | | **4** | **29,600.00** | **$6.58** | **$194,696.00** |
| | **Item Code 203025 Total No. of Proj.** | | | **4** | | **Total Amount** | **$194,696.00** |
| **203026** | MOVE-IN/MOVE-OUT (EROSION CONTROL) | EA | 1 | 6 | 26.00 | $875.00 | $22,750.00 |
| | | EA | 2 | 3 | 21.00 | $989.57 | $20,781.00 |
| | | EA | 3 | 8 | 57.00 | $712.91 | $40,636.00 |
| | | EA | 4 | 11 | 53.00 | $814.34 | $43,160.00 |
| | | EA | 5 | 7 | 30.00 | $548.17 | $16,445.02 |
| | | EA | 6 | 2 | 13.00 | $673.85 | $8,760.00 |
| | | EA | 7 | 4 | 9.00 | $654.22 | $5,888.00 |
| | | EA | 8 | 3 | 8.00 | $734.38 | $5,875.00 |
| | | EA | 9 | 3 | 14.00 | $1,492.86 | $20,900.00 |
| | | EA | 10 | 4 | 19.00 | $580.26 | $11,025.00 |
| | | EA | 11 | 7 | 33.00 | $490.91 | $16,200.00 |
| | | EA | 12 | 3 | 8.00 | $475.00 | $3,800.00 |
| | **Unit Sub Total** | **EA** | | **61** | **291.00** | **$743.02** | **$216,220.02** |
| | **Item Code 203026 Total No. of Proj.** | | | **61** | | **Total Amount** | **$216,220.02** |
| **203045** | PURE LIVE SEED (EROSION CONTROL) | KG | 1 | 1 | 95.00 | $20.00 | $1,900.00 |
| | | KG | 10 | 1 | 940.00 | $76.40 | $71,816.00 |
| | **Unit Sub Total** | **KG** | | **2** | **1,035.00** | **$71.22** | **$73,716.00** |
| | **Item Code 203045 Total No. of Proj.** | | | **2** | | **Total Amount** | **$73,716.00** |
| **203056** | COMMERCIAL FERTILIZER (EROSION CONTROL) | KG | 10 | 1 | 9,000.00 | $1.18 | $10,620.00 |
| | | KG | 11 | 1 | 840.00 | $1.00 | $840.00 |
| | **Unit Sub Total** | **KG** | | **2** | **9,840.00** | **$1.16** | **$11,460.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 203056 Total No. of Proj.** | | | **2** | | **Total Amount** | **$11,460.00** |
| **203061** | STABILIZING EMULSION (EROSION CONTROL) | KG | 1 | 1 | 95.00 | $2.00 | $190.00 |
| | | KG | 5 | 1 | 2,390.00 | $3.00 | $7,170.00 |
| | | KG | 10 | 1 | 4,200.00 | $1.25 | $5,250.00 |
| | | KG | 11 | 1 | 7,860.00 | $1.50 | $11,790.00 |
| | **Unit Sub Total** | **KG** | | **4** | **14,545.00** | **$1.68** | **$24,400.00** |
| | **Item Code 203061 Total No. of Proj.** | | | **4** | | **Total Amount** | **$24,400.00** |
| **203561** | JUTE MESH | M2 | 5 | 2 | 71,390.00 | $2.39 | $170,740.00 |
| | **Unit Sub Total** | **M2** | | **2** | **71,390.00** | **$2.39** | **$170,740.00** |
| **203561** | JUTE MESH | SQYD | 5 | 1 | 4,300.00 | $3.40 | $14,620.00 |
| | | SQYD | 11 | 1 | 20.00 | $18.00 | $360.00 |
| | **Unit Sub Total** | **SQYD** | | **2** | **4,320.00** | **$3.47** | **$14,980.00** |
| | **Item Code 203561 Total No. of Proj.** | | | **4** | | **Total Amount** | **$185,720.00** |
| **204001** | PLANT (GROUP A) | EA | 3 | 1 | 1,640.00 | $6.14 | $10,069.60 |
| | | EA | 4 | 1 | 310.00 | $2.00 | $620.00 |
| | | EA | 6 | 1 | 88.00 | $5.82 | $512.16 |
| | | EA | 10 | 1 | 48.00 | $7.25 | $348.00 |
| | | EA | 12 | 1 | 640.00 | $6.88 | $4,403.20 |
| | **Unit Sub Total** | **EA** | | **5** | **2,726.00** | **$5.85** | **$15,952.96** |
| | **Item Code 204001 Total No. of Proj.** | | | **5** | | **Total Amount** | **$15,952.96** |
| **204002** | PLANT (GROUP B) | EA | 3 | 1 | 30.00 | $40.48 | $1,214.40 |
| | | EA | 6 | 1 | 15.00 | $24.30 | $364.50 |
| | | EA | 8 | 1 | 570.00 | $16.14 | $9,199.80 |
| | | EA | 10 | 1 | 490.00 | $23.65 | $11,588.50 |
| | **Unit Sub Total** | **EA** | | **4** | **1,105.00** | **$20.24** | **$22,367.20** |
| | **Item Code 204002 Total No. of Proj.** | | | **4** | | **Total Amount** | **$22,367.20** |
| **204006** | PLANT (GROUP F) | EA | 11 | 3 | 181,200.00 | $0.29 | $52,491.00 |
| | | EA | 12 | 1 | 179,100.00 | $0.52 | $93,132.00 |
| | **Unit Sub Total** | **EA** | | **4** | **360,300.00** | **$0.40** | **$145,623.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 204006 Total No. of Proj.** | | | **4** | | **Total Amount** | **$145,623.00** |
| **204007** | PLANT (GROUP G) | EA | 11 | 2 | 764,000.00 | $0.30 | $231,200.00 |
| | **Unit Sub Total** | **EA** | | **2** | **764,000.00** | **$0.30** | **$231,200.00** |
| | **Item Code 204007 Total No. of Proj.** | | | **2** | | **Total Amount** | **$231,200.00** |
| **204008** | PLANT (GROUP H) | EA | 6 | 1 | 95,140.00 | $0.20 | $19,028.00 |
| | | EA | 11 | 4 | 1,485,900.00 | $0.13 | $194,109.00 |
| | **Unit Sub Total** | **EA** | | **5** | **1,581,040.00** | **$0.13** | **$213,137.00** |
| | **Item Code 204008 Total No. of Proj.** | | | **5** | | **Total Amount** | **$213,137.00** |
| **204009** | PLANT (GROUP I) | EA | 4 | 1 | 2,780.00 | $3.71 | $10,313.80 |
| | | EA | 6 | 1 | 280.00 | $6.22 | $1,741.60 |
| | | EA | 10 | 1 | 360.00 | $6.15 | $2,214.00 |
| | **Unit Sub Total** | **EA** | | **3** | **3,420.00** | **$4.17** | **$14,269.40** |
| | **Item Code 204009 Total No. of Proj.** | | | **3** | | **Total Amount** | **$14,269.40** |
| **204011** | PLANT (GROUP K) | EA | 11 | 1 | 230.00 | $250.00 | $57,500.00 |
| | **Unit Sub Total** | **EA** | | **1** | **230.00** | **$250.00** | **$57,500.00** |
| | **Item Code 204011 Total No. of Proj.** | | | **1** | | **Total Amount** | **$57,500.00** |
| **204013** | PLANT (GROUP M) | EA | 3 | 1 | 810.00 | $1.03 | $834.30 |
| | | EA | 11 | 1 | 12,500.00 | $2.00 | $25,000.00 |
| | **Unit Sub Total** | **EA** | | **2** | **13,310.00** | **$1.94** | **$25,834.30** |
| | **Item Code 204013 Total No. of Proj.** | | | **2** | | **Total Amount** | **$25,834.30** |
| **204017** | PLANT (GROUP W) | EA | 4 | 1 | 90.00 | $55.00 | $4,950.00 |
| | | EA | 5 | 4 | 295.00 | $20.16 | $5,948.20 |
| | | EA | 7 | 4 | 2,000.00 | $13.50 | $27,009.30 |
| | | EA | 8 | 1 | 150.00 | $10.00 | $1,500.00 |
| | | EA | 9 | 2 | 75.00 | $90.00 | $6,750.00 |
| | | EA | 11 | 2 | 1,654.00 | $4.63 | $7,650.00 |
| | **Unit Sub Total** | **EA** | | **14** | **4,264.00** | **$12.62** | **$53,807.50** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | **Item Code 204017** | **Total No. of Proj.** | | | **14** | | **Total Amount** | **$53,807.50** |
| **204021** | PLANT (GROUP U) | | EA | 4 | 1 | 110.00 | $40.00 | $4,400.00 |
| | | | EA | 8 | 1 | 65.00 | $99.25 | $6,451.25 |
| | | | EA | 11 | 2 | 244.00 | $71.73 | $17,501.88 |
| | | | EA | 12 | 1 | 70.00 | $89.81 | $6,286.70 |
| | | **Unit Sub Total** | **EA** | | **5** | **489.00** | **$70.84** | **$34,639.83** |
| | **Item Code 204021** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$34,639.83** |
| **204022** | PLANT (GROUP Z) | | EA | 12 | 1 | 43.00 | $2,883.25 | $123,979.75 |
| | | **Unit Sub Total** | **EA** | | **1** | **43.00** | **$2,883.25** | **$123,979.75** |
| | **Item Code 204022** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$123,979.75** |
| **204030** | TRANSPLANT TREE | | EA | 12 | 1 | 3.00 | $15,000.00 | $45,000.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **3.00** | **$15,000.00** | **$45,000.00** |
| | **Item Code 204030** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$45,000.00** |
| **204031** | TRANSPLANT PALM TREE | | EA | 5 | 1 | 21.00 | $5,070.00 | $106,470.00 |
| | | | EA | 6 | 1 | 4.00 | $8,800.00 | $35,200.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **25.00** | **$5,666.80** | **$141,670.00** |
| | **Item Code 204031** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$141,670.00** |
| **204035** | PLANT (GROUP A) | | EA | 4 | 1 | 1,870.00 | $8.74 | $16,343.80 |
| | | | EA | 6 | 1 | 6,370.00 | $7.00 | $44,590.00 |
| | | | EA | 11 | 2 | 25,930.00 | $6.90 | $178,954.00 |
| | | **Unit Sub Total** | **EA** | | **4** | **34,170.00** | **$7.02** | **$239,887.80** |
| | **Item Code 204035** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$239,887.80** |
| **204036** | PLANT (GROUP B) | | EA | 4 | 1 | 310.00 | $17.18 | $5,325.80 |
| | | | EA | 11 | 2 | 3,070.00 | $20.51 | $62,966.40 |
| | | **Unit Sub Total** | **EA** | | **3** | **3,380.00** | **$20.20** | **$68,292.20** |
| | **Item Code 204036** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$68,292.20** |
| **204038** | PLANT (GROUP U) | | EA | 1 | 1 | 5.00 | $250.00 | $1,250.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **204038** | PLANT (GROUP U) | EA | 6 | 1 | 79.00 | $70.00 | $5,530.00 |
| | | EA | 11 | 2 | 1,090.00 | $87.87 | $95,776.00 |
| | **Unit Sub Total** | **EA** | | **4** | **1,174.00** | **$87.36** | **$102,556.00** |
| | **Item Code 204038 Total No. of Proj.** | | | **4** | | **Total Amount** | **$102,556.00** |
| **204051** | SEEDING | SQYD | 11 | 1 | 360.00 | $10.00 | $3,600.00 |
| | **Unit Sub Total** | **SQYD** | | **1** | **360.00** | **$10.00** | **$3,600.00** |
| | **Item Code 204051 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,600.00** |
| **204053** | WILD FLOWER SEEDING | ACRE | 11 | 1 | 10.00 | $2,627.00 | $26,270.00 |
| | **Unit Sub Total** | **ACRE** | | **1** | **10.00** | **$2,627.00** | **$26,270.00** |
| **204053** | WILD FLOWER SEEDING | SQYD | 6 | 1 | 25,400.00 | $0.95 | $24,130.00 |
| | | SQYD | 12 | 1 | 1,060.00 | $3.51 | $3,720.60 |
| | **Unit Sub Total** | **SQYD** | | **2** | **26,460.00** | **$1.05** | **$27,850.60** |
| | **Item Code 204053 Total No. of Proj.** | | | **3** | | **Total Amount** | **$54,120.60** |
| **204096** | MAINTAIN EXISTING PLANTED AREAS | LS | 2 | 2 | 2.00 | $18,100.00 | $36,200.00 |
| | | LS | 3 | 2 | 2.00 | $1,465.00 | $2,930.00 |
| | | LS | 4 | 2 | 2.00 | $984.00 | $1,968.00 |
| | | LS | 5 | 1 | 1.00 | $6,500.00 | $6,500.00 |
| | | LS | 6 | 3 | 3.00 | $26,333.33 | $79,000.00 |
| | | LS | 8 | 1 | 1.00 | $2,600.00 | $2,600.00 |
| | | LS | 11 | 1 | 1.00 | $50,000.00 | $50,000.00 |
| | | LS | 12 | 3 | 3.00 | $4,949.78 | $14,849.33 |
| | **Unit Sub Total** | **LS** | | **15** | **15.00** | **$12,936.49** | **$194,047.33** |
| | **Item Code 204096 Total No. of Proj.** | | | **15** | | **Total Amount** | **$194,047.33** |
| **204099** | PLANT ESTABLISHMENT WORK | LS | 1 | 3 | 3.00 | $9,500.00 | $28,500.00 |
| | | LS | 2 | 3 | 3.00 | $2,931.00 | $8,793.00 |
| | | LS | 3 | 6 | 6.00 | $27,652.30 | $165,913.81 |
| | | LS | 4 | 6 | 6.00 | $47,108.33 | $282,650.00 |
| | | LS | 5 | 14 | 14.00 | $16,464.29 | $230,500.01 |
| | | LS | 6 | 7 | 7.00 | $24,413.86 | $170,897.00 |
| | | LS | 7 | 15 | 15.00 | $23,029.13 | $345,437.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **204099** | PLANT ESTABLISHMENT WORK | LS | 8 | 6 | 6.00 | $54,221.67 | $325,330.00 |
| | | LS | 9 | 1 | 1.00 | $8,000.00 | $8,000.00 |
| | | LS | 10 | 2 | 2.00 | $93,306.25 | $186,612.50 |
| | | LS | 11 | 15 | 15.00 | $51,688.43 | $775,326.42 |
| | | LS | 12 | 7 | 7.00 | $21,436.64 | $150,056.49 |
| | **Unit Sub Total** | **LS** | | **85** | **85.00** | **$31,506.07** | **$2,678,016.23** |
| | **Item Code 204099 Total No. of Proj.** | | | **85** | | **Total Amount** | **$2,678,016.23** |
| **204100** | ESTABLISH EXISTING PLANTING | LS | 8 | 1 | 1.00 | $120,000.00 | $120,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$120,000.00** | **$120,000.00** |
| | **Item Code 204100 Total No. of Proj.** | | | **1** | | **Total Amount** | **$120,000.00** |
| **205051** | FOLIAGE PROTECTOR | EA | 6 | 1 | 14.00 | $12.70 | $177.80 |
| | **Unit Sub Total** | **EA** | | **1** | **14.00** | **$12.70** | **$177.80** |
| | **Item Code 205051 Total No. of Proj.** | | | **1** | | **Total Amount** | **$177.80** |
| **205061** | ROOT PROTECTOR | EA | 6 | 2 | 427.00 | $13.50 | $5,766.00 |
| | | EA | 10 | 1 | 360.00 | $20.00 | $7,200.00 |
| | **Unit Sub Total** | **EA** | | **3** | **787.00** | **$16.48** | **$12,966.00** |
| | **Item Code 205061 Total No. of Proj.** | | | **3** | | **Total Amount** | **$12,966.00** |
| **206401** | MAINTAIN EXISTING IRRIGATION FACILITIES | LS | 2 | 3 | 3.00 | $3,633.33 | $10,900.00 |
| | | LS | 3 | 5 | 5.00 | $3,346.00 | $16,730.00 |
| | | LS | 4 | 3 | 3.00 | $970.00 | $2,910.00 |
| | | LS | 5 | 2 | 2.00 | $600.00 | $1,200.00 |
| | | LS | 6 | 4 | 4.00 | $20,500.00 | $82,000.00 |
| | | LS | 7 | 1 | 1.00 | $500.00 | $500.00 |
| | | LS | 8 | 2 | 2.00 | $4,625.00 | $9,250.00 |
| | | LS | 11 | 1 | 1.00 | $50,000.00 | $50,000.00 |
| | | LS | 12 | 5 | 5.00 | $1,306.40 | $6,532.00 |
| | **Unit Sub Total** | **LS** | | **26** | **26.00** | **$6,923.92** | **$180,022.00** |
| | **Item Code 206401 Total No. of Proj.** | | | **26** | | **Total Amount** | **$180,022.00** |
| **206560** | CONTROL AND NEUTRAL CONDUCTORS | LS | 3 | 1 | 1.00 | $31,173.50 | $31,173.50 |
| | | LS | 4 | 2 | 2.00 | $14,948.50 | $29,897.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **206560** | CONTROL AND NEUTRAL CONDUCTORS | LS | 6 | 3 | 3.00 | $50,473.39 | $151,420.17 |
| | | LS | 8 | 1 | 1.00 | $17,480.00 | $17,480.00 |
| | | LS | 10 | 1 | 1.00 | $43,200.00 | $43,200.00 |
| | | LS | 11 | 4 | 4.00 | $88,661.38 | $354,645.51 |
| | | LS | 12 | 1 | 1.00 | $21,740.76 | $21,740.76 |
| | **Unit Sub Total** | **LS** | | **13** | **13.00** | **$49,965.92** | **$649,556.94** |
| | **Item Code 206560 Total No. of Proj.** | | | **13** | | **Total Amount** | **$649,556.94** |
| **206601** | 3/4" ELECTRIC REMOTE CONTROL VALVE | EA | 12 | 1 | 1.00 | $257.23 | $257.23 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$257.23** | **$257.23** |
| | **Item Code 206601 Total No. of Proj.** | | | **1** | | **Total Amount** | **$257.23** |
| **206602** | 1" ELECTRIC REMOTE CONTROL VALVE | EA | 3 | 1 | 33.00 | $143.29 | $4,728.57 |
| | | EA | 4 | 1 | 9.00 | $100.00 | $900.00 |
| | | EA | 6 | 1 | 1.00 | $254.00 | $254.00 |
| | | EA | 8 | 1 | 10.00 | $207.50 | $2,075.00 |
| | | EA | 10 | 1 | 13.00 | $217.00 | $2,821.00 |
| | | EA | 11 | 1 | 2.00 | $205.31 | $410.62 |
| | | EA | 12 | 1 | 20.00 | $272.70 | $5,454.00 |
| | **Unit Sub Total** | **EA** | | **7** | **88.00** | **$189.13** | **$16,643.19** |
| | **Item Code 206602 Total No. of Proj.** | | | **7** | | **Total Amount** | **$16,643.19** |
| **206603** | 1 1/4" ELECTRIC REMOTE CONTROL VALVE | EA | 3 | 1 | 8.00 | $160.53 | $1,284.24 |
| | | EA | 12 | 1 | 22.00 | $298.68 | $6,570.96 |
| | **Unit Sub Total** | **EA** | | **2** | **30.00** | **$261.84** | **$7,855.20** |
| | **Item Code 206603 Total No. of Proj.** | | | **2** | | **Total Amount** | **$7,855.20** |
| **206604** | 1 1/2" ELECTRIC REMOTE CONTROL VALVE | EA | 3 | 1 | 5.00 | $160.80 | $804.00 |
| | | EA | 6 | 1 | 2.00 | $3,011.00 | $6,022.00 |
| | | EA | 8 | 1 | 15.00 | $222.93 | $3,343.95 |
| | | EA | 12 | 1 | 34.00 | $332.03 | $11,289.02 |
| | **Unit Sub Total** | **EA** | | **4** | **56.00** | **$383.20** | **$21,458.97** |
| | **Item Code 206604 Total No. of Proj.** | | | **4** | | **Total Amount** | **$21,458.97** |
| **206605** | 2" ELECTRIC REMOTE CONTROL VALVE | EA | 6 | 1 | 8.00 | $282.97 | $2,263.76 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **206605** | 2" ELECTRIC REMOTE CONTROL VALVE | EA | 8 | 1 | 3.00 | $254.23 | $762.69 |
| | | EA | 10 | 1 | 1.00 | $325.00 | $325.00 |
| | **Unit Sub Total** | **EA** | | **3** | **12.00** | **$279.29** | **$3,351.45** |
| | **Item Code 206605 Total No. of Proj.** | | | **3** | | **Total Amount** | **$3,351.45** |
| **206607** | 3" ELECTRIC REMOTE CONTROL VALVE | EA | 3 | 1 | 2.00 | $324.06 | $648.12 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$324.06** | **$648.12** |
| | **Item Code 206607 Total No. of Proj.** | | | **1** | | **Total Amount** | **$648.12** |
| **206611** | 25 MM ELECTRIC REMOTE CONTROL VALVE | EA | 4 | 1 | 14.00 | $189.12 | $2,647.68 |
| | | EA | 11 | 2 | 47.00 | $338.11 | $15,891.04 |
| | **Unit Sub Total** | **EA** | | **3** | **61.00** | **$303.91** | **$18,538.72** |
| | **Item Code 206611 Total No. of Proj.** | | | **3** | | **Total Amount** | **$18,538.72** |
| **206612** | 32 MM ELECTRIC REMOTE CONTROL VALVE | EA | 4 | 1 | 4.00 | $228.84 | $915.36 |
| | | EA | 6 | 1 | 10.00 | $200.00 | $2,000.00 |
| | **Unit Sub Total** | **EA** | | **2** | **14.00** | **$208.24** | **$2,915.36** |
| | **Item Code 206612 Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,915.36** |
| **206613** | 40 MM ELECTRIC REMOTE CONTROL VALVE | EA | 4 | 1 | 1.00 | $228.83 | $228.83 |
| | | EA | 6 | 1 | 22.00 | $240.00 | $5,280.00 |
| | | EA | 11 | 2 | 289.00 | $347.40 | $100,397.52 |
| | **Unit Sub Total** | **EA** | | **4** | **312.00** | **$339.44** | **$105,906.35** |
| | **Item Code 206613 Total No. of Proj.** | | | **4** | | **Total Amount** | **$105,906.35** |
| **206614** | 50 MM ELECTRIC REMOTE CONTROL VALVE | EA | 6 | 1 | 59.00 | $260.00 | $15,340.00 |
| | | EA | 11 | 1 | 1.00 | $380.00 | $380.00 |
| | **Unit Sub Total** | **EA** | | **2** | **60.00** | **$262.00** | **$15,720.00** |
| | **Item Code 206614 Total No. of Proj.** | | | **2** | | **Total Amount** | **$15,720.00** |
| **206749** | 8 STATION IRRIGATION CONTROLLER (WALL MOUNTED) | EA | 4 | 1 | 1.00 | $1,871.00 | $1,871.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,871.00** | **$1,871.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 206749 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,871.00** |
| **206753** | 24 STATION IRRIGATION CONTROLLER (WALL MOUNTED) | EA | 4 | 1 | 1.00 | $3,571.00 | $3,571.00 |
| | | EA | 6 | 2 | 8.00 | $8,858.13 | $70,865.00 |
| | | EA | 8 | 1 | 2.00 | $2,050.00 | $4,100.00 |
| | **Unit Sub Total** | **EA** | | **4** | **11.00** | **$7,139.64** | **$78,536.00** |
| | **Item Code 206753 Total No. of Proj.** | | | **4** | | **Total Amount** | **$78,536.00** |
| **208000** | IRRIGATION SYSTEM | LS | 2 | 4 | 4.00 | $82,625.50 | $330,502.00 |
| | | LS | 3 | 7 | 7.00 | $49,685.71 | $347,800.00 |
| | | LS | 4 | 4 | 4.00 | $38,675.00 | $154,700.00 |
| | | LS | 5 | 13 | 13.00 | $80,085.76 | $1,041,114.87 |
| | | LS | 6 | 5 | 5.00 | $130,550.00 | $652,750.00 |
| | | LS | 7 | 12 | 12.00 | $56,333.33 | $676,000.00 |
| | | LS | 8 | 3 | 3.00 | $50,566.67 | $151,700.00 |
| | | LS | 10 | 2 | 2.00 | $9,516.70 | $19,033.40 |
| | | LS | 11 | 14 | 14.00 | $117,448.40 | $1,644,277.66 |
| | | LS | 12 | 7 | 7.00 | $18,668.57 | $130,680.00 |
| | **Unit Sub Total** | **LS** | | **71** | **71.00** | **$72,514.90** | **$5,148,557.93** |
| | **Item Code 208000 Total No. of Proj.** | | | **71** | | **Total Amount** | **$5,148,557.93** |
| **208024** | 100 MM GALVANIZED STEEL PIPE (SUPPLY LINE) | M | 11 | 1 | 3.00 | $600.00 | $1,800.00 |
| | **Unit Sub Total** | **M** | | **1** | **3.00** | **$600.00** | **$1,800.00** |
| | **Item Code 208024 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,800.00** |
| **208036** | NPS 2 SUPPLY LINE (BRIDGE) | M | 5 | 1 | 39.00 | $9.00 | $351.00 |
| | **Unit Sub Total** | **M** | | **1** | **39.00** | **$9.00** | **$351.00** |
| | **Item Code 208036 Total No. of Proj.** | | | **1** | | **Total Amount** | **$351.00** |
| **208038** | NPS 3 SUPPLY LINE (BRIDGE) | M | 5 | 1 | 39.00 | $25.40 | $990.60 |
| | | M | 11 | 2 | 1,335.00 | $324.44 | $433,125.00 |
| | **Unit Sub Total** | **M** | | **3** | **1,374.00** | **$315.95** | **$434,115.60** |
| | **Item Code 208038 Total No. of Proj.** | | | **3** | | **Total Amount** | **$434,115.60** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **208039** | NPS 4 SUPPLY LINE (BRIDGE) | M | 11 | 3 | 1,226.00 | $259.85 | $318,580.00 |
| | **Unit Sub Total** | **M** | | **3** | **1,226.00** | **$259.85** | **$318,580.00** |
| | **Item Code 208039 Total No. of Proj.** | | | **3** | | **Total Amount** | **$318,580.00** |
| **208046** | 4" GALVANIZED STEEL PIPE (SUPPLY LINE ON BRIDGE) | LF | 3 | 1 | 180.00 | $40.13 | $7,223.40 |
| | **Unit Sub Total** | **LF** | | **1** | **180.00** | **$40.13** | **$7,223.40** |
| | **Item Code 208046 Total No. of Proj.** | | | **1** | | **Total Amount** | **$7,223.40** |
| **208214** | 15 MM PLASTIC PIPE (IRRIGATION LINE) | M | 4 | 1 | 8,864.00 | $0.98 | $8,686.72 |
| | **Unit Sub Total** | **M** | | **1** | **8,864.00** | **$0.98** | **$8,686.72** |
| | **Item Code 208214 Total No. of Proj.** | | | **1** | | **Total Amount** | **$8,686.72** |
| **208249** | 20 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | M | 4 | 1 | 750.00 | $7.30 | $5,475.00 |
| | | M | 6 | 1 | 3,438.00 | $6.00 | $20,628.00 |
| | **Unit Sub Total** | **M** | | **2** | **4,188.00** | **$6.23** | **$26,103.00** |
| | **Item Code 208249 Total No. of Proj.** | | | **2** | | **Total Amount** | **$26,103.00** |
| **208250** | 25 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | M | 4 | 1 | 348.00 | $7.50 | $2,610.00 |
| | | M | 6 | 1 | 2,184.00 | $7.00 | $15,288.00 |
| | | M | 11 | 2 | 28,072.00 | $6.19 | $173,861.31 |
| | **Unit Sub Total** | **M** | | **4** | **30,604.00** | **$6.27** | **$191,759.31** |
| | **Item Code 208250 Total No. of Proj.** | | | **4** | | **Total Amount** | **$191,759.31** |
| **208251** | 32 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | M | 4 | 1 | 563.00 | $7.90 | $4,447.70 |
| | | M | 6 | 1 | 1,799.00 | $8.00 | $14,392.00 |
| | | M | 11 | 2 | 6,025.00 | $6.60 | $39,792.15 |
| | **Unit Sub Total** | **M** | | **4** | **8,387.00** | **$6.99** | **$58,631.85** |
| | **Item Code 208251 Total No. of Proj.** | | | **4** | | **Total Amount** | **$58,631.85** |
| **208252** | 40 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | M | 4 | 1 | 558.00 | $8.20 | $4,575.60 |
| | | M | 5 | 1 | 150.00 | $30.25 | $4,537.50 |
| | | M | 6 | 1 | 1,040.00 | $9.00 | $9,360.00 |
| | | M | 11 | 2 | 4,954.00 | $7.00 | $34,662.12 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **M** | | **5** | **6,702.00** | **$7.93** | **$53,135.22** |
| | **Item Code 208252 Total No. of Proj.** | | | **5** | | **Total Amount** | **$53,135.22** |
| **208253** | 50 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | M | 6 | 1 | 1,159.00 | $10.00 | $11,590.00 |
| | | M | 11 | 2 | 6,854.00 | $9.56 | $65,529.65 |
| | **Unit Sub Total** | **M** | | **3** | **8,013.00** | **$9.62** | **$77,119.65** |
| | **Item Code 208253 Total No. of Proj.** | | | **3** | | **Total Amount** | **$77,119.65** |
| **208254** | 65 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | M | 6 | 1 | 3,297.00 | $11.00 | $36,267.00 |
| | | M | 11 | 2 | 3,371.00 | $9.91 | $33,390.29 |
| | **Unit Sub Total** | **M** | | **3** | **6,668.00** | **$10.45** | **$69,657.29** |
| | **Item Code 208254 Total No. of Proj.** | | | **3** | | **Total Amount** | **$69,657.29** |
| **208255** | 75 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | M | 6 | 1 | 917.00 | $12.00 | $11,004.00 |
| | | M | 11 | 2 | 7,334.00 | $9.82 | $72,008.50 |
| | **Unit Sub Total** | **M** | | **3** | **8,251.00** | **$10.06** | **$83,012.50** |
| | **Item Code 208255 Total No. of Proj.** | | | **3** | | **Total Amount** | **$83,012.50** |
| **208256** | 100 MM PLASTIC PIPE (PR 200) (SUPPLY LINE) | M | 11 | 2 | 2,029.00 | $32.26 | $65,460.00 |
| | **Unit Sub Total** | **M** | | **2** | **2,029.00** | **$32.26** | **$65,460.00** |
| | **Item Code 208256 Total No. of Proj.** | | | **2** | | **Total Amount** | **$65,460.00** |
| **208262** | 3/4" PLASTIC PIPE (PR 200) (SUPPLY LINE) | LF | 4 | 1 | 4,895.00 | $1.00 | $4,895.00 |
| | | LF | 6 | 1 | 1,022.00 | $1.09 | $1,113.98 |
| | | LF | 10 | 1 | 26,792.00 | $1.00 | $26,792.00 |
| | | LF | 12 | 1 | 18,880.00 | $1.65 | $31,152.00 |
| | **Unit Sub Total** | **LF** | | **4** | **51,589.00** | **$1.24** | **$63,952.98** |
| | **Item Code 208262 Total No. of Proj.** | | | **4** | | **Total Amount** | **$63,952.98** |
| **208263** | 1" PLASTIC PIPE (PR 200) (SUPPLY LINE) | LF | 3 | 1 | 13,300.00 | $0.98 | $13,034.00 |
| | | LF | 4 | 1 | 435.00 | $2.00 | $870.00 |
| | | LF | 6 | 1 | 754.00 | $1.21 | $912.34 |
| | | LF | 10 | 1 | 5,051.00 | $1.10 | $5,556.10 |
| | | LF | 11 | 1 | 1,800.00 | $1.42 | $2,556.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **208263** | 1" PLASTIC PIPE (PR 200) (SUPPLY LINE) | LF | 12 | 1 | 11,206.00 | $1.69 | $18,938.14 |
| | **Unit Sub Total** | **LF** | | **6** | **32,546.00** | **$1.29** | **$41,866.58** |
| | **Item Code 208263 Total No. of Proj.** | | | **6** | | **Total Amount** | **$41,866.58** |
| **208264** | 1 1/4" PLASTIC PIPE (PR 200) (SUPPLY LINE) | LF | 3 | 1 | 2,600.00 | $1.13 | $2,938.00 |
| | | LF | 4 | 1 | 240.00 | $3.00 | $720.00 |
| | | LF | 6 | 1 | 1,589.00 | $1.30 | $2,065.70 |
| | | LF | 10 | 1 | 1,214.00 | $1.20 | $1,456.80 |
| | | LF | 12 | 1 | 8,309.00 | $1.78 | $14,790.02 |
| | **Unit Sub Total** | **LF** | | **5** | **13,952.00** | **$1.57** | **$21,970.52** |
| | **Item Code 208264 Total No. of Proj.** | | | **5** | | **Total Amount** | **$21,970.52** |
| **208265** | 1 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE) | LF | 3 | 1 | 1,830.00 | $1.24 | $2,269.20 |
| | | LF | 4 | 1 | 60.00 | $3.00 | $180.00 |
| | | LF | 6 | 1 | 882.00 | $1.47 | $1,296.54 |
| | | LF | 10 | 1 | 45.00 | $1.40 | $63.00 |
| | | LF | 12 | 1 | 3,959.00 | $1.86 | $7,363.74 |
| | **Unit Sub Total** | **LF** | | **5** | **6,776.00** | **$1.65** | **$11,172.48** |
| | **Item Code 208265 Total No. of Proj.** | | | **5** | | **Total Amount** | **$11,172.48** |
| **208266** | 2" PLASTIC PIPE (PR 200) (SUPPLY LINE) | LF | 3 | 1 | 4,060.00 | $1.51 | $6,130.60 |
| | | LF | 4 | 1 | 1,750.00 | $1.00 | $1,750.00 |
| | | LF | 6 | 2 | 3,461.00 | $2.05 | $7,109.84 |
| | | LF | 10 | 1 | 2,557.00 | $1.98 | $5,062.86 |
| | | LF | 12 | 1 | 5,421.00 | $3.71 | $20,111.91 |
| | **Unit Sub Total** | **LF** | | **6** | **17,249.00** | **$2.33** | **$40,165.21** |
| | **Item Code 208266 Total No. of Proj.** | | | **6** | | **Total Amount** | **$40,165.21** |
| **208267** | 2 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE) | LF | 6 | 1 | 75.00 | $2.63 | $197.25 |
| | | LF | 12 | 1 | 2,728.00 | $3.96 | $10,802.88 |
| | **Unit Sub Total** | **LF** | | **2** | **2,803.00** | **$3.92** | **$11,000.13** |
| | **Item Code 208267 Total No. of Proj.** | | | **2** | | **Total Amount** | **$11,000.13** |
| **208268** | 3" PLASTIC PIPE (PR 200) (SUPPLY LINE) | LF | 10 | 1 | 5,404.00 | $3.02 | $16,320.08 |
| | | LF | 11 | 2 | 3,470.00 | $5.33 | $18,486.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **LF** | | **3** | **8,874.00** | **$3.92** | **$34,806.08** |
| | **Item Code 208268 Total No. of Proj.** | | | **3** | | **Total Amount** | **$34,806.08** |
| **208278** | 3" PLASTIC PIPE (PR 315) (SUPPLY LINE) | LF | 12 | 1 | 13,124.00 | $4.96 | $65,095.04 |
| | **Unit Sub Total** | **LF** | | **1** | **13,124.00** | **$4.96** | **$65,095.04** |
| | **Item Code 208278 Total No. of Proj.** | | | **1** | | **Total Amount** | **$65,095.04** |
| **208279** | 4" PLASTIC PIPE (PR 315) (SUPPLY LINE) | LF | 3 | 1 | 6,520.00 | $5.99 | $39,054.80 |
| | **Unit Sub Total** | **LF** | | **1** | **6,520.00** | **$5.99** | **$39,054.80** |
| | **Item Code 208279 Total No. of Proj.** | | | **1** | | **Total Amount** | **$39,054.80** |
| **208281** | 6" PLASTIC PIPE (PR 200) (SUPPLY LINE) | LF | 11 | 2 | 40.00 | $29.45 | $1,178.00 |
| | **Unit Sub Total** | **LF** | | **2** | **40.00** | **$29.45** | **$1,178.00** |
| | **Item Code 208281 Total No. of Proj.** | | | **2** | | **Total Amount** | **$1,178.00** |
| **208289** | 65 MM PLASTIC PIPE (PR 315) (SUPPLY LINE) | M | 4 | 1 | 66.00 | $82.00 | $5,412.00 |
| | **Unit Sub Total** | **M** | | **1** | **66.00** | **$82.00** | **$5,412.00** |
| | **Item Code 208289 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,412.00** |
| **208304** | WATER METER | EA | 4 | 1 | 1.00 | $28,177.00 | $28,177.00 |
| | | EA | 6 | 3 | 12.00 | $1,000.00 | $12,000.00 |
| | | EA | 10 | 1 | 1.00 | $12,000.00 | $12,000.00 |
| | | EA | 11 | 9 | 15.00 | $27,858.00 | $417,870.00 |
| | **Unit Sub Total** | **EA** | | **14** | **29.00** | **$16,208.52** | **$470,047.00** |
| | **Item Code 208304 Total No. of Proj.** | | | **14** | | **Total Amount** | **$470,047.00** |
| **208310** | IRRIGATION SLEEVE | LF | 5 | 1 | 950.00 | $35.00 | $33,250.00 |
| | | LF | 7 | 1 | 96.00 | $50.00 | $4,800.00 |
| | | LF | 8 | 1 | 380.00 | $12.00 | $4,560.00 |
| | | LF | 10 | 1 | 200.00 | $7.30 | $1,460.00 |
| | | LF | 11 | 1 | 40.00 | $40.00 | $1,600.00 |
| | | LF | 12 | 1 | 160.00 | $23.74 | $3,798.40 |
| | **Unit Sub Total** | **LF** | | **6** | **1,826.00** | **$27.09** | **$49,468.40** |
| **208310** | IRRIGATION SLEEVE | M | 2 | 1 | 10.00 | $171.00 | $1,710.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **208310** | IRRIGATION SLEEVE | M | 4 | 2 | 68.00 | $109.19 | $7,425.00 |
| | | M | 5 | 1 | 15.00 | $30.00 | $450.00 |
| | | M | 7 | 1 | 55.00 | $100.00 | $5,500.00 |
| | | M | 11 | 1 | 45.00 | $201.00 | $9,045.00 |
| | **Unit Sub Total** | **M** | | **6** | **193.00** | **$125.03** | **$24,130.00** |
| | **Item Code 208310 Total No. of Proj.** | | | **12** | | **Total Amount** | **$73,598.40** |
| **208420** | BACKFLOW PREVENTER ASSEMBLY | EA | 6 | 1 | 1.00 | $1,108.00 | $1,108.00 |
| | | EA | 11 | 2 | 3.00 | $22,916.67 | $68,750.00 |
| | **Unit Sub Total** | **EA** | | **3** | **4.00** | **$17,464.50** | **$69,858.00** |
| | **Item Code 208420 Total No. of Proj.** | | | **3** | | **Total Amount** | **$69,858.00** |
| **208421** | BACKFLOW PREVENTER ASSEMBLY ENCLOSURE | EA | 3 | 1 | 1.00 | $2,223.74 | $2,223.74 |
| | | EA | 4 | 2 | 8.00 | $2,164.03 | $17,312.20 |
| | | EA | 6 | 3 | 12.00 | $1,713.36 | $20,560.33 |
| | | EA | 8 | 1 | 2.00 | $1,325.00 | $2,650.00 |
| | | EA | 10 | 1 | 1.00 | $20,185.85 | $20,185.85 |
| | | EA | 11 | 2 | 5.00 | $1,968.76 | $9,843.80 |
| | **Unit Sub Total** | **EA** | | **10** | **29.00** | **$2,509.51** | **$72,775.92** |
| | **Item Code 208421 Total No. of Proj.** | | | **10** | | **Total Amount** | **$72,775.92** |
| **208426** | 2" BACKFLOW PREVENTER ASSEMBLY | EA | 6 | 1 | 7.00 | $1,610.48 | $11,273.36 |
| | | EA | 8 | 1 | 2.00 | $2,600.00 | $5,200.00 |
| | | EA | 10 | 1 | 1.00 | $12,560.50 | $12,560.50 |
| | **Unit Sub Total** | **EA** | | **3** | **10.00** | **$2,903.39** | **$29,033.86** |
| | **Item Code 208426 Total No. of Proj.** | | | **3** | | **Total Amount** | **$29,033.86** |
| **208428** | 3" BACKFLOW PREVENTER ASSEMBLY | EA | 3 | 1 | 1.00 | $2,871.52 | $2,871.52 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$2,871.52** | **$2,871.52** |
| | **Item Code 208428 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,871.52** |
| **208432** | 25 MM BACKFLOW PREVENTER ASSEMBLY | EA | 4 | 1 | 1.00 | $654.00 | $654.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$654.00** | **$654.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 208432 Total No. of Proj.** | | | **1** | | **Total Amount** | **$654.00** |
| **208434** | 40 MM BACKFLOW PREVENTER ASSEMBLY | EA | 4 | 1 | 1.00 | $1,057.00 | $1,057.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,057.00** | **$1,057.00** |
| | **Item Code 208434 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,057.00** |
| **208435** | 50 MM BACKFLOW PREVENTER ASSEMBLY | EA | 4 | 2 | 7.00 | $3,204.00 | $22,428.00 |
| | | EA | 6 | 1 | 4.00 | $1,800.00 | $7,200.00 |
| | | EA | 11 | 2 | 5.00 | $1,585.71 | $7,928.55 |
| | **Unit Sub Total** | **EA** | | **5** | **16.00** | **$2,347.28** | **$37,556.55** |
| | **Item Code 208435 Total No. of Proj.** | | | **5** | | **Total Amount** | **$37,556.55** |
| **208439** | BACKFLOW PREVENTER ASSEMBLY BLANKET | EA | 3 | 1 | 1.00 | $153.81 | $153.81 |
| | | EA | 6 | 2 | 11.00 | $127.50 | $1,402.55 |
| | | EA | 10 | 1 | 1.00 | $112.50 | $112.50 |
| | **Unit Sub Total** | **EA** | | **4** | **13.00** | **$128.37** | **$1,668.86** |
| | **Item Code 208439 Total No. of Proj.** | | | **4** | | **Total Amount** | **$1,668.86** |
| **208461** | SPRINKLER (TYPE A-1) | EA | 6 | 1 | 330.00 | $35.00 | $11,550.00 |
| | **Unit Sub Total** | **EA** | | **1** | **330.00** | **$35.00** | **$11,550.00** |
| | **Item Code 208461 Total No. of Proj.** | | | **1** | | **Total Amount** | **$11,550.00** |
| **208463** | SPRINKLER (TYPE A-3) | EA | 6 | 1 | 140.00 | $35.00 | $4,900.00 |
| | | EA | 12 | 1 | 330.00 | $19.65 | $6,484.50 |
| | **Unit Sub Total** | **EA** | | **2** | **470.00** | **$24.22** | **$11,384.50** |
| | **Item Code 208463 Total No. of Proj.** | | | **2** | | **Total Amount** | **$11,384.50** |
| **208464** | SPRINKLER (TYPE A-4) | EA | 12 | 1 | 76.00 | $22.33 | $1,697.08 |
| | **Unit Sub Total** | **EA** | | **1** | **76.00** | **$22.33** | **$1,697.08** |
| | **Item Code 208464 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,697.08** |
| **208465** | SPRINKLER (TYPE A-5) | EA | 11 | 3 | 591.00 | $41.61 | $24,594.40 |
| | | EA | 12 | 1 | 180.00 | $42.43 | $7,637.40 |
| | **Unit Sub Total** | **EA** | | **4** | **771.00** | **$41.81** | **$32,231.80** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 208465 Total No. of Proj.** | | | **4** | | **Total Amount** | **$32,231.80** |
| **208466** | SPRINKLER (TYPE A-6) | EA | 11 | 2 | 98.00 | $31.53 | $3,090.00 |
| | | EA | 12 | 1 | 180.00 | $45.11 | $8,119.80 |
| | **Unit Sub Total** | **EA** | | **3** | **278.00** | **$40.32** | **$11,209.80** |
| | **Item Code 208466 Total No. of Proj.** | | | **3** | | **Total Amount** | **$11,209.80** |
| **208467** | SPRINKLER (TYPE A-7) | EA | 3 | 1 | 62.00 | $38.96 | $2,415.52 |
| | | EA | 11 | 3 | 1,573.00 | $47.47 | $74,668.00 |
| | | EA | 12 | 1 | 320.00 | $13.97 | $4,470.40 |
| | **Unit Sub Total** | **EA** | | **5** | **1,955.00** | **$41.72** | **$81,553.92** |
| | **Item Code 208467 Total No. of Proj.** | | | **5** | | **Total Amount** | **$81,553.92** |
| **208468** | SPRINKLER (TYPE A-8) | EA | 3 | 1 | 120.00 | $33.65 | $4,038.00 |
| | | EA | 11 | 1 | 73.00 | $80.00 | $5,840.00 |
| | | EA | 12 | 1 | 270.00 | $37.31 | $10,073.70 |
| | **Unit Sub Total** | **EA** | | **3** | **463.00** | **$43.09** | **$19,951.70** |
| | **Item Code 208468 Total No. of Proj.** | | | **3** | | **Total Amount** | **$19,951.70** |
| **208471** | SPRINKLER (TYPE B-1) | EA | 3 | 1 | 14.00 | $22.80 | $319.20 |
| | | EA | 12 | 1 | 550.00 | $12.90 | $7,095.00 |
| | **Unit Sub Total** | **EA** | | **2** | **564.00** | **$13.15** | **$7,414.20** |
| | **Item Code 208471 Total No. of Proj.** | | | **2** | | **Total Amount** | **$7,414.20** |
| **208472** | SPRINKLER (TYPE B-2) | EA | 3 | 1 | 200.00 | $32.19 | $6,438.00 |
| | | EA | 6 | 1 | 65.00 | $20.00 | $1,300.00 |
| | | EA | 11 | 1 | 110.00 | $20.00 | $2,200.00 |
| | **Unit Sub Total** | **EA** | | **3** | **375.00** | **$26.50** | **$9,938.00** |
| | **Item Code 208472 Total No. of Proj.** | | | **3** | | **Total Amount** | **$9,938.00** |
| **208480** | SPRINKLER TYPE C-2 MOD | EA | 11 | 3 | 2,194.00 | $34.85 | $76,462.18 |
| | **Unit Sub Total** | **EA** | | **3** | **2,194.00** | **$34.85** | **$76,462.18** |
| | **Item Code 208480 Total No. of Proj.** | | | **3** | | **Total Amount** | **$76,462.18** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **208482** | SPRINKLER (TYPE C-2) | EA | 3 | 1 | 1,070.00 | $23.79 | $25,455.30 |
| | | EA | 4 | 1 | 420.00 | $4.00 | $1,680.00 |
| | | EA | 6 | 1 | 200.00 | $6.00 | $1,200.00 |
| | | EA | 8 | 1 | 710.00 | $11.40 | $8,094.00 |
| | | EA | 11 | 1 | 190.00 | $15.00 | $2,850.00 |
| | **Unit Sub Total** | **EA** | | **5** | **2,590.00** | **$15.17** | **$39,279.30** |
| | **Item Code 208482 Total No. of Proj.** | | | **5** | | **Total Amount** | **$39,279.30** |
| **208483** | SPRINKLER (TYPE C-3) | EA | 6 | 2 | 1,680.00 | $9.65 | $16,205.00 |
| | | EA | 10 | 1 | 870.00 | $5.65 | $4,915.50 |
| | **Unit Sub Total** | **EA** | | **3** | **2,550.00** | **$8.28** | **$21,120.50** |
| | **Item Code 208483 Total No. of Proj.** | | | **3** | | **Total Amount** | **$21,120.50** |
| **208489** | 32 MM GATE VALVE | EA | 4 | 1 | 1.00 | $141.00 | $141.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$141.00** | **$141.00** |
| | **Item Code 208489 Total No. of Proj.** | | | **1** | | **Total Amount** | **$141.00** |
| **208490** | 40 MM GATE VALVE | EA | 4 | 1 | 2.00 | $148.60 | $297.20 |
| | | EA | 11 | 1 | 5.00 | $220.00 | $1,100.00 |
| | **Unit Sub Total** | **EA** | | **2** | **7.00** | **$199.60** | **$1,397.20** |
| | **Item Code 208490 Total No. of Proj.** | | | **2** | | **Total Amount** | **$1,397.20** |
| **208491** | 50 MM GATE VALVE | EA | 11 | 2 | 77.00 | $280.88 | $21,627.75 |
| | **Unit Sub Total** | **EA** | | **2** | **77.00** | **$280.88** | **$21,627.75** |
| | **Item Code 208491 Total No. of Proj.** | | | **2** | | **Total Amount** | **$21,627.75** |
| **208492** | 65 MM GATE VALVE | EA | 11 | 1 | 11.00 | $420.00 | $4,620.00 |
| | **Unit Sub Total** | **EA** | | **1** | **11.00** | **$420.00** | **$4,620.00** |
| | **Item Code 208492 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,620.00** |
| **208493** | 75 MM GATE VALVE | EA | 11 | 2 | 33.00 | $517.52 | $17,078.30 |
| | **Unit Sub Total** | **EA** | | **2** | **33.00** | **$517.52** | **$17,078.30** |
| | **Item Code 208493 Total No. of Proj.** | | | **2** | | **Total Amount** | **$17,078.30** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **208494** | 100 MM GATE VALVE | EA | 11 | 2 | 5.00 | $660.00 | $3,300.00 |
| | **Unit Sub Total** | **EA** | | **2** | **5.00** | **$660.00** | **$3,300.00** |
| | **Item Code 208494 Total No. of Proj.** | | | **2** | | **Total Amount** | **$3,300.00** |
| **208495** | 150 MM GATE VALVE | EA | 11 | 1 | 2.00 | $500.00 | $1,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$500.00** | **$1,000.00** |
| | **Item Code 208495 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,000.00** |
| **208509** | 25 MM WYE STRAINER | EA | 4 | 1 | 5.00 | $143.28 | $716.40 |
| | **Unit Sub Total** | **EA** | | **1** | **5.00** | **$143.28** | **$716.40** |
| | **Item Code 208509 Total No. of Proj.** | | | **1** | | **Total Amount** | **$716.40** |
| **208510** | 32 MM WYE STRAINER | EA | 4 | 1 | 3.00 | $163.84 | $491.52 |
| | **Unit Sub Total** | **EA** | | **1** | **3.00** | **$163.84** | **$491.52** |
| | **Item Code 208510 Total No. of Proj.** | | | **1** | | **Total Amount** | **$491.52** |
| **208517** | 20 MM QUICK COUPLING VALVE | EA | 4 | 1 | 8.00 | $143.35 | $1,146.80 |
| | **Unit Sub Total** | **EA** | | **1** | **8.00** | **$143.35** | **$1,146.80** |
| | **Item Code 208517 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,146.80** |
| **208526** | SPRINKLER (TYPE D-1) | EA | 4 | 1 | 6,840.00 | $5.58 | $38,167.20 |
| | **Unit Sub Total** | **EA** | | **1** | **6,840.00** | **$5.58** | **$38,167.20** |
| | **Item Code 208526 Total No. of Proj.** | | | **1** | | **Total Amount** | **$38,167.20** |
| **208560** | FILTER ASSEMBLY UNIT | EA | 6 | 2 | 13.00 | $328.46 | $4,270.00 |
| | **Unit Sub Total** | **EA** | | **2** | **13.00** | **$328.46** | **$4,270.00** |
| | **Item Code 208560 Total No. of Proj.** | | | **2** | | **Total Amount** | **$4,270.00** |
| **208562** | CAM COUPLER ASSEMBLY | EA | 6 | 1 | 2.00 | $536.00 | $1,072.00 |
| | | EA | 10 | 1 | 6.00 | $525.00 | $3,150.00 |
| | **Unit Sub Total** | **EA** | | **2** | **8.00** | **$527.75** | **$4,222.00** |
| | **Item Code 208562 Total No. of Proj.** | | | **2** | | **Total Amount** | **$4,222.00** |
| **208565** | REPLACE VALVE BOX COVER | EA | 11 | 3 | 310.00 | $20.16 | $6,249.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **3** | **310.00** | **$20.16** | **$6,249.00** |
| | **Item Code 208565** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$6,249.00** |
| **208570** | 3/4" GATE VALVE | | EA | 10 | 1 | 9.00 | $115.00 | $1,035.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **9.00** | **$115.00** | **$1,035.00** |
| | **Item Code 208570** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,035.00** |
| **208572** | 1" GATE VALVE | | EA | 10 | 1 | 2.00 | $130.00 | $260.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$130.00** | **$260.00** |
| | **Item Code 208572** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$260.00** |
| **208574** | 1 1/2" GATE VALVE | | EA | 8 | 1 | 5.00 | $227.00 | $1,135.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **5.00** | **$227.00** | **$1,135.00** |
| | **Item Code 208574** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,135.00** |
| **208575** | 2" GATE VALVE | | EA | 6 | 2 | 9.00 | $152.00 | $1,368.04 |
| | | | EA | 8 | 1 | 1.00 | $305.00 | $305.00 |
| | | | EA | 10 | 1 | 6.00 | $181.00 | $1,086.00 |
| | | | EA | 11 | 1 | 2.00 | $353.53 | $707.06 |
| | | **Unit Sub Total** | **EA** | | **5** | **18.00** | **$192.56** | **$3,466.10** |
| | **Item Code 208575** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$3,466.10** |
| **208588** | 3" GATE VALVE | | EA | 11 | 2 | 5.00 | $572.60 | $2,863.01 |
| | | | EA | 12 | 1 | 10.00 | $523.44 | $5,234.40 |
| | | **Unit Sub Total** | **EA** | | **3** | **15.00** | **$539.83** | **$8,097.41** |
| | **Item Code 208588** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$8,097.41** |
| **208589** | 4" GATE VALVE | | EA | 3 | 1 | 8.00 | $514.13 | $4,113.04 |
| | | **Unit Sub Total** | **EA** | | **1** | **8.00** | **$514.13** | **$4,113.04** |
| | **Item Code 208589** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,113.04** |
| **208590** | 6" GATE VALVE | | EA | 11 | 1 | 1.00 | $1,500.00 | $1,500.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,500.00** | **$1,500.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 208590 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,500.00** |
| **208594** | 3/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE) | LF | 8 | 1 | 7,240.00 | $3.63 | $26,281.20 |
| | **Unit Sub Total** | **LF** | | **1** | **7,240.00** | **$3.63** | **$26,281.20** |
| | **Item Code 208594 Total No. of Proj.** | | | **1** | | **Total Amount** | **$26,281.20** |
| **208595** | 1" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE) | LF | 8 | 1 | 1,640.00 | $3.69 | $6,051.60 |
| | **Unit Sub Total** | **LF** | | **1** | **1,640.00** | **$3.69** | **$6,051.60** |
| | **Item Code 208595 Total No. of Proj.** | | | **1** | | **Total Amount** | **$6,051.60** |
| **208596** | 1 1/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE) | LF | 8 | 1 | 2,610.00 | $3.81 | $9,944.10 |
| | **Unit Sub Total** | **LF** | | **1** | **2,610.00** | **$3.81** | **$9,944.10** |
| | **Item Code 208596 Total No. of Proj.** | | | **1** | | **Total Amount** | **$9,944.10** |
| **208597** | 1 1/2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE) | LF | 8 | 1 | 870.00 | $3.83 | $3,332.10 |
| | **Unit Sub Total** | **LF** | | **1** | **870.00** | **$3.83** | **$3,332.10** |
| | **Item Code 208597 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,332.10** |
| **208598** | 2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE) | LF | 8 | 1 | 1,510.00 | $4.04 | $6,100.40 |
| | **Unit Sub Total** | **LF** | | **1** | **1,510.00** | **$4.04** | **$6,100.40** |
| | **Item Code 208598 Total No. of Proj.** | | | **1** | | **Total Amount** | **$6,100.40** |
| **208599** | 2 1/2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE) | LF | 8 | 1 | 550.00 | $4.58 | $2,519.00 |
| | **Unit Sub Total** | **LF** | | **1** | **550.00** | **$4.58** | **$2,519.00** |
| | **Item Code 208599 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,519.00** |
| **208625** | 3/4" WYE STRAINER | EA | 10 | 1 | 9.00 | $123.75 | $1,113.75 |
| | **Unit Sub Total** | **EA** | | **1** | **9.00** | **$123.75** | **$1,113.75** |
| | **Item Code 208625 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,113.75** |
| **208626** | 1" WYE STRAINER | EA | 10 | 1 | 2.00 | $136.50 | $273.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$136.50** | **$273.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 208626 Total No. of Proj.** | | | **1** | | **Total Amount** | **$273.00** |
| **208628** | 1 1/2" WYE STRAINER | EA | 4 | 1 | 4.00 | $250.00 | $1,000.00 |
| | | EA | 8 | 1 | 5.00 | $201.00 | $1,005.00 |
| | **Unit Sub Total** | **EA** | | **2** | **9.00** | **$222.78** | **$2,005.00** |
| | **Item Code 208628 Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,005.00** |
| **208630** | 2" WYE STRAINER | EA | 8 | 1 | 1.00 | $287.00 | $287.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$287.00** | **$287.00** |
| | **Item Code 208630 Total No. of Proj.** | | | **1** | | **Total Amount** | **$287.00** |
| **208649** | QUICK COUPLING VALVE | EA | 12 | 1 | 30.00 | $190.76 | $5,722.80 |
| | **Unit Sub Total** | **EA** | | **1** | **30.00** | **$190.76** | **$5,722.80** |
| | **Item Code 208649 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,722.80** |
| **208683** | BALL VALVE | EA | 3 | 1 | 8.00 | $205.60 | $1,644.80 |
| | | EA | 4 | 2 | 11.00 | $154.35 | $1,697.90 |
| | | EA | 6 | 2 | 19.00 | $173.79 | $3,302.00 |
| | | EA | 10 | 1 | 10.00 | $95.50 | $955.00 |
| | | EA | 12 | 1 | 30.00 | $204.81 | $6,144.30 |
| | **Unit Sub Total** | **EA** | | **7** | **78.00** | **$176.21** | **$13,744.00** |
| | **Item Code 208683 Total No. of Proj.** | | | **7** | | **Total Amount** | **$13,744.00** |
| **208697** | 100 MM CONDUIT | M | 2 | 1 | 190.00 | $47.00 | $8,930.00 |
| | **Unit Sub Total** | **M** | | **1** | **190.00** | **$47.00** | **$8,930.00** |
| | **Item Code 208697 Total No. of Proj.** | | | **1** | | **Total Amount** | **$8,930.00** |
| **208731** | 200 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT | M | 2 | 1 | 240.00 | $450.00 | $108,000.00 |
| | | M | 4 | 2 | 250.00 | $189.00 | $47,250.00 |
| | | M | 5 | 2 | 280.00 | $100.50 | $28,140.00 |
| | | M | 7 | 2 | 1,030.00 | $96.50 | $99,390.00 |
| | | M | 11 | 6 | 1,933.00 | $144.35 | $279,036.00 |
| | **Unit Sub Total** | **M** | | **13** | **3,733.00** | **$150.50** | **$561,816.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 208731 Total No. of Proj.** | | | **13** | | **Total Amount** | **$561,816.00** |
| **208732** | 250 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT | M | 5 | 2 | 190.00 | $105.33 | $20,012.00 |
| | | M | 11 | 4 | 1,069.00 | $222.74 | $238,110.00 |
| | **Unit Sub Total** | **M** | | **6** | **1,259.00** | **$205.02** | **$258,122.00** |
| | **Item Code 208732 Total No. of Proj.** | | | **6** | | **Total Amount** | **$258,122.00** |
| **208733** | 300 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT | M | 5 | 1 | 63.00 | $94.00 | $5,922.00 |
| | | M | 10 | 1 | 66.00 | $200.00 | $13,200.00 |
| | **Unit Sub Total** | **M** | | **2** | **129.00** | **$148.23** | **$19,122.00** |
| | **Item Code 208733 Total No. of Proj.** | | | **2** | | **Total Amount** | **$19,122.00** |
| **208738** | 8" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT | LF | 5 | 1 | 40.00 | $25.00 | $1,000.00 |
| | | LF | 6 | 1 | 180.00 | $91.42 | $16,455.60 |
| | **Unit Sub Total** | **LF** | | **2** | **220.00** | **$79.34** | **$17,455.60** |
| | **Item Code 208738 Total No. of Proj.** | | | **2** | | **Total Amount** | **$17,455.60** |
| **208739** | 10" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT | LF | 5 | 1 | 62.00 | $235.00 | $14,570.00 |
| | **Unit Sub Total** | **LF** | | **1** | **62.00** | **$235.00** | **$14,570.00** |
| | **Item Code 208739 Total No. of Proj.** | | | **1** | | **Total Amount** | **$14,570.00** |
| **208746** | 200 MM BITUMINOUS COATED STEEL PIPE CONDUIT (1.63 MM THICK) | M | 3 | 1 | 430.00 | $200.00 | $86,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **430.00** | **$200.00** | **$86,000.00** |
| | **Item Code 208746 Total No. of Proj.** | | | **1** | | **Total Amount** | **$86,000.00** |
| **208796** | 100 MM WELDED STEEL PIPE CONDUIT (6.02 MM THICK) | M | 3 | 1 | 8.00 | $400.00 | $3,200.00 |
| | **Unit Sub Total** | **M** | | **1** | **8.00** | **$400.00** | **$3,200.00** |
| | **Item Code 208796 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,200.00** |
| **208797** | 150 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK) | M | 5 | 1 | 15.00 | $218.15 | $3,272.25 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **M** | | **1** | **15.00** | **$218.15** | **$3,272.25** |
| | **Item Code 208797 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,272.25** |
| **208798** | 200 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK) | M | 5 | 1 | 150.00 | $264.60 | $39,690.00 |
| | | M | 6 | 1 | 83.00 | $125.00 | $10,375.00 |
| | | M | 11 | 6 | 798.00 | $261.05 | $208,314.00 |
| | **Unit Sub Total** | **M** | | **8** | **1,031.00** | **$250.61** | **$258,379.00** |
| | **Item Code 208798 Total No. of Proj.** | | | **8** | | **Total Amount** | **$258,379.00** |
| **208799** | 250 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK) | M | 5 | 1 | 62.00 | $334.80 | $20,757.60 |
| | | M | 7 | 1 | 65.00 | $576.00 | $37,440.00 |
| | | M | 11 | 2 | 108.00 | $538.06 | $58,110.00 |
| | **Unit Sub Total** | **M** | | **4** | **235.00** | **$494.93** | **$116,307.60** |
| | **Item Code 208799 Total No. of Proj.** | | | **4** | | **Total Amount** | **$116,307.60** |
| **208800** | 300 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK) | M | 8 | 1 | 1,050.00 | $870.00 | $913,500.00 |
| | **Unit Sub Total** | **M** | | **1** | **1,050.00** | **$870.00** | **$913,500.00** |
| | **Item Code 208800 Total No. of Proj.** | | | **1** | | **Total Amount** | **$913,500.00** |
| **208808** | 8" WELDED STEEL PIPE CONDUIT (.250" THICK) | LF | 3 | 1 | 40.00 | $80.00 | $3,200.00 |
| | | LF | 10 | 1 | 570.00 | $108.80 | $62,016.00 |
| | | LF | 11 | 1 | 990.00 | $130.00 | $128,700.00 |
| | **Unit Sub Total** | **LF** | | **3** | **1,600.00** | **$121.20** | **$193,916.00** |
| | **Item Code 208808 Total No. of Proj.** | | | **3** | | **Total Amount** | **$193,916.00** |
| **208905** | EXTEND 6" CONDUIT | LF | 3 | 1 | 15.00 | $116.00 | $1,740.00 |
| | **Unit Sub Total** | **LF** | | **1** | **15.00** | **$116.00** | **$1,740.00** |
| | **Item Code 208905 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,740.00** |
| **208906** | EXTEND 8" CONDUIT | LF | 3 | 2 | 1,118.00 | $74.53 | $83,322.80 |
| | **Unit Sub Total** | **LF** | | **2** | **1,118.00** | **$74.53** | **$83,322.80** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 208906 Total No. of Proj.** | | | **2** | | **Total Amount** | **$83,322.80** |
| **208907** | EXTEND 10" CONDUIT | LF | 3 | 1 | 880.00 | $75.00 | $66,000.00 |
| | | LF | 11 | 1 | 12.00 | $80.00 | $960.00 |
| | | LF | 12 | 1 | 62.00 | $365.00 | $22,630.00 |
| | **Unit Sub Total** | **LF** | | **3** | **954.00** | **$93.91** | **$89,590.00** |
| | **Item Code 208907 Total No. of Proj.** | | | **3** | | **Total Amount** | **$89,590.00** |
| **208908** | EXTEND 150 MM CONDUIT | M | 5 | 2 | 14.00 | $396.83 | $5,555.65 |
| | | M | 8 | 1 | 3.00 | $350.00 | $1,050.00 |
| | **Unit Sub Total** | **M** | | **3** | **17.00** | **$388.57** | **$6,605.65** |
| | **Item Code 208908 Total No. of Proj.** | | | **3** | | **Total Amount** | **$6,605.65** |
| **208909** | EXTEND 200 MM CONDUIT | M | 3 | 2 | 41.00 | $210.61 | $8,635.00 |
| | | M | 5 | 3 | 29.00 | $565.76 | $16,407.18 |
| | | M | 7 | 3 | 25.00 | $537.60 | $13,440.00 |
| | | M | 11 | 1 | 15.00 | $350.00 | $5,250.00 |
| | **Unit Sub Total** | **M** | | **9** | **110.00** | **$397.57** | **$43,732.18** |
| | **Item Code 208909 Total No. of Proj.** | | | **9** | | **Total Amount** | **$43,732.18** |
| **208910** | EXTEND 250 MM CONDUIT | LS | 12 | 1 | 1.00 | $4,500.00 | $4,500.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$4,500.00** | **$4,500.00** |
| **208910** | EXTEND 250 MM CONDUIT | M | 3 | 1 | 15.00 | $160.00 | $2,400.00 |
| | | M | 5 | 1 | 26.00 | $660.85 | $17,182.10 |
| | | M | 11 | 3 | 74.00 | $549.73 | $40,680.00 |
| | | M | 12 | 1 | 5.00 | $340.00 | $1,700.00 |
| | **Unit Sub Total** | **M** | | **6** | **120.00** | **$516.35** | **$61,962.10** |
| | **Item Code 208910 Total No. of Proj.** | | | **7** | | **Total Amount** | **$66,462.10** |
| **209202** | RECYCLED WATER WARNING SIGNS | LS | 11 | 2 | 2.00 | $2,000.00 | $4,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$2,000.00** | **$4,000.00** |
| | **Item Code 209202 Total No. of Proj.** | | | **2** | | **Total Amount** | **$4,000.00** |
| **209502** | BOOSTER PUMP | EA | 11 | 1 | 1.00 | $25,000.00 | $25,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$25,000.00** | **$25,000.00** |
| | **Item Code 209502** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$25,000.00** |
| **209503** | BOOSTER PUMP SYSTEM | | EA | 2 | 1 | 1.00 | $9,000.00 | $9,000.00 |
| | | | EA | 6 | 2 | 12.00 | $19,777.00 | $237,324.00 |
| | | | EA | 10 | 1 | 1.00 | $18,450.00 | $18,450.00 |
| | | **Unit Sub Total** | **EA** | | **4** | **14.00** | **$18,912.43** | **$264,774.00** |
| **209503** | BOOSTER PUMP SYSTEM | | LS | 2 | 1 | 1.00 | $92,515.00 | $92,515.00 |
| | | | LS | 11 | 1 | 1.00 | $20,000.00 | $20,000.00 |
| | | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$56,257.50** | **$112,515.00** |
| | **Item Code 209503** | **Total No. of Proj.** | | | **6** | | **Total Amount** | **$377,289.00** |
| **209801** | MAINTENANCE VEHICLE PULLOUT | | EA | 6 | 1 | 3.00 | $6,600.00 | $19,800.00 |
| | | | EA | 12 | 1 | 5.00 | $8,347.87 | $41,739.35 |
| | | **Unit Sub Total** | **EA** | | **2** | **8.00** | **$7,692.42** | **$61,539.35** |
| | **Item Code 209801** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$61,539.35** |
| **220101** | FINISHING ROADWAY | | LS | 2 | 1 | 1.00 | $50,000.00 | $50,000.00 |
| | | | LS | 3 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | | | LS | 4 | 1 | 1.00 | $20,000.00 | $20,000.00 |
| | | | LS | 5 | 1 | 1.00 | $17,000.00 | $17,000.00 |
| | | | LS | 9 | 2 | 2.00 | $30,000.00 | $60,000.00 |
| | | | LS | 11 | 7 | 7.00 | $30,785.71 | $215,500.00 |
| | | **Unit Sub Total** | **LS** | | **13** | **13.00** | **$27,961.54** | **$363,500.00** |
| | **Item Code 220101** | **Total No. of Proj.** | | | **13** | | **Total Amount** | **$363,500.00** |
| **240100** | LIME | | TONN | 4 | 3 | 13,250.00 | $177.81 | $2,356,010.00 |
| | | **Unit Sub Total** | **TONN** | | **3** | **13,250.00** | **$177.81** | **$2,356,010.00** |
| | **Item Code 240100** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$2,356,010.00** |
| **250201** | CLASS 2 AGGREGATE SUBBASE | | CY | 6 | 2 | 8,690.00 | $19.60 | $170,303.00 |
| | | | CY | 12 | 6 | 9,312.90 | $25.50 | $237,488.00 |
| | | **Unit Sub Total** | **CY** | | **8** | **18,002.90** | **$22.65** | **$407,791.00** |
| **250201** | CLASS 2 AGGREGATE SUBBASE | | M3 | 3 | 3 | 191,070.00 | $31.33 | $5,985,790.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **250201** | CLASS 2 AGGREGATE SUBBASE | | M3 | 6 | 1 | 6,490.00 | $24.00 | $155,760.00 |
| | | | M3 | 7 | 1 | 26.00 | $100.00 | $2,600.00 |
| | | | M3 | 8 | 1 | 11,100.00 | $40.00 | $444,000.00 |
| | | **Unit Sub Total** | **M3** | | **6** | **208,686.00** | **$31.57** | **$6,588,150.00** |
| | **Item Code 250201** | **Total No. of Proj.** | | | **14** | | **Total Amount** | **$6,995,941.00** |
| **250401** | CLASS 4 AGGREGATE SUBBASE | | CY | 4 | 3 | 2,560.00 | $24.34 | $62,310.00 |
| | | | CY | 7 | 2 | 242.60 | $79.65 | $19,324.24 |
| | | | CY | 11 | 2 | 35,240.00 | $18.27 | $643,840.00 |
| | | **Unit Sub Total** | **CY** | | **7** | **38,042.60** | **$19.07** | **$725,474.24** |
| **250401** | CLASS 4 AGGREGATE SUBBASE | | M3 | 4 | 7 | 166,186.10 | $13.77 | $2,288,323.00 |
| | | | M3 | 5 | 1 | 68,900.00 | $34.40 | $2,370,160.00 |
| | | | M3 | 7 | 4 | 1,730.00 | $56.92 | $98,470.00 |
| | | | M3 | 11 | 6 | 205,890.00 | $31.09 | $6,400,260.00 |
| | | **Unit Sub Total** | **M3** | | **18** | **442,706.10** | **$25.20** | **$11,157,213.00** |
| | **Item Code 250401** | **Total No. of Proj.** | | | **25** | | **Total Amount** | **$11,882,687.24** |
| **260201** | CLASS 2 AGGREGATE BASE | | CY | 1 | 8 | 4,992.00 | $51.99 | $259,525.00 |
| | | | CY | 2 | 13 | 20,943.00 | $45.01 | $942,695.00 |
| | | | CY | 3 | 19 | 268,800.00 | $29.98 | $8,058,459.50 |
| | | | CY | 4 | 1 | 2.00 | $500.00 | $1,000.00 |
| | | | CY | 5 | 4 | 5,183.00 | $68.37 | $354,361.40 |
| | | | CY | 6 | 6 | 10,343.00 | $32.16 | $332,646.00 |
| | | | CY | 7 | 2 | 78.10 | $104.81 | $8,185.90 |
| | | | CY | 8 | 7 | 7,403.00 | $60.54 | $448,192.50 |
| | | | CY | 10 | 1 | 500.00 | $49.00 | $24,500.00 |
| | | | CY | 11 | 6 | 8,951.00 | $41.72 | $373,458.00 |
| | | | CY | 12 | 8 | 1,451.00 | $57.63 | $83,616.00 |
| | | **Unit Sub Total** | **CY** | | **75** | **328,646.10** | **$33.13** | **$10,886,639.30** |
| **260201** | CLASS 2 AGGREGATE BASE | | M3 | 1 | 7 | 48,150.00 | $65.14 | $3,136,620.00 |
| | | | M3 | 2 | 5 | 30,500.00 | $63.48 | $1,936,067.80 |
| | | | M3 | 3 | 8 | 388,070.00 | $40.37 | $15,666,100.00 |
| | | | M3 | 4 | 2 | 136.00 | $64.78 | $8,810.00 |
| | | | M3 | 5 | 13 | 93,140.00 | $53.68 | $4,999,498.50 |
| | | | M3 | 6 | 6 | 62,820.00 | $40.27 | $2,529,550.50 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **260201** | CLASS 2 AGGREGATE BASE | M3 | 7 | 6 | 1,568.00 | $70.67 | $110,810.00 |
| | | M3 | 8 | 6 | 39,907.00 | $37.58 | $1,499,655.00 |
| | | M3 | 9 | 3 | 42,840.00 | $54.82 | $2,348,460.00 |
| | | M3 | 10 | 9 | 35,024.00 | $45.44 | $1,591,355.00 |
| | | M3 | 11 | 10 | 327,370.00 | $39.96 | $13,081,750.00 |
| | | M3 | 12 | 3 | 1,110.00 | $85.99 | $95,450.00 |
| | **Unit Sub Total** | **M3** | | **78** | **1,070,635.00** | **$43.90** | **$47,004,126.80** |
| | **Item Code 260201 Total No. of Proj.** | | | **153** | | **Total Amount** | **$57,890,766.10** |
| **260210** | AGGREGATE BASE (APPROACH SLAB) | CY | 2 | 1 | 9.00 | $300.00 | $2,700.00 |
| | | CY | 3 | 6 | 209.70 | $234.72 | $49,220.00 |
| | | CY | 4 | 4 | 258.00 | $402.52 | $103,850.00 |
| | | CY | 6 | 1 | 30.00 | $200.00 | $6,000.00 |
| | | CY | 7 | 1 | 159.00 | $550.00 | $87,450.00 |
| | | CY | 10 | 2 | 24.50 | $356.45 | $8,733.00 |
| | | CY | 11 | 2 | 41.00 | $654.88 | $26,850.00 |
| | | CY | 12 | 3 | 66.00 | $247.86 | $16,359.00 |
| | **Unit Sub Total** | **CY** | | **20** | **797.20** | **$377.77** | **$301,162.00** |
| **260210** | AGGREGATE BASE (APPROACH SLAB) | M3 | 3 | 2 | 91.00 | $178.24 | $16,220.00 |
| | | M3 | 4 | 2 | 27.50 | $500.18 | $13,755.00 |
| | | M3 | 7 | 4 | 260.00 | $361.94 | $94,104.00 |
| | | M3 | 8 | 2 | 322.00 | $332.92 | $107,200.00 |
| | | M3 | 11 | 3 | 45.00 | $486.67 | $21,900.00 |
| | | M3 | 12 | 1 | 35.00 | $700.00 | $24,500.00 |
| | **Unit Sub Total** | **M3** | | **14** | **780.50** | **$355.77** | **$277,679.00** |
| | **Item Code 260210 Total No. of Proj.** | | | **34** | | **Total Amount** | **$578,841.00** |
| **260301** | CLASS 3 AGGREGATE BASE | CY | 1 | 1 | 170.00 | $120.00 | $20,400.00 |
| | | CY | 4 | 2 | 1,360.00 | $56.21 | $76,450.00 |
| | | CY | 7 | 5 | 1,040.00 | $67.40 | $70,092.00 |
| | **Unit Sub Total** | **CY** | | **8** | **2,570.00** | **$64.96** | **$166,942.00** |
| **260301** | CLASS 3 AGGREGATE BASE | M3 | 4 | 10 | 64,360.00 | $47.45 | $3,053,950.00 |
| | | M3 | 5 | 1 | 11.00 | $124.00 | $1,364.00 |
| | | M3 | 7 | 15 | 106,615.00 | $50.28 | $5,360,090.60 |
| | | M3 | 9 | 1 | 1,700.00 | $67.00 | $113,900.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **M3** | | **27** | **172,686.00** | **$49.39** | **$8,529,304.60** |
| | **Item Code 260301 Total No. of Proj.** | | | **35** | | **Total Amount** | **$8,696,246.60** |
| **270011** | CEMENT TREATED BASE (PLANT-MIXED, CLASS A) | M3 | 4 | 2 | 26,620.00 | $89.29 | $2,376,932.00 |
| | **Unit Sub Total** | **M3** | | **2** | **26,620.00** | **$89.29** | **$2,376,932.00** |
| | **Item Code 270011 Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,376,932.00** |
| **270065** | ASPHALTIC EMULSION (CURING SEAL) | TONN | 4 | 3 | 245.00 | $570.31 | $139,725.00 |
| | **Unit Sub Total** | **TONN** | | **3** | **245.00** | **$570.31** | **$139,725.00** |
| | **Item Code 270065 Total No. of Proj.** | | | **3** | | **Total Amount** | **$139,725.00** |
| **280000** | LEAN CONCRETE BASE | CY | 3 | 1 | 33,100.00 | $80.00 | $2,648,000.00 |
| | | CY | 5 | 1 | 450.00 | $246.00 | $110,700.00 |
| | | CY | 6 | 1 | 5,760.00 | $110.00 | $633,600.00 |
| | | CY | 7 | 2 | 315.00 | $184.05 | $57,975.00 |
| | | CY | 12 | 2 | 890.00 | $251.35 | $223,700.00 |
| | **Unit Sub Total** | **CY** | | **7** | **40,515.00** | **$90.68** | **$3,673,975.00** |
| **280000** | LEAN CONCRETE BASE | M3 | 3 | 1 | 1,790.00 | $180.00 | $322,200.00 |
| | | M3 | 4 | 3 | 72,350.00 | $173.66 | $12,564,625.00 |
| | | M3 | 6 | 1 | 440.00 | $200.00 | $88,000.00 |
| | | M3 | 7 | 10 | 40,164.00 | $173.24 | $6,957,900.00 |
| | | M3 | 8 | 1 | 7,880.00 | $185.00 | $1,457,800.00 |
| | | M3 | 10 | 1 | 21,800.00 | $101.00 | $2,201,800.00 |
| | | M3 | 12 | 1 | 470.00 | $200.00 | $94,000.00 |
| | **Unit Sub Total** | **M3** | | **18** | **144,894.00** | **$163.47** | **$23,686,325.00** |
| | **Item Code 280000 Total No. of Proj.** | | | **25** | | **Total Amount** | **$27,360,300.00** |
| **290201** | ASPHALT TREATED PERMEABLE BASE | CY | 11 | 1 | 6,540.00 | $110.00 | $719,400.00 |
| | **Unit Sub Total** | **CY** | | **1** | **6,540.00** | **$110.00** | **$719,400.00** |
| **290201** | ASPHALT TREATED PERMEABLE BASE | M3 | 4 | 2 | 540.00 | $216.11 | $116,700.00 |
| | | M3 | 5 | 2 | 12,426.00 | $155.60 | $1,933,440.00 |
| | | M3 | 11 | 3 | 5,248.00 | $143.88 | $755,100.00 |
| | **Unit Sub Total** | **M3** | | **7** | **18,214.00** | **$154.02** | **$2,805,240.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 290201 Total No. of Proj.** | | | **8** | | **Total Amount** | **$3,524,640.00** |
| **365001** | SAND COVER | TON | 2 | 2 | 560.00 | $49.45 | $27,690.00 |
| | | TON | 3 | 5 | 2,200.00 | $21.23 | $46,695.50 |
| | | TON | 6 | 5 | 2,550.00 | $30.19 | $76,996.00 |
| | | TON | 8 | 2 | 1,000.00 | $25.00 | $25,000.00 |
| | | TON | 9 | 3 | 1,620.00 | $130.12 | $210,800.00 |
| | | TON | 11 | 2 | 1,580.00 | $28.82 | $45,532.50 |
| | **Unit Sub Total** | **TON** | | **19** | **9,510.00** | **$45.50** | **$432,714.00** |
| | **Item Code 365001 Total No. of Proj.** | | | **19** | | **Total Amount** | **$432,714.00** |
| **370120** | ASPHALT-RUBBER BINDER | TON | 1 | 2 | 1,100.00 | $778.00 | $855,800.00 |
| | | TON | 9 | 2 | 1,690.00 | $813.93 | $1,375,540.00 |
| | | TON | 11 | 2 | 1,940.00 | $629.25 | $1,220,750.00 |
| | **Unit Sub Total** | **TON** | | **6** | **4,730.00** | **$729.83** | **$3,452,090.00** |
| | **Item Code 370120 Total No. of Proj.** | | | **6** | | **Total Amount** | **$3,452,090.00** |
| **370125** | ASPHALT BINDER (POLYMER MODIFIED) | TON | 6 | 1 | 270.00 | $1,100.00 | $297,000.00 |
| | **Unit Sub Total** | **TON** | | **1** | **270.00** | **$1,100.00** | **$297,000.00** |
| | **Item Code 370125 Total No. of Proj.** | | | **1** | | **Total Amount** | **$297,000.00** |
| **374002** | ASPHALTIC EMULSION (FOG SEAL COAT) | TON | 2 | 4 | 195.00 | $508.46 | $99,150.00 |
| | | TON | 3 | 7 | 355.00 | $648.33 | $230,157.50 |
| | | TON | 4 | 3 | 145.00 | $482.16 | $69,913.00 |
| | | TON | 5 | 8 | 55.50 | $714.00 | $39,627.00 |
| | | TON | 6 | 6 | 312.30 | $523.81 | $163,585.00 |
| | | TON | 7 | 1 | 18.00 | $1,013.60 | $18,244.80 |
| | | TON | 8 | 5 | 520.00 | $453.27 | $235,700.00 |
| | | TON | 9 | 3 | 179.00 | $718.97 | $128,695.00 |
| | | TON | 10 | 4 | 181.00 | $145.13 | $26,269.00 |
| | | TON | 11 | 15 | 300.50 | $819.26 | $246,188.71 |
| | **Unit Sub Total** | **TON** | | **56** | **2,261.30** | **$556.11** | **$1,257,530.01** |
| **374002** | ASPHALTIC EMULSION (FOG SEAL COAT) | TONN | 2 | 1 | 12.00 | $1,184.10 | $14,209.20 |
| | | TONN | 3 | 1 | 0.10 | $2,000.00 | $200.00 |
| | | TONN | 4 | 1 | 30.00 | $100.00 | $3,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **374002** | ASPHALTIC EMULSION (FOG SEAL COAT) | TONN | 5 | 1 | 0.20 | $4,168.00 | $833.60 |
| | | TONN | 9 | 1 | 5.00 | $400.00 | $2,000.00 |
| | | TONN | 11 | 9 | 113.00 | $892.79 | $100,885.00 |
| | **Unit Sub Total** | **TONN** | | **14** | **160.30** | **$755.63** | **$121,127.80** |
| | **Item Code 374002 Total No. of Proj.** | | | **70** | | **Total Amount** | **$1,378,657.81** |
| **374206** | SEAL RANDOM CRACKS | LNKM | 3 | 1 | 10.00 | $4,000.00 | $40,000.00 |
| | | LNKM | 4 | 2 | 6.00 | $11,308.33 | $67,850.00 |
| | | LNKM | 5 | 1 | 12.00 | $2,100.00 | $25,200.00 |
| | | LNKM | 6 | 2 | 34.00 | $2,197.06 | $74,700.00 |
| | | LNKM | 7 | 1 | 1.30 | $1,026.76 | $1,334.79 |
| | | LNKM | 9 | 4 | 80.50 | $1,479.50 | $119,100.00 |
| | **Unit Sub Total** | **LNKM** | | **11** | **143.80** | **$2,282.23** | **$328,184.79** |
| **374206** | SEAL RANDOM CRACKS | LNMI | 1 | 5 | 39.80 | $3,849.87 | $153,225.00 |
| | | LNMI | 3 | 7 | 102.10 | $3,995.71 | $407,962.00 |
| | | LNMI | 4 | 15 | 138.20 | $3,595.52 | $496,900.71 |
| | | LNMI | 6 | 1 | 25.00 | $2,500.00 | $62,500.00 |
| | | LNMI | 7 | 2 | 6.40 | $2,392.58 | $15,312.50 |
| | | LNMI | 10 | 2 | 16.00 | $3,287.50 | $52,600.00 |
| | **Unit Sub Total** | **LNMI** | | **32** | **327.50** | **$3,629.01** | **$1,188,500.21** |
| | **Item Code 374206 Total No. of Proj.** | | | **43** | | **Total Amount** | **$1,516,685.00** |
| **374492** | ASPHALTIC EMULSION (POLYMER MODIFIED) | TON | 3 | 6 | 2,330.00 | $714.85 | $1,665,610.00 |
| | | TON | 6 | 4 | 2,040.00 | $736.25 | $1,501,940.00 |
| | | TON | 8 | 2 | 730.00 | $455.34 | $332,400.00 |
| | | TON | 9 | 1 | 260.00 | $657.00 | $170,820.00 |
| | **Unit Sub Total** | **TON** | | **13** | **5,360.00** | **$684.85** | **$3,670,770.00** |
| **374492** | ASPHALTIC EMULSION (POLYMER MODIFIED) | TONN | 9 | 1 | 25.00 | $800.00 | $20,000.00 |
| | **Unit Sub Total** | **TONN** | | **1** | **25.00** | **$800.00** | **$20,000.00** |
| | **Item Code 374492 Total No. of Proj.** | | | **14** | | **Total Amount** | **$3,690,770.00** |
| **375021** | SCREENINGS (MEDIUM FINE) | TON | 8 | 2 | 6,200.00 | $32.70 | $202,750.00 |
| | **Unit Sub Total** | **TON** | | **2** | **6,200.00** | **$32.70** | **$202,750.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | **Item Code 375021** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$202,750.00** |
| **375022** | SCREENINGS (MEDIUM) | | TON | 3 | 4 | 12,600.00 | $23.10 | $291,075.00 |
| | | | TON | 6 | 3 | 18,370.00 | $34.11 | $626,529.00 |
| | | | TON | 9 | 1 | 2,380.00 | $23.00 | $54,740.00 |
| | | **Unit Sub Total** | **TON** | | **8** | **33,350.00** | **$29.16** | **$972,344.00** |
| **375022** | SCREENINGS (MEDIUM) | | TONN | 9 | 1 | 230.00 | $90.00 | $20,700.00 |
| | | **Unit Sub Total** | **TONN** | | **1** | **230.00** | **$90.00** | **$20,700.00** |
| | **Item Code 375022** | **Total No. of Proj.** | | | **9** | | **Total Amount** | **$993,044.00** |
| **375023** | SCREENINGS (COARSE) | | TON | 3 | 1 | 3,880.00 | $30.00 | $116,400.00 |
| | | **Unit Sub Total** | **TON** | | **1** | **3,880.00** | **$30.00** | **$116,400.00** |
| | **Item Code 375023** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$116,400.00** |
| **375030** | SCREENINGS (HOT-APPLIED) | | TON | 1 | 2 | 7,270.00 | $70.08 | $509,470.00 |
| | | | TON | 6 | 1 | 3,130.00 | $70.00 | $219,100.00 |
| | | | TON | 9 | 2 | 11,450.00 | $69.52 | $796,050.00 |
| | | | TON | 11 | 2 | 16,230.00 | $53.40 | $866,670.00 |
| | | **Unit Sub Total** | **TON** | | **7** | **38,080.00** | **$62.80** | **$2,391,290.00** |
| | **Item Code 375030** | **Total No. of Proj.** | | | **7** | | **Total Amount** | **$2,391,290.00** |
| **377501** | SLURRY SEAL | | TON | 5 | 1 | 350.00 | $323.00 | $113,050.00 |
| | | | TON | 6 | 2 | 4,990.00 | $149.92 | $748,104.30 |
| | | | TON | 10 | 1 | 1,950.00 | $142.77 | $278,401.50 |
| | | | TON | 11 | 1 | 60.00 | $520.00 | $31,200.00 |
| | | | TON | 12 | 2 | 35.00 | $590.71 | $20,675.00 |
| | | **Unit Sub Total** | **TON** | | **7** | **7,385.00** | **$161.33** | **$1,191,430.80** |
| **377501** | SLURRY SEAL | | TONN | 3 | 2 | 231.00 | $244.59 | $56,500.00 |
| | | | TONN | 11 | 1 | 36.00 | $1,500.00 | $54,000.00 |
| | | **Unit Sub Total** | **TONN** | | **3** | **267.00** | **$413.86** | **$110,500.00** |
| | **Item Code 377501** | **Total No. of Proj.** | | | **10** | | **Total Amount** | **$1,301,930.80** |
| **390095** | REPLACE ASPHALT CONCRETE SURFACING | | CY | 1 | 7 | 14,133.00 | $246.31 | $3,481,105.00 |
| | | | CY | 2 | 11 | 6,360.00 | $288.71 | $1,836,185.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **390095** | REPLACE ASPHALT CONCRETE SURFACING | CY | 3 | 21 | 13,463.60 | $221.32 | $2,979,813.40 |
| | | CY | 4 | 17 | 13,621.00 | $249.62 | $3,400,127.50 |
| | | CY | 6 | 1 | 2,980.00 | $194.00 | $578,120.00 |
| | | CY | 7 | 5 | 499.00 | $257.94 | $128,712.40 |
| | | CY | 8 | 10 | 4,481.00 | $277.77 | $1,244,684.20 |
| | | CY | 10 | 3 | 2,080.00 | $257.79 | $536,200.00 |
| | | CY | 11 | 2 | 283.50 | $415.18 | $117,702.20 |
| | **Unit Sub Total** | **CY** | | **77** | **57,901.10** | **$247.02** | **$14,302,649.70** |
| **390095** | REPLACE ASPHALT CONCRETE SURFACING | M3 | 1 | 2 | 730.00 | $346.64 | $253,050.00 |
| | | M3 | 3 | 2 | 27.00 | $596.30 | $16,100.00 |
| | | M3 | 4 | 6 | 2,993.00 | $276.95 | $828,917.00 |
| | | M3 | 7 | 1 | 27.00 | $100.00 | $2,700.00 |
| | | M3 | 8 | 2 | 105.00 | $379.93 | $39,893.00 |
| | | M3 | 10 | 2 | 1,567.00 | $218.79 | $342,845.00 |
| | **Unit Sub Total** | **M3** | | **15** | **5,449.00** | **$272.25** | **$1,483,505.00** |
| | **Item Code 390095** **Total No. of Proj.** | | | **92** | | **Total Amount** | **$15,786,154.70** |
| **390101** | ASPHALT CONCRETE | TON | 5 | 2 | 497.00 | $186.78 | $92,829.80 |
| | | TON | 8 | 1 | 3.90 | $1,011.00 | $3,942.90 |
| | | TON | 11 | 4 | 320.80 | $109.10 | $35,000.00 |
| | **Unit Sub Total** | **TON** | | **7** | **821.70** | **$160.37** | **$131,772.70** |
| **390101** | ASPHALT CONCRETE | TONN | 4 | 1 | 85.00 | $155.88 | $13,249.80 |
| | | TONN | 5 | 1 | 23.00 | $400.00 | $9,200.00 |
| | | TONN | 6 | 1 | 14.00 | $525.00 | $7,350.00 |
| | **Unit Sub Total** | **TONN** | | **3** | **122.00** | **$244.26** | **$29,799.80** |
| | **Item Code 390101** **Total No. of Proj.** | | | **10** | | **Total Amount** | **$161,572.50** |
| **390102** | ASPHALT CONCRETE (TYPE A) | TON | 1 | 2 | 770.00 | $133.09 | $102,480.00 |
| | | TON | 2 | 1 | 4,530.00 | $105.00 | $475,650.00 |
| | | TON | 3 | 6 | 15,951.00 | $61.07 | $974,171.00 |
| | | TON | 4 | 6 | 148,920.00 | $70.42 | $10,486,640.00 |
| | | TON | 5 | 2 | 72.00 | $218.75 | $15,750.00 |
| | | TON | 6 | 1 | 24.00 | $200.00 | $4,800.00 |
| | | TON | 8 | 2 | 5,600.00 | $88.05 | $493,060.00 |
| | | TON | 10 | 1 | 2,620.00 | $71.00 | $186,020.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **390102** | ASPHALT CONCRETE (TYPE A) | | TON | 11 | 3 | 7,220.00 | $87.29 | $630,250.00 |
| | | | TON | 12 | 4 | 390.00 | $132.18 | $51,550.00 |
| | | **Unit Sub Total** | **TON** | | **28** | **186,097.00** | **$72.11** | **$13,420,371.00** |
| **390102** | ASPHALT CONCRETE (TYPE A) | | TONN | 1 | 2 | 16,050.00 | $140.14 | $2,249,250.00 |
| | | | TONN | 2 | 5 | 43,580.00 | $109.75 | $4,782,861.00 |
| | | | TONN | 3 | 4 | 154,710.00 | $80.95 | $12,524,400.00 |
| | | | TONN | 4 | 4 | 125,560.00 | $91.44 | $11,481,600.00 |
| | | | TONN | 5 | 7 | 79,470.00 | $112.33 | $8,926,750.00 |
| | | | TONN | 6 | 3 | 26,620.00 | $98.49 | $2,621,700.00 |
| | | | TONN | 7 | 2 | 58,000.00 | $89.92 | $5,215,200.00 |
| | | | TONN | 8 | 5 | 44,093.00 | $78.65 | $3,467,845.50 |
| | | | TONN | 10 | 1 | 32,600.00 | $74.75 | $2,436,850.00 |
| | | | TONN | 11 | 7 | 142,970.00 | $80.89 | $11,564,720.00 |
| | | | TONN | 12 | 2 | 1,257.00 | $111.61 | $140,300.00 |
| | | **Unit Sub Total** | **TONN** | | **42** | **724,910.00** | **$90.23** | **$65,411,476.50** |
| | **Item Code 390102** | **Total No. of Proj.** | | | **70** | | **Total Amount** | **$78,831,847.50** |
| **390103** | ASPHALT CONCRETE (TYPE B) | | TON | 6 | 1 | 3.00 | $2,700.00 | $8,100.00 |
| | | | TON | 7 | 1 | 510.00 | $128.00 | $65,280.00 |
| | | **Unit Sub Total** | **TON** | | **2** | **513.00** | **$143.04** | **$73,380.00** |
| **390103** | ASPHALT CONCRETE (TYPE B) | | TONN | 7 | 12 | 48,231.00 | $88.71 | $4,278,466.00 |
| | | | TONN | 10 | 3 | 33,211.00 | $74.15 | $2,462,480.00 |
| | | **Unit Sub Total** | **TONN** | | **15** | **81,442.00** | **$82.77** | **$6,740,946.00** |
| | **Item Code 390103** | **Total No. of Proj.** | | | **17** | | **Total Amount** | **$6,814,326.00** |
| **390104** | ASPHALT CONCRETE | | TON | 5 | 1 | 88,400.00 | $64.00 | $5,657,600.00 |
| | | | TON | 12 | 1 | 10,900.00 | $95.00 | $1,035,500.00 |
| | | **Unit Sub Total** | **TON** | | **2** | **99,300.00** | **$67.40** | **$6,693,100.00** |
| **390104** | ASPHALT CONCRETE | | TONN | 3 | 2 | 213,800.00 | $95.24 | $20,362,000.00 |
| | | | TONN | 4 | 3 | 312,200.00 | $112.51 | $35,125,600.00 |
| | | | TONN | 5 | 2 | 226,500.00 | $90.11 | $20,409,480.00 |
| | | | TONN | 6 | 3 | 93,380.00 | $79.65 | $7,437,823.00 |
| | | | TONN | 9 | 1 | 111,000.00 | $105.00 | $11,655,000.00 |
| | | | TONN | 10 | 1 | 17,300.00 | $80.00 | $1,384,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **TONN** | | **12** | **974,180.00** | **$98.93** | **$96,373,903.00** |
| | **Item Code 390104 Total No. of Proj.** | | | **14** | | **Total Amount** | **$103,067,003.00** |
| **390106** | ASPHALT CONCRETE (OPEN GRADED) | TON | 3 | 1 | 3,570.00 | $90.60 | $323,442.00 |
| | | TON | 4 | 2 | 66,100.00 | $78.13 | $5,164,200.00 |
| | **Unit Sub Total** | **TON** | | **3** | **69,670.00** | **$78.77** | **$5,487,642.00** |
| **390106** | ASPHALT CONCRETE (OPEN GRADED) | TONN | 1 | 5 | 14,650.00 | $132.22 | $1,936,990.00 |
| | | TONN | 3 | 3 | 12,150.00 | $83.27 | $1,011,750.00 |
| | | TONN | 4 | 3 | 63,500.00 | $114.10 | $7,245,500.00 |
| | | TONN | 5 | 3 | 3,380.00 | $133.14 | $450,020.00 |
| | | TONN | 8 | 1 | 780.00 | $130.00 | $101,400.00 |
| | **Unit Sub Total** | **TONN** | | **15** | **94,460.00** | **$113.76** | **$10,745,660.00** |
| | **Item Code 390106 Total No. of Proj.** | | | **18** | | **Total Amount** | **$16,233,302.00** |
| **390107** | ASPHALT CONCRETE (LEVELING) | TONN | 4 | 2 | 24,500.00 | $116.53 | $2,855,100.00 |
| | **Unit Sub Total** | **TONN** | | **2** | **24,500.00** | **$116.53** | **$2,855,100.00** |
| | **Item Code 390107 Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,855,100.00** |
| **390108** | ASPHALT CONCRETE BASE (TYPE A) | TON | 11 | 1 | 12,700.00 | $72.00 | $914,400.00 |
| | | TON | 12 | 2 | 10,390.00 | $94.50 | $981,870.00 |
| | **Unit Sub Total** | **TON** | | **3** | **23,090.00** | **$82.13** | **$1,896,270.00** |
| **390108** | ASPHALT CONCRETE BASE (TYPE A) | TONN | 11 | 6 | 175,130.00 | $78.72 | $13,785,750.00 |
| | **Unit Sub Total** | **TONN** | | **6** | **175,130.00** | **$78.72** | **$13,785,750.00** |
| | **Item Code 390108 Total No. of Proj.** | | | **9** | | **Total Amount** | **$15,682,020.00** |
| **390126** | RUBBERIZED ASPHALT CONCRETE (TYPE G) | TON | 2 | 1 | 19,600.00 | $108.00 | $2,116,800.00 |
| | | TON | 4 | 1 | 87,900.00 | $94.00 | $8,262,600.00 |
| | | TON | 7 | 2 | 4,910.00 | $109.55 | $537,915.00 |
| | | TON | 10 | 2 | 20,800.00 | $91.25 | $1,898,000.00 |
| | | TON | 12 | 5 | 38,690.00 | $79.83 | $3,088,565.00 |
| | **Unit Sub Total** | **TON** | | **11** | **171,900.00** | **$92.52** | **$15,903,880.00** |
| **390126** | RUBBERIZED ASPHALT CONCRETE (TYPE G) | TONN | 2 | 1 | 8,270.00 | $135.00 | $1,116,450.00 |
| | | TONN | 3 | 1 | 52,700.00 | $115.00 | $6,060,500.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **390126** | RUBBERIZED ASPHALT CONCRETE (TYPE G) | TONN | 4 | 4 | 135,500.00 | $118.87 | $16,106,500.00 |
| | | TONN | 6 | 1 | 10,080.00 | $102.00 | $1,028,160.00 |
| | | TONN | 7 | 2 | 6,580.00 | $97.23 | $639,745.50 |
| | | TONN | 9 | 1 | 44,500.00 | $126.00 | $5,607,000.00 |
| | | TONN | 10 | 1 | 6,000.00 | $118.00 | $708,000.00 |
| | | TONN | 12 | 1 | 750.00 | $115.00 | $86,250.00 |
| | **Unit Sub Total** | **TONN** | | **12** | **264,380.00** | **$118.59** | **$31,352,605.50** |
| | **Item Code 390126 Total No. of Proj.** | | | **23** | | **Total Amount** | **$47,256,485.50** |
| **390127** | RUBBERIZED ASPHALT CONCRETE (TYPE O) | TON | 6 | 1 | 6,430.00 | $154.00 | $990,220.00 |
| | | TON | 12 | 2 | 48,100.00 | $77.94 | $3,748,700.00 |
| | **Unit Sub Total** | **TON** | | **3** | **54,530.00** | **$86.90** | **$4,738,920.00** |
| **390127** | RUBBERIZED ASPHALT CONCRETE (TYPE O) | TONN | 2 | 2 | 5,550.00 | $126.64 | $702,870.00 |
| | | TONN | 3 | 1 | 4,950.00 | $90.00 | $445,500.00 |
| | | TONN | 4 | 1 | 16,100.00 | $100.00 | $1,610,000.00 |
| | **Unit Sub Total** | **TONN** | | **4** | **26,600.00** | **$103.70** | **$2,758,370.00** |
| | **Item Code 390127 Total No. of Proj.** | | | **7** | | **Total Amount** | **$7,497,290.00** |
| **390130** | HOT MIX ASPHALT | TON | 3 | 2 | 452.30 | $112.72 | $50,985.00 |
| | **Unit Sub Total** | **TON** | | **2** | **452.30** | **$112.72** | **$50,985.00** |
| **390130** | HOT MIX ASPHALT | TONN | 4 | 1 | 220.00 | $171.00 | $37,620.00 |
| | **Unit Sub Total** | **TONN** | | **1** | **220.00** | **$171.00** | **$37,620.00** |
| | **Item Code 390130 Total No. of Proj.** | | | **3** | | **Total Amount** | **$88,605.00** |
| **390131** | HOT MIX ASPHALT | TON | 2 | 3 | 75,000.00 | $96.41 | $7,230,500.00 |
| | | TON | 3 | 2 | 300,800.00 | $84.36 | $25,376,000.00 |
| | | TON | 5 | 1 | 37.00 | $150.00 | $5,550.00 |
| | | TON | 6 | 2 | 69,800.00 | $90.09 | $6,288,150.00 |
| | **Unit Sub Total** | **TON** | | **8** | **445,637.00** | **$87.29** | **$38,900,200.00** |
| **390131** | HOT MIX ASPHALT | TONN | 3 | 1 | 43,400.00 | $70.00 | $3,038,000.00 |
| | | TONN | 4 | 2 | 64,100.00 | $99.91 | $6,404,200.00 |
| | | TONN | 6 | 1 | 69,300.00 | $86.50 | $5,994,450.00 |
| | | TONN | 7 | 1 | 105,000.00 | $106.00 | $11,130,000.00 |
| | | TONN | 8 | 2 | 44,600.00 | $90.10 | $4,018,525.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **390131** | HOT MIX ASPHALT | | TONN | 9 | 2 | 60,300.00 | $113.34 | $6,834,600.00 |
| | | | TONN | 10 | 1 | 10,300.00 | $90.00 | $927,000.00 |
| | | | TONN | 11 | 3 | 118,600.00 | $99.52 | $11,802,500.00 |
| | | **Unit Sub Total** | **TONN** | | **13** | **515,600.00** | **$97.26** | **$50,149,275.00** |
| | **Item Code 390131** | **Total No. of Proj.** | | | **21** | | **Total Amount** | **$89,049,475.00** |
| **390132** | HOT MIX ASPHALT (TYPE A) | | TON | 1 | 16 | 17,139.00 | $121.10 | $2,075,500.00 |
| | | | TON | 2 | 14 | 45,790.00 | $112.76 | $5,163,273.00 |
| | | | TON | 3 | 21 | 125,305.00 | $107.03 | $13,411,727.00 |
| | | | TON | 4 | 13 | 25,743.00 | $103.64 | $2,667,877.00 |
| | | | TON | 5 | 8 | 27,030.00 | $99.37 | $2,685,900.00 |
| | | | TON | 6 | 12 | 26,167.00 | $100.52 | $2,630,290.00 |
| | | | TON | 8 | 9 | 15,428.00 | $98.87 | $1,525,419.60 |
| | | | TON | 9 | 2 | 6,963.00 | $106.57 | $742,020.00 |
| | | | TON | 10 | 6 | 6,580.00 | $100.64 | $662,191.70 |
| | | | TON | 11 | 3 | 11,447.00 | $95.41 | $1,092,171.40 |
| | | | TON | 12 | 7 | 6,576.00 | $95.91 | $630,684.20 |
| | | **Unit Sub Total** | **TON** | | **111** | **314,168.00** | **$105.95** | **$33,287,053.90** |
| **390132** | HOT MIX ASPHALT (TYPE A) | | TONN | 1 | 2 | 1,200.00 | $134.15 | $160,980.00 |
| | | | TONN | 2 | 1 | 230.00 | $325.00 | $74,750.00 |
| | | | TONN | 3 | 1 | 230.00 | $140.00 | $32,200.00 |
| | | | TONN | 4 | 6 | 10,310.00 | $118.49 | $1,221,650.00 |
| | | | TONN | 5 | 6 | 8,553.00 | $124.34 | $1,063,472.50 |
| | | | TONN | 6 | 2 | 1,206.00 | $147.43 | $177,800.00 |
| | | | TONN | 9 | 2 | 8,600.00 | $123.17 | $1,059,270.00 |
| | | | TONN | 10 | 1 | 330.00 | $125.00 | $41,250.00 |
| | | | TONN | 12 | 3 | 1,980.00 | $139.92 | $277,040.00 |
| | | **Unit Sub Total** | **TONN** | | **24** | **32,639.00** | **$125.87** | **$4,108,412.50** |
| | **Item Code 390132** | **Total No. of Proj.** | | | **135** | | **Total Amount** | **$37,395,466.40** |
| **390133** | HOT MIX ASPHALT (TYPE B) | | TON | 6 | 1 | 2.00 | $300.00 | $600.00 |
| | | | TON | 7 | 9 | 12,040.40 | $106.65 | $1,284,139.80 |
| | | | TON | 10 | 4 | 2,050.00 | $95.39 | $195,545.00 |
| | | | TON | 12 | 1 | 270.00 | $177.00 | $47,790.00 |
| | | **Unit Sub Total** | **TON** | | **15** | **14,362.40** | **$106.39** | **$1,528,074.80** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **390133** | HOT MIX ASPHALT (TYPE B) | TONN | 2 | 1 | 110.00 | $200.00 | $22,000.00 |
| | | TONN | 7 | 8 | 5,555.90 | $118.54 | $658,586.95 |
| | | TONN | 10 | 4 | 3,680.00 | $102.26 | $376,324.00 |
| | **Unit Sub Total** | **TONN** | | **13** | **9,345.90** | **$113.09** | **$1,056,910.95** |
| | **Item Code 390133 Total No. of Proj.** | | | **28** | | **Total Amount** | **$2,584,985.75** |
| **390134** | HOT MIX ASPHALT (OPEN GRADED) | TON | 1 | 8 | 25,960.00 | $117.20 | $3,042,580.00 |
| | | TON | 2 | 2 | 55,540.00 | $82.38 | $4,575,360.00 |
| | | TON | 3 | 4 | 594.00 | $124.32 | $73,844.00 |
| | | TON | 4 | 2 | 5,870.00 | $111.29 | $653,290.00 |
| | | TON | 5 | 2 | 18,140.00 | $116.56 | $2,114,400.00 |
| | | TON | 6 | 3 | 2,560.00 | $128.42 | $328,745.00 |
| | | TON | 9 | 1 | 9,080.00 | $110.00 | $998,800.00 |
| | | TON | 12 | 3 | 730.00 | $148.61 | $108,482.00 |
| | **Unit Sub Total** | **TON** | | **25** | **118,474.00** | **$100.41** | **$11,895,501.00** |
| **390134** | HOT MIX ASPHALT (OPEN GRADED) | TONN | 1 | 1 | 380.00 | $142.00 | $53,960.00 |
| | | TONN | 3 | 1 | 60.00 | $140.00 | $8,400.00 |
| | | TONN | 4 | 1 | 9,670.00 | $120.15 | $1,161,850.50 |
| | | TONN | 8 | 1 | 2,310.00 | $75.75 | $174,982.50 |
| | **Unit Sub Total** | **TONN** | | **4** | **12,420.00** | **$112.66** | **$1,399,193.00** |
| | **Item Code 390134 Total No. of Proj.** | | | **29** | | **Total Amount** | **$13,294,694.00** |
| **390135** | HOT MIX ASPHALT (LEVELING) | TONN | 4 | 1 | 3,600.00 | $106.00 | $381,600.00 |
| | | TONN | 8 | 1 | 1,790.00 | $113.00 | $202,270.00 |
| | **Unit Sub Total** | **TONN** | | **2** | **5,390.00** | **$108.32** | **$583,870.00** |
| | **Item Code 390135 Total No. of Proj.** | | | **2** | | **Total Amount** | **$583,870.00** |
| **390136** | MINOR HOT MIX ASPHALT | TON | 2 | 3 | 176.00 | $176.70 | $31,099.75 |
| | | TON | 3 | 8 | 396.40 | $136.97 | $54,296.00 |
| | | TON | 4 | 2 | 170.00 | $217.35 | $36,950.00 |
| | | TON | 5 | 2 | 148.00 | $167.91 | $24,850.00 |
| | | TON | 6 | 5 | 738.00 | $104.67 | $77,250.00 |
| | | TON | 7 | 3 | 101.00 | $153.86 | $15,540.00 |
| | | TON | 8 | 3 | 63.00 | $272.10 | $17,142.00 |
| | | TON | 9 | 1 | 90.00 | $83.00 | $7,470.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **390136** | MINOR HOT MIX ASPHALT | TON | 10 | 1 | 93.00 | $120.00 | $11,160.00 |
| | | TON | 11 | 6 | 679.90 | $104.70 | $71,184.40 |
| | **Unit Sub Total** | **TON** | | **34** | **2,655.30** | **$130.66** | **$346,942.15** |
| **390136** | MINOR HOT MIX ASPHALT | TONN | 2 | 1 | 97.00 | $301.00 | $29,197.00 |
| | | TONN | 4 | 1 | 70.00 | $220.00 | $15,400.00 |
| | | TONN | 5 | 4 | 213.00 | $204.44 | $43,545.00 |
| | | TONN | 7 | 1 | 5.00 | $250.00 | $1,250.00 |
| | | TONN | 8 | 2 | 19.90 | $701.51 | $13,960.00 |
| | | TONN | 10 | 1 | 21.00 | $175.00 | $3,675.00 |
| | **Unit Sub Total** | **TONN** | | **10** | **425.90** | **$251.30** | **$107,027.00** |
| | **Item Code 390136 Total No. of Proj.** | | | **44** | | **Total Amount** | **$453,969.15** |
| **390137** | RUBBERIZED HOT MIX ASPHALT (GAP GRADED) | TON | 1 | 2 | 72,200.00 | $109.26 | $7,888,600.00 |
| | | TON | 4 | 3 | 23,450.00 | $127.80 | $2,997,026.40 |
| | | TON | 5 | 3 | 13,570.00 | $121.84 | $1,653,430.00 |
| | | TON | 6 | 3 | 7,230.00 | $124.01 | $896,575.00 |
| | | TON | 7 | 10 | 49,688.00 | $97.44 | $4,841,452.30 |
| | | TON | 8 | 6 | 40,480.00 | $100.20 | $4,056,093.50 |
| | | TON | 10 | 5 | 32,330.00 | $102.67 | $3,319,325.00 |
| | | TON | 11 | 3 | 23,070.00 | $117.03 | $2,699,953.90 |
| | | TON | 12 | 1 | 9,920.00 | $118.00 | $1,170,560.00 |
| | **Unit Sub Total** | **TON** | | **36** | **271,938.00** | **$108.57** | **$29,523,016.10** |
| **390137** | RUBBERIZED HOT MIX ASPHALT (GAP GRADED) | TONN | 7 | 4 | 11,440.00 | $139.94 | $1,600,903.80 |
| | | TONN | 10 | 2 | 4,600.00 | $139.50 | $641,680.00 |
| | **Unit Sub Total** | **TONN** | | **6** | **16,040.00** | **$139.81** | **$2,242,583.80** |
| | **Item Code 390137 Total No. of Proj.** | | | **42** | | **Total Amount** | **$31,765,599.90** |
| **390138** | RUBBERIZED HOT MIX ASPHALT (OPEN GRADED) | TON | 1 | 3 | 58,500.00 | $103.55 | $6,057,400.00 |
| | | TON | 3 | 2 | 27,320.00 | $90.53 | $2,473,280.00 |
| | | TON | 6 | 5 | 40,090.00 | $104.10 | $4,173,275.00 |
| | | TON | 8 | 4 | 78,830.00 | $75.46 | $5,948,300.00 |
| | | TON | 11 | 2 | 16,160.00 | $141.79 | $2,291,302.00 |
| | **Unit Sub Total** | **TON** | | **16** | **220,900.00** | **$94.81** | **$20,943,557.00** |
| **390138** | RUBBERIZED HOT MIX ASPHALT (OPEN GRADED) | TONN | 3 | 1 | 17,200.00 | $100.00 | $1,720,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **390138** | RUBBERIZED HOT MIX ASPHALT (OPEN GRADED) | TONN | 8 | 1 | 16,500.00 | $121.00 | $1,996,500.00 |
| | **Unit Sub Total** | **TONN** | | **2** | **33,700.00** | **$110.28** | **$3,716,500.00** |
| | **Item Code 390138 Total No. of Proj.** | | | **18** | | **Total Amount** | **$24,660,057.00** |
| **390139** | RUBBERIZED HOT MIX ASPHALT (OPEN GRADED HIGH BINDER) | TON | 9 | 5 | 77,400.00 | $147.83 | $11,442,200.00 |
| | **Unit Sub Total** | **TON** | | **5** | **77,400.00** | **$147.83** | **$11,442,200.00** |
| | **Item Code 390139 Total No. of Proj.** | | | **5** | | **Total Amount** | **$11,442,200.00** |
| **390140** | RUBBERIZED HOT MIX ASPHALT (GAP GRADED) | TON | 1 | 1 | 23,100.00 | $118.00 | $2,725,800.00 |
| | | TON | 6 | 4 | 81,700.00 | $113.44 | $9,268,100.00 |
| | | TON | 8 | 1 | 17,700.00 | $102.00 | $1,805,400.00 |
| | | TON | 10 | 3 | 48,100.00 | $100.62 | $4,839,900.00 |
| | | TON | 12 | 1 | 11,500.00 | $98.56 | $1,133,440.00 |
| | **Unit Sub Total** | **TON** | | **10** | **182,100.00** | **$108.58** | **$19,772,640.00** |
| **390140** | RUBBERIZED HOT MIX ASPHALT (GAP GRADED) | TONN | 4 | 1 | 14,500.00 | $141.65 | $2,053,925.00 |
| | | TONN | 6 | 1 | 46,100.00 | $118.00 | $5,439,800.00 |
| | | TONN | 7 | 1 | 23,600.00 | $119.00 | $2,808,400.00 |
| | | TONN | 8 | 1 | 12,400.00 | $120.00 | $1,488,000.00 |
| | | TONN | 9 | 1 | 12,900.00 | $155.00 | $1,999,500.00 |
| | | TONN | 10 | 1 | 18,000.00 | $122.25 | $2,200,500.00 |
| | **Unit Sub Total** | **TONN** | | **6** | **127,500.00** | **$125.41** | **$15,990,125.00** |
| | **Item Code 390140 Total No. of Proj.** | | | **16** | | **Total Amount** | **$35,762,765.00** |
| **390142** | HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED) | TON | 3 | 1 | 23,000.00 | $120.00 | $2,760,000.00 |
| | **Unit Sub Total** | **TON** | | **1** | **23,000.00** | **$120.00** | **$2,760,000.00** |
| | **Item Code 390142 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,760,000.00** |
| **390144** | ASPHALT CONCRETE (TYPE A, 19-MM MAXIMUM GRADING) | TONN | 1 | 3 | 41,550.00 | $106.00 | $4,404,400.00 |
| | | TONN | 8 | 1 | 410.00 | $100.00 | $41,000.00 |
| | **Unit Sub Total** | **TONN** | | **4** | **41,960.00** | **$105.94** | **$4,445,400.00** |
| | **Item Code 390144 Total No. of Proj.** | | | **4** | | **Total Amount** | **$4,445,400.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **390146** | ASPHALT CONCRETE (TYPE A, 12.5-MM MAXIMUM GRADING) | TONN | 1 | 3 | 4,600.00 | $107.77 | $495,740.00 |
| | **Unit Sub Total** | **TONN** | | **3** | **4,600.00** | **$107.77** | **$495,740.00** |
| | **Item Code 390146 Total No. of Proj.** | | | **3** | | **Total Amount** | **$495,740.00** |
| **390149** | ASPHALTIC EMULSION MEMBRANE (BONDED WEARING COURSE) | TON | 1 | 2 | 810.00 | $940.70 | $761,970.00 |
| | | TON | 3 | 1 | 390.00 | $50.00 | $19,500.00 |
| | | TON | 6 | 1 | 590.00 | $588.00 | $346,920.00 |
| | **Unit Sub Total** | **TON** | | **4** | **1,790.00** | **$630.39** | **$1,128,390.00** |
| | **Item Code 390149 Total No. of Proj.** | | | **4** | | **Total Amount** | **$1,128,390.00** |
| **390157** | RUBBERIZED HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED) | TON | 6 | 1 | 14,100.00 | $139.00 | $1,959,900.00 |
| | **Unit Sub Total** | **TON** | | **1** | **14,100.00** | **$139.00** | **$1,959,900.00** |
| | **Item Code 390157 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,959,900.00** |
| **390158** | HOT MIX ASPHALT (BONDED WEARING COURSE-OPEN GRADED) | TON | 1 | 1 | 7,140.00 | $145.00 | $1,035,300.00 |
| | **Unit Sub Total** | **TON** | | **1** | **7,140.00** | **$145.00** | **$1,035,300.00** |
| | **Item Code 390158 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,035,300.00** |
| **390159** | RUBBERIZED HOT MIX ASPHALT (BONDED WEARING COURSE-OPEN GRADED) | TON | 1 | 1 | 32,000.00 | $160.50 | $5,136,000.00 |
| | | TON | 6 | 1 | 29,400.00 | $139.00 | $4,086,600.00 |
| | **Unit Sub Total** | **TON** | | **2** | **61,400.00** | **$150.21** | **$9,222,600.00** |
| | **Item Code 390159 Total No. of Proj.** | | | **2** | | **Total Amount** | **$9,222,600.00** |
| **391005** | PAVING ASPHALT (BINDER-PAVEMENT REINFORCING FABRIC) | KG | 1 | 1 | 72.00 | $40.00 | $2,880.00 |
| | **Unit Sub Total** | **KG** | | **1** | **72.00** | **$40.00** | **$2,880.00** |
| **391005** | PAVING ASPHALT (BINDER-PAVEMENT REINFORCING FABRIC) | TONN | 1 | 3 | 54.50 | $177.83 | $9,692.00 |
| | | TONN | 4 | 2 | 530.00 | $8.13 | $4,310.00 |
| | | TONN | 5 | 1 | 48.00 | $670.00 | $32,160.00 |
| | **Unit Sub Total** | **TONN** | | **6** | **632.50** | **$72.98** | **$46,162.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 391005 Total No. of Proj.** | | | **7** | | **Total Amount** | **$49,042.00** |
| **391007** | PAVING ASPHALT (BINDER, GEOSYNTHETIC PAVEMENT INTERLAYER) | TON | 1 | 1 | 9.00 | $100.00 | $900.00 |
| | | TON | 2 | 1 | 66.00 | $100.00 | $6,600.00 |
| | | TON | 3 | 4 | 223.70 | $807.02 | $180,530.00 |
| | | TON | 4 | 2 | 13.00 | $750.00 | $9,750.00 |
| | **Unit Sub Total** | **TON** | | **8** | **311.70** | **$634.52** | **$197,780.00** |
| **391007** | PAVING ASPHALT (BINDER, GEOSYNTHETIC PAVEMENT INTERLAYER) | TONN | 4 | 1 | 150.00 | $10.00 | $1,500.00 |
| | | TONN | 11 | 1 | 0.30 | $10,000.00 | $3,000.00 |
| | **Unit Sub Total** | **TONN** | | **2** | **150.30** | **$29.94** | **$4,500.00** |
| | **Item Code 391007 Total No. of Proj.** | | | **10** | | **Total Amount** | **$202,280.00** |
| **391031** | PAVING ASPHALT (BINDER-PAVEMENT REINFORCING FABRIC) | TONN | 3 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | **Unit Sub Total** | **TONN** | | **1** | **1.00** | **$2,000.00** | **$2,000.00** |
| | **Item Code 391031 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,000.00** |
| **393001** | PAVEMENT REINFORCING FABRIC | M2 | 1 | 4 | 45,045.00 | $1.53 | $68,695.00 |
| | | M2 | 3 | 2 | 5,630.00 | $3.21 | $18,090.00 |
| | | M2 | 4 | 3 | 398,400.00 | $1.77 | $705,600.00 |
| | | M2 | 5 | 2 | 282,600.00 | $1.24 | $349,700.00 |
| | **Unit Sub Total** | **M2** | | **11** | **731,675.00** | **$1.56** | **$1,142,085.00** |
| **393001** | PAVEMENT REINFORCING FABRIC | SQYD | 4 | 1 | 869,000.00 | $0.95 | $825,550.00 |
| | **Unit Sub Total** | **SQYD** | | **1** | **869,000.00** | **$0.95** | **$825,550.00** |
| | **Item Code 393001 Total No. of Proj.** | | | **12** | | **Total Amount** | **$1,967,635.00** |
| **393003** | GEOSYNTHETIC PAVEMENT INTERLAYER | M2 | 4 | 1 | 125,000.00 | $2.22 | $277,500.00 |
| | | M2 | 7 | 1 | 36,600.00 | $2.00 | $73,200.00 |
| | | M2 | 11 | 1 | 200.00 | $13.00 | $2,600.00 |
| | | M2 | 12 | 1 | 850.00 | $2.20 | $1,870.00 |
| | **Unit Sub Total** | **M2** | | **4** | **162,650.00** | **$2.18** | **$355,170.00** |
| **393003** | GEOSYNTHETIC PAVEMENT INTERLAYER | SQYD | 1 | 3 | 10,002.00 | $2.22 | $22,230.00 |
| | | SQYD | 2 | 1 | 20,000.00 | $0.20 | $4,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **393003** | GEOSYNTHETIC PAVEMENT INTERLAYER | SQYD | 3 | 5 | 337,920.00 | $1.13 | $381,312.00 |
| | | SQYD | 4 | 2 | 11,050.00 | $0.98 | $10,880.00 |
| | **Unit Sub Total** | **SQYD** | | **11** | **378,972.00** | **$1.10** | **$418,422.00** |
| | **Item Code 393003 Total No. of Proj.** | | | **15** | | **Total Amount** | **$773,592.00** |
| **394001** | PLACE ASPHALT CONCRETE DIKE | LF | 11 | 6 | 32,333.00 | $1.98 | $64,024.50 |
| | **Unit Sub Total** | **LF** | | **6** | **32,333.00** | **$1.98** | **$64,024.50** |
| **394001** | PLACE ASPHALT CONCRETE DIKE | M | 11 | 7 | 27,260.00 | $6.46 | $175,980.00 |
| | **Unit Sub Total** | **M** | | **7** | **27,260.00** | **$6.46** | **$175,980.00** |
| | **Item Code 394001 Total No. of Proj.** | | | **13** | | **Total Amount** | **$240,004.50** |
| **394002** | PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA) | M2 | 1 | 2 | 1,033.00 | $29.09 | $30,050.00 |
| | | M2 | 2 | 3 | 520.00 | $38.12 | $19,820.00 |
| | | M2 | 3 | 5 | 9,873.00 | $9.16 | $90,440.00 |
| | | M2 | 4 | 6 | 3,156.00 | $33.06 | $104,340.00 |
| | | M2 | 5 | 8 | 5,239.00 | $20.78 | $108,857.00 |
| | | M2 | 6 | 4 | 4,907.00 | $30.01 | $147,250.00 |
| | | M2 | 7 | 4 | 1,209.00 | $18.94 | $22,899.00 |
| | | M2 | 8 | 1 | 16.00 | $150.00 | $2,400.00 |
| | | M2 | 9 | 1 | 200.00 | $70.00 | $14,000.00 |
| | | M2 | 10 | 3 | 1,385.00 | $41.55 | $57,545.00 |
| | | M2 | 11 | 6 | 4,898.50 | $20.53 | $100,550.00 |
| | | M2 | 12 | 2 | 444.00 | $13.78 | $6,120.00 |
| | **Unit Sub Total** | **M2** | | **45** | **32,880.50** | **$21.42** | **$704,271.00** |
| **394002** | PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA) | SQFT | 7 | 1 | 28,400.00 | $5.80 | $164,720.00 |
| | **Unit Sub Total** | **SQFT** | | **1** | **28,400.00** | **$5.80** | **$164,720.00** |
| **394002** | PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA) | SQYD | 1 | 2 | 852.00 | $5.47 | $4,660.00 |
| | | SQYD | 2 | 1 | 120.00 | $30.00 | $3,600.00 |
| | | SQYD | 3 | 1 | 1.00 | $55.00 | $55.00 |
| | | SQYD | 4 | 1 | 220.00 | $80.00 | $17,600.00 |
| | | SQYD | 5 | 3 | 1,165.00 | $35.05 | $40,830.60 |
| | | SQYD | 6 | 1 | 7.00 | $55.00 | $385.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **394002** | PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA) | SQYD | 11 | 5 | 97.00 | $104.85 | $10,170.00 |
| | | SQYD | 12 | 1 | 370.00 | $25.00 | $9,250.00 |
| | **Unit Sub Total** | **SQYD** | | **15** | **2,832.00** | **$30.56** | **$86,550.60** |
| | **Item Code 394002 Total No. of Proj.** | | | **61** | | **Total Amount** | **$955,541.60** |
| **394040** | PLACE ASPHALT CONCRETE DIKE (TYPE A) | LF | 1 | 1 | 110.00 | $22.50 | $2,475.00 |
| | | LF | 2 | 1 | 25.00 | $3.00 | $75.00 |
| | | LF | 3 | 1 | 180.00 | $10.00 | $1,800.00 |
| | | LF | 4 | 2 | 895.00 | $1.25 | $1,120.00 |
| | | LF | 5 | 1 | 12,600.00 | $1.00 | $12,600.00 |
| | | LF | 7 | 1 | 540.00 | $6.50 | $3,510.00 |
| | | LF | 12 | 1 | 240.00 | $9.00 | $2,160.00 |
| | **Unit Sub Total** | **LF** | | **8** | **14,590.00** | **$1.63** | **$23,740.00** |
| **394040** | PLACE ASPHALT CONCRETE DIKE (TYPE A) | M | 1 | 2 | 121.00 | $10.36 | $1,254.00 |
| | | M | 2 | 1 | 200.00 | $29.60 | $5,920.00 |
| | | M | 4 | 1 | 170.00 | $58.87 | $10,007.90 |
| | | M | 5 | 7 | 6,141.00 | $4.09 | $25,138.00 |
| | | M | 6 | 3 | 1,100.00 | $5.86 | $6,450.00 |
| | | M | 7 | 2 | 1,820.00 | $9.78 | $17,800.00 |
| | | M | 8 | 1 | 20.00 | $5.00 | $100.00 |
| | | M | 9 | 1 | 93.00 | $10.00 | $930.00 |
| | | M | 10 | 3 | 347.00 | $19.37 | $6,720.00 |
| | **Unit Sub Total** | **M** | | **21** | **10,012.00** | **$7.42** | **$74,319.90** |
| | **Item Code 394040 Total No. of Proj.** | | | **29** | | **Total Amount** | **$98,059.90** |
| **394044** | PLACE ASPHALT CONCRETE DIKE (TYPE C) | LF | 1 | 1 | 3,000.00 | $1.00 | $3,000.00 |
| | | LF | 3 | 2 | 88.00 | $11.42 | $1,005.00 |
| | | LF | 4 | 2 | 1,000.00 | $4.99 | $4,990.00 |
| | | LF | 5 | 4 | 2,160.00 | $3.40 | $7,353.00 |
| | | LF | 6 | 1 | 250.00 | $2.00 | $500.00 |
| | | LF | 7 | 1 | 5,400.00 | $6.50 | $35,100.00 |
| | | LF | 8 | 1 | 250.00 | $14.00 | $3,500.00 |
| | | LF | 12 | 2 | 360.00 | $10.83 | $3,900.00 |
| | **Unit Sub Total** | **LF** | | **14** | **12,508.00** | **$4.74** | **$59,348.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **394044** | PLACE ASPHALT CONCRETE DIKE (TYPE C) | M | 1 | 2 | 122.00 | $13.50 | $1,647.50 |
| | | M | 2 | 2 | 130.00 | $10.83 | $1,408.00 |
| | | M | 3 | 2 | 305.00 | $7.91 | $2,413.75 |
| | | M | 4 | 6 | 900.00 | $6.60 | $5,941.00 |
| | | M | 5 | 4 | 902.00 | $4.35 | $3,925.60 |
| | | M | 6 | 1 | 60.00 | $17.50 | $1,050.00 |
| | | M | 7 | 5 | 4,624.00 | $18.07 | $83,566.00 |
| | | M | 8 | 1 | 12.00 | $100.00 | $1,200.00 |
| | | M | 10 | 2 | 77.00 | $3.91 | $301.00 |
| | **Unit Sub Total** | **M** | | **25** | **7,132.00** | **$14.23** | **$101,452.85** |
| | **Item Code 394044 Total No. of Proj.** | | | **39** | | **Total Amount** | **$160,800.85** |
| **394046** | PLACE ASPHALT CONCRETE DIKE (TYPE D) | LF | 1 | 1 | 100.00 | $23.50 | $2,350.00 |
| | | LF | 2 | 1 | 570.00 | $3.50 | $1,995.00 |
| | | LF | 4 | 2 | 16,410.00 | $0.74 | $12,210.00 |
| | | LF | 5 | 1 | 700.00 | $1.00 | $700.00 |
| | **Unit Sub Total** | **LF** | | **5** | **17,780.00** | **$0.97** | **$17,255.00** |
| **394046** | PLACE ASPHALT CONCRETE DIKE (TYPE D) | M | 3 | 1 | 150.00 | $20.00 | $3,000.00 |
| | | M | 4 | 1 | 38.00 | $25.00 | $950.00 |
| | | M | 5 | 1 | 98.00 | $253.00 | $24,794.00 |
| | | M | 7 | 2 | 650.00 | $12.57 | $8,170.00 |
| | | M | 8 | 1 | 940.00 | $5.50 | $5,170.00 |
| | **Unit Sub Total** | **M** | | **6** | **1,876.00** | **$22.43** | **$42,084.00** |
| | **Item Code 394046 Total No. of Proj.** | | | **11** | | **Total Amount** | **$59,339.00** |
| **394048** | PLACE ASPHALT CONCRETE DIKE (TYPE E) | LF | 3 | 1 | 530.00 | $3.00 | $1,590.00 |
| | | LF | 4 | 2 | 30,670.00 | $0.78 | $23,980.00 |
| | | LF | 5 | 2 | 20,480.00 | $1.05 | $21,600.00 |
| | | LF | 6 | 1 | 250.00 | $2.00 | $500.00 |
| | | LF | 12 | 1 | 60.00 | $24.00 | $1,440.00 |
| | **Unit Sub Total** | **LF** | | **7** | **51,990.00** | **$0.94** | **$49,110.00** |
| **394048** | PLACE ASPHALT CONCRETE DIKE (TYPE E) | M | 1 | 3 | 3,620.00 | $5.97 | $21,612.50 |
| | | M | 2 | 3 | 1,623.00 | $8.50 | $13,796.00 |
| | | M | 3 | 3 | 1,530.00 | $11.11 | $17,000.00 |
| | | M | 4 | 5 | 24,980.00 | $4.10 | $102,491.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **394048** | PLACE ASPHALT CONCRETE DIKE (TYPE E) | M | 5 | 6 | 21,880.00 | $6.14 | $134,260.00 |
| | | M | 6 | 3 | 3,640.00 | $5.20 | $18,910.00 |
| | | M | 8 | 1 | 300.00 | $5.50 | $1,650.00 |
| | | M | 9 | 1 | 370.00 | $10.00 | $3,700.00 |
| | | M | 10 | 3 | 3,940.00 | $5.55 | $21,880.00 |
| | **Unit Sub Total** | **M** | | **28** | **61,883.00** | **$5.42** | **$335,299.50** |
| | **Item Code 394048 Total No. of Proj.** | | | **35** | | **Total Amount** | **$384,409.50** |
| **394049** | PLACE ASPHALT CONCRETE DIKE (TYPE F) | LF | 1 | 1 | 13,900.00 | $1.00 | $13,900.00 |
| | | LF | 2 | 2 | 820.00 | $4.19 | $3,435.00 |
| | | LF | 3 | 3 | 4,290.00 | $1.27 | $5,440.00 |
| | | LF | 4 | 2 | 23,540.00 | $1.03 | $24,221.00 |
| | | LF | 5 | 5 | 19,030.00 | $1.88 | $35,689.00 |
| | | LF | 6 | 1 | 910.00 | $2.00 | $1,820.00 |
| | | LF | 7 | 1 | 110.00 | $6.50 | $715.00 |
| | | LF | 8 | 1 | 160.00 | $14.00 | $2,240.00 |
| | | LF | 12 | 2 | 140.00 | $15.96 | $2,235.00 |
| | **Unit Sub Total** | **LF** | | **18** | **62,900.00** | **$1.43** | **$89,695.00** |
| **394049** | PLACE ASPHALT CONCRETE DIKE (TYPE F) | M | 1 | 2 | 76.00 | $12.13 | $921.50 |
| | | M | 2 | 2 | 1,050.00 | $10.21 | $10,720.00 |
| | | M | 3 | 3 | 1,760.00 | $8.36 | $14,717.50 |
| | | M | 4 | 6 | 1,900.00 | $4.26 | $8,102.00 |
| | | M | 5 | 5 | 6,463.80 | $5.49 | $35,498.20 |
| | | M | 6 | 1 | 31.00 | $17.50 | $542.50 |
| | | M | 7 | 4 | 10,608.00 | $10.11 | $107,244.00 |
| | | M | 8 | 1 | 15.00 | $120.00 | $1,800.00 |
| | | M | 9 | 1 | 230.00 | $10.00 | $2,300.00 |
| | | M | 10 | 3 | 1,056.00 | $4.30 | $4,540.00 |
| | **Unit Sub Total** | **M** | | **28** | **23,189.80** | **$8.04** | **$186,385.70** |
| | **Item Code 394049 Total No. of Proj.** | | | **46** | | **Total Amount** | **$276,080.70** |
| **394050** | RUMBLE STRIP | STA | 6 | 1 | 210.00 | $17.25 | $3,622.50 |
| | | STA | 7 | 1 | 180.00 | $26.38 | $4,748.40 |
| | **Unit Sub Total** | **STA** | | **2** | **390.00** | **$21.46** | **$8,370.90** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 394050 Total No. of Proj.** | | | **2** | | **Total Amount** | **$8,370.90** |
| **394051** | SHOULDER RUMBLE STRIP (HMA,ROLLED-IN INDENTATIONS) | LF | 10 | 1 | 2,400.00 | $1.00 | $2,400.00 |
| | **Unit Sub Total** | **LF** | | **1** | **2,400.00** | **$1.00** | **$2,400.00** |
| **394051** | SHOULDER RUMBLE STRIP (HMA,ROLLED-IN INDENTATIONS) | STA | 5 | 1 | 180.00 | $35.00 | $6,300.00 |
| | **Unit Sub Total** | **STA** | | **1** | **180.00** | **$35.00** | **$6,300.00** |
| | **Item Code 394051 Total No. of Proj.** | | | **2** | | **Total Amount** | **$8,700.00** |
| **394052** | SHOULDER RUMBLE STRIP (AC, ROLLED-IN INDENTATIONS) | STA | 5 | 1 | 170.00 | $180.00 | $30,600.00 |
| | **Unit Sub Total** | **STA** | | **1** | **170.00** | **$180.00** | **$30,600.00** |
| | **Item Code 394052 Total No. of Proj.** | | | **1** | | **Total Amount** | **$30,600.00** |
| **394053** | SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS) | LF | 3 | 2 | 16,650.00 | $0.56 | $9,252.00 |
| | **Unit Sub Total** | **LF** | | **2** | **16,650.00** | **$0.56** | **$9,252.00** |
| **394053** | SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS) | STA | 1 | 5 | 4,657.00 | $26.18 | $121,908.00 |
| | | STA | 2 | 1 | 2,370.00 | $17.00 | $40,290.00 |
| | | STA | 3 | 2 | 2,480.00 | $38.68 | $95,930.00 |
| | | STA | 5 | 2 | 320.00 | $49.59 | $15,870.00 |
| | | STA | 6 | 4 | 5,470.00 | $20.14 | $110,146.00 |
| | | STA | 9 | 9 | 4,070.00 | $33.01 | $134,367.50 |
| | **Unit Sub Total** | **STA** | | **23** | **19,367.00** | **$26.77** | **$518,511.50** |
| | **Item Code 394053 Total No. of Proj.** | | | **25** | | **Total Amount** | **$527,763.50** |
| **394054** | SHOULDER RUMBLE STRIP (AC, GROUND-IN INDENTATIONS) | LF | 4 | 1 | 5,560.00 | $1.30 | $7,228.00 |
| | | LF | 5 | 1 | 197,000.00 | $0.25 | $49,250.00 |
| | **Unit Sub Total** | **LF** | | **2** | **202,560.00** | **$0.28** | **$56,478.00** |
| **394054** | SHOULDER RUMBLE STRIP (AC, GROUND-IN INDENTATIONS) | M | 3 | 1 | 19,500.00 | $1.00 | $19,500.00 |
| | | M | 4 | 1 | 590.00 | $6.00 | $3,540.00 |
| | **Unit Sub Total** | **M** | | **2** | **20,090.00** | **$1.15** | **$23,040.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **394054** | SHOULDER RUMBLE STRIP (AC, GROUND-IN INDENTATIONS) | STA | 1 | 3 | 157.00 | $146.82 | $23,050.00 |
| | | STA | 2 | 2 | 102.00 | $208.14 | $21,230.00 |
| | | STA | 3 | 1 | 270.00 | $40.00 | $10,800.00 |
| | | STA | 4 | 4 | 934.00 | $78.61 | $73,425.00 |
| | | STA | 5 | 3 | 780.00 | $71.92 | $56,100.00 |
| | | STA | 6 | 3 | 1,840.00 | $27.17 | $49,988.00 |
| | | STA | 8 | 2 | 705.00 | $49.40 | $34,825.00 |
| | | STA | 9 | 2 | 871.00 | $43.66 | $38,025.00 |
| | | STA | 11 | 1 | 49.00 | $71.00 | $3,479.00 |
| | **Unit Sub Total** | **STA** | | **21** | **5,708.00** | **$54.47** | **$310,922.00** |
| | **Item Code 394054 Total No. of Proj.** | | | **25** | | **Total Amount** | **$390,440.00** |
| **394071** | PLACE HOT MIX ASPHALT DIKE | LF | 6 | 1 | 1,270.00 | $3.00 | $3,810.00 |
| | | LF | 8 | 1 | 120.00 | $33.00 | $3,960.00 |
| | | LF | 11 | 5 | 44,348.00 | $2.18 | $96,743.00 |
| | **Unit Sub Total** | **LF** | | **7** | **45,738.00** | **$2.29** | **$104,513.00** |
| **394071** | PLACE HOT MIX ASPHALT DIKE | M | 11 | 3 | 9,370.00 | $4.83 | $45,270.00 |
| | **Unit Sub Total** | **M** | | **3** | **9,370.00** | **$4.83** | **$45,270.00** |
| | **Item Code 394071 Total No. of Proj.** | | | **10** | | **Total Amount** | **$149,783.00** |
| **394073** | PLACE HOT MIX ASPHALT DIKE (TYPE A) | LF | 1 | 5 | 18,570.00 | $1.77 | $32,827.00 |
| | | LF | 2 | 5 | 2,138.00 | $14.90 | $31,850.00 |
| | | LF | 3 | 2 | 17,240.00 | $1.05 | $18,164.00 |
| | | LF | 4 | 2 | 310.00 | $23.23 | $7,200.00 |
| | | LF | 6 | 3 | 3,470.00 | $2.69 | $9,319.00 |
| | | LF | 7 | 2 | 1,510.00 | $8.64 | $13,040.00 |
| | | LF | 10 | 1 | 10,700.00 | $0.90 | $9,630.00 |
| | | LF | 11 | 1 | 350.00 | $2.93 | $1,025.50 |
| | | LF | 12 | 2 | 22,015.00 | $1.62 | $35,582.00 |
| | **Unit Sub Total** | **LF** | | **23** | **76,303.00** | **$2.08** | **$158,637.50** |
| **394073** | PLACE HOT MIX ASPHALT DIKE (TYPE A) | M | 1 | 1 | 125.00 | $40.00 | $5,000.00 |
| | | M | 3 | 2 | 338.00 | $16.39 | $5,540.00 |
| | | M | 4 | 2 | 35.00 | $221.43 | $7,750.00 |
| | | M | 5 | 3 | 343.00 | $29.50 | $10,120.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **394073** | PLACE HOT MIX ASPHALT DIKE (TYPE A) | M | 7 | 3 | 825.00 | $7.07 | $5,831.00 |
| | | M | 10 | 1 | 190.00 | $10.50 | $1,995.00 |
| | **Unit Sub Total** | **M** | | **12** | **1,856.00** | **$19.52** | **$36,236.00** |
| | **Item Code 394073 Total No. of Proj.** | | | **35** | | **Total Amount** | **$194,873.50** |
| **394074** | PLACE HOT MIX ASPHALT DIKE (TYPE C) | LF | 1 | 3 | 2,795.00 | $1.47 | $4,096.00 |
| | | LF | 2 | 1 | 16.00 | $40.00 | $640.00 |
| | | LF | 3 | 4 | 3,390.00 | $1.14 | $3,875.00 |
| | | LF | 4 | 1 | 65.00 | $20.00 | $1,300.00 |
| | | LF | 5 | 3 | 2,553.00 | $1.71 | $4,353.00 |
| | | LF | 6 | 2 | 720.00 | $1.37 | $984.00 |
| | | LF | 7 | 2 | 223.00 | $6.43 | $1,435.00 |
| | | LF | 8 | 1 | 68.00 | $5.00 | $340.00 |
| | | LF | 10 | 1 | 60.00 | $0.90 | $54.00 |
| | | LF | 12 | 3 | 1,296.00 | $4.30 | $5,577.50 |
| | **Unit Sub Total** | **LF** | | **21** | **11,186.00** | **$2.03** | **$22,654.50** |
| **394074** | PLACE HOT MIX ASPHALT DIKE (TYPE C) | M | 3 | 2 | 84.00 | $17.20 | $1,444.50 |
| | | M | 4 | 1 | 560.00 | $10.00 | $5,600.00 |
| | | M | 5 | 3 | 96.00 | $23.05 | $2,212.50 |
| | | M | 6 | 1 | 65.00 | $10.00 | $650.00 |
| | | M | 7 | 5 | 1,324.00 | $7.73 | $10,238.75 |
| | | M | 8 | 1 | 1,180.00 | $8.40 | $9,912.00 |
| | **Unit Sub Total** | **M** | | **13** | **3,309.00** | **$9.08** | **$30,057.75** |
| | **Item Code 394074 Total No. of Proj.** | | | **34** | | **Total Amount** | **$52,712.25** |
| **394075** | PLACE HOT MIX ASPHALT DIKE (TYPE D) | LF | 1 | 2 | 11,080.00 | $3.66 | $40,558.00 |
| | | LF | 2 | 2 | 1,550.00 | $6.45 | $10,000.00 |
| | | LF | 3 | 4 | 9,320.00 | $2.61 | $24,318.00 |
| | **Unit Sub Total** | **LF** | | **8** | **21,950.00** | **$3.41** | **$74,876.00** |
| **394075** | PLACE HOT MIX ASPHALT DIKE (TYPE D) | M | 4 | 1 | 290.00 | $13.50 | $3,915.00 |
| | | M | 7 | 1 | 600.00 | $7.15 | $4,290.00 |
| | | M | 8 | 1 | 31.00 | $40.00 | $1,240.00 |
| | **Unit Sub Total** | **M** | | **3** | **921.00** | **$10.26** | **$9,445.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 394075 Total No. of Proj.** | | | **11** | | **Total Amount** | **$84,321.00** |
| **394076** | PLACE HOT MIX ASPHALT DIKE (TYPE E) | LF | 1 | 2 | 14,040.00 | $1.25 | $17,520.00 |
| | | LF | 2 | 1 | 3,650.00 | $2.50 | $9,125.00 |
| | | LF | 3 | 9 | 101,065.00 | $2.05 | $207,600.00 |
| | | LF | 4 | 1 | 1,350.00 | $3.00 | $4,050.00 |
| | | LF | 5 | 1 | 4,730.00 | $1.10 | $5,203.00 |
| | | LF | 6 | 2 | 47,290.00 | $1.25 | $58,980.00 |
| | | LF | 8 | 2 | 2,560.00 | $4.69 | $12,016.00 |
| | | LF | 9 | 1 | 4,830.00 | $1.50 | $7,245.00 |
| | | LF | 10 | 2 | 21,265.00 | $1.01 | $21,550.00 |
| | **Unit Sub Total** | **LF** | | **21** | **200,780.00** | **$1.71** | **$343,289.00** |
| **394076** | PLACE HOT MIX ASPHALT DIKE (TYPE E) | M | 3 | 1 | 850.00 | $11.50 | $9,775.00 |
| | | M | 4 | 4 | 2,581.00 | $10.94 | $28,236.00 |
| | | M | 5 | 2 | 67.00 | $34.63 | $2,320.00 |
| | | M | 6 | 1 | 1,900.00 | $10.00 | $19,000.00 |
| | | M | 7 | 3 | 18,530.00 | $4.12 | $76,400.00 |
| | | M | 8 | 1 | 24,600.00 | $8.40 | $206,640.00 |
| | | M | 9 | 3 | 3,330.00 | $7.23 | $24,078.00 |
| | | M | 10 | 3 | 1,500.00 | $7.25 | $10,871.00 |
| | **Unit Sub Total** | **M** | | **18** | **53,358.00** | **$7.07** | **$377,320.00** |
| | **Item Code 394076 Total No. of Proj.** | | | **39** | | **Total Amount** | **$720,609.00** |
| **394077** | PLACE HOT MIX ASPHALT DIKE (TYPE F) | LF | 1 | 4 | 17,810.00 | $1.82 | $32,434.00 |
| | | LF | 2 | 3 | 694.00 | $17.16 | $11,910.00 |
| | | LF | 3 | 11 | 67,501.00 | $2.27 | $153,550.00 |
| | | LF | 4 | 2 | 690.00 | $6.45 | $4,450.00 |
| | | LF | 5 | 3 | 10,160.00 | $2.33 | $23,685.00 |
| | | LF | 6 | 4 | 14,040.00 | $1.63 | $22,880.00 |
| | | LF | 7 | 2 | 1,730.00 | $5.95 | $10,290.00 |
| | | LF | 8 | 1 | 540.00 | $5.00 | $2,700.00 |
| | | LF | 10 | 1 | 60.00 | $0.90 | $54.00 |
| | | LF | 11 | 1 | 320.00 | $13.00 | $4,160.00 |
| | | LF | 12 | 3 | 8,140.00 | $2.05 | $16,660.50 |
| | **Unit Sub Total** | **LF** | | **35** | **121,685.00** | **$2.32** | **$282,773.50** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **394077** | PLACE HOT MIX ASPHALT DIKE (TYPE F) | M | 3 | 1 | 960.00 | $11.50 | $11,040.00 |
| | | M | 4 | 2 | 265.00 | $8.46 | $2,242.00 |
| | | M | 5 | 4 | 4,442.00 | $8.98 | $39,900.00 |
| | | M | 6 | 1 | 23.00 | $10.00 | $230.00 |
| | | M | 7 | 5 | 6,860.00 | $3.93 | $26,928.65 |
| | | M | 8 | 1 | 4,100.00 | $8.40 | $34,440.00 |
| | | M | 9 | 1 | 26.00 | $10.00 | $260.00 |
| | **Unit Sub Total** | **M** | | **15** | **16,676.00** | **$6.90** | **$115,040.65** |
| | **Item Code 394077 Total No. of Proj.** | | | **50** | | **Total Amount** | **$397,814.15** |
| **394090** | PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA) | M2 | 2 | 1 | 27.00 | $161.00 | $4,347.00 |
| | | M2 | 3 | 1 | 950.00 | $48.00 | $45,600.00 |
| | | M2 | 4 | 2 | 1,670.00 | $21.01 | $35,090.50 |
| | | M2 | 5 | 2 | 154.00 | $66.43 | $10,230.00 |
| | | M2 | 6 | 1 | 2,150.00 | $7.00 | $15,050.00 |
| | | M2 | 7 | 5 | 8,494.00 | $8.62 | $73,206.00 |
| | | M2 | 8 | 2 | 537.00 | $105.52 | $56,665.00 |
| | | M2 | 9 | 2 | 33.00 | $80.12 | $2,644.00 |
| | | M2 | 10 | 5 | 405.00 | $54.02 | $21,878.00 |
| | | M2 | 11 | 3 | 2,606.00 | $13.59 | $35,418.00 |
| | **Unit Sub Total** | **M2** | | **24** | **17,026.00** | **$17.63** | **$300,128.50** |
| **394090** | PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA) | SQFT | 1 | 1 | 60.00 | $14.00 | $840.00 |
| | | SQFT | 2 | 1 | 11,200.00 | $1.00 | $11,200.00 |
| | | SQFT | 3 | 1 | 900.00 | $5.00 | $4,500.00 |
| | | SQFT | 6 | 2 | 2,920.00 | $3.12 | $9,100.00 |
| | **Unit Sub Total** | **SQFT** | | **5** | **15,080.00** | **$1.70** | **$25,640.00** |
| **394090** | PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA) | SQYD | 1 | 8 | 7,655.00 | $10.10 | $77,343.00 |
| | | SQYD | 2 | 5 | 369.00 | $30.41 | $11,220.00 |
| | | SQYD | 3 | 14 | 13,741.00 | $20.82 | $286,027.00 |
| | | SQYD | 4 | 2 | 5,440.00 | $8.48 | $46,145.00 |
| | | SQYD | 5 | 2 | 10.70 | $186.36 | $1,994.00 |
| | | SQYD | 6 | 5 | 1,510.00 | $40.44 | $61,070.00 |
| | | SQYD | 7 | 3 | 241.20 | $37.62 | $9,074.60 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **394090** | PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA) | SQYD | 8 | 1 | 66.00 | $56.00 | $3,696.00 |
| | | SQYD | 10 | 2 | 146.00 | $84.38 | $12,320.00 |
| | | SQYD | 12 | 1 | 14.00 | $350.00 | $4,900.00 |
| | **Unit Sub Total** | **SQYD** | | **43** | **29,192.90** | **$17.60** | **$513,789.60** |
| | **Item Code 394090 Total No. of Proj.** | | | **72** | | **Total Amount** | **$839,558.10** |
| **394095** | ROADSIDE PAVING (MISCELLANEOUS AREAS) | SQYD | 5 | 1 | 52.00 | $350.00 | $18,200.00 |
| | | SQYD | 6 | 1 | 110.00 | $42.65 | $4,691.50 |
| | | SQYD | 11 | 1 | 87.00 | $160.00 | $13,920.00 |
| | **Unit Sub Total** | **SQYD** | | **3** | **249.00** | **$147.84** | **$36,811.50** |
| | **Item Code 394095 Total No. of Proj.** | | | **3** | | **Total Amount** | **$36,811.50** |
| **395000** | LIQUID ASPHALT (PRIME COAT) | TON | 8 | 1 | 14.00 | $1,500.00 | $21,000.00 |
| | **Unit Sub Total** | **TON** | | **1** | **14.00** | **$1,500.00** | **$21,000.00** |
| **395000** | LIQUID ASPHALT (PRIME COAT) | TONN | 4 | 1 | 3.00 | $1,645.00 | $4,935.00 |
| | | TONN | 8 | 1 | 30.00 | $1,000.00 | $30,000.00 |
| | **Unit Sub Total** | **TONN** | | **2** | **33.00** | **$1,058.64** | **$34,935.00** |
| | **Item Code 395000 Total No. of Proj.** | | | **3** | | **Total Amount** | **$55,935.00** |
| **395001** | LIQUID ASPHALT, SC-70 (PRIME COAT) | TON | 12 | 1 | 20.00 | $585.00 | $11,700.00 |
| | **Unit Sub Total** | **TON** | | **1** | **20.00** | **$585.00** | **$11,700.00** |
| | **Item Code 395001 Total No. of Proj.** | | | **1** | | **Total Amount** | **$11,700.00** |
| **395501** | LIQUID ASPHALT, MC-70 (PRIME COAT) | TONN | 8 | 1 | 5.00 | $950.00 | $4,750.00 |
| | **Unit Sub Total** | **TONN** | | **1** | **5.00** | **$950.00** | **$4,750.00** |
| | **Item Code 395501 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,750.00** |
| **397001** | ASPHALTIC EMULSION (PAINT BINDER) | TON | 4 | 4 | 1,206.60 | $564.92 | $681,628.00 |
| | | TON | 5 | 1 | 430.00 | $0.01 | $4.30 |
| | | TON | 10 | 4 | 178.00 | $252.31 | $44,911.00 |
| | | TON | 11 | 6 | 18.20 | $1,204.67 | $21,925.00 |
| | | TON | 12 | 6 | 406.70 | $519.63 | $211,332.50 |
| | **Unit Sub Total** | **TON** | | **21** | **2,239.50** | **$428.58** | **$959,800.80** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **397001** | ASPHALTIC EMULSION (PAINT BINDER) | TONN | 1 | 1 | 45.00 | $1,000.00 | $45,000.00 |
| | | TONN | 3 | 3 | 545.00 | $464.06 | $252,910.00 |
| | | TONN | 4 | 6 | 356.50 | $358.92 | $127,954.00 |
| | | TONN | 5 | 6 | 780.90 | $721.20 | $563,182.50 |
| | | TONN | 6 | 3 | 249.00 | $352.21 | $87,700.00 |
| | | TONN | 10 | 3 | 68.00 | $978.25 | $66,521.00 |
| | | TONN | 11 | 7 | 161.50 | $448.54 | $72,440.00 |
| | **Unit Sub Total** | **TONN** | | **29** | **2,205.90** | **$551.12** | **$1,215,707.50** |
| | **Item Code 397001 Total No. of Proj.** | | | **50** | | **Total Amount** | **$2,175,508.30** |
| **397005** | TACK COAT | TON | 1 | 1 | 10.00 | $500.00 | $5,000.00 |
| | | TON | 3 | 3 | 512.40 | $105.62 | $54,120.00 |
| | | TON | 4 | 10 | 281.50 | $375.07 | $105,581.10 |
| | | TON | 5 | 9 | 395.40 | $416.29 | $164,600.00 |
| | | TON | 6 | 11 | 755.00 | $346.42 | $261,547.00 |
| | | TON | 8 | 13 | 786.80 | $492.22 | $387,281.06 |
| | | TON | 10 | 8 | 581.00 | $170.19 | $98,878.00 |
| | | TON | 11 | 6 | 320.00 | $895.54 | $286,572.22 |
| | | TON | 12 | 3 | 64.00 | $1,007.22 | $64,461.88 |
| | **Unit Sub Total** | **TON** | | **64** | **3,706.10** | **$385.32** | **$1,428,041.26** |
| **397005** | TACK COAT | TONN | 4 | 1 | 52.00 | $1.00 | $52.00 |
| | | TONN | 5 | 2 | 8.00 | $1,356.25 | $10,850.00 |
| | | TONN | 6 | 1 | 270.00 | $855.00 | $230,850.00 |
| | | TONN | 8 | 4 | 209.00 | $754.67 | $157,725.00 |
| | | TONN | 9 | 1 | 6.00 | $1,000.00 | $6,000.00 |
| | | TONN | 10 | 3 | 75.30 | $661.15 | $49,784.30 |
| | | TONN | 11 | 3 | 159.00 | $1,267.30 | $201,500.00 |
| | | TONN | 12 | 1 | 3.00 | $770.00 | $2,310.00 |
| | **Unit Sub Total** | **TONN** | | **16** | **782.30** | **$842.48** | **$659,071.30** |
| | **Item Code 397005 Total No. of Proj.** | | | **80** | | **Total Amount** | **$2,087,112.56** |
| **401000** | CONCRETE PAVEMENT | CY | 3 | 3 | 146,495.00 | $185.86 | $27,227,050.00 |
| | | CY | 4 | 1 | 13.00 | $1,500.00 | $19,500.00 |
| | | CY | 7 | 2 | 440.00 | $247.39 | $108,850.00 |
| | | CY | 11 | 1 | 19,600.00 | $187.00 | $3,665,200.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| 401000 | CONCRETE PAVEMENT | CY | 12 | 1 | 1,330.00 | $275.00 | $365,750.00 |
| | **Unit Sub Total** | **CY** | | **8** | **167,878.00** | **$186.96** | **$31,386,350.00** |
| 401000 | CONCRETE PAVEMENT | M3 | 3 | 2 | 20,252.00 | $264.35 | $5,353,600.00 |
| | | M3 | 6 | 1 | 880.00 | $255.00 | $224,400.00 |
| | | M3 | 7 | 7 | 68,050.00 | $222.65 | $15,151,550.00 |
| | | M3 | 8 | 1 | 16,900.00 | $235.00 | $3,971,500.00 |
| | | M3 | 10 | 1 | 39,200.00 | $170.35 | $6,677,720.00 |
| | | M3 | 11 | 10 | 181,070.00 | $227.93 | $41,272,010.00 |
| | **Unit Sub Total** | **M3** | | **22** | **326,352.00** | **$222.61** | **$72,650,780.00** |
| | **Item Code 401000 Total No. of Proj.** | | | **30** | | **Total Amount** | **$104,037,130.00** |
| 401066 | CONCRETE PAVEMENT (RAMP TERMINI) | CY | 12 | 2 | 255.00 | $353.33 | $90,100.00 |
| | **Unit Sub Total** | **CY** | | **2** | **255.00** | **$353.33** | **$90,100.00** |
| 401066 | CONCRETE PAVEMENT (RAMP TERMINI) | M3 | 7 | 2 | 2,800.00 | $325.85 | $912,380.00 |
| | | M3 | 8 | 1 | 700.00 | $425.00 | $297,500.00 |
| | | M3 | 12 | 1 | 120.00 | $320.00 | $38,400.00 |
| | **Unit Sub Total** | **M3** | | **4** | **3,620.00** | **$344.83** | **$1,248,280.00** |
| | **Item Code 401066 Total No. of Proj.** | | | **6** | | **Total Amount** | **$1,338,380.00** |
| 401080 | SHOULDER RUMBLE STRIP (PCC, ROLLED-IN INDENTATIONS) | STA | 6 | 1 | 230.00 | $45.00 | $10,350.00 |
| | **Unit Sub Total** | **STA** | | **1** | **230.00** | **$45.00** | **$10,350.00** |
| | **Item Code 401080 Total No. of Proj.** | | | **1** | | **Total Amount** | **$10,350.00** |
| 401082 | SHOULDER RUMBLE STRIP (PCC, GROUND-IN INDENTATIONS) | STA | 3 | 3 | 5,689.00 | $45.03 | $256,190.00 |
| | | STA | 11 | 1 | 82.00 | $950.00 | $77,900.00 |
| | **Unit Sub Total** | **STA** | | **4** | **5,771.00** | **$57.89** | **$334,090.00** |
| | **Item Code 401082 Total No. of Proj.** | | | **4** | | **Total Amount** | **$334,090.00** |
| 401102 | CONCRETE PAVEMENT (WEIGH-IN-MOTION) | M3 | 4 | 1 | 60.00 | $1,365.00 | $81,900.00 |
| | **Unit Sub Total** | **M3** | | **1** | **60.00** | **$1,365.00** | **$81,900.00** |
| | **Item Code 401102 Total No. of Proj.** | | | **1** | | **Total Amount** | **$81,900.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **401108** | REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE) | CY | 1 | 2 | 4,440.00 | $458.88 | $2,037,420.00 |
| | | CY | 3 | 3 | 4,290.00 | $401.82 | $1,723,800.00 |
| | | CY | 4 | 4 | 5,440.00 | $580.69 | $3,158,930.00 |
| | | CY | 5 | 2 | 2,280.00 | $724.42 | $1,651,680.00 |
| | | CY | 6 | 1 | 1,420.00 | $610.00 | $866,200.00 |
| | | CY | 7 | 6 | 9,308.00 | $497.35 | $4,629,355.00 |
| | | CY | 10 | 2 | 1,510.00 | $529.96 | $800,235.00 |
| | | CY | 12 | 2 | 730.00 | $713.90 | $521,150.00 |
| | **Unit Sub Total** | **CY** | | **22** | **29,418.00** | **$523.11** | **$15,388,770.00** |
| **401108** | REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE) | M3 | 3 | 2 | 3,410.00 | $981.96 | $3,348,500.00 |
| | | M3 | 4 | 4 | 5,890.00 | $667.51 | $3,931,628.00 |
| | | M3 | 7 | 1 | 18,000.00 | $671.00 | $12,078,000.00 |
| | | M3 | 8 | 1 | 8,610.00 | $390.00 | $3,357,900.00 |
| | | M3 | 11 | 1 | 90.00 | $1,400.00 | $126,000.00 |
| | **Unit Sub Total** | **M3** | | **9** | **36,000.00** | **$634.50** | **$22,842,028.00** |
| | **Item Code 401108 Total No. of Proj.** | | | **31** | | **Total Amount** | **$38,230,798.00** |
| **404092** | SEAL PAVEMENT JOINT | LF | 3 | 3 | 450,300.00 | $1.28 | $577,900.00 |
| | | LF | 6 | 1 | 25,200.00 | $2.15 | $54,180.00 |
| | | LF | 7 | 2 | 38,200.00 | $5.60 | $214,010.00 |
| | | LF | 11 | 1 | 77,300.00 | $1.00 | $77,300.00 |
| | | LF | 12 | 2 | 6,060.00 | $5.94 | $36,000.00 |
| | **Unit Sub Total** | **LF** | | **9** | **597,060.00** | **$1.61** | **$959,390.00** |
| **404092** | SEAL PAVEMENT JOINT | M | 3 | 1 | 25,400.00 | $7.00 | $177,800.00 |
| | | M | 7 | 9 | 137,490.00 | $14.06 | $1,932,472.00 |
| | | M | 8 | 1 | 23,600.00 | $5.50 | $129,800.00 |
| | | M | 10 | 1 | 68,700.00 | $3.57 | $245,259.00 |
| | | M | 11 | 8 | 275,100.00 | $4.59 | $1,264,075.00 |
| | **Unit Sub Total** | **M** | | **20** | **530,290.00** | **$7.07** | **$3,749,406.00** |
| | **Item Code 404092 Total No. of Proj.** | | | **29** | | **Total Amount** | **$4,708,796.00** |
| **404094** | SEAL LONGITUDINAL ISOLATION JOINT | LF | 3 | 3 | 74,870.00 | $4.06 | $303,615.50 |
| | | LF | 6 | 1 | 24,300.00 | $5.40 | $131,220.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **404094** | SEAL LONGITUDINAL ISOLATION JOINT | LF | 7 | 1 | 420.00 | $2.60 | $1,092.00 |
| | | LF | 11 | 1 | 33,500.00 | $1.50 | $50,250.00 |
| | | LF | 12 | 2 | 2,710.00 | $9.82 | $26,625.00 |
| | **Unit Sub Total** | **LF** | | **8** | **135,800.00** | **$3.78** | **$512,802.50** |
| **404094** | SEAL LONGITUDINAL ISOLATION JOINT | M | 7 | 7 | 15,300.00 | $29.57 | $452,370.00 |
| | | M | 8 | 1 | 20,200.00 | $4.00 | $80,800.00 |
| | | M | 11 | 6 | 46,839.00 | $20.14 | $943,286.00 |
| | **Unit Sub Total** | **M** | | **14** | **82,339.00** | **$17.93** | **$1,476,456.00** |
| | **Item Code 404094 Total No. of Proj.** | | | **22** | | **Total Amount** | **$1,989,258.50** |
| **406001** | TIE BAR | EA | 3 | 1 | 26,300.00 | $7.00 | $184,100.00 |
| | **Unit Sub Total** | **EA** | | **1** | **26,300.00** | **$7.00** | **$184,100.00** |
| | **Item Code 406001 Total No. of Proj.** | | | **1** | | **Total Amount** | **$184,100.00** |
| **406003** | TIE BAR (DRILL AND BOND) | EA | 3 | 1 | 1,270.00 | $10.00 | $12,700.00 |
| | | EA | 4 | 1 | 2,360.00 | $20.00 | $47,200.00 |
| | | EA | 7 | 2 | 95,330.00 | $9.66 | $920,630.00 |
| | | EA | 11 | 1 | 95.00 | $28.00 | $2,660.00 |
| | | EA | 12 | 1 | 1,630.00 | $10.00 | $16,300.00 |
| | **Unit Sub Total** | **EA** | | **6** | **100,685.00** | **$9.93** | **$999,490.00** |
| | **Item Code 406003 Total No. of Proj.** | | | **6** | | **Total Amount** | **$999,490.00** |
| **406100** | DOWEL BAR RETROFIT | EA | 3 | 1 | 7,530.00 | $100.00 | $753,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **7,530.00** | **$100.00** | **$753,000.00** |
| | **Item Code 406100 Total No. of Proj.** | | | **1** | | **Total Amount** | **$753,000.00** |
| **413111** | REPAIR SPALLED JOINTS | LS | 11 | 1 | 1.00 | $100.00 | $100.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$100.00** | **$100.00** |
| **413111** | REPAIR SPALLED JOINTS | M2 | 3 | 1 | 100.00 | $1,100.00 | $110,000.00 |
| | | M2 | 11 | 3 | 70.00 | $935.71 | $65,500.00 |
| | **Unit Sub Total** | **M2** | | **4** | **170.00** | **$1,032.35** | **$175,500.00** |
| **413111** | REPAIR SPALLED JOINTS | SQYD | 3 | 1 | 120.00 | $935.00 | $112,200.00 |
| | | SQYD | 8 | 2 | 9.70 | $1,039.69 | $10,085.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **SQYD** | | **3** | **129.70** | **$942.83** | **$122,285.00** |
| | **Item Code 413111 Total No. of Proj.** | | | **8** | | **Total Amount** | **$297,885.00** |
| **413115** | SEAL JOINT (EXISTING CONCRETE PAVEMENT) | LF | 3 | 1 | 100,000.00 | $1.22 | $122,000.00 |
| | | LF | 6 | 1 | 450,000.00 | $0.38 | $171,000.00 |
| | | LF | 7 | 1 | 447,000.00 | $1.30 | $581,100.00 |
| | | LF | 8 | 1 | 307,000.00 | $1.02 | $313,140.00 |
| | **Unit Sub Total** | **LF** | | **4** | **1,304,000.00** | **$0.91** | **$1,187,240.00** |
| **413115** | SEAL JOINT (EXISTING CONCRETE PAVEMENT) | M | 11 | 1 | 5,420.00 | $7.00 | $37,940.00 |
| | **Unit Sub Total** | **M** | | **1** | **5,420.00** | **$7.00** | **$37,940.00** |
| | **Item Code 413115 Total No. of Proj.** | | | **5** | | **Total Amount** | **$1,225,180.00** |
| **414091** | SEAL LONGITUDINAL JOINT | M | 11 | 1 | 24,100.00 | $4.20 | $101,220.00 |
| | **Unit Sub Total** | **M** | | **1** | **24,100.00** | **$4.20** | **$101,220.00** |
| | **Item Code 414091 Total No. of Proj.** | | | **1** | | **Total Amount** | **$101,220.00** |
| **414101** | SEAL TRANSVERSE JOINT | M | 11 | 1 | 15,000.00 | $4.20 | $63,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **15,000.00** | **$4.20** | **$63,000.00** |
| | **Item Code 414101 Total No. of Proj.** | | | **1** | | **Total Amount** | **$63,000.00** |
| **415101** | CRACK EXISTING CONCRETE PAVEMENT | M2 | 4 | 4 | 404,000.00 | $0.67 | $271,416.00 |
| | | M2 | 6 | 1 | 22,400.00 | $0.98 | $21,952.00 |
| | | M2 | 7 | 1 | 36,500.00 | $0.67 | $24,455.00 |
| | **Unit Sub Total** | **M2** | | **6** | **462,900.00** | **$0.69** | **$317,823.00** |
| **415101** | CRACK EXISTING CONCRETE PAVEMENT | SQYD | 3 | 1 | 82,900.00 | $0.65 | $53,885.00 |
| | | SQYD | 4 | 1 | 387,000.00 | $0.70 | $270,900.00 |
| | **Unit Sub Total** | **SQYD** | | **2** | **469,900.00** | **$0.69** | **$324,785.00** |
| | **Item Code 415101 Total No. of Proj.** | | | **8** | | **Total Amount** | **$642,608.00** |
| **416101** | PAVEMENT TRANSITION TAPER | M2 | 4 | 1 | 3,630.00 | $28.00 | $101,640.00 |
| | **Unit Sub Total** | **M2** | | **1** | **3,630.00** | **$28.00** | **$101,640.00** |
| **416101** | PAVEMENT TRANSITION TAPER | SQYD | 3 | 1 | 3,040.00 | $28.00 | $85,120.00 |
| | **Unit Sub Total** | **SQYD** | | **1** | **3,040.00** | **$28.00** | **$85,120.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 416101 Total No. of Proj.** | | | **2** | | **Total Amount** | **$186,760.00** |
| **420102** | GROOVE EXISTING CONCRETE PAVEMENT | SQYD | 3 | 1 | 131,000.00 | $2.50 | $327,500.00 |
| | **Unit Sub Total** | **SQYD** | | **1** | **131,000.00** | **$2.50** | **$327,500.00** |
| | **Item Code 420102 Total No. of Proj.** | | | **1** | | **Total Amount** | **$327,500.00** |
| **420201** | GRIND EXISTING CONCRETE PAVEMENT | M2 | 3 | 2 | 13,740.00 | $12.02 | $165,100.00 |
| | | M2 | 4 | 5 | 11,360.00 | $14.56 | $165,355.80 |
| | | M2 | 7 | 4 | 623,322.00 | $4.75 | $2,961,382.00 |
| | | M2 | 8 | 1 | 84,400.00 | $4.60 | $388,240.00 |
| | | M2 | 11 | 5 | 83,930.00 | $6.03 | $506,450.00 |
| | **Unit Sub Total** | **M2** | | **17** | **816,752.00** | **$5.13** | **$4,186,527.80** |
| **420201** | GRIND EXISTING CONCRETE PAVEMENT | SQFT | 12 | 1 | 1,190,000.00 | $0.48 | $571,200.00 |
| | **Unit Sub Total** | **SQFT** | | **1** | **1,190,000.00** | **$0.48** | **$571,200.00** |
| **420201** | GRIND EXISTING CONCRETE PAVEMENT | SQYD | 1 | 2 | 13,410.00 | $6.63 | $88,878.50 |
| | | SQYD | 3 | 2 | 29,200.00 | $14.41 | $420,700.00 |
| | | SQYD | 4 | 3 | 377,470.00 | $4.77 | $1,799,930.00 |
| | | SQYD | 5 | 2 | 43,590.00 | $5.32 | $231,810.00 |
| | | SQYD | 6 | 1 | 98,500.00 | $5.71 | $562,435.00 |
| | | SQYD | 7 | 8 | 720,202.00 | $4.48 | $3,223,841.20 |
| | | SQYD | 8 | 1 | 33,800.00 | $4.70 | $158,860.00 |
| | | SQYD | 11 | 1 | 8,620.00 | $4.60 | $39,652.00 |
| | | SQYD | 12 | 2 | 1,050.00 | $18.43 | $19,350.00 |
| | **Unit Sub Total** | **SQYD** | | **22** | **1,325,842.00** | **$4.94** | **$6,545,456.70** |
| | **Item Code 420201 Total No. of Proj.** | | | **40** | | **Total Amount** | **$11,303,184.50** |
| **490505** | FURNISH STEEL PILING (HP 250 X 62) | M | 3 | 1 | 2,508.00 | $130.00 | $326,040.00 |
| | **Unit Sub Total** | **M** | | **1** | **2,508.00** | **$130.00** | **$326,040.00** |
| | **Item Code 490505 Total No. of Proj.** | | | **1** | | **Total Amount** | **$326,040.00** |
| **490506** | DRIVE STEEL PILE (HP 250 X 62) | EA | 3 | 1 | 197.00 | $800.00 | $157,600.00 |
| | **Unit Sub Total** | **EA** | | **1** | **197.00** | **$800.00** | **$157,600.00** |
| | **Item Code 490506 Total No. of Proj.** | | | **1** | | **Total Amount** | **$157,600.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **490511** | FURNISH STEEL PILING (HP 250 X 85) | M | 3 | 3 | 13,839.00 | $154.38 | $2,136,479.00 |
| | | M | 5 | 1 | 37.00 | $357.00 | $13,209.00 |
| | | M | 9 | 1 | 1,854.00 | $150.00 | $278,100.00 |
| | | M | 10 | 1 | 3,843.00 | $20.00 | $76,860.00 |
| | | M | 11 | 2 | 2,818.00 | $180.92 | $509,840.00 |
| | **Unit Sub Total** | **M** | | **8** | **22,391.00** | **$134.63** | **$3,014,488.00** |
| | **Item Code 490511 Total No. of Proj.** | | | **8** | | **Total Amount** | **$3,014,488.00** |
| **490512** | DRIVE STEEL PILE (HP 250 X 85) | EA | 3 | 3 | 907.00 | $1,023.48 | $928,300.00 |
| | | EA | 5 | 1 | 2.00 | $7,842.00 | $15,684.00 |
| | | EA | 9 | 1 | 107.00 | $3,500.00 | $374,500.00 |
| | | EA | 10 | 1 | 210.00 | $500.00 | $105,000.00 |
| | | EA | 11 | 2 | 248.00 | $1,372.82 | $340,460.00 |
| | **Unit Sub Total** | **EA** | | **8** | **1,474.00** | **$1,196.71** | **$1,763,944.00** |
| | **Item Code 490512 Total No. of Proj.** | | | **8** | | **Total Amount** | **$1,763,944.00** |
| **490566** | FURNISH STEEL PILING (HP 360 X 132) | M | 1 | 1 | 1,675.00 | $300.00 | $502,500.00 |
| | | M | 3 | 1 | 1,284.00 | $270.00 | $346,680.00 |
| | | M | 10 | 1 | 1,473.00 | $20.00 | $29,460.00 |
| | **Unit Sub Total** | **M** | | **3** | **4,432.00** | **$198.25** | **$878,640.00** |
| | **Item Code 490566 Total No. of Proj.** | | | **3** | | **Total Amount** | **$878,640.00** |
| **490567** | DRIVE STEEL PILE (HP 360 X 132) | EA | 1 | 1 | 79.00 | $2,500.00 | $197,500.00 |
| | | EA | 3 | 1 | 92.00 | $800.00 | $73,600.00 |
| | | EA | 10 | 1 | 95.00 | $500.00 | $47,500.00 |
| | **Unit Sub Total** | **EA** | | **3** | **266.00** | **$1,197.74** | **$318,600.00** |
| | **Item Code 490567 Total No. of Proj.** | | | **3** | | **Total Amount** | **$318,600.00** |
| **490568** | FURNISH STEEL PILING (HP 360 X 152) | M | 1 | 1 | 1,209.00 | $311.00 | $375,999.00 |
| | **Unit Sub Total** | **M** | | **1** | **1,209.00** | **$311.00** | **$375,999.00** |
| | **Item Code 490568 Total No. of Proj.** | | | **1** | | **Total Amount** | **$375,999.00** |
| **490570** | FURNISH STEEL PILING (HP 360 X 174) | M | 3 | 1 | 966.00 | $370.00 | $357,420.00 |
| | **Unit Sub Total** | **M** | | **1** | **966.00** | **$370.00** | **$357,420.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 490570 Total No. of Proj.** | | | **1** | | **Total Amount** | **$357,420.00** |
| **490571** | DRIVE STEEL PILE (HP 360 X 174) | EA | 3 | 1 | 64.00 | $800.00 | $51,200.00 |
| | **Unit Sub Total** | **EA** | | **1** | **64.00** | **$800.00** | **$51,200.00** |
| | **Item Code 490571 Total No. of Proj.** | | | **1** | | **Total Amount** | **$51,200.00** |
| **490582** | FURNISH STEEL PIPE PILING (406 MM) | M | 11 | 1 | 2,235.00 | $355.00 | $793,425.00 |
| | **Unit Sub Total** | **M** | | **1** | **2,235.00** | **$355.00** | **$793,425.00** |
| | **Item Code 490582 Total No. of Proj.** | | | **1** | | **Total Amount** | **$793,425.00** |
| **490583** | DRIVE STEEL PIPE PILE (406 MM) | EA | 11 | 1 | 120.00 | $1,600.00 | $192,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **120.00** | **$1,600.00** | **$192,000.00** |
| | **Item Code 490583 Total No. of Proj.** | | | **1** | | **Total Amount** | **$192,000.00** |
| **490584** | FURNISH STEEL PIPE PILING (610 MM) | M | 1 | 1 | 782.00 | $480.00 | $375,360.00 |
| | **Unit Sub Total** | **M** | | **1** | **782.00** | **$480.00** | **$375,360.00** |
| | **Item Code 490584 Total No. of Proj.** | | | **1** | | **Total Amount** | **$375,360.00** |
| **490585** | DRIVE STEEL PIPE PILE (610 MM) | EA | 1 | 1 | 46.00 | $3,500.00 | $161,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **46.00** | **$3,500.00** | **$161,000.00** |
| | **Item Code 490585 Total No. of Proj.** | | | **1** | | **Total Amount** | **$161,000.00** |
| **490601** | 16" CAST-IN-DRILLED-HOLE CONCRETE PILING | LF | 4 | 1 | 1,431.00 | $70.00 | $100,170.00 |
| | **Unit Sub Total** | **LF** | | **1** | **1,431.00** | **$70.00** | **$100,170.00** |
| | **Item Code 490601 Total No. of Proj.** | | | **1** | | **Total Amount** | **$100,170.00** |
| **490603** | 24" CAST-IN-DRILLED-HOLE CONCRETE PILING | LF | 12 | 1 | 383.00 | $46.00 | $17,618.00 |
| | **Unit Sub Total** | **LF** | | **1** | **383.00** | **$46.00** | **$17,618.00** |
| | **Item Code 490603 Total No. of Proj.** | | | **1** | | **Total Amount** | **$17,618.00** |
| **490604** | 30" CAST-IN-DRILLED-HOLE CONCRETE PILING | LF | 12 | 1 | 240.00 | $190.00 | $45,600.00 |
| | **Unit Sub Total** | **LF** | | **1** | **240.00** | **$190.00** | **$45,600.00** |
| | **Item Code 490604 Total No. of Proj.** | | | **1** | | **Total Amount** | **$45,600.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **490605** | 36" CAST-IN-DRILLED-HOLE CONCRETE PILING | LF | 4 | 1 | 40.00 | $2,000.00 | $80,000.00 |
| | **Unit Sub Total** | **LF** | | **1** | **40.00** | **$2,000.00** | **$80,000.00** |
| | **Item Code 490605 Total No. of Proj.** | | | **1** | | **Total Amount** | **$80,000.00** |
| **490607** | 48" CAST-IN-DRILLED-HOLE CONCRETE PILING | LF | 7 | 1 | 360.00 | $540.00 | $194,400.00 |
| | **Unit Sub Total** | **LF** | | **1** | **360.00** | **$540.00** | **$194,400.00** |
| | **Item Code 490607 Total No. of Proj.** | | | **1** | | **Total Amount** | **$194,400.00** |
| **490609** | 60" CAST-IN-DRILLED-HOLE CONCRETE PILING | LF | 4 | 1 | 129.00 | $1,000.00 | $129,000.00 |
| | | LF | 8 | 1 | 80.00 | $1,600.00 | $128,000.00 |
| | **Unit Sub Total** | **LF** | | **2** | **209.00** | **$1,229.67** | **$257,000.00** |
| | **Item Code 490609 Total No. of Proj.** | | | **2** | | **Total Amount** | **$257,000.00** |
| **490611** | 72" CAST-IN-DRILLED-HOLE CONCRETE PILING | LF | 7 | 1 | 140.00 | $1,050.00 | $147,000.00 |
| | | LF | 8 | 1 | 80.00 | $2,200.00 | $176,000.00 |
| | **Unit Sub Total** | **LF** | | **2** | **220.00** | **$1,468.18** | **$323,000.00** |
| | **Item Code 490611 Total No. of Proj.** | | | **2** | | **Total Amount** | **$323,000.00** |
| **490655** | 400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING | M | 3 | 1 | 9,700.00 | $180.00 | $1,746,000.00 |
| | | M | 4 | 1 | 1,520.00 | $300.00 | $456,000.00 |
| | | M | 7 | 2 | 2,089.00 | $204.01 | $426,170.00 |
| | | M | 11 | 2 | 501.00 | $229.54 | $115,000.00 |
| | **Unit Sub Total** | **M** | | **6** | **13,810.00** | **$198.64** | **$2,743,170.00** |
| | **Item Code 490655 Total No. of Proj.** | | | **6** | | **Total Amount** | **$2,743,170.00** |
| **490657** | 600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING | M | 2 | 1 | 26.00 | $2,156.00 | $56,056.00 |
| | | M | 4 | 3 | 490.00 | $538.02 | $263,630.00 |
| | | M | 7 | 1 | 1,345.00 | $260.00 | $349,700.00 |
| | | M | 11 | 1 | 297.00 | $260.00 | $77,220.00 |
| | **Unit Sub Total** | **M** | | **6** | **2,158.00** | **$345.97** | **$746,606.00** |
| | **Item Code 490657 Total No. of Proj.** | | | **6** | | **Total Amount** | **$746,606.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **490658** | 750 MM CAST-IN-DRILLED-HOLE CONCRETE PILING | M | 3 | 1 | 117.00 | $1,200.00 | $140,400.00 |
| | | M | 11 | 2 | 1,921.00 | $596.80 | $1,146,450.00 |
| | **Unit Sub Total** | **M** | | **3** | **2,038.00** | **$631.43** | **$1,286,850.00** |
| | **Item Code 490658 Total No. of Proj.** | | | **3** | | **Total Amount** | **$1,286,850.00** |
| **490661** | 1.2 M CAST-IN-DRILLED-HOLE CONCRETE PILING | M | 3 | 1 | 180.00 | $2,300.00 | $414,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **180.00** | **$2,300.00** | **$414,000.00** |
| | **Item Code 490661 Total No. of Proj.** | | | **1** | | **Total Amount** | **$414,000.00** |
| **490663** | 1.5 M CAST-IN-DRILLED-HOLE CONCRETE PILING | M | 2 | 2 | 2,230.00 | $268.30 | $598,300.00 |
| | | M | 7 | 2 | 159.00 | $2,435.85 | $387,300.00 |
| | | M | 11 | 1 | 204.00 | $910.00 | $185,640.00 |
| | **Unit Sub Total** | **M** | | **5** | **2,593.00** | **$451.69** | **$1,171,240.00** |
| | **Item Code 490663 Total No. of Proj.** | | | **5** | | **Total Amount** | **$1,171,240.00** |
| **490665** | 1.8 M CAST-IN-DRILLED-HOLE CONCRETE PILING | M | 2 | 1 | 230.00 | $4,500.00 | $1,035,000.00 |
| | | M | 7 | 1 | 214.00 | $2,000.00 | $428,000.00 |
| | **Unit Sub Total** | **M** | | **2** | **444.00** | **$3,295.05** | **$1,463,000.00** |
| | **Item Code 490665 Total No. of Proj.** | | | **2** | | **Total Amount** | **$1,463,000.00** |
| **490669** | 2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING | M | 11 | 1 | 63.00 | $22,000.00 | $1,386,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **63.00** | **$22,000.00** | **$1,386,000.00** |
| | **Item Code 490669 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,386,000.00** |
| **490671** | 2.4 M CAST-IN-DRILLED-HOLE CONCRETE PILING | M | 2 | 2 | 843.00 | $9,259.51 | $7,805,766.00 |
| | | M | 3 | 1 | 77.00 | $2,800.00 | $215,600.00 |
| | | M | 11 | 2 | 118.00 | $18,694.92 | $2,206,000.00 |
| | **Unit Sub Total** | **M** | | **5** | **1,038.00** | **$9,852.95** | **$10,227,366.00** |
| | **Item Code 490671 Total No. of Proj.** | | | **5** | | **Total Amount** | **$10,227,366.00** |
| **490673** | 3.0 M CAST-IN-DRILLED-HOLE CONCRETE PILING | M | 7 | 1 | 32.00 | $24,000.00 | $768,000.00 |
| | | M | 11 | 1 | 689.00 | $11,250.00 | $7,751,250.00 |
| | **Unit Sub Total** | **M** | | **2** | **721.00** | **$11,815.88** | **$8,519,250.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 490673 Total No. of Proj.** | | | **2** | | **Total Amount** | **$8,519,250.00** |
| **490677** | 1.2 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET) | M | 7 | 1 | 74.00 | $2,250.00 | $166,500.00 |
| | **Unit Sub Total** | **M** | | **1** | **74.00** | **$2,250.00** | **$166,500.00** |
| | **Item Code 490677 Total No. of Proj.** | | | **1** | | **Total Amount** | **$166,500.00** |
| **490678** | 1.5 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET) | M | 2 | 1 | 88.00 | $9,500.00 | $836,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **88.00** | **$9,500.00** | **$836,000.00** |
| | **Item Code 490678 Total No. of Proj.** | | | **1** | | **Total Amount** | **$836,000.00** |
| **490679** | 1.8 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET) | M | 4 | 1 | 34.00 | $4,200.00 | $142,800.00 |
| | **Unit Sub Total** | **M** | | **1** | **34.00** | **$4,200.00** | **$142,800.00** |
| | **Item Code 490679 Total No. of Proj.** | | | **1** | | **Total Amount** | **$142,800.00** |
| **490680** | 2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET) | M | 2 | 1 | 138.00 | $10,500.00 | $1,449,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **138.00** | **$10,500.00** | **$1,449,000.00** |
| | **Item Code 490680 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,449,000.00** |
| **490681** | 2.4 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET) | M | 7 | 1 | 466.00 | $5,000.00 | $2,330,000.00 |
| | | M | 11 | 1 | 43.00 | $26,000.00 | $1,118,000.00 |
| | **Unit Sub Total** | **M** | | **2** | **509.00** | **$6,774.07** | **$3,448,000.00** |
| | **Item Code 490681 Total No. of Proj.** | | | **2** | | **Total Amount** | **$3,448,000.00** |
| **490696** | FURNISH PILING (CLASS 900) | M | 4 | 1 | 391.00 | $45.00 | $17,595.00 |
| | **Unit Sub Total** | **M** | | **1** | **391.00** | **$45.00** | **$17,595.00** |
| | **Item Code 490696 Total No. of Proj.** | | | **1** | | **Total Amount** | **$17,595.00** |
| **490697** | DRIVE PILE (CLASS 900) | EA | 4 | 1 | 30.00 | $2,500.00 | $75,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **30.00** | **$2,500.00** | **$75,000.00** |
| | **Item Code 490697 Total No. of Proj.** | | | **1** | | **Total Amount** | **$75,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **490700** | FURNISH PILING (CLASS 900) (ALTERNATIVE W) | M | 5 | 1 | 1,312.00 | $230.00 | $301,760.00 |
| | | M | 10 | 1 | 1,160.00 | $265.20 | $307,632.00 |
| | **Unit Sub Total** | **M** | | **2** | **2,472.00** | **$246.52** | **$609,392.00** |
| | **Item Code 490700 Total No. of Proj.** | | | **2** | | **Total Amount** | **$609,392.00** |
| **490701** | DRIVE PILE (CLASS 900) (ALTERNATIVE W) | EA | 5 | 1 | 76.00 | $2,160.00 | $164,160.00 |
| | | EA | 10 | 1 | 80.00 | $1,777.00 | $142,160.00 |
| | **Unit Sub Total** | **EA** | | **2** | **156.00** | **$1,963.59** | **$306,320.00** |
| | **Item Code 490701 Total No. of Proj.** | | | **2** | | **Total Amount** | **$306,320.00** |
| **490738** | FURNISH PILING (CLASS 140) | LF | 12 | 1 | 1,813.00 | $20.00 | $36,260.00 |
| | **Unit Sub Total** | **LF** | | **1** | **1,813.00** | **$20.00** | **$36,260.00** |
| | **Item Code 490738 Total No. of Proj.** | | | **1** | | **Total Amount** | **$36,260.00** |
| **490739** | DRIVE PILE (CLASS 140) | EA | 12 | 1 | 36.00 | $2,910.00 | $104,760.00 |
| | **Unit Sub Total** | **EA** | | **1** | **36.00** | **$2,910.00** | **$104,760.00** |
| | **Item Code 490739 Total No. of Proj.** | | | **1** | | **Total Amount** | **$104,760.00** |
| **490753** | FURNISH PILING (CLASS 625) | M | 11 | 1 | 9,230.00 | $105.00 | $969,150.00 |
| | **Unit Sub Total** | **M** | | **1** | **9,230.00** | **$105.00** | **$969,150.00** |
| | **Item Code 490753 Total No. of Proj.** | | | **1** | | **Total Amount** | **$969,150.00** |
| **490754** | DRIVE PILE (CLASS 625) | EA | 11 | 1 | 555.00 | $1,600.00 | $888,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **555.00** | **$1,600.00** | **$888,000.00** |
| | **Item Code 490754 Total No. of Proj.** | | | **1** | | **Total Amount** | **$888,000.00** |
| **490755** | FURNISH PILING (CLASS 625 MODIFIED) | M | 4 | 1 | 101.00 | $40.00 | $4,040.00 |
| | **Unit Sub Total** | **M** | | **1** | **101.00** | **$40.00** | **$4,040.00** |
| | **Item Code 490755 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,040.00** |
| **490756** | DRIVE PILE (CLASS 625 MODIFIED) | EA | 4 | 1 | 8.00 | $2,500.00 | $20,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **8.00** | **$2,500.00** | **$20,000.00** |
| | **Item Code 490756 Total No. of Proj.** | | | **1** | | **Total Amount** | **$20,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **490770** | FURNISH PILING (CLASS 625) (ALTERNATIVE V) | M | 2 | 1 | 41.00 | $550.00 | $22,550.00 |
| | | M | 5 | 1 | 1,810.00 | $126.00 | $228,060.00 |
| | | M | 11 | 2 | 1,382.00 | $158.84 | $219,513.00 |
| | **Unit Sub Total** | **M** | | **4** | **3,233.00** | **$145.41** | **$470,123.00** |
| | **Item Code 490770 Total No. of Proj.** | | | **4** | | **Total Amount** | **$470,123.00** |
| **490771** | DRIVE PILE (CLASS 625) (ALTERNATIVE V) | EA | 2 | 1 | 4.00 | $7,500.00 | $30,000.00 |
| | | EA | 5 | 1 | 92.00 | $1,080.00 | $99,360.00 |
| | | EA | 11 | 2 | 145.00 | $1,276.55 | $185,100.00 |
| | **Unit Sub Total** | **EA** | | **4** | **241.00** | **$1,304.81** | **$314,460.00** |
| | **Item Code 490771 Total No. of Proj.** | | | **4** | | **Total Amount** | **$314,460.00** |
| **490772** | FURNISH PILING (CLASS 625) (ALTERNATIVE W) | M | 10 | 1 | 1,805.00 | $204.00 | $368,220.00 |
| | **Unit Sub Total** | **M** | | **1** | **1,805.00** | **$204.00** | **$368,220.00** |
| | **Item Code 490772 Total No. of Proj.** | | | **1** | | **Total Amount** | **$368,220.00** |
| **490773** | DRIVE PILE (CLASS 625) (ALTERNATIVE W) | EA | 10 | 1 | 103.00 | $1,777.00 | $183,031.00 |
| | **Unit Sub Total** | **EA** | | **1** | **103.00** | **$1,777.00** | **$183,031.00** |
| | **Item Code 490773 Total No. of Proj.** | | | **1** | | **Total Amount** | **$183,031.00** |
| **490801** | STEEL SHEET PILING | M2 | 2 | 1 | 684.00 | $376.00 | $257,184.00 |
| | | M2 | 6 | 1 | 56.00 | $750.00 | $42,000.00 |
| | **Unit Sub Total** | **M2** | | **2** | **740.00** | **$404.30** | **$299,184.00** |
| | **Item Code 490801 Total No. of Proj.** | | | **2** | | **Total Amount** | **$299,184.00** |
| **491007** | FURNISH PILING (CLASS 400) | M | 4 | 1 | 160.00 | $5.10 | $816.00 |
| | | M | 5 | 1 | 11,738.00 | $87.00 | $1,021,206.00 |
| | | M | 10 | 1 | 5,252.00 | $20.00 | $105,040.00 |
| | **Unit Sub Total** | **M** | | **3** | **17,150.00** | **$65.72** | **$1,127,062.00** |
| | **Item Code 491007 Total No. of Proj.** | | | **3** | | **Total Amount** | **$1,127,062.00** |
| **491008** | DRIVE PILE (CLASS 400) | EA | 4 | 1 | 14.00 | $7,650.00 | $107,100.00 |
| | | EA | 5 | 1 | 956.00 | $1,080.00 | $1,032,480.00 |
| | | EA | 10 | 1 | 464.00 | $3,460.00 | $1,605,440.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **EA** | | **3** | **1,434.00** | **$1,914.24** | **$2,745,020.00** |
| | **Item Code 491008 Total No. of Proj.** | | | **3** | | **Total Amount** | **$2,745,020.00** |
| **491012** | FURNISH PILING (CLASS 400) (ALTERNATIVE W) | M | 10 | 1 | 625.00 | $178.50 | $111,562.50 |
| | **Unit Sub Total** | **M** | | **1** | **625.00** | **$178.50** | **$111,562.50** |
| | **Item Code 491012 Total No. of Proj.** | | | **1** | | **Total Amount** | **$111,562.50** |
| **491013** | DRIVE PILE (CLASS 400) (ALTERNATIVE W) | EA | 10 | 1 | 46.00 | $1,530.00 | $70,380.00 |
| | **Unit Sub Total** | **EA** | | **1** | **46.00** | **$1,530.00** | **$70,380.00** |
| | **Item Code 491013 Total No. of Proj.** | | | **1** | | **Total Amount** | **$70,380.00** |
| **493487** | 2.4 M PERMANENT STEEL CASING | M | 2 | 1 | 144.00 | $6,750.00 | $972,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **144.00** | **$6,750.00** | **$972,000.00** |
| | **Item Code 493487 Total No. of Proj.** | | | **1** | | **Total Amount** | **$972,000.00** |
| **498027** | 400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL) | M | 3 | 1 | 150.00 | $300.00 | $45,000.00 |
| | | M | 7 | 1 | 2,850.00 | $120.00 | $342,000.00 |
| | | M | 11 | 2 | 1,459.00 | $126.34 | $184,334.34 |
| | **Unit Sub Total** | **M** | | **4** | **4,459.00** | **$128.13** | **$571,334.34** |
| | **Item Code 498027 Total No. of Proj.** | | | **4** | | **Total Amount** | **$571,334.34** |
| **498030** | 600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL) | M | 7 | 1 | 278.00 | $310.00 | $86,180.00 |
| | **Unit Sub Total** | **M** | | **1** | **278.00** | **$310.00** | **$86,180.00** |
| | **Item Code 498030 Total No. of Proj.** | | | **1** | | **Total Amount** | **$86,180.00** |
| **499024** | FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (460 MM) | M | 5 | 1 | 1,080.00 | $345.00 | $372,600.00 |
| | **Unit Sub Total** | **M** | | **1** | **1,080.00** | **$345.00** | **$372,600.00** |
| | **Item Code 499024 Total No. of Proj.** | | | **1** | | **Total Amount** | **$372,600.00** |
| **499025** | DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (460 MM) | EA | 5 | 1 | 104.00 | $2,430.00 | $252,720.00 |
| | **Unit Sub Total** | **EA** | | **1** | **104.00** | **$2,430.00** | **$252,720.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 499025 Total No. of Proj.** | | | **1** | | **Total Amount** | **$252,720.00** |
| **499030** | FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (610 MM) | M | 1 | 1 | 280.00 | $480.00 | $134,400.00 |
| | | M | 11 | 1 | 1,228.00 | $610.00 | $749,080.00 |
| | **Unit Sub Total** | **M** | | **2** | **1,508.00** | **$585.86** | **$883,480.00** |
| | **Item Code 499030 Total No. of Proj.** | | | **2** | | **Total Amount** | **$883,480.00** |
| **499031** | DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (610 MM) | EA | 1 | 1 | 16.00 | $6,000.00 | $96,000.00 |
| | | EA | 11 | 1 | 56.00 | $5,900.00 | $330,400.00 |
| | **Unit Sub Total** | **EA** | | **2** | **72.00** | **$5,922.22** | **$426,400.00** |
| | **Item Code 499031 Total No. of Proj.** | | | **2** | | **Total Amount** | **$426,400.00** |
| **499052** | FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (1219 MM) | M | 11 | 1 | 656.00 | $1,200.00 | $787,200.00 |
| | **Unit Sub Total** | **M** | | **1** | **656.00** | **$1,200.00** | **$787,200.00** |
| | **Item Code 499052 Total No. of Proj.** | | | **1** | | **Total Amount** | **$787,200.00** |
| **499053** | DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (1219 MM) | EA | 11 | 1 | 16.00 | $41,000.00 | $656,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **16.00** | **$41,000.00** | **$656,000.00** |
| | **Item Code 499053 Total No. of Proj.** | | | **1** | | **Total Amount** | **$656,000.00** |
| **500001** | PRESTRESSING CAST-IN-PLACE CONCRETE | LS | 1 | 3 | 3.00 | $253,333.33 | $760,000.00 |
| | | LS | 2 | 2 | 2.00 | $717,500.00 | $1,435,000.00 |
| | | LS | 3 | 2 | 2.00 | $485,000.00 | $970,000.00 |
| | | LS | 4 | 3 | 3.00 | $67,000.00 | $201,000.00 |
| | | LS | 5 | 1 | 1.00 | $170,000.00 | $170,000.00 |
| | | LS | 7 | 2 | 2.00 | $645,000.00 | $1,290,000.00 |
| | | LS | 8 | 2 | 2.00 | $159,000.00 | $318,000.00 |
| | | LS | 9 | 1 | 1.00 | $80,000.00 | $80,000.00 |
| | | LS | 10 | 2 | 2.00 | $183,750.00 | $367,500.00 |
| | | LS | 11 | 9 | 9.00 | $432,222.22 | $3,890,000.00 |
| | | LS | 12 | 1 | 1.00 | $65,000.00 | $65,000.00 |
| | **Unit Sub Total** | **LS** | | **28** | **28.00** | **$340,946.43** | **$9,546,500.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | **Item Code 500001** | **Total No. of Proj.** | | | **28** | | **Total Amount** | **$9,546,500.00** |
| **500010** | PRESTRESSING | | LS | 1 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | | | LS | 5 | 1 | 1.00 | $17,251.00 | $17,251.00 |
| | | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$21,125.50** | **$42,251.00** |
| | **Item Code 500010** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$42,251.00** |
| **500050** | TIEBACK ANCHOR | | EA | 1 | 2 | 413.00 | $5,584.64 | $2,306,455.00 |
| | | | EA | 2 | 1 | 13.00 | $5,400.00 | $70,200.00 |
| | | | EA | 3 | 1 | 252.00 | $2,450.00 | $617,400.00 |
| | | | EA | 4 | 4 | 285.00 | $3,291.75 | $938,150.00 |
| | | | EA | 5 | 1 | 13.00 | $10,000.00 | $130,000.00 |
| | | | EA | 7 | 1 | 4.00 | $2,000.00 | $8,000.00 |
| | | | EA | 8 | 1 | 11.00 | $6,500.00 | $71,500.00 |
| | | | EA | 11 | 2 | 307.00 | $2,033.88 | $624,400.00 |
| | | **Unit Sub Total** | **EA** | | **13** | **1,298.00** | **$3,671.88** | **$4,766,105.00** |
| | **Item Code 500050** | **Total No. of Proj.** | | | **13** | | **Total Amount** | **$4,766,105.00** |
| **500060** | TIEDOWN ANCHOR | | EA | 11 | 2 | 16.00 | $7,050.00 | $112,800.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **16.00** | **$7,050.00** | **$112,800.00** |
| | **Item Code 500060** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$112,800.00** |
| **510000** | SEAL COURSE CONCRETE | | M3 | 1 | 1 | 233.00 | $1,000.00 | $233,000.00 |
| | | | M3 | 3 | 1 | 590.00 | $400.00 | $236,000.00 |
| | | | M3 | 4 | 1 | 110.00 | $500.00 | $55,000.00 |
| | | | M3 | 9 | 1 | 252.00 | $1,200.00 | $302,400.00 |
| | | **Unit Sub Total** | **M3** | | **4** | **1,185.00** | **$697.38** | **$826,400.00** |
| | **Item Code 510000** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$826,400.00** |
| **510050** | STRUCTURAL CONCRETE | | CY | 2 | 1 | 36.00 | $1,400.00 | $50,400.00 |
| | | | CY | 3 | 1 | 50.00 | $550.00 | $27,500.00 |
| | | **Unit Sub Total** | **CY** | | **2** | **86.00** | **$905.81** | **$77,900.00** |
| **510050** | STRUCTURAL CONCRETE | | M3 | 4 | 1 | 19.00 | $2,000.00 | $38,000.00 |
| | | | M3 | 11 | 2 | 95.00 | $789.47 | $75,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M3** | | **3** | **114.00** | **$991.23** | **$113,000.00** |
| | **Item Code 510050** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$190,900.00** |
| **510051** | STRUCTURAL CONCRETE, BRIDGE FOOTING | | CY | 4 | 1 | 69.00 | $900.00 | $62,100.00 |
| | | | CY | 8 | 1 | 440.00 | $600.00 | $264,000.00 |
| | | | CY | 12 | 1 | 112.00 | $230.00 | $25,760.00 |
| | | **Unit Sub Total** | **CY** | | **3** | **621.00** | **$566.60** | **$351,860.00** |
| **510051** | STRUCTURAL CONCRETE, BRIDGE FOOTING | | M3 | 1 | 3 | 270.00 | $774.07 | $209,000.00 |
| | | | M3 | 2 | 1 | 220.00 | $700.00 | $154,000.00 |
| | | | M3 | 3 | 3 | 2,508.00 | $549.33 | $1,377,710.00 |
| | | | M3 | 4 | 3 | 289.00 | $771.85 | $223,066.00 |
| | | | M3 | 5 | 1 | 890.00 | $515.00 | $458,350.00 |
| | | | M3 | 7 | 5 | 1,032.00 | $602.13 | $621,400.00 |
| | | | M3 | 8 | 1 | 1,143.00 | $200.00 | $228,600.00 |
| | | | M3 | 9 | 1 | 112.00 | $1,500.00 | $168,000.00 |
| | | | M3 | 10 | 2 | 935.00 | $425.76 | $398,088.00 |
| | | | M3 | 11 | 9 | 6,870.00 | $355.96 | $2,445,460.00 |
| | | **Unit Sub Total** | **M3** | | **29** | **14,269.00** | **$440.37** | **$6,283,674.00** |
| | **Item Code 510051** | **Total No. of Proj.** | | | **32** | | **Total Amount** | **$6,635,534.00** |
| **510053** | STRUCTURAL CONCRETE, BRIDGE | | CY | 1 | 1 | 19.00 | $500.00 | $9,500.00 |
| | | | CY | 2 | 1 | 132.00 | $520.00 | $68,640.00 |
| | | | CY | 3 | 5 | 445.70 | $1,023.13 | $456,009.00 |
| | | | CY | 4 | 5 | 1,192.50 | $924.00 | $1,101,875.00 |
| | | | CY | 7 | 4 | 853.00 | $1,122.52 | $957,510.00 |
| | | | CY | 8 | 1 | 6,680.00 | $1,200.00 | $8,016,000.00 |
| | | | CY | 10 | 6 | 119.50 | $1,669.12 | $199,460.00 |
| | | | CY | 11 | 2 | 19.00 | $2,884.21 | $54,800.00 |
| | | | CY | 12 | 2 | 979.00 | $627.07 | $613,900.00 |
| | | **Unit Sub Total** | **CY** | | **27** | **10,439.70** | **$1,099.43** | **$11,477,694.00** |
| **510053** | STRUCTURAL CONCRETE, BRIDGE | | M3 | 1 | 3 | 7,725.00 | $938.81 | $7,252,325.00 |
| | | | M3 | 2 | 5 | 22,778.00 | $589.88 | $13,436,250.00 |
| | | | M3 | 3 | 4 | 16,509.00 | $867.00 | $14,313,237.00 |
| | | | M3 | 4 | 5 | 2,910.00 | $1,218.67 | $3,546,324.00 |
| | | | M3 | 5 | 2 | 5,039.00 | $915.44 | $4,612,903.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **510053** | STRUCTURAL CONCRETE, BRIDGE | M3 | 6 | 1 | 245.00 | $1,300.00 | $318,500.00 |
| | | M3 | 7 | 8 | 25,135.00 | $1,033.38 | $25,974,077.00 |
| | | M3 | 8 | 1 | 1,091.00 | $1,000.00 | $1,091,000.00 |
| | | M3 | 9 | 1 | 760.00 | $1,700.00 | $1,292,000.00 |
| | | M3 | 10 | 2 | 4,790.00 | $589.41 | $2,823,264.00 |
| | | M3 | 11 | 9 | 48,121.00 | $794.20 | $38,217,860.00 |
| | **Unit Sub Total** | **M3** | | **41** | **135,103.00** | **$835.49** | **$112,877,740.00** |
| | **Item Code 510053 Total No. of Proj.** | | | **68** | | **Total Amount** | **$124,355,434.00** |
| **510060** | STRUCTURAL CONCRETE, RETAINING WALL | CY | 4 | 1 | 45.00 | $750.00 | $33,750.00 |
| | | CY | 7 | 1 | 53.00 | $630.00 | $33,390.00 |
| | | CY | 8 | 1 | 528.50 | $600.00 | $317,100.00 |
| | | CY | 12 | 2 | 4,077.00 | $328.97 | $1,341,195.00 |
| | **Unit Sub Total** | **CY** | | **5** | **4,703.50** | **$366.84** | **$1,725,435.00** |
| **510060** | STRUCTURAL CONCRETE, RETAINING WALL | M3 | 1 | 2 | 259.00 | $956.90 | $247,836.00 |
| | | M3 | 2 | 1 | 135.00 | $800.00 | $108,000.00 |
| | | M3 | 3 | 3 | 3,295.00 | $747.45 | $2,462,850.00 |
| | | M3 | 4 | 7 | 12,280.00 | $581.77 | $7,144,159.00 |
| | | M3 | 5 | 5 | 2,989.00 | $810.50 | $2,422,588.00 |
| | | M3 | 7 | 7 | 14,068.40 | $613.18 | $8,626,497.85 |
| | | M3 | 8 | 1 | 558.00 | $595.00 | $332,010.00 |
| | | M3 | 10 | 2 | 1,520.00 | $1,132.24 | $1,721,000.00 |
| | | M3 | 11 | 8 | 35,668.00 | $429.18 | $15,308,090.00 |
| | **Unit Sub Total** | **M3** | | **36** | **70,772.40** | **$542.20** | **$38,373,030.85** |
| | **Item Code 510060 Total No. of Proj.** | | | **41** | | **Total Amount** | **$40,098,465.85** |
| **510061** | STRUCTURAL CONCRETE, SOUND WALL | M3 | 7 | 1 | 504.00 | $800.00 | $403,200.00 |
| | **Unit Sub Total** | **M3** | | **1** | **504.00** | **$800.00** | **$403,200.00** |
| | **Item Code 510061 Total No. of Proj.** | | | **1** | | **Total Amount** | **$403,200.00** |
| **510065** | STRUCTURAL CONCRETE, PIER COLUMN | CY | 8 | 1 | 1,030.00 | $600.00 | $618,000.00 |
| | **Unit Sub Total** | **CY** | | **1** | **1,030.00** | **$600.00** | **$618,000.00** |
| | **Item Code 510065 Total No. of Proj.** | | | **1** | | **Total Amount** | **$618,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **510072** | STRUCTURAL CONCRETE, BARRIER SLAB | CY | 6 | 1 | 250.00 | $840.00 | $210,000.00 |
| | | CY | 7 | 1 | 25.00 | $872.00 | $21,800.00 |
| | | CY | 8 | 1 | 72.00 | $650.00 | $46,800.00 |
| | **Unit Sub Total** | **CY** | | **3** | **347.00** | **$802.88** | **$278,600.00** |
| **510072** | STRUCTURAL CONCRETE, BARRIER SLAB | M3 | 1 | 1 | 25.00 | $940.00 | $23,500.00 |
| | | M3 | 3 | 1 | 47.00 | $1,400.00 | $65,800.00 |
| | | M3 | 4 | 1 | 110.00 | $800.00 | $88,000.00 |
| | | M3 | 5 | 1 | 225.00 | $420.00 | $94,500.00 |
| | | M3 | 11 | 5 | 2,822.00 | $478.79 | $1,351,150.00 |
| | **Unit Sub Total** | **M3** | | **9** | **3,229.00** | **$502.62** | **$1,622,950.00** |
| | **Item Code 510072 Total No. of Proj.** | | | **12** | | **Total Amount** | **$1,901,550.00** |
| **510085** | STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ) | CY | 7 | 1 | 36.00 | $1,000.00 | $36,000.00 |
| | **Unit Sub Total** | **CY** | | **1** | **36.00** | **$1,000.00** | **$36,000.00** |
| **510085** | STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ) | M3 | 1 | 1 | 24.00 | $850.00 | $20,400.00 |
| | | M3 | 3 | 1 | 72.00 | $1,300.00 | $93,600.00 |
| | | M3 | 7 | 2 | 17.20 | $1,967.44 | $33,840.00 |
| | | M3 | 11 | 2 | 117.00 | $1,320.51 | $154,500.00 |
| | **Unit Sub Total** | **M3** | | **6** | **230.20** | **$1,313.38** | **$302,340.00** |
| | **Item Code 510085 Total No. of Proj.** | | | **7** | | **Total Amount** | **$338,340.00** |
| **510086** | STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N) | CY | 4 | 1 | 80.00 | $300.00 | $24,000.00 |
| | | CY | 8 | 1 | 365.00 | $800.00 | $292,000.00 |
| | | CY | 12 | 1 | 90.00 | $605.00 | $54,450.00 |
| | **Unit Sub Total** | **CY** | | **3** | **535.00** | **$692.43** | **$370,450.00** |
| **510086** | STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N) | M3 | 1 | 1 | 188.00 | $1,250.00 | $235,000.00 |
| | | M3 | 2 | 3 | 777.00 | $714.93 | $555,500.00 |
| | | M3 | 3 | 2 | 1,102.00 | $811.00 | $893,725.00 |
| | | M3 | 4 | 2 | 151.00 | $1,831.38 | $276,538.00 |
| | | M3 | 5 | 1 | 590.00 | $1,040.00 | $613,600.00 |
| | | M3 | 7 | 1 | 669.00 | $400.00 | $267,600.00 |
| | | M3 | 8 | 1 | 187.00 | $900.00 | $168,300.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **510086** | STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N) | M3 | 9 | 1 | 63.00 | $1,200.00 | $75,600.00 |
| | | M3 | 10 | 2 | 405.00 | $766.80 | $310,552.00 |
| | | M3 | 11 | 7 | 2,374.00 | $849.79 | $2,017,400.00 |
| | **Unit Sub Total** | **M3** | | **21** | **6,506.00** | **$832.13** | **$5,413,815.00** |
| | **Item Code 510086 Total No. of Proj.** | | | **24** | | **Total Amount** | **$5,784,265.00** |
| **510087** | STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R) | CY | 2 | 1 | 87.00 | $1,400.00 | $121,800.00 |
| | | CY | 3 | 6 | 2,042.00 | $1,017.91 | $2,078,582.00 |
| | | CY | 4 | 4 | 2,219.00 | $980.43 | $2,175,575.00 |
| | | CY | 6 | 1 | 314.00 | $950.00 | $298,300.00 |
| | | CY | 7 | 1 | 319.00 | $1,100.00 | $350,900.00 |
| | | CY | 10 | 2 | 241.00 | $1,676.66 | $404,076.00 |
| | | CY | 11 | 2 | 400.00 | $1,940.06 | $776,025.00 |
| | | CY | 12 | 3 | 633.00 | $1,035.86 | $655,700.00 |
| | **Unit Sub Total** | **CY** | | **20** | **6,255.00** | **$1,096.88** | **$6,860,958.00** |
| **510087** | STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R) | M3 | 3 | 2 | 418.00 | $1,388.28 | $580,300.00 |
| | | M3 | 4 | 2 | 273.00 | $1,513.89 | $413,292.00 |
| | | M3 | 7 | 4 | 2,602.00 | $1,502.16 | $3,908,620.00 |
| | | M3 | 8 | 1 | 1,259.00 | $875.00 | $1,101,625.00 |
| | | M3 | 11 | 3 | 418.00 | $1,100.00 | $459,800.00 |
| | | M3 | 12 | 1 | 345.00 | $1,560.00 | $538,200.00 |
| | **Unit Sub Total** | **M3** | | **13** | **5,315.00** | **$1,317.37** | **$7,001,837.00** |
| | **Item Code 510087 Total No. of Proj.** | | | **33** | | **Total Amount** | **$13,862,795.00** |
| **510088** | STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N MODIFIED) | M3 | 11 | 3 | 623.00 | $992.22 | $618,150.00 |
| | **Unit Sub Total** | **M3** | | **3** | **623.00** | **$992.22** | **$618,150.00** |
| | **Item Code 510088 Total No. of Proj.** | | | **3** | | **Total Amount** | **$618,150.00** |
| **510126** | CLASS 2 CONCRETE (MINOR STRUCTURE) | M3 | 4 | 1 | 348.00 | $1,290.00 | $448,920.00 |
| | | M3 | 6 | 1 | 2.60 | $1,150.00 | $2,990.00 |
| | | M3 | 11 | 6 | 118.00 | $1,715.93 | $202,480.00 |
| | **Unit Sub Total** | **M3** | | **8** | **468.60** | **$1,396.48** | **$654,390.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 510126 Total No. of Proj.** | | | **8** | | **Total Amount** | **$654,390.00** |
| **510129** | CLASS 2 CONCRETE (BOX CULVERT) | M3 | 4 | 4 | 615.00 | $1,329.76 | $817,800.00 |
| | | M3 | 5 | 1 | 252.00 | $1,230.00 | $309,960.00 |
| | **Unit Sub Total** | **M3** | | **5** | **867.00** | **$1,300.76** | **$1,127,760.00** |
| | **Item Code 510129 Total No. of Proj.** | | | **5** | | **Total Amount** | **$1,127,760.00** |
| **510133** | CLASS 2 CONCRETE (RETAINING WALL) | CY | 7 | 1 | 146.00 | $630.00 | $91,980.00 |
| | **Unit Sub Total** | **CY** | | **1** | **146.00** | **$630.00** | **$91,980.00** |
| **510133** | CLASS 2 CONCRETE (RETAINING WALL) | M3 | 1 | 1 | 14.00 | $1,470.00 | $20,580.00 |
| | | M3 | 5 | 1 | 1,437.00 | $620.00 | $890,940.00 |
| | | M3 | 9 | 2 | 775.40 | $557.73 | $432,460.00 |
| | **Unit Sub Total** | **M3** | | **4** | **2,226.40** | **$603.66** | **$1,343,980.00** |
| | **Item Code 510133 Total No. of Proj.** | | | **5** | | **Total Amount** | **$1,435,960.00** |
| **510135** | CLASS 2 CONCRETE (HEADWALL) | M3 | 4 | 3 | 20.00 | $2,727.50 | $54,550.00 |
| | | M3 | 6 | 1 | 43.00 | $900.00 | $38,700.00 |
| | | M3 | 9 | 1 | 14.00 | $2,100.00 | $29,400.00 |
| | | M3 | 11 | 1 | 2.60 | $1,500.00 | $3,900.00 |
| | **Unit Sub Total** | **M3** | | **6** | **79.60** | **$1,589.82** | **$126,550.00** |
| | **Item Code 510135 Total No. of Proj.** | | | **6** | | **Total Amount** | **$126,550.00** |
| **510138** | CLASS 2 CONCRETE (WINGWALLS) | CY | 6 | 2 | 75.00 | $1,000.00 | $75,000.00 |
| | **Unit Sub Total** | **CY** | | **2** | **75.00** | **$1,000.00** | **$75,000.00** |
| **510138** | CLASS 2 CONCRETE (WINGWALLS) | M3 | 4 | 2 | 16.20 | $1,617.28 | $26,200.00 |
| | | M3 | 5 | 1 | 30.00 | $1,000.00 | $30,000.00 |
| | | M3 | 6 | 2 | 77.00 | $1,850.65 | $142,500.00 |
| | | M3 | 9 | 3 | 277.60 | $1,023.05 | $284,000.00 |
| | **Unit Sub Total** | **M3** | | **8** | **400.80** | **$1,204.34** | **$482,700.00** |
| | **Item Code 510138 Total No. of Proj.** | | | **10** | | **Total Amount** | **$557,700.00** |
| **510217** | CLASS 3 CONCRETE | M3 | 4 | 1 | 1.50 | $2,000.00 | $3,000.00 |
| | **Unit Sub Total** | **M3** | | **1** | **1.50** | **$2,000.00** | **$3,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 510217 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,000.00** |
| **510220** | CLASS 3 CONCRETE (BACKFILL) | CY | 8 | 1 | 125.00 | $250.00 | $31,250.00 |
| | **Unit Sub Total** | **CY** | | **1** | **125.00** | **$250.00** | **$31,250.00** |
| **510220** | CLASS 3 CONCRETE (BACKFILL) | M3 | 1 | 2 | 230.00 | $299.73 | $68,938.00 |
| | | M3 | 4 | 1 | 460.00 | $235.00 | $108,100.00 |
| | | M3 | 11 | 1 | 189.00 | $150.00 | $28,350.00 |
| | **Unit Sub Total** | **M3** | | **4** | **879.00** | **$233.66** | **$205,388.00** |
| | **Item Code 510220 Total No. of Proj.** | | | **5** | | **Total Amount** | **$236,638.00** |
| **510314** | CLASS 4 CONCRETE (BACKFILL) | CY | 3 | 2 | 73.50 | $170.14 | $12,505.00 |
| | | CY | 12 | 1 | 5.00 | $450.00 | $2,250.00 |
| | **Unit Sub Total** | **CY** | | **3** | **78.50** | **$187.96** | **$14,755.00** |
| **510314** | CLASS 4 CONCRETE (BACKFILL) | M3 | 3 | 1 | 130.00 | $150.00 | $19,500.00 |
| | | M3 | 5 | 1 | 5.00 | $390.00 | $1,950.00 |
| | | M3 | 10 | 1 | 9.00 | $200.00 | $1,800.00 |
| | | M3 | 11 | 4 | 657.00 | $188.19 | $123,640.00 |
| | **Unit Sub Total** | **M3** | | **7** | **801.00** | **$183.38** | **$146,890.00** |
| | **Item Code 510314 Total No. of Proj.** | | | **10** | | **Total Amount** | **$161,645.00** |
| **510408** | CLASS 1 CONCRETE (RETAINING WALL) | CY | 2 | 1 | 33.00 | $1,815.00 | $59,895.00 |
| | **Unit Sub Total** | **CY** | | **1** | **33.00** | **$1,815.00** | **$59,895.00** |
| **510408** | CLASS 1 CONCRETE (RETAINING WALL) | M3 | 2 | 1 | 2,184.00 | $875.00 | $1,911,000.00 |
| | | M3 | 6 | 1 | 35.00 | $1,400.00 | $49,000.00 |
| | | M3 | 11 | 4 | 8,411.00 | $512.02 | $4,306,625.00 |
| | **Unit Sub Total** | **M3** | | **6** | **10,630.00** | **$589.52** | **$6,266,625.00** |
| | **Item Code 510408 Total No. of Proj.** | | | **7** | | **Total Amount** | **$6,326,520.00** |
| **510409** | CLASS 1 CONCRETE (MINOR STRUCTURE) | CY | 3 | 2 | 894.00 | $1,621.36 | $1,449,500.00 |
| | **Unit Sub Total** | **CY** | | **2** | **894.00** | **$1,621.36** | **$1,449,500.00** |
| **510409** | CLASS 1 CONCRETE (MINOR STRUCTURE) | M3 | 9 | 1 | 0.70 | $8,000.00 | $5,600.00 |
| | **Unit Sub Total** | **M3** | | **1** | **0.70** | **$8,000.00** | **$5,600.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 510409 Total No. of Proj.** | | | **3** | | **Total Amount** | **$1,455,100.00** |
| **510410** | CLASS 1 CONCRETE (STRUCTURE) | M3 | 7 | 1 | 4.00 | $2,200.00 | $8,800.00 |
| | | M3 | 8 | 1 | 0.50 | $4,200.00 | $2,100.00 |
| | **Unit Sub Total** | **M3** | | **2** | **4.50** | **$2,422.22** | **$10,900.00** |
| | **Item Code 510410 Total No. of Proj.** | | | **2** | | **Total Amount** | **$10,900.00** |
| **510413** | CLASS 1 CONCRETE (BOX CULVERT) | CY | 6 | 1 | 80.00 | $1,000.00 | $80,000.00 |
| | **Unit Sub Total** | **CY** | | **1** | **80.00** | **$1,000.00** | **$80,000.00** |
| **510413** | CLASS 1 CONCRETE (BOX CULVERT) | M3 | 1 | 1 | 16.80 | $2,700.00 | $45,360.00 |
| | | M3 | 2 | 1 | 300.00 | $1,320.00 | $396,000.00 |
| | | M3 | 3 | 1 | 1,340.00 | $1,055.00 | $1,413,700.00 |
| | | M3 | 4 | 1 | 195.00 | $1,150.00 | $224,250.00 |
| | | M3 | 5 | 3 | 901.10 | $760.33 | $685,130.00 |
| | | M3 | 6 | 2 | 325.00 | $1,111.77 | $361,325.00 |
| | | M3 | 7 | 2 | 19.10 | $2,532.98 | $48,380.00 |
| | | M3 | 9 | 2 | 322.80 | $815.78 | $263,335.00 |
| | | M3 | 11 | 3 | 6,087.00 | $442.81 | $2,695,410.00 |
| | **Unit Sub Total** | **M3** | | **16** | **9,506.80** | **$645.11** | **$6,132,890.00** |
| | **Item Code 510413 Total No. of Proj.** | | | **17** | | **Total Amount** | **$6,212,890.00** |
| **510414** | CLASS 1 CONCRETE (BACKFILL) | CY | 12 | 1 | 21.00 | $138.00 | $2,898.00 |
| | **Unit Sub Total** | **CY** | | **1** | **21.00** | **$138.00** | **$2,898.00** |
| **510414** | CLASS 1 CONCRETE (BACKFILL) | M3 | 11 | 3 | 162.00 | $280.25 | $45,400.00 |
| | **Unit Sub Total** | **M3** | | **3** | **162.00** | **$280.25** | **$45,400.00** |
| | **Item Code 510414 Total No. of Proj.** | | | **4** | | **Total Amount** | **$48,298.00** |
| **510501** | MINOR CONCRETE | CY | 7 | 1 | 6.00 | $1,120.00 | $6,720.00 |
| | | CY | 11 | 1 | 21.00 | $1,000.00 | $21,000.00 |
| | **Unit Sub Total** | **CY** | | **2** | **27.00** | **$1,026.67** | **$27,720.00** |
| **510501** | MINOR CONCRETE | M3 | 2 | 1 | 9.00 | $2,249.79 | $20,248.11 |
| | | M3 | 11 | 1 | 6.00 | $888.00 | $5,328.00 |
| | **Unit Sub Total** | **M3** | | **2** | **15.00** | **$1,705.07** | **$25,576.11** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 510501 Total No. of Proj.** | | | **4** | | **Total Amount** | **$53,296.11** |
| **510502** | MINOR CONCRETE (MINOR STRUCTURE) | CY | 1 | 8 | 24.70 | $1,839.47 | $45,435.00 |
| | | CY | 2 | 10 | 161.50 | $1,326.27 | $214,193.00 |
| | | CY | 3 | 12 | 763.80 | $1,756.60 | $1,341,687.80 |
| | | CY | 4 | 4 | 45.10 | $1,189.80 | $53,660.00 |
| | | CY | 5 | 5 | 114.70 | $2,277.11 | $261,185.00 |
| | | CY | 6 | 3 | 10.90 | $1,856.88 | $20,240.00 |
| | | CY | 7 | 5 | 393.40 | $1,062.56 | $418,011.40 |
| | | CY | 8 | 6 | 127.80 | $1,913.85 | $244,590.00 |
| | | CY | 9 | 1 | 25.00 | $1,361.00 | $34,025.00 |
| | | CY | 11 | 7 | 289.40 | $2,268.73 | $656,570.00 |
| | | CY | 12 | 5 | 56.10 | $2,154.19 | $120,850.00 |
| | **Unit Sub Total** | **CY** | | **66** | **2,012.40** | **$1,694.72** | **$3,410,447.20** |
| **510502** | MINOR CONCRETE (MINOR STRUCTURE) | M3 | 1 | 6 | 213.90 | $1,727.02 | $369,409.00 |
| | | M3 | 2 | 5 | 202.80 | $1,256.97 | $254,913.34 |
| | | M3 | 3 | 8 | 1,066.00 | $1,357.36 | $1,446,950.19 |
| | | M3 | 4 | 16 | 1,085.40 | $1,234.85 | $1,340,310.87 |
| | | M3 | 5 | 13 | 690.80 | $2,299.47 | $1,588,471.60 |
| | | M3 | 6 | 7 | 371.00 | $1,092.08 | $405,160.00 |
| | | M3 | 7 | 18 | 1,412.40 | $2,728.70 | $3,854,010.00 |
| | | M3 | 8 | 6 | 616.00 | $1,849.89 | $1,139,530.00 |
| | | M3 | 9 | 2 | 91.00 | $2,756.92 | $250,880.00 |
| | | M3 | 10 | 7 | 195.40 | $1,206.93 | $235,835.00 |
| | | M3 | 11 | 11 | 2,048.50 | $1,837.12 | $3,763,339.87 |
| | | M3 | 12 | 3 | 115.70 | $1,301.73 | $150,610.00 |
| | **Unit Sub Total** | **M3** | | **102** | **8,108.90** | **$1,825.08** | **$14,799,419.87** |
| | **Item Code 510502 Total No. of Proj.** | | | **168** | | **Total Amount** | **$18,209,867.07** |
| **510504** | MINOR CONCRETE (PIPE ENCASEMENT) | CY | 7 | 1 | 90.00 | $200.00 | $18,000.00 |
| | **Unit Sub Total** | **CY** | | **1** | **90.00** | **$200.00** | **$18,000.00** |
| | **Item Code 510504 Total No. of Proj.** | | | **1** | | **Total Amount** | **$18,000.00** |
| **510510** | MINOR CONCRETE (INVERT PAVING) | CY | 3 | 2 | 40.00 | $2,747.50 | $109,900.00 |
| | **Unit Sub Total** | **CY** | | **2** | **40.00** | **$2,747.50** | **$109,900.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | **Item Code 510510** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$109,900.00** |
| **510524** | MINOR CONCRETE (SOUND WALL) | | M2 | 11 | 1 | 60.00 | $1,240.00 | $74,400.00 |
| | | **Unit Sub Total** | **M2** | | **1** | **60.00** | **$1,240.00** | **$74,400.00** |
| **510524** | MINOR CONCRETE (SOUND WALL) | | M3 | 4 | 1 | 29.00 | $800.00 | $23,200.00 |
| | | | M3 | 5 | 1 | 700.00 | $650.00 | $455,000.00 |
| | | | M3 | 7 | 1 | 371.00 | $500.00 | $185,500.00 |
| | | | M3 | 10 | 2 | 1,010.00 | $644.87 | $651,318.00 |
| | | | M3 | 11 | 5 | 1,573.00 | $696.19 | $1,095,109.52 |
| | | **Unit Sub Total** | **M3** | | **10** | **3,683.00** | **$654.39** | **$2,410,127.52** |
| | **Item Code 510524** | **Total No. of Proj.** | | | **11** | | **Total Amount** | **$2,484,527.52** |
| **510526** | MINOR CONCRETE (BACKFILL) | | CY | 1 | 1 | 1.30 | $400.00 | $520.00 |
| | | | CY | 2 | 3 | 18.40 | $336.30 | $6,188.00 |
| | | | CY | 3 | 2 | 277.00 | $190.25 | $52,699.00 |
| | | | CY | 4 | 1 | 8.00 | $300.00 | $2,400.00 |
| | | | CY | 5 | 1 | 2.50 | $1,100.00 | $2,750.00 |
| | | | CY | 9 | 1 | 190.00 | $300.00 | $57,000.00 |
| | | | CY | 11 | 1 | 180.00 | $185.00 | $33,300.00 |
| | | **Unit Sub Total** | **CY** | | **10** | **677.20** | **$228.67** | **$154,857.00** |
| **510526** | MINOR CONCRETE (BACKFILL) | | M3 | 1 | 2 | 132.00 | $239.09 | $31,560.00 |
| | | | M3 | 4 | 5 | 640.00 | $227.62 | $145,675.00 |
| | | | M3 | 5 | 2 | 142.00 | $266.90 | $37,900.00 |
| | | | M3 | 6 | 3 | 712.00 | $152.11 | $108,300.00 |
| | | | M3 | 7 | 2 | 213.00 | $199.30 | $42,450.00 |
| | | | M3 | 8 | 1 | 68.00 | $225.00 | $15,300.00 |
| | | | M3 | 9 | 4 | 415.00 | $274.11 | $113,757.00 |
| | | | M3 | 10 | 2 | 49.00 | $294.43 | $14,427.00 |
| | | | M3 | 11 | 1 | 63.00 | $280.00 | $17,640.00 |
| | | **Unit Sub Total** | **M3** | | **22** | **2,434.00** | **$216.52** | **$527,009.00** |
| | **Item Code 510526** | **Total No. of Proj.** | | | **32** | | **Total Amount** | **$681,866.00** |
| **510535** | MINOR CONCRETE (HEADWALL) | | CY | 3 | 2 | 2.20 | $1,954.55 | $4,300.00 |
| | | **Unit Sub Total** | **CY** | | **2** | **2.20** | **$1,954.55** | **$4,300.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | **Item Code 510535** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$4,300.00** |
| **510700** | MINOR CONCRETE (PILE CAP) | | M3 | 3 | 1 | 318.00 | $1,500.00 | $477,000.00 |
| | | **Unit Sub Total** | **M3** | | **1** | **318.00** | **$1,500.00** | **$477,000.00** |
| | **Item Code 510700** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$477,000.00** |
| **510800** | PAVING NOTCH EXTENSION | | CY | 2 | 1 | 2.20 | $7,000.00 | $15,400.00 |
| | | | CY | 3 | 3 | 32.80 | $4,832.93 | $158,520.00 |
| | | | CY | 4 | 2 | 53.00 | $3,787.17 | $200,720.00 |
| | | | CY | 6 | 1 | 4.70 | $4,900.00 | $23,030.00 |
| | | | CY | 7 | 1 | 8.00 | $4,800.00 | $38,400.00 |
| | | | CY | 10 | 2 | 7.70 | $3,066.23 | $23,610.00 |
| | | | CY | 11 | 2 | 2.20 | $7,541.82 | $16,592.00 |
| | | | CY | 12 | 1 | 1.00 | $1,400.00 | $1,400.00 |
| | | **Unit Sub Total** | **CY** | | **13** | **111.60** | **$4,280.22** | **$477,672.00** |
| **510800** | PAVING NOTCH EXTENSION | | M3 | 3 | 1 | 4.50 | $5,500.00 | $24,750.00 |
| | | | M3 | 4 | 2 | 7.40 | $7,147.30 | $52,890.00 |
| | | | M3 | 7 | 4 | 40.40 | $13,422.30 | $542,261.00 |
| | | | M3 | 8 | 2 | 22.10 | $2,558.60 | $56,545.00 |
| | | | M3 | 11 | 2 | 4.90 | $2,383.67 | $11,680.00 |
| | | **Unit Sub Total** | **M3** | | **11** | **79.30** | **$8,677.50** | **$688,126.00** |
| | **Item Code 510800** | **Total No. of Proj.** | | | **24** | | **Total Amount** | **$1,165,798.00** |
| **510805** | DIAPHRAGM BOLSTER | | EA | 11 | 1 | 32.00 | $1,200.00 | $38,400.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **32.00** | **$1,200.00** | **$38,400.00** |
| | **Item Code 510805** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$38,400.00** |
| **511001** | LIGHTWEIGHT CONCRETE | | M3 | 4 | 1 | 43.00 | $950.00 | $40,850.00 |
| | | **Unit Sub Total** | **M3** | | **1** | **43.00** | **$950.00** | **$40,850.00** |
| | **Item Code 511001** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$40,850.00** |
| **511035** | ARCHITECTURAL TREATMENT | | M2 | 2 | 1 | 1,177.00 | $510.00 | $600,270.00 |
| | | | M2 | 7 | 1 | 300.00 | $200.00 | $60,000.00 |
| | | | M2 | 11 | 1 | 80.00 | $650.00 | $52,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M2** | | **3** | **1,557.00** | **$457.46** | **$712,270.00** |
| | **Item Code 511035** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$712,270.00** |
| **511036** | ARCHITECTURAL SURFACE (BARRIER) | | M2 | 11 | 5 | 4,735.00 | $30.22 | $143,113.00 |
| | | **Unit Sub Total** | **M2** | | **5** | **4,735.00** | **$30.22** | **$143,113.00** |
| | **Item Code 511036** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$143,113.00** |
| **511045** | EXPOSED AGGREGATE FINISH | | M2 | 11 | 1 | 220.00 | $155.00 | $34,100.00 |
| | | **Unit Sub Total** | **M2** | | **1** | **220.00** | **$155.00** | **$34,100.00** |
| | **Item Code 511045** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$34,100.00** |
| **511046** | HEAVY BLAST TEXTURE | | M2 | 11 | 1 | 3,531.00 | $10.00 | $35,310.00 |
| | | **Unit Sub Total** | **M2** | | **1** | **3,531.00** | **$10.00** | **$35,310.00** |
| | **Item Code 511046** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$35,310.00** |
| **511047** | ANTI-GRAFFITI COATING | | M2 | 2 | 1 | 1,320.00 | $35.00 | $46,200.00 |
| | | | M2 | 5 | 1 | 1,660.00 | $11.00 | $18,260.00 |
| | | **Unit Sub Total** | **M2** | | **2** | **2,980.00** | **$21.63** | **$64,460.00** |
| | **Item Code 511047** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$64,460.00** |
| **511064** | FRACTURED RIB TEXTURE | | M2 | 1 | 1 | 52.00 | $150.00 | $7,800.00 |
| | | | M2 | 4 | 3 | 1,677.00 | $82.07 | $137,634.00 |
| | | | M2 | 8 | 1 | 1,267.00 | $53.00 | $67,151.00 |
| | | | M2 | 10 | 1 | 2,520.00 | $40.00 | $100,800.00 |
| | | | M2 | 11 | 2 | 990.00 | $110.61 | $109,500.00 |
| | | **Unit Sub Total** | **M2** | | **8** | **6,506.00** | **$65.00** | **$422,885.00** |
| | **Item Code 511064** | **Total No. of Proj.** | | | **8** | | **Total Amount** | **$422,885.00** |
| **511071** | RIPPED TEXTURE (ROPE) | | M2 | 11 | 1 | 110.00 | $44.00 | $4,840.00 |
| | | **Unit Sub Total** | **M2** | | **1** | **110.00** | **$44.00** | **$4,840.00** |
| | **Item Code 511071** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,840.00** |
| **511106** | DRILL AND BOND DOWEL | | LF | 2 | 2 | 1,190.00 | $39.88 | $47,455.00 |
| | | | LF | 3 | 2 | 112.00 | $62.50 | $7,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **511106** | DRILL AND BOND DOWEL | LF | 4 | 2 | 180.00 | $236.67 | $42,600.00 |
| | | LF | 7 | 1 | 60.00 | $15.00 | $900.00 |
| | | LF | 8 | 1 | 1,190.00 | $50.00 | $59,500.00 |
| | | LF | 10 | 1 | 520.00 | $32.50 | $16,900.00 |
| | | LF | 11 | 1 | 8.00 | $60.00 | $480.00 |
| | | LF | 12 | 1 | 305.00 | $10.00 | $3,050.00 |
| | **Unit Sub Total** | **LF** | | **11** | **3,565.00** | **$49.90** | **$177,885.00** |
| **511106** | DRILL AND BOND DOWEL | M | 1 | 1 | 213.00 | $90.00 | $19,170.00 |
| | | M | 2 | 2 | 131.00 | $131.22 | $17,190.00 |
| | | M | 3 | 1 | 12.00 | $180.00 | $2,160.00 |
| | | M | 4 | 3 | 1,034.00 | $59.14 | $61,154.50 |
| | | M | 5 | 1 | 9.00 | $626.00 | $5,634.00 |
| | | M | 6 | 1 | 290.00 | $70.00 | $20,300.00 |
| | | M | 7 | 8 | 3,385.00 | $57.37 | $194,188.00 |
| | | M | 8 | 1 | 336.00 | $69.00 | $23,184.00 |
| | | M | 11 | 5 | 944.00 | $85.52 | $80,732.00 |
| | **Unit Sub Total** | **M** | | **23** | **6,354.00** | **$66.68** | **$423,712.50** |
| | **Item Code 511106** | **Total No. of Proj.** | | **34** | | **Total Amount** | **$601,597.50** |
| **511109** | DRILL AND BOND DOWEL (EPOXY CARTRIDGE) | EA | 1 | 1 | 1,014.00 | $15.00 | $15,210.00 |
| | | EA | 3 | 1 | 106.00 | $20.00 | $2,120.00 |
| | | EA | 7 | 2 | 80.00 | $72.90 | $5,832.00 |
| | **Unit Sub Total** | **EA** | | **4** | **1,200.00** | **$19.30** | **$23,162.00** |
| | **Item Code 511109** | **Total No. of Proj.** | | **4** | | **Total Amount** | **$23,162.00** |
| **511110** | DRILL AND BOND DOWEL (CHEMICAL ADHESIVE) | EA | 4 | 1 | 36.00 | $100.00 | $3,600.00 |
| | | EA | 8 | 2 | 312.00 | $88.69 | $27,672.00 |
| | **Unit Sub Total** | **EA** | | **3** | **348.00** | **$89.86** | **$31,272.00** |
| | **Item Code 511110** | **Total No. of Proj.** | | **3** | | **Total Amount** | **$31,272.00** |
| **511115** | EPOXY ADHESIVE (BOND COAT) | GAL | 7 | 1 | 280.00 | $220.00 | $61,600.00 |
| | **Unit Sub Total** | **GAL** | | **1** | **280.00** | **$220.00** | **$61,600.00** |
| | **Item Code 511115** | **Total No. of Proj.** | | **1** | | **Total Amount** | **$61,600.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **511118** | CLEAN EXPANSION JOINT | LF | 1 | 1 | 1,117.00 | $17.00 | $18,989.00 |
| | | LF | 2 | 3 | 3,168.00 | $18.20 | $57,671.00 |
| | | LF | 3 | 5 | 4,133.00 | $26.61 | $109,993.00 |
| | | LF | 4 | 13 | 22,083.00 | $20.25 | $447,102.00 |
| | | LF | 5 | 1 | 82.00 | $50.00 | $4,100.00 |
| | | LF | 6 | 3 | 835.00 | $27.07 | $22,605.00 |
| | | LF | 7 | 13 | 29,388.00 | $16.15 | $474,617.50 |
| | | LF | 8 | 2 | 1,044.00 | $30.72 | $32,070.00 |
| | | LF | 10 | 7 | 5,508.00 | $15.94 | $87,775.00 |
| | | LF | 11 | 6 | 4,995.00 | $25.63 | $128,035.00 |
| | | LF | 12 | 1 | 7,338.00 | $27.00 | $198,126.00 |
| | **Unit Sub Total** | **LF** | | **55** | **79,691.00** | **$19.84** | **$1,581,083.50** |
| **511118** | CLEAN EXPANSION JOINT | M | 1 | 1 | 51.00 | $100.00 | $5,100.00 |
| | | M | 2 | 1 | 140.00 | $77.00 | $10,780.00 |
| | | M | 3 | 2 | 918.00 | $30.40 | $27,908.00 |
| | | M | 4 | 1 | 176.00 | $60.00 | $10,560.00 |
| | | M | 7 | 4 | 1,269.00 | $131.09 | $166,350.20 |
| | | M | 8 | 2 | 319.00 | $57.96 | $18,490.50 |
| | | M | 11 | 2 | 243.00 | $93.05 | $22,610.00 |
| | | M | 12 | 1 | 18.00 | $205.00 | $3,690.00 |
| | **Unit Sub Total** | **M** | | **14** | **3,134.00** | **$84.71** | **$265,488.70** |
| | **Item Code 511118** **Total No. of Proj.** | | | **69** | | **Total Amount** | **$1,846,572.20** |
| **511121** | PORTLAND CEMENT CONCRETE (PATCH) | CF | 7 | 1 | 550.00 | $22.00 | $12,100.00 |
| | **Unit Sub Total** | **CF** | | **1** | **550.00** | **$22.00** | **$12,100.00** |
| | **Item Code 511121** **Total No. of Proj.** | | | **1** | | **Total Amount** | **$12,100.00** |
| **511124** | RAPID SETTING CONCRETE (PATCH) | CF | 1 | 1 | 80.00 | $100.00 | $8,000.00 |
| | | CF | 2 | 1 | 142.00 | $120.00 | $17,040.00 |
| | | CF | 3 | 6 | 604.00 | $146.33 | $88,385.00 |
| | | CF | 4 | 9 | 7,096.00 | $75.74 | $537,460.00 |
| | | CF | 6 | 2 | 47.00 | $219.79 | $10,330.00 |
| | | CF | 7 | 6 | 2,258.00 | $79.73 | $180,034.00 |
| | | CF | 8 | 3 | 481.00 | $102.25 | $49,181.00 |
| | | CF | 10 | 7 | 755.00 | $92.52 | $69,849.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **511124** | RAPID SETTING CONCRETE (PATCH) | CF | 11 | 6 | 2,546.00 | $63.41 | $161,439.00 |
| | | CF | 12 | 3 | 937.30 | $86.17 | $80,767.00 |
| | **Unit Sub Total** | **CF** | | **44** | **14,946.30** | **$80.45** | **$1,202,485.00** |
| **511124** | RAPID SETTING CONCRETE (PATCH) | M3 | 3 | 1 | 1.00 | $3,100.00 | $3,100.00 |
| | | M3 | 4 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | | M3 | 7 | 1 | 13.00 | $920.00 | $11,960.00 |
| | | M3 | 8 | 1 | 47.00 | $1,175.00 | $55,225.00 |
| | **Unit Sub Total** | **M3** | | **4** | **62.00** | **$1,214.27** | **$75,285.00** |
| | **Item Code 511124 Total No. of Proj.** | | | **48** | | **Total Amount** | **$1,277,770.00** |
| **511130** | INJECT CRACK (EPOXY) | LF | 4 | 1 | 22.00 | $400.00 | $8,800.00 |
| | | LF | 10 | 1 | 70.00 | $50.00 | $3,500.00 |
| | | LF | 11 | 2 | 132.00 | $65.45 | $8,640.00 |
| | **Unit Sub Total** | **LF** | | **4** | **224.00** | **$93.48** | **$20,940.00** |
| | **Item Code 511130 Total No. of Proj.** | | | **4** | | **Total Amount** | **$20,940.00** |
| **512229** | FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (5 M - 10 M) | EA | 5 | 1 | 2.00 | $15,500.00 | $31,000.00 |
| | | EA | 8 | 1 | 6.00 | $9,800.00 | $58,800.00 |
| | **Unit Sub Total** | **EA** | | **2** | **8.00** | **$11,225.00** | **$89,800.00** |
| | **Item Code 512229 Total No. of Proj.** | | | **2** | | **Total Amount** | **$89,800.00** |
| **512231** | FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (15 M - 20 M) | EA | 5 | 1 | 1.00 | $24,800.00 | $24,800.00 |
| | | EA | 7 | 1 | 2.00 | $22,000.00 | $44,000.00 |
| | | EA | 8 | 1 | 3.00 | $19,250.00 | $57,750.00 |
| | **Unit Sub Total** | **EA** | | **3** | **6.00** | **$21,091.67** | **$126,550.00** |
| | **Item Code 512231 Total No. of Proj.** | | | **3** | | **Total Amount** | **$126,550.00** |
| **512232** | FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (20 M - 25 M) | EA | 3 | 1 | 10.00 | $11,200.00 | $112,000.00 |
| | | EA | 7 | 1 | 2.00 | $24,000.00 | $48,000.00 |
| | **Unit Sub Total** | **EA** | | **2** | **12.00** | **$13,333.33** | **$160,000.00** |
| | **Item Code 512232 Total No. of Proj.** | | | **2** | | **Total Amount** | **$160,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **512233** | FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (25 M - 30 M) | EA | 7 | 1 | 1.00 | $40,000.00 | $40,000.00 |
| | | EA | 11 | 3 | 48.00 | $25,187.50 | $1,209,000.00 |
| | **Unit Sub Total** | **EA** | | **4** | **49.00** | **$25,489.80** | **$1,249,000.00** |
| | **Item Code 512233 Total No. of Proj.** | | | **4** | | **Total Amount** | **$1,249,000.00** |
| **512234** | FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (30 M - 35 M) | EA | 2 | 1 | 14.00 | $28,000.00 | $392,000.00 |
| | | EA | 11 | 2 | 15.00 | $34,400.00 | $516,000.00 |
| | **Unit Sub Total** | **EA** | | **3** | **29.00** | **$31,310.34** | **$908,000.00** |
| | **Item Code 512234 Total No. of Proj.** | | | **3** | | **Total Amount** | **$908,000.00** |
| **512240** | FURNISH PRECAST PRESTRESSED CONCRETE BOX GIRDER (20 M - 25 M) | EA | 11 | 1 | 2.00 | $60,000.00 | $120,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$60,000.00** | **$120,000.00** |
| | **Item Code 512240 Total No. of Proj.** | | | **1** | | **Total Amount** | **$120,000.00** |
| **512253** | FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (20 M-25 M) | EA | 2 | 1 | 165.00 | $0.00 | $0.00 |
| | **Unit Sub Total** | **EA** | | **1** | **165.00** | **$0.00** | **$0.00** |
| | **Item Code 512253 Total No. of Proj.** | | | **1** | | **Total Amount** | **$0.00** |
| **512278** | FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (90'-100') | EA | 7 | 1 | 12.00 | $29,100.00 | $349,200.00 |
| | **Unit Sub Total** | **EA** | | **1** | **12.00** | **$29,100.00** | **$349,200.00** |
| | **Item Code 512278 Total No. of Proj.** | | | **1** | | **Total Amount** | **$349,200.00** |
| **512500** | ERECT PRECAST PRESTRESSED CONCRETE GIRDER | EA | 2 | 2 | 179.00 | $391.06 | $70,000.00 |
| | | EA | 3 | 1 | 10.00 | $2,650.00 | $26,500.00 |
| | | EA | 5 | 1 | 3.00 | $3,382.00 | $10,146.00 |
| | | EA | 7 | 4 | 23.00 | $21,308.17 | $490,088.00 |
| | | EA | 8 | 1 | 9.00 | $2,900.00 | $26,100.00 |
| | | EA | 11 | 3 | 63.00 | $6,114.29 | $385,200.00 |
| | **Unit Sub Total** | **EA** | | **12** | **287.00** | **$3,512.31** | **$1,008,034.00** |
| | **Item Code 512500 Total No. of Proj.** | | | **12** | | **Total Amount** | **$1,008,034.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **512502** | ERECT PRECAST PRESTRESSED CONCRETE BOX GIRDER | EA | 11 | 1 | 2.00 | $7,000.00 | $14,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$7,000.00** | **$14,000.00** |
| | **Item Code 512502 Total No. of Proj.** | | | **1** | | **Total Amount** | **$14,000.00** |
| **513501** | CONCRETE CLOSURE WALL | M2 | 5 | 1 | 77.00 | $570.00 | $43,890.00 |
| | **Unit Sub Total** | **M2** | | **1** | **77.00** | **$570.00** | **$43,890.00** |
| | **Item Code 513501 Total No. of Proj.** | | | **1** | | **Total Amount** | **$43,890.00** |
| **513551** | RETAINING WALL STEM (TYPE 6) | M2 | 5 | 1 | 24.00 | $1,535.00 | $36,840.00 |
| | **Unit Sub Total** | **M2** | | **1** | **24.00** | **$1,535.00** | **$36,840.00** |
| | **Item Code 513551 Total No. of Proj.** | | | **1** | | **Total Amount** | **$36,840.00** |
| **513603** | REINFORCED CONCRETE CRIB WALL (TYPE C) | M2 | 5 | 1 | 37.00 | $880.00 | $32,560.00 |
| | **Unit Sub Total** | **M2** | | **1** | **37.00** | **$880.00** | **$32,560.00** |
| | **Item Code 513603 Total No. of Proj.** | | | **1** | | **Total Amount** | **$32,560.00** |
| **513604** | REINFORCED CONCRETE CRIB WALL (TYPE D) | M2 | 5 | 1 | 151.00 | $1,000.00 | $151,000.00 |
| | **Unit Sub Total** | **M2** | | **1** | **151.00** | **$1,000.00** | **$151,000.00** |
| | **Item Code 513604 Total No. of Proj.** | | | **1** | | **Total Amount** | **$151,000.00** |
| **515020** | REFINISH BRIDGE DECK | M2 | 4 | 3 | 200.00 | $180.21 | $36,042.00 |
| | | M2 | 7 | 1 | 187.00 | $275.00 | $51,425.00 |
| | | M2 | 8 | 2 | 63.00 | $842.22 | $53,060.00 |
| | | M2 | 11 | 2 | 87.00 | $287.36 | $25,000.00 |
| | **Unit Sub Total** | **M2** | | **8** | **537.00** | **$308.24** | **$165,527.00** |
| **515020** | REFINISH BRIDGE DECK | SQFT | 3 | 1 | 173.00 | $10.00 | $1,730.00 |
| | | SQFT | 6 | 1 | 3,420.00 | $8.00 | $27,360.00 |
| | | SQFT | 12 | 1 | 203.00 | $26.00 | $5,278.00 |
| | **Unit Sub Total** | **SQFT** | | **3** | **3,796.00** | **$9.05** | **$34,368.00** |
| | **Item Code 515020 Total No. of Proj.** | | | **11** | | **Total Amount** | **$199,895.00** |
| **515028** | REPAIR SPALLED SURFACE AREA | SQFT | 4 | 1 | 245.00 | $300.00 | $73,500.00 |
| | **Unit Sub Total** | **SQFT** | | **1** | **245.00** | **$300.00** | **$73,500.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 515028 Total No. of Proj.** | | | **1** | | **Total Amount** | **$73,500.00** |
| **515041** | FURNISH POLYESTER CONCRETE OVERLAY | CF | 1 | 2 | 2,828.00 | $82.08 | $232,110.00 |
| | | CF | 2 | 2 | 14,250.00 | $80.84 | $1,151,921.75 |
| | | CF | 3 | 8 | 12,463.00 | $88.31 | $1,100,620.00 |
| | | CF | 4 | 6 | 10,501.00 | $74.20 | $779,140.00 |
| | | CF | 7 | 1 | 839.00 | $79.00 | $66,281.00 |
| | | CF | 8 | 2 | 3,154.00 | $105.00 | $331,170.00 |
| | | CF | 10 | 3 | 3,966.00 | $96.94 | $384,454.00 |
| | | CF | 12 | 1 | 660.00 | $92.00 | $60,720.00 |
| | **Unit Sub Total** | **CF** | | **25** | **48,661.00** | **$84.39** | **$4,106,416.75** |
| **515041** | FURNISH POLYESTER CONCRETE OVERLAY | CY | 4 | 1 | 240.00 | $1,975.00 | $474,000.00 |
| | | CY | 11 | 1 | 31.00 | $2,095.00 | $64,945.00 |
| | **Unit Sub Total** | **CY** | | **2** | **271.00** | **$1,988.73** | **$538,945.00** |
| **515041** | FURNISH POLYESTER CONCRETE OVERLAY | M3 | 1 | 1 | 23.80 | $3,500.00 | $83,300.00 |
| | | M3 | 2 | 3 | 407.00 | $2,976.14 | $1,211,287.00 |
| | | M3 | 3 | 3 | 1,680.00 | $2,227.09 | $3,741,510.00 |
| | | M3 | 5 | 1 | 15.00 | $3,900.00 | $58,500.00 |
| | | M3 | 6 | 1 | 137.00 | $2,450.00 | $335,650.00 |
| | | M3 | 7 | 4 | 62.40 | $3,719.23 | $232,080.00 |
| | | M3 | 8 | 1 | 50.00 | $3,000.00 | $150,000.00 |
| | | M3 | 11 | 2 | 13.00 | $4,542.31 | $59,050.00 |
| | **Unit Sub Total** | **M3** | | **16** | **2,388.20** | **$2,458.49** | **$5,871,377.00** |
| | **Item Code 515041 Total No. of Proj.** | | | **43** | | **Total Amount** | **$10,516,738.75** |
| **515042** | PLACE POLYESTER CONCRETE OVERLAY | M2 | 1 | 1 | 1,202.00 | $30.00 | $36,060.00 |
| | | M2 | 2 | 3 | 19,261.00 | $15.65 | $301,372.00 |
| | | M2 | 3 | 3 | 69,158.00 | $14.86 | $1,027,806.10 |
| | | M2 | 5 | 1 | 750.00 | $52.00 | $39,000.00 |
| | | M2 | 6 | 1 | 1,617.00 | $32.00 | $51,744.00 |
| | | M2 | 7 | 4 | 1,511.00 | $103.10 | $155,785.00 |
| | | M2 | 8 | 1 | 2,600.00 | $10.00 | $26,000.00 |
| | | M2 | 11 | 2 | 420.00 | $73.21 | $30,750.00 |
| | **Unit Sub Total** | **M2** | | **16** | **96,519.00** | **$17.29** | **$1,668,517.10** |
| **515042** | PLACE POLYESTER CONCRETE OVERLAY | SQFT | 1 | 2 | 37,748.00 | $1.94 | $73,212.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **515042** | PLACE POLYESTER CONCRETE OVERLAY | SQFT | 2 | 2 | 190,022.00 | $0.94 | $178,619.80 |
| | | SQFT | 3 | 8 | 158,089.00 | $1.98 | $313,222.55 |
| | | SQFT | 4 | 7 | 218,912.00 | $1.44 | $315,569.00 |
| | | SQFT | 7 | 1 | 4,189.00 | $3.00 | $12,567.00 |
| | | SQFT | 8 | 2 | 50,334.00 | $1.12 | $56,516.40 |
| | | SQFT | 10 | 3 | 34,219.00 | $3.18 | $108,908.50 |
| | | SQFT | 12 | 1 | 10,536.00 | $4.00 | $42,144.00 |
| | **Unit Sub Total** | **SQFT** | | **26** | **704,049.00** | **$1.56** | **$1,100,759.25** |
| **515042** | PLACE POLYESTER CONCRETE OVERLAY | SQYD | 11 | 1 | 550.00 | $25.00 | $13,750.00 |
| | **Unit Sub Total** | **SQYD** | | **1** | **550.00** | **$25.00** | **$13,750.00** |
| | **Item Code 515042** | **Total No. of Proj.** | | **43** | | **Total Amount** | **$2,783,026.35** |
| **515070** | CORE CONCRETE (10") | LF | 4 | 1 | 1.50 | $600.00 | $900.00 |
| | **Unit Sub Total** | **LF** | | **1** | **1.50** | **$600.00** | **$900.00** |
| | **Item Code 515070** | **Total No. of Proj.** | | **1** | | **Total Amount** | **$900.00** |
| **515072** | CORE CONCRETE (0 - 50 MM) | M | 11 | 1 | 37.00 | $750.00 | $27,750.00 |
| | **Unit Sub Total** | **M** | | **1** | **37.00** | **$750.00** | **$27,750.00** |
| | **Item Code 515072** | **Total No. of Proj.** | | **1** | | **Total Amount** | **$27,750.00** |
| **515073** | CORE CONCRETE (51 MM - 100 MM) | M | 4 | 1 | 26.00 | $500.00 | $13,000.00 |
| | | M | 5 | 1 | 7.00 | $677.00 | $4,739.00 |
| | | M | 7 | 1 | 1.20 | $1,825.00 | $2,190.00 |
| | | M | 11 | 1 | 2.00 | $850.00 | $1,700.00 |
| | **Unit Sub Total** | **M** | | **4** | **36.20** | **$597.49** | **$21,629.00** |
| | **Item Code 515073** | **Total No. of Proj.** | | **4** | | **Total Amount** | **$21,629.00** |
| **515074** | CORE CONCRETE (101 MM - 150 MM) | M | 4 | 1 | 10.00 | $700.00 | $7,000.00 |
| | | M | 11 | 1 | 15.00 | $900.00 | $13,500.00 |
| | **Unit Sub Total** | **M** | | **2** | **25.00** | **$820.00** | **$20,500.00** |
| | **Item Code 515074** | **Total No. of Proj.** | | **2** | | **Total Amount** | **$20,500.00** |
| **515075** | CORE CONCRETE (151 MM - 200 MM) | M | 11 | 2 | 7.00 | $492.86 | $3,450.00 |
| | **Unit Sub Total** | **M** | | **2** | **7.00** | **$492.86** | **$3,450.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 515075 Total No. of Proj.** | | | **2** | | **Total Amount** | **$3,450.00** |
| **515077** | CORE CONCRETE (251 MM - 300 MM) | M | 11 | 1 | 3.00 | $850.00 | $2,550.00 |
| | **Unit Sub Total** | **M** | | **1** | **3.00** | **$850.00** | **$2,550.00** |
| | **Item Code 515077 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,550.00** |
| **515079** | CORE CONCRETE (351 MM - 400 MM) | M | 11 | 1 | 2.00 | $1,000.00 | $2,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **2.00** | **$1,000.00** | **$2,000.00** |
| | **Item Code 515079 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,000.00** |
| **515160** | CORE CONCRETE (1 1/2") | LF | 4 | 1 | 128.00 | $100.00 | $12,800.00 |
| | **Unit Sub Total** | **LF** | | **1** | **128.00** | **$100.00** | **$12,800.00** |
| | **Item Code 515160 Total No. of Proj.** | | | **1** | | **Total Amount** | **$12,800.00** |
| **517961** | SOUND WALL (BARRIER) (MASONRY BLOCK) | M2 | 4 | 1 | 1,789.00 | $160.00 | $286,240.00 |
| | | M2 | 11 | 1 | 55.00 | $256.00 | $14,080.00 |
| | **Unit Sub Total** | **M2** | | **2** | **1,844.00** | **$162.86** | **$300,320.00** |
| | **Item Code 517961 Total No. of Proj.** | | | **2** | | **Total Amount** | **$300,320.00** |
| **518002** | SOUND WALL (MASONRY BLOCK) | M2 | 3 | 2 | 15,887.00 | $222.35 | $3,532,430.00 |
| | | M2 | 5 | 1 | 2,790.00 | $123.00 | $343,170.00 |
| | | M2 | 7 | 1 | 8,622.00 | $160.00 | $1,379,520.00 |
| | | M2 | 10 | 3 | 5,325.00 | $237.43 | $1,264,314.00 |
| | | M2 | 11 | 6 | 16,444.00 | $194.14 | $3,192,465.00 |
| | **Unit Sub Total** | **M2** | | **13** | **49,068.00** | **$197.93** | **$9,711,899.00** |
| | **Item Code 518002 Total No. of Proj.** | | | **13** | | **Total Amount** | **$9,711,899.00** |
| **518010** | ACCESS GATE (SOUND WALL) | EA | 11 | 1 | 3.00 | $3,350.00 | $10,050.00 |
| | **Unit Sub Total** | **EA** | | **1** | **3.00** | **$3,350.00** | **$10,050.00** |
| | **Item Code 518010 Total No. of Proj.** | | | **1** | | **Total Amount** | **$10,050.00** |
| **518050** | PTFE BEARING | EA | 1 | 1 | 27.00 | $2,500.00 | $67,500.00 |
| | | EA | 2 | 1 | 20.00 | $3,800.00 | $76,000.00 |
| | | EA | 7 | 1 | 8.00 | $2,750.00 | $22,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **3** | **55.00** | **$3,009.09** | **$165,500.00** |
| | **Item Code 518050** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$165,500.00** |
| **518051** | PTFE SPHERICAL BEARING | | EA | 7 | 1 | 9.00 | $10,000.00 | $90,000.00 |
| | | | EA | 8 | 1 | 16.00 | $7,000.00 | $112,000.00 |
| | | | EA | 11 | 1 | 52.00 | $3,100.00 | $161,200.00 |
| | | **Unit Sub Total** | **EA** | | **3** | **77.00** | **$4,716.88** | **$363,200.00** |
| | **Item Code 518051** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$363,200.00** |
| **518201** | MASONRY BLOCK WALL | | M2 | 8 | 1 | 250.00 | $308.00 | $77,000.00 |
| | | **Unit Sub Total** | **M2** | | **1** | **250.00** | **$308.00** | **$77,000.00** |
| | **Item Code 518201** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$77,000.00** |
| **519050** | EXPANSION DAM | | CF | 3 | 1 | 11.00 | $500.00 | $5,500.00 |
| | | | CF | 4 | 1 | 418.00 | $180.00 | $75,240.00 |
| | | **Unit Sub Total** | **CF** | | **2** | **429.00** | **$188.21** | **$80,740.00** |
| | **Item Code 519050** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$80,740.00** |
| **519078** | SNOWPLOW DEFLECTOR | | EA | 3 | 1 | 87.00 | $220.00 | $19,140.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **87.00** | **$220.00** | **$19,140.00** |
| | **Item Code 519078** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$19,140.00** |
| **519081** | JOINT SEAL (MR 1/2") | | LF | 1 | 1 | 518.00 | $20.00 | $10,360.00 |
| | | | LF | 2 | 3 | 2,005.00 | $26.39 | $52,903.00 |
| | | | LF | 3 | 5 | 2,815.00 | $27.71 | $78,002.00 |
| | | | LF | 4 | 11 | 10,159.00 | $19.59 | $199,049.00 |
| | | | LF | 6 | 2 | 283.00 | $35.17 | $9,952.00 |
| | | | LF | 7 | 10 | 15,458.00 | $19.68 | $304,224.00 |
| | | | LF | 8 | 1 | 794.00 | $21.00 | $16,674.00 |
| | | | LF | 10 | 4 | 1,674.00 | $21.83 | $36,540.00 |
| | | | LF | 11 | 4 | 1,722.00 | $15.04 | $25,899.00 |
| | | | LF | 12 | 1 | 24.00 | $148.00 | $3,552.00 |
| | | **Unit Sub Total** | **LF** | | **42** | **35,452.00** | **$20.79** | **$737,155.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 519081 Total No. of Proj.** | | | **42** | | **Total Amount** | **$737,155.00** |
| **519088** | JOINT SEAL (MR 1") | LF | 1 | 1 | 262.00 | $20.00 | $5,240.00 |
| | | LF | 2 | 3 | 1,092.00 | $29.03 | $31,701.00 |
| | | LF | 3 | 8 | 2,809.00 | $42.32 | $118,886.00 |
| | | LF | 4 | 6 | 6,542.00 | $20.35 | $133,098.00 |
| | | LF | 6 | 1 | 391.00 | $38.00 | $14,858.00 |
| | | LF | 7 | 11 | 7,783.00 | $31.91 | $248,321.00 |
| | | LF | 8 | 1 | 100.00 | $35.00 | $3,500.00 |
| | | LF | 10 | 6 | 3,173.00 | $27.92 | $88,584.50 |
| | | LF | 11 | 4 | 1,210.00 | $31.17 | $37,720.00 |
| | **Unit Sub Total** | **LF** | | **41** | **23,362.00** | **$29.19** | **$681,908.50** |
| | **Item Code 519088 Total No. of Proj.** | | | **41** | | **Total Amount** | **$681,908.50** |
| **519091** | JOINT SEAL (MR 1 1/2") | LF | 1 | 1 | 338.00 | $55.00 | $18,590.00 |
| | | LF | 3 | 3 | 575.00 | $86.52 | $49,750.00 |
| | | LF | 4 | 8 | 2,346.00 | $57.00 | $133,719.00 |
| | | LF | 7 | 8 | 5,309.00 | $50.70 | $269,155.00 |
| | | LF | 10 | 3 | 1,002.00 | $46.91 | $47,002.60 |
| | | LF | 11 | 3 | 1,984.00 | $50.95 | $101,083.00 |
| | | LF | 12 | 2 | 1,901.00 | $47.98 | $91,215.00 |
| | **Unit Sub Total** | **LF** | | **28** | **13,455.00** | **$52.81** | **$710,514.60** |
| | **Item Code 519091 Total No. of Proj.** | | | **28** | | **Total Amount** | **$710,514.60** |
| **519092** | JOINT SEAL ASSEMBLY (MR 2 1/2") | LF | 3 | 1 | 161.00 | $200.00 | $32,200.00 |
| | | LF | 4 | 2 | 621.00 | $281.51 | $174,820.00 |
| | | LF | 7 | 1 | 33.00 | $205.00 | $6,765.00 |
| | | LF | 10 | 1 | 33.00 | $350.00 | $11,550.00 |
| | **Unit Sub Total** | **LF** | | **5** | **848.00** | **$265.73** | **$225,335.00** |
| | **Item Code 519092 Total No. of Proj.** | | | **5** | | **Total Amount** | **$225,335.00** |
| **519093** | JOINT SEAL ASSEMBLY (MR 3") | LF | 2 | 1 | 49.00 | $216.00 | $10,584.00 |
| | | LF | 4 | 1 | 486.00 | $280.00 | $136,080.00 |
| | | LF | 7 | 1 | 64.00 | $215.00 | $13,760.00 |
| | | LF | 10 | 1 | 525.00 | $350.00 | $183,750.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **LF** | | **4** | **1,124.00** | **$306.20** | **$344,174.00** |
| | **Item Code 519093 Total No. of Proj.** | | | **4** | | **Total Amount** | **$344,174.00** |
| **519094** | JOINT SEAL ASSEMBLY (MR 3 1/2") | LF | 4 | 1 | 248.00 | $300.00 | $74,400.00 |
| | | LF | 10 | 1 | 139.00 | $350.00 | $48,650.00 |
| | | LF | 11 | 1 | 40.00 | $174.00 | $6,960.00 |
| | **Unit Sub Total** | **LF** | | **3** | **427.00** | **$304.47** | **$130,010.00** |
| | **Item Code 519094 Total No. of Proj.** | | | **3** | | **Total Amount** | **$130,010.00** |
| **519095** | JOINT SEAL ASSEMBLY (MR 4") | LF | 4 | 2 | 404.00 | $233.17 | $94,200.00 |
| | | LF | 7 | 1 | 33.00 | $230.00 | $7,590.00 |
| | | LF | 10 | 2 | 218.00 | $526.33 | $114,740.00 |
| | | LF | 11 | 1 | 40.00 | $174.00 | $6,960.00 |
| | | LF | 12 | 1 | 178.00 | $282.00 | $50,196.00 |
| | **Unit Sub Total** | **LF** | | **7** | **873.00** | **$313.50** | **$273,686.00** |
| | **Item Code 519095 Total No. of Proj.** | | | **7** | | **Total Amount** | **$273,686.00** |
| **519097** | JOINT SEAL ASSEMBLY (MR 5") | LF | 11 | 1 | 78.00 | $550.00 | $42,900.00 |
| | **Unit Sub Total** | **LF** | | **1** | **78.00** | **$550.00** | **$42,900.00** |
| | **Item Code 519097 Total No. of Proj.** | | | **1** | | **Total Amount** | **$42,900.00** |
| **519099** | JOINT SEAL ASSEMBLY (MR 6") | LF | 4 | 1 | 136.00 | $650.00 | $88,400.00 |
| | **Unit Sub Total** | **LF** | | **1** | **136.00** | **$650.00** | **$88,400.00** |
| | **Item Code 519099 Total No. of Proj.** | | | **1** | | **Total Amount** | **$88,400.00** |
| **519100** | JOINT SEAL (MR 2") | LF | 2 | 1 | 25.00 | $115.00 | $2,875.00 |
| | | LF | 3 | 2 | 410.00 | $75.46 | $30,940.00 |
| | | LF | 4 | 6 | 879.00 | $91.57 | $80,486.00 |
| | | LF | 5 | 1 | 82.00 | $85.00 | $6,970.00 |
| | | LF | 6 | 1 | 92.00 | $100.00 | $9,200.00 |
| | | LF | 7 | 2 | 1,602.00 | $65.43 | $104,820.00 |
| | | LF | 8 | 1 | 150.00 | $65.00 | $9,750.00 |
| | | LF | 11 | 3 | 205.00 | $53.56 | $10,980.00 |
| | | LF | 12 | 2 | 3,464.00 | $75.46 | $261,400.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **LF** | | **19** | **6,909.00** | **$74.89** | **$517,421.00** |
| | **Item Code 519100** | **Total No. of Proj.** | | | **19** | | **Total Amount** | **$517,421.00** |
| **519101** | JOINT SEAL (TYPE A) | | M | 11 | 1 | 43.00 | $65.00 | $2,795.00 |
| | | **Unit Sub Total** | **M** | | **1** | **43.00** | **$65.00** | **$2,795.00** |
| | **Item Code 519101** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,795.00** |
| **519102** | JOINT SEAL (TYPE AL) | | LF | 4 | 2 | 456.00 | $17.98 | $8,200.00 |
| | | | LF | 6 | 1 | 180.00 | $37.00 | $6,660.00 |
| | | **Unit Sub Total** | **LF** | | **3** | **636.00** | **$23.36** | **$14,860.00** |
| **519102** | JOINT SEAL (TYPE AL) | | M | 3 | 1 | 190.00 | $115.00 | $21,850.00 |
| | | | M | 7 | 1 | 249.00 | $120.00 | $29,880.00 |
| | | | M | 11 | 2 | 118.00 | $90.17 | $10,640.00 |
| | | **Unit Sub Total** | **M** | | **4** | **557.00** | **$111.97** | **$62,370.00** |
| | **Item Code 519102** | **Total No. of Proj.** | | | **7** | | **Total Amount** | **$77,230.00** |
| **519117** | JOINT SEAL (MR 30 MM) | | M | 1 | 1 | 44.00 | $100.00 | $4,400.00 |
| | | | M | 2 | 1 | 56.00 | $77.00 | $4,312.00 |
| | | | M | 3 | 3 | 806.00 | $122.37 | $98,630.00 |
| | | | M | 4 | 1 | 53.00 | $140.00 | $7,420.00 |
| | | | M | 5 | 1 | 88.00 | $97.00 | $8,536.00 |
| | | | M | 7 | 4 | 511.00 | $159.71 | $81,612.00 |
| | | | M | 8 | 2 | 349.00 | $144.41 | $50,398.00 |
| | | | M | 11 | 3 | 170.00 | $97.94 | $16,650.00 |
| | | | M | 12 | 1 | 200.00 | $196.00 | $39,200.00 |
| | | **Unit Sub Total** | **M** | | **17** | **2,277.00** | **$136.65** | **$311,158.00** |
| | **Item Code 519117** | **Total No. of Proj.** | | | **17** | | **Total Amount** | **$311,158.00** |
| **519120** | JOINT SEAL (MR 15 MM) | | M | 1 | 1 | 15.00 | $100.00 | $1,500.00 |
| | | | M | 2 | 1 | 36.00 | $124.00 | $4,464.00 |
| | | | M | 3 | 1 | 99.00 | $150.00 | $14,850.00 |
| | | | M | 4 | 2 | 229.00 | $167.01 | $38,245.00 |
| | | | M | 5 | 1 | 80.00 | $97.00 | $7,760.00 |
| | | | M | 7 | 5 | 1,766.00 | $140.66 | $248,398.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **519120** | JOINT SEAL (MR 15 MM) | M | 8 | 1 | 255.00 | $115.00 | $29,325.00 |
| | **Unit Sub Total** | **M** | | **12** | **2,480.00** | **$138.93** | **$344,542.00** |
| | **Item Code 519120 Total No. of Proj.** | | | **12** | | **Total Amount** | **$344,542.00** |
| **519124** | JOINT SEAL ASSEMBLY (MR 60 MM) | M | 7 | 1 | 71.00 | $400.00 | $28,400.00 |
| | **Unit Sub Total** | **M** | | **1** | **71.00** | **$400.00** | **$28,400.00** |
| | **Item Code 519124 Total No. of Proj.** | | | **1** | | **Total Amount** | **$28,400.00** |
| **519125** | JOINT SEAL ASSEMBLY (MR 70 MM) | M | 3 | 1 | 62.00 | $700.00 | $43,400.00 |
| | | M | 10 | 1 | 50.00 | $510.00 | $25,500.00 |
| | | M | 11 | 1 | 62.00 | $650.00 | $40,300.00 |
| | **Unit Sub Total** | **M** | | **3** | **174.00** | **$627.59** | **$109,200.00** |
| | **Item Code 519125 Total No. of Proj.** | | | **3** | | **Total Amount** | **$109,200.00** |
| **519126** | JOINT SEAL ASSEMBLY (MR 80 MM) | M | 3 | 1 | 117.00 | $700.00 | $81,900.00 |
| | | M | 7 | 1 | 78.00 | $400.00 | $31,200.00 |
| | | M | 10 | 1 | 76.00 | $60.00 | $4,560.00 |
| | **Unit Sub Total** | **M** | | **3** | **271.00** | **$434.17** | **$117,660.00** |
| | **Item Code 519126 Total No. of Proj.** | | | **3** | | **Total Amount** | **$117,660.00** |
| **519128** | JOINT SEAL ASSEMBLY (MR 100 MM) | M | 7 | 1 | 18.00 | $735.00 | $13,230.00 |
| | | M | 9 | 1 | 36.00 | $1,100.00 | $39,600.00 |
| | **Unit Sub Total** | **M** | | **2** | **54.00** | **$978.33** | **$52,830.00** |
| | **Item Code 519128 Total No. of Proj.** | | | **2** | | **Total Amount** | **$52,830.00** |
| **519129** | JOINT SEAL ASSEMBLY (MR 101 MM - 160 MM) | M | 1 | 1 | 71.00 | $1,900.00 | $134,900.00 |
| | | M | 2 | 2 | 165.00 | $1,509.09 | $249,000.00 |
| | | M | 7 | 2 | 23.00 | $2,143.48 | $49,300.00 |
| | | M | 11 | 1 | 74.00 | $2,600.00 | $192,400.00 |
| | **Unit Sub Total** | **M** | | **6** | **333.00** | **$1,878.68** | **$625,600.00** |
| | **Item Code 519129 Total No. of Proj.** | | | **6** | | **Total Amount** | **$625,600.00** |
| **519130** | JOINT SEAL ASSEMBLY (MR 161 MM - 240 MM) | M | 7 | 1 | 36.50 | $2,500.00 | $91,250.00 |
| | | M | 11 | 1 | 61.00 | $4,100.00 | $250,100.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **M** | | **2** | **97.50** | **$3,501.03** | **$341,350.00** |
| | **Item Code 519130 Total No. of Proj.** | | | **2** | | **Total Amount** | **$341,350.00** |
| **519131** | JOINT SEAL ASSEMBLY (MR 241 MM - 320 MM) | M | 7 | 1 | 39.00 | $3,200.00 | $124,800.00 |
| | | M | 11 | 1 | 12.00 | $6,000.00 | $72,000.00 |
| | **Unit Sub Total** | **M** | | **2** | **51.00** | **$3,858.82** | **$196,800.00** |
| | **Item Code 519131 Total No. of Proj.** | | | **2** | | **Total Amount** | **$196,800.00** |
| **519132** | JOINT SEAL ASSEMBLY (MR 321 MM - 400 MM) | M | 11 | 1 | 12.00 | $6,500.00 | $78,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **12.00** | **$6,500.00** | **$78,000.00** |
| | **Item Code 519132 Total No. of Proj.** | | | **1** | | **Total Amount** | **$78,000.00** |
| **519133** | JOINT SEAL (ASPHALTIC PLUG) | LF | 4 | 2 | 1,326.00 | $71.93 | $95,380.00 |
| | **Unit Sub Total** | **LF** | | **2** | **1,326.00** | **$71.93** | **$95,380.00** |
| | **Item Code 519133 Total No. of Proj.** | | | **2** | | **Total Amount** | **$95,380.00** |
| **519142** | JOINT SEAL (MR 40 MM) | M | 1 | 1 | 36.00 | $200.00 | $7,200.00 |
| | | M | 2 | 2 | 90.00 | $193.00 | $17,370.00 |
| | | M | 3 | 2 | 307.00 | $174.80 | $53,665.00 |
| | | M | 4 | 1 | 10.00 | $306.00 | $3,060.00 |
| | | M | 11 | 5 | 888.00 | $241.82 | $214,740.00 |
| | **Unit Sub Total** | **M** | | **11** | **1,331.00** | **$222.42** | **$296,035.00** |
| | **Item Code 519142 Total No. of Proj.** | | | **11** | | **Total Amount** | **$296,035.00** |
| **519144** | JOINT SEAL (MR 50 MM) | M | 2 | 1 | 157.00 | $0.00 | $0.00 |
| | | M | 3 | 2 | 188.00 | $262.55 | $49,360.00 |
| | | M | 4 | 2 | 87.00 | $333.79 | $29,040.00 |
| | | M | 5 | 1 | 128.00 | $294.00 | $37,632.00 |
| | | M | 7 | 1 | 8.00 | $480.00 | $3,840.00 |
| | | M | 10 | 1 | 38.00 | $204.00 | $7,752.00 |
| | | M | 11 | 6 | 488.00 | $276.67 | $135,015.00 |
| | **Unit Sub Total** | **M** | | **14** | **1,094.00** | **$240.07** | **$262,639.00** |
| | **Item Code 519144 Total No. of Proj.** | | | **14** | | **Total Amount** | **$262,639.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **520101** | BAR REINFORCING STEEL | | KG | 4 | 4 | 94,962.00 | $2.31 | $219,164.00 |
| | | | KG | 7 | 1 | 1,566.60 | $3.00 | $4,699.80 |
| | | | KG | 8 | 1 | 59.00 | $23.00 | $1,357.00 |
| | | | KG | 9 | 1 | 3,458.00 | $8.00 | $27,664.00 |
| | | | KG | 11 | 2 | 16,000.00 | $2.39 | $38,250.00 |
| | | **Unit Sub Total** | **KG** | | **9** | **116,045.60** | **$2.51** | **$291,134.80** |
| **520101** | BAR REINFORCING STEEL | | LB | 2 | 2 | 10,100.00 | $2.22 | $22,386.50 |
| | | | LB | 3 | 1 | 7,188.00 | $1.30 | $9,344.40 |
| | | | LB | 4 | 1 | 8,200.00 | $1.00 | $8,200.00 |
| | | | LB | 6 | 1 | 3,800.00 | $2.00 | $7,600.00 |
| | | | LB | 8 | 1 | 2,000.00 | $1.00 | $2,000.00 |
| | | | LB | 11 | 2 | 8,482.00 | $1.71 | $14,509.40 |
| | | **Unit Sub Total** | **LB** | | **8** | **39,770.00** | **$1.61** | **$64,040.30** |
| | **Item Code 520101** | **Total No. of Proj.** | | | **17** | | **Total Amount** | **$355,175.10** |
| **520102** | BAR REINFORCING STEEL (BRIDGE) | | KG | 1 | 3 | 1,357,070.00 | $2.56 | $3,469,710.00 |
| | | | KG | 2 | 4 | 5,814,770.00 | $1.40 | $8,168,430.00 |
| | | | KG | 3 | 4 | 2,596,387.00 | $2.33 | $6,037,970.50 |
| | | | KG | 4 | 5 | 444,513.00 | $2.47 | $1,099,110.70 |
| | | | KG | 5 | 2 | 664,920.00 | $2.74 | $1,819,712.00 |
| | | | KG | 6 | 1 | 29,665.00 | $2.30 | $68,229.50 |
| | | | KG | 7 | 8 | 7,015,960.00 | $1.81 | $12,710,556.70 |
| | | | KG | 8 | 1 | 127,157.00 | $2.80 | $356,039.60 |
| | | | KG | 9 | 1 | 116,010.00 | $2.50 | $290,025.00 |
| | | | KG | 10 | 2 | 742,300.00 | $2.02 | $1,496,640.00 |
| | | | KG | 11 | 9 | 9,041,450.00 | $1.85 | $16,737,870.00 |
| | | **Unit Sub Total** | **KG** | | **40** | **27,950,202.00** | **$1.87** | **$52,254,294.00** |
| **520102** | BAR REINFORCING STEEL (BRIDGE) | | LB | 1 | 1 | 102.00 | $7.00 | $714.00 |
| | | | LB | 2 | 1 | 6,540.00 | $3.00 | $19,620.00 |
| | | | LB | 3 | 1 | 1,915.00 | $2.00 | $3,830.00 |
| | | | LB | 4 | 4 | 326,640.00 | $1.23 | $400,504.50 |
| | | | LB | 7 | 4 | 308,652.00 | $1.57 | $485,484.00 |
| | | | LB | 8 | 1 | 1,406,000.00 | $1.30 | $1,827,800.00 |
| | | | LB | 10 | 6 | 17,691.00 | $1.37 | $24,194.50 |
| | | | LB | 11 | 2 | 1,200.00 | $2.25 | $2,700.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **520102** | BAR REINFORCING STEEL (BRIDGE) | LB | 12 | 2 | 226,145.00 | $1.39 | $314,868.50 |
| | **Unit Sub Total** | **LB** | | **22** | **2,294,885.00** | **$1.34** | **$3,079,715.50** |
| | **Item Code 520102 Total No. of Proj.** | | | **62** | | **Total Amount** | **$55,334,009.50** |
| **520103** | BAR REINFORCING STEEL (RETAINING WALL) | KG | 1 | 2 | 3,574.00 | $3.18 | $11,352.00 |
| | | KG | 2 | 1 | 130,774.00 | $3.30 | $431,554.20 |
| | | KG | 3 | 3 | 239,332.00 | $2.59 | $620,214.45 |
| | | KG | 4 | 6 | 814,874.00 | $2.59 | $2,113,044.80 |
| | | KG | 5 | 5 | 328,964.00 | $2.54 | $835,969.90 |
| | | KG | 6 | 1 | 5,060.00 | $1.39 | $7,033.40 |
| | | KG | 7 | 6 | 1,199,256.00 | $1.94 | $2,323,525.40 |
| | | KG | 8 | 1 | 41,680.00 | $2.30 | $95,864.00 |
| | | KG | 9 | 2 | 50,987.00 | $1.61 | $82,340.80 |
| | | KG | 10 | 2 | 147,700.00 | $3.38 | $499,660.00 |
| | | KG | 11 | 8 | 3,139,531.00 | $2.16 | $6,776,885.70 |
| | **Unit Sub Total** | **KG** | | **37** | **6,101,732.00** | **$2.26** | **$13,797,444.65** |
| **520103** | BAR REINFORCING STEEL (RETAINING WALL) | LB | 2 | 1 | 6,900.00 | $2.00 | $13,800.00 |
| | | LB | 4 | 1 | 3,800.00 | $1.40 | $5,320.00 |
| | | LB | 7 | 1 | 19,245.00 | $1.50 | $28,867.50 |
| | | LB | 8 | 1 | 92,060.00 | $1.20 | $110,472.00 |
| | | LB | 11 | 1 | 3,175.00 | $2.70 | $8,572.50 |
| | | LB | 12 | 2 | 515,729.00 | $1.34 | $691,674.15 |
| | **Unit Sub Total** | **LB** | | **7** | **640,909.00** | **$1.34** | **$858,706.15** |
| | **Item Code 520103 Total No. of Proj.** | | | **44** | | **Total Amount** | **$14,656,150.80** |
| **520105** | BAR REINFORCING STEEL (SOUND WALL) | KG | 4 | 1 | 1,891.00 | $3.00 | $5,673.00 |
| | | KG | 5 | 1 | 10,200.00 | $2.30 | $23,460.00 |
| | | KG | 7 | 1 | 73,430.00 | $2.00 | $146,860.00 |
| | **Unit Sub Total** | **KG** | | **3** | **85,521.00** | **$2.06** | **$175,993.00** |
| | **Item Code 520105 Total No. of Proj.** | | | **3** | | **Total Amount** | **$175,993.00** |
| **520106** | BAR REINFORCING STEEL (EPOXY COATED) | KG | 1 | 1 | 1,480.00 | $3.00 | $4,440.00 |
| | | KG | 3 | 1 | 17,992.00 | $4.00 | $71,968.00 |
| | | KG | 4 | 1 | 32,536.00 | $3.50 | $113,876.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **KG** | | **3** | **52,008.00** | **$3.66** | **$190,284.00** |
| **520106** | BAR REINFORCING STEEL (EPOXY COATED) | LB | 3 | 1 | 260.00 | $10.00 | $2,600.00 |
| | | LB | 4 | 1 | 1,440.00 | $5.00 | $7,200.00 |
| | | LB | 8 | 1 | 21,200.00 | $1.30 | $27,560.00 |
| | **Unit Sub Total** | **LB** | | **3** | **22,900.00** | **$1.63** | **$37,360.00** |
| | **Item Code 520106 Total No. of Proj.** | | | **6** | | **Total Amount** | **$227,644.00** |
| **520107** | BAR REINFORCING STEEL (BOX CULVERT) | KG | 1 | 1 | 2,117.00 | $4.00 | $8,468.00 |
| | | KG | 2 | 1 | 31,391.00 | $2.65 | $83,186.15 |
| | | KG | 3 | 1 | 153,790.00 | $2.30 | $353,717.00 |
| | | KG | 4 | 3 | 32,427.00 | $1.45 | $46,933.75 |
| | | KG | 5 | 3 | 140,703.00 | $2.23 | $313,121.75 |
| | | KG | 6 | 2 | 39,992.00 | $1.48 | $59,189.00 |
| | | KG | 7 | 2 | 1,907.00 | $2.72 | $5,189.50 |
| | | KG | 9 | 2 | 53,645.00 | $2.15 | $115,330.20 |
| | | KG | 11 | 3 | 876,868.00 | $1.61 | $1,412,439.00 |
| | **Unit Sub Total** | **KG** | | **18** | **1,332,840.00** | **$1.80** | **$2,397,574.35** |
| **520107** | BAR REINFORCING STEEL (BOX CULVERT) | LB | 6 | 1 | 24,144.00 | $1.50 | $36,216.00 |
| | **Unit Sub Total** | **LB** | | **1** | **24,144.00** | **$1.50** | **$36,216.00** |
| | **Item Code 520107 Total No. of Proj.** | | | **19** | | **Total Amount** | **$2,433,790.35** |
| **520110** | BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE) | KG | 2 | 2 | 18,582.00 | $5.31 | $98,760.00 |
| | | KG | 3 | 1 | 19,290.00 | $2.80 | $54,012.00 |
| | | KG | 7 | 1 | 21,225.00 | $5.00 | $106,125.00 |
| | **Unit Sub Total** | **KG** | | **4** | **59,097.00** | **$4.38** | **$258,897.00** |
| **520110** | BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE) | LB | 2 | 1 | 15,243.00 | $1.70 | $25,913.10 |
| | | LB | 3 | 2 | 128,197.00 | $1.27 | $162,359.00 |
| | | LB | 8 | 1 | 685,000.00 | $1.15 | $787,750.00 |
| | **Unit Sub Total** | **LB** | | **4** | **828,440.00** | **$1.18** | **$976,022.10** |
| | **Item Code 520110 Total No. of Proj.** | | | **8** | | **Total Amount** | **$1,234,919.10** |
| **520120** | HEADED BAR REINFORCEMENT | EA | 1 | 1 | 72.00 | $50.00 | $3,600.00 |
| | | EA | 2 | 1 | 893.00 | $8.00 | $7,144.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **520120** | HEADED BAR REINFORCEMENT | | EA | 10 | 1 | 400.00 | $10.20 | $4,080.00 |
| | | | EA | 11 | 4 | 2,194.00 | $19.09 | $41,880.00 |
| | | **Unit Sub Total** | **EA** | | **7** | **3,559.00** | **$15.93** | **$56,704.00** |
| | **Item Code 520120** | **Total No. of Proj.** | | | **7** | | **Total Amount** | **$56,704.00** |
| **530100** | SHOTCRETE | | CF | 10 | 1 | 6.00 | $300.00 | $1,800.00 |
| | | **Unit Sub Total** | **CF** | | **1** | **6.00** | **$300.00** | **$1,800.00** |
| **530100** | SHOTCRETE | | CY | 2 | 1 | 36.00 | $1,200.00 | $43,200.00 |
| | | | CY | 6 | 1 | 10.00 | $1,500.00 | $15,000.00 |
| | | | CY | 8 | 1 | 528.00 | $600.00 | $316,800.00 |
| | | | CY | 11 | 1 | 28.00 | $1,325.00 | $37,100.00 |
| | | **Unit Sub Total** | **CY** | | **4** | **602.00** | **$684.55** | **$412,100.00** |
| **530100** | SHOTCRETE | | M3 | 2 | 1 | 49.00 | $900.00 | $44,100.00 |
| | | | M3 | 3 | 1 | 578.00 | $720.00 | $416,160.00 |
| | | | M3 | 4 | 4 | 700.00 | $627.18 | $439,025.00 |
| | | | M3 | 5 | 3 | 171.30 | $1,098.68 | $188,204.00 |
| | | | M3 | 7 | 1 | 1,797.00 | $475.00 | $853,575.00 |
| | | | M3 | 8 | 1 | 13.00 | $970.00 | $12,610.00 |
| | | | M3 | 11 | 4 | 614.00 | $740.96 | $454,950.00 |
| | | **Unit Sub Total** | **M3** | | **15** | **3,922.30** | **$614.08** | **$2,408,624.00** |
| | **Item Code 530100** | **Total No. of Proj.** | | | **20** | | **Total Amount** | **$2,822,524.00** |
| **540100** | DECK SEAL | | M2 | 2 | 1 | 32.00 | $200.00 | $6,400.00 |
| | | **Unit Sub Total** | **M2** | | **1** | **32.00** | **$200.00** | **$6,400.00** |
| | **Item Code 540100** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$6,400.00** |
| **540101** | ASPHALT MEMBRANE WATERPROOFING | | M2 | 1 | 1 | 25.00 | $500.00 | $12,500.00 |
| | | | M2 | 4 | 2 | 201.00 | $116.56 | $23,428.00 |
| | | | M2 | 5 | 1 | 320.00 | $45.00 | $14,400.00 |
| | | | M2 | 11 | 1 | 60.00 | $145.00 | $8,700.00 |
| | | **Unit Sub Total** | **M2** | | **5** | **606.00** | **$97.41** | **$59,028.00** |
| | **Item Code 540101** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$59,028.00** |
| **540102** | TREAT BRIDGE DECK | | M2 | 2 | 1 | 468.00 | $26.00 | $12,168.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **540102** | TREAT BRIDGE DECK | | M2 | 3 | 2 | 3,457.00 | $6.85 | $23,686.80 |
| | | | M2 | 4 | 2 | 4,571.00 | $2.73 | $12,483.00 |
| | | | M2 | 7 | 1 | 9,866.00 | $4.00 | $39,464.00 |
| | | | M2 | 8 | 2 | 21,623.00 | $4.48 | $96,895.40 |
| | | | M2 | 11 | 3 | 12,975.00 | $2.90 | $37,670.00 |
| | | **Unit Sub Total** | **M2** | | **11** | **52,960.00** | **$4.20** | **$222,367.20** |
| **540102** | TREAT BRIDGE DECK | | SQFT | 1 | 3 | 54,048.00 | $0.42 | $22,897.75 |
| | | | SQFT | 2 | 1 | 200,813.00 | $0.30 | $60,243.90 |
| | | | SQFT | 3 | 9 | 482,646.00 | $0.45 | $215,971.48 |
| | | | SQFT | 4 | 8 | 3,208,873.00 | $0.25 | $795,769.76 |
| | | | SQFT | 5 | 2 | 166,328.00 | $0.31 | $51,600.28 |
| | | | SQFT | 6 | 2 | 46,518.00 | $1.20 | $55,709.16 |
| | | | SQFT | 7 | 5 | 911,768.00 | $0.21 | $189,351.35 |
| | | | SQFT | 8 | 4 | 361,027.00 | $0.19 | $70,397.10 |
| | | | SQFT | 10 | 4 | 677,746.00 | $0.17 | $116,472.58 |
| | | | SQFT | 11 | 6 | 1,052,153.00 | $0.19 | $195,027.40 |
| | | | SQFT | 12 | 3 | 398,400.00 | $0.39 | $154,274.00 |
| | | **Unit Sub Total** | **SQFT** | | **47** | **7,560,320.00** | **$0.25** | **$1,927,714.76** |
| | **Item Code 540102** | **Total No. of Proj.** | | | **58** | | **Total Amount** | **$2,150,081.96** |
| **540108** | FURNISH BRIDGE DECK TREATMENT MATERIAL | | GAL | 1 | 2 | 597.00 | $78.44 | $46,831.00 |
| | | | GAL | 2 | 1 | 2,285.00 | $70.00 | $159,950.00 |
| | | | GAL | 3 | 9 | 5,694.00 | $64.57 | $367,635.50 |
| | | | GAL | 4 | 8 | 36,562.00 | $57.05 | $2,085,800.00 |
| | | | GAL | 6 | 2 | 567.00 | $76.47 | $43,360.00 |
| | | | GAL | 7 | 5 | 10,139.00 | $56.50 | $572,826.00 |
| | | | GAL | 8 | 4 | 3,662.00 | $78.57 | $287,714.00 |
| | | | GAL | 10 | 4 | 7,971.00 | $60.50 | $482,260.00 |
| | | | GAL | 11 | 6 | 12,122.00 | $61.84 | $749,659.00 |
| | | | GAL | 12 | 3 | 5,675.00 | $56.18 | $318,835.00 |
| | | **Unit Sub Total** | **GAL** | | **44** | **85,274.00** | **$59.98** | **$5,114,870.50** |
| **540108** | FURNISH BRIDGE DECK TREATMENT MATERIAL | | L | 2 | 1 | 213.00 | $20.00 | $4,260.00 |
| | | | L | 3 | 2 | 1,571.00 | $23.08 | $36,265.00 |
| | | | L | 4 | 2 | 2,150.00 | $20.84 | $44,810.00 |
| | | | L | 7 | 1 | 4,471.00 | $17.00 | $76,007.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **540108** | FURNISH BRIDGE DECK TREATMENT MATERIAL | L | 8 | 2 | 9,436.00 | $19.52 | $184,179.50 |
| | | L | 11 | 3 | 5,900.00 | $18.75 | $110,600.00 |
| | **Unit Sub Total** | **L** | | **11** | **23,741.00** | **$19.21** | **$456,121.50** |
| | **Item Code 540108 Total No. of Proj.** | | | **55** | | **Total Amount** | **$5,570,992.00** |
| **540109** | FURNISH BRIDGE DECK TREATMENT MATERIAL (LOW ODOR) | GAL | 1 | 1 | 95.00 | $65.00 | $6,175.00 |
| | | GAL | 5 | 2 | 1,910.00 | $72.04 | $137,600.00 |
| | **Unit Sub Total** | **GAL** | | **3** | **2,005.00** | **$71.71** | **$143,775.00** |
| | **Item Code 540109 Total No. of Proj.** | | | **3** | | **Total Amount** | **$143,775.00** |
| **550101** | STRUCTURAL STEEL | LB | 11 | 1 | 29,725.00 | $5.25 | $156,056.25 |
| | **Unit Sub Total** | **LB** | | **1** | **29,725.00** | **$5.25** | **$156,056.25** |
| | **Item Code 550101 Total No. of Proj.** | | | **1** | | **Total Amount** | **$156,056.25** |
| **550102** | STRUCTURAL STEEL (BRIDGE) | KG | 1 | 1 | 6,080.00 | $15.00 | $91,200.00 |
| | **Unit Sub Total** | **KG** | | **1** | **6,080.00** | **$15.00** | **$91,200.00** |
| **550102** | STRUCTURAL STEEL (BRIDGE) | LB | 7 | 1 | 101,000.00 | $6.15 | $621,150.00 |
| | **Unit Sub Total** | **LB** | | **1** | **101,000.00** | **$6.15** | **$621,150.00** |
| | **Item Code 550102 Total No. of Proj.** | | | **2** | | **Total Amount** | **$712,350.00** |
| **550110** | COLUMN CASING | KG | 1 | 1 | 5,340.00 | $12.00 | $64,080.00 |
| | | KG | 4 | 2 | 73,394.00 | $14.66 | $1,075,985.20 |
| | | KG | 11 | 1 | 20,200.00 | $13.00 | $262,600.00 |
| | **Unit Sub Total** | **KG** | | **4** | **98,934.00** | **$14.18** | **$1,402,665.20** |
| | **Item Code 550110 Total No. of Proj.** | | | **4** | | **Total Amount** | **$1,402,665.20** |
| **550203** | FURNISH STRUCTURAL STEEL (BRIDGE) | LB | 11 | 1 | 160.00 | $6.00 | $960.00 |
| | **Unit Sub Total** | **LB** | | **1** | **160.00** | **$6.00** | **$960.00** |
| | **Item Code 550203 Total No. of Proj.** | | | **1** | | **Total Amount** | **$960.00** |
| **550204** | ERECT STRUCTURAL STEEL (BRIDGE) | LB | 11 | 1 | 160.00 | $185.00 | $29,600.00 |
| | **Unit Sub Total** | **LB** | | **1** | **160.00** | **$185.00** | **$29,600.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 550204 Total No. of Proj.** | | | **1** | | **Total Amount** | **$29,600.00** |
| **558028** | METAL CATTLE GUARD (4.3 M) | EA | 9 | 2 | 24.00 | $10,979.17 | $263,500.00 |
| | **Unit Sub Total** | **EA** | | **2** | **24.00** | **$10,979.17** | **$263,500.00** |
| | **Item Code 558028 Total No. of Proj.** | | | **2** | | **Total Amount** | **$263,500.00** |
| **560203** | FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY) | KG | 3 | 2 | 8,100.00 | $12.86 | $104,140.00 |
| | | KG | 5 | 1 | 2,260.00 | $13.00 | $29,380.00 |
| | | KG | 7 | 2 | 2,415.00 | $31.01 | $74,884.00 |
| | | KG | 8 | 1 | 3,460.00 | $15.00 | $51,900.00 |
| | | KG | 10 | 1 | 3,900.00 | $14.80 | $57,720.00 |
| | | KG | 11 | 3 | 14,141.00 | $13.58 | $192,073.00 |
| | **Unit Sub Total** | **KG** | | **10** | **34,276.00** | **$14.88** | **$510,097.00** |
| **560203** | FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY) | LB | 3 | 2 | 47,211.00 | $6.45 | $304,534.30 |
| | | LB | 4 | 1 | 2,000.00 | $5.00 | $10,000.00 |
| | | LB | 6 | 1 | 3,688.00 | $8.00 | $29,504.00 |
| | **Unit Sub Total** | **LB** | | **4** | **52,899.00** | **$6.50** | **$344,038.30** |
| | **Item Code 560203 Total No. of Proj.** | | | **14** | | **Total Amount** | **$854,135.30** |
| **560204** | INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY) | KG | 3 | 2 | 8,100.00 | $3.43 | $27,770.00 |
| | | KG | 5 | 1 | 2,260.00 | $6.00 | $13,560.00 |
| | | KG | 7 | 2 | 2,415.00 | $14.50 | $35,028.00 |
| | | KG | 8 | 1 | 3,460.00 | $2.30 | $7,958.00 |
| | | KG | 10 | 1 | 3,900.00 | $3.06 | $11,934.00 |
| | | KG | 11 | 3 | 14,959.00 | $5.88 | $87,978.00 |
| | **Unit Sub Total** | **KG** | | **10** | **35,094.00** | **$5.25** | **$184,228.00** |
| **560204** | INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY) | LB | 3 | 2 | 47,211.00 | $1.56 | $73,738.00 |
| | | LB | 4 | 1 | 2,000.00 | $5.00 | $10,000.00 |
| | | LB | 6 | 1 | 3,688.00 | $2.00 | $7,376.00 |
| | **Unit Sub Total** | **LB** | | **4** | **52,899.00** | **$1.72** | **$91,114.00** |
| | **Item Code 560204 Total No. of Proj.** | | | **14** | | **Total Amount** | **$275,342.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **560206** | FURNISH REMOVABLE SIGN PANEL FRAME WITH SIGN PANELS ATTACHED | KG | 7 | 2 | 392.00 | $20.82 | $8,160.00 |
| | **Unit Sub Total** | **KG** | | **2** | **392.00** | **$20.82** | **$8,160.00** |
| | **Item Code 560206 Total No. of Proj.** | | | **2** | | **Total Amount** | **$8,160.00** |
| **560208** | FURNISH SIGN STRUCTURE (TUBULAR) | KG | 2 | 1 | 57,231.00 | $11.50 | $658,156.50 |
| | | KG | 7 | 1 | 22,665.00 | $13.00 | $294,645.00 |
| | | KG | 11 | 5 | 719,744.00 | $11.51 | $8,282,260.00 |
| | **Unit Sub Total** | **KG** | | **7** | **799,640.00** | **$11.55** | **$9,235,061.50** |
| | **Item Code 560208 Total No. of Proj.** | | | **7** | | **Total Amount** | **$9,235,061.50** |
| **560209** | INSTALL SIGN STRUCTURE (TUBULAR) | KG | 2 | 1 | 57,231.00 | $1.25 | $71,538.75 |
| | | KG | 7 | 1 | 22,665.00 | $1.20 | $27,198.00 |
| | | KG | 11 | 5 | 719,744.00 | $1.09 | $781,409.00 |
| | **Unit Sub Total** | **KG** | | **7** | **799,640.00** | **$1.10** | **$880,145.75** |
| | **Item Code 560209 Total No. of Proj.** | | | **7** | | **Total Amount** | **$880,145.75** |
| **560213** | FURNISH SIGN STRUCTURE (LIGHTWEIGHT) | KG | 3 | 2 | 5,868.00 | $12.94 | $75,946.00 |
| | | KG | 7 | 1 | 908.00 | $45.00 | $40,860.00 |
| | | KG | 11 | 6 | 68,358.00 | $11.46 | $783,296.00 |
| | **Unit Sub Total** | **KG** | | **9** | **75,134.00** | **$11.98** | **$900,102.00** |
| **560213** | FURNISH SIGN STRUCTURE (LIGHTWEIGHT) | LB | 4 | 1 | 2,900.00 | $30.00 | $87,000.00 |
| | | LB | 12 | 2 | 25,400.00 | $4.94 | $125,560.00 |
| | **Unit Sub Total** | **LB** | | **3** | **28,300.00** | **$7.51** | **$212,560.00** |
| | **Item Code 560213 Total No. of Proj.** | | | **12** | | **Total Amount** | **$1,112,662.00** |
| **560214** | INSTALL SIGN STRUCTURE (LIGHTWEIGHT) | KG | 3 | 2 | 5,868.00 | $3.00 | $17,604.00 |
| | | KG | 7 | 1 | 908.00 | $10.00 | $9,080.00 |
| | | KG | 11 | 6 | 68,358.00 | $1.44 | $98,672.00 |
| | **Unit Sub Total** | **KG** | | **9** | **75,134.00** | **$1.67** | **$125,356.00** |
| **560214** | INSTALL SIGN STRUCTURE (LIGHTWEIGHT) | LB | 4 | 1 | 2,900.00 | $1.20 | $3,480.00 |
| | | LB | 12 | 2 | 25,400.00 | $1.00 | $25,400.00 |
| | **Unit Sub Total** | **LB** | | **3** | **28,300.00** | **$1.02** | **$28,880.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | **Item Code 560214** | **Total No. of Proj.** | | | **12** | | **Total Amount** | **$154,236.00** |
| **560218** | FURNISH SIGN STRUCTURE (TRUSS) | | KG | 3 | 3 | 172,803.00 | $10.91 | $1,885,207.50 |
| | | | KG | 4 | 6 | 705,515.00 | $11.45 | $8,076,445.00 |
| | | | KG | 5 | 4 | 144,841.00 | $11.20 | $1,622,880.70 |
| | | | KG | 7 | 7 | 503,512.00 | $12.35 | $6,217,146.10 |
| | | | KG | 8 | 2 | 25,490.00 | $14.16 | $360,877.20 |
| | | | KG | 10 | 2 | 77,235.00 | $10.28 | $794,068.20 |
| | | | KG | 11 | 4 | 334,230.00 | $10.23 | $3,419,760.00 |
| | | | KG | 12 | 1 | 30,800.00 | $10.50 | $323,400.00 |
| | | **Unit Sub Total** | **KG** | | **29** | **1,994,426.00** | **$11.38** | **$22,699,784.70** |
| **560218** | FURNISH SIGN STRUCTURE (TRUSS) | | LB | 3 | 7 | 776,404.00 | $5.23 | $4,059,299.45 |
| | | | LB | 5 | 1 | 29,031.00 | $5.00 | $145,155.00 |
| | | | LB | 6 | 1 | 18,200.00 | $5.00 | $91,000.00 |
| | | | LB | 10 | 1 | 13,896.00 | $5.00 | $69,480.00 |
| | | | LB | 11 | 1 | 3,120.00 | $10.00 | $31,200.00 |
| | | | LB | 12 | 3 | 171,304.00 | $5.08 | $870,020.00 |
| | | **Unit Sub Total** | **LB** | | **14** | **1,011,955.00** | **$5.20** | **$5,266,154.45** |
| | **Item Code 560218** | **Total No. of Proj.** | | | **43** | | **Total Amount** | **$27,965,939.15** |
| **560219** | INSTALL SIGN STRUCTURE (TRUSS) | | KG | 3 | 2 | 170,241.00 | $0.93 | $158,578.40 |
| | | | KG | 4 | 6 | 705,515.00 | $0.55 | $386,755.50 |
| | | | KG | 5 | 4 | 144,841.00 | $1.20 | $173,629.02 |
| | | | KG | 7 | 7 | 503,512.00 | $0.54 | $269,706.80 |
| | | | KG | 8 | 2 | 25,490.00 | $0.95 | $24,169.00 |
| | | | KG | 10 | 2 | 77,235.00 | $0.54 | $41,707.60 |
| | | | KG | 11 | 4 | 334,150.00 | $1.14 | $379,842.00 |
| | | | KG | 12 | 1 | 30,800.00 | $0.80 | $24,640.00 |
| | | **Unit Sub Total** | **KG** | | **28** | **1,991,784.00** | **$0.73** | **$1,459,028.32** |
| **560219** | INSTALL SIGN STRUCTURE (TRUSS) | | LB | 3 | 7 | 757,410.00 | $0.36 | $270,629.60 |
| | | | LB | 5 | 1 | 29,031.00 | $1.00 | $29,031.00 |
| | | | LB | 6 | 1 | 18,200.00 | $0.50 | $9,100.00 |
| | | | LB | 10 | 1 | 13,896.00 | $1.00 | $13,896.00 |
| | | | LB | 12 | 3 | 171,304.00 | $0.72 | $123,826.00 |
| | | **Unit Sub Total** | **LB** | | **13** | **989,841.00** | **$0.45** | **$446,482.60** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 560219 Total No. of Proj.** | | | **41** | | **Total Amount** | **$1,905,510.92** |
| **560223** | FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY) | KG | 11 | 2 | 7,000.00 | $15.57 | $109,000.00 |
| | **Unit Sub Total** | **KG** | | **2** | **7,000.00** | **$15.57** | **$109,000.00** |
| | **Item Code 560223 Total No. of Proj.** | | | **2** | | **Total Amount** | **$109,000.00** |
| **560224** | INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY) | KG | 11 | 2 | 7,000.00 | $4.86 | $34,000.00 |
| | **Unit Sub Total** | **KG** | | **2** | **7,000.00** | **$4.86** | **$34,000.00** |
| | **Item Code 560224 Total No. of Proj.** | | | **2** | | **Total Amount** | **$34,000.00** |
| **560232** | FURNISH FORMED PANEL SIGN (ROADSIDE) | M2 | 5 | 2 | 3.10 | $250.00 | $775.00 |
| | **Unit Sub Total** | **M2** | | **2** | **3.10** | **$250.00** | **$775.00** |
| | **Item Code 560232 Total No. of Proj.** | | | **2** | | **Total Amount** | **$775.00** |
| **560233** | FURNISH FORMED PANEL SIGN (OVERHEAD) | M2 | 4 | 7 | 1,886.00 | $133.78 | $252,302.00 |
| | | M2 | 5 | 3 | 499.00 | $122.23 | $60,992.00 |
| | | M2 | 7 | 5 | 1,501.00 | $102.63 | $154,050.80 |
| | | M2 | 8 | 1 | 77.00 | $145.00 | $11,165.00 |
| | **Unit Sub Total** | **M2** | | **16** | **3,963.00** | **$120.74** | **$478,509.80** |
| **560233** | FURNISH FORMED PANEL SIGN (OVERHEAD) | SQFT | 3 | 3 | 1,968.00 | $11.23 | $22,094.00 |
| | | SQFT | 8 | 2 | 4,380.00 | $11.12 | $48,720.00 |
| | **Unit Sub Total** | **SQFT** | | **5** | **6,348.00** | **$11.16** | **$70,814.00** |
| | **Item Code 560233 Total No. of Proj.** | | | **21** | | **Total Amount** | **$549,323.80** |
| **560234** | FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE A) | M2 | 2 | 1 | 160.00 | $160.00 | $25,600.00 |
| | | M2 | 3 | 1 | 270.00 | $155.00 | $41,850.00 |
| | | M2 | 4 | 3 | 98.00 | $210.71 | $20,650.00 |
| | | M2 | 5 | 2 | 580.00 | $160.86 | $93,300.00 |
| | | M2 | 7 | 3 | 439.60 | $146.12 | $64,232.84 |
| | | M2 | 10 | 1 | 28.00 | $60.00 | $1,680.00 |
| | | M2 | 11 | 8 | 2,700.00 | $167.14 | $451,270.00 |
| | | M2 | 12 | 1 | 38.00 | $200.00 | $7,600.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M2** | | **20** | **4,313.60** | **$163.71** | **$706,182.84** |
| | **Item Code 560234** | **Total No. of Proj.** | | | **20** | | **Total Amount** | **$706,182.84** |
| **560235** | FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE B) | | M2 | 2 | 1 | 7.00 | $160.00 | $1,120.00 |
| | | | M2 | 3 | 2 | 38.00 | $220.00 | $8,360.00 |
| | | | M2 | 4 | 2 | 55.00 | $236.00 | $12,980.00 |
| | | | M2 | 5 | 1 | 120.00 | $200.00 | $24,000.00 |
| | | | M2 | 7 | 3 | 55.00 | $196.69 | $10,817.90 |
| | | | M2 | 8 | 1 | 49.00 | $155.00 | $7,595.00 |
| | | | M2 | 9 | 1 | 6.00 | $200.00 | $1,200.00 |
| | | | M2 | 11 | 2 | 113.00 | $190.58 | $21,535.00 |
| | | **Unit Sub Total** | **M2** | | **13** | **443.00** | **$197.76** | **$87,607.90** |
| | **Item Code 560235** | **Total No. of Proj.** | | | **13** | | **Total Amount** | **$87,607.90** |
| **560236** | FURNISH LAMINATED PANEL SIGN (63.5 MM-TYPE B) | | M2 | 2 | 1 | 20.00 | $170.00 | $3,400.00 |
| | | | M2 | 8 | 1 | 80.00 | $170.00 | $13,600.00 |
| | | **Unit Sub Total** | **M2** | | **2** | **100.00** | **$170.00** | **$17,000.00** |
| | **Item Code 560236** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$17,000.00** |
| **560238** | FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-UNFRAMED) | | M2 | 1 | 1 | 19.00 | $175.00 | $3,325.00 |
| | | | M2 | 2 | 2 | 85.50 | $98.31 | $8,405.50 |
| | | | M2 | 3 | 4 | 82.80 | $123.66 | $10,239.00 |
| | | | M2 | 4 | 8 | 218.30 | $119.08 | $25,996.00 |
| | | | M2 | 5 | 6 | 135.80 | $137.97 | $18,737.00 |
| | | | M2 | 6 | 6 | 133.50 | $112.90 | $15,072.00 |
| | | | M2 | 7 | 8 | 105.00 | $104.19 | $10,939.50 |
| | | | M2 | 8 | 2 | 7.20 | $133.00 | $957.60 |
| | | | M2 | 9 | 3 | 216.00 | $121.11 | $26,160.00 |
| | | | M2 | 10 | 8 | 92.80 | $138.55 | $12,857.00 |
| | | | M2 | 11 | 11 | 608.00 | $108.24 | $65,812.00 |
| | | | M2 | 12 | 4 | 22.40 | $108.93 | $2,440.00 |
| | | **Unit Sub Total** | **M2** | | **63** | **1,726.30** | **$116.40** | **$200,940.60** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **560238** | FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-UNFRAMED) | SQFT | 8 | 2 | 16.30 | $26.75 | $436.00 |
| | **Unit Sub Total** | **SQFT** | | **2** | **16.30** | **$26.75** | **$436.00** |
| | **Item Code 560238 Total No. of Proj.** | | | **65** | | **Total Amount** | **$201,376.60** |
| **560239** | FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-UNFRAMED) | M2 | 1 | 1 | 31.00 | $110.00 | $3,410.00 |
| | | M2 | 2 | 1 | 41.00 | $90.00 | $3,690.00 |
| | | M2 | 3 | 4 | 98.80 | $132.37 | $13,078.00 |
| | | M2 | 4 | 8 | 90.20 | $154.67 | $13,951.60 |
| | | M2 | 5 | 5 | 164.50 | $132.99 | $21,877.00 |
| | | M2 | 6 | 2 | 18.20 | $138.46 | $2,520.00 |
| | | M2 | 7 | 9 | 161.80 | $144.25 | $23,339.00 |
| | | M2 | 8 | 2 | 50.00 | $116.00 | $5,800.00 |
| | | M2 | 9 | 3 | 217.00 | $128.77 | $27,943.00 |
| | | M2 | 10 | 5 | 59.40 | $88.53 | $5,258.80 |
| | | M2 | 11 | 9 | 386.00 | $112.51 | $43,430.00 |
| | | M2 | 12 | 1 | 28.00 | $100.00 | $2,800.00 |
| | **Unit Sub Total** | **M2** | | **50** | **1,345.90** | **$124.15** | **$167,097.40** |
| | **Item Code 560239 Total No. of Proj.** | | | **50** | | **Total Amount** | **$167,097.40** |
| **560241** | FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-FRAMED) | M2 | 2 | 1 | 27.00 | $100.00 | $2,700.00 |
| | | M2 | 3 | 3 | 29.00 | $117.07 | $3,395.00 |
| | | M2 | 4 | 5 | 40.40 | $192.33 | $7,770.00 |
| | | M2 | 5 | 1 | 20.00 | $147.00 | $2,940.00 |
| | | M2 | 7 | 2 | 263.00 | $149.26 | $39,255.00 |
| | | M2 | 9 | 2 | 4.10 | $163.41 | $670.00 |
| | | M2 | 10 | 3 | 41.00 | $210.37 | $8,625.00 |
| | | M2 | 11 | 10 | 249.00 | $136.77 | $34,055.00 |
| | **Unit Sub Total** | **M2** | | **27** | **673.50** | **$147.60** | **$99,410.00** |
| | **Item Code 560241 Total No. of Proj.** | | | **27** | | **Total Amount** | **$99,410.00** |
| **560242** | FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-FRAMED) | M2 | 1 | 1 | 22.00 | $175.00 | $3,850.00 |
| | | M2 | 2 | 1 | 24.00 | $100.00 | $2,400.00 |
| | | M2 | 3 | 2 | 25.00 | $158.60 | $3,965.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **560242** | FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-FRAMED) | M2 | 4 | 3 | 75.00 | $178.80 | $13,410.00 |
| | | M2 | 5 | 1 | 24.00 | $165.00 | $3,960.00 |
| | | M2 | 7 | 3 | 20.00 | $132.53 | $2,650.50 |
| | | M2 | 9 | 3 | 38.00 | $165.58 | $6,292.00 |
| | | M2 | 10 | 2 | 11.90 | $121.76 | $1,449.00 |
| | | M2 | 11 | 9 | 258.00 | $157.53 | $40,644.00 |
| | **Unit Sub Total** | **M2** | | **25** | **497.90** | **$157.90** | **$78,620.50** |
| | **Item Code 560242 Total No. of Proj.** | | | **25** | | **Total Amount** | **$78,620.50** |
| **560244** | FURNISH LAMINATED PANEL SIGN (1"-TYPE A) | SQFT | 3 | 5 | 17,358.00 | $16.18 | $280,796.00 |
| | | SQFT | 4 | 2 | 117.00 | $30.17 | $3,530.00 |
| | | SQFT | 6 | 1 | 200.00 | $17.00 | $3,400.00 |
| | | SQFT | 8 | 2 | 10,730.00 | $18.78 | $201,540.00 |
| | | SQFT | 11 | 2 | 2,050.00 | $15.71 | $32,200.00 |
| | | SQFT | 12 | 3 | 2,010.00 | $14.96 | $30,060.00 |
| | **Unit Sub Total** | **SQFT** | | **15** | **32,465.00** | **$16.99** | **$551,526.00** |
| | **Item Code 560244 Total No. of Proj.** | | | **15** | | **Total Amount** | **$551,526.00** |
| **560245** | FURNISH LAMINATED PANEL SIGN (1"-TYPE B) | SQFT | 3 | 1 | 60.00 | $20.00 | $1,200.00 |
| | | SQFT | 7 | 1 | 6.30 | $45.00 | $283.50 |
| | | SQFT | 8 | 3 | 10,140.00 | $21.16 | $214,580.00 |
| | **Unit Sub Total** | **SQFT** | | **5** | **10,206.30** | **$21.17** | **$216,063.50** |
| | **Item Code 560245 Total No. of Proj.** | | | **5** | | **Total Amount** | **$216,063.50** |
| **560246** | FURNISH LAMINATED PANEL SIGN (2 1/2"-TYPE B) | SQFT | 8 | 2 | 9,820.00 | $21.48 | $210,940.00 |
| | **Unit Sub Total** | **SQFT** | | **2** | **9,820.00** | **$21.48** | **$210,940.00** |
| | **Item Code 560246 Total No. of Proj.** | | | **2** | | **Total Amount** | **$210,940.00** |
| **560248** | FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED) | SQFT | 1 | 1 | 24.00 | $17.50 | $420.00 |
| | | SQFT | 2 | 6 | 344.00 | $25.63 | $8,815.00 |
| | | SQFT | 3 | 5 | 369.20 | $14.89 | $5,496.80 |
| | | SQFT | 4 | 4 | 1,084.00 | $16.99 | $18,420.00 |
| | | SQFT | 5 | 2 | 171.00 | $17.28 | $2,955.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **560248** | FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED) | SQFT | 6 | 2 | 390.00 | $8.72 | $3,400.00 |
| | | SQFT | 7 | 6 | 517.00 | $14.78 | $7,642.50 |
| | | SQFT | 8 | 11 | 954.00 | $12.99 | $12,395.44 |
| | | SQFT | 10 | 3 | 66.00 | $13.65 | $901.00 |
| | | SQFT | 11 | 6 | 531.00 | $13.14 | $6,976.00 |
| | | SQFT | 12 | 22 | 1,517.00 | $11.78 | $17,873.72 |
| | **Unit Sub Total** | **SQFT** | | **68** | **5,967.20** | **$14.29** | **$85,295.46** |
| | **Item Code 560248 Total No. of Proj.** | | | **68** | | **Total Amount** | **$85,295.46** |
| **560249** | FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED) | SQFT | 1 | 1 | 14.00 | $22.00 | $308.00 |
| | | SQFT | 2 | 2 | 163.00 | $17.18 | $2,800.00 |
| | | SQFT | 3 | 3 | 709.00 | $21.70 | $15,386.00 |
| | | SQFT | 4 | 2 | 110.00 | $33.82 | $3,720.00 |
| | | SQFT | 5 | 2 | 103.50 | $15.29 | $1,582.50 |
| | | SQFT | 6 | 2 | 940.00 | $8.92 | $8,388.00 |
| | | SQFT | 7 | 3 | 76.00 | $36.74 | $2,792.00 |
| | | SQFT | 8 | 4 | 4,516.00 | $13.00 | $58,728.00 |
| | | SQFT | 10 | 1 | 88.00 | $12.50 | $1,100.00 |
| | | SQFT | 11 | 3 | 107.00 | $13.48 | $1,442.00 |
| | | SQFT | 12 | 13 | 1,149.00 | $14.95 | $17,174.00 |
| | **Unit Sub Total** | **SQFT** | | **36** | **7,975.50** | **$14.22** | **$113,420.50** |
| | **Item Code 560249 Total No. of Proj.** | | | **36** | | **Total Amount** | **$113,420.50** |
| **560251** | FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED) | SQFT | 3 | 2 | 210.00 | $19.71 | $4,140.00 |
| | | SQFT | 4 | 1 | 44.00 | $10.00 | $440.00 |
| | | SQFT | 6 | 1 | 40.00 | $8.00 | $320.00 |
| | | SQFT | 8 | 2 | 99.00 | $16.70 | $1,653.00 |
| | | SQFT | 10 | 1 | 36.00 | $14.20 | $511.20 |
| | | SQFT | 11 | 2 | 134.00 | $14.27 | $1,912.00 |
| | | SQFT | 12 | 3 | 300.00 | $10.44 | $3,131.00 |
| | **Unit Sub Total** | **SQFT** | | **12** | **863.00** | **$14.03** | **$12,107.20** |
| | **Item Code 560251 Total No. of Proj.** | | | **12** | | **Total Amount** | **$12,107.20** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **560252** | FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED) | SQFT | 3 | 2 | 275.00 | $24.24 | $6,665.00 |
| | | SQFT | 7 | 1 | 45.00 | $18.00 | $810.00 |
| | | SQFT | 8 | 4 | 265.00 | $17.60 | $4,665.00 |
| | | SQFT | 10 | 1 | 16.00 | $12.00 | $192.00 |
| | | SQFT | 11 | 3 | 476.00 | $19.30 | $9,186.00 |
| | | SQFT | 12 | 3 | 312.00 | $12.54 | $3,912.00 |
| | **Unit Sub Total** | **SQFT** | | **14** | **1,389.00** | **$18.31** | **$25,430.00** |
| | **Item Code 560252 Total No. of Proj.** | | | **14** | | **Total Amount** | **$25,430.00** |
| **561005** | 36" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | LF | 12 | 2 | 79.00 | $398.73 | $31,500.00 |
| | **Unit Sub Total** | **LF** | | **2** | **79.00** | **$398.73** | **$31,500.00** |
| | **Item Code 561005 Total No. of Proj.** | | | **2** | | **Total Amount** | **$31,500.00** |
| **561008** | 760 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | M | 3 | 1 | 4.00 | $2,000.00 | $8,000.00 |
| | | M | 7 | 1 | 3.40 | $1,100.00 | $3,740.00 |
| | **Unit Sub Total** | **M** | | **2** | **7.40** | **$1,586.49** | **$11,740.00** |
| | **Item Code 561008 Total No. of Proj.** | | | **2** | | **Total Amount** | **$11,740.00** |
| **561009** | 920 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | M | 11 | 5 | 105.00 | $2,454.76 | $257,750.00 |
| | **Unit Sub Total** | **M** | | **5** | **105.00** | **$2,454.76** | **$257,750.00** |
| | **Item Code 561009 Total No. of Proj.** | | | **5** | | **Total Amount** | **$257,750.00** |
| **561011** | 48" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | LF | 3 | 2 | 90.00 | $2,498.00 | $224,820.00 |
| | **Unit Sub Total** | **LF** | | **2** | **90.00** | **$2,498.00** | **$224,820.00** |
| | **Item Code 561011 Total No. of Proj.** | | | **2** | | **Total Amount** | **$224,820.00** |
| **561013** | 1372 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | M | 3 | 2 | 42.00 | $6,069.05 | $254,900.00 |
| | | M | 4 | 3 | 60.00 | $3,030.00 | $181,800.00 |
| | | M | 5 | 1 | 29.00 | $2,300.00 | $66,700.00 |
| | | M | 7 | 2 | 12.00 | $2,800.00 | $33,600.00 |
| | | M | 10 | 1 | 24.00 | $2,295.00 | $55,080.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **561013** | 1372 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | M | 11 | 2 | 44.00 | $3,329.55 | $146,500.00 |
| | | M | 12 | 1 | 16.00 | $3,000.00 | $48,000.00 |
| | **Unit Sub Total** | **M** | | **12** | **227.00** | **$3,465.11** | **$786,580.00** |
| | **Item Code 561013 Total No. of Proj.** | | | **12** | | **Total Amount** | **$786,580.00** |
| **561014** | 54" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | LF | 3 | 4 | 337.00 | $859.64 | $289,700.00 |
| | | LF | 12 | 1 | 40.00 | $480.00 | $19,200.00 |
| | **Unit Sub Total** | **LF** | | **5** | **377.00** | **$819.36** | **$308,900.00** |
| | **Item Code 561014 Total No. of Proj.** | | | **5** | | **Total Amount** | **$308,900.00** |
| **561015** | 1524 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | M | 2 | 1 | 86.00 | $3,750.00 | $322,500.00 |
| | | M | 3 | 2 | 116.00 | $3,295.69 | $382,300.00 |
| | | M | 4 | 6 | 550.60 | $3,136.56 | $1,726,990.00 |
| | | M | 5 | 4 | 70.00 | $2,782.43 | $194,770.00 |
| | | M | 7 | 6 | 363.80 | $2,389.95 | $869,462.40 |
| | | M | 8 | 2 | 25.80 | $3,017.98 | $77,864.00 |
| | | M | 10 | 2 | 56.00 | $2,788.26 | $156,142.50 |
| | | M | 11 | 7 | 771.00 | $2,618.94 | $2,019,200.00 |
| | | M | 12 | 1 | 20.00 | $4,000.00 | $80,000.00 |
| | **Unit Sub Total** | **M** | | **31** | **2,059.20** | **$2,830.82** | **$5,829,228.90** |
| | **Item Code 561015 Total No. of Proj.** | | | **31** | | **Total Amount** | **$5,829,228.90** |
| **561016** | 60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION) | LF | 3 | 3 | 679.00 | $1,459.50 | $991,000.00 |
| | | LF | 5 | 1 | 44.00 | $1,000.00 | $44,000.00 |
| | | LF | 6 | 1 | 23.00 | $700.00 | $16,100.00 |
| | | LF | 10 | 1 | 22.00 | $750.00 | $16,500.00 |
| | | LF | 12 | 2 | 165.00 | $600.00 | $99,000.00 |
| | **Unit Sub Total** | **LF** | | **8** | **933.00** | **$1,250.38** | **$1,166,600.00** |
| | **Item Code 561016 Total No. of Proj.** | | | **8** | | **Total Amount** | **$1,166,600.00** |
| **562002** | METAL (BARRIER MOUNTED SIGN) | KG | 2 | 1 | 82.00 | $25.00 | $2,050.00 |
| | | KG | 4 | 2 | 6,720.00 | $10.33 | $69,432.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **562002** | METAL (BARRIER MOUNTED SIGN) | | KG | 7 | 2 | 1,820.00 | $23.65 | $43,050.00 |
| | | | KG | 11 | 1 | 200.00 | $26.00 | $5,200.00 |
| | | **Unit Sub Total** | **KG** | | **6** | **8,822.00** | **$13.57** | **$119,732.00** |
| **562002** | METAL (BARRIER MOUNTED SIGN) | | LB | 11 | 1 | 82.00 | $20.00 | $1,640.00 |
| | | | LB | 12 | 1 | 1,830.00 | $6.50 | $11,895.00 |
| | | **Unit Sub Total** | **LB** | | **2** | **1,912.00** | **$7.08** | **$13,535.00** |
| | **Item Code 562002** | **Total No. of Proj.** | | | **8** | | **Total Amount** | **$133,267.00** |
| **562004** | METAL (RAIL MOUNTED SIGN) | | KG | 4 | 3 | 4,550.00 | $15.62 | $71,078.00 |
| | | | KG | 7 | 1 | 110.00 | $12.00 | $1,320.00 |
| | | | KG | 11 | 5 | 4,680.00 | $29.90 | $139,920.00 |
| | | **Unit Sub Total** | **KG** | | **9** | **9,340.00** | **$22.73** | **$212,318.00** |
| **562004** | METAL (RAIL MOUNTED SIGN) | | LB | 4 | 1 | 2,160.00 | $8.00 | $17,280.00 |
| | | **Unit Sub Total** | **LB** | | **1** | **2,160.00** | **$8.00** | **$17,280.00** |
| | **Item Code 562004** | **Total No. of Proj.** | | | **10** | | **Total Amount** | **$229,598.00** |
| **562007** | ROADSIDE SIGN (METAL POST) | | EA | 7 | 2 | 10.00 | $310.00 | $3,100.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **10.00** | **$310.00** | **$3,100.00** |
| | **Item Code 562007** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$3,100.00** |
| **566011** | ROADSIDE SIGN - ONE POST | | EA | 1 | 7 | 125.00 | $339.92 | $42,490.00 |
| | | | EA | 2 | 10 | 101.00 | $358.66 | $36,225.00 |
| | | | EA | 3 | 13 | 710.00 | $267.93 | $190,233.00 |
| | | | EA | 4 | 12 | 84.00 | $240.88 | $20,234.00 |
| | | | EA | 5 | 13 | 271.00 | $324.15 | $87,844.00 |
| | | | EA | 6 | 11 | 165.00 | $182.45 | $30,105.00 |
| | | | EA | 7 | 15 | 403.00 | $335.45 | $135,187.00 |
| | | | EA | 8 | 14 | 323.00 | $434.01 | $140,185.98 |
| | | | EA | 9 | 3 | 230.00 | $314.82 | $72,408.00 |
| | | | EA | 10 | 12 | 182.00 | $199.19 | $36,252.60 |
| | | | EA | 11 | 15 | 476.00 | $401.29 | $191,015.00 |
| | | | EA | 12 | 19 | 110.00 | $362.04 | $39,824.35 |
| | | **Unit Sub Total** | **EA** | | **144** | **3,180.00** | **$321.38** | **$1,022,003.93** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 566011 Total No. of Proj.** | | | **144** | | **Total Amount** | **$1,022,003.93** |
| **566012** | ROADSIDE SIGN - TWO POST | EA | 1 | 3 | 10.00 | $685.00 | $6,850.00 |
| | | EA | 2 | 1 | 23.00 | $700.00 | $16,100.00 |
| | | EA | 3 | 9 | 119.00 | $457.85 | $54,484.00 |
| | | EA | 4 | 9 | 32.00 | $446.19 | $14,278.10 |
| | | EA | 5 | 4 | 17.00 | $577.35 | $9,815.00 |
| | | EA | 6 | 1 | 8.00 | $220.00 | $1,760.00 |
| | | EA | 7 | 6 | 24.00 | $752.08 | $18,050.00 |
| | | EA | 8 | 6 | 49.00 | $553.06 | $27,100.00 |
| | | EA | 9 | 3 | 19.00 | $620.11 | $11,782.00 |
| | | EA | 10 | 5 | 24.00 | $286.67 | $6,880.00 |
| | | EA | 11 | 12 | 91.00 | $1,084.07 | $98,650.00 |
| | | EA | 12 | 8 | 38.00 | $963.95 | $36,630.00 |
| | **Unit Sub Total** | **EA** | | **67** | **454.00** | **$666.03** | **$302,379.10** |
| | **Item Code 566012 Total No. of Proj.** | | | **67** | | **Total Amount** | **$302,379.10** |
| **566013** | ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD) | EA | 7 | 1 | 1.00 | $100.00 | $100.00 |
| | | EA | 12 | 1 | 1.00 | $100.00 | $100.00 |
| | **Unit Sub Total** | **EA** | | **2** | **2.00** | **$100.00** | **$200.00** |
| | **Item Code 566013 Total No. of Proj.** | | | **2** | | **Total Amount** | **$200.00** |
| **568001** | INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD) | EA | 2 | 1 | 28.00 | $350.00 | $9,800.00 |
| | | EA | 3 | 8 | 110.00 | $106.09 | $11,670.00 |
| | | EA | 4 | 4 | 73.00 | $172.45 | $12,588.80 |
| | | EA | 5 | 2 | 10.00 | $115.40 | $1,154.00 |
| | | EA | 6 | 1 | 21.00 | $85.00 | $1,785.00 |
| | | EA | 7 | 8 | 127.00 | $89.41 | $11,355.00 |
| | | EA | 11 | 12 | 154.00 | $106.75 | $16,440.00 |
| | | EA | 12 | 14 | 76.00 | $109.29 | $8,306.13 |
| | **Unit Sub Total** | **EA** | | **50** | **599.00** | **$122.03** | **$73,098.93** |
| | **Item Code 568001 Total No. of Proj.** | | | **50** | | **Total Amount** | **$73,098.93** |
| **568007** | INSTALL SIGN OVERLAY | EA | 3 | 1 | 1.00 | $525.00 | $525.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **568007** | INSTALL SIGN OVERLAY | EA | 4 | 1 | 4.00 | $1,880.00 | $7,520.00 |
| | | EA | 5 | 1 | 1.00 | $1,500.00 | $1,500.00 |
| | | EA | 6 | 1 | 4.00 | $500.00 | $2,000.00 |
| | **Unit Sub Total** | **EA** | | **4** | **10.00** | **$1,154.50** | **$11,545.00** |
| **568007** | INSTALL SIGN OVERLAY | M2 | 3 | 1 | 4.00 | $500.00 | $2,000.00 |
| | | M2 | 4 | 1 | 3.00 | $100.00 | $300.00 |
| | | M2 | 7 | 1 | 3.00 | $190.00 | $570.00 |
| | | M2 | 11 | 1 | 5.30 | $750.00 | $3,975.00 |
| | **Unit Sub Total** | **M2** | | **4** | **15.30** | **$447.39** | **$6,845.00** |
| **568007** | INSTALL SIGN OVERLAY | SQFT | 6 | 1 | 36.00 | $20.00 | $720.00 |
| | | SQFT | 8 | 2 | 340.00 | $28.24 | $9,600.00 |
| | | SQFT | 11 | 1 | 36.00 | $20.00 | $720.00 |
| | **Unit Sub Total** | **SQFT** | | **4** | **412.00** | **$26.80** | **$11,040.00** |
| | **Item Code 568007 Total No. of Proj.** | | | **12** | | **Total Amount** | **$29,430.00** |
| **568015** | INSTALL SIGN (MAST-ARM HANGER METHOD) | EA | 7 | 1 | 3.00 | $250.00 | $750.00 |
| | **Unit Sub Total** | **EA** | | **1** | **3.00** | **$250.00** | **$750.00** |
| | **Item Code 568015 Total No. of Proj.** | | | **1** | | **Total Amount** | **$750.00** |
| **568016** | INSTALL SIGN PANEL ON EXISTING FRAME | EA | 5 | 1 | 1.00 | $750.00 | $750.00 |
| | | EA | 8 | 2 | 112.00 | $793.75 | $88,900.00 |
| | | EA | 9 | 1 | 2.00 | $600.00 | $1,200.00 |
| | **Unit Sub Total** | **EA** | | **4** | **115.00** | **$790.00** | **$90,850.00** |
| **568016** | INSTALL SIGN PANEL ON EXISTING FRAME | M2 | 3 | 3 | 155.00 | $130.77 | $20,270.00 |
| | | M2 | 4 | 3 | 322.00 | $112.05 | $36,080.00 |
| | | M2 | 7 | 4 | 1,366.00 | $41.48 | $56,660.00 |
| | **Unit Sub Total** | **M2** | | **10** | **1,843.00** | **$61.32** | **$113,010.00** |
| **568016** | INSTALL SIGN PANEL ON EXISTING FRAME | SQFT | 3 | 4 | 6,787.00 | $8.92 | $60,519.00 |
| | | SQFT | 4 | 1 | 58.00 | $10.00 | $580.00 |
| | **Unit Sub Total** | **SQFT** | | **5** | **6,845.00** | **$8.93** | **$61,099.00** |
| | **Item Code 568016 Total No. of Proj.** | | | **19** | | **Total Amount** | **$264,959.00** |
| **568017** | INSTALL ROADSIDE SIGN PANEL ON EXISTING POST | EA | 3 | 1 | 3.00 | $500.00 | $1,500.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **568017** | INSTALL ROADSIDE SIGN PANEL ON EXISTING POST | EA | 4 | 2 | 5.00 | $220.00 | $1,100.00 |
| | | EA | 5 | 2 | 8.00 | $137.50 | $1,100.00 |
| | | EA | 7 | 2 | 5.00 | $274.00 | $1,370.00 |
| | | EA | 8 | 7 | 75.00 | $405.63 | $30,422.00 |
| | | EA | 9 | 1 | 1.00 | $100.00 | $100.00 |
| | | EA | 10 | 1 | 1.00 | $100.00 | $100.00 |
| | | EA | 11 | 9 | 236.00 | $192.75 | $45,490.00 |
| | | EA | 12 | 9 | 57.00 | $143.75 | $8,193.66 |
| | **Unit Sub Total** | **EA** | | **34** | **391.00** | **$228.58** | **$89,375.66** |
| | **Item Code 568017 Total No. of Proj.** | | | **34** | | **Total Amount** | **$89,375.66** |
| **568020** | INSTALL SIGN PANEL ON EXISTING STRUCTURE | M2 | 4 | 1 | 48.00 | $50.00 | $2,400.00 |
| | | M2 | 11 | 1 | 34.00 | $300.00 | $10,200.00 |
| | **Unit Sub Total** | **M2** | | **2** | **82.00** | **$153.66** | **$12,600.00** |
| | **Item Code 568020 Total No. of Proj.** | | | **2** | | **Total Amount** | **$12,600.00** |
| **568023** | INSTALL ROADSIDE SIGN (LAMINATED WOOD BOX POST) | EA | 1 | 2 | 7.00 | $1,614.29 | $11,300.00 |
| | | EA | 2 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | | EA | 3 | 1 | 1.00 | $2,100.00 | $2,100.00 |
| | | EA | 4 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | | EA | 5 | 2 | 17.00 | $1,826.76 | $31,055.00 |
| | | EA | 7 | 2 | 9.00 | $2,366.67 | $21,300.00 |
| | | EA | 8 | 3 | 134.00 | $1,271.08 | $170,325.00 |
| | | EA | 10 | 1 | 1.00 | $1,326.00 | $1,326.00 |
| | **Unit Sub Total** | **EA** | | **13** | **171.00** | **$1,405.88** | **$240,406.00** |
| | **Item Code 568023 Total No. of Proj.** | | | **13** | | **Total Amount** | **$240,406.00** |
| **575004** | TIMBER LAGGING | M3 | 1 | 2 | 163.00 | $1,128.83 | $184,000.00 |
| | | M3 | 4 | 2 | 118.00 | $1,203.39 | $142,000.00 |
| | | M3 | 5 | 1 | 91.00 | $1,200.00 | $109,200.00 |
| | | M3 | 7 | 1 | 13.00 | $5,000.00 | $65,000.00 |
| | | M3 | 11 | 4 | 166.00 | $1,936.14 | $321,400.00 |
| | **Unit Sub Total** | **M3** | | **10** | **551.00** | **$1,491.11** | **$821,600.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **575004** | TIMBER LAGGING | MFBM | 1 | 1 | 72.00 | $3,000.00 | $216,000.00 |
| | | MFBM | 8 | 1 | 10.00 | $3,000.00 | $30,000.00 |
| | **Unit Sub Total** | **MFBM** | | **2** | **82.00** | **$3,000.00** | **$246,000.00** |
| | **Item Code 575004 Total No. of Proj.** | | | **12** | | **Total Amount** | **$1,067,600.00** |
| **590106** | CLEAN STRUCTURAL STEEL (EXISTING BRIDGE) | LS | 1 | 1 | 1.00 | $692,500.00 | $692,500.00 |
| | | LS | 5 | 2 | 2.00 | $91,004.50 | $182,009.00 |
| | | LS | 11 | 1 | 1.00 | $26,500.00 | $26,500.00 |
| | **Unit Sub Total** | **LS** | | **4** | **4.00** | **$225,252.25** | **$901,009.00** |
| | **Item Code 590106 Total No. of Proj.** | | | **4** | | **Total Amount** | **$901,009.00** |
| **590111** | PAINT STRUCTURAL STEEL (EXISTING BRIDGE) | LS | 1 | 1 | 1.00 | $561,238.00 | $561,238.00 |
| | | LS | 3 | 1 | 1.00 | $25,500.00 | $25,500.00 |
| | | LS | 5 | 2 | 2.00 | $111,717.00 | $223,434.00 |
| | | LS | 11 | 1 | 1.00 | $9,000.00 | $9,000.00 |
| | **Unit Sub Total** | **LS** | | **5** | **5.00** | **$163,834.40** | **$819,172.00** |
| | **Item Code 590111 Total No. of Proj.** | | | **5** | | **Total Amount** | **$819,172.00** |
| **590115** | CLEAN AND PAINT STRUCTURAL STEEL | LS | 5 | 3 | 3.00 | $5,366.67 | $16,100.00 |
| | | LS | 7 | 1 | 1.00 | $245,000.00 | $245,000.00 |
| | | LS | 11 | 2 | 2.00 | $16,500.00 | $33,000.00 |
| | **Unit Sub Total** | **LS** | | **6** | **6.00** | **$49,016.67** | **$294,100.00** |
| | **Item Code 590115 Total No. of Proj.** | | | **6** | | **Total Amount** | **$294,100.00** |
| **590135** | SPOT BLAST CLEAN AND PAINT UNDERCOAT | M2 | 1 | 1 | 9.00 | $1,500.00 | $13,500.00 |
| | **Unit Sub Total** | **M2** | | **1** | **9.00** | **$1,500.00** | **$13,500.00** |
| **590135** | SPOT BLAST CLEAN AND PAINT UNDERCOAT | SQFT | 1 | 1 | 5,376.00 | $12.00 | $64,512.00 |
| | | SQFT | 3 | 1 | 4.00 | $500.00 | $2,000.00 |
| | | SQFT | 5 | 2 | 8,848.00 | $14.80 | $130,979.76 |
| | | SQFT | 7 | 1 | 2,076.00 | $85.00 | $176,460.00 |
| | | SQFT | 11 | 1 | 409.00 | $35.00 | $14,315.00 |
| | **Unit Sub Total** | **SQFT** | | **6** | **16,713.00** | **$23.23** | **$388,266.76** |
| | **Item Code 590135 Total No. of Proj.** | | | **7** | | **Total Amount** | **$401,766.76** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **590280** | PAINT CONCRETE SURFACES | SQFT | 12 | 1 | 330.00 | $1.84 | $607.20 |
| | **Unit Sub Total** | **SQFT** | | **1** | **330.00** | **$1.84** | **$607.20** |
| | **Item Code 590280 Total No. of Proj.** | | | **1** | | **Total Amount** | **$607.20** |
| **590301** | WORK AREA MONITORING | LS | 1 | 1 | 1.00 | $20,000.00 | $20,000.00 |
| | | LS | 5 | 2 | 2.00 | $48,334.00 | $96,668.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$38,889.33** | **$116,668.00** |
| | **Item Code 590301 Total No. of Proj.** | | | **3** | | **Total Amount** | **$116,668.00** |
| **597401** | PAINT CURB (2-COAT) | LF | 1 | 1 | 550.00 | $5.00 | $2,750.00 |
| | | LF | 7 | 1 | 260.00 | $0.30 | $78.00 |
| | **Unit Sub Total** | **LF** | | **2** | **810.00** | **$3.49** | **$2,828.00** |
| **597401** | PAINT CURB (2-COAT) | M | 1 | 1 | 580.00 | $2.50 | $1,450.00 |
| | | M | 5 | 1 | 7.00 | $30.00 | $210.00 |
| | | M | 9 | 2 | 2,290.00 | $4.38 | $10,020.00 |
| | | M | 12 | 1 | 33.00 | $7.50 | $247.50 |
| | **Unit Sub Total** | **M** | | **5** | **2,910.00** | **$4.10** | **$11,927.50** |
| **597401** | PAINT CURB (2-COAT) | SQFT | 2 | 1 | 29.00 | $22.00 | $638.00 |
| | | SQFT | 7 | 2 | 12,080.00 | $0.64 | $7,788.00 |
| | **Unit Sub Total** | **SQFT** | | **3** | **12,109.00** | **$0.70** | **$8,426.00** |
| | **Item Code 597401 Total No. of Proj.** | | | **10** | | **Total Amount** | **$23,181.50** |
| **597600** | PREPARE AND PAINT CONCRETE | M2 | 3 | 1 | 6,871.00 | $55.00 | $377,905.00 |
| | | M2 | 5 | 1 | 1,660.00 | $25.00 | $41,500.00 |
| | | M2 | 7 | 1 | 3,848.00 | $11.00 | $42,328.00 |
| | | M2 | 8 | 1 | 44,000.00 | $8.35 | $367,400.00 |
| | | M2 | 11 | 1 | 560.00 | $25.00 | $14,000.00 |
| | **Unit Sub Total** | **M2** | | **5** | **56,939.00** | **$14.81** | **$843,133.00** |
| **597600** | PREPARE AND PAINT CONCRETE | SQFT | 11 | 1 | 292,000.00 | $0.30 | $87,600.00 |
| | **Unit Sub Total** | **SQFT** | | **1** | **292,000.00** | **$0.30** | **$87,600.00** |
| | **Item Code 597600 Total No. of Proj.** | | | **6** | | **Total Amount** | **$930,733.00** |
| **597601** | PREPARE AND STAIN CONCRETE | LS | 3 | 1 | 1.00 | $200,000.00 | $200,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$200,000.00** | **$200,000.00** |
| **597601** | PREPARE AND STAIN CONCRETE | | M2 | 3 | 1 | 31.00 | $100.00 | $3,100.00 |
| | | | M2 | 4 | 1 | 661.00 | $30.00 | $19,830.00 |
| | | | M2 | 5 | 2 | 953.00 | $65.31 | $62,243.00 |
| | | | M2 | 10 | 2 | 360.00 | $104.53 | $37,630.00 |
| | | | M2 | 11 | 1 | 8.00 | $280.00 | $2,240.00 |
| | | **Unit Sub Total** | **M2** | | **7** | **2,013.00** | **$62.12** | **$125,043.00** |
| **597601** | PREPARE AND STAIN CONCRETE | | SQFT | 2 | 2 | 1,272.00 | $1.70 | $2,166.00 |
| | | **Unit Sub Total** | **SQFT** | | **2** | **1,272.00** | **$1.70** | **$2,166.00** |
| | **Item Code 597601** | **Total No. of Proj.** | | | **10** | | **Total Amount** | **$327,209.00** |
| **620002** | 6" ALTERNATIVE PIPE CULVERT | | LF | 4 | 1 | 84.00 | $250.00 | $21,000.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **84.00** | **$250.00** | **$21,000.00** |
| | **Item Code 620002** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$21,000.00** |
| **620060** | 12" ALTERNATIVE PIPE CULVERT | | LF | 2 | 1 | 42.00 | $70.00 | $2,940.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **42.00** | **$70.00** | **$2,940.00** |
| | **Item Code 620060** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,940.00** |
| **620080** | 15" ALTERNATIVE PIPE CULVERT | | LF | 2 | 1 | 61.00 | $150.00 | $9,150.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **61.00** | **$150.00** | **$9,150.00** |
| | **Item Code 620080** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$9,150.00** |
| **620100** | 18" ALTERNATIVE PIPE CULVERT | | LF | 1 | 2 | 784.00 | $82.96 | $65,040.00 |
| | | | LF | 2 | 1 | 76.00 | $98.00 | $7,448.00 |
| | | | LF | 3 | 2 | 163.00 | $149.82 | $24,420.00 |
| | | | LF | 4 | 2 | 655.00 | $79.62 | $52,150.00 |
| | | | LF | 5 | 1 | 500.00 | $53.00 | $26,500.00 |
| | | | LF | 8 | 2 | 887.00 | $198.37 | $175,955.00 |
| | | | LF | 11 | 1 | 1,600.00 | $52.00 | $83,200.00 |
| | | | LF | 12 | 1 | 160.00 | $125.00 | $20,000.00 |
| | | **Unit Sub Total** | **LF** | | **12** | **4,825.00** | **$94.24** | **$454,713.00** |
| | **Item Code 620100** | **Total No. of Proj.** | | | **12** | | **Total Amount** | **$454,713.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **620140** | 24" ALTERNATIVE PIPE CULVERT | LF | 1 | 4 | 717.00 | $176.74 | $126,725.00 |
| | | LF | 2 | 1 | 960.00 | $245.00 | $235,200.00 |
| | | LF | 3 | 1 | 420.00 | $75.50 | $31,710.00 |
| | | LF | 5 | 2 | 1,110.00 | $58.76 | $65,220.00 |
| | | LF | 8 | 2 | 1,810.00 | $151.36 | $273,960.00 |
| | | LF | 11 | 1 | 15,700.00 | $83.00 | $1,303,100.00 |
| | | LF | 12 | 1 | 220.00 | $110.00 | $24,200.00 |
| | **Unit Sub Total** | **LF** | | **12** | **20,937.00** | **$98.40** | **$2,060,115.00** |
| | **Item Code 620140 Total No. of Proj.** | | | **12** | | **Total Amount** | **$2,060,115.00** |
| **620180** | 30" ALTERNATIVE PIPE CULVERT | LF | 1 | 1 | 120.00 | $150.00 | $18,000.00 |
| | | LF | 3 | 1 | 210.00 | $87.00 | $18,270.00 |
| | | LF | 8 | 1 | 600.00 | $340.00 | $204,000.00 |
| | **Unit Sub Total** | **LF** | | **3** | **930.00** | **$258.35** | **$240,270.00** |
| | **Item Code 620180 Total No. of Proj.** | | | **3** | | **Total Amount** | **$240,270.00** |
| **620220** | 36" ALTERNATIVE PIPE CULVERT | LF | 1 | 1 | 100.00 | $160.00 | $16,000.00 |
| | | LF | 3 | 1 | 96.00 | $111.00 | $10,656.00 |
| | **Unit Sub Total** | **LF** | | **2** | **196.00** | **$136.00** | **$26,656.00** |
| | **Item Code 620220 Total No. of Proj.** | | | **2** | | **Total Amount** | **$26,656.00** |
| **620260** | 42" ALTERNATIVE PIPE CULVERT | LF | 1 | 1 | 20.00 | $160.00 | $3,200.00 |
| | **Unit Sub Total** | **LF** | | **1** | **20.00** | **$160.00** | **$3,200.00** |
| | **Item Code 620260 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,200.00** |
| **620902** | 200 MM ALTERNATIVE PIPE CULVERT | M | 2 | 1 | 100.00 | $165.00 | $16,500.00 |
| | | M | 6 | 1 | 48.00 | $380.00 | $18,240.00 |
| | | M | 11 | 1 | 46.00 | $150.00 | $6,900.00 |
| | **Unit Sub Total** | **M** | | **3** | **194.00** | **$214.64** | **$41,640.00** |
| | **Item Code 620902 Total No. of Proj.** | | | **3** | | **Total Amount** | **$41,640.00** |
| **620904** | 300 MM ALTERNATIVE PIPE CULVERT | M | 1 | 2 | 41.00 | $268.29 | $11,000.00 |
| | | M | 2 | 1 | 90.00 | $200.00 | $18,000.00 |
| | | M | 3 | 3 | 113.50 | $362.42 | $41,135.00 |
| | | M | 4 | 1 | 80.00 | $78.00 | $6,240.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **620904** | 300 MM ALTERNATIVE PIPE CULVERT | M | 5 | 1 | 30.00 | $600.00 | $18,000.00 |
| | | M | 9 | 1 | 31.00 | $210.00 | $6,510.00 |
| | | M | 10 | 1 | 6.00 | $200.00 | $1,200.00 |
| | | M | 11 | 2 | 133.00 | $256.39 | $34,100.00 |
| | **Unit Sub Total** | **M** | | **12** | **524.50** | **$259.65** | **$136,185.00** |
| | **Item Code 620904 Total No. of Proj.** | | | **12** | | **Total Amount** | **$136,185.00** |
| **620908** | 375 MM ALTERNATIVE PIPE CULVERT | M | 2 | 1 | 130.00 | $250.00 | $32,500.00 |
| | | M | 4 | 1 | 46.00 | $200.00 | $9,200.00 |
| | **Unit Sub Total** | **M** | | **2** | **176.00** | **$236.93** | **$41,700.00** |
| | **Item Code 620908 Total No. of Proj.** | | | **2** | | **Total Amount** | **$41,700.00** |
| **620909** | 450 MM ALTERNATIVE PIPE CULVERT | M | 1 | 3 | 225.00 | $340.67 | $76,650.00 |
| | | M | 2 | 1 | 62.00 | $340.00 | $21,080.00 |
| | | M | 3 | 4 | 4,250.00 | $346.62 | $1,473,150.00 |
| | | M | 4 | 6 | 4,382.00 | $207.93 | $911,160.00 |
| | | M | 5 | 3 | 1,576.00 | $324.70 | $511,720.00 |
| | | M | 8 | 2 | 1,360.00 | $235.96 | $320,900.00 |
| | | M | 9 | 3 | 1,575.00 | $223.53 | $352,060.00 |
| | | M | 10 | 2 | 37.00 | $305.84 | $11,316.00 |
| | | M | 11 | 7 | 5,298.30 | $159.66 | $845,940.00 |
| | **Unit Sub Total** | **M** | | **31** | **18,765.30** | **$241.08** | **$4,523,976.00** |
| | **Item Code 620909 Total No. of Proj.** | | | **31** | | **Total Amount** | **$4,523,976.00** |
| **620910** | 450 MM ALTERNATIVE PIPE CULVERT (TYPE A) | M | 4 | 3 | 2,481.00 | $204.76 | $508,005.00 |
| | **Unit Sub Total** | **M** | | **3** | **2,481.00** | **$204.76** | **$508,005.00** |
| | **Item Code 620910 Total No. of Proj.** | | | **3** | | **Total Amount** | **$508,005.00** |
| **620911** | 450 MM ALTERNATIVE PIPE CULVERT (TYPE B) | M | 4 | 3 | 1,131.00 | $201.47 | $227,860.00 |
| | **Unit Sub Total** | **M** | | **3** | **1,131.00** | **$201.47** | **$227,860.00** |
| | **Item Code 620911 Total No. of Proj.** | | | **3** | | **Total Amount** | **$227,860.00** |
| **620913** | 600 MM ALTERNATIVE PIPE CULVERT | M | 1 | 4 | 1,692.00 | $233.78 | $395,550.00 |
| | | M | 2 | 1 | 80.00 | $352.00 | $28,160.00 |
| | | M | 3 | 5 | 2,351.00 | $314.62 | $739,675.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **620913** | 600 MM ALTERNATIVE PIPE CULVERT | M | 4 | 6 | 893.00 | $334.49 | $298,700.00 |
| | | M | 5 | 5 | 3,961.00 | $340.64 | $1,349,280.00 |
| | | M | 8 | 2 | 3,750.00 | $228.36 | $856,350.00 |
| | | M | 9 | 2 | 1,150.00 | $235.22 | $270,500.00 |
| | | M | 10 | 2 | 53.00 | $224.49 | $11,898.00 |
| | | M | 11 | 7 | 14,332.00 | $204.80 | $2,935,230.00 |
| | **Unit Sub Total** | **M** | | **34** | **28,262.00** | **$243.63** | **$6,885,343.00** |
| | **Item Code 620913 Total No. of Proj.** | | | **34** | | **Total Amount** | **$6,885,343.00** |
| **620914** | 600 MM ALTERNATIVE PIPE CULVERT (TYPE A) | M | 4 | 3 | 709.00 | $204.75 | $145,168.00 |
| | **Unit Sub Total** | **M** | | **3** | **709.00** | **$204.75** | **$145,168.00** |
| | **Item Code 620914 Total No. of Proj.** | | | **3** | | **Total Amount** | **$145,168.00** |
| **620915** | 600 MM ALTERNATIVE PIPE CULVERT (TYPE B) | M | 4 | 3 | 670.00 | $238.36 | $159,700.00 |
| | **Unit Sub Total** | **M** | | **3** | **670.00** | **$238.36** | **$159,700.00** |
| | **Item Code 620915 Total No. of Proj.** | | | **3** | | **Total Amount** | **$159,700.00** |
| **620916** | 600 MM ALTERNATIVE PIPE CULVERT (TYPE C) | M | 4 | 1 | 160.00 | $227.00 | $36,320.00 |
| | **Unit Sub Total** | **M** | | **1** | **160.00** | **$227.00** | **$36,320.00** |
| | **Item Code 620916 Total No. of Proj.** | | | **1** | | **Total Amount** | **$36,320.00** |
| **620919** | 750 MM ALTERNATIVE PIPE CULVERT | M | 1 | 1 | 380.00 | $225.00 | $85,500.00 |
| | | M | 3 | 2 | 212.00 | $565.09 | $119,800.00 |
| | | M | 4 | 2 | 83.00 | $605.42 | $50,250.00 |
| | | M | 5 | 2 | 219.00 | $364.50 | $79,825.00 |
| | | M | 9 | 1 | 330.00 | $310.00 | $102,300.00 |
| | | M | 11 | 5 | 3,150.00 | $246.22 | $775,580.00 |
| | **Unit Sub Total** | **M** | | **13** | **4,374.00** | **$277.38** | **$1,213,255.00** |
| | **Item Code 620919 Total No. of Proj.** | | | **13** | | **Total Amount** | **$1,213,255.00** |
| **620924** | 900 MM ALTERNATIVE PIPE CULVERT | M | 1 | 2 | 87.00 | $278.28 | $24,210.00 |
| | | M | 2 | 1 | 130.00 | $435.00 | $56,550.00 |
| | | M | 3 | 2 | 25.70 | $649.03 | $16,680.00 |
| | | M | 4 | 2 | 18.60 | $801.08 | $14,900.00 |
| | | M | 5 | 3 | 752.00 | $450.84 | $339,030.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **620924** | 900 MM ALTERNATIVE PIPE CULVERT | M | 11 | 5 | 1,998.00 | $269.24 | $537,950.00 |
| | **Unit Sub Total** | **M** | | **15** | **3,011.30** | **$328.54** | **$989,320.00** |
| | **Item Code 620924 Total No. of Proj.** | | | **15** | | **Total Amount** | **$989,320.00** |
| **620925** | 900 MM ALTERNATIVE PIPE CULVERT (TYPE A) | M | 4 | 1 | 70.00 | $470.00 | $32,900.00 |
| | **Unit Sub Total** | **M** | | **1** | **70.00** | **$470.00** | **$32,900.00** |
| | **Item Code 620925 Total No. of Proj.** | | | **1** | | **Total Amount** | **$32,900.00** |
| **620930** | 1050 MM ALTERNATIVE PIPE CULVERT | M | 1 | 2 | 183.00 | $302.73 | $55,400.00 |
| | | M | 3 | 1 | 65.00 | $400.00 | $26,000.00 |
| | | M | 11 | 3 | 640.00 | $358.05 | $229,150.00 |
| | **Unit Sub Total** | **M** | | **6** | **888.00** | **$349.72** | **$310,550.00** |
| | **Item Code 620930 Total No. of Proj.** | | | **6** | | **Total Amount** | **$310,550.00** |
| **620932** | 1050 MM ALTERNATIVE PIPE CULVERT (TYPE B) | M | 4 | 1 | 100.00 | $480.00 | $48,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **100.00** | **$480.00** | **$48,000.00** |
| | **Item Code 620932 Total No. of Proj.** | | | **1** | | **Total Amount** | **$48,000.00** |
| **620933** | 1200 MM ALTERNATIVE PIPE CULVERT | M | 3 | 1 | 510.00 | $350.00 | $178,500.00 |
| | | M | 4 | 1 | 520.00 | $500.00 | $260,000.00 |
| | | M | 5 | 1 | 180.00 | $555.00 | $99,900.00 |
| | | M | 9 | 1 | 85.00 | $580.00 | $49,300.00 |
| | | M | 11 | 2 | 489.00 | $418.48 | $204,635.00 |
| | **Unit Sub Total** | **M** | | **6** | **1,784.00** | **$444.13** | **$792,335.00** |
| | **Item Code 620933 Total No. of Proj.** | | | **6** | | **Total Amount** | **$792,335.00** |
| **620940** | 1500 MM ALTERNATIVE PIPE CULVERT | M | 3 | 1 | 42.00 | $600.00 | $25,200.00 |
| | | M | 4 | 1 | 310.00 | $500.00 | $155,000.00 |
| | | M | 5 | 1 | 190.00 | $590.00 | $112,100.00 |
| | **Unit Sub Total** | **M** | | **3** | **542.00** | **$539.30** | **$292,300.00** |
| | **Item Code 620940 Total No. of Proj.** | | | **3** | | **Total Amount** | **$292,300.00** |
| **620943** | 1650 MM ALTERNATIVE PIPE CULVERT | M | 9 | 1 | 140.00 | $480.00 | $67,200.00 |
| | | M | 11 | 1 | 25.00 | $2,560.00 | $64,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **M** | | **2** | **165.00** | **$795.15** | **$131,200.00** |
| | **Item Code 620943 Total No. of Proj.** | | | **2** | | **Total Amount** | **$131,200.00** |
| **625382** | 525 MM X 375 MM ALTERNATIVE PIPE ARCH CULVERT | M | 1 | 1 | 56.00 | $275.00 | $15,400.00 |
| | **Unit Sub Total** | **M** | | **1** | **56.00** | **$275.00** | **$15,400.00** |
| | **Item Code 625382 Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,400.00** |
| **641113** | 24" PLASTIC PIPE | LF | 11 | 1 | 75.00 | $100.00 | $7,500.00 |
| | **Unit Sub Total** | **LF** | | **1** | **75.00** | **$100.00** | **$7,500.00** |
| | **Item Code 641113 Total No. of Proj.** | | | **1** | | **Total Amount** | **$7,500.00** |
| **641119** | 30" PLASTIC PIPE | LF | 9 | 1 | 190.00 | $78.00 | $14,820.00 |
| | **Unit Sub Total** | **LF** | | **1** | **190.00** | **$78.00** | **$14,820.00** |
| | **Item Code 641119 Total No. of Proj.** | | | **1** | | **Total Amount** | **$14,820.00** |
| **641132** | 300 MM PLASTIC PIPE | M | 1 | 1 | 5.00 | $250.00 | $1,250.00 |
| | **Unit Sub Total** | **M** | | **1** | **5.00** | **$250.00** | **$1,250.00** |
| | **Item Code 641132 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,250.00** |
| **641134** | 450 MM PLASTIC PIPE | M | 4 | 6 | 310.30 | $204.21 | $63,366.70 |
| | | M | 5 | 1 | 22.00 | $200.00 | $4,400.00 |
| | **Unit Sub Total** | **M** | | **7** | **332.30** | **$203.93** | **$67,766.70** |
| | **Item Code 641134 Total No. of Proj.** | | | **7** | | **Total Amount** | **$67,766.70** |
| **642110** | 12" SLOTTED PLASTIC PIPE | LF | 3 | 1 | 1,700.00 | $110.00 | $187,000.00 |
| | **Unit Sub Total** | **LF** | | **1** | **1,700.00** | **$110.00** | **$187,000.00** |
| | **Item Code 642110 Total No. of Proj.** | | | **1** | | **Total Amount** | **$187,000.00** |
| **650010** | 12" REINFORCED CONCRETE PIPE | LF | 8 | 1 | 8.00 | $400.00 | $3,200.00 |
| | | LF | 11 | 1 | 4.00 | $84.00 | $336.00 |
| | **Unit Sub Total** | **LF** | | **2** | **12.00** | **$294.67** | **$3,536.00** |
| | **Item Code 650010 Total No. of Proj.** | | | **2** | | **Total Amount** | **$3,536.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **650014** | 18" REINFORCED CONCRETE PIPE | LF | 3 | 1 | 6,950.00 | $104.00 | $722,800.00 |
| | | LF | 6 | 1 | 3.00 | $1,000.00 | $3,000.00 |
| | | LF | 7 | 1 | 27.00 | $170.00 | $4,590.00 |
| | | LF | 8 | 1 | 2.00 | $250.00 | $500.00 |
| | | LF | 11 | 1 | 4.00 | $84.00 | $336.00 |
| | | LF | 12 | 4 | 252.00 | $166.07 | $41,850.00 |
| | **Unit Sub Total** | **LF** | | **9** | **7,238.00** | **$106.81** | **$773,076.00** |
| | **Item Code 650014 Total No. of Proj.** | | | **9** | | **Total Amount** | **$773,076.00** |
| **650018** | 24" REINFORCED CONCRETE PIPE | LF | 3 | 2 | 2,230.00 | $129.46 | $288,700.00 |
| | | LF | 5 | 1 | 17.00 | $715.07 | $12,156.19 |
| | | LF | 6 | 1 | 530.00 | $168.00 | $89,040.00 |
| | | LF | 7 | 2 | 480.00 | $154.06 | $73,950.00 |
| | | LF | 11 | 2 | 396.00 | $127.12 | $50,340.00 |
| | | LF | 12 | 2 | 188.00 | $110.11 | $20,700.00 |
| | **Unit Sub Total** | **LF** | | **10** | **3,841.00** | **$139.26** | **$534,886.19** |
| | **Item Code 650018 Total No. of Proj.** | | | **10** | | **Total Amount** | **$534,886.19** |
| **650022** | 30" REINFORCED CONCRETE PIPE | LF | 11 | 1 | 77.00 | $149.00 | $11,473.00 |
| | **Unit Sub Total** | **LF** | | **1** | **77.00** | **$149.00** | **$11,473.00** |
| | **Item Code 650022 Total No. of Proj.** | | | **1** | | **Total Amount** | **$11,473.00** |
| **650026** | 36" REINFORCED CONCRETE PIPE | LF | 7 | 2 | 275.00 | $160.91 | $44,250.00 |
| | | LF | 8 | 1 | 8.00 | $100.00 | $800.00 |
| | | LF | 11 | 1 | 110.00 | $169.00 | $18,590.00 |
| | **Unit Sub Total** | **LF** | | **4** | **393.00** | **$161.93** | **$63,640.00** |
| | **Item Code 650026 Total No. of Proj.** | | | **4** | | **Total Amount** | **$63,640.00** |
| **650038** | 54" REINFORCED CONCRETE PIPE | LF | 11 | 1 | 150.00 | $223.00 | $33,450.00 |
| | **Unit Sub Total** | **LF** | | **1** | **150.00** | **$223.00** | **$33,450.00** |
| | **Item Code 650038 Total No. of Proj.** | | | **1** | | **Total Amount** | **$33,450.00** |
| **650067** | 300 MM REINFORCED CONCRETE PIPE | M | 2 | 1 | 150.00 | $340.00 | $51,000.00 |
| | | M | 4 | 1 | 201.00 | $215.00 | $43,215.00 |
| | | M | 10 | 2 | 83.00 | $311.17 | $25,827.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **650067** | 300 MM REINFORCED CONCRETE PIPE | M | 11 | 2 | 21.50 | $312.37 | $6,716.00 |
| | **Unit Sub Total** | **M** | | **6** | **455.50** | **$278.28** | **$126,758.00** |
| | **Item Code 650067 Total No. of Proj.** | | | **6** | | **Total Amount** | **$126,758.00** |
| **650068** | 375 MM REINFORCED CONCRETE PIPE | M | 2 | 1 | 540.00 | $350.00 | $189,000.00 |
| | | M | 5 | 2 | 123.00 | $394.72 | $48,550.00 |
| | | M | 7 | 1 | 4.00 | $300.00 | $1,200.00 |
| | | M | 10 | 1 | 43.00 | $225.00 | $9,675.00 |
| | **Unit Sub Total** | **M** | | **5** | **710.00** | **$349.89** | **$248,425.00** |
| | **Item Code 650068 Total No. of Proj.** | | | **5** | | **Total Amount** | **$248,425.00** |
| **650069** | 450 MM REINFORCED CONCRETE PIPE | M | 2 | 1 | 170.00 | $420.00 | $71,400.00 |
| | | M | 3 | 1 | 1.60 | $1,200.00 | $1,920.00 |
| | | M | 4 | 1 | 18.00 | $600.00 | $10,800.00 |
| | | M | 5 | 2 | 240.00 | $338.21 | $81,170.00 |
| | | M | 6 | 2 | 459.00 | $226.03 | $103,750.00 |
| | | M | 7 | 8 | 6,285.00 | $232.60 | $1,461,892.00 |
| | | M | 8 | 2 | 440.00 | $462.50 | $203,500.00 |
| | | M | 10 | 3 | 345.00 | $246.51 | $85,045.00 |
| | | M | 11 | 7 | 3,625.00 | $186.97 | $677,760.00 |
| | | M | 12 | 1 | 66.00 | $315.00 | $20,790.00 |
| | **Unit Sub Total** | **M** | | **28** | **11,649.60** | **$233.32** | **$2,718,027.00** |
| | **Item Code 650069 Total No. of Proj.** | | | **28** | | **Total Amount** | **$2,718,027.00** |
| **650072** | 525 MM REINFORCED CONCRETE PIPE | M | 7 | 1 | 8.00 | $600.00 | $4,800.00 |
| | **Unit Sub Total** | **M** | | **1** | **8.00** | **$600.00** | **$4,800.00** |
| | **Item Code 650072 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,800.00** |
| **650075** | 600 MM REINFORCED CONCRETE PIPE | M | 2 | 2 | 276.50 | $447.57 | $123,753.00 |
| | | M | 3 | 2 | 90.00 | $431.33 | $38,820.00 |
| | | M | 4 | 2 | 102.00 | $433.82 | $44,250.00 |
| | | M | 5 | 5 | 721.00 | $377.25 | $272,000.00 |
| | | M | 6 | 2 | 1,170.00 | $181.33 | $212,160.00 |
| | | M | 7 | 10 | 2,064.00 | $309.69 | $639,202.50 |
| | | M | 8 | 2 | 201.00 | $356.92 | $71,740.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **650075** | 600 MM REINFORCED CONCRETE PIPE | M | 10 | 4 | 1,914.00 | $230.99 | $442,118.00 |
| | | M | 11 | 7 | 3,254.00 | $328.19 | $1,067,920.00 |
| | | M | 12 | 1 | 130.00 | $315.00 | $40,950.00 |
| | **Unit Sub Total** | **M** | | **37** | **9,922.50** | **$297.60** | **$2,952,913.50** |
| | **Item Code 650075 Total No. of Proj.** | | | **37** | | **Total Amount** | **$2,952,913.50** |
| **650077** | 750 MM REINFORCED CONCRETE PIPE | M | 2 | 1 | 210.00 | $430.00 | $90,300.00 |
| | | M | 4 | 1 | 13.00 | $600.00 | $7,800.00 |
| | | M | 5 | 2 | 173.00 | $617.16 | $106,768.00 |
| | | M | 7 | 2 | 18.00 | $654.17 | $11,775.00 |
| | | M | 8 | 2 | 421.00 | $284.42 | $119,740.00 |
| | | M | 10 | 1 | 6.00 | $500.00 | $3,000.00 |
| | | M | 11 | 4 | 200.00 | $282.10 | $56,420.00 |
| | **Unit Sub Total** | **M** | | **13** | **1,041.00** | **$380.21** | **$395,803.00** |
| | **Item Code 650077 Total No. of Proj.** | | | **13** | | **Total Amount** | **$395,803.00** |
| **650079** | 900 MM REINFORCED CONCRETE PIPE | M | 5 | 3 | 30.00 | $763.33 | $22,900.00 |
| | | M | 6 | 1 | 20.00 | $770.00 | $15,400.00 |
| | | M | 7 | 4 | 1,568.00 | $315.81 | $495,190.00 |
| | | M | 8 | 2 | 43.00 | $484.42 | $20,830.00 |
| | | M | 10 | 3 | 973.00 | $276.14 | $268,688.00 |
| | | M | 11 | 5 | 1,196.00 | $362.36 | $433,380.00 |
| | | M | 12 | 2 | 283.00 | $711.66 | $201,400.00 |
| | **Unit Sub Total** | **M** | | **20** | **4,113.00** | **$354.43** | **$1,457,788.00** |
| | **Item Code 650079 Total No. of Proj.** | | | **20** | | **Total Amount** | **$1,457,788.00** |
| **650080** | 975 MM REINFORCED CONCRETE PIPE | M | 8 | 1 | 46.00 | $500.00 | $23,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **46.00** | **$500.00** | **$23,000.00** |
| | **Item Code 650080 Total No. of Proj.** | | | **1** | | **Total Amount** | **$23,000.00** |
| **650081** | 1050 MM REINFORCED CONCRETE PIPE | M | 4 | 1 | 5.00 | $800.00 | $4,000.00 |
| | | M | 5 | 1 | 12.00 | $1,100.00 | $13,200.00 |
| | | M | 6 | 1 | 20.00 | $830.00 | $16,600.00 |
| | **Unit Sub Total** | **M** | | **3** | **37.00** | **$913.51** | **$33,800.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 650081 Total No. of Proj.** | | | **3** | | **Total Amount** | **$33,800.00** |
| **650084** | 1200 MM REINFORCED CONCRETE PIPE | M | 3 | 1 | 13.00 | $500.00 | $6,500.00 |
| | | M | 7 | 1 | 200.00 | $500.00 | $100,000.00 |
| | | M | 11 | 5 | 944.00 | $558.83 | $527,540.00 |
| | **Unit Sub Total** | **M** | | **7** | **1,157.00** | **$548.00** | **$634,040.00** |
| | **Item Code 650084 Total No. of Proj.** | | | **7** | | **Total Amount** | **$634,040.00** |
| **650086** | 1350 MM REINFORCED CONCRETE PIPE | M | 5 | 1 | 160.00 | $575.00 | $92,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **160.00** | **$575.00** | **$92,000.00** |
| | **Item Code 650086 Total No. of Proj.** | | | **1** | | **Total Amount** | **$92,000.00** |
| **650089** | 1500 MM REINFORCED CONCRETE PIPE | M | 4 | 1 | 130.00 | $700.00 | $91,000.00 |
| | | M | 11 | 2 | 296.00 | $722.97 | $214,000.00 |
| | **Unit Sub Total** | **M** | | **3** | **426.00** | **$715.96** | **$305,000.00** |
| | **Item Code 650089 Total No. of Proj.** | | | **3** | | **Total Amount** | **$305,000.00** |
| **650091** | 1650 MM REINFORCED CONCRETE PIPE | M | 5 | 1 | 43.00 | $900.00 | $38,700.00 |
| | **Unit Sub Total** | **M** | | **1** | **43.00** | **$900.00** | **$38,700.00** |
| | **Item Code 650091 Total No. of Proj.** | | | **1** | | **Total Amount** | **$38,700.00** |
| **650092** | 1800 MM REINFORCED CONCRETE PIPE | M | 5 | 1 | 150.00 | $950.00 | $142,500.00 |
| | **Unit Sub Total** | **M** | | **1** | **150.00** | **$950.00** | **$142,500.00** |
| | **Item Code 650092 Total No. of Proj.** | | | **1** | | **Total Amount** | **$142,500.00** |
| **650127** | 450 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT) | M | 6 | 1 | 270.00 | $630.00 | $170,100.00 |
| | | M | 10 | 1 | 1,030.00 | $134.00 | $138,020.00 |
| | **Unit Sub Total** | **M** | | **2** | **1,300.00** | **$237.02** | **$308,120.00** |
| | **Item Code 650127 Total No. of Proj.** | | | **2** | | **Total Amount** | **$308,120.00** |
| **650128** | 600 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT) | M | 10 | 1 | 36.00 | $450.00 | $16,200.00 |
| | **Unit Sub Total** | **M** | | **1** | **36.00** | **$450.00** | **$16,200.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 650128 Total No. of Proj.** | | | **1** | | **Total Amount** | **$16,200.00** |
| **650311** | 18" REINFORCED CONCRETE PIPE (CLASS III) | LF | 1 | 1 | 16.00 | $338.00 | $5,408.00 |
| | **Unit Sub Total** | **LF** | | **1** | **16.00** | **$338.00** | **$5,408.00** |
| | **Item Code 650311 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,408.00** |
| **650365** | 450 MM REINFORCED CONCRETE PIPE (CLASS III) | M | 4 | 1 | 380.00 | $200.00 | $76,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **380.00** | **$200.00** | **$76,000.00** |
| | **Item Code 650365 Total No. of Proj.** | | | **1** | | **Total Amount** | **$76,000.00** |
| **650370** | 600 MM REINFORCED CONCRETE PIPE (CLASS III) | M | 4 | 1 | 520.00 | $225.00 | $117,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **520.00** | **$225.00** | **$117,000.00** |
| | **Item Code 650370 Total No. of Proj.** | | | **1** | | **Total Amount** | **$117,000.00** |
| **650373** | 675 MM REINFORCED CONCRETE PIPE (CLASS III) | M | 4 | 1 | 0.90 | $700.00 | $630.00 |
| | **Unit Sub Total** | **M** | | **1** | **0.90** | **$700.00** | **$630.00** |
| | **Item Code 650373 Total No. of Proj.** | | | **1** | | **Total Amount** | **$630.00** |
| **650470** | 450 MM REINFORCED CONCRETE PIPE (CLASS IV) | M | 3 | 1 | 710.00 | $260.00 | $184,600.00 |
| | **Unit Sub Total** | **M** | | **1** | **710.00** | **$260.00** | **$184,600.00** |
| | **Item Code 650470 Total No. of Proj.** | | | **1** | | **Total Amount** | **$184,600.00** |
| **650476** | 600 MM REINFORCED CONCRETE PIPE (CLASS IV) | M | 3 | 1 | 1,390.00 | $265.00 | $368,350.00 |
| | **Unit Sub Total** | **M** | | **1** | **1,390.00** | **$265.00** | **$368,350.00** |
| | **Item Code 650476 Total No. of Proj.** | | | **1** | | **Total Amount** | **$368,350.00** |
| **650478** | 750 MM REINFORCED CONCRETE PIPE (CLASS IV) | M | 3 | 1 | 270.00 | $300.00 | $81,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **270.00** | **$300.00** | **$81,000.00** |
| | **Item Code 650478 Total No. of Proj.** | | | **1** | | **Total Amount** | **$81,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **650481** | 900 MM REINFORCED CONCRETE PIPE (CLASS IV) | M | 3 | 1 | 660.00 | $360.00 | $237,600.00 |
| | **Unit Sub Total** | **M** | | **1** | **660.00** | **$360.00** | **$237,600.00** |
| | **Item Code 650481 Total No. of Proj.** | | | **1** | | **Total Amount** | **$237,600.00** |
| **652215** | 24" REINFORCED CONCRETE PIPE (CLASS II, RUBBER GASKET JOINT) | LF | 3 | 1 | 2,480.00 | $75.00 | $186,000.00 |
| | **Unit Sub Total** | **LF** | | **1** | **2,480.00** | **$75.00** | **$186,000.00** |
| | **Item Code 652215 Total No. of Proj.** | | | **1** | | **Total Amount** | **$186,000.00** |
| **655256** | JACKED 600 MM REINFORCED CONCRETE PIPE (CLASS II) | M | 5 | 1 | 63.00 | $1,400.00 | $88,200.00 |
| | **Unit Sub Total** | **M** | | **1** | **63.00** | **$1,400.00** | **$88,200.00** |
| | **Item Code 655256 Total No. of Proj.** | | | **1** | | **Total Amount** | **$88,200.00** |
| **655258** | JACKED 900 MM REINFORCED CONCRETE PIPE (CLASS II) | M | 7 | 1 | 62.00 | $3,645.00 | $225,990.00 |
| | **Unit Sub Total** | **M** | | **1** | **62.00** | **$3,645.00** | **$225,990.00** |
| | **Item Code 655258 Total No. of Proj.** | | | **1** | | **Total Amount** | **$225,990.00** |
| **655370** | JACKED 1050 MM REINFORCED CONCRETE PIPE (CLASS III) | M | 1 | 1 | 50.00 | $2,600.00 | $130,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **50.00** | **$2,600.00** | **$130,000.00** |
| | **Item Code 655370 Total No. of Proj.** | | | **1** | | **Total Amount** | **$130,000.00** |
| **655460** | JACKED 750 MM REINFORCED CONCRETE PIPE (CLASS IV) | M | 5 | 1 | 72.00 | $1,850.00 | $133,200.00 |
| | **Unit Sub Total** | **M** | | **1** | **72.00** | **$1,850.00** | **$133,200.00** |
| | **Item Code 655460 Total No. of Proj.** | | | **1** | | **Total Amount** | **$133,200.00** |
| **655464** | JACKED 1350 MM REINFORCED CONCRETE PIPE (CLASS IV) | M | 5 | 1 | 88.00 | $2,500.00 | $220,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **88.00** | **$2,500.00** | **$220,000.00** |
| | **Item Code 655464 Total No. of Proj.** | | | **1** | | **Total Amount** | **$220,000.00** |
| **664002** | 150 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 3 | 1 | 51.00 | $200.00 | $10,200.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M** | | **1** | **51.00** | **$200.00** | **$10,200.00** |
| | **Item Code 664002** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$10,200.00** |
| **664003** | 200 MM CORRUGATED STEEL PIPE (1.63 MM THICK) | | M | 6 | 1 | 980.00 | $102.00 | $99,960.00 |
| | | | M | 8 | 1 | 4.00 | $660.00 | $2,640.00 |
| | | **Unit Sub Total** | **M** | | **2** | **984.00** | **$104.27** | **$102,600.00** |
| | **Item Code 664003** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$102,600.00** |
| **664004** | 200 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | | M | 10 | 1 | 1.20 | $802.00 | $962.40 |
| | | **Unit Sub Total** | **M** | | **1** | **1.20** | **$802.00** | **$962.40** |
| | **Item Code 664004** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$962.40** |
| **664008** | 300 MM CORRUGATED STEEL PIPE | | M | 4 | 1 | 17.00 | $120.00 | $2,040.00 |
| | | | M | 5 | 1 | 19.00 | $309.00 | $5,871.00 |
| | | | M | 8 | 1 | 10.00 | $385.00 | $3,850.00 |
| | | **Unit Sub Total** | **M** | | **3** | **46.00** | **$255.67** | **$11,761.00** |
| | **Item Code 664008** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$11,761.00** |
| **664009** | 300 MM CORRUGATED STEEL PIPE (1.63 MM THICK) | | M | 4 | 2 | 93.50 | $203.74 | $19,050.00 |
| | | | M | 6 | 2 | 1,599.00 | $112.26 | $179,500.00 |
| | | | M | 8 | 1 | 16.00 | $1,850.00 | $29,600.00 |
| | | **Unit Sub Total** | **M** | | **5** | **1,708.50** | **$133.54** | **$228,150.00** |
| | **Item Code 664009** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$228,150.00** |
| **664010** | 300 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | | M | 2 | 1 | 34.00 | $210.00 | $7,140.00 |
| | | | M | 3 | 2 | 182.00 | $217.03 | $39,500.00 |
| | | | M | 4 | 1 | 210.00 | $215.00 | $45,150.00 |
| | | | M | 10 | 1 | 19.00 | $280.00 | $5,320.00 |
| | | | M | 11 | 1 | 3.00 | $345.00 | $1,035.00 |
| | | **Unit Sub Total** | **M** | | **6** | **448.00** | **$219.07** | **$98,145.00** |
| | **Item Code 664010** | **Total No. of Proj.** | | | **6** | | **Total Amount** | **$98,145.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **664014** | 450 MM CORRUGATED STEEL PIPE (1.63 MM THICK) | M | 3 | 1 | 7.20 | $440.00 | $3,168.00 |
| | | M | 4 | 3 | 96.00 | $189.42 | $18,184.00 |
| | | M | 5 | 1 | 16.00 | $280.00 | $4,480.00 |
| | | M | 6 | 1 | 16.00 | $275.00 | $4,400.00 |
| | | M | 8 | 2 | 56.00 | $216.07 | $12,100.00 |
| | **Unit Sub Total** | **M** | | **8** | **191.20** | **$221.40** | **$42,332.00** |
| | **Item Code 664014 Total No. of Proj.** | | | **8** | | **Total Amount** | **$42,332.00** |
| **664015** | 450 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 4 | 2 | 12.00 | $483.33 | $5,800.00 |
| | | M | 5 | 1 | 170.00 | $94.00 | $15,980.00 |
| | | M | 7 | 9 | 945.00 | $316.74 | $299,322.00 |
| | | M | 10 | 2 | 29.00 | $436.52 | $12,659.00 |
| | **Unit Sub Total** | **M** | | **14** | **1,156.00** | **$288.72** | **$333,761.00** |
| | **Item Code 664015 Total No. of Proj.** | | | **14** | | **Total Amount** | **$333,761.00** |
| **664016** | 450 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | M | 1 | 1 | 140.00 | $500.00 | $70,000.00 |
| | | M | 3 | 2 | 108.00 | $242.59 | $26,200.00 |
| | | M | 5 | 1 | 15.00 | $800.00 | $12,000.00 |
| | **Unit Sub Total** | **M** | | **4** | **263.00** | **$411.41** | **$108,200.00** |
| | **Item Code 664016 Total No. of Proj.** | | | **4** | | **Total Amount** | **$108,200.00** |
| **664019** | 600 MM CORRUGATED STEEL PIPE (1.63 MM THICK) | M | 3 | 1 | 2.10 | $880.00 | $1,848.00 |
| | | M | 4 | 2 | 6.00 | $225.00 | $1,350.00 |
| | | M | 6 | 1 | 5.00 | $275.00 | $1,375.00 |
| | **Unit Sub Total** | **M** | | **4** | **13.10** | **$349.08** | **$4,573.00** |
| | **Item Code 664019 Total No. of Proj.** | | | **4** | | **Total Amount** | **$4,573.00** |
| **664020** | 600 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 4 | 2 | 2.00 | $1,150.00 | $2,300.00 |
| | | M | 5 | 2 | 29.00 | $209.14 | $6,065.00 |
| | | M | 7 | 1 | 70.00 | $448.00 | $31,360.00 |
| | | M | 8 | 1 | 17.00 | $250.00 | $4,250.00 |
| | | M | 9 | 1 | 2.00 | $715.00 | $1,430.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **664020** | 600 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 10 | 2 | 7.00 | $1,064.29 | $7,450.00 |
| | **Unit Sub Total** | **M** | | **9** | **127.00** | **$416.18** | **$52,855.00** |
| | **Item Code 664020 Total No. of Proj.** | | | **9** | | **Total Amount** | **$52,855.00** |
| **664021** | 600 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | M | 1 | 2 | 195.00 | $442.31 | $86,250.00 |
| | | M | 3 | 2 | 680.00 | $233.09 | $158,500.00 |
| | | M | 5 | 1 | 3.00 | $370.00 | $1,110.00 |
| | | M | 7 | 2 | 48.00 | $290.53 | $13,945.55 |
| | | M | 9 | 2 | 109.00 | $323.30 | $35,240.00 |
| | **Unit Sub Total** | **M** | | **9** | **1,035.00** | **$285.07** | **$295,045.55** |
| | **Item Code 664021 Total No. of Proj.** | | | **9** | | **Total Amount** | **$295,045.55** |
| **664022** | 600 MM CORRUGATED STEEL PIPE (3.51 MM THICK) | M | 1 | 1 | 47.00 | $482.00 | $22,654.00 |
| | **Unit Sub Total** | **M** | | **1** | **47.00** | **$482.00** | **$22,654.00** |
| | **Item Code 664022 Total No. of Proj.** | | | **1** | | **Total Amount** | **$22,654.00** |
| **664027** | 750 MM CORRUGATED STEEL PIPE (1.63 MM THICK) | M | 5 | 2 | 76.00 | $135.53 | $10,300.00 |
| | **Unit Sub Total** | **M** | | **2** | **76.00** | **$135.53** | **$10,300.00** |
| | **Item Code 664027 Total No. of Proj.** | | | **2** | | **Total Amount** | **$10,300.00** |
| **664028** | 750 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 7 | 1 | 68.00 | $484.00 | $32,912.00 |
| | **Unit Sub Total** | **M** | | **1** | **68.00** | **$484.00** | **$32,912.00** |
| | **Item Code 664028 Total No. of Proj.** | | | **1** | | **Total Amount** | **$32,912.00** |
| **664029** | 750 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | M | 1 | 1 | 18.00 | $650.00 | $11,700.00 |
| | | M | 3 | 1 | 10.00 | $500.00 | $5,000.00 |
| | | M | 9 | 1 | 58.00 | $804.00 | $46,632.00 |
| | **Unit Sub Total** | **M** | | **3** | **86.00** | **$736.42** | **$63,332.00** |
| | **Item Code 664029 Total No. of Proj.** | | | **3** | | **Total Amount** | **$63,332.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **664030** | 750 MM CORRUGATED STEEL PIPE (3.51 MM THICK) | M | 2 | 1 | 4.00 | $850.00 | $3,400.00 |
| | **Unit Sub Total** | **M** | | **1** | **4.00** | **$850.00** | **$3,400.00** |
| | **Item Code 664030 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,400.00** |
| **664032** | 900 MM CORRUGATED STEEL PIPE (1.63 MM THICK) | M | 5 | 1 | 8.00 | $639.00 | $5,112.00 |
| | **Unit Sub Total** | **M** | | **1** | **8.00** | **$639.00** | **$5,112.00** |
| | **Item Code 664032 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,112.00** |
| **664033** | 900 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 2 | 1 | 9.00 | $330.00 | $2,970.00 |
| | | M | 5 | 2 | 9.20 | $1,105.52 | $10,170.80 |
| | | M | 7 | 1 | 2.00 | $1,255.00 | $2,510.00 |
| | **Unit Sub Total** | **M** | | **4** | **20.20** | **$774.79** | **$15,650.80** |
| | **Item Code 664033 Total No. of Proj.** | | | **4** | | **Total Amount** | **$15,650.80** |
| **664034** | 900 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | M | 1 | 1 | 9.00 | $800.00 | $7,200.00 |
| | | M | 4 | 1 | 9.00 | $450.00 | $4,050.00 |
| | **Unit Sub Total** | **M** | | **2** | **18.00** | **$625.00** | **$11,250.00** |
| | **Item Code 664034 Total No. of Proj.** | | | **2** | | **Total Amount** | **$11,250.00** |
| **664035** | 900 MM CORRUGATED STEEL PIPE (3.51 MM THICK) | M | 10 | 1 | 3.00 | $860.00 | $2,580.00 |
| | **Unit Sub Total** | **M** | | **1** | **3.00** | **$860.00** | **$2,580.00** |
| | **Item Code 664035 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,580.00** |
| **664038** | 1050 MM CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 4 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **1.00** | **$1,000.00** | **$1,000.00** |
| | **Item Code 664038 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,000.00** |
| **664039** | 1050 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | M | 1 | 1 | 7.00 | $650.00 | $4,550.00 |
| | **Unit Sub Total** | **M** | | **1** | **7.00** | **$650.00** | **$4,550.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 664039 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,550.00** |
| **664044** | 1200 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | M | 1 | 1 | 23.00 | $600.00 | $13,800.00 |
| | **Unit Sub Total** | **M** | | **1** | **23.00** | **$600.00** | **$13,800.00** |
| | **Item Code 664044 Total No. of Proj.** | | | **1** | | **Total Amount** | **$13,800.00** |
| **664052** | 1500 MM CORRUGATED STEEL PIPE (2.77 MM THICK) | M | 9 | 1 | 5.00 | $1,060.00 | $5,300.00 |
| | **Unit Sub Total** | **M** | | **1** | **5.00** | **$1,060.00** | **$5,300.00** |
| | **Item Code 664052 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,300.00** |
| **664053** | 1500 MM CORRUGATED STEEL PIPE (3.51 MM THICK) | M | 2 | 1 | 2.50 | $800.00 | $2,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **2.50** | **$800.00** | **$2,000.00** |
| | **Item Code 664053 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,000.00** |
| **664081** | 250 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (1.63 MM THICK) | M | 10 | 1 | 200.00 | $200.00 | $40,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **200.00** | **$200.00** | **$40,000.00** |
| | **Item Code 664081 Total No. of Proj.** | | | **1** | | **Total Amount** | **$40,000.00** |
| **664085** | 300 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 4 | 1 | 170.00 | $100.00 | $17,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **170.00** | **$100.00** | **$17,000.00** |
| | **Item Code 664085 Total No. of Proj.** | | | **1** | | **Total Amount** | **$17,000.00** |
| **664089** | 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (1.63 MM THICK) | M | 4 | 1 | 14.00 | $1,000.00 | $14,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **14.00** | **$1,000.00** | **$14,000.00** |
| | **Item Code 664089 Total No. of Proj.** | | | **1** | | **Total Amount** | **$14,000.00** |
| **664090** | 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 3 | 1 | 290.00 | $250.00 | $72,500.00 |
| | | M | 4 | 1 | 55.00 | $235.00 | $12,925.00 |
| | **Unit Sub Total** | **M** | | **2** | **345.00** | **$247.61** | **$85,425.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 664090 Total No. of Proj.** | | | **2** | | **Total Amount** | **$85,425.00** |
| **664097** | 600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK) | M | 1 | 1 | 250.00 | $500.00 | $125,000.00 |
| | | M | 10 | 1 | 4.00 | $1,000.00 | $4,000.00 |
| | **Unit Sub Total** | **M** | | **2** | **254.00** | **$507.87** | **$129,000.00** |
| | **Item Code 664097 Total No. of Proj.** | | | **2** | | **Total Amount** | **$129,000.00** |
| **664105** | 750 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK) | M | 11 | 1 | 5.00 | $450.00 | $2,250.00 |
| | **Unit Sub Total** | **M** | | **1** | **5.00** | **$450.00** | **$2,250.00** |
| | **Item Code 664105 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,250.00** |
| **664109** | 900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 3 | 1 | 4.00 | $1,000.00 | $4,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **4.00** | **$1,000.00** | **$4,000.00** |
| | **Item Code 664109 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,000.00** |
| **664110** | 900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK) | M | 1 | 1 | 18.00 | $700.00 | $12,600.00 |
| | **Unit Sub Total** | **M** | | **1** | **18.00** | **$700.00** | **$12,600.00** |
| | **Item Code 664110 Total No. of Proj.** | | | **1** | | **Total Amount** | **$12,600.00** |
| **665003** | 6" CORRUGATED STEEL PIPE (.079" THICK) | LF | 3 | 1 | 590.00 | $25.00 | $14,750.00 |
| | **Unit Sub Total** | **LF** | | **1** | **590.00** | **$25.00** | **$14,750.00** |
| | **Item Code 665003 Total No. of Proj.** | | | **1** | | **Total Amount** | **$14,750.00** |
| **665012** | 12" CORRUGATED STEEL PIPE (.079" THICK) | LF | 2 | 2 | 43.00 | $106.98 | $4,600.00 |
| | | LF | 3 | 2 | 34.00 | $127.94 | $4,350.00 |
| | **Unit Sub Total** | **LF** | | **4** | **77.00** | **$116.23** | **$8,950.00** |
| | **Item Code 665012 Total No. of Proj.** | | | **4** | | **Total Amount** | **$8,950.00** |
| **665016** | 18" CORRUGATED STEEL PIPE (.064" THICK) | LF | 2 | 2 | 290.00 | $119.66 | $34,700.00 |
| | | LF | 5 | 1 | 10.00 | $55.00 | $550.00 |
| | | LF | 6 | 1 | 15.00 | $500.00 | $7,500.00 |
| | **Unit Sub Total** | **LF** | | **4** | **315.00** | **$135.71** | **$42,750.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 665016 Total No. of Proj.** | | | **4** | | **Total Amount** | **$42,750.00** |
| **665017** | 18" CORRUGATED STEEL PIPE (.079" THICK) | LF | 2 | 3 | 530.00 | $115.09 | $61,000.00 |
| | | LF | 3 | 2 | 690.00 | $65.65 | $45,300.00 |
| | | LF | 6 | 1 | 61.00 | $200.00 | $12,200.00 |
| | | LF | 12 | 1 | 79.00 | $125.00 | $9,875.00 |
| | **Unit Sub Total** | **LF** | | **7** | **1,360.00** | **$94.39** | **$128,375.00** |
| | **Item Code 665017 Total No. of Proj.** | | | **7** | | **Total Amount** | **$128,375.00** |
| **665018** | 18" CORRUGATED STEEL PIPE (.109" THICK) | LF | 1 | 1 | 6.00 | $361.00 | $2,166.00 |
| | | LF | 2 | 2 | 233.00 | $94.12 | $21,930.00 |
| | | LF | 3 | 2 | 43.00 | $261.86 | $11,260.00 |
| | **Unit Sub Total** | **LF** | | **5** | **282.00** | **$125.38** | **$35,356.00** |
| | **Item Code 665018 Total No. of Proj.** | | | **5** | | **Total Amount** | **$35,356.00** |
| **665022** | 24" CORRUGATED STEEL PIPE (.064" THICK) | LF | 2 | 2 | 58.00 | $192.76 | $11,180.00 |
| | **Unit Sub Total** | **LF** | | **2** | **58.00** | **$192.76** | **$11,180.00** |
| | **Item Code 665022 Total No. of Proj.** | | | **2** | | **Total Amount** | **$11,180.00** |
| **665023** | 24" CORRUGATED STEEL PIPE (.079" THICK) | LF | 2 | 1 | 38.00 | $246.50 | $9,367.00 |
| | | LF | 3 | 3 | 643.00 | $266.95 | $171,650.00 |
| | | LF | 6 | 1 | 190.00 | $210.00 | $39,900.00 |
| | | LF | 8 | 1 | 1,140.00 | $170.00 | $193,800.00 |
| | **Unit Sub Total** | **LF** | | **6** | **2,011.00** | **$206.22** | **$414,717.00** |
| | **Item Code 665023 Total No. of Proj.** | | | **6** | | **Total Amount** | **$414,717.00** |
| **665024** | 24" CORRUGATED STEEL PIPE (.109" THICK) | LF | 2 | 3 | 442.00 | $132.81 | $58,702.00 |
| | | LF | 3 | 2 | 33.00 | $246.27 | $8,127.00 |
| | | LF | 6 | 1 | 2.20 | $280.00 | $616.00 |
| | **Unit Sub Total** | **LF** | | **6** | **477.20** | **$141.33** | **$67,445.00** |
| | **Item Code 665024 Total No. of Proj.** | | | **6** | | **Total Amount** | **$67,445.00** |
| **665025** | 24" CORRUGATED STEEL PIPE (.138" THICK) | LF | 1 | 1 | 2.00 | $525.00 | $1,050.00 |
| | | LF | 3 | 1 | 12.00 | $800.00 | $9,600.00 |
| | | LF | 7 | 1 | 160.00 | $89.10 | $14,256.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **LF** | | **3** | **174.00** | **$143.14** | **$24,906.00** |
| | **Item Code 665025 Total No. of Proj.** | | | **3** | | **Total Amount** | **$24,906.00** |
| **665030** | 30" CORRUGATED STEEL PIPE (.064" THICK) | LF | 5 | 1 | 34.00 | $135.00 | $4,590.00 |
| | **Unit Sub Total** | **LF** | | **1** | **34.00** | **$135.00** | **$4,590.00** |
| | **Item Code 665030 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,590.00** |
| **665031** | 30" CORRUGATED STEEL PIPE (.079" THICK) | LF | 8 | 1 | 200.00 | $310.00 | $62,000.00 |
| | **Unit Sub Total** | **LF** | | **1** | **200.00** | **$310.00** | **$62,000.00** |
| | **Item Code 665031 Total No. of Proj.** | | | **1** | | **Total Amount** | **$62,000.00** |
| **665032** | 30" CORRUGATED STEEL PIPE (.109" THICK) | LF | 2 | 2 | 184.00 | $158.59 | $29,180.00 |
| | | LF | 3 | 1 | 3.00 | $515.00 | $1,545.00 |
| | **Unit Sub Total** | **LF** | | **3** | **187.00** | **$164.30** | **$30,725.00** |
| | **Item Code 665032 Total No. of Proj.** | | | **3** | | **Total Amount** | **$30,725.00** |
| **665036** | 36" CORRUGATED STEEL PIPE (.079" THICK) | LF | 3 | 1 | 110.00 | $500.00 | $55,000.00 |
| | | LF | 6 | 1 | 9.00 | $120.00 | $1,080.00 |
| | **Unit Sub Total** | **LF** | | **2** | **119.00** | **$471.26** | **$56,080.00** |
| | **Item Code 665036 Total No. of Proj.** | | | **2** | | **Total Amount** | **$56,080.00** |
| **665037** | 36" CORRUGATED STEEL PIPE (.109" THICK) | LF | 2 | 2 | 130.00 | $169.51 | $22,036.00 |
| | **Unit Sub Total** | **LF** | | **2** | **130.00** | **$169.51** | **$22,036.00** |
| | **Item Code 665037 Total No. of Proj.** | | | **2** | | **Total Amount** | **$22,036.00** |
| **665042** | 42" CORRUGATED STEEL PIPE (.109" THICK) | LF | 2 | 1 | 30.00 | $150.00 | $4,500.00 |
| | **Unit Sub Total** | **LF** | | **1** | **30.00** | **$150.00** | **$4,500.00** |
| | **Item Code 665042 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,500.00** |
| **665045** | 48" CORRUGATED STEEL PIPE (.064" THICK) | LF | 5 | 1 | 23.00 | $450.00 | $10,350.00 |
| | **Unit Sub Total** | **LF** | | **1** | **23.00** | **$450.00** | **$10,350.00** |
| | **Item Code 665045 Total No. of Proj.** | | | **1** | | **Total Amount** | **$10,350.00** |
| **665049** | 48" CORRUGATED STEEL PIPE (.168" THICK) | LF | 1 | 1 | 15.00 | $225.00 | $3,375.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **LF** | | **1** | **15.00** | **$225.00** | **$3,375.00** |
| | **Item Code 665049 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,375.00** |
| **665050** | 54" CORRUGATED STEEL PIPE (.079" THICK) | LF | 5 | 1 | 6.00 | $440.00 | $2,640.00 |
| | **Unit Sub Total** | **LF** | | **1** | **6.00** | **$440.00** | **$2,640.00** |
| | **Item Code 665050 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,640.00** |
| **665075** | 18" CORRUGATED STEEL PIPE (.138" THICK) | LF | 3 | 2 | 42.00 | $478.57 | $20,100.00 |
| | **Unit Sub Total** | **LF** | | **2** | **42.00** | **$478.57** | **$20,100.00** |
| | **Item Code 665075 Total No. of Proj.** | | | **2** | | **Total Amount** | **$20,100.00** |
| **665112** | 12" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK) | LF | 11 | 1 | 29.00 | $535.00 | $15,515.00 |
| | **Unit Sub Total** | **LF** | | **1** | **29.00** | **$535.00** | **$15,515.00** |
| | **Item Code 665112 Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,515.00** |
| **665278** | 750 MM BITUMINOUS COATED PAVED INVERT CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 11 | 1 | 6.00 | $600.00 | $3,600.00 |
| | **Unit Sub Total** | **M** | | **1** | **6.00** | **$600.00** | **$3,600.00** |
| | **Item Code 665278 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,600.00** |
| **665717** | 18" SLOTTED CORRUGATED STEEL PIPE (.079" THICK) | LF | 6 | 1 | 40.00 | $358.00 | $14,320.00 |
| | **Unit Sub Total** | **LF** | | **1** | **40.00** | **$358.00** | **$14,320.00** |
| | **Item Code 665717 Total No. of Proj.** | | | **1** | | **Total Amount** | **$14,320.00** |
| **665718** | 18" SLOTTED CORRUGATED STEEL PIPE (.168" THICK) | LF | 3 | 2 | 17,610.00 | $132.94 | $2,341,060.00 |
| | **Unit Sub Total** | **LF** | | **2** | **17,610.00** | **$132.94** | **$2,341,060.00** |
| | **Item Code 665718 Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,341,060.00** |
| **665729** | 300 MM SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 3 | 1 | 190.00 | $150.00 | $28,500.00 |
| | | M | 4 | 1 | 52.00 | $500.00 | $26,000.00 |
| | **Unit Sub Total** | **M** | | **2** | **242.00** | **$225.21** | **$54,500.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 665729 Total No. of Proj.** | | | **2** | | **Total Amount** | **$54,500.00** |
| **665730** | 300 MM SLOTTED CORRUGATED STEEL PIPE (2.77 MM THICK) | M | 1 | 1 | 11.00 | $600.00 | $6,600.00 |
| | **Unit Sub Total** | **M** | | **1** | **11.00** | **$600.00** | **$6,600.00** |
| | **Item Code 665730 Total No. of Proj.** | | | **1** | | **Total Amount** | **$6,600.00** |
| **665733** | 450 MM SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 4 | 2 | 327.00 | $322.11 | $105,330.00 |
| | | M | 5 | 1 | 16.00 | $1,100.00 | $17,600.00 |
| | | M | 7 | 3 | 12,830.00 | $366.11 | $4,697,150.00 |
| | **Unit Sub Total** | **M** | | **6** | **13,173.00** | **$365.91** | **$4,820,080.00** |
| | **Item Code 665733 Total No. of Proj.** | | | **6** | | **Total Amount** | **$4,820,080.00** |
| **665833** | 450 MM BITUMINOUS COATED SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK) | M | 3 | 1 | 380.00 | $400.00 | $152,000.00 |
| | | M | 4 | 1 | 25.00 | $400.00 | $10,000.00 |
| | **Unit Sub Total** | **M** | | **2** | **405.00** | **$400.00** | **$162,000.00** |
| | **Item Code 665833 Total No. of Proj.** | | | **2** | | **Total Amount** | **$162,000.00** |
| **667041** | 71" X 47" CORRUGATED STEEL PIPE ARCH (.109" THICK) | LF | 9 | 1 | 140.00 | $230.00 | $32,200.00 |
| | **Unit Sub Total** | **LF** | | **1** | **140.00** | **$230.00** | **$32,200.00** |
| | **Item Code 667041 Total No. of Proj.** | | | **1** | | **Total Amount** | **$32,200.00** |
| **667054** | 700 MM X 500 MM CORRUGATED STEEL PIPE ARCH (2.01 MM THICK) | M | 9 | 2 | 682.00 | $235.48 | $160,600.00 |
| | **Unit Sub Total** | **M** | | **2** | **682.00** | **$235.48** | **$160,600.00** |
| | **Item Code 667054 Total No. of Proj.** | | | **2** | | **Total Amount** | **$160,600.00** |
| **667055** | 700 MM X 500 MM CORRUGATED STEEL PIPE ARCH (2.77 MM THICK) | M | 4 | 1 | 90.00 | $285.00 | $25,650.00 |
| | **Unit Sub Total** | **M** | | **1** | **90.00** | **$285.00** | **$25,650.00** |
| | **Item Code 667055 Total No. of Proj.** | | | **1** | | **Total Amount** | **$25,650.00** |
| **667057** | 875 MM X 600 MM CORRUGATED STEEL PIPE ARCH (2.01 MM THICK) | M | 9 | 1 | 170.00 | $250.00 | $42,500.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **M** | | **1** | **170.00** | **$250.00** | **$42,500.00** |
| | **Item Code 667057 Total No. of Proj.** | | | **1** | | **Total Amount** | **$42,500.00** |
| **667060** | 1050 MM X 725 MM CORRUGATED STEEL PIPE ARCH (2.01 MM THICK) | M | 9 | 1 | 150.00 | $270.00 | $40,500.00 |
| | **Unit Sub Total** | **M** | | **1** | **150.00** | **$270.00** | **$40,500.00** |
| | **Item Code 667060 Total No. of Proj.** | | | **1** | | **Total Amount** | **$40,500.00** |
| **667064** | 1225 MM X 825 MM CORRUGATED STEEL PIPE ARCH (2.77 MM THICK) | M | 1 | 1 | 22.00 | $800.00 | $17,600.00 |
| | **Unit Sub Total** | **M** | | **1** | **22.00** | **$800.00** | **$17,600.00** |
| | **Item Code 667064 Total No. of Proj.** | | | **1** | | **Total Amount** | **$17,600.00** |
| **667070** | 1600 MM X 1075 MM CORRUGATED STEEL PIPE ARCH (2.77 MM THICK) | M | 9 | 1 | 55.00 | $450.00 | $24,750.00 |
| | **Unit Sub Total** | **M** | | **1** | **55.00** | **$450.00** | **$24,750.00** |
| | **Item Code 667070 Total No. of Proj.** | | | **1** | | **Total Amount** | **$24,750.00** |
| **680207** | 3" PLASTIC PIPE | LF | 2 | 1 | 13.00 | $15.00 | $195.00 |
| | **Unit Sub Total** | **LF** | | **1** | **13.00** | **$15.00** | **$195.00** |
| | **Item Code 680207 Total No. of Proj.** | | | **1** | | **Total Amount** | **$195.00** |
| **680226** | 6" SLOTTED CORRUGATED PLASTIC PIPE UNDERDRAIN | LF | 3 | 1 | 440.00 | $80.00 | $35,200.00 |
| | **Unit Sub Total** | **LF** | | **1** | **440.00** | **$80.00** | **$35,200.00** |
| | **Item Code 680226 Total No. of Proj.** | | | **1** | | **Total Amount** | **$35,200.00** |
| **680256** | 80 MM PLASTIC PIPE | M | 4 | 1 | 41.00 | $100.00 | $4,100.00 |
| | **Unit Sub Total** | **M** | | **1** | **41.00** | **$100.00** | **$4,100.00** |
| | **Item Code 680256 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,100.00** |
| **680259** | 80 MM SLOTTED PLASTIC PIPE | M | 5 | 1 | 1,100.00 | $60.00 | $66,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **1,100.00** | **$60.00** | **$66,000.00** |
| | **Item Code 680259 Total No. of Proj.** | | | **1** | | **Total Amount** | **$66,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **680264** | 80 MM PLASTIC PIPE (OUTLET) | M | 11 | 1 | 84.00 | $250.00 | $21,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **84.00** | **$250.00** | **$21,000.00** |
| | **Item Code 680264 Total No. of Proj.** | | | **1** | | **Total Amount** | **$21,000.00** |
| **680271** | 80 MM PLASTIC PIPE UNDERDRAIN | M | 7 | 1 | 49.00 | $20.00 | $980.00 |
| | **Unit Sub Total** | **M** | | **1** | **49.00** | **$20.00** | **$980.00** |
| | **Item Code 680271 Total No. of Proj.** | | | **1** | | **Total Amount** | **$980.00** |
| **680272** | 100 MM PLASTIC PIPE UNDERDRAIN | M | 11 | 2 | 1,880.00 | $61.33 | $115,300.00 |
| | **Unit Sub Total** | **M** | | **2** | **1,880.00** | **$61.33** | **$115,300.00** |
| | **Item Code 680272 Total No. of Proj.** | | | **2** | | **Total Amount** | **$115,300.00** |
| **680273** | 80 MM SLOTTED PLASTIC PIPE UNDERDRAIN | M | 7 | 1 | 71.00 | $20.00 | $1,420.00 |
| | **Unit Sub Total** | **M** | | **1** | **71.00** | **$20.00** | **$1,420.00** |
| | **Item Code 680273 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,420.00** |
| **680285** | 4" PLASTIC PIPE UNDERDRAIN | LF | 4 | 1 | 180.00 | $11.39 | $2,050.20 |
| | **Unit Sub Total** | **LF** | | **1** | **180.00** | **$11.39** | **$2,050.20** |
| | **Item Code 680285 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,050.20** |
| **680405** | 8" PERFORATED STEEL PIPE UNDERDRAIN (.064" THICK) | LF | 3 | 2 | 510.00 | $52.77 | $26,912.50 |
| | **Unit Sub Total** | **LF** | | **2** | **510.00** | **$52.77** | **$26,912.50** |
| | **Item Code 680405 Total No. of Proj.** | | | **2** | | **Total Amount** | **$26,912.50** |
| **680406** | 8" PERFORATED STEEL PIPE UNDERDRAIN (.079" THICK) | LF | 3 | 1 | 24.00 | $175.00 | $4,200.00 |
| | **Unit Sub Total** | **LF** | | **1** | **24.00** | **$175.00** | **$4,200.00** |
| | **Item Code 680406 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,200.00** |
| **680461** | 150 MM PERFORATED STEEL PIPE UNDERDRAIN | M | 2 | 1 | 26.00 | $135.00 | $3,510.00 |
| | **Unit Sub Total** | **M** | | **1** | **26.00** | **$135.00** | **$3,510.00** |
| | **Item Code 680461 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,510.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **680465** | 200 MM PERFORATED STEEL PIPE UNDERDRAIN (1.63 MM THICK) | M | 5 | 1 | 10.00 | $245.00 | $2,450.00 |
| | **Unit Sub Total** | **M** | | **1** | **10.00** | **$245.00** | **$2,450.00** |
| | **Item Code 680465 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,450.00** |
| **680469** | 300 MM PERFORATED STEEL PIPE UNDERDRAIN (2.01 MM THICK) | M | 7 | 1 | 110.00 | $295.00 | $32,450.00 |
| | **Unit Sub Total** | **M** | | **1** | **110.00** | **$295.00** | **$32,450.00** |
| | **Item Code 680469 Total No. of Proj.** | | | **1** | | **Total Amount** | **$32,450.00** |
| **680903** | 6" NON-PERFORATED PLASTIC PIPE UNDERDRAIN | LF | 3 | 1 | 200.00 | $40.00 | $8,000.00 |
| | **Unit Sub Total** | **LF** | | **1** | **200.00** | **$40.00** | **$8,000.00** |
| | **Item Code 680903 Total No. of Proj.** | | | **1** | | **Total Amount** | **$8,000.00** |
| **680905** | 8" PERFORATED PLASTIC PIPE UNDERDRAIN | LF | 1 | 2 | 660.00 | $44.55 | $29,400.00 |
| | | LF | 2 | 1 | 400.00 | $80.00 | $32,000.00 |
| | | LF | 3 | 2 | 39,960.00 | $41.96 | $1,676,600.00 |
| | | LF | 4 | 1 | 270.00 | $70.00 | $18,900.00 |
| | | LF | 6 | 1 | 1,210.00 | $35.00 | $42,350.00 |
| | **Unit Sub Total** | **LF** | | **7** | **42,500.00** | **$42.34** | **$1,799,250.00** |
| | **Item Code 680905 Total No. of Proj.** | | | **7** | | **Total Amount** | **$1,799,250.00** |
| **680931** | 150 MM PERFORATED PLASTIC PIPE UNDERDRAIN | M | 4 | 2 | 768.00 | $68.54 | $52,640.00 |
| | | M | 7 | 1 | 720.00 | $125.00 | $90,000.00 |
| | **Unit Sub Total** | **M** | | **3** | **1,488.00** | **$95.86** | **$142,640.00** |
| | **Item Code 680931 Total No. of Proj.** | | | **3** | | **Total Amount** | **$142,640.00** |
| **680932** | 150 MM NON-PERFORATED PLASTIC PIPE UNDERDRAIN | M | 4 | 1 | 42.00 | $90.00 | $3,780.00 |
| | | M | 7 | 1 | 12.00 | $230.00 | $2,760.00 |
| | **Unit Sub Total** | **M** | | **2** | **54.00** | **$121.11** | **$6,540.00** |
| | **Item Code 680932 Total No. of Proj.** | | | **2** | | **Total Amount** | **$6,540.00** |
| **680933** | 200 MM PERFORATED PLASTIC PIPE UNDERDRAIN | M | 1 | 2 | 360.00 | $65.50 | $23,580.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **680933** | 200 MM PERFORATED PLASTIC PIPE UNDERDRAIN | M | 2 | 1 | 15.00 | $20.00 | $300.00 |
| | | M | 4 | 3 | 1,895.00 | $97.05 | $183,904.00 |
| | **Unit Sub Total** | **M** | | **6** | **2,270.00** | **$91.53** | **$207,784.00** |
| | **Item Code 680933 Total No. of Proj.** | | | **6** | | **Total Amount** | **$207,784.00** |
| **681023** | 6" PLASTIC PIPE | LF | 11 | 1 | 18.00 | $100.00 | $1,800.00 |
| | **Unit Sub Total** | **LF** | | **1** | **18.00** | **$100.00** | **$1,800.00** |
| | **Item Code 681023 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,800.00** |
| **681066** | 150 MM PLASTIC PIPE | M | 4 | 1 | 37.00 | $82.00 | $3,034.00 |
| | | M | 5 | 1 | 40.00 | $220.00 | $8,800.00 |
| | | M | 11 | 2 | 59.00 | $125.85 | $7,425.00 |
| | **Unit Sub Total** | **M** | | **4** | **136.00** | **$141.61** | **$19,259.00** |
| | **Item Code 681066 Total No. of Proj.** | | | **4** | | **Total Amount** | **$19,259.00** |
| **681067** | 250 MM PERFORATED PLASTIC PIPE UNDERDRAIN | M | 1 | 1 | 39.00 | $250.00 | $9,750.00 |
| | **Unit Sub Total** | **M** | | **1** | **39.00** | **$250.00** | **$9,750.00** |
| | **Item Code 681067 Total No. of Proj.** | | | **1** | | **Total Amount** | **$9,750.00** |
| **681103** | 3" PLASTIC PIPE (EDGE DRAIN) | LF | 11 | 1 | 8,190.00 | $10.00 | $81,900.00 |
| | **Unit Sub Total** | **LF** | | **1** | **8,190.00** | **$10.00** | **$81,900.00** |
| | **Item Code 681103 Total No. of Proj.** | | | **1** | | **Total Amount** | **$81,900.00** |
| **681107** | 3" PLASTIC PIPE (EDGE DRAIN OUTLET) | LF | 11 | 1 | 380.00 | $53.00 | $20,140.00 |
| | **Unit Sub Total** | **LF** | | **1** | **380.00** | **$53.00** | **$20,140.00** |
| | **Item Code 681107 Total No. of Proj.** | | | **1** | | **Total Amount** | **$20,140.00** |
| **681132** | GEOCOMPOSITE DRAIN | M2 | 3 | 1 | 25,000.00 | $12.00 | $300,000.00 |
| | | M2 | 4 | 1 | 161.00 | $150.00 | $24,150.00 |
| | **Unit Sub Total** | **M2** | | **2** | **25,161.00** | **$12.88** | **$324,150.00** |
| | **Item Code 681132 Total No. of Proj.** | | | **2** | | **Total Amount** | **$324,150.00** |
| **681134** | 80 MM PLASTIC PIPE (EDGE DRAIN) | M | 2 | 1 | 2,100.00 | $58.00 | $121,800.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **681134** | 80 MM PLASTIC PIPE (EDGE DRAIN) | M | 4 | 2 | 1,730.00 | $19.54 | $33,800.00 |
| | | M | 5 | 2 | 10,363.00 | $10.30 | $106,780.00 |
| | | M | 7 | 1 | 33.00 | $100.00 | $3,300.00 |
| | | M | 11 | 2 | 3,790.00 | $41.97 | $159,050.00 |
| | **Unit Sub Total** | **M** | | **8** | **18,016.00** | **$23.58** | **$424,730.00** |
| | **Item Code 681134 Total No. of Proj.** | | | **8** | | **Total Amount** | **$424,730.00** |
| **681137** | 80 MM PLASTIC PIPE (EDGE DRAIN OUTLET) | M | 2 | 2 | 438.00 | $83.42 | $36,540.00 |
| | | M | 3 | 1 | 110.00 | $60.00 | $6,600.00 |
| | | M | 4 | 2 | 236.00 | $128.81 | $30,400.00 |
| | | M | 5 | 1 | 710.00 | $26.50 | $18,815.00 |
| | | M | 11 | 1 | 85.00 | $142.00 | $12,070.00 |
| | **Unit Sub Total** | **M** | | **7** | **1,579.00** | **$66.13** | **$104,425.00** |
| | **Item Code 681137 Total No. of Proj.** | | | **7** | | **Total Amount** | **$104,425.00** |
| **681141** | 100 MM PLASTIC PIPE (EDGE DRAIN OUTLET) | M | 4 | 1 | 4.00 | $150.00 | $600.00 |
| | **Unit Sub Total** | **M** | | **1** | **4.00** | **$150.00** | **$600.00** |
| | **Item Code 681141 Total No. of Proj.** | | | **1** | | **Total Amount** | **$600.00** |
| **681501** | FURNISH AND INSTALL DRAIN PIPE (HORIZONTAL DRAIN) | LF | 1 | 1 | 2,570.00 | $1.50 | $3,855.00 |
| | | LF | 3 | 1 | 2,510.00 | $21.00 | $52,710.00 |
| | **Unit Sub Total** | **LF** | | **2** | **5,080.00** | **$11.13** | **$56,565.00** |
| **681501** | FURNISH AND INSTALL DRAIN PIPE (HORIZONTAL DRAIN) | M | 4 | 1 | 81.00 | $20.00 | $1,620.00 |
| | | M | 5 | 1 | 250.00 | $15.50 | $3,875.00 |
| | **Unit Sub Total** | **M** | | **2** | **331.00** | **$16.60** | **$5,495.00** |
| | **Item Code 681501 Total No. of Proj.** | | | **4** | | **Total Amount** | **$62,060.00** |
| **681502** | DRILL HOLE (HORIZONTAL DRAIN) | LF | 1 | 1 | 2,540.00 | $22.70 | $57,658.00 |
| | | LF | 3 | 1 | 2,220.00 | $9.00 | $19,980.00 |
| | **Unit Sub Total** | **LF** | | **2** | **4,760.00** | **$16.31** | **$77,638.00** |
| **681502** | DRILL HOLE (HORIZONTAL DRAIN) | M | 4 | 1 | 81.00 | $120.00 | $9,720.00 |
| | | M | 5 | 1 | 240.00 | $50.00 | $12,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **M** | | **2** | **321.00** | **$67.66** | **$21,720.00** |
| | **Item Code 681502 Total No. of Proj.** | | | **4** | | **Total Amount** | **$99,358.00** |
| **681512** | 8" COLLECTOR SYSTEM (HORIZONTAL DRAIN) | LF | 3 | 1 | 260.00 | $22.00 | $5,720.00 |
| | **Unit Sub Total** | **LF** | | **1** | **260.00** | **$22.00** | **$5,720.00** |
| | **Item Code 681512 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,720.00** |
| **681592** | 200 MM COLLECTOR SYSTEM (HORIZONTAL DRAIN) | M | 5 | 1 | 82.00 | $35.00 | $2,870.00 |
| | **Unit Sub Total** | **M** | | **1** | **82.00** | **$35.00** | **$2,870.00** |
| | **Item Code 681592 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,870.00** |
| **681990** | FILTER FABRIC | M2 | 1 | 1 | 3,000.00 | $1.00 | $3,000.00 |
| | | M2 | 4 | 1 | 4,600.00 | $1.85 | $8,510.00 |
| | | M2 | 5 | 2 | 4,502.00 | $2.63 | $11,860.00 |
| | **Unit Sub Total** | **M2** | | **4** | **12,102.00** | **$1.93** | **$23,370.00** |
| **681990** | FILTER FABRIC | SQYD | 2 | 1 | 180.00 | $10.00 | $1,800.00 |
| | **Unit Sub Total** | **SQYD** | | **1** | **180.00** | **$10.00** | **$1,800.00** |
| | **Item Code 681990 Total No. of Proj.** | | | **5** | | **Total Amount** | **$25,170.00** |
| **682001** | PERMEABLE MATERIAL | CY | 1 | 1 | 110.00 | $125.00 | $13,750.00 |
| | | CY | 2 | 1 | 17.00 | $194.00 | $3,298.00 |
| | | CY | 3 | 2 | 400.00 | $124.00 | $49,600.00 |
| | **Unit Sub Total** | **CY** | | **4** | **527.00** | **$126.47** | **$66,648.00** |
| **682001** | PERMEABLE MATERIAL | M3 | 3 | 1 | 226.00 | $140.00 | $31,640.00 |
| | **Unit Sub Total** | **M3** | | **1** | **226.00** | **$140.00** | **$31,640.00** |
| **682001** | PERMEABLE MATERIAL | TONN | 2 | 1 | 890.00 | $57.00 | $50,730.00 |
| | **Unit Sub Total** | **TONN** | | **1** | **890.00** | **$57.00** | **$50,730.00** |
| | **Item Code 682001 Total No. of Proj.** | | | **6** | | **Total Amount** | **$149,018.00** |
| **682008** | PERMEABLE MATERIAL (BLANKET) | CY | 4 | 2 | 56.00 | $163.91 | $9,179.20 |
| | **Unit Sub Total** | **CY** | | **2** | **56.00** | **$163.91** | **$9,179.20** |
| **682008** | PERMEABLE MATERIAL (BLANKET) | M3 | 4 | 2 | 2,950.00 | $62.37 | $184,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **682008** | PERMEABLE MATERIAL (BLANKET) | M3 | 11 | 1 | 25,800.00 | $93.00 | $2,399,400.00 |
| | **Unit Sub Total** | **M3** | | **3** | **28,750.00** | **$89.86** | **$2,583,400.00** |
| | **Item Code 682008 Total No. of Proj.** | | | **5** | | **Total Amount** | **$2,592,579.20** |
| **682020** | CLASS 1 PERMEABLE MATERIAL | CY | 1 | 1 | 23.00 | $122.00 | $2,806.00 |
| | | CY | 3 | 1 | 27.00 | $70.00 | $1,890.00 |
| | **Unit Sub Total** | **CY** | | **2** | **50.00** | **$93.92** | **$4,696.00** |
| **682020** | CLASS 1 PERMEABLE MATERIAL | M3 | 1 | 1 | 710.00 | $110.00 | $78,100.00 |
| | | M3 | 5 | 1 | 800.00 | $70.00 | $56,000.00 |
| | **Unit Sub Total** | **M3** | | **2** | **1,510.00** | **$88.81** | **$134,100.00** |
| | **Item Code 682020 Total No. of Proj.** | | | **4** | | **Total Amount** | **$138,796.00** |
| **682045** | CLASS 3 PERMEABLE MATERIAL | CY | 4 | 2 | 46.00 | $128.26 | $5,900.00 |
| | **Unit Sub Total** | **CY** | | **2** | **46.00** | **$128.26** | **$5,900.00** |
| | **Item Code 682045 Total No. of Proj.** | | | **2** | | **Total Amount** | **$5,900.00** |
| **682049** | CLASS 3 PERMEABLE MATERIAL (BLANKET) | M3 | 4 | 2 | 3,880.00 | $76.49 | $296,800.00 |
| | | M3 | 9 | 1 | 320.00 | $40.00 | $12,800.00 |
| | **Unit Sub Total** | **M3** | | **3** | **4,200.00** | **$73.71** | **$309,600.00** |
| | **Item Code 682049 Total No. of Proj.** | | | **3** | | **Total Amount** | **$309,600.00** |
| **685020** | 8" ALTERNATIVE PIPE UNDERDRAIN | LF | 2 | 1 | 370.00 | $55.00 | $20,350.00 |
| | **Unit Sub Total** | **LF** | | **1** | **370.00** | **$55.00** | **$20,350.00** |
| | **Item Code 685020 Total No. of Proj.** | | | **1** | | **Total Amount** | **$20,350.00** |
| **685062** | 150 MM ALTERNATIVE PIPE UNDERDRAIN | M | 11 | 1 | 280.00 | $100.00 | $28,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **280.00** | **$100.00** | **$28,000.00** |
| | **Item Code 685062 Total No. of Proj.** | | | **1** | | **Total Amount** | **$28,000.00** |
| **690104** | 8" CORRUGATED STEEL PIPE DOWNDRAIN | LF | 3 | 1 | 1,400.00 | $70.00 | $98,000.00 |
| | **Unit Sub Total** | **LF** | | **1** | **1,400.00** | **$70.00** | **$98,000.00** |
| | **Item Code 690104 Total No. of Proj.** | | | **1** | | **Total Amount** | **$98,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **690106** | 8" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK) | LF | 2 | 1 | 3.00 | $75.00 | $225.00 |
| | **Unit Sub Total** | **LF** | | **1** | **3.00** | **$75.00** | **$225.00** |
| | **Item Code 690106 Total No. of Proj.** | | | **1** | | **Total Amount** | **$225.00** |
| **690110** | 12" CORRUGATED STEEL PIPE DOWNDRAIN | LF | 2 | 1 | 56.00 | $84.00 | $4,704.00 |
| | **Unit Sub Total** | **LF** | | **1** | **56.00** | **$84.00** | **$4,704.00** |
| | **Item Code 690110 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,704.00** |
| **690112** | 12" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK) | LF | 1 | 2 | 130.00 | $54.62 | $7,100.00 |
| | | LF | 2 | 1 | 55.00 | $68.00 | $3,740.00 |
| | | LF | 3 | 2 | 480.00 | $45.06 | $21,630.00 |
| | **Unit Sub Total** | **LF** | | **5** | **665.00** | **$48.83** | **$32,470.00** |
| | **Item Code 690112 Total No. of Proj.** | | | **5** | | **Total Amount** | **$32,470.00** |
| **690116** | 18" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK) | LF | 4 | 1 | 20.00 | $150.00 | $3,000.00 |
| | | LF | 5 | 1 | 57.00 | $44.00 | $2,508.00 |
| | **Unit Sub Total** | **LF** | | **2** | **77.00** | **$71.53** | **$5,508.00** |
| | **Item Code 690116 Total No. of Proj.** | | | **2** | | **Total Amount** | **$5,508.00** |
| **690117** | 18" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK) | LF | 6 | 1 | 1,500.00 | $125.00 | $187,500.00 |
| | **Unit Sub Total** | **LF** | | **1** | **1,500.00** | **$125.00** | **$187,500.00** |
| | **Item Code 690117 Total No. of Proj.** | | | **1** | | **Total Amount** | **$187,500.00** |
| **690118** | 18" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK) | LF | 1 | 1 | 62.00 | $170.00 | $10,540.00 |
| | | LF | 3 | 1 | 920.00 | $50.00 | $46,000.00 |
| | **Unit Sub Total** | **LF** | | **2** | **982.00** | **$57.58** | **$56,540.00** |
| | **Item Code 690118 Total No. of Proj.** | | | **2** | | **Total Amount** | **$56,540.00** |
| **690122** | 24" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK) | LF | 4 | 1 | 8.00 | $200.00 | $1,600.00 |
| | **Unit Sub Total** | **LF** | | **1** | **8.00** | **$200.00** | **$1,600.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 690122 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,600.00** |
| **690124** | 24" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK) | LF | 2 | 1 | 400.00 | $75.00 | $30,000.00 |
| | | LF | 3 | 2 | 320.00 | $111.81 | $35,780.00 |
| | **Unit Sub Total** | **LF** | | **3** | **720.00** | **$91.36** | **$65,780.00** |
| | **Item Code 690124 Total No. of Proj.** | | | **3** | | **Total Amount** | **$65,780.00** |
| **690125** | 24" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK) | LF | 3 | 1 | 180.00 | $82.00 | $14,760.00 |
| | **Unit Sub Total** | **LF** | | **1** | **180.00** | **$82.00** | **$14,760.00** |
| | **Item Code 690125 Total No. of Proj.** | | | **1** | | **Total Amount** | **$14,760.00** |
| **690137** | 36" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK) | LF | 2 | 1 | 120.00 | $95.00 | $11,400.00 |
| | **Unit Sub Total** | **LF** | | **1** | **120.00** | **$95.00** | **$11,400.00** |
| | **Item Code 690137 Total No. of Proj.** | | | **1** | | **Total Amount** | **$11,400.00** |
| **690158** | 300 MM CORRUGATED STEEL PIPE DOWNDRAIN | M | 4 | 1 | 6.00 | $190.00 | $1,140.00 |
| | **Unit Sub Total** | **M** | | **1** | **6.00** | **$190.00** | **$1,140.00** |
| | **Item Code 690158 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,140.00** |
| **690160** | 300 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK) | M | 3 | 1 | 16.00 | $225.00 | $3,600.00 |
| | **Unit Sub Total** | **M** | | **1** | **16.00** | **$225.00** | **$3,600.00** |
| | **Item Code 690160 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,600.00** |
| **690165** | 450 MM CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK) | M | 4 | 2 | 13.00 | $588.21 | $7,646.75 |
| | **Unit Sub Total** | **M** | | **2** | **13.00** | **$588.21** | **$7,646.75** |
| | **Item Code 690165 Total No. of Proj.** | | | **2** | | **Total Amount** | **$7,646.75** |
| **690166** | 450 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK) | M | 7 | 3 | 112.00 | $377.81 | $42,315.00 |
| | **Unit Sub Total** | **M** | | **3** | **112.00** | **$377.81** | **$42,315.00** |
| | **Item Code 690166 Total No. of Proj.** | | | **3** | | **Total Amount** | **$42,315.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **690167** | 450 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK) | M | 3 | 1 | 59.00 | $250.00 | $14,750.00 |
| | | M | 4 | 1 | 18.00 | $170.00 | $3,060.00 |
| | | M | 7 | 2 | 12.50 | $268.00 | $3,350.00 |
| | **Unit Sub Total** | **M** | | **4** | **89.50** | **$236.42** | **$21,160.00** |
| | **Item Code 690167 Total No. of Proj.** | | | **4** | | **Total Amount** | **$21,160.00** |
| **690170** | 600 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK) | M | 7 | 1 | 7.00 | $250.00 | $1,750.00 |
| | **Unit Sub Total** | **M** | | **1** | **7.00** | **$250.00** | **$1,750.00** |
| | **Item Code 690170 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,750.00** |
| **690171** | 600 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK) | M | 7 | 1 | 50.00 | $150.00 | $7,500.00 |
| | **Unit Sub Total** | **M** | | **1** | **50.00** | **$150.00** | **$7,500.00** |
| | **Item Code 690171 Total No. of Proj.** | | | **1** | | **Total Amount** | **$7,500.00** |
| **690273** | 300 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK) | M | 11 | 1 | 4.00 | $750.00 | $3,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **4.00** | **$750.00** | **$3,000.00** |
| | **Item Code 690273 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,000.00** |
| **690275** | 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK) | M | 4 | 1 | 26.00 | $300.00 | $7,800.00 |
| | **Unit Sub Total** | **M** | | **1** | **26.00** | **$300.00** | **$7,800.00** |
| | **Item Code 690275 Total No. of Proj.** | | | **1** | | **Total Amount** | **$7,800.00** |
| **690276** | 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK) | M | 5 | 1 | 40.00 | $50.00 | $2,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **40.00** | **$50.00** | **$2,000.00** |
| | **Item Code 690276 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,000.00** |
| **690277** | 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK) | M | 11 | 2 | 242.00 | $339.29 | $82,108.00 |
| | **Unit Sub Total** | **M** | | **2** | **242.00** | **$339.29** | **$82,108.00** |
| | **Item Code 690277 Total No. of Proj.** | | | **2** | | **Total Amount** | **$82,108.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **690281** | 600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK) | M | 11 | 4 | 416.00 | $282.24 | $117,410.00 |
| | **Unit Sub Total** | **M** | | **4** | **416.00** | **$282.24** | **$117,410.00** |
| | **Item Code 690281 Total No. of Proj.** | | | **4** | | **Total Amount** | **$117,410.00** |
| **690282** | 600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (3.51 MM THICK) | M | 11 | 1 | 120.00 | $200.00 | $24,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **120.00** | **$200.00** | **$24,000.00** |
| | **Item Code 690282 Total No. of Proj.** | | | **1** | | **Total Amount** | **$24,000.00** |
| **690297** | 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (3.51 MM THICK) | M | 11 | 1 | 130.00 | $240.00 | $31,200.00 |
| | **Unit Sub Total** | **M** | | **1** | **130.00** | **$240.00** | **$31,200.00** |
| | **Item Code 690297 Total No. of Proj.** | | | **1** | | **Total Amount** | **$31,200.00** |
| **691001** | CORRUGATED STEEL FLUME DOWNDRAIN | LF | 1 | 1 | 260.00 | $35.00 | $9,100.00 |
| | **Unit Sub Total** | **LF** | | **1** | **260.00** | **$35.00** | **$9,100.00** |
| | **Item Code 691001 Total No. of Proj.** | | | **1** | | **Total Amount** | **$9,100.00** |
| **691004** | 10" CORRUGATED STEEL FLUME DOWNDRAIN | LF | 3 | 1 | 40.00 | $45.00 | $1,800.00 |
| | **Unit Sub Total** | **LF** | | **1** | **40.00** | **$45.00** | **$1,800.00** |
| | **Item Code 691004 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,800.00** |
| **691900** | FLUME DOWNDRAIN | LF | 6 | 1 | 26.00 | $210.00 | $5,460.00 |
| | **Unit Sub Total** | **LF** | | **1** | **26.00** | **$210.00** | **$5,460.00** |
| **691900** | FLUME DOWNDRAIN | M | 2 | 1 | 94.00 | $135.00 | $12,690.00 |
| | | M | 8 | 1 | 250.00 | $300.00 | $75,000.00 |
| | | M | 10 | 2 | 190.00 | $122.32 | $23,241.00 |
| | **Unit Sub Total** | **M** | | **4** | **534.00** | **$207.74** | **$110,931.00** |
| | **Item Code 691900 Total No. of Proj.** | | | **5** | | **Total Amount** | **$116,391.00** |
| **691902** | 10" FLUME DOWNDRAIN | LF | 2 | 1 | 36.00 | $68.00 | $2,448.00 |
| | **Unit Sub Total** | **LF** | | **1** | **36.00** | **$68.00** | **$2,448.00** |
| | **Item Code 691902 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,448.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **692001** | ENTRANCE TAPER | EA | 4 | 1 | 1.00 | $300.00 | $300.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$300.00** | **$300.00** |
| | **Item Code 692001 Total No. of Proj.** | | | **1** | | **Total Amount** | **$300.00** |
| **692003** | 8" ENTRANCE TAPER | EA | 2 | 2 | 2.00 | $300.00 | $600.00 |
| | **Unit Sub Total** | **EA** | | **2** | **2.00** | **$300.00** | **$600.00** |
| | **Item Code 692003 Total No. of Proj.** | | | **2** | | **Total Amount** | **$600.00** |
| **692005** | 12" ENTRANCE TAPER | EA | 1 | 2 | 2.00 | $950.00 | $1,900.00 |
| | | EA | 2 | 2 | 3.00 | $300.00 | $900.00 |
| | | EA | 3 | 1 | 5.00 | $500.00 | $2,500.00 |
| | **Unit Sub Total** | **EA** | | **5** | **10.00** | **$530.00** | **$5,300.00** |
| | **Item Code 692005 Total No. of Proj.** | | | **5** | | **Total Amount** | **$5,300.00** |
| **692007** | 18" ENTRANCE TAPER | EA | 5 | 1 | 2.00 | $852.00 | $1,704.00 |
| | | EA | 6 | 1 | 37.00 | $550.00 | $20,350.00 |
| | **Unit Sub Total** | **EA** | | **2** | **39.00** | **$565.49** | **$22,054.00** |
| | **Item Code 692007 Total No. of Proj.** | | | **2** | | **Total Amount** | **$22,054.00** |
| **692088** | 300 MM ENTRANCE TAPER | EA | 5 | 3 | 39.00 | $663.59 | $25,880.00 |
| | **Unit Sub Total** | **EA** | | **3** | **39.00** | **$663.59** | **$25,880.00** |
| | **Item Code 692088 Total No. of Proj.** | | | **3** | | **Total Amount** | **$25,880.00** |
| **692090** | 450 MM ENTRANCE TAPER | EA | 3 | 1 | 2.00 | $800.00 | $1,600.00 |
| | | EA | 5 | 2 | 7.00 | $1,767.86 | $12,375.00 |
| | | EA | 7 | 1 | 4.00 | $700.00 | $2,800.00 |
| | **Unit Sub Total** | **EA** | | **4** | **13.00** | **$1,290.38** | **$16,775.00** |
| | **Item Code 692090 Total No. of Proj.** | | | **4** | | **Total Amount** | **$16,775.00** |
| **692095** | 450 MM BITUMINOUS COATED ENTRANCE TAPER | EA | 5 | 1 | 2.00 | $550.00 | $1,100.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$550.00** | **$1,100.00** |
| | **Item Code 692095 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,100.00** |
| **692101** | TAPERED INLET | EA | 1 | 1 | 10.00 | $95.00 | $950.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **692101** | TAPERED INLET | EA | 2 | 1 | 9.00 | $550.00 | $4,950.00 |
| | | EA | 6 | 1 | 2.00 | $220.00 | $440.00 |
| | | EA | 8 | 1 | 23.00 | $375.00 | $8,625.00 |
| | | EA | 10 | 2 | 43.00 | $271.88 | $11,691.00 |
| | **Unit Sub Total** | **EA** | | **6** | **87.00** | **$306.39** | **$26,656.00** |
| | **Item Code 692101 Total No. of Proj.** | | | **6** | | **Total Amount** | **$26,656.00** |
| **692104** | 10" TAPERED INLET | EA | 2 | 1 | 2.00 | $200.00 | $400.00 |
| | | EA | 3 | 1 | 1.00 | $500.00 | $500.00 |
| | **Unit Sub Total** | **EA** | | **2** | **3.00** | **$300.00** | **$900.00** |
| | **Item Code 692104 Total No. of Proj.** | | | **2** | | **Total Amount** | **$900.00** |
| **692209** | 24" DOWNDRAIN SLIP JOINT | EA | 1 | 1 | 2.00 | $700.00 | $1,400.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$700.00** | **$1,400.00** |
| | **Item Code 692209 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,400.00** |
| **692237** | 18" BITUMINOUS COATED DOWNDRAIN SLIP JOINT | EA | 5 | 1 | 2.00 | $550.00 | $1,100.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$550.00** | **$1,100.00** |
| | **Item Code 692237 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,100.00** |
| **692245** | 300 MM DOWNDRAIN SLIP JOINT | EA | 5 | 1 | 1.00 | $2,500.00 | $2,500.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$2,500.00** | **$2,500.00** |
| | **Item Code 692245 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,500.00** |
| **692301** | ANCHOR ASSEMBLY | EA | 2 | 1 | 32.00 | $700.00 | $22,400.00 |
| | | EA | 3 | 1 | 8.00 | $200.00 | $1,600.00 |
| | | EA | 4 | 2 | 3.00 | $1,124.55 | $3,373.66 |
| | | EA | 5 | 2 | 32.00 | $525.00 | $16,800.00 |
| | | EA | 6 | 1 | 51.00 | $375.00 | $19,125.00 |
| | **Unit Sub Total** | **EA** | | **7** | **126.00** | **$502.37** | **$63,298.66** |
| | **Item Code 692301 Total No. of Proj.** | | | **7** | | **Total Amount** | **$63,298.66** |
| **692305** | 12" ANCHOR ASSEMBLY | EA | 1 | 2 | 8.00 | $462.50 | $3,700.00 |
| | | EA | 2 | 2 | 8.00 | $415.00 | $3,320.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **692305** | 12" ANCHOR ASSEMBLY | | EA | 3 | 2 | 10.00 | $565.00 | $5,650.00 |
| | | **Unit Sub Total** | **EA** | | **6** | **26.00** | **$487.31** | **$12,670.00** |
| | **Item Code 692305** | **Total No. of Proj.** | | | **6** | | **Total Amount** | **$12,670.00** |
| **692307** | 18" ANCHOR ASSEMBLY | | EA | 5 | 1 | 4.00 | $325.00 | $1,300.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **4.00** | **$325.00** | **$1,300.00** |
| | **Item Code 692307** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,300.00** |
| **692309** | 24" ANCHOR ASSEMBLY | | EA | 1 | 1 | 4.00 | $535.00 | $2,140.00 |
| | | | EA | 2 | 2 | 24.00 | $202.50 | $4,860.00 |
| | | | EA | 3 | 1 | 3.00 | $1,525.00 | $4,575.00 |
| | | **Unit Sub Total** | **EA** | | **4** | **31.00** | **$373.39** | **$11,575.00** |
| | **Item Code 692309** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$11,575.00** |
| **692313** | 36" ANCHOR ASSEMBLY | | EA | 2 | 1 | 5.00 | $185.00 | $925.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **5.00** | **$185.00** | **$925.00** |
| | **Item Code 692313** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$925.00** |
| **692361** | FLUME ANCHOR ASSEMBLY | | EA | 1 | 1 | 16.00 | $300.00 | $4,800.00 |
| | | | EA | 10 | 1 | 10.00 | $75.00 | $750.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **26.00** | **$213.46** | **$5,550.00** |
| | **Item Code 692361** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$5,550.00** |
| **692364** | 10" FLUME ANCHOR ASSEMBLY | | EA | 2 | 1 | 4.00 | $200.00 | $800.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **4.00** | **$200.00** | **$800.00** |
| | **Item Code 692364** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$800.00** |
| **692383** | 300 MM ANCHOR ASSEMBLY | | EA | 4 | 1 | 2.00 | $380.00 | $760.00 |
| | | | EA | 5 | 2 | 6.00 | $319.17 | $1,915.00 |
| | | **Unit Sub Total** | **EA** | | **3** | **8.00** | **$334.38** | **$2,675.00** |
| | **Item Code 692383** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$2,675.00** |
| **692385** | 450 MM ANCHOR ASSEMBLY | | EA | 3 | 2 | 11.00 | $407.73 | $4,485.00 |
| | | | EA | 4 | 2 | 9.00 | $288.89 | $2,600.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **692385** | 450 MM ANCHOR ASSEMBLY | EA | 5 | 2 | 14.00 | $460.71 | $6,450.00 |
| | **Unit Sub Total** | **EA** | | **6** | **34.00** | **$398.09** | **$13,535.00** |
| | **Item Code 692385 Total No. of Proj.** | | | **6** | | **Total Amount** | **$13,535.00** |
| **692386** | 600 MM ANCHOR ASSEMBLY | EA | 3 | 1 | 1.00 | $600.00 | $600.00 |
| | | EA | 5 | 1 | 18.00 | $300.00 | $5,400.00 |
| | **Unit Sub Total** | **EA** | | **2** | **19.00** | **$315.79** | **$6,000.00** |
| | **Item Code 692386 Total No. of Proj.** | | | **2** | | **Total Amount** | **$6,000.00** |
| **692409** | CABLE ANCHORAGE SYSTEM | LF | 1 | 1 | 6.00 | $950.00 | $5,700.00 |
| | | LF | 3 | 2 | 2,140.00 | $20.29 | $43,430.00 |
| | **Unit Sub Total** | **LF** | | **3** | **2,146.00** | **$22.89** | **$49,130.00** |
| **692409** | CABLE ANCHORAGE SYSTEM | M | 1 | 1 | 30.00 | $175.00 | $5,250.00 |
| | **Unit Sub Total** | **M** | | **1** | **30.00** | **$175.00** | **$5,250.00** |
| | **Item Code 692409 Total No. of Proj.** | | | **4** | | **Total Amount** | **$54,380.00** |
| **698091** | 300 MM ALTERNATIVE PIPE DOWNDRAIN | M | 5 | 2 | 26.00 | $315.38 | $8,200.00 |
| | | M | 8 | 1 | 30.00 | $400.00 | $12,000.00 |
| | | M | 10 | 1 | 280.00 | $135.85 | $38,038.00 |
| | **Unit Sub Total** | **M** | | **4** | **336.00** | **$173.33** | **$58,238.00** |
| | **Item Code 698091 Total No. of Proj.** | | | **4** | | **Total Amount** | **$58,238.00** |
| **698140** | 24" ALTERNATIVE PIPE DOWNDRAIN | LF | 1 | 3 | 77.00 | $103.69 | $7,984.00 |
| | **Unit Sub Total** | **LF** | | **3** | **77.00** | **$103.69** | **$7,984.00** |
| | **Item Code 698140 Total No. of Proj.** | | | **3** | | **Total Amount** | **$7,984.00** |
| **698162** | 450 MM ALTERNATIVE PIPE DOWNDRAIN | M | 3 | 1 | 24.00 | $450.00 | $10,800.00 |
| | | M | 5 | 1 | 59.00 | $200.00 | $11,800.00 |
| | | M | 11 | 1 | 6.00 | $500.00 | $3,000.00 |
| | **Unit Sub Total** | **M** | | **3** | **89.00** | **$287.64** | **$25,600.00** |
| | **Item Code 698162 Total No. of Proj.** | | | **3** | | **Total Amount** | **$25,600.00** |
| **698169** | 600 MM ALTERNATIVE PIPE DOWNDRAIN | M | 5 | 1 | 260.00 | $160.00 | $41,600.00 |
| | | M | 11 | 1 | 5.00 | $600.00 | $3,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M** | | **2** | **265.00** | **$168.30** | **$44,600.00** |
| | **Item Code 698169** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$44,600.00** |
| **698200** | 36" ALTERNATIVE PIPE DOWNDRAIN | | LF | 1 | 1 | 10.00 | $125.00 | $1,250.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **10.00** | **$125.00** | **$1,250.00** |
| | **Item Code 698200** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,250.00** |
| **698507** | 300 MM PIPE DOWNDRAIN | | M | 5 | 1 | 34.00 | $85.00 | $2,890.00 |
| | | **Unit Sub Total** | **M** | | **1** | **34.00** | **$85.00** | **$2,890.00** |
| | **Item Code 698507** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,890.00** |
| **700617** | DRAINAGE INLET MARKER | | EA | 3 | 2 | 102.00 | $29.52 | $3,011.00 |
| | | | EA | 4 | 4 | 58.00 | $115.95 | $6,725.00 |
| | | | EA | 5 | 4 | 122.00 | $132.19 | $16,127.00 |
| | | | EA | 8 | 2 | 5.00 | $186.40 | $932.00 |
| | | | EA | 11 | 5 | 22.00 | $413.91 | $9,106.02 |
| | | **Unit Sub Total** | **EA** | | **17** | **309.00** | **$116.18** | **$35,901.02** |
| | **Item Code 700617** | **Total No. of Proj.** | | | **17** | | **Total Amount** | **$35,901.02** |
| **700619** | INSTALL DRAINAGE INLET MARKER | | EA | 1 | 1 | 5.00 | $55.00 | $275.00 |
| | | | EA | 2 | 2 | 32.00 | $84.38 | $2,700.00 |
| | | **Unit Sub Total** | **EA** | | **3** | **37.00** | **$80.41** | **$2,975.00** |
| | **Item Code 700619** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$2,975.00** |
| **700638** | 36" CORRUGATED STEEL PIPE INLET (.079" THICK) | | LF | 1 | 1 | 16.00 | $550.00 | $8,800.00 |
| | | | LF | 8 | 1 | 33.00 | $670.00 | $22,110.00 |
| | | **Unit Sub Total** | **LF** | | **2** | **49.00** | **$630.82** | **$30,910.00** |
| | **Item Code 700638** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$30,910.00** |
| **700639** | 36" CORRUGATED STEEL PIPE INLET (.109" THICK) | | LF | 2 | 1 | 4.00 | $600.00 | $2,400.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **4.00** | **$600.00** | **$2,400.00** |
| | **Item Code 700639** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,400.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **700640** | 36" CORRUGATED STEEL PIPE INLET (.138" THICK) | LF | 3 | 1 | 38.00 | $250.00 | $9,500.00 |
| | | LF | 6 | 1 | 9.00 | $534.00 | $4,806.00 |
| | **Unit Sub Total** | **LF** | | **2** | **47.00** | **$304.38** | **$14,306.00** |
| | **Item Code 700640 Total No. of Proj.** | | | **2** | | **Total Amount** | **$14,306.00** |
| **700657** | 900 MM CORRUGATED STEEL PIPE INLET (1.63 MM THICK) | M | 4 | 1 | 1.20 | $1,000.00 | $1,200.00 |
| | **Unit Sub Total** | **M** | | **1** | **1.20** | **$1,000.00** | **$1,200.00** |
| | **Item Code 700657 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,200.00** |
| **700658** | 900 MM CORRUGATED STEEL PIPE INLET (2.01 MM THICK) | M | 4 | 1 | 1.60 | $1,200.00 | $1,920.00 |
| | **Unit Sub Total** | **M** | | **1** | **1.60** | **$1,200.00** | **$1,920.00** |
| | **Item Code 700658 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,920.00** |
| **700659** | 900 MM CORRUGATED STEEL PIPE INLET (2.77 MM THICK) | EA | 4 | 1 | 2.00 | $2,125.00 | $4,250.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$2,125.00** | **$4,250.00** |
| **700659** | 900 MM CORRUGATED STEEL PIPE INLET (2.77 MM THICK) | M | 1 | 2 | 4.90 | $1,346.94 | $6,600.00 |
| | | M | 3 | 1 | 220.00 | $800.00 | $176,000.00 |
| | | M | 4 | 1 | 1.20 | $1,157.64 | $1,389.17 |
| | | M | 5 | 1 | 1.60 | $1,489.00 | $2,382.40 |
| | | M | 7 | 1 | 2.00 | $1,100.00 | $2,200.00 |
| | **Unit Sub Total** | **M** | | **6** | **229.70** | **$820.95** | **$188,571.57** |
| | **Item Code 700659 Total No. of Proj.** | | | **7** | | **Total Amount** | **$192,821.57** |
| **700660** | 900 MM CORRUGATED STEEL PIPE INLET (3.51 MM THICK) | M | 5 | 1 | 20.00 | $1,300.00 | $26,000.00 |
| | | M | 9 | 2 | 8.20 | $1,653.66 | $13,560.00 |
| | **Unit Sub Total** | **M** | | **3** | **28.20** | **$1,402.84** | **$39,560.00** |
| | **Item Code 700660 Total No. of Proj.** | | | **3** | | **Total Amount** | **$39,560.00** |
| **700661** | 900 MM CORRUGATED STEEL PIPE INLET (4.27 MM THICK) | M | 2 | 1 | 5.00 | $1,740.00 | $8,700.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **M** | | **1** | **5.00** | **$1,740.00** | **$8,700.00** |
| | **Item Code 700661 Total No. of Proj.** | | | **1** | | **Total Amount** | **$8,700.00** |
| **700857** | 900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE INLET (2.01 MM THICK) | M | 11 | 1 | 2.00 | $900.00 | $1,800.00 |
| | **Unit Sub Total** | **M** | | **1** | **2.00** | **$900.00** | **$1,800.00** |
| | **Item Code 700857 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,800.00** |
| **702616** | 24" CORRUGATED STEEL PIPE ENERGY DISSIPATOR (.064" THICK) | LF | 7 | 1 | 20.00 | $148.50 | $2,970.00 |
| | **Unit Sub Total** | **LF** | | **1** | **20.00** | **$148.50** | **$2,970.00** |
| | **Item Code 702616 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,970.00** |
| **702671** | 450 MM CORRUGATED STEEL PIPE ENERGY DISSIPATOR (1.63 MM THICK) | EA | 3 | 1 | 1.00 | $1,300.00 | $1,300.00 |
| | | EA | 4 | 1 | 2.00 | $400.00 | $800.00 |
| | **Unit Sub Total** | **EA** | | **2** | **3.00** | **$700.00** | **$2,100.00** |
| | **Item Code 702671 Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,100.00** |
| **702672** | 600 MM CORRUGATED STEEL PIPE ENERGY DISSIPATOR (1.63 MM THICK) | EA | 3 | 1 | 2.00 | $1,000.00 | $2,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$1,000.00** | **$2,000.00** |
| | **Item Code 702672 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,000.00** |
| **703223** | 24" CORRUGATED STEEL PIPE RISER (.079" THICK) | LF | 8 | 1 | 10.00 | $310.00 | $3,100.00 |
| | **Unit Sub Total** | **LF** | | **1** | **10.00** | **$310.00** | **$3,100.00** |
| | **Item Code 703223 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,100.00** |
| **703233** | GRATED LINE DRAIN | LF | 5 | 1 | 340.00 | $112.00 | $38,080.00 |
| | | LF | 11 | 2 | 1,315.00 | $101.33 | $133,250.00 |
| | | LF | 12 | 2 | 119.00 | $129.08 | $15,360.00 |
| | **Unit Sub Total** | **LF** | | **5** | **1,774.00** | **$105.24** | **$186,690.00** |
| **703233** | GRATED LINE DRAIN | M | 1 | 3 | 63.00 | $565.71 | $35,640.00 |
| | | M | 3 | 1 | 490.00 | $275.00 | $134,750.00 |
| | | M | 4 | 1 | 13.00 | $700.00 | $9,100.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **703233** | GRATED LINE DRAIN | M | 6 | 1 | 70.00 | $389.00 | $27,230.00 |
| | | M | 7 | 3 | 565.00 | $225.11 | $127,188.50 |
| | | M | 8 | 2 | 2,409.00 | $317.69 | $765,325.00 |
| | | M | 11 | 7 | 866.00 | $344.71 | $298,520.00 |
| | **Unit Sub Total** | **M** | | **18** | **4,476.00** | **$312.28** | **$1,397,753.50** |
| | **Item Code 703233 Total No. of Proj.** | | | **23** | | **Total Amount** | **$1,584,443.50** |
| **703267** | 300 MM CORRUGATED STEEL PIPE RISER (1.63 MM THICK) | M | 8 | 1 | 33.00 | $1,250.00 | $41,250.00 |
| | **Unit Sub Total** | **M** | | **1** | **33.00** | **$1,250.00** | **$41,250.00** |
| | **Item Code 703267 Total No. of Proj.** | | | **1** | | **Total Amount** | **$41,250.00** |
| **703268** | 300 MM CORRUGATED STEEL PIPE RISER (2.01 MM THICK) | M | 7 | 1 | 10.00 | $435.00 | $4,350.00 |
| | **Unit Sub Total** | **M** | | **1** | **10.00** | **$435.00** | **$4,350.00** |
| | **Item Code 703268 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,350.00** |
| **703283** | 900 MM CORRUGATED STEEL PIPE RISER (2.01 MM THICK) | M | 7 | 1 | 16.00 | $635.00 | $10,160.00 |
| | **Unit Sub Total** | **M** | | **1** | **16.00** | **$635.00** | **$10,160.00** |
| | **Item Code 703283 Total No. of Proj.** | | | **1** | | **Total Amount** | **$10,160.00** |
| **703284** | 900 MM CORRUGATED STEEL PIPE RISER (2.77 MM THICK) | M | 11 | 1 | 3.00 | $3,500.00 | $10,500.00 |
| | **Unit Sub Total** | **M** | | **1** | **3.00** | **$3,500.00** | **$10,500.00** |
| | **Item Code 703284 Total No. of Proj.** | | | **1** | | **Total Amount** | **$10,500.00** |
| **703285** | 900 MM CORRUGATED STEEL PIPE RISER (3.51 MM THICK) | M | 10 | 1 | 10.00 | $275.00 | $2,750.00 |
| | **Unit Sub Total** | **M** | | **1** | **10.00** | **$275.00** | **$2,750.00** |
| | **Item Code 703285 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,750.00** |
| **703358** | 300 MM BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (2.01 MM THICK) | M | 8 | 1 | 1.20 | $635.00 | $762.00 |
| | **Unit Sub Total** | **M** | | **1** | **1.20** | **$635.00** | **$762.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 703358 Total No. of Proj.** | | | **1** | | **Total Amount** | **$762.00** |
| **703363** | 450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (3.51 MM THICK) | M | 11 | 1 | 4.00 | $510.00 | $2,040.00 |
| | **Unit Sub Total** | **M** | | **1** | **4.00** | **$510.00** | **$2,040.00** |
| | **Item Code 703363 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,040.00** |
| **703369** | 900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (2.01 MM THICK) | M | 11 | 2 | 9.80 | $910.20 | $8,920.00 |
| | **Unit Sub Total** | **M** | | **2** | **9.80** | **$910.20** | **$8,920.00** |
| | **Item Code 703369 Total No. of Proj.** | | | **2** | | **Total Amount** | **$8,920.00** |
| **703450** | WELDED STEEL PIPE CASING (BRIDGE) | LF | 12 | 1 | 76.00 | $690.00 | $52,440.00 |
| | **Unit Sub Total** | **LF** | | **1** | **76.00** | **$690.00** | **$52,440.00** |
| **703450** | WELDED STEEL PIPE CASING (BRIDGE) | M | 1 | 1 | 48.00 | $800.00 | $38,400.00 |
| | | M | 2 | 3 | 74.00 | $287.16 | $21,250.00 |
| | | M | 3 | 1 | 24.00 | $350.00 | $8,400.00 |
| | | M | 11 | 2 | 120.00 | $208.33 | $25,000.00 |
| | **Unit Sub Total** | **M** | | **7** | **266.00** | **$349.81** | **$93,050.00** |
| | **Item Code 703450 Total No. of Proj.** | | | **8** | | **Total Amount** | **$145,490.00** |
| **703481** | 600 MM WELDED STEEL PIPE CASING (BRIDGE) | M | 10 | 1 | 120.00 | $510.00 | $61,200.00 |
| | | M | 11 | 1 | 225.00 | $460.00 | $103,500.00 |
| | **Unit Sub Total** | **M** | | **2** | **345.00** | **$477.39** | **$164,700.00** |
| | **Item Code 703481 Total No. of Proj.** | | | **2** | | **Total Amount** | **$164,700.00** |
| **703509** | 6" WELDED STEEL PIPE (.134" THICK) | LF | 8 | 1 | 180.00 | $70.00 | $12,600.00 |
| | **Unit Sub Total** | **LF** | | **1** | **180.00** | **$70.00** | **$12,600.00** |
| | **Item Code 703509 Total No. of Proj.** | | | **1** | | **Total Amount** | **$12,600.00** |
| **703542** | 300 MM WELDED STEEL PIPE (2.67 MM THICK) | M | 4 | 1 | 28.00 | $1,100.00 | $30,800.00 |
| | **Unit Sub Total** | **M** | | **1** | **28.00** | **$1,100.00** | **$30,800.00** |
| | **Item Code 703542 Total No. of Proj.** | | | **1** | | **Total Amount** | **$30,800.00** |
| **703543** | 300 MM WELDED STEEL PIPE (3.40 MM THICK) | M | 4 | 1 | 62.00 | $324.00 | $20,088.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **703543** | 300 MM WELDED STEEL PIPE (3.40 MM THICK) | M | 10 | 1 | 9.00 | $600.00 | $5,400.00 |
| | **Unit Sub Total** | **M** | | **2** | **71.00** | **$358.99** | **$25,488.00** |
| | **Item Code 703543 Total No. of Proj.** | | | **2** | | **Total Amount** | **$25,488.00** |
| **703646** | 42" WELDED STEEL PIPE (.375" THICK) | LF | 1 | 1 | 130.00 | $1,000.00 | $130,000.00 |
| | **Unit Sub Total** | **LF** | | **1** | **130.00** | **$1,000.00** | **$130,000.00** |
| | **Item Code 703646 Total No. of Proj.** | | | **1** | | **Total Amount** | **$130,000.00** |
| **703698** | 1200 MM WELDED STEEL PIPE (9.53 MM THICK) | M | 2 | 1 | 27.00 | $480.00 | $12,960.00 |
| | **Unit Sub Total** | **M** | | **1** | **27.00** | **$480.00** | **$12,960.00** |
| | **Item Code 703698 Total No. of Proj.** | | | **1** | | **Total Amount** | **$12,960.00** |
| **704196** | JACKED 30" WELDED STEEL PIPE (.239" THICK) | LF | 2 | 1 | 95.00 | $850.00 | $80,750.00 |
| | **Unit Sub Total** | **LF** | | **1** | **95.00** | **$850.00** | **$80,750.00** |
| | **Item Code 704196 Total No. of Proj.** | | | **1** | | **Total Amount** | **$80,750.00** |
| **705007** | 12" STEEL FLARED END SECTION | EA | 3 | 1 | 1.00 | $900.00 | $900.00 |
| | | EA | 6 | 1 | 1.00 | $750.00 | $750.00 |
| | **Unit Sub Total** | **EA** | | **2** | **2.00** | **$825.00** | **$1,650.00** |
| | **Item Code 705007 Total No. of Proj.** | | | **2** | | **Total Amount** | **$1,650.00** |
| **705011** | 18" STEEL FLARED END SECTION | EA | 1 | 2 | 2.00 | $420.00 | $840.00 |
| | | EA | 2 | 1 | 1.00 | $330.00 | $330.00 |
| | | EA | 3 | 3 | 21.00 | $619.05 | $13,000.00 |
| | | EA | 6 | 2 | 2.00 | $775.00 | $1,550.00 |
| | | EA | 12 | 1 | 1.00 | $2,200.00 | $2,200.00 |
| | **Unit Sub Total** | **EA** | | **9** | **27.00** | **$663.70** | **$17,920.00** |
| | **Item Code 705011 Total No. of Proj.** | | | **9** | | **Total Amount** | **$17,920.00** |
| **705015** | 24" STEEL FLARED END SECTION | EA | 1 | 1 | 4.00 | $650.00 | $2,600.00 |
| | | EA | 2 | 1 | 3.00 | $200.00 | $600.00 |
| | | EA | 3 | 5 | 31.00 | $993.71 | $30,805.00 |
| | | EA | 6 | 1 | 1.00 | $4,100.00 | $4,100.00 |
| | | EA | 7 | 1 | 1.00 | $440.00 | $440.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **9** | **40.00** | **$963.63** | **$38,545.00** |
| | **Item Code 705015** | **Total No. of Proj.** | | | **9** | | **Total Amount** | **$38,545.00** |
| **705019** | 30" STEEL FLARED END SECTION | | EA | 1 | 1 | 2.00 | $820.00 | $1,640.00 |
| | | | EA | 2 | 1 | 1.00 | $400.00 | $400.00 |
| | | | EA | 3 | 1 | 21.00 | $900.00 | $18,900.00 |
| | | **Unit Sub Total** | **EA** | | **3** | **24.00** | **$872.50** | **$20,940.00** |
| | **Item Code 705019** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$20,940.00** |
| **705023** | 36" STEEL FLARED END SECTION | | EA | 1 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,000.00** | **$1,000.00** |
| | **Item Code 705023** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,000.00** |
| **705027** | 42" STEEL FLARED END SECTION | | EA | 3 | 1 | 4.00 | $900.00 | $3,600.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **4.00** | **$900.00** | **$3,600.00** |
| | **Item Code 705027** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,600.00** |
| **705035** | 54" STEEL FLARED END SECTION | | EA | 3 | 1 | 2.00 | $900.00 | $1,800.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$900.00** | **$1,800.00** |
| | **Item Code 705035** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,800.00** |
| **705042** | 300 MM STEEL FLARED END SECTION | | EA | 3 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | | | EA | 4 | 2 | 4.00 | $208.75 | $835.00 |
| | | | EA | 5 | 1 | 5.00 | $258.00 | $1,290.00 |
| | | **Unit Sub Total** | **EA** | | **4** | **10.00** | **$312.50** | **$3,125.00** |
| | **Item Code 705042** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$3,125.00** |
| **705044** | 450 MM STEEL FLARED END SECTION | | EA | 1 | 1 | 18.00 | $400.00 | $7,200.00 |
| | | | EA | 3 | 2 | 12.00 | $700.00 | $8,400.00 |
| | | | EA | 4 | 1 | 2.00 | $325.00 | $650.00 |
| | | | EA | 5 | 3 | 4.00 | $217.25 | $869.00 |
| | | | EA | 7 | 4 | 21.00 | $427.14 | $8,970.00 |
| | | | EA | 8 | 2 | 4.00 | $275.00 | $1,100.00 |
| | | | EA | 9 | 1 | 6.00 | $300.00 | $1,800.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **705044** | 450 MM STEEL FLARED END SECTION | EA | 10 | 2 | 3.00 | $1,003.67 | $3,011.00 |
| | **Unit Sub Total** | **EA** | | **16** | **70.00** | **$457.14** | **$32,000.00** |
| | **Item Code 705044 Total No. of Proj.** | | | **16** | | **Total Amount** | **$32,000.00** |
| **705045** | 600 MM STEEL FLARED END SECTION | EA | 1 | 1 | 4.00 | $700.00 | $2,800.00 |
| | | EA | 2 | 1 | 1.00 | $903.00 | $903.00 |
| | | EA | 3 | 2 | 53.00 | $952.83 | $50,500.00 |
| | | EA | 5 | 2 | 5.00 | $385.60 | $1,928.00 |
| | | EA | 7 | 3 | 11.00 | $531.45 | $5,846.00 |
| | | EA | 8 | 1 | 2.00 | $350.00 | $700.00 |
| | | EA | 9 | 1 | 12.00 | $760.00 | $9,120.00 |
| | | EA | 10 | 2 | 2.00 | $450.00 | $900.00 |
| | **Unit Sub Total** | **EA** | | **13** | **90.00** | **$807.74** | **$72,697.00** |
| | **Item Code 705045 Total No. of Proj.** | | | **13** | | **Total Amount** | **$72,697.00** |
| **705047** | 750 MM STEEL FLARED END SECTION | EA | 3 | 2 | 2.00 | $750.00 | $1,500.00 |
| | | EA | 5 | 2 | 2.00 | $450.00 | $900.00 |
| | | EA | 9 | 1 | 6.00 | $1,000.00 | $6,000.00 |
| | **Unit Sub Total** | **EA** | | **5** | **10.00** | **$840.00** | **$8,400.00** |
| | **Item Code 705047 Total No. of Proj.** | | | **5** | | **Total Amount** | **$8,400.00** |
| **705048** | 900 MM STEEL FLARED END SECTION | EA | 2 | 1 | 2.00 | $1,652.00 | $3,304.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$1,652.00** | **$3,304.00** |
| | **Item Code 705048 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,304.00** |
| **705055** | 450 MM BITUMINOUS COATED STEEL FLARED END SECTION | EA | 11 | 1 | 2.00 | $445.00 | $890.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$445.00** | **$890.00** |
| | **Item Code 705055 Total No. of Proj.** | | | **1** | | **Total Amount** | **$890.00** |
| **705056** | 600 MM BITUMINOUS COATED STEEL FLARED END SECTION | EA | 7 | 1 | 1.00 | $780.00 | $780.00 |
| | | EA | 11 | 1 | 2.00 | $590.00 | $1,180.00 |
| | **Unit Sub Total** | **EA** | | **2** | **3.00** | **$653.33** | **$1,960.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 705056 Total No. of Proj.** | | | **2** | | **Total Amount** | **$1,960.00** |
| **705204** | 18" CONCRETE FLARED END SECTION | EA | 3 | 2 | 5.00 | $1,280.00 | $6,400.00 |
| | **Unit Sub Total** | **EA** | | **2** | **5.00** | **$1,280.00** | **$6,400.00** |
| | **Item Code 705204 Total No. of Proj.** | | | **2** | | **Total Amount** | **$6,400.00** |
| **705206** | 24" CONCRETE FLARED END SECTION | EA | 5 | 1 | 1.00 | $698.50 | $698.50 |
| | | EA | 6 | 2 | 2.00 | $1,650.00 | $3,300.00 |
| | | EA | 12 | 1 | 2.00 | $1,500.00 | $3,000.00 |
| | **Unit Sub Total** | **EA** | | **4** | **5.00** | **$1,399.70** | **$6,998.50** |
| | **Item Code 705206 Total No. of Proj.** | | | **4** | | **Total Amount** | **$6,998.50** |
| **705220** | 300 MM CONCRETE FLARED END SECTION | EA | 2 | 1 | 1.00 | $750.00 | $750.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$750.00** | **$750.00** |
| | **Item Code 705220 Total No. of Proj.** | | | **1** | | **Total Amount** | **$750.00** |
| **705221** | 375 MM CONCRETE FLARED END SECTION | EA | 2 | 1 | 2.00 | $800.00 | $1,600.00 |
| | | EA | 10 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | **Unit Sub Total** | **EA** | | **2** | **3.00** | **$866.67** | **$2,600.00** |
| | **Item Code 705221 Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,600.00** |
| **705222** | 450 MM CONCRETE FLARED END SECTION | EA | 2 | 1 | 2.00 | $800.00 | $1,600.00 |
| | | EA | 3 | 1 | 13.00 | $650.00 | $8,450.00 |
| | | EA | 4 | 1 | 3.00 | $400.00 | $1,200.00 |
| | | EA | 10 | 2 | 26.00 | $1,135.38 | $29,520.00 |
| | | EA | 11 | 2 | 3.00 | $883.33 | $2,650.00 |
| | **Unit Sub Total** | **EA** | | **7** | **47.00** | **$923.83** | **$43,420.00** |
| | **Item Code 705222 Total No. of Proj.** | | | **7** | | **Total Amount** | **$43,420.00** |
| **705224** | 600 MM CONCRETE FLARED END SECTION | EA | 2 | 1 | 2.00 | $1,000.00 | $2,000.00 |
| | | EA | 3 | 2 | 46.00 | $716.30 | $32,950.00 |
| | | EA | 4 | 1 | 3.00 | $500.00 | $1,500.00 |
| | | EA | 7 | 1 | 1.00 | $1,200.00 | $1,200.00 |
| | | EA | 10 | 4 | 40.00 | $912.50 | $36,500.00 |
| | | EA | 11 | 2 | 10.00 | $1,000.00 | $10,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **EA** | | **11** | **102.00** | **$825.00** | **$84,150.00** |
| | **Item Code 705224 Total No. of Proj.** | | | **11** | | **Total Amount** | **$84,150.00** |
| **705226** | 750 MM CONCRETE FLARED END SECTION | EA | 2 | 1 | 1.00 | $1,250.00 | $1,250.00 |
| | | EA | 3 | 1 | 6.00 | $850.00 | $5,100.00 |
| | | EA | 4 | 1 | 2.00 | $800.00 | $1,600.00 |
| | | EA | 11 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | **Unit Sub Total** | **EA** | | **4** | **10.00** | **$995.00** | **$9,950.00** |
| | **Item Code 705226 Total No. of Proj.** | | | **4** | | **Total Amount** | **$9,950.00** |
| **705227** | 900 MM CONCRETE FLARED END SECTION | EA | 3 | 1 | 24.00 | $1,500.00 | $36,000.00 |
| | | EA | 7 | 4 | 74.00 | $1,664.19 | $123,150.00 |
| | **Unit Sub Total** | **EA** | | **5** | **98.00** | **$1,623.98** | **$159,150.00** |
| | **Item Code 705227 Total No. of Proj.** | | | **5** | | **Total Amount** | **$159,150.00** |
| **705228** | 1050 MM CONCRETE FLARED END SECTION | EA | 4 | 1 | 1.00 | $1,500.00 | $1,500.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,500.00** | **$1,500.00** |
| | **Item Code 705228 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,500.00** |
| **705229** | 1200 MM CONCRETE FLARED END SECTION | EA | 7 | 1 | 8.00 | $2,600.00 | $20,800.00 |
| | | EA | 12 | 1 | 1.00 | $6,600.00 | $6,600.00 |
| | **Unit Sub Total** | **EA** | | **2** | **9.00** | **$3,044.44** | **$27,400.00** |
| | **Item Code 705229 Total No. of Proj.** | | | **2** | | **Total Amount** | **$27,400.00** |
| **705300** | ALTERNATIVE FLARED END SECTION | EA | 1 | 1 | 2.00 | $650.00 | $1,300.00 |
| | | EA | 4 | 1 | 2.00 | $200.00 | $400.00 |
| | **Unit Sub Total** | **EA** | | **2** | **4.00** | **$425.00** | **$1,700.00** |
| | **Item Code 705300 Total No. of Proj.** | | | **2** | | **Total Amount** | **$1,700.00** |
| **705307** | 12" ALTERNATIVE FLARED END SECTION | EA | 2 | 1 | 4.00 | $150.00 | $600.00 |
| | **Unit Sub Total** | **EA** | | **1** | **4.00** | **$150.00** | **$600.00** |
| | **Item Code 705307 Total No. of Proj.** | | | **1** | | **Total Amount** | **$600.00** |
| **705311** | 18" ALTERNATIVE FLARED END SECTION | EA | 2 | 1 | 3.00 | $330.00 | $990.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **705311** | 18" ALTERNATIVE FLARED END SECTION | EA | 3 | 1 | 1.00 | $300.00 | $300.00 |
| | **Unit Sub Total** | **EA** | | **2** | **4.00** | **$322.50** | **$1,290.00** |
| | **Item Code 705311 Total No. of Proj.** | | | **2** | | **Total Amount** | **$1,290.00** |
| **705315** | 24" ALTERNATIVE FLARED END SECTION | EA | 1 | 1 | 1.00 | $300.00 | $300.00 |
| | | EA | 2 | 1 | 11.00 | $390.00 | $4,290.00 |
| | | EA | 8 | 1 | 6.00 | $580.00 | $3,480.00 |
| | **Unit Sub Total** | **EA** | | **3** | **18.00** | **$448.33** | **$8,070.00** |
| | **Item Code 705315 Total No. of Proj.** | | | **3** | | **Total Amount** | **$8,070.00** |
| **705334** | 300 MM ALTERNATIVE FLARED END SECTION | EA | 3 | 2 | 16.00 | $443.75 | $7,100.00 |
| | | EA | 4 | 2 | 2.00 | $160.00 | $320.00 |
| | | EA | 5 | 1 | 1.00 | $2,400.00 | $2,400.00 |
| | | EA | 6 | 1 | 2.00 | $560.00 | $1,120.00 |
| | | EA | 8 | 1 | 5.00 | $350.00 | $1,750.00 |
| | | EA | 10 | 1 | 18.00 | $236.75 | $4,261.50 |
| | **Unit Sub Total** | **EA** | | **8** | **44.00** | **$385.26** | **$16,951.50** |
| | **Item Code 705334 Total No. of Proj.** | | | **8** | | **Total Amount** | **$16,951.50** |
| **705336** | 450 MM ALTERNATIVE FLARED END SECTION | EA | 1 | 2 | 3.00 | $433.33 | $1,300.00 |
| | | EA | 3 | 4 | 67.00 | $586.12 | $39,270.00 |
| | | EA | 4 | 5 | 49.00 | $232.24 | $11,380.00 |
| | | EA | 5 | 1 | 9.00 | $2,000.00 | $18,000.00 |
| | | EA | 6 | 2 | 3.00 | $908.33 | $2,725.00 |
| | | EA | 8 | 1 | 1.00 | $315.00 | $315.00 |
| | | EA | 9 | 1 | 18.00 | $325.00 | $5,850.00 |
| | | EA | 10 | 1 | 5.00 | $358.55 | $1,792.75 |
| | | EA | 11 | 1 | 4.00 | $800.00 | $3,200.00 |
| | **Unit Sub Total** | **EA** | | **18** | **159.00** | **$527.25** | **$83,832.75** |
| | **Item Code 705336 Total No. of Proj.** | | | **18** | | **Total Amount** | **$83,832.75** |
| **705337** | 600 MM ALTERNATIVE FLARED END SECTION | EA | 1 | 2 | 3.00 | $466.67 | $1,400.00 |
| | | EA | 3 | 4 | 20.00 | $667.00 | $13,340.00 |
| | | EA | 4 | 6 | 41.00 | $269.85 | $11,064.00 |
| | | EA | 5 | 3 | 46.00 | $1,679.57 | $77,260.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **705337** | 600 MM ALTERNATIVE FLARED END SECTION | EA | 6 | 1 | 2.00 | $500.00 | $1,000.00 |
| | | EA | 8 | 1 | 1.00 | $420.00 | $420.00 |
| | | EA | 9 | 3 | 70.00 | $405.71 | $28,400.00 |
| | | EA | 10 | 1 | 4.00 | $449.55 | $1,798.20 |
| | | EA | 11 | 6 | 31.00 | $854.19 | $26,480.00 |
| | **Unit Sub Total** | **EA** | | **27** | **218.00** | **$739.28** | **$161,162.20** |
| | **Item Code 705337 Total No. of Proj.** | | | **27** | | **Total Amount** | **$161,162.20** |
| **705338** | 750 MM ALTERNATIVE FLARED END SECTION | EA | 3 | 1 | 2.00 | $660.00 | $1,320.00 |
| | | EA | 4 | 1 | 8.00 | $300.00 | $2,400.00 |
| | | EA | 9 | 1 | 18.00 | $500.00 | $9,000.00 |
| | **Unit Sub Total** | **EA** | | **3** | **28.00** | **$454.29** | **$12,720.00** |
| | **Item Code 705338 Total No. of Proj.** | | | **3** | | **Total Amount** | **$12,720.00** |
| **705339** | 900 MM ALTERNATIVE FLARED END SECTION | EA | 3 | 1 | 1.00 | $800.00 | $800.00 |
| | | EA | 4 | 2 | 3.00 | $666.67 | $2,000.00 |
| | | EA | 5 | 2 | 5.00 | $2,780.00 | $13,900.00 |
| | | EA | 11 | 1 | 1.00 | $1,200.00 | $1,200.00 |
| | **Unit Sub Total** | **EA** | | **6** | **10.00** | **$1,790.00** | **$17,900.00** |
| | **Item Code 705339 Total No. of Proj.** | | | **6** | | **Total Amount** | **$17,900.00** |
| **705340** | 1050 MM ALTERNATIVE FLARED END SECTION | EA | 11 | 1 | 2.00 | $1,700.00 | $3,400.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$1,700.00** | **$3,400.00** |
| | **Item Code 705340 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,400.00** |
| **705341** | 1200 MM ALTERNATIVE FLARED END SECTION | EA | 9 | 1 | 2.00 | $1,150.00 | $2,300.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$1,150.00** | **$2,300.00** |
| | **Item Code 705341 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,300.00** |
| **705476** | 700 MM X 500 MM STEEL FLARED END PIPE ARCH SECTION | EA | 9 | 1 | 48.00 | $350.00 | $16,800.00 |
| | **Unit Sub Total** | **EA** | | **1** | **48.00** | **$350.00** | **$16,800.00** |
| | **Item Code 705476 Total No. of Proj.** | | | **1** | | **Total Amount** | **$16,800.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **705477** | 875 MM X 600 MM STEEL FLARED END PIPE ARCH SECTION | EA | 9 | 1 | 12.00 | $450.00 | $5,400.00 |
| | **Unit Sub Total** | **EA** | | **1** | **12.00** | **$450.00** | **$5,400.00** |
| | **Item Code 705477 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,400.00** |
| **705478** | 1050 MM X 725 MM STEEL FLARED END PIPE ARCH SECTION | EA | 9 | 1 | 2.00 | $575.00 | $1,150.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$575.00** | **$1,150.00** |
| | **Item Code 705478 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,150.00** |
| **705479** | 1225 MM X 825 MM STEEL FLARED END PIPE ARCH SECTION | EA | 1 | 1 | 1.00 | $1,700.00 | $1,700.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,700.00** | **$1,700.00** |
| | **Item Code 705479 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,700.00** |
| **705651** | 600 MM SLIDE HEADGATE | EA | 9 | 1 | 2.00 | $2,500.00 | $5,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$2,500.00** | **$5,000.00** |
| | **Item Code 705651 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,000.00** |
| **705952** | 200 MM GATE VALVE | EA | 10 | 1 | 4.00 | $250.00 | $1,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **4.00** | **$250.00** | **$1,000.00** |
| | **Item Code 705952 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,000.00** |
| **705953** | 250 MM GATE VALVE | EA | 10 | 1 | 4.00 | $250.00 | $1,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **4.00** | **$250.00** | **$1,000.00** |
| | **Item Code 705953 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,000.00** |
| **705954** | 300 MM GATE VALVE | EA | 11 | 2 | 11.00 | $3,981.82 | $43,800.00 |
| | **Unit Sub Total** | **EA** | | **2** | **11.00** | **$3,981.82** | **$43,800.00** |
| | **Item Code 705954 Total No. of Proj.** | | | **2** | | **Total Amount** | **$43,800.00** |
| **706500** | DEBRIS RACK | EA | 4 | 1 | 1.00 | $10,000.00 | $10,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$10,000.00** | **$10,000.00** |
| | **Item Code 706500 Total No. of Proj.** | | | **1** | | **Total Amount** | **$10,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **706607** | 48" DEBRIS RACK CAGE (H=4') | EA | 2 | 1 | 3.00 | $4,500.00 | $13,500.00 |
| | **Unit Sub Total** | **EA** | | **1** | **3.00** | **$4,500.00** | **$13,500.00** |
| | **Item Code 706607 Total No. of Proj.** | | | **1** | | **Total Amount** | **$13,500.00** |
| **707050** | DRAINAGE INLET | EA | 8 | 1 | 1.00 | $4,000.00 | $4,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$4,000.00** | **$4,000.00** |
| | **Item Code 707050 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,000.00** |
| **707051** | DRAINAGE MANHOLE | EA | 8 | 1 | 3.00 | $8,600.00 | $25,800.00 |
| | **Unit Sub Total** | **EA** | | **1** | **3.00** | **$8,600.00** | **$25,800.00** |
| | **Item Code 707051 Total No. of Proj.** | | | **1** | | **Total Amount** | **$25,800.00** |
| **707117** | 36" PRECAST CONCRETE PIPE INLET | LF | 1 | 1 | 5.00 | $148.00 | $740.00 |
| | | LF | 3 | 2 | 112.70 | $326.35 | $36,780.00 |
| | | LF | 5 | 1 | 5.00 | $750.00 | $3,750.00 |
| | **Unit Sub Total** | **LF** | | **4** | **122.70** | **$336.35** | **$41,270.00** |
| | **Item Code 707117 Total No. of Proj.** | | | **4** | | **Total Amount** | **$41,270.00** |
| **707133** | 900 MM PRECAST CONCRETE PIPE INLET | M | 1 | 2 | 7.40 | $3,064.86 | $22,680.00 |
| | | M | 4 | 2 | 7.10 | $746.48 | $5,300.00 |
| | | M | 5 | 1 | 6.00 | $977.00 | $5,862.00 |
| | | M | 8 | 1 | 7.00 | $1,050.00 | $7,350.00 |
| | | M | 10 | 2 | 24.30 | $661.32 | $16,070.00 |
| | | M | 11 | 2 | 27.00 | $950.00 | $25,650.00 |
| | **Unit Sub Total** | **M** | | **10** | **78.80** | **$1,052.18** | **$82,912.00** |
| | **Item Code 707133 Total No. of Proj.** | | | **10** | | **Total Amount** | **$82,912.00** |
| **707135** | 1200 MM PRECAST CONCRETE PIPE INLET | M | 11 | 1 | 2.40 | $1,640.00 | $3,936.00 |
| | **Unit Sub Total** | **M** | | **1** | **2.40** | **$1,640.00** | **$3,936.00** |
| | **Item Code 707135 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,936.00** |
| **707217** | 36" PRECAST CONCRETE PIPE MANHOLE | LF | 7 | 1 | 3.00 | $200.00 | $600.00 |
| | | LF | 12 | 2 | 10.00 | $592.00 | $5,920.00 |
| | **Unit Sub Total** | **LF** | | **3** | **13.00** | **$501.54** | **$6,520.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 707217 Total No. of Proj.** | | | **3** | | **Total Amount** | **$6,520.00** |
| **707225** | 48" PRECAST CONCRETE PIPE MANHOLE | EA | 3 | 1 | 2.00 | $7,000.00 | $14,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$7,000.00** | **$14,000.00** |
| | **Item Code 707225 Total No. of Proj.** | | | **1** | | **Total Amount** | **$14,000.00** |
| **707241** | 72" PRECAST CONCRETE PIPE MANHOLE | LF | 7 | 1 | 83.00 | $200.00 | $16,600.00 |
| | **Unit Sub Total** | **LF** | | **1** | **83.00** | **$200.00** | **$16,600.00** |
| | **Item Code 707241 Total No. of Proj.** | | | **1** | | **Total Amount** | **$16,600.00** |
| **707244** | 900 MM PRECAST CONCRETE PIPE MANHOLE | M | 7 | 2 | 21.00 | $935.71 | $19,650.00 |
| | | M | 12 | 1 | 11.00 | $675.00 | $7,425.00 |
| | **Unit Sub Total** | **M** | | **3** | **32.00** | **$846.09** | **$27,075.00** |
| | **Item Code 707244 Total No. of Proj.** | | | **3** | | **Total Amount** | **$27,075.00** |
| **707247** | 1200 MM PRECAST CONCRETE PIPE MANHOLE | EA | 3 | 1 | 3.00 | $3,300.00 | $9,900.00 |
| | | EA | 5 | 1 | 3.00 | $8,000.00 | $24,000.00 |
| | **Unit Sub Total** | **EA** | | **2** | **6.00** | **$5,650.00** | **$33,900.00** |
| | **Item Code 707247 Total No. of Proj.** | | | **2** | | **Total Amount** | **$33,900.00** |
| **707249** | 1500 MM PRECAST CONCRETE PIPE MANHOLE | M | 2 | 1 | 6.00 | $1,041.00 | $6,246.00 |
| | **Unit Sub Total** | **M** | | **1** | **6.00** | **$1,041.00** | **$6,246.00** |
| | **Item Code 707249 Total No. of Proj.** | | | **1** | | **Total Amount** | **$6,246.00** |
| **707410** | 24" PRECAST CONCRETE PIPE RISER | LF | 3 | 2 | 330.00 | $227.27 | $75,000.00 |
| | **Unit Sub Total** | **LF** | | **2** | **330.00** | **$227.27** | **$75,000.00** |
| | **Item Code 707410 Total No. of Proj.** | | | **2** | | **Total Amount** | **$75,000.00** |
| **707470** | 600 MM PRECAST CONCRETE PIPE RISER | M | 11 | 1 | 11.00 | $800.00 | $8,800.00 |
| | **Unit Sub Total** | **M** | | **1** | **11.00** | **$800.00** | **$8,800.00** |
| | **Item Code 707470 Total No. of Proj.** | | | **1** | | **Total Amount** | **$8,800.00** |
| **707471** | 900 MM PRECAST CONCRETE PIPE RISER | M | 11 | 6 | 111.60 | $1,185.04 | $132,250.00 |
| | **Unit Sub Total** | **M** | | **6** | **111.60** | **$1,185.04** | **$132,250.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 707471 Total No. of Proj.** | | | **6** | | **Total Amount** | **$132,250.00** |
| **707479** | 900 MM REINFORCED CONCRETE PIPE RISER | M | 5 | 1 | 0.50 | $2,000.00 | $1,000.00 |
| | | M | 11 | 3 | 63.00 | $903.17 | $56,900.00 |
| | **Unit Sub Total** | **M** | | **4** | **63.50** | **$911.81** | **$57,900.00** |
| | **Item Code 707479 Total No. of Proj.** | | | **4** | | **Total Amount** | **$57,900.00** |
| **708021** | 36" ALTERNATIVE PIPE INLET | LF | 1 | 1 | 6.00 | $350.00 | $2,100.00 |
| | **Unit Sub Total** | **LF** | | **1** | **6.00** | **$350.00** | **$2,100.00** |
| | **Item Code 708021 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,100.00** |
| **708031** | 6" ALTERNATIVE PIPE RISER | LF | 3 | 1 | 10.00 | $450.00 | $4,500.00 |
| | **Unit Sub Total** | **LF** | | **1** | **10.00** | **$450.00** | **$4,500.00** |
| | **Item Code 708031 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,500.00** |
| **708062** | 300 MM ALTERNATIVE PIPE RISER | M | 11 | 1 | 5.00 | $1,400.00 | $7,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **5.00** | **$1,400.00** | **$7,000.00** |
| | **Item Code 708062 Total No. of Proj.** | | | **1** | | **Total Amount** | **$7,000.00** |
| **708064** | 450 MM ALTERNATIVE PIPE RISER | M | 11 | 2 | 40.00 | $1,027.50 | $41,100.00 |
| | **Unit Sub Total** | **M** | | **2** | **40.00** | **$1,027.50** | **$41,100.00** |
| | **Item Code 708064 Total No. of Proj.** | | | **2** | | **Total Amount** | **$41,100.00** |
| **708068** | 900 MM ALTERNATIVE PIPE RISER | M | 11 | 1 | 21.00 | $2,650.00 | $55,650.00 |
| | **Unit Sub Total** | **M** | | **1** | **21.00** | **$2,650.00** | **$55,650.00** |
| | **Item Code 708068 Total No. of Proj.** | | | **1** | | **Total Amount** | **$55,650.00** |
| **709528** | 750 MM STANDPIPE | EA | 10 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,000.00** | **$1,000.00** |
| | **Item Code 709528 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,000.00** |
| **717001** | 4" POLYVINYL CHLORIDE SEWER PIPE | LF | 2 | 1 | 170.00 | $50.00 | $8,500.00 |
| | **Unit Sub Total** | **LF** | | **1** | **170.00** | **$50.00** | **$8,500.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 717001 Total No. of Proj.** | | | **1** | | **Total Amount** | **$8,500.00** |
| **717074** | 150 MM SEWER PIPE (LATERAL) | EA | 11 | 1 | 1.00 | $13,800.00 | $13,800.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$13,800.00** | **$13,800.00** |
| | **Item Code 717074 Total No. of Proj.** | | | **1** | | **Total Amount** | **$13,800.00** |
| **717077** | 200 MM POLYVINYL CHLORIDE SEWER PIPE | M | 11 | 1 | 120.00 | $192.00 | $23,040.00 |
| | **Unit Sub Total** | **M** | | **1** | **120.00** | **$192.00** | **$23,040.00** |
| | **Item Code 717077 Total No. of Proj.** | | | **1** | | **Total Amount** | **$23,040.00** |
| **719190** | SEWER MANHOLE FRAME AND COVER | EA | 10 | 1 | 7.00 | $500.00 | $3,500.00 |
| | | EA | 11 | 1 | 7.00 | $1,500.00 | $10,500.00 |
| | **Unit Sub Total** | **EA** | | **2** | **14.00** | **$1,000.00** | **$14,000.00** |
| | **Item Code 719190 Total No. of Proj.** | | | **2** | | **Total Amount** | **$14,000.00** |
| **719200** | SEWER MANHOLE | EA | 2 | 1 | 3.00 | $3,855.00 | $11,565.00 |
| | | EA | 8 | 1 | 2.00 | $6,445.00 | $12,890.00 |
| | **Unit Sub Total** | **EA** | | **2** | **5.00** | **$4,891.00** | **$24,455.00** |
| | **Item Code 719200 Total No. of Proj.** | | | **2** | | **Total Amount** | **$24,455.00** |
| **719202** | SEWER MANHOLE B | EA | 11 | 1 | 7.00 | $8,000.00 | $56,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **7.00** | **$8,000.00** | **$56,000.00** |
| | **Item Code 719202 Total No. of Proj.** | | | **1** | | **Total Amount** | **$56,000.00** |
| **719246** | 900 MM SEWER MANHOLE | EA | 11 | 1 | 14.00 | $5,200.00 | $72,800.00 |
| | **Unit Sub Total** | **EA** | | **1** | **14.00** | **$5,200.00** | **$72,800.00** |
| | **Item Code 719246 Total No. of Proj.** | | | **1** | | **Total Amount** | **$72,800.00** |
| **719300** | MANHOLE | EA | 6 | 1 | 6.00 | $3,500.00 | $21,000.00 |
| | | EA | 8 | 1 | 3.00 | $2,100.00 | $6,300.00 |
| | | EA | 10 | 1 | 8.00 | $5,900.00 | $47,200.00 |
| | **Unit Sub Total** | **EA** | | **3** | **17.00** | **$4,382.35** | **$74,500.00** |
| **719300** | MANHOLE | LF | 4 | 1 | 4.50 | $600.00 | $2,700.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **LF** | | **1** | **4.50** | **$600.00** | **$2,700.00** |
| | **Item Code 719300 Total No. of Proj.** | | | **4** | | **Total Amount** | **$77,200.00** |
| **719305** | MANHOLE (TYPE A) | EA | 4 | 1 | 1.00 | $3,000.00 | $3,000.00 |
| | | EA | 6 | 1 | 1.00 | $2,600.00 | $2,600.00 |
| | | EA | 10 | 2 | 19.00 | $935.79 | $17,780.00 |
| | **Unit Sub Total** | **EA** | | **4** | **21.00** | **$1,113.33** | **$23,380.00** |
| | **Item Code 719305 Total No. of Proj.** | | | **4** | | **Total Amount** | **$23,380.00** |
| **719589** | MINOR CONCRETE (BACKFILL) | M3 | 2 | 2 | 22.00 | $200.73 | $4,416.00 |
| | | M3 | 4 | 1 | 23.00 | $250.00 | $5,750.00 |
| | | M3 | 5 | 2 | 400.00 | $430.50 | $172,200.00 |
| | | M3 | 7 | 2 | 52.00 | $274.06 | $14,251.00 |
| | | M3 | 11 | 2 | 39.00 | $205.13 | $8,000.00 |
| | **Unit Sub Total** | **M3** | | **9** | **536.00** | **$381.75** | **$204,617.00** |
| | **Item Code 719589 Total No. of Proj.** | | | **9** | | **Total Amount** | **$204,617.00** |
| **719598** | CLASS 4 CONCRETE (BACKFILL) | M3 | 3 | 2 | 640.00 | $185.63 | $118,800.00 |
| | | M3 | 11 | 1 | 280.00 | $245.00 | $68,600.00 |
| | **Unit Sub Total** | **M3** | | **3** | **920.00** | **$203.70** | **$187,400.00** |
| | **Item Code 719598 Total No. of Proj.** | | | **3** | | **Total Amount** | **$187,400.00** |
| **720102** | ROCK SLOPE PROTECTION (4 TON, METHOD A) | CY | 7 | 1 | 7,430.00 | $90.20 | $670,186.00 |
| | **Unit Sub Total** | **CY** | | **1** | **7,430.00** | **$90.20** | **$670,186.00** |
| | **Item Code 720102 Total No. of Proj.** | | | **1** | | **Total Amount** | **$670,186.00** |
| **720104** | ROCK SLOPE PROTECTION (1 TON, METHOD A) | CY | 1 | 1 | 1,430.00 | $66.00 | $94,380.00 |
| | | CY | 3 | 1 | 180.00 | $150.00 | $27,000.00 |
| | | CY | 7 | 1 | 10.00 | $165.00 | $1,650.00 |
| | **Unit Sub Total** | **CY** | | **3** | **1,620.00** | **$75.94** | **$123,030.00** |
| **720104** | ROCK SLOPE PROTECTION (1 TON, METHOD A) | TON | 5 | 1 | 49.00 | $210.00 | $10,290.00 |
| | **Unit Sub Total** | **TON** | | **1** | **49.00** | **$210.00** | **$10,290.00** |
| | **Item Code 720104 Total No. of Proj.** | | | **4** | | **Total Amount** | **$133,320.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **720106** | ROCK SLOPE PROTECTION (1/2 TON, METHOD A) | CY | 3 | 1 | 690.00 | $110.00 | $75,900.00 |
| | **Unit Sub Total** | **CY** | | **1** | **690.00** | **$110.00** | **$75,900.00** |
| **720106** | ROCK SLOPE PROTECTION (1/2 TON, METHOD A) | TON | 2 | 1 | 1,980.00 | $42.00 | $83,160.00 |
| | **Unit Sub Total** | **TON** | | **1** | **1,980.00** | **$42.00** | **$83,160.00** |
| | **Item Code 720106 Total No. of Proj.** | | | **2** | | **Total Amount** | **$159,060.00** |
| **720117** | ROCK SLOPE PROTECTION (4T, METHOD A) | M3 | 5 | 1 | 130.00 | $288.00 | $37,440.00 |
| | **Unit Sub Total** | **M3** | | **1** | **130.00** | **$288.00** | **$37,440.00** |
| | **Item Code 720117 Total No. of Proj.** | | | **1** | | **Total Amount** | **$37,440.00** |
| **720118** | ROCK SLOPE PROTECTION (2T, METHOD A) | M3 | 5 | 1 | 1,130.00 | $136.00 | $153,680.00 |
| | **Unit Sub Total** | **M3** | | **1** | **1,130.00** | **$136.00** | **$153,680.00** |
| **720118** | ROCK SLOPE PROTECTION (2T, METHOD A) | TONN | 2 | 2 | 870.00 | $95.23 | $82,850.00 |
| | **Unit Sub Total** | **TONN** | | **2** | **870.00** | **$95.23** | **$82,850.00** |
| | **Item Code 720118 Total No. of Proj.** | | | **3** | | **Total Amount** | **$236,530.00** |
| **720119** | ROCK SLOPE PROTECTION (1T, METHOD A) | TONN | 2 | 1 | 2,900.00 | $50.00 | $145,000.00 |
| | **Unit Sub Total** | **TONN** | | **1** | **2,900.00** | **$50.00** | **$145,000.00** |
| | **Item Code 720119 Total No. of Proj.** | | | **1** | | **Total Amount** | **$145,000.00** |
| **720120** | ROCK SLOPE PROTECTION (1/2T, METHOD A) | M3 | 1 | 1 | 132.00 | $175.00 | $23,100.00 |
| | | M3 | 5 | 1 | 690.00 | $126.50 | $87,285.00 |
| | **Unit Sub Total** | **M3** | | **2** | **822.00** | **$134.29** | **$110,385.00** |
| **720120** | ROCK SLOPE PROTECTION (1/2T, METHOD A) | TONN | 2 | 1 | 21.00 | $263.00 | $5,523.00 |
| | **Unit Sub Total** | **TONN** | | **1** | **21.00** | **$263.00** | **$5,523.00** |
| | **Item Code 720120 Total No. of Proj.** | | | **3** | | **Total Amount** | **$115,908.00** |
| **721006** | ROCK SLOPE PROTECTION (1/2 TON, METHOD B) | CY | 1 | 1 | 360.00 | $80.00 | $28,800.00 |
| | **Unit Sub Total** | **CY** | | **1** | **360.00** | **$80.00** | **$28,800.00** |
| | **Item Code 721006 Total No. of Proj.** | | | **1** | | **Total Amount** | **$28,800.00** |
| **721007** | ROCK SLOPE PROTECTION (1/4 TON, METHOD B) | CY | 1 | 3 | 1,037.00 | $82.76 | $85,825.00 |
| | | CY | 3 | 2 | 97.00 | $164.91 | $15,996.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **721007** | ROCK SLOPE PROTECTION (1/4 TON, METHOD B) | CY | 4 | 1 | 540.00 | $112.50 | $60,750.00 |
| | | CY | 7 | 1 | 1,960.00 | $70.00 | $137,200.00 |
| | | CY | 9 | 1 | 27.00 | $184.00 | $4,968.00 |
| | | CY | 11 | 1 | 69.00 | $52.00 | $3,588.00 |
| | **Unit Sub Total** | **CY** | | **9** | **3,730.00** | **$82.66** | **$308,327.00** |
| **721007** | ROCK SLOPE PROTECTION (1/4 TON, METHOD B) | M3 | 3 | 1 | 18,000.00 | $85.00 | $1,530,000.00 |
| | | M3 | 5 | 1 | 1,010.00 | $130.00 | $131,300.00 |
| | | M3 | 11 | 2 | 271.00 | $80.07 | $21,700.00 |
| | | M3 | 12 | 1 | 30.00 | $180.00 | $5,400.00 |
| | **Unit Sub Total** | **M3** | | **5** | **19,311.00** | **$87.43** | **$1,688,400.00** |
| | **Item Code 721007 Total No. of Proj.** | | | **14** | | **Total Amount** | **$1,996,727.00** |
| **721008** | ROCK SLOPE PROTECTION (LIGHT, METHOD B) | CY | 1 | 6 | 1,242.00 | $67.29 | $83,570.00 |
| | | CY | 2 | 1 | 21.00 | $221.00 | $4,641.00 |
| | | CY | 3 | 4 | 210.00 | $161.24 | $33,860.00 |
| | | CY | 4 | 1 | 45.00 | $141.26 | $6,356.70 |
| | | CY | 5 | 2 | 6.40 | $676.56 | $4,330.00 |
| | | CY | 6 | 1 | 8.00 | $375.00 | $3,000.00 |
| | | CY | 7 | 2 | 603.00 | $41.56 | $25,059.00 |
| | | CY | 8 | 1 | 6.00 | $200.00 | $1,200.00 |
| | | CY | 11 | 1 | 7.00 | $430.00 | $3,010.00 |
| | | CY | 12 | 1 | 5.00 | $260.00 | $1,300.00 |
| | **Unit Sub Total** | **CY** | | **20** | **2,153.40** | **$77.24** | **$166,326.70** |
| **721008** | ROCK SLOPE PROTECTION (LIGHT, METHOD B) | M3 | 1 | 3 | 211.20 | $104.19 | $22,005.00 |
| | | M3 | 2 | 1 | 7.00 | $200.00 | $1,400.00 |
| | | M3 | 3 | 4 | 6,467.00 | $94.43 | $610,650.00 |
| | | M3 | 4 | 5 | 358.70 | $138.73 | $49,763.64 |
| | | M3 | 5 | 3 | 807.00 | $199.07 | $160,650.00 |
| | | M3 | 7 | 1 | 2.40 | $50.00 | $120.00 |
| | | M3 | 8 | 1 | 120.00 | $125.00 | $15,000.00 |
| | | M3 | 10 | 3 | 64.00 | $195.88 | $12,536.00 |
| | | M3 | 11 | 3 | 103.10 | $197.28 | $20,340.00 |
| | **Unit Sub Total** | **M3** | | **24** | **8,140.40** | **$109.63** | **$892,464.64** |
| **721008** | ROCK SLOPE PROTECTION (LIGHT, METHOD B) | TON | 2 | 2 | 2,040.00 | $56.18 | $114,600.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **TON** | | **2** | **2,040.00** | **$56.18** | **$114,600.00** |
| **721008** | ROCK SLOPE PROTECTION (LIGHT, METHOD B) | TONN | 2 | 1 | 250.00 | $70.00 | $17,500.00 |
| | **Unit Sub Total** | **TONN** | | **1** | **250.00** | **$70.00** | **$17,500.00** |
| | **Item Code 721008 Total No. of Proj.** | | | **47** | | **Total Amount** | **$1,190,891.34** |
| **721009** | ROCK SLOPE PROTECTION (FACING, METHOD B) | CY | 1 | 2 | 148.00 | $88.51 | $13,100.00 |
| | | CY | 2 | 2 | 11.70 | $150.00 | $1,755.00 |
| | | CY | 3 | 3 | 963.00 | $111.93 | $107,790.00 |
| | | CY | 6 | 1 | 3.00 | $500.00 | $1,500.00 |
| | **Unit Sub Total** | **CY** | | **8** | **1,125.70** | **$110.28** | **$124,145.00** |
| **721009** | ROCK SLOPE PROTECTION (FACING, METHOD B) | M3 | 1 | 1 | 133.00 | $175.00 | $23,275.00 |
| | | M3 | 2 | 1 | 50.00 | $132.00 | $6,600.00 |
| | | M3 | 3 | 3 | 1,373.00 | $126.04 | $173,050.00 |
| | | M3 | 4 | 4 | 34.00 | $240.00 | $8,160.00 |
| | | M3 | 7 | 7 | 299.00 | $297.66 | $88,999.50 |
| | | M3 | 8 | 2 | 18.00 | $356.67 | $6,420.00 |
| | | M3 | 9 | 3 | 1,829.00 | $67.93 | $124,250.00 |
| | | M3 | 10 | 1 | 71.00 | $150.00 | $10,650.00 |
| | | M3 | 11 | 5 | 210.00 | $265.85 | $55,828.20 |
| | **Unit Sub Total** | **M3** | | **27** | **4,017.00** | **$123.78** | **$497,232.70** |
| **721009** | ROCK SLOPE PROTECTION (FACING, METHOD B) | TON | 2 | 1 | 80.00 | $90.00 | $7,200.00 |
| | **Unit Sub Total** | **TON** | | **1** | **80.00** | **$90.00** | **$7,200.00** |
| | **Item Code 721009 Total No. of Proj.** | | | **36** | | **Total Amount** | **$628,577.70** |
| **721010** | ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B) | CY | 1 | 2 | 223.00 | $96.82 | $21,590.00 |
| | | CY | 2 | 1 | 104.00 | $87.00 | $9,048.00 |
| | | CY | 3 | 2 | 50.00 | $223.00 | $11,150.00 |
| | | CY | 5 | 1 | 2.70 | $400.00 | $1,080.00 |
| | | CY | 7 | 1 | 1,070.00 | $71.00 | $75,970.00 |
| | **Unit Sub Total** | **CY** | | **7** | **1,449.70** | **$81.97** | **$118,838.00** |
| **721010** | ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B) | M3 | 1 | 1 | 75.00 | $190.00 | $14,250.00 |
| | | M3 | 3 | 2 | 228.00 | $95.75 | $21,831.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **721010** | ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B) | M3 | 4 | 2 | 691.00 | $113.24 | $78,250.00 |
| | | M3 | 5 | 4 | 440.00 | $166.85 | $73,412.00 |
| | | M3 | 7 | 1 | 290.00 | $170.00 | $49,300.00 |
| | | M3 | 8 | 1 | 55.00 | $175.00 | $9,625.00 |
| | | M3 | 10 | 1 | 10.00 | $300.00 | $3,000.00 |
| | | M3 | 11 | 2 | 59.00 | $242.88 | $14,330.00 |
| | **Unit Sub Total** | **M3** | | **14** | **1,848.00** | **$142.86** | **$263,998.00** |
| **721010** | ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B) | TONN | 2 | 2 | 5,300.00 | $45.67 | $242,040.00 |
| | **Unit Sub Total** | **TONN** | | **2** | **5,300.00** | **$45.67** | **$242,040.00** |
| | **Item Code 721010 Total No. of Proj.** | | | **23** | | **Total Amount** | **$624,876.00** |
| **721011** | ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B) | CY | 1 | 1 | 72.00 | $120.00 | $8,640.00 |
| | | CY | 2 | 1 | 74.00 | $139.00 | $10,286.00 |
| | | CY | 3 | 6 | 600.00 | $114.63 | $68,777.00 |
| | | CY | 9 | 1 | 56.00 | $135.00 | $7,560.00 |
| | | CY | 11 | 1 | 26.00 | $28.00 | $728.00 |
| | **Unit Sub Total** | **CY** | | **10** | **828.00** | **$115.93** | **$95,991.00** |
| **721011** | ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B) | M3 | 1 | 2 | 250.00 | $120.20 | $30,050.00 |
| | | M3 | 3 | 2 | 3,640.00 | $108.27 | $394,100.00 |
| | | M3 | 4 | 2 | 27.00 | $331.48 | $8,950.00 |
| | | M3 | 5 | 7 | 1,680.80 | $171.81 | $288,776.40 |
| | | M3 | 6 | 2 | 5.30 | $1,004.72 | $5,325.00 |
| | | M3 | 7 | 1 | 4.00 | $300.00 | $1,200.00 |
| | | M3 | 8 | 1 | 22.00 | $200.00 | $4,400.00 |
| | | M3 | 10 | 5 | 184.70 | $142.88 | $26,390.00 |
| | | M3 | 11 | 4 | 810.40 | $135.02 | $109,420.00 |
| | | M3 | 12 | 1 | 11.00 | $180.00 | $1,980.00 |
| | **Unit Sub Total** | **M3** | | **27** | **6,635.20** | **$131.21** | **$870,591.40** |
| **721011** | ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B) | TON | 2 | 1 | 370.00 | $40.00 | $14,800.00 |
| | **Unit Sub Total** | **TON** | | **1** | **370.00** | **$40.00** | **$14,800.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| 721011 | ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B) | TONN | 2 | 3 | 2,820.00 | $50.54 | $142,520.00 |
| | **Unit Sub Total** | **TONN** | | **3** | **2,820.00** | **$50.54** | **$142,520.00** |
| | **Item Code 721011 Total No. of Proj.** | | | **41** | | **Total Amount** | **$1,123,902.40** |
| 721012 | ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B) | CY | 3 | 2 | 202.00 | $106.73 | $21,560.00 |
| | | CY | 4 | 1 | 75.00 | $112.50 | $8,437.50 |
| | | CY | 7 | 1 | 0.10 | $1,000.00 | $100.00 |
| | | CY | 12 | 1 | 2.20 | $520.00 | $1,144.00 |
| | **Unit Sub Total** | **CY** | | **5** | **279.30** | **$111.86** | **$31,241.50** |
| 721012 | ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B) | M3 | 1 | 1 | 72.00 | $165.00 | $11,880.00 |
| | | M3 | 2 | 1 | 260.00 | $83.00 | $21,580.00 |
| | | M3 | 3 | 2 | 915.00 | $165.03 | $151,000.00 |
| | | M3 | 5 | 1 | 4.00 | $355.00 | $1,420.00 |
| | | M3 | 8 | 1 | 10.00 | $330.00 | $3,300.00 |
| | **Unit Sub Total** | **M3** | | **6** | **1,261.00** | **$150.02** | **$189,180.00** |
| 721012 | ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B) | TONN | 2 | 1 | 77.00 | $99.00 | $7,623.00 |
| | **Unit Sub Total** | **TONN** | | **1** | **77.00** | **$99.00** | **$7,623.00** |
| | **Item Code 721012 Total No. of Proj.** | | | **12** | | **Total Amount** | **$228,044.50** |
| 721022 | ROCK SLOPE PROTECTION (1T, METHOD B) | CY | 8 | 1 | 320.00 | $90.00 | $28,800.00 |
| | **Unit Sub Total** | **CY** | | **1** | **320.00** | **$90.00** | **$28,800.00** |
| 721022 | ROCK SLOPE PROTECTION (1T, METHOD B) | M3 | 2 | 1 | 130.00 | $180.00 | $23,400.00 |
| | | M3 | 7 | 1 | 31.00 | $200.00 | $6,200.00 |
| | | M3 | 11 | 1 | 1,750.00 | $159.00 | $278,250.00 |
| | **Unit Sub Total** | **M3** | | **3** | **1,911.00** | **$161.09** | **$307,850.00** |
| | **Item Code 721022 Total No. of Proj.** | | | **4** | | **Total Amount** | **$336,650.00** |
| 721023 | ROCK SLOPE PROTECTION (1/2T, METHOD B) | M3 | 2 | 1 | 70.00 | $180.00 | $12,600.00 |
| | | M3 | 3 | 2 | 1,950.00 | $116.90 | $227,952.00 |
| | | M3 | 4 | 1 | 1,430.00 | $100.00 | $143,000.00 |
| | | M3 | 5 | 1 | 200.00 | $133.00 | $26,600.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| 721023 | ROCK SLOPE PROTECTION (1/2T, METHOD B) | M3 | 7 | 1 | 690.00 | $170.00 | $117,300.00 |
| | **Unit Sub Total** | **M3** | | **6** | **4,340.00** | **$121.53** | **$527,452.00** |
| 721023 | ROCK SLOPE PROTECTION (1/2T, METHOD B) | TONN | 2 | 1 | 510.00 | $47.00 | $23,970.00 |
| | **Unit Sub Total** | **TONN** | | **1** | **510.00** | **$47.00** | **$23,970.00** |
| | **Item Code 721023 Total No. of Proj.** | | | **7** | | **Total Amount** | **$551,422.00** |
| 721024 | ROCK SLOPE PROTECTION (1/4T, METHOD B) | CY | 2 | 1 | 20.00 | $75.00 | $1,500.00 |
| | | CY | 3 | 1 | 550.00 | $58.00 | $31,900.00 |
| | | CY | 9 | 1 | 170.00 | $164.00 | $27,880.00 |
| | **Unit Sub Total** | **CY** | | **3** | **740.00** | **$82.81** | **$61,280.00** |
| 721024 | ROCK SLOPE PROTECTION (1/4T, METHOD B) | M3 | 1 | 4 | 706.00 | $90.22 | $63,693.00 |
| | | M3 | 2 | 1 | 40.00 | $180.00 | $7,200.00 |
| | | M3 | 3 | 4 | 1,143.00 | $117.53 | $134,335.00 |
| | | M3 | 4 | 4 | 622.00 | $190.43 | $118,450.00 |
| | | M3 | 5 | 3 | 1,189.00 | $152.24 | $181,018.00 |
| | | M3 | 8 | 2 | 78.00 | $194.55 | $15,175.00 |
| | | M3 | 11 | 2 | 1,765.00 | $95.22 | $168,055.00 |
| | **Unit Sub Total** | **M3** | | **20** | **5,543.00** | **$124.11** | **$687,926.00** |
| 721024 | ROCK SLOPE PROTECTION (1/4T, METHOD B) | TONN | 2 | 3 | 15,609.00 | $44.71 | $697,890.00 |
| | **Unit Sub Total** | **TONN** | | **3** | **15,609.00** | **$44.71** | **$697,890.00** |
| | **Item Code 721024 Total No. of Proj.** | | | **26** | | **Total Amount** | **$1,447,096.00** |
| 721400 | CONCRETE (SLOPE PROTECTION) | M3 | 5 | 1 | 44.00 | $650.00 | $28,600.00 |
| | **Unit Sub Total** | **M3** | | **1** | **44.00** | **$650.00** | **$28,600.00** |
| | **Item Code 721400 Total No. of Proj.** | | | **1** | | **Total Amount** | **$28,600.00** |
| 721410 | CONCRETE (GUTTER LINING) | M3 | 4 | 1 | 52.00 | $490.00 | $25,480.00 |
| | **Unit Sub Total** | **M3** | | **1** | **52.00** | **$490.00** | **$25,480.00** |
| | **Item Code 721410 Total No. of Proj.** | | | **1** | | **Total Amount** | **$25,480.00** |
| 721420 | CONCRETE (DITCH LINING) | CY | 4 | 1 | 15.00 | $642.43 | $9,636.45 |
| | **Unit Sub Total** | **CY** | | **1** | **15.00** | **$642.43** | **$9,636.45** |
| 721420 | CONCRETE (DITCH LINING) | M3 | 3 | 1 | 360.00 | $632.00 | $227,520.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **721420** | CONCRETE (DITCH LINING) | M3 | 4 | 2 | 21.00 | $1,168.10 | $24,530.05 |
| | | M3 | 5 | 1 | 280.00 | $600.00 | $168,000.00 |
| | | M3 | 11 | 1 | 92.00 | $450.00 | $41,400.00 |
| | **Unit Sub Total** | **M3** | | **5** | **753.00** | **$612.82** | **$461,450.05** |
| | **Item Code 721420 Total No. of Proj.** | | | **6** | | **Total Amount** | **$471,086.50** |
| **721430** | CONCRETE (CHANNEL LINING) | CY | 11 | 1 | 440.00 | $365.00 | $160,600.00 |
| | **Unit Sub Total** | **CY** | | **1** | **440.00** | **$365.00** | **$160,600.00** |
| **721430** | CONCRETE (CHANNEL LINING) | M3 | 4 | 3 | 93.00 | $888.56 | $82,636.00 |
| | | M3 | 9 | 1 | 515.10 | $650.00 | $334,815.00 |
| | | M3 | 12 | 1 | 132.50 | $300.00 | $39,750.00 |
| | **Unit Sub Total** | **M3** | | **5** | **740.60** | **$617.34** | **$457,201.00** |
| | **Item Code 721430 Total No. of Proj.** | | | **6** | | **Total Amount** | **$617,801.00** |
| **721431** | CONCRETE (CONCRETE APRON) | CY | 6 | 1 | 6.00 | $1,800.00 | $10,800.00 |
| | | CY | 11 | 1 | 17.00 | $800.00 | $13,600.00 |
| | **Unit Sub Total** | **CY** | | **2** | **23.00** | **$1,060.87** | **$24,400.00** |
| **721431** | CONCRETE (CONCRETE APRON) | M3 | 5 | 3 | 35.00 | $1,174.29 | $41,100.00 |
| | | M3 | 12 | 1 | 1.20 | $380.00 | $456.00 |
| | **Unit Sub Total** | **M3** | | **4** | **36.20** | **$1,147.96** | **$41,556.00** |
| | **Item Code 721431 Total No. of Proj.** | | | **6** | | **Total Amount** | **$65,956.00** |
| **721501** | CONCRETE (CONCRETED-ROCK SLOPE PROTECTION) | CY | 3 | 2 | 1,484.00 | $220.95 | $327,896.00 |
| | | CY | 11 | 1 | 280.00 | $210.00 | $58,800.00 |
| | **Unit Sub Total** | **CY** | | **3** | **1,764.00** | **$219.22** | **$386,696.00** |
| **721501** | CONCRETE (CONCRETED-ROCK SLOPE PROTECTION) | M3 | 3 | 1 | 47.00 | $184.41 | $8,667.27 |
| | | M3 | 7 | 1 | 13.00 | $250.00 | $3,250.00 |
| | **Unit Sub Total** | **M3** | | **2** | **60.00** | **$198.62** | **$11,917.27** |
| | **Item Code 721501 Total No. of Proj.** | | | **5** | | **Total Amount** | **$398,613.27** |
| **721506** | CONCRETED-ROCK SLOPE PROTECTION (1/2 TON, METHOD A) | CY | 3 | 1 | 96.00 | $246.00 | $23,616.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **CY** | | **1** | **96.00** | **$246.00** | **$23,616.00** |
| | **Item Code 721506 Total No. of Proj.** | | | **1** | | **Total Amount** | **$23,616.00** |
| **721507** | CONCRETED-ROCK SLOPE PROTECTION (1/4 TON, METHOD A) | CY | 3 | 1 | 3,690.00 | $75.00 | $276,750.00 |
| | **Unit Sub Total** | **CY** | | **1** | **3,690.00** | **$75.00** | **$276,750.00** |
| | **Item Code 721507 Total No. of Proj.** | | | **1** | | **Total Amount** | **$276,750.00** |
| **721519** | CONCRETED-ROCK SLOPE PROTECTION (1/2T, METHOD A) | M3 | 3 | 1 | 130.00 | $89.92 | $11,689.60 |
| | **Unit Sub Total** | **M3** | | **1** | **130.00** | **$89.92** | **$11,689.60** |
| | **Item Code 721519 Total No. of Proj.** | | | **1** | | **Total Amount** | **$11,689.60** |
| **721520** | CONCRETED-ROCK SLOPE PROTECTION (1/4T, METHOD A) | M3 | 1 | 1 | 21.00 | $400.00 | $8,400.00 |
| | **Unit Sub Total** | **M3** | | **1** | **21.00** | **$400.00** | **$8,400.00** |
| | **Item Code 721520 Total No. of Proj.** | | | **1** | | **Total Amount** | **$8,400.00** |
| **721607** | CONCRETED-ROCK SLOPE PROTECTION (1/4 TON, METHOD B) | CY | 9 | 1 | 14.00 | $313.00 | $4,382.00 |
| | **Unit Sub Total** | **CY** | | **1** | **14.00** | **$313.00** | **$4,382.00** |
| **721607** | CONCRETED-ROCK SLOPE PROTECTION (1/4 TON, METHOD B) | TON | 11 | 1 | 830.00 | $70.00 | $58,100.00 |
| | **Unit Sub Total** | **TON** | | **1** | **830.00** | **$70.00** | **$58,100.00** |
| | **Item Code 721607 Total No. of Proj.** | | | **2** | | **Total Amount** | **$62,482.00** |
| **721608** | CONCRETED-ROCK SLOPE PROTECTION (LIGHT, METHOD B) | M3 | 7 | 1 | 13.00 | $250.00 | $3,250.00 |
| | **Unit Sub Total** | **M3** | | **1** | **13.00** | **$250.00** | **$3,250.00** |
| | **Item Code 721608 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,250.00** |
| **721616** | CONCRETED-ROCK SLOPE PROTECTION (COBBLE, METHOD B) | M3 | 2 | 1 | 8.00 | $947.28 | $7,578.24 |
| | | M3 | 4 | 1 | 21.00 | $400.00 | $8,400.00 |
| | **Unit Sub Total** | **M3** | | **2** | **29.00** | **$550.97** | **$15,978.24** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | **Item Code 721616** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$15,978.24** |
| **721810** | SLOPE PAVING (CONCRETE) | | CY | 7 | 2 | 840.00 | $369.05 | $310,000.00 |
| | | | CY | 11 | 1 | 2.80 | $750.00 | $2,100.00 |
| | | | CY | 12 | 3 | 430.00 | $383.95 | $165,100.00 |
| | | **Unit Sub Total** | **CY** | | **6** | **1,272.80** | **$374.92** | **$477,200.00** |
| **721810** | SLOPE PAVING (CONCRETE) | | M3 | 1 | 1 | 3.90 | $1,500.00 | $5,850.00 |
| | | | M3 | 2 | 1 | 37.00 | $900.00 | $33,300.00 |
| | | | M3 | 3 | 1 | 223.00 | $1,000.00 | $223,000.00 |
| | | | M3 | 4 | 1 | 19.00 | $1,601.40 | $30,426.60 |
| | | | M3 | 7 | 3 | 113.00 | $578.58 | $65,380.00 |
| | | | M3 | 8 | 1 | 8.00 | $1,575.00 | $12,600.00 |
| | | | M3 | 10 | 1 | 35.00 | $663.00 | $23,205.00 |
| | | | M3 | 11 | 4 | 653.00 | $715.20 | $467,025.00 |
| | | **Unit Sub Total** | **M3** | | **13** | **1,091.90** | **$788.34** | **$860,786.60** |
| | **Item Code 721810** | **Total No. of Proj.** | | | **19** | | **Total Amount** | **$1,337,986.60** |
| **721811** | SLOPE PAVING (MASONRY BLOCK) | | M2 | 11 | 1 | 3,580.00 | $150.00 | $537,000.00 |
| | | **Unit Sub Total** | **M2** | | **1** | **3,580.00** | **$150.00** | **$537,000.00** |
| | **Item Code 721811** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$537,000.00** |
| **722020** | GABION | | CY | 3 | 1 | 1,190.00 | $210.00 | $249,900.00 |
| | | | CY | 6 | 1 | 200.00 | $650.00 | $130,000.00 |
| | | **Unit Sub Total** | **CY** | | **2** | **1,390.00** | **$273.31** | **$379,900.00** |
| **722020** | GABION | | M3 | 5 | 1 | 62.00 | $676.75 | $41,958.50 |
| | | | M3 | 8 | 1 | 100.00 | $786.00 | $78,600.00 |
| | | **Unit Sub Total** | **M3** | | **2** | **162.00** | **$744.19** | **$120,558.50** |
| | **Item Code 722020** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$500,458.50** |
| **725001** | SACKED CONCRETE SLOPE PROTECTION | | SQFT | 2 | 1 | 390.00 | $20.00 | $7,800.00 |
| | | **Unit Sub Total** | **SQFT** | | **1** | **390.00** | **$20.00** | **$7,800.00** |
| | **Item Code 725001** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$7,800.00** |
| **727901** | MINOR CONCRETE (DITCH LINING) | | CY | 7 | 1 | 2.50 | $1,800.00 | $4,500.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **727901** | MINOR CONCRETE (DITCH LINING) | CY | 8 | 1 | 140.00 | $750.00 | $105,000.00 |
| | | CY | 11 | 2 | 38.10 | $469.29 | $17,880.00 |
| | **Unit Sub Total** | **CY** | | **4** | **180.60** | **$705.32** | **$127,380.00** |
| **727901** | MINOR CONCRETE (DITCH LINING) | M3 | 7 | 1 | 81.00 | $500.00 | $40,500.00 |
| | | M3 | 11 | 5 | 305.50 | $502.47 | $153,506.00 |
| | **Unit Sub Total** | **M3** | | **6** | **386.50** | **$501.96** | **$194,006.00** |
| | **Item Code 727901 Total No. of Proj.** | | | **10** | | **Total Amount** | **$321,386.00** |
| **727902** | MINOR CONCRETE (SLOPE PROTECTION) | M3 | 11 | 2 | 370.00 | $751.35 | $278,000.00 |
| | **Unit Sub Total** | **M3** | | **2** | **370.00** | **$751.35** | **$278,000.00** |
| | **Item Code 727902 Total No. of Proj.** | | | **2** | | **Total Amount** | **$278,000.00** |
| **727905** | MINOR CONCRETE (CHANNEL LINING) | CY | 3 | 1 | 5.20 | $700.00 | $3,640.00 |
| | **Unit Sub Total** | **CY** | | **1** | **5.20** | **$700.00** | **$3,640.00** |
| **727905** | MINOR CONCRETE (CHANNEL LINING) | M3 | 3 | 1 | 52.00 | $300.01 | $15,600.52 |
| | | M3 | 5 | 1 | 13.00 | $1,051.00 | $13,663.00 |
| | | M3 | 8 | 1 | 71.00 | $1,000.00 | $71,000.00 |
| | **Unit Sub Total** | **M3** | | **3** | **136.00** | **$737.23** | **$100,263.52** |
| | **Item Code 727905 Total No. of Proj.** | | | **4** | | **Total Amount** | **$103,903.52** |
| **727906** | MINOR CONCRETE (GUTTER LINING) | CY | 3 | 1 | 1,100.00 | $300.00 | $330,000.00 |
| | **Unit Sub Total** | **CY** | | **1** | **1,100.00** | **$300.00** | **$330,000.00** |
| | **Item Code 727906 Total No. of Proj.** | | | **1** | | **Total Amount** | **$330,000.00** |
| **729010** | ROCK SLOPE PROTECTION FABRIC | M2 | 1 | 5 | 2,692.00 | $5.88 | $15,822.00 |
| | | M2 | 2 | 6 | 15,164.00 | $3.34 | $50,572.16 |
| | | M2 | 3 | 8 | 38,480.00 | $1.41 | $54,319.90 |
| | | M2 | 4 | 12 | 4,698.00 | $1.84 | $8,658.02 |
| | | M2 | 5 | 13 | 7,988.00 | $3.72 | $29,678.40 |
| | | M2 | 6 | 2 | 16.00 | $11.25 | $180.00 |
| | | M2 | 7 | 9 | 1,859.00 | $6.83 | $12,689.00 |
| | | M2 | 8 | 4 | 2,315.00 | $3.89 | $9,013.00 |
| | | M2 | 9 | 2 | 4,790.00 | $3.57 | $17,105.00 |
| | | M2 | 10 | 8 | 1,127.00 | $11.34 | $12,783.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **729010** | ROCK SLOPE PROTECTION FABRIC | | M2 | 11 | 11 | 13,761.00 | $10.32 | $142,052.97 |
| | | | M2 | 12 | 1 | 30.00 | $31.00 | $930.00 |
| | | **Unit Sub Total** | **M2** | | **81** | **92,920.00** | **$3.81** | **$353,803.45** |
| **729010** | ROCK SLOPE PROTECTION FABRIC | | SQFT | 3 | 1 | 750.00 | $3.50 | $2,625.00 |
| | | | SQFT | 4 | 1 | 300.00 | $10.00 | $3,000.00 |
| | | **Unit Sub Total** | **SQFT** | | **2** | **1,050.00** | **$5.36** | **$5,625.00** |
| **729010** | ROCK SLOPE PROTECTION FABRIC | | SQYD | 1 | 7 | 4,779.00 | $1.74 | $8,298.00 |
| | | | SQYD | 2 | 7 | 2,230.00 | $2.21 | $4,918.00 |
| | | | SQYD | 3 | 9 | 16,840.00 | $2.81 | $47,360.50 |
| | | | SQYD | 4 | 1 | 150.00 | $1.47 | $220.50 |
| | | | SQYD | 5 | 3 | 30.40 | $41.57 | $1,263.60 |
| | | | SQYD | 6 | 2 | 33.00 | $17.67 | $583.00 |
| | | | SQYD | 7 | 3 | 7,140.00 | $2.15 | $15,346.00 |
| | | | SQYD | 8 | 1 | 160.00 | $5.00 | $800.00 |
| | | | SQYD | 9 | 2 | 338.00 | $9.83 | $3,322.00 |
| | | | SQYD | 11 | 3 | 92.00 | $9.13 | $840.40 |
| | | | SQYD | 12 | 1 | 21.00 | $13.00 | $273.00 |
| | | **Unit Sub Total** | **SQYD** | | **39** | **31,813.40** | **$2.62** | **$83,225.00** |
| | **Item Code 729010** | **Total No. of Proj.** | | | **122** | | **Total Amount** | **$442,653.45** |
| **731501** | MINOR CONCRETE (CURB) | | CY | 4 | 2 | 220.00 | $445.45 | $98,000.00 |
| | | | CY | 7 | 2 | 35.00 | $1,865.71 | $65,300.00 |
| | | | CY | 8 | 1 | 3.60 | $450.00 | $1,620.00 |
| | | | CY | 10 | 2 | 75.00 | $417.60 | $31,320.00 |
| | | | CY | 12 | 3 | 94.20 | $699.79 | $65,920.00 |
| | | **Unit Sub Total** | **CY** | | **10** | **427.80** | **$612.81** | **$262,160.00** |
| **731501** | MINOR CONCRETE (CURB) | | LF | 1 | 2 | 790.00 | $38.73 | $30,600.00 |
| | | **Unit Sub Total** | **LF** | | **2** | **790.00** | **$38.73** | **$30,600.00** |
| **731501** | MINOR CONCRETE (CURB) | | M | 6 | 1 | 130.00 | $120.00 | $15,600.00 |
| | | | M | 12 | 1 | 15.00 | $290.00 | $4,350.00 |
| | | **Unit Sub Total** | **M** | | **2** | **145.00** | **$137.59** | **$19,950.00** |
| **731501** | MINOR CONCRETE (CURB) | | M3 | 3 | 2 | 12.50 | $1,281.60 | $16,020.00 |
| | | | M3 | 5 | 1 | 96.00 | $850.00 | $81,600.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **731501** | MINOR CONCRETE (CURB) | M3 | 6 | 1 | 4.40 | $1,300.00 | $5,720.00 |
| | | M3 | 7 | 3 | 165.00 | $368.82 | $60,855.00 |
| | | M3 | 10 | 1 | 2.80 | $387.60 | $1,085.28 |
| | **Unit Sub Total** | **M3** | | **8** | **280.70** | **$588.81** | **$165,280.28** |
| | **Item Code 731501 Total No. of Proj.** | | | **22** | | **Total Amount** | **$477,990.28** |
| **731502** | MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION) | CY | 2 | 3 | 21.20 | $744.34 | $15,780.00 |
| | | CY | 3 | 2 | 965.00 | $309.97 | $299,125.00 |
| | | CY | 4 | 2 | 145.00 | $589.66 | $85,500.00 |
| | | CY | 5 | 1 | 26.00 | $1,905.00 | $49,530.00 |
| | | CY | 6 | 2 | 1,090.00 | $518.81 | $565,500.00 |
| | | CY | 7 | 3 | 247.00 | $818.22 | $202,100.00 |
| | | CY | 8 | 2 | 165.00 | $310.06 | $51,160.40 |
| | | CY | 11 | 5 | 93.30 | $503.97 | $47,020.00 |
| | | CY | 12 | 5 | 283.30 | $407.74 | $115,512.00 |
| | **Unit Sub Total** | **CY** | | **25** | **3,035.80** | **$471.45** | **$1,431,227.40** |
| **731502** | MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION) | M3 | 1 | 1 | 220.00 | $800.00 | $176,000.00 |
| | | M3 | 3 | 2 | 1,920.00 | $1,163.54 | $2,234,000.00 |
| | | M3 | 4 | 8 | 738.00 | $974.01 | $718,820.82 |
| | | M3 | 5 | 6 | 688.50 | $770.05 | $530,180.00 |
| | | M3 | 6 | 3 | 2,748.00 | $404.70 | $1,112,120.00 |
| | | M3 | 7 | 6 | 1,562.50 | $714.17 | $1,115,889.60 |
| | | M3 | 8 | 3 | 530.00 | $631.32 | $334,600.00 |
| | | M3 | 9 | 2 | 1,290.00 | $433.49 | $559,200.00 |
| | | M3 | 10 | 3 | 1,514.00 | $434.21 | $657,400.00 |
| | | M3 | 11 | 6 | 1,718.00 | $461.15 | $792,250.00 |
| | | M3 | 12 | 2 | 33.00 | $875.45 | $28,890.00 |
| | **Unit Sub Total** | **M3** | | **42** | **12,962.00** | **$637.20** | **$8,259,350.42** |
| | **Item Code 731502 Total No. of Proj.** | | | **67** | | **Total Amount** | **$9,690,577.82** |
| **731504** | MINOR CONCRETE (CURB AND GUTTER) | CY | 2 | 1 | 14.00 | $1,000.00 | $14,000.00 |
| | | CY | 8 | 1 | 15.00 | $450.00 | $6,750.00 |
| | **Unit Sub Total** | **CY** | | **2** | **29.00** | **$715.52** | **$20,750.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| 731504 | MINOR CONCRETE (CURB AND GUTTER) | LF | 12 | 1 | 380.00 | $43.00 | $16,340.00 |
| | **Unit Sub Total** | **LF** | | **1** | **380.00** | **$43.00** | **$16,340.00** |
| 731504 | MINOR CONCRETE (CURB AND GUTTER) | M3 | 2 | 1 | 110.00 | $625.00 | $68,750.00 |
| | | M3 | 3 | 1 | 390.00 | $500.00 | $195,000.00 |
| | | M3 | 5 | 1 | 310.00 | $535.00 | $165,850.00 |
| | | M3 | 7 | 3 | 247.00 | $263.60 | $65,110.00 |
| | | M3 | 10 | 1 | 11.00 | $575.00 | $6,325.00 |
| | **Unit Sub Total** | **M3** | | **7** | **1,068.00** | **$469.13** | **$501,035.00** |
| | **Item Code 731504 Total No. of Proj.** | | | **10** | | **Total Amount** | **$538,125.00** |
| 731505 | MINOR CONCRETE (CURB AND SIDEWALK) | CY | 1 | 1 | 16.00 | $1,300.00 | $20,800.00 |
| | | CY | 3 | 1 | 19.00 | $750.00 | $14,250.00 |
| | **Unit Sub Total** | **CY** | | **2** | **35.00** | **$1,001.43** | **$35,050.00** |
| 731505 | MINOR CONCRETE (CURB AND SIDEWALK) | M3 | 3 | 1 | 46.00 | $628.00 | $28,888.00 |
| | | M3 | 7 | 1 | 7.50 | $1,000.00 | $7,500.00 |
| | **Unit Sub Total** | **M3** | | **2** | **53.50** | **$680.15** | **$36,388.00** |
| | **Item Code 731505 Total No. of Proj.** | | | **4** | | **Total Amount** | **$71,438.00** |
| 731507 | MINOR CONCRETE (GUTTER DEPRESSION) | CY | 4 | 1 | 8.00 | $900.00 | $7,200.00 |
| | **Unit Sub Total** | **CY** | | **1** | **8.00** | **$900.00** | **$7,200.00** |
| | **Item Code 731507 Total No. of Proj.** | | | **1** | | **Total Amount** | **$7,200.00** |
| 731510 | MINOR CONCRETE (CURB, GUTTER, SIDEWALK AND DRIVEWAY) | M3 | 11 | 2 | 85.00 | $600.34 | $51,029.00 |
| | **Unit Sub Total** | **M3** | | **2** | **85.00** | **$600.34** | **$51,029.00** |
| | **Item Code 731510 Total No. of Proj.** | | | **2** | | **Total Amount** | **$51,029.00** |
| 731511 | MINOR CONCRETE (ISLAND PAVING) | CY | 4 | 2 | 634.00 | $366.25 | $232,200.00 |
| | **Unit Sub Total** | **CY** | | **2** | **634.00** | **$366.25** | **$232,200.00** |
| 731511 | MINOR CONCRETE (ISLAND PAVING) | SQYD | 12 | 1 | 1,900.00 | $90.59 | $172,121.00 |
| | **Unit Sub Total** | **SQYD** | | **1** | **1,900.00** | **$90.59** | **$172,121.00** |
| | **Item Code 731511 Total No. of Proj.** | | | **3** | | **Total Amount** | **$404,321.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| 731512 | MINOR CONCRETE (EXPOSED AGGREGATE SIDEWALK) | CY | 8 | 1 | 33.00 | $488.00 | $16,104.00 |
| | **Unit Sub Total** | **CY** | | **1** | **33.00** | **$488.00** | **$16,104.00** |
| | **Item Code 731512 Total No. of Proj.** | | | **1** | | **Total Amount** | **$16,104.00** |
| 731516 | MINOR CONCRETE (DRIVEWAY) | CY | 8 | 1 | 70.00 | $351.00 | $24,570.00 |
| | | CY | 12 | 1 | 0.30 | $3,000.00 | $900.00 |
| | **Unit Sub Total** | **CY** | | **2** | **70.30** | **$362.30** | **$25,470.00** |
| 731516 | MINOR CONCRETE (DRIVEWAY) | M3 | 5 | 1 | 38.00 | $550.00 | $20,900.00 |
| | **Unit Sub Total** | **M3** | | **1** | **38.00** | **$550.00** | **$20,900.00** |
| | **Item Code 731516 Total No. of Proj.** | | | **3** | | **Total Amount** | **$46,370.00** |
| 731517 | MINOR CONCRETE (GUTTER) | LF | 1 | 1 | 397.00 | $40.00 | $15,880.00 |
| | **Unit Sub Total** | **LF** | | **1** | **397.00** | **$40.00** | **$15,880.00** |
| 731517 | MINOR CONCRETE (GUTTER) | M | 3 | 1 | 869.00 | $78.00 | $67,782.00 |
| | | M | 4 | 3 | 1,633.00 | $106.38 | $173,710.60 |
| | | M | 5 | 1 | 744.00 | $40.00 | $29,760.00 |
| | | M | 7 | 1 | 31.00 | $20.00 | $620.00 |
| | | M | 8 | 1 | 109.00 | $130.00 | $14,170.00 |
| | | M | 10 | 2 | 51.00 | $183.53 | $9,360.00 |
| | | M | 11 | 6 | 602.00 | $100.90 | $60,740.00 |
| | **Unit Sub Total** | **M** | | **15** | **4,039.00** | **$88.18** | **$356,142.60** |
| 731517 | MINOR CONCRETE (GUTTER) | M2 | 7 | 1 | 23.00 | $1,480.00 | $34,040.00 |
| | **Unit Sub Total** | **M2** | | **1** | **23.00** | **$1,480.00** | **$34,040.00** |
| 731517 | MINOR CONCRETE (GUTTER) | M3 | 5 | 2 | 22.00 | $847.95 | $18,655.00 |
| | | M3 | 11 | 1 | 48.00 | $75.00 | $3,600.00 |
| | **Unit Sub Total** | **M3** | | **3** | **70.00** | **$317.93** | **$22,255.00** |
| | **Item Code 731517 Total No. of Proj.** | | | **20** | | **Total Amount** | **$428,317.60** |
| 731519 | MINOR CONCRETE (STAMPED CONCRETE) | CY | 12 | 1 | 70.00 | $250.00 | $17,500.00 |
| | **Unit Sub Total** | **CY** | | **1** | **70.00** | **$250.00** | **$17,500.00** |
| 731519 | MINOR CONCRETE (STAMPED CONCRETE) | M2 | 3 | 1 | 200.00 | $100.00 | $20,000.00 |
| | | M2 | 7 | 3 | 21,130.00 | $85.28 | $1,801,980.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **M2** | | **4** | **21,330.00** | **$85.42** | **$1,821,980.00** |
| **731519** | MINOR CONCRETE (STAMPED CONCRETE) | M3 | 7 | 1 | 61.00 | $871.70 | $53,173.70 |
| | **Unit Sub Total** | **M3** | | **1** | **61.00** | **$871.70** | **$53,173.70** |
| | **Item Code 731519 Total No. of Proj.** | | | **6** | | **Total Amount** | **$1,892,653.70** |
| **731521** | MINOR CONCRETE (SIDEWALK) | CY | 2 | 1 | 17.00 | $1,500.00 | $25,500.00 |
| | | CY | 7 | 2 | 171.00 | $336.96 | $57,620.00 |
| | | CY | 8 | 3 | 559.00 | $345.56 | $193,170.00 |
| | | CY | 12 | 1 | 0.40 | $3,000.00 | $1,200.00 |
| | **Unit Sub Total** | **CY** | | **7** | **747.40** | **$371.27** | **$277,490.00** |
| **731521** | MINOR CONCRETE (SIDEWALK) | M3 | 2 | 1 | 880.00 | $625.00 | $550,000.00 |
| | | M3 | 3 | 1 | 390.00 | $300.00 | $117,000.00 |
| | | M3 | 5 | 1 | 460.00 | $550.00 | $253,000.00 |
| | | M3 | 7 | 1 | 450.00 | $215.00 | $96,750.00 |
| | **Unit Sub Total** | **M3** | | **4** | **2,180.00** | **$466.40** | **$1,016,750.00** |
| | **Item Code 731521 Total No. of Proj.** | | | **11** | | **Total Amount** | **$1,294,240.00** |
| **731530** | MINOR CONCRETE (TEXTURED PAVING) | CY | 3 | 1 | 10.00 | $590.00 | $5,900.00 |
| | | CY | 11 | 1 | 2.50 | $9,000.00 | $22,500.00 |
| | **Unit Sub Total** | **CY** | | **2** | **12.50** | **$2,272.00** | **$28,400.00** |
| **731530** | MINOR CONCRETE (TEXTURED PAVING) | M2 | 3 | 1 | 1,460.00 | $90.00 | $131,400.00 |
| | | M2 | 4 | 1 | 1,220.00 | $60.00 | $73,200.00 |
| | | M2 | 5 | 1 | 160.00 | $105.00 | $16,800.00 |
| | | M2 | 6 | 1 | 220.00 | $85.00 | $18,700.00 |
| | | M2 | 10 | 1 | 750.00 | $30.00 | $22,500.00 |
| | | M2 | 11 | 8 | 20,790.00 | $67.03 | $1,393,640.00 |
| | **Unit Sub Total** | **M2** | | **13** | **24,600.00** | **$67.33** | **$1,656,240.00** |
| **731530** | MINOR CONCRETE (TEXTURED PAVING) | M3 | 6 | 1 | 30.00 | $900.00 | $27,000.00 |
| | | M3 | 10 | 1 | 210.00 | $623.25 | $130,882.50 |
| | **Unit Sub Total** | **M3** | | **2** | **240.00** | **$657.84** | **$157,882.50** |
| **731530** | MINOR CONCRETE (TEXTURED PAVING) | SQFT | 6 | 1 | 4,930.00 | $9.15 | $45,109.50 |
| | **Unit Sub Total** | **SQFT** | | **1** | **4,930.00** | **$9.15** | **$45,109.50** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 731530 Total No. of Proj.** | | | **18** | | **Total Amount** | **$1,887,632.00** |
| **731623** | MINOR CONCRETE (CURB RAMP) | CY | 4 | 1 | 1.00 | $2,500.00 | $2,500.00 |
| | | CY | 7 | 1 | 22.00 | $336.00 | $7,392.00 |
| | | CY | 11 | 1 | 8.00 | $1,300.00 | $10,400.00 |
| | | CY | 12 | 1 | 2.50 | $1,350.00 | $3,375.00 |
| | **Unit Sub Total** | **CY** | | **4** | **33.50** | **$706.48** | **$23,667.00** |
| **731623** | MINOR CONCRETE (CURB RAMP) | M3 | 3 | 1 | 54.00 | $500.00 | $27,000.00 |
| | | M3 | 5 | 1 | 24.00 | $1,600.00 | $38,400.00 |
| | | M3 | 7 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | | M3 | 10 | 1 | 89.00 | $2,400.00 | $213,600.00 |
| | **Unit Sub Total** | **M3** | | **4** | **168.00** | **$1,672.62** | **$281,000.00** |
| | **Item Code 731623 Total No. of Proj.** | | | **8** | | **Total Amount** | **$304,667.00** |
| **731626** | MINOR CONCRETE (CURB AND CURB RAMP) | CY | 3 | 1 | 4.20 | $950.00 | $3,990.00 |
| | | CY | 10 | 1 | 27.00 | $732.00 | $19,764.00 |
| | **Unit Sub Total** | **CY** | | **2** | **31.20** | **$761.35** | **$23,754.00** |
| **731626** | MINOR CONCRETE (CURB AND CURB RAMP) | M3 | 2 | 1 | 0.70 | $3,552.31 | $2,486.62 |
| | | M3 | 3 | 1 | 2.00 | $1,041.00 | $2,082.00 |
| | **Unit Sub Total** | **M3** | | **2** | **2.70** | **$1,692.08** | **$4,568.62** |
| | **Item Code 731626 Total No. of Proj.** | | | **4** | | **Total Amount** | **$28,322.62** |
| **731627** | MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP) | CY | 1 | 1 | 11.00 | $1,550.00 | $17,050.00 |
| | | CY | 4 | 1 | 170.00 | $1,310.00 | $222,700.00 |
| | | CY | 8 | 4 | 88.00 | $486.82 | $42,840.00 |
| | | CY | 11 | 1 | 10.00 | $660.00 | $6,600.00 |
| | | CY | 12 | 2 | 13.00 | $769.23 | $10,000.00 |
| | **Unit Sub Total** | **CY** | | **9** | **292.00** | **$1,024.62** | **$299,190.00** |
| **731627** | MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP) | M3 | 1 | 1 | 39.00 | $600.00 | $23,400.00 |
| | | M3 | 3 | 1 | 4.00 | $2,000.00 | $8,000.00 |
| | | M3 | 5 | 1 | 24.00 | $1,555.00 | $37,320.00 |
| | | M3 | 7 | 3 | 14.00 | $1,255.71 | $17,580.00 |
| | | M3 | 8 | 1 | 30.00 | $660.00 | $19,800.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| 731627 | MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP) | M3 | 10 | 1 | 59.00 | $515.00 | $30,385.00 |
| | | M3 | 11 | 3 | 560.00 | $585.36 | $327,800.00 |
| | **Unit Sub Total** | **M3** | | **11** | **730.00** | **$636.01** | **$464,285.00** |
| | **Item Code 731627 Total No. of Proj.** | | | **20** | | **Total Amount** | **$763,475.00** |
| 731656 | CURB RAMP DETECTABLE WARNING SURFACE | EA | 8 | 1 | 1.00 | $400.00 | $400.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$400.00** | **$400.00** |
| 731656 | CURB RAMP DETECTABLE WARNING SURFACE | M2 | 12 | 1 | 1.40 | $800.00 | $1,120.00 |
| | **Unit Sub Total** | **M2** | | **1** | **1.40** | **$800.00** | **$1,120.00** |
| 731656 | CURB RAMP DETECTABLE WARNING SURFACE | SQFT | 2 | 1 | 48.00 | $40.00 | $1,920.00 |
| | | SQFT | 12 | 8 | 270.00 | $51.28 | $13,845.04 |
| | **Unit Sub Total** | **SQFT** | | **9** | **318.00** | **$49.58** | **$15,765.04** |
| | **Item Code 731656 Total No. of Proj.** | | | **11** | | **Total Amount** | **$17,285.04** |
| 740500 | DRAINAGE PUMPING EQUIPMENT | LS | 10 | 1 | 1.00 | $30,000.00 | $30,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$30,000.00** | **$30,000.00** |
| | **Item Code 740500 Total No. of Proj.** | | | **1** | | **Total Amount** | **$30,000.00** |
| 750001 | MISCELLANEOUS IRON AND STEEL | KG | 1 | 6 | 9,478.00 | $3.77 | $35,719.00 |
| | | KG | 2 | 4 | 12,346.00 | $4.88 | $60,241.12 |
| | | KG | 3 | 6 | 83,464.00 | $3.88 | $324,128.20 |
| | | KG | 4 | 15 | 104,446.00 | $3.22 | $336,532.96 |
| | | KG | 5 | 13 | 56,012.00 | $3.81 | $213,452.10 |
| | | KG | 6 | 3 | 6,392.00 | $4.08 | $26,094.00 |
| | | KG | 7 | 14 | 193,877.00 | $4.16 | $806,244.25 |
| | | KG | 8 | 4 | 64,648.00 | $4.00 | $258,372.20 |
| | | KG | 9 | 2 | 9,842.00 | $5.80 | $57,127.00 |
| | | KG | 10 | 6 | 7,701.00 | $5.74 | $44,236.00 |
| | | KG | 11 | 12 | 181,920.00 | $4.13 | $751,071.14 |
| | | KG | 12 | 1 | 1,435.00 | $5.00 | $7,175.00 |
| | **Unit Sub Total** | **KG** | | **86** | **731,561.00** | **$3.99** | **$2,920,392.97** |
| 750001 | MISCELLANEOUS IRON AND STEEL | LB | 1 | 7 | 2,532.00 | $3.38 | $8,566.00 |
| | | LB | 2 | 8 | 12,702.00 | $2.62 | $33,296.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **750001** | MISCELLANEOUS IRON AND STEEL | LB | 3 | 9 | 213,594.00 | $2.67 | $569,610.00 |
| | | LB | 4 | 4 | 6,021.00 | $3.50 | $21,063.00 |
| | | LB | 5 | 4 | 5,238.00 | $2.73 | $14,310.40 |
| | | LB | 6 | 5 | 10,319.00 | $1.76 | $18,166.00 |
| | | LB | 7 | 2 | 7,345.00 | $16.60 | $121,929.50 |
| | | LB | 8 | 4 | 12,740.00 | $4.65 | $59,227.00 |
| | | LB | 11 | 4 | 31,859.00 | $1.60 | $50,935.00 |
| | | LB | 12 | 5 | 8,195.00 | $2.64 | $21,646.50 |
| | **Unit Sub Total** | **LB** | | **52** | **310,545.00** | **$2.96** | **$918,749.40** |
| | **Item Code 750001 Total No. of Proj.** | | | **138** | | **Total Amount** | **$3,839,142.37** |
| **750007** | FRAME AND GRATE | EA | 4 | 1 | 5.00 | $300.00 | $1,500.00 |
| | | EA | 6 | 1 | 1.00 | $425.00 | $425.00 |
| | | EA | 10 | 1 | 100.00 | $366.00 | $36,600.00 |
| | **Unit Sub Total** | **EA** | | **3** | **106.00** | **$363.44** | **$38,525.00** |
| | **Item Code 750007 Total No. of Proj.** | | | **3** | | **Total Amount** | **$38,525.00** |
| **750008** | FRAME AND COVER | EA | 5 | 1 | 56.00 | $231.00 | $12,936.00 |
| | **Unit Sub Total** | **EA** | | **1** | **56.00** | **$231.00** | **$12,936.00** |
| | **Item Code 750008 Total No. of Proj.** | | | **1** | | **Total Amount** | **$12,936.00** |
| **750010** | MANHOLE FRAME AND COVER | EA | 10 | 2 | 23.00 | $565.00 | $12,995.00 |
| | **Unit Sub Total** | **EA** | | **2** | **23.00** | **$565.00** | **$12,995.00** |
| | **Item Code 750010 Total No. of Proj.** | | | **2** | | **Total Amount** | **$12,995.00** |
| **750013** | MANHOLE FRAME AND COVER (PRESSURE) | EA | 10 | 1 | 10.00 | $500.00 | $5,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **10.00** | **$500.00** | **$5,000.00** |
| | **Item Code 750013 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,000.00** |
| **750030** | INLET FRAME AND GRATE | EA | 8 | 1 | 2.00 | $550.00 | $1,100.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$550.00** | **$1,100.00** |
| | **Item Code 750030 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,100.00** |
| **750041** | ISOLATION CASING | KG | 1 | 1 | 6,785.00 | $30.00 | $203,550.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **750041** | ISOLATION CASING | KG | 7 | 1 | 1,560.00 | $21.00 | $32,760.00 |
| | | KG | 11 | 1 | 26,900.00 | $3.60 | $96,840.00 |
| | **Unit Sub Total** | **KG** | | **3** | **35,245.00** | **$9.45** | **$333,150.00** |
| **750041** | ISOLATION CASING | LB | 8 | 1 | 7,170.00 | $7.00 | $50,190.00 |
| | **Unit Sub Total** | **LB** | | **1** | **7,170.00** | **$7.00** | **$50,190.00** |
| | **Item Code 750041 Total No. of Proj.** | | | **4** | | **Total Amount** | **$383,340.00** |
| **750049** | INLET GRATE (TYPE 36R) | EA | 3 | 1 | 5.00 | $500.00 | $2,500.00 |
| | **Unit Sub Total** | **EA** | | **1** | **5.00** | **$500.00** | **$2,500.00** |
| | **Item Code 750049 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,500.00** |
| **750050** | INLET GRATE | EA | 4 | 1 | 1.00 | $700.00 | $700.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$700.00** | **$700.00** |
| | **Item Code 750050 Total No. of Proj.** | | | **1** | | **Total Amount** | **$700.00** |
| **750496** | MISCELLANEOUS METAL (RESTRAINER - PIPE TYPE) | KG | 2 | 1 | 46,597.00 | $0.00 | $0.00 |
| | **Unit Sub Total** | **KG** | | **1** | **46,597.00** | **$0.00** | **$0.00** |
| | **Item Code 750496 Total No. of Proj.** | | | **1** | | **Total Amount** | **$0.00** |
| **750498** | MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE) | KG | 4 | 1 | 6,000.00 | $50.00 | $300,000.00 |
| | | KG | 7 | 2 | 4,245.00 | $14.77 | $62,680.00 |
| | **Unit Sub Total** | **KG** | | **3** | **10,245.00** | **$35.40** | **$362,680.00** |
| **750498** | MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE) | LB | 3 | 1 | 8,080.00 | $12.50 | $101,000.00 |
| | | LB | 11 | 1 | 150.00 | $48.00 | $7,200.00 |
| | **Unit Sub Total** | **LB** | | **2** | **8,230.00** | **$13.15** | **$108,200.00** |
| | **Item Code 750498 Total No. of Proj.** | | | **5** | | **Total Amount** | **$470,880.00** |
| **750500** | MISCELLANEOUS METAL | KG | 7 | 1 | 9,299.00 | $9.00 | $83,691.00 |
| | | KG | 9 | 1 | 182.00 | $15.00 | $2,730.00 |
| | **Unit Sub Total** | **KG** | | **2** | **9,481.00** | **$9.12** | **$86,421.00** |
| **750500** | MISCELLANEOUS METAL | LB | 2 | 1 | 1,400.00 | $10.00 | $14,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **LB** | | **1** | **1,400.00** | **$10.00** | **$14,000.00** |
| | **Item Code 750500** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$100,421.00** |
| **750501** | MISCELLANEOUS METAL (BRIDGE) | | KG | 1 | 1 | 50.00 | $25.00 | $1,250.00 |
| | | | KG | 2 | 1 | 1,237.00 | $8.00 | $9,896.00 |
| | | | KG | 3 | 2 | 27,995.00 | $9.82 | $274,895.00 |
| | | | KG | 4 | 1 | 644.00 | $15.00 | $9,660.00 |
| | | | KG | 5 | 1 | 410.00 | $3.50 | $1,435.00 |
| | | | KG | 7 | 2 | 34,594.00 | $12.23 | $423,078.00 |
| | | | KG | 11 | 5 | 4,005.00 | $10.75 | $43,055.00 |
| | | **Unit Sub Total** | **KG** | | **13** | **68,935.00** | **$11.07** | **$763,269.00** |
| **750501** | MISCELLANEOUS METAL (BRIDGE) | | LB | 4 | 2 | 38,147.00 | $4.15 | $158,140.00 |
| | | | LB | 8 | 1 | 30,900.00 | $7.00 | $216,300.00 |
| | | **Unit Sub Total** | **LB** | | **3** | **69,047.00** | **$5.42** | **$374,440.00** |
| | **Item Code 750501** | **Total No. of Proj.** | | | **16** | | **Total Amount** | **$1,137,709.00** |
| **750502** | MISCELLANEOUS METAL (RETAINING WALL) | | KG | 4 | 1 | 90.00 | $30.60 | $2,754.00 |
| | | **Unit Sub Total** | **KG** | | **1** | **90.00** | **$30.60** | **$2,754.00** |
| | **Item Code 750502** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,754.00** |
| **750505** | BRIDGE DECK DRAINAGE SYSTEM | | KG | 1 | 1 | 1,910.00 | $18.00 | $34,380.00 |
| | | | KG | 2 | 1 | 2,416.00 | $14.00 | $33,824.00 |
| | | | KG | 4 | 1 | 840.00 | $22.00 | $18,480.00 |
| | | | KG | 7 | 1 | 20,180.00 | $10.00 | $201,800.00 |
| | | | KG | 11 | 8 | 43,510.00 | $12.40 | $539,405.00 |
| | | **Unit Sub Total** | **KG** | | **12** | **68,856.00** | **$12.02** | **$827,889.00** |
| **750505** | BRIDGE DECK DRAINAGE SYSTEM | | LB | 7 | 1 | 5,110.00 | $7.50 | $38,325.00 |
| | | **Unit Sub Total** | **LB** | | **1** | **5,110.00** | **$7.50** | **$38,325.00** |
| **750505** | BRIDGE DECK DRAINAGE SYSTEM | | LS | 4 | 1 | 1.00 | $1,800.00 | $1,800.00 |
| | | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$1,800.00** | **$1,800.00** |
| | **Item Code 750505** | **Total No. of Proj.** | | | **14** | | **Total Amount** | **$868,014.00** |
| **760011** | WELL DEVELOPMENT | | LS | 3 | 1 | 1.00 | $95,000.00 | $95,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **760011** | WELL DEVELOPMENT | | LS | 5 | 1 | 1.00 | $18,000.00 | $18,000.00 |
| | | | LS | 6 | 1 | 1.00 | $30,000.00 | $30,000.00 |
| | | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$47,666.67** | **$143,000.00** |
| | **Item Code 760011** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$143,000.00** |
| **760012** | TESTING WELL | | HR | 3 | 1 | 18.00 | $255.00 | $4,590.00 |
| | | | HR | 5 | 1 | 8.00 | $1,400.00 | $11,200.00 |
| | | | HR | 6 | 1 | 8.00 | $300.00 | $2,400.00 |
| | | **Unit Sub Total** | **HR** | | **3** | **34.00** | **$535.00** | **$18,190.00** |
| | **Item Code 760012** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$18,190.00** |
| **760021** | DRILL PILOT HOLE | | LF | 5 | 1 | 300.00 | $200.00 | $60,000.00 |
| | | | LF | 6 | 1 | 350.00 | $100.00 | $35,000.00 |
| | | **Unit Sub Total** | **LF** | | **2** | **650.00** | **$146.15** | **$95,000.00** |
| **760021** | DRILL PILOT HOLE | | M | 3 | 1 | 92.00 | $115.00 | $10,580.00 |
| | | **Unit Sub Total** | **M** | | **1** | **92.00** | **$115.00** | **$10,580.00** |
| | **Item Code 760021** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$105,580.00** |
| **760022** | REAMING WATER WELL | | LF | 5 | 1 | 300.00 | $200.00 | $60,000.00 |
| | | | LF | 6 | 1 | 350.00 | $80.00 | $28,000.00 |
| | | **Unit Sub Total** | **LF** | | **2** | **650.00** | **$135.38** | **$88,000.00** |
| **760022** | REAMING WATER WELL | | M | 3 | 1 | 92.00 | $250.00 | $23,000.00 |
| | | **Unit Sub Total** | **M** | | **1** | **92.00** | **$250.00** | **$23,000.00** |
| | **Item Code 760022** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$111,000.00** |
| **760025** | CONDUCTOR CASING | | LF | 5 | 1 | 50.00 | $510.00 | $25,500.00 |
| | | | LF | 6 | 1 | 50.00 | $400.00 | $20,000.00 |
| | | **Unit Sub Total** | **LF** | | **2** | **100.00** | **$455.00** | **$45,500.00** |
| **760025** | CONDUCTOR CASING | | M | 3 | 1 | 46.00 | $1,200.00 | $55,200.00 |
| | | **Unit Sub Total** | **M** | | **1** | **46.00** | **$1,200.00** | **$55,200.00** |
| | **Item Code 760025** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$100,700.00** |
| **760030** | BLANK WELL CASING | | LF | 5 | 1 | 290.00 | $125.00 | $36,250.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **760030** | BLANK WELL CASING | | LF | 6 | 1 | 340.00 | $60.00 | $20,400.00 |
| | | **Unit Sub Total** | **LF** | | **2** | **630.00** | **$89.92** | **$56,650.00** |
| **760030** | BLANK WELL CASING | | M | 3 | 1 | 60.00 | $185.00 | $11,100.00 |
| | | **Unit Sub Total** | **M** | | **1** | **60.00** | **$185.00** | **$11,100.00** |
| | **Item Code 760030** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$67,750.00** |
| **760035** | WELL SCREEN | | LF | 5 | 1 | 13.00 | $1,200.00 | $15,600.00 |
| | | | LF | 6 | 1 | 13.00 | $850.00 | $11,050.00 |
| | | **Unit Sub Total** | **LF** | | **2** | **26.00** | **$1,025.00** | **$26,650.00** |
| **760035** | WELL SCREEN | | M | 3 | 1 | 28.00 | $250.00 | $7,000.00 |
| | | **Unit Sub Total** | **M** | | **1** | **28.00** | **$250.00** | **$7,000.00** |
| | **Item Code 760035** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$33,650.00** |
| **760090** | MOBILIZATION, DEMOBILIZATION, AND FINAL CLEANUP | | LS | 3 | 1 | 1.00 | $210,000.00 | $210,000.00 |
| | | | LS | 5 | 1 | 1.00 | $90,000.00 | $90,000.00 |
| | | | LS | 6 | 1 | 1.00 | $180,000.00 | $180,000.00 |
| | | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$160,000.00** | **$480,000.00** |
| | **Item Code 760090** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$480,000.00** |
| **800001** | FENCE (TYPE BW, METAL POST) | | M | 1 | 1 | 1,120.00 | $48.00 | $53,760.00 |
| | | | M | 2 | 1 | 100.00 | $110.00 | $11,000.00 |
| | | | M | 5 | 1 | 115.00 | $39.00 | $4,485.00 |
| | | | M | 6 | 1 | 590.00 | $18.75 | $11,062.50 |
| | | **Unit Sub Total** | **M** | | **4** | **1,925.00** | **$41.72** | **$80,307.50** |
| | **Item Code 800001** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$80,307.50** |
| **800007** | FENCE (TYPE BW, 5 STRAND, METAL POST) | | LF | 1 | 1 | 510.00 | $7.50 | $3,825.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **510.00** | **$7.50** | **$3,825.00** |
| **800007** | FENCE (TYPE BW, 5 STRAND, METAL POST) | | M | 1 | 1 | 3,770.00 | $21.00 | $79,170.00 |
| | | | M | 5 | 5 | 10,113.00 | $13.92 | $140,807.25 |
| | | | M | 6 | 1 | 1,520.00 | $17.00 | $25,840.00 |
| | | | M | 9 | 3 | 43,090.00 | $12.70 | $547,305.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **M** | | **10** | **58,493.00** | **$13.56** | **$793,122.25** |
| | **Item Code 800007 Total No. of Proj.** | | | **11** | | **Total Amount** | **$796,947.25** |
| **800008** | FENCE (TYPE BW, 4-STRAND, METAL POST) | M | 3 | 1 | 47.00 | $50.00 | $2,350.00 |
| | | M | 11 | 1 | 7,640.00 | $15.00 | $114,600.00 |
| | **Unit Sub Total** | **M** | | **2** | **7,687.00** | **$15.21** | **$116,950.00** |
| | **Item Code 800008 Total No. of Proj.** | | | **2** | | **Total Amount** | **$116,950.00** |
| **800010** | FENCE (TYPE BW, 4-STRAND, WOOD POST) | M | 1 | 1 | 670.00 | $19.00 | $12,730.00 |
| | **Unit Sub Total** | **M** | | **1** | **670.00** | **$19.00** | **$12,730.00** |
| | **Item Code 800010 Total No. of Proj.** | | | **1** | | **Total Amount** | **$12,730.00** |
| **800051** | FENCE (TYPE WM, METAL POST) | LF | 1 | 1 | 240.00 | $5.00 | $1,200.00 |
| | | LF | 3 | 1 | 90.00 | $60.00 | $5,400.00 |
| | | LF | 5 | 1 | 1,900.00 | $9.00 | $17,100.00 |
| | | LF | 10 | 1 | 21,200.00 | $4.40 | $93,280.00 |
| | **Unit Sub Total** | **LF** | | **4** | **23,430.00** | **$4.99** | **$116,980.00** |
| **800051** | FENCE (TYPE WM, METAL POST) | M | 1 | 2 | 5,210.00 | $20.12 | $104,830.00 |
| | | M | 3 | 3 | 15,160.00 | $18.18 | $275,600.00 |
| | | M | 4 | 1 | 13,400.00 | $14.00 | $187,600.00 |
| | **Unit Sub Total** | **M** | | **6** | **33,770.00** | **$16.82** | **$568,030.00** |
| | **Item Code 800051 Total No. of Proj.** | | | **10** | | **Total Amount** | **$685,010.00** |
| **800052** | FENCE (TYPE WM, WOOD POST) | LF | 3 | 1 | 640.00 | $27.00 | $17,280.00 |
| | **Unit Sub Total** | **LF** | | **1** | **640.00** | **$27.00** | **$17,280.00** |
| **800052** | FENCE (TYPE WM, WOOD POST) | M | 4 | 1 | 340.00 | $58.50 | $19,890.00 |
| | **Unit Sub Total** | **M** | | **1** | **340.00** | **$58.50** | **$19,890.00** |
| | **Item Code 800052 Total No. of Proj.** | | | **2** | | **Total Amount** | **$37,170.00** |
| **800054** | FENCE (TYPE WM, MODIFIED) | M | 5 | 1 | 7,810.00 | $23.00 | $179,630.00 |
| | **Unit Sub Total** | **M** | | **1** | **7,810.00** | **$23.00** | **$179,630.00** |
| | **Item Code 800054 Total No. of Proj.** | | | **1** | | **Total Amount** | **$179,630.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **800060** | FENCE (TYPE WM AND BW) | M | 1 | 1 | 190.00 | $25.00 | $4,750.00 |
| | | M | 2 | 1 | 49.00 | $127.00 | $6,223.00 |
| | **Unit Sub Total** | **M** | | **2** | **239.00** | **$45.91** | **$10,973.00** |
| | **Item Code 800060 Total No. of Proj.** | | | **2** | | **Total Amount** | **$10,973.00** |
| **800320** | CHAIN LINK FENCE (TYPE CL-4) | LF | 1 | 1 | 1,080.00 | $9.00 | $9,720.00 |
| | | LF | 4 | 1 | 43.00 | $60.12 | $2,585.16 |
| | | LF | 7 | 1 | 53.00 | $80.00 | $4,240.00 |
| | **Unit Sub Total** | **LF** | | **3** | **1,176.00** | **$14.07** | **$16,545.16** |
| | **Item Code 800320 Total No. of Proj.** | | | **3** | | **Total Amount** | **$16,545.16** |
| **800360** | CHAIN LINK FENCE (TYPE CL-6) | LF | 1 | 2 | 190.00 | $40.05 | $7,610.00 |
| | | LF | 4 | 2 | 211.00 | $72.44 | $15,285.05 |
| | | LF | 7 | 1 | 2,210.00 | $14.00 | $30,940.00 |
| | | LF | 8 | 1 | 1,180.00 | $20.00 | $23,600.00 |
| | | LF | 10 | 2 | 9,300.00 | $11.51 | $107,013.00 |
| | | LF | 12 | 2 | 340.00 | $28.18 | $9,582.00 |
| | **Unit Sub Total** | **LF** | | **10** | **13,431.00** | **$14.45** | **$194,030.05** |
| | **Item Code 800360 Total No. of Proj.** | | | **10** | | **Total Amount** | **$194,030.05** |
| **800361** | CHAIN LINK FENCE (TYPE CL-6, VINYL-CLAD) | LF | 11 | 1 | 80.00 | $110.00 | $8,800.00 |
| | **Unit Sub Total** | **LF** | | **1** | **80.00** | **$110.00** | **$8,800.00** |
| | **Item Code 800361 Total No. of Proj.** | | | **1** | | **Total Amount** | **$8,800.00** |
| **800365** | CHAIN LINK FENCE (TYPE CL-6, SLATTED) | LF | 4 | 1 | 40.00 | $25.00 | $1,000.00 |
| | | LF | 5 | 1 | 200.00 | $53.00 | $10,600.00 |
| | **Unit Sub Total** | **LF** | | **2** | **240.00** | **$48.33** | **$11,600.00** |
| | **Item Code 800365 Total No. of Proj.** | | | **2** | | **Total Amount** | **$11,600.00** |
| **800381** | CHAIN LINK FENCE (TYPE CL-0.9) | M | 4 | 1 | 380.00 | $40.00 | $15,200.00 |
| | **Unit Sub Total** | **M** | | **1** | **380.00** | **$40.00** | **$15,200.00** |
| | **Item Code 800381 Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,200.00** |
| **800382** | CHAIN LINK FENCE (TYPE CL-0.9, VINYL-CLAD) | M | 2 | 1 | 400.00 | $60.00 | $24,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M** | | **1** | **400.00** | **$60.00** | **$24,000.00** |
| | **Item Code 800382** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$24,000.00** |
| **800385** | CHAIN LINK FENCE (TYPE CL-1.2) | | M | 2 | 1 | 200.00 | $46.00 | $9,200.00 |
| | | | M | 3 | 1 | 2,510.00 | $40.00 | $100,400.00 |
| | | | M | 4 | 1 | 1,360.00 | $48.00 | $65,280.00 |
| | | | M | 5 | 1 | 25.00 | $170.00 | $4,250.00 |
| | | **Unit Sub Total** | **M** | | **4** | **4,095.00** | **$43.74** | **$179,130.00** |
| | **Item Code 800385** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$179,130.00** |
| **800386** | CHAIN LINK FENCE (TYPE CL-1.2, VINYL-CLAD) | | M | 4 | 3 | 1,267.00 | $86.91 | $110,121.00 |
| | | | M | 11 | 1 | 280.00 | $40.00 | $11,200.00 |
| | | **Unit Sub Total** | **M** | | **4** | **1,547.00** | **$78.42** | **$121,321.00** |
| | **Item Code 800386** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$121,321.00** |
| **800391** | CHAIN LINK FENCE (TYPE CL-1.8) | | M | 1 | 3 | 1,264.00 | $49.37 | $62,404.00 |
| | | | M | 2 | 3 | 1,996.00 | $53.79 | $107,361.48 |
| | | | M | 3 | 2 | 44,100.00 | $35.81 | $1,579,200.00 |
| | | | M | 4 | 4 | 1,063.00 | $66.10 | $70,259.00 |
| | | | M | 5 | 1 | 1,840.00 | $39.15 | $72,036.00 |
| | | | M | 6 | 1 | 89.00 | $292.00 | $25,988.00 |
| | | | M | 7 | 5 | 1,108.00 | $56.60 | $62,715.00 |
| | | | M | 8 | 1 | 10,100.00 | $39.50 | $398,950.00 |
| | | | M | 10 | 2 | 9,520.00 | $29.95 | $285,160.50 |
| | | | M | 11 | 7 | 5,351.00 | $52.64 | $281,660.00 |
| | | **Unit Sub Total** | **M** | | **29** | **76,431.00** | **$38.54** | **$2,945,733.98** |
| | **Item Code 800391** | **Total No. of Proj.** | | | **29** | | **Total Amount** | **$2,945,733.98** |
| **800392** | CHAIN LINK FENCE (TYPE CL-1.8, VINYL-CLAD) | | M | 2 | 1 | 1,050.00 | $60.00 | $63,000.00 |
| | | | M | 3 | 1 | 450.00 | $76.00 | $34,200.00 |
| | | | M | 7 | 1 | 280.00 | $235.00 | $65,800.00 |
| | | | M | 11 | 2 | 3,290.00 | $53.05 | $174,520.00 |
| | | **Unit Sub Total** | **M** | | **5** | **5,070.00** | **$66.57** | **$337,520.00** |
| | **Item Code 800392** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$337,520.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **800701** | WOOD FENCE | | LF | 4 | 1 | 120.00 | $40.00 | $4,800.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **120.00** | **$40.00** | **$4,800.00** |
| | **Item Code 800701** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,800.00** |
| **801191** | 1.2 M WIRE MESH GATE | | EA | 4 | 1 | 1.00 | $700.00 | $700.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$700.00** | **$700.00** |
| | **Item Code 801191** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$700.00** |
| **801194** | 2.4 M WIRE MESH GATE | | EA | 4 | 1 | 2.00 | $1,000.00 | $2,000.00 |
| | | | EA | 11 | 1 | 9.00 | $1,510.00 | $13,590.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **11.00** | **$1,417.27** | **$15,590.00** |
| | **Item Code 801194** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$15,590.00** |
| **801196** | 3.7 M WIRE MESH GATE | | EA | 1 | 1 | 7.00 | $600.00 | $4,200.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **7.00** | **$600.00** | **$4,200.00** |
| | **Item Code 801196** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,200.00** |
| **801272** | 4.3 M WIRE MESH GATE | | EA | 9 | 2 | 25.00 | $1,328.00 | $33,200.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **25.00** | **$1,328.00** | **$33,200.00** |
| | **Item Code 801272** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$33,200.00** |
| **801273** | 4.6 M WIRE MESH GATE | | EA | 1 | 1 | 4.00 | $1,500.00 | $6,000.00 |
| | | | EA | 6 | 1 | 1.00 | $2,100.00 | $2,100.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **5.00** | **$1,620.00** | **$8,100.00** |
| | **Item Code 801273** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$8,100.00** |
| **801274** | 4.9 M WIRE MESH GATE | | EA | 1 | 2 | 9.00 | $866.67 | $7,800.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **9.00** | **$866.67** | **$7,800.00** |
| | **Item Code 801274** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$7,800.00** |
| **801364** | 16' METAL GATE | | EA | 8 | 1 | 3.00 | $7,000.00 | $21,000.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **3.00** | **$7,000.00** | **$21,000.00** |
| | **Item Code 801364** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$21,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **801371** | 4.9 M METAL GATE | EA | 9 | 2 | 13.00 | $1,467.69 | $19,080.00 |
| | **Unit Sub Total** | **EA** | | **2** | **13.00** | **$1,467.69** | **$19,080.00** |
| | **Item Code 801371 Total No. of Proj.** | | | **2** | | **Total Amount** | **$19,080.00** |
| **801900** | CHAIN LINK GATE | EA | 7 | 1 | 1.00 | $1,170.00 | $1,170.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,170.00** | **$1,170.00** |
| | **Item Code 801900 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,170.00** |
| **802501** | 4' CHAIN LINK GATE (TYPE CL-6) | EA | 3 | 1 | 1.00 | $2,291.15 | $2,291.15 |
| | | EA | 4 | 1 | 1.00 | $1,250.00 | $1,250.00 |
| | | EA | 12 | 1 | 2.00 | $928.00 | $1,856.00 |
| | **Unit Sub Total** | **EA** | | **3** | **4.00** | **$1,349.29** | **$5,397.15** |
| | **Item Code 802501 Total No. of Proj.** | | | **3** | | **Total Amount** | **$5,397.15** |
| **802504** | 4' CHAIN LINK GATE (TYPE CL-6, SLATTED) | EA | 5 | 1 | 2.00 | $1,170.00 | $2,340.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$1,170.00** | **$2,340.00** |
| | **Item Code 802504 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,340.00** |
| **802510** | 5' CHAIN LINK GATE (TYPE CL-6) | EA | 4 | 1 | 1.00 | $1,965.00 | $1,965.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$1,965.00** | **$1,965.00** |
| | **Item Code 802510 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,965.00** |
| **802520** | 6' CHAIN LINK GATE (TYPE CL-6) | EA | 5 | 1 | 4.00 | $1,170.00 | $4,680.00 |
| | | EA | 6 | 1 | 2.00 | $1,250.00 | $2,500.00 |
| | | EA | 11 | 1 | 6.00 | $1,500.00 | $9,000.00 |
| | **Unit Sub Total** | **EA** | | **3** | **12.00** | **$1,348.33** | **$16,180.00** |
| | **Item Code 802520 Total No. of Proj.** | | | **3** | | **Total Amount** | **$16,180.00** |
| **802580** | 12' CHAIN LINK GATE (TYPE CL-6) | EA | 6 | 1 | 1.00 | $2,540.00 | $2,540.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$2,540.00** | **$2,540.00** |
| | **Item Code 802580 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,540.00** |
| **802584** | 0.9 M CHAIN LINK GATE (TYPE CL-1.8) | EA | 3 | 1 | 1.00 | $670.00 | $670.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$670.00** | **$670.00** |
| | **Item Code 802584** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$670.00** |
| **802585** | 1.2 M CHAIN LINK GATE (TYPE CL-1.8) | | EA | 4 | 1 | 4.00 | $1,500.00 | $6,000.00 |
| | | | EA | 5 | 1 | 1.00 | $1,750.00 | $1,750.00 |
| | | | EA | 7 | 1 | 20.00 | $900.00 | $18,000.00 |
| | | | EA | 11 | 5 | 14.00 | $1,163.29 | $16,286.00 |
| | | **Unit Sub Total** | **EA** | | **8** | **39.00** | **$1,077.85** | **$42,036.00** |
| | **Item Code 802585** | **Total No. of Proj.** | | | **8** | | **Total Amount** | **$42,036.00** |
| **802586** | 1.2 M CHAIN LINK GATE (TYPE CL-1.8, VINYL-CLAD) | | EA | 3 | 1 | 2.00 | $1,000.00 | $2,000.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$1,000.00** | **$2,000.00** |
| | **Item Code 802586** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,000.00** |
| **802590** | 1.8 M CHAIN LINK GATE (TYPE CL-1.8) | | EA | 5 | 1 | 1.00 | $1,850.00 | $1,850.00 |
| | | | EA | 10 | 1 | 4.00 | $300.00 | $1,200.00 |
| | | | EA | 11 | 1 | 5.00 | $900.00 | $4,500.00 |
| | | **Unit Sub Total** | **EA** | | **3** | **10.00** | **$755.00** | **$7,550.00** |
| | **Item Code 802590** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$7,550.00** |
| **802592** | 2.4 M CHAIN LINK GATE (TYPE CL-1.8) | | EA | 2 | 1 | 2.00 | $1,322.00 | $2,644.00 |
| | | | EA | 4 | 1 | 2.00 | $1,020.00 | $2,040.00 |
| | | | EA | 7 | 1 | 2.00 | $2,000.00 | $4,000.00 |
| | | | EA | 11 | 3 | 19.00 | $1,147.37 | $21,800.00 |
| | | **Unit Sub Total** | **EA** | | **6** | **25.00** | **$1,219.36** | **$30,484.00** |
| | **Item Code 802592** | **Total No. of Proj.** | | | **6** | | **Total Amount** | **$30,484.00** |
| **802595** | 3.0 M CHAIN LINK GATE (TYPE CL-1.8) | | EA | 3 | 1 | 26.00 | $1,000.00 | $26,000.00 |
| | | | EA | 10 | 1 | 6.00 | $816.00 | $4,896.00 |
| | | | EA | 11 | 1 | 3.00 | $2,000.00 | $6,000.00 |
| | | **Unit Sub Total** | **EA** | | **3** | **35.00** | **$1,054.17** | **$36,896.00** |
| | **Item Code 802595** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$36,896.00** |
| **802596** | 3.7 M CHAIN LINK GATE (TYPE CL-1.8) | | EA | 2 | 2 | 4.00 | $1,517.61 | $6,070.44 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **802596** | 3.7 M CHAIN LINK GATE (TYPE CL-1.8) | EA | 5 | 1 | 1.00 | $1,980.00 | $1,980.00 |
| | | EA | 7 | 1 | 1.00 | $1,885.00 | $1,885.00 |
| | | EA | 11 | 1 | 2.00 | $525.00 | $1,050.00 |
| | **Unit Sub Total** | **EA** | | **5** | **8.00** | **$1,373.18** | **$10,985.44** |
| | **Item Code 802596 Total No. of Proj.** | | | **5** | | **Total Amount** | **$10,985.44** |
| **802620** | 16' CHAIN LINK GATE (TYPE CL-6) | EA | 7 | 1 | 14.00 | $1,400.00 | $19,600.00 |
| | **Unit Sub Total** | **EA** | | **1** | **14.00** | **$1,400.00** | **$19,600.00** |
| | **Item Code 802620 Total No. of Proj.** | | | **1** | | **Total Amount** | **$19,600.00** |
| **802660** | 20' CHAIN LINK GATE (TYPE CL-6) | EA | 12 | 1 | 2.00 | $1,677.58 | $3,355.16 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$1,677.58** | **$3,355.16** |
| | **Item Code 802660 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,355.16** |
| **802671** | 4.3 M CHAIN LINK GATE (TYPE CL-1.8) | EA | 3 | 1 | 2.00 | $1,500.00 | $3,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$1,500.00** | **$3,000.00** |
| | **Item Code 802671 Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,000.00** |
| **802672** | 4.9 M CHAIN LINK GATE (TYPE CL-1.8) | EA | 1 | 1 | 1.00 | $1,800.00 | $1,800.00 |
| | | EA | 8 | 1 | 5.00 | $1,575.00 | $7,875.00 |
| | | EA | 11 | 1 | 1.00 | $2,853.58 | $2,853.58 |
| | **Unit Sub Total** | **EA** | | **3** | **7.00** | **$1,789.80** | **$12,528.58** |
| | **Item Code 802672 Total No. of Proj.** | | | **3** | | **Total Amount** | **$12,528.58** |
| **802675** | 6.1 M CHAIN LINK GATE (TYPE CL-1.8) | EA | 3 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$2,000.00** | **$2,000.00** |
| | **Item Code 802675 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,000.00** |
| **810110** | SURVEY MONUMENT | EA | 5 | 2 | 34.00 | $408.82 | $13,900.00 |
| | | EA | 6 | 1 | 2.00 | $650.00 | $1,300.00 |
| | | EA | 8 | 1 | 13.00 | $1,980.00 | $25,740.00 |
| | **Unit Sub Total** | **EA** | | **4** | **49.00** | **$835.51** | **$40,940.00** |
| | **Item Code 810110 Total No. of Proj.** | | | **4** | | **Total Amount** | **$40,940.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **810111** | SURVEY MONUMENT (TYPE A) | EA | 5 | 2 | 19.00 | $989.74 | $18,805.00 |
| | | EA | 10 | 1 | 1.00 | $500.00 | $500.00 |
| | **Unit Sub Total** | **EA** | | **3** | **20.00** | **$965.25** | **$19,305.00** |
| | **Item Code 810111 Total No. of Proj.** | | | **3** | | **Total Amount** | **$19,305.00** |
| **810112** | SURVEY MONUMENT (TYPE B) | EA | 6 | 2 | 38.00 | $554.47 | $21,070.00 |
| | **Unit Sub Total** | **EA** | | **2** | **38.00** | **$554.47** | **$21,070.00** |
| | **Item Code 810112 Total No. of Proj.** | | | **2** | | **Total Amount** | **$21,070.00** |
| **810116** | SURVEY MONUMENT (TYPE D) | EA | 5 | 1 | 20.00 | $598.00 | $11,960.00 |
| | | EA | 8 | 1 | 12.00 | $750.00 | $9,000.00 |
| | | EA | 9 | 2 | 16.00 | $675.00 | $10,800.00 |
| | | EA | 10 | 1 | 7.00 | $365.00 | $2,555.00 |
| | **Unit Sub Total** | **EA** | | **5** | **55.00** | **$623.91** | **$34,315.00** |
| | **Item Code 810116 Total No. of Proj.** | | | **5** | | **Total Amount** | **$34,315.00** |
| **820101** | MARKER | EA | 11 | 1 | 1.00 | $416.14 | $416.14 |
| | **Unit Sub Total** | **EA** | | **1** | **1.00** | **$416.14** | **$416.14** |
| | **Item Code 820101 Total No. of Proj.** | | | **1** | | **Total Amount** | **$416.14** |
| **820105** | DELINEATOR (SPECIAL) | EA | 9 | 1 | 31.00 | $70.00 | $2,170.00 |
| | **Unit Sub Total** | **EA** | | **1** | **31.00** | **$70.00** | **$2,170.00** |
| | **Item Code 820105 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,170.00** |
| **820107** | DELINEATOR (CLASS 1) | EA | 1 | 7 | 905.00 | $40.65 | $36,785.00 |
| | | EA | 2 | 2 | 96.00 | $53.85 | $5,170.00 |
| | | EA | 3 | 10 | 776.00 | $42.61 | $33,069.00 |
| | | EA | 4 | 7 | 830.00 | $37.45 | $31,082.00 |
| | | EA | 5 | 16 | 1,919.00 | $33.40 | $64,099.10 |
| | | EA | 6 | 6 | 241.00 | $36.48 | $8,792.00 |
| | | EA | 7 | 6 | 301.00 | $36.10 | $10,866.00 |
| | | EA | 8 | 3 | 141.00 | $48.44 | $6,830.00 |
| | | EA | 10 | 8 | 379.00 | $38.84 | $14,722.00 |
| | | EA | 11 | 12 | 1,194.00 | $46.89 | $55,982.00 |
| | | EA | 12 | 9 | 828.00 | $46.53 | $38,525.46 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **86** | **7,610.00** | **$40.20** | **$305,922.56** |
| | **Item Code 820107** | **Total No. of Proj.** | | | **86** | | **Total Amount** | **$305,922.56** |
| **820108** | DELINEATOR (CLASS 2) | | EA | 1 | 2 | 12.00 | $42.67 | $512.00 |
| | | | EA | 2 | 7 | 366.00 | $66.82 | $24,455.00 |
| | | | EA | 3 | 11 | 2,664.00 | $39.08 | $104,110.00 |
| | | | EA | 6 | 1 | 480.00 | $15.00 | $7,200.00 |
| | | | EA | 8 | 1 | 240.00 | $50.00 | $12,000.00 |
| | | | EA | 9 | 4 | 1,108.00 | $41.18 | $45,630.00 |
| | | **Unit Sub Total** | **EA** | | **26** | **4,870.00** | **$39.82** | **$193,907.00** |
| | **Item Code 820108** | **Total No. of Proj.** | | | **26** | | **Total Amount** | **$193,907.00** |
| **820109** | METAL MARKER POST | | EA | 2 | 1 | 30.00 | $150.00 | $4,500.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **30.00** | **$150.00** | **$4,500.00** |
| | **Item Code 820109** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,500.00** |
| **820110** | MILEPOST MARKER | | EA | 1 | 3 | 12.00 | $37.50 | $450.00 |
| | | | EA | 2 | 7 | 26.00 | $70.77 | $1,840.00 |
| | | | EA | 3 | 2 | 36.00 | $40.00 | $1,440.00 |
| | | | EA | 6 | 3 | 28.00 | $44.82 | $1,255.00 |
| | | | EA | 7 | 1 | 4.00 | $45.00 | $180.00 |
| | | | EA | 8 | 1 | 10.00 | $100.00 | $1,000.00 |
| | | | EA | 9 | 3 | 74.00 | $46.35 | $3,430.00 |
| | | | EA | 10 | 2 | 7.00 | $40.86 | $286.00 |
| | | | EA | 11 | 11 | 144.00 | $94.51 | $13,609.00 |
| | | **Unit Sub Total** | **EA** | | **33** | **341.00** | **$68.89** | **$23,490.00** |
| | **Item Code 820110** | **Total No. of Proj.** | | | **33** | | **Total Amount** | **$23,490.00** |
| **820111** | UNDERDRAIN MARKER | | EA | 1 | 1 | 2.00 | $25.00 | $50.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$25.00** | **$50.00** |
| | **Item Code 820111** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$50.00** |
| **820112** | MARKER (CULVERT) | | EA | 1 | 8 | 118.00 | $45.21 | $5,335.00 |
| | | | EA | 2 | 11 | 210.00 | $61.98 | $13,015.00 |
| | | | EA | 3 | 10 | 310.00 | $54.42 | $16,870.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **820112** | MARKER (CULVERT) | EA | 5 | 1 | 1.00 | $48.00 | $48.00 |
| | | EA | 9 | 5 | 220.00 | $45.15 | $9,932.00 |
| | **Unit Sub Total** | **EA** | | **35** | **859.00** | **$52.62** | **$45,200.00** |
| | **Item Code 820112 Total No. of Proj.** | | | **35** | | **Total Amount** | **$45,200.00** |
| **820114** | KILOMETER POST MARKER | EA | 3 | 1 | 1.00 | $50.00 | $50.00 |
| | | EA | 11 | 1 | 8.00 | $85.00 | $680.00 |
| | **Unit Sub Total** | **EA** | | **2** | **9.00** | **$81.11** | **$730.00** |
| | **Item Code 820114 Total No. of Proj.** | | | **2** | | **Total Amount** | **$730.00** |
| **820115** | SNOW POLE MARKER | EA | 3 | 1 | 4.00 | $90.00 | $360.00 |
| | | EA | 9 | 1 | 41.00 | $71.00 | $2,911.00 |
| | **Unit Sub Total** | **EA** | | **2** | **45.00** | **$72.69** | **$3,271.00** |
| | **Item Code 820115 Total No. of Proj.** | | | **2** | | **Total Amount** | **$3,271.00** |
| **820118** | GUARD RAILING DELINEATOR | EA | 1 | 5 | 225.00 | $12.72 | $2,862.00 |
| | | EA | 4 | 8 | 1,170.00 | $14.15 | $16,552.00 |
| | | EA | 5 | 12 | 648.00 | $15.71 | $10,179.00 |
| | | EA | 7 | 7 | 3,039.00 | $26.31 | $79,946.00 |
| | | EA | 8 | 1 | 12.00 | $15.00 | $180.00 |
| | | EA | 10 | 3 | 135.00 | $30.59 | $4,129.00 |
| | | EA | 11 | 15 | 1,122.00 | $20.64 | $23,154.00 |
| | | EA | 12 | 3 | 554.00 | $21.68 | $12,010.00 |
| | **Unit Sub Total** | **EA** | | **54** | **6,905.00** | **$21.58** | **$149,012.00** |
| | **Item Code 820118 Total No. of Proj.** | | | **54** | | **Total Amount** | **$149,012.00** |
| **820130** | OBJECT MARKER | EA | 1 | 2 | 3.00 | $40.00 | $120.00 |
| | | EA | 4 | 2 | 17.00 | $41.18 | $700.00 |
| | | EA | 5 | 4 | 255.00 | $47.79 | $12,186.00 |
| | | EA | 6 | 2 | 8.00 | $19.38 | $155.00 |
| | | EA | 7 | 1 | 1.00 | $100.00 | $100.00 |
| | | EA | 8 | 1 | 4.00 | $100.00 | $400.00 |
| | | EA | 9 | 2 | 49.00 | $51.41 | $2,519.00 |
| | | EA | 11 | 1 | 10.00 | $75.00 | $750.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **15** | **347.00** | **$48.79** | **$16,930.00** |
| | **Item Code 820130** | **Total No. of Proj.** | | | **15** | | **Total Amount** | **$16,930.00** |
| **820131** | OBJECT MARKER (TYPE K) | | EA | 6 | 2 | 46.00 | $36.52 | $1,680.00 |
| | | | EA | 10 | 1 | 3.00 | $50.00 | $150.00 |
| | | | EA | 12 | 1 | 1.00 | $100.00 | $100.00 |
| | | **Unit Sub Total** | **EA** | | **4** | **50.00** | **$38.60** | **$1,930.00** |
| | **Item Code 820131** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$1,930.00** |
| **820132** | OBJECT MARKER (TYPE L) | | EA | 5 | 10 | 116.00 | $44.71 | $5,186.00 |
| | | | EA | 6 | 1 | 2.00 | $125.00 | $250.00 |
| | | | EA | 10 | 2 | 4.00 | $125.00 | $500.00 |
| | | **Unit Sub Total** | **EA** | | **13** | **122.00** | **$48.66** | **$5,936.00** |
| | **Item Code 820132** | **Total No. of Proj.** | | | **13** | | **Total Amount** | **$5,936.00** |
| **820133** | OBJECT MARKER (TYPE N) | | EA | 5 | 1 | 2.00 | $23.00 | $46.00 |
| | | | EA | 12 | 1 | 13.00 | $69.08 | $898.04 |
| | | **Unit Sub Total** | **EA** | | **2** | **15.00** | **$62.94** | **$944.04** |
| | **Item Code 820133** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$944.04** |
| **820134** | OBJECT MARKER (TYPE P) | | EA | 2 | 3 | 11.00 | $65.91 | $725.00 |
| | | | EA | 3 | 2 | 32.00 | $50.00 | $1,600.00 |
| | | | EA | 4 | 2 | 36.00 | $75.56 | $2,720.00 |
| | | | EA | 5 | 6 | 31.00 | $98.91 | $3,066.19 |
| | | | EA | 6 | 1 | 8.00 | $55.00 | $440.00 |
| | | | EA | 8 | 1 | 13.00 | $175.00 | $2,275.00 |
| | | | EA | 10 | 1 | 8.00 | $40.80 | $326.40 |
| | | **Unit Sub Total** | **EA** | | **16** | **139.00** | **$80.23** | **$11,152.59** |
| | **Item Code 820134** | **Total No. of Proj.** | | | **16** | | **Total Amount** | **$11,152.59** |
| **820135** | OBJECT MARKER (TYPE R) | | EA | 4 | 1 | 2.00 | $90.00 | $180.00 |
| | | | EA | 5 | 3 | 11.00 | $91.75 | $1,009.28 |
| | | **Unit Sub Total** | **EA** | | **4** | **13.00** | **$91.48** | **$1,189.28** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 820135 Total No. of Proj.** | | | **4** | | **Total Amount** | **$1,189.28** |
| **820141** | OBJECT MARKER (TYPE K-1) | EA | 1 | 1 | 1.00 | $30.00 | $30.00 |
| | | EA | 3 | 2 | 29.00 | $45.86 | $1,330.00 |
| | | EA | 4 | 1 | 2.00 | $97.00 | $194.00 |
| | | EA | 8 | 2 | 243.00 | $31.48 | $7,650.00 |
| | | EA | 10 | 4 | 11.00 | $44.09 | $485.00 |
| | | EA | 12 | 2 | 3.00 | $66.67 | $200.00 |
| | **Unit Sub Total** | **EA** | | **12** | **289.00** | **$34.22** | **$9,889.00** |
| | **Item Code 820141 Total No. of Proj.** | | | **12** | | **Total Amount** | **$9,889.00** |
| **820151** | OBJECT MARKER (TYPE L-1) | EA | 1 | 4 | 42.00 | $42.38 | $1,780.00 |
| | | EA | 2 | 5 | 43.00 | $56.16 | $2,415.00 |
| | | EA | 3 | 16 | 256.00 | $44.75 | $11,455.00 |
| | | EA | 4 | 9 | 356.00 | $39.72 | $14,141.30 |
| | | EA | 5 | 4 | 88.00 | $42.73 | $3,760.00 |
| | | EA | 6 | 2 | 18.00 | $49.61 | $893.00 |
| | | EA | 7 | 1 | 4.00 | $125.00 | $500.00 |
| | | EA | 8 | 2 | 51.00 | $89.47 | $4,563.00 |
| | | EA | 10 | 1 | 2.00 | $35.00 | $70.00 |
| | **Unit Sub Total** | **EA** | | **44** | **860.00** | **$46.02** | **$39,577.30** |
| | **Item Code 820151 Total No. of Proj.** | | | **44** | | **Total Amount** | **$39,577.30** |
| **820152** | OBJECT MARKER (TYPE L-2) | EA | 6 | 1 | 130.00 | $37.00 | $4,810.00 |
| | **Unit Sub Total** | **EA** | | **1** | **130.00** | **$37.00** | **$4,810.00** |
| | **Item Code 820152 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,810.00** |
| **820180** | INSTALL MEDIAN MILEAGE PANEL | EA | 7 | 1 | 9.00 | $250.00 | $2,250.00 |
| | **Unit Sub Total** | **EA** | | **1** | **9.00** | **$250.00** | **$2,250.00** |
| | **Item Code 820180 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,250.00** |
| **832001** | METAL BEAM GUARD RAILING | LF | 1 | 2 | 20,090.00 | $23.53 | $472,750.00 |
| | | LF | 2 | 2 | 1,150.00 | $28.37 | $32,620.00 |
| | | LF | 3 | 5 | 35,826.00 | $32.78 | $1,174,316.00 |
| | | LF | 4 | 4 | 555.00 | $117.16 | $65,025.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **832001** | METAL BEAM GUARD RAILING | LF | 7 | 1 | 75.00 | $27.00 | $2,025.00 |
| | | LF | 9 | 1 | 610.00 | $30.00 | $18,300.00 |
| | | LF | 11 | 6 | 3,862.00 | $33.12 | $127,910.00 |
| | | LF | 12 | 1 | 3,970.00 | $26.00 | $103,220.00 |
| | **Unit Sub Total** | **LF** | | **22** | **66,138.00** | **$30.18** | **$1,996,166.00** |
| **832001** | METAL BEAM GUARD RAILING | M | 1 | 5 | 614.00 | $90.98 | $55,862.00 |
| | | M | 2 | 2 | 80.00 | $87.20 | $6,976.00 |
| | | M | 4 | 1 | 70.00 | $75.00 | $5,250.00 |
| | | M | 7 | 4 | 2,110.00 | $99.04 | $208,980.00 |
| | | M | 11 | 11 | 5,341.00 | $82.29 | $439,487.50 |
| | **Unit Sub Total** | **M** | | **23** | **8,215.00** | **$87.23** | **$716,555.50** |
| | **Item Code 832001 Total No. of Proj.** | | | **45** | | **Total Amount** | **$2,712,721.50** |
| **832002** | METAL BEAM GUARD RAILING (STEEL POST) | LF | 2 | 1 | 250.00 | $40.00 | $10,000.00 |
| | | LF | 3 | 4 | 13,280.00 | $31.46 | $417,775.00 |
| | | LF | 4 | 2 | 2,820.00 | $19.74 | $55,660.00 |
| | | LF | 5 | 7 | 49,920.00 | $22.88 | $1,141,956.00 |
| | | LF | 6 | 4 | 2,950.00 | $34.80 | $102,660.00 |
| | | LF | 8 | 1 | 740.00 | $30.00 | $22,200.00 |
| | | LF | 10 | 1 | 50.00 | $53.00 | $2,650.00 |
| | | LF | 11 | 3 | 640.00 | $36.53 | $23,376.50 |
| | **Unit Sub Total** | **LF** | | **23** | **70,650.00** | **$25.14** | **$1,776,277.50** |
| **832002** | METAL BEAM GUARD RAILING (STEEL POST) | M | 5 | 11 | 11,023.00 | $80.82 | $890,912.50 |
| | | M | 6 | 2 | 330.00 | $93.36 | $30,810.00 |
| | | M | 7 | 3 | 189.00 | $249.21 | $47,100.00 |
| | | M | 9 | 1 | 290.00 | $112.00 | $32,480.00 |
| | | M | 10 | 2 | 1,623.00 | $72.98 | $118,440.00 |
| | **Unit Sub Total** | **M** | | **19** | **13,455.00** | **$83.22** | **$1,119,742.50** |
| | **Item Code 832002 Total No. of Proj.** | | | **42** | | **Total Amount** | **$2,896,020.00** |
| **832003** | METAL BEAM GUARD RAILING (WOOD POST) | LF | 2 | 4 | 4,960.00 | $30.48 | $151,166.00 |
| | | LF | 3 | 7 | 1,538.00 | $40.15 | $61,758.00 |
| | | LF | 4 | 4 | 59,030.00 | $19.63 | $1,158,790.00 |
| | | LF | 5 | 1 | 280.00 | $29.00 | $8,120.00 |
| | | LF | 6 | 1 | 68.00 | $80.00 | $5,440.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **832003** | METAL BEAM GUARD RAILING (WOOD POST) | LF | 7 | 4 | 20,558.00 | $28.95 | $595,180.00 |
| | | LF | 8 | 1 | 190.00 | $32.00 | $6,080.00 |
| | | LF | 12 | 5 | 5,360.00 | $23.11 | $123,850.00 |
| | **Unit Sub Total** | **LF** | | **27** | **91,984.00** | **$22.94** | **$2,110,384.00** |
| **832003** | METAL BEAM GUARD RAILING (WOOD POST) | M | 1 | 1 | 600.00 | $110.00 | $66,000.00 |
| | | M | 2 | 2 | 1,360.00 | $93.97 | $127,800.00 |
| | | M | 3 | 5 | 3,769.00 | $85.22 | $321,210.00 |
| | | M | 4 | 10 | 5,775.00 | $96.43 | $556,865.00 |
| | | M | 5 | 1 | 130.00 | $123.00 | $15,990.00 |
| | | M | 7 | 7 | 9,200.00 | $78.00 | $717,599.70 |
| | | M | 8 | 2 | 6,730.00 | $66.08 | $444,700.00 |
| | | M | 10 | 1 | 550.00 | $69.40 | $38,170.00 |
| | | M | 12 | 1 | 220.00 | $90.00 | $19,800.00 |
| | **Unit Sub Total** | **M** | | **30** | **28,334.00** | **$81.46** | **$2,308,134.70** |
| | **Item Code 832003 Total No. of Proj.** | | | **57** | | **Total Amount** | **$4,418,518.70** |
| **832004** | METAL BEAM GUARD RAILING (SPECIAL) | LF | 2 | 1 | 204.00 | $75.00 | $15,300.00 |
| | **Unit Sub Total** | **LF** | | **1** | **204.00** | **$75.00** | **$15,300.00** |
| | **Item Code 832004 Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,300.00** |
| **832008** | METAL BEAM GUARD RAILING (ELEMENT) | LF | 3 | 1 | 410.00 | $20.00 | $8,200.00 |
| | **Unit Sub Total** | **LF** | | **1** | **410.00** | **$20.00** | **$8,200.00** |
| | **Item Code 832008 Total No. of Proj.** | | | **1** | | **Total Amount** | **$8,200.00** |
| **832012** | METAL BEAM GUARD RAILING (7' WOOD POST) | LF | 1 | 1 | 2,180.00 | $28.00 | $61,040.00 |
| | | LF | 3 | 3 | 35,718.00 | $26.91 | $961,320.00 |
| | | LF | 7 | 1 | 1,420.00 | $38.00 | $53,960.00 |
| | **Unit Sub Total** | **LF** | | **5** | **39,318.00** | **$27.37** | **$1,076,320.00** |
| | **Item Code 832012 Total No. of Proj.** | | | **5** | | **Total Amount** | **$1,076,320.00** |
| **832013** | METAL BEAM GUARD RAILING (7' POST) | LF | 7 | 1 | 420.00 | $36.00 | $15,120.00 |
| | **Unit Sub Total** | **LF** | | **1** | **420.00** | **$36.00** | **$15,120.00** |
| | **Item Code 832013 Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,120.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **832014** | METAL BEAM GUARD RAILING (8' POST) | LF | 7 | 1 | 650.00 | $31.00 | $20,150.00 |
| | **Unit Sub Total** | **LF** | | **1** | **650.00** | **$31.00** | **$20,150.00** |
| | **Item Code 832014 Total No. of Proj.** | | | **1** | | **Total Amount** | **$20,150.00** |
| **832061** | METAL BEAM GUARD RAILING (2.1 M WOOD POST) | M | 3 | 2 | 226.00 | $108.41 | $24,500.00 |
| | | M | 4 | 1 | 150.00 | $80.00 | $12,000.00 |
| | | M | 7 | 1 | 290.00 | $105.00 | $30,450.00 |
| | | M | 8 | 1 | 46.00 | $118.00 | $5,428.00 |
| | **Unit Sub Total** | **M** | | **5** | **712.00** | **$101.65** | **$72,378.00** |
| | **Item Code 832061 Total No. of Proj.** | | | **5** | | **Total Amount** | **$72,378.00** |
| **832062** | METAL BEAM GUARD RAILING (2.1 M POST) | M | 5 | 3 | 3,380.00 | $79.24 | $267,846.00 |
| | | M | 9 | 1 | 120.00 | $120.00 | $14,400.00 |
| | **Unit Sub Total** | **M** | | **4** | **3,500.00** | **$80.64** | **$282,246.00** |
| | **Item Code 832062 Total No. of Proj.** | | | **4** | | **Total Amount** | **$282,246.00** |
| **832063** | METAL BEAM GUARD RAILING (2.4 M POST) | M | 5 | 2 | 840.00 | $124.27 | $104,390.00 |
| | **Unit Sub Total** | **M** | | **2** | **840.00** | **$124.27** | **$104,390.00** |
| | **Item Code 832063 Total No. of Proj.** | | | **2** | | **Total Amount** | **$104,390.00** |
| **832070** | VEGETATION CONTROL (MINOR CONCRETE) | M2 | 1 | 1 | 500.00 | $85.00 | $42,500.00 |
| | | M2 | 2 | 2 | 2,310.00 | $137.23 | $317,000.00 |
| | | M2 | 3 | 2 | 2,040.00 | $71.45 | $145,760.00 |
| | | M2 | 5 | 1 | 3,230.00 | $50.00 | $161,500.00 |
| | | M2 | 7 | 1 | 26.00 | $200.00 | $5,200.00 |
| | | M2 | 12 | 1 | 230.00 | $1.00 | $230.00 |
| | **Unit Sub Total** | **M2** | | **8** | **8,336.00** | **$80.64** | **$672,190.00** |
| **832070** | VEGETATION CONTROL (MINOR CONCRETE) | SQFT | 3 | 1 | 1,590.00 | $5.50 | $8,745.00 |
| | **Unit Sub Total** | **SQFT** | | **1** | **1,590.00** | **$5.50** | **$8,745.00** |
| **832070** | VEGETATION CONTROL (MINOR CONCRETE) | SQYD | 2 | 4 | 1,180.00 | $46.92 | $55,360.00 |
| | | SQYD | 3 | 1 | 360.00 | $75.00 | $27,000.00 |
| | | SQYD | 4 | 1 | 30,800.00 | $39.00 | $1,201,200.00 |
| | | SQYD | 5 | 1 | 590.00 | $73.00 | $43,070.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **832070** | VEGETATION CONTROL (MINOR CONCRETE) | SQYD | 7 | 3 | 3,080.00 | $49.69 | $153,040.00 |
| | | SQYD | 11 | 2 | 650.00 | $121.08 | $78,700.00 |
| | | SQYD | 12 | 2 | 3,650.00 | $20.89 | $76,250.00 |
| | **Unit Sub Total** | **SQYD** | | **14** | **40,310.00** | **$40.55** | **$1,634,620.00** |
| | **Item Code 832070 Total No. of Proj.** | | | **23** | | **Total Amount** | **$2,315,555.00** |
| **833000** | METAL RAILING | M | 1 | 1 | 241.00 | $550.00 | $132,550.00 |
| | **Unit Sub Total** | **M** | | **1** | **241.00** | **$550.00** | **$132,550.00** |
| | **Item Code 833000 Total No. of Proj.** | | | **1** | | **Total Amount** | **$132,550.00** |
| **833020** | CHAIN LINK RAILING | M | 4 | 1 | 16.00 | $400.00 | $6,400.00 |
| | | M | 7 | 1 | 92.00 | $140.00 | $12,880.00 |
| | **Unit Sub Total** | **M** | | **2** | **108.00** | **$178.52** | **$19,280.00** |
| | **Item Code 833020 Total No. of Proj.** | | | **2** | | **Total Amount** | **$19,280.00** |
| **833023** | CHAIN LINK RAILING (TYPE 3L) | M | 1 | 1 | 63.00 | $150.00 | $9,450.00 |
| | **Unit Sub Total** | **M** | | **1** | **63.00** | **$150.00** | **$9,450.00** |
| | **Item Code 833023 Total No. of Proj.** | | | **1** | | **Total Amount** | **$9,450.00** |
| **833031** | CHAIN LINK RAILING (TYPE 6) | M | 3 | 1 | 365.00 | $250.00 | $91,250.00 |
| | **Unit Sub Total** | **M** | | **1** | **365.00** | **$250.00** | **$91,250.00** |
| | **Item Code 833031 Total No. of Proj.** | | | **1** | | **Total Amount** | **$91,250.00** |
| **833032** | CHAIN LINK RAILING (TYPE 7) | LF | 3 | 1 | 205.00 | $92.00 | $18,860.00 |
| | | LF | 4 | 1 | 662.00 | $65.00 | $43,030.00 |
| | | LF | 6 | 1 | 637.00 | $50.00 | $31,850.00 |
| | | LF | 12 | 1 | 258.00 | $65.00 | $16,770.00 |
| | **Unit Sub Total** | **LF** | | **4** | **1,762.00** | **$62.72** | **$110,510.00** |
| **833032** | CHAIN LINK RAILING (TYPE 7) | M | 1 | 1 | 63.00 | $275.00 | $17,325.00 |
| | | M | 4 | 1 | 129.00 | $165.00 | $21,285.00 |
| | | M | 7 | 4 | 484.00 | $251.45 | $121,700.40 |
| | | M | 10 | 1 | 317.00 | $60.00 | $19,020.00 |
| | | M | 11 | 3 | 635.00 | $231.83 | $147,210.00 |
| | **Unit Sub Total** | **M** | | **10** | **1,628.00** | **$200.58** | **$326,540.40** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 833032 Total No. of Proj.** | | | **14** | | **Total Amount** | **$437,050.40** |
| **833033** | CHAIN LINK RAILING (TYPE 7 MODIFIED) | M | 11 | 2 | 636.00 | $193.02 | $122,760.00 |
| | **Unit Sub Total** | **M** | | **2** | **636.00** | **$193.02** | **$122,760.00** |
| | **Item Code 833033 Total No. of Proj.** | | | **2** | | **Total Amount** | **$122,760.00** |
| **833034** | CHAIN LINK RAILING (TYPE 7L) | M | 10 | 1 | 125.00 | $265.20 | $33,150.00 |
| | **Unit Sub Total** | **M** | | **1** | **125.00** | **$265.20** | **$33,150.00** |
| | **Item Code 833034 Total No. of Proj.** | | | **1** | | **Total Amount** | **$33,150.00** |
| **833073** | WILDLIFE PASSAGE WAY (TYPE M) | EA | 4 | 1 | 8.00 | $300.00 | $2,400.00 |
| | **Unit Sub Total** | **EA** | | **1** | **8.00** | **$300.00** | **$2,400.00** |
| | **Item Code 833073 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,400.00** |
| **833077** | PEDESTRIAN BARRICADE | EA | 4 | 1 | 1.00 | $400.00 | $400.00 |
| | | EA | 12 | 1 | 2.00 | $450.00 | $900.00 |
| | **Unit Sub Total** | **EA** | | **2** | **3.00** | **$433.33** | **$1,300.00** |
| | **Item Code 833077 Total No. of Proj.** | | | **2** | | **Total Amount** | **$1,300.00** |
| **833080** | CONCRETE BARRIER (TYPE K) | LF | 3 | 2 | 2,610.00 | $32.31 | $84,317.00 |
| | | LF | 5 | 1 | 1,600.00 | $20.00 | $32,000.00 |
| | | LF | 11 | 1 | 48,100.00 | $41.00 | $1,972,100.00 |
| | **Unit Sub Total** | **LF** | | **4** | **52,310.00** | **$39.92** | **$2,088,417.00** |
| **833080** | CONCRETE BARRIER (TYPE K) | M | 4 | 1 | 190.00 | $110.00 | $20,900.00 |
| | | M | 10 | 1 | 450.00 | $40.00 | $18,000.00 |
| | | M | 11 | 5 | 5,810.00 | $99.54 | $578,300.00 |
| | **Unit Sub Total** | **M** | | **7** | **6,450.00** | **$95.69** | **$617,200.00** |
| | **Item Code 833080 Total No. of Proj.** | | | **11** | | **Total Amount** | **$2,705,617.00** |
| **833088** | TUBULAR HANDRAILING | LF | 8 | 1 | 618.00 | $150.00 | $92,700.00 |
| | **Unit Sub Total** | **LF** | | **1** | **618.00** | **$150.00** | **$92,700.00** |
| **833088** | TUBULAR HANDRAILING | M | 7 | 3 | 210.00 | $435.86 | $91,530.00 |
| | | M | 9 | 2 | 115.00 | $203.26 | $23,375.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **M** | | **5** | **325.00** | **$353.55** | **$114,905.00** |
| | **Item Code 833088 Total No. of Proj.** | | | **6** | | **Total Amount** | **$207,605.00** |
| **833090** | TUBULAR HANDRAILING (MODIFIED) | LF | 7 | 1 | 403.00 | $57.00 | $22,971.00 |
| | **Unit Sub Total** | **LF** | | **1** | **403.00** | **$57.00** | **$22,971.00** |
| **833090** | TUBULAR HANDRAILING (MODIFIED) | M | 5 | 1 | 96.00 | $288.00 | $27,648.00 |
| | **Unit Sub Total** | **M** | | **1** | **96.00** | **$288.00** | **$27,648.00** |
| | **Item Code 833090 Total No. of Proj.** | | | **2** | | **Total Amount** | **$50,619.00** |
| **833125** | CONCRETE BARRIER (TYPE 25) | LF | 4 | 1 | 331.00 | $60.00 | $19,860.00 |
| | **Unit Sub Total** | **LF** | | **1** | **331.00** | **$60.00** | **$19,860.00** |
| **833125** | CONCRETE BARRIER (TYPE 25) | M | 3 | 1 | 63.00 | $350.00 | $22,050.00 |
| | **Unit Sub Total** | **M** | | **1** | **63.00** | **$350.00** | **$22,050.00** |
| | **Item Code 833125 Total No. of Proj.** | | | **2** | | **Total Amount** | **$41,910.00** |
| **833126** | CONCRETE BARRIER (TYPE 25A) | LF | 7 | 1 | 235.00 | $140.00 | $32,900.00 |
| | **Unit Sub Total** | **LF** | | **1** | **235.00** | **$140.00** | **$32,900.00** |
| | **Item Code 833126 Total No. of Proj.** | | | **1** | | **Total Amount** | **$32,900.00** |
| **833128** | CONCRETE BARRIER (TYPE 25 MODIFIED) | LF | 2 | 1 | 89.00 | $456.00 | $40,584.00 |
| | | LF | 3 | 1 | 1.50 | $5,000.00 | $7,500.00 |
| | **Unit Sub Total** | **LF** | | **2** | **90.50** | **$531.31** | **$48,084.00** |
| | **Item Code 833128 Total No. of Proj.** | | | **2** | | **Total Amount** | **$48,084.00** |
| **833140** | CONCRETE BARRIER (TYPE 26) | LF | 4 | 1 | 331.00 | $90.00 | $29,790.00 |
| | **Unit Sub Total** | **LF** | | **1** | **331.00** | **$90.00** | **$29,790.00** |
| | **Item Code 833140 Total No. of Proj.** | | | **1** | | **Total Amount** | **$29,790.00** |
| **833142** | CONCRETE BARRIER (TYPE 26 MODIFIED) | LF | 3 | 1 | 205.00 | $245.00 | $50,225.00 |
| | **Unit Sub Total** | **LF** | | **1** | **205.00** | **$245.00** | **$50,225.00** |
| **833142** | CONCRETE BARRIER (TYPE 26 MODIFIED) | M | 1 | 1 | 63.00 | $600.00 | $37,800.00 |
| | | M | 2 | 1 | 65.00 | $330.00 | $21,450.00 |
| | | M | 3 | 1 | 180.00 | $425.00 | $76,500.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **833142** | CONCRETE BARRIER (TYPE 26 MODIFIED) | M | 5 | 1 | 96.00 | $644.00 | $61,824.00 |
| | | M | 7 | 2 | 123.00 | $598.15 | $73,572.00 |
| | | M | 10 | 1 | 243.00 | $140.00 | $34,020.00 |
| | | M | 11 | 3 | 595.00 | $535.62 | $318,695.00 |
| | **Unit Sub Total** | **M** | | **10** | **1,365.00** | **$457.04** | **$623,861.00** |
| | **Item Code 833142 Total No. of Proj.** | | | **11** | | **Total Amount** | **$674,086.00** |
| **833148** | CONCRETE BARRIER (TYPE 26R MODIFIED) | M | 7 | 1 | 228.00 | $425.00 | $96,900.00 |
| | **Unit Sub Total** | **M** | | **1** | **228.00** | **$425.00** | **$96,900.00** |
| | **Item Code 833148 Total No. of Proj.** | | | **1** | | **Total Amount** | **$96,900.00** |
| **833165** | CONCRETE BARRIER (TYPE 27B MODIFIED) | M | 7 | 2 | 62.00 | $1,013.16 | $62,816.00 |
| | **Unit Sub Total** | **M** | | **2** | **62.00** | **$1,013.16** | **$62,816.00** |
| | **Item Code 833165 Total No. of Proj.** | | | **2** | | **Total Amount** | **$62,816.00** |
| **833187** | CONCRETE BARRIER (TYPE 27 MODIFIED) | M | 4 | 1 | 129.00 | $250.00 | $32,250.00 |
| | **Unit Sub Total** | **M** | | **1** | **129.00** | **$250.00** | **$32,250.00** |
| | **Item Code 833187 Total No. of Proj.** | | | **1** | | **Total Amount** | **$32,250.00** |
| **833190** | CONCRETE BARRIER (TYPE 28) | M | 7 | 1 | 704.00 | $220.00 | $154,880.00 |
| | **Unit Sub Total** | **M** | | **1** | **704.00** | **$220.00** | **$154,880.00** |
| | **Item Code 833190 Total No. of Proj.** | | | **1** | | **Total Amount** | **$154,880.00** |
| **839201** | DOUBLE METAL BEAM BARRIER | LF | 5 | 1 | 220.00 | $38.00 | $8,360.00 |
| | **Unit Sub Total** | **LF** | | **1** | **220.00** | **$38.00** | **$8,360.00** |
| **839201** | DOUBLE METAL BEAM BARRIER | M | 2 | 1 | 49.00 | $125.00 | $6,125.00 |
| | **Unit Sub Total** | **M** | | **1** | **49.00** | **$125.00** | **$6,125.00** |
| | **Item Code 839201 Total No. of Proj.** | | | **2** | | **Total Amount** | **$14,485.00** |
| **839220** | DOUBLE METAL BEAM GUARD RAILING (WOOD POST) | LF | 1 | 1 | 320.00 | $45.00 | $14,400.00 |
| | | LF | 3 | 1 | 75.00 | $64.40 | $4,830.00 |
| | | LF | 7 | 1 | 50.00 | $39.00 | $1,950.00 |
| | **Unit Sub Total** | **LF** | | **3** | **445.00** | **$47.60** | **$21,180.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **839220** | DOUBLE METAL BEAM GUARD RAILING (WOOD POST) | M | 3 | 1 | 630.00 | $100.00 | $63,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **630.00** | **$100.00** | **$63,000.00** |
| | **Item Code 839220 Total No. of Proj.** | | | **4** | | **Total Amount** | **$84,180.00** |
| **839301** | SINGLE THRIE BEAM BARRIER | LF | 3 | 1 | 6,700.00 | $26.50 | $177,550.00 |
| | | LF | 7 | 1 | 1,330.00 | $31.00 | $41,230.00 |
| | | LF | 11 | 1 | 1,300.00 | $56.00 | $72,800.00 |
| | **Unit Sub Total** | **LF** | | **3** | **9,330.00** | **$31.25** | **$291,580.00** |
| **839301** | SINGLE THRIE BEAM BARRIER | M | 4 | 1 | 170.00 | $100.00 | $17,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **170.00** | **$100.00** | **$17,000.00** |
| | **Item Code 839301 Total No. of Proj.** | | | **4** | | **Total Amount** | **$308,580.00** |
| **839302** | SINGLE THRIE BEAM BARRIER (WOOD POST) | LF | 3 | 1 | 300.00 | $40.00 | $12,000.00 |
| | | LF | 7 | 1 | 2,130.00 | $26.00 | $55,380.00 |
| | **Unit Sub Total** | **LF** | | **2** | **2,430.00** | **$27.73** | **$67,380.00** |
| **839302** | SINGLE THRIE BEAM BARRIER (WOOD POST) | M | 3 | 1 | 8.00 | $112.00 | $896.00 |
| | | M | 4 | 1 | 260.00 | $108.15 | $28,119.00 |
| | | M | 8 | 2 | 222.00 | $108.49 | $24,084.00 |
| | | M | 11 | 1 | 1,010.00 | $105.00 | $106,050.00 |
| | **Unit Sub Total** | **M** | | **5** | **1,500.00** | **$106.10** | **$159,149.00** |
| | **Item Code 839302 Total No. of Proj.** | | | **7** | | **Total Amount** | **$226,529.00** |
| **839303** | SINGLE THRIE BEAM BARRIER (STEEL POST) | LF | 4 | 1 | 220.00 | $37.00 | $8,140.00 |
| | | LF | 5 | 1 | 1,540.00 | $30.69 | $47,262.60 |
| | | LF | 8 | 1 | 3,630.00 | $22.00 | $79,860.00 |
| | **Unit Sub Total** | **LF** | | **3** | **5,390.00** | **$25.10** | **$135,262.60** |
| **839303** | SINGLE THRIE BEAM BARRIER (STEEL POST) | M | 5 | 3 | 2,869.00 | $99.66 | $285,926.00 |
| | **Unit Sub Total** | **M** | | **3** | **2,869.00** | **$99.66** | **$285,926.00** |
| | **Item Code 839303 Total No. of Proj.** | | | **6** | | **Total Amount** | **$421,188.60** |
| **839310** | DOUBLE THRIE BEAM BARRIER | LF | 3 | 1 | 160.00 | $40.00 | $6,400.00 |
| | | LF | 11 | 1 | 1,880.00 | $67.00 | $125,960.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **LF** | | **2** | **2,040.00** | **$64.88** | **$132,360.00** |
| **839310** | DOUBLE THRIE BEAM BARRIER | | M | 4 | 1 | 710.00 | $190.00 | $134,900.00 |
| | | | M | 11 | 1 | 120.00 | $200.00 | $24,000.00 |
| | | **Unit Sub Total** | **M** | | **2** | **830.00** | **$191.45** | **$158,900.00** |
| | **Item Code 839310** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$291,260.00** |
| **839311** | DOUBLE THRIE BEAM BARRIER (WOOD POST) | | LF | 4 | 2 | 640.00 | $57.30 | $36,670.00 |
| | | | LF | 7 | 1 | 63.00 | $49.25 | $3,102.75 |
| | | | LF | 11 | 1 | 2,070.00 | $96.00 | $198,720.00 |
| | | | LF | 12 | 1 | 860.00 | $49.00 | $42,140.00 |
| | | **Unit Sub Total** | **LF** | | **5** | **3,633.00** | **$77.25** | **$280,632.75** |
| **839311** | DOUBLE THRIE BEAM BARRIER (WOOD POST) | | M | 1 | 2 | 2,080.00 | $163.32 | $339,700.00 |
| | | | M | 2 | 1 | 820.00 | $126.00 | $103,320.00 |
| | | | M | 3 | 1 | 350.00 | $140.00 | $49,000.00 |
| | | | M | 4 | 1 | 1,630.00 | $169.35 | $276,040.50 |
| | | | M | 8 | 1 | 7,300.00 | $106.00 | $773,800.00 |
| | | | M | 11 | 1 | 2,750.00 | $122.00 | $335,500.00 |
| | | **Unit Sub Total** | **M** | | **7** | **14,930.00** | **$125.74** | **$1,877,360.50** |
| | **Item Code 839311** | **Total No. of Proj.** | | | **12** | | **Total Amount** | **$2,157,993.25** |
| **839312** | DOUBLE THRIE BEAM BARRIER (STEEL POST) | | LF | 4 | 2 | 12,210.00 | $41.75 | $509,820.00 |
| | | | LF | 5 | 3 | 1,940.00 | $53.33 | $103,451.60 |
| | | | LF | 8 | 2 | 21,700.00 | $33.43 | $725,360.00 |
| | | **Unit Sub Total** | **LF** | | **7** | **35,850.00** | **$37.34** | **$1,338,631.60** |
| | **Item Code 839312** | **Total No. of Proj.** | | | **7** | | **Total Amount** | **$1,338,631.60** |
| **839313** | DOUBLE THRIE BEAM BARRIER (BRIDGE) | | LF | 4 | 1 | 25.00 | $265.00 | $6,625.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **25.00** | **$265.00** | **$6,625.00** |
| **839313** | DOUBLE THRIE BEAM BARRIER (BRIDGE) | | M | 1 | 1 | 61.00 | $350.00 | $21,350.00 |
| | | **Unit Sub Total** | **M** | | **1** | **61.00** | **$350.00** | **$21,350.00** |
| | **Item Code 839313** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$27,975.00** |
| **839401** | CONCRETE BARRIER | | LF | 1 | 1 | 27.00 | $725.00 | $19,575.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **839401** | CONCRETE BARRIER | | LF | 11 | 1 | 64.00 | $300.00 | $19,200.00 |
| | | **Unit Sub Total** | **LF** | | **2** | **91.00** | **$426.10** | **$38,775.00** |
| **839401** | CONCRETE BARRIER | | M | 7 | 1 | 44.00 | $240.00 | $10,560.00 |
| | | **Unit Sub Total** | **M** | | **1** | **44.00** | **$240.00** | **$10,560.00** |
| | **Item Code 839401** | **Total No. of Proj.** | | | **3** | | **Total Amount** | **$49,335.00** |
| **839482** | CONCRETE BARRIER (TYPE 50 MODIFIED) | | LF | 5 | 1 | 13.00 | $255.54 | $3,322.02 |
| | | **Unit Sub Total** | **LF** | | **1** | **13.00** | **$255.54** | **$3,322.02** |
| | **Item Code 839482** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,322.02** |
| **839514** | HANDRAILING | | LF | 8 | 1 | 100.00 | $150.00 | $15,000.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **100.00** | **$150.00** | **$15,000.00** |
| | **Item Code 839514** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,000.00** |
| **839521** | CABLE RAILING | | LF | 1 | 2 | 411.00 | $27.55 | $11,325.00 |
| | | | LF | 2 | 4 | 383.00 | $57.99 | $22,210.00 |
| | | | LF | 3 | 1 | 12.00 | $145.00 | $1,740.00 |
| | | | LF | 7 | 1 | 4,050.00 | $19.30 | $78,165.00 |
| | | | LF | 9 | 1 | 87.00 | $49.00 | $4,263.00 |
| | | | LF | 11 | 1 | 41.00 | $96.00 | $3,936.00 |
| | | **Unit Sub Total** | **LF** | | **10** | **4,984.00** | **$24.41** | **$121,639.00** |
| **839521** | CABLE RAILING | | M | 1 | 4 | 392.00 | $76.31 | $29,915.00 |
| | | | M | 2 | 1 | 170.00 | $60.00 | $10,200.00 |
| | | | M | 3 | 4 | 1,187.00 | $51.65 | $61,304.25 |
| | | | M | 4 | 1 | 114.00 | $65.00 | $7,410.00 |
| | | | M | 5 | 4 | 1,516.00 | $48.88 | $74,106.00 |
| | | | M | 7 | 4 | 2,277.00 | $36.51 | $83,143.50 |
| | | | M | 8 | 1 | 144.00 | $40.00 | $5,760.00 |
| | | | M | 9 | 3 | 244.00 | $74.47 | $18,170.00 |
| | | | M | 10 | 3 | 65.40 | $147.86 | $9,670.00 |
| | | | M | 11 | 10 | 2,306.00 | $50.66 | $116,817.00 |
| | | **Unit Sub Total** | **M** | | **35** | **8,415.40** | **$49.49** | **$416,495.75** |
| | **Item Code 839521** | **Total No. of Proj.** | | | **45** | | **Total Amount** | **$538,134.75** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **839522** | REMOVABLE BARRIER POST | | EA | 2 | 1 | 3.00 | $1,000.00 | $3,000.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **3.00** | **$1,000.00** | **$3,000.00** |
| | **Item Code 839522** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,000.00** |
| **839528** | BURIED POST ANCHOR | | EA | 2 | 1 | 1.00 | $3,560.00 | $3,560.00 |
| | | | EA | 7 | 1 | 2.00 | $950.00 | $1,900.00 |
| | | **Unit Sub Total** | **EA** | | **2** | **3.00** | **$1,820.00** | **$5,460.00** |
| | **Item Code 839528** | **Total No. of Proj.** | | | **2** | | **Total Amount** | **$5,460.00** |
| **839540** | TRANSITION RAILING (TYPE STB) | | EA | 3 | 1 | 3.00 | $3,500.00 | $10,500.00 |
| | | | EA | 4 | 2 | 2.00 | $4,750.00 | $9,500.00 |
| | | | EA | 5 | 1 | 1.00 | $3,900.00 | $3,900.00 |
| | | | EA | 11 | 1 | 2.00 | $4,000.00 | $8,000.00 |
| | | **Unit Sub Total** | **EA** | | **5** | **8.00** | **$3,987.50** | **$31,900.00** |
| | **Item Code 839540** | **Total No. of Proj.** | | | **5** | | **Total Amount** | **$31,900.00** |
| **839541** | TRANSITION RAILING (TYPE WB) | | EA | 1 | 7 | 41.00 | $4,043.90 | $165,800.00 |
| | | | EA | 2 | 9 | 122.00 | $4,331.11 | $528,395.00 |
| | | | EA | 3 | 17 | 107.00 | $3,870.56 | $414,150.00 |
| | | | EA | 4 | 12 | 99.00 | $3,474.12 | $343,938.00 |
| | | | EA | 5 | 13 | 98.00 | $2,980.10 | $292,050.00 |
| | | | EA | 6 | 6 | 50.00 | $3,683.20 | $184,160.00 |
| | | | EA | 7 | 15 | 378.00 | $3,618.61 | $1,367,835.60 |
| | | | EA | 8 | 5 | 42.00 | $3,483.33 | $146,300.00 |
| | | | EA | 9 | 2 | 7.00 | $3,542.86 | $24,800.00 |
| | | | EA | 10 | 3 | 11.00 | $3,441.09 | $37,852.00 |
| | | | EA | 11 | 12 | 82.00 | $3,784.15 | $310,300.00 |
| | | | EA | 12 | 2 | 20.00 | $5,017.50 | $100,350.00 |
| | | **Unit Sub Total** | **EA** | | **103** | **1,057.00** | **$3,704.76** | **$3,915,930.60** |
| | **Item Code 839541** | **Total No. of Proj.** | | | **103** | | **Total Amount** | **$3,915,930.60** |
| **839542** | TRANSITION RAILING (TYPE DTB) | | EA | 1 | 2 | 7.00 | $4,142.86 | $29,000.00 |
| | | | EA | 2 | 1 | 2.00 | $3,500.00 | $7,000.00 |
| | | | EA | 4 | 3 | 5.00 | $3,313.60 | $16,568.00 |
| | | | EA | 5 | 1 | 1.00 | $3,706.32 | $3,706.32 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **839542** | TRANSITION RAILING (TYPE DTB) | EA | 8 | 2 | 9.00 | $2,961.11 | $26,650.00 |
| | | EA | 11 | 2 | 112.00 | $4,198.21 | $470,200.00 |
| | **Unit Sub Total** | **EA** | | **11** | **136.00** | **$4,067.09** | **$553,124.32** |
| | **Item Code 839542 Total No. of Proj.** | | | **11** | | **Total Amount** | **$553,124.32** |
| **839552** | TERMINAL SECTION (TYPE C) | EA | 3 | 1 | 5.00 | $150.00 | $750.00 |
| | **Unit Sub Total** | **EA** | | **1** | **5.00** | **$150.00** | **$750.00** |
| | **Item Code 839552 Total No. of Proj.** | | | **1** | | **Total Amount** | **$750.00** |
| **839555** | END CAP | EA | 1 | 1 | 1.00 | $200.00 | $200.00 |
| | | EA | 3 | 1 | 2.00 | $500.00 | $1,000.00 |
| | | EA | 4 | 1 | 4.00 | $200.00 | $800.00 |
| | | EA | 11 | 1 | 2.00 | $297.25 | $594.50 |
| | | EA | 12 | 1 | 3.00 | $106.00 | $318.00 |
| | **Unit Sub Total** | **EA** | | **5** | **12.00** | **$242.71** | **$2,912.50** |
| | **Item Code 839555 Total No. of Proj.** | | | **5** | | **Total Amount** | **$2,912.50** |
| **839559** | TERMINAL SYSTEM (TYPE ET) | EA | 5 | 1 | 2.00 | $4,700.00 | $9,400.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$4,700.00** | **$9,400.00** |
| | **Item Code 839559 Total No. of Proj.** | | | **1** | | **Total Amount** | **$9,400.00** |
| **839561** | RAIL TENSIONING ASSEMBLY | EA | 1 | 2 | 13.00 | $535.77 | $6,965.00 |
| | | EA | 2 | 1 | 24.00 | $200.00 | $4,800.00 |
| | | EA | 6 | 1 | 8.00 | $380.00 | $3,040.00 |
| | | EA | 10 | 1 | 2.00 | $586.50 | $1,173.00 |
| | | EA | 11 | 2 | 12.00 | $554.17 | $6,650.00 |
| | **Unit Sub Total** | **EA** | | **7** | **59.00** | **$383.53** | **$22,628.00** |
| | **Item Code 839561 Total No. of Proj.** | | | **7** | | **Total Amount** | **$22,628.00** |
| **839565** | TERMINAL SYSTEM (TYPE SRT) | EA | 5 | 1 | 4.00 | $3,500.00 | $14,000.00 |
| | | EA | 7 | 1 | 120.00 | $2,570.00 | $308,400.00 |
| | **Unit Sub Total** | **EA** | | **2** | **124.00** | **$2,600.00** | **$322,400.00** |
| | **Item Code 839565 Total No. of Proj.** | | | **2** | | **Total Amount** | **$322,400.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **839566** | TERMINAL SYSTEM (TYPE CAT) | EA | 3 | 1 | 1.00 | $6,100.00 | $6,100.00 |
| | | EA | 5 | 2 | 4.00 | $4,320.00 | $17,280.00 |
| | | EA | 7 | 1 | 10.00 | $4,800.00 | $48,000.00 |
| | | EA | 11 | 1 | 1.00 | $5,800.00 | $5,800.00 |
| | **Unit Sub Total** | **EA** | | **5** | **16.00** | **$4,823.75** | **$77,180.00** |
| | **Item Code 839566 Total No. of Proj.** | | | **5** | | **Total Amount** | **$77,180.00** |
| **839567** | TERMINAL SYSTEM (TYPE CAT) BACKUP | EA | 3 | 1 | 1.00 | $560.00 | $560.00 |
| | | EA | 5 | 2 | 4.00 | $997.50 | $3,990.00 |
| | | EA | 11 | 1 | 1.00 | $800.00 | $800.00 |
| | **Unit Sub Total** | **EA** | | **4** | **6.00** | **$891.67** | **$5,350.00** |
| | **Item Code 839567 Total No. of Proj.** | | | **4** | | **Total Amount** | **$5,350.00** |
| **839568** | TERMINAL ANCHOR ASSEMBLY (TYPE SFT) | EA | 1 | 1 | 2.00 | $600.00 | $1,200.00 |
| | | EA | 3 | 1 | 5.00 | $650.00 | $3,250.00 |
| | | EA | 4 | 1 | 11.00 | $825.00 | $9,075.00 |
| | | EA | 5 | 1 | 8.00 | $1,295.00 | $10,360.00 |
| | | EA | 7 | 3 | 9.00 | $1,402.22 | $12,620.00 |
| | | EA | 8 | 1 | 45.00 | $600.00 | $27,000.00 |
| | | EA | 11 | 2 | 30.00 | $804.17 | $24,125.00 |
| | | EA | 12 | 3 | 7.00 | $734.29 | $5,140.00 |
| | **Unit Sub Total** | **EA** | | **13** | **117.00** | **$792.91** | **$92,770.00** |
| | **Item Code 839568 Total No. of Proj.** | | | **13** | | **Total Amount** | **$92,770.00** |
| **839569** | TERMINAL ANCHOR ASSEMBLY (TYPE CA) | EA | 4 | 1 | 2.00 | $1,100.00 | $2,200.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$1,100.00** | **$2,200.00** |
| | **Item Code 839569 Total No. of Proj.** | | | **1** | | **Total Amount** | **$2,200.00** |
| **839571** | RETURN CAP | EA | 8 | 1 | 6.00 | $250.00 | $1,500.00 |
| | **Unit Sub Total** | **EA** | | **1** | **6.00** | **$250.00** | **$1,500.00** |
| | **Item Code 839571 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,500.00** |
| **839572** | RETURN CAP (TYPE TA) | EA | 1 | 1 | 1.00 | $135.00 | $135.00 |
| | | EA | 3 | 1 | 1.00 | $140.00 | $140.00 |
| | | EA | 4 | 1 | 1.00 | $200.00 | $200.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| **839572** | RETURN CAP (TYPE TA) | | EA | 12 | 1 | 1.00 | $265.00 | $265.00 |
| | | **Unit Sub Total** | **EA** | | **4** | **4.00** | **$185.00** | **$740.00** |
| | **Item Code 839572** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$740.00** |
| **839576** | END CAP (TYPE A) | | EA | 1 | 1 | 1.00 | $135.00 | $135.00 |
| | | | EA | 2 | 1 | 4.00 | $100.00 | $400.00 |
| | | | EA | 3 | 3 | 26.00 | $103.46 | $2,690.00 |
| | | | EA | 4 | 2 | 5.00 | $430.00 | $2,150.00 |
| | | | EA | 5 | 2 | 4.00 | $220.00 | $880.00 |
| | | | EA | 7 | 2 | 40.00 | $172.50 | $6,900.00 |
| | | | EA | 8 | 1 | 12.00 | $360.00 | $4,320.00 |
| | | | EA | 10 | 1 | 1.00 | $500.00 | $500.00 |
| | | | EA | 11 | 1 | 10.00 | $600.00 | $6,000.00 |
| | | **Unit Sub Total** | **EA** | | **14** | **103.00** | **$232.77** | **$23,975.00** |
| | **Item Code 839576** | **Total No. of Proj.** | | | **14** | | **Total Amount** | **$23,975.00** |
| **839577** | END CAP (TYPE TA) | | EA | 1 | 1 | 3.00 | $135.00 | $405.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **3.00** | **$135.00** | **$405.00** |
| | **Item Code 839577** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$405.00** |
| **839578** | END CAP (TYPE TC) | | EA | 1 | 2 | 15.00 | $187.00 | $2,805.00 |
| | | | EA | 2 | 1 | 8.00 | $175.00 | $1,400.00 |
| | | | EA | 3 | 5 | 20.00 | $241.75 | $4,835.00 |
| | | | EA | 4 | 1 | 7.00 | $100.00 | $700.00 |
| | | | EA | 5 | 1 | 10.00 | $350.00 | $3,500.00 |
| | | | EA | 7 | 2 | 44.00 | $415.91 | $18,300.00 |
| | | | EA | 8 | 1 | 1.00 | $100.00 | $100.00 |
| | | **Unit Sub Total** | **EA** | | **13** | **105.00** | **$301.33** | **$31,640.00** |
| | **Item Code 839578** | **Total No. of Proj.** | | | **13** | | **Total Amount** | **$31,640.00** |
| **839581** | END ANCHOR ASSEMBLY (TYPE SFT) | | EA | 1 | 6 | 31.00 | $693.55 | $21,500.00 |
| | | | EA | 2 | 1 | 3.00 | $1,000.00 | $3,000.00 |
| | | | EA | 3 | 18 | 114.00 | $913.11 | $104,095.00 |
| | | | EA | 4 | 15 | 384.00 | $722.19 | $277,322.00 |
| | | | EA | 5 | 14 | 145.00 | $700.20 | $101,528.50 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **839581** | END ANCHOR ASSEMBLY (TYPE SFT) | EA | 6 | 5 | 29.00 | $885.03 | $25,666.00 |
| | | EA | 7 | 11 | 293.00 | $804.78 | $235,799.60 |
| | | EA | 8 | 3 | 14.00 | $867.86 | $12,150.00 |
| | | EA | 9 | 2 | 10.00 | $860.00 | $8,600.00 |
| | | EA | 10 | 3 | 20.00 | $825.23 | $16,504.50 |
| | | EA | 11 | 13 | 50.00 | $763.30 | $38,165.00 |
| | | EA | 12 | 4 | 39.00 | $782.72 | $30,526.00 |
| | **Unit Sub Total** | **EA** | | **95** | **1,132.00** | **$772.84** | **$874,856.60** |
| | **Item Code 839581 Total No. of Proj.** | | | **95** | | **Total Amount** | **$874,856.60** |
| **839582** | END ANCHOR ASSEMBLY (TYPE CA) | EA | 1 | 1 | 1.00 | $1,200.00 | $1,200.00 |
| | | EA | 3 | 1 | 1.00 | $1,350.00 | $1,350.00 |
| | | EA | 4 | 2 | 4.00 | $1,705.00 | $6,820.00 |
| | | EA | 5 | 1 | 1.00 | $1,400.00 | $1,400.00 |
| | | EA | 10 | 1 | 2.00 | $3,060.00 | $6,120.00 |
| | | EA | 11 | 1 | 3.00 | $1,200.00 | $3,600.00 |
| | | EA | 12 | 1 | 1.00 | $915.00 | $915.00 |
| | **Unit Sub Total** | **EA** | | **8** | **13.00** | **$1,646.54** | **$21,405.00** |
| | **Item Code 839582 Total No. of Proj.** | | | **8** | | **Total Amount** | **$21,405.00** |
| **839584** | ALTERNATIVE IN-LINE TERMINAL SYSTEM | EA | 1 | 7 | 28.00 | $3,078.93 | $86,210.00 |
| | | EA | 2 | 6 | 32.00 | $2,493.28 | $79,785.00 |
| | | EA | 3 | 12 | 62.00 | $3,299.19 | $204,550.00 |
| | | EA | 4 | 8 | 103.00 | $2,755.34 | $283,800.00 |
| | | EA | 5 | 10 | 56.00 | $2,909.68 | $162,942.00 |
| | | EA | 6 | 3 | 22.00 | $3,263.64 | $71,800.00 |
| | | EA | 7 | 18 | 220.00 | $3,137.03 | $690,146.90 |
| | | EA | 8 | 3 | 8.00 | $3,687.50 | $29,500.00 |
| | | EA | 9 | 1 | 2.00 | $2,500.00 | $5,000.00 |
| | | EA | 11 | 8 | 23.00 | $3,669.57 | $84,400.00 |
| | | EA | 12 | 3 | 29.00 | $3,279.31 | $95,100.00 |
| | **Unit Sub Total** | **EA** | | **79** | **585.00** | **$3,065.36** | **$1,793,233.90** |
| | **Item Code 839584 Total No. of Proj.** | | | **79** | | **Total Amount** | **$1,793,233.90** |
| **839585** | ALTERNATIVE FLARED TERMINAL SYSTEM | EA | 1 | 9 | 49.00 | $2,495.41 | $122,275.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **839585** | ALTERNATIVE FLARED TERMINAL SYSTEM | EA | 2 | 11 | 51.00 | $2,810.37 | $143,329.00 |
| | | EA | 3 | 16 | 179.00 | $2,422.71 | $433,665.00 |
| | | EA | 4 | 22 | 383.00 | $2,190.46 | $838,947.00 |
| | | EA | 5 | 14 | 155.00 | $2,103.46 | $326,036.33 |
| | | EA | 6 | 7 | 56.00 | $3,307.68 | $185,230.00 |
| | | EA | 7 | 11 | 246.00 | $2,333.25 | $573,979.00 |
| | | EA | 8 | 5 | 70.00 | $2,607.79 | $182,545.00 |
| | | EA | 9 | 3 | 10.00 | $2,720.00 | $27,200.00 |
| | | EA | 10 | 5 | 23.00 | $2,197.09 | $50,533.00 |
| | | EA | 11 | 15 | 112.00 | $2,746.25 | $307,580.00 |
| | | EA | 12 | 8 | 31.00 | $2,487.10 | $77,100.00 |
| | **Unit Sub Total** | **EA** | | **126** | **1,365.00** | **$2,394.45** | **$3,268,419.33** |
| | **Item Code 839585 Total No. of Proj.** | | | **126** | | **Total Amount** | **$3,268,419.33** |
| **839591** | CRASH CUSHION, SAND FILLED | EA | 3 | 2 | 15.00 | $3,986.67 | $59,800.00 |
| | | EA | 4 | 7 | 10.00 | $4,462.70 | $44,627.00 |
| | | EA | 5 | 1 | 1.00 | $6,000.00 | $6,000.00 |
| | | EA | 7 | 2 | 2.00 | $6,700.00 | $13,400.00 |
| | | EA | 10 | 1 | 2.00 | $2,040.00 | $4,080.00 |
| | **Unit Sub Total** | **EA** | | **13** | **30.00** | **$4,263.57** | **$127,907.00** |
| | **Item Code 839591 Total No. of Proj.** | | | **13** | | **Total Amount** | **$127,907.00** |
| **839601** | CRASH CUSHION (TYPE CAT) | EA | 1 | 1 | 8.00 | $7,500.00 | $60,000.00 |
| | | EA | 2 | 2 | 4.00 | $5,832.50 | $23,330.00 |
| | | EA | 4 | 1 | 2.00 | $6,000.00 | $12,000.00 |
| | | EA | 5 | 1 | 7.00 | $5,300.00 | $37,100.00 |
| | | EA | 7 | 4 | 23.00 | $5,760.87 | $132,500.00 |
| | | EA | 8 | 1 | 1.00 | $5,340.00 | $5,340.00 |
| | | EA | 11 | 4 | 15.00 | $5,533.33 | $83,000.00 |
| | | EA | 12 | 1 | 2.00 | $10,400.00 | $20,800.00 |
| | **Unit Sub Total** | **EA** | | **15** | **62.00** | **$6,033.39** | **$374,070.00** |
| | **Item Code 839601 Total No. of Proj.** | | | **15** | | **Total Amount** | **$374,070.00** |
| **839602** | CRASH CUSHION (TYPE CAT) BACKUP | EA | 2 | 1 | 2.00 | $927.00 | $1,854.00 |
| | | EA | 5 | 1 | 4.00 | $550.00 | $2,200.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **839602** | CRASH CUSHION (TYPE CAT) BACKUP | EA | 8 | 1 | 1.00 | $525.00 | $525.00 |
| | | EA | 11 | 3 | 13.00 | $392.31 | $5,100.00 |
| | | EA | 12 | 1 | 2.00 | $1,000.00 | $2,000.00 |
| | **Unit Sub Total** | **EA** | | **7** | **22.00** | **$530.86** | **$11,679.00** |
| | **Item Code 839602 Total No. of Proj.** | | | **7** | | **Total Amount** | **$11,679.00** |
| **839604** | CRASH CUSHION (REACT 9CBB) | EA | 4 | 1 | 3.00 | $50,000.00 | $150,000.00 |
| | | EA | 7 | 3 | 3.00 | $58,600.00 | $175,800.00 |
| | | EA | 11 | 7 | 23.00 | $42,860.87 | $985,800.00 |
| | **Unit Sub Total** | **EA** | | **11** | **29.00** | **$45,227.59** | **$1,311,600.00** |
| | **Item Code 839604 Total No. of Proj.** | | | **11** | | **Total Amount** | **$1,311,600.00** |
| **839605** | CRASH CUSHION (REACT 9SCBS) | EA | 4 | 1 | 1.00 | $60,000.00 | $60,000.00 |
| | | EA | 7 | 1 | 1.00 | $15,000.00 | $15,000.00 |
| | | EA | 11 | 1 | 1.00 | $55,000.00 | $55,000.00 |
| | **Unit Sub Total** | **EA** | | **3** | **3.00** | **$43,333.33** | **$130,000.00** |
| | **Item Code 839605 Total No. of Proj.** | | | **3** | | **Total Amount** | **$130,000.00** |
| **839631** | CRASH CUSHION MODULE, SAND FILLED | EA | 10 | 1 | 28.00 | $100.00 | $2,800.00 |
| | | EA | 11 | 1 | 2.00 | $550.00 | $1,100.00 |
| | **Unit Sub Total** | **EA** | | **2** | **30.00** | **$130.00** | **$3,900.00** |
| | **Item Code 839631 Total No. of Proj.** | | | **2** | | **Total Amount** | **$3,900.00** |
| **839701** | CONCRETE BARRIER (TYPE 60) | LF | 3 | 3 | 65,860.00 | $46.03 | $3,031,500.00 |
| | | LF | 4 | 3 | 7,300.00 | $53.13 | $387,870.00 |
| | | LF | 5 | 3 | 15,020.00 | $43.77 | $657,480.00 |
| | | LF | 7 | 2 | 1,470.00 | $81.05 | $119,150.00 |
| | | LF | 12 | 1 | 660.00 | $60.00 | $39,600.00 |
| | **Unit Sub Total** | **LF** | | **12** | **90,310.00** | **$46.90** | **$4,235,600.00** |
| **839701** | CONCRETE BARRIER (TYPE 60) | M | 1 | 1 | 550.00 | $250.00 | $137,500.00 |
| | | M | 2 | 1 | 2,150.00 | $210.00 | $451,500.00 |
| | | M | 3 | 2 | 3,500.00 | $146.46 | $512,600.00 |
| | | M | 4 | 4 | 9,547.00 | $174.24 | $1,663,505.00 |
| | | M | 5 | 2 | 1,980.00 | $184.32 | $364,950.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **839701** | CONCRETE BARRIER (TYPE 60) | M | 7 | 3 | 785.00 | $193.06 | $151,550.00 |
| | | M | 8 | 2 | 1,860.00 | $116.80 | $217,250.00 |
| | | M | 10 | 1 | 57.00 | $200.00 | $11,400.00 |
| | | M | 11 | 6 | 13,323.00 | $173.40 | $2,310,200.00 |
| | **Unit Sub Total** | **M** | | **22** | **33,752.00** | **$172.45** | **$5,820,455.00** |
| | **Item Code 839701 Total No. of Proj.** | | | **34** | | **Total Amount** | **$10,056,055.00** |
| **839702** | CONCRETE BARRIER (TYPE 60A) | M | 2 | 3 | 920.00 | $146.79 | $135,045.00 |
| | | M | 4 | 1 | 86.00 | $250.00 | $21,500.00 |
| | | M | 7 | 1 | 1,020.00 | $200.00 | $204,000.00 |
| | | M | 11 | 1 | 52.00 | $160.00 | $8,320.00 |
| | **Unit Sub Total** | **M** | | **6** | **2,078.00** | **$177.51** | **$368,865.00** |
| | **Item Code 839702 Total No. of Proj.** | | | **6** | | **Total Amount** | **$368,865.00** |
| **839703** | CONCRETE BARRIER (TYPE 60C) | LF | 3 | 2 | 27,350.00 | $61.57 | $1,683,900.00 |
| | | LF | 4 | 1 | 4,460.00 | $57.00 | $254,220.00 |
| | | LF | 5 | 1 | 4,020.00 | $59.00 | $237,180.00 |
| | | LF | 8 | 1 | 1,280.00 | $70.00 | $89,600.00 |
| | | LF | 11 | 1 | 480.00 | $126.00 | $60,480.00 |
| | **Unit Sub Total** | **LF** | | **6** | **37,590.00** | **$61.86** | **$2,325,380.00** |
| **839703** | CONCRETE BARRIER (TYPE 60C) | M | 2 | 1 | 380.00 | $270.00 | $102,600.00 |
| | | M | 3 | 2 | 1,700.00 | $167.12 | $284,100.00 |
| | | M | 4 | 6 | 34,123.00 | $209.29 | $7,141,450.00 |
| | | M | 5 | 1 | 560.00 | $325.00 | $182,000.00 |
| | | M | 7 | 3 | 1,091.00 | $297.86 | $324,970.00 |
| | | M | 8 | 1 | 2,090.00 | $130.00 | $271,700.00 |
| | | M | 11 | 6 | 1,780.00 | $343.48 | $611,400.00 |
| | **Unit Sub Total** | **M** | | **20** | **41,724.00** | **$213.74** | **$8,918,220.00** |
| | **Item Code 839703 Total No. of Proj.** | | | **26** | | **Total Amount** | **$11,243,600.00** |
| **839704** | CONCRETE BARRIER (TYPE 60D) | M | 2 | 1 | 310.00 | $280.00 | $86,800.00 |
| | | M | 3 | 1 | 1,132.00 | $124.00 | $140,368.00 |
| | | M | 4 | 3 | 1,621.00 | $166.85 | $270,470.00 |
| | | M | 5 | 2 | 873.00 | $151.89 | $132,603.00 |
| | | M | 7 | 1 | 3,100.00 | $142.00 | $440,200.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **839704** | CONCRETE BARRIER (TYPE 60D) | M | 8 | 1 | 64.00 | $175.00 | $11,200.00 |
| | | M | 10 | 1 | 30.00 | $350.00 | $10,500.00 |
| | | M | 11 | 6 | 1,094.00 | $216.59 | $236,945.00 |
| | **Unit Sub Total** | **M** | | **16** | **8,224.00** | **$161.61** | **$1,329,086.00** |
| | **Item Code 839704 Total No. of Proj.** | | | **16** | | **Total Amount** | **$1,329,086.00** |
| **839705** | CONCRETE BARRIER (TYPE 60E) | LF | 4 | 3 | 1,146.00 | $182.46 | $209,100.00 |
| | **Unit Sub Total** | **LF** | | **3** | **1,146.00** | **$182.46** | **$209,100.00** |
| **839705** | CONCRETE BARRIER (TYPE 60E) | M | 2 | 1 | 72.00 | $600.00 | $43,200.00 |
| | | M | 3 | 1 | 320.00 | $650.00 | $208,000.00 |
| | | M | 4 | 3 | 763.00 | $664.74 | $507,200.00 |
| | | M | 7 | 1 | 260.00 | $680.00 | $176,800.00 |
| | | M | 11 | 1 | 640.00 | $706.00 | $451,840.00 |
| | **Unit Sub Total** | **M** | | **7** | **2,055.00** | **$674.96** | **$1,387,040.00** |
| | **Item Code 839705 Total No. of Proj.** | | | **10** | | **Total Amount** | **$1,596,140.00** |
| **839706** | CONCRETE BARRIER (TYPE 60G) | LF | 3 | 1 | 4,830.00 | $61.00 | $294,630.00 |
| | | LF | 5 | 1 | 64.00 | $210.00 | $13,440.00 |
| | **Unit Sub Total** | **LF** | | **2** | **4,894.00** | **$62.95** | **$308,070.00** |
| **839706** | CONCRETE BARRIER (TYPE 60G) | M | 7 | 1 | 225.00 | $333.00 | $74,925.00 |
| | | M | 8 | 1 | 33.00 | $240.00 | $7,920.00 |
| | | M | 11 | 2 | 326.00 | $369.94 | $120,600.00 |
| | **Unit Sub Total** | **M** | | **4** | **584.00** | **$348.36** | **$203,445.00** |
| | **Item Code 839706 Total No. of Proj.** | | | **6** | | **Total Amount** | **$511,515.00** |
| **839707** | CONCRETE BARRIER (TYPE 60GA) | M | 8 | 1 | 23.00 | $510.00 | $11,730.00 |
| | **Unit Sub Total** | **M** | | **1** | **23.00** | **$510.00** | **$11,730.00** |
| | **Item Code 839707 Total No. of Proj.** | | | **1** | | **Total Amount** | **$11,730.00** |
| **839708** | CONCRETE BARRIER (TYPE 60GC) | LF | 3 | 1 | 4,190.00 | $71.00 | $297,490.00 |
| | **Unit Sub Total** | **LF** | | **1** | **4,190.00** | **$71.00** | **$297,490.00** |
| **839708** | CONCRETE BARRIER (TYPE 60GC) | M | 7 | 1 | 990.00 | $350.00 | $346,500.00 |
| | | M | 8 | 3 | 15,613.00 | $272.94 | $4,261,390.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **839708** | CONCRETE BARRIER (TYPE 60GC) | M | 11 | 1 | 40.00 | $590.00 | $23,600.00 |
| | **Unit Sub Total** | **M** | | **5** | **16,643.00** | **$278.28** | **$4,631,490.00** |
| | **Item Code 839708 Total No. of Proj.** | | | **6** | | **Total Amount** | **$4,928,980.00** |
| **839709** | CONCRETE BARRIER (TYPE 60GE) | LF | 3 | 1 | 1,660.00 | $253.00 | $419,980.00 |
| | **Unit Sub Total** | **LF** | | **1** | **1,660.00** | **$253.00** | **$419,980.00** |
| **839709** | CONCRETE BARRIER (TYPE 60GE) | M | 8 | 3 | 601.00 | $708.50 | $425,810.00 |
| | | M | 11 | 3 | 920.00 | $1,007.61 | $927,000.00 |
| | **Unit Sub Total** | **M** | | **6** | **1,521.00** | **$889.42** | **$1,352,810.00** |
| | **Item Code 839709 Total No. of Proj.** | | | **7** | | **Total Amount** | **$1,772,790.00** |
| **839710** | CONCRETE BARRIER (TYPE 60S) | LF | 4 | 1 | 2,000.00 | $40.00 | $80,000.00 |
| | **Unit Sub Total** | **LF** | | **1** | **2,000.00** | **$40.00** | **$80,000.00** |
| **839710** | CONCRETE BARRIER (TYPE 60S) | M | 3 | 1 | 1,780.00 | $204.00 | $363,120.00 |
| | | M | 5 | 1 | 48.00 | $363.00 | $17,424.00 |
| | | M | 11 | 3 | 3,380.00 | $170.24 | $575,400.00 |
| | **Unit Sub Total** | **M** | | **5** | **5,208.00** | **$183.55** | **$955,944.00** |
| | **Item Code 839710 Total No. of Proj.** | | | **6** | | **Total Amount** | **$1,035,944.00** |
| **839711** | CONCRETE BARRIER (TYPE 60SA) | M | 3 | 1 | 18.00 | $224.00 | $4,032.00 |
| | | M | 11 | 2 | 90.00 | $293.56 | $26,420.00 |
| | **Unit Sub Total** | **M** | | **3** | **108.00** | **$281.96** | **$30,452.00** |
| | **Item Code 839711 Total No. of Proj.** | | | **3** | | **Total Amount** | **$30,452.00** |
| **839712** | CONCRETE BARRIER (TYPE 60SC) | LF | 3 | 1 | 1,450.00 | $165.00 | $239,250.00 |
| | **Unit Sub Total** | **LF** | | **1** | **1,450.00** | **$165.00** | **$239,250.00** |
| **839712** | CONCRETE BARRIER (TYPE 60SC) | M | 3 | 1 | 500.00 | $224.00 | $112,000.00 |
| | | M | 5 | 1 | 630.00 | $325.00 | $204,750.00 |
| | | M | 8 | 1 | 1,000.00 | $250.00 | $250,000.00 |
| | | M | 11 | 3 | 10,240.00 | $226.97 | $2,324,200.00 |
| | **Unit Sub Total** | **M** | | **6** | **12,370.00** | **$233.71** | **$2,890,950.00** |
| | **Item Code 839712 Total No. of Proj.** | | | **7** | | **Total Amount** | **$3,130,200.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **839713** | CONCRETE BARRIER (TYPE 60SE) | M | 11 | 1 | 140.00 | $700.00 | $98,000.00 |
| | **Unit Sub Total** | **M** | | **1** | **140.00** | **$700.00** | **$98,000.00** |
| | **Item Code 839713 Total No. of Proj.** | | | **1** | | **Total Amount** | **$98,000.00** |
| **839714** | CONCRETE BARRIER (TYPE 80) | LF | 7 | 1 | 403.00 | $240.00 | $96,720.00 |
| | | LF | 8 | 1 | 565.00 | $250.00 | $141,250.00 |
| | **Unit Sub Total** | **LF** | | **2** | **968.00** | **$245.84** | **$237,970.00** |
| **839714** | CONCRETE BARRIER (TYPE 80) | M | 4 | 1 | 182.00 | $480.00 | $87,360.00 |
| | **Unit Sub Total** | **M** | | **1** | **182.00** | **$480.00** | **$87,360.00** |
| | **Item Code 839714 Total No. of Proj.** | | | **3** | | **Total Amount** | **$325,330.00** |
| **839717** | CONCRETE BARRIER (TYPE 732 MODIFIED) | LF | 7 | 1 | 21.00 | $200.00 | $4,200.00 |
| | **Unit Sub Total** | **LF** | | **1** | **21.00** | **$200.00** | **$4,200.00** |
| **839717** | CONCRETE BARRIER (TYPE 732 MODIFIED) | M | 1 | 2 | 353.00 | $315.16 | $111,250.00 |
| | | M | 2 | 2 | 399.00 | $472.74 | $188,625.00 |
| | | M | 3 | 1 | 63.00 | $84.00 | $5,292.00 |
| | | M | 4 | 2 | 161.00 | $532.11 | $85,670.00 |
| | | M | 7 | 1 | 72.00 | $198.00 | $14,256.00 |
| | | M | 10 | 1 | 407.00 | $362.10 | $147,374.70 |
| | | M | 11 | 1 | 439.00 | $220.00 | $96,580.00 |
| | **Unit Sub Total** | **M** | | **10** | **1,894.00** | **$342.69** | **$649,047.70** |
| | **Item Code 839717 Total No. of Proj.** | | | **11** | | **Total Amount** | **$653,247.70** |
| **839718** | CONCRETE BARRIER (TYPE 732R) | LF | 6 | 1 | 637.00 | $140.00 | $89,180.00 |
| | **Unit Sub Total** | **LF** | | **1** | **637.00** | **$140.00** | **$89,180.00** |
| **839718** | CONCRETE BARRIER (TYPE 732R) | M | 7 | 1 | 1,088.00 | $450.00 | $489,600.00 |
| | | M | 8 | 1 | 153.00 | $215.00 | $32,895.00 |
| | **Unit Sub Total** | **M** | | **2** | **1,241.00** | **$421.03** | **$522,495.00** |
| | **Item Code 839718 Total No. of Proj.** | | | **3** | | **Total Amount** | **$611,675.00** |
| **839720** | CONCRETE BARRIER (TYPE 732) | LF | 3 | 1 | 895.00 | $90.00 | $80,550.00 |
| | **Unit Sub Total** | **LF** | | **1** | **895.00** | **$90.00** | **$80,550.00** |
| **839720** | CONCRETE BARRIER (TYPE 732) | M | 1 | 1 | 68.00 | $480.00 | $32,640.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **839720** | CONCRETE BARRIER (TYPE 732) | M | 2 | 3 | 1,559.00 | $109.77 | $171,130.00 |
| | | M | 3 | 2 | 441.00 | $230.18 | $101,510.00 |
| | | M | 4 | 2 | 326.00 | $370.37 | $120,740.00 |
| | | M | 6 | 1 | 275.00 | $295.00 | $81,125.00 |
| | | M | 8 | 1 | 227.00 | $185.00 | $41,995.00 |
| | | M | 9 | 1 | 178.00 | $320.00 | $56,960.00 |
| | | M | 11 | 1 | 1,843.00 | $224.00 | $412,832.00 |
| | **Unit Sub Total** | **M** | | **12** | **4,917.00** | **$207.23** | **$1,018,932.00** |
| | **Item Code 839720 Total No. of Proj.** | | | **13** | | **Total Amount** | **$1,099,482.00** |
| **839721** | CONCRETE BARRIER (TYPE 732A) | M | 2 | 1 | 110.00 | $310.00 | $34,100.00 |
| | | M | 3 | 1 | 130.00 | $266.00 | $34,580.00 |
| | | M | 4 | 2 | 1,860.00 | $185.90 | $345,780.00 |
| | | M | 5 | 2 | 558.00 | $265.63 | $148,220.00 |
| | | M | 7 | 1 | 730.00 | $209.00 | $152,570.00 |
| | | M | 10 | 1 | 129.00 | $160.00 | $20,640.00 |
| | **Unit Sub Total** | **M** | | **8** | **3,517.00** | **$209.24** | **$735,890.00** |
| | **Item Code 839721 Total No. of Proj.** | | | **8** | | **Total Amount** | **$735,890.00** |
| **839723** | CONCRETE BARRIER (TYPE 732B) | M | 3 | 1 | 170.00 | $400.00 | $68,000.00 |
| | | M | 5 | 2 | 98.00 | $402.35 | $39,430.00 |
| | | M | 7 | 2 | 186.00 | $274.72 | $51,098.00 |
| | | M | 11 | 1 | 38.00 | $512.00 | $19,456.00 |
| | **Unit Sub Total** | **M** | | **6** | **492.00** | **$361.76** | **$177,984.00** |
| | **Item Code 839723 Total No. of Proj.** | | | **6** | | **Total Amount** | **$177,984.00** |
| **839725** | CONCRETE BARRIER (TYPE 736) | LF | 7 | 1 | 90.00 | $283.00 | $25,470.00 |
| | | LF | 12 | 1 | 258.00 | $75.00 | $19,350.00 |
| | **Unit Sub Total** | **LF** | | **2** | **348.00** | **$128.79** | **$44,820.00** |
| **839725** | CONCRETE BARRIER (TYPE 736) | M | 1 | 1 | 34.00 | $675.00 | $22,950.00 |
| | | M | 2 | 1 | 64.00 | $325.00 | $20,800.00 |
| | | M | 4 | 2 | 484.00 | $297.59 | $144,035.00 |
| | | M | 6 | 1 | 14.00 | $825.00 | $11,550.00 |
| | | M | 7 | 3 | 230.00 | $264.30 | $60,790.00 |
| | | M | 11 | 3 | 1,472.00 | $179.85 | $264,740.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M** | | **11** | **2,298.00** | **$228.40** | **$524,865.00** |
| | **Item Code 839725** | **Total No. of Proj.** | | | **13** | | **Total Amount** | **$569,685.00** |
| **839726** | CONCRETE BARRIER (TYPE 736A) | | LF | 2 | 1 | 63.00 | $551.00 | $34,713.00 |
| | | | LF | 12 | 2 | 3,168.00 | $54.79 | $173,576.00 |
| | | **Unit Sub Total** | **LF** | | **3** | **3,231.00** | **$64.47** | **$208,289.00** |
| **839726** | CONCRETE BARRIER (TYPE 736A) | | M | 2 | 1 | 740.00 | $300.00 | $222,000.00 |
| | | | M | 3 | 1 | 810.00 | $85.00 | $68,850.00 |
| | | | M | 4 | 1 | 490.00 | $220.00 | $107,800.00 |
| | | | M | 5 | 1 | 99.00 | $190.00 | $18,810.00 |
| | | | M | 6 | 1 | 22.00 | $1,135.00 | $24,970.00 |
| | | | M | 7 | 2 | 1,332.00 | $220.39 | $293,561.60 |
| | | | M | 9 | 1 | 98.00 | $80.00 | $7,840.00 |
| | | | M | 11 | 3 | 721.00 | $252.41 | $181,990.00 |
| | | **Unit Sub Total** | **M** | | **11** | **4,312.00** | **$214.71** | **$925,821.60** |
| | **Item Code 839726** | **Total No. of Proj.** | | | **14** | | **Total Amount** | **$1,134,110.60** |
| **839727** | CONCRETE BARRIER (TYPE 736 MODIFIED) | | LF | 3 | 1 | 230.00 | $215.00 | $49,450.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **230.00** | **$215.00** | **$49,450.00** |
| **839727** | CONCRETE BARRIER (TYPE 736 MODIFIED) | | M | 2 | 1 | 9.00 | $900.00 | $8,100.00 |
| | | | M | 3 | 1 | 3,255.00 | $230.00 | $748,650.00 |
| | | | M | 5 | 2 | 250.00 | $267.04 | $66,760.00 |
| | | | M | 7 | 2 | 6,078.00 | $250.41 | $1,521,990.00 |
| | | | M | 11 | 7 | 3,827.00 | $232.64 | $890,320.00 |
| | | **Unit Sub Total** | **M** | | **13** | **13,419.00** | **$241.14** | **$3,235,820.00** |
| | **Item Code 839727** | **Total No. of Proj.** | | | **14** | | **Total Amount** | **$3,285,270.00** |
| **839728** | CONCRETE BARRIER (TYPE 736R) | | LF | 3 | 1 | 473.00 | $300.00 | $141,900.00 |
| | | **Unit Sub Total** | **LF** | | **1** | **473.00** | **$300.00** | **$141,900.00** |
| **839728** | CONCRETE BARRIER (TYPE 736R) | | M | 6 | 1 | 14.00 | $935.00 | $13,090.00 |
| | | | M | 7 | 1 | 691.00 | $425.00 | $293,675.00 |
| | | | M | 11 | 1 | 61.00 | $285.00 | $17,385.00 |
| | | **Unit Sub Total** | **M** | | **3** | **766.00** | **$423.17** | **$324,150.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 839728 Total No. of Proj.** | | | **4** | | **Total Amount** | **$466,050.00** |
| **839731** | CONCRETE BARRIER (TYPE 736B) | M | 3 | 1 | 350.00 | $105.00 | $36,750.00 |
| | | M | 4 | 1 | 260.00 | $450.00 | $117,000.00 |
| | | M | 7 | 4 | 537.00 | $337.60 | $181,290.00 |
| | | M | 11 | 3 | 760.00 | $328.62 | $249,750.00 |
| | **Unit Sub Total** | **M** | | **9** | **1,907.00** | **$306.65** | **$584,790.00** |
| | **Item Code 839731 Total No. of Proj.** | | | **9** | | **Total Amount** | **$584,790.00** |
| **839734** | CONCRETE BARRIER (TYPE 736SV) | M | 3 | 1 | 2,300.00 | $575.00 | $1,322,500.00 |
| | | M | 4 | 1 | 527.00 | $700.00 | $368,900.00 |
| | | M | 7 | 1 | 530.00 | $500.00 | $265,000.00 |
| | **Unit Sub Total** | **M** | | **3** | **3,357.00** | **$582.78** | **$1,956,400.00** |
| | **Item Code 839734 Total No. of Proj.** | | | **3** | | **Total Amount** | **$1,956,400.00** |
| **839735** | CONCRETE BARRIER (TYPE 742) | M | 11 | 1 | 2,938.00 | $200.00 | $587,600.00 |
| | **Unit Sub Total** | **M** | | **1** | **2,938.00** | **$200.00** | **$587,600.00** |
| | **Item Code 839735 Total No. of Proj.** | | | **1** | | **Total Amount** | **$587,600.00** |
| **839736** | CONCRETE BARRIER (TYPE 742A) | M | 11 | 1 | 907.00 | $200.00 | $181,400.00 |
| | **Unit Sub Total** | **M** | | **1** | **907.00** | **$200.00** | **$181,400.00** |
| | **Item Code 839736 Total No. of Proj.** | | | **1** | | **Total Amount** | **$181,400.00** |
| **839737** | CONCRETE BARRIER (TYPE 742B) | M | 8 | 1 | 43.00 | $350.00 | $15,050.00 |
| | **Unit Sub Total** | **M** | | **1** | **43.00** | **$350.00** | **$15,050.00** |
| | **Item Code 839737 Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,050.00** |
| **839740** | CALIFORNIA ST-10 BRIDGE RAIL | LF | 6 | 1 | 337.00 | $275.00 | $92,675.00 |
| | **Unit Sub Total** | **LF** | | **1** | **337.00** | **$275.00** | **$92,675.00** |
| **839740** | CALIFORNIA ST-10 BRIDGE RAIL | M | 1 | 1 | 729.00 | $600.00 | $437,400.00 |
| | **Unit Sub Total** | **M** | | **1** | **729.00** | **$600.00** | **$437,400.00** |
| | **Item Code 839740 Total No. of Proj.** | | | **2** | | **Total Amount** | **$530,075.00** |
| **840501** | THERMOPLASTIC TRAFFIC STRIPE | LF | 2 | 1 | 250.00 | $1.00 | $250.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **840501** | THERMOPLASTIC TRAFFIC STRIPE | LF | 3 | 1 | 1,600.00 | $3.00 | $4,800.00 |
| | | LF | 4 | 1 | 1,460.00 | $1.60 | $2,336.00 |
| | | LF | 7 | 1 | 2,360.00 | $1.23 | $2,902.80 |
| | | LF | 8 | 4 | 15,260.00 | $0.66 | $10,113.10 |
| | **Unit Sub Total** | **LF** | | **8** | **20,930.00** | **$0.97** | **$20,401.90** |
| **840501** | THERMOPLASTIC TRAFFIC STRIPE | M | 6 | 1 | 180.00 | $17.00 | $3,060.00 |
| | | M | 7 | 1 | 1,560.00 | $3.00 | $4,680.00 |
| | **Unit Sub Total** | **M** | | **2** | **1,740.00** | **$4.45** | **$7,740.00** |
| | **Item Code 840501 Total No. of Proj.** | | | **10** | | **Total Amount** | **$28,141.90** |
| **840504** | 4" THERMOPLASTIC TRAFFIC STRIPE | LF | 1 | 20 | 1,499,330.00 | $0.31 | $463,770.00 |
| | | LF | 2 | 1 | 12,200.00 | $0.55 | $6,710.00 |
| | | LF | 3 | 30 | 2,525,710.00 | $0.30 | $761,033.50 |
| | | LF | 4 | 34 | 1,293,224.00 | $0.45 | $583,980.00 |
| | | LF | 5 | 10 | 389,280.00 | $0.25 | $99,093.00 |
| | | LF | 6 | 18 | 1,909,020.00 | $0.24 | $463,364.50 |
| | | LF | 7 | 24 | 1,017,330.00 | $0.31 | $318,385.20 |
| | | LF | 8 | 2 | 49,450.00 | $0.29 | $14,258.50 |
| | | LF | 11 | 1 | 99,000.00 | $0.20 | $19,800.00 |
| | | LF | 12 | 24 | 1,077,440.00 | $0.28 | $296,458.10 |
| | **Unit Sub Total** | **LF** | | **164** | **9,871,984.00** | **$0.31** | **$3,026,852.80** |
| | **Item Code 840504 Total No. of Proj.** | | | **164** | | **Total Amount** | **$3,026,852.80** |
| **840505** | 6" THERMOPLASTIC TRAFFIC STRIPE | LF | 3 | 1 | 1,420.00 | $1.10 | $1,562.00 |
| | | LF | 4 | 3 | 4,530.00 | $0.80 | $3,640.00 |
| | | LF | 5 | 1 | 14,400.00 | $0.39 | $5,616.00 |
| | | LF | 11 | 1 | 200.00 | $1.00 | $200.00 |
| | | LF | 12 | 1 | 50.00 | $1.00 | $50.00 |
| | **Unit Sub Total** | **LF** | | **7** | **20,600.00** | **$0.54** | **$11,068.00** |
| | **Item Code 840505 Total No. of Proj.** | | | **7** | | **Total Amount** | **$11,068.00** |
| **840506** | 8" THERMOPLASTIC TRAFFIC STRIPE | LF | 1 | 9 | 17,188.00 | $0.96 | $16,432.50 |
| | | LF | 2 | 1 | 20.00 | $3.00 | $60.00 |
| | | LF | 3 | 17 | 21,484.00 | $0.92 | $19,841.50 |
| | | LF | 4 | 20 | 69,160.00 | $0.95 | $65,506.80 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **840506** | 8" THERMOPLASTIC TRAFFIC STRIPE | LF | 5 | 9 | 42,580.00 | $0.78 | $33,003.50 |
| | | LF | 6 | 15 | 58,540.00 | $0.58 | $33,913.40 |
| | | LF | 7 | 17 | 55,050.00 | $0.92 | $50,723.10 |
| | | LF | 8 | 1 | 740.00 | $0.88 | $651.20 |
| | | LF | 11 | 20 | 48,850.00 | $0.95 | $46,510.50 |
| | | LF | 12 | 22 | 88,587.00 | $0.61 | $53,777.15 |
| | **Unit Sub Total** | **LF** | | **131** | **402,199.00** | **$0.80** | **$320,419.65** |
| | **Item Code 840506 Total No. of Proj.** | | | **131** | | **Total Amount** | **$320,419.65** |
| **840508** | 8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3) | LF | 1 | 2 | 4,870.00 | $0.43 | $2,084.00 |
| | | LF | 3 | 7 | 4,010.00 | $1.40 | $5,632.00 |
| | | LF | 4 | 7 | 8,530.00 | $1.18 | $10,060.00 |
| | | LF | 5 | 5 | 4,160.00 | $0.59 | $2,460.60 |
| | | LF | 6 | 3 | 2,790.00 | $0.56 | $1,576.00 |
| | | LF | 7 | 8 | 34,630.00 | $0.57 | $19,768.90 |
| | | LF | 8 | 1 | 110.00 | $0.88 | $96.80 |
| | | LF | 11 | 7 | 11,600.00 | $0.66 | $7,650.20 |
| | | LF | 12 | 13 | 43,860.00 | $0.45 | $19,727.80 |
| | **Unit Sub Total** | **LF** | | **53** | **114,560.00** | **$0.60** | **$69,056.30** |
| | **Item Code 840508 Total No. of Proj.** | | | **53** | | **Total Amount** | **$69,056.30** |
| **840515** | THERMOPLASTIC PAVEMENT MARKING | M2 | 1 | 5 | 551.00 | $53.25 | $29,340.00 |
| | | M2 | 2 | 3 | 355.00 | $73.62 | $26,135.00 |
| | | M2 | 3 | 6 | 2,669.00 | $47.57 | $126,960.00 |
| | | M2 | 4 | 8 | 1,632.00 | $54.74 | $89,327.80 |
| | | M2 | 5 | 8 | 3,384.00 | $29.72 | $100,574.00 |
| | | M2 | 6 | 7 | 1,630.00 | $35.17 | $57,320.00 |
| | | M2 | 7 | 16 | 15,840.00 | $21.44 | $339,540.84 |
| | | M2 | 8 | 5 | 525.10 | $41.10 | $21,580.00 |
| | | M2 | 9 | 3 | 1,250.00 | $24.46 | $30,580.00 |
| | | M2 | 10 | 9 | 2,824.00 | $28.17 | $79,538.00 |
| | | M2 | 11 | 11 | 3,159.00 | $37.13 | $117,302.00 |
| | | M2 | 12 | 3 | 127.00 | $47.42 | $6,022.00 |
| | **Unit Sub Total** | **M2** | | **84** | **33,946.10** | **$30.17** | **$1,024,219.64** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **840515** | THERMOPLASTIC PAVEMENT MARKING | SQFT | 1 | 12 | 16,992.00 | $6.03 | $102,511.50 |
| | | SQFT | 2 | 19 | 20,346.00 | $6.45 | $131,249.50 |
| | | SQFT | 3 | 19 | 17,072.00 | $5.06 | $86,314.00 |
| | | SQFT | 4 | 27 | 30,901.00 | $3.39 | $104,822.40 |
| | | SQFT | 5 | 13 | 42,108.00 | $2.32 | $97,579.40 |
| | | SQFT | 6 | 18 | 24,081.00 | $3.05 | $73,376.50 |
| | | SQFT | 7 | 19 | 41,020.00 | $3.06 | $125,717.10 |
| | | SQFT | 8 | 22 | 22,104.00 | $3.20 | $70,700.18 |
| | | SQFT | 9 | 3 | 9,550.00 | $2.42 | $23,078.00 |
| | | SQFT | 10 | 16 | 15,777.00 | $3.82 | $60,343.60 |
| | | SQFT | 11 | 18 | 33,223.00 | $2.81 | $93,498.80 |
| | | SQFT | 12 | 23 | 50,910.00 | $2.40 | $121,984.50 |
| | **Unit Sub Total** | **SQFT** | | **209** | **324,084.00** | **$3.37** | **$1,091,175.48** |
| | **Item Code 840515 Total No. of Proj.** | | | **293** | | **Total Amount** | **$2,115,395.12** |
| **840519** | THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING | M2 | 7 | 1 | 80.00 | $33.00 | $2,640.00 |
| | | M2 | 12 | 2 | 105.00 | $38.57 | $4,050.00 |
| | **Unit Sub Total** | **M2** | | **3** | **185.00** | **$36.16** | **$6,690.00** |
| **840519** | THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING | SQFT | 1 | 2 | 9,590.00 | $5.21 | $49,979.00 |
| | | SQFT | 4 | 1 | 1,560.00 | $6.37 | $9,937.20 |
| | **Unit Sub Total** | **SQFT** | | **3** | **11,150.00** | **$5.37** | **$59,916.20** |
| | **Item Code 840519 Total No. of Proj.** | | | **6** | | **Total Amount** | **$66,606.20** |
| **840521** | 4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 6-1) | LF | 7 | 3 | 990.00 | $0.60 | $595.30 |
| | | LF | 11 | 3 | 328.00 | $0.48 | $156.50 |
| | | LF | 12 | 4 | 870.00 | $0.65 | $564.80 |
| | **Unit Sub Total** | **LF** | | **10** | **2,188.00** | **$0.60** | **$1,316.60** |
| | **Item Code 840521 Total No. of Proj.** | | | **10** | | **Total Amount** | **$1,316.60** |
| **840523** | 4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3) | LF | 1 | 6 | 6,900.00 | $0.42 | $2,869.10 |
| | | LF | 2 | 1 | 1,190.00 | $0.55 | $654.50 |
| | | LF | 3 | 11 | 14,580.00 | $0.25 | $3,667.90 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **840523** | 4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3) | LF | 4 | 1 | 110.00 | $0.30 | $33.00 |
| | | LF | 6 | 6 | 13,250.00 | $0.19 | $2,479.55 |
| | | LF | 7 | 1 | 200.00 | $0.17 | $34.00 |
| | **Unit Sub Total** | **LF** | | **26** | **36,230.00** | **$0.27** | **$9,738.05** |
| | **Item Code 840523 Total No. of Proj.** | | | **26** | | **Total Amount** | **$9,738.05** |
| **840525** | 4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12) | LF | 1 | 11 | 211,970.00 | $0.30 | $62,626.60 |
| | | LF | 2 | 1 | 270.00 | $0.55 | $148.50 |
| | | LF | 3 | 22 | 754,700.00 | $0.26 | $194,545.00 |
| | | LF | 4 | 16 | 104,810.00 | $0.49 | $51,807.40 |
| | | LF | 5 | 5 | 62,190.00 | $0.18 | $11,243.60 |
| | | LF | 6 | 13 | 970,970.00 | $0.14 | $140,605.00 |
| | | LF | 7 | 18 | 530,720.00 | $0.19 | $101,911.80 |
| | | LF | 8 | 1 | 490.00 | $0.39 | $191.10 |
| | | LF | 11 | 1 | 9,510.00 | $0.15 | $1,426.50 |
| | | LF | 12 | 12 | 612,680.00 | $0.20 | $125,238.00 |
| | **Unit Sub Total** | **LF** | | **100** | **3,258,310.00** | **$0.21** | **$689,743.50** |
| | **Item Code 840525 Total No. of Proj.** | | | **100** | | **Total Amount** | **$689,743.50** |
| **840526** | 4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 17-7) | LF | 1 | 3 | 3,250.00 | $0.47 | $1,522.20 |
| | | LF | 3 | 7 | 5,080.00 | $1.07 | $5,428.50 |
| | | LF | 4 | 15 | 32,680.00 | $0.59 | $19,165.20 |
| | | LF | 5 | 2 | 5,965.00 | $0.17 | $985.90 |
| | | LF | 6 | 5 | 86,230.00 | $0.14 | $12,356.00 |
| | | LF | 7 | 11 | 124,710.00 | $0.21 | $26,726.60 |
| | | LF | 11 | 7 | 47,335.00 | $0.17 | $8,039.60 |
| | | LF | 12 | 16 | 32,800.00 | $0.29 | $9,592.40 |
| | **Unit Sub Total** | **LF** | | **66** | **338,050.00** | **$0.25** | **$83,816.40** |
| | **Item Code 840526 Total No. of Proj.** | | | **66** | | **Total Amount** | **$83,816.40** |
| **840545** | 4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED, BROKEN 36-12) | LF | 3 | 3 | 90,160.00 | $2.20 | $198,510.00 |
| | | LF | 9 | 1 | 19,600.00 | $2.05 | $40,180.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **LF** | | **4** | **109,760.00** | **$2.17** | **$238,690.00** |
| | **Item Code 840545 Total No. of Proj.** | | | **4** | | **Total Amount** | **$238,690.00** |
| **840550** | 8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12) | LF | 7 | 5 | 15,580.00 | $0.49 | $7,602.00 |
| | | LF | 12 | 6 | 35,970.00 | $0.46 | $16,696.00 |
| | **Unit Sub Total** | **LF** | | **11** | **51,550.00** | **$0.47** | **$24,298.00** |
| | **Item Code 840550 Total No. of Proj.** | | | **11** | | **Total Amount** | **$24,298.00** |
| **840559** | 100 MM THERMOPLASTIC TRAFFIC STRIPE (RECESSED) (BROKEN 5.18 M - 2.14 M) | M | 3 | 2 | 4,340.00 | $9.54 | $41,391.00 |
| | **Unit Sub Total** | **M** | | **2** | **4,340.00** | **$9.54** | **$41,391.00** |
| | **Item Code 840559 Total No. of Proj.** | | | **2** | | **Total Amount** | **$41,391.00** |
| **840560** | THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE) | LF | 1 | 3 | 96,480.00 | $0.28 | $27,150.00 |
| | | LF | 2 | 21 | 2,197,500.00 | $0.22 | $480,177.50 |
| | | LF | 3 | 4 | 5,010.00 | $3.13 | $15,660.00 |
| | | LF | 4 | 2 | 41,310.00 | $0.50 | $20,655.00 |
| | | LF | 5 | 7 | 384,950.00 | $0.24 | $92,882.00 |
| | | LF | 6 | 13 | 1,106,670.00 | $0.15 | $162,354.00 |
| | | LF | 8 | 32 | 5,124,270.00 | $0.15 | $762,255.50 |
| | | LF | 10 | 25 | 1,550,770.00 | $0.23 | $360,003.40 |
| | **Unit Sub Total** | **LF** | | **107** | **10,506,960.00** | **$0.18** | **$1,921,137.40** |
| **840560** | THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE) | M | 2 | 4 | 12,100.00 | $1.51 | $18,265.00 |
| | | M | 3 | 1 | 24,700.00 | $1.00 | $24,700.00 |
| | | M | 4 | 2 | 25,010.00 | $0.45 | $11,140.00 |
| | | M | 5 | 15 | 188,410.00 | $0.75 | $141,708.00 |
| | | M | 6 | 4 | 43,400.00 | $0.82 | $35,529.00 |
| | | M | 8 | 5 | 144,430.00 | $0.96 | $139,365.00 |
| | | M | 10 | 10 | 126,420.00 | $0.65 | $81,863.00 |
| | **Unit Sub Total** | **M** | | **41** | **564,470.00** | **$0.80** | **$452,570.00** |
| | **Item Code 840560 Total No. of Proj.** | | | **148** | | **Total Amount** | **$2,373,707.40** |
| **840561** | 100 MM THERMOPLASTIC TRAFFIC STRIPE | LF | 4 | 1 | 25,100.00 | $0.69 | $17,319.00 |
| | **Unit Sub Total** | **LF** | | **1** | **25,100.00** | **$0.69** | **$17,319.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **840561** | 100 MM THERMOPLASTIC TRAFFIC STRIPE | M | 1 | 7 | 59,130.00 | $1.50 | $88,948.00 |
| | | M | 2 | 2 | 17,040.00 | $1.16 | $19,730.00 |
| | | M | 3 | 5 | 230,120.00 | $0.85 | $196,417.00 |
| | | M | 4 | 14 | 301,470.00 | $1.28 | $385,804.00 |
| | | M | 5 | 2 | 9,380.00 | $0.89 | $8,363.00 |
| | | M | 6 | 7 | 91,100.00 | $0.98 | $89,342.00 |
| | | M | 7 | 21 | 416,550.00 | $0.90 | $375,383.00 |
| | | M | 8 | 1 | 26,200.00 | $0.64 | $16,768.00 |
| | | M | 10 | 1 | 5,770.00 | $0.50 | $2,885.00 |
| | | M | 11 | 3 | 73,430.00 | $0.86 | $62,800.00 |
| | | M | 12 | 5 | 5,760.00 | $1.62 | $9,357.00 |
| | **Unit Sub Total** | **M** | | **68** | **1,235,950.00** | **$1.02** | **$1,255,797.00** |
| | **Item Code 840561 Total No. of Proj.** | | | **69** | | **Total Amount** | **$1,273,116.00** |
| **840562** | 150 MM THERMOPLASTIC TRAFFIC STRIPE | M | 1 | 1 | 670.00 | $2.50 | $1,675.00 |
| | | M | 2 | 1 | 210.00 | $1.10 | $231.00 |
| | | M | 3 | 1 | 1,400.00 | $1.00 | $1,400.00 |
| | | M | 5 | 2 | 7,640.00 | $1.32 | $10,081.00 |
| | | M | 7 | 1 | 50.00 | $4.00 | $200.00 |
| | | M | 11 | 2 | 334.00 | $1.78 | $595.00 |
| | **Unit Sub Total** | **M** | | **8** | **10,304.00** | **$1.38** | **$14,182.00** |
| | **Item Code 840562 Total No. of Proj.** | | | **8** | | **Total Amount** | **$14,182.00** |
| **840563** | 200 MM THERMOPLASTIC TRAFFIC STRIPE | LF | 4 | 1 | 370.00 | $1.27 | $469.90 |
| | **Unit Sub Total** | **LF** | | **1** | **370.00** | **$1.27** | **$469.90** |
| **840563** | 200 MM THERMOPLASTIC TRAFFIC STRIPE | M | 1 | 4 | 1,863.00 | $4.07 | $7,588.50 |
| | | M | 2 | 2 | 2,300.00 | $1.34 | $3,076.00 |
| | | M | 3 | 6 | 19,430.00 | $2.33 | $45,253.00 |
| | | M | 4 | 10 | 17,455.00 | $1.90 | $33,148.80 |
| | | M | 5 | 2 | 4,020.00 | $3.07 | $12,360.00 |
| | | M | 6 | 8 | 6,100.00 | $1.72 | $10,467.00 |
| | | M | 7 | 18 | 29,642.00 | $2.27 | $67,302.00 |
| | | M | 10 | 1 | 1,420.00 | $0.50 | $710.00 |
| | | M | 11 | 11 | 26,680.00 | $2.44 | $65,043.00 |
| | | M | 12 | 4 | 1,202.00 | $2.80 | $3,371.50 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **M** | | **66** | **110,112.00** | **$2.26** | **$248,319.80** |
| | **Item Code 840563** | **Total No. of Proj.** | | | **67** | | **Total Amount** | **$248,789.70** |
| **840564** | 200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M) | | M | 2 | 1 | 1,960.00 | $1.10 | $2,156.00 |
| | | | M | 3 | 3 | 7,310.00 | $2.02 | $14,797.00 |
| | | | M | 4 | 5 | 6,800.00 | $2.33 | $15,865.80 |
| | | | M | 5 | 2 | 1,640.00 | $1.42 | $2,320.90 |
| | | | M | 6 | 1 | 150.00 | $1.30 | $195.00 |
| | | | M | 7 | 7 | 12,860.00 | $0.91 | $11,724.60 |
| | | | M | 11 | 9 | 15,140.00 | $1.46 | $22,117.00 |
| | | | M | 12 | 1 | 250.00 | $3.40 | $850.00 |
| | | **Unit Sub Total** | **M** | | **29** | **46,110.00** | **$1.52** | **$70,026.30** |
| | **Item Code 840564** | **Total No. of Proj.** | | | **29** | | **Total Amount** | **$70,026.30** |
| **840567** | 100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 1.83 M - 0.30 M) | | M | 2 | 1 | 53.00 | $1.10 | $58.30 |
| | | | M | 3 | 3 | 384.00 | $1.02 | $390.00 |
| | | | M | 4 | 1 | 100.00 | $1.00 | $100.00 |
| | | | M | 7 | 2 | 132.00 | $2.68 | $354.00 |
| | | | M | 11 | 6 | 509.00 | $3.13 | $1,592.75 |
| | | **Unit Sub Total** | **M** | | **13** | **1,178.00** | **$2.12** | **$2,495.05** |
| | **Item Code 840567** | **Total No. of Proj.** | | | **13** | | **Total Amount** | **$2,495.05** |
| **840568** | 100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M) | | M | 1 | 2 | 575.00 | $1.45 | $832.50 |
| | | | M | 2 | 1 | 69.00 | $1.10 | $75.90 |
| | | | M | 3 | 2 | 280.00 | $3.68 | $1,030.00 |
| | | | M | 4 | 2 | 960.00 | $1.06 | $1,016.00 |
| | | | M | 5 | 2 | 1,160.00 | $0.91 | $1,052.00 |
| | | | M | 6 | 2 | 2,060.00 | $0.43 | $893.00 |
| | | | M | 11 | 1 | 2,820.00 | $0.90 | $2,538.00 |
| | | **Unit Sub Total** | **M** | | **12** | **7,924.00** | **$0.94** | **$7,437.40** |
| | **Item Code 840568** | **Total No. of Proj.** | | | **12** | | **Total Amount** | **$7,437.40** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **840570** | 100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M) | M | 1 | 4 | 4,830.00 | $1.84 | $8,886.00 |
| | | M | 2 | 1 | 5,240.00 | $1.10 | $5,764.00 |
| | | M | 3 | 5 | 115,560.00 | $1.22 | $141,410.00 |
| | | M | 5 | 3 | 42,320.00 | $0.63 | $26,860.00 |
| | | M | 6 | 5 | 43,843.00 | $0.41 | $18,117.50 |
| | | M | 7 | 10 | 186,250.00 | $0.56 | $104,186.50 |
| | | M | 8 | 1 | 78,500.00 | $0.56 | $43,960.00 |
| | | M | 10 | 1 | 2,010.00 | $0.50 | $1,005.00 |
| | | M | 12 | 3 | 1,416.00 | $2.54 | $3,602.00 |
| | **Unit Sub Total** | **M** | | **33** | **479,969.00** | **$0.74** | **$353,791.00** |
| | **Item Code 840570 Total No. of Proj.** | | | **33** | | **Total Amount** | **$353,791.00** |
| **840571** | 100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 5.18 M - 2.14 M) | M | 1 | 1 | 210.00 | $0.60 | $126.00 |
| | | M | 2 | 1 | 440.00 | $1.10 | $484.00 |
| | | M | 3 | 4 | 7,740.00 | $1.11 | $8,576.00 |
| | | M | 4 | 6 | 5,450.00 | $2.05 | $11,187.00 |
| | | M | 5 | 3 | 8,240.00 | $0.51 | $4,183.20 |
| | | M | 6 | 2 | 12,600.00 | $0.74 | $9,370.00 |
| | | M | 7 | 9 | 10,740.00 | $0.78 | $8,395.70 |
| | | M | 10 | 1 | 2,250.00 | $0.50 | $1,125.00 |
| | | M | 11 | 8 | 2,511.00 | $1.53 | $3,830.00 |
| | | M | 12 | 3 | 1,020.00 | $1.50 | $1,530.50 |
| | **Unit Sub Total** | **M** | | **38** | **51,201.00** | **$0.95** | **$48,807.40** |
| | **Item Code 840571 Total No. of Proj.** | | | **38** | | **Total Amount** | **$48,807.40** |
| **840572** | 100 MM THERMOPLASTIC TRAFFIC STRIPE (RECESSED) | M | 3 | 2 | 42,180.00 | $11.16 | $470,680.00 |
| | | M | 10 | 1 | 8,370.00 | $4.00 | $33,480.00 |
| | **Unit Sub Total** | **M** | | **3** | **50,550.00** | **$9.97** | **$504,160.00** |
| | **Item Code 840572 Total No. of Proj.** | | | **3** | | **Total Amount** | **$504,160.00** |
| **840573** | 100 MM THERMOPLASTIC TRAFFIC STRIPE (RECESSED, BROKEN 10.98 M - 3.66 M) | M | 3 | 2 | 8,950.00 | $20.27 | $181,380.00 |
| | **Unit Sub Total** | **M** | | **2** | **8,950.00** | **$20.27** | **$181,380.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 840573 Total No. of Proj.** | | | **2** | | **Total Amount** | **$181,380.00** |
| **840574** | 200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M) | M | 11 | 1 | 1,160.00 | $1.50 | $1,740.00 |
| | | M | 12 | 1 | 80.00 | $3.45 | $276.00 |
| | **Unit Sub Total** | **M** | | **2** | **1,240.00** | **$1.63** | **$2,016.00** |
| | **Item Code 840574 Total No. of Proj.** | | | **2** | | **Total Amount** | **$2,016.00** |
| **840575** | 100 MM TWO-COMPONENT PAINT TRAFFIC STRIPE | M | 3 | 1 | 11,600.00 | $7.00 | $81,200.00 |
| | | M | 7 | 1 | 630.00 | $48.00 | $30,240.00 |
| | **Unit Sub Total** | **M** | | **2** | **12,230.00** | **$9.11** | **$111,440.00** |
| | **Item Code 840575 Total No. of Proj.** | | | **2** | | **Total Amount** | **$111,440.00** |
| **840580** | 4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED) (BROKEN 17-7) | LF | 3 | 1 | 680.00 | $1.27 | $863.60 |
| | | LF | 9 | 1 | 9,520.00 | $2.05 | $19,516.00 |
| | **Unit Sub Total** | **LF** | | **2** | **10,200.00** | **$2.00** | **$20,379.60** |
| | **Item Code 840580 Total No. of Proj.** | | | **2** | | **Total Amount** | **$20,379.60** |
| **840581** | 4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED) | LF | 9 | 1 | 55,100.00 | $2.25 | $123,975.00 |
| | **Unit Sub Total** | **LF** | | **1** | **55,100.00** | **$2.25** | **$123,975.00** |
| | **Item Code 840581 Total No. of Proj.** | | | **1** | | **Total Amount** | **$123,975.00** |
| **840582** | 4" TWO-COMPONENT PAINT TRAFFIC STRIPE | LF | 3 | 12 | 1,315,670.00 | $0.60 | $794,654.00 |
| | | LF | 11 | 1 | 51,300.00 | $1.00 | $51,300.00 |
| | **Unit Sub Total** | **LF** | | **13** | **1,366,970.00** | **$0.62** | **$845,954.00** |
| | **Item Code 840582 Total No. of Proj.** | | | **13** | | **Total Amount** | **$845,954.00** |
| **840584** | 8" TWO-COMPONENT PAINT TRAFFIC STRIPE | LF | 3 | 2 | 12,730.00 | $0.82 | $10,493.70 |
| | **Unit Sub Total** | **LF** | | **2** | **12,730.00** | **$0.82** | **$10,493.70** |
| | **Item Code 840584 Total No. of Proj.** | | | **2** | | **Total Amount** | **$10,493.70** |
| **840600** | PAINTED TRAFFIC STRIPE | LF | 7 | 1 | 53,600.00 | $0.11 | $5,896.00 |
| | **Unit Sub Total** | **LF** | | **1** | **53,600.00** | **$0.11** | **$5,896.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 840600 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,896.00** |
| **840651** | PAINTED STALL LINES AND PAVEMENT MARKINGS | M2 | 1 | 1 | 26.00 | $204.00 | $5,304.00 |
| | **Unit Sub Total** | **M2** | | **1** | **26.00** | **$204.00** | **$5,304.00** |
| | **Item Code 840651 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,304.00** |
| **840653** | PAINT TRAFFIC STRIPE | LF | 7 | 1 | 6,780.00 | $0.15 | $1,017.00 |
| | | LF | 12 | 1 | 590.00 | $2.60 | $1,534.00 |
| | **Unit Sub Total** | **LF** | | **2** | **7,370.00** | **$0.35** | **$2,551.00** |
| **840653** | PAINT TRAFFIC STRIPE | M | 7 | 1 | 3,130.00 | $0.55 | $1,721.50 |
| | **Unit Sub Total** | **M** | | **1** | **3,130.00** | **$0.55** | **$1,721.50** |
| | **Item Code 840653 Total No. of Proj.** | | | **3** | | **Total Amount** | **$4,272.50** |
| **840655** | PAINT TRAFFIC STRIPE (1-COAT) | LF | 1 | 9 | 184,670.00 | $0.14 | $26,303.00 |
| | | LF | 2 | 1 | 1,950.00 | $0.82 | $1,599.00 |
| | | LF | 8 | 1 | 317,000.00 | $0.04 | $12,680.00 |
| | **Unit Sub Total** | **LF** | | **11** | **503,620.00** | **$0.08** | **$40,582.00** |
| **840655** | PAINT TRAFFIC STRIPE (1-COAT) | M | 1 | 1 | 5,890.00 | $0.40 | $2,356.00 |
| | | M | 11 | 1 | 48,000.00 | $0.32 | $15,360.00 |
| | **Unit Sub Total** | **M** | | **2** | **53,890.00** | **$0.33** | **$17,716.00** |
| | **Item Code 840655 Total No. of Proj.** | | | **13** | | **Total Amount** | **$58,298.00** |
| **840656** | PAINT TRAFFIC STRIPE (2-COAT) | LF | 2 | 1 | 1,230.00 | $2.00 | $2,460.00 |
| | | LF | 3 | 2 | 1,180.00 | $4.24 | $5,005.00 |
| | | LF | 4 | 1 | 23,300.00 | $0.50 | $11,650.00 |
| | | LF | 5 | 8 | 429,780.00 | $0.11 | $46,935.00 |
| | | LF | 6 | 3 | 520,880.00 | $0.16 | $81,450.00 |
| | | LF | 7 | 6 | 95,510.00 | $0.20 | $18,695.10 |
| | | LF | 8 | 3 | 212,200.00 | $0.14 | $28,650.00 |
| | | LF | 9 | 10 | 2,021,240.00 | $0.12 | $242,990.00 |
| | | LF | 10 | 1 | 1,770.00 | $1.00 | $1,770.00 |
| | | LF | 11 | 25 | 1,901,941.00 | $0.17 | $322,198.50 |
| | | LF | 12 | 6 | 280,810.00 | $0.09 | $25,997.20 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **LF** | | **66** | **5,489,841.00** | **$0.14** | **$787,800.80** |
| **840656** | PAINT TRAFFIC STRIPE (2-COAT) | M | 2 | 1 | 19,300.00 | $0.50 | $9,650.00 |
| | | M | 4 | 1 | 540.00 | $2.00 | $1,080.00 |
| | | M | 5 | 2 | 82,200.00 | $0.60 | $48,918.00 |
| | | M | 6 | 1 | 7,390.00 | $0.20 | $1,478.00 |
| | | M | 7 | 7 | 78,280.00 | $0.76 | $59,612.00 |
| | | M | 8 | 1 | 580.00 | $1.50 | $870.00 |
| | | M | 9 | 5 | 199,160.00 | $0.37 | $73,014.00 |
| | | M | 10 | 2 | 25,940.00 | $0.39 | $10,184.00 |
| | | M | 11 | 11 | 1,034,610.00 | $0.49 | $510,112.00 |
| | | M | 12 | 2 | 1,530.00 | $0.98 | $1,506.00 |
| | **Unit Sub Total** | **M** | | **33** | **1,449,530.00** | **$0.49** | **$716,424.00** |
| | **Item Code 840656 Total No. of Proj.** | | | **99** | | **Total Amount** | **$1,504,224.80** |
| **840660** | PAINT PAVEMENT MARKING | M2 | 7 | 1 | 270.00 | $10.00 | $2,700.00 |
| | | M2 | 11 | 1 | 94.00 | $30.00 | $2,820.00 |
| | **Unit Sub Total** | **M2** | | **2** | **364.00** | **$15.16** | **$5,520.00** |
| **840660** | PAINT PAVEMENT MARKING | SQFT | 8 | 1 | 430.00 | $1.75 | $753.02 |
| | | SQFT | 12 | 1 | 250.00 | $5.70 | $1,425.00 |
| | **Unit Sub Total** | **SQFT** | | **2** | **680.00** | **$3.20** | **$2,178.02** |
| | **Item Code 840660 Total No. of Proj.** | | | **4** | | **Total Amount** | **$7,698.02** |
| **840661** | TWO-COMPONENT PAINT PAVEMENT MARKING | M2 | 3 | 2 | 580.00 | $163.69 | $94,938.00 |
| | | M2 | 4 | 1 | 60.00 | $455.00 | $27,300.00 |
| | **Unit Sub Total** | **M2** | | **3** | **640.00** | **$191.00** | **$122,238.00** |
| **840661** | TWO-COMPONENT PAINT PAVEMENT MARKING | SQFT | 3 | 8 | 19,130.00 | $4.38 | $83,800.00 |
| | **Unit Sub Total** | **SQFT** | | **8** | **19,130.00** | **$4.38** | **$83,800.00** |
| | **Item Code 840661 Total No. of Proj.** | | | **11** | | **Total Amount** | **$206,038.00** |
| **840666** | PAINT PAVEMENT MARKING (2-COAT) | M2 | 2 | 1 | 41.00 | $110.00 | $4,510.00 |
| | | M2 | 3 | 1 | 120.00 | $60.00 | $7,200.00 |
| | | M2 | 4 | 1 | 90.00 | $35.00 | $3,150.00 |
| | | M2 | 5 | 2 | 320.00 | $33.88 | $10,840.00 |
| | | M2 | 6 | 1 | 540.00 | $18.00 | $9,720.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **840666** | PAINT PAVEMENT MARKING (2-COAT) | M2 | 7 | 1 | 240.00 | $18.00 | $4,320.00 |
| | | M2 | 8 | 1 | 9.00 | $49.00 | $441.00 |
| | | M2 | 9 | 1 | 17.00 | $22.00 | $374.00 |
| | | M2 | 10 | 2 | 260.00 | $14.80 | $3,848.00 |
| | | M2 | 11 | 2 | 258.00 | $18.99 | $4,900.00 |
| | | M2 | 12 | 1 | 44.00 | $30.00 | $1,320.00 |
| | **Unit Sub Total** | **M2** | | **14** | **1,939.00** | **$26.11** | **$50,623.00** |
| **840666** | PAINT PAVEMENT MARKING (2-COAT) | SQFT | 2 | 1 | 110.00 | $10.30 | $1,133.00 |
| | | SQFT | 4 | 1 | 45.00 | $20.00 | $900.00 |
| | | SQFT | 6 | 2 | 2,290.00 | $2.00 | $4,580.00 |
| | | SQFT | 7 | 2 | 104.00 | $2.69 | $280.00 |
| | | SQFT | 9 | 5 | 14,914.00 | $2.05 | $30,565.30 |
| | | SQFT | 12 | 3 | 5,370.00 | $1.34 | $7,185.00 |
| | **Unit Sub Total** | **SQFT** | | **14** | **22,833.00** | **$1.96** | **$44,643.30** |
| | **Item Code 840666 Total No. of Proj.** | | | **28** | | **Total Amount** | **$95,266.30** |
| **842000** | PARKING BUMPER (PRECAST CONCRETE) | EA | 8 | 3 | 107.00 | $43.31 | $4,634.00 |
| | | EA | 11 | 1 | 5.00 | $115.00 | $575.00 |
| | **Unit Sub Total** | **EA** | | **4** | **112.00** | **$46.51** | **$5,209.00** |
| | **Item Code 842000 Total No. of Proj.** | | | **4** | | **Total Amount** | **$5,209.00** |
| **850101** | PAVEMENT MARKER (NON-REFLECTIVE) | EA | 1 | 12 | 24,830.00 | $3.19 | $79,107.00 |
| | | EA | 2 | 1 | 2,200.00 | $2.50 | $5,500.00 |
| | | EA | 3 | 6 | 16,695.00 | $2.96 | $49,387.50 |
| | | EA | 4 | 29 | 147,590.00 | $2.04 | $300,932.00 |
| | | EA | 5 | 20 | 49,168.00 | $1.28 | $62,910.40 |
| | | EA | 6 | 1 | 420.00 | $1.00 | $420.00 |
| | | EA | 7 | 28 | 104,358.00 | $1.31 | $136,933.40 |
| | | EA | 8 | 16 | 113,680.00 | $1.06 | $120,992.10 |
| | | EA | 10 | 2 | 114.00 | $2.07 | $236.00 |
| | | EA | 11 | 27 | 221,132.00 | $1.24 | $273,197.00 |
| | | EA | 12 | 19 | 75,995.00 | $1.15 | $87,134.50 |
| | **Unit Sub Total** | **EA** | | **161** | **756,182.00** | **$1.48** | **$1,116,749.90** |
| | **Item Code 850101 Total No. of Proj.** | | | **161** | | **Total Amount** | **$1,116,749.90** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **850102** | PAVEMENT MARKER (REFLECTIVE) | EA | 3 | 1 | 130.00 | $4.25 | $552.50 |
| | | EA | 4 | 1 | 11,800.00 | $3.00 | $35,400.00 |
| | **Unit Sub Total** | **EA** | | **2** | **11,930.00** | **$3.01** | **$35,952.50** |
| | **Item Code 850102 Total No. of Proj.** | | | **2** | | **Total Amount** | **$35,952.50** |
| **850103** | PAVEMENT MARKER (REFLECTIVE-SPECIAL TYPE G) | EA | 4 | 1 | 1,580.00 | $3.00 | $4,740.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1,580.00** | **$3.00** | **$4,740.00** |
| | **Item Code 850103 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,740.00** |
| **850104** | PAVEMENT MARKER (REFLECTIVE-SPECIAL TYPE H) | EA | 4 | 1 | 1,150.00 | $4.00 | $4,600.00 |
| | **Unit Sub Total** | **EA** | | **1** | **1,150.00** | **$4.00** | **$4,600.00** |
| | **Item Code 850104 Total No. of Proj.** | | | **1** | | **Total Amount** | **$4,600.00** |
| **850111** | PAVEMENT MARKER (RETROREFLECTIVE) | EA | 1 | 21 | 37,401.00 | $3.12 | $116,716.50 |
| | | EA | 2 | 9 | 27,356.00 | $4.26 | $116,605.00 |
| | | EA | 3 | 34 | 92,085.00 | $3.86 | $355,145.90 |
| | | EA | 4 | 48 | 93,976.00 | $3.60 | $338,542.20 |
| | | EA | 5 | 31 | 55,113.00 | $2.90 | $159,912.00 |
| | | EA | 6 | 31 | 55,903.00 | $3.63 | $203,043.70 |
| | | EA | 7 | 49 | 105,162.00 | $2.68 | $282,003.40 |
| | | EA | 8 | 29 | 73,177.00 | $2.51 | $183,378.70 |
| | | EA | 10 | 33 | 45,530.00 | $3.20 | $145,886.30 |
| | | EA | 11 | 35 | 126,623.00 | $2.93 | $370,699.82 |
| | | EA | 12 | 29 | 59,928.00 | $2.48 | $148,646.91 |
| | **Unit Sub Total** | **EA** | | **349** | **772,254.00** | **$3.13** | **$2,420,580.43** |
| | **Item Code 850111 Total No. of Proj.** | | | **349** | | **Total Amount** | **$2,420,580.43** |
| **850112** | PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE G) | EA | 4 | 2 | 190.00 | $7.29 | $1,385.00 |
| | | EA | 7 | 1 | 150.00 | $2.70 | $405.00 |
| | **Unit Sub Total** | **EA** | | **3** | **340.00** | **$5.26** | **$1,790.00** |
| | **Item Code 850112 Total No. of Proj.** | | | **3** | | **Total Amount** | **$1,790.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **850113** | PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE H) | EA | 7 | 1 | 180.00 | $2.70 | $486.00 |
| | **Unit Sub Total** | **EA** | | **1** | **180.00** | **$2.70** | **$486.00** |
| | **Item Code 850113 Total No. of Proj.** | | | **1** | | **Total Amount** | **$486.00** |
| **850121** | PAVEMENT MARKER (NON-REFLECTIVE-RECESSED) | EA | 2 | 1 | 30.00 | $10.00 | $300.00 |
| | **Unit Sub Total** | **EA** | | **1** | **30.00** | **$10.00** | **$300.00** |
| | **Item Code 850121 Total No. of Proj.** | | | **1** | | **Total Amount** | **$300.00** |
| **850122** | PAVEMENT MARKER (RETROREFLECTIVE-RECESSED) | EA | 1 | 9 | 12,150.00 | $8.66 | $105,255.00 |
| | | EA | 2 | 20 | 45,154.00 | $8.15 | $367,844.50 |
| | | EA | 3 | 4 | 705.00 | $26.55 | $18,716.00 |
| | | EA | 6 | 4 | 21,460.00 | $7.75 | $166,320.00 |
| | | EA | 7 | 1 | 870.00 | $7.00 | $6,090.00 |
| | | EA | 8 | 12 | 34,708.00 | $6.08 | $210,925.00 |
| | **Unit Sub Total** | **EA** | | **50** | **115,047.00** | **$7.61** | **$875,150.50** |
| | **Item Code 850122 Total No. of Proj.** | | | **50** | | **Total Amount** | **$875,150.50** |
| **860090** | MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION | LS | 1 | 17 | 17.00 | $1,878.53 | $31,935.00 |
| | | LS | 2 | 12 | 12.00 | $3,575.08 | $42,901.00 |
| | | LS | 3 | 28 | 28.00 | $4,026.34 | $112,737.50 |
| | | LS | 4 | 22 | 22.00 | $2,913.65 | $64,100.31 |
| | | LS | 5 | 15 | 15.00 | $4,781.02 | $71,715.25 |
| | | LS | 6 | 32 | 32.00 | $1,433.94 | $45,886.00 |
| | | LS | 7 | 62 | 62.00 | $2,762.10 | $171,249.94 |
| | | LS | 8 | 15 | 15.00 | $2,833.83 | $42,507.51 |
| | | LS | 9 | 3 | 3.00 | $916.67 | $2,750.00 |
| | | LS | 10 | 20 | 20.00 | $1,695.55 | $33,911.00 |
| | | LS | 11 | 44 | 44.00 | $2,160.51 | $95,062.41 |
| | | LS | 12 | 33 | 33.00 | $1,879.10 | $62,010.16 |
| | **Unit Sub Total** | **LS** | | **303** | **303.00** | **$2,563.58** | **$776,766.08** |
| | **Item Code 860090 Total No. of Proj.** | | | **303** | | **Total Amount** | **$776,766.08** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **860150** | SIGNAL AND LIGHTING (TEMPORARY) | LS | 3 | 1 | 1.00 | $11,000.00 | $11,000.00 |
| | | LS | 7 | 1 | 1.00 | $70,000.00 | $70,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$40,500.00** | **$81,000.00** |
| | **Item Code 860150 Total No. of Proj.** | | | **2** | | **Total Amount** | **$81,000.00** |
| **860201** | SIGNAL AND LIGHTING | LS | 3 | 1 | 1.00 | $114,000.00 | $114,000.00 |
| | | LS | 4 | 1 | 1.00 | $95,000.00 | $95,000.00 |
| | | LS | 5 | 1 | 1.00 | $189,000.00 | $189,000.00 |
| | | LS | 6 | 2 | 2.00 | $176,000.00 | $352,000.00 |
| | | LS | 7 | 2 | 2.00 | $140,300.00 | $280,600.00 |
| | | LS | 8 | 5 | 5.00 | $193,605.88 | $968,029.40 |
| | | LS | 10 | 5 | 5.00 | $153,386.60 | $766,933.00 |
| | | LS | 11 | 4 | 4.00 | $131,950.00 | $527,800.00 |
| | | LS | 12 | 5 | 5.00 | $90,936.52 | $454,682.60 |
| | **Unit Sub Total** | **LS** | | **26** | **26.00** | **$144,155.58** | **$3,748,045.00** |
| | **Item Code 860201 Total No. of Proj.** | | | **26** | | **Total Amount** | **$3,748,045.00** |
| **860251** | SIGNAL AND LIGHTING (LOCATION 1) | LS | 2 | 1 | 1.00 | $200,000.00 | $200,000.00 |
| | | LS | 3 | 2 | 2.00 | $125,000.00 | $250,000.00 |
| | | LS | 4 | 3 | 3.00 | $105,000.00 | $315,000.00 |
| | | LS | 11 | 7 | 7.00 | $128,714.29 | $901,000.00 |
| | **Unit Sub Total** | **LS** | | **13** | **13.00** | **$128,153.85** | **$1,666,000.00** |
| | **Item Code 860251 Total No. of Proj.** | | | **13** | | **Total Amount** | **$1,666,000.00** |
| **860252** | SIGNAL AND LIGHTING (LOCATION 2) | LS | 3 | 2 | 2.00 | $125,000.00 | $250,000.00 |
| | | LS | 4 | 3 | 3.00 | $115,000.00 | $345,000.00 |
| | | LS | 11 | 7 | 7.00 | $123,285.71 | $863,000.00 |
| | **Unit Sub Total** | **LS** | | **12** | **12.00** | **$121,500.00** | **$1,458,000.00** |
| | **Item Code 860252 Total No. of Proj.** | | | **12** | | **Total Amount** | **$1,458,000.00** |
| **860253** | SIGNAL AND LIGHTING (LOCATION 3) | LS | 3 | 1 | 1.00 | $100,000.00 | $100,000.00 |
| | | LS | 11 | 4 | 4.00 | $152,750.00 | $611,000.00 |
| | **Unit Sub Total** | **LS** | | **5** | **5.00** | **$142,200.00** | **$711,000.00** |
| | **Item Code 860253 Total No. of Proj.** | | | **5** | | **Total Amount** | **$711,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **860254** | SIGNAL AND LIGHTING (LOCATION 4) | LS | 3 | 1 | 1.00 | $150,000.00 | $150,000.00 |
| | | LS | 11 | 3 | 3.00 | $147,000.00 | $441,000.00 |
| | **Unit Sub Total** | **LS** | | **4** | **4.00** | **$147,750.00** | **$591,000.00** |
| | **Item Code 860254 Total No. of Proj.** | | | **4** | | **Total Amount** | **$591,000.00** |
| **860255** | SIGNAL AND LIGHTING (LOCATION 5) | LS | 3 | 1 | 1.00 | $400,000.00 | $400,000.00 |
| | | LS | 11 | 2 | 2.00 | $160,000.00 | $320,000.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$240,000.00** | **$720,000.00** |
| | **Item Code 860255 Total No. of Proj.** | | | **3** | | **Total Amount** | **$720,000.00** |
| **860256** | SIGNAL AND LIGHTING (LOCATION 6) | LS | 3 | 1 | 1.00 | $300,000.00 | $300,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$300,000.00** | **$300,000.00** |
| | **Item Code 860256 Total No. of Proj.** | | | **1** | | **Total Amount** | **$300,000.00** |
| **860257** | SIGNAL AND LIGHTING (LOCATION 7) | LS | 3 | 1 | 1.00 | $300,000.00 | $300,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$300,000.00** | **$300,000.00** |
| | **Item Code 860257 Total No. of Proj.** | | | **1** | | **Total Amount** | **$300,000.00** |
| **860297** | SIGNAL AND LIGHTING (CITY) | LS | 5 | 1 | 1.00 | $212,800.00 | $212,800.00 |
| | | LS | 11 | 1 | 1.00 | $40,000.00 | $40,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$126,400.00** | **$252,800.00** |
| | **Item Code 860297 Total No. of Proj.** | | | **2** | | **Total Amount** | **$252,800.00** |
| **860298** | SIGNAL AND LIGHTING (STAGE CONSTRUCTION) | LS | 3 | 1 | 1.00 | $50,000.00 | $50,000.00 |
| | | LS | 4 | 1 | 1.00 | $40,000.00 | $40,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$45,000.00** | **$90,000.00** |
| | **Item Code 860298 Total No. of Proj.** | | | **2** | | **Total Amount** | **$90,000.00** |
| **860300** | SIGNAL AND LIGHTING (CITY STREET LOCATION 1) | LS | 11 | 1 | 1.00 | $160,000.00 | $160,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$160,000.00** | **$160,000.00** |
| | **Item Code 860300 Total No. of Proj.** | | | **1** | | **Total Amount** | **$160,000.00** |
| **860301** | SIGNAL AND LIGHTING | LS | 6 | 2 | 2.00 | $192,794.00 | $385,588.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **860301** | SIGNAL AND LIGHTING | LS | 7 | 3 | 3.00 | $103,524.67 | $310,574.00 |
| | **Unit Sub Total** | **LS** | | **5** | **5.00** | **$139,232.40** | **$696,162.00** |
| | **Item Code 860301 Total No. of Proj.** | | | **5** | | **Total Amount** | **$696,162.00** |
| **860302** | SIGNAL AND LIGHTING (CITY STREET LOCATION 2) | LS | 10 | 1 | 1.00 | $45,000.00 | $45,000.00 |
| | | LS | 11 | 1 | 1.00 | $100,000.00 | $100,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$72,500.00** | **$145,000.00** |
| | **Item Code 860302 Total No. of Proj.** | | | **2** | | **Total Amount** | **$145,000.00** |
| **860303** | SIGNAL AND LIGHTING (CITY STREET LOCATION 3) | LS | 2 | 1 | 1.00 | $200,000.00 | $200,000.00 |
| | | LS | 10 | 1 | 1.00 | $45,000.00 | $45,000.00 |
| | | LS | 11 | 1 | 1.00 | $10,000.00 | $10,000.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$85,000.00** | **$255,000.00** |
| | **Item Code 860303 Total No. of Proj.** | | | **3** | | **Total Amount** | **$255,000.00** |
| **860304** | SIGNAL AND LIGHTING (CITY STREET LOCATION 4) | LS | 2 | 1 | 1.00 | $120,000.00 | $120,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$120,000.00** | **$120,000.00** |
| | **Item Code 860304 Total No. of Proj.** | | | **1** | | **Total Amount** | **$120,000.00** |
| **860400** | LIGHTING (TEMPORARY) | LS | 1 | 1 | 1.00 | $88,000.00 | $88,000.00 |
| | | LS | 3 | 2 | 2.00 | $13,500.00 | $27,000.00 |
| | | LS | 4 | 2 | 2.00 | $27,500.00 | $55,000.00 |
| | | LS | 7 | 4 | 4.00 | $73,375.00 | $293,500.00 |
| | | LS | 11 | 1 | 1.00 | $370,000.00 | $370,000.00 |
| | **Unit Sub Total** | **LS** | | **10** | **10.00** | **$83,350.00** | **$833,500.00** |
| | **Item Code 860400 Total No. of Proj.** | | | **10** | | **Total Amount** | **$833,500.00** |
| **860401** | LIGHTING | LS | 1 | 1 | 1.00 | $235,000.00 | $235,000.00 |
| | | LS | 3 | 3 | 3.00 | $271,933.33 | $815,800.00 |
| | | LS | 4 | 2 | 2.00 | $17,100.00 | $34,200.00 |
| | | LS | 7 | 1 | 1.00 | $150,000.00 | $150,000.00 |
| | | LS | 9 | 1 | 1.00 | $553,000.00 | $553,000.00 |
| | | LS | 10 | 2 | 2.00 | $36,165.00 | $72,330.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **860401** | LIGHTING | LS | 11 | 1 | 1.00 | $188,000.00 | $188,000.00 |
| | | LS | 12 | 1 | 1.00 | $45,000.00 | $45,000.00 |
| | **Unit Sub Total** | **LS** | | **12** | **12.00** | **$174,444.17** | **$2,093,330.00** |
| | **Item Code 860401 Total No. of Proj.** | | | **12** | | **Total Amount** | **$2,093,330.00** |
| **860402** | LIGHTING (CITY STREET) | LS | 3 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | | LS | 4 | 1 | 1.00 | $15,000.00 | $15,000.00 |
| | | LS | 5 | 1 | 1.00 | $427,500.00 | $427,500.00 |
| | | LS | 6 | 1 | 1.00 | $355,000.00 | $355,000.00 |
| | | LS | 11 | 5 | 5.00 | $191,600.00 | $958,000.00 |
| | **Unit Sub Total** | **LS** | | **9** | **9.00** | **$197,833.33** | **$1,780,500.00** |
| | **Item Code 860402 Total No. of Proj.** | | | **9** | | **Total Amount** | **$1,780,500.00** |
| **860403** | HIGHWAY LIGHTING | LS | 1 | 1 | 1.00 | $40,000.00 | $40,000.00 |
| | | LS | 4 | 1 | 1.00 | $38,700.00 | $38,700.00 |
| | | LS | 6 | 5 | 5.00 | $34,412.00 | $172,060.00 |
| | **Unit Sub Total** | **LS** | | **7** | **7.00** | **$35,822.86** | **$250,760.00** |
| | **Item Code 860403 Total No. of Proj.** | | | **7** | | **Total Amount** | **$250,760.00** |
| **860415** | LIGHTING (STAGE CONSTRUCTION) | LS | 3 | 1 | 1.00 | $200,000.00 | $200,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$200,000.00** | **$200,000.00** |
| | **Item Code 860415 Total No. of Proj.** | | | **1** | | **Total Amount** | **$200,000.00** |
| **860420** | LIGHTING (TUNNEL) | LS | 11 | 1 | 1.00 | $124,000.00 | $124,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$124,000.00** | **$124,000.00** |
| | **Item Code 860420 Total No. of Proj.** | | | **1** | | **Total Amount** | **$124,000.00** |
| **860460** | LIGHTING AND SIGN ILLUMINATION | LS | 2 | 1 | 1.00 | $565,000.00 | $565,000.00 |
| | | LS | 3 | 2 | 2.00 | $237,500.00 | $475,000.00 |
| | | LS | 4 | 2 | 2.00 | $472,000.00 | $944,000.00 |
| | | LS | 7 | 1 | 1.00 | $170,500.00 | $170,500.00 |
| | | LS | 8 | 1 | 1.00 | $1,305,600.00 | $1,305,600.00 |
| | | LS | 10 | 2 | 2.00 | $203,955.00 | $407,910.00 |
| | | LS | 11 | 10 | 10.00 | $471,626.79 | $4,716,267.91 |
| | | LS | 12 | 3 | 3.00 | $81,000.00 | $243,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **LS** | | **22** | **22.00** | **$401,239.91** | **$8,827,277.91** |
| | **Item Code 860460 Total No. of Proj.** | | | **22** | | **Total Amount** | **$8,827,277.91** |
| **860461** | LIGHTING (LOCATION 1) | LS | 2 | 1 | 1.00 | $118,800.00 | $118,800.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$118,800.00** | **$118,800.00** |
| | **Item Code 860461 Total No. of Proj.** | | | **1** | | **Total Amount** | **$118,800.00** |
| **860462** | LIGHTING (LOCATION 2) | LS | 2 | 1 | 1.00 | $115,000.00 | $115,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$115,000.00** | **$115,000.00** |
| | **Item Code 860462 Total No. of Proj.** | | | **1** | | **Total Amount** | **$115,000.00** |
| **860501** | SIGN ILLUMINATION | LS | 3 | 3 | 3.00 | $34,083.33 | $102,250.00 |
| | | LS | 4 | 1 | 1.00 | $36,000.00 | $36,000.00 |
| | **Unit Sub Total** | **LS** | | **4** | **4.00** | **$34,562.50** | **$138,250.00** |
| | **Item Code 860501 Total No. of Proj.** | | | **4** | | **Total Amount** | **$138,250.00** |
| **860503** | EXTINGUISHABLE MESSAGE SIGN | LS | 3 | 1 | 1.00 | $45,000.00 | $45,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$45,000.00** | **$45,000.00** |
| | **Item Code 860503 Total No. of Proj.** | | | **1** | | **Total Amount** | **$45,000.00** |
| **860508** | MODIFY SIGN ILLUMINATION | LS | 3 | 2 | 2.00 | $67,800.00 | $135,600.00 |
| | | LS | 6 | 1 | 1.00 | $3,000.00 | $3,000.00 |
| | | LS | 7 | 3 | 3.00 | $47,500.00 | $142,500.00 |
| | **Unit Sub Total** | **LS** | | **6** | **6.00** | **$46,850.00** | **$281,100.00** |
| | **Item Code 860508 Total No. of Proj.** | | | **6** | | **Total Amount** | **$281,100.00** |
| **860520** | HIGHWAY ADVISORY RADIO SYSTEM | EA | 4 | 2 | 2.00 | $58,150.00 | $116,300.00 |
| | **Unit Sub Total** | **EA** | | **2** | **2.00** | **$58,150.00** | **$116,300.00** |
| **860520** | HIGHWAY ADVISORY RADIO SYSTEM | LS | 10 | 1 | 1.00 | $179,907.00 | $179,907.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$179,907.00** | **$179,907.00** |
| | **Item Code 860520 Total No. of Proj.** | | | **3** | | **Total Amount** | **$296,207.00** |
| **860530** | CHANGEABLE MESSAGE SIGN SYSTEM | LS | 3 | 2 | 2.00 | $16,500.00 | $33,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **860530** | CHANGEABLE MESSAGE SIGN SYSTEM | LS | 8 | 1 | 1.00 | $92,000.00 | $92,000.00 |
| | | LS | 10 | 1 | 1.00 | $26,600.00 | $26,600.00 |
| | | LS | 11 | 5 | 5.00 | $76,000.00 | $380,000.00 |
| | **Unit Sub Total** | **LS** | | **9** | **9.00** | **$59,066.67** | **$531,600.00** |
| | **Item Code 860530 Total No. of Proj.** | | | **9** | | **Total Amount** | **$531,600.00** |
| **860551** | LIGHTING AND SIGN ILLUMINATION (LOCATION 1) | LS | 4 | 1 | 1.00 | $150,000.00 | $150,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$150,000.00** | **$150,000.00** |
| | **Item Code 860551 Total No. of Proj.** | | | **1** | | **Total Amount** | **$150,000.00** |
| **860552** | LIGHTING AND SIGN ILLUMINATION (LOCATION 2) | LS | 4 | 1 | 1.00 | $250,000.00 | $250,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$250,000.00** | **$250,000.00** |
| | **Item Code 860552 Total No. of Proj.** | | | **1** | | **Total Amount** | **$250,000.00** |
| **860553** | LIGHTING AND SIGN ILLUMINATION (LOCATION 3) | LS | 4 | 1 | 1.00 | $400,000.00 | $400,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$400,000.00** | **$400,000.00** |
| | **Item Code 860553 Total No. of Proj.** | | | **1** | | **Total Amount** | **$400,000.00** |
| **860554** | LIGHTING AND SIGN ILLUMINATION (LOCATION 4) | LS | 4 | 1 | 1.00 | $350,000.00 | $350,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$350,000.00** | **$350,000.00** |
| | **Item Code 860554 Total No. of Proj.** | | | **1** | | **Total Amount** | **$350,000.00** |
| **860601** | FLASHING BEACON | LS | 1 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | | LS | 4 | 1 | 1.00 | $7,800.00 | $7,800.00 |
| | | LS | 6 | 1 | 1.00 | $46,200.00 | $46,200.00 |
| | | LS | 11 | 1 | 1.00 | $45,000.00 | $45,000.00 |
| | **Unit Sub Total** | **LS** | | **4** | **4.00** | **$31,000.00** | **$124,000.00** |
| | **Item Code 860601 Total No. of Proj.** | | | **4** | | **Total Amount** | **$124,000.00** |
| **860602** | FLASHING BEACON AND SIGN ILLUMINATION | LS | 7 | 1 | 1.00 | $50,000.00 | $50,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$50,000.00** | **$50,000.00** |
| | **Item Code 860602 Total No. of Proj.** | | | **1** | | **Total Amount** | **$50,000.00** |
| **860603** | FLASHING BEACON AND LIGHTING | LS | 4 | 1 | 1.00 | $100,000.00 | $100,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$100,000.00** | **$100,000.00** |
| | **Item Code 860603 Total No. of Proj.** | | | **1** | | **Total Amount** | **$100,000.00** |
| **860604** | FLASHING BEACON SYSTEM | LS | 11 | 2 | 2.00 | $52,543.00 | $105,086.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$52,543.00** | **$105,086.00** |
| | **Item Code 860604 Total No. of Proj.** | | | **2** | | **Total Amount** | **$105,086.00** |
| **860615** | MODIFY FLASHING BEACON | LS | 6 | 1 | 1.00 | $15,875.00 | $15,875.00 |
| | | LS | 7 | 1 | 1.00 | $13,000.00 | $13,000.00 |
| | | LS | 10 | 1 | 1.00 | $18,000.00 | $18,000.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$15,625.00** | **$46,875.00** |
| | **Item Code 860615 Total No. of Proj.** | | | **3** | | **Total Amount** | **$46,875.00** |
| **860701** | INTERCONNECTION CONDUIT AND CONDUCTOR | LS | 7 | 2 | 2.00 | $22,500.00 | $45,000.00 |
| | | LS | 12 | 1 | 1.00 | $6,000.00 | $6,000.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$17,000.00** | **$51,000.00** |
| | **Item Code 860701 Total No. of Proj.** | | | **3** | | **Total Amount** | **$51,000.00** |
| **860703** | INTERCONNECTION CONDUIT AND CABLE | LS | 3 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$25,000.00** | **$25,000.00** |
| | **Item Code 860703 Total No. of Proj.** | | | **1** | | **Total Amount** | **$25,000.00** |
| **860761** | LIGHTING CONDUIT (BRIDGE) | LS | 6 | 1 | 1.00 | $23,450.00 | $23,450.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$23,450.00** | **$23,450.00** |
| **860761** | LIGHTING CONDUIT (BRIDGE) | M | 7 | 1 | 1,540.00 | $60.00 | $92,400.00 |
| | | M | 11 | 1 | 1,040.00 | $50.00 | $52,000.00 |
| | **Unit Sub Total** | **M** | | **2** | **2,580.00** | **$55.97** | **$144,400.00** |
| | **Item Code 860761 Total No. of Proj.** | | | **3** | | **Total Amount** | **$167,850.00** |
| **860791** | COMMUNICATION CONDUIT | LS | 1 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | | LS | 11 | 1 | 1.00 | $285,000.00 | $285,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$155,000.00** | **$310,000.00** |
| | **Item Code 860791 Total No. of Proj.** | | | **2** | | **Total Amount** | **$310,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **860792** | COMMUNICATION CONDUIT (BRIDGE) | LS | 3 | 1 | 1.00 | $125,000.00 | $125,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$125,000.00** | **$125,000.00** |
| **860792** | COMMUNICATION CONDUIT (BRIDGE) | M | 7 | 2 | 1,350.00 | $140.48 | $189,650.00 |
| | **Unit Sub Total** | **M** | | **2** | **1,350.00** | **$140.48** | **$189,650.00** |
| | **Item Code 860792 Total No. of Proj.** | | | **3** | | **Total Amount** | **$314,650.00** |
| **860796** | SPRINKLER CONTROL CONDUIT (BRIDGE) | M | 5 | 1 | 78.00 | $151.00 | $11,778.00 |
| | | M | 11 | 7 | 3,375.00 | $50.92 | $171,850.00 |
| | **Unit Sub Total** | **M** | | **8** | **3,453.00** | **$53.18** | **$183,628.00** |
| | **Item Code 860796 Total No. of Proj.** | | | **8** | | **Total Amount** | **$183,628.00** |
| **860797** | ELECTRIC SERVICE (IRRIGATION) | LS | 2 | 1 | 1.00 | $10,000.00 | $10,000.00 |
| | | LS | 3 | 1 | 1.00 | $2,479.08 | $2,479.08 |
| | | LS | 4 | 1 | 1.00 | $1,205.00 | $1,205.00 |
| | | LS | 5 | 2 | 2.00 | $5,410.00 | $10,820.00 |
| | | LS | 6 | 4 | 4.00 | $68,434.75 | $273,739.00 |
| | | LS | 10 | 1 | 1.00 | $1,270.00 | $1,270.00 |
| | | LS | 11 | 4 | 4.00 | $9,227.15 | $36,908.59 |
| | **Unit Sub Total** | **LS** | | **14** | **14.00** | **$24,030.12** | **$336,421.67** |
| | **Item Code 860797 Total No. of Proj.** | | | **14** | | **Total Amount** | **$336,421.67** |
| **860798** | BOOSTER PUMP ELECTRICAL SYSTEM | LS | 2 | 1 | 1.00 | $10,000.00 | $10,000.00 |
| | | LS | 6 | 1 | 1.00 | $4,000.00 | $4,000.00 |
| | | LS | 10 | 1 | 1.00 | $1,270.00 | $1,270.00 |
| | | LS | 11 | 2 | 2.00 | $23,750.00 | $47,500.00 |
| | **Unit Sub Total** | **LS** | | **5** | **5.00** | **$12,554.00** | **$62,770.00** |
| | **Item Code 860798 Total No. of Proj.** | | | **5** | | **Total Amount** | **$62,770.00** |
| **860799** | BATTERY BACKUP SYSTEM | LS | 3 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$25,000.00** | **$25,000.00** |
| | **Item Code 860799 Total No. of Proj.** | | | **1** | | **Total Amount** | **$25,000.00** |
| **860810** | INDUCTIVE LOOP DETECTOR | EA | 2 | 1 | 28.00 | $300.00 | $8,400.00 |
| | | EA | 8 | 5 | 40.00 | $827.00 | $33,080.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **860810** | INDUCTIVE LOOP DETECTOR | EA | 11 | 5 | 211.00 | $416.19 | $87,817.08 |
| | | EA | 12 | 6 | 413.00 | $253.38 | $104,645.00 |
| | **Unit Sub Total** | **EA** | | **17** | **692.00** | **$338.07** | **$233,942.08** |
| **860810** | INDUCTIVE LOOP DETECTOR | LS | 5 | 2 | 2.00 | $9,760.00 | $19,520.00 |
| | | LS | 7 | 1 | 1.00 | $5,300.00 | $5,300.00 |
| | | LS | 12 | 6 | 6.00 | $27,080.49 | $162,482.95 |
| | **Unit Sub Total** | **LS** | | **9** | **9.00** | **$20,811.44** | **$187,302.95** |
| | **Item Code 860810 Total No. of Proj.** | | | **26** | | **Total Amount** | **$421,245.03** |
| **860811** | DETECTOR LOOP | EA | 5 | 1 | 2.00 | $3,500.00 | $7,000.00 |
| | | EA | 8 | 2 | 72.00 | $345.06 | $24,844.00 |
| | | EA | 9 | 1 | 2.00 | $2,200.00 | $4,400.00 |
| | **Unit Sub Total** | **EA** | | **4** | **76.00** | **$476.89** | **$36,244.00** |
| **860811** | DETECTOR LOOP | LS | 2 | 2 | 2.00 | $12,000.00 | $24,000.00 |
| | | LS | 5 | 2 | 2.00 | $16,905.00 | $33,810.00 |
| | | LS | 6 | 1 | 1.00 | $4,500.00 | $4,500.00 |
| | **Unit Sub Total** | **LS** | | **5** | **5.00** | **$12,462.00** | **$62,310.00** |
| | **Item Code 860811 Total No. of Proj.** | | | **9** | | **Total Amount** | **$98,554.00** |
| **860812** | MICROWAVE VEHICLE DETECTION SYSTEM | LS | 7 | 1 | 1.00 | $146,595.00 | $146,595.00 |
| | | LS | 8 | 1 | 1.00 | $716,990.00 | $716,990.00 |
| | | LS | 10 | 1 | 1.00 | $31,505.00 | $31,505.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$298,363.33** | **$895,090.00** |
| | **Item Code 860812 Total No. of Proj.** | | | **3** | | **Total Amount** | **$895,090.00** |
| **860889** | MODIFY TRAFFIC MONITORING STATION | LS | 2 | 1 | 1.00 | $24,000.00 | $24,000.00 |
| | | LS | 3 | 7 | 7.00 | $56,500.00 | $395,500.00 |
| | | LS | 6 | 1 | 1.00 | $15,000.00 | $15,000.00 |
| | | LS | 7 | 1 | 1.00 | $426,000.00 | $426,000.00 |
| | | LS | 8 | 2 | 2.00 | $24,950.00 | $49,900.00 |
| | | LS | 11 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | | LS | 12 | 1 | 1.00 | $12,500.00 | $12,500.00 |
| | **Unit Sub Total** | **LS** | | **14** | **14.00** | **$67,707.14** | **$947,900.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 860889 Total No. of Proj.** | | | **14** | | **Total Amount** | **$947,900.00** |
| **860890** | MODIFY TRAFFIC MONITORING STATION (COUNT) | LS | 1 | 1 | 1.00 | $3,000.00 | $3,000.00 |
| | | LS | 2 | 1 | 1.00 | $10,000.00 | $10,000.00 |
| | | LS | 3 | 6 | 6.00 | $40,317.17 | $241,903.00 |
| | | LS | 9 | 1 | 1.00 | $21,300.00 | $21,300.00 |
| | | LS | 10 | 1 | 1.00 | $19,000.00 | $19,000.00 |
| | | LS | 11 | 1 | 1.00 | $13,000.00 | $13,000.00 |
| | **Unit Sub Total** | **LS** | | **11** | **11.00** | **$28,018.45** | **$308,203.00** |
| | **Item Code 860890 Total No. of Proj.** | | | **11** | | **Total Amount** | **$308,203.00** |
| **860925** | TRAFFIC MONITORING STATION (COUNT) | LS | 2 | 1 | 1.00 | $52,000.00 | $52,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$52,000.00** | **$52,000.00** |
| | **Item Code 860925 Total No. of Proj.** | | | **1** | | **Total Amount** | **$52,000.00** |
| **860930** | TRAFFIC MONITORING STATION | LS | 1 | 1 | 1.00 | $45,000.00 | $45,000.00 |
| | | LS | 2 | 4 | 4.00 | $24,075.00 | $96,300.00 |
| | | LS | 3 | 2 | 2.00 | $60,587.50 | $121,175.00 |
| | | LS | 5 | 2 | 2.00 | $26,000.00 | $52,000.00 |
| | | LS | 6 | 4 | 4.00 | $16,070.00 | $64,280.00 |
| | | LS | 10 | 1 | 1.00 | $121,260.00 | $121,260.00 |
| | | LS | 11 | 2 | 2.00 | $66,000.00 | $132,000.00 |
| | **Unit Sub Total** | **LS** | | **16** | **16.00** | **$39,500.94** | **$632,015.00** |
| | **Item Code 860930 Total No. of Proj.** | | | **16** | | **Total Amount** | **$632,015.00** |
| **860931** | TRAFFIC MONITORING STATION (LOCATION 1) | LS | 4 | 1 | 1.00 | $15,000.00 | $15,000.00 |
| | | LS | 6 | 1 | 1.00 | $8,000.00 | $8,000.00 |
| | | LS | 7 | 1 | 1.00 | $79,900.00 | $79,900.00 |
| | | LS | 10 | 1 | 1.00 | $33,660.00 | $33,660.00 |
| | | LS | 11 | 8 | 8.00 | $62,100.00 | $496,800.00 |
| | **Unit Sub Total** | **LS** | | **12** | **12.00** | **$52,780.00** | **$633,360.00** |
| | **Item Code 860931 Total No. of Proj.** | | | **12** | | **Total Amount** | **$633,360.00** |
| **860932** | TRAFFIC MONITORING STATION (LOCATION 2) | LS | 4 | 1 | 1.00 | $15,000.00 | $15,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **860932** | TRAFFIC MONITORING STATION (LOCATION 2) | LS | 6 | 1 | 1.00 | $8,000.00 | $8,000.00 |
| | | LS | 7 | 1 | 1.00 | $75,600.00 | $75,600.00 |
| | | LS | 10 | 1 | 1.00 | $42,840.00 | $42,840.00 |
| | | LS | 11 | 8 | 8.00 | $65,037.50 | $520,300.00 |
| | **Unit Sub Total** | **LS** | | **12** | **12.00** | **$55,145.00** | **$661,740.00** |
| | **Item Code 860932 Total No. of Proj.** | | | **12** | | **Total Amount** | **$661,740.00** |
| **860933** | TRAFFIC MONITORING STATION (LOCATION 3) | LS | 4 | 1 | 1.00 | $15,000.00 | $15,000.00 |
| | | LS | 6 | 1 | 1.00 | $8,000.00 | $8,000.00 |
| | | LS | 7 | 1 | 1.00 | $17,300.00 | $17,300.00 |
| | | LS | 11 | 3 | 3.00 | $64,833.33 | $194,500.00 |
| | **Unit Sub Total** | **LS** | | **6** | **6.00** | **$39,133.33** | **$234,800.00** |
| | **Item Code 860933 Total No. of Proj.** | | | **6** | | **Total Amount** | **$234,800.00** |
| **860934** | TRAFFIC MONITORING STATION (LOCATION 4) | LS | 4 | 1 | 1.00 | $15,000.00 | $15,000.00 |
| | | LS | 11 | 1 | 1.00 | $53,400.00 | $53,400.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$34,200.00** | **$68,400.00** |
| | **Item Code 860934 Total No. of Proj.** | | | **2** | | **Total Amount** | **$68,400.00** |
| **860935** | TRAFFIC MONITORING STATION (LOCATION 5) | LS | 4 | 1 | 1.00 | $15,000.00 | $15,000.00 |
| | | LS | 11 | 1 | 1.00 | $60,700.00 | $60,700.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$37,850.00** | **$75,700.00** |
| | **Item Code 860935 Total No. of Proj.** | | | **2** | | **Total Amount** | **$75,700.00** |
| **860936** | TRAFFIC MONITORING STATION (LOCATION 6) | LS | 4 | 1 | 1.00 | $15,000.00 | $15,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$15,000.00** | **$15,000.00** |
| | **Item Code 860936 Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,000.00** |
| **860937** | TRAFFIC MONITORING STATION (LOCATION 7) | LS | 4 | 1 | 1.00 | $15,000.00 | $15,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$15,000.00** | **$15,000.00** |
| | **Item Code 860937 Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,000.00** |
| **860938** | TRAFFIC MONITORING STATION (LOCATION 8) | LS | 4 | 1 | 1.00 | $15,000.00 | $15,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$15,000.00** | **$15,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 860938 Total No. of Proj.** | | | **1** | | **Total Amount** | **$15,000.00** |
| **860990** | CLOSED CIRCUIT TELEVISION SYSTEM | LS | 2 | 1 | 1.00 | $50,000.00 | $50,000.00 |
| | | LS | 3 | 1 | 1.00 | $69,389.00 | $69,389.00 |
| | | LS | 5 | 1 | 1.00 | $16,000.00 | $16,000.00 |
| | | LS | 10 | 3 | 3.00 | $36,172.67 | $108,518.00 |
| | | LS | 11 | 1 | 1.00 | $65,000.00 | $65,000.00 |
| | **Unit Sub Total** | **LS** | | **7** | **7.00** | **$44,129.57** | **$308,907.00** |
| | **Item Code 860990 Total No. of Proj.** | | | **7** | | **Total Amount** | **$308,907.00** |
| **861088** | MODIFY RAMP METERING SYSTEM | LS | 3 | 3 | 3.00 | $78,633.33 | $235,900.00 |
| | | LS | 7 | 2 | 2.00 | $772,371.30 | $1,544,742.60 |
| | | LS | 8 | 1 | 1.00 | $18,000.00 | $18,000.00 |
| | | LS | 12 | 3 | 3.00 | $8,109.14 | $24,327.42 |
| | **Unit Sub Total** | **LS** | | **9** | **9.00** | **$202,552.22** | **$1,822,970.02** |
| | **Item Code 861088 Total No. of Proj.** | | | **9** | | **Total Amount** | **$1,822,970.02** |
| **861100** | RAMP METERING SYSTEM | LS | 2 | 1 | 1.00 | $80,000.00 | $80,000.00 |
| | | LS | 7 | 1 | 1.00 | $77,000.00 | $77,000.00 |
| | | LS | 8 | 1 | 1.00 | $84,000.00 | $84,000.00 |
| | | LS | 11 | 3 | 3.00 | $72,143.13 | $216,429.38 |
| | | LS | 12 | 1 | 1.00 | $4,700.00 | $4,700.00 |
| | **Unit Sub Total** | **LS** | | **7** | **7.00** | **$66,018.48** | **$462,129.38** |
| | **Item Code 861100 Total No. of Proj.** | | | **7** | | **Total Amount** | **$462,129.38** |
| **861101** | RAMP METERING SYSTEM (LOCATION 1) | LS | 3 | 1 | 1.00 | $75,000.00 | $75,000.00 |
| | | LS | 8 | 1 | 1.00 | $73,950.00 | $73,950.00 |
| | | LS | 11 | 7 | 7.00 | $73,857.14 | $517,000.00 |
| | **Unit Sub Total** | **LS** | | **9** | **9.00** | **$73,994.44** | **$665,950.00** |
| | **Item Code 861101 Total No. of Proj.** | | | **9** | | **Total Amount** | **$665,950.00** |
| **861102** | RAMP METERING SYSTEM (LOCATION 2) | LS | 3 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | | LS | 8 | 1 | 1.00 | $71,400.00 | $71,400.00 |
| | | LS | 11 | 7 | 7.00 | $70,428.57 | $493,000.00 |
| | **Unit Sub Total** | **LS** | | **9** | **9.00** | **$65,488.89** | **$589,400.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 861102 Total No. of Proj.** | | | **9** | | **Total Amount** | **$589,400.00** |
| **861103** | RAMP METERING SYSTEM (LOCATION 3) | LS | 3 | 1 | 1.00 | $25,000.00 | $25,000.00 |
| | | LS | 11 | 7 | 7.00 | $68,814.29 | $481,700.00 |
| | **Unit Sub Total** | **LS** | | **8** | **8.00** | **$63,337.50** | **$506,700.00** |
| | **Item Code 861103 Total No. of Proj.** | | | **8** | | **Total Amount** | **$506,700.00** |
| **861104** | RAMP METERING SYSTEM (LOCATION 4) | LS | 11 | 4 | 4.00 | $59,650.00 | $238,600.00 |
| | **Unit Sub Total** | **LS** | | **4** | **4.00** | **$59,650.00** | **$238,600.00** |
| | **Item Code 861104 Total No. of Proj.** | | | **4** | | **Total Amount** | **$238,600.00** |
| **861105** | RAMP METERING SYSTEM (LOCATION 5) | LS | 11 | 2 | 2.00 | $61,200.00 | $122,400.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$61,200.00** | **$122,400.00** |
| | **Item Code 861105 Total No. of Proj.** | | | **2** | | **Total Amount** | **$122,400.00** |
| **861203** | HIGH SPEED WEIGH-IN-MOTION SYSTEM | LS | 4 | 2 | 2.00 | $400,000.00 | $800,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$400,000.00** | **$800,000.00** |
| | **Item Code 861203 Total No. of Proj.** | | | **2** | | **Total Amount** | **$800,000.00** |
| **861290** | RELOCATE ELECTROLIER | EA | 6 | 1 | 1.00 | $2,000.00 | $2,000.00 |
| | | EA | 9 | 1 | 1.00 | $9,000.00 | $9,000.00 |
| | **Unit Sub Total** | **EA** | | **2** | **2.00** | **$5,500.00** | **$11,000.00** |
| | **Item Code 861290 Total No. of Proj.** | | | **2** | | **Total Amount** | **$11,000.00** |
| **861295** | RELOCATE EXTINGUISHABLE MESSAGE SIGN | LS | 1 | 1 | 1.00 | $1,000.00 | $1,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$1,000.00** | **$1,000.00** |
| | **Item Code 861295 Total No. of Proj.** | | | **1** | | **Total Amount** | **$1,000.00** |
| **861303** | RELOCATE FLASHING BEACON | EA | 9 | 1 | 2.00 | $5,000.00 | $10,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$5,000.00** | **$10,000.00** |
| | **Item Code 861303 Total No. of Proj.** | | | **1** | | **Total Amount** | **$10,000.00** |
| **861349** | REMOVE EXISTING SIGNAL SYSTEM | LS | 5 | 1 | 1.00 | $18,900.00 | $18,900.00 |
| | | LS | 8 | 1 | 1.00 | $20,826.00 | $20,826.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **861349** | REMOVE EXISTING SIGNAL SYSTEM | LS | 11 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$14,908.67** | **$44,726.00** |
| | **Item Code 861349 Total No. of Proj.** | | | **3** | | **Total Amount** | **$44,726.00** |
| **861490** | REMOVE FLASHING BEACON AND LIGHTING | LS | 3 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$5,000.00** | **$5,000.00** |
| | **Item Code 861490 Total No. of Proj.** | | | **1** | | **Total Amount** | **$5,000.00** |
| **861491** | MODIFY SIGNAL (LOCATION 1) | LS | 6 | 1 | 1.00 | $8,500.00 | $8,500.00 |
| | | LS | 10 | 1 | 1.00 | $18,380.00 | $18,380.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$13,440.00** | **$26,880.00** |
| | **Item Code 861491 Total No. of Proj.** | | | **2** | | **Total Amount** | **$26,880.00** |
| **861492** | MODIFY SIGNAL (LOCATION 2) | LS | 6 | 1 | 1.00 | $7,000.00 | $7,000.00 |
| | | LS | 10 | 1 | 1.00 | $11,735.00 | $11,735.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$9,367.50** | **$18,735.00** |
| | **Item Code 861492 Total No. of Proj.** | | | **2** | | **Total Amount** | **$18,735.00** |
| **861497** | MODIFY SIGNAL AND LIGHTING (LOCATION 1) | LS | 4 | 1 | 1.00 | $18,000.00 | $18,000.00 |
| | | LS | 5 | 2 | 2.00 | $53,975.00 | $107,950.00 |
| | | LS | 6 | 1 | 1.00 | $85,000.00 | $85,000.00 |
| | | LS | 8 | 1 | 1.00 | $25,500.00 | $25,500.00 |
| | | LS | 10 | 1 | 1.00 | $138,000.00 | $138,000.00 |
| | | LS | 11 | 1 | 1.00 | $20,000.00 | $20,000.00 |
| | | LS | 12 | 1 | 1.00 | $96,000.00 | $96,000.00 |
| | **Unit Sub Total** | **LS** | | **8** | **8.00** | **$61,306.25** | **$490,450.00** |
| | **Item Code 861497 Total No. of Proj.** | | | **8** | | **Total Amount** | **$490,450.00** |
| **861498** | MODIFY SIGNAL AND LIGHTING (LOCATION 2) | LS | 4 | 1 | 1.00 | $146,000.00 | $146,000.00 |
| | | LS | 5 | 2 | 2.00 | $100,532.50 | $201,065.00 |
| | | LS | 6 | 1 | 1.00 | $115,000.00 | $115,000.00 |
| | | LS | 8 | 1 | 1.00 | $40,800.00 | $40,800.00 |
| | | LS | 10 | 1 | 1.00 | $215,000.00 | $215,000.00 |
| | | LS | 11 | 1 | 1.00 | $50,000.00 | $50,000.00 |
| | | LS | 12 | 1 | 1.00 | $86,000.00 | $86,000.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **LS** | | **8** | **8.00** | **$106,733.13** | **$853,865.00** |
| | **Item Code 861498 Total No. of Proj.** | | | **8** | | **Total Amount** | **$853,865.00** |
| **861499** | MODIFY SIGNAL AND LIGHTING (LOCATION 3) | LS | 4 | 1 | 1.00 | $138,000.00 | $138,000.00 |
| | | LS | 5 | 1 | 1.00 | $17,000.00 | $17,000.00 |
| | | LS | 6 | 1 | 1.00 | $110,000.00 | $110,000.00 |
| | | LS | 8 | 1 | 1.00 | $7,650.00 | $7,650.00 |
| | | LS | 11 | 1 | 1.00 | $20,000.00 | $20,000.00 |
| | | LS | 12 | 1 | 1.00 | $62,000.00 | $62,000.00 |
| | **Unit Sub Total** | **LS** | | **6** | **6.00** | **$59,108.33** | **$354,650.00** |
| | **Item Code 861499 Total No. of Proj.** | | | **6** | | **Total Amount** | **$354,650.00** |
| **861500** | MODIFY SIGNAL AND LIGHTING (LOCATION 4) | LS | 4 | 1 | 1.00 | $135,000.00 | $135,000.00 |
| | | LS | 5 | 1 | 1.00 | $12,350.00 | $12,350.00 |
| | | LS | 6 | 1 | 1.00 | $40,000.00 | $40,000.00 |
| | | LS | 12 | 1 | 1.00 | $8,300.00 | $8,300.00 |
| | **Unit Sub Total** | **LS** | | **4** | **4.00** | **$48,912.50** | **$195,650.00** |
| | **Item Code 861500 Total No. of Proj.** | | | **4** | | **Total Amount** | **$195,650.00** |
| **861501** | MODIFY SIGNAL AND LIGHTING | LS | 1 | 2 | 2.00 | $138,246.00 | $276,492.00 |
| | | LS | 3 | 3 | 3.00 | $97,946.00 | $293,838.00 |
| | | LS | 4 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | | LS | 5 | 2 | 2.00 | $96,900.00 | $193,800.00 |
| | | LS | 7 | 4 | 4.00 | $50,022.87 | $200,091.49 |
| | | LS | 8 | 4 | 4.00 | $56,786.25 | $227,145.00 |
| | | LS | 10 | 3 | 3.00 | $404,171.00 | $1,212,513.00 |
| | | LS | 11 | 1 | 1.00 | $11,000.00 | $11,000.00 |
| | | LS | 12 | 3 | 3.00 | $64,166.67 | $192,500.00 |
| | **Unit Sub Total** | **LS** | | **23** | **23.00** | **$113,581.72** | **$2,612,379.49** |
| | **Item Code 861501 Total No. of Proj.** | | | **23** | | **Total Amount** | **$2,612,379.49** |
| **861502** | MODIFY SIGNAL | LS | 1 | 1 | 1.00 | $27,000.00 | $27,000.00 |
| | | LS | 2 | 1 | 1.00 | $27,500.00 | $27,500.00 |
| | | LS | 3 | 1 | 1.00 | $6,295.00 | $6,295.00 |
| | | LS | 4 | 1 | 1.00 | $45,900.00 | $45,900.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| **861502** | MODIFY SIGNAL | LS | 6 | 2 | 2.00 | $17,850.00 | $35,700.00 |
| | | LS | 7 | 1 | 1.00 | $10,120.35 | $10,120.35 |
| | | LS | 9 | 1 | 1.00 | $15,000.00 | $15,000.00 |
| | | LS | 10 | 2 | 2.00 | $10,625.00 | $21,250.00 |
| | **Unit Sub Total** | **LS** | | **10** | **10.00** | **$18,876.54** | **$188,765.35** |
| | **Item Code 861502 Total No. of Proj.** | | | **10** | | **Total Amount** | **$188,765.35** |
| **861503** | MODIFY LIGHTING | LS | 1 | 2 | 2.00 | $123,000.00 | $246,000.00 |
| | | LS | 3 | 1 | 1.00 | $46,300.00 | $46,300.00 |
| | | LS | 4 | 2 | 2.00 | $17,500.00 | $35,000.00 |
| | | LS | 5 | 6 | 6.00 | $71,766.67 | $430,600.00 |
| | | LS | 6 | 2 | 2.00 | $40,100.00 | $80,200.00 |
| | | LS | 7 | 3 | 3.00 | $69,333.33 | $208,000.00 |
| | | LS | 9 | 1 | 1.00 | $50,000.00 | $50,000.00 |
| | | LS | 10 | 2 | 2.00 | $7,250.00 | $14,500.00 |
| | | LS | 11 | 1 | 1.00 | $45,000.00 | $45,000.00 |
| | | LS | 12 | 1 | 1.00 | $11,150.00 | $11,150.00 |
| | **Unit Sub Total** | **LS** | | **21** | **21.00** | **$55,559.52** | **$1,166,750.00** |
| | **Item Code 861503 Total No. of Proj.** | | | **21** | | **Total Amount** | **$1,166,750.00** |
| **861504** | MODIFY LIGHTING AND SIGN ILLUMINATION | LS | 3 | 3 | 3.00 | $315,000.00 | $945,000.00 |
| | | LS | 4 | 2 | 2.00 | $147,500.00 | $295,000.00 |
| | | LS | 5 | 6 | 6.00 | $133,005.17 | $798,031.00 |
| | | LS | 6 | 1 | 1.00 | $15,000.00 | $15,000.00 |
| | | LS | 7 | 6 | 6.00 | $994,239.17 | $5,965,435.00 |
| | | LS | 8 | 2 | 2.00 | $149,036.00 | $298,072.00 |
| | | LS | 12 | 2 | 2.00 | $50,624.00 | $101,248.00 |
| | **Unit Sub Total** | **LS** | | **22** | **22.00** | **$382,626.64** | **$8,417,786.00** |
| | **Item Code 861504 Total No. of Proj.** | | | **22** | | **Total Amount** | **$8,417,786.00** |
| **861505** | MODIFY SIGNAL AND LIGHTING (LOCATION 5) | LS | 4 | 1 | 1.00 | $134,000.00 | $134,000.00 |
| | | LS | 5 | 1 | 1.00 | $65,925.00 | $65,925.00 |
| | | LS | 6 | 1 | 1.00 | $110,000.00 | $110,000.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$103,308.33** | **$309,925.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 861505 Total No. of Proj.** | | | **3** | | **Total Amount** | **$309,925.00** |
| **861506** | MODIFY SIGNAL AND LIGHTING (LOCATION 6) | LS | 4 | 1 | 1.00 | $135,000.00 | $135,000.00 |
| | | LS | 5 | 1 | 1.00 | $16,510.00 | $16,510.00 |
| | | LS | 6 | 1 | 1.00 | $40,000.00 | $40,000.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$63,836.67** | **$191,510.00** |
| | **Item Code 861506 Total No. of Proj.** | | | **3** | | **Total Amount** | **$191,510.00** |
| **861507** | MODIFY SIGNAL AND LIGHTING (LOCATION 7) | LS | 4 | 1 | 1.00 | $137,000.00 | $137,000.00 |
| | | LS | 5 | 1 | 1.00 | $81,400.00 | $81,400.00 |
| | | LS | 6 | 1 | 1.00 | $130,000.00 | $130,000.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$116,133.33** | **$348,400.00** |
| | **Item Code 861507 Total No. of Proj.** | | | **3** | | **Total Amount** | **$348,400.00** |
| **861508** | MODIFY SIGNAL AND LIGHTING (LOCATION 8) | LS | 4 | 1 | 1.00 | $136,000.00 | $136,000.00 |
| | | LS | 5 | 1 | 1.00 | $143,269.00 | $143,269.00 |
| | | LS | 6 | 1 | 1.00 | $120,000.00 | $120,000.00 |
| | **Unit Sub Total** | **LS** | | **3** | **3.00** | **$133,089.67** | **$399,269.00** |
| | **Item Code 861508 Total No. of Proj.** | | | **3** | | **Total Amount** | **$399,269.00** |
| **861509** | MODIFY SIGNAL AND LIGHTING (LOCATION 9) | LS | 4 | 1 | 1.00 | $134,000.00 | $134,000.00 |
| | | LS | 6 | 1 | 1.00 | $100,000.00 | $100,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$117,000.00** | **$234,000.00** |
| | **Item Code 861509 Total No. of Proj.** | | | **2** | | **Total Amount** | **$234,000.00** |
| **861511** | MODIFY LIGHTING (LOCATION 1) | LS | 1 | 1 | 1.00 | $134,000.00 | $134,000.00 |
| | | LS | 3 | 1 | 1.00 | $49,000.00 | $49,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$91,500.00** | **$183,000.00** |
| | **Item Code 861511 Total No. of Proj.** | | | **2** | | **Total Amount** | **$183,000.00** |
| **861512** | MODIFY LIGHTING (LOCATION 2) | LS | 1 | 1 | 1.00 | $123,000.00 | $123,000.00 |
| | | LS | 3 | 1 | 1.00 | $37,000.00 | $37,000.00 |
| | **Unit Sub Total** | **LS** | | **2** | **2.00** | **$80,000.00** | **$160,000.00** |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Item Code 861512 Total No. of Proj.** | | | **2** | | **Total Amount** | **$160,000.00** |
| **861513** | MODIFY LIGHTING (LOCATION 3) | LS | 1 | 1 | 1.00 | $137,000.00 | $137,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$137,000.00** | **$137,000.00** |
| | **Item Code 861513 Total No. of Proj.** | | | **1** | | **Total Amount** | **$137,000.00** |
| **862065** | REPLACE PULL BOX | LS | 4 | 1 | 1.00 | $73,000.00 | $73,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$73,000.00** | **$73,000.00** |
| | **Item Code 862065 Total No. of Proj.** | | | **1** | | **Total Amount** | **$73,000.00** |
| **867014** | 12 SINGLEMODE FIBER OPTIC CABLE | M | 7 | 1 | 900.00 | $3.93 | $3,537.00 |
| | | M | 8 | 1 | 200.00 | $7.00 | $1,400.00 |
| | **Unit Sub Total** | **M** | | **2** | **1,100.00** | **$4.49** | **$4,937.00** |
| | **Item Code 867014 Total No. of Proj.** | | | **2** | | **Total Amount** | **$4,937.00** |
| **867017** | 48 SINGLEMODE FIBER OPTIC CABLE | M | 7 | 1 | 8,130.00 | $4.80 | $39,024.00 |
| | **Unit Sub Total** | **M** | | **1** | **8,130.00** | **$4.80** | **$39,024.00** |
| | **Item Code 867017 Total No. of Proj.** | | | **1** | | **Total Amount** | **$39,024.00** |
| **867130** | FIBER OPTIC SPLICE CLOSURE | EA | 7 | 1 | 10.00 | $728.00 | $7,280.00 |
| | **Unit Sub Total** | **EA** | | **1** | **10.00** | **$728.00** | **$7,280.00** |
| | **Item Code 867130 Total No. of Proj.** | | | **1** | | **Total Amount** | **$7,280.00** |
| **868007** | REMOVE LIGHTING STANDARD | EA | 6 | 1 | 10.00 | $200.00 | $2,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **10.00** | **$200.00** | **$2,000.00** |
| **868007** | REMOVE LIGHTING STANDARD | LS | 3 | 1 | 1.00 | $5,000.00 | $5,000.00 |
| | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$5,000.00** | **$5,000.00** |
| | **Item Code 868007 Total No. of Proj.** | | | **2** | | **Total Amount** | **$7,000.00** |
| **869034** | NO. 5(T) PULL BOX | EA | 7 | 1 | 7.00 | $1,050.00 | $7,350.00 |
| | **Unit Sub Total** | **EA** | | **1** | **7.00** | **$1,050.00** | **$7,350.00** |
| | **Item Code 869034 Total No. of Proj.** | | | **1** | | **Total Amount** | **$7,350.00** |
| **869039** | COMMUNICATION PULL BOX | EA | 7 | 1 | 19.00 | $1,715.00 | $32,585.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | **Unit Sub Total** | **EA** | | **1** | **19.00** | **$1,715.00** | **$32,585.00** |
| | **Item Code 869039** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$32,585.00** |
| **869042** | ADJUST PULL BOX | | EA | 1 | 1 | 9.00 | $400.00 | $3,600.00 |
| | | | EA | 2 | 1 | 1.00 | $250.00 | $250.00 |
| | | | EA | 3 | 1 | 14.00 | $1,000.00 | $14,000.00 |
| | | | EA | 7 | 2 | 6.00 | $237.50 | $1,425.00 |
| | | | EA | 12 | 1 | 20.00 | $31.70 | $634.00 |
| | | **Unit Sub Total** | **EA** | | **6** | **50.00** | **$398.18** | **$19,909.00** |
| | **Item Code 869042** | **Total No. of Proj.** | | | **6** | | **Total Amount** | **$19,909.00** |
| **869043** | REMOVE PULL BOX | | EA | 12 | 1 | 2.00 | $125.00 | $250.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **2.00** | **$125.00** | **$250.00** |
| | **Item Code 869043** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$250.00** |
| **869047** | SPLICE VAULT | | EA | 7 | 1 | 5.00 | $5,716.00 | $28,580.00 |
| | | **Unit Sub Total** | **EA** | | **1** | **5.00** | **$5,716.00** | **$28,580.00** |
| | **Item Code 869047** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$28,580.00** |
| **869072** | SEISMIC MONITORING SYSTEM | | LS | 7 | 1 | 1.00 | $177,100.00 | $177,100.00 |
| | | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$177,100.00** | **$177,100.00** |
| | **Item Code 869072** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$177,100.00** |
| **869075** | SYSTEM TESTING AND DOCUMENTATION | | LS | 7 | 3 | 3.00 | $41,175.00 | $123,525.00 |
| | | | LS | 8 | 1 | 1.00 | $4,400.00 | $4,400.00 |
| | | **Unit Sub Total** | **LS** | | **4** | **4.00** | **$31,981.25** | **$127,925.00** |
| | **Item Code 869075** | **Total No. of Proj.** | | | **4** | | **Total Amount** | **$127,925.00** |
| **869080** | TRAINING | | LS | 3 | 1 | 1.00 | $3,100.00 | $3,100.00 |
| | | **Unit Sub Total** | **LS** | | **1** | **1.00** | **$3,100.00** | **$3,100.00** |
| | **Item Code 869080** | **Total No. of Proj.** | | | **1** | | **Total Amount** | **$3,100.00** |
| **993002** | FIRE HYDRANT | | EA | 10 | 1 | 11.00 | $500.00 | $5,500.00 |
| | | | EA | 11 | 2 | 4.00 | $2,265.00 | $9,060.00 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | **Unit Sub Total** | **EA** | | **3** | **15.00** | **$970.67** | **$14,560.00** |
| | **Item Code 993002 Total No. of Proj.** | | | **3** | | **Total Amount** | **$14,560.00** |
| **993013** | 150 MM FIRE HYDRANT ASSEMBLY | EA | 11 | 3 | 8.00 | $7,252.50 | $58,020.00 |
| | **Unit Sub Total** | **EA** | | **3** | **8.00** | **$7,252.50** | **$58,020.00** |
| | **Item Code 993013 Total No. of Proj.** | | | **3** | | **Total Amount** | **$58,020.00** |
| **994650** | BUILDING WORK | LS | 2 | 4 | 4.00 | $1,580,657.81 | $6,322,631.23 |
| | | LS | 3 | 5 | 5.00 | $2,277,841.00 | $11,389,205.00 |
| | | LS | 4 | 4 | 4.00 | $1,097,250.00 | $4,389,000.00 |
| | | LS | 5 | 2 | 2.00 | $1,915,700.00 | $3,831,400.00 |
| | | LS | 6 | 2 | 2.00 | $3,317,776.00 | $6,635,552.00 |
| | | LS | 8 | 5 | 5.00 | $4,363,127.00 | $21,815,635.00 |
| | | LS | 9 | 1 | 1.00 | $621,000.00 | $621,000.00 |
| | | LS | 10 | 2 | 2.00 | $2,902,415.00 | $5,804,830.00 |
| | | LS | 11 | 3 | 3.00 | $2,127,802.65 | $6,383,407.95 |
| | **Unit Sub Total** | **LS** | | **28** | **28.00** | **$2,399,737.90** | **$67,192,661.18** |
| | **Item Code 994650 Total No. of Proj.** | | | **28** | | **Total Amount** | **$67,192,661.18** |
| **995000** | BUS SHELTER | EA | 6 | 1 | 20.00 | $10,800.00 | $216,000.00 |
| | **Unit Sub Total** | **EA** | | **1** | **20.00** | **$10,800.00** | **$216,000.00** |
| | **Item Code 995000 Total No. of Proj.** | | | **1** | | **Total Amount** | **$216,000.00** |
| **999990** | MOBILIZATION | LS | 1 | 22 | 22.00 | $393,021.91 | $8,646,482.00 |
| | | LS | 2 | 15 | 15.00 | $701,336.90 | $10,520,053.50 |
| | | LS | 3 | 36 | 36.00 | $1,192,469.73 | $42,928,910.45 |
| | | LS | 4 | 54 | 54.00 | $497,976.54 | $26,890,733.00 |
| | | LS | 5 | 32 | 32.00 | $175,296.88 | $5,609,500.05 |
| | | LS | 6 | 20 | 20.00 | $223,645.37 | $4,472,907.45 |
| | | LS | 7 | 80 | 80.00 | $374,783.88 | $29,982,710.05 |
| | | LS | 8 | 22 | 22.00 | $405,420.25 | $8,919,245.40 |
| | | LS | 9 | 3 | 3.00 | $1,293,465.00 | $3,880,395.00 |
| | | LS | 10 | 18 | 18.00 | $291,040.56 | $5,238,730.05 |
| | | LS | 11 | 44 | 44.00 | $1,128,919.37 | $49,672,452.40 |
| | | LS | 12 | 22 | 22.00 | $94,350.30 | $2,075,706.67 |

## CONTRACT ITEM COST DATA

| ITEM CODE | ITEM DESCRIPTION | UNIT | DIST | NO. OF PROJ | QUANTITY | AVE PRICE PER UNIT | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|
| | Unit Sub Total | LS | | 368 | 368.00 | $540,320.18 | $198,837,826.02 |
| | Item Code 999990 Total No. of Proj. | | | 368 | | Total Amount | $198,837,826.02 |

# APPENDIX A

Conversion Factors From English Units to SI Units

| Unit | Abbr. | Multiply: | Unit | Abbr. |
|---|---|---|---|---|
| Acre | ACRE | 0.4046856 | Hectare | HA |
| Calendar Day | CDAY | 1 | Calendar Day | CDAY |
| Cubic Foot | CF | 0.02831685 | Cubic Meter | M3 |
| Cubic Yard | CY | 0.7645549 | Cubic Meter | M3 |
| Each | EA | 1 | Each | EA |
| Gallon | GAL | 3.785412 | Liter | L |
| Hour | HR | 1 | Hour | H |
| Pound | LB | 0.4535924 | Kilogram | KG |
| Linear Foot | LF | 0.3048 | Meter | M |
| Lane Mile | LNMI | 1.609344 | Lane Kilometer | LNKM |
| Lump Sum | LS | 1 | Lump Sum | LS |
| Thousand Foot Board Measure | MFBM | 2.359737 | Cubic Meter | M3 |
| Mile | MI | 1.609344 | Kilometer | KM |
| Square Foot | SQFT | 0.09290304 | Square Meter | M2 |
| Square Yard | SQYD | 0.8361274 | Square Meter | M2 |
| Station (100 Ft) | STA | 0.3048 | Station (100 m) | STA |
| Tablet | TAB | 1 | Tablet | TAB |
| Ton | TON | 0.9071847 | Tonne (1000 kg) | TONN |
| Track Foot | TF | 1 | Track Foot | TF |
| Working Day | WDAY | 1 | Working Day | WDAY |
| | | | | |

# APPENDIX B

Conversion Factors From SI Units to English Units

| Unit | Abbr. | Multiply: | Unit | Abbr. |
|---|---|---|---|---|
| Hectare | HA | 2.471054 | Acre | ACRE |
| Calendar Day | CDAY | 1 | Calendar Day | CDAY |
| Cubic Meter | M3 | 35.31467 | Cubic Foot | CF |
| Cubic Meter | M3 | 1.307951 | Cubic Yard | CY |
| Each | EA | 1 | Each | EA |
| Liter | L | 0.2641720 | Gallon | GAL |
| Hour | H | 1 | Hour | HR |
| Kilogram | KG | 2.204623 | Pound | LB |
| Meter | M | 3.280840 | Linear Foot | LF |
| Lane Kilometer | LNKM | 0.6213712 | Lane Mile | LNMI |
| Lump Sum | LS | 1 | Lump Sum | LS |
| Cubic Meter | M3 | 0.4237760 | Thousand Foot Board Measure | MFBM |
| Kilometer | KM | 0.6213712 | Mile | MI |
| Square Meter | M2 | 10.76391 | Square Foot | SQFT |
| Square Meter | M2 | 1.195990 | Square Yard | SQYD |
| Station (100 m) | STA | 3.280840 | Station (100 Ft) | STA |
| Tablet | TAB | 1 | Tablet | TAB |
| Tonne (1000 kg) | TONN | 1.102312 | Ton | TON |
| Track Foot | TF | 1 | Track Foot | TF |
| Working Day | WDAY | 1 | Working Day | WDAY |