

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
SN-000	Special Notice	Use if project has at least one Special Notice. Automatically inserted by boilerplate.	SAME CONTENT	SAME CONTENT	SN-000
SN-001	Special Notice	Used for projects that have risk advertisement pending budget and call out number is greater than or equal to \$25 million. Automatically inserted by boilerplate.	SAME CONTENT	SAME CONTENT	SN-001
SN-002	Special Notice	Used for projects that have risk advertisement pending budget and the call out number is less than \$25 million. Automatically inserted by boilerplate.	SAME CONTENT	SAME CONTENT	SN-002
SN-003	Special Notice	Use for projects that have SSPC QP certification	SAME CONTENT	SAME CONTENT	SN-003
SN-006	Special Notice	Use in all projects with Sacramento bid openings. Automatically inserted by boilerplate.	NO SN AT THIS TIME	SAME CONTENT	SN-012
SN-012	Special Notice	Use for building projects with federal aid. Automatically inserted by boilerplate.	SAME CONTENT	SAME CONTENT	SN-020
SN-016	Special Notice	Automatically inserted by boilerplate. Notification of LDs located in the amendments.	No SN needed for liquidated damages. LDs are in the standard specifications.	SAME CONTENT	SN-220
SN-020	Special Notice	Use when District anticipates the felling and removal of timber from within the limits of a construction project.	SAME CONTENT	Removed clause directing attention to sections 2, 3, 4 of the special provisions. Removed clause on when contractor to start work for infomal-bid projects.	SN-290
SN-025	Special Notice	Use in non-federal-aid projects. Automatically inserted by boilerplate.	No SN needed for DVBE requirements--attention is directed to. Requirements are in section 2.	SAME CONTENT	SN-310
SN-050	Special Notice	Use in projects with TERO requirements. District to include with	PENDING--WORKING ON TERO	Separate SNs for 315 and 405 in 2006.	SN-315

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
		special provisions.			
SN-213	Special Notice	Use if there is an Information Handout for the project. Automatically inserted by boilerplate.	No SN for where info handout material is located.	SAME CONTENT	SN-410
SN-220	Special Notice	Used in projects that have a mandatory prebid meeting. Automatically inserted by boilerplate.	SAME CONTENT	SAME CONTENT	SN-935
SN-290	Special Notice	Used for informal-bid projects. Automatically inserted by boilerplate.	Mandatory prebid site tour information is specified.	SAME CONTENT	SN-936
SN-310	Special Notice	Used in projects with 60-day award. Automatically inserted by boilerplate.	SAME CONTENT	Use for all projects. Not available in 2006.	0-SP
SN-315	Special Notice	Used for projects with Early Return / Early Start provisions and no ARRA funding. Automatically inserted by boilerplate.	Merged SN 315 and 405 into 2010 SN 315.	All new. List of bid item that does not correspond to the specification section. Add nonstandard bid items to the list. Not available in 2006.	1-1.01
SN-405	Special Notice	Used for projects with Early Return / Early Start provisions and no ARRA funding. Automatically inserted by boilerplate.	No longer needed. See SN 315.	Use for informal-bid contract with a 7-day work week. Go to SSP S4-002.	1-1.07B
SN-410	Special Notice	Use when SSP S4-008 or S4-009 is used. (Use for \$1 Projects.)	SAME CONTENT	Use for freeze-thaw areas. Individual SSPs addressed freeze-thaw areas in 2006.	1-1.09
SN-550	Special Notice	Use in projects with American Recovery and Reinvestment Act Federal-aid funds. Automatically inserted by boilerplate.	ARRA no longer supported after JANUARY 2012.	District requires mandatory prebid meeting. Go to SSP S2-100.	2-1.03
SN-714	Special Notice (Electronic Submission of Payroll Records)	Use in all projects. Automatically inserted by boilerplate.	No SN needed to notify contractors on electronic payroll--attention is directed to.	Use when supplemental project information is available.	2-1.06B

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
				Go to SSP S5-280.	
SN-935	Special Notice	Use for BATA projects that do not get funded until after bid opening.	SAME CONTENT	Use for a project with an estimated cost less than \$200 million with a 60-day award period or an informal-bid contract. Go to SSPs S3-070 and S3-080.	3-1.04
SN-936	Special Notice	This special notice is automatically inserted for Friday bid openings. If your project has a special bid opening date other than Friday, include this special notice, manually, and revise the bid opening time and location in the Notice to Bidders for your special case.	SAME CONTENT	Use for a same-day-award contract or a contract with an early return of documents and early start of work. Go to SSPs S3-090 and S3-092.	3-1.18
S1-000	Section 1 Title	Use in All projects. (inserted by boilerplate by DES-OE.)	No longer needed. 2010 use SSP SP as base template to assemble SSPs.	Use for a project with an estimated cost over \$10 million and with 100 or more working days. Go to SSP S5-155.	5-1.09A
S1-020H	Amendments to the May 2006 Standards Specifications	Use in All projects. DO NOT EDIT. (Inserted by DES-OE.)	New document name. 2010 use RSS document automatically inserted by boilerplate.	Use if work under other contracts is at or near the job site. Identify the other contracts. Go to SSP 07-850.	5-1.20A
S2-000	Section 2 title	Used in all projects. Automatically inserted by boilerplate.	No longer needed. 2010 use SSP SP as base template to assemble SSPs.	Use for right-of-way parcels that have not been cleared and may be occupied. Go to SSP 08-100.	5-1.20D
S2-050	SSPC QP Certification	Use if requested by District. For use with SSP 59-501. Automatically	Moved to the standard specifications.	Use if utilities are to be relocated during	5-1.36D

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
	Preaward Qualification	inserted by boilerplate.	Go to SS 2-1.35.	construction or if utilities are involved with pile driving, drilling, or substructure construction. Go to SSP S5-775.	
S2-100	Mandatory Prebid Meeting	Used as requested by the District. Automatically inserted by boilerplate.	Not automated. Go to SSP 2-1.03.	Use if (1) a bridge with a material hauling equipment lane is over 400 feet long (2) if the designer allows more than 1 piece of equipment on the bridge at one time. Insert number of pieces provided by designer. Go to SSP 07-600 and SSP 07-610.	5-1.37B(3)
S2-120	Small Business and Non-Small Business Subcontractor Preferences	Use in State-funded only projects. Automatically inserted by boilerplate.	Moved to the standard specifications. Go to SS 2-1.18.	Use for Department-furnished materials. Go to SSP S8-M10.	6-2.03
S2-130	Disabled Veteran Business Enterprises	Use in projects over \$5 million with no Federal aid. Automatically inserted by boilerplate.	Moved to standard specifications. Go to SS 2-1.15.	Use if scaffolding may be constructed over or adjacent to traffic. Go to SSP 07-640.	7-1.02K(6)(e)
S2-135	Disabled Veteran Business Enterprises	Use in projects \$5 million or less with no Federal aid. Automatically inserted by boilerplate.	Moved to standard specifications. Go to SS 2-1.15.	Use for earth material containing lead. Go to SSPs 15-027 and 19-900.	7-1.02K(6)(j)(ii) i)
S2-140	California Companies	Use in State-funded only projects. Automatically inserted by boilerplate.	Moved to the standard specifications. Go to SS 2-1.27.	Use for fire prevention. Go to SSP S5-690.	7-1.02M(2)

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
S2-145	Tie Bid Resolution	Use in all projects. Automatically inserted by boilerplate.	Moved to the standard specifications. Go to SS 2-1.24.	Use for special order of work requirements. Go to SSPs 05-xxx.	8-1.02A
S2-150	Disadvantaged Business Enterprises	Use in projects with Federal-aid funds and UDBE goal. Inserted automatically by boilerplate.	Moved to the standard specifications. Go to SS 2-1.12.	Use for a project with an estimated cost from \$1 to \$5 million and over 250 working days if requested by the district. Go to SSP 08-012.	8-1.02C
S2-155	Disadvantaged Business Enterprises	Use in Federal-aid projects with no DBE goal. Inserted automatically by boilerplate.	Moved to the standard specifications. Go to SS 2-1.12.	Use for delayed start requirements. Go to SSP S4-003.	8-1.04C
S2-200	DVBE Information Submittal for Informal-bid Projects	Used in all projects. Automatically inserted by boilerplate.	Moved to the standard specifications. Go to SS 2-1.15.	Use for early return of documents and early start of work. Go to SSP S3-092.	8-1.04D
S2-300	Opt Out of Payment Adjustments for Price Index Fluctuations	Use in all projects. Automatically inserted by boilerplate	Moved to the standard specifications. Go to SS 2-1.33D.	Use for an informal-bid contract. Go to SSP S4-002.	8-1.04E
S3-000	Section 3 title	Used in all projects. Automatically inserted by boilerplate.	No longer needed. 2010 use 0-SP as base template to assemble SSPs.	Use for a highway maintenance or Minor A project with 50 working days or less. (Flexible Start) Go to SSP S4-004.	8-1.04F
S3-070	Contract Award	Used in projects with a 60 day contract award period. Automatically inserted by boilerplate.	Go to SSP 3-1.04	Use for a project with minimum financing in the 2010-2011 FY budget. Do not include for bid	8-1.04G

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
				openings after the 2011-2012 FY budget becomes law. Go to SSP S4-008.	
S3-080	Contract Award	Used for informal-bid projects that do not have same day award. Automatically inserted by boilerplate.	Go to SSP 3-1.04.	Use for (1) a highway maintenance or Minor A project with 50 working days or less or (2) a project with minimum financing in the 2010-2011 FY budget and 50 working days or less. Do not use for bid openings after the 2011-2012 FY budget becomes law. Go to SSPs S4-004 and S4-009.	8-1.05
S3-090	Contract Award and Contract Execution	Used for informal-bid projects that have same day award. Automatically inserted by boilerplate.	Go to SSP 3-1.04.	Add RUC for cost + time project. Go to SSP 08-018, SSP S4-001, and SSP S4-003.	8-1.10A
S3-092	Contract Execution	Used for Early Return / Early Start provisions and no ARRA funding. Automatically inserted by boilerplate.	Go to SSP 3-1.18, SSP 8-1.04D.	Use for work not completed in a specified time. Go to SSP S1-020, SS 8-1.07B.	8-1.10B
S3-100	Data Universal Numbering System (D-U-N-S) Number and Contract Execution	Used in projects with American Recovery and Reinvestment Act Federal-aid funds. Automatically inserted by boilerplate. Use until January 2012.	ARRA no longer supported after JANUARY 2012.	Use for work not completed by a specified date. Go to SSP S1-020, SS 8-1.07C.	8-1.10C
S3-200	Small Business	Use in all projects. Automatically	Moved to the standard	Use if building work is over	9-1.11

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
	Participation Report	inserted by boilerplate.	specifications. Go to SS 3-1.08.	50 percent of the estimated bid item total. Requirements from SSPs 08-017, and 08-018, are in the SS. This spec takes them out when building work is over 50% of the total.	
S3-300	Caltrans Bidder - DBE Information Form	Used in Federal-aid projects. Automatically inserted by boilerplate.	Moved to the standard specifications. Go to SS 3-1.12.	Use for items eligible for progress payment. Go to SSP S5-250.	9-1.16C
S4-001	Section 4. Beginning of Work, Time of Completion, And Liquidated Damages	This SSP is inserted by boiler plate in all standard Sections 1 through 4 packages. This SSP includes options for projects with plant establishment work and cost plus time bidding. The day for start of work is typically the 15th day. For projects with early return of documents and early start of work, the day for start of work is reduced to the 5th day. Data from the database is inserted in the appropriate locations during the merge process. Alternative Section 4 SSPs are available for special projects. This SSP is not used for Highway Planting Projects.	Moved to the standard specifications. Go to SS 8-1.04 and SS 8-1.05. Also SSPs 8-1.04s, 8-1.05, and 8-1.10A.		
S4-002	Section 4. Beginning of Work, Time of Completion, And Liquidated Damages	Used for informal projects. Automatically inserted by boilerplate.	Go to SSP 8-1.04E and SS 1-1.07B for definition of days.		
S4-003	Section 4. Beginning of	Use in projects that meet any of the following conditions:	Go to SSP 8-1.04C, SS 8-1.05 SSP 8-1.05, SS 8-1.10A, SSP 8-		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
	Work, Time of Completion, And Liquidated Damages	1. Needs a delay start to procure materials 2. Is a Highway Planting project 3. Is \$5 million or more and 200 working days. See SSP instructions for additional criteria.	1.05, and SSP 8-1.10A.		
S4-004	Section 4. Beginning of Work, Time of Completion, And Liquidated Damages	Use in Highway Maintenance and Minor A projects with 50 working days or less.	Go to SSP 8-1.04F and SSP 8-1.05.		
S4-008	Section 4. Beginning of Work, Time of Completion, And Liquidated Damages	Use if project contains "minimum financing" in 2010/2011 fiscal year budget and has more than 50 working days. Do not include in projects with bid openings after 2011/2012 FY Budget becomes law.	Go to SSP 8-1.04G.		
S4-009	Section 4. Beginning of Work, Time of Completion, And Liquidated Damages	Use if project contains "minimum financing" in 2010/2011 fiscal year budget and has 50 working days or less. Do not include in projects with bid openings after 2011/2012 FY Budget becomes law.	Go to SSP 8-1.05 and SSP 8-1.05.		
S4-070	Water Availability Clause	Add to the end of Section 4 when the District has determined that there is a definite possibility that water could become unavailable during construction. Do not use in projects with highway planting work.	Go to section SS 17-1.01A.		
S5-000	Section 5 Title	Used in ALL projects (inserted by boilerplate by DES-OE.)	No longer needed. 2010 use SSP 0-SP as base template to assemble SSPs.		
S5-003	Federal Requirements	Use in projects with American Recovery and Reinvestment Act	ARRA no longer supported after JANUARY 2012.		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
	(American Recovery and Reinvestment Act)	Federal-aid funds. Automatically inserted by boilerplate. Use until January 2012.			
S5-005	Monthly Employment Report (American Recovery and Reinvestment Act)	Use in projects with American Recovery and Reinvestment Act Federal-aid funds. Automatically inserted by boilerplate. Use until January 2012.	ARRA no longer supported after JANUARY 2012.		
S5-014	Emissions Reduction	Use in ALL projects. Automatically inserted by boilerplate.	Moved to the standard specifications. Go to SS 7-1.02C.		
S5-090	Non-Small Business	Used in State-funded only projects. Automatically inserted by boilerplate.	Move to the standard specifications. Go to SS 5-1.13D.		
S5-095	Disabled Veteran Business Enterprises	Used in State-funded projects. Automatically inserted by boilerplate.	Move to the standard specifications. Go to SS 5-1.13C.		
S5-099	Performance of DBEs	Used in Federal-aid projects. Automatically inserted by boilerplate.	Moved to the standard specifications. Go to SS 5-1.13B.		
S5-101	Performance of UDBEs	Use in projects with Federal-aid funds and UDBE goal. Inserted automatically by boilerplate.	Moved to the standard specifications. Go to SS 5-1.13B(2).		
S5-135	Force Account Payment	Use in projects with Time Related Overhead (SSP 08-017 or 08-018). Do not use when the item for building work is over 50% of the total bid items.	SSP Go to 9-1.11.		
S5-155	Partnering Dispute	Use in projects over \$10 million and	Go to SSP 5-1.09A.		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
	Resolution	with 100 or more working days (inserted by boilerplate by DES-OE).			
S5-180	Responsibility To Other Entities	Use when requested in writing by a local government entity.	Move to the standard specifications. Go to SS 7-1.05B.		
S5-190	Interim Estimate and Claims	Use ONLY for projects included in the warranty pilot program.	No longer needed.		
S5-200	Damage Claims	Use in ALL seal coat projects when screenings will be applied.	Moved to the standard specifications. Go to SS 7-1.07B.		
S5-230	Payment Adjustments for Price Index Fluctuations	Use in all projects. Automatically inserted by boilerplate.	Moved to the standard specifications. Go to SS 9-1.07.		
S5-240	Areas For Contractor's Use	Use when the District has determined that yard areas or plant sites are available for the project.	Moved to the standard specifications. Go to SS 5-1.32.		
S5-250	Payments	Use in ALL projects	Go to SSP 9-1.16C.		
S5-255	Payments	Use ONLY for projects included in the warranty pilot program.	No longer needed.		
S5-270	Airspace	Use when portions of the right of way are listed in the District's nonoperating right of way inventory.	No longer needed.		
S5-280	Supplemental Project Information	Use if information for the project is available or required for the bidders to accurately bid the project.	Go to SSP 2-1.06B.		
S5-310	Noise Control	Use for work in a residential or urban area (1) at night or (2) if night or Sunday noise restrictions exist.	Go to SSP 14-8.02.		
S5-320	Water Conservation	Use where a water shortage exists.	<u>Missing specification requirements.</u> <u>Developing parallel specifications.</u>		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
S5-450	Surface Mining and Reclamation Act	Use in all projects. Automatically inserted by boilerplate.	Moved to the standard specifications. Go to SS 7-1.02M(3).		
S5-500	Highway Construction Equipment	Use when a majority of the work is away from public traffic.	Moved to the standard specifications. Go to SS 7-1.02O.		
S5-505	Species Protection	Use when district biologist has determined that the project is occurring in our adjacent to regulated species habitat.	Go to SSP 14-6.03. Go to SSP 14-6.02.		
S5-506	Natural Resources Protection Plan	Use when district biologist has determined that the natural resource protection plan is necessary. Use with 07-321 Contractor Supplied Biologist.	Go to SSP 14-6.07.		
S5-600	Project Appearance	Use on projects where appearance of the work would have an unusual effect on public opinion. Justification is required.	Moved to the standard specifications. Go to SS 5-1.31.		
S5-610	State Park Regulations	Use when the project limits include a portion of a State Park.	Go to SSP 14-12.03.		
S5-625	Bird Protection	Use when migratory or nongame birds may be adversely affected, injured, or killed during construction activities.	Go to SSP 14-6.02 and SSP 14-6.03.		
S5-630	Relations With California Regional Water Quality Control Board	Use with SSP 07-340 or 07-345, "Water Pollution Control."	Go to SS 7-1.01 and individual SSP's where needed.		
S5-640	Relations With State Reclamation Board	Use when a California State Reclamation Board application has been obtained.	Go to SSP 14-12.04.		
S5-650	Open Burning Of	Use only in areas where burning is	No longer needed, it's covered by		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
	Waste Material	still permitted AND when the District fully justifies the necessity for burning.	the laws on air pollution and preservation of property.		
S5-690	Fire Plan	Use this SSP when requested by the District.	Go to SSP 7-1.02M(2).		
S5-700	Material Sites	Use when requested by the District.	Go to SS 19-7.03 and SSP 19-7.02B, paragraph 3.		
S5-714	Electronic Submission of Payroll Records	Use in all projects. Automatically inserted by boilerplate	Moved to the standard specifications. Go to SS 7-1.02K(2) and SS 7-1.02K(3).		
S5-715	Training	Use for federal-aid projects with trainees.	Moved number of trainees to <i>Notice to Bidders</i> . Go to NTB.		
S5-720	Borrow, Disposal And Material Sites	Use in desert areas or other critical areas.	No longer needed.		
S5-740	Aerially Deposited Lead	Use in projects containing soils with aerially deposited lead.	Go to SSP 14-11.03.		
S5-750	Naturally Occurring Asbestos	Use with SSP 19-910.	Go to SSP 14-11.05.		
S5-760	Environmentally Sensitive Area	Use if an Environmentally Sensitive Area (ESA) is shown on the plans for preservation of archeological sites, existing vegetation, biological habitat protection, or other.	Go to SSP 14-1.02.		
S5-775	Nonhighway Facilities (Including Utilities)	Use if utilities are to be relocated during construction or if utilities are involved with pile driving, drilling, or substructure construction.	Go to SSP 5-1.36D.		
S5-780	Damage Repair	Use on Highway Planting Projects and on Highway Construction Projects with Highway Planting.	Moved to the standard specifications. Go to SS 5-1.39.		
S5-790	Relief from	Use for Highway Construction	Moved to the standard		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
	Maintenance and Responsibility	projects with plant establishment period. Use on Highway Planting projects with hardscape (rock blanket, AC, MVP, etc.). Use Para 6 of SSP 20-550.	specifications. Go to SS 5-1.38.		
S5-800	Tunnel Safety Orders	Use in all projects with potential for human entry into or activity near the entry of, an underground facility meeting the definition of a tunnel.	Moved to the standard specifications. Go to SS 7-1.02K(6)(c).		
S5-950	Areas For Contractor's Use, Utilities, Sanitary Provisions, Bridge Tolls, Access to Project Site, Drawings, and Permits and Licenses.	Use in ALL Toll Bridge Projects.	No longer maintaining toll bridge specifications.		
S8-C00	Section 8-2 Title	Use in all projects. Delete Section 8-2 heading that is not applicable.	No longer needed.		
S8-C02	Portland Cement Concrete	Use "Strength Development Time" section for projects in Climate Areas I or II. Use "Supplementary Cementitious Materials" section for projects with minor concrete. If neither section is used, do not use this SSP.	Go to SS 90-1.01D(5)(a), SS 90-1.02B(3), and SSP 90-2.02B (for minor concrete)		
S8-C04	Corrosion Control for Portland Cement Concrete	Use for concrete in direct contact with a corrosive environment, including those located in Climate Area III as defined in the RTL Guide.	Go to SS 90-1.02H and SSP 90-1.02H.		
S8-C05	Freezing Condition Requirements	Use when project falls within the post mile limits shown for Climate Area III as defined in the RTL Guide.	Go to SS 1-1.09 and SSP 1-1.09 and SS 90-1.02I.		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
S8-C06	Rapid Strength Concrete for Structures	Use for approach slab and joint seal assembly replacements, and minor bridge deck repairs.	Moved to the standard specifications. Go to SS 51-5 and SS 90-3.		
S8-C15	Precast Concrete Quality Control	Use when projects includes precast piles, girders, deck unit, or MSE panels. Use also for other work that requires precast concrete quality control.	Go to SS 11-2 and SSPs 11-2.01 and 11-2.04B.		
S8-C16	Contractor Quality Control (Concrete Pavement)	Use if the Engineer's Estimate includes 2,000 or more cubic yards of concrete pavement.	Go to SS 40-1.01D(4) and SSP 40-1_X1.		
S8-C20	Self-Consolidating Concrete for Precast Elements	Use in projects with precast elements.	Go to SS 90-5 and SSP 90-5.01.		
S8-M00	Section 8 Title	Use in ALL projects.	No longer needed.		
S8-M03	Prequalified and Tested Signing and Delineation Materials	Use in ALL Projects.	New term is authorized material list. Go to 6-3.05K (it will direct you to METS Web site).		
S8-M10	State-Furnished Materials	Use in projects with State-furnished materials.	Go to SSP 6-2.03.		
S8-M25	Slag Aggregate	Use in ALL District 07, 08, 11, and 12 projects.	Go to SSP 87-2.		
S8-M26	Slag Aggregate	Use for ALL District 07, 08, 11, and 12 Highway Planting projects.	Go to SSP 87-2. "Use in all District 07, 08, 11, and 12 projects." This spec is put in when slag aggregate isn't supposed to be used in D7, D8, D11, and D12 for Highway planting projects.		
S8-M81	Filter Fabric	Use in projects with filter fabric.	Go to SS 88-1.02B and SSP 88-1.02B.		
S8-M91	Paint (Recycled)	Use when exterior wood surfaces are to be painted.	Moved to the standard specifications.		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
			Go to SS 91-3.03.		
S8-W00	Section 8-3 Title (Welding)	Use in all projects where welding is required.	No longer needed.		
S8-W04	Welding	Use when ANY welding may be performed on the project.	Moved to the standard specifications. Go to SS 11-3.		
S8-W05	Welding for Overhead Sign and Pole Structures	Use when project includes work conforming to Section 56-1, "Overhead Sign Structures," or "Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.	Moved to the standard specifications. Go to SS 11-3.03.		
S8-W06	Steel Pipe Piling Qualification Audit	Use this specification when the project includes steel pipe for CISS piles, unfilled pipe piles (including when the option to use steel pipe piling is allowed per the plans or standard plans), or permanent steel casings for CIDH piles. Use with S8-W04 and S8-W09. Include SSP 49-350 in the special provisions.	Moved to the standard specifications. Go to SS 6-3.05I and SS 49-2.02A(4)(b).		
S8-W09	Payment	Use when ANY welding may be performed on the project. Use with S8 W04, S8 W05, or S8-W06.	No longer needed. Payment covered in section 9.		
S9-S10	Sections 9 and 10 Title	Use in ALL projects.	No longer needed. For 2010 use SSP 0-SP as base template to assemble SSPs.		
05-000	Construction Project Information Signs	Use on all projects (excluding seal coat, resurfacing and seismic projects) with an estimated contract cost of \$750 000 or more and 50 working days or more.	Go to SSP 12-2.		
05-010	Order of Work	LEAD SSP. Add special features which apply to the project.	Go to SSP 10-1.02 for construction sequence activities and SSP 10-		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
			1.03 for time constraint activities.		
05-020	Miscellaneous Clauses For Order of Work	Miscellaneous order of work clauses. Add to SSP 05-010.	"Attention is directed to..." is not needed. Actual requirements are included in the applicable section. Par. 1 is covered by SSP 72-11.01. Par. 2 is covered by SS 73-1.01D. Par. 3 is covered by SSP 58-3. Par. 4 is not needed. We don't have timber sound walls. Par.5 covered by SS 53. Par. 6 is not needed. It is only a reference to Fire Plan. Par. 7 is covered by section 40-1.01(3) and SSP 40-1. Par. 8 is not needed. Go to SS 14-1.02.		
05-030	Miscellaneous Clauses for Order of Work	Use for signal and lighting work. Add to SSP 05-010.	Par. 1 is covered by Delay Start in SSP 8-1.04C. Pars. 2 and 3 are in SSP 8-1.02A.		
05-050	Miscellaneous Clauses For Order of Work	Use for projects with planned staging or when staging is inherent to the type of work. Add to SSP 05-010.	"Attention is directed to..." is not needed. Actual requirements are included in the applicable section. Par. 1 is not needed.. It is only a reference. Par. 2 is covered in SS 8-1.02D(5). Par. 3 is covered in SS 8-1.02D(2). Par. 4 is covered by SSP 12-8, Temporary Pavement Delineation. Par. 5 is covered in RSS 10-1.02. Par. 6 is covered in SS 37-2.03D, 37-3.03A, 39-1.13, and 54-5.03.		
05-060	Miscellaneous Clauses For Order of Work	Use only on State-financed seal coat projects. Add to SSP 05-010.	Par. 1 is not needed. It is only a reference. Par. 2 is covered by SSP 12-8_X2.		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
			Par. 3 is covered in RSS 10-1.02. Par. 4 is covered in SS 37-2.03D and SS 37-3.03A Par. 5 is covered in SS 37-2.03A. Par. 6 is covered in SS 37-2.03A.		
05-080	Miscellaneous Clauses For Order of Work	Use for widening projects that will require excavation adjacent to a lane being used by public traffic and that allow a moving operation without "safety wedge." Add to SSP 05-010.	Go to SS 8-1.02A.		
05-100	Miscellaneous Clause For Order of Work	Use for projects that require excavation adjacent to a lane being used by public traffic and that needs a "safety wedge" during nonworking hours. Add to SSP 05-010.	Go to SS 8-1.02A.		
05-150	Miscellaneous Clause For Order of Work	Use when work on guard railing, thrie beam barrier or metal beam barrier is to be done adjacent to traffic. Add to SSP 05-010.	Go to SS 83-1.02A		
05-200	Miscellaneous Clauses For Order of Work	Miscellaneous clauses for planting and seeding work and irrigation work. Add to SSP 05-010 or to other "Order of Work" SSPs as required.	Pars. 1-3 are covered in SS 20-7.01B(1). Par. 4 is covered in SS 20-7.03I(16). Par. 5 is covered in SS 20-7.04. Par. 6 is covered in SS 21-1.01B. Par. 7 is not needed. The only products specified for straw are wheat, rice, and barley. Other products are not specified. Par. 8 is covered in SS 20-3.03A. Par. 9 is covered in SS 20-3.03B(6). Par. 10 is covered in SS 20-3.03C(2)(a). Par. 11 is covered in SS 20-3.03B(4). Par. 12 is covered in SS 16-1.01.		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
			Par. 13 is covered in SS 20-3.03C(2)(d). Par 14 is covered in SS 20-3.01C(4). <u>Par 15 is covered by SS 20-3.02I.</u>		
05-500	Miscellaneous Clause For Order of Work	Use when project requires embankment settlement period or surcharge embankments. Add to SSP 05-010	Not needed. All requirements for settlement periods are in section 19-6.03D (standard specification and SSP).		
07-320	Archaeological Monitoring Area (AMA)	Use in projects when information is provided by the Project Archaeologist for AMAs. Location of AMAs must be shown on the plans. Refer to the Standard Environmental Reference (SER) for design guidance.	Moved to SS 14-2.03. Go to SSP 14-2.03 if archaeologist provides AMA info.		
07-321	Contractor Supplied Biologist	Use when a District Biologist has determined that the project is occurring in or adjacent to a regulated species habitat and species monitoring is necessary	Go to SSP 14-6.05.		
07-322	Biological Monitoring Area (BMA)	Use when a project Biologist requires biological monitoring areas.	Incorporated biological monitoring into species protection plan. Go to SSP 14-6.02.		
07-323	Biological Resource Information Program	Use if required by PLAC. Use with 07-321 "Contractor Supplied Biologist " .	Go to SSP 14-6.08.		
07-324	Fish Protection	Use when bridge construction is scheduled in a stream channel that contains protected fish.	Go to SS 14-6.04 and SSP 14-6.04.		
07-325	Environmental Protection (Desert Tortoise)	Use in District 9 only. Use when an Incidental Take permit or Biological Opinion is issued.	Go to SSP 14-6.02.		
07-327	Environmental Protection (Mohave Ground	Use in District 9 only. Use when a Mohave ground squirrel incidental take permit is issued.	Go to SSP 14-6.02.		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
	Squirrel)				
07-328	Temporary Wetland Protection Mat	Use when motorized equipment or vehicles need to cross wetlands and permits to use mats have been obtained.	Go to SSP 14-6.09.		
07-330	Material Containing Aerially Deposited Lead	Use in Districts 4, 6, 7, 8, 10, 11, and 12. Use in projects with minor soil disturbance, such as installing guardrail, fencing, sign posts, highway planting and irrigation, erosion control, or traffic operation systems, that have known contamination from aerially deposited lead.	Go to SSPs 14-11.04.		
07-340	Water Pollution Control	Use with all projects where construction activities, such as clearing, grading, and excavation result in less than 1 acre of soil disturbance or projects that qualify for an EPA Small Construction Erosivity Waiver.	Go to SS 13-1, SS 13-2, SSP 13-2.01.		
07-345	Water Pollution Control	Use with all projects where construction activities, such as clearing, grading, and excavation result in 1 or more acres of soil disturbance; or for projects where there may be significant water quality impairment.	Go to SS 13-3.		
07-346	Construction Site Management	Use in all projects.	Go to SS 13-4 and for hazardous waste management go to SS 14-11.		
07-347	Temporary Active Treatment System	Use only for dewatering and discharge of uncontaminated groundwater, stormwater, or both. Use only for sediment and turbidity.	Go to SS 13-8 and SSP 13-8.01A.		
07-351	Temporary Hydraulic Mulch	Use as a temporary source control for soil stabilization.	Go to SS 13-5.03D and SS 21-1.03E.		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
07-352	Temporary Hydraulic Mulch (Cementitious Binder)	Use as a temporary source control for soil stabilization.	Go to SS 13-5.02D, SS 13-5.03G, and SS 21-1.03E.		
07-353	Temporary Hydroseed	Use as a temporary source control for soil stabilization.	Go to SS 13-5.03I, SS 21-1.03E.		
07-354	Temporary Tacked Straw	Use as a temporary source control for soil stabilization.	Go to SS 13-5.03H and SS 21-1.03H.		
07-360	Street Sweeping	Use for project conditions that require machine-operated sweepers to control sediment in conjunction with other tracking controls and control sediment, particulate matter, debris, and trash that may be tracked off site.	Go to SS 13-7.03D and SSP 13-7.03D.		
07-371	Temporary Soil Binder	Use as a temporary source control for soil stabilization.	Go to SS 13-5.03J and SS 21-1.03E.		
07-380	Temporary Mulch	Use as a temporary source control for soil stabilization.	Go to SS 13-5.02C, SS 13-5.03C, and SS 20-7.03I(10).		
07-381	Temporary Hydraulic Mulch (Bonded Fiber Matrix)	Use as a temporary source control for soil stabilization. Temporary hydraulic mulch (bonded fiber matrix) is used to cover and protect disturbed soil areas from erosion due to wind or water.	Go to SS 13-5.03E and SS 21-1.03J.		
07-382	Temporary Hydraulic Mulch (Polymer Stabilized Fiber Matrix)	Use as a temporary source control for soil stabilization. Temporary hydraulic mulch (polymer stabilized fiber matrix) is used to cover and protect disturbed soil areas by flocculating suspended solids and sediment from runoff.	Go to SS 13-5.03F and SS 21-1.03I.		
07-390	Temporary Erosion Control Blanket	Use as a temporary erosion control blanket for soil stabilization.	Go to SS 13-5.03B, SS 21-1.03O.		
07-395	Temporary Cover	Use as a temporary plastic cover for soil stabilization. Temporary cover is used as a source control to protect disturbed soil areas, such as	Go to SS 13-5 and SS 88-1.02H.		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
		unfinished embankments, cut slopes, and temporary stockpiles from erosion by water and by wind.			
07-400	Temporary Culverts	Use when temporary culverts are used for detours.	Go to SS 62-3.		
07-405	Temporary Concrete Washout Facility	Use for conditions that require a waste management and material pollution control for concrete operations.	Go to SS 13-9.		
07-406	Temporary Concrete Washout (Portable)	Use instead of "Temporary Concrete Washout Facility" if there is not enough space for the placement of that facility.	Go to SS 13-9.		
07-407	Temporary Concrete Washout Bin	Use for waste management and material pollution control for concrete operations, and to eliminate discharge of portland cement concrete slurries and asphalt concrete wastes from entering storm drain systems or watercourses.	Go to SS 13-9.		
07-410	Temporary Metal Beam Guard Railing	Use when project requires temporary metal beam guard railing.	Go to SS 83-1.02B(3).		
07-415	Temporary Check Dam	Use as a temporary sediment control structure in ditches and swales to trap and detain sediment in concentrated flows of storm water runoff from construction sites.	Go to SS 13-6.03B.		
07-420	Temporary Fiber Roll	Use as a temporary linear barrier for sediment control to intercept runoff, reduce runoff flow velocity, and release runoff as sheet flow.	Go to SS 13-6.03E, SS 13-6.04, and SS 21-1.02P.		
07-421	Temporary Large Sediment Barrier	Use as a temporary linear barrier for sediment control to intercept and slow	Go to SS 13-6.03G and SS 13-10.		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
		the flow of sediment-laden runoff.			
07-430	Temporary Silt Fence	Use as a temporary linear barrier for sediment control to intercept and detain sediment in storm water runoff from unprotected areas at construction sites.	Go to SS 13-6.03I and SS 13-10.03F.		
07-432	Temporary Reinforced Silt Fence	Use if sediment loads require a stronger silt fence than is available with Temporary Silt Fence (SSP 07-430).	Go to SS 13-6.03H, SSP 13-6.03H, and SS 13-10.03F.		
07-440	Temporary Fence	Use when project requires temporary fence.	Go to SS 80-1.07.		
07-446	Temporary Fence (Type ESA)	Use if project requires a temporary fence to delineate environmentally sensitive areas, preserve existing vegetation, or other conditions that require temporary, high visibility fence.	Go to SS 14-1.03.		
07-460	Temporary Straw Bale Barrier	Use as temporary linear sediment barrier to control, intercept and detain sediment in storm water runoff from unprotected areas at job sites.	Go to SS 13-6.03J and SS 13-10.03G.		
07-470	Temporary Gravel Bag Berm	Use as a temporary linear berm for sediment control to intercept runoff, reduce runoff flow velocity, and release runoff as sheet flow.	Go to SS 13-5.02G, SS 13-6.03F, SS 13-10.02J, and SS 13-10.03C.		
07-480	Temporary Construction Entrance	Use as a temporary tracking control at points of ingress and egress at the construction sites to reduce tracking of mud and sediment onto public roads by construction vehicles.	Go to SS 13-7.03B.		
07-481	Temporary Construction Roadway	Use as a temporary tracking control to limit dust generation and minimize tracking of sediment while providing access for construction activities.	Go to SS 13-7.		
07-485	Move-In/Move-Out	Use to apply temporary soil	Go to SS 13-5.01.		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
	(Temporary Erosion Control)	stabilization (erosion control) BMPs on newly completed slopes. Use where grading is sequential and slopes are not all finished at the same time. Recommended for large projects (25 acres or more DSA) that extend through several rainy seasons and use SSP 07 345. Not recommended for small projects with a single rainy season.			
07-490	Temporary Drainage Inlet Protection	Use for project conditions that require a temporary sediment control by providing temporary drainage inlet protection to filter or settle sediment-laden runoff prior to discharge into a storm drainage system or watercourse.	Go to SS 13-6.03C and SS 13-10.03A		
07-600	Materials Hauling Equipment Loading On Bridges	Use when bridges are shown on the plans to carry the materials hauling equipment loading.	Go to SSP 5-1.37B(3).		
07-610	Materials Hauling Equipment Loading On Bridges	Use when alternative details for bridges are shown on the plans to carry the materials hauling equipment loading.	Go to SSP 5-1.37B(3).		
07-640	Scaffolding	Use when scaffolding would be over or adjacent to traffic or suspended from the traveled way.	Go to SSP 7-1.02K(6)(e).		
07-650	Temporary Decking	Use when removing and replacing joint seal assemblies or portions of the bridge deck and it has been determined that the time for lane closure is not long enough to allow for continuous completion of the work.	Go to SSP 48-4.		
07-850	Cooperation	Use when one or more projects are adjacent to or within the project limits.	Go to SSP 5-1.20A		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
08-012	Progress Schedule (Critical Path Method)	Use in projects (except highway planting) that meet one of the following criteria: 1. Less than \$1 million and with 100 or more working days 2. From \$1 million to \$5 million, except the District may use SSP 08-015 for complex projects over 250 working days. 3. Over \$5 million and less than 100 working days.	Go to SS 8-1.02C		
08-015	Progress Schedule (Critical Path Method)	Use in projects (except highway planting) over \$5 million and with 100 or more working days.	Go to SS 8-1.02D.		
08-017	Time-Related Overhead	Use in projects over \$5 million and 100 or more working days. Do not include on cost plus time contracts. Use SSP 08-018 on cost plus time contracts. Include SSPs S5-135, 05-050, and 08-015 when this SP is used. Do not use for building projects when the building work item is over 50% of the total bid items.	Go to SS 9-1.11 and SSP 9-1.11.		
08-018	Time-Related Overhead	Use in A+B projects over \$5 million and 100 or more working days. Include SSPs S5-135, 05-050, and 08-015 when this SSP is used. Do not use for building projects when the building work item is over 50% of the total bid items.	Go to SS 9-1.11 and SSP 9-1.11.		
08-100	Right of Way Obstructions	Use in Federal Aid projects that have been approved for advertising even though some right of way parcels have NOT been cleared AND MAY BE OCCUPIED. This "work-around"	Go to SSP 5-1.20D.		

WHERE IS IT NOW?
07/23/12

2006 Special Notices and Standard Special Provisions				2010 Special Notices and Standard Specifications	
2006 SSP no.	Description	Instruction for use	Any changes? Where is it in the 2010s?	Any changes? Where is it in the 2006s?	2010 SSP no.
		SSP is to be used in VERY unusual conditions and should not be used in normal projects.			