

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

[www.dot.ca.gov/hq/esc/oe](http://www.dot.ca.gov/hq/esc/oe)

*Serious Drought.  
Help save water!*

October 28, 2015

01-DN-199-8.7, 21.7

01-0B3104

Project ID 0112000115

ACSTP-ER-19B9(004)E

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN DEL NORTE COUNTY NEAR GASQUET AT 1.5 MILES NORTH OF MYRTLE CREEK BRIDGE AND ABOUT 8 MILES NORTH OF GASQUET AT 0.4 MILE SOUTH OF PATRICK CREEK BRIDGE to revise the project plans, the *Notice to Bidders and Special Provisions* and the *Bid* book.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, November 4, 2015.

Project plan sheet 44 is replaced and attached for substitution for the like-numbered sheets.

In the *Special Provisions*, Section 39-4.02C, the first paragraph is replaced as follows:

"For HMA-O, the grade of asphalt binder must be PG 58-34 PM."

In the *Bid* book, in the "Bid Item List," Items 36, 37 and 58 are replaced.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

**[http://www.dot.ca.gov/hq/esc/oe/electronic\\_bidding/electronic\\_bidding.html](http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html)**

Inform subcontractors and suppliers as necessary.

Addendum No. 2  
Page 2  
October 28, 2015

01-DN-199-8.7, 21.7  
01-0B3104  
Project ID 0112000115  
ACSTP-ER-19B9(004)E

This addendum, EBS addendum file, attachments are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/01/01-0B3104](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/01/01-0B3104)**

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



fes

CHARLIE FIELDER  
District Director

Attachments

**BID ITEM LIST**

**01-0B3104**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	141000	TEMPORARY FENCE (TYPE ESA)	LF	390		
22	141103	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	LF	1,320		
23	141120	TREATED WOOD WASTE	LB	1,100		
24	146001	CONTRACTOR-SUPPLIED BIOLOGIST (DAY)	DAY	6		
25	149001	DUST CONTROL PLAN (NATURALLY OCCURRING ASBESTOS)	LS	LUMP SUM	LUMP SUM	
26	150661	REMOVE GUARDRAIL	LF	70		
27	150711	REMOVE PAINTED TRAFFIC STRIPE	LF	530		
28	150712	REMOVE PAINTED PAVEMENT MARKING	SQFT	48		
29	150722	REMOVE PAVEMENT MARKER	EA	82		
30	151627	RECONSTRUCT GUARDRAIL (WOOD POST)	LF	25		
31	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	620		
32	160102	CLEARING AND GRUBBING (LS)	LS	LUMP SUM	LUMP SUM	
33	190101	ROADWAY EXCAVATION	CY	100		
34	190109	ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS)	CY	150		
35	190185	SHOULDER BACKING	TON	50		
36 (F)	192049	STRUCTURE EXCAVATION (SOLDIER PILE WALL)	CY	150		
37 (F)	193029	STRUCTURE BACKFILL (SOLDIER PILE WALL)	CY	39		
38 (F)	193116	CONCRETE BACKFILL (SOLDIER PILE WALL)	CY	79		
39 (F)	193119	LEAN CONCRETE BACKFILL	CY	23		
40	210270	ROLLED EROSION CONTROL PRODUCT (NETTING)	SQFT	8,790		

**BID ITEM LIST**  
**01-0B3104**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41	210300	HYDROMULCH	SQFT	12,200		
42	210350	FIBER ROLLS	LF	820		
43	210420	STRAW	SQFT	3,330		
44	210430	HYDROSEED	SQFT	12,200		
45	260203	CLASS 2 AGGREGATE BASE (CY)	CY	100		
46	390132	HOT MIX ASPHALT (TYPE A)	TON	250		
47	390401	HOT MIX ASPHALT-OPEN GRADED (OPEN GRADED FRICTION COURSE)	TON	90		
48	393004	GEOSYNTHETIC PAVEMENT INTERLAYER (PAVING FABRIC)	SQYD	340		
49	029986	CENTERLINE RUMBLE STRIP	STA	5		
50	397005	TACK COAT	TON	0.5		
51	045111	STEEL SOLDIER PILE (W 16 X 67)	LF	405		
52	045112	STEEL SOLDIER PILE (W 16 X 89)	LF	315		
53	045113	STEEL SOLDIER PILE (W 14 X 120)	LF	240		
54	490400	24" DRILLED HOLE	LF	920		
55 (F)	510060	STRUCTURAL CONCRETE, RETAINING WALL	CY	71		
56 (F)	510072	STRUCTURAL CONCRETE, BARRIER SLAB	CY	68		
57 (F)	045114	RANDOM ROCK TEXTURE	SQFT	1,687		
58 (F)	520103	BAR REINFORCING STEEL (RETAINING WALL)	LB	6,200		
59 (F)	575004	TIMBER LAGGING	MFBM	9		
60	597601	PREPARE AND STAIN CONCRETE	SQFT	1,687		