

**DEPARTMENT OF TRANSPORTATION**

ES-OE MS #43  
1727 30TH Street, 2ND Floor  
Sacramento, CA 95816



July 20, 2001

01-Hum-283-0.2/0.6  
01-310404  
ACBHSTP-S283(001)E

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in HUMBOLDT COUNTY IN AND NEAR RIO DELL AT EEL RIVER BRIDGE OVERHEAD.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on July 31, 2001 instead of the original date of July 24, 2001.

This addendum is being issued to change the bid opening date as shown herein, and to revise the Project Plans, the Notice to Contractors and Special Provisions, and the Proposal and Contract.

Project Plan Sheet 20 is revised as follows:

In the first sentence of the first note at the top of the sheet, "2.8 thick, 9 gage" is revised to "9 gage minimum."

The last sentence of the second note at the top of the sheet is revised as follows:

"All new sidewalk connections shall be made @152 OC maximum with counter sunk stainless steel 6 dia. coarse thread, flat head socket cap screws with lock washer and hex head nut."

In the Special Provisions, Section 10-1.17, "EXISTING HIGHWAY FACILITIES," the fourth paragraph of subsection, "BRIDGE REMOVAL (PORTION)," is replaced by the following paragraphs:

"The area of existing steel within a 100-mm radius measured in any direction from the point of application of heat for welding or flame cutting shall be abrasive blast cleaned in conformance with the requirements in Surface Preparation Specification No. 10, "Near White Blast Cleaning," of the "SSPC: The Society for Protective Coatings," and "Clean and Paint Existing Structural Steel" of these special provisions.

Full compensation for blast cleaning shall be considered as included in the contract price paid per lump sum for bridge removal (portion) and no additional compensation will be allowed therefor."

In the Special Provisions, Section 10-1.20, "CLEAN AND PAINT EXISTING STRUCTURAL STEEL," the first paragraph is revised as follows:

"Exposed metal surfaces of the existing structure including existing steel railing and those exposed by sidewalk steel plate removal shall be cleaned and painted in conformance with the provisions in Section 59-2, "Painting Structural Steel," and Section 91, "Paint," of the Standard Specifications and these special provisions."

Addendum No.2  
Page 2  
July 20, 2001

01-Hum-283-0.2/0.6  
01-310404  
ACBHSTP-S283(001)E

In the Special Provisions, Section 10-1.21, "MISCELLANEOUS METAL (BRIDGE)," the following paragraph is added after the third paragraph:

"Miscellaneous metal (bridge) shall not be galvanized."

In the Proposal and Contract, the Engineer's Estimate Item 16 is revised, as attached.

To Proposal and Contract book holders:

Replace page 3 of the Engineer's Estimate in the Proposal with the attached revised page 3 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief  
Plans, Specifications & Estimates Branch  
Office of Office Engineer

Attachment

**ENGINEER'S ESTIMATE**  
**01-310404**

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
2 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
3 (S)	120120	TYPE III BARRICADE	EA	8		
4	120152	TEMPORARY PAVEMENT MARKING (TAPE)	M2	17		
5	120165	CHANNELIZER (SURFACE MOUNTED)	EA	65		
6 (S)	128601	TEMPORARY SIGNAL SYSTEM	LS	LUMP SUM	LUMP SUM	
7	128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2		
8	150662	REMOVE METAL BEAM GUARD RAILING	M	12		
9	021643	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	M	180		
10 (S)	151572	RECONSTRUCT METAL BEAM GUARD RAILING	M	12		
11 (S)	021644	RECONSTRUCT TERMINAL SECTION (TYPE C)	LS	LUMP SUM	LUMP SUM	
12	157560	BRIDGE REMOVAL (PORTION)	LS	LUMP SUM	LUMP SUM	
13 (S)	021645	GUARD RAILING WEED CONTROL MAT	M	25		
14	590106	CLEAN STRUCTURAL STEEL (EXISTING BRIDGE)	LS	LUMP SUM	LUMP SUM	
15	590111	PAINT STRUCTURAL STEEL (EXISTING BRIDGE)	LS	LUMP SUM	LUMP SUM	
16	590135	SPOT BLAST CLEAN AND PAINT UNDERCOAT	M2	2640		
17 (S)	590301	WORK AREA MONITORING	LS	LUMP SUM	LUMP SUM	
18 (S)	048533	AIR MONITORING INSIDE CONTAINMENT SYSTEM	LS	LUMP SUM	LUMP SUM	
19 (S-F)	750501	MISCELLANEOUS METAL (BRIDGE)	KG	72 200		
20 (S)	839565	TERMINAL SYSTEM (TYPE SRT)	EA	1		