

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
 OFFICE ENGINEER, MS 43
 1727 30TH STREET
 P.O. BOX 168041
 SACRAMENTO, CA 95816-8041
 FAX (916) 227-6214
 TTY 711



Flex your power!
Be energy efficient!

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

November 20, 2008

01-Hum-96-16.0/18.7
 01-452404
 OTS

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN HUMBOLDT COUNTY NEAR HOOPA FROM 0.8 MILE SOUTH OF ROCK CHUTE VIADUCT TO 1.9 MILES NORTH OF SIDEHILL VIADUCT .

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on December 2, 2008.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, and the Bid book.

Project Plan Sheet 25 is revised as follows:

"In the ROADWAY quantity table, the quantity of "HMA (Type A) " is revised from 6058 TON to 1298 TON."

In the Special Provisions, Section 10-1.06, "TEMPORARY EROSION CONTROL," subsection "APPLICATION," the table in item A, is revised as follows:

Material	Pounds Per Acre (Slope Measurement)
Fiber	1200
Seed	65

In the Special Provisions, Section 10-1.33, "EROSION CONTROL (TYPE D)," subsection "MATERIALS," subsection "Seed, " the fifth paragraph is deleted.

In the Special Provisions, Section 10-1.42, "CONCRETE STRUCTURES," the following paragraphs are added after the last paragraph as follows:

" Concrete walers at the tieback wall will be measured and paid for as structural concrete, barrier slab at Hoopa Bluffs Retaining Wall (Br. No. 04-E0011).
 Full compensation for furnishing and installing stud connectors shall be considered as included in the contract price paid per cubic yard for structure concrete, barrier slab at Hoopa Bluffs Retaining Wall (Br. No. 04-E0011) and no additional compensation will be allowed therefor."

Addendum No. 1
Page 2
November 20, 2008

01-Hum-96-16.0/18.7
01-452404
OTS

In the Bid book, in the "Bid Item List," Item 42 is revised as attached.

To Bid book holders:

Replace the page of the "Bid Item List" in the Bid book with the attached revised page of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it. A copy of this addendum is available for the Contractors' use on the Web site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

ROBERT E. TRAVIS, Chief
Office of Plans, Specifications & Estimates
Division of Engineering Services - Office Engineer

Attachment

BID ITEM LIST
01-452404

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41	390095	REPLACE ASPHALT CONCRETE SURFACING	CY	160		
42	390132	HOT MIX ASPHALT (TYPE A)	TON	1,300		
43	393003	GEOSYNTHETIC PAVEMENT INTERLAYER	SQYD	120		
44	041528	STEEL SOLDIER PILE (HP 12X84)	LF	454		
45	041529	24" DIAMETER DRILLED HOLE	LF	330		
46	500050	TIEBACK ANCHOR	EA	8		
47 (F)	510072	STRUCTURAL CONCRETE, BARRIER SLAB	CY	203		
48 (F)	510220	CLASS 3 CONCRETE (BACKFILL)	CY	27		
49 (F)	575004	TIMBER LAGGING	MFBM	11		
50	041530	CLEAN AND PAINT STEEL SOLDIER PILING	LS	LUMP SUM	LUMP SUM	
51	820118	GUARD RAILING DELINEATOR	EA	110		
52	832002	METAL BEAM GUARD RAILING (STEEL POST)	LF	1,820		
53	832004	METAL BEAM GUARD RAILING (SPECIAL)	LF	760		
54	015056	METAL BEAM GUARD RAILING (STEEL POST) (7' POST)	LF	650		
55	832070	VEGETATION CONTROL (MINOR CONCRETE)	SQYD	1,220		
56	839541	TRANSITION RAILING (TYPE WB)	EA	7		
57	015057	TRANSITION RAILING (TYPE WB) (MODIFIED)	EA	1		
58	015058	THRIE BEAM CONNECTION (TYPE 2)	EA	2		
59	015059	THRIE BEAM CONNECTION (TYPE 1)	EA	1		
60	839568	TERMINAL ANCHOR ASSEMBLY (TYPE SFT)	EA	5		