

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

[www.dot.ca.gov/hq/esc/oe](http://www.dot.ca.gov/hq/esc/oe)*Flex your power!  
Be energy efficient!*

September 27, 2013

01-Men-128-35.0/35.3

01-476604

Project ID 0100000351

ER-43M5(004)

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN MENDOCINO COUNTY ABOUT 5.0 MILES EAST OF BOONVILLE FROM 0.5 MILE EAST OF SHEARING CREEK BRIDGE TO 0.9 MILE WEST OF MAPLE CREEK BRIDGE.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Tuesday, October 8, 2013.

This addendum is being issued to revise the *Notice to Bidders and Special Provisions* and the Federal Minimum Wages with Modification Number 11 dated 09/20/2013.

In the Special Provisions, Section 16, "CLEARING AND GRUBBING," is replaced as attached.

In the Special Provisions, Section 72, "SLOPE PROTECTION," is added as attached.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the *Bid* book.

Submit bids in the *Bid* book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No.1  
Page 2  
September 27, 2013

01-Men-128-35.0/35.3  
01-476604  
Project ID 0100000351  
ER-43M5(004)

This addendum, attachments and the modified wage rates are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/01/01-476604](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/01/01-476604)**

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



REBECCA D. HARNAGEL  
Chief, Office of Plans, Specifications & Estimates  
Office Engineer  
Division of Engineering Services

Attachments

## **16 CLEARING AND GRUBBING**

### **Add to section 16-1.01:**

Request a biological survey for nesting birds at least two weeks before you cut trees or brush from June 15 to September 15. Do not cut trees or brush until authorized.

Remove the existing horizontal drains as shown.

### **Add to section 16-1.03B:**

For trees that are being removed, that are 10 inches in diameter or greater, leave a minimum of 5' of trunk attached to the root wad. Remove loose material from root wad and stockpile on site.

Trim branches from removed tree trunks and limbs that are a minimum of 12 inches in diameter, and stockpile trimmed wood on site.

### **Add to section 16-1.03D:**

Stockpiled woody material will be placed at streambed locations authorized by the Engineer. This is extra work.

## **72 SLOPE PROTECTION**

**Replace the 1st paragraph in section 72-2.01 with:**

Section 72-2 includes specifications for constructing RSP. RSP includes:

1. Excavating for the RSP
2. Placing RSP fabric where shown
3. Placing revetment type rock courses on the slope

**Add to section 72-2.03A:**

When excavating for the RSP buttress, stop excavation if the Engineer determines that competent rock has been encountered.