

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

TTY 711

*Flex your power!  
Be energy efficient!*

July 12, 2011

02-Sha,Sis-5-Var  
02-2E3204  
Project ID 0200000583  
IM-000C(344)E

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN SHASTA AND SISKIYOU COUNTIES AT VARIOUS LOCATIONS.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Tuesday, July 19, 2011.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, and the Bid book.

Project Plan Sheets 13, 36, 37 and 38 are revised. Copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 10-1.21, "EXISTING HIGHWAY FACILITIES," subsection "RECONSTRUCT METAL BEAM GUARD RAILING," the fourth and sixth paragraphs are revised as follows:

"New steel posts, blocks, and hardware shall be furnished and used to reconstruct metal beam guard railing. New posts and blocks shall conform to the provisions in Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications.

Full compensation for furnishing and installing new steel posts, blocks, and hardware; for connecting reconstructed metal beam guard railing to existing structures, other flat concrete surfaces or terminal systems; and for removing and disposing of anchor assemblies shall be considered as included in the contract price paid per linear foot for reconstruct metal beam guard railing and no separate payment will be made therefor."

In the Special Provisions, Section 10-1.41, "METAL BEAM GUARD RAILING," the third paragraph is revised as follows:

"Line posts shall be steel. Blocks shall be wood or plastic."

Addendum No. 2  
Page 2  
July 12, 2011

02-Sha,Sis-5-Var  
02-2E3204  
Project ID 0200000583  
IM-000C(344)E

In the Bid book, in the "Bid Item List," Items 12, 17 and 41 are revised as attached.

To Bid book holders:

Replace pages 3 and 5 of the "Bid Item List" in the Bid book with the attached revised pages 3 and 5 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This addendum and attachments are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/02/02-2E3204](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/02/02-2E3204)**

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



REBECCA D. HARNAGEL  
Chief, Office of Plans, Specifications & Estimates  
Office Engineer  
Division of Engineering Services

Attachments

**BID ITEM LIST**  
**02-2E3204**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
2	074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
3	074028	TEMPORARY FIBER ROLL	LF	150		
4	074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	LUMP SUM	LUMP SUM	
5	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
6	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
7	120151	TEMPORARY TRAFFIC STRIPE (TAPE)	LF	52,000		
8	120165	CHANNELIZER (SURFACE MOUNTED)	EA	400		
9	128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	LUMP SUM	LUMP SUM	
10	129000	TEMPORARY RAILING (TYPE K)	LF	5,120		
11	129100	TEMPORARY CRASH CUSHION MODULE	EA	140		
12	150662	REMOVE METAL BEAM GUARD RAILING	LF	180		
13	150710	REMOVE TRAFFIC STRIPE	LF	2,210		
14	150857	REMOVE ASPHALT CONCRETE SURFACING	SQFT	26,200		
15	043119	REMOVE REINFORCED PORTLAND CEMENT CONCRETE OVERLAY	SQFT	4,800		
16	043120	GRIND EPOXY GRIT OVERLAY	SQFT	5,337		
17	151572	RECONSTRUCT METAL BEAM GUARD RAILING	LF	480		
18	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	2,570		
19	153223	REMOVE UNSOUND CONCRETE	CF	417		
20	153225	PREPARE CONCRETE BRIDGE DECK SURFACE	SQFT	36,337		

**BID ITEM LIST  
02-2E3204**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41	839541	TRANSITION RAILING (TYPE WB)	EA	7		
42 (F)	839728	CONCRETE BARRIER (TYPE 736R)	LF	1,503		
43 (F)	043122	CONCRETE BARRIER (TYPE 736A MODIFIED)	LF	248		
44	840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	LF	47,200		
45	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	12		
46	850122	PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	EA	690		
47	860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM	LUMP SUM	
48	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

**TOTAL BASE BID (TBB): = \$ \_\_\_\_\_**

**ADDITIVE ITEM(S)**

**Route 5 (TBB + Additive Item 1) LUMP SUM: = \$ \_\_\_\_\_**