

DEPARTMENT OF TRANSPORTATION

DES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

June 13, 2003

02-Sha,Las-299-152.9/160.0, 0.0/7.6
02-310204
ACSTP-P299(138)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in SHASTA AND LASSEN COUNTY IN AND NEAR MCARTHUR FROM 0.3 KM WEST OF MCARTHUR- GLENBURN ROAD TO 1.3 KM EAST OF LASSEN COUNTY ROAD NO. 407.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on June 25, 2003, instead of the original date of June 17, 2003.

This addendum is being issued to set a new bid opening date as shown herein and revise the Project Plans, the Notice to Contractors and Special Provisions, and the Proposal and Contract.

Project Plan Sheets 2, 3, 4, 5, 10, 12, 41, 42, 43, 53, 54, 59, 61, 111, 112, 136, 137, 138, 139, 141, 144, 145, 151, 152, 156, 162, 199, 200, 201, 202, 203, 205, 206, 207, 287, 288, 289, 290, 292, 293, and 294 are revised. Half-sized copies of the revised sheets are attached for substitution for the like-numbered sheets.

Project Plan Sheets 44, 45, 55, 56, 57, and 58 are deleted.

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the fourth paragraph is deleted and the following paragraph is added after the first paragraph:

"Tree removal and the interim 25 mm layer of asphalt concrete paving between Stations "A1" 1532+20 to 1539+80 shall be the first order of work. Unless otherwise approved by the Engineer, tree removal shall only be performed during the period between August 31 and March 31 due to the potential presence of nesting migratory birds. For the interim 25 mm layer of asphalt concrete between Stations "A1" 1532+20 to 1539+80, the Compensation Adjustment Factor (CAF) shall be equal to zero of Section 39-11.02, "Statistical Evaluation and Determination of Pay Factor," of Section 11-1 "Quality Control/Quality Assurance," of these special provisions. At the Contractor's option, commercial mix asphalt concrete produced at an established commercial mixing plant may be utilized for the 25 mm layer of interim asphalt concrete between Stations "A1" 1532+20 to 1539+80, and will not be subject to the requirements for aggregate quality, lime treatment, or grade of asphalt binder and mix design as specified in "Asphalt Concrete" of these special provisions."

02-Sha,Las-299-152.9/160.0, 0.0/7.6
02-310204
ACSTP-P299(138)E

In the Special Provisions, Section 10-1.09, "OBSTRUCTIONS," the following is added:

It is anticipated that the following utility facilities will be relocated prior to the dates shown:

Utility	Location	Date
Frontier Communications	Pittville Road	May 1, 2004

Raising and lowering of the following utility facilities will require coordination with the Contractor's operations. The Contractor shall make the necessary arrangements with the utility company, through the Engineer, and shall submit a schedule of work, verified by a representative of the utility company, to the Engineer. The schedule of work shall provide not less than the following number of working days, as defined in Section 8-1.06, "Time of Completion," of the Standard Specifications for the utility company to complete their work:

Utility	Type and Location	Working Days
Pacific Gas and Electric Fall River Mills Community Service District (water) Frontier Communications Mallard Cable Company	Utility boxes, vaults and covers Downtown McArthur	5

In the Special Provisions, Section 10-1.52, "WELDED STEEL PIPE," the second, third, and fifth paragraphs are deleted.

In the Proposal and Contract, the Engineer's Estimate Items 21, 25, 29, 34, 35, 37, 38, 40, 41, 42, 43, 46, 51, 55, 64, 65, 71, 76, 77, 82, 83, 84, 85, 96, and 97 are revised, Items 101, and 102 are added and Item 100 is deleted as attached.

To Proposal and Contract book holders:

Replace the entire Engineer's Estimate in the Proposal with the attached revised Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 1
Page 3
June 13, 2003

02-Sha,Las-299-152.9/160.0, 0.0/7.6
02-310204
ACSTP-P299(138)E

This office is sending this addendum by UPS overnight mail Proposal and Contract book holders to ensure that each receives it. A copy of this addendum and the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

ENGINEER'S ESTIMATE

02-310204

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM	LUMP SUM	
2	070018	TIME-RELATED OVERHEAD	WDAY	160		
3	071325	TEMPORARY FENCE (TYPE ESA)	M	650		
4	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM	LUMP SUM	
5	074020	WATER POLLUTION CONTROL	LS	LUMP SUM	LUMP SUM	
6	074028	TEMPORARY FIBER ROLL	M	800		
7	074029	TEMPORARY SILT FENCE	M	700		
8	074030	TEMPORARY STRAW BALE	EA	150		
9 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
10 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
11 (S)	120159	TEMPORARY TRAFFIC STRIPE (PAINT)	M	7200		
12	120182	PORTABLE DELINEATOR	EA	380		
13	128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	LUMP SUM	LUMP SUM	
14 (S)	128660	TEMPORARY FLASHING BEACON	LS	LUMP SUM	LUMP SUM	
15	150206	ABANDON CULVERT	M	470		
16	150305	OBLITERATE SURFACING	M2	2060		
17	150662	REMOVE METAL BEAM GUARD RAILING	M	610		
18	150705	REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING	M2	38		
19	150713	REMOVE PAVEMENT MARKING	M2	78		
20	150742	REMOVE ROADSIDE SIGN	EA	110		

ENGINEER'S ESTIMATE

02-310204

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	150805	REMOVE CULVERT	EA	43		
22	152320	RESET ROADSIDE SIGN	EA	13		
23	152370	RELOCATE MAILBOX	EA	22		
24	152390	RELOCATE ROADSIDE SIGN	EA	5		
25 (S)	153154	COLD PLANE ASPHALT CONCRETE PAVEMENT (60 MM MAXIMUM)	M2	2010		
26	031332	REMOVE WINGWALL	EA	1		
27	160101	CLEARING AND GRUBBING	LS	LUMP SUM	LUMP SUM	
28	180101	BINDER (DUST PALLIATIVE)	TONN	210		
29	190101	ROADWAY EXCAVATION	M3	78 300		
30	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
31	193114	SAND BACKFILL	M3	48		
32	031333	STRUCTURE BACKFILL (SLURRY CEMENT)	M3	200		
33	194001	DITCH EXCAVATION	M3	250		
34	198007	IMPORTED MATERIAL (SHOULDER BACKING)	TONN	9120		
35	198200	SUBGRADE ENHANCEMENT FABRIC	M2	3460		
36	200114	ROCK BLANKET	M2	17		
37 (S)	203014	FIBER (EROSION CONTROL)	KG	19 800		
38 (S)	203024	COMPOST (EROSION CONTROL)	KG	65 000		
39 (S)	203026	MOVE-IN, MOVE-OUT (EROSION CONTROL)	EA	2		
40 (S)	203045	PURE LIVE SEED (EROSION CONTROL)	KG	1390		

ENGINEER'S ESTIMATE

02-310204

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41 (S)	203056	COMMERCIAL FERTILIZER (EROSION CONTROL)	KG	3710		
42 (S)	203061	STABILIZING EMULSION (EROSION CONTROL)	KG	3340		
43	260201	CLASS 2 AGGREGATE BASE	M3	33 000		
44	374206	SEAL RANDOM CRACKS	LNKM	20		
45	390095	REPLACE ASPHALT CONCRETE SURFACING	M3	2740		
46	390153	ASPHALT CONCRETE (TYPE A)	TONN	70 000		
47	391031	PAVING ASPHALT (BINDER- PAVEMENT REINFORCING FABRIC)	TONN	31		
48	393001	PAVEMENT REINFORCING FABRIC	M2	26 200		
49	031334	DRIVEWAYS (TYPE 1)	EA	110		
50	031335	DRIVEWAYS (TYPE 2)	EA	10		
51	394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	M2	330		
52	394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	M	240		
53	031336	PRECAST REINFORCED CONCRETE BOX CULVERT (1.5 M X 0.9 M)	M	26		
54 (F)	510129	CLASS 2 CONCRETE (BOX CULVERT)	M3	29		
55 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	101		
56	510526	MINOR CONCRETE (BACKFILL)	M3	570		
57	511106	DRILL AND BOND DOWEL	M	22		
58 (F)	520107	BAR REINFORCING STEEL (BOX CULVERT)	KG	3470		
59	566011	ROADSIDE SIGN - ONE POST	EA	90		
60	031337	ROADSIDE SIGN - SPECIAL METAL POST	EA	4		

ENGINEER'S ESTIMATE

02-310204

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	566012	ROADSIDE SIGN - TWO POST	EA	9		
62	620904	300 MM ALTERNATIVE PIPE CULVERT	M	29		
63	620909	450 MM ALTERNATIVE PIPE CULVERT	M	1200		
64	620913	600 MM ALTERNATIVE PIPE CULVERT	M	1710		
65	620919	750 MM ALTERNATIVE PIPE CULVERT	M	64		
66	620924	900 MM ALTERNATIVE PIPE CULVERT	M	14		
67	620930	1050 MM ALTERNATIVE PIPE CULVERT	M	15		
68	625382	525 MM X 375 MM ALTERNATIVE PIPE ARCH CULVERT	M	300		
69	625388	700 MM X 500 MM ALTERNATIVE PIPE ARCH CULVERT	M	56		
70	692301	ANCHOR ASSEMBLY	EA	1		
71	698091	300 MM ALTERNATIVE PIPE DOWNDRAIN	M	26		
72	698169	600 MM ALTERNATIVE PIPE DOWNDRAIN	M	12		
73	700659	900 MM CORRUGATED STEEL PIPE INLET (2.77 MM THICK)	M	35		
74	703233	GRATED LINE DRAIN	M	67		
75	031338	1200 MM WELDED STEEL PIPE (6.32 MM THICK)	M	14		
76	705044	450 MM STEEL FLARED END SECTION	EA	110		
77	705045	600 MM STEEL FLARED END SECTION	EA	45		
78	705047	750 MM STEEL FLARED END SECTION	EA	3		
79	705474	525 MM X 375 MM STEEL FLARED END PIPE ARCH SECTION	EA	12		
80	705476	700 MM X 500 MM STEEL FLARED END PIPE ARCH SECTION	EA	6		

ENGINEER'S ESTIMATE

02-310204

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
81	721008	ROCK SLOPE PROTECTION (LIGHT, METHOD B)	M3	140		
82	729010	ROCK SLOPE PROTECTION FABRIC	M2	160		
83	731516	MINOR CONCRETE (DRIVEWAY)	M3	66		
84	731517	MINOR CONCRETE (GUTTER)	M3	270		
85 (F)	750001	MISCELLANEOUS IRON AND STEEL	KG	5105		
86	820108	DELINEATOR (CLASS 2)	EA	460		
87	031339	HIGHWAY POST MARKER	EA	21		
88	820112	MARKER (CULVERT)	EA	110		
89	820133	OBJECT MARKER (TYPE N)	EA	3		
90	820151	OBJECT MARKER (TYPE L-1)	EA	260		
91 (S)	832003	METAL BEAM GUARD RAILING (WOOD POST)	M	630		
92 (S)	839521	CABLE RAILING	M	12		
93 (S)	839565	TERMINAL SYSTEM (TYPE SRT)	EA	10		
94 (S)	839568	TERMINAL ANCHOR ASSEMBLY (TYPE SFT)	EA	4		
95	839570	RETURN SECTION	EA	4		
96 (S)	840515	THERMOPLASTIC PAVEMENT MARKING	M2	330		
97 (S)	840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	M	51 500		
98 (S)	850122	PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	EA	3330		
99	860925	TRAFFIC MONITORING STATION (COUNT)	LS	LUMP SUM	LUMP SUM	
100	BLANK					

ENGINEER'S ESTIMATE

02-310204

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
101 (S)	203003	STRAW (EROSION CONTROL)	TONN	100		
102	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID: _____