

**** WARNING ** WARNING ** WARNING ** WARNING ****

This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

**NOTICE TO CONTRACTORS
AND
SPECIAL PROVISIONS
FOR BUILDING CONSTRUCTION IN
TRINITY COUNTY IN HAYFORK AT HAYFORK MAINTENANCE STATION**

DISTRICT 02, ROUTE 5717

**For Use in Connection with Standard Specifications Dated JULY 1999, Standard Plans Dated JULY 2004 and Labor
Surcharge and Equipment Rental Rates.**

CONTRACT NO. 02-350904

02-Tri-5717

Bids Open: February 6, 2008

Dated: December 24, 2007

OSD

IH

IMPORTANT SPECIAL NOTICES

- Attention is directed to Section 3, "Award and Execution of Contract," of these special provisions regarding submittal of the documents identified in Section 3-1.025, "Insurance Policies," of the Standard Specifications.

TABLE OF CONTENTS

NOTICE TO CONTRACTORS	1
COPY OF ENGINEER'S ESTIMATE	3
SPECIAL PROVISIONS	5
SECTION 1. SPECIFICATIONS AND PLANS	5
AMENDMENTS TO JULY 1999 STANDARD SPECIFICATIONS	5
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS	116
2-1.01 GENERAL	116
2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)	117
2-1.02A DVBE GOAL FOR THIS PROJECT	117
2-1.02B SUBMISSION OF DVBE INFORMATION	117
2-1.03 SMALL BUSINESS AND NON-SMALL BUSINESS SUBCONTRACTOR PREFERENCES	118
2-1.03A SMALL BUSINESS PREFERENCE	118
2-1.03B NON-SMALL BUSINESS SUBCONTRACTOR PREFERENCE	118
2-1.04 CALIFORNIA COMPANY PREFERENCE	118
SECTION 3. AWARD AND EXECUTION OF CONTRACT	119
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES	120
SECTION 5. GENERAL	120
SECTION 5-1. MISCELLANEOUS	120
5-1.01 GUARANTEE	120
5-1.019 COST REDUCTION INCENTIVE	121
5-1.02 LABOR NONDISCRIMINATION	121
5-1.03 INTEREST ON PAYMENTS	122
5-1.04 PUBLIC SAFETY	122
5-1.05 TESTING	123
5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES	123
5-1.065 SOLID WASTE DISPOSAL AND RECYCLING REPORT	123
5-1.07 (BLANK)	124
5-1.08 (BLANK)	124
5-1.09 SUBCONTRACTING	124
5-1.09A DVBE SUBCONTRACTING	124
5-1.09B NON-SMALL BUSINESS SUBCONTRACTING	124
5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS	125
5-1.103 RECORDS	125
5-1.104 INTERNET DAILY EXTRA WORK REPORT	125
5-1.105 ARCHAEOLOGICAL DISCOVERIES	126
5-1.11 PARTNERING	127
5-1.12 DISPUTE RESOLUTION ADVISOR	127
5-1.13 COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS	133
5-1.14 AREAS FOR CONTRACTOR'S USE	134
5-1.15 PAYMENTS	134
5-1.16 PROJECT INFORMATION	134
5-1.17 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD	135
WITHHOLDS	135
SECTION 6. (BLANK)	136
SECTION 7. (BLANK)	136
SECTION 8. MATERIALS	136
SECTION 8-1. MISCELLANEOUS	136
8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS	136
8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS	143
8-1.03 ENGINEERING FABRICS	148
8-1.04 ASPHALTIC EMULSION	149
SECTION 8-2. CONCRETE	149
8-2.01 PORTLAND CEMENT CONCRETE	149

8-2.02 FREEZING CONDITION REQUIREMENTS	149
SECTION 8-3. (BLANK).....	150
SECTION 9. (BLANK).....	150
SECTION 10. CONSTRUCTION DETAILS	150
SECTION 10-1. GENERAL.....	150
10-1.01 ORDER OF WORK.....	150
10-1.02 WATER POLLUTION CONTROL.....	150
IMPLEMENTATION REQUIREMENTS.....	152
INSPECTION AND MAINTENANCE.....	153
REPORTING REQUIREMENTS.....	153
PAYMENT.....	153
10-1.03 CONSTRUCTION SITE MANAGEMENT.....	154
SPILL PREVENTION AND CONTROL.....	154
MATERIAL MANAGEMENT.....	155
WASTE MANAGEMENT.....	157
NON-STORM WATER MANAGEMENT.....	159
DEWATERING.....	162
PAYMENT.....	162
10-1.04 TEMPORARY CONCRETE WASHOUT FACILITY.....	162
10-1.05 TEMPORARY CHECK DAM.....	164
10-1.06 TEMPORARY FIBER ROLL.....	166
10-1.07 PROGRESS SCHEDULE (CRITICAL PATH METHOD).....	167
10-1.08 OBSTRUCTIONS.....	170
10-1.09 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES.....	170
10-1.10 EXISTING HIGHWAY FACILITIES.....	171
REMOVE METAL BEAM GUARD RAILING.....	171
REMOVE FENCE.....	171
REMOVE PIPE GUARD POST.....	172
REMOVE CONCRETE.....	172
10-1.11 CLEARING AND GRUBBING.....	172
10-1.12 DEMOLISH BUILDING.....	172
PART 1 - GENERAL.....	172
PART 2 - PRODUCTS (Not applicable).....	173
PART 3 - EXECUTION.....	173
10-1.13 EARTHWORK.....	174
10-1.14 AGGREGATE BASE.....	174
10-1.15 FOG SEAL COAT.....	174
10-1.16 ASPHALT CONCRETE.....	174
10-1.17 CONCRETE STRUCTURES.....	178
10-1.18 SLOPE PROTECTION.....	178
10-1.19 MISCELLANEOUS CONCRETE CONSTRUCTION.....	178
10-1.20 MISCELLANEOUS IRON AND STEEL.....	178
10-1.21 CHAIN LINK FENCE.....	178
10-1.22 GUARD POST.....	178
SECTION 11. (BLANK).....	179
SECTION 12-1. GENERAL REQUIREMENTS.....	179
12-1.01 SCOPE.....	179
12-1.02 ABBREVIATIONS.....	179
12-1.03 GUARANTEE.....	180
12-1.04 AREAS FOR CONTRACTOR'S USE.....	180
12-1.05 COOPERATION.....	180
12-1.06 SUBMITTALS.....	180
12-1.07 PROGRESS SCHEDULE.....	181
12-1.08 SCHEDULE OF VALUES.....	181
12-1.09 INSPECTION.....	181
12-1.10 OBSTRUCTIONS.....	181
12-1.11 PRESERVATION OF PROPERTY.....	182
12-1.12 UTILITY CONNECTION.....	182
12-1.13 TEMPORARY UTILITIES.....	182

12-1.14	SANITARY FACILITIES.....	182
12-1.15	MEASUREMENT AND PAYMENT.....	182
12-1.16	PROJECT RECORD DRAWINGS.....	183
12-1.17	FIELD ENGINEERING.....	183
12-1.18	SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS	184
SECTION 12-2.	SITWORK.....	194
12-2.01	REMOVING PORTIONS OF EXISTING FACILITIES	194
	PART 1.- GENERAL.....	194
	PART 2.- PRODUCTS (Not applicable).....	194
	PART 3.- EXECUTION.....	194
12-2.02	RELOCATING MATERIALS AND EQUIPMENT	194
	PART 1.- GENERAL.....	194
	PART 2.- PRODUCTS (Not applicable).....	195
	PART 3.- EXECUTION.....	195
12-2.03	REMOVE WASTE DISPOSAL SYSTEM.....	195
	PART 1. - GENERAL.....	195
	PART 2. - PRODUCTS (Not applicable).....	195
	PART 3. - EXECUTION.....	195
12-2.04	CORE CONCRETE	196
	PART 1- GENERAL.....	196
	PART 3- EXECUTION.....	196
12-2.05	EARTHWORK FOR BUILDING WORK	196
	PART 1.- GENERAL.....	196
	PART 2.- PRODUCTS.....	197
	PART 3.- EXECUTION.....	198
12-2.06	AGGREGATE BASE	199
	PART 1.-GENERAL.....	199
	PART 2.-PRODUCTS.....	199
	PART 3.-EXECUTION.....	200
12-2.07	FREE DRAINING GRANULAR MATERIAL.....	200
	PART 1.- GENERAL.....	200
	PART 2.- PRODUCTS.....	200
	PART 3.- EXECUTION.....	200
12-2.08	TERMITE CONTROL.....	201
	PART 1.- GENERAL.....	201
	PART 2.- PRODUCTS.....	201
	PART 3.- EXECUTION.....	201
12-2.09	CAST-IN-DRILLED-HOLE CONCRETE PILES	202
	PART 1.- GENERAL.....	202
	PART 2.-PRODUCTS.....	202
	PART 3.-EXECUTION.....	202
12-2.10	PAINTED PAVEMENT MARKINGS	203
	PART 1.- GENERAL.....	203
	PART 2.- PRODUCTS.....	203
	PART 3.- EXECUTION.....	203
12-2.11	SANITARY SEWAGE DISPOSAL SYSTEM.....	204
	PART 1. - GENERAL.....	204
	PART 2. - PRODUCTS.....	205
	PART 3. - EXECUTION.....	206
12-2.12	GUARD POSTS.....	207
	PART 1.- GENERAL.....	207
	PART 2.- PRODUCTS.....	207
	PART 3.- EXECUTION.....	208
12-2.13	PARKING BUMPERS.....	208
	PART 1.- GENERAL.....	208
	PART 2.- PRODUCTS.....	208
	PART 3.- EXECUTION.....	208
12-2.14	ACCESSIBLE PARKING AND AUTHORIZATION SIGNS.....	208
	PART 1.- GENERAL.....	208

PART 2.- PRODUCTS.....	208
PART 3.- EXECUTION.....	209
SECTION 12-3. CONCRETE AND REINFORCEMENT	209
12-3.01 CAST-IN-PLACE CONCRETE	209
PART 1.- GENERAL.....	209
PART 2.- PRODUCTS.....	210
PART 3.- EXECUTION.....	214
SECTION 12-4. MASONRY	216
12-4.01 CONCRETE MASONRY UNITS	216
PART 1.- GENERAL.....	216
PART 2.- PRODUCTS.....	217
PART 3.- EXECUTION.....	218
SECTION 12-5. METALS	220
12-5.01 STRUCTURAL STEEL FOR BUILDINGS.....	220
PART 1.- GENERAL.....	220
PART 2.- PRODUCTS.....	221
PART 3.- EXECUTION.....	223
12-5.02 METAL DECK	224
PART 1.- GENERAL.....	224
PART 2.- PRODUCTS.....	224
PART 3.- EXECUTION.....	225
12-5.03 BUILDING MISCELLANEOUS METAL.....	225
PART 1.- GENERAL.....	225
PART 2.- PRODUCTS.....	226
PART 3.- EXECUTION.....	227
SECTION 12-6. WOOD AND PLASTICS.....	227
12-6.01 ROUGH CARPENTRY	227
PART 1.- GENERAL.....	227
PART 2.- PRODUCTS.....	228
PART 3.- EXECUTION.....	229
12-6.02 PREFABRICATED WOOD I-BEAM JOISTS.....	230
PART 1.- GENERAL.....	230
PART 2.- PRODUCTS.....	230
PART 3.- EXECUTION.....	231
12-6.03 FINISH CARPENTRY	231
PART 1.- GENERAL.....	231
PART 2.- PRODUCTS.....	231
PART 3.- EXECUTION.....	232
12-6.04 CABINETS	233
PART 1.- GENERAL.....	233
PART 2.- PRODUCTS.....	233
PART 3.- EXECUTION.....	235
SECTION 12-7. THERMAL AND MOISTURE PROTECTION	235
12-7.01 WATER REPELLENT COATING.....	235
PART 1.- GENERAL.....	235
PART 2.- PRODUCTS.....	236
PART 3.- EXECUTION.....	236
12-7.02 INSULATION (GENERAL).....	236
PART 1.- GENERAL.....	236
PART 2.- PRODUCTS (Not applicable.).....	237
PART 3.- EXECUTION (Not applicable.).....	237
12-7.03 BATT AND BLANKET INSULATION	237
PART 1.- GENERAL.....	237
PART 2.- PRODUCTS.....	237
PART 3.- EXECUTION.....	238
12-7.04 RIGID WALL INSULATION	238
PART 1.- GENERAL.....	238
PART 2.- PRODUCTS.....	238
PART 3.- EXECUTION.....	239

12-7.05 THROUGH-PENETRATION FIRESTOPPING	239
PART 1.- GENERAL	239
PART 2.- PRODUCTS.....	240
PART 3.-EXECUTION.....	240
12-7.06 WATER AND ICE BARRIER	240
PART 1.- GENERAL.....	240
PART 2.- PRODUCTS.....	241
PART 3.- EXECUTION.....	241
12-7.07 METAL ROOFING	241
PART 1.- GENERAL	241
PART 2.- PRODUCTS.....	242
PART 3.- EXECUTION.--.....	243
12-7.08 SNOW GUARDS	244
PART 1.- GENERAL	244
PART 2.- PRODUCTS.....	244
PART 3.- EXECUTION.....	245
12-7.09 SHEET METAL FLASHING	245
PART 1.- GENERAL.....	245
PART 2.- PRODUCTS.....	245
PART 3.- EXECUTION.....	246
12-7.10 ROOF SPECIALTIES.....	247
PART 1.- GENERAL	247
PART 2.- PRODUCTS.....	247
PART 3.- EXECUTION.....	248
12-7.11 SEALANTS AND CAULKING	248
PART 1.- GENERAL	248
PART 2.- PRODUCTS.....	249
PART 3.- EXECUTION.....	249
SECTION 12-8. DOORS AND WINDOWS	249
12-8.01 HINGED DOORS	249
PART 1.- GENERAL	249
PART 2.- PRODUCTS.....	250
PART 3.- EXECUTION.....	250
12-8.02 ATTIC ACCESS DOORS.....	251
PART 1.- GENERAL	251
PART 2.- PRODUCTS.....	251
PART 3.- EXECUTION.....	251
12-8.03 SECTIONAL OVERHEAD DOORS	251
PART 1.- GENERAL	251
PART 2.- PRODUCTS.....	252
PART 3.- EXECUTION.....	253
12-8.04 WINDOWS	254
PART 1.- GENERAL	254
PART 2.- PRODUCTS.....	254
PART 3.- EXECUTION.....	255
12-8.05 PRESSED METAL FRAMED WINDOWS.....	255
PART 1.- GENERAL	255
PART 2.- PRODUCTS.....	255
PART 3.- EXECUTION.....	255
12-8.06 FINISH HARDWARE	256
PART 1.- GENERAL	256
PART 2.- PRODUCTS.--.....	256
PART 3.- EXECUTION.....	259
12-8.07 GLAZING	260
PART 1.- GENERAL	260
PART 2.- PRODUCTS.....	261
PART 3.- EXECUTION.....	261
SECTION 12-9. FINISHES	262
12-9.01 GYPSUM WALLBOARD.....	262

PART 1.- GENERAL.....	262
PART 2.- PRODUCTS.....	262
PART 3.- EXECUTION.....	262
12-9.02 PORCELAIN CERAMIC TILE.....	263
PART 1.- GENERAL.....	263
PART 2.- PRODUCTS.....	264
PART 3.- EXECUTION.....	266
12-9.03 RUBBER BASE.....	269
PART 1.- GENERAL.....	269
PART 2.- PRODUCTS.....	269
PART 3.- EXECUTION.....	269
12-9.04 VINYL COMPOSITION TILE.....	269
PART 1.- GENERAL.....	269
PART 2.- PRODUCTS.....	269
PART 3.- EXECUTION.....	270
12-9.05 RESILIENT SHEET FLOORING.....	270
PART 1.- GENERAL.....	270
PART 2.- PRODUCTS.....	270
PART 3.- EXECUTION.....	271
12-9.06 PAINTING.....	271
PART 1.- GENERAL.....	271
PART 2.- PRODUCTS.....	272
PART 3.- EXECUTION.....	272
12-9.07 FIBERGLASS REINFORCED PLASTIC PANELS.....	275
PART 1.- GENERAL.....	275
PART 2.- PRODUCTS.....	276
PART 3.- EXECUTION.....	276
SECTION 12-10. SPECIALTIES.....	276
12-10.01 TACKBOARDS.....	276
PART 1.- GENERAL.....	276
PART 2.- PRODUCTS.....	276
PART 3.- EXECUTION.....	277
12-10.02 MARKER BOARDS.....	277
PART 1.- GENERAL.....	277
PART 2.- PRODUCTS.....	277
PART 3.- EXECUTION.....	277
12-10.03 METAL TOILET PARTITIONS.....	277
PART 1.- GENERAL.....	277
PART 2.- PRODUCTS.....	278
PART 3.- EXECUTION.....	278
12-10.04 LOUVERS.....	279
PART 1.- GENERAL.....	279
PART 2.-PRODUCTS.....	279
PART 3.- EXECUTION.....	279
12-10.05 SIGNS.....	279
PART 1.- GENERAL.....	279
PART 2.- PRODUCTS.....	279
PART 3.- EXECUTION.....	280
12-10.06 WARDROBE LOCKERS.....	280
PART 1.- GENERAL.....	280
PART 2.- PRODUCTS.....	280
PART 3.- EXECUTION.....	281
12-10.07 WOOD BENCHES.....	281
PART 1.- GENERAL.....	281
PART 2.- PRODUCTS.....	281
PART 3.- EXECUTION.....	282
12-10.08 FIRE EXTINGUISHERS AND CABINETS.....	282
PART 1.- GENERAL.....	282
PART 2.- PRODUCTS.....	282

PART 3.- EXECUTION.....	283
12-10.09 FREE STANDING STEEL SHELVING.....	283
PART 1.- GENERAL.....	283
PART 2.- PRODUCTS.....	283
PART 3.- EXECUTION.....	283
12-10.10 TOILET AND SHOWER ACCESSORIES.....	284
PART 1.- GENERAL.....	284
PART 2.- PRODUCTS.....	284
PART 3.- EXECUTION.....	285
12-10.11 MOP RACK.....	285
PART 1.- GENERAL.....	285
PART 2.- PRODUCTS.....	285
PART 3.- EXECUTION.....	285
SECTION 12-11. EQUIPMENT.....	285
12-11.01 HIGH PRESSURE WASHER (STATIONARY).....	285
PART 1.- GENERAL.....	285
PART 2.- PRODUCTS.....	286
PART 3.- EXECUTION.....	287
12-11.02 ICE MACHINE.....	288
PART 1.- GENERAL.....	288
PART 2.- PRODUCTS.....	288
PART 3.- EXECUTION.....	288
12-11.03 GARBAGE DISPOSAL.....	288
PART 1.- GENERAL.....	288
PART 2.- PRODUCTS.....	288
PART 3.- EXECUTION.....	288
12-11.04 REFRIGERATOR.....	288
PART 1.- GENERAL.....	288
PART 2.- PRODUCTS.....	288
PART 3.- EXECUTION.....	289
12-11.05 MICROWAVE OVEN.....	289
PART 1. GENERAL.....	289
PART 2.- PRODUCTS.....	289
PART 3.- EXECUTION.....	289
12-11.06 WORKBENCH.....	289
PART 1.- GENERAL.....	289
PART 2.- PRODUCTS.....	289
PART 3.- EXECUTION.....	290
SECTION 12-12. FURNISHINGS.....	290
12-12.01 VERTICAL BLINDS.....	290
PART 1.- GENERAL.....	290
PART 2.- PRODUCTS.....	290
PART 3.- EXECUTION.....	290
SECTION 12-13. (BLANK).....	290
SECTION 12-14. (BLANK).....	290
SECTION 12-15. MECHANICAL.....	290
12-15.01 MECHANICAL WORK.....	290
GENERAL.....	290
12-15.02 PIPE, FITTINGS AND VALVES.....	293
PART 1.- GENERAL.....	293
PART 2.- PRODUCTS.....	293
PART 3.- EXECUTION.....	297
12-15.03 MECHANICAL INSULATION.....	302
PART 1.- GENERAL.....	302
PART 2.- PRODUCTS.....	302
PART 3.- EXECUTION.....	303
12-15.04 PLUMBING FIXTURES.....	305
PART 1.- GENERAL.....	305
PART 2.- PRODUCTS.....	305

PART 3.- EXECUTION.....	308
12-15.05 WHEELCHAIR ACCESSIBLE SHOWER UNIT	308
PART 1.- GENERAL.....	308
PART 2.- PRODUCTS.....	309
PART 3.- EXECUTION.....	309
12-L5.06 LIQUEFIED PETROLEUM GAS (LPG) SYSTEM.....	309
PART 1.- GENERAL.....	309
PART 2.- PRODUCTS.....	309
PART 3.- EXECUTION.....	310
12-15.07 HEATING, VENTILATING AND AIR CONDITIONING EQUIPMENT AND SYSTEMS.....	310
PART 1.- GENERAL.....	310
PART 2.- PRODUCTS.....	311
PART 3.- EXECUTION.....	313
12-15.08 CATHODIC PROTECTION.....	315
PART 1- GENERAL.....	315
PART 2- PRODUCTS.....	315
PART 3- EXECUTION.....	316
SECTION 12-16. ELECTRICAL.....	317
12-16.01 ELECTRICAL WORK	317
PART 1.- GENERAL.....	317
12-16.02 BASIC MATERIALS AND METHODS.....	317
PART 1.- GENERAL.....	317
PART 2.- PRODUCTS.....	318
PART 3.- EXECUTION.....	322
12-16.03 SERVICE AND DISTRIBUTION.....	324
PART 1.- GENERAL.....	324
PART 2.- PRODUCTS.....	325
PART 3.- EXECUTION.....	325
12-16.04 ELECTRICAL EQUIPMENT.....	326
PART 1.- GENERAL.....	326
PART 2.- PRODUCTS.....	326
PART 3.- EXECUTION.....	328
12-16.05 LIGHTING.....	329
PART 1.- GENERAL.....	329
PART 2.- PRODUCTS.....	329
PART 3.- EXECUTION.....	331
12-16.06 INTRUSION ALARM SYSTEM	332
PART 1.- GENERAL.....	332
PART 2.- PRODUCTS.....	332
PART 3. EXECUTION.--	333
12-16.07 FIBERGLASS ANTENNA POLE.....	334

STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

RUBBER	Adhesive.--
BASE.--	
A10A	Acronyms and Abbreviations (A-L)
A10B	Acronyms and Abbreviations (M-Z)
A10C	Symbols (Sheet 1 of 2)
A10D	Symbols (Sheet 2 of 2)
A85	Chain Link Fence
RSP A87A	Curbs and Driveways
A87B	Asphalt Concrete Dikes
RSP A88A	Curb Ramp Details
D89	Pipe Headwalls
T2	Temporary Crash Cushion, Sand Filled (Shoulder Installations)
T56	Temporary Water Pollution Control Details (Temporary Fiber Roll)
T57	Temporary Water Pollution Control Details (Temporary Check Dam)
T59	Temporary Water Pollution Control Details (Temporary Concrete Washout Facility)
S94	Roadside Single Sheet Aluminum Signs, Rectangular Shape
S95	Roadside Single Sheet Aluminum Signs, Diamond Shape
ES-6A	Electrical Systems (Lighting Standards Types 15 and 21)
ES-6F	Electrical Systems (Lighting Standards Type 30 and 31, Base Plate Details)
RSP ES-7M	Electrical Systems (Signal and Lighting Standards – Details No. 1)
ES-7N	Electrical Systems (Signal and Lighting Standards – Details No. 2)
ES-8	Electrical Systems (Pull Box Details)
ES-10	Electrical Systems (Isolux Diagrams)
ES-13A	Electrical Systems (Splicing Details)
ES-13B	Electrical Systems (Wiring Details and Fuse Ratings)

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

CONTRACT NO. 02-350904

02-Tri-5717

Sealed proposals for the work shown on the plans entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR BUILDING CONSTRUCTION IN TRINITY COUNTY IN HAYFORK AT HAYFORK MAINTENANCE STATION

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on February 6, 2008, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR BUILDING CONSTRUCTION IN TRINITY COUNTY IN HAYFORK AT HAYFORK MAINTENANCE STATION

General work description: Construct Office, Equipment Bays, and Covered Storage.

This project has a goal of 3 percent disabled veteran business enterprise (DVBE) participation.

No prebid meeting is scheduled for this project.

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A license or Class B license or a combination of Class C licenses which constitutes a majority of the work.

The Contractor must also be properly licensed at the time the bid is submitted, except that on a joint venture bid a joint venture license may be obtained by a combination of licenses after bid opening but before award in conformance with Business and Professions Code, Section 7029.1.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

This project is subject to the State Small Business Preference, Non-Small Business Subcontractor Preference, and California Company Reciprocal Preference.

The District in which the work for this project is located has been incorporated into the Department's Northern Region. References in the Instruction to Bidders or the General Conditions or in the special provisions to the district shall be deemed to mean the Northern Region. The office of the District Director for the Northern Region is located at Marysville.

Inquiries or questions based on alleged patent ambiguity of the plans, specifications or estimate must be communicated as a bidder inquiry prior to bid opening. Any such inquiries or questions, submitted after bid opening, will not be treated as a bid protest.

The Department will consider bidder inquiries only when made in writing and shall be submitted to CALTRANS North Region Construction Office by either E-mail or Fax:

E-mail: inquiry_nr_bid@dot.ca.gov

FAX Number: (530) 822-4324

Responses to the bidder will be posted on the Internet at:

Contract No. 02-350904

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

The successful bidder shall furnish a payment bond and a performance bond.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' Internet Web Site at: <http://www.dir.ca.gov>. Future effective general prevailing wage rates which have been predetermined and are on file with the Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated December 24, 2007

WLW

**COPY OF ENGINEER'S ESTIMATE
(NOT TO BE USED FOR BIDDING PURPOSES)**

02-350904

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
1	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM
2	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM
3	074028	TEMPORARY FIBER ROLL	M	100
4	074032	TEMPORARY CONCRETE WASHOUT FACILITY	EA	2
5	074035	TEMPORARY CHECK DAM	M	17
6	150605	REMOVE FENCE	M	36
7	150662	REMOVE METAL BEAM GUARD RAILING	M	7
8	013017	REMOVE PIPE GUARD POST	EA	20
9	153210	REMOVE CONCRETE	M3	9
10	160101	CLEARING AND GRUBBING	LS	LUMP SUM
11	160132	DEMOLISH BUILDING	LS	LUMP SUM
12	190101	ROADWAY EXCAVATION	M3	2660
13	260201	CLASS 2 AGGREGATE BASE	M3	1710
14	374002	ASPHALTIC EMULSION (FOG SEAL COAT)	TONN	12
15	390102	ASPHALT CONCRETE (TYPE A)	TONN	2850
16	394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	M	200
17	510501	MINOR CONCRETE	M3	9
18 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	8.3
19	721616	CONCRETED-ROCK SLOPE PROTECTION (COBBLE, METHOD B)	M3	8
20	729010	ROCK SLOPE PROTECTION FABRIC	M2	24

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
21	731626	MINOR CONCRETE (CURB AND CURB RAMP)	M3	0.7
22 (F)	750001	MISCELLANEOUS IRON AND STEEL	KG	12
23	800391	CHAIN LINK FENCE (TYPE CL-1.8)	M	36
24	802596	3.7 M CHAIN LINK GATE (TYPE CL-1.8)	EA	2
25	013018	PIPE GUARD POST	EA	5
26	994650	BUILDING WORK	LS	LUMP SUM

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISIONS

Annexed to Contract No. 02-350904

SECTION 1. SPECIFICATIONS AND PLANS

The work embraced herein shall conform to the provisions in the Standard Specifications dated July 1999, and the Standard Plans dated July 2004, of the Department of Transportation insofar as the same may apply, and these special provisions.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and shall be used in lieu of the conflicting portions.

AMENDMENTS TO JULY 1999 STANDARD SPECIFICATIONS

UPDATED NOVEMBER 2, 2007

SECTION 0: GLOBAL REVISIONS

Issue Date: August 17, 2007

Blank

SECTION 1: DEFINITIONS AND TERMS

Issue Date: October 19, 2007

Section 1-1.01, "General," of the Standard Specifications is amended by adding the following:

- The Department is gradually changing the style and language of the specifications. The new style and language includes:

1. Use of:

- 1.1. Imperative mood
- 1.2. Introductory modifiers
- 1.3. Conditional clauses

2. Elimination of:

- 2.1. Language variations
- 2.2. Definitions for industry-standard terms
- 2.3. Redundant specifications
- 2.4. Needless cross-references

- The use of this new style does not change the meaning of a specification not yet using this style.

- The specifications are written to the Bidder before award and the Contractor after. Before award, interpret sentences written in the imperative mood as starting with "The Bidder must" and interpret "you" as "the Bidder" and "your" as "the Bidder's." After award, interpret sentences written in the imperative mood as starting with "The Contractor must" and interpret "you" as "the Contractor" and "your" as "the Contractor's."
- Unless an object or activity is specified to be less than the total, the quantity or amount is all of the object or activity.
- All items in a list apply unless the items are specified as choices.
- Interpret terms as defined in the Contract documents. A term not defined in the Contract documents has the meaning defined in Means Illustrated Construction Dictionary, Condensed Version, Second Edition.

The 1st table in Section 1-1.02, "Abbreviations," of the Standard Specifications is amended by adding:

SSPC	The Society for Protective Coatings
------	-------------------------------------

Section 1, "Definitions and Terms," of the Standard Specifications is amended by adding the following sections:

1-1.082 BUSINESS DAY

- Day on the calendar except Saturday or holiday.

1-1.084 CALIFORNIA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES

• The California Manual on Uniform Traffic Control Devices for Streets and Highways (California MUTCD) is issued by the Department of Transportation and is the Federal Highway Administration's MUTCD 2003 Edition, as amended for use in California. Part 6 of the California MUTCD, "Temporary Traffic Control," supersedes the Department's Manual of Traffic Controls.

1-1.125 DEDUCTION

• Amount of money permanently taken from progress payment and final payment. Deductions are cumulative and are not retentions under Pub Cont Code § 7107.

1-1.205 FEDERAL-AID CONTRACT

- Contract that has a Federal-aid project number on the cover of the Notice to Contractors and Special Provisions.

1-1.245 HOLIDAY

1. Every Sunday
2. January 1st, New Year's Day
3. 3rd Monday in January, Birthday of Martin Luther King, Jr.
4. February 12th, Lincoln's Birthday
5. 3rd Monday in February, Washington's Birthday
6. March 31st, Cesar Chavez Day
7. Last Monday in May, Memorial Day
8. July 4th, Independence Day
9. 1st Monday in September, Labor Day
10. 2nd Monday in October, Columbus Day
11. November 11th, Veterans Day
12. 4th Thursday in November, Thanksgiving Day
13. 4th Friday in November, Day after Thanksgiving Day
14. December 25th, Christmas Day

• If January 1st, February 12th, March 31st, July 4th, November 11th, or December 25th falls on a Sunday, the Monday following is a holiday. If November 11th falls on a Saturday, the preceding Friday is a holiday.

1-1.475 WITHHOLD

• Money temporarily or permanently taken from progress payment. Withholds are cumulative and are not retentions under Pub Cont Code § 7107.

Section 1-1.25, "Laboratory," of the Standard Specifications is amended to read:

1-1.25 LABORATORY

- The Division of Engineering Services - Materials Engineering and Testing Services and Division of Engineering Services - Geotechnical Services of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean Division of Engineering Services - Materials Engineering and Testing Services and Division of Engineering Services - Geotechnical Services, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

Section 1-1.255, "Legal Holidays," of the Standard Specifications is deleted.

Section 1-1.265, "Manual of Traffic Controls," of the Standard Specifications is deleted.

Section 1-1.275, "Office of Structure Design," of the Standard Specifications is amended to read:

1-1.275 OFFICES OF STRUCTURE DESIGN

- The Offices of Structure Design of the Department of Transportation. When the specifications require working drawings to be submitted to the Offices of Structure Design, the drawings shall be submitted to: Offices of Structure Design, Documents Unit, Mail Station 9-4/4I, 1801 30th Street, Sacramento, CA 95816, Telephone (916) 227-8252.

Section 1-1.39, "State," of the Standard Specifications is amended to read:

1-1.39 STATE

- The State of California, including its agencies, departments, or divisions, whose conduct or action is related to the work.

SECTION 2: PROPOSAL REQUIREMENTS AND CONDITIONS

Issue Date: June 19, 2003

Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications is amended to read:

2-1.03 Examination of Plans, Specifications, Contract, and Site of Work

- The bidder shall examine carefully the site of the work contemplated, the plans and specifications, and the proposal and contract forms therefor. The submission of a bid shall be conclusive evidence that the bidder has investigated and is satisfied as to the general and local conditions to be encountered, as to the character, quality and scope of work to be performed, the quantities of materials to be furnished and as to the requirements of the proposal, plans, specifications and the contract.

- The submission of a bid shall also be conclusive evidence that the bidder is satisfied as to the character, quality and quantity of surface and subsurface materials or obstacles to be encountered insofar as this information was reasonably ascertainable from an inspection of the site and the records of exploratory work done by the Department as shown in the bid documents, as well as from the plans and specifications made a part of the contract.

- Where the Department has made investigations of site conditions including subsurface conditions in areas where work is to be performed under the contract, or in other areas, some of which may constitute possible local material sources, bidders or contractors may, upon written request, inspect the records of the Department as to those investigations subject to and upon the conditions hereinafter set forth.

- Where there has been prior construction by the Department or other public agencies within the project limits, records of the prior construction that are currently in the possession of the Department and which have been used by, or are known to, the designers and administrators of the project will be made available for inspection by bidders or contractors, upon written request, subject to the conditions hereinafter set forth. The records may include, but are not limited to, as-built drawings, design calculations, foundation and site studies, project reports and other data assembled in connection with the investigation, design, construction and maintenance of the prior projects.

- Inspection of the records of investigations and project records may be made at the office of the district in which the work is situated, or in the case of records of investigations related to structure work, at the Transportation Laboratory in Sacramento, California.

- When a log of test borings or other record of geotechnical data obtained by the Department's investigation of surface and subsurface conditions is included with the contract plans, it is furnished for the bidders' or Contractor's information and its use shall be subject to the conditions and limitations set forth in this Section 2-1.03.
- In some instances, information considered by the Department to be of possible interest to bidders or contractors has been compiled as "Materials Information." The use of the "Materials Information" shall be subject to the conditions and limitations set forth in this Section 2-1.03 and Section 6-2, "Local Materials."
 - When cross sections are not included with the plans, but are available, bidders or contractors may inspect the cross sections and obtain copies for their use, at their expense.
 - When cross sections are included with the contract plans, it is expressly understood and agreed that the cross sections do not constitute part of the contract, do not necessarily represent actual site conditions or show location, character, dimensions and details of work to be performed, and are included in the plans only for the convenience of bidders and their use is subject to the conditions and limitations set forth in this Section 2-1.03.
 - When contour maps were used in the design of the project, the bidders may inspect those maps, and if available, they may obtain copies for their use.
 - The availability or use of information described in this Section 2-1.03 is not to be construed in any way as a waiver of the provisions of the first paragraph in this Section 2-1.03 and bidders and contractors are cautioned to make independent investigations and examinations as they deem necessary to be satisfied as to conditions to be encountered in the performance of the work and, with respect to possible local material sources, the quality and quantity of material available from the property and the type and extent of processing that may be required in order to produce material conforming to the requirements of the specifications.
 - The Department assumes no responsibility for conclusions or interpretations made by a bidder or contractor based on the information or data made available by the Department. The Department does not assume responsibility for representation made by its officers or agents before the execution of the contract concerning surface or subsurface conditions, unless that representation is expressly stated in the contract.
 - No conclusions or interpretations made by a bidder or contractor from the information and data made available by the Department will relieve a bidder or contractor from properly fulfilling the terms of the contract.

SECTION 3: AWARD AND EXECUTION OF CONTRACT

Issue Date: August 17, 2007

Section 3, "Award and Execution of Contract," of the Standard Specifications is amended by adding the following section after Section 3-1.02, "Contract Bonds":

3-1.025 INSURANCE POLICIES

- The successful bidder shall submit:
 1. Copy of its commercial general liability policy and its excess policy or binder until such time as a policy is available, including the declarations page, applicable endorsements, riders, and other modifications in effect at the time of contract execution. Standard ISO form No. CG 0001 or similar exclusions are allowed if not inconsistent with Section 7-1.12, "Indemnification and Insurance." Allowance of additional exclusions is at the discretion of the Department.
 2. Certificate of insurance showing all other required coverages. Certificates of insurance, as evidence of required insurance for the auto liability and any other required policy, shall set forth deductible amounts applicable to each policy and all exclusions that are added by endorsement to each policy. The evidence of insurance shall provide that no cancellation, lapse, or reduction of coverage will occur without 10 days prior written notice to the Department.
 3. A declaration under the penalty of perjury by a certified public accountant certifying the accountant has applied Generally Accepted Accounting Principles (GAAP) guidelines confirming the successful bidder has sufficient funds and resources to cover any self-insured retentions if the self-insured retention is \$50 000 or higher.
- If the successful bidder uses any form of self-insurance for workers compensation in lieu of an insurance policy, it shall submit a certificate of consent to self-insure in accordance with the provisions of Section 3700 of the Labor Code.

Section 3-1.03, "Execution of Contract," of the Standard Specifications is amended to read:

3-1.03 EXECUTION OF CONTRACT

- The contract shall be signed by the successful bidder and returned, together with the contract bonds and the documents identified in Section 3-1.025, "Insurance Policies," within 10 business days of receiving the contract for execution.

Section 3-1.04, "Failure to Execute Contract," of the Standard Specifications is amended to read:

3-1.04 FAILURE TO EXECUTE CONTRACT

- Failure of the lowest responsible bidder, the second lowest responsible bidder, or the third lowest responsible bidder to execute the contract as required in Section 3-1.03, "Execution of Contract," within 10 business days of receiving the contract for execution shall be just cause for the forfeiture of the proposal guaranty. The successful bidder may file with the Department a written notice, signed by the bidder or the bidder's authorized representative, specifying that the bidder will refuse to execute the contract if it is presented. The filing of this notice shall have the same force and effect as the failure of the bidder to execute the contract and furnish acceptable bonds within the time specified.

Section 3-1.05, "Return of Proposal Guaranties," of the Standard Specifications is amended to read:

3-1.05 RETURN OF PROPOSAL GUARANTIES

- The Department keeps the proposal guaranties of the 1st, 2nd and 3rd lowest responsible bidders until the contract has been executed. The other bidders' guaranties, other than bidders' bonds, are returned upon determination of the 1st, 2nd, and 3rd apparent lowest bidders, and their bidders' bonds are of no further effect.

SECTION 4: SCOPE OF WORK

Issue Date: August 17, 2007

Section 4-1.01, "Intent of Plans and Specifications," of the Standard Specifications is amended by adding the following:

- Nothing in the specifications voids the Contractor's public safety responsibilities.

SECTION 5: CONTROL OF WORK

Issue Date: October 19, 2007

Section 5, "Control of Work," of the Standard Specifications is amended by adding the following sections:

5-1.005 GENERAL

- Failure to comply with any specification part is a breach of the contract and a waiver of your right to time or payment adjustment.
- After contract approval, submit documents and direct questions to the Engineer. Orders, approvals, and requests to the Contractor are by the Engineer.
- The Engineer furnishes the following in writing:
 1. Approvals
 2. Notifications
 3. Orders
- The Contractor must furnish the following in writing:
 1. Assignments
 2. Notifications
 3. Proposals
 4. Requests, sequentially numbered
 5. Subcontracts
 6. Test results
- The Department rejects a form if it has any error or any omission.

- Convert foreign language documents to English.
- Use contract administration forms available at the Department's Web site.
- If the last day for submitting a document falls on a Saturday or holiday, it may be submitted on the next business day with the same effect as if it had been submitted on the day specified.

5-1.015 RECORD RETENTION, INSPECTION, COPYING, AND AUDITING

- Retain project records and make them available for inspection, copying, and auditing by State representatives from bid preparation through:

1. Final payment
2. Resolution of claims, if any

- For at least 3 years after the later of these, retain and make available for inspection, copying, and auditing cost records by State representatives including:

1. Records pertaining to bid preparation
2. Overhead
3. Payroll records and certified payroll
4. Payments to suppliers and subcontractors
5. Cost accounting records
6. Records of subcontractors and suppliers

- Maintain the records in an organized way in the original format, electronic and hard copy, conducive to professional review and audit.

- Before contract acceptance, the State representative notifies the Contractor, subcontractor, or supplier 5 days before inspection, copying, or auditing.

- If an audit is to start more than 30 days after contract acceptance, the State representative notifies the Contractor, subcontractor, or supplier when the audit is to start.

Section 5-1.01, "Authority of Engineer," of the Standard Specifications is amended by adding:

- Failure to enforce a contract provision does not waive enforcement of any contract provision.

Section 5-1.02A, "Trench Excavation Safety Plans," of the Standard Specifications is amended to read:

5-1.02A Excavation Safety Plans

• The Construction Safety Orders of the Division of Occupational Safety and Health shall apply to all excavations. For all excavations 1.5 m or more in depth, the Contractor shall submit to the Engineer a detailed plan showing the design and details of the protective systems to be provided for worker protection from the hazard of caving ground during excavation. The detailed plan shall include any tabulated data and any design calculations used in the preparation of the plan. Excavation shall not begin until the detailed plan has been reviewed and approved by the Engineer.

• Detailed plans of protective systems for which the Construction Safety Orders require design by a registered professional engineer shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California, and shall include the soil classification, soil properties, soil design calculations that demonstrate adequate stability of the protective system, and any other design calculations used in the preparation of the plan.

• No plan shall allow the use of a protective system less effective than that required by the Construction Safety Orders.

• If the detailed plan includes designs of protective systems developed only from the allowable configurations and slopes, or Appendices, contained in the Construction Safety Orders, the plan shall be submitted at least 5 days before the Contractor intends to begin excavation. If the detailed plan includes designs of protective systems developed from tabulated data, or designs for which design by a registered professional engineer is required, the plan shall be submitted at least 3 weeks before the Contractor intends to begin excavation.

- Attention is directed to Section 7-1.01E, "Trench Safety."

Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications, and Special Provisions," of the Standard Specifications is amended to read:

5-1.04 CONTRACT COMPONENTS

- A component in one contract part applies as if appearing in each. The parts are complementary and describe and provide for a complete work.

- If a discrepancy exists:

1. The governing ranking of contract parts in descending order is:

- 1.1. Special provisions
- 1.2. Project plans
- 1.3. Revised Standard Plans
- 1.4. Standard Plans
- 1.5. Amendments to the Standard Specifications
- 1.6. Standard Specifications
- 1.7. Project information

2. Written numbers and notes on a drawing govern over graphics

3. A detail drawing governs over a general drawing

4. A detail specification governs over a general specification

5. A specification in a section governs over a specification referenced by that section

- If a discrepancy is found or confusion arises, request correction or clarification.

Section 5-1.07, "Lines and Grades," of the Standard Specifications is replaced with the following:

5-1.07 LINES AND GRADES

- The Engineer places stakes and marks under Chapter 12, "Construction Surveys," of the Department's Surveys Manual.

- Submit your request for Department-furnished stakes:

1. On a Request for Construction Stakes form. Ensure:

- 1.1. Requested staking area is ready for stakes

- 1.2. You use the stakes in a reasonable time

2. A reasonable time before starting an activity using the stakes

- Establish priorities for stakes and note priorities on the request.

- Preserve stakes and marks placed by the Engineer. If the stakes or marks are destroyed, the Engineer replaces them at the Engineer's earliest convenience and deducts the cost.

SECTION 6: CONTROL OF MATERIALS

Issue Date: August 17, 2007

Section 6-1.05, "Trade Names and Alternatives," of the Standard Specifications is amended to read:

6-1.05 Specific Brand or Trade Name and Substitution

- A reference to a specific brand or trade name establishes a quality standard and is not intended to limit competition. You may use a product that is equal to or better than the specified brand or trade name if approved.

- Submit a substitution request within a time period that:

1. Follows Contract award

2. Allows 30 days for review

3. Causes no delay

- Include substantiating data with the substitution request that proves the substitution:

1. Is of equal or better quality and suitability
2. Causes no delay in product delivery and installation

Section 6, "Control of Materials," of the Standard Specifications is amended by adding the following sections:

6-1.085 BUY AMERICA (23 CFR 635.410)

- For a Federal-aid contract, furnish steel and iron materials to be incorporated into the work that are produced in the United States except:

1. Foreign pig iron and processed, pelletized, and reduced iron ore may be used in the domestic production of the steel and iron materials [60 Fed Reg 15478 (03/24/1995)]
2. If the total combined cost of the materials does not exceed the greater of 0.1 percent of the total bid or \$2 500, material produced outside the United States may be used

- Production includes:

1. Processing steel and iron materials, including smelting or other processes that alter the physical form or shape (such as rolling, extruding, machining, bending, grinding, and drilling) or chemical composition
2. Coating application, including epoxy coating, galvanizing, and painting, that protects or enhances the value of steel and iron materials

- For steel and iron materials to be incorporated into the work, submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications that certifies all production processes occurred in the United States except for the above exceptions.

6-1.087 BUY AMERICA (PUB RES CODE § 42703(d))

- Furnish crumb rubber to be incorporated into the work that is produced in the United States and is derived from waste tires taken from vehicles owned and operated in the United States.

- For crumb rubber to be incorporated into the work, submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications that certifies only crumb rubber manufactured in the United States and derived from waste tires taken from vehicles owned and operated in the United States is used.

The 7th and 8th paragraph of Section 6-2.01, "General," of the Standard Specifications are amended to read:

- Upon the Contractor's written request, the Department tests materials from an untested local source. If satisfactory material from that source is used in the work, the Department does not charge the Contractor for the tests; otherwise, the Department deducts the test cost.

The 2nd sentence of the 7th paragraph of Section 6-2.02, "Possible Local Material Sources," of the Standard Specifications is amended to read:

- The Department deducts the charges for the removed material.

SECTION 7: LEGAL RELATIONS AND RESPONSIBILITY

Issue Date: August 17, 2007

Section 7-1.01, "Laws To Be Observed," of the Standard Specifications is amended to read:

7-1.01 LAWS TO BE OBSERVED

- Comply with laws, orders, decrees, and permits. Indemnify and defend the State against any claim or liability arising from the violation of a law, order, decree, or permit by you or your employees. Immediately report to the Engineer in writing a discrepancy or inconsistency between the contract and a law, order, decree, or permit.

The 3rd listed requirement of the 1st paragraph of Section 7-1.01A(2), "Prevailing Wage," of the Standard Specifications is amended to read:

3. Upon becoming aware of the subcontractor's failure to pay the specified prevailing rate of wages to the subcontractor's workers, the Contractor must diligently take corrective action to stop or rectify the failure, including withholding sufficient funds due the subcontractor for work performed on the public works project.

The 2nd paragraph of Section 7-1.01A(2), "Prevailing Wage," of the Standard Specifications is amended to read:

- Pursuant to Section 1775 of the Labor Code, the Division of Labor Standards Enforcement must notify the Contractor on a public works project within 15 days of the receipt by the Division of Labor Standards Enforcement of a complaint of the failure of a subcontractor on that public works project to pay workers the general prevailing rate of per diem wages. If the Division of Labor Standards Enforcement determines that employees of a subcontractor were not paid the general prevailing rate of per diem wages and if the Department did not withhold sufficient money under the contract to pay those employees the balance of wages owed under the general prevailing rate of per diem wages, the Contractor must withhold an amount of moneys due the subcontractor sufficient to pay those employees the general prevailing rate of per diem wages if requested by the Division of Labor Standards Enforcement. The Contractor must pay any money withheld from and owed to a subcontractor upon receipt of notification by the Division of Labor Standards Enforcement that the wage complaint has been resolved. If notice of the resolution of the wage complaint has not been received by the Contractor within 180 days of the filing of a valid notice of completion or acceptance of the public works project, whichever occurs later, the Contractor must pay all moneys withheld from the subcontractor to the Department. The Department withholds these moneys pending the final decision of an enforcement action.

The 2nd paragraph of Section 7-1.01A(3), "Payroll Records," of the Standard Specifications is amended to read:

- The Department withholds the penalties specified in subdivision (g) of Labor Code § 1776 for noncompliance with the requirements in Section 1776.

The 4th paragraph of Section 7-1.01A(3), "Payroll Records," of the Standard Specifications is amended to read:

- The Department withholds for delinquent or inadequate payroll records (Labor Code § 1771.5). If the Contractor has not submitted an adequate payroll record by the month's 15th day for the period ending on or before the 1st of that month, the Department withholds 10 percent of the monthly progress estimate, exclusive of mobilization. The Department does not withhold more than \$10 000 or less than \$1000.

The 5th paragraph of Section 7-1.01A(3), "Payroll Records," of the Standard Specifications is deleted.

The eighth paragraph of Section 7-1.09, "Public Safety," of the Standard Specifications is amended to read:

- Signs, lights, flags, and other warning and safety devices and their use shall conform to the requirements set forth in Part 6 of the California MUTCD. Signs or other protective devices furnished and erected by the Contractor, at the Contractor's expense, as above provided, shall not obscure the visibility of, nor conflict in intent, meaning and function of either existing signs, lights and traffic control devices or any construction area signs and traffic control devices for which furnishing of, or payment for, is provided elsewhere in the specifications. Signs furnished and erected by the Contractor, at the Contractor's expense, shall be approved by the Engineer as to size, wording and location.

The fourteenth paragraph of Section 7-1.09, "Public Safety," of the Standard Specifications is amended to read:

- The Contractor shall notify the Engineer not less than 18 days and no more than 90 days prior to the anticipated start of an operation that will change the vertical or horizontal clearance available to public traffic (including shoulders).

The sixteenth paragraph of Section 7-1.09, "Public Safety," of the Standard Specifications is amended to read:

- When vertical clearance is temporarily reduced to 4.72 m or less, low clearance warning signs shall be placed in accordance with Part 2 of the California MUTCD and as directed by the Engineer. Signs shall conform to the dimensions, color, and legend requirements of the California MUTCD and these specifications except that the signs shall have black letters and numbers on an orange retroreflective background. W12-2P signs shall be illuminated so that the signs are clearly visible.

Section 7-1.01A(6), "Workers' Compensation," of the Standard Specifications is amended to read:

7-1.101A(6) (Blank)

The last sentence of the 2nd paragraph of Section 7-1.11, "Preservation of Property," of the Standard Specifications is amended to read:

- The cost of the repairs must be borne by the Contractor and will be deducted.

Section 7-1.12, "Indemnification and Insurance," of the Standard Specifications is amended to read:

7-1.12 INDEMNIFICATION AND INSURANCE

• The Contractor's obligations regarding indemnification of the State of California and the requirements for insurance shall conform to the provisions in Section 3-1.025, "Insurance Policies," and Sections 7-1.12A, "Indemnification," and 7-1.12B, "Insurance," of this Section 7-1.12.

7-1.12A Indemnification

• The Contractor shall defend, indemnify, and save harmless the State, including its officers, employees, and agents (excluding agents who are design professionals) from any and all claims, demands, causes of action, damages, costs, expenses, actual attorneys' fees, losses or liabilities, in law or in equity (Section 7-1.12A Claims) arising out of or in connection with the Contractor's performance of this contract for:

1. Bodily injury including, but not limited to, bodily injury, sickness or disease, emotional injury or death to persons, including, but not limited to, the public, any employees or agents of the Contractor, the State, or any other contractor; and
2. Damage to property of anyone including loss of use thereof; caused or alleged to be caused in whole or in part by any negligent or otherwise legally actionable act or omission of the Contractor or anyone directly or indirectly employed by the Contractor or anyone for whose acts the Contractor may be liable.

• Except as otherwise provided by law, these requirements apply regardless of the existence or degree of fault of the State. The Contractor is not obligated to indemnify the State for Claims arising from conduct delineated in Civil Code Section 2782 and to Claims arising from any defective or substandard condition of the highway that existed at or before the start of work, unless this condition has been changed by the work or the scope of the work requires the Contractor to maintain existing highway facilities and the Claim arises from the Contractor's failure to maintain. The Contractor's defense and indemnity obligation shall extend to Claims arising after the work is completed and accepted if the Claims are directly related to alleged acts or omissions by the Contractor that occurred during the course of the work. State inspection is not a waiver of full compliance with these requirements.

• The Contractor's obligation to defend and indemnify shall not be excused because of the Contractor's inability to evaluate liability or because the Contractor evaluates liability and determine that the Contractor is not liable. The Contractor shall respond within 30 days to the tender of any Claim for defense and indemnity by the State, unless this time has been extended by the State. If the Contractor fails to accept or reject a tender of defense and indemnity within 30 days, in addition to any other remedy authorized by law, the Department may withhold such funds the State reasonably considers necessary for its defense and indemnity until disposition has been made of the Claim or until the Contractor accepts or rejects the tender of defense, whichever occurs first.

• With respect to third-party claims against the Contractor, the Contractor waives all rights of any type to express or implied indemnity against the State, its officers, employees, or agents (excluding agents who are design professionals).

• Nothing in the Contract is intended to establish a standard of care owed to any member of the public or to extend to the public the status of a third-party beneficiary for any of these indemnification specifications.

7-1.12B Insurance

7-1.12B(1) General

• Nothing in the contract is intended to establish a standard of care owed to any member of the public or to extend to the public the status of a third-party beneficiary for any of these insurance specifications.

7-1.12B(2) Casualty Insurance

• The Contractor shall procure and maintain insurance on all of its operations with companies acceptable to the State as follows:

1. The Contractor shall keep all insurance in full force and effect from the beginning of the work through contract acceptance.
2. All insurance shall be with an insurance company with a rating from A.M. Best Financial Strength Rating of A- or better and a Financial Size Category of VII or better.
3. The Contractor shall maintain completed operations coverage with a carrier acceptable to the State through the expiration of the patent deficiency in construction statute of repose set forth in Code of Civil Procedure Section 337.1.

7-1.12B(3) Workers' Compensation and Employer's Liability Insurance

- In accordance with Labor Code Section 1860, the Contractor shall secure the payment of worker's compensation in accordance with Labor Code Section 3700.
- In accordance with Labor Code Section 1861, the Contractor shall submit to the Department the following certification before performing the work:

I am aware of the provisions of Section 3700 of the Labor Code which require every employer to be insured against liability for workers' compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with such provisions before commencing the performance of the work of this contract.

- Contract execution constitutes certification submittal.
- The Contractor shall provide Employer's Liability Insurance in amounts not less than:
 1. \$1 000 000 for each accident for bodily injury by accident
 2. \$1 000 000 policy limit for bodily injury by disease
 3. \$1 000 000 for each employee for bodily injury by disease

- If there is an exposure of injury to the Contractor's employees under the U.S. Longshoremen's and Harbor Workers' Compensation Act, the Jones Act, or under laws, regulations, or statutes applicable to maritime employees, coverage shall be included for such injuries or claims.

7-1.12B(4) Liability Insurance

7-1.12B(4)(a) General

- The Contractor shall carry General Liability and Umbrella or Excess Liability Insurance covering all operations by or on behalf of the Contractor providing insurance for bodily injury liability and property damage liability for the following limits and including coverage for:

1. Premises, operations, and mobile equipment
2. Products and completed operations
3. Broad form property damage (including completed operations)
4. Explosion, collapse, and underground hazards
5. Personal injury
6. Contractual liability

7-1.12B(4)(b) Liability Limits/Additional Insureds

- The limits of liability shall be at least the amounts shown in the following table:

Total Bid	For Each Occurrence ¹	Aggregate for Products/Completed Operation	General Aggregate ²	Umbrella or Excess Liability ³
≤\$1 000 000	\$1 000 000	\$2 000 000	\$2 000 000	\$5 000 000
>\$1 000 000	\$1 000 000	\$2 000 000	\$2 000 000	\$10 000 000
≤\$5 000 000	\$1 000 000	\$2 000 000	\$2 000 000	\$10 000 000
>\$5 000 000	\$2 000 000	\$2 000 000	\$4 000 000	\$15 000 000
≤\$25 000 000	\$2 000 000	\$2 000 000	\$4 000 000	\$25 000 000
>\$25 000 000	\$2 000 000	\$2 000 000	\$4 000 000	\$25 000 000

1. Combined single limit for bodily injury and property damage.
2. This limit shall apply separately to the Contractor's work under this contract.
3. The umbrella or excess policy shall contain a clause stating that it takes effect (drops down) in the event the primary limits are impaired or exhausted.

- The Contractor shall not require certified Small Business subcontractors to carry Liability Insurance that exceeds the limits in the table above. Notwithstanding the limits specified herein, at the option of the Contractor, the liability insurance limits for certified Small Business subcontractors of any tier may be less than those limits specified in the table. For Small Business subcontracts, "Total Bid" shall be interpreted as the amount of subcontracted work to a certified Small Business.

- The State, including its officers, directors, agents (excluding agents who are design professionals), and employees, shall be named as additional insureds under the General Liability and Umbrella Liability Policies with respect to liability arising out of or connected with work or operations performed by or on behalf of the Contractor under this contract. Coverage for such additional insureds does not extend to liability:

- Arising from any defective or substandard condition of the roadway which existed at or before the time the Contractor started work, unless such condition has been changed by the work or the scope of the work requires the Contractor to maintain existing roadway facilities and the claim arises from the Contractor's failure to maintain;
- For claims occurring after the work is completed and accepted unless these claims are directly related to alleged acts or omissions of the Contractor that occurred during the course of the work; or
- To the extent prohibited by Insurance Code Section 11580.04

- Additional insured coverage shall be provided by a policy provision or by an endorsement providing coverage at least as broad as Additional Insured (Form B) endorsement form CG 2010, as published by the Insurance Services Office (ISO), or other form designated by the Department.

7-1.12B(4)(c) Contractor's Insurance Policy is Primary

- The policy shall stipulate that the insurance afforded the additional insureds applies as primary insurance. Any other insurance or self-insurance maintained by the State is excess only and shall not be called upon to contribute with this insurance.

7-1.12B(5) Automobile Liability Insurance

- The Contractor shall carry automobile liability insurance, including coverage for all owned, hired, and nonowned automobiles. The primary limits of liability shall be not less than \$1 000 000 combined single limit each accident for bodily injury and property damage. The umbrella or excess liability coverage required under Section 7-1.12B(4)(b) also applies to automobile liability.

7-1.12B(6) Policy Forms, Endorsements, and Certificates

- The Contractor shall provide its General Liability Insurance under Commercial General Liability policy form No. CG0001 as published by the Insurance Services Office (ISO) or under a policy form at least as broad as policy form No. CG0001.

7-1.12B(7) Deductibles

- The State may expressly allow deductible clauses, which it does not consider excessive, overly broad, or harmful to the interests of the State. Regardless of the allowance of exclusions or deductions by the State, the Contractor is responsible for any deductible amount and shall warrant that the coverage provided to the State is in accordance with Section 7-1.12B, "Insurance."

7-1.12B(8) Enforcement

- The Department may assure the Contractor's compliance with its insurance obligations. Ten days before an insurance policy lapses or is canceled during the contract period, the Contractor shall submit to the Department evidence of renewal or replacement of the policy.
- If the Contractor fails to maintain any required insurance coverage, the Department may maintain this coverage and withhold or charge the expense to the Contractor or terminate the Contractor's control of the work in accordance with Section 8-1.08, "Termination of Control."
- The Contractor is not relieved of its duties and responsibilities to indemnify, defend, and hold harmless the State, its officers, agents, and employees by the Department's acceptance of insurance policies and certificates.
- Minimum insurance coverage amounts do not relieve the Contractor for liability in excess of such coverage, nor do they preclude the State from taking other actions available to it, including the withholding of funds under this contract.

7-1.12B(9) Self-Insurance

- Self-insurance programs and self-insured retentions in insurance policies are subject to separate annual review and approval by the State.
- If the Contractor uses a self-insurance program or self-insured retention, the Contractor shall provide the State with the same protection from liability and defense of suits as would be afforded by first-dollar insurance. Execution of the contract is the Contractor's acknowledgement that the Contractor will be bound by all laws as if the Contractor were an insurer as defined under Insurance Code Section 23 and that the self-insurance program or self-insured retention shall operate as insurance as defined under Insurance Code Section 22.

SECTION 8: PROSECUTION AND PROGRESS

Issue Date: August 17, 2007

The 2nd paragraph of Section 8-1.02, "Assignment," of the Standard Specifications is amended to read:

- If the Contractor assigns the right to receive contract payments, the Department accepts the assignment upon the Engineer's receipt of a notice. Assigned payments remain subject to deductions and withholds described in the contract. The Department may use withheld payments for work completion whether payments are assigned or not.

SECTION 9: MEASUREMENT AND PAYMENT

Issue Date: August 17, 2007

The last sentence of the 1st paragraph of Section 9-1.02, "Scope of Payment," of the Standard Specifications is amended to read:

- Neither the payment of any estimate nor of any retained percentage or withhold relieves the Contractor of any obligation to make good any defective work or material.

The third paragraph of Section 9-1.03, "Work Performed by Contractor," of the Standard Specifications is amended to read:

- The above markups shall constitute full compensation for all delay costs, overhead costs and profit which shall be deemed to include all items of expense not specifically designated as cost or equipment rental in Sections 9-1.03A(1), "Labor," 9-1.03A(2), "Materials," and 9-1.03A(3), "Equipment Rental." The total payment made as provided above shall be deemed to be the actual cost of the work and shall constitute full compensation therefor.

The 6th paragraph of Section 9-1.03C, "Records," of the Standard Specifications is deleted.

Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications is amended to read:

9-1.04 NOTICE OF POTENTIAL CLAIM

- It is the intention of this section that disputes between the parties arising under and by virtue of the contract be brought to the attention of the Engineer at the earliest possible time in order that the matters may be resolved, if possible, or other appropriate action promptly taken.

- Disputes will not be considered unless the Contractor has first complied with specified notice or protest requirements, including Section 4-1.03, "Changes," Section 5-1.116, "Differing Site Conditions," Section 8-1.06, "Time of Completion," Section 8-1.07, "Liquidated Damages," and Section 8-1.10, "Utility and Non-Highway Facilities."

- For disputes arising under and by virtue of the contract, including an act or failure to act by the Engineer, the Contractor shall provide a signed written initial notice of potential claim to the Engineer within 5 days from the date the dispute first arose. The initial notice of potential claim shall provide the nature and circumstances involved in the dispute which shall remain consistent through the dispute. The initial notice of potential claim shall be submitted on Form CEM-6201A furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655. The Contractor shall assign an exclusive identification number for each dispute, determined by chronological sequencing, based on the date of the dispute.

- The exclusive identification number for each dispute shall be used on the following corresponding documents:

1. Initial notice of potential claim
2. Supplemental notice of potential claim
3. Full and final documentation of potential claim
4. Corresponding claim included in the Contractor's written statement of claims

- The Contractor shall provide the Engineer the opportunity to examine the site of work within 5 days from the date of the initial notice of potential claim. The Contractor shall proceed with the performance of contract work unless otherwise specified or directed by the Engineer.

- Throughout the disputed work, the Contractor shall maintain records that provide a clear distinction between the incurred direct costs of disputed work and that of undisputed work. The Contractor shall allow the Engineer access to the Contractor's project records deemed necessary by the Engineer to evaluate the potential claim within 20 days of the date of the Engineer's written request.

- Within 15 days of submitting the initial notice of potential claim, the Contractor shall provide a signed supplemental notice of potential claim to the Engineer that provides the following information:

1. The complete nature and circumstances of the dispute which caused the potential claim
2. The contract provisions that provide the basis of claim
3. The estimated cost of the potential claim, including an itemized breakdown of individual costs and how the estimate was determined
4. A time impact analysis of the project schedule that illustrates the effect on the scheduled completion date due to schedule changes or disruptions where a request for adjustment of contract time is made

- The information provided in items 1 and 2 above shall provide the Contractor's complete reasoning for additional compensation or adjustments.

- The supplemental notice of potential claim shall be submitted on Form CEM-6201B furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655. The Engineer will evaluate the information presented in the supplemental notice of potential claim and provide a written response to the Contractor within 20 days of its receipt. If the estimated cost or effect on the scheduled completion date changes, the Contractor shall update information in items 3 and 4 above as soon as the change is recognized and submit this information to the Engineer.

- Within 30 days of the completion of work related to the potential claim, the Contractor shall provide the full and final documentation of potential claim to the Engineer that provides the following information:

1. A detailed factual narration of events fully describing the nature and circumstances that caused the dispute, including, but not limited to, necessary dates, locations, and items of work affected by the dispute
2. The specific provisions of the contract that support the potential claim and a statement of the reasons these provisions support and provide a basis for entitlement of the potential claim
3. When additional monetary compensation is requested, the exact amount requested calculated in conformance with Section 9-1.03, "Force Account Payment," or Section 8-1.09, "Right of Way Delays," including an itemized breakdown of individual costs. These costs shall be segregated into the following cost categories:
 - 3.1. Labor – A listing of individuals, classifications, regular hours and overtime hours worked, dates worked, and other pertinent information related to the requested reimbursement of labor costs
 - 3.2. Materials – Invoices, purchase orders, location of materials either stored or incorporated into the work, dates materials were transported to the project or incorporated into the work, and other pertinent information related to the requested reimbursement of material costs

- 3.3. Equipment – Listing of detailed description (make, model, and serial number), hours of use, dates of use and equipment rates. Equipment rates shall be at the applicable State rental rate as listed in the Department of Transportation publication entitled "Labor Surcharge and Equipment Rental Rates," in effect when the affected work related to the dispute was performed.
 - 3.4. Other categories as specified by the Contractor or the Engineer
4. When an adjustment of contract time is requested the following information shall be provided:
 - 4.1. The specific dates for which contract time is being requested
 - 4.2. The specific reasons for entitlement to a contract time adjustment
 - 4.3. The specific provisions of the contract that provide the basis for the requested contract time adjustment
 - 4.4. A detailed time impact analysis of the project schedule. The time impact analysis shall show the effect of changes or disruptions on the scheduled completion date to demonstrate entitlement to a contract time adjustment.
 5. The identification and copies of the Contractor's documents and the substance of oral communications that support the potential claim
 - The full and final documentation of the potential claim shall be submitted on Form CEM-6201C furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655.
 - Pertinent information, references, arguments, and data to support the potential claim shall be included in the full and final documentation of potential claim. Information submitted subsequent to the full and final documentation submittal will not be considered. Information required in the full and final documentation of potential claim, as listed in items 1 to 5 above, that is not applicable to the dispute may be exempted as determined by the Engineer. No full and final documentation of potential claim will be considered that does not have the same nature and circumstances, and basis of claim as those specified on the initial and supplemental notices of potential claim.
 - The Engineer will evaluate the information presented in the full and final documentation of potential claim and provide a written response to the Contractor within 30 days of its receipt unless otherwise specified. The Engineer's receipt of the full and final documentation of potential claim shall be evidenced by postal receipt or the Engineer's written receipt if delivered by hand. If the full and final documentation of potential claim is submitted by the Contractor after acceptance of the work by the Director, the Engineer need not provide a written response.
 - Provisions in this section shall not apply to those claims for overhead costs and administrative disputes that occur after issuance of the proposed final estimate. Administrative disputes are disputes of administrative deductions or withholds, contract item quantities, contract item adjustments, interest payments, protests of contract change orders as provided in Section 4-1.03A, "Procedure and Protest," and protests of the Weekly Statement of Working Days as provided in Section 8-1.06, "Time of Completion." Administrative disputes that occur prior to issuance of the proposed final estimate shall follow applicable requirements of this section. Information listed in the supplemental notice and full and final documentation of potential claim that is not applicable to the administrative dispute may be exempted as determined by the Engineer.
 - Unless otherwise specified in the special provisions, the Contractor may pursue the administrative claim process pursuant to Section 9-1.07B, "Final Payment and Claims," for any potential claim found by the Engineer to be without merit.
 - Failure of the Contractor to conform to specified dispute procedures shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract, and is deemed as the Contractor's waiver of the potential claim and a waiver of the right to a corresponding claim for the disputed work in the administrative claim process in conformance with Section 9-1.07B, "Final Payment of Claims," and shall operate as a bar to arbitration pursuant to Section 10240.2 of the California Public Contract Code.

Section 9-1.05, "Stop Notices," of the Standard Specifications is amended to read:

9-1.05 STOP NOTICE WITHHOLDS

- The Department may withhold payments to cover claims filed under Civ Code § 3179 et seq.

Section 9, "Measurement and Payment," of the Standard Specifications is amended by adding the following sections:

Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications is amended to read:

9-1.053 PERFORMANCE FAILURE WITHHOLDS

- During each estimate period you fail to comply with a contract part, including submittal of a document as specified, the Department withholds a part of the progress payment. The documents include quality control plans, schedules, traffic control plans, and water pollution control submittals.
- For 1 performance failure, the Department withholds 25 percent of the progress payment but does not withhold more than 10 percent of the total bid.
- For multiple performance failures, the Department withholds 100 percent of the progress payment but does not withhold more than 10 percent of the total bid.
- The Department returns performance-failure withholds in the progress payment following the correction of noncompliance.

9-1.055 PENALTY WITHHOLDS

- Penalties include fines and damages that are proposed, assessed, or levied against you or the Department by a governmental agency or citizen lawsuit. Penalties are also payments made or costs incurred in settling alleged permit violations of Federal, State, or local laws, regulations, or requirements. The cost incurred may include the amount spent for mitigation or correcting a violation.
- If you or the Department is assessed a penalty, the Department may withhold the penalty amount until the penalty disposition has been resolved. The Department may withhold penalty funds and notify you within 15 days of the withhold. If the penalty amount is less than the amount being withheld from progress payments for retentions, the Department will not withhold the penalty amount.
- If the penalty is resolved for less than the amount withheld, the Department pays interest at a rate of 6 percent per year on the excess withhold. If the penalty is not resolved, the withhold becomes a deduction.
- Instead of the withhold, you may provide a bond payable to the Department of Transportation equal to the highest estimated liability for any disputed penalties proposed.

9-1.057 PROGRESS WITHHOLDS FOR FEDERAL-AID CONTRACTS

- Section 9-1.057, "Progress Withholds for Federal-Aid Contracts," applies to a Federal-aid contract.
- The Department withholds 10 percent of a partial payment for noncompliant progress. Noncompliant progress occurs when:
 1. Total days to date exceed 75 percent of the revised contract working days
 2. Percent of working days elapsed exceeds the percent of value of work completed by more than 15 percent
- The Engineer determines the percent of working days elapsed by dividing the total days to date by the revised contract working days and converting the quotient to a percentage.
- The Engineer determines the percent of value of work completed by summing payments made to date and the amount due on the current progress estimate, dividing this sum by the current total estimated value of the work, and converting the quotient to a percentage. These amounts are shown on the Progress Payment Voucher.
- When the percent of working days elapsed minus the percent of value of work completed is less than or equal to 15 percent, the Department returns the withhold in the next progress payment.

The 3rd paragraph of Section 9-1.06, "Partial Payments," of the Standard Specifications is amended to read:

- For a non-Federal-aid project, the Department retains 10 percent of the estimated value of the work done and 10 percent of the value of materials estimated to have been furnished and delivered and unused or furnished and stored as part security for the fulfillment of the contract by the Contractor, except that at any time after 20 percent of the work has been completed, if the Engineer finds that satisfactory progress is being made, the Department may reduce the total amount being retained from payment pursuant to the above requirements to 5 percent of the total estimated value of the work and materials and may also reduce the amount retained from any of the remaining partial payments to 5 percent of the estimated value of the work and materials. In addition, on any partial payment made after 95 percent of the work has been completed, the Department may reduce the amount retained from payment pursuant to the requirements of this Section 9-1.06, to such lesser amount as the Department determines is adequate security for the fulfillment of the balance of the work and other requirements of the contract, but in no event is that amount reduced to less than 125 percent of the estimated value of the work yet to be completed as determined by the Engineer. The reduction is made only upon the request of the Contractor and must be approved in writing by the surety on the performance bond and by the surety on the payment bond. The approval of the surety must be submitted to the Disbursing Officer of the Department; the signature of the person executing the approval for the surety must be properly acknowledged and the power of attorney authorizing the person to give that consent must

either accompany the document or be on file with the Department. The retentions specified in this paragraph are those defined in Pub Cont Code § 7107(b).

The 1st sentence of the 4th paragraph of Section 9-1.06, "Partial Payments," of the Standard Specifications is amended to read:

- The Department shall pay monthly to the Contractor, while carrying on the work, the balance not retained, as aforesaid, after deducting therefrom all previous payments and all sums to be deducted or withheld under the provisions of the contract.

The title and 1st and 2nd paragraphs of Section 9-1.065, "Payment of Withheld Funds," of the Standard Specifications are amended to read:

9-1.065 RELEASE OF RETAINED FUNDS

- The Department releases retained funds if you:
 1. Request release of the retention (Pub Cont Code § 10263) in writing
 2. Deposit securities equivalent to the funds you want released into escrow with the State Treasurer or with a bank acceptable to the Department
 3. Are the beneficial owner of and receive interest on the deposited securities substituted for the retained funds

The 2nd sentence Section 9-1.07A, "Payment Prior to Proposed Final Estimate," of the Standard Specifications is amended to read:

- The Department pays the balance due less previous payments, deductions, withholds, and retentions under the provisions of the contract and those further amounts that the Engineer determines to be necessary pending issuance of the proposed final estimate and payment thereon.

Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications is amended to read:

9-1.07B Final Payment and Claims

- After acceptance by the Director, the Engineer makes a proposed final estimate of the total amount payable to the Contractor, including an itemization of the total amount, segregated by contract item quantities, extra work, and other basis for payment, and shows each deduction made or to be made for prior payments and amounts to be deducted, withheld, or retained under the provisions of the contract. Prior estimates and payments are subject to correction in the proposed final estimate. The Contractor must submit written approval of the proposed final estimate or a written statement of claims arising under or by virtue of the contract so that the Engineer receives the written approval or statement of claims no later than close of business of the 30th day after receiving the proposed final estimate. The Contractor's receipt of the proposed final estimate must be evidenced by postal receipt. The Engineer's receipt of the Contractor's written approval or statement of claims must be evidenced by postal receipt or the Engineer's written receipt if delivered by hand.

- On the Contractor's approval, or if the Contractor files no claim within the specified period of 30 days, the Engineer will issue a final estimate in writing in conformance with the proposed final estimate submitted to the Contractor, and within 30 days thereafter the State will pay the entire sum so found to be due. That final estimate and payment thereon shall be conclusive and binding against both parties to the contract on all questions relating to the amount of work done and the compensation payable therefor, except as otherwise provided in Sections 9-1.03C, "Records," and 9-1.09, "Clerical Errors."

- If the Contractor within the specified period of 30 days files claims, the Engineer will issue a semifinal estimate in conformance with the proposed final estimate submitted to the Contractor and within 30 days thereafter the State will pay the sum found to be due. The semifinal estimate and corresponding payment shall be conclusive and binding against both parties to the contract on each question relating to the amount of work done and the compensation payable therefor, except insofar as affected by the claims filed within the time and in the manner required hereunder and except as otherwise provided in Sections 9-1.03C, "Records," and 9-1.09, "Clerical Errors."

- Except for claims for overhead costs and administrative disputes that occur after issuance of the proposed final estimate, the Contractor shall only provide the following two items of information for each claim:

1. The exclusive identification number that corresponds to the supporting full and final documentation of potential claim
2. The final amount of requested additional compensation

- If the final amount of requested additional compensation is different than the amount of requested compensation included in the full and final documentation of potential claim, the Contractor shall provide in the written statement of claims the reasons for the changed amount, the specific provisions of the contract which support the changed amount, and a statement of the reasons the provisions support and provide a basis for the changed amount. If the Contractor's claim fails to provide an exclusive identification number or if there is a disparity in the provided exclusive identification number, the Engineer will notify the Contractor of the omission or disparity. The Contractor shall have 15 days after receiving notification from the Engineer to correct the omission or disparity. If after the 15 days has elapsed, there is still an omission or disparity of the exclusive identification number assigned to the claim, the Engineer will assign the number. No claim will be considered that has any of the following deficiencies:

- The claim does not have the same nature, circumstances, and basis as the corresponding full and final documentation of potential claim.
- The claim does not have a corresponding full and final documentation of potential claim.
- The claim was not included in the written statement of claims.
- The Contractor did not comply with applicable notice or protest requirements of Sections 4-1.03, "Changes," 5-1.116, "Differing Site Condition," 8-1.06, "Time of Completion," 8-1.07, "Liquidated Damages," 8-1.10, "Utility and Non-Highway Facilities," and 9-1.04, "Notice of Potential Claim."

- Administrative disputes that occur after issuance of the proposed final estimate shall be included in the Contractor's written statement of claims in sufficient detail to enable the Engineer to ascertain the basis and amounts of those claims.

- The Contractor shall keep full and complete records of the costs and additional time incurred for work for which a claim for additional compensation is made. The Engineer or designated claim investigators or auditors shall have access to those records and any other records as may be required by the Engineer to determine the facts or contentions involved in the claims. Failure to permit access to those records shall be sufficient cause for denying the claims.

- The written statement of claims submitted by the Contractor shall be accompanied by a notarized certificate containing the following language:

Under the penalty of law for perjury or falsification and with specific reference to the California False Claims Act, Government Code Section 12650 et. seq., the undersigned,

(name) _____ of

(title) _____

(company)

hereby certifies that the claim for the additional compensation and time, if any, made herein for the work on this contract is a true statement of the actual costs incurred and time sought, and is fully documented and supported under the contract between parties.

Dated _____
 /s/ _____
 Subscribed and sworn before me this _____ day
 of _____

(Notary Public)
 My Commission
 Expires _____

- Failure to submit the notarized certificate will be sufficient cause for denying the claim.

• Any claim for overhead, in addition to being certified as stated above, shall be supported and accompanied by an audit report of an independent Certified Public Accountant. Omission of a supporting audit report of an independent Certified Public Accountant shall result in denial of the claim and shall operate as a bar to arbitration, as to the claim, in conformance with the requirements in Section 10240.2 of the California Public Contract Code. Any claim for overhead shall be subject to audit by the State at its discretion. The costs of performing an audit examination and submitting the report shall be borne by the Contractor. The Department will deduct an offset amount for field and home office overhead paid on all added work from any claim for overhead as appropriate, as determined by the Department. The value of the added work equals the value of the work completed minus the total bid. The home office overhead offset equals 5 percent of the added work. The field office overhead offset equals 5-1/2 percent of the added work. The Certified Public Accountant's audit examination shall be performed in conformance with the requirements of the American Institute of Certified Public Accountants Attestation Standards. The audit examination and report shall depict the Contractor's project and company-wide financial records and shall specify the actual overall average daily rates for both field and home office overhead for the entire duration of the project, and whether the costs have been properly allocated. The rates of field and home office overhead shall exclude unallowable costs as determined in Title 48 of the Federal Acquisition Regulations, Chapter 1, Part 31. The audit examination and report shall determine if the rates of field and home office overhead are:

1. Allowable in conformance with the requirements in Title 48 of the Federal Acquisition Regulations, Chapter 1, Part 31.
2. Adequately supported by reliable documentation.
3. Related solely to the project under examination.

• Costs or expenses incurred by the State in reviewing or auditing claims that are not supported by the Contractor's cost accounting or other records shall be deemed to be damages incurred by the State within the meaning of the California False Claims Act.

• If the Engineer determines that a claim requires additional analysis, the Engineer will schedule a board of review meeting. The Contractor shall meet with the review board or person and make a presentation in support of the claim. Attendance by the Contractor at the board of review meeting shall be mandatory.

• The District Director of the District that administered the contract will make the final determination of any claims which remain in dispute after completion of claim review by the Engineer or board of review meeting.

The final determination of claims will be sent to the Contractor by hand delivery or deposit in the U.S. mail. The Engineer will then make and issue the Engineer's final estimate in writing and within 30 days thereafter the State will pay the entire sum, if any, found due thereon. That final estimate shall be conclusive and binding against both parties to the contract on all questions relating to the amount of work done and the compensation payable therefor, except as otherwise provided in Sections 9-1.03C, "Records," and 9-1.09, "Clerical Errors."

• Failure of the Contractor to conform to the specified dispute procedures shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract and shall operate as a bar to arbitration in conformance with the requirements in Section 10240.2 of the California Public Contract Code.

SECTION 12: CONSTRUCTION AREA TRAFFIC CONTROL DEVICES

Issue Date: October 6, 2006

The second paragraph of Section 12-1.01, "Description," of the Standard Specifications is amended to read:

• Attention is directed to Part 6 of the California MUTCD. Nothing in this Section 12 is to be construed as to reduce the minimum standards in these manuals.

Section 12-2.01, "Flaggers," of the Standard Specifications is amended to read:

• Flaggers while on duty and assigned to traffic control or to give warning to the public that the highway is under construction and of any dangerous conditions to be encountered as a result thereof, shall perform their duties and shall be provided with the necessary equipment in conformance with Part 6 of the California MUTCD. The equipment shall be furnished and kept clean and in good repair by the Contractor at the Contractor's expense.

The first paragraph of Section 12-3.01, "General," of the Standard Specifications is amended to read:

• In addition to the requirements in Part 6 of the California MUTCD, all devices used by the Contractor in the performance of the work shall conform to the provisions in this Section 12-3.

The fifth paragraph of Section 12-3.01, "General," of the Standard Specifications is amended to read:

- Retroreflective sheeting shall conform to the requirements in ASTM Designation: D 4956 and to the special provisions.

The first paragraph of Section 12-3.06, "Construction Area Signs," of the Standard Specifications is amended to read:

- The term "Construction Area Signs" shall include all temporary signs required for the direction of public traffic through or around the work during construction. Construction area signs are shown in or referred to in Part 6 of the California MUTCD.

The fourth paragraph of Section 12-3.06, "Construction Area Signs," of the Standard Specifications is amended to read:

- All construction area signs shall conform to the dimensions, color and legend requirements of the plans, Part 6 of the California MUTCD and these specifications. All sign panels shall be the product of a commercial sign manufacturer, and shall be as specified in these specifications.

The eighth paragraph of Section 12-3.06, "Construction Area Signs," of the Standard Specifications is amended to read:

- Used signs with the specified sheeting material will be considered satisfactory if they conform to the requirements for visibility and legibility and the colors conform to the requirements in Part 6 of the California MUTCD. A significant difference between day and nighttime retroreflective color will be grounds for rejecting signs.

Section 12-3.06A, "Stationary Mounted Signs," of the Standard Specifications is amended by deleting the third, fourth, fifth, and sixth paragraphs.

SECTION 15: EXISTING HIGHWAY FACILITIES

Issue Date: November 2, 2004

The sixth paragraph of Section 15-2.07, "Payment," of the Standard Specifications is amended to read:

- Full compensation for removing, salvaging, reconstructing, relocating or resetting end caps, return caps, terminal sections, and buried post anchors, for metal beam guard railings and thrie beam barriers, and for connecting reconstructed, relocated or reset railings and barriers to new and existing facilities, including connections to concrete, shall be considered as included in the contract price paid per meter for the type of railing or barrier work involved and no additional compensation will be allowed therefor.

SECTION 19: EARTHWORK

Issue Date: January 5, 2007

The third paragraph of Section 19-1.02, "Preservation of Property," of the Standard Specifications is amended to read:

- In addition to the provisions in Sections 5-1.02, "Plans and Working Drawings," and 5-1.02A, "Excavation Safety Plans," detailed plans of the protective systems for excavations on or affecting railroad property will be reviewed for adequacy of protection provided for railroad facilities, property, and traffic. These plans shall be submitted at least 9 weeks before the Contractor intends to begin excavation requiring the protective systems. Approval by the Engineer of the detailed plans for the protective systems will be contingent upon the plans being satisfactory to the railroad company involved.

The first paragraph of Section 19-3.025C, "Soil Cement Bedding," of the Standard Specifications is amended to read:

- Cementitious material used in soil cement bedding shall conform to the provisions in Section 90-2.01, "Cementitious Materials." Supplementary cementitious material will not be required.

The fourth paragraph of Section 19-3.025C, "Soil Cement Bedding," of the Standard Specifications is amended to read:

- The aggregate, cementitious material, and water shall be proportioned either by mass or by volume. Soil cement bedding shall contain not less than 175 kg of cementitious material per cubic meter. The water content shall be sufficient to produce a fluid, workable mix that will flow and can be pumped without segregation of the aggregate while being placed.

The first paragraph of Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications is amended to read:

- Slurry cement backfill shall consist of a fluid, workable mixture of aggregate, cementitious material, and water.

The fifth paragraph of Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications is amended to read:

- Cementitious material shall conform to the provisions in Section 90-2.01, "Cementitious Materials." Supplementary cementitious material will not be required.

The eighth paragraph of Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications is amended to read:

- The aggregate, cementitious material, and water shall be proportioned either by mass or by volume. Slurry cement backfill shall contain not less than 110 kg of cementitious material per cubic meter. The water content shall be sufficient to produce a fluid, workable mix that will flow and can be pumped without segregation of the aggregate while being placed.

SECTION 20: EROSION CONTROL AND HIGHWAY PLANTING

Issue Date: August 17, 2007

Section 20-2.03, "Soil Amendment," of the Standard Specifications is amended to read:

20-2.03 SOIL AMENDMENT

- Soil amendment shall comply with the requirements in the California Food and Agricultural Code.
- Soil amendment producers shall comply with the following:
 1. Be fully permitted to produce compost as specified under the California Integrated Waste Management Board, Local Enforcement Agencies and any other State and Local Agencies that regulate Solid Waste Facilities. If exempt from State permitting requirements, the composting facility must certify that it follows guidelines and procedures for production of compost meeting the environmental health standards of Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7.
 2. Be a participant in United States Composting Council's Seal of Testing Assurance program.
- Soil amendment shall be composted and may be derived from any single, or mixture of any of the following feedstock materials:
 1. Green material consisting of chipped, shredded, or ground vegetation; or clean processed recycled wood products
 2. Biosolids
 3. Manure
 4. Mixed food waste
- Soil amendment feedstock materials shall be composted to reduce weed seeds, pathogens and deleterious materials as specified under Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7, Section 17868.3.
 - Soil amendment shall not be derived from mixed municipal solid waste and must be reasonably free of visible contaminants. Soil amendment must not contain paint, petroleum products, pesticides or any other chemical residues harmful to animal life or plant growth. Soil amendment must not possess objectionable odors.
 - Metal concentrations in soil amendment must not exceed the maximum metal concentrations listed in Title 14, California Code of Regulations, Division 7, Chapter 3.1, Section 17868.2.
 - Soil amendment must comply with the following:

Physical/Chemical Requirements

Property	Test Method	Requirement
pH	*TMECC 04.11-A, Elastometric pH 1:5 Slurry Method, pH Units	6.0–8.0
Soluble Salts	TMECC 04.10-A, Electrical Conductivity 1:5 Slurry Method dS/m (mmhos/cm)	0-10.0
Moisture Content	TMECC 03.09-A, Total Solids & Moisture at 70+/- 5 deg C, % Wet Weight Basis	30–60
Organic Matter Content	TMECC 05.07-A, Loss-On-Ignition Organic Matter Method (LOI), % Dry Weight Basis	30–65
Maturity	TMECC 05.05-A, Germination and Vigor Seed Emergence Seedling Vigor % Relative to Positive Control	80 or Above 80 or Above
Stability	TMECC 05.08-B, Carbon Dioxide Evolution Rate mg CO ₂ -C/g OM per day	8 or below
Particle Size	TMECC 02.02-B Sample Sieving for Aggregate Size Classification % Dry Weight Basis	95% Passing 5/8 inch 70% Passing 3/8 inch
Pathogen	TMECC 07.01-B, Fecal Coliform Bacteria < 1000 MPN/gram dry wt.	Pass
Pathogen	TMECC 07.01-B, Salmonella < 3 MPN/4 grams dry wt.	Pass
Physical Contaminants	TMECC 02.02-C, Man Made Inert Removal and Classification: Plastic, Glass and Metal, % > 4mm fraction	Combined Total: < 1.0
Physical Contaminants	TMECC 02.02-C, Man Made Inert Removal and Classification: Sharps (Sewing needles, straight pins and hypodermic needles), % > 4mm fraction	None Detected

*TMECC refers to "Test Methods for the Examination of Composting and Compost," published by the United States Department of Agriculture and the United States Compost Council (USCC).

- Prior to application, the Contractor shall provide the Engineer with a copy of the soil amendment producer's Compost Technical Data Sheet and a copy of the compost producers STA certification. The Compost Technical Data Sheet shall include laboratory analytical test results, directions for product use, and a list of product ingredients.
- Prior to application, the Contractor shall provide the Engineer with a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

The last 3 paragraphs of Section 20-2.10, "Seed," of the Standard Specifications are deleted.

Section 20-2.25, "Backflow Preventers," of the Standard Specifications is amended to read:

20-2.25 BACKFLOW PREVENTERS

- Backflow preventers shall be one of the reduced pressure principle devices as specified in these specifications and the special provisions.
- Backflow preventers shall be factory assembled and shall include 2 check valves, one pressure differential relief valve, 2 shut-off valves and 4 test cocks. Backflow preventer and valves shall be the same size as the pipeline in which they are installed, unless otherwise shown on the plans.
- Backflow preventer shut-off valves shall be manufactured from iron or bronze and shall be either resilient wedged gate valves, resilient seated and fully ported ball valves, or resilient seated butterfly valves. Threaded type shut-off valves shall be provided with a union on one side of each valve. Unions shall be brass or malleable iron.

The last paragraph of Section 20-3.04A, "General," of the Standard Specifications is deleted.

Section 20-4.055, "Pruning," of the Standard Specifications is amended to read:

20-4.055 PRUNING

- Pruning of plants shall be consistent with American National Standards Institute (ANSI), "Tree, Shrub and Other Woody Plant Maintenance Standard Practices," ANSI 300 (Part 1)-2001 and "Best Management Practices Tree Pruning," 2002 (ISBN 1-881956318), published by the International Society of Arboriculture, P.O. Boc 3129, Champaign, IL 61826.

Section 20-5.03J, "Check and Test Backflow Preventers," of the Standard Specifications is amended to read:

20-5.03J Check and Test Backflow Preventers

- Backflow preventers shall be checked and tested for proper operation by a certified Backflow Preventer Tester. The tester shall hold a valid certification as a Backflow Preventer Tester from the local governing authority in which the device to be tested is located. The local governing authority shall be the county, city or water purveyor having the governing authority over testing of backflow preventers involved. If the local governing authority does not have a certification program for Backflow Preventer Testers, the tester shall have a certificate from one of the following:

- A. The American Water Works Association.
- B. A county which has a certification program for Backflow Preventer Testers.

- Tests for proper operation shall conform to the requirements of the governing authority.
- The Engineer shall be notified at least 5 days prior to testing backflow preventers.
- One copy of the test results for each backflow preventer tested shall be furnished to the Engineer.
- Backflow preventers, installed by the Contractor, failing required tests shall be repaired at the Contractor's expense.

SECTION 25: AGGREGATE SUBBASES

Issue Date: February 16, 2007

The first paragraph of Section 25-1.02A, "Class 1, Class 2, and Class 3 Aggregate Subbases," of the Standard Specifications is amended to read:

- Aggregate must be clean and free from organic matter and other deleterious substances. Aggregate must consist of any combination of:

- 1. Broken stone
- 2. Crushed gravel
- 3. Natural rough surfaced gravel
- 4. Sand
- 5. Up to 100 percent of any combination of processed:
 - 5.1. Asphalt concrete
 - 5.2. Portland cement concrete
 - 5.3. Lean concrete base
 - 5.4. Cement treated base

The first paragraph of Section 25-1.02B, "Class 4 Aggregate Subbase," of the Standard Specifications is amended to read:

- Aggregate must be clean and free from organic matter and other deleterious substances. Aggregate must consist of any combination of:

- 1. Broken stone
- 2. Crushed gravel
- 3. Natural rough surfaced gravel
- 4. Sand
- 5. Up to 100 percent of any combination of processed:
 - 5.1. Asphalt concrete
 - 5.2. Portland cement concrete
 - 5.3. Lean concrete base

5.4. Cement treated base

SECTION 26: AGGREGATE BASE

Issue Date: February 16, 2007

The first paragraph of Section 26-1.02A, "Class 2 Aggregate Base," of the Standard Specifications is amended to read:

- Aggregate must be clean and free from organic matter and other deleterious substances. Aggregate must consist of any combination of:
 1. Broken stone
 2. Crushed gravel
 3. Natural rough surfaced gravel
 4. Sand
 5. Up to 100 percent of any combination of processed:
 - 5.1. Asphalt concrete
 - 5.2. Portland cement concrete
 - 5.3. Lean concrete base
 - 5.4. Cement treated base

The first paragraph of Section 26-1.02B, "Class 3 Aggregate Base," of the Standard Specifications is amended to read:

- Aggregate must be clean and free from organic matter and other deleterious substances. Aggregate must consist of any combination of:
 1. Broken stone
 2. Crushed gravel
 3. Natural rough surfaced gravel
 4. Sand
 5. Up to 100 percent of any combination of processed:
 - 5.1. Asphalt concrete
 - 5.2. Portland cement concrete
 - 5.3. Lean concrete base
 - 5.4. Cement treated base

SECTION 27: CEMENT TREATED BASES

Issue Date: January 5, 2007

The first paragraph of Section 27-1.02, "Materials," of the Standard Specifications is amended to read:

- Cement shall be Type II portland cement conforming to the provisions in Section 90-2.01A, "Cement."

The third paragraph of Section 27-1.02, "Materials," of the Standard Specifications is amended to read:

- Aggregate for use in Class A cement treated base shall be of such quality that when mixed with cement in an amount not to exceed 5 percent by mass of the dry aggregate and compacted at optimum moisture content, the compressive strength of a sample of the compacted mixture shall not be less than 5.2 MPa at 7 days, when tested by California Test 312.

The fourth paragraph of Section 27-1.02, "Materials," of the Standard Specifications is amended to read:

- Aggregate for use in Class B cement treated base shall have a Resistance (R-value) of not less than 60 before mixing with cement and a Resistance (R-value) of not less than 80 after mixing with cement in an amount not to exceed 2.5 percent by mass of the dry aggregate.

SECTION 28: LEAN CONCRETE BASE

Issue Date: January 5, 2007

The first paragraph of Section 28-1.02, "Materials," of the Standard Specifications is amended to read:

- Cement shall be Type II portland cement conforming to the provisions in Section 90-2.01A, "Cement."

The sixth paragraph of Section 28-1.02, "Materials," of the Standard Specifications is amended to read:

- Aggregate shall be of such quality that, when mixed with cement in an amount not to exceed 180 kg per cubic meter, and tested in conformance with the requirements in California Test 548, the compressive strength of a sample will be not less than 5.0 MPa at 7 days.

SECTION 29: TREATED PERMEABLE BASES

Issue Date: January 5, 2007

The fourth paragraph of Section 29-1.02A, "Asphalt Treated Permeable Base," of the Standard Specifications is amended to read:

- The type and grade of asphalt binder to be mixed with aggregate will be specified in the special provisions.

The second paragraph of Section 29-1.02B, "Cement Treated Permeable Base," of the Standard Specifications is amended to read:

- Cement shall be Type II portland cement conforming to the provisions in Section 90-2.01A, "Cement."

The second paragraph of Section 29-1.04B, "Cement Treated Permeable Base," of the Standard Specifications is amended to read:

- Cement treated permeable base shall contain not less than 170 kg of cement per cubic meter.

SECTION 37: BITUMINOUS SEALS

Issue Date: August 17, 2007

The fourth through sixth paragraphs in Section 37-1.03, "Maintaining Traffic," of the Standard Specifications are amended to read:

- On 2-lane two-way roadways, W8-7 "LOOSE GRAVEL" signs and W13-1 (35) speed advisory signs shall be furnished and placed adjacent to both sides of the traveled way where screenings are being spread on a traffic lane. The first W8-7 sign in each direction shall be placed where traffic first encounters loose screenings, regardless of which lane the screenings are being spread on. The W13-1 (35) signs need not be placed in those areas with posted speed limits of less than 40 MPH. The signs shall be placed at maximum 600-m intervals along each side of the traveled way and at public roads or streets entering the seal coat area as directed by the Engineer.

- On multilane roadways (freeways, expressways and multilane conventional highways) where screenings are being spread on a traffic lane, W8-7 "LOOSE GRAVEL" signs and W13-1 (35) speed advisory signs shall be furnished and placed adjacent to the outside edge of the traveled way nearest to the lane being worked on. The first W8-7 sign shall be placed where the screenings begin with respect to the direction of travel on that lane. The W13-1 (35) signs need not be placed in those areas with posted speed limits of less than 40 MPH. The signs shall be placed at maximum 600-m intervals along the edge of traveled way and at on-ramps, public roads or streets entering the seal coat area as directed by the Engineer.

- The W8-7 and W13-1 signs shall be maintained in place at each location until final brooming of the seal coat surface at that location is completed. The W8-7 and W13-1 signs shall conform to the provisions for construction area signs in Section 12, "Construction Area Traffic Control Devices." The signs may be set on temporary portable supports with the W13-1 below the W8-7 or on barricades with the W13-1 sign alternating with the W8-7 sign.

The second paragraph in Section 37-1.09, "Payment," of the Standard Specifications is amended to read:

Contract No. 02-350904

- The above prices and payments shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in applying seal coat, complete in place, including furnishing, placing, maintaining, and removing W8-7 and W13-1 signs, when required, and temporary supports or barricades for the signs, as shown on the plans, and as specified in these specifications and the special provisions, and as directed by the Engineer.

SECTION 39: ASPHALT CONCRETE

Issue Date: November 18, 2005

The fifth paragraph of Section 39-2.01, "Asphalts," of the Standard Specifications is amended to read:

- Paving asphalt to be used as a binder for pavement reinforcing fabric shall be a steam-refined paving asphalt conforming to the provisions in Section 92, "Asphalts," and shall be Grade PG 70-10.

SECTION 40: PORTLAND CEMENT CONCRETE PAVEMENT

Issue Date: January 5, 2007

Section 40-1.015, "Cement Content," is deleted.

Section 40-1.05, "Proportioning," of the Standard Specifications is amended to read:

- Aggregate and cementitious material proportioning shall conform to the provisions in Section 90-5, "Proportioning."

The first paragraph in Section 40-1.105, "Exit Ramp Termini," of the Standard Specifications is amended to read:

- Concrete pavement shall be constructed at the ends of exit ramps when required by the plans or the special provisions. Texturing for exit ramp termini shall be by means of heavy brooming in a direction normal to ramp centerline. The hardened surface shall have a coefficient of friction not less than 0.35 as determined by California Test 342. Minimum cementitious material content of concrete in pavement for exit ramp termini shall be 350 kg/m³.

The fourth paragraph of Section 40-1.08, "Joints," of the Standard Specifications is amended to read:

- Straight tie bars shall be deformed reinforcing steel bars conforming to the requirements in ASTM Designation: A 615/A 615M, Grade 280 or 420; ASTM Designation: A 996/A 996M, Grade 350 or 420; or ASTM Designation: A 706/A 706M.

The first paragraph in Section 40-1.14, "Payment," of the Standard Specifications is amended to read:

- The contract price paid per cubic meter for concrete pavement shall include full compensation for furnishing all labor, materials (including cementitious material in the amount specified), tools, equipment, and incidentals, and for doing all the work involved in constructing the portland cement concrete pavement, complete in place, as shown on the plans, and as specified in these specifications and the special provisions, and as directed by the Engineer.

SECTION 41: PAVEMENT SUBSEALING AND JACKING

Issue Date: January 5, 2007

The second paragraph of Section 41-1.02, "Materials," of the Standard Specifications is amended to read:

- Cement for grout shall be Type II portland cement conforming to the provisions in Section 90-2.01A, "Cement."

The third paragraph of Section 41-1.02, "Materials," of the Standard Specifications is amended to read:

- Fly ash shall conform to the requirements in AASHTO Designation: M 295 for either Class C or for Class F. The brand of fly ash used in the work shall conform to the provisions for approval of admixture brands in Section 90-4.03, "Admixture Approval."

The fifth paragraph of Section 41-1.02, "Materials," of the Standard Specifications is amended to read:

- Chemical admixtures and calcium chloride may be used. Chemical admixtures in the grout mix shall conform to the provisions in Section 90-4, "Admixtures." Calcium chloride shall conform to ASTM Designation: D 98.

SECTION 42: GROOVE AND GRIND PAVEMENT

Issue Date: December 31, 2001

The last sentence of the first subparagraph of the third paragraph in Section 42-2.02, "Construction," of the Standard Specifications is amended to read:

- After grinding has been completed, the pavement shall conform to the straightedge and profile requirements specified in Section 40-1.10, "Final Finishing."

SECTION 49: PILING

Issue Date: January 5, 2007

The first paragraph in Section 49-1.03, "Determination of Length," of the Standard Specifications is amended to read:

- Foundation piles of any material shall be of such length as is required to obtain the specified penetration, and to extend into the cap or footing block as shown on the plans, or specified in the special provisions.

The fourth paragraph in Section 49-1.03, "Determination of Length," of the Standard Specifications is amended to read:

- Modification to the specified installation methods and specified pile tip elevation will not be considered at locations where tension or lateral load demands control design pile tip elevations or when the plans state that specified pile tip elevation shall not be revised.

The sixth and seventh paragraphs in Section 49-1.03, "Determination of Length," of the Standard Specifications are amended to read:

- Indicator compression pile load testing shall conform to the requirements in ASTM Designation: D 1143-81. The pile shall sustain the first compression test load applied which is equal to the nominal resistance in compression, as shown on the plans, with no more than 13 mm total vertical movement at the top of the pile measured relative to the top of the pile prior to the start of compression load testing.
- Indicator tension pile load testing shall conform to the requirements in ASTM Designation: D 3689-90. The loading apparatus described as "Load Applied to Pile by Hydraulic Jack(s) Acting at One End of Test Beam(s) Anchored to the Pile" shall not be used. The pile shall sustain the first tension test load applied which is equal to the nominal resistance in tension, as shown on the plans, with no more than 13 mm total vertical movement at the top of the pile measured relative to the top of the pile prior to the start of tension load testing.

The ninth paragraph in Section 49-1.03, "Determination of Length," of the Standard Specifications is amended to read:

- For driven piling, the Contractor shall furnish piling of sufficient length to obtain the specified tip elevation shown on the plans or specified in the special provisions. For cast-in-drilled-hole concrete piling, the Contractor shall construct piling of such length to develop the nominal resistance in compression and to obtain the specified tip elevation shown on the plans or specified in the special provisions.

The tenth paragraph in Section 49-1.03, "Determination of Length," of the Standard Specifications is deleted.

The fourth paragraph in Section 49-1.04, "Load Test Piles," of the Standard Specifications is amended to read:

- Load test piles and anchor piles which are not to be incorporated in the completed structure shall be removed in conformance with the provisions in Section 15-4.02, "Removal Methods," and the remaining holes shall be backfilled with earth or other suitable material approved by the Engineer.

The fifth paragraph in Section 49-1.04, "Load Test Piles," of the Standard Specifications is amended to read:

- Load test anchorages in piles used as anchor piles shall conform to the following requirements:
 - A. High strength threaded steel rods shall conform to the provisions for bars in Section 50-1.05, "Prestressing Steel," except Type II bars shall be used.
 - B. High strength steel plates shall conform to the requirements in ASTM Designation: A 709/A 709M, Grade 345.
 - C. Anchor nuts shall conform to the provisions in the second paragraph in Section 50-1.06, "Anchorages and Distribution."

The sixth paragraph in Section 49-1.04, "Load Test Piles," of the Standard Specifications is amended to read:

- The Contractor may use additional cementitious material in the concrete for the load test and anchor piles.

The first paragraph in Section 49-1.05, "Driving Equipment," of the Standard Specifications is amended to read:

- Driven piles shall be installed with impact hammers that are approved in writing by the Engineer. Impact hammers shall be steam, hydraulic, air or diesel hammers. Impact hammers shall develop sufficient energy to drive the piles at a penetration rate of not less than 3 mm per blow at the specified nominal resistance.

The seventh paragraph in Section 49-1.05, "Driving Equipment," of the Standard Specifications is amended to read:

- When necessary to obtain the specified penetration and when authorized by the Engineer, the Contractor may supply and operate one or more water jets and pumps, or furnish the necessary drilling apparatus and drill holes not greater than the least dimension of the pile to the proper depth and drive the piles therein. Jets shall not be used at locations where the stability of embankments or other improvements would be endangered. In addition, for steel piles, steel shells, or steel casings, when necessary to obtain the specified penetration or to prevent damage to the pile during installation, the Contractor shall provide special driving tips or heavier pile sections or take other measures as approved by the Engineer.
- The use of followers or underwater hammers for driving piles will be permitted if authorized in writing by the Engineer. When a follower or underwater hammer is used, its efficiency shall be verified by furnishing the first pile in each bent or footing sufficiently long and driving the pile without the use of a follower or underwater hammer.

The second paragraph in Section 49-1.07, "Driving," of the Standard Specifications is amended to read:

- Timber piles shall be fresh-headed and square and when permitted by the Engineer, the heads of the piles may be protected by means of heavy steel or wrought iron rings. During driving operations timber piling shall be restrained from lateral movement at intervals not to exceed 6 m over the length between the driving head and the ground surface. During driving operations, the timber pile shall be kept moving by continuous operation of the hammer. When the blow count exceeds either 2 times the blow count required in 300 mm, or 3 times the blow count required in 75 mm for the nominal resistance as shown on the plans, computed in conformance with the provisions in Section 49-1.08, "Pile Driving Acceptance Criteria," additional aids shall be used to obtain the specified penetration. These aids may include the use of water jets or drilling, where permitted, or the use of a larger hammer employing a heavy ram striking with a low velocity.

Section 49-1.08, "Bearing Value and Penetration," of the Standard Specifications is amended to read:

49-1.08 PILE DRIVING ACCEPTANCE CRITERIA

- Except for piles to be load tested, driven piles shall be driven to a value of not less than the nominal resistance shown on the plans unless otherwise specified in the special provisions or permitted in writing by the Engineer. In addition, when a pile tip elevation is specified, driven piles shall penetrate at least to the specified tip elevation, unless otherwise permitted in writing by the Engineer. Piles to be load tested shall be driven to the specified tip elevation.
 - When the pile nominal resistance is omitted from the plans or the special provisions, timber piles shall be driven to a nominal resistance of 800 kN, and steel and concrete piles shall be driven to a nominal resistance of 1250 kN.
 - The nominal resistance for driven piles shall be determined from the following formula in which " R_u " is the nominal resistance in kilonewtons, " E_r " is the manufacturer's rating for joules of energy developed by the hammer at the observed field drop height, and "N" is the number of hammer blows in the last 300 millimeters. (maximum value to be used for N is 100):

$$R_u = (7 * (E_r)^{1/2} * \log_{10} (0.83 * N)) - 550$$

The first paragraph in Section 49-2.03, "Requirements," of the Standard Specifications is amended to read:

- When preservative treatment of timber piles is required by the plans or specified in the special provisions, the treatment shall conform to the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," and the applicable AWWA Use Category.

The first paragraph in Section 49-2.04, "Treatment of Pile Heads," of the Standard Specifications is amended to read:

- A. An application of wood preservative conforming to the provisions in Section 58-1.04, "Wood Preservative for Manual Treatment," shall first be applied to the head of the pile and a protective cap shall then be built up by applying alternate layers of loosely woven fabric and hot asphalt or tar similar to membrane waterproofing, using 3 layers of asphalt or tar and 2 layers of fabric. The fabric shall measure at least 150 mm more in each direction than the diameter of the pile and shall be turned down over the pile and the edges secured by binding with 2 turns of No. 10 galvanized wire. The fabric shall be wired in advance of the application of the final layer of asphalt or tar, which shall extend down over the wiring.
- B. The sawed surface shall be covered with 3 applications of a hot mixture of 60 percent creosote and 40 percent roofing pitch, or thoroughly brushcoated with 3 applications of hot creosote and covered with hot roofing pitch. A covering of 3.50-mm nominal thickness galvanized steel sheet shall be placed over the coating and bent down over the sides of each pile to shed water.

Section 49-3.01, "Description," of the Standard Specifications is amended by deleting the fifth paragraph.

The sixth and seventh paragraphs in Section 49-3.01, "Description," of the Standard Specifications are amended to read:

- Except for precast prestressed concrete piles in a corrosive environment, lifting anchors used in precast prestressed concrete piles shall be removed, and the holes filled in conformance with the provisions in Section 51-1.18A, "Ordinary Surface Finish."
 - Lifting anchors used in precast prestressed concrete piles in a corrosive environment shall be removed to a depth of at least 25 mm below the surface of the concrete, and the resulting hole shall be filled with epoxy adhesive before the piles are delivered to the job site. The epoxy adhesive shall conform to the provisions in Sections 95-1, "General," and 95-2.01, "Binder (Adhesive), Epoxy Resin Base (State Specification 8040-03)."

The first and second paragraphs in Section 49-4.01, "Description," of the Standard Specifications are amended to read:

- Cast-in-place concrete piles shall consist of one of the following:
 - A. Steel shells driven permanently to the required nominal resistance and penetration and filled with concrete.
 - B. Steel casings installed permanently to the required penetration and filled with concrete.
 - C. Drilled holes filled with concrete.
 - D. Rock sockets filled with concrete.
- The drilling of holes shall conform to the provisions in these specifications. Concrete filling for cast-in-place concrete piles is designated by compressive strength and shall have a minimum 28-day compressive strength of 25 MPa. At the option of the Contractor, the combined aggregate grading for the concrete shall be either the 25-mm maximum grading, the 12.5-mm maximum grading, or the 9.5-mm maximum grading. Concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," and Section 51, "Concrete Structures." Reinforcement shall conform to the provisions in Section 52, "Reinforcement."

The fourth paragraph in Section 49-4.03, "Drilled Holes," of the Standard Specifications is amended to read:

- After placing reinforcement and prior to placing concrete in the drilled hole, if caving occurs or deteriorated foundation material accumulates on the bottom of the hole, the bottom of the drilled hole shall be cleaned. The Contractor shall verify that the bottom of the drilled hole is clean.

The first and second paragraphs in Section 49-4.04, "Steel Shells," of the Standard Specifications are amended to read:

- Steel shells shall be sufficiently watertight to exclude water during the placing of concrete. The shells may be cylindrical or tapered, step-tapered, or a combination of either, with cylindrical sections.

The first paragraph in Section 49-4.05, "Inspection," of the Standard Specifications is amended to read:

- After being driven and prior to placing reinforcement and concrete therein, the steel shells shall be examined for collapse or reduced diameter at any point. Any shell which is improperly driven or broken or shows partial collapse to such an extent as to materially decrease its nominal resistance will be rejected. Rejected shells shall be removed and replaced, or a new shell shall be driven adjacent to the rejected shell. Rejected shells which cannot be removed shall be filled with concrete by the Contractor at the Contractor's expense. When a new shell is driven to replace a rejected shell, the Contractor, at the Contractor's expense, shall enlarge the footing as determined necessary by the Engineer.

The third paragraph in Section 49-5.01, "Description," of the Standard Specifications is amended to read:

- Steel pipe piles shall conform to the following requirements:
 1. Steel pipe piles less than 360 mm in diameter shall conform to the requirements in ASTM Designation: A 252, Grade 2 or 3.
 2. Steel pipe piles 360 mm and greater in diameter shall conform to the requirements in ASTM Designation: A 252, Grade 3.
 3. Steel pipe piles shall be of the nominal diameter and nominal wall thickness shown on the plans or specified in the special provisions.
 4. The carbon equivalency (CE) of steel for steel pipe piles, as defined in AWS D 1.1, Section XI5.1, shall not exceed 0.45.
 5. The sulfur content of steel for steel pipe piles shall not exceed 0.05-percent.
 6. Seams in steel pipe piles shall be complete penetration welds.

The first paragraph in Section 49-6.01, "Measurement," of the Standard Specifications is amended to read:

- The length of timber, steel, and precast prestressed concrete piles, and of cast-in-place concrete piles consisting of driven shells filled with concrete, shall be the greater of the following:
 - A. The total length in place in the completed work, measured along the longest side, from the tip of the pile to the plane of pile cut-off.
 - B. The length measured along the longest side, from the tip elevation shown on the plans or the tip elevation ordered by the Engineer, to the plane of pile cut-off.

The third paragraph in Section 49-6.02, "Payment," of the Standard Specifications is amended to read:

- The contract price paid per meter for cast-in-drilled-hole concrete piling shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in drilling holes, disposing of material resulting from drilling holes, temporarily casing holes and removing water when necessary, furnishing and placing concrete and reinforcement, and constructing reinforced concrete extensions, complete in place, to the required penetration, as shown on the plans, as specified in these specifications and in the special provisions, and as directed by the Engineer.

The seventh paragraph in Section 49-6.02, "Payment," of the Standard Specifications is amended to read:

- The contract unit price paid for drive pile shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in driving timber, concrete and steel piles, driving steel shells for cast-in-place concrete piles, placing filling materials for cast-in-place concrete piles and cutting off piles, all complete in place to the required nominal resistance and penetration as shown on the plans and as specified in these specifications and the special provisions, and as directed by the Engineer.

The ninth paragraph in Section 49-6.02, "Payment," of the Standard Specifications is amended to read:

- Full compensation for all jetting, drilling, providing special driving tips or heavier sections for steel piles or shells, or other work necessary to obtain the specified penetration and nominal resistance of the piles, for predrilling holes through embankment and filling the space remaining around the pile with sand or pea gravel, for disposing of material resulting from jetting, drilling or predrilling holes, and for all excavation and backfill involved in constructing concrete extensions as shown on the plans, and as specified in these specifications and the special provisions, and as directed by the Engineer shall be considered as included in the contract unit price paid for drive pile or in the contract price paid per meter for cast-in-drilled-hole concrete piling, and no additional compensation will be allowed therefor.

Section 49-6.02, "Payment," of the Standard Specifications is amended by adding the following paragraphs:

- Full compensation for furnishing and placing additional testing reinforcement, for load test anchorages, and for cutting off test piles, shall be considered as included in the contract price paid for piling of the type or class shown in the Engineer's Estimate, and no additional compensation will be allowed.

- No additional compensation or extension of time will be made for additional foundation investigation, installation and testing of indicator piling, cutting off piling and restoring the foundation investigation and indicator pile sites, and review of request by the Engineer.

SECTION 50: PRESTRESSING CONCRETE

Issue Date: January 5, 2007

Section 50-1.02, "Drawings," of the Standard Specifications is amended by adding the following paragraph after the second paragraph:

- Each working drawing submittal shall consist of plans for a single bridge or portion thereof. For multi-frame bridges, each frame shall require a separate working drawing submittal.

The eighth paragraph of Section 50-1.02, "Drawings," of the Standard Specifications is deleted.

Section 50-1.05, "Prestressing Steel," of the Standard Specifications is amended to read:

- Prestressing steel shall be high-tensile wire conforming to the requirements in ASTM Designation: A 421, including Supplement I; high-tensile seven-wire strand conforming to the requirements in ASTM Designation: A 416; or uncoated high-strength steel bars conforming to the requirements in ASTM Designation: A 722, including all supplementary requirements. The maximum mass requirement of ASTM Designation: A 722 will not apply.

- In addition to the requirements of ASTM Designation: A 722, for deformed bars, the reduction of area shall be determined from a bar from which the deformations have been removed. The bar shall be machined no more than necessary to remove the deformations over a length of 300 mm, and reduction will be based on the area of the machined portion.

- In addition to the requirements specified herein, epoxy-coated seven-wire prestressing steel strand shall be grit impregnated and filled in conformance with the requirements in ASTM Designation: A 882/A 882M, including Supplement I, and the following:

- A. The coating material shall be on the Department's list of approved coating materials for epoxy-coated strand, available from the Transportation Laboratory.
- B. The film thickness of the coating after curing shall be 381 μm to 1143 μm .
- C. Prior to coating the strand, the Contractor shall furnish to the Transportation Laboratory a representative 230-g sample from each batch of epoxy coating material to be used. Each sample shall be packaged in an airtight container identified with the manufacturer's name and batch number.
- D. Prior to use of the epoxy-coated strand in the work, written certifications referenced in ASTM Designation: A 882/A 882M, including a representative load-elongation curve for each size and grade of strand to be used and a copy of the quality control tests performed by the manufacturer, shall be furnished to the Engineer.
- E. In addition to the requirements in Section 50-1.10, "Samples for Testing," four 1.5-m long samples of coated strand and one 1.5-m long sample of uncoated strand of each size and reel shall be furnished to the Engineer for testing. These samples, as selected by the Engineer, shall be representative of the material to be used in the work.
- F. Epoxy-coated strand shall be cut using an abrasive saw.

G. All visible damage to coatings caused by shipping and handling, or during installation, including cut ends, shall be repaired in conformance with the requirements in ASTM Designation: A 882/A 882M. The patching material shall be furnished by the manufacturer of the epoxy powder and shall be applied in conformance with the manufacturer's written recommendations. The patching material shall be compatible with the original epoxy coating material and shall be inert in concrete.

- All bars in any individual member shall be of the same grade, unless otherwise permitted by the Engineer.
- When bars are to be extended by the use of couplers, the assembled units shall have a tensile strength of not less than the manufacturer's minimum guaranteed ultimate tensile strength of the bars. Failure of any one sample to meet this requirement will be cause for rejection of the heat of bars and lot of couplers. The location of couplers in the member shall be subject to approval by the Engineer.
 - Wires shall be straightened if necessary to produce equal stress in all wires or wire groups or parallel lay cables that are to be stressed simultaneously or when necessary to ensure proper positioning in the ducts.
 - Where wires are to be button-headed, the buttons shall be cold formed symmetrically about the axes of the wires. The buttons shall develop the minimum guaranteed ultimate tensile strength of the wire. No cold forming process shall be used that causes indentations in the wire. Buttonheads shall not contain wide open splits, more than 2 splits per head, or splits not parallel with the axis of the wire.
 - Prestressing steel shall be protected against physical damage and rust or other results of corrosion at all times from manufacture to grouting or encasing in concrete. Prestressing steel that has sustained physical damage at any time shall be rejected. The development of visible rust or other results of corrosion shall be cause for rejection, when ordered by the Engineer.
 - Epoxy-coated prestressing steel strand shall be covered with an opaque polyethylene sheeting or other suitable protective material to protect the strand from exposure to sunlight, salt spray, and weather. For stacked coils, the protective covering shall be draped around the perimeter of the stack. The covering shall be adequately secured; however, it should allow for air circulation around the strand to prevent condensation under the covering. Epoxy-coated strand shall not be stored within 300 m of ocean or tidal water for more than 2 months.
 - Prestressing steel shall be packaged in containers or shipping forms for the protection of the steel against physical damage and corrosion during shipping and storage. Except for epoxy-coated strand, a corrosion inhibitor which prevents rust or other results of corrosion, shall be placed in the package or form, or shall be incorporated in a corrosion inhibitor carrier type packaging material, or when permitted by the Engineer, may be applied directly to the steel. The corrosion inhibitor shall have no deleterious effect on the steel or concrete or bond strength of steel to concrete. Packaging or forms damaged from any cause shall be immediately replaced or restored to original condition.
 - The shipping package or form shall be clearly marked with a statement that the package contains high-strength prestressing steel, and the type of corrosion inhibitor used, including the date packaged.
 - Prestressing steel for post-tensioning which is installed in members prior to placing and curing of the concrete, and which is not epoxy-coated, shall be continuously protected against rust or other results of corrosion, until grouted, by means of a corrosion inhibitor placed in the ducts or applied to the steel in the duct. The corrosion inhibitor shall conform to the provisions specified herein.
 - When steam curing is used, prestressing steel for post-tensioning shall not be installed until the steam curing is completed.
 - Water used for flushing ducts shall contain either quick lime (calcium oxide) or slaked lime (calcium hydroxide) in the amount of 0.01-kg/L. Compressed air used to blow out ducts shall be oil free.
 - When prestressing steel for post-tensioning is installed in the ducts after completion of concrete curing, and if stressing and grouting are completed within 10 days after the installation of the prestressing steel, rust which may form during those 10 days will not be cause for rejection of the steel. Prestressing steel installed, tensioned, and grouted in this manner, all within 10 days, will not require the use of a corrosion inhibitor in the duct following installation of the prestressing steel. Prestressing steel installed as above but not grouted within 10 days shall be subject to all the requirements in this section pertaining to corrosion protection and rejection because of rust. The requirements in this section pertaining to tensioning and grouting within 10 days shall not apply to epoxy-coated prestressing steel strand.
 - Any time prestressing steel for pretensioning is placed in the stressing bed and is exposed to the elements for more than 36 hours prior to encasement in concrete, adequate measures shall be taken by the Contractor, as approved by the Engineer, to protect the steel from contamination or corrosion.
 - After final fabrication of the seven-wire prestressing steel strand, no electric welding of any form shall be performed on the prestressing steel. Whenever electric welding is performed on or near members containing prestressing steel, the welding ground shall be attached directly to the steel being welded.

- Pretensioned prestressing steel shall be cut off flush with the end of the member. For epoxy-coated prestressing steel, only abrasive saws shall be used to cut the steel. The exposed ends of the prestressing steel and a 25-mm strip of adjoining concrete shall be cleaned and painted. Cleaning shall be by wire brushing or abrasive blast cleaning to remove all dirt and residue on the metal or concrete surfaces. Immediately after cleaning, the surfaces shall be covered with one application of unthinned zinc-rich primer (organic vehicle type) conforming to the provisions in Section 91, "Paint," except that 2 applications shall be applied to surfaces which will not be covered by concrete or mortar. Aerosol cans shall not be used. The paint shall be thoroughly mixed at the time of application and shall be worked into any voids in the prestressing tendons.

The seventh paragraph in Section 50-1.07, "Ducts," of the Standard Specifications is amended to read:

- All ducts with a total length of 120 m or more shall be vented. Vents shall be placed at intervals of not more than 120 m and shall be located within 2 m of every high point in the duct profile. Vents shall be 12 mm minimum diameter standard pipe or suitable plastic pipe. Connections to ducts shall be made with metallic or plastic structural fasteners. Plastic components, if selected, shall not react with the concrete or enhance corrosion of the prestressing steel and shall be free of water soluble chlorides. The vents shall be mortar tight, taped as necessary, and shall provide means for injection of grout through the vents and for sealing the vents. Ends of vents shall be removed 25 mm below the roadway surface after grouting has been completed.

The sixth paragraph of Section 50-1.08, "Prestressing," of the Standard Specifications is amended to read:

- The following formula and friction coefficients shall be used in calculating friction losses in tendons:

$$T_o = T_x e^{(\mu\alpha + KL)}$$

Where:

T_o = steel stress at jacking end

T_x = steel stress at any point x

e = base of Napierian logarithms

μ = friction curvature coefficient

α = total angular change of prestressing steel profile in radians from jacking end to point x

K = friction wobble coefficient (=0.00066/m)

L = length of prestressing steel from jacking end to point x

Type of Steel Tendon	Length of Tendon L(m)	Type of Duct	μ
Wire or Strand	0 to less than 183	Rigid or semi-rigid galvanized sheet metal	0.15
	183 to less than 275		0.20
	275 to less than 366		0.25
	Greater than or equal to 366		0.25*
Wire or Strand	All	Plastic	0.23
	All	Rigid Steel Pipes	0.25*
High Strength Bar	All	Rigid or semi-rigid galvanized sheet metal	0.30

* With the use of lubrication

The thirteenth and fourteenth paragraphs in Section 50-1.08, "Prestressing," of the Standard Specifications are amended to read:

- Prestressing steel in pretensioned members shall not be cut or released until the concrete in the member has attained a compressive strength of not less than the value shown on the plans or 28 MPa, whichever is greater. In addition to these concrete strength requirements, when epoxy-coated prestressing steel strand is used, the steel shall not be cut or released until the temperature of the concrete surrounding the strand is less than 65°C, and falling.
- When ordered by the Engineer, prestressing steel strands in pretensioned members, if tensioned individually, shall be checked by the Contractor for loss of prestress not more than 48 hours prior to placing concrete for the members. The method and equipment for checking the loss of prestress shall be subject to approval by the Engineer. Strands which show a loss of prestress in excess of 3 percent shall be retensioned to the original computed jacking stress.

Item 2 of the eleventh paragraph in Section 50-1.08, "Prestressing," of the Standard Specifications is amended to read:

2. When the concrete is designated by class or cementitious material content, either the concrete compressive strength shall have reached the strength shown on the plans at the time of stressing or at least 28 days shall have elapsed since the last concrete to be prestressed has been placed, whichever occurs first.

The second and third paragraphs in Section 50-1.09, "Bonding and Grouting," of the Standard Specifications are amended to read:

- Grout shall consist of cement and water and may contain an admixture if approved by the Engineer.
- Cement shall conform to the provisions in Section 90-2.01A, "Cement."

The fifth paragraph in Section 50-1.10, "Samples for Testing," of the Standard Specifications is amended to read:

- The following samples of materials and tendons, selected by the Engineer from the prestressing steel at the plant or jobsite, shall be furnished by the Contractor to the Engineer well in advance of anticipated use:
 - A. For wire or bars, one 2-m long sample and for strand, one 1.5-m long sample, of each size shall be furnished for each heat or reel.
 - B. For epoxy-coated strand, one 1.5-m long sample of uncoated strand of each size shall be furnished for each reel.
 - C. If the prestressing tendon is a bar, one 2-m long sample shall be furnished and in addition, if couplers are to be used with the bar, two 1.25-m long samples of bar, equipped with one coupler and fabricated to fit the coupler, shall be furnished.

The first paragraph in Section 50-1.11, "Payment," of the Standard Specifications is amended to read:

- No separate payment will be made for pretensioning precast concrete members. Payment for pretensioning precast concrete members shall be considered as included in the contract price paid for furnish precast members as provided for in Section 51, "Concrete Structures."

The second paragraph in Section 50-1.11, "Payment," of the Standard Specifications is amended to read:

- The contract lump sum prices paid for prestressing cast-in-place concrete of the types listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in furnishing, placing, and tensioning the prestressing steel in cast-in-place concrete structures, complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

SECTION 51: CONCRETE STRUCTURES

Issue Date: October 5, 2007

The eleventh paragraph in Section 51-1.05, "Forms," of the Standard Specifications is amended to read:

- Form panels for exposed surfaces shall be furnished and placed in uniform widths of not less than 0.9-m and in uniform lengths of not less than 1.8 m, except at the end of continuously formed surfaces where the final panel length required is less than 1.8 m. Where the width of the member formed is less than 0.9-m, the width of the panels shall be not less than the width of the member. Panels shall be arranged in symmetrical patterns conforming to the general lines of the structure. Except when otherwise provided herein or shown on the plans, panels for vertical surfaces shall be placed with the long dimension horizontal and with horizontal joints level and continuous. Form panels for curved surfaces of columns shall be continuous for a minimum of one quarter of the circumference, or 1.8 m. For walls with sloping footings which do not abut other walls, panels may be placed with the long dimension parallel to the footing. Form panels on each side of the panel joint shall be precisely aligned, by means of supports or fasteners common to both panels, to result in a continuous unbroken concrete plane surface. When prefabricated soffit panels are used, form filler panels joining prefabricated panels shall have a uniform minimum width of 0.3-m and shall produce a smooth uniform surface with consistent longitudinal joint lines between the prefabricated panels.

The first and second paragraph in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications are amended to read:

- The Contractor shall submit to the Engineer working drawings and design calculations for falsework proposed for use at bridges. For bridges where the height of any portion of the falsework, as measured from the ground line to the soffit of the superstructure, exceeds 4.25 m; or where any individual falsework clear span length exceeds 4.85 m; or where provision for vehicular, pedestrian, or railroad traffic through the falsework is made; the drawings shall be signed by an engineer who is registered as a Civil Engineer in the State of California. Six sets of the working drawings and 2 copies of the design calculations shall be furnished. Additional working drawings and design calculations shall be submitted to the Engineer when specified in "Railroad Relations and Insurance" of the special provisions.

- The falsework drawings shall include details of the falsework erection and removal operations showing the methods and sequences of erection and removal and the equipment to be used. The details of the falsework erection and removal operations shall demonstrate the stability of all or any portions of the falsework during all stages of the erection and removal operations.

The seventh paragraph in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications is amended to read:

- In the event that several falsework plans are submitted simultaneously, or an additional plan is submitted for review before the review of a previously submitted plan has been completed, the Contractor shall designate the sequence in which the plans are to be reviewed. In such event, the time to be provided for the review of any plan in the sequence shall be not less than the review time specified above for that plan, plus 2 weeks for each plan of higher priority which is still under review. A falsework plan submittal shall consist of plans for a single bridge or portion thereof. For multi-frame bridges, each frame shall require a separate falsework plan submittal.

Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications is amended by adding the following paragraphs:

- If structural composite lumber is proposed for use, the falsework drawings shall clearly identify the structural composite lumber members by grade (E value), species, and type. The Contractor shall provide technical data from the manufacturer showing the tabulated working stress values of the composite lumber. The Contractor shall furnish a certificate of compliance as specified in Section 6-1.07, "Certificates of Compliance," for each delivery of structural composite lumber to the project site.

- For falsework piles with a calculated loading capacity greater than 900 kN, the falsework piles shall be designed by an engineer who is registered as either a Civil Engineer or a Geotechnical Engineer in the State of California, and the calculations shall be submitted to the Engineer.

The first paragraph in Section 51-1.06A(1), "Design Loads," of the Standard Specifications is amended to read:

- The design load for falsework shall consist of the sum of dead and live vertical loads, and an assumed horizontal load. The minimum total design load for any falsework, including members that support walkways, shall be not less than 4800 N/m² for the combined live and dead load regardless of slab thickness.

The eighth paragraph in Section 51-1.06A(1), "Design Loads," of the Standard Specifications is amended to read:

- In addition to the minimum requirements specified in this Section 51-1.06A, falsework for box girder structures with internal falsework bracing systems using flexible members capable of withstanding tensile forces only, shall be designed to include the vertical effects caused by the elongation of the flexible member and the design horizontal load combined with the dead and live loads imposed by concrete placement for the girder stems and connected bottom slabs. Falsework comprised of individual steel towers with bracing systems using flexible members capable of withstanding tensile forces only to resist overturning, shall be exempt from these additional requirements.

The third paragraph in Section 51-1.06B, "Falsework Construction," of the Standard Specifications is amended to read:

- When falsework is supported on piles, the piles shall be driven and the actual nominal resistance assessed in conformance with the provisions in Section 49, "Piling."

Section 51-1.06B, "Falsework Construction," of the Standard Specifications is amended by adding the following paragraphs:

- For falsework piles with a calculated nominal resistance greater than 1800 kN, the Contractor shall conduct dynamic monitoring of pile driving and generate field acceptance criteria based on a wave equation analysis. These analyses shall be signed by an engineer who is registered as a Civil Engineer in the State of California and submitted to the Engineer prior to completion of falsework erection.

- Prior to the placement of falsework members above the stringers, the final bracing system for the falsework shall be installed.

Section 51-1.06C, "Removing Falsework," of the Standard Specifications is amended by adding the following paragraph:

- The falsework removal operation shall be conducted in such a manner that any portion of the falsework not yet removed remains in a stable condition at all times.

The sixth paragraph in Section 51-1.09, "Placing Concrete," of the Standard Specifications is amended to read:

- Vibrators used to consolidate concrete containing epoxy-coated bar reinforcement or epoxy-coated prestressing steel shall have a resilient covering to prevent damage to the epoxy-coating on the reinforcement or prestressing steel.

The fourth paragraph in Section 51-1.12D, "Sheet Packing, Preformed Pads, and Board Fillers," of the Standard Specifications is amended to read:

- Expanded polystyrene shall be a commercially available polystyrene board. Expanded polystyrene shall have a minimum flexural strength of 240 kPa determined in conformance with the requirements in ASTM Designation: C 203 and a compressive yield strength of between 110 and 275 kPa at 5 percent compression. Surfaces of expanded polystyrene against which concrete is placed shall be faced with hardboard. Hardboard shall be 3 mm minimum thickness, conforming to ANSI A135.4, any class. Other facing materials may be used provided they furnish equivalent protection. Boards shall be held in place by nails, waterproof adhesive, or other means approved by the Engineer.

Section 51-1.12F, "Sealed Joints," of the Standard Specifications is amended by adding the following paragraph:

- The opening of the joints at the time of placing shall be that shown on the plans adjusted for temperature. Care shall be taken to avoid impairment of the clearance in any manner.

The first paragraph in Section 51-1.12F, "Sealed Joints," of the Standard Specifications is amended to read:

- Where shown on the plans, joints in structures shall be sealed with joint seals, joint seal assemblies, or seismic joints in conformance with the details shown on the plans, the provisions in these specifications, and the special provisions.

The 2nd paragraph of Section 51-1.12F, "Sealed Joints," of the Standard Specifications is amended to read:

- Type A and AL joint seals shall consist of a groove in the concrete that is filled with field-mixed silicone sealant.

The fourth paragraph in Section 51-1.12F, "Sealed Joints," of the Standard Specifications is amended to read:

- Joint seal assemblies and seismic joints shall consist of metal or metal and elastomeric assemblies which are anchored or cast into a recess in the concrete over the joint. Strip seal joint seal assemblies consist of only one joint cell. Modular unit joint seal assemblies consist of more than one joint cell.

The fifth paragraph in Section 51-1.12F, "Sealed Joints," of the Standard Specifications is amended to read:

- The Movement Rating (MR) shall be measured normal to the longitudinal axis of the joint. The type of seal to be used for the MR shown on the plans shall be as follows:

Movement Rating (MR)	Seal Type
MR ≤ 25 mm	Type A or Type B
25 mm < MR ≤ 50 mm	Type B
50 mm < MR ≤ 100 mm	Joint Seal Assembly (Strip Seal)
MR > 100 mm	Joint Seal Assembly (Modular Unit) or Seismic Joint

The 1st paragraph of Section 51-1.12F(3)(a), "Type A and AL Seal," of the Standard Specifications is amended to read:

- The sealant must consist of a 2-component silicone sealant that will withstand up to ±50 percent movement.

The 2nd paragraph of Section 51-1.12F(3)(a), "Type A and AL Seal," of the Standard Specifications is amended to read:

- Silicone sealants must be tested under California Test 435 and must comply with the following:

Specification	Requirement
Modulus at 150 percent elongation	35–520 kPa
Recovery	17 mm max.
Notch Test	Notched or loss of bond 6 mm, max.
Water Resistance	Notched or loss of bond 6 mm, max.
Ultraviolet Exposure ASTM Designation: G 154, Table X2.1, Cycle 2.	No more than slight checking or cracking.
Cone Penetration	4.5-12.0 mm

The 3rd paragraph of Section 51-1.12F(3)(a), "Type A and AL Seal," of the Standard Specifications is deleted.

The 8th paragraph of Section 51-1.12F(3)(a), "Type A and AL Seal," of the Standard Specifications is deleted.

The 10th paragraph of Section 51-1.12F(3)(a), "Type A and AL Seal," of the Standard Specifications is amended to read:

- A Certificate of Compliance accompanied by a certified test report must be furnished for each batch of silicone sealant in conformance with the provisions in Section 6-1.07, "Certificates of Compliance."

The 2nd paragraph of Section 51-1.12F(3)(b), "Type B Seal," of the Standard Specifications is amended to read:

- The preformed elastomeric joint seal must conform to the requirements in ASTM D 2628 and the following:
 - The seal must consist of a multichannel, nonporous, homogeneous material furnished in a finished extruded form.
 - The minimum depth of the seal measured at the contact surface must be at least 95 percent of the minimum uncompressed width of the seal as designated by the manufacturer.
 - When tested in conformance with the requirements in California Test 673 for Type B seals, joint seals must provide a movement rating (MR) of not less than that shown on the plans.
 - The top and bottom edges of the joint seal must maintain continuous contact with the sides of the groove over the entire range of joint movement.
 - The seal must be furnished full length for each joint with no more than 1 shop splice in any 18 m length of seal.

6. The Contractor must demonstrate the adequacy of the procedures to be used in the work before installing seals in the joints.
7. One field splice per joint may be made at locations and by methods approved by the Engineer. The seals are to be manufactured full length for the intended joint, then cut at the approved splice section and rematched before splicing. The Contractor must submit splicing details prepared by the joint seal manufacturer for approval before beginning splicing work.
8. Shop splices and field splices must have no visible offset of exterior surfaces and must show no evidence of bond failure.
9. At all open ends of the seal that would admit water or debris, each cell must be filled to a depth of 80 mm with commercial quality open cell polyurethane foam or closed by other means subject to approval by the Engineer.

The 7th paragraph of Section 51-1.12F(3)(b), "Type B Seal," of the Standard Specifications is amended to read:

- The joint seal must be installed full length for each joint with equipment that does not twist or distort the seal, elongate the seal longitudinally, or otherwise cause damage to the seal or to the concrete forming the groove.

Section 51-1.12F(3)(c), "Joint Seal Assemblies," of the Standard Specifications is amended to read:

(c) Joint Seal Assemblies and Seismic Joints

- Joint seal assemblies and seismic joints shall be furnished and installed in joints in bridge decks as shown on the plans and as specified in the special provisions.

The eighth paragraph in Section 51-1.12H(1), "Plain and Fabric Reinforced Elastomeric Bearing Pads," of the Standard Specifications is amended to read:

- The elastomer, as determined from test specimens, shall conform to the following:

Test	ASTM Designation	Requirement
Tensile strength, MPa	D 412	15.5 Min.
Elongation at break, percent	D 412	350 Min.
Compression set, 22 h at 70°C, percent	D 395 (Method B)	25 Max.
Tear strength, kN/m	D 624 (Die C)	31.5 Min.
Hardness (Type A)	D 2240 with 2 kg. mass	55 ±5
Ozone resistance 20% strain, 100 h at 40°C ±2°C	D 1149 (except 100 ±20 parts per 100 000 000)	No cracks
Instantaneous thermal stiffening at -40°C	D 1043	Shall not exceed 4 times the stiffness measured at 23°C
Low temperature brittleness at -40°C	D 746 (Procedure B)	Pass

The table in the ninth paragraph of Section 51-1.12H(1), "Plain and Fabric Reinforced Elastomeric Bearing Pads," of the Standard Specifications is amended to read:

Tensile strength, percent	-15
Elongation at break, percent	-40; but not less than 300% total elongation of the material
Hardness, points	+10

The first paragraph in Section 51-1.12H(2), "Steel Reinforced Elastomeric Bearings," of the Standard Specifications is amended to read:

- Steel reinforced elastomeric bearings shall conform to the requirements for steel-laminated elastomeric bearings in ASTM Designation: D 4014 and the following:

- A. The bearings shall consist of alternating steel laminates and internal elastomer laminates with top and bottom elastomer covers. Steel laminates shall have a nominal thickness of 1.9 mm (14 gage). Internal elastomer laminates shall have a thickness of 12 mm, and top and bottom elastomer covers shall each have a thickness of 6 mm. The combined thickness of internal elastomer laminates and top and bottom elastomer covers shall be equal to the bearing pad thickness shown on the plans. The elastomer cover to the steel laminates at the sides of the bearing shall be 3 mm. If guide pins or other devices are used to control the side cover over the steel laminates, any exposed portions of the steel laminates shall be sealed by vulcanized patching. The length, width, or diameter of the bearings shall be as shown on the plans.
- B. The total thickness of the bearings shall be equal to the thickness of elastomer laminates and covers plus the thickness of the steel laminates.
- C. Elastomer for steel reinforced elastomeric bearings shall conform to the provisions for elastomer in Section 51-1.12H(1), "Plain and Fabric Reinforced Elastomeric Bearing Pads."
- D. A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished to the Engineer certifying that the bearings to be furnished conform to all of the above provisions. The Certificate of Compliance shall be supported by a certified copy of the results of tests performed by the manufacturer on the bearings.
- E. One sample bearing shall be furnished to the Engineer from each lot of bearings to be furnished for the contract. Samples shall be available at least 3 weeks in advance of intended use. The sample bearing shall be one of the following:

Bearing Pad Thickness as Shown on the Plans	Sample Bearing
≤ 50 mm	Smallest complete bearing shown on the plans
> 50 mm	* 57 ± 3 mm thick sample not less than 200 mm x 305 mm in plan and cut by the manufacturer from the center of one of the thickest complete bearings

* The sample bearing plus remnant parts of the complete bearing shall be furnished to the Engineer.

- F. A test specimen taken from the sample furnished to the Engineer will be tested in conformance with the requirements in California Test 663. Specimens tested shall show no indication of loss of bond between the elastomer and steel laminates.

The first paragraph in Section 51-1.135, "Mortar," of the Standard Specifications is amended to read:

- Mortar shall be composed of cementitious material, sand, and water proportioned and mixed as specified in this Section 51-1.135.

The third paragraph in Section 51-1.135, "Mortar," of the Standard Specifications is amended to read:

- The proportion of cementitious material to sand, measured by volume, shall be 1:2 unless otherwise specified.

The fourth paragraph in Section 51-1.14, "Waterstops," of the Standard Specifications is amended to read:

- Neoprene shall be manufactured from a vulcanized elastomeric compound containing neoprene as the sole elastomer and shall conform to the following:

Test	ASTM Designation	Requirement
Tensile strength, MPa	D 412	13.8 Min.
Elongation at break, percent	D 412	300 Min.
Compression set, 22 h at 70°C, percent	D 395 (Method B)	30 Max.
Tear strength, kN/m	D 624 (Die C)	26.3 Min.
Hardness (Type A)	D 2240	55±5
Ozone resistance 20% strain, 100 h at 38°C ±1°C	D 1149 (except 100±20 parts per 100 000 000)	No cracks
Low temperature brittleness at -40°C	D 746 (Procedure B)	Pass
Flame resistance	C 542	Must not propagate flame
Oil Swell, ASTM Oil #3, 70 h at 100°C, volume change, percent	D 471	80 Max.
Water absorption, immersed 7 days at 70°C, change in mass, percent	D 471	15 Max.

The first sentence of the fourth paragraph in Section 51-1.17, "Finish Bridge Decks," of the Standard Specifications is amended to read:

- The smoothness of completed roadway surfaces of structures, approach slabs and the adjacent 15 m of approach pavement, and the top surfaces of concrete decks which are to be covered with another material, will be tested by the Engineer with a bridge profilograph in conformance with the requirements in California Test 547 and the requirements herein.

Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications is amended by deleting the seventh, thirteenth and fourteenth paragraphs and adding the following subsection:

51-1.17A DECK CRACK TREATMENT

- The Contractor shall use all means necessary to minimize the development of shrinkage cracks.
- The Contractor shall remove all equipment and materials from the deck and clean the surface as necessary for the Engineer to measure the surface crack intensity. Surface crack intensity will be determined by the Engineer after completion of concrete cure, before prestressing, and before the release of falsework. In any 50 square meter portion of deck within the limits of the new concrete deck, should the intensity of cracking be such that there are more than 5 m of cracks whose width at any location exceeds 0.5 mm, the deck shall be treated with methacrylate resin. The area of deck to be treated shall have a width that extends for the entire width of new deck inside the concrete barriers and a length that extends at least 1.5 m beyond the furthest single continuous crack outside the 50 square meter portion, measured from where that crack exceeds 0.5 mm in width, as determined by the Engineer.
- Deck crack treatment shall include furnishing, testing, and application of methacrylate resin and sand. If grinding is required, deck treatment shall take place before grinding.

51-1.17A(1) Submittals

- Before starting deck treatment, the Contractor shall submit plans in conformance with Section 5-1.02, "Plans and Working Drawings," for the following:
 1. Public safety plan for the use of methacrylate resin
 2. Placement plan for the construction operation
- The plans shall identify materials, equipment, and methods to be used.
- The public safety plan for the use of methacrylate resin shall include details for the following:

1. Shipping
2. Storage
3. Handling
4. Disposal of residual methacrylate resin and the containers

- The placement plan for construction shall include the following:

1. Schedule of deck treatment for each bridge. The schedule shall be consistent with "Maintaining Traffic," of the special provisions and shall include time for the Engineer to perform California Test 342.
2. Methods and materials to be used, including the following:
 - 2.1. Description of equipment for applying the resin
 - 2.2. Description of equipment for applying the sand
 - 2.3. Gel time range and final cure time for the resin

- If the measures proposed in the safety plan are inadequate to provide for public safety associated with the use of methacrylate resin, the Engineer will reject the plan and direct the Contractor to revise the plan. Directions for revisions will be in writing and include detailed comments. The Engineer will notify the Contractor of the approval or rejection of a submitted or revised plan within 15 days of receipt of that plan.

- In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

51-1.17A(2) Materials

- Before using methacrylate resin, a Material Safety Data Sheet shall be submitted for each shipment of resin.
- Methacrylate resin shall be low odor and have a high molecular weight. Before adding initiator, the resin shall have a maximum volatile content of 30 percent when tested in conformance with the requirements in ASTM Designation: D 2369, and shall conform to the following:

PROPERTY	REQUIREMENT	TEST METHOD
* Viscosity	0.025 Pa·s, maximum, (Brookfield RVT with UL adaptor, 50 RPM at 25°C	ASTM D 2196
* Specific Gravity	0.90 minimum, at 25°C	ASTM D 1475
* Flash Point	82°C, minimum	ASTM D 3278
* Vapor Pressure	1.0 mm Hg, maximum, at 25°C	ASTM D 323
Tack-free Time	400 minutes, maximum, at 25°C	Specimen prepared per California Test 551
PCC Saturated Surface-Dry Bond Strength	3.5 MPa, minimum at 24 hours and 21±1°C	California Test 551
* Test shall be performed before adding initiator.		

51-1.17A(3) Testing

- The Contractor shall allow 20 days for sampling and testing by the Engineer of the methacrylate resin before proposed use. If bulk resin is to be used, the Contractor shall notify the Engineer in writing at least 15 days before the delivery of the bulk resin to the job site. Bulk resin is any resin stored in containers in excess of 209 liters.

- Before starting production treatment, the Contractor shall treat a test area of approximately 50 square meters that is within the project limits and at a location approved by the Engineer. When available the test area shall be outside of the traveled way. Weather and pavement conditions during the test treatment shall be similar to those expected on the deck. Equipment used for testing shall be similar to those used for deck treating operations.

- During test and production deck treatment, test tiles shall be used to evaluate the resin cure time. The Contractor shall coat at least one 102 mm x 102 mm commercial quality smooth glazed tile for each batch of methacrylate resin. The coated tile shall be placed adjacent to the corresponding treated area. Sand shall not be applied to the test tiles.

- The acceptance criteria for a treated area is as follows:

1. The test tiles are dry to the touch.
2. The treated deck surface is tack free (non-oily).
3. The sand cover adheres and resists brushing by hand.
4. Excess sand has been removed by vacuuming or sweeping.
5. The coefficient of friction is at least 0.35 when tested in conformance with California Test 342.

- If a test or production area fails to meet the acceptance criteria, as determined by the Engineer, the treatment will be rejected, and the treatment shall be removed and replaced until the area complies with the acceptance criteria.

51-1.17A(4) Construction

- Equipment shall be fitted with suitable traps, filters, drip pans, or other devices as necessary to prevent oil or other deleterious material from being deposited on the deck.

- Before deck treatment with methacrylate resin, the bridge deck surface shall be cleaned by abrasive blasting, and all loose material shall be blown from visible cracks using high-pressure air. Concrete curing seals shall be cleaned from the deck surface to be treated, and the deck shall be dry when blast cleaning is performed. If the deck surface becomes contaminated at any time before placing the resin, the deck surface shall be cleaned by abrasive blasting.

- Where abrasive blasting is being performed within 3 m of a lane occupied by public traffic, the residue including dust shall be removed immediately after contact between the abrasive and the surface being treated. The removal shall be by a vacuum attachment operating concurrently with the abrasive blasting operation.

- A compatible promoter/initiator system shall be capable of providing the resin gel time range shown on the placement plan. Gel time shall be adjusted to compensate for the changes in temperature throughout treatment application.

- Resin shall be applied by machine and by using a two-part resin system with a promoted resin for one part and an initiated resin for the other part. This two-part resin system shall be combined at equal volumes to the spray bars through separate positive displacement pumps. Combining of the 2 components shall be by either static in-line mixers or by external intersecting spray fans. The pump pressure at the spray bars shall not be great enough to cause appreciable atomization of the resin. Compressed air shall not be used to produce the spray. A shroud shall be used to enclose the spray bar apparatus.

- At the Contractor's option, manual application may be used. For manual application, (1) the quantity of resin mixed with promoter and initiator shall be limited to 20 L at a time, and (2) the resin shall be distributed by squeegees and brooms within 10 minutes after application.

- The Contractor shall apply methacrylate resin only to the specified area. Barriers, railing, joints, and drainage facilities shall be adequately protected to prevent contamination by the treatment material. Contaminated items shall be repaired at the Contractor's expense.

- The relative humidity shall be less than 90 percent at the time of treatment. The prepared area shall be dry and the surface temperature shall be at least 10°C, and not more than 38°C when the resin is applied. The rate of application of promoted/initiated resin shall be 2.2 square meter per liter; the exact rate shall be determined by the Engineer.

- The deck surfaces to be treated shall be completely covered with resin so the resin penetrates and fills all cracks. The resin shall be applied within 5 minutes after complete mixing. A significant increase in viscosity shall be cause for rejection. Excess material shall be redistributed by squeegees or brooms within 10 minutes after application. For textured deck surfaces, including grooved surfaces, excess material shall be removed from the texture indentations.

- After the resin has been applied, at least 20 minutes shall elapse before applying sand. The sand shall be commercial quality dry blast sand. At least 95 percent of the sand shall pass the 2.36-mm sieve and at least 95 percent shall be retained on the 850-µm sieve. The sand shall be applied at a rate of approximately one kilogram per square meter or until refusal as determined by the Engineer.

- Traffic will not be allowed on treated areas until the acceptance criteria has been met as determined by the Engineer.

The second paragraph in Section 51-1.18C, "Class 2 Surface Finish (Gun Finish)," of the Standard Specifications is amended to read:

- When Class 2 surface finish (gun finish) is specified, ordinary surface finish shall first be completed. The concrete surfaces shall then be abrasive blasted to a rough texture and thoroughly washed down with water. While the washed surfaces are damp, but not wet, a finish coating of machine applied mortar, approximately 6 mm thick, shall be applied in not less than 2 passes. The coating shall be pneumatically applied and shall consist of either (1) sand, cementitious material, and water mechanically mixed prior to its introduction to the nozzle or (2) premixed sand and cementitious material to which water is added prior to its expulsion from the nozzle. The use of admixtures shall be subject to the approval of the Engineer as provided in Section 90, "Portland Cement Concrete." Unless otherwise specified, supplementary cementitious materials will not be required. The proportion of cementitious material to sand shall be not less than one to 4, unless otherwise directed by the Engineer. Sand shall be of a grading suitable for the purpose intended. The machines shall be operated and the coating shall be applied in conformance with standard practice. The coating shall be firmly bonded to the concrete surfaces on which it is applied.

The fifth paragraph in Section 51-1.18C, "Class 2 Surface Finish (Gun Finish)," of the Standard Specifications is amended to read:

- When surfaces to be finished are in pedestrian undercrossings, the sand shall be silica sand and the cementitious material shall be standard white portland cement.

The fourteenth paragraph in Section 51-1.23, "Payment," of the Standard Specifications is amended by deleting "and injecting epoxy in cracks".

Section 51-1.23, "Payment," of the Standard Specifications is amended by adding the following:

- Full compensation for deck crack treatment, including execution of the public safety plan, shall be considered as included in the contract price paid per cubic yard for structural concrete, bridge, and no additional compensation will be allowed therefor.

SECTION 52: REINFORCEMENT

Issue Date: June 30, 2006

The first paragraph in Section 52-1.02A, "Bar Reinforcement," of the Standard Specifications is amended to read:

- Reinforcing bars shall be low-alloy steel deformed bars conforming to the requirements in ASTM Designation: A 706/A 706M, except that deformed or plain billet-steel bars conforming to the requirements in ASTM Designation: A 615/A 615M, Grade 280 or 420, may be used as reinforcement in the following 5 categories:

- A. Slope and channel paving,
- B. Minor structures,
- C. Sign and signal foundations (pile and spread footing types),
- D. Roadside rest facilities, and
- E. Concrete barrier Type 50 and Type 60 series and temporary railing.

The third paragraph in Section 52-1.04, "Inspection," of the Standard Specifications is amended to read:

- A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall also be furnished for each shipment of epoxy-coated bar reinforcement or wire reinforcement certifying that the coated reinforcement conforms to the requirements in ASTM Designation: A 775/A 775M or A 884/A 884M respectively, and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement." The Certificate of Compliance shall include all of the certifications specified in ASTM Designation: A 775/A 775M or A 884/A 884M respectively.

The third paragraph of Section 52-1.06, "Bending," of the Standard Specifications is amended to read:

- Hooks and bends shall conform to the provisions of the Building Code Requirements for Structural Concrete of the American Concrete Institute.

Section 52-1.07 "Placing," of the Standard Specifications is amended by deleting item C of the third paragraph.

The eleventh paragraph in Section 52-1.07, "Placing," of the Standard Specifications is amended to read:

- Attention is directed to the provisions in Section 7-1.09, "Public Safety." Whenever a portion of an assemblage of bar reinforcing steel that is not encased in concrete exceeds 6 m in height, the Contractor shall submit to the Engineer for approval, in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," working drawings and design calculations for the temporary support system to be used. The working drawings and design calculations shall be signed by an engineer who is registered as a Civil Engineer in the State of California. The temporary support system shall be designed to resist all expected loads and shall be adequate to prevent collapse or overturning of the assemblage. If the installation of forms or other work requires revisions to or temporary release of any portion of the temporary support system, the working drawings shall show the support system to be used during each phase of construction. The minimum horizontal wind load to be applied to the bar reinforcing steel assemblage, or to a combined assemblage of reinforcing steel and forms, shall be the sum of the products of the wind impact area and the applicable wind pressure value for each height zone. The wind impact area is the total projected area of the cage normal to the direction of the applied wind. Wind pressure values shall be determined from the following table:

Height Zone (Meters above ground)	Wind Pressure Value (Pa)
0-9.0	960
9.1-15.0	1200
15.1-30.0	1440
Over 30	1675

Section 52-1.08 "Splicing," of the Standard Specifications is amended to read:

52-1.08 SPLICING

- Splices of reinforcing bars shall consist of lap splices, service splices, or ultimate butt splices.
- Splicing of reinforcing bars will not be permitted at a location designated on the plans as a "No-Splice Zone." At the option of the Contractor, reinforcing bars may be continuous at locations where splices are shown on the plans. The location of splices, except where shown on the plans, shall be determined by the Contractor using available commercial lengths where practicable.
 - Unless otherwise shown on the plans, splices in adjacent reinforcing bars at any particular section shall be staggered. The minimum distance between staggered lap splices or mechanical lap splices shall be the same as the length required for a lap splice in the largest bar. The minimum distance between staggered butt splices shall be 600 mm, measured between the midpoints of the splices along a line which is centered between the axes of the adjacent bars.

52-1.08A Lap Splicing Requirements

- Splices made by lapping shall consist of placing reinforcing bars in contact and wiring them together, maintaining the alignment of the bars and the minimum clearances. Should the Contractor elect to use a butt welded or mechanical splice at a location not designated on the plans as requiring a service or ultimate butt splice, this splice shall conform to the testing requirements for service splice.

- Reinforcing bars shall not be spliced by lapping at locations where the concrete section is not sufficient to provide a minimum clear distance of 50 mm between the splice and the nearest adjacent bar. The clearance to the surface of the concrete specified in Section 52-1.07, "Placing," shall not be reduced.

- Reinforcing bars Nos. 43 and 57 shall not be spliced by lapping.

- Where ASTM Designations: A 615/A 615M, Grade 420 or A 706/A 706M reinforcing bars are required, the length of lap splices shall be as follows: Reinforcing bars No. 25 or smaller shall be lapped at least 45 diameters of the smaller bar joined; and reinforcing bars Nos. 29, 32, and 36 shall be lapped at least 60 diameters of the smaller bar joined, except when otherwise shown on the plans.

- Where ASTM Designation: A 615/A 615M, Grade 280 reinforcing bars are permitted, the length of lap splices shall be as follows: Reinforcing bars No. 25 or smaller shall be lapped at least 30 diameters of the smaller bar joined; and reinforcing bars Nos. 29, 32, and 36 shall be lapped at least 45 diameters of the smaller bar joined, except when otherwise shown on the plans.

- Splices in bundled bars shall conform to the following:

A In bundles of 2 bars, the length of the lap splice shall be the same as the length of a single bar lap splice.

B In bundles of 3 bars, the length of the lap splice shall be 1.2 times the length of a single bar lap splice.

- Welded wire fabric shall be lapped such that the overlap between the outermost cross wires is not less than the larger of:
 - A. 150 mm,
 - B. The spacing of the cross wires plus 50 mm, or
 - C. The numerical value of the longitudinal wire size (MW-Size Number) times 370 divided by the spacing of the longitudinal wires in millimeters.

52-1.08B Service Splicing and Ultimate Butt Splicing Requirements

- Service splices and ultimate butt splices shall be either butt welded or mechanical splices, shall be used at the locations shown on the plans, and shall conform to the requirements of these specifications and the special provisions.

52-1.08B(1) Mechanical Splices

- Mechanical splices to be used in the work shall be on the Department's current prequalified list before use. The prequalified list can be obtained from the Department's internet site listed in the special provisions or by contacting the Transportation Laboratory directly.
 - When tested in conformance with the requirements in California Test 670, the total slip shall not exceed the values listed in the following table:

Reinforcing Bar Number	Total Slip (µm)
13	250
16	250
19	250
22	350
25	350
29	350
32	450
36	450
43	600
57	750

- Slip requirements shall not apply to mechanical lap splices, splices that are welded, or splices that are used on hoops.
- Splicing procedures shall be in conformance with the manufacturer's recommendations, except as modified in this section. Splices shall be made using the manufacturer's standard equipment, jigs, clamps, and other required accessories.
 - Splice devices shall have a clear coverage of not less than 40 mm measured from the surface of the concrete to the outside of the splice device. Stirrups, ties, and other reinforcement shall be adjusted or relocated, and additional reinforcement shall be placed, if necessary, to provide the specified clear coverage to reinforcement.
 - The Contractor shall furnish the following information for each shipment of splice material in conformance with the provisions in Section 6-1.07, "Certificates of Compliance:"
 - A. The type or series identification of the splice material including tracking information for traceability.
 - B. The bar grade and size number to be spliced.
 - C. A copy of the manufacturer's product literature giving complete data on the splice material and installation procedures.
 - D. A statement that the splicing systems and materials used in conformance with the manufacturer's installation procedures will develop the required tensile strengths, based on the nominal bar area, and will conform to the total slip requirements and the other requirements in these specifications.
 - E. A statement that the splice material conforms to the type of mechanical splice in the Department's current prequalified list.

52-1.08B(2) Butt Welded Splices

- Except for resistance butt welds, butt welded splices of reinforcing bars shall be complete joint penetration butt welds conforming to the requirements in AWS D 1.4, and these specifications.
 - Welders and welding procedures shall be qualified in conformance with the requirements in AWS D 1.4.
 - Only the joint details and dimensions as shown in Figure 3.2, "Direct Butt Joints," of AWS D 1.4, shall be used for making complete joint penetration butt welds of bar reinforcement. Split pipe backing shall not be used.

- Butt welds shall be made with multiple weld passes using a stringer bead without an appreciable weaving motion. The maximum stringer bead width shall be 2.5 times the diameter of the electrode and slagging shall be performed between each weld pass. Weld reinforcement shall not exceed 4 mm in convexity.

- Electrodes used for welding shall meet the minimum Charpy V-notch impact requirement of 27°J at -20°C.

- For welding of bars conforming to the requirements of ASTM Designation: A 615/A 615M, Grade 280 or Grade 420, the requirements of Table 5.2, "Minimum Preheat and Interpass Temperatures," of AWS D 1.4 are superseded by the following:

The minimum preheat and interpass temperatures shall be 200°C for Grade 280 bars and 300°C for Grade 420 bars. Immediately after completing the welding, at least 150 mm of the bar on each side of the splice shall be covered by an insulated wrapping to control the rate of cooling. The insulated wrapping shall remain in place until the bar has cooled below 90°C.

- When welding different grades of reinforcing bars, the electrode shall conform to Grade 280 bar requirements and the preheat shall conform to the Grade 420 bar requirements.

- In the event that any of the specified preheat, interpass, and post weld cooling temperatures are not met, all weld and heat affected zone metal shall be removed and the splice rewelded.

- Welding shall be protected from air currents, drafts, and precipitation to prevent loss of heat or loss of arc shielding. The method of protecting the welding area from loss of heat or loss of arc shielding shall be subject to approval by the Engineer.

- Reinforcing bars shall not be direct butt spliced by thermite welding.

- Procedures to be used in making welded splices in reinforcing bars, and welders employed to make splices in reinforcing bars, shall be qualified by tests performed by the Contractor on sample splices of the type to be used, before making splices to be used in the work.

52-1.08B(3) Resistance Butt Welds

- Shop produced resistance butt welds shall be produced by a fabricator who is approved by the Transportation Laboratory. The list of approved fabricators can be obtained from the Department's internet site or by contacting the Transportation Laboratory directly.

- Before manufacturing hoops using resistance butt welding, the Contractor shall submit to the Engineer the manufacturer's Quality Control (QC) manual for the fabrication of hoops. As a minimum, the QC manual shall include the following:

- A. The pre-production procedures for the qualification of material and equipment.
- B. The methods and frequencies for performing QC procedures during production.
- C. The calibration procedures and calibration frequency for all equipment.
- D. The welding procedure specification (WPS) for resistance welding.
- E. The method for identifying and tracking lots.

52-1.08C Service Splice and Ultimate Butt Splice Testing Requirements

- The Contractor shall designate in writing a splicing Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for 1) the quality of all service and ultimate butt splicing including the inspection of materials and workmanship performed by the Contractor and all subcontractors; and 2) submitting, receiving, and approving all correspondence, required submittals, and reports regarding service and ultimate splicing to and from the Engineer.

- The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

- Testing on prequalification and production sample splices shall be performed at the Contractor's expense, at an independent qualified testing laboratory. The laboratory shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors who will provide other services or materials for the project, and shall have the following:

- A. Proper facilities, including a tensile testing machine capable of breaking the largest size of reinforcing bar to be tested with minimum lengths as shown in this section.
- B. A device for measuring the total slip of the reinforcing bars across the splice to the nearest 25 μm, that, when placed parallel to the longitudinal axis of the bar is able to simultaneously measure movement across the splice at 2 locations 180 degrees apart.

- C. Operators who have received formal training for performing the testing requirements of ASTM Designation: A 370 and California Test 670.
- D. A record of annual calibration of testing equipment performed by an independent third party that has 1) standards that are traceable to the National Institute of Standards and Technology, and 2) a formal reporting procedure, including published test forms.

- The Contractor shall provide samples for quality assurance testing in conformance with the provisions in these specifications and the special provisions.

- Prequalification and production sample splices shall be 1) a minimum length of 1.5 meters for reinforcing bars No. 25 or smaller, and 2 meters for reinforcing bars No. 29 or larger, with the splice located at mid-point; and 2) suitably identified before shipment with weatherproof markings that do not interfere with the Engineer's tamper-proof markings or seals. Splices that show signs of tampering will be rejected.

- Shorter length sample splice bars may be furnished if approved in writing by the Engineer.

- The Contractor shall ensure that sample splices are properly secured and transported to the testing laboratory in such a manner that no alterations to the physical conditions occur during transportation. Sample splices shall be tested in the same condition as received. No modifications to the sample splices shall be made before testing.

- Each set or sample splice, as defined herein, shall be identified as representing either a prequalification or production test sample splice.

- For the purpose of production testing, a lot of either service splices or ultimate butt splices is defined as 1) 150, or fraction thereof, of the same type of mechanical splices used for each bar size and each bar deformation pattern that is used in the work, or 2) 150, or fraction thereof, of complete joint penetration butt welded splices or resistance butt welded splices for each bar size used in the work. If different diameters of hoop reinforcement are shown on the plans, separate lots shall be used for each different hoop diameter.

- Whenever a lot of splices is rejected, the rejected lot and subsequent lots of splices shall not be used in the work until 1) the QCM performs a complete review of the Contractor's quality control process for these splices, 2) a written report is submitted to the Engineer describing the cause of failure for the splices in this lot and provisions for preventing similar failures in future lots, and 3) the Engineer has provided the Contractor with written notification that the report is acceptable. The Engineer shall have 3 working days after receipt of the report to provide notification to the Contractor. In the event the Engineer fails to provide notification within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in providing notification, the Contractor will be compensated for any resulting loss, and an extension of time will be granted in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

52-1.08C(1) Splice Prequalification Report

- Before using any service splices or ultimate butt splices in the work, the Contractor shall submit a Splice Prequalification Report. The report shall include splice material information, names of the operators who will be performing the splicing, and descriptions of the positions, locations, equipment, and procedures that will be used in the work.

- The Splice Prequalification Report shall also include certifications from the fabricator for prequalifications of operators and procedures based on sample tests performed no more than 2 years before submitting the report. Each operator shall be certified by performing 2 sample splices for each bar size of each splice type that the operator will be performing in the work. For deformation-dependent types of splice devices, each operator shall be certified by performing 2 additional samples for each bar size and deformation pattern that will be used in the work.

- Prequalification sample splices shall be tested by an independent qualified testing laboratory and shall conform to the appropriate production test criteria and slip requirements specified herein. When epoxy-coated reinforcement is required, resistance butt welded sample splices shall have the weld flash removed by the same procedure as will be used in the work, before coating and testing. The Splice Prequalification Report shall include the certified test results for all prequalification sample splices.

- The QCM shall review and approve the Splice Prequalification Report before submitting it to the Engineer for approval. The Contractor shall allow 2 weeks for the review and approval of a complete report before performing any service splicing or ultimate butt splicing in the work. In the event the Engineer fails to complete the review within the time allowed, and in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

52-1.08C(2) Service Splice Test Criteria

- Service production and quality assurance sample splices shall be tensile tested in conformance with the requirements in ASTM Designation: A 370 and California Test 670 and shall develop a minimum tensile strength of not less than 550 MPa.

52-1.08C(2)(a) Production Test Requirements for Service Splices

- Production tests shall be performed by the Contractor's independent laboratory for all service splices used in the work. A production test shall consist of testing 4 sample splices prepared for each lot of completed splices. The samples shall be prepared by the Contractor using the same splice material, position, operators, location, and equipment, and following the same procedure as used in the work.
- At least one week before testing, the Contractor shall notify the Engineer in writing of the date when and the location where the testing of the samples will be performed.
- The 4 samples from each production test shall be securely bundled together and identified with a completed sample identification card before shipment to the independent laboratory. The card will be furnished by the Engineer. Bundles of samples containing fewer than 4 samples of splices shall not be tested.
- Before performing any tensile tests on production test sample splices, one of the 4 samples shall be tested for, and shall conform to, the requirements for total slip. Should this sample not meet the total slip requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. Should any of the 3 remaining samples not conform to the total slip requirements, all splices in the lot represented by this production test will be rejected.
- If 3 or more sample splices from a production test conform to the provisions in this Section 52-1.08C(2), "Service Splice Test Criteria," all splices in the lot represented by this production test will be considered acceptable, provided each of the 4 samples develop a minimum tensile strength of not less than 420 MPa.
- Should only 2 sample splices from a production test conform to the provisions in this Section 52-1.08C(2), "Service Splice Test Criteria," one additional production test shall be performed on the same lot of splices. This additional production test shall consist of testing 4 sample splices that have been randomly selected by the Engineer and removed by the Contractor from the actual completed lot of splices. Should any of the 4 splices from this additional test fail to conform to these provisions, all splices in the lot represented by these production tests will be rejected.
- If only one sample splice from a production test conforms to the provisions in this Section 52-1.08C(2), "Service Splice Test Criteria," all splices in the lot represented by this production test will be rejected.
- If a production test for a lot fails, the Contractor shall repair or replace all reinforcing bars from which sample splices were removed before the Engineer selects additional splices from this lot for further testing.

52-1.08C(2)(b) Quality Assurance Test Requirements for Service Splices

- For the first production test performed, and for at least one, randomly selected by the Engineer, of every 5 subsequent production tests, or portion thereof, the Contractor shall concurrently prepare 4 additional service quality assurance sample splices. These service quality assurance sample splices shall be prepared in the same manner as specified herein for service production sample splices.
- These 4 additional quality assurance sample splices shall be shipped to the Transportation Laboratory for quality assurance testing. The 4 sample splices shall be securely bundled together and identified by location and contract number with weatherproof markings before shipment. Bundles containing fewer than 4 samples of splices will not be tested. Sample splices not accompanied by the supporting documentation required in Section 52-1.08B(1), for mechanical splices, or in Section 52-1.08B(3), for resistance butt welds, will not be tested.
- Quality assurance testing will be performed in conformance with the requirements for service production sample splices in Section 52-1.08C(2)(a), "Production Test Requirements for Service Splices."

52-1.08C(3) Ultimate Butt Splice Test Criteria

- Ultimate production and quality assurance sample splices shall be tensile tested in conformance with the requirements described in ASTM Designation: A 370 and California Test 670.
- A minimum of one control bar shall be removed from the same bar as, and adjacent to, all ultimate prequalification, production, and quality assurance sample splices. Control bars shall be 1) a minimum length of one meter for reinforcing bars No. 25 or smaller and 1.5 meters for reinforcing bars No. 29 or larger, and 2) suitably identified before shipment with weatherproof markings that do not interfere with the Engineer's tamper-proof markings or seals. The portion of adjacent bar remaining in the work shall also be identified with weatherproof markings that correspond to its adjacent control bar.
- Each sample splice and its associated control bar shall be identified and marked as a set. Each set shall be identified as representing a prequalification, production, or quality assurance sample splice.
- The portion of hoop reinforcing bar, removed to obtain a sample splice and control bar, shall be replaced using a prequalified ultimate mechanical butt splice, or the hoop shall be replaced in kind.
- Reinforcing bars, other than hoops, from which sample splices are removed, shall be repaired using ultimate mechanical butt splices conforming to the provisions in Section 52-1.08C(1), "Splice Prequalification Report," or the bars shall be replaced in kind. These bars shall be repaired or replaced such that no splices are located in any "No Splice Zone" shown on the plans.

- Ultimate production and quality assurance sample splices shall rupture in the reinforcing bar either: 1) outside of the affected zone or 2) within the affected zone, provided that the sample splice has achieved at least 95 percent of the ultimate tensile strength of the control bar associated with the sample splice. In addition, necking of the bar, as defined in California Test 670, shall be evident at rupture regardless of whether the bar breaks inside or outside the affected zone.

- The affected zone is the portion of the reinforcing bar where any properties of the bar, including the physical, metallurgical, or material characteristics, have been altered by fabrication or installation of the splice.

- The ultimate tensile strength shall be determined for all control bars by tensile testing the bars to rupture, regardless of where each sample splice ruptures. If 2 control bars are tested for one sample splice, the bar with the lower ultimate tensile strength shall be considered the control bar.

52-1.08C(3)(a) Production Test Requirements for Ultimate Butt Splices

- Production tests shall be performed for all ultimate butt splices used in the work. A production test shall consist of testing 4 sets of sample splices and control bars removed from each lot of completed splices, except when quality assurance tests are performed.

- After the splices in a lot have been completed, and the bars have been epoxy-coated when required, the QCM shall notify the Engineer in writing that the splices in this lot conform to the specifications and are ready for testing. Except for hoops, sample splices will be selected by the Engineer at the job site. Sample splices for hoops will be selected by the Engineer either at the job site or a fabrication facility.

- After notification has been received, the Engineer will randomly select the 4 sample splices to be removed from the lot and place tamper-proof markings or seals on them. The Contractor shall select the adjacent control bar for each sample splice bar, and the Engineer will place tamper-proof markings or seals on them. These ultimate production sample splices and control bars shall be removed by the Contractor, and tested by an independent qualified testing laboratory.

- At least one week before testing, the Contractor shall notify the Engineer in writing of the date when and the location where the testing of the samples will be performed.

- A sample splice or control bar from any set will be rejected if a tamper-proof marking or seal is disturbed before testing.

- The 4 sets from each production test shall be securely bundled together and identified with a completed sample identification card before shipment to the independent laboratory. The card will be furnished by the Engineer. Bundles of samples containing fewer than 4 sets of splices shall not be tested.

- Before performing any tensile tests on production test sample splices, one of the 4 sample splices shall be tested for, and shall conform to, the requirements for total slip. Should this sample splice not meet these requirements, one retest, in which the 3 remaining sample splices are tested for total slip, will be allowed. Should any of the 3 remaining sample splices not conform to these requirements, all splices in the lot represented by this production test will be rejected.

- If 3 or more sample splices from a production test conform to the provisions in Section 52-1.08C(3), "Ultimate Butt Splice Test Criteria," all splices in the lot represented by this production test will be considered acceptable.

- Should only 2 sample splices from a production test conform to the provisions in Section 52-1.08C(3), "Ultimate Butt Splice Test Criteria," one additional production test shall be performed on the same lot of splices. Should any of the 4 sample splices from this additional test fail to conform to these provisions, all splices in the lot represented by these production tests will be rejected.

- If only one sample splice from a production test conforms to the provisions in Section 52-1.08C(3), "Ultimate Butt Splice Test Criteria," all splices in the lot represented by this production test will be rejected.

- If a production test for a lot fails, the Contractor shall repair or replace all reinforcing bars from which sample splices were removed, complete in place, before the Engineer selects additional splices from this lot for further testing.

- Production tests will not be required on repaired splices from a lot, regardless of the type of prequalified ultimate mechanical butt splice used to make the repair. However, should an additional production test be required, the Engineer may select any repaired splice for the additional production test.

52-1.08C(3)(b) Quality Assurance Test Requirements for Ultimate Butt Splices

- For the first production test performed, and for at least one, randomly selected by the Engineer, of every 5 subsequent production tests, or portion thereof, the Contractor shall concurrently prepare 4 additional ultimate quality assurance sample splices along with associated control bars.

- Each time 4 additional ultimate quality assurance sample splices are prepared, 2 of these quality assurance sample splice and associated control bar sets and 2 of the production sample splice and associated control bar sets, together, shall conform to the requirements for ultimate production sample splices in Section 52-1.08C(3)(a), "Production Test Requirements for Ultimate Butt Splices."

- The 2 remaining quality assurance sample splice and associated control bar sets, along with the 2 remaining production sample splice and associated control bar sets shall be shipped to the Transportation Laboratory for quality assurance testing. The 4 sets shall be securely bundled together and identified by location and contract number with weatherproof markings before shipment. Bundles containing fewer than 4 sets will not be tested.
- Quality assurance testing will be performed in conformance with the requirements for ultimate production sample splices in Section 52-1.08C(3)(a), "Production Test Requirements for Ultimate Butt Splices."

52-1.08C(3)(c) Nondestructive Splice Tests

- When the specifications allow for welded sample splices to be taken from other than the completed lot of splices, the Contractor shall meet the following additional requirements.
 - Except for resistance butt welded splices, radiographic examinations shall be performed on 25 percent of all complete joint penetration butt welded splices from a production lot. The size of a production lot will be a maximum of 150 splices. The Engineer will select the splices which will compose the production lot and also the splices within each production lot to be radiographically examined.
 - All required radiographic examinations of complete joint penetration butt welded splices shall be performed by the Contractor in conformance with the requirements in AWS D 1.4 and these specifications.
 - Before radiographic examination, welds shall conform to the requirements in Section 4.4, "Quality of Welds," of AWS D 1.4.
 - Should more than 12 percent of the splices which have been radiographically examined in any production lot be defective, an additional 25 percent of the splices, selected by the Engineer from the same production lot, shall be radiographically examined. Should more than 12 percent of the cumulative total of splices tested from the same production lot be defective, all remaining splices in the lot shall be radiographically examined.
 - Additional radiographic examinations performed due to the identification of defective splices shall be at the Contractor's expense.
 - All defects shall be repaired in conformance with the requirements in AWS D 1.4.
 - The Contractor shall notify the Engineer in writing 48 hours before performing any radiographic examinations.
 - The radiographic procedure used shall conform to the requirements in AWS D1.1, AWS D1.4, and the following:
 - A. Two exposures shall be made for each complete joint penetration butt welded splice. For each of the 2 exposures, the radiation source shall be centered on each bar to be radiographed. The first exposure shall be made with the radiation source placed at zero degrees from the top of the weld and perpendicular to the weld root and identified with a station mark of "0." The second exposure shall be at 90 degrees to the "0" station mark and shall be identified with a station mark of "90." When obstructions prevent a 90 degree placement of the radiation source for the second exposure, and when approved in writing by the Engineer, the source may be rotated, around the centerline of the reinforcing bar, a maximum of 25 degrees.
 - B. For field produced complete joint penetration butt welds, no more than one weld shall be radiographed during one exposure. For shop produced complete joint penetration butt welds, if more than one weld is to be radiographed during one exposure, the angle between the root line of each weld and the direction to the radiation source shall be not less than 65 degrees.
 - C. Radiographs shall be made by either X-ray or gamma ray. Radiographs made by X-ray or gamma rays shall have densities of not less than 2.3 nor more than 3.5 in the area of interest. A tolerance of 0.05 in density is allowed for densitometer variations. Gamma rays shall be from the iridium 192 isotope and the emitting specimen shall not exceed 4.45 mm in the greatest diagonal dimension.
 - D. The radiographic film shall be placed perpendicular to the radiation source at all times; parallel to the root line of the weld unless source placement determines that the film must be turned; and as close to the root of the weld as possible.
 - E. The minimum source to film distance shall be maintained so as to ensure that all radiographs maintain a maximum geometric unsharpness of 0.020 at all times, regardless of the size of the reinforcing bars.
 - F. Penetrators shall be placed on the source side of the bar and perpendicular to the radiation source at all times. One penetrator shall be placed in the center of each bar to be radiographed, perpendicular to the weld root, and adjacent to the weld. Penetrator images shall not appear in the weld area.
 - G. When radiography of more than one weld is being performed per exposure, each exposure shall have a minimum of one penetrator per bar, or 3 penetrators per exposure. When 3 penetrators per exposure are used, one penetrator shall be placed on each of the 2 outermost bars of the exposure, and the remaining penetrator shall be placed on a centrally located bar.
 - H. An allowable weld buildup of 4 mm may be added to the total material thickness when determining the proper penetrator selection. No image quality indicator equivalency will be accepted. Wire penetrators or penetrator blocks shall not be used.

- I. Penetrimeters shall be sufficiently shimmed using a radiographically identical material. Penetrimeter image densities shall be a minimum of 2.0 and a maximum of 3.6.
- J. Radiographic film shall be Class 1, regardless of the size of reinforcing bars.
- K. Radiographs shall be free of film artifacts and processing defects, including, but not limited to, streaks, scratches, pressure marks or marks made for the purpose of identifying film or welding indications.
- L. Each splice shall be clearly identified on each radiograph and the radiograph identification and marking system shall be established between the Contractor and the Engineer before radiographic inspection begins. Film shall be identified by lead numbers only; etching, flashing or writing in identifications of any type will not be permitted. Each piece of film identification information shall be legible and shall include, as a minimum, the following information: Contractor's name, date, name of nondestructive testing firm, initials of radiographer, contract number, part number and weld number. The letter "R" and repair number shall be placed directly after the weld number to designate a radiograph of a repaired weld.
- M. Radiographic film shall be developed within a time range of one minute less to one minute more than the film manufacturer's recommended maximum development time. Sight development will not be allowed.
- N. Processing chemistry shall be done with a consistent mixture and quality, and processing rinses and tanks shall be clean to ensure proper results. Records of all developing processes and any chemical changes to the developing processes shall be kept and furnished to the Engineer upon request. The Engineer may request, at any time, that a sheet of unexposed film be processed in the presence of the Engineer to verify processing chemical and rinse quality.
- O. The results of all radiographic interpretations shall be recorded on a signed certification and a copy kept with the film packet.
- P. Technique sheets prepared in conformance with the requirements in ASME Boiler and Pressure Vessels Code, Section V, Article 2 Section T-291 shall also contain the developer temperature, developing time, fixing duration and all rinse times.

52-1.08D Reporting Test Results

- A Production Test Report for all testing performed on each lot shall be prepared by the independent testing laboratory performing the testing and submitted to the QCM for review and approval. The report shall be signed by an engineer who represents the laboratory and is registered as a Civil Engineer in the State of California. The report shall include, as a minimum, the following information for each test: contract number, bridge number, lot number and location, bar size, type of splice, length of mechanical splice, length of test specimen, physical condition of test sample splice and any associated control bar, any notable defects, total measured slip, ultimate tensile strength of each splice, and for ultimate butt splices, limits of affected zone, location of visible necking area, ultimate tensile strength and 95 percent of this ultimate tensile strength for each control bar, and a comparison between 95 percent of the ultimate tensile strength of each control bar and the ultimate tensile strength of its associated splice.

- The QCM must review, approve, and forward each Production Test Report to the Engineer for review before the splices represented by the report are encased in concrete. The Engineer will have 3 working days to review each Production Test Report and respond in writing after a complete report has been received. Should the Contractor elect to encase any splices before receiving notification from the Engineer, it is expressly understood that the Contractor will not be relieved of the responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase splices pending notification by the Engineer, and in the event the Engineer fails to complete the review and provide notification within the time allowed, and if, in the opinion of the Engineer, the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

- Quality assurance test results for each bundle of 4 sets or 4 samples of splices will be reported in writing to the Contractor within 3 working days after receipt of the bundle by the Transportation Laboratory. In the event that more than one bundle is received on the same day, 2 additional working days shall be allowed for providing test results for each additional bundle received. A test report will be made for each bundle received. Should the Contractor elect to encase splices before receiving notification from the Engineer, it is expressly understood that the Contractor will not be relieved of the responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase splices pending notification by the Engineer, and in the event the Engineer fails to complete the review within the time allowed, and in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

Section 52-1.11, "Payment," of the Standard Specifications is amended by adding the following paragraph after the seventh paragraph:

- If a portion or all of the reinforcing steel is epoxy-coated more than 480 air line kilometers from both Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impracticable and extremely difficult to ascertain and determine the actual increase in these expenses, it is agreed that payment to the Contractor for furnishing the epoxy-coated reinforcement will be reduced \$5000 for each epoxy-coating facility located more than 480 air line kilometers from both Sacramento and Los Angeles and an additional \$3000 (\$8000 total) for each epoxy-coating facility located more than 4800 air line kilometers from both Sacramento and Los Angeles.

SECTION 53: SHOTCRETE

Issue Date: November 2, 2007

The third paragraph in Section 53-1.01, "Description," of the Standard Specifications is amended to read:

- The dry-mix process shall consist of delivering dry mixed aggregate and cementitious material pneumatically or mechanically to the nozzle body and adding water and mixing the materials in the nozzle body. The wet-mix process shall consist of delivering mixed aggregate, cement, and water pneumatically to the nozzle and adding any admixture at the nozzle.

The first through fourth paragraphs in Section 53-1.02, "Materials," of the Standard Specifications is amended to read:

- Cementitious material, fine aggregate, and mixing water shall conform to the provisions in Section 90, "Portland Cement Concrete."
- Shotcrete to be mixed and applied by the dry-mix process shall consist of one part cementitious material to not more than 4.5 parts fine aggregate, thoroughly mixed in a dry state before being charged into the machine. Measurement may be either by volume or by mass. The fine aggregate shall contain not more than 6 percent moisture by mass.
- Shotcrete to be mixed and applied by the wet-mix process shall consist of cementitious material, fine aggregate, and water and shall contain not less than 375 kilograms of cementitious material per cubic meter. A maximum of 30 percent pea gravel may be substituted for fine aggregate. The maximum size of pea gravel shall be such that 100 percent passes the 12.5 mm screen and at least 90 percent passes the 9.5 mm screen.
- Admixtures may be added to shotcrete and shall conform to the provisions in Section 90-4, "Admixtures."

The third subparagraph of the third paragraph in Section 53-1.04, "Placing Shotcrete," of the Standard Specifications is amended to read:

Aggregate and cementitious material that have been mixed for more than 45 minutes shall not be used unless otherwise permitted by the Engineer.

Section 53-1.07, "Measurement," of the Standard Specifications is amended to read:

- Quantities of shotcrete will be measured by the cubic meter computed from measurements, along the slope, of actual areas placed and the theoretical thickness shown on the plans. The Department does not pay for shotcrete placed outside the dimensions shown on the plans or to fill low foundation.

Section 53-1.08, "Payment," of the Standard Specifications is amended to read:

- The contract price paid per cubic meter for shotcrete shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in placing shotcrete, including preparing the foundation, wire reinforcement, structure backfill, joint filling material, and if required by the plans, drains with sacked pervious backfill material, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

SECTION 55: STEEL STRUCTURES

Issue Date: January 5, 2007

The third and fourth paragraphs of Section 55-1.01, "Description," of the Standard Specifications are amended to read:

- Details of connections for highway bridges selected for use by the Contractor shall conform to the AASHTO LRFD Bridge Design Specifications with Caltrans Amendments.
- Details of design selected by the Contractor, fabrication and workmanship, for steel railway bridges shall conform to the requirements of the Specifications for Steel Railway Bridges, for Fixed Spans Not Exceeding 400 Feet in Length of the AREMA, as set forth in the special provisions.

The third paragraph of Section 55-1.05, "Falsework," of the Standard Specifications is amended to read:

- Construction methods and equipment employed by the Contractor shall conform to the provisions in Section 7-1.02, "Load Limitations." Loads imposed on existing, new or partially completed structures shall not exceed the load carrying capacity of the structure, or portion of structure, as determined by the AASHTO LRFD Bridge Design Specifications with Caltrans Amendments.

The fourth and fifth paragraphs of Section 55-2.01, "Description," of the Standard Specifications are amended to read:

- All structural steel plate used for the fabrication of tension members, tension flanges, eyebars and hanger plates and for splice plates of tension members, tension flanges and eyebars shall meet the longitudinal Charpy V-notch impact value requirements specified herein. Sampling procedures shall conform to the requirements in ASTM Designation: A 673. The H (Heat) frequency of testing shall be used for structural steels conforming to the requirements in ASTM Designations: A 709/A 709M, Grades 36 [250], 50 [345], 50W [345W], and HPS 50W [345W]. The P (Piece) frequency of testing shall be used for structural steel conforming to the requirements in ASTM Designation: A 709/A 709M, Grades HPS 70W [485W], 100 [690], and 100W [690W]. Charpy V-notch impact values shall be determined in conformance with the requirements in ASTM Designation: E 23.

- Charpy V-notch (CVN) impact values shall conform to the following minimum values for non fracture critical members:

Material Conforming to ASTM Designation: A 709/A 709M	CVN Impact Value (Joules at Temp.)
Grade 36 [250]	20 at 4°C
Grade 50 [345]* (50 mm and under in thickness)	20 at 4°C
Grade 50W [345W]* (50 mm and under in thickness)	20 at 4°C
Grade 50 [345]* (Over 50 mm to 100 mm in thickness)	27 at 4°C
Grade 50W [345W]* (Over 50 mm to 100 mm in thickness)	27 at 4°C
Grade HPS 50W [345W]* (100 mm and under in thickness)	27 at -12°C
Grade HPS 70W [485]* (100 mm and under in thickness)	34 at -23°C
Grade 100 [490] (65 mm and under in thickness)	34 at -18°C
Grade 100W [490W] (Over 65 mm to 100 mm in thickness)	48 at -18°C

* If the yield point of the material exceeds 450 MPa, the temperature for the CVN impact value for acceptability shall be reduced 8°C for each increment of 70 MPa above 450 MPa.

Structural Steel Materials

Material	Specification
Structural steel:	
Carbon steel	ASTM: A 709/A 709M, Grade 36 [250] or {A 36/A 36M}a
High strength low alloy columbium vanadium steel	ASTM: A 709/A 709M, Grade 50 [345] or {A 572/A 572M, Grade 50 [345]}a
High strength low alloy structural steel	ASTM: A 709/A 709M, Grade 50W [345W], Grade HPS 50W [HSP 345W], or {A 588/A 588M}a
High strength low alloy structural steel plate	ASTM: A 709/A 709M, Grade HPS 70W [HPS 485W]
High-yield strength, quenched and tempered alloy steel plate suitable for welding	ASTM: A 709/A 709M, Grade 100 [690] and Grade 100W [690W], or {A 514/A 514M}a
Steel fastener components for general applications:	
Bolts and studs	ASTM: A 307
Headed anchor bolts	ASTM: A 307, Grade B, including S1 supplementary requirements
Nonheaded anchor bolts	ASTM: A 307, Grade C, including S1 supplementary requirements and S1.6 of AASHTO: M 314 supplementary requirements or AASHTO: M 314, Grade 36 or 55, including S1 supplementary requirements
High-strength bolts and studs	ASTM: A 449, Type 1
High-strength threaded rods	ASTM: A 449, Type 1
High-strength nonheaded anchor bolts	ASTM: A 449, Type 1
Nuts	ASTM: A 563, including Appendix X1b
Washers	ASTM: F 844

Components of high-strength steel fastener assemblies for use in structural steel joints:	
Bolts	ASTM: A 325, Type 1
Tension control bolts	ASTM: F 1852, Type 1
Nuts	ASTM: A 563, including Appendix X1b
Hardened washers	ASTM : F 436, Type 1, Circular, including S1 supplementary requirements
Direct tension indicators	ASTM: F 959, Type 325, zinc-coated
Carbon steel for forgings, pins and rollers	ASTM: A 668/A 668M, Class D
Alloy steel for forgings	ASTM: A 668/A 668M, Class G
Pin nuts	ASTM: A 36/A 36M
Carbon-steel castings	ASTM: A 27/A 27M, Grade 65-35, Class 1
Malleable iron castings	ASTM: A 47, Grade 32510 or A 47M, Grade 22010
Gray iron castings	ASTM: A 48, Class 30B
Carbon steel structural tubing	ASTM: A 500, Grade B or A 501
Steel pipe (Hydrostatic testing will not apply)	ASTM: A 53, Type E or S, Grade B; A 106, Grade B; or A 139, Grade B
Stud connectors	ASTM: A 108 and AASHTO/AWS D1.5

- a Grades that may be substituted for the equivalent ASTM Designation: A 709 steel, at the Contractor's option, subject to the modifications and additions specified and to the requirements of A 709.
- b Zinc-coated nuts that will be tightened beyond snug or wrench tight shall be furnished with a dry lubricant conforming to Supplementary Requirement S2 in ASTM Designation: A 563.

The first sentence of the first paragraph of Section 55-2.02, "Structural Steel," of the Standard Specifications is amended to read:

- Unless otherwise specified or shown on the plans, all structural steel plates, shapes, and bars shall conform to ASTM Designation: A 709/A 709M, Grade 50 [345].

The first paragraph in Section 55-3.05, "Flatness of Faying and Bearing Surfaces," of the Standard Specifications is amended to read:

- Surfaces of bearing and base plates and other metal surfaces that are to come in contact with each other or with ground concrete surfaces or with asbestos sheet packing shall be flat to within one mm tolerance in 305 mm and to within 2 mm tolerance overall. Surfaces of bearing and base plates and other metal bearing surfaces that are to come in contact with preformed fabric pads, elastomeric bearing pads, or mortar shall be flat to within 3 mm tolerance in 305 mm and to within 5 mm tolerance overall.

Section 55-3.14, "Bolted Connections," of the Standard Specifications is amended by adding the following after the ninth paragraph:

- If a torque multiplier is used in conjunction with a calibrated wrench as a method for tightening fastener assemblies to the required tension, both the multiplier and the wrench shall be calibrated together as a system. The same length input and output sockets and extensions that will be used in the work shall also be included in the calibration of the system. The manufacturer's torque multiplication ratio shall be adjusted during calibration of the system, such that when this adjusted ratio is multiplied by the actual input calibrated wrench reading, the product is a calculated output torque that is within 2 percent of the true output torque. When this system is used in the work to perform any installation tension testing, rotational capacity testing, fastener tightening, or tension verification, it shall be used, intact as calibrated.

The second paragraph of Section 55-3.17, "Welding," of the Standard Specifications is amended to read:

- The minimum size of all fillet welds, except those to reinforce groove welds, shall be as shown in the following table:

Base Metal Thickness of the Thicker Part Joined (Millimeters)	*Minimum Size of Fillet Weld (Millimeters)
To 19 inclusive	6
Over 19	8

* Except that the weld size need not exceed the thickness of the thinner part joined.

The third paragraph in Section 55-3.19, "Bearings and Anchorages," of the Standard Specifications is amended to read:

- Immediately before setting bearing assemblies or masonry plates directly on ground concrete surfaces, the Contractor shall thoroughly clean the surfaces of the concrete and the metal to be in contact and shall apply a coating of nonsag polysulfide or polyurethane caulking conforming to the requirements in ASTM Designation: C 920 to contact areas to provide full bedding.

The fifth paragraph in Section 55-3.19, "Bearings and Anchorages," of the Standard Specifications is amended to read:

- Mortar to be placed below masonry plates or bearing plates of the bearing assemblies and in anchor bolt sleeves or canisters shall conform to the provisions in Section 51-1.135, "Mortar," except that the proportion of cementitious material to sand shall be 1:3.

The sixth paragraph of Section 55-4.02, "Payment," of the Standard Specifications is amended to read:

- If a portion or all of the structural steel is fabricated more than 480 air line kilometers from both Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impracticable and extremely difficult to ascertain and determine the actual increase in these expenses, it is agreed that payment to the Contractor for furnishing the structural steel from each fabrication site located more than 480 air line kilometers from both Sacramento and Los Angeles will be reduced \$5000 or by an amount computed at \$0.044 per kilogram of structural steel fabricated, whichever is greater, or in the case of each fabrication site located more than 4800 air line kilometers from both Sacramento and Los Angeles, payment will be reduced \$8000 or by \$0.079 per kilogram of structural steel fabricated, whichever is greater.

SECTION 56: SIGNS

Issue Date: March 16, 2007

Section 56-1.01, "Description," of the Standard Specifications is amended by deleting the third paragraph.

Section 56-1.02A, "Bars, Plates and Shapes," of the Standard Specifications is amended to read:

56-1.02A Bars, Plates, Shapes, and Structural Tubing

- Bars, plates, and shapes shall be structural steel conforming to the requirements in ASTM Designation: A 36/A 36M, except, at the option of the Contractor, the light fixture mounting channel shall be continuous-slot steel channel conforming to the requirements in ASTM Designation: A 1011/A 1011M, Designation SS, Grade 33[230], or aluminum Alloy 6063-T6 extruded aluminum conforming to the requirements in ASTM Designation: B 221 or B 221M.
- Structural tubing shall be structural steel conforming to the requirements in ASTM Designation: A 500, Grade B.
- Removable sign panel frames shall be constructed of structural steel conforming to the requirements in ASTM Designation: A 36/A 36M.

Section 56-1.02B, "Sheets," of the Standard Specifications is amended to read:

56-1.02B Sheets

- Sheets shall be carbon-steel sheets conforming to the requirements in ASTM Designation: A 1011/A 1011M, Designation SS, Grade 33[230].

- Ribbed sheet metal for box beam-closed truss sign structures shall be fabricated from galvanized sheet steel conforming to the requirements in ASTM Designation: A 653/A 653M, Designation SS, Grade 33[230]. Sheet metal panels shall be G 165 coating designation in conformance with the requirements in ASTM Designation: A 653/A 653M.

Section 56-1.02F, "Steel Walkway Gratings," of the Standard Specifications is amended to read:

56-1.02F Steel Walkway Gratings

- Steel walkway gratings shall be furnished and installed in conformance with the details shown on the plans and the following provisions:
 - A. Gratings shall be the standard product of an established grating manufacturer.
 - B. Material for gratings shall be structural steel conforming to the requirements in ASTM Designation: A 1011/A 1011M, Designation CS, Type B.
 - C. For welded type gratings, each joint shall be full resistance welded under pressure, to provide a sound, completely beaded joint.
 - D. For mechanically locked gratings, the method of fabrication and interlocking of the members shall be approved by the Engineer, and the fabricated grating shall be equal in strength to the welded type.
 - E. Gratings shall be accurately fabricated and free from warps, twists, or other defects affecting their appearance or serviceability. Ends of all rectangular panels shall be square. The tops of the bearing bars and cross members shall be in the same plane. Gratings distorted by the galvanizing process shall be straightened.

The fifth paragraph in Section 56-1.03, "Fabrication," of the Standard Specifications is amended to read:

- Clips, eyes, or removable brackets shall be affixed to all signs and all posts and shall be used to secure the sign during shipping and for lifting and moving during erection as necessary to prevent damage to the finished galvanized or painted surfaces. Brackets on tubular sign structures shall be removed after erection. Details of the devices shall be shown on the working drawings.

The sixth through the thirteenth paragraphs in Section 56-1.03, "Fabrication," of the Standard Specifications are amended to read:

- High-strength bolted connections, where shown on the plans, shall conform to the provisions in Section 55-3.14, "Bolted Connections," except that only fastener assemblies consisting of a high-strength bolt, nut, hardened washer, and direct tension indicator shall be used.
 - High-strength fastener assemblies, and any other bolts, nuts, and washers attached to sign structures shall be zinc-coated by the mechanical deposition process.
 - Nuts for high-strength bolts designated as snug-tight shall not be lubricated.
 - An alternating snugging and tensioning pattern for anchor bolts and high-strength bolted splices shall be used. Once tensioned, high-strength fastener components and direct tension indicators shall not be reused.
 - For bolt diameters less than 10 mm, the diameter of the bolt hole shall be not more than 0.80-mm larger than the nominal bolt diameter. For bolt diameters greater than or equal to 10 mm, the diameter of the bolt hole shall be not more than 1.6 mm larger than the nominal bolt diameter.
 - Sign structures shall be fabricated into the largest practical sections prior to galvanizing.
 - Ribbed sheet metal panels for box beam closed truss sign structures shall be fastened to the truss members by cap screws or bolts as shown on the plans, or by 4.76 mm stainless steel blind rivets conforming to Industrial Fasteners Institute, Standard IFI-114, Grade 51. The outside diameter of the large flange rivet head shall be not less than 15.88 mm in diameter. Web splices in ribbed sheet metal panels may be made with similar type blind rivets of a size suitable for the thickness of material being connected.
 - Spalling or chipping of concrete structures shall be repaired by the Contractor at the Contractor's expense.
 - Overhead sign supports shall have an aluminum identification plate permanently attached near the base, adjacent to the traffic side on one of the vertical posts, using either stainless steel rivets or stainless steel screws. As a minimum, the information on the plate shall include the name of the manufacturer, the date of manufacture and the contract number.

The fourth paragraph of Section 56-1.10, "Payment," of the Standard Specifications is amended to read:

- The contract price paid per kilogram for install sign structure of the type or types designated in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing sign structures, complete in place, including installing anchor bolt assemblies, removable sign panel frames, and sign panels and performing any welding, painting or galvanizing required during installation, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

The fifth paragraph of Section 56-2.02B, "Wood Posts," of the Standard Specifications is amended to read:

- Douglas fir and Hem-Fir posts shall be treated in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," and in conformance with AWPAs Use Category System: UC4A, Commodity Specification A. Posts shall be incised and the minimum retention of preservative shall be as specified in AWPAs Standards.

The fourth paragraph in Section 56-2.03, "Construction," of the Standard Specifications is amended to read:

- Backfill material for metal posts shall consist of minor concrete conforming to the provisions in Section 90-10, "Minor Concrete," and shall contain not less than 275 kilograms of cementitious material per cubic meter.

SECTION 57: TIMBER STRUCTURES

Issue Date: October 12, 2004

The second paragraph of Section 57-1.02A, "Structural Timber and Lumber," of the Standard Specifications is amended to read:

- When preservative treatment of timber and lumber is required, the treatment shall conform to the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," and AWPAs Use Category 4B. The type of treatment to be used will be shown on the plans or specified in the special provisions.

SECTION 58: PRESERVATIVE TREATMENT OF LUMBER, TIMBER AND PILING

Issue Date: November 18, 2005

The first paragraph of Section 58-1.02, "Treatment and Retention," of the Standard Specifications is amended to read:

- Timber, lumber, and piling shall be pressure treated after millwork is completed. Preservatives, treatment, and results of treatment shall conform to the requirements in AWPAs Standards U1 and T1. Treatment of lumber and timber shall conform to the specified AWPAs Use Category cited in the special provisions, on the plans, or elsewhere in these specifications.

The second paragraph of Section 58-1.02, "Treatment and Retention," of the Standard Specifications is deleted.

SECTION 59: PAINTING

Issue Date: January 19, 2007

The first paragraph of Section 59-1.02, "Weather Conditions," of the Standard Specifications is amended to read:

- Paint shall be applied only on thoroughly dry surfaces and during periods of favorable weather. Blast cleaning or application of solvent-borne paint will not be permitted when the atmospheric or surface temperature is at or below 2°C or above 38°C, or when the relative humidity exceeds 85 percent at the site of the work. Application of water-borne paint will not be permitted when the atmospheric or surface temperature is at or below 10°C, or above 38°C, or when the relative humidity exceeds 75 percent at the site of the work. Application of paint will not be permitted when the steel surface temperature is less than 3°C above the dew point, or when freshly painted surfaces may become damaged by rain, fog or condensation, or when it can be anticipated that the atmospheric temperature or relative humidity will not remain within the specified application conditions during the drying period, except as provided in the following paragraph for enclosures. If uncured paint is damaged by the elements, it shall be replaced or repaired by the Contractor at the Contractor's expense.

The second paragraph of Section 59-1.05, "Protection Against Damage," of the Standard Specifications is amended to read:

- Paint or paint stains on surfaces not designated to be painted shall be removed by the Contractor at the Contractor's expense and to the satisfaction of the Engineer.

Section 59-2.01, "General," of the Standard Specifications is amended by adding the following paragraphs after the first paragraph:

- Unless otherwise specified, no painting Contractors or subcontractors will be permitted to commence work without having the following current "SSPC: The Society for Protective Coatings" (formerly the Steel Structures Painting Council) certifications in good standing:
 - A. For cleaning and painting structural steel in the field, certification in conformance with the requirements in Qualification Procedure No. 1, "Standard Procedure For Evaluating Painting Contractors (Field Application to Complex Industrial Structures)" (SSPC-QP 1).
 - B. For removing paint from structural steel, certification in conformance with the requirements in Qualification Procedure No. 2, "Standard Procedure For Evaluating Painting Contractors (Field Removal of Hazardous Coatings from Complex Structures)" (SSPC-QP 2).
 - C. For cleaning and painting structural steel in a permanent painting facility, certification in conformance with the requirements in Qualification Procedure No. 3, "Standard Procedure For Evaluating Qualifications of Shop Painting Applicators" (SSPC-QP 3). The AISC's Sophisticated Paint Endorsement (SPE) quality program will be considered equivalent to SSPC-QP 3.

The third paragraph of Section 59-2.03, "Blast Cleaning," of the Standard Specifications is amended to read:

- Exposed steel or other metal surfaces to be blast cleaned shall be cleaned in conformance with the requirements in Surface Preparation Specification No. 6, "Commercial Blast Cleaning," of the "SSPC: The Society for Protective Coatings." Blast cleaning shall leave all surfaces with a dense, uniform, angular anchor pattern of not less than 35 μm as measured in conformance with the requirements in ASTM Designation: D 4417.

The first paragraph of Section 59-2.06, "Hand Cleaning," of the Standard Specifications is amended to read:

- Dirt, loose rust and mill scale, or paint which is not firmly bonded to the surfaces shall be removed in conformance with the requirements in Surface Preparation Specification No. 2, "Hand Tool Cleaning," of the "SSPC: The Society for Protective Coatings." Edges of old remaining paint shall be feathered.

The third and fourth paragraphs of Section 59-2.12, "Painting," of the Standard Specifications are amended to read:

- Contact surfaces of stiffeners, railings, built up members or open seam exceeding 6 mils in width that would retain moisture, shall be caulked with polysulfide or polyurethane sealing compound conforming to the requirements in ASTM Designation: C 920, Type S, Grade NS, Class 25, Use O, or other approved material.
 - The dry film thickness of the paint will be measured in place with a calibrated Type 2 magnetic film thickness gage in conformance with the requirements in SSPC-PA 2, "Measurement of Dry Coating Thickness with Magnetic Gages," of the "SSPC: The Society for Protective Coatings," except that there shall be no limit to the number or location of spot measurements to verify compliance with specified thickness requirements.

The third paragraph of Section 59-2.13, "Application of Zinc-Rich Primer," of the Standard Specifications is amended to read:

- Mechanical mixers shall be used in mixing the primer. After mixing, the zinc-rich primer shall be strained through a 0.6 to 0.25 mm screen or a double layer of cheesecloth immediately prior to or during pouring into the spray pot.

SECTION 64: PLASTIC PIPE

Issue Date: January 5, 2007

The first paragraph of Section 64-1.06, "Concrete Backfill," of the Standard Specifications is amended to read:

Contract No. 02-350904

- At locations where pipe is to be backfilled with concrete as shown on the plans, the concrete backfill shall be constructed of minor concrete or Class 4 concrete conforming to the provisions in Section 90, "Portland Cement Concrete." Minor concrete shall contain not less than 250 kg of cementitious material per cubic meter. The concrete to be used will be designated in the contract item or shown on the plans.

SECTION 65: REINFORCED CONCRETE PIPE

Issue Date: January 5, 2007

The first paragraph of Section 65-1.02, "Materials," of the Standard Specifications is amended to read:

- Cementitious material and aggregate shall conform to the provisions in Section 90-2, "Materials," except that mortar strengths relative to Ottawa sand and grading requirements shall not apply to the aggregate. Use of supplemental cementitious material shall conform to AASHTO Designation: M 170M.

Subparagraph "c" of the eleventh paragraph of Section 65-1.02A(1) "Circular Reinforced Concrete Pipe (Designated or Selected by Class)," of the Standard Specifications is amended to read:

- c. Cementitious material and aggregate for non-reinforced concrete pipe shall conform to the provisions in Section 65-1.02, "Materials."

The first paragraph of Section 65-1.035, "Concrete Backfill," of the Standard Specifications is amended to read:

- At locations where pipe is to be backfilled with concrete as shown on the plans, the concrete backfill shall be constructed of minor concrete or Class 4 concrete in conformance with the provisions in Section 90, "Portland Cement Concrete." Minor concrete shall contain not less than 225 kg of cementitious material per cubic meter. The concrete to be used will be designated in the contract item.

The first subparagraph of the second paragraph of Section 65-1.06, "Joints," of the Standard Specifications is amended to read:

- Cement Mortar.- Mortar shall be composed of one part cementitious material and 2 parts sand by volume. Supplementary cementitious material will not be required.

SECTION 66: CORRUGATED METAL PIPE

Issue Date: January 5, 2007

The first paragraph of Section 66-1.045, "Concrete Backfill," of the Standard Specifications is amended to read:

- At locations where pipe is to be backfilled with concrete as shown on the plans, the concrete backfill shall be constructed of minor concrete or Class 4 concrete conforming to the provisions in Section 90, "Portland Cement Concrete." Minor concrete shall contain not less than 225 kg of cementitious material per cubic meter. The concrete to be used will be designated in the contract item or shown on the plans.

SECTION 68: SUBSURFACE DRAINS

Issue Date: January 5, 2007

The first and second paragraphs of Section 68-3.02D, "Miscellaneous," of the Standard Specifications are amended to read:

- Concrete for splash pads shall be produced from minor concrete conforming to the provisions in Section 90-10, "Minor Concrete." Minor concrete shall contain not less than 275 kg of cementitious material per cubic meter.
- Mortar placed where edge drain outlets and vents connect to drainage pipe and existing drainage inlets shall conform to the provisions in Section 51-1.135, "Mortar."

SECTION 70: MISCELLANEOUS FACILITIES

Issue Date: January 5, 2007

The second paragraph of Section 70-1.02C, "Flared End Sections," of the Standard Specifications is amended to read:

- Precast concrete flared end sections shall conform to the requirements for Class III Reinforced Concrete Pipe in AASHTO Designation: M 170M. Cementitious materials and aggregate shall conform to the provisions in Section 90-2, "Materials," except that mortar strengths relative to Ottawa sand and grading requirements shall not apply to the aggregate. Use of supplementary cementitious material shall conform to the requirements in AASHTO Designation: M 170M. The area of steel reinforcement per meter of flared end section shall be at least equal to the minimum steel requirements for circular reinforcement in circular pipe for the internal diameter of the circular portion of the flared end section. The basis of acceptance of the precast concrete flared end section shall conform to the requirements of Section 5.1.2 of AASHTO Designation: M 170M.

The first paragraph of Section 70-1.02H, "Precast Concrete Structures," of the Standard Specifications is amended to read:

- Precast concrete pipe risers and pipe reducers, and precast concrete pipe sections, adjustment rings and tapered sections for pipe energy dissipators, pipe inlets and pipe manholes shall conform to the requirements in AASHTO Designation: M 199M, except that the cementitious material and aggregate shall conform to the provisions in Section 90-2, "Materials," except that mortar strengths relative to Ottawa sand and grading requirements shall not apply to the aggregate. Use of supplementary cementitious material shall conform to the requirements in AASHTO Designation: M 170M.

The second paragraph of Section 70-1.03, "Installation," of the Standard Specifications is amended to read:

- Cutoff walls for precast concrete flared end sections shall be constructed of minor concrete conforming to the provisions in Section 90-10, "Minor Concrete." Minor concrete shall contain not less than 275 kg of cementitious material per cubic meter.

SECTION 72: SLOPE PROTECTION

Issue Date: November 18, 2005

The sixth paragraph of Section 72-4.04, "Construction," of the Standard Specifications is amended to read:

- Pervious backfill material, if required by the plans, shall be placed as shown. A securely tied sack containing 0.03-m³ of pervious backfill material shall be placed at each weep hole and drain hole. The sack material shall conform to the provisions in Section 88-1.03, "Filter Fabric."

SECTION 73: CONCRETE CURBS AND SIDEWALKS

Issue Date: January 5, 2007

The second subparagraph of the second paragraph of Section 73-1.01, "Description," of the Standard Specifications is amended to read:

2. Minor concrete shall contain not less than 275 kg of cementitious material per cubic meter except that when extruded or slip-formed curbs are constructed using 9.5-mm maximum size aggregate, minor concrete shall contain not less than 325 kg of cementitious material per cubic meter.

SECTION 75: MISCELLANEOUS METAL

Issue Date: August 17, 2007

The table in the tenth paragraph of Section 75-1.02, "Miscellaneous Iron and Steel," of the Standard Specifications is amended to read:

Material	Specification
Steel bars, plates and shapes	ASTM Designation: A 36/A 36M or A 575, A 576 (AISI or M Grades 1016 through 1030)
Steel fastener components for general applications:	
Bolts and studs	ASTM Designation: A 307
Headed anchor bolts	ASTM Designation: A 307, Grade B, including S1 supplementary requirements
Nonheaded anchor bolts	ASTM Designation: A 307, Grade C, including S1 supplementary requirements and S1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements
High-strength bolts and studs, threaded rods, and nonheaded anchor bolts	ASTM Designation: A 449, Type 1
Nuts	ASTM Designation: A 563, including Appendix X1*
Washers	ASTM Designation: F 844
Components of high-strength steel fastener assemblies for use in structural steel joints:	
Bolts	ASTM Designation: A 325, Type 1
Tension control bolts	ASTM Designation: F 1852, Type 1
Nuts	ASTM Designation: A 563, including Appendix X1*
Hardened washers	ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements
Direct tension indicators	ASTM Designation: F 959, Type 325, zinc-coated
Stainless steel fasteners (Alloys 304 & 316) for general applications:	
Bolts, screws, studs, threaded rods, and nonheaded anchor bolts	ASTM Designation: F 593 or F 738M
Nuts	ASTM Designation: F 594 or F 836M
Washers	ASTM Designation: A 240/A 240M and ANSI B 18.22M
Carbon-steel castings	ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1
Malleable iron castings	ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010
Gray iron castings	ASTM Designation: A 48, Class 30B
Ductile iron castings	ASTM Designation: A 536, Grade 65-45-12
Cast iron pipe	Commercial quality
Steel pipe	Commercial quality, welded or extruded
Other parts for general Applications	Commercial quality

* Zinc-coated nuts that will be tightened beyond snug or wrench tight shall be furnished with a dyed dry lubricant conforming to Supplementary Requirement S2 in ASTM Designation: A 563.

The second paragraph in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

- Miscellaneous bridge metal shall consist of the following, except as further provided in Section 51-1.19, "Utility Facilities," and in the special provisions:
 - A. Bearing assemblies, equalizing bolts and expansion joint armor in concrete structures.
 - B. Expansion joint armor in steel structures.
 - C. Manhole frames and covers, frames and grates, ladder rungs, guard posts and access door assemblies.
 - D. Deck drains, area drains, retaining wall drains, and drainage piping, except drainage items identified as "Bridge Deck Drainage System" in the special provisions.

The seventh paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

- Sheet steel for access doors shall be galvanized sheet conforming to the requirements in ASTM Designation: A 653/A 653M, Coating Designation Z600 {G210}.

The table in the eighteenth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Stud Diameter (millimeters)	Sustained Tension Test Load (kilonewtons)
29.01-33.00	137.9
23.01-29.00	79.6
21.01-23.00	64.1
* 18.01-21.00	22.2
15.01-18.00	18.2
12.01-15.00	14.2
9.01-12.00	9.34
6.00-9.00	4.23

* Maximum stud diameter permitted for mechanical expansion anchors.

The table in the nineteenth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Stud Diameter (millimeters)	Ultimate Tensile Load (kilonewtons)
30.01-33.00	112.1
27.01-30.00	88.1
23.01-27.00	71.2
20.01-23.00	51.6
16.01-20.00	32.0
14.01-16.00	29.4
12.00-14.00	18.7

The table in the twenty-second paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Installation Torque Values, (newton meters)

Stud Diameter (millimeters)	Shell Type Mechanical Expansion Anchors	Integral Stud Type Mechanical Expansion Anchors	Resin Capsule Anchors and Cast-in-Place Inserts
29.01-33.00	—	—	540
23.01-29.00	—	—	315
21.01-23.00	—	—	235
18.01-21.00	110	235	200
15.01-18.00	45	120	100
12.01-15.00	30	65	40
9.01-12.00	15	35	24
6.00-9.00	5	10	—

The twenty-fourth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

- Sealing compound, for caulking and adhesive sealing, shall be a polysulfide or polyurethane material conforming to the requirements in ASTM Designation: C 920, Type S, Grade NS, Class 25, Use O.

The third paragraph in Section 75-1.035, "Bridge Joint Restrainer Units," of the Standard Specifications is amended to read:

- Cables shall be 19 mm preformed, 6 x 19, wire strand core or independent wire rope core (IWRC), galvanized in conformance with the requirements in Federal Specification RR-W-410, right regular lay, manufactured of improved plow steel with a minimum breaking strength of 200 kN. Two certified copies of mill test reports of each manufactured length of cable used shall be furnished to the Engineer.

The twelfth paragraph in Section 75-1.035, "Bridge Joint Restrainer Units," of the Standard Specifications is amended to read:

- Concrete for filling cable drum units shall conform to the provisions in Section 90-10, "Minor Concrete," or at the option of the Contractor, may be a mix with 9.5 mm maximum size aggregate and not less than 400 kilograms of cementitious material per cubic meter.

The second paragraph in Section 75-1.05, "Galvanizing," of the Standard Specifications is amended to read:

- At the option of the Contractor, material thinner than 3.2 mm shall be galvanized either before fabrication in conformance with the requirements of ASTM Designation: A 653/A 653M, Coating Designation Z600, or after fabrication in conformance with the requirements of ASTM Designation: A 123, except that the weight of zinc coating shall average not less than 365 g per square meter of actual surface area with no individual specimen having a coating weight of less than 305 g per square meter.

SECTION 80: FENCES

Issue Date: January 5, 2007

The second paragraph of Section 80-3.01B(2), "Treated Wood Posts and Braces," of the Standard Specifications is amended to read:

- Posts and braces to be treated shall be pressure treated in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," and AWPA Use Category System: UC4A, Commodity Specification A or B.

The fourth paragraph of Section 80-3.01F, "Miscellaneous," of the Standard Specifications is amended to read:

- Portland cement concrete for metal post and brace footings and for deadmen shall be minor concrete conforming to the provisions in Section 90-10, "Minor Concrete." Minor concrete shall contain not less than 275 kg of cementitious material per cubic meter.

The fourth paragraph of Section 80-4.01C, "Miscellaneous," of the Standard Specifications is amended to read:

- Portland cement concrete for metal post and for deadmen shall be produced from minor concrete conforming to the provisions in Section 90-10, "Minor Concrete." Minor concrete shall contain not less than 275 kg of cementitious material per cubic meter.

SECTION 81: MONUMENTS

Issue Date: June 30, 2006

The fifth paragraph of Section 81-1.02, "Materials," of the Standard Specifications is amended to read:

- At the option of the Contractor, the frame and cover for Type B and Type D survey monuments shall be fabricated from either cast steel or gray cast iron. The covers shall fit into the frames without rocking.

The seventh paragraph of Section 81-1.02, "Materials," of the Standard Specifications is amended to read:

- Granular material for Type B and Type D survey monuments shall be gravel, crushed gravel, crushed rock or any combination thereof. Granular material shall not exceed 37.5 mm in greatest dimension.

SECTION 82: MARKERS AND DELINEATORS

Issue Date: June 30, 2006

The first paragraph of Section 82-1.02B, "Metal Posts," of the Standard Specifications is amended to read:

- Steel for metal posts shall conform to the requirements in ASTM Designation: A 36/A 36M. The posts shall be galvanized in conformance with the requirements in Section 75-1.05, "Galvanizing."

The third paragraph of Section 82-1.02D, "Target Plates," of the Standard Specifications is amended to read:

- The zinc-coated steel sheet shall conform to the requirements in ASTM Designation: A 653/A 653M, Classification: Commercial Steel (CS Types A, B and C). The steel sheets shall be galvanized in conformance with the requirements in Section 75-1.05, "Galvanizing." The zinc-coated surface shall be prepared for painting in a manner designed to produce optimum paint adherence. The surface preparation shall be accomplished without damaging or removing the zinc coating. Any evidence of damage or removal of the zinc coating shall be cause for rejection of the entire lot.

The eleventh paragraph of Section 82-1.02D, "Target Plates," of the Standard Specifications is amended to read:

- When tested in conformance with the requirements in California Test 671, the painted metal target plates shall, in general, have satisfactory resistance to weathering, humidity, salt spray and chemicals; the enamel coating shall have satisfactory adherence and impact resistance, a pencil lead hardness of HB minimum, 60° specular gloss of 80 percent minimum, an excitation purity of 3 percent maximum as received and after 1000 hours in an artificial weathering device in conformance with the requirements in ASTM Designation: G 155, Table X3.1, Cycle 1, and a daylight luminous directional reflectance ("Y" value) of 70 minimum.

The second paragraph of Section 82-1.02F, "Reflectors," of the Standard Specifications is amended to read:

- Reflectors for flexible target plates on Type K object markers and target plates on Class 2 delineators, and reflectors for Class 1 delineators shall be made from impact resistant retroreflective sheeting as specified in the special provisions. The color of the retroreflective sheeting shall conform to the color designated on the plans and the Chromaticity Coordinates specified in ASTM Designation: D 4956, or the PR color number specified by the Federal Highway Administration's Color Tolerance Chart.

The fourth paragraph of Section 82-1.02F, "Reflectors," of the Standard Specifications is amended to read:

The instrumental method of determining color shall conform to the requirements specified in ASTM Designation: D 4956. In the event of any dispute concerning the test results of instrumental testing, the visual test shall prevail.

SECTION 83: RAILINGS AND BARRIERS

Issue Date: August 17, 2007

The seventh paragraph in Section 83-1.02, "Materials and Construction," of the Standard Specifications is amended to read:

- Mortar shall conform to the provisions in Section 51-1.135, "Mortar," and shall consist of one part by volume of cementitious material and 3 parts of clean sand.

The first paragraph of Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications is amended to read:

- The rail elements, backup plates, terminal sections, end and return caps, bolts, nuts and other fittings shall conform to the requirements in AASHTO Designation: M 180, except as modified in this Section 83-1.02B and as specified in Section 83-1.02. The rail elements, backup plates, terminal sections, end and return caps shall conform to Class A, Type 1 W-Beam guard railing as shown in AASHTO Designation: M 180. The edges and center of the rail element shall contact each post block. Rail element joints shall be lapped not less than 316 mm and bolted. The rail metal, in addition to conforming to the requirements in AASHTO Designation: M 180, shall withstand a cold bend, without cracking, of 180 degrees around a mandrel of a diameter equal to 2.5 times the thickness of the plate.

The ninth paragraph in Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications is amended to read:

- The grades and species of wood posts and blocks shall be No. 1 timbers (also known as No. 1 structural) Douglas fir or No. 1 timbers Southern yellow pine. Wood posts and blocks shall be graded in conformance with the provisions in Section 57-2, "Structural Timber," of the Standard Specifications, except allowances for shrinkage after mill cutting shall in no case exceed 5 percent of the American Lumber Standards minimum sizes, at the time of installation.

The eleventh paragraph in Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications is amended to read:

- After fabrication, wood posts and blocks shall be pressure treated in conformance with Section 58, "Preservative Treatment of Lumber, Timber and Piling," and AWPA Use Category System: UC4A, Commodity Specification A.

The twelfth paragraph in Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications is amended to read:

- If copper naphthenate, ammoniacal copper arsenate, chromated copper arsenate, ammoniacal copper zinc arsenate, ammoniacal copper quat or copper azole is used to treat the wood posts and blocks, the bolt holes shall be treated as follows:

- A. Before the bolts are inserted, bolt holes shall be filled with a grease, recommended by the manufacturer for corrosion protection, which will not melt or run at a temperature of 65°C.

The 24th paragraph of Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications is amended to read:

- End anchor assemblies and rail tensioning assemblies for metal beam guard railing shall be constructed as shown on the plans and shall conform to the following provisions:

1. An end anchor assembly (Type SFT) for metal beam guard railing shall consist of an anchor cable, an anchor plate, a wood post, a steel foundation tube, a steel soil plate and hardware.
2. An end anchor assembly (Type CA) for metal beam guard railing shall consist of an anchor cable, an anchor plate, a single anchor rod or double anchor rods, hardware and one concrete anchor.
3. A rail tensioning assembly for metal beam guard railing shall consist of an anchor cable, an anchor plate, and hardware.
4. The anchor plate, metal plates, steel foundation tubes and steel soil plate shall be fabricated of steel conforming to the requirements in ASTM Designation: A 36/A 36M.
5. The anchor rods shall be fabricated of steel conforming to the requirements in ASTM Designation: A 36/A 36M, A 441 or A 572, or ASTM Designation: A 576, Grades 1018, 1019, 1021 or 1026. The eyes shall be hot forged or formed with full penetration welds. After fabrication, anchor rods with eyes that have been formed with any part of the eye below 870°C during the forming operation or with eyes that have been closed by welding shall be thermally stress relieved prior to galvanizing. The completed anchor rod, after galvanizing, shall develop a strength of 220 kN.
6. In lieu of built-up fabrication of anchor plates as shown on the plans, anchor plates may be press-formed from steel plate, with or without welded seams.
7. All bolts and nuts shall conform to the requirements in ASTM Designation: A 307, unless otherwise specified in the special provisions or shown on the plans.
8. Anchor cable shall be 19 mm preformed, 6 x 19, wire strand core or independent wire rope core (IWRC), galvanized in conformance with the requirements in Federal Specification RR-W-410, right regular lay, manufactured of improved plow steel with a minimum breaking strength of 200 kN. Two certified copies of mill test reports of each manufactured length of cable used shall be furnished to the Engineer. The overall length of each cable anchor assembly shall be as shown on the plans, but shall be a minimum of 2 m.
9. Where shown on the plans, cable clips and a cable thimble shall be used to attach cable to the anchor rod. Thimbles shall be commercial quality, galvanized steel. Cable clips shall be commercial quality drop forged galvanized steel.
10. The swaged fitting shall be machined from hot-rolled bars of steel conforming to AISI Designation: C 1035, and shall be annealed suitable for cold swaging. The swaged fitting shall be galvanized before swaging. A lock pin hole to accommodate a 6 mm, plated, spring steel pin shall be drilled through the head of the swage fitting to retain the stud in proper position. The manufacturer's identifying mark shall be stamped on the body of the swage fitting.
11. The 25 mm nominal diameter stud shall conform to the requirements in ASTM Designation: A 449 after galvanizing. Prior to galvanizing, a 10 mm slot for the locking pin shall be milled in the stud end.
12. The swaged fittings, stud and nut assembly shall develop the specified breaking strength of the cable.
13. The cable assemblies shall be shipped as a complete unit including stud and nut.
14. Clevises shall be drop forged galvanized steel and shall develop the specified breaking strength of the cable.
15. One sample of cable properly fitted with swaged fitting and right hand thread stud at both ends as specified above, including a clevis when shown on the plans, one meter in total length, shall be furnished the Engineer for testing.
16. The portion of the anchor rod to be buried in earth shall be coated with a minimum 0.5 mm thickness of coal tar enamel conforming to AWWA Standard: C203 or a coal tar epoxy conforming to the requirements in Steel Structures Painting Council Paint Specification No. 16, Coal-Tar Epoxy-Polyimide Black Paint or Corps of Engineers Specification, Formula C-200a, Coal-Tar Epoxy Paint.
17. Metal components of the anchor assembly shall be fabricated in conformance with good shop practice and shall be hot-dip galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing."
18. Anchor cables shall be tightened after the concrete anchor has cured for at least 5 days.
19. Concrete used to construct anchors for end anchor assemblies shall be Class 3 or minor concrete conforming to the provisions in Section 90, "Portland Cement Concrete."
20. Concrete shall be placed against undisturbed material of the excavated holes for end anchors. The top 300 mm of holes shall be formed, if required by the Engineer.
21. Reinforcing steel in concrete anchors for end anchor assemblies shall conform to the provisions in Section 52, "Reinforcement."

The second paragraph in Section 83-1.02D, "Steel Bridge Railing," of the Standard Specifications is amended to read:

- Structural shapes, tubing, plates, bars, bolts, nuts, and washers shall be structural steel conforming to the provisions in Section 55-2, "Materials." Other fittings shall be commercial quality.

The second and third paragraphs in Section 83-1.02E, "Cable Railing," of the Standard Specifications are replaced with the following paragraph:

- Pipe for posts and braces shall be standard steel pipe or pipe that conforms to the provisions in Section 80-4.01A, "Posts and Braces."

The 2nd sentence of the 7th paragraph of Section 83-1.02E, "Cable Railing," of the Standard Specifications is amended to read:

Cable shall be galvanized in conformance with the requirements in Federal Specification RR-W-410.

The 5th paragraph of Section 83-1.02I, "Chain Link Railing," of the Standard Specifications is amended to read:

Where shown on the plans, cables used in the frame shall be 8 mm in diameter, wire rope, with a minimum breaking strength of 22 kN and shall be galvanized in conformance with the requirements in Federal Specification RR-W-410.

The 14th paragraph of Section 83-1.02I, "Chain Link Railing," of the Standard Specifications is amended to read:

Chain link fabric shall be either 11-gage Type I zinc-coated fabric conforming to the requirements in AASHTO M 181 or 11-gage Type IV polyvinyl chloride (PVC) coated fabric conforming to the requirements in Federal Specification RR-F-191/1.

The second paragraph of Section 83-1.03, "Measurement," of the Standard Specifications is amended to read:

- Except for metal beam guard railing within the pay limits of a terminal system end treatment or transition railing (Type WB), metal beam guard railing will be measured by the meter along the face of the rail element from end post to end post of the completed railing at each installation. The point of measurement at each end post will be the center of the bolt attaching the rail element to the end post.

The seventh paragraph of Section 83-1.03, "Measurement," of the Standard Specifications is amended to read:

- The quantities of end anchor assemblies (Type SFT or Type CA) and rail tensioning assemblies will be measured as units determined from actual count. An end anchor assembly (Type CA) with 2 cables attached to one concrete anchor will be counted as one terminal anchor assembly (Type CA) for measurement and payment.

The eighth paragraph of Section 83-1.03, "Measurement," of the Standard Specifications is amended to read:

- The quantities of return and end caps and the various types of terminal sections for metal beam guard railing will be determined as units from actual count.

The third paragraph of Section 83-1.04, "Payment," of the Standard Specifications is amended to read:

- The contract unit prices paid for end anchor assembly (Type SFT), end anchor assembly (Type CA), and rail tensioning assembly shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in constructing the end anchor assemblies, complete in place, including drilling anchor plate bolt holes in rail elements, driving steel foundation tubes, excavating for concrete anchor holes and disposing of surplus material, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

The fourth paragraph of Section 83-1.04, "Payment," of the Standard Specifications is amended to read:

- The contract unit prices paid for return caps, end caps, and the various types of terminal sections for metal beam guard railing shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing terminal sections, return and end caps, complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

The second paragraph of Section 83-2.02B, "Thrie Beam Barrier," of the Standard Specifications is amended to read:

- Rail elements, backup plates, terminal connectors, terminal sections, and return caps shall conform to Class A, Type 1 thrie beam guard railing as shown in AASHTO Designation: M 180.

The fourteenth paragraph of Section 83-2.02B, "Thrie Beam Barrier," of the Standard Specifications is amended to read:

- All metal work shall be fabricated in the shop, and no punching, cutting or welding will be permitted in the field. Rail elements shall be lapped so that the exposed ends will not face approaching traffic. Terminal sections and return caps shall be installed in conformance with the manufacturer's recommendation.

The first paragraph in Section 83-2.02D(2), "Materials," of the Standard Specifications is amended to read:

- Type 50 and 60 series concrete barriers shall be constructed of minor concrete conforming to the provisions in Section 90-10, "Minor Concrete," except as follows:
 - a. The maximum size of aggregate used for extruded or slip-formed concrete barriers shall be at the option of the Contractor, but in no case shall the maximum size be larger than 37.5-mm or smaller than 9.5-mm.
 - b. If the 9.5 mm maximum size aggregate grading is used to construct extruded or slip-formed concrete barriers, the cementitious material content of the minor concrete shall be not less than 400 kilograms per cubic meter.

The third paragraph in Section 83-2.02D(2), "Materials," of the Standard Specifications is amended to read:

- The concrete paving between the tops of the 2 walls of concrete barrier (Types 50E, 60E, 60GE, and 60SE) and the optional concrete slab at the base between the 2 walls of concrete barrier (Types 50E, 60E, 60GE, and 60SE) shall be constructed of minor concrete conforming to the provisions of Section 90-10, "Minor Concrete," except that the minor concrete shall contain not less than 300 kilograms of cementitious material per cubic meter.

The first paragraph of Section 83-2.03, "Measurement," of the Standard Specifications is amended to read:

- Except for single thrie beam barrier within the pay limits of transition railing (Type STB), single thrie beam barrier will be measured by the meter from end post to end post along the face of the rail element of the installed barrier. Single thrie beam barriers constructed on each side of piers under structures or other obstructions will be measured for payment along each line of the installed barrier.

The second paragraph of Section 83-2.03, "Measurement," of the Standard Specifications is amended to read:

- Except for double thrie beam barrier within the pay limits of transition railing (Type DTB), double thrie beam barrier will be measured by the meter from end post to end post along the center line of the installed barrier.

The fifth paragraph of Section 83-2.03, "Measurement," of the Standard Specifications is amended to read:

- The quantity of return caps, terminal connectors and the various types of terminal sections for single and double thrie beam barriers will be determined as units from actual count.

The sixth paragraph of Section 83-2.03, "Measurement," of the Standard Specifications is amended to read:

- The quantity of end anchor assemblies will be paid for as units determined from actual count.

The first paragraph of Section 83-2.04, "Payment," of the Standard Specifications is amended to read:

- The various types of thrie beam barrier, measured as specified in Section 83-2.03, "Measurement," will be paid for at the contract price per meter for single or double thrie beam barrier, whichever applies, and the contract unit price or prices for end anchor assemblies, return caps, terminal connectors and the various types of terminal sections.

The second paragraph of Section 83-2.04, "Payment," of the Standard Specifications is amended to read:

- The above prices and payments shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in constructing the barrier, complete in place, including drilling holes for wood posts, driving posts, backfilling the space around posts, excavating and backfilling end anchor assembly holes, connecting thrie beam barrier to concrete surfaces and disposing of surplus excavated material, and for furnishing, placing, removing and disposing of the temporary railing for closing the gap between existing barrier and the barrier being constructed as shown on the plans, and as specified in these specifications and the special provisions, and as directed by the Engineer.

The fourth paragraph in Section 83-2.04, "Payments," of the Standard Specifications is amended to read:

- Steel plate barrier attached to concrete barrier at overhead sign foundations, electroliers, drainage structures, and other locations shown on the plans will be measured and paid for as the type of concrete barrier attached thereto.

SECTION 84: TRAFFIC STRIPES AND PAVEMENT MARKINGS

Issue Date: July 21, 2006

The first paragraph of Section 84-2.02, "Materials," of the Standard Specifications is amended to read:

- The thermoplastic material shall conform to State Specification PTH-02SPRAY, PTH-02HYDRO or PTH-02ALKYD. Glass beads to be applied to the surface of the molten thermoplastic material shall conform to the requirements of State Specification 8010-004 (Type II).

The first paragraph of Section 84-3.02, "Materials," of the Standard Specifications is amended to read:

- Paint for traffic stripes and pavement markings shall conform to the following State Specifications:

Paint Type	Color	State Specification No.
Waterborne Traffic Line	White, Yellow and Black	PTWB-01
Acetone-Based	White, Yellow and Black	PT-150VOC(A)
Waterborne Traffic Line for disabled persons' parking, and other curb markings	Blue, Red and Green	Federal Specification No. TT-P-1952D

The fourth paragraph of Section 84-3.02, "Materials," of the Standard Specifications is amended to read:

- The kind of paint to be used (waterborne or acetone-based) shall be determined by the Contractor based on the time of year the paint is applied and local air pollution control regulations.

The first paragraph of Section 84-3.05, "Application," of the Standard Specifications is amended to read:

Traffic stripes and pavement markings shall be applied only on dry surfaces and only during periods of favorable weather. Painting shall not be performed when the atmospheric temperature is below 5°C when using acetone-based paint or below 10°C when using water borne paint; when freshly painted surfaces may become damaged by rain, fog, or condensation; nor when it can be anticipated that the atmospheric temperature will drop below the aforementioned 5°C or 10°C temperatures during the drying period.

The third paragraph of Section 84-3.05, "Application," of the Standard Specifications is deleted.

The tenth paragraph of Section 84-3.05, "Application," of the Standard Specifications is amended to read:

- Paint to be applied in 2 coats shall be applied approximately as follows:

Paint Type	Square Meter Coverage Per Liter	
	First Coat	Second Coat
Waterborne Paint	6	6
Acetone-Based Paint	10	5

SECTION 85: PAVEMENT MARKERS

Issue Date: August 17, 2007

The second through fifth paragraphs in Section 85-1.03, "Sampling, Tolerances and Packaging," of the Standard Specifications are amended to read:

Sampling

- Twenty markers selected at random will constitute a representative sample for each lot of markers.
- The lot size shall not exceed 25 000 markers.

Tolerances

- Three test specimens will be randomly selected from the sample for each test and tested in conformance with these specifications. Should any one of the 3 specimens fail to conform with the requirements in these specifications, 6 additional specimens will be tested. The failure of any one of these 6 specimens shall be cause for rejection of the entire lot or shipment represented by the sample.
- The entire sample of retroreflective pavement markers will be tested for reflectance. The failure of 10 percent or more of the original sampling shall be cause for rejection.

Section 85-1.04, "Non-Reflective Pavement Markers," of the Standard Specifications is amended to read:

85-1.04 Non-Reflective Pavement Markers

- Non-reflective pavement markers (Types A and AY) shall be, at the option of the Contractor, either ceramic or plastic conforming to these specifications.
- The top surface of the marker shall be convex with a gradual change in curvature. The top, bottom and sides shall be free of objectionable marks or discoloration that will affect adhesion or appearance.
- The bottom of markers shall have areas of integrally formed protrusions or indentations, which will increase the effective bonding surface area of adhesive. The bottom surface of the marker shall not deviate more than 1.5 mm from a flat surface. The areas of protrusion shall have faces parallel to the bottom of the marker and shall project approximately one mm from the bottom.

The second through fourth paragraphs of Section 85-1.04A, "Non-Reflective Pavement Markers (Ceramic)," of the Standard Specifications are deleted.

The table in the fifth paragraph in Section 85-1.04A, "Non-Reflective Pavement Markers (Ceramic)," of the Standard Specifications is amended to read:

Testing

- Tests shall be performed in conformance with the requirements in California Test 669.

Test	Test Description	Requirement
a	Bond strength	4.8 MPa, min.
b	Glaze thickness	180 μ m, min.
c	Hardness	6 Moh, min.
d	Luminance factor, Type A, white markers only, glazed surface	75, min.
e	Yellowness index, Type A, white markers only, glazed surface	7, max.
f	Color-yellow, Type AY, yellow markers only. The chromaticity coordinates shall be within a color box defined in CTM 669	Pass
g	Compressive strength	6700 N, min.
h	Water absorption	2.0 %, max.
i	Artificial weathering, 500 hours exposure, yellowness index	20, max.

Section 85-1.04B, "Non-Reflective Pavement Markers (Plastic)," of the Standard Specifications is amended to read:

85-1.04B Non-Reflective Pavement Markers (Plastic)

- Plastic non-reflective pavement markers Types A and AY shall be, at the option of the Contractor, either polypropylene or acrylonitrile-butadiene-styrene (ABS) plastic type.
- Plastic markers shall conform to the testing requirements specified in Section 85-1.04A, "Non-Reflective Pavement Markers (Ceramic)," except that Tests a, b, c, and h shall not apply. The plastic markers shall not be coated with substances that interfere with the ability of the adhesive bonding to the marker.

The sixth and seventh paragraphs in Section 85-1.05, "Retroreflective Pavement Markers," of the Standard Specifications are amended to read:

Testing

- Tests shall be performed in conformance with the requirements in California Test 669.

Test Description	Requirement		
Bond strength ^a	3.4 MPa, min.		
Compressive strength ^b	8900 N, min.		
Abrasion resistance, marker must meet the respective specific intensity minimum requirements after abrasion.	Pass		
Water Soak Resistance	No delamination of the body or lens system of the marker nor loss of reflectance		
Reflectance	Specific Intensity		
	Clear	Yellow	Red
0° Incidence Angle, min.	3.0	1.5	0.75
20° Incidence Angle, min.	1.2	0.60	0.30
After one year field evaluation	0.30	0.15	0.08

- Failure of the marker body or filler material prior to reaching 3.4 MPa shall constitute a failing bond strength test.
- Deformation of the marker of more than 3 mm at a load of less than 8900 N or delamination of the shell and the filler material of more than 3 mm regardless of the load required to break the marker shall be cause for rejection of the markers as specified in Section 85-1.03, "Sampling, Tolerances and Packaging."

- Pavement markers to be placed in pavement recesses shall conform to the above requirements for retroreflective pavement markers except that the minimum compressive strength requirement shall be 5338 N.

The eighth paragraph of Section 85-1.05, "Retroreflective Pavement Markers," of the Standard Specifications is deleted.

The eighth paragraph in Section 85-1.06, "Placement," of the Standard Specifications is amended to read:

- Epoxy adhesive shall not be used to apply non-reflective plastic pavement markers.

The seventh sentence of the fourteenth paragraph of Section 85-1.06, "Placement," of the Standard Specifications is amended to read:

- Soft rags moistened with mineral spirits conforming to Army Mil-PRF-680A(1) or kerosene may be used, if necessary, to remove adhesive from exposed faces of pavement markers.

SECTION 86: SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS

Issue Date: January 5, 2007

The second paragraph of Section 86-1.01, "Description," of the Standard Specifications is amended to read:

- The locations of signals, beacons, standards, lighting fixtures, signs, controls, services and appurtenances shown on the plans are approximate and the exact locations will be approved by the Engineer in the field.

The tenth paragraph of Section 86-1.06, "Maintaining Existing and Temporary Electrical Systems," of the Standard Specifications is amended to read:

- These provisions will not relieve the Contractor in any manner of the Contractor's responsibilities as provided in Section 7-1.12, "Indemnification and Insurance," and Section 7-1.16, "Contractor's Responsibility for the Work and Materials."

The first paragraph of Section 86-2.03, "Foundations," of the Standard Specifications is amended to read:

- Except for concrete for cast-in-drilled-hole concrete pile foundations, portland cement concrete shall conform to Section 90-10, "Minor Concrete."

The fourth paragraph in Section 86-2.03, "Foundations," of the Standard Specifications is amended to read:

- After each post, standard, and pedestal on structures is in proper position, mortar shall be placed under the base plate as shown on the plans. The exposed portions shall be formed to present a neat appearance. Mortar shall conform to Section 51-1.135, "Mortar," except the mortar shall consist of one part by volume of cementitious material and 3 parts of clean sand and shall contain only sufficient moisture to permit packing. Mortar shall be cured by keeping it damp for 3 days.

The fifth paragraph of Section 86-2.03, "Foundations," of the Standard Specifications is amended to read:

- Reinforced cast-in-drilled-hole concrete pile foundations for traffic signal and lighting standards shall conform to the provisions in Section 49, "Piling," with the following exceptions: 1) Material resulting from drilling holes shall be disposed of in conformance with the provisions in Section 86-2.01, "Excavating and Backfilling," and 2) Concrete filling for cast-in-drilled-hole concrete piles will not be considered as designated by compressive strength.

The seventh paragraph of Section 86-2.03, "Foundations," of the Standard Specifications is amended to read:

- Forms shall be true to line and grade. Tops of foundations for posts and standards, except special foundations, shall be finished to curb or sidewalk grade or as directed by the Engineer. Forms shall be rigid and securely braced in place. Conduit ends and anchor bolts shall be placed in proper position and to proper height, and anchor bolts shall be held in place by means of rigid top and bottom templates. The bottom template shall be made of steel. The bottom template shall provide proper spacing and alignment of the anchor bolts near their bottom embedded end. The bottom template shall be installed before placing footing concrete. Anchor bolts shall not be installed more than 1:40 from vertical.

Section 86-2.03, "Foundations," of the Standard Specifications is amended by deleting the eighth paragraph.

The twelfth paragraph of Section 86-2.03, "Foundations," of the Standard Specifications is amended to read:

- Plumbing of the standards shall be accomplished by adjusting the leveling nuts before placing the mortar or before the foundation is finished to final grade. Shims or other similar devices shall not be used for plumbing or raking of posts, standards, or pedestals. After final adjustments of both top nuts and leveling nuts on anchorage assemblies have been made, firm contact shall exist between all bearing surfaces of the anchor bolt nuts, washers, and the base plates.

The first paragraph of Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications is amended to read:

- Bolts, nuts and washers, and anchor bolts for use in signal and lighting support structures shall conform to the provisions in Section 55-2, "Materials." Except when bearing-type connections or slipbases are specified, high-strength bolted connections shall conform to the provisions in Section 55-3.14, "Bolted Connections." Welding, nondestructive testing (NDT) of welds, and acceptance and repair criteria for NDT of steel members shall conform to the requirements of AWS D1.1 and the special provisions.

The second paragraph of Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications is amended to read:

- On each lighting standard except Type 1, one rectangular corrosion resistant metal identification tag shall be permanently attached above the hand hole, near the base of the standard, using stainless steel rivets. On each signal pole support, two corrosion resistant metal identification tags shall be attached, one above the hand hole near the base of the vertical standard and one on the underside of the signal mast arm near the arm plate. As a minimum, the information on each identification tag shall include the name of the manufacturer, the date of manufacture, the identification number as shown on the plans, the contract number, and a unique identification code assigned by the fabricator. This number shall be traceable to a particular contract and the welds on that component, and shall be readable after the support structure is coated and installed. The lettering shall be a minimum of 7 mm high. The information may be either depressed or raised, and shall be legible.

The fourth paragraph of Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications is amended to read:

- Ferrous metal parts of standards, with shaft length of 4.6 m and longer, shall conform to the details shown on the plans, the provisions in Section 55-2, "Materials," except as otherwise noted, and the following requirements:

- A. Except as otherwise specified, standards shall be fabricated from sheet steel of weldable grade having a minimum yield strength, after fabrication, of 276 MPa.
- B. Certified test reports which verify conformance to the minimum yield strength requirements shall be submitted to the Engineer. The test reports may be the mill test reports for the as-received steel or, when the as-received steel has a lower yield strength than required, the Contractor shall provide supportive test data which provides assurance that the Contractor's method of cold forming will consistently increase the tensile properties of the steel to meet the specified minimum yield strength. The supportive test data shall include tensile properties of the steel after cold forming for specific heats and thicknesses.
- C. When a single-ply 8-mm thick pole is specified, a 2-ply pole with equivalent section modulus may be substituted.
- D. Standards may be fabricated of full-length sheets or shorter sections. Each section shall be fabricated from not more than 2 pieces of sheet steel. Where 2 pieces are used, the longitudinal welded seams shall be directly opposite one another. When the sections are butt-welded together, the longitudinal welded seams on adjacent sections shall be placed to form continuous straight seams from base to top of standard.
- E. Butt-welded circumferential joints of tubular sections requiring CJP groove welds shall be made using a metal sleeve backing ring inside each joint. The sleeve shall be 3-mm nominal thickness, or thicker, and manufactured from steel having the same chemical composition as the steel in the tubular sections to be joined. When the sections to be joined have different specified minimum yield strengths, the steel in the sleeve shall have the same chemical composition as the tubular section having the higher minimum yield strength. The width of the metal sleeve shall be consistent with the type of NDT chosen and shall be a minimum width of 25 mm. The sleeve shall be centered at the joint and be in contact with the tubular section at the point of the weld at time of fit-up.
- F. Welds shall be continuous.
- G. The weld metal at the transverse joint shall extend to the sleeve, making the sleeve an integral part of the joint.
- H. During fabrication, longitudinal seams on vertical tubular members of cantilevered support structures shall be centered on and along the side of the pole that the pole plate is located. Longitudinal seams on horizontal tubular members, including signal and luminaire arms, shall be within +/-45 degrees of the bottom of the arm.
- I. The longitudinal seam welds in steel tubular sections may be made by the electric resistance welding process.
- J. Longitudinal seam welds shall have 60 percent minimum penetration, except that within 150 mm of circumferential welds, longitudinal seam welds shall be CJP groove welds. In addition, longitudinal seam welds on lighting support structures having telescopic pole segment splices shall be CJP groove welds on the female end for a length on each end equal to the designated slip fit splice length plus 150 mm.
- K. Exposed circumferential welds, except fillet and fatigue-resistant welds, shall be ground flush (-0, +2 mm) with the base metal prior to galvanizing or painting.
- L. Circumferential welds and base plate-to-pole welds may be repaired only one time without written permission from the Engineer.

- M. Exposed edges of the plates that make up the base assembly shall be finished smooth and exposed corners of the plates shall be broken unless otherwise shown on the plans. Shafts shall be provided with slip-fitter shaft caps.
- N. Flatness of surfaces of 1) base plates that are to come in contact with concrete, grout, or washers and leveling nuts; 2) plates in high-strength bolted connections; 3) plates in joints where cap screws are used to secure luminaire and signal arms; and 4) plates used for breakaway slip base assemblies shall conform to the requirements in ASTM A6.
- O. Standards shall be straight, with a permissive variation not to exceed 25 mm measured at the midpoint of a 9-m or 11-m standard and not to exceed 20 mm measured at the midpoint of a 5-m through 6-m standard. Variation shall not exceed 25 mm at a point 4.5 m above the base plate for Type 35 and Type 36 standards.
- P. Zinc-coated nuts used on fastener assemblies having a specified preload (obtained by specifying a prescribed tension, torque value, or degree of turn) shall be provided with a colored lubricant that is clean and dry to the touch. The color of the lubricant shall be in contrast to the zinc coating on the nut so that the presence of the lubricant is visually obvious. In addition, either the lubricant shall be insoluble in water, or fastener components shall be shipped to the job site in a sealed container.
- Q. No holes shall be made in structural members unless the holes are shown on the plans or are approved in writing by the Engineer.
- R. Standards with an outside diameter of 300 mm or less shall be round. Standards with an outside diameter greater than 300 mm shall be round or multisided. Multisided standards shall have a minimum of 12 sides which shall be convex and shall have a minimum bend radius of 100 mm.
- S. Mast arms for standards shall be fabricated from material as specified for standards, and shall conform to the dimensions shown on the plans.
- T. The cast steel option for slip bases shall be fabricated from material conforming to the requirements in ASTM Designation: A 27/A 27M, Grade 70-40. Other comparable material may be used if written permission is given by the Engineer. The casting tolerances shall be in conformance with the Steel Founder's Society of America recommendations (green sand molding).
- U. One casting from each lot of 50 castings or less shall be subject to radiographic inspection, in conformance with the requirements in ASTM Designation: E 94. The castings shall comply with the acceptance criteria severity level 3 or better for the types and categories of discontinuities in conformance with the requirements in ASTM Designations: E 186 and E 446. If the one casting fails to pass the inspection, 2 additional castings shall be radiographed. Both of these castings shall pass the inspection, or the entire lot of 50 will be rejected.
- V. Material certifications, consisting of physical and chemical properties, and radiographic films of the castings shall be filed at the manufacturer's office. These certifications and films shall be available for inspection upon request.
- W. High-strength bolts, nuts, and flat washers used to connect slip base plates shall conform to the requirements in ASTM Designation: A 325 or A 325M and shall be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing."
- X. Plate washers shall be fabricated by saw cutting and drilling steel plate conforming to the requirements in AISI Designation: 1018, and be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing." Prior to galvanizing, burrs and sharp edges shall be removed and holes shall be chamfered sufficiently on each side to allow the bolt head to make full contact with the washer without tension on the bolt.
- Y. High-strength cap screws shown on the plans for attaching arms to standards shall conform to the requirements in ASTM Designation: A 325, A 325M, or A 449, and shall comply with the mechanical requirements in ASTM Designation: A 325 or A 325M after galvanizing. The cap screws shall be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing." The threads of the cap screws shall be coated with a colored lubricant that is clean and dry to the touch. The color of the lubricant shall be in contrast to the color of the zinc coating on the cap screw so that presence of the lubricant is visually obvious. In addition, either the lubricant shall be insoluble in water, or fastener components shall be shipped to the job site in a sealed container.
- Z. Unless otherwise specified, bolted connections attaching signal or luminaire arms to poles shall be considered slip critical. Galvanized faying surfaces on plates on luminaire and signal arms and matching plate surfaces on poles shall be roughened by hand using a wire brush prior to assembly and shall conform to the requirements for Class C surface conditions for slip-critical connections in "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts," a specification approved by the Research Council on Structural Connections (RCSC) of the Engineering Foundation. For faying surfaces required to be painted, the paint shall be an approved type, brand, and thickness that has been tested and approved according to the RCSC Specification as a Class B coating.
- AA. Samples of fastener components will be randomly taken from each production lot by the Engineer and submitted, along with test reports required by appropriate ASTM fastener specifications, for QA testing and evaluation. Sample sizes for each fastener component shall be as determined by the Engineer.

The seventh paragraph of Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications is amended to read:

- To avoid interference of arm plate-to-tube welds with cap screw heads, and to ensure cap screw heads can be turned using conventional installation tools, fabricators shall make necessary adjustments to details prior to fabrication and properly locate the position of arm tubes on arm plates during fabrication.

The fourth subparagraph of the eighteenth paragraph in Section 86-2.05C, "Installation," of the Standard Specifications is amended to read:

- The conduit shall be placed in the bottom of the trench, and the trench shall be backfilled with minor concrete conforming to the provisions in Section 90-10, "Minor Concrete." Minor concrete shall contain not less than 350 kilograms of cementitious material per cubic meter. Concrete backfill shall be placed to the pavement surface except, when the trench is in asphalt concrete pavement and additional pavement is not being placed, the top 30 mm of the trench shall be backfilled with asphalt concrete produced from commercial quality paving asphalt and aggregates.

The third subparagraph of the twenty-third paragraph in Section 86-2.05C, "Installation," of the Standard Specifications is amended to read:

- Precast concrete conduit cradles shall conform to the dimensions shown on the plans and shall be constructed of minor concrete and commercial quality welded wire fabric. Minor concrete shall conform to the provisions in Section 90-10, "Minor Concrete," and shall contain not less than 350 kilograms of cementitious material per cubic meter. The cradles shall be moist cured for not less than 3 days.

The seventh subparagraph of the twenty-third paragraph in Section 86-2.05C, "Installation," of the Standard Specifications is amended to read:

- The space around conduits through bridge abutment walls shall be filled with mortar conforming to the provisions in Section 51-1.135, "Mortar," except that the proportion of cementitious material to sand shall be 1:3.

The fifth paragraph in Section 86-2.07, "Traffic Pull Boxes," of the Standard Specifications is amended to read:

- Concrete placed around and under traffic pull boxes as shown on the plans shall be minor concrete conforming to the provisions in Section 90-10, "Minor Concrete."

The traffic signal controller cabinet requirement in the table in Section 86-2.08A, "Conductor Identification," of the Standard Specifications is amended to read:

Traffic Signal Controller Cabinet	Ungrounded Circuit Conductor	Blk	None	CON-1	6
	Grounded Circuit Conductor	Wht	None	CON-2	6

The second paragraph of Section 86-2.08B, "Multiple Circuit Conductors," of the Standard Specifications is amended to read by the following 2 paragraphs:

- At any point, the minimum insulation thickness of any Type USE, RHH, or RHW insulation shall be 1.0 mm for conductor sizes No. 14 to No. 10, inclusive; and 1.3 mm for No. 8 to No. 2, inclusive.
- At any point, the minimum insulation thickness of any Type THW or TW wires shall be 0.7 mm for conductor sizes No. 14 to No. 10, inclusive; 1.0 mm for No. 8; and 1.4 mm for No. 6 to No. 2, inclusive.

The sixth and seventh paragraphs of 86-2.12, "Wood Poles," of the Standard Specifications are amended to read:

- After fabrication, wood poles shall be pressure treated in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," and AWPA Use Category System: UC4B, Commodity Specification D.
- Wood poles, when specified in the special provisions to be painted, shall be treated with waterborne wood preservatives.

The first paragraph of Section 86-2.15, "Galvanizing," of the Standard Specifications is amended to read:

- Galvanizing shall be in conformance with the provisions in Section 75-1.05, "Galvanizing," except that cabinets may be constructed of material galvanized prior to fabrication in conformance with the requirements in ASTM Designation: A 653/653M, Coating Designation G 90, in which case all cut or damaged edges shall be painted with at least 2 applications of approved unthinned zinc-rich primer (organic vehicle type) conforming to the provisions in Section 91, "Paint." Aerosol cans shall not be used. Other types of protective coating must be approved by the Engineer prior to installation.

Item B of the thirteenth paragraph of Section 86-2.16, "Painting," of the Standard Specifications is amended to read:

B. Salt Spray Resistance - The undercutting of the film of the coating system shall not exceed 3 mm average, from lines scored diagonally and deep enough to expose the base metal, after 336 hours exposure in a salt spray cabinet in conformance with the requirements in ASTM Designation: B 117.

The first paragraph of Section 86-4.01, "Vehicle Signal Faces," of the Standard Specifications is amended to read:

- Each vehicle signal face shall be of the adjustable type conforming to the requirements in Institute of Transportation Engineers (ITE) Publication: ST-017B, "Vehicle Traffic Control Signal Heads."

Subparagraphs 1 and 3 of the first paragraph of Section 86-4.01A, "Optical Units," of the Standard Specifications are amended to read:

- Lenses, reflectors, reflector assemblies, lamp receptacles, lamps, wiring and light distribution shall conform to the requirements in ITE Publication: ST-017B.
- All reflectors shall conform to the requirements in ITE Publication: ST-017B except that reflectors shall be made of silvered glass or of specular aluminum with an anodic coating. Reflector ring holder shall be made of cast aluminum.

The first paragraph of Section 86-4.01B, "Signal Sections," of the Standard Specifications is amended to read:

- Each signal section housing shall be either die-cast or permanent mold-cast aluminum conforming to ITE Publication: ST-017B or, when specified in the special provisions, shall be structural plastic.

The first paragraph of Section 86-4.01C, "Electrical Components," of the Standard Specifications is amended to read:

- Lamp receptacles and wiring shall conform to ITE Publication: ST-017B. The metal portion of the medium base lamp socket shall be brass, copper or phosphor bronze.

The first paragraph of Section 86-4.01D, "Visors," of the Standard Specifications is amended to read:

- Each signal section shall be provided with a removable visor conforming to the requirements in ITE Publication: ST-017B. Visors are classified, on the basis of lens enclosure, as full circle, tunnel (bottom open), or cap (bottom and lower sides open). Unless otherwise specified, visors shall be the tunnel type.

The first paragraph of Section 86-4.02A, "Physical and Mechanical Requirements," of the Standard Specifications is amended to read:

- Light emitting diode signal modules shall be designed as retrofit replacements for optical units of standard traffic signal sections and shall not require special tools for installation. Light emitting diode signal modules shall fit into existing traffic signal section housings built in conformance with the requirements in the Institute of Transportation Engineers (ITE) publication ST-017B, "Vehicle Traffic Control Signal Heads (VTCSH)" without modification to the housing.

The seventh paragraph of Section 86-4.02A, "Physical and Mechanical Requirements," of the Standard Specifications is amended to read:

- Light emitting diode signal modules shall be protected against dust and moisture intrusion in conformance with the requirements in NEMA Standard 250 for Type 4 enclosures to protect the internal components.

The first paragraph of Section 86-4.02B, "Photometric Requirements," of the Standard Specifications is amended to read:

- The minimum initial luminous intensity values for light emitting diode signal modules shall conform to the requirements in Section 11.04 of the Institute of Transportation Engineers (ITE) publication ST-017B, "Vehicle Traffic Control Signal Heads (VTCSH)" at 25°C.

The third paragraph of Section 86-4.02C, "Electrical," of the Standard Specifications is amended to read:

- The light emitting diode signal module on-board circuitry shall include voltage surge protection to withstand high-repetition noise transients as specified in Section 2.1.6 of NEMA Standard TS2.

Subparagraph 7 of the fourth paragraph of Section 86-4.02D(1), "Design Qualification Testing," of the Standard Specifications is amended to read:

- Moisture resistance testing shall be performed on light emitting diode signal modules in conformance with the requirements in NEMA Standard 250 for Type 4 enclosures. Evidence of internal moisture after testing shall be cause for rejection.

The second paragraph of Section 86-4.05, "Programmed Visibility Vehicle Signal Faces," of the Standard Specifications is amended to read:

- Each programmed visibility signal section shall provide a nominal 300-mm diameter circular or arrow indication. Color and arrow configuration shall conform to the requirements in ITE Publication: ST-017B.

The first paragraph of Section 86-4.06, "Pedestrian Signal Faces," of the Standard Specifications is amended to read:

- Message symbols for pedestrian signal faces shall be white WALKING PERSON and Portland orange UPRAISED HAND conforming to the requirements in the Institute of Transportation Engineers Standards: "Pedestrian Traffic Control Signal Indications" and "California MUTCD." The height of each symbol shall be not less than 250 mm and the width of each symbol shall be not less than 165 mm.

Subparagraph 3 of the first paragraph of Section 86-4.06A, "Types," of the Standard Specifications is amended to read:

- Each reflector assembly shall consist of a double reflector or 2 single reflectors. Each reflector shall be made of either aluminum or plastic. Reflectors shall conform to the requirements in Institute of Transportation Engineers Publication: ST-017B, "Vehicle Traffic Control Signal Heads." Plastic reflectors shall consist of molded or vacuum-formed plastic with a vacuum-deposited aluminum reflecting surface. The plastic material shall not distort when the reflector is used with the lamp of the wattage normally furnished with the signal. In addition, the UL nonmechanical loading temperature of the material shall exceed, by at least 10°C, the maximum temperature in the signal section with the lamp "ON" and measured in an ambient air temperature of 25°C in conformance with the requirements in UL Publication UL 746B. Each completed reflector shall, when operated with the appropriate lamp and lens, provide the message brightness specified.

The tenth paragraph of Section 86-4.07, "Light Emitting Diode Pedestrian Signal Face 'Upraised Hand' Module," of the Standard Specifications is amended to read:

- The luminance of the "UPRAISED HAND" symbol shall be 3750 cd/m² minimum. The color of "UPRAISED HAND" shall be Portland orange conforming to the requirements of the Institute of Transportation Engineers Standards: "Pedestrian Traffic Control Signal Indications" and "California MUTCD." The height of each symbol shall be not less than 250 mm and the width of each symbol shall be not less than 165 mm.

The second paragraph of Section 86-4.07C, "Electrical," of the Standard Specifications is amended to read:

- On-board circuitry of the light emitting diode pedestrian signal modules shall include voltage surge protection to withstand high-repetition noise transients as stated in Section 2.1.6 of NEMA Standard TS2.

The second paragraph of Section 86-4.07D(1), "Design Qualification Testing," of the Standard Specifications is amended to read:

- A quantity of 2 units for each design shall be submitted for Design Qualification Testing. Test units shall be submitted to the Transportation Laboratory, after manufacturer's testing is complete.

Subparagraphs 5 and 7 of the fourth paragraph of Section 86-4.07D(1), "Design Qualification Testing," of the Standard Specifications are amended to read:

- Mechanical vibration testing shall be in conformance with the requirements in Military Specification MIL-STD-883, Test Method 2007, using three 4-minute cycles along each x, y and z axis, at a force of 2.5 Gs, with a frequency sweep from 2 Hz to 120 Hz. The loosening of the lens or of internal components, or other physical damage shall be cause for rejection.
- Moisture resistance testing shall be performed on modules mounted in a standard pedestrian signal housing in conformance to the requirements in NEMA Standard 250 for Type 4 enclosures. Evidence of internal moisture after testing shall be cause for rejection.

The cone penetration, flow, and resilience requirements in the table in the second paragraph under "Hot-Melt Rubberized Asphalt Sealant" of Section 86-5.01A(5), "Installation Details," of the Standard Specifications is amended to read:

Cone Penetration, 25°C, 150 g, 5 s	D 5329, Sec. 6	3.5 mm, max.
Flow, 60°C	D 5329, Sec. 8	5 mm, max.
Resilience, 25°C	D 5329, Sec. 12	25%, min.

The first paragraph in Section 86-5.01D, "Removing or Abandoning Existing Pressure-Sensitive Detectors," of the Standard Specifications is amended to read:

- When a foundation for a pressure-sensitive vehicle detector is to be removed, the hole left by removing the detector frame and foundation shall be filled with minor concrete, except the roadway surface shall be reconstructed with material to match existing surfacing. Minor concrete shall conform to the provisions in Section 90-10, "Minor Concrete," except that the concrete shall contain not less than 250 kilograms of cementitious material per cubic meter for asphalt concrete surfaced roadways and not less than 350 kilograms of cementitious material per cubic meter for portland cement concrete surfaced roadways.

The third paragraph under "Mounting Assemblies" of Section 86-6.065, "Internally Illuminated Street Name Signs," of the Standard Specifications is amended to read:

- At least 4.9 m of clearance shall be provided between the bottom of the fixture and the roadway.

The first paragraph of Section 86-8.01, "Payment," of the Standard Specifications is amended to read:

- The contract lump sum price or prices paid for signal, ramp metering, flashing beacon, lighting, sign illumination, traffic monitoring station, highway advisory radio systems, closed circuit television systems, or combinations thereof; for modifying or removing those systems; for temporary systems; or the lump sum or unit prices paid for various units of those systems; or the lump sum or per meter price paid for conduit of the various sizes, types and installation methods listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in furnishing and installing, modifying, or removing the systems, combinations or units thereof, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer, including any necessary pull boxes (except when the type required is shown as a separate contract item); excavation and backfill; concrete foundations (except when shown as a separate contract item); pedestrian barricades; furnishing and installing illuminated street name signs; installing sign panels on pedestrian barricades, on flashing beacon standards, and on traffic signal mast arms; restoring sidewalk, pavement and appurtenances damaged or destroyed during construction; salvaging existing materials; and making all required tests.

Section 86-8.01, "Payment," of the Standard Specifications is amended by adding the following paragraph after the first paragraph:

- If a portion or all of the poles for signal, lighting and electrical systems pursuant to Standard Specification Section 86, "Signals, Lighting and Electrical Systems," is fabricated more than 480 air line kilometers from both-Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impracticable and extremely difficult to ascertain and determine the actual increase in such expenses, it is agreed that payment to the Contractor for furnishing such items from each fabrication site located more than 480 air line kilometers from both Sacramento and Los Angeles will be reduced \$5000; in addition, in the case where a fabrication site is located more than 4800 air line kilometers from both Sacramento and Los Angeles, payment will be reduced an additional \$3000 per each fabrication site (\$8000 total per site).

SECTION 88: ENGINEERING FABRIC

Issue Date: January 15, 2002

Section 88-1.02, "Pavement Reinforcing Fabric," of the Standard Specifications is amended to read:

- Pavement reinforcing fabric shall be 100 percent polypropylene staple fiber fabric material, needle-punched, thermally bonded on one side, and conform to the following:

Specification	Requirement
Weight, grams per square meter ASTM Designation: D 5261	140
Grab tensile strength (25-mm grip), kilonewtons, min. in each direction ASTM Designation: D 4632	0.45
Elongation at break, percent min. ASTM Designation: D 4632	50
Asphalt retention by fabric, grams per square meter. (Residual Minimum) ASTM Designation: D 6140	900

Note: Weight, grab, elongation and asphalt retention are based on Minimum Average Roll Value (MARV)

SECTION 90: PORTLAND CEMENT CONCRETE

Issue Date: March 16, 2007

Section 90, "Portland Cement Concrete," of the Standard Specifications is amended to read:

SECTION 90: PORTLAND CEMENT CONCRETE

90-1 GENERAL

90-1.01 DESCRIPTION

- Portland cement concrete shall be composed of cementitious material, fine aggregate, coarse aggregate, admixtures if used, and water, proportioned and mixed as specified in these specifications.
- The Contractor shall determine the mix proportions for concrete in conformance with these specifications.
- Class 1 concrete shall contain not less than 400 kg of cementitious material per cubic meter.
- Class 2 concrete shall contain not less than 350 kg of cementitious material per cubic meter.
- Class 3 concrete shall contain not less than 300 kg of cementitious material per cubic meter.
- Class 4 concrete shall contain not less than 250 kg of cementitious material per cubic meter.
- Minor concrete shall contain not less than 325 kg of cementitious material per cubic meter unless otherwise specified in these specifications or the special provisions.
- Unless otherwise designated on the plans or specified in these specifications or the special provisions, the amount of cementitious material used per cubic meter of concrete in structures or portions of structures shall conform to the following:

Use	Cementitious Material Content (kg/m ³)
Concrete designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min., 475 max.
Roof sections of exposed top box culverts	400 min., 475 max.
Other portions of structures	350 min., 475 max.
Concrete not designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min.
Roof sections of exposed top box culverts	400 min.
Prestressed members	400 min.
Seal courses	400 min.
Other portions of structures	350 min.
Concrete for precast members	350 min., 550 max.

- Whenever the 28-day compressive strength shown on the plans is greater than 25 MPa, the concrete shall be designated by compressive strength. If the plans show a 28-day compressive strength that is 28 MPa or greater, an additional 14 days will be allowed to obtain the specified strength. The 28-day compressive strengths shown on the plans that are 25 MPa or less are shown for design information only and are not a requirement for acceptance of the concrete.

- Concrete designated by compressive strength shall be proportioned such that the concrete will attain the strength shown on the plans or specified in the special provisions.

- Before using concrete for which the mix proportions have been determined by the Contractor, or in advance of revising those mix proportions, the Contractor shall submit in writing to the Engineer a copy of the mix design.

- Compliance with cementitious material content requirements will be verified in conformance with procedures described in California Test 518 for cement content. For testing purposes, supplementary cementitious material shall be considered to be cement. Batch proportions shall be adjusted as necessary to produce concrete having the specified cementitious material content.

- If any concrete has a cementitious material, portland cement, or supplementary cementitious material content that is less than the minimum required, the concrete shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State \$0.55 for each kilogram of cementitious material, portland cement, or supplementary cementitious material that is less than the minimum required. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract. The deductions will not be made unless the difference between the contents required and those actually provided exceeds the batching tolerances permitted by Section 90-5, "Proportioning." No deductions will be made based on the results of California Test 518.

- The requirements of the preceding paragraph shall not apply to minor concrete or commercial quality concrete.

90-2 MATERIALS

90-2.01 CEMENTITIOUS MATERIALS

- Unless otherwise specified, cementitious material shall be either a combination of Type II or Type V portland cement and a supplementary cementitious material, or a blended cement.

- Cementitious materials used in cast-in-place concrete for exposed surfaces of like elements of a structure shall be from the same sources and of the same proportions.

- Cementitious materials shall be protected from moisture until used. Sacked cementitious materials shall be piled to permit access for tallying, inspecting, and identifying each shipment.

- Facilities shall be provided to ensure that cementitious materials meeting this Section 90-2.01 are kept separate from other cementitious materials. Sampling cementitious materials shall be in conformance with California Test 125.

- The Contractor shall furnish a Certificate of Compliance for cementitious materials in conformance with the provisions in Section 6-1.07, "Certificates of Compliance." The Certificate of Compliance shall indicate the source by name and location (including country, state, and city). If cementitious material is delivered directly to the job site, the Certificate of Compliance shall be signed by the cementitious material supplier. If the cementitious material is used in ready-mixed concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.

90-2.01A CEMENT

- Portland cement shall conform to the requirements in ASTM Designation: C 150 except, using a 10-sample moving average, limestone shall not exceed 2.5 percent. The C₃S content of Type II cement shall not exceed 65 percent.

- Blended cement shall conform to the requirements for Portland Blast-Furnace Slag, Cement Type IS (MS) or Portland-Pozzolan Cement, Type IP (MS) in AASHTO Designation: M 240 and shall be comprised of an intimate and uniform blend of Type II or Type V cement and supplementary cementitious material in an amount conforming to the requirements in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials."

- In addition, blended cement, Type II portland cement, and Type V portland cement shall conform to the following requirements:

- A. The cement shall not contain more than 0.60-percent by mass of alkalis, calculated as the percentage of Na₂O plus 0.658 times the percentage of K₂O, when determined by methods as required in AASHTO Designation: T 105;
- B. The autoclave expansion shall not exceed 0.50-percent; and
- C. Mortar, containing the cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not expand in water more than 0.010-percent and shall not contract in air more than 0.048-percent, except that when cement is to be used for precast prestressed concrete piling, precast prestressed concrete members, or steam cured concrete products, the mortar shall not contract in air more than 0.053-percent.

- Type III portland cement shall be used only as specified in the special provisions or with the approval of the Engineer. Type III portland cement shall conform to the additional requirements listed above for Type II portland cement, except when tested in conformance with California Test 527, mortar containing Type III portland cement shall not contract in air more than 0.075-percent.

90-2.01B SUPPLEMENTARY CEMENTITIOUS MATERIALS (SCM)

- Fly ash shall conform to the requirements in AASHTO Designation: M 295, Class F, and the following:

- A. Calcium oxide content shall not exceed 10 percent.
- B. The available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 311 or the total alkali, as sodium oxide equivalent, shall not exceed 5.0 percent when determined in conformance with the requirements in AASHTO Designation: T 105.
- C. Commingling of fly ash from different sources at uncontrolled ratios is permissible only if the following criteria are satisfied:
 1. Sources of fly ash to be commingled shall be on the approved list of materials for use in concrete.
 2. Testing of the commingled product is the responsibility of the fly ash supplier.
 3. Each fly ash's running average of density shall not differ from any other by more than 0.25g/cm³ at the time of commingling.
 4. Each fly ash's running average of loss on ignition shall not differ from any other by more than one percent at the time of commingling.
 5. The final product of commingled fly ash shall conform to the requirement in AASHTO Designation: M 295.

- Raw or calcined natural pozzolans shall conform to the requirements in AASHTO Designation: M 295, Class N and the following requirements:

- A. Calcium oxide content shall not exceed 10 percent.
- B. The available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 311 or the total alkali, as sodium oxide equivalent, shall not exceed 5.0 percent when determined in conformance with the requirements in AASHTO Designation: T 105.

- Ground Granulated Blast Furnace Slag (GGBFS) shall conform to the requirements in AASHTO Designation: M 302, Grade 100 or Grade 120.

- Silica Fume shall conform to the requirements of AASHTO Designation: M 307 with reduction in mortar expansion of 80 percent, minimum, using the cement from the proposed mix design.

90-2.01C REQUIRED USE OF SUPPLEMENTARY CEMENTITIOUS MATERIALS

- The amount of portland cement and SCM used in portland cement concrete shall conform to the minimum cementitious material content provisions in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," and the following:

- A. If a blended cement conforming to the provisions in Section 90-2.01A, "Cement," is used, the minimum amount of SCM incorporated into the cement shall conform to the provisions in this Section 90-2.01C.
 - B. Fly ash or natural pozzolan, silica fume, or GGBFS shall not be used with Type IP or Type IS cements.
- Use of SCMs shall conform to the following:
 - A. If fly ash or natural pozzolan is used:
 - 1. The minimum amount of portland cement shall not be less than 75 percent by mass of the specified minimum cementitious material content.
 - 2. The minimum amount of fly ash or natural pozzolan shall be:
 - a. Fifteen percent by mass of the total amount of cementitious material if the calcium oxide content of fly ash or natural pozzolan is equal to or less than 2 percent by mass;
 - b. Twenty-five percent by mass of the total amount of cementitious material if the calcium oxide content of fly ash or natural pozzolan is greater than 2 percent by mass.
 - B. The total amount of fly ash or natural pozzolan shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. If Section 90-1.01, "Description," specifies a maximum cementitious material content in kilograms per cubic meter, the total mass of portland cement and fly ash or natural pozzolan per cubic meter shall not exceed the specified maximum cementitious material content.
 - C. If silica fume is used:
 - 1. The amount of silica fume shall not be less than 10 percent by mass of the total amount of cementitious material.
 - 2. The amount of portland cement shall not be less than 75 percent by mass of the specified minimum cementitious material content.
 - 3. If Section 90-1.01, "Description," specifies a maximum cementitious material content in kilograms per cubic meter, the total mass of portland cement and silica fume per cubic meter shall not exceed the specified maximum cementitious material content.
 - D. If GGBFS is used:
 - 1. The minimum amount of GGBFS shall be either:
 - a. Forty percent of the total cementitious material to be used, if the aggregates used in the concrete are on the Department's list of "Approved Aggregates For Use in Concrete with Reduced Fly Ash."
 - b. No less than 50 percent.
 - 2. The amount of GGBFS shall not exceed 60 percent by mass of the total amount of cementitious materials to be used.

90-2.02 AGGREGATES

- Aggregates shall be free from deleterious coatings, clay balls, roots, bark, sticks, rags, and other extraneous material.
- The Contractor shall provide safe and suitable facilities, including necessary splitting devices for obtaining samples of aggregates, in conformance with California Test 125.
 - Aggregates shall be of such character that it will be possible to produce workable concrete within the limits of water content provided in Section 90-6.06, "Amount of Water and Penetration."
 - Aggregates shall have not more than 10 percent loss when tested for soundness in conformance with the requirements in California Test 214. The soundness requirement for fine aggregate will be waived, provided that the durability index, D_f , of the fine aggregate is 60 or greater when tested for durability in conformance with California Test 229.
 - If the results of any one or more of the Cleanness Value, Sand Equivalent, or aggregate grading tests do not meet the requirements specified for "Operating Range" but all meet the "Contract Compliance" requirements, the placement of concrete shall be suspended at the completion of the current pour until tests or other information indicate that the next material to be used in the work will comply with the requirements specified for "Operating Range."

- If the results of either or both the Cleanness Value and coarse aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete that is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State \$4.60 per cubic meter for paving concrete and \$7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

- If the results of either or both the Sand Equivalent and fine aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete that is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State \$4.60 per cubic meter for paving concrete and \$7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

- The 2 preceding paragraphs apply individually to the "Contract Compliance" requirements for coarse aggregate and fine aggregate. When both coarse aggregate and fine aggregate do not conform to the "Contract Compliance" requirements, both paragraphs shall apply. The payments specified in those paragraphs are in addition to any payments made in conformance with the provisions in Section 90-1.01, "Description."

- No single Cleanness Value, Sand Equivalent, or aggregate grading test shall represent more than 250 m³ of concrete or one day's pour, whichever is smaller.

- When the source of an aggregate is changed, the Contractor shall adjust the mix proportions and submit in writing to the Engineer a copy of the mix design before using the aggregates.

90-2.02A COARSE AGGREGATE

- Coarse aggregate shall consist of gravel, crushed gravel, crushed rock, reclaimed aggregate, crushed air-cooled iron blast furnace slag or combinations thereof. Crushed air-cooled blast furnace slag shall not be used in reinforced or prestressed concrete.

- Reclaimed aggregate is aggregate that has been recovered from plastic concrete by washing away the cementitious material. Reclaimed aggregate shall conform to all aggregate requirements.

- Coarse aggregate shall conform to the following quality requirements:

Tests	California Test	Requirements
Loss in Los Angeles Rattler (after 500 revolutions)	211	45% max.
Cleanness Value		
Operating Range	227	75 min.
Contract Compliance	227	71 min.

- In lieu of the above Cleanness Value requirements, a Cleanness Value "Operating Range" limit of 71, minimum, and a Cleanness Value "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the coarse aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

A. Coarse aggregate sampled at the completion of processing at the aggregate production plant had a Cleanness Value of not less than 82 when tested in conformance with the requirements in California Test 227; and

B. Prequalification tests performed in conformance with the requirements in California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.02B FINE AGGREGATE

- Fine aggregate shall consist of natural sand, manufactured sand produced from larger aggregate or a combination thereof. Manufactured sand shall be well graded.

- Fine aggregate shall conform to the following quality requirements:

Test	California Test	Requirements
Organic Impurities	213	Satisfactory ^a
Mortar Strengths Relative to Ottawa Sand	515	95%, min.
Sand Equivalent:		
Operating Range	217	75, min.
Contract Compliance	217	71, min.

- a Fine aggregate developing a color darker than the reference standard color solution may be accepted if it is determined by the Engineer, from mortar strength tests, that a darker color is acceptable.

• In lieu of the above Sand Equivalent requirements, a Sand Equivalent "Operating Range" limit of 71, minimum, and a Sand Equivalent "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the fine aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

- A. Fine aggregate sampled at the completion of processing at the aggregate production plant had a Sand Equivalent value of not less than 82 when tested by California Test 217; and
- B. Prequalification tests performed in conformance with California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.03 WATER

• In conventionally reinforced concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 1000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1300 parts per million of sulfates as SO₄, when tested in conformance with California Test 417. In prestressed concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 650 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1300 parts per million of sulfates as SO₄, when tested in conformance with California Test 417. In no case shall the water contain an amount of impurities that will cause either: 1) a change in the setting time of cement of more than 25 percent when tested in conformance with the requirements in ASTM Designation: C 191 or ASTM Designation: C 266 or 2) a reduction in the compressive strength of mortar at 14 days of more than 5 percent, when tested in conformance with the requirements in ASTM Designation: C 109, when compared to the results obtained with distilled water or deionized water, tested in conformance with the requirements in ASTM Designation: C 109.

• In nonreinforced concrete work, the water for curing, for washing aggregates and for mixing shall be free from oil and shall not contain more than 2000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, or more than 1500 parts per million of sulfates as SO₄, when tested in conformance with California Test 417.

• In addition to the above provisions, water for curing concrete shall not contain impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.

• Water reclaimed from mixer wash-out operations may be used in mixing concrete. The water shall not contain coloring agents or more than 300 parts per million of alkalis (Na₂O + 0.658 K₂O) as determined on the filtrate. The specific gravity of the water shall not exceed 1.03 and shall not vary more than ±0.010 during a day's operations.

90-2.04 ADMIXTURE MATERIALS

- Admixture materials shall conform to the requirements in the following ASTM Designations:
 - A. Chemical Admixtures—ASTM Designation: C 494.
 - B. Air-entraining Admixtures—ASTM Designation: C 260.

90-3 AGGREGATE GRADINGS

90-3.01 GENERAL

• Before beginning concrete work, the Contractor shall submit in writing to the Engineer the gradation of the primary aggregate nominal sizes that the Contractor proposes to furnish. If a primary coarse aggregate or the fine aggregate is separated into 2 or more sizes, the proposed gradation shall consist of the gradation for each individual size, and the proposed proportions of each individual size, combined mathematically to indicate one proposed gradation. The proposed gradation

shall meet the grading requirements shown in the table in this section, and shall show the percentage passing each of the sieve sizes used in determining the end result.

- The Engineer may waive, in writing, the gradation requirements in this Section 90-3.01 and in Sections 90-3.02, "Coarse Aggregate Grading," 90-3.03, "Fine Aggregate Grading," and 90-3.04, "Combined Aggregate Gradings," if, in the Engineer's opinion, furnishing the gradation is not necessary for the type or amount of concrete work to be constructed.

- Gradations proposed by the Contractor shall be within the following percentage passing limits:

Primary Aggregate Nominal Size	Sieve Size	Limits of Proposed Gradation
37.5-mm x 19-mm	25-mm	19 - 41
25-mm x 4.75-mm	19-mm	52 - 85
25-mm x 4.75-mm	9.5-mm	15 - 38
12.5-mm x 4.75-mm	9.5-mm	40 - 78
9.5-mm x 2.36-mm	9.5-mm	50 - 85
Fine Aggregate	1.18-mm	55 - 75
Fine Aggregate	600- μ m	34 - 46
Fine Aggregate	300- μ m	16 - 29

- Should the Contractor change the source of supply, the Contractor shall submit in writing to the Engineer the new gradations before their intended use.

90-3.02 COARSE AGGREGATE GRADING

- The grading requirements for coarse aggregates are shown in the following table for each size of coarse aggregate:

Sieve Sizes	Percentage Passing Primary Aggregate Nominal Sizes							
	37.5-mm x 19-mm		25-mm x 4.75-mm		12.5-mm x 4.75-mm		9.5-mm x 2.36-mm	
	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance
50-mm	100	100	—	—	—	—	—	—
37.5-mm	88 - 100	85 - 100	100	100	—	—	—	—
25-mm	X \pm 18	X \pm 25	88 - 100	86 - 100	—	—	—	—
19-mm	0 - 17	0 - 20	X \pm 15	X \pm 22	100	100	—	—
12.5-mm	—	—	—	—	82 - 100	80 - 100	100	100
9.5-mm	0 - 7	0 - 9	X \pm 15	X \pm 22	X \pm 15	X \pm 22	X \pm 15	X \pm 20
4.75-mm	—	—	0 - 16	0 - 18	0 - 15	0 - 18	0 - 25	0 - 28
2.36-mm	—	—	0 - 6	0 - 7	0 - 6	0 - 7	0 - 6	0 - 7

- In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

- Coarse aggregate for the 37.5-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," shall be furnished in 2 or more primary aggregate nominal sizes. Each primary aggregate nominal size may be separated into 2 sizes and stored separately, provided that the combined material conforms to the grading requirements for that particular primary aggregate nominal size.

- When the 25-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," is to be used, the coarse aggregate may be separated into 2 sizes and stored separately, provided that the combined material shall conform to the grading requirements for the 25-mm x 4.75-mm primary aggregate nominal size.

90-3.03 FINE AGGREGATE GRADING

- Fine aggregate shall be graded within the following limits:

Sieve Sizes	Percentage Passing	
	Operating Range	Contract Compliance
9.5-mm	100	100
4.75-mm	95 - 100	93 - 100
2.36-mm	65 - 95	61 - 99
1.18-mm	X ±10	X ±13
600-µm	X ±9	X ±12
300-µm	X ±6	X ±9
150-µm	2 - 12	1 - 15
75-µm	0 - 8	0 - 10

- In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."
- In addition to the above required grading analysis, the distribution of the fine aggregate sizes shall be such that the difference between the total percentage passing the 1.18-mm sieve and the total percentage passing the 600-µm sieve shall be between 10 and 40, and the difference between the percentage passing the 600-µm and 300-µm sieves shall be between 10 and 40.
- Fine aggregate may be separated into 2 or more sizes and stored separately, provided that the combined material conforms to the grading requirements specified in this Section 90-3.03.

90-3.04 COMBINED AGGREGATE GRADINGS

- Combined aggregate grading limits shall be used only for the design of concrete mixes. Concrete mixes shall be designed so that aggregates are combined in proportions that shall produce a mixture within the grading limits for combined aggregates as specified herein.
- The combined aggregate grading, except when otherwise specified in these specifications or the special provisions, shall be either the 37.5-mm, maximum grading, or the 25-mm, maximum grading, at the option of the Contractor.

Grading Limits of Combined Aggregates

Sieve Sizes	Percentage Passing			
	37.5-mm Max.	25-mm Max.	12.5-mm Max.	9.5-mm Max.
50-mm	100	—	—	—
37.5-mm	90 - 100	100	—	—
25-mm	50 - 86	90 - 100	—	—
19-mm	45 - 75	55 - 100	100	—
12.5-mm	—	—	90-100	100
9.5-mm	38 - 55	45 - 75	55 - 86	50 - 100
4.75-mm	30 - 45	35 - 60	45 - 63	45 - 63
2.36-mm	23 - 38	27 - 45	35 - 49	35 - 49
1.18-mm	17 - 33	20 - 35	25 - 37	25 - 37
600-µm	10 - 22	12 - 25	15 - 25	15 - 25
300-µm	4 - 10	5 - 15	5 - 15	5 - 15
150-µm	1 - 6	1 - 8	1 - 8	1 - 8
75-µm	0 - 3	0 - 4	0 - 4	0 - 4

- Changes from one grading to another shall not be made during the progress of the work unless permitted by the Engineer.

90-4 ADMIXTURES

90-4.01 GENERAL

- Admixtures used in portland cement concrete shall conform to and be used in conformance with the provisions in this Section 90-4 and the special provisions. Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option as provided herein.
- Chemical admixtures and air-entraining admixtures containing chlorides as Cl in excess of one percent by mass of admixture, as determined by California Test 415, shall not be used.

- Admixtures shall be uniform in properties throughout their use in the work. Should it be found that an admixture as furnished is not uniform in properties, its use shall be discontinued.
- If more than one admixture is used, the admixtures shall be compatible with each other so that the desirable effects of all admixtures used will be realized.
- Chemical admixtures shall be used in conformance with the manufacturer's written recommendations.

90-4.02 MATERIALS

- Admixture materials shall conform to the provisions in Section 90-2.04, "Admixture Materials."

90-4.03 ADMIXTURE APPROVAL

- No admixture brand shall be used in the work unless it is on the Department's current list of approved brands for the type of admixture involved.
- Admixture brands will be considered for addition to the approved list if the manufacturer of the admixture submits to the Transportation Laboratory a sample of the admixture accompanied by certified test results demonstrating that the admixture complies with the requirements in the appropriate ASTM Designation and these specifications. The sample shall be sufficient to permit performance of all required tests. Approval of admixture brands will be dependent upon a determination as to compliance with the requirements, based on the certified test results submitted, together with tests the Department may elect to perform.
 - If the Contractor proposes to use an admixture of a brand and type on the current list of approved admixture brands, the Contractor shall furnish a Certificate of Compliance from the manufacturer, as provided in Section 6-1.07, "Certificates of Compliance," certifying that the admixture furnished is the same as that previously approved. If a previously approved admixture is not accompanied by a Certificate of Compliance, the admixture shall not be used in the work until the Engineer has had sufficient time to make the appropriate tests and has approved the admixture for use. The Engineer may take samples for testing at any time, whether or not the admixture has been accompanied by a Certificate of Compliance.

90-4.04 REQUIRED USE OF CHEMICAL ADMIXTURES

- If the use of a chemical admixture is specified, the admixture shall be used at the dosage specified, except that if no dosage is specified, the admixture shall be used at the dosage normally recommended by the manufacturer of the admixture.

90-4.05 OPTIONAL USE OF CHEMICAL ADMIXTURES

- The Contractor may use Type A or F, water-reducing; Type B, retarding; or Type D or G, water-reducing and retarding admixtures as described in ASTM Designation: C 494 to conserve cementitious material or to facilitate any concrete construction application subject to the following conditions:
 - A. If a water-reducing admixture or a water-reducing and retarding admixture is used, the cementitious material content specified or ordered may be reduced by a maximum of 5 percent by mass, except that the resultant cementitious material content shall be not less than 300 kilograms per cubic meter; and
 - B. When a reduction in cementitious material content is made, the dosage of admixture used shall be the dosage used in determining approval of the admixture.
- Unless otherwise specified, a Type C accelerating chemical admixture conforming to the requirements in ASTM Designation: C 494, may be used in portland cement concrete. Inclusion in the mix design submitted for approval will not be required provided that the admixture is added to counteract changing conditions that contribute to delayed setting of the portland cement concrete, and the use or change in dosage of the admixture is approved in writing by the Engineer.

90-4.06 REQUIRED USE OF AIR-ENTRAINING ADMIXTURES

- When air-entrainment is specified or ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce a concrete having the specified air content as determined by California Test 504.

90-4.07 OPTIONAL USE OF AIR-ENTRAINING ADMIXTURES

- When air-entrainment has not been specified or ordered by the Engineer, the Contractor will be permitted to use an air-entraining admixture to facilitate the use of any construction procedure or equipment provided that the average air content, as determined by California Test 504, of 3 successive tests does not exceed 4 percent, and no single test value exceeds 5.5 percent. If the Contractor elects to use an air-entraining admixture in concrete for pavement, the Contractor shall so indicate at the time the Contractor designates the source of aggregate.

90-4.08 BLANK

90-4.09 BLANK

90-4.10 PROPORTIONING AND DISPENSING LIQUID ADMIXTURES

- Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers for liquid admixtures shall have sufficient capacity to measure at one time the prescribed quantity required for each batch of concrete. Each dispenser shall include a graduated measuring unit into which liquid admixtures are measured to within ± 5 percent of the prescribed quantity for each batch. Dispensers shall be located and maintained so that the graduations can be accurately read from the point at which proportioning operations are controlled to permit a visual check of batching accuracy prior to discharge. Each measuring unit shall be clearly marked for the type and quantity of admixture.

- Each liquid admixture dispensing system shall be equipped with a sampling device consisting of a valve located in a safe and readily accessible position such that a sample of the admixture may be withdrawn slowly by the Engineer.

- If more than one liquid admixture is used in the concrete mix, each liquid admixture shall have a separate measuring unit and shall be dispensed by injecting equipment located in such a manner that the admixtures are not mixed at high concentrations and do not interfere with the effectiveness of each other. When air-entraining admixtures are used in conjunction with other liquid admixtures, the air-entraining admixture shall be the first to be incorporated into the mix, unless it is demonstrated that a different sequence improves performance.

- When automatic proportioning devices are required for concrete pavement, dispensers for liquid admixtures shall operate automatically with the batching control equipment. The dispensers shall be equipped with an automatic warning system in good operating condition that will provide a visible or audible signal at the point at which proportioning operations are controlled when the quantity of admixture measured for each batch of concrete varies from the preselected dosage by more than 5 percent, or when the entire contents of the measuring unit are not emptied from the dispenser into each batch of concrete.

- Unless liquid admixtures are added to premeasured water for the batch, their discharge into the batch shall be arranged to flow into the stream of water so that the admixtures are well dispersed throughout the batch, except that air-entraining admixtures may be dispensed directly into moist sand in the batching bins provided that adequate control of the air content of the concrete can be maintained.

- Liquid admixtures requiring dosages greater than 2.5 L/m^3 shall be considered to be water when determining the total amount of free water as specified in Section 90-6.06, "Amount of Water and Penetration."

90-4.11 BLANK

90-5 PROPORTIONING

90-5.01 STORAGE OF AGGREGATES

- Aggregates shall be stored or stockpiled in such a manner that separation of coarse and fine particles of each size shall be avoided and the various sizes shall not become intermixed before proportioning.

- Aggregates shall be stored or stockpiled and handled in a manner that prevent contamination by foreign materials. In addition, storage of aggregates at batching or mixing facilities that are erected subsequent to the award of the contract and that furnish concrete to the project shall conform to the following:

- A. Intermingling of the different sizes of aggregates shall be positively prevented. The Contractor shall take the necessary measures to prevent intermingling. The preventive measures may include, but are not necessarily limited to, physical separation of stockpiles or construction of bulkheads of adequate length and height; and

- B. Contamination of aggregates by contact with the ground shall be positively prevented. The Contractor shall take the necessary measures to prevent contamination. The preventive measures shall include, but are not necessarily limited to, placing aggregates on wooden platforms or on hardened surfaces consisting of portland cement concrete, asphalt concrete, or cement treated material.

- In placing aggregates in storage or in moving the aggregates from storage to the weigh hopper of the batching plant, any method that may cause segregation, degradation, or the combining of materials of different gradings that will result in any size of aggregate at the weigh hopper failing to meet the grading requirements shall be discontinued. Any method of handling aggregates that results in excessive breakage of particles shall be discontinued. The use of suitable devices to reduce impact of falling aggregates may be required by the Engineer.

90-5.02 PROPORTIONING DEVICES

- Weighing, measuring, or metering devices used for proportioning materials shall conform to the requirements in Section 9-1.01, "Measurement of Quantities," and this Section 90-5.02. In addition, automatic weighing systems shall comply with the requirements for automatic proportioning devices in Section 90-5.03A, "Proportioning for Pavement." Automatic devices shall be automatic to the extent that the only manual operation required for proportioning the aggregates, cement, and supplementary cementitious material for one batch of concrete is a single operation of a switch or starter.

- Proportioning devices shall be tested as frequently as the Engineer may deem necessary to ensure their accuracy.

- Weighing equipment shall be insulated against vibration or movement of other operating equipment in the plant. When the plant is in operation, the mass of each batch of material shall not vary from the mass designated by the Engineer by more than the tolerances specified herein.

- Equipment for cumulative weighing of aggregate shall have a zero tolerance of ± 0.5 percent of the designated total batch mass of the aggregate. For systems with individual weigh hoppers for the various sizes of aggregate, the zero tolerance shall be ± 0.5 percent of the individual batch mass designated for each size of aggregate. Equipment for cumulative weighing of cement and supplementary cementitious material shall have a zero tolerance of ± 0.5 percent of the designated total batch mass of the cement and supplementary cementitious material. Equipment for weighing cement or supplementary cementitious material separately shall have a zero tolerance of ± 0.5 percent of their designated individual batch masses. Equipment for measuring water shall have a zero tolerance of ± 0.5 percent of its designated mass or volume.

- The mass indicated for any batch of material shall not vary from the preselected scale setting by more than the following:

- A. Aggregate weighed cumulatively shall be within 1.0 percent of the designated total batch mass of the aggregate. Aggregates weighed individually shall be within 1.5 percent of their respective designated batch masses; and
- B. Cement shall be 99 to 102 percent of its designated batch mass. When weighed individually, supplementary cementitious material shall be 99 to 102 percent of its designated batch mass. When supplementary cementitious material and cement are permitted to be weighed cumulatively, cement shall be weighed first to 99 to 102 percent of its designated batch mass, and the total for cement and supplementary cementitious material shall be 99 to 102 percent of the sum of their designated batch masses; and
- C. Water shall be within 1.5 percent of its designated mass or volume.

- Each scale graduation shall be approximately 0.001 of the total capacity of the scale. The capacity of scales for weighing cement, supplementary cementitious material, or cement plus supplementary cementitious material and aggregates shall not exceed that of commercially available scales having single graduations indicating a mass not exceeding the maximum permissible mass variation above, except that no scale shall be required having a capacity of less than 500 kg, with 0.5-kg graduations.

90-5.03 PROPORTIONING

- Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cementitious material and water as provided in these specifications. Aggregates shall be proportioned by mass.

- At the time of batching, aggregates shall have been dried or drained sufficiently to result in a stable moisture content such that no visible separation of water from aggregate will take place during transportation from the proportioning plant to the point of mixing. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry mass.

- Should separate supplies of aggregate material of the same size group, but of different moisture content or specific gravity or surface characteristics affecting workability, be available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another.

- Bulk Type IP (MS) cement shall be weighed in an individual hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer.

- Bulk cement and supplementary cementitious material may be weighed in separate, individual weigh hoppers or may be weighed in the same weigh hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer. If the cement and supplementary cementitious material are weighed cumulatively, the cement shall be weighed first.

- If cement and supplementary cementitious material are weighed in separate weigh hoppers, the weigh systems for the proportioning of the aggregate, the cement, and the supplementary cementitious material shall be individual and distinct from all other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and independent material weighing device. The cement and the supplementary cementitious material shall be discharged into the mixer simultaneously with the aggregate.

- The scales and weigh hoppers for bulk weighing cement, supplementary cementitious material, or cement plus supplementary cementitious material shall be separate and distinct from the aggregate weighing equipment.
- For batches of one cubic meter or more, the batching equipment shall conform to one of the following combinations:
 - A. Separate boxes and separate scale and indicator for weighing each size of aggregate.
 - B. Single box and scale indicator for all aggregates.
 - C. Single box or separate boxes and automatic weighing mechanism for all aggregates.
- In order to check the accuracy of batch masses, the gross mass and tare mass of batch trucks, truck mixers, truck agitators, and non-agitating hauling equipment shall be determined when ordered by the Engineer. The equipment shall be weighed on scales designated by the Engineer.

90-5.03A PROPORTIONING FOR PAVEMENT

- Aggregates and bulk supplementary cementitious material for use in pavement shall be proportioned by mass by means of automatic proportioning devices of approved type conforming to these specifications.
 - The Contractor shall install and maintain in operating condition an electronically actuated moisture meter that will indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched within a sensitivity of 0.5 percent by mass of the fine aggregate.
 - The batching of cement, supplementary cementitious material, or cement plus supplementary cementitious material and aggregate shall be interlocked so that a new batch cannot be started until all weigh hoppers are empty, the proportioning devices are within zero tolerance, and the discharge gates are closed. The interlock shall permit no part of the batch to be discharged until all aggregate hoppers and the cement and supplementary cementitious material hoppers or the cement plus supplementary cementitious material hopper are charged with masses that are within the tolerances specified in Section 90-5.02, "Proportioning Devices."
 - If interlocks are required for cement and supplementary cementitious material charging mechanisms and cement and supplementary cementitious material are weighed cumulatively, their charging mechanisms shall be interlocked to prevent the introduction of mineral admixture until the mass of cement in the cement weigh hopper is within the tolerances specified in Section 90-5.02, "Proportioning Devices."
 - If concrete is completely mixed in stationary paving mixers, the supplementary cementitious materials shall be weighed in a separate weigh hopper and the supplementary cementitious material and cement shall be introduced simultaneously into the mixer proportionately with the aggregate. If the Contractor provides certification that the stationary mixer is capable of mixing the cement, supplementary cementitious material, aggregates, and water uniformly before discharge, weighing the supplementary cementitious material cumulatively with the cement is permitted. Certification shall contain the following:
 - A. Test results for 2 compressive strength test cylinders of concrete taken within the first one-third and 2 compressive strength test cylinders of concrete taken within the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength";
 - B. Calculations demonstrating that the difference in the averages of 2 compressive strengths taken in the first one-third is no greater than 7.5 percent different than the averages of 2 compressive strengths taken in the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;" and
 - C. The mixer rotation speed and time of mixing before discharge that are required to produce a mix that meets the requirements above.
- The discharge gate on the cement and supplementary cementitious material hoppers or the cement plus supplementary cementitious material hopper shall be designed to permit regulating the flow of cement, supplementary cementitious material, or cement plus supplementary cementitious material into the aggregate as directed by the Engineer.
 - If separate weigh boxes are used for each size of aggregate, the discharge gates shall permit regulating the flow of each size of aggregate as directed by the Engineer.
 - Material discharged from the several bins shall be controlled by gates or by mechanical conveyors. The means of withdrawal from the several bins, and of discharge from the weigh box, shall be interlocked so that not more than one bin can discharge at a time, and so that the weigh box cannot be tripped until the required quantity from each of the several bins has been deposited therein. Should a separate weigh box be used for each size of aggregate, all may be operated and discharged simultaneously.
 - If the discharge from the several bins is controlled by gates, each gate shall be actuated automatically so that the required mass is discharged into the weigh box, after which the gate shall automatically close and lock.

- The automatic weighing system shall be designed so that all proportions required may be set on the weighing controller at the same time.

90-6 MIXING AND TRANSPORTING

90-6.01 GENERAL

- Concrete shall be mixed in mechanically operated mixers, except that when permitted by the Engineer, batches not exceeding 0.25-m³ may be mixed by hand methods in conformance with the provisions in Section 90-6.05, "Hand-Mixing."
- Equipment having components made of aluminum or magnesium alloys that would have contact with plastic concrete during mixing, transporting, or pumping of portland cement concrete shall not be used.
- Concrete shall be homogeneous and thoroughly mixed, and there shall be no lumps or evidence of undispersed cementitious material.
- Uniformity of concrete mixtures will be determined by differences in penetration as determined by California Test 533, or slump as determined by ASTM Designation: C 143, and by variations in the proportion of coarse aggregate as determined by California Test 529.
- When the mix design specifies a penetration value, the difference in penetration, determined by comparing penetration tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed 10 mm. When the mix design specifies a slump value, the difference in slump, determined by comparing slump tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed the values given in the table below. Variation in the proportion of coarse aggregate will be determined by comparing the results of tests of 2 samples of mixed concrete from the same batch or truck mixer load and the difference between the 2 results shall not exceed 100 kg per cubic meter of concrete.

Average Slump	Maximum Permissible Difference
Less than 100-mm	25-mm
100-mm to 150-mm	38-mm
Greater than 150-mm to 225-mm	50-mm

- The Contractor shall furnish samples of the freshly mixed concrete and provide satisfactory facilities for obtaining the samples.

90-6.02 MACHINE MIXING

- Concrete mixers may be of the revolving drum or the revolving blade type, and the mixing drum or blades shall be operated uniformly at the mixing speed recommended by the manufacturer. Mixers and agitators that have an accumulation of hard concrete or mortar shall not be used.
- The temperature of mixed concrete, immediately before placing, shall be not less than 10°C or more than 32°C. Aggregates and water shall be heated or cooled as necessary to produce concrete within these temperature limits. Neither aggregates nor mixing water shall be heated to exceed 65°C. If ice is used to cool the concrete, discharge of the mixer will not be permitted until all ice is melted.
- The batch shall be so charged into the mixer that some water will enter in advance of cementitious materials and aggregates. All water shall be in the drum by the end of the first one-fourth of the specified mixing time.
- Cementitious materials shall be batched and charged into the mixer by means that will not result either in loss of cementitious materials due to the effect of wind, in accumulation of cementitious materials on surfaces of conveyors or hoppers, or in other conditions that reduce or vary the required quantity of cementitious material in the concrete mixture.
- Paving and stationary mixers shall be operated with an automatic timing device. The timing device and discharge mechanism shall be interlocked so that during normal operation no part of the batch will be discharged until the specified mixing time has elapsed.
- The total elapsed time between the intermingling of damp aggregates and all cementitious materials and the start of mixing shall not exceed 30 minutes.
- The size of batch shall not exceed the manufacturer's guaranteed capacity.
- When producing concrete for pavement or base, suitable batch counters shall be installed and maintained in good operating condition at job site batching plants and stationary mixers. The batch counters shall indicate the exact number of batches proportioned and mixed.
- Concrete shall be mixed and delivered to the job site by means of one of the following combinations of operations:
 - A. Mixed completely in a stationary mixer and the mixed concrete transported to the point of delivery in truck agitators or in nonagitating hauling equipment (central-mixed concrete).
 - B. Mixed partially in a stationary mixer, and the mixing completed in a truck mixer (shrink-mixed concrete).

- C. Mixed completely in a truck mixer (transit-mixed concrete).
- D. Mixed completely in a paving mixer.

- Agitators may be truck mixers operating at agitating speed or truck agitators. Each mixer and agitator shall have attached thereto in a prominent place a metal plate or plates on which is plainly marked the various uses for which the equipment is designed, the manufacturer's guaranteed capacity of the drum or container in terms of the volume of mixed concrete and the speed of rotation of the mixing drum or blades.

- Truck mixers shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified.

- When shrink-mixed concrete is furnished, concrete that has been partially mixed at a central plant shall be transferred to a truck mixer and all requirements for transit-mixed concrete shall apply. No credit in the number of revolutions at mixing speed will be allowed for partial mixing in a central plant.

90-6.03 TRANSPORTING MIXED CONCRETE

- Mixed concrete may be transported to the delivery point in truck agitators or truck mixers operating at the speed designated by the manufacturer of the equipment as agitating speed, or in nonagitating hauling equipment, provided the consistency and workability of the mixed concrete upon discharge at the delivery point is suitable for adequate placement and consolidation in place, and provided the mixed concrete after hauling to the delivery point conforms to the provisions in Section 90-6.01, "General."

- Truck agitators shall be loaded not to exceed the manufacturer's guaranteed capacity and shall maintain the mixed concrete in a thoroughly mixed and uniform mass during hauling.

- Bodies of nonagitating hauling equipment shall be constructed so that leakage of the concrete mix, or any part thereof, will not occur at any time.

- Concrete hauled in open-top vehicles shall be protected during hauling against rain or against exposure to the sun for more than 20 minutes when the ambient temperature exceeds 24°C.

- No additional mixing water shall be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer. If the Engineer authorizes additional water to be incorporated into the concrete, the drum shall be revolved not less than 30 revolutions at mixing speed after the water is added and before discharge is commenced.

- The rate of discharge of mixed concrete from truck mixer-agitators shall be controlled by the speed of rotation of the drum in the discharge direction with the discharge gate fully open.

- If a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be completed within 1.5 hours or before 250 revolutions of the drum or blades, whichever occurs first, after the introduction of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or if the temperature of the concrete is 30°C or above, the time allowed may be less than 1.5 hours. If an admixture is used to retard the set time, the temperature of the concrete shall not exceed 30°C, the time limit shall be 2 hours, and the revolution limitation shall be 300.

- If nonagitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be completed within one hour after the addition of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

- Each load of concrete delivered at the job site shall be accompanied by a weighmaster certificate showing the mix identification number, nonrepeating load number, date and time at which the materials were batched, the total amount of water added to the load, and for transit-mixed concrete, the reading of the revolution counter at the time the truck mixer is charged with cement. This weighmaster certificate shall also show the actual scale masses (kilograms) for the ingredients batched. Theoretical or target batch masses shall not be used as a substitute for actual scale masses.

- Weighmaster certificates shall be provided in printed form, or if approved by the Engineer, the data may be submitted in electronic media. Electronic media shall be presented in a tab-delimited format on a 90 mm diskette with a capacity of at least 1.4 megabytes. Captured data, for the ingredients represented by each batch shall be "line feed, carriage return" (LFCR) and "one line, separate record" with allowances for sufficient fields to satisfy the amount of data required by these specifications.

- The Contractor may furnish a weighmaster certificate accompanied by a separate certificate that lists the actual batch masses or measurements for a load of concrete provided that both certificates are imprinted with the same nonrepeating load number that is unique to the contract and delivered to the job site with the load.

- Weighmaster certificates furnished by the Contractor shall conform to the provisions in Section 9-1.01, "Measurement of Quantities."

90-6.04 TIME OR AMOUNT OF MIXING

- Mixing of concrete in paving or stationary mixers shall continue for the required mixing time after all ingredients, except water and admixture, if added with the water, are in the mixing compartment of the mixer before any part of the batch is released. Transfer time in multiple drum mixers shall not be counted as part of the required mixing time.
- The required mixing time, in paving or stationary mixers, of concrete used for concrete structures, except minor structures, shall be not less than 90 seconds or more than 5 minutes, except that when directed by the Engineer in writing, the requirements of the following paragraph shall apply.
- The required mixing time, in paving or stationary mixers, except as provided in the preceding paragraph, shall be not less than 50 seconds or more than 5 minutes.
- The minimum required revolutions at the mixing speed for transit-mixed concrete shall not be less than that recommended by the mixer manufacturer, but in no case shall the number of revolutions be less than that required to consistently produce concrete conforming to the provisions for uniformity in Section 90-6.01, "General."
- When a high range water-reducing admixture is added to the concrete at the job site, the total number of revolutions shall not exceed 300.

90-6.05 HAND-MIXING

- Hand-mixed concrete shall be made in batches of not more than 0.25-m³ and shall be mixed on a watertight, level platform. The proper amount of coarse aggregate shall be measured in measuring boxes and spread on the platform and the fine aggregate shall be spread on this layer, the 2 layers being not more than 0.3-meters in total depth. On this mixture shall be spread the dry cementitious materials and the whole mass turned no fewer than 2 times dry; then sufficient clean water shall be added, evenly distributed, and the whole mass again turned no fewer than 3 times, not including placing in the carriers or forms.

90-6.06 AMOUNT OF WATER AND PENETRATION

- The amount of water used in concrete mixes shall be regulated so that the penetration of the concrete as determined by California Test 533 or the slump of the concrete as determined by ASTM Designation: C 143 is within the nominal values shown in the following table. When the penetration or slump of the concrete is found to exceed the nominal values listed, the mixture of subsequent batches shall be adjusted to reduce the penetration or slump to a value within the nominal range shown. Batches of concrete with a penetration or slump exceeding the maximum values listed shall not be used in the work. If Type F or Type G chemical admixtures are added to the mix, the penetration requirements shall not apply and the slump shall not exceed 225 mm after the chemical admixtures are added.

Type of Work	Nominal		Maximum	
	Penetration (mm)	Slump (mm)	Penetration (mm)	Slump (mm)
Concrete Pavement	0 - 25	—	40	—
Non-reinforced concrete facilities	0 - 35	—	50	—
Reinforced concrete structures				
Sections over 300-mm thick	0 - 35	—	65	—
Sections 300-mm thick or less	0 - 50	—	75	—
Concrete placed under water	—	150 - 200	—	225
Cast-in-place concrete piles	65 - 90	130 - 180	100	200

- The amount of free water used in concrete shall not exceed 183 kg/m³, plus 20 kg for each required 100 kg of cementitious material in excess of 325 kg/m³.
- The term free water is defined as the total water in the mixture minus the water absorbed by the aggregates in reaching a saturated surface-dry condition.
- If there are adverse or difficult conditions that affect the placing of concrete, the above specified penetration and free water content limitations may be exceeded providing the Contractor is granted permission by the Engineer in writing to increase the cementitious material content per cubic meter of concrete. The increase in water and cementitious material shall be at a ratio not to exceed 30 kg of water per added 100 kg of cementitious material per cubic meter. Full compensation for additional cementitious material and water added under these conditions shall be considered as included in the contract price paid for the concrete work involved and no additional compensation will be allowed therefor.

- The equipment for supplying water to the mixer shall be constructed and arranged so that the amount of water added can be measured accurately. Any method of discharging water into the mixer for a batch shall be accurate within 1.5 percent of the quantity of water required to be added to the mix for any position of the mixer. Tanks used to measure water shall be designed so that water cannot enter while water is being discharged into the mixer and discharge into the mixer shall be made rapidly in one operation without dribbling. All equipment shall be arranged so as to permit checking the amount of water delivered by discharging into measured containers.

90-7 CURING CONCRETE

90-7.01 METHODS OF CURING

- Newly placed concrete shall be cured by the methods specified in this Section 90-7.01 and the special provisions.

90-7.01A WATER METHOD

- The concrete shall be kept continuously wet by the application of water for a minimum curing period of 7 days after the concrete has been placed.

- Cotton mats, rugs, carpets, or earth or sand blankets may be used as a curing medium to retain the moisture during the curing period.

- If a curing medium consisting of cotton mats, rugs, carpets, polyethylene sheeting, polyethylene sheeting on burlap, or earth or sand blankets is to be used to retain the moisture, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. The moisture from the nozzle shall not be applied under pressure directly upon the concrete and shall not be allowed to accumulate on the concrete in a quantity sufficient to cause a flow or wash the surface. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing media.

- At the option of the Contractor, a curing medium consisting of white opaque polyethylene sheeting extruded onto burlap may be used to cure concrete structures. The polyethylene sheeting shall have a minimum thickness of 100 µm, and shall be extruded onto 283.5-gram burlap.

- At the option of the Contractor, a curing medium consisting of polyethylene sheeting may be used to cure concrete columns. The polyethylene sheeting shall have a minimum thickness of 250 µm achieved in a single layer of material.

- If the Contractor chooses to use polyethylene sheeting or polyethylene sheeting on burlap as a curing medium, these media and any joints therein shall be secured as necessary to provide moisture retention and shall be within 75 mm of the concrete at all points along the surface being cured. When these media are used, the temperature of the concrete shall be monitored during curing. If the temperature of the concrete cannot be maintained below 60°C, use of these curing media shall be disallowed.

- When concrete bridge decks and flat slabs are to be cured without the use of a curing medium, the entire surface of the bridge deck or slab shall be kept damp by the application of water with an atomizing nozzle as specified above, until the concrete has set, after which the entire surface of the concrete shall be sprinkled continuously with water for a period of not less than 7 days.

90-7.01B CURING COMPOUND METHOD

- Surfaces of the concrete that are exposed to the air shall be sprayed uniformly with a curing compound.
- Curing compounds to be used shall be as follows:

1. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B, except the resin type shall be poly-alpha-methylstyrene.
2. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B.
3. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class A.
4. Nonpigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class B.
5. Nonpigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class A.
6. Nonpigmented curing compound with fugitive dye conforming to the requirements in ASTM Designation: C 309, Type 1-D, Class A.

- The infrared scan for the dried vehicle from curing compound (1) shall match the infrared scan on file at the Transportation Laboratory.

- The loss of water for each type of curing compound, when tested in conformance with the requirements in California Test 534, shall not be more than 0.15-kg/m² in 24 hours.

- The curing compound to be used will be specified elsewhere in these specifications or in the special provisions.

- If the use of curing compound is required or permitted elsewhere in these specifications or in the special provisions and no specific kind is specified, any of the curing compounds listed above may be used.
- Curing compound shall be applied at a nominal rate of 3.7 m²/L, unless otherwise specified.
- At any point, the application rate shall be within ±1.2 m²/L of the nominal rate specified, and the average application rate shall be within ±0.5 m²/L of the nominal rate specified when tested in conformance with the requirements in California Test 535. Runs, sags, thin areas, skips, or holidays in the applied curing compound shall be evidence that the application is not satisfactory.
- Curing compounds shall be applied using power operated spray equipment. The power operated spraying equipment shall be equipped with an operational pressure gage and a means of controlling the pressure. Hand spraying of small and irregular areas that are not reasonably accessible to mechanical spraying equipment, in the opinion of the Engineer, may be permitted.
- The curing compound shall be applied to the concrete following the surface finishing operation, immediately before the moisture sheen disappears from the surface, but before any drying shrinkage or craze cracks begin to appear. In the event of any drying or cracking of the surface, application of water with an atomizing nozzle as specified in Section 90-7.01A, "Water Method," shall be started immediately and shall be continued until application of the compound is resumed or started; however, the compound shall not be applied over any resulting freestanding water. Should the film of compound be damaged from any cause before the expiration of 7 days after the concrete is placed in the case of structures and 72 hours in the case of pavement, the damaged portion shall be repaired immediately with additional compound.
- At the time of use, compounds containing pigments shall be in a thoroughly mixed condition with the pigment uniformly dispersed throughout the vehicle. A paddle shall be used to loosen all settled pigment from the bottom of the container, and a power driven agitator shall be used to disperse the pigment uniformly throughout the vehicle.
- Agitation shall not introduce air or other foreign substance into the curing compound.
- The manufacturer shall include in the curing compound the necessary additives for control of sagging, pigment settling, leveling, de-emulsification, or other requisite qualities of a satisfactory working material. Pigmented curing compounds shall be manufactured so that the pigment does not settle badly, does not cake or thicken in the container, and does not become granular or curdled. Settlement of pigment shall be a thoroughly wetted, soft, mushy mass permitting the complete and easy vertical penetration of a paddle. Settled pigment shall be easily redispersed, with minimum resistance to the sideways manual motion of the paddle across the bottom of the container, to form a smooth uniform product of the proper consistency.
- Curing compounds shall remain sprayable at temperatures above 4°C and shall not be diluted or altered after manufacture.
- The curing compound shall be packaged in clean 1040-L totes, 210-L barrels, or 19-L pails, or shall be supplied from a suitable storage tank located at the job site. The containers shall comply with "Title 49, Code of Federal Regulations, Hazardous Materials Regulations." The 1040-L totes and the 210-L barrels shall have removable lids and airtight fasteners. The 19-L pails shall be round and have standard full open head and bail. Lids with bungholes will not be permitted. Settling or separation of solids in containers, except tanks, must be completely redispersed with low speed mixing prior to use, in conformance with these specifications and the manufacturer's recommendations. Mixing shall be accomplished either manually by use of a paddle or by use of a mixing blade driven by a drill motor, at low speed. Mixing blades shall be the type used for mixing paint. On-site storage tanks shall be kept clean and free of contaminants. Each tank shall have a permanent system designed to completely redisperse settled material without introducing air or other foreign substances.
- Steel containers and lids shall be lined with a coating that will prevent destructive action by the compound or chemical agents in the air space above the compound. The coating shall not come off the container or lid as skins. Containers shall be filled in a manner that will prevent skinning. Plastic containers shall not react with the compound.
- Each container shall be labeled with the manufacturer's name, kind of curing compound, batch number, volume, date of manufacture, and volatile organic compound (VOC) content. The label shall also warn that the curing compound containing pigment shall be well stirred before use. Precautions concerning the handling and the application of curing compound shall be shown on the label of the curing compound containers in conformance with the Construction Safety Orders and General Industry Safety Orders of the State.
- Containers of curing compound shall be labeled to indicate that the contents fully comply with the rules and regulations concerning air pollution control in the State.
- When the curing compound is shipped in tanks or tank trucks, a shipping invoice shall accompany each load. The invoice shall contain the same information as that required herein for container labels.
- Curing compound will be sampled by the Engineer at the source of supply, at the job site, or at both locations.
- Curing compound shall be formulated so as to maintain the specified properties for a minimum of one year. The Engineer may require additional testing before use to determine compliance with these specifications if the compound has not been used within one year or whenever the Engineer has reason to believe the compound is no longer satisfactory.
- Tests will be conducted in conformance with the latest ASTM test methods and methods in use by the Transportation Laboratory.

90-7.01C WATERPROOF MEMBRANE METHOD

- The exposed finished surfaces of concrete shall be sprayed with water, using a nozzle that so atomizes the flow that a mist and not a spray is formed, until the concrete has set, after which the curing membrane, shall be placed. The curing membrane shall remain in place for a period of not less than 72 hours.
- Sheeting material for curing concrete shall conform to the requirements in AASHTO Designation: M 171 for white reflective materials.
- The sheeting material shall be fabricated into sheets of such width as to provide a complete cover for the entire concrete surface. Joints in the sheets shall be securely cemented together in such a manner as to provide a waterproof joint. The joint seams shall have a minimum lap of 100 mm.
- The sheets shall be securely weighted down by placing a bank of earth on the edges of the sheets or by other means satisfactory to the Engineer.
- Should any portion of the sheets be broken or damaged before the expiration of 72 hours after being placed, the broken or damaged portions shall be immediately repaired with new sheets properly cemented into place.
- Sections of membrane that have lost their waterproof qualities or have been damaged to such an extent as to render them unfit for curing the concrete shall not be used.

90-7.01D FORMS-IN-PLACE METHOD

- Formed surfaces of concrete may be cured by retaining the forms in place. The forms shall remain in place for a minimum period of 7 days after the concrete has been placed, except that for members over 0.5-m in least dimension the forms shall remain in place for a minimum period of 5 days.
- Joints in the forms and the joints between the end of forms and concrete shall be kept moisture tight during the curing period. Cracks in the forms and cracks between the forms and the concrete shall be resealed by methods subject to the approval of the Engineer.

90-7.02 CURING PAVEMENT

- The entire exposed area of the pavement, including edges, shall be cured by the waterproof membrane method, or curing compound method using curing compound (1) or (2) as the Contractor may elect. Should the side forms be removed before the expiration of 72 hours following the start of curing, the exposed pavement edges shall also be cured. If the pavement is cured by means of the curing compound method, the sawcut and all portions of the curing compound that have been disturbed by sawing operations shall be restored by spraying with additional curing compound.
- Curing shall commence as soon as the finishing process provided in Section 40-1.10, "Final Finishing," has been completed. The method selected shall conform to the provisions in Section 90-7.01, "Methods of Curing."
- When the curing compound method is used, the compound shall be applied to the entire pavement surface by mechanical sprayers. Spraying equipment shall be of the fully atomizing type equipped with a tank agitator that provides for continual agitation of the curing compound during the time of application. The spray shall be adequately protected against wind, and the nozzles shall be so oriented or moved mechanically transversely as to result in the minimum specified rate of coverage being applied uniformly on exposed faces. Hand spraying of small and irregular areas, and areas inaccessible to mechanical spraying equipment, in the opinion of the Engineer, will be permitted. When the ambient air temperature is above 15°C, the Contractor shall fog the surface of the concrete with a fine spray of water as specified in Section 90-7.01A, "Water Method." The surface of the pavement shall be kept moist between the hours of 10:00 a.m. and 4:30 p.m. on the day the concrete is placed. However, the fogging done after the curing compound has been applied shall not begin until the compound has set sufficiently to prevent displacement. Fogging shall be discontinued if ordered in writing by the Engineer.

90-7.03 CURING STRUCTURES

- Newly placed concrete for cast-in-place structures, other than highway bridge decks, shall be cured by the water method, the forms-in-place method, or, as permitted herein, by the curing compound method, in conformance with the provisions in Section 90-7.01, "Methods of Curing."
- The curing compound method using a pigmented curing compound may be used on concrete surfaces of construction joints, surfaces that are to be buried underground, and surfaces where only ordinary surface finish is to be applied and on which a uniform color is not required and that will not be visible from a public traveled way. If the Contractor elects to use the curing compound method on the bottom slab of box girder spans, the curing compound shall be curing compound (1).
- The top surface of highway bridge decks shall be cured by both the curing compound method and the water method. The curing compound shall be curing compound (1).
- Concrete surfaces of minor structures, as defined in Section 51-1.02, "Minor Structures," shall be cured by the water method, the forms-in-place method or the curing compound method.

- When deemed necessary by the Engineer during periods of hot weather, water shall be applied to concrete surfaces being cured by the curing compound method or by the forms-in-place method, until the Engineer determines that a cooling effect is no longer required. Application of water for this purpose will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

90-7.04 CURING PRECAST CONCRETE MEMBERS

- Precast concrete members shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing." Curing shall be provided for the minimum time specified for each method or until the concrete reaches its design strength, whichever is less. Steam curing may also be used for precast members and shall conform to the following provisions:

- A. After placement of the concrete, members shall be held for a minimum 4-hour presteaming period. If the ambient air temperature is below 10°C, steam shall be applied during the presteaming period to hold the air surrounding the member at a temperature between 10°C and 32°C.
- B. To prevent moisture loss on exposed surfaces during the presteaming period, members shall be covered as soon as possible after casting or the exposed surfaces shall be kept wet by fog spray or wet blankets.
- C. Enclosures for steam curing shall allow free circulation of steam about the member and shall be constructed to contain the live steam with a minimum moisture loss. The use of tarpaulins or similar flexible covers will be permitted, provided they are kept in good repair and secured in such a manner as to prevent the loss of steam and moisture.
- D. Steam at the jets shall be at low pressure and in a saturated condition. Steam jets shall not impinge directly on the concrete, test cylinders, or forms. During application of the steam, the temperature rise within the enclosure shall not exceed 22°C per hour. The curing temperature throughout the enclosure shall not exceed 65°C and shall be maintained at a constant level for a sufficient time necessary to develop the required transfer strength. Control cylinders shall be covered to prevent moisture loss and shall be placed in a location where temperature is representative of the average temperature of the enclosure.
- E. Temperature recording devices that will provide an accurate, continuous, permanent record of the curing temperature shall be provided. A minimum of one temperature recording device per 60 m of continuous bed length will be required for checking temperature.
- F. Members in pretension beds shall be detensioned immediately after the termination of steam curing while the concrete and forms are still warm, or the temperature under the enclosure shall be maintained above 15°C until the stress is transferred to the concrete.
- G. Curing of precast concrete will be considered completed after termination of the steam curing cycle.

90-7.05 CURING PRECAST PRESTRESSED CONCRETE PILES

- Newly placed concrete for precast prestressed concrete piles shall be cured in conformance with the provisions in Section 90-7.04, "Curing Precast Concrete Members," except that piles in a corrosive environment shall be cured as follows:

- A. Piles shall be either steam cured or water cured. If water curing is used, the piles shall be kept continuously wet by the application of water in conformance with the provisions in Section 90-7.01A, "Water Method."
- B. If steam curing is used, the steam curing provisions in Section 90-7.04, "Curing Precast Concrete Members," shall apply except that the piles shall be kept continuously wet for their entire length for a period of not less than 3 days, including the holding and steam curing periods.

90-7.06 CURING SLOPE PROTECTION

- Concrete slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."
- Concreted-rock slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing," with a blanket of earth kept wet for 72 hours, or by sprinkling with a fine spray of water every 2 hours during the daytime for a period of 3 days.

90-7.07 CURING MISCELLANEOUS CONCRETE WORK

- Exposed surfaces of curbs shall be cured by pigmented curing compounds as specified in Section 90-7.01B, "Curing Compound Method."
- Concrete sidewalks, gutter depressions, island paving, curb ramps, driveways, and other miscellaneous concrete areas shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."
- Shotcrete shall be cured for at least 72 hours by spraying with water, by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

- Mortar and grout shall be cured by keeping the surface damp for 3 days.
- After placing, the exposed surfaces of sign structure foundations, including pedestal portions, if constructed, shall be cured for at least 72 hours by spraying with water, by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

90-8 PROTECTING CONCRETE

90-8.01 GENERAL

- In addition to the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," the Contractor shall protect concrete as provided in this Section 90-8. If required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.
 - The Contractor shall protect concrete from damage from any cause, which shall include, but not be limited to: rain, heat, cold, wind, Contractor's actions, and actions of others.
 - Concrete shall not be placed on frozen or ice-coated ground or subgrade nor on ice-coated forms, reinforcing steel, structural steel, conduits, precast members, or construction joints.
 - Under rainy conditions, placing of concrete shall be stopped before the quantity of surface water is sufficient to damage surface mortar or cause a flow or wash of the concrete surface, unless the Contractor provides adequate protection against damage.
 - Concrete that has been frozen or damaged by other causes, as determined by the Engineer, shall be removed and replaced by the Contractor at the Contractor's expense.

90-8.02 PROTECTING CONCRETE STRUCTURES

- Structure concrete and shotcrete used as structure concrete shall be maintained at a temperature of not less than 7°C for 72 hours after placing and at not less than 4°C for an additional 4 days.

90-8.03 PROTECTING CONCRETE PAVEMENT

- Pavement concrete shall be maintained at a temperature of not less than 4°C for 72 hours.
- Except as provided in Section 7-1.08, "Public Convenience," the Contractor shall protect concrete pavement against construction and other activities that abrade, scar, discolor, reduce texture depth, lower coefficient of friction, or otherwise damage the surface. Stockpiling, drifting, or excessive spillage of soil, gravel, petroleum products, and concrete or asphalt mixes on the surface of concrete pavement is prohibited unless otherwise specified in these specifications, the special provisions or permitted by the Engineer.
 - If ordered by the Engineer or shown on the plans or specified in the special provisions, pavement crossings shall be constructed for the convenience of public traffic. The material and work necessary for the construction of the crossings, and their subsequent removal and disposal, will be paid for at the contract unit prices for the items of work involved and if there are no contract items for the work involved, payment for pavement crossings will be made by extra work as provided in Section 4-1.03D, "Extra Work." Where public traffic will be required to cross over the new pavement, Type III portland cement may be used in concrete, if permitted in writing by the Engineer. The pavement may be opened to traffic as soon as the concrete has developed a modulus of rupture of 3.8 MPa. The modulus of rupture will be determined by California Test 523.
 - No traffic or Contractor's equipment, except as hereinafter provided, will be permitted on the pavement before a period of 10 days has elapsed after the concrete has been placed, nor before the concrete has developed a modulus of rupture of at least 3.8 MPa. Concrete that fails to attain a modulus of rupture of 3.8 MPa within 10 days shall not be opened to traffic until directed by the Engineer.
 - Equipment for sawing weakened plane joints will be permitted on the pavement as specified in Section 40-1.08B, "Weakened Plane Joints."
 - When requested in writing by the Contractor, the tracks on one side of paving equipment will be permitted on the pavement after a modulus of rupture of 2.4 MPa has been attained, provided that:
 - A. Unit pressure exerted on the pavement by the paver shall not exceed 135 kPa;
 - B. Tracks with cleats, grousers, or similar protuberances shall be modified or shall travel on planks or equivalent protective material, so that the pavement is not damaged; and
 - C. No part of the track shall be closer than 0.3-m from the edge of pavement.
- In case of visible cracking of, or other damage to the pavement, operation of the paving equipment on the pavement shall be immediately discontinued.

- Damage to the pavement resulting from early use of pavement by the Contractor's equipment as provided above shall be repaired by the Contractor.
- The State will furnish the molds and machines for testing the concrete for modulus of rupture, and the Contractor, at the Contractor's expense, shall furnish the material and whatever labor the Engineer may require.

90-9 COMPRESSIVE STRENGTH

90-9.01 GENERAL

- Concrete compressive strength requirements consist of a minimum strength that shall be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or the special provisions or are shown on the plans.
- The compressive strength of concrete will be determined from test cylinders that have been fabricated from concrete sampled in conformance with the requirements of California Test 539. Test cylinders will be molded and initially field cured in conformance with California Test 540. Test cylinders will be cured and tested after receipt at the testing laboratory in conformance with the requirements of California Test 521. A strength test shall consist of the average strength of 2 cylinders fabricated from material taken from a single load of concrete, except that, if any cylinder should show evidence of improper sampling, molding, or testing, that cylinder shall be discarded and the strength test shall consist of the strength of the remaining cylinder.
- When concrete compressive strength is specified as a prerequisite to applying loads or stresses to a concrete structure or member, test cylinders for other than steam cured concrete will be cured in conformance with Method 1 of California Test 540. The compressive strength of concrete determined for these purposes will be evaluated on the basis of individual tests.
- When concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete strength to be used as a basis for acceptance of other than steam cured concrete will be determined from cylinders cured in conformance with Method 1 of California Test 540. If the result of a single compressive strength test at the maximum age specified or allowed is below the specified strength but is 95 percent or more of the specified strength, the Contractor shall make corrective changes, subject to approval of the Engineer, in the mix proportions or in the concrete fabrication procedures, before placing additional concrete, and shall pay to the State \$14 for each in-place cubic meter of concrete represented by the deficient test. If the result of a single compressive strength test at the maximum age specified or allowed is below 95 percent of the specified strength, but is 85 percent or more of the specified strength, the Contractor shall make the corrective changes specified above, and shall pay to the State \$20 for each in place cubic meter of concrete represented by the deficient test. In addition, such corrective changes shall be made when the compressive strength of concrete tested at 7 days indicates, in the judgment of the Engineer, that the concrete will not attain the required compressive strength at the maximum age specified or allowed. Concrete represented by a single test that indicates a compressive strength of less than 85 percent of the specified 28-day compressive strength will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials."
- If the test result indicates that the compressive strength at the maximum curing age specified or allowed is below the specified strength, but is 85 percent or more of the specified strength, payments to the State as required above shall be made, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength of the concrete placed in the work meets or exceeds the specified 28-day compressive strength. If the test result indicates a compressive strength at the maximum curing age specified or allowed below 85 percent, the concrete represented by that test will be rejected, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength and quality of the concrete placed in the work are acceptable. If the evidence consists of tests made on cores taken from the work, the cores shall be obtained and tested in conformance with the requirements in ASTM Designation: C 42.
 - No single compressive strength test shall represent more than 250 m³.
 - If a precast concrete member is steam cured, the compressive strength of the concrete will be determined from test cylinders that have been handled and stored in conformance with Method 3 of California Test 540. The compressive strength of steam cured concrete will be evaluated on the basis of individual tests representing specific portions of production. If the concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete shall be considered to be acceptable whenever its compressive strength reaches the specified 28-day compressive strength provided that strength is reached in not more than the maximum number of days specified or allowed after the member is cast.
 - When concrete is specified by compressive strength, prequalification of materials, mix proportions, mixing equipment, and procedures proposed for use will be required prior to placement of the concrete. Prequalification shall be accomplished by the submission of acceptable certified test data or trial batch reports by the Contractor. Prequalification data shall be based on the use of materials, mix proportions, mixing equipment, procedures, and size of batch proposed for use in the work.

- Certified test data, in order to be acceptable, shall indicate that not less than 90 percent of at least 20 consecutive tests exceed the specified strength at the maximum number of cure days specified or allowed, and none of those tests are less than 95 percent of specified strength. Strength tests included in the data shall be the most recent tests made on concrete of the proposed mix design and all shall have been made within one year of the proposed use of the concrete.

- Trial batch test reports, in order to be acceptable, shall indicate that the average compressive strength of 5 consecutive concrete cylinders, taken from a single batch, at not more than 28 days (or the maximum age allowed) after molding shall be at least 4 MPa greater than the specified 28-day compressive strength, and no individual cylinder shall have a strength less than the specified strength at the maximum age specified or allowed. Data contained in the report shall be from trial batches that were produced within one year of the proposed use of specified strength concrete in the project. Whenever air-entrainment is required, the air content of trial batches shall be equal to or greater than the air content specified for the concrete without reduction due to tolerances.

- Tests shall be performed in conformance with either the appropriate California Test methods or the comparable ASTM test methods. Equipment employed in testing shall be in good condition and shall be properly calibrated. If the tests are performed during the life of the contract, the Engineer shall be notified sufficiently in advance of performing the tests in order to witness the test procedures.

- The certified test data and trial batch test reports shall include the following information:

- A. Date of mixing.

- B. Mixing equipment and procedures used.

- C. The size of batch in cubic meters and the mass, type, and source of all ingredients used.

- D. Penetration or slump (if the concrete will be placed under water or placed in cast-in-place concrete piles) of the concrete.

- E. The air content of the concrete if an air-entraining admixture is used.

- F. The age at time of testing and strength of all concrete cylinders tested.

- Certified test data and trial batch test reports shall be signed by an official of the firm that performed the tests.

- When approved by the Engineer, concrete from trial batches may be used in the work at locations where concrete of a lower quality is required and the concrete will be paid for as the type or class of concrete required at that location.

- After materials, mix proportions, mixing equipment, and procedures for concrete have been prequalified for use, additional prequalification by testing of trial batches will be required prior to making changes that, in the judgment of the Engineer, could result in a strength of concrete below that specified.

- The Contractor's attention is directed to the time required to test trial batches and the Contractor shall be responsible for production of trial batches at a sufficiently early date so that the progress of the work is not delayed.

- When precast concrete members are manufactured at the plant of an established manufacturer of precast concrete members, the mix proportions of the concrete shall be determined by the Contractor, and a trial batch and prequalification of the materials, mix proportions, mixing equipment, and procedures will not be required.

90-10 MINOR CONCRETE

90-10.01 GENERAL

- Concrete for minor structures, slope paving, curbs, sidewalks and other concrete work, when designated as minor concrete on the plans, in the specifications, or in the contract item, shall conform to the provisions specified herein.

- The Engineer, at the Engineer's discretion, will inspect and test the facilities, materials and methods for producing the concrete to ensure that minor concrete of the quality suitable for use in the work is obtained.

90-10.02 MATERIALS

- Minor concrete shall conform to the following requirements:

90-10.02A CEMENTITIOUS MATERIAL

- Cementitious material shall conform to the provisions in Section 90-1.01, "Description."

90-10.02B AGGREGATE

- Aggregate shall be clean and free from deleterious coatings, clay balls, roots, and other extraneous materials.

- Use of crushed concrete or reclaimed aggregate is acceptable only if the aggregate satisfies all aggregate requirements.

- The Contractor shall submit to the Engineer for approval, a grading of the combined aggregate proposed for use in the minor concrete. After acceptance of the grading, aggregate furnished for minor concrete shall conform to that grading, unless a change is authorized in writing by the Engineer.

- The Engineer may require the Contractor to furnish periodic test reports of the aggregate grading furnished. The maximum size of aggregate used shall be at the option of the Contractor, but in no case shall the maximum size be larger than 37.5 mm or smaller than 19 mm.

- The Engineer may waive, in writing, the gradation requirements in this Section 90-10.02B, if, in the Engineer's opinion, the furnishing of the gradation is not necessary for the type or amount of concrete work to be constructed.

90-10.02C WATER

- Water used for washing, mixing, and curing shall be free from oil, salts, and other impurities that would discolor or etch the surface or have an adverse affect on the quality of the concrete.

90-10.02D ADMIXTURES

- The use of admixtures shall conform to the provisions in Section 90-4, "Admixtures."

90-10.03 PRODUCTION

- Cementitious material, water, aggregate, and admixtures shall be stored, proportioned, mixed, transported, and discharged in conformance with recognized standards of good practice that will result in concrete that is thoroughly and uniformly mixed, that is suitable for the use intended, and that conforms to requirements specified herein. Recognized standards of good practice are outlined in various industry publications such as are issued by American Concrete Institute, AASHTO, or the Department.

- The cementitious material content of minor concrete shall conform to the provisions in Section 90-1.01, "Description."

- The amount of water used shall result in a consistency of concrete conforming to the provisions in Section 90-6.06, "Amount of Water and Penetration." Additional mixing water shall not be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer.

- Discharge of ready-mixed concrete from the transporting vehicle shall be made while the concrete is still plastic and before stiffening occurs. An elapsed time of 1.5 hours (one hour in nonagitating hauling equipment), or more than 250 revolutions of the drum or blades, after the introduction of the cementitious material to the aggregates, or a temperature of concrete of more than 32°C will be considered conditions contributing to the quick stiffening of concrete. The Contractor shall take whatever action is necessary to eliminate quick stiffening, except that the addition of water will not be permitted.

- The required mixing time in stationary mixers shall be not less than 50 seconds or more than 5 minutes.

- The minimum required revolutions at mixing speed for transit-mixed concrete shall be not less than that recommended by the mixer manufacturer, and shall be increased, if necessary, to produce thoroughly and uniformly mixed concrete.

- When a high range water-reducing admixture is added to the concrete at the job site, the total number of revolutions shall not exceed 300.

- Each load of ready-mixed concrete shall be accompanied by a weighmaster certificate that shall be delivered to the Engineer at the discharge location of the concrete, unless otherwise directed by the Engineer. The weighmaster certificate shall be clearly marked with the date and time of day when the load left the batching plant and, if hauled in truck mixers or agitators, the time the mixing cycle started.

- A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished to the Engineer, prior to placing minor concrete from a source not previously used on the contract, stating that minor concrete to be furnished meets contract requirements, including minimum cementitious material content specified.

90-10.04 CURING MINOR CONCRETE

- Curing minor concrete shall conform to the provisions in Section 90-7, "Curing Concrete."

90-10.05 PROTECTING MINOR CONCRETE

- Protecting minor concrete shall conform to the provisions in Section 90-8, "Protecting Concrete," except the concrete shall be maintained at a temperature of not less than 4°C for 72 hours after placing.

90-10.06 MEASUREMENT AND PAYMENT

- Minor concrete will be measured and paid for in conformance with the provisions specified in the various sections of these specifications covering concrete construction when minor concrete is specified in the specifications, shown on the plans, or indicated by contract item in the Engineer's Estimate.

90-11 MEASUREMENT AND PAYMENT

90-11.01 MEASUREMENT

- Portland cement concrete will be measured in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.
- For concrete measured at the mixer, the volume in cubic meters shall be computed as the total mass of the batch in kilograms divided by the density of the concrete in kilograms per cubic meter. The total mass of the batch shall be calculated as the sum of all materials, including water, entering the batch. The density of the concrete will be determined in conformance with the requirements in California Test 518.

90-11.02 PAYMENT

- Portland cement concrete will be paid for in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.
- Full compensation for furnishing and incorporating admixtures required by these specifications or the special provisions will be considered as included in the contract prices paid for the concrete involved and no additional compensation will be allowed therefor.
- Should the Engineer order the Contractor to incorporate any admixtures in the concrete when their use is not required by these specifications or the special provisions, furnishing the admixtures and adding them to the concrete will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."
- Should the Contractor use admixtures in conformance with the provisions in Section 90-4.05, "Optional Use of Chemical Admixtures," or Section 90-4.07, "Optional Use of Air-entraining Admixtures," or should the Contractor request and obtain permission to use other admixtures for the Contractor's benefit, the Contractor shall furnish those admixtures and incorporate them into the concrete at the Contractor's expense and no additional compensation will be allowed therefor.

SECTION 91: PAINT

Issue Date: November 18, 2005

Section 91-3, "Paints for Timber," of the Standard Specifications is amended to read:

91-3 PAINTS FOR TIMBER

91-3.01 WOOD PRIMER, LATEX-BASE

Classification:

- This specification covers a ready-mixed priming paint for use on unpainted wood or exterior woodwork. It shall conform with the requirements in the Detailed Performance Standards of the Master Painters Institute (MPI) for exterior wood primers, and be listed on the Exterior Latex Wood Primer MPI List Number 6.

91-3.02 PAINT; LATEX-BASE FOR EXTERIOR WOOD, WHITE AND TINTS

Classification:

- This specification covers a ready-mixed paint for use on wood surfaces subject to outside exposures. This paint shall conform to the requirements in the Detailed Performance Standards of the Master Painters Institute (MPI) for Paint, Latex, Exterior, and shall be listed on the following MPI Approved Products List:

- A. Exterior Latex, Flat MPI Gloss Level 1, MPI List Number 10.
- B. Exterior Latex, Semi-Gloss, MPI Gloss Level 5, MPI List Number 11.
- C. Exterior Latex, Gloss, MPI Gloss Level 6, MPI List Number 119.

- Unpainted wood shall first be primed with wood primer conforming to the provisions in Section 91-3.01, "Wood Primer, Latex-Base."

Section 91-4, "Miscellaneous Paints," of the Standard Specifications is amended to read:

91-4 MISCELLANEOUS PAINTS

91-4.01 THROUGH 91-4.04 (BLANK)

91-4.05 PAINT; ACRYLIC EMULSION, EXTERIOR WHITE AND LIGHT AND MEDIUM TINTS

Classification:

- This specification covers an acrylic emulsion paint designed for use on exterior masonry. This paint shall conform to the requirements in the Detailed Performance Standards of the Master Painters Institute (MPI) for Paint, Latex, Exterior, and shall be listed on the following MPI Approved Products Lists:

- A. Exterior Latex, Flat MPI Gloss Level 1, MPI List Number 10.
- B. Exterior Latex, Semi-Gloss, MPI Gloss Level 5, MPI List Number 11.
- C. Exterior Latex, Gloss, MPI Gloss Level 6, MPI List Number 119.

- This paint may be tinted by using "universal" or "all purpose" concentrates.

SECTION 92: ASPHALTS

Issue Date: February 2, 2007

Section 92, "Asphalts," of the Standard Specifications is amended to read:

92-1.01 DESCRIPTION

- Asphalt is refined petroleum or a mixture of refined liquid asphalt and refined solid asphalt that are prepared from crude petroleum. Asphalt is:

1. Free from residues caused by the artificial distillation of coal, coal tar, or paraffin
2. Free from water
3. Homogeneous

92-1.02 MATERIALS

GENERAL

- Furnish asphalt under the Department's "Certification Program for Suppliers of Asphalt." The Department maintains the program requirements, procedures, and a list of approved suppliers at:

<http://www.dot.ca.gov/hq/esc/Translab/fpmcoc.htm>

- Transport, store, use, and dispose of asphalt safely.
- Prevent the formation of carbonized particles caused by overheating asphalt during manufacturing or construction.

GRADES

- Performance graded (PG) asphalt binder is:

Performance Graded Asphalt Binder

Property	AASHTO Test Method	Specification				
		Grade				
		PG 58-22 ^a	PG 64-10	PG 64-16	PG 64-28	PG 70-10
Original Binder						
Flash Point, Minimum °C	T 48	230	230	230	230	230
Solubility, Minimum % ^b	T 44	99	99	99	99	99
Viscosity at 135°C, ^c Maximum, Pa·s	T 316	3.0	3.0	3.0	3.0	3.0
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 1.00	64 1.00	64 1.00	64 1.00	70 1.00
RTFO Test, ^e Mass Loss, Maximum, %	T 240	1.00	1.00	1.00	1.00	1.00
RTFO Test Aged Binder						
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 2.20	64 2.20	64 2.20	64 2.20	70 2.20
Ductility at 25°C Minimum, cm	T 51	75	75	75	75	75
PAV ^f Aging, Temperature, °C	R 28	100	100	100	100	110
RTFO Test and PAV Aged Binder						
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum G*sin(delta), kPa	T 315	22 ^d 5000	31 ^d 5000	28 ^d 5000	22 ^d 5000	34 ^d 5000
Creep Stiffness, Test Temperature, °C Maximum S-value, Mpa Minimum M-value	T 313	-12 300 0.300	0 300 0.300	-6 300 0.300	-18 300 0.300	0 300 0.300

Notes:

- a. Use as asphalt rubber base stock for high mountain and high desert area.
 - b. The Engineer waives this specification if the supplier is a Quality Supplier as defined by the Department's "Certification Program for Suppliers of Asphalt."
 - c. The Engineer waives this specification if the supplier certifies the asphalt binder can be adequately pumped and mixed at temperatures meeting applicable safety standards.
 - d. Test the sample at 3°C higher if it fails at the specified test temperature. G*sin(delta) remains 5000 kPa maximum.
 - e. "RTFO Test" means the asphaltic residue obtained using the Rolling Thin Film Oven Test, AASHTO Test Method T 240 or ASTM Designation: D 2872. The residue from mass change determination may be used for other tests.
 - f. "PAV" means Pressurized Aging Vessel.
- Performance graded polymer modified asphalt binder (PG Polymer Modified) is:

Performance Graded Polymer Modified Asphalt Binder ^a

Property	AASHTO Test Method	Specification Grade		
		PG 58-34 PM	PG 64-28 PM	PG 76-22 PM
Original Binder				
Flash Point, Minimum °C	T 48	230	230	230
Solubility, Minimum % ^b	T 44 ^c	98.5	98.5	98.5
Viscosity at 135°C, ^d Maximum, Pa·s	T 316	3.0	3.0	3.0
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 1.00	64 1.00	76 1.00
RTFO Test , Mass Loss, Maximum, %	T 240	1.00	1.00	1.00
RTFO Test Aged Binder				
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 2.20	64 2.20	76 2.20
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum (delta), %	T 315	Note e 80	Note e 80	Note e 80
Elastic Recovery ^f , Test Temp., °C Minimum recovery, %	T 301	25 75	25 75	25 65
PAV ^g Aging, Temperature, °C	R 28	100	100	110
RTFO Test and PAV Aged Binder				
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum G*sin(delta), kPa	T 315	16 5000	22 5000	31 5000
Creep Stiffness, Test Temperature, °C Maximum S-value, MPa Minimum M-value	T 313	-24 300 0.300	-18 300 0.300	-12 300 0.300

Notes:

- Do not modify PG Polymer Modified using acid modification.
- The Engineer waives this specification if the supplier is a Quality Supplier as defined by the Department's "Certification Program for Suppliers of Asphalt."
- The Department allows ASTM D 5546 instead of AASHTO T 44
- The Engineer waives this specification if the supplier certifies the asphalt binder can be adequately pumped and mixed at temperatures meeting applicable safety standards.
- Test temperature is the temperature at which G*/sin(delta) is 2.2 kPa. A graph of log G*/sin(delta) plotted against temperature may be used to determine the test temperature when G*/sin(delta) is 2.2 kPa. A graph of (delta) versus temperature may be used to determine delta at the temperature when G*/sin(delta) is 2.2 kPa. The Engineer also accepts direct measurement of (delta) at the temperature when G*/sin(delta) is 2.2 kPa.
- Tests without a force ductility clamp may be performed.
- "PAV" means Pressurized Aging Vessel.

SAMPLING

- Provide a sampling device in the asphalt feed line connecting the plant storage tanks to the asphalt weighing system or spray bar. Make the sampling device accessible between 600 and 750 mm above the platform. Provide a receptacle for flushing the sampling device.
 - Include with the sampling device a valve:

1. Between 10 and 20 mm in diameter
2. Manufactured in a manner that a one-liter sample may be taken slowly at any time during plant operations
3. Maintained in good condition

- Replace failed valves.
- In the Engineer's presence, take 2 one-liter samples per operating day. Provide round, friction top, one-liter containers for storing samples.

92-1.03 EXECUTION

- If asphalt is applied, you must comply with the heating and application specifications for liquid asphalt in Section 93, "Liquid Asphalts."

92-1.04 MEASUREMENT

- If the contract work item for asphalt is paid by mass, the Department measures asphalt tonnes by complying with the specifications for mass determination of liquid asphalt in Section 93, "Liquid Asphalts."
 - The Engineer determines the asphalt mass from volumetric measurements if you:

1. Use a partial asphalt load.
2. Use asphalt at a location other than a mixing plant and no scales within 35 km are available and suitable.
3. Deliver asphalt in either of the following:
 - 3.1. A calibrated truck with each tank accompanied by its measuring stick and calibration card.
 - 3.2. A truck equipped with a calibrated thermometer that determines the asphalt temperature at the delivery time and with a vehicle tank meter complying with the specifications for weighing, measuring, and metering devices in Section 9-1.01, "Measurement of Quantities."

- If you furnish asphalt concrete from a mixing plant producing material for only one project, the Engineer determines the asphalt quantity by measuring the volume in the tank at the project's start and end provided the tank is calibrated and equipped with its measuring stick and calibration card.

- The Engineer determines pay quantities from volumetric measurements as follows:
 1. Before converting the volume to mass, the Engineer reduces the measured volume to that which the asphalt would occupy at 15°C.
 2. The Engineer uses 981 L/tonne and 1020 g/L for the average mass and volume for PG and PG Polymer Modified asphalt grades at 15°C.
 3. The Engineer uses the Conversion Table in Section 93, "Liquid Asphalts."

SECTION 93: LIQUID ASPHALTS

Issue Date: November 3, 2006

The ninth paragraph of Section 93-1.04, "Measurement," of the Standard Specifications is amended to read:

- The following Legend and Conversion Table is to be used for converting volumes of liquid asphalt products, Grades 70 to 3000, inclusive, and paving asphalt Grades PG 58-22, PG 64-10, PG 64-16, PG 64-28, and PG 70-10, and Grades PG 58-34 PM, PG 64-28 PM, and PG 76-22 PM.

SECTION 95: EPOXY

Issue Date: March 16, 2007

Section 95, "Epoxy," of the Standard Specifications is amended to read:

95-1 GENERAL

95-1.01 DESCRIPTION

- These specifications are intended to specify epoxy that will meet service requirements for highway construction.
- Epoxy shall be furnished as 2 components, which shall be mixed together at the site of the work.

95-1.02 SAMPLING AND TESTING

- Epoxy shall not be used prior to sampling and testing unless its use is permitted prior to sampling and testing in conformance with the provisions in Section 6-1.07, "Certificates of Compliance."
- Tests will be conducted in conformance with the latest test methods of the American Society for Testing and Materials, and California Test Methods in use by the Transportation Laboratory.
- Epoxy components shall be formulated to maintain the specified properties for a minimum of one year. The Engineer may require additional testing of any epoxy component that has not been used within one year of manufacture.

95-1.03 PACKAGING, LABELING AND STORING

- Each component shall be packaged in containers of size proportional to the amount of that component in the mix so that one container of each component is used in mixing one batch of epoxy. The containers shall be of such design that all of the contents may be readily removed and shall be well sealed to prevent leakage. The containers and labeling shall meet U.S. Department of Transportation Hazardous Material Shipping Regulations, and the containers shall be of a material, or lined with a material, of such character as to resist any action by the components. Each container shall be clearly labeled with the ASTM Designation: C881 Class and Type; designation (Component A or B); manufacturer's name; date of manufacture; batch number (a batch shall consist of a single charge of all components in a mixing chamber); all directions for use (as specified elsewhere) and such warning or precautions concerning the contents as may be required by State or Federal Laws and Regulations. The manufacturer of the finished epoxy components shall furnish a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," and a copy of the label for each material. The certificate shall include a list, by Title and Section, of the State and Federal packaging and labeling laws and regulations that the manufacturer has complied with.
- Attention is directed to the characteristic of some epoxy components to crystallize or thicken excessively prior to use when stored at temperatures below 2°C. Any material which shows evidence of crystallization or a permanent increase in viscosity or settling of pigments which cannot be readily redispersed with a paddle shall not be used.

95-1.04 DIRECTIONS FOR USE

- At the time of mixing, components A and B shall be at a temperature between 15°C and 30°C, unless otherwise specified. Any heating of the adhesive components shall be done by application of indirect heat. Immediately prior to mixing, each component shall be thoroughly mixed with a paddle. Separate paddles shall be used to stir each component. Immediately prior to use, the 2 components shall be thoroughly mixed together in the specified ratios. No solvent shall be added to any epoxy.
- After mixing, epoxies shall be placed in the work and any overlaying or inserted material which is to be bonded to the work by the epoxy shall also be placed before thickening of the epoxy has begun. Surfaces upon which epoxy is to be placed shall be free of rust, paint, grease, asphalt, and loose and deleterious material. When epoxy is used as a binder to make epoxy concrete or mortar, the 2 components of epoxy shall be thoroughly mixed together before the aggregate is added and, unless otherwise specified, the mix proportions shall consist of one part of binder to approximately 4 parts of aggregate, by volume. Aggregate for use in epoxy concrete and mortar shall be clean and shall have a moisture content of not more than 0.50-percent when tested by California Test 226. Surfaces against which epoxy concrete and mortar are to be placed shall be primed with a coat of the epoxy used just prior to placing the concrete or mortar.

95-2 TYPES OF EPOXIES

95-2.01 BINDER (ADHESIVE), EPOXY RESIN BASE

Classification:

- This specification covers a low viscosity epoxy formulated primarily for use in making high-strength epoxy concrete and epoxy mortar and in pressure grouting of cracks in concrete. For load bearing applications, use ASTM Designation: C 881, Type IV, Grade 1, Class B or C. Class B or C shall be used depending on the substrate and ambient temperatures. Use Grade B for atmospheric and surface temperatures as low as 4°C. Use Class C when temperatures are 15°C or higher. For non-load bearing applications use ASTM Designation: C881, Type I, Grade 1, Class B or C. Apply no thicker than

recommended by the manufacturer. Thick sections of this epoxy are not suitable for use in freeze thaw environments. In a freeze-thaw environment, increase the aggregate loading to improve the properties of the epoxy concrete.

Directions for Use:

- Mix in conformance with the manufacturer's written recommendations. No more material shall be mixed than can be used within the pot-life from the time mixing operations are started.

95-2.02 (BLANK)

95-2.03 EPOXY RESIN ADHESIVE FOR BONDING NEW CONCRETE TO OLD CONCRETE

Classification:

- This specification covers a low viscosity paste epoxy formulated primarily for use in bonding new portland cement concrete to hardened portland cement concrete. The epoxy shall meet the specification requirements of ASTM Designation: C 881, Type V, Grade 2. This epoxy is available in 2 Classes: Class C for general use at temperature greater than 15°C and Class B for use when cure temperatures are below 15°C and above 4°C, or when a faster cure is required.

Directions for Use:

- The mixing ratio and use shall be in conformance with the manufacturer's written recommendations. When measuring as individual Components A and B, stir and tap the measuring containers to remove possible air voids. The ingredients in Components A and B shall be thoroughly dispersed such that each component forms a uniform paste. Do not mix more material than can be spread within the pot life from the time mixing operations are started. The spreading rate shall be sufficient to thoroughly coat the surface. Spread the mixed adhesive by brush or roller over blast-cleaned concrete at a rate recommended by the manufacturer. The new concrete shall be placed against the adhesive coating on the old concrete before the adhesive has set. If the adhesive has set and is not tacky prior to placing the new concrete, a new coating of adhesive shall be applied.

95-2.04 RAPID SET EPOXY ADHESIVE FOR PAVEMENT MARKERS

Classification:

- This specification covers a high viscosity paste, rapid set epoxy formulated primarily for use in bonding pavement markers to portland cement concrete and asphalt concrete. The adhesive shall meet ASTM Designation: C 881, Type IV, Grade 3, Class B and C except that the gel time may be shorter than 30 minutes. The adhesive shall conform to these requirements and the following.

Characteristics of Combined Components:

- All tests shall be performed in conformance with the requirements in California Test 434.

Property	Requirement
Gel time, minutes, maximum, at 25°C	30
Bond Strength to Concrete, Time, minutes (maximum) to reach not less than 1.4 MPa	
at 25°C ±1°C	35
at 10°C ±1°C	45
Slant Shear Strength	
2 days at 25°C ±1°C, MPa	7
14 days at 25°C ±1°C, plus water soak, MPa	10.5
Tensile Adhesion and Cohesion	
Ceramic marker bottom, MPa	4.8 min.
Ceramic marker bottom, including post cure, MPa	4.8 min.
Retroreflective pavement marker bottom, MPa	3.4 min.
Color of mixed epoxy	gray
Glass transition temperature, Tg, samples conditioned at 25°C for 24 hours, ASTM Designation: D 4065	30°C min.

Directions for Use:

- Components A and B shall be mixed in conformance with the manufacturer's written recommendations. When an automatic proportioning and mixing machine is used, the temperature of the components shall be maintained by indirect heating or cooling, so that the adhesive will meter, mix and extrude properly. The maximum temperature shall be such that after proper mixing no excess adhesive shall flow from under the marker other than that specified in Section 85-1.06, "Placement."

95-2.05 STANDARD SET EPOXY ADHESIVE FOR PAVEMENT MARKERS

Classification:

- This specification covers a high viscosity paste standard set epoxy formulated primarily for use in bonding pavement markers to portland cement concrete and asphalt concrete. The epoxy shall meet ASTM Designation: C 881, Type IV, Viscosity Grade 3, Classes B or C, except that the gel time may be shorter than 30 minutes.

Characteristics of Combined Components:

- All tests shall be performed in conformance with the requirements in California Test 434.

Property	Requirement
Gel time, minutes, maximum, at 25°C	30
Bond Strength to Concrete, Time (maximum) to reach not less than 1.4 MPa	
at 25°C ±1°C	3.5 hours
at 13°C ±1°C	24 hours
Slant Shear Strength	
2 days at 25°C ±1°C, MPa	7 min.
14 days at 25°C ±1°C, plus water soak, MPa	10.5 min.
Tensile Adhesion and Cohesion	
Ceramic marker bottom, MPa	4.8 min.
Ceramic marker bottom, including post cure, MPa	4.8 min.
Reflective pavement marker bottom, MPa	3.4 min.
Color of Mixed Components	gray
Glass transition temperature, Tg, samples conditioned at 25°C for 24 hours, ASTM Designation: D 4065	30°C min.

Directions for Use:

- Components A and B shall be mixed in conformance with the manufacturer's written recommendations. When an automatic proportioning and mixing machine is used, the temperature of the components shall be maintained by indirect heating or cooling, so that the adhesive will meter, mix and extrude properly. The maximum temperature shall be such that after proper mixing no excess adhesive shall flow from under the marker other than that specified in Section 85-1.06, "Placement."

95-2.06 (BLANK)

95-2.07 (BLANK)

95-2.08 (BLANK)

95-2.09 EPOXY SEALANT FOR INDUCTIVE LOOPS

Classification:

- This specification covers a high viscosity liquid epoxy formulated primarily for use in sealing inductive wire loops and leads imbedded in asphalt concrete and portland cement concrete for traffic signal controls and vehicle counters. This epoxy is to be used for repair work on existing spalls, cracks and other deformations in and around saw cuts housing inductor loops and leads. The rapid cure allows minimum traffic delay. This sealant is suitable for use in freeze-thaw areas. The epoxy shall meet ASTM Designation: C 881, Type I, Grade 2 and the following requirements.

Characteristics of Combined Components:

- All tests shall be performed in conformance with the requirements in California Test 434.

Property	Requirement
Gel time, minutes, maximum	30
On 3-mm cast sheet, cured 18 hours at 25°C, + 5 hours at 70°C	
Tensile Strength, MPa	2.7 min.
Elongation, percent	90 min.
Shore D Hardness	45 min.

Directions for Use:

- Saw cuts shall be cleaned with compressed air to remove all excess moisture and debris. For repairing damaged saw cuts, all loose spalled material shall be cleaned away from the saw cut, chipping back to sound asphalt concrete or portland cement concrete and all loose material cleaned from loop wires.
- The mixing ratio shall be in conformance with the manufacturer's recommendations. No more material shall be mixed than can be used within the gel time from the time mixing operations are started.
- When automatic mixing equipment is used for mixing the sealant, the provisions in the twelfth paragraph in Section 85-1.06, "Placement," shall apply.

95-2.10 (BLANK)

95-2.11 EPOXY RESIN ADHESIVE FOR INJECTION GROUTING OF PORTLAND CEMENT CONCRETE PAVEMENTS

Directions for Use:

- Both components and the mixed material shall contain no solvents. The mixing ratio of the components in terms of volume and mass shall be clearly stated. The material shall be suitable for use in the mixing equipment used by the applicator. Epoxy adhesive samples shall be furnished to the Engineer for testing at least 12 days before the expected time of use.

Characteristics of Adhesive:

Test ^a	California Test	Requirement
Brookfield Viscosity, No. 3 Spindle at 20 rpm, Pa·s at 25°C	434, Part 4	0.9 max.
Gel time, minutes	434, Part 1	2 to 15
Slant Shear Strength on Dry Concrete, MPa, after 4 days of cure in air at 25°C ±1°C	434, Part 5 ^b	41.4 min.
Slant Shear Strength on Wet Concrete, MPa, after 4 days of cure in air at 25°C ±1°C	434, Part 5 ^b	21.1 min.
Tensile Strength, Mpa	434, Part 7, except test after 4 days of cure at 25°C ±1°C	31.0 min.
Elongation, %	434, Part 7, except test after 4 days of cure at 25°C ±1°C	10 max.

a The mixing ratio used will be that recommended by the manufacturer.

b For slant shear strength on concrete, delete Sections B-1 and B-5 of California Test 434, Part 5. For dry concrete, use Step "2" below only. For wet concrete, use both Steps "1" & "2":

1 Soak blocks in water for 24 hours at 25°C ±1°C. Remove and wipe off excess water.

2 Mix epoxy as described in California Test 434, Part 1, and apply a coat approximately 250 µm thick to each diagonal surface. Place four 3-mm square pieces of shim stock 305 µm thick on one block to control final film thickness. Before pressing the coated surfaces together, leave the blocks so that the coated surfaces are horizontal until the epoxy reacts slightly to prevent excessive flow.

END OF AMENDMENTS

SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS

2-1.01 GENERAL

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the proposal form and the submission of the bid.

The bidder shall complete the "List of Subcontractors" form in the Proposal and Contract book, listing the name, address, and portion of work to be performed by each subcontractor listed. In addition to the subcontractors required to be listed in conformance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, the bidder shall list on this form each first tier Disabled Veteran Business Enterprise subcontractor to be used for credit in meeting the goal. A first tier subcontractor is one to whom the bidder proposes to directly subcontract portions of the work.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

Failure of the bidder to fulfill the requirements of the Special Provisions for submittals required to be furnished after bid opening, (including but not limited to DVBE submittals, and escrowed bid documents or prequalification materials when required), may subject the bidder to a determination of the bidder's responsibility in the event it is the apparent low bidder on any subsequent public works contracts.

2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)

It is the policy of the Department that Disabled Veteran Business Enterprises (DVBEs) shall be provided the opportunity for full participation in the performance of contracts financed solely with state funds. The Contractor shall take all necessary and reasonable steps to ensure that DVBEs have such opportunity to participate in the performance of this contract. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the award and performance of subcontracts.

It is the bidder's responsibility to make a sufficient portion of the work available to subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DVBE subcontractors and suppliers, so as to assure meeting the goal for DVBE participation or to provide information to establish that, prior to bidding, the bidder made good faith efforts to do so.

Section 999, et seq., of the Military and Veterans Code sets forth requirements for DVBE participation goals, summarized as follows:

- A. "Disabled Veteran Business Enterprise" (DVBE) means a business concern certified as a DVBE by the Office of Small Business and DVBE Services, Department of General Services.
- B. DVBEs must be certified on the date bids for the project are opened before credit may be allowed toward the DVBE goal. It is the Contractor's responsibility to verify that DVBEs are certified.
- C. The disabled veteran business owner must be domiciled in the State of California.
- D. A DVBE may participate as a prime contractor, as a subcontractor, as a joint venture partner with a prime or subcontractor, or as a vendor of material or supplies.
- E. The DVBE must perform a commercially useful function, that is, be responsible for the execution of a distinct element of the work and carry out its responsibility by actually performing, managing, or supervising the work. An extra participant will not be considered to perform a commercially useful function.
- F. Credit for DVBE prime contractors will be 100 percent of the contract price.
- G. Credit for participation of a DVBE subcontractor, supplier, or broker will be 100 percent provided such DVBE is performing a commercially useful function.
- H. A DVBE broker shall submit the required declarations and federal tax returns at the time of performance.

Failure to carry out the requirements of Section 999, et seq., of the Military and Veterans Code shall constitute a material breach of this contract and may result in termination of the contract or other remedy the Department deems appropriate.

A DVBE joint venture partner must be responsible for specific contract items of work, or portions thereof. The DVBE joint venture partner must share in the ownership, control, management responsibilities, risks, and profits of the joint venture. The DVBE joint venture must submit the joint venture agreement with the Caltrans Bidder DVBE Information form required in Section 2-1.02B, "Submission of DVBE Information," elsewhere in these special provisions.

Section 10115 of the Public Contract Code requires the Department to establish a goal for Disabled Veteran Business Enterprise (DVBE) participation in contracts.

2-1.02A DVBE GOAL FOR THIS PROJECT

The Disabled Veteran Business Enterprise (DVBE) participation goal for this project: 3 percent.

The Office of Small Business and DVBE Services, Department of General Services, is located at 707 Third Street, West Sacramento, CA 95605. It may be contacted at (800) 559-5529 or (916) 375-4940 or its internet web site at <http://www.pd.dgs.ca.gov/smbus/default.htm> for program information.

2-1.02B SUBMISSION OF DVBE INFORMATION

The required DVBE information shall be submitted on the "CALTRANS BIDDER - DVBE INFORMATION" form included in the Proposal. If this information is not submitted with the bid, the DVBE information forms shall be removed from the documents prior to submitting the bid.

If the DVBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit the DVBE information to the following address: Department of Transportation, MS 43, Attn: Office Engineer, 1727 30th Street, Sacramento, California 95816 so the information is received by the Department no later than 4:00 p.m. on the fourth business day following bid opening. The Department will not accept facsimile submittals of DVBE information. Failure to submit the required DVBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DVBE information unless requested to do so by the Department.

The bidder's DVBE information shall establish that either it met the goal or that, prior to bidding, it made good faith efforts to meet the goal. Information demonstrating that a good faith effort to meet the DVBE goal has been made by the bidder shall be submitted on the "DVBE INFORMATION GOOD FAITH EFFORTS" form included in the Proposal.

Bidders are cautioned that even though their submittal indicates they will meet the stated DVBE goal, their submittal should also include their good faith efforts information along with their DVBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DVBE information shall include the names of all DVBE firms that will participate, with a complete description of work or supplies to be provided by each and the dollar value of each DVBE transaction. When 100 percent of a contract item of work is not to be performed or furnished by a DVBE, a description of the exact portion of that work to be performed or furnished by that DVBE shall be included in the DVBE information, including the planned location of that work.

A bidder shall be deemed to have made good faith efforts if, within the time specified by the Department, it submits documentary evidence that all of the following actions were taken:

- A. Contact was made with the Office of Small Business and DVBE Services, Department of General Services or their web site at <http://www.pd.dgs.ca.gov/smbus/default.htm> to identify Disabled Veteran Business Enterprises.
- B. Advertising was published in trade media and media focusing on Disabled Veteran Business Enterprises, unless time limits imposed by the Department do not permit that advertising.
- C. Invitations to bid were submitted to potential Disabled Veteran Business Enterprise contractors.
- D. Available Disabled Veteran Business Enterprises were considered.

2-1.03 SMALL BUSINESS AND NON-SMALL BUSINESS SUBCONTRACTOR PREFERENCES

Attention is directed to the Small Business Procurement and Contract Act, Government Code Section 14835, et seq. and to the Small Business regulations at Title 2, California Code of Regulations, Section 1896, et seq.

Bidders, subcontractors, and suppliers who wish to be certified as Small Businesses under the provisions of those laws and regulations, shall be certified as Small Business by the Office of Small Business and DVBE Services, Department of General Services, 707 Third Street, West Sacramento, CA 95605.

Attention is directed to "Award and Execution of Contract" of these special provisions.

2-1.03A SMALL BUSINESS PREFERENCE

To request Small Business Preference, bidders shall fill out and sign the "Request for Small Business Preference and Non-Small Business Subcontractor Preference" form in the Proposal and shall attach a copy of their Office of Small Business and DVBE Services Small Business Certification letter to the form. The bidder's signature on the "Request for Small Business Preference" certifies that the bidder is certified as a Small Business at the time and day of bid opening or has applied for certification and is subsequently certified by the Department of General Services.

2-1.03B NON-SMALL BUSINESS SUBCONTRACTOR PREFERENCE

To request Non-Small Business Subcontractor Preference, bidders shall fill out and sign the "Request for Small Business Preference and Non-Small Business Subcontractor Preference" form in the Proposal. The bidder's signature certifies that the bidder commits to subcontract at least 25 percent of its bid amount with one or more subcontractors or suppliers that are certified as Small Businesses.

The bidder shall also fill out the "CALTRANS BIDDER – SMALL BUSINESS SUBCONTRACTOR - INFORMATION" form. If the Small Business Subcontractor information is not submitted with the bid, the form shall be removed from the documents and submitted in the same time and manner specified for DVBE Information in "Submission of DVBE Information" of these special provisions. The bidder shall attach a copy of the Office of Small Business and DVBE Services small business certification letter for each listed subcontractor or supplier, to the form. The listed subcontractors and suppliers shall be certified as Small Business at the time and day of bid opening or have applied for certification and are subsequently certified by the Department of General Services. Each listed subcontractor or supplier shall be designated to perform a commercially useful function.

2-1.04 CALIFORNIA COMPANY PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

In conformance with the requirements of Section 6107 of the Public Contract Code, a "California company" will be granted a reciprocal preference for bid comparison purposes as against a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

A "California company" means a sole proprietorship, partnership, joint venture, corporation, or other business entity that was a licensed California contractor on the date when bids for the public contract were opened and meets one of the following:

- A. Has its principal place of business in California.
- B. Has its principal place of business in a state in which there is no local contractor preference on construction contracts.
- C. Has its principal place of business in a state in which there is a local contractor construction preference and the Contractor has paid not less than \$5000 in sales or use taxes to California for construction related activity for each of the five years immediately preceding the submission of the bid.

To carry out the "California company" reciprocal preference requirements of Section 6107 of the Public Contract Code, all bidders shall fill out and sign the California Company Preference form in the Proposal. The bidder's signature on the California Company Preference form certifies, under penalty of perjury, that the bidder is or is not a "California company" and if not, the amount of the preference applied by the state of the nonresident Contractor.

A nonresident Contractor shall disclose any and all bid preferences provided to the nonresident Contractor by the state or country in which the nonresident Contractor has its principal place of business.

Proposals without the California Company Preference form filled out and signed may be rejected.

SECTION 3. AWARD AND EXECUTION OF CONTRACT

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

Requests for relief of bid and bid protests are to be delivered to the following address: Department of Transportation, MS 43, Attn: Office Engineer, 1727 30th Street, Sacramento, CA 95816 or by facsimile to the Office Engineer at (916) 227-6282.

The award of the contract, if made, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DVBE participation or has demonstrated, to the satisfaction of the Department, good faith efforts to do so.

The contract shall be executed by the successful bidder and shall be returned, together with the contract bonds and the documents identified in Section 3-1.025, "Insurance Policies," of the Standard Specifications, to the Department so that it is received within 10 business days after the bidder has received the contract for execution. Failure to do so shall be just cause for forfeiture of the proposal guaranty. The executed contract documents shall be delivered to the following address: Department of Transportation MS 43, Attn: Office Engineer, 1727 30th Street, Sacramento, CA 95816.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract, contract bonds and the documents identified in Section 3-1.025, "Insurance Policies," of the Standard Specifications. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 20 percent of payments due the Contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

Attention is also directed to "Small Business and Non-Small Business Subcontractor Preferences" of these special provisions.

A bidder who is certified as a Small Business by the Office of Small Business and DVBE Services, Department of General Services, will be allowed a preference in the award of this contract under the following conditions:

- A. The bidder filled out and signed the "Request for Small Business Preference and Non-Small Business Subcontractor Preference" form, requesting Small Business preference, and attached a copy of its Office of Small Business and DVBE Services small business certification letter to the form; and
- B. The apparent low bidder is not certified as a Small Business.

A bidder who is not certified as a Small Business by the Office of Small Business and DVBE Services, Department of General Services, will be allowed a preference in the award of this contract under the following conditions:

- A. The bidder filled out and signed the "Request for Small Business Preference and Non-Small Business Subcontractor Preference" form, requesting Non-Small Business Subcontractor preference and notifying the Department that it commits to subcontract at least 25 percent of its bid amount with one or more Small Businesses, and submitted the "CALTRANS BIDDER – SMALL BUSINESS SUBCONTRACTOR – INFORMATION" form listing the subcontractors and suppliers it commits to subcontract with; and
- B. The apparent low bidder is not certified as a Small Business, and has not filled out and signed the "Request for Small Business Preference and Non-Small Business Subcontractor Preference."

The Small Business preference will be a reduction in the bid submitted by the Small Business contractor, for bid comparison purposes, by an amount equal to 5 percent of the amount bid by the apparent low bidder, the amount not to exceed \$50,000. If this reduction results in the Small Business contractor becoming the low bidder, or in a precise tie with a Non-Small Business apparent low bidder, then the contract will be awarded to the Small Business contractor on the basis of the actual bid of the Small Business contractor notwithstanding the reduced bid price used for bid comparison purposes.

The Non-Small Business Subcontractor preference will be a reduction in the bid submitted by the Non-Small Business contractor requesting the preference, for bid comparison purposes, by an amount equal to 5 percent of the amount bid by the apparent low bidder, the amount not to exceed \$50,000. If this reduction results in the Non-Small Business contractor requesting the preference becoming the low bidder, or in a precise tie with a Non-Small Business apparent low bidder not requesting the preference, then the contract will be awarded to the Non-Small Business contractor requesting the preference on the basis of its actual bid notwithstanding the reduced bid price used for bid comparison purposes. Application of the Non-Small Business Subcontractor preference shall not result in the displacement of a Small Business in winning the award.

Attention is also directed to "California Company Preference" of these special provisions.

The amount of the California company reciprocal preference shall be equal to the amount of the preference applied by the state of the nonresident contractor with the lowest responsive bid, except where the "California company" is eligible for a California Small Business Preference or a California Non-Small Business Subcontractor Preference, in which case the preference applied shall be the greater of the two, but not both.

If the bidder submitting the lowest responsive bid is not a "California company" and with the benefit of the reciprocal preference, a "California company's" responsive bid is equal to or less than the original lowest responsive bid, the "California company" will be awarded the contract at its submitted bid price except as provided below.

Small Business bidders shall have precedence over Non-Small Business bidders in that the application of the "California company" preference for which Non-Small Business bidders may be eligible shall not result in the denial of the award to a Small Business bidder.

DVBE bidders shall have precedence over Non-DVBE bidders in that in the event the application of the Small Business preference to more than one bidder results in a precise tie in the bid amounts used for comparison purposes, the award shall go to the DVBE that is also a small business. This precedence shall not apply to the application of the California company reciprocal preference.

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

The first working day is the fifteenth day after contract approval.

The work shall be diligently prosecuted to completion before the expiration of 250 WORKING DAYS.

The Contractor shall pay to the State of California the sum of \$2600 per day for each day's delay in finishing the work.

SECTION 5. GENERAL

SECTION 5-1. MISCELLANEOUS

5-1.01 GUARANTEE

GENERAL

The Contractor shall guarantee the work is in accordance with contract requirements and remains free from substantial defects in materials and workmanship for a period of one year after contract acceptance. For certain portions of the work where the Director relieves the Contractor of responsibility in accordance with Section 7-1.15, "Relief from Maintenance and Responsibility," of the Standard Specifications, the guarantee period starts on the relief date and ends one year therefrom.

Substantial defects in materials and workmanship means defective work objectively manifested by damaged, displaced, or missing parts or components and workmanship resulting in improper function of materials, components, equipment, or systems, as installed or manufactured by the Contractor, subcontractor, supplier, or manufacturer.

During the guarantee period, the Contractor shall repair or replace contract work and associated work which is not in accordance with contract requirements or has substantial defects in materials and workmanship. The Contractor shall perform the corrective work with no expense to the Department other than State-provided field inspection services.

The guarantee of work excludes damage or displacement that is outside the control of the Contractor and caused by normal wear and tear, improper operation, insufficient maintenance, abuse, unauthorized modification, or natural disaster as described in Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications.

The Contractor shall have the same insurance coverage during corrective work operations as prior to contract acceptance, in accordance with Section 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The contract bonds furnished in accordance with Section 3-1.02, "Contract Bonds," of the Standard Specifications must remain in full force and effect during the guarantee period and until all corrective work is complete.

In the case of conflict between this guarantee provision and any warranty provision included in the contract, the warranty provision shall govern for the specific construction product or feature covered.

CORRECTIVE WORK

During the guarantee period, the Department will monitor performance of the highway facilities completed by the Contractor and will perform a thorough review of the contract work at least 60 days before the expiration of the one-year guarantee.

If the Engineer discovers contract work not in compliance with contract requirements or that has substantial defects in materials and workmanship, at any time during the guarantee period, a list of items that require corrective work will be developed and forwarded to the Contractor. Within 15 days of receipt of a list, the Contractor shall submit to the Engineer a detailed plan for performing corrective work. The work plan shall include a start to finish schedule. It shall include a list of labor, equipment, materials, and any special services intended to be used. It shall clearly show related work including traffic control, temporary delineation, and permanent delineation.

The Contractor shall start the corrective and related work within 15 days of receiving notice from the Engineer that the Contractor's work plan is approved. The corrective work shall be diligently prosecuted and completed within the time allotted in the approved work plan.

If the Engineer determines that corrective work, covered by the guarantee, is urgently needed to prevent injury or property damage, the Engineer will give the Contractor a request to start emergency repair work and a list of items that require repair work. The Contractor shall mobilize within 24 hours and diligently perform emergency repair work on the damaged highway facilities. The Contractor shall submit a work plan within 5 days of starting emergency repair work.

If the Contractor fails to commence and execute, with due diligence, corrective work and related work required under the guarantee in the time allotted, the Engineer may proceed to have the work performed by State forces or other forces at the Contractor's expense. Upon demand, the Contractor shall pay all costs incurred by the Department for work performed by State forces or other forces including labor, equipment, material, and special services.

PAYMENT

Full compensation for performing corrective work; and related work such as traffic control, temporary delineation, and permanent delineation, and to maintain insurance coverage and bonds, shall be considered as included in the contract prices paid for the various contract items of work and no separate payment will be made therefor.

5-1.019 COST REDUCTION INCENTIVE

Attention is directed to Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

Prior to preparing a written cost reduction proposal, the Contractor shall request a meeting with the Engineer to discuss the proposal in concept. Items of discussion will also include permit issues, impact on other projects, impact on the project schedule, peer reviews, overall merit of the proposal, and review times required by the Department and other agencies.

If a cost reduction proposal submitted by the Contractor, and subsequently approved by the Engineer, provides for a reduction in contract time, 50 percent of that contract time reduction shall be credited to the State by reducing the contract working days, not including plant establishment. Attention is directed to "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions regarding the working days.

If a cost reduction proposal submitted by the Contractor, and subsequently approved by the Engineer, provides for a reduction in traffic congestion or avoids traffic congestion during construction, 60 percent of the estimated net savings in construction costs attributable to the cost reduction proposal will be paid to the Contractor. In addition to the requirements in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications, the Contractor shall provide detailed comparisons of the traffic handling between the existing contract and the proposed change, and estimates of the traffic volumes and congestion.

5-1.02 LABOR NONDISCRIMINATION

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM

(GOV. CODE, SECTION 12990)

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5000 or more.

5-1.03 INTEREST ON PAYMENTS

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments, and claim payments as follows:

- A. Unpaid progress payments, payment after acceptance, and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
- B. Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in conformance with the provisions in Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
- C. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and extra work payments shall be 10 percent per annum.
- D. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

5-1.04 PUBLIC SAFETY

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations—The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
 - 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
 - 2. Excavations less than 0.3-m deep.
 - 3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
 - 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
 - 5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
 - 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.05 TESTING

Testing of materials and work shall conform to the provisions in Section 6-3, "Testing," of the Standard Specifications and these special provisions.

Whenever the provisions of Section 6-3.01, "General," of the Standard Specifications refer to tests or testing, it shall mean tests to assure the quality and to determine the acceptability of the materials and work.

The Engineer will deduct the costs for testing of materials and work found to be unacceptable, as determined by the tests performed by the Department, and the costs for testing of material sources identified by the Contractor which are not used for the work, from moneys due or to become due to the Contractor. The amount deducted will be determined by the Engineer.

5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

5-1.065 SOLID WASTE DISPOSAL AND RECYCLING REPORT

This work shall consist of reporting disposal and recycling of construction solid waste, as specified in these special provisions. For the purposes of this section, solid waste includes construction and demolition waste debris, but not hazardous waste.

Annually by the fifteenth day of January, the Contractor shall complete and certify Form CEM-4401, "Solid Waste Disposal and Recycling Report," which quantifies solid waste generated by the work performed and disposed of in landfills or recycled during the previous calendar year. The amount and type of solid waste disposed of or recycled shall be reported in tons. The Contractor shall also complete and certify Form CEM-4401 within 5 days following contract acceptance.

Form CEM-4401, "Solid Waste Disposal and Recycling Report" can be downloaded from the following website:

<http://www.dot.ca.gov/hq/construc/manual2001>

If the Contractor has not submitted Form CEM-4401, by the dates specified above, the Department will withhold the amount of \$10,000 for each missing or incomplete report. The moneys withheld will be released for payment on the next monthly estimate for partial payment following the date that a complete and acceptable Form CEM-4401 is submitted to the Engineer. Upon completion of all contract work and submittal of the final Form CEM-4401, remaining withheld funds associated with this section, "Solid Waste Disposal and Recycling Report," will be released for payment. Withheld funds in conformance with this section shall be in addition to other moneys withheld provided for in the contract. No interest will be due the Contractor on withheld amounts.

Full compensation for preparing and submitting Form CEM-4401, "Solid Waste Disposal and Recycling Report," shall be considered as included in the contract price for the various items of work involved and no additional compensation will be allowed therefor.

5-1.07 (BLANK)

5-1.08 (BLANK)

5-1.09 SUBCONTRACTING

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, Section 2, "Proposal Requirements and Conditions," and Section 3, "Award and Execution of Contract," of these special provisions.

The first sentence in the third paragraph of Section 8-1.01, "Subcontracting," of the Standard Specifications shall not apply.

Pursuant to the provisions in Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

<http://www.dir.ca.gov/DLSE/Debar.html>

Unauthorized substitution of a listed subcontractor may constitute a violation of the "Subletting and Subcontracting Fair Practices Act" and may subject the Contractor to the penalties imposed therein.

5-1.09A DVBE SUBCONTRACTING

The DVBEs listed by the Contractor in response to the provisions in Section 2-1.02B, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DVBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Unauthorized substitution of a DVBE may also constitute a violation of California Code of Regulations Section 1896.64. The Contractor shall not be entitled to payment for the work or material unless it is performed or supplied by the listed DVBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

The provisions in Section 2-1.02, "Disabled Veteran Business Enterprise (DVBE)," of these special provisions that DVBEs shall be certified on the date bids are opened does not apply to substitutions after award of the contract.

The Contractor shall maintain records of all subcontracts entered into with certified DVBE subcontractors and records of materials purchased from certified DVBE suppliers. The records shall show the name and business address of each DVBE subcontractor or vendor and the total dollar amount actually paid each DVBE subcontractor or vendor.

The Contractor agrees that the awarding department will have the right to review, obtain and copy all records pertaining to performance of DVBEs during the contract. The Contractor agrees to provide the awarding department with any relevant information requested and shall permit access to its premises, upon reasonable notice, during normal business hours for the purpose of interviewing employees and inspecting and copying such books, records, accounts and other material that may be relevant to a matter under investigation for the purpose of determining compliance with Public Contract Code Section 10115 et seq. The Contractor further agrees to maintain such records for a period of three (3) years after final payment under the contract.

5-1.09B NON-SMALL BUSINESS SUBCONTRACTING

The Small Business subcontractors listed by the Contractor in response to the provisions in Section 2-1.03B, "Non-small Business Subcontractor Preference," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified as Small Business, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Unauthorized substitution of a Small Business subcontractor may also constitute a violation of California Code of Regulations Section 1896.10 and may subject the Contractor to the sanctions referenced therein.

The provisions in Section 2-1.03B, "Non-small Business Subcontractor Preference," of these special provisions that Small Business subcontractors shall be certified on the date bids are opened does not apply to substitutions after award of the contract.

The Contractor shall maintain records of all subcontracts entered into with certified Small Business subcontractors and records of materials purchased from certified Small Business suppliers. The records shall show the name and business address of each Small Business subcontractor or vendor and the total dollar amount actually paid each Small Business subcontractor or vendor.

Contractor agrees that the awarding department will have the right to review, obtain and copy all records pertaining to performance of Small Businesses during the contract. The Contractor agrees to provide the awarding department with any relevant information requested and shall permit access to its premises, upon reasonable notice, during normal business hours for the purpose of interviewing employees and inspecting and copying such books, records, accounts and other material that may be relevant to a matter under investigation for the purpose of determining compliance with California Code of Regulations Section 1896, et seq. The Contractor further agrees to maintain such records for a period of three (3) years after final payment under the contract.

5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code concerning prompt payment to subcontractors.

5-1.103 RECORDS

The Contractor shall maintain cost accounting records for the contract pertaining to, and in such a manner as to provide a clear distinction between, the following six categories of costs of work during the life of the contract:

- A. Direct costs of contract item work.
- B. Direct costs of changes in character in conformance with Section 4-1.03C, "Changes in Character of Work," of the Standard Specifications.
- C. Direct costs of extra work in conformance with Section 4-1.03D, "Extra Work," of the Standard Specifications.
- D. Direct costs of work not required by the contract and performed for others.
- E. Direct costs of work performed under a notice of potential claim in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications.
- F. Indirect costs of overhead.

Cost accounting records shall include the information specified for daily extra work reports in Section 9-1.03C, "Records," of the Standard Specifications. The requirements for furnishing the Engineer completed daily extra work reports shall only apply to work paid for on a force account basis.

The cost accounting records for the contract shall be maintained separately from other contracts, during the life of the contract, and for a period of not less than 3 years after the date of acceptance of the contract. If the Contractor intends to file claims against the Department, the Contractor shall keep the cost accounting records specified above until complete resolution of all claims has been reached.

5-1.104 INTERNET DAILY EXTRA WORK REPORT

When extra work is being paid for on a force account basis, the Contractor shall submit daily extra work reports in conformance with the provisions in Section 9-1.03C, "Records," of the Standard Specifications and these special provisions.

The Contractor shall send daily extra work reports to the Engineer using the Department's Internet extra work billing system. The reports shall conform to the requirements in the "iCAS User's Guide" (Guide). The Guide is available from the Department, and is also found on the Internet at:

http://www.dot.ca.gov/hq/construc/ewb/EWB_INSTRUCTION.pdf

The Department will provide system accounts to the Contractor's authorized representatives when at least one of the representatives has received training. The Department will provide system training to at least one of the Contractor's authorized representatives within 30 days of the Contractor's request for training. The Department will assign an account and user identification to the Contractor's authorized representatives, and each Contractor's authorized representative shall maintain a unique password. A daily extra work report that the Contractor's authorized representative sends to the Department using the Internet extra work billing system will be considered signed by the Contractor. A daily extra work report that the Engineer approves using the Internet extra work billing system will be considered signed by the Engineer.

Daily extra work reports that include billing for materials shall be substantiated by a valid copy of a vendor's invoice in conformance to the requirements in Section 9-1.03C, "Records," of the Standard Specifications. Each materials invoice shall clearly identify the relative daily extra work report and the associated cost of the materials. In addition to postal service and parcel service and if approved by the Engineer, invoices may be sent by facsimile or as an electronic-mail attachment.

The Contractor shall maintain the Contractor's interface with the Department's Internet extra work billing system. If the Contractor is using the file transfer process to submit extra work reports, it shall conform to the file transfer format and process defined in the Guide.

5-1.105 ARCHAEOLOGICAL DISCOVERIES

If archaeological materials, including but not limited to human skeletal material and disarticulated human bone, are discovered at the job site, protect and leave undisturbed and in place archaeological materials in accordance with the following codes and these special provisions:

1. California Public Resources Code, Division 5, Chapter 1.7 § 5097.5
2. California Public Resources Code, Division 5, Chapter 1.75 § 5097.98 and § 5097.99
3. California Administrative Code, Title 14 § 4308
4. California Penal Code, Part 1, Title 14 § 622-1/2
5. California Health and Safety Code, Division 7, Part 1, Chapter 2, § 7050.5

Archaeological materials are the physical remains of past human activity and include historic-period archaeological materials and prehistoric Native American archaeological materials. Nonhuman fossils are not considered to be archaeological except when showing direct evidence of human use or alteration or when found in direct physical association with archaeological materials as described in these special provisions.

Historic-period archaeological materials include cultural remains beginning with initial European contact in California, but at least 50 years old. Historical archaeological materials include:

1. Trash deposits or clearly defined disposal pits containing tin cans, bottles, ceramic dishes, or other refuse indicating previous occupation or use of the site
2. Structural remains of stone, brick, concrete, wood, or other building material found above or below ground or
3. Human skeletal remains from the historic period, with or without coffins or caskets, including any associated grave goods

Prehistoric Native American archaeological materials include:

1. Human skeletal remains or associated burial goods such as beads or ornaments
2. Evidence of tool making or hunting such as arrowheads and associated chipping debris of fine-grained materials such as obsidian, chert, or basalt
3. Evidence of plant processing such as pestles, grinding slabs, or stone bowls
4. Evidence of habitation such as cooking pits, stone hearths, packed or burnt earth floors or
5. Remains from food processing such as concentrations of discarded or burnt animal bone, shellfish remains, or burnt rocks used in cooking

Immediately upon discovery of archaeological materials, stop all work within a 18.5 meter radius of the archaeological materials and immediately notify the Engineer. Archaeological materials found during construction are the property of the State. Do not resume work within the 18.5 meter radius of the find until the Engineer gives you written approval. If, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of an archeological find or investigation or recovery of archeological materials, you will be compensated for resulting losses and an extension of time will be granted in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Department may use other forces to investigate and recover archaeological materials from the location of the find. When ordered by the Engineer furnish labor, material, tools and equipment, to secure the location of the find, and assist in the investigation or recovery of archaeological materials and the cost will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Full compensation for immediately notifying the Engineer upon discovery of archaeological materials and leaving undisturbed and in place archaeological materials discovered on the job site shall be considered as included in the contract price paid for various items of work involved and no additional compensation will be allowed therefor.

5-1.11 PARTNERING

The State will promote the formation of a "Partnering" relationship with the Contractor in order to effectively complete the contract to the benefit of both parties. The purpose of this relationship is to maintain a cooperative communication and to mutually resolve conflicts at the lowest responsible management level.

The Contractor may request the formation of a "Partnering" relationship by submitting a request in writing to the Engineer after approval of the contract. If the Contractor's request for "Partnering" is approved by the Engineer, scheduling of a "Partnering Workshop," selecting the "Partnering" facilitator and workshop site, and other administrative details shall be as agreed to by both parties. If agreed to by the parties, additional "Partnering Workshops" will be conducted as needed throughout the life of the contract.

The costs involved in providing the "Partnering Workshop" facilitator and workshop site will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost in providing the "Partnering Workshop" facilitator and workshop site in conformance with the provisions in Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor one-half of that cost, except no markups will be allowed.

All other costs associated with "Partnering Workshops" will be borne separately by the party incurring the costs, such as wages and travel expenses, and no additional compensation will be allowed therefor.

The establishment of a "Partnering" relationship will not change or modify the terms and conditions of the contract and will not relieve either party of the legal requirements of the contract.

5-1.12 DISPUTE RESOLUTION ADVISOR

A dispute resolution advisor, hereinafter referred to as "DRA", is chosen by the Department and the Contractor to assist in the resolution of disputes. The DRA is a part of the contract administrative claims process as specified in the provisions in Section 9-1.04, "Notice of Potential Claim," and Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. The DRA shall not serve as a substitute for filing a protest or a notice of potential claim.

The DRA shall be established by the Department and the Contractor within 30 days of contract approval.

The Department and the Contractor shall each propose 3 potential DRA candidates. Each potential candidate shall provide the Department and the Contractor with their disclosure statement. The disclosure statement shall include a resume of the potential candidate's experience and a declaration statement describing past, present, anticipated, and planned relationships with all parties involved in this contract.

The Department and the Contractor shall select one of the 6 nominees to be the DRA. If the Department and the Contractor cannot agree on one candidate, the Department and the Contractor shall each choose one of the 3 nominated by the other. The final selection of the DRA will be decided by a coin toss between the two candidates.

The Department and the Contractor shall complete and adhere to the Dispute Resolution Advisor Agreement. No DRA meeting shall take place until the Dispute Resolution Advisor Agreement has been signed by all parties, unless all parties agree to sign it at the first meeting.

If DRA needs outside technical services, technical services shall be preapproved by both the Department and the Contractor.

DRA recommendations are nonbinding.

The Contractor shall not use the DRA for disputes between subcontractors or suppliers that have no grounds for a lawsuit against the Department.

DRA replacement is selected in the same manner as the original selection. The appointment of a replacement DRA will begin promptly upon determination of the need for replacement. The Dispute Resolution Advisor Agreement shall be amended to reflect the change of the DRA.

Failure of the Contractor to participate in selecting DRA will result in the withhold of 25 percent of the estimated value of all work performed during each estimate period that the Contractor fails to comply. DRA withholds will be released for payment on the next monthly progress payment following the date that the Contractor has provided assistance in choosing the DRA and no interest will be due the Contractor.

The State and the Contractor shall bear the costs and expenses of the DRA equally.

The DRA shall be compensated at an agreed rate of \$1,500 per day for time spent per meeting either at the start of the project or for a dispute. A member serving on more than one State DRA or Dispute Review Board, regardless the number of meetings per day shall not be paid more than the agreed rate per day. The agreed rate shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel, and incidentals for each day or portion thereof that the DRA is at an authorized DRA meeting.

No additional compensation will be made for time spent by the DRA to review and research activities outside the official DRA meetings unless that time, such as time spent evaluating and preparing recommendations on specific issues presented to the DRA, has been specifically agreed to in advance by the State and Contractor. Time away from the project that has been specifically agreed to in advance by the Department and the Contractor will be compensated at an agreed rate of \$150 per hour. The agreed amount of \$150 per hour shall include all incidentals including expenses for telephone, fax, and computer services.

The State will provide conference facilities for DRA meetings at no cost to the Contractor.

The Contractor shall make direct payments to the DRA for participation in authorized meetings and approved hourly rate charges from invoices submitted.

The State will reimburse the Contractor for the State's share of the costs.

There will be no markups applied to expenses associated with the DRA, either by the DRA or by the Contractor when requesting payment of the State's share of DRA expenses. Regardless of the DRA recommendation, neither party will be entitled to reimbursement of DRA costs from the other party.

The Contractor shall submit extra work bills and include invoices with original supporting documents for reimbursement of the State's share.

The cost of technical services will be borne equally by the State and Contractor. There will be no markups for these costs.

A copy of the "Dispute Resolution Advisor Agreement" to be executed by the Contractor, State and the DRA is as follows:

Form CEM 6206 Rev (04-06-07)

DISPUTE RESOLUTION ADVISOR AGREEMENT

(Contract Identification)

Contract No. _____

THIS DISPUTE RESOLUTION ADVISOR AGREEMENT, hereinafter called "AGREEMENT", made and entered into this _____ day of _____, _____, between the State of California, acting through the California Department of Transportation and the Director of Transportation, hereinafter called the "STATE," _____ hereinafter called the "CONTRACTOR," and _____, the Dispute Resolution Advisor, hereinafter called the "DRA." .

WITNESSETH, that

WHEREAS, the STATE and the CONTRACTOR, hereinafter called the "parties," are now engaged in the construction on the State Highway project referenced above; and

WHEREAS, the special provisions for the above referenced contract provides for the establishment and operation of the DRA to assist in resolving disputes; and

WHEREAS, the DRA is composed of one person, chosen by the CONTRACTOR and the STATE;

NOW THEREFORE, in consideration of the terms, conditions, covenants, and performance contained herein, or attached and incorporated and made a part hereof, the STATE, the CONTRACTOR, and the DRA hereto agree as follows:

SECTION I DESCRIPTION OF WORK

To assist in the timely resolution of disputes between the parties, the contract provides for the establishment and the operation of the DRA. The DRA is to fairly and impartially consider disputes placed before it and provide recommendations for resolution of these disputes to the parties. The DRA shall provide recommendations based on the facts related to the dispute, the contract and applicable laws and regulations. The DRA shall perform the services necessary to participate in the DRA's actions as designated in Section III, Scope of Work.

SECTION II DRA QUALIFICATIONS

DRA shall be knowledgeable in the type of construction and contract documents anticipated by the contract and shall have completed training through the Dispute Review Board Foundation. In addition, it is desirable for the DRA to have served on several State Dispute Review Boards (DRB).

No DRA shall have prior direct involvement in this contract. No DRA shall have a financial interest in this contract or parties thereto, including but not limited to the CONTRACTOR, subcontractors, suppliers, consultants, and legal and business services, within a period 6 months prior to award and during this contract. Exceptions to above are compensation for services on this or other DRAs and DRBs or retirement payments or pensions received from a party that are not tied to, dependent on or affected by the net worth of the party.

DRA shall fully disclose all direct or indirect professional or personal relationships with all key members of the contract.

SECTION III SCOPE OF WORK

The Scope of Work of the DRA includes, but is not limited to, the following:

A. PROCEDURES

The DRA shall meet with the parties at the start of the project to establish procedures that will govern the conduct of its business and reporting procedures in conformance with the requirements of the contract and the terms of this AGREEMENT. The DRA established procedures shall only be implemented upon approval by the parties. Subsequent meetings shall be held only to hear disputes between the parties.

The DRA shall not meet with, or discuss contract issues with individual parties.

State shall provide the DRA with the contract and all written correspondence regarding the dispute between the parties and, if available, the Contractor's supplemental notice of potential claim, and the Engineer's response to the supplemental notice of potential claim.

The parties shall not call the DRA who served on this contract as a witness in arbitration proceedings, which may arise from this contract.

The DRA shall have no claim against the STATE or the CONTRACTOR, or both, from claimed harm arising out of the parties' evaluations of the DRA's opinions.

B. DISPUTE MEETING

The term "dispute meeting" as used in this subsection shall refer to both the informal and traditional dispute meeting processes, unless otherwise noted.

If the CONTRACTOR requests a dispute meeting with the DRA, the Contractor must simultaneously notify the STATE. Upon being notified of the need for a dispute meeting, the DRA shall review and consider the dispute. The DRA shall determine the time and location of the dispute meeting with due consideration for the needs and preferences of the parties, while recognizing the importance of a speedy resolution to the dispute.

Dispute meetings shall be conducted at any location that would be convenient and provide required facilities and access to necessary documentation.

Only the STATE's Resident Engineer or Area Construction Engineer and the CONTRACTOR's or subcontractor's, if the dispute involves a subcontractor, Superintendent or Project Manager may present information at a dispute meeting. There shall be no participation of persons who are not directly involved in the contract or who do not have direct knowledge of the dispute. The exception to this is technical services, as described below:

The DRA, with approval of the parties, may obtain technical services necessary to adequately review the disputes presented, including audit, geotechnical, schedule analysis and other services. The parties' technical staff may supply those services as appropriate. The cost of technical services, as agreed to by the parties, shall be borne equally by the two parties as specified in an approved contract change order. The CONTRACTOR shall not be entitled to markups for the payments made for these services.

At the dispute meeting the DRA may ask questions, seek clarification, and request further clarification of data presented by either of the parties as may be necessary to assist in making a fully informed recommendation. However, the DRA shall refrain from expressing opinions on the merits of statements on matters under dispute during the parties' presentations. Each party will be given ample time to fully present its position, make rebuttals, provide relevant documents, and respond to DRA questions and requests.

There shall be no testimony under oath or cross-examination, during DRA dispute meetings. There shall be no reporting of the procedures by a shorthand reporter or by electronic means. Documents and verbal statements shall be received by the DRA in conformance with the rules and regulations established at the first meeting between the DRA and parties. These established rules and regulations need not comply with prescribed legal laws of evidence.

Failure to attend a dispute meeting by either of the parties shall be conclusively considered by the DRA as indication that the non-attending party considers all written documents and correspondence submitted as their entire and complete argument. The claimant shall discuss the dispute, followed by the other party. Each party shall then be allowed one or more rebuttals at the meeting until all aspects of the dispute are thoroughly covered.

1. TRADITIONAL DISPUTE MEETING:

The following procedure shall be used for the traditional dispute meeting:

- a. Within 5 days, after receiving the STATE's written response to the CONTRACTOR's supplemental notice of potential claim, the CONTRACTOR shall refer the dispute to the DRA, if the CONTRACTOR wishes to further pursue the dispute. The CONTRACTOR shall make the referral in writing to the DRA, simultaneously copied to the STATE. The written dispute referral shall describe the disputed matter in individual discrete segments, so that it will be clear to both parties and the DRA what discrete elements of the dispute have been resolved, and which remain unresolved, and shall include an estimate of the cost of the affected work and impacts, if any, on project completion.
- b. The parties shall each be afforded an opportunity to be present and to be heard by the DRA, and to offer evidence. Either party furnishing written evidence or documentation to the DRA must furnish copies of such information to the other party a minimum of 10 days prior to the date the DRA is scheduled to convene the meeting for the dispute. Either party shall produce such additional evidence as the DRA may deem necessary to reach an understanding and a determination of the dispute. The party furnishing additional evidence shall furnish copies of such additional evidence to the other party at the same time the evidence is provided to the DRA. The DRA shall not consider evidence not furnished in conformance with the terms specified herein.
- c. Upon receipt by the DRA of a written referral of a dispute, the DRA shall convene to review and consider the dispute. The dispute meeting shall be held no later than 25 days after receipt of the written referral unless otherwise agreed to by all parties.
- d. The DRA shall furnish a written report to both parties. The DRA may request clarifying information of either party within 5 days after the DRA dispute meeting. Requested information shall be submitted to the DRA within 5 days of the DRA request. The DRA shall complete its report and submit it to the parties within 10 days of the DRA dispute meeting, except that time extensions may be granted at the request of the DRA with the written concurrence of both parties. The report shall summarize the facts considered, the contract language, law or regulation viewed by the DRA as pertinent to the dispute, and the DRA's interpretation and philosophy in arriving at its conclusions and recommendations and, if appropriate, recommends guidelines for determining compensation. The DRA's written opinion shall stand on its own, without attachments or appendices.
- e. Within 10 days after receiving the DRA's report, both parties shall respond to the DRA in writing signifying that the dispute is either resolved or remains unresolved. Failure to provide the written response within the time specified, or a written rejection of the DRA's recommendation or response to a request for reconsideration presented in the report by either party, shall conclusively indicate that the party(s) failing to respond accepts the DRA recommendation. Immediately after responses have been received from both parties, the DRA shall provide copies of both responses to the parties simultaneously. Either party may request clarification of elements of the DRA's report from the DRA prior to responding to the report. The DRA shall consider any clarification request only if submitted within 5 days of receipt of the DRA's report, and if submitted simultaneously in writing to both the DRA and the other party. Each party may submit only one request for clarification for any individual DRA report. The DRA shall respond, in writing, to requests for clarification within 5 days of receipt of such requests.
- f. Either party may seek a reconsideration of the DRA's recommendation. The DRA shall only grant reconsideration based upon submission of new evidence and if the request is submitted within the 10 day time limit specified for response to the DRA's written report. Each party may submit only one request for reconsideration regarding an individual DRA recommendation.
- g. If the parties are able to settle their dispute with the aid of the DRA's report, the STATE and CONTRACTOR shall promptly accept and implement the settlement of the parties. If the parties cannot agree on compensation within 30 days of the acceptance by both parties of the settlement, either party may request the DRA to make a recommendation regarding compensation.

2. INFORMAL DISPUTE MEETING

An informal dispute meeting shall be convened, only if, the parties and the DRA agree that this dispute resolution process is appropriate to settle the dispute.

The following procedure shall be used for the informal dispute meeting:

- a. The parties shall furnish the DRA with one copy of pertinent documents requested by the DRA that are or may become necessary for the DRA to perform its function. The party furnishing documents shall furnish such documents to the other party at the same time the document is provided to the DRA.
- b. After the dispute meeting has concluded; the DRA shall deliberate in private the same day, until a response to the parties is reached or as otherwise agreed to by the parties.

- c. The DRA then verbally delivers its recommendation with findings to the parties.
- d. After the recommendation is presented, the parties may ask for clarifications.
- e. Occasionally the DRA on complex issues may be unable to formulate a recommendation based on the information given at a dispute meeting. However, the DRA may provide the parties with advice on strengths and weaknesses of their prospective positions, in the hope of the parties reaching settlement.
- f. If the parties are able to settle their dispute with the aid of the DRA's opinion, the STATE and CONTRACTOR shall promptly accept and implement the settlement of the parties.
- g. The DRA will not be bound by its oral recommendation in the event that a dispute is later heard by the DRA in a traditional dispute meeting.

Unless the dispute is settled, use of the informal dispute meeting does not relieve the parties of their responsibilities under Section 5-1.12, "Dispute Resolution Advisor," of the Special Provisions or Subsection, "Traditional Dispute Meeting," of this AGREEMENT. There will be no extension of time allowed for the process to permit the use of the informal dispute meeting, unless otherwise agreed to by the parties.

SECTION IV TIME FOR BEGINNING AND COMPLETION

Once established, the DRA shall be in operation until the day the Director accepts the contract. The DRA shall not begin work under the terms of this AGREEMENT until authorized in writing by the STATE or as agreed to by the parties.

SECTION V PAYMENT

DRA shall be compensated at an agreed rate of \$1,500 per day for time spent per meeting, either at the start of the project or for a dispute. A member serving on more than one State DRA or DRB, regardless the number of meetings per day, shall not be paid more than the agreed rate per day. The agreed rate shall be considered full compensation for onsite time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof that the DRA is at an authorized DRA meeting. No additional compensation will be made for time spent by DRA to review and research activities outside the official DRA meetings unless that time, (such as time spent evaluating and preparing recommendations on specific issues presented to the DRA), has been specifically agreed to in advance by the parties. Time away from the project, which has been specifically agreed to in advance by the parties, will be compensated at an agreed rate of \$150 per hour. The agreed amount of \$150 per hour shall include all incidentals including expenses for telephone, fax, and computer services. The State will provide administrative services such as conference facilities to the DRA.

A. PAYMENT PROCESSING

CONTRACTOR shall make direct payments to DRA for their participation in authorized meetings and approved hourly rate charges, from invoices submitted by the DRA, and technical services.

DRA may submit invoices to the CONTRACTOR for partial payment for work performed and services rendered for their participation in authorized meetings not more often than once per month during the progress of the work. The invoices shall be in a format approved by the parties and accompanied by a general description of activities performed during that billing period. Payment for hourly fees, at the agreed rate, shall not be paid to a DRA until the amount and extent of those fees are approved by the STATE and CONTRACTOR.

B. INSPECTION OF COSTS RECORDS

DRA and the CONTRACTOR shall keep available for inspection by representatives of the STATE and the United States, for a period of 3 years after final payment, the cost records and accounts pertaining to this AGREEMENT. If any litigation, claim, or audit arising out of, in connection with, or related to this contract is initiated before the expiration of the 3-year period, the cost records and accounts shall be retained until such litigation, claim, or audit involving the records is completed.

SECTION VI ASSIGNMENT OF TASKS OF WORK

DRA shall not assign the work of this AGREEMENT.

SECTION VII TERMINATION OF A DRA MEMBER

DRA may resign after providing not less than 15 days written notice of the resignation to the STATE and CONTRACTOR. The DRA may be terminated, by either party, for failing to fully comply at all times with all required employment or financial disclosure conditions of DRA membership in conformance with the terms of the contract and this AGREEMENT. Each party shall document the need for replacement and substantiate the replacement request in writing to the other party and the DRA.

SECTION VIII LEGAL RELATIONS

The parties hereto mutually understand and agree that the DRA in the performance of duties is acting in the capacity of an independent agent and not as an employee of either party.

No party to this AGREEMENT shall bear a greater responsibility for damages or personal injury than is normally provided by Federal or State of California Law.

Notwithstanding the provisions of this contract that require the CONTRACTOR to indemnify and hold harmless the STATE, the parties shall jointly indemnify and hold harmless the DRA from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRA.

SECTION IX CONFIDENTIALITY

The parties hereto mutually understand and agree that all documents and records provided by the parties in reference to issues brought before the DRA, which documents and records are marked "Confidential - for use by the DRA only," shall be kept in confidence and used only for the purpose of resolution of subject disputes, and for assisting in development of DRA findings and recommendations; that such documents and records will not be utilized or revealed to others, except to officials of the parties who are authorized to act on the subject disputes, for any purposes, during the life of this AGREEMENT. Upon termination of this AGREEMENT, said confidential documents and records, and all copies thereof, shall be returned to the parties who furnished them to the DRA. However, the parties understand that such documents may be subsequently discoverable and admissible in court or arbitration proceedings unless a protective order has been obtained by the party seeking further confidentiality.

SECTION X DISPUTES

Disputes between the parties arising out of the work or other terms of this AGREEMENT that cannot be resolved by negotiation and mutual concurrence between the parties or through the administrative process provided in the contract shall be resolved by arbitration as provided in Section 9-1.10, "Arbitration," of the Standard Specifications. Disputes between the DRA and the parties that cannot be resolved by negotiation and mutual concurrence shall be resolved in the appropriate forum.

SECTION XI VENUE, APPLICABLE LAW, AND PERSONAL JURISDICTION

In the event that any party, including the DRA, deems it necessary to institute arbitration proceedings to enforce any right or obligation under this AGREEMENT, the parties hereto agree that such action shall be initiated in the Office of Administrative Hearings of the State of California. The parties hereto agree that all questions shall be resolved by arbitration by application of California law and that the parties to such arbitration shall have the right of appeal from such decisions to the Superior Court in conformance with the laws of the State of California. Venue for the arbitration shall be Sacramento or any other location as agreed to by the parties.

SECTION XII FEDERAL REVIEW AND REQUIREMENTS

On Federal-Aid contracts, the Federal Highway Administration shall have the right to review the work of the DRA in progress, except for private meetings or deliberations of the DRA.

Other Federal requirements in this agreement shall only apply to Federal-Aid contracts.

SECTION XIII CERTIFICATION OF CONTRACTOR, DRA, AND STATE

IN WITNESS WHEREOF, the parties hereto have executed this AGREEMENT as of the day and year first above written.

DRA

By: _____

Title: _____

CONTRACTOR

CALIFORNIA STATE DEPARTMENT
OF TRANSPORTATION

By: _____

By: _____

Title: _____

Title: _____

5-1.13 COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS

The provisions of this section shall apply only to the following contract items:

ITEM CODE	ITEM
390102	ASPHALT CONCRETE (TYPE A)
374002	ASPHALTIC EMULSION (FOG SEAL COAT)

The compensation payable for paving asphalt used in asphalt concrete and asphaltic emulsion (fog seal coat) will be increased or decreased in conformance with the provisions of this section for paving asphalt price fluctuations exceeding 10 percent (Iu/Ib is greater than 1.10 or less than 0.90) which occur during performance of the work.

The quantity of paving asphalt used in asphaltic emulsion (fog seal coat) will be determined by multiplying the item quantity for asphaltic emulsion (fog seal coat) included in a monthly estimate by the minimum percent residue specified in Section 94, "Asphaltic Emulsions," of the Standard Specifications. The asphaltic emulsion minimum percent residue will be based on the type of emulsion used by the Contractor.

At the Contractor's option, the Contractor may provide actual daily test results for paving asphalt residue for the asphaltic emulsion (fog seal coat) used. Test results provided by the Contractor shall be from an independent testing laboratory that participates in the AASHTO Proficiency Sample Program. The Contractor shall take samples of asphaltic emulsion from the distributor truck at mid-load from a sampling tap or thief. Two separate 2-liter samples shall be taken in the presence of the Engineer. The Contractor shall provide one sample to the Contractor's independent testing laboratory within 24 hours of sampling. The second sample shall be given to the Engineer. The test results from the Contractor's independent testing laboratory shall be delivered to the Engineer within 10 days from sample date.

The adjustment in compensation will be determined in conformance with the following formulae when the item of asphalt concrete or asphaltic emulsion (fog seal coat), or both, are included in a monthly estimate:

- A. Total monthly adjustment = AQ
- B. For an increase in paving asphalt price index exceeding 10 percent:

$$A = 0.90 (1.1023) (Iu/Ib - 1.10) Ib$$

- C. For a decrease in paving asphalt price index exceeding 10 percent:

$$A = 0.90 (1.1023) (Iu/Ib - 0.90) Ib$$

- D. Where:

A = Adjustment in dollars per tonne of paving asphalt used to produce asphalt concrete and asphaltic emulsion residue used as fog seal coat rounded to the nearest \$0.01.

Iu = The California Statewide Paving Asphalt Price Index which is in effect on the first business day of the month within the pay period in which the quantity subject to adjustment was included in the estimate.

Ib = The California Statewide Paving Asphalt Price Index for the month in which the bid opening for the project occurred.

Q = Quantity in tonnes of paving asphalt that was used in producing the quantity of asphalt concrete shown under "This Estimate" on the monthly estimate using the amount of asphalt determined by the Engineer plus the quantity in tonnes of paving asphalt that would have been used as residue in the asphaltic emulsion (fog seal coat) shown under "This Estimate" on the monthly estimate.

The adjustment in compensation will also be subject to the following:

- A. The compensation adjustments provided herein will be shown separately on payment estimates. The Contractor shall be liable to the State for decreased compensation adjustments and the Department may deduct the amount thereof from moneys due or that may become due the Contractor.
- B. Compensation adjustments made under this section will be taken into account in making adjustments in conformance with the provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.

- C. In the event of an overrun of contract time, adjustment in compensation for paving asphalt included in estimates during the overrun period will be determined using the California Statewide Paving Asphalt Price Index in effect on the first business day of the month within the pay period in which the overrun began.

The California Statewide Paving Asphalt Price Index is determined each month on the first business day of the month by the Department using the median of posted prices in effect as posted by Chevron, ExxonMobil, and Union 76 for the Buena Vista, Huntington Beach, and Midway Sunset fields.

In the event that the companies discontinue posting their prices for a field, the Department will determine an index from the remaining posted prices. The Department reserves the right to include in the index determination the posted prices of additional fields.

The California Statewide Paving Asphalt Price Index is available on the Division of Engineering Services website at:

http://www.dot.ca.gov/hq/esc/oe/asphalt_index/astable.html

5-1.14 AREAS FOR CONTRACTOR'S USE

Attention is directed to the provisions in Section 7-1.19, "Rights in Land and Improvements," of the Standard Specifications and these special provisions.

The highway right of way shall be used only for purposes that are necessary to perform the required work. The Contractor shall not occupy the right of way, or allow others to occupy the right of way, for purposes which are not necessary to perform the required work.

No State-owned parcels adjacent to the right of way are available for the exclusive use of the Contractor within the contract limits. The Contractor shall secure, at the Contractor's own expense, areas required for plant sites, storage of equipment or materials, or for other purposes.

No area is available within the contract limits for the exclusive use of the Contractor. However, temporary storage of equipment and materials on State property may be arranged with the Engineer, subject to the prior demands of State maintenance forces and to other contract requirements. Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk, and the State shall not be held liable for damage to or loss of materials or equipment located within such areas.

5-1.15 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount set forth for the contract items of work hereinafter listed shall be deemed to be the maximum value of the contract item of work which will be recognized for progress payment purposes:

A. Clearing and Grubbing	\$10,000.00
B. Demolish Building	\$10,000.00

After acceptance of the contract pursuant to the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, payable for a contract item of work in excess of the maximum value for progress payment purposes hereinabove listed for the item, will be included for payment in the first estimate made after acceptance of the contract.

No partial payment will be made for any materials on hand which are furnished but not incorporated in the work.

5-1.16 PROJECT INFORMATION

The information in this section has been compiled specifically for this project and is made available for bidders and Contractors. Other information referenced in the Standard Specifications and these special provisions do not appear in this section. The information is subject to the conditions and limitations set forth in Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," and Section 6-2, "Local Materials," of the Standard Specifications. Bidders and Contractors shall be responsible for knowing the procedures for obtaining information.

Information attached to the project plans is as follows:

- A. Log of Test Borings.

Information included in the Information Handout provided to bidders and Contractors is as follows:

- A. Foundation Investigation Report.

Cross sections are not available for this project.

5-1.17 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD

This project lies within the boundaries of the North Coast Regional Water Quality Control Board (RWQCB).

The State Water Resources Control Board (SWRCB) has issued to the Department a permit that governs storm water and non-storm water discharges from the Department's properties, facilities, and activities. The Department's permit is entitled "Order No. 99 - 06 - DWQ, NPDES No. CAS000003, National Pollutant Discharge Elimination System (NPDES) Permit, Statewide Storm Water Permit and Waste Discharge Requirements (WDRs) for the State of California, Department of Transportation (Caltrans)." Copies of the Department's permit are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254, and may also be obtained at:

<http://www.swrcb.ca.gov/stormwtr/caltrans.html>

The Department's permit references and incorporates by reference the current statewide general permit issued by the SWRCB entitled "Order No. 99-08-DWQ, National Pollutant Discharge Elimination System (NPDES) General Permit No. CAS000002, Waste Discharge Requirements (WDRs) for Discharges of Storm Water Runoff Associated with Construction Activity" that regulates discharges of storm water and non-storm water from construction activities disturbing 0.4-hectare or more of soil in a common plan of development. Sampling and analysis requirements as specified in SWRCB Resolution No. 2001-46 are added to the statewide general permit. Copies of the statewide permit and modifications thereto are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254 and may also be obtained at:

<http://www.swrcb.ca.gov/stormwtr/construction.html>

The NPDES permits that regulate this project, as referenced above, are collectively referred to in this section as the "permits."

This project shall conform to the permits and modifications thereto. The Contractor shall maintain copies of the permits at the project site and shall make them available during construction.

The Contractor shall know and comply with provisions of Federal, State, and local regulations and requirements that govern the Contractor's operations and storm water and non-storm water discharges from the project site and areas of disturbance outside the project limits during construction. Attention is directed to Sections 7-1.01, "Laws to be Observed," 7-1.11, "Preservation of Property," and 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The Contractor shall be responsible for penalties assessed on the Contractor or the Department as a result of the Contractor's failure to comply with the provisions in "Water Pollution Control" of these special provisions or with the applicable provisions of the Federal, State, and local regulations and requirements.

Penalties as used in this section shall include fines, penalties, and damages, whether proposed, assessed, or levied against the Department or the Contractor, including those levied under the Federal Clean Water Act and the State Porter-Cologne Water Quality Control Act, by governmental agencies or as a result of citizen suits. Penalties shall also include payments made or costs incurred in settlement for alleged violations of applicable laws, regulations, or requirements. Costs incurred could include sums spent instead of penalties, in mitigation or to remediate or correct violations.

WITHHOLDS

The Department will withhold money due the Contractor, in an amount estimated by the Department, to include the full amount of penalties and mitigation costs proposed, assessed, or levied as a result of the Contractor's violation of the permits, or Federal or State law, regulations, or requirements. Funds will be withheld by the Department until final disposition of these costs has been made. The Contractor shall remain liable for the full amount until the potential liability is finally resolved with the entity seeking the penalties. Instead of the withhold, the Contractor may provide a suitable bond in favor of the Department to cover the highest estimated liability for any disputed penalties proposed as a result of the Contractor's violation of the permits, law, regulations, or requirements.

If a regulatory agency identifies a failure to comply with the permits and modifications thereto, or other Federal, State, or local requirements, the Department will withhold money due the Contractor, subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to withhold funds from payments which may become due to the Contractor before acceptance of the contract. Funds withheld after acceptance of the contract will be made without prior notice to the Contractor.
- B. No withholds of additional amounts out of payments will be made if the amount to be withheld does not exceed the amount being withheld from partial payments in accordance with Section 9-1.06, "Partial Payments," of the Standard Specifications.
- C. If the Department has withheld funds and it is subsequently determined that the State is not subject to the entire amount of the costs and liabilities assessed or proposed in connection with the matter for which the withhold was made, the Department will return the excess amount withheld to the Contractor in the progress payment following the determination. If the matter is resolved for less than the amount withheld, the Department will pay interest at a rate of 6 percent per year on the excess withhold.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor, or otherwise access the project site or the Contractor's records pertaining to water pollution control work. The Contractor and the Department shall provide copies of correspondence, notices of violation, enforcement actions, or proposed fines by regulatory agencies to the requesting regulatory agency.

SECTION 6. (BLANK)

SECTION 7. (BLANK)

SECTION 8. MATERIALS

SECTION 8-1. MISCELLANEOUS

8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the United States Standard Measures which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

- A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.
- B. Before other non-metric materials and products will be considered for use, the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.
- C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details, the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The plans and working drawings shall be submitted at least 7 days before the Contractor intends to begin the work involved.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT

ASTM Designation: A 82

METRIC SIZE SHOWN ON THE PLANS mm ²	SIZE TO BE SUBSTITUTED inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

SUBSTITUTION TABLE FOR BAR REINFORCEMENT

METRIC BAR DESIGNATION NUMBER ¹ SHOWN ON THE PLANS	BAR DESIGNATION NUMBER ² TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

¹Bar designation numbers approximate the number of millimeters of the nominal diameter of the bars.

²Bar numbers are based on the number of eighths of an inch included in the nominal diameter of the bars.

No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

SUBSTITUTION TABLE FOR SIZES OF:

- (1) STEEL FASTENERS FOR GENERAL APPLICATIONS (ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55), and
 (2) HIGH STRENGTH STEEL FASTENERS (ASTM Designation: A 325 or A 449)

METRIC SIZE SHOWN ON THE PLANS mm	SIZE TO BE SUBSTITUTED inch
6 or 6.35	1/4
8 or 7.94	5/16
10 or 9.52	3/8
11 or 11.11	7/16
13, 12.70, or M12	1/2
14 or 14.29	9/16
16, 15.88, or M16	5/8
19, 19.05, or M20	3/4
22, 22.22, or M22	7/8
24, 25, 25.40, or M24	1
29, 28.58, or M27	1-1/8
32, 31.75, or M30	1-1/4
35 or 34.93	1-3/8
38, 38.10, or M36	1-1/2
44 or 44.45	1-3/4
51 or 50.80	2
57 or 57.15	2-1/4
64 or 63.50	2-1/2
70 or 69.85	2-3/4
76 or 76.20	3
83 or 82.55	3-1/4
89 or 88.90	3-1/2
95 or 95.25	3-3/4
102 or 101.60	4

SUBSTITUTION TABLE FOR NOMINAL THICKNESS OF SHEET METAL

UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS (GALVANIZED)	
METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch	METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269	-----	-----
0.61	0.0239	-----	-----
0.53	0.0209	-----	-----
0.45	0.0179	-----	-----
0.42	0.0164	-----	-----
0.38	0.0149	-----	-----

SUBSTITUTION TABLE FOR WIRE

METRIC THICKNESS SHOWN ON THE PLANS mm	WIRE THICKNESS TO BE SUBSTITUTED inch	GAGE NO.
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

SUBSTITUTION TABLE FOR PIPE PILES

METRIC SIZE SHOWN ON THE PLANS mm x mm	SIZE TO BE SUBSTITUTED inch x inch
PP 360 x 4.55	NPS 14 x 0.179
PP 360 x 6.35	NPS 14 x 0.250
PP 360 x 9.53	NPS 14 x 0.375
PP 360 x 11.12	NPS 14 x 0.438
PP 406 x 12.70	NPS 16 x 0.500
PP 460 x T	NPS 18 x T"
PP 508 x T	NPS 20 x T"
PP 559 x T	NPS 22 x T"
PP 610 x T	NPS 24 x T"
PP 660 x T	NPS 26 x T"
PP 711 x T	NPS 28 x T"
PP 762 x T	NPS 30 x T"
PP 813 x T	NPS 32 x T"
PP 864 x T	NPS 34 x T"
PP 914 x T	NPS 36 x T"
PP 965 x T	NPS 38 x T"
PP 1016 x T	NPS 40 x T"
PP 1067 x T	NPS 42 x T"
PP 1118 x T	NPS 44 x T"
PP 1219 x T	NPS 48 x T"
PP 1524 x T	NPS 60 x T"

The thickness in millimeters (T) represents an exact conversion of the thickness in inches (T").

SUBSTITUTION TABLE FOR CIDH CONCRETE PILING

METRIC SIZE SHOWN ON THE PLANS	ACTUAL AUGER SIZE TO BE SUBSTITUTED inches
350 mm	14
400 mm	16
450 mm	18
600 mm	24
750 mm	30
900 mm	36
1.0 m	42
1.2 m	48
1.5 m	60
1.8 m	72
2.1 m	84
2.4 m	96
2.7 m	108
3.0 m	120
3.3 m	132
3.6 m	144
4.0 m	156

SUBSTITUTION TABLE FOR STRUCTURAL TIMBER AND LUMBER

METRIC MINIMUM DRESSED DRY, SHOWN ON THE PLANS mm x mm	METRIC MINIMUM DRESSED GREEN, SHOWN ON THE PLANS mm x mm	NOMINAL SIZE TO BE SUBSTITUTED inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

SUBSTITUTION TABLE FOR NAILS AND SPIKES

METRIC COMMON NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC BOX NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC SPIKE, SHOWN ON THE PLANS Length, mm Diameter, mm	SIZE TO BE SUBSTITUTED Penny-weight
50.80 2.87	50.80 2.51	————	6d
63.50 3.33	63.50 2.87	————	8d
76.20 3.76	76.20 3.25	76.20 4.88	10d
82.55 3.76	82.55 3.25	82.55 4.88	12d
88.90 4.11	88.90 3.43	88.90 5.26	16d
101.60 4.88	101.60 3.76	101.60 5.72	20d
114.30 5.26	114.30 3.76	114.30 6.20	30d
127.00 5.72	127.00 4.11	127.00 6.68	40d
————	————	139.70 7.19	50d
————	————	152.40 7.19	60d

SUBSTITUTION TABLE FOR IRRIGATION
COMPONENTS

METRIC WATER METERS, TRUCK LOADING STANDPIPES, VALVES, BACKFLOW PREVENTERS, FLOW SENSORS, WYE STRAINERS, FILTER ASSEMBLY UNITS, PIPE SUPPLY LINES, AND PIPE IRRIGATION SUPPLY LINES SHOWN ON THE PLANS DIAMETER NOMINAL (DN) mm	NOMINAL SIZE TO BE SUBSTITUTED inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

Unless otherwise specified, substitutions of United States Standard Measures standard structural shapes corresponding to the metric designations shown on the plans and in conformance with the requirements in ASTM Designation: A 6/A 6M, Annex 2, will be allowed.

8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS

The Department maintains the following list of Prequalified and Tested Signing and Delineation Materials. The Engineer shall not be precluded from sampling and testing products on the list of Prequalified and Tested Signing and Delineation Materials.

The manufacturer of products on the list of Prequalified and Tested Signing and Delineation Materials shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

For those categories of materials included on the list of Prequalified and Tested Signing and Delineation Materials, only those products shown within the listing may be used in the work. Other categories of products, not included on the list of Prequalified and Tested Signing and Delineation Materials, may be used in the work provided they conform to the requirements of the Standard Specifications.

Materials and products may be added to the list of Prequalified and Tested Signing and Delineation Materials if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

PAVEMENT MARKERS, PERMANENT TYPE

Retroreflective With Abrasion Resistant Surface (ARS)

1. Apex, Model 921AR (100 mm x 100 mm)
2. Ennis Paint, Models C88 (100 mm x 100 mm), 911 (100 mm x 100 mm) and 953 (70 mm x 114 mm)
3. Ray-O-Lite, Model "AA" ARS (100 mm x 100 mm)
4. 3M Series 290 (89 mm x 100 mm)
5. 3M Series 290 PSA, with pressure sensitive adhesive pad (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

(for recessed applications only)

1. Ennis Paint, Model 948 (58 mm x 119 mm)
 2. Ennis Paint, Model 944SB (51 mm x 100 mm)*
 3. Ray-O-Lite, Model 2002 (51 mm x 117 mm)
 4. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)*
- *For use only in 114 mm wide (older) recessed slots

Non-Reflective, 100-mm Round

1. Apex Universal (Ceramic)
2. Apex Universal, Models 929 (ABS) and 929PP (Polypropylene)
3. Glowlite, Inc. (Ceramic)
4. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
5. Interstate Sales, "Diamond Back" (Polypropylene)
6. Novabrite Models Cdot (White) Cdot-y (Yellow), Ceramic
7. Novabrite Models Pdot-w (White) Pdot-y (Yellow), Polypropylene
8. Three D Traffic Works TD10000 (ABS), TD10500 (Polypropylene)

PAVEMENT MARKERS, TEMPORARY TYPE

Temporary Markers For Long Term Day/Night Use (180 days or less)

1. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

Temporary Markers For Short Term Day/Night Use (14 days or less)

(For seal coat or chip seal applications, clear protective covers are required)

1. Apex Universal, Model 932
2. Filtrona Extrusion, Models T.O.M., T.R.P.M., and "HH" (High Heat)
3. Hi-Way Safety, Inc., Model 1280/1281
4. Glowlite, Inc., Model 932

STRIPING AND PAVEMENT MARKING MATERIAL

Permanent Traffic Striping and Pavement Marking Tape

1. Advanced Traffic Marking, Series 300 and 400
2. Brite-Line, Series 1000
3. Brite-Line, "DeltaLine XRP"
4. Swarco Industries, "Director 35" (For transverse application only)
5. Swarco Industries, "Director 60"
6. 3M, "Stamark" Series 380 and 5730
7. 3M, "Stamark" Series 420 (For transverse application only)

Temporary (Removable) Striping and Pavement Marking Tape (180 days or less)

1. Advanced Traffic Marking, Series 200
2. Brite-Line, Series 100
3. Garlock Rubber Technologies, Series 2000
4. P.B. Laminations, Aztec, Grade 102
5. Swarco Industries, "Director-2"
6. Trelleborg Industries, R140 Series
7. 3M Series 620 "CR", and Series A750
8. 3M Series A145, Removable Black Line Mask

- (Black Tape: for use only on Asphalt Concrete Surfaces)
9. Advanced Traffic Marking Black "Hide-A-Line"
(Black Tape: for use only on Asphalt Concrete Surfaces)
 10. Brite-Line "BTR" Black Removable Tape
(Black Tape: for use only on Asphalt Concrete Surfaces)
 11. Trelleborg Industries, RB-140
(Black Tape: for use only on Asphalt Concrete Surfaces)

Preformed Thermoplastic (Heated in place)

1. Flint Trading Inc., "Hot Tape"
2. Flint Trading Inc., "Premark Plus"
3. Ennis Paint Inc., "Flametape"

Ceramic Surfacing Laminate, 150 mm x 150 mm

1. Highway Ceramics, Inc.

CLASS 1 DELINEATORS

One Piece Driveable Flexible Type, 1700-mm

1. Filtrona Extrusion, "Flexi-Guide Models 400 and 566"
2. Carsonite, Curve-Flex CFRM-400
3. Carsonite, Roadmarker CRM-375
4. FlexStake, Model 654 TM
5. GreenLine Model CGD1-66

Special Use Type, 1700-mm

1. Filtrona Extrusion, Model FG 560 (with 450-mm U-Channel base)
2. Carsonite, "Survivor" (with 450-mm U-Channel base)
3. Carsonite, Roadmarker CRM-375 (with 450-mm U-Channel base)
4. FlexStake, Model 604
5. GreenLine Model CGD (with 450-mm U-Channel base)
6. Impact Recovery Model D36, with #105 Driveable Base
7. Safe-Hit with 200-mm pavement anchor (SH248-GP1)
8. Safe-Hit with 380-mm soil anchor (SH248-GP2) and with 450-mm soil anchor (SH248-GP3)

Surface Mount Type, 1200-mm

1. Bent Manufacturing Company, Masterflex Model MF-180EX-48
2. Carsonite, "Channelizer"
3. FlexStake, Models 704, 754 TM, and EB4
4. Impact Recovery Model D48, with #101 Fixed (Surface-Mount) Base
5. Three D Traffic Works "Channelflex" ID No. 522248W

CHANNELIZERS

Surface Mount Type, 900-mm

1. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
2. Filtrona Extrusion, Flexi-Guide Models FG300PE, FG300UR, and FG300EFX
3. Carsonite, "Super Duck" (Round SDR-336)
4. Carsonite, Model SDCF03601MB "Channelizer"
5. FlexStake, Models 703, 753 TM, and EB3
6. GreenLine, Model SMD-36
7. Hi-way Safety, Inc. "Channel Guide Channelizer" Model CGC36
8. Impact Recovery Model D36, with #101 Fixed (Surface-Mount) Base
9. Safe-Hit, Guide Post, Model SH236SMA
10. Three D Traffic Works "Boomerang" ID No. 522053W

Lane Separation System

1. Filtrona Extrusion, "Flexi-Guide (FG) 300 Curb System"
2. Qwick Kurb, "Klemmfix Guide System"
3. Dura-Curb System

CONICAL DELINEATORS, 1070-mm

(For 700-mm Traffic Cones, see Standard Specifications)

1. Bent Manufacturing Company "T-Top"
2. Plastic Safety Systems "Navigator-1070 mm"
3. Traffix Devices "Grabber"
4. Three D Traffic Works "Ringtop" TD7000, ID No. 742143
5. Three D Traffic Works, TD7500

OBJECT MARKERS

Type "K", 450-mm

1. Filtrona Extrusion, Model FG318PE
2. Carsonite, Model SMD 615
3. FlexStake, Model 701 KM
4. Safe-Hit, Model SH718SMA

Type "K-4" / "Q" Object Markers, 600-mm

1. Bent Manufacturing "Masterflex" Model MF-360-24
2. Filtrona Extrusion, Model FG324PE
3. Carsonite, "Channelizer"
4. FlexStake, Model 701KM
5. Safe-Hit, Models SH824SMA_WA and SH824GP3_WA
6. Three D Traffic Works ID No. 531702W and TD 5200
7. Three D Traffic Works ID No. 520896W

CONCRETE BARRIER MARKERS AND TEMPORARY RAILING (TYPE K) REFLECTORS

Impactable Type

1. ARTUK, "FB"
2. Filtrona Extrusion, Models PCBM-12 and PCBM-T12
3. Duraflex Corp., "Flexx 2020" and "Electriflexx"
4. Hi-Way Safety, Inc., Model GMKRM100
5. Plastic Safety Systems "BAM" Models OM-BARR and OM-BWAR
6. Three D Traffic Works "Roadguide" Model TD 9304

Non-Impactable Type

1. ARTUK, JD Series
2. Plastic Safety Systems "BAM" Models OM-BITARW and OM-BITARA
3. Vega Molded Products, Models GBM and JD
4. Plastic Vacuum Forming, "Cap-It C400"

METAL BEAM GUARD RAIL POST MARKERS

(For use to the left of traffic)

1. Filtrona Extrusion, "Mini" (75 mm x 254 mm)
2. Creative Building Products, "Dura-Bull, Model 11201"
3. Duraflex Corp., "Railrider"
4. Plastic Vacuum Forming, "Cap-It C300"

CONCRETE BARRIER DELINEATORS, 400-mm

(For use to the right of traffic)

1. Filtrona Extrusion, Model PCBM T-16
2. Safe-Hit, Model SH216RBM

CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)

1. Stinson Equipment Company "SaddleMarker"

GUARD RAILING DELINEATOR

(Place top of reflective element at 1200 mm above plane of roadway)

Wood Post Type, 686-mm

1. Filtrona Extrusion, FG 427 and FG 527
2. Carsonite, Model 427
3. FlexStake, Model 102 GR
4. GreenLine GRD 27
5. Safe-Hit, Model SH227GRD
6. Three D Traffic Works "Guardflex" TD9100
7. New Directions Mfg, NDM27

Steel Post Type

1. Carsonite, Model CFGR-327

RETROREFLECTIVE SHEETING

Channelizers, Barrier Markers, and Delineators

1. Avery Dennison T-6500 Series (For rigid substrate devices only)
2. Avery Dennison WR-7100 Series
3. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
4. Reflexite, PC-1000 Metalized Polycarbonate
5. Reflexite, AC-1000 Acrylic
6. Reflexite, AP-1000 Metalized Polyester
7. Reflexite, Conformalight, AR-1000 Abrasion Resistant Coating
8. 3M, High Intensity

Traffic Cones, 100-mm and 150-mm Sleeves

1. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
2. Reflexite, Vinyl, "TR" (Semi-transparent) or "Conformalight"
3. 3M Series 3840
4. Avery Dennison S-9000C

Drums

1. Avery Dennison WR-6100
2. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
3. Reflexite, "Conformalight", "Super High Intensity" or "High Impact Drum Sheeting"
4. 3M Series 3810

Barricades: Type I, Medium-Intensity (Typically Enclosed Lens, Glass-Bead Element)

1. Nippon Carbide Industries, CN8117
2. Avery Dennison, W 1100 series
3. 3M Series CW 44

Barricades: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)

1. Avery Dennison, W-2100 Series

Signs: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)

1. Avery Dennison, T-2500 Series
2. Nippon Carbide Industries, Nikkalite 18000

Signs: Type III, High-Intensity (Typically Encapsulated Glass-Bead Element)

1. Avery Dennison, T-5500A and T-6500 Series
2. Nippon Carbide Industries, Nikkalite Brand Ultralite Grade II
3. 3M 3870 and 3930 Series

Signs: Type IV, High-Intensity (Typically Unmetallized Microprismatic Element)

1. Avery Dennison, T-6500 Series
2. Nippon Carbide Industries, Crystal Grade, 94000 Series
3. Nippon Carbide Industries, Model No. 94847 Fluorescent Orange
4. 3M Series 3930 and Series 3924S

Signs: Type VI, Elastomeric (Roll-Up) High-Intensity, without Adhesive

1. Avery Dennison, WU-6014
2. Novabrite LLC, "Econobrite"
3. Reflexite "Vinyl"
4. Reflexite "SuperBright"
5. Reflexite "Marathon"
6. 3M Series RS20

Signs: Type VII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)

1. 3M Series 3924S, Fluorescent Orange
2. 3M LDP Series 3970

Signs: Type VIII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)

1. Avery Dennison, T-7500 Series
2. Avery Dennison, T-7511 Fluorescent Yellow
3. Avery Dennison, T-7513 Fluorescent Yellow Green
4. Avery Dennison, W-7514 Fluorescent Orange
5. Nippon Carbide Industries, Nikkalite Crystal Grade Series 92800
6. Nippon Carbide Industries, Nikkalite Crystal Grade Model 92847 Fluorescent Orange

Signs: Type IX, Very-High-Intensity (Typically Unmetallized Microprismatic Element)

1. 3M VIP Series 3981 Diamond Grade Fluorescent Yellow
2. 3M VIP Series 3983 Diamond Grade Fluorescent Yellow/Green
3. 3M VIP Series 3990 Diamond Grade
4. Avery Dennison T-9500 Series
5. Avery Dennison, T9513, Fluorescent Yellow Green
6. Avery Dennison, W9514, Fluorescent Orange

SPECIALTY SIGNS

1. Reflexite "Endurance" Work Zone Sign (with Semi-Rigid Plastic Substrate)

ALTERNATIVE SIGN SUBSTRATES

Fiberglass Reinforced Plastic (FRP) and Expanded Foam PVC

1. Fiber-Brite (FRP)
2. Sequentia, "Polyplate" (FRP)
3. Intoplast Group "InteCel" (13 mm for Post-Mounted CZ Signs, 1200 mm or less)(PVC)

Aluminum Composite, Temporary Construction Signs Only

1. Alcan Composites "Dibond Material, 2 mm"
2. Mitsubishi Chemical America, Alpollic 350

8-1.03 ENGINEERING FABRICS

Engineering fabrics shall conform to the provisions in Section 88, "Engineering Fabrics," of the Standard Specifications and these special provisions.

8-1.04 ASPHALTIC EMULSION

Asphaltic emulsion shall conform to the provisions in Section 94, "Asphaltic Emulsions," of the Standard Specifications and these special provisions.

When tested in conformance with the "Residue and Oil Distillate by Distillation" test of AASHTO Designation: T 59, the composition of SS1 asphaltic emulsion shall be a minimum 57 percent of residue.

SECTION 8-2. CONCRETE

8-2.01 PORTLAND CEMENT CONCRETE

Portland cement concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

The Department maintains a list of sources of fine and coarse aggregate that have been approved for use with a reduced amount of supplementary cementitious material in the total amount of cementitious material to be used. A source of aggregate will be considered for addition to the approved list if the producer of the aggregate submits to the Transportation Laboratory certified test results from a qualified testing laboratory that verify the aggregate complies with the requirements. Before the testing starts, the aggregate test shall be registered with the Department. A registration number can be obtained by calling (916) 227-7228. The registration number shall be used as the identification for the aggregate sample in correspondence with the Department. Upon request, a split of the tested sample shall be provided to the Department. Approval of aggregate will depend upon compliance with the specifications, based on the certified test results submitted, together with any replicate testing the Department may elect to perform. Approval will expire 3 years from the date the most recent registered and evaluated sample was collected from the aggregate source.

Qualified testing laboratories shall conform to the following requirements:

1. Laboratories performing ASTM Designation: C 1293 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Concrete Proficiency Sample Program and shall have received a score of 3 or better on each test of the previous 2 sets of concrete samples.
2. Laboratories performing ASTM Designation: C 1260 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Pozzolan Proficiency Sample Program and shall have received a score of 3 or better on the shrinkage and soundness tests of the previous 2 sets of pozzolan samples.

Aggregates on the list shall conform to one of the following requirements:

1. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1293, the average expansion at one year shall be less than or equal to 0.040 percent; or
2. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1260, the average of the expansion at 16 days shall be less than or equal to 0.15 percent.

If the aggregates used in the concrete are on the Department's list, the minimum amount of supplementary cementitious material shall conform to the following:

1. If fly ash or natural pozzolan conforming to the provisions in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials," of the Standard Specifications is used, the minimum amount of supplementary cementitious material shall be 15 percent by mass of the total cementitious material; or
2. If silica fume conforming to the provisions in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials," of the Standard Specifications is used, the minimum amount of supplementary cementitious material shall be 7 percent by mass of the total cementitious material.

The limitation on tricalcium silicate (C₃S) content in Type II cement specified in Section 90-2.01A, "Cement," of the Standard Specifications shall not apply.

8-2.02 FREEZING CONDITION REQUIREMENTS

The mortar strength of fine aggregate relative to the mortar strength of Ottawa sand shall be a minimum of 100 percent as determined by California Test 515.

Portland cement concrete shall contain not less than 350 kilograms of cementitious material per cubic meter unless a higher cementitious material content is required elsewhere in these special provisions.

An air-entraining admixture conforming to the provisions in Section 90-4, "Admixtures," of the Standard Specifications shall be added to the concrete at the rate required to result in an air content of 6.0 ± 1.5 percent in the freshly mixed concrete, unless a different air content is specified in these special provisions.

SECTION 8-3. (BLANK)

SECTION 9. (BLANK)

SECTION 10. CONSTRUCTION DETAILS

SECTION 10-1. GENERAL

10-1.01 ORDER OF WORK

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

All underground utility work shall be completed by October 1, before any other work is allowed to proceed. Trenches for underground utilities shall not be left open for more than 48 hours. The site shall be graded to finished subgrade. This work shall be staged such that the State has full access to the facility.

The Contractor's schedule submittal shall be approved by the Engineer prior to constructing slabs, retaining walls and footings.

All materials required to complete the new main switchboard work shall be on hand before beginning the work.

The Contractor shall notify the Engineer, in writing, 14 calendar days prior to connecting the new main switchboard.

The entire facility shall be de-energized to connect to the new main switchboard. The facility shall be de-energized beginning at 5 p.m. on a Friday and fully functional by 9 a.m. the following Monday. Power to the existing facility shall be maintained until the new main switchboard is ready for energization.

During the power switchover process, at the existing facility, phase sequencing of the new electrical service shall be the same as the phase sequencing of the existing electrical service.

The final order of work shall be placing a fog seal coat on all asphalt concrete.

Attention is directed to "Miscellaneous Concrete Construction" of these special provisions regarding constructing a 600 mm by 600 mm test panel prior to constructing curb ramps with detectable warning surfaces.

Attention is directed to "Water Pollution Control" of these special provisions regarding the submittal and approval of the Storm Water Pollution Prevention Plan prior to performing work having potential to cause water pollution.

The work shall be performed in conformance with the stages of construction shown on the plans. Nonconflicting work in subsequent stages may proceed concurrently with work in preceding stages, provided satisfactory progress is maintained in the preceding stages of construction.

Prior to applying asphalt concrete (Type A), the Contractor shall cover all manholes, valve and monument covers, grates, or other exposed facilities located within the area of application, using a plastic or oil resistant construction paper secured to the facility being covered by tape or adhesive. The covered facilities shall be referenced by the Contractor, with a sufficient number of control points to relocate the facilities after the asphaltic emulsion (Fog Seal Coat) has been placed. After completion of the asphaltic emulsion (Fog Seal Coat) operation, all covers shall be removed and disposed of in a manner satisfactory to the Engineer. Full compensation for covering manholes, valve and monument covers, grates, or other exposed facilities, referencing, and removing temporary cover shall be considered as included in the contract price paid per tonne for asphalt concrete (Type A), and no additional compensation will be allowed therefor.

All paving shall be completed to within 1.5 m of the building slabs and aprons or a final lift may be held off until all building work is complete.

10-1.02 WATER POLLUTION CONTROL

GENERAL

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, section of these special provisions entitled "Relations With California Regional Water Quality Control Board," and these special provisions.

The Contractor may obtain other National Pollutant Discharge Elimination System (NPDES) permits that apply to activities and mobile operations within or outside of the project limits including asphalt batch plants, material borrow areas, concrete plants, staging areas, storage yards, or access roads.

The Contractor shall perform water pollution control work in conformance with the requirements in the "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual" and its addenda in effect on the day the Notice to Contractors is dated. This manual is referred to as the "Preparation Manual." Copies of the Preparation Manual may be obtained from:

State of California
Department of Transportation
Publication Distribution Unit
1900 Royal Oaks Drive
Sacramento, California 95815
Telephone: (916) 445-3520

The Preparation Manual and other references for performing water pollution control work are available from the Department's Construction Storm Water and Water Pollution Control web site at:

<http://www.dot.ca.gov/hq/construc/stormwater/stormwater1.htm>

Before the start of job site activities, the Contractor shall provide training for project managers, supervisory personnel, and employees involved with water pollution control work. The training shall include:

- A. Rules and regulations
- B. Implementation and maintenance for:
 - 1. Temporary Soil Stabilization
 - 2. Temporary Sediment Control
 - 3. Tracking Control
 - 4. Wind Erosion Control

The Contractor shall designate in writing a Water Pollution Control Manager (WPCM). The Contractor shall submit a statement of qualifications describing the training, work history, and expertise of the proposed WPCM. The qualifications shall include either:

- A. A minimum of 24 hours of Department approved storm water management training described at Department's Construction Storm Water and Water Pollution Control web site.
- B. Certification as a Certified Professional in Erosion and Sediment Control (CPESC).

The WPCM shall be:

- A. Responsible for water pollution control work.
- B. The primary contact for water pollution control work.
- C. Have authority to mobilize crews to make immediate repairs to water pollution control practices.

The Contractor may designate one manager to prepare the SWPPP and a different manager to implement the plan. The WPCP preparer shall meet the training requirements for the WPCM.

STORM WATER POLLUTION PREVENTION PLAN

The Contractor shall submit a Storm Water Pollution Prevention Plan (SWPPP) to the Engineer for approval. The SWPPP shall conform to the requirements in the Preparation Manual, the NPDES permit, and these special provisions. The SWPPP shall be submitted in place of the water pollution control program required by the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications.

The SWPPP shall include water pollution control practices:

- A. For storm water and non-storm water from areas outside of the job site related to construction activities for this contract such as:
 - 1. Staging areas.
 - 2. Storage yards.
 - 3. Access roads.
- B. Appropriate for each season as described in "Implementation Requirements" of these special provisions.
- C. For activities or mobile operations related to all NPDES permits.

The SWPPP shall include a schedule that:

- A. Describes when work activities that could cause water pollution will be performed.
- B. Identifies soil stabilization and sediment control practices for disturbed soil area.
- C. Includes dates when these practices will be 25, 50, and 100 percent complete.
- D. Shows 100 percent completion of these practices before the rainy season.

The SWPPP shall include the following temporary water pollution control practices and their associated contract items of work as shown on the plans or specified in these special provisions:

- A. Temporary Sediment Control
 1. Temporary Fiber Roll
 1. Temporary Check Dam
- B. Waste Management and Materials Pollution Control
 1. Temporary Concrete Washout Facility

Within 20 days after contract approval, the Contractor shall submit 3 copies of the SWPPP to the Engineer. The Contractor shall allow 20 days for the Engineer's review. If revisions are required, the Engineer will provide comments and specify the date that the review stopped. The Contractor shall revise and resubmit the SWPPP within 15 days of receipt of the Engineer's comments. The Engineer's review will resume when the complete SWPPP is resubmitted. When the Engineer approves the SWPPP, the Contractor shall submit 4 copies of the approved SWPPP to the Engineer. The Contractor may proceed with construction activities if the Engineer conditionally approves the SWPPP while minor revisions are being completed. If the Engineer fails to complete the review within the time allowed and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay, the Contractor will be compensated for resulting losses, and an extension of time will be granted, as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Contractor shall not perform work that may cause water pollution until the SWPPP has been approved by the Engineer. The Engineer's review and approval shall not waive any contract requirements and shall not relieve the Contractor from complying with Federal, State and local laws, regulations, and requirements.

The Contractor shall amend the SWPPP annually and shall resubmit it to the Engineer 25 days before the defined rainy season.

If there is a change in construction schedule or activities, the Contractor shall prepare an amendment to the SWPPP to identify additional or revised water pollution control practices. The Contractor shall submit the amendment to the Engineer for review within a time agreed to by the Engineer not to exceed the number of days specified for the initial submittal of the SWPPP. The Engineer will review the amendment within the same time allotted for the review of the initial submittal of the SWPPP.

If directed by the Engineer or requested in writing by the Contractor and approved by the Engineer, changes to the water pollution control work specified in these special provisions will be allowed. Changes may include addition of new water pollution control practices. The Contractor shall incorporate these changes in the SWPPP. Additional water pollution control work will be paid for as extra work in accordance with Section 4-1.03, "Extra work," of the Standard Specifications.

The Contractor shall keep a copy of the approved SWPPP at the job site. The SWPPP shall be made available when requested by a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency, or the local storm water management agency. Requests from the public shall be directed to the Engineer.

IMPLEMENTATION REQUIREMENTS

The Contractor's responsibility for SWPPP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications.

If the Contractor or the Engineer identifies a deficiency in the implementation of the approved SWPPP, the deficiency shall be corrected immediately, unless an agreed date for correction is approved in writing by the Engineer. The deficiency shall be corrected before the onset of precipitation. If the Contractor fails to correct the deficiency by the agreed date or before the onset of precipitation, the Department may correct the deficiency and deduct the cost of correcting deficiencies from payments.

If the Contractor fails to conform to the provisions of this section, "Water Pollution Control," the Engineer may order the suspension of work until the project complies with the requirements of this section.

Year-Round

The Contractor shall monitor the National Weather Service weather forecast on a daily basis during the contract. The Contractor may use an alternative weather forecasting service if approved by the Engineer. Appropriate water pollution control practices shall be in place before precipitation.

The Contractor may discontinue earthwork operations for a disturbed area for up to 21 days and the disturbed soil area will still be considered active. When earthwork operations in the disturbed area have been completed, the Contractor shall implement appropriate water pollution control practices within 15 days, or before predicted precipitation, whichever occurs first.

Rainy Season

The Contractor shall provide soil stabilization and sediment control practices during the rainy season between October 15 and April 15.

The Contractor shall implement soil stabilization and sediment control practices a minimum of 10 days before the start of the rainy season.

During the defined rainy season, the active disturbed soil area of the project site shall be not more than 2 hectares. The Engineer may approve expansions of the active disturbed soil area limit if requested in writing. The Contractor shall maintain soil stabilization and sediment control materials on site to protect disturbed soil areas.

INSPECTION AND MAINTENANCE

The WPCM shall inspect the water pollution control practices identified in the SWPPP as follows:

- A. Before a forecasted storm,
- B. After precipitation that causes site runoff,
- C. At 24-hour intervals during extended precipitation,
- D. On a predetermined schedule, a minimum of once every 2 weeks outside of the defined rainy season, and
- E. On a predetermined schedule, a minimum of once a week during the defined rainy season.

The WPCM shall oversee the maintenance of the water pollution control practices.

The WPCM shall use the Storm Water Quality Construction Site Inspection Checklist provided in the Preparation Manual or an alternative inspection checklist provided by the Engineer. A copy of the completed site inspection checklist shall be submitted to the Engineer within 24 hours of finishing the inspection.

REPORTING REQUIREMENTS

If the Contractor identifies discharges into surface waters or drainage systems causing or potentially causing pollution, or if the project receives a written notice or order from a regulatory agency, the Contractor shall immediately inform the Engineer. The Contractor shall submit a written report to the Engineer within 7 days of the discharge, notice or order. The report shall include the following information:

- A. The date, time, location, and nature of the operation, type of discharge and quantity, and the cause of the notice or order.
- B. The water pollution control practices used before the discharge, or before receiving the notice or order.
- C. The date of placement and type of additional or altered water pollution control practices placed after the discharge, or after receiving the notice or order.
- D. A maintenance schedule for affected water pollution control practices.

Annual Certifications

By June 15 of each year, the Contractor shall complete and submit to the Engineer an Annual Certification of Compliance, as contained in the Preparation Manual.

PAYMENT

During each estimate period the Contractor fails to conform to the provisions in this section, "Water Pollution Control," or fails to implement the water pollution control practices shown on the plans or specified elsewhere in these special provisions as items of work, the Department will withhold 25 percent of the progress payment.

Withholds for failure to perform water pollution control work will be in addition to all other withholds provided for in the contract. The Department will return performance-failure withholds in the progress payment following the correction of noncompliance.

The contract lump sum price paid for prepare storm water pollution prevention plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in preparing, obtaining approval of, and amending the SWPPP, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Payments for prepare storm water pollution prevention plan will be made as follows:

- A. After the SWPPP has been approved by the Engineer, 50 percent of the contract item price for prepare storm water pollution prevention plan will be included in the monthly progress estimate.
- B. Forty percent of the contract item price for prepare storm water pollution prevention plan will be paid over the life of the contract.
- C. After acceptance of the contract in conformance with the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, payment for the remaining 10 percent of the contract item price for prepare storm water pollution prevention plan will be made in conformance with the provisions in Section 9-1.07A, "Payment Prior to Proposed Final Estimate."

Implementation of water pollution control practices in areas outside the highway right of way not specifically provided for in the SWPPP or in these special provisions will not be paid for.

Water pollution control practices for which there are separate contract items of work will be measured and paid for as those contract items of work.

10-1.03 CONSTRUCTION SITE MANAGEMENT

Construction site management shall consist of controlling potential sources of water pollution before they come in contact with storm water systems or watercourses. The Contractor shall control material pollution and manage waste and non-storm water existing at the construction site by implementing effective handling, storage, use, and disposal practices.

Attention is directed to "Water Pollution Control" of these special provisions regarding the Contractor's appointment of a water pollution control manager (WPCM) for the project.

The Contractor shall train all employees and subcontractors regarding:

- A. Material pollution prevention and control;
- B. Waste management;
- C. Non-storm water management;
- D. Identifying and handling hazardous substances; and
- E. Potential dangers to humans and the environment from spills and leaks or exposure to toxic or hazardous substances.

Training shall take place before starting work on this project. New employees shall receive the complete training before starting work on this project. The Contractor shall have regular meetings to discuss and reinforce spill prevention and control; material delivery, storage, use, and disposal; waste management; and non-storm water management procedures.

Instructions for material and waste handling, storage, and spill reporting and cleanup shall be posted at all times in an open, conspicuous, and accessible location at the construction site.

Nonhazardous construction site waste and excess material shall be recycled when practical or disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications, unless otherwise specified.

Vehicles and equipment at the construction site shall be inspected by the WPCM on a frequent, predetermined schedule, and by the operator each day of use. Leaks shall be repaired immediately, or the vehicle or equipment shall be removed from the construction site.

SPILL PREVENTION AND CONTROL

The Contractor shall implement spill and leak prevention procedures when chemicals or hazardous substances are stored. Spills of petroleum products; substances listed under CFR Title 40, Parts 110, 117, and 302; and sanitary and septic waste shall be contained and cleaned up as soon as is safe.

Minor spills involve small quantities of oil, gasoline, paint, or other material that can be controlled by the first responder upon discovery of the spill. Cleanup of minor spills includes:

- A. Containing the spread of the spill,
- B. Recovering the spilled material using absorption,
- C. Cleaning the contaminated area, and
- D. Disposing of contaminated material promptly and properly.

Semi-significant spills are those that can be controlled by the first responder with the help of other personnel. Cleanup of semi-significant spills shall be immediate. Cleanup of semi-significant spills includes:

- A. Containing the spread of the spill;
- B. Recovering the spilled material using absorption if the spill occurs on paved or an impermeable surface;
- C. Containing the spill with an earthen dike and digging up contaminated soil for disposal if the spill occurs on dirt;
- D. Covering the spill with plastic or other material to prevent contaminating runoff if the spill occurs during precipitation; and
- E. Disposing of contaminated material promptly and properly.

Significant or hazardous spills are those that cannot be controlled by construction personnel. Notifications of these spills shall be immediate. The following steps shall be taken:

- A. Construction personnel shall not attempt to cleanup the spill until qualified staff have arrived;
- B. Notify the Engineer and follow up with a written report;
- C. Obtain the services of a spills contractor or hazardous material team immediately;
- D. Notify the local emergency response team by dialing 911 and county officials at the emergency phone numbers kept on the construction site;
- E. Notify the Governor's Office of Emergency Services Warning Center at (805) 852-7550;
- F. Notify the National Response Center at (800) 424-8802 regarding spills of Federal reportable quantities in conformance with CFR Title 40, Parts 110, 119, and 302;
- G. Notify other agencies as appropriate, including:
 1. Fire Department,
 2. Public Works Department,
 3. Coast Guard,
 4. Highway Patrol,
 5. City Police or County Sheriff Department,
 6. Department of Toxic Substances,
 7. California Division of Oil and Gas,
 8. Cal OSHA, or
 9. Regional Water Resources Control Board.

The WPCM shall oversee and enforce proper spill prevention and control measures. Minor, semi-significant, and significant spills shall be reported to the Contractor's WPCM who shall notify the Engineer immediately.

The Contractor shall prevent spills from entering storm water runoff before and during cleanup. Spills shall not be buried or washed with water.

The Contractor shall keep material or waste storage areas clean, well organized, and equipped with enough cleanup supplies for the material being stored. Plastic shall be placed under paving equipment when not in use to catch drips.

MATERIAL MANAGEMENT

Material shall be delivered, used, and stored for this contract in a manner that minimizes or eliminates discharge of material into the air, storm drain systems, or watercourses.

The Contractor shall implement the practices described in this section when taking delivery of, using, or storing the following materials:

- A. Hazardous chemicals including:
 1. Acids,
 2. Lime,
 3. Glues,
 4. Adhesives,
 5. Paints,
 6. Solvents, and
 7. Curing compounds;

- B. Soil stabilizers and binders;
- C. Fertilizers;
- D. Detergents;
- E. Plaster;
- F. Petroleum products including:
 - 1. Fuel,
 - 2. Oil, and
 - 3. Grease;
- G. Asphalt components and concrete components; and
- H. Pesticides and herbicides.

The Contractor shall supply the Material Safety Data Sheet to the Engineer for material used or stored. The Contractor shall keep an accurate inventory of material delivered and stored at the construction site.

Employees trained in emergency spill cleanup procedures shall be present when hazardous materials or chemicals are unloaded.

The Contractor shall use recycled or less hazardous products when practical.

Material Storage

The Contractor shall store liquids, petroleum products, and substances listed in CFR Title 40, Parts 110, 117, and 302 in containers or drums approved by the United States Environmental Protection Agency, and place them in secondary containment facilities.

Secondary containment facilities shall be impervious to the materials stored there for a minimum contact time of 72 hours.

Throughout the rainy season secondary containment facilities shall be covered during non-working days and when precipitation is predicted. Secondary containment facilities shall be adequately ventilated.

The Contractor shall keep the secondary containment facility free of accumulated rainwater or spills. After precipitation, or in the event of spills or leaks, accumulated liquid shall be collected and placed into drums within 24 hours. These liquids shall be handled as hazardous waste in accordance with the provisions in "Hazardous Waste" of these special provisions, unless testing determines them to be nonhazardous.

Incompatible materials, such as chlorine and ammonia, shall not be stored in the same secondary containment facility.

Materials shall be stored in the original containers with the original product labels maintained in legible condition. Damaged or illegible labels shall be replaced immediately.

The secondary containment facility shall have the capacity to contain precipitation from a 24-hour-long, 25-year storm; and 10 percent of the aggregate volume of all containers, or all of the volume of the largest container within the facility, whichever is greater.

The Contractor shall store bagged or boxed material on pallets. Throughout the rainy season, bagged or boxed material shall be protected from wind and rain during non-working days and when precipitation is predicted.

The Contractor shall provide sufficient separation between stored containers to allow for spill cleanup or emergency response access. Storage areas shall be kept clean, well organized, and equipped with cleanup supplies appropriate for the materials being stored.

The Contractor shall repair or replace perimeter controls, containment structures, covers, and liners as needed. Storage areas shall be inspected before and after precipitation, and at least weekly during other times.

Stockpile Management

The Contractor shall reduce or eliminate potential air and water pollution from stockpiled material including soil, paving material, or pressure treated wood. Stockpiles shall be located out of floodplains when possible, and at least 15 m from concentrated flows of storm water, drainage courses, or inlets unless written approval is obtained from the Engineer.

The Contractor may discontinue adding or removing material for up to 21 days and a stockpile will still be considered active.

The Contractor shall protect active stockpiles with plastic or geotextile cover, soil stabilization measures, or with linear sediment barrier when precipitation is predicted. Active stockpiles of cold mix asphalt concrete shall be placed on an impervious surface and covered with plastic when precipitation is predicted.

The Contractor shall protect inactive soil stockpiles with a plastic or geotextile cover, or with soil stabilization measures at all times during the rainy season. A linear sediment barrier around the perimeter of the stockpile shall also be used. During the non-rainy season soil stockpiles shall be covered and protected with a linear sediment barrier when precipitation is predicted. The Contractor shall control wind erosion during dry weather as provided in Section 10, "Dust Control," of the Standard Specifications.

Stockpiles of portland cement concrete rubble, asphalt concrete, asphalt concrete rubble, aggregate base, or aggregate subbase shall be covered with plastic or geotextile, or protected with a linear sediment barrier at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

Stockpiles of cold mix asphalt concrete shall be placed on and covered with impermeable material at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

Stockpiles of pressure treated wood shall be covered with impermeable material and placed on pallets at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

The Contractor shall repair or replace linear sediment barriers and covers as needed or as directed by the Engineer to keep them functioning properly. Sediment shall be removed when it accumulates to 1/3 of the linear sediment barrier height.

WASTE MANAGEMENT

Solid Waste

The Contractor shall not allow litter or debris to accumulate anywhere on the construction site, including storm drain grates, trash racks, and ditch lines. The Contractor shall pick up and remove trash and debris from the construction site at least once a week. The WPCM shall monitor solid waste storage and disposal procedures on the construction site. The Contractor shall provide enough dumpsters of sufficient size to contain the solid waste generated by the project. Dumpsters shall be emptied when refuse reaches the fill line. Dumpsters shall be watertight. The Contractor shall not wash out dumpsters on the construction site. The Contractor shall provide additional containers and more frequent pickup during the demolition phase of construction

Solid waste includes:

- A. Brick,
- B. Mortar,
- C. Timber,
- D. Metal scraps,
- E. Sawdust,
- F. Pipe,
- G. Electrical cuttings,
- H. Non-hazardous equipment parts,
- I. Styrofoam and other packaging materials,
- J. Vegetative material and plant containers from highway planting, and
- K. Litter and smoking material, including litter generated randomly by the public.

Trash receptacles shall be provided and used in the Contractor's yard, field trailers, and locations where workers gather for lunch and breaks.

Hazardous Waste

The Contractor shall implement hazardous waste management practices when waste is generated on the construction site from the following substances:

- A. Petroleum products,
- B. Asphalt products,
- C. Concrete curing compound,
- D. Pesticides,
- E. Acids,
- F. Paints,
- G. Stains,
- H. Solvents,
- I. Wood preservatives,
- J. Roofing tar, and
- K. Materials classified as hazardous by California Code of Regulations, Title 22, Division 4.5; or listed in CFR Title 40, Parts 110, 117, 261, or 302.

Nothing in these special provisions shall relieve the Contractor of the responsibility for compliance with Federal, State, and local laws regarding storage, handling, transportation, and disposal of hazardous wastes.

The WPCM shall oversee and enforce hazardous waste management practices. Production of hazardous materials and hazardous waste on the construction site shall be kept to a minimum. Perimeter controls, containment structures, covers, and liners shall be repaired or replaced when damaged.

The Contractor shall have a laboratory certified by the Department of Health Services (DHS) sample and test waste when hazardous material levels are unknown to determine safe methods for storage and disposal.

The Contractor shall segregate potentially hazardous waste from nonhazardous waste at the construction site. Hazardous waste shall be handled, stored, and disposed of as required in California Code of Regulations, Title 22, Division 4.5, Section 66262.34; and in CFR Title 49, Parts 261, 262, and 263.

The Contractor shall store hazardous waste in sealed containers constructed and labeled with the contents and date accumulated as required in California Code of Regulations, Title 22, Division 4.5; and in CFR Title 49, Parts 172, 173, 178, and 179. Hazardous waste containers shall be kept in temporary containment facilities conforming to the provisions in "Material Storage" of these special provisions.

There shall be adequate storage volume and containers shall be conveniently located for hazardous waste collection. Containers of hazardous waste shall not be overfilled and hazardous wastes shall not be mixed. Containers of dry waste that are not watertight shall be stored on pallets. The Contractor shall not allow potentially hazardous waste to accumulate on the ground. Hazardous waste shall be stored away from storm drains, watercourses, moving vehicles, and equipment.

The Contractor shall clean water based or oil based paint from brushes or equipment within a contained area and shall not contaminate soil, watercourses, or storm drain systems. Paints, thinners, solvents, residues, and sludges that cannot be recycled or reused shall be disposed of as hazardous waste. When thoroughly dry, latex paint and paint cans, used brushes, rags, absorbent materials, and drop cloths shall be disposed of as solid waste.

The Contractor shall dispose of hazardous waste within 90 days of being generated. Hazardous waste shall be disposed of by a licensed hazardous waste transporter using uniform hazardous waste manifest forms and taken to a Class I Disposal Site. A copy of the manifest shall be provided to the Engineer.

Contaminated Soil

The Contractor shall identify contaminated soil from spills or leaks by noticing discoloration, odors, or differences in soil properties. Soil with evidence of contamination shall be sampled and tested by a laboratory certified by DHS. If levels of contamination are found to be hazardous, the soil shall be handled and disposed of as hazardous waste.

The Contractor shall prevent the flow of water, including ground water, from mixing with contaminated soil by using one or a combination of the following measures:

- A. Berms,
- B. Cofferdams,
- C. Grout curtains,
- D. Freeze walls, or
- E. Concrete seal course.

If water mixes with contaminated soil and becomes contaminated, the water shall be sampled and tested by a laboratory certified by the DHS. If levels of contamination are found to be hazardous, the water shall be handled and disposed of as hazardous waste.

Concrete Waste

The Contractor shall implement practices to prevent the discharge of portland cement concrete or asphalt concrete waste into storm drain systems or watercourses.

Portland cement concrete or asphalt concrete waste shall be collected at the following locations and disposed of:

- A. Where concrete material, including grout, is used;
- B. Where concrete dust and debris result from demolition;
- C. Where sawcutting, coring, grinding, grooving, or hydro-concrete demolition of portland cement concrete or asphalt concrete creates a residue or slurry; or
- D. Where concrete trucks or other concrete-coated equipment is cleaned at the construction site.

Sanitary and Septic Waste

Wastewater from sanitary or septic systems shall not be discharged or buried within the Department right of way. The WPCM shall inspect sanitary or septic waste storage and monitor disposal procedures at least weekly. Sanitary facilities that discharge to the sanitary sewer system shall be properly connected and free from leaks.

The Contractor shall obtain written approval from the local health agency, city, county, and sewer district before discharging from a sanitary or septic system directly into a sanitary sewer system, and provide a copy to the Engineer. The Contractor shall comply with local health agency requirements when using an on-site disposal system.

Liquid Waste

The Contractor shall not allow construction site liquid waste, including the following, to enter storm drain systems or watercourses:

- A. Drilling slurries or fluids,
- B. Grease-free or oil-free wastewater or rinse water,
- C. Dredgings,
- D. Liquid waste running off a surface including wash or rinse water, or
- E. Other non-storm water liquids not covered by separate permits.

The Contractor shall hold liquid waste in structurally sound, leak proof containers such as:

- A. Sediment traps,
- B. Roll-off bins, or
- C. Portable tanks.

Liquid waste containers shall be of sufficient quantity and volume to prevent spills and leaks. The containers shall be stored at least 15 m from storm drains, watercourses, moving vehicles, and equipment.

The Contractor shall remove and dispose of deposited solids from sediment traps as provided in "Solid Waste" of these special provisions, unless determined infeasible by the Engineer.

Liquid waste may require testing to determine hazardous material content before disposal.

Drilling fluids and residue shall be disposed of outside the highway right of way. If the Engineer determines that an appropriate location is available, fluids and residue exempt under California Code of Regulations, Title 23, Section 2511(g) may be dried by infiltration and evaporation in a leak proof container. The remaining solid waste may be disposed of as provided in "Solid Waste" of these special provisions.

NON-STORM WATER MANAGEMENT

Water Control and Conservation

The Contractor shall prevent erosion or the discharge of pollutants into storm drain systems or watercourses by managing the water used for construction operations. The Contractor shall obtain the Engineer's approval before washing anything on the construction site with water that could discharge into a storm drain system or watercourse. Discharges shall be reported to the Engineer immediately.

The Contractor shall implement water conservation practices when water is used on the construction site. Irrigation areas shall be inspected and watering schedules shall be adjusted to prevent erosion, excess watering, or runoff. The Contractor shall shut off the water source to broken lines, sprinklers, or valves, and they shall be repaired as soon as possible. When possible, water from waterline flushing shall be reused for landscape irrigation. Paved areas shall be swept and vacuumed, not washed with water.

Construction water runoff, including water from water line repair, shall be directed to areas to infiltrate into the ground and shall not be allowed to enter storm drain systems or watercourses. Spilled water shall not be allowed to escape water truck filling areas. When possible, the Contractor shall direct water from off-site sources around the construction site, or shall minimize contact with the construction site.

Illegal Connection and Discharge Detection and Reporting

The Contractor shall inspect the construction site and the site perimeter before beginning work for evidence of illegal connections, discharges, or dumping. Subsequently, the construction site and perimeter shall be inspected on a frequent, predetermined schedule.

The Contractor shall immediately notify the Engineer when illegal connections, discharges, or dumping are discovered. The Contractor shall take no further action unless directed by the Engineer. Unlabeled or unidentifiable material shall be assumed to be hazardous.

The Contractor shall look for the following evidence of illegal connections, discharges, or dumping:

- A. Debris or trash piles,
- B. Staining or discoloration on pavement or soils,
- C. Pungent odors coming from drainage systems,

- D. Discoloration or oily sheen on water,
- E. Stains or residue in ditches, channels or drain boxes,
- F. Abnormal water flow during dry weather,
- G. Excessive sediment deposits,
- H. Nonstandard drainage junction structures, or
- I. Broken concrete or other disturbances near junction structures.

Vehicle and Equipment Cleaning

The Contractor shall limit vehicle and equipment cleaning or washing on the construction site to that necessary to control vehicle tracking or hazardous waste. Vehicles and equipment shall not be cleaned on the construction site with soap, solvents, or steam until the Engineer has been notified. The resulting waste shall be contained and recycled, or disposed of as provided in "Liquid Waste" or "Hazardous Waste" of these special provisions, whichever is applicable. The Contractor shall not use diesel to clean vehicles or equipment, and shall minimize the use of solvents.

The Contractor shall clean or wash vehicles and equipment in a structure equipped with disposal facilities. If using a structure is not possible, vehicles and equipment shall be cleaned or washed in an outside area with the following characteristics:

- A. Located at least 15 m from storm drainage systems or watercourses,
- B. Paved with asphalt concrete or portland cement concrete,
- C. Surrounded by a containment berm, and
- D. Equipped with a sump to collect and dispose of wash water.

When washing vehicles or equipment with water, the Contractor shall use as little water as possible. Hoses shall be equipped with a positive shutoff valve.

Wash racks shall discharge to a recycle system or to another system approved by the Engineer. Sumps shall be inspected regularly, and liquids and sediments shall be removed as needed.

Vehicle and Equipment Fueling and Maintenance

The Contractor shall fuel or perform maintenance on vehicles and equipment off the construction site whenever practical. When fueling or maintenance must be done at the construction site, the Contractor shall designate a site, or sites, and obtain approval from the Engineer before using. The fueling or maintenance site shall be protected from storm water, shall be on level ground, and shall be located at least 15 m from drainage inlets or watercourses. The WPCM shall inspect the fueling or maintenance site regularly. Mobile fueling or maintenance shall be kept to a minimum.

The Contractor shall use containment berms or dikes around the fueling and maintenance area. Adequate amounts of absorbent spill cleanup material and spill kits shall be kept in the fueling and maintenance area and on fueling trucks. Spill cleanup material and kits shall be disposed of immediately after use. Drip pans or absorbent pads shall be used during fueling or maintenance unless performed over an impermeable surface.

Fueling or maintenance operations shall not be left unattended. Fueling nozzles shall be equipped with an automatic shutoff control. Vapor recovery fueling nozzles shall be used where required by the Air Quality Management District. Nozzles shall be secured upright when not in use. Fuel tanks shall not be topped-off.

The Contractor shall recycle or properly dispose of used batteries and tires.

Material and Equipment Used Over Water

Drip pans and absorbent pads shall be placed under vehicles or equipment used over water, and an adequate supply of spill cleanup material shall be kept with the vehicle or equipment. Drip pans or plastic sheeting shall be placed under vehicles or equipment on docks, barges, or other surfaces over water when the vehicle or equipment will be idle for more than one hour.

The Contractor shall provide watertight curbs or toe boards on barges, platforms, docks, or other surfaces over water to contain material, debris, and tools. Material shall be secured to prevent spills or discharge into water due to wind.

Structure Removal Over or Adjacent to Water

The Contractor shall not allow demolished material to enter storm water systems or watercourses. The Contractor shall use covers and platforms approved by the Engineer to collect debris. Attachments shall be used on equipment to catch debris on small demolition operations. Debris catching devices shall be emptied regularly and debris shall be handled as provided in "Waste Management" of these special provisions.

The WPCM shall inspect demolition sites within 15 m of storm water systems or watercourses every day.

Paving, Sealing, Sawcutting, and Grinding Operations

The Contractor shall prevent the following material from entering storm drain systems or water courses:

- A. Cementitious material,
- B. Asphaltic material,
- C. Aggregate or screenings,
- D. Grinding or sawcutting residue,
- E. Pavement chunks, or
- F. Shoulder backing.

The Contractor shall cover drainage inlets and use linear sediment barriers to protect downhill watercourses until paving, sealing, sawcutting, or grinding operations are completed and excess material has been removed. Drainage inlets and manholes shall be covered during the application of seal coat, tack coat, slurry seal, or fog seal.

During the rainy season or when precipitation is predicted, paving, sawcutting, and grinding operations shall be limited to places where runoff can be captured. Seal coat, tack coat, slurry seal, or fog seal operations shall not begin if precipitation is predicted for the application or the curing period. The Contractor shall not excavate material from existing roadways during precipitation.

The Contractor shall vacuum up slurry from sawcutting operations immediately after the slurry is produced. Slurry shall not be allowed to run onto lanes open to public traffic or off the pavement.

The Contractor shall collect residue from portland cement concrete grinding operations with a vacuum attachment on the grinding machine. The residue shall not be left on the pavement or allowed to flow across the pavement.

Material excavated from existing roadways may be stockpiled as provided in "Stockpile Management" of these special provisions if approved by the Engineer. Asphalt concrete chunks used in embankment shall be placed above the water table and covered by at least 0.3-m of material.

Substances used to coat asphalt trucks and equipment shall not contain soap, foaming agents, or toxic chemicals.

Thermoplastic Striping and Pavement Markers

Thermoplastic striping and preheating equipment shutoff valves shall work properly at all times when on the construction site. The Contractor shall not preheat, transfer, or load thermoplastic within 15 m of drainage inlets or watercourses. The Contractor shall not fill the preheating container to more than 150 mm from the top. Truck beds shall be cleaned daily of scraps or melted thermoplastic.

The Contractor shall not unload, transfer, or load bituminous material for pavement markers within 15 m of drainage inlets or watercourses. All pressure shall be released from melting tanks before removing the lid to fill or service. Melting tanks shall not be filled to more than 150 mm from the top.

The Contractor shall collect bituminous material from the roadway after marker removal.

Pile Driving

The Contractor shall keep spill kits and cleanup material at pile driving locations. Pile driving equipment shall be parked over drip pans, absorbent pads, or plastic sheeting where possible. When not in use, pile driving equipment shall be stored at least 15 m from concentrated flows of storm water, drainage courses, or inlets. The Contractor shall protect pile driving equipment by parking it on plywood and covering it with plastic when precipitation is predicted. The WPCM shall inspect the pile driving area every day for leaks and spills.

The Contractor shall use vegetable oil instead of hydraulic fluid when practical.

Concrete Curing

The Contractor shall not overspray chemical curing compound. Drift shall be minimized by spraying as close to the concrete as possible. Drainage inlets shall be covered before applying curing compound.

The Contractor shall minimize the use and discharge of water by using wet blankets or similar methods to maintain moisture when curing concrete.

Concrete Finishing

The Contractor shall collect and dispose of water and solid waste from high-pressure water blasting. Drainage inlets within 15 m shall be covered before sandblasting. The nozzle shall be kept as close to the surface of the concrete as possible to minimize drift of dust and blast material. Blast residue may contain hazardous material.

Containment structures for concrete finishing operations shall be inspected for damage before each day of use and before predicted precipitation. Liquid and solid waste shall be removed from the containment structure after each work shift.

DEWATERING

Dewatering shall consist of discharging accumulated storm water, ground water, or surface water from excavations or temporary containment facilities. The Contractor shall discharge water within the limits of the project.

Dewatering discharge shall not cause erosion, scour, or sedimentary deposits that impact natural bedding materials.

The Contractor shall conduct dewatering activities in accordance with the Field Guide for Construction Dewatering available at:

<http://www.dot.ca.gov/hq/construc/stormwater/manuals.htm>

Before dewatering the Contractor shall submit a Dewatering and Discharge Plan to the Engineer in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and "Water Pollution Control," of these special provisions. At a minimum, the Dewatering and Discharge Plan shall include the following:

- A. A title sheet and table of contents;
- B. A description of the dewatering and discharge operations detailing the locations, quantity of water, equipment, and discharge point;
- C. The estimated schedule for dewatering and discharge (begin and end dates, intermittent or continuous);
- D. Discharge alternatives such as dust control or percolation; and
- E. Visual monitoring procedures with inspection log.

The Contractor shall not discharge storm water or non-storm water that has an odor, discoloration other than sediment, an oily sheen, or foam on the surface and shall notify the Engineer immediately upon discovery.

If water cannot be discharged within the project limits due to site constraints it shall be disposed of in the same manner specified for material in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

PAYMENT

The contract lump sum price paid for construction site management shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in spill prevention and control, material management, waste management, non-storm water management, and dewatering and identifying, sampling, testing, handling, and disposing of hazardous waste, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.04 TEMPORARY CONCRETE WASHOUT FACILITY

Temporary concrete washout facilities shall be constructed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary concrete washout facilities shall be one of the water pollution control practices for waste management and materials pollution control. The SWPPP shall include the use of temporary concrete washout facilities.

MATERIALS

Plastic Liner

Plastic liners shall be single ply, new polyethylene sheeting, a minimum of 0.25-mm thick and shall be free of holes, punctures, tears or other defects that compromise the impermeability of the material. Plastic liners shall not have seams or overlapping joints.

Gravel-filled Bags

Gravel bag fabric shall be nonwoven polypropylene geotextile (or comparable polymer) and shall conform to the following requirements:

Specification	Requirements
Mass per unit area, grams per square meter, min. ASTM Designation: D 5261	270
Grab tensile strength (25-mm grip), kilonewtons, min. ASTM Designation: D4632*	0.89
Ultraviolet stability, percent tensile strength retained after 500 hours, ASTM Designation: D4355, xenon arc lamp method	70

* or appropriate test method for specific polymer

Gravel bags shall be between 600 mm and 800 mm in length, and between 400 mm and 500 mm in width.

Yarn used for binding gravel bags shall be as recommended by the manufacturer or bag supplier and shall be of a contrasting color.

Gravel shall be between 10 mm and 20 mm in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials.

The opening of gravel-filled bags shall be secured to prevent gravel from escaping. Gravel-filled bags shall be between 13 kg and 22 kg in mass.

Straw Bales

Straw for straw bales shall conform to the provisions in Section 20-2.06, "Straw," of the Standard Specifications.

Straw bales shall be a minimum of 360 mm in width, 450 mm in height, 900 mm in length and shall have a minimum mass of 23 kg. The straw bale shall be composed entirely of vegetative matter, except for binding material.

Straw bales shall be bound by either wire, nylon or polypropylene string. Jute or cotton binding shall not be used. Baling wire shall be a minimum 1.57 mm in diameter. Nylon or polypropylene string shall be approximately 2 mm in diameter with 360 N of breaking strength.

Stakes

Stakes shall be wood or metal. Wood stakes shall be untreated fir, redwood, cedar, or pine and cut from sound timber. They shall be straight and free of loose or unsound knots or other defects which would render them unfit for the purpose intended. Wood stakes shall be a minimum 50 mm x 50 mm in size. Metal stakes may be used as an alternative, and shall be a minimum 13 mm in diameter. Stakes shall be a minimum 1.2 m in length. The tops of the metal stakes shall be bent at a 90-degree angle or capped with an orange or red plastic safety cap that fits snugly to the metal stake. The Contractor shall submit a sample of the metal stake and plastic cap, if used, for the Engineer's approval before installation.

Staples

Staples shall be as shown on the plans. An alternative attachment device such as geotextile pins or plastic pegs may be used instead of staples. The Contractor shall submit a sample of the alternative attachment device for the Engineer's approval before installation.

Signs

Wood posts for signs shall conform to the provisions in Section 56-2.02B, "Wood Posts," of the Standard Specifications. Lag screws shall conform to the provisions in Section 56-2.02D, "Sign Panel Fastening Hardware," of the Standard Specifications.

Plywood shall be freshly painted for each installation with not less than 2 applications of flat white paint. Sign letters shown on the plans shall be stenciled with commercial quality exterior black paint. Testing of paint will not be required.

INSTALLATION

Temporary concrete washout facilities shall be as follows:

1. Temporary concrete washout facilities shall be installed before beginning placement of concrete and located a minimum of 15 m from storm drain inlets, open drainage facilities, and water courses unless determined infeasible by the Engineer. Temporary concrete washout facilities shall be located away from construction traffic or access areas at a location determined by the Contractor and approved by the Engineer.
2. A sign shall be installed adjacent to each washout facility at a location determined by the Contractor and approved by the Engineer. Signs shall be installed in conformance with the provisions in Section 56-2.03, "Construction," and Section 56-2.04, "Sign Panel Installation," of the Standard Specifications.
3. The length and width of a temporary concrete washout facility may be increased from the minimum dimensions shown on the plans upon approval of the Engineer.

4. Temporary concrete washout facilities shall be constructed in sufficient quantity and size to contain liquid and concrete waste generated by washout operations for concrete wastes. These facilities shall be constructed to contain liquid and concrete waste without seepage, spills, or overflow.
5. Berms for below grade temporary concrete washout facilities shall be constructed from compacted native material. Gravel may be used in conjunction with compacted native material.
6. A plastic liner shall be installed in below grade temporary concrete washout facilities.

Details for an alternative temporary concrete washout facility shall be submitted to the Engineer for approval at least 7 days before installation.

When temporary concrete washout facilities are no longer required for the work, as determined by the Engineer, the hardened concrete and liquid residue shall be removed and disposed of in conformance with the provisions in Section 15-3.02, "Removal Methods," of the Standard Specifications. Temporary concrete washout facilities shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary concrete washout facilities shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

Temporary concrete washout facilities shall be maintained to provide adequate holding capacity with a minimum freeboard of 300 mm. Maintaining temporary concrete washout facilities shall include removing and disposing of hardened concrete and returning the facilities to a functional condition. Hardened concrete materials shall be removed and disposed of in conformance with the provisions in Section 15-3.02, "Removal Methods," of the Standard Specifications. Holes, rips, and voids in the plastic liner shall be patched and repaired by taping or the plastic liner shall be replaced. The plastic liner shall be replaced when patches or repairs compromise the impermeability of the material as determined by the Engineer.

Gravel bags shall be replaced when the bag material is ruptured or when the yarn has failed, allowing the bag contents to spill out.

Temporary concrete washout facilities shall be repaired or replaced on the same day the damage occurs. Damage to temporary concrete washout facilities resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

MEASUREMENT AND PAYMENT

Quantities of temporary concrete washout facilities will be measured as units determined from actual count in place.

The contract unit price paid for temporary concrete washout facility shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in constructing a temporary concrete washout facility, complete in place, including excavation and backfill, maintenance, and removal, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.05 TEMPORARY CHECK DAM

Temporary check dams shall be constructed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary check dams shall be one of the water pollution control practices for sediment control. The SWPPP shall include the use of temporary check dams.

Temporary check dams shall be Type 2 (gravel bag).

MATERIALS

Gravel-filled Bag

Gravel bag fabric shall be nonwoven polypropylene geotextile (or comparable polymer) and shall conform to the following requirements:

Specification	Requirements
Mass per unit area, grams per square meter, min. ASTM Designation: D 5261	270
Grab tensile strength (25-mm grip), kilonewtons, min. ASTM Designation: D4632*	0.89
Ultraviolet stability, percent tensile strength retained after 500 hours, ASTM Designation: D4355, xenon arc lamp method	70

* or appropriate test method for specific polymer

Gravel bags shall be between 600 mm and 800 mm in length, and between 400 mm and 500 mm in width.

Yarn used in construction of the gravel bags shall be as recommended by the manufacturer or bag supplier and shall be of a contrasting color.

Gravel shall be between 10 mm and 20 mm in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials. The opening of gravel-filled bags shall be secured to prevent gravel from escaping. Gravel-filled bags shall be between 13 kg and 22 kg in mass.

INSTALLATION

Temporary check dams shall be installed as follows:

1. Temporary check dam (Type 2): A single layer of gravel bags shall be placed in lined or unlined ditches with ends abutted tightly and not overlapped.
2. The bedding area for the temporary check dam shall be cleared of obstructions including, rocks, clods, and debris greater than 25 mm in diameter before installation.
3. The temporary check dam shall be installed across and approximately perpendicular to the centerline of a ditch or drainage line.
4. The temporary check dam shall be installed with sufficient spillway depth to prevent flanking of concentrated flow around the ends of the check dam.
5. The temporary check dam shall be installed in an unlined ditch or swale before the application of other temporary erosion control or soil stabilization material in the same unlined ditch or swale.

Details for an alternative temporary check dam shall be submitted to the Engineer for approval at least 7 days before installation.

When the temporary check dam is no longer required, as determined by the Engineer, it shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbances including holes and depressions caused by the installation and removal of the temporary check dam shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

Temporary check dams shall be maintained to provide sediment holding capacity and to reduce runoff velocities. Split, torn, or unraveling rolls shall be repaired or replaced. Broken or split stakes shall be replaced. Gravel bags shall be replaced when the bag material is ruptured or when the yarn has failed, allowing the bag contents to spill out. Locations where rills and other evidence of concentrated runoff have occurred beneath the check dams shall be corrected.

When sediment exceeds 1/3 of the height of the check dam above ground, or when directed by the Engineer, sediment shall be removed. The removed sediment shall be deposited within the project limits so that the sediment is not subject to erosion by wind or by water.

Temporary check dams shall be repaired or replaced the same day damage occurs. Washouts or scour beneath the temporary check dam shall be repaired. Temporary check dams damaged during the progress of work or resulting from the Contractor's vehicles, equipment, or operations shall be repaired or replaced at the Contractor's expense.

MEASUREMENT AND PAYMENT

Quantities of temporary check dams to be paid for will be determined by the meter measured along the centerline of the installed check dam.

The contract price paid per meter for temporary check dam shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary check dams, complete in place, including maintenance, and removal, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.06 TEMPORARY FIBER ROLL

Temporary fiber roll shall be furnished, installed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary fiber roll shall be installed on excavation and embankment slopes and other disturbed soil areas, active or nonactive.

Temporary fiber roll shall be one of the water pollution control practices for sediment control. The SWPPP shall include the use of temporary fiber roll.

Temporary fiber roll shall be either Type 1 or Type 2.

MATERIALS

Fiber Roll

Fiber roll shall be either:

1. Constructed with a premanufactured blanket consisting of either wood excelsior, rice or wheat straw, or coconut fibers or a combination of these materials. The blanket shall be between 2.0 m and 2.4 m in width and between 20 m and 29 m in length. Wood excelsior shall be individual fibers, of which 80 percent shall be 150 mm or longer in length. The blanket shall have a biodegradable jute, sisal, or coir fiber netting on at least one side. The blanket shall be rolled along the width and secured with jute twine spaced 2 m apart along the full length of the roll and placed 150 mm from the ends of each roll. The finished roll shall be between 200 mm and 250 mm in diameter, a minimum of 6 m in length, and shall weigh a minimum 0.81-kg/m. More than one blanket may be required to achieve the finished roll diameter. When more than one blanket is required, blankets shall be jointed longitudinally with an overlap of 150 mm along the length of the blanket.
2. A premanufactured roll of rice or wheat straw, wood excelsior, or coconut fiber encapsulated within a biodegradable jute, sisal, or coir fiber netting. The netting shall have a minimum durability of one year after installation. The netting shall be secured tightly at each end of the roll. Rolls shall be between 200 mm and 300 mm in diameter. Rolls between 200 mm and 250 mm in diameter shall have a minimum weight of 1.6 kg/m and a minimum length of 6 m. Rolls between 250 mm and 300 mm in diameter shall have a minimum weight of 4.5 kg/m and a minimum length of 3 m.

Stakes

Wood stakes shall be a minimum of 19 mm x 19 mm x 450 mm in size for Type 1 installation, or a minimum of 19 mm x 38 mm x 450 mm in size for Type 2 installation. Wood stakes shall be untreated fir, redwood, cedar, or pine and cut from sound timber. They shall be straight and free of loose or unsound knots and other defects which would render them unfit for the purpose intended. Metal stakes shall not be used.

Rope

Rope shall be biodegradable, such as sisal or manila, with a minimum diameter of 6.35 mm.

INSTALLATION

Temporary fiber roll shall be installed as follows:

1. Temporary fiber roll (Type 1): Furrows shall be constructed to a depth between 50 mm and 100 mm, and to a sufficient width to hold the fiber roll. Stakes shall be installed 600 mm apart along the length of the fiber rolls and stopped at 300 mm from each end of the rolls. Stakes shall be driven to a maximum of 50 mm above, or flush with the top of the roll.
2. Temporary fiber roll (Type 2): Rope and notched stakes shall be used to restrain the fiber rolls against the slope. Stakes shall be driven into the slope until the notch is even with the top of the fiber roll. Rope shall be knotted at each stake and laced between stakes. After installation of the rope, stakes shall be driven into the slope such that the rope will hold the fiber roll tightly to the slope. Furrows will not be required.

3. Temporary fiber rolls shall be placed 3 m apart along the slope for slope inclination (vertical:horizontal) of 1:2 and steeper, 4.5 m apart along the slope for slope inclination between 1:2 and 1:4, 6 m apart along the slope for slope inclination between 1:4 and 1:10, and a maximum of 15 m apart along the slope for slope inclination of 1:10 and flatter.
4. The bedding area for the fiber roll shall be cleared of obstructions including rocks, clods, and debris greater than 25 mm in diameter before installation.
5. Temporary fiber rolls shall be installed approximately parallel to the slope contour.
6. Temporary fiber rolls shall be installed before the application of other temporary erosion control or soil stabilization materials in the same area.

When no longer required, as determined by the Engineer, temporary fiber rolls shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. Temporary fiber rolls may be abandoned in place when approved in writing by the Engineer.

Ground disturbances including holes and depressions caused by the installation and removal of the temporary fiber roll shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

Temporary fiber rolls shall be maintained to disperse concentrated water runoff and to reduce runoff velocities. Split, torn, or unraveling rolls shall be repaired or replaced. Broken or split stakes shall be replaced. Sagging or slumping fiber rolls shall be repaired with additional stakes or replaced. Locations where rills and other evidence of concentrated runoff have occurred beneath the rolls shall be corrected. Temporary fiber rolls shall be repaired or replaced within 24 hours of identifying the deficiency.

MEASUREMENT AND PAYMENT

Quantities of temporary fiber rolls to be paid for will be determined by the meter measured along the centerline of the installed roll. Where temporary fiber rolls are joined and overlapped, the overlap will be measured as a single installed roll.

The contract price paid per meter for temporary fiber roll shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary fiber rolls, complete in place, including furrow excavation and backfill, maintenance, and removal, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Damage to temporary fiber rolls resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

10-1.07 PROGRESS SCHEDULE (CRITICAL PATH METHOD)

The Contractor shall submit to the Engineer practicable critical path method (CPM) progress schedules in conformance with these special provisions. Whenever the term "schedule" is used in this section it shall mean CPM progress schedule.

The provisions in Section 8-1.04, "Progress Schedule," of the Standard Specifications shall not apply.

DEFINITIONS

The following definitions shall apply to this section:

- A. **ACTIVITY.**—A task, event or other project element on a schedule that contributes to completing the project. Activities have a description, start date, finish date, duration and one or more logic ties.
- B. **BASELINE SCHEDULE.**—The initial schedule representing the Contractor's work plan on the first working day of the project.
- C. **CONTRACT COMPLETION DATE.**—The current extended date for completion of the contract shown on the weekly statement of working days furnished by the Engineer in conformance with the provisions in Section 8-1.06, "Time of Completion," of the Standard Specifications.
- D. **CRITICAL PATH.**—The longest continuous chain of activities for the project that has the least amount of total float of all chains. In general, a delay on the critical path will extend the scheduled completion date.
- E. **CRITICAL PATH METHOD (CPM).**—A network based planning technique using activity durations and the relationships between activities to mathematically calculate a schedule for the entire project.
- F. **DATA DATE.**—The day after the date through which a schedule is current. Everything occurring earlier than the data date is "as-built" and everything on or after the data date is "planned."
- G. **FLOAT.**—The difference between the earliest and latest allowable start or finish times for an activity.

- H. MILESTONE.—An event activity that has zero duration and is typically used to represent the beginning or end of a certain stage of the project.
- I. NEAR CRITICAL PATH.—A chain of activities with total float exceeding that of the critical path but having no more than 10 working days of total float.
- J. SCHEDULED COMPLETION DATE.—The planned project finish date shown on the current accepted schedule.
- K. TOTAL FLOAT.—The amount of time that an activity or chain of activities can be delayed before extending the scheduled completion date.
- L. UPDATE SCHEDULE.—A current schedule developed from the baseline or subsequent schedule through regular monthly review to incorporate as-built progress and any planned changes.

GENERAL REQUIREMENTS

The Contractor shall submit to the Engineer baseline, monthly update and final update schedules, each consistent in all respects with the time and order of work requirements of the contract. The project work shall be executed in the sequence indicated on the current accepted schedule.

Schedules shall show the order in which the Contractor proposes to carry out the work with logical links between time-scaled work activities, and calculations made using the critical path method to determine the controlling operation or operations. The Contractor is responsible for assuring that all activity sequences are logical and that each schedule shows a coordinated plan for complete performance of the work.

The Contractor shall produce schedules using computer software and shall furnish compatible software for the Engineer's exclusive possession and use. The Contractor shall furnish network diagrams and schedule data as parts of each schedule submittal.

Schedules shall include, but not be limited to, applicable activities that show the following:

- A. Project characteristics, salient features, or interfaces, including those with outside entities, that could affect time of completion.
- B. Project start date, scheduled completion date and other milestones.
- C. Work performed by the Contractor, subcontractors and suppliers.
- D. Submittal development, delivery, review and approval, including those from the Contractor, subcontractors and suppliers.
- E. Procurement, delivery, installation and testing of materials, plants and equipment.
- F. Testing and settlement periods.
- G. Utility notification and relocation.
- H. Erection and removal of falsework and shoring.
- I. Major traffic stage switches.
- J. Finishing roadway and final cleanup.

Schedule activities shall include the following:

- A. A clear and legible description.
- B. Start and finish dates.
- C. A duration of not less than one working day, except for event activities, and not more than 20 working days, unless otherwise authorized by the Engineer.
- D. At least one predecessor and one successor activity, except for project start and finish milestones.
- E. Required constraints.

The Engineer's review and acceptance of schedules shall not waive any contract requirements and shall not relieve the Contractor of any obligation thereunder or responsibility for submitting complete and accurate information. Schedules that are rejected shall be corrected by the Contractor and resubmitted to the Engineer within 5 working days of notification by the Engineer, at which time a new review period of one week will begin.

Errors or omissions on schedules shall not relieve the Contractor from finishing all work within the time limit specified for completion of the contract. If, after a schedule has been accepted by the Engineer, either the Contractor or the Engineer discover that any aspect of the schedule has an error or omission, it shall be corrected by the Contractor on the next update schedule.

COMPUTER SOFTWARE

The Contractor shall submit to the Engineer for approval a description of proposed software before delivery. The software shall be the current version of Primavera SureTrak Project Manager for Windows, or equal, and shall be compatible with Windows NT (version 4.0) operating system. If software other than SureTrak is proposed, it shall be capable of generating files that can be imported into SureTrak.

The Contractor shall furnish schedule software and all original software instruction manuals to the Engineer with submittal of the baseline schedule. The schedule software will be returned to the Contractor within 4 weeks of submittal of the final update schedule. The State will compensate the Contractor in conformance with the provisions in Section 4-1.03D, "Extra Work," of the Standard Specifications for replacement of software which is damaged, lost or stolen after delivery to the Engineer.

NETWORK DIAGRAMS, REPORTS AND DATA

The Contractor shall include the following for each schedule submittal:

- A. Two sets of originally plotted, time-scaled network diagrams.
- B. One 1.44-megabyte 90 mm (3.5 inch) floppy diskette containing the schedule data.

The time-scaled network diagrams shall conform to the following:

- A. Show a continuous flow of information from left to right.
- B. Be based on early start and early finish dates of activities.
- C. Clearly show the primary paths of criticality using graphical presentation.
- D. Be prepared on B-size sheets, 280 mm x 430 mm (11 inch x 17 inch), or larger size.
- E. Include a title block and a timeline on each page.

BASELINE SCHEDULE

The Contractor shall submit to the Engineer a baseline schedule within 20 working days of approval of the contract. The Contractor shall allow 3 weeks for the Engineer's review after the baseline schedule and all support data are submitted. Beginning the week the baseline schedule is first submitted, the Contractor shall meet with the Engineer weekly to discuss and resolve schedule issues until the baseline schedule is accepted.

The baseline schedule shall include the entire scope of work and shall show how the Contractor plans to complete all work contemplated. The baseline schedule shall show the activities that define the critical path. Multiple critical paths and near-critical paths shall be kept to a minimum. A total of not more than 50 percent of the baseline schedule activities shall be critical or near critical, unless otherwise authorized by the Engineer.

The baseline schedule shall not extend beyond the number of working days originally provided in these special provisions. The baseline schedule shall have a data date of the first working day of the contract and not include any completed work to date. The baseline schedule shall not attribute negative float or negative lag to any activity.

UPDATE SCHEDULE

The Contractor shall submit an update schedule and meet with the Engineer to review contract progress, on or before the first day of each month, beginning one month after the baseline schedule is accepted. The Contractor shall allow 2 weeks for the Engineer's review after the update schedule and all support data are submitted, except that the review period shall not start until any previous month's required schedule is accepted. Update schedules that are not accepted or rejected within the review period will be considered accepted by the Engineer.

The update schedule shall have a data date of the twenty-first day of the month or other date established by the Engineer. The update schedule shall show the status of work actually completed to date and the work yet to be performed as planned. In addition, the update schedule shall show any proposed schedule modifications including adding or deleting activities or changing activity constraints, durations or logic. The Contractor shall state in writing the reasons for any changes to activities and the critical path that result in a delay to the scheduled completion date compared to the previous accepted schedule.

FINAL UPDATE SCHEDULE

The Contractor shall submit a final update, as-built schedule with actual start and finish dates for the activities, within 30 days after completion of contract work. The Contractor shall provide a written certificate with this submittal signed by the Contractor's project manager and an officer of the company stating, "To my knowledge and belief, the enclosed final update schedule reflects the actual start and finish dates of the actual activities for the project contained herein." An officer of the company may delegate in writing the authority to sign the certificate to a responsible manager.

RETENTION

The Department will retain an amount equal to 25 percent of the estimated value of the work performed during each estimate period in which the Contractor fails to submit an acceptable schedule conforming to the requirements of these special provisions as determined by the Engineer. Schedule retentions will be released for payment on the next monthly estimate for partial payment following the date that acceptable schedules are submitted to the Engineer or as otherwise specified herein. Upon completion of all contract work and submittal of the final update schedule and certification, any remaining retained funds associated with this section, "Progress Schedule (Critical Path Method)", will be released for payment. Retentions held in conformance with this section shall be in addition to other retentions provided for in the contract. No interest will be due the Contractor on retention amounts.

PAYMENT

Full compensation for the required schedules and software shall be considered as included in the contract prices paid for the various items of work involved, and no additional compensation will be allowed therefor.

10-1.08 OBSTRUCTIONS

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Trenches for under ground utilities shall not be left open for more that 48 hours.

Attention is directed to the existence of certain underground facilities that may require special precautions be taken by the Contractor to protect the health, safety and welfare of workers and of the public. Facilities requiring special precautions include, but are not limited to: conductors of petroleum products, oxygen, chlorine, and toxic or flammable gases; natural gas in pipelines greater than 150 mm in diameter or pipelines operating at pressures greater than 415 kPa (gage); underground electric supply system conductors or cables, with potential to ground of more than 300 V, either directly buried or in a duct or conduit which do not have concentric grounded or other effectively grounded metal shields or sheaths.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444
	1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133
	1-800-227-2600

10-1.09 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES

Flagging, signs, and temporary traffic control devices furnished, installed, maintained, and removed when no longer required shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Category 1 temporary traffic control devices are defined as small and lightweight (less than 45 kg) devices. These devices shall be certified as crashworthy by crash testing, crash testing of similar devices, or years of demonstrable safe performance. Category 1 temporary traffic control devices include traffic cones, plastic drums, portable delineators, and channelizers.

If requested by the Engineer, the Contractor shall provide written self-certification for crashworthiness of Category 1 temporary traffic control devices at least 5 days before beginning any work using the devices or within 2 days after the request if the devices are already in use. Self-certification shall be provided by the manufacturer or Contractor and shall include the following:

- A. Date,
- B. Federal Aid number (if applicable),
- C. Contract number, district, county, route and kilometer post of project limits,
- D. Company name of certifying vendor, street address, city, state and zip code,
- E. Printed name, signature and title of certifying person; and
- F. Category 1 temporary traffic control devices that will be used on the project.

The Contractor may obtain a standard form for self-certification from the Engineer.

Category 2 temporary traffic control devices are defined as small and lightweight (less than 45 kg) devices that are not expected to produce significant vehicular velocity change, but may cause potential harm to impacting vehicles. Category 2 temporary traffic control devices include barricades and portable sign supports.

Category 2 temporary traffic control devices shall be on the Federal Highway Administration's (FHWA) list of Acceptable Crashworthy Category 2 Hardware for Work Zones. This list is maintained by FHWA and can be located at:

http://safety.fhwa.dot.gov/roadway_dept/road_hardware/listing.cfm?code=workzone

The Department also maintains this list at:

<http://www.dot.ca.gov/hq/traffops/signtech/signdel/pdf/Category2.pdf>

Category 2 temporary traffic control devices that have not received FHWA acceptance shall not be used. Category 2 temporary traffic control devices in use that have received FHWA acceptance shall be labeled with the FHWA acceptance letter number and the name of the manufacturer. The label shall be readable and permanently affixed by the manufacturer. Category 2 temporary traffic control devices without a label shall not be used.

If requested by the Engineer, the Contractor shall provide a written list of Category 2 temporary traffic control devices to be used on the project at least 5 days before beginning any work using the devices or within 2 days after the request if the devices are already in use.

Category 3 temporary traffic control devices consist of temporary traffic-handling equipment and devices that weigh 45 kg or more and are expected to produce significant vehicular velocity change to impacting vehicles. Temporary traffic-handling equipment and devices include crash cushions, truck-mounted attenuators, temporary railing, temporary barrier, and end treatments for temporary railing and barrier.

Type III barricades may be used as sign supports if the barricades have been successfully crash tested, meeting the NCHRP Report 350 criteria, as one unit with a construction area sign attached.

Category 3 temporary traffic control devices shall be shown on the plans or on the Department's Highway Safety Features list. This list is maintained by the Division of Engineering Services and can be found at:

http://www.dot.ca.gov/hq/esc/approved_products_list/HighwaySafe.htm

Category 3 temporary traffic control devices that are not shown on the plans or not listed on the Department's Highway Safety Features list shall not be used.

Full compensation for providing self-certification for crashworthiness of Category 1 temporary traffic control devices and for providing a list of Category 2 temporary traffic control devices used on the project shall be considered as included in the prices paid for the various items of work requiring the use of the Category 1 or Category 2 temporary traffic control devices and no additional compensation will be allowed therefor.

10-1.10 EXISTING HIGHWAY FACILITIES

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

REMOVE METAL BEAM GUARD RAILING

Existing metal beam guard railing, where shown on the plans to be removed, shall be removed and disposed of.

Existing concrete anchors or steel foundation tubes shall be completely removed and disposed of. Full compensation for removing concrete anchors shall be considered as included in the contract price paid per meter for remove metal beam guard railing and no separate payment will be made therefor.

Full compensation for removing cable anchor assemblies, terminal anchor assemblies or steel foundation tubes shall be considered as included in the contract price paid per meter for remove metal beam guard railing and no separate payment will be made therefor.

REMOVE FENCE

Existing fence, where shown on the plans to be removed, shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Fences shall not be removed until their use is no longer required, as determined by the Engineer. The Contractor shall notify the Engineer in advance of any intended fence removal.

REMOVE PIPE GUARD POST

Existing pipe guard posts, where shown on the plans to be removed, shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Existing concrete anchors or steel foundation tubes shall be completely removed and disposed of. Full compensation for removing concrete anchors or steel foundation tubes shall be considered as included in the unit price paid for remove pipe guard posts and no separate payment will be made therefor.

REMOVE CONCRETE

Concrete, where shown on the plans to be removed, shall be removed.

The pay quantities of concrete to be removed will be measured by the cubic meter, measured before and during removal operations.

Concrete removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

10-1.11 CLEARING AND GRUBBING

Clearing and grubbing shall conform to the provisions in Section 16, "Clearing and Grubbing," of the Standard Specifications and these special provisions.

Improvements remaining either wholly or partially within the highway right of way, including, but not limited to, sheds, stables, buildings, foundations, and slabs above ground, shall be demolished and removed as part of the work included under clearing and grubbing.

The State reserves the right to salvage materials from the improvements prior to the date set for opening of bids.

The Contractor shall not dispose of the improvements or materials therefrom by sale, gift or in any manner whatsoever to the general public at the site, provided however, that this provision shall not be construed as limiting or prohibiting the sale or disposal of the improvements or materials at the site to duly licensed contractors or material vendors, and provided that the materials are removed from the improvement by the State's Contractor. Removal of buildings as a unit, or in sections capable of reassembly as a structure, is expressly prohibited.

Full compensation for demolition, removal, and disposal of the facilities specified herein shall be considered as included in the contract lump sum price paid for clearing and grubbing and no additional compensation will be allowed therefor.

10-1.12 DEMOLISH BUILDING

PART 1 - GENERAL

Scope: This work shall consist of demolition and removal of existing facilities, including salvaging of materials and equipment, in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Work Plan: The Contractor shall submit a complete building removal plan to the Engineer for the building demolition and removal. The plan shall provide for safe conduct of the work, including procedures and methods to provide necessary supports, lateral bracing and shoring when required, careful removal and transmittal of materials specified to be salvaged, protection of property which is to remain undisturbed, coordination with other work in progress, and timely disconnection of utility services. The plan shall include a detailed description of the methods and equipment to be used for each operation and the sequence of operations.

PROTECTION

Necessary precautions shall be taken to avoid damage to existing items to remain in place, to be reused, or to remain the property of the State. Damaged items shall be repaired or replaced at the Contractor's expense. The Contractor shall coordinate demolition with all other work.

Burning: The use of burning at the project site shall not be allowed.

Explosives: The use of explosives shall not be used.

PART 2 - PRODUCTS (Not applicable)

PART 3 - EXECUTION

PREPARATION

The Contractor shall notify the Engineer 5 days prior to the start of demolition work. The limits of removal shall be located and identified. Items to be removed and the interface of items to be removed and items to remain intact shall be identified and marked.

Prior to removing concrete or masonry, a saw cut approximately one inch deep shall be made along the limits of removal on all faces that will be visible in the completed work.

REMOVAL

Removal shall be to the limits shown on the plans. Removal shall be done carefully to minimize damage to the portions to remain.

Assemblies to be salvaged which require dismantling for removal shall be matchmarked before dismantling.

Structures: Existing structures indicated shall be removed to grade including underground foundations and slabs.

Utilities and Related Equipment: The existing utilities shall be removed as shown on the plans and terminated in a manner conforming to the nationally recognized code covering the specific utility and approved by the Engineer.

Air Conditioning Equipment: Air conditioning equipment shall be removed without releasing chlorofluorocarbon refrigerants to the atmosphere in accordance with the Clean Air Act Amendment of 1990.

Disposal of Ozone Depleting Substance (ODS): Class I and Class II ODS are defined in Section, 602(a) and (b), of The Clean Air Act. The contractor shall prevent discharge of Class I and Class II ODS to the atmosphere. Recovered ODS shall be placed in cylinders meeting ARI Guideline K suitable for the type ODS (filled to no more than 80 percent capacity) and appropriate labeling shall be provided. Recovered ODS shall be removed from State property and disposed of in accordance with State requirements. Equipment and appliances containing ODS in a sealed, self-contained system (e.g. residential refrigerators and window air conditioners) shall be disposed of in accordance with 40 CFR 82.

Piping and Conduits: Piping and conduits to be abandoned shall be capped or plugged.

Surfaces that are exposed to view at the limits of removal work shall be patched, bumps shall be removed and depressions filled, and the surface shall be finished to match the existing surrounding surfaces. Depressions in concrete less than one inch deep shall be deepened to one-inch minimum depth before filling with cement mortar.

Anchor bolts and reinforcement shall be removed at least one inch below the surrounding surfaces, and the resulting hole shall be patched with cement mortar.

DISPOSAL

Materials that are to be removed shall become the property of the Contractor and shall be disposed of outside the highway right of way in accordance with the requirements in Section 7-1.13, "Disposal of Material Outside of the Highway Right of Way," of the Standard Specifications.

SALVAGE

Materials or equipment shown on the plans to be salvaged shall remain the property of the State and shall be removed, cleaned and stockpiled at a location at the project site designated by the Engineer.

10-1.13 EARTHWORK

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

Surplus excavated material shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Reinforcement or metal attached to reinforced concrete rubble placed in embankments shall not protrude above the grading plane. Prior to placement within 0.6-m below the grading plane of embankments, reinforcement or metal shall be trimmed to no greater than 20 mm from the face of reinforced concrete rubble. Full compensation for trimming reinforcement or metal shall be considered as included in the contract prices paid per cubic meter for the types of excavation shown in the Engineer's estimate, or the contract prices paid for furnishing and placing imported borrow or embankment material, as the case may be, and no additional compensation will be allowed therefor.

10-1.14 AGGREGATE BASE

Aggregate base must comply with Section 26, "Aggregate Bases," of the Standard Specifications and these special provisions.

Aggregate base must be Class 2.

Do not store reclaimed asphalt concrete or aggregate base with reclaimed asphalt concrete within 30 m measured horizontally of any culvert, watercourse, or bridge.

10-1.15 FOG SEAL COAT

Fog seal coat shall conform to the provisions in Section 37-1, "Seal Coats," of the Standard Specifications and these special provisions.

Attention is directed to "Order of Work" in these special provisions regarding application of asphalt emulsion.

Asphaltic emulsion shall be CSS1h grade.

10-1.16 ASPHALT CONCRETE

GENERAL

Asphalt concrete shall be Type A and shall conform to the provisions in Section 39, "Asphalt Concrete," of the Standard Specifications and these special provisions.

The grade of asphalt binder to be mixed with aggregate for Type A asphalt concrete shall be Grade PG-64-28 PM conforming to the provisions in Section 92, "Asphalts," of the Standard Specifications.

In addition to aggregate quality requirements specified in Section 39-2.02, "Aggregate," in the Standard Specifications and these special provisions, aggregate from each source shall also conform to the following quality requirements:

Test	California Test	Requirement
Los Angeles Rattler	211	
Loss at 500 Rev. (Max)		25%
Durability Index	229	
Fine Aggregate (Df) (Min).		50

California Test 367 is modified by amending Section C, "Optimum Bitumen Content," as follows:

OPTIMUM BITUMEN CONTENT

1. Plot asphalt content versus void content for each specimen on Form TL-306 (Figure 3), and connect adjacent points with straight lines.
2. Modify Form TL-306 (Figure 3) to show stability on the vertical axis beginning with a stability value of 20 on the bottom horizontal line and ending with a value of 60 on the top horizontal line.
3. Plot stability versus asphalt content for each specimen on Form TL-306 (Figure 3) as modified in step 2 above and connect adjacent points with straight lines.
4. Select the theoretical asphalt content which is at the point passing through the minimum specification for stability from modified Figure 3.
5. Optimum asphalt content is determined as follows:

- a. If voids are less than 4.0% at the asphalt content selected in Step 4, then select the asphalt content at 4.0% voids from Figure 3. Selected optimum asphalt content should be as close to 4.0% voids as possible.
6. To establish a recommended range, use the Optimum Bitumen Content (OBC) as the high value and 0.3% less as the low value where the OBC is 7.9% or less. When the OBC is between 8.0% and 8.6%, use it as the high value of the range and use 7.6% as the low value. When the OBC is greater than 8.6%, use it as the high value and 1.0% less as the low value.

If the recommended bitumen ratio range, as determined by California Test 367, is increased or decreased by the Engineer beyond the recommended range by more than 0.1 percent by weight of the dry aggregate, the compensation payable to the Contractor for asphalt concrete will be increased or decreased on the basis of the total increase or decrease in tonnes of asphalt binder times the cost of asphalt binder per tonne, f.o.b. the asphalt binder plant (including sales tax) plus the freight cost per tonne, at the carrier's established rates, for the delivery of the asphalt binder from the asphalt binder plant to the asphalt concrete plant being used for the project. In determining the cost of the asphalt binder, any cash or trade discount offered or available will be credited to the State notwithstanding the fact that such discount may not have been taken by the purchaser. The highest value of the specified range will be considered to be the specified asphalt content for determining the total increase in asphalt binder and the lowest value of the specified range will be considered to be the specified asphalt content for determining the total decrease in asphalt binder.

The amount of asphalt binder used in asphalt concrete placed in dikes, gutters, gutter flares, overside drains and aprons at the ends of drainage structures shall be increased one percent by mass of the aggregate over the amount of asphalt binder determined for use in asphalt concrete placed on the traveled way.

The aggregate for Type A asphalt concrete shall conform to the 12.5 mm maximum, medium grading specified in Section 39-2.02, "Aggregate," of the Standard Specifications.

The aggregate for Type A asphalt concrete shall be lime treated in conformance with "Lime Treated Aggregates" of these special provisions.

When portland cement concrete is placed on asphalt concrete base, the finished surface of the asphalt concrete base shall not extend above the grade established by the Engineer. Asphalt concrete base with a surface higher than the grade established by the Engineer shall be cold planed until the surface of asphalt concrete base conforms to the tolerances specified. Cold planing equipment shall be power driven and specifically designed to produce a smooth surface that conforms to the straight edge requirements specified in Section 39-6.03, "Compacting" of the Standard Specifications. Asphalt concrete base with a surface lower than 15 mm below the grade established by the Engineer shall be removed and replaced with asphalt concrete base which complies with requirements of these specifications.

Aggregate for asphalt concrete dikes shall be in conformance with the provisions for 9.5-mm Maximum grading in Section 39-2.02, "Aggregate," of the Standard Specifications.

If the Contractor selects the batch mixing method, asphalt concrete shall be produced by the automatic batch mixing method in conformance with the provisions in Section 39-3.03A(2), "Automatic Proportioning," of the Standard Specifications.

If the finished surface of the asphalt concrete does not meet the specified surface tolerances, the surfacing shall be brought within tolerance by either (1) abrasive grinding (2) removal and replacement or (3) placing an overlay of asphalt concrete. The method will be selected by the Engineer. The corrective work shall be at the Contractor's expense.

If abrasive grinding is used to bring the finished surface to the specified surface tolerances, additional grinding shall be performed, as necessary, as directed by the Engineer. Ground areas shall be neat rectangular areas of uniform surface appearance. Abrasive grinding shall conform to the provisions in the first paragraph and the last 4 paragraphs in Section 42-2.02, "Construction," of the Standard Specifications.

RECLAIMED ASPHALT PAVEMENT

The Contractor may produce asphalt concrete Type A and Type B using reclaimed asphalt pavement (RAP). Asphalt concrete produced using RAP shall conform to the provisions for asphalt concrete in this section, "Asphalt Concrete," and these special provisions. The Contractor may substitute RAP for a portion of the virgin aggregate in asphalt concrete in an amount not exceeding 15 percent of the asphalt concrete dry aggregate mass.

RAP shall be processed from asphalt concrete removed from pavement surfaces. RAP shall be stored in stockpiles on smooth surfaces free of debris and organic material. RAP stockpiles shall consist only of homogeneous RAP. The Contractor may process and stockpile RAP throughout the project's life. Processing and stockpiling operations shall prevent material contamination and segregation.

The Contractor shall determine the amount of asphalt binder to be mixed with the combined virgin aggregate and RAP in conformance with the requirements in California Test 367 amended by Lab Procedure-9 (LP-9), "Asphalt Concrete Using Up To 15% Reclaimed Asphalt Pavement (RAP)." LP-9 is available at:

At least 20 days before starting production of asphalt concrete using RAP, the Contractor shall submit a proposed asphalt concrete mix design in writing to the Engineer. The mix design submittal shall consist of the following:

A. RAP:

1. Processed stockpile locations.
2. LP-9 test results.
3. Correlation factor for aggregate gradations from California Test 382 and LP-9.
4. Three 32-kg samples of processed RAP representing the material to be used. The three samples shall be split from the sample the Contractor uses to determine the mix design. The Contractor shall obtain and split the samples in conformance with the requirements in California Test 125 and LP-9.
5. The substitution rate for virgin aggregate and percent RAP.

B. Virgin aggregate and supplemental fine aggregate blend:

1. Percent passing values for each sieve size.
2. Aggregate quality tests results.
3. Each aggregate source to be used including producer, location, and California Mine Identification number.
4. Percentage of each aggregate stockpile, cold feed, and hot bin to be used.
5. Gradation of each aggregate stockpile, cold feed, and hot bin to be used.

C. Asphalt binder:

1. Source.
2. Material Safety Data Sheets.

D. Antistrip additives, if used:

1. Name of product.
2. Name of manufacturer.
3. Manufacturer's designation and proposed rate.
4. Location and method of addition.
5. Material Safety Data Sheets.

E. Asphalt concrete:

1. A completed mix design that reflects the percent of RAP to be used including the electronic worksheet identified in LP-9.
2. In graphical format, stability and air voids versus asphalt binder percentage of asphalt in conformance with the requirements in CTM 367.

Asphalt concrete production using RAP shall not begin until the Engineer approves the mix design. If the Engineer fails to review the mix design in 20 days, and if, in the opinion of the Engineer, work completion is delayed as a result of the failure to review, the Engineer will adjust payment and contract time in conformance with the requirements in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

If proposing a change in the RAP substitution rate, the Contractor shall notify the Engineer. If the substitution rate changes more than 5 percent by dry aggregate mass in the asphalt concrete mixture, the Contractor shall submit a new mix design.

The aggregate gradation for the asphalt concrete produced with RAP shall be calculated based on the mathematical combination of the virgin aggregate gradation during production and the daily RAP gradation. RAP shall be sampled and gradation shall be determined in conformance with the requirements in LP-9. RAP gradations shall be:

- A. Determined daily by the Contractor.
- B. Used for the mathematical combination of that day's asphalt concrete production.
- C. Reported to the Engineer.

The Contractor shall perform quality control testing of the RAP source each day asphalt concrete using RAP is produced.

The Contractor shall perform quality control testing of the aggregates and the asphalt concrete mixture at least once for every 1000 tonnes of asphalt concrete using RAP produced, but not less than 2 tests per day.

Daily, the Contractor shall submit to the Engineer:

- A. Results for RAP gradation and the asphalt binder content in RAP determined in conformance with the requirements in LP-9. The Contractor shall sample RAP from the weighhopper or pugmill.
- B. Mathematical calculation of the gradation of the virgin aggregate and RAP aggregate blend.
- C. Correlation factor for RAP burn-off determined in conformance with the requirements in LP-9.

RAP proportioning shall conform to the provisions for aggregate proportioning specified in Section 39-3.03, "Proportioning," of the Standard Specifications and these special provisions. The Contractor's mixing equipment shall have a device that safely provides a sample representative of the virgin aggregate and RAP incorporated into the asphalt concrete. The Contractor shall sample in conformance with the requirements in California Test 125 and LP-9.

The temperature of asphalt concrete using RAP shall not exceed 165°C.

If batch mixing is used, RAP shall be kept separate from the virgin aggregate until both ingredients enter the weighhopper or pugmill. After introduction to the pugmill and before asphalt binder is added, the mixing time for the virgin aggregate and RAP shall not be less than 5 seconds. After asphalt binder is added, the mixing time shall not be less than 30 seconds.

If continuous mixing is used, the RAP shall be protected from direct contact with the burner flame with a device such as a shield, separator, or second drum.

PAINT BINDER (TACK COAT)

Paint binder (tack coat) shall be applied to existing surfaces to be surfaced and between layers of asphalt concrete, except when eliminated by the Engineer.

Paint binder (tack coat) shall be, at the option of the Contractor, either rapid-setting asphaltic emulsion CRS-2, or PMCRS-2, or paving asphalt. Rapid-setting asphaltic emulsion shall conform to the provisions in Section 39-4.02, "Prime Coat and Paint Binder (Tack Coat)," and the provisions in Section 94, "Asphaltic Emulsions," of the Standard Specifications. When paving asphalt is used for paint binder, the grade will be determined by the Engineer. Paving asphalt shall conform to the provisions in Section 39-4.02, "Prime Coat and Paint Binder (Tack Coat)," and the provisions in Section 92, "Asphalts," of the Standard Specifications.

Paint binder (tack coat) shall be applied in the liter per square meter range limits specified for the surfaces to receive asphalt concrete in the tables below. The exact application rate within the range will be determined by the Engineer.

Application Rates for Asphaltic Emulsion Paint Binder (Tack Coat) on Asphalt Concrete (except Open Graded) and on Portland Cement Concrete Pavement (PCCP)	
Type of surface to receive paint binder (tack coat)	Rapid-Setting Asphaltic Emulsion L/m ² (Note B)
Dense, compact surfaces, between layers, and on PCCP	0.10 – 0.20
Open textured, or dry, aged surfaces	0.20 – 0.40

Note B: Undiluted rapid-setting asphaltic emulsion.

Application Rates for Paint Binder (Tack Coat) on Asphalt Concrete (except Open Graded) and on Portland Cement Concrete Pavement (PCCP)	
Type of surface to receive paint binder (tack coat)	Paving Asphalt L/m ²
Dense, compact surfaces, between layers, and on PCCP	0.05 – 0.10
Open textured, or dry, aged surfaces	0.10 – 0.25

When asphaltic emulsion is used as paint binder (tack coat), asphalt concrete shall not be placed until the applied asphaltic emulsion has completely changed color from brown to black.

The area to which paint binder has been applied shall be closed to public traffic. Care shall be taken to avoid tracking binder material onto existing pavement surfaces beyond the limits of construction.

AUTOMATIC SCREED CONTROL

In addition to the provisions in Section 39-5.01, "Spreading Equipment," of the Standard Specifications, asphalt paving equipment shall be equipped with automatic screed controls and a sensing device or devices.

When placing asphalt concrete to the lines and grades established by the Engineer, the automatic controls shall control the longitudinal grade and transverse slope of the screed. Grade and slope references shall be furnished, installed, and maintained by the Contractor. Should the Contractor elect to use a ski device, the minimum length of the ski device shall be 9 m. The ski device shall be a rigid one piece unit and the entire length shall be utilized in activating the sensor.

When placing the initial mat of asphalt concrete on existing pavement, the end of the screed nearest the centerline shall be controlled by a sensor activated by a ski device not less than 9 m long. The end of the screed farthest from centerline shall be controlled by a sensor activated by a similar ski device.

When paving contiguously with previously placed mats, the end of the screed adjacent to the previously placed mat shall be controlled by a sensor that responds to the grade of the previously placed mat and will reproduce the grade in the new mat within a 3-mm tolerance. The end of the screed farthest from the previously placed mat shall be controlled in the same way it was controlled when placing the initial mat.

Should the methods and equipment furnished by the Contractor fail to produce a layer of asphalt concrete conforming to the provisions, including straightedge tolerance, of Section 39-6.03, "Compacting," of the Standard Specifications, the paving operations shall be discontinued and the Contractor shall modify the equipment or methods, or furnish substitute equipment.

Should the automatic screed controls fail to operate properly during a day's work, the Contractor may manually control the spreading equipment for the remainder of that day. However, the equipment shall be corrected or replaced with alternative automatically controlled equipment conforming to the provisions in this section before starting another day's work.

10-1.17 CONCRETE STRUCTURES

Portland cement concrete structures shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Portland cement concrete shall conform to the provisions in "Freezing Condition Requirements" of these special provisions.

Full compensation for filter fabric shall be considered as included in the contract price paid per cubic meter for minor concrete (minor structure) and no separate payment will be made therefor.

10-1.18 SLOPE PROTECTION

Slope protection shall be placed or constructed in conformance with the provisions in Section 72, "Slope Protection," of the Standard Specifications.

Rock slope protection fabric shall be woven or nonwoven type fabric, Type A or Type B, at the option of the Contractor.

10-1.19 MISCELLANEOUS CONCRETE CONSTRUCTION

Minor concrete (curb and curb ramp) shall conform to the provisions in Section 73, "Concrete Curbs and Sidewalks," of the Standard Specifications.

10-1.20 MISCELLANEOUS IRON AND STEEL

Miscellaneous iron and steel shall conform to the provisions in Section 75, "Miscellaneous Metal," of the Standard Specifications.

10-1.21 CHAIN LINK FENCE

Chain link fence shall be Type CL-1.8 and shall conform to the provisions in Section 80, "Fences," of the Standard Specifications.

10-1.22 GUARD POST

Guard posts shall be constructed of 200-mm galvanized standard pipe 2.4 m long. Posts shall be set 1.2 m in a block of portland cement concrete, as shown on the plans, and the pipe shall be filled with portland cement concrete.

Pipe used for guard posts shall conform to the specifications of ASTM Designation: A 53.

The contract unit price paid for guard post shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing guard posts, complete in place, as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

SECTION 11. (BLANK)

SECTION 12-1. GENERAL REQUIREMENTS

12-1.01 SCOPE

Building work described herein and as shown on the plans shall conform to the requirements of these special provisions and Sections 1 through 9 of the Standard Specifications. Sections 10 through 95 of the Standard Specifications shall not apply to the work in this Section 12 except when specific reference is made thereto.

The building work to be done consists, in general, of constructing an Equipment/Office Building, Materials Bin with Canopy, Equipment Canopy, including related mechanical, electrical, and sanitary work, and such other items or details, not mentioned above, that are required by the plans, General Conditions, or these special provisions shall be performed, placed, constructed or installed at the Hayfork Maintenance Station.

12-1.02 ABBREVIATIONS

Section 1-1.02, "Abbreviations," of the Standard Specifications is amended by adding the following:

AAMA	American Architectural Manufacturers' Association
ACI	American Concrete Institute
AGA	American Gas Association
AITC	American Institute of Timber Construction
AMCA	Air Movement and Control Association
APA	American Plywood Association
ARI	American Refrigeration Institute
ASHRAE	American Society of Heating, Refrigeration and Air Conditioning Engineers
CBC	California Building Code (2001 Edition)
CEC	California Electrical Code (2001 Edition)
CMC	California Mechanical Code (2001 Edition)
CPC	California Plumbing Code (2001 Edition)
CS	Commercial Standards (US Department of Commerce)
ESO	Electrical Safety Orders
FGMA	Flat Glass Marketing Association
FM	Factory Mutual
FS	Federal Specification
ICBO	International Conference of Building Officials
NAAMM	National Association of Architectural Metal Manufacturers
NBFU	National Board Fire Underwriters
NEC	National Electrical Code
NFPA	National Fire Protection Association or National Forests Products Association
PEI	Porcelain Enamel Institute
PS	Product Standard (US Department of Commerce)
RIS	Redwood Inspection Service
SCPI	Structural Clay Products Institute
SMACNA	Sheet Metal and Air Conditioning Contractors' National Association
SSPC	Steel Structures Paint Council
TCA	Tile Council of America
TPI	Truss Plate Institute
UBC	Uniform Building Code (1997 Edition)
WCLIB	West Coast Lumber Inspection Bureau (stamped WCLB)
WCLB	Grade stamp for WCLIB
WIC	Woodwork Institute of California
WWPA	Western Wood Products' Association

12-1.03 GUARANTEE

The Contractor hereby unconditionally guarantees that the building work will be done in accordance with the requirements of the contract, and further guarantees the building work of the contract to be and remain free of defects in workmanship and materials for a period of one year from the date of acceptance of the contract, unless a longer guarantee period is required elsewhere in these special provisions. The Contractor hereby agrees to repair or replace any and all building work, together with any other adjacent work which may be displaced in so doing, that may prove to be not in accordance with the requirements of the contract or that may be defective in its workmanship or material within the guarantee period specified, without any expense whatsoever to the Department, ordinary wear and tear and unusual abuse or neglect excepted.

The performance bond for contract price of the building work, shall remain in full force and effect during the guarantee period.

The Contractor further agrees, that within 10 calendar days after being notified in writing by the Department of any building work not in accordance with the requirements of the contract or any defects in the building work, he shall commence and prosecute with due diligence all work necessary to fulfill the terms of this guarantee, and shall complete the work within a reasonable period of time, and, in the event he fails to comply, he does hereby authorize the Department to proceed to have such work done at the Contractor's expense and he shall honor and pay the cost and charges therefor upon demand. The Department shall be entitled to all costs and expenses, including reasonable attorney's fees, necessarily incurred upon the Contractor's refusal to honor and pay the above costs and charges.

12-1.04 AREAS FOR CONTRACTOR'S USE

No area is available within the contract limits for the exclusive use of the Contractor. The Contractor shall arrange with the Engineer for areas to store equipment and materials within the work area.

12-1.05 COOPERATION

Attention is directed to Sections 7-1.14, "Cooperation," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

Work by State forces will be in progress within the contract limits during the working period for this contract.

The Contractor shall comply with all security policies and normal working hours of the State concerning the Hayfork Maintenance Station.

The Contractor shall plan his work to minimize interference with State forces and the public. Interruptions to any services for the purpose of making or breaking a connection shall be made only after consultation with and for such time periods as directed by the Engineer.

12-1.06 SUBMITTALS

Working drawings, material lists, descriptive data, samples and other submittals specified in these special provisions shall be submitted for approval in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and these special provisions.

Unless otherwise permitted in writing by the Engineer, all submittals required by these special provisions shall be submitted within 35 days after the contract has been approved.

Attention is directed to the provisions in Section 5-1.01, "Authority of Engineer," of the Standard Specifications. The Engineer may request submittals for materials or products where submittals have not been specified in these special provisions, or may request that additional information be included in specified submittals, as necessary to determine the quality or acceptability of such materials or products.

Attention is directed to Section 6-1.05, "Trade Names and Alternatives," of the Standard Specifications. The second indented paragraph of the first paragraph of said Section 6-1.05 is amended to read:

Whenever the specifications permit the substitution of a similar or equivalent material or article, no test or action relating to the approval of such substituted material will be made until the request for substitution is made in writing by the Contractor accompanied by complete data as to the equality of the material or article proposed. Such request shall be made within 35 days after the date the contract has been approved and in ample time to permit approval without delaying the work, but need not be made in less than 35 days after award of the contract.

Work requiring the submittal of working drawings, material lists, descriptive data, samples, or other submittals shall not begin prior to approval of said submittal by the Engineer. Fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete his review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications.

Submittals shall be delivered to the locations indicated in these special provisions. If a specific location is not indicated, the submittal shall be delivered to the Division of Structure Design, Documents Unit, Fourth Floor, Mail Station 9-4/4I, 1801 30th Street, Sacramento, California 95816, telephone (916) 227-8252, or the submittals shall be mailed to the Division of Structure Design, Documents Unit, Mail Station 9-4/4I, P. O. Box 942874, Sacramento, California 94274-0001.

Each submission of drawings, material lists and descriptive data shall consist of at least 5 copies. Two copies will be returned to the Contractor either approved for use or returned for correction and resubmittal.

Each separate item submitted shall bear a descriptive title, the name of the project, district, county, and contract number. Plans and detailed drawings shall be not larger than 559 mm x 914 mm.

The material list shall be complete as to name of manufacturer, catalog number, size, capacity, finish, all pertinent ratings, and identification symbols used on the plans and in the special provisions for each unit.

Parts lists and service instructions packaged with or accompanying the equipment installed in the work shall be delivered to the Engineer at the jobsite. Required operating and maintenance instructions shall be submitted in triplicate.

Manufacturer's warranties for products installed in the work shall be delivered to the Engineer at the jobsite.

Unapproved samples and samples not incorporated in the work shall be removed from State property, when directed by the Engineer.

12-1.07 PROGRESS SCHEDULE

A progress schedule shall be submitted in duplicate for the building work in accordance with the requirements in Section 8-1.04, "Progress Schedule," of the Standard Specifications.

12-1.08 SCHEDULE OF VALUES

The Contractor shall prepare and submit to the Engineer for approval 2 copies of a Schedule of Values within 15 working days of approval of the contract covering each lump sum item for building work. Fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete his review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications.

The Schedule of Values must be accurately divided into sections representing the cost of each separate building or structure. All work that is not part of a separate building or structure, such as excavation, grading, curbs, gutters, sidewalks, paving, sewer and storm drainage and utility distribution lines are to be included under a specific section as General Work and not included in the building or structure cost. Indirect costs and general condition items are to be listed as a separate line item of work. The sections representing each building or structure must be identified as to the building or structure they represent and be broken down to show the corresponding value of each craft, trade or other significant portion of the work. A sub-total for each section shall be provided.

The Schedule of Values shall be approved by the Engineer before any partial payment estimate is prepared.

The sum of the items listed in the Schedule of Values shall equal the contract lump sum price for building work. Overhead, profit and bond premium are to be appropriately distributed across all line items of cost.

12-1.09 INSPECTION

All items covered or all stages of work that are not to remain observable must be inspected and approved before progress of work conceals portions to be inspected. The Contractor shall notify the Engineer not less than 72 hours in advance of when such inspection is needed.

12-1.10 OBSTRUCTIONS

Attention is directed to Sections 7-1.11, "Preservation of Property," 7-1.12, "Responsibility for Damage," 7-1.16, "Contractor's Responsibility for the Work and Materials," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 5 working days prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include but are not limited to the following:

Underground Service Alert
Northern California (USA)
Telephone: 1(800)642-2444

Underground Service Alert
Southern California (USA)
Telephone: 1(800)422-4133

South Shore Utility
Coordinating Council (DIGS)
Telephone: 1(800)541-3447

Western Utilities
Underground Alert, Inc.
Telephone: 1(800)424-3447

12-1.11 PRESERVATION OF PROPERTY

Attention is directed to Sections 7-1.11, "Preservation of Property," 7-1.12, "Responsibility for Damage," 7-1.16, "Contractor's Responsibility for the Work and Materials," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

Operations shall be conducted in such a manner that existing facilities, surfacing, installations, and utilities which are to remain in place will not be damaged. Temporary surfacing, facilities, utilities and installations shall also be protected until they are no longer required. The Contractor, at his expense shall furnish and install piling, sheet piling, cribbing, bulkheads, shores, or whatever means may be necessary to adequately support material carrying such facilities, or to support the facilities themselves and shall maintain such support until they are no longer needed.

12-1.12 UTILITY CONNECTION

The Contractor shall make all arrangements, and obtain all permits and licenses required for the extension of and connection to each utility service applicable to this project, shall furnish all labor and materials necessary for such extensions which are not performed or provided by the utility, and shall furnish and install any intermediate equipment required by the serving utilities.

Upon written request by the Contractor, the State will pay all utility permits, licenses, connection charges, and excess length charges directly to the utility. Such request shall be submitted not less than 45 days before service connections are required.

The costs incurred by the Contractor for the extensions of utilities beyond the limits shown on the plans, and in furnishing and installing any intermediate equipment required by the serving utilities, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Full compensation for any costs incurred by the Contractor to obtain the permits and licenses shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

12-1.13 TEMPORARY UTILITIES

The Contractor may obtain electrical power and water from existing State electrical power and water outlets within the contract limits free of charge for contract operations where such utilities exist, provided that such utility services are in service and are not required by the State for other purposes and subject to the provisions in the section "Cooperation" of these special provisions.

The Contractor shall make his own arrangements to obtain any additional electrical power and water or other utilities required for his operations and shall make and maintain the necessary service connections at his own expense.

When existing utility systems are being modified, periods of shutdown will be determined by the Engineer.

The Contractor shall provide adequate temporary lighting to perform the work and allow the Engineer to inspect the project as each portion is completed.

The Contractor shall provide and pay for telephone service he may require. State telephone facilities shall not be used.

12-1.14 SANITARY FACILITIES

When operational, State sanitary facilities will be available for use by the Contractor's employees, during normal State working hours. Tools shall not be cleaned nor shall cleaning liquids be disposed of in State sanitary facilities or sewers.

12-1.15 MEASUREMENT AND PAYMENT

The contract lump sum price paid for building work shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the building work, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for any incidental materials and labor, not shown on the plans or specified, which are necessary to complete the buildings and appurtenances shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

12-1.16 PROJECT RECORD DRAWINGS

The Contractor shall prepare and maintain one set of project record drawings, using an unaltered set of original project plans, to clearly show all as-constructed information for the project. As a minimum, the information to be shown shall include 1) any plan clarifications or change orders, 2) locations of any underground utilities, or 3) the location, size, type, and manufacturer of all major products or components selected by the Contractor for use in the work.

All markings shall be placed on the project record drawings using red ink or red pencil. Original figures shall not be eradicated nor written over and superseded material shall be neatly lined out. Additional drawings shall be submitted if the required information cannot be clearly shown on the original set of project plans. The additional drawings shall be not less than 279 mm x 432 mm in size and shall have the contract number on each sheet. The Contractor shall sign and date each sheet of the project record drawings to verify that all as-constructed information shown on the drawings is correct.

The Contractor shall periodically review the set of project record drawings with the Engineer during the progress of the work to assure that all changes and other required information are being recorded.

Before completion of the work, the Contractor shall request a review of the project record drawings to determine the completeness and adequacy of them. If the project record drawings are unacceptable, the Contractor shall inspect, measure, and survey the project as necessary to record the required additional information.

The set of completed project record drawings shall be delivered to the Engineer prior to acceptance of the contract.

12-1.17 FIELD ENGINEERING

This section specifies administrative and procedural requirements for field engineering services to be performed by the Contractor.

Lines and grades.--Attention is directed to Section 5-1.07 "Lines and Grades," of the Standard Specifications.

Such stakes or marks will be set by the Engineer as he determines to be necessary to establish the lines and grades required for the completion of the work shown on the plans and as specified in these special provisions. In general, these will consist of the primary vertical and horizontal control points.

Stakes and marks set by the Engineer shall be carefully preserved by the Contractor. In case such stakes and marks are destroyed or damaged they will be replaced at the Engineer's earliest convenience. The Contractor will be charged for the cost of necessary replacement or restoration of such stakes and marks which in the judgment of the Engineer were carelessly or willfully destroyed or damaged by the Contractor's operations. This charge will be deducted from any moneys due or to become due the Contractor.

All other stakes or marks required to establish the lines and grades required for the completion of the work shall be the responsibility of the Contractor.

Existing utilities and equipment.--The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, the Contractor shall investigate and verify the existence and location of underground utilities and other construction.

Prior to construction, the Contractor shall verify the location and invert elevation at points of connection of sanitary and septic sewers, storm sewer, and water or fire service piping.

Surveys for layout and performance.--The Contractor shall perform all surveys for layout and performance, reduce field notes, and make all necessary calculations and drawings necessary to carry out the work.

The Contractor shall locate and layout site improvements, and other work requiring field engineering services, including pavements, stakes for grading, fill and topsoil placement, utility slopes and invert elevations by instrumentation and similar appropriate means.

Batter boards shall be located and laid out for structures, building foundations, column grids and locations, floor levels and, control lines and levels required for mechanical and electrical work.

Survey accuracy and tolerances.--The tolerances generally applicable in setting survey stakes for foundations, slabs, and underground work shall not exceed the following:

Survey Stakes or Markers	Tolerance
Rough grading or excavation	30 mm
Trimming or preparation of subgrade for roadways	15 mm
Roadway surfacing, steel or concrete pipe	6 mm
Structures or building construction	3 mm

Such tolerance shall not supersede stricter tolerances required by the plans or special provisions, and shall not otherwise relieve the Contractor of responsibility for measurements in compliance therein.

12-1.18 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the inch-pound (imperial) system which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following requirements:

Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.

Before other non-metric materials and products will be considered for use the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish all information necessary as required to the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision shall be final.

When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, a list of substitutions to be made shall be submitted for approval.

The following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325M	
METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	IMPERIAL SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR REINFORCEMENT	
METRIC BAR DESIGNATION NUMBER AS SHOWN ON THE PLANS	IMPERIAL BAR DESIGNATION NUMBER TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

SUBSTITUTION TABLE FOR WELDED PLAIN WIRE REINFORCEMENT, ASTM DESIGNATION: A 185	
	US CUSTOMARY UNITS SIZE TO BE SUBSTITUTED inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

The sizes in the following tables of materials and products are exact conversions of metric sizes of materials and products and are listed as acceptable equivalents:

CONVERSION TABLE FOR SIZES OF: (1) STEEL FASTENERS FOR GENERAL APPLICATIONS, ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55, and (2) HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325 or A 449	
DIAMETER	
METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
6, or 6.35	1/4
8 or 7.94	5/16
10, or 9.52	3/8
11, or 11.11	7/16
13 or 12.70	1/2
14, or 14.29	9/16
16, or 15.88	5/8
19, or 19.05	3/4
22, or 22.22	7/8
24, 25, or 25.40	1
29, or 28.58	1-1/8
32, or 31.75	1-1/4
35, or 34.93	1-3/8
38 or 38.10	1-1/2
44, or 44.45	1-3/4
51, or 50.80	2
57, or 57.15	2-1/4
64, or 63.50	2-1/2
70 or 69.85	2-3/4
76, or 76.20	3
83, or 82.55	3-1/4
89 or 88.90	3-1/2
95, or 95.25	3-3/4
102, or 101.60	4

CONVERSION TABLE FOR NOMINAL THICKNESS OF SHEET METAL			
UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED (GALVANIZED) SHEETS	
METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT US STANDARD GAGE inch	METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT GALVANIZED SHEET GAGE inch
7.94	0.3125		
6.07	0.2391		
5.69	0.2242		
5.31	0.2092		
4.94	0.1943		
4.55	0.1793		
4.18	0.1644	4.270	0.1681
3.80	0.1495	3.891	0.1532
3.42	0.1345	3.510	0.1382
3.04	0.1196	3.132	0.1233
2.66	0.1046	2.753	0.1084
2.28	0.0897	2.372	0.0934
1.90	0.0747	1.994	0.0785
1.71	0.0673	1.803	0.0710
1.52	0.0598	1.613	0.0635
1.37	0.0538	1.461	0.0575
1.21	0.0478	1.311	0.0516
1.06	0.0418	1.158	0.0456
0.91	0.0359	1.006 or 1.016	0.0396
0.84	0.0329	0.930	0.0366
0.76	0.0299	0.853	0.0336
0.68	0.0269	0.777	0.0306
0.61	0.0239	0.701	0.0276
0.53	0.0209	0.627	0.0247
0.45	0.0179	0.551	0.0217
0.42	0.0164	0.513	0.0202
0.38	0.0149	0.475	0.0187

CONVERSION TABLE FOR WIRE		
METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT USA STEEL WIRE THICKNESS	GAGE NO.
mm	inch	
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

CONVERSION TABLE FOR COMMON NAILS				
NAIL SIZE	METRIC mm		ENGLISH inch	
	Length	Diameter	Length	Diameter
8d	63.5	3.33	2 1/2	0.131
10d	76.2	3.76	3	0.148
16d	88.9	4.11	3 1/2	0.162

CONVERSION TABLE FOR LUMBER	
METRIC NOMINAL SURFACE DRY SIZE	EQUIVALENT NOMINAL SURFACE DRY U S SIZE
mm	inch
51	2
102	4
152	6
203	8
254	10
305	12

CONVERSION TABLE FOR PLYWOOD	
METRIC mm	ENGLISH inch
6.4	1/4
7.9	5/16
9.5	3/8
11.1	7/16
11.9	15/32
12.7	1/2
15.1	19/32
15.9	5/8
18.3	23/32
19.1	3/4
22.2	7/8
25.4	1
28.6	1 1/8

CONVERSION TABLE FOR INSULATION R-VALUE	
METRIC (K m ² /W)	ENGLISH (HR FT ² F/BTU)
0.5	3
0.7	4
1.4	8
1.9	11
2.3	13
2.5	14
3.3	19
5.3	30

CONVERSION TABLE FOR VAPOR TRANSMISSION RATING	
METRIC (Perm-m)	ENGLISH (perm-inch)
0.29	0.02

CONVERSION TABLE FOR LOW PRESSURE	
METRIC (Pa)	ENGLISH (Inches of Water Column)
30	0.125
60	0.25
90	0.375
120	0.50
150	0.60
155	0.625
175	0.70
185	0.75
200	0.80
250	1.00
310	1.25

CONVERSION TABLE FOR PRESSURE	
METRIC (kPa)	ENGLISH (psi)
10	1.5
210	30
280	40
350	50
690	100
860	125
1040	150
1100	160
1210	175
1380	200
1730	250
2070	300
2170	315
2410	350
2590	375
2760	400
4830	700
5170	750
5520	800
13800	2000
17200	2500
20700	3000
27600	4000
34500	5000
137900	20000

CONVERSION TABLE FOR MIL THICKNESS	
METRIC (mm)	ENGLISH (inch/1000)
0.10	4
0.13	5
0.15	6
0.50	20
0.75	30
1.00	40

CONVERSION TABLE FOR HVAC DUCTING.	
METRIC (mm)	ENGLISH (inch)
100	4
125	5
150	6
175	7
200	8
225	9
250	10
300	12
360	14
410	16
460	18
510	20
560	22
610	24
660	26
710	28
760	30

CONVERSION TABLE FOR MECHANICAL PIPING		
METRIC (GSP, PVC, BSP, DUCTILE IRON)	METRIC (mm)	ENGLISH (inch)
NPS 1/2	15	1/2
NPS 3/4	20	3/4
NPS 1	25	1
NPS 1 1/4	32	1 1/4
NPS 1 1/2	40	1 1/2
NPS 2	50	2
NPS 2 1/2	65	2 1/2
NPS 3	75	3
NPS 4	100	4
NPS 6	150	6

CONVERSION TABLE FOR LUBRICATION PIPING TUBING WALL THICKNESS	
METRIC (mm)	ENGLISH (inch)
2.1	0.083
0.9	0.035

CONVERSION TABLE FOR HOSE/TUBING SIZES O. D.	
METRIC (mm)	ENGLISH (inch)
6	1/4
10	3/8
13	1/2
16	5/8
19	3/4
22	7/8
25	1

CONVERSION TABLE FOR DRUM SIZES			
METRIC		ENGLISH	
L	kg	gallons	pounds
205	180	55	400
60	55	16	120
19	16	5	35

CONVERSION TABLE FOR POWER	
METRIC (kW)	ENGLISH (HP)
0.037	1/20
0.075	1/10
0.18	1/4
0.25	1/3
0.37	1/2
0.55	3/4
0.75	1
1.1	1 1/2
1.5	2
2.2	3
3.7	5
5.5	7 1/2
7.5	10
11	15
15	20
18.5	25
22	30
30	40
37	50
45	60
55	75
75	100
90	120
110	150

CONVERSION TABLE FOR IMPELLER BALANCE		
SYNCHRONOUS RPM	METRIC (g mm/kg)	ENGLISH (ounce- inch/pound)
720	94	0.059
900	73	0.046
1200	54	0.034
1800	41	0.026
3600	17	0.011

CONVERSION TABLE FOR ELECTRICAL CONDUIT	
METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
16	1/2
21	3/4
27	1
35	1 1/4
41	1 1/2
53	2
103	4

SECTION 12-2. SITEWORK

12-2.01 REMOVING PORTIONS OF EXISTING FACILITIES

PART 1.- GENERAL

Scope.--This work shall consist of removing portions of the existing facilities, including removal of existing work to gain access to or for new work, in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS (Not applicable)

PART 3.- EXECUTION

PREPARATION.--

General.--The limits of removal shall be located and identified. Items to be removed and the interface of items to be removed and items to remain intact shall be identified and marked.

Prior to removing concrete or masonry, a saw cut approximately 25 mm deep shall be made along the limits of removal on all faces that will be visible in the completed work.

REMOVAL.--

General.--Removal shall be to the limits shown on the plans. Removal shall be done carefully to minimize damage to the portions to remain. Remaining portions that are damaged by the Contractor's operation shall be restored to original condition at the Contractor's expense.

Assemblies to be salvaged which require dismantling for removal shall be matchmarked before dismantling.

Existing apparatuses, devices, or accessories which would be functionally impaired by new construction or remodeling shall be moved, brought out to new surfaces, or provided with new access covers, as necessary to restore apparatuses, devices, or accessories to their original usefulness.

Piping and conduits to be abandoned shall be capped or plugged.

Surfaces that are exposed to view at the limits of removal work shall be patched, bumps shall be removed and depressions filled, and the surface shall be finished to match the existing surrounding surfaces. Depressions in concrete less than 25 mm deep shall be deepened to 25 mm minimum depth before filling with cement mortar.

Existing reinforcement that is to be incorporated into the new work shall be protected from damage and thoroughly cleaned before being embedded in new concrete.

DISPOSAL.--

General.--Materials that are to be removed, shall become the property of the Contractor and shall be disposed of outside the highway right of way in accordance with the requirements in Section 7-1.13, "Disposal of Material Outside of the Highway Right of Way," of the Standard Specifications.

SALVAGE.--

General.--Materials or equipment shown on the plans to be salvaged shall remain the property of the State and shall be removed, cleaned and stockpiled at a location at the project site designated by the Engineer.

12-2.02 RELOCATING MATERIALS AND EQUIPMENT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of relocating existing materials and equipment in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS (Not applicable)

PART 3.- EXECUTION

RELOCATION.--

General.--Materials or equipment to be relocated shall be removed carefully to avoid damage to the materials or equipment or to the materials or equipment which are to remain. Assemblies to be relocated which require dismantling for removal shall be matchmarked before dismantling.

The Contractor shall notify the Engineer prior to the relocation work in order that the materials or equipment may be inspected for existing damage.

Materials or equipment to be relocated shall have all adhering concrete, mastics, earth or other deleterious materials removed and shall have all exterior surfaces cleaned.

Materials or equipment which are damaged by the Contractor's operations shall be replaced or restored to match the condition of the materials or equipment prior to the beginning of the Contractor's operations. Replacement or restoration of damaged materials or equipment shall be at the Contractor's expense.

Connections, anchorages and fasteners for relocated materials and equipment shall match existing and shall be furnished and installed by the Contractor. Assemblies which have been dismantled shall be reassembled to match the existing installation. Relocated materials and equipment shall be installed as required for new work.

Modifications to wiring and plumbing to accommodate relocated items shall be as shown on the plans. Ends of piping and conduits to be abandoned shall be capped.

Surfaces that are exposed to view upon removal or relocation of materials or equipment shall be patched. Bumps shall be removed and depressions filled, and the surface finished to match the existing surfaces. Depressions in concrete less than 25 mm deep shall be deepened to 25 mm minimum depth before filling with cement mortar.

DISPOSAL.--

General.--Materials from existing facilities to be reused in the work, in the opinion of the Engineer, is unsuitable for use shall become the property of the Contractor and disposed of as provided in Section 7-1.13, "Disposal of Material Outside of the Highway Right of Way." of the Standard Specifications. The unsuitable material shall be replaced as ordered by the Engineer and will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

12-2.03 REMOVE WASTE DISPOSAL SYSTEM

PART 1. - GENERAL

SUMMARY

Scope: This work shall consist of removing the existing waste disposal system in accordance with the details shown on the plans and these special provisions.

Codes and Standards: Attention is directed to Section 7-1.01, "Laws to be Observed," of the Standard Specifications.

PART 2. - PRODUCTS (Not applicable)

PART 3. - EXECUTION

Disposal: Sewage facilities to be removed shall be pumped out and the sewage and sediment removed from such facilities shall be disposed of away from the premises. Disposal shall conform to the laws, rules and regulations of the agency having jurisdiction of the disposal site.

Abandoning Piping: Each pipe entering or exiting the sewage disposal system to be removed shall be closed by a tight fitting plug or wall of concrete not less than 0.5 foot thick. Such concrete shall be commercial quality concrete and shall contain not less than 470 pounds of cement per cubic yard of concrete.

Manhole Frames and Covers: Manhole frames and covers which are to be removed shall become the property of the Contractor and disposed of away from the premises. Such disposal shall conform to the laws, rules, and regulations of all agencies having jurisdiction at the disposal site.

12-2.04 CORE CONCRETE

PART 1- GENERAL

This work shall consist of coring holes through existing concrete surfaces in accordance with the details shown on the plans and these special provisions.

PART 3- EXECUTION

Holes shall be cored by methods that will not shatter or damage the concrete adjacent to the holes.

The diameter of the cored holes shall be as shown on the plans.

Water for the core drilling operations shall be from the domestic water supply and shall not contain more than 1,000 parts per million of chlorides as Cl, nor more than 1,300 parts per million of sulfates as SO₄, nor shall it contain any impurities in a sufficient amount to cause discoloration or etching of the surface.

Water from the core drilling operations shall not be permitted to flow into sewers or other drainage facilities.

12-2.05 EARTHWORK FOR BUILDING WORK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of performing earthwork for building work in accordance with the details shown on the plans and these special provisions.

Earthwork for building work shall consist of structure excavation and structure backfill. Structure excavation shall include excavation for footings, foundations, slabs, and trenches. Structure backfill shall include backfilling under slabs; backfilling under and around footings; backfilling for pipes and conduits. In addition to structure excavation and structure backfill, earthwork for building work shall include any other earthwork, not mentioned, but necessary to complete the building work.

Attention is directed to the Materials Information Handout for information regarding foundation recommendations and reports that were prepared for use during the design of this project.

Attention is directed to the requirements of "Field Engineering" in Section 12-1, "General Requirements," of these special provisions.

QUALITY ASSURANCE.--

Samples.--Samples of sand, pea gravel, or crushed stone, weighing not less than 11 kg, shall be submitted to the Engineer at the jobsite for approval.

SITE CONDITIONS.--

Existing underground piping and conduit.--The location of existing underground piping and conduit is based on the best records available. Before beginning work, the Contractor shall accurately locate the piping and conduit involved in the work. If the location of the existing piping or conduit deviates from the location shown on the plans by more than 1.5 meters, or, if no elevations are indicated and the piping or conduit is more than 0.9 meter below grade, the cost of the additional excavation, backfill, piping or conduit, and removal and replacement of concrete, if any, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Existing surfaced areas.--Existing surfaced areas that are removed, broken or damaged by the Contractor's operations shall be restored to their original condition except as otherwise shown on the plans or specified herein.

Restoration materials shall be equal to or better than the original materials. Surfacing shall be replaced to match the material thickness, grades, and finish of the adjacent surrounding surfaces.

PART 2.- PRODUCTS

BACKFILL MATERIALS.--

Structure backfill.--

Structure and trench backfill shall be free of organic and other deleterious material and shall be suitable for the required compaction. Gravel without sand matrix shall not be used except as free draining granular material beneath slabs and footings.

Sand.--

Sand shall be clean, washed sand, free from clay or organic material graded such that 100 percent passes the 6 mm sieve, 90 percent to 100 percent passes the 4.75 mm sieve and not more than 5 percent passes the 75 μ m sieve size.

Pea gravel (naturally rounded).--

Pea gravel (naturally rounded) shall be clean, washed, dry density of not less than 1522 kg/m³, free from clay or organic material and shall conform to the following grading as determined by California Test 202:

Sieve or Screen Size	Percentage Passing
19 mm	100
13 mm	90-100
9.5 mm	40-70
4.75 mm	0-15
2.36 mm	0-3

Pea gravel shall conform to the following requirements:

Test	California Test No.	Test Requirements
Durability Index	229	35 Min.

Crushed stone.--

Crushed stone shall be clean, washed, dry density of not less than 1522 kg/m³, crushed stone or crushed gravel with an angular particle size not less than 3 mm or more than 13 mm.

Sieve or Screen Size	Percentage Passing
13 mm	100
9.5 mm	85-100
4.75 mm	10-30
2.36 mm	0-3

Crushed stone shall conform to the following requirements:

Test	California Test No.	Test Requirements
Durability Index	229	35 Min.

PART 3.- EXECUTION

PREPARATION & RESTORATION.--

Sawcutting.--Prior to excavation or trenching, existing surfacing shall be removed to saw cut lines, or to existing wood dividers or expansion joints, if any. The saw cut shall be to a neat line and have a depth not less than 25 mm.

Restoration.--Surfacing shall be replaced to match the thickness, grades and finish of the adjacent surrounding surfaces.

STRUCTURE EXCAVATION.--

General.--Unless otherwise noted, all excavation for building work shall be classified as structure excavation.

Footing excavation.--The bottom of excavation shall not be disturbed. The contractor shall excavate by hand to the final grade. The bottom of concrete footings shall be poured against undisturbed material. Unless otherwise noted, compaction of the bottom of footing excavation is not required unless the material is disturbed. The footing depths shown on the plans shall be changed to suit field conditions when directed by the Engineer. Solid rock at or near required depths shall not be disturbed. Unsuitable material shall be excavated down to firm bearing as directed by the Engineer. Work and materials required because of excavation in excess of the depths shown on the plans, when such excavation has been ordered by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Excavate to the elevations and dimensions within a tolerance of ± 12 mm. Limits of the excavation shall allow for adequate working space for installing materials and as required for safety of personnel. Such working space excavation shall be replaced in kind and compacted at the Contractor's expense.

Overdepth excavation for footings shall be backfilled with concrete or such other material recommended by the Contractor and approved by the Engineer. Relative compaction shall be not less than 95 percent.

Excavation for pipes and conduits.--Pipes or conduits in the same trench shall have a minimum clear distance between pipes or conduits of 150 mm. Pipes or conduits shall have not less than 0.75 meter of cover from top of pipes or conduits to finished grade unless otherwise shown on the plans or specified.

Trenching shall be of sufficient depth to permit placing a minimum depth of 100 mm of compacted sand under all pipes and conduits.

Excavation adjacent to trees shall be performed by hand methods where necessary to avoid injury to trees and roots. Roots 50 mm in diameter and larger shall be protected with heavy burlap. Roots smaller than 50 mm in diameter adjacent to trees shall be hand trimmed. Cuts through roots 13 mm in diameter and larger shall be sealed with tree trimmers' asphaltic emulsion. If trenches remain open more than 24 hours, the side of the trench adjacent to the tree shall be shaded with burlap and kept damp. Materials shall not be stockpiled within the drip line of trees.

Dewatering.--Excavations shall be kept clear of standing water. Water shall be removed by pumping if necessary. Water removed from excavation shall be carried away from the building site and disposed of in a manner that will not harm State or adjacent property.

STRUCTURE BACKFILLING.--

General.--Unless otherwise noted, all backfill for building work shall be classified as structure backfill. Backfill shall be placed and compacted in horizontal layers, not more than 150 mm thick prior to compaction, and to the lines and grades shown on the plans or to original ground.

Structure backfill.--After structures are in place and forms are removed, wood and other debris shall be removed from excavations before placing structure backfill.

Backfilling pipes and conduits.--Backfill placed under pipe and conduits shall be compacted sand, 100 mm minimum depth. Backfill material placed to a level 150 mm above tops of pipes and conduits shall be sand or fine earth and particles shall not exceed 13 mm in greatest dimension. For wrapped, coated, or plastic pipe or conduits, sand shall be used for backfill. Backfill material placed higher than 150 mm above tops of pipes or conduits shall consist of material free of stones or lumps exceeding 100 mm in greatest dimension except:

- (a) The top 300 mm of backfill under roads, walks or paving shall consist of aggregate base material.
- (b) The top 150 mm of backfill in planted areas shall consist of topsoil.

COMPACTION.--

General.--Relative compaction shall be determined in accordance with California Test 216 or 231. Unless otherwise noted below, all backfill shall be compacted to a minimum relative compaction of 90 percent. Unless approved in writing by the Engineer, compaction by jetting or ponding will not be permitted.

Compact original ground.--Original ground surface under fill with surfacing of concrete and asphalt concrete shall be compacted to a relative compaction of not less than 95 percent for a minimum depth of 150 mm.

Structure backfill.--Structure backfill shall be compacted to not less than 95 percent relative compaction.

Trench backfill.--Trench backfill placed beneath slabs or paved areas shall be compacted to a relative compaction of not less than 95 percent.

DISPOSAL.--

Surplus material.--Surplus material from the excavation shall be removed and disposed of outside the right-of-way in accordance with Section 7-1.13 of the Standard Specifications.

FIELD QUALITY CONTROL.--

Inspection.--When the excavation is substantially completed to grade, the Contractor shall notify the Engineer. No concrete shall be placed until the foundation has been approved by the Engineer.

Testing.--The State will conduct compaction tests during the backfilling and compacting operations.

12-2.06 AGGREGATE BASE

PART 1.-GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing, spreading and compacting aggregate base in accordance with the details shown on the plans and these special provisions.

PART 2.-PRODUCTS

Aggregate base.--

Aggregate base shall be commercial quality aggregates consisting of broken stone; crushed gravel; natural, clean, rough-surfaced gravel and sand; or a combination thereof.

Aggregate base shall conform to the following grading as determined by California Test 202:

Sieve or Screen Size	Percentage Passing
25 mm	100
19 mm	90 - 100
4.75 mm	35 - 60
600 µm	10 - 30
75 µm	2 - 9

Aggregate base shall also conform to the following quality requirements:

Tests	California Test No.	Test Requirements
Durability Index	229	35 Min.
Resistance (R-Value)	301	78 Min.
Sand Equivalent	217	22 Min.

PART 3.-EXECUTION

SPREADING AND COMPACTING.--

Spreading.--Aggregate base shall be placed and compacted to the lines and grades shown on the plans.

Spreading and compacting shall be performed by methods that will produce a uniform base, free from pockets of coarse or fine material.

Compaction.--Relative compaction of each layer of compacted base material shall be not less than 95 percent, as determined by California Test 216 or 231.

12-2.07 FREE DRAINING GRANULAR MATERIAL

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and placing free draining granular material beneath slabs in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Free draining granular material.--

Free draining granular material shall be clean, hard, durable, free-draining rock. The material gradation shall be such that all passes the 25 mm screen, and not more than 10 percent passes the 4.75 mm sieve as determined by California Test 202. Granular material shall be free from organic material, clay balls or other deleterious substances.

PART 3.- EXECUTION

SPREADING AND CONSOLIDATING.--

General.--Free draining granular material shall be placed, spread and consolidated by tamping or vibrating.

12-2.08 TERMITE CONTROL

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and applying soil treatment for termite control in accordance with these special provisions.

SUBMITTALS.--

Product data.--Product labels for the soil treatment material showing descriptive information on the active chemical ingredients, mixing instructions for concentration levels, directions for use, application rates, and precautionary information shall be submitted for approval. Labels shall include an EPA product registration number.

QUALITY ASSURANCE.--

Attention is directed to Section 7-1.01H, "Use of Pesticides," of the Standard Specifications.

Soil treatment operations for control of termites shall be performed by a pest control operator who is licensed by the State of California.

Insecticides used in termite control work shall be approved and registered by the United States Environmental Protection Agency (EPA) and the State of California.

DELIVERY, HANDLING AND STORAGE.--

General.--The storage, mixing and application of chemicals; the cleaning of equipment; and the disposal of product containers shall be in accordance with federal, state and local regulations.

PART 2.- PRODUCTS

Soil treatment material.--

Soil treatment materials for termite control shall be commercial quality and shall be water emulsifiable.

The active chemical ingredient of the termiticide shall be any EPA approved chemical or combinations of chemicals intended for the eradication and control of subterranean termites.

All product containers shall bear the manufacturer's EPA approved label with EPA registration number.

PART 3.- EXECUTION

PREPARATION.--

General.--The Engineer shall be notified not less than 3 working days in advance of the planned termite control work. Similar notice shall be given to any state or local agency which requires that their representative be present during the termite control work.

Soil preparation.--Excavation, embankment construction, backfilling and grading operations shall be completed prior to the application of the soil treatment solution. Deleterious matter that will decrease the effectiveness of the treatment shall be removed from all areas to be treated.

Soil to be treated, except under slabs and foundations and vertical surfaces of trenches, shall be cultivated a minimum of 50 mm in depth, and shall be graded as shown on the plans.

Termite control work shall be performed in the presence of the Engineer unless the Contractor has received written approval from the Engineer to proceed.

MIXING.--

General.--The soil treatment emulsion shall be mixed in accordance with the manufacturer's instructions to achieve the chemical concentration level shown on the EPA approved product label for the type of soil and the area to be treated.

APPLICATION.--

General.--The soil treatment emulsion shall be applied to all soil within the area of the building including floor slab areas, under foundations and footings, to the horizontal and vertical surfaces of excavations and to such other areas or surfaces, not mentioned, but which are required for the complete and total protection of the building. The application shall be in accordance with the instructions shown on the EPA approved product label.

Where free draining material has previously been placed, sufficient amount of dilution shall be added to reach the soil beneath the free draining material.

Treated areas that are subsequently excavated, graded, trenched or filled shall be given an additional application.

PROTECTION.--

General.--Treated areas shall be protected in accordance with the instructions shown on the EPA approved product label until the treated surface is covered by subsequent construction.

If concrete slab cannot be placed over the soil the same day it has been treated, a vapor barrier shall be placed over the treated area to prevent disturbance of the treated soil.

12-2.09 CAST-IN-DRILLED-HOLE CONCRETE PILES

PART 1.- GENERAL

SUMMARY.--

Scope.--This work consists of constructing cast-in-drilled-hole concrete piles in accordance with the details shown on the plans and these special provisions.

PART 2.-PRODUCTS

Concrete and reinforcement.--

Concrete and reinforcement shall conform to the requirements specified under "Cast-In-Place Concrete" in Section 12-3, "Concrete and Reinforcement," of these special provisions.

PART 3.-EXECUTION

CONSTRUCTION.--

Drilling holes.--All holes for cast-in-drilled-hole concrete piles shall be drilled to the depths shown on the plans. All holes shall be examined for straightness and any hole which on visual inspection from the top shows less than 1/2 the diameter of the hole at the bottom of the hole shall be rejected. Suitable casings shall be furnished and placed to prevent caving of the hole.

All loose material existing at the bottom of the hole after drilling operations have been completed shall be removed before placing concrete.

Material resulting from drilling holes shall be wasted on the job site as directed by the Engineer.

Surface water shall not be permitted to enter the hole and all water which may have infiltrated into the hole shall be removed before placing concrete.

Placing reinforcement.--The reinforcing cage shall be placed and secured symmetrically about the center of the pile and blocked to clear the sides of the hole.

Longitudinal reinforcing steel shall be continuous for the entire length of pile, including pile extensions.

Placing concrete.--The concrete filling shall be vibrated to a dense and homogeneous condition. Concrete shall be placed against undisturbed material except when portions of the pile will be exposed to view. Surfaces exposed to view and adjacent surfaces within 250 mm of finished grade shall be formed.

Casing, if used in drilling operations, shall be removed from the hole as concrete is placed therein. The bottom of the casing shall be maintained not more than 1.5 meter nor less than 0.3 meter below the top of the concrete during withdrawal and placing operations. Separation of the concrete during withdrawal operations shall be avoided by hammering or otherwise vibrating the casing.

Formed surfaces shall conform to the requirements specified under "Cast-In-Place Concrete" in Section 12-3, "Concrete and Reinforcement," of these special provisions.

12-2.10 PAINTED PAVEMENT MARKINGS

PART 1.- GENERAL

Scope.--This work shall consist of furnishing and applying paint for pavement markings in accordance with the details shown on the plans and these special provisions.

Pavement markings include, but are not limited to, word and symbol markings, and parking stall markings.

PART 2.- PRODUCTS

Paint.--

Paint shall be top commercial quality for pavement marking, formulated for the use intended, and manufactured by a nationally recognized manufacturer of paint and other coating products.

The kind of paint to be used (solvent or water borne) shall be determined by the Contractor, based on local air pollution control regulations and weather conditions.

PART 3.- EXECUTION

ALIGNMENT AND LAYOUT.--All necessary alignment and layout work shall be performed by the Contractor, in a manner that will not damage the pavement.

Unless otherwise shown on the plans, the width of parking stall markings shall be 105 mm.

EQUIPMENT AND OPERATION.--Mechanical means shall be used to paint pavement markings.

All equipment used in the application of paint shall produce pavement markings of uniform quality.

All spray equipment shall be the proper type and of adequate capacity for the work involved.

Air atomized spray equipment shall be equipped with oil and water extractors and pressure regulators, and shall have adequate air volume and compressor recovery capacity. Spray gun tip needle assemblies and orifices shall be the proper size.

Rapid dry paint shall be applied only with airless type equipment.

Stencils and hand spray equipment shall be used to paint word and symbol markings. Stencils shall be furnished by the Contractor. The stencil layout shall conform to the dimensions shown on the plans.

SURFACE PREPARATION.--Surfaces which are to receive paint shall be cleaned of all dirt and loose material.

APPLICATION.--Paint shall be applied only on dry surfaces, and only during periods of favorable weather, in accordance with the manufacturer's recommendations.

On new surfacing, paint shall be applied in 2 coats. The first coat shall be dry before application of the second coat is applied.

On existing surfacing, paint shall be applied in one coat.

Completed pavement markings shall have clean and well-defined edges, and shall conform to the dimensions shown on the plans or as specified in these special provisions.

Drips, oversprays, improper markings, and paint material tracked by traffic shall be immediately removed from the pavement by methods approved by the Engineer. All such removal shall be at the Contractor's expense.

APPLICATION RATES.--Each application of paint shall be applied at the rates recommended by the paint manufacturer for the type of surface involved.

PROTECTION.--Newly placed pavement markings shall be protected from damage by traffic or other causes until the paint is thoroughly dry.

DISABLED ACCESSIBLE PARKING STALL SYMBOL.--Each parking space reserved for persons with physical disabilities shall have a minimum 0.9 m x 0.9 m surface identification with the international symbol of accessibility. The symbol and border shall be white and the background shall be blue conforming to Federal Standard 595B, Color No. 15090.

12-2.11 SANITARY SEWAGE DISPOSAL SYSTEM

PART 1. - GENERAL

SUMMARY

Scope: This work shall consist of furnishing, installing and constructing a sanitary sewage system in accordance with the details shown on the plans and these special provisions.

Sanitary sewage system shall include other fittings and appurtenances, not mentioned, which are required for the complete installation and proper operation of the system.

Related Work: Sewer pipes in buildings and to a point 5 feet beyond the building shall be as specified in Section 12-15, "Mechanical," of these special provisions.

Order of Work: Work which will curtail the use of the existing sewage system shall not be done until the facilities utilizing the system are closed and are no longer required.

SUBMITTALS

Product data:

Materials list for materials to be used shall be submitted for approval and shall include the name of the manufacturer and the source, model number, description, and standard of manufacture.

Manufacturer's descriptive data and catalog cuts shall be submitted for the following:

- Underground tracer tape
- Sewer pipe and fittings
- Sewer pipe adapters
- Drain pipe and fittings
- Manhole
- Manhole frame and cover
- Coatings
- Valve box and cover
- Meter box
- Cleanouts to grades
- Bituminous coating

QUALITY ASSURANCE

Codes and Standards: All sanitary sewage work shall conform to the applicable portions of the California Plumbing Code (CPC).

Certificates of Compliance: Certificates of compliance shall be furnished for manhole covers and frames in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

PART 2. - PRODUCTS

IDENTIFICATION

Underground Tracer Tape: Underground tracer tape shall be permanent, detectable, bright colored, continuous printed plastic tape intended for direct burial service; not less than 2 inches wide; lettering shall read "CAUTION SEWER BURIED BELOW".

PIPES AND FITTINGS

The Contractor shall install pipes and fittings from the following materials, of the weight and class with the joining method as indicated.

Sewer and Drain Pipe: Sewer and drain pipe and fittings shall be polyvinyl chloride (PVC) gravity sewer plastic pipe and fittings conforming to ASTM Designation: D 3034, Standard Dimension Ratio (SDR) 35, with integral bell and bell and spigot rubber gasketed joints or conforming to ASTM Designation: D2665 with solvent welded fittings. Rubber gaskets shall conform to ASTM Designation: F 477. Stainless steel clamps with rubber boots shall not be used.

Sewer Pipe Adapters: Sewer pipe adapters for PVC to cast iron soil pipe or clay piping shall be appropriately sized PVC flexible coupling manufactured for connecting dissimilar pipes. Adapters shall be attached to piping with adjustable stainless steel band clamps with hex tightening screws. Rubber boots will not be allowed. Sewer pipe adapter shall be Indiana Seal; Fernco; or equal.

SEWER MANHOLES

Manhole: Manhole and distribution box riser sections and cones shall be precast, reinforced concrete, conforming to ASTM Designation: C 478, or precast reinforced concrete pipe conforming to ASTM Designation: C 76.

Manhole Frame and Cover: Manhole frame and cover shall be gray cast iron, conforming to ASTM Designation: A 48, Class 30 or greater (traffic type). Cover shall be no bolt, closed pick hole and shall be marked "SS," "SEWER," or "SANITARY SEWER". The side or bottom of the cover shall be machined grooved for an integral O-ring gasket. The frame seat for the bottom O-ring gasket shall be a minimum of 22 mm in width.

VALVE AND METER BOXES

Valve Box: Valve box shall be precast concrete box with cast iron cover. Cover shall be factory marked "SEWER," "SS," or "SANITARY SEWER" and shall be traffic rated. Valve box shall be Cook Concrete Products, No. 10-T-12; Christy No. G-5C; Brooks, No. 3-RT; or equal with extensions as required.

Meter Box: Meter box shall be precast concrete with cast iron cover. Cover shall be factory marked "SEWER," "SS," or "SANITARY SEWER" and shall be traffic rated. Meter box shall be Bes, No. C9W with C15 cover; Christy, No. B9 with B9C cover; Cook Concrete Products, No. 14 with 14-T cover; or equal.

CLEANOUTS AND VALVES

Cleanout to Grade: Cleanout piping shall terminate with an appropriately sized flexible PVC access cap and stainless steel band coupler with hex tightening screw. Rubber coupling or cap will not be allowed. Access cap shall be Indiana Seal; Fernco; or equal.

COATINGS

Bituminous Coating: Bituminous coating shall conform to ASTM Designations: D 41 and D 449.

MISCELLANEOUS MATERIALS

Cement Mortar: Cement mortar shall be one part cement to 2 to 3 parts clean plaster or concrete sand mixed with just enough water for suitable consistency.

Epoxy Mortar: Epoxy mortar shall be a commercial quality, trowelable, 3-component epoxy mortar consisting of 2 pourable epoxy components and a chemically resistant aggregate filler of silica quartz sand with a maximum water absorption of 0.1 percent. Epoxy shall have a pull-off strength of not less than 70.323 kg/cm and a 90 percent cure in 24 hours. Epoxy mortar shall be the type that requires no primer as a bonding agent.

PART 3. - EXECUTION

INSTALLATION OF IDENTIFICATION

Continuous underground tracer tape shall be installed directly above buried lines and 152 mm to 305 mm below finished grade during backfilling operations.

INSTALLATION OF PIPES AND FITTINGS

Sewer and drain pipe shall be installed upgrade (starting from utility connection back to the construction) unless otherwise permitted by the Engineer.

Closing Abandoned Utilities: Open ends of abandoned underground utilities shall be closed. Sufficiently strong closures, either 152 mm of concrete or pipe cap with concrete thrust block, shall be placed to withstand hydro-static pressure which may result after the pipes are closed.

Sewers Near Eater Lines: Sewers near water lines shall be installed below water lines in the same trench, in parallel trenches less than 3050 mm apart, or at any crossing.

When water lines cross above a sewer line, a vertical separation of not less than 305 mm shall be maintained between the top of the sewer pipe and the bottom of the water line.

Connections between Differing Pipe Types: Joints between different types of pipes shall be made with sewer pipe adapters intended for that purpose.

Damaged Pipe: Damaged pipe shall be replaced prior to use. Misaligned pipe shall be corrected or replaced prior to use.

Cleaning Pipe: Interior of pipes shall be cleaned of dirt and other materials as the work progresses.

Lines between manholes shall be flushed as necessary to remove collected material.

Interior Inspection: Interiors of pipes shall be inspected to determine displacement or damage during installation or backfilling.

INSTALLATION OF MANHOLES AND VALVE AND METER BOXES

Manholes and valve and meter boxes shall be installed in accordance with their manufacturer's recommendations.

All joints and penetrations of manholes and valve and meter boxes shall be sealed watertight, inside and outside, with epoxy mortar.

A concrete collar shall be formed and cast in place around each manhole in accordance with the details shown on the plans.

Where new manholes, valve or meter boxes are to be installed to grade in areas to be paved or surfaced, no individual structure shall be constructed to final grade until the paving or surfacing has been completed in the immediate area.

INSTALLATION OF CLEANOUTS

Cleanouts shall be installed 90 degrees to finished grade and shall terminate in a valve box. A concrete pad shall be provided full width of the trench under a wye branch.

Cleanouts to grade shall be a combination of fittings as shown on the plans. Piping and fittings for 102 mm pipe shall be sewer pipe. Piping and fittings for 76 mm pipe and smaller shall be drain pipe.

Collars shall be broom surface finished. Collars shall match existing/finished grade. Compaction prior to form work shall be as specified elsewhere in these special provisions.

APPLICATION OF COATINGS

The interior and exterior surfaces of concrete sewer structures, except the bottom of tanks, shall be completely coated with 2 applications of bituminous coating, applied at a rate of 2.5 square meters per liter.

Concrete surfaces to be coated shall not be coated until 28 days after the last concrete for these structures has been poured.

The edge and bottom of manhole cover seat areas shall be coated with a uniform application of heavy duty, waterproof automotive or industrial grease.

FIELD QUALITY CONTROL

Testing Pipes:

All sewer and drain pipes shall be tested for obstructions before covering the pipes by balling and flushing the pipes with an approved commercial sewer cleaning ball. The ball shall be moved slowly through the sewer with a tag line. 102 mm sewer pipe shall be tested by pulling an appropriate sized inflatable plug through the pipe. Obstructions or irregularities shall be removed or repaired.

Sewer and drain pipes shall be tested for leakage for a minimum period of 4 hours by filling with water to an elevation of 1220 mm above the average invert of sewer pipe, or to the top of the manholes where less than 1220 mm deep. The system shall show no visible leaks, and the leakage rate shall not exceed the rate allowed by the local agency. In the absence of such requirements, leakage shall not exceed one pint per 24 hours, per millimeter diameter, per 30480 mm of pipe. Sewer pipes may be tested in sections with the test water progressively passed down the sewers if feasible. Water shall be released at a rate which will not create water hammer or surge in the plugged section of sewer.

In lieu of hydrostatic test with water, the air test method, "Air Test," as outlined in the CPC, may be used.

12-2.12 GUARD POSTS

PART 1.- GENERAL

Scope.--This work shall consist of constructing guard posts in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Steel posts.--

Steel posts for guard posts shall be standard weight, galvanized steel.

Concrete.--

Concrete for guard posts shall be commercial quality concrete, proportioned to provide a workable mix suitable for the intended use, with not less than 300 kilograms of cement per cubic meter.

PART 3.- EXECUTION

Installation.--

Guard posts shall be placed in holes and shall be installed plumb.
Guard posts shall be backfilled with concrete.

Painting.--Guard posts shall be prepared and painted in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

12-2.13 PARKING BUMPERS

PART 1.- GENERAL

Scope.--This work shall consist of furnishing and installing precast concrete parking bumpers in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Parking bumpers.--

Parking bumpers shall be commercially available precast parking bumpers.

Parking bumpers shall be nominal 1220 mm long, 200 mm wide and 150 mm high with both top longitudinal corners continuously chamfered, and anchor holes 230 mm from each end.

PART 3.- EXECUTION

Layout.--Arrangement of parking bumpers shall be coordinated with the layout of parking stalls and traffic aisles, providing the proper angle to engage wheels and located to prevent overtravel of vehicles.

Parking bumpers shall be anchored with two 19 mm diameter reinforcing bars 380 mm in length. The reinforcing bars shall be installed such that the top of the bars is flush with the top of the parking bumper.

12-2.14 ACCESSIBLE PARKING AND AUTHORIZATION SIGNS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing accessible parking and authorization signs in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and sign fastening details shall be submitted for approval.

PART 2.- PRODUCTS

Accessible parking stall identification sign.--

Accessible parking stall identification sign shall be a metal sign with baked enamel finish and the international symbol of accessibility. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Symbol, lettering and border shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Van accessible sign.--

Van accessible sign shall be a metal sign with baked enamel finish and the international symbol of accessibility. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Lettering and border shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Unauthorized vehicles parking sign.--

Unauthorized vehicles parking sign shall be a metal sign with baked enamel finish. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Lettering and border shall be white and shall conform to Federal Standard 595B, Color No. 17886. Lettering shall be not less than 25 mm in height and shall read as shown on the plans.

Support post.--

Support post shall be commercial quality, standard weight, galvanized steel pipe. Pipe diameter shall be 35 mm.

Fastening hardware.--

Fastening hardware shall be galvanized or cadmium plated.

Concrete.--

Concrete for support posts shall be commercial quality concrete, proportioned to provide a workable mix suitable for the intended use, with not less than 300 kilograms of cement per cubic meter.

PART 3.- EXECUTION

Installation.--Support posts shall be placed in holes excavated to the depth and cross-section shown on the plans. Posts shall be set vertical and shall be firmly embedded in concrete backfill. The top of the concrete backfill around the post shall be crowned to drain water.

Support posts shall be fitted with a rainproof top.

Sign shall be fastened rigidly and securely to the support post.

The Engineer will provide the Contractor with the necessary information for the disabled authorization sign.

SECTION 12-3. CONCRETE AND REINFORCEMENT

12-3.01 CAST-IN-PLACE CONCRETE

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of constructing cast-in-place concrete facilities in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for admixtures, expansion joint material, vapor barrier, hardener, and sealer shall be submitted for approval.

Descriptive data shall be delivered to the Engineer at the jobsite.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of Compliance shall be furnished for cement, reinforcement, , and admixtures in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

A Certificate of Compliance shall be furnished for each shipment of epoxy-coated reinforcing bars certifying that the coated bars conform to the requirements of ASTM Designation: D 3963. Said Certificate of Compliance shall include all certifications specified in ASTM Designation: D 3963 and a statement that the coating material has been prequalified by acceptance testing performed by the National Bureau of Standards or by the Valley Forge Laboratories, Inc., Devon, Pennsylvania.

Samples.--Prior to coating, the Contractor shall furnish to the Engineer a representative 0.11 kg sample from each batch of epoxy coating material used. The sample shall be packaged in an airtight container identified with the manufacturer's name and batch number.

After coating, two 800 mm long samples of epoxy-coated reinforcing steel from each size and from each load shipped to the jobsite shall be submitted to the Engineer. The samples shall be representative of the material furnished. The samples, as well as any additional random samples taken by the Engineer, may be tested for specification compliance. Such additional sampling, and all tests performed by the Engineer, may be performed at any location deemed appropriate by the Engineer. Failure of any sample to meet the requirements of the specification will be cause for rejection of all reinforcing bars represented by the sample.

PART 2.- PRODUCTS

CONCRETE MIXES.--

Concrete (structural work).--

Commercial quality concrete shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 350 kg/m³ of cement; 0 to 50 mm penetration, inclusive, as determined by California Test 533.

The air content of the freshly mixed concrete shall be $6 \pm 1 \frac{1}{2}$ percent, as determined by California Test 504.

Concrete (minor work).--

Commercial quality concrete for thrust blocks and collars shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 300 kg/m³ of cement; 0 to 50 mm penetration, inclusive, as determined by California Test 533.

The air content of the freshly mixed concrete shall be $6 \pm 1 \frac{1}{2}$ percent, as determined by California Test 504.

CONCRETE MATERIALS.--

Cement.--

Cement shall conform to ASTM Designation: C 150, Types II, or III portland cement; or Type IP (MS) Modified cement. Type IP (MS) Modified shall conform to ASTM Designation: C 595 and shall be comprised of an intimate mixture of Type II Modified cement and not more than 20 percent of a pozzolanic material.

Aggregates.--

Aggregates shall be free from deleterious coatings, clay balls and other extraneous materials.

Aggregates proposed for use shall conform to the requirements for freezing and thawing shall as determined by California Test 528.

A list of sources of aggregates which have previously passed the freeze-thaw test is available in the District Office at 1657 Riverside Drive, Redding, CA 96001.

Admixtures.--

Admixtures used in portland cement concrete shall be included on the Department's current list of approved admixtures, and shall conform to ASTM Designation: C 494, Types A, B, D, F or G for chemical admixtures; ASTM Designation: C 260 for air-entraining admixtures; and ASTM Designation: C 618 for mineral admixtures, except loss on ignition shall not exceed 4 percent. Properties of admixtures shall be uniform in each lot.

FORM MATERIALS.--

Forms for exposed finish concrete.--

Forms for exposed surfaces shall be plywood, metal or other panel type materials. Plywood shall be not less than 16 mm thick and without scars, dents, and delaminations. Forms shall be furnished in largest practical pieces to minimize number of joints.

Plywood shall conform to the requirements of U. S. Product Standard PS-1 for Exterior B-B (Concrete Form) Class I.

Forms for edges of slabs shall be nominal 50 mm solid stock lumber, plywood, or metal forms.

Forms for unexposed finish concrete.--

Forms for unexposed finish concrete surfaces shall be plywood, lumber, metal or other acceptable material.

Forms for cylindrical columns or supports.--

Forms for cylindrical columns shall be metal, fiberglass reinforced plastic, paper or fiber tubes. Paper or fiber tubes shall be constructed of laminated plies using water-resistant adhesive with wax-impregnated exterior for protection against weather or moisture.

Form ties.--

Form ties shall be factory fabricated, removable or snapoff metal ties for use as necessary to prevent spreading of forms during concrete placement.

Form oil.--

Form oil shall be commercial quality form oil which will permit the ready release of the forms and will not discolor the concrete.

REINFORCING MATERIALS.--

Bar reinforcement.--

Bar reinforcement shall conform to ASTM Designation: A 615/A 615M, Grade 60 [420], or ASTM Designation: A 706/A 706M.

Epoxy coated reinforcement.--

The reinforcing steel to be coated shall conform to ASTM Designation: A 615/A 615M, Grade 60 [420], or A 706/A 706M. Epoxy-coated reinforcement shall conform to ASTM Designation: D 775, except that the thickness of the coating shall be 0.2 mm plus or minus 0.05 mm. The coating shall have a light pastel color.

Bar supports.--

Bar supports for reinforcement shall be precast mortar blocks or ferrous metal chairs, spacers, metal hangers, supporting wires, and other approved devices of sufficient strength to resist crushing under applied loads.

RELATED MATERIALS.--

Anchor bolts, nuts, and washers.--

Nonheaded anchor bolts shall conform to ASTM Designation: A 36/A 36M, with a minimum hook length of 6.2 diameters.

Headed anchor bolts shall conform to ASTM Designation: A 307.

Threaded rods shall conform to ASTM Designation: A 572.

Nuts shall conform to ASTM Designation: A 563M, Grade A.

Washers for anchor bolts shall be commercial quality.
Exposed anchor bolts, nuts, and washers shall be hot dipped galvanized.

Expansion joint material.--

Expansion joint material shall be commercial quality asphalt impregnated pressed fiber sheets, 13 mm minimum thickness.

Vapor barrier.--

Vapor barrier shall be commercial quality polyethylene sheets not less than 0.15 mm thick.

Type A control joints.--

Type A control joints shall be commercial quality, preformed, T-shaped plastic strips with detachable top flange.

Keyed construction joint forms.--

Keyed construction joint forms shall be commercial quality, galvanized metal or plastic, factory fabricated construction joint forms. Forms shall produce a rabbeted key type joint.

Mortar.--

Mortar shall consist of one part cement to 2 parts clean sand and only enough water to permit placing and packing.

Curing compound.--

Curing compound shall be a non-pigmented curing compound with fugitive dye conforming to the requirements of ASTM Designation: C 309, Type 1-D, Class A.

Concrete hardener.--

Concrete hardener shall be commercial quality water borne penetrating type magnesium fluosilicate, zinc fluosilicate or combination thereof.

Concrete sealer.--

Concrete sealer shall be commercial quality VOC-compliant, silane type sealer with hydrophobic and oleophobic properties.

ADMIXTURES.--

General.--Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option to conserve cement or to facilitate any construction operation.

Calcium chloride shall not be used in any concrete.

Admixtures shall be combined with concrete materials by methods that produce uniform properties throughout the concrete.

If more than one admixture is used, said admixtures shall be compatible with each other so that the desirable effects of all admixtures will be realized.

Mineral admixtures may be used to replace up to 15 percent of Type II portland cement provided the weight of mineral admixture used is not less than the weight of cement replaced. Mineral admixtures shall not be used to replace Type IP (MS) Modified or Type III cements. Chemical admixtures may be used to reduce up to 5 percent of the portland cement except that the cement content shall not be less than 300 kg/m³. When both chemical and mineral admixtures are used with Type II cement, the weight of cement replaced by mineral admixture may be considered as cement in determining the resulting cement content.

Mineral admixtures will be required in the manufacture of concrete containing aggregates that are determined to be "deleterious" or "potentially deleterious" when tested in accordance with ASTM Designation: C 289. The use of mineral admixture in such concrete shall conform to the requirements in this section except that the use of set retarding admixtures will not be permitted.

When the use of a chemical admixture is specified or is ordered by the Engineer, the admixture shall be used at the rate specified or ordered. If no rate is specified or ordered, or if the Contractor uses a chemical admixture for his own convenience, the admixture shall be used at the dosage normally recommended by the admixture manufacturer.

When air-entrainment is specified or is ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce concrete having the specified or ordered air content as determined by California Test 504. If the Contractor uses air-entrainment for his own convenience, the average air content shall not exceed 4 percent and no single test shall exceed 5 1/2 percent.

Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers shall have sufficient capacity to measure at one time the total quantity required for each batch. If more than one liquid admixture is used in the concrete, a separate measuring unit shall be provided for each liquid admixture and dispensing shall be such that the admixtures are not mixed at high concentrations. When air-entraining admixtures are used with other liquid admixtures, the air-entraining admixtures shall be the first to be incorporated into the mix. Unless liquid admixtures are added to premeasured water for the batch, they shall be discharged to flow into the stream of water so that the admixtures are well dispersed throughout the batch.

BAR REINFORCING STEEL.--

Bending.--Reinforcing steel bars shall accurately conform to the dimensions shown on the plans.

Bars shall be bent or straightened in a manner that will not crack or break the material. Bars with kinks or improper bends shall not be used.

Hooks, bends and splices shall conform to the provisions of the Building Code Requirements for Reinforced Concrete of the American Concrete Institute.

Epoxy-coated Reinforcing Steel.--In fabricating, handling, shipping, and placing of epoxy-coated reinforcing bars, adequate care shall be taken to avoid damage to the coating. Handling and shipping equipment shall have padded contact areas. All bundling bands shall be padded or suitable banding shall be used to prevent damage to the coating. All bundles of coated bars shall be lifted with a strongback or multiple support system to prevent bar-to-bar abrasion from sags in the bundles. Bars or bundles shall not be dropped or dragged.

All damage to the coating caused by handling and fabrication prior to shipment to the jobsite shall be repaired as required by ASTM Designation: D 775. Damage to the coating occurring during shipment or installation, or both, need not be repaired where the damaged areas are 6 mm by 6 mm or smaller and the sum of all damaged areas in each 300 mm length of bar does not exceed 2 percent of the bar surface area. All bars with total damage greater than 2 percent of the bar surface area will be rejected and shall be removed. On bars with a total damaged coating area not exceeding 2 percent of the bar surface area, all damaged areas larger than 6 mm square and all damage in sections of bar with more than 2 percent coating damage in a 300 mm length shall be repaired with patching material. The bar surface area covered by patching material shall not exceed 5 percent of the total surface area of the bar.

Patching material shall be compatible with the coating material, not harmfully reactive with the concrete, and shall be feasible for repairs by the coating applicator or bar fabricator or in the field. The patching material shall be prequalified as required for the coating material and shall be either identified on the container as meeting the requirements of Annex A1 of ASTM Designation: D 775 or shall be accompanied by a Certificate of Compliance certifying that the material meets the requirements of said Annex A1. Patching of damaged areas shall be performed in accordance with the patching material manufacturer's recommendations.

MIXING AND TRANSPORTING CONCRETE.--

General.--When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be complete within 1 1/2 hours, or before 250 revolutions of the drum or blades, whichever comes first, after the introduction of cement to the aggregates.

The temperature of mixed concrete, immediately before placing, shall be not less than 10°C nor more than 32°C.

Truck mixers or agitator shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified. The counters shall be of the continuous-registering type, which accurately register the number of revolutions and shall be mounted on the truck so that the Engineer may safely and conveniently inspect them from alongside the truck. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, a time less than 1 1/2 hours may be required.

When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be complete within one hour after the introduction of cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C, or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

Each load of concrete for the work shall be accompanied by a trip ticket, a copy of which shall be delivered to the Engineer at the jobsite. The trip ticket shall show volume of concrete, weight of cement and aggregates, quantity of each admixture, quantity of water including water added at the jobsite, time of day the concrete is batched, and revolution counter readings on transit mix trucks at the times the truck is charged and unloaded.

PART 3.- EXECUTION

PREPARATION.--

Existing concrete construction.--Where fresh concrete joins existing or previously placed concrete or masonry, the contact surfaces of the existing or previously placed material shall be roughened, cleaned, flushed with water and allowed to dry to a surface dry condition immediately prior to placing the fresh concrete. The roughened surface shall be no smoother than a wood trowelled surface. Cleaning of the contact surfaces shall remove laitance, curing compounds, debris, dirt and such other substances or materials which would prevent bonding of the fresh concrete.

Abrasive blast methods shall be used to clean horizontal construction joints to the extent that clean aggregate is exposed.

Exposed reinforcing steel located at the contact surfaces which is to be encased in the fresh concrete shall be cleaned to remove any substance or material that would prevent bonding of the fresh concrete.

Forms.--Forms shall be mortar tight, true to the dimensions, lines, and grades shown on the plans, securely fastened and supported, and of adequate rigidity to prevent distortion during placing of concrete.

Forms for exposed surfaces shall be constructed with triangular fillets not less than 19 mm x 19 mm attached so as to prevent mortar runs and to produce smooth straight chamfers at all sharp edges of the concrete.

Form fasteners shall be removable without chipping, spalling, heating or otherwise damaging the concrete surface. Form ties shall be removed to a depth of at least 25 mm below the surface of the concrete.

The inside surfaces of forms shall be cleaned of all dirt, mortar and foreign material. Forms shall be thoroughly coated with form oil prior to use.

Forms shall not be stripped until at least 40 hours after placing concrete, except soffit forms and supports shall not be released or removed until at least 10 days after placing concrete.

Anchorage and embedded items shall be placed and rigidly secured at their planned locations prior to placing concrete.

Reglets or embedded flashing shall be installed on concrete forms before the concrete is placed.

Vapor barrier.--Vapor barrier shall be lapped 150 mm and securely taped at splices. Vapor barrier shall be protected with a 75 mm layer of clean uncompacted sand cover.

Unless otherwise shown on the plans, vapor barrier shall be placed under portions of the floor slab scheduled to receive finish flooring.

Placing reinforcing steel.--Reinforcing steel bars shall be accurately placed to the dimensions shown on the plans.

Bar reinforcement conforming to ASTM Designation: A 615/A 615M, Grade 60 [420], or A 706//A 706M shall be lapped at least 45 diameters.

Bars shall be firmly and securely held in position by means of wiring and approved bar supports. The spacing of supports and ties shall prevent displacement of the reinforcing or crushing of supports.

Tie wire shall be clear of concrete formwork and concrete surfaces.

All reinforcing steel shall be in place and inspected before concrete placement begins. Placing of bars on fresh layers of concrete will not be permitted.

Within areas where epoxy-coated reinforcement is required, tie wire and bar chairs or other metallic devices used to secure or support the reinforcement shall be plastic-coated or epoxy-coated to prevent corrosion of the devices or damage to the coated reinforcement.

Ground bar.--A continuous reinforcing steel bar shall be installed in the building foundation at the location indicated on the plans for the electrical ground bar. The use of epoxy coated reinforcing bar is not permitted. The end of the ground bar shall extend beyond the concrete surface and shall be protected from damage by construction operations.

PLACING CONCRETE.--

General.--Concrete shall be placed and consolidated by means of internal vibrators to form dense, homogeneous concrete free of voids and rock pockets.

Forms and subgrade shall be thoroughly moistened with water immediately before placing concrete.

Concrete shall be placed as nearly as possible to its final location and the use of vibrators for extensive shifting of the concrete will not be permitted.

Concrete shall be deposited and consolidated in a continuous operation within limits of construction joints, until the placing of the panel or section is completed.

When concrete is to be placed in large areas requiring more than two pours, concrete shall be placed in alternate long strips between construction joints and the final slab infilled.

FINISHING CONCRETE SURFACES.--

Finishing unformed surfaces.--Slabs shall be placed full thickness to finish elevation and leveled to screeds by use of long straightedges. The screeds shall be set to grade at approximately 1.8 meter centers. After leveling, screeds shall be removed and the surface shall be floated with wooden floats.

Type A control joint strips shall be inserted into the floated concrete so that the bottom of the top flange is flush with the finish elevation. Strips shall be standard manufactured lengths and shall be placed on an approximate straight line. The top flange of the strips shall be removed after the concrete has set and cured.

The floated surface shall be trowelled with steel trowels. Troweling shall form a dense, smooth and true finish. Walkways, pedestrian ramps, stairs and outdoor slabs for pedestrian traffic shall be given a non-slip broom finish unless a different finish is called for on the plans or in these special provisions.

The application of cement dust coat will not be permitted.

Concrete floor surfaces to receive ceramic tile shall be floated to grade and then, before final set of the concrete, the floated surfaces shall be roughened with stiff bristled brushes or rakes.

Finished surfaces of floor slabs shall not deviate more than 3 mm from the lower edge of a 3-meter long straight edge.

Finishing formed surfaces.--Formed concrete surfaces shall be finished by filling holes or depressions in the surface, repairing all rock pockets, and removing fins. All surfaces of formed concrete exposed to view shall have stains and discolorations removed, unsightly bulges removed, and all areas which do not exhibit the required smooth, even surface of uniform texture and appearance shall be sanded with power sanders or other approved abrasive means until smooth, even surfaces of uniform texture and appearance are obtained.

Cement mortar, patching and finishing materials used to finish exposed surfaces of concrete shall closely match the color of surrounding surfaces.

CURING CONCRETE.--

General.--Freshly placed concrete shall be protected from premature drying and excessive cold or hot temperatures.

Initial curing of floor slabs shall start as soon as free water has disappeared from the concrete surface. The concrete shall be kept continuously wet by application of water for not less than 7 days after the concrete has been placed.

Cotton mats, rugs, carpets, or sand blankets may be used as a curing medium to retain the moisture during the curing period. Curing materials that will stain or discolor concrete shall not be used on surfaces exposed to view.

Prior to placing the curing medium, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing mediums.

Concrete surfaces, other than floor slabs, shall be kept moist for a period of at least 5 days by leaving the forms in place or by covering the exposed surfaces using moist rugs, cotton mats or other curing materials approved by the Engineer.

Concrete thrust blocks, collars may be cured with a curing compound.

PROTECTING CONCRETE.--

General.--Concrete shall not be placed on frozen or frost covered surfaces.

Concrete shall be protected from damage due to rain, freezing or inclement weather, and shall be maintained at a temperature of not less than 4°C for 72 hours. When required by the Engineer, the Contractor shall provide a written outline of his proposed methods of protecting concrete.

Vehicles, equipment, or concentrated loads weighing more than 140 kg individually and material stockpiles weighing more than 240 kg/m² will not be permitted on the concrete within 10 calendar days after placing.

SPECIAL TREATMENTS.--

Concrete hardener.--Chemical concrete hardener shall be applied to the floor surfaces shown on the plans, prior to the application of concrete sealer. Surfaces shall be clean and dry before the application of hardener.

The solution shall be applied in accordance with the manufacturer's instructions.

After the hardener has dried, the surface shall be mopped with water to remove encrusted salts.

Concrete sealer.--Concrete sealer shall be applied to the concrete surfaces designated on the plans in accordance with the manufacturer's instructions for heavy duty use. The sealer shall be applied to dry concrete surfaces.

SECTION 12-4. MASONRY

12-4.01 CONCRETE MASONRY UNITS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of constructing reinforced hollow concrete masonry units in accordance with the details shown on the plans and these special provisions.

Related work.--Water repellent coating shall be applied in accordance with the requirements specified under "Water Repellent Coating" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

PERFORMANCE REQUIREMENTS.--

Unit Strength.--Provide masonry units that develop the following installed compressive strengths (f_m) at 28 days:

Based on net area $f_m = 10.34 \text{ MPa}$

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for each type of masonry unit, accessory, and other manufactured products shall be submitted for approval.

Samples.--Two samples 204 mm x 204 mm of masonry units of each color and architectural finish shall be submitted for approval.

QUALITY ASSURANCE.--

Masonry preconstruction testing service.--The Contractor shall employ and pay all costs for the services of a testing laboratory acceptable to the Engineer and experienced in performing preconstruction masonry tests. The testing laboratory shall comply with the requirements of ASTM Designation: E 329.

Preconstruction tests shall be performed on the following materials by the Unit Strength Method as defined by Section 2105, "Quality Assurance," of the CBC:

Concrete masonry units shall be tested in accordance with ASTM Designation: C 140.

Grout shall be tested in accordance with ASTM Designation: C 1019.

In addition:

Mortar shall be tested in accordance with UBC Standard: 21-16.

Test results shall be reported in writing to the Engineer and the Contractor on the same day the tests are made.

Single source responsibility.--Exposed masonry units of uniform color and texture shall be obtained from one manufacturer for each different product required for each continuous surface or visually related surfaces.

Mortar ingredients of uniform quality, including color for exposed masonry, shall be obtained from one manufacturer for each cementitious component and from one source and producer for each aggregate.

Certificates of Compliance.--Certificate of Compliance shall be furnished for masonry units, aggregate for grout and transit mixed grout in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

DELIVERY, HANDLING AND STORAGE.--

Delivery.--Masonry materials shall be delivered to the project in an undamaged condition.

Storage and handling.--Masonry units shall be stored and handled in order to prevent deterioration or damage due to moisture, temperature changes, contamination, corrosion or other causes.

PART 2.- PRODUCTS

CONCRETE MASONRY UNITS.--

Concrete masonry units.--

Concrete masonry units shall be nominal size, color and architectural finish as shown on plans; hollow load bearing, light weight or medium weight, Grade N, Type II, conforming to ASTM Designation: C 90; standard or open ended masonry units.

Special shapes shall be provided where required for lintels, corners, jambs, sash, control joints, headers, bonding and other special conditions.

MORTAR AND GROUT MATERIALS.--

Cement.--

Cement for mortar shall be Type II, low alkali portland cement conforming to ASTM Designation: C 150; or masonry cement conforming to ASTM Designation: C 91.

Cement for grout shall be Type II portland cement conforming to ASTM Designation: C 150 with maximum 15 percent Class N, F, or C mineral admixture conforming to ASTM Designation: C 618 except that the loss on ignition shall not exceed 4 percent; or Type IP(MS) blended hydraulic cement conforming to ASTM Designation: C 595.

Aggregate.--

Aggregate for mortar shall conform to ASTM Designation: C 144, except not more than 10 percent shall pass the No. 100 sieve.

Aggregate for grout shall conform to ASTM Designation: C 404, except 100 percent of the coarse aggregate shall pass the 9.5 mm sieve. Soundness loss shall not exceed 10 percent as determined by California Test 214.

Coloring for mortar.--

Coloring for mortar shall be chemically inert, fade resistant mineral oxide or synthetic type.

Lime.--

Lime shall conform to ASTM Designation: C 207, Type S.

Premixed mortar or grout.--

A premixed packaged blend of cement, lime, and sand, with or without color, that requires only water to prepare for use as masonry mortar or grout may be furnished. Packages of premix shall bear the manufacturer's name, brand, contents, weight, and color identification.

Transit mixed grout.--

Transit mixed grout shall conform to ASTM Designation: C 94, except aggregate shall be as specified herein for aggregate for grout. The minimum compressive strength shall be 17236 kPa at 28 days when tested in accordance with ASTM Designation: C 39. Admixtures, if used, shall conform to ASTM Designation: C 494, Types A, E or F and shall not contain chlorides.

REINFORCEMENT, TIES AND ANCHORING DEVICES.--

Bar reinforcement.--

Bar reinforcement shall conform to ASTM Designation: A 615/A 615 M, Grade 60 [420], or ASTM Designation: A 706/A 706 M.

Anchor bolts.--

Anchor bolts shall conform to ASTM Designation: A 36/A 6M with a minimum hook length of 6.2 diameters, and shall be 12 mm diameter unless otherwise shown on the plans.

Anchors, ties, angles, and metal lath.--

Anchors, ties, angles, and metal lath shall be commercial quality, and shall be galvanized.

Dry pack.--

Dry pack to set items into masonry shall be one part portland cement to not over 3 parts of clean sand and with a minimum amount of water for hydration and packing.

PROPORTIONING MORTAR AND GROUT.--

General.--Mortar shall be proportioned by loose volume and shall have one part cement, one quarter part of hydrated lime and 2 1/4 to 3 parts aggregate. Mortar shall be tinted with coloring to match the masonry units.

Grout, except transit mixed and packaged premix grout, shall be proportioned by loose volume and shall have one part cement, not more than 1/10 part hydrated lime, 2 1/4 to 3 parts sand aggregate, and not more than 2 parts gravel aggregate.

Aggregate shall be measured in a damp loose condition.

Grout shall be mixed with sufficient water to produce a mix consistency suitable for pumping without segregation. Slump shall not exceed 229 mm.

PART 3.- EXECUTION

CONSTRUCTION.--

General.--Masonry units shall be laid in running bond, except as otherwise shown on the plans.

Surfaces of metal, glass, wood, completed masonry, and other such materials exposed to view shall be protected from spillage, splatters and other deposits of cementitious materials from masonry construction. All such deposits shall be removed without damage to the materials or exposed surfaces.

Construction will comply with Section 2104, "Construction," of the CBC. Tolerances specified in Section 2104 shall be in affect unless otherwise shown on the plans.

Where fresh masonry joins concrete or masonry, the contact surfaces of existing material shall be roughened, cleaned and lightly wetted. The roughened surface shall be no smoother than a wood troweled surface. Cleaning shall remove laitance, curing compounds, debris, dirt and any substance which decreases bond to the fresh masonry.

Masonry shall not be erected when the ambient air temperature is below 5° C.

Surfaces of masonry erected when the ambient air temperature exceeds 38° C. shall be kept moist with water for a period of not less than 24 hours. Water shall be uniformly applied with a fog spray at the intervals required to keep the surfaces moist but not to exceed 3 hours unless otherwise approved by the Engineer.

All anchors, bolts, dowels, reglets and other miscellaneous items to be cast into the wall, shall be firmly secured in place before grout is poured.

Shoring for concrete masonry lintels shall remain in place a minimum of 15 days after the wall has been completed.

Laying masonry units.--Concrete masonry units shall be laid dry.

During laying of units all cells shall be kept dry in inclement weather by suitably covering incomplete walls. Wooden boards and planks shall not be used as covering materials. The covering shall extend down each side of masonry walls approximately 600 mm.

Chases shall be kept free from debris and mortar.

Bond beam units with an opening at each cross web shall be used at all horizontal reinforcing bars.

Where masonry unit cutting is necessary, all cuts shall be made with a masonry saw to neat and true lines. Blocks with excessive cracking or chipping of the finished surfaces exposed to view will not be acceptable.

Lintels.--Masonry lintels shall be as shown on the plans. Lintels shall be formed using U-shaped lintel units with reinforcing bars placed as shown on the plans. Formed-in-place lintels shall be temporarily supported.

Bar reinforcement.--Bar reinforcement shall be accurately positioned in the center of the cell and securely held in position with either wire ties or spacing devices near the ends of bars and at intervals not exceeding 192 bar diameters. Wire shall be 16-gage or heavier. Wooden, aluminum, or plastic spacing devices shall not be used. Tolerances for the placement of vertical reinforcement in walls and flexural elements shall be ± 12 mm. Tolerance for longitudinal reinforcement in walls shall be ± 50 mm.

The minimum spacing for splices in vertical reinforcement for masonry walls shall be 1220 mm plus lap.

Bar reinforcement shall not be placed in the plane of mortar joints.

Mortar.--Mortar joints shall be approximately 9.5 mm wide. Units shall be laid with all head and bed joints filled solidly with mortar for the full width of masonry unit shell. Head joints shall be shoved tight. Exposed joints shall be concave, tooled smooth, unless otherwise shown on the plans.

Mortar that has been mixed more than one hour shall not be retempered.

Mortar placed in joints shall preserve the unobstructed vertical continuity of the concrete filling. Any overhanging mortar projecting more than 12 mm, or other obstruction or debris shall be removed from the inside of such cells.

GROUTING.--

General.--All cells shall be filled solidly with grout. All grout in the cells shall be consolidated at the time of placement by vibrating and reconsolidated after excess moisture has been absorbed but before plasticity is lost. Slicing with a trowel is not acceptable.

Masonry units may be placed full height of the masonry work before grouting, or they may be placed in increments for individual grout pours.

Cleanouts shall be provided for all grout pours over 1524 mm in height. Such cleanouts shall be provided in the bottom course at every cell containing vertical reinforcement. After cell inspection, the cleanouts shall be sealed before filling with grout.

Masonry units shall be placed full height of the grout pour. Grout shall be placed in a continuous pour in grout lifts not exceeding 1828 mm. The interruption between placing successive lifts of grout shall be not more than one hour.

Between grout pours, a horizontal construction joint shall be formed by stopping the grout a minimum of 38 mm below the top of the last course, except if the joint is at a bond beam, it shall be 12 mm below the top of the bond beam unit, or at the top of the wall.

CLEANING AND PROTECTING MASONRY.--

General.--Splashes, stains or spots on the faces of the masonry exposed to view shall be removed.

Completed masonry shall be protected from freezing for a period of at least 5 days.

FIELD QUALITY CONTROL.--

General.--The Contractor shall employ, at his own expense, a special inspector and testing laboratory to perform structural tests and inspections of masonry to verify that the construction conforms to the CBC in accordance with the requirements in Section 1701, "Special Inspections," and Section 2105, "Quality Assurance," of the CBC. The Contractor shall submit a written Field Quality Control Plan that identifies the inspector, the lab, and the procedures used. The Field Quality Control Plan shall conform to these specifications and the CBC. The Contractor's Field Quality Control Plan shall be submitted to the Engineer for approval. The Engineer shall have three weeks to approve the plan.

The Contractor shall designate in the Field Quality Control Plan a masonry Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for the quality of masonry, including materials and workmanship, performed by the Contractor and all subcontractors.

The QCM shall be the sole individual responsible to the Contractor for submitting, receiving, and approving all correspondence, required submittals, and reports to and from the Engineer.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

Masonry special inspection personnel or testing firms to be used in the work shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project, except for the following conditions:

Special Inspector.--The special inspector shall be, as a minimum, an International Conference of Building Officials (ICBO) certified Special Masonry Inspector. The special masonry inspector shall perform the inspections required under Section 1701.5.7., "Structural masonry" of the CBC. The special inspector shall prepare a "Daily Field Report" providing information regarding the specific operations witnessed, including placing of masonry units and bar reinforcing, grouting, fabrication of test specimens, and other observations of importance to the work. A "Daily Field Report" is required for each day that the Special Inspector is on the jobsite. A copy of these reports shall be delivered to the Engineer on the day following the preparation. The special inspector shall submit a final signed report to the Engineer and Contractor stating whether the work requiring special inspection was, to the best of the inspector's knowledge, in conformance with the approved plans, specifications, and the applicable workmanship provisions of these specifications and the CBC.

Testing.--The testing laboratory shall comply with the requirements of ASTM Designation: E 329. Test results shall be reported in writing to the Engineer and the Contractor on the same day the tests are made. Testing shall be done in accordance with Section 2105.3,"Compliance with fm" of the CBC. The Contractor can establish fm by either Sections 2105.3.2, 2105.3.3, or 2105.3.4. A set of tests shall be done for each 465 m² of wall area, but not less than one test per project. Tests shall be performed on the following materials by the Unit Test Method as defined:

Concrete masonry units shall be tested in accordance with ASTM Designation: C 140.
Grout shall be tested in accordance with ASTM Designation: C 1019.
In addition:

Mortar shall be tested in accordance with UBC Standard: 21-16.

Any work not meeting the requirements of section 2105 shall be redone and retested. Sampling, inspecting, reworking and retesting of material will be done at the contractor's expense.

SECTION 12-5. METALS

12-5.01 STRUCTURAL STEEL FOR BUILDINGS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of fabricating, assembling, furnishing and erecting structural steel in accordance with the details shown on the plans and these special provisions.

Structural steel consists of:

Steel roof framing and columns, including connections for all structures.

Source quality control.--Materials and fabrication procedures are subject to inspection and tests in mill, shop and field, conducted by the Engineer or a qualified inspection agency. The Contractor or fabricator shall provide access to the Engineer or testing agency to places where the structural steel work is being fabricated or produced so that the required inspection and testing can be accomplished. Such inspections and tests will not relieve the Contractor of responsibility for providing materials and fabrication procedures in compliance with specified requirements. The testing agency may inspect the structural steel at the plant before shipment; however, the Engineer reserves the right, at any time before final acceptance to reject the material that does not conform to the contract requirements.

REFERENCES.--

General.--Structural steel shall be fabricated, assembled and erected in accordance with American Institute of Steel Construction (AISC), "Specifications for the Design, Fabrication and Erection of Structural Steel for Buildings."

Welding shall be in accordance with American Welding Society (AWS) D1.1, "Structural Welding Code - Steel."

SUBMITTALS.--

Product data.--Product data for items to be incorporated into the work, including structural steel, high strength bolts, nuts and washers and alternative connectors, shall be submitted for approval.

Working drawings.--Working drawings and calculations shall be submitted for approval.

Working drawings shall show any changes proposed in the work, details of connections and joints exposed to the weather, details for connections not dimensioned on the plans, the sequence of shop and field assembly and erection, welding sequences and procedures. If required, the location of butt welded splices on a layout drawing of the entire structure, and the location and details of any temporary supports that are to be used.

Calculations and working drawings for falsework to be used for the erection of structural steel shall be submitted for approval. The falsework shall be designed and constructed to provide the necessary rigidity and to support loads which will be applied. Working drawings and design calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California. The expiration date of the registration shall be shown.

CLOSEOUT SUBMITTALS.--

Final drawings.--At the completion of each building on the contract, one set of reduced prints on 27 kg (minimum) bond paper, 280 mm x 432 mm in size, of the corrected original tracings of all approved drawings for each building shall be furnished to the Engineer. An index prepared specifically for the drawings for each building containing sheet numbers and titles shall be included on the first reduced print in the set for each building. Reduced prints for each building shall be arranged in the order of drawing numbers shown in the index.

The edge of the corrected original tracing image shall be clearly visible and visually parallel with the edges of the page. A clear, legible symbol shall be provided on the upper left side of each page to show the amount of reduction and a horizontal and vertical scale shall be provided on each reduced print to facilitate enlargement to original scale.

QUALITY ASSURANCE.--

Qualifications for welding.--A certified copy of qualification test record for welders shall be submitted to the Engineer at the jobsite. Descriptive data for equipment for field welding structural steel, including type and electric power requirements, shall be submitted for approval.

Certificates of Compliance.--Certificate of Compliance shall be furnished for structural steel products in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. Certificate of Compliance shall include mill test certificates for each heat number used in the work.

DELIVERY, HANDLING AND STORAGE.--

Structural materials shall be loaded, transported, unloaded and stored so that it is kept clean and undamaged. Material shall be stored above ground on platforms, skids, or other supports. Covers and protection shall be provided to protect the materials from corrosion.

Anchorage and anchor bolts, which are to be embedded in concrete or masonry, shall be delivered in ample time to not delay the work.

PART 2.- PRODUCTS

MATERIALS.--

Steel bars, plates and shapes.--

Steel beams shall conform to ASTM Designation: A 992 or A 572 Grade 50. Channels shall conform to ASTM Designation: A 572/A 572M, Grade 50 [345].

Steel bars, plates and angles shall conform to ASTM Designation: A 36/A 36M or A 572/A 572M, Grade 50 [345].

Steel tubing.--

Steel tubing shall conform to ASTM Designation: A 500, Grade B.

Stud connectors.--

Stud connectors shall conform to ASTM Designation: A 108, Grades 1018 through 1020, cold drawn, either semi- or fully killed.

Machine bolts, nuts and washers.--

Machine bolts and nuts shall conform to ASTM Designation: A 307.

Washers for machine bolts shall be commercial quality.

Inorganic zinc primer.--

Inorganic zinc primer shall be a waterborne inorganic zinc primer conforming to the requirements of AASHTO Designation: M 300-92 I, Type II. Inorganic zinc primer shall be listed on the qualified products list which may be obtained from the Transportation Laboratory, (916) 227-7000.

Mortar.--

Mortar shall consist of one part cement, measured by volume, to 2 parts clean sand and only enough water to permit placing and packing.

FABRICATION.--

Shop fabrication and assembly.--Workmanship and finish shall be equal to the best general practice in modern shops.

Cuts shall not deviate more than 2 mm from the intended line. Roughness, notches or gouges shall be removed.

Bearing stiffeners at points of loading shall be square with the web and shall have at least 75 percent of the stiffener in contact with the flanges.

Finished members shall be true to line, shall have square corners and smooth bends and shall be free from twists, kinks, warps, dents and open joints.

Exposed edges and ends of metal shall be dressed smooth, with no sharp edges and with corners slightly rounded.

Stud connectors.--Steel surfaces shall be prepared as recommended by the manufacturer of the stud connectors. Stud connectors shall be welded to the flanges of beams or girders as shown on the plans. Automatic end welding of headed stud connectors shall be in accordance with the manufacturer's instructions.

Connections.--Abutting surfaces at connections shall be clean.

Cutting and welding at the jobsite will not be allowed except as shown on the approved drawings or specifically approved by the Engineer.

Finished holes for bolts shall be cylindrical and perpendicular to the plane of the connection. Subpunched and subdrilled holes shall be 6 mm smaller in diameter than the diameter specified for the finished hole.

Bolted Connections.--Bolts for connecting steel to steel shall be machine bolts conforming to ASTM Designation: A 307.

Holes for other work.--Holes for securing other work to structural steel and passage of other work through steel framing members shall be as shown on the approved drawings.

Threaded nuts or specialty items for securing other work to steel members shall be as shown on the approved drawings.

Holes shall be cut, drilled or punched perpendicular to metal surfaces. Holes shall not be flame cut or enlarged by burning. Holes are to be drilled in bearing plates.

SHOP PAINTING.--

General.--Structural steel members shall be painted. Color shall be as shown on the plans.

Surface preparation.--Surfaces of structural steel to receive inorganic zinc primer shall be blast cleaned in accordance with Steel Structures Painting Council, SSPC-SP 10, "Near-White Blast Cleaning."

Bolted connections.--Contact surfaces of ungalvanized anchor bolt assemblies shall be blast cleaned and coated with waterborne inorganic zinc primer before assembly. The total thickness of primer on each surface shall be between 0.025 mm to 0.076 mm and may be applied in one application.

Painting.--Immediately after surface preparation, surfaces of structural steel shall receive an undercoat of waterborne inorganic zinc primer. Color shall essentially match Federal Standard 595B, No. 36373.

The manufacturer's published mixing and application instructions for inorganic zinc primer shall be followed.

PART 3.- EXECUTION

ERECTION AND ASSEMBLY.--

Field splices.--Field splices shall be made only at the locations shown on approved working drawings.

The parts shall be accurately assembled in their final position as shown on the plans and in true alignment with related and adjoining work before final fastening.

All parts shall be supported adequately and at locations to provide a vibration free, rigid, and secure installation.

Bolted connections.--The bolt head type and head location shall be consistent within a joint.

Nuts shall be on side of member least exposed to view.

Setting bases and bearing plates.--Concrete and masonry surfaces shall be cleaned and roughened to improve bond. Bottom of base and bearing plates shall be clean.

Base plates and bearing plates for structural members shall be set on wedges or other adjusting devices.

Anchor bolts shall be wrench tightened after supported members have been positioned and plumbed.

Mortar shall be solidly packed between bearing surfaces and base or bearing plates to ensure that no voids remain. Exposed surfaces shall be finished and allowed to cure.

FIELD PAINTING.--

Touch-up painting.--After erection, the Contractor shall clean field welds, bolted connections, and abraded areas of shop paint and apply the same materials as applied for shop painting.

Surfaces that are scheduled to receive finish coats shall be painted with an additional prime coat and finish coats in accordance with the requirements specified for shop primed steel under "Painting" in Section 12-9.

QUALITY CONTROL.--

Testing and inspection.--Ultrasonic examination shall be performed by the Contractor on at least 50 percent of all full penetration butt-welded splices in accordance with the requirements of AWS D1.1 and these special provisions.

Welding procedures and methods shall be subject to inspection for conformance with AWS D1.1.

Butt welds shall be tested in accordance with AWS D1.1, Chapter 6, Part C, Ultrasonic Testing of Groove Welds.

Examination, reporting and disposition of tests shall be in accordance with the provisions of 6.12, AWS D1.1.

In addition to ultrasonic examinations by the Contractor, welds may be subject to inspection or non-destructive testing by the Engineer.

When additional inspection or non-destructive testing is required by the Engineer, the Contractor shall provide sufficient access facilities in the shop and at the jobsite to permit the Engineer or his agent to perform such inspection and testing.

The Contractor shall correct all deficiencies in the structural steel work which inspections and laboratory test reports have indicated to be not in compliance with these special provisions. Additional tests shall be performed by the Contractor at his expense to reconfirm any non-compliance of original work, and to show compliance of the corrected work.

12-5.02 METAL DECK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing metal deck in accordance with the details shown on the plans and these special provisions.

Metal deck includes ribbed sheet steel decking units, bent plates, accessories, fasteners and such other components, not mentioned, but required for a rigid, secure and complete installation.

REFERENCES.--

General.--The design, fabrication and erection of metal deck shall conform to the applicable requirements of the American Iron and Steel Institute (AISI) publication, "Specifications for the Design of Light Gauge Cold Formed Steel Structural Members," and the applicable Steel Deck Institute Design Manual and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for each type of deck and accessories shall be submitted for approval.

Working drawings.--Working drawings showing complete erection layouts, details, dimensions, deck section properties shall be submitted for approval. Drawings shall show types and gages, fastening methods, including the location, type and sequence of connections, surface finishes and temporary supports or bracing.

The metal deck supplier shall submit technical specifications for the steel, galvanized fastener along with a fastening schedule for approval.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of Compliance shall be furnished for the metal deck in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

DELIVERY, HANDLING AND STORAGE.--

General.--Metal deck units and accessories shall be transported, stored and erected in a manner that will prevent corrosion, distortion or other damage.

Deck units shall be stored off the ground with one end elevated to provide drainage.

PART 2.- PRODUCTS

MANUFACTURERS.--Acceptable manufacturers shall be; Verco Manufacturing Co.; BHP Co.; or equal.

MATERIALS.--

Deck units.--

Deck units, closures and plates shall be fabricated from galvanized sheet steel conforming to ASTM Designation: A 653/A 653M, Grade 33 [230].

Galvanizing shall conform to the requirements of ASTM Designation: A 924/A 924M, G60 [Z180].

Miscellaneous steel shapes.--

Miscellaneous steel shapes shall conform to ASTM Designation: A 36/A 36M.

Anchor clips, vent clips, flashing, saddle plates, flexible closure strips and other accessories.--

Anchor clips, vent clips, flashing, saddle plates, flexible closure strips and other accessories shall be as recommended by the deck manufacturer.

FABRICATION.--

General.--Deck units shall be formed to span 3 or more supports, with flush, telescoped or nested 50 mm laps at ends and interlocking or nested side laps unless otherwise shown on the plans.

Deck units shall conform to the configurations, metal thickness, depth and width and section properties shown on the plans.

End bearing shall be not less than 38 mm.

Metal closure strips.--Metal closure strips for opening between deck units and other construction shall be fabricated from the same gage and material as the adjacent deck units. Strips shall be formed to provide tight-fitting closures at end of cells or flutes and sides of deck.

PART 3.- EXECUTION

INSTALLATION.--

General.--Deck units and accessories shall be installed in accordance with the manufacturer's recommendations and approved drawings and these special provisions.

Units shall be placed on supporting structural framework, adjusted in place and properly aligned before being permanently fastened. Ends of units shall have positive bearing over structural supports.

Cutting and fitting shall present a neat and true appearance with exposed burrs removed. Openings through the deck shall be cut square and shall be reinforced as recommended by the deck manufacturer.

The metal deck shall not be used as a working platform before deck units are fastened in place. Supplies, equipment or other loads shall not be stored on the deck. Mechanical equipment or other loads shall not be hung from metal roof deck.

Fastening roof deck units.--Roof deck units shall be fastened to supporting structural members as shown on the structural plans.

Fastening side laps.--Side laps of adjacent deck units shall be fastened as shown on the plans.

Field painting:--Immediately following erection, abraded areas shall be cleaned with a wire brush. Metal deck shall be shop primed and field painted. Locations of deck to be field painted shall be as shown on the plans.

Galvanized surfaces shall be touched-up with galvanizing repair paint recommended by the manufacturer.

12-5.03 BUILDING MISCELLANEOUS METAL

PART 1.- GENERAL

Scope.--This work shall consist of fabricating, furnishing and installing building miscellaneous metal in accordance with the details shown on the plans and these special provisions.

Building miscellaneous metal shall consist of the following:

- Sectional overhead door jambs and track supports
- Unit heater support
- Miscellaneous plates and shapes

including all anchors, fastenings, hardware, accessories and other supplementary parts necessary to complete the work.

REFERENCES.--

Codes and standards.--Welding of steel shall be in accordance with American Welding Society (AWS) D 1.1, "Structural Welding Code-Steel" and D 1.3, "Structural Welding Code-Sheet Steel."

SUBMITTALS.--

Product data.--Submit manufacturer's specifications, anchor details and installation instructions for products used in miscellaneous metal fabrications.

Working drawings.--Working drawings of fabricated items shall be submitted for approval.

QUALITY ASSURANCE.--

Shop assembly.--Preassemble items in shop to the greatest extent possible to minimize field splicing and assembly. Disassemble units only as necessary for shipping and handling limitations. Clearly mark all units for reassembly and installation.

Inspection and tests.--Materials and fabrication procedures shall be subject to inspection and tests by the Engineer, in mill, shop and field. Such tests will not relieve the Contractor of responsibility of providing materials and fabrication procedures in compliance with specified requirements.

PART 2.- PRODUCTS

MATERIALS.--

Steel bars, plates and hot-rolled shapes.--

Steel bars, plates and hot-rolled shapes shall conform to ASTM Designation: A 36/A 36M.

Bolts, studs, threaded rods, nuts and washers.--

Bolts, studs and nuts for general application shall conform to ASTM Designation: A 307.

Washers shall be commercial quality.

Expansion anchors.--

Expansion anchors shall be ICBO approved for the purpose intended, integral stud type anchor or internally threaded type with independent stud, hex nut and washer.

Powder driven anchors.--

Powder driven anchors shall be plated, spring steel alloy drive pin or threaded stud type anchors for use in concrete or steel. Spring steel shall conform to ASTM Designation: A 227M, Class 1. The diameter, length and type of shank and the number and type of washer shall be as recommended by the manufacturer for the types and thickness of material being anchored or fastened.

FABRICATION.--

Workmanship and finish.--Workmanship and finish shall be equal to the best general practice in modern shops.

Miscellaneous metal shall be clean and free from loose mill scale, flake rust and rust pitting, and shall be well formed and finished to shape and size with sharp lines and angles. Bends from shearing or punching shall be straightened.

The thickness of metal and details of assembly and support shall give ample strength and stiffness.

Built-up parts shall be true to line and without sharp bends, twists and kinks. Exposed ends and edges of metal shall be milled or ground smooth, with corners slightly rounded.

Joints exposed to the weather shall be made up to exclude water.

Galvanizing.--Items indicated on the plans to be galvanized shall be hot-dip galvanized after fabrication. The weight of galvanized coating shall be at least 460 grams per square meter of surface area, except drainage grates shall have at least 610 grams per square meter of surface area.

Painting.--Building miscellaneous metal items not galvanized shall be cleaned and prime painted prior to erection in accordance with the requirements specified for steel and other ferrous metals under "Painting" in Section 12-9, "Finishes," of these special provisions.

PART 3.- EXECUTION

GENERAL.--

Anchorage.--Anchorage devices and fasteners shall be provided for securing miscellaneous metal in-place construction; including threaded fasteners for concrete and masonry inserts, toggle bolts, through bolts, lag bolts, wood screws and other connectors.

Cutting, drilling and fitting shall be performed as required for installation of miscellaneous metal fabrications. Work is to set accurately in location, alignment and elevation, plumb, level, true and free of rack, measured from established lines and levels.

Powder driven anchors.--Powder driven anchors shall be installed with low velocity powder actuated equipment in accordance with the manufacturer's instructions and State and Federal OSHA regulations.

DAMAGED SURFACES.--

General.--Galvanized surfaces that are abraded or damaged at any time after the application of the zinc coating shall be repaired by thoroughly wire brushing the damaged areas and removing all loose and cracked coating, after which the clean areas shall be painted with 2 applications of unthinned zinc-rich primer (organic vehicle type). Aerosol cans shall not be used.

SECTION 12-6. WOOD AND PLASTICS

12-6.01 ROUGH CARPENTRY

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing materials and performing rough carpentry work including wood framing, furring, and sheathing in accordance with the details shown on the plans and these special provisions.

Rough carpentry includes carpentry work not specified as part of other sections and which is generally not exposed.

SUBMITTALS.--

Product Data.--Manufacturer's material data and installation instructions shall be submitted for gypsum sheathing, framing hardware and underlayments.

Wood treatment data.--Chemical treatment manufacturer's instructions shall be submitted for the handling, sorting, installation, and finishing of treated materials.

For each type of preservative treatment used, certification by treating plant shall include type of preservative solution and pressure process used, net amount of preservative retained and conformance with the applicable standards of the American Wood Preservers Association.

DELIVERY, HANDLING AND STORAGE.--

Delivery and storage.--Materials shall be kept under cover and dry. All materials shall be protected from exposure to weather and contact with damp or wet surfaces with blocking and stickers. All lumber, plywood and other panels shall be stacked in such a manner to provide air circulation within and around the stacks.

PART 2.- PRODUCTS

LUMBER.--

General.--Lumber shall be manufactured to comply with PS 20, "American Softwood Lumber Standard," and with applicable grading rules of inspection.

Softwood lumber shall be quality grade stamped or shall be accompanied by a certificate of inspection. Inspection certificates or grade stamps shall indicate compliance with the grading requirements of WWPA, WCLIB, RIS, or other approved lumber inspection agencies.

All lumber used shall be nominal sized and dressed S4S unless otherwise specified in these special provisions.

Framing lumber shall be solid stock lumber, Douglas Fir-Larch, and the grades indicated under WCLIB or WWPA rules. Moisture content shall not exceed 19 percent and shall be grade stamped "S-Dry."

DIMENSION LUMBER.--

Except as otherwise shown on the plans, lumber shall have the following grades.

Vertical framing lumber.--

Vertical framing lumber, nominal 51 mm x 51 mm through 102 mm x 102 mm, shall be Construction grade or better.

Vertical framing lumber, nominal 51 mm x 152 mm through 102 mm x 152 mm shall be No. 2 or better.

Horizontal framing lumber.--

Horizontal framing lumber, nominal 51 mm x 102 mm and wider, including joists shall be No. 2 or better.

Horizontal framing lumber, nominal 102 mm x 102 mm and wider, including joist shall be No. 1 or better.

Miscellaneous lumber.--

Miscellaneous lumber for support or attachment of other work including rooftop equipment curbs and support bases, cant strips, bucks, nailers, blocking, furring, grounds, stripping and similar members shall be not less than No. 2 or better.

Lumber in contact with concrete or masonry construction shall be pressure treated Douglas Fir-Larch.

TIMBERS.--

Timbers (nominal 127 mm or thicker).--

Timbers shall be No. 1 or better.

PLYWOOD PANELS.--

General.—Plywood panels shall comply with Voluntary Product Standard PS1, "U. S. Product Standard for Construction and Industrial Plywood."

Plywood panels shall be Group 1 unless otherwise noted.

Each plywood panel shall be factory marked with APA or other trademark evidencing compliance with grade requirements.

Structural plywood roof sheathing.--

Structure plywood roof sheathing shall be APA RATED SHEATHING, Exposure 1, 13mm, C-C plugged exterior.

MISCELLANEOUS MATERIALS.--

Rough Carpentry Hardware.--

Steel plates and rolled sections shall be mild, weldable steel, conforming to AISI grades 1016 through 1030 except 1017.

Nails, screws, bolts, nuts, washers shall be commercial quality. Exposed fasteners shall be hot dipped galvanized or stainless steel.

Joist hangers, clips and other standard framing hardware shall be ICBO approved, commercial quality, galvanized sheet steel or hot dipped galvanized, of the size shown on the plans.

Expansion anchors and powder driven anchors shall be as specified under "Building Miscellaneous Metal," in Section 12-5, "Metals," of these special provisions.

Nails.--

Nails shall conform to ASTM F 1667-95. "Common" nails shall conform to the following table:

Nail Size	Length (mm)	Diameter (mm)
8d	63.5	3.33
10d	76.2	3.76
16d	88.9	4.11

Plywood screws.--

Plywood screws shall be metal deck screws with pull-out test of 135 kg minimum, at 152 mm on center at perimeter of panels and 305 mm on center in field.

WOOD TREATMENT BY PRESSURE PROCESS.--

Preservative treatment.--

Preservative treatment shall be copper naphthenate, pentachlorophenol or water-borne arsenicals (ACA, CCA or ACZA).

The following items shall be treated:

Wood sills, sleepers, blocking, furring and other similar members in contact with concrete or masonry.

All holes, daps and cut ends of treated lumber shall be thoroughly swabbed with 2 applications of copper naphthenate.

PART 3.- EXECUTION

INSTALLATION.--

Wood framing.--Wood framing shall be in accordance with Chapter 23 of the California Building Code.

Framing members shall be of sizes and spacing shown on the plans. Unless otherwise shown on the plans, structural members shall not be spliced between supports.

Wood framing shall be accurately cut and assembled to provide closely fitted members. Framing shall be erected true to the lines and grades shown on the plans and shall be rigidly secured in place as shown and as required by recognized standards. Bracing shall be placed wherever necessary to support all loads on the structure during erection.

The size and spacing of fasteners and the edge distance for nails shall be as shown on the plans.

Nailing schedule shall be as shown on the plans and shall comply with the California Building Code.

Plywood panels.--Plywood panels shall be attached to the framing with finish nails.

Spacing between panels shall be 3 mm.

12-6.02 PREFABRICATED WOOD I-BEAM JOISTS

PART 1.- GENERAL

Scope.--This work shall consist of designing, fabricating, furnishing and erecting pre-engineered, factory fabricated wood I-beam joists in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Working drawings.--Complete working drawings, erection drawings, if required, and design calculations for the pre-engineered I-beam joists, permanent bracing and connection details shall be submitted for approval. Submittals shall be approved prior to the start of fabrication.

Working drawings and design calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California. The expiration date of the registration shall be shown. Engineer's original signature shall be submitted.

Working drawings shall show the lumber and plywood sizes, species and grades for joist flanges and webs and for temporary and permanent bracing members. Joint and connection details shall be shown.

Working drawings shall include a location plan which shows the location and identification of each joist.

Calculations for the design of the joists, bracing and connections shall include a list of applied loads and load combinations with the resulting member forces and member stresses.

If the design calculations contain or consist of computerized or tabulated calculations, the values pertaining to the design shall be identified, described or indexed in such a manner that a design review can be performed.

QUALITY ASSURANCE.--

Codes and standards.--I-beam joists and permanent bracing shall be designed for the loads shown on the plans. The design shall be in accordance with the requirements of the CBC, the "National Design Specification for Stress-Graded Lumber and Its Fasteners" by the National Forest Products Association (NFPA), and the "Timber Construction Standards" by the American Institute of Timber Construction (AITC). Joist trusses shall be ICBO approved.

Certificates of Compliance.--Certificates of Compliance shall be furnished for I-beam joists in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

DELIVERY, STORAGE AND HANDLING.--

General.--I-beam joists shall be transported and handled in such a manner as to prevent damage due to warping, distortion and moisture. Joists shall be stored off the ground.

PART 2.- PRODUCTS

I-beam joists.--

I-beam joists shall be factory fabricated, pre-engineered I-beam joists, with solid sawn or laminated wood flanges and plywood or oriented strand board (OSB) webs. Joists shall be sized to fit the location shown on the plans. Lumber sizes, and lumber species and grades shall be as shown on the approved working drawings. Lumber and plywood shall bear grade marks of a recognized grading association and the moisture content of the lumber shall be within the amount specified in the referenced specifications.

Connectors and fasteners.--

Connectors and fasteners shall be as shown on the approved working drawings.

FABRICATION.--

General.--Joists and bracing members shall be accurately cut to provide tightly fitted joints and connections.

Camber, if required by the design, shall be built into the joists.

Each joist shall be stamped or marked with a location identification mark or symbol and with the name and address of the manufacturer.

PART 3.- EXECUTION

INSTALLATION AND ERECTION.--

General.--Joists shall be erected plumb and true and shall be secured rigidly in place in accordance with the joist manufacturer's recommendations.

Nails and other fasteners shall be placed as shown on the plans and as recommended by the manufacturer.

Bracing shall be installed during erection to hold the joists plumb and true and in a safe position until sufficient permanent construction is in place to provide full stability.

All permanent bracing shall be secured in place before any sustained permanent loads are applied to the joist system.

Materials loaded on the joist system shall be located in such a manner to insure that the design load is not exceeded in the area of placement of the materials.

12-6.03 FINISH CARPENTRY

PART 1.- GENERAL

SUMMARY.--

Scope.--This work consists of furnishing and installing materials and performing finish carpentry, including interior trim, plywood ceiling and plywood wall paneling, as shown on the plans and these special provisions.

Finish carpentry includes carpentry work not specified as part of other sections and which is generally exposed to view.

SUBMITTALS.--

Product data.--Manufacturer's specifications and installation instructions for each item of factory-fabricated siding and paneling.

Samples.--One sample shall be submitted to the Engineer at the jobsite for each species and cut or pattern of finish carpentry as shown below:

Interior standing and running trim - 610 mm long by full board or molding width, finished on one side and one edge.

Plywood paneling - 2440 mm long x full panel width, finished on one side.

QUALITY ASSURANCE.--

Factory marks.--Each piece of lumber and plywood shall be marked with type, grade, mill and grading agency identification. Marks shall be omitted from surfaces to receive transparent finish. A mill certificate stating that material has been inspected and graded in accordance with requirements shall be furnished if marks cannot be placed on concealed surfaces.

PRODUCT DELIVERY, STORAGE AND HANDLING.--

Delivery.--Carpentry materials shall be delivered after painting, wet work and similar operations have been completed.

Protection.--Finish carpentry materials shall be protected during transit, delivery, storage and handling to prevent damage, soiling and deterioration.

PART 2.- PRODUCTS

WOOD PRODUCT QUALITY STANDARDS.--

Softwood lumber.--Softwood lumber shall conform to the requirements of PS 20, "American Softwood Lumber Standard," with applicable grading rules of inspection.

Plywood.--Plywood shall conform to the requirements of Voluntary Products Standard PS-1, "U. S. Product Standard for Construction and Industrial Plywood."

Woodworking.--Woodworking shall conform to the requirements of Woodwork Institute of California (WIC), "Manual of Millwork."

MATERIALS.--

General.--Lumber sizes indicated shall be nominal sizes except as indicated by detailed dimensions. Lumber which is to be dressed or worked and dressed shall be manufactured to the actual sizes as required by PS 20.

Lumber that is to be painted may be solid or glued-up lumber at the contractor's option.

Plywood paneling and wainscotting.--

Plywood paneling and wainscotting shall be APA Interior Grade A-C, Group 1, Exposure 1 plywood, 13 mm thick. Grade A face to be exposed.

Interior standing and running trim.--

Standing and running trim to be painted shall be paint-grade pine, solid stock or finger jointed.

Miscellaneous Materials.--

Nails, screws and other anchoring devices of the type, size, material and finish required shall be provided for secure attachment, concealed where possible.

Fasteners and anchorages for exterior use shall be hot dip galvanized.

Preservative treatment.--

Preservative treatment shall be copper naphthenate, pentachlorophenol or water-borne arsenicals (ACA, CCA or ACZA).

All holes, daps, or cuts made after treating shall be thoroughly swabbed with copper naphthenate

PART 3.- EXECUTION

INSTALLATION.--

General.--All work shall be installed plumb, level and true with no distortions.

Standing and running trim.--Standing and running trim shall be installed with minimum number of joints possible, using full length pieces to the greatest extent possible.

Anchor finish carpentry.--Finish carpentry shall be anchored to framing or blocking built in or attached directly to the substrate.

Interior carpentry shall be attached to grounds, stripping and blocking with countersunk, concealed fasteners and blind nailing where required for complete installation. Fine finish nails shall be used for exposed nailing, countersunk and filled flush with finished surface.

ADJUSTMENT, CLEANING, FINISHING AND PROTECTION.--

General.--Damaged and defective finish carpentry work shall be repaired or replaced.

All exposed or semi-exposed surfaces shall be cleaned.

Finish carpentry shall be finished in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

12-6.04 CABINETS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing wood cabinets and plastic laminate tops, splashes and returns as shown on the plans and in these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's product data for plastic laminates and cabinet hardware shall be submitted for approval.

Samples.--Three samples shall be submitted for each of the items shown below:

Plastic laminate, 203 mm x 254 mm for each type, color, pattern and surface finish.

Working drawings.--Working drawings for cabinets showing location of cabinets, dimensioned plans and elevations, attachment devices and other components shall be submitted for approval. Working drawings shall bear the "WIC Certified Compliance Label" on the first sheet of the drawings.

QUALITY ASSURANCE.--

Codes and standards.--Cabinets and swinging gate shall be manufactured and installed in accordance with the Manual of Millwork of the Woodwork Institute of California (WIC) requirements for the grade or grades specified or shown on the plans.

Certificates of Compliance.--Prior to delivery to the jobsite, the cabinet manufacturer shall issue a WIC Certified Compliance Certificate indicating that the products he will furnish for this job and certifying that they will fully meet all the requirements of the grade or grades specified.

WIC Certified Compliance Label shall be stamped on all cabinet work and swinging gate.

Each plastic laminate top shall bear the WIC Certified Compliance Label.

Prior to completion of the contract, a WIC Certified Compliance Certificate for Installation shall be delivered to the Engineer.

DELIVERY, STORAGE AND HANDLING.--

Protection.--Cabinets shall be protected during transit, delivery, storage and handling to prevent damage, soiling and deterioration.

PART 2.- PRODUCTS

ACCEPTABLE MANUFACTURERS.--

Manufacturers.--Subject to compliance with these specifications, high pressure decorative laminates shall be Consoweld Corp.; Formica Corp.; Nevamar Corp.; or equal.

MANUFACTURED UNITS.--

General.--Cabinets shall be fabricated to the dimensions, profiles, and details shown on the plans with openings and mortises precut, where possible to receive hardware and other items and work.

Fabrication, assembly, finishing, hardware application, and other work shall be completed to the maximum extent possible prior to shipment to the jobsite.

Laminate clad cabinets.--

Laminate clad cabinets shall be custom grade, flush overlay construction.

Laminate cladding shall be high pressure decorative laminate complying with NEMA LD 3. Color, pattern and finish shall be as shown on the plans. Laminate surface and grade shall be as follows:

Horizontal and vertical surfaces other than tops shall conform to GP-50 (1.27 mm nominal thickness).

Postformed surfaces shall conform to PF-42 (1.07 mm nominal thickness).

Laminated counter tops and splashes.--

Laminated counter tops and splashes shall be WIC custom grade.

Surface material shall be high pressure laminated plastic conforming to NEMA LD-3, 1.27 mm thickness.

Unless otherwise shown on the plans, splashes shall be 102 mm high from the surface of the deck. Back splashes shall be continuous formed and coved. Side splashes shall be top set.

Laminated counter tops self edged, counter tops to receive sinks or plumbing fixtures shall have a bullnose.

The underside of tops and backsides of splashes shall be covered with an approved backing sheet.

CABINET HARDWARE AND ACCESSORY MATERIALS.--

General.--Cabinet hardware and accessory materials shall be provided for cabinets. Hardware shall be provided with standard US 26D metal plated finish.

Drawer slides.--

Drawer slides shall be side mounting full extension with fully enclosed rolling balls and rollers. Concealed slides and bearings, and positive stop. Capacity shall be not less than 35 kg, except capacity shall be not less than 45 kg for heavy duty drawers.

Door guides.--

Sliding door guides shall be continuous, dual channel, metal guides, top and bottom. Bottom guide shall have crowned track.

Shelf supports.--

Shelf supports shall be adjustable, semi-recessed, chrome finished pressed metal, heavy duty standards and support clip, with one inch adjustment increments.

Cabinet hinges.--

Cabinet hinges shall be steel. Length of jamb leaf shall be 64 mm. The type of hinge shall be as shown on the plans.

Cabinet hinge manufacturers shall be Stanley, Hager, McKinney, or equal.

Cabinet catches.--

Cabinet catches shall be self aligning magnetic type in aluminum case with zinc plated steel strike.

Cabinet catch manufacturers shall be Stanley, Hager, McKinney, or equal.

Cabinet pulls.--

Cabinet pulls shall be 8 mm diameter rod, with 33 mm projection and 75 mm center to center fastening.

Cabinet pull manufacturers shall be Stanley, Hager, McKinney, or equal.

FABRICATION.--

Shop assembly.--Nails shall be countersunk and the holes filled, molds shall be neatly mitered and all joints shall be tight and true.

As far as practicable, work shall be assembled at the mill and delivered to the building ready to be set in place. Parts shall be smoothly dressed and interior work shall be belt sanded at the mill and hand sanded at the building. After assembly, work shall be cleaned and made ready for the specified finish.

Veneer sequence matching shall be maintained of cabinets with transparent finish.

All work shall be prepared to receive finish hardware. Finish hardware shall be accurately fitted and securely fastened as recommended by the manufacturer. Finish hardware shall not be fastened with adhesives.

Drawers shall be fitted with dust covers of 6 mm plywood or hardboard above compartments and drawers except where located directly under tops.

Precut openings.--Openings for hardware, appliances, plumbing fixtures, and similar items shall be precut where possible. Openings shall be accurately located and templates used for proper size and shape. Edges of cutouts shall be smoothed and edges sealed with a water-resistant coating.

PART 3.- EXECUTION

INSTALLATION.--

Cabinets.--Cabinets shall be installed without distortion so that doors and drawers fit openings properly and are accurately aligned. Hardware shall be adjusted to center doors and drawers in openings and to provide unencumbered operation. Installation of hardware and accessory items shall be completed as indicated on the approved drawings.

Laminate tops.--Laminate tops shall be securely fastened to base units and other support systems as indicated on the approved drawings.

Cabinet hardware.--Doors for cabinets shall be equipped with one pair of hinges and one catch per leaf, unless otherwise shown on the plans. Each door leaf shall be equipped with one pull.

Drawers up to 610 mm wide shall have one pull and drawers over 610 mm wide shall have two pulls.

SECTION 12-7. THERMAL AND MOISTURE PROTECTION

12-7.01 WATER REPELLENT COATING

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and applying water repellent coating to masonry surfaces in accordance with the details shown on the plans and these special provisions.

The water repellent coating shall be applied to all exterior masonry surfaces.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, application instructions and general recommendations for water repellents shall be submitted for approval.

QUALITY ASSURANCE.--

Codes and standards.--Water repellent coatings shall comply with all rules and regulations concerning air pollution in the State of California.

Certificates of Compliance.--Certificates of Compliance shall be furnished with each shipment of water repellent coating materials in accordance with Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

PART 2.- PRODUCTS

Water repellent coating.--

Water repellent coating shall be clear, colorless, water-based sealer. Water repellent coating shall be Hydrozo Inc., Clear Double 7; Euclid Chemical Co., Architectural Seal VOX; Tamms Industries Co., Chemstop; or equal.

PART 3.- EXECUTION

Preparation.--All surfaces to receive water repellent coating shall be dry and cleaned by removing contaminants that block pores of the surface. Cleaning methods shall be as recommended by the water repellent manufacturer.

Application.--The water repellent solution shall be applied in accordance with the manufacturer's printed instructions. The time period between applications of water repellent coating shall be not less than 24 hours.

Protection.--Surfaces of other materials surrounding or near the surfaces to receive the water repellent coating shall be protected from overspray or spillage from the waterproofing operation. Water repellent coating applied to surfaces not intended to be waterproofed shall be removed and the surfaces restored to their original condition.

12-7.02 INSULATION (GENERAL)

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing insulation in accordance with the details shown on the plans and these special provisions.

Insulation materials shall be as specified in these special provisions, and shall be compatible with existing or new materials incorporated in the building.

SUBMITTALS.--

Product data.--A list of materials, manufacturer's descriptive data, location schedule, and time schedule shall be submitted for approval.

The list of materials to be used shall include the trade name, manufacturer's name, smoke developed and flame spread classification, resistance rating and thickness for the insulation materials and accessories.

Schedules.--A location schedule and time schedule shall be submitted for approval.

The location schedule shall show where each material is to be installed.

The Contractor shall provide the Engineer at the jobsite with an accurate time schedule of the areas of the building to be insulated each day. The time schedule shall be submitted 3 working days in advance of the work.

Samples.--Samples of insulation material shall be submitted to the Engineer at the jobsite.

QUALITY ASSURANCE.--

Codes and standards.--All insulating materials shall be certified to comply with the California Quality Standards for Insulating Materials and shall be listed in the Department of Consumer Affairs publication "Consumer Guide and Directory of Certified Insulation Material."

DELIVERY, STORAGE AND HANDLING.--

General.--Insulating materials shall be delivered to the jobsite and stored in a safe dry location with labels intact and legible.

Insulating materials shall be protected from physical damage and from becoming wet or soiled.

In the event of damage, materials shall be repaired or replaced as necessary to comply with these specifications.

PART 2.- PRODUCTS (Not applicable.)

PART 3.- EXECUTION (Not applicable.)

12-7.03 BATT AND BLANKET INSULATION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing batt or blanket insulation in accordance with the details shown on the plans and these special provisions.

Batt insulation shall include faced and unfaced batts in walls and ceilings, acoustical batts for sound control and exposed batt or blanket insulation for ceilings and walls.

QUALITY ASSURANCE.--

The name of the laminator shall be submitted with the Product Data.

Codes and standards.--All batt or blanket insulation, including facings such as vapor barriers, shall have a flame-spread rating not to exceed 25 and a smoke density not to exceed 450 when tested in accordance with UBC Standard No. 8-1.

The flame-spread and smoke density limitations do not apply to facings on batt insulation installed between ceiling joists, or in roof-ceiling or wall cavities, provided the facing is installed in substantial contact with the surface of the ceiling or wall finish.

PART 2.- PRODUCTS

INSULATING MATERIALS.--

General.--Fiberglass batts shall be thermal insulation produced by combining glass fibers with thermosetting resins to comply with ASTM Designation: C 665.

Wall insulation.--

Wall insulation shall be R-2.2 $K \cdot m^2/W$ fiberglass batts with paper-laminate vapor-retarder membrane on one face. Insulation shall conform to ASTM Designation: C 665, Type II, Class C.

Ceiling insulation.--

Ceiling insulation shall be R-5.3 $K \cdot m^2/W$ fiberglass batts with paper-laminate vapor-retarder membrane on one face. Insulation shall conform to ASTM Designation: C 665, Type II, Class C.

Acoustical insulation.--

Acoustical insulation shall be 89 mm, unfaced fiberglass insulation batts. Insulation shall conform to ASTM Designation: C 665, Type I.

Exposed insulation.--

Exposed insulation shall be fiberglass batts with vinyl vapor-retarder membrane on one face. Insulation shall conform to ASTM Designation: C 665, Type I. Exposed insulation for roof shall be R-5.3 $K \cdot m^2/W$.

VAPOR-RETARDERS.--

Paper-laminate vapor-retarder.--

Paper-laminate vapor-retarder shall be kraft paper sheets laminated together with asphalt or other vapor retarding compounds, scrim reinforced at edges of sheets.

Polyethylene vapor-retarder.--

Vinyl vapor-retarder shall be heavy duty white polyester film, vinyl faced fiberglass, metallized polyester film with a vapor transmission rating not to exceed 0.2 perm when tested in accordance with ASTM Designation: E-96. Vinyl vapor retarder shall be applied to face of roof framing as shown on the plans.

AUXILIARY INSULATION MATERIALS.--**Insulation tape.--**

Insulation tape shall be as recommended by the insulation manufacturer.

PART 3.- EXECUTION**INSTALLATION.--**

General.--The vapor retarder on faced batts shall be toward the interior and shall be fastened to provide a sealed retarder. Punctures and holes in the retarder shall be repaired.

Unless otherwise shown on the plans or specified elsewhere in these special provisions, insulation shall be kept 75 mm to 100 mm clear of lighting fixtures and heat producing electrical appliances and equipment.

Installing batt type insulation.--Insulation batts shall be installed to completely fill the space between framing members. Apply a single layer of insulation of required thickness, unless otherwise shown on the plans or required to make up total thickness. Installation shall conform to the manufacturer's recommendations and these special provisions.

12-7.04 RIGID WALL INSULATION**PART 1.- GENERAL****SUMMARY.--**

Scope.--This work shall consist of furnishing and installing rigid wall insulation in accordance with the details shown on the plans and these special provisions.

Rigid insulation shall include rigid insulation, wood nailers, fasteners and such other materials, not mentioned, which are required for the complete installation of the rigid insulation system.

QUALITY ASSURANCE.--

Codes and standards.--Rigid foam insulation shall have a flame-spread rating not to exceed 75 and a smoke density not to exceed 450 when tested in accordance with UBC Standard No. 8-1. Rigid foam insulation shall be approved in accordance with UBC Standard 26-3 to be installed exposed, or without a thermal barrier on the room side of the insulation.

PART 2.- PRODUCTS**Rigid insulation.--**

Rigid insulation shall be rigid rectangular boards of polyisocyanurate foam with aluminum foil facing on both sides and an aged thermal resistance of R-1.9 K• m²/W. Facing on exposed insulation shall be white tinted aluminum foil.

Wood nailers.--

Wood nailers shall be Douglas fir, Hem-fir or equivalent western softwood. Nailers in contact with masonry or concrete shall be pressure treated after fabrication. Wood preservatives shall be waterborne type.

Insulation tape.--

Insulation tape shall be as recommended by the insulation manufacturer.

Adhesive.--

Adhesive shall be construction grade panel adhesive as recommended by the insulation manufacturer.

PVC strips.--

PVC strips shall be interlocking male and female white PVC strips.

Fasteners.--

Fasteners shall be concrete nails; Bostich, Pneumatic Nail System; Buildex, Tampon Fasteners; or equal.

PART 3.- EXECUTION

Installation of rigid insulation.--The preparation of the wall surfaces and the installation of insulation shall conform to the manufacturer's recommendations and these special provisions.

Rigid insulation placed behind plywood or gypsum board shall be tight fitting between nominal 51 mm x 102 mm wood nailers laid flat and spaced 0.6 meter on center. Wood nailers shall also be placed at the top and bottom of the plywood or gypsum board.

Exposed rigid insulation shall be installed tight fitting between PVC strips spaced at 1.2 meter on center. PVC strips shall align with the vertical joints of the plywood below. Adhesive shall be applied to the PVC strips and the wall as recommended by the insulation manufacturer. Exposed insulation shall have no horizontal joints between the top of the plywood and the bottom of the trusses.

All joints between insulation boards and between insulation boards and wood nailers shall be taped.

Insulation panels with broken or crushed corners or edges shall be trimmed free of such defects or shall be discarded. Replacement boards less than 300 mm wide shall not be used.

Damaged insulation in the completed work shall be removed and replaced. Insulation that has been wet or is wet shall be considered damaged.

12-7.05 THROUGH-PENETRATION FIRESTOPPING**PART 1.- GENERAL****SUMMARY.--**

Scope.--This work shall consist of furnishing and installing firestopping materials at penetrations in fire-rated walls, floors, and ceilings in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--A list of materials, manufacturer's descriptive data, and location schedule shall be submitted for approval.

Descriptive data shall include trade names, manufacturers' names, complete information on the materials to be applied, approved lab Listing, the material thickness for the required fire resistance ratings, and the manufacturer's printed instructions for installation. Manufacturer's assembly shall be California State Fire Marshal approved.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of Compliance shall be furnished with each shipment of firestopping materials in accordance with Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

DELIVERY, STORAGE AND HANDLING.--

Delivery.--Materials to be applied shall be delivered in original unopened packages. Packages shall be identified by the manufacturer's label and shall bear proper labels for fire resistance classification.

Storage.--Materials shall be stored above ground, under cover, and in a dry location until ready for use. Packages which have been exposed to moisture before use shall be discarded.

PART 2.- PRODUCTS

Fire-rated caulk.--

Fire-rated caulk shall conform to ASTM Designation: E 814 and shall be rated for use in one-hour fire-rated assemblies. Fire-rated caulk shall be 3M Brand, Fire Barrier Caulk; Dow Corning, Fire Stop Sealant; Standard Oil, Fyre Putty; or equal.

Wrap strip.--

Wrap strip shall be nominal 6 mm thick intumescent elastomeric material in 50 mm wide strips, faced one side with aluminum foil, and rated for use in 1-hour and 2-hour fire-rated systems.

Packing material.--

Packing material shall be polyethylene backer rod or nominal one inch thickness of tightly packed ceramic (alumina silica) fiber blanket, mineral-wool batt or glass fiber insulation material.

Fire-rated mortar.--

Fire-rated mortar shall be non-asbestos, 753 to 913 kilograms per cubic meter air dried density portland cement fly ash through-penetration firestopping mortar. Fire-rated mortar shall conform to ASTM Designation: E 814 and shall be rated for use in 3-hour fire-rated systems at 75 mm minimum thickness.

Fire safing insulation.--

Fire safing insulation shall be inorganic 56 kilograms per cubic meter minimum density, non-combustible fiber insulation conforming to Federal Specifications HH-1-521F, when tested in accordance with ASTM Designation: E 119 and ASTM Designation: E 136 for 3 hour fire resistance.

PART 3.-EXECUTION

Installation.--Firestopping materials shall be installed to conform to the requirements of the California State Fire Marshal Listing and the manufacturer's recommendations.

12-7.06 WATER AND ICE BARRIER

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing water / ice barrier with in accordance with the details shown on the plans and these special provisions.

Water / ice barrier shall consist of membrane, which is required for a complete, self adhering and weather tight installation.

SUBMITTALS.--

Product data.--Manufacturer's technical product data, samples, installation instructions and recommendations for water / ice barrier membrane shall be submitted for approval.

Product data shall include the manufacturer's name and a complete material description for the membrane.

Samples.--Material samples shall not be less than 200 mm x 200 mm in size.

DELIVERY, HANDLING AND STORAGE.--

General.--Membrane shall be protected against damage and discoloration.

Membrane shall be stored above ground, with one end elevated for drainage and protected against standing water and condensation between adjacent surfaces.

WARRANTY.--

Warranty.--Membrane shall be warranted to be free of defects in manufacture.

PART 2.- PRODUCTS

WATER AND ICE BARRIER.--

Membrane.--

Water and ice barrier shall be a cold applied, self adhering rubberized asphalt roofing underlayment not less than 1.02 mm thick.

Water and ice barrier shall be W. R. Grace & Co., Ice and Water Shield; Protecto Wrap, Ice and Water Guard; Carlisle Coatings and Waterproofing, CCW WIP 300HT, or equal.

PART 3.- EXECUTION

INSTALLATION.--

General.--Water and ice barrier shall be installed in accordance with the manufacturer's instructions and recommendations.

The membrane shall be applied directly to plywood substrate. The plywood substrate shall be dry and cleaned of dust, dirt, loose nails or other protrusions from deck.

Water and ice barrier shall be applied only in fair weather at temperatures of 4.4°C or higher.

12-7.07 METAL ROOFING

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing preformed metal roofing in accordance with the details shown on the plans and these special provisions.

Metal roofing system shall consist of prefinished metal roof panels, trim, flashings, counterflashings, reglets, concealed fasteners, sealants, and other accessories and components, not mentioned, which are required for a complete, securely fastened and weathertight installation.

SYSTEM DESCRIPTION.--

Design Requirements.--The roofing system shall conform to the wind design requirements for uplift in Chapter 16 of the CBC for the wind speed and exposure shown on the plans.

SUBMITTALS.--

Product Data.--Manufacturer's technical product data, installation instructions, and recommendations for each type of roofing material shall be submitted for approval.

Product data shall include the manufacturer's name and a complete material description of all components of the metal roofing system.

Samples.--Material samples shall include a 305 mm x 305 mm sample of the roofing panel for each color to be installed and a sample of each anchor clip and fastening device.

A sample each type of snow guard shall be submitted for approval.

Working Drawings.--Working drawings showing the layout and details of the metal roofing shall be submitted for approval.

Working drawings shall show the shape, size, thickness, and method of attachment for each component used in the work; the layout and spacing of fasteners; details of connections and closures; and details for expansion joints and weathertight joints.

Design calculations for the fastening system with the substrate shown on the plans shall be submitted to verify compliance with the design requirements.

Working drawings and design calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California. The expiration date of the registration shall be shown. The Engineer's signature shall be original.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of compliance shall be furnished for the metal roofing system in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

DELIVERY, HANDLING AND STORAGE.--

Delivery and handling.--Panels shall be protected against damage and discoloration.

Storage.--Panels shall be stored above ground, with one end elevated for drainage and protected against standing water and condensation between adjacent surfaces.

PART 2.- PRODUCTS

MATERIALS.--

SHEET MATERIAL.--

Base metal.--

Base metal shall be cold formed, 0.71 mm (24-gage), galvanized sheet steel conforming to ASTM Designation: A 653/A 653M, Grade 33 [230] with G90 [Z275] coating, except where a higher strength is required for performance, extra smooth; or cold formed aluminum-zinc alloy-coated, commercial quality, sheet steel conforming to ASTM Designation: A 792/A 792M, Grade 40 [275] with AZ55 [AZM 165], coating extra smooth.

Configuration.--

Metal roofing system shall be a standing seam system with standing rib a minimum of 45 mm high and spaced not less than 305 mm nor more than 460 mm on center.

METAL FINISHES.--

General.--Coatings shall be applied before or after forming and fabricating panels, as required for maximum coating performance capability.

Colors shall be as shown on the plans.

Fluoropolymer coating.--

Finish shall be the manufacturer's standard Kynar coating with a baked on primer (0.005 mm) and a finish coat of 0.02 mm nominal for a total dry film thickness of approximately 0.025 mm nominal.

Interior finish shall consist of a 0.004 mm epoxy primer and a backer coat.

MISCELLANEOUS METAL SHAPES.--

Flashings, counterflashings, and reglets.--

Flashings, counterflashings and reglets shall be formed from the same material, gage and in the same color and finish as the roofing panels.

Soffit panels Perforated soffit.--

Soffit panels shall be smooth, flat, 305 mm wide and shall be formed from the same material, gage and in the same finish as the roof panels. Color shall be as shown on the plans.

MISCELLANEOUS MATERIALS--**Fastener clips.--**

Fastener clips shall be noncorrosive ferrous metal fasteners as recommended by the metal roofing system manufacturer to resist the design loads.

Fasteners.--

Fasteners shall be as recommended by the metal roofing system manufacturer. Sheet metal screws shall not be used except to fasten trim and flashings.

Underlayment.--

Underlayment shall be as specified under "Water/Ice Barrier" elsewhere in this Section 12-7 of these special provisions.

Sealant and sealant tape.--

Sealant and sealant tape shall be as recommended by the roofing manufacturer.

Closures.--

Closures shall be rubber, neoprene, closed cell plastic or prefinished metal.

Snow guards.--

Snow guard shall be as specified under "Snow Guards" elsewhere in this Section 12-7 of these special provisions.

FABRICATION.--

General.--Unless otherwise shown on the plans, or specified herein, roof panels shall be fabricated in continuous lengths for the length of the roof, from ridge or peak to eave, except such length shall not exceed the manufacturer's maximum production length. Flashings shall be fabricated in the longest practical lengths.

Roofing panels shall be factory formed. Field formed panels are not acceptable.

PART 3.- EXECUTION.--**INSTALLATION.--**

Roof panels.--The roof system shall be installed and fastened in accordance with the details shown on the plans and the approved working drawings. Cutting and fitting shall present a neat and true appearance with exposed burrs removed. Openings through roof panels shall be cut square and shall be reinforced as recommended by the metal roofing system manufacturer.

Roof panels shall be adjusted in place and properly aligned for the detailed conditions before fastening. Panels shall not be warped, bowed or twisted. The surface finish on the panels shall not be cracked, blemished or otherwise damaged.

Gaskets, joint fillers, sealants and sealing tape shall be installed where indicated on the approved drawings or as required for weatherproof performance of panel systems.

Fasteners shall not be driven through roof panels or batten covers.

Miscellaneous metal shapes.--Trim, fascia, flashings, gutters, downspouts, scuppers, caps, and other prefinished metal work shall be positioned to the correct alignment for each detailed condition. Metal work shall be securely attached to backing using fasteners at the spacing shown on approved working drawings. Prefinished metal to be installed over concrete, masonry or plaster shall be back-coated with asphaltic paint as recommended by the metal roofing system manufacturer.

Roof panels, trim, and other prefinished metal that are marred, punctured, incorrectly bent, or incorrectly installed will be considered damaged and shall be replaced with undamaged units.

The metal roofing system shall be installed weathertight. Closures shall be tight fitting and shall be provided at the ends of panels, at the boundary of the roof, and as indicated on the approved working drawings.

CLEAN UP AND CLOSE OUT.--

Clean up.--Adjacent surfaces shall be protected during the roofing system installation and sealant work. Excess sealant shall be removed as the installation progresses.

Roof panels, molding, trim, and other prefinished metal surfaces shall be cleaned after installation as recommended by the manufacturer. Exposed cuts shall be touched-up with a matching durable primer and paint as recommended by the metal roofing system manufacturer.

Touch up.--Damaged paint surfaces shall be touched up by using an air dry touch up paint supplied by the metal roofing system manufacturer. Only a small brush shall be used for touching up. No spraying of touch up paint is to be performed.

Damaged units.--Panels and other components of the work which have been damaged or have deteriorated beyond successful repair shall be removed and replaced.

12-7.08 SNOW GUARDS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing snow guards in accordance with the details shown on the plans and these special provisions.

Snow guards shall include roof seam clamps, color strip, fastening bolts, snow clips, and any other accessories needed to provide a complete installation.

Related work.--Metal roofing shall be in accordance with the requirements specified under "Metal Roofing" in this Section 12-7, of these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, and installation instructions shall be submitted for approval.

Samples.--Three samples of the complete snow guard assembly shall be submitted for approval.

DELIVERY, STORAGE, AND HANDLING.--

Delivery.--Materials shall be delivered in original packages and containers with seals unbroken and bearing manufacturer's labels containing brand name.

Storage.--Materials shall be kept dry and protected from the weather.

PART 2.- PRODUCTS

Snow guards.--

Snow guards shall be Alpine Snow Guards, "Color Gard"; Snowblox, Color bar Rail System; or approved equal.

Snow guards shall be 6061 T6 extruded aluminum, approximately 50 mm high, designed to receive a color strip and attach to the roof seam clamps with bolts and washers.

Roof seam clamps.--

Roof seam clamps shall be 6061 T6 extruded aluminum designed as appropriate for the roof seam profile and attached to the roof seam with 2 set screws.

Fasteners.--

Fasteners shall be Series 300 stainless steel bolts, washers and set screws. Bolts and set screws shall have a minimum diameter of 9.5 mm. Set screws shall have a rounded nose point to prevent damage to the panel finish.

Color strips.--

Color strips shall be prefinished metal of the same material and color as the prefinished metal roof panel.

PART 3.- EXECUTION

Installation.--Snow guards shall be installed true to line in accordance with the manufacturer's recommendations.

Set screws shall be on the same side of the roof seam clamp and on the same side of the roof seam throughout the installation. Set screws shall be torqued as recommended by the manufacturer to provide maximum holding strength. Set screws shall not penetrate the roof seam.

12-7.09 SHEET METAL FLASHING**PART 1.- GENERAL****SUMMARY.--**

Scope.--This work shall consist of fabricating, furnishing and installing sheet metal flashing in accordance with the details shown on the plans and these special provisions.

Sheet metal shall include metal flashings, counterflashings, straps, roof jacks, reglets, copings, scuppers, conductor heads, and screen type vents.

Alternatives.--Premolded roof flashings may be used in lieu of sheet metal flashings where shown on the plans.

QUALITY ASSURANCE.--

Codes and standards.--Sheet metal work shall in accordance with the requirements in the latest edition of the Sheet Metal and Air Conditioning Contractors National Association (SMACNA) "Standard Practice in Architectural Sheet Metal Work."

PART 2.- PRODUCTS**MATERIALS.--****Galvanized sheet steel.--**

Galvanized sheet steel shall conform to ASTM Designation: A 653/A 653M with G 90 [Z275] coating, not less than 0.71 mm (24-gage), unless otherwise shown on the plans. Surfaces to be painted shall not have factory coatings on galvanizing that cannot be removed by paint thinner.

Sheet aluminum.--

Sheet aluminum shall be not less than 0.81 mm thick, mill finish, 3003-H14 alloy, conforming to ASTM Designation: B 209M.

Sheet lead.--

Sheet lead shall be not less than 1.6 mm thick, conforming to ASTM Designation: B 749.

Premolded roof flashing.--

Premolded flashing shall be premolded neoprene or ethylene propylene diene monomer (EPDM) flashing, resistant to ozone and ultraviolet. Units shall have overlapping tab to flash the seam.

Hardware and fastenings.--

Hardware and fastening for premolded roof flashings shall be stainless steel.

Solder.--

Solder shall conform to ASTM Designation: B 32, Alloy Grade Sn50.

Soldering flux.--

Soldering flux shall be acid type, conforming to Federal Specification: O-F-506C, Type I, Form A.

Lap joint sealant.--

Lap joint sealant for concealed locations shall be a non-drying butyl.

Flashing cement.--

Flashing cement shall be a bituminous plastic cement, asbestos free, conforming to ASTM Designation: D 4586, Type II.

Sealant.--

Sealant for exposed locations shall be a silicone sealant conforming to ASTM Designation: C 920.

Primer.--

Primer shall be as recommended by the sealant manufacturer.

Coal tar paint.--

Coal tar paint shall be coal-tar epoxy coating conforming to U.S. Corps of Engineers Specification: C-200 or Steel Structures Painting Council Paint Specification: SSPC-16-68T.

FABRICATION.--

General.--Sheet metal shall be assembled to Sheet Metal and Air Conditioning Contractors National Association Standards.

Sheet metal shall be formed to the sizes, shapes and dimensions shown on the plans or as specified herein with angles and lines straight, sharp and in true alignment. The number of joints shall be kept to a minimum.

Angle bends and folds for interlocking the metal shall be made with full regard for expansion and contraction to avoid buckling or fullness in the metal after it is installed.

Joints in sheet metal work shall be closed watertight unless slip joints are specifically required. Watertight joints shall be mechanically interlocked and then thoroughly soldered for metals other than aluminum. Watertight joints in aluminum or between aluminum and other metals shall be sealed with acrylic sealant.

Sheet metal joints to be soldered shall be cleaned with steel wool or other means, pre-tinned and soldered watertight.

All joints shall be wiped clean of flux after soldering. Acid flux shall be neutralized by washing the joints with sodium bicarbonate.

Flashings shall have a 45 degree drip return at bottom edges. Unless otherwise shown on the plans, counterflashing shall extend not less than 100 mm over roofing or other materials protected by the counterflashing and shall be arranged so that roofing or materials can be repaired without damage to the counterflashing. Where reglets are indicated, counterflashing shall be fastened by lead wedges or snap-in flashing.

PART 3.- EXECUTION

PREPARATION.--Surfaces to receive sheet metal shall be clean, smooth and free from defects.

PROTECTION.--Aluminum surfaces to be in contact with concrete, mortar, or dissimilar metals shall be given a heavy coat of coal tar paint.

INSTALLATION.--

Roof penetration flashings.--All pipes, ducts, vents and flues passing through roofs shall be made waterproof with flashings of storm collars or counterflashings.

Roof penetration flashings shall be fabricated from galvanized sheet steel, not less than 0.71 mm (24-gage). Size and shape shall be as shown on the plans.

Premolded roof flashings.--Premolded roof flashings shall be installed in accordance with the manufacturer's instructions.

12-7.10 ROOF SPECIALTIES

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing roof specialties in accordance with details shown on the plans and these special provisions.

Roof specialties shall include prefabricated curb units.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, rough-in diagrams, installation instructions and general product recommendations shall be submitted for approval.

QUALITY ASSURANCE.--

Labels.--Units shall be provided which have been tested, listed, and bear the label of UL, FM or other recognized testing agency.

Codes and standards.--Prefabricated units shall conform to the requirements of SMACNA, "Architectural Sheet Metal Manual," details for fabrication of units, including flanges and cap flashing to coordinate with types of roofing involved.

PART 2.- PRODUCTS

General.--Manufacturer's standard units, modified as necessary, shall be provided to comply with the contract requirements. Each unit shall be shop fabricated to the greatest extent possible.

MATERIALS.--

Sheet steel.--

Sheet steel shall be structural quality conforming to the requirements of ASTM Designation: A 570.

Insulation.--

Insulation shall be the manufacturer's standard rigid or semi-rigid board of glass fiber and shall be the thickness required.

Fasteners.--

Fasteners shall be the same metal as the metal to be fastened, or other non-corrosive metal as recommended by the unit manufacturer. Finish of the fastener shall be the same finish as the metal being fastened.

Bituminous coating.--

Bituminous coating shall be as recommended by the unit manufacturer for the use specified.

Gaskets.--

Gaskets shall be tubular or fingered design of neoprene or polyvinyl chloride as recommended by the unit manufacturer.

PREFABRICATED CURB AND EQUIPMENT SUPPORTS.--

General.--Curb shall conform to the loading and strength requirements of the equipment to be supported. Dimensions shall conform to the dimensions shown on the coordination drawings of equipment to be supported. Unit shall be fabricated from sheet steel conforming to ASTM Designation: A 570 and galvanized after fabrication.

Units shall be fabricated with welded or sealed mechanical corner joints, complete with cant strips and base profile coordinated with roof slope.

Curb supports shall be fabricated with height tapered to provide a level installation.

PART 3.- EXECUTION

INSTALLATION.--

General.--Prefabricated units shall be installed in accordance with the manufacturer's instructions and approved coordination drawings.

Installation of the units shall be coordinated with installation of the roof deck and flashing materials.

Units shall be securely fastened to supporting members, adequate to withstand all lateral, inward or outward loading pressures.

Except as noted above, roof flanges shall be set in a thick bed of roofing cement to form a watertight seal.

Operational testing.--Units with operational components shall be fully tested. Joints and hardware shall be cleaned and lubricated. All units shall be adjusted for proper operation.

CLEANING AND PROTECTION.--

General.--All exposed metal and plastic surfaces shall be cleaned in accordance with the manufacturer's instructions. Damaged metal coatings shall be repaired.

12-7.11 SEALANTS AND CAULKING

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and applying sealants and caulking which are required for this project, but not specified elsewhere, in accordance with the details shown on the plans and these special provisions.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of compliance shall be furnished for the sealants and caulking in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and installation instructions for all sealants shall be submitted for approval.

Samples.--Color samples of all sealants shall be submitted for approval. Unless otherwise shown on the plans, colors will be selected by the Engineer from the manufacturer's standard colors.

PART 2.- PRODUCTS

MATERIALS.--

General.--All sealants, primers and accessories shall be non-staining to adjacent exposed surfaces. Products having similar applications and usage shall be of the same type and same manufacturer. Gun consistency compound shall be used unless otherwise required by the job conditions.

Acrylic sealant.--

Acrylic sealant shall be one compound, solvent release acrylic sealant.

Butyl sealant.--

Butyl sealant shall be one component, skinning type.

Silicone sealant.--

Silicone sealant shall be one component, low modulus building sealant. Sealant shall be tack-free in one hour, shall not sag or flow, shall be ozone resistant and capable of 100 percent extension without failure.

Joint sealant.--

Joint sealant shall be a two-part, non sag polysulfide base, synthetic rubber sealant formulated from liquid polysulfide polymer.

Backer rod.--

Backer rod shall be round, open or closed cell polyurethane. Backer rod shall be sized such that it must be compressed between 25 and 75 percent of its uncompressed diameter during installation in the joint.

Neoprene.--

Neoprene shall conform to the requirements of ASTM Designation: C 542.

PART 3.- EXECUTION

APPLICATION.--

General.--Unless otherwise shown on the plans, sealants shall be applied in accordance with the manufacturer's instructions.

Silicone sealants shall not be used in locations where painting is required.

Butyl sealants shall not be used in exterior applications, and acrylic sealants shall not be used in interior applications.

Sealants shall be applied in a continuous operation for the full length of the joint. Immediately following the application of the sealant, the sealant shall be tooled smooth using a tool similar to that used to produce concave masonry joints. Following tooling, the sealant shall remain undisturbed for not less than 48 hours.

SECTION 12-8. DOORS AND WINDOWS

12-8.01 HINGED DOORS

PART 1.- GENERAL

This work shall consist of furnishing and installing hinged doors and frames in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions for fire rated assemblies and a door schedule shall be submitted for approval. The door schedule shall include a description of the type, location and size of each door and frame.

PART 2.- PRODUCTS

Wood door.--

Wood door shall be Woodwork Institute of California (WIC) "Custom" grade flush, hollow or solid core wood doors as shown on the plans. Face shall be stain grade hardwood veneer except as otherwise shown on the plans. Doors shall bear the WIC quality grade mark or shall be accompanied by a Certificate of Compliance certifying compliance with the WIC quality specified herein. Certificates of Compliance shall be in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Metal door.--

Metal door shall be flush, seamless steel door factory prepared and reinforced to receive hardware and having cold rolled stretcher leveled sheet steel face sheets not less than 1.2 mm thick (18-gage). Face sheets shall be bonded with thermosetting adhesive to rigid board honeycomb or precured foam core; or face sheets shall be welded to all parts of an assembled grid of cold formed pressed metal stiffeners and framing members located around edges, ends, openings and at all locations necessary to prevent buckling of face sheets. Seams shall be tack welded, filled and ground smooth. Bottom edge and internal stiffeners of grid type core shall have moisture vents. Welds on exposed surfaces shall be ground smooth. Louvered or glazed openings shall be provided where shown on the plans.

Where fire rated doors are required, doors shall be listed and labeled for the fire rating shown on the plans.

Door shall be cleaned and treated by the bonderized process or approved phosphatizing process and then given one factory application of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Glazing for doors.--

Glazing for doors shall be safety glass as specified under "Glazing" in Section 12-8, "Doors and Windows," of these special provisions. Glazing shall be not less than 5 mm thick.

Louvers shall be cleaned and treated by the bonderized process or approved phosphatizing process and then given one factory application of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Pressed metal frame.--

Pressed metal frame shall be not less than 1.5 mm thick (16-gage) sheet steel with integral stop, mitered corners, face welded and ground smooth corners. Frames shall be reinforced for all hardware and shall be cleaned and treated by the bonderized process or an approved phosphatizing process and then given one factory application of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Frames for fire rated doors shall be listed for the same rating shown on the plans for fire rated doors.

Sealants.--

Sealants shall be ultraviolet and ozone resistant, gun grade polysulfide or polyurethane, multicomponent, Federal Specification: TT-S-227.

PART 3.- EXECUTION

INSTALLATION.--Doors and frames shall be installed rigidly, securely, plumb and true and in such a manner that the doors operate freely without rubbing or binding. Clearance between frame and door shall be not more than 3 mm. The exterior frame shall be sealed weathertight.

Pressed metal frames shall be secured with clips and anchors as shown on the plans.

Fire rated assemblies shall be installed according to the manufacturer's recommendations.

Fire rated assemblies shall include doors, door frames, automatic smoke-actuated closers, self-closing mechanisms, panic hardware, wire glass, and fire rated louvers. Assemblies shall be approved by the California State Fire Marshal.

PAINTING.--Except for the primer application specified herein, doors and frames shall be cleaned, prepared and painted in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

12-8.02 ATTIC ACCESS DOORS

PART 1.- GENERAL

This work shall consist of furnishing and installing attic access doors in accordance with the details shown on the plans and these special provisions

SUBMITTALS.--Manufacturer's descriptive data and installation instructions shall be submitted for approval.

PART 2.- PRODUCTS

Access doors.--

Access doors shall be factory assembled and factory prime painted steel. Door panel shall be 1.90 mm thick (14-gage) and door frame shall be 1.5 mm thick (16-gage) . The door and frame assembly shall have standard screw driver operated cam locks, concealed springs or continuous piano hinge and inside release handle. Access doors shall be by Babcock-Davis Hatchways, Bar-Co Access Doors, Inryco-Milcor, J.L. Industries, or equal.

PART 3.- EXECUTION

INSTALLATION.--Access doors shall be installed in accordance with the manufacturer's recommendations. The access door assemblies shall be painted to the match the color of the adjacent surrounding surfaces.

12-8.03 SECTIONAL OVERHEAD DOORS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing sectional overhead doors in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, roughing-in diagram and installation instructions for each size and type of door shall be submitted for approval.

Manufacturer's descriptive data shall include door panel construction and material thickness, door track size and material thickness, counterbalance spring service life and motor operator specifications.

Materials list shall contain all items proposed to be furnished and installed under this section of these special provisions.

Working drawings shall show details of special components and installations which are not fully dimensioned in manufacturer's descriptive data.

QUALITY ASSURANCE.--

Single source.--Each sectional door shall be provided as a complete unit produced by one manufacturer, including frames, sections, bracket guides, tracks, counterbalance mechanisms, hardware, operators and installation accessories, to suit opening and head room available.

Wind loading.--Design and reinforce section overhead doors to withstand a 960 PA wind load with a midspan deflection not to exceed 1/120 span.

PART 2.- PRODUCTS

MANUFACTURERS.--

Available manufacturers.--Subject to compliance with the specifications, manufacturers offering products which may be incorporated into the work include, but are not limited to the following: Clopay Corp.; Overhead Door Corp.; Raynor Garage Doors.

STEEL SECTIONS.--

Door sections.--

Door sections shall be galvanized commercial quality steel sheets and a minimum of G60 zinc coating complying with ASTM Designation: A 525.

Face sheets shall be not less than 0.86mm (20-gage). Back sheet shall be not less than 0.45 mm (26-gage).

Sections shall be fabricated from a single sheet to provide sections not more than 610 mm high, and nominal 50 mm deep. Meeting horizontal edges shall be rolled to a continuous shiplap, rabbeted, or keyed weather seal, with a reinforcing flange return.

Intermediate and end stiles shall be 1.52 mm (16-gage) galvanized steel welded in place. Intermediate stiles shall be spaced at not more than 1220 mm on center.

Bottom section shall be reinforced with a continuous channel or angle conforming to the bottom section profile.

Insulation.--

Insulation shall be the manufacturer's glass fiber, polystyrene or polyurethane foam type insulation and have an R-Value not less than 1.4 K•m²/W.

Finish.--

Finish shall be the manufacturer's standard baked on polyester prime coat, applied to interior and exterior faces. Final exterior finish on door sections and components shall be field applied in accordance with the requirements specified under "Painting" in Section 12- 9, "Finishes," of these special provisions.

TRACKS, SUPPORTS. AND ACCESSORIES.--

Door tracks.--

Door tracks shall be the manufacturers standard 76 mm, galvanized steel track system, sized for door size and weight, and designed for the clearances shown on the plans. Complete track assembly shall be provided, including brackets, bracing and reinforcing for rigid support of ball bearing roller guides, for required door type and size.

Track reinforcement and supports.--

Track reinforcement and supports shall be galvanized steel. Tracks shall be reinforced and supported as required for the size and weight of door to provide strength and rigidity, and to ensure against sag, sway and vibration during operation.

Door seals.--

Doors shall have perimeter gasket seals at head and jambs and seal shall have a replaceable vinyl or neoprene bottom seal.

Vision panels.--

Vision panels shall be door manufacturer's standard glazed opening with wire safety glass, metal frame and vinyl or neoprene glazing gasket for water tight construction. The approximate size shall be as shown on the plans.

Operable louvers.--

Operable louvers shall be factory fabricated units of extruded aluminum alloy not less than 2.0 mm thick or galvanized steel not less than 0.91 mm thick (20-gage) with standard "Z" type blades set in a continuous channel frame, with a 6 mm mesh galvanized bird-screen in a removable frame on the inside.

Blades shall have center pivot on 10 mm aluminum rods in stainless steel ball bearings in cadmium plated races.

Operable louvers shall be equipped with hand-hold fixed to the operating bar for easy adjustment with wingnut spring tension to lock louvers in desired position.

HARDWARE.--

General.--Hardware shall be heavy-duty, rust-resistant, with galvanized or cadmium-plated or stainless steel fasteners, to suit type of door.

Hinges.--

Heavy steel hinges shall be provided at each end stile and at intermediate stiles, per manufacturer's recommendations for size of door.

Rollers.--

Rollers shall be heavy-duty with steel ball bearings in case-hardened steel races, mounted to suit slope of track. Rollers shall have case-hardened tires.

COUNTERBALANCE MECHANISMS.--

Counterbalance spring.--

The door shall have a torsion spring counterbalance on a continuous cross header shaft; the entire assembly shall be all-bearing mounted. The spring shall have a rated service life of not less than 25,000 cycles.

ELECTRIC DOOR OPERATORS.--

Door operator shall be heavy duty, commercial type. Motor shall be a 208-volt, 3-phase, high starting torque motor with single reduction worm gear, completely housed and running in an oil bath. Motor shall be of sufficient capacity to raise and lower the door at speed of approximately 0.2 m per second.

Door operator and assembly shall be equipped with solenoid brake, limit switches for upper and lower limits of door travel, emergency hand chain with electrical interlock to break motor circuit when hand chain is engaged, 3-button operating station in a NEMA Type 4 enclosure, and a factory wired NEMA Type 1 control panel.

Control panel shall contain an instrument transformer, reversing magnetic contactor with overload relay, and all necessary control relays and other devices required for complete automatic operation of the door. Motor shall be removable for repair without affecting emergency operation. Motor shall be centermounted or sidemounted as shown on the plans.

Reversing door edge.--

Reversing door edge shall be an electrically operated safety device extending across the full width of the bottom of the door which shall cause the door to stop automatically and return to open position upon contact with any obstruction.

PART 3.- EXECUTION

INSTALLATION.--

General.--Door, track, and operating equipment, complete with necessary hardware, jamb and head mold stops, anchors, inserts, hangers, and equipment supports, shall be installed in accordance with the final drawings, manufacturer's installation instructions and these special provisions.

Vertical track assembly shall be fastened to framing at not less than 610 mm on center. Horizontal track shall be hung from structural overhead framing with angle or channel hangers, welded or bolted into place. Sway bracing, diagonal bracing, and reinforcing as required for rigid installation of track and door operating equipment.

12-8.04 WINDOWS

PART 1.- GENERAL

SUMMARY.--This work shall consist of furnishing and installing windows in accordance with the details shown on the plans and these special provisions.

Windows shall meet the requirement of NAFS-1, "Voluntary Performance Specification for Windows, Skylights, and Glass Doors," and shall meet the C30 (Commercial) product designation unless otherwise shown on the plans. Windows shall be labeled with the AAMA label.

Windows shall be factory finished as shown on the plans,

Glazing for windows shall be in accordance with the requirements specified under "Glazing" in Section 12-8, "Doors and Windows," of these special provisions.

CERTIFICATES OF COMPLIANCE.--Certificates of compliance shall be furnished for all windows in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions and schedule shall be submitted for approval.

Manufacturer's descriptive data and installation instructions shall show window elevations, plan views, full size sections, anchoring details to all substrates, anchors and hardware.

Installation schedule shall show location, size and type for each window.

PART 2.- PRODUCTS

Fixed windows.--

Fixed windows shall be non-operable glazed panel inserted into a frame to include muntins, glazing stops, and glazing accessories.

Horizontal sliding windows.--

Horizontal sliding windows shall be horizontal slide by windows with tightly contacting weatherstripped meeting stiles, self-lubricating rollers, glazing accessories, tubular sill, snap locks and push handle. Vents shall be screened.

Aluminum.--

Aluminum shall be extruded 6063-T5 aluminum alloy.

Screws, fasteners and window accessories.--

Screws, fasteners and window accessories shall be non-corrosive metals compatible with aluminum except guides and rollers may be vinyl and nylon respectively. Finish for locks, operators, strikes, keepers and other metal hardware shall match window finish.

Weatherstripping.--

Weatherstripping shall be continuous, replaceable type, wool pile mounted in metal or double runs of ultraviolet resistant neoprene or vinyl.

Vent screen.--

Vent screen shall be aluminum frame with 18 x 14 mesh aluminum screening and polyvinyl-chloride splines. Screen frames shall be removable from interior of building. Finish of screen frame shall match window finish.

Sealant.--

Sealant shall be single-component, solvent type acrylic, self-leveling, non-sag, conforming to Federal Specification: TT-S-230.

Tape.--

Tape shall be compatible with sealant; Pecora, "B-44 Extra-Seal;" Pittsburg Plate Glass, "Duribbon;" Protective Treatment, "PTU 606;" Tremco, "440 Tape;" or equal.

PART 3.- EXECUTION

FABRICATION.--Frame and sash shall be accurately machined and fitted to hairline joinery that develops the members. Joints shall be factory sealed weathertight.

Sash shall be removable from the interior only. Sash shall have concealed condensation weeps to the outside.

DELIVERY AND STORAGE.--Windows shall be delivered in original, unopened, unbroken containers, wrappings, or bags with labels bearing the brand name, name of manufacturer or supplier, standard of manufacture, and product description.

Windows and accessories shall be stored off the ground, kept dry, fully protected from weather and damage

INSTALLATION.--Window units shall be set straight, level, plumb and in true alignment in prepared openings. Windows shall be centered in openings. Clearance between the window unit and the building framing shall be from 4 mm to 6 mm at the sides and 13 mm at the top. Ventilator sash shall be adjusted after glazing for easy, smooth and proper operation.

The installation shall be flashed and sealed weathertight.

All aluminum surfaces in contact with masonry, steel or other incompatible materials shall be isolated with pressure sensitive tape, zinc chromate primer, bituminous paint or such other material recommended by the window manufacturer and approved by the Engineer.

12-8.05 PRESSED METAL FRAMED WINDOWS

PART 1.- GENERAL

SUMMARY.--This work shall consist of furnishing and installing pressed metal framed windows in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, working drawings and installation instructions shall be submitted for approval.

PART 2.- PRODUCTS

Framing.--

Framing shall be pressed metal, not less than 1.52 mm thick (16-gage) with all members square and true, full mitered frame corners and continuous welds at all joints and cover plates. Welds at frame faces shall be ground smooth and flush with surrounding surfaces. All metal surfaces shall be cleaned and factory primed with one coat of metal protective rust inhibitive primer. Primer shall not contain lead type pigments.

Anchors.--

Anchors shall be manufacturer's standard.

Glazing.--

Glazing shall conform to the requirements specified under "Glazing," in Section 12-8, "Doors and Windows," of these special provisions.

Backer rod.--

Backer rod shall be close cell, non-absorbent, non-staining foam rod compatible with sealant.

Sealant.--

Sealant shall be ultraviolet and ozone resistant, gun grade polysulfide or polyurethane, single component. Sealant shall conform to Federal Specification: TT-S-227.

PART 3.- EXECUTION

INSTALLATION.--Frames shall be installed rigidly, securely, plumb and true. Installations shall be sealed watertight and weathertight.

PAINTING.--Except for the primer application specified herein, exposed frame surfaces shall be cleaned, prepared and painted in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

12-8.06 FINISH HARDWARE

PART 1.- GENERAL

SUMMARY.--

This work shall consist of furnishing and installing hardware items for doors in accordance with the details shown on the plans and these special provisions.

Hardware for special doors and frames, if required, shall be as specified under "Hinged Doors" in Section 12-8 "Doors and Windows," of these special provisions.

Hardware assemblies shall comply with the fire code and the disabled accessibility requirements indicated on the plans and specified in these special provisions.

SUBMITTALS.—

Manufacturer's technical information and catalog cuts for each item of door hardware and a door hardware schedule shall be submitted for approval prior to installation.

Manufacturer's catalog cuts shall include catalog numbers, material, grade, type, size, function, design, quality and finish of hardware.

The door hardware schedule shall indicate the location and size of door opening, the door and frame material, and the size, style, finish and quantity of the hardware components required.

FINISHES.—

Hardware shall be provided with standard US 26D metal plated finish.

KEYING INSTRUCTIONS.—

New locks shall be compatible with the master key system of the existing facility and shall be keyed to the existing lock system in use.

Locks and cylinders shall be provided with six pin "O" cylinders and blank keys. Cylinders and blank keys shall be delivered to the Engineer for combining of cylinders and cutting of keys.

The Contractor shall provide cylinders for use during construction. Construction cylinders shall remain in place until permanent cylinders are installed. Construction cylinders shall remain the property of the Contractor.

Key bows shall be stamped "State of California" and "Do Not Duplicate."

PART 2.- PRODUCTS.--

GENERAL.—

Door hardware equal in material, grade, type, size, function, design, quality and manufacture to that specified herein may be submitted for approval.

Butt hinges.--

Butt hinges shall be steel, 1 1/2-pair per door unless otherwise specified or shown on the plans. Nonremovable pins shall be provided at outswing exterior doors. Hinge size shall be 114 mm x 114 mm unless otherwise noted.

Standard weight hinges shall be:

Hager	BB 1279
McKinney	TB 2714
Stanley	BB 179
or equal.	

Mortise locksets, latchsets and privacy sets.--

Mortise locksets shall be steel case with 32 mm x 203 mm face plate and 70 mm backset. Door and frame preparation for mortise locksets shall conform to ANSI A115.1.

Lever operated lockset shall be:

Best	35H 6FW 15H
Falcon	LM521 DG
Schlage	L9453P x 06
or equal.	

Cylindrical locksets and privacy sets.--

Cylindrical locksets and privacy sets shall be steel chassis, 54 mm diameter, 70 mm backset. Door and frame preparation for cylindrical lockset and privacy sets shall conform to ANSI A115.1.

Lever operated lockset shall be:

Best	83K6 AB 9C
Schlage	D53PD RHO
Falcon	LY501 DG
or equal.	

Lever operated privacy set shall be:

Best	83K OL 9C
Falcon	LY301 DG
Schlage	D40S RHO
or equal.	

Door closers.--

Parallel arms for closers shall be installed at outswing exterior doors. Closers shall have sprayed finish to match other hardware on door.

Door closers shall be:

LCN	4040
Norton	85001
Dorma	7800
or equal.	

Pushplates and pullplates.--

Pushplates and pullplates shall be 102 mm x 406 mm x 1.52 mm (16-gage). Grips shall be 25 mm diameter with 38 mm standoff and 203 mm center to center fastening, unless indicated otherwise.

Pushplates shall be:

Builders Brass	47
Quality	40
Trimco	1001-3
or equal.	

Pullplates shall be:

Builders Brass	47x290-1
Quality	1515
Trimco	01-3 x 1193-2
or equal.	

Kickplates.--

Kickplates shall be 254 mm in height x 51 mm less than door width x 1.52 mm (16-gage).

Kickplates shall be:

Builders Brass	37
Quality	48
Trimco	6000
or equal.	

Floor mounted stops.--

Floor mounted stops shall be dome type. The height of the stop shall be determined by the clearance required when a threshold is used or not used.

Stops for openings without thresholds shall be:

Builders Brass	8061
Quality	331
Trimco	1210
or equal.	

Stops for openings with thresholds shall be:

Builders Brass	8063
Quality	431
Trimco	1213
or equal.	

Wall bumpers.--

Wall bumpers base diameter shall be 64 mm with a 25 mm projection.

Bumpers shall be:

Builders Brass	WC9
Quality	302
Trimco	1272-1/4-CCS
or equal.	

Thresholds, rain drips, and door shoes.--

Thresholds, rain drips, and door shoes shall conform to the sizes and configurations shown on plans. Thresholds at door openings with accessibility requirements shall not exceed 13 mm in height.

Threshold, rain drip, and door shoe manufacturers shall be Pemko, Reese, Zero, or equal.

Threshold bedding sealant.--

Threshold bedding sealant shall conform to Federal Specification: SS-C-153.

Weatherstrip.--

Weatherstrip shall conform to the sizes and shapes shown on plans. Assemblies shall be UL listed and shall be provided where shown on the plans or as specified in these special provisions.

Weatherstrip manufacturers shall be Pemko, Reese, Zero, or equal.

Door signs and name plates.--

Door signs and name plates shall be as specified under "Signs" in Section 12-10, "Specialties," of these special provisions.

PART 3.- EXECUTION

DOORS AND FRAMES.--Doors and frames shall be set square and plumb and be properly prepared before the installation of hardware.

INSTALLATION.--Hardware items shall be accurately fitted, securely applied, and adjusted and lubricated in accordance with the manufacturer's instructions. Installation shall provide proper operation without bind or excessive play.

Hinges shall be installed at equal spacing with the center of the end hinges not more than 244 mm from the top and bottom of the door. Pushplates and door pulls shall be centered 1118 mm from the finished floor. Locksets and privacy sets shall be 1024 mm from the finished floor. Kickplates shall be mounted on the push side of the doors, 25 mm clear of door edges.

Thresholds shall be set in a continuous bed of sealant material.

Door controls shall be set so that the effort required to operate doors with closers shall not exceed 37.8 N maximum for exterior doors and 22.3 N maximum for interior doors. The effort required to operate fire doors may be increased above the values shown for exterior and interior doors but shall not exceed 66.7 N maximum.

Door stops located on concrete surfaces shall be fastened rigidly and securely in place with expansion anchoring devices. Door stops mounted elsewhere shall be securely attached with wood screws or expansion devices as required.

Backing shall be provided in wall framing at wall bumper locations.

The location and inscriptions for door signs and name plates shall be as shown on the plans.

Hardware, except hinges, shall be removed from surfaces to be painted before painting.

Upon completion of installation and adjustment, the Contractor shall deliver to the Engineer all dogging keys, closer valve keys, lock spanner wrenches, and other factory furnished installation aids, instructions and maintenance guides.

DOOR HARDWARE GROUPS AND SCHEDULE.--Hardware groups specified herein shall correspond to those shown on the plans:

GROUP 1

- 1 1/2-pair butt hinges
- 1 each lever operated mortise lockset
- 1 each door closer
- 1 each kickplate
- 1 each floor mounted door stop (door one only)
- 1 each weatherstrip
- 1 each door shoe with drip
- 1 each threshold

GROUP 2

- 1 1/2-pair butt hinges
- 1 each lever operated cylindrical lockset
- 1 each kickplate
- 1 each wall bumper (omit at door 15)

GROUP 3

1 1/2-pair butt hinges
1 each lever operated cylindrical lockset
1 each door closer
1 each weatherstrip
1 each kickplate
1 each wall bumper (omit at door 12)
1 each door shoe

GROUP 4

1 1/2-pair butt hinges
1 each lever operated cylindrical privacy set
1 each kickplate
1 each wall bumper
1 each threshold

GROUP 5

1 1/2-pair butt hinges
1 each door closer
1 each pushplate
1 each pullplate
1 each kickplate
1 each wall bumper
1 each threshold

12-8.07 GLAZING

PART 1.- GENERAL

SUMMARY.---

This work shall consist of furnishing and installing glazing in accordance with the details shown on the plans and these special provisions.

Glazing shall consist of glass for windows and doors.

All glass shall conform to ASTM Designation: C 1036 and the classifications specified herein and shall be clear glass except as noted.

Safety glass shall be furnished and installed at all locations designated in Consumer Product Safety Commission's Safety Standard For Architectural Glazing Materials 16 CFR 1201.

SUBMITTALS.—

A detailed list of glazing materials including glass, sheet, sealants, tapes, setting blocks, shims, compression seals, and glazing channels shall be submitted for approval. The list shall include a schedule of the materials to be used at each location.

LABELS.—

Each individual pane of heat strengthened or fully tempered glass shall bear an identification label in accordance with ASTM Designation: C 1048.

PART 2.- PRODUCTS

Sheet glass, float glass, or plate glass.--

Sheet glass, float glass, or plate glass shall be Type I, Class 1, Quality q4 or better, double strength for panes to 0.93 m², 5 mm thick for panes between 0.93 m² and 2.6 m², and 6 mm thick for panes over 2.6 m², except as otherwise shown on the plans.

Obscure glass.--

Obscure glass shall be Type II, Class 1, Form 3, Quality q8, Finish f1, Pattern p1 or p2; 3 mm thick flat figured glass, one surface smooth, other surface fine grid pattern.

Safety glass.--

Safety glass shall conform to Consumer Product Safety Commission Safety Standard For Architectural Glazing Materials: 16 CFR 1201, and ANSI Standard Z97.1 and shall be one of the following:

Tempered glass.--

Tempered glass shall conform to ASTM Designation: C 1048, Kind FT, Condition A, Type 1, Quality q4 or better.

Wire glass.--

Wire glass shall be Type II, Class 1, Form 1, Mesh m1; 6 mm thick clear polished wire glass with diamond mesh.

Tinted glass.--

Tinted glass shall be bronze; all the same tint.

Insulating glass assemblies.--

Insulating glass assemblies shall be double pane units consisting of 2 pieces of glass separated by a spacer and hermetically sealed with double seal sealants. The entrapped air shall be at atmospheric pressure and maintained in a hydrated condition by a drying agent located in the spacer.

Seals, caulks, putties, setting blocks, shims, tapes, compression seals, felt, spacers, and channels.--

Seals, caulks, putties, setting blocks, shims, tapes, compression seals, felt, spacers, and channels shall be top grade, commercial quality, as recommended by the glass or sheet manufacturer and shall conform to the requirements in the publications of the Flat Glass Marketing Association.

PART 3.- EXECUTION

INSTALLATION.—

Glazing shall conform to the general conditions and applicable details in the publications of the Flat Glass Marketing Association.

Cut edges of tinted glass shall conform to the recommendations of the glass manufacturer. The glazier shall inspect each edge of tinted glass. Panes with edges that do not conform to the manufacturer's standards for tinted glass edges for sunny elevations shall not be used.

Panels shall be bedded fully and evenly, set straight and square within panels in such a manner that the pane is entirely free of any contact with metal edges and surfaces.

For all panes on the exterior of the building, the glazing on both sides of window panes shall provide a watertight seal and watershed. Seals shall extend not more than 2 mm beyond the holding members. A void shall be left between the vertical edges of the panes and the glazing channel. Weep systems shall be provided to drain condensation to the outside.

Panels in assemblies using extruded gasket glazing shall be set in accordance with the assembly manufacturer's instructions using gaskets and stops supplied by the manufacturer.

Whenever welding or burning of metal is in progress within 4.6 m of glazing materials, a protective cover shall be provided over exposed surfaces.

REPLACEMENT AND CLEANING.—

All broken or cracked glass and glass with scratches which reduce the strength shall be replaced before completion of the project.

Panes shall be kept clean of cement and plaster products, cleansers, sealants, tapes and all other foreign material that may cause discoloration, etching, staining, or surface blemishes to the materials.

Excess sealant left on the surface of the glass or surrounding materials shall be removed during the work life of the sealant.

Solvents and cleaning compounds shall be chemically compatible with materials, coatings and glazing compounds to remain. Cleaners shall not have abrasives that scratch or mar the surfaces.

All panes shall be cleaned just before the final inspection. All stains and defects shall be removed. Paint, dirt, stains, labels (except etched labels), and surplus glazing compound shall be removed without scratching or marring the surface of the panes or metal work.

SECTION 12-9. FINISHES

12-9.01 GYPSUM WALLBOARD

PART 1.- GENERAL

This work shall consist of furnishing, installing and finishing gypsum wallboard in accordance with the details shown on the plans and these special provisions.

Where assembly fire ratings are indicated on the plans, construction shall provide the fire resistance in accordance with the applicable standards in the Fire Resistance Design Manual published by the Gypsum Association.

Wallboard backing for use in restroom and shower areas shall be water-resistant gypsum backing board.

PART 2.- PRODUCTS

Gypsum wallboard.--

Gypsum wallboard shall conform to ASTM Designation: C 36/C 36M.

Water-resistant gypsum backing board.--

Water-resistant gypsum backing board shall conform to ASTM Designation: C 630/C C 630M.

Joint tape and joint and finishing compound.--

Joint tape and joint and finishing compound shall conform to ASTM Designation: C 475.

Corner beads, metal trim and control joints.--

Corner beads, metal trim and control joints shall be galvanized steel of standard manufacture.

Fasteners.--

Fasteners shall be gypsum wallboard nails conforming to ASTM Designation: C 514 or steel drill screws conforming to ASTM Designation: C 1002.

PART 3.- EXECUTION

DELIVERY AND STORAGE.--Materials shall be delivered in original packages, containers or bundles bearing brand name, applicable standard of manufacture, and name of manufacturer or supplier and shall be kept dry and fully protected from weather and direct sunlight exposure. Gypsum wallboard shall be stacked flat with adequate support to prevent sagging or damage to edges, ends and surfaces.

INSTALLATION.--Wallboard panels to be installed on ceilings and soffits shall be installed with the long dimension of the panels perpendicular to the framing members. Wallboard panels to be installed on walls may be installed with the long dimension of the panels either parallel or perpendicular to the framing members. The direction of placing the panels shall be the same on any one wall or partition assembly.

Edges of wallboard panels shall be butted loosely together. All cut edges and ends shall be smoothed as needed for neat fitting joints.

All edges and ends of gypsum wallboard panels shall coincide with the framing members, except those edges and ends which are perpendicular to the framing members. End joints on ceiling and on the opposite sides of a partition assembly shall be staggered.

Except where closer spacings are shown on the plans, the spacing of fasteners shall not exceed the following:

Nails	175 mm
Screws	300 mm
Screws at perimeter of panels for fire resistive assemblies having metal framing	200 mm

Type W steel drill screws shall be used to fasten wallboard to wood framing.

Adhesives shall not be used for securing wallboard to framing.

Gypsum wallboard panels shall be fastened to all framing members except at the following locations:

At internal angles formed by ceiling and walls; ceiling panels shall be installed first with the fasteners terminating at a row 175 mm from the walls, except for walls parallel to ceiling framing. Wall panels shall butt the ceiling panels. The top row of wall panel fasteners shall terminate 200 mm from the ceiling.

At internal vertical angles formed by the walls; fasteners shall not be installed along the edge or end of the panel that is installed first. Fasteners shall be installed only along the edge or end of the panel that butts and overlaps the panel installed first.

Fasteners shall be located at least 10 mm from wallboard panel edges and ends. Nails shall penetrate into wood framing at least 30 mm. Screws shall penetrate into wood framing at least 20 mm. All metal fasteners shall be driven slightly below surface level without breaking the paper or fracturing the core.

Metal trim shall be installed at all free edges of panels, at locations where wallboard panels abut dissimilar materials and at locations shown on the plans. Corner beads shall be installed at external corners. Control joints shall be installed at the locations shown on the plans.

Joints between face panels, the internal angles formed by ceiling and walls and the internal vertical angles formed by walls shall be filled and finished with joint tape and at least 3 coats of joint compound. Tape in the corners shall be folded to conform to the angle of the corner. Tape at joints and corners shall be embedded in joint compound.

Dimples at nail and screw heads, dents, and voids or surface irregularities shall be patched with joint compound. Each patch shall consist of at least 3 coats and each coat shall be applied in a different direction.

Flanges of corner beads, control joints and trim shall be finished with a least 3 coats of joint compound.

Each coat of joint compound shall be feathered out onto the panel surface and shall be dry and lightly sanded before applying the next coat. The finished surfaces of joint compound at the panel joints, internal angles, patches and at the flanges of trim, corner beads and control joints shall be flat and true to the plane of the surrounding surfaces and shall be lightly sanded.

Good lighting of the work area shall be provided during the final application and sanding of the joint compound.

Surfaces of wallboard to be textured shall receive an orange peel texture, unless otherwise shown on the plans.

12-9.02 PORCELAIN CERAMIC TILE

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing porcelain ceramic tile in accordance with the details shown on the plans and these special provisions.

Ceramic tile shall include unglazed matte porcelain floor tile, setting materials, grouts and such other materials as may be required for a complete installation.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, a list of materials to be used, and installation instructions for all materials required for the work shall be submitted for approval.

Manufacturer's descriptive data shall be submitted for each type of tile, mortar bed materials, bond coat materials and additives, and grout materials and additives.

Materials list and installation instructions shall include all products and materials to be incorporated into the work. Friction reports shall be submitted for tile products to be used on floors and other pedestrian surfaces.

Samples.--Samples shall include 2 individual samples of each type and color of tile to be installed and shall be of the same size, shape, pattern and finish as the tile to be installed.

QUALITY ASSURANCE.--

Single source responsibility.--Each type and color of tile, grout and setting materials shall be obtained from a single source.

Master Grade Certificates.--Each shipment of tile to the project site shall be accompanied by a Master Grade Certificate issued by the tile manufacturer.

Certificates of Compliance.--Certificates of compliance shall be furnished for bond coat materials, setting bed materials and grout in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

DELIVERY, STORAGE AND HANDLING.--

Delivery.--Tile and packaged materials shall be delivered to the job site in sealed, unbroken, unopened containers with the labels intact. Tile containers shall bear the Standard Grade label.

Storage and handling.--Materials shall be stored and handled in such a manner as to prevent damage or contamination by water, freezing or foreign matter.

PROJECT CONDITIONS.--

Protection.--Tile work shall be protected and environmental conditions maintained during and after installation to comply with the reference standards and manufacturer's printed instructions.

Temperatures.--Unless otherwise specified in the manufacturer's installation instructions, the ambient temperature shall be maintained at not less than 10°C nor more than 38°C in tiled areas during installation and for 7 days after completion. Exterior work areas shall be shaded from direct sunlight during installation.

Tile shall not be installed when the temperature of the substrate is greater than 32°C or is frost covered.

Illumination.--Interior work areas shall be illuminated to provide the same level and angle of illumination as will be available during final inspection.

PART 2.- PRODUCTS

MANUFACTURERS.--

Available manufacture's.--Subject to compliance with the specifications, tile shall be American Olean Tile Co., Inc.; Summitville Tiles, Inc.; United States Ceramic Tile Co.; or equal.

GENERAL.--

Ceramic tile.--Ceramic tile shall conform to the requirements in ANSI Standard: A137.1, "American National Standard Specifications for Ceramic Tile" for types and grades of tile indicated.

Ceramic tile shall conform to the "Standard Grade" requirements.

Tile installation materials.--Tile installation materials shall conform to the requirements in ANSI standard referenced with products and materials indicated for setting and grouting.

Tile color and size.--Tile color shall be as shown on the plans.

TILE PRODUCTS.--

Unglazed matte porcelain tile.--

Unglazed matte porcelain tile shall be machine made, unpolished, dust pressed natural porcelain clay and shall have a plain face. Tile shall have a nominal thickness of 8 mm. Matte porcelain tile shall be slip resistant.

Unglazed matte porcelain trim tile shall include cove type base at walls and single piece intersecting cove base at corners.

SETTING MATERIALS.--

Portland cement mortar installation materials.--

Materials for portland cement mortar installation shall conform to the requirements in ANSI Standard: A108.1 as required for installation method designated, unless otherwise indicated.

Membrane.--Membrane shall be asphalt impregnated felt conforming to ASTM Designation: D 226, Type I, or polyethylene film conforming to ASTM Designation: C 171, Type 1.1.2. Polyethylene film shall not be less than 0.1 mm thick.

Reinforcement.--Reinforcement shall be galvanized welded wire fabric with 50 mm x 50 mm - 1.6 mm x 1.6 mm conforming to ASTM Designations: A 82 and A 185 except for minimum wire size. Reinforcement shall be provided in flat sheets.

Metal lath.--Metal lath shall be self furring, galvanized, conforming to ASTM Designation: C 847, flat expanded type weighing not less than 1.4 kg/m². Factory assembled metal lath and paper backing may be used where reinforcement over paper is shown on the plans.

Tile bond coat.--

Tile bond coat shall be latex-portland cement bond coat.

Latex-portland cement mortar bond coat shall be a prepackaged mortar mix, conforming to ANSI Standard: A118.4, incorporating a dry acrylic resin, and to which only water is added at the job site. Mortar shall be suitable for exterior use and be labeled for the type of tile to be installed.

Epoxy bond coat.--

Epoxy bond coat shall be a 2 part prepackaged epoxy mortar conforming to ANSI Standard: A118.3, suitable for exterior use. Mortar shall be labeled for the type of tile to be installed.

GROUTING MATERIALS.--

Tile grout.--

Tile grout shall be latex-portland cement grout.

Latex-portland cement grout shall be a prepackaged grout mix, conforming to ANSI Standard: A118.6, incorporating a dry acrylic resin, and to which only water is added at the jobsite. Grout shall be suitable for exterior use and labeled for the type of tile to be installed.

Epoxy grout.--

Epoxy grout shall be a 2 part prepackaged epoxy grout conforming to ANSI Standard: A118.3 and suitable for exterior use. Grout shall be labeled for the type of tile to be used.

Grout pigment.--

Grout pigment shall be chemically inert, fade resistant mineral oxide or synthetic type. Color shall be as shown on the plans.

SEALANTS.--

Sealant.--

Sealant for vertical expansion joints shall be a medium modulus silicone or polyurethane. Sealant for horizontal joints shall be a 2-part polyurethane type material with a Shore Hardness of 35 to 45.

Color of exposed sealants shall match color of grout in tile adjoining sealed joints.

MORTAR BEDS.--

Cement mortar bed.--

Cement mortar bed for floors shall be proportioned of one part cement, 1/10 parts hydrated lime, 5 parts damp sand by volume and only enough water added to provide the necessary workability. Ingredients shall be dry mixed, water added, and materials blended to produce a stiff mix. Mortar bed shall be not less than 32 mm in thickness.

MISCELLANEOUS MATERIALS.--

Sand.--

Sand shall be a natural or manufactured sand conforming to ASTM Designation: C 144, except that no more than 10 percent shall pass the No. 150 µm sieve.

Sealers.--

Sealer for unglazed quarry tile shall be water repellent, clear solution of ammonium cementitious compound, silicone base material, or other commercially manufactured sealer.

Sealer for grout shall be a penetrating proprietary compound designed for sealing grout. Silicone sealers shall not be used.

Cement.--

Cement shall conform to ASTM Designation: C 150, Type I.

Hydrated lime.--

Hydrated lime shall conform to ASTM Designation: C 206, Type S, or ASTM Designation: C 207, Type S.

Water.--

Water shall be clean and potable.

Metal edge strips.--

Metal edge strips shall be stainless steel terrazzo strips, 3 mm wide at top edge with integral provision for anchorage to mortar bed or substrate.

MIXING MORTAR AND GROUT.--

Mixing.--Mortar and grout shall be mixed to comply with the requirements of referenced standards and manufacturers for accurately proportioning of materials, water or additive content, mixing equipment and mixer speeds, mixing containers, mixing time, and other procedures need to produce mortars and grout of uniform quality with optimum performance characteristics for application intended.

PART 3.- EXECUTION

PREPARATION.--

General.--Surfaces to receive a mortar setting bed or a bond coat shall be cleaned adequately to assure a tight bond to the applied material. Such cleaning shall leave the surface thoroughly roughened and free from laitance, coatings, oil, sand, dust and loose particles.

The cleaned surfaces which are to receive a mortar bed shall be saturated with water just prior to placing mortar or the cleaned surfaces shall be coated with fresh neat cement slurry. If the surface is saturated with water, excess water shall be removed and the wetted surfaces uniformly dusted with portland cement. The slurry or wetted cement dust shall be broomed to completely coat the surface with a thin and uniform coating just prior to placing the mortar.

Substrates shall be inspected to insure that grounds, anchors, plugs, recessed frames, bucks, drains, electrical work, mechanical work, and similar items in or behind the tile have been installed before proceeding with installation of the tiles.

INSTALLATION.--

General.--Tile installation shall conform to applicable parts of ANSI 108 Series of the tile installation standards included under "American National Standard Specifications for the Installation of Ceramic Tile" and Tile Council of American, "Handbook for Ceramic Tile Installation."

All tile shall be installed on a bond coat over a setting bed. The setting bed shall be a cured cement mortar bed or a prepared, dimensionally stable substrate of concrete, masonry, cementitious backer board, or other cementitious material.

The back face of the tile shall be free of paper, adhesives, fiber mesh, resins, or other materials affecting the bond of the tile to the bedding material.

Tile sheets shall have permanent edge bonding or temporary mounting materials on the exposed face. Water soluble or absorbent adhesives shall not be used for edge bonding. Temporary mounting materials shall allow observation during tile setting operations.

Tile work shall extend into recesses and under or behind equipment and fixtures, to form a complete covering without interruptions, except as shown on the plans. Work shall be terminated neatly at obstructions, edges and corners without disrupting pattern or joint alignments.

Intersections and returns shall be accurately formed. Cutting and drilling of tile shall be performed without marring visible surfaces. Cut edges of tile abutting trim, finish or built-in items shall be carefully ground to produce straight aligned joints. Tile shall be closely fit to electrical outlets, piping, fixtures and other penetrations such that plates, collars, or covers overlap the tile.

Mortar bed placement.--The mortar bed, with or without reinforcement as shown on the plans, shall be placed, consolidated, and finished to the required thickness.

The surface of the mortar bed shall be true and pitched as shown on the plans, without high or low spots. The mortar bed surface shall not vary more than 3 mm in 2.4 m from a plane parallel to the finished tile surface when tile is installed on a cured mortar bed.

In no case shall the allowed tolerances result in offsets between adjoining tiles, low spots on finished tile surfaces that can pond water, or finished tile surfaces that are not plumb or not true.

Tile bond coat.--The tile bond coat mortar shall be mixed according to the manufacturer's recommendations. The consistency of the mixture shall be such that ridges formed with the recommended notched trowel shall not flow or slump. Reworking will be allowed provided no water or materials are added. The setting bed surfaces shall be dampened before placing the bond coat as necessary tile installation, but the setting bed shall not be soaked. The setting bed surfaces for epoxy bond coat shall be dry.

The bond coat shall be floated onto the cured mortar bed surface with sufficient pressure to cover the surface evenly with no bare spots. The surface area to be covered with the bond coat shall be no greater than the area that can be tiled while the bond coat is still plastic. The bond coat shall be combed with a notched trowel as recommended by the manufacturer within 10 minutes before installing tile. Tile shall not be installed on a skinned over bond coat.

Installing tiles.--Tile shall be installed in accordance with the manufacturer's instructions and shall be set solid and shall be well bonded to the substrate.

Tile set on a tile bond coat shall be installed in accordance with ANSI Standard: A108.5, and tile set on an epoxy mortar shall be installed in accordance with ANSI Standard: A108.6.

If tiles are cut, the cuts shall be made with saws. Cut edges shall be rubbed with an abrasive stone to bring the edge of the glaze slightly back from the body of the tile. Cuts shall be accurately made to neatly fit the tile in place. Cut edges shall not be butted against other tile. Cut tile shall be at least half the size of a full size tile.

Tile shall completely cover wall areas behind mirrors and fixtures.

Tile shall be installed so that the finished tile surface does not vary more than 3 mm in 2.4 m from the finished tile surface shown on the plans. In no case shall there be offsets in adjoining tiles, low spots on finished tile surfaces that can pond water, or finished tile surfaces that are not plumb or true in the completed tile work.

Tiles shall be firmly pressed into the freshly notched bond coat. Tile on interior surfaces shall be tapped and beat into a true surface and to obtain at least 80 percent coverage by the mortar on the back of each tile. Tile on exterior surfaces shall have 100 percent coverage and shall be back-buttered immediately prior to setting the tile.

Mortar that exudes into the grout spaces between tiles shall be removed to the bottom of tile.

Joints.--Joints between tile shall be continuous both vertically and horizontally. Joints shall be straight and of uniform and equal width. Where tiles on adjoining surface are the same size, the joints shall align, one with the other. Joint width shall be as recommended by the tile manufacturer.

Grouting tile.--Grout shall be mixed, applied and cured in accordance with the manufacturer's recommendations and ANSI Standard: A108.10 for cement grout and ANSI Standard: A108.9 for epoxy grout.

Spacers, strings, ropes, pegs, glue, paper, and face mounting material shall be removed before grouting. Joints between glazed wall tile shall be wetted if they have become dry. Joints for epoxy mortar shall be dry.

Grouting shall not begin until at least 48 hours after installing tile.

A maximum amount of grout shall be forced into the joints between tiles in accordance with the manufacturer's recommendations. The grout shall be finished to the depth of the cushion for cushion edge tile and finished flush with the surface for square edge tile. All gaps and skips in the grout spaces shall be filled.

Mortar or mounting mesh shall not show through the grouted joints.

The finished grout shall have a uniform color and shall be smooth without voids, pinholes or low spots.

Expansion joints shall be kept free of grout or mortar.

Grout shall be protected from freezing or frost for a least 5 days after installation.

Expansion joints.--Expansion joints shall be installed at the perimeter of all tile floors and at all substrate control joints and changes in the substrate material. Exterior expansion joint spacing shall not exceed 5 m in any direction.

All expansion joints shall be made with sealant over backer rods. The thickness of sealant at the center of expansion joints shall not exceed the width of the joint. Joint edges shall be primed as recommended by the sealant manufacturer.

Edge strips.--Edge strips shall be installed at openings where the threshold has not been shown on the plans, but where tile floor abuts other flooring materials at the same level. Edge strips shall be installed centered under the closed door, or where there is no door, centered in the opening.

Sounding tile.--Tiled surfaces shall be sounded with a metal bar or chain for improperly bonded tile or setting bed. Tile or setting bed that emits a hollow sound shall be replaced.

Replacement.--Cracked, chipped, broken, or otherwise defective tiles shall be removed and replaced. All tiles which differ more than 2 mm in elevation from adjacent tile edges shall be removed and replaced.

Curing.--After the installation of tile and the grouting of joints, the tile and grout shall be cured by keeping the surface continuously damp for at least 72 hours after grouting. Curing materials shall not stain the tile or grouted joints. Curing methods shall not erode away the grout.

After grouting, horizontal tiled surfaces shall be closed to traffic, and all tiled surfaces shall be kept free from impact, vibration or shock, for at least 72 hours.

CLEANING AND PROTECTION.--

Cleaning tile surfaces.--All exposed tile surfaces shall be cleaned of all grout haze upon completion of grouting. Acids and chemicals used to clean tile shall conform to the tile manufacturer's recommendations. Cleaners shall not be harmful to materials on surfaces of abutting floors, walls, and ceilings. Tile work shall be rinsed thoroughly with clean water before and after using acid or chemical cleaners. After cleaning and rinsing, tile surfaces shall be polished using a soft cloth.

Tile work shall be cleaned and polished again immediately prior to completion of the contract. All dirt, grime, stains, paints, grease, and other discoloring agents or foreign materials shall be removed.

Protection.--After grouting, horizontal tiled surfaces shall be closed to traffic, and all tiled surfaces shall be kept free from impact, vibration or shock, for at least 72 hours after.

Tile surfaces damaged by construction operations shall be retiled.

SCHEDULES.--

Floor tile.--

Floor tile shall be nominal 51 mm x 51 mm unglazed matte porcelain tile installed on a mortar bed using a tile bond coat and grout and shall conform to the requirements of Method F 112, "Handbook for Ceramic Tile Installation."

12-9.03 RUBBER BASE

PART 1.- GENERAL

This work shall consist of furnishing and installing rubber base in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions, color palette, and samples of rubber base shall be submitted for approval. Samples shall be not less than 50 mm in length.

PART 2.- PRODUCTS

Rubber base.--

Resilient base shall be manufacturer's best grade, rubber with premolded internal and external corner pieces. The height and color shall be as shown on the plans.

Adhesive.--

Adhesive shall be as recommended by base manufacturer.

PART 3.- EXECUTION

INSTALLATION.--Bases shall be firmly and totally attached to walls with adhesive and shall be accurately scribed to trim, molding and cabinets. All joints shall be tight fitting. Bases between premolded corners or other termini may be installed continuous or installed using one m minimum standard manufactured lengths. Filler pieces shall be not less than 0.5 m.

12-9.04 VINYL COMPOSITION TILE

PART 1.- GENERAL

This work shall consist of furnishing and installing vinyl composition tile in accordance with the details shown on the plans and these special provisions.

Vinyl composition tile shall consist of vinyl composition tile, edger strips, floor wax and tile manufacturer's recommended primers and adhesives.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions, color and pattern samples shall be submitted for approval. Samples of tile shall be 305 mm x 305 mm in size.

PART 2.- PRODUCTS

Vinyl composition tile.--

Vinyl composition tile shall be semi-flexible, 2.38 mm minimum thick, 305 mm x 305 mm tile conforming to Federal Specification: SS-T-312, Type IV. Color and pattern shall be as shown on the plans.

Primer, leveling compound crack filler and adhesives.--

Primer, leveling compound crack filler and adhesives shall be waterproof types as recommended by the tile manufacturer.

Wax.--

Wax shall be water emulsion, self-polishing type containing not less than 16 percent wax solids, wetting agents, and a nonslip agent. The wax shall meet UL antislip standards.

Edger strips.--

Edger strips shall be commercial quality, stainless steel or aluminum.

PART 3.- EXECUTION

PREPARATION.--Before placing adhesives, all surfaces to receive vinyl composition tile shall be made free of localized depressions or bumps. Bumps shall be ground flat. Holes, depressions and cracks shall be filled with crack filler or leveling compound.

Immediately prior to application of the tile flooring, the surface to be covered shall be thoroughly dry, free of paint, oil, grease, mortar, plaster droppings, scaly surfaces or other irregularities and shall be broom clean. Primer, when recommended, shall be thoroughly brushed on the surface at the rate recommended by the adhesive manufacturer and shall be completely dry before the application of adhesives.

The rooms where tile is to be installed shall be maintained at a temperature of at least 21°C for not less than 72 hours before installation, during installation and for 5 days after installation.

APPLICATION.--Tile shall be laid to a true, straight, smooth and even finished surface in accordance with the manufacturer's instructions. Joints shall be tight fitting. Floor covering shall be placed before floor mounted fixtures are installed. After tile has been set, the finished surface shall be rolled and crossrolled with a roller weighing 50 kg or more.

Edger strips shall be installed at free edges.

Where tile patterns between rooms differ, the pattern break at openings shall occur at the centerline of the common wall.

Upon completion of the tile application, all stains, surplus adhesive, dirt and debris resulting from the work shall be removed and the floor left broom clean. Tile shall be protected from damage at all times during construction. As a last order of work, tile shall be washed with soap and warm water, rinsed, and then waxed in accordance with the tile manufacturer's printed instructions. Not less than 2 applications of wax shall be placed on the tile flooring.

12-9.05 RESILIENT SHEET FLOORING**PART 1.- GENERAL**

This work shall consist of furnishing and installing resilient sheet flooring in accordance with the details shown on the plans and these special provisions.

Resilient sheet flooring shall also include cove molding, metal caps, edger strips, floor wax and flooring manufacturer's recommended primers and adhesives.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions, color and pattern samples shall be submitted for approval. Samples of sheet flooring shall be 305 mm x 305 mm in size.

PART 2.- PRODUCTS**Resilient sheet flooring.--**

Resilient sheet flooring shall be flexible vinyl sheet not less than 2 mm thick. Color and pattern shall be as shown on the plans.

Primer, leveling compound crack filler and adhesives.--

Primer, leveling compound crack filler and adhesives shall be waterproof types as recommended by the flooring manufacturer.

Wax.--

Wax shall be water emulsion, self-polishing type containing not less than 16 percent wax solids, wetting agents, and a nonslip agent. The wax shall meet UL antislip standards.

Cove molding.--

Cove molding shall be commercial quality wood, rubber or plastic.

Edger strips.--

Edger strips shall be commercial quality, stainless steel or aluminum.

Metal caps.--

Metal caps shall be commercial quality, noncorrosive metal.

PART 3.- EXECUTION

PREPARATION.--Before placing adhesives, all surfaces to receive resilient sheet flooring shall be made free of localized depressions or bumps. Bumps shall be ground flat. Holes, depressions and cracks shall be filled with crack filler or leveling compound.

Immediately prior to installation of the resilient sheet flooring, the surface to be covered shall be thoroughly dry, free of paint, oil, grease, mortar, plaster droppings, scaly surfaces or other irregularities and shall be broom clean. Primer, when recommended, shall be thoroughly brushed on the surface at the rate recommended by the adhesive manufacturer and shall be completely dry before application of adhesives.

The rooms where resilient sheet flooring is to be installed shall be maintained at a temperature of at least 21°C for not less than 72 hours before installation, during installation and for 5 days after installation.

INSTALLATION.--Resilient sheet flooring shall be laid to a true, straight, smooth and even finish surface in accordance with the manufacturer's instructions. Resilient sheet flooring shall be laid parallel to building lines with the minimum of seams using manufacturer's standard widths. Seams shall be tight fitting, fully bonded along their length and present a continuous pattern.

Resilient sheet flooring shall be placed before floor mounted fixtures are installed.

After resilient sheet flooring has been installed, the finished surface shall be rolled and crossrolled with a roller weighing 50 kg or more.

Edger strips shall be installed at free edges.

Upon completion of the flooring installation, all stains, surplus adhesive, dirt and debris resulting from the work shall be removed and the floor left broom clean. Resilient sheet flooring shall be protected from damage at all times during construction. As a last order of work, floor covering shall be washed with soap and warm water, rinsed, and then waxed in accordance with the floor covering and wax manufacturers' printed instructions. Not less than 2 applications of wax shall be placed on the floor covering.

12-9.06 PAINTING**PART 1.- GENERAL**

SUMMARY.--This work shall consist of preparing surfaces to receive coatings, and furnishing and applying coatings, in accordance with the schedules and details shown on the plans, and these special provisions.

The coatings specified in this section are in addition to any factory finishes, shop priming, or surface treatment specified elsewhere in these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, a materials list, and color samples shall be submitted for approval.

Product descriptive data shall include product description, manufacturer's recommendations for product mixing, thinning, tinting, handling, site environmental requirements, product application and drying time.

Materials list shall include manufacturer's name, trade name, and product numbers for each type coating to be applied.

Color samples shall be manufacturer's color cards, approximately 50 mm x 75 mm, for each color of coating shown on the plans. Color samples for stains shall be submitted on wood of the same species, color, and texture as the wood to receive the stain.

CLOSEOUT SUBMITTALS.--The Contractor shall submit to the Engineer an additional minimum of 8 liters of paint of each color and finish used in this project.

REGULATORY REQUIREMENTS.--Coatings and applications shall conform to the rules for control of volatile organic compound emissions adopted by the air quality control district in the air basin in which the coatings are applied.

SITE ENVIRONMENTAL REQUIREMENTS.--Coatings shall not be applied when the air temperature is below 10°C (20°C for varnishes) or when the relative humidity exceeds 75 percent.

The surface to be coated shall be maintained at a minimum temperature of 7°C for a period of 24 hours prior to, and 48 hours after the application of the coating. Heating facilities shall be provided when necessary.

Continuous ventilation shall be provided during application of the coatings.

A minimum lighting level of 865 lux, measured 1 m from the surface to be coated, shall be provided while surfaces are being prepared for coatings and during coating applications.

DELIVERY, STORAGE, AND HANDLING.--Products shall be delivered to the site in sealed, labeled containers and stored in a well ventilated area at an ambient air temperature of not less than 7°C. Container labeling shall include manufacturer's name, type of coating, trade name, color designation, drying time, and instructions for tinting, mixing, and thinning.

MAINTENANCE STOCK.--Upon completion of coating work, a full 3.8 liter container of each type and color of finish coat and stain used shall be delivered to the location at the project site designated by the Engineer. Containers shall be tightly sealed and labeled with color, texture, and room locations where used, in addition to the manufacturer's standard product label.

PART 2.- PRODUCTS

GENERAL.--The products shall be the best quality grade coatings of the specified types as regularly manufactured by nationally recognized paint and varnish manufacturers that have not less than 10 years experience in manufacturing paints and varnishes. Products that do not bear the manufacturer's identification as the best quality grade product shall not be used. Products for each coating system shall be by a single manufacturer and shall not contain lead type pigments.

Thinners, shellac, fillers, patching compounds, coloring tint, and other products required to achieve the specified finish shall be the manufacturer's best quality and shall be used as recommended.

PART 3.- EXECUTION

INSPECTION.--Surfaces to be coated at the jobsite shall be approved by the Engineer prior to the application of coatings. The Contractor shall notify the Engineer at least 3 working days prior to the application of coatings.

SURFACE PREPARATION.--Surfaces scheduled to be coated shall be prepared in accordance with the following, except that the surfaces not specified herein shall be prepared as recommended by the coating manufacturer.

GENERAL.--Hardware, cover plates, light fixture trim, and similar items shall be removed prior to preparing surfaces for coating. Following the application of the finish coating, the removed items shall be reinstalled in their original locations.

WOOD.--Oil and grease shall be removed by solvent wash. Mildew shall be removed by mildew wash. Surfaces to be coated shall be cleaned of all dirt, excess material, or filler by hand cleaning. Smooth surfaced wood shall be sanded lightly.

A sealer composed of equal parts of shellac and alcohol shall be spot applied to knots, sap, pitch, tar, creosote, and other bleeding substances.

After the application of the prime coat, all nail holes, cracks, open joints, dents, scars, and surface irregularities shall be filled, hand cleaned, and spot primed to provide smooth surfaces for the application of finish coats.

Irregularities in wood surfaces to receive a transparent stain finish shall be filled and hand cleaned after the first coat of stain has been applied. The color of the filler shall match the color of the stained wood.

Irregularities in wood surfaces to receive a clear finish shall be filled and hand cleaned before the application of coatings. The color of the filler shall match the color of the coated wood.

GALVANIZED METAL.--Oils, grease, and fabrication lubricants shall be removed by solvent wash. Surfaces shall be cleaned of remaining surface treatments by hand cleaning. New surfaces shall be roughened by hand cleaning or light abrasive blasting.

Abraded or corroded areas shall be hand cleaned and spot coated with one coat of vinyl wash pretreatment. Abraded or corroded areas on new surfaces not scheduled to be painted shall be cleaned by solvent wash, hand cleaned, and given 2 spot applications of zinc rich paint.

STEEL AND OTHER FERROUS METALS.--Oils, grease, and fabrication lubricants shall be removed by solvent wash. Dirt, water soluble chemicals, and similar surface contamination shall be removed by detergent wash or steam cleaning. Mill scale and rust shall be removed by hand cleaning or abrasive blasting.

ALUMINUM AND OTHER NON-FERROUS METALS.--Oils, grease, and fabrication lubricants shall be removed by solvent wash. Dirt, water soluble chemicals, and similar surface contamination shall be removed by detergent wash.

GYPSUM BOARD.--Holes, cracks, and other surface imperfections shall be filled with joint compound or suitable filler prior to application of coatings. Taped joints and filled areas shall be hand sanded to remove excess joint compound and filler.

SHOP PRIMED SURFACES.--Dirt, oil, grease, or other surface contaminants shall be removed by water blasting, steam cleaning, or TSP wash. Minor surface imperfections shall be filled as required for new work. Mildew shall be removed by mildew wash. Chalking paint shall be removed by hand cleaning. The surfaces of existing hard or glossy coatings shall be abraded to dull the finish by hand cleaning or light abrasive blasting. Abrasive blasting shall not be used on wood or non-ferrous metal surfaces.

DEFINITIONS.--

DETERGENT WASH.--Removal of dirt and water soluble chemicals by scrubbing with a solution of detergent and water, and removal of all solution and residues with clean water.

HAND CLEANING.--Removal of dirt, loose rust, mill scale, excess base material, filler, aluminum oxide, chalking paint, peeling paint, or paint which is not firmly bonded to the surfaces by using hand or powered wire brushes, hand scraping tools, power grinders, or sandpaper and removal of all loose particles and dust prior to coating.

MILDEW WASH.--Removal of mildew by scrubbing with a solution of detergent, hypochlorite-type household bleach, and warm water, and removal of all solution and residues with clean water.

ABRASIVE BLASTING.--Removal of oil, grease, form release agents, paint, dirt, rust, mill scale, efflorescence, weak concrete, or laitance, by the use of airborne abrasives, and removal of loose particles, dust, and abrasives by blasting with clean air.

Abrasives shall be limited to clean dry sand, mineral grit, steel grit, or steel shot, and shall be graded to produce satisfactory results. Unwashed beach sand containing salt or silt shall not be used.

Abrasive blasting shall conform to the requirements of SSPC-SP6-85, Commercial Blast Cleaning, as defined in the Steel Structures Painting Council Manual.

Light abrasive blasting shall conform to the requirements of SSPC-SP7-85, Brush-Off Blast Cleaning, as defined in the Steel Structures Painting Council Manual.

SOLVENT WASH.--Removal of oil, grease, wax, dirt, or other foreign matter by using solvents, such as mineral spirits or xylol, or other approved cleaning compounds.

STEAM CLEANING.--Removal of oil, grease, dirt, rust, scale, or other foreign matter by using steam generated by commercial steam cleaning equipment, from a solution of water and steam cleaning compounds, and removal of all residues and cleaning compounds with clean water.

TSP WASH.--Removal of oil, grease, dirt, paint gloss, and other foreign matter by scrubbing with a solution of trisodium phosphate and warm water, and removal of all solution and residues with clean water.

WATER BLASTING.--High pressure, low volume water stream for removing dirt, light scale, chalking or peeling paint. Water blasting equipment shall produce not less than a 13 800 MPa minimum output pressure when used. Heated water shall not exceed 66°C. If a detergent solution is used, it shall be biodegradable and shall be removed from all surfaces with clean water.

PROTECTION.--The Contractor shall provide protective devices, such as tarps, screens or covers, as necessary to prevent damage to the work and to other property or persons from all cleaning and painting operations.

Paint or paint stains on surfaces not designated to be painted shall be removed by the Contractor at his expense and the original surface restored to the satisfaction of the Engineer.

APPLICATION.--

GENERAL.--Coatings shall be applied in accordance with the printed instructions and at the application rates recommended by the manufacturer to achieve the dry film thickness specified in these special provisions.

Mixing, thinning and tinting shall conform to the manufacturer's printed instructions. Thinning will be allowed only when recommended by the manufacturer.

Coatings shall be applied only when surfaces are dry and properly prepared.

Cleaning and painting shall be scheduled so that dust and other contaminants from the cleaning process will not fall on wet, newly coated surfaces.

Materials required to be coated shall have coatings applied to all exposed surfaces, including the tops and bottoms of wood and metal doors, the insides of cabinets, and other surfaces not normally visible from eye level.

APPLICATION SURFACE FINISH.--Each coat shall be applied to a uniform finish. Finished surfaces shall be free of surface deviations and imperfections such as skips, cloudiness, spotting, holidays, laps, brush marks, runs, sags, curtains, ropiness, improper cutting in, overspray, drips, ridges, waves, and variations in color and texture.

Each application of a multiple application finish system shall closely resemble the final color coat, except each application shall provide enough contrast in shade to distinguish the separate applications.

WORK REQUIRED BETWEEN APPLICATIONS.--Each application of material shall be cured in accordance with the coating manufacturer's recommendations before applying the succeeding coating. Enamels and clear finishes shall be lightly sanded, dusted, and wiped clean between applications.

Stain blocking primer shall be spot applied whenever stains bleed through the previous application of a coating.

TIMING OF APPLICATIONS.--The first application of the specified coating system shall be applied prior to any deterioration of the newly prepared surface. Metal surfaces shall be prepared and prime coated the same day that cleaning of bare metal is performed. Additional prime coats shall be applied as soon as drying time of the preceding coat permits.

Metal surfaces shall be prime coated within 12 hours of application of vinyl wash pretreatment.

Shellac sealer shall be allowed to dry at least 12 hours before applying the next coat.

Drying time between applications of water borne coatings shall be at least 12 hours.

APPLICATION METHODS.--Coatings shall be applied by brush, roller or spray. Rollers shall be of a type which do not leave a stippled texture in the paint film. Extension handles for rollers shall not be greater than 2 m in length.

If spray methods are used, surface deviations and imperfections such as, overspray, thickness deviations, lap marks, and orange peel shall be considered as evidence that the work is unsatisfactory and the Contractor shall apply the remainder of the coating by brush or roller, as approved by the Engineer.

DRY FILM THICKNESS.--

Vinyl wash pretreatment	0.007 mm to 0.13 mm, maximum.
Bituminous paint	0.1 mm, minimum.
Other primers, undercoats, sealers, and coatings	As recommended by the manufacturer.

BACKPRIMING.--The first application of the specified coating system shall be applied to all wood surfaces (face, back, edges, and ends) of wood materials that are not factory coated, immediately upon delivery to the project site, except surfaces of interior finish woodwork that adjoin concrete or masonry shall be coated with one application of alkyd exterior wood primer before installation.

When clear or stain type coatings are required on millwork, trim, or paneling, varnish, reduced 25 percent by mineral spirits, shall be used for coating the back faces.

All primed metal surfaces in contact with concrete or concrete block exterior walls shall be coated with a bituminous paint on those surfaces in contact with the wall.

FINISHING MECHANICAL AND ELECTRICAL COMPONENTS.--Shop primed mechanical and electrical components shall be finish coated in accordance with the coating system entitled, "Shop Primed Steel." Louvers, grilles, covers, and access panels on mechanical and electrical components shall be removed and coated separately.

Interior surfaces of air ducts which are visible through grilles or louvers shall be coated with one application of flat black enamel, to limit of the sight line.

Exposed conduit, piping, and other mechanical and electrical components visible in public areas shall be painted.

Both sides and all surfaces, including edges and back of wood mounting panels for electrical and telephone equipment shall be finish coated before installing equipment.

CLEANING.--Upon completion of all operations, the coated surfaces shall be thoroughly cleaned of dust, dirt, grease, or other unsightly materials or substances.

Surfaces marred or damaged as a result of the Contractor's operations shall be repaired, at his expense, to match the condition of the surfaces prior to the beginning of the Contractor's operations.

COATING SYSTEMS.--The surfaces to be coated shall be as shown on the plans and as specified elsewhere in these special provisions. When a coating system is not shown or specified for a surface to be finish coated, the coating system to be used shall be as specified for the substrate material. The number of applications specified for each coating system listed herein is a minimum. Additional coats shall be applied if necessary to obtain a uniform color, texture, appearance, or required dry film thickness.

SYSTEM 1- ALUMINUM AND OTHER NON-FERROUS METALS.--

1 pretreat coat: vinyl wash pretreatment
1 prime coat: aluminum primer
2 finish coats: acrylic, exterior enamel, semi-gloss

SYSTEM 2- GALVANIZED METAL.--

1 pretreat coat: vinyl wash pretreatment
1 prime coat: galvanized metal primer
2 finish coats: acrylic, exterior enamel, semi-gloss

SYSTEM 3- GYPSUM BOARD.--

1 prime coat: PVA wall sealer
2 finish coats: acrylic, interior enamel, semi-gloss

SYSTEM 4- SHOP PRIMED STEEL.--

1 prime coat : red oxide ferrous metal primer
2 finish coats: alkyd, exterior enamel, semi-gloss

SYSTEM 5- STEEL AND OTHER FERROUS METALS.--

2 prime coats: red oxide ferrous metal primer
2 finish coats: alkyd, exterior enamel, semi-gloss

SYSTEM 6- WOOD, PAINTED.--

1 prime coat: alkyd, exterior wood primer
2 finish coats: acrylic, exterior enamel, semi-gloss

COLOR SCHEDULE.--Colors shall be as shown on the plans.

12-9.07 FIBERGLASS REINFORCED PLASTIC PANELS

PART 1.- GENERAL

This work shall consist of furnishing and installing fiberglass reinforced plastic (FRP) panels and trim molding in accordance with details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions, and finish options shall be submitted for approval.

Product descriptive data shall show the manufacturer's name and shall indicate conformance to these special provisions.

Installation instructions shall show the FRP panel manufacturer's recommended method of installation.

Finish options shall show the manufacturer's standard color palette for FRP panels and trim molding. Color shall be as shown on the plans.

PART 2.- PRODUCTS

FRP panel.--

FRP panel shall be Class I flame-spread, minimum nominal thickness of 2 mm; Marlite, Class A/I FRP; Kemlite, Fire-X Glasbord; or equal.

Trim molding.--

Trim molding shall be manufacturer's standard vinyl molding with nailing flanges and a 9 mm deep channel of sufficient width to receive panels and sealant.

Adhesive and sealant.--

Adhesive and sealant shall be as recommended by the FRP panel manufacturer.

PART 3.- EXECUTION

INSTALLATION.--The FRP panels and trim molding shall be installed in accordance with the manufacturer's installation instructions.

Trim molding shall be nailed through the flange into solid wood backing. All nails shall be concealed by FRP panels in the completed installation. Trim shall be one continuous piece along each wall unless the wall length exceeds the manufacturer's standard trim length. If more than one piece is used on one wall, the pieces shall be approximately equal length, with no piece less than 1 m in length. All FRP panel edges shall be covered by a trim molding.

Panels shall be one continuous piece along each wall unless the wall length exceeds the manufacturer's standard panel length. If more than one panel piece is used on one wall, the pieces shall be approximately equal length, with no piece less than one meter in length.

CLEAN-UP.--Adjacent surfaces shall be protected from adhesive or sealant. Excess adhesive and sealant shall be removed as the installation progresses using a solvent or cleaning agent recommended by the FRP panel manufacturer.

SECTION 12-10. SPECIALTIES

12-10.01 TACKBOARDS

PART 1.- GENERAL

This work shall consist of furnishing and installing tackboards in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, color and texture samples and installation instructions shall be submitted for approval.

PART 2.- PRODUCTS

Tackboards.--

Tackboards shall be textured plastic coating on cotton-fabric, pressure laminated to 6 mm thick cork underlayment. Cork underlayment shall be bonded to a 6 mm thick hardboard backing. Tackboard dimensions shall be 1830 mm x 1220 mm.

Border moldings.--

Border moldings shall be factory applied, extruded clear anodized aluminum trim.

PART 3.- EXECUTION

INSTALLATION.--Tackboards shall be installed rigidly, securely, plumb and true, and in accordance with the manufacturer's recommendations.

12-10.02 MARKER BOARDS

PART 1.- GENERAL

This work shall consist of furnishing and installing a marker boards in accordance with the details shown on the plans and these special provisions.

One felt eraser and 12 felt tipped liquid chalk markers of assorted colors shall be furnished for each marker board installed.

SUBMITTALS.--Manufacturer's descriptive data and installation instructions shall be submitted for approval.

PART 2.- PRODUCTS

Marker board.--

Marker board shall conform to Porcelain Enamel Institute Standard PEI-S-104, and shall be porcelain enamel surface on 0.61 mm thick (24-gage) sheet steel pressure laminated to 6 mm thick tempered hardboard. Hardboard shall have a backing of 0.38 mm nominal thickness aluminum sheet. Enamel surface shall be suitable for marking with felt tipped liquid chalk markers and erasing with a felt eraser or dry cloth. The enamel surface shall be white in color.

Marker board dimensions shall be 1830 mm x 1220 mm.

Trim and marker tray.--

Trim and marker tray shall be factory installed, satin finish, clear anodized aluminum extrusions.

PART 3.- EXECUTION

INSTALLATION.--Marker boards shall be installed rigidly, securely, plumb and true in accordance with the manufacturer's instructions.

12-10.03 METAL TOILET PARTITIONS

PART 1.- GENERAL

This work shall consist of furnishing and installing metal toilet partitions in accordance with the details shown on the plans and these special provisions.

Metal toilet partitions shall consist of panels, doors, pilasters, urinal screens, fasteners, anchorages and hardware. Internal reinforcement shall be provided at all fasteners, anchorages, hardware and accessories.

Doors, panels, pilasters, and urinal screens shall have a factory applied, baked on enamel finish consisting of not less than one prime coat over a chemically pretreated base followed by at least one baked on enamel finish coat.

SUBMITTALS.--Manufacturer's descriptive data, standard color palette, installation instructions and working drawings shall be submitted for approval.

Colors will be selected from the manufacturer's standard color palette.

Working drawings shall show the plan layout, door and panel elevations and all details required for the complete installation and anchorage of the partition system.

PART 2.- PRODUCTS

Doors and panels.--

Doors and panels shall be flush, 25 mm minimum thickness, formed of two 0.86 mm (22-gage) minimum thickness, galvanized steel sheets over a honeycomb core. Doors and panels shall have formed edges sealed with a continuous oval crown locking strip, and shall be mitered, welded and finished at the corners.

Doors shall have controlled action hinges, with vertical pintle and ball bearing roller operating on adjustable cams, or moving parts of nylon and stainless steel. Top pivots shall be recessed into edges of doors.

Doors shall be provided with slide bar latch and a combination coat-hat hook and door stop, except as otherwise specified.

Doors on stalls designed for use by the disabled shall be provided with a grip and turn latch, combination coat-hat hook and door stop, and U-shaped door pulls immediately below the latch on the inside and outside of the door.

Pilasters.--

Pilasters shall be 32 mm thick, of the same construction as the doors and panels, except the galvanized face sheets shall be 1.0 mm (20-gage) minimum thickness, and shall have an adjustable, leveling base.

Urinal screens.--

Urinal screens shall be wall-mounted, and of the same construction as the doors and panels, except face sheets shall be 1.0 mm (20-gage) minimum thickness. All fasteners shall be concealed.

Fasteners and anchorages.--

Fasteners and anchorages shall be stainless steel with vandal resistant heads.

Hardware.--

Hardware shall be highly polished chromium plated, cast alloy, or heavy duty anodized aluminum.

Pilasters anchors.--

Pilasters anchors shall be integral stud anchor type or internally threaded expansion sleeve type with single cone expander. Self-drilling type anchorage shall not be used.

Pilaster shoes.--

Pilaster shoes shall be one-piece, stainless steel, with concealed hold down clips, and of sufficient height to completely cover the base and anchors.

PART 3.- EXECUTION

INSTALLATION.--Metal toilet partitions shall be installed rigidly, securely, plumb, and true and in accordance with the manufacturer's recommendations. Tops and bottoms of doors shall align with tops and bottoms of panels, and all horizontal lines shall be level.

Rigid backing shall be provided in walls to receive anchorages.

Panels shall be anchored with at least 3 brackets at each wall and pilaster. Two anchors shall be used to fasten each pilaster base to the floor.

Doors shall not bind during opening and closing. The clearance between the door edges and pilasters shall be uniform, equidistant, and shall not exceed 5 mm. Hinges shall be adjusted to hold doors ajar when unlatched. Doors on stalls designed for use by the disabled shall return to the closed position.

Drilling, cutting and fitting of wall and floor finishes shall be concealed by the completed installation.

CLEAN-UP.--Toilet partitions shall be cleaned, polished and free of all defects. Chipped, dented, scratched, or otherwise damaged work shall be replaced at the Contractor's expense.

12-10.04 LOUVERS

PART 1.- GENERAL

This work consists of furnishing and installing louvers in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data and installation instructions shall be submitted for approval.

PART 2.-PRODUCTS

Louvers.--

Louvers shall be factory fabricated units of extruded aluminum alloy not less than 2 mm thick (12-gage) or galvanized steel sheet not less than 1.63 mm thick (16-gage) with standard "Z" type blades, and removable bronze 16 x 16 mesh insect screens mounted on the inside of the units.

Louvers shall have integral caulking strips and retaining beads.

The finish on louvers shall be baked on primer and fluorocarbon polymeric resin. Color shall be as shown on the plans.

PART 3.- EXECUTION

INSTALLATION.--Louvers shall be installed in accordance with the manufacturer's instructions. The completed louver installation shall be weather tight.

12-10.05 SIGNS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing signs in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for sign materials, colors and graphics, and for fastening hardware and material shall be submitted for approval.

PART 2.- PRODUCTS

Plastic signs (permanent room identification).--

Plastic signs for permanent room identification for other than restrooms shall be scratch resistant, non-static, fire retardent, washable melamine laminate with a non-glare surface, not less than 3 mm thick. Letters and numbers shall be upper case Helvetica, 25 mm in height, 0.80 mm above and integral with sign material, accompanied by Grade 2 Braille.

Grade 2 Braille dots shall be 2.5 mm on centers in each cell with 5 mm space between cells. Dots shall be raised a minimum of 0.6 mm above the background.

Plastic sign (restroom).--

Plastic sign for restroom shall be not less than 6 mm acrylic plastic. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Male/female symbol and lettering shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Male restroom identification shall be a male symbol on an equilateral triangle with edges 305 mm long and a vertex pointing upward.

Female restroom identification shall be a female symbol on a 305 mm diameter circle.

Unisex restroom identification shall be a male and female symbol on a 305 mm equilateral triangle superimposed on a 305 mm diameter circle.

Accessible building entrance sign.--

Accessible building entrance sign shall be not less than 3 mm acrylic plastic, not less than 102 mm x 102 mm , with the international symbol of accessibility.

Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Symbol and border shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Fastening hardware and material.--

Fastening hardware and material shall be as recommended by the sign manufacturer. Fasteners shall be noncorrosive.

PART 3.- EXECUTION

Inscription.--Sign messages shall be as shown on the plans.

Installation.--Plastic signs for room identification and restrooms shall be fastened or secured to clean, finished surfaces in accordance with the sign manufacturer's instructions. Signs shall be installed at a location and height as shown on the plans.

Fastening hardware and material shall be installed within the sign as shown on the plans.

12-10.06 WARDROBE LOCKERS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing wardrobe lockers in accordance with the details shown on the plans and these special provisions. A minimum of one locker shall conform to the accessibility provisions of the California Building Code

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, installation instructions, and standard color palette shall be submitted for approval.

PART 2.- PRODUCTS

ACCEPTABLE MANUFACTURERS.--

Available manufacturers.--Subject to conformance with the contract provisions, metal lockers shall be Art Metal Products; Interior Steel Equipment Co.; Republic Storage Systems; or equal.

Lockers.--

Lockers shall be standard, factory fabricated steel units. Framing shall be 1.52 mm thick (16-gage) and face sheets shall be 0.61 mm (24-gage), except door face sheets shall be 1.5 mm (16-gage).

Lockers shall be equipped with the following: hat shelf located approximately 255 mm below the top of the wardrobe locker, side to side coat rod, coat hook, louver vents at top and bottom of door, nonbreakable handle with provisions for a padlock, lockbar with 3-point latching contact with door frame and 1 1/2 pair full looped leaf hinges.

The approximate dimensions of the wardrobe lockers shall be 380 mm wide, 457 mm deep and 1829 mm high.

Closed bBase.--

Base shall be the manufacturer's standard continuous 16-gage, 152 mm channel base, fabricated of the same material and designed for use with the lockers provided. Base shall be set 13 mm off the face of the cabinet. Bases shall have the same finish as the locker units.

Top.--

Top shall be the manufacturer's standard continuous sloping top with end closure as needed, fabricated of the same material and designed for use with the lockers provided. Tops shall have the same finish as the locker units.

FABRICATION.--

Shop assembly.--Lockers shall be fabricated square, rigid, and without warp, with metal faces flat and free of dents or distortion.

Frame joints and seams shall be welded. Exposed welds shall be ground smooth. Hinge and latch connections shall be welded or riveted.

Bolts shall be used for assembly and mounting lockers components. Bolt or rivet heads on fronts of locker doors or frame shall not be exposed.

Factory finish.--Lockers shall be chemically pretreated with degreasing and phosphatizing process. Wardrobe lockers shall have a baked enamel finish on all surfaces, exposed and concealed.

PART 3.- EXECUTION

Installation.--Lockers shall be mounted on closed bases at locations shown in accordance with the manufacturer's instructions for plumb, level, rigid, and flush installation.

Wardrobe lockers shall be bolted together at tops and bottoms. The backs of the end lockers shall be bolted to wall anchors with 6 mm bolts installed near the tops of the wardrobe lockers as recommended by the locker manufacturer.

Trim, sloping tops, and metal filler panels, if required, shall be installed using concealed fasteners to provide flush, hairline joints against adjacent surfaces.

The number of lockers shall be as shown on the plans.

12-10.07 WOOD BENCHES**PART 1.- GENERAL**

This work shall consist of furnishing and installing wood benches in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data and installation instructions shall be submitted for approval.

PART 2.- PRODUCTS

Acceptable manufacturer's.--Subject to compliance with these requirements, manufacturer's shall be Penco Products, Inc.; Republic Storage Systems, Inc.; Interior Steel Equipment Co.; or equal.

Seat.--

Seat shall be factory fabricated, laminated seat units of solid birch or other suitable, dense hardwood and manufacturer's standard clear coating. Seat units shall be approximately 240 mm wide by 32 mm thick, by 914 mm long. Edges of the seat shall be rounded and all surfaces shall be smooth and free of splinters which would snag clothing or skin.

Supports assemblies.--

Supports assemblies shall be standard steel pedestal assemblies with continuously welded top and bottom flange fittings. Flanges shall have provisions for fasteners to the floor and securing to the bench. Pedestal diameter shall be not less than 32 mm. Pedestal color and finish shall be selected from the manufacturer's standard colors.

Fasteners.--

Fasteners for fastening seat units and support assemblies shall be the manufacturer's standard fasteners for the purpose intended.

PART 3.- EXECUTION

Installation.--Bottom flange fittings of the support assemblies shall bear solidly on the floor without rocking and shall be fastened rigidly and securely to the floor in accordance with the manufacturer's recommendations.

12-10.08 FIRE EXTINGUISHERS AND CABINETS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing fire extinguishers with cabinets in accordance with the details shown on the plans and these special provisions.

REFERENCES.--

General.--Fire Extinguishers shall conform to the requirements in California Code of Regulations, Title 19 Division 1, Chapter 3, "Portable Fire Extinguishers."

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and installation instructions shall be submitted for approval.

QUALITY ASSURANCE.--

Codes and standards.--Fire extinguishers shall be Underwriters Laboratories or Factory Mutual Laboratories approved for the type, rating and classification of extinguisher specified.

PART 2.- PRODUCTS

MANUFACTURER'S.--

Acceptable manufacturers.--Subject to contract compliance, manufacturers shall be J. L. Industries; Larsen's Manufacturing; Potter-Roemer; or equal.

COMPONENTS.--

Fire extinguisher.--

Fire extinguisher shall be fully charged, multi-purpose dry chemical type, with charge indicator, hose and nozzle, and attached service record tag. Fire extinguisher shall be of the capacity and type rating shown on the plans.

Mounting bracket.--

Fire extinguisher cabinet.--

Fire extinguisher cabinet shall be factory fabricated, constructed of steel with a clear plastic panel in a steel door frame, and shall have a baked enamel finish. Color to be selected from the manufacturer's standard colors.

Fire extinguisher cabinet shall be surface mounted or semi-recessed as shown on the plans.

PART 3.- EXECUTION

INSTALLATION.--

General.--Fire extinguishers shall be installed in locations and at mounting heights shown on the plans, or if not shown, at a height of 1220 mm from the finished floor to the top of the fire extinguisher.

Fire extinguisher cabinets shall be attached to structure, square and plumb, in accordance with the manufacturer's recommendations.

IDENTIFICATION.--

Cabinet-mounted.--Extinguishers in cabinets shall be identified with letter spelling "FIRE EXTINGUISHER" applied to the cabinet door. Letter size, styles, and color shall be selected by the Engineer from manufacturer's standard arrangements.

SERVICING.--

General.--Fire extinguishers shall be serviced, charged, and tagged not more than 5 days prior to contract acceptance.

12-10.09 FREE STANDING STEEL SHELVING

PART 1.- GENERAL

This work shall consist of furnishing and installing free standing steel shelving in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, installation instructions and standard color palette shall be submitted for approval. The color will be selected by the Engineer from the manufacturer's standard color palette.

PART 2.- PRODUCTS

Shelving.--

Shelving shall be factory fabricated steel shelves and supports capable of supporting loads of 1200 Pa of shelf area. Shelves shall not deflect more than 8 mm when subjected to the loads specified herein and shall show no permanent deflection after removal of such loads. Shelves shall be supported and attached by means of clips. Studs or bolts shall not be used. Shelves shall be adjustable in vertical increments of 75 mm or less. Shelving shall be of the approximate dimensions and number shown on the plans and shall have a baked enamel finish.

PART 3.- EXECUTION

Free standing steel shelving shall be installed in accordance with the manufacturer's instructions.

12-10.10 TOILET AND SHOWER ACCESSORIES

PART 1.- GENERAL

Scope.--This work shall consist of furnishing and installing toilet and shower accessories in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and installation instructions and details shall be submitted for approval.

PART 2.- PRODUCTS

Toilet tissue dispenser.--

Toilet tissue dispenser shall be dual roll, surface mounted, stainless steel with satin finish, approximately 150 mm x 290 mm x 150 mm deep. Dispenser shall utilize standard toilet tissue rolls. The top roll shall automatically drop into place after the bottom roll is depleted. One dispenser per toilet stall.

Toilet seat cover dispenser.--

Toilet seat cover dispenser shall be white plastic dispenser, approximately 210 mm x 320 mm x 48 mm deep, single pack. One dispenser per toilet stall.

Napkin receptacle.--

Napkin receptacle shall be wall hung, white enameled sheet steel napkin receptacle with hinged top and bottom, disposable liner, approximate 3.8 liter capacity container. One receptacle per women's toilet stall.

Waste receptacle.--

Waste receptacle shall be white enameled sheet steel waste receptacle, 45 liter minimum capacity. One receptacle per toilet room.

Clothes hook.--

Clothes hook shall be stainless steel clothes hook with 2 prongs.

Paper towel dispenser.--

Paper towel dispenser shall be white enameled sheet steel towel dispenser with a capacity of 1000 single fold paper towels. One dispenser per lavatory.

Liquid soap dispenser.--

Liquid soap dispenser shall be surface mounted, heavy duty plastic dispenser for industrial use with a capacity of at least 710 mL. One dispenser per lavatory.

Mirror, wall hung.--

Mirror, wall hung shall be Number 1 quality, 6 mm thick, electrolytically copper plated float or plate glass mirror with nonmoisture-absorbing filler. Mirror shall have a heavy gage galvanized steel back and stainless steel frame. The frame shall have a satin finish and shall be mitered and welded and the corners shall be ground smooth. Fasteners shall not penetrate surfaces of the frame exposed to view. Mirror shall conform to Federal Specification: DD-M-411b and shall be guaranteed against silver spoilage for not less than 10 years.

Mirror, wall hung with shelf (women's restroom).--

Mirror, wall hung shall be Number 1 quality, 6 mm thick, electrolytically copper plated float or plate glass mirror with nonmoisture-absorbing filler. Mirror shall have a heavy gage galvanized steel back and stainless steel frame with integral 127 mm wide stainless steel shelf. The frame shall have a satin finish and shall be mitered and welded and the corners shall be ground smooth. Fasteners shall not penetrate surfaces of the frame exposed to view. Mirror shall conform to Federal Specification: DD-M-411b and shall be guaranteed against silver spoilage for not less than 10 years.

Steel grab bars.--

Steel grab bars shall be stainless steel, 38 mm diameter bars and escutcheon covered integral mounting flanges.

PART 3.- EXECUTION

Installation.--Toilet and shower accessories shall be installed in accordance with the manufacturer's recommendations. Fasteners for mounting accessories shall be concealed and tamper proof.

Expansion anchors shall be used for mounting accessories on masonry or concrete walls.

Toilet and shower accessories shall be mounted after painting work is complete.

All toilet room accessories shall be mounted plumb, secure and rigid. Grab bars shall be supported adequately so the bars will withstand an applied load of 113 kg at any point.

Support assembly for folding seat shall bear solidly on the wall without rocking and shall be fastened rigidly and securely to the wall in accordance with the manufacturer's recommendations.

12-10.11 MOP RACK

PART 1.- GENERAL

This work shall consist of furnishing and installing a mop rack in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data shall be submitted for approval.

PART 2.- PRODUCTS

Mop holder.--

Mop holder shall hold 3 mops and shall be fabricated of heavy gauge stainless steel with a polished satin finish. Mop holder consists of spring loaded rubber cams on plated steel retainers. Mop holder shall be A&J Modes UJ13A; Bradley Model 9953; Bobrick Model B-223; or equal.

PART 3.- EXECUTION

INSTALLATION.--Mop rack shall be installed rigidly and securely.

SECTION 12-11. EQUIPMENT

12-11.01 HIGH PRESSURE WASHER (STATIONARY)

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing a stationary high pressure washer and accessories in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for high pressure washer shall be submitted for approval.

Manufacturer's descriptive data shall include a complete description, performance data and installation instructions for the materials and accessories specified herein.

CLOSEOUT SUBMITTALS.--

Operation and maintenance manuals.--Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be in a bound manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material shall be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

WARRANTY.--

Warranties and guarantees.--Manufacturers warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

PART 2.- PRODUCTS

MANUFACTURERS.--

Acceptable manufacturers.--Subject to compliance with the requirements, products shall be Hotsy, Landa, Whitco, or equal.

MANUFACTURED UNITS.--

High pressure washer.--

High pressure washer shall be stationary type, electric motor driven, LPG-fired, minimum 80 percent efficient, automatic operating type washer designed for continuous operation. The washer shall have a capacity of 15 liters per minute (LPM) of hot water solution heated to 49°C at 13 800 kPa. Maximum LPG input shall be 129 kW. The heating coil shall have an inside diameter of not less than 12 mm. The unit shall be completely housed in a steel cabinet with parts shielded from spray or splash.

The control panel shall display temperature and pressure gauges and shall include the motor starter and the power disconnect breaker. The motor shall be 3.8 kW, 208 VAC, 3 phase as shown on the plans.

The unit shall be equipped with safety controls, safety valve, vent stack and the following accessories: swivel cleaning gun with trigger control and 760 mm long extension; hot water hose with safety couplings, 15 meters in length; flat, round and wide type spray nozzles; water pump and regulator; wall mounted hose and gun rack; remote on/off control manual motor starter with motor overload protection and external manual reset button in a NEMA-1 enclosure.

ACCESSORIES.--

Pressure washer pipe and fittings.—

Pressure pipe and fittings shall be as recommended by the high pressure washer manufacturer.

Drum dolly.--

Drum dolly shall have welded steel construction with a cross braced bottom and a 50 mm continuous perimeter lip, 4 ball bearing casters with steel or semi-steel wheels. Drum dolly shall be sized to match the liquid detergent drum with a minimum capacity of 450 kg.

Vent stack.--

Vent stack shall be listed Class B. Vent stack shall include back draft diverter, fire stop spacer, ventilating thimble with drip cap and listed vent cap.

Hose and gun brackets.--

Hose and gun reel.--

Hose and gun reel shall be heavy duty assembly of steel construction with connecting hose, locking automatic ratchet, guide rollers and heavy duty spring activated hose pickup. Hose and gun reel shall have bushings, swivels, ball stops, and sized for a 15 m delivery hose. The reel shall have a baked enamel finish. Manufacturers reel mounting brackets shall be supplied with reel.

Soap/water mixing meter.--

The soap/water mixing meter shall be wall mounted, have a blend center consisting of; siphon breaker; kick-off spring; stainless steel enclosure; vinyl tubing; proportioner; ceramic weight; pipe plug; magnetic housing; push button; spring; spacer; plunger valve body; pipe to garden hose adapter; foot valve; inlet screen; and meter tip kit.

Non-emulsifying soap.--

Non-emulsifying soap shall be a commercially formulated, concentrated liquid that removes surface dirt, road film, and bug residue from vehicle exteriors with minimal brushing when used in conjunction with a high pressure washer. The soap shall contain no solvents, caustics, acids or phosphates. It shall work with hot or cold water, rinse easily and leave no unsightly soap film or streaks. A drum containing 208 liters of the product shall be supplied by, or approved by the manufacturer of the oil/water separator specified elsewhere in these special provisions. Product shall conform to the following:

Boiling point	>100°C
Specific Gravity	1.102
Solubility in water	100%
Evaporation rate	>1
pH	11-12

Expansion anchors.--

Expansion anchors shall be ICBO approved, integral stud type or internally threaded type with independent stud complete with hex nut and cut washer.

PART 3.- EXECUTION

INSTALLATION.--

General.--The high pressure washer shall be installed in accordance with the manufacturer's recommendations.

Piping shall be installed to provide a minimum headroom clearance of 2.5 meters. Piping shall not be installed in travel areas at floor level.

Hose and gun brackets shall be installed on the wall to hold both the hot water hose and the gun with extension. Location shall be approved by the Engineer. Hose brackets shall be attached to the wall with lag screws or expansion anchors.

Hose and gun reel assembly shall be attached to the wall with 6 mm (minimum) stud type expansion anchors. If hose and gun reel does not include brackets for the gun nozzle, wall brackets shall be installed at the Contractor's expense.

Factory fittings for mixing meter shall be installed on the 208 liter drum of non-emulsified soap and placed on the drum dolly. Soap and dolly shall be ready for use and placed in the equipment building or other location as designated by the Engineer.

FIELD QUALITY CONTROL.--

Testing.--Testing of the high pressure washer shall be conducted by the Contractor in the presence of the Engineer.

The Contractor shall notify the Engineer in writing not less than 5 days prior to the time that testing is to be conducted.

12-11.02 ICE MACHINE

PART 1- GENERAL

This work shall consist of furnishing and installing an ice machine as shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data and installation instructions shall be submitted for approval.

PART 2- PRODUCTS

Ice machine.--

Ice machine shall be Manitowoc, Model Q270; Scotsman, Model SCE275; or equal.

PART 3- EXECUTION

Installation shall be as recommended by the manufacturer.

12-11.03 GARBAGE DISPOSAL

PART 1.- GENERAL

This work shall consist of furnishing and installing a garbage disposal as shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data and installation instructions shall be submitted for approval.

PART 2.- PRODUCTS

Disposal.--

Disposal shall be a 1/2 HP, General Electric, GFC800R; Badger, V; or equal.

PART 3.- EXECUTION

Installation shall be as recommended by the manufacturer.

12-11.04 REFRIGERATOR

PART 1.- GENERAL

This work shall consist of furnishing and installing an electric refrigerator unit as shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data and installation instructions shall be submitted for approval.

PART 2.- PRODUCTS

Refrigerator.--

Refrigerator shall be free standing, 2 door, no frost type, UL listed, 120-volt AC, single phase, 60 hertz, with upper freezer compartment and automatic ice maker, and 2 vegetable/fruit pans, nominal 0.51 cubic meter capacity, with interior and door shelves. Refrigerator shall be of the following types: GE, TBX18CIB; Kenmore, 74802 or equal.

Color shall be white.

PART 3.- EXECUTION

Installation shall be as recommended by the manufacturer.

12-11.05 MICROWAVE OVEN

PART 1. GENERAL

This work shall consist of furnishing and installing a microwave oven as shown on the plans and these special provisions.

The color of crew room equipment shall be white.

SUBMITTALS.--Manufacturer's descriptive data and installation instructions shall be submitted for approval.

PART 2.- PRODUCTS

Microwave oven.--

Microwave oven shall be nominal 0.028310 m³ capacity oven, UL listed, 120 volts AC, single phase, 60 hertz, electronic touch controls, multiple power levels, digital display with clock function. Microwave shall be of the following type: GE, JE1160WB; Whirlpool MT4110SP or equal.

Color shall be white.

PART 3.- EXECUTION

Installation shall be as recommended by the manufacturer.

12-11.06 WORKBENCH

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing a workbench in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and standard color palette shall be submitted for approval.

PART 2.- PRODUCTS

Workbench.--

Workbench shall be standard, factory fabricated and factory painted heavy duty workbench unit with plywood reinforced steel top, drawers, curb and shelves. Plywood top reinforcement shall consist of two layers of securely fastened 19 mm thick exterior type plywood. The drawers, shelves and curb shall be as shown on the plans. Paint shall be an industrial grade enamel.

Leg anchors.--

Leg anchors shall be ICBO approved, integral stud type expansion anchors or internally threaded type anchors with independent stud.

PART 3.- EXECUTION

Installation.--The workbench shall be installed with the top level and the legs rigidly and securely fastened to the floor. Anchors for the legs shall be installed in accordance with the manufacturer's instructions.

SECTION 12-12. FURNISHINGS

12-12.01 VERTICAL BLINDS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing vertical blinds in accordance with the details shown on the plans and these special provisions.

Vertical blinds shall be standard, factory manufactured assemblies suitable for use on exterior wall windows.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, color chips, and installation instructions shall be submitted for approval.

PART 2.- PRODUCTS

Vertical blinds.--

Vertical blinds shall be white vinyl vertical vanes, nominal 89 mm wide, supported from an anodized extruded aluminum track with wheeled carriers and vane hooks. Vanes shall rotate 180 degrees simultaneously, utilizing a drive system centered in the track and activated by a nickel-plated bead chain. The vanes shall be transverse one-way by means of a pulley system and a cord attached to the lead carrier. The cord shall be held down by cord weight in a plastic housing. When closed, the vanes shall overlap a minimum of 10 mm. Vanes shall be replaceable without demounting the track. Fire retardancy and labeling shall conform to Title 19 CCR Division 1, Chapter 8.

Vertical blinds shall be Carey-McFall Corp., Hunter Douglas, Inc., Levelor Corp., or equal.

PART 3.- EXECUTION

Installation.--Vertical blinds shall be installed in accordance with the manufacturer's instructions.

Vertical blinds shall be installed to provide a smooth uniform working operation.

Cleaning.--If vinyl vanes become soiled, they shall be wiped or sponged using a mild detergent and warm water solution.

SECTION 12-13. (BLANK)

SECTION 12-14. (BLANK)

SECTION 12-15. MECHANICAL

12-15.01 MECHANICAL WORK

GENERAL

Scope.--This work shall consist of performing mechanical work in accordance with the details shown on the plans and these special provisions.

Mechanical work shall include furnishing all labor, materials, equipment and services required for providing heating, ventilating, air conditioning, plumbing and liquefied petroleum gas (LPG) distribution systems.

Earthwork, foundations, sheet metal, painting, electrical, and such other work incidental and necessary to the proper installation and operation of the mechanical work shall be in accordance with the requirements specified for similar type work elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of pipes, ducts, etc., and location of equipment is to be governed by structural conditions and obstructions. Equipment requiring maintenance and inspection is to be readily accessible.

Roof penetrations shall be flashed and sealed watertight in accordance with the requirements specified under "Sheet Metal Flashing" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for plumbing fixtures, and component layout shall be included where applicable.

Manufacturer's descriptive data shall be submitted for the following:

- Water hammer arrestor
- Access door
- Compression stop
- Hose faucet
- Pipe insulation
- Cleanouts
- Valve boxes
- Floor drain
- Water closet
- Urinal
- Lavatory
- Lavatory carrier
- Lavatory and sink faucets
- Mop sink
- Kitchen sink
- Water heaters
- Emergency shower and eyewash
- Gate valves
- Ball valves
- Balancing dampers
- Unit heater
- Heat-vent-light combination
- Supply fan
- Exhaust fans
- Air conditioning units
- Thermostats
- Thermostat lockout cover
- Time switches
- Diffusers
- Registers
- Duct insulation
- Duct liner
- LPG regulator
- Compressed air supply
- LPG system
- Wharf hydrant
- Backflow preventer

CLOSEOUT SUBMITTALS.--

Operation and maintenance manuals.--Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be indexed and bound in a manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material shall be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

Operation and maintenance manuals shall be submitted for the following equipment:

- Air conditioning units
- Evaporative coolers
- Exhaust fans
- Unit heaters
- Thermostats
- LPG system
- Wharf hydrant
- Emergency shower and eyewash

QUALITY ASSURANCE.--

Codes and standards.--Mechanical work, including equipment, materials and installation, shall conform to the California Building Standards Code, Title 24, and to the California Code of Regulations, Title 8, Chapter 4, Division of Industrial Safety (DIS).

WARRANTY.--

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

SYSTEM IDENTIFICATION.--

Piping, ducts, valves and equipment.--Identification of piping, ducts, valves and equipment shall be as shown on the plans or these special provisions:

Above ground piping and ducts.--Markers shall be provided on lines which are either exposed or concealed in accessible spaces. For piping systems, except drain and vent lines, indicate the fluid conveyed or its abbreviation; either by preprinted markers or stenciled markings, and include arrows to show the direction of flow. Colors shall comply with ANSI Standard: A13.1. Locate markers at ends of lines, near major branches and other interruptions including equipment in the line, where lines pass through penetrations in floors, walls or ceilings or otherwise pass into inaccessible spaces, and at 15 m maximum intervals along exposed portions of the lines. Marking of short branches and repetitive branches for equipment connections is not required.

Valves.--Valve tags shall be provided on all valves of each piping system, excluding check valves, valves within equipment, faucets, stops and shut-off valves at fixtures and other repetitive terminal units. Provide brass or plastic laminate tags. Prepare and submit a tagged valve schedule, listing each valve by tag number, location and piping service. Valve schedule shall be mounted in a glazed frame at a location approved by the Engineer.

Equipment.--All equipment shall be identified with a plastic laminated, engraved nameplate which bears the unit mark number as indicated on the drawings (for example, AC-4). Provide 13 mm high lettering, white on black background. Nameplates shall be permanently secured to the unit.

12-15.02 PIPE, FITTINGS AND VALVES

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing pipes, fittings and valves in accordance with the details shown on the plans and these special provisions. Pipe, fittings and valves shall include such plumbing and piping accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the plumbing and piping systems.

All piping insulation and wrapping material shall be in accordance with the requirements specified under "Mechanical Insulation," in this Section 12-15.

Cathodic protection for underground piping shall be in accordance with the requirements specified under "Cathodic Protection," of these special provisions.

The pipe sizes shown on the plans are nominal pipe size. No change in the pipe size shown on the plans shall be permitted without written permission from the Engineer.

The pipe and fitting classes and material descriptions shall be as specified herein. No change in class or description shall be permitted without written permission from the Engineer.

QUALITY ASSURANCE.--

Codes and standards.--Pipe, fittings and valves shall be installed in accordance with the requirements in the 2001 edition of the California Plumbing Code, the manufacturer's recommendations and the requirements specified herein.

PART 2.- PRODUCTS

MATERIALS.--

PIPE AND FITTINGS --

Class Description

A1.--

Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with 1040 kPa galvanized malleable iron banded screwed fittings and galvanized steel couplings. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

A2.--

Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with black cast iron recessed drainage fittings. For rainwater leaders, neoprene-gasket compression couplings, Smith Blair, Dresser, or equal, may be used. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

B2.--

Schedule 40 black steel pipe conforming to ASTM Designation: A 53, with 1040 kPa black malleable iron banded screwed fittings and black steel couplings.

Steel pipe coating, where required, shall be factory applied plastic. Pipe coating shall be Standard Pipe Protection, X-Tru-Coat (0.50 mm thick); Pipe Line Service Corporation, Republic; 3M Company, Scotchkote 205 (0.30 mm thick); or equal.

B3.--

Schedule 80 black steel pipe conforming to ASTM Designation: A 53 grade B, 50 mm and smaller shall be 20 700 kPa WOG socket welding fittings and couplings or 13 800 kPa WOG threaded forged steel, ASTM Designation: A 105. 65 mm and larger shall be extra strong weight butt welding fittings and couplings.

C1.--

Hub and plain end cast iron soil pipe with neoprene gaskets conforming to Cast Iron Soil Pipe Institute's Standard 301. Pipe, fittings and gaskets shall be of one manufacturer.

C2.--

Hubless cast iron soil pipe with neoprene gaskets, corrugated stainless steel shields and stainless steel clamps conforming to Cast Iron Soil Pipe Institute's Standard 301. Joint materials shall be furnished by pipe manufacturer.

H1.--

Type DWV hard copper tubing conforming to ASTM Designation: B 306, with DWV drainage fittings, stop type couplings and threaded adapters.

H2.--

Type K hard copper tubing conforming to ASTM Designation: B 88, with wrought copper or cast bronze solder joint pressure fittings, stop type couplings and threaded adapters. Solder shall be lead-free.

H3.--

Type L hard copper tubing conforming to ASTM Designation: B 88, with wrought copper or cast bronze solder joint pressure fittings, stop type couplings and threaded adapters. Solder shall be lead-free.

P2.--

Polyvinyl chloride (PVC) plastic pipe and fittings conforming to ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 1380 kPa working pressure at 23°C, National Sanitation Foundation approved. Pipe shall have bell ends conforming to ASTM Designation: D 3139 with triple edge rubber sealing ring. For pipe sizes 50 mm diameter and smaller, plain end pipe with solvent welded fittings ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 1380 kPa may be used.

P3.--

Polyvinyl chloride (PVC) standard weight pipe and fittings, Schedule 40, conforming to ASTM Designation: D 1785. Pipe shall meet or exceed requirements of National Sanitation Foundation Standard No. 14. Pipe shall have bell ends conforming to ASTM Designation: D 2672. For pipe sizes 75 mm and smaller, plain end pipe with solvent welded fittings conforming to ASTM Designation: D 2241, may be used.

P4.—

Polyvinyl chloride (PVC) plastic pipe and fittings shall conform to AWWA Designation: C900, class 150, Standard Dimension Ratio (SDR) 18. Pipe shall have bell end with a solid cross section elastomeric ring conforming to ASTM Designation: D 3139.

Unions (for steel pipe)--

Unions (for steel pipe) shall be 1730 kPa, threaded malleable iron, ground joint, brass to iron seat, galvanized or black to match piping.

Unions (for copper or brass pipe)--

Unions (for copper or brass pipe) shall be 1040 kPa cast bronze, ground joint, bronze to bronze seat with silver brazing threadless ends or 860 kPa cast brass, ground joint, brass to brass seat with threaded ends.

Unions (for brass waste and flush pipes)--

Unions (for brass waste and flush pipes) shall be slip or flange joint unions with soft rubber or leather gaskets. Unions shall be placed on the fixture side of the traps.

Dielectric waterway.--

Dielectric waterway shall be a premanufactured unit that incorporates an insulated interior lining at least 75 mm in length between the 2 pipes being connected while maintaining metal to metal contact on the exterior surface. Dielectric water way shall be listed by IAPMO (International Association of Plumbing and Mechanical Officials).

Insulating union.--

Insulating union or flange as applicable shall be suitable for the service on which used. Connections shall be constructed such that the 2 pipes being connected are completely insulated from each other with no metal to metal contact. Insulating couplings shall not be used. Insulating union shall be F. H. Maloney; Central Plastics; EPCO; or equal.

Insulating connection (to hot water tanks)--

Insulating connection (to hot water tanks) shall be 150 mm minimum, flexible copper tubing with dielectric union at each end and designed to withstand a pressure of 1040 kPa and a temperature of 93°C.

VALVES.--**Gate valve (65 mm and smaller)--**

Gate valve (65 mm and smaller) shall be bronze body and trim, removable bonnet and non rising stem, Class 125 and same size as pipe in which installed. Gate valve shall be Crane, 438; Nibco Scott, T-113; Jenkins, 370; or equal.

Gate valve in nonferrous water piping systems may be solder joint type with bronze body and trim. Valve shall be Kitz, 59; Nibco Scott, S-113; Jenkins, 1240; or equal.

Gate valve (75 mm and larger, above ground)--

Gate valve (75 mm and larger, above ground) shall be iron body with bronze trim, removable bonnet and non-rising stem, class 125 and same size as pipe in which installed. Gate valve shall be Crane, 461; Nibco Scott, F-619; Jenkins, 326; or equal.

Gate valve (75 mm and larger, below ground)--

Gate valve (75 mm and larger, below ground) shall be AWWA double disc, hub or rubber ring type, removable bonnet and non-rising stem, equipped with operating nuts, 1380 kPa working pressure, and Tee handle wrench for each valve. Valve shall be Mueller, A-2380; American Valve, Model 28; or equal.

Ball valve.--

Ball valve shall be two piece, minimum 2760 kPa WOG, bronze body and chrome plated or brass ball with full size port. Valve shall be Nibco Scott, T-580; Watts, B-6000; Kitz, 56; or equal.

LPG gas valve.--

LPG gas valve shall be listed, 1730 kPa (minimum) WOG bronze ball valve. Valve shall be Jenkins, Model 30-A; Crane, Accesso; Watts; or equal.

FAUCET AND HYDRANTS.--**Hose faucet.--**

Hose faucet shall be compression type, angle pattern, wall flange at exterior locations, tee handle, 20 mm female thread with hose end, rough chrome or nickel plated finish for locations inside building, rough brass finish for others. Hose faucet shall be supplied with an integral or nonremovable threaded outlet vacuum breaker which meets the requirements of the American Society of Sanitary Engineering (ASSE) Standard: 1011. Hose faucet shall be Nibco, No. 63VB; Chicago, No. 13T; or equal.

Wall hydrant.--

Wall hydrant shall be 20 mm, non-freeze type, exposed, nickel bronze head with bronze casing, and integral vacuum breaker. Operating key shall be provided. Wall hydrant shall be J. R. Smith Model 5609 QT, Josam Model 71050, Zurn, Model 1310; or equal.

Wharf hydrant.--

Wharf hydrant shall be bronze, 2070 kPa working pressure, operating nut, lug type reducer and hose cap, and chain. Wharf hydrant shall have standard threads on inlet and National Standard Hose Threads on outlet. Lug type reducer shall have National Standard Hose Threads. Wharf hydrant shall be James Jones; Powhatan; John W. Moon Inc.; or equal.

A wharf hydrant operating nut wrench and hose spanner wrench or the combination type shall be provided for each wharf hydrant.

CLEANOUTS.--**Cleanout through floor.--**

Cleanout through floor shall have nonslip scoriated nickel bronze access plate and adjustable frame with square pattern top for ceramic tile and round pattern top for other finishes. Where floors are constructed with a membrane, access frame shall be provided with membrane clamping flange. Plug shall be countersunk brass or bronze with tapered threads. Cleanout shall be Wade, W-7000 Series; Smith, 4023 Series; Zurn, No. 1400; or equal.

Cleanout through floors in exterior locations shall be heavy duty, floating pipe type with cast iron cover. Cleanouts shall be Wade, No. W-8300-HF; Smith, No. 4253; Zurn, No. 1474; or equal.

MISCELLANEOUS ITEMS.--**Water hammer arrestor.--**

Water hammer arrestor shall be stainless steel body with bellows or piston. Arrestor compression chambers shall be pneumatically charged. Water hammer arrestors shall be tested and certified in accordance with the Plumbing and Drainage Institute Standard: PDI-WH201 and sized as shown on the plans.

Access door.--

Access door shall be 1.52 mm prime coated steel, face mounting square frame, minimum 300 mm x 300 mm door with concealed hinge and screwdriver latch.

Compression stop (exposed).--

Compression stop (exposed) shall be metal full free waterway, angle type, ground joint union, non-rising stem, molded rubber seat and wheel handle.

Compression stop (concealed).--

Compression stop (concealed) shall be long neck, built-in compression stops for required wall thickness, loose key and exposed parts polished chromium plated. Supplies shall be Chicago, 1771; California Brass, No. 172; or equal.

Gas regulator.--

Gas regulator shall be listed as suitable for gas and equipped with full capacity relief valve, low pressure safety shut-off and weatherproof and insect proof vent for outside installation. Capacity shall be as shown on the plans. Gas regulator shall be Fisher; Reliance; Rockwell; or equal.

Backflow preventer.--

Backflow preventer shall be factory assembled with 2 check valves, one pressure differential relief valve, 2 ball valves and 4 test cocks. Backflow preventers shall be of the approved type reduced pressure principle devices listed by the County of Trinity Department of Health Services, Cross-Connection and Water Pollution Control Section.

Pipe hanger (for piping supported from overhead).--

Pipe hanger (for piping supported from overhead) shall be Grinnell, Model 269; Super Struct, C711; or equal.

Pipe wrapping tape and primer.--

Pipe wrapping tape shall be pressure sensitive polyvinyl chloride or pressure sensitive polyethylene tape having nominal thickness of 0.50 mm. Wrapping tape shall be Polyken, 922; Manville, Trantex VID-20; Scotchrap, 51; or equal.

Pipe wrapping primer shall be compatible with the pipe wrapping tape used.

Floor, wall, and ceiling plates.--

Floor, wall, and ceiling plates shall be chromium plated steel or plastic plates having screw or spring clamping devices and concealed hinges. Plates shall be sized to completely cover the hole.

Valve box.--

Valve box shall be precast high density concrete with polyethylene face and cast iron cover marked "WATER," "GAS" or "CO-SS" as applicable. Extension shall be provided as required. Valve box shall be Christy, B3; Brooks Products Company, 3TL; Frazer, 3; or equal.

Floor drain.--

Floor drain shall be cast iron body and flashing collar, adjustable nickel bronze 150 mm strainer head with seepage openings and caulk or no-hub outlet. Floor drain shall be round or square as shown on the Architectural plans. Floor drain shall be J. R. Smith, 2005/2010; Wade, W-1100; Zurn, Z-415; or equal.

Trench drain.--

Trench drain modules shall have a minimum slope of 0.60 percent and minimum flow rate of 280 liters per minute. Trench drain shall be Advanced Building Technologies, Inc., Polydrain; Zurn, Flo Thru; or equal.

PART 3.- EXECUTION

INSTALLATION.--

INSTALLATION OF PIPES AND FITTINGS.--

Pipe and fittings.--Pipe and fittings shall be installed in accordance with the following designated uses:

Designated Use	Pipe and Fitting Class
Domestic water (CW and HW) in buildings	H3 or A1
Domestic water underground within 1.5 m of the building	A1 or H2
Domestic water underground 1.5 m beyond the building	P2, P3, P4, A1 or H2
Sanitary drain piping above ground in building	H1, C1, or C2
Sanitary drain and vent piping underground within 1.5 m of the building	C1 or C2
Sanitary vent piping above ground in building	A2, H1, C1, or C2
Liquefied petroleum gas (LPG), 860 kPa or less, above ground	A1 or B2
LPG, 860 kPa or less, underground	B2 (plastic coated)
LPG, exceeding 860 kPa	B3
Compressed air	A1
Rainwater leaders	A2
Equipment drains and relief valve discharge	H3 or A1
Soap lines	H3

Installing piping.--Water piping shall be installed generally level, free of traps and bends, and arranged to conform to the building requirements.

Piping installed underground shall be tested as specified elsewhere in these special provisions before backfilling.

Public use areas, offices, rest rooms, locker rooms, crew rooms, training rooms, storage rooms in office areas, hallway type rooms, and similar type use areas shall have concealed piping.

Warehouse rooms, equipment bays, shall have exposed piping.

Piping shall not be run in floor fill, except as shown on the plans.

Piping shall be installed parallel to walls. All obstructions shall be cleared, headroom preserved and openings and passageways kept clear whether shown or not. Piping shall not interfere with other work.

Where pipes pass through exterior walls, a clear space around pipe shall be provided. Space shall be caulked water tight with silicone caulk.

Underground copper pipe shall have brazed joints. Underground plastic pipe shall be buried with No. 14 solid bare copper wire. Wire ends at pipe ends shall be brought up 200 mm and looped around pipe.

Exposed supply and drain piping in rest rooms shall be chrome finished.

Compressed air piping shall be pitched to low point. Ball valved drips shall be provided at all low points. Branches shall be taken off top of main.

Gas piping shall not be installed under building concrete slabs or structure. An insulating connection and valve shall be installed above ground at each building supply.

Gas piping shall be pitched to equipment or to low point and provided with a 200 mm minimum dirt leg.

Forty-five degree bends shall be used where offsets are required in venting. Vent pipe headers shall be sloped to eliminate any water or condensation.

Vent piping shall extend a minimum of 200 mm above the roof.

Horizontal sanitary sewer pipe inside buildings shall be installed on a uniform grade of not less than 2 percent unless shown otherwise on the plans.

Drainage pipe shall be run as straight as possible and shall have easy bends with long turns.

Wye fittings and 1/8 or 1/16 bends shall be used where possible. Long sweep bends and combination Wye and 1/8 bends may be used only for the connection of branch pipes to fixtures and on vertical runs of pipe.

Water pipe near sewers.--Water pipe shall not be installed below sewer pipe in the same trench or at any crossing, or below sewer pipe in parallel trenches less than 3 m apart.

When a water pipe crosses above a sewer pipe, a vertical separation of at least 300 mm between the top of the sewer and the bottom of the water pipe shall be maintained.

When water and sewer pipe is installed in the same trench, the water pipe shall be on a solid shelf at least 300 mm above the top of the sewer pipe and 300 mm to one side.

Pipe sleeves.--The Contractor shall provide sleeves, inserts and openings necessary for the installation of pipe, fittings and valves. Damage to surrounding surfaces shall be patched to match existing.

PVC pipe sleeves shall be provided where each pipe passes through concrete floors, footings, walls or ceilings. Inside diameter of sleeves shall be at least 20 mm larger than outside diameter of pipe. Sleeves shall be installed to provide at least 10 mm space all around pipe the full depth of concrete. Space between pipes and pipe sleeves shall be caulked watertight.

Pipe penetrations in fire rated assemblies.--Where pipes pass through fire rated wall, floor or ceiling assemblies, the penetration shall be protected in accordance with the requirements specified under "Through-Penetration Firestopping," in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

Cutting pipe.--All pipe shall be cut straight and true and the ends shall be reamed to the full inside diameter of the pipe after cutting.

Damaged pipe.--Pipe that is cracked, bent or otherwise damaged shall be removed from the work.

Pipe joints and connections.--Joints in threaded steel pipe shall be made with teflon tape or a pipe joint compound that is nonhardening and noncorrosive, placed on the pipe and not in the fittings.

The use of thread cement or caulking on threaded joints will not be permitted. Threaded joints shall be made tight. Long screw or other packed joints will not be permitted. Any leaky joints shall be remade with new material.

Exposed polished or enameled connections to fixtures or equipment shall be made with special care, showing no tool marks or threads.

Cleaning and closing pipe.--The interior of all pipe shall be cleaned before installation. All openings shall be capped or plugged as soon as the pipe is installed to prevent the entrance of any materials. The caps or plugs shall remain in place until their removal is necessary for completion of the installation.

Securing pipe.--Pipe in the buildings shall be held in place by iron hangers, supports, pipe rests, anchors, sway braces, guides or other special hangers. Material for hangers and supports shall be compatible with the piping or neoprene isolators shall be used. Allowances shall be made for expansion and contraction. Steel pipe shall have hangers or supports every 3 m. Copper pipe 25 mm or smaller shall have hangers or supports every 2 m and sizes larger than 25 mm shall have hangers or supports every 3 m. Plastic pipe shall have hangers or supports every 1 m. Cast iron soil pipe with neoprene gaskets shall be supported at each joint. Vertical pipes shall be supported with clamps or straps. Horizontal and vertical piping shall be securely supported and braced to prevent swaying, sagging or flexing of joints.

Hangers and supports.--Hangers and supports shall be selected to withstand all conditions of loading to which the piping and associated equipment may be subjected and within the manufacturer's load ratings. Hangers and supports shall be spaced and distributed so as to avoid load concentrations and to minimize the loading effect on the building structure.

Hangers and supports shall be sized to fit the outside diameter of pipe or pipe insulation. Hangers shall be removable from around pipe and shall have provisions for vertical adjustment after erection. Turnbuckles may be used.

Materials for holding pipe in place shall be compatible with piping material.

Hanger rods shall be provided with locknuts at all threaded connections. Hanger rods shall be sized as follows:

Pipe Size	Minimum Hanger Rod Diameter
15 mm to 50 mm	10 mm
65 mm to 87 mm	13 mm
100 mm to 125 mm	16 mm

Wrapping and coating steel pipe.--Steel pipe buried in the ground shall be wrapped or shall be plastic coated as specified herein:

1. Wrapped steel pipe shall be thoroughly cleaned and primed as recommended by the tape manufacturer.
2. Tapes shall be tightly applied with 1/2 uniform lap, free from wrinkles and voids with approved wrapping machines and experienced operators to provide not less than 1.00 mm thickness.
3. Plastic coating on steel pipe shall be factory applied. Coating imperfections and damage shall be repaired to the satisfaction of the Engineer.
4. Field joints, fittings and valves for wrapped and plastic coated steel pipe shall be covered to provide continuous protection by puttying and double wrapping with 0.50 mm thick tape. Wrapping at joints shall extend a minimum of 150 mm over the adjacent pipe covering. Width of tape for wrapping fittings shall not exceed 50 mm. Adequate tension shall be applied so tape will conform closely to contours of fittings. Putty tape insulation compounds approved by the Engineer shall be used to fill voids and provide a smooth even surface for the application of the tape wrap.

Wrapped or coated pipe, fittings, and filed joints shall be approved by the Engineer after assembly. Piping shall be placed on temporary blocks to allow for inspection. Deficiencies shall be repaired to the satisfaction of the Engineer before backfilling or closing in.

Thrust blocks.--Thrust blocks shall be formed by pouring concrete between pipe and trench wall. Thrust blocks shall be sized and so placed as to take all thrusts created by maximum internal water pressure.

Plastic pipe underground shall be provided with thrust blocks and clamps at changes in direction of piping, connections or branches from mains 50 mm and larger, and all capped connections.

Union.--Unions shall be installed where shown and at each threaded or soldered connection to equipment and tanks. Unions shall be located so piping can be easily disconnected for removal of equipment or tanks. Unions shall be omitted at compression stops.

Dielectric waterway.--Dielectric waterway shall be provided between metal pipes of different material, and between brass or bronze valves and steel piping.

Insulating union and insulating connection.--Insulating union and insulating connection shall be provided where shown and at the following locations:

1. In metallic water, gas and air service connections into each. Insulating connections shall be installed on the exterior of the building, above ground and after shut-off valve.
2. In water, gas and air service connections in ground at point where new metallic pipes connect to existing metallic pipes. Install valve box above insulating connection.
3. At points of connections of copper or steel water pipes to steel domestic water heaters and tanks.
4. At each end of buried ferrous pipe protected by cathodic protection.

Bonding at insulating connections.--Interior water piping and other interior piping that may be electrically energized and are connected with insulating connections shall be bonded in accordance with the California Electrical Code. Bonding shall all be coordinated with electrical work.

Compression stop.--Each fixture, including hose faucets, shall be equipped with a compression stop installed on water supply pipes to permit repairs without shutting off water mains. Ball valves may be installed where shown on the plans or otherwise permitted by the Engineer.

INSTALLATION OF VALVES.--

Exterior valves.--Exterior valves located underground shall be installed in a valve box marked "Water." Extensions shall be provided as required.

INSTALLATION OF FAUCETS AND HYDRANTS.--

Hose faucet and hydrants.--Faucets and hydrants shall be installed with outlets 0.5 m above finished grade.

INSTALLATION OF CLEANOUTS.--

Cleanouts.--A concrete pad 0.5 m long and 100 mm thick shall be placed across the full width of trench under cleanout Wye or 1/8 bend. Cast iron soil pipe (C1 or C2) and fittings shall be used from Wye to surface. Required clearance around cleanouts shall be maintained.

Cleanout risers installed in tile and concrete floors, including building aprons and sidewalks, shall terminate in a cleanout through floor.

INSTALLATION OF MISCELLANEOUS ITEMS.--

Water hammer arrestor.--Water hammer arrestor shall be installed so that they are vertical and accessible for replacement. Water hammer arrestor shall be installed with access door when in walls or there is no access to ceiling crawl spaces. Access door location shall be where shown on the plans or as approved by the Engineer.

Gas appliance connection.--Gas valve and flexible connector shall be provided for gas piping at each appliance. Appropriately rated gas cocks may be used in 15 mm gas pipe. Cock or valve shall be within one meter of the appliance.

Gas regulator.--Gas regulator shall be installed complete with dirt leg, capped test tee, union, insulating union, gas valve and fittings.

Backflow preventer.--Backflow preventer assembly shall include a wye strainer, backflow preventer, fittings and pipe. Assembly components shall be the same size as the pipe in which they are installed unless otherwise shown on the plans.

Backflow preventer shall be installed a minimum of 300 mm above ground and shall be the same size as the pipe in which it is installed unless otherwise shown on the plans.

Water meter.--Water meter shall be installed in horizontal piping run with no fittings located within 750 mm of either side of the meter.

Flushing completed systems.--All completed systems shall be flushed and blown out.

Chlorination.--The Contractor shall flush and chlorinate all domestic water piping and fixtures.

Calcium hypochlorite granules or tablets, if used, shall not be applied in the dry form, but shall first be dissolved into a solution before application.

The Contractor shall take adequate precautions in handling chlorine so as not to endanger workmen or damage materials. All pipes and fittings shall be completely filled with water containing a minimum of 50 ppm available chlorine. Each outlet in the system shall be opened and water run to waste until a strong chlorine test is obtained. The line shall then be closed and the chlorine solution allowed to remain in the system for a minimum of 24 hours so that the line shall contain no less than 25 ppm chlorine throughout. After the retention period, the system shall be drained, flushed and refilled with fresh water.

FIELD QUALITY CONTROL.--

Testing.--The Contractor shall test piping at completion of roughing in, before backfilling, and at other times as directed by the Engineer.

The system shall be tested as a single unit, or in sections as approved by the Engineer. The Contractor shall furnish necessary materials, test pumps, instruments and labor and notify the Engineer at least 3 working days in advance of testing. After testing, the Contractor shall repair all leaks and retest to determine that leaks have been stopped. Surplus water shall be disposed of after testing as directed by the Engineer.

The Contractor shall take precautions to prevent joints from drawing while pipes and appurtenances are being tested. The Contractor shall repair damage to pipes and appurtenances or to other structures resulting from or caused by tests.

Cathodic protection tests.--The State will conduct tests at locations where cathodic protection is required to determine compliance with the specified requirements.

General tests.--All piping shall be tested after assembly and prior to backfill, pipe wrapping, connecting fixtures, wrapping joints and covering the pipe. Systems shall show no loss in pressure or visible leaks.

The Contractor shall test systems according to the following schedule for a period of not less than 4 hours:

Test Schedule		
Piping System	Test Pressure	Test Media
Sanitary sewer and vent	300 mm head	Water
Water	860 kPa	Water
Gas (except P6)	690 kPa	Air
Air	860 kPa	Air

During testing of water systems, valves shall be closed and pipeline filled with water. Provisions shall be made for release of air.

Sanitary sewers shall be cleared of obstructions before testing for leakage. The pipe shall be proved clear of obstructions by pulling an appropriate size inflatable plug through the pipe. The plug shall be moved slowly through the pipe with a tag line. The Contractor shall remove or repair any obstructions or irregularities.

Sanitary sewer pipes beyond 1.5 m perpendicular to the building shall be tested for leakage for a period of not less than 4 hours by filling with water to an elevation of 1.2 m above average invert of sewer or to top of manholes where less than 1.2 m deep. The system shall show no visible leaks. The sewer may be tested in sections with testing water progressively passed down the sewer as feasible. Water shall be released at a rate that will not create water hammer or surge in plugged sections of sewer.

Testing backflow preventers.--Backflow preventers installed by the Contractor shall be tested at the completion of the supply system installation for proper operation by a certified Backflow Preventer Tester.

The tester shall hold a valid certificate as a Backflow Preventer Tester from the county in which the device to be tested is located or, if the county does not have a certification program for Backflow Preventer Testers, the tester shall have a certificate from one of the following:

1. The American Water Works Association.

2. A county which has a certification program for Backflow Preventer Testers. The certification under which the tester has been certified shall be acceptable to the water purveyor and the local agency having jurisdiction.

Testing for proper operation shall conform to the procedures of the county in which the testing is being performed, or, if such procedures are not available in the county, such tests shall conform to the provisions in the latest edition of the Guidance Manual For Cross Connection Control Program, which is available from the California Department of Health Services, Division of Drinking Water and Environmental Management, 601 N 7th Street, P.O. Box 942732, Sacramento, CA 94234.

The Contractor shall notify the Engineer at least 5 days prior to testing backflow preventers. Such tests shall be satisfactorily completed after installation of the backflow preventer assemblies and before operation of the systems.

One copy of all test results for each backflow preventer shall be furnished to the Engineer.

Full compensation for providing the certified Backflow Preventer Tester and for testing the backflow preventers shall be considered as included in the lump sum price paid for building work and no additional compensation will be allowed therefor.

12-15.03 MECHANICAL INSULATION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing mechanical insulation in accordance with the details shown on the plans and these special provisions.

Piping insulation shall be installed on all domestic hot water piping, above grade, in non-conditioned spaces.

P-trap, hot water supply pipes and angle valves for lavatories and sinks, except in janitor closets or similar enclosed spaces, shall be insulated.

Duct insulation shall be installed on all rigid ductwork installed in concealed non-conditioned spaces.

Duct liner shall be installed in all rectangular ductwork installed in exposed non-conditioned spaces and in exterior locations. Plenum liner shall be installed in all plenums in non-conditioned spaces or in walls facing a non-conditioned space.

QUALITY ASSURANCE.--

Codes and standards.--Mechanical insulation shall conform to California State Energy Commission regulations and, where applicable, shall meet American Society of Testing and Materials (ASTM) standards.

All materials shall bear the label of the Underwriters Laboratory (UL) or other approved testing laboratory indicating that the materials proposed for use conform to the required fire hazard ratings.

Pipe safety insulation shall conform to Section 1504(b) of Title 24, Part 5, California Plumbing Code.

PART 2.- PRODUCTS

MATERIAL.--

General.--All pipe insulation and wrapping material, including adhesives and jackets, located within buildings shall be certified to have a composite flame spread rating of not more than 25 and smoke development rating of not more than 450 when tested in accordance with ASTM Designation: E 84.

Duct insulation and wrapping material, including adhesives and jackets, located within buildings shall be certified to have a composite flame spread of not more than 25 and smoke development rating of not more than 50 when tested in accordance with ASTM Designation: E 84.

Domestic water and interior hydronic piping insulation.--

Piping insulation shall be glass fiber molded pipe insulation with factory applied jacket suitable for service temperatures up to 175°C. Covering jacket shall have pressure sealing lap adhesive joints. Pipe insulation shall have a minimum thermal resistance of $R-0.5 \text{ K}\cdot\text{m}^2/\text{W}$. Insulation and jackets shall be Owens-Corning, Fiberglass 25 with ASJ/SSL All Service Jacket; Manville, Micro-Lok 650ML with AP-T All Purpose Jacket; or equal.

Piping insulation cement.--

Insulation cement shall be Fenco, All Purpose Cement; Manville, JM375; or equal.

Exterior piping insulation

Piping insulation shall be polyurethane foam insulation with a service temperature range of 0°C to 120°C. A 0.15 mm vapor barrier shall be applied over the top off the insulation. The vapor barrier shall be installed with an adhesive as recommended by the manufacturer.

PVC jacket.--

PCV jacket shall be rated for a service temperature of 80°C. PVC jacket shall include covers specifically designed to cover pipe fittings.

Pipe safety insulation.--

Pipe safety insulation for P-traps, hot water supply pipes and angle valves shall be molded closed cell vinyl or closed cell foam with exterior vinyl surface. Pipe safety insulation shall be configured to protect against contact. Pipe safety insulation shall be Truebro Inc., Handi Lav-guard; Plumberex Specialty Products, Handy Shield; or equal.

External duct insulation.--

External duct insulation shall be 38 mm thick, 0.5 kg density glass-fiber blanket type. Material and coatings shall be fire resistive and shall be approved by the State Fire Marshal. External duct insulation shall be Fiberglas, Type PF-336; Ultralite, No. 100; Pittsburgh Plate Glass, Superfine; Johns-Manville, Microlite; Silvercote, Silvercel; or equal.

Plenum and duct liner.--

Plenum and duct liner shall be 25 mm minimum thickness. Material and coatings shall be fire resistive and shall be approved by the State Fire Marshal. Liner shall be Gustin-Bacon, Ultra-Liner duct insulation; Owens-Corning Fiberglas, Type CE; Gustin-Bacon, coated insulation Board No. 90-A; Owens-Corning Fiberglas 0.7 kg density coated flexible duct liner; Johns-Manville, MicroBar, or 0.7 kg density coated Microlite; Pittsburgh Plate Glass, Superfine 0.7 kg density coated interior duct insulation; or equal.

Adhesive.--

Adhesive shall be non-flammable type: Benjamin Foster Company, No. 85-20 Spark Safe; Goodloe E. Moore Company, Tuff Bond No. 6; Permacel, No. PA-310; 3M, No. 38 Insulation Adhesive; Swift's, No. 7228 brush type or No. 7336 spray type; Chicago Mastic, 17-461; or equal.

Studs.--

Studs shall be cement-in-place type, pneumatic driven type or percussive welding type, and shall have 25 mm minimum diameter washers.

Insulation inserts.--

Insulation inserts at pipe hangers supports for pipes 50 mm or larger shall be calcium silicate, cellular glass, or other acceptable material of the same thickness as the adjacent insulation and not less than 6 kg density.

PART 3.- EXECUTION**INSTALLATION.--**

General.--Insulation materials shall be neatly installed with smooth and even surfaces, jackets drawn tight and smoothly cemented down.

Insulation material shall not be installed until all pipes or surfaces to be covered are tested for leaks, cleaned and dried, and foreign materials, such as rust, have been removed.

Piping insulation.--Piping insulation shall be in accordance with the following, except that unions, unless integral with valves, and flexible connections shall not be insulated.

- a. Where insulation butts against flanges or is discontinued, insulation shall be tapered to pipe to allow for covering jacket to completely seal off end of insulation.

Insulation shall be extended on the valve bodies up to the valve bonnet.

Extend insulation continuous through pipe hangers and pipe sleeves. At hangers where pipe is supported, provide an insulated protection shield.

Insulating cement shall be applied to fittings, valves, and strainers and troweled smooth to thickness of adjacent covering. Strainer cleanout plugs shall remain accessible. Covers fabricated from molded pipe covering may be used in lieu of cement, provided covers are neat and well secured.

- b. Jacket flap shall be sealed down with factory applied self-sealing lap. Seams shall be lapped not less than 40 mm. Jacket shall be secured with aluminum bands installed at 300 mm centers.
- c. Exposed outdoor insulation shall have an additional 0.40 mm minimum thickness aluminum jacket applied over the completed insulation. The jacket shall have a factory applied moisture barrier and shall be Childers; Smith; or equal.

End joints shall be lapped with aluminum holding traps located directly over the lap. Additional aluminum holding straps shall be placed at 200 mm centers. Jacket at ells and tees shall be mitered, or premanufactured fitting jackets shall be provided, with additional aluminum holding bands, as required. All joints shall be sealed watertight using silicon type, heat resistant sealant.

- d. In-ground insulation shall have an additional PVC jacket applied over the completed insulation and vapor barrier. PVC jacket shall be made water with adhesive or sealant as recommended by the PVC jacket manufacturer.

Pipe safety insulation.--Pipe safety insulation shall be installed in accordance with the manufacturer's recommendations.

Duct insulation.--Ragged edges shall be repaired or taped. Coverings shall be neatly finished at joints and edges. Each joint shall have a 50 mm minimum lap.

Where transitions are made between externally covered ducts and lined ducts, the lined duct shall be overlapped 200 mm with external covering.

Insulation shall be flush with but not cover control devices, damper controls or access doors.

Before insulation is wrapped around concealed ducts, an adhesive shall be spot applied at a maximum of 100 mm centers on each side of the ducts to prevent sagging of the insulation. Insulation shall be wrapped entirely around the ducts and shall be wired securely in place with No. 16 copper clad wire, metal bands at least 10 mm wide or plastic ties. Supports shall be spaced a maximum of 300 mm on centers. Metal bands shall be installed with the use of a banding machine. Seams in the insulation shall be taped.

The finished insulation covering shall be even and level and shall not contain humps.

Plenum and duct liner.--Plenums and exposed ducts shall be lined with plenum and duct liner. Plenums and ducts shall be sized to provide the clear inside dimensions shown on plans after the liner is installed.

The insulation shall be applied with coated side exposed to air stream to prevent surface erosion.

The lining shall be fastened in place with adhesive and with studs with washers spaced a maximum of 500 mm on center each way.

Applying adhesive.--The adhesive shall be liberally applied over entire interior surfaces of ducts or plenums.

Stud installation.--Studs shall be installed as follows:

- a. Cement-In-Place Type Studs.--Cement-in-place type studs shall be cemented in place with adhesives manufactured for this purpose and shall be as recommended by the stud manufacturer. Cement-in-place type studs shall be used where concrete walls form part of plenum.
- b. Percussive Welding Type Studs.--Percussive welding type studs shall be carefully welded in place with current settings that will not appreciably burn galvanizing on opposite side of the sheet metal.
- c. Pneumatic Driven Type Studs.--At locations where pneumatic driven type studs are used, hardened steel backup plates or dollies shall be used under the sheet metal.

12-15.04 PLUMBING FIXTURES

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing plumbing fixtures in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

General.--Plumbing fixtures shall be white in color and shall meet the following requirements:

Water closet (disabled accessible, 6 liters per flush, floor mounted with tank).--

Disabled accessible water closet shall be 6 liters per flush maximum, vitreous china, siphonable jet, 410 mm to 440 mm high elongated bowl, close coupled tank, floor mounted, with solid plastic open front elongated seat with check hinges. Water closet shall meet or exceed Americans with Disabilities Accessibility Act Guidelines (ADAAG) and ANSI Standards: A117.1 and A112.19.2. Closet and accessories shall be of the following types or equal:

	American Standard	Crane	Universal Rundle
Closet	"Cadet 17 EL1.6/PA" 2168.100 or 4086.800	"Hymont" 3-154E or 3-152 with3-655	"Atlas 1.5" UR 4078-341 or UR 4078-342
Seat	Church 5321.070	Olsonite 95	Benke 527

Water closet (6 liters per flush, floor mounted with tank).--

Water closet shall be 6 liters per flush maximum, vitreous china, siphon jet, elongated bowl, close coupled tank, floor mounted, with solid plastic open front elongated seat with check hinges. Tank shall be water pressurized air reservoir type. Water closet shall meet or exceed ANSI Standard: A112.19.2. Closet and accessories shall be the following types or equal:

	American Standard	Crane	Kohler
Closet	"Cadet EL 1.6/PA" 2292.100	"Economiser" 3-604	"Wellworth" K-3458
Seat	Olsonite 95	Church 5321.070	"Lustra" K-4670-C

Water closet seat.--

Urinal.--

Urinal shall be vitreous china, wall hung, washout, 20 mm top spud, integral shields, spreader and trap. Urinal and valve shall be of following types or equal:

	American Standard	Crane	Kohler
Urinal	"Washbrook" 6501.010	"Cromwell" 7-187	"Bardon" K-4960-T
Flush valve	Exposed, diaphragm type, chrome plated, with oscillating handle, integral control stop, adjustable tail piece and vacuum breaker suitable for use with 20 mm spud urinals.		

Urinal (disabled accessible).--

Urinal shall be vitreous china, wall hung, siphon jet or washout, top spud, integral shields, spreader and trap, with 380 mm maximum extension from wall. Urinal and valve shall meet Americans with Disabilities Accessibility Act Guidelines (ADAAG) and shall be of following types or equal:

35

	American Standard	Crane	Kohler
Urinal	"Allbrook" 6540.017	"Manhattan" 7-109	"Bardon" K-4960-T
Flush valve	Exposed, diaphragm type, chrome plated, with oscillating handle, integral control stop, adjustable tail piece and vacuum breaker suitable for use with top spud urinals.		

Lavatory (wall-mounted).--

Lavatory shall be vitreous china, with back, integral perforated grid drain, drilled for 102 mm centers, size 508 mm x 457 mm, with single extra long lever mixing faucet and chair carrier with concealed arms. Lavatory shall be equipped with temperature controls to limit the hot water supply to 43°C. Lavatory shall be equipped with a flow limiting device that limits the flow rate of hot water to no more than 2 liters per minute. Lavatory and accessories shall be of the following types or equal:

	Eljer	Crane	Kohler
Lavatory	"Lucerne" 0355.012	"Norwich" 1-194-V	"Greenwich" K-2032
Drain	--	C-1065-G or Moen 52659	K-7715
Supplies	Brass Craft FR1711C	C-1151 or Moen 52664	K-7605
Faucet	2385.130	Moen 8400	K-15592-5
Trap	32 mm chromium plated brass exposed bent tube adjustable 1.37 mm (17-gage) minimum thickness.		
Carrier	Concealed wall mounted carrier with leveling screws and locking devices; Zurn, J.R. Smith, Josam, Wade, Jonespec, or equal.		

Mop sink.--

Mop sink shall be acid resisting enameled cast iron, 711 mm x 711 mm outside dimensions, 75 mm trap, vinyl coated rim guard, vacuum breaker faucet with hose and wall hook. Sink and accessories shall be of the following types or equal:

	American Standard	Eljer	Kohler
Mop sink	"Florwell" 7740.020	"Custodial" 242-0050	"Whitby" K-6710
Strainer	7721.038	803-0630	K-9146
Faucet	8344.111	749-1450	K-8928

Service sink.--

Service sink shall be acid resisting enameled cast iron, plain undrilled back, stainless steel strainer, stainless steel or chrome plated sheet brass rim guard on three sides, size approximately 560 mm x 460 mm, with 75 mm trap with cleanout and floor mounting flange. Sink and accessories shall be of the following types or equal:

	American Standard	Eljer	Kohler
Service sink	"Lakewell" 7692.023	242-0120	"Bannon" K-6718
Strainer	8301.061	-----	-----
Trap	7798.176	804-1060 w/strainer	K-6673 w/strainer
Faucet	Bucket hook, vacuum breaker, integral stops, top brace, long spout with hose threads.		
	8344.111	749-1200	K8907

Kitchen sink.--

Kitchen sink shall be constructed of 18-gage minimum stainless steel with full undercoating. Sink shall be single compartment, self-rimmed with ledge for faucet. Normal bowl size shall be 533 mm x 381 mm with an outside depth of 178 mm or less. Sink shall be supplied with stainless steel strainer and chrome p-trap. Kitchen sink faucet shall be metal body, chrome plated, single lever mixing type with 200 mm long spout aerator and replaceable ceramic cartridge.

Water heater shall be equipped with an ASME labeled, tank mounted, pressure and temperature relief valve sized for maximum input.

Water heater (LPG).--

Water heater shall be minimum capacity as shown on plans, designed for minimum 860 kPa, glass lined, and equipped with gas pressure regulator, magnesium anodes, cold water drop tube, high temperature energy shut-off device, valved drain, high density R-1.4 K•m²/W minimum foam insulation and finished with a steel jacket with baked enamel finish. Water heater shall meet the requirements of the California Energy Commission.

Water heater shall be equipped with an ASME labeled, tank mounted, pressure and temperature relief valve sized for maximum input.

Emergency eyewash and shower.--

Emergency eyewash and shower shall be separate drench shower and eye bath, 32 mm minimum, galvanized steel pipe stand with 229 mm floor mounting flange and equipped with 216 mm x 279 mm pictorial and worded emergency identification sign.

Shower head shall have a 254 mm diameter ABS plastic head with a stay-open ball valve operated by a rigid pullrod with triangular handle.

Eyewash shall have a 254 mm diameter stainless steel bowl, anti-surge heads and circular chrome plated spray ring to bathe the entire face, dust cover assembly, and a stay-open ball valve operated by a flag handle. Eyewash unit shall be mounted on the shower pipe stand.

Emergency eyewash and shower shall be Haws, 8346; Speakman, SE-607; Western, 9231; or equal.

PART 3.- EXECUTION

INSTALLATION.--

General.--All finish for exposed metal on any fixture, including wall flanges, bolts, nuts and washer, shall be polished chrome plated.

Fixtures shall be sealed to wall or floor with silicone caulk bead.

All exposed metal surfaces on fixture supports shall be enameled to harmonize with fixtures.

Wall mounted fixtures shall be installed on concealed chair carriers designed to support weight of fixture from the floor, made for the specific fixture to be supported and for the particular installation conditions.

All fixtures, including showers, shall be provided with accessible metal stop valves.

Hot water supply, trap and tailpiece on lavatories shall be wrapped with insulating material.

Flush valves for fixtures designated on the plans as disabled accessible shall be installed so that the valve handle is on the widest side of the toilet space.

FIXTURE MOUNTING HEIGHTS.--

General.--Unless otherwise noted, fixtures shall be mounted at the heights shown on the plans.

Service sink.--Service sink double faucet shall be mounted on wall above sink back with spout outlet face 400 mm above service sink rim.

Mop sink.--Mop sink double faucet shall be mounted on wall above sink back with spout outlet face one meter above the floor.

Water heater.--Water heater shall be installed with seismic restraints, inlet ball valve and insulating connections, and 20 mm pressure and temperature relief drain pipe.

Emergency eyewash and shower.--Emergency eyewash and shower shall be installed with a rigid bracket located 1.2 m above the floor. Bracket shall be minimum 1.52 mm (16-gage) steel and shall be braced to the wall.

FIELD QUALITY CONTROL.--

Testing.--The Contractor shall test piping in accordance with the requirements specified elsewhere in these special provisions.

All installed fixtures shall be tested for proper operation after all plumbing work has been completed.

12-15.05 WHEELCHAIR ACCESSIBLE SHOWER UNIT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing a wheelchair accessible shower unit and fittings in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, installation instructions and color palette shall be submitted for approval by the Engineer.

QUALITY ASSURANCE.--

Codes and standards.--Shower units shall conform to the requirements of the California State Accessibility Standards contained in the California Building Standards Code, Title 24.

PART 2.- PRODUCTS

Shower stall.--

Shower stall shall be single unit, single piece construction with clear interior dimensions of 1524 mm wide, 760 mm deep, 2030 mm high, and no obstruction at the threshold. Shower stall shall be fabricated from gel-coated fiberglass or acrylic with a Class I Flame Spread. Shower unit shall be reinforced to accommodate the grab bars and seat.

Shower unit shall have a threshold or recessed drop, a maximum of 13 mm in height, sloped at an angle not exceeding 45 degrees from the horizontal. The floor shall be slip-resistant, sloping a maximum of 4 percent to a drain located near the rear wall.

Shower unit shall be provided with the following fittings and accessories: stainless steel corner grab bar and folding teakwood or woodgrain phenolic wheelchair transfer seat, each capable of resisting 1112 N of lateral, vertical and tensile load, stainless steel soap dish, chromium plated or stainless steel curtain rod, chromium plated steel hand-held shower head with ball joint, chromium plated 1525 mm long flexible shower spray hose, chromium plated fixed shower head, chromium plated metal outlet drain with removable strainer, chromium plated single lever control thermostatic mixing valve with control cartridge with no metal to metal wearing surface, a lever operated shower head selector, and vinyl shower curtain with corrosion resistant hooks.

Shower stall units shall be Crane; Florestone; Maron and Associates; or equal.

PART 3.- EXECUTION

INSTALLATION.--

General.--Shower shall be installed with the manufacturer's instructions. All joints shall be sealed and caulked watertight.

12-15.06 LIQUEFIED PETROLEUM GAS (LPG) SYSTEM

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of relocating liquefied petroleum gas (LPG) distribution system in accordance with the details shown on the plans and these special provisions.

The LPG distribution system shall include the LPG storage tanks, pipe, fittings, valves and such other system components necessary for the proper installation and operation of the LPG system.

QUALITY ASSURANCE.--

Codes and standards.--All work performed and materials installed shall conform to the California Building Standards Code, Title 24, Part 4 and Part 5; the California Code of Regulations, Title 8, Chapter 4, Subchapter 1, Article 5; and National Fire Protection Association Standard No. 58.

PART 2.- PRODUCTS

Tank valves, fittings, regulators and accessories.--

Tank valves, fittings, regulators and accessories shall be UL listed and labeled. Valves, fittings, regulators and accessories shall be as required by the California Codes listed above and shall be Rego, Fisher, Rockwell, or equal.

Pipe and fittings (at the tank and underground).--

Pipe and fittings shall be as specified under "Pipe, Fittings and Valves" in Section 12-15, "Mechanical," of these special provisions. Piping below grade shall be factory coated.

Warning signs.--

Warning signs shall be aluminum, not less than 1.0 mm thick with a baked enamel coating and shall have red letters on a white background.

PART 3.- EXECUTION

INSTALLATION.--

General.--The LPG tank and system components shall be installed in accordance with NFPA standards, the manufacturer's instructions and the approved installation drawings.

Foundation.--The tank shall be installed on a concrete foundation. The tank installation shall include seismic restraint and provisions for expansion and contraction. Neoprene or asphalt impregnated felt anti-corrosion pads shall be installed between the saddle and the concrete foundation.

The concrete foundation shall be constructed in accordance with the requirements specified for minor work under "Cast-In-Place Concrete" in Section 12-3, Concrete and Reinforcement," of these special provisions.

All openings shall be capped until ready for field connections. Piping shall be supported adequately, with allowance for swing joint movement.

Piping installation.--Piping shall be buried 900 mm minimum depth and shall be provided with cathodic protection. Insulating unions shall be installed at least 150 mm above grade between the coated pipe and the above ground pipe lines.

Joints for underground piping shall be cleaned, primed and wrapped in accordance with the requirements specified under "Pipes, Fittings and Valves" in Section 12-15, "Mechanical," of these special provisions. The cleaning, priming and wrapping of pipe joints shall be completed after testing the piping system.

Cathodic protection shall be installed in accordance with the details shown on the plans and the requirements specified under "Cathodic Protection" in Section 12-15, "Mechanical," of these special provisions.

Coated pipe inspection.--The coating on all coated pipe shall be inspected for flaws prior to any testing, and shall be reinspected after testing and before the cleaning, priming and wrapping of the joints.

Warning sign installation and application.-- Three warning signs with the words "NO SMOKING, OPEN FLAMES OR OTHER SOURCE OF IGNITION PERMITTED WITHIN 15.2 METERS (50 FEET)" shall be placed at the locations shown on the plans. Sign lettering shall be standard-type not less than 38 mm in height. The lettering color shall be in sharp contrast to the color of the sign.

FIELD QUALITY CONTROL.--

Testing.--After construction, installation and pipe testing, the LPG system shall be pressure tested with air or nitrogen. The system shall be tested for a minimum time period of 30 minutes at 1380 kPa. If any leaks are detected during the test, the system shall be repaired and retested until no leaks are detected.

After the pressure tests have been completed, the LPG system shall be purged 5 times with methanol (methyl alcohol), using one-liter per 1000 liters water capacity, to remove moisture from the system.

After testing and purging the system, the tank shall be filled to 25 percent of the water capacity of the tank, measured in liters, with State-furnished LPG as provided under "State-Furnished Materials" in Section 8, "Materials," of these special provisions.

An operational test shall be performed on the LPG system upon completion of the pressure tests, the purging of the system and the delivery of the State furnished LPG fuel. The operational test shall consist of operating all LPG equipment for a period of three 24-hour days.

12-15.07 HEATING, VENTILATING AND AIR CONDITIONING EQUIPMENT AND SYSTEMS

PART 1.- GENERAL

Scope.--This work shall consist of furnishing, installing and testing heating, ventilating and air conditioning (HVAC) equipment and systems in accordance with the details shown on the plans and these special provisions.

The performance rating and electric service of the HVAC equipment shall be as shown on the plans.

Temperature controls.--Thermostats, relays, timer switches, and other sensor type control devices required for this work shall be furnished and installed by the supplier of the heating, ventilating and air conditioning equipment. All temperature control wiring shall be furnished and installed in accordance with the requirements specified in Section 12-16, "Electrical," of these special provisions.

Codes and standards.--Equipment and systems shall conform to California State Energy Commission Regulations and, where applicable, shall be American Refrigeration Institute (ARI), American Gas Association (AGA), Sheet Metal and Air Conditioning Contractors National Association, Inc. (SMACNA), and Air Movement and Control Association (AMCA) approved for performance ratings and application shown on the plans.

Any appliance for which there is a California standard established in the Appliance Efficiency Standards may be installed only if the manufacturer has certified to the Commission, as specified in those regulations, that the appliance complies with the applicable standards for that appliance. Space conditioning equipment may be installed only if the manufacturer has certified that the equipment meets or exceeds all applicable efficiency requirements listed in the Energy Efficiency Standards.

PART 2.- PRODUCTS

HEATING AND COOLING UNITS.--

Furnace.—

Furnace shall be gas fired, sealed combustion system, induced draft, high efficiency, listed condensing furnace. Furnace shall be AGA approved for LPG, shall be equipped with electronically controlled blower and hot surface ignition. Furnace cabinet shall have an enamel finish and the primary and secondary heat exchangers shall be corrosion resistant construction. Blower shall be vibration-isolated.

Furnace shall be listed for use of plastic combustion and vent pipe from the unit to the outside of the building. Combustion air and vent pipe shall extend through a single concentric terminal assembly supplied by the furnace manufacturer. Dual pipe penetrations shall not be allowed.

The fan and fan motor shall provide the specified air circulation, with filters, against external static pressure as shown on the plans.

Split system furnace/air conditioner shall include a cased evaporator coil, a remote outdoor condensing unit and economizer. Indoor evaporator coil shall be a factory assembled unit by the forced air furnace equipment manufacturer. Furnace and cased coil unit shall be designed to mate with each other. Unit shall be provided with a refrigerant metering device and corrosion-resistant condensate drain pan with drain connections. The wetted coil air friction shall not exceed 75 Pa. The cased coil unit shall have the same finish as the furnace.

Refrigerant lines and condensate drain piping shall be as specified elsewhere in these special provisions.

Outdoor condensing unit shall be same manufacturer as indoor unit; air cooled, factory assembled, charged and tested, and wired for single point power and control connections. Unit shall be enclosed in a weatherproof acoustically lined cabinet with access panels and a baked-on enamel finish. The compressor shall be the hermetically sealed type pressure relief valve, high and low pressure switches, liquid-line filter-dryer, crankcase heater, short cycling protection, and service valves.

Unit heater.--

Unit heater shall be gas-fired, propeller fan type, AGA approved for LPG and shall be equipped with aluminized steel heat exchanger, built in backdraft diverter, fan switch marked "SUMMER"- "WINTER," adjustable discharge louvers, gas pressure regulator, intermittent ignition device, gas main and pilot shutoff valves, automatic gas valve, high limit shutoff, 24-volt transformer, and fan motor local disconnect. All components shall be factory assembled. Unit heater shall be Reznor; Modine; Hastings; or equal.

Unit heater fan motor shall have integral thermal overload protection.

FANS AND VENTILATORS.--

Exhaust fan (ceiling mounted).--

Exhaust fan shall be ceiling mounted, AMCA certified and shall be equipped with grille, backdraft damper and metal housing. Exhaust fan motor shall have integral thermal overload protection. Ceiling exhaust fan shall be Breidert, ILG, Penn, or equal.

Combination heat lamp/light/fan.--

Combination heat lamp/light/fan shall be ceiling mounted, recessed type unit with metal housing, grille and backdraft damper. Ducting size shall be as required by the manufacturer. Combination heat lamp/light/fan shall be Broan, No. 164; Nutone, No. 9427; or equal.

Fume exhaust fan.--

Fume exhaust fan shall be AMCA certified and shall be equipped with metal housing, centrifugal fan wheel, backdraft damper and bird screen. Fan motor and fan assembly shall be isolated from base with rubber vibration isolators. Fan motor shall have integral thermal overload protection. Roof fan shall be completely weatherproof and shall have a disconnect means under the hood. Roof curb shall be insulated and shall be supplied by the fan manufacturer. Roof fan shall be Penn; Jenn-Air; Cook; or equal.

HVAC CONTROLS.--

Unit heater thermostat.--

Unit heater thermostat shall be 120 volt in line type, single set point range internally adjustable from 4°C to 27°C, and provided with a blank cover.

Thermostat (office only).--

Thermostat shall be 24-volt, 7-day programmable, electronic heating/cooling thermostat, with the ability to program the fan-on mode during normal working hours, and fan-off mode during unoccupied periods. Thermostat shall be provided with sub-base selector switches for "AUTO-HEAT-OFF-COOL" and fan "AUTO-ON". Thermostat shall have full temperature range setback capacity. Thermostat shall be Robertshaw, 7900; Honeywell, T7300; or equal.

Thermostat guard.--

Thermostat guard shall be clear plastic w/lockout key cover. Thermostat guard shall be Dayton, Honeywell, or equal.

Time switch.--

Time switch shall be one-hour, spring-wound, "OFF" type time switch without a "HOLD" feature. Time switch shall be Intermatic, Type F60M; Tork, A500 Series; or equal.

AUXILIARY HVAC COMPONENTS.--

Unless specified herein, all components shall be sized and have the characteristics as shown on the plans.

Rigid ductwork.--

Rigid ductwork shall be galvanized steel sheet metal conforming to the latest edition of the SMACNA "Low Velocity Duct Construction Standards." Galvanized steel shall be cleaned by washing with mineral spirit solvent sufficient to remove any oil, grease or other materials foreign to the galvanized coating.

Spiral duct.--

Spiral duct shall be prefabricated type.

Duct supports.--

Duct supports shall be hot-dip galvanized steel.

Flexible ductwork.--

Flexible ductwork shall be UL 181, Class 1 air duct rated and shall meet the requirements of NFPA 90-A and the California Mechanical Code. Duct shall have steel helix wire, flexible insulation, minimum thermal resistance of $R-0.7$ ($m^2 \cdot K/W$), and flame resistant vapor barrier. Inner and outer surfaces shall be non-metallic. Outer surface shall be Copolymer or Mylar, factory applied.

Flexible connection.--

Flexible connection shall be prefabricated type and shall be commercial quality flexible glass fabric coated on both sides with neoprene or hypalon.

Ceiling diffuser (for gypsum board ceilings).--

Ceiling diffuser for gypsum board ceilings shall be rectangular or square type. Diffuser shall be steel with oven baked-on enamel bone white dull finish or extruded aluminum, equipped with a removable core and a standard flanged frame with sponge rubber or felt gasket. Diffuser shall have individually adjustable curved blades, counter-sunk screw holes, shall be surface mounted, with face velocity less than 3.05 m/s; Titus, 250; Air Mate, 400-O; Hart and Cooley, A40; or equal.

Return register (for gypsum board ceilings).--

Return register for gypsum board ceilings shall be rectangular or square, and shall be steel with oven baked-on enamel bone white dull finish or extruded aluminum, fixed bar type, die formed louvers set at 45 degrees, 13 mm spacing maximum, surface mounted; Titus, 335; Air Mate, 280; or equal.

Balance damper.--

Balance damper shall be butterfly type, 1.52 mm (16-gage) minimum galvanized steel blade, end bearings with steel shaft and locking and indicator operator. Balance damper shall be Ventlock, Young, Anemostat, or equal.

Air filter (for HVAC units).--

Air filter shall be permanent metal viscous impingement type, constructed of aluminum or galvanized steel, 50 mm minimum thickness and be approved for Class 2 use. Filter shall have a minimum efficiency rating of 50 percent as determined when tested in accordance with ASHRAE Test Standard 52. Filter shall be mounted in 1.52 mm (16-gage) galvanized steel holding frames. Two cans of recharging adhesive shall be provided with the filter and shall be nearly odorless, have a high flash point, rapid wetting characteristics, dye tracer and be water soluble. Filter shall be Airspan, Type AF, Eco-Air Products, Inc., Type HIA; Snyder General, Type AAF; or approved equal.

Vents and flues (for heaters).--

Vents and flues for heaters shall be approved Type B or approved plastic vents for condensing furnaces.

Refrigerant and condensate drain piping.--

Refrigerant and condensate drain piping shall be rigid, Type L copper tubing with brazed solder fittings. The suction line shall be insulated, with vapor barrier and shall be weatherproofed for exterior installation. Factory sealed tubing shall not be used.

PART 3.- EXECUTION**INSTALLATION.--**

Heaters.--Furnaces and unit heaters shall be installed in such a manner as to insure adequate furnace clearance and separation of combustion air and circulating air. Appliances shall be connected to a rigidly mounted gas pipe supply system by an AGA approved flex connector and gas valve.

Ventilators.--Exhaust ducts connected to exhaust fans shall be routed as shown on the plans and shall terminate in a weatherproof cap. Duct sizes shall be as shown on the plans or as recommended by the manufacturer, whichever is larger.

Roof fans shall be curb mounted.

Condensate drains.--Air conditioning units shall be provided with condensate drain trap and piping. Piping shall extend as shown on the plans. Air gap shall be installed where required by code. Interior condensate drain piping shall be insulated with foam insulation.

Mounting heights.--Thermostats and time switches shall be installed as shown on the plans.

Temperature controls.--Temperature control for each unit heater shall be provided by 2-120 volts in line thermostats and a time switch. One thermostat shall be set at 7°C. for low-limit temperature control and the second thermostat shall be set at 21°C. The first thermostat shall energize the heater whenever the temperature is below the setpoint. The second thermostat shall be wired in series with the time switch and shall de-energize the heater above the setpoint.

Each thermostat shall be insulated from the outside walls, and shall be provided with an aluminum radiation shield above the thermostat.

The time switch shall be installed beside the thermostat or where shown on the plans.

Air outlets.--Volume dampers shall be furnished and installed for all diffusers. Blocking shall be provided on all sides of air outlets between ceiling or wall joists. Collars shall be supplied for all outlets and shall be taped and sealed in place.

Vents and flues.--Vents and flues shall be securely fastened to the building construction, shall be provided with a collar at all ceiling penetrations and shall terminate with a weather cap fabricated of the same material.

Access door.--Access doors shall be provided in rigid ducts and plenums for access to volume dampers, fire dampers and control devices located within such ductwork; and shall be provided at such other locations as shown on the plans.

Ducts and vents.--Ductwork within the building shall be installed to clear lighting fixtures, doors, windows and other obstructions. Ductwork shall preserve head room and shall keep openings and passageways clear whether shown on plans or not.

Ductwork shall be installed and braced according to the latest edition of the SMACNA "HVAC Duct Construction Standards."

Slopes in sides at transitions shall be approximately one to five. The ductwork system shall not contain abrupt changes or offsets of any kind unless otherwise shown on the plans.

Where ducts pass through walls, floors or ceilings, galvanized sheet metal or steel angle collars shall be installed around the ducts.

Duct sections shall be connected by beaded sleeve-type couplings using joint sealer as recommended by the duct manufacturer. Duct sections shall be mechanically fastened with pop rivets or sheet metal screws and sealed with mastic or insulated, reinforced silver tape.

Flexible connections shall be provided at both inlet and outlet of fan coil and ventilating units.

Sheet metal plenums shall be adequately braced and supported from the floor or structure with structural steel angles to prevent sagging, flexing and vibration.

All standing seams and transverse joints of supply, return and exhaust ducts and seams around plenums, fan and coil housings shall be sealed with sealant and taped.

Ductwork identification.--Ductwork shall be identified as follows:

Duct Description	Identification Symbol
Supply duct	S
Return duct	R
Exhaust duct	EXH
Outside air duct	OA

Identification symbol letters shall be stenciled at locations visible from the access routes to be used by maintenance workers. Such letters shall be painted with black colored paint and shall be a minimum of 50 mm high.

FIELD QUALITY CONTROL.

Pre-test requirements.--Before starting or operating systems, equipment shall be cleaned and checked for proper installation, lubrication and servicing.

The final air quantities shall be achieved by adjusting the balance dampers or the fan RPM.

Final adjustments and balancing of the systems shall be performed in such a manner that the systems will operate as specified and as shown on the plans.

The Contractor shall replace or revise any equipment, systems or work found deficient during tests.

All automatic operating devices which are pertinent to the adjustment of the aforementioned air systems shall be set and adjusted to deliver the required quantities of air and at temperatures specified by the Engineer. All control work shall be done in collaboration with the control manufacturer's representative.

Project completion tests.--The Engineer shall be notified at least 3 working days in advance of starting project completion tests.

The project completion tests shall consist of the following:

1. **Air Systems.**--All air systems shall be tested and balanced to the conditions set forth on the plans and in these special provisions. This work shall be performed by an Associated Air Balance Council (AABC) or National Environmental Balancing Bureau (NEBB) certified contractor. The air systems include, but are not necessarily limited to, the following:
 - a. Supply air systems
 - b. Return air systems
 - c. Exhaust air systems
2. **Operational Data.**--The tests shall include operation of the heating, cooling, and ventilating systems for not less than two 8-hour days, each system shall operate at not less than 90 percent of their full specified capacities.

The required data shall be accurately measured. The data shall be measured during one operational cycle in the presence of the Engineer and shall be submitted for approval.

The following data shall be measured and tabulated:

- a. Ambient temperatures and conditions, °C
- b. Supply and return air quantities, L/sec, each room
- c. Thermostat set point, °C
- d. Air temperatures at room center, °C
- e. Fan motor amperages and voltages
- f. System static pressures, Pa

12-15.08 CATHODIC PROTECTION

PART 1- GENERAL

This work shall consist of providing cathodic protection for LPG pipes in accordance with the details shown on the plans and the requirements in these special provisions.

SUBMITTALS.--Descriptive data for anodes, test stations, test boxes, and fusion welded connections shall be submitted for approval.

PART 2- PRODUCTS

Anodes.--

Anodes shall be magnesium, prepackaged in cloth bags containing hydrated gypsum and bentonite clay; Dow, Galvo Mag; Kaiser, Electromag; or equal.

Anode test station.--

Anode test station shall be conduit mounted non-metallic terminal board with integral compression-fit base and screw on cover. The terminal board shall have nickel plated brass factory installed hardware. The test station shall be fabricated of white polycarbonate.

Anode test box.--

Anode test box shall be precast concrete box with terminal board as described herein and cast iron locking traffic cover marked "ANODE"; Christy, B3; Brooks, 3TL; or equal.

Conductors.--

Conductors shall be solid No. 12 AWG copper, Type TW or THW, insulation colored black for anode and red for all others.

Fusion weld material.--

Fusion weld material shall be a mixture of copper oxide and aluminum.

PART 3- EXECUTION

INSTALLATION.--Excavation and backfill shall be in accordance with the requirements specified under "Earthwork for Building Work" in Section 12-2, "Sitework," of these special provisions.

Impervious wrapping around the cloth bag packaged anode shall be removed immediately before installing the anode.

Anodes shall be installed at the locations shown on the plans. The packaged anode shall be wetted thoroughly before backfilling. Backfill material placed to 300 mm above the anode shall be native soil, free from aggregate larger than 13 mm in size.

Conductors shall be connected to pipes by fusion welding. Connection to the lift post shall be located to remain visible. All other connections shall be insulated watertight after inspection by the Engineer.

Fusion weld connection to steel surface shall be made of molten copper produced by exothermic reaction following ignition of a mixture of copper oxide and aluminum flowing into weld cavity of a properly fitting graphite mold.

Each pipe conductor shall connect only one pipe to a terminal on the terminal board in the anode test box except where otherwise shown on the plans.

Pipe conductors shall have 300 mm slack at pipe connections and 600 mm slack at the anode test box.

Conductors shall be direct buried and located safe from damage due to construction operations.

All metals connected to cathodic protection, except plastic-coated pipes, shall be tape-wrapped as specified under "Pipe, Fittings and Valves" in Division 15, "Mechanical," of these special provisions. Cathodically protected metals shall be isolated from all other metals.

TESTING.--

CATHODIC PROTECTION TESTING.--Cathodic protection systems shall be tested by a corrosion technician certified by the National Association of Corrosion Engineers (NACE). Tests shall include the following:

1. Isolation of protected metal from electrical conduit, piping for water and sewage, fuel island vents, steel the building, or other metals.

If the same potential is measured from a stationary copper-copper sulphate half cell to any foreign structure as to the protected structure, the protected structure shall be deemed to be metallicity connected to the foreign structure and the installation shall be deemed unacceptable.

2. Anode current.
3. Polarized potential.

An instant-off potential of less than 850 millivolts shall be deemed to indicate an unacceptable installation. The instant-off potential shall be the voltage between the protected structure and a copper-copper sulphate half cell measured after the immediate shift that occurs when anode current is interrupted, but before any further current decay.

4. Anode potential.

The anode open-circuit potential shall be at least 95 percent of the value listed in the manufacturer's published data for the type of anode furnished.

The tests shall be performed after all reinforcing steel, conduits, pipes and other foreign structures that might be inadvertently connected to the protected structures have been installed and backfilled or encased.

The corrosion technician shall submit a written report certifying the cathodic protection. The report shall indicate each measurement made and its recorded value.

SECTION 12-16. ELECTRICAL

12-16.01 ELECTRICAL WORK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of performing electrical work in accordance with the details shown on the plans and these special provisions.

Electrical work shall include furnishing all labor, materials, equipment and services required to construct and install the complete electrical system shown on the plans and the work of installing electrical connections for the thermostats, motors, and controls specified elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of conduits and other facilities and location of equipment is to be governed by structural conditions and other obstructions, and shall be coordinated with the work of other trades. Equipment requiring maintenance and inspection shall be located where it is readily accessible for the performance of such maintenance and inspection.

Related work.--Earthwork, foundations, sheet metal, painting, mechanical and such other work incidental to and necessary for the proper installation and operation of the electrical work shall be done in accordance with the requirements specified for similar work elsewhere in these special provisions.

CLOSEOUT SUBMITTALS.--

Operation and maintenance manuals.--Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be in a bound manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material will be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

Manuals shall be submitted for the following equipment:

Intrusion alarm system

QUALITY ASSURANCE.--

Codes and standards.--All work performed and materials installed shall be in accordance with the CEC and the California Code of Regulations, Title 8, Chapter 4, "Electrical Safety Orders."

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

TESTING.--

After the electrical system installation work has been completed, the electrical system shall be tested in the presence of the Engineer to demonstrate that the electrical system functions properly. The Contractor shall make necessary repairs, replacements, adjustments and retests at his expense.

12-16.02 BASIC MATERIALS AND METHODS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing conduits, conductors, fittings, and wiring devices in accordance with the details shown on the plans and these special provisions.

Conduits, conductors, fittings, and wiring devices shall include those accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the electrical system.

Related work.--Roof penetrations shall be flashed and sealed watertight conforming to the requirements specified under "Sheet Metal Flashing" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

Where conduits pass through fire rated wall, floor or ceiling assemblies, the penetrations shall be protected in accordance with the requirements specified under "Through-Penetration Firestopping" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for recessed junction and pull boxes, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS

CONDUITS AND FITTINGS.--

Rigid steel conduit and fittings.--

Rigid steel conduit shall be threaded, full weight rigid steel, hot-dip galvanized inside and outside with steel or malleable iron fittings. Fittings shall be threaded unless otherwise specified or shown on the plans.

Split or three-piece couplings shall be electroplated, malleable cast iron couplings.

Insulated grounding bushings shall be threaded malleable cast iron body with plastic insulated throat and steel, lay-in ground lug with compression screw.

Insulated metallic bushings shall be threaded malleable cast iron body with plastic insulated throat.

Electrical metallic tubing (EMT) and fittings.--

Electrical metallic tubing shall be formed of cold rolled strip steel, electrical resistance welded continuously along the longitudinal seam with zinc coating outside and enamel or lacquer coating inside.

Couplings shall be electroplated, rain and concrete tight, gland compression type, steel body couplings with malleable iron nuts.

Connectors shall be electroplated, rain and concrete tight, gland compression type, steel body connectors with male hub, die cast zinc nut and insulated plastic throat.

Flexible metallic conduit and fittings.--

Flexible metallic conduit shall be fabricated in continuous lengths from galvanized steel strip, spirally wound and formed to provide an interlocking design.

Fittings shall be electroplated screw-in type with malleable cast iron body and threaded male hub with insulated throat.

Liquid tight flexible metallic conduit and fittings.--

Liquid tight flexible metallic conduit shall be fabricated in continuous length from galvanized sheet steel, spirally wound and formed to provide an interlocking design with an extruded polyvinyl chloride cover.

Fittings shall be electroplated, malleable cast iron body, with cap nut, grounding ferrule, and connector body with insulated throat.

Rigid non-metallic conduit and fittings.--

Rigid non-metallic conduit shall be Schedule 40, high impact, nonconducting, self-extinguishing polyvinyl chloride (PVC) rigid non-metallic conduit for direct underground burial.

Couplings shall be PVC, socket type or thread on one end and socket type on the other end as required for the particular application.

Terminal adapters for adapting PVC conduit to boxes, threaded fittings, or metallic conduit system shall be PVC adapters with threads on one end and socket type on the other end.

CABLES AND CONDUCTORS.--**25-Pair telephone cable.--**

25-Pair telephone cable shall be AT&T 1024-025A 25/24; General Cable SMPR/CMR 25 pair 24; or equal.

Conductors.--

Conductors shall be stranded copper wire.

Conductor insulation types unless otherwise shown or specified, shall be as follows:

1. Conductors across hinges of control panel enclosures shall be Type MTW.
2. Conductors shall be type XHHW-2 in wet and outdoor locations.
3. Conductors shall be type THHN in dry locations.

Wire connections and devices.--

Wire connections and devices shall be pressure or compression type, except that connectors for No. 10 AWG and smaller conductors in dry locations may be preinsulated spring-pressure type.

ELECTRICAL BOXES.--**Outlet, device and junction boxes.--**

Unless otherwise shown or specified, boxes shall be galvanized steel boxes with knock-outs and shall be the size and configuration best suited to the application indicated on the plans. Minimum size of outlet, receptacle, switch or junction boxes shall be 100 mm square by 40 mm deep, except that switch boxes for the installation of single switches and outlet boxes for flush-mounted light fixtures shall be 50 mm by 75 mm by 40 mm deep.

Multiple switches shall be installed in standard gang boxes, unless otherwise specified or shown on the plans.

Cast metal boxes shall be cast iron boxes with threaded hubs and shall be of the size and configuration best suited to the application shown on the plans.

Flush-mounted boxes shall have stainless steel covers, one mm thick. Cover screws shall be metal with finish to match cover finish.

Unless otherwise shown or specified, surface-mounted boxes shall have galvanized steel covers with metal screws.

Weatherproof junction boxes shall have cast metal covers with gaskets.

Weatherproof switch and receptacle boxes shall have gasketed covers with gasketed hinged flaps to cover switches and receptacles.

Underground pull boxes.--

Pull boxes shall be high density reinforced concrete box with ultraviolet inhibitor polyethylene etched face anchored in concrete and fiberglass cover with hold down bolts. The polyethylene and fiberglass material shall be fire resistant and show no appreciable change in physical properties with exposure to the weather. No. 5 pull box shall be Brooks Products No. 5; Christy Concrete Products, N30; or equal. No. 6 pull box shall be Brooks Products, No. 6; Christy Concrete Products, N36; or equal.

Traffic rated pull boxes shall be high density reinforced concrete box with steel cover with hold down bolts and bonding strap. Pull box and cover shall be designed for H20 loading. No. 5 pull box shall have inside dimensions of 335 mm by 610 mm. No. 6 pull box shall have inside dimensions of 413 mm by 743 mm.

RECEPTACLES AND SWITCHES.--**Ground fault circuit interrupter receptacles, (GFCI)--**

Ground fault circuit interrupter receptacles shall be NEMA Type 5-20R, feed-through type, ivory color, 3-wire, 20-Ampere, 125-Volt AC, grounding type, specification grade, duplex receptacle with ground fault interruption. Receptacle shall detect and trip at current leakage of 5 milliamperes and shall have front mounted test and reset buttons.

Single receptacles.--

Single receptacles shall be NEMA Type 5-20R, 3-wire, 20-Ampere, 125-Volt AC, safety grounding, ivory color, specification grade receptacle suitable for wiring with stranded conductors.

Duplex receptacles.--

Duplex receptacles shall be NEMA Type 5-20R, 3-wire, 20-Ampere, 125-Volt AC, safety grounding, ivory color, specification grade receptacle suitable for wiring with stranded conductors.

Fourplex receptacles.--

Fourplex receptacles shall be NEMA Type 5-20R, 20-Ampere, 125-Volt AC, safety grounding, ivory color, industrial grade receptacle suitable for wiring with stranded conductors.

Management information services (MIS) receptacles.--

Management information services (MIS) receptacles shall be NEMA type 5-20R, 3-wire, 20-Ampere, 125-Volt AC, isolated, grounding type, orange color, specification grade duplex receptacle suitable for wiring with stranded conductors.

Standby power receptacle, SPR.--

600 V, 200 A, 4-wire, 4-pole, circuit breaking, weather resistant, cast iron, rain tight receptacle with male interior assembly, grounded through the conduit system, complete with an AJ back box, angle adapter with a screw on dust cover and chain or self-closing, spring actuated cover. A mating plug to the SPR shall be furnished.

Multi-outlet assemblies.--

Multi-outlet assemblies shall be 3-wire, 15-Ampere, 125-Volt AC, 800 mm long strip, grounding type receptacles spaced 150 mm on center. The assembly shall be provided with the necessary entrance end fitting and blank end fitting.

Snap switches.--

Snap switches shall be 20-Ampere, 120/277-Volt AC, quiet type, specification grade, ivory color switch with silver cadmium alloy contacts. Switch shall be suitable for wiring with stranded conductors.

Motion sensor wall switches.--

Motion sensor wall switches shall be wall-mounted, 3-wire, 1500-Watt incandescent or fluorescent, off-auto-on, passive infrared sensor switch with adjustable photocell override and time delay and shall operate on 120/277 Volts. The sensor switch shall cover a minimum of 84 square meters of floor area, be suitable for installation in a single gang box, and shall have a field of view of not less than 170 degrees. The time delay setting shall be adjustable from 30 seconds to 20 minutes, initially set at 5 minutes. Sensor switch shall be flicker-free type and compatible with electronic ballast.

Three-way toggle switches.--

Three-way toggle switches shall be 20-Ampere, 120/277-Volt AC, quiet type, specification grade, ivory color switch with silver cadmium alloy contacts. Switch shall be suitable for wiring with stranded conductors.

MISCELLANEOUS MATERIALS.--**Warning Tape.--**

Warning tape shall be 100 mm wide and contain the printed warning "CAUTION ELECTRICAL CONDUIT" in bold 19 mm black letters at 760 mm intervals on bright orange or yellow background. The printed warning shall be non-erasable when submerged under water and resistant to insects, acids, alkali, and other corrosive elements in the soil. The tape shall have a tensile strength of not less than 70 kg per 100 mm wide strip and shall have a minimum elongation of 700 percent before breaking.

Pull ropes.--

Pull ropes shall be nylon or polypropylene with a minimum tensile strength of 225 kg.

Watertight conduit plugs.--

Watertight conduit plugs shall be a hollow or solid stem expansion plugs complete with inner and outer white polypropylene compression plates and red thermoplastic rubber seal. Seal material shall be non-stick type rubber resistant to oils, salt, and alkaline substances normally available at the construction sites.

Anchorage devices.--

Anchorage devices shall be corrosion resistant, toggle bolts, wood screws, bolts, machine screws, studs, expansion shields, and expansion anchors and inserts.

Electrical supporting devices.--

Electrical supporting devices shall be one hole conduit clamps with clamp backs, hot-dipped galvanized, malleable cast iron.

Construction channel shall be 41 mm x 41 mm, 2.66 mm (12-gage) galvanized steel channel with 13 mm diameter bolt holes, 40 mm on center in the base of the channel.

Ground rod(s).--

Ground rod(s) shall be a 19 mm (minimum) galvanized or copper clad steel rod, 3 meters long.

Telephone and data outlet boxes.--

Data, and data and voice telephone outlet boxes shall be 102 mm square boxes and plates with modular type telephone outlet. Boxes on stud walls shall have plaster ring. Voice and data outlet jacks are combination of data and telephone jacks. Data jacks shall be 8-wire, RJ45 unkeyed data jacks, Category 5 compliant TIA/EIA 568A standard pin out. Telephone jacks shall be 4-wire, RJ11 jacks.

Plates for flush mounting outlets in finished room shall be Type 430 stainless steel, one mm thick with satin finish.

PART 3.- EXECUTION

INSTALLATION.--

Conduit, general.--Rigid steel conduit shall be used unless otherwise shown on the plans or specified in these special provisions.

Electrical metallic tubing may be used in furred spaces and for exposed work indoors above the switch height.

Unless otherwise specified or shown on the plans, flexible metal conduit shall be used to connect suspended lighting fixtures, motors, HVAC equipment, and other equipment subject to vibration in dry locations.

Unless otherwise specified or shown on the plans, liquid-tight flexible metal conduit shall be used to connect motors, HVAC equipment, and other equipment subject to vibration in wet locations.

Rigid non-metallic conduit shall be used at the locations shown on the plans for direct underground burial 762 mm below grade. All risers and elbows shall be rigid steel.

Conduit installation.--Conduit trade sizes are shown on the plans. No deviation from the conduit size shown on the plans will be permitted without written permission from the Engineer.

Conduit shall be concealed unless otherwise shown on the plans.

Conduits shall be tightly covered and well protected during construction using metallic bushings and bushing "pennies" to seal open ends.

Rigid non-metallic conduit bends of 30 degrees or greater shall be factory-made long radius sweeps. Bends less than 30 degrees shall be made using an approved heat box.

A pull rope shall be installed in all empty conduits. At least one meter of pull rope shall be doubled back into the conduit at each termination.

Locations of conduit runs shall be planned in advance of the installation and coordinated with the ductwork, plumbing, ceiling and wall construction in the same areas and shall not unnecessarily cross other conduits or pipe, nor prevent removal of ceiling tiles or panels, nor block access to mechanical or electrical equipment.

Where practical, conduits shall be installed in groups in parallel, vertical or horizontal runs and at elevations that avoid unnecessary offsets.

Exposed conduit shall be installed parallel and at right angles to the building lines.

Conduits shall not be placed closer than 300 mm from a parallel hot water or steam pipe or 75 mm from such lines crossing perpendicular to the runs.

All raceway systems shall be secured to the building structures using specified fasteners, clamps and hangers.

All metal conduits, metal conduit risers, and metal conduit elbows in contact with soil or concrete shall be wrapped with a double layer of 0.5 mm thick pipe wrapping tape. Each individual layer shall be overlapped a minimum of 50 percent.

Single conduit runs shall be supported by using one hole pipe clamps. Where run horizontally on walls in damp or wet locations, conduit shall be installed with "clamp backs" to space conduit off the surface.

Multiple conduit runs shall be supported with construction channel secured to the building structure. Conduits shall be fastened to construction channel with channel compatible pipe clamps.

Raceways of different types shall be joined using approved couplings or transition fittings.

Expansion couplings shall be installed where conduit crosses a building separation or expansion joint.

All floor and wall penetrations shall be sealed water-tight.

Existing underground conduit to be incorporated into a new system shall be cleaned with a mandrel or cylindrical wire brush and blown out with compressed air.

Conduit terminations.--Rigid steel conduits shall be securely fastened to cabinets, boxes and gutters using 2 locknuts and specified insulating metallic bushing. Electrical metallic tubing shall be securely fastened to cabinets, boxes and gutters using specified connectors. Conduit terminations at exposed weatherproof enclosures and cast outlet boxes shall be made watertight using specified hubs.

Grounding bushings with bonding jumpers shall be installed on all type of conduits terminating at concentric knockouts and on all conduits containing service conductors, grounding electrode conductor, and conductors feeding separate buildings.

Rigid non-metallic conduits shall be terminated inside the underground pull boxes with an approved conduit bushings or fittings. All conduits shall enter the pull box at an angle of 90 degrees or more.

All future conduits terminated in underground pull boxes or exposed indoor and outdoor shall be provided with watertight conduit plugs.

Warning Tape.--Warning tape shall be placed over each conduit in a trench. Each warning tape shall be centered over the conduit and shall be placed over the 150 mm layer of sand covering the conduit as described elsewhere in these special provisions.

Conductor and cable installation.--Conductors shall not be installed in conduit until all work of any nature that may cause injury is completed. Care shall be taken in pulling conductors that insulation is not damaged. An approved non-petroleum base and insulating type pulling compound shall be used as needed.

All cables shall be installed and tested in accordance with manufacturer's recommendations.

Splices and joints shall be insulated with insulation equivalent to that of the conductor.

Provide 155 mm of slack at each outlet and device connection. If the outlet or device is not at the end of a run of wire, connection shall be made with correctly colored pigtails tapped to the runs with splices as specified herein.

Branch circuit conductors in panelboards and load centers shall be neatly trained along a path from the breaker terminals to their exit point. The conductors shall have ample length to transverse the path without strain, but shall not be so long as to require coiling, doubling back, or cramming. The path shall transverse the panelboard gutter spaces without entering a gutter containing service conductors and, unless otherwise shown on the plans, without entering the gutter space of any panelboard feeder.

All pressure type connectors and lugs shall be retightened after the initial set.

Splices in underground pull boxes and similar locations shall be made watertight.

Junction boxes in furred or accessible ceiling spaces shall be identified with felt-tip pen denoting the circuits contained in the box.

Conductor identification.--The neutral and equipment grounding conductors shall be identified as follows:

Neutral conductor shall have a white or natural gray insulation except that conductors No. 4 and larger may be identified by distinctive white marker such as paint or white tape at each termination.

Equipment grounding conductor shall be bare or insulated. If insulated, equipment grounding conductors shall have green or green with one or more yellow stripes insulation over its entire length except that conductors No. 4 and larger may be permanently identified by distinctive green markers such as paint or green tape over its entire exposed insulation.

Ungrounded feeder and branch circuit conductors shall be color coded by continuously colored insulation, except conductors No. 6 AWG or larger may be color coded by colored tape at each connection and where accessible. Ungrounded conductor color coding shall be as follows:

SYSTEM	COLOR CODE
120/208V-Three phase	Black, red, blue

Once an insulated circuit conductor, including grounded and ungrounded conductors, is identified with a specific color code, that color code shall be used for the entire length of the circuit.

Where more than one branch circuit enters or leaves a conduit, panel, gutter, or junction box, each conductor shall be identified by its panelboard and circuit number. All control conductors including control conductors of manufacturer supplied and field wired control devices shall be identified at each termination with the wire numbers shown on the plans, approved working drawings, and as directed by the Engineer where deemed necessary. Identification shall be made with one of the following:

1. Adhesive backed paper or cloth wrap-around markers with clear, heat shrinkable tubing sealed over either type of marker.
2. Self-laminating wrap around type, printable, transparent, permanent heat bonding type thermoplastic film markers.
3. Pre-printed, white, heat-shrinkable tubing.

Each terminal block shall have a molded marking strip attached with screws. The identifying numbers of the terminating conductors, as shown on the plans or on the submittal drawings, shall be engraved in the marking strip.

Outlet, device and junction box installation.--Where exposed threaded steel conduits are connected to an outlet, device, or junction box below switch height, the box shall be a cast metal box. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall be sheet steel boxes. Weatherproof outlet, device and junction boxes shall have cast metal covers with gaskets. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall have standard galvanized covers.

All boxes shall finish flush with building walls, ceiling and floors except where exposed work is called for.

Raised device covers (plaster rings) shall be installed on all boxes concealed in concrete, masonry or stud walls.

No unused openings shall be left in any box. Knockout seals shall be installed as required to close openings.

Outlet, device, and junction boxes shall be installed at the locations and elevations shown on the plans or specified herein. Adjustments to locations may be made as required by structural conditions and to suit coordination requirements of other trades.

Boxes in stud walls and partitions shall not be mounted back to back. Through-wall boxes shall not be used.

Boxes installed in metal stud walls shall be equipped with brackets designed for attaching directly to the studs or shall be mounted on heavy gauge galvanized steel, snap-in box supports.

Fixture outlet boxes installed in suspended ceilings of gypsum board or lath and plaster construction shall be mounted on 1.52 mm (16-gage) metal channel bars attached to main ceiling runners.

Fixture outlet boxes for pendant-mounted fixtures installed in suspended ceilings supporting acoustical tiles or panels shall be supported directly from the structures above.

Underground pull box installation.--Electrical pull box covers or lids shall be marked "ELECTRICAL." Otherwise pull box covers or lids that is being used for lighting circuits shall be marked "LIGHTING." Telephone service and radio pull box covers or lids shall have plain, unmarked covers.

The bottom of pull boxes shall be bedded in 155 mm of clean, crushed rock or gravel and shall be grouted with 40 mm thick grout prior to installation of conductors. Grout shall be sloped to a 25 mm PVC pipe drain hole. Conduit shall be sealed in place with grout.

Top of pull boxes shall be flush with surrounding grade or top of curb. In unpaved areas where pull box is not immediately adjacent to and protected by a concrete foundation, pole or other protective construction, the top of pull box shall be set at plus 30 mm above surrounding grade. Pull boxes shown on the plans in the vicinity of curbs shall be placed adjacent to the back of curb. Pull boxes shown on the plans adjacent to lighting standards shall be placed on the side of foundation facing away from traffic.

Ground rod(s) installation.--The ground rod(s) shall be driven vertically until the top is 155 mm above the surrounding surface. When vertical penetration of the ground rod cannot be obtained, an equivalent horizontal grounding system, approved by the Engineer, shall be installed.

Anchorage.--Hangers, brackets, conduit straps, supports, and electrical equipment shall be rigidly and securely fastened to surfaces by means of toggle bolts on hollow masonry; expansion shields and machine screws, or expansion anchors and studs or standard preset inserts on concrete or solid masonry; machine screws or bolts on metal surfaces; and wood or lag screws on wood construction.

Anchorage devices shall be installed in accordance with the anchorage manufacturer's recommendations.

Mounting heights.--Electrical system components shall be mounted at the following mounting heights, unless otherwise shown on the plans. The mounting height dimensions shall be measured above the finished floor to the bottom of the device or component.

Thermostats	1.1 m office areas 1.25 m equipment bays
Wall switches	1.0 m
Convenience outlets	510 mm office areas 1.25 m, all other areas
Electric water cooler outlet	As recommended by the water cooler manufacturer.
Telephone and data outlets	510 mm office areas, 1.25 m, all other areas

12-16.03 SERVICE AND DISTRIBUTION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing service and distribution equipment in accordance with the requirements of the serving utilities, the details shown on the plans and these special provisions.

Attention is directed to "Utility Connection" in Section 12-1, "General Requirements," of these special provisions regarding arrangements, permits, licenses, charges, fees and costs for utility connections and extensions.

Related work.--Concrete and reinforcement for service pedestal shall conform to the requirements specified for minor work under "Cast-in-Place Concrete," in Section 12-3, "Concrete and Reinforcement," of these special provisions.

SUBMITTALS.--

Installation details.--The Contractor shall submit complete service installation details to the serving utilities for approval. Prior to submitting installation details to the serving utility, the Contractor shall have said drawings reviewed and stamped "APPROVED" by the Engineer. Submittals shall be approved by the serving utility prior to commencing work.

Product data.--A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS

Main switchboard, MSB.--

Main switchboard, MSB, shall contain an underground pull section, metering compartment, service disconnect switch compartment and distribution section for 120/208-Volt, 800-Ampere, 3-phase, 4-wire service. The distribution section shall have molded case circuit breakers as shown on the plans.

The switchboard bussing shall be of sufficient cross-sectional area to meet UL Standard 891 on temperature rise. The main bus shall have a minimum ampacity of 800-Amperes and shall be braced to have a short circuit rating of not less than 42,000 Amperes symmetrical at 240 Volts.

Main switchboard enclosure.--

Enclosure shall be NEMA 3R enclosure. Exterior shall be 2.66 mm (12-gage) and interior shall be 1.90 mm (14-gage) sheet steel. All screws, latches, hinge pins and similar hardware shall be stainless steel. Circuit breaker shall be operable with the exterior door open. Exterior door shall be lockable with a padlock. Enclosure finish shall be baked enamel or baked thermosetting polyester finish.

Main service disconnect switch.--

Main service disconnect switch shall be 3-pole, 240-Volt, 600-Ampere frame, 600-Ampere trip, molded case circuit breaker. The interrupting capacity of the circuit breaker shall be 42,000 Amperes symmetrical at 240 Volts.

Distribution circuit breakers.--

Distribution circuit breakers inside the distribution section shall be molded case circuit breakers rated 240 Volts, with interrupting capacity of 42,000 Amperes symmetrical at 240 Volts. The ampere trip and number of poles of circuit breakers shall be as shown on the plans.

Lightning arrester and surge capacitor.--

Lightning arrester and surge capacitor shall be suitable for use at the service entrance of a 120/208 Volt, three-phase, 4-wire, 60 Hz distribution system and shall be mounted on a bracket inside a NEMA 3R enclosure. Lightning arrester shall meet the design tests as required by ANSI/IEEE C62.11 for 10 kA, 4x10 microsecond impulses. Lightning arrester and surge capacitor shall be as manufactured by General Electric; Delta; or equal.

PART 3.- EXECUTION

Foundation for main switchboard shall be as shown on the plans.

Installation of service and distribution equipment shall be in accordance with the requirements of the serving utilities as shown on the approved installation details.

12-16.04 ELECTRICAL EQUIPMENT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing panelboards, starters, disconnect switches, and related accessories in accordance with the details shown on the plans and these special provisions.

Related work.--Anchorage devices shall be as specified under "Basic Materials and Methods" elsewhere in this Section 12-16.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS

PANELBOARDS.--

Panelboard 1E.--

Panelboard 1E shall be indoor type, top feed, surface-mounted, factory assembled, 3-phase, 4-wire, 208/120-Volt, AC panelboard at least 500 mm wide with 150-Ampere main circuit breaker, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panel shall be Square D Company, Westinghouse, General Electric, or equal.

Panelboard 2E.--

Panelboard 2E shall be indoor type, top feed, surface-mounted, factory assembled, 3-phase, 4-wire, 208/120-Volt, AC panelboard at least 500 mm wide with 100-Ampere main circuit breaker, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panel shall be Square D Company, Westinghouse, General Electric, or equal.

Panelboard A.--

Panelboard A shall be indoor type, top feed, surface-mounted, factory assembled, 3-phase, 4-wire, 208/120-Volt, AC panelboard at least 500 mm wide with 200-Ampere main circuit breaker, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panel shall be Square D Company, Westinghouse, General Electric, or equal.

Panelboard B.--

Panelboard B shall be indoor type, top feed, surface-mounted, factory assembled, 3-phase, 4-wire, 208/120-Volt, AC panelboard at least 500 mm wide with 200-Ampere main lugs, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panel shall be Square D Company, Westinghouse, General Electric, or equal.

Panelboard D.--

Panelboard D shall be outdoor type, bottom feed, surface-mounted, factory assembled, single-phase, 3-wire, 208/120-Volt, AC panelboard at least 500 mm wide with 60-Ampere main circuit breaker, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Panel shall be Square D Company, Westinghouse, General Electric, or equal.

Panelboard M.--

Panelboard M shall be indoor type, top feed, surface-mounted, factory assembled, 3-phase, 4-wire, 208/120-Volt, AC panelboard at least 500 mm wide with 400-Ampere main circuit breaker, insulated groundable neutral, equipment ground bar, hinged door and molded case branch circuit breakers as shown on the plans. Panel shall be rated 22,000 AIC. Panel M shall be UL listed suitable for use as service entrance equipment. Panels shall be Square D Company, NF series; General Electric, Spectra APNB series; or equal.

STARTERS.--

Air compressor combination starter.--

Air compressor starter shall be combination 3-pole, 208-Volt, NEMA Size 1, NEMA rated, line voltage starter and motor circuit protector in a NEMA-1 enclosure. Air compressor starter shall have two, 2-Ampere, dual element, 250-Volt fuses with 2-pole barrier type fuse base; 208-Volt coil, double-break silver contacts and 3 manual reset, non-adjustable thermal overloads, set to trip between 115 and 125 percent of full load motor current, as quoted on the nameplate by the motor manufacturer. Reset button shall be externally operable.

SWITCHES.--

A/C condensing unit disconnect switch.--

A/C condensing unit disconnect switch shall be 3-pole, 208-Volt, AC, 60-Ampere, fused, heavy duty safety switch in a NEMA-3R enclosure. The fuses shall be sized to suit the A/C condensing unit furnished.

Overhead door operator disconnect switch.--

Door operator disconnect switch shall be 3-pole, 240-Volt, AC, 30-Ampere, non-fusible, general duty safety switch in a NEMA-1 enclosure with provision for padlocking in the "OFF" position.

Exhaust fan disconnect switch.--

Exhaust fan disconnect switch shall be 20-Ampere, 208-Volt AC, quiet type, specification grade, ivory color switch with silver cadmium alloy contacts. Switch shall be suitable for wiring with stranded conductors.

Exhaust fan timer switch.--

Exhaust fan timer switch shall be single-pole, 120-Volt, 20-Ampere, quiet type, single throw, spring wound timer switch with one-hour limit and without a hold feature. Switch shall be suitable for wiring with stranded conductors.

Fume exhaust fan disconnect switch.--

Fume exhaust fan disconnect switch shall be single-pole manual motor starter rated one horsepower at 120-Volt AC. Starter shall have provisions for locking in the OFF position. Manual motor starter enclosure shall be surface-mounted NEMA 3R weatherproof enclosure.

Fume exhaust fan timer switch.--

Timer switch shall be 20-Ampere, 120-Volt AC, quiet type, single pole, single throw spring wound timer switch with four-hour limit and without a hold feature. Switch shall be suitable for wiring with stranded conductors.

Furnace disconnect switch, S_{HP}--

Furnace disconnect switch shall be single-pole manual motor starter one horsepower at 120-Volt AC. Starter shall have provisions for locking in the OFF position. Manual motor starter enclosure shall be surface-mounted NEMA 1 enclosure.

High pressure washer disconnect switch.--

High pressure washer disconnect switch shall be 3-pole, 240-Volt, AC, 60-Ampere, non-fusible, heavy duty safety switch in a NEMA-3R enclosure with provision for padlocking in the "OFF" position.

Power transfer switch, PTS.--

Power transfer switch, PTS, shall be 3-pole, double throw, 240-Volt, AC, 200-Ampere, rotary type, transfer switch in a NEMA-1 enclosure. The switch shall have a handle and escutcheon plate with a legend "UTILITY-STANDBY."

Garbage disposal switch.--

Garbage disposal switch shall be 20-Ampere, 120/277-Volt AC, quiet type, specification grade, ivory color switch with silver cadmium alloy contacts. Switch shall be suitable for wiring with stranded conductors.

Vestibule fan disconnect switch, S_{HP}--

Vestibule fan disconnect switch shall be a single-pole manual motor starter rated one horsepower at 120-Volt AC. Starter shall have provisions for locking in the OFF position. Manual motor starter enclosure shall be surface-mounted NEMA 1 enclosure. Manual starters shall meet the requirements of NEMA ICS.

MISCELLANEOUS MATERIALS.--**Nameplates.--**

Nameplates shall be laminated phenolic plastic with white core and black front and back. Nameplate inscription shall be in capitals letters etched through the outer layer of the nameplate material.

Plywood backing board.--

Plywood backing board for mounting electrical, telephone, or radio equipment shall be 19 mm, APA plywood panels, C-D PLUGGED and touch-sanded, Exposure 1. Plywood for telephone and radio terminal board shall be 1220 mm x 1220 mm.

PART 3.- EXECUTION**INSTALLATION.--**

Plywood backing board.--Plywood backing board shall be securely fastened to walls or other vertical framing. Surface to be coated shall be cleaned of all dirt, excess materials, of filler by hand cleaning.

Plywood backing board exposed surfaces shall receive the following paint system: one prime coat, alkyd, interior wood primer and 2-finish coats, acrylic, interior enamel, semi-gloss. Color shall match surrounding surfaces, or shall be as directed by the Engineer.

Coatings shall be applied in accordance with the manufacturer's instructions. Each coat shall be applied to a uniform finish, free of skips, brush marks, laps or other imperfections.

Existing panelboards.--Provide new circuit breakers, where required to match existing type unless otherwise shown on the plans. Provide mounting hardware, bus straps, and related materials for proper circuit breaker installation. Provide new panelboard identification nameplate with designation as shown for each panelboard. Remove existing nameplates where applicable. Provide new typewritten circuit directory reflecting changes made under the Contract.

Panelboard installation.--Set cabinets plumb and symmetrical with building lines. Train interior wiring as specified under "Conductor and Cable Installation" in "Basic Materials and Methods" of these special provisions. Touch-up paint any marks, blemishes, or other finish damage suffered during installation. Replace cabinets, doors or trim exhibiting dents, bends, warps or poor fit which may impede ready access, security or integrity.

Mounting height shall be 1.67 meters to the highest circuit breaker handle, measured above the finished floor.

Where "Space" is indicated on the plans, branch connectors, mounting brackets, and other hardware shall be furnished and installed for future breaker.

A typewritten directory under transparent protective cover shall be provided and set in metal frame inside each cabinet door. Directory panel designation for each circuit breaker shall include complete information concerning equipment controlled, including room number or area designated on the plans.

Equipment identification.--Equipment shall be identified with nameplates fastened with self-tapping, cadmium-plated screws or nickel-plated bolts.

Nameplate inscriptions shall be 6 mm high letters and shall be as shown on the plans as follows:

1. Inscriptions for panelboards shall include panel designation, voltage, and phase of supply and shall read in the following example: PANEL M, 208/120 V, 3-PHASE, 4-WIRE.
2. Inscriptions for starters, timer switches, disconnect switches and pushbuttons shall be the respective device it is controlling and shall read in the following example: OVERHEAD DOOR.
3. Inscriptions for combination starters and control panels shall be the panel designation as shown on the plans and shall read as in the following example: INTRUSION ALARM CONTROL PANEL.

12-16.05 LIGHTING

PART 1.- GENERAL

This work shall consist of furnishing, installing and connecting all lighting equipment in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive information, photometric curves, catalog cuts, and installation instructions shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

PART 2.- PRODUCTS

Lighting fixture lamps.--

Lighting fixture lamps shall be type and size as shown on the plans. Lamps shall be General Electric, Phillips, Sylvania, or equal. Fluorescent lamps, unless otherwise noted, shall be 4100K tri-phosphor with a CRI of 70 or greater.

Ballasts.--

All fixtures shall be equipped with high power factor ballasts suitable for the line voltage and for the type, size and number of lamps required by the fixture. Fluorescent ballasts shall be UL Listed, Class P and ETL Certified ballasts with sound rating A. Fluorescent ballasts shall be high-frequency electronic ballasts with power factor greater than 0.95, nominal ballast factor of 0.88 unless specified otherwise, total harmonic distortion less than 20 percent, crest factor less than or equal to 1.7, complying with ANSI C 62.41 Category A for surge protection, and FCC Part 18 for interference.

Lighting fixtures.--

Lighting fixtures shall be as shown on the plans and as specified herein. Outdoor luminaires shall be listed and labeled "Fixture Suitable For Wet Locations."

F1.--

Surface-mounted, white finish, fluorescent fixture with two-32 Watts T8 lamps, 120-Volt electronic ballast and one-piece, clear acrylic, wrap-around diffuser. The fixture shall be Day Brite, OWW series; Lithonia, 2LB series; or equal.

F2.--

Surface-mounted, white finish, fluorescent fixture with one-32 Watts T8 lamp, 120-Volt electronic ballast and one-piece, clear acrylic, wrap-around diffuser. The fixture shall be Day Brite, SJ series; Lithonia, CB series; or equal.

F3.--

Similar to F2 except F3 shall be equipped with emergency battery pack, battery status indicator light and test switch.

F4.--

Stem mounted 2438 mm fluorescent fixture with two-60 Watts T8 Slimline lamps, 120-Volt rated electronic ballast and white baked enamel ribbed reflector complete with end plates. The fixture shall be Lithonia, LA series; Day Brite, 1F series; or equal.

F5.--

Similar to F4 except F5 shall be bracket mounted fixture equipped with emergency battery pack, battery status indicator light and test switch.

F6.--

Similar to F4 except F6 shall be bracket mounted type light fixture.

F7.--

Surface-mounted, enclosed and gasketed, 2438 mm fluorescent fixture with two high output, 110-watt high-output lamps, 120-Volt minus 20 degree Celsius rated ballast and high-impact acrylic lens. Fixture shall be UL listed for wet locations. The fixture shall be Day Brite, V series; Lithonia, VRI series; or equal.

F7.--**MH1.--**

Outdoor, wall mounted, 175-Watt, 120-Volt metal halide luminaire with glass refractor and integral ballast. The luminaire shall be Lithonia, Series TWH; Day Brite, Series WL; or equal.

MH2.--

Outdoor, recessed, 100-Watt, 120-Volt, metal halide luminaire with integral ballast, tempered prismatic lens and regressed white door. Luminaire shall be listed for recessed mounting and wet locations. The luminaire shall be Lithonia, LAH series; Ruud, MRCO series; or equal.

MH3.--

Outdoor, wall mounted, 100-Watt, 120-Volt metal halide luminaire with integral ballast and cutoff refractor. Luminaire shall be listed for wet locations. The luminaire shall be Lithonia, Series TWAC; or equal.

MH4.--

Outdoor, surface mounted, listed for wet location, 175-Watt, 120-Volt metal halide luminaire with integral ballast and vandal resistant lens. The luminaire shall be Lithonia, VR4C series; Day Brite, CL1 series; or equal.

MH5.--

Pole mounted, Type 15 lighting standard as shown on Sheet ES-6A of the Standard Plans, with 250-Watt, 120-Volt, Type II distribution, metal halide, cutoff luminaire with integral ballast and built-in photocontrol unit. The luminaire shall be General Electric, Holophane, or equal.

Pole shall have a 3.7-meter mast arm. Pole shall conform to Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

Timer switch.--

Timer switch shall be 1-pole, 120-Volt, 20-Ampere, quiet type, single throw, spring wound timer switch with two-hour limit and without a hold feature. Switch shall be suitable for wiring with stranded conductors and enclosed in a non-metallic box with a weatherproof cover.

Fused splices.--

Fused splices shall be Buss, Elastimold, or equal; with standard midget, ferrule, 5-Ampere, 120-Volt, slow blowing fuses.

Photoelectric unit, PEC.--

Photoelectric unit shall be cadmium sulfide photoelectric control with capacity of 1800-Watt inductive or fluorescent load, mounting adapter, and EEI-NEMA twist lock receptacle; Fisher-Pierce, Ripley, or equal.

Outdoor light control panel (OLCP)--

Outdoor light control panel shall consist of a power disconnect, lighting contactor, selector switch, terminal block and pilot light in a surface mounted NEMA-12 enclosure with a hinged door.

Power disconnect, PD.--

Power disconnect shall be 2-pole, AC, molded case circuit breaker built and listed to UL 489 with ampere trip as shown on the plans, and interrupting capacity of 10,000 Amperes (symmetrical) at 240 Volts.

Lighting contactor, LC.--

Lighting contactor shall be electrically held, 4-pole lighting contactor with 120-Volt AC coil and 20-Ampere, double-break, silver alloy contacts; Square D Company, I.T.E., Westinghouse, or equal.

Selector switch, SS.--

Selector switch shall be rotary action, single-pole, 3-position, 10-Ampere, 120-Volt switch. Switch contacts shall have an inductive pilot duty rating of 60 Amperes (make), 6 Amperes (break) and 10 Amperes (continuous) at 120 Volts and 35 percent power factor. Selector switch shall have legend plate marked MANUAL-OFF-AUTO.

Pilot light, PL.--

Pilot light shall be panel mounted, heavy duty, oil tight indicating light with 120-Volt, AC, LED lamp with red domed cap.

Terminal block, TB.--

Terminal block shall be 30-Ampere, 600-Volt, molded plastic with two or more mounting holes and two or more terminals in each cast block. The molded plastic shall have a high resistance to heat, moisture, mechanical shock, and electrical potential and shall have a smooth even finish. Each block shall have a molded marking strip attached with screws. Terminal blocks shall have tubular, high pressure clamp connectors.

Concrete.--

Concrete shall be as specified under Section 12-3, "Concrete and Reinforcement," of these special provisions. The concrete shall be commercial quality portland cement concrete containing not less than 337 kilograms of cement per cubic meter.

FABRICATION.--

Component mounting.--The following electrical components shall be mounted on the back panel of the outdoor light control panel:

- Power Disconnect, PD
- Terminal Block, TB
- Lighting contactors, LC

The following electrical components shall be mounted on the hinged door of the outdoor light control panel:

- Selector switch, SS
- Indicating light, PL

PART 3.- EXECUTION

LIGHTING FIXTURES.--Lighting fixtures shall be mounted securely in accordance with the manufacturer's recommendations. Mounting methods shall be suitable for the particular type of ceiling or support at each location.

The Contractor shall provide all supports, hangers, spacers, channels, fasteners and other hardware necessary to support the fixtures.

Fixtures shall be set at the mounting heights shown on the plans, except heights shown shall be adjusted to meet conditions.

BALLASTS.--All fluorescent fixtures shall be equipped with high power factor ballasts suitable for the line voltage and for the type, size and number of lamps required by fixture. The Contractor has the option to install low voltage dimming control provided that the Contractor submit plans and specifications with appropriate revisions for the low voltage dimming control to the Engineers for approval prior to installation.

All ballasts used in unheated areas inside the building shall be -20°C ballasts or less.

POLE MOUNTED LUMINAIRES.--In the pull box adjacent to each pole for luminaire, a fused splice connector shall be installed in each ungrounded conductor between the line and the ballast. The connector shall be readily accessible in the pull box and shall be insulated and made waterproof in accordance with the splice connector manufacturer's recommendations.

Concrete foundations shall be as shown on the plans. Anchor bolts or devices shall be accurately located and positioned to match the holes in the pole base plates. Pole and luminaire orientation shall be as indicated on the plans.

The poles for pole mounted type fixtures shall be mounted rigidly and securely on the foundations as recommended by the fixture and pole manufacturer.

12-16.06 INTRUSION ALARM SYSTEM

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing a complete and operational intrusion alarm system in accordance with the details shown on the plans and these special provisions.

The system shall include all materials, whether mentioned or not, that are necessary for a complete and operational intrusion alarm system.

SYSTEM DESCRIPTION.--

Design requirements.--The intrusion alarm system shall be a low voltage, direct current, zoned alarm system, and shall consist of a control panel, magnetic contact switches, combination detectors, glass break discriminators, and digital keypad stations for designated control points into the building. Each zone shall be "supervised, Class B circuit." The end of line resistor shall be installed in the control panel.

The alarm system shall self-test and report status of individual zones every twenty-four (24) hours.

The alarm system shall provide an automatically rechargeable back-up power supply system, 24-hour minimum, in case of building power interruption.

The alarm system components shall be U.L. or F.M. Listed. The system proposed shall be approved by the Federal Communication Commission (FCC).

SUBMITTALS.--

Product data.--Manufacturer's descriptive information and installation instructions shall be submitted for approval.

Installation instructions shall include manufacturer and catalog reference, and model number of equipment to be furnished, conduit and conductor sizes, wiring diagram, and floor plan showing locations of devices.

QUALITY ASSURANCE.--

Installer qualification.--The installer of the security alarm system shall be licensed by the State Department of Consumer Affairs, Bureau of Security and Investigative Services. License numbers and expiration dates shall be included on all correspondence.

PART 2.- PRODUCTS

Intrusion alarm control panel.--

The control panel (Radionics 9412B) shall be a surface-mounted, locking cabinet, completely self-contained control panel suitable for 120-Volt, AC, input power with separate terminals for all external wires.

The control panel shall meet the following requirements:

U.L. Listed for Commercial Fire and Burglar reporting;
Minimum eight (8) zones (capable of zone expansion);
Digital dialer communicator;
12-Volt auxiliary power supply (24 hours minimum);
Rechargeable battery (24 hour minimum);
Battery charger;
Low battery reporting;
Silent alarm signaling;
System connected to RJ31X or RJ38X telephone jack or equivalent;
Line test every twenty-four (24) hours
120-Volt, AC, input
Front accessible control and indication digital keypad;
U.L. listed for commercial use;
Remote Control identification.

Magnetic contact switch.--

Magnetic door switch for pedestrian door shall be a 2-section, self-lock mounting type switch, and shall be compatible with the material of the door on which it is installed. The switch shall be epoxied in the switch housing. Magnetic contact switches shall be the type capable of being concealed on the top of the door frame.

Magnetic contact switches for the overhead vehicle doors shall be 2-section, extra heavy-duty, floor mounting type switch with stainless steel armored cable.

Switch shall be housed in a non-magnetic case.

Glass break discriminator.--

Glass break discriminator shall be an acoustic glass break detector with advanced technology for sensing and reporting simultaneous sound and shock wave activity. Detector shall respond to energy of breaking windows using piezo-electric crystal microphone. Sensor coverage pattern shall be directional, detecting breakage of uncovered glass in a 10.5 meters wide area at a distance of 3.5 meters minimum. The sensor shall be housed in a fire retardant ABS housing.

Digital keypad.--

Keypad shall be weatherproof 12 button keypad with 16 user codes capable of expansion to 120, surface-mounted, low voltage 12 V(dc)/24 V(dc), vandal resistant device with programmable ability for user codes 1-6 digits. Keypad will have an EEPROM memory for backup of all codes, have a relock time delay adjustable time from 1-90 seconds or on/off and have a tamper switch to detect unauthorized access to the keypad working mechanism. The keypad will have incorporated four (4) on-board relays for electric door locks, alarm shunting, forced door monitoring and door ajar monitoring.

Combination motion detector.--

Combination motion detectors shall be low voltage, wall-mounted, long rangemicrowave or passive infrared detectors with a detection pattern appropriate to cover areas indicated on the plans. Model must be specified on proposed installation layout. The detector shall have an LED indicating light.

PART 3. EXECUTION.--

INSTALLATION.--

General.--The intrusion alarm system shall be installed in accordance with the manufacturer's recommendations and at the locations specified on the floor plans.

The switch section without wires shall be recessed flush into the top edge of the door at the approximate center of the door, and the switch section with wires shall be recessed flush in the top section of the door frame. The two sections of the switch shall be mounted directly opposite each other to provide maximum sensitivity. The wiring from each magnetic switch shall be run to the control panel in the zone dedicated for the intrusion alarm circuit.

Magnetic contact switches for overhead doors shall be mounted as follows. The switch section mounted on the bottom edge of the overhead door shall be without wires. The switch section with wire shall be mounted on the floor directly below the switch part without wires. The wiring from each magnetic switch shall be run to the control panel in the zone dedicated for the intrusion alarm circuit.

The glass break discriminator shall be mounted on the ceiling at locations shown on the plans.

Combination motion detectors shall be mounted on adjacent walls no more than 2.0 meters above finished floor at locations shown on the plans. As required wiring is to be concealed in walls or use EMT conduit to protect device wiring from damage or unauthorized tampering. Placement at this height will provide for adequate coverage in the areas to be protected.

At pedestrian access doors the following devices are to be installed per manufacturer instructions and work as an integrated system to control employee access and egress into the designated areas. For this building, all digital keypads are to be mounted internal of the building. Other components of the entry system will be mounted on the access door and will include a magnetic contact switch and cylindrical lever door locks.

Intrusion alarm zoning.--Intrusion alarm panel zoning shall be as shown on the plan.

Conduit and conductors.--All intrusion alarm system wiring shall be installed in conduit system conforming to the requirements under "Basic Materials and Methods" elsewhere in these special provisions. Conduit size shall be as recommended by the intrusion alarm manufacturer, except that conduits shall be not less than 16 mm diameter. All conduits shall be concealed in ceiling or walls except inside the Equipment Bays conduits shall be exposed.

All conductors and cables for the intrusion alarm system wiring shall be as recommended by the intrusion alarm system manufacturer.

All points of protection must be specifically identified by zone when reporting to the intrusion alarm panel. All points of protection will be transmitted to the U.L. Listed monitoring company.

FIELD QUALITY CONTROL.--

Testing.--The operational test for the intrusion alarm system shall be performed by the Contractor in the presence of the Engineer and a representative from Caltrans Operation Security Branch. The operational tests shall demonstrate that all functions of the system operate in the manner described in the manufacturer's literature and demonstrate system stability under normal vibration and shocks to components. The Contractor shall notify the Engineer and Caltrans Operation Security Branch in writing not less than 10 days in advance of performing the operational tests.

Monitoring.--The contractor shall provide U.L. Listed monitoring services for the facility for one year after the acceptance of the contract. The services shall include a toll-free telephone line connecting to the 24-hour on call monitoring station. Monitoring station shall contact designated site representative in the event of alarm and dispatch an immediate on-site response to the alarm location if the site representative cannot be reached or verification of the cause of the alarm cannot be determined.

Monitoring services after the first year will be handled by the State.

DEMONSTRATION.--

Training.--The Contractor shall provide on-site training on the use, operation, and maintenance of the system for designated State employees. The Contractor shall notify the Engineer in writing not less than 10 days in advance of proposed training class.

12-16.07 FIBERGLASS ANTENNA POLE

The Antenna Pole shall be fiberglass-reinforced plastic (FRP) pole conforming to these special provisions.

Fiberglass-reinforced plastic pole standard shall consist of round, fiberglass-reinforced plastic pole and base. Fiberglass-reinforced plastic pole shall be hollow, tapered or with tapered sections, non-conductive and chemically inert.

Fiberglass-reinforced plastic pole standard shall conform to the details shown on the plans and shall conform to the requirements in "Standard Specifications for Structural Supports for Signs, Luminaires, and Traffic Signals" published by AASHTO, and ANSI Standard: C136.20, "Fiberglass-Reinforced Plastic (FRP) Lighting Poles."

For standard specified or shown as "Breakaway" type, fiberglass-reinforced plastic pole standard shall conform to the requirements in National Cooperative Highway Research Program Report 230, "Recommended Procedures for the Safety Performance Evaluation of Highway Appurtenances." Design wind velocity for Fiberglass Antenna Pole standard systems shall be 129 km/h.

The pole shall withstand the bending strength test load shown in the following table. The pole shall withstand this load with the handhole in compression. The pole shall not exceed a maximum deflection of 13 percent of the length of the pole above the ground line when subjected to the deflection test load shown in the following table:

TEST LOAD TABLE

Standard Type	Bending Strength Test Load	Deflection Test Load
Type 21F, Type 21F (Breakaway)	2562 N	1708 N

Test loads shall be applied in conformance with the requirements in Section 12, "Pole Deflection Measurements," of ANSI Standard: C 136.20. Poles shall be loaded 300 mm below the tip.

Fiberglass-reinforced plastic pole standard shall be the anchor base type unless otherwise designated.

The manufacturer of fiberglass-reinforced plastic pole standard shall have an approved testing and quality control program on file at the Transportation Laboratory prior to fabricating pole standard for this contract.

The Engineer shall be provided a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The certificate shall certify that the pole standard conform to the requirements in the specifications and were manufactured in conformance with the approved testing and quality control program. The certificate shall also include the date of the certificate, reference job number, manufacturer product catalog number, pole type number, dates of manufacture and the signature of the manufacturer's management person responsible for the testing and quality control program.

CONSTRUCTION

Pole shall be constructed from ultraviolet-resistant resin which shall be pigmented light gray and be of uniform color throughout the entire body of the pole. The finish of poles shall be smooth.

Pole shall have 2 handholes and handhole covers. The cover over the handhole nearest the base shall bear the name of the manufacturer. The handhole covers shall be securely attached to the pole with tamper-resistant hardware. The handholes shall be located as shown in the plans.

The base shall be bonded to the pole with a suitable adhesive and coated with an aliphatic-type acrylic-modified polyurethane finish. The adapter plate shall not be used to attach the pole standard to the foundation.

The pole standard shall be provided with a removable aluminum or galvanized steel pole top cap.

The pole standard shall have an identification plate conforming to the provisions in Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications. The identification plate shall show the pole standard type, manufacturer's name, manufacturer's part number and the year of fabrication. If the fiberglass-reinforced plastic pole standard is a breakaway type, the identification plate shall include the word "BREAKAWAY." The plate shall be located either on the anchor base or just above the base handhole.

EXTERIOR PROTECTION

An aliphatic-type acrylic-modified polyurethane coating shall be applied to the exterior of the fiberglass pole. The coating shall be semi-gloss, highly weather resistant and light gray in color matching the color of the resin and shall have a minimum 0.075-mm dry film thickness. A one liter can of the coating matching the pole shall be supplied with the order of pole. The polyurethane coating shall be tested for adhesion to the pole surface in conformance with the requirements in ASTM Designation: D 3359, Method A, and shall have a scale rating of 5A. The adhesion testing shall be conducted before and after the accelerated weathering evaluation.

The finished surface of the pole shall withstand a minimum of 2500 hours of accelerated weathering when tested in conformance with the requirements in ASTM Designation: G 53. Lamps shall be UV-B (313 nm wavelength). The testing cycle shall be 4 hours ultraviolet (UV) exposure at 60°C, then 4 hours condensate exposure at 40°C.

After testing, the finished surface of the pole shall exhibit the following:

Fiber exposure	None
Crazing	None
Checking	None
Chalking	Very slight
Change in color	May dull slightly
Paint adhesion	5A scale rating, per ASTM Designation: D 3359, Method A using Permacel 99 tape.

PACKAGING

The pole shall be spiral wrapped in its entirety with a weatherproof wrap for protection during shipping and storage.