Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
03	ED	50	73.7/75.4	97	119

REGISTERED CIVIL ENGINEER 4-26-12 DATE

7-30-12
PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER JACK COWELL No. 65521 Exp. 9-30-13 CIVIL STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

TEMPORARY CONSTRUCTION ENTRANCE

LOCATION	EA
ROUTE 50	~~2~~ 3
TOTAL	~~2~~ 3

1

PLACE HOT MIX ASPHALT DIKE

STATION/LOCATION	TYPE C	TYPE E	TYPE F	HOT MIX ASPHALT (TYPE A)
	LF	LF	LF	TON
"A1" 898+18.71 to 903+24.72 Lt		506.0		13.3
"A1" 917+53.53 to 918+88.70 Rt		137.7		3.6
"A1" 920+91.97 to 922+26.90 Rt		137.9		3.6
"A1" 943+83.27 to 944+50.00 Lt			66.7	0.9
"A1" 944+50.00 to 945+05.00 Lt	55.0			0.4
SHEET TOTAL	55.0	781.6	66.7	21.8*
TOTAL	55.0	781.6	66.7	

SIDEWALK QUANTITIES

STATION/LOCATION	HOT MIX ASPHALT (TYPE A)	PLACE HOT MIX ASPHALT (Misc AREA)	CLASS 2 AGGREGATE BASE	TACK COAT	ROADWAY EXCAVATION
	TON	SQYD	CY	TON	CY
"A1" 942+56.50 to 945+94.42 Lt	17.5	173.0		0.02	
"A1" 946+11.51 to 947+24.92 Lt	6.2	60.9		0.01	
"A1" 947+24.92 to 951+01.77 Lt	28.2	209.0	34.8		48.8
"A1" 951+41.77 to 953+26.87 Lt	13.9	102.8	17.1		24.0
"A1" 953+71.63 to 956+08.10 Lt	12.8	126.9		0.02	
"A1" 956+08.10 to 956+35.13 Lt	1.9	14.0	2.3		3.3
"A1" 957+01.18 to 957+55.76 Lt	3.6	27.0		0.01	
"A1" 958+04.11 to 959+08.40 Lt	7.5	55.6	9.3		13.0
"A1" 959+08.40 to 959+83.04 Lt	4.7	35.1		0.01	
"A1" 960+19.82 to 961+29.59 Lt	5.2	51.5		0.01	
"A1" 961+55.33 to 962+63.60 Lt	5.5	54.7		0.01	
"A1" 963+00.90 to 963+67.21 Lt	3.7	36.2		0.01	
"A1" 963+96.37 to 965+41.36 Lt	7.9	77.8		0.01	
"A1" 965+85.53 to 969+23.91 Lt	25.4	188.0	31.3		43.9
"A1" 969+77.91 to 970+82.00 Lt	7.8	57.8	9.6		13.5
"A1" 971+95.67 to 973.84.08 Lt	14.1	104.7	17.4		24.4
"A1" 974+48.08 to 976+06.69 Lt	11.9	88.1	14.7		20.6
SHEET TOTAL	177.8	1463.1	136.5	0.11	191.5

REMOVE ASPHALT CONCRETE DIKE, PORTLAND CEMENT CURB

LOCATION	REMOVE ASPHALT CONCRETE DIKE	REMOVE CONCRETE CURB
	LF	LF
"A1" 890+80.50 TO 891+00.00 Lt		19.5
"A1" 891+00.00 TO 907+32.62 Lt	1634.0	
"A1" 934+08.59 TO 943+80.0 Lt	971.4	
"A1" 946+00.0 TO 968+00 Lt	2200.0	
"A1" 946+00.0 TO 951+21.77 Rt	521.8	
"A1" 959+57.00 TO 965+70.00 Rt	613.0	
"A1" 967+10.0 TO 979+70.0 Rt		1260.0
"A1" 968+00 TO 979+70.0 Lt		1170.0
TOTAL	5940.2	2449.5

TEMPORARY COVER

LOCATION	SQYD	
ROUTE 50	~~1060~~	1500
TOTAL	~~1060~~	1500

1

TEMPORARY FIBER ROLL

LOCATION	LF
ROUTE 50	5800
TOTAL	5800

TEMPORARY SILT FENCE

LOCATION	LF
ROUTE 50	5200
TOTAL	5200

TEMPORARY DRAINAGE INLET PROTECTION

LOCATION	EA
ROUTE 50	30
TOTAL	30

TEMPORARY HYDRAULIC MULCH

LOCATION	SQYD
ROUTE 50	3700
TOTAL	3700

TEMPORARY CHECK DAM

LOCATION	LF	
ROUTE 50	~~12~~	240
TOTAL	~~12~~	240

1

SIDEWALK QUANTITIES

STATION/LOCATION	HOT MIX ASPHALT (TYPE A)	PLACE HOT MIX ASPHALT (Misc AREA)	CLASS 2 AGGREGATE BASE	TACK COAT	ROADWAY EXCAVATION
	TON	SQYD	CY	TON	CY
"A1" 948+06.60 to 949+13.84 Rt	8.0	59.6	9.9		13.9
"A1" 949+65.84 to 951+11.08 Rt	10.9	80.7	13.4		18.8
"A1" 951+61.08 to 952+65.23 Rt	7.8	57.9	9.6		13.5
"A1" 953+21.23 to 953+27.59 Rt	0.5	3.5	0.6		0.8
"A1" 953+83.59 to 955+47.65 Rt	12.3	91.1	15.2		21.3
"A1" 956+03.65 to 956+44.00 Rt	3.0	22.4	3.7		5.2
"A1" 956+96.00 to 957+26.93 Rt	2.3	17.2	2.9		4.0
"A1" 957+82.93 to 958+41.88 Rt	4.4	32.8	5.5		7.6
"A1" 959+72.28 to 960+29.52 Rt	4.3	31.8	5.3		7.4
"A1" 960+67.56 to 962+92.16 Rt	12.8	126.8		0.02	
"A1" 963+21.24 to 965+65.85 Rt	13.7	135.6		0.02	
"A1" 966+08.97 to 966+38.00 Rt	2.2	16.1	2.7		3.8
"A1" 967+02.00 to 967+41.00 Rt	2.9	21.7	3.6		5.1
"A1" 967+97.00 to 968+15.13 Rt	1.4	10.1	1.7		2.4
"A1" 968+65.13 to 968+86.74 Rt	1.6	12.0	2.0		2.8
"A1" 969+32.74 to 969+36.74 Rt	0.3	2.2	0.4		0.5
"A1" 970+34.87 to 970+38.87 Rt	0.3	2.2	0.4		0.5
"A1" 970+79.58 to 970+86.22 Rt	0.5	3.7	0.6		0.9
"A1" 971+30.22 to 971+79.08 Rt	3.7	27.1	4.5		6.3
"A1" 972+31.08 to 972+74.00 Rt	3.2	23.8	4.0		5.6
"A1" 973+26.00 to 974+73.54 Rt	11.9	88.1		0.01	
SHEET TOTAL	108.0	866.4	86.0	0.05	120.4
TRANSFERRED TOTAL	177.8	1463.1	136.5	0.11	191.5
TOTAL	285.8*	2329.5*	222.5*	0.16*	311.9*

* FOR TOTAL QUANTITY, SEE ROADWAY QUANTITIES

1 **REVISED PER ADDENDUM No. 1 DATED NOVEMBER 16, 2012**

SUMMARY OF QUANTITIES

Q-4

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
NORTH REGION
DIVISION OF ENGINEERING
DESIGN BRANCH M8

FUNCTIONAL SUPERVISOR: MASTRI ALVANDI
JACK COWELL | MASTRI ALVANDI
CALCULATED-DESIGNED BY | CHECKED BY
REVISED BY | DATE REVISED

LAST REVISION 04-23-12 | DATE PLOTTED => 16-NOV-2012 | TIME PLOTTED => 10:00