

DEPARTMENT OF TRANSPORTATION

DES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

July 5, 2002

04-CC-680-38.5/40.1
04-006054
ACIM-680-1(054)N

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in CONTRA COSTA COUNTY IN AND NEAR MARTINEZ FROM 0.5 KM SOUTH OF MOCOCO OVERHEAD TO BENICIA-MARTINEZ BRIDGE AND OVERHEAD.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on July 16, 2002.

This addendum is being issued to revise the Project Plans, the Notice to Contractors and Special Provisions, the Proposal and Contract, and the Federal Minimum Wages with Modification Number 10 dated 6-14-02. A copy of the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

Project Plan Sheets 73, 74, 75, 76, 77, 78, and 79 are deleted

Project Plan Sheets 280, 288, and 289 are revised. Half-sized copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 10-5. "SANITARY SEWER SYSTEM," is deleted.

In the Proposal and Contract, the Engineer's Estimate Items 63, 67, 79, 99, 101, and 127 are revised and Items 78, 168, 171, 172, 173, 174, 175, 176, 177, and 219 are deleted as attached.

To Proposal and Contract book holders:

Replace pages 6, 7, 8, 9, 11, and 13 of the Engineer's Estimate in the Proposal with the attached revised pages 6, 7, 8, 9, 11, and 13 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 3
Page 2
July 5, 2002

04-CC-680-38.5/40.1
04-006054
ACIM-680-1(054)N

This office is sending this addendum by UPS overnight mail to Proposal and Contract book holders to ensure that each receives it.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY:

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

ENGINEER'S ESTIMATE

04-006054

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	023734	ROADWAY EXCAVATION (HAZARDOUS)	M3	270		
62	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
63 (F)	192003	STRUCTURE EXCAVATION (BRIDGE)	M3	1675		
64 (F)	192023	STRUCTURE EXCAVATION (TYPE H)	M3	204		
65 (F)	192037	STRUCTURE EXCAVATION (RETAINING WALL)	M3	1786		
66 (F)	192055	STRUCTURE EXCAVATION (SOIL NAIL WALL)	M3	160		
67 (F)	193003	STRUCTURE BACKFILL (BRIDGE)	M3	1444		
68 (F)	193013	STRUCTURE BACKFILL (RETAINING WALL)	M3	2371		
69	023735	STRUCTURE EXCAVATION (SIGN FOUNDATION)	M3	22		
70	023736	STRUCTURE BACKFILL (SIGN FOUNDATION)	M3	16		
71 (F)	193028	STRUCTURE BACKFILL (SOIL NAIL WALL)	M3	20		
72	193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	M3	140		
73	193114	SAND BACKFILL	M3	11		
74	194001	DITCH EXCAVATION	M3	1080		
75	023737	DITCH EXCAVATION (HAZARDOUS)	M3	200		
76	023738	DRAINAGE EXCAVATION (HAZARDOUS)	M3	49		
77 (S)	197060	SOIL NAIL ASSEMBLY	M	830		
78	BLANK					
79	198200	SUBGRADE ENHANCEMENT FABRIC	M2	3290		
80	023740	GEOMEMBRANE (TYPE B)	M2	11 600		

ENGINEER'S ESTIMATE

04-006054

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
81	023741	LIGHTWEIGHT EMBANKMENT MATERIAL (CELLULAR CONCRETE, 4.7 KN/M3)	M3	29 700		
82	023742	LIGHTWEIGHT EMBANKMENT MATERIAL (CELLULAR CONCRETE, 6.3 KN/M3)	M3	18 400		
83 (S)	023743	LIGHTWEIGHT EMBANKMENT MATERIAL (EPS BLOCK)	M3	11 700		
84	023744	SHORING	M	400		
85	023745	GEOMEMBRANE (TYPE A-GASOLINE RESISTANT)	M2	9170		
86	023746	GEOTEXTILE CUSHION	M2	3510		
87 (S)	023747	EROSION CONTROL (NETTING)	M2	6690		
88 (S)	203003	STRAW (EROSION CONTROL)	TONN	6.3		
89 (S)	203014	FIBER (EROSION CONTROL)	KG	2090		
90 (S)	203021	FIBER ROLLS	M	2400		
91 (S)	203024	COMPOST (EROSION CONTROL)	KG	6340		
92 (S)	203026	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	12		
93 (S)	023748	PURE LIVE SEED (TYPE 1)(EROSION CONTROL)	KG	110		
94 (S)	023749	PURE LIVE SEED (TYPE 2)(EROSION CONTROL)	KG	37		
95 (S)	203056	COMMERCIAL FERTILIZER (EROSION CONTROL)	KG	130		
96 (S)	203061	STABILIZING EMULSION (EROSION CONTROL)	KG	480		
97	048965	NPS 12 SUPPLY LINE (BRIDGE)	M	204		
98	250401	CLASS 4 AGGREGATE SUBBASE	M3	1470		
99	260301	CLASS 3 AGGREGATE BASE	M3	1150		
100	290211	ASPHALT TREATED PERMEABLE BASE	M3	740		

ENGINEER'S ESTIMATE

04-006054

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
101	390155	ASPHALT CONCRETE (TYPE A)	TONN	17 400		
102	390165	ASPHALT CONCRETE (OPEN GRADED)	TONN	370		
103	394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	M2	130		
104	394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	M	470		
105	397001	ASPHALTIC EMULSION (PAINT BINDER)	TONN	4		
106	023750	PORTLAND CEMENT CONCRETE SLAB	M3	470		
107	048966	2.8 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	560		
108 (S)	048967	2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	M	152		
109 (S)	048968	2.4 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	M	404		
110 (S)	048969	2.8 M PERMANENT STEEL CASING	M	561		
111 (S)	048970	ISOLATION CASING	KG	20 000		
112	023751	FURNISH PILING (CLASS 400C) (SIGN FOUNDATION)	M	54		
113	023752	DRIVE PILE (CLASS 400C) (SIGN FOUNDATION)	EA	4		
114	023753	CUTOFF WALL (STEEL SHEET PILING)	M2	3280		
115	499030	FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (610 MM)	M	4120		
116 (S)	499031	DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (610 MM)	EA	219		
117	499036	FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (762 MM)	M	376		
118 (S)	499037	DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (762 MM)	EA	20		
119 (S)	048971	PRESTRESSING CONCRETE	LS	LUMP SUM	LUMP SUM	
120 (F)	510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	M3	1040		

ENGINEER'S ESTIMATE

04-006054

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
121 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	M3	10 430		
122 (F)	510060	STRUCTURAL CONCRETE, RETAINING WALL	M3	1937		
123 (F)	510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	M3	360		
124 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	28.1		
125	510507	MINOR CONCRETE (SIGN FOUNDATION)	M3	6		
126	510522	MINOR CONCRETE (PIPE COVER)	M3	3		
127	510526	MINOR CONCRETE (BACKFILL)	M3	120		
128 (F)	511064	FRACTURED RIB TEXTURE	M2	410		
129	048972	DRILL AND BOND ANCHOR BOLT	M	92		
130 (S)	048973	FURNISH PRECAST PRETENSIONED CONCRETE BULB-TEE GIRDER (5 M - 10 M)	EA	12		
131 (S)	048974	FURNISH PRECAST PRETENSIONED CONCRETE BULB-TEE GIRDER (30 M - 35 M)	EA	1		
132 (S)	048975	FURNISH PRECAST PRETENSIONED CONCRETE BULB-TEE GIRDER (35 M - 40 M)	EA	8		
133 (S)	048976	FURNISH PRECAST PRETENSIONED CONCRETE BULB-TEE GIRDER (40 M - 45 M)	EA	3		
134 (S)	048977	FURNISH PRECAST PRETENSIONED CONCRETE BULB-TEE GIRDER (45 M - 50 M)	EA	8		
135 (S)	048978	FURNISH PRECAST PRETENSIONED CONCRETE BULB-TEE GIRDER (50 M - 55 M)	EA	17		
136 (S)	048979	FURNISH PRECAST PRETENSIONED CONCRETE BULB-TEE GIRDER (55 M - 60 M)	EA	20		
137 (S)	048980	FURNISH PRECAST PRETENSIONED CONCRETE BULB-TEE GIRDER (60 M - 65 M)	EA	3		
138 (S)	048981	ERECT PRECAST PRETENSIONED CONCRETE GIRDER	EA	72		
139	515020	REFINISH BRIDGE DECK	M2	41		
140 (S)	518051	PTFE SPHERICAL BEARING	EA	12		

ENGINEER'S ESTIMATE

04-006054

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
161	620912	525 MM ALTERNATIVE PIPE CULVERT	M	97		
162	620913	600 MM ALTERNATIVE PIPE CULVERT	M	140		
163	650069	450 MM REINFORCED CONCRETE PIPE	M	31		
164	650075	600 MM REINFORCED CONCRETE PIPE	M	1.2		
165	681134	80 MM PLASTIC PIPE (EDGE DRAIN)	M	880		
166	681137	80 MM PLASTIC PIPE (EDGE DRAIN OUTLET)	M	180		
167	682008	PERMEABLE MATERIAL (BLANKET)	M3	2150		
168	BLANK					
169	705222	450 MM CONCRETE FLARED END SECTION	EA	1		
170	705336	450 MM ALTERNATIVE FLARED END SECTION	EA	1		
171	BLANK					
172 (S)	BLANK					
173 (S)	BLANK					
174 (S)	BLANK					
175 (S)	BLANK					
176 (S)	BLANK					
177 (S)	BLANK					
178	721008	ROCK SLOPE PROTECTION (LIGHT, METHOD B)	M3	6		
179	721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	M3	32		
180	721410	CONCRETE (GUTTER LINING)	M3	23		

ENGINEER'S ESTIMATE

04-006054

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
201	839701	CONCRETE BARRIER (TYPE 60)	M	79		
202 (F)	839704	CONCRETE BARRIER (TYPE 60D)	M	120		
203 (F)	839725	CONCRETE BARRIER (TYPE 736)	M	897		
204 (F)	839726	CONCRETE BARRIER (TYPE 736A)	M	277		
205	840501	THERMOPLASTIC TRAFFIC STRIPE	M	3440		
206	840515	THERMOPLASTIC PAVEMENT MARKING	M2	84		
207 (S)	840656	PAINT TRAFFIC STRIPE (2-COAT)	M	12 100		
208 (S)	840666	PAINT PAVEMENT MARKING (2-COAT)	M2	60		
209 (S)	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	1700		
210 (S)	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	1360		
211 (S)	860201	SIGNAL AND LIGHTING	LS	LUMP SUM	LUMP SUM	
212 (S)	860298	SIGNAL AND LIGHTING (STAGE CONSTRUCTION)	LS	LUMP SUM	LUMP SUM	
213 (S)	860415	LIGHTING (STAGE CONSTRUCTION)	LS	LUMP SUM	LUMP SUM	
214 (S)	860460	LIGHTING AND SIGN ILLUMINATION	LS	LUMP SUM	LUMP SUM	
215 (S)	023763	TRAFFIC OPERATIONS SYSTEM	LS	LUMP SUM	LUMP SUM	
216	BLANK					
217	024820	RELOCATE CATHODIC PROTECTION (RECTIFIER)	LS	LUMP SUM	LUMP SUM	
218	024281	SEWER LINE VIDEO SURVEY	EA	2		
219	BLANK					
220	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID: _____