

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

TTY 711

*Flex your power!
Be energy efficient!*

November 23, 2011

04-CC,Sol-80-13.9/14.2; 0.0/0.5

04-049074

Project ID 0400000058

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN CONTRA COSTA AND SOLANO COUNTIES AT THE CARQUINEZ BRIDGES.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, December 14, 2011.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions and the Bid book.

Project Plan Sheets 16, 17, 18, 19, 20, 21, 22, 23, 24, 26, 27, 28, 29, 30, 31, 37, 40, and 41 are revised. Copies of the revised sheets are attached for substitution for the like-numbered sheets.

Project Plan Sheet 25 is deleted.

In the Special Provisions, Section 10-1.20, "PILING," subsection "GENERAL," the following paragraph is added after the first paragraph.

"Concrete for cast-in-place concrete piling shall be prequalified in conformance with the provisions in Section 90-9, "Compressive Strength," of the Standard Specifications."

In the Special Provisions, Section 10-1.20, "PILING," subsection "NONDESTRUCTIVE TESTING OF CLASS N STEEL PIPE PILING," is deleted.

In the Special Provisions, Section 10-1.21, "CONCRETE STRUCTURES," subsection "MASS CONCRETE," is deleted.

In the Special Provisions, Section 10-1.26, "PLASTIC LUMBER," subsection "Hardware," the second paragraph is revised as follows:

"All hardware must conform to the provisions in ASTM A276, Type 316 for stainless steel."

Addendum No. 3
Page 2
November 23, 2011

04-CC,Sol-80-13.9/14.2; 0.0/0.5
04-049074
Project ID 0400000058

In the Bid book, in the "Bid Item List," Items 11, 12, 13, 14, 16, 17, 20, are revised as attached.

To Bid book holders:

Replace page 3 of the "Bid Item List" in the Bid book with the attached revised page 3 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This addendum and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/04/04-049074

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



FDR

REBECCA D. HARNAGEL
Chief, Office of Plans, Specifications & Estimates
Office Engineer
Division of Engineering Services

Attachments

BID ITEM LIST

04-049074

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM	LUMP SUM	
2	070018	TIME-RELATED OVERHEAD	WDAY	200		
3	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
4	074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
5	074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	LUMP SUM	LUMP SUM	
6	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
7	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
8	128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	LUMP SUM	LUMP SUM	
9	021252	HYDROACOUSTIC MONITORING	LS	LUMP SUM	LUMP SUM	
10	157560	BRIDGE REMOVAL (PORTION)	LS	LUMP SUM	LUMP SUM	
11	495121	FURNISH 28" CAST-IN-STEEL SHELL CONCRETE PILING	LF	4,060		
12	495122	DRIVE 28" CAST-IN-STEEL SHELL CONCRETE PILE	EA	29		
13 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	CY	1,854		
14	511106	DRILL AND BOND DOWEL	LF	187		
15	043254	RUBBER BUMPER	EA	8		
16 (F)	520102	BAR REINFORCING STEEL (BRIDGE)	LB	35,830		
17 (F)	520110	BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	LB	517,790		
18 (F)	043255	PLASTIC LUMBER	MFBM	341		
19	043256	CLEAN AND THERMAL SPRAY COAT STEEL PIPE PILE	LS	LUMP SUM	LUMP SUM	
20 (F)	750501	MISCELLANEOUS METAL (BRIDGE)	LB	255,582		