

DEPARTMENT OF TRANSPORTATION

ESC/OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



July 14, 2000

04-Ala-580-46.4
04-124454

Addendum No. 4

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in ALAMEDA COUNTY IN CASTRO VALLEY AT HAYWARD MAINTENANCE STATION.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on July 19, 2000.

This addendum is being issued to revise the Proposal and Contract.

In the Proposal and Contract, the Engineer's Estimate Item 9 is revised as attached.

To Proposal and Contract book holders:

REPLACE THE ENTIRE ENGINEER'S ESTIMATE IN THE PROPOSAL WITH THE ATTACHED REVISED ENGINEER'S ESTIMATE. THE REVISED ENGINEER'S ESTIMATE IS TO BE USED IN THE BID.

INDICATE RECEIPT OF THIS ADDENDUM BY FILLING IN THE NUMBER OF THIS ADDENDUM IN THE SPACE PROVIDED ON THE SIGNATURE PAGE OF THE PROPOSAL.

SUBMIT BIDS IN THE PROPOSAL AND CONTRACT BOOK YOU NOW POSSESS. HOLDERS WHO HAVE ALREADY MAILED THEIR BOOK WILL BE CONTACTED TO ARRANGE FOR THE RETURN OF THEIR BOOK.

INFORM SUBCONTRACTORS AND SUPPLIERS AS NECESSARY.

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

NICK YAMBAO, Chief
Office of Plans, Specifications & Estimates
Division of Office Engineer

Attachment

**ENGINEER'S ESTIMATE
04-124454**

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	074018	HEALTH AND SAFETY PLAN	LS	LUMP SUM	LUMP SUM	
2	019247	CONTAMINATED WASTE MATERIAL DISPOSAL	M3	1800		
3	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
4	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
5	150805	REMOVE CULVERT	M	89		
6	150820	REMOVE INLET	EA	1		
7	018229	REMOVE AND RESET TRAILERS	LS	LUMP SUM	LUMP SUM	
8	160101	CLEARING AND GRUBBING	LS	LUMP SUM	LUMP SUM	
9	190101	ROADWAY EXCAVATION	M3	2100		
10	198200	SUBGRADE ENHANCEMENT FABRIC	M2	5900		
11	260301	CLASS 3 AGGREGATE BASE	M3	880		
12	390102	ASPHALT CONCRETE (TYPE A)	TONN	3580		
13	394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	M	130		
14	510409	CLASS 1 CONCRETE (MINOR STRUCTURE)	M3	15		
15	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	8		
16	650068	375 MM REINFORCED CONCRETE PIPE	M	200		
17	750001	MISCELLANEOUS IRON AND STEEL	KG	690		
18	707244	900 MM PRECAST CONCRETE PIPE MANHOLE	EA	1		
19	707247	1200 MM PRECAST CONQUER PIPE MANHOLE	EA	1		

TOTAL BID: _____