

### **10-3.\_\_ EXTINGUISHABLE MESSAGE SIGN SYSTEM**

Extinguishable message sign (EMS) will be State-furnished as provided under "Materials" of these special provisions.

The work to be done at EMS system, as shown on the plans, as a minimum, shall consist of the following:

1. Install EMS panels on wood posts.
2. Install NEMA 3R enclosure, conduits and conductors on the wood post.
3. Install conduits, conductors and pull boxes from controller cabinet to EMS.
4. Terminate conductors in the controller cabinet.
5. Terminate conductors in NEMA 3R enclosure and EMS panels.