

10-3. __ TRAFFIC OPERATIONS SYSTEM EQUIPMENT TESTING

Prior to shipping to the project, the Contractor shall submit the following items to the State of California, Department of Transportation Laboratory, 5900 Folsom Blvd, Sacramento, CA 95819 for acceptance testing:

1. Integrated Camera Unit
2. Camera Control Unit (CCU)
3. Video Encoder Unit (VEU)
4. High Mast Camera Lowering Device System
5. Fiber Optic Transmitter And Receiver
6. Extinguishable Message Sign Panels
7. Remote traffic microwave sensor (RTMS) system

Approximately 30 days will be required for the testing. The Contractor will be notified upon completion of the testing and shall arrange for delivery of the equipment to a storage location designated by the Contractor. The Contractor is responsible for the costs of such testing and the transportation to and from the Laboratory.

In addition to the above items, the Contractor shall submit all additional equipment listed elsewhere in these special provisions to the Laboratory for acceptance testing.

Approximately 30 days will be required for the testing. Upon satisfactory completion of the testing, the Contractor shall pick up the equipment from the Laboratory and deliver to a State-owned storage location designated by the Engineer.