DIST.	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
04	Ala,CC	24,260	R5.9/R6.2, R0.0/R0.5,R0.9/R1.9	97	100

REGISTERED ELECTRICAL ENGINEER — 02-26-08 DATE

REGISTERED PROFESSIONAL ENGINEER ROBERT J. FEE No. E-13014 Exp. 6/30/09 ELEC STATE OF CALIFORNIA

11-24-08
PLANS APPROVAL DATE

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

STV Incorporated
9130 Anaheim Place, Suite 210
Rancho Cucamonga, CA 91730

JDL Design, LLC
18582 Beach Blvd, Suite 229
Huntington Beach, CA 92647

Emergency Telephone & Fire | Webster 400 Volt Syst. Alameda | Alarm Manager | Ack. All Alarms
CO & NO Level Display | Webster 400 Volt Syst. Oakland | Historical Trends | User Log in/Log out

2/4/2003 11:05:45 AM

Webster Alameda Exhauster Room

EXHAUSTER #1

SCADA CONTROL DAMPER
Man Auto
Open
Close
Damper In Remote
Opened
967 RPM
11326 Hrs
VFD In Remote

SCADA CONTROL EXHAUSTER VFD
Man Auto
Run
Stop
58.7 Hz

EXHAUSTER #2

SCADA CONTROL DAMPER
Man Auto
Open
Close
Damper In Remote
Closed
0 RPM
1656 Hrs
VFD In Remote

SCADA CONTROL EXHAUSTER VFD
Man Auto
Run
Stop
00.0 Hz

EXHAUSTER #3

SCADA CONTROL DAMPER
Man Auto
Open
Close
Damper In Remote
Opened
967 RPM
11326 Hrs
VFD In Remote

SCADA CONTROL EXHAUSTER VFD
Man Auto
Run
Stop
52.5 Hz

EXHAUSTER #4

SCADA CONTROL DAMPER
Man Auto
Open
Close
Damper In Remote
Opened
967 RPM
11326 Hrs
VFD In Remote

SCADA CONTROL EXHAUSTER VFD
Man Auto
Run
Stop
55.9 Hz

Notes 1) Damper(s) must be in REM for SCADA control. 2) VFD must be in REM for SCADA control. 3) Fan will not operate with damper(s) in "Closed" position. 4) Local VFD operation requires damper(s) in "Opened" position.

MM/DD HH:MM:SS	EVT	Type	Pri	Name	GroupName	Value/Limit
02/02 11:21:15	ALM	DISC	1	digon	$System	ON/ ON

Webster Exhauster Alameda | Webster Blower Alameda | Posey Exhauster Alameda | Posey Blower Alameda
Webster Exhauster Oakland | Webster Blower Oakland | Posey Exhauster Oakland | Posey Blower Oakland
Caldecott Exhst Bore 1&2W | Caldecott Blower Bore 1&2W | Caldecott Blwr/Exhst Bore 3W | Configure Posey Tube Fans
Caldecott Exhst Bore 1&2E | Caldecott Blower Bore 1&2E | Configure Caldecott Fans | Configure Webster Tube Fans

	BY	CHECKED
DESIGN	G.RUSSELL	D.LE
DETAILS	D.LE	S.LO
QUANTITIES		

PREPARED FOR THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES
ELECTRICAL-MECHANICAL-WATER AND WASTEWATER DESIGN

BRIDGE NO. VARIES
POST MILE VARIES

SCADA SYSTEM UPGRADE: POSEY/WEBSTER STREET TUBES AND CALDECOTT TUNNEL
WEBSTER STREET TUBE ALAMEDA EXHAUSTER ROOM WONDERWARE SCREEN

SHEET EE4-28-13

DOES SD Imperial Rev.1/07

ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0 1 2 3

CU 04220
EA 1A4604

DISREGARD PRINTS BEARING EARLIER REVISION DATES →
REVISION DATES (PRELIMINARY STAGE ONLY)

SHEET 92 OF 95

26-NOV-2008 11:12
EE4-28-13.dgn