

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

TTY 711

*Flex your power!
Be energy efficient!*

August 26, 2011

04-CC-4-R26.6/R27.5
04-2285E4
Project ID 0400020039

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN CONTRA COSTA COUNTY IN ANTIOCH FROM 0.3 MILE WEST OF CONTRA LOMA BOULEVARD UNDERCROSSING TO 0.2 MILE EAST OF G STREET OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, September 14, 2011, instead of the original date of Wednesday, August 31, 2011.

This addendum is being issued to set a new bid opening date as shown herein and revise the Project Plans, the Notice to Bidders and Special Provisions, and the Bid book.

Project Plan Sheets 3, 50, 307, 383 are revised. Copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 10-1.50, "MATERIAL CONTAINING HAZARDOUS WASTE CONCENTRATIONS OF AERIALY DEPOSITED LEAD," the third paragraph is revised as follows:

"Type Y-1 material contains aerially deposited lead in average concentrations of 1.5 mg/L or less extractable lead (based on a modified waste extraction test using deionized water as the extractant) and 1411 mg/kg or less total lead. Type Y-1 material exists from "E" Line Station 136+00 to "E" Line Station 179+00, and from a depth of 0 feet to 1 feet below existing grade, as shown on the plans. This material shall be placed as shown on the plans, unless otherwise directed by the Engineer, and shall be buried beneath pavement and a 2.5-foot layer of nonhazardous soil. This material is hazardous waste regulated by the State of California that may be reused as permitted under the Variance of the California Department of Toxic Substances Control (DTSC) provided that the lead contaminated soil is placed a minimum of 5 feet above the maximum water table elevation. Temporary surplus material may be generated on this project due to the requirements of stage construction. Temporary surplus material shall not be transported outside the State right of way. In order to conform to the requirements of these provisions it may be necessary to stockpile material for subsequent stages, to construct some embankments out of stage, or to handle temporary surplus material more than once."

Addendum No. 2
Page 2
August 26, 2011

04-CC-4-R26.6/R27.5
04-2285E4
Project ID 0400020039

In the Bid book, in the "Bid Item List," Item 38 is revised as attached.

To Bid book holders:

Replace page 4 of the "Bid Item List" in the Bid book with the attached revised page 4 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.


Inform subcontractors and suppliers as necessary.

This addendum and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/04/04-2285E4

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



REBECCA D. HARNAGEL
Chief, Office of Plans, Specifications & Estimates
Office Engineer
Division of Engineering Services

Attachment

BID ITEM LIST
04-2285E4

| Item No. | Item Code | Item Description | Unit of Measure | Estimated Quantity | Unit Price | Item Total |
|----------|-----------|---|-----------------|--------------------|------------|------------|
| 21 | 074034 | TEMPORARY COVER | SQYD | 3,300 | | |
| 22 | 074036 | TEMPORARY STRAW BALE BARRIER | LF | 320 | | |
| 23 | 074037 | MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL) | EA | 33 | | |
| 24 | 074038 | TEMPORARY DRAINAGE INLET PROTECTION | EA | 60 | | |
| 25 | 074040 | TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX) | SQYD | 28,900 | | |
| 26 | 074041 | STREET SWEEPING | LS | LUMP SUM | LUMP SUM | |
| 27 | 074056 | RAIN EVENT ACTION PLAN | EA | 99 | 500.00 | 49,500.00 |
| 28 | 074057 | STORM WATER ANNUAL REPORT | EA | 4 | 2,000.00 | 8,000.00 |
| 29 | 074058 | STORM WATER SAMPLING AND ANALYSIS DAY | EA | 23 | | |
| 30 | 120090 | CONSTRUCTION AREA SIGNS | LS | LUMP SUM | LUMP SUM | |
| 31 | 120100 | TRAFFIC CONTROL SYSTEM | LS | LUMP SUM | LUMP SUM | |
| 32 | 120120 | TYPE III BARRICADE | EA | 150 | | |
| 33 | 120149 | TEMPORARY PAVEMENT MARKING (PAINT) | SQFT | 2,210 | | |
| 34 | 120159 | TEMPORARY TRAFFIC STRIPE (PAINT) | LF | 96,000 | | |
| 35 | 120165 | CHANNELIZER (SURFACE MOUNTED) | EA | 1,840 | | |
| 36 | 120300 | TEMPORARY PAVEMENT MARKER | EA | 4,410 | | |
| 37 | 128650 | PORTABLE CHANGEABLE MESSAGE SIGN | LS | LUMP SUM | LUMP SUM | |
| 38 | 129000 | TEMPORARY RAILING (TYPE K) | LF | 45,500 | | |
| 39 | 129100 | TEMPORARY CRASH CUSHION MODULE | EA | 300 | | |
| 40 | 021115 | TEMPORARY CRASH CUSHION (TYPE ABSORB 350) | EA | 63 | | |