

DEPARTMENT OF TRANSPORTATION

DES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

August 2, 2002

04-Ala-880-24.8/25.7, 27.3/28.8
04-243004
ACIM-880-1(050)E

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for Highway Planting on State highway in ALAMEDA COUNTY IN HAYWARD ON ROUTE 880 FROM 0.3 KM SOUTH TO 0.6 KM NORTH OF TENNYSON ROAD OVERCROSSING AND FROM 0.6 KM SOUTH TO 0.5 KM NORTH OF WINTON AVENUE OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on August 20, 2002.

This addendum is being issued to revise the Project Plans, the Notice to Contractors and Special Provisions, the Proposal and Contract and the Federal Minimum Wages with Modification Number 12 dated 7-19-02. A copy of the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

Project Plan Sheets 12, 21, 22, 23, 24, 25, 26, 27 and 28 are revised. Half-sized copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 10-2.04 "HIGHWAY PLANTING," in the subsection "PLANT ESTABLISHMENT WORK," after the third paragraph the table listing the spacing of replacement ground cover plants is revised as follows:

ORIGINAL SPACING (Millimeters)	SPACING OF REPLACEMENT GROUND COVER PLANTS (Millimeters)		
	Number of Completed Plant Establishment Working Days		
	1-125	126-190	191-End of Plant Establishment
500	500	340	270

Addendum No. 3
Page 2
August 2, 2002

04-Ala-880-24.8/25.7, 27.3/28.8
04-243004
ACIM-880-1(050)E

In the Proposal and Contract, the Engineer's Estimate Items 10 and 14 are revised and Item 26 is deleted as attached.

To Proposal and Contract book holders:

Replace pages 3 and 4 of the Engineer's Estimate in the Proposal with the attached revised pages 3 and 4 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by UPS overnight mail to Proposal and Contract book holders to ensure that each receives it.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

**ENGINEER'S ESTIMATE
04-243004**

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1 (S)	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM	LUMP SUM	
2	074020	WATER POLLUTION CONTROL	LS	LUMP SUM	LUMP SUM	
3	024188	TEMPORARY DRAINAGE INLET PROTECTION	EA	3		
4	074029	TEMPORARY SILT FENCE	M	150		
5 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
6 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
7	128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	LUMP SUM	LUMP SUM	
8	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
9	200002	ROADSIDE CLEARING	LS	LUMP SUM	LUMP SUM	
10	200120	CULTIVATE	M2	32 320		
11	202011	MULCH	M3	550		
12	203021	FIBER ROLLS	M	2640		
13	024189	FIBER ROLL CHECK DAM	EA	3		
14	204008	PLANT (GROUP H)	EA	179 470		
15	204035	PLANT (GROUP A)	EA	1440		
16	204038	PLANT (GROUP U)	EA	400		
17	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM	LUMP SUM	
18	206560	CONTROL AND NEUTRAL CONDUCTORS	LS	LUMP SUM	LUMP SUM	
19	206611	25 MM ELECTRIC REMOTE CONTROL VALVE	EA	23		
20	206613	40 MM ELECTRIC REMOTE CONTROL VALVE	EA	23		

**ENGINEER'S ESTIMATE
04-243004**

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	206614	50 MM ELECTRIC REMOTE CONTROL VALVE	EA	17		
22	206615	65 MM ELECTRIC REMOTE CONTROL VALVE	EA	6		
23	206616	75 MM ELECTRIC REMOTE CONTROL VALVE	EA	13		
24	206753	24 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	3		
25	024190	32 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	1		
26	BLANK					
27 (F)	208249	20 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	7583		
28 (F)	208250	25 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	2595		
29 (F)	208251	32 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	2032		
30 (F)	208252	40 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	1256		
31 (F)	208253	50 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	1137		
32 (F)	208254	65 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	451		
33 (F)	208255	75 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3723		
34	024192	50 MM FLOW SENSOR	EA	4		
35	024193	FLOW MONITOR PACKAGE	EA	4		
36	208467	SPRINKLER (TYPE A-7)	EA	220		
37	208471	SPRINKLER (TYPE B-1)	EA	680		
38	208482	SPRINKLER (TYPE C-2)	EA	980		
39	208488	25 MM GATE VALVE	EA	3		
40	208490	40 MM GATE VALVE	EA	3		