

DEPARTMENT OF TRANSPORTATION

DES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

August 26, 2003

04-SF-80-7.4/8.1
04-248214
ER-1599(004)E

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in THE CITY AND COUNTY OF SAN FRANCISCO FROM 0.1 KM SOUTH OF HARRIET STREET TO FOURTH STREET.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on September 9, 2003.

This addendum is being issued to revise the Notice to Contractors and Special Provisions, and the Proposal and Contract.

In the Special Provisions, Section 10-1.28, "EXISTING HIGHWAY FACILITIES," subsection "BRIDGE REMOVAL," the following is added after the first paragraph:

"In addition to the portions of the bridge shown on the plans to be removed, existing barrier shall be removed within the limits shown on the plans for barrier replacement."

In the Special Provisions, Section 10-1.44 "PILING," subsection "MEASUREMENT AND PAYMENT (PILING)," the second paragraph is revised as follows:

"The length of furnish piling (unfilled) and furnish piling (filled) are based on the total length measured from the specified tip elevations to the plane of pile cut-off shown on the plans for the soil cement piling alternative. No change in the quantities to be paid will be made because of the use by the Contractor of the cast-in-steel-shell concrete piling alternative."

In the Proposal and Contract, the Engineer's Estimate Items 70 and 72 are revised as attached.

Addendum No. 3
Page 2
August 26, 2003

04-SF-80-7.4/8.1
04-248214
ER-1599(004)E

To Proposal and Contract book holders:

Replace page 6 of the Engineer's Estimate in the Proposal with the attached revised page 6 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it. A copy of this addendum and the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachment

**ENGINEER'S ESTIMATE
04-248214**

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	030549	IMPORTED BORROW(LIGHTWEIGHT AGGREGATE)	M3	70		
62 (S)	030550	EROSION CONTROL (MULCH)	M3	35		
63	250401	CLASS 4 AGGREGATE SUBBASE	M3	23		
64	260301	CLASS 3 AGGREGATE BASE	M3	60		
65	374206	SEAL RANDOM CRACKS	LNKM	5		
66	390102	ASPHALT CONCRETE (TYPE A)	TONN	1750		
67	394042	PLACE ASPHALT CONCRETE DIKE (TYPE B)	M	80		
68	397001	ASPHALTIC EMULSION (PAINT BINDER)	TONN	11		
69	405030	PORTLAND CEMENT CONCRETE BASE	M3	75		
70 (F)	049454	FURNISH PILING (UNFILLED)	M	987		
71 (S)	049455	INSTALL PILE (UNFILLED)	EA	30		
72 (F)	049456	FURNISH PILING (FILLED)	M	8542		
73 (S)	049457	INSTALL PILING (FILLED)	EA	348		
74 (S)	500001	PRESTRESSING CAST-IN-PLACE CONCRETE	LS	LUMP SUM	LUMP SUM	
75 (F)	510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	M3	1446		
76 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	M3	1730		
77 (F)	510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	M3	17		
78 (F)	510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	M3	29		
79	510220	CLASS 3 CONCRETE (BACKFILL)	M3	10		
80 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	40		