

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

[www.dot.ca.gov/hq/esc/oe](http://www.dot.ca.gov/hq/esc/oe)

*Serious Drought.  
Help save water!*

October 21, 2015

04-SCI-17, 85, 87, 101, 280, 680, 880, 237-VARIOUS

04-2J1704

Project ID 0414000434

ACNHP-X085(057)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN SANTA CLARA COUNTY AT VARIOUS LOCATIONS.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, October 29, 2015.

This addendum is being issued to revise the project plans, the *Notice to Bidders and Special Provisions* and the *Bid* book.

Project plan sheets 6, 15, 18, 40, 42, 44, 55, 57, and 60 are replaced and attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 14-6.02 is replaced as attached.

In the Special Provisions, Section 14-6.05 is replaced as attached.

In the Special Provisions, Section 14-6.08 is deleted.

In the *Bid* book, in the "Bid Item List," Items 9, 10, 11 and 12 are replaced.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

**[http://www.dot.ca.gov/hq/esc/oe/electronic\\_bidding/electronic\\_bidding.html](http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html)**

Inform subcontractors and suppliers as necessary.

Addendum No. 1  
Page 2  
October 21, 2015

04-SCI-17, 85, 87, 101, 280, 680, 880, 237-VARIOUS  
04-2J1704  
Project ID 0414000434  
ACNHP-X085(057)E

This addendum, EBS addendum file and attachments are available for the Contractors' download on the Web site:

[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/04/04-2J1704](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/04/04-2J1704)

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



BIJAN SARTIPI  
District Director

Attachments

Replace section 14-6.02 with:

**14-6.02 SPECIES PROTECTION**

**14-6.02A General**

Section 14-6.02 includes specifications for protecting regulated species or their habitat.

This project is within or near habitat for regulated species shown in the following table:

Species Name
Nesting migratory birds
Nesting raptors

The Department anticipates nesting or attempted nesting by migratory and nongame birds from February 1 to August 31.

**14-6.02B Material**

Not Used

**14-6.02C Construction**

**14-6.02C(1) General**

Not Used

**14-6.02C(2) Protective Radius**

Upon discovery of a regulated species, stop construction activities within a 50-foot radius of the discovery or as defined in the table below. Immediately notify the Engineer. Do not resume activities until receiving notification from the Engineer.

Regulated species name	Protective radius
Nesting raptors	300 feet

**14-6.02C(3) Protocols**

Not Used

**14-6.02C(4) Biological Resource Information**

Not Used

#### **14-6.02C(5) Protection Measures**

Within job site, implement the following protection measures:

1. Pre-construction survey notification:
  - 1.1 Notify the Engineer at least 30 days before starting job site activities such that pre-construction surveys can be conducted.
2. Nesting migratory bird protection:
  - 2.1 Initial bird surveys and work authorization period:
    - 2.1.1 Notify the Engineer 10 days before the start of work. A contractor supplied biologist will perform an initial nesting bird survey of the job site
    - 2.1.2 Proceed with work when authorized.
    - 2.1.3 This work authorization is valid for 72 hours.
  - 2.2 Subsequent bird surveys and work authorization periods:
    - 2.2.1 After 72 hours, the contractor supplied biologist is required to perform another bird survey of the job site and work area.
    - 2.2.2 Proceed with work when authorized.
    - 2.2.3 Work authorization is valid for 72 hours.
  - 2.3 If you discover a nest, stop work within the protective radius immediately and notify the Engineer. Do not disturb birds or nests occupied by birds, hatchlings or eggs. Do not resume work until directed.
3. Nighttime construction activities:
  - 4.1 During night work, direct construction lights away from natural areas.
4. Work performed near salt marshes:
  - 4.1 Perform work at the following locations only in the non-nesting season from September 1 to January 31:
    - 4.1.1 On Route 880, sign location number 304, 305 and 306.
    - 4.1.2 On Route 237, sign location number 322, 323, 324 and 325.

#### **14-6.02C(6) Monitoring Schedule**

Not Used

#### **14-6.02D Payment**

Not Used

Replace section 14-6.05 with:

**14-6.05 CONTRACTOR-SUPPLIED BIOLOGIST**

**14-6.05A General**

**14-6.05A(1) Summary**

Section 14-6.05 includes specifications for providing a Contractor-supplied biologist to monitor construction and other activities to protect regulated species that may be harmed during construction activities.

**14-6.05A(2) Submittals**

**14-6.05A(2)(a) Qualifications**

Within 7 days after Contract approval, submit each biologist's name, resume, and statement of qualifications. Allow 15 days for review. If the submittal is incomplete, the Engineer will provide comments. Within 7 days after receiving the Engineer's comments, update and resubmit qualifications data. Do not start construction activities until the Contractor-supplied biologist is authorized.

**14-6.05A(2)(b) Protocols**

Within 30 days before beginning survey activities, submit protocols for species protection surveys for acceptance.

**14-6.05A(2)(c) Pre-Construction Survey Report**

Submit a pre-construction survey report within 14 days before starting construction activities.

**14-6.05A(2)(d) Initial Monitoring Report**

Submit an Initial Monitoring Report that includes, at a minimum, the requirements for Monitoring Report submittals within 12 hours after starting ground-disturbing activities.

**14-6.05A(2)(e) Monitoring Report**

Submit a Monitoring Report every 5 working days during the monitoring period.

**14-6.05A(2)(f) Incident Report**

Submit an Incident Report within 24 hours of the incident.

**14-6.05A(2)(g) Annual Monitoring Report**

Not Used

**14-6.05A(2)(h) Final Monitoring Report**

Not Used

**14-6.05A(3) Quality Control and Assurance**

Not Used

**14-6.05A(3)(a) Qualifications**

Not Used

**14-6.05A(3)(b) Protocols**

Not Used

**14-6.05B Materials**

Not Used

**14-6.05C Construction**

**14-6.05C(1) General**

Not Used

**14-6.05C(2) Pre-construction Survey**

Survey the work area for regulated species within 3 days before starting construction activities.

#### **14-6.05C(3) Protective Radius**

Upon discovery of a regulated species, stop construction activities within a 100 foot radius of the discovery. Immediately notify the Engineer. Do not resume activities until the Engineer notifies you.

#### **14-6.05C(4) Monitoring Schedule**

Monitoring must comply with the schedule in section 14-6.02.

#### **14-6.05C(5) Monitoring Duties**

The biologist must:

1. Monitor for regulated species within the project area.
2. Assure that construction activities do not result in take of regulated species.
3. Assure that construction activities comply with PLACs.
4. Immediately notify the Engineer of any take of regulated species.
5. Prepare, submit, and sign notifications and reports.

#### **14-6.05C(6) Notification and Reporting**

All reports must include the following:

1. PLAC requirement implementation
2. Name(s) of the biologist(s) conducting biological activity
3. Date(s) and time(s) of monitoring
4. Locations and activities monitored
5. Representative photographs
6. Findings
7. If regulated species are observed, reports must recommend actions to protect the regulated species
8. Name of the biologist who prepared the report
9. Signature of the biologist certifying the accuracy of the report

The Pre-Construction Survey Report includes one of the following:

1. Detailed observations and locations where regulated species were observed
2. Statement that no regulated species were observed by each biologist

The Incident Report includes:

1. Description of any take incident
2. Species name and number taken
3. Details of required notifications with contact information
4. Corrective actions proposed or taken
5. Disposition of taken species

#### **14-6.05D Payment**

Not Used

**BID ITEM LIST  
04-2J1704**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	090105	TIME-RELATED OVERHEAD (LS)	LS	LUMP SUM	LUMP SUM	
2	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
3	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
4	128652	PORTABLE CHANGEABLE MESSAGE SIGN (LS)	LS	LUMP SUM	LUMP SUM	
5	130100	JOB SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
6	130200	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
7	146002	CONTRACTOR-SUPPLIED BIOLOGIST (LS)	LS	LUMP SUM	LUMP SUM	
8	150755	REMOVE SIGN STRUCTURE WALKWAY (EA)	EA	340		
9	568016	INSTALL SIGN PANEL ON EXISTING FRAME	SQFT	73,100		
10	029995	FURNISH FORMED PANEL SIGN (OVERHEAD) FOR RETROREFLECTIVE SHEETING (TYPE XI)	SQFT	55,200		
11	029996	FURNISH LAMINATED PANEL SIGN (1"-TYPE A) FOR RETROREFLECTIVE SHEETING (TYPE XI)	SQFT	18,000		
12	029997	RETROREFLECTIVE SHEETING(TYPE X1)	SQFT	73,100		
13	860508	MODIFY SIGN ILLUMINATION	LS	LUMP SUM	LUMP SUM	
14	029998	REMOVE ELECTRICAL SYSTEM	LS	LUMP SUM	LUMP SUM	
15	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

**TOTAL BID:**

**\$**

---