

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER, MS 43
1727 30TH STREET
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
TTY (916) 227-8454



*Flex your power!
Be energy efficient!*

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

November 21, 2008

04-SCI-9-0.0/7.1
04-3A0704

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in SANTA CLARA COUNTY FROM SANTA CLARA COUNTY LINE TO 6TH STREET.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on December 9, 2008.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, and the Bid book.

Project Plan Sheet 1 is revised. Half-sized copies of the revised sheet is attached for substitution for the like-numbered sheet.

Project Plan Sheets 11A and 11B are added. Half-sized copies of the added sheets are attached for addition to the project plans.

In the "NOTICE TO CONTRACTORS," the seventh paragraph is revised as follows:

"At the time this contract is awarded, the Contractor shall possess either a Class A license or a combination of Class C licenses which constitutes a majority of the work: C-32, C-61D42."

In the Special Provisions, Section 10-1.07," CONSTRUCCION AREA SIGNS," the following paragraph is added after the fourth paragraph.

"Orange background on construction area signs shall be fluorescent orange."

04-SCI-9-0.0/7.1
04-3A0704

In the Special Provisions, Section 10-1.155, "ROADSIDE SIGNS," is added as follows:

"10-1.155 ROADSIDE SIGNS

Roadside signs shall be furnished and installed at the locations shown on the plans or where designated by the Engineer and in conformance with the provisions in Section 56-2, "Roadside Signs," of the Standard Specifications and these special provisions.

The Contractor shall furnish roadside sign panels in conformance with the provisions in "Furnish Sign" of these special provisions.

Wood posts shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications and AWPAs Use Category System: UC4A, Commodity Specification A or B."

In the Special Provisions, Section 10-1.16, "FURNISH SIGN," after the subsection "SINGLE SHEET ALUMINUM SIGN," the following subsection is added:

"MEASUREMENT AND PAYMENT

Furnishing signs (except for construction area signs) will be measured by the square foot and the quantity to be paid for will be the total area, in square feet, of the sign panel types installed in place.

The contract price paid per square foot for furnish sign of the types specified in the Engineer's estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in fabricating and furnishing the signs, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for furnishing and installing protective overlay on signs shall be considered as included in the contract price paid per square foot for furnish sign of the various types and no separate payment will be made therefor."

In the Bid book, in the "Bid Item List," Items 15 and 16 are added as attached.

To Proposal and Contract book holders:

Replace page 3 of the "Bid Item List" in the Bid book with the attached revised page 3 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 3
Page 3
November 21, 2008

04-SCI-9-0.0/7.1
04-3A0704

This office is sending this addendum by GSO overnight mail to Proposal and Contract book holders to ensure that each receives it. A copy of this addendum is available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

BIJAN SARTIPI
District Director
For AADD projects from District 4

Attachments

**ENGINEER'S ESTIMATE
04-3A0704**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
2	074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
3	074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	2		
4	074041	STREET SWEEPING	LS	LUMP SUM	LUMP SUM	
5	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
6	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
7	128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2		
8	150704	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	LF	74,800		
9	150722	REMOVE PAVEMENT MARKER	EA	9,300		
10	015216	LEAD COMPLIANCE PLAN (STRIPE REMOVAL)	LS	LUMP SUM	LUMP SUM	
11	015217	CENTERLINE RUMBLE STRIP (AC, GROUND-IN INDENTATIONS)	STA	380		
12	840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	150,000		
13	840506	8" THERMOPLASTIC TRAFFIC STRIPE	LF	970		
14	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	9,360		
15	560248	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	SQFT	270		
16	566011	ROADSIGN SIGN - ONE POST	EA	24		

TOTAL BID: _____