**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, exerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

STATE OF CALIFORNIA

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

AND

SPECIAL PROVISIONS

FOR CONSTRUCTION ON STATE HIGHWAY IN

SANTA CLARA COUNTY IN SAN JOSE

FROM 0.4 KM NORTH OF BRAHNAM LANE OVERCROSSING

TO 0.4 KM NORTH OF VIRGINIA STREET OVERCROSSING

DISTRICT 04, ROUTE 87

For Use in Connection with Standard Specifications Dated JULY 1999,

Standard Plans Dated JULY 1999, and Labor Surcharge and Equipment Rental Rates.

CONTRACT NO. 04-4396U4

04-SCl-87-1.6/8.1

Federal Aid Project

ACNH-S087(027)E

Bids Open: September 28, 2004
Dated: August 2, 2004

OSD

****

IMPORTANT SPECIAL NOTICES

****

Effective September 2, 2003, Triaxial Management Services will no longer provide lists of certified DBEs to contractors bidding on projects or provide DBEs with assistance in preparing bids for subcontracting or supplying materials. Triaxial provided these services for contracts in Districts 01, 02, 03, 04, 05 (except San Luis Obispo and Santa Barbara Counties), 06 (except Kern County), 09 and 10.

Contractors bidding on projects in these Districts may obtain lists of certified DBEs from the Department's Website at http://www.dot.ca.gov/hq/bep. The Department also publishes a quarterly directory of certified firms that may be ordered from the Publications Unit at (916) 445-3520.

Contractors bidding on projects with DBE goals in Districts 05 (San Luis Obispo and Santa Barbara Counties), 06 (Kern County), 07, 08, 11 and 12 may continue to call Padilla & Associates at the telephone numbers listed in the Special Provisions.

TABLE OF CONTENTS

NOTICE TO CONTRACTORS 1
COPY OF ENGINEER'S ESTIMATE 4
SPECIAL PROVISIONS 18
SECTION 1. SPECIFICATIONS AND PLANS 18
AMENDMENTS TO JULY 1999 STANDARD SPECIFICATIONS 18
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS 71
2-1.01 GENERAL 71
2-1.015 FEDERAL LOBBYING RESTRICTIONS 71
2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE) 72
2-1.02A DBE GOAL FOR THIS PROJECT 73
2-1.02B SUBMISSION OF DBE INFORMATION 74
SECTION 3. AWARD AND EXECUTION OF CONTRACT 75
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES 76
SECTION 5. GENERAL 76
SECTION 5-1. MISCELLANEOUS 76
5-1.01 PLANS AND WORKING DRAWINGS 76
5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK 76
5-1.012 DIFFERING SITE CONDITIONS 76
5-1.013 LINES AND GRADES 77
5-1.015 LABORATORY 77
5-1.017 CONTRACT BONDS 77
5-1.019 COST REDUCTION INCENTIVE 77
5-1.02 LABOR NONDISCRIMINATION 77
5-1.022 EXCLUSION OF RETENTION 77
5-1.023 UNSATISFACTORY PROGRESS 78
5-1.03 INTEREST ON PAYMENTS 78
5-1.04 PUBLIC SAFETY 78
5-1.05 TESTING 79
5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES 79
5-1.07 YEAR 2000 COMPLIANCE 80
5-1.075 BUY AMERICA REQUIREMENTS 80
5-1.08 SUBCONTRACTOR AND DBE RECORDS 80
5-1.083 DBE CERTIFICATION STATUS 81
5-1.086 PERFORMANCE OF DBE SUBCONTRACTORS AND SUPPLIERS 81
5-1.09 SUBCONTRACTING 81
5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS 82
5-1.103 RECORDS 82
5-1.11 PARTNERING 82
5-1.114 VALUE ANALYSIS 83
5-1.12 DISPUTE REVIEW BOARD 83
5-1.13 FORCE ACCOUNT PAYMENT 93
5-1.14 RESPONSIBILITY TO OTHER ENTITIES 94
5-1.15 COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS 94
5-1.16 AREAS FOR CONTRACTOR'S USE 95
5-1.17 PAYMENTS 95
5-1.18 SOUND CONTROL REQUIREMENTS 96
5-1.19 RELATIONS WITH CALIFORNIA DEPARTMENT OF FISH AND GAME 96
5-1.20 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD 97
5-1.21 RELATIONS WITH U.S. ARMY CORPS OF ENGINEERS 97
5-1.22 RELATIONS WITH SANTA CLARA VALLEY WATER DISTRICT 98
5-1.23 RELATIONS WITH CITY OF SAN JOSE 98
5-1.24 RELATIONS WITH SANTA CLARA COUNTY ROADS AND AIRPORTS DEPARTMENT 98
5–1.25 RELATIONS WITH SANTA CLARA VALLEY TRANSPORTATION AUTHORITY 99
SANTA CLARA VALLEY TRANSPORTATION AUTHORITY 99

ENCROACHMENT PROCEDURES WITHIN LIGHT RAIL RIGHT OF WAY....99
PERMIT REQUIREMENTS....99
AUTHORITY....100
ADMINISTRATIVE AUTHORITY....100
OCC AUTHORITY....100
DEFINITIONS....100
SERVICE SCHEDULE....101
GENERAL....101
SAFETY AND HEALTH PROVISIONS....102
SITE SPECIFIC WORK PLAN (SSWP)....102
VTA LRT OPERATING RULES AND PROCEDURES....103
RESTRICTED ACCESS PERMIT....103
LRT FLAGGERS....103
CLEARANCE FROM ENERGIZED LINES....104
SAFETY TRAINING....104
EMERGENCY CONTACT....104
CONTRACTOR ACCESS....104
SINGLE TRACKING OPERATIONS....104
TRACK ALLOCATION MEETINGS....105
RIGHT OF WAY....105
TRACKS....105
DRAINAGE PIPES AND CONDUITS....105
TRACTION ELECTRIFICATION SYSTEM....106
SIGNALS....106
TRACTION POWER "LOCKOUT AND TAG" PROCEDURE....106
REMOVAL OF POWER....106
LOCKOUT AND TAG PROCEDURE....106
RESTORATION OF POWER....106
LOCKOUT AND TAG PROCEDURE....106
CONTRACTOR REPRESENTATIVE....106
LOCKS AND TAGS UNACCOUNTED FOR....107
RESTRICTIONS WHILE OCS IS ENERGIZED....107
WARNING FLAGS....107
REDUCED SPEED ZONE, (HIGH SPEED AUTOMATIC BLOCK SIGNAL SYSTEM (ABS) AREAS)....107
EMERGENCY PROTECTION, (HIGH SPEED ABS AREAS)....108
EMERGENCY PROTECTION....108
HAND SIGNALS....108
PROTECTION OF BALLAST....108
SAFETY FENCE....108
CONSTRUCTION REQUIREMENTS....109
PAYMENT....109
5-1.26 NATURALLY OCCURRING ASBESTOS MATERIAL, GENERAL....109
5-1.27 HAZARDOUS, RESTRICTED AND NON-HAZARDOUS MATERIAL, GENERAL....111
APPLICABLE RULES AND REGULATIONS....112
PERMITS AND LICENSES....112
HEALTH SAFETY AND WORK PLAN....112
SAFETY....112
STOCKPILING....113
SAMPLING AND ANALYSIS....113
MEASUREMENT AND PAYMENT....114
5-1.28 AERIALLY DEPOSITED LEAD....114
5-1.29 ENVIRONMENTALLY SENSITIVE AREA....114
5-1.30 ARCHAEOLOGICAL SENSITIVE AREAS....114
5-1.31 MITIGATION MEASURES....115
5-1.32 MIGRATORY NESTING BIRDS AND ROOSTING WILDLIFE....117
SECTION 6. (BLANK)....117
SECTION 7. (BLANK)....117
SECTION 8. MATERIALS....117
SECTION 8-1. MISCELLANEOUS....117

8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS 118
8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS 124
PAVEMENT MARKERS, PERMANENT TYPE 124
PAVEMENT MARKERS, TEMPORARY TYPE 125
STRIPING AND PAVEMENT MARKING MATERIAL 125
CLASS 1 DELINEATORS 126
CHANNELIZERS 126
CONICAL DELINEATORS, 1070 mm 127
OBJECT MARKERS 127
CONCRETE BARRIER MARKERS AND 127
TEMPORARY RAILING (TYPE K) REFLECTORS 127
METAL BEAM GUARD RAIL POST MARKERS 128
CONCRETE BARRIER DELINEATORS, 400 mm 128
CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm) 128
SOUND WALL DELINEATOR 128
GUARD RAILING DELINEATOR 128
RETROREFLECTIVE SHEETING 128
SPECIALTY SIGNS 129
SIGN SUBSTRATE 130
8-1.03 STATE-FURNISHED MATERIALS 130
8-1.04 ADHESIVE FOR BONDING REFLEX REFLECTORS TO PORCELAIN ENAMEL TRAFFIC SIGNS 130
8-1.05 ENGINEERING FABRICS 131
SECTION 8-2. CONCRETE 131
8-2.01 PORTLAND CEMENT CONCRETE 131
8-2.02 PRECAST CONCRETE QUALITY CONTROL 132
GENERAL 132
PRECAST CONCRETE QUALIFICATION AUDIT 133
PRECAST CONCRETE QUALITY CONTROL PLAN 133
REPORTING 134
PAYMENT 134
SECTION 8-3. WELDING 134
8-3.01 WELDING 135
GENERAL 135
WELDING QUALITY CONTROL 137
WELDING FOR OVERHEAD SIGN AND POLE STRUCTURES 139
PAYMENT 139
SECTION 9. DESCRIPTION OF BRIDGE WORK 139
SECTION 10. CONSTRUCTION DETAILS 141
SECTION 10-1. GENERAL 141
10-1.00 CONSTRUCTION PROJECT INFORMATION SIGNS 141
10-1.01 ORDER OF WORK 141
10-1.02 WATER POLLUTION CONTROL 143
RETENTION OF FUNDS 144
STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND AMENDMENTS 144
COST BREAK-DOWN 146
SWPPP IMPLEMENTATION 148
MAINTENANCE 149
REPORTING REQUIREMENTS 149
SAMPLING AND ANALYTICAL REQUIREMENTS 150
PAYMENT 151
10-1.03 TEMPORARY DRAINAGE INLET PROTECTION 152
MATERIALS 152
INSTALLATION 155
MAINTENANCE 156
MEASUREMENT AND PAYMENT 157
10-1.04 TEMPORARY EROSION CONTROL 157
MATERIALS 157

APPLICATION 158
MEASUREMENT AND PAYMENT 158
10-1.05 TEMPORARY COVER 158
10-1.06 TEMPORARY DRAINAGE FACILITIES 160
10-1.07 TEMPORARY CONCRETE WASHOUT FACILITY 161
10-1.08 TEMPORARY SILT FENCE 163
10-1.09 TEMPORARY FENCE (TYPE ESA) 165
MATERIALS 165
INSTALLATION 165
MAINTENANCE 166
MEASUREMENT AND PAYMENT 166
10-1.10 PRESERVATION OF PROPERTY 166
10-1.11 TEMPORARY CONSTRUCTION ENTRANCE 166
10-1.12 FISH FRIENDLY DIVERSION 168
MEASUREMENT AND PAYMENT 169
10-1.13 COOPERATION 169
10-1.14 PROGRESS SCHEDULE (CRITICAL PATH METHOD) 170
DEFINITIONS 170
GENERAL REQUIREMENTS 170
COMPUTER SOFTWARE 172
NETWORK DIAGRAMS, REPORTS AND DATA 172
PRE-CONSTRUCTION SCHEDULING CONFERENCE 173
BASELINE SCHEDULE 173
UPDATE SCHEDULE 174
TIME IMPACT ANALYSIS 174
FINAL UPDATE SCHEDULE 174
RETENTION 175
PAYMENT 175
10-1.15 TIME-RELATED OVERHEAD 175
10-1.16 OBSTRUCTIONS 178
10-1.17 DUST CONTROL 179
10-1.18 MOBILIZATION 179
10-1.19 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES 179
10-1.20 CONSTRUCTION AREA SIGNS 179
10-1.21 MAINTAINING TRAFFIC 180
10-1.22 CLOSURE REQUIREMENTS AND CONDITIONS 195
CLOSURE SCHEDULE 195
CONTINGENCY PLAN 195
LATE REOPENING OF CLOSURES 195
COMPENSATION 195
10-1.23 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE 196
STATIONARY LANE CLOSURE 196
MOVING LANE CLOSURE 196
PAYMENT 197
10-1.24 TEMPORARY PAVEMENT DELINEATION 197
GENERAL 197
TEMPORARY LANELINE AND CENTERLINE DELINEATION 198
TEMPORARY EDGELINE DELINEATION 198
TEMPORARY TRAFFIC STRIPE (PAINT) 199
TEMPORARY PAVEMENT MARKING (PAINT) 199
TEMPORARY PAVEMENT MARKERS 199
MEASUREMENT AND PAYMENT 199
10-1.25 PORTABLE CHANGEABLE MESSAGE SIGN 200
10-1.26 TEMPORARY RAILING 200
10-1.27 CHANNELIZER 200
10-1.28 TEMPORARY CRASH CUSHION MODULE 200
10-1.29 EXISTING HIGHWAY FACILITIES 202
ABANDON CULVERT 202
ABANDON RISER 203

ABANDON PIEZOMETER 203
SALVAGE METAL BEAM GUARD RAILING 203
REMOVE SIGN STRUCTURE 203
REMOVE PAVEMENT MARKER 204
REMOVE FENCE 204
REMOVE TRAFFIC STRIPE 204
REMOVE CULVERT 205
REMOVE UNDERDRAIN 205
REMOVE SEWER PIPE 206
REMOVE PVC WATERLINE 206
REMOVE DRAINAGE FACILITY 206
REMOVE ASPHALT CONCRETE DIKE 206
CLEANOUT EXISTING DRAINAGE FACILITY 206
REMOVE ROADSIDE SIGN 206
REMOVE FRAMED SIGN PANEL 207
REMOVE CRASH CUSHION (SAND FILLED) 207
RECONSTRUCT CHAIN LINK RAILING 207
PLASTIC PIPELINER 207
CURED-IN-PLACE PIPE (CIPP) 208
PRODUCT, MANUFACTURER/INSTALLER QUALIFICATION REQUIREMENTS 208
MATERIALS 209
STRUCTURAL REQUIREMENTS 209
TESTING REQUIREMENTS 211
INSTALLATION RESPONSIBILITIES FOR INCIDENTAL ITEMS 211
INSTALLATION 211
REINSTATEMENT OF BRANCH CONNECTIONS 212
INSPECTION 212
CLEAN-UP 212
PAYMENT 212
ADJUST INLET 212
REMOVE PORTLAND CEMENT CONCRETE PAVEMENT 212
REMOVE BASE AND SURFACING 213
COLD PLANE ASPHALT CONCRETE PAVEMENT 213
REMOVE SOUNDWALL 213
CLEAN BRIDGE DECK 214
BRIDGE REMOVAL 214
ACCESS OPENING, SOFFIT 217
BRIDGE REMOVAL: ASBESTOS CONTAINING MATERIAL 217
REMOVAL OF ASBESTOS 218
AUTHORIZED PERSONNEL ONLY 219
PAYMENT 219
ASBESTOS HEALTH AND SAFETY PLAN 219
TRAINING 220
EQUIPMENT AND MEDICAL SURVEILLANCE 220
REMOVE CONCRETE 220
REMOVE SLOPE PROTECTION 220
10-1.30 CLEARING AND GRUBBING 220
10-1.31 WATERING 221
10-1.32 EARTHWORK 221
10-1.33 HAZARDOUS, RESTRICTED AND NON-HAZARDOUS MATERIAL EXCAVATION 223
MEASUREMENT AND PAYMENT 224
10-1.34 DEWATERING 224
MATERIALS 225
MONITORING 226
MEASUREMENT AND PAYMENT 227
10-1.35 NATURALLY OCCURRING ASBESTOS MATERIAL EXCAVATION 227
PAYMENT 229
10-1.36 LIGHTWEIGHT EMBANKMENT MATERIAL (CELLULAR CONCRETE) 229
10-1.37 COMPACTION GROUTING 230

GENERAL 230
DEFINITIONS 231
SUBMITTALS 231
MATERIALS 231
EQUIPMENT 232
CONSTRUCTION PROCEDURES 232
PERFORMANCE CRITERIA 234
MEASUREMENT AND PAYMENT 234
10-1.38 MATERIAL CONTAINING AERIALLY DEPOSITED LEAD 234
LEAD COMPLIANCE PLAN 234
DUST CONTROL 235
10-1.39 EROSION CONTROL (BLANKET) 235
MATERIALS 235
APPLICATION 236
MEASUREMENT AND PAYMENT 236
10-1.40 MOVE-IN/MOVE-OUT (EROSION CONTROL) 237
10-1.41 EROSION CONTROL (TYPE D) 237
MATERIALS 237
APPLICATION 239
MEASUREMENT AND PAYMENT 239
10-1.42 FIBER ROLLS 239
MATERIALS 239
INSTALLATION 240
MEASUREMENT AND PAYMENT 240
10-1.43 IRRIGATION CROSSOVERS 240
10-1.44 EXTEND IRRIGATION CROSSOVERS 240
10-1.45 AGGREGATE SUBBASE 241
10-1.46 AGGREGATE BASE 242
10-1.47 CEMENT TREATED BASE 242
10-1.48 TREATED PERMEABLE BASE 243
10-1.49 ASPHALT CONCRETE 243
10-1.50 ASPHALT CONCRETE (MISCELLANEOUS AREAS) 244
10-1.51 CONCRETE PAVEMENT 244
10-1.52 PILING 252
GENERAL 252
CAST-IN-DRILLED-HOLE CONCRETE PILES 252
MEASUREMENT AND PAYMENT (PILING) 262
10-1.53 PRESTRESSING CONCRETE 262
10-1.54 CONCRETE STRUCTURES 262
FALSEWORK 263
COST REDUCTION INCENTIVE PROPOSALS FOR CAST-IN-PLACE PRESTRESSED BOX GIRDER BRIDGES 264
DECK CLOSURE POURS 265
SLIDING JOINTS 265
SLIDING BEARINGS 265
ELASTOMERIC BEARING PADS 266
DECK CRACK TREATMENT 266
PRECAST PRESTRESSED CONCRETE BRIDGE MEMBERS 268
MEASUREMENT AND PAYMENT 269
10-1.55 STRUCTURE APPROACH SLABS (TYPE N) 269
GENERAL 269
STRUCTURE APPROACH DRAINAGE SYSTEM 269
ENGINEERING FABRICS 270
TREATED PERMEABLE BASE UNDER APPROACH SLAB 270
APPROACH SLABS 271
JOINTS 271
MEASUREMENT AND PAYMENT 272
10-1.56 STRUCTURE APPROACH SLABS (TYPE R) 272
GENERAL 272

TEMPORARY ROADWAY STRUCTURAL SECTION....272
REMOVING PORTIONS OF EXISTING STRUCTURES....273
REMOVING EXISTING PAVEMENT AND BASE MATERIALS....273
AGGREGATE BASE (APPROACH SLAB)....273
STRUCTURE APPROACH SLAB....273
JOINTS....275
MEASUREMENT AND PAYMENT....275
10-1.57 PAVING NOTCH EXTENSION....275
10-1.58 SOUND WALL....276
DESCRIPTION....276
SOUND WALL (MASONRY BLOCK)....276
ACCESS GATES....277
MEASUREMENT AND PAYMENT....278
10-1.59 DRILL AND BOND DOWEL (EPOXY CARTRIDGE)....278
10-1.60 DRILL AND BOND DOWELS....279
10-1.61 CORE CONCRETE....279
10-1.62 SEALING JOINTS....279
10-1.63 ARCHITECTURAL SURFACE (TEXTURED CONCRETE)....280
TEST PANEL....280
FORM LINERS....280
RELEASING FORM LINERS....281
CURING....281
MEASUREMENT AND PAYMENT....281
10-1.64 REINFORCEMENT....281
MEASUREMENT AND PAYMENT....281
10-1.65 HEADED BAR REINFORCEMENT....282
GENERAL....282
PRODUCTION TESTS....282
MEASUREMENT AND PAYMENT....283
10-1.66 TREAT BRIDGE DECKS....283
MATERIALS....284
TESTING....285
CONSTRUCTION....285
MEASUREMENT AND PAYMENT....285
10-1.67 SIGN STRUCTURES....286
10-1.68 ROADSIDE SIGNS....287
10-1.69 INSTALL FRAMED SIGN PANEL....287
10-1.70 INSTALL SIGN OVERLAY....287
10-1.71 CLEAN AND PAINT STRUCTURAL STEEL....287
CLEANING....288
PAINTING....288
MEASUREMENT AND PAYMENT....289
10-1.72 ALTERNATIVE PIPE....289
SPIRAL RIB PIPE....289
10-1.73 PLASTIC PIPE....289
10-1.74 REINFORCED CONCRETE PIPE....289
10-1.75 JACKED REINFORCED CONCRETE PIPE....290
10-1.76 CORRUGATED METAL PIPE....290
10-1.77 UNDERDRAIN....290
10-1.78 EDGE DRAIN....290
10-1.79 PERMEABLE MATERIAL (BLANKET)....291
10-1.80 OVERSIDE DRAIN....291
10-1.81 MISCELLANEOUS FACILITIES....292
10-1.82 WELDED STEEL PIPE CASING (BRIDGE)....292
WORKING DRAWINGS....292
MATERIALS....292
CONSTRUCTION....292
MEASUREMENT AND PAYMENT....293
10-1.83 AUTOMATIC DRAINAGE GATE....293

10-1.84 PVC WATERLINE 293
GENERAL 293
PRESSURE TESTING 293
MEASUREMENT AND PAYMENT 293
10-1.85 REINFORCED CONCRETE PIPE CASING 293
10-1.86 VITRIFIED CLAY PIPE 294
MATERIALS 294
LAYING PIPE 294
FIELD JOINING OF PIPE 294
JOINTS 294
TEMPORARY DIVERSION SYSTEM 295
TESTS 295
TELEVISION INSPECTION 295
MEASUREMENT AND PAYMENT 296
10-1.87 SLOPE PROTECTION 296
10-1.88 SLOPE PAVING 296
10-1.89 MINOR CONCRETE (GUTTER) 297
10-1.90 MISCELLANEOUS CONCRETE CONSTRUCTION 298
10-1.91 MINOR CONCRETE (BACKFILL) 298
MEASUREMENT AND PAYMENT 298
10-1.92 MISCELLANEOUS IRON AND STEEL 298
10-1.93 MISCELLANEOUS METAL (BRIDGE) 298
10-1.94 MISCELLANEOUS METAL (RESTRAINER-PIPE TYPE) 298
10-1.95 MISCELLANEOUS METAL (RESTRAINER-BAR TYPE) 299
10-1.96 CHAIN LINK FENCE 299
10-1.97 CHAIN LINK WALK GATE 299
10-1.98 SECURITY FENCE AND GATE 300
10-1.99 MARKERS 300
10-1.100 METAL BEAM GUARD RAILING 300
TERMINAL SYSTEM (TYPE SRT) 300
10-1.101 CHAIN LINK RAILING 301
10-1.102 CONCRETE BARRIER 301
10-1.103 CRASH CUSHION (ADIEM) 301
10-1.104 CRASH CUSHION (QUADGUARD) 302
10-1.105 THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING 303
10-1.106 PAINT PAVEMENT MARKING 303
10-1.107 PAVEMENT MARKERS 303
SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS 303
10-2.01 GENERAL 303
PROGRESS INSPECTIONS 304
10-2.02 EXISTING HIGHWAY PLANTING 304
MAINTAIN EXISTING PLANTED AREAS 304
10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES 305
LOCATE EXISTING CROSSOVERS AND CONDUITS 305
MEASUREMENT AND PAYMENT 305
CHECK AND TEST EXISTING IRRIGATION FACILITIES 305
MAINTAIN EXISTING IRRIGATION FACILITIES 305
REMOVE EXISTING IRRIGATION FACILITIES 306
PESTICIDES 306
SECTION 10-3. SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS 307
10-3.01 DESCRIPTION 307
10-3.02 COST BREAK-DOWN 307
10-3.03 EQUIPMENT LIST AND DRAWINGS 308
10-3.04 MAINTAINING EXISTING AND TEMPORARY ELECTRICAL SYSTEMS 308
10-3.05 FOUNDATIONS 308
10-3.06 STANDARDS, STEEL PEDESTALS AND POSTS 308
10-3.07 CONDUIT 308
10-3.08 PULL BOXES 309
10-3.09 CONDUCTORS AND WIRING 309

TELEPHONE CABLE 309
10-3.10 BONDING AND GROUNDING 310
10-3.11 SERVICE 310
10-3.12 SIGN DISCONNECTS 310
10-3.13 NUMBERING ELECTRICAL EQUIPMENT 310
10-3.14 VEHICLE SIGNAL FACES AND SIGNAL HEADS 310
10-3.15 PEDESTRIAN SIGNALS 310
10-3.16 PROGRAMMED VISIBILITY VEHICLE TRAFFIC SIGNAL HEADS 310
10-3.17 DETECTORS 311
10-3.18 LONG LEAD-IN LOOP DETECTOR (LLLD) 311
10-3.19 LUMINAIRES 311
10-3.20 SOFFIT AND WALL LUMINAIRES 311
10-3.21 INTERNALLY ILLUMINATED SIGNS 312
10-3.22 VIDEO IMAGE PROCESSING SYSTEM 312
HARDWARE 312
FUNCTIONAL CAPABILITIES 312
IMAGE SENSOR: 313
MODEL 282 - ADAPTER 313
SPECIFICATIONS 313
COAXIAL CABLE CONNECTORS 317
TESTING 317
INSTALLATION AND TRAINING 318
WARRANTY 318
10-3.23 ABBREVIATIONS 318
10-3.24 CITY OF SAN JOSE ELECTRICAL SPECIAL PROVISIONS 318
MAINTAINING EXISTING CITY TRAFFIC SIGNAL AND STREET LIGHTING SYSTEMS 318
REGULATIONS AND CODE 318
EQUIPMENT LIST AND DRAWINGS 318
MAINTAINING EXISTING AND TEMPORARY ELECTRICAL SYSTEMS 318
SCHEDULING OF WORK 319
INSPECTION 319
EXCAVATION AND BACKFILLING 319
REMOVING AND REPLACING IMPROVEMENTS 319
FOUNDATIONS 319
STANDARDS, STEEL PEDESTAL AND POSTS 320
SIGNAL STANDARDS 321
CONDUIT 321
BONDING AND GROUNDING 329
SERVICE 329
PAINTING 330
CONTROLLER ASSEMBLIES 330
TYPE 'P' CABINET SPECIFICATIONS 331
SUB-ASSEMBLIES 331
SYSTEM INTERFACE TERMINATION PANEL SPECIFICATIONS 336
CONSTRUCTION 337
SIGNAL CONTROLLER SPECIFICATIONS 337
TRAFFIC SIGNAL FACES AND FITTINGS 338
DETECTORS 340
LIGHTING 341
10-3.25 REMOVING, REINSTALLING OR SALVAGING ELECTRICAL EQUIPMENT 343
10-3.26 PAYMENT 343
10-3.27 REMOVING, REINSTALLING OR SALVAGING ELECTRICAL EQUIPMENT 344
SECTION 11. MODIFIED STANDARD SPECIFICATION SECTIONS 344
SECTION 11-1. QUALITY CONTROL / QUALITY ASSURANCE 344
SECTION 39: ASPHALT CONCRETE 344
39-1 GENERAL 344
39-1.01 DESCRIPTION 344
39-2 MATERIALS 344
39-2.01 ASPHALTS 344

39-2.02 AGGREGATE 345
39-2.03 ASPHALT CONCRETE MIXTURE 346
39-2.04 PAVEMENT REINFORCING FABRIC 347
39-3 ASPHALT CONCRETE MIX DESIGN PROPOSAL AND REVIEW 347
39-3.01 CONTRACTOR MIX DESIGN PROPOSAL 347
39-3.02 ENGINEER REVIEW OF ASPHALT CONCRETE MIX DESIGN 347
39-4 CONTRACTOR QUALITY CONTROL 348
39-4.01 GENERAL 348
39-4.02 QUALITY CONTROL PLAN 348
39-4.03 CONTRACTOR QUALITY CONTROL INSPECTION, SAMPLING, AND TESTING 349
39-4.04 CONTRACTOR PROCESS CONTROL 349
39-4.05 CONTRACTOR QUALITY CONTROL 350
39-4.06 CHARTS AND RECORDS 351
39-4.06A Compliance Charts 351
39-4.06B Records of Inspection and Testing 351
39-5 ENGINEER QUALITY ASSURANCE 352
39-5.01 GENERAL 352
39-5.02 SAMPLING AND TESTING FOR VERIFICATION 352
39-5.03 VERIFICATION 353
39-6 DISPUTE RESOLUTION 354
39-6.01 GENERAL 354
39-6.02 DURING THE ASPHALT CONCRETE MIX DESIGN REVIEW 355
39-6.03 DURING THE PRODUCTION START-UP EVALUATION 355
39-6.04 DURING PRODUCTION 355
39-7 STORING, PROPORTIONING AND MIXING MATERIALS 356
39-7.01 STORAGE 356
39-7.01A Aggregate Cold Storage 356
39-7.01B Aggregate Hot Storage 356
39-7.01C Asphalt Binder Storage 356
39-7.02 DRYING 357
39-7.03 PROPORTIONING 357
39-7.03A Proportioning for Batch Mixing 357
39-7.03B Proportioning for Continuous Mixing 358
39-7.04 (BLANK) 359
39-7.05 MIXING 359
39-7.05A Batch Mixing 359
39-7.05B Continuous Mixing 359
39-7.06 ASPHALT CONCRETE STORAGE 360
39-7.07 ASPHALT CONCRETE PLANTS 360
39-8 SUBGRADE, PRIME COAT, PAINT BINDER (TACK COAT), AND PAVEMENT REINFORCING FABRIC 360
39-8.01 SUBGRADE 360
39-8.02 PRIME COAT AND PAINT BINDER (TACK COAT) 360
39-8.03 PAVEMENT REINFORCING FABRIC 361
39-9 SPREADING AND COMPACTING EQUIPMENT 361
39-9.01 SPREADING EQUIPMENT 361
39-9.02 COMPACTING EQUIPMENT 362
39-10 SPREADING AND COMPACTING 362
39-10.01 GENERAL REQUIREMENTS 362
39-10.02 PRODUCTION START-UP EVALUATION AND NUCLEAR DENSITY TEST STRIPS 363
39-10.02A Production Start-Up Evaluation 363
39-10.02B Nuclear Density Test Strip 364
39-10.03 SPREADING 364
39-10.04 COMPACTING 365
39-11 ACCEPTANCE OF WORK 365
39-11.01 GENERAL 365
39-11.02 STATISTICAL EVALUATION AND DETERMINATION OF PAY FACTOR 366
39-11.02A General 366
39-11.02B Statistical Evaluation 366

39-11.02C Pay Factor Determination and Compensation Adjustment 368
39-12 MEASUREMENT AND PAYMENT 372
39-12.01 MEASUREMENT 372
39-12.02 PAYMENT 373
SECTION 12. (BLANK) 374
SECTION 13. RELATIONS WITH RAILROAD 374
13-1.0101 GENERAL 374
SECTION 14 FEDERAL REQUIREMENTS FOR FEDERAL-AID CONSTRUCTION PROJECTS 375
FEDERAL REQUIREMENT TRAINING SPECIAL PROVISIONS 394

STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Abbreviations
A10B	Symbols
A20A	Pavement Markers and Traffic Lines, Typical Details
A20B	Pavement Markers and Traffic Lines, Typical Details
A20C	Pavement Markers and Traffic Lines, Typical Details
A20D	Pavement Markers and Traffic Lines, Typical Details
A24A	Pavement Markings - Arrows
A24B	Pavement Markings - Arrows
A24C	Pavement Markings - Symbols and Numerals
A24D	Pavement Markings - Words
A24E	Pavement Markings - Words and Crosswalks
RSP A35A	Portland Cement Concrete Pavement (Undoweled Transverse Joints)
RSP A35B	Portland Cement Concrete Pavement (Doweled Transverse Joints)
A35C	Portland Cement Concrete Pavement Joint and End Anchor Details
NSP A35D	Dowel Bar Retrofit In Existing Concrete Pavement (Longitudinal Joints Coincide With Laneline Pavement Delineation)
A62A	Excavation and Backfill - Miscellaneous Details
A62B	Limits of Payment for Excavation and Backfill - Bridge Surcharge and Wall
A62C	Limits of Payment for Excavation and Backfill - Bridge
A62D	Excavation and Backfill - Concrete Pipe Culverts
RSP A62DA	Excavation and Backfill - Concrete Pipe Culverts
A62F	Excavation and Backfill - Metal and Plastic Culverts
A73A	Object Markers
A73B	Markers
RSP A73C	Delineators, Channelizers and Barricades
A76A	Concrete Barrier Type 60
A76B	Concrete Barrier Type 60
A76C	Concrete Barrier Type 60E
A77A	Metal Beam Guard Railing – Typical Wood Post With Wood Block
A77B	Metal Beam Guard Railing - Standard Hardware
A77C	Metal Beam Guard Railing – Wood Post and Wood Block Details
A77D	Metal Beam Guard Railing – Typical Layouts
A77E	Metal Beam Guard Railing – Typical Layouts
A77F	Metal Beam Guard Railing – Typical Embankment Widening for End Treatments
A77H	Metal Beam Guard Railing - Anchor Cable and Anchor Plate Details
A77J	Metal Beam Guard Railing Connections to Bridge Railings, Retaining Walls and Abutments
RSP A77L	Metal Beam Guard Railing and Single Faced Barrier Railing Terminal System - End Treatments

A82B	Crash Cushion (Type ADIEM)
A85	Chain Link Fence
A87	Curbs, Dikes and Driveways
A88A	Curb Ramp Details
A88B	Curb Ramp Details
D73	Drainage Inlets
D74A	Drainage Inlets
D74C	Drainage Inlet Details
D77A	Grate Details
D77B	Bicycle Proof Grate Details
D78	Gutter Depressions
D87A	Corrugated Metal Pipe Downdrain Details
D88	Construction Loads On Culverts
D94A	Metal and Plastic Flared End Sections
D94B	Concrete Flared End Sections
D97A	Corrugated Metal Pipe Coupling Details No. 1 - Annular Coupling Band Bar and Strap and Angle Connectors
D97B	Corrugated Metal Pipe Coupling Details No. 2 - Hat Band Coupler and Flange Details
D97C	Corrugated Metal Pipe Coupling Details No. 3 - Helical and Universal Couplers
D97D	Corrugated Metal Pipe Coupling Details No. 4 - Hugger Coupling Bands
D97E	Corrugated Metal Pipe Coupling Details No. 5 - Standard Joint
D97F	Corrugated Metal Pipe Coupling Details No. 6 - Positive Joint
D97G	Corrugated Metal Pipe Coupling Details No. 7 - Positive Joints and Downdrains
D97H	Reinforced Concrete Pipe or Non-Reinforced Concrete Pipe - Standard and Positive Joints
D98A	Slotted Corrugated Steel Pipe Drain Details
D98B	Slotted Corrugated Steel Pipe Drain Details
D99B	Edge Drain Outlet and Vent Details
D99C	Edge Drain Cleanout and Vent Details
D102	Underdrains
H1	Planting and Irrigation - Abbreviations
H2	Planting and Irrigation - Symbols
H8	Planting and Irrigation Details
T1A	Temporary Crash Cushion, Sand Filled (Unidirectional)
RSP T2	Temporary Crash Cushion, Sand Filled (Shoulder Installations)
T3	Temporary Railing (Type K)
T7	Construction Project Funding Identification Signs
T10	Traffic Control System for Lane Closure On Freeways and Expressways
T10A	Traffic Control System for Lane and Complete Closures On Freeways and Expressways
T11	Traffic Control System for Lane Closure On Multilane Conventional Highways
T13	Traffic Control System for Lane Closure On Two Lane Conventional Highways
T14	Traffic Control System for Ramp Closure
T15	Traffic Control System for Moving Lane Closure On Multilane Highways
T16	Traffic Control System for Moving Lane Closure On Multilane Highways
B0-1	Bridge Details
RSP B0-3	Bridge Details
B0-5	Bridge Details
B0-13	Bridge Details
B2-5	Pile Details-Class 400 and Class 625
B2-6	Pile Details-Class 400C and Class 625C
B2-8	Pile Details-Class 900 and Class 900C
RSP B3-1	Retaining Wall Type 1 - H=1200 Through 9100 mm
RSP B3-7	Retaining Wall Type 5
RSP B3-8	Retaining Wall Details No. 1
B3-9	Retaining Wall Details No. 2
B6-21	Joint Seals (Maximum Movement Rating = 50 mm)
B7-1	Box Girder Details

B7-10	Utility Opening - Box Girder
B8-5	Cast-in-Place Prestressed Girder Details
B11-47	Cable Railing
RSP B11-53	Concrete Barrier Type 25
RS1	Roadside Signs, Typical Installation Details No. 1
RS2	Roadside Signs - Wood Post, Typical Installation Details No. 2
RS3	Roadside Signs - Laminated Wood Box Post Typical Installation Details No. 3
RS4	Roadside Signs, Typical Installation Details No. 4
RSP S1	Overhead Signs - Truss, Instructions and Examples
RSP S2	Overhead Signs - Truss, Single Post Type - Post Types II Thru VII
S4	Overhead Signs - Truss, Single Post Type - Structural Frame Members
RSP S5	Overhead Signs - Truss Two Post Type - Structural Frame Members
RSP S6	Overhead Signs - Truss, Structural Frame Details
RSP S7	Overhead Signs -Truss, Frame Juncture Details
RSP S8A	Overhead Signs - Steel Frames - Removable Sign Panel Frames
S8B	Overhead Signs - Removable Sign Panel Frames - Overhead Formed Panel Mounting Details
S8D	Overhead Signs - Truss, Removable Sign Panel Frames - 2794 mm and 3048 mm Sign Panels
S9	Overhead Signs - Walkway Details No. 1
S10	Overhead Signs - Walkway Details No. 2
RSP S11	Overhead Signs - Walkway Safety Railing Details
RSP S13	Overhead Signs - Truss, Pile Foundation
ES-1A	Signal, Lighting and Electrical Systems - Symbols and Abbreviations
ES-1B	Signal, Lighting and Electrical Systems - Symbols and Abbreviations
ES-2A	Signal, Lighting and Electrical Systems - Service Equipment
ES-2C	Signal, Lighting and Electrical Systems - Service Equipment Notes, Type III Series
ES-2D	Signal, Lighting and Electrical Systems - Service Equipment and Typical Wiring Diagram Type III-A Series
ES-3A	Signal, Lighting and Electrical Systems - Controller Cabinet Details
ES-3C	Signal, Lighting and Electrical Systems - Controller Cabinet Details
ES-3F	Signal, Lighting and Electrical Systems - Telephone Demarcation Cabinet Details, Type C
ES-3G	Signal, Lighting and Electrical Systems – Telephone Demarcation Cabinet, Type C Details
ES-4A	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-4B	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-4C	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-4D	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-4E	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-5A	Signal, Lighting and Electrical Systems - Detectors
ES-5B	Signal, Lighting and Electrical Systems - Detectors
ES-5E	Signal, Lighting and Electrical Systems - Detectors
RSP ES-6A	Lighting Standards - Types 15, 21 and 22
RSP ES-6B	Lighting Standards - Types 15 AND 21, Barrier Rail Mounted Details
ES-6E	Lighting Standards - Types 30 and 31
RSP ES-6F	Lighting Standards - Type 30 and 31 Base Plate Details
ES-7B	Signal and Lighting Standards - Type 1 Standards and Equipment Numbering
ES-7F	Signal and Lighting Standards - Case 4 Arm Loading, Wind Velocity = 129 km/h, Arm Lengths 7.6 m to 13.7 m
ES-7G	Signal and Lighting Standards - Case 5 Arm Loading, Wind Velocity = 129 km/h, Arm Lengths 15.2 m to 16.8 m
ES-7M	Signal and Lighting Standards - Details No. 1
ES-7N	Signal and Lighting Standards - Details No. 2
ES-8	Signal, Lighting and Electrical Systems - Pull Box Details
ES-9A	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9B	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9C	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9E	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations

ES-9F	Signal, Lighting and Electrical Systems - Flush Soffit Luminaire Modification Details, Structure Installations
ES-10	Signal, Lighting and Electrical Systems - Isolux Diagrams
ES-11	Signal, Lighting and Electrical Systems - Foundation Installations
ES-13A	Signal, Lighting and Electrical Systems - Splicing Details
ES-13B	Signal, Lighting and Electrical Systems - Wiring Details and Fuse Ratings
ES-15A	Sign Illumination - Mercury Vapor Sign Illumination Equipment
ES-15C	Sign Illumination - Sign Illumination Equipment
ES-15D	Sign Illumination - Sign Illumination Control

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

CONTRACT NO. 04-4396U4

04-SCl-87-1.6/8.1

Sealed proposals for the work shown on the plans entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR CONSTRUCTION ON STATE HIGHWAY IN SANTA CLARA COUNTY IN SAN JOSE FROM 0.4 KM NORTH OF BRAHNAM LANE OVER CROSSING TO 0.4 KM NORTH OF VIRGINIA STREET OVERCROSSING

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on September 28, 2004, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR CONSTRUCTION ON STATE HIGHWAY IN SANTA CLARA COUNTY IN SAN JOSE FROM 0.4 KM NORTH OF BRAHNAM LANE OVER CROSSING TO 0.4 KM NORTH OF VIRGINIA STREETOVER CROSSING

General work description: Rehabilitation of the pavement and bridge repair.

This project has a goal of 12 percent disadvantaged business enterprise (DBE) participation.

No prebid meeting is scheduled for this project.

THIS PROJECT IS SUBJECT TO THE "BUY AMERICA" PROVISIONS OF THE SURFACE TRANSPORTATION ASSISTANCE ACT OF 1982 AS AMENDED BY THE INTERMODAL SURFACE TRANSPORTATION EFFICIENCY ACT OF 1991.

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A license or a combination of Class C licenses which constitutes a majority of the work.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

Inquiries or questions based on alleged patent ambiguity of the plans, specifications or estimate must be communicated as a bidder inquiry prior to bid opening. Any such inquiries or questions, submitted after bid opening, will not be treated as a bid protest.

Bidder inquiries may be made as follows:

The Department will consider bidder inquiries only when a completed "Bidder Inquiry" form is submitted. A copy of the "Bidder Inquiry" form is available at the Internet address shown below. The bidder inquiry shall include the bidder's name and telephone number. Submit "Bidder Inquiry" forms to :

Construction Program Duty Senior
111 Grand Avenue
Oakland, CA 94612

Fax Number: (510) 622-1805
E-mail: DUTY_SENIOR_DISTRICT04@dot.ca.gov
Tel. Number: (510) 286-5209

To expedite processing, submittal of "Bidder Inquiry" forms via Fax or E-mail is preferred.

To the extent feasible and at the discretion of the Department, completed "Bidder Inquiry" forms submitted for consideration will be investigated, and responses will be posted on the Internet at:

http://www.dot.ca.gov/hq/esc/oe/project_status/bid_inq.html

The responses to bidders' inquiries, unless incorporated into formal addenda to the contract, are not a part of the contract, and are provided for the bidder's convenience only. In some instances, the question and answer may represent a summary of the matters discussed rather than a word-for-word recitation. The availability or use of information provided in the responses to bidders' inquiries is not to be construed in any way as a waiver of the provisions of Section 2-1.03 of the Standard Specifications or any other provision of the contract, the plans, Standard Specifications or Special Provisions, nor to excuse the contractor from full compliance with those contract requirements. Bidders are cautioned that subsequent responses or contract addenda may affect or vary a response previously given.

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

Cross sections for this project are available at the office of the District Director of Transportation of the district in which the work is situated in paper copy format.

The successful bidder shall furnish a payment bond and a performance bond.

The Department of Transportation hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full opportunity to submit bids in response to this invitation.

The U.S. Department of Transportation (DOT) provides a toll-free "hotline" service to report bid rigging activities. Bid rigging activities can be reported Mondays through Fridays, between 8:00 a.m. and 5:00 p.m., eastern time, Telephone No. 1-800-424-9071. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report these activities. The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' internet web site at: http://www.dir.ca.gov. The Federal minimum wage rates for this project as predetermined by the United States Secretary of Labor are available through the California Department of Transportation's Electronic Project Document Distribution Site on the internet at http://hqidoc1.dot.ca.gov/. Addenda to modify the Federal minimum wage rates, if necessary, will be issued to holders of "Proposal and Contract" books. Future effective general prevailing wage rates which have been predetermined and are on file with the California Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

If there is a difference between the minimum wage rates predetermined by the United States Secretary of Labor and the general prevailing wage rates determined by the Director of the California Department of Industrial Relations for similar classifications of labor, the Contractor and subcontractors shall pay not less than the higher wage rate. The Department will not accept lower State wage rates not specifically included in the Federal minimum wage determinations. This includes "helper" (or other classifications based on hours of experience) or any other classification not appearing in the Federal wage determinations. Where Federal wage determinations do not contain the State wage rate determination otherwise available for use by the Contractor and subcontractors, the Contractor and subcontractors shall pay not less than the Federal minimum wage rate which most closely approximates the duties of the employees in question.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated August 2, 2004

REG

COPY OF ENGINEER'S ESTIMATE

(NOT TO BE USED FOR BIDDING PURPOSES)

04-4396U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
1	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM
2	070018	TIME-RELATED OVERHEAD	WDAY	440
3	071325	TEMPORARY FENCE (TYPE ESA)	M	65
4	073028	450 MM TEMPORARY CULVERT	M	53
5	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM
6	074020	WATER POLLUTION CONTROL	LS	LUMP SUM
7	074020	TEMPORARY DRAINAGE INLET PROTECTION	EA	350
8	074020	TEMPORARY EROSION CONTROL	M2	14 000
9	074020	TEMPORARY INLET	EA	2
10	074029	TEMPORARY SILT FENCE	M	6000
11	074032	TEMPORARY CONCRETE WASHOUT FACILITY	EA	12
12	074033	TEMPORARY CONSTRUCTION ENTRANCE	EA	15
13	074034	TEMPORARY COVER	M2	6250
14	074034	FISH FRIENDLY DIVERSION	LS	LUMP SUM
15 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
16 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
17	120149	TEMPORARY PAVEMENT MARKING (PAINT)	M2	31
18	120159	TEMPORARY TRAFFIC STRIPE (PAINT)	M	60 500
19	120165	CHANNELIZER (SURFACE MOUNTED)	EA	340
20	120300	TEMPORARY PAVEMENT MARKER	EA	12 600

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
21 (S)	128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	23
22	129000	TEMPORARY RAILING (TYPE K)	M	26 555
23	129100	TEMPORARY CRASH CUSHION MODULE	EA	570
24	150206	ABANDON CULVERT	EA	4
25	150206	ABANDON RISER	EA	9
26	150206	ABANDON PIEZOMETER	EA	10
27	150605	REMOVE SECURITY FENCE	M	22
28	150608	REMOVE CHAIN LINK FENCE	M	1780
29	150668	REMOVE FLARED END SECTION	EA	1
30	150701	REMOVE YELLOW PAINTED TRAFFIC STRIPE	M	27 100
31	150711	REMOVE PAINTED TRAFFIC STRIPE	M	24 400
32	150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	M	4220
33	150722	REMOVE PAVEMENT MARKER	EA	12 300
34	150742	REMOVE ROADSIDE SIGN	EA	25
35	150760	REMOVE SIGN STRUCTURE	EA	8
36	150763	REMOVE FRAMED SIGN PANEL	EA	13
37	150771	REMOVE ASPHALT CONCRETE DIKE	M	410
38	150800	REMOVE 40 MM PVC WATERLINE	M	30
39	150805	REMOVE CULVERT	M	1410
40	150805	REMOVE UNDERDRAIN	M	1710

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
41	150820	REMOVE INLET	EA	49
42	150821	REMOVE HEADWALL	EA	1
43	150826	REMOVE MANHOLE	EA	1
44	150841	REMOVE 750 MM VCP SEWER PIPE	M	48
45	150846	REMOVE CONCRETE PAVEMENT	M2	410
46	150860	REMOVE BASE AND SURFACING	M3	36
47	151272	SALVAGE METAL BEAM GUARD RAILING	M	1970
48	151538	RECONSTRUCT CHAIN LINK RAILING	M	56
49	152430	ADJUST INLET	EA	32
50	152659	990 MM PLASTIC PIPE LINER (SDR = 32.5)	M	700
51	152659	450 MM CURED IN PLACE PIPE	M	380
52	152659	600 MM CURED IN PLACE PIPE	M	280
53	152659	750 MM CURED IN PLACE PIPE	M	140
54	152659	1350 MM CURED IN PLACE PIPE	M	110
55 (S)	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	M2	16 300
56	153210	REMOVE CONCRETE	M3	110
57	153221	REMOVE CONCRETE BARRIER	M	2680
58	153221	REMOVE SLOPE PROTECTION (ROCK)	M3	235
59	153221	REMOVE SLOPE PROTECTION (SACKED CONCRETE)	M3	77
60	153235	CLEAN BRIDGE DECK	M2	6330

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
61	153300	REMOVE AUTOMATIC DRAINAGE GATE	EA	1
62	153300	CLEANOUT EXISTING DRAINAGE FACILITY	EA	2
63	153531	ACCESS OPENING, SOFFIT	EA	4
64	156590	REMOVE CRASH CUSHION (SAND FILLED)	EA	1
65	157561	BRIDGE REMOVAL (PORTION), LOCATION A	LS	LUMP SUM
66	157562	BRIDGE REMOVAL (PORTION), LOCATION B	LS	LUMP SUM
67	157563	BRIDGE REMOVAL (PORTION), LOCATION C	LS	LUMP SUM
68	157564	BRIDGE REMOVAL (PORTION), LOCATION D	LS	LUMP SUM
69	157565	BRIDGE REMOVAL (PORTION), LOCATION E	LS	LUMP SUM
70	157566	BRIDGE REMOVAL (PORTION), LOCATION F	LS	LUMP SUM
71	157567	BRIDGE REMOVAL (PORTION), LOCATION G	LS	LUMP SUM
72	157568	BRIDGE REMOVAL (PORTION), LOCATION H	LS	LUMP SUM
73	157569	BRIDGE REMOVAL (PORTION), LOCATION I	LS	LUMP SUM
74	157570	BRIDGE REMOVAL (PORTION), LOCATION J	LS	LUMP SUM
75	157571	BRIDGE REMOVAL (PORTION), LOCATION K	LS	LUMP SUM
76	157572	BRIDGE REMOVAL (PORTION), LOCATION L	LS	LUMP SUM
77	160101	CLEARING AND GRUBBING	LS	LUMP SUM
78	170101	DEVELOP WATER SUPPLY	LS	LUMP SUM
79	190101	ROADWAY EXCAVATION	M3	82 500
80	190101	ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS) (RESTRICTED)	M3	21 200

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
81	190101	ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS) (HAZARDOUS)	M3	4900
82	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM
83	190110	ASBESTOS HEALTH AND SAFETY	LS	LUMP SUM
84	190140	DEWATERING	LS	LUMP SUM
85	192003	STRUCTURE EXCAVATION (BRIDGE)	M3	921
86	192008	STRUCTURE EXCAVATION (TYPE A)	M3	104
87	192037	STRUCTURE EXCAVATION (RETAINING WALL)	M3	13 977
88	193003	STRUCTURE BACKFILL (BRIDGE)	M3	734
89	193013	STRUCTURE BACKFILL (RETAINING WALL)	M3	14 115
90	193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	M3	924
91	193114	SAND BACKFILL	M3	32
92	193114	GROUT BACKFILL	M3	25
93	193114	COMPACTION GROUTING	M3	2900
94	194001	DITCH EXCAVATION	M3	5
95	198100	LIGHTWEIGHT EMBANKMENT MATERIAL (CELLULAR CONCRETE)	M3	15 400
96 (S)	203001	EROSION CONTROL (BLANKET)	M2	1640
97 (S)	203003	STRAW (EROSION CONTROL)	TONN	11
98	203014	FIBER (EROSION CONTROL)	KG	1590
99	203021	FIBER ROLLS	M	3710
100	203026	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	2

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
101 (S)	203040	SEED (EROSION CONTROL)	KG	110
102 (S)	203040	COMPOST (EROSION CONTROL)	KG	4790
103 (S)	203040	STABILIZING EMULSION (EROSION CONTROL)	KG	360
104	204096	MAINTAIN EXISTING PLANTED AREAS	LS	LUMP SUM
105	204098	REMOVE EXISTING IRRIGATION FACILITIES	LS	LUMP SUM
106	206401	MAINTAIN EXISTING IRRIGATION FACILITIES	LS	LUMP SUM
107	208731	200 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	M	20
108	208798	200 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	64
109	208909	EXTEND 200 MM CONDUIT	M	24
110	250401	CLASS 4 AGGREGATE SUBBASE	M3	32 600
111	260301	CLASS 3 AGGREGATE BASE	M3	660
112	270011	CEMENT TREATED BASE	M3	13 100
113	290211	ASPHALT TREATED PERMEABLE BASE	M3	3680
114	390153	ASPHALT CONCRETE (TYPE A)	TONN	52 100
115	394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	M2	5050
116	394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	M	330
117	394042	PLACE ASPHALT CONCRETE DIKE (TYPE B)	M	180
118	394048	PLACE ASPHALT CONCRETE DIKE (TYPE E)	M	150
119	394049	PLACE ASPHALT CONCRETE DIKE (TYPE F)	M	19
120	395001	LIQUID ASPHALT, SC-70 (PRIME COAT)	TONN	5

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
121	401000	CONCRETE PAVEMENT	M3	370
122	404092	SEAL PAVEMENT JOINT	M	1110
123	490557	FURNISH STEEL PILING (HP 310 X 79)	M	105
124 (S)	490558	DRIVE STEEL PILE (HP 310 X 79)	M	4
125 (S)	490661	1.2 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	55
126 (S)	490663	1.5 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	93
127 (S)	490669	2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	61
128 (S)	490671	2.4 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	49
129 (S)	490675	900 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	158
130	490706	FURNISH PILING (CLASS 900C)	M	53
131 (S)	490707	DRIVE PILE (CLASS 900C)	EA	3
132	490753	FURNISH CONCRETE PILING (CLASS 625 MOD ALT "X")	M	299
133 (S)	490754	DRIVE CONCRETE PILE (CLASS 625 MOD ALT "X")	EA	15
134	490757	FURNISH PILING (CLASS 625C MODIFIED)	M	889
135 (S)	490758	DRIVE PILE (CLASS 625C MODIFIED)	EA	66
136	490759	FURNISH PILING (CLASS 400C MODIFIED)	M	24 899
137 (S)	490760	DRIVE PILE (CLASS 400C MODIFIED)	EA	1366
138	491013	FURNISH CONCRETE PILING (CLASS 400 MOD ALT "X")	M	222
139 (S)	491014	DRIVE CONCRETE PILE (CLASS 400 MOD ALT "X")	EA	15
140 (S)	498030	600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	M	880

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
141 (S)	500001	PRESTRESSING CAST-IN-PLACE CONCRETE	LS	LUMP SUM
142	510000	SEAL COURSE CONCRETE	M3	10
143	510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	M3	145
144	510053	STRUCTURAL CONCRETE, BRIDGE	M3	1521
145	510060	STRUCTURAL CONCRETE, RETAINING WALL	M3	5871
146	510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	M3	993
147	510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	M3	135
148 (S)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	333
149	510526	MINOR CONCRETE (BACKFILL)	M3	37
150	511063	FRACTURED FIN TEXTURE	M2	4766
151	511106	DRILL AND BOND DOWEL	M	310
152 (S)	512232	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (20 M - 25 M)	EA	6
153 (S)	512500	ERECT PRECAST PRESTRESSED CONCRETE GIRDER	EA	6
154 (S)	515076	CORE CONCRETE (201 MM - 250 MM)	M	4
155 (S)	515077	CORE CONCRETE (251 MM - 300 MM)	M	9
156 (S)	518002	SOUND WALL (MASONRY BLOCK)	M2	3140
157 (S)	519117	JOINT SEAL (MR 30 MM)	M	213
158 (S)	519142	JOINT SEAL (MR 40 MM)	M	116
159 (S)	519144	JOINT SEAL (MR 50 MM)	M	54
160 (S)	520102	BAR REINFORCING STEEL (BRIDGE)	KG	352 450

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
161	520103	BAR REINFORCING STEEL (RETAINING WALL)	KG	410 762
162	540102	TREAT BRIDGE DECK	M2	6330
163	540109	FURNISH BRIDGE DECK TREATMENT MATERIAL (LOW ODOR)	L	2534
164	560203	FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	KG	1360
165 (S)	560204	INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	KG	1360
166	560218	FURNISH SIGN STRUCTURE (TRUSS)	KG	45 900
167 (S)	560219	INSTALL SIGN STRUCTURE (TRUSS)	KG	45 900
168 (S)	561009	920 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	33
169	562002	METAL (BARRIER MOUNTED SIGN)	KG	1170
170	562004	METAL (RAIL MOUNTED SIGN)	KG	330
171	562004	METAL (SOUNDWALL MOUNTED SIGN)	KG	360
172	566011	ROADSIDE SIGN - ONE POST	EA	23
173	566012	ROADSIDE SIGN - TWO POST	EA	5
174	568001	INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	4
175	568007	INSTALL SIGN OVERLAY	M2	2
176	568021	INSTALL FRAMED SIGN PANEL	EA	13
177	620909	450 MM ALTERNATIVE PIPE CULVERT	M	1110
178	620913	600 MM ALTERNATIVE PIPE CULVERT	M	140
179	620924	900 MM ALTERNATIVE PIPE CULVERT	M	52
180	650069	450 MM REINFORCED CONCRETE PIPE	M	200

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
181	650075	600 MM REINFORCED CONCRETE PIPE	M	4
182	650077	750 MM REINFORCED CONCRETE PIPE	M	69
183	650084	1200 MM REINFORCED CONCRETE PIPE	M	46
184	655458	JACKED 450 MM REINFORCED CONCRETE PIPE (CLASS IV)	M	130
185	655459	JACKED 600 MM REINFORCED CONCRETE PIPE (CLASS IV)	M	160
186	664095	600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (1.32 MM THICK)	M	42
187	664103	750 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (1.32 MM THICK)	M	14
188	665832	450 MM BITUMINOUS COATED SLOTTED CORRUGATED STEEL PIPE (1.32 MM THICK)	M	980
189	680933	200 MM PERFORATED PLASTIC PIPE UNDERDRAIN	M	1780
190	681067	250 MM PERFORATED PLASTIC PIPE UNDERDRAIN	M	880
191	681134	80 MM PLASTIC PIPE (EDGE DRAIN)	M	5210
192	681137	80 MM PLASTIC PIPE (EDGE DRAIN OUTLET)	M	53
193	681140	80 MM PLASTIC PIPE (APPROACH SLAB DRAIN OUTLET)	M	140
194	682049	CLASS 3 PERMEABLE MATERIAL (BLANKET)	M3	6500
195	690275	450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN	M	200
196	692385	450 MM ANCHOR ASSEMBLY	EA	16
197	703450	WELDED STEEL PIPE CASING (BRIDGE)	M	23
198	705336	450 MM ALTERNATIVE FLARED END SECTION	EA	2
199	705567	750 MM AUTOMATIC DRAINAGE GATE	EA	1
200	707247	1220 MM PRECAST CONCRETE PIPE MANHOLE	M	21

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
201	710000	40 MM PVC WATERLINE	M	31
202	710000	300 MM REINFORCED CONCRETE PIPE CASING	M	10
203 (S)	714042	750 MM VITRIFIED CLAY PIPE	M	51
204	721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	M3	120
205	721024	ROCK SLOPE PROTECTION (1/4T, METHOD B)	M3	320
206	721410	CONCRETE (GUTTER LINING)	M3	80
207	721810	SLOPE PAVING (CONCRETE)	M3	169
208	721810	SLOPE PAVING (PRECAST PANEL)	M3	5
209	729010	ROCK SLOPE PROTECTION FABRIC	M2	490
210	731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	M3	120
211	731517	MINOR CONCRETE (GUTTER)	M	504
212	750001	MISCELLANEOUS IRON AND STEEL	KG	16 100
213 (S)	750496	MISCELLANEOUS METAL (RESTRAINER - PIPE TYPE)	KG	2950
214 (S)	750497	MISCELLANEOUS METAL (RESTRAINER - BAR TYPE)	KG	930
215 (S)	750501	MISCELLANEOUS METAL (BRIDGE)	KG	2970
216 (S)	750502	MISCELLANEOUS METAL (RETAINING WALL)	KG	244
217 (S)	800001	SECURITY FENCE	M	33
218 (S)	800002	SECURITY FENCE GATE	EA	1
219 (S)	800386	CHAIN LINK FENCE (TYPE CL-1.2, VINYL-CLAD)	M	1034
220 (S)	800386	CHAIN LINK FENCE (TYPE CL-1.2, BARRIER MOUNTED)	M	310

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
221	800390	CHAIN LINK FENCE (TYPE CL-1.5, VINYL-CLAD)	M	670
222 (S)	800391	CHAIN LINK FENCE (TYPE CL-1.8)	M	370
223 (S)	802584	0.9 M CHAIN LINK GATE (TYPE CL-1.8)	EA	9
224 (S)	802592	2.4 M CHAIN LINK GATE (TYPE CL-1.8)	EA	6
225 (S)	802595	3.0 M CHAIN LINK GATE (TYPE CL-1.8)	EA	1
226	820130	OBJECT MARKER	EA	11
227	832003	METAL BEAM GUARD RAILING (WOOD POST)	M	46
228 (S)	833032	CHAIN LINK RAILING (TYPE 7)	M	290
229	833125	CONCRETE BARRIER (TYPE 25)	M	39
230	833127	CONCRETE BARRIER (TYPE 25B)	M	620
231	833159	CONCRETE BARRIER (TYPE 27A MODIFIED)	M	1323
232	833160	CONCRETE BARRIER (TYPE 27)	M	23
233	833161	CONCRETE BARRIER (TYPE 27A)	M	441
234	833162	CONCRETE BARRIER (TYPE 27B)	M	110
235	833165	CONCRETE BARRIER (TYPE 27B MODIFIED)	M	42
236	833184	CONCRETE BARRIER (TYPE 27SV MODIFIED)	M	175
237	833187	CONCRETE BARRIER (TYPE 27 MODIFIED)	M	422
238	839481	CONCRETE BARRIER (TYPE 50)	M	2380
239	839487	CONCRETE BARRIER (TYPE 50C)	M	110
240	839490	CONCRETE BARRIER (TYPE 50G2)	M	5

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
241	839565	TERMINAL SYSTEM (TYPE SRT)	EA	6
242 (S)	839600	CRASH CUSHION (QUAD-GUARD)	EA	1
243 (S)	839603	CRASH CUSHION (ADIEM)	EA	1
244	839701	CONCRETE BARRIER (TYPE 60)	M	900
245	839702	CONCRETE BARRIER (TYPE 60A MODIFIED)	M	144
246	839703	CONCRETE BARRIER (TYPE 60C)	M	220
247	839704	CONCRETE BARRIER (TYPE 60D)	M	525
248	839705	CONCRETE BARRIER (TYPE 60E)	M	3
249 (S)	840515	THERMOPLASTIC PAVEMENT MARKING	M2	200
250 (S)	840561	100 MM THERMOPLASTIC TRAFFIC STRIPE	M	37 000
251 (S)	840563	200 MM THERMOPLASTIC TRAFFIC STRIPE	M	5720
252 (S)	840660	PAINT POSTMILE PARKING	M2	10
253 (S)	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	8440
254 (S)	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	4830
255 (S)	860300	SIGNAL AND LIGHTING (CITY STREET LOCATION 1)	LS	LUMP SUM
256 (S)	860402	LIGHTING (CITY STREET,LOCATION 1)	LS	LUMP SUM
257 (S)	860402	LIGHTING (CITY STREET,LOCATION 2)	LS	LUMP SUM
258 (S)	860402	LIGHTING (CITY STREET,LOCATION 3)	LS	LUMP SUM
259 (S)	860415	LIGHTING (STAGE CONSTRUCTION)	LS	LUMP SUM
260 (S)	860460	LIGHTING AND SIGN ILLUMINATION	LS	LUMP SUM

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
261 (S)	860700	POWER AND COMMUNICATION (VTA)	LS	LUMP SUM
262 (S)	860900	TRAFFIC OPERATION SYSTEMS	LS	LUMP SUM
263 (S)	860900	TRAFFIC OPERATION SYSTEMS (STAGE CONSTRUCTION)	LS	LUMP SUM
264 (S)	860900	TRAFFIC OPERATION SYSTEMS (COUNTY)	LS	LUMP SUM
265 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 1)	LS	LUMP SUM
266 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 2)	LS	LUMP SUM
267 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 3)	LS	LUMP SUM
268 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 4)	LS	LUMP SUM
269 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 5)	LS	LUMP SUM
270 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 6)	LS	LUMP SUM
271 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 7)	LS	LUMP SUM
272 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 8)	LS	LUMP SUM
273 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 9)	LS	LUMP SUM
274 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 10)	LS	LUMP SUM
275 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 11)	LS	LUMP SUM
276 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 12)	LS	LUMP SUM
277 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 13)	LS	LUMP SUM
278 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 14)	LS	LUMP SUM
279 (S)	860900	TRAFFIC OPERATION SYSTEMS (LOCATION 15)	LS	LUMP SUM
280	999990	MOBILIZATION	LS	LUMP SUM

STATE OF CALIFORNIA

DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISIONS

Annexed to Contract No. 04-4396U4

SECTION 1. SPECIFICATIONS AND PLANS

The work embraced herein shall conform to the provisions in the Standard Specifications dated July 1999, and the Standard Plans dated July 1999, of the Department of Transportation insofar as the same may apply, and these special provisions.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and shall be used in lieu of the conflicting portions.

AMENDMENTS TO JULY 1999 STANDARD SPECIFICATIONS

UPDATED March 25, 2004

Amendments to the Standard Specifications set forth in these special provisions shall be considered as part of the Standard Specifications for the purposes set forth in Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications and Special Provisions," of the Standard Specifications. Whenever either the term "Standard Specifications is amended" or the term "Standard Specifications are amended" is used in the special provisions, the text or table following the term shall be considered an amendment to the Standard Specifications. In case of conflict between such amendments and the Standard Specifications, the amendments shall take precedence over and be used in lieu of the conflicting portions.

SECTION 2: PROPOSAL REQUIREMENTS AND CONDITIONS

Issue Date: June 19, 2003

Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications is amended to read:

2-1.03 Examination of Plans, Specifications, Contract, and Site of Work

- The bidder shall examine carefully the site of the work contemplated, the plans and specifications, and the proposal and contract forms therefor. The submission of a bid shall be conclusive evidence that the bidder has investigated and is satisfied as to the general and local conditions to be encountered, as to the character, quality and scope of work to be performed, the quantities of materials to be furnished and as to the requirements of the proposal, plans, specifications and the contract.
- The submission of a bid shall also be conclusive evidence that the bidder is satisfied as to the character, quality and quantity of surface and subsurface materials or obstacles to be encountered insofar as this information was reasonably ascertainable from an inspection of the site and the records of exploratory work done by the Department as shown in the bid documents, as well as from the plans and specifications made a part of the contract.
- Where the Department has made investigations of site conditions including subsurface conditions in areas where work is to be performed under the contract, or in other areas, some of which may constitute possible local material sources, bidders or contractors may, upon written request, inspect the records of the Department as to those investigations subject to and upon the conditions hereinafter set forth.

• Where there has been prior construction by the Department or other public agencies within the project limits, records of the prior construction that are currently in the possession of the Department and which have been used by, or are known to, the designers and administrators of the project will be made available for inspection by bidders or contractors, upon written request, subject to the conditions hereinafter set forth. The records may include, but are not limited to, as-built drawings, design calculations, foundation and site studies, project reports and other data assembled in connection with the investigation, design, construction and maintenance of the prior projects.

• Inspection of the records of investigations and project records may be made at the office of the district in which the work is situated, or in the case of records of investigations related to structure work, at the Transportation Laboratory in Sacramento, California.

• When a log of test borings or other record of geotechnical data obtained by the Department's investigation of surface and subsurface conditions is included with the contract plans, it is furnished for the bidders' or Contractor's information and its use shall be subject to the conditions and limitations set forth in this Section 2-1.03.

• In some instances, information considered by the Department to be of possible interest to bidders or contractors has been compiled as "Materials Information." The use of the "Materials Information" shall be subject to the conditions and limitations set forth in this Section 2-1.03 and Section 6-2, "Local Materials."

• When cross sections are not included with the plans, but are available, bidders or contractors may inspect the cross sections and obtain copies for their use, at their expense.

• When cross sections are included with the contract plans, it is expressly understood and agreed that the cross sections do not constitute part of the contract, do not necessarily represent actual site conditions or show location, character, dimensions and details of work to be performed, and are included in the plans only for the convenience of bidders and their use is subject to the conditions and limitations set forth in this Section 2-1.03.

• When contour maps were used in the design of the project, the bidders may inspect those maps, and if available, they may obtain copies for their use.

• The availability or use of information described in this Section 2-1.03 is not to be construed in any way as a waiver of the provisions of the first paragraph in this Section 2-1.03 and bidders and contractors are cautioned to make independent investigations and examinations as they deem necessary to be satisfied as to conditions to be encountered in the performance of the work and, with respect to possible local material sources, the quality and quantity of material available from the property and the type and extent of processing that may be required in order to produce material conforming to the requirements of the specifications.

• The Department assumes no responsibility for conclusions or interpretations made by a bidder or contractor based on the information or data made available by the Department. The Department does not assume responsibility for representation made by its officers or agents before the execution of the contract concerning surface or subsurface conditions, unless that representation is expressly stated in the contract.

• No conclusions or interpretations made by a bidder or contractor from the information and data made available by the Department will relieve a bidder or contractor from properly fulfilling the terms of the contract.

SECTION 5: CONTROL OF WORK

Issue Date: December 31, 2001

Section 5-1.02A, "Trench Excavation Safety Plans," of the Standard Specifications is amended to read:

5-1.02A Excavation Safety Plans

• The Construction Safety Orders of the Division of Occupational Safety and Health shall apply to all excavations. For all excavations 1.5 m or more in depth, the Contractor shall submit to the Engineer a detailed plan showing the design and details of the protective systems to be provided for worker protection from the hazard of caving ground during excavation. The detailed plan shall include any tabulated data and any design calculations used in the preparation of the plan. Excavation shall not begin until the detailed plan has been reviewed and approved by the Engineer.

• Detailed plans of protective systems for which the Construction Safety Orders require design by a registered professional engineer shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California, and shall include the soil classification, soil properties, soil design calculations that demonstrate adequate stability of the protective system, and any other design calculations used in the preparation of the plan.

• No plan shall allow the use of a protective system less effective than that required by the Construction Safety Orders.

• If the detailed plan includes designs of protective systems developed only from the allowable configurations and slopes, or Appendices, contained in the Construction Safety Orders, the plan shall be submitted at least 5 days before the Contractor intends to begin excavation. If the detailed plan includes designs of protective systems developed from tabulated

data, or designs for which design by a registered professional engineer is required, the plan shall be submitted at least 3 weeks before the Contractor intends to begin excavation.

- Attention is directed to Section 7-1.01E, "Trench Safety."

SECTION 9: MEASUREMENT AND PAYMENT

Issue Date: February 10, 2004

Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications is amended to read:

9-1.04 NOTICE OF POTENTIAL CLAIM

- It is the intention of this section that disputes between the parties arising under and by virtue of the contract be brought to the attention of the Engineer at the earliest possible time in order that the matters may be resolved, if possible, or other appropriate action promptly taken.
- Disputes will not be considered unless the Contractor has first complied with specified notice or protest requirements, including Section 4-1.03, "Changes," Section 5-1.116, "Differing Site Conditions," Section 8-1.06, "Time of Completion," Section 8-1.07, "Liquidated Damages," and Section 8-1.10, "Utility and Non-Highway Facilities."
- For disputes arising under and by virtue of the contract, including an act or failure to act by the Engineer, the Contractor shall provide a signed written initial notice of potential claim to the Engineer within 5 days from the date the dispute first arose. The initial notice of potential claim shall provide the nature and circumstances involved in the dispute which shall remain consistent through the dispute. The initial notice of potential claim shall be submitted on Form CEM-6201A furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655. The Contractor shall assign an exclusive identification number for each dispute, determined by chronological sequencing, based on the date of the dispute.
- The exclusive identification number for each dispute shall be used on the following corresponding documents:

A. Initial notice of potential claim.
B. Supplemental notice of potential claim.
C. Full and final documentation of potential claim.
D. Corresponding claim included in the Contractor's written statement of claims.

- The Contractor shall provide the Engineer the opportunity to examine the site of work within 5 days from the date of the initial notice of potential claim. The Contractor shall proceed with the performance of contract work unless otherwise specified or directed by the Engineer.
- Throughout the disputed work, the Contractor shall maintain records that provide a clear distinction between the incurred direct costs of disputed work and that of undisputed work. The Contractor shall allow the Engineer access to the Contractor's project records deemed necessary by the Engineer to evaluate the potential claim within 20 days of the date of the Engineer's written request.
- Within 15 days of submitting the initial notice of potential claim, the Contractor shall provide a signed supplemental notice of potential claim to the Engineer that provides the following information:

A. The complete nature and circumstances of the dispute which caused the potential claim.
B. The contract provisions that provide the basis of claim.
C. The estimated cost of the potential claim, including an itemized breakdown of individual costs and how the estimate was determined.
D. A time impact analysis of the project schedule that illustrates the effect on the scheduled completion date due to schedule changes or disruptions where a request for adjustment of contract time is made.

- The information provided in items A and B above shall provide the Contractor's complete reasoning for additional compensation or adjustments.
- The supplemental notice of potential claim shall be submitted on Form CEM-6201B furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655. The Engineer will evaluate the information presented in the supplemental notice of potential claim and provide a written response to the Contractor within 20 days of its receipt. If the estimated cost or effect on the scheduled completion date changes, the Contractor shall update information in items C and D above as soon as the change is recognized and submit this information to the Engineer.
- Within 30 days of the completion of work related to the potential claim, the Contractor shall provide the full and final documentation of potential claim to the Engineer that provides the following information:

A. A detailed factual narration of events fully describing the nature and circumstances that caused the dispute, including, but not limited to, necessary dates, locations, and items of work affected by the dispute.
B. The specific provisions of the contract that support the potential claim and a statement of the reasons these provisions support and provide a basis for entitlement of the potential claim.
C. When additional monetary compensation is requested, the exact amount requested calculated in conformance with Section 9-1.03, "Force Account Payment," or Section 8-1.09, "Right of Way Delays," including an itemized breakdown of individual costs. These costs shall be segregated into the following cost categories:

    1. Labor – A listing of individuals, classifications, regular hours and overtime hours worked, dates worked, and other pertinent information related to the requested reimbursement of labor costs.
    2. Materials – Invoices, purchase orders, location of materials either stored or incorporated into the work, dates materials were transported to the project or incorporated into the work, and other pertinent information related to the requested reimbursement of material costs.
    3. Equipment – Listing of detailed description (make, model, and serial number), hours of use, dates of use and equipment rates. Equipment rates shall be at the applicable State rental rate as listed in the Department of Transportation publication entitled "Labor Surcharge and Equipment Rental Rates," in effect when the affected work related to the dispute was performed.
    4. Other categories as specified by the Contractor or the Engineer.

D. When an adjustment of contract time is requested the following information shall be provided:

    1. The specific dates for which contract time is being requested.
    2. The specific reasons for entitlement to a contract time adjustment.
    3. The specific provisions of the contract that provide the basis for the requested contract time adjustment.
    4. A detailed time impact analysis of the project schedule. The time impact analysis shall show the effect of changes or disruptions on the scheduled completion date to demonstrate entitlement to a contract time adjustment.

E. The identification and copies of the Contractor's documents and the substance of oral communications that support the potential claim.

- The full and final documentation of the potential claim shall be submitted on Form CEM-6201C furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655.
- Pertinent information, references, arguments, and data to support the potential claim shall be included in the full and final documentation of potential claim. Information submitted subsequent to the full and final documentation submittal will not be considered. Information required in the full and final documentation of potential claim, as listed in items A to E above, that is not applicable to the dispute may be exempted as determined by the Engineer. No full and final documentation of potential claim will be considered that does not have the same nature and circumstances, and basis of claim as those specified on the initial and supplemental notices of potential claim.
- The Engineer will evaluate the information presented in the full and final documentation of potential claim and provide a written response to the Contractor within 30 days of its receipt unless otherwise specified. The Engineer's receipt of the full and final documentation of potential claim shall be evidenced by postal receipt or the Engineer's written receipt if delivered by hand. If the full and final documentation of potential claim is submitted by the Contractor after acceptance of the work by the Director, the Engineer need not provide a written response.
- Provisions in this section shall not apply to those claims for overhead costs and administrative disputes that occur after issuance of the proposed final estimate. Administrative disputes are disputes of administrative deductions or retentions, contract item quantities, contract item adjustments, interest payments, protests of contract change orders as provided in Section 4-1.03A, "Procedure and Protest," and protests of the weekly statement of working days as provided in Section 8-1.06, "Time of Completion." Administrative disputes that occur prior to issuance of the proposed final estimate shall follow applicable requirements of this section. Information listed in the supplemental notice and full and final documentation of potential claim that is not applicable to the administrative dispute may be exempted as determined by the Engineer.
- Unless otherwise specified in the special provisions, the Contractor may pursue the administrative claim process pursuant to Section 9-1.07B, "Final Payment and Claims," for any potential claim found by the Engineer to be without merit.
- Failure of the Contractor to conform to specified dispute procedures shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract, and is deemed as the Contractor's waiver of the potential claim and a waiver of the right to a corresponding claim for the disputed work in the administrative claim process in conformance with

Section 9-1.07B, "Final Payment of Claims," and shall operate as a bar to arbitration pursuant to Section 10240.2 of the California Public Contract Code.

Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications is amended to read:

9-1.07B Final Payment and Claims

• After acceptance by the Director, the Engineer will make a proposed final estimate in writing of the total amount payable to the Contractor, including an itemization of the total amount, segregated by contract item quantities, extra work and other bases for payment, and shall also show each deduction made or to be made for prior payments and amounts to be kept or retained under the provisions of the contract. Prior estimates and payments shall be subject to correction in the proposed final estimate. The Contractor shall submit written approval of the proposed final estimate or a written statement of claims arising under or by virtue of the contract so that the Engineer receives the written approval or statement of claims no later than close of business of the thirtieth day after receiving the proposed final estimate. If the thirtieth day falls on a Saturday, Sunday or legal holiday, then receipt of the written approval or statement of claims by the Engineer shall not be later than close of business of the next business day. The Contractor's receipt of the proposed final estimate shall be evidenced by postal receipt. The Engineer's receipt of the Contractor's written approval or statement of claims shall be evidenced by postal receipt or the Engineer's written receipt if delivered by hand.

• On the Contractor's approval, or if the Contractor files no claim within the specified period of 30 days, the Engineer will issue a final estimate in writing in conformance with the proposed final estimate submitted to the Contractor, and within 30 days thereafter the State will pay the entire sum so found to be due. That final estimate and payment thereon shall be conclusive and binding against both parties to the contract on all questions relating to the amount of work done and the compensation payable therefor, except as otherwise provided in Sections 9-1.03C, "Records," and 9-1.09, "Clerical Errors."

• If the Contractor within the specified period of 30 days files claims, the Engineer will issue a semifinal estimate in conformance with the proposed final estimate submitted to the Contractor and within 30 days thereafter the State will pay the sum found to be due. The semifinal estimate and corresponding payment shall be conclusive and binding against both parties to the contract on each question relating to the amount of work done and the compensation payable therefor, except insofar as affected by the claims filed within the time and in the manner required hereunder and except as otherwise provided in Sections 9-1.03C, "Records," and 9-1.09, "Clerical Errors."

• Except for claims for overhead costs and administrative disputes that occur after issuance of the proposed final estimate, the Contractor shall only provide the following two items of information for each claim:

A. The exclusive identification number that corresponds to the supporting full and final documentation of potential claim.
B. The final amount of requested additional compensation.

• If the final amount of requested additional compensation is different than the amount of requested compensation included in the full and final documentation of potential claim, the Contractor shall provide in the written statement of claims the reasons for the changed amount, the specific provisions of the contract which support the changed amount, and a statement of the reasons the provisions support and provide a basis for the changed amount. If the Contractor's claim fails to provide an exclusive identification number or if there is a disparity in the provided exclusive identification number, the Engineer will notify the Contractor of the omission or disparity. The Contractor shall have 15 days after receiving notification from the Engineer to correct the omission or disparity. If after the 15 days has elapsed, there is still an omission or disparity of the exclusive identification number assigned to the claim, the Engineer will assign the number. No claim will be considered that has any of the following deficiencies:

A. The claim does not have the same nature, circumstances, and basis as the corresponding full and final documentation of potential claim.
B. The claim does not have a corresponding full and final documentation of potential claim.
C. The claim was not included in the written statement of claims.
D. The Contractor did not comply with applicable notice or protest requirements of Sections 4-1.03, "Changes," 5-1.116, "Differing Site Condition," 8-1.06, "Time of Completion," 8-1.07, "Liquidated Damages," 8-1.10, "Utility and Non-Highway Facilities," and 9-1.04, "Notice of Potential Claim."

• Administrative disputes that occur after issuance of the proposed final estimate shall be included in the Contractor's written statement of claims in sufficient detail to enable the Engineer to ascertain the basis and amounts of those claims.

• The Contractor shall keep full and complete records of the costs and additional time incurred for work for which a claim for additional compensation is made. The Engineer or designated claim investigators or auditors shall have access to

those records and any other records as may be required by the Engineer to determine the facts or contentions involved in the claims. Failure to permit access to those records shall be sufficient cause for denying the claims.

- The written statement of claims submitted by the Contractor shall be accompanied by a notarized certificate containing the following language:

> Under the penalty of law for perjury or falsification and with specific reference to the California False Claims Act, Government Code Section 12650 et. seq., the undersigned,
>
> _____ .
> *(name)*
>
> _____ *of*
> *(title)*
>
> _____ .
> *(company)*
>
> hereby certifies that the claim for the additional compensation and time, if any, made herein for the work on this contract is a true statement of the actual costs incurred and time sought, and is fully documented and supported under the contract between parties.
>
> Dated _____
>
> /s/ _____
>
> Subscribed and sworn before me this _____ day
>
> of _____ .
>
> _____
> *(Notary Public)*
> My Commission
> Expires _____

- Failure to submit the notarized certificate will be sufficient cause for denying the claim.
- Claims for overhead type expenses or costs, in addition to being certified as stated above, shall be supported and accompanied by an audit report of an independent Certified Public Accountant. Omission of a supporting audit report of an independent Certified Public Accountant shall result in denial of the claim and shall operate as a bar to arbitration, as to the claim, in conformance with the requirements in Section 10240.2 of the California Public Contract Code. Claims for overhead type expenses or costs shall be subject to audit by the State at its discretion. The costs of performing an audit examination and submitting the report shall be borne by the Contractor. The Certified Public Accountant's audit examination shall be performed in conformance with the requirements of the American Institute of Certified Public Accountants Attestation Standards. The audit examination and report shall depict the Contractor's project and company-wide financial records and shall specify the actual overall average daily rates for both field and home office overhead for the entire duration of the project, and whether the costs have been properly allocated. The rates of field and home office overhead shall exclude unallowable costs as determined in Title 48 of the Federal Acquisition Regulations, Chapter 1, Part 31. The audit examination and report shall determine if the rates of field and home office overhead are:

A. Allowable in conformance with the requirements in Title 48 of the Federal Acquisition Regulations, Chapter 1, Part 31.
B. Adequately supported by reliable documentation.
C. Related solely to the project under examination.

- Costs or expenses incurred by the State in reviewing or auditing claims that are not supported by the Contractor's cost accounting or other records shall be deemed to be damages incurred by the State within the meaning of the California False Claims Act.
- If the Contractor files a timely written statement of claims in response to the proposed final estimate, the District that administers the contract will submit a claim position letter to the Contractor by hand delivery or deposit in the U.S. mail within 135 days of acceptance of the contract. The claim position letter will delineate the District's position on the Contractor's claims. If the Contractor disagrees with the claim position letter, the Contractor shall submit a written notification of its disagreement and a written request to meet with the board of review, to be received by the District not later than 15 days after the Contractor's receipt of the claim position letter. The written notification of disagreement shall set forth

the basis for the Contractor's disagreement and be submitted to the office designated in the claim position letter. The Contractor's failure to provide a timely written notification of disagreement or timely written request to meet with the board of review shall constitute the Contractor's acceptance and agreement with the determinations provided in the claim position letter and with final payment pursuant to the claim position letter.

- If the Contractor files a timely notification of disagreement with the District claim position letter and a timely request to meet with the board of review, then the board of review, designated by the District Director to review claims that remain in dispute, will meet with the Contractor within 45 days after receipt by the District of the notification of disagreement.
- If the District fails to submit a claim position letter to the Contractor within 135 days after the acceptance of the contract and the Contractor has claims that remain in dispute, the Contractor may request a meeting with the board of review designated by the District Director to review claims that remain in dispute. The Contractor's request for a meeting shall identify the claims that remain in dispute. If the Contractor files a request for a meeting, the board of review will meet with the Contractor within 45 days after the District receives the request for the meeting.
- Attendance by the Contractor at the board of review meeting shall be mandatory. The board of review will review those claims and make a written recommendation thereon to the District Director. The final determination of claims, made by the District Director, will be sent to the Contractor by hand delivery or deposit in the U.S. mail. The Engineer will then make and issue the Engineer's final estimate in writing and within 30 days thereafter the State will pay the entire sum, if any, found due thereon. That final estimate shall be conclusive and binding against both parties to the contract on all questions relating to the amount of work done and the compensation payable therefor, except as otherwise provided in Sections 9-1.03C, "Records," and 9-1.09, "Clerical Errors."
- Failure of the Contractor to conform to the specified dispute procedures shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract and shall operate as a bar to arbitration in conformance with the requirements in Section 10240.2 of the California Public Contract Code.

SECTION 19: EARTHWORK

Issue Date: December 31, 2001

The third paragraph of Section 19-1.02, "Preservation of Property," of the Standard Specifications is amended to read:

- In addition to the provisions in Sections 5-1.02, "Plans and Working Drawings," and 5-1.02A, "Excavation Safety Plans," detailed plans of the protective systems for excavations on or affecting railroad property will be reviewed for adequacy of protection provided for railroad facilities, property, and traffic. These plans shall be submitted at least 9 weeks before the Contractor intends to begin excavation requiring the protective systems. Approval by the Engineer of the detailed plans for the protective systems will be contingent upon the plans being satisfactory to the railroad company involved.

SECTION 42: GROOVE AND GRIND PAVEMENT

Issue Date: December 31, 2001

The last sentence of the first subparagraph of the third paragraph in Section 42-2.02, "Construction," of the Standard Specifications is amended to read:

- After grinding has been completed, the pavement shall conform to the straightedge and profile requirements specified in Section 40-1.10, "Final Finishing."

SECTION 49: PILING

Issue Date: March 25, 2004

The first paragraph in Section 49-1.03, "Determination of Length," of the Standard Specifications is amended to read:

- Foundation piles of any material shall be of such length as is required to develop the nominal resistance, to obtain the specified penetration, and to extend into the cap or footing block as shown on the plans, or specified in the special provisions.

The fourth paragraph in Section 49-1.03, "Determination of Length," of the Standard Specifications is amended to read:

• Modification to the specified installation methods and specified pile tip elevation will not be considered at locations where tension or lateral load demands control design pile tip elevations or when the plans state that specified pile tip elevation shall not be revised.

The sixth and seventh paragraphs in Section 49-1.03, "Determination of Length," of the Standard Specifications are amended to read:

• Indicator compression pile load testing shall conform to the requirements in ASTM Designation: D 1143. The pile shall sustain the first compression test load applied which is equal to the nominal resistance in compression, as shown on the plans, with no more than 13 mm total vertical movement at the top of the pile measured relative to the top of the pile prior to the start of compression load testing.

• Indicator tension pile load testing shall conform to the requirements in ASTM Designation: D 3689. The loading apparatus described as "Load Applied to Pile by Hydraulic Jack(s) Acting at One End of Test Beam(s) Anchored to the Pile" shall not be used. The pile shall sustain the first tension test load applied which is equal to the nominal resistance in tension, as shown on the plans, with no more than 13 mm total vertical movement at the top of the pile measured relative to the top of the pile prior to the start of tension load testing.

The ninth paragraph in Section 49-1.03, "Determination of Length," of the Standard Specifications is amended to read:

• For driven piling, the Contractor shall furnish piling of sufficient length to obtain both the specified tip elevation and nominal resistance shown on the plans or specified in the special provisions. For cast-in-drilled-hole concrete piling, the Contractor shall construct piling of such length to develop the nominal resistance in compression and to obtain the specified tip elevation shown on the plans or specified in the special provisions.

The tenth paragraph in Section 49-1.03, "Determination of Length," of the Standard Specifications is deleted.

The fourth paragraph in Section 49-1.04, "Load Test Piles," of the Standard Specifications is amended to read:

• Load test piles and anchor piles which are not to be incorporated in the completed structure shall be removed in conformance with the provisions in Section 15-4.02, "Removal Methods," and the remaining holes shall be backfilled with earth or other suitable material approved by the Engineer.

The first paragraph in Section 49-1.05, "Driving Equipment," of the Standard Specifications is amended to read:

• Driven piles shall be installed with impact hammers that are approved in writing by the Engineer. Impact hammers shall be steam, hydraulic, air or diesel hammers. Impact hammers shall develop sufficient energy to drive the piles at a penetration rate of not less than 3 mm per blow at the specified nominal resistance.

The seventh paragraph in Section 49-1.05, "Driving Equipment," of the Standard Specifications is amended to read:

• When necessary to obtain the specified penetration and when authorized by the Engineer, the Contractor may supply and operate one or more water jets and pumps, or furnish the necessary drilling apparatus and drill holes not greater than the least dimension of the pile to the proper depth and drive the piles therein. Jets shall not be used at locations where the stability of embankments or other improvements would be endangered. In addition, for steel piles, steel shells, or steel casings, when necessary to obtain the specified penetration or to prevent damage to the pile during installation, the Contractor shall provide special driving tips or heavier pile sections or take other measures as approved by the Engineer.

• The use of followers or underwater hammers for driving piles will be permitted if authorized in writing by the Engineer. When a follower or underwater hammer is used, its efficiency shall be verified by furnishing the first pile in each bent or footing sufficiently long and driving the pile without the use of a follower or underwater hammer.

The second paragraph in Section 49-1.07, "Driving," of the Standard Specifications is amended to read:

• Timber piles shall be fresh-headed and square and when permitted by the Engineer, the heads of the piles may be protected by means of heavy steel or wrought iron rings. During driving operations timber piling shall be restrained from lateral movement at intervals not to exceed 6 m over the length between the driving head and the ground surface. During driving operations, the timber pile shall be kept moving by continuous operation of the hammer. When the blow count exceeds either 2 times the blow count required in 300 mm, or 3 times the blow count required in 75 mm for the nominal resistance as shown on the plans, computed in conformance with the provisions in Section 49-1.08, "Pile Driving Acceptance

Criteria," additional aids shall be used to obtain the specified penetration. These aids may include the use of water jets or drilling, where permitted, or the use of a larger hammer employing a heavy ram striking with a low velocity.

Section 49-1.08, "Bearing Value and Penetration," of the Standard Specifications is amended to read:

49-1.08 PILE DRIVING ACCEPTANCE CRITERIA

- Except for piles to be load tested, driven piles shall be driven to a value of not less than the nominal resistance shown on the plans unless otherwise specified in the special provisions or permitted in writing by the Engineer. In addition, when a pile tip elevation is specified, driven piles shall penetrate at least to the specified tip elevation, unless otherwise permitted in writing by the Engineer. Piles to be load tested shall be driven to the specified tip elevation.
- When the pile nominal resistance is omitted from the plans or the special provisions, timber piles shall be driven to a nominal resistance of 800 kN, and steel and concrete piles shall be driven to a nominal resistance of 1250 kN.
- The nominal resistance for driven piles shall be determined from the following formula in which "R_u" is the nominal resistance in kilonewtons, "E_r" is the manufacturer's rating for joules of energy developed by the hammer at the observed field drop height, and "N" is the number of hammer blows in the last 300 millimeters. (maximum value to be used for N is 100):

$$R_u = (7 * (E_r)^{1/2} * \log_{10} (0.83 * N)) - 550$$

Section 49-3.01, "Description," of the Standard Specifications is amended by deleting the fifth paragraph.

The sixth paragraph in Section 49-3.01, "Description," of the Standard Specifications is amended to read:

- Lifting anchors used in precast prestressed concrete piles without a class designation ending in "C" (corrosion resistant) shall be removed, and the holes filled in conformance with the provisions in Section 51-1.18A, "Ordinary Surface Finish."

The first and second paragraphs in Section 49-4.01, "Description," of the Standard Specifications are amended to read:

- Cast-in-place concrete piles shall consist of one of the following:

  A. Steel shells driven permanently to the required nominal resistance and penetration and filled with concrete.
  B. Steel casings installed permanently to the required penetration and filled with concrete.
  C. Drilled holes filled with concrete.
  D. Rock sockets filled with concrete.

- The drilling of holes shall conform to the provisions in these specifications. Concrete filling for cast-in-place concrete piles is designated by compressive strength and shall have a minimum 28-day compressive strength of 25 MPa. At the option of the Contractor, the combined aggregate grading for the concrete shall be either the 25-mm maximum grading, the 12.5-mm maximum grading, or the 9.5-mm maximum grading. Concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," and Section 51, "Concrete Structures." Reinforcement shall conform to the provisions in Section 52, "Reinforcement."

The fourth paragraph in Section 49-4.03, "Drilled Holes," of the Standard Specifications is amended to read:

- After placing reinforcement and prior to placing concrete in the drilled hole, if caving occurs or deteriorated foundation material accumulates on the bottom of the hole, the bottom of the drilled hole shall be cleaned. The Contractor shall verify that the bottom of the drilled hole is clean.

The first and second paragraphs in Section 49-4.04, "Steel Shells," of the Standard Specifications are amended to read:

- Steel shells shall be sufficiently watertight to exclude water during the placing of concrete. The shells may be cylindrical or tapered, step-tapered, or a combination of either, with cylindrical sections.

The first paragraph in Section 49-4.05, "Inspection," of the Standard Specifications is amended to read:

- After being driven and prior to placing reinforcement and concrete therein, the steel shells shall be examined for collapse or reduced diameter at any point. Any shell which is improperly driven or broken or shows partial collapse to such an extent as to materially decrease its nominal resistance will be rejected. Rejected shells shall be removed and replaced, or a new shell shall be driven adjacent to the rejected shell. Rejected shells which cannot be removed shall be filled with concrete by the Contractor at the Contractor's expense. When a new shell is driven to replace a rejected shell, the Contractor, at the Contractor's expense, shall enlarge the footing as determined necessary by the Engineer.

The third paragraph in Section 49-5.01, "Description," of the Standard Specifications is amended to read:

- Steel pipe piles shall conform to the following requirements:

    1. Steel pipe piles less than 360 mm in diameter shall conform to the requirements in ASTM Designation: A 252, Grade 2 or 3.
    2. Steel pipe piles 360 mm and greater in diameter shall conform to the requirements in ASTM Designation: A 252, Grade 3.
    3. Steel pipe piles shall be of the nominal diameter and nominal wall thickness shown on the plans or specified in the special provisions.
    4. The carbon equivalency (CE) of steel for steel pipe piles, as defined in AWS D 1.1, Section XI5.1, shall not exceed 0.45.
    5. The sulfur content of steel for steel pipe piles shall not exceed 0.05-percent.
    6. Seams in steel pipe piles shall be complete penetration welds.

The third paragraph in Section 49-6.02, "Payment," of the Standard Specifications is amended to read:

- The contract price paid per meter for cast-in-drilled-hole concrete piling shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in drilling holes, disposing of material resulting from drilling holes, temporarily casing holes and removing water when necessary, furnishing and placing concrete and reinforcement, and constructing reinforced concrete extensions, complete in place, to the required penetration, as shown on the plans, as specified in these specifications and in the special provisions, and as directed by the Engineer.

The seventh paragraph in Section 49-6.02, "Payment," of the Standard Specifications is amended to read

- The contract unit price paid for drive pile shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in driving timber, concrete and steel piles, driving steel shells for cast-in-place concrete piles, placing filling materials for cast-in-place concrete piles and cutting off piles, all complete in place to the required nominal resistance and penetration as shown on the plans and as specified in these specifications and the special provisions, and as directed by the Engineer.

The ninth paragraph in Section 49-6.02, "Payment," of the Standard Specifications is amended to read:

- Full compensation for all jetting, drilling, providing special driving tips or heavier sections for steel piles or shells, or other work necessary to obtain the specified penetration and nominal resistance of the piles, for predrilling holes through embankment and filling the space remaining around the pile with sand or pea gravel, for disposing of material resulting from jetting, drilling or predrilling holes, and for all excavation and backfill involved in constructing concrete extensions as shown on the plans, and as specified in these specifications and the special provisions, and as directed by the Engineer shall be considered as included in the contract unit price paid for drive pile or in the contract price paid per meter for cast-in-drilled-hole concrete piling, and no additional compensation will be allowed therefor.

Section 49-6.02, "Payment," of the Standard Specifications is amended by adding the following paragraphs:

Full compensation for furnishing and placing additional testing reinforcement, for load test anchorages, and for cutting off test piles, shall be considered as included in the contract price paid for piling of the type or class shown in the Engineer's Estimate, and no additional compensation will be allowed.

No additional compensation or extension of time will be made for additional foundation investigation, installation and testing of indicator piling, cutting off piling and restoring the foundation investigation and indicator pile sites, and review of request by the Engineer

SECTION 50: PRESTRESSING CONCRETE

Issue Date: November 18, 2002

Section 50-1.02, "Drawings," of the Standard Specifications is amended by adding the following paragraph after the second paragraph:

• Each working drawing submittal shall consist of plans for a single bridge or portion thereof. For multi-frame bridges, each frame shall require a separate working drawing submittal.

Section 50-1.05, "Prestressing Steel," of the Standard Specifications is amended to read:

• Prestressing steel shall be high-tensile wire conforming to the requirements in ASTM Designation: A 421, including Supplement I; high-tensile seven-wire strand conforming to the requirements in ASTM Designation: A 416; or uncoated high-strength steel bars conforming to the requirements in ASTM Designation: A 722, including all supplementary requirements. The maximum mass requirement of ASTM Designation: A 722 will not apply.

• In addition to the requirements of ASTM Designation: A 722, for deformed bars, the reduction of area shall be determined from a bar from which the deformations have been removed. The bar shall be machined no more than necessary to remove the deformations over a length of 300 mm, and reduction will be based on the area of the machined portion.

• In addition to the requirements specified herein, epoxy-coated seven-wire prestressing steel strand shall be grit impregnated and filled in conformance with the requirements in ASTM Designation: A 882/A 882M, including Supplement I, and the following:

A. The coating material shall be on the Department's list of approved coating materials for epoxy-coated strand, available from the Transportation Laboratory.
B. The film thickness of the coating after curing shall be 381 µm to 1143 µm.
C. Prior to coating the strand, the Contractor shall furnish to the Transportation Laboratory a representative 230-g sample from each batch of epoxy coating material to be used. Each sample shall be packaged in an airtight container identified with the manufacturer's name and batch number.
D. Prior to use of the epoxy-coated strand in the work, written certifications referenced in ASTM Designation: A 882/A 882M, including a representative load-elongation curve for each size and grade of strand to be used and a copy of the quality control tests performed by the manufacturer, shall be furnished to the Engineer.
E. In addition to the requirements in Section 50-1.10, "Samples for Testing," four 1.5-m long samples of coated strand and one 1.5-m long sample of uncoated strand of each size and reel shall be furnished to the Engineer for testing. These samples, as selected by the Engineer, shall be representative of the material to be used in the work.
F. Epoxy-coated strand shall be cut using an abrasive saw.
G. All visible damage to coatings caused by shipping and handling, or during installation, including cut ends, shall be repaired in conformance with the requirements in ASTM Designation: A 882/A 882M. The patching material shall be furnished by the manufacturer of the epoxy powder and shall be applied in conformance with the manufacturer's written recommendations. The patching material shall be compatible with the original epoxy coating material and shall be inert in concrete.

• All bars in any individual member shall be of the same grade, unless otherwise permitted by the Engineer.

• When bars are to be extended by the use of couplers, the assembled units shall have a tensile strength of not less than the manufacturer's minimum guaranteed ultimate tensile strength of the bars. Failure of any one sample to meet this requirement will be cause for rejection of the heat of bars and lot of couplers. The location of couplers in the member shall be subject to approval by the Engineer.

• Wires shall be straightened if necessary to produce equal stress in all wires or wire groups or parallel lay cables that are to be stressed simultaneously or when necessary to ensure proper positioning in the ducts.

• Where wires are to be button-headed, the buttons shall be cold formed symmetrically about the axes of the wires. The buttons shall develop the minimum guaranteed ultimate tensile strength of the wire. No cold forming process shall be used that causes indentations in the wire. Buttonheads shall not contain wide open splits, more than 2 splits per head, or splits not parallel with the axis of the wire.

• Prestressing steel shall be protected against physical damage and rust or other results of corrosion at all times from manufacture to grouting or encasing in concrete. Prestressing steel that has sustained physical damage at any time shall be rejected. The development of visible rust or other results of corrosion shall be cause for rejection, when ordered by the Engineer.

- Epoxy-coated prestressing steel strand shall be covered with an opaque polyethylene sheeting or other suitable protective material to protect the strand from exposure to sunlight, salt spray, and weather. For stacked coils, the protective covering shall be draped around the perimeter of the stack. The covering shall be adequately secured; however, it should allow for air circulation around the strand to prevent condensation under the covering. Epoxy-coated strand shall not be stored within 300 m of ocean or tidal water for more than 2 months.
- Prestressing steel shall be packaged in containers or shipping forms for the protection of the steel against physical damage and corrosion during shipping and storage. Except for epoxy-coated strand, a corrosion inhibitor which prevents rust or other results of corrosion, shall be placed in the package or form, or shall be incorporated in a corrosion inhibitor carrier type packaging material, or when permitted by the Engineer, may be applied directly to the steel. The corrosion inhibitor shall have no deleterious effect on the steel or concrete or bond strength of steel to concrete. Packaging or forms damaged from any cause shall be immediately replaced or restored to original condition.
- The shipping package or form shall be clearly marked with a statement that the package contains high-strength prestressing steel, and the type of corrosion inhibitor used, including the date packaged.
- Prestressing steel for post-tensioning which is installed in members prior to placing and curing of the concrete, and which is not epoxy-coated, shall be continuously protected against rust or other results of corrosion, until grouted, by means of a corrosion inhibitor placed in the ducts or applied to the steel in the duct. The corrosion inhibitor shall conform to the provisions specified herein.
- When steam curing is used, prestressing steel for post-tensioning shall not be installed until the steam curing is completed.
- Water used for flushing ducts shall contain either quick lime (calcium oxide) or slaked lime (calcium hydroxide) in the amount of 0.01-kg/L. Compressed air used to blow out ducts shall be oil free.
- When prestressing steel for post-tensioning is installed in the ducts after completion of concrete curing, and if stressing and grouting are completed within 10 days after the installation of the prestressing steel, rust which may form during those 10 days will not be cause for rejection of the steel. Prestressing steel installed, tensioned, and grouted in this manner, all within 10 days, will not require the use of a corrosion inhibitor in the duct following installation of the prestressing steel. Prestressing steel installed as above but not grouted within 10 days shall be subject to all the requirements in this section pertaining to corrosion protection and rejection because of rust. The requirements in this section pertaining to tensioning and grouting within 10 days shall not apply to epoxy-coated prestressing steel strand.
- Any time prestressing steel for pretensioning is placed in the stressing bed and is exposed to the elements for more than 36 hours prior to encasement in concrete, adequate measures shall be taken by the Contractor, as approved by the Engineer, to protect the steel from contamination or corrosion.
- After final fabrication of the seven-wire prestressing steel strand, no electric welding of any form shall be performed on the prestressing steel. Whenever electric welding is performed on or near members containing prestressing steel, the welding ground shall be attached directly to the steel being welded.
- Pretensioned prestressing steel shall be cut off flush with the end of the member. For epoxy-coated prestressing steel, only abrasive saws shall be used to cut the steel. The exposed ends of the prestressing steel and a 25-mm strip of adjoining concrete shall be cleaned and painted. Cleaning shall be by wire brushing or abrasive blast cleaning to remove all dirt and residue on the metal or concrete surfaces. Immediately after cleaning, the surfaces shall be covered with one application of unthinned zinc-rich primer (organic vehicle type) conforming to the provisions in Section 91, "Paint," except that 2 applications shall be applied to surfaces which will not be covered by concrete or mortar. Aerosol cans shall not be used. The paint shall be thoroughly mixed at the time of application and shall be worked into any voids in the prestressing tendons.

The thirteenth paragraph in Section 50-1.08, "Prestressing," of the Standard Specifications is amended to read:

- Prestressing steel in pretensioned members shall not be cut or released until the concrete in the member has attained a compressive strength of not less than the value shown on the plans or 28 MPa, whichever is greater. In addition to these concrete strength requirements, when epoxy-coated prestressing steel strand is used, the steel shall not be cut or released until the temperature of the concrete surrounding the strand is less than 65°C, and falling.

The fifth paragraph in Section 50-1.10, "Samples for Testing," of the Standard Specifications is amended to read:

- The following samples of materials and tendons, selected by the Engineer from the prestressing steel at the plant or jobsite, shall be furnished by the Contractor to the Engineer well in advance of anticipated use:

A. For wire or bars, one 2-m long sample and for strand, one 1.5-m long sample, of each size shall be furnished for each heat or reel.
B. For epoxy-coated strand, one 1.5-m long sample of uncoated strand of each size shall be furnished for each reel.

C. If the prestressing tendon is a bar, one 2-m long sample shall be furnished and in addition, if couplers are to be used with the bar, two 1.25-m long samples of bar, equipped with one coupler and fabricated to fit the coupler, shall be furnished.

The second paragraph in Section 50-1.11, "Payment," of the Standard Specifications is amended to read:

• The contract lump sum prices paid for prestressing cast-in-place concrete of the types listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in furnishing, placing, and tensioning the prestressing steel in cast-in-place concrete structures, complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

SECTION 51: CONCRETE STRUCTURES

Issue Date: December 23, 2003

The eleventh paragraph in Section 51-1.05, "Forms," of the Standard Specifications is amended to read:

• Form panels for exposed surfaces shall be furnished and placed in uniform widths of not less than 0.9-m and in uniform lengths of not less than 1.8 m, except at the end of continuously formed surfaces where the final panel length required is less than 1.8 m. Where the width of the member formed is less than 0.9-m, the width of the panels shall be not less than the width of the member. Panels shall be arranged in symmetrical patterns conforming to the general lines of the structure. Except when otherwise provided herein or shown on the plans, panels for vertical surfaces shall be placed with the long dimension horizontal and with horizontal joints level and continuous. Form panels for curved surfaces of columns shall be continuous for a minimum of one quarter of the circumference, or 1.8 m. For walls with sloping footings which do not abut other walls, panels may be placed with the long dimension parallel to the footing. Form panels on each side of the panel joint shall be precisely aligned, by means of supports or fasteners common to both panels, to result in a continuous unbroken concrete plane surface. When prefabricated soffit panels are used, form filler panels joining prefabricated panels shall have a uniform minimum width of 0.3-m and shall produce a smooth uniform surface with consistent longitudinal joint lines between the prefabricated panels.

The first and second paragraph in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications are amended to read:

• The Contractor shall submit to the Engineer working drawings and design calculations for falsework proposed for use at bridges. For bridges where the height of any portion of the falsework, as measured from the ground line to the soffit of the superstructure, exceeds 4.25 m; or where any individual falsework clear span length exceeds 4.85 m; or where provision for vehicular, pedestrian, or railroad traffic through the falsework is made; the drawings shall be signed by an engineer who is registered as a Civil Engineer in the State of California. Six sets of the working drawings and 2 copies of the design calculations shall be furnished. Additional working drawings and design calculations shall be submitted to the Engineer when specified in "Railroad Relations and Insurance" of the special provisions.

• The falsework drawings shall include details of the falsework erection and removal operations showing the methods and sequences of erection and removal and the equipment to be used. The details of the falsework erection and removal operations shall demonstrate the stability of all or any portions of the falsework during all stages of the erection and removal operations.

The seventh paragraph in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications is amended to read:

• In the event that several falsework plans are submitted simultaneously, or an additional plan is submitted for review before the review of a previously submitted plan has been completed, the Contractor shall designate the sequence in which the plans are to be reviewed. In such event, the time to be provided for the review of any plan in the sequence shall be not less than the review time specified above for that plan, plus 2 weeks for each plan of higher priority which is still under review. A falsework plan submittal shall consist of plans for a single bridge or portion thereof. For multi-frame bridges, each frame shall require a separate falsework plan submittal.

Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications is amended by adding the following paragraphs:

• If structural composite lumber is proposed for use, the falsework drawings shall clearly identify the structural composite lumber members by grade (E value), species, and type. The Contractor shall provide technical data from the manufacturer showing the tabulated working stress values of the composite lumber. The Contractor shall furnish a certificate of compliance as specified in Section 6-1.07, "Certificates of Compliance," for each delivery of structural composite lumber to the project site.

• For falsework piles with a calculated loading capacity greater than 900 kN, the falsework piles shall be designed by an engineer who is registered as either a Civil Engineer or a Geotechnical Engineer in the State of California, and the calculations shall be submitted to the Engineer.

The first paragraph in Section 51-1.06A(1), "Design Loads," of the Standard Specifications is amended to read:

• The design load for falsework shall consist of the sum of dead and live vertical loads, and an assumed horizontal load. The minimum total design load for any falsework, including members that support walkways, shall be not less than 4800 N/m^2 for the combined live and dead load regardless of slab thickness.

The eighth paragraph in Section 51-1.06A(1), "Design Loads," of the Standard Specifications is amended to read:

• In addition to the minimum requirements specified in this Section 51-1.06A, falsework for box girder structures with internal falsework bracing systems using flexible members capable of withstanding tensile forces only, shall be designed to include the vertical effects caused by the elongation of the flexible member and the design horizontal load combined with the dead and live loads imposed by concrete placement for the girder stems and connected bottom slabs. Falsework comprised of individual steel towers with bracing systems using flexible members capable of withstanding tensile forces only to resist overturning, shall be exempt from these additional requirements.

The third paragraph in Section 51-1.06B, "Falsework Construction," of the Standard Specifications is amended to read:

• When falsework is supported on piles, the piles shall be driven and the actual nominal resistance assessed in conformance with the provisions in Section 49, "Piling."

Section 51-1.06B, "Falsework Construction," of the Standard Specifications is amended by adding the following paragraphs:

• For falsework piles with a calculated nominal resistance greater than 1800 kN, the Contractor shall conduct dynamic monitoring of pile driving and generate field acceptance criteria based on a wave equation analysis. These analyses shall be signed by an engineer who is registered as a Civil Engineer in the State of California and submitted to the Engineer prior to completion of falsework erection.

• Prior to the placement of falsework members above the stringers, the final bracing system for the falsework shall be installed.

Section 51-1.06C, "Removing Falsework," of the Standard Specifications is amended by adding the following paragraph:

• The falsework removal operation shall be conducted in such a manner that any portion of the falsework not yet removed remains in a stable condition at all times.

The sixth paragraph in Section 51-1.09, "Placing Concrete," of the Standard Specifications is amended to read:

• Vibrators used to consolidate concrete containing epoxy-coated bar reinforcement or epoxy-coated prestressing steel shall have a resilient covering to prevent damage to the epoxy-coating on the reinforcement or prestressing steel.

The third sentence of the fourth paragraph in Section 51-1.12D, "Sheet Packing, Preformed Pads and Board Fillers," of the Standard Specifications is amended to read:

Surfaces of expanded polystyrene against which concrete is placed shall be faced with hardboard.

The table in the ninth paragraph of Section 51-1.12H(1), "Plain and Fabric Reinforced Elastomeric Bearing Pads," of the Standard Specifications is amended to read:

Tensile strength, percent	-15
Elongation at break, percent	-40; but not less than 300% total elongation of the material
Hardness, points	+10

The first sentence of the fourth paragraph in Section 51-1.17, "Finish Bridge Decks," of the Standard Specifications is amended to read:

- The smoothness of completed roadway surfaces of structures, approach slabs and the adjacent 15 m of approach pavement, and the top surfaces of concrete decks which are to be covered with another material, will be tested by the Engineer with a bridge profilograph in conformance with the requirements in California Test 547 and the requirements herein.

Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications is amended by deleting the seventh, thirteenth and fourteenth paragraphs.

The fourteenth paragraph in Section 51-1.23, "Payment," of the Standard Specifications is amended by deleting "and injecting epoxy in cracks".

SECTION 52: REINFORCEMENT

Issue Date: March 25, 2004

The third paragraph in Section 52-1.04, "Inspection," of the Standard Specifications is amended to read:

- A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall also be furnished for each shipment of epoxy-coated bar reinforcement or wire reinforcement certifying that the coated reinforcement conforms to the requirements in ASTM Designation: A 775/A 775M or A 884/A 884M, respectively, and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement." The Certificate of Compliance shall include all of the certifications specified in ASTM Designation: A 775/A 775M or A 884/A 884M respectively, and a statement that the coating material has been prequalified by acceptance testing performed by the Valley Forge Laboratories, Inc., Devon, Pennsylvania.

Section 52-1.07 "Placing," of the Standard Specifications is amended to read by deleting item C of the third paragraph.

Section 52-1.08 "Splicing," of the Standard Specifications is amended to read:

52-1.08 SPLICING

- Splices of reinforcing bars shall consist of lap splices, service splices, or ultimate butt splices.
- Splicing of reinforcing bars will not be permitted at a location designated on the plans as a "No-Splice Zone." At the option of the Contractor, reinforcing bars may be continuous at locations where splices are shown on the plans. The location of splices, except where shown on the plans, shall be determined by the Contractor using available commercial lengths where practicable.
- Unless otherwise shown on the plans, splices in adjacent reinforcing bars at any particular section shall be staggered. The minimum distance between staggered lap splices or mechanical lap splices shall be the same as the length required for a lap splice in the largest bar. The minimum distance between staggered butt splices shall be 600 mm, measured between the midpoints of the splices along a line which is centered between the axes of the adjacent bars.

52-1.08A Lap Splicing Requirements

- Splices made by lapping shall consist of placing reinforcing bars in contact and wiring them together, maintaining the alignment of the bars and the minimum clearances. Should the Contractor elect to use a butt welded or mechanical splice at a location not designated on the plans as requiring a service or ultimate butt splice, this splice shall conform to the testing requirements for service splice.
- Reinforcing bars shall not be spliced by lapping at locations where the concrete section is not sufficient to provide a minimum clear distance of 50 mm between the splice and the nearest adjacent bar. The clearance to the surface of the concrete specified in Section 52-1.07, "Placing," shall not be reduced.
- Reinforcing bars Nos. 43 and 57 shall not be spliced by lapping.

• Where ASTM Designations: A 615/A 615M, Grade 420 or A 706/A 706M reinforcing bars are required, the length of lap splices shall be as follows: Reinforcing bars No. 25 or smaller shall be lapped at least 45 diameters of the smaller bar joined; and reinforcing bars Nos. 29, 32, and 36 shall be lapped at least 60 diameters of the smaller bar joined, except when otherwise shown on the plans.

• Where ASTM Designation: A 615/A 615M, Grade 280 reinforcing bars are permitted, the length of lap splices shall be as follows: Reinforcing bars No. 25 or smaller shall be lapped at least 30 diameters of the smaller bar joined; and reinforcing bars Nos. 29, 32, and 36 shall be lapped at least 45 diameters of the smaller bar joined, except when otherwise shown on the plans.

• Splices in bundled bars shall conform to the following:

A In bundles of 2 bars, the length of the lap splice shall be the same as the length of a single bar lap splice.
B. In bundles of 3 bars, the length of the lap splice shall be 1.2 times the length of a single bar lap splice.

• Welded wire fabric shall be lapped such that the overlap between the outermost cross wires is not less than the larger of:

A. 150 mm,
B. The spacing of the cross wires plus 50 mm, or
C. The numerical value of the longitudinal wire size (MW-Size Number) times 370 divided by the spacing of the longitudinal wires in millimeters.

52-1.08B Service Splicing and Ultimate Butt Splicing Requirements

• Service splices and ultimate butt splices shall be either butt welded or mechanical splices, shall be used at the locations shown on the plans, and shall conform to the requirements of these specifications and the special provisions.

52-1.08B(1) Mechanical Splices

• Mechanical splices to be used in the work shall be on the Department's current prequalified list before use. The prequalified list can be obtained from the Department's internet site listed in the special provisions or by contacting the Transportation Laboratory directly.

• When tested in conformance with the requirements in California Test 670, the total slip of the reinforcing bars within the splice device after loading in tension to 200 MPa and relaxing to 20 MPa shall not exceed the values listed in the following table. The slip shall be measured between gage points that are clear of the splice device.

Reinforcing Bar Number	Total Slip (μm)
13	250
16	250
19	250
22	350
25	350
29	350
32	450
36	450
43	600
57	750

• Slip requirements shall not apply to mechanical lap splices, splices that are welded, or splices that are used on hoops.

• Splicing procedures shall be in conformance with the manufacturer's recommendations, except as modified in this section. Splices shall be made using the manufacturer's standard equipment, jigs, clamps, and other required accessories.

• Splice devices shall have a clear coverage of not less than 40 mm measured from the surface of the concrete to the outside of the splice device. Stirrups, ties, and other reinforcement shall be adjusted or relocated, and additional reinforcement shall be placed, if necessary, to provide the specified clear coverage to reinforcement.

• The Contractor shall furnish the following information for each shipment of splice material in conformance with the provisions in Section 6-1.07, "Certificates of Compliance:"

A. The type or series identification of the splice material including tracking information for traceability.
B. The bar grade and size number to be spliced.

C. A copy of the manufacturer's product literature giving complete data on the splice material and installation procedures.
D. A statement that the splicing systems and materials used in conformance with the manufacturer's installation procedures will develop the required tensile strengths, based on the nominal bar area, and will conform to the total slip requirements and the other requirements in these specifications.
E. A statement that the splice material conforms to the type of mechanical splice in the Department's current prequalified list.

52-1.08B(2) Butt Welded Splices

• Except for resistance butt welds, butt welded splices of reinforcing bars shall be complete joint penetration butt welds conforming to the requirements in AWS D 1.4, and these specifications.

• Welders and welding procedures shall be qualified in conformance with the requirements in AWS D 1.4.

• Only the joint details and dimensions as shown in Figure 3.2, "Direct Butt Joints," of AWS D 1.4, shall be used for making complete joint penetration butt welds of bar reinforcement. Split pipe backing shall not be used.

• Butt welds shall be made with multiple weld passes using a stringer bead without an appreciable weaving motion. The maximum stringer bead width shall be 2.5 times the diameter of the electrode and slagging shall be performed between each weld pass. Weld reinforcement shall not exceed 4 mm in convexity.

• Electrodes used for welding shall meet the minimum Charpy V-notch impact requirement of 27°J at –20°C.

• For welding of bars conforming to the requirements of ASTM Designation: A 615/A 615M, Grade 280 or Grade 420, the requirements of Table 5.2, "Minimum Preheat and Interpass Temperatures," of AWS D 1.4 are superseded by the following:

The minimum preheat and interpass temperatures shall be 200°C for Grade 280 bars and 300°C for Grade 420 bars. Immediately after completing the welding, at least 150 mm of the bar on each side of the splice shall be covered by an insulated wrapping to control the rate of cooling. The insulated wrapping shall remain in place until the bar has cooled below 90°C.

• When welding different grades of reinforcing bars, the electrode shall conform to Grade 280 bar requirements and the preheat shall conform to the Grade 420 bar requirements.

• In the event that any of the specified preheat, interpass, and post weld cooling temperatures are not met, all weld and heat affected zone metal shall be removed and the splice rewelded.

• Welding shall be protected from air currents, drafts, and precipitation to prevent loss of heat or loss of arc shielding. The method of protecting the welding area from loss of heat or loss of arc shielding shall be subject to approval by the Engineer.

• Reinforcing bars shall not be direct butt spliced by thermite welding.

• Procedures to be used in making welded splices in reinforcing bars, and welders employed to make splices in reinforcing bars, shall be qualified by tests performed by the Contractor on sample splices of the type to be used, before making splices to be used in the work.

52-1.08B(3) Resistance Butt Welds

• Shop produced resistance butt welds shall be produced by a fabricator who is approved by the Transportation Laboratory. The list of approved fabricators can be obtained from the Department's internet site or by contacting the Transportation Laboratory directly.

• Before manufacturing hoops using resistance butt welding, the Contractor shall submit to the Engineer the manufacturer's Quality Control (QC) manual for the fabrication of hoops. As a minimum, the QC manual shall include the following:

A. The pre-production procedures for the qualification of material and equipment.
B. The methods and frequencies for performing QC procedures during production.
C. The calibration procedures and calibration frequency for all equipment.
D. The welding procedure specification (WPS) for resistance welding.
E. The method for identifying and tracking lots.

52-1.08C Service Splice and Ultimate Butt Splice Testing Requirements

• The Contractor shall designate in writing a splicing Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for 1) the quality of all service and ultimate butt splicing including the inspection of materials and workmanship performed by the Contractor and all subcontractors; and 2) submitting, receiving, and approving all correspondence, required submittals, and reports regarding service and ultimate splicing to and from the Engineer.

• The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

• Testing on prequalification and production sample splices shall be performed at the Contractor's expense, at an independent qualified testing laboratory. The laboratory shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors who will provide other services or materials for the project, and shall have the following:

A. Proper facilities, including a tensile testing machine capable of breaking the largest size of reinforcing bar to be tested with minimum lengths as shown in this section.
B. A device for measuring the total slip of the reinforcing bars across the splice to the nearest 25 µm, that, when placed parallel to the longitudinal axis of the bar is able to simultaneously measure movement across the splice, at 2 locations, 180 degrees apart.
C. Operators who have received formal training for performing the testing requirements of ASTM Designation: A 370 and California Test 670.
D. A record of annual calibration of testing equipment performed by an independent third party that has 1) standards that are traceable to the National Institute of Standards and Technology, and 2) a formal reporting procedure, including published test forms.

• The Contractor shall provide samples for quality assurance testing in conformance with the provisions in these specifications and the special provisions.

• Prequalification and production sample splices shall be 1) a minimum length of 1.5 meters for reinforcing bars No. 25 or smaller, and 2 meters for reinforcing bars No. 29 or larger, with the splice located at mid-point; and 2) suitably identified before shipment with weatherproof markings that do not interfere with the Engineer's tamper-proof markings or seals. Splices that shows signs of tampering will be rejected.

• Each set or sample splice, as defined herein, shall be identified as representing either a prequalification or production test sample splice.

• For the purpose of production testing, a lot of either service splices or ultimate butt splices is defined as 1) 150, or fraction thereof, of the same type of mechanical splices used for each bar size and each bar deformation pattern that is used in the work, or 2) 150, or fraction thereof, of complete joint penetration butt welded splices, or resistance butt welded splices for each bar size used in the work. If different diameters of hoop reinforcement are shown on the plans, separate lots shall be used for each different hoop diameter.

• Whenever a lot of splices is rejected, the rejected lot and subsequent lots of splices shall not be used in the work until 1) the QCM performs a complete review of the Contractor's quality control process for these splices, 2) a written report is submitted to the Engineer describing the cause of failure for the splices in this lot and provisions for preventing similar failures in future lots, and 3) the Engineer has provided the Contractor with written notification that the report is acceptable. The Engineer shall have 3 working days after receipt of the report to provide notification to the Contractor. In the event the Engineer fails to provide notification within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in providing notification, the Contractor will be compensated for any resulting loss, and an extension of time will be granted in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

52-1.08C(1) Splice Prequalification Report

• Before using any service splices or ultimate butt splices in the work, the Contractor shall submit a Splice Prequalification Report. The report shall include splice material information, names of the operators who will be performing the splicing, and descriptions of the positions, locations, equipment, and procedures that will be used in the work.

• The Splice Prequalification Report shall also include certifications from the fabricator for prequalifications of operators and procedures based on sample tests performed no more than 2 years before submitting the report. Each operator shall be certified by performing 2 sample splices for each bar size of each splice type that the operator will be performing in the work. For deformation-dependent types of splice devices, each operator shall be certified by performing 2 additional samples for each bar size and deformation pattern that will be used in the work.

• Prequalification sample splices shall be tested by an independent qualified testing laboratory and shall conform to the appropriate production test criteria and slip requirements specified herein. When epoxy-coated reinforcement is required, resistance butt welded sample splices shall have the weld flash removed by the same procedure as will be used in the work, before coating and testing. The Splice Prequalification Report shall include the certified test results for all prequalification sample splices.

• The QCM shall review and approve the Splice Prequalification Report before submitting it to the Engineer for approval. The Contractor shall allow 2 weeks for the review and approval of a complete report before performing any service splicing or ultimate butt splicing in the work. In the event the Engineer fails to complete the review within the time allowed,

and in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

52-1.08C(2) Service Splice Test Criteria

• Service production and quality assurance sample splices shall be tensile tested in conformance with the requirements in ASTM Designation: A 370 and California Test 670 and shall develop a minimum tensile strength of not less than 550 MPa.

52-1.08C(2)(a) Production Test Requirements for Service Splices

• Production tests shall be performed by the Contractor's independent laboratory for all service splices used in the work. A production test shall consist of testing 4 sample splices prepared for each lot of completed splices. The samples shall be prepared by the Contractor using the same splice material, position, operators, location, and equipment, and following the same procedure as used in the work.

• At least one week before testing, the Contractor shall notify the Engineer in writing of the date when and the location where the testing of the samples will be performed.

• The 4 samples from each production test shall be securely bundled together and identified with a completed sample identification card before shipment to the independent laboratory. The card will be furnished by the Engineer. Bundles of samples containing fewer than 4 samples of splices shall not be tested.

• Before performing any tensile tests on production test sample splices, one of the 4 samples shall be tested for, and shall conform to, the requirements for total slip. Should this sample not meet the total slip requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. Should any of the 3 remaining samples not conform to the total slip requirements, all splices in the lot represented by this production test will be rejected.

• If 3 or more sample splices from a production test conform to the provisions in this Section 52-1.08C(2),"Service Splice Test Criteria," all splices in the lot represented by this production test will be considered acceptable, provided each of the 4 samples develop a minimum tensile strength of not less than 420 MPa.

• Should only 2 sample splices from a production test conform to the provisions in this Section 52-1.08C(2), "Service Splice Test Criteria," one additional production test shall be performed on the same lot of splices. This additional production test shall consist of testing 4 samples splices that have been randomly selected by the Engineer and removed by the Contractor from the actual completed lot of splices. Should any of the 4 splices from this additional test fail to conform to these provisions, all splices in the lot represented by these production tests will be rejected.

• If only one sample splice from a production test conforms to the provisions in this Section 52-1.08C(2), "Service Splice Test Criteria," all splices in the lot represented by this production test will be rejected.

• If a production test for a lot fails, the Contractor shall repair or replace all reinforcing bars from which sample splices were removed before the Engineer selects additional splices from this lot for further testing.

52-1.08C(2)(b) Quality Assurance Test Requirements for Service Splices

• For the first production test performed, and for at least one, randomly selected by the Engineer, of every 5 subsequent production tests, or portion thereof, the Contractor shall concurrently prepare 4 additional service quality assurance sample splices. These service quality assurance sample splices shall be prepared in the same manner as specified herein for service production sample splices.

• These 4 additional quality assurance sample splices shall be shipped to the Transportation Laboratory for quality assurance testing. The 4 sample splices shall be securely bundled together and identified by location and contract number with weatherproof markings before shipment. Bundles containing fewer than 4 samples of splices will not be tested. Sample splices not accompanied by the supporting documentation required in Section 52-1.08B(1), for mechanical splices, or in Section 52-1.08B(3), for resistance butt welds, will not be tested.

• Quality assurance testing will be performed in conformance with the requirements for service production sample splices in Section 52-1.08C(2)(a), "Production Test Requirements for Service Splices."

52-1.08C(3) Ultimate Butt Splice Test Criteria

• Ultimate production and quality assurance sample splices shall be tensile tested in conformance with the requirements described in ASTM Designation: A 370 and California Test 670.

• A minimum of one control bar shall be removed from the same bar as, and adjacent to, all ultimate production, and quality assurance sample splices. Control bars shall be 1) a minimum length of one meter for reinforcing bars No. 25 or smaller and 1.5 meters for reinforcing bars No. 29 or larger, and 2) suitably identified before shipment with weatherproof markings that do not interfere with the Engineer's tamper-proof markings or seals. The portion of adjacent bar remaining in the work shall also be identified with weatherproof markings that correspond to its adjacent control bar.

• Each sample splice and its associated control bar shall be identified and marked as a set. Each set shall be identified as representing a prequalification, production, or quality assurance sample splice.

- The portion of hoop reinforcing bar, removed to obtain a sample splice and control bar, shall be replaced using a prequalified ultimate mechanical butt splice, or the hoop shall be replaced in kind.
- Reinforcing bars, other than hoops, from which sample splices are removed, shall be repaired using ultimate mechanical butt splices conforming to the provisions in Section 52-1.08C(1), "Splice Prequalification Report," or the bars shall be replaced in kind. These bars shall be repaired or replaced such that no splices are located in any "No Splice Zone" shown on the plans.
- Ultimate production and quality assurance sample splices shall rupture in the reinforcing bar either: 1) outside of the affected zone or 2) within the affected zone, provided that the sample splice has achieved at least 95 percent of the ultimate tensile strength of the control bar associated with the sample splice. In addition, necking of the bar shall be visibly evident at rupture regardless of whether the bar breaks inside or outside the affected zone.
- The affected zone is the portion of the reinforcing bar where any properties of the bar, including the physical, metallurgical, or material characteristics, have been altered by fabrication or installation of the splice.
- The ultimate tensile strength shall be determined for all control bars by tensile testing the bars to rupture, regardless of where each sample splice ruptures. If 2 control bars are tested for one sample splice, the bar with the lower ultimate tensile strength shall be considered the control bar.

52-1.08C(3)(a) Production Test Requirements for Ultimate Butt Splices

- Production tests shall be performed for all ultimate butt splices used in the work. A production test shall consist of testing 4 sets of sample splices and control bars removed from each lot of completed splices, except when quality assurance tests are performed.
- After the splices in a lot have been completed, and the bars have been epoxy-coated when required, the QCM shall notify the Engineer in writing that the splices in this lot conform to the specifications and are ready for testing. Except for hoops, sample splices will be selected by the Engineer at the job site. Sample splices for hoops will be selected by the Engineer either at the job site or a fabrication facility.
- After notification has been received, the Engineer will randomly select the 4 sample splices to be removed from the lot and place tamper-proof markings or seals on them. The Contractor shall select the adjacent control bar for each sample splice bar, and the Engineer will place tamper-proof markings or seals on them. These ultimate production sample splices and control bars shall be removed by the Contractor, and tested by an independent qualified testing laboratory.
- At least one week before testing, the Contractor shall notify the Engineer in writing of the date when and the location where the testing of the samples will be performed.
- A sample splice or control bar from any set will be rejected if a tamper-proof marking or seal is disturbed before testing.
- The 4 sets from each production test shall be securely bundled together and identified with a completed sample identification card before shipment to the independent laboratory. The card will be furnished by the Engineer. Bundles of samples containing fewer than 4 sets of splices shall not be tested.
- Before performing any tensile tests on production test sample splices, one of the 4 sample splices shall be tested for, and shall conform to, the requirements for total slip. Should this sample splice not meet these requirements, one retest, in which the 3 remaining sample splices are tested for total slip, will be allowed. Should any of the 3 remaining sample splices not conform to these requirements, all splices in the lot represented by this production test will be rejected.
- If 3 or more sample splices from a production test conform to the provisions in Section 52-1.08C(3), "Ultimate Butt Splice Test Criteria," all splices in the lot represented by this production test will be considered acceptable.
- Should only 2 sample splices from a production test conform to the provisions in Section 52-1.08C(3), "Ultimate Butt Splice Test Criteria," one additional production test shall be performed on the same lot of splices. Should any of the 4 sample splices from this additional test fail to conform to these provisions, all splices in the lot represented by these production tests will be rejected.
- If only one sample splice from a production test conforms to the provisions in Section 52-1.08C(3), "Ultimate Butt Splice Test Criteria," all splices in the lot represented by this production test will be rejected.
- If a production test for a lot fails, the Contractor shall repair or replace all reinforcing bars from which sample splices were removed, complete in place, before the Engineer selects additional splices from this lot for further testing.
- Production tests will not be required on repaired splices from a lot, regardless of the type of prequalified ultimate mechanical butt splice used to make the repair. However, should an additional production test be required, the Engineer may select any repaired splice for the additional production test.

52-1.08C(3)(b) Quality Assurance Test Requirements for Ultimate Butt Splices

- For the first production test performed, and for at least one, randomly selected by the Engineer, of every 5 subsequent production tests, or portion thereof, the Contractor shall concurrently prepare 4 additional ultimate quality assurance sample splices along with associated control bars.
- Each time 4 additional ultimate quality assurance sample splices are prepared, 2 of these quality assurance sample splice and associated control bar sets and 2 of the production sample splice and associated control bar sets, together, shall

conform to the requirements for ultimate production sample splices in Section 52-1.08C(3)(a),"Production Test Requirements for Ultimate Butt Splices."

- The 2 remaining quality assurance sample splice and associated control bar sets, along with the 2 remaining production sample splice and associated control bar sets shall be shipped to the Transportation Laboratory for quality assurance testing. The 4 sets shall be securely bundled together and identified by location and contract number with weatherproof markings before shipment. Bundles containing fewer than 4 sets will not be tested.
- Quality assurance testing will be performed in conformance with the requirements for ultimate production sample splices in Section 52-1.08C(3)(a), "Production Test Requirements for Ultimate Butt Splices."

52-1.08C(3)(c) Nondestructive Splice Tests

- When the specifications allow for welded sample splices to be taken from other than the completed lot of splices, the Contractor shall meet the following additional requirements.
- Except for resistance butt welded splices, radiographic examinations shall be performed on 25 percent of all complete joint penetration butt welded splices from a production lot. The size of a production lot will be a maximum of 150 splices. The Engineer will select the splices which will compose the production lot and also the splices within each production lot to be radiographically examined.
- All required radiographic examinations of complete joint penetration butt welded splices shall be performed by the Contractor in conformance with the requirements in AWS D 1.4 and these specifications.
- Before radiographic examination, welds shall conform to the requirements in Section 4.4, "Quality of Welds," of AWS D 1.4.
- Should more than 12 percent of the splices which have been radiographically examined in any production lot be defective, an additional 25 percent of the splices, selected by the Engineer from the same production lot, shall be radiographically examined. Should more than 12 percent of the cumulative total of splices tested from the same production lot be defective, all remaining splices in the lot shall be radiographically examined.
- Additional radiographic examinations performed due to the identification of defective splices shall be at the Contractor's expense.
- All defects shall be repaired in conformance with the requirements in AWS D 1.4.
- The Contractor shall notify the Engineer in writing 48 hours before performing any radiographic examinations.
- The radiographic procedure used shall conform to the requirements in AWS D1.1, AWS D1.4, and the following:

Two exposures shall be made for each complete joint penetration butt welded splice. For each of the 2 exposures, the radiation source shall be centered on each bar to be radiographed. The first exposure shall be made with the radiation source placed at zero degrees from the top of the weld and perpendicular to the weld root and identified with a station mark of "0." The second exposure shall be at 90 degrees to the "0" station mark and shall be identified with a station mark of "90." When obstructions prevent a 90 degree placement of the radiation source for the second exposure, and when approved in writing by the Engineer, the source may be rotated, around the centerline of the reinforcing bar, a maximum of 25 degrees.

For field produced complete joint penetration butt welds, no more than one weld shall be radiographed during one exposure. For shop produced complete joint penetration butt welds, if more than one weld is to be radiographed during one exposure, the angle between the root line of each weld and the direction to the radiation source shall be not less than 65 degrees.

Radiographs shall be made by either X-ray or gamma ray. Radiographs made by X-ray or gamma rays shall have densities of not less than 2.3 nor more than 3.5 in the area of interest. A tolerance of 0.05 in density is allowed for densitometer variations. Gamma rays shall be from the iridium 192 isotope and the emitting specimen shall not exceed 4.45 mm in the greatest diagonal dimension.

The radiographic film shall be placed perpendicular to the radiation source at all times; parallel to the root line of the weld unless source placement determines that the film must be turned; and as close to the root of the weld as possible.

The minimum source to film distance shall be maintained so as to ensure that all radiographs maintain a maximum geometric unsharpness of 0.020 at all times, regardless of the size of the reinforcing bars.

Penetrameters shall be placed on the source side of the bar and perpendicular to the radiation source at all times. One penetrameter shall be placed in the center of each bar to be radiographed, perpendicular to the weld root, and adjacent to the weld. Penetrameter images shall not appear in the weld area.

When radiography of more than one weld is being performed per exposure, each exposure shall have a minimum of one penetrameter per bar, or 3 penetrameters per exposure. When 3 penetrameters per exposure are used, one penetrameter shall be placed on each of the 2 outermost bars of the exposure, and the remaining penetrameter shall be placed on a centrally located bar.

An allowable weld buildup of 4 mm may be added to the total material thickness when determining the proper penetrameter selection. No image quality indicator equivalency will be accepted. Wire penetrameters or penetrameter blocks shall not be used.

Penetrameters shall be sufficiently shimmed using a radiographically identical material. Penetrameter image densities shall be a minimum of 2.0 and a maximum of 3.6.

Radiographic film shall be Class 1, regardless of the size of reinforcing bars.

Radiographs shall be free of film artifacts and processing defects, including, but not limited to, streaks, scratches, pressure marks or marks made for the purpose of identifying film or welding indications.

Each splice shall be clearly identified on each radiograph and the radiograph identification and marking system shall be established between the Contractor and the Engineer before radiographic inspection begins. Film shall be identified by lead numbers only; etching, flashing or writing in identifications of any type will not be permitted. Each piece of film identification information shall be legible and shall include, as a minimum, the following information: Contractor's name, date, name of nondestructive testing firm, initials of radiographer, contract number, part number and weld number. The letter "R" and repair number shall be placed directly after the weld number to designate a radiograph of a repaired weld.

Radiographic film shall be developed within a time range of one minute less to one minute more than the film manufacturer's recommended maximum development time. Sight development will not be allowed.

Processing chemistry shall be done with a consistent mixture and quality, and processing rinses and tanks shall be clean to ensure proper results. Records of all developing processes and any chemical changes to the developing processes shall be kept and furnished to the Engineer upon request. The Engineer may request, at any time, that a sheet of unexposed film be processed in the presence of the Engineer to verify processing chemical and rinse quality.

The results of all radiographic interpretations shall be recorded on a signed certification and a copy kept with the film packet.

Technique sheets prepared in conformance with the requirements in ASME Boiler and Pressure Vessels Code, Section V, Article 2 Section T-291 shall also contain the developer temperature, developing time, fixing duration and all rinse times.

52-1.08D Reporting Test Results

- A Production Test Report for all testing performed on each lot shall be prepared by the independent testing laboratory performing the testing and submitted to the QCM for review and approval. The report shall be signed by an engineer who represents the laboratory and is registered as a Civil Engineer in the State of California. The report shall include, as a minimum, the following information for each test: contract number, bridge number, lot number and location, bar size, type of splice, length of mechanical splice, length of test specimen, physical condition of test sample splice and any associated control bar, any notable defects, total measured slip, ultimate tensile strength of each splice, and for ultimate butt splices, limits of affected zone, location of visible necking area, ultimate tensile strength and 95 percent of this ultimate tensile strength for each control bar, and a comparison between 95 percent of the ultimate tensile strength of each control bar and the ultimate tensile strength of its associated splice.
- The QCM must review, approve, and forward each Production Test Report to the Engineer for review before the splices represented by the report are encased in concrete. The Engineer will have 3 working days to review each Production Test Report and respond in writing after a complete report has been received. Should the Contractor elect to encase any splices before receiving notification from the Engineer, it is expressly understood that the Contractor will not be relieved of the responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase splices pending notification by the Engineer, and in the event the Engineer fails to complete the review and provide notification within the time allowed, and if, in the opinion of the Engineer, the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."
- Quality assurance test results for each bundle of 4 sets or 4 samples of splices will be reported in writing to the Contractor within 3 working days after receipt of the bundle by the Transportation Laboratory. In the event that more than one bundle is received on the same day, 2 additional working days shall be allowed for providing test results for each additional bundle received. A test report will be made for each bundle received. Should the Contractor elect to encase splices before receiving notification from the Engineer, it is expressly understood that the Contractor will not be relieved of the responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase splices pending notification by the Engineer, and in the event the Engineer fails to complete the review within the time allowed, and in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

SECTION 55: STEEL STRUCTURES

Issue Date: December 31, 2001

Section 55-3.14, "Bolted Connections," of the Standard Specifications is amended by adding the following after the ninth paragraph:

- If a torque multiplier is used in conjunction with a calibrated wrench as a method for tightening fastener assemblies to the required tension, both the multiplier and the wrench shall be calibrated together as a system. The same length input and output sockets and extensions that will be used in the work shall also be included in the calibration of the system. The manufacturer's torque multiplication ratio shall be adjusted during calibration of the system, such that when this adjusted ratio is multiplied by the actual input calibrated wrench reading, the product is a calculated output torque that is within 2 percent of the true output torque. When this system is used in the work to perform any installation tension testing, rotational capacity testing, fastener tightening, or tension verification, it shall be used, intact as calibrated.

The sixth paragraph of Section 55-4.02, "Payment," of the Standard Specifications is amended to read:

- If a portion or all of the structural steel is fabricated more than 480 air line kilometers from both Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impracticable and extremely difficult to ascertain and determine the actual increase in these expenses, it is agreed that payment to the Contractor for furnishing the structural steel from each fabrication site located more than 480 air line kilometers from both Sacramento and Los Angeles will be reduced $5000 or by an amount computed at $0.044 per kilogram of structural steel fabricated, whichever is greater, or in the case of each fabrication site located more than 4800 air line kilometers from both Sacramento and Los Angeles, payment will be reduced $8000 or by $0.079 per kilogram of structural steel fabricated, whichever is greater.

SECTION 56: SIGNS

Issue Date: December 31, 2001

Section 56-1.01, "Description," of the Standard Specifications is amended by deleting the third paragraph.

The sixth through the thirteenth paragraphs in Section 56-1.03, "Fabrication," of the Standard Specifications are amended to read:

- High-strength bolted connections, where shown on the plans, shall conform to the provisions in Section 55-3.14, "Bolted Connections," except that only fastener assemblies consisting of a high-strength bolt, nut, hardened washer, and direct tension indicator shall be used.
- High-strength fastener assemblies, and any other bolts, nuts, and washers attached to sign structures shall be zinc-coated by the mechanical deposition process.
- An alternating snugging and tensioning pattern for anchor bolts and high-strength bolted splices shall be used. Once tensioned, high-strength fastener components and direct tension indicators shall not be reused.
- For bolt diameters less than 10 mm, the diameter of the bolt hole shall be not more than 0.80-mm larger than the nominal bolt diameter. For bolt diameters greater than or equal to 10 mm, the diameter of the bolt hole shall be not more than 1.6 mm larger than the nominal bolt diameter.
- Sign structures shall be fabricated into the largest practical sections prior to galvanizing.
- Ribbed sheet metal panels for box beam closed truss sign structures shall be fastened to the truss members by cap screws or bolts as shown on the plans, or by 4.76 mm stainless steel blind rivets conforming to Industrial Fasteners Institute, Standard IFI-114, Grade 51. The outside diameter of the large flange rivet head shall be not less than 15.88 mm in diameter. Web splices in ribbed sheet metal panels may be made with similar type blind rivets of a size suitable for the thickness of material being connected.
- Spalling or chipping of concrete structures shall be repaired by the Contractor at the Contractor's expense.
- Overhead sign supports shall have an aluminum identification plate permanently attached near the base, adjacent to the traffic side on one of the vertical posts, using either stainless steel rivets or stainless steel screws. As a minimum, the information on the plate shall include the name of the manufacturer, the date of manufacture and the contract number.

SECTION 59: PAINTING

Issue Date: December 31, 2001

Section 59-2.01, "General," of the Standard Specifications is amended by adding the following paragraphs after the first paragraph:

• Unless otherwise specified, no painting Contractors or subcontractors will be permitted to commence work without having the following current "SSPC: The Society for Protective Coatings" (formerly the Steel Structures Painting Council) certifications in good standing:

A. For cleaning and painting structural steel in the field, certification in conformance with the requirements in Qualification Procedure No. 1, "Standard Procedure For Evaluating Painting Contractors (Field Application to Complex Industrial Structures)" (SSPC-QP 1).
B. For removing paint from structural steel, certification in conformance with the requirements in Qualification Procedure No. 2, "Standard Procedure For Evaluating Painting Contractors (Field Removal of Hazardous Coatings from Complex Structures)" (SSPC-QP 2).
C. For cleaning and painting structural steel in a permanent painting facility, certification in conformance with the requirements in Qualification Procedure No. 3, "Standard Procedure For Evaluating Qualifications of Shop Painting Applicators" (SSPC-QP 3). The AISC's Sophisticated Paint Endorsement (SPE) quality program will be considered equivalent to SSPC-QP 3.

The third paragraph of Section 59-2.03, "Blast Cleaning," of the Standard Specifications is amended to read:

• Exposed steel or other metal surfaces to be blast cleaned shall be cleaned in conformance with the requirements in Surface Preparation Specification No. 6, "Commercial Blast Cleaning," of the "SSPC: The Society for Protective Coatings." Blast cleaning shall leave all surfaces with a dense, uniform, angular anchor pattern of not less than 35 µm as measured in conformance with the requirements in ASTM Designation: D 4417.

The first paragraph of Section 59-2.06, "Hand Cleaning," of the Standard Specifications is amended to read:

• Dirt, loose rust and mill scale, or paint which is not firmly bonded to the surfaces shall be removed in conformance with the requirements in Surface Preparation Specification No. 2, "Hand Tool Cleaning," of the "SSPC: The Society for Protective Coatings." Edges of old remaining paint shall be feathered.

The fourth paragraph of Section 59-2.12, "Painting," of the Standard Specifications is amended to read:

• The dry film thickness of the paint will be measured in place with a calibrated Type 2 magnetic film thickness gage in conformance with the requirements of specification SSPC-PA2 of the "SSPC: The Society for Protective Coatings."

SECTION 75: MISCELLANEOUS METAL

Issue Date: December 31, 2001

The table in the tenth paragraph of Section 75-1.02, "Miscellaneous Iron and Steel," of the Standard Specifications is amended to read:

Material	Specification
Steel bars, plates and shapes	ASTM Designation: A 36/A 36M or A 575, A 576 (AISI or M Grades 1016 through 1030 except Grade 1017)
Steel fastener components for general applications:	
Bolts and studs	ASTM Designation: A 307
Headed anchor bolts	ASTM Designation: A 307, Grade B, including S1 supplementary requirements
Nonheaded anchor bolts	ASTM Designation: A 307, Grade C, including S1 supplementary requirements and S1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements
High-strength bolts and studs, threaded rods, and nonheaded anchor bolts	ASTM Designation: A 449, Type 1
Nuts	ASTM Designation: A 563, including Appendix X1*
Washers	ASTM Designation: F 844
Components of high-strength steel fastener assemblies for use in structural steel joints:	
Bolts	ASTM Designation: A 325, Type 1
Tension control bolts	ASTM Designation: F 1852, Type 1
Nuts	ASTM Designation: A 563, including Appendix X1*
Hardened washers	ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements
Direct tension indicators	ASTM Designation: F 959, Type 325, zinc-coated
Stainless steel fasteners (Alloys 304 & 316) for general applications:	
Bolts, screws, studs, threaded rods, and nonheaded anchor bolts	ASTM Designation: F 593 or F 738M
Nuts	ASTM Designation: F 594 or F 836M
Washers	ASTM Designation: A 240/A 240M and ANSI B 18.22M
Carbon-steel castings	ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1
Malleable iron castings	ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010
Gray iron castings	ASTM Designation: A 48, Class 30B
Ductile iron castings	ASTM Designation: A 536, Grade 65-45-12
Cast iron pipe	Commercial quality
Steel pipe	Commercial quality, welded or extruded
Other parts for general applications	Commercial quality

* Zinc-coated nuts that will be tightened beyond snug or wrench tight shall be furnished with a dyed dry lubricant conforming to Supplementary Requirement S2 in ASTM Designation: A 563.

The table in the eighteenth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Stud Diameter (millimeters)	Sustained Tension Test Load (kilonewtons)
29.01-33.00	137.9
23.01-29.00	79.6
21.01-23.00	64.1
* 18.01-21.00	22.2
15.01-18.00	18.2
12.01-15.00	14.2
9.01-12.00	9.34
6.00-9.00	4.23

* Maximum stud diameter permitted for mechanical expansion anchors.

The table in the nineteenth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Stud Diameter (millimeters)	Ultimate Tensile Load (kilonewtons)
30.01-33.00	112.1
27.01-30.00	88.1
23.01-27.00	71.2
20.01-23.00	51.6
16.01-20.00	32.0
14.01-16.00	29.4
12.00-14.00	18.7

The table in the twenty-second paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Installation Torque Values, (newton meters)

Stud Diameter (millimeters)	Shell Type Mechanical Expansion Anchors	Integral Stud Type Mechanical Expansion Anchors	Resin Capsule Anchors and Cast-in-Place Inserts
29.01-33.00	—	—	540
23.01-29.00	—	—	315
21.01-23.00	—	—	235
18.01-21.00	110	235	200
15.01-18.00	45	120	100
12.01-15.00	30	65	40
9.01-12.00	15	35	24
6.00-9.00	5	10	—

SECTION 83: RAILINGS AND BARRIERS

Issue Date: June 13, 2002

The ninth paragraph in Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications is amended to read:

- The grades and species of wood posts and blocks shall be No. 1 timbers (also known as No. 1 structural) Douglas fir or No. 1 timbers Southern yellow pine. Wood posts and blocks shall be graded in conformance with the provisions in Section 57-2, "Structural Timber," of the Standard Specifications, except allowances for shrinkage after mill cutting shall in no case exceed 5 percent of the American Lumber Standards minimum sizes, at the time of installation.

The eleventh paragraph in Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications is amended to read:

- Wood posts and blocks shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications with creosote, creosote coal tar solution, creosote petroleum solution (50-50), pentachlorophenol in hydrocarbon solvent, copper naphthenate, ammoniacal copper arsenate, or ammoniacal copper zinc arsenate. In addition to the preservatives listed above, Southern yellow pine may also be pressure treated with chromated copper arsenate. When other than one of the creosote processes is used, blocks shall have a minimum retention of 6.4 Kg/m^3, and need not be incised.

SECTION 85: PAVEMENT MARKERS

Issue Date: May 16, 2003

The second through fifth paragraphs in Section 85-1.03, "Sampling, Tolerances and Packaging," of the Standard Specifications are amended to read:

Sampling

- Twenty markers selected at random will constitute a representative sample for each lot of markers.
- The lot size shall not exceed 25000 markers.

Tolerances

- Three test specimens will be randomly selected from the sample for each test and tested in conformance with these specifications. Should any one of the 3 specimens fail to conform with the requirements in these specifications, 6 additional specimens will be tested. The failure of any one of these 6 specimens shall be cause for rejection of the entire lot or shipment represented by the sample.
- The entire sample of retroreflective pavement markers will be tested for reflectance. The failure of 10 percent or more of the original sampling shall be cause for rejection.

Section 85-1.04, "Non-Reflective Pavement Markers," of the Standard Specifications is amended to read:

85-1.04 Non-Reflective Pavement Markers

- Non-reflective pavement markers (Types A and AY) shall be, at the option of the Contractor, either ceramic or plastic conforming to these specifications.
- The top surface of the marker shall be convex with a gradual change in curvature. The top, bottom and sides shall be free of objectionable marks or discoloration that will affect adhesion or appearance.
- The bottom of markers shall have areas of integrally formed protrusions or indentations, which will increase the effective bonding surface area of adhesive. The bottom surface of the marker shall not deviate more than 1.5 mm from a flat surface. The areas of protrusion shall have faces parallel to the bottom of the marker and shall project approximately one mm from the bottom.

The second through fourth paragraphs of Section 85-1.04A, "Non-Reflective Pavement Markers (Ceramic)," of the Standard Specifications are deleted.

The table in the fifth paragraph in Section 85-1.04A, "Non-Reflective Pavement Markers (Ceramic)," of the Standard Specifications is amended to read:

Testing

- Tests shall be performed in conformance with the requirements in California Test 669.

Test	Test Description	Requirement
a	Bond strength	4.8 MPa, min.
b	Glaze thickness	180 µm, min.
c	Hardness	6 Moh, min.
d	Luminance factor, Type A, white markers only, glazed surface	75, min.
e	Yellowness index, Type A, white markers only, glazed surface	7, max.
f	Color-yellow, Type AY, yellow markers only. The chromaticity coordinates shall be within a color box defined in CTM 669	Pass
g	Compressive strength	6700 N, min.
h	Water absorption	2.0 %, max.
i	Artificial weathering, 500 hours exposure, yellowness index	20, max.

Section 85-1.04B, "Non-Reflective Pavement Markers (Plastic)," of the Standard Specifications is amended to read:

85-1.04B Non-Reflective Pavement Markers (Plastic)

- Plastic non-reflective pavement markers Types A and AY shall be, at the option of the Contractor, either polypropylene or acrylonitrile-butadiene-styrene (ABS) plastic type.
- Plastic markers shall conform to the testing requirements specified in Section 85-1.04A, "Non-Reflective Pavement Markers (Ceramic)," except that Tests a, b, c, and h shall not apply. The plastic markers shall not be coated with substances that interfere with the ability of the adhesive bonding to the marker.

The sixth and seventh paragraphs in Section 85-1.05, "Retroreflective Pavement Markers," of the Standard Specifications are amended to read:

Testing

- Tests shall be performed in conformance with the requirements in California Test 669.

Test Description	Requirement		
Bond strength[a]	3.4 MPa, min.		
Compressive strength[b]	8900 N, min.		
Abrasion resistance, marker must meet the respective specific intensity minimum requirements after abrasion.	Pass		
Water Soak Resistance	No delamination of the body or lens system of the marker nor loss of reflectance		
	Specific Intensity		
Reflectance	Clear	Yellow	Red
0° Incidence Angle, min.	3.0	1.5	0.75
20° Incidence Angle, min.	1.2	0.60	0.30
After one year field evaluation	0.30	0.15	0.08

a Failure of the marker body or filler material prior to reaching 3.4 MPa shall constitute a failing bond strength test.
b Deformation of the marker of more than 3 mm at a load of less than 8900 N or delamination of the shell and the filler material of more than 3 mm regardless of the load required to break the marker shall be cause for rejection of the markers as specified in Section 85-1.03, "Sampling, Tolerances and Packaging."

- Pavement markers to be placed in pavement recesses shall conform to the above requirements for retroreflective pavement markers except that the minimum compressive strength requirement shall be 5338 N.

The eighth paragraph of Section 85-1.05, "Retrorelective Pavement Markers" of the Standard Specifications is deleted.

The eighth paragraph in Section 85-1.06, "Replacement," of the Standard Specifications is amended to read:

- Epoxy adhesive shall not be used to apply non-reflective plastic pavement markers.

SECTION 86: SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS

Issue Date: June 19, 2003

The seventh paragraph of Section 86-2.03, "Foundations," of the Standard Specifications is amended to read:

- Forms shall be true to line and grade. Tops of foundations for posts and standards, except special foundations, shall be finished to curb or sidewalk grade or as directed by the Engineer. Forms shall be rigid and securely braced in place. Conduit ends and anchor bolts shall be placed in proper position and to proper height, and anchor bolts shall be held in place by means of rigid top and bottom templates. The bottom template shall be made of steel. The bottom template shall provide proper spacing and alignment of the anchor bolts near their bottom embedded end. The bottom template shall be installed before placing footing concrete. Anchor bolts shall not be installed more than 1:40 from vertical.

Section 86-2.03, "Foundations," of the Standard Specifications is amended by deleting the eighth paragraph.

The twelfth paragraph of Section 86-2.03, "Foundations," of the Standard Specifications is amended to read:

- Plumbing of the standards shall be accomplished by adjusting the leveling nuts before placing the mortar or before the foundation is finished to final grade. Shims, or other similar devices shall not be used for plumbing or raking of posts, standards or pedestals. After final adjustments of both top nuts and leveling nuts on anchorage assemblies have been made, firm contact shall exist between all bearing surfaces of the anchor bolt nuts, washers, and the base plate.

The first paragraph of Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications is amended to read:

- Standards for traffic signals and lighting, and steel pedestals for cabinets and other similar equipment, shall be located as shown on the plans. Bolts, nuts and washers, and anchor bolts for use in signal and lighting support structures shall conform to the provisions in Section 55-2, "Materials." Except when bearing-type connections or slipbases are specified, high-strength bolted connections shall conform to the provisions in Section 55-3.14, "Bolted Connections." Welding, nondestructive testing (NDT) of welds, and acceptance and repair criteria for NDT of steel members shall conform to the requirements of AWS D1.1 and the contract special provisions.

The second paragraph of Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications is amended to read:

- On each lighting standard except Type 1, one rectangular corrosion resistant metal identification tag shall be permanently attached above the hand hole, near the base of the standard, using stainless steel rivets. On each signal pole support, two corrosion resistant metal identification tags shall be attached, one above the hand hole near the base of the vertical standard and one on the underside of the signal mast arm near the arm plate. As a minimum, the information on each identification tag shall include the name of the manufacturer, the date of manufacture, the identification number as shown on the plans, the contract number, and a unique identification code assigned by the fabricator. This number shall be traceable to a particular contract and the welds on that component, and shall be readable after the support structure is coated and installed. The lettering shall be a minimum of 7 mm high. The information may be either depressed or raised, and shall be legible.

The fourth paragraph of Section 86-2.04, "Standards, Steel Pedestals and Posts" of the Standard Specifications is amended to read:

- Ferrous metal parts of standards, with shaft length of 4.6 m and longer, shall conform to the details shown on the plans, the provisions in Section 55, "Steel Structures," except as otherwise noted, and the following requirements:

  Except as otherwise specified, standards shall be fabricated from sheet steel of weldable grade having a minimum yield strength, after fabrication, of 276 MPa.

  Certified test reports which verify conformance to the minimum yield strength requirements shall be submitted to the Engineer. The test reports may be the mill test reports for the as-received steel or, when the as-received steel has a

lower yield strength than required, the Contractor shall provide supportive test data which provides assurance that the Contractor's method of cold forming will consistently increase the tensile properties of the steel to meet the specified minimum yield strength. The supportive test data shall include tensile properties of the steel after cold forming for specific heats and thicknesses.

When a single-ply 8-mm thick pole is specified, a 2-ply pole with equivalent section modulus may be substituted.

Standards may be fabricated of full-length sheets or shorter sections. Each section shall be fabricated from not more than 2 pieces of sheet steel. Where 2 pieces are used, the longitudinal welded seams shall be directly opposite one another. When the sections are butt-welded together, the longitudinal welded seams on adjacent sections shall be placed to form continuous straight seams from base to top of standard.

Butt-welded circumferential joints of tubular sections requiring CJP groove welds shall be made using a metal sleeve backing ring inside each joint. The sleeve shall be 3-mm nominal thickness, or thicker, and manufactured from steel having the same chemical composition as the steel in the tubular sections to be joined. When the sections to be joined have different specified minimum yield strengths, the steel in the sleeve shall have the same chemical composition as the tubular section having the higher minimum yield strength. The width of the metal sleeve shall be consistent with the type of NDT chosen and shall be a minimum width of 25 mm. The sleeve shall be centered at the joint and be in contact with the tubular section at the point of the weld at time of fit-up.

Welds shall be continuous.

The weld metal at the transverse joint shall extend to the sleeve, making the sleeve an integral part of the joint.

During fabrication, longitudinal seams on vertical tubular members of cantilevered support structures shall be centered on and along the side of the pole that the pole plate is located. Longitudinal seams on horizontal tubular members, including signal and luminaire arms, shall be within +/-45 degrees of the bottom of the arm.

The longitudinal welds in steel tubular sections may be made by the electric resistance welding process.

Longitudinal seam welds shall have 60 percent minimum penetration, except that within 150 mm of circumferential welds, longitudinal seam welds shall be CJP groove welds. In addition, longitudinal seam welds on lighting support structures having telescopic pole segment splices shall be CJP groove welds on the female end for a length on each end equal to the designated slip fit splice length plus 150 mm.

Exposed circumferential welds, except fillet and fatigue-resistant welds, shall be ground flush (-0, +2mm) with the base metal prior to galvanizing or painting.

Circumferential welds and base plate-to-pole welds may be repaired only one time without written permission from the Engineer.

Exposed edges of the plates that make up the base assembly shall be finished smooth and exposed corners of the plates shall be broken unless otherwise shown on the plans. Shafts shall be provided with slip-fitter shaft caps.

Flatness of surfaces of 1) base plates that are to come in contact with concrete, grout, or washers and leveling nuts 2) plates in high-strength bolted connections, 3) plates in joints where cap screws are used to secure luminaire and signal arms, and 4) plates used for breakaway slip base assemblies shall conform to the requirements of ASTM A6.

Standards shall be straight, with a permissive variation not to exceed 25 mm measured at the midpoint of a 9-m or 11-m standard and not to exceed 20 mm measured at the midpoint of a 5-m through 6-m standard. Variation shall not exceed 25 mm at a point 4.5 m above the base plate for Type 35 and Type 36 standards.

Zinc-coated nuts used on fastener assemblies having a specified preload (obtained by specifying a prescribed tension, torque value, or degree of turn) shall be provided with a colored lubricant that is clean and dry to the touch. The color of the lubricant shall be in contrast to the zinc coating on the nut so that the presence of the lubricant is visually obvious. In addition, either the lubricant shall be insoluble in water, or fastener components shall be shipped to the job site in a sealed container.

No holes shall be made in structural members unless the holes are shown on the plans or are approved in writing by the Engineer.

Standards with an outside diameter of 300 mm or less shall be round. Standards with an outside diameter greater than 300 mm shall be round or multisided. Multisided standards shall have a minimum of 12 sides which shall be convex and shall have a minimum bend radius of 100 mm.

Mast arms for standards shall be fabricated from material as specified for standards, and shall conform to the dimensions shown on the plans.

The cast steel option for slip bases shall be fabricated from material conforming to the requirements in ASTM Designation: A 27/A 27M, Grade 70-40. Other comparable material may be used if written permission is given by the Engineer. The casting tolerances shall be in conformance with the Steel Founder's Society of America recommendations (green sand molding).

One casting from each lot of 50 castings or less shall be subject to radiographic inspection, in conformance with the requirements in ASTM Designation: E 94. The castings shall comply with the acceptance criteria severity level 3 or better for the types and categories of discontinuities in conformance with the requirements in ASTM Designations: E 186 and E 446. If the one casting fails to pass the inspection, 2 additional castings shall be radiographed. Both of these castings shall pass the inspection or the entire lot of 50 will be rejected.

Material certifications, consisting of physical and chemical properties, and radiographic films of the castings shall be filed at the manufacturer's office. These certifications and films shall be available for inspection upon request.

High-strength bolts, nuts and flat washers used to connect slip base plates shall conform to the requirements in ASTM Designation: A 325 or A 325M and shall be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing."

Plate washers shall be fabricated by saw cutting and drilling steel plate conforming to the requirements in AISI Designation: 1018, and be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing." Prior to galvanizing, burrs and sharp edges shall be removed and holes shall be chamfered sufficiently on each side to allow the bolt head to make full contact with the washer without tension on the bolt.

High-strength cap screws shown on the plans for attaching arms to standards shall conform to the requirements in ASTM Designation: A 325, A 325M or ASTM Designation: A 449, and shall comply with the mechanical requirements in ASTM Designation: A 325 or A 325M after galvanizing. The cap screws shall be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing." The threads of the cap screws shall be coated with a colored lubricant that is clean and dry to the touch. The color of the lubricant shall be in contrast to the color of the zinc coating on the cap screw so that presence of the lubricant is visually obvious. In addition, either the lubricant shall be insoluble in water, or fastener components shall be shipped to the job site in a sealed container.

Unless otherwise specified, bolted connections attaching signal or luminaire arms to poles shall be considered slip critical. Galvanized faying surfaces on plates on luminaire and signal arms and matching plate surfaces on poles shall be roughened by hand using a wire brush prior to assembly and shall conform to the requirements for Class C surface conditions for slip-critical connections in "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts," a specification approved by the Research Council on Structural Connections (RCSC) of the Engineering Foundation. For faying surfaces required to be painted, the paint shall be an approved type, brand, and thickness that has been tested and approved according to the RCSC Specification as a Class B coating.

Samples of fastener components will be randomly taken from each production lot by the Engineer and submitted, along with test reports required by appropriate ASTM fastener specifications, for QA testing and evaluation. Sample sizes for each fastener component shall be as determined by the Engineer.

The seventh paragraph of 86-2.04, "Standards, Steel Pedestals and Posts" of the Standard Specifications is amended to read:

- To avoid interference of arm plate-to-tube welds with cap screw heads, and to ensure cap screw heads can be turned using conventional installation tools, fabricators shall make necessary adjustments to details prior to fabrication and properly locate the position of arm tubes on arm plates during fabrication.

Section 86-8.01, "Payment," of the Standard Specifications is amended by adding the following paragraph after the first paragraph:

- If a portion or all of the poles for signal, lighting and electrical systems pursuant to Standard Specification Section 86, "Signals, Lighting and Electrical Systems," is fabricated more than 480 air line kilometers from both-Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impracticable and extremely difficult to ascertain and determine the actual increase in such expenses, it is agreed that payment to the Contractor for furnishing such items from each fabrication site located more than 480 air line kilometers from both Sacramento and Los Angeles will be reduced $5000; in addition, in the case where a fabrication site is located more than 4800 air line kilometers from both Sacramento and Los Angeles, payment will be reduced an additional $3000 per each fabrication site ($8000 total per site).

SECTION 88: ENGINEERING FABRIC

Issue Date: January 15, 2002

Section 88-1.02, "Pavement Reinforcing Fabric," of the Standard Specifications is amended to read:

- Pavement reinforcing fabric shall be 100 percent polypropylene staple fiber fabric material, needle-punched, thermally bonded on one side, and conform to the following:

Specification	Requirement
Weight, grams per square meter ASTM Designation: D 5261	140
Grab tensile strength (25-mm grip), kilonewtons, min. in each direction ASTM Designation: D 4632	0.45
Elongation at break, percent min. ASTM Designation: D 4632	50
Asphalt retention by fabric, grams per square meter. (Residual Minimum) ASTM Designation: D 6140	900

Note: Weight, grab, elongation and asphalt retention are based on Minimum Average Roll Value (MARV)

SECTION 90: PORTLAND CEMENT CONCRETE

Issue Date: June 19, 2003

Section 90, "Portland Cement Concrete," of the Standard Specifications is amended to read:

SECTION 90: PORTLAND CEMENT CONCRETE
90-1 GENERAL

90-1.01 DESCRIPTION

- Portland cement concrete shall be composed of cementitious material, fine aggregate, coarse aggregate, admixtures if used, and water, proportioned and mixed as specified in these specifications.
- The Contractor shall determine the mix proportions for concrete in conformance with these specifications. Unless otherwise specified, cementitious material shall be a combination of cement and mineral admixture. Cementitious material shall be either:

1. "Type IP (MS) Modified" cement; or
2. A combination of "Type II Modified" portland cement and mineral admixture; or
3. A combination of Type V portland cement and mineral admixture.

- Type III portland cement shall be used only as allowed in the special provisions or with the approval of the Engineer.
- Class 1 concrete shall contain not less than 400 kg of cementitious material per cubic meter.
- Class 2 concrete shall contain not less than 350 kg of cementitious material per cubic meter.
- Class 3 concrete shall contain not less than 300 kg of cementitious material per cubic meter.
- Class 4 concrete shall contain not less than 250 kg of cementitious material per cubic meter.
- Minor concrete shall contain not less than 325 kg of cementitious material per cubic meter unless otherwise specified in these specifications or the special provisions.
- Unless otherwise designated on the plans or specified in these specifications or the special provisions, the amount of cementitious material used per cubic meter of concrete in structures or portions of structures shall conform to the following:

Use	Cementitious Material Content (kg/m3)
Concrete designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min., 475 max.
Roof sections of exposed top box culverts	400 min., 475 max.
Other portions of structures	350 min., 475 max.
Concrete not designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min.
Roof sections of exposed top box culverts	400 min.
Prestressed members	400 min.
Seal courses	400 min.
Other portions of structures	350 min.
Concrete for precast members	350 min., 550 max.

- Whenever the 28-day compressive strength shown on the plans is greater than 25 MPa, the concrete shall be designated by compressive strength. If the plans show a 28-day compressive strength that is 28 MPa or greater, an additional 14 days will be allowed to obtain the specified strength. The 28-day compressive strengths shown on the plans that are 25 MPa or less are shown for design information only and are not a requirement for acceptance of the concrete.
- Concrete designated by compressive strength shall be proportioned such that the concrete will attain the strength shown on the plans or specified in the special provisions.
- Before using concrete for which the mix proportions have been determined by the Contractor, or in advance of revising those mix proportions, the Contractor shall submit in writing to the Engineer a copy of the mix design.
- Compliance with cementitious material content requirements will be verified in conformance with procedures described in California Test 518 for cement content. For testing purposes, mineral admixture shall be considered to be cement. Batch proportions shall be adjusted as necessary to produce concrete having the specified cementitious material content.
- If any concrete has a cementitious material, portland cement, or mineral admixture content that is less than the minimum required, the concrete shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State $0.55 for each kilogram of cementitious material, portland cement, or mineral admixture that is less than the minimum required. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract. The deductions will not be made unless the difference between the contents required and those actually provided exceeds the batching tolerances permitted by Section 90-5, "Proportioning." No deductions will be made based on the results of California Test 518.
- The requirements of the preceding paragraph shall not apply to minor concrete or commercial quality concrete.

90-2 MATERIALS

90-2.01 CEMENT

- Unless otherwise specified, cement shall be either "Type IP (MS) Modified" cement, "Type II Modified" portland cement or Type V portland cement.
- "Type IP (MS) Modified" cement shall conform to the requirements for Type IP (MS) cement in ASTM Designation: C 595, and shall be comprised of an intimate and uniform blend of Type II cement and not more than 35 percent by mass of mineral admixture. The type and minimum amount of mineral admixture used in the manufacture of "Type IP (MS) Modified" cement shall be in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."
- "Type II Modified" portland cement shall conform to the requirements for Type II portland cement in ASTM Designation: C 150.
- In addition, "Type IP (MS) Modified" cement and "Type II Modified" portland cement shall conform to the following requirements:

A. The cement shall not contain more than 0.60-percent by mass of alkalies, calculated as the percentage of Na_2O plus 0.658 times the percentage of K_2O, when determined by either direct intensity flame photometry or by the atomic absorption method. The instrument and procedure used shall be qualified as to precision and accuracy in conformance with the requirements in ASTM Designation: C 114;
B. The autoclave expansion shall not exceed 0.50-percent; and
C. Mortar, containing the cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not expand in water more than 0.010 percent and shall not contract in air more than 0.048 percent, except that

when cement is to be used for precast prestressed concrete piling, precast prestressed concrete members, or steam cured concrete products, the mortar shall not contract in air more than 0.053 percent.

- Type III and Type V portland cements shall conform to the requirements in ASTM Designation: C 150 and the additional requirements listed above for "Type II Modified" portland cement, except that when tested in conformance with California Test 527, mortar containing Type III portland cement shall not contract in air more than 0.075 percent.
- Cement used in the manufacture of cast-in-place concrete for exposed surfaces of like elements of a structure shall be from the same cement mill.
- Cement shall be protected from exposure to moisture until used. Sacked cement shall be piled to permit access for tally, inspection, and identification of each shipment.
- Adequate facilities shall be provided to assure that cement meeting the provisions specified in this Section 90-2.01 shall be kept separate from other cement in order to prevent any but the specified cement from entering the work. Safe and suitable facilities for sampling cement shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper, in conformance with California Test 125.
- If cement is used prior to sampling and testing as provided in Section 6-1.07, "Certificates of Compliance," and the cement is delivered directly to the site of the work, the Certificate of Compliance shall be signed by the cement manufacturer or supplier of the cement. If the cement is used in ready-mixed concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.
- Cement furnished without a Certificate of Compliance shall not be used in the work until the Engineer has had sufficient time to make appropriate tests and has approved the cement for use.

90-2.02 AGGREGATES

- Aggregates shall be free from deleterious coatings, clay balls, roots, bark, sticks, rags, and other extraneous material.
- Natural aggregates shall be thoroughly and uniformly washed before use.
- The Contractor, at the Contractor's expense, shall provide safe and suitable facilities, including necessary splitting devices for obtaining samples of aggregates, in conformance with California Test 125.
- Aggregates shall be of such character that it will be possible to produce workable concrete within the limits of water content provided in Section 90-6.06, "Amount of Water and Penetration."
- Aggregates shall have not more than 10 percent loss when tested for soundness in conformance with the requirements in California Test 214. The soundness requirement for fine aggregate will be waived, provided that the durability index, D_f, of the fine aggregate is 60, or greater, when tested for durability in conformance with California Test 229.
- If the results of any one or more of the Cleanness Value, Sand Equivalent, or aggregate grading tests do not meet the requirements specified for "Operating Range" but all meet the "Contract Compliance" requirements, the placement of concrete shall be suspended at the completion of the current pour until tests or other information indicate that the next material to be used in the work will comply with the requirements specified for "Operating Range."
- If the results of either or both the Cleanness Value and coarse aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete that is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State $4.60 per cubic meter for paving concrete and $7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.
- If the results of either or both the Sand Equivalent and fine aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete which is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State $4.60 per cubic meter for paving concrete and $7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.
- The 2 preceding paragraphs apply individually to the "Contract Compliance" requirements for coarse aggregate and fine aggregate. When both coarse aggregate and fine aggregate do not conform to the "Contract Compliance" requirements, both paragraphs shall apply. The payments specified in those paragraphs shall be in addition to any payments made in conformance with the provisions in Section 90-1.01, "Description."
- No single Cleanness Value, Sand Equivalent or aggregate grading test shall represent more than 250 m^3 of concrete or one day's pour, whichever is smaller.
- When the source of an aggregate is changed, the Contractor shall adjust the mix proportions and submit in writing to the Engineer a copy of the mix design before using the aggregates.

90-2.02A Coarse Aggregate

• Coarse aggregate shall consist of gravel, crushed gravel, crushed rock, crushed air-cooled iron blast furnace slag or combinations thereof. Crushed air-cooled blast furnace slag shall not be used in reinforced or prestressed concrete.

• Coarse aggregate shall conform to the following quality requirements:

Tests	California Test	Requirements
Loss in Los Angeles Rattler (after 500 revolutions)	211	45% max.
Cleanness Value		
Operating Range	227	75 min.
Contract Compliance	227	71 min.

• In lieu of the above Cleanness Value requirements, a Cleanness Value "Operating Range" limit of 71, minimum, and a Cleanness Value "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the coarse aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

1. coarse aggregate sampled at the completion of processing at the aggregate production plant had a Cleanness Value of not less than 82 when tested by California Test 227; and
2. prequalification tests performed in conformance with the requirements in California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.02B Fine Aggregate

• Fine aggregate shall consist of natural sand, manufactured sand produced from larger aggregate or a combination thereof. Manufactured sand shall be well graded.

• Fine aggregate shall conform to the following quality requirements:

Test	California Test	Requirements
Organic Impurities	213	Satisfactory[a]
Mortar Strengths Relative to Ottawa Sand	515	95%, min.
Sand Equivalent:		
Operating Range	217	75, min.
Contract Compliance	217	71, min.

a Fine aggregate developing a color darker than the reference standard color solution may be accepted if it is determined by the Engineer, from mortar strength tests, that a darker color is acceptable.

• In lieu of the above Sand Equivalent requirements, a Sand Equivalent "Operating Range" limit of 71 minimum and a Sand Equivalent "Contract Compliance" limit of 68 minimum will be used to determine the acceptability of the fine aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

1. fine aggregate sampled at the completion of processing at the aggregate production plant had a Sand Equivalent value of not less than 82 when tested by California Test 217; and
2. prequalification tests performed in conformance with California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.03 WATER

• In conventionally reinforced concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 1000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1300 parts per million of sulfates as SO_4, when tested in conformance with California Test 417. In prestressed concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil

and shall not contain more than 650 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1300 parts per million of sulfates as SO_4, when tested in conformance with California Test 417. In no case shall the water contain an amount of impurities that will cause either: 1) a change in the setting time of cement of more than 25 percent when tested in conformance with the requirements in ASTM Designation: C 191 or ASTM Designation: C 266 or 2) a reduction in the compressive strength of mortar at 14 days of more than 5 percent, when tested in conformance with the requirements in ASTM Designation: C 109, when compared to the results obtained with distilled water or deionized water, tested in conformance with the requirements in ASTM Designation: C 109.

- In non-reinforced concrete work, the water for curing, for washing aggregates and for mixing shall be free from oil and shall not contain more than 2000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, or more than 1500 parts per million of sulfates as SO_4, when tested in conformance with California Test 417.
- In addition to the above provisions, water for curing concrete shall not contain impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.
- Water reclaimed from mixer wash-out operations may be used in mixing concrete. The water shall not contain coloring agents or more than 300 parts per million of alkalis (Na_2O + 0.658 K_2O) as determined on the filtrate. The specific gravity of the water shall not exceed 1.03 and shall not vary more than ±0.010 during a day's operations.

90-2.04 ADMIXTURE MATERIALS

- Admixture materials shall conform to the requirements in the following ASTM Designations:

A. Chemical Admixtures—ASTM Designation: C 494.
B. Air-entraining Admixtures—ASTM Designation: C 260.
C. Calcium Chloride—ASTM Designation: D 98.
D. Mineral Admixtures—Coal fly ash; raw or calcined natural pozzolan as specified in ASTM Designation: C 618; silica fume conforming to the requirements in ASTM Designation: C 1240, with reduction of mortar expansion of 80 percent, minimum, using the cement from the proposed mix design.

- Unless otherwise specified in the special provisions, mineral admixtures shall be used in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."

90-3 AGGREGATE GRADINGS

90-3.01 GENERAL

- Before beginning concrete work, the Contractor shall submit in writing to the Engineer the gradation of the primary aggregate nominal sizes that the Contractor proposes to furnish. If a primary coarse aggregate or the fine aggregate is separated into 2 or more sizes, the proposed gradation shall consist of the gradation for each individual size, and the proposed proportions of each individual size, combined mathematically to indicate one proposed gradation. The proposed gradation shall meet the grading requirements shown in the table in this section, and shall show the percentage passing each of the sieve sizes used in determining the end result.
- The Engineer may waive, in writing, the gradation requirements in this Section 90-3.01 and in Sections 90-3.02, "Coarse Aggregate Grading," 90-3.03, "Fine Aggregate Grading," and 90-3.04, "Combined Aggregate Gradings," if, in the Engineer's opinion, furnishing the gradation is not necessary for the type or amount of concrete work to be constructed.
- Gradations proposed by the Contractor shall be within the following percentage passing limits:

Primary Aggregate Nominal Size	Sieve Size	Limits of Proposed Gradation
37.5-mm x 19-mm	25-mm	19 - 41
25-mm x 4.75-mm	19-mm	52 - 85
25-mm x 4.75-mm	9.5-mm	15 - 38
12.5-mm x 4.75-mm	9.5-mm	40 - 78
9.5-mm x 2.36-mm	9.5-mm	50 - 85
Fine Aggregate	1.18-mm	55 - 75
Fine Aggregate	600-µm	34 - 46
Fine Aggregate	300-µm	16 - 29

- Should the Contractor change the source of supply, the Contractor shall submit in writing to the Engineer the new gradations before their intended use.

90-3.02 COARSE AGGREGATE GRADING

- The grading requirements for coarse aggregates are shown in the following table for each size of coarse aggregate:

Sieve Sizes	Percentage Passing Primary Aggregate Nominal Sizes							
	37.5-mm x 19-mm		25-mm x 4.75-mm		12.5-mm x 4.75-mm		9.5-mm x 2.36-mm	
	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance
50-mm	100	100	—	—	—	—	—	—
37.5-mm	88-100	85-100	100	100	—	—	—	—
25-mm	x ± 18	X ± 25	88-100	86-100	—	—	—	—
19-mm	0-17	0-20	X ± 15	X ± 22	100	100	—	—
12.5-mm	—	—	—	—	82-100	80-100	100	100
9.5-mm	0-7	0-9	X ± 15	X ± 22	X ± 15	X ± 22	X ± 15	X ± 20
4.75-mm	—	—	0-16	0-18	0-15	0-18	0-25	0-28
2.36-mm	—	—	0-6	0-7	0-6	0-7	0-6	0-7

- In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."
- Coarse aggregate for the 37.5-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," shall be furnished in 2 or more primary aggregate nominal sizes. Each primary aggregate nominal size may be separated into 2 sizes and stored separately, provided that the combined material conforms to the grading requirements for that particular primary aggregate nominal size.
- When the 25-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," is to be used, the coarse aggregate may be separated into 2 sizes and stored separately, provided that the combined material shall conform to the grading requirements for the 25-mm x 4.75-mm primary aggregate nominal size.

90-3.03 FINE AGGREGATE GRADING

- Fine aggregate shall be graded within the following limits:

Sieve Sizes	Percentage Passing	
	Operating Range	Contract Compliance
9.5-mm	100	100
4.75-mm	95-100	93-100
2.36-mm	65-95	61-99
1.18-mm	X ± 10	X ± 13
600-µm	X ± 9	X ± 12
300-µm	X ± 6	X ± 9
150-µm	2-12	1-15
75-µm	0-8	0-10

- In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."
- In addition to the above required grading analysis, the distribution of the fine aggregate sizes shall be such that the difference between the total percentage passing the 1.18-mm sieve and the total percentage passing the 600-µm sieve shall be between 10 and 40, and the difference between the percentage passing the 600-µm and 300-µm sieves shall be between 10 and 40.
- Fine aggregate may be separated into 2 or more sizes and stored separately, provided that the combined material conforms to the grading requirements specified in this Section 90-3.03.

90-3.04 COMBINED AGGREGATE GRADINGS

- Combined aggregate grading limits shall be used only for the design of concrete mixes. Concrete mixes shall be designed so that aggregates are combined in proportions that shall produce a mixture within the grading limits for combined aggregates as specified herein. Within these limitations, the relative proportions shall be as ordered by the Engineer, except as otherwise provided in Section 90-1.01, "Description."

• The combined aggregate grading, except when otherwise specified in these specifications or the special provisions, shall be either the 37.5-mm, maximum grading, or the 25-mm, maximum grading, at the option of the Contractor.

Grading Limits of Combined Aggregates

Sieve Sizes	Percentage Passing			
	37.5-mm Max.	25-mm Max.	12.5-mm Max.	9.5-mm Max.
50-mm	100	—	—	—
37.5-mm	90-100	100	—	—
25-mm	50-86	90-100	—	—
19-mm	45-75	55-100	100	—
12.5-mm	—	—	90-100	100
9.5-mm	38-55	45-75	55-86	50 - 100
4.75-mm	30-45	35-60	45-63	45 - 63
2.36-mm	23-38	27-45	35-49	35 - 49
1.18-mm	17-33	20-35	25-37	25 - 37
600-µm	10-22	12-25	15-25	15 - 25
300-µm	4-10	5-15	5-15	5 - 15
150-µm	1-6	1-8	1-8	1 - 8
75-µm	0-3	0-4	0-4	0 - 4

• Changes from one grading to another shall not be made during the progress of the work unless permitted by the Engineer.

90-4 ADMIXTURES

90-4.01 GENERAL

• Admixtures used in portland cement concrete shall conform to and be used in conformance with the provisions in this Section 90-4 and the special provisions. Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option as provided herein.

• Chemical admixtures and air-entraining admixtures containing chlorides as Cl in excess of one percent by mass of admixture, as determined by California Test 415, shall not be used in prestressed or reinforced concrete.

• Calcium chloride shall not be used in concrete except when otherwise specified.

• Mineral admixture used in concrete for exposed surfaces of like elements of a structure shall be from the same source and of the same percentage.

• Admixtures shall be uniform in properties throughout their use in the work. Should it be found that an admixture as furnished is not uniform in properties, its use shall be discontinued.

• If more than one admixture is used, the admixtures shall be compatible with each other so that the desirable effects of all admixtures used will be realized.

90-4.02 MATERIALS

• Admixture materials shall conform to the provisions in Section 90–2.04, "Admixture Materials."

90-4.03 ADMIXTURE APPROVAL

• No admixture brand shall be used in the work unless it is on the Department's current list of approved brands for the type of admixture involved.

• Admixture brands will be considered for addition to the approved list if the manufacturer of the admixture submits to the Transportation Laboratory a sample of the admixture accompanied by certified test results demonstrating that the admixture complies with the requirements in the appropriate ASTM Designation and these specifications. The sample shall be sufficient to permit performance of all required tests. Approval of admixture brands will be dependent upon a determination as to compliance with the requirements, based on the certified test results submitted, together with tests the Department may elect to perform.

• When the Contractor proposes to use an admixture of a brand and type on the current list of approved admixture brands, the Contractor shall furnish a Certificate of Compliance from the manufacturer, as provided in Section 6-1.07, "Certificates of Compliance," certifying that the admixture furnished is the same as that previously approved. If a previously approved admixture is not accompanied by a Certificate of Compliance, the admixture shall not be used in the work until the Engineer has had sufficient time to make the appropriate tests and has approved the admixture for use. The Engineer may take samples for testing at any time, whether or not the admixture has been accompanied by a Certificate of Compliance.

• If a mineral admixture is delivered directly to the site of the work, the Certificate of Compliance shall be signed by the manufacturer or supplier of the mineral admixture. If the mineral admixture is used in ready-mix concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.

90-4.04 REQUIRED USE OF CHEMICAL ADMIXTURES AND CALCIUM CHLORIDE

• When the use of a chemical admixture or calcium chloride is specified, the admixture shall be used at the dosage specified, except that if no dosage is specified, the admixture shall be used at the dosage normally recommended by the manufacturer of the admixture.

• Calcium chloride shall be dispensed in liquid, flake, or pellet form. Calcium chloride dispensed in liquid form shall conform to the provisions for dispensing liquid admixtures in Section 90-4.10, "Proportioning and Dispensing Liquid Admixtures."

90-4.05 OPTIONAL USE OF CHEMICAL ADMIXTURES

• The Contractor will be permitted to use Type A or F, water-reducing; Type B, retarding; or Type D or G, water-reducing and retarding admixtures as described in ASTM Designation: C 494 to conserve cementitious material or to facilitate any concrete construction application subject to the following conditions:

A. When a water-reducing admixture or a water-reducing and retarding admixture is used, the cementitious material content specified or ordered may be reduced by a maximum of 5 percent by mass, except that the resultant cementitious material content shall be not less than 300 kilograms per cubic meter; and
B. When a reduction in cementitious material content is made, the dosage of admixture used shall be the dosage used in determining approval of the admixture.

• Unless otherwise specified, a Type C accelerating chemical admixture conforming to the requirements in ASTM Designation: C 494, may be used in portland cement concrete. Inclusion in the mix design submitted for approval will not be required provided that the admixture is added to counteract changing conditions that contribute to delayed setting of the portland cement concrete, and the use or change in dosage of the admixture is approved in writing by the Engineer.

90-4.06 REQUIRED USE OF AIR-ENTRAINING ADMIXTURES

• When air-entrainment is specified or ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce a concrete having the specified air content as determined by California Test 504.

90-4.07 OPTIONAL USE OF AIR-ENTRAINING ADMIXTURES

• When air-entrainment has not been specified or ordered by the Engineer, the Contractor will be permitted to use an air-entraining admixture to facilitate the use of any construction procedure or equipment provided that the average air content, as determined by California Test 504, of 3 successive tests does not exceed 4 percent, and no single test value exceeds 5.5 percent. If the Contractor elects to use an air-entraining admixture in concrete for pavement, the Contractor shall so indicate at the time the Contractor designates the source of aggregate as provided in Section 40-1.015, "Cement Content."

90-4.08 REQUIRED USE OF MINERAL ADMIXTURES

• Unless otherwise specified, mineral admixture shall be combined with cement to make cementitious material.

• The calcium oxide content of mineral admixtures shall not exceed 10 percent and the available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 618.

• The amounts of cement and mineral admixture used in cementitious material shall be sufficient to satisfy the minimum cementitious material content requirements specified in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," and shall conform to the following:

A. The minimum amount of cement shall not be less than 75 percent by mass of the specified minimum cementitious material content;
B. The minimum amount of mineral admixture to be combined with cement shall be determined using one of the following criteria:

    1. When the calcium oxide content of a mineral admixture is equal to or less than 2 percent by mass, the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix;

2. When the calcium oxide content of a mineral admixture is greater than 2 percent, the amount of mineral admixture shall not be less than 25 percent by mass of the total amount of cementitious material to be used in the mix;
3. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," is used, the amount of mineral admixture shall not be less than 10 percent by mass of the total amount of cementitious material to be used in the mix

C. The total amount of mineral admixture shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. Where Section 90-1.01, "Description," specifies a maximum cementitious content in kilograms per cubic meter, the total mass of cement and mineral admixture per cubic meter shall not exceed the specified maximum cementitious material content.

90-4.09 BLANK

90-4.10 PROPORTIONING AND DISPENSING LIQUID ADMIXTURES

• Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers for liquid admixtures shall have sufficient capacity to measure at one time the prescribed quantity required for each batch of concrete. Each dispenser shall include a graduated measuring unit into which liquid admixtures are measured to within ±5 percent of the prescribed quantity for each batch. Dispensers shall be located and maintained so that the graduations can be accurately read from the point at which proportioning operations are controlled to permit a visual check of batching accuracy prior to discharge. Each measuring unit shall be clearly marked for the type and quantity of admixture.

• Each liquid admixture dispensing system shall be equipped with a sampling device consisting of a valve located in a safe and readily accessible position such that a sample of the admixture may be withdrawn slowly by the Engineer.

• If more than one liquid admixture is used in the concrete mix, each liquid admixture shall have a separate measuring unit and shall be dispensed by injecting equipment located in such a manner that the admixtures are not mixed at high concentrations and do not interfere with the effectiveness of each other. When air-entraining admixtures are used in conjunction with other liquid admixtures, the air-entraining admixture shall be the first to be incorporated into the mix.

• When automatic proportioning devices are required for concrete pavement, dispensers for liquid admixtures shall operate automatically with the batching control equipment. The dispensers shall be equipped with an automatic warning system in good operating condition that will provide a visible or audible signal at the point at which proportioning operations are controlled when the quantity of admixture measured for each batch of concrete varies from the preselected dosage by more than 5 percent, or when the entire contents of the measuring unit are not emptied from the dispenser into each batch of concrete.

• Unless liquid admixtures are added to premeasured water for the batch, their discharge into the batch shall be arranged to flow into the stream of water so that the admixtures are well dispersed throughout the batch, except that air-entraining admixtures may be dispensed directly into moist sand in the batching bins provided that adequate control of the air content of the concrete can be maintained.

• Liquid admixtures requiring dosages greater than 2.5 L/m^3 shall be considered to be water when determining the total amount of free water as specified in Section 90-6.06, "Amount of Water and Penetration."

• Special admixtures, such as "high range" water reducers that may contribute to a high rate of slump loss, shall be measured and dispensed as recommended by the admixture manufacturer and as approved by the Engineer.

90-4.11 STORAGE, PROPORTIONING, AND DISPENSING OF MINERAL ADMIXTURES

• Mineral admixtures shall be protected from exposure to moisture until used. Sacked material shall be piled to permit access for tally, inspection and identification for each shipment.

• Adequate facilities shall be provided to assure that mineral admixtures meeting the specified requirements are kept separate from other mineral admixtures in order to prevent any but the specified mineral admixtures from entering the work. Safe and suitable facilities for sampling mineral admixtures shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper.

• Mineral admixtures shall be incorporated into concrete using equipment conforming to the requirements for cement weigh hoppers, and charging and discharging mechanisms in ASTM Designation: C 94, in Section 90-5.03, "Proportioning," and in this Section 90-4.11.

• When concrete is completely mixed in stationary paving mixers, the mineral admixture shall be weighed in a separate weigh hopper conforming to the provisions for cement weigh hoppers and charging and discharging mechanisms in Section 90-5.03A, "Proportioning for Pavement," and the mineral admixture and cement shall be introduced simultaneously into the mixer proportionately with the aggregate. If the mineral admixture is not weighed in a separate weigh hopper, the Contractor shall provide certification that the stationary mixer is capable of mixing the cement, admixture, aggregates and water uniformly prior to discharge. Certification shall contain the following:

A. Test results for 2 compressive strength test cylinders of concrete taken within the first one-third and 2 compressive strength test cylinders of concrete taken within the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;"
B. Calculations demonstrating that the difference in the averages of 2 compressive strengths taken in the first one-third is no greater than 7.5 percent different than the averages of 2 compressive strengths taken in the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;" and
C. The mixer rotation speed and time of mixing prior to discharge that are required to produce a mix that meets the requirements above.

90-5 PROPORTIONING

90-5.01 STORAGE OF AGGREGATES

• Aggregates shall be stored or stockpiled in such a manner that separation of coarse and fine particles of each size shall be avoided and also that the various sizes shall not become intermixed before proportioning.

• Aggregates shall be stored or stockpiled and handled in a manner that shall prevent contamination by foreign materials. In addition, storage of aggregates at batching or mixing facilities that are erected subsequent to the award of the contract and that furnish concrete to the project shall conform to the following:

A. Intermingling of the different sizes of aggregates shall be positively prevented. The Contractor shall take the necessary measures to prevent intermingling. The preventive measures may include, but are not necessarily limited to, physical separation of stockpiles or construction of bulkheads of adequate length and height; and
B. Contamination of aggregates by contact with the ground shall be positively prevented. The Contractor shall take the necessary measures to prevent contamination. The preventive measures shall include, but are not necessarily limited to, placing aggregates on wooden platforms or on hardened surfaces consisting of portland cement concrete, asphalt concrete, or cement treated material.

• In placing aggregates in storage or in moving the aggregates from storage to the weigh hopper of the batching plant, any method that may cause segregation, degradation, or the combining of materials of different gradings that will result in any size of aggregate at the weigh hopper failing to meet the grading requirements, shall be discontinued. Any method of handling aggregates that results in excessive breakage of particles shall be discontinued. The use of suitable devices to reduce impact of falling aggregates may be required by the Engineer.

90-5.02 PROPORTIONING DEVICES

• Weighing, measuring, or metering devices used for proportioning materials shall conform to the requirements in Section 9-1.01, "Measurement of Quantities," and this Section 90-5.02. In addition, automatic weighing systems shall comply with the requirements for automatic proportioning devices in Section 90-5.03A, "Proportioning for Pavement." Automatic devices shall be automatic to the extent that the only manual operation required for proportioning the aggregates, cement, and mineral admixture for one batch of concrete is a single operation of a switch or starter.

• Proportioning devices shall be tested at the expense of the Contractor as frequently as the Engineer may deem necessary to ensure their accuracy.

• Weighing equipment shall be insulated against vibration or movement of other operating equipment in the plant. When the plant is in operation, the mass of each batch of material shall not vary from the mass designated by the Engineer by more than the tolerances specified herein.

• Equipment for cumulative weighing of aggregate shall have a zero tolerance of ±0.5 percent of the designated total batch mass of the aggregate. For systems with individual weigh hoppers for the various sizes of aggregate, the zero tolerance shall be ±0.5 percent of the individual batch mass designated for each size of aggregate. Equipment for cumulative weighing of cement and mineral admixtures shall have a zero tolerance of ±0.5 percent of the designated total batch mass of the cement and mineral admixture. Equipment for weighing cement or mineral admixture separately shall have a zero tolerance of ±0.5 percent of their designated individual batch masses. Equipment for measuring water shall have a zero tolerance of ±0.5 percent of its designated mass or volume.

• The mass indicated for any batch of material shall not vary from the preselected scale setting by more than the following:

A. Aggregate weighed cumulatively shall be within 1.0 percent of the designated total batch mass of the aggregate. Aggregates weighed individually shall be within 1.5 percent of their respective designated batch masses; and

B. Cement shall be within 1.0 percent of its designated batch mass. When weighed individually, mineral admixture shall be within 1.0 percent of its designated batch mass. When mineral admixture and cement are permitted to be weighed cumulatively, cement shall be weighed first to within 1.0 percent of its designated batch mass, and the total for cement and mineral admixture shall be within 1.0 percent of the sum of their designated batch masses; and
C. Water shall be within 1.5 percent of its designated mass or volume.

• Each scale graduation shall be approximately 0.001 of the total capacity of the scale. The capacity of scales for weighing cement, mineral admixture, or cement plus mineral admixture and aggregates shall not exceed that of commercially available scales having single graduations indicating a mass not exceeding the maximum permissible mass variation above, except that no scale shall be required having a capacity of less than 500 kg, with 0.5-kg graduations.

90-5.03 PROPORTIONING

• Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cement, mineral admixture, and water as provided in these specifications. Aggregates shall be proportioned by mass.

• At the time of batching, aggregates shall have been dried or drained sufficiently to result in a stable moisture content such that no visible separation of water from aggregate will take place during transportation from the proportioning plant to the point of mixing. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry mass.

• Should separate supplies of aggregate material of the same size group, but of different moisture content or specific gravity or surface characteristics affecting workability, be available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another.

• Bulk "Type IP (MS) Modified" cement shall be weighed in an individual hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer.

• Bulk cement and mineral admixture may be weighed in separate, individual weigh hoppers or may be weighed in the same weigh hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer. If the cement and mineral admixture are weighed cumulatively, the cement shall be weighed first.

• When cement and mineral admixtures are weighed in separate weigh hoppers**,** the weigh systems for the proportioning of the aggregate, the cement, and the mineral admixture shall be individual and distinct from all other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and independent material weighing device. The cement and the mineral admixture shall be discharged into the mixer simultaneously with the aggregate.

• The scales and weigh hoppers for bulk weighing cement, mineral admixture, or cement plus mineral admixture shall be separate and distinct from the aggregate weighing equipment.

• For batches with a volume of one cubic meter or more, the batching equipment shall conform to one of the following combinations:

A. Separate boxes and separate scale and indicator for weighing each size of aggregate.
B. Single box and scale indicator for all aggregates.
C. Single box or separate boxes and automatic weighing mechanism for all aggregates.

• In order to check the accuracy of batch masses, the gross mass and tare mass of batch trucks, truck mixers, truck agitators, and non-agitating hauling equipment shall be determined when ordered by the Engineer. The equipment shall be weighed at the Contractor's expense on scales designated by the Engineer.

90-5.03A Proportioning for Pavement

• Aggregates and bulk cement, mineral admixture, and cement plus mineral admixture for use in pavement shall be proportioned by mass by means of automatic proportioning devices of approved type conforming to these specifications.

• The Contractor shall install and maintain in operating condition an electronically actuated moisture meter that will indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched within a sensitivity of 0.5 percent by mass of the fine aggregate.

• The batching of cement, mineral admixture, or cement plus mineral admixture and aggregate shall be interlocked so that a new batch cannot be started until all weigh hoppers are empty, the proportioning devices are within zero tolerance, and the discharge gates are closed. The interlock shall permit no part of the batch to be discharged until all aggregate hoppers and the cement and mineral admixture hoppers or the cement plus mineral admixture hopper are charged with masses that are within the tolerances specified in Section 90-5.02, "Proportioning Devices."

• When interlocks are required for cement and mineral admixture charging mechanisms and cement and mineral admixtures are weighed cumulatively, their charging mechanisms shall be interlocked to prevent the introduction of mineral

admixture until the mass of cement in the cement weigh hopper is within the tolerances specified in Section 90-5.02, "Proportioning Devices."

- The discharge gate on the cement and mineral admixture hoppers or the cement plus mineral admixture hopper shall be designed to permit regulating the flow of cement, mineral admixture, or cement plus mineral admixture into the aggregate as directed by the Engineer.
- When separate weigh boxes are used for each size of aggregate, the discharge gates shall permit regulating the flow of each size of aggregate as directed by the Engineer.
- Material discharged from the several bins shall be controlled by gates or by mechanical conveyors. The means of withdrawal from the several bins, and of discharge from the weigh box, shall be interlocked so that not more than one bin can discharge at a time, and so that the weigh box cannot be tripped until the required quantity from each of the several bins has been deposited therein. Should a separate weigh box be used for each size of aggregate, all may be operated and discharged simultaneously.
- When the discharge from the several bins is controlled by gates, each gate shall be actuated automatically so that the required mass is discharged into the weigh box, after which the gate shall automatically close and lock.
- The automatic weighing system shall be designed so that all proportions required may be set on the weighing controller at the same time.

90-6 MIXING AND TRANSPORTING

90-6.01 GENERAL

- Concrete shall be mixed in mechanically operated mixers, except that when permitted by the Engineer, batches not exceeding 0.25 m^3 may be mixed by hand methods in conformance with the provisions in Section 90-6.05, "Hand-Mixing."
- Equipment having components made of aluminum or magnesium alloys that would have contact with plastic concrete during mixing, transporting, or pumping of portland cement concrete shall not be used.
- Concrete shall be homogeneous and thoroughly mixed, and there shall be no lumps or evidence of undispersed cement, mineral admixture, or cement plus mineral admixture.
- Uniformity of concrete mixtures will be determined by differences in penetration as determined by California Test 533, or slump as determined by ASTM Designation: C 143, and by variations in the proportion of coarse aggregate as determined by California Test 529.
- When the mix design specifies a penetration value, the difference in penetration, determined by comparing penetration tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed 10 mm. When the mix design specifies a slump value, the difference in slump, determined by comparing slump tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed the values given in the table below. Variation in the proportion of coarse aggregate will be determined by comparing the results of tests of 2 samples of mixed concrete from the same batch or truck mixer load and the difference between the 2 results shall not exceed 100 kg per cubic meter of concrete.

Average Slump	Maximum Permissible Difference
Less than 100-mm	25-mm
100-mm to 150-mm	38-mm
Greater than 150-mm to 225-mm	50-mm

- The Contractor, at the Contractor's expense, shall furnish samples of the freshly mixed concrete and provide satisfactory facilities for obtaining the samples.

90-6.02 MACHINE MIXING

- Concrete mixers may be of the revolving drum or the revolving blade type, and the mixing drum or blades shall be operated uniformly at the mixing speed recommended by the manufacturer. Mixers and agitators that have an accumulation of hard concrete or mortar shall not be used.
- The temperature of mixed concrete, immediately before placing, shall be not less than 10°C or more than 32°C. Aggregates and water shall be heated or cooled as necessary to produce concrete within these temperature limits. Neither aggregates nor mixing water shall be heated to exceed 65°C. If ice is used to cool the concrete, discharge of the mixer will not be permitted until all ice is melted.
- The batch shall be so charged into the mixer that some water will enter in advance of cementitious materials and aggregates. All water shall be in the drum by the end of the first one-fourth of the specified mixing time.
- Cementitious materials shall be batched and charged into the mixer by means that will not result either in loss of cementitious materials due to the effect of wind, in accumulation of cementitious materials on surfaces of conveyors or hoppers, or in other conditions that reduce or vary the required quantity of cementitious material in the concrete mixture.

- Paving and stationary mixers shall be operated with an automatic timing device. The timing device and discharge mechanism shall be interlocked so that during normal operation no part of the batch will be discharged until the specified mixing time has elapsed.
- The total elapsed time between the intermingling of damp aggregates and all cementitious materials and the start of mixing shall not exceed 30 minutes.
- The size of batch shall not exceed the manufacturer's guaranteed capacity.
- When producing concrete for pavement or base, suitable batch counters shall be installed and maintained in good operating condition at jobsite batching plants and stationary mixers. The batch counters shall indicate the exact number of batches proportioned and mixed.
- Concrete shall be mixed and delivered to the jobsite by means of one of the following combinations of operations:

A. Mixed completely in a stationary mixer and the mixed concrete transported to the point of delivery in truck agitators or in non-agitating hauling equipment (central-mixed concrete).
B. Mixed partially in a stationary mixer, and the mixing completed in a truck mixer (shrink-mixed concrete).
C. Mixed completely in a truck mixer (transit-mixed concrete).
D. Mixed completely in a paving mixer.

- Agitators may be truck mixers operating at agitating speed or truck agitators. Each mixer and agitator shall have attached thereto in a prominent place a metal plate or plates on which is plainly marked the various uses for which the equipment is designed, the manufacturer's guaranteed capacity of the drum or container in terms of the volume of mixed concrete and the speed of rotation of the mixing drum or blades.
- Truck mixers shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified.
- When shrink-mixed concrete is furnished, concrete that has been partially mixed at a central plant shall be transferred to a truck mixer and all requirements for transit-mixed concrete shall apply. No credit in the number of revolutions at mixing speed shall be allowed for partial mixing in a central plant.

90-6.03 TRANSPORTING MIXED CONCRETE

- Mixed concrete may be transported to the delivery point in truck agitators or truck mixers operating at the speed designated by the manufacturer of the equipment as agitating speed, or in non-agitating hauling equipment, provided the consistency and workability of the mixed concrete upon discharge at the delivery point is suitable for adequate placement and consolidation in place, and provided the mixed concrete after hauling to the delivery point conforms to the provisions in Section 90-6.01, "General."
- Truck agitators shall be loaded not to exceed the manufacturer's guaranteed capacity and shall maintain the mixed concrete in a thoroughly mixed and uniform mass during hauling.
- Bodies of non-agitating hauling equipment shall be constructed so that leakage of the concrete mix, or any part thereof, will not occur at any time.
- Concrete hauled in open-top vehicles shall be protected during hauling against rain or against exposure to the sun for more than 20 minutes when the ambient temperature exceeds 24°C.
- No additional mixing water shall be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer. If the Engineer authorizes additional water to be incorporated into the concrete, the drum shall be revolved not less than 30 revolutions at mixing speed after the water is added and before discharge is commenced.
- The rate of discharge of mixed concrete from truck mixer-agitators shall be controlled by the speed of rotation of the drum in the discharge direction with the discharge gate fully open.
- When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be completed within 1.5 hours or before 250 revolutions of the drum or blades, whichever occurs first, after the introduction of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, the time allowed may be less than 1.5 hours.
- When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be completed within one hour after the addition of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.
- Each load of concrete delivered at the jobsite shall be accompanied by a weighmaster certificate showing the mix identification number, non-repeating load number, date and time at which the materials were batched, the total amount of water added to the load, and for transit-mixed concrete, the reading of the revolution counter at the time the truck mixer is charged with cement. This weighmaster certificate shall also show the actual scale masses (kilograms) for the ingredients batched. Theoretical or target batch masses shall not be used as a substitute for actual scale masses.

• Weighmaster certificates shall be provided in printed form, or if approved by the Engineer, the data may be submitted in electronic media. Electronic media shall be presented in a tab-delimited format on a 90 mm diskette with a capacity of at least 1.4 megabytes. Captured data, for the ingredients represented by each batch shall be "line feed, carriage return" (LFCR) and "one line, separate record" with allowances for sufficient fields to satisfy the amount of data required by these specifications.

• The Contractor may furnish a weighmaster certificate accompanied by a separate certificate that lists the actual batch masses or measurements for a load of concrete provided that both certificates are imprinted with the same non-repeating load number that is unique to the contract and delivered to the jobsite with the load.

• Weighmaster certificates furnished by the Contractor shall conform to the provisions in Section 9-1.01, "Measurement of Quantities."

90-6.04 TIME OR AMOUNT OF MIXING

• Mixing of concrete in paving or stationary mixers shall continue for the required mixing time after all ingredients, except water and admixture, if added with the water, are in the mixing compartment of the mixer before any part of the batch is released. Transfer time in multiple drum mixers shall not be counted as part of the required mixing time.

• The required mixing time, in paving or stationary mixers, of concrete used for concrete structures, except minor structures, shall be not less than 90 seconds or more than 5 minutes, except that when directed by the Engineer in writing, the requirements of the following paragraph shall apply.

• The required mixing time, in paving or stationary mixers, except as provided in the preceding paragraph, shall be not less than 50 seconds or more than 5 minutes.

• The minimum required revolutions at the mixing speed for transit-mixed concrete shall not be less than that recommended by the mixer manufacturer, but in no case shall the number of revolutions be less than that required to consistently produce concrete conforming to the provisions for uniformity in Section 90-6.01, "General."

90-6.05 HAND-MIXING

• Hand-mixed concrete shall be made in batches of not more than 0.25 m^3 and shall be mixed on a watertight, level platform. The proper amount of coarse aggregate shall be measured in measuring boxes and spread on the platform and the fine aggregate shall be spread on this layer, the 2 layers being not more than 0.3 meters in total depth. On this mixture shall be spread the dry cement and mineral admixture and the whole mass turned no fewer than 2 times dry; then sufficient clean water shall be added, evenly distributed, and the whole mass again turned no fewer than 3 times, not including placing in the carriers or forms.

90-6.06 AMOUNT OF WATER AND PENETRATION

• The amount of water used in concrete mixes shall be regulated so that the penetration of the concrete as determined by California Test 533 or the slump of the concrete as determined by ASTM Designation: C 143 is within the "Nominal" values shown in the following table. When the penetration or slump of the concrete is found to exceed the nominal values listed, the mixture of subsequent batches shall be adjusted to reduce the penetration or slump to a value within the nominal range shown. Batches of concrete with a penetration or slump exceeding the maximum values listed shall not be used in the work. When Type F or Type G chemical admixtures are added to the mix, the penetration requirements shall not apply and the slump shall not exceed 225 mm after the chemical admixtures are added.

Type of Work	Nominal		Maximum	
	Penetration (mm)	Slump (mm)	Penetration (mm)	Slump (mm)
Concrete Pavement	0-25	—	40	—
Non-reinforced concrete facilities	0-35	—	50	—
Reinforced concrete structures				
Sections over 300-mm thick	0-35	—	65	—
Sections 300-mm thick or less	0-50	—	75	—
Concrete placed under water	—	150-200	—	225
Cast-in-place concrete piles	65-90	130-180	100	200

• The amount of free water used in concrete shall not exceed 183 kg/m^3, plus 20 kg for each required 100 kg of cementitious material in excess of 325 kg/m^3.

• The term free water is defined as the total water in the mixture minus the water absorbed by the aggregates in reaching a saturated surface-dry condition.

• Where there are adverse or difficult conditions that affect the placing of concrete, the above specified penetration and free water content limitations may be exceeded providing the Contractor is granted permission by the Engineer in writing to increase the cementitious material content per cubic meter of concrete. The increase in water and cementitious material shall be at a ratio not to exceed 30 kg of water per added 100 kg of cementitious material per cubic meter. The cost of additional cementitious material and water added under these conditions shall be at the Contractor's expense and no additional compensation will be allowed therefor.

• The equipment for supplying water to the mixer shall be constructed and arranged so that the amount of water added can be measured accurately. Any method of discharging water into the mixer for a batch shall be accurate within 1.5 percent of the quantity of water required to be added to the mix for any position of the mixer. Tanks used to measure water shall be designed so that water cannot enter while water is being discharged into the mixer and discharge into the mixer shall be made rapidly in one operation without dribbling. All equipment shall be arranged so as to permit checking the amount of water delivered by discharging into measured containers.

90-7 CURING CONCRETE

90-7.01 METHODS OF CURING

• Newly placed concrete shall be cured by the methods specified in this Section 90-7.01 and the special provisions.

90-7.01A Water Method

• The concrete shall be kept continuously wet by the application of water for a minimum curing period of 7 days after the concrete has been placed.

• When a curing medium consisting of cotton mats, rugs, carpets, or earth or sand blankets is to be used to retain the moisture, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. The moisture from the nozzle shall not be applied under pressure directly upon the concrete and shall not be allowed to accumulate on the concrete in a quantity sufficient to cause a flow or wash the surface. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing mediums.

• When concrete bridge decks and flat slabs are to be cured without the use of a curing medium, the entire surface of the bridge deck or slab shall be kept damp by the application of water with an atomizing nozzle as specified in the preceding paragraph, until the concrete has set, after which the entire surface of the concrete shall be sprinkled continuously with water for a period of not less than 7 days.

90-7.01B Curing Compound Method

• Surfaces of the concrete that are exposed to the air shall be sprayed uniformly with a curing compound.

• Curing compounds to be used shall be as follows:

1. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B, except the resin type shall be poly-alpha-methylstyrene.
2. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B.
3. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class A.
4. Non-pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class B.
5. Non-pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class A.
6. Non-pigmented curing compound with fugitive dye conforming to the requirements in ASTM Designation: C 309, Type 1-D, Class A.

• The infrared scan for the dried vehicle from curing compound (1) shall match the infrared scan on file at the Transportation Laboratory.

• The loss of water for each type of curing compound, when tested in conformance with the requirements in California Test 534, shall not be more than 0.15-kg/m^2 in 24 hours.

• The curing compound to be used will be specified elsewhere in these specifications or in the special provisions.

• When the use of curing compound is required or permitted elsewhere in these specifications or in the special provisions and no specific kind is specified, any of the curing compounds listed above may be used.

• Curing compound shall be applied at a nominal rate of 3.7 m^2/L, unless otherwise specified.

• At any point, the application rate shall be within ±1.2 m^2/L of the nominal rate specified, and the average application rate shall be within ±0.5 m^2/L of the nominal rate specified when tested in conformance with the requirements in California Test 535. Runs, sags, thin areas, skips, or holidays in the applied curing compound shall be evidence that the application is not satisfactory.

• Curing compounds shall be applied using power operated spray equipment. The power operated spraying equipment shall be equipped with an operational pressure gage and a means of controlling the pressure. Hand spraying of small and irregular areas that are not reasonably accessible to mechanical spraying equipment, in the opinion of the Engineer, may be permitted.

• The curing compound shall be applied to the concrete following the surface finishing operation, immediately before the moisture sheen disappears from the surface, but before any drying shrinkage or craze cracks begin to appear. In the event of any drying or cracking of the surface, application of water with an atomizing nozzle as specified in Section 90-7.01A, "Water Method," shall be started immediately and shall be continued until application of the compound is resumed or started; however, the compound shall not be applied over any resulting freestanding water. Should the film of compound be damaged from any cause before the expiration of 7 days after the concrete is placed in the case of structures and 72 hours in the case of pavement, the damaged portion shall be repaired immediately with additional compound.

• At the time of use, compounds containing pigments shall be in a thoroughly mixed condition with the pigment uniformly dispersed throughout the vehicle. A paddle shall be used to loosen all settled pigment from the bottom of the container, and a power driven agitator shall be used to disperse the pigment uniformly throughout the vehicle.

• Agitation shall not introduce air or other foreign substance into the curing compound.

• The manufacturer shall include in the curing compound the necessary additives for control of sagging, pigment settling, leveling, de-emulsification, or other requisite qualities of a satisfactory working material. Pigmented curing compounds shall be manufactured so that the pigment does not settle badly, does not cake or thicken in the container, and does not become granular or curdled. Settlement of pigment shall be a thoroughly wetted, soft, mushy mass permitting the complete and easy vertical penetration of a paddle. Settled pigment shall be easily redispersed, with minimum resistance to the sideways manual motion of the paddle across the bottom of the container, to form a smooth uniform product of the proper consistency.

• Curing compounds shall remain sprayable at temperatures above 4°C and shall not be diluted or altered after manufacture.

• The curing compound shall be packaged in clean 1040-L totes, 210-L barrels

or 19-L pails shall be supplied from a suitable storage tank located at the jobsite. The containers shall comply with "Title 49, Code of Federal Regulations, Hazardous Materials Regulations." The 1040-L totes and the 210-L barrels shall have removable lids and airtight fasteners. The 19-L pails shall be round and have standard full open head and bail. Lids with bungholes shall not be permitted. Settling or separation of solids in containers, except tanks, must be completely redispersed with low speed mixing prior to use, in conformance with these specifications and the manufacturer's recommendations. Mixing shall be accomplished either manually by use of a paddle or by use of a mixing blade driven by a drill motor, at low speed. Mixing blades shall be the type used for mixing paint. On site storage tanks shall be kept clean and free of contaminants. Each tank shall have a permanent system designed to completely redisperse settled material without introducing air or other foreign substances.

• Steel containers and lids shall be lined with a coating that will prevent destructive action by the compound or chemical agents in the air space above the compound. The coating shall not come off the container or lid as skins. Containers shall be filled in a manner that will prevent skinning. Plastic containers shall not react with the compound.

• Each container shall be labeled with the manufacturer's name, kind of curing compound, batch number, volume, date of manufacture, and volatile organic compound (VOC) content. The label shall also warn that the curing compound containing pigment shall be well stirred before use. Precautions concerning the handling and the application of curing compound shall be shown on the label of the curing compound containers in conformance with the Construction Safety Orders and General Industry Safety Orders of the State of California.

• Containers of curing compound shall be labeled to indicate that the contents fully comply with the rules and regulations concerning air pollution control in the State of California.

• When the curing compound is shipped in tanks or tank trucks, a shipping invoice shall accompany each load. The invoice shall contain the same information as that required herein for container labels.

• Curing compound will be sampled by the Engineer at the source of supply or at the jobsite or at both locations.

• Curing compound shall be formulated so as to maintain the specified properties for a minimum of one year. The Engineer may require additional testing before use to determine compliance with these specifications if the compound has not been used within one year or whenever the Engineer has reason to believe the compound is no longer satisfactory.

• Tests will be conducted in conformance with the latest ASTM test methods and methods in use by the Transportation Laboratory.

90-7.01C Waterproof Membrane Method

• The exposed finished surfaces of concrete shall be sprayed with water, using a nozzle that so atomizes the flow that a mist and not a spray is formed, until the concrete has set, after which the curing membrane shall be placed. The curing membrane shall remain in place for a period of not less than 72 hours.

- Sheeting material for curing concrete shall conform to the requirements in AASHTO Designation: M 171 for white reflective materials.
- The sheeting material shall be fabricated into sheets of such width as to provide a complete cover for the entire concrete surface. Joints in the sheets shall be securely cemented together in such a manner as to provide a waterproof joint. The joint seams shall have a minimum lap of 100 mm.
- The sheets shall be securely weighted down by placing a bank of earth on the edges of the sheets or by other means satisfactory to the Engineer.
- Should any portion of the sheets be broken or damaged before the expiration of 72 hours after being placed, the broken or damaged portions shall be immediately repaired with new sheets properly cemented into place.
- Sections of membrane that have lost their waterproof qualities or have been damaged to such an extent as to render them unfit for curing the concrete shall not be used.

90-7.01D Forms-In-Place Method

- Formed surfaces of concrete may be cured by retaining the forms in place. The forms shall remain in place for a minimum period of 7 days after the concrete has been placed, except that for members over 0.5-m in least dimension the forms shall remain in place for a minimum period of 5 days.
- Joints in the forms and the joints between the end of forms and concrete shall be kept moisture tight during the curing period. Cracks in the forms and cracks between the forms and the concrete shall be resealed by methods subject to the approval of the Engineer.

90-7.02 CURING PAVEMENT

- The entire exposed area of the pavement, including edges, shall be cured by the waterproof membrane method, or curing compound method using curing compound (1) or (2) as the Contractor may elect. Should the side forms be removed before the expiration of 72 hours following the start of curing, the exposed pavement edges shall also be cured. If the pavement is cured by means of the curing compound method, the sawcut and all portions of the curing compound that have been disturbed by sawing operations shall be restored by spraying with additional curing compound.
- Curing shall commence as soon as the finishing process provided in Section 40-1.10, "Final Finishing," has been completed. The method selected shall conform to the provisions in Section 90-7.01, "Methods of Curing."
- When the curing compound method is used, the compound shall be applied to the entire pavement surface by mechanical sprayers. Spraying equipment shall be of the fully atomizing type equipped with a tank agitator that provides for continual agitation of the curing compound during the time of application. The spray shall be adequately protected against wind, and the nozzles shall be so oriented or moved mechanically transversely as to result in the minimum specified rate of coverage being applied uniformly on exposed faces. Hand spraying of small and irregular areas, and areas inaccessible to mechanical spraying equipment, in the opinion of the Engineer, will be permitted. When the ambient air temperature is above 15°C, the Contractor shall fog the surface of the concrete with a fine spray of water as specified in Section 90-7.01A, "Water Method." The surface of the pavement shall be kept moist between the hours of 10:00 a.m. and 4:30 p.m. on the day the concrete is placed. However, the fogging done after the curing compound has been applied shall not begin until the compound has set sufficiently to prevent displacement. Fogging shall be discontinued if ordered in writing by the Engineer.

90-7.03 CURING STRUCTURES

- Newly placed concrete for cast-in-place structures, other than highway bridge decks, shall be cured by the water method, the forms-in-place method, or, as permitted herein, by the curing compound method, in conformance with the provisions in Section 90-7.01, "Methods of Curing."
- The curing compound method using a pigmented curing compound may be used on concrete surfaces of construction joints, surfaces that are to be buried underground, and surfaces where only Ordinary Surface Finish is to be applied and on which a uniform color is not required and that will not be visible from a public traveled way. If the Contractor elects to use the curing compound method on the bottom slab of box girder spans, the curing compound shall be curing compound (1).
- The top surface of highway bridge decks shall be cured by both the curing compound method and the water method. The curing compound shall be curing compound (1).
- Concrete surfaces of minor structures, as defined in Section 51-1.02, "Minor Structures," shall be cured by the water method, the forms-in-place method or the curing compound method.
- When deemed necessary by the Engineer during periods of hot weather, water shall be applied to concrete surfaces being cured by the curing compound method or by the forms-in-place method, until the Engineer determines that a cooling effect is no longer required. Application of water for this purpose will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

90-7.04 CURING PRECAST CONCRETE MEMBERS

• Precast concrete members shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing." Curing shall be provided for the minimum time specified for each method or until the concrete reaches its design strength, whichever is less. Steam curing may also be used for precast members and shall conform to the following provisions:

A. After placement of the concrete, members shall be held for a minimum 4-hour presteaming period. If the ambient air temperature is below 10°C, steam shall be applied during the presteaming period to hold the air surrounding the member at a temperature between 10°C and 32°C.
B. To prevent moisture loss on exposed surfaces during the presteaming period, members shall be covered as soon as possible after casting or the exposed surfaces shall be kept wet by fog spray or wet blankets.
C. Enclosures for steam curing shall allow free circulation of steam about the member and shall be constructed to contain the live steam with a minimum moisture loss. The use of tarpaulins or similar flexible covers will be permitted, provided they are kept in good repair and secured in such a manner as to prevent the loss of steam and moisture.
D. Steam at the jets shall be at low pressure and in a saturated condition. Steam jets shall not impinge directly on the concrete, test cylinders, or forms. During application of the steam, the temperature rise within the enclosure shall not exceed 22°C per hour. The curing temperature throughout the enclosure shall not exceed 65°C and shall be maintained at a constant level for a sufficient time necessary to develop the required transfer strength. Control cylinders shall be covered to prevent moisture loss and shall be placed in a location where temperature is representative of the average temperature of the enclosure.
E. Temperature recording devices that will provide an accurate, continuous, permanent record of the curing temperature shall be provided. A minimum of one temperature recording device per 60 m of continuous bed length will be required for checking temperature.
F. Members in pretension beds shall be detensioned immediately after the termination of steam curing while the concrete and forms are still warm, or the temperature under the enclosure shall be maintained above 15°C until the stress is transferred to the concrete.
G. Curing of precast concrete will be considered completed after termination of the steam curing cycle.

90-7.05 CURING PRECAST PRESTRESSED CONCRETE PILES

• Newly placed concrete for precast prestressed concrete piles shall be cured in conformance with the provisions in Section 90-7.04, "Curing Precast Concrete Members," except that piles with a class designation ending in C (corrosion resistant) shall be cured as follows:

A. Piles shall be either steam cured or water cured. If water curing is used, the piles shall be kept continuously wet by the application of water in conformance with the provisions in Section 90-7.01A, "Water Method."
B. If steam curing is used, the steam curing provisions in Section 90-7.04, "Curing Precast Concrete Members," shall apply except that the piles shall be kept continuously wet for their entire length for a period of not less than 3 days, including the holding and steam curing periods.

90-7.06 CURING SLOPE PROTECTION

• Concrete slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

• Concreted-rock slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing," or with a blanket of earth kept wet for 72 hours, or by sprinkling with a fine spray of water every 2 hours during the daytime for a period of 3 days.

90-7.07 CURING MISCELLANEOUS CONCRETE WORK

• Exposed surfaces of curbs shall be cured by pigmented curing compounds as specified in Section 90-7.01B, "Curing Compound Method."

• Concrete sidewalks, gutter depressions, island paving, curb ramps, driveways, and other miscellaneous concrete areas shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

• Shotcrete shall be cured for at least 72 hours by spraying with water, or by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

• Mortar and grout shall be cured by keeping the surface damp for 3 days.

• After placing, the exposed surfaces of sign structure foundations, including pedestal portions, if constructed, shall be cured for at least 72 hours by spraying with water, or by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

90-8 PROTECTING CONCRETE

90-8.01 GENERAL

• In addition to the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," the Contractor shall protect concrete as provided in this Section 90-8.

• Concrete shall not be placed on frozen or ice-coated ground or subgrade nor on ice-coated forms, reinforcing steel, structural steel, conduits, precast members, or construction joints.

• Under rainy conditions, placing of concrete shall be stopped before the quantity of surface water is sufficient to damage surface mortar or cause a flow or wash of the concrete surface, unless the Contractor provides adequate protection against damage.

• Concrete that has been frozen or damaged by other causes, as determined by the Engineer, shall be removed and replaced by the Contractor at the Contractor's expense.

90-8.02 PROTECTING CONCRETE STRUCTURES

• Structure concrete and shotcrete used as structure concrete shall be maintained at a temperature of not less than 7°C for 72 hours after placing and at not less than 4°C for an additional 4 days. When required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

90-8.03 PROTECTING CONCRETE PAVEMENT

• Pavement concrete shall be maintained at a temperature of not less than 4°C for 72 hours. When required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

• Except as provided in Section 7-1.08, "Public Convenience," the Contractor shall protect concrete pavement against construction and other activities that abrade, scar, discolor, reduce texture depth, lower coefficient of friction, or otherwise damage the surface. Stockpiling, drifting, or excessive spillage of soil, gravel, petroleum products, and concrete or asphalt mixes on the surface of concrete pavement is prohibited unless otherwise specified in these specifications, the special provisions or permitted by the Engineer.

• When ordered by the Engineer or shown on the plans or specified in the special provisions, pavement crossings shall be constructed for the convenience of public traffic. The material and work necessary for the construction of the crossings, and their subsequent removal and disposal, will be paid for at the contract unit prices for the items of work involved and if there are no contract items for the work involved, payment for pavement crossings will be made by extra work as provided in Section 4-1.03D, "Extra Work.". Where public traffic will be required to cross over the new pavement, Type III portland cement may be used in concrete, if permitted in writing by the Engineer. The pavement may be opened to traffic as soon as the concrete has developed a modulus of rupture of 3.8 MPa. The modulus of rupture will be determined by California Test 523.

• No traffic or Contractor's equipment, except as hereinafter provided, will be permitted on the pavement before a period of 10 days has elapsed after the concrete has been placed, nor before the concrete has developed a modulus of rupture of at least 3.8 MPa. Concrete that fails to attain a modulus of rupture of 3.8 MPa within 10 days shall not be opened to traffic until directed by the Engineer.

• Equipment for sawing weakened plane joints will be permitted on the pavement as specified in Section 40-1.08B, "Weakened Plane Joints."

• When requested in writing by the Contractor, the tracks on one side of paving equipment will be permitted on the pavement after a modulus of rupture of 2.4 MPa has been attained, provided that:

A. Unit pressure exerted on the pavement by the paver shall not exceed 135 kPa;
B. Tracks with cleats, grousers, or similar protuberances shall be modified or shall travel on planks or equivalent protective material, so that the pavement is not damaged; and
C. No part of the track shall be closer than 0.3-m from the edge of pavement.

• In case of visible cracking of, or other damage to the pavement, operation of the paving equipment on the pavement shall be immediately discontinued.

• Damage to the pavement resulting from early use of pavement by the Contractor's equipment as provided above shall be repaired by the Contractor at the Contractor's expense.

• The State will furnish the molds and machines for testing the concrete for modulus of rupture, and the Contractor, at the Contractor's expense, shall furnish the material and whatever labor the Engineer may require.

90-9 COMPRESSIVE STRENGTH

90-9.01 GENERAL

• Concrete compressive strength requirements consist of a minimum strength that shall be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or the special provisions or are shown on the plans.

• The compressive strength of concrete will be determined from test cylinders that have been fabricated from concrete sampled in conformance with the requirements of California Test 539. Test cylinders will be molded and initially field cured in conformance with California Test 540. Test cylinders will be cured and tested after receipt at the testing laboratory in conformance with the requirements of California Test 521. A strength test shall consist of the average strength of 2 cylinders fabricated from material taken from a single load of concrete, except that, if any cylinder should show evidence of improper sampling, molding, or testing, that cylinder shall be discarded and the strength test shall consist of the strength of the remaining cylinder.

• When concrete compressive strength is specified as a prerequisite to applying loads or stresses to a concrete structure or member, test cylinders for other than steam cured concrete will be cured in conformance with Method 1 of California Test 540. The compressive strength of concrete determined for these purposes will be evaluated on the basis of individual tests.

• When concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete strength to be used as a basis for acceptance of other than steam cured concrete will be determined from cylinders cured in conformance with Method 1 of California Test 540. If the result of a single compressive strength test at the maximum age specified or allowed is below the specified strength but is 95 percent or more of the specified strength, the Contractor shall, at the Contractor's expense, make corrective changes, subject to approval of the Engineer, in the mix proportions or in the concrete fabrication procedures, before placing additional concrete, and shall pay to the State $14 for each in-place cubic meter of concrete represented by the deficient test. If the result of a single compressive strength test at the maximum age specified or allowed is below 95 percent of the specified strength, but is 85 percent or more of the specified strength, the Contractor shall make the corrective changes specified above, and shall pay to the State $20 for each in place cubic meter of concrete represented by the deficient test. In addition, such corrective changes shall be made when the compressive strength of concrete tested at 7 days indicates, in the judgment of the Engineer, that the concrete will not attain the required compressive strength at the maximum age specified or allowed. Concrete represented by a single test that indicates a compressive strength of less than 85 percent of the specified 28-day compressive strength will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials."

• If the test result indicates that the compressive strength at the maximum curing age specified or allowed is below the specified strength, but is 85 percent or more of the specified strength, payments to the State as required above shall be made, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength of the concrete placed in the work meets or exceeds the specified 28-day compressive strength. If the test result indicates a compressive strength at the maximum curing age specified or allowed below 85 percent, the concrete represented by that test will be rejected, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength and quality of the concrete placed in the work are acceptable. If the evidence consists of tests made on cores taken from the work, the cores shall be obtained and tested in conformance with the requirements in ASTM Designation: C 42.

• No single compressive strength test shall represent more than 250 m^3.

• When a precast concrete member is steam cured, the compressive strength of the concrete will be determined from test cylinders that have been handled and stored in conformance with Method 3 of California Test 540. The compressive strength of steam cured concrete will be evaluated on the basis of individual tests representing specific portions of production. When the concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete shall be considered to be acceptable whenever its compressive strength reaches the specified 28-day compressive strength provided that strength is reached in not more than the maximum number of days specified or allowed after the member is cast.

• When concrete is specified by compressive strength, prequalification of materials, mix proportions, mixing equipment, and procedures proposed for use will be required prior to placement of the concrete. Prequalification shall be accomplished by the submission of acceptable certified test data or trial batch reports by the Contractor. Prequalification data shall be based on the use of materials, mix proportions, mixing equipment, procedures, and size of batch proposed for use in the work.

• Certified test data, in order to be acceptable, shall indicate that not less than 90 percent of at least 20 consecutive tests exceed the specified strength at the maximum number of cure days specified or allowed, and none of those tests are less than 95 percent of specified strength. Strength tests included in the data shall be the most recent tests made on concrete of the proposed mix design and all shall have been made within one year of the proposed use of the concrete.

• Trial batch test reports, in order to be acceptable, shall indicate that the average compressive strength of 5 consecutive concrete cylinders, taken from a single batch, at not more than 28 days (or the maximum age allowed) after molding shall be at least 4 MPa greater than the specified 28-day compressive strength, and no individual cylinder shall have a strength less than the specified strength at the maximum age specified or allowed. Data contained in the report shall be from trial batches that were produced within one year of the proposed use of specified strength concrete in the project. Whenever air-entrainment is required, the air content of trial batches shall be equal to or greater than the air content specified for the concrete without reduction due to tolerances.

• Tests shall be performed in conformance with either the appropriate California Test methods or the comparable ASTM test methods. Equipment employed in testing shall be in good condition and shall be properly calibrated. If the tests are performed during the life of the contract, the Engineer shall be notified sufficiently in advance of performing the tests in order to witness the test procedures.

• The certified test data and trial batch test reports shall include the following information:

A. Date of mixing.
B. Mixing equipment and procedures used.
C. The size of batch in cubic meters and the mass, type, and source of all ingredients used.
D. Penetration of the concrete.
E. The air content of the concrete if an air-entraining admixture is used.
F. The age at time of testing and strength of all concrete cylinders tested.

• Certified test data and trial batch test reports shall be signed by an official of the firm that performed the tests.

• When approved by the Engineer, concrete from trial batches may be used in the work at locations where concrete of a lower quality is required and the concrete will be paid for as the type or class of concrete required at that location.

• After materials, mix proportions, mixing equipment, and procedures for concrete have been prequalified for use, additional prequalification by testing of trial batches will be required prior to making changes that, in the judgment of the Engineer, could result in a strength of concrete below that specified.

• The Contractor’s attention is directed to the time required to test trial batches and the Contractor shall be responsible for production of trial batches at a sufficiently early date so that the progress of the work is not delayed.

• When precast concrete members are manufactured at the plant of an established manufacturer of precast concrete members, the mix proportions of the concrete shall be determined by the Contractor, and a trial batch and prequalification of the materials, mix proportions, mixing equipment, and procedures will not be required.

90-10 MINOR CONCRETE

90-10.01 GENERAL

• Concrete for minor structures, slope paving, curbs, sidewalks and other concrete work, when designated as minor concrete on the plans, in the specifications, or in the contract item, shall conform to the provisions specified herein.

• The Engineer, at the Engineer's discretion, will inspect and test the facilities, materials and methods for producing the concrete to ensure that minor concrete of the quality suitable for use in the work is obtained.

90-10.02 MATERIALS

• Minor concrete shall conform to the following requirements:

90-10.02A Cementitious Material

• Cementitious material shall conform to the provisions in Section 90-1.01, "Description."

90-10.02B Aggregate

• Aggregate shall be clean and free from deleterious coatings, clay balls, roots, and other extraneous materials.

• The Contractor shall submit to the Engineer for approval, a grading of the combined aggregate proposed for use in the minor concrete. After acceptance of the grading, aggregate furnished for minor concrete shall conform to that grading, unless a change is authorized in writing by the Engineer.

• The Engineer may require the Contractor to furnish periodic test reports of the aggregate grading furnished. The maximum size of aggregate used shall be at the option of the Contractor, but in no case shall the maximum size be larger than 37.5 mm or smaller than 19 mm.

• The Engineer may waive, in writing, the gradation requirements in this Section 90-10.02B, if, in the Engineer's opinion, the furnishing of the gradation is not necessary for the type or amount of concrete work to be constructed.

90-10.02C Water

• Water used for washing, mixing, and curing shall be free from oil, salts, and other impurities that would discolor or etch the surface or have an adverse affect on the quality of the concrete.

90-10.02D Admixtures

• The use of admixtures shall conform to the provisions in Section 90-4, "Admixtures."

90-10.03 PRODUCTION

• Cementitious material, water, aggregate, and admixtures shall be stored, proportioned, mixed, transported, and discharged in conformance with recognized standards of good practice that will result in concrete that is thoroughly and uniformly mixed, that is suitable for the use intended, and that conforms to requirements specified herein. Recognized standards of good practice are outlined in various industry publications such as are issued by American Concrete Institute, AASHTO, or the Department.

• The cementitious material content of minor concrete shall conform to the provisions in Section 90-1.01, "Description."

• The amount of water used shall result in a consistency of concrete conforming to the provisions in Section 90-6.06, "Amount of Water and Penetration." Additional mixing water shall not be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer.

• Discharge of ready-mixed concrete from the transporting vehicle shall be made while the concrete is still plastic and before stiffening occurs. An elapsed time of 1.5 hours (one hour in non-agitating hauling equipment), or more than 250 revolutions of the drum or blades, after the introduction of the cementitious material to the aggregates, or a temperature of concrete of more than 32°C will be considered conditions contributing to the quick stiffening of concrete. The Contractor shall take whatever action is necessary to eliminate quick stiffening, except that the addition of water will not be permitted.

• The required mixing time in stationary mixers shall be not less than 50 seconds or more than 5 minutes.

• The minimum required revolutions at mixing speed for transit-mixed concrete shall be not less than that recommended by the mixer manufacturer, and shall be increased, if necessary, to produce thoroughly and uniformly mixed concrete.

• Each load of ready-mixed concrete shall be accompanied by a weighmaster certificate that shall be delivered to the Engineer at the discharge location of the concrete, unless otherwise directed by the Engineer. The weighmaster certificate shall be clearly marked with the date and time of day when the load left the batching plant and, if hauled in truck mixers or agitators, the time the mixing cycle started.

• A Certificate of Compliance conforming to the provisions in Section 6–1.07, "Certificates of Compliance," shall be furnished to the Engineer, prior to placing minor concrete from a source not previously used on the contract, stating that minor concrete to be furnished meets contract requirements, including minimum cementitious material content specified.

90-10.04 CURING MINOR CONCRETE

• Curing minor concrete shall conform to the provisions in Section 90-7, "Curing Concrete."

90-10.05 PROTECTING MINOR CONCRETE

• Protecting minor concrete shall conform to the provisions in Section 90-8, "Protecting Concrete," except the concrete shall be maintained at a temperature of not less than 4°C for 72 hours after placing.

90-10.06 MEASUREMENT AND PAYMENT

• Minor concrete will be measured and paid for in conformance with the provisions specified in the various sections of these specifications covering concrete construction when minor concrete is specified in the specifications, shown on the plans, or indicated by contract item in the Engineer's Estimate.

90-11 MEASUREMENT AND PAYMENT

90-11.01 MEASUREMENT

• Portland cement concrete will be measured in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.

• When it is provided that concrete will be measured at the mixer, the volume in cubic meters shall be computed as the total mass of the batch in kilograms divided by the density of the concrete in kilograms per cubic meter. The total mass of the batch shall be calculated as the sum of all materials, including water, entering the batch. The density of the concrete will be determined in conformance with the requirements in California Test 518.

90-11.02 PAYMENT

- Portland cement concrete will be paid for in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.
- Full compensation for furnishing and incorporating admixtures required by these specifications or the special provisions will be considered as included in the contract prices paid for the concrete involved and no additional compensation will be allowed therefor.
- Should the Engineer order the Contractor to incorporate any admixtures in the concrete when their use is not required by these specifications or the special provisions, furnishing the admixtures and adding them to the concrete will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."
- Should the Contractor use admixtures in conformance with the provisions in Section 90-4.05, "Optional Use of Chemical Admixtures," or Section 90-4.07, "Optional Use of Air-entraining Admixtures," or should the Contractor request and obtain permission to use other admixtures for the Contractor's benefit, the Contractor shall furnish those admixtures and incorporate them into the concrete at the Contractor's expense and no additional compensation will be allowed therefor.

END OF AMENDMENTS

SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS

2-1.01 GENERAL

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the Proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in conformance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, each proposal shall have listed therein the portion of work that will be performed by each subcontractor listed.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

Submit request for substitution of an "or equal" item, and the data substantiating the request to the Department of Transportation, Division Of Construction - Duty Senior, Mail Station: 3 - B, 111 Grand Avenue / P. O. Box 23660, Oakland, Ca 94623-0660, so that the request is received by the Department by close of business on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

The contractor, sub recipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate. Each subcontract signed by the bidder must include this assurance.

Failure of the bidder to fulfill the requirements of the Special Provisions for submittals required to be furnished after bid opening, including but not limited to DBE or DVBE submittals, or escrowed bid documents, where applicable, may subject the bidder to a determination of the bidder's responsibility in the event it is the apparent low bidder on a future public works contracts.

2-1.015 FEDERAL LOBBYING RESTRICTIONS

Section 1352, Title 31, United States Code prohibits Federal funds from being expended by the recipient or any lower tier subrecipient of a Federal-aid contract to pay for any person for influencing or attempting to influence a Federal agency or Congress in connection with the awarding of any Federal-aid contract, the making of any Federal grant or loan, or the entering into of any cooperative agreement.

If any funds other than Federal funds have been paid for the same purposes in connection with this Federal-aid contract, the recipient shall submit an executed certification and, if required, submit a completed disclosure form as part of the bid documents.

A certification for Federal-aid contracts regarding payment of funds to lobby Congress or a Federal agency is included in the Proposal. Standard Form - LLL, "Disclosure of Lobbying Activities," with instructions for completion of the Standard Form is also included in the Proposal. Signing the Proposal shall constitute signature of the Certification.

The above-referenced certification and disclosure of lobbying activities shall be included in each subcontract and any lower-tier contracts exceeding $100,000. All disclosure forms, but not certifications, shall be forwarded from tier to tier until received by the Engineer.

The Contractor, subcontractors and any lower-tier contractors shall file a disclosure form at the end of each calendar quarter in which there occurs any event that requires disclosure or that materially affects the accuracy of the information contained in any disclosure form previously filed by the Contractor, subcontractors and any lower-tier contractors. An event that materially affects the accuracy of the information reported includes:

A. A cumulative increase of $25,000 or more in the amount paid or expected to be paid for influencing or attempting to influence a covered Federal action; or
B. A change in the person(s) or individual(s) influencing or attempting to influence a covered Federal action; or,
C. A change in the officer(s), employee(s), or Member(s) contacted to influence or attempt to influence a covered Federal action.

2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE)

This project is subject to Part 26, Title 49, Code of Federal Regulations entitled "Participation by Disadvantaged Business Enterprises in Department of Transportation Financial Assistance Programs." The Regulations in their entirety are incorporated herein by this reference.

Bidders shall be fully informed respecting the requirements of the Regulations and the Department's Disadvantaged Business Enterprise (DBE) program developed pursuant to the Regulations; particular attention is directed to the following matters:

A. A DBE must be a small business concern as defined pursuant to Section 3 of U.S. Small Business Act and relevant regulations promulgated pursuant thereto.
B. A DBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, vendor of material or supplies, or as a trucking company.
C. A DBE bidder, not bidding as a joint venture with a non-DBE, will be required to document one or a combination of the following:

    1. The bidder will meet the goal by performing work with its own forces.
    2. The bidder will meet the goal through work performed by DBE subcontractors, suppliers or trucking companies.
    3. The bidder, prior to bidding, made adequate good faith efforts to meet the goal.

D. A DBE joint venture partner must be responsible for specific contract items of work, or portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DBE joint venture partner must share in the capital contribution, control, management, risks and profits of the joint venture. The DBE joint venturer must submit the joint venture agreement with the proposal or the DBE Information form required in the Section entitled "Submission of DBE Information" of these special provisions.
E. A DBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
F. DBEs must be certified by the California Unified Certification Program (CUCP). It is the contractor's responsibility to confirm that the firm is DBE certified as of the date of bid opening. Listings of DBEs certified by the CUCP are available from the following sources:

    1. The Department's DBE Directory, which is published quarterly. This Directory may be obtained from the Department of Transportation, Materiel Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520.
    2. The Department's web site at http://www.dot.ca.gov/hq/bep.
    3. The organizations listed in the Section entitled "DBE Goal for this Project" of these special provisions.

G. Credit for materials or supplies purchased from DBEs will be as follows:

    1. If the materials or supplies are obtained from a DBE manufacturer, 100 percent of the cost of the materials or supplies will count toward the DBE goal. A DBE manufacturer is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications.

2. If the materials or supplies are purchased from a DBE regular dealer, 60 percent of the cost of the materials or supplies will count toward the DBE goal. A DBE regular dealer is a firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications and required under the contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business. To be a DBE regular dealer, the firm must be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question. A person may be a DBE regular dealer in such bulk items as petroleum products, steel, cement, gravel, stone, or asphalt without owning, operating, or maintaining a place of business as provided in this paragraph G.2. if the person both owns and operates distribution equipment for the products. Any supplementing of regular dealers' own distribution equipment shall be by a long-term lease agreement and not on an ad hoc or contract-by-contract basis. Packagers, brokers, manufacturers' representatives, or other persons who arrange or expedite transactions are not DBE regular dealers within the meaning of this paragraph G.2.
3. Credit for materials or supplies purchased from a DBE which is neither a manufacturer nor a regular dealer will be limited to the entire amount of fees or commissions charged for assistance in the procurement of the materials and supplies, or fees or transportation charges for the delivery of materials or supplies required on a job site, provided the fees are reasonable and not excessive as compared with fees charged for similar services.

H. Credit for DBE trucking companies will be as follows:

1. The DBE must be responsible for the management and supervision of the entire trucking operation for which it is responsible on a particular contract, and there cannot be a contrived arrangement for the purpose of meeting the DBE goal.
2. The DBE must itself own and operate at least one fully licensed, insured, and operational truck used on the contract.
3. The DBE receives credit for the total value of the transportation services it provides on the contract using trucks its owns, insures, and operates using drivers it employs.
4. The DBE may lease trucks from another DBE firm, including an owner-operator who is certified as a DBE. The DBE who leases trucks from another DBE receives credit for the total value of the transportation services the lessee DBE provides on the contract.
5. The DBE may also lease trucks from a non-DBE firm, including an owner-operator. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement. The DBE does not receive credit for the total value of the transportation services provided by the lessee, since these services are not provided by a DBE.
6. For the purposes of this paragraph H, a lease must indicate that the DBE has exclusive use of and control over the truck. This does not preclude the leased truck from working for others during the term of the lease with the consent of the DBE, so long as the lease gives the DBE absolute priority for use of the leased truck. Leased trucks must display the name and identification number of the DBE.

I. Noncompliance by the Contractor with the requirements of the regulations constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.
J. Bidders are encouraged to use services offered by financial institutions owned and controlled by DBEs.

2-1.02A DBE GOAL FOR THIS PROJECT

The Department has established the following goal for Disadvantaged Business Enterprise (DBE) participation for this project:

Disadvantaged Business Enterprise (DBE): 12 percent

Bidders may use the services of the following firms to contact interested DBEs. These firms are available to assist DBEs in preparing bids for subcontracting or supplying materials.

The following firms may be contacted for projects in the following locations:

Districts 04, 05 (except San Luis Obispo and Santa Barbara Counties), 06 (except Kern County) and 10:	Districts 08 and 11:
See the Department's DBE database at: http://www.dot.ca.gov/hq/bep/	Padilla & Associates - San Diego 2725 Congress Street, Suite 1D San Diego, CA 92110 Telephone: (619) 725-0843 FAX No.: (619) 725-0854

Districts 07, 08, and 12; in San Luis Obispo and Santa Barbara Counties in District 05; and in Kern County in District 06:	Districts 01, 02, 03 and 09:
Padilla & Associates - Commerce 5675 East Telegraph Rd., Suite A-260 Commerce, CA 90040 Telephone: (323) 728-8847 FAX No.: (323) 728-8867	See the Department's DBE database at: http://www.dot.ca.gov/hq/bep/

2-1.02B SUBMISSION OF DBE INFORMATION

All bidders shall complete the "CALTRANS BIDDER - DBE INFORMATION" form included in the Proposal and submit it WITH THE BID.

Failure to submit the "CALTRANS BIDDER - DBE INFORMATION" form with the bid will be grounds for finding the bid nonresponsive.

The bidder shall submit written confirmation from each DBE that the DBE is participating in the contract, and include the confirmation with the submittal of the bid or submit it by the time specified for submittal of the GOOD FAITH EFFORT (GFE) DOCUMENTATION form. A copy of a DBE's quote will serve as written confirmation that the DBE is participating in the contract.

Where the bidder has not met the designated DBE goal, it must submit good faith efforts (GFE) documentation to establish that, prior to the bid, it made adequate good faith efforts to meet the goal.

Bidders are cautioned that even though their "CALTRANS BIDDER - DBE INFORMATION" form indicates they will meet the stated DBE goal, they should also submit their GFE documentation within the time specified herein, to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The apparent successful bidder (low bidder), the second low bidder and the third low bidder shall complete and submit the GOOD FAITH EFFORT (GFE) DOCUMENTATION form, if they have not met the goal, to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. ON THE FOURTH DAY, not including Saturdays, Sundays and legal holidays, following bid opening. GFE documentation sent by U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Other bidders need not submit GFE documentation unless requested to do so by the Department. When a request is made by the Department, the GFE documentation of the other bidders shall be received by the Department within 4 days of the request, not including Saturdays, Sundays and legal holidays, unless a later time is authorized by the Department.

If it is determined that GFE documentation is needed to determine a bidder's eligibility for award, failure of the bidder to have submitted the GFE documentation by the time specified herein will be grounds for finding the bid or proposal nonresponsive.

It is the bidder's responsibility to make enough work available to DBEs and to select those portions of the work or material needs consistent with the available DBEs to meet the goal for DBE participation.

The bidder's "CALTRANS BIDDER - DBE INFORMATION" form shall include the names, addresses and phone numbers of DBE firms that will participate, with a complete description of work or supplies to be provided by each, and the dollar value of each DBE transaction. When 100 percent of a contract item of work is not to be performed or furnished by a DBE, a description of the exact portion of that work to be performed or furnished by that DBE shall be included in the DBE information, including the planned location of that work. The work that a DBE prime contractor has committed to

performing with its own forces as well as the work that it has committed to be performed by DBE subcontractors, suppliers and trucking companies will count toward the goal.

The bidder's good faith effort (GFE) documentation shall establish that good faith efforts to meet the DBE goal have been made.

In order to establish the bidder's good faith efforts to meet the DBE goal, the bidder should include the following information and supporting documents, as necessary:

A. Items of work the bidder has made available to DBE firms. Identify those items of work the bidder might otherwise perform with its own forces and those items that have been broken down into economically feasible units to facilitate DBE participation. For each item listed, show the dollar value and percentage of the total contract. It is the bidder's responsibility to demonstrate that sufficient work to meet the goal was made available to DBE firms.
B. The names of certified DBEs and the dates on which they were solicited to bid on the project. Include the items of work offered. Describe the methods used for following up initial solicitations to determine with certainty if the DBEs were interested, and the dates of the follow-up. Attach supporting documents such as copies of letters, memos, facsimiles sent, telephone logs, telephone billing statements, and other evidence of solicitation. Bidders are reminded to solicit certified DBEs through all reasonable and available means and provide sufficient time to allow DBEs to respond.
C. For each item of work made available, the DBEs that provided quotes, the selected firm and its status as a DBE, the price quote for each firm, and the name, address and telephone number for each firm. If the firm selected for the item is not a DBE, provide the reasons for the selection.
D. The names and dates of each publication in which a request for DBE participation for the project was placed by the bidder. Attach copies of the published advertisements.
E. The names of agencies, including the firms listed in Section 2-1.02A, "DBE Goal for this Project," and the dates on which they were contacted to provide assistance in contacting, recruiting and using DBE firms. If the agencies were contacted in writing, provide copies of supporting documents.
F. Descriptions of the efforts made to provide interested DBEs with adequate information about the plans, specifications and requirements of the contract to assist them in responding to a solicitation. Where the bidder has provided information, identify the name of the DBE assisted, the nature of the information provided, and date of contact. Provide copies of supporting documents, as appropriate.
G. Descriptions of any and all efforts made to assist interested DBEs in obtaining bonding, lines of credit, insurance, necessary equipment, supplies, and materials (excluding supplies and equipment which the DBE subcontractor purchases or leases from the prime contractor or its affiliate). Where such assistance was provided by the bidder, identify the name of the DBE assisted, nature of the assistance offered, and date. Provide copies of supporting documents, as appropriate.
H. Any additional data to support a demonstration of good faith efforts.

SECTION 3. AWARD AND EXECUTION OF CONTRACT

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

Bid protests are to be delivered to the following address: Department of Transportation, MS 43, Attn: Office Engineer, 1727 30th Street, Sacramento, CA 95816 or by facsimile to the Office Engineer at (916) 227-6282.

The award of the contract, if it be awarded, will be made within 30 days after the opening of the proposals if the apparent lowest bidder has met the goal for DBE participation. The award of the contract, if it be awarded, will be made within 60 days after the opening of the proposals if the apparent lowest bidder has not met the goal for DBE participation but has claimed good faith efforts to do so. These periods will be subject to extension for such further periods as may be agreed upon in writing between the Department and the bidders concerned. The award, if made, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DBE participation or has demonstrated, to the satisfaction of the Department, adequate good faith efforts to do so. Meeting the goal for DBE participation or demonstrating, to the satisfaction of the Department, adequate good faith efforts to do so is a condition for being eligible for award of contract.

The contract shall be executed by the successful bidder and shall be returned, together with the contract bonds, to the Department so that it is received within 10 days, not including Saturdays, Sundays and legal holidays, after the bidder has received the contract for execution. Failure to do so shall be just cause for forfeiture of the proposal guaranty. The executed contract documents shall be delivered to the following address: Department of Transportation MS 43, Attn: Office Engineer, 1727 30th Street, Sacramento, CA 95816.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, payee

shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 31 percent of payments due the contractor and penalties of up to $20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Attention is directed to the provisions in Section 8-1.03, "Beginning of Work," in Section 8-1.06, "Time of Completion," and in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and these special provisions.

The Contractor shall furnish the Engineer with a statement from the vendor that the order for the electrical materials required for this contract has been received and accepted by the vendor; and the statement shall be furnished within 15 calendar days after the contract has been approved by the Attorney General, or the attorney appointed and authorized to represent the Department of Transportation. The statement shall give the date that the electrical materials will be shipped. If the Contractor has the necessary materials on hand, the Contractor will not be required to furnish the vendor's statement.

The Contractor shall begin work within fifteen calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

The work shall be diligently prosecuted to completion before the expiration of **440 WORKING DAYS** beginning on the date that work begins, or beginning on the fifteenth calendar day after approval of the contract, whichever occurs first.

The Contractor shall pay to the State of California the sum of $15,000 per day, for each and every calendar day's delay in finishing the work in excess of **440 WORKING DAYS**.

The Contractor shall pay to the State of California the sums identified in “Relations With Santa Clara Valley Transportation Authority,” of these special provisions for finishing working in excess of time identified.

The Contractor shall pay to the State of California the sum of $4,000 per day for each and every calendar day’s delay in finishing working in excess of the number of working days prescribed for completion of Stage 1A (Phase 1 and Phase 2) as prescribed in “Order of Work” of these special provisions.

The Contractor shall pay to the State of California the sum of $15,000 per day for each and every calendar day’s delay in finishing working in excess of the number of working days prescribed for completion of bike path as prescribed in “Order of Work” of these special provisions.

The 72 hours advance notice before beginning work specified in Section 8-1.03, "Beginning of Work," of the Standard Specifications is changed to 5 days advance notice for this project.

SECTION 5. GENERAL

SECTION 5-1. MISCELLANEOUS

5-1.01 PLANS AND WORKING DRAWINGS

When the specifications require working drawings to be submitted to the Division of Structure Design, the drawings shall be submitted to: Division of Structure Design, Documents Unit, Mail Station 9, 1801 30th Street, Sacramento, CA 95816, Telephone 916 227-8252.

5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK

Attention is directed to "Differing Site Conditions" of these special provisions regarding physical conditions at the site which may differ from those indicated in "Materials Information," log of test borings or other geotechnical information obtained by the Department's investigation of site conditions.

5-1.012 DIFFERING SITE CONDITIONS

Attention is directed to Section 5-1.116, "Differing Site Conditions," of the Standard Specifications.

During the progress of the work, if subsurface or latent conditions are encountered at the site differing materially from those indicated in the "Materials Information," log of test borings, other geotechnical data obtained by the Department's investigation of subsurface conditions, or an examination of the conditions above ground at the site, the party discovering those conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

The Contractor will be allowed 15 days from the notification of the Engineer's determination of whether or not an adjustment of the contract is warranted, in which to file a notice of potential claim in conformance with the provisions of Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and as specified herein; otherwise the decision of the Engineer shall be deemed to have been accepted by the Contractor as correct. The notice of potential claim shall set forth in what respects the Contractor's position differs from the Engineer's determination and provide any additional information obtained by the Contractor, including but not limited to additional geotechnical data. The notice of potential claim shall be

accompanied by the Contractor's certification that the following were made in preparation of the bid: a review of the contract, a review of the "Materials Information," a review of the log of test borings and other records of geotechnical data to the extent they were made available to bidders prior to the opening of bids, and an examination of the conditions above ground at the site. Supplementary information, obtained by the Contractor subsequent to the filing of the notice of potential claim, shall be submitted to the Engineer in an expeditious manner.

5-1.013 LINES AND GRADES

Attention is directed to Section 5-1.07, "Lines and Grades," of the Standard Specifications.

Stakes or marks will be set by the Engineer in conformance with the requirements in Chapter 12, "Construction Surveys," of the Department's Surveys Manual.

5-1.015 LABORATORY

When a reference is made in the specifications to the "Laboratory," the reference shall mean Division of Engineering Services - Materials Engineering and Testing Services and Division of Engineering Services - Geotechnical Services of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean Division of Engineering Services - Materials Engineering and Testing Services and Division of Engineering Services - Geotechnical Services, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

5-1.017 CONTRACT BONDS

Attention is directed to Section 3-1.02, "Contract Bonds," of the Standard Specifications and these special provisions.

The payment bond shall be in a sum not less than one hundred percent of the total amount payable by the terms of the contract.

5-1.019 COST REDUCTION INCENTIVE

Attention is directed to Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

Prior to preparing a written cost reduction proposal, the Contractor shall request a meeting with the Engineer to discuss the proposal in concept. Items of discussion will also include permit issues, impact on other projects, impact on the project schedule, peer reviews, overall merit of the proposal, and review times required by the Department and other agencies.

If a cost reduction proposal submitted by the Contractor, and subsequently approved by the Engineer, provides for a reduction in contract time, 50 percent of that contract time reduction shall be credited to the State by reducing the contract working days, not including plant establishment. Attention is directed to "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions regarding the working days.

If a cost reduction proposal submitted by the Contractor, and subsequently approved by the Engineer, provides for a reduction in traffic congestion or avoids traffic congestion during construction, 60 percent of the estimated net savings in construction costs attributable to the cost reduction proposal will be paid to the Contractor. In addition to the requirements in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications, the Contractor shall provide detailed comparisons of the traffic handling between the existing contract and the proposed change, and estimates of the traffic volumes and congestion.

5-1.02 LABOR NONDISCRIMINATION

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM

(GOV. CODE, SECTION 12990)

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of $5000 or more.

5-1.022 EXCLUSION OF RETENTION

In conformance with 49 CFR, Part 26, Subpart B, Section 26.29 (b)(1), the retention of proceeds required by Public Contract Code Section 10261 shall not apply. In conformance with Public Contract Code 7200 (b), in subcontracts between the Contractor and a subcontractor and in subcontracts between a subcontractor and any subcontractor thereunder, retention

proceeds shall not be withheld, and the exceptions provided in Public Contract Code 7200 (c) shall not apply. At the option of the Contractor, subcontractors may be required to furnish payment and performance bonds issued by an admitted surety insurer.

The third paragraph of Section 9-1.06, "Partial Payments," of the Standard Specifications, and Section 9-1.065, "Payment of Withheld Funds," of the Standard Specifications shall not apply.

5-1.023 UNSATISFACTORY PROGRESS

If the number of working days charged to the contract exceeds 75 percent of the working days in the current time of completion and the percent working days elapsed exceeds the percent work completed by more than 15 percentage points, the Department will withhold 10 percent of the amount due on the current monthly estimate.

The percent working days elapsed will be determined from the number of working days charged to the contract divided by the number of contract working days in the current time of completion, expressed as a percentage. The number of contract working days in the current time of completion shall consist of the original contract working days increased or decreased by time adjustment s approved by the Engineer.

The percent work completed will be determined by the Engineer from the sum of payments made to date plus the amount due on the current monthly estimate, divided by the current total estimated value of the work, expressed as a percentage.

When the percent of working days elapsed minus the percent of work completed is less than or equal to 15 percentage points, the funds withheld shall be returned to the Contractor with the next monthly progress payment.

Funds kept or withheld from payment, due to the failure of the Contractor to comply with the provisions of the contract, will not be subject to the requirements of Public Contract Code 7107 or to the payment of interest pursuant to Public Contract Code Section 10261.5.

5-1.03 INTEREST ON PAYMENTS

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments, and claim payments as follows:

A. Unpaid progress payments, payment after acceptance, and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
B. Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in conformance with the provisions in Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
C. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and extra work payments shall be 10 percent per annum.
D. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

5-1.04 PUBLIC SAFETY

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

A. Excavations**.—**The near edge of the excavation is 3.6 m or less from the edge of the lane, except:

1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
2. Excavations less than 0.3-m deep.
3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).

6. Excavations protected by existing barrier or railing.

B. Temporarily Unprotected Permanent Obstacles.—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.

C. Storage Areas.—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications. Temporary railing (Type K), conforming to the details shown on 1999 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.05 TESTING

Testing of materials and work shall conform to the provisions in Section 6-3, "Testing," of the Standard Specifications and these special provisions.

Whenever the provisions of Section 6-3.01, "General," of the Standard Specifications refer to tests or testing, it shall mean tests to assure the quality and to determine the acceptability of the materials and work.

The Engineer will deduct the costs for testing of materials and work found to be unacceptable, as determined by the tests performed by the Department, and the costs for testing of material sources identified by the Contractor which are not used for the work, from moneys due or to become due to the Contractor. The amount deducted will be determined by the Engineer.

5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered

harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

5-1.07 YEAR 2000 COMPLIANCE

This contract is subject to Year 2000 Compliance for automated devices in the State of California.

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year 2000 is recognized and processed as a leap year. The product shall operate accurately in the manner in which the product was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all automated devices furnished for the project.

5-1.075 BUY AMERICA REQUIREMENTS

Attention is directed to the "Buy America" requirements of the Surface Transportation Assistance Act of 1982 (Section 165) and the Intermodal Surface Transportation Efficiency Act of 1991 (ISTEA) Sections 1041(a) and 1048(a), and the regulations adopted pursuant thereto. In conformance with the law and regulations, all manufacturing processes for steel and iron materials furnished for incorporation into the work on this project shall occur in the United States; with the exception that pig iron and processed, pelletized and reduced iron ore manufactured outside of the United States may be used in the domestic manufacturing process for such steel and iron materials. The application of coatings, such as epoxy coating, galvanizing, painting, and other coatings that protect or enhance the value of steel or iron materials shall be considered a manufacturing process subject to the "Buy America" requirements.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for steel and iron materials. The certificates, in addition to certifying that the materials comply with the specifications, shall specifically certify that all manufacturing processes for the materials occurred in the United States, except for the above exceptions.

The requirements imposed by the law and regulations do not prevent a minimal use of foreign steel and iron materials if the total combined cost of the materials used does not exceed one-tenth of one percent (0.1 percent) of the total contract cost or $2500, whichever is greater. The Contractor shall furnish the Engineer acceptable documentation of the quantity and value of the foreign steel and iron prior to incorporating the materials into the work.

5-1.08 SUBCONTRACTOR AND DBE RECORDS

The Contractor shall maintain records showing the name and business address of each first-tier subcontractor. The records shall also show the name and business address of every DBE subcontractor, DBE vendor of materials and DBE trucking company, regardless of tier. The records shall show the date of payment and the total dollar figure paid to all of these firms. DBE prime contractors shall also show the date of work performed by their own forces along with the corresponding dollar value of the work.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 (F) and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer. The form shall be furnished to the Engineer within 90 days from the date of contract acceptance. $10,000 will be withheld from payment until the Form CEM-2402 (F) is submitted. The amount will be returned to the Contractor when a satisfactory Form CEM-2402 (F) is submitted.

Prior to the fifteenth of each month, the Contractor shall submit documentation to the Engineer showing the amount paid to DBE trucking companies listed in the Contractor's DBE information. This monthly documentation shall indicate the portion of the revenue paid to DBE trucking companies which is claimed toward DBE participation. The Contractor shall also obtain and submit documentation to the Engineer showing the amount paid by DBE trucking companies to all firms, including owner-operators, for the leasing of trucks. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement. The records must confirm that the amount of credit claimed toward DBE participation conforms with Section 2-1.02, "Disadvantaged Business Enterprise," of these special provisions.

The Contractor shall also obtain and submit documentation to the Engineer showing the truck number, owner's name, California Highway Patrol CA number, and if applicable, the DBE certification number of the owner of the truck for all

trucks used during that month for which DBE participation will be claimed. This documentation shall be submitted on Form CEM-2404 (F).

5-1.083 DBE CERTIFICATION STATUS

If a DBE subcontractor is decertified during the life of the project, the decertified subcontractor shall notify the Contractor in writing with the date of decertification. If a subcontractor becomes a certified DBE during the life of the project, the subcontractor shall notify the Contractor in writing with the date of certification. The Contractor shall furnish the written documentation to the Engineer.

Upon completion of the contract, Form CEM-2403 (F) indicating the DBE's existing certification status shall be signed and certified correct by the Contractor. The certified form shall be furnished to the Engineer within 90 days from the date of contract acceptance.

5-1.086 PERFORMANCE OF DBE SUBCONTRACTORS AND SUPPLIERS

The DBEs listed by the Contractor in response to the provisions in Section 2-1.02B, "Submission of DBE Information," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to use other forces or sources of materials may be requested for the following reasons:

A. The listed DBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when such written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of such subcontractor's or supplier's written bid, is presented by the Contractor.
B. The listed DBE becomes bankrupt or insolvent.
C. The listed DBE fails or refuses to perform the subcontract or furnish the listed materials.
D. The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DBE subcontractor fails or refuses to meet the bond requirements of the Contractor.
E. The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial conformance with the plans and specifications, or the subcontractor is substantially delaying or disrupting the progress of the work.
F. It would be in the best interest of the State.

The Contractor shall not be entitled to any payment for such work or material unless it is performed or supplied by the listed DBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

5-1.09 SUBCONTRACTING

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, and Section 2, "Proposal Requirements and Conditions," and Section 3, "Award and Execution of Contract," of these special provisions.

Pursuant to the provisions of Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

http://www.dir.ca.gov/DLSE/Debar.html.

The provisions in the third paragraph of Section 8-1.01, "Subcontracting," of the Standard Specifications, that the Contractor shall perform with the Contractor's own organization contract work amounting to not less than 50 percent of the original contract price, is not changed by the Federal Aid requirement specified under "Required Contract Provisions Federal-Aid Construction Contracts" in Section 14 of these special provisions that the Contractor perform not less than 30 percent of the original contract work with the Contractor's own organization.

Each subcontract and any lower tier subcontract that may in turn be made shall include the "Required Contract Provisions Federal-Aid Construction Contracts" in Section 14 of these special provisions. This requirement shall be enforced as follows:

A. Noncompliance shall be corrected. Payment for subcontracted work involved will be withheld from progress payments due, or to become due, until correction is made. Failure to comply may result in termination of the contract.

In conformance with the Federal DBE regulations Sections 26.53(f)(1) and 26.53(f)(2) Part 26, Title 49 CFR:

A. The Contractor shall not terminate for convenience a DBE subcontractor listed in response to Section 2-1.02B, "Submission of DBE Information," and then perform that work with its own forces, or those of an affiliate without the written consent of the Department, and
B. If a DBE subcontractor is terminated or fails to complete its work for any reason, the Contractor will be required to make good faith efforts to substitute another DBE subcontractor for the original DBE subcontractor, to the extent needed to meet the contract goal.

The requirement in Section 2-1.02, "Disadvantaged Business Enterprise (DBE)," of these special provisions that DBEs must be certified on the date bids are opened does not apply to DBE substitutions after award of the contract.

5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code concerning prompt payment to subcontractors.

5-1.103 RECORDS

The Contractor shall maintain cost accounting records for the contract pertaining to, and in such a manner as to provide a clear distinction between, the following six categories of costs of work during the life of the contract:

A. Direct costs of contract item work.
B. Direct costs of changes in character in conformance with Section 4-1.03C, "Changes in Character of Work," of the Standard Specifications.
C. Direct costs of extra work in conformance with Section 4-1.03D, "Extra Work," of the Standard Specifications.
D. Direct costs of work not required by the contract and performed for others.
E. Direct costs of work performed under a notice of potential claim in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications.
F. Indirect costs of overhead.

Cost accounting records shall include the information specified for daily extra work reports in Section 9-1.03C, "Records," of the Standard Specifications. The requirements for furnishing the Engineer completed daily extra work reports shall only apply to work paid for on a force account basis.

The cost accounting records for the contract shall be maintained separately from other contracts, during the life of the contract, and for a period of not less than 3 years after the date of acceptance of the contract. If the Contractor intends to file claims against the Department, the Contractor shall keep the cost accounting records specified above until complete resolution of all claims has been reached.

5-1.11 PARTNERING

The State will promote the formation of a "Partnering" relationship with the Contractor in order to effectively complete the contract to the benefit of both parties. The purpose of this relationship is to maintain a cooperative communication and to mutually resolve conflicts at the lowest responsible management level.

The Contractor may request the formation of a "Partnering" relationship by submitting a request in writing to the Engineer after approval of the contract. If the Contractor's request for "Partnering" is approved by the Engineer, scheduling of a "Partnering Workshop," selecting the "Partnering" facilitator and workshop site, and other administrative details shall be as agreed to by both parties. If agreed to by the parties, additional "Partnering Workshops" will be conducted as needed throughout the life of the contract.

A one-day "Training in Partnering Concepts" session will be conducted regardless of whether the Contractor requests the formation of a "Partnering" relationship. The "Training in Partnering Concepts" session will be conducted locally for the Contractor's and the Engineer's project representatives. The Contractor shall be represented by a minimum of 2 representatives, one being the Contractor's authorized representative pursuant to Section 5-1.06, "Superintendence," of the Standard Specifications. Scheduling of the "Training in Partnering Concepts" session and selection of the trainer and training site shall be determined cooperatively by the Contractor and the Engineer. If, upon the Contractor's request, "Partnering" is approved by the Engineer, the "Training in Partnering Concepts" session shall be conducted prior to the initial "Partnering Workshop."

The costs involved in providing the "Training in Partnering Concepts" trainer and training site will be borne entirely by the State. The costs will be determined in conformance with the provisions in Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor the sum of that cost, except no markups will be allowed.

The costs involved in providing the "Partnering Workshop" facilitator and workshop site will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost in providing the "Partnering Workshop"

facilitator and workshop site in conformance with the provisions in Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor one-half of that cost, except no markups will be allowed.

All other costs associated with "Training in Partnering Concepts" and "Partnering Workshops" will be borne separately by the party incurring the costs, such as wages and travel expenses, and no additional compensation will be allowed therefor.

The establishment of a "Partnering" relationship will not change or modify the terms and conditions of the contract and will not relieve either party of the legal requirements of the contract.

5-1.114 VALUE ANALYSIS

The Contractor may submit to the Engineer, in writing, a request for a "Value Analysis" workshop. The purpose for having a workshop is to identify value enhancing opportunities and to consider modifications to the plans and specifications that will reduce either the total cost, time of construction or traffic congestion, without impairing, in any manner, the essential functions or characteristics of the project including, but not limited to, service life, economy of operation, ease of maintenance, benefits to the travelling public, desired appearance, or design and safety standards.

To maximize the potential benefits of a workshop, the request should be submitted to the Engineer early in the project after approval of the contract. If the Contractor's request for a "Value Analysis" workshop is approved by the Engineer, scheduling of a workshop, selecting the facilitator and workshop site, and other administrative details shall be determined cooperatively by the Contractor and the Engineer.

The workshop shall be conducted in conformance with the methodology described in the Department's "Value Analysis Team Guide" available at the Department's web site at:

http://www.dot.ca.gov/hq/oppd/value/

The facilitator shall be a Certified Value Specialist (CVS) as recognized by the Society of American Value Engineers (SAVE) International, which may be contacted as follows:

SAVE International, 60 Revere Drive, Northbrook, IL 60062
Telephone 1-847-480-1730, FAX 1-847-480-9282

The Contractor may submit recommendations resulting from a "Value Analysis" workshop for approval by the Engineer as cost reduction incentive proposals in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

The costs involved in providing the "Value Analysis" facilitator and workshop site will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost in providing the "Value Analysis" facilitator and workshop site in conformance with the provisions in Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor one-half of that cost, except no markups will be allowed.

All other costs associated with the "Value Analysis" workshop will be borne separately by the party incurring the costs, such as wages and travel expenses, and no additional compensation will be allowed therefor.

5-1.12 DISPUTE REVIEW BOARD

GENERAL

To assist in the resolution of disputes or potential claims arising out of the work of this project, a Dispute Review Board, hereinafter referred to as the "DRB," shall be established by the Engineer and Contractor cooperatively upon approval of the contract. The DRB is intended to assist the contract administrative claims resolution process as specified in the provisions in Section 9-1.04, "Notice of Potential Claim," and Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications and these special provisions. The DRB shall not serve as a substitute for provisions in the specifications in regard to filing potential claims. The requirements and procedures established in this section shall be a prerequisite to filing a claim, filing for arbitration, or filing for litigation prior or subsequent to project completion.

The DRB shall be utilized when dispute or potential claim resolution at the project level is unsuccessful. The DRB shall function as specified herein until the day of acceptance of the contract, at which time the work of the DRB will cease except for completion of unfinished reports. No DRB dispute meetings shall take place later than 30 days prior to acceptance of contract. After acceptance of contract, disputes or potential claims which have followed the dispute resolution processes of the Standard Specifications and these special provisions, but have not been resolved, shall be stated or restated by the Contractor, in response to the Proposed Final Estimate within the time limits provided in Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. The State will review those claims in conformance with the provisions in Section 9-1.07B of the Standard Specifications. Following the adherence to and completion of the contractual administrative

claims procedure, the Contractor may file for arbitration in conformance with the provisions in Section 9-1.10, "Arbitration," of the Standard Specifications and these special provisions.

Disputes, as used in this section, shall include differences of opinion, properly noticed as provided hereinafter, between the State and Contractor on matters related to the work and other subjects considered by the State or Contractor, or by both, to be of concern to the DRB on this project, except matters relating to Contractor, subcontractor or supplier potential claims not actionable against the Department as specified in these special provisions or quantification of disputes for overhead type expenses or costs. Disputes for overhead type expenses or costs shall conform to the requirements of Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. Whenever the term "dispute" or "disputes" is used herein, it shall be deemed to include potential claims as well as disputes.

The DRB shall serve as an advisory body to assist in the resolution of disputes between the State and the Contractor, hereinafter referred to as the "parties." The DRB shall consider disputes referred to it, and furnish written reports containing findings and recommendations pertaining to those disputes, to the parties to aid in resolution of the differences between them. DRB findings and recommendations are not binding on the parties.

SELECTION PROCESS, DISCLOSURE AND APPOINTMENTS

The DRB shall consist of one member selected by the State and approved by the Contractor, one member selected by the Contractor and approved by the State, and a third member selected by the first 2 members and approved by both the State and the Contractor. The third member shall act as the DRB Chairperson.

DRB members shall be especially knowledgeable in the type of construction and contract documents potentially anticipated by the contract. DRB members shall discharge their responsibilities impartially as an independent body, considering the facts and circumstances related to the matters under consideration, pertinent provisions of the contract and applicable laws and regulations.

The State and the Contractor shall nominate and approve DRB members in conformance with the terms and conditions of the Dispute Review Board Agreement and these special provisions, within 45 days of the approval of the contract. Each party shall provide written notification to the other of the name of their selected DRB nominee along with the prospective member's complete written disclosure statement.

Disclosure statements shall include a resume of the prospective member's experience and a declaration statement describing past, present, anticipated, and planned relationships, including indirect relationships through the prospective member's primary or full-time employer, to this project and with the parties involved in this construction contract, including but not limited to, relevant subcontractors or suppliers to the parties, parties' principals, or parties' counsel. DRB members shall also include a full disclosure of close professional or personal relationships with all key members of the contract. Objections to nominees must be based on a specific breech or violation of nominee responsibilities or on nominee qualifications under these provisions unless otherwise specified. The Contractor or the State may, on a one-time basis, object to the other's nominee without specifying a reason and this person will not be selected for the DRB. Another person shall then be nominated within 15 days.

The first duty of the State and Contractor selected members of the DRB shall be to select and recommend a prospective third DRB member to the parties for final selection and approval. The first 2 DRB members shall proceed with the selection of the third DRB member immediately upon receiving written notification from the State of their selection, and shall provide their recommendation simultaneously to the parties within 15 days of the notification.

The first 2 DRB members shall select a third DRB member subject to mutual approval of the parties or may mutually concur on a list of potentially acceptable third DRB members and submit the list to the parties for final selection and approval of the third member. The goal in the selection of the third member is to complement the professional experience of the first 2 members and to provide leadership for the DRB's activities.

The third prospective DRB member shall supply a full disclosure statement to the first 2 DRB members and to the parties prior to appointment.

An impasse shall be considered to have been reached if the parties are unable to approve a third member within 15 days of receipt of the recommendation of the first 2 DRB members, or if the first 2 DRB members are unable to agree upon a recommendation within their 15 day time limit. In the event of an impasse in selection of third DRB member the State and the Contractor shall each propose 3 candidates for the third DRB member position. The parties shall select the candidates proposed under this paragraph from the current list of arbitrators certified by the Public Works Contract Arbitration Committee created by Article 7.2 (commencing with Section 10245) of the State Contract Act. The first 2 DRB members shall then select one of the 6 proposed candidates in a blind draw.

No DRB member shall have prior direct involvement in this contract. No member shall have a financial interest in this contract or the parties thereto, within a period of 6 months prior to award of this contract or during the contract, except as follows:

A. Compensation for services on this DRB.

B. Ownership interest in a party or parties, documented by the prospective DRB member, that has been reviewed and determined in writing by the State to be sufficiently insignificant to render the prospective member acceptable to the State.
C. Service as a member of other Dispute Review Boards on other contracts.
D. Retirement payments or pensions received from a party that are not tied to, dependent on or affected by the net worth of the party.
E. The above provisions apply to parties having a financial interest in this contract, including but not limited to contractors, subcontractors, suppliers, consultants, and legal and business services.

The Contractor or the State may reject any of the three DRB members who fail to fully comply at all times with all required employment and financial disclosure conditions of DRB membership as described in the Dispute Review Board Agreement and as specified herein. A copy of the Dispute Review Board Agreement is included in this section.

The Contractor, the State, and the 3 members of the DRB shall complete and adhere to the Dispute Review Board Agreement in administration of this DRB within 15 days of the parties' concurrence in the selection of the third member. No DRB meeting shall take place until the Dispute Review Board Agreement has been signed by all parties. The State authorizes the Engineer to execute and administer the terms of the Agreement. The person(s) designated by the Contractor as authorized to execute contract change orders shall be authorized to execute and administer the terms of this agreement, or to delegate the authority in writing. The operation of the DRB shall be in conformance with the terms of the Dispute Review Board Agreement.

COMPENSATION

The State and the Contractor shall bear the costs and expenses of the DRB equally. Each DRB member shall be compensated at an agreed rate of $1,200 per day if time spent per meeting, including on-site time plus one hour of travel time, is greater than 4 hours. Each DRB member shall be compensated at an agreed rate of $700 per day if time spent per meeting, including on-site time plus one hour of travel time, is less than or equal to 4 hours. The agreed rates shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof, that the DRB member is at an authorized DRB meeting. No additional compensation will be made for time spent by DRB members in review and research activities outside the official DRB meetings unless that time, (such as time spent evaluating and preparing recommendations on specific issues presented to the DRB), has been specifically agreed to in advance by the State and Contractor. Time away from the project, which has been specifically agreed to in advance by the parties, will be compensated at an agreed rate of $125 per hour. The agreed amount of $125 per hour shall include all incidentals including expenses for telephone, fax, and computer services. Members serving on more than one DRB involving the Department, regardless of the number of meetings per day, shall not be paid more than the all inclusive rate per day or rate per hour for an individual project. The State will provide, at no cost to the Contractor, administrative services such as conference facilities and secretarial services to the DRB. These special provisions and the Dispute Review Board Agreement state the provisions for compensation and expenses of the DRB. DRB members shall be compensated at the same daily and hourly rate. The Contractor shall make direct payments to each DRB member for their participation in authorized meetings and approved hourly rate charges from invoices submitted by each DRB member. The State will reimburse the Contractor for the State's share of the costs. There will be no markups applied to expenses connected with the DRB, either by the DRB members or by the Contractor when requesting payment of the State's share of DRB expenses. Regardless of the DRB recommendation, neither party shall be entitled to reimbursement of DRB costs from the other party.

REPLACEMENT OF DRB MEMBERS

Service of a DRB member may be terminated at any time with not less than 15 days notice as follows:

A. The State may terminate service of the State appointed member.
B. The Contractor may terminate service of the Contractor appointed member.
C. Upon the written recommendation of the State and Contractor appointed members for the removal of the third member.
D. Upon resignation of a member.
E. The State or Contractor may terminate the service of any member who fails to fully comply with all required employment and financial disclosure conditions of DRB membership

When a member of the DRB is replaced, the replacement member shall be appointed in the same manner as the replaced member was appointed. The appointment of a replacement DRB member will begin promptly upon determination of the need for replacement and shall be completed within 15 days. Changes in either of the DRB members chosen by the two

parties will not require re-selection of the third member, unless both parties agree to such re-selection in writing. The Dispute Review Board Agreement shall be amended to reflect the change of a DRB member.

OPERATION

The following procedure shall be used for dispute resolution:

A. If the Contractor objects to any decision, act or order of the Engineer, the Contractor shall give written notice of potential claim in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and these special provisions, including the provision of applicable cost documentation; or file written protests or notices in conformance with the provisions in the Standard Specifications and these special provisions.
B. The Engineer will respond, in writing, to the Contractor's written supplemental notice of potential claim within 20 days of receipt of the notice.
C. Within 15 days after receipt of the Engineer's written response, the Contractor shall, if the Contractor still objects, file a written reply with the Engineer, stating clearly and in detail the basis of the objection.
D. Following an objection to the Engineer's written response, the Contractor shall refer the dispute to the DRB if the Contractor wishes to further pursue the objection to the Engineer's decision. The Contractor shall make the referral in writing to the DRB, simultaneously copied to the State, within 21 days after receipt of the written response from the Engineer. The written dispute referral shall describe the disputed matter in individual discrete segments so that it will be clear to both parties and the DRB what discrete elements of the dispute have been resolved, and which remain unresolved, and shall include an estimate of the cost of the affected work and impacts, if any, on project completion.
E. By failing to submit the written notice of referral to the DRB, within 21 days after receipt of the Engineer's written response to the supplemental notice of potential claim, the Contractor waives future claims and arbitration on the matter in contention.
F. The Contractor and the State shall each be afforded an opportunity to be present and to be heard by the DRB, and to offer evidence. Either party furnishing written evidence or documentation to the DRB must furnish copies of such information to the other party a minimum of 15 days prior to the date the DRB is scheduled to convene the meeting for the dispute. Either party shall produce such additional evidence as the DRB may deem necessary to reach an understanding and a determination of the dispute. The party furnishing additional evidence shall furnish copies of such additional evidence to the other party at the same time the evidence is provided to the DRB. The DRB shall not consider evidence not furnished in conformance with the terms specified herein.
G. Upon receipt by the DRB of a written referral of a dispute, the DRB shall convene to review and consider the dispute. The dispute meeting shall be held no earlier than 30 days and no later than 60 days after receipt of the written referral unless otherwise agreed to by all parties. The DRB shall determine the time and location of the DRB dispute meeting, with due consideration for the needs and preferences of the parties while recognizing the paramount importance of a timely hearing of the dispute.
H. There shall be no participation of either party's attorneys at DRB dispute meetings.
I. There shall be no participation of persons who are not directly involved in the contract or who do not have direct knowledge of the dispute, including but not limited to consultants, except for expert testimony allowed at the discretion of the DRB and with approval prior to the dispute meeting by both parties.
J. The DRB shall furnish a report, containing findings and recommendations as described in the Dispute Review Board Agreement, in writing to both the State and the Contractor. The DRB may request clarifying information of either party within 10 days after the DRB dispute meeting. Requested information shall be submitted to the DRB within 10 days of the DRB request. The DRB shall complete its report, including minority opinion, if any, and submit it to the parties within 30 days of the DRB dispute meeting, except that time extensions may be granted at the request of the DRB with the written concurrence of both parties. The report shall include the facts and circumstances related to the matters under consideration, pertinent provisions of the contract, applicable laws and regulations, and actual costs and time incurred as shown on the Contractor's cost accounting records. The DRB shall make recommendations on the merit of the dispute and, if appropriate, recommend guidelines for determining compensation.
K. Within 30 days after receiving the DRB's report, both the State and the Contractor shall respond to the DRB in writing signifying that the dispute is either resolved or remains unresolved. Failure to provide the written response within the time specified, or a written rejection of the DRB's recommendation or response to a request for reconsideration presented in the report by either party, shall conclusively indicate that the party(s) failing to respond accepts the DRB recommendation. Immediately after responses have been received from both parties, the DRB shall provide copies of both responses to the parties simultaneously. Either party may request clarification of elements of the DRB's report from the DRB prior to responding to the report. The DRB shall consider any clarification request only if submitted within 10 days of receipt of the DRB's report, and if submitted simultaneously

in writing to both the DRB and the other party. Each party may submit only one request for clarification for any individual DRB report. The DRB shall respond, in writing, to requests for clarification within 10 days of receipt of such requests.

L. The DRB's recommendations, stated in the DRB's reports, are not binding on either party. Either party may seek a reconsideration of a recommendation of the DRB. The DRB shall only grant a reconsideration based upon submission of new evidence and if the request is submitted within the 30-day time limit specified for response to the DRB's written report. Each party may submit only one request for reconsideration regarding an individual DRB recommendation.

M. If the State and the Contractor are able to resolve their dispute with the aid of the DRB's report, the State and Contractor shall promptly accept and implement the recommendations of the DRB. If the parties cannot agree on compensation within 60 days of the acceptance by both parties of the DRB's recommendation, either party may request the DRB to make a recommendation regarding compensation.

N. The State or the Contractor shall not call DRB members who served on the DRB for this contract as witnesses in arbitration proceedings which may arise from this contract, and all documents created by the DRB shall be inadmissible as evidence in subsequent arbitration proceedings, except the DRB's final written reports on each issue brought before it.

O. The State and Contractor shall jointly indemnify and hold harmless the DRB members from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRB.

P. The DRB members shall have no claim against the State or the Contractor, or both, from claimed harm arising out of the parties' evaluations of the DRB's report.

DISPUTES INVOLVING SUBCONTRACTOR POTENTIAL CLAIMS

For purposes of this section, a "subcontractor potential claim" shall include any potential claim by a subcontractor (including also any pass through potential claims by a lower tier subcontractor or supplier) against the Contractor that is actionable by the Contractor against the Department which arises from the work, services, or materials provided or to be provided in connection with the contract. If the Contractor determines to pursue a dispute against the Department that includes a subcontractor potential claim, the dispute shall be processed and resolved in conformance with these special provisions and in conformance with the following:

A. The Contractor shall identify clearly in submissions pursuant to this section, that portion of the dispute that involves a subcontractor potential claim or potential claims.

B. The Contractor shall include, as part of its submission pursuant to Step D above, a certification (False Claims Act Certification) by the subcontractor's or supplier's officer, partner, or authorized representative with authority to bind the subcontractor and with direct knowledge of the facts underlying the subcontractor potential claim. The Contractor shall submit a certification that the subcontractor potential claim is acknowledged and forwarded by the Contractor. The form for these certifications is available from the Engineer.

C. At DRB dispute meetings involving one or more subcontractor potential claims, the Contractor shall require that each subcontractor involved in the dispute have present an authorized representative with actual knowledge of the facts underlying the subcontractor potential claim to assist in presenting the subcontractor potential claim and to answer questions raised by the DRB members or the Department's representatives.

D. Failure by the Contractor to declare a subcontractor potential claim on behalf of its subcontractor (including lower tier subcontractors' and suppliers' pass through potential claims) at the time of submission of the Contractor's potential claims, as provided hereunder, shall constitute a release of the State by the Contractor of such subcontractor potential claim.

E. The Contractor shall include in all subcontracts under this contract that subcontractors and suppliers of any tier (a) agree to submit subcontractor potential claims to the Contractor in a proper form and in sufficient time to allow processing by the Contractor in conformance with the Dispute Review Board resolution specifications; (b) agree to be bound by the terms of the Dispute Review Board provisions to the extent applicable to subcontractor potential claims; (c) agree that, to the extent a subcontractor potential claim is involved, completion of all steps required under these Dispute Review Board special provisions shall be a condition precedent to pursuit by the subcontractor of other remedies permitted by law, including without limitation of a lawsuit against the Contractor; and (d) agree that the existence of a dispute resolution process for disputes involving subcontractor potential claims shall not be deemed to create any claim, right, or cause of action by any subcontractor or supplier against the Department.

Notwithstanding the foregoing, this Dispute Review Board special provision shall not apply to, and the DRB shall not have the authority to consider, subcontractor potential claims between the subcontractor(s) or supplier(s) and the Contractor that are not actionable by the Contractor against the Department.

RETENTION

Failure of the Contractor to nominate and approve DRB members in conformance with the terms and conditions of the Dispute Review Board Agreement and these special provisions shall result in the retention of 25 percent of the estimated value of all work performed during each estimate period in which the Contractor fails to comply with the requirements of this section as determined by the Engineer. DRB retentions will be released for payment on the next monthly estimate for partial payment following the date that the Contractor has nominated and approved DRB members and no interest will be due the Contractor.

DISPUTE REVIEW BOARD AGREEMENT

A copy of the "Dispute Review Board Agreement" to be executed by the Contractor, State and the 3 DRB members after approval of the contract follows:

Form 6202 Rev (09/01/02)

DISPUTE REVIEW BOARD AGREEMENT

_____
(Contract Identification)

Contract No. _____

THIS DISPUTE REVIEW BOARD AGREEMENT, hereinafter called "AGREEMENT", made and entered into this _____ day of _____, _____, between the State of California, acting through the California Department of Transportation and the Director of Transportation, hereinafter called the "STATE," _____ _____ hereinafter called the "CONTRACTOR," and the Dispute Review Board, hereinafter called the "DRB" consisting of the following members:

_____ ,
(Contractor Appointee)

_____ ,
(State Appointee)

and _____
(Third Person)

WITNESSETH, that

WHEREAS, the STATE and the CONTRACTOR, hereinafter called the "parties," are now engaged in the construction on the State Highway project referenced above; and

WHEREAS, the special provisions for the above referenced contract provides for the establishment and operation of the DRB to assist in resolving disputes; and

WHEREAS, the DRB is composed of three members, one selected by the STATE, one selected by the CONTRACTOR, and the third member selected by the other two members and approved by the parties;

NOW THEREFORE, in consideration of the terms, conditions, covenants, and performance contained herein, or attached and incorporated and made a part hereof, the STATE, the CONTRACTOR, and the DRB members hereto agree as follows:

SECTION I DESCRIPTION OF WORK

To assist in the resolution of disputes between the parties, the contract provides for the establishment and the operation of the DRB. The intent of the DRB is to fairly and impartially consider disputes placed before it and provide written recommendations for resolution of these disputes to both parties. The members of this DRB shall perform the services necessary to participate in the DRB's actions as designated in Section II, Scope of Work.

SECTION II SCOPE OF WORK

The scope of work of the DRB includes, but is not limited to, the following:

A. OBJECTIVE

The principal objective of the DRB is to assist in the timely resolution of disputes between the parties arising from performance of this contract. It is not intended for either party to default on their normal responsibility to amicably and fairly settle their differences by indiscriminately assigning them to the DRB. It is intended that the mere existence of the DRB will encourage the parties to resolve disputes without resorting to this review procedure. But when a dispute that is serious enough to warrant the DRB's review does develop, the process for prompt and efficient action will be in place.

B. PROCEDURES

The DRB shall render written reports on disputes between the parties arising from the construction contract. Prior to consideration of a dispute, the DRB shall establish rules and regulations that will govern the conduct of its business and reporting procedures in conformance with the requirements of the contract and the terms of this AGREEMENT. DRB recommendations, resulting from its consideration of a dispute, shall be furnished in writing to both parties. The recommendations shall be based on facts and circumstances involved in the dispute, pertinent contract provisions, applicable laws and regulations. The recommendations shall find one responsible party in a dispute; shared or "jury" determinations shall not be rendered. The DRB shall make recommendations on the merit of the dispute, and if appropriate, recommend guidelines for determining compensation. If the parties cannot agree on compensation within 60 days of the acceptance by both parties of the DRB's recommendation, either party may request the DRB to make a recommendation regarding compensation.

The DRB shall refrain from officially giving advice or consulting services to anyone involved in the contract. The individual members shall act in a completely independent manner and while serving as members of the DRB shall have no consulting business connections with either party or its principals or attorneys or other affiliates (subcontractors, suppliers, etc.) who have a beneficial interest in the contract.

During scheduled meetings of the DRB as well as during dispute meetings, DRB members shall refrain from expressing opinions on the merits of statements on matters under dispute or potential dispute. Opinions of DRB members expressed in private sessions shall be kept strictly confidential. Individual DRB members shall not meet with, or discuss contract issues with individual parties, except as directed by the DRB Chairperson. Such discussions or meetings shall be disclosed to both parties. Other discussions regarding the project between the DRB members and the parties shall be in the presence of all three members and both parties. Individual DRB members shall not undertake independent investigations of any kind pertaining to disputes or potential disputes, except with the knowledge of both parties and as expressly directed by the DRB Chairperson.

C. CONSTRUCTION SITE VISITS, PROGRESS MEETINGS AND FIELD INSPECTIONS

The DRB members shall visit the project site and meet with representatives of the parties to keep abreast of construction activities and to develop familiarity with the work in progress. Scheduled progress meetings shall be held at or near the project site. The DRB shall meet at least once at the start of the project, and at least once every 4 months thereafter. The frequency, exact time, and duration of additional site visits and progress meetings shall be as recommended by the DRB and approved by the parties consistent with the construction activities or matters under consideration and dispute. Each meeting shall consist of a round table discussion and a field inspection of the work being performed on the contract, if necessary. Each meeting shall be attended by representatives of both parties. The agenda shall generally be as follows:

1. Meeting opened by the DRB Chairperson.
2. Remarks by the STATE's representative.
3. A description by the CONTRACTOR's representative of work accomplished since the last meeting; the current schedule status of the work; and a forecast for the coming period.
4. An outline by the CONTRACTOR's representative of potential problems and a description of proposed solutions.
5. An outline by the STATE's representative of the status of the work as the STATE views it.
6. A brief description by the CONTRACTOR's or STATE's representative of potential claims or disputes which have surfaced since the last meeting.
7. A summary by the STATE's representative, the CONTRACTOR's representative, or the DRB of the status of past disputes and potential claims.

The STATE's representative will prepare minutes of all progress meetings and circulate them for revision and approval by all concerned within 10 days of the meeting.

The field inspection shall cover all active segments of the work, the DRB being accompanied by both parties' representatives. The field inspection may be waived upon mutual agreement of the parties.

D. DRB CONSIDERATION AND HANDLING OF DISPUTES

Upon receipt by the DRB of a written referral of a dispute, the DRB shall convene to review and consider the dispute. The dispute meeting shall be held no earlier than 30 days and no later than 60 days after receipt of the written referral, unless otherwise agreed to by all parties. The DRB shall determine the time and location of DRB dispute meetings, with due consideration for the needs and preferences of the parties while recognizing the paramount importance of speedy resolution of issues. No dispute meetings shall take place later than 30 days prior to acceptance of contract.

Normally, dispute meetings shall be conducted at or near the project site. However, any location that would be more convenient and still provide required facilities and access to necessary documentation shall be satisfactory.

Both parties shall be given the opportunity to present their evidence at these dispute meetings. It is expressly understood that the DRB members are to act impartially and independently in the consideration of the contract provisions, applicable laws and regulations, and the facts and conditions surrounding any dispute presented by either party, and that the recommendations concerning any such dispute are advisory and nonbinding on the parties.

The DRB may request that written documentation and arguments from both parties be sent to each DRB member, through the DRB Chairperson, for review before the dispute meeting begins. A party furnishing written documentation to the DRB shall furnish copies of such information to the other party at the same time that such information is supplied to the DRB.

DRB dispute meetings shall be informal. There shall be no testimony under oath or cross-examination. There shall be no reporting of the procedures by a shorthand reporter or by electronic means. Documents and verbal statements shall be received by the DRB in conformance with acceptance standards established by the DRB. These standards need not comply with prescribed legal laws of evidence.

The third DRB member shall act as Chairperson for dispute meetings and all other DRB activities. The parties shall have a representative at all dispute meetings. Failure to attend a duly noticed dispute meeting by either of the parties shall be conclusively considered by the DRB as indication that the non-attending party considers written submittals as their entire and complete argument. The claimant shall discuss the dispute, followed by the other party. Each party shall then be allowed one or more rebuttals until all aspects of the dispute are thoroughly covered. DRB members shall ask questions, seek clarification, and request further data from either of the parties as may be necessary to assist in making a fully informed recommendation. The DRB may request from either party documents or information that would assist the DRB in making its findings and recommendations including, but not limited to, documents used by the CONTRACTOR in preparing the bid for the project. A refusal by a party to provide information requested by the DRB may be considered by the DRB as an indication that the requested material would tend to disprove that party's position. In large or complex cases, additional dispute meetings may be necessary in order to consider all the evidence presented by both parties. All involved parties shall maintain the confidentiality of all documents and information, as provided in this AGREEMENT.

During dispute meetings, no DRB member shall express an opinion concerning the merit of any facet of the case. DRB deliberations shall be conducted in private, with interim individual views kept strictly confidential.

After dispute meetings are concluded, the DRB shall meet in private and reach a conclusion supported by 2 or more members. Private sessions of the DRB may be held at a location other than the job site or by electronic conferencing as deemed appropriate, in order to expedite the process.

The DRB's findings and recommendations, along with discussion of reasons therefor, shall then be submitted as a written report to both parties. Recommendations shall be based on the pertinent contract provisions, applicable laws and regulations, and facts and circumstances related to the dispute. The report shall be thorough in discussing the facts considered, the contract language, law or regulation viewed by the DRB as pertinent to the issues, and the DRB's interpretation and philosophy in arriving at its conclusions and recommendations. The DRB's report shall stand on its own, without attachments or appendices. The DRB Chairperson shall furnish a copy of the written recommendation report to the DRB Coordinator, Division of Construction, MS 44, P.O. Box 942874, Sacramento, CA 94274.

With prior written approval of both parties, the DRB may obtain technical services necessary to adequately review the disputes presented, including audit, geotechnical, schedule analysis and other services. The parties' technical staff may supply those services as appropriate. The cost of technical services, as agreed to by the parties, shall be borne equally by the 2 parties as specified in an approved contract change order. The CONTRACTOR will not be entitled to markups for the payments made for these services.

The DRB shall resist submittal of incremental portions of information by either party, in the interest of making a fully informed decision and recommendation.

The DRB shall make every effort to reach a unanimous decision. If this proves impossible, the dissenting member shall prepare a minority opinion, which shall be included in the DRB's report.

Although both parties should place weight upon the DRB's recommendations, they are not binding. Either party may appeal a recommendation to the DRB for reconsideration. However, reconsideration shall only be allowed when there is new evidence to present, and the DRB shall accept only one appeal from each party pertaining to an individual DRB recommendation. The DRB shall hear appeals in conformance with the terms described in the Section entitled "Dispute Review Board" in the special provisions.

E. DRB MEMBER REPLACEMENT

Should the need arise to appoint a replacement DRB member, the replacement DRB member shall be appointed in the same manner as the original DRB members were appointed. The selection of a replacement DRB member shall begin promptly upon notification of the necessity for a replacement and shall be completed within 15 days. This AGREEMENT shall be amended to indicate change in DRB membership.

SECTION III CONTRACTOR RESPONSIBILITIES

The CONTRACTOR shall furnish to each DRB member one copy of pertinent documents that are or may become necessary for the DRB to perform their function. Pertinent documents are written notices of potential claim, responses to those notices, drawings or sketches, calculations, procedures, schedules, estimates, or other documents which are used in the performance of the work or in justifying or substantiating the CONTRACTOR's position. The CONTRACTOR shall also furnish a copy of such pertinent documents to the STATE, in conformance with the terms outlined in the special provisions.

SECTION IV STATE RESPONSIBILITIES

The STATE will furnish the following services and items:

A. CONTRACT RELATED DOCUMENTS

The STATE will furnish to each DRB member one copy of Notice to Contractors and Special Provisions, Proposal and Contract, Plans, Standard Specifications, and Standard Plans, change orders, written instructions issued by the STATE to the CONTRACTOR, or other documents pertinent to any dispute that has been referred to the DRB and necessary for the DRB to perform its function.

B. COORDINATION AND SERVICES

The STATE, through the Engineer, will, in cooperation with the CONTRACTOR, coordinate the operations of the DRB. The Engineer will arrange or provide conference facilities at or near the project site and provide secretarial and copying services to the DRB without charge to the CONTRACTOR.

SECTION V TIME FOR BEGINNING AND COMPLETION

Once established, the DRB shall be in operation until the day of acceptance of the contract. The DRB members shall not begin work under the terms of this AGREEMENT until authorized in writing by the STATE.

SECTION VI PAYMENT

A. ALL INCLUSIVE RATE PAYMENT

The STATE and the CONTRACTOR shall bear the costs and expenses of the DRB equally. Each DRB member shall be compensated at an agreed rate of $1,200 per day if time spent per meeting, including on-site time plus one hour of travel time, is greater than 4 hours. Each DRB member shall be compensated at an agreed rate of $700 per day if time spent per meeting, including on-site time plus one hour of travel time, is less than or equal to 4 hours. The agreed rates shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof, that the DRB member is at an authorized DRB meeting. No additional compensation will be made for time spent by DRB members in review and research activities outside the official DRB meetings unless that time has been specifically agreed to in advance by the STATE and CONTRACTOR. Time away from the project that has been specifically agreed to in advance by the parties will be compensated at an agreed rate of $125 per hour. The agreed amount of $125 per hour shall include all incidentals including expenses for telephone, fax, and computer services. Members serving on more than one DRB involving the State, regardless of the number of meetings per day, shall not be paid more than the all inclusive rate per day or rate per hour for an individual project. The STATE will provide, at no cost to the CONTRACTOR, administrative services such as conference facilities and secretarial services to the DRB.

B. PAYMENTS

DRB members shall be compensated at the same rate. The CONTRACTOR shall make direct payments to each DRB member for their participation in authorized meetings and approved hourly rate charges from invoices submitted by each DRB member. The STATE will reimburse the CONTRACTOR for its share of the costs of the DRB.

The DRB members may submit invoices to the CONTRACTOR for partial payment for work performed and services rendered for their participation in authorized meetings not more often than once per month during the progress of the work. The invoices shall be in a format approved by the parties and accompanied by a general description of activities performed during that billing period. Payment for hourly fees, at the agreed rate, shall not be paid to a DRB member until the amount and extent of those fees are approved by the STATE and CONTRACTOR.

Invoices shall be accompanied by original supporting documents, which the CONTRACTOR shall include with the extra work billing when submitting for reimbursement of the STATE's share of cost from the STATE. The CONTRACTOR will be reimbursed for one-half of approved costs of the DRB. No markups will be added to the CONTRACTOR's payment.

C. INSPECTION OF COSTS RECORDS

The DRB members and the CONTRACTOR shall keep available for inspection by representatives of the STATE and the United States, for a period of 3 years after final payment, the cost records and accounts pertaining to this AGREEMENT. If any litigation, claim, or audit arising out of, in connection with, or related to this contract is initiated before the expiration of the 3-year period, the cost records and accounts shall be retained until such litigation, claim, or audit involving the records is completed.

SECTION VII ASSIGNMENT OF TASKS OF WORK

The DRB members shall not assign the work of this AGREEMENT.

SECTION VIII TERMINATION OF DRB MEMBERS

DRB members may resign from the DRB by providing not less than 15 days written notice of the resignation to the STATE and CONTRACTOR. DRB members may be terminated by their original appointing power or by either party, for failing to fully comply at all times with all required employment and financial disclosure conditions of DRB membership in conformance with the terms of the contract.

SECTION IX LEGAL RELATIONS

The parties hereto mutually understand and agree that the DRB member in the performance of duties on the DRB, is acting in the capacity of an independent agent and not as an employee of either party.

No party to this AGREEMENT shall bear a greater responsibility for damages or personal injury than is normally provided by Federal or State of California Law.

Notwithstanding the provisions of this contract that require the CONTRACTOR to indemnify and hold harmless the STATE, the parties shall jointly indemnify and hold harmless the DRB members from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRB.

SECTION X CONFIDENTIALITY

The parties hereto mutually understand and agree that all documents and records provided by the parties in reference to issues brought before the DRB, which documents and records are marked "Confidential - for use by the DRB only," shall be kept in confidence and used only for the purpose of resolution of subject disputes, and for assisting in development of DRB findings and recommendations; that such documents and records will not be utilized or revealed to others, except to officials of the parties who are authorized to act on the subject disputes, for any purposes, during the life of the DRB. Upon termination of this AGREEMENT, said confidential documents and records, and all copies thereof, shall be returned to the parties who furnished them to the DRB. However, the parties understand that such documents shall be subsequently discoverable and admissible in court or arbitration proceedings unless a protective order has been obtained by the party seeking further confidentiality.

SECTION XI DISPUTES

Disputes between the parties hereto, including disputes between the DRB members and either party or both parties, arising out of the work or other terms of this AGREEMENT, which cannot be resolved by negotiation and mutual concurrence between the parties, or through the administrative process provided in the contract, shall be resolved by arbitration as provided in Section 9-1.10, "Arbitration," of the Standard Specifications.

SECTION XII VENUE, APPLICABLE LAW, AND PERSONAL JURISDICTION

In the event that any party, including an individual member of the DRB, deems it necessary to institute arbitration proceedings to enforce any right or obligation under this AGREEMENT, the parties hereto agree that such action shall be initiated in the Office of Administrative Hearings of the State of California. The parties hereto agree that all questions shall be resolved by arbitration by application of California law and that the parties to such arbitration shall have the right of appeal from such decisions to the Superior Court in conformance with the laws of the State of California. Venue for the arbitration shall be Sacramento or any other location as agreed to by the parties.

SECTION XIII FEDERAL REVIEW AND REQUIREMENTS

On Federal-Aid contracts, the Federal Highway Administration shall have the right to review the work of the DRB in progress, except for private meetings or deliberations of the DRB.

Other Federal requirements in this agreement shall only apply to Federal-Aid contracts.

SECTION XIV CERTIFICATION OF THE CONTRACTOR, THE DRB MEMBERS, AND THE STATE

IN WITNESS WHEREOF, the parties hereto have executed this AGREEMENT as of the day and year first above written.

DRB MEMBER

By: _____

Title: _____

DRB MEMBER

By: _____

Title : _____

DRB MEMBER

By : _____

Title : _____

CONTRACTOR

By: _____

Title: _____

CALIFORNIA STATE DEPARTMENT OF TRANSPORTATION

By: _____

Title: _____

5-1.13 FORCE ACCOUNT PAYMENT

The second, third and fourth paragraphs of Section 9-1.03A, "Work Performed by Contractor," in the Standard Specifications, shall not apply.

Attention is directed to "Time-Related Overhead" of these special provisions.

To the total of the direct costs for work performed on a force account basis, computed as provided in Sections 9-1.03A(1), "Labor," 9-1.03A(2), "Materials," and 9-1.03A(3), "Equipment Rental," of the Standard Specifications, there will be added the following markups:

Cost	Percent Markup
Labor	28
Materials	10
Equipment Rental	10

The above markups shall be applied to work performed on a force account basis, regardless of whether the work revises the current contract completion date.

The above markups, together with payments made for time-related overhead pursuant to "Time-Related Overhead" of these special provisions, shall constitute full compensation for all overhead costs for work performed on a force account basis. These overhead costs shall be deemed to include all items of expense not specifically designated as cost or equipment rental in conformance with the provisions in Sections 9-1.03A(1), "Labor," 9-1.03A(2), "Materials," and 9-1.03A(3), "Equipment Rental," of the Standard Specifications. The total payment made as provided above and in the first paragraph of Section 9-1.03A, "Work Performed by Contractor," of the Standard Specifications shall be deemed to be the actual cost of the work performed on a force account basis, and shall constitute full compensation therefor.

Full compensation for overhead costs for work performed on a force account basis, and for which no adjustment is made to the lump sum price bid for time-related overhead conforming to the provisions in "Time-Related Overhead" of these special provisions, shall be considered as included in the markups specified above, and no additional compensation will be allowed therefor.

When extra work to be paid for on a force account basis is performed by a subcontractor, approved in conformance with the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, an additional markup of 7 percent will be added to the total cost of that extra work including all markups specified in this section "Force Account Payment". The additional 7 percent markup shall reimburse the Contractor for additional administrative costs, and no other additional payment will be made by reason of performance of the extra work by a subcontractor.

5-1.14 RESPONSIBILITY TO OTHER ENTITIES

The Contractor shall be responsible for any liability imposed by law and for injuries to or death of any person including, but not limited to, workers and the public or damage to property, and shall indemnify and save harmless the Santa Clara Valley Transportation Authority (VTA) , its officers and employees connected with the work, within the limits of the VTA where the work is being performed, all in the same manner and to the same extent conforming to the provisions in Section 7-1.12, "Indemnification and Insurance," of the Standard Specifications, for the protection of the State of California and all officers and employees thereof connected with the work.

5-1.15 COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS

The provisions of this section shall apply only to the following contract items:

ITEM CODE	ITEM
390153	ASPHALT CONCRETE (TYPE A_)
290211	ASPHALT TREATED PERMEABLE BASE

The compensation payable for asphalt concrete and asphalt treated permeable base will be increased or decreased in conformance with the provisions of this section for paving asphalt price fluctuations exceeding 10 percent (Iu/Ib is greater than 1.10 or less than 0.90) which occur during performance of the work.

The adjustment in compensation will be determined in conformance with the following formulae when the item of asphalt concrete or asphalt treated permeable base (or both) is included in a monthly estimate:

A. Total monthly adjustment = AQ
B. For an increase in paving asphalt price index exceeding 10 percent:

$$A = 0.90\ (1.1023)\ (Iu/Ib - 1.10)\ Ib$$

C. For a decrease in paving asphalt price index exceeding 10 percent:

$$A = 0.90\ (1.1023)\ (Iu/Ib - 0.90)\ Ib$$

D. Where:

A = Adjustment in dollars per tonne of paving asphalt used to produce asphalt concrete and asphalt treated permeable base rounded to the nearest $0.01.
Iu = The California Statewide Paving Asphalt Price Index which is in effect on the first business day of the month within the pay period in which the quantity subject to adjustment was included in the estimate.
Ib = The California Statewide Paving Asphalt Price Index for the month in which the bid opening for the project occurred.
Q = Quantity in tonnes of paving asphalt that was used in producing the quantity of asphalt concrete shown under "This Estimate" on the monthly estimate using the amount of asphalt determined by the Engineer plus the quantity in tonnes of paving asphalt that would have been used in producing the quantity of asphalt treated permeable base shown under "This Estimate" on the monthly estimate using the amount of asphalt specified in the specifications.

The adjustment in compensation will also be subject to the following:

A. The compensation adjustments provided herein will be shown separately on payment estimates. The Contractor shall be liable to the State for decreased compensation adjustments and the Department may deduct the amount thereof from any moneys due or that may become due the Contractor.
B. Compensation adjustments made under this section will be taken into account in making adjustments in conformance with the provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.
C. In the event of an overrun of contract time, adjustment in compensation for paving asphalt included in estimates during the overrun period will be determined using the California Statewide Paving Asphalt Price Index in effect on the first business day of the month within the pay period in which the overrun began.

The California Statewide Paving Asphalt Price Index is determined each month on the first business day of the month by the Department using the median of posted prices in effect as posted by Chevron, Mobil, and Unocal for the Buena Vista, Huntington Beach, Kern River, Long Beach, Midway Sunset, and Wilmington fields.

In the event that the companies discontinue posting their prices for a field, the Department will determine an index from the remaining posted prices. The Department reserves the right to include in the index determination the posted prices of additional fields.

5-1.16 AREAS FOR CONTRACTOR'S USE

Attention is directed to the provisions in Section 7-1.19, "Rights in Land and Improvements," of the Standard Specifications and these special provisions.

The highway right of way shall be used only for purposes that are necessary to perform the required work. The Contractor shall not occupy the right of way, or allow others to occupy the right of way, for purposes which are not necessary to perform the required work.

No State-owned parcels adjacent to the right of way are available for the exclusive use of the Contractor within the contract limits. The Contractor shall secure, at the Contractor's own expense, areas required for plant sites, storage of equipment or materials, or for other purposes.

No area is available within the contract limits for the exclusive use of the Contractor. However, temporary storage of equipment and materials on State property may be arranged with the Engineer, subject to the prior demands of State maintenance forces and to other contract requirements. Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk, and the State shall not be held liable for damage to or loss of materials or equipment located within such areas.

5-1.17 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount set forth for the contract items of work hereinafter listed shall be deemed to be the maximum value of the contract item of work which will be recognized for progress payment purposes:

A.	Clearing and Grubbing	$108,000
B.	Develop Water Supply	$108,000
C.	Progress Schedule (Critical Path Method)	$135,000
D.	Bridge Removal (Portion) Location A	$ 42,500
E.	Bridge Removal (Portion) Location B	$ 57,300
F.	Bridge Removal (Portion) Location C	$ 35,000
G.	Bridge Removal (Portion) Location D	$ 37,300
H.	Bridge Removal (Portion) Location E	$ 45,500
I.	Bridge Removal (Portion) Location F	$ 21,800
J.	Bridge Removal (Portion) Location G	$ 16,500
K.	Bridge Removal (Portion) Location H	$ 15,200
L.	Bridge Removal (Portion) Location I	$ 3,200
M.	Bridge Removal (Portion) Location J	$ 2,700
N.	Bridge Removal (Portion) Location K	$ 39,000
O.	Bridge Removal (Portion) Location L	$ 28,200
P.	Prepare Storm Water Pollution Prevention Plan	$ 13,500
Q.	Lead Compliance Plan	$ 4,500
R.	Asbestos Health and Safety Plan	$ 4,500

After acceptance of the contract pursuant to the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, payable for a contract item of work in excess of the maximum value for progress payment purposes hereinabove listed for the item, will be included for payment in the first estimate made after acceptance of the contract.

In determining the partial payments to be made to the Contractor, only the following listed materials will be considered for inclusion in the payment as materials furnished but not incorporated in the work:

A. Welded steel pipe conduit
B. Piling
C. Prestressing Steel in Sealed Containers (sealed packages only)

D. Precast prestressed concrete girders
E. Soundwall (Barrier)(Masonry Block)
F. Joint seals
G. Bar reinforcing steel
H. Metal sign structures
I. Culvert pipe
J. Underdrain pipe
K. Edge drain pipe
L. Plastic Pipe (Approach Slab Drain Outlet)
M. Plastic pipe liners
N. Welded steel pipe casing (Bridge)
O. PVC waterline
P. Vitrified clay pipe
Q. Miscellaneous iron and steel
R. Miscellaneous metal
S. Miscellaneous metal (bridge)
T. Fences and gates
U. Metal beam guard railing and terminal system
V. Crash cushions
W. Pavement markers Luminaires
X. Signal and lighting standards
Signal heads and mounting brackets

5-1.18 SOUND CONTROL REQUIREMENTS

Sound control shall conform to the provisions in Section 7-1.01I, "Sound Control Requirements," of the Standard Specifications and these special provisions.

The noise level from the Contractor's operations, between the hours of 9:00 p.m. and 6:00 a.m., shall not exceed 86 dBa at a distance of 15 m. This requirement shall not relieve the Contractor from responsibility for complying with local ordinances regulating noise level.

The noise level requirement shall apply to the equipment on the job or related to the job, including but not limited to trucks, transit mixers or transient equipment that may or may not be owned by the Contractor. The use of loud sound signals shall be avoided in favor of light warnings except those required by safety laws for the protection of personnel.

Full compensation for conforming to the requirements of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

5-1.19 RELATIONS WITH CALIFORNIA DEPARTMENT OF FISH AND GAME

A portion of this project is located within the jurisdiction of the California Department of Fish and Game. An agreement regarding a stream or lake has been entered into by the Department of Transportation and the Department of Fish and Game. The Contractor shall be fully informed of the requirements of this agreement as well as rules, regulations, and conditions that may govern the Contractor's operations in these areas and shall conduct the work accordingly.

Copies of the agreement may be obtained at the Department of Transportation, Plans and Bid Documents Section, MS 26, 1120 N Street, Room 200, Sacramento, CA 95814, Telephone 916-654-4490, and are available for inspection at the office of the District Director of Transportation at 111 Grand Ave., Oakland, CA, 94612.

It is unlawful for any person to divert, obstruct or change the natural flow of the bed, channel or bank of a stream, river or lake without first notifying the Department of Fish and Game, unless the project or activity is noticed and constructed in conformance with conditions imposed under Fish and Game Code Section 1601.

Attention is directed to Sections 7-1.01, "Laws to be Observed," 7-1.01G, "Water Pollution," and 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

Modifications to the agreement between the Department of Transportation and the Department of Fish and Game which are proposed by the Contractor shall be submitted in writing to the Engineer for transmittal to the Department of Fish and Game for their consideration.

When the Contractor is notified by the Engineer that a modification to the agreement is under consideration, no work shall be performed which is inconsistent with the original agreement or proposed modification until the Departments take action on the proposed modifications. Compensation for delay will be determined in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The provisions of this section shall be made a part of every subcontract executed pursuant to this contract.

Modifications to any agreement between the Department of Transportation and the Department of Fish and Game will be fully binding on the Contractor. The provisions of this section shall be made a part of every subcontract executed pursuant to this contract.

5-1.20 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD

The location of the Willow Street Viaduct is within an area controlled by the Regional Water Quality Control Board. Regional Water Quality Control Board has issued a certification letter covering work to be performed under this contract. The Contractor shall be fully informed of rules, regulations, and conditions that may govern the Contractor's operations in the areas and shall conduct the work accordingly.

Copies of the certification letter may be obtained at the Department of Transportation, Plans and Bid Documents Section, MS 26, 1120 N Street, Room 200, Sacramento, CA 95814, Telephone 916-654-4490, and are available for inspection at the office of the District Director of Transportation at 111 Grand Ave., Oakland, CA, 94612.

Attention is directed to Section 7-1.11, "Preservation of Property," and Section 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The Contractor's attention is directed to the following conditions which are among those established by the Regional Water Quality Control Board in their certification letter for this project:

A No debris, rubbish, creosote-treated wood, soil, silt, sand, cement, concrete, or washings thereof, or other construction related material or wastes, oil or petroleum products or other organic or earthen material shall be allowed to enter into, or be placed where it may be washed by rainfall or runoff into waters of the State. Any of these materials placed within or where they may enter the Guadalupe River by the Contractor shall be removed immediately. When operations are completed, any excess material shall be removed from the work area and any areas adjacent to the work area where such material may be washed into the Guadalupe River. During construction, the Contractor shall not dump any litter or construction debris within the riparian/stream zone. All such debris and waster shall be picked up daily and properly disposed of at an appropriate site

B. Attention is directed to "Water Pollution Control" of these special provisions.

C. Concrete used in the construction of abutments, piers, and outfalls shall be allowed to completely cure (a minimum of 28 days) or treated with CDFG approved sealant before it comes into contact with flowing water.

D. No equipment shall be operated in areas of flowing or standing water; no fueling, cleaning, or maintenance of vehicles or equipment shall take place within any areas where an accidental discharge to the Guadalupe River may occur; construction materials and heavy equipment must be stored outside the ordinary high water mark; all earth moving work and pouring of concrete shall be performed outside the narrowed channel.

Changes in the above listed conditions proposed by the Contractor shall be submitted to the Engineer for transmittal to the Regional Water Quality Control Board for their approval. Changes shall not be implemented until approved in writing by the Regional Water Quality Control Board.

Attention is directed to Section 8-1.06, "Time of Completion," of the Standard Specifications. Days when the Contractor's operations are restricted by the requirements of this section shall not be considered to be nonworking days whether or not the controlling operation is delayed.

5-1.21 RELATIONS WITH U.S. ARMY CORPS OF ENGINEERS

A portion of this project is within area controlled by the U.S. Army Corps of Engineers nationwide permit and special conditions have been issued covering work to be performed under this contract. The Contractor shall be fully informed of rules, regulations, and conditions that may govern the Contractor's operations in the areas and shall conduct the work accordingly.

Copies of the permit and letter may be obtained at the Department of Transportation, Plans and Bid Documents Section, MS 26, 1120 N Street, Room 200, Sacramento, CA 95814, Telephone 916-654-4490, and are available for inspection at the office of the District Director of Transportation at 111 Grand Ave., Oakland, CA, 94612.

Attention is directed to Section 7-1.11, "Preservation of Property," and Section 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The Contractor's attention is directed to the special conditions in the U.S. Army Corps of Engineer’s permit dated April 23, 2004 (File No. 28744S).

Changes in the above listed conditions proposed by the Contractor shall be submitted to the Engineer for transmittal to the U.S Army Corps of Engineers for their approval. Changes shall not be implemented until approved in writing by the U.S Army Corps of Engineers.

Attention is directed to Section 8-1.06, "Time of Completion," of the Standard Specifications. Days when the Contractor's operations are restricted by the requirements of this section shall not be considered to be nonworking days whether or not the controlling operation is delayed.

Full compensation for conforming to the requirements in the nationwide permit and conditions shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.22 RELATIONS WITH SANTA CLARA VALLEY WATER DISTRICT

A portion of this project is within area controlled by the Santa Clara Valley Water District (SCVWD). A permit and special conditions have been issued covering work to be performed under this contract. The Contractor shall be fully informed of rules, regulations, and conditions that may govern the Contractor's operations in the areas and shall conduct the work accordingly.

Copies of the permit and special conditions may be obtained at the Department of Transportation, Plans and Bid Documents Section, MS 26, 1120 N Street, Room 200, Sacramento, CA 95814, Telephone 916-654-4490, and are available for inspection at the office of the District Director of Transportation at 111 Grand Ave., Oakland, CA, 94612.

Attention is directed to Section 7-1.11, "Preservation of Property," and Section 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The above referenced SCVWD permit for this project will not cover the placement of any falsework within the river, a separate permit or amendment to the project permit will be required. Plans for falsework that is required to be placed within or over the Guadalupe River shall be submitted to the Engineer for review, approval and permit issuance by SCVWD. The falsework shall not remain at the river between October 15 and April 15 without written approval from the SCVWD and any other agencies that have jurisdiction over the work.

The Contractor's attention is directed to the conditions in the Santa Clara Valley Water District permit No. 04319 dated April 6, 2004 File No. 29258.

Changes in the above listed conditions proposed by the Contractor shall be submitted to the Engineer for transmittal to the Santa Clara Valley Water District for their approval. Changes shall not be implemented until approved in writing by the Santa Clara Valley Water District.

Attention is directed to Section 8-1.06, "Time of Completion," of the Standard Specifications. Days when the Contractor's operations are restricted by the requirements of this section shall not be considered to be nonworking days whether or not the controlling operation is delayed.

Full compensation for conforming to the requirements in the Santa Clara Valley Water District permit and conditions shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.23 RELATIONS WITH CITY OF SAN JOSE

A portion of this project is within area controlled by the City of San Jose. An encroachment permit, standard conditions and special conditions have been issued covering work to be performed under this contract. The Contractor shall be fully informed of rules, regulations, and conditions that may govern the Contractor's operations in the areas and shall conduct the work accordingly.

Copies of the permit and conditions may be obtained at the Department of Transportation, Plans and Bid Documents Section, MS 26, 1120 N Street, Room 200, Sacramento, CA 95814, Telephone 916-654-4490, and are available for inspection at the office of the District Director of Transportation at 111 Grand Ave., Oakland, CA. 94612.

Attention is directed to Section 7-1.11, "Preservation of Property," and Section 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The Contractor's attention is directed to the conditions in the City of San Jose encroachment permit No. 3-0413RU dated April 5, 2004. Contractor shall obtain a haul route permit from City of San Jose Department of Transportation prior to hauling any material onto City of San Jose right of way. Attention is directed to a blank haul route permit specified in the "Materials Information" handout available to the contractors.

Changes in the above listed conditions proposed by the Contractor shall be submitted to the Engineer for transmittal to the City of San Jose for their approval. Changes shall not be implemented until approved in writing by the City of San Jose.

Full compensation for conforming to the requirements in the City of San Jose permit shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.24 RELATIONS WITH SANTA CLARA COUNTY ROADS AND AIRPORTS DEPARTMENT

A portion of this project is within area controlled by the Santa Clara County Roads and Airports Department. An encroachment permit, general provisions and special provisions have been issued covering work to be performed under this contract. The Contractor shall be fully informed of rules, regulations, and conditions that may govern the Contractor's operations in the areas and shall conduct the work accordingly.

Copies of the permit may be obtained at the Department of Transportation, Plans and Bid Documents Section, MS 26, 1120 N Street, Room 200, Sacramento, CA 95814, Telephone 916-654-4490, and are available for inspection at the office of the District Director of Transportation at 111 Grand Ave., Oakland, CA. 94612.

Attention is directed to Section 7-1.11, "Preservation of Property," and Section 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The Contractor's attention is directed to the general provision and special provisions in the Santa Clara County Roads and Airports Department permit No. 24040217 dated April 28, 2004.

Changes in the above listed conditions proposed by the Contractor shall be submitted to the Engineer for transmittal to the Santa Clara County Roads and Airports Department for their approval. Changes shall not be implemented until approved in writing by the Santa Clara County Roads and Airports Department.

Full compensation for conforming to the requirements in the Santa Clara County Roads and Airports Department permit shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5–1.25 RELATIONS WITH SANTA CLARA VALLEY TRANSPORTATION AUTHORITY

A portion of this project is within area controlled by the Santa Clara Valley Transportation Authority (VTA). A Construction Access Permit and special provisions and general conditions have been issued covering work to be performed under this contract. The Contractor shall be fully informed of rules, regulations, and conditions that may govern the Contractor's operations in the areas and shall conduct the work accordingly.

Copies of the construction access permit, special provisions, general conditions may be obtained at the Department of Transportation, Plans and Bid Documents Section, MS 26, 1120 N Street, Room 200, Sacramento, CA 95814, Telephone 916-654-4490, and are available for inspection at the office of the District Director of Transportation at 111 Grand Ave., Oakland, CA. 94612.

Attention is directed to Section 7–1.11, "Preservation of Property," and Section 7–1.12, "Indemnification and Insurance," of the Standard Specifications.

The Contractor's attention is directed to the special provisions and general conditions in the VTA Construction Access Permit No. 04040004 dated May 3, 2004.

Changes in the above listed conditions proposed by the Contractor shall be submitted to the Engineer for transmittal to the VTA for their approval. Changes shall not be implemented until approved in writing by the VTA.

Attention is directed to Section 8–1.06, "Time of Completion," of the Standard Specifications. Days when the Contractor's operations are restricted by the requirements of this section shall not be considered to be nonworking days whether or not the controlling operation is delayed.

Attention is directed to requirements for shoring in “Earthwork” of these special provisions.

SANTA CLARA VALLEY TRANSPORTATION AUTHORITY
ENCROACHMENT PROCEDURES WITHIN LIGHT RAIL RIGHT OF WAY

Contractor shall obtain Light Rail Restricted Access Permits as required and there will be no cost to the Contractor.

The following conditions of the Permit are set forth to provide a method of protection of the integrity of the Santa Clara Valley Transportation Authority Light Rail Transit facilities and services.

PERMIT REQUIREMENTS

No person(s) or Agency shall obstruct or encroach upon the Light Rail right of way without first obtaining written authorization from the VTA Operations Control Center (OCC) in the form of a Light Rail Restricted Access Permit with Light Rail requirements set forth herein.

I. The following items are required for a Light Rail Restricted Access Permit:

a. Detailed description of work within VTA property includes:
   Type of project
   Duration of project
   Contractor schedule
   If known, the impact on VTA Operations

b. Liability insurance certificate must be received from the Contractor prior to issuance of Restricted Access Permits to the prime contractor. The certificate must include:

Insurance requirement	Project under $50,000	Project over $50,000
General liability	$1,000,000	$5,000,000
Automobile liability	$1,000,000	$5,000,000
Worker's compensation	$1,000,000	$1,000,000
Employer liability insurance	$1,000,000	$1,000,000
*Railroad liability insurance	$1,000,000	$5,000,000

*(When applicable see item II c below)
VTA Shall be Shown as Additional Insured
Best's rating of no less than B+, VIII

II. The following items are required when applicable:

a. Work within 3 meters of the Light Rail Tracks/System, or over/under any catenary system, requires an approved copy of the Light Rail Restricted Access Permit and completion of OCC Safety Training Class. Call 408-546-7608 prior to issuance of permit.
b. Traffic Control Plan
c. Work within 15 meters of the light rail tracks/light rail system or/over under any catenary system requires Railroad Protective Liability Insurance.
d. As stated in Government Code 4216.9 (a), "No permit to excavate shall be valid unless the application has been provided with an initial inquiry identification number." Permittee or their General Contractor shall notify VTA's Permit and Utility Services Unit of the USA Ticket Number prior to start of work.
e. The Contractor shall videotape the work site prior to start of work and at the completion of work. The entire VTA right-of-way shall be videotaped with the Engineer present, and as directed by the Engineer. Two copies of the videotape shall be given to the Engineer after the completion of the videotaping.
f. The Contractor shall pothole by means of vacuum extraction to determine the exact depth of the combined System Duck bank and/or any utility within the work area prior to the start of any bore or excavation under the Light Rail R/W or within VTA property.
g. The Contractor shall attend weekly Track Allocation meetings or other meetings as required.

AUTHORITY

ADMINISTRATIVE AUTHORITY

All main track operations will be under the supervision of the VTA Guadalupe Division Superintendent of Transportation. The Superintendent of Transportation shall be the final authority for all operations.

OCC AUTHORITY

Under general direction of the VTA Assistant Superintendent of Transit Communications, the Controller on duty at the Operations Control Center shall have sole authority over movement of all rail equipment and vehicles outside the yard limits of the Light Rail Division Facility, during an emergency situation.

The on-duty OCC Controller shall assume full authority over access to the following restricted systems:

1. Electrical Sub-Stations
2. Signal Facilities
3. Main Track
4. Overhead Electrification System

The Contractor shall call OCC and the Engineer at the start and end of the workday.

The Guadalupe Division Superintendent of Transportation or designated representative, may move, remove, cover, tow away, or clean up any encroachment in the Light Rail right of way placed without access authorization, at the expense of the Contractor. Any damage done to Light Rail Facilities resulting in delay of service must be repaired by Light Rail Operations at the direct cost of the Contractor.

DEFINITIONS

Light Rail Facilities - Any appurtenances owned by Santa Clara Valley Transportation Authority relative to the operation of the Light Rail system (i.e., track, overhead wires, stations, park and ride lots, trains, bus stops, etc.)

Flagger - A person whose sole duty, while there is encroachment, is to watch for approaching rail mounted vehicles, provide warning to all persons working on or near the track, provide hand signals to trains, and all ancillary duties necessary to avoid trains coming into contact with workers, equipment, or materials within the work zone.

LRV - Light Rail Vehicle

LRT - Light Rail Transit

OCC - Operations Control Center at 101 West Younger Avenue, San Jose, CA. 95110-1719, telephone (408) 546-7688.

OCS - Overhead Catenary System

POWER DOWN - Overhead power supply being de-energized completely.

RESTRICTED AREA - Area to which only authorized personnel are allowed. Unauthorized personnel are required to have an access permit. Any point within 10 feet of the nearest rail of any track.

RIGHT OF WAY - The Right to pass over property owned by another; strip of land over which facilities (highway, utility, railroad or power lines) are built.

Santa Clara Valley Transportation Authority (VTA) at 3331 North First Street, San Jose, CA 95134-1927.

Traction Electrification System (TES) includes overhead catenary wires, poles, feeder cables and substations supplying power to Light Rail System.

SERVICE SCHEDULE

Light Rail Service schedule is subject to change. The current schedule can be obtained from OCC at 408-546-7688.

GENERAL

Portions of this project are located within the jurisdiction of the VTA LRT. Construction permits regarding work at or adjacent to LRT right of way will be required between the VTA and the Contractor. The Contractor shall fully inform himself of the requirements of the VTA construction permits, and all associated rules, regulations, and conditions that may govern Contractor operations in LRT right of way, and the Contractor shall conduct his operations accordingly. All work that affects LRT facilities shall be in accordance with these special provisions.

Attention is directed to the provisions in "Section 4 – Beginning of Work, Time of Completion and Liquidated Damages," "Order of Work," "Cooperation," "Obstructions," and "Preservation of Property" of these special provisions.

The Contractor shall ensure that LRT train operations are not interrupted and that the LRT tracks, its patrons, LRT employees, the Contractor and other personnel are protected from injury or damage in accordance with these special provisions.

The Contractor shall submit a Site Specific Work Plan (SSWP) for all construction activities within or above the LRT operating envelope or any construction activity having potential impact on LRT train operations, and not limited to the following locations:

Drainage pipe installations between Almaden Road to Alma Avenue (Northbound and Southbound)

Drainage pipe installations just northerly of Tamien Station. (Northbound and Southbound)

The following full weekend single tracking operations will be allowed at no cost to the Contractor. Single tracking consists of shutting down either the northbound or the southbound track and running two-way rail traffic on the remaining track. The power will also be de-energized or draped along the shutdown track. Draping consists of insulating the contact and messenger wires and the hangers.

Nine (9) Single Tracking Full Weekend Operations

Nine (9) single tracking full weekend operations shall occur at one of the following four locations:

1. Northbound Track at Capitol Expressway shutdown with draped power down.
2. Southbound Track at Capitol Expressway shutdown with draped power down.
3. Northbound Track from Curtner Avenue to Alma Avenue shutdown with de-energized power down..
4. Southbound Track from Alma Avenue to Curtner Avenue shutdown with de-energized power down.

The Contractor shall select the location and only one location shall be used per weekend. The single tracking locations or shutdown limits are approximate and the precise limits will be determined at the Track Allocation Meetings.

In addition, the following weekend night (Friday, Saturday, or Sunday) or weeknight (Monday, Tuesday, Wednesday or Thursday) single tracking operations will be allowed at no cost to the Contractor.

Ten (10) Single Tracking Weekend Night Or Weeknight Operations.

The single track shutdown limits for weekend night or weeknight operations shall be as stated in 1 through 4 above or the limits shall be negotiated through the Track Allocation Meeting process.

Full weekend, weekend night or weeknight single track operation schedules shall not overlap or coincide unless approved at the Track Allocation Meeting.

Any work which will involve access into LRT restricted areas (full weekend, weekend night or weeknight single tracking) shall be restricted to the hours in the following table.

Flaggers may be used on the active track of a single tracking operation to permit VTA-approved work in restricted areas. The Contractor may be required to interrupt his work to allow train passage on the active track.

LRT Single Tracking Schedule

Location: Light Rail System Within Project Limits

FROM HOUR TO HOUR	A.M.													P.M.												
	2										0	1	2											0	1	2
Mondays through		▨	▨	▨	▨																			▨	▨	
Fridays		▨	▨	▨	▨																			▨	▨	
Saturdays		▨	▨	▨	▨	▨																	▨	▨	▨	
Sundays		▨	▨	▨	▨	▨																	▨	▨	▨	
Full Weekend	Single Tracking will be allowed between hours of 10 P.M. Friday through 4:00 A.M. Monday																									
Designated Legal																										

Legend:

▨ LRT Single Tracking allowed

☐ No work that interferes with the LRT service

REMARKS:

Lockout and Tag procedures shall be performed before and after the Single Tracking periods given in this table with participation by the Contractor. The estimated time for Lockout and Tag procedures is one hour before and after the Single Tracking period.

The number and timing of LRT single tracking operations during these hours must be approved by the VTA as described in this "General" section of the special provisions.

LRT restricted area Clearance Diagram is shown in the plans.

SAFETY AND HEALTH PROVISIONS

Attention is directed to the provisions in Section 5-1.02A, "Trench Excavation Safety Plans" of the Standard Specifications and "Earthwork" of these special provisions.

No combustible material shall be permitted to be stored alongside LRT right of way or within the fenced construction site provided in "Preservation of Property" elsewhere in these special provisions.

Before any construction begins in the vicinity of LRT right of way, the Contractor shall submit a fire analysis report identifying all possible fire sources and mitigating measures to the Engineer for approval. The Contractor shall allow 10 days after the complete report and all supporting data are submitted, for review and approval.

SITE SPECIFIC WORK PLAN (SSWP)

SSWP is defined as a program, plan, and schedule prepared and submitted by the Contractor and approved by the Engineer, which accurately describes and illustrates the manner in which work within restricted areas will be accomplished.

The Contractor shall furnish all labor, materials, and equipment as required to perform and complete the work in the limited time available. The Contractor shall maintain the approved schedule in the SSWP.

The Contractor shall allow 20 working days after the complete SSWP and all supporting data are submitted for review and approval. No work in the vicinity of the LRT right of way shall commence until the plan is approved.

Once the Plan is approved, the Contractor shall assemble the resources necessary to perform the Work represented by the SSWP, so that the necessary resources are available and ready to use when single tracking is required. At that time, the Engineer will make a final decision as to whether or not the Work is to proceed as planned or will be canceled. The prime consideration will be the stage of readiness of the Contractor, which the Contractor shall demonstrate to the Engineer. However, VTA LRT operation and maintenance plans may also affect the decision.

Work week for working in VTA LRT right of way is defined as the week starting with Friday and the next six days of the proposed work schedule.

All Site Specific Work Plans (SSWP) which may impact the normal operation of any part of the VTA LRT operating system (including park and ride lots) shall contain a schedule of activity. The schedule shall include a time at which all

activities planned under the SSWP will be completed. Failure of the Contractor to complete the scheduled activities by the planned time or to put in place an approved contingency plan so that the system is available for operations at the approved completion time shall make the Contractor liable for liquidated damages as follows:

$5,000 per weeknight and per weekend night and $25,000 per full weekend for additional single tracking periods exceeding the number permitted.

$5,000 per cancelled single tracking period each week night, weekend night or full weekend closure cancellation with less than 48 hours advance written notice.

For each 10-minute interval, or fraction thereof, past the time specified to reopen the LRT services, the Department will deduct $3000 per interval for moneys due or that may become due from the Contractor under the contract.

These liquidated damages are distinct and separate from liquidated damages which are specified in "Beginning of Work, Time of Completion and Liquidated Damages," of these special provisions.

A full weekend single tracking is considered to have been utilized by the Contractor if the single tracking exceeds the time frame allowed for a weekend night service interruption.

VTA LRT OPERATING RULES AND PROCEDURES

All Contractor activities within the VTA's restricted areas shall comply with the VTA Restricted Access Permit. Contractor shall be strictly confined to the time and location restrictions of their Access Permit. When performing work on or about the right of way, Contractor shall adhere to all rules and procedures contained within the VTA Restricted Access Procedures Manual. Work sites will be monitored; any deviation from or violation of these rules shall be cause for the immediate eviction of the Contractor from the work site at the expense of the Contractor. This permit may be revoked at any time by VTA for violation of rules and requirements or as deemed necessary for the safety of personnel and equipment

Except as otherwise permitted in VTA's Restricted Access Permit, the Contractor shall not enter the VTA operating right of way unless accompanied by VTA personnel. High visibility vests shall be worn at all times. Approved hard hats must be worn by all personnel working within 1.22m of the track.

RESTRICTED ACCESS PERMIT

A valid Restricted Access Permit shall be on worksite and produced upon request. Access permits are obtained from VTA Permits Department. All access permits must be applied for 10 working days in advance of the requested time of entry. VTA Permits must be notified 48 hours in advance to work commencing.

Any access to enter or cross the trackway and all work performed within 3 meters of the tracks shall require a permit. Permits are available through the Light Rail Restricted Access Permit Office. A double-sided copy of this permit must be available on the work site and must be provided to all workers prior to the start of work. Permits must be shown upon request. Failure to produce a valid Access Permit upon request may result in the Contractor being removed from the property.

Access Permits are obtained at the Light Rail Facility, 101 West Younger Avenue. San Jose, CA, 95110-1719. Permits may be granted with less than 7 days notice in cases of emergency. Extensions of an Access Permit may be approved by telephone. If there are changes to the working conditions and/or if there is a request for power removal, a new Restricted Area Access Permit will be required.

A minimum of 30 days notice (immediate notice for emergency work) shall be given to OCC prior to commencing work in restricted areas.

LRT FLAGGERS

All work performed within 3.0 meters of the track (0.76 meters from a station platform edge) and when equipment greater than 3.0 meters tall or have devices which can extend beyond 3.0 meters, such as cranes and boom trucks, shall require a designated worker (Flagger) to watch for approaching trains. This Flagger shall notify workers to move to a distance of 3.0 meters from the tracks upon approach of a train. Once workers have moved, the Flagger shall give the train a Proceed hand signal. If workers are within the 3.0 meters area, a stop hand signal shall be given to the train. The spotter is required to give the appropriate hand signal to each approaching train. Any construction equipment and/or materials must maintain the same 3.0 meters clearance from the track.

Flagger(s) shall notify worker(s) of approaching rail-mounted vehicles ("trains") in sufficient time so that all personnel, equipment, and unsecured material are moved outside the trackway a minimum of 30 seconds prior to train entering the work limits.

If the Flagger must stop multiple trains prior to entering the work limits during a shift, the Flagger shall provide workers with earlier notification so that the track way is clear a minimum of 30 seconds prior to the train entering the work limits.

If rail mounted vehicles must slow or stop because the track way is not clear 30 seconds before the train enters the work limits, the LRT Flagger shall increase the time for notifying worker(s) of an approaching train by not less than one minute.

Multiple work groups may be under the control of one Flagger provided that the Flagger can view approaching trains and all workers under the Flagger's control and provide notification to workers of the approaching rail mounted vehicles.

Contractor shall provide personnel for all flagging requirements. Flaggers shall be trained by the VTA Restricted Access Office; contact Assistant Superintendent Transit Communications at 408-546-7608 for available training schedules. Flaggers shall be provided with cell phones for communication with LRT operators (trains). Equipment needed by the Flaggers shall be furnished and maintained clean and in good repair by the Contractor at the Contractor's expense. Flaggers shall be scheduled by the Contractor for operations requiring their deployment. The schedule shall be submitted to the Engineer for review and approval 10 calendar days prior to their scheduled deployment. Flaggers should only stop trains in emergencies under normal two track one way operation.

CLEARANCE FROM ENERGIZED LINES

The overhead catenary system is energized with 750 Volts DC at all times. In accordance with Cal-OSHA Title 8, all work (including metal ladders, metal handle extensions, or equipment) shall remain 3.0 meters from the overhead catenary system unless a **Lockout and Tag procedure** has been approved and completed and a ground strap is visible to the workers.

SAFETY TRAINING

Prior to commencement of work, all Contractor's employees, subcontractor's and any third tier services personnel must attend a safety orientation at the Light Rail Division or at the work site (as designated by the Restricted Access Permit Office) on how to work around Light Rail. After successful attendance of the safety orientation, a safety sticker will be issued which must be applied to the hard hat. Safety orientations can be scheduled through the Light Rail Restricted Access Permit Office. Safety seminar records and reports shall be submitted at least monthly by the Contractor. Re-certification of Contractor's employees will be required on an annual basis.

EMERGENCY CONTACT

Prior to commencing work, OCC and the Engineer shall be given the names of two persons responsible for the work who can be reached 24 hours per day, 7 days per week, in the event of an emergency.

CONTRACTOR ACCESS

Contractor desiring access to any restricted access area under OCC authority must complete the "Light Rail Restricted Area Access" Safety Seminar and must obtain written permission at least 48 hours prior to entry time. An approved "Restricted Area Access Permit" must be obtained from a qualified Transportation Supervisor for access to the following restricted access areas.

1. Electrical Sub-Station
2. Signal Facilities
3. Main Track, or operation of equipment across the right of way
4. Overhead Electrification System

SINGLE TRACKING OPERATIONS

VTA will not allow any single track operations on the Light Rail system, except for those specified in the LRT Single Tracking Schedule of this special provision.

The Contractor shall provide sufficient resources to ensure single tracking operations are kept to a minimum. Attention is directed to the liquidated damages provisions specified in Site Specific Work Plans of this special provision.

The Contractor shall submit to OCC the dates on which all single tracking operations are proposed a minimum of 30 days in advance, for approval by the VTA. Cancellation of any LRT single tracking operation later than 10 calendar days prior to scheduled activity will result in deducting one weeknight or weekend night single tracking operation from the total allowance, except cancellations due to weather or circumstances beyond the control of the Contractor, as determined by the Engineer.

Cancellations with less than the 48-hour written notice shall result in liquidated damage charges. The Contractor shall bear any costs and expenses resulting from cancellations with less than the 48 hour written notice except cancellations due to weather or circumstances beyond the control of the Contractor, as determined by the Engineer.

Single tracking operations that conflict with the following holidays, celebrations and other major local events will not be approved. The Contractor shall request a list of these special dates from the VTA.

4th of July
Labor Day weekend (Saturday, Sunday and Monday)
Moffett Air Show weekend

Cinco de Mayo weekend

If, due to the Contractor's operations, the LRT single tracking operation can not be terminated by the specified time, work shall be suspended in conformance with the provisions in Section 8-1.05 "Temporary Suspension of the Work" of the Standard Specifications. The Contractor shall not make any further single tracking requests until the Engineer has accepted a work plan, submitted by the Contractor that will ensure future normal one way operations will be reopened at the specified time. The Engineer will have 2 working days to accept or reject the Contractor's proposed work plan. The Contractor will not be entitled to any compensation for the suspension of work resulting from the late reopening of normal one way LRT operation. Liquidated damages assessed for late opening are defined in the Site Specific Work Plan (SSWP).

TRACK ALLOCATION MEETINGS

Light Rail Operations department will conduct weekly Access Meetings as required for Contractor and the Light Rail Operations department to discuss Light Rail operations and future Contractor activities, and to resolve any conflicts in these activities with the Light Rail right of way. The access meetings shall be held at the Guadalupe Light Rail Facility, 101 West Younger Avenue, San Jose CA. 95110-1719.

During meetings, blank Restricted Area Access Request forms shall be issued to those individuals requesting access for future activities. Upon completion of the access meeting, the Restricted Access Permit staff shall inspect the Restricted Access Request form(s) for completeness, paying special attention to the location, time, power status, protection needed and the priority for access. If the requester doesn't know the protection needed, it is the responsibility of the Restricted Access staff to inform the requester of the different levels of protection available to provide safe working conditions along the right of way.

If any conflicts for access arise during major construction projects along the right of way involving future Light Rail expansions, the Restricted Access Permit and Rail Activation staff shall resolve the conflicts.

If unforeseen circumstances arise where access is needed at short notice, the Contractor will contact the Engineer and OCC at 408-546-7688.

RIGHT OF WAY

Work area within LRT right of way must be kept clean during all phases of construction – especially high public use areas (stations, station access). Non-compliance to this request will result in LRT personnel cleaning area at direct cost to the Contractor.

TRACKS

Track, including grooves of girder rails, shall be kept broom clean at all times. Any damage to the tracks must be reported to the Engineer and OCC immediately at 408-546-7688.

DRAINAGE PIPES AND CONDUITS

All jacking of pipes or direct boring of conduits within Light Rail right of way shall be performed during the shaded nighttime/early morning hours shown in the LRT Single Tracking Schedule. LRT Flagger(s) shall be available when boring/jacking pipe/conduit greater than 75mm in diameter. Schedules for jacking of pipes and direct boring of conduits shall be presented and approved at Track Allocation Meetings and any VTA conditions shall be complied with by the Contractor. Pipe jacking and direct boring of conduit greater than 75 mm placed beneath the LRT right-of-way shall be placed when there are no rail operation. Single tracking operations do not apply to pipe jacking and direct boring of conduit construction.

A survey of Light Rail tracks will be performed by VTA immediately before and after jacking or boring operations at locations of this work. Survey of tracks shall be performed for all tracks at intervals of 10 meters for a distance of 30 meters in each direction of boring/jacking work. The Contractor shall be responsible for payment of any repairs necessary to the tracks due to boring/jacking operations.

Any jacking operations which cross the Light Rail tracks shall be performed from the combined system duct side of track. Contractor shall pothole the top and bottom of the combined system duct bank prior to boring or jacking operations. Contractor shall backfill potholing per VTA requirements.

All drainage pipes within the light rail right of way shall have a #8 AWG trace wire mounted onto the outside top of pipe. Trace wire shall be mounted onto centerline of top of pipe without damage to the pipe.

Contractor shall notify the Engineer and VTA Permits (408)321-5856 48 hours in advance of pipe jacking and conduit direct boring.

Boring methods are subject to the following conditions:

1. Wet bores are not allowed (wet bores refer to the use of liquids to displace soil)

2. The machine operator has control over the direction of the boring tool
3. Pull back methods use mandrels up to 50.8 millimeters larger than the diameter of the casing.
4. Shallow bores, misdirected bores, or other unsuccessful bore are abandoned and filled at the discretion of the Engineer.
5. If a bore is unsuccessful, future attempts are made only with the approval of the Engineer.
6. Auger heads are not allowed more than 152 millimeters ahead of the casing being inserted.
7. Bore stems and cutting heads may have to be left in the ground if they cannot be retrieved through the bore hole. Open excavation to retrieve parts is not allowed.

TRACTION ELECTRIFICATION SYSTEM

The overhead electrical system in the yard and on the main track is energized for vehicle operation. Access to and operation of any equipment shall be under the control of the OCC Controller. The overhead electrical system shall be considered hot (energized) at all times. Shutdown of the overhead electrical system shall be in accordance with the Traction Power Lockout and Tag Procedures.

SIGNALS

Hand signals used by flaggers to trains shall consist of: STOP and STAY (hand or light swung at right angle to the track); PROCEED (hand or light raised and lowered vertically parallel to the track facing the operator. Horn signals used by trains to workers shall consist of: REQUEST FOR HAND SIGNAL (Four Horns); HAND SIGNAL UNDERSTOOD (Two Horns).

Training procedures for flaggers are provided by VTA OCC as a condition of the VTA Restricted Access Permit.

TRACTION POWER "LOCKOUT AND TAG" PROCEDURE

These Lockout and Tag procedures are used to allow safe access to high voltage equipment only. These Tags are for personnel protection while work is in progress on or near high voltage circuits. The Tag consists of two sections: a 'Tag" and a "Stub". Both sections have the same number and can be separated at the perforated line. The Lockout and Tag procedure shall be used on all electrical circuits as deemed necessary by the Power Supervisor or designee.

REMOVAL OF POWER

The VTA shall Lock and Tag all sources of high voltage electrical power that are being de-energized to enable Contractors and/or personnel to work within the restricted area safely. In addition, each Contractor shall have their own Lock(s) and Tag(s) to attach to the breakers and/or switches.

LOCKOUT AND TAG PROCEDURE

Requires Locks and Tags on all open or racked out breakers, voltage test(s), grounds (if needed), and a combination of flags, cones and/or signs to physically protect the area. Procedure completed by Contractor and VTA.

This condition shall be used whenever Contractors or other outside agencies will be working on or within 3m of the overhead line or underground feeder system.

Upon completion of the test, the VTA will confirm that the Lock stubs have been issued to the requestors.

RESTORATION OF POWER

LOCKOUT AND TAG PROCEDURE

After all Contractors are finished working within 3m of the overhead, the VTA will perform power restoration.

The VTA employee will notify OCC that all flags, cones and/or signs have been removed and the line is ready for train operation.

CONTRACTOR REPRESENTATIVE

1. Once the Lock(s) and Tag(s) are in place, the individual placing the Locks(s) and Tag(s) is expected to remain accessible and shall return at the agreed upon time and place. If the Contractor and crew need to leave the work area, they shall call the Engineer and OCC before leaving. For safety, the Contractor shall never leave one member of the work crew alone at the work site.
2. Should the need arise to transfer this authority to another individual, the Engineer and OCC shall be contacted immediately.
3. The VTA will meet with the person(s) who are surrendering authority and person(s) assuming the responsibility for the Lock(s) to ensure that the person assuming responsibility, are qualified. OCC shall log the time of transfer of authority and the name(s) of the person(s) assuming responsibility.

LOCKS AND TAGS UNACCOUNTED FOR

In the event that one ore more Locks and/or Tags are unaccounted for, the VTA power employee shall contact OCC, advising that the Contractor is no longer in the area and the Tags and Locks are still on the breakers. OCC will call and page the Contractor. If there is no response within 5 minutes, OCC shall contact the Power Supervisor or Superintendent of Way, Power & Signal Department (WP&S).

If OCC is not able to contact either person, OCC and the power employee shall confirm that all personnel are clear and the equipment and/or system is safe to operate. The power employee shall remove the Lock(s) and Tag(s) from the breaker(s) and/or switch(s). OCC and the Power employee will then continue the power restoration protocol.

The permit will be canceled with an effective time, date, and OCCs radio number, written on the permit with a brief explanation.

RESTRICTIONS WHILE OCS IS ENERGIZED

No work requiring a crane within restricted areas shall be done with the overhead system energized. Power may only be taken down during the hours specified in this section.

No loads shall be moved over the overhead contact wire while the OCS system is energized, unless suitable protection is provided to protect the wires from construction above.

No personnel shall be permitted within 3.0 meter of the OCS wires unless power has been shut down.

No metal objects, metal handle extensions, poles, ladders, etc. shall be allowed closer than 3.0 meter to the OCS wire unless power has been shut down and the overhead grounded.

Power Shutdowns - Power removal, when necessary, shall be done by the Contractor with a Lockout and Tag procedure under the direction of the power department and rail controller.

OCC will coordinate a request to shutdown power. Specific items of work which will require the OCS to be de-energized include, but are not limited to:

Drainage pipe/inlets installation and concrete ditch installation between Almaden Road and Alma Avenue.

Drainage pipe/inlets installation at north end of Tamien Station.

All of the above items of work shall be done during the hours described in this section under “LRT Single Tracking Schedule.”

WARNING FLAGS

Flags shall be posted in accordance with the existing Restricted Access Procedures Manual prior to the start of all work performed within 3m of the tracks. Any flags left on a work site for longer than 30 minutes without the obvious presence of workers (without notification to OCC) shall become the property of VTA. Cost and procurement of flags shall be the responsibility of the Contractor. Flags may be purchased at local safety suppliers.

When performing work on or about the trackway during train operations, Contractors will adhere to the following:

REDUCED SPEED ZONE, (HIGH SPEED AUTOMATIC BLOCK SIGNAL SYSTEM (ABS) AREAS)

Track which is not in condition for normal speed, or areas where work may affect the safety of personnel or trains, shall be protected. Protection shall be provided by means of the following signs:

Stop Ahead: 240 meters (800 feet) ahead of protected work area and to the right of the affected track, a black on white "Stop Ahead" sign shall be posted to instruct operators to immediately reduce to Restricted Speed and be prepared to stop at the red flag or white on red "Stop" sign.

Stop Sign: 30 meters (100 feet) ahead of protected work area and to the right of the affected track a red flag or a white on red "Stop" sign shall be posted to stop all trains. Trains shall stop until the red flag, or stop sign, has been removed and permission to proceed has been given by the flag person.

OR

Slow Zone Ahead: 240 meters (800 feet) ahead of protected work area and to the right of the affected track, a black on white "Slow Zone Ahead" sign shall be posted to instruct operators to reduce speed-to-speed limit sign.

Temporary Speed Limit: 90 meters (300 feet) ahead of protected work area and to the right of the affected track, a black on yellow "Speed Limit Sign (speed limit is established per the work protection and/or track condition) shall be posted to instruct operator to operate their train at the specific speed posted.

Resume Speed: 90 meters (300 feet) beyond protected work area and to right of the affect track, a green flag or solid green sign shall be posted to allow trains to resume normal posted speed when the cab of the lead car reaches the sign.

Operators encountering signs marking a temporary Reduced Speed Zone, when they have no Special Instructions or Train Orders for such a zone, shall reduce the train speed as indicated by the signs and notify the Controller immediately.

If workers fail to acknowledge train signals and/or fail to move to a point of safety, the train operator shall bring the train to a full stop and notify OCC.

NOTE - Posting of speed zones in high-speed areas will be done by VTA staff only, except as exempted by the Restricted Access Permit Office.

EMERGENCY PROTECTION, (HIGH SPEED ABS AREAS)

When it is necessary to temporarily protect a section of right of way in ABS Territory due to a defect in overhead or trackway, a Reduced Speed Zone shall be set up in the following manner using reflectorized cones and flags:

Reflectorized Cone - 240 meters (800 feet) ahead of protected area and to the right of the affected track.
Yellow Flag - 30 meters (100 feet) ahead of protected area and to the right of the affected track.
Green Flag - 90 meters (300 feet) beyond protected area and to the right of the affected track.
Red Flag - When required, a Flagger shall be stationed with a red flag just prior to the work area, monitoring train operation and employees working within the area. The Flaggers shall ensure that all workers move to a safe location when trains approach. If employees do not move to a safe location, the Flaggers shall stop the train until it is safe for the train to proceed through the work zone.

This temporary protection shall be used only until a Reduced Speed Zone can be put in place by the Way, Power & Signals Department.

EMERGENCY PROTECTION

When it is necessary to temporarily protect a section of right of way, due to a defect in the overhead or trackway, a Reduced Speed Zone shall be set up in the following manner using reflectorized cones and flags:

Reflectorized Cone - 30 meters (100 feet) ahead of protected area and one meter to right of track.
Yellow Flag - 15 meters (50 feet) ahead of protected area and one meter to right of track. OCC shall designate the speed restriction form the yellow to the green flag.
Green Flag - 90 meters (300 feet) beyond protected area and one meter to right of track.

HAND SIGNALS

Hand signals governing train operation are detailed in the Light Rail Restricted Access Permit Manual. Signals may be given by hand, flag, lantern, or other objects. Operators shall acknowledge hand signals by horn or bell. Hand signals given during times of limited visibility must be given by lantern.

A red or orange flag, a road flare, a boulevard stop sign or any object waved violently by any person on or near the track shall be considered as a signal to stop.

PROTECTION OF BALLAST

The ballast within the Light Rail corridor shall be kept free of dirt and other debris. A filter fabric material shall be placed at all locations along the LRT corridor where the Contractor will be performing work within the LRT corridor. The filter fabric shall be placed along the nearest track ballast to ensure the ballast is kept clean. The filter fabric material shall be placed for a width of at least 1.0 meter and shall start at the beginning limit of the ballast material; however, the fabric shall be kept clear of the LRT track ties by a distance of 0.6 meter. The type of fabric and fabric restrainers shall be the same as specified in “Temporary Cover” of these special provisions.

At locations where excavation of ballast is necessary, Contractor shall segregate ballast from other excavated material including but not limited to using sheet pile.

Contractor shall remove ballast which contains dirt or debris deposited on ballast by Contractor, and shall replace with new ballast. New ballast shall be in accordance with VTA specifications for ballast. The Engineer will determine if the ballast is contaminated.

SAFETY FENCE

A safety fence shall be placed at all locations along the LRT corridor where the Contractor will be performing work within the LRT corridor. The safety fence shall be placed between the work area and the track. Proper clearances as required by the VTA requirements shall be maintained for placement of the safety fence. The type of safety fence shall be the same as specified in “Temporary Fence (Type ESA)” of these special provisions.

CONSTRUCTION REQUIREMENTS

Shoring installed within the clearance line shall not extend above the plane which passes through the tops of the rails.

Temporary drainage shall be provided where existing drainage is disturbed by the Contractor's operations. The Contractor shall submit a temporary drainage plan for Engineer's approval.

Excavation and similar equipment working within the LRT right of way shall not be capable of reaching within 3.0 meters of the OCS wires.

PAYMENT

Full compensation for conforming to the requirements in the permit and special provisions and general conditions and these special provisions including but not limited warning flags, ballast, protective shields, LRT flaggers, temporary drainage, fencing, surveying, potholing, and backfilling potholes shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

The costs incurred by VTA for their staff time for inspection, testing, energization/denergization, busing and other work related to the Light Rail system by VTA staff will not be charged to the Contractor, except for liquidated damage assessment as specified elsewhere in these Special Provisions.

Any cost to VTA resulting from any unscheduled disruption to train or bus revenue service caused by the Contractor's action or inaction will be the responsibility of the Contractor.

In consideration of issuance of this permit, the Contractor shall indemnify and hold harmless the Santa Clara Valley Transportation Authority (VTA), its employees and agents from any demands, claims or judgments arising as a result of any act or omission of the Contractor, or the Contractor's employees or agents.

5-1.26 NATURALLY OCCURRING ASBESTOS MATERIAL, GENERAL

Asbestos-containing material (ACM), has been defined in Section 1529, "Asbestos," of the Construction Safety Orders, Title 8, of the California Code of Regulations. Naturally Occurring Asbestos (NOA) material has been discovered through testing of materials from within the project limits.

Attention is directed to "Naturally Occurring Asbestos Material Excavation" elsewhere in these special provisions.

Friable ACM is defined under Asbestos Hazard Emergency Response Act (AHERA) as "any material containing more than 1 percent (%) asbestos by area, that hand pressure can crumble, pulverize or reduce to powder when dry". The term non- friable implies that the asbestos fibers are tightly bound into the matrix of the material and should not become an airborne hazard as long as the material remains intact and undamaged, sawed, sanded, drilled or otherwise abraded during removal.

Samples of potential NOA material were taken from several locations within the project limits as indicated in the Site Investigation Report, Route 87 South HOV Project, San Jose. Asbestos was reported in several composite and discrete samples. The complete report entitled "Site Investigation Report, Route 87 South HOV Project, San Jose, California dated January 2004" is available for inspection at the Department of Transportation, Duty Senior's Desk, 111 Grand Avenue, Oakland, California, and (510) 286-5209. These test results have been used for disposal characterization of material within the project limits and shall not be construed as identifying all locations within the project limits that contain NOA.

Where the material containing NOA with average asbestos concentration greater than 1% is to be removed during excavation, the material shall be considered as friable, shall be treated as hazardous material, and shall be removed, hauled and disposed of in accordance with all applicable Federal, State and local laws and ordinances.

Where the material containing NOA with average asbestos concentration equal to or greater than 0.25% and less than or equal to 1% is to be removed during excavation, the material shall be defined as restricted material, which shall be removed, hauled and disposed of in accordance with all applicable Federal, State and local laws and ordinances.

Where the material containing NOA with average asbestos concentration less than 0.25% or nondetect (ND) is to be removed during excavation, the material shall be defined as non-hazardous material. This material shall become the property of the Contractor and shall be removed, hauled and disposed of in accordance with all applicable Federal, State and local laws and ordinances.

The requirements of subsection (d), "Multi-employer work sites," of Section 1529, "Asbestos," of the Construction Safety Orders, Title 8, of the California Code of Regulations shall be observed during the performance of the work. This shall not be construed as relieving the Contractor from the Contractor's responsibilities as provided in Section 8-1.01, "Subcontracting," of the Standard Specifications.

All dust control measures shall be implemented in accordance with California Division of Occupational Safety and Health Administration (Cal-OSHA), Air Resource Board and other applicable regulations. Excavation, transportation, placement, handling, and disposal of hazardous and restricted materials shall result in no visible dust. The Contractor shall have a water truck available at all times while performing earthwork, excavation or grubbing activities in work areas containing such materials.

All hazardous and restricted material on exteriors of transport vehicles shall be removed and placed either into the current transport vehicle or the excavation prior to the vehicle leaving the exclusion zone. No hazardous and restricted material shall be deposited on public roads. The Contractor shall indemnify the State from any costs due to spillage during the transport of the hazardous and restricted material to the disposal facility.

The Contractor shall monitor the air quality continuously during excavation operations at all locations containing NOA material.

Permits. The Contractor shall procure all permits and licenses, pay all charges and fees for due and lawful prosecution of the work. The Contractor shall notify the Bay Area Air Quality Management District as required by NESHAP, 40CFR Part 61, and California Air Resources Control Board regulations. The Contractor shall also notify Division of Occupational Safety and Health (Cal-OSHA) in accordance with the applicable regulations. A copy of the notification form and attachments shall be provided to the Engineer prior to submittal to the Bay Area Air Quality Management District. Notification shall take place a minimum of 14 days prior to start of work. An asbestos dust mitigation plan shall be submitted to Bay Area Air Quality Management District and their approval obtained prior to starting any excavation work involving NOA.

Codes and standards.--Codes, which govern removal and disposal of materials containing asbestos include, but are not necessarily limited to the following:

1. California Health and Safety Code, Division 20, Chapter 6.5, Hazardous Waste Control.
2. California Code of Regulations, Title 22, Division 4, Chapter 30, "Minimum Standards for Management of Hazardous and Extremely Hazardous Material," latest revisions, as applicable.
3. California Code of Regulations, Title 8, General Industry Safety Order 5208 Asbestos.
4. Occupational Safety and Health Administration, Part 26 (amended), of Title 29 of the Code of Federal Regulations.
5. California Air Resources Board Regulations, Division 3, Chapter 1, Subchapter 7.5, section 93105 (Asbestos Airborne Toxic Control Measure for Construction, Grading, Quarrying and Surface Mining Operations).
6. Bay Area Air Quality Management District Regulations

Submittals – The Contractor shall prepare a project Health and Safety Plan to prevent or minimize exposure to asbestos. The Contractor's attention is directed to Title 8, California Code of Regulations, Section 5192 (b), Occupational Safety and Health Guidance Manual published by the National Institute of Occupational Safety and Health (NIOSH), Occupational Safety and Health Administration (OSHA), and United States Environmental Protection Agency (USEPA) for elements of the site safety plan. The Health and Safety Plan shall contain as a minimum but not limited to the identification of key personnel for the project, job hazard analysis for work assignments, summary of risk assessment, air monitoring plan, personal protective equipment, delineation of work zones on-site, decontamination procedures, general safe work practices, security measures, emergency response plans, and worker training.

The Health and Safety Plan shall utilize monitoring and exposure standards based on Construction Standards of Title 8, California Code of Regulations, Construction Safety Orders, Section 1529, “Asbestos” and as a minimum shall contain a description of activities, specific means employed to achieve compliance, report of the technology considered, exposure monitoring, schedule for the implementation of the program, a work practice program, administrative control schedule, asbestos removal and abatement plan and other relevant information. The Health and Safety Plan shall include an exposure monitoring plan that shall include, but not limited to, upwind and downwind perimeter monitoring and a discussion of how the exposure monitoring will be conducted during the progression of work in areas designated as containing asbestos. The Health and Safety Plan shall be prepared and signed by the Contractor’s Industrial Hygienist certified by the State of California before submission to the Engineer for review and acceptance. The Plan shall be submitted to the Engineer at least 15 working days prior to beginning any work in areas containing asbestos.

Training – Prior to performing any work in areas containing asbestos, personnel who have no prior training or are not current in their training status, including State Personnel, shall complete a safety training program provided by the Contractor, which meets the requirement of Title 8, California Code of Regulations, Section 1529. The Contractor shall provide a written certification of completion of safety training to the Engineer for all trained personnel prior to performing any work in areas containing NOA.

Equipment and Medical Surveillance – Personnel protective equipment, training, and medical surveillance required by the Contractor’s Health and Safety Plan shall be provided to State personnel by the Contractor. The number of State personnel will be 5.

Stockpiles – Hazardous and restricted NOA materials shall be transferred temporarily to a stockpile location approved by the Engineer before disposal. These stockpiles shall be properly maintained. The Contractor shall prepare a work plan for the handling and stockpiling of hazardous and restricted NOA materials. The stockpile locations shall also be maintained in accordance with following requirements:

The material shall be stored on undamaged 60-mil high-density polyethylene or an equivalent impermeable barrier unless the stockpiling location is on a paved surface. If the location is on a paved surface the thickness of the barrier can be reduced to 20-mil high-density polyethylene or its equivalent. The dimensions of the barrier shall exceed the dimensions of the stockpile at all times. Any seams in the barrier shall be sealed to prevent leakage.

The surface of these stockpiles shall be kept adequately wetted. At the end of the day these stockpiles shall be covered with undamaged 12-mil polyethylene or an equivalent impermeable barrier to prevent windblown dispersion and precipitation run-off and run-on. When more than one sheet is required to cover the material, the sheets shall be overlapped a minimum of 1.5 feet in a manner that prevents water from flowing onto the material. The cover shall be secured in a manner that keeps it in place at all times. Driven anchors shall not be used except at the perimeter of the stockpile. The cover shall be inspected and maintained in accordance with the requirements of "Water Pollution Control" of these special provisions.

These and any other stockpiling requirements apply to all temporary storage of hazardous and restricted NOA materials outside of an excavation or a transport container including, but not limited to, staging of excavated material next to the excavation prior to pickup by loading equipment, accumulating material for full transport loads, and awaiting test results required by a disposal facility. The removal of stockpiles shall begin within 30 days of accumulating 100 kg of such materials. After the removal has occurred the Contractor shall be responsible for any cleanup deemed necessary by the Engineer.

Sampling Requirements--The Contractor shall be OSHA-certified by the Division of Occupational Safety and Health, and AHERA trained, who has taken and passed an EPA-approved Building Inspector course. The sampling investigation shall be consistent with the US EPA's Asbestos/NESHAP Regulated Asbestos Containing Materials Guidance. The Contractor shall sample and test the hazardous and restricted NOA material to be excavated at his own expense for any additional acceptance criteria put forth by the disposal facility.

Sampling Method--Samples shall be analyzed for NOA concentration by a laboratory certified by the Department of Health Services, according to the method specified by methods approved by Air Resources Board regulations. Laboratory results shall be sent by facsimile or hand delivered to the Engineer as soon as they are available. A summary report of sampling protocols, chain of custody, analysis and laboratory data sheets shall be supplied to the Engineer within 15 days of completion of sampling.

Payment – Full compensation for conforming to the requirements of this section, except as specifically provided elsewhere in these special provisions, shall be considered as included in the prices paid for various contract items involved and no additional compensation will be allowed therefor.

5-1.27 HAZARDOUS, RESTRICTED AND NON-HAZARDOUS MATERIAL, GENERAL

Attention is directed to "Hazardous, Restricted and Non-Hazardous Material Excavation" under "Earthwork" of these special provisions regarding the removal and disposal of hazardous, restricted and non-hazardous material.

Attention is directed to "Naturally Occurring Asbestos Material, General" and "Naturally Occurring Asbestos Material Excavation" elsewhere in these special provisions.

Hazardous, restricted and non-hazardous material has been discovered through testing within the project limits. Testing consisted of collecting and analyzing in situ samples from within the limits of excavation shown on the plans. The report entitled "Site Investigation Report, Route 87 South HOV Project, San Jose, California dated January 2004" is available for inspection at the Department of Transportation, Duty Senior's Desk, 111 Grand Avenue, Oakland, California, (510) 286-5209. The test results from this report have been used for disposal characterization of material within the project limits and shall not be construed as identifying all locations within the project limits that contain contaminants.

Within the context of this contract, wherever the following terms are used , the meaning and intent shall be interpreted as provided below:

A "Hazardous" shall apply to soil material with contaminant levels that meet or exceed the contaminant levels specified in Title 22 in the California Code of Regulations (CCR), Section 66261.24. The designation "hazardous" shall also apply to materials designated as hazardous under the Resource Conservation and Recovery Act (RCRA), and to material with BTEX (Benzene, Toluene, Ethylbenzene, Xylenes) greater than Preliminary Remediation Goals (PRGs) for Industrial Wastes, and to PCBs and pesticides exceeding the limits established by applicable regulations.

B. "Restricted" shall apply to soil material with Total Petroleum Hydrocarbons (TPH) greater than 100 mg/kg.

C. "Non-hazardous" shall apply to soil material with contaminant levels below the levels specified in the California Code of Regulations Title 22, the Preliminary Remediation Goals (PRGs) for Industrial Wastes, other applicable regulations, and/or with TPH levels less than or equal to 100 mg/kg, and/or with non-detect contaminant levels.

Characterization and disposal of additional material resulting from excavations performed outside of the pay limits shown on the plans, and specified in the Standard Specifications, for the Contractor's convenience, shall be at the Contractor's expense. This resultant material shall be presumed to be hazardous material. The Contractor shall dispose of the resultant material in conformance with the provisions in "Earthwork" of these special provisions. When the material must be removed from highway right of way, the Contractor shall furnish replacement material suitable for the purpose intended in conformance with the provisions in Section 19, "Earthwork," of the Standard Specifications.

APPLICABLE RULES AND REGULATIONS

Excavation, transport and disposal of hazardous material, restricted material, and non-hazardous material shall be in accordance with the rules and regulations of the following agencies:

United States Department of Transportation (USDOT)
United States Environmental Protection Agency (USEPA)
California Environmental Protection Agency (CAL-EPA)

1. Department of Toxic Substance Control (DTSC)
2. Integrated Waste Management Board
3. Regional Water Quality Control Board, Region 2 (RWQCB)
4. State Air Resources Board

Bay Area Air Quality Management District (BAAQMD)
California Division of Occupational Safety and Health Administration (CAL-OSHA)
City of San Jose and Santa Clara County.

PERMITS AND LICENSES

The Contractor shall procure all permits and licenses, pay all charges and fees, and give all notices necessary and incident to the due and lawful prosecution of the work, including registration for transporting vehicles carrying the hazardous material. The California Environmental Quality Act (CEQA) of 1970 (Chapter 1433, Stats. 1970), as amended may be applicable to permits, licenses and authorizations which the Contractor shall obtain from all agencies in connection with performing the work of the contract. The Contractor shall comply with the provisions of said statutes in obtaining such permits, licenses and other authorizations. The Contractor shall also comply with the provisions in section 7-1.04 "Permits and Licenses" of the Standard Specifications.

The Engineer will obtain the Environmental Protection Agency Generator Identification No. and Board of Equalization Identification Number as the State is the Generator.

HEALTH SAFETY AND WORK PLAN

The Contractor's Industrial Hygienist Certified by State of California shall prepare a detailed Site Health, Safety and Work Plan for all site personnel in accordance with the California Code of Regulations, DTSC and CAL-OSHA regulations. The Health, Safety and Work Plan shall include, at a minimum, but not limited to key site safety personnel, risks associated with the work, training requirements, appropriate personal protective equipment, medical surveillance requirements, air monitoring requirements, work zones, physical barriers, and decontamination requirements. The Health, Safety and Work Plan shall be submitted at least fifteen (15) working days prior to beginning any work for review and acceptance by the Engineer. If the plan is unacceptable it shall be returned, within fifteen (15) working days of the submittal, to the Contractor for revision. The Engineer shall have five (5) working days to review and accept or reject the revised plan from the date the revised plan is received from the Contractor. No work shall proceed until the plan is accepted by the Engineer. Prior to submittal, the Contractor shall have the Health, Safety and Work Plan prepared and signed by a Civil Engineer, registered in the State of California and by a Certified Industrial Hygienist.

SAFETY

Prior to performing any work at the locations containing material classified as hazardous and restricted, all personnel, including State Personnel, shall complete a CAL-OSHA 40 hour safety training program which meets 29 CFR 1910.120 and 8 CCR 5192 covering the potential hazards as identified. The training, including subsequent training required until the completion of the work, shall be provided by the Contractor. The Contractor shall provide a certification of completion of the Safety Training Program to all personnel. Any personal protective equipment required by the Contractor's Health, Safety and Work Plan for personnel working within the exclusion zone will be supplied to State personnel by the Contractor. The number of State personnel requiring the above mentioned safety training program and personal protective equipment will be 5.

The decontamination area shall be located outside of the exclusion zone. Water from decontamination procedures shall be collected and disposed of at an appropriate disposal site by the Contractor. Non-reusable protective equipment, once used

by any personnel, including State personnel, shall be collected and disposed of at an appropriate disposal site by the Contractor.

STOCKPILING

Hazardous and restricted materials shall be transferred temporarily to a stockpile location approved by the Engineer before disposal. These stockpiles shall be properly maintained. The Contractor shall prepare a work plan for the handling and stockpiling of hazardous and restricted materials. The stockpile locations shall also be maintained in accordance with following requirements:

The material shall be stored on undamaged 60-mil high-density polyethylene or an equivalent impermeable barrier unless the stockpiling location is on a paved surface. If the location is on a paved surface the thickness of the barrier can be reduced to 20-mil high-density polyethylene or its equivalent. The dimensions of the barrier shall exceed the dimensions of the stockpile at all times. Any seams in the barrier shall be sealed to prevent leakage.

The surface of these stockpiles shall be kept adequately wetted. At the end of the day these stockpiles shall be covered with undamaged 12-mil polyethylene or an equivalent impermeable barrier to prevent windblown dispersion and precipitation run-off and run-on. When more than one sheet is required to cover the material, the sheets shall be overlapped a minimum of 1.5 feet in a manner that prevents water from flowing onto the material. The cover shall be secured in a manner that keeps it in place at all times. Driven anchors shall not be used except at the perimeter of the stockpile. The cover shall be inspected and maintained in accordance with the requirements of "Water Pollution Control" of these special provisions.

These and any other stockpiling requirements apply to all temporary storage of hazardous and restricted materials outside of an excavation or a transport container including, but not limited to, staging of excavated material next to the excavation prior to pickup by loading equipment, accumulating material for full transport loads, and awaiting test results required by a disposal facility. The removal of stockpiles shall begin within 30 days of accumulating 100 kg of such materials. After the removal has occurred the Contractor shall be responsible for any cleanup deemed necessary by the Engineer.

SAMPLING AND ANALYSIS

Sampling and analysis shall be based on guidelines in USEPA, SW 846, "Test Methods for Evaluating Solid Waste, Volume II: Field Manual Physical/Chemical Methods".

Hazardous material was found during testing of soil samples at Alma Overhead, Alma Avenue UC, and Alma Station PUC. Hazardous material was also found during the testing of soil samples at Retaining Wall 3. Restricted material was found during testing of soil samples at Almaden Road UC. The material excavated during the widening/modification of Alma Overhead, Alma Avenue UC, and Alma Station PUC structures shall be stockpiled separately for each location prior to disposal. The material excavated for Retaining Wall 3 excavation shall also be stockpiled prior to disposal. The material excavated during the widening/modification of Almaden Road UC structure shall also be stockpiled separately prior to disposal. The material excavated during widening/modification of Curtner Avenue Undercrossing, Capitol Expressway Undercrossing, Capitol Expressway Undercrossing (Off-Ramp), and Virginia Street Overcrossing shall also be stockpiled separately for each location prior to disposal.

Each stockpile shall be sampled and tested separately prior to disposal. At least four soil samples shall be taken from an excavated quantity of 600 cubic meters. Thereafter, sampling shall be at a minimum rate of one sample per 150 cubic meter of excavated soil. The soil samples shall be representative of each stockpile. All the discrete samples for each stockpile shall be composited into one sample and each composite soil sample analyzed for Title 22 Metals for Alma Overhead, Alma Avenue UC, and Alma Station PUC, Retaining Wall 3, Curtner Avenue Undercrossing, Capitol Expressway Undercrossing, Capitol Expressway Undercrossing (Off-Ramp), and Virginia Street Overcrossing, and for Total Petroleum Hydrocarbons (TPHd and TPHmo) for Retaining Wall 3, Curtner Avenue Undercrossing, Capitol Expressway Undercrossing, Capitol Expressway Undercrossing (Off-Ramp), and Virginia Street Overcrossing by a laboratory certified by the California Department of Health Services. The Contractor shall submit, for review and acceptance of the Engineer, a sampling and testing plan, analytical methods and procedures, and the name and the address of the analytical laboratory at least 15 working days prior to beginning sampling or analysis for characterization of stockpiled material. Samples shall be transported to the laboratory within 24 hours of sampling. The work plan based on sampling and testing plan shall be prepared and signed by a California registered geologist or professional engineer qualified to do so as per regulations and be submitted for review by the engineer. The laboratory shall run analytical tests a 48-hour turn-around. The Engineer will make the final decision on characterization of the material after review of the test data. Five (5) working days shall be allowed for the review of test data. Laboratory results shall be sent by facsimile or hand delivered to the Engineer as soon as they are available. A summary report of sampling protocols, chain of custody, analysis and laboratory data sheets shall be supplied to the Engineer within 20 working days of completion of sampling. Based on the total test results for metals the soil samples shall be tested for soluble concentration as directed by the Engineer. If in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Ways Delays" of the Standard Specifications.

The Contractor shall test the material to be excavated at his own expense for any additional acceptance requirements put forth by the disposal facility. Sampling and analysis shall be performed using the sampling and analysis procedure required by the disposal facility. The Contractor shall take samples and obtain analyses under the supervision and guidance of a California registered professional Engineer or Geologist experienced in site characterization.

MEASUREMENT AND PAYMENT

Full compensation for conforming to the requirements of this section shall be considered as included in the prices paid for the various contract items of work affected by this section and no additional compensation will be allowed therefor.

5-1.28 AERIALLY DEPOSITED LEAD

Aerially deposited lead is present within the project limits. Aerially deposited lead is lead deposited within unpaved areas or formerly unpaved areas, primarily due to vehicle emissions.

Attention is directed to "Material Containing Aerially Deposited Lead" of these special provisions.

Portions of the Site Investigation Report are included in the "Material Information" handout. The complete report, entitled "Site Investigation Report, Route 87 South HOV Project, San Jose, California dated January 2004," is available for inspection at the Department of Transportation, Duty Senior's Desk, 111 Grand Avenue, Oakland, California, (510) 286-5209.

Aerially deposited lead is typically found within the top 0.6-m of material in unpaved areas within the highway right of way. Levels of lead found near the project limits range from less than 1.00 mg/kg to 57.00 mg/kg total lead as analyzed by EPA Test Method 6010 or EPA Test Method 7000 series.

Once the Contractor has completed the placement of material containing aerially deposited lead in conformance with these special provisions and as directed by the Engineer, the Contractor shall have no responsibility for such materials in place. The Department will not consider the Contractor a generator of such contaminated materials. Further cleanup, removal or remedial actions for such materials will not be required if handled or disposed of as specified herein.

Excavation, reuse, and disposal of material with aerially deposited lead shall be in conformance with all rules and regulations including, but not limited to, those of the following agencies:

United States Department of Transportation (USDOT)
United States Environmental Protection Agency (USEPA)
California Environmental Protection Agency (Cal-EPA)
California Department of Health Services
Department of Toxic Substances Control (DTSC), Region 2
California Division of Occupational Safety and Health Administration (Cal-OSHA)
Integrated Waste Management Board
Regional Water Quality Control Board (RWQCB), Region 2
State Air Resources Control Board
Bay Area Air Quality Management District (AQMD)

5-1.29 ENVIRONMENTALLY SENSITIVE AREA

Attention is directed to the designated Environmentally Sensitive Areas (ESAs) shown on the plans. The exact location of the boundaries of ESAs will be determined by the Engineer and shall be clearly delineated by the placement of temporary fence (Type ESA) as specified in these special provisions.

Vehicle access, storage or transport of materials or equipment, or other project related activities are prohibited within the boundaries of ESAs.

The Contractor shall repair, or perform work to mitigate, damage or impacts to ESAs caused by the Contractor's operations, at the Contractor's expense. If the Engineer determines repairs or mitigation work will be performed by others, or if mitigation fees are assessed the Department, deductions from moneys due or to become due the Contractor will be made for the repair or mitigation costs.

Contractor shall cooperate in permitting ESA monitoring operations during construction as directed by the Engineer.

Full compensation for work involved in complying with the requirements of "Environmentally Sensitive Areas", of these special provisions shall be considered as included in the contract prices paid for the various items of work involved and no additional time or compensation will be allowed therefor.

5-1.30 ARCHAEOLOGICAL SENSITIVE AREAS

Contractor's attention is directed to the fact that the project work along Route 87 in the vicinity of the Capitol Expressway interchange is within an archaeological sensitive area. Where designated on the plans, archaeological sensitive areas shall be designated as ESA areas and treated in accordance with "Environmentally Sensitive Areas" of these special provisions. When fencing and avoidance of an archaeological ESA is not feasible, the area shall be designated a Special

Construction Area (SCA). All construction activities within the SCA shall be performed in accordance with these special provisions and as directed by the Engineer.

General: It is the intent of the State under Section 106 of the National Historic Preservation Act of 1966, the Caltrans Environmental Handbook (Vol. 2:1-2.2) that the ESA be archaeologically monitored during construction and that impacts to archaeological resources be avoided. Archaeological monitoring by the State archaeologist will be required during construction activities.

The California Public Resources Code Chapter 1.7, section 5097.5 makes it a criminal offense for anyone to knowingly disturb a historical feature. California Public Resources Code Chapter 5097.98 and 5097.00 require protection of Native American remains which might be found, and outline procedures for handling any burials found. The California Public Resources Code Section 5097.9 and Health and Safety Code 7050 require coordination with the Native American Heritage Commission (NAHC).

Construction: The State will perform archaeological monitoring during construction of this project. The Contractor shall cooperate with the archaeologists with regard to the discovery and evaluation of archaeological materials, if any are uncovered during construction.

An archaeological pre-construction meeting with the Contractor (this can be done as part of the general pre-construction meeting) shall be held prior to the start of construction, The purpose of the meeting is to discuss archaeological issues, ascertain delineation of the location of the ESA (delineated in the field with orange fencing) on the ground, and introduce the State archaeologist to the Contractor.

No sub-surface construction activities are permitted within ESA without prior approval by the Engineer AND the archaeological monitor. Sub-surface construction activities include, but are not limited to: temporary fence post installation, geotechnical borings, clearing and grubbing, excavation, installation of shoring, grading, piling work, utility installation, and other earthmoving or land surface alteration of any kind.

If human skeletal material or other archaeological finds are encountered by the Contractor during construction, the Contractor shall stop work immediately and shall immediately notify the Engineer. The Contractor will be directed to continue work outside the clearly delineated ESA, while the staff archaeologists investigate the find. The staff archaeologist may require up to 14 working days to complete an archaeological investigation at each location.

If, in the opinion of the Engineer, the Contractor's operation is delayed or interfered with by reason of the archaeological investigation, the State will compensate the Contractor for such delay to the extent provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications, and not otherwise, except as provided in Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

Contractor labor, equipment and materials used in assisting the archaeologist will be paid for as extra work as provided in section 4-1.03D, "Extra Work," of the Standard Specification. Once an archaeologist investigation is complete, the area in the vicinity of a find shall be designated an SCA.

Full compensation for work involved in complying with the requirements of "Archaeological Sensitive Areas", of these special provisions shall be considered as included in the contract prices paid for the various items of work involved and no additional time or compensation will be allowed therefor.

5-1.31 MITIGATION MEASURES

The State has adopted a Mitigated Negative Declaration/Finding of No Significant Impact and Initial Study/Environmental Assessment for this project dated November 2003. This report is available for inspection at the Department of Transportation, Duty Senior's Desk, 111 Grand Avenue, Oakland, CA, 94612, (510) 286-5209.

The following Contractor is advised that compliance with the provisions of this document is a requirement of the Contract. Contractor shall comply with the mitigation measures contained in the Final Environmental Impact Report, the regulatory agency permits, and the following requirements:

Riparian Habitat

Contractor shall take all reasonable precautions to prevent incidental incursions of personnel or equipment into riparian habitat shown on plans and/or marked in the field to be avoided. Prior to any site preparation, grading or construction at Guadalupe River, Contractor shall mark the limits of clearing and grubbing. The clearing and grubbing limits shall be approved by the Engineer in writing, and ESA fencing shall be installed to delineate clearing and grubbing limits prior to commencement of any work near the River.

Steelhead Rainbow Trout and Chinook Salmon

During construction, all concrete poured during widening of the bridges over Guadalupe River must be completely dried before it comes into contact with Guadalupe River waters.

All site preparation, grading and construction activity at Guadalupe River shall be restricted to the dry season as defined by the most restrictive of the jurisdictional permits. No equipment shall be operated in the live, flowing stream channel of Guadalupe River. Prior to site preparation, grading and/or construction, water in Guadalupe River will be diverted as shown on the plans unless modifications are approved in writing by the Engineer. Any proposed modification to the stream diversion must demonstrate less impact to fish passage and habitat than the diversion in the plans. A plan showing any proposed modification to the stream diversion must be submitted to the Engineer for regulatory agency review and approval 60 days prior to diversion installation.

Western Pond Turtles

Contractor shall maintain channel connectivity in the Guadalupe River at all times to avoid impacts to the movement of Western Pond Turtles.

Raptors

If possible, Contractor's construction activities, particularly tree and shrub removal, will be scheduled between September and December to avoid the nesting season for most bird species, including raptors.

Contractor shall provide the Engineer with written notice at least 15 and not more than 30 days prior to any site preparation, grading or construction activity to allow the State biologist to conduct pre-construction surveys for nesting raptors.

If an active nest is located during the breeding season, (January 1 to August 31), Contractor shall erect ESA fence to establish such a construction-free buffer zone at 75 meters (approximately 250 feet) around the active nest, as directed by the Engineer. No activities, including grading or other construction, shall proceed in the ESA.

Burrowing Owls

Contractor shall provide the Engineer with written notice at least 15 and not more than 30 days prior to any site preparation, grading, or construction activities to allow the State biologist to conduct preconstruction surveys for burrowing owls.

If an active nest is located during the breeding season (February 1 to August 31), the Contractor shall erect ESA fence to establish such a construction-free buffer zone at 75 meters (approximately 250 feet) around the active burrow, as directed by the Engineer. If an active nest is located during the non-breeding season (September 1 to January 31), the Contractor shall erect ESA fence to establish a construction-free buffer zone at 50 meters (approximately 160 feet) around the active burrow, as directed by the Engineer. No activities, including grading or other construction shall proceed in the ESA.

The State's consulting biologists will conduct weekly surveys to determine the status of the burrow. If a burrow becomes inactive, the buffer zone may be removed following consultation with the Engineer and the California Department of Fish and Game, and after written permission is obtained from the Engineer.

If avoidance of a burrow is infeasible, burrowing owls may be evicted by a State biologist during the non-breeding season only. Contractor shall submit written documentation that avoidance is not possible and a request for owl eviction to the Engineer 30 days prior to any planned activity within 50 meters (approximately 160 feet) of the occupied burrow. No activity may proceed in the 50 meter buffer zone until the owl(s) are evicted and the Engineer provides Contractor with written notice thereof.

Noise

Contractor shall limit pile driving to the hours of 8:00 AM to 5:00 PM, Monday through Friday. Any deviation from these hours must be approved in writing by the Engineer. Contractor shall construct any soundwalls for the project as the first order of work in that area to the maximum extent feasible.

Contractor shall maintain and operate all equipment consistent with the manufacturer's specifications. Construction equipment will include available noise suppression devices and properly maintained mufflers.

Contractor shall site fixed and mobile equipment to minimize noise emissions outside the Route 87 right-of-way in the vicinity of residences and other sensitive receptors.

Contractor shall minimize the staging of construction equipment and unnecessary idling of equipment in the vicinity of residences and other sensitive receptors.

All pre-construction surveys in this section are valid for a period of 14 days only. Contractor shall begin work within 14 days after the completion of the pre- construction survey. If the Contractor does not begin work 14 days after the completion of the pre-construction survey, a new pre-construction survey is required. The cost of the new pre-construction survey will be paid by the Contractor and such costs will be deducted from any money due or to become due to the Contractor.

Except for delays related to the valid period for preconstruction surveys, if Contractor's operation is delayed or interfered with by reason of complying with this special provision**,** State will compensate Contractor for such delays to the extent provided in for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications**.**

Full compensation for work involved in complying with the requirements of this special provision shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.32 MIGRATORY NESTING BIRDS AND ROOSTING WILDLIFE

The Contractor's attention is directed to the nesting/breeding migratory birds and roosting bats that may be present in the project area. For all migratory birds except raptors and burrowing owls, the nesting season in the project area is considered to be from February 15th to August .31st It is against the law to harm these birds and other wildlife as per the Migratory Bird Treaty Act and the California Fish and Game Code. It is the Contractor's responsibility to ensure that birds and other wildlife (such as bats) are not allowed to nest or roost in areas that may be impacted by construction.

All bridge work and clearing and grubbing activities shall occur between September 1st and February 15th to the maximum extent feasible. The Contractor shall notify the Engineer at least 15 and no more than 30 days in advance of bridge work or clearing and grubbing activities.

Attention is directed to "Description of Bridge Work" and "Clearing and Grubbing" of these special provisons. Bridge work includes the widening of the southbound structures of Almaden Road UC (Widen)(Bridge No. 37-0366 R/L), Alma Overhead (Widen)(Bridge No. 37-0420 R/L), Alma Avenue UC ((Widen)(Bridge No. 37-0368 R/L), Alma Station PUC (Widen)(Bridge No. 37-0434L), Alma Station Separation(Widen)(Bridge No. 37-0421 R/L), and Willow Street Viaduct (Widen)(Bridge No. 37-0346 R/L), Curtner Avenue UC (Bridge No. 37-0362 R/L), Capitol Expwy UC (Bridge No. 37-0415 R/L), Capitol Expwy UC (Off-ramp)(Bridge No. 37-0415S), Virginia Street Overcrossing (Bridge No. 37-0315)

Prior to the beginning of the nesting season, Contractor shall inspect all project areas that may be impacted by construction and remove any inactive bird nests. During the nesting season, the Contractor shall inspect all project areas that may be impacted by construction, including all vegetation, grounds, and bridge(s), every two (2) days to identify any new and partially built nests before the nests are halfway completed.

The Contractor shall be responsible for the removal of any new and partially built nests. Nests may be removed with a long pole, may be hosed off with water, or other another method may be used as approved by the Engineer. These methods must be directed only at partially-built nests and not at birds. No birds, nests with eggs, or nests with hatchlings will be disturbed. The Contractor shall maintain and submit a log weekly documenting the time, date, condition of nests and any nest prevention actions taken during inspections.

In the event that an active nest or roost is discovered in the construction areas, or in adjacent areas considered by the State biologist to be disturbed by construction, the Contractor shall erect ESA fence around the nest /roost at the direction of the Engineer. No construction activity may occur within the ESA until the Contractor coordinates with the Engineer, California Department of Fish and Game (CDFG), and a CDFG-approved ornithologist to develop alternatives to avoid take of the nest. Once consultation is complete, work may begin/resume when written permission is obtained from the Engineer to remove the ESA. No additional time or compensation will be allowed therefor.

In the event that an eviction of a bat species occurs, a qualified biologist shall perform the eviction, and construction shall begin not less than 24 hours after the eviction (i.e. one night after the eviction).

If necessary, Contractor shall install and maintain nesting and roosting exclusion devices throughout the breeding season, or until work in the area makes the devices unnecessary. The need for such devices shall be determined by the Engineer. Contractor shall be responsible for the maintenance, repair, or replacement of exclusion devices until all of the work is complete. Contractor shall remove all exclusion devices when work in the area is complete.

If any deficiencies related to this requirement are discovered by the Engineer or their designated representative during the life of the contract, the Contractor will be notified and expected to correct the problem within twenty-four (24) hours.

The Contractor shall be responsible for any work stoppages and shall be expected to complete all work as specified elsewhere in these special provisions.

Full compensation for work involved in complying with the requirements of this special provision shall be considered as included in the contract prices paid for the various items of work involved and no additional time or compensation will be allowed therefor.

SECTION 6. (BLANK)

SECTION 7. (BLANK)

SECTION 8. MATERIALS

SECTION 8-1. MISCELLANEOUS

8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the United States Standard Measures which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.
B. Before other non-metric materials and products will be considered for use, the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.
C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details, the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The plans and working drawings shall be submitted at least 7 days before the Contractor intends to begin the work involved.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS
ASTM Designation: A 325M

METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT
ASTM Designation: A 82

METRIC SIZE SHOWN ON THE PLANS mm^2	SIZE TO BE SUBSTITUTED $inch^2$ x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

SUBSTITUTION TABLE FOR BAR REINFORCEMENT

METRIC BAR DESIGNATION NUMBER[1] SHOWN ON THE PLANS	BAR DESIGNATION NUMBER[2] TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

[1]Bar designation numbers approximate the number of millimeters of the nominal diameter of the bars.
[2]Bar numbers are based on the number of eighths of an inch included in the nominal diameter of the bars.
No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

SUBSTITUTION TABLE FOR SIZES OF:

(1) STEEL FASTENERS FOR GENERAL APPLICATIONS (ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55), and

(2) HIGH STRENGTH STEEL FASTENERS (ASTM Designation: A 325 or A 449)

METRIC SIZE SHOWN ON THE PLANS mm	SIZE TO BE SUBSTITUTED inch
6 or 6.35	1/4
8 or 7.94	5/16
10 or 9.52	3/8
11 or 11.11	7/16
13 or 12.70	1/2
14 or 14.29	9/16
16 or 15.88	5/8
19 or 19.05	3/4
22 or 22.22	7/8
24, 25, or 25.40	1
29 or 28.58	1-1/8
32 or 31.75	1-1/4
35 or 34.93	1-3/8
38 or 38.10	1-1/2
44 or 44.45	1-3/4
51 or 50.80	2
57 or 57.15	2-1/4
64 or 63.50	2-1/2
70 or 69.85	2-3/4
76 or 76.20	3
83 or 82.55	3-1/4
89 or 88.90	3-1/2
95 or 95.25	3-3/4
102 or 101.60	4

SUBSTITUTION TABLE FOR NOMINAL THICKNESS OF SHEET METAL

UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS (GALVANIZED)	
METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch	METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269	--------	--------
0.61	0.0239	--------	--------
0.53	0.0209	--------	--------
0.45	0.0179	--------	--------
0.42	0.0164	--------	--------
0.38	0.0149	--------	--------

SUBSTITUTION TABLE FOR WIRE

METRIC THICKNESS SHOWN ON THE PLANS mm	WIRE THICKNESS TO BE SUBSTITUTED inch	GAGE NO.
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

SUBSTITUTION TABLE FOR PIPE PILES

METRIC SIZE SHOWN ON THE PLANS mm x mm	SIZE TO BE SUBSTITUTED inch x inch
PP 360 x 4.55	NPS 14 x 0.179
PP 360 x 6.35	NPS 14 x 0.250
PP 360 x 9.53	NPS 14 x 0.375
PP 360 x 11.12	NPS 14 x 0.438
PP 406 x 12.70	NPS 16 x 0.500
PP 460 x T	NPS 18 x T"
PP 508 x T	NPS 20 x T"
PP 559 x T	NPS 22 x T"
PP 610 x T	NPS 24 x T"
PP 660 x T	NPS 26 x T"
PP 711 x T	NPS 28 x T"
PP 762 x T	NPS 30 x T"
PP 813 x T	NPS 32 x T"
PP 864 x T	NPS 34 x T"
PP 914 x T	NPS 36 x T"
PP 965 x T	NPS 38 x T"
PP 1016 x T	NPS 40 x T"
PP 1067 x T	NPS 42 x T"
PP 1118 x T	NPS 44 x T"
PP 1219 x T	NPS 48 x T"
PP 1524 x T	NPS 60 x T"

The thickness in millimeters (T) represents an exact conversion of the thickness in inches (T").

SUBSTITUTION TABLE FOR STRUCTURAL TIMBER AND LUMBER

METRIC MINIMUM DRESSED DRY, SHOWN ON THE PLANS mm x mm	METRIC MINIMUM DRESSED GREEN, SHOWN ON THE PLANS mm x mm	NOMINAL SIZE TO BE SUBSTITUTED inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

SUBSTITUTION TABLE FOR NAILS AND SPIKES

METRIC COMMON NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC BOX NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC SPIKE, SHOWN ON THE PLANS Length, mm Diameter, mm	SIZE TO BE SUBSTITUTED Penny-weight
50.80 2.87	50.80 2.51	_____	6d
63.50 3.33	63.50 2.87	_____	8d
76.20 3.76	76.20 3.25	76.20 4.88	10d
82.55 3.76	82.55 3.25	82.55 4.88	12d
88.90 4.11	88.90 3.43	88.90 5.26	16d
101.60 4.88	101.60 3.76	101.60 5.72	20d
114.30 5.26	114.30 3.76	114.30 6.20	30d
127.00 5.72	127.00 4.11	127.00 6.68	40d
_____	_____	139.70 7.19	50d
_____	_____	152.40 7.19	60d

SUBSTITUTION TABLE FOR IRRIGATION COMPONENTS

METRIC WATER METERS, TRUCK LOADING STANDPIPES, VALVES, BACKFLOW PREVENTERS, FLOW SENSORS, WYE STRAINERS, FILTER ASSEMBLY UNITS, PIPE SUPPLY LINES, AND PIPE IRRIGATION SUPPLY LINES SHOWN ON THE PLANS DIAMETER NOMINAL (DN) mm	NOMINAL SIZE TO BE SUBSTITUTED inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

Unless otherwise specified, substitutions of United States Standard Measures standard structural shapes corresponding to the metric designations shown on the plans and in conformance with the requirements in ASTM Designation: A 6/A 6M, Annex 2, will be allowed.

8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS

The Department maintains the following list of Prequalified and Tested Signing and Delineation Materials. The Engineer shall not be precluded from sampling and testing products on the list of Prequalified and Tested Signing and Delineation Materials.

The manufacturer of products on the list of Prequalified and Tested Signing and Delineation Materials shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

For those categories of materials included on the list of Prequalified and Tested Signing and Delineation Materials, only those products shown within the listing may be used in the work. Other categories of products, not included on the list of Prequalified and Tested Signing and Delineation Materials, may be used in the work provided they conform to the requirements of the Standard Specifications.

Materials and products may be added to the list of Prequalified and Tested Signing and Delineation Materials if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

PAVEMENT MARKERS, PERMANENT TYPE

Retroreflective With Abrasion Resistant Surface (ARS)

A. Apex, Model 921AR (100 mm x 100 mm)

B. Avery Dennison (formerly Stimsonite), Models C88 (100 mm x 100 mm), 911 (100 mm x 100 mm) and 953 (70 mm x 114 mm)
C. Ray-O-Lite, Model "AA" ARS (100 mm x 100 mm)
D. 3M Series 290 (89 mm x 100 mm)
E. 3M Series 290 PSA, with pressure sensitive adhesive pad (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

(for recessed applications only)

A. Avery Dennison (formerly Stimsonite), Model 948 (58 mm x 119 mm)
B. Avery Dennison (formerly Stimsonite), Model 944SB (51 mm x 100 mm)*
C. Ray-O-Lite, Model 2002 (58 mm x 117 mm)
D. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)*
*For use only in 114 mm wide (older) recessed slots

Non-Reflective, 100 mm Round

A. Alpine Products, "D-Dot" and "ANR" (ABS)
B. Apex Universal (Ceramic)
C. Apex Universal, Models 929 (ABS) and 929PP (Polypropylene)
D. Elgin Molded Plastics, "Empco-Lite" Model 900 (ABS)
E. Glowlite (Ceramic)
F. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
G. Interstate Sales, "Diamond Back" (ABS) and (Polypropylene)
H. Novabrite Models Cdot (White) Cdot-y (Yellow), Ceramic
I. Novabrite Models Adot-w (White) Adot-y (Yellow), (ABS)
J. Novabrite Models Pdot-w (White) Pdot-y (Yellow), Polypropylene
K. Road Creations, Model RCB4NR (Acrylic)
L. Three D Traffic Works TD10000 (ABS), TD10500 (Polypropylene)
M. Zumar Industries, "Titan TM40A" (ABS)

PAVEMENT MARKERS, TEMPORARY TYPE

Temporary Markers For Long Term Day/Night Use (6 months or less)

A. Apex Universal, Model 924 (100 mm x 100 mm)
B. Elgin Molded Plastics, "Empco-Lite" Model 901 (100 mm x 100 mm)
C. Road Creations, Model R41C (100 mm x 100 mm)
D. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

Temporary Markers For Short Term Day/Night Use (14 days or less)

(For seal coat or chip seal applications, clear protective covers are required)

A. Apex Universal, Model 932
B. Bunzl Extrusion, Models T.O.M., T.R.P.M., and "HH" (High Heat)
C. Hi-Way Safety, Inc., Model 1280/1281

STRIPING AND PAVEMENT MARKING MATERIAL

Permanent Traffic Striping and Pavement Marking Tape

A. Advanced Traffic Marking, Series 300 and 400
B. Brite-Line, Series 1000
C. Brite-Line, "DeltaLine XRP"
D. Swarco Industries, "Director 35" (For transverse application only)
E. Swarco Industries, "Director 60"
F. 3M, "Stamark" Series 380 and 5730
G. 3M, "Stamark" Series 420 (For transverse application only)

Temporary (Removable) Striping and Pavement Marking Tape (6 months or less)

A. Advanced Traffic Marking, Series 200
B. Brite-Line, Series 100
C. Garlock Rubber Technologies, Series 2000

D. P.B. Laminations, Aztec, Grade 102
E. Swarco Industries, "Director-2"
F. Trelleborg Industri, R140 Series
G. 3M, Series 620 "CR", and Series A750
H. 3M, Series A145, Removable Black Line Mask
(Black Tape: for use only on Asphalt Concrete Surfaces)
I. Advanced Traffic Marking Black "Hide-A-Line"
(Black Tape: for use only on Asphalt Concrete Surfaces)
J. Brite-Line "BTR" Black Removable Tape
(Black Tape: for use only on Asphalt Concrete Surfaces)
K. Trelleborg Industri, RB-140
(Black Tape: for use only on Asphalt Concrete Surfaces)

Preformed Thermoplastic (Heated in place)

A. Avery Dennison, "Hotape"
B. Flint Trading, "Premark," "Premark 20/20 Flex," and "Premark 20/20 Flex Plus"

Ceramic Surfacing Laminate, 150 mm x 150 mm

A. Safeline Industries/Highway Ceramics, Inc.

CLASS 1 DELINEATORS

One Piece Driveable Flexible Type, 1700 mm

A. Bunzl Extrusion, "Flexi-Guide Models 400 and 566"
B. Carsonite, Curve-Flex CFRM-400
C. Carsonite, Roadmarker CRM-375
D. FlexStake, Model 654 TM
E. GreenLine Models HWD1-66 and CGD1-66
F. J. Miller Industries, Model JMI-375 (with soil anchor)

Special Use Type, 1700 mm

A. Bunzl Extrusion, Model FG 560 (with 450 mm U-Channel base)
B. Carsonite, "Survivor" (with 450 mm U-Channel base)
C. Carsonite, Roadmarker CRM-375 (with 450 mm U-Channel base)
D. FlexStake, Model 604
E. GreenLine Models HWDU and CGD (with 450 mm U-Channel base)
F. Impact Recovery Model D36, with #105 Driveable Base
G. Safe-Hit with 200 mm pavement anchor (SH248-GP1)
H. Safe-Hit with 380 mm soil anchor (SH248-GP2) and with 450 mm soil anchor (SH248-GP3)

Surface Mount Type, 1200 mm

A. Bent Manufacturing Company, Masterflex Model MF-180EX-48
B. Carsonite, "Super Duck II"
C. FlexStake, Surface Mount, Models 704 and 754 TM
D. Impact Recovery Model D48, with #101 Fixed (Surface-Mount) Base
E. Three D Traffic Works "Channelflex" ID No. 522248W

CHANNELIZERS

Surface Mount Type, 900 mm

A. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
B. Bunzl Extrusion, Flexi-Guide Models FG300LD and FG300UR
C. Carsonite, "Super Duck" (Flat SDF-436, Round SDR-336)
D. Carsonite, "Super Duck II" Model SDCF203601MB "The Channelizer"
E. FlexStake, Surface Mount, Models 703 and 753 TM
F. GreenLine, Model SMD-36
G. Hi-Way Safety, Inc. "Channel Guide Channelizer" Model CGC36
H. Impact Recovery Model D36, with #101 Fixed (Surface-Mount) Base

I. Repo, Models 300 and 400
J. Safe-Hit, Guide Post, Model SH236SMA
K. The Line Connection, "Dura-Post" Model DP36-3 (Permanent)
L. The Line Connection, "Dura-Post" Model DP36-3C (Temporary)
M. Three D Traffic Works "Channelflex" ID No. 522053W

Lane Separation System

A. Bunzl "Flexi-Guide (FG) 300 Curb System"
B. Qwick Kurb, "Klemmfix Guide System"
C. Recycled Technology, Inc. "Safe-Lane System"

CONICAL DELINEATORS, 1070 mm

(For 700 mm Traffic Cones, see Standard Specifications)
A. Bent Manufacturing Company "T-Top"
B. Plastic Safety Systems "Navigator-42"
C. Radiator Specialty Company "Enforcer"
D. Roadmaker Company "Stacker"
E. TrafFix Devices "Grabber"
F. Three D Traffic Works "Ringtop" TD7000, ID No. 742143

OBJECT MARKERS

Type "K", 450 mm

A. Bunzl, Model FG318PE
B. Carsonite, Model SMD 615
C. FlexStake, Model 701 KM
D. Repo, Models 300 and 400
E. Safe-Hit, Model SH718SMA
F. The Line Connection, Model DP21-4K

Type "K-4" / "Q" Object Markers, 600 mm

A. Bent Manufacturing "Masterflex" Model MF-360-24
B. Bunzl Extrusion, Model FG324PE
C. Carsonite, Super Duck II
D. FlexStake, Model 701KM
E. Repo, Models 300 and 400
F. Safe-Hit, Models SH8 24SMA_WA and SH8 24GP3_WA
G. The Line Connection, Model DP21-4Q
H. Three D Traffic Works "Q" Marker, ID No. 531702W

CONCRETE BARRIER MARKERS AND
TEMPORARY RAILING (TYPE K) REFLECTORS

Impactable Type

A. ARTUK, "FB"
B. Bunzl Extrusion, Models PCBM-12 and PCBM-T12
C. Duraflex Corp., "Flexx 2020" and "Electriflexx"
D. Hi-Way Safety, Inc., Model GMKRM100
E. Plastic Safety Systems "BAM" Models OM-BARR and OM-BWAR
F. Sun-Lab Technology, "Safety Guide Light Model TM-5"
G. Three D Traffic Works "Roadguide" 9304 Series, ID No. 903176 (One-Way), ID No. 903215 (Two-Way)

Non-Impactable Type

A. ARTUK, JD Series
B. Plastic Safety Systems "BAM" Models OM-BITARW and OM-BITARA
C. Vega Molded Products, Models GBM and JD

METAL BEAM GUARD RAIL POST MARKERS

(For use to the left of traffic)

A. Bunzl Extrusion, "Mini" (75 mm x 254 mm)
B. Creative Building Products, "Dura-Bull, Model 11201"
C. Duraflex Corp., "Railrider"

CONCRETE BARRIER DELINEATORS, 400 mm

(For use to the right of traffic)

A. Bunzl Extrusion, Model PCBM T-16
B. Safe-Hit, Model SH216RBM
C. Sun-Lab Technology, "Safety Guide Light, Model TM16," (75 mm x 300 mm)
D. Three D Traffic Works "Roadguide" ID No. 904364 (White), ID No. 904390 (Yellow)

CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)

A. Stinson Equipment Company "SaddleMarker"

SOUND WALL DELINEATOR

(Applied vertically. Place top of 75 mm x 300 mm reflective element at 1200 mm above roadway)

A. Bunzl Extrusion, PCBM S-36
B. Sun-Lab Technology, "Safety Guide Light, Model SM12," (75 mm x 300 mm)

GUARD RAILING DELINEATOR

(Place top of reflective element at 1200 mm above plane of roadway)

Wood Post Type, 686 mm

A. Bunzl Extrusion, FG 427 and FG 527
B. Carsonite, Model 427
C. FlexStake, Model 102 GR
D. GreenLine GRD 27
E. J. Miller Model JMI-375G
F. Safe-Hit, Model SH227GRD
G. Three D Traffic Works "Guardflex" TD9100 Series, ID No. 510476

Steel Post Type

A. Carsonite, Model CFGR-327 with CFGRBK300 Mounting Bracket

RETROREFLECTIVE SHEETING

Channelizers, Barrier Markers, and Delineators

A. Avery Dennison T-6500 Series (Formerly Stimsonite, Series 6200) (For rigid substrate devices only)
B. Avery Dennison WR-6100 Series
C. Nippon Carbide, Flexible Ultralite Grade (ULG) II
D. Reflexite, PC-1000 Metalized Polycarbonate
E. Reflexite, AC-1000 Acrylic
F. Reflexite, AP-1000 Metalized Polyester
G. Reflexite, Conformalight, AR-1000 Abrasion Resistant Coating
H. 3M, High Intensity

Traffic Cones, 330 mm Sleeves

A. Reflexite SB (Polyester), Vinyl or "TR" (Semi-transparent)

Traffic Cones, 100 mm and 150 mm Sleeves

A. Nippon Carbide, Flexible Ultralite Grade (ULG) II
B. Reflexite, Vinyl, "TR" (Semi-transparent) or "Conformalight"
C. 3M Series 3840

Barrels and Drums

A. Avery Dennison WR-6100
B. Nippon Carbide, Flexible Ultralite Grade (ULG) II
C. Reflexite, "Conformalight", "Super High Intensity" or "High Impact Drum Sheeting"
D. 3M Series 3810

Barricades: Type I, Medium-Intensity (Typically Enclosed Lens, Glass-Bead Element)

A. American Decal, Adcolite
B. Avery Dennison, T-1500 and T-1600 series
C. 3M Engineer Grade, Series 3170

Barricades: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)

A. Avery Dennison, T-2500 Series
B. Kiwalite Type II
C. Nikkalite 1800 Series

Signs: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)

A. Avery Dennison, T-2500 Series
B. Kiwalite, Type II
C. Nikkalite 1800 Series

Signs: Type III, High-Intensity (Typically Encapsulated Glass-Bead Element)

A. Avery Dennison, T-5500 and T-5500A Series
B. Nippon Carbide, Nikkalite Brand Ultralite Grade II
C. 3M Series 3870

Signs: Type IV, High-Intensity (Typically Unmetallized Microprismatic Element)

A. Avery Dennison, T-6500 Series (Formerly Stimsonite Series 6200)
B. Nippon Carbide, Crystal Grade, 94000 Series

Signs: Type VI, Elastomeric (Roll-Up) High-Intensity, without Adhesive

A. Avery Dennison, WU-6014
B. Novabrite LLC, "Econobrite"
C. Reflexite "Vinyl"
D. Reflexite "SuperBright"
E. Reflexite "Marathon"
F. 3M Series RS34 (Orange) and RS20 (Fluorescent orange)

Signs: Type VII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)

A. 3M LDP Series 3924 (Fluorescent Red/Orange)
B. 3M LDP Series 3970

Signs: Type VIII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)

A. Avery Dennison, T-7500 Series

Signs: Type IX, Very-High-Intensity (Typically Unmetallized Microprismatic Element)

A. 3M VIP Series 3981 Diamond Grade (Fluorescent yellow)
B. 3M VIP Series 3983 Diamond Grade (Fluorescent yellow/Green)
C. 3M VIP Series 3990 Diamond

SPECIALTY SIGNS

A. All Sign Products, STOP Sign (All Plastic), 750 mm
B. Relexite "Endurance" Work Zone Sign (with Semi-Rigid Plastic Substrate)

SIGN SUBSTRATE

Fiberglass Reinforced Plastic (FRP)

A. Fiber-Brite
B. Sequentia, "Polyplate"
C. Inteplast Group "InteCel" (13 mm for Post-Mounted CZ Signs, 1200 mm or less)

Aluminum Composite

A. Alcan Composites "Dibond Material, 2 mm" (for temporary construction signs only)
B. Mitsubishi Chemical America, Alpolic 350 (for temporary construction signs only)

8-1.03 STATE-FURNISHED MATERIALS

Attention is directed to Section 6-1.02, "State-Furnished Materials," of the Standard Specifications and these special provisions.

The following materials will be furnished to the Contractor:

A. Sign panels for roadside signs and overhead sign structures.
B. Sign overlay panels for roadside signs and overhead sign structures.
C. Route shields for funding signs
D. Hardware for mounting sign panels as follows:

    1. Blind rivets for mounting overlapping legend at sign panel joints.
    2. Closure inserts.
    3. Aluminum bolts, nuts, and washers for mounting overhead formed panels.

E. Padlocks for backflow preventer assembly enclosures, backflow preventer assembly blankets, walk gates, service cabinets, service equipment enclosure and other cabinets.
F. Marker panels, including reflectors, for Type P, and Type R object markers.
G. Lamps for “Meter On” signs.
H. Loop detector unit sensors.
I. Wiring diagrams for the controller cabinets.
J. Light Emitting Diode modules and lamps for vehicle signal assembles
K. Light Emitting Diode and lamps for Type A pedestrian signal assemblies
L. Reflectors and adhesives for temporary railing (Type K)

Sign panels and overlay panels will be furnished to the Contractor at the District Warehouse located adjacent to the San Francisco – Oakland Bay Bridge Toll Plaza.

The Contractor shall notify the District Warehouse Manager, Telephone 510-286-6100 and the Engineer not less than 48 hours before State-furnished material is to be picked up by the Contractor. A full description of the material and the time the material will be picked up shall be provided. The number, type, and size of the sign panels, and the contract number shall also be provided to the District Warehouse Manager.

Contractor shall submit written request to the Engineer of sign panels at least 90 working days prior to its intended use.

8-1.04 ADHESIVE FOR BONDING REFLEX REFLECTORS TO PORCELAIN ENAMEL TRAFFIC SIGNS

Adhesive shall be an RTV (room temperature vulcanizing) one-component silicone - rubber adhesive. Adhesive shall be compounded to be highly resistant to ozone, ultraviolet light, and extremes of ambient temperature, shall possess good chemical resistance, and shall exhibit excellent overall weatherability. The cured material shall remain flexible and maintain its adhesive qualities indefinitely.

The adhesive shall possess the following physical properties:

Property	Value	Test Method
Color	Translucent	Visual Determination
Consistency	Soft, spreadable thixotropic paste	Visual Determination
Tack-Free Time	One hour maximum	Finger-touch test
Durometer, Shore A	25-40	ASTM Designation: D 2240(1)
Tensile Strength, MPa	2.1 minimum	ASTM Designation: D 412(1)
Elongation, Percent	350 minimum	ASTM Designation: D 412(1)
Specific Gravity	1.07±0.02	ASTM Designation: D 792, Method A-1, Notes: (1) and (2)
Shear-Adhesion, MPa	1.0 minimum	Note: (3)

Notes:

(1) After specimen has cured for a total of 48 hours.
(2) 25-mm square specimen.
(3) Test method on file and available at the Transportation Laboratory.

When stored at temperatures below 27°C, the adhesive shall have a shelf life of at least one year.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for each lot of adhesive supplied.

8-1.05 ENGINEERING FABRICS

Engineering fabrics shall conform to the provisions in Section 88, "Engineering Fabrics," of the Standard Specifications and these special provisions.

Filter fabric for this project shall be ultraviolet (UV) ray protected.

SECTION 8-2. CONCRETE

8-2.01 PORTLAND CEMENT CONCRETE

Portland cement concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

References to Section 90-2.01, "Portland Cement," of the Standard Specifications shall mean Section 90-2.01, "Cement," of the Standard Specifications.

Mineral admixture shall be combined with cement in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures," of the Standard Specifications for the concrete materials specified in Section 56-2, "Roadside Signs," of the Standard Specifications.

The requirements of Section 90-4.08, "Required Use of Mineral Admixture," of the Standard Specifications shall not apply to Section 19-3.025C, "Soil Cement Bedding," of the Standard Specifications.

The Department maintains a list of sources of fine and coarse aggregate that have been approved for use with a reduced amount of mineral admixture in the total amount of cementitious material to be used. A source of aggregate will be considered for addition to the approved list if the producer of the aggregate submits to the Transportation Laboratory certified test results from a qualified testing laboratory that verify the aggregate complies with the requirements. Prior to starting the testing, the aggregate test shall be registered with the Department. A registration number can be obtained by calling (916) 227-7228. The registration number shall be used as the identification for the aggregate sample in correspondence with the Department. Upon request, a split of the tested sample shall be provided to the Department. Approval of aggregate will depend upon compliance with the specifications, based on the certified test results submitted, together with any replicate testing the Department may elect to perform. Approval will expire 3 years from the date the most recent registered and evaluated sample was collected from the aggregate source.

Qualified testing laboratories shall conform to the following requirements:

A. Laboratories performing ASTM Designation: C 1293 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Concrete Proficiency Sample Program and shall have received a score of 3 or better on all tests of the previous 2 sets of concrete samples.
B. Laboratories performing ASTM Designation: C 1260 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Pozzolan Proficiency Sample Program and shall have received a score of 3 or better on the shrinkage and soundness tests of the previous 2 sets of pozzolan samples.

Aggregates on the list shall conform to one of the following requirements:

A. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1293, the average expansion at one year shall be less than or equal to 0.040 percent; or
B. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1260, the average of the expansion at 16 days shall be less than or equal to 0.15 percent.

The amounts of cement and mineral admixture used in cementitious material shall be sufficient to satisfy the minimum cementitious material content requirements specified in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," of the Standard Specifications and shall conform to the following:

A. The minimum amount of cement shall not be less than 75 percent by mass of the specified minimum cementitious material content.
B. The minimum amount of mineral admixture to be combined with cement shall be determined using one of the following criteria:

    1. When the calcium oxide content of a mineral admixture is equal to or less than 2 percent by mass, the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix.
    2. When the calcium oxide content of a mineral admixture is greater than 2 percent by mass, and any of the aggregates used are not listed on the approved list as specified in these special provisions, then the amount of mineral admixture shall not be less than 25 percent by mass of the total amount of cementitious material to be used in the mix.
    3. When the calcium oxide content of a mineral admixture is greater than 2 percent by mass and the fine and coarse aggregates are listed on the approved list as specified in these special provisions, then the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix.
    4. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," of the Standard Specifications is used, the amount of mineral admixture shall not be less than 10 percent by mass of the total amount of cementitious material to be used in the mix.
    5. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," of the Standard Specifications is used and the fine and coarse aggregates are listed on the approved list as specified in these special provisions, then the amount of mineral admixture shall not be less than 7 percent by mass of the total amount of cementitious material to be used in the mix.

C. The total amount of mineral admixture shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. Where Section 90-1.01, "Description," of the Standard Specifications specifies a maximum cementitious content in kilograms per cubic meter, the total mass of cement and mineral admixture per cubic meter shall not exceed the specified maximum cementitious material content.

Unless otherwise specified, mineral admixture will not be required in portland cement concrete used for precast concrete girders.

The Contractor will be permitted to use Type III portland cement for concrete used in the manufacture of precast concrete members.

8-2.02 PRECAST CONCRETE QUALITY CONTROL

GENERAL

Precast concrete quality control shall conform to these special provisions.

Unless otherwise specified, precast concrete quality control shall apply when any precast concrete members are fabricated in conformance with the provisions in Section 49, "Piling," or Section 51, "Concrete Structures," of the Standard Specifications.

Quality Control (QC) shall be the responsibility of the Contractor. The Contractor's QC inspectors shall perform inspection and testing prior to precasting, during precasting, and after precasting, and as specified in this section and additionally as necessary to ensure that materials and workmanship conform to the details shown on the plans and specifications.

Quality Assurance (QA) is the prerogative of the Engineer. Regardless of the acceptance for a given precast element by the Contractor, the Engineer will evaluate the precast element. The Engineer will reject any precast element that does not conform to the approved Precast Concrete Quality Control Plan (PCQCP), the details shown on the plans, and these special provisions.

The Contractor shall designate in writing a precast Quality Control Manager (QCM) for each precasting facility. The QCM shall be responsible directly to the Contractor for the quality of precasting, including materials and workmanship, performed by the Contractor and all subcontractors. The QCM shall be the sole individual responsible to the Contractor for submitting, receiving, and approving all correspondence, required submittals, and reports to and from the Engineer. The QCM shall not be employed or compensated by any subcontractor, or other persons or entities hired by subcontractors, or suppliers, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

Prior to submitting the PCQCP required herein, a meeting between the Engineer, the Contractor's QCM, and a representative from each entity performing precast concrete operations for this project, shall be held to discuss the requirements for precast quality control.

QC Inspectors shall either be 1) licensed as Civil Engineers in the State of California, or 2) have a current Plant Quality Personnel Certification, Level II, from the Precast/Prestressed Concrete Institute. A QC Inspector shall witness all precast concrete operations.

PRECAST CONCRETE QUALIFICATION AUDIT

Unless otherwise specified, no Contractors or subcontractors performing precast concrete operations for the project shall commence work without having successfully completed the Department's Precast Fabrication Qualification Audit, hereinafter referred to as the audit. The Engineer will perform the audit, and copies of the audit form, along with procedures for requesting and completing the audit, are available at the Transportation Laboratory or the following website:

http://www.dot.ca.gov/hq/esc/Translab/smbresources.htm

An audit that was previously approved by the Engineer no more than three years prior to the beginning of work on this contract will be acceptable for the entire period of this contract, provided the Engineer determines the audit is for the same type of work that is to be performed on this contract.

Successful completion of an audit shall not relieve the Contractor of the responsibility for furnishing materials or producing finished work of the quality specified in these special provisions and as shown on the plans.

PRECAST CONCRETE QUALITY CONTROL PLAN

Prior to performing any precasting operations, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate PCQCP for each item of work which is to be precast. A separate PCQCP shall be submitted for each facility. As a minimum, each PCQCP shall include the following:

A. The name of the precasting firm, the concrete plants to be used, and any concrete testing firm to be used;
B. A manual prepared by the precasting firm that includes equipment, testing procedures, safety plan, and the names, qualifications, and documentation of certifications for all personnel to be used;
C. The name of the QCM and the names, qualifications, and documentation of certifications for all QC inspection personnel to be used;
D. An organizational chart showing all QC personnel and their assigned QC responsibilities;
E. The methods and frequencies for performing all required quality control procedures, including all inspections, material testing, and any required survey procedures for all components of the precast elements including prestressing systems, concrete, grout, reinforcement, steel components embedded or attached to the precast member, miscellaneous metal, and formwork;
F. A system for identification and tracking of required precast element repairs, and a procedure for the re-inspection of any repaired precast element. The system shall have provisions for a method of reporting nonconforming precast elements to the Engineer; and
G. Forms to be used for Certificates of Compliance, daily production logs, and daily reports.

The Engineer shall have 4 weeks to review the PCQCP submittal after a complete plan has been received. No precasting shall be performed until the PCQCP is approved in writing by the Engineer.

A PCQCP that was previously approved by the Engineer no more than one year prior to the beginning of work on this contract will be acceptable for the entire period of this contract, provided the Engineer determines the PCQCP is for the same type of work that is to be performed on this contract.

An amended PCQCP or addendum shall be submitted to, and approved in writing by the Engineer, for any proposed revisions to the approved PCQCP. An amended PCQCP or addendum will be required for any revisions to the PCQCP, including but not limited to changes in concrete plants or source materials, changes in material testing procedures and testing labs, changes in procedures and equipment, changes in QC personnel, or updated systems for tracking and identifying precast elements. The Engineer shall have 2 weeks to complete the review of the amended PCQCP or addendum, once a complete

submittal has been received. Work that is affected by any of the proposed revisions shall not be performed until the amended PCQCP or addendum has been approved.

After final approval of the PCQCP, amended PCQCP, or addendum, the Contractor shall submit 7 copies to the Engineer of each of these approved documents.

It is expressly understood that the Engineer's approval of the Contractor's PCQCP shall not relieve the Contractor of any responsibility under the contract for the successful completion of the work in conformance with the requirements of the plans and specifications. The Engineer's approval shall neither constitute a waiver of any of the requirements of the plans and specifications nor relieve the Contractor of any obligation thereunder, and defective work, materials, and equipment may be rejected notwithstanding approval of the PCQCP.

REPORTING

The QC Inspector shall provide reports to the QCM on a daily basis for each day that precasting operations are performed.

A daily production log for precasting shall be kept by the QCM for each day that precasting operations, including setting forms, placing reinforcement, setting prestressing steel, casting, curing, post tensioning, and form release, are performed. The log shall include the facility location, and shall include specific description of casting or related operations, any problems or deficiencies discovered, any testing or repair work performed, and the names of all QC personnel and the specific QC inspections they performed that day. The daily report from each QC Inspector shall also be included in the log. This daily log shall be available for viewing by the Engineer, at the precasting facility.

All reports regarding material tests and any required survey checks shall be signed by the person that performed the test or check, and then submitted directly to the QCM for review and signature prior to submittal to the Engineer. Corresponding names shall be clearly printed or typewritten next to all signatures.

The Engineer shall be notified immediately in writing when any precasting problems or deficiencies are discovered and also of the proposed repair or process changes required to correct them. The Engineer shall have 4 weeks to review these procedures. No remedial work shall begin until the Engineer approves these procedures in writing.

The following items shall be included in a Precast Report that is to be submitted to the Engineer following the completion of any precast element:

A. Reports of all material tests and any required survey checks;
B. Documentation that the Contractor has evaluated all tests and corrected all rejected deficiencies, and all repairs have been re-examined with the required tests and found acceptable; and
C. Daily production log.

At the completion of any precast element, and if the QCM determines that element is in conformance with these special provisions, the QCM shall sign and furnish to the Engineer, a certificate of compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. This certificate of compliance shall be submitted with the Precast Report. The certificate shall state that all of the materials and workmanship incorporated in the work, and all required tests and inspections of this work, have been performed in conformance with the details shown on the plans and the provisions of the Standard Specifications and these special provisions.

PAYMENT

In the event the Engineer fails to complete the review of 1) a PCQCP, 2) an amended PCQCP or addendum, or 3) a proposed repair or process change, within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

All required repair work or process changes required to correct precasting operation deficiencies, whether discovered by the QCM, QC Inspector, or by the Engineer, and any associated delays or expenses to the Contractor caused by performing these repairs, shall be at the Contractor's expense.

Full compensation for conforming to the requirements of this section shall be considered as included in the contract prices paid for the various items of work involved, and no additional compensation will be allowed therefor.

SECTION 8-3. WELDING

8-3.01 WELDING

GENERAL

Flux core welding electrodes conforming to the requirements of AWS A5.20 E6XT-4 or E7XT-4 shall not be used to perform welding for this project.

Wherever reference is made to the following AWS welding codes in the Standard Specifications, on the plans, or in these special provisions, the year of adoption for these codes shall be as listed:

AWS Code	Year of Adoption
D1.1	2002
D1.4	1998
D1.5	2002
D1.6	1999

Requirements of the AWS welding codes shall apply unless specified otherwise in the Standard Specifications, on the plans, or in these special provisions. Wherever the abbreviation AWS is used, it shall be equivalent to the abbreviations ANSI/AWS or AASHTO/AWS.

Section 6.1.1.1 of AWS D1.5 is replaced with the following:

Quality Control (QC) shall be the responsibility of the Contractor. As a minimum, the Contractor shall perform inspection and testing of each weld joint prior to welding, during welding, and after welding as specified in this section and as necessary to ensure that materials and workmanship conform to the requirements of the contract documents.

Sections 6.1.3 through 6.1.4.3 of AWS D1.1, Section 7.1.2 of AWS D1.4, and Sections 6.1.1.2 through 6.1.3.3 of AWS D1.5 are replaced with the following:

The QC Inspector shall be the duly designated person who acts for and on behalf of the Contractor for inspection, testing, and quality related matters for all welding.

Quality Assurance (QA) is the prerogative of the Engineer. The QA Inspector is the duly designated person who acts for and on behalf of the Engineer.

The QC Inspector shall be responsible for quality control acceptance or rejection of materials and workmanship, and shall be currently certified as an AWS Certified Welding Inspector (CWI) in conformance with the requirements in AWS QC1, " Standard for AWS Certification of Welding Inspectors."

The QC Inspector may be assisted by an Assistant QC Inspector provided that this individual is currently certified as an AWS Certified Associate Welding Inspector (CAWI) in conformance with the requirements in AWS QC1, "Standard for AWS Certification of Welding Inspectors." The Assistant QC Inspector may perform inspection under the direct supervision of the QC Inspector provided the Assistant is always within visible and audible range of the QC Inspector. The QC Inspector shall be responsible for signing all reports and for determining if welded materials conform to workmanship and acceptance criteria. The ratio of QC Assistants to QC Inspectors shall not exceed 5 to 1.

When the term "Inspector" is used without further qualification, it shall refer to the QC Inspector.

Section 6.14.6, "Personnel Qualification," of AWS D1.1, Section 7.8, "Personnel Qualification," of AWS D1.4, and Section 6.1.3.4, "Personnel Qualification," of AWS D1.5 are replaced with the following:

Personnel performing nondestructive testing (NDT) shall be qualified and certified in conformance with the requirements of the American Society for Nondestructive Testing (ASNT) Recommended Practice No. SNT-TC-1A and the Written Practice of the NDT firm. The Written Practice of the NDT firm shall meet or exceed the guidelines of the ASNT Recommended Practice No. SNT-TC-1A. Individuals who perform NDT, review the results, and prepare the written reports shall be either:

A. Certified NDT Level II technicians, or;
B. Level III technicians who hold a current ASNT Level III certificate in that discipline and are authorized and certified to perform the work of Level II technicians.

Section 6.5.4 of AWS D1.5 is replaced with the following:

The QC Inspector shall inspect and approve each joint preparation, assembly practice, welding technique, joint fit-up, and the performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved Welding Procedure Specification (WPS) are met. The QC Inspector shall examine the work to

make certain that it meets the requirements of Sections 3 and 6.26. The size and contour of all welds shall be measured using suitable gages. Visual inspection for cracks in welds and base metal, and for other discontinuities should be aided by strong light magnifiers, or such other devices as may be helpful. Acceptance criteria different from those specified in this code may be used when approved by the Engineer.

Section 6.6.5, "Nonspecified NDT Other than Visual," of AWS D1.1, Section 6.6.5 of AWS D1.4 and Section 6.6.5 of AWS D1.5 shall not apply.

For any welding, the Engineer may direct the Contractor to perform NDT that is in addition to the visual inspection or NDT specified in the AWS or other specified welding codes, in the Standard Specifications, or in these special provisions. Additional NDT required by the Engineer will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. Should any welding deficiencies be discovered by this additional NDT, all costs associated with the repair of the deficient area, including NDT of the weld and of the weld repair, and any delays caused by the repair, shall be at the Contractor's expense.

Repair work to correct welding deficiencies discovered by visual inspection or NDT, or by additional NDT directed or performed by the Engineer, and any associated delays or expenses caused to the Contractor by performing these repairs, shall be at the Contractor's expense.

The Engineer shall have the authority to verify the qualifications or certifications of any welder, QC Inspector, or NDT personnel to specified levels by retests or other means approved by the Engineer.

Continuous inspection shall be provided when any welding is being performed. Continuous inspection, as a minimum, shall include having a QC Inspector within such close proximity of all welders or welding operators so that inspections by the QC Inspector of each welding operation at each welding location shall not lapse for a period exceeding 30 minutes.

Inspection and approval of all joint preparations, assembly practices, joint fit-ups, welding techniques, and the performance of each welder, welding operator, and tack welder shall be documented by the QC Inspector on a daily basis for each day welding is performed. For each inspection, including fit-up, Welding Procedure Specification (WPS) verification, and final weld inspection, the QC Inspector shall confirm and document compliance with the requirements of the AWS or other specified code criteria and the requirements of these special provisions on all welded joints before welding, during welding, and after the completion of each weld.

When joint weld details that are not prequalified to the details of Section 3 of AWS D1.1 or to the details of Figure 2.4 or 2.5 of AWS D1.5 are proposed for use in the work, the joint details, their intended locations, and the proposed welding parameters and essential variables, will be approved by the Engineer. The Engineer shall have 2 weeks to complete the review of the proposed joint detail locations. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications. Upon approval of the proposed joint detail locations and qualification of the proposed joint details, welders and welding operators using these details shall perform a qualification test plate using the WPS variables and the joint detail to be used in production. The test plate shall have the maximum thickness to be used in production and a minimum length of 180 mm and minimum finish welded width 460 mm. The test plate shall be mechanically and radiographically tested. Mechanical and radiographic testing and acceptance criteria shall be as specified in the applicable AWS codes.

In addition to the requirements specified in the applicable code, the period of effectiveness for a welder's or welding operator's qualification shall be a maximum of 3 years for the same weld process, welding position, and weld type. If production welding will be performed without gas shielding, then qualification shall also be without gas shielding. Excluding welding of fracture critical members, a valid qualification at the beginning of work on a contract will be acceptable for the entire period of the contract, as long as the welder's or welding operator's work remains satisfactory.

The Engineer will witness all qualification tests for WPSs that were not previously approved by the Department. An approved independent third party will witness the qualification tests for welders or welding operators. The independent third party shall be a current CWI and shall not be employed by the contractor performing the welding. The Engineer shall have 2 weeks to review the qualifications and copy of the current certification of the independent third party. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications. The Contractor shall notify the Engineer one week prior to performing any qualification tests. Witnessing of qualification tests by the Engineer shall not constitute approval of the intended joint locations, welding parameters, or essential variables.

In addition to the requirements of AWS D1.5 Section 5.12 or 5.13, welding procedures qualification, for work welded in conformance with that code, shall conform to the following requirements:

A. Unless considered prequalified, fillet welds, including reinforcing fillet welds, shall be qualified in each position. The fillet weld soundness test shall be conducted using the essential variables of the WPS as established by the Procedure Qualification Record (PQR.)
B. For qualification of joints that do not conform to Figures 2.4 and 2.5 of AWS D1.5, two WPS qualification tests are required. The tests conforming to AWS D1.5 Section 5.13 shall be conducted using both Figure 5.1 and Figure 5.3. The test conforming to Figure 5.3 shall be conducted using the same welding electrical parameters that were established for the test conducted conforming to Figure 5.1.
C. The travel speed, current, and voltage values that are used for tests conducted per AWS D1.5 Section 5.12 or 5.13 shall be consistent for each weld joint, and shall in no case vary by more than 10 percent for travel speed, 10 percent for current, and 7 percent for voltage.
D. For a WPS qualified in conformance with AWS D1.5 Section 5.13, the values to be used for calculating ranges for current and voltage shall be based on the average of all weld passes made in the test. Heat input shall be calculated using the average of current and voltage of all weld passes made in the test for a WPS qualified in conformance with Section 5.12 or 5.13.
E. To qualify for unlimited material thickness, two qualification tests are required for WPSs utilized for welding material thicknesses greater than 38 mm. One test shall be conducted using 20-mm thick test plates, and one test shall be conducted using test plates with a thickness between 38 mm and 50 mm. Two maximum heat input tests may be conducted for unlimited thickness qualification.
F. Macroetch tests are required for WPS qualification tests, and acceptance shall be per AWS D1.5 Section 5.19.3.
G. When a weld joint is to be made using a combination of qualified WPSs, each process shall be qualified separately.
H. When a weld joint is to be made using a combination of qualified and prequalified processes, the WPS shall reflect both processes and the limitations of essential variables, including weld bead placement, for both processes.
I. Prior to preparing mechanical test specimens, the PQR welds shall be inspected by visual and radiographic tests. Backing bar shall be 75 mm in width and shall remain in place during NDT testing. Results of the visual and radiographic tests shall comply with AWS D1.5 Section 6.26.2, excluding Section 6.26.2.2. Test plates that do not comply with both tests shall not be used.

WELDING QUALITY CONTROL

Welding quality control shall conform to the requirements in the AWS or other specified welding codes, the Standard Specifications, and these special provisions.

Unless otherwise specified, welding quality control shall apply when any work is welded in conformance with the provisions in Section 49, "Piling," Section 52, "Reinforcement," Section 55, "Steel Structures," or Section 75-1.035, "Bridge Joint Restrainer Units," of the Standard Specifications.

The welding of fracture critical members (FCMs) shall conform to the provisions specified in the Fracture Control Plan (FCP) and herein.

The Contractor shall designate in writing a welding Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for the quality of welding, including materials and workmanship, performed by the Contractor and subcontractors.

The QCM shall be the sole individual responsible to the Contractor for submitting, receiving, reviewing, and approving all correspondence, required submittals, and reports to and from the Engineer. The QCM shall be a registered professional engineer or shall be currently certified as a CWI or a CAWI.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

Welding inspection personnel or NDT firms to be used in the work shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project, except for the following conditions:

A. The work is welded in conformance with AWS D1.5 and is performed at a permanent fabrication or manufacturing facility which is certified under the AISC Quality Certification Program, Category Cbr, Major Steel Bridges and Fracture Critical endorsement F.
B. The welding is performed on pipe pile material at a permanent pipe manufacturing facility authorized to apply the American Petroleum Institute (API) monogram for API 5L pipe.

For welding performed at such facilities, the inspection personnel or NDT firms may be employed or compensated by the facility performing the welding.

Prior to submitting the Welding Quality Control Plan (WQCP) required herein, a pre-welding meeting between the Engineer, the Contractor's QCM, and a representative from each entity performing welding or inspection for this project, shall be held to discuss the requirements for the WQCP.

The Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 2 copies of a separate WQCP for each subcontractor or supplier for each item of work for which welding is to be performed.

The Contractor shall allow the Engineer 2 weeks to review the WQCP submittal after a complete plan has been received. No welding shall be performed until the WQCP is approved in writing by the Engineer. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

An amended WQCP or any addendum to the approved WQCP shall be submitted to, and approved in writing by the Engineer, for proposed revisions to the approved WQCP. An amended WQCP or addendum will be required for revisions to the WQCP, including but not limited to a revised WPS; additional welders; changes in NDT firms, QC, or NDT personnel or procedures; or updated systems for tracking and identifying welds. The Engineer shall have 1 week to complete the review of the amended WQCP or addendum. Work affected by the proposed revisions shall not be performed until the amended WQCP or addendum has been approved. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Information regarding the contents, format, and organization of a WQCP, is available at the Transportation Laboratory or the following website:

http://www.dot.ca.gov/hq/esc/Translab/smbresources.htm

After final approval of the WQCP, amended WQCP, or addendum, the Contractor shall submit 7 copies to the Engineer of the approved documents. A copy of the Engineer approved document shall be available at each location where welding is to be performed

A daily production log for welding shall be kept for each day that welding is performed. The log shall clearly indicate the locations of all welding. The log shall include the welders' names, amount of welding performed, any problems or deficiencies discovered, and any testing or repair work performed, at each location. The daily report from each QC Inspector shall also be included in the log.

The following items shall be included in a Welding Report that is to be submitted to the Engineer within 10 days following the performance of any welding:

A. Reports of all visual weld inspections and NDT.
B. Radiographs and radiographic reports, and other required NDT reports.
C. Documentation that the Contractor has evaluated all radiographs and other nondestructive tests and corrected all rejectable deficiencies, and all repaired welds have been reexamined by the required NDT and found acceptable.
D. Daily production log.

The following information shall be clearly written on the outside of radiographic envelopes: name of the QCM, name of the nondestructive testing firm, name of the radiographer, date, contract number, complete part description, and all included weld numbers or a report number, as detailed in the WQCP. In addition, all innerleaves shall have clearly written on them the part description and all included weld numbers, as detailed in the WQCP.

Reports regarding NDT shall be signed by both the NDT technician and the person that performed the review, and then submitted directly to the QCM for review and signature prior to submittal to the Engineer. Corresponding names shall be clearly printed or typewritten next to all signatures.

The Engineer will review the Welding Report to determine if the Contractor is in conformance with the WQCP. Unless otherwise specified, the Engineer shall be allowed 10 days to review the report and respond in writing after a complete Welding Report has been received. Prior to receiving notification from the Engineer of the Contractor's conformance with the WQCP, the Contractor may encase in concrete or cover welds for which a Welding Report has been submitted. However, should the Contractor elect to encase or cover those welds prior to receiving notification from the Engineer, it is expressly understood that the Contractor shall not be relieved of the responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase or cover welds pending notification by the Engineer, and in the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be

compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The QC Inspector shall provide reports to the QCM on a daily basis for each day that welding is performed.

Except for noncritical weld repairs, the Engineer shall be notified immediately in writing when welding problems, deficiencies, base metal repairs, or any other type of repairs not submitted in the WQCP are discovered, and also of the proposed repair procedures to correct them. The Contractor shall allow the Engineer one week to review these procedures. No remedial work shall begin until the repair procedures are approved in writing by the Engineer. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The QCM shall sign and furnish to the Engineer, a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each item of work for which welding was performed. The certificate shall state that all of the materials and workmanship incorporated in the work, and all required tests and inspections of this work, have been performed in conformance with the details shown on the plans, the Standard Specifications, and these special provisions.

WELDING FOR OVERHEAD SIGN AND POLE STRUCTURES

The Contractor shall meet the following requirements for any work welded in conformance with the provisions in Section 56-1, "Overhead Sign Structures," or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

Welding inspection personnel or NDT firms to be used in the work shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project, except for when the welding is performed at a permanent fabrication or manufacturing facility which is certified under the AISC Quality Certification Program, Category Sbd, Conventional Steel Building Structures.

Welding Qualification Audit

Contractors or subcontractors performing welding operations for overhead sign and pole structures shall not deliver materials to the project without having successfully completed the Department's "Manufacturing Qualification Audit for Overhead Sign and Pole Structures," hereinafter referred to as the audit, not more than one year prior to the delivery of the materials. The Engineer will perform the audit. Copies of the audit form, and procedures for requesting and completing the audit, are available at the Transportation Laboratory or the following website:

http://www.dot.ca.gov/hq/esc/Translab/smbresources.htm

An audit that was approved by the Engineer no more than one year prior to the beginning of work on this contract will be acceptable for the entire period of this contract, provided the Engineer determines the audit was for the same type of work that is to be performed on this contract.

Successful completion of an audit shall not relieve the Contractor of the responsibility for furnishing materials or producing finished work of the quality specified in these special provisions and as shown on the plans.

Welding Report

For work welded in conformance with the provisions in Section 56-1, "Overhead Sign Structures," or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, a Welding Report shall be submitted in conformance with the provisions in "Welding Quality Control," of these special provisions.

PAYMENT

Full compensation for conforming to the requirements of "Welding" shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

SECTION 9. DESCRIPTION OF BRIDGE WORK

Location A
ALMADEN ROAD UNDERCROSSING (WIDEN)
Bridge Number 37-366 R/L

A three-span cast-in-place prestressed concrete box girder structure to be widened approximately 3.5 meters (37-366 L). Three approach slabs will be replaced.

Location B
ALMA OVERHEAD (WIDEN)
Bridge Number 37-420 R/L

A three-span cast-in-place prestressed concrete box girder structure to be widened approximately 3.5 meters (37-420 L). Four approach slabs will be replaced.

Location C
ALMA AVENUE UNDERCROSSING (WIDEN)
Bridge Number 37-368 R/L

A single-span cast-in-place prestressed concrete box girder structure to be widened approximately 3.5 meters (37-368 L). Two approach slabs will be replaced.

Location D
ALMA STATION PEDESTRIAN UNDERCROSSING (WIDEN)
Bridge Number 37-434 L

A single-span cast-in-place prestressed concrete box girder structure to be widened approximately 3.5 meters. Two approach slabs will be replaced.

Location E
ALMA STATION SEPERATION (WIDEN)
Bridge Number 37-421 L

A three-span cast-in-place prestressed concrete box girder structure to be widened approximately 5.8 meters. One approach slab will be replaced.

Location F
WILLOW STREET VIADUCT (WIDEN)
Bridge Number 37-422 L

A four-span cast-in-place prestressed concrete box girder structure to be widened approximately 5.8 meters.

Location G
CURTNER AVENUE UNDERCROSSING
Bridge Number 37-362 R/L

Two approach slabs will be replaced.

Location H
CAPITOL EXPRESSWAY UNDERCROSSING
Bridge Number 37-415 R/L

Two approach slabs will be replaced.

Location I
CAPITOL EXPRESSWAY UNDERCROSSING (OFF-RAMP)
Bridge Number 37-415S

One approach slab will be replaced.

Location J
VIRGINIA STREET OVERCROSSING
Bridge Number 37-315

Slope paving portions will be replaced.

Location K
Retaining Wall No. 1

Retaining Wall portions will be replaced.

Location L
Retaining Wall No. 9

Retaining Wall portions will be replaced.

SECTION 10. CONSTRUCTION DETAILS

SECTION 10-1. GENERAL

10-1.00 CONSTRUCTION PROJECT INFORMATION SIGNS

Before any major physical construction work readily visible to highway users is started on this contract, the Contractor shall furnish and erect 2 Type 2 and 1 Type 1 Construction Project Information signs at the locations designated by the Engineer.

The signs and overlays shall be of a type and material consistent with the estimated time of completion of the project and shall conform to the details shown on the plans.

The sign letters, border and the Department's construction logos shall conform to the colors (non-reflective) and details shown on the plans, and shall be on a white background (non-reflective). The colors blue and orange shall conform to PR Color Number 3 and Number 6, respectively, as specified in the Federal Highway Administration's Color Tolerance Chart.

The sign message to be used for fund types shall consist of the following, in the order shown:

FEDERAL HIGHWAY TRUST FUNDS
STATE HIGHWAY FUNDS
SANTA CLARA COUNTY VALLEY TRANSPORTATION AUTHORITY FUNDS

The sign message to be used for type of work shall consist of the following:

HIGHWAY CONSTRUCTION

The sign message to be used for the Year of Completion of Project Construction will be furnished by the Engineer. The Contractor shall furnish and install the "Year" sign overlay within 10 working days of notification of the year date to be used.

The letter sizes to be used shall be as shown on the plans. The information shown on the signs shall be limited to that shown on the plans.

The signs shall be kept clean and in good repair by the Contractor.

Upon completion of the work, the signs shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications.

Full compensation for furnishing, erecting, maintaining, and removing and disposing of the construction project information signs shall be considered as included in the contract lump sum price paid for construction area signs and no additional compensation will be allowed therefor.

10-1.01 ORDER OF WORK

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

The work in Stages 1A (Phase 1) and Stage 1A (Phase 2) shall be completed by 120 working days.

The Contractor shall submit a progress schedule in conformance with the provisions in “Progress Schedule (Critical Path)” elsewhere in these special provisions showing work in Stages 1A (Phase 1), Stage 2A and Stage 3A occurring simultaneously.

Work requiring the continuous closure of the bike path closure shall be completed within 40 working days after beginning of bike path closure. The bike path closure shall occur between December 1 and March 31. The Contractor shall submit a progress schedule in conformance with the provisions in “Progress Schedule (Critical Path)” elsewhere in these special provisions that shows bike path work in conformance to the requirements of this section.

Compaction grouting shall be completed before roadway excavation begins.

All work within the Guadalupe River shall be confined to the period between June 1st and October 15th.

The Contractor shall notify 24 hours in advance of starting, resuming, or changing scheduled work within the City of San Jose right-of-way to (a) City of San Jose Engineering Services Division-Inspection at (408) 998-6090, (b) Santa Clara County Transit, if bus stops will be blocked at (408) 321-7000, (c) City of San Jose Communications for any detours and closures at (408) 277-8900

Attention is directed to "Slope Paving" of these special provisions regarding constructing a 1.2 m by 1.8 m test panel prior to placing the permanent slope paving, and slope paving (Precast panel).

Temporary railing (Type K) and temporary crash cushions shall be secured in place prior to commencing work for which the temporary railing and crash cushions are required.

Attention is directed to "Concrete Pavement" of these special provisions in regards to furnishing tests and mix proportions for concrete to be used in concrete pavement, providing Pre-Paving Conference and the Just-In-Time Training prior to commencing pavement operations.

Attention is directed to "Environmentally Sensitive Area" and "Temporary Fence (Type ESA)" of these special provisions. Prior to beginning work, the boundaries of the Environmentally Sensitive Areas (ESA) shall be clearly delineated in the field. The boundaries shall be delineated by the installation of temporary fence (Type ESA).

Attention is directed to "Water Pollution Control" of these special provisions regarding the submittal and approval of the Storm Water Pollution Prevention Plan prior to performing work having potential to cause water pollution.

The first order of work shall be to place the order for the traffic signal equipment.

The uppermost layer of new pavement shall not be placed until all underlying conduits and loop detectors have been installed.

Prior to commencement of the traffic signal functional test at any location, all items of work related to signal control shall be completed and all roadside signs, pavement delineation, and pavement markings shall be in place at that location.

No overhead sign panel shall be installed until the overhead sign lighting is completely operational.

No above ground electrical work shall be performed on any system within the project site until all Contractor-furnished electrical materials for that individual system have been tested and delivered to the Contractor.

Attention is directed to "Maintaining Traffic" and "Temporary Pavement Delineation" of these special provisions and to the stage construction and traffic handling sheets of the plans.

Attention is directed to "Progress Schedule (Critical Path Method)" of these special provisions regarding the submittal of a general time-scaled logic diagram within 10 days after approval of the contract. The diagram shall be submitted prior to performing any work that may be affected by any proposed deviations to the construction staging of the project.

The work shall be performed in conformance with the stages of construction shown on the plans. Nonconflicting work in subsequent stages may proceed concurrently with work in preceding stages, provided satisfactory progress is maintained in the preceding stages of construction.

Existing soundwalls shall not be removed until new soundwalls have been constructed as shown on the plans and the existing soundwalls are no longer required, unless directed by the Engineer.

In each stage, after completion of the preceding stage, the first order of work shall be the removal of existing pavement delineation as directed by the Engineer. Pavement delineation removal shall be coordinated with new delineation so that lane lines are provided at all times on traveled ways open to public traffic.

Before obliterating any pavement delineation (traffic stripes, pavement markings, and pavement markers) that is to be replaced on the same alignment and location, as determined by the Engineer, the pavement delineation shall be referenced by the Contractor, with a sufficient number of control points to reestablish the alignment and location of the new pavement delineation. The references shall include the limits or changes in striping pattern, including one- and 2-way barrier lines, limit lines, crosswalks and other pavement markings. Full compensation for referencing existing pavement delineation shall be considered as included in the contract prices paid for new pavement delineation and no additional compensation will be allowed therefor.

At those locations exposed to public traffic where guard railings or are to be constructed, or removed, the Contractor shall schedule operations so that at the end of each working day there shall be no post holes open nor shall there be any railing posts installed without the blocks and rail elements assembled and mounted thereon.

.Not less than 60 days prior to applying seeds, the Contractor shall furnish the Engineer a statement from the vendor that the order for the seed required for this contract has been received and accepted by the vendor. The statement from the vendor shall include the names and quantity of seed ordered and the anticipated date of delivery.

Attention is directed to "Locate Existing Crossovers and Conduits" of these special provisions regarding locating existing irrigation water line crossovers and conduits shown on the plans to be incorporated in the new work. Existing irrigation water line crossovers and conduits shall be located prior to performing work on the irrigation system.

Unless otherwise shown on the plans or specified in these special provisions, conduits to be jacked or drilled or installed by the open trench method for water line crossovers and sprinkler control crossovers shall be installed prior to the installation of other pipe supply lines.

Attention is directed to "Existing Highway Irrigation Facilities" of these special provisions regarding the checking of existing irrigation facilities that are to remain in place, prior to the start of any irrigation work.

Clearing, grubbing, and earthwork operations shall not be performed in areas where existing irrigation facilities are to remain in place until existing irrigation facilities have been checked for proper operation in conformance with the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Existing conduits to be extended shall be located in conformance with the provisions in "Extend Irrigation Crossovers" of these special provisions prior to the start of other work in these areas.

Attention is directed to “fiber rolls” of these special provisions, regarding restrictions for other erosion control (Type D) operations.

Attention is directed to “Move-in/Move-out (Erosion Control) in these special provisions regarding the mobilization of equipment and materials for erosion control work.

Attention is directed to “Obstructions” and “Cooperation” in these special provisions.

10-1.02 WATER POLLUTION CONTROL

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications and these special provisions.

This project lies within the boundaries of the Region 2 San Francisco Bay Regional Water Quality Control Board (RWQCB).

The State Water Resources Control Board (SWRCB) has issued a permit to the Department which governs storm water and non-storm water discharges from its properties, facilities and activities. The Department's Permit is entitled: "Order No. 99-06-DWQ, NPDES No. CAS000003, National Pollutant Discharge Elimination System (NPDES) Permit, Storm Water Permit and Waste Discharge Requirements (WDRs) for the State of California, Department of Transportation Properties, Facilities, and Activities." Copies of the Department's Permit are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254, and may also be obtained from the SWRCB Internet website at: http://www.swrcb.ca.gov/stormwtr/caltrans.html.

The Department's Permit references and incorporates by reference the current Statewide General Permit issued by the SWRCB entitled "Order No. 99-08-DWQ, National Pollutant Discharge Elimination System (NPDES) General Permit No. CAS000002, Waste Discharge Requirements (WDRs) for Discharges of Storm Water Associated with Construction Activity," which regulates discharges of storm water and non-storm water from construction activities disturbing 0.4-hectare or more of soil in a common plan of development. Sampling and analysis requirements as specified in SWRCB Resolution No. 2001-46 are added to the Statewide General Permit. Copies of the Statewide General Permit and modifications thereto are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254 and may also be obtained from the SWRCB Internet website at: http://www.swrcb.ca.gov/stormwtr/construction.html.

The NPDES permits that regulate this project, as referenced above, are hereafter collectively referred to as the "Permits."

This project shall conform to the Permits and modifications thereto. The Contractor shall maintain copies of the Permits at the project site and shall make the Permits available during construction.

The Permits require the preparation of a Storm Water Pollution Prevention Plan (SWPPP). The SWPPP shall be prepared in conformance with the requirements of the Permits, the Department's "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual," and the Department's "Construction Site Best Management Practices (BMPs) Manual," including addenda to those permits and manuals issued up to and including the date of advertisement of the project. These manuals are hereinafter referred to, respectively, as the "Preparation Manual" and the "Construction Site BMPs Manual," and collectively, as the "Manuals." Copies of the Manuals may be obtained from the Department of Transportation, Material Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520, and may also be obtained from the Department's Internet website at: http://www.dot.ca.gov/hq/construc/stormwater/stormwater1.htm.

The Contractor shall know and fully comply with applicable provisions of the Permits and all modifications thereto, the Manuals, and Federal, State, and local regulations and requirements that govern the Contractor's operations and storm water and non-storm water discharges from both the project site and areas of disturbance outside the project limits during construction. Attention is directed to Sections 7-1.01, "Laws to be Observed," and 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The Permits shall apply to storm water and certain permitted non-storm water discharges from areas outside the project site which are directly related to construction activities for this contract including, but not limited to, asphalt batch plants, material borrow areas, concrete plants, staging areas, storage yards and access roads. The Contractor shall comply with the Permits and the Manuals for those areas and shall implement, inspect and maintain the required water pollution control practices. The Engineer shall be allowed full access to these areas during construction to assure Contractor's proper implementation of water pollution control practices. Installing, inspecting and maintaining water pollution control practices on areas outside the highway right of way not specifically arranged and provided for by the Department for the execution of this contract, will not be paid for.

The Contractor shall be responsible for penalties assessed or levied on the Contractor or the Department as a result of the Contractor's failure to comply with the provisions in this section "Water Pollution Control" including, but not limited to, compliance with the applicable provisions of the Permits, the Manuals, and Federal, State and local regulations and requirements as set forth therein.

Penalties as used in this section, "Water Pollution Control," shall include fines, penalties and damages, whether proposed, assessed, or levied against the Department or the Contractor, including those levied under the Federal Clean Water Act and the State Porter-Cologne Water Quality Control Act, by governmental agencies or as a result of citizen suits. Penalties shall also include payments made or costs incurred in settlement for alleged violations of the Permits, the Manuals, or applicable laws, regulations, or requirements. Costs incurred could include sums spent instead of penalties, in mitigation or to remediate or correct violations.

RETENTION OF FUNDS

Notwithstanding any other remedies authorized by law, the Department may retain money due the Contractor under the contract, in an amount determined by the Department, up to and including the entire amount of Penalties proposed, assessed, or levied as a result of the Contractor's violation of the Permits, the Manuals, or Federal or State law, regulations or requirements. Funds may be retained by the Department until final disposition has been made as to the Penalties. The Contractor shall remain liable for the full amount of Penalties until such time as they are finally resolved with the entity seeking the Penalties.

Retention of funds for failure to conform to the provisions in this section, "Water Pollution Control," shall be in addition to the other retention amounts required by the contract. The amounts retained for the Contractor's failure to conform to provisions in this section will be released for payment on the next monthly estimate for partial payment following the date when an approved SWPPP has been implemented and maintained, and when water pollution has been adequately controlled, as determined by the Engineer.

When a regulatory agency identifies a failure to comply with the Permits and modifications thereto, the Manuals, or other Federal, State or local requirements, the Department may retain money due the Contractor, subject to the following:

A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications.
C. If the Department has retained funds, and it is subsequently determined that the State is not subject to the entire amount of the Costs and Liabilities assessed or proposed in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained for the period of the retention. The interest rate payable shall be 6 percent per annum.

During the first estimate period that the Contractor fails to conform to the provisions in this section, "Water Pollution Control," the Department may retain an amount equal to 25 percent of the estimated value of the contract work performed.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor, or otherwise access the project site or the Contractor's records pertaining to water pollution control work. The Contractor and the Department shall provide copies of correspondence, notices of violation, enforcement actions or proposed fines by regulatory agencies to the requesting regulatory agency.

STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND AMENDMENTS

As part of the water pollution control work, a Storm Water Pollution Prevention Plan (SWPPP) is required for this contract. The SWPPP shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, the requirements in the Manuals, the requirements of the Permits, and these special provisions. Upon the Engineer's approval of the SWPPP, the SWPPP shall be considered to fulfill the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications for development and submittal of a Water Pollution Control Program.

No work having potential to cause water pollution, shall be performed until the SWPPP has been approved by the Engineer. Approval shall not constitute a finding that the SWPPP complies with applicable requirements of the Permits, the Manuals and applicable Federal, State and local laws, regulations, and requirements.

The Contractor shall designate a Water Pollution Control Manager. The Water Pollution Control Manager shall be responsible for the preparation of the SWPPP and required modifications or amendments, and shall be responsible for the implementation and adequate functioning of the various water pollution control practices employed. The Contractor may designate different Water Pollution Control Managers to prepare the SWPPP and to implement the water pollution control practices. The Water Pollution Control Managers shall serve as the primary contact for issues related to the SWPPP or its implementation. The Contractor shall submit to the Engineer a statement of qualifications, describing the training, previous work history and expertise of the individual selected by the Contractor to serve as Water Pollution Control Manager. The Water Pollution Control Manager shall have a minimum of 24 hours of formal storm water management training or certification as a Certified Professional in Erosion and Sediment Control (CPESC). The Engineer will reject the Contractor's submission of a Water Pollution Control Manager if the submitted qualifications are deemed to be inadequate.

The SWPPP shall apply to the areas within and those outside of the highway right of way that are directly related to construction operations including, but not limited to, asphalt batch plants, material borrow areas, concrete plants, staging areas, storage yards, and access roads.

The SWPPP shall incorporate water pollution control practices in the following categories:

A. Soil stabilization.
B. Sediment control.
C. Wind erosion control.
D. Tracking control.
E. Non-storm water management.
F. Waste management and materials pollution control.

The following contract items of work shall be incorporated into the SWPPP as "Temporary Water Pollution Control Practices": Temporary Erosion Control, Temporary Silt Fence, Temporary Drainage Inlet Protection, Temporary Cover, Temporary Construction Entrance, and Temporary Concrete Washout Facility. The Contractor's attention is directed to the special provisions provided for Temporary Water Pollution Control Practices.

The following contract items of work, as shown on the project plans or as specified elsewhere in these special provisions, shall be identified in the SWPPP as permanent water pollution control practices: Straw (Erosion Control), Fiber (Erosion Control), Seed (Erosion Control), Compost (Erosion Control), Move-in/Move-out (Erosion Control), Stabilizing Emulsion (Erosion Control), Erosion Control Blanket and Fiber Rolls. These permanent water pollution control practices shall be constructed as specified in "Order of Work" of these special provisions, and utilized during the construction period. The Contractor shall maintain and protect the permanent water pollution control practices throughout the duration of the project and shall restore these controls to the lines, grades and condition shown on the plans prior to acceptance of the contract.

The SWPPP shall include, but not be limited to, the items described in the Manuals, Permits and related information contained in the contract documents. The SWPPP shall also include a copy of the following: Notice of Construction (NOC), RWQCB Permit.

The Contractor shall develop and include in the SWPPP the Sampling and Analysis Plan(s) as required by the Permits, and modifications thereto, and as required in "Sampling and Analytical Requirements" of this section.

The Contractor shall develop a Water Pollution Control Schedule that describes the timing of grading or other work activities that could affect water pollution. The Water Pollution Control Schedule shall be updated by the Contractor to reflect changes in the Contractor's operations that would affect the necessary implementation of water pollution control practices.

The Contractor shall complete the "Construction Site BMPs Consideration Checklist" presented in the Preparation Manual and shall incorporate water pollution control practices into the SWPPP. Water pollution control practices include the "Minimum Requirements" and other Contractor-selected water pollution control practices from the "Construction Site BMPs Consideration Checklist" and the "Project-Specific Minimum Requirements" identified in the Water Pollution Control Cost Break-Down of this section.

Within 20 working days after the approval of the contract, the Contractor shall submit 3 copies of the draft SWPPP to the Engineer. The Engineer will have 10 working days to review the SWPPP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the SWPPP within 10 working days of receipt of the Engineer's comments. The Engineer will have 5 working days to review the revisions. Upon the Engineer's approval of the SWPPP, 4 approved copies of the SWPPP, incorporating the required changes, shall be submitted to the Engineer. In order to allow construction activities to proceed, the Engineer may conditionally approve the SWPPP while minor revisions are being completed. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for resulting losses, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Contractor shall prepare an amendment to the SWPPP when there is a change in construction activities or operations which may affect the discharge of pollutants to surface waters, ground waters, municipal storm drain systems, or when the Contractor's activities or operations violate a condition of the Permits, or when directed by the Engineer. Amendments shall identify additional water pollution control practices or revised operations, including those areas or operations not identified in the initially approved SWPPP. Amendments to the SWPPP shall be prepared and submitted for review and approval within a time approved by the Engineer, but in no case longer than the time specified for the initial submittal and review of the SWPPP. At a minimum, the SWPPP shall be amended annually and submitted to the Engineer 25 days prior to the defined rainy season.

The Contractor shall keep one copy of the approved SWPPP and approved amendments at the project site. The SWPPP shall be made available upon request by a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency, or the local storm water management agency. Requests by the public shall be directed to the Engineer.

COST BREAK-DOWN

The Contractor shall include a Water Pollution Control Cost Break-Down in the SWPPP which itemizes the contract lump sum for water pollution control work. The Contractor shall use the Water Pollution Control Cost Break-Down provided in this section as the basis for the cost break-down submitted with the SWPPP. The Contractor shall use the Water Pollution Control Cost Break-Down to identify items, quantities and values for water pollution control work, excluding Temporary Water Pollution Control Practices for which there are separate bid items. The Contractor shall be responsible for the accuracy of the quantities and values used in the cost break-down submitted with the SWPPP. Partial payment for the item of water pollution control will not be made until the Water Pollution Control Cost Break-Down is approved by the Engineer.

Attention is directed to "Time-Related Overhead" of these special provisions regarding compensation for time-related overhead.

Line items indicated in the Water Pollution Control Cost Break-Down in this section with a specified Estimated Quantity shall be considered "Project-Specific Minimum Requirements." The Contractor shall incorporate Project-Specific Minimum Requirements with Contractor-designated quantities and values into the Water Pollution Control Cost Break-Down submitted with the SWPPP.

Line items indicated in the Water Pollution Control Cost Break-Down in this section without a specified Estimated Quantity shall be considered by the Contractor for selection to meet the applicable "Minimum Requirements" as defined in the Manuals, or for other water pollution control work as identified in the "Construction Site BMPs Consideration Checklist" presented in the Preparation Manual. In the Water Pollution Control Cost Break-Down submitted with the SWPPP, the Contractor shall list only those water pollution control practices selected for the project, including quantities and values required to complete the work for those items.

The sum of the amounts for the items of work listed in the Water Pollution Control Cost Break-Down shall be equal to the contract lump sum price bid for water pollution control. Overhead and profit, except for time-related overhead, shall be included in the individual items listed in the cost break-down.

WATER POLLUTION CONTROL COST BREAK-DOWN

Contract No. 04-4396U4

ITEM	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	VALUE	AMOUNT
SS-1	Scheduling	LS			
SS-2	Preservation of Existing Vegetation	LS			
SS-5	Soil Binders	M2			
WE-1	Wind Erosion Control	LS			
NS-6	Illicit Connection/Illegal Discharge Detection and Reporting	LS			
NS-8	Vehicle and Equipment Cleaning	LS			
NS-9	Vehicle and Equipment Fueling	LS			
NS-10	Vehicle and Equipment Maintenance	LS			

ITEM	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	VALUE	AMOUNT
WM-1	Material Delivery and Storage	LS			
WM-2	Material Use	LS			
WM-4	Spill Prevention and Control	LS			
WM-5	Solid Waste Management	LS			
WM-9	Sanitary/Septic Waste Management	LS			

TOTAL _____

Adjustments in the items of work and quantities listed in the approved cost break-down shall be made when required to address amendments to the SWPPP, except when the adjusted items are paid for as extra work.

No adjustment in compensation will be made to the contract lump sum price paid for water pollution control due to differences between the quantities shown in the approved cost break-down and the quantities required to complete the work as shown on the approved SWPPP. No adjustment in compensation will be made for ordered changes to correct SWPPP work resulting from the Contractor's own operations or from the Contractor's negligence.

The approved cost break-down will be used to determine partial payments during the progress of the work and as the basis for calculating the adjustment in compensation for the item of water pollution control due to increases or decreases of quantities ordered by the Engineer. When an ordered change increases or decreases the quantities of an approved cost break-down item, the adjustment in compensation will be determined in the same manner specified for increases and decreases in the quantity of a contract item of work in conformance with the provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications. If an ordered change requires a new item which is not on the approved cost break-down, the adjustment in compensation will be determined in the same manner specified for extra work in conformance with Section 4-1.03D, "Extra Work," of the Standard Specifications.

If requested by the Contractor and approved by the Engineer, changes to the water pollution control practices listed in the approved cost break-down, including addition of new water pollution control practices, will be allowed. Changes shall be included in the approved amendment of the SWPPP. If the requested changes result in a net cost increase to the lump sum price for water pollution control, an adjustment in compensation will be made without change to the water pollution control item. The net cost increase to the water pollution control item will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

SWPPP IMPLEMENTATION

Unless otherwise specified, upon approval of the SWPPP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, maintaining, removing, and disposing of the water pollution control practices specified in the SWPPP and in the amendments. Unless otherwise directed by the Engineer, the Contractor's responsibility for SWPPP implementation shall continue throughout temporary suspensions of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Requirements for installation, construction, inspection, maintenance, removal, and disposal of water pollution control practices shall conform to the requirements in the Manuals and these special provisions.

If the Contractor or the Engineer identifies a deficiency in the implementation of the approved SWPPP or amendments, the deficiency shall be corrected immediately unless requested by the Contractor and approved by the Engineer in writing, but shall be corrected prior to the onset of precipitation. If the Contractor fails to correct the identified deficiency by the date agreed or prior to the onset of precipitation, the project shall be in nonconformance with this section, "Water Pollution Control." Attention is directed to Section 5-1.01, "Authority of Engineer," of the Standard Specifications, and to "Retention of Funds" of this section for possible nonconformance penalties.

If the Contractor fails to conform to the provisions of this section, "Water Pollution Control," the Engineer may order the suspension of construction operations until the project complies with the requirements of this section.

Implementation of water pollution control practices may vary by season. The Construction Site BMPs Manual and these special provisions shall be followed for control practice selection of year-round, rainy season and non-rainy season water pollution control practices.

Year-Round Implementation Requirements

The Contractor shall have a year-round program for implementing, inspecting and maintaining water pollution control practices for wind erosion control, tracking control, non-storm water management, and waste management and materials pollution control.

The National Weather Service weather forecast shall be monitored and used by the Contractor on a daily basis. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted, the necessary water pollution control practices shall be deployed prior to the onset of the precipitation.

Disturbed soil areas shall be considered active whenever the soil disturbing activities have occurred, continue to occur or will occur during the ensuing 21 days. Non-active areas shall be protected as prescribed in the Construction Site BMPs Manual within 14 days of cessation of soil disturbing activities or prior to the onset of precipitation, whichever occurs first.

In order to provide effective erosion control, the Contractor may be directed by the Engineer to apply permanent erosion control in small or multiple units. The Contractor’s attention is directed to "Erosion Control (Type D)" and "Move-In/Move-Out (Erosion Control)" of these special provisions.

The Contractor shall implement, maintain and inspect the following temporary sediment control practices on a year-round basis. The listed practices shall remain in place until their use is no longer needed, as determined by the Engineer.

YEAR-ROUND SEDIMENT CONTROL PRACTICES	LOCATION USED
Temporary Construction Entrance	At the conform between construction work area and roadways used by the public

Rainy Season Implementation Requirements

Soil stabilization and sediment control practices shall be provided throughout the rainy season, defined as between October 15 and April 15.

An implementation schedule of required soil stabilization and sediment control practices for disturbed soil areas shall be completed no later than 20 days prior to the beginning of each rainy season. The implementation schedule shall identify the soil stabilization and sediment control practices and the dates when the implementation will be 25 percent, 50 percent and 100 percent complete, respectively. For construction activities beginning during the rainy season, the Contractor shall implement applicable soil stabilization and sediment control practices. The Contractor shall implement soil stabilization and sediment control practices a minimum of 10 days prior to the start of the rainy season.

Throughout the defined rainy season, the active disturbed soil area of the project site shall be not more than 2.0 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active disturbed soil area limit. Soil stabilization and sediment control materials shall be maintained on site sufficient to protect disturbed soil areas. A detailed plan for the mobilization of sufficient labor and equipment shall be maintained to deploy the water pollution control practices required to protect disturbed soil areas prior to the onset of precipitation.

Non-Rainy Season Implementation Requirements

The non-rainy season shall be defined as days outside the defined rainy season. The Contractor's attention is directed to the Construction Site BMPs Manual for soil stabilization and sediment control implementation requirements on disturbed soil areas during the non-rainy season. Disturbed soil areas within the project shall be protected in conformance with the requirements in the Construction Site BMPs Manual with an effective combination of soil stabilization and sediment control.

MAINTENANCE

To ensure the proper implementation and functioning of water pollution control practices, the Contractor shall regularly inspect and maintain the construction site for the water pollution control practices identified in the SWPPP. The construction site shall be inspected by the Contractor as follows:

A. Prior to a forecast storm.
B. After a precipitation event which causes site runoff.
C. At 24 hour intervals during extended precipitation events.
D. Routinely, a minimum of once every two weeks outside of the defined rainy season.
E. Routinely, a minimum of once every week during the defined rainy season.

The Contractor shall use the Storm Water Quality Construction Site Inspection Checklist provided in the Preparation Manual or an alternative inspection checklist provided by the Engineer. One copy of each site inspection record shall be submitted to the Engineer within 24 hours of completing the inspection.

REPORTING REQUIREMENTS

Report of Discharges, Notices or Orders

If the Contractor identifies discharges into surface waters or drainage systems in a manner causing, or potentially causing, a condition of pollution, or if the project receives a written notice or order from a regulatory agency, the Contractor shall immediately inform the Engineer. The Contractor shall submit a written report to the Engineer within 7 days of the discharge event, notice or order. The report shall include the following information:

A. The date, time, location, nature of the operation, and type of discharge, including the cause or nature of the notice or order.
B. The water pollution control practices deployed before the discharge event, or prior to receiving the notice or order.
C. The date of deployment and type of water pollution control practices deployed after the discharge event, or after receiving the notice or order, including additional measures installed or planned to reduce or prevent reoccurrence.
D. An implementation and maintenance schedule for affected water pollution control practices.

Report of First-Time Non-Storm Water Discharge

The Contractor shall notify the Engineer at least 3 days in advance of first-time non-storm water discharge events, excluding exempted discharges. The Contractor shall notify the Engineer of the operations causing non-storm water discharges and shall obtain field approval for first-time non-storm water discharges. Non-storm water discharges shall be monitored at first-time occurrences and routinely thereafter.

Annual Certifications

By June 15 of each year, the Contractor shall complete and submit an Annual Certification of Compliance, as contained in the Preparation Manual, to the Engineer.

SAMPLING AND ANALYTICAL REQUIREMENTS

The Contractor is required to implement specific sampling and analytical procedures to determine whether BMPs implemented on the construction site are:

A. preventing pollutants that are known or should be known by permittees to occur on construction sites that are not visually detectable in storm water discharges, to cause or contribute to exceedances of water quality objectives, and
B. preventing further impairment by sediment in storm waters discharged into water bodies listed as impaired due to sediment, siltation or turbidity.

Non-Visible Pollutants

The project has the potential to discharge non-visible pollutants in storm water from the construction site. The project SWPPP shall contain a Sampling and Analysis Plan (SAP) that describes the sampling and analysis strategy and schedule to be implemented on the project for monitoring non-visible pollutants in conformance with this section.

The SAP shall identify potential non-visible pollutants that are known or should be known to occur on the construction site associated with the following: (1) construction materials, wastes or operations; (2) known existing contamination due to historical site usage; or (3) application of soil amendments, including soil stabilization products, with the potential to alter pH or contribute toxic pollutants to storm water. Planned material and waste storage areas, locations of known existing contamination, and areas planned for application of soil amendments shall be shown on the SWPPP Water Pollution Control Drawings.

The SAP shall identify a sampling schedule for collecting a sample down gradient from the applicable non-visible pollutant source and a sufficiently large uncontaminated control sample during the first two hours of discharge from rain events during daylight hours which result in a sufficient discharge for sample collection. If run-on occurs onto the non-visible pollutant source, a run-on sample that is immediately down gradient of the run-on to the Department's right of way shall be collected. A minimum of 72 hours of dry weather shall occur between rain events to distinguish separate rain events.

The SAP shall state that water quality sampling will be triggered when any of the following conditions are observed during the required storm water inspections conducted before or during a rain event:

A. Materials or wastes containing potential non-visible pollutants are not stored under watertight conditions.
B. Materials or wastes containing potential non-visible pollutants are stored under watertight conditions, but (1) a breach, leakage, malfunction, or spill is observed; and (2) the leak or spill has not been cleaned up prior to the rain event; and (3) there is the potential for discharge of non-visible pollutants to surface waters or drainage system.
C. Construction activities, such as application of fertilizer, pesticide, herbicide, methyl methacrylate concrete sealant, or non-pigmented curing compound have occurred during a rain event or within 24 hours preceding a rain event, and there is the potential for discharge of pollutants to surface waters or drainage system.
D. Soil amendments, including soil stabilization products, with the potential to alter pH levels or contribute toxic pollutants to storm water runoff have been applied, and there is the potential for discharge of pollutants to surface waters or drainage system (unless independent test data are available that demonstrate acceptable concentration levels of non-visible pollutants in the soil amendment).
E. Storm water runoff from an area contaminated by historical usage of the site is observed to combine with storm water, and there is the potential for discharge of pollutants to surface waters or drainage system.

The SAP shall identify sampling locations for collecting down gradient and control samples, and the rationale for their selection. The control sampling location shall be selected where the sample does not come into contact with materials, wastes or areas associated with potential non-visible pollutants or disturbed soil areas. Sampling locations shall be shown on the SWPPP Water Pollution Control Drawings. Only trained personnel shall collect water quality samples and be identified in the SAP. Qualifications of designated sampling personnel shall describe training and experience, and shall be included in

the SWPPP. The SAP shall state monitoring preparation, sample collection procedures, quality assurance/quality control, sample labeling procedures, sample collection documentation, sample shipping and chain of custody procedures, sample numbering system, and reference the construction site health and safety plan.

The SAP shall identify the analytical method to be used for analyzing down gradient and control samples for potential non-visible pollutants on the project. For samples analyzed in the field by sampling personnel, collection, analysis, and equipment calibration shall be in conformance with the Manufacturer's specifications. For samples that will be analyzed by a laboratory, sampling, preservation, and analysis shall be performed by a State-certified laboratory in conformance with 40 CFR 136. The SAP shall identify the specific State-certified laboratory, sample containers, preservation requirements, holding times, and analysis method to be used. A list of State-certified laboratories that are approved by the Department is available at the following internet site: http://www.dhs.ca.gov/ps/ls/elap/html/lablist_county.htm.

Analytical Results and Evaluation

The Contractor shall submit a hard copy and electronic copy of water quality analytical results and quality assurance/quality control data to the Engineer within 5 days of sampling for field analyses and within 30 days for laboratory analyses. Analytical results shall be accompanied by an evaluation from the Contractor to determine if down gradient samples show elevated levels of the tested parameter relative to levels in the control sample. If down gradient or downstream samples, as applicable, show increased levels, the Contractor will assess the BMPs, site conditions, and surrounding influences to determine the probable cause for the increase. As determined by the assessment, the Contractor will repair or modify BMPs to address increases and amend the SWPPP as necessary. Electronic results (in one of the following file formats: .xls, .txt, .csv, .dbs, or .mdb) shall have at a minimum the following information: sample identification number, contract number, constituent, reported value, method reference, method detection limit, and reported detection limit. The Contractor shall document sample collection during rain events.

Water quality sampling documentation and analytical results shall be maintained with the SWPPP on the project site until a Notice of Completion has been submitted and approved.

If construction activities or knowledge of site conditions change, such that discharges or sampling locations change, the Contractor shall amend the SAP in conformance with this section, "Water Pollution Control."

PAYMENT

The contract lump sum price paid for prepare storm water pollution prevention plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in developing, preparing, obtaining approval of, revising, and amending the SWPPP, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Attention is directed to Section 9-1.06, "Partial Payments," and Section 9-1.07, "Payment After Acceptance," of the Standard Specifications. Payments for prepare storm water pollution prevention plan will be made as follows:

A. After the SWPPP has been approved by the Engineer, 75 percent of the contract item price for prepare storm water pollution prevention plan will be included in the monthly partial payment estimate.
B. After acceptance of the contract in conformance with the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, payment for the remaining 25 percent of the contract item price for prepare storm water pollution prevention plan will be made in conformance with the provisions in Section 9-1.07.

The contract lump sum price paid for water pollution control shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing, constructing, removing, and disposing of water pollution control practices, including non-storm water management, and waste management and materials pollution water pollution control practices, except those for which there is a contract item of work as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Storm water sampling and analysis will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. No payment will be made for the preparation, collection, analysis, and reporting of storm water samples required where appropriate BMPs are not implemented prior to a rain event, or if a failure of a BMP is not corrected prior to a rain event.

For items identified on the approved Water Pollution Control Cost Break-Down, the cost of maintaining the temporary water pollution control practices shall be divided equally by the State and the Contractor as follows:

Soil Stabilization

Temporary water pollution control practices except:

SS-1 Scheduling
SS-2 Preservation of Existing Vegetation

Sediment Control

Temporary water pollution control practices except:
SC-7 Street Sweeping and Vacuuming

Wind Erosion Control

No sharing of maintenance costs will be allowed.

Tracking Control

TC-1 Stabilized Construction Entrance/Exit.

Non-Storm Water Management

No sharing of maintenance costs will be allowed.

Waste Management & Materials Pollution Control

No sharing of maintenance costs will be allowed.

The division of cost will be made by determining the cost of maintaining water pollution control practices in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications and paying to the Contractor one-half of that cost. Cleanup, repair, removal, disposal, improper installation, and replacement of water pollution control practices damaged by the Contractor's negligence, shall not be considered as included in the cost for performing maintenance.

The provisions for sharing maintenance costs shall not relieve the Contractor from the responsibility for providing appropriate maintenance on items with no shared maintenance costs.

Full compensation for non-shared maintenance costs of water pollution control practices, as specified in this section, "Water Pollution Control," shall be considered as included in the contract lump sum price paid for water pollution control and no additional compensation will be allowed therefor.

Water pollution control practices for which there is a contract item of work, will be measured and paid for as that contract item of work.

10-1.03 TEMPORARY DRAINAGE INLET PROTECTION

Temporary drainage inlet protection shall be constructed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Attention is directed to "Water Pollution Control" of these special provisions.

Temporary drainage inlet protection shall be one of the water pollution control practices for sediment control. The Storm Water Pollution Prevention Plan shall include the use of temporary drainage inlet protection.

Temporary drainage inlet protection shall be either Type 1, Type 2, Type 3A, Type 3B, Type 4A, Type 4B or Type 5.

MATERIALS

Erosion Control Blanket

Erosion control blanket for temporary drainage inlet protection (Types 1, 2, 3B, and 4A) shall be one of the following:

A. Machine produced mats consisting of curled wood excelsior with 80 percent of the fiber 150 mm or longer. The excelsior blanket shall be of consistent thickness with wood fiber evenly distributed over the entire area of the blanket. The top surface of the blanket shall be covered with an extruded photodegradable plastic netting or lightweight non-synthetic netting. The blanket shall be smolder resistant without the use of chemical additives and shall be non-toxic and non-injurious to plant and animal life. Excelsior blanket shall be furnished in rolled strips with a minimum mass per unit area of 0.40-kg/m^2.
B. Machine produced mats consisting of 70 percent straw and 30 percent coconut fiber with an extruded photodegradable plastic netting or lightweight non-synthetic netting on the top and bottom surfaces of the blanket. The straw and coconut shall adhere to the netting using thread or glue strip. The straw and coconut blanket shall be of consistent thickness, with straw and coconut fiber shall be evenly distributed over the entire area of the blanket. Straw and coconut fiber blanket shall be furnished in rolled strips with a minimum mass per unit area of 0.27 kg/m^2.
C. Machine produced mats consisting of 100 percent coir consisting of coconut fiber with an extruded photodegradable plastic netting or lightweight non-synthetic netting on the top and bottom surfaces of the blanket. The coconut fiber shall adhere to the netting using thread or glue strip. The coconut blanket shall be of consistent thickness, with

coconut fiber evenly distributed over the entire area of the blanket. Coconut fiber blanket shall be furnished in rolled strips with a minimum mass per unit area of 0.27 kg/m^2.

D. Machine woven netting consisting of 100 percent spun coir consisting of coconut fiber with an average open area of 63 to 70 percent. Coconut coir netting shall be furnished in rolled strips with a minimum mass per unit area of 0.40 kg/m^2.

Geotextile

Geotextile blanket for temporary drainage inlet protection (Types 1, 2, 3B, and 4A) shall conform to the provisions in Section 88-1.04, "Rock Slope Protection Fabric," of the Standard Specifications for rock slope protection fabric (Type A).

Staples

Staples for temporary drainage inlet protection (Types 1, 2, 3B, and 4A) shall be as shown on the plans. An alternative attachment device such as geotextile pins or plastic pegs may be used instead of staples. The Contractor shall submit a sample of the alternative attachment device for Engineer's approval prior to installation.

Rocks

Rocks for temporary drainage inlet protection (Types 1 and 2) shall be angular to subangular in shape, and shall conform to the material quality requirements in Section 72-2.02, "Materials," of the Standard Specifications for apparent specific gravity, absorption, and durability index. Rocks used for the temporary entrance shall conform to the following sizes:

Square Screen Size (mm)	Percentage Passing
150	100
75	0-20

Fiber Roll

Fiber roll for temporary drainage inlet protection (Type 4A) shall be one of the following:

A. Fiber roll shall be constructed with a pre-manufactured blanket consisting of one material or a combination of materials consisting of wood excelsior, rice or wheat straw, or coconut fibers. The blanket shall be between 2.0 m and 2.4 m in width and between 20 m and 29 m in length. Wood excelsior shall be individual fibers, of which percent shall be 150 mm or longer in length. The blanket shall have a photodegradable plastic netting or biodegradable jute, sisal or coir fiber netting on at least one side. The blanket shall be rolled along the width and secured with jute twine spaced 2 m apart along the full length of the roll and placed 150 mm from the ends of each roll. The finished roll shall be between 200 mm and 250 mm in diameter, between 3 m and 6 m in length and shall weigh at least 0.81-kg/m. More than one blanket may be required to achieve the finished roll diameter. When more than one blanket is required, blankets shall be jointed longitudinally with an overlap of 150 mm along the length of the blanket.

B. Fiber roll shall be a pre-manufactured roll of rice or wheat straw, wood excelsior or coconut fiber encapsulated within a photodegradable plastic or biodegradable jute, sisal or coir fiber netting. Rolls shall be between 200 mm and 250 mm in diameter, between 3 m and 6 m in length and shall weigh at least 1.6 kg/m. The netting shall have a minimum durability of one year after installation. The netting shall be secured tightly at each end of the rolls.

Stakes

Stakes (fiber roll) shall be shall be a minimum of 19 mm x 38 mm x 450 mm. Wood stakes shall be untreated fir, redwood, cedar, or pine, shall be cut from sound timber, and shall be straight and free of loose or unsound knots and other defects which would render them unfit for the purpose intended.

Rope

Rope (fiber roll) shall be biodegradable, such as sisal or manila, with a minimum diameter of 6.35 mm.

Gravel Bag

Gravel bag fabric for temporary drainage inlet protection (Types 3A, 3B, and 4B) shall be non-woven polypropylene geotextile (or comparable polymer) and shall conform to the following requirements:

Specification	Requirements
Mass per unit area, grams per square meter, min. ASTM Designation: D 5261	270
Grab tensile strength (25-mm grip), kilonewtons, min. ASTM Designation: D4632*	0.89
Ultraviolet stability, percent tensile strength retained after 500 hours, ASTM Designation: D4355, xenon arc lamp method	70

* or appropriate test method for specific polymer

Gravel bags shall be between 600 mm and 800 mm in length, and between 400 mm and 500 mm in width.

Yarn used for binding gravel bags shall be as recommended by the manufacturer or bag supplier and shall be of a contrasting color.

Gravel shall be between 10 mm and 20 mm in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials. The opening of gravel-filled bags shall be secured to prevent gravel from escaping. Gravel-filled bags shall be between 13 kg and 22 kg in mass.

Silt Fence Fabric

Silt fence fabric for temporary drainage inlet protection shall be geotextile manufactured from woven polypropylene or polymer material. Silt Fence Fabric may be virgin or recycled, or a combination of virgin and recycled polymer materials. No virgin or recycled polymer materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance to the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Silt fence fabric shall conform to the following requirements:

Specification	Requirements
Width, mm, min.	900
Grab tensile strength (25-mm grip), kilonewtons, min. in each direction ASTM Designation: D 4632*	0.55
Elongation, percent minimum in each direction ASTM Designation: D 4632*	15
Permittivity, 1/sec., min. ASTM Designation: D 4491	0.05
Flow rate, liters per minute per square meter, min. ASTM Designation: D 4491	400
Ultraviolet stability, percent tensile strength retained after 500 hours, min. ASTM Designation: D 4355 (xenon-arc lamp and water spray weathering method)	70

* or appropriate test method for specific polymer

Posts

Posts for temporary silt fence shall be one of the following:

A. Posts (temporary silt fence) shall be fir or pine, a minimum 34 mm x 40 mm in size, and 1.2 m in length. One end of the post shall be pointed. Wood preservative treatment will not be required for wood posts.
B. Posts (temporary silt fence) shall be steel and have a "U", "T", "L" or other cross sectional shape that can resist failure by lateral loads. The steel posts shall have a minimum mass per length of 1.1 kg/m and a minimum length of 1.2 m. One end of the steel posts shall be pointed and the other end shall be capped with an orange or red plastic safety cap which fits snugly to the steel post. The Contractor shall submit to the Engineer for approval a sample of the capped steel post prior to installation.

Fasteners

Fasteners for attaching silt fence fabric to posts shall be as follows:

A. When prefabricated silt fence is used, posts shall be inserted into sewn pockets.
B. Silt fence fabric shall be attached to wooden posts with nails or staples as shown on the plans or as recommended by the manufacturer or supplier. Tie wire or locking plastic fasteners shall be used to fasten the silt fence fabric to steel posts. Maximum spacing of fasteners shall be 200 mm along the length of the steel post.

Foam Barrier

Foam barrier fabric cover and skirt for temporary drainage inlet protection (Type 4B) shall be a woven polypropylene fabric with a minimum tensile strength of 0.44-kN, conforming to ASTM Designation: D 4632. The prefabricated fabric shall be high visibility orange in color that is integral to the fabric; painting shall not be allowed. The fabric shall have an ultraviolet (UV) stability exceeding 70 percent.

Foam core (foam barrier) shall be urethane foam and shall be shaped and dimensioned as shown on the plans.

Adhesive for foam barrier shall be a solvent free rubber modified asphalt emulsion. The color of the emulsion shall be brown when wet and shall have a drying period of not more than 3 hours.

Anchoring nails or spikes for foam barrier shall be a minimum of 25 mm in length and capable of penetrating concrete and asphalt surfaces.

Sediment Filter Bag

Sediment filter bag for temporary drainage inlet protection (Type 5) shall be manufactured from sediment filter bag fabric. The sediment filter bag shall be sized to fit the catch basin or drainage inlet and be complete with lifting loops and dump straps attached at the bottom to facilitate emptying of the sediment filter bag. The sediment filter bags shall have a restraint cord approximately halfway up the bag to keep the sides away from the catch basin walls.

Sediment filter bag fabric shall be geotextile manufactured from woven polypropylene or polymer material. Sediment filter bag fabric may be virgin or recycled, or a combination of virgin and recycled polymer materials. No virgin or recycled polymer materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance to the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Sediment filter bag fabric shall conform to the following requirements:

Specification	Requirements
Grab tensile strength (25-mm grip), kilonewtons, min. in each direction ASTM Designation: D 4632*	1.35
Elongation, percent minimum in each direction ASTM Designation: D 4632*	20
Permittivity, 1/sec., min. ASTM Designation: D 4491	0.55
Flow rate, liters per minute per square meter, min. ASTM Designation: D 4491	1600
Ultraviolet stability, percent tensile strength retained after 500 hours, min. ASTM Designation: D 4355 (xenon-arc lamp and water spray weathering method)	80

* or appropriate test method for specific polymer

INSTALLATION

Temporary drainage inlet protection shall be installed at drain inlets in paved and unpaved areas as follows:

A. Temporary drainage inlet protection shall be installed such that ponded runoff does not encroach into the traveled way or overtop the curb or dike. Gravel-filled bags shall be placed to control ponding and prevent runoff from overtopping the curb or dike.
B. The bedding area for the temporary drainage inlet protection shall be cleared of obstructions including, but not limited to, rocks, clods, and debris greater than 25 mm in diameter prior to installation.
C. Temporary silt fence shall be installed as necessary up-slope of the existing drainage inlet and parallel to the curb, dike, or flow line to prevent sediment from entering the drainage inlet.
D. Temporary drainage inlet protection (Type 1): Erosion control blanket or geotextile fabric shall be secured with staples and embedded into a trench adjacent to the drainage inlet. The silt fence shall be installed along the perimeter of the installed erosion control blanket or geotextile fabric. The silt fence shall be installed with the posts facing the drainage inlet. The silt fence fabric and the perimeter edge of the erosion control blanket or geotextile fabric shall be anchored in a trench. The trench shall be backfilled and mechanically or hand tamped to secure the silt fence fabric in the bottom of the trench.
E. Temporary drainage inlet protection (Type 2): The area around the drainage inlet shall be excavated to create a sediment trap. Erosion control blanket or geotextile fabric shall be secured to the surface of the excavated sediment trap with staples and embedded into a trench adjacent to the drainage inlet. The silt fence shall be installed along the perimeter of the installed erosion control blanket or geotextile fabric. The silt fence shall be installed with the posts facing the drainage inlet. The silt fence fabric and the perimeter edge of the erosion control blanket or geotextile

fabric shall be anchored in a trench. The trench shall be backfilled and mechanically or hand tamped to secure the silt fence fabric in the bottom of the trench.

F. Temporary drainage inlet protection (Type 3A): Gravel-filled bags shall be staked in rows two layers high to form a gravel bag barrier. The gravel-filled bags shall be placed so that the bags are tightly abutted and overlap the joints in adjacent rows. A spillway shall be created by removing one or more gravel-filled bags from the upper layer of the gravel bag barrier.

G. Temporary drainage inlet protection (Type 3B): Erosion control blanket or geotextile fabric shall be secured with staples and embedded into a trench adjacent to the drainage inlet. Gravel-filled bags shall be staked in rows two layers high in a pyramid configuration to form a gravel bag barrier centered over the perimeter of the erosion control blanket or geotextile fabric. The gravel-filled bags shall be placed so that the bags are tightly abutted and overlap the joints in adjacent rows. A spillway shall be created by removing one or more gravel-filled bags from the upper layer of the gravel bag barrier.

H. Temporary drainage inlet protection (Type 4A): Erosion control blanket or geotextile fabric shall be secured with staples and embedded into a trench adjacent to the drainage inlet. Fiber rolls shall be placed over the erosion control blanket or geotextile fabric with the ends of the fiber roll abutted tightly together. Fiber rolls shall be secured with stakes installed along the length of the fiber rolls and stopped at 300 mm from each end of the rolls. Stakes shall be driven to a maximum of 50 mm above, or flush with, the top of the roll.

I. Temporary drainage inlet protection (Type 4B): Foam barrier shall consist of individual sections installed in conjunction with one another adjacent to existing drainage inlets. Foam barriers shall be securely attached to the pavement according to the angle and spacing as shown on the plans. Foam barrier shall be installed flush against the sides of concrete or asphalt curbs, dikes and pavement with the inner material and fabric cover cut smoothly and evenly to provide a tight flush joint.

J. Temporary drainage inlet protection (Type 5): Sediment filter bags shall be installed by removing the drainage inlet grate, placing the sediment bag in the opening, and replacing the grate to secure the sediment filter bag in place.

The Contractor shall select the appropriate drainage inlet protection in conformance with the details to meet the field condition around the drainage inlet. For all other drainage inlets within the project limits that do not conform to the details shown on the plans, the Contractor shall submit to the Engineer for approval, provisions for providing temporary drainage inlet protection.

Details for an alternative temporary drainage inlet protection shall be submitted to the Engineer for approval at least 7 days prior to installation.

Throughout the duration of the Contract, the Contractor shall be required to provide protection to meet the changing condition of the drainage inlet.

Special attention shall be given to existing and new drainage inlets adjacent to traffic. The Engineer shall review the need for drainage inlet protection at each location. Each proposed drainage inlet protection shall be approved by the Engineer to ensure safety.

When the temporary drainage inlet protections are no longer required, temporary drainage inlet protection materials shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Holes, depressions or other ground disturbance caused by the removal of the temporary drainage inlet protection shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

Temporary drainage inlet protection shall be maintained to provide sediment holding capacity and to reduce runoff velocities and as follows:

A. Gravel-filled bags shall be replaced when the bag material ruptures and allows the contents to spill out, or when the yarn fails and allows the bag contents to spill out.

B. Temporary silt fence shall be repaired or replaced when silt fence fabric becomes split, torn, or unraveled. Broken or split stakes shall be replaced. Sagging or slumping silt fence shall be repaired with additional stakes or replaced.

C. Locations where rills and other evidence of concentrated runoff have occurred beneath the fiber rolls, silt fences, foam barriers, or gravel bag barriers shall be corrected.

D. Sediment deposits, trash and debris shall be removed from temporary drainage inlet as described in this special provision or as directed by the Engineer. Removed sediment shall be deposited within the project limits in such a way that the sediment is not subject to erosion by wind or by water. Trash and debris shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

E. Temporary drainage inlet protection (Type 1): Temporary silt fence shall be maintained to provide a sediment holding capacity of approximately one-third the height of the silt fence fabric above ground. Sediment in excess of 50 mm above the surface of the erosion control blanket or geotextile fabric shall be removed.
F. Temporary drainage inlet protection (Type 2): Temporary silt fence shall be maintained to provide a sediment holding capacity of approximately one-third the height of the silt fence fabric above ground. Sediment shall be removed from the sediment trap when the volume has been reduced by approximately one-half.
G. Temporary drainage inlet protection (Type 3A): Sediment deposits shall be removed when the deposit reaches one-third the height of the gravel bag barrier or one-half the height of the spillway; whichever is less.
H. Temporary drainage inlet protection (Type 3B): Sediment deposits shall be removed when the deposit reaches one-third the height of the gravel bag barrier or one-half the height of the spillway; whichever is less. Sediment in excess of 50 mm above the surface of the erosion control blanket or geotextile fabric shall be removed.
I. Temporary drainage inlet protection (Type 4A): Split, torn, or unraveling fiber rolls shall be replaced. Broken or split stakes shall be replaced. Sagging or slumping fiber rolls shall be repaired with additional stakes or replaced. Sediment in excess of 50 mm above the surface of the erosion control blanket or geotextile fabric shall be removed.
J. Temporary drainage inlet protection (Type 4B): Foam barriers shall be repaired or replaced when the geotextile fabric cover becomes split, torn, or unraveled. Foam barriers that become detached or dislodged shall be reattached to the pavement. Sediment deposits shall be removed when the deposit reaches one-third of the foam barrier height.
K. Temporary drainage inlet protection (Type 5): Sediment filter bags shall be emptied when the restraint cords are no longer visible. Emptying of the bag shall be facilitated by the use of 25mm steel reinforcing bars placed through the lifting loops. The sediment bag shall be emptied of material and rinsed before replacement in the catch basin or drainage inlet.

Temporary drainage inlet protection shall be repaired or replaced on the same day when the damage occurs. Damage to the temporary drainage inlet protection resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor’s expense.

MEASUREMENT AND PAYMENT

Temporary drainage inlet protection Type 1A, 1B, 2A, 2B, 3 and 4 shall be measured and paid for as temporary drainage inlet protection.

The quantity of temporary drainage inlet protection to be paid for will be measured by the unit as determined from actual count in place. The protection is measured one time only and no additional measurement is recognized and no additional compensation made if the temporary drainage inlet protection changes during the course of construction.

The contract unit price paid for temporary drainage inlet protection shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the temporary drainage inlet protection, complete in place, including maintenance, removal of materials, and backfilling and repairing holes, depressions and other ground disturbance, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

No adjustment of compensation will be made for any increase or decrease in the quantities of temporary drainage inlet protection required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to temporary drainage inlet protection.

10-1.04 TEMPORARY EROSION CONTROL

Temporary erosion control shall conform to the provisions for erosion control in Section 20-3, "Erosion Control," of the Standard Specifications and these special provisions.

Attention is directed to "Water Pollution Control" of these special provisions.

Temporary erosion control work shall consist of applying erosion control materials to embankment slopes, excavation slopes and other areas designated on the plans. Temporary erosion control work shall be completed in the designated areas during the period starting October 15 and ending April 15. Temporary erosion control work shall be implemented on unfinished active disturbed soil areas as directed by the Engineer.

Temporary erosion control work shall consist of hydraulically applying a temporary soil stabilizer (solids) consisting of processed gypsum plaster, color hardener, fiber, and water to slopes and other areas as provided for in these special provisions.

MATERIALS

Materials shall conform to the provisions in Section 20-2, "Materials," of the Standard Specifications and the following:

Stabilizing Emulsion (Solids)

A. Stabilizing emulsion (solids) shall consist of a gypsum plaster processed into a dry, ground powder of calcium sulfate hemi-hydrate. Plaster shall be furnished either in bags or bulk. Plaster that has set into a lumpy or caked condition prior to use shall be rejected.
B. Stabilizing emulsion (solids) shall be formulated specifically for use in erosion control and soil stabilization. Emulsion (solids) shall be non-corrosive and water-soluble emulsion such that, upon application, cures to a water insoluble binding and cementing agent.

Color Hardener

Coloring, material shall consist of a processed powdered cementitious hardener with a muted green color conforming to ASTM C 979.

APPLICATION

Temporary erosion control materials shall be applied as follows:

A. The application shall consist of applying the following mixture in the proportions indicated with hydro-seeding equipment:

Material	Kilograms Per Hectare (Slope Measurement)
Fiber	840
Stabilizing Emulsion (solids)	6740
Color Hardener (solids)	54

B. The dilution of stabilizing emulsion (solids) to water (liter) per hectare shall be as required to facilitate even application of material. Several applications may be required to apply all specified materials. Stabilizing emulsion (solids) and color hardener (solids) shall be added to the water and fiber mixture in the tanks.
C. Stabilizers shall not be applied to areas with standing water.
D. The application of soil stabilizer will be applied in a down slope direction to provide uniform coverage when possible. Application of material shall be performed during dry weather with a minimum of 8 hours of dry weather predicted following application prior to any anticipated rain.
E. Due to the cementitious nature of the stabilizing emulsion (solids) and color hardener (solids), it is recommended that application of the soil stabilizer be performed continuously without interruption to prevent setting up of the material. All equipment used to apply soil stabilizer shall be flushed immediately following application and cleaned thoroughly as soon as possible as recommended by the manufacturer.
F. Any areas disturbed or displaced by construction operations or equipment following application shall be replaced at the Contractor's expense.

MEASUREMENT AND PAYMENT

Temporary erosion control work will be measured by the square meter or hectare, whichever is designated in the contract item. The quantity of temporary erosion control to be paid for by the square meter or hectare will be calculated on the basis of actual or computed slope measurements.

Temporary erosion control placed at locations other than as shown on the project plans or directed by the Engineer, in conformance with the Contractor's Storm Water Pollution Prevention Plan, will not be measured and will be paid for as specified in "Water Pollution Control" of these special provisions.

No adjustment of compensation will be made for any increase or decrease in the quantities of temporary erosion control required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to temporary erosion control.

10-1.05 TEMPORARY COVER

Temporary cover shall be furnished, installed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Attention is directed to "Water Pollution Control" of these special provisions.

Temporary cover shall be one of the water pollution control practices for soil stabilization. The Storm Water Pollution Prevention Plan shall include the use of temporary cover.

MATERIALS

Temporary Cover Fabric

Temporary cover fabric shall be either a geomembrane (plastic sheeting) or a geotextile (engineering fabric) conforming to one of the following requirements:

A. Geotextile shall be a woven, slit film fabric which is also known as woven tape. The fabric shall be non-biodegradable, resistant to deterioration by sunlight, and inert to most soil chemicals. Edges of the film fabric shall be selvage or serge to prevent unraveling. The film fabric shall also conform to the following requirements:

Specification	Requirements
Grab tensile strength (25-mm grip), kilonewtons, min. ASTM Designation: D4632*	0.89
Elongation at break, percent min. ASTM Designation: D4632*	15
Toughness, kilonewtons, min. (percent elongation x grab tensile strength)	13.3
Permittivity, 1/sec, max. (liters per minute per square meter) ASTM Designation: D 4491	0.08 (244)
Ultraviolet light stability, percent tensile strength retained after 500 hours, min. ASTM Designation: D 4355 (xenon arc lamp method)	70

* or appropriate test method for specific polymer

B. Geomembrane shall consist of 0.25-mm thick, single-ply material in conformance with the requirements in ASTM Designation: D 5199.

Temporary cover fabric shall be manufactured from polyethylene or polypropylene, or comparable polymers. The polymer materials may be virgin, recycled, or a combination of virgin and recycled materials. The polymer materials shall not contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance with the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Restrainers

Restrainers for securing the temporary cover fabric on slopes and stockpiles shall consist of one or a combination of the following:

A. Gravel-filled bags used as restrainers shall be knotted, roped, and placed at a maximum of 2 m apart on the temporary cover fabric as shown on the plans. Gravel-filled bags shall be between 13 kg and 22 kg in mass, between 600 mm and 800 mm in length, and between 400 mm and 500 mm in width. Gravel bag fabric shall be non-woven polypropylene geotextile with a minimum unit weight of 270 g/m^2. The fabric shall have a minimum grab tensile strength (25-mm grip) of 0.89-kN in conformance with the requirements in ASTM Designation: D 4632, and an ultraviolet (UV) stability of 70 percent tensile strength retained after 500 hours in conformance to the requirements in ASTM Designation: D 4355, xenon arc lamp method. Gravel shall consist of non-cohesive material between 10 mm and 20 mm in diameter, free of clay balls, organic matter, and other deleterious material. The openings of filled gravel bags shall be secured to prevent escape of gravel.
B. Restrainers consisting of a steel anchor with a wooden lath shall be fabricated and placed as shown on the plans. Wooden lath shall conform to the provisions in Section 20-2.12, "Lumber," of the Standard Specifications and shall be fir or pine, 38 mm x 89 mm in size, and 2.4 m in length. The wooden lath shall be secured to the temporary cover with steel anchors placed 1.2 m apart along the lath.

The Contractor may use an alternative restrainer if approved by the Engineer in writing. The Contractor shall submit details for an alternative restrainer to the Engineer prior to installation. The alternative restrainer shall be installed and maintained in conformance with these special provisions.

INSTALLATION

Temporary cover shall be installed as follows:

A. Temporary cover fabric shall be placed and anchored as shown on the plans.
B. Abutting edges of the temporary cover fabric shall overlap a minimum of 600 mm. Non-abutting edges shall be embedded in the soil a minimum of 150 mm.
C. Restrainers shall be placed at the overlap area and along the toe of the slope. Restrainers outside the overlap areas shall be placed at a maximum spacing of 2.4 m.
D. Steel anchors shall be installed to allow the leg of the steel anchor to pierce through the temporary cover fabric into the slope with the crown section securing the wooden lath firmly against the slope.
E. Earthen berm, a linear sediment barrier, shall be constructed adjacent to the toe of the slope with a minimum height of 200 mm and a minimum width of 940 mm. The earthen berms shall be hand or mechanically compacted. Alternative linear sediment barrier may be used at the Contractor's expense if approved by the Engineer in writing .

If the Contractor removes the temporary cover in order to facilitate other work, the temporary cover shall be replaced and secured by the Contractor at the Contractor's expense.

When no longer required as determined by the Engineer, temporary cover shall become the property of the Contractor and be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbances, including holes and depressions, caused by the installation and removal of the temporary cover shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

The Contractor shall maintain the temporary cover throughout the contract to prevent displacement or migration of the material on the slope or stockpiled.

Temporary cover shall be maintained to minimize exposure of the protected area. Restrainers shall be relocated and secured as needed to restrain the temporary cover fabric in place. Temporary cover that breaks free shall be immediately secured. Holes, tears, and voids in the temporary cover fabric shall be patched, repaired, or replaced. When patches or repairs are unacceptable as determined by the Engineer, the temporary cover shall be replaced.

Temporary cover shall be repaired or replaced on the same day when the damage occurs. Damage to the temporary cover resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor’s expense.

MEASUREMENT AND PAYMENT

The quantity of temporary cover to be paid for will be measured by the square meter for the actual area covered.

The contract price paid per square meter for temporary cover shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary cover, complete in place, including trench excavation and backfill, maintenance, and removal of temporary cover, as shown in the Contractor’s Storm Water Pollution Prevention Plan, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

No adjustment of compensation will be made for any increase or decrease in the quantities of temporary cover required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to temporary cover.

10-1.06 TEMPORARY DRAINAGE FACILITIES

Temporary culverts and inlets shall be furnished, installed, maintained, and later removed as shown on the plans, as specified in these special provisions and as directed by the Engineer.

The size and type of temporary culvert and inlets to be installed at each location shall be at the option of the Contractor; however, the culvert shall be capable of sustaining the intended load and of discharging a quantity of water equivalent to the type and size of culvert and inlets shown on the plans. Adequacy as to equivalent strength and capacity shall be subject to approval, in writing, by the Engineer.

Used materials may be installed provided the used materials are good, sound and are suitable for the purpose intended, as determined by the Engineer.

Excavation and backfill for temporary culverts and inlets shall be performed in a manner that will provide adequate support for the culvert and inlets with a firm, nonsettling foundation for the roadbeds to be constructed over the culverts.

Temporary culverts and inlets that are damaged from any cause during the progress of the work shall be repaired or replaced by the Contractor at the Contractor's expense.

When no longer required for the work as determined by the Engineer, temporary culverts and inlets shall be removed. Removed facilities shall become the property of the Contractor and shall be removed from the site of the work, except as otherwise provided in this section.

Removed temporary culverts that are not damaged may be installed in the permanent work provided the culverts conform to the requirements specified for the permanent work and the culverts are new when installed as temporary culverts.

Trenches and pits caused by the removal of temporary culverts and inlets shall be backfilled in conformance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

Regardless of the sizes or kinds of temporary culverts installed, temporary culverts will be measured and paid for by the meter for the sizes of temporary culverts shown on the plans and listed in the Engineer's Estimate in the same manner specified for corrugated metal pipe in Section 66-4.01, "Measurement," and Section 66-4.02, "Payment," of the Standard Specifications.

Regardless of the sizes and kinds of temporary inlets installed, temporary inlets will be measured as units determined from actual count in place on drainage quantity sheet D-76.

Full compensation for maintaining, removing and disposing of temporary culverts shall be considered as included in the contract prices paid per meter for the various sizes or kinds of temporary culverts and no additional compensation will be allowed therefor.

Full compensation for maintaining, removing and disposing of temporary inlets shall be considered as included in the contract unit price paid per for the temporary inlet and no additional compensation will be allowed therefor.

10-1.07 TEMPORARY CONCRETE WASHOUT FACILITY

Temporary concrete washout facilities shall be constructed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Attention is directed to "Water Pollution Control" of these special provisions.

Temporary concrete washout facilities shall be one of the water pollution control practices for waste management and materials pollution control. The Storm Water Pollution Prevention Plan shall include the use of temporary concrete washout facilities.

MATERIALS

Plastic Liner

Plastic liner shall be single ply, new polyethylene sheeting, a minimum of 0.25-mm thick and shall be free of holes, punctures, tears or other defects that compromise the impermeability of the material. Plastic liner shall not have seams or overlapping joints.

Gravel-filled Bags

Gravel bag fabric shall be non-woven polypropylene geotextile (or comparable polymer) and shall conform to the following requirements:

Specification	Requirements
Mass per unit area, grams per square meter, min. ASTM Designation: D 5261	270
Grab tensile strength (25-mm grip), kilonewtons, min. ASTM Designation: D4632*	0.89
Ultraviolet stability, percent tensile strength retained after 500 hours, ASTM Designation: D4355, xenon arc lamp method	70

* or appropriate test method for specific polymer

Gravel bags shall be between 600 mm and 800 mm in length, and between 400 mm and 500 mm in width.

Yarn used for binding gravel bags shall be as recommended by the manufacturer or bag supplier and shall be of a contrasting color.

Gravel shall be between 10 mm and 20 mm in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials.

The opening of gravel-filled bags shall be secured to prevent gravel from escaping. Gravel-filled bags shall be between 13 kg and 22 kg in mass.

Straw Bales

Straw for straw bales shall conform to the provisions in Section 20-2.06, "Straw," of the Standard Specifications.

Straw bales shall be a minimum of 360 mm in width, 450 mm in height, 900 mm in length and shall have a minimum mass of 23 kg. The straw bale shall be composed entirely of vegetative matter, except for binding material.

Straw bales shall be bound by either wire, nylon or polypropylene string. Jute or cotton binding shall not be used. Baling wire shall be a minimum 1.57 mm in diameter. Nylon or polypropylene string shall be approximately 2 mm in diameter with 360 N of breaking strength.

Stakes

Stakes shall be wood or metal. Wood stakes shall be untreated fir, redwood, cedar, or pine, shall be cut from sound timber, and shall be straight and free from loose or unsound knots and other defects which would render them unfit for the purpose intended. Wood stakes shall be minimum 50 mm x 50 mm in size. Metal stakes may be used as an alternative, and shall be a minimum 13 mm in diameter. Stakes shall be a minimum 1.2 m in length. The tops of the metal stakes shall be bent at a 90-degree angle or capped with an orange or red plastic safety cap that fits snugly to the metal stake. The Contractor shall submit a sample of the metal stake and plastic cap, if used, for Engineer's approval prior to installation.

Staples

Staples shall be as shown on the plans. An alternative attachment device such as geotextile pins or plastic pegs may be used instead of staples. The Contractor shall submit a sample of the alternative attachment device for Engineer's approval prior to installation.

Signs

Wood posts for signs shall conform to the provisions in Section 56-2.02B, "Wood Posts," of the Standard Specifications. Lag screws shall conform to the provisions in Section 56-2.02D, "Sign Panel Fastening Hardware," of the Standard Specifications.

Plywood shall be freshly painted for each installation with not less than 2 applications of flat white paint. Sign letters shown on the plans shall be stenciled with commercial quality exterior black paint. Testing of paint will not be required.

INSTALLATION

Temporary concrete washout facilities shall be as follows:

A. Temporary concrete washout facilities shall be installed prior to beginning placement of concrete and located a minimum of 15 m from storm drain inlets, open drainage facilities, and water courses unless determined infeasible by the Engineer. Temporary concrete washout facilities shall be located away from construction traffic or access areas at a location determined by the Contractor and approved by the Engineer.
B. A sign shall be installed adjacent to each washout facility at a location determined by the Contractor and approved by the Engineer. Signs shall be installed in conformance with the provisions in Section 56-2.03, "Construction," and Section 56-2.04, "Sign Panel Installation," of the Standard Specifications.
C. The length and width of a temporary concrete washout facility may be increased from the minimum dimensions shown on the plans, at the Contractor's expense and upon approval of the Engineer.
D. Temporary concrete washout facilities shall be constructed in sufficient quantity and size to contain liquid and concrete waste generated by washout operations for concrete wastes. These facilities shall be constructed to contain liquid and concrete waste without seepage, spillage or overflow.
E. Berms for below grade temporary concrete washout facilities shall be constructed from compacted native material. Gravel may be used in conjunction with compacted native material.
F. Plastic liner shall be installed in below grade temporary concrete washout facilities.

Details for an alternative temporary concrete washout facility shall be submitted to the Engineer for approval at least 7 days prior to installation.

When temporary concrete washout facilities are no longer required for the work, as determined by the Engineer, the hardened concrete and liquid residue shall be removed and disposed of in conformance with the provisions in Section 15-3.02, "Removal Methods," of the Standard Specifications. Temporary concrete washout facilities shall become the property of the Contractor and be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary concrete washout facilities shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

Temporary concrete washout facilities shall be maintained to provide adequate holding capacity with a minimum freeboard of 300 mm. Maintaining temporary concrete washout facilities shall include removing and disposing of hardened

concrete and returning the facilities to a functional condition. Hardened concrete materials shall be removed and disposed of in conformance with the provisions in Section 15-3.02, "Removal Methods," of the Standard Specifications. Holes, rips, and voids in the plastic liner shall be patched and repaired by taping or the plastic liner shall be replaced. Plastic liner shall be replaced when patches or repairs compromise the impermeability of the material as determined by the Engineer.

Gravel bags shall be replaced when the bag material is ruptured or when the yarn has failed, allowing the bag contents to spill out.

Temporary concrete washout facility shall be repaired or replaced on the same day when the damage occurs. Damage to the temporary concrete washout facility resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

MEASUREMENT AND PAYMENT

The quantity of temporary concrete washout facility to be paid for will be measured as unit determined from actual count in place.

The contract unit price paid for temporary concrete washout facility shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in constructing temporary concrete washout facility, complete in place, including excavation and backfill, maintenance, and removal of temporary concrete washout facility, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

No adjustment of compensation will be made for any increase or decrease in the quantities of temporary concrete washout facility required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to temporary concrete washout facility.

10-1.08 TEMPORARY SILT FENCE

Temporary silt fence shall be furnished, installed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Attention is directed to "Water Pollution Control" of these special provisions.

Temporary silt fence shall be one of the water pollution control practices for sediment control. The Storm Water Pollution Prevention Plan shall include the use of temporary silt fence.

MATERIALS

At the Contractor's option, temporary silt fence shall be prefabricated or constructed with silt fence fabric, posts, and fasteners.

Silt Fence Fabric

Silt fence fabric shall be geotextile manufactured from woven polypropylene or polymer material. Silt Fence Fabric may be virgin or recycled, or a combination of virgin and recycled polymer materials. No virgin or recycled polymer materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance to the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Silt fence fabric shall conform to the following requirements:

Specification	Requirements
Width, mm, min.	900
Grab tensile strength (25-mm grip), kilonewtons, min. in each direction ASTM Designation: D 4632*	0.55
Elongation, percent minimum in each direction ASTM Designation: D 4632*	15
Permittivity, 1/sec., min. ASTM Designation: D 4491	0.05
Flow rate, liters per minute per square meter, min. ASTM Designation: D 4491	400
Ultraviolet stability, percent tensile strength retained after 500 hours, min. ASTM Designation: D 4355 (xenon-arc lamp and water spray weathering method)	70

* or appropriate test method for specific polymer

Posts

Posts for temporary silt fence shall be one of the following:

C. Posts shall be untreated fir or pine, minimum 34 mm x 40 mm in size, and 1.2 m in length. One end of the post shall be pointed.
D. Posts shall be steel and have a "U", "T", "L" or other cross sectional shape that can resist failure by lateral loads. The steel posts shall have a minimum mass per length of 1.1 kg/m and a minimum length of 1.2 m. One end of the steel posts shall be pointed and the other end shall be capped with an orange or red plastic safety cap which fits snugly to the steel post. The Contractor shall submit to the Engineer for approval a sample of the capped steel post prior to installation.

Fasteners

Fasteners for attaching silt fence fabric to posts shall be as follows:

C. When prefabricated silt fence is used, posts shall be inserted into sewn pockets.
D. Silt fence fabric shall be attached to wooden posts with nails or staples as shown on the plans or as recommended by the manufacturer or supplier. Tie wire or locking plastic fasteners shall be used to fasten the silt fence fabric to steel posts. Maximum spacing of fasteners shall be 200 mm along the length of the steel post.

INSTALLATION

Temporary silt fence shall be installed parallel with the slope contour in reaches not to exceed 150 m. A reach is considered a continuous run of temporary silt fence from end to end or from an end to an opening, including joined panels. Each reach shall be constructed so that the elevation at the base of the fence does not deviate from the contour more than one third of the fence height.

The silt fence fabric shall be installed on the side of the posts facing the slope. The silt fence fabric shall be anchored in a trench as shown on the plans. The trench shall be backfilled and mechanically or hand tamped to secure the silt fence fabric in the bottom of the trench.

Mechanically pushing 300 mm of the silt fence fabric vertically through the soil may be allowed if the Contractor can demonstrate to the Engineer that the silt fence fabric will not be damaged and will not slip out of the soil, resulting in sediment passing under the silt fence fabric.

At the option of the Contractor, the maximum post spacing may increase to 3 m if the fence is reinforced by a wire or plastic material by prefabrication or by field installation. The field-assembled reinforced temporary silt fence shall be able to retain saturated sediment without collapsing.

Temporary silt fence shall be joined as shown on the plans. The tops of the posts shall be tied together by minimum of 2 wraps of tie wire of a minimum 1.5 mm diameter. The silt fence fabric shall be attached to the posts at the joint as specified in these special provisions.

Temporary silt fence shall be repaired or replaced at the expense of the Contractor on the same day when the damage occurs.

When no longer required as determined by the Engineer, temporary silt fence shall become the property of the Contractor and be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. Trimming the silt fence fabric and leaving it in place will not be allowed.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary silt fence shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

Temporary silt fence shall be maintained to provide a sediment holding capacity of approximately one-third the height of the silt fence fabric above ground. When sediment exceeds this height, or when directed by the Engineer, sediment shall be removed. The removed sediment shall be deposited within the project limits in such a way that the sediment is not subject to erosion by wind or by water.

Temporary silt fence shall be repaired or replaced on the same day when the damage occurs. Damage to the temporary silt fence resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor’s expense.

MEASUREMENT AND PAYMENT

The quantity of temporary silt fence to be paid for will be measured by the meter, parallel with the ground slope along the line of the installed temporary silt fence, deducting the widths of openings.

The contract price paid per meter for temporary silt fence shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary silt fence, complete in place, including trench excavation and backfill, maintenance, and removal of temporary silt fence, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

No adjustment of compensation will be made for any increase or decrease in the quantities of temporary silt fence required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to temporary silt fence.

10-1.09 TEMPORARY FENCE (TYPE ESA)

Temporary fence (Type ESA) shall be furnished, installed, maintained, and later removed in conformance with the details shown on the plans, as specified in these special provisions and as directed by the Engineer.

MATERIALS

Used materials may be installed provided the used materials conform to these special provisions. Materials for temporary fence (Type ESA) shall conform to the following:

High Visibility Fabric

High visibility fabric shall be machine produced mesh manufactured from polypropylene or polyethylene and shall be orange in color. High visibility fabric may be virgin or recycled polymer materials, or a combination of virgin and recycled polymer materials. No virgin or recycled polymer materials shall contain biodegradable filler materials that degrade the physical or chemical characteristics of the finished fabric. High visibility fabric shall be fully stabilized ultraviolet (UV) resistant. High visibility fabric shall be a minimum of 1.22 m in width with a maximum mesh opening of 50 mm x 50 mm. High visibility fabric shall be furnished in one continuous width and shall not be spliced to conform to the specified width dimension.

Posts

Posts for temporary fence (Type ESA) shall be of one of the following:

A. Posts shall be fir or pine, a minimum of 38 mm x 50 mm in size, and a minimum 1.6 m in length. One end of the post shall be pointed. Posts shall not be treated with wood preservative.
B. Posts shall be steel and have a "U", "T", "L" or other cross sectional shape that resists failure by lateral loads. Steel posts shall have a minimum mass per length of 1.1 kg/m and a minimum length of 1.6 m. One end of the steel post shall be pointed and the other end shall have a high visibility colored top.

Fasteners

Fasteners for attaching high visibility fabric to the posts shall be as follows:

A. The high visibility fabric shall be attached to wooden posts with commercial quality nails or staples, or as recommended by the manufacturer or supplier, as determined by the Engineer.
B. Tie wire or locking plastic fasteners shall be used for attaching the high visibility fabric to steel posts. Maximum spacing of tie wire or fasteners shall be 600 mm along the length of the steel post.

INSTALLATION

Temporary fence (Type ESA) shall be installed as follows:

A. Posts shall be driven into the soil a minimum of 400 mm. Posts shall be spaced at 2-m centers maximum and shall at all times support the fence in a vertical, upright position.
B. Temporary fence (Type ESA) shall be constructed prior to any clearing and grubbing work and a sufficient distance from protected plants to enclose all of the foliage canopy and not encroach upon visible roots of the plants.
C. Temporary fence (Type ESA) shall be located to be unobstructed from view, as determined by the Engineer.

When no longer required for the work, as determined by the Engineer, temporary fence (Type ESA) shall be removed. Removed temporary fence (Type ESA) shall become the property of the Contractor and shall be removed from the site of the work, except when reused as provided in this section.

Holes caused by the removal of temporary fence (Type ESA) shall be backfilled in conformance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

Temporary fence (Type ESA) that is damaged during the progress of the work shall be repaired or replaced by the Contractor the same day the damage occurred.

MEASUREMENT AND PAYMENT

Temporary fence (Type ESA) shall be measured in the manner specified for permanent fences in Section 80, "Fences," of the Standard Specifications.

The contract price paid per meter for temporary fence (Type ESA) shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in constructing temporary fence (Type ESA) complete in place, including maintenance and removal and disposal of materials, as specified in these special provisions, and as directed by the Engineer.

10-1.10 PRESERVATION OF PROPERTY

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications, “Clearing and Grubbing” elsewhere in these special provisions, and these special provisions.

Existing trees, shrubs and other plants, that are not to be removed as shown on the plans or specified in these special provisions, and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree replacement shall be 600 mm box and the minimum size of shrub replacement shall be No. 15 container. Replacement ground cover plants shall be from flats and shall be planted 300 mm on center. Replacement of Carpobrotus ground cover plants shall be from cuttings and shall be planted 300 mm on center. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-l.13 of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips. The chipped material shall be spread within the highway right of way at locations designated by the Engineer.

Replacement planting of injured or damaged trees, shrubs and other plants shall be completed not less than 20 working days prior to acceptance of the contract. Replacement plants shall be watered as necessary to maintain the plants in a healthy condition.

10-1.11 TEMPORARY CONSTRUCTION ENTRANCE

Temporary construction entrance shall be constructed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Attention is directed to "Water Pollution Control" of these special provisions.

Temporary construction entrance shall be one of the water pollution control practices for tracking control. The Storm Water Pollution Prevention Plan shall include the use of temporary construction entrance.

At the option of the Contractor, temporary construction entrance shall be Type 1 or Type 2 .

MATERIALS

Temporary Entrance Fabric

Temporary entrance fabric shall be manufactured from polyester, nylon or polypropylene material or any combination thereof. Temporary entrance fabric shall be a nonwoven, needle-punched fabric, free of any needles which may have broken off during the manufacturing process. Temporary entrance fabric shall be permeable and shall not act as a wicking agent.

Temporary entrance fabric shall be manufactured from virgin or recycled, or a combination of virgin and recycled, polymer materials. No virgin or recycled materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance to the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Temporary entrance fabric shall conform to the following requirements:

Specification	Requirements
Mass per unit area, grams per square meter, min. ASTM Designation: D 5261	235
Grab tensile strength (25-mm grip), kilonewtons, min. ASTM Designation: D4632*	0.89
Elongation at break, percent min. ASTM Designation: D4632*	50
Toughness, kilonewtons, min. (percent elongation x grab tensile strength)	53

* or appropriate test method for specific polymer

Rocks

Rocks shall be angular to subangular in shape, and shall conform to the material quality requirements in Section 72-2.02, "Materials," of the Standard Specifications for apparent specific gravity, absorption, and durability index. Rocks used for the temporary entrance shall conform to the following sizes:

Square Screen Size (mm)	Percentage Passing
150	100
75	0-20

Corrugated Steel Panels

Corrugated steel panels shall be prefabricated and shall be pressed or shop welded, with a slot or hooked section to facilitate coupling at the ends of the panels.

INSTALLATION

Temporary construction entrance shall be installed as follows:

A. Prior to placing the temporary entrance fabric, the areas shall be cleared of all trash and debris. Vegetation shall be removed to the ground level. Trash, debris, and removed vegetation shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.
B. A sump shall be constructed within 6 m of each temporary construction entrance as shown on the plans. The exact location of the sump will be determined by the Engineer.
C. Before placing the temporary entrance fabric, the ground shall be graded to a uniform plane. The relative compaction of the top 0.5-m shall be not less than 90 percent. The ground surface shall be free of sharp objects that may damage the temporary entrance fabric, and shall be graded to drain to the sump as shown on the plans.
D. Temporary entrance fabric shall be positioned longitudinally along the alignment of the entrance, as directed by the Engineer.
E. The adjacent ends of the fabric shall be overlapped a minimum length of 300 mm.
F. Rocks to be placed directly over the fabric shall be spread in the direction of traffic, longitudinally and along the alignment of the temporary construction entrance.
G. During spreading of the rocks, vehicles or equipment shall not be driven directly on the fabric. A layer of rocks of minimum 150 mm thick shall be placed between the fabric and the spreading equipment to prevent damage to the fabric.
H. For Type 2 temporary construction entrance, a minimum of 6 coupled panel sections shall be installed for each temporary construction entrance. Prior to installing the panels, the ground surface shall be cleared of all debris to ensure uniform contact with the ground surface.

Fabric damaged during rock placement shall be repaired by placing a new piece of fabric over the damaged area. The piece of fabric shall be large enough to cover the damaged area and provide a minimum 450-mm overlap on all edges.

Details for alternative temporary construction entrance shall be submitted to the Engineer for approval at least 7 days prior to installation.

If buildup of soil and sediment deter the function of the temporary construction entrance, the Contractor shall immediately remove and dispose of the soil and sediment, and install additional corrugated steel panels and spread additional rocks to increase the capacity of the temporary construction entrance at the Contractor's expenses.

When no longer required as determined by the Engineer, temporary construction entrances shall become the property of the Contractor and be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary construction entrance, including the sumps, shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

While the temporary construction entrance is in use, pavement shall be cleaned and sediment removed at least once a day, and as often as necessary when directed by the Engineer. Soil and sediment or other extraneous material tracked onto existing pavement shall not be allowed to enter drainage facilities.

MAINTENANCE

The Contractor shall maintain temporary construction entrance throughout the contract or until removed. The Contractor shall prevent displacement or migration of the rock surfacing or corrugated steel panels. Any significant depressions resulted from settlement or heavy equipment shall be repaired by the Contractor, as directed by the Engineer.

Temporary construction entrance shall be maintained to minimize tracking of soil and sediment onto existing public roads.

Temporary construction entrance shall be repaired or replaced on the same day when the damage occurs. Damage to the temporary construction entrance resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor’s expense.

MEASUREMENT AND PAYMENT

The quantity of temporary construction entrance to be paid for will be measured as unit determined from actual count in place.

The contract unit price paid for temporary construction entrance shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing temporary construction entrance, complete in place, including excavation and backfill, maintenance, and removal of temporary construction entrance, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

No adjustment of compensation will be made for any increase or decrease in the quantities of temporary construction entrance required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to temporary construction entrance.

10-1.12 FISH FRIENDLY DIVERSION

Fish-Friendly Diversion shall be provided as shown on the plans and these special provisions.

Attention is directed to “Relations with California Department of Fish and Game”, “Relations With California Regional Water Quality Control Board”, “Environmentally Sensitive Areas”, and “Mitigation Measures” elsewhere in these special provisions.

Caltrans is the lead agency in relations with approving agencies.

Contractor shall not perform any work in the River, from top of bank to top of bank, from October 15th to June 1st, or as per the most restrictive of the regulatory agency permits.

Contractor shall not perform any work in the low flow channel from October 15th to June 1st, or as per the most restrictive of the regulatory agency permits.

For the purposes of River restoration, the Contractor shall survey the River areas to be disturbed from top of bank to top of bank. The River survey shall be submitted to the Engineer, prior to commencing with work on Fish-Friendly Diversion Facilities and the Willow Street Viaduct (Widen) or storm drain outfall. The survey shall be of sufficient accuracy to document the River configuration prior to the commencement of work.

Fish-Friendly Diversion shall be complete, in place, prior to work on Willow Street Viaduct (Widen), storm drain outfall, or rock slope protection.

Contractor shall restore the River to pre-existing conditions or/and in accordance with California Dept of Fish and Game, US Army Corp of Engineers, Santa Clara Valley Water District and the Engineer after each construction season, prior to October 15th, and at completion of work.

Contractor shall be solely responsible for provision of adequate site drainage at all times during the course of the work. The contractor shall construct cofferdam and culverts as shown on the plans for the purpose of conveying flows through the construction area.

Materials

Special attention shall be directed, but not limited, to the following facilities and items to be provided prior, during, and (or) after work on Willow Street Viaduct (Widen) or storm drain outfall:

The cofferdams and/or in-channel berms shall be constructed of clean river run gravel placed in gravel sacks. River run gravel shall have a fines content that is less than 15%. Fines are defined as material that is able to pass through a #20 sieve.

Gravel sacks are to be manufactured from a non-woven material with the following characteristics:

Minimum Weight - 270 grams per square meter nominal

Minimum Grab tensile strength - 0.89 kilonewtons (25-mm grip, each direction)

Plastic sheet shall be commercial quality polyethylene with a minimum thickness of 0.33-mm.

Culvert shall conform to Section 62, "Alternative Culverts" and shall be water tight.

Installation

Contractor shall dewater the bottom of the creek with a temporary construction of a cofferdam on the upstream side beginning June 1st. An impermeable plastic sheet shall be placed in the temporary diversion as shown on the plans. All joints between the edges shall be lapped and joined with commercial quality waterproof tape. All joints between the plastic sheet and pipe shall be sealed with commercial quality waterproof tape. The Contractor shall be responsible for preventing, at his expense, any leakage in the temporary creek diversion system that may interfere with his work.

The type of temporary culverts to be installed shall be at the option of the Contactor, however, the culverts shall be capable of sustaining the intended load, and of discharging a quantity of water equivalent to the type and size of culvert shown on the plans and shall be subject to written approval by the Engineer.

Used materials may be used for the temporary culverts providing the used materials are good, sound, and suitable for the purposed intended and approved, in writing, by the Engineer.

Any portion of the fish friendly diversion facility that is damaged from any cause during the progress of work shall be repaired or replaced by the Contractor at the Contractor's expense.

When no longer required for the work as determined by the Engineer, the fish friendly diversion shall be removed in accordance with 7-1.13, "Disposal of Materials Outside the Highway Right of Way," of the Standard Specifications.

MEASUREMENT AND PAYMENT

The contract lump sum price paid for the fish-friendly diversion facilities, shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in fish-friendly diversion facilities, including maintenance, dewatering, pumping as required to keep work area dry, replacement and repairs in the event of a washout, removal and reconstruction of facilities during and after Willow Street Viaduct (Widen), storm drain outfall construction, or rock slope protection, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.13 COOPERATION

Attention is directed to Section 7-1.14, "Cooperation," and Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

It is anticipated that work by other contractors may be in progress adjacent to or within the limits of this project during progress of the work on this contract. The other contracts adjacent to or within the limits of this project are as follows:

Contract No. 04-439614, widening north portion of Route 87 in San Jose from West Virginia Street Overcrossing to 0.1 km north of Julian Street Undercrossing (KP 7.9 to KP 10.1).

Contract No. 04-244604, to install highway planting and irrigation on Route 87 in San Jose from West Virginia Street Overcrossing to San Carlos Street Overcrossing (KP 7.7 to KP 8.9) and on Route 280 in San Jose from Vine Street Undercrossing to Bird Avenue Overcrossing (KP 3.7 to KP 4.5).

Contract No. 04-438104, to construct interchange modification on Route 85 in San Jose from Santa Teresa Blvd. to 0.1 km east of Almaden Expressway Overcrossing (KP 7.8 to KP 9.5) and from N85-N87 connector overcrossing to 0.04 km north of Branham Lane Overcrossing (KP 0.0 to KP 1.6).

Contract No. 04-247304, to construct drainage improvements on Route 87 at Communications Hill from 0.3 km north of Hillsdale Ave. Undercrossing to 1.1 km south of Curtner Ave Undercrossing (KP 3.1 to KP 3.8).

Contract No. (not available at time of advertisement), to construct ramp widening on the southbound Route 87off-ramp at the Capitol Expressway Interchange (KP 2.2 to KP 2.5).

Santa Clara County Roads and Airports Contract, to construct electrical conduit along Almaden Expressway and traffic signal modifications at the northbound Route 87 on-ramp at Almaden Expressway (KP 5.4 to KP 5.6).

Joint Powers Board Contract, to construct seismic retrofit on the Joint Powers Board bridge structure over Willow Street (KP 7.3).

Santa Clara County Valley Transportation Authority Contract, to construct light rail station modifications at various stations locations including Capitol Station (KP 2.1 to KP 2.4), Curtner Station (KP 4.4 to KP 4.6), Tamien Station (KP 6.6 to KP 6.8), and Virginia Station (KP 7.6 to KP 7.8).

City of San Jose Contract, to replace the bridge structure over Guadalupe River at Willow Glen Way.

The progress schedules for other work in progress, if available, may be inspected by the Contractor upon approval by the Engineer. Such progress schedules are tentative and cannot be guaranteed to be accurate.

The Contractor shall attend joint weekly meeting, to be organized by the Engineer with other Contractors and/or operation managers on adjacent projects in order to minimize conflicts and coordinate traffic control. The Contractor shall coordinate with and accommodate other segment contractors when preparing operations and schedules.

10-1.14 PROGRESS SCHEDULE (CRITICAL PATH METHOD)

The Contractor shall submit to the Engineer practicable critical path method (CPM) progress schedules in conformance with these special provisions. Whenever the term "schedule" is used in this section it shall mean CPM progress schedule.

Attention is directed to "Payments" of Section 5 of these special provisions.

The provisions in Section 8-1.04, "Progress Schedule," of the Standard Specifications shall not apply.

DEFINITIONS

The following definitions shall apply to this section:

A. ACTIVITY.—A task, event or other project element on a schedule that contributes to completing the project. Activities have a description, start date, finish date, duration and one or more logic ties.
B. BASELINE SCHEDULE.—The initial schedule representing the Contractor's work plan on the first working day of the project.
C. CONTRACT COMPLETION DATE.—The current extended date for completion of the contract shown on the weekly statement of working days furnished by the Engineer in conformance with the provisions in Section 8-1.06, "Time of Completion," of the Standard Specifications.
D. CRITICAL PATH.—The longest continuous chain of activities for the project that has the least amount of total float of all chains. In general, a delay on the critical path will extend the scheduled completion date.
E. CRITICAL PATH METHOD (CPM).—A network based planning technique using activity durations and the relationships between activities to mathematically calculate a schedule for the entire project.
F. DATA DATE.—The day after the date through which a schedule is current. Everything occurring earlier than the data date is "as-built" and everything on or after the data date is "planned."
G. EARLY COMPLETION TIME.—The difference in time between an early scheduled completion date and the contract completion date.
H. FLOAT.—The difference between the earliest and latest allowable start or finish times for an activity.
I. MILESTONE.—An event activity that has zero duration and is typically used to represent the beginning or end of a certain stage of the project.
J. NARRATIVE REPORT.—A document submitted with each schedule that discusses topics related to project progress and scheduling.
K. NEAR CRITICAL PATH.—A chain of activities with total float exceeding that of the critical path but having no more than 10 working days of total float.
L. SCHEDULED COMPLETION DATE.—The planned project finish date shown on the current accepted schedule.
M. STATE OWNED FLOAT ACTIVITY.—The activity documenting time saved on the critical path by actions of the State. It is the last activity prior to the scheduled completion date.
N. TIME IMPACT ANALYSIS.—A schedule and narrative report developed specifically to demonstrate what effect a proposed change or delay has on the current scheduled completion date.
O. TOTAL FLOAT.—The amount of time that an activity or chain of activities can be delayed before extending the scheduled completion date.
P. UPDATE SCHEDULE.—A current schedule developed from the baseline or subsequent schedule through regular monthly review to incorporate as-built progress and any planned changes.

GENERAL REQUIREMENTS

The Contractor shall submit to the Engineer baseline, monthly update and final update schedules, each consistent in all respects with the time and order of work requirements of the contract. The project work shall be executed in the sequence indicated on the current accepted schedule.

Schedules shall show the order in which the Contractor proposes to carry out the work with logical links between time-scaled work activities, and calculations made using the critical path method to determine the controlling operation or operations. The Contractor is responsible for assuring that all activity sequences are logical and that each schedule shows a coordinated plan for complete performance of the work.

The Contractor shall produce schedules using computer software and shall furnish compatible software for the Engineer's exclusive possession and use. The Contractor shall furnish network diagrams, narrative reports, tabular reports and schedule data as parts of each schedule submittal.

Schedules shall include, but not be limited to, activities that show the following that are applicable to the project:

A. Project characteristics, salient features, or interfaces, including those with outside entities, that could affect time of completion.
B. Project start date, scheduled completion date and other milestones.
C. Work performed by the Contractor, subcontractors and suppliers.
D. Submittal development, delivery, review and approval, including those from the Contractor, subcontractors and suppliers.
E. Procurement, delivery, installation and testing of materials, plants and equipment.
F. Testing and settlement periods.
G. Utility notification and relocation.
H. Erection and removal of falsework and shoring.
I. Major traffic stage switches.
J. Finishing roadway and final cleanup.
K. State-owned float as the predecessor activity to the scheduled completion date.

Schedules shall have not less than 50 and not more than 500 activities, unless otherwise authorized by the Engineer. The number of activities shall be sufficient to assure adequate planning of the project, to permit monitoring and evaluation of progress, and to do an analysis of time impacts.

Schedule activities shall include the following:

A. A clear and legible description.
B. Start and finish dates.
C. A duration of not less than one working day, except for event activities, and not more than 20 working days, unless otherwise authorized by the Engineer.
D. At least one predecessor and one successor activity, except for project start and finish milestones.
E. Required constraints.
F. Codes for responsibility, stage, work shifts, location and contract pay item numbers.

The Contractor may show early completion time on any schedule provided that the requirements of the contract are met. Early completion time shall be considered a resource for the exclusive use of the Contractor. The Contractor may increase early completion time by improving production, reallocating resources to be more efficient, performing sequential activities concurrently or by completing activities earlier than planned. The Contractor may also submit for approval a cost reduction incentive proposal in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications that will reduce time of construction.

The Contractor may show a scheduled completion date that is later than the contract completion date on an update schedule, after the baseline schedule is accepted. The Contractor shall provide an explanation for a late scheduled completion date in the narrative report that is included with the schedule.

State-owned float shall be considered a resource for the exclusive use of the State. The Engineer may accrue State-owned float by the early completion of review of any type of required submittal when it saves time on the critical path. The Contractor shall prepare a time impact analysis, when requested by the Engineer, to determine the effect of the action in conformance with the provisions in "Time Impact Analysis" specified herein. The Engineer will document State-owned float by directing the Contractor to update the State-owned float activity on the next update schedule. The Contractor shall include a log of the action on the State-owned float activity and include a discussion of the action in the narrative report. The Engineer may use State-owned float to mitigate past, present or future State delays by offsetting potential time extensions for contract change orders.

The Engineer may adjust contract working days for ordered changes that affect the scheduled completion date, in conformance with the provisions in Section 4-1.03, "Changes," of the Standard Specifications. The Contractor shall prepare a time impact analysis to determine the effect of the change in conformance with the provisions in "Time Impact Analysis" specified herein, and shall include the impacts acceptable to the Engineer in the next update schedule. Changes that do not affect the controlling operation on the critical path will not be considered as the basis for a time adjustment. Changes that do affect the controlling operation on the critical path will be considered by the Engineer in decreasing time or granting an extension of time for completion of the contract. Time extensions will only be granted if the total float is absorbed and the scheduled completion date is delayed one or more working days because of the ordered change.

The Engineer's review and acceptance of schedules shall not waive any contract requirements and shall not relieve the Contractor of any obligation thereunder or responsibility for submitting complete and accurate information. Schedules that are rejected shall be corrected by the Contractor and resubmitted to the Engineer within 5 working days of notification by the Engineer, at which time a new review period of one week will begin.

Errors or omissions on schedules shall not relieve the Contractor from finishing all work within the time limit specified for completion of the contract. If, after a schedule has been accepted by the Engineer, either the Contractor or the Engineer discover that any aspect of the schedule has an error or omission, it shall be corrected by the Contractor on the next update schedule.

COMPUTER SOFTWARE

The Contractor shall submit to the Engineer for approval a description of proposed software before delivery. The software shall be the current version of Primavera SureTrak Project Manager for Windows, or equal, and shall be compatible with Windows NT (version 4.0) operating system. If software other than SureTrak is proposed, it shall be capable of generating files that can be imported into SureTrak.

The Contractor shall furnish schedule software and all original software instruction manuals to the Engineer with submittal of the baseline schedule. The furnished schedule software shall become the property of the State and will not be returned to the Contractor. The State will compensate the Contractor in conformance with the provisions in Section 4-1.03, "Extra Work," of the Standard Specifications for replacement of software which is damaged, lost or stolen after delivery to the Engineer.

The Contractor shall instruct the Engineer in the use of the software and provide software support until the contract is accepted. Within 20 working days of contract approval, the Contractor shall provide a commercial 8-hour training session for 2 Department employees in the use of the software at a location acceptable to the Engineer. It is recommended that the Contractor also send at least 2 employees to the same training session to facilitate development of similar knowledge and skills in the use of the software. If software other than SureTrak is furnished, then the training session shall be a total of 16-hours for each Department employee.

NETWORK DIAGRAMS, REPORTS AND DATA

The Contractor shall include the following for each schedule submittal:

A. Two sets of originally plotted, time-scaled network diagrams.
B. Two copies of a narrative report.
C. Two copies of each of 3 sorts of the CPM software-generated tabular reports.
D. One 1.44-megabyte 90 mm (3.5 inch) floppy diskette containing the schedule data.

The time-scaled network diagrams shall conform to the following:

A. Show a continuous flow of information from left to right.
B. Be based on early start and early finish dates of activities.
C. Clearly show the primary paths of criticality using graphical presentation.
D. Be prepared on E-size sheets, 860 mm x 1120 mm (34 inch x 44 inch).
E. Include a title block and a timeline on each page.

The narrative report shall be organized in the following sequence with all applicable documents included:

A. Contractor's transmittal letter.
B. Work completed during the period.
C. Identification of unusual conditions or restrictions regarding labor, equipment or material; including multiple shifts, 6-day work weeks, specified overtime or work at times other than regular days or hours.
D. Description of the current critical path.
E. Changes to the critical path and scheduled completion date since the last schedule submittal.
F. Description of problem areas.
G. Current and anticipated delays:

    1. Cause of delay.
    2. Impact of delay on other activities, milestones and completion dates.
    3. Corrective action and schedule adjustments to correct the delay.

H. Pending items and status thereof:

    1. Permits
    2. Change orders
    3. Time adjustments

4. Non-compliance notices

I. Reasons for an early or late scheduled completion date in comparison to the contract completion date.

Tabular reports shall be software-generated and provide information for each activity included in the project schedule. Three different reports shall be sorted by (1) activity number, (2) early start and (3) total float. Tabular reports shall be 215 mm x 280 mm (8 1/2 inch x 11 inch) in size and shall include, as a minimum, the following applicable information:

A. Data date
B. Activity number and description
C. Predecessor and successor activity numbers and descriptions
D. Activity codes
E. Scheduled, or actual and remaining durations (work days) for each activity
F. Earliest start (calendar) date
G. Earliest finish (calendar) date
H. Actual start (calendar) date
I. Actual finish (calendar) date
J. Latest start (calendar) date
K. Latest finish (calendar) date
L. Free float (work days)
M. Total float (work days)
N. Percentage of activity complete and remaining duration for incomplete activities.
O. Lags
P. Required constraints

Schedule submittals will only be considered complete when all documents and data have been provided as described above.

PRE-CONSTRUCTION SCHEDULING CONFERENCE

The Contractor shall schedule and the Engineer will conduct a pre-construction scheduling conference with the Contractor's project manager and construction scheduler within 10 working days of the approval of the contract. At this meeting the Engineer will review the requirements of this section of the special provisions with the Contractor.

The Contractor shall submit a general time-scaled logic diagram displaying the major activities and sequence of planned operations and shall be prepared to discuss the proposed work plan and schedule methodology that comply with the requirements of these special provisions. If the Contractor proposes deviations to the construction staging of the project, then the general time-scaled logic diagram shall also display the deviations and resulting time impacts. The Contractor shall be prepared to discuss the proposal.

At this meeting, the Contractor shall additionally submit the alphanumeric coding structure and the activity identification system for labeling the work activities. To easily identify relationships, each activity description shall indicate its associated scope or location of work by including such terms as quantity of material, type of work, bridge number, station to station location, side of highway (such as left, right, northbound, southbound), lane number, shoulder, ramp name, ramp line descriptor or mainline.

The Engineer will review the logic diagram, coding structure, and activity identification system, and provide any required baseline schedule changes to the Contractor for implementation.

BASELINE SCHEDULE

Beginning the week following the pre-construction scheduling conference, the Contractor shall meet with the Engineer weekly until the baseline schedule is accepted by the Engineer to discuss schedule development and resolve schedule issues.

The Contractor shall submit to the Engineer a baseline schedule within 20 working days of approval of the contract. The Contractor shall allow 3 weeks for the Engineer's review after the baseline schedule and all support data are submitted. In addition, the baseline schedule submittal will not be considered complete until the computer software is delivered and installed for use in review of the schedule.

The baseline schedule shall include the entire scope of work and how the Contractor plans to complete all work contemplated. The baseline schedule shall show the activities that define the critical path. Multiple critical paths and near-critical paths shall be kept to a minimum. A total of not more than 50 percent of the baseline schedule activities shall be critical or near critical, unless otherwise authorized by the Engineer.

The baseline schedule shall not extend beyond the number of working days specified in these special provisions. The baseline schedule shall have a data date of the first working day of the contract and not include any completed work to date. The baseline schedule shall not attribute negative float or negative lag to any activity.

If the Contractor submits an early completion baseline schedule that shows contract completion in less than 85 percent of the working days specified in these special provisions, the baseline schedule shall be supplemented with resource allocations for every task activity and include time-scaled resource histograms. The resource allocations shall be shown to a level of detail that facilitates report generation based on labor crafts and equipment classes for the Contractor and subcontractors. The Contractor shall use average composite crews to display the labor loading of on-site construction activities. The Contractor shall optimize and level labor to reflect a reasonable plan for accomplishing the work of the contract and to assure that resources are not duplicated in concurrent activities. The time-scaled resource histograms shall show labor crafts and equipment classes to be utilized on the contract. The Engineer may review the baseline schedule activity resource allocations using Means Productivity Standards or equivalent to determine if the schedule is practicable.

UPDATE SCHEDULE

The Contractor shall submit an update schedule and meet with the Engineer to review contract progress, on or before the first day of each month, beginning one month after the baseline schedule is accepted. The Contractor shall allow 2 weeks for the Engineer's review after the update schedule and all support data are submitted, except that the review period shall not start until the previous month's required schedule is accepted. Update schedules that are not accepted or rejected within the review period will be considered accepted by the Engineer.

The update schedule shall have a data date of the twenty-first day of the month or other date established by the Engineer. The update schedule shall show the status of work actually completed to date and the work yet to be performed as planned. Actual activity start dates, percent complete and finish dates shall be shown as applicable. Durations for work that has been completed shall be shown on the update schedule as the work actually occurred, including Engineer submittal review and Contractor resubmittal times.

The Contractor may include modifications such as adding or deleting activities or changing activity constraints, durations or logic that do not (1) alter the critical path(s) or near critical path(s) or (2) extend the scheduled completion date compared to that shown on the current accepted schedule. The Contractor shall state in writing the reasons for any changes to planned work. If any proposed changes in planned work will result in (1) or (2) above, then the Contractor shall submit a time impact analysis as described herein.

TIME IMPACT ANALYSIS

The Contractor shall submit a written time impact analysis (TIA) to the Engineer with each request for adjustment of contract time, or when the Contractor or Engineer consider that an approved or anticipated change may impact the critical path or contract progress.

The TIA shall illustrate the impacts of each change or delay on the current scheduled completion date or internal milestone, as appropriate. The analysis shall use the accepted schedule that has a data date closest to and prior to the event. If the Engineer determines that the accepted schedule used does not appropriately represent the conditions prior to the event, the accepted schedule shall be updated to the day before the event being analyzed. The TIA shall include an impact schedule developed from incorporating the event into the accepted schedule by adding or deleting activities, or by changing durations or logic of existing activities. If the impact schedule shows that incorporating the event modifies the critical path and scheduled completion date of the accepted schedule, the difference between scheduled completion dates of the two schedules shall be equal to the adjustment of contract time. The Engineer may construct and utilize an appropriate project schedule or other recognized method to determine adjustments in contract time until the Contractor provides the TIA.

The Contractor shall submit a TIA in duplicate within 15 working days of receiving a written request for a TIA from the Engineer. The Contractor shall allow the Engineer 2 weeks after receipt to approve or reject the submitted TIA. All approved TIA schedule changes shall be shown on the next update schedule.

If a TIA submitted by the Contractor is rejected by the Engineer, the Contractor shall meet with the Engineer to discuss and resolve issues related to the TIA. If agreement is not reached, the Contractor will be allowed 15 days from the meeting with the Engineer to give notice in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications. The Contractor shall only show actual as-built work, not unapproved changes related to the TIA, in subsequent update schedules. If agreement is reached at a later date, approved TIA schedule changes shall be shown on the next update schedule. The Engineer will withhold remaining payment on the schedule contract item if a TIA is requested by the Engineer and not submitted by the Contractor within 15 working days. The schedule item payment will resume on the next estimate after the requested TIA is submitted. No other contract payment will be retained regarding TIA submittals.

FINAL UPDATE SCHEDULE

The Contractor shall submit a final update, as-built schedule with actual start and finish dates for the activities, within 30 days after completion of contract work. The Contractor shall provide a written certificate with this submittal signed by the

Contractor's project manager and an officer of the company stating, "To my knowledge and belief, the enclosed final update schedule reflects the actual start and finish dates of the actual activities for the project contained herein." An officer of the company may delegate in writing the authority to sign the certificate to a responsible manager.

RETENTION

The Department will retain an amount equal to 25 percent of the estimated value of the work performed during each estimate period in which the Contractor fails to submit an acceptable schedule conforming to the requirements of these special provisions as determined by the Engineer. Schedule retentions will be released for payment on the next monthly estimate for partial payment following the date that acceptable schedules are submitted to the Engineer or as otherwise specified herein. Upon completion of all contract work and submittal of the final update schedule and certification, any remaining retained funds associated with this section, "Progress Schedule (Critical Path Method)", will be released for payment. Retentions held in conformance with this section shall be in addition to other retentions provided for in the contract. No interest will be due the Contractor on retention amounts.

PAYMENT

Progress schedule (critical path method) will be paid for at a lump sum price. The contract lump sum price paid for progress schedule (critical path method) shall include full compensation for furnishing all labor, material, tools, equipment, and incidentals, including computer software, and for doing all the work involved in preparing, furnishing, and updating schedules, and instructing and assisting the Engineer in the use of computer software, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Payments for the progress schedule (critical path method) contract item will be made progressively as follows:

A. A total of 25 percent of the item amount or a total of 25 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon achieving all of the following:

    1. Completion of 5 percent of all contract item work.
    2. Acceptance of all schedules and TIAs required to the time when 5 percent of all contract item work is complete.
    3. Delivery of schedule software to the Engineer.
    4. Completion of required schedule software training.

B. A total of 50 percent of the item amount or a total of 50 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon completion of 25 percent of all contract item work and acceptance of all schedules and TIAs required to the time when 25 percent of all contract item work is complete.
C. A total of 75 percent of the item amount or a total of 75 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon completion of 50 percent of all contract item work and acceptance of all schedules and TIAs required to the time when 50 percent of all contract item work is complete.
D. A total of 100 percent of the item amount or a total of 100 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon completion of all contract item work, acceptance of all schedules and TIAs required to the time when all contract item work is complete, and submittal of the certified final update schedule.

If the Contractor fails to complete any of the work or provide any of the schedules required by this section, the Engineer shall make an adjustment in compensation in conformance with the provisions in Section 4-1.03C, "Changes in Character of Work," of the Standard Specifications for the work not performed. Adjustments in compensation for schedules will not be made for any increased or decreased work ordered by the Engineer in furnishing schedules.

10-1.15 TIME-RELATED OVERHEAD

The Contractor will be compensated for time-related overhead in conformance with these special provisions.

Attention is directed to "Beginning of Work, Time of Completion and Liquidated Damages," "Force Account Payment," and "Progress Schedule (Critical Path Method)" of these special provisions.

The provisions in Section 9-1.08, "Adjustment of Overhead Costs," of the Standard Specifications shall not apply.

Time-related overhead shall consist of those overhead costs, including field and home office overhead, that are in proportion to the time required to complete the work. Time-related overhead shall not include costs that are not related to time, including but not limited to, mobilization, licenses, permits, and other charges incurred only once during the contract.

Field office overhead expenses include time-related costs associated with the normal and recurring operations of the construction project, and shall not include costs directly attributable to the work of the contract. Time-related costs of field office overhead include, but are not limited to, salaries, benefits, and equipment costs of project managers, general superintendents, field office managers and other field office staff assigned to the project, and rent, utilities, maintenance, security, supplies, and equipment costs of the project field office.

Home office overhead or general and administrative expenses refer to the fixed costs of operating the Contractor's business. These costs include, but are not limited to, general administration, insurance, personnel and subcontract administration, purchasing, accounting, and project engineering and estimating. Home office overhead costs shall exclude expenses specifically related to other contracts or other businesses of the Contractor, equipment coordination, material deliveries, and consultant and legal fees.

The amount of time-related overhead associated with a reduction in contract time for cost reduction incentive proposals accepted and executed in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications shall be considered a construction cost attributable to the resultant estimated net savings due to the cost reduction incentive.

If the final increased amount of time-related overhead exceeds 149 percent of the contract lump sum price bid, the Contractor shall, within 60 days of the Engineer's written request, submit to the Engineer an audit examination and report performed by an independent Certified Public Accountant of the Contractor's actual overhead costs. The independent Certified Public Accountant's audit examination shall be performed in conformance with the requirements of the American Institute of Certified Public Accountants Attestation Standards. The audit examination and report shall depict the Contractor's project and company-wide financial records and shall specify the actual overall average daily rates for both field and home office overhead for the entire duration of the project, and whether the costs have been properly allocated. The rates of field and home office overhead shall exclude unallowable costs as determined in the Federal Acquisition Regulations, 48 CFR, Chapter 1, Part 31. The audit examination and report shall determine if the rates of field office overhead and home office overhead are:

A. Allowable in conformance with the requirements of the Federal Acquisition Regulations, 48 CFR, Chapter 1, Part 31.
B. Adequately supported by reliable documentation.
C. Related solely to the project under examination.

Within 20 days of receipt of the Engineer's written request, the Contractor shall make its financial records available for audit by the State for the purpose of verifying the actual rate of time-related overhead specified in the audit submitted by the Contractor. The actual rate of time-related overhead specified in the audit, submitted by the Contractor, will be subject to approval by the Engineer.

If the Engineer requests the independent Certified Public Accountant audit, or if it is requested in writing by the Contractor, the contract lump sum payment for time-related overhead, in excess of 149 percent of the lump sum price bid, will be adjusted to reflect the actual rate.

The cost of performing an independent Certified Public Accountant audit examination and submitting the report, requested by the Engineer, will be borne equally by the State and the Contractor. The division of the cost will be made by determining the cost of providing an audit examination and report in conformance with the provisions of Section 9-1.03B, "Work Performed by Special Forces or Other Special Services" of the Standard Specifications, and paying to the Contractor one-half of that cost. The cost of performing an audit examination and submitting the independent Certified Public Accountant audit report for overhead claims other than for the purpose of verifying the actual rate of time-related overhead shall be entirely borne by the Contractor.

Time-related overhead will be paid for at a lump sum price. The contract lump sum price bid for time-related overhead will be increased or decreased only as a result of suspensions or adjustments of contract time which revise the current contract completion date and which satisfy any of the following criteria:

A. Suspensions of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications, except:

    1. Suspensions ordered due to weather conditions being unfavorable for the suitable prosecution of the controlling operation or operations.
    2. Suspensions ordered due to the failure on the part of the Contractor to carry out orders given, or to perform the provisions of the contract.
    3. Suspensions ordered due to factors beyond the control of and not caused by the State or the Contractor, for which the Contractor is granted extensions of time in conformance with the provisions of the third paragraph of Section 8-1.07, "Liquidated Damages," of the Standard Specifications.
    4. Other suspensions that mutually benefit the State and the Contractor.

B. Extensions of contract time granted by the State in conformance with the provisions in the fifth paragraph in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and set forth in approved contract change orders, in conformance with the provisions in Section 4-1.03, "Changes," of the Standard Specifications.
C. Reductions in contract time set forth in approved contract change orders, in conformance with the provisions in Section 4-1.03, "Changes," of the Standard Specifications.

For each day the number of working days bid to complete the contract, in conformance with the provisions in "Beginning Of Work, Time Of Completion And Liquidated Damages," of these special provisions, is increased or decreased due to suspensions or adjustments of contract time as specified above, the lump sum price for time-related overhead will be increased or decreased by an amount equal to the contract lump sum price bid for time-related overhead divided by the number of working days bid to complete the contract.

In the event an early completion progress schedule, as defined in "Progress Schedule (Critical Path Method)" of these special provisions, is submitted by the Contractor and approved by the Engineer, the amount of time-related overhead eligible for payment will be based on the total number of working days for the project, in conformance with the provisions in "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions, rather than the Contractor's early completion progress schedule.

The contract lump sum price paid for time-related overhead shall include full compensation for time-related overhead, including the Contractor's share of costs of an independent Certified Public Accountant audit of overhead costs requested by the Engineer, as specified in these special provisions, and as directed by the Engineer.

The provisions in Sections 4-1.03B, "Increased or Decreased Quantities," and 4-1.03C, "Changes in Character of the Work," of the Standard Specifications shall not apply to the contract item of time-related overhead.

Full compensation for additional overhead costs involved in incentive and disincentive provisions to satisfy internal milestone or multiple calendar requirements shall be considered as included in the contract items of work involved and no additional compensation will be allowed therefor.

Full compensation for additional overhead costs incurred during days of inclement weather when the contract work is extended into additional construction seasons due to delays caused by the State shall be considered as included in the time-related overhead paid during the contract working days, and no additional compensation will be allowed therefor.

Full compensation for additional overhead costs involved in performing additional contract item work that is not a controlling operation shall be considered as included in the contract items of work involved, and no additional compensation will be allowed therefor.

Full compensation for overhead, other than time-related overhead measured and paid for as specified above, and other than overhead costs included in the markups specified in "Force Account Payment" of these special provisions, shall be considered as included in the various items of work and no additional compensation will be allowed therefor.

Overhead costs incurred by joint venture partners, subcontractors, suppliers or other parties associated with the Contractor shall be considered as included in the various overhead costs for which the Contractor is compensated, and no additional compensation will be allowed therefor.

For the purpose of making partial payments pursuant to the provisions in Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount of time-related overhead in each monthly partial payment will be based on the number of working days that occurred during that monthly estimate period, including compensable suspensions and right of way delays. Working days granted by contract change order due to extra work or changes in character of work, will be compensated upon completion of the contract. The amount earned per working day for time-related overhead shall be the lesser of the following amounts:

A. The contract lump sum price for time-related overhead, divided by the number of working days bid to complete the contract, in conformance with the provisions in "Beginning Of Work, Time Of Completion And Liquidated Damages," of these special provisions.
B. Twenty percent of the original total contract amount, divided by the number of working days bid to complete the contract, in conformance with the provisions in "Beginning Of Work, Time Of Completion And Liquidated Damages," of these special provisions.

After acceptance of the contract in conformance with the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount of the contract lump sum price for time-related overhead not yet paid, will be included for payment in the first estimate made after acceptance of the contract in conformance with the provisions in Section 9-1.07, "Payment After Acceptance," of the Standard Specifications.

10-1.16 OBSTRUCTIONS

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Attention is directed to the existence of certain underground facilities that may require special precautions be taken by the Contractor to protect the health, safety and welfare of workers and of the public. Facilities requiring special precautions include, but are not limited to: conductors of petroleum products, oxygen, chlorine, and toxic or flammable gases; natural gas in pipelines greater than 150 mm in diameter or pipelines operating at pressures greater than 415 kPa (gage); underground electric supply system conductors or cables, with potential to ground of more than 300 V, either directly buried or in a duct or conduit which do not have concentric grounded or other effectively grounded metal shields or sheaths.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

It is anticipated that the following utility facilities will be relocated prior to the dates shown:

Utility	Location	Date
P.G.&E. Gas	Willow Glen Way	11/15/04

The following utility facilities will be relocated during the progress of the contract. The Contractor shall notify the Engineer, in writing, prior to doing work in the vicinity of the facility. The utility facility will be relocated within the listed working days, as defined in Section 8-1.06, "Time of Completion," of the Standard Specifications, after the notification is received by the Engineer:

Utility	Location	Working Days
Call Box Telephone	GM1 92+60	5
	GM1 101+10	5
	GM1 109+10	5

Installation of the following utility facilities will require coordination with the Contractor's operations. The Contractor shall make the necessary arrangements with the utility company, through the Engineer, and shall submit a schedule of work, verified by a representative of the utility company, to the Engineer. The schedule of work shall provide not less than the following number of working days, as defined in Section 8-1.06, "Time of Completion," of the Standard Specifications for the utility company to complete their work:

Utility (address)	Location	Working Days
SBC Telephone 3475B North First Street San Jose, CA 95134	Route 87- Station GM1 112+05 Lt.	6 hours
PG&E Electric 308 Stockton Street San Jose, CA 95126	Route 87- Station GM1 112+05 Lt.	6 hours

In the event that the utility facilities mentioned above are not removed or relocated by the date specified and, if in the opinion of the Engineer, the Contractor's operations are delayed or interfered with by reason of the utility facilities not being removed or relocated by the date specified, the State will compensate the Contractor for the delays to the extent provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications, and not otherwise, except as provided in Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

10-1.17 DUST CONTROL

Dust control shall conform to the provisions in Section 10, "Dust Control," of the Standard Specifications.

10-1.18 MOBILIZATION

Mobilization shall conform to the provisions in Section 11, "Mobilization," of the Standard Specifications.

10-1.19 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES

Flagging, signs, and all other traffic control devices furnished, installed, maintained, and removed when no longer required shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Category 1 traffic control devices are defined as those devices that are small and lightweight (less than 45 kg), and have been in common use for many years. The devices shall be known to be crashworthy by crash testing, crash testing of similar devices, or years of demonstrable safe performance. Category 1 traffic control devices include traffic cones, plastic drums, portable delineators, and channelizers.

If requested by the Engineer, the Contractor shall provide written self-certification for crashworthiness of Category 1 traffic control devices. Self-certification shall be provided by the manufacturer or Contractor and shall include the following: date, Federal Aid number (if applicable), expenditure authorization, district, county, route and kilometer post of project limits; company name of certifying vendor, street address, city, state and zip code; printed name, signature and title of certifying person; and an indication of which Category 1 traffic control devices will be used on the project. The Contractor may obtain a standard form for self-certification from the Engineer.

Category 2 traffic control devices are defined as those items that are small and lightweight (less than 45 kg), that are not expected to produce significant vehicular velocity change, but may otherwise be potentially hazardous. Category 2 traffic control devices include: barricades and portable sign supports.

Category 2 devices purchased on or after October 1, 2000 shall be on the Federal Highway Administration (FHWA) Acceptable Crashworthy Category 2 Hardware for Work Zones list. This list is maintained by FHWA and can be located at the following internet address: http://safety.fhwa.dot.gov/fourthlevel/hardware/listing.cfm?code=workzone. The Department maintains a secondary list at the following internet address: http://www.dot.ca.gov/hq/traffops/signtech/signdel/pdf.htm.

Category 2 devices that have not received FHWA acceptance, and were purchased before October 1, 2000, may continue to be used until they complete their useful service life or until January 1, 2003, whichever comes first. Category 2 devices in use that have received FHWA acceptance shall be labeled with the FHWA acceptance letter number and the name of the manufacturer by the start of the project. The label shall be readable. After January 1, 2003, all Category 2 devices without a label shall not be used on the project.

If requested by the Engineer, the Contractor shall provide a written list of Category 2 devices to be used on the project at least 5 days prior to beginning any work using the devices. For each type of device, the list shall indicate the FHWA acceptance letter number and the name of the manufacturer.

Full compensation for providing self-certification for crashworthiness of Category 1 traffic control devices and for providing a list of Category 2 devices used on the project and labeling Category 2 devices as specified shall be considered as included in the prices paid for the various contract items of work requiring the use of the Category 1 or Category 2 traffic control devices and no additional compensation will be allowed therefor.

10-1.20 CONSTRUCTION AREA SIGNS

Construction area signs shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels.

Attention is directed to "Construction Project Information Signs" of these special provisions regarding the number and type of construction project information signs to be furnished, erected, maintained, and removed and disposed of.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes.

Sign substrates for stationary mounted construction area signs may be fabricated from fiberglass reinforced plastic as specified under "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

The Contractor may be required to cover certain signs during the progress of the work. Signs that are no longer required or that convey inaccurate information to the public shall be immediately covered or removed, or the information shall be corrected. Covers for construction area signs shall be of sufficient size and density to completely block out the complete face of the signs. The retroreflective face of the covered signs shall not be visible either during the day or at night. Covers shall be fastened securely so that the signs remain covered during inclement weather. Covers shall be replaced when they no longer cover the signs properly.

“Advance information signs” shown on the plans shall be placed at least 7 calendar days in advance of the freeway, ramp, connector ramp closure, and local street closure. The Contractor shall notify the Engineer not less than 7 calendar days prior to installing “advance information signs”.

“Advance information signs” shown on the plans shall be placed at least 14 calendar days in advance of the bike path closure. The Contractor shall notify the Engineer not less then 14 calendar days prior to installing “advance information signs”.

Detour maps for “advance information sign” for bike path closure will be provided by the Engineer. Contractor shall mount and maintain detour map on sign.

10-1.21 MAINTAINING TRAFFIC

Attention is directed to Sections 7-1.08, "Public Convenience," 7-1.09, "Public Safety," and 12, "Construction Area Traffic Control Devices," of the Standard Specifications and to the provisions in "Public Safety" of these special provisions and these special provisions. Nothing in these special provisions shall be construed as relieving the Contractor from the responsibilities specified in Section 7-1.09.

Lane closures shall conform to the provisions in section "Traffic Control System for Lane Closure" of these special provisions.

Ramps and local streets that do not have freeway closure, lane closure, ramp closure and local street closure charts shall not be permitted to be closed.

Bike path closure shall not be permitted, and contractor staging activities or storage for materials on the bike path shall not be allowed, except for the working day period specified in “Order of Work” of these special provisions.

At locations where falsework pavement lighting or pedestrian openings through falsework are designated, falsework lighting shall be installed in conformance with the provisions in Section 86-6.11, "Falsework Lighting," of the Standard Specifications.

Openings shall be provided through bridge falsework for the use of public traffic at each location where falsework is constructed over the streets or routes listed in the following table. The type, minimum width, height, and number of openings at each location, and the location and maximum spacing of falsework lighting, if required for each opening, shall conform to the requirements in the table. The width of vehicular openings shall be the clear width between temporary railings or other protective work. The spacing shown for falsework pavement lighting is the maximum distance center to center in meters between fixtures.

ALMADEN ROAD UNDERCROSSING (WIDEN)
Bridge Number 37-366 R/L

	Number	Width	Height
Vehicle Openings	1	9.6	4.6
Pedestrian Openings	2	2.4	3.1
	Location	Spacing	
Falsework Pavement Lighting	R and L		

(Width and Height in meters)
(R = Right side of traffic. L = Left side of traffic)
(C = Centered overhead)

ALMA OVERHEAD (WIDEN)
Bridge Number 37-420 R/L

	Number	Width	Height
Railroad Openings	1	3.66	6.4

(Width and Height in meters)

*ALMA AVENUE UNDERCROSSING (WIDEN)
Bridge Number 37-366 R/L

	Number	Width	Height
Vehicle Openings	1	9.6	4.6
Pedestrian Openings	2	2.4	3.1
	Location	Spacing	
Falsework Pavement Lighting	R and L		

(Width and Height in meters)
(R = Right side of traffic. L = Left side of traffic)
(C = Centered overhead)

* Non standard falsework depth is anticipated due to limited vertical clearance.

ALMA STATION PEDESTRIAN
UNDERCROSSING (WIDEN)
Bridge Number 37-434

	Number	Width	Height
Pedestrian Openings	1	6	4.1
	Location	Spacing	
Falsework Pavement Lighting	C		

(Width and Height in meters)
(R = Right side of traffic. L = Left side of traffic)
(C = Centered overhead)

ALMA STATION SEPERATION (WIDEN)
Bridge Number 37-421 L

	Number	Width	Height
Vehicle Openings	1	6.0	4.6
Pedestrian Openings	1	3.0	3.1
	Location	Spacing	
Falsework Pavement Lighting	R		

(Width and Height in meters)
(R = Right side of traffic. L = Left side of traffic)
(C = Centered overhead)

WILLOW STREET VIADUCT
Bridge Number 37-422 L

	Number	Width	Height
Vehicle Openings	1	9.6	4.6
Pedestrian Openings	1	2.4	3.1
	Location	Spacing	
Falsework Pavement Lighting	R and L		

(Width and Height in meters)
(R = Right side of traffic. L = Left side of traffic)
(C = Centered overhead)

The exact location of openings will be determined by the Engineer.

Personal vehicles of the Contractor's employees shall not be parked within the State Right of Way .

The Contractor shall notify local authorities of the Contractor's intent to begin work at least 5 days before work is begun. The Contractor shall cooperate with local authorities relative to handling traffic through the area and shall make arrangements relative to keeping the working area clear of parked vehicles.

Whenever vehicles or equipment are parked on the shoulder within 1.8 m of a traffic lane, the shoulder area shall be closed as shown on the plans.

Lanes and ramps shall be closed only during the hours shown on the charts included in this section "Maintaining Traffic." Except work required under Sections 7-1.08 and 7-1.09, work that interferes with public traffic shall be performed only during the hours shown for lane closures.

No two consecutive entrance ramps or two consecutive exit ramps in the same direction of traffic shall be closed concurrently.

The full width of the traveled way shall be open for use by public traffic on Saturdays, Sundays and designated legal holidays; after 3:00 p.m. on Fridays and the day preceding designated legal holidays; and when construction operations are not actively in progress.

Designated legal holidays are: January 1st, the third Monday in February, the last Monday in May, July 4th, the first Monday in September, November 11th, Thanksgiving Day, and December 25th. When a designated legal holiday falls on a Sunday, the following Monday shall be a designated legal holiday. When November 11th falls on a Saturday, the preceding Friday shall be a designated legal holiday.

Martin Luther King Jr. Day (3rd Monday in January), Lincoln's Birthday (February 12), Cesar Chavez Day (March 31), Columbus Day (2nd Monday in October) and Veteran's Day (November 11) shall follow Friday's schedule for lane closure purposes, and if this date occurs on a Saturday or Sunday, then the allowable lane closure hours shall follow the normal holiday schedule.

Minor deviations from the requirements of this section concerning hours of work which do not significantly change the cost of the work may be permitted upon the written request of the Contractor, if in the opinion of the Engineer, public traffic will be better served and the work expedited. These deviations shall not be adopted by the Contractor until the Engineer has approved the deviations in writing. All other modifications will be made by contract change order.

Chart No. 1
Free Lane Closure Requirements (K-rail & Pavement Markers Placement)

Location: **NB Route 87** From Route 85 to Route 280

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1																				1
Fridays	1	1	1	1	1																				
Saturdays	1	1	1	1	1	1																			
Sundays	1	1	1	1	1	1	1	1																	1
Day before designated legal holiday	1	1	1	1	1																				
Designated legal holidays	1	1	1	1	1	1	1	1																	1

Legend:
1 One lane open in direction of travel.

No work that interferes with public traffic will be allowed.

REMARKS:

Chart No. 2
Free Lane Closure Requirements (K-rail & Pavement Markers Placement)

Location: **SB Route 87** From Route 85 to Route 280

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1																				
Fridays	1	1	1	1	1																				
Saturdays		1	1	1	1	1	1																		
Sundays		1	1	1	1	1	1	1																	
Day before designated legal holiday	1	1	1	1	1																				
Designated legal holidays		1	1	1	1	1	1	1																	

Legend:
1 One lane open in direction of travel.

No work that interferes with public traffic will be allowed.

REMARKS:

Chart No. 3
Free Lane Closure Requirements (Methacrylate Treatment for Bridges)

Location: **SB Route 87 Full Closure** From Route 280 to Almaden Expressway

	a.m.												p.m.												
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																				
Fridays	X	X	X	X	X																				
Saturdays	X	X	X	X	X																				
Sundays	X	X	X	X	X																				
Day before designated legal holiday	X	X	X	X	X																				
Designated legal holidays	X	X	X	X	X																				

Legend:
X Freeway may be closed.

No work that interferes with public traffic will be allowed.

REMARKS: See attached detour plans CS-19, CS-20, CS-21, and CS-22 for detouring details.

Chart No. 4
Free Lane Closure Requirements (Install Overhead Sign Bridge)

Location: **SB Route 87 Full Closure** From Alma Avenue to Almaden Expressway

	a.m.												p.m.												
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																				
Fridays	X	X	X	X	X																				
Saturdays	X	X	X	X	X																				
Sundays	X	X	X	X	X																				
Day before designated legal holiday	X	X	X	X	X																				
Designated legal holidays	X	X	X	X	X																				

Legend:
X Freeway may be closed.

No work that interferes with public traffic will be allowed.

REMARKS: See attached detour plan CS-23 for detouring details.

Chart No. 5
Multilane Lane Requirements

Location: **Alma Avenue** at Route 87 overpass

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	X	X	X	X	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
Fridays	1	X	X	X	X	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
Saturdays	1	X	X	X	X	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
Sundays	1	X	X	X	X	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
Day before designated legal holiday	1	X	X	X	X	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
Designated legal holidays	1	X	X	X	X	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	

Legend:

1 One lane open in direction of travel

X Freeway may be closed

REMARKS:

Chart No. 6
Ramp Lane Requirements

Location: **SB Route 85 to NB Route 87 Connector Ramp**

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																				
Fridays	X	X	X	X	X																				
Saturdays		X	X	X	X	X	X																		
Sundays		X	X	X	X	X	X																		
Day before designated legal holiday	X	X	X	X	X																				
Designated legal holidays		X	X	X	X	X	X																		

Legend:

X Ramp may be closed

No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-4 for detouring details.

Chart No. 7
Ramp Lane Requirements

Location: **SB Route 87 to SB Route 85 Connector Ramp**

	a.m.												p.m.												
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1																				
Fridays		1	1	1	1																				
Saturdays		1	1	1	1	1	1																		
Sundays		1	1	1	1	1	1																		
Day before designated legal holiday		1	1	1	1	1	1																		
Designated legal holidays		1	1	1	1	1	1																		

Legend:

1	A minimum of one paved ramp lane, not less than 3.3 m wide, shall be open for use by public traffic
	No work that interferes with public traffic will be allowed

REMARKS:

Chart No. 8
Ramp Lane Requirements

Location: **Capitol Expressway to SB Route 87 On-Ramp**

	a.m.												p.m.												
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																			X	
Fridays	X	X	X	X	X																				
Saturdays	X	X	X	X	X	X	X																	X	
Sundays	X	X	X	X	X	X	X																	X	
Day before designated legal holiday	X	X	X	X	X																				
Designated legal holidays	X	X	X	X	X	X	X																	X	

Legend:

X	Ramp may be closed
	No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-5 for detouring details.

Chart No. 9
Ramp Lane Requirements

Location: **Capitol Expressway to NB Route 87 On-Ramp**

	a.m.												p.m.												
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																				
Fridays	X	X	X	X	X																				
Saturdays		X	X	X	X																				
Sundays		X	X	X	X	X																			
Day before designated legal holiday	X	X	X	X	X																				
Designated legal holidays		X	X	X	X	X																			

Legend:

X	Ramp may be closed
	No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-6 for detouring details.

Chart No. 10
Ramp Lane Requirements

Location: **NB Route 87 to Capitol Expressway Off-Ramp**

	a.m.												p.m.												
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																				X
Fridays	X	X	X	X	X																				
Saturdays	X	X	X	X	X	X	X																		X
Sundays	X	X	X	X	X	X	X																		X
Day before designated legal holiday	X	X	X	X	X																				
Designated legal holidays	X	X	X	X	X																				X

Legend:

X	Ramp may be closed
	No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-7 for detouring details.

Chart No. 11
Ramp Lane Requirements

Location: **SB Route 87 Off-Ramp to Capitol Expressway**

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1	1	1	1	1	1	1	1											1	1	
Fridays	1	1	1	1	1	1	1	1	1	1	1	1											1	1	
Saturdays	1	1	1	1	1	1	1	1	1	1	1												1	1	
Sundays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
Day before designated legal holiday	1	1	1	1	1	1	1	1	1	1	1	1											1	1	
Designated legal holidays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	

Legend:

1	A minimum of one paved ramp lane, not less than 3.3 m wide, shall be open for use by public traffic
	No work that interferes with public traffic will be allowed

REMARKS:

Chart No. 12
Ramp Lane Requirements

Location: **SB Route 87 to Curtner Avenue Off-Ramp**

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																			X	
Fridays	X	X	X	X	X																			X	
Saturdays	X	X	X	X	X	X	X																	X	
Sundays	X	X	X	X	X	X	X																	X	
Day before designated legal holiday	X	X	X	X	X																			X	
Designated legal holidays	X	X	X	X	X	X	X																	X	

Legend:

X	Ramp may be closed
	No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-8 for detouring details.

Chart No. 13
Ramp Lane Requirements

Location: **SB Route 87 On-Ramp from EB Curtner Avenue**

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																		X	X	
Fridays	X	X	X	X	X																		X	X	
Saturdays	X	X	X	X	X	X	X																X	X	
Sundays	X	X	X	X	X	X	X																X	X	
Day before designated legal holiday	X	X	X	X	X																		X	X	
Designated legal holidays	X	X	X	X	X	X	X																X	X	

Legend:

X Ramp may be closed

No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-9 for detouring details.

Chart No. 14
Ramp Lane Requirements

Location: **NB Route 87 to Curtner Avenue Off-Ramp**

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																			X	
Fridays	X	X	X	X	X																			X	
Saturdays	X	X	X	X	X	X	X																	X	
Sundays	X	X	X	X	X	X	X																	X	
Day before designated legal holiday	X	X	X	X	X																			X	
Designated legal holidays	X	X	X	X	X	X	X																	X	

Legend:

X Ramp may be closed

No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-10 for detouring details.

Chart No. 15
Ramp Lane Requirements

Location: WB Curtner Avenue to SB Route 87 On-Ramp

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																		X	X	
Fridays	X	X	X	X	X																		X	X	
Saturdays	X	X	X	X	X	X	X																X	X	
Sundays	X	X	X	X	X	X	X																X	X	
Day before designated legal holiday	X	X	X	X	X																		X	X	
Designated legal holidays	X	X	X	X	X	X	X																X	X	

Legend:

X Ramp may be closed

No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-11 for detouring details.

Chart No. 16
Ramp Lane Requirements

Location: **Curtner Avenue to NB Route 87 On-Ramp**

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																			X	
Fridays	X	X	X	X	X																			X	
Saturdays	X	X	X	X	X	X	X																		
Sundays	X	X	X	X	X	X	X																	X	
Day before designated legal holiday	X	X	X	X	X																			X	
Designated legal holidays	X	X	X	X	X	X	X																	X	

Legend:

X Ramp may be closed

No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-12 for detouring details.

Chart No. 17
Ramp Lane Requirements

Location: **SB Route 87 to Almaden Expressway Off-Ramp**

	a.m.												p.m.												
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																				
Fridays	X	X	X	X	X																				
Saturdays	X	X	X	X	X	X	X																		
Sundays	X	X	X	X	X	X	X																		
Day before designated legal holiday	X	X	X	X	X																				
Designated legal holidays	X	X	X	X	X	X	X																		

Legend:

X Ramp may be closed

No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-13 for detouring details.

Chart No. 18
Ramp Lane Requirements

Location: Almaden Expressway to NB Route 87 On-Ramp

	a.m.												p.m.												
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																		X	X	
Fridays	X	X	X	X	X																			X	
Saturdays	X	X	X	X	X	X	X																	X	
Sundays	X	X	X	X	X	X	X																X	X	
Day before designated legal holiday	X	X	X	X	X																			X	
Designated legal holidays	X	X	X	X	X	X	X																X	X	

Legend:

X Ramp may be closed

No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-14 for detouring details.

Chart No. 19
Ramp Lane Requirements

Location: SB Route 87 to Alma Avenue Off-Ramp

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																				X
Fridays	X	X	X	X	X																				
Saturdays	X	X	X	X	X	X	X																		
Sundays	X	X	X	X	X	X	X																		X
Day before designated legal holiday	X	X	X	X	X																				
Designated legal holidays	X	X	X	X	X	X	X																		X

Legend:

X Ramp may be closed

No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-15 for detouring details.

Chart No. 20
Ramp Lane Requirements

Location: Alma Avenue to NB Route 87 On-Ramp

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																				X
Fridays	X	X	X	X	X																				
Saturdays	X	X	X	X	X	X	X																		
Sundays	X	X	X	X	X	X	X																		X
Day before designated legal holiday	X	X	X	X	X																				
Designated legal holidays	X	X	X	X	X	X	X																		X

Legend:

X Ramp may be closed

No work that interferes with public traffic will be allowed

REMARKS: See attached detour plan CS-16 for detouring details.

Chart No. 21
Ramp Lane Requirements

Location: NB Route 87 Off-Ramp to Route 280

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1																				1
Fridays	1	1	1	1	1																				1
Saturdays	1	1	1	1	1	1	1																		1
Sundays	1	1	1	1	1	1	1	1																	1
Day before designated legal holiday	1	1	1	1	1																				1
Designated legal holidays	1	1	1	1	1	1	1	1																	1

Legend:

1	A minimum of one paved ramp lane, not less than 3.3 m wide, shall be open for use by public traffic
	No work that interferes with public traffic will be allowed

REMARKS:

Chart No. 22
Ramp Lane Requirements

Location: NB Route 280 to SB Route 87 Freeway Connector

	a.m.												p.m.											
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																				
Fridays	X	X	X	X	X																				
Saturdays	X	X	X	X	X	X	X																		
Sundays	X	X	X	X	X	X	X																		X
Day before designated legal holiday	X	X	X	X	X																				
Designated legal holidays	X	X	X	X	X	X	X																		X

Legend:

X	Ramp may be closed
	No work that interferes with public traffic will be allowed

REMARKS: See attached detour plans CS-17 and CS-19 for detouring details.

Chart No. 23
Ramp Lane Requirements

Location: SB Route 280 to SB Route 87 Freeway Connector

	a.m.												p.m.												
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																				
Fridays	X	X	X	X	X																				
Saturdays	X	X	X	X	X	X	X																		
Sundays	X	X	X	X	X	X	X																		X
Day before designated legal holiday	X	X	X	X	X																				
Designated legal holidays	X	X	X	X	X	X	X																		X

Legend:

X Ramp may be closed

No work that interferes with public traffic will be allowed

REMARKS: See attached detour plans CS-18 and CS-20 for detouring details.

Chart No. 24
Ramp Lane Requirements

Location: SB Route 87 On-Ramp from Auzerais Avenue

	a.m.												p.m.												
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X																				
Fridays	X	X	X	X	X																				
Saturdays	X	X	X	X	X	X	X																		
Sundays	X	X	X	X	X																				X
Day before designated legal holiday	X	X	X	X	X	X	X																		
Designated legal holidays	X	X	X	X	X	X	X																		X

Legend:

X Ramp may be closed

No work that interferes with public traffic will be allowed

REMARKS: See detour plan CS-21 for detouring details.

Pedestrian access facilities shall be provided through construction areas within the right of way as shown on the plans and as specified herein. Pedestrian walkways shall be surfaced with asphalt concrete, portland cement concrete or timber. The surface shall be skid resistant and free of irregularities. Hand railings shall be provided on each side of pedestrian walkways as necessary to protect pedestrian traffic from hazards due to construction operations or adjacent vehicular traffic. Protective overhead covering shall be provided as necessary to insure protection from falling objects and drip from overhead structures.

In addition to the required openings through falsework, pedestrian facilities shall be provided during pile driving, footing, wall, and other bridge construction operations. At least one walkway shall be available at all times. If the Contractor's operations require the closure of one walkway, then another walkway shall be provided nearby, off the traveled roadway.

Railings shall be constructed of wood, S4S, and shall be painted white. Railings and walkways shall be maintained in good condition. Walkways shall be kept clear of obstructions.

Full compensation for providing pedestrian facilities shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

Erection of Almaden Road shall be undertaken on one span at a time. During girder erection, public traffic in the lanes over which girders are being placed shall be routed around the work area by means of a local detour.

Erection and removal of falsework at locations where falsework openings are required shall be undertaken one location at a time. During falsework erection and removal, public traffic in the lanes over which falsework is being erected or removed shall be routed around the work area on adjacent streets. Erection shall include all adjustments or removal of falsework components prior to concrete placement that contribute to the horizontal stability of the falsework system. Removal shall include lowering falsework, blowing sand from sand jacks, turning screws on screw jacks, and removing wedges.

Regardless of the construction procedure, methods and equipment selected, the Contractor shall have necessary materials and equipment on the site to erect or remove the girders falsework in any one span or over any one opening prior to detouring or stopping public traffic, and shall erect or remove the girders falsework in an expeditious manner in order that inconvenience to public traffic will be at a minimum.

10-1.22 CLOSURE REQUIREMENTS AND CONDITIONS

Lane closures shall conform to the provisions in "Maintaining Traffic" of these special provisions and these special provisions.

The term closure, as used herein, is defined as the closure of a traffic lane or lanes, including ramp or connector lanes, within a single traffic control system.

CLOSURE SCHEDULE

By noon Monday, the Contractor shall submit a written schedule of planned closures for the following week period, defined as Friday noon through the following Friday noon.

The Closure Schedule shall show the locations and times when the proposed closures are to be in effect. The Contractor shall use the Closure Schedule request forms furnished by the Engineer. Closure Schedules submitted to the Engineer with incomplete, unintelligible or inaccurate information will be returned for correction and resubmittal. The Contractor will be notified of disapproved closures or closures that require coordination with other parties as a condition of approval.

Amendments to the Closure Schedule, including adding additional closures, shall be submitted to the Engineer, in writing, at least 3 working days in advance of a planned closure. Approval of amendments to the Closure Schedule will be at the discretion of the Engineer.

The Contractor shall confirm, in writing, all scheduled closures by no later than 8:00 a.m. 3 working days prior to the date on which the closure is to be made. Approval or denial of scheduled closures will be made no later than 4:00 p.m. 2 working days prior to the date on which the closure is to be made. Closures not confirmed or approved will not be allowed.

Confirmed closures that are cancelled due to unsuitable weather may be rescheduled at the discretion of the Engineer for the following working day.

CONTINGENCY PLAN

The Contractor shall prepare a contingency plan for reopening closures to public traffic. The Contractor shall submit the contingency plan for a given operation to the Engineer within one working day of the Engineer's request.

LATE REOPENING OF CLOSURES

If a closure is not reopened to public traffic by the specified time, work shall be suspended in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. The Contractor shall not make any further closures until the Engineer has accepted a work plan, submitted by the Contractor, that will insure that future closures will be reopened to public traffic at the specified time. The Engineer will have 2 working days to accept or reject the Contractor's proposed work plan. The Contractor will not be entitled to any compensation for the suspension of work resulting from the late reopening of closures.

For each 10-minute interval, or fraction thereof past the time specified to reopen the closure, the Department will deduct $4,200 per interval from moneys due or that may become due the Contractor under the contract.

COMPENSATION

The Contractor shall notify the Engineer of any delay in the Contractor's operations due to the following conditions, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of those conditions, and the Contractor's loss due to that delay could not have been avoided by rescheduling the affected closure or by judicious handling of forces, equipment and plant, the delay will be considered a right of way delay within the meaning of

Section 8-1.09, "Right of Way Delays," and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09:

A. The Contractor's proposed Closure Schedule is denied and his planned closures are within the time frame allowed for closures in "Maintaining Traffic" of these special provisions, except that the Contractor will not be entitled to any compensation for amendments to the Closure Schedule that are not approved.
B. The Contractor is denied a confirmed closure.

Should the Engineer direct the Contractor to remove a closure prior to the time designated in the approved Closure Schedule, any delay to the Contractor's schedule due to removal of the closure will be considered a right of way delay within the meaning of Section 8-1.09, "Right of Way Delays," and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09.

10-1.23 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE

A traffic control system shall consist of closing traffic lanes and ramps in conformance with the details shown on the plans, the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, the provisions under "Maintaining Traffic" and "Construction Area Signs" of these special provisions, and these special provisions.

The provisions in this section will not relieve the Contractor of responsibility for providing additional devices or taking measures as may be necessary to comply with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications.

During traffic stripe operations and pavement marker placement operations using bituminous adhesive, traffic shall be controlled, at the option of the Contractor, with either stationary or moving lane closures. During other operations, traffic shall be controlled with stationary lane closures. Attention is directed to the provisions in Section 84-1.04, "Protection From Damage," and Section 85-1.06, "Placement," of the Standard Specifications.

A portable changeable message sign shall be placed in advance of each traffic control system at locations as directed by the Engineer. The sign shall be in place and in operation before any other component of the traffic control system is placed and shall remain in operation until all other components of the traffic control system are removed. Portable changeable message signs shall conform to the provisions in “Portable Changeable Signs,” of these special provisions.

If components in the traffic control system are displaced or cease to operate or function as specified, from any cause, during the progress of the work, the Contractor shall immediately repair the components to the original condition or replace the components and shall restore the components to the original location.

STATIONARY LANE CLOSURE

When lane and ramp closures are made for work periods only, at the end of each work period, components of the traffic control system, except portable delineators placed along open trenches or excavation adjacent to the traveled way, shall be removed from the traveled way and shoulder. If the Contractor so elects, the components may be stored at selected central locations, designated by the Engineer within the limits of the highway right of way.

Each vehicle used to place, maintain and remove components of a traffic control system on multilane highways shall be equipped with a Type II flashing arrow sign which shall be in operation when the vehicle is being used for placing, maintaining or removing the components. Vehicles equipped with Type II flashing arrow sign not involved in placing, maintaining or removing the components when operated within a stationary type lane closure shall only display the caution display mode. The sign shall be controllable by the operator of the vehicle while the vehicle is in motion. The flashing arrow sign shown on the plans shall not be used on the vehicles which are doing the placing, maintaining and removing of components of a traffic control system and shall be in place before a lane closure requiring the sign's use is completed.

MOVING LANE CLOSURE

Flashing arrow signs used in moving lane closures shall be truck-mounted. Changeable message signs used in moving lane closure operations shall conform to the provisions in Section 12-3.12, "Portable Changeable Message Signs," of the Standard Specifications, except the signs shall be truck-mounted and the full operation height of the bottom of the sign may be less than 2.1 m above the ground, but should be as high as practicable.

Truck-mounted attenuators (TMA) for use in moving lane closures shall be any of the following approved models, or equal:

A. Hexfoam TMA Series 3000, Alpha 1000 TMA Series 1000 and Alpha 2001 TMA Series 2001, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076, Telephone (312) 467-6750.

1. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX (916) 387-9734.
2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274.

B. Cal T-001 Model 2 or Model 3, manufacturer and distributor: Hexcel Corporation, 11711 Dublin Boulevard, P.O. Box 2312, Dublin, CA 94568, Telephone (510) 828-4200.
C. Renco Rengard Model Nos. CAM 8-815 and RAM 8-815, manufacturer and distributor: Renco Inc., 1582 Pflugerville Loop Road, P.O. Box 730, Pflugerville, TX 78660-0730, Telephone 1-800-654-8182.

Each TMA shall be individually identified with the manufacturer's name, address, TMA model number, and a specific serial number. The names and numbers shall each be a minimum 13 mm high and located on the left (street) side at the lower front corner. The TMA shall have a message next to the name and model number in 13 mm high letters which states, "The bottom of this TMA shall be _____ mm ± _____ mm above the ground at all points for proper impact performance." Any TMA which is damaged or appears to be in poor condition shall not be used unless recertified by the manufacturer. The Engineer shall be the sole judge as to whether used TMAs supplied under this contract need recertification. Each unit shall be certified by the manufacturer to meet the requirements for TMA in conformance with the standards established by the Transportation Laboratory.

Approvals for new TMA designs proposed as equal to the above approved models shall be in conformance with the procedures (including crash testing) established by the Transportation Laboratory. For information regarding submittal of new designs for evaluation contact: Transportation Laboratory, 5900 Folsom Boulevard, Sacramento, California 95819.

New TMAs proposed as equal to approved TMAs or approved TMAs determined by the Engineer to need recertification shall not be used until approved or recertified by the Transportation Laboratory.

PAYMENT

The contract lump sum price paid for traffic control system shall include full compensation for furnishing all labor (except for flagging costs), materials (including signs), tools, equipment, and incidentals, and for doing all the work involved in placing, removing, storing, maintaining, moving to new locations, replacing and disposing of the components of the traffic control system shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer. Flagging costs will be paid for as provided in Section 12-2.02, "Flagging Costs," of the Standard Specifications.

The adjustment provisions in Section 4-1.03, "Changes," of the Standard Specifications shall not apply to the item of traffic control system. Adjustments in compensation for traffic control system will be made only for increased or decreased traffic control system required by changes ordered by the Engineer and will be made on the basis of the cost of the increased or decreased traffic control necessary. The adjustment will be made on a force account basis as provided in Section 9-1.03, "Force Account Payment," of the Standard Specifications for increased work and estimated on the same basis in the case of decreased work.

Traffic control system required by work which is classed as extra work, as provided in Section 4-1.03D of the Standard Specifications, will be paid for as a part of the extra work.

10-1.24 TEMPORARY PAVEMENT DELINEATION

Temporary pavement delineation shall be furnished, placed, maintained, and removed in conformance with the provisions in Section 12-3.01, "General," of the Standard Specifications and these special provisions. Nothing in these special provisions shall be construed as reducing the minimum standards specified in the Manual of Traffic Controls published by the Department or as relieving the Contractor from the responsibilities specified in Section 7-1.09, "Public Safety," of the Standard Specifications.

GENERAL

Whenever the work causes obliteration of pavement delineation, temporary or permanent pavement delineation shall be in place prior to opening the traveled way to public traffic. Laneline or centerline pavement delineation shall be provided at all times for traveled ways open to public traffic. On multilane roadways (freeways and expressways) edgeline delineation shall be provided at all times for traveled ways open to public traffic.

The Contractor shall perform the work necessary to establish the alignment of temporary pavement delineation, including required lines or marks. Surfaces to receive temporary pavement delineation shall be dry and free of dirt and loose material. Temporary pavement delineation shall not be applied over existing pavement delineation or other temporary pavement delineation. Temporary pavement delineation shall be maintained until superseded or replaced with a new pattern of temporary pavement delineation or permanent pavement delineation.

Temporary pavement markers, including underlying adhesive, and removable traffic tape which are applied to the final layer of surfacing or existing pavement to remain in place or which conflicts with a subsequent or new traffic pattern for the area shall be removed when no longer required for the direction of public traffic, as determined by the Engineer.

TEMPORARY LANELINE AND CENTERLINE DELINEATION

Whenever lanelines or centerlines are obliterated and temporary pavement delineation to replace the lines is not shown on the plans, the minimum laneline and centerline delineation to be provided for that area shall be temporary pavement markers placed at longitudinal intervals of not more than 7.3 m. The temporary pavement markers shall be the same color as the laneline or centerline the pavement markers replace. Temporary pavement markers shall be, at the option of the Contractor, one of the temporary pavement markers listed for short term day/night use (14 days or less) or long term day/night use (6 months or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. The temporary pavement markers shall be placed in conformance with the manufacturer's instructions. Temporary pavement markers for long term day/night use (6 months or less) shall be cemented to the surfacing with the adhesive recommended by the manufacturer, except epoxy adhesive shall not be used to place the temporary pavement markers in areas where removal of the temporary pavement markers will be required.

Temporary laneline or centerline delineation consisting entirely of temporary pavement markers listed for short term day/night use (14 days or less), shall be placed on longitudinal intervals of not more than 7.3 m and shall be used for a maximum of 14 days on lanes opened to public traffic. Prior to the end of the 14 days the permanent pavement delineation shall be placed. If the permanent pavement delineation is not placed within the 14 days, the Contractor shall replace the temporary pavement markers and provide additional temporary pavement delineation and shall bear the cost thereof. The additional temporary pavement delineation to be provided shall be equivalent to the pattern specified for the permanent pavement delineation for the area, as determined by the Engineer.

Full compensation for furnishing, placing, maintaining, and removing the temporary pavement markers (including underlying adhesive, layout (dribble) lines to establish alignment of temporary pavement markers or used for temporary laneline and centerline for those areas where temporary laneline and centerline delineation is not shown on the plans and for providing equivalent patterns of permanent traffic lines for those areas when required, shall be considered as included in the contract prices paid for the items of work that obliterated the laneline and centerline pavement delineation and no separate payment will be made therefor.

TEMPORARY EDGELINE DELINEATION

On multilane roadways (freeways and expressways), whenever edgelines are obliterated and temporary pavement delineation to replace those edgelines is not shown on the plans, the edgeline delineation to be provided for those areas adjacent to lanes open to public traffic shall be as follows:

A. Temporary pavement delineation for right edgelines shall, at the option of the Contractor, consist of either a solid 100-mm wide traffic stripe of the same color as the stripe the temporary edgeline delineation replaces, or traffic cones, portable delineators or channelizers placed at longitudinal intervals not to exceed 30 m.
B. Temporary pavement delineation for left edgelines shall, at the option of the Contractor, consist of either solid 100-mm wide traffic stripe of the same color as the stripe the temporary edgeline delineation replaces, traffic cones, portable delineators or channelizers placed at longitudinal intervals not to exceed 30 m or temporary pavement markers placed at longitudinal intervals of not more than 1.8 m. Temporary pavement markers used for temporary left edgeline delineation shall be one of the types of temporary pavement markers listed for short term day/night use (14 days or less) or long term day/night use (6 months or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Traffic stripe (100-mm wide) placed as temporary edgeline delineation which will require removal shall conform to the provisions of "Temporary Traffic Stripe (Tape)" of these special provisions. Where removal of the 100-mm wide traffic stripe will not be required, painted traffic stripe conforming to the provisions of "Temporary Traffic Stripe (Paint)" of these special provisions may be used. The quantity of temporary traffic stripe (paint) used for this temporary edgeline delineation will not be included in the quantities of tape or paint to be paid for.

The lateral offset for traffic cones, portable delineators or channelizers used for temporary edgeline delineation shall be as determined by the Engineer. If traffic cones or portable delineators are used as temporary pavement delineation for edgelines, the Contractor shall provide personnel to remain at the project site to maintain the cones or delineators during the hours of the day that the portable delineators are in use.

Channelizers used for temporary edgeline delineation shall be the surface mounted type and shall be orange in color. Channelizer bases shall be cemented to the pavement in the same manner provided for cementing pavement markers to pavement in "Pavement Markers" of these special provisions, except epoxy adhesive shall not be used to place channelizers

on the top layer of pavement. Channelizers shall be, at the Contractor's option, one of the surface mount types (900 mm) listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Temporary edgeline delineation shall be removed when no longer required for the direction of public traffic as determined by the Engineer.

The quantity of channelizers used as temporary edgeline delineation will not be included in the quantity of channelizers to be paid for. Full compensation for furnishing, placing, maintaining and removing temporary edgeline delineation for those areas where temporary edgeline delineation is not shown on the plans shall be considered as included in the contract prices paid for the items of work that obliterated the edgeline pavement delineation and no separate payment will be made therefor.

TEMPORARY TRAFFIC STRIPE (PAINT)

Temporary traffic stripe consisting of painted traffic stripe shall be applied and maintained at the locations shown on the plans. The painted temporary traffic stripe shall be complete in place at the location shown prior to opening the traveled way to public traffic. Removal of painted temporary traffic stripe will not be required.

Temporary painted traffic stripe shall conform to the provisions in "Paint Traffic Stripes and Pavement Markings" of these special provisions, except for payment. At the option of the Contractor, either one or 2 coats shall be applied regardless of whether on new or existing pavement.

When painted traffic stripe is specified for temporary left edgeline delineation, temporary pavement markers placed at longitudinal intervals of not more than 1.8 m may be used in place of the temporary painted traffic stripe. Temporary pavement markers shall be one of the types of temporary pavement markers listed for long term day/night use (6 months or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. When temporary reflective pavement markers are used in place of temporary painted traffic stripe, payment for those temporary pavement markers will be made on the basis of the theoretical quantity of temporary traffic stripe (paint) required for the left edgeline the temporary pavement markers replace.

TEMPORARY PAVEMENT MARKING (PAINT)

Temporary pavement marking consisting of painted pavement marking shall be applied and maintained at the locations shown on the plans. The painted temporary pavement marking shall be complete in place at the location shown prior to opening the traveled way to public traffic. Removal of painted temporary pavement marking will not be required.

Temporary painted pavement marking shall conform to the provisions in "Paint Traffic Stripes and Pavement Markings" of these special provisions, except for payment. At the option of the Contractor, either one or 2 coats shall be applied regardless whether on new or existing pavement.

TEMPORARY PAVEMENT MARKERS

Temporary pavement markers shall be applied at the locations shown on the plans. The pavement markers shall be applied complete in place at the locations shown prior to opening the traveled way to public traffic.

Temporary pavement markers shall be placed in conformance with the manufacturer's instructions and shall be cemented to the surfacing with the adhesive recommended by the manufacturer, except epoxy adhesive shall not be used in areas where removal of the pavement markers will be required.

Where the temporary pavement delineation shown on the plans for lanelines or centerlines consists entirely of a pattern of broken traffic stripe and pavement markers, the Contractor may use groups of the temporary pavement markers for long term day/night use (6 months or less) in place of the painted temporary traffic stripe. The groups of pavement markers shall be spaced as shown on the plans for a similar pattern of permanent traffic line, except pavement markers shown to be placed in the gap between the broken traffic stripe shall be placed as part of the group to delineate the pattern of broken temporary traffic stripe. The kind of laneline and centerline delineation selected by the Contractor shall be continuous within a given location. Payment for those temporary pavement markers used in place of temporary traffic stripe will be made on the basis of the theoretical length of the patterns of temporary traffic stripe (tape) or temporary traffic stripe (paint).

Retroreflective pavement markers conforming to the provisions in "Pavement Markers" of these special provisions may be used in place of temporary pavement markers for long term day/night use (6 months or less) except to simulate patterns of broken traffic stripe. Placement of the retroreflective pavement markers used for temporary pavement markers shall conform to the provisions in "Pavement Markers" of these special provisions except the waiting period provisions before placing the pavement markers on new asphalt concrete surfacing as specified in Section 85-1.06, "Placement," of the Standard Specifications shall not apply and epoxy adhesive shall not be used to place pavement markers in areas where removal of the pavement markers will be required.

MEASUREMENT AND PAYMENT

Temporary traffic stripe (paint) and temporary pavement marking (paint) will be measured and paid for in the same manner specified for paint traffic stripe (1-coat) and paint pavement marking (1-coat) in Section 84-3.06, "Measurement," and Section 84-3.07, "Payment," of the Standard Specifications.

Temporary pavement markers, shown on the plans, will be measured and paid for by the unit in the same manner specified for retroreflective pavement markers in Section 85-1.08, "Measurement," and Section 85-1.09, "Payment," of the Standard Specifications. Temporary pavement markers used for temporary laneline and centerline delineation for areas which are not shown on the plans will not be included in the quantities of temporary pavement markers to be paid for. Full compensation for removing temporary pavement markers, when no longer required, shall be considered as included in the contract unit price paid for temporary pavement marker and no separate payment will be made therefor.

10-1.25 PORTABLE CHANGEABLE MESSAGE SIGN

Portable changeable message signs shall be furnished, placed, operated, and maintained at those locations shown on the plans or where designated by the Engineer in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to “Traffic Control System for Lane Closure” of these special provisions regarding the use of the portable changeable message signs.

10-1.26 TEMPORARY RAILING

Temporary railing (Type K) shall be placed as shown on the plans, as specified in the Standard Specifications or these special provisions or where ordered by the Engineer and shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Reflectors on temporary railing (Type K) shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Temporary railing (Type K) shall conform to the details shown on Standard Plan T3. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Attention is directed to "Public Safety" and "Order of Work" of these special provisions.

Temporary railing (Type K) placed in conformance with the provisions in "Public Safety" of these special provisions will be neither measured nor paid for.

Reflectors for temporary railing (Type K) shall be furnished by the Contractor. Reflectors shall be, at the option of the Contractor, one of the non-impactable type listed under “concrete barrier markers” in Section “Prequalified and Tested Signing and Delineation Materials” elsewhere in these specials provisions. Adhesive for mounting reflectors shall be per manufactures recommendations and as approved by the Engineer.

Full compensation for reflectors and adhesive shall be considered as included in the contract price paid per meter for temporary railing (Type K) and no separate payment will be made therefore.

Dowels are required when the offset from the base of the temporary railing (Type K) to the edge of the open trench is less than 610 mm. Dowels requirements shall conform to Section 12-3.08, Temporary Railing (Type K),” and Section 12-4, “Measurement and Payment,” of the Standard Specifications.

10-1.27 CHANNELIZER

Channelizers shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Channelizers shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

When no longer required for the work as determined by the Engineer, channelizers and underlying adhesive used to cement the channelizer bases to the pavement shall be removed. Removed channelizers and adhesive shall become the property of the Contractor and shall be removed from the site of work.

10-1.28 TEMPORARY CRASH CUSHION MODULE

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety", and "Order of Work", of these special provisions.

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 4.6 m or more from a lane carrying public traffic and the temporary crash cushion

is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

At the Contractor's option, the modules for use in sand filled temporary crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or TrafFix Sand Barrels manufactured after March 31, 1997, or equal:

A. Energite III and Fitch Inertial Modules, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076. Telephone 1-312-467-6750, FAX 1-800-770-6755

   1. Distributor (North): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828. Telephone 1-800-884-8274, FAX 1-916-387-9734
   2. Distributor (South): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805. Telephone 1-800-222-8274, FAX 1-714-937-1070

B. TrafFix Sand Barrels, manufactured by TrafFix Devices, Inc., 220 Calle Pintoresco, San Clemente, CA 92672. Telephone 1-949 361-5663, FAX 1-949 361-9205

   1. Distributor (North): United Rentals, Inc., 1533 Berger Drive, San Jose, CA 95112. Telephone 1-408 287-4303, FAX 1-408 287-1929
   2. Distributor (South): Statewide Safety & Sign, Inc., P.O. Box 1440, Pismo Beach, CA 93448. Telephone 1-800-559-7080, FAX 1-805 929-5786

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in kilograms for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

Temporary crash cushion modules shall be placed on movable pallets or frames conforming to the dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 3.6 m of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

Temporary crash cushion modules will be measured by the unit as determined from the actual count of modules used in the work or ordered by the Engineer at each location. Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions and modules placed in excess of the number specified or shown will not be measured nor paid for.

Repairing modules damaged by public traffic will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Modules damaged beyond repair by public traffic, when ordered by the Engineer, shall be removed and replaced immediately by the Contractor. Modules replaced due to damage by public traffic will be measured and paid for as temporary crash cushion module.

If the Engineer orders a lateral move of the sand filled temporary crash cushions and the repositioning is not shown on the plans, moving the sand filled temporary crash cushion will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications and these temporary crash cushion modules will not be counted for payment in the new position.

The contract unit price paid for temporary crash cushion module shall include full compensation for furnishing all labor, materials (including sand, pallets or frames and marker panels), tools, equipment, and incidentals, and for doing all the work involved in furnishing, installing, maintaining, moving, and resetting during a work period for access to the work, and removing from the site of the work when no longer required (including those damaged by public traffic) sand filled

temporary crash cushion modules, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.29 EXISTING HIGHWAY FACILITIES

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Except as otherwise provided for damaged materials in Section 15-2.04, "Salvage," of the Standard Specifications, the materials to be salvaged shall remain the property of the State, and shall be cleaned, packaged, bundled, tagged, and hauled to the District Recycle Center at San Francisco – Oakland Bay Bridge toll Plaza warehouse supply area adjacent to the San Francisco-Oakland Bay Bridge Toll Plaza and stockpiled.

The Contractor shall notify the Engineer and the District Recycle Coordinator, telephone (510) 286-6100 a minimum of 48 hours prior to hauling salvaged material to the Recycle Center.

The Recycle Center is open from 8:00 AM to Noon, and from 1:00PM to 2:30 PM Monday through Friday except legal holidays.

Plans of the existing bridges may be requested by fax from the Office of Structure Maintenance and Investigations, 1801 30th Street, Sacramento, CA, Fax (916) 227-8357.

Plans of the existing bridges available to the Contractor are reproductions of the original contract plans with significant changes noted and working drawings and do not necessarily show normal construction tolerances and variances. Where dimensions of new construction required by this contract are dependent on the dimensions of the existing bridges, the Contractor shall verify the controlling field dimensions and shall be responsible for adjusting dimensions of the work to fit existing conditions.

Attention is directed to Section 7-1.06, "Safety and Health Provisions," of the Standard Specifications. Work practices and worker health and safety shall conform to the California Division of Occupational Safety and Health Construction Safety Orders Title 8, of the California Code of Regulations including Section 5158, "Other Confined Space Operations."

Full compensation for conforming to the requirements of these special provisions shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefore.

ABANDON CULVERT

Existing culverts, where shown on the plans to be abandoned, shall be abandoned in place or, at the option of the Contractor, the culverts shall be removed and disposed of. Resulting openings into existing structures that are to remain in place shall be plugged with commercial quality concrete containing not less than 300 kg of cement per cubic meter.

Abandoning culverts in place shall conform to the following:

A. Culverts that intersect the side slopes shall be removed to a depth of not less than one meter measured normal to the plane of the finished side slope, before being abandoned.
B. Culverts 300 mm in diameter and larger, shall, at the Contractor's option, be backfilled with either sand, controlled low strength material or slurry cement backfill conforming to the provisions in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications by any method acceptable to the Engineer that completely fills the pipe. Sand backfill material shall be clean, free draining, and free from roots and other deleterious substances.
C. The ends of culverts shall be securely closed by a 150 mm thick tight fitting plug or wall of commercial quality concrete.

Culverts shall not be abandoned until their use is no longer required. The Contractor shall notify the Engineer in advance of any intended culvert abandonment.

If the Contractor elects to remove and dispose of a culvert which is specified to be abandoned, as provided herein, backfill specified for the pipe will be measured and paid for in the same manner as if the culvert has been abandoned in place.

Backfill will be measured by the cubic meter determined from the dimensions of the culverts and pipelines to be abandoned.

The contract price paid per cubic meter for sand backfill shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in backfilling culverts with sand, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Controlled low strength material and slurry cement backfill, if used at the Contractor's option, will be measured and paid for by the cubic meter as sand backfill.

Controlled slurry cement backfill where shown on the plans will be measured and paid for by the cubic meter of grout backfill.

The contract price paid per cubic meter for grout backfill shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in backfilling culverts with grout, complete

in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for concrete plugs, pipe removal, structure excavation, and backfill shall be considered as included in the contract unit price paid for abandon culvert and no additional compensation will be allowed therefor.

ABANDON RISER

Existing risers, where shown on the plans to be abandoned, shall be abandoned in place or, at the option of the Contractor, the risers shall be removed and disposed of. Resulting openings into existing structures that are to remain in place shall be plugged with commercial quality concrete containing not less than 300 kg of cement per cubic meter.

Abandoning risers in place shall conform to the following:

A. Risers that intersect the side slopes shall be removed to a depth of not less than one meter measured normal to the plane of the finished side slope, before being abandoned.
B. Risers 300 mm in diameter and larger, shall, at the Contractor's option, be backfilled with either sand, controlled low strength material or slurry cement backfill conforming to the provisions in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications by any method acceptable to the Engineer that completely fills the pipe. Sand backfill material shall be clean, free draining, and free from roots and other deleterious substances.
C. The ends of risers shall be securely closed by a 150 mm thick tight fitting plug or wall of commercial quality concrete.

Risers shall not be abandoned until their use is no longer required. The Contractor shall notify the Engineer in advance of any intended riser abandonment.

If the Contractor elects to remove and dispose of a riser which is specified to be abandoned, as provided herein, backfill specified for the pipe will be measured and paid for in the same manner as if the riser has been abandoned in place.

Backfill will be measured by the cubic meter determined from the dimensions of the risers to be abandoned.

The contract price paid per cubic meter for sand backfill shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in backfilling riser with sand, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Controlled low strength material and slurry cement backfill, if used at the Contractor's option, will be measured and paid for by the cubic meter as sand backfill.

Full compensation for concrete plugs, pipe removal, structure excavation, and backfill (including sand, controlled low strength material or slurry cement backfill) shall be considered as included in the contract unit price paid for abandon riser and no additional compensation will be allowed therefor.

ABANDON PIEZOMETER

Existing piezometers , where shown on the plans to be abandoned, shall be abandoned in place.

Abandoning piezometers in place shall conform to the following:

A. Piezometers that intersect the side slopes shall be cut and removed to a depth of not less than one meter measured normal to the plane of the bottom of overexcavation, before being abandoned.
B. Piezometers be backfilled slurry cement backfill conforming to the provisions in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications by any method acceptable to the Engineer that completely fills the pipe.
C. Conduits and meter boxes to piezometers shall be removed and disposed of.

Full compensation for piezometer removal, conduit removal, meter box removal, structure excavation, and backfill (including slurry cement backfill) shall be considered as included in the contract unit price paid for abandon piezometer and no additional compensation will be allowed therefor.

SALVAGE METAL BEAM GUARD RAILING

Existing metal beam guard railing, where shown on the plans to be salvaged, shall be removed and salvaged.

Full compensation for removing cable anchor assemblies, terminal anchor assemblies or steel foundation tubes shall be considered as included in the contract price paid per meter for salvage metal beam guard railing and no separate payment will be made therefor.

REMOVE SIGN STRUCTURE

Existing sign structures, where shown on the plans to be removed, shall be removed and disposed of.

Overhead sign structure removal shall consist of removing posts, frames, portions of foundations, sign panels, walkways with safety railings, and sign lighting electrical equipment.

A sign structure shall not be removed until the structure is no longer required for the direction of public traffic unless otherwise directed by the Engineer.

Concrete foundations may be abandoned in place, except that the top portion, including anchor bolts, reinforcing steel, and conduits shall be removed to a depth of not less than 1 m below the adjacent finished grade. The resulting holes shall be backfilled and compacted with material equivalent to the surrounding material.

Electrical wiring shall be removed to the nearest pull box. Fuses within spliced connections in the pull box shall be removed and disposed of.

The removable sign panel frame on the sign structure shown on the plans shall be removed and salvaged.

Full compensation for salvaging removable sign frame shall be considered as included in the contract unit price paid for remove sign structure and no separate payment will be made therefor.

REMOVE PAVEMENT MARKER

Existing pavement markers, including underlying adhesive, when no longer required for traffic lane delineation as determined by the Engineer, shall be removed and disposed of.

REMOVE FENCE

Existing chain link fence and security fence, where shown on the plans, shall be removed and disposed of in conformance with Section 15, “Existing Highway Facilities,” of the Standard Specifications.

Existing security fence is same as details shown for security fence.

REMOVE TRAFFIC STRIPE

Traffic stripe shall be removed at the locations shown on the plans and as directed by the Engineer.

Attention is directed to "Water Pollution Control" of these special provisions.

Waste from removal of yellow painted traffic stripe contains lead chromate in average concentrations greater than or equal to 5 mg/L Soluble Lead or 1000 mg/kg Total Lead. Yellow painted traffic stripe exist within the project limits. Residue produced when –yellow paint is removed may contain heavy metals in concentrations that exceed thresholds established by the California Health and Safety Code and may produce toxic fumes when heated.

The removed -yellow paint shall be disposed of at a Class 1 disposal facility within 90 days after accumulating 100 kg of residue and dust. The Contractor shall make necessary arrangements with the operator of the disposal facility to test the yellow paint residue as required by the facility and these special provisions. Testing shall include, at a minimum, (1) Total Lead and Chromium by EPA Method 7000 series and (2) Soluble Lead and Chromium by California Waste Extraction Test. From the first 3360 L of waste or portion thereof, if less than 3360 L of waste are produced, a minimum of four randomly selected samples shall be taken and analyzed. From each additional 840 L of waste or portion thereof, if less than 840 L are produced, a minimum of one additional random sample shall be taken and analyzed. The Contractor shall submit the name and location of the disposal facility and analytical laboratory along with the testing requirements to the Engineer not less than 21 days prior to the start of removal of yellow painted traffic stripe. The analytical laboratory shall be certified by the Department of Health Services Environmental Laboratory Accreditation Program. Test results shall be provided to the Engineer for review prior to signing a waste profile as requested by the disposal facility, prior to issuing an EPA identification number, and prior to allowing removal of the waste from the site.

The Contractor shall prepare a project specific Lead Compliance Plan to prevent or minimize worker exposure to lead while handling removed yellow paint residue. Attention is directed to Title 8, California Code of Regulations, Section 1532.1, "Lead," for specific Cal-OSHA requirements when working with lead.

The Lead Compliance Plan shall contain the elements listed in Title 8, California Code of Regulations, Section 1532.1(e)(2)(B). Before submission to the Engineer, the Lead Compliance Plan shall be approved by an Industrial Hygienist certified in Comprehensive Practice by the American Board of Industrial Hygiene. The Plan shall be submitted to the Engineer at least 7 days prior to beginning removal of yellow paint.

Prior to removing yellow painted traffic stripe, personnel who have no prior training, including State personnel, shall complete a safety training program provided by the Contractor that meets the requirements of Title 8, California Code of Regulations, Section 1532.1, "Lead," and the Contractor's Lead Compliance Program.

Personal protective equipment, training, and washing facilities required by the Contractor's Lead Compliance Plan shall be supplied to State personnel by the Contractor. The number of State personnel will be 5.

Where grinding or other methods approved by the Engineer are used to remove yellow painted traffic stripe, the removed residue, including dust, shall be contained and collected immediately. Sweeping equipment shall not be used. Collection shall be by a high efficiency particulate air (HEPA) filter equipped vacuum attachment operated concurrently with the removal operations or other equally effective methods approved by the Engineer. The Contractor shall submit a written work plan for the removal, storage, and disposal of yellow painted traffic stripe to the Engineer for approval not less than 15 days

prior to the start of the removal operations. Removal operations shall not be started until the Engineer has approved the work plan.

The removed yellow painted traffic stripe residue shall be stored and labeled in covered containers. Labels shall conform to the provisions of Title 22, California Code of Regulations, Sections 66262.31 and 66262.32. Labels shall be marked with date when the waste is generated, the words "Hazardous Waste", composition and physical state of the waste (for example, asphalt grindings with thermoplastic or paint), the word "Toxic", the name and address of the Engineer, the Engineer's telephone number, contract number, and Contractor or subcontractor. The containers shall be a type approved by the United States Department of Transportation for the transportation and temporary storage of the removed residue. The containers shall be handled so that no spillage will occur. The containers shall be stored in a secured enclosure at a location within the project limits until disposal, as approved by the Engineer.

If the yellow painted traffic stripe residue is transported to a Class 1 disposal facility, a manifest shall be used, and the transporter shall be registered with the California Department of Toxic Substance Control. The Engineer will obtain the United States Environmental Protection Agency Identification Number and sign all manifests as the generator within 2 working days of receiving sample test results and approving the test methods.

The Contractor shall assume that the yellow paint removed is not regulated under the Federal Resource Conservation and Recovery Act (RCRA). Additional disposal costs for removal residue regulated under RCRA, as determined by test results required by the disposal facility, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Nothing in these special provisions shall relieve the Contractor of the Contractor's responsibilities as specified in Section 7-1.09, "Public Safety," of the Standard Specifications.

Attention is directed to "Material Containing Aerially Deposited Lead" of these special provisions regarding payment for the Lead Compliance Plan.

Full compensation for providing a written work plan for the removal, storage, and disposal of yellow painted traffic stripe shall be considered as included in the contract prices paid per meter for remove yellow painted traffic stripe and no separate payment will be made therefor.

REMOVE CULVERT

Existing culverts, where shown on the plans to be removed, shall be removed and disposed of outside the highway right of way in accordance with the provisions in Section 7-1.13, “Disposal of Material Outside the Highway Right of Way,” of the Standard Specifications. Resulting openings into existing structures that are to remain in place shall be plugged with commercial quality concrete containing no less than 300 kg of cement per cubic meter.

Attention is directed to “Hazardous, Restricted and Non-Hazardous Material, General,” and “Naturally Occurring Asbestos Material-General,” elsewhere in these special provisions.

Culverts shall not be removed until their use is no longer required. The Contractor shall notify the Engineer in advance of any intended culvert removal.

Full compensation for concrete plugs, structure excavation, and backfill shall be considered as included in the contract price paid per meter for remove culvert and no additional compensation will be allowed therefor.

REMOVE UNDERDRAIN

Existing underdrains, where shown on the plans to be removed, shall be removed and disposed of outside the highway right of way in accordance with the provisions in Section 7-1.13, “Disposal of Material Outside the Highway Right of Way,” of the Standard Specifications. Resulting openings into existing structures that are to remain in place shall be plugged with commercial quality concrete containing no less than 300 kg of cement per cubic meter.

Attention is directed to “Hazardous, Restricted and Non-Hazardous Material, General,” and “Naturally Occurring Asbestos Material-General,” elsewhere in these special provisions.

Removal of underdrains shall include removal of permeable material and filter fabric within underdrain. Underdrain shall be backfilled with roadway embankment to conforming to Section 19. “Earthwork,” of the Standard Specifications and these special provisions.

Contractor shall take precautions with existing filter fabric to allow filter fabric to be overlapped with proposed filter fabric as shown on the plans.

Underdrains shall not be removed until their use is no longer required. The Contractor shall notify the Engineer in advance of any intended underdrain removal.

Full compensation for concrete plugs, structure excavation, and backfill shall be considered as included in the contract price paid per meter for remove underdrain and no additional compensation will be allowed therefor.

REMOVE SEWER PIPE

Existing sewer pipe, where shown on the plans to be removed, shall be removed and disposed of outside the highway and street right of way in accordance with the provisions in Section 7-1.13, “Disposal of Material Outside the Highway Right

of Way," of the Standard Specifications. Resulting openings into existing structures that are to remain in place shall be plugged with commercial quality concrete containing no less than 300 kg of cement per cubic meter.

Attention is directed to "Hazardous, Restricted and Non-Hazardous Material, General," and "Naturally Occurring Asbestos Material-General," elsewhere in these special provisions.

Sewer pipe shall not be removed until their use is no longer required. The Contractor shall notify the Engineer in advance of any intended sewer pipe removal.

Full compensation for concrete plugs, structure excavation, and backfill shall be considered as included in the contract price paid per meter for remove sewer pipe and no additional compensation will be allowed therefor.

REMOVE PVC WATERLINE

Existing PVC waterline, where shown on the plans to be removed, shall be removed and disposed of outside the highway right of way in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The existing waterline shall be removed with a clean cut at each end of removal. Foreign material shall be prevented from entering the water system. The unattached ends of the pipe that remain shall be plugged or capped pending attachment of additional pipe or fittings.

PVC waterline shall not be removed until its use is no longer required. The Contractor shall notify the Engineer 3 weeks in advance of any intended PVC waterline removal.

Full compensation for temporary plugging or capping of pipe, structure excavation, and backfill shall be considered as included in the contract price paid per meter for remove PVC waterline and no additional compensation will be allowed therefor.

REMOVE DRAINAGE FACILITY

Existing inlets, manholes, flared end sections, automatic drainage gate, and headwalls, where any portion of these structures is within one meter of the grading plane in excavation areas, or within 0.3-m of original ground in embankment areas, or where shown on the plans to be removed, shall be completely removed and disposed of.

REMOVE ASPHALT CONCRETE DIKE

Existing asphalt concrete dike, where shown on the plans to be removed, shall be removed.

Prior to removing the dike, the outside edge of the asphalt concrete to remain in place shall be cut on a neat line to a minimum depth of 50 mm.

The dike shall be removed in such a manner that the surfacing which is to remain in place is not damaged.

The dike shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications.

CLEANOUT EXISTING DRAINAGE FACILITY

Existing drainage facility shown on the plans to be cleaned out shall include the culvert and the connected adjacent inlet and flared end section. The facility shall be fully cleaned by flushing with water with sufficient pressure to clean out the facility. Removal of existing silt and other items, which reduce the capacity of the existing drainage facility, shall be cleaned, to the satisfaction of the Engineer. Silt and debris shall be captured and shall not be allowed to flush downstream into other culverts.

The contract unit price paid for cleanout existing drainage facility shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in cleaning out of drainage facility (including removing and disposing of silt and debris), complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

REMOVE ROADSIDE SIGN

Existing roadside signs, at those locations shown on the plans to be removed, shall be removed and disposed of.

Sign panels shown on the plans shall be salvaged.

Existing roadside signs shall not be removed until replacement signs have been installed or until the existing signs are no longer required for the direction of public traffic, unless otherwise directed by the Engineer.

Full compensation for salvaging sign panels shall be considered as included in the contract unit price paid for remove roadside sign and no separate payment will be made therefor.

REMOVE FRAMED SIGN PANEL

Existing framed sign panel, at those locations shown on the plans to be removed, shall be removed and salvaged.

The removable sign frame on the existing sign structure shown on the plans shall be salvaged.

Remove framed sign panels will be measured by the unit as determined from actual count in place. A unit shall consist of one removable sign panel frame with sign panels attached.

REMOVE CRASH CUSHION (SAND FILLED)

Existing crash cushion (sand filled), at those locations shown on the plans to be removed, shall be removed and disposed of.

Existing crash cushion (sand filled) shall not be removed until existing crash cushions (sand filled) are no longer required for the protection of public traffic as determined by the Engineer.

Remove sand filled crash cushions will be measured and paid for by each crash cushion module.

RECONSTRUCT CHAIN LINK RAILING

Existing chain link railing, at the locations shown on the plans, shall be removed and reconstructed.

Railing removed in excess of that required for reconstructing chain link railing shall be disposed of.Full compensation for removing and disposing of excess railing shall be considered as included in the contract price paid per meter for reconstruct chain link railing and no separate payment will be made therefor.

PLASTIC PIPELINER

Plastic pipeliner shall be furnished and installed in existing culverts at the locations shown on the plans and in conformance with the details shown on the plans and these special provisions.

Plastic pipeliner shall have a nominal diameter, thickness, and maximum Standard Dimension Ratio (when applicable) as shown on the plans or specified.

Plastic pipeliner shall be High density polyethylene (HDPE) solid wall pipe conforming to the requirements in ASTM Designation: F714 and a Standard Dimension Ratio (SDR) of 32.5.

A Certificate of Compliance shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of plastic pipeliner furnished.

Plastic pipeliner joints shall be joint systems or couplers conforming to the manufacturer's requirements. Joint systems or couplers shall perform the intended function and comply with the "Standard" shear strength and watertightness provisions specified in Section 61-1.02, "Performance Requirements for Culvert and Drainage Pipe Joints," of the Standard Specifications. The Contractor shall furnish a Certificate of Compliance to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications that the material being furnished conforms to the joint property requirements as described herein.

The existing culvert shall be cleaned thoroughly prior to inserting the plastic pipeliner. Earthy material, trash, cuttings, and other waste materials removed from the existing culverts shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. During the installation of the plastic pipeliner, the Contractor shall provide all necessary protection to prevent damage to the plastic pipeliner and the existing culvert.

The entire annular space between the plastic pipeliner and the existing culvert shall be filled with grout. Voids in and around the culvert shall be filled for the entire length of the culvert.

The grout (low density foam concrete) shall be composed of water, portland cement, sand, and a foaming agent. The foaming agent shall conform to the requirements of ASTM Designations: C 869 and C 796. Portland cement shall conform to the requirements of Section 90-2.01, "Cement," of the Standard Specifications. Sand shall be clean and free from deleterious coatings, clay balls, roots and other extraneous material and shall be of a size that will pass a 2.36-mm sieve.

The grout shall have a cast density, at the point of placement, of between 675 and 950 kg/m^3 and shall have a minimum compressive strength of 1400 kPa at 28 days. Compressive strength will be determined from test cylinders sampled, molded, cured, and tested in conformance with the provisions in Section 90-9, "Compressive Strength," of the Standard Specifications.

The water, cement, and sand shall be mixed prior to adding the foaming agent. The foaming agent shall not be added until the material is at the project site.

The Contractor shall determine the mix proportions of the grout.

Before using grout for which the mix proportions have been determined by the Contractor, the Contractor shall submit in writing to the Engineer a copy of the mix design for approval. Certified test data or trial batch reports, verifying that the mix design complies with the density and compressive strength requirements of these special provisions, shall be submitted with the mix design.

The Contractor shall develop and submit a grouting plan to the Engineer. The grouting plan shall address all aspects of the grouting procedure, including plans for diverting existing stream flow. Grouting shall not begin until the grouting plan has been approved by the Engineer. The Engineer will have 2 days for review of the grouting plan.

Grouting pressure shall not exceed 35 kPa for plastic pipeliners with a pipe stiffness of less than 200 kPa and the grouting pressure shall not exceed 50 kPa for all other plastic pipeliners.

Prior to grouting, the existing culvert shall be free from water and debris. Grouting shall not begin until the existing stream flow has been temporarily diverted. Grout shall be placed in a continuous manner. The Contractor's placement method shall prevent floating or shifting of the plastic pipeliner and shall prevent segregation or voids from occurring in the grout mix.

The length of plastic pipeliner to be paid for will be the slope length determined by the Engineer. Pipe placed in excess of the length designated will not be paid for.

The contract price paid per meter for 990 mm plastic pipeliner shall include full compensation for furnishing all labor, materials (including grout), tools, equipment, and incidentals, and for doing all the work involved in installing plastic pipeliner, complete in place, including grouting and submitting the grout mix design and grouting plan, diverting existing stream flow, cleaning existing culverts and disposal of residue from cleaning, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

CURED-IN-PLACE PIPE (CIPP)

Intention

It is the intent of this specification to provide for the reconstruction of pipelines and conduits by the installation of a resin-impregnated flexible tube, which is formed to the original conduit by use of a hydrostatic head. The resin is cured using hot water under hydrostatic pressure within the tube. The Cured-In-Place Pipe (CIPP) will be continuous and tight fitting.

Referenced Documents

This specification references ASTM F1216 (Rehabilitation of pipelines by the inversion and curing of a resin-impregnated tube), ASTM F1743 (Rehabilitation of pipelines by pulled-in-place installation of a cured-in-place thermosetting resin pipe), and ASTM D790 (Test methods for flexural properties of non-reinforced plastics) which are made a part hereof by such reference and shall be the latest edition and revision thereof. In case of conflicting requirements between this specification and these referenced documents, this specification will govern.

PRODUCT, MANUFACTURER/INSTALLER QUALIFICATION REQUIREMENTS

Only proven products with substantial successful long term track records will be approved. All trenchless rehabilitation products and installers must be pre-approved prior to the formal opening of proposals.

Products and Installers seeking approval must meet all of the following criteria to be deemed Commercially Acceptable:

1. For a Product to be considered Commercially Proven, a minimum of 304,800 linear meters or 4,000 manhole-to-manhole (or inlet-to-inlet) line sections of successful wastewater collection system installations in the U.S. must be documented to the satisfaction of the Engineer to assure commercial viability. In addition, at least 15,240 meters of the product shall have been in successful service within the State for a minimum of five years.
2. For an Installer to be considered as Commercially Proven, the Installer must satisfy all insurance, financial, and bonding requirements of the Engineer, and must have had at least 5 (five) years active experience in the commercial installation of the product bid. In addition, the Installer must have successfully installed at least 15,240 meters of the product bid in wastewater collection systems. Acceptable documentation of these minimum installations must be submitted to the Engineer.
3. Sewer rehabilitation products submitted for approval must provide. Third Party Test Results supporting the long term performance and structural strength of the product and such data shall be satisfactory to the Engineer. Test samples shall be prepared so as to simulate installation methods and trauma of the product. No product will be approved without independent third party testing verification.
4. Both the rehabilitation manufacturing and installation processes shall operate under a quality management system which is third-party certified to ISO 9000 or other internationally recognized organization standards. Proof of certification shall be required for approval.
5. Proposals must be labeled clearly on the outside of the proposal envelope, listing the product name and installer being proposed. Only proposals using pre-approved products and installers will be opened and read. Proposals submitted on products and/or from installers that have not been pre-approved will be returned unopened.

Documentation for products and installers seeking pre-approved status must be submitted no less than 2 weeks prior to proposal due date to allow time for adequate consideration. The Engineer will advise of acceptance or rejection a minimum of three days prior to the due date. All required submittals must be satisfactory to the Engineer.

MATERIALS

Tube

The sewn Tube shall consist of one or more layers of absorbent non-woven felt fabric and meet the requirements of ASTM F1216 or ASTM F1743, Section 5. The tube shall be constructed to withstand installation pressures, have sufficient strength to bridge missing pipe, and stretch to fit irregular pipe sections.

The wet out Tube shall have a uniform thickness that when compressed at installation pressures will meet or exceed the Design thickness.

The Tube shall be sewn to a size that when installed will tightly fit the internal circumference and length of the original pipe. Allowance should be made for circumferential stretching during inversion. Overlapped layers of felt in longitudinal seams that cause lumps in the final product shall not be utilized.

The outside layer of the Tube (before wet out) shall be coated with an impermeable, flexible membrane that will contain the resin and facilitate monitoring of resin saturation during the resin impregnation (wet out) procedure.

The Tube shall be homogeneous across the entire wall thickness containing no intermediate or encapsulated elastomeric layers. No material shall be included in the Tube that may cause delamination in the cured CIPP. No dry or unsaturated layers shall be evident.

The wall color of the interior pipe surface of CIPP after installation shall be a light reflective color so that a clear detailed examination with closed circuit television inspection equipment may be made.

Seams in the Tube shall be stronger than the non-seamed felt.

The outside of the Tube shall be marked for distance at regular intervals along its entire length, not to exceed 1.5 m. Such markings shall include the Manufacturers name or identifying symbol. The tubes must be manufactured in the USA.

Resin - The resin system shall be a corrosion resistant polyester, vinyl ester, or epoxy and catalyst system that when properly cured within the tube composite meets the requirements of ASTM F1216 and ASTM F1743, the physical properties herein, and those which are to be utilized in the Design of the CIPP for this project. The resin shall produce CIPP which will comply with the structural and chemical resistance requirements of this specification.

STRUCTURAL REQUIREMENTS

The CIPP shall be designed as per ASTM F1216, Appendix X.1. The CIPP design shall assume no bonding to the original pipe wall.

The Contractor must have performed long-term testing for flexural creep of the CIPP pipe material installed by his Company. Such testing results are to be used to determine the Long-term, time dependent flexural modulus to be utilized in the product design. This is a performance test of the materials (Tube and Resin) and general workmanship of the installation and curing. A percentage of the instantaneous flexural modulus value (as measured by ASTM D-790 testing) will be used in design calculations for external buckling. The percentage, or the long-term creep retention value utilized, will be verified by this testing. Values in excess of 50% will not be applied unless substantiated by qualified third party test data. The materials utilized for the contracted project shall be of a quality equal to or better than the materials used in the long-term test with respect to the initial flexural modulus used in Design.

The Enhancement Factor 'K' to be used in 'Partially Deteriorated' Design conditions shall be assigned a value of 7. Application of Enhancement (K) Factors in excess of 7 shall be substantiated through independent test data.

The layers of the cured CIPP shall be uniformly bonded. It shall not be possible to separate any two layers with a probe or point of a knife blade so that the layers separate cleanly or the probe or knife blade moves freely between the layers. If separation of the layers occur during testing of field samples, new samples will be cut from the work. Any reoccurrence may cause rejection of the work.

The cured pipe material (CIPP) shall conform to the structural properties, as listed below:

MINIMUM PHYSICAL PROPERTIES

Property	Test Method	Cured Composite min. per ASTM F1216	Cured Composite (2,757,900kPa Resin)
Modulus of Elasticity	ASTM D-790 (short term)	1,723,690 kPa	2,757,900 kPa
Flexural Stress	ASTM D-790	31,000 kPa	27,580 kPa

The required structural CIPP wall thickness shall be based as a minimum, on the physical properties in Section 5.5 and in accordance with the Design Equations in the appendix of ASTM F 1216, and the following design parameters:

Design Safety Factor	2.0
Retention Factor for Long-Term Flexural Modulus to be used in Design (*as determined by Long-Term tests described above*)	1%-60%
Ovality*	2%
Enhancement Factor, k	7
Groundwater Depth (above invert)*	0
Soil Depth (above crown)*	See project plans
Soil Modulus**	**
Soil Density**	**
Live Load**	H20 Highway
Design Condition (partially or fully deteriorated)***	Partially deteriorated

*Denotes information which can be provided here or in inspection video tapes or project construction plans. Multiple line segments may require a table of values.

**Denotes information required only for fully deteriorated design conditions.

***Based on review of video logs, conditions of pipeline can be fully or partially deteriorated.

(See ASTM F1216 Appendix) The Engineer will be sole judge as to pipe conditions and parameters utilized in Design.

Refer to the attached Dimensional Ratio table for specific pipe section requirements, based on the pipe condition, depth, ovality, etc. as computed for the conditions shown, using ASTM F 1216 Design Equations.

CIPP WALL THICKNESS
PARTIALLY DETERIORATED DESIGN (PD)

		Required DR (D / t)			
		Ei = 1,723,690 kPa		Ei = 2,757,900 kPa	
		Ground Water Depth			
Ovality	Range of Depth to invert (meter)	50% Depth	Full Depth	50% Depth	Full Depth
	1.2 – 2.4	78	62	92	73
	2.4 – 3.6	69	55	80	64
2 % *	3.6 – 4.9	62	50	73	58
	4.9 – 6.1	58	46	68	54
	6.1 – 7.3	55	44	64	51
	1.2 – 2.4	72	57	84	67
	2.4 – 3.6	63	50	73	58
5 %	3.6 – 4.9	57	46	67	53
	4.9 – 6.1	53	42	62	49
	6.1 – 7.3	50	40	58	47
	1.2 – 2.4	66	52	77	61
	2.4 – 3.6	58	46	67	54
8 %	3.6 – 4.9	52	42	61	49
	4.9 – 6.1	49	39	57	45
	6.1 – 7.3	46	37	54	43

*2% ovality is typically assumed when the host pipe measurements have not been field verified.

PD wall thickness varies with the height of the groundwater above the invert of the host pipe. The table assumes the height of the groundwater equal to half or full depth to the pipe invert. The table represents CIPP pipe wall thickness for a host pipe range of 200 to 1200 mm. This is a guideline only. Specific calculations should refer to ASTM F-1216, Appendix X.1.

Design Parameters:

Poisson's Ratio = 0.3

Factor of Safety = 2.0
Enhancement Factor = 7
DR = Dimension Ratio = Diameter / thickness $\Rightarrow$ **t = D / DR**
Effective reduction of Ei modulus to approximate effects of creep = 50 %
Ovality % = 100 x (Mean Dia. - Minimum Dia.) / Mean Dia.

Any layers of the tube that are not saturated with resin prior to insertion into the existing pipe shall not be included in the structural CIPP wall thickness computation.

TESTING REQUIREMENTS

Chemical Resistance

The CIPP shall meet the chemical resistance requirements of ASTM F1216, Appendix X2. CIPP samples for testing shall be of tube and resin system similar to that proposed for actual construction. It is required that CIPP samples with and without plastic coating meet these chemical testing requirements.

Hydraulic Capacity

Overall, the hydraulic profile shall be maintained as large as possible. The CIPP shall have a minimum of the full flow capacity of the original pipe before rehabilitation. Calculated capacities may be derived using a commonly accepted roughness coefficient for the existing pipe material taking into consideration its age and condition.

CIPP Field Samples

When requested by the Engineer, the Contractor shall submit test results from field installations in the USA of the same resin system and tube materials as proposed for the actual installation. These test results must verify that the CIPP physical properties specified in Section 5.5 have been achieved in previous field applications. Samples for this project shall be made and tested as described in Section 10.1.

INSTALLATION RESPONSIBILITIES FOR INCIDENTAL ITEMS

It shall be the responsibility of the Engineer to locate and designate all inlet access points open and accessible for the work, and provide rights of access to these points. If a street must be closed to traffic because of the orientation of the pipeline, the Engineer shall institute the actions necessary to do this for the mutually agreed time period. The Engineer shall also provide free access to water hydrants for cleaning, inversion and other work items requiring water.

Cleaning of Storm Lines - The Contractor, when required, shall remove all internal debris out of the sewer line that will interfere with the installation of CIPP. Attention is directed to Section 16-1.04, “Removal and Disposal of Materials,” of the standard specifications. Any hazardous waste material encountered during this project will be considered as a changed condition.

Inspection of Pipelines - Inspection of pipelines shall be performed by experienced personnel trained in locating breaks, obstacles and service connections by close circuit television. The interior of the pipeline shall be carefully inspected to determine the location of any conditions which may prevent proper installation of CIPP into the pipelines, and it shall be noted so that these conditions can be corrected. A video tape and suitable log shall be kept for later reference by the Engineer.

Line Obstructions - It shall be the responsibility of the Contractor to clear the line of obstructions such as solids and roots that will prevent the insertion of CIPP. If pre-installation inspection reveals an obstruction such as a protruding service connection, dropped joint, or a collapse that will prevent the inversion process, that was not evident on the pre-bid video and it cannot be removed by conventional sewer cleaning equipment, then the Contractor shall make a point repair excavation to uncover and remove or repair the obstruction. Such excavation shall be approved in writing by the Engineer's representative prior to the commencement of the work and shall be considered as a separate pay item.

The Contractor shall be responsible for confirming the locations of all branch service connections prior to installing and curing the CIPP.

INSTALLATION

CIPP installation shall be in accordance with ASTM F1216, Section 7, or ASTM F1743, Section 6, with the following modifications:

1. **Resin Impregnation** - The quantity of resin used for tube impregnation shall be sufficient to fill the volume of air voids in the tube with additional allowances for polymerization shrinkage and the loss of resin through cracks and irregularities in the original pipe wall. A vacuum impregnation process shall be used. To insure thorough resin saturation throughout the length of the felt tube, the point of vacuum shall be no further than 7.6 meters from the point of initial resin introduction. After vacuum in the tube is established, a vacuum point shall be no further than 22.9 meters from the leading edge of the resin. The leading edge of the resin slug shall be as near to perpendicular

as possible. A roller system shall be used to uniformly distribute the resin throughout the tube. If the Installer uses an alternate method of resin impregnation, the method must produce the same results. Any alternate resin impregnation method must be proven.

2. **Tube Insertion** – The wet out tube shall be positioned in the pipeline using either inversion or a pull-in method. If pulled into place, a power winch should be utilized and care should be exercised not to damage the tube as a result of pull-in friction. The tube should be pulled-in or inverted through an existing manhole or approved access point and fully extend to the next designated manhole or termination point.

3. Temperature gauges shall be placed inside the tube at the invert level of each end to monitor the temperatures during the cure cycle.

4. Curing shall be accomplished by utilizing hot water under hydrostatic pressure in accordance with the manufacturer's recommended cure schedule.

REINSTATEMENT OF BRANCH CONNECTIONS

It is the intent of these specifications that branch connections to buildings be reopened without excavation, utilizing a remote controlled cutting device, monitored by a video TV camera. The Contractor shall certify he has a minimum of 2 complete working cutters plus spare key components on the site before each inversion. Unless otherwise directed by the Engineer, all laterals will be reinstated. No additional payment will be made for excavations for the purpose of reopening connections and the Contractor will be responsible for all costs and liability associated with such excavation and restoration work.

INSPECTION

CIPP samples shall be prepared and physical properties tested in accordance with ASTM F1216 or ASTM F1743, Section 8, using either method proposed. The flexural properties must meet or exceed the values listed in Table 1 of the applicable ASTM.

Wall thickness of samples shall be determined as described in paragraph 8.1.6 of ASTM F1743. The minimum wall thickness at any point shall not be less than 87½% of the design thickness as calculated in the section "Structural Requirements" listed above of these special provisions.

Visual inspection of the CIPP shall be in accordance with ASTM F1743, Section 8.6.

CLEAN-UP

Upon acceptance of the installation work and testing, the Contractor shall restore the project area affected by the operations to a condition at least equal to that existing prior to the work.

PAYMENT

The contract price paid per meter for the different sizes of Cured-In-Place Pipe (CIPP) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing plastic pipe liner, complete in place, including CCTV inspection of pipelines, cleaning existing culverts and disposal of residue from cleaning and reinstatement of branch connections, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

ADJUST INLET

Existing concrete drainage inlets shall be adjusted as shown on the plans.

Portland cement concrete shall be minor concrete or may be produced from commercial quality concrete containing not less than 350 kilograms of cement per cubic meter.

Where inlets are located in areas to be paved or surfaced, no individual structure shall be constructed to final grade until the paving or surfacing has been completed immediately adjacent to the structure.

REMOVE PORTLAND CEMENT CONCRETE PAVEMENT

Removing portland cement concrete pavement shall conform to the provisions in Section 15-3, "Removing Concrete," of the Standard Specifications.

Where no joint exists in the pavement on the line at which concrete is to be removed, a straight, neat cut with a power driven saw shall be made along the line to a minimum depth of 50 mm before removing the concrete.

The quantities of portland cement concrete pavement removed will be measured and paid for by the square meter.

No deduction will be made from any excavation quantities for the quantity of portland cement concrete pavement removed.

Full compensation for removing bituminous or other overlying material and sawing joints at removal lines, as required, shall be considered as included in the contract price paid per square meter for remove concrete pavement and no additional compensation will be allowed therefor.

REMOVE BASE AND SURFACING

Existing base and bituminous surfacing shown on the plans to be removed, shall be removed to a depth of at least 150 mm below the grade of the existing surfacing. Resulting holes and depressions shall be backfilled with earthy material selected from excavation to the lines and grade established by the Engineer.

Removing base and surfacing will be measured by the cubic meter in the same manner specified for roadway excavation in conformance with the provisions in Section 19, "Earthwork," of the Standard Specifications and will be paid for at the contract price per cubic meter for remove base and surfacing.

COLD PLANE ASPHALT CONCRETE PAVEMENT

Existing asphalt concrete pavement shall be cold planed at the locations and to the dimensions shown on the plans.

Planing asphalt concrete pavement shall be performed by the cold planing method. Planing of the asphalt concrete pavement shall not be done by the heater planing method.

Cold planing machines shall be equipped with a cutter head not less than 750 mm in width and shall be operated so that no fumes or smoke will be produced. The cold planing machine shall plane the pavement without requiring the use of a heating device to soften the pavement during or prior to the planing operation.

The depth, width, and shape of the cut shall be as shown on the typical cross sections or as designated by the Engineer. The final cut shall result in a uniform surface conforming to the typical cross sections. The outside lines of the planed area shall be neat and uniform. Planing asphalt concrete pavement operations shall be performed without damage to the surfacing to remain in place.

Planed widths of pavement shall be continuous except for intersections at cross streets where the planing shall be carried around the corners and through the conform lines. Following planing operations, a drop-off of more than 45 mm will not be allowed between adjacent lanes open to public traffic.

Where transverse joints are planed in the pavement at conform lines no drop-off shall remain between the existing pavement and the planed area when the pavement is opened to public traffic. If asphalt concrete has not been placed to the level of existing pavement before the pavement is to be opened to public traffic a temporary asphalt concrete taper shall be constructed. Asphalt concrete for temporary tapers shall be placed to the level of the existing pavement and tapered on a slope of 1:30 (Vertical: Horizontal) or flatter to the level of the planed area.

Asphalt concrete for temporary tapers shall be commercial quality and may be spread and compacted by any method that will produce a smooth riding surface. Temporary asphalt concrete tapers shall be completely removed, including the removal of loose material from the underlying surface, before placing the permanent surfacing. The removed material shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Operations shall be scheduled so that not more than 7 days shall elapse between the time when transverse joints are planed in the pavement at the conform lines and the permanent surfacing is placed at the conform lines.

The material planed from the roadway surface, including material deposited in existing gutters or on the adjacent traveled way, shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. Removal operations of cold planed material shall be concurrent with planing operations and follow within 15 m of the planer, unless otherwise directed by the Engineer.

Cold plane asphalt concrete pavement will be measured by the square meter. The quantity to be paid for will be the actual area of surface cold planed irrespective of the number of passes required to obtain the depth shown on the plans.

The contract price paid per square meter for cold plane asphalt concrete pavement shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in cold planing asphalt concrete surfacing and disposing of planed material, including furnishing the asphalt concrete for and constructing, maintaining, removing, and disposing of temporary asphalt concrete tapers, as specified in the Standard Specifications and these special provisions and as directed by the Engineer.

REMOVE SOUNDWALL

Soundwall, where shown on the plans to be removed, shall be removed.

Attention is directed to “Order of Work” of these special provisions.

Soundwall removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The pay quantities of concrete to be removed will be measured by the square meter of face area of the wall.

The face area of wall shall be measured from the pavement surface at the base of the soundwall to the top of the wall. The concrete barrier shall be considered as the concrete soundwall.

Slurry cement backfill shall conform to the provisions in Section 19-3.062, “Slurry Cement Backfill.” of the Standard Specifications.

Full compensation for removal of existing pile and backfilling with slurry cement at Soundwall No.1 shall be considered as included in the contract unit price paid per square meter for remove soundwall and no separate payment will be made therefore.

CLEAN BRIDGE DECK

This work shall consist of cleaning the portland cement concrete bridge deck surface as shown on the plans and as specified in these special provisions.

The deck surface shall be cleaned by abrasive blasting and shall be dry when blast cleaning is performed.

Traffic stripes, pavement markings, and pavement markers shall be removed as specified in these special provisions during the process of cleaning the deck.

Where abrasive blasting is being performed within 3 m of a lane occupied by public traffic, the residue including dust shall be removed immediately after contact between the abrasive and the surface being treated. The removal shall be by a vacuum attachment operating concurrently with the abrasive blasting operation.

Nothing in these special provisions shall relieve the Contractor from the responsibilities provided in Section 7-1.09, "Public Safety," of the Standard Specifications.

After abrasive cleaning, loose material shall be blown from visible cracks using high pressure air, and the entire deck surface shall be cleaned by manual or power sweeping.

Equipment shall be fitted with suitable traps, filters, drip pans, or other devices as necessary to prevent oil or other deleterious material from being deposited on the deck.

Except otherwise provided, removed materials shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Cleaning bridge deck surface will be measured by the square meter of surface that is cleaned, based on field measurement of the completed work.

The contract price paid per square meter for clean bridge deck shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in cleaning the bridge deck, including removing contrast treatment except slurry or chip seal contrast treatment, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

BRIDGE REMOVAL

Removing bridges or portions of bridges shall conform to the provisions in Section 15-4, "Bridge Removal," of the Standard Specifications and these special provisions.

Attention is directed to “Hazardous, Restricted and Non-Hazardous Material, General,” “Naturally Occurring Asbestos Material-General,” and “Bridge Removal-Asbestos Containing Material,” elsewhere in these special provisions.

Bridge removal shall consist of removing soundwall and concrete barrier, deck overhang, wingwall, abutment, approach slab and slope paving for the following structures as shown on the plans:

Location A
ALMADEN ROAD UNDERCROSSING (WIDEN)
Bridge Number 37-366 R/L

Location B
ALMA OVERHEAD (WIDEN)
Bridge Number 37-420 R/L

Location C
ALMA AVENUE UNDERCROSSING (WIDEN)
Bridge Number 37-368 R/L

Location D
ALMA STATION PEDESTRIAN UNDERCROSSING (WIDEN)
Bridge Number 37-434 L

Location E

ALMA STATION SEPARATION (WIDEN)
Bridge Number 37-421 L

Location F
WILLOW STREET VIADUCT (WIDEN)
Bridge Number 37-422 L

Also, bridge removal shall consist of removing concrete barrier and approach slab for the following structures as shown on the plans:

Location G
CURTNER AVENUE UNDERCROSSING
Bridge Number 37-362 R/L

Location H
CAPITOL EXPRESSWAY UNDERCROSSING
Bridge Number 37-415 R/L

Location I
CAPITOL EXPRESSWAY UNDERCROSSING (OFF-RAMP)
Bridge Number 37-415S

Also, bridge removal shall consist of removing slope paving for the following structure as shown on the plans:

Location J
VIRGINIA STREET OVERCROSSING
Bridge Number 37-315

Also, bridge removal shall consist of removing portions of retaining wall for the following structure as shown on the plans:

Location K
RETAINING WALL No. 1

Location L
RETAINING WALL No. 9

Removed materials that are not to be salvaged or used in the reconstruction shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The Contractor shall submit a complete bridge removal plan to the Engineer for each bridge listed above, detailing procedures, sequences, and all features required to perform the removal in a safe and controlled manner.

The bridge removal plan shall include, but not be limited to the following:

A. The removal sequence, including staging of removal operations.
B. Equipment locations on the structure during removal operations.
C. Temporary support shoring or temporary bracing.
D. Locations where work is to be performed over traffic, utilities, or railroad property.
E. Details, locations, and types of protective covers to be used.
F. Measures to assure that people, property, utilities, and improvements will not be endangered.
G. Details and measures for preventing material, equipment, and debris from falling onto public traffic, or railroad property.

When protective covers are required for removal of portions of a bridge, or when superstructure removal works on bridges are involved, the Contractor shall submit working drawings, with design calculations, to the Engineer for the proposed bridge removal plan, and the bridge removal plan shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California. The design calculations shall be adequate to demonstrate the stability of the structure during all stages of the removal operations. Calculations shall be provided for each stage of bridge removal and shall include dead and live load values assumed in the design of protective covers.Temporary support shoring, temporary

bracing, and protective covers, as required, shall be designed and constructed in conformance with the provisions in Section 51-1.06, "Falsework," of the Standard Specifications and these special provisions.

The assumed horizontal load to be resisted by the temporary support shoring and temporary bracing, for removal operations only, shall be the sum of the actual horizontal loads due to equipment, construction sequence or other causes, and an allowance for wind, but in no case shall the assumed horizontal load to be resisted in any direction be less than 5 percent of the total dead load of the structure to be removed.

The bridge removal plan shall conform to the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The number of sets of drawings, design calculations, and unless otherwise specified in the following table, the time for reviewing bridge removal plans shall be the same as specified for falsework working drawings in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications.

The time to be provided for the Engineer's review of the bridge removal plans for removing specific structures, or portions thereof, shall be as follows:

Structure or Portion of Structure	Review Time - Weeks
Almaden Road Overcrossing (Widen)	3
Alma Overhead (Widen)	3
Alma Avenue Overcrossing (Widen)	3
Alma Station Pedestrian Overcrossing (Widen)	3
Willow Street Viaduct (Widen)	6

The following additional requirements apply to the removal of bridges or portions of bridges that are over or adjacent to roadways that may be closed to public traffic for only brief periods of time:

A. The closure of roadways to public traffic shall conform to the provisions in "Maintaining Traffic" of these special provisions.
B. Prior to closing a roadway to traffic to accommodate bridge removal operations, the Contractor shall have all necessary workers, materials, and equipment at the site as needed to proceed with the removal work in an expeditious manner. While the roadway is closed to public traffic, work shall be pursued promptly and without interruption until the roadway is reopened to public traffic.
C. Bridge removal operations shall be performed during periods of time that the roadway is closed to public traffic except as specified herein for preliminary work.
D. Preliminary work shall be limited to operations that will not reduce the structural strength or stability of the bridge, or any element thereof, to a level that in the judgment of the Engineer would constitute a hazard to the public. This preliminary work shall also be limited to operations that cannot cause debris or any other material to fall onto the roadway. Protective covers may be used to perform preliminary work such as chipping or cutting the superstructure into segments, provided the covers are of sufficient strength to support all loads and are sufficiently tight to prevent dust and fine material from sifting down onto the traveled way. Protective covers shall extend at least 1.2 m beyond the limit of the work underway.
E. Temporary support shoring and temporary bracing shall be used in conjunction with preliminary work when necessary to insure the stability of the bridge.
F. Temporary support shoring, temporary bracing, and protective covers shall not encroach closer than 2.4 m horizontally from the edge or 4.6 m vertically above any traffic lane or shoulder that is open to public traffic.
G. During periods when the roadway is closed to public traffic, debris from bridge removal operations may be allowed to fall directly onto the lower roadway provided adequate protection is furnished for all highway facilities. The minimum protection for paved areas shall be a 0.6-m thick earthen pad or a 25-mm thick steel plate placed over the area where debris can fall. Prior to reopening the roadway to public traffic, all debris, protective pads, and devices shall be removed and the roadway swept clean with wet power sweepers or equivalent methods.

The following additional requirements apply to the removal of bridges or portions of bridges whenever the removal work is to be performed over public traffic:

A. A protective cover shall be constructed before beginning bridge removal work. The protective cover shall be supported by shoring, falsework, or members of the existing structure. The Contractor shall be responsible for designing and constructing safe and adequate protective covers, shoring, and falsework with sufficient strength and rigidity to support the entire load to be imposed.
B. The construction and removal of the protective cover, and the installation and removal of temporary railings shall conform to the provisions in "Order of Work," "Maintaining Traffic," "Temporary Railings" of these special provisions.

C. Bridge removal methods shall be described in the working drawings, supported by calculations with sufficient details to substantiate live loads used in the protective cover design. Dead and live load values assumed for designing the protective cover shall be shown on the working drawings.
D. The protective cover shall prevent any materials, equipment, or debris from falling onto public traffic. The protective cover shall have a minimum strength equivalent to that provided by good, sound Douglas fir planking having a nominal thickness of 50 mm. Additional layers of material shall be furnished as necessary to prevent fine materials or debris from sifting down upon the traveled way and shoulders.
E. During the removal of bridge segments, and when portions of the bridge, such as deck slabs or box girder slabs, comply with the requirements for the protective cover, a separate protective cover need not be constructed.
F. The construction of the protective cover as specified herein shall not relieve the Contractor of responsibilities specified in Section 7-1.12A, "Indemnification," and Section 7-1.12B, "Insurance," of the Standard Specifications.
G. Before removal of the protective cover, the Contractor shall clean the protective cover of all debris and fine material.

For bridge removal that requires the Contractor's registered engineer to prepare and sign the bridge removal plan, the Contractor's registered engineer shall be present at all times when bridge removal operations are in progress. The Contractor's registered engineer shall inspect the bridge removal operation and report in writing on a daily basis the progress of the operation and the status of the remaining structure. A copy of the daily report shall be available at the site of the work at all times. Should an unplanned event occur or the bridge operation deviate from the approved bridge removal plan, the Contractor's registered engineer shall submit immediately to the Engineer for approval, the procedure of operation proposed to correct or remedy the occurrence.

ACCESS OPENING, SOFFIT

Access openings in bridge soffits shall consist of removing portions of existing box girder bridge soffits at the locations and to the dimensions shown on the plans.

A 19-mm deep saw cut shall be made around the perimeter of the soffit areas to be removed.

Bar reinforcing steel shall be removed as shown on the plans. The ends of the remaining bars shall be coated with 2 applications of a zinc-rich primer in the same manner specified for exposed ends of prestressing steel in Section 50-1.05, "Prestressing Steel," of the Standard Specifications.

Within a cell where work is to be performed, existing formwork and miscellaneous concrete that will interfere with the work shall be removed.All material removed shall become the property of the Contractor and shall be disposed of outside the highway right of way as provided in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

When no longer required, soffit access openings shall be closed as shown on the plans. All materials, including galvanized sheet metal covers, steel hardware, hinges, and corrosion resistant concrete expansion anchorage devices, shall be commercial quality.

Thread locking system shall conform to the provisions in Section 75, "Miscellaneous Metal," of the Standard Specifications.

Unless specified as an option, using deck access openings in lieu of soffit access openings will not be allowed.

Access openings through soffits will be measured and paid for by the unit as access opening, soffit. Openings to be paid for will be determined from actual count of the completed units in place.

The contract unit price paid for access opening, soffit shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the soffit access opening, complete in place, including closing the soffit access opening and removing forms and miscellaneous concrete, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

BRIDGE REMOVAL: ASBESTOS CONTAINING MATERIAL

Asbestos-containing material (ACM), as defined in Section 1529, "Asbestos," of the Construction Safety Orders, Title 8, of the California Code of Regulations, may be present in joint seals, columns, the abutments, and other locations of bridges, retaining walls, sound walls, and other structures on Route 87 South HOV Lane Project, San Jose, Santa Clara County, California.

Attention is directed to "Removal of Asbestos" and "Asbestos Health and Safety Plan" elsewhere in these special provisions.

Friable ACM is defined under AHERA as "any material containing more than 1 percent (%) asbestos by area, that hand pressure can crumble, pulverize or reduce to powder when dry". The term non- friable implies that the asbestos fibers are tightly bound into the matrix of the material and should not become an airborne hazard as long as the material remains intact and undamaged, sawed, sanded, drilled or otherwise abraded during removal.

Samples of potential asbestos containing materials were taken from several exposed locations of the bridges, retaining walls, sound walls, and other structures as indicated in the Asbestos and Lead-Containing Paint Survey Reports, and tested

for asbestos . Asbestos was not detected in any sample. The complete reports entitled "Site Investigation Report, Asbestos and Lead-Containing Paint Survey, Route 87 South HOV Project, State Route 87, San Jose, California dated July 2003" and "Site Investigation Report, Follow-Up Asbestos and Lead-Containing Paint Survey, Route 87 South HOV Project, State Route 87, San Jose, California dated April 2004" are available for inspection at the Department of Transportation, Duty Senior's Desk, 111 Grand Avenue, Oakland, California, (510) 286-5209.

Where existing ACM is detected during demolition, construction or alterations, such material shall be treated as hazardous waste, and shall be removed, hauled and disposed of in accordance with all applicable Federal, State and local laws and ordinances.

Permits.-The Contractor shall notify the Bay Area Air Quality Management District as required by National Emission Standards for Hazardous Air Pollutants (NESHAP), 40CFR Part 61, and California Air Resources Control Board rules. The Contractor shall also notify Division of Occupational Safety and Health (Cal OSHA) in accordance with the applicable regulations. A copy of the notification form and attachments shall be provided to the Engineer prior to submittal to the Air District. Notification shall take place a minimum of 10 days prior to demolition. The Contractor shall also notify other local permit agencies and utility companies prior to demolition.

Codes and standards.-Codes, which govern removal and disposal of materials containing asbestos include, but are not necessarily limited to the following:

1. California Health and Safety Code, Division 20, Chapter 6.5, Hazardous Waste Control.
2. California Code of Regulations, Title 22, Division 4, Chapter 30, "Minimum Standards for Management of Hazardous and Extremely Hazardous Material," latest revisions, as applicable.
3. Occupational Safety and Health Administration, Part 26 (amended), of Title 29 of the Code of Federal Regulations.

Sampling Requirements.-The Contractor, who shall be OSHA-certified by the Division of Occupational Safety and Health, and AHERA (Asbestos Hazard Emergency Response Act) trained, has taken and passed an EPA-approved Building Inspector course, and has a valid AHERA certification shall perform additional asbestos survey sampling investigation, if required, for ACM. The sampling investigation shall be consistent with the US EPA's Asbestos/NESHAP Regulated Asbestos Containing Materials Guidance.

Full compensation for conforming to the requirements of this section, except as otherwise specifically provided in these special provisions, shall be considered as included in the contract prices paid for the items involved and no additional compensation will be allowed therefor.

REMOVAL OF ASBESTOS

When the presence of asbestos is not shown on the plans or indicated in the specifications and these special provisions and the Contractor encounters materials which the Contractor reasonably believes to be asbestos as defined in Section 25914.1 of the Health and Safety Code, and the asbestos has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

Attention is directed to "Bridge Removal: Asbestos-Containing Material" and "Asbestos Health and Safety Plan" elsewhere in these special provisions.

Removal and management of ACM.-All work including the work to identify and determine the extent of asbestos encountered during the demolition/alteration of bridges, retaining walls, sound walls, and other structures, and the removal and disposal of ACM shall be performed by a contractor who is registered pursuant to Section 6501.5 of the Labor Code and certified pursuant to Section 7058.6 of the Business and Professions Code. Asbestos removal shall conform to Cal OSHA requirements in Title 8 Sections 1529 and 341. Packaging, storage, transporting, and disposing of ACM shall conform to Division 4.5 of Title 22 , California Code of Regulations.

All friable material shall be removed in a manner, which conforms to OSHA work practice requirements. All non-friable ACM shall be removed and handled to prevent breakage. Non-friable ACM such as cement pipe shall be disposed of to a landfill facility permitted to take asbestos containing products. The Contractor shall select a disposal site that meets all the requirements specified by Federal, State and Local regulations. The removal of ACM encased in concrete or other similar structural material is not required prior to demolition, but such material shall be adequately wetted whenever exposed prior to demolition.

Identifying and determining the extent of asbestos and transportation and disposal of ACM will be paid as extra work in accordance with section 4-1.03D of the Standard Specifications.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Safety- Attention is directed to Section 7-1.06, "Safety and Health Provisions," of the Standard Specifications and to "Asbestos Health and Safety Plan" elsewhere in these special provisions. Written notification of exposure monitoring results shall be submitted to the Engineer upon completion of the monitoring. A copy of any required written certification of the adequacy of alternative work practices shall be submitted to the Engineer before performing any work.

Handling.-The Contractor shall comply with all Federal, State, and local regulations for the removal of ACM prior to demolition or/and during demolition/alteration. The Contractor shall place such removed material in approved plastic containers (double ply, 0.15 mm minimum thickness, plastic bags) with caution labels affixed to said bags. Such caution labels shall have conspicuous, legible lettering, which spells out the following, or equivalent warning:

CAUTION
CONTAINS ASBESTOS FIBERS
BREATHING ASBESTOS DUST MAY
CAUSE SERIOUS BODILY HARM

At the option of the Contractor, the removed ACM may be placed directly into a roll off or drop box, which shall have the same caution label, affixed on all sides.

The Contractor shall comply with all Federal, State and local requirements for safety which shall include providing employees with coveralls (preferably disposable plastic coated), rubber gloves (to be discarded after use), rubber boots (to be washed thoroughly after use), and disposable dust respirators (to cover nose and mouth). The use of goggles shall be optional.

The Contractor shall be responsible for verifying that all employees, who are involved in ACM removal operations, have prior training which meets the requirements of Title 8, California Code of Regulations, Section~~s~~ 1529, Asbestos, Section 5192 (b), Safety and Health, and wear protective devices enumerated herein during removal operations.

Transporting.--All haulers of Asbestos Containing Material shall be currently registered with the State Department of Health Services (DOHS), and shall have a U.S. Environmental Protection Agency Identification Number (U.S. EPA I.D. Number). All vehicles used to transport hazardous waste material shall have affixed to the vehicle a valid Certificate of Compliance issued by DOHS. If a roll off or drop box is utilized, both the drop box and the transporting vehicle must have a valid Certificate of Compliance issued by DOHS.

AUTHORIZED PERSONNEL ONLY

Disposal.-The Engineer will obtain the required EPA generator identification numbers, and will sign the hazardous waste manifests.

The Contractor shall dispose of all hazardous waste containing asbestos at a Disposal Facility, which had previously agreed to accept the hazardous waste and is permitted to take such material.

The Contractor shall notify the proper authorities at the disposal site in advance of delivery of hazardous waste containing asbestos to the disposal site.

PAYMENT

Full compensation for conforming to the requirements of this section, except as otherwise specifically provided in these special provisions, shall be considered as included in the contract prices paid for the items involved and no additional compensation will be allowed therefor.

ASBESTOS HEALTH AND SAFETY PLAN

Attention is directed to "Bridge Removal: Asbestos-Containing Material" and "Removal of Asbestos" elsewhere in these special provisions.

The Contractor shall prepare an Asbestos Health and Safety Plan to prevent or minimize exposure to asbestos. The Contractor's attention is directed to Title 8, California Code of Regulation, Section 5192 (b) (4)(B) and Section 1529, Occupational Safety and Health Guidance Manual published by the National Institute of Occupational Safety and Health (NIOSH), Occupational Safety and Health Administration (OSHA), and USEPA for elements of the site safety plan. The Health and Safety Plan shall contain as a minimum but not be limited to: identification of key personnel for the project, job hazard analysis for work assignments, summary of risk assessment, air monitoring plan, personal protective equipment,

delineation of work zones on-site, decontamination procedures, general safe work practices, security measures, emergency response plans and worker training. The Asbestos Health and Safety Plan shall include an exposure monitoring plan that shall include, but not be limited to, upwind and downwind perimeter monitoring and a discussion of how the exposure monitoring will be conducted during the progression of work in areas designated as containing asbestos. The Asbestos Health and Safety Plan shall be approved by the Contractor's Certified Industrial Hygienist before submission to the Engineer for review and acceptance. The plan shall be submitted to the Engineer at least 15 working days prior to beginning any work in areas containing asbestos.

TRAINING

Prior to performing any work in areas containing asbestos, personnel who have no prior training or are not current in their training status, including State personnel, shall complete a safety training program provided by the Contractor, which meets the requirement of Title 8, California Code of Regulations, Section 1529 and Section 5192 (b) (4)(B). The Contractor shall provide a written certification of completion of safety training to the Engineer for all trained personnel prior to performing any work in areas containing asbestos.

EQUIPMENT AND MEDICAL SURVEILLANCE

The Contractor shall provide personnel protective equipment, training, and medical surveillance required by the Contractor's Health and Safety Plan to 5 State personnel.

The contract lump sum price paid for Asbestos Health and Safety Plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all work involved in preparing and implementing the Asbestos Health and Safety Plan including paying the Certified Industrial Hygienist and for providing personal protective equipment, training and medical surveillance as specified in these special provisions and as directed by the Engineer.

Full compensation for conforming to the requirements of this section, except as otherwise specifically provided in these special provisions, shall be considered as included in the contract price paid for the items involved and no additional compensation will be allowed therefor.

REMOVE CONCRETE

Concrete, where shown on the plans to be removed, shall be removed.

The pay quantities of concrete to be removed will be measured by the cubic meter, measured before and during removal operations.

Removing concrete barrier will be measured by the meter, measured along the barrier before removal operations.

Concrete removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

REMOVE SLOPE PROTECTION

Slope protection (sacked concrete) and slope protection (rock) and, where shown on the plans to be removed, shall be removed.

Material removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The pay quantities of slope protection (sacked concrete) and slope protection (rock) will be measured by the cubic meter, measured before and during removal operations.

10-1.30 CLEARING AND GRUBBING

Clearing and grubbing shall conform to the provisions in Section 16, "Clearing and Grubbing," of the Standard Specifications and these special provisions.

Vegetation shall be cleared and grubbed only within the excavation and embankment slope lines.

At locations where there is no grading adjacent to a bridge or other structure, clearing and grubbing of vegetation shall be limited to 1.5 m outside the physical limits of the bridge or structure.

Existing vegetation outside the areas to be cleared and grubbed shall be protected from injury or damage resulting from the Contractor's operations.

Activities controlled by the Contractor, except cleanup or other required work, shall be confined within the graded areas of the roadway.

Nothing herein shall be construed as relieving the Contractor of the Contractor's responsibility for final cleanup of the highway as provided in Section 4-1.02, "Final Cleaning Up," of the Standard Specifications.

Trees that are within the limits of excavation and embankment slopes, shall be removed in accordance with these special provisions, shall be completely removed in their entirety, including stumps and root system, to a depth of 1.0 meters below finished grade. Holes resulting from the removal of existing trees shall be backfilled the same day the trees are removed. Soil

from the surrounding area may be used to backfill these holes. The backfill shall be graded to conform with the adjacent existing grade.

The Contractor is responsible for complying with any requirements regarding Sudden Oak Death (SOD), including any requirements from the Santa Clara Agricultural Commissioner or federal agencies regarding quarantines for plant material. The project includes removal of Madrones and Tanoaks, two known carriers of SOD, and these trees shall be chipped and the chipped material spread within the project limits at locations designated by the Engineer. At the option of the Contractor, the other species of removed trees may also be chipped and spread within the project limits at locations designated by the Engineer. All tree removal and chipping equipment must be pressure washed before leaving the work area.

All “Tree of Heaven” (Ailanthus altissima) trees, including mature trees, saplings, seedlings, stumps, root sprouts and roots shall be completely removed from the non-paved areas on the project. The Contractor shall individually remove branches with seeds prior to bulldozing and demolition of the trees and stumps. Immediately upon removal, all parts of these trees shall be disposed of outside the highway right of way to avoid any seeds from being spread over the project.

Full compensation for tree removal shall be considered as included in the contract price paid for clearing and grubbing and no additional compensation will be allowed therefore.

10-1.31 WATERING

Developing a water supply and applying watering shall conform to the provisions in Section 17, "Watering," of the Standard Specifications and these special provisions.

Attention is directed to the source or sources of water for use on the project specified in the "Materials Information" handout available to the contractors.

Water used for dust control on this project shall be nonpotable water and shall be furnished and applied as provided in Section 17, "Watering," of the Standard Specifications. Water for uses other than dust control on this project may, at the option of the Contractor, be nonpotable.

Reclaimed waste water from sources, not listed in the "Materials Information," that are developed for use on the project shall meet the California Department of Health Services water reclamation criteria and the Regional Water Quality Control Board requirements. The Contractor shall obtain either a waste water discharge permit or a waiver from the Regional Water Quality Control Board. Copies of permits or waivers from the Regional Water Quality Control Board, for sources not listed in the "Materials Information," shall be delivered to the Engineer before using reclaimed waste water on the project.

Full compensation for developing nonpotable water supply, loading and transporting nonpotable water, and labeling as specified shall be considered as included in the contract lump sum price paid for develop water supply and no additional compensation will be allowed therefor.

If the Engineer orders the use of potable water, an adjustment of compensation for develop water supply will be made in conformance with the provisions in Section 4-1.03C, "Changes in Character of Work," of the Standard Specifications.

10-1.32 EARTHWORK

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

Attention is directed to “Order of Work”, “Hazardous, Restricted and Non-Hazardous Material, General,” and “Naturally Occurring Asbestos Material-General,” elsewhere in these special provisions.

Shoring within the influence line of the light rail track facilities as shown on the plans shall meet the VTA Design Light Rail Vehicle (LRV) loading requirements. Attention is directed to the VTA Design LRV loading requirements in the "Materials Information" handout available to the contractors. All excavations within the influence line of the light rail track facilities shall be shored. No excavations shall be performed within the influence line of the light rail track facilities without shoring.

Class 1 bedding for backfill of City of San Jose sewer and storm drains shall have a Durability Index (California Test No. 29) of not less than 30. Where percent passing the #1 sieve is equal or greater than 8%, the Sand Equivalent (California Test No. 217) shall not be less than 40. Gradation requirements are shown on Table below.

Bedding Gradation

Bedding Class (Gradation – Percent Passing)	
Sieve Size	Percent Passing
25 mm	100
19 mm	90-100
12.5 mm	---
9.5 mm	20-55
4.75 mm	0-10
2.36 mm	0-5

Surplus excavated material not designated or determined hazardous or restricted shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Where a portion of the existing surfacing is to be removed, the outline of the area to be removed shall be cut on a neat line with a power-driven saw to a minimum depth of 50 mm before removing the surfacing. Full compensation for cutting the existing surfacing shall be considered as included in the contract price paid per cubic meter for roadway excavation and no additional compensation will be allowed therefor.

The portion of embankment placed within 1.5 m of the finished grade shall have a Resistance (R-Value) of not less than 15.

Reinforcement or metal attached to reinforced concrete rubble placed in embankments shall not protrude above the grading plane. Prior to placement within 0.6-m below the grading plane of embankments, reinforcement or metal shall be trimmed to no greater than 20 mm from the face of reinforced concrete rubble. Full compensation for trimming reinforcement or metal shall be considered as included in the contract prices paid per cubic meter for the types of excavation shown in the Engineer's estimate, or the contract prices paid for furnishing and placing imported borrow or embankment material, as the case may be, and no additional compensation will be allowed therefor.

If the Contractor elects to use the "Weep Hole and Geocomposite Drain" alternative where permitted on the plans, the geocomposite drain shall conform to the details shown on the plans and the following:

A. Attention is directed to "Engineering Fabrics" under "Materials" of these special provisions.
B. Geocomposite drain shall consist of a manufactured core not less than 6.35 mm thick nor more than 50 mm thick with one or both sides covered with a layer of filter fabric that will provide a drainage void. The drain shall produce a flow rate, through the drainage void, of at least 25 liters per minute per meter of width at a hydraulic gradient of 1.0 and a minimum externally applied pressure of 168 kPa.
C. A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for the geocomposite drain certifying that the drain produces the required flow rate and complies with these special provisions. The Certificate of Compliance shall be accompanied by a flow capability graph for the geocomposite drain showing flow rates for externally applied pressures and hydraulic gradients. The flow capability graph shall be stamped with the verification of an independent testing laboratory.
D. Filter fabric for the geocomposite drain shall conform to the provisions for fabric for underdrains in Section 88, "Engineering Fabrics," of the Standard Specifications.
E. The manufactured core shall be either a preformed grid of embossed plastic, a mat of random shapes of plastic fibers, a drainage net consisting of a uniform pattern of polymeric strands forming 2 sets of continuous flow channels, or a system of plastic pillars and interconnections forming a semirigid mat.
F. The core material and filter fabric shall be capable of maintaining the drainage void for the entire height of geocomposite drain. Filter fabric shall be integrally bonded to the side of the core material with the drainage void. Core material manufactured from impermeable plastic sheeting having nonconnecting corrugations shall be placed with the corrugations approximately perpendicular to the drainage collection system.
G. The geocomposite drain shall be installed with the drainage void and the filter fabric facing the embankment. The fabric facing the embankment side shall overlap a minimum of 75 mm at all joints and wrap around the exterior edges a minimum of 75 mm beyond the exterior edge. If additional fabric is needed to provide overlap at joints and wrap-around at edges, the added fabric shall overlap the fabric on the geocomposite drain at least 150 mm and be attached thereto.
H. Should the fabric on the geocomposite drain be torn or punctured, the damaged section shall be replaced completely or repaired by placing a piece of fabric that is large enough to cover the damaged area and provide a minimum 150-mm overlap.
I. Plastic pipe shall conform to the provisions for edge drain pipe and edge drain outlets in Section 68-3, "Edge Drains," of the Standard Specifications.
J. Treated permeable base to be placed around the slotted plastic pipe at the bottom of the geocomposite drain shall be cement treated permeable base conforming to the provisions for cement treated permeable base in Section 29, "Treated Permeable Bases," of the Standard Specifications and these special provisions.
K. The treated permeable base shall be enclosed with a high density polyethylene sheet or PVC geomembrane, not less than 250 µm thick, which is bonded with a suitable adhesive to the concrete and geocomposite drain. Surfaces to receive the polyethylene sheet shall be cleaned before applying the adhesive. The treated permeable base shall be compacted with a vibrating shoe type compactor.

If structure excavation or structure backfill for bridges is not otherwise designated by type and payment for the structure excavation or structure backfill has not otherwise been provided for in the Standard Specifications or these special provisions, the structure excavation or structure backfill will be measured and paid for as structure excavation (bridge) or structure backfill (bridge), respectively.

The contract price paid per cubic meter for roadway excavation, shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in roadway excavation work, including removal and disposal, temporary shoring; and removal and replacement of geocomposite drain, filter fabric, plastic pipe, and treated permeable material at existing retaining wall, as shown on the plans, as specified in these special provisions and the Standard Specifications, and as directed by the Engineer.

Structure excavation designated as (Rock Slope Protection), for footings at the locations shown on the plans, will be measured and paid for by the cubic meter as structure excavation (Rock Slope Protection). Structure excavation for footings at locations not designated on the plans as structure excavation (Rock Slope Protection), and where rock slope is encountered, will be measured and paid for by the cubic meter as structure excavation (bridge).

Full compensation for slurry cement backfill at Alma Avenue Undercrossing (Widen) shall be considered as included in the contract price paid per cubic meter for slope paving and no separate payment will be made therefore.

10-1.33 HAZARDOUS, RESTRICTED AND NON-HAZARDOUS MATERIAL EXCAVATION

All hazardous and restricted material to be excavated as directed by the Engineer, and/or indicated in these special provisions, shall be transported to a disposal facility permitted to accept such material.

All non-hazardous material, except the quantity of non-hazardous material that will be used within the project limits, will become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of material Outside the Highway Right of Way," of the Standard Specifications.

Attention is directed to "Hazardous, Restricted and Non-Hazardous Material, General" elsewhere in these special provisions.

Excavated materials shall be handled and disposed of in conformance with the requirements in "Hazardous, Restricted, and Non-Hazardous Material, General" elsewhere in these special provisions.

Except for the materials that have been determined to be hazardous, restricted or non-hazardous , all excavated soil resulting from clearing and grubbing, construction area signs, soil excavated for widening/modification of Curtner Avenue Undercrossing, Capitol Expressway Undercrossing, Capitol Expressway Undercrossing (Off-Ramp), and Virginia Street Overcrossing including piling work, drainage systems, and signal, lighting and traffic operation systems as shown on the plans and described elsewhere in these special provisions shall be classified as hazardous material and shall conform to the requirements in "Hazardous, Restricted, and Non-Hazardous Material, General" of these special provisions.

Hazardous and restricted materials shall be transferred directly from the excavation to a temporary stockpile location approved by the Engineer prior to disposal. Soil excavated for widening/modification of Curtner Avenue Undercrossing, Capitol Expressway Undercrossing, Capitol Expressway Undercrossing (Off-Ramp), and Virginia Street Overcrossing shall also be transferred directly from the excavation to a temporary stockpile location approved by the Engineer prior to disposal. Non-hazardous material shall be transferred directly from the excavation and placed into an appropriate portable storage container or loaded into an appropriate transport vehicle.

Hazardous, restricted, and non-hazardous materials shall not be deposited directly on the pavement or on public roads.

All Hazardous and restricted material on exteriors of transport vehicles shall be removed and placed either into the current transport vehicle or the excavation prior to the vehicle leaving the exclusion zone. The Contractor shall indemnify the State from any costs due to spillage during the transport of hazardous and restricted material.

The Contractor shall monitor the air quality continuously during excavation operations at all locations containing hazardous and restricted material.

The Contractor shall implement a plan to prevent exposure of personnel working in hazardous and restricted material excavations. The Contractor's plan to prevent exposure of personnel shall consist of a physical barrier. The barrier shall be maintained by the Contractor. When no longer required, as determined by the Engineer, the physical barrier shall be removed and either decontaminated or disposed of by the Contractor.

Upon completion of the hazardous and restricted material excavation, physical barrier and personal protective equipment, when no longer required, as determined by the Engineer, shall be removed from the job site.

Disposal of additional material resulting from the Contractor's option to slope the excavations in lieu of shoring at locations where this is possible will be at the Contractor's expense. All this additional material is designated as hazardous. At the Contractor's option and expense, the Contractor may perform testing of this material, and if the material is non-hazardous, it may be handled and disposed of as non-hazardous material. The Contractor shall dispose of this material in conformance with the provisions in "Earthwork" of these special provisions.

MEASUREMENT AND PAYMENT

Transportation and disposal of hazardous and restricted material determined from testing of stockpiles as specified elsewhere in these special provisions will be paid for as extra work in accordance with Section 4-1.03D, "Extra Work", of the Standard Specifications.

Quantities of Roadway Excavation, Structure Excavation, Excavation from Cast-In-Drilled-Hole (CIDH) Concrete Piling, and the excavation involved in other items classified as hazardous, except as otherwise specifically provided in these

special provisions, will be measured and paid for as Roadway Excavations, Structure Excavations, including excavation under CIDH piling and drive piles, and excavation involved in other items as shown in the Engineer's Estimate.

Full compensation for excavation, and loading of hazardous and restricted material including providing storage containers, handling and storage of such containers; stockpiling; furnishing, installing and removing physical barriers; and for loading, transporting, and disposing of non-hazardous material; incidentals and other items conforming to the requirements of this section shall be considered as included in the contract prices paid for various items of ,work involved and no additional compensation will be allowed therefor.

10-1.34 DEWATERING

The Contractor shall prevent the flow of water, including ground water, from entering any excavation. Such preventative measures may consist of, but are not limited to: berms, cofferdams, grout curtains, freeze walls, and seal course concrete or any combination thereof. If water does enter an excavation, such water, when necessary to proceed with the work, shall be discharged to closed top, water tight, transportable holding tanks with 15,000 to 21,000 gallon capacities. The Contractor shall be responsible for all work and costs involved in providing the tanks and placing the water into the tanks. The filled water tanks will be discharged within 30 working days as directed by the Engineer.

However, nothing in this section "Dewatering" will be construed as relieving the Contractor of full responsibility of complying with Section 7-1.16, "Contractor's Responsibility for the Work and Materials", of the Standard Specifications.

Non–storm water discharge shall conform to the requirements in Section 7-1.01G, "Water Pollution" of the Standard Specifications, these special provisions, and the requirements of the Regional Water Quality Control Board, Region 2 (RWQCB).

Dewatering shall consist of work required for managing groundwater in this project, as shown on the plans, and as specified in these special provisions.

Dewatering shall include labor and materials for operating and providing pumping equipment, settling tanks, monitoring, inspection, maintenance, and removal and disposal of materials. Groundwater contaminated with petroleum hydrocarbons, metals, Pesticides, and PCBs may be encountered during the excavation necessary for construction of this project. The Contractor shall provide a sealed excavation and prevent the flow of ground water, surface runoff, and tidal flow from entering any excavation including, but not limited to, footing excavations, pile foundation excavations, and excavations for storm drainage systems and their appurtenances. Well points and continuous pumping of excavations for dewatering purposes shall not allowed. The Contractor may dewater an initial volume of water equivalent to the excavation pay limits for a particular excavation. The maximum seepage rate of the sealed excavation, after initial dewatering is complete, shall not exceed five gallons per square meter of the excavation area per eight-hour period. The excavation area shall be measured at the top of the excavation as seen in plan view. A meter that has been approved by the Engineer shall be used to measure all excavation discharges.

The Contractor shall provide a schedule of planned dewatering activities to the Engineer at least 15 working days prior to the commencement of dewatering activities.

The Contractor shall submit a plan to the Engineer in accordance with Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, which details the methods and measures that will be used to pump groundwater. The Plan shall at a minimum contain a graphic for the dewatering operation showing both a sectional plan and plan view that details the removal techniques. The graphic shall define the flow path and placement of pipes, hoses, pumps and other equipment that will be used to convey the discharge. In addition, the Contractor shall provide a drawing that depicts the general position of the dewatering measures relative to the excavations undergoing dewatering and the point of effluent discharge. The written descriptions of the dewatering operations shall include but are not limited to an estimate of the discharge volume, flow rate; location of the discharge; and inspection and monitoring procedures related to the discharge. The discharge plan shall also show the details of how and where the water will be discharged by the Contractor.

The Plan shall be submitted at least 3 weeks prior to beginning excavation operations. The Contractor shall allow 10 working days for the Engineer to review and approve the plan.

If the initial dewatering volume exceeds the volume of the structure excavation pay limits or the seepage rate exceeds the specified maximum see page rate of sealed excavation, the Contractor shall immediately stop all work within the excavation not related to the control of water and submit a plan of corrective measures. The Contractor may not resume operations in that excavation until the plan is approved by the Engineer.

Dewatering shall conform Section7-1.01G, "Water Pollution" of the Standard Specifications, ,and Section 10.1 of these special provisions. Conformance with the requirements of this section shall in no way relieve the Contractor's responsibilities, as provided in Section 7-1.11, "Preservation of Property", Section 7-1.12, "Responsibility for Damage" and Section 7-1.16, "Contractor's Responsibility for the Work and Materials" of the Standard Specifications. Copies of various permits shall be provided to the Engineer fifteen working days prior to disposal of excavation dewatering water. Penalties assessed against the State for permit non-compliance by the Contractor will be borne by the Contractor. Such penalties will be deducted from the monthly progress payments.

Discharge of excavation dewater into the drainage system of the City of San Jose shall be conducted in accordance with Batch Waste Water Permit from the City of San Jose and County of Santa Clara. If contaminant concentrations that exceed the limits established by the Regional Water Quality Control Board are detected, the water shall not be discharged into the City of San Jose wastewater collection system and /or storm drain collection system.

Except for contaminated groundwater, all water from the dewatering process that is discharged into the storm drain system shall be handled in accordance with these special provisions, the requirements of City of San Jose , Santa Clara County and of the Regional Water Quality Control Board.

In the event the Contractor proposes to have the excavation dewatering water transported and discharged at a facility outside of the City of San Jose and the Santa Clara County, the Contractor shall submit a plan to the Engineer, in accordance with Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, which details the methods and measures used to dewater the excavations and convey the discharge into transportable tanks or vessels. A copy of the plan shall be included as an amendment to the Water Pollution Control Plan (WPCP), as specified in "Water Pollution Control" of these special provisions. The plan shall include a graphic of the dewatering operation depicting both a sectional and plan view that details any pre-treatment techniques for the removal of suspended solids and other constituents of concern. The graphic shall define the flow path and placement of pipes, hoses, pumps, and other equipment used to convey the discharge. In addition, the Contractor shall provide a sketch that depicts the general position of the dewatering measures relative to the piles or excavations undergoing dewatering and the point of discharge into transportable tanks or vessels.

The written descriptions of the dewatering operation shall include, but not limited to, an estimate of the discharge volume, flow rate, frequency; location of discharge; and the inspection and monitoring procedures related to the discharge.

The Contractor shall conduct a daily inspection of the dewatering equipment when in use, to ensure that all components are functional and routinely maintained to prevent leakage during and prior to discharge. Should any component of the dewatering apparatus be found to be damaged or to affect the performance of the apparatus, the dewatering operation shall be discontinued and the component shall be immediately repaired or replaced.

Observations, which indicate that the dewatering equipment is leaking, shall be immediately reported to the Engineer. The discharge activity shall immediately cease, so that corrective actions are undertaken to repair, modify, or replace the equipment. The commencement of discharge activities shall be allowed upon approval by the Engineer.

In addition, the Contractor shall conduct inspections, at a minimum, one-hour prior to discharge, during the first ten minutes of initiating discharge, every four hours during discharge, and upon cessation of discharge. The observations shall be recorded daily in a tabular format known as the monitoring report to be provided to the Engineer. The monitoring report shall be provided weekly to the Engineer, or as directed by the Engineer.

Upon completion of the dewatering activities, a letter report shall be prepared and signed by a California Registered Civil Engineer or Geologist and shall include, at a minimum, the volume of removed groundwater, volume of contaminated groundwater and volume of groundwater discharged to the City of San Jose collection systems, sampling procedures and analytical results.

MATERIALS

Materials shall conform to the provisions in Section 6, "Control of Materials," Section 7-1.16, "Contractor's Responsibility for the Work and Materials," and Section 74-2, "Drainage Pump Equipment" of the Standard Specifications and these special provisions.

The Contractor shall provide two (2) settling tanks on-site during dewatering activities with a minimum holding capacity of 7,570 L (2,000 gal) per individual tank and capable of connecting multiple tanks in series. Settling tanks shall be able to accommodate temporary installation of submersible pumps of such capability to discharge water at a maximum rate of 150 L/min (40 gal/min). All tanks shall be of the same make and manufacturer and shall remain on the job site until dewatering operations are no longer necessary as determined by the Engineer..

Pumps shall be capable of being submerged in water and discharging water and other materials including, but not limited to small rocks, gravel, sand and sediments. Two (2) submersible pumps will be required for this project and shall be capable, at all times, of discharging at a flow rate necessary to remove the water in the excavation. In addition, a third submersible pump shall be provided by the Contractor that is capable of discharging treated effluent from the temporary holding container to the dedicated discharge location.

Plastic piping may be approved for use as determined by the Engineer in writing. If plastic piping is used, it shall conform to the provisions in section 20-5.03E, "Pipe" of the Standard Specifications. The Contractor shall be responsible for providing all piping required to convey the clean effluent from the temporary holding container to the point of release at the dedicated discharge location.

The Contractor shall be responsible for maintaining all of the equipment and materials outlined in these special provision to operational levels necessary to comply with provisions outlined in these special provisions and permits issued for this project. If the Contractor or the Engineer identifies a deficiency in the functioning of any equipment or material, the deficiency shall be immediately corrected by the Contractor.

MONITORING

The regulatory limits of various contaminants for the discharge of water have been established by the Regional Water Quality Control Board (RWQCB), Region 2 (San Francisco Bay Region). The RWQCB is located at 1515 Clay Street, Suite 1400, Oakland, California 94612 and their telephone number is (510) 622-2300. These limits are generally provided in their Water Quality Control Plan. The Contractor shall not allow discharge of water to the City of San Jose drainage system exceeding the limits established by the RWQCB as partially shown in the table below:

Parameter	Limit (mg/l)	EPA Test Method
Arsenic	0.02	6010
Thallium	0.04	6010
Barium	0.0039	6010
Beryllium	0.0051	6010
Cadmium	0.0011	6010
Cobalt	0.003	6010
Copper	0.0031	6010
Lead	0.0056	6010
Mercury	0.00001	6010
Nickel	0.0071	6010
Selenium	0.005	6010
Silver	0.00012	6010
Vanadium	0.019	6010
Zinc	0.023	6010
TPH as diesel	0.006	8015
TPH as gas	0.05	8021B

*Note: Metals, BTEX, Total Petroleum Hydrocarbons (TPH), Pesticides and PCBs shall be analyzed by a method with sufficient sensitivity to quantify the concentration of metals, BTEX, TPH, Pesticides, and PCBs well below the regulatory limits.

The Contractor shall seek advance approval from the Engineer on use of a commercial laboratory prior to dewatering. Samples shall be obtained downstream of the flow meter, and just prior to the discharge point. Samples shall be obtained prior to the first discharge, and monthly thereafter. The Contractor shall submit a monitoring report that tabulates laboratory results, describes sampling protocols, and includes laboratory documentation (chain of custodies, final laboratory analysis records, cover letters, etc.) weekly to the Engineer during the period that the permit is in effect even if there is no flow during the week. If there is no sampling performed due to the lack of discharge, then the Contractor shall submit a monitoring report explaining the discharge situation. The Engineer will have 10 working days to review the monitoring report. If revisions are required as determined by the Engineer, the Contractor shall revise and resubmit the draft report within 5 working days of receipt of the Engineer's comments. The Engineer will have 3 working days to review the revisions. Upon the Engineer's approval of the monitoring report, the Contractor shall provide 3 copies of the monitoring report to the Engineer.

The Contractor shall record the flow-meter totalizer readings for every day of dewatering operations. The meter readings and the computed average daily volume (gal/day) shall be submitted to the Engineer as a Discharge Volume Report weekly.

MEASUREMENT AND PAYMENT

The contract lump sum price paid for dewatering shall include full compensation for furnishing all labor, materials, tools, equipment, including providing sealed excavation and measures to prevent the flow of water from entering the excavation; providing dewatering equipment; transportable tanks or vessels; conducting inspections and monitoring; obtaining discharge permits; disposal of excavation dewater including treatment to excavation dewater for removing suspended solids and other constituents of concern; and incidentals, and for doing all the work involved in dewatering as described, including placement, maintenance, and removal of equipment, complete in place, as shown in the plans, and these special provisions, and no additional compensation will be allowed therefor.

Fees associated with discharge to the City of San Jose will be paid by the Contractor.

10-1.35 NATURALLY OCCURRING ASBESTOS MATERIAL EXCAVATION

Attention is directed to Section 5-1.26 "Naturally Occurring Asbestos Material, General" of these special provisions.

The material to be excavated within the project limits was found to contain Naturally Occurring Asbestos (NOA) during sampling and testing at various locations within the project limits. Based on the test results included in the Site Investigation Report information concerning the Hazardous, Restricted, or Non-Hazardous nature of the materials to be excavated at various locations is provided below:

Soil generated from Overexcavation of Material at approach slabs to a maximum depth of approximately 3.5 meters as shown on the plans shall be considered as Hazardous, Restricted, or Non-Hazardous at following locations as indicated.

Southbound Route 87 Approaches to Almaden Road UC-Non-Hazardous
Northbound Route 87 Approaches to Almaden Road UC-Restricted
Southbound Route 87 Approaches to Alma OH – Restricted
Northbound Route 87 Approaches to Alma OH – Non-Hazardous
Northbound Route 87 Approaches to Alma Avenue UC – Restricted
Southbound Route 87 Approaches to Capital Expressway UC – Hazardous from surface to 1.8-meter depth
Southbound Route 87 Approaches to Capital Expressway UC – Non-Hazardous from: 1.8meter depth below surface to bottom of overexcavation

Northbound Route 87 Approaches to Capital Expressway UC – Hazardous from surface to 1.8 meter depth

Northbound Route 87 Approaches to Capital Expressway UC – Non-Hazardous from 1.8meter depth below surface to bottom of overexcavation

Southbound Route 87 Approaches to Alma Station PUC – Hazardous
Southbound Route 87 Approaches to Curtner Avenue UC – Non-Hazardous
Northbound Route 87 Approaches to Curtner Avenue UC – Non-Hazardous

Soil generated from Overexcavation of Material at Bike Path to a maximum depth of approximately 2.00 meters as shown on the plans shall be considered as Hazardous, Restricted, or Non-Hazardous at following locations as indicated.

BKC Line from station 90+60 to 91+41 – Non-Hazardous
BKC Line from station 92+15 to 95+86 – Restricted
BKC Line from station 96+29 to 100+42 – Hazardous

The soil generated from Overexcavation of Material at each of the line locations ~~as~~ indicated above shall be stockpiled separately at one location prior to disposal.

Excavation of materials to a maximum depth of approximately 1.00 meter, except from areas where Overexcavation of Material will be performed as indicated above and shown on the plans, shall be considered as Hazardous, Restricted, or Non-Hazardous at following locations as indicated.

GM1 Line station 74+20 to 76+00 adjoining median –Restricted
GM1 Line station 99+30 to 101+80 adjoining median -- Restricted
GM1 Line along the remaining length adjoining median—Non-Hazardous

Excavation of materials shall be considered as Hazardous, Restricted, or Non-Hazardous at following locations as indicated.

Retaining Wall No. 1 and CR1M Line – Non-hazardous
Retaining Wall Nos. 2 and 3 and ADR1M Line – Non-Hazardous.
Sound Wall No. 1, Retaining Wall Nos. 4 and 5 and GM1 Line adjoining these walls - Non-Hazardous
Retaining Wall Nos. 6 and 7 and GM1 Line adjoining these walls – Non-Hazardous
Retaining Wall Nos. 8 and 9 and AR1M Line – Non-Hazardous

Retaining Wall No. 10, AR4M Line, and GA1M Line from station – Non-Hazardous

Sound Wall No. 4, Retaining Wall No. 11, Retaining Wall No. 12 and GA1M Line adjoining sound wall no. 4 and these retaining walls – Non-hazardous

Retaining Wall No. 14 and GR2M Line – Non-Hazardous

GA1M Line Station 112+00 to 114+23 – Non-Hazardous

Attention is directed to "Naturally Occurring Asbestos Material, General" elsewhere in these special provisions.

Removal and Management of Hazardous and Restricted NOA Material- All work shall be performed by a Contractor who is registered pursuant to Section 6501.5 of the Labor Code and certified pursuant to Section 7058.6 of the Business and Professions Code. Asbestos removal shall conform to California Division of Occupational Safety and Health Administration (Cal- OSHA) requirements in Title 8 Sections 1529 and 341. Packaging, storage, transporting, and disposing of ACM shall conform to Division 4.5 of Title 22, California Code of Regulations and as indicated in these special provisions.

All friable material shall be removed in a manner, which conforms to Cal-OSHA work practice requirements.

Non-Hazardous materials can be used without restrictions within the project limits and shall be consistent with Bay Area Air Quality Management District Regulation 11, Rule 14, Air Resources Control Board Asbestos Airborne Toxic Control Measures, and other regulations.

Handling.--The Contractor shall comply with all Federal, State, and local regulations for the removal of material containing NOA prior to excavation and during excavation, shall place such removed material in temporary storage/stockpile showing following caution labels. Such caution labels shall have conspicuous, legible lettering, which spells out the following, or equivalent warning:

CAUTION
CONTAINS ASBESTOS FIBERS
BREATHING ASBESTOS DUST MAY
CAUSE SERIOUS BODILY HARM

Excavated soil from Retaining Wall No. 1 and road widening adjoining this retaining wall shall be stockpiled separately at one location prior to disposal.

Excavated soil from Retaining Wall No. 3 and road widening adjoining this retaining wall shall be stockpiled separately at one location prior to disposal.

Excavated soil from Retaining Wall Nos. 4 and 5 and road widening adjoining these retaining walls shall be stockpiled separately at one location prior to disposal.

Excavated soil from Retaining Wall Nos. 6 and 7 and road widening adjoining these retaining wall shall be stockpiled separately at one location prior to disposal.

Excavated soil from Retaining Wall Nos. 8 and 9 and AR1M Line widening adjoining these retaining wall shall be stockpiled separately at one location prior to disposal.

Excavated soil from Retaining Wall No. 10, AR4M Line and GA1M Line widening adjoining this retaining wall shall be stockpiled separately at one location prior to disposal.

Excavated soil from Sound Wall No. 4, Retaining Wall Nos. 11, 12, and 14, GA1M Line and GR2M Line widening adjoining Sound Wall No. 4 and this retaining wall shall be stockpiled separately at one location prior to disposal.

Excavated soil from Retaining Wall No. 14 and GA1M Line widening adjoining this retaining wall shall be stockpiled separately at one location prior to disposal.

Excavated soil from GM1 Line station 74+20 to 76+00 adjoining median shall be stockpiled separately at one location prior to disposal.

Excavated soil from GM1 Line station 99+30 to 101+80 adjoining median shall be stockpiled separately at one location prior to disposal.

Excavated soil from GM1 Line along the remaining length adjoining median shall be stockpiled separately at one location prior to disposal.

Transporting.-All haulers of hazardous NOA material shall be currently registered with the State Department of Health Services (DOHS), and shall have a U.S. Environmental Protection Agency Identification Number (U.S. EPA I.D. Number). All vehicles used to transport hazardous ~~waste~~ material shall have affixed to the vehicle a valid Certificate of Compliance issued by DOHS. If a roll off or drop box is utilized, both the drop box and the transporting vehicle must have a valid Certificate of Compliance issued by DOHS.

All haulers of restricted NOA material shall be currently registered in accordance with applicable rules and regulations.

The hazardous, restricted, and non-hazardous materials shall be wetted and covered securely during transportation

Disposal.-The Engineer will obtain the required EPA generator identification number, and will sign the hazardous waste manifests for transporting hazardous material.

The Contractor shall dispose of all hazardous and restricted NOA materials at a Disposal Facility permitted to accept such materials.

The Contractor shall notify the proper authorities at the disposal facility in advance of delivery of hazardous and restricted materials to the disposal facility .

The Contractor may dispose of non-hazardous material at sites other than a Disposal Facility permitted to accept it. The Contractor shall conduct any further investigation deemed necessary by the owner of the property accepting the non-hazardous material. This investigation shall be at Contractor's expense and shall be conducted in accordance with applicable rules and regulations. Characterization of the material shall be based on guidelines in USEPA, SW 846, ARB Method 435 and Air Resources Board Asbestos Airborne Toxic Control Measure.

The written authorization from the property owner for the receipt of non-hazardous material shall include an acknowledgement that the material contains asbestos, and shall state the levels of asbestos reported from testing. The Contractor shall supply a copy of the State supplied information to the property owner.

PAYMENT

Quantities of Roadway Excavation in hazardous, restricted and non-hazardous materials will be measured and paid for as Roadway Excavation (Naturally Occurring Asbestos)(Hazardous), Roadway Excavation (Naturally Occurring Asbestos)(Restricted) and Roadway Excavatiion respectively as shown in the Engineer's Estimate.

Full compensation for conforming to the requirements of this section including loading, transporting, and disposal of hazardous, restricted and non-hazardous materials, including furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work pertaining to Roadway excavation items, including compliance with all regulatory requirements, stockpiling, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer, except as otherwise specifically provided in these special provisions, shall be considered as included in the contract prices paid for the items involved and no additional compensation will be allowed therefor.

10-1.36 LIGHTWEIGHT EMBANKMENT MATERIAL (CELLULAR CONCRETE)

The work shall consist of constructing a lightweight embankment material (cellular concrete) to the lines, grades, and dimensions shown on the plans, in accordance with the Standard Specifications, these special provisions and as directed by the Engineer.

The Contractor shall furnish two mix designs, one of which will produce a cast density (at point of placement) of 6.3 to 6.6 kN/m^3 with a minimum compressive strength of 550 kPa at 28 days, and one mix design which will produce a cast density (at point of placement) of 3.9 to 4.7 kN/m^3 with a minimum compressive strength of 276 kPa at 28 days. The Contractor shall provide the Engineer with a Work Plan of the equipment and procedures proposed at least 10 working days prior to placement; items in the submittal shall include:

1. Material list of items; manufacturer's specifications;
2. Mix designs, including laboratory data using the mix design verifying mass and strength requirements.

Admixtures for accelerating the set time may be used in accordance with the manufacturer's recommendations. A foaming agent shall be used and shall be tested in accordance with ASTM C 796. Mixing water shall be potable and free of deleterious amounts of acids, alkali, salts, oils, and organic materials which would adversely affect the setting or strength of the Lightweight Embankment Material (cellular concrete).

Portland Cement shall comply with ASTM C150, Types I, II, or III. Pozzolans and other cementitious materials may be used when specifically approved by the manufacturer of the foaming agent.

At the point of placement, the density shall be in accordance with the specified cast density. A single cast density test shall represent the lesser of 230 cubic meters or one day's production.

The compressive strength shall be tested in accordance with ASTM C 495 except as follows:

1. Unless otherwise approved by the Engineer, the specimens shall be 76.2 mm (3-inch) by 152.4 mm (6-inch) cylinders. During molding, place the concrete in two approximately equal layers, and raise an drop the cylinders approximately 25 mm three times on a hard surface after placing each layer; no rodding shall be allowed. Specimens shall be covered and protected immediately after casting to prevent damage and loss of moisture.
2. Specimens shall be moist cured in the molds for a period of seven (7) days prior to the 28-day compressive strength test. Specimens shall not be oven dried.

Lightweight embankment material (cellular concrete) shall be placed to the designated dimensions as specified in Sections 19-1.03, "Grade Tolerance,".

Lift thickness for lightweight embankment material (cellular concrete) shall not exceed 0.6 m. If more than one lift is required, the layer to receive the next lift shall be scarified with a broom or rake to provide surface roughness. After curing for 12 hours, any crumbling area on the surface should be removed and scarified before the next layer is placed. Surface stepping shall be limited to 125 mm. Grades of up to 5 percent may be made by adding a thickening agent to the mix, in conformance with the manufacturer's recommendations.

A minimum 12-hour waiting time between lifts shall be required. If ambient temperatures are anticipated to be below 4.5 C within 24 hours after placement, the mixing water should be heated when specifically approved by the manufacturer of the foaming agent, or placement shall be prohibited during such period. Placement shall not be allowed on frozen ground.

Cement and water may be premixed and delivered to the site; and foam shall be added at the site. Slurry coats and multilayer casting are acceptable methods of installation. Subgrade to receive lightweight embankment material (cellular concrete) shall be free of all loose and extraneous material. Subgrade shall be uniformly moist, and any excess water standing on the surface shall be removed prior to placing lightweight embankment material (cellular concrete).

After placing the final lift of lightweight embankment material (cellular concrete), the exposed surface of shall be covered with a prime coat. The prime coat shall conform to the requirements in Section 94, "Asphaltic Emulsions," of the Standard Specifications. A prime coat of SS-1 shall be applied uniformly at a rate of between 0.68 and 1.13 liters per square-meter, with the exact rate determined by the Engineer.

Pay quantities for lightweight embankment material (cellular concrete) will be measured by the cubic meter, to the lines and grade shown on the plans and as directed by the Engineer.

The contract price paid per cubic meter for lightweight embankment material (cellular concrete) shall include full compensation for furnishing all labor, materials (including furnishing and applying the prime coat), tools, equipment, and incidentals, and for doing all the work involved in furnishing and placing, the lightweight embankment material (cellular concrete), complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.37 COMPACTION GROUTING

GENERAL

Soils shall be compaction grouted as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

Attention is directed to "Order of Work" elsewhere in these special provisions.

The Geotechnical Design Report and Materials Report for this project is included in the "Information Handout" available for review at the Department of Transportation, . Duty Senior's Desk, 111 Grand Avenue, Oakland, California, (510) 286-5209.A Grouting Contractor that specializes in compaction grouting shall perform the work. The Contractor shall have a minimum of 5 years experience in planning and directing work dealing with compaction grouting, in the actual placement of grout pipes, and in the mixing and injection of grout.

The Contractor shall submit a list of personnel to be used on this project outlining the employees' experience with compaction grouting. The grouting supervisor shall have a minimum of 3 years of actual on-the-job supervisory experience in similar applications and shall be assisted by an experienced grouting foreman on each shift of grouting operation.

The Contractor shall determine on the ground, the vertical and horizontal projection of the exterior limits of all underground structures, conduits, irrigation systems, etc., including, but not limited to, storm drain pipes, Santa Clara Valley Transportation Authority (VTA) control and communication ductbank and conduit lines, VTA drainage lines, VTA electrical conduits in order to adjust grout injection point locations to fit field conditions.

Surplus materials generated from the grouting ground pipes shall become the property of the Contractor and shall be disposed of as provided in Section 7-1.13. "Disposal of Material Outside the Highway Right of Way."

DEFINITIONS

A. Compaction Grouting – A process by which a very stiff, low-slump (0 to 50 millimeters) cement mortar grout is injected under high pressure through a grout pipe into the ground at various elevations (stages) to displace and thereby densify in-situ soils.

B. Grout Injection Point (Hole) – A point on the pavement or slope surface through which the Contractor inserts the grout pipe for the purpose of conducting grouting. On the pavement surface the grout injection points shall consist of coring holes through Portland cement or asphalt concrete pavement, including setting up and removing equipment involved at each location where compaction grouting is performed.

SUBMITTALS

Prior to performing compaction grouting operations the Contractor shall submit 3 copies, for approval by the Engineer, a draft written grouting program outlining the proposed work plan for the compaction grouting operation. No compaction grouting operations shall be performed until the written grouting program has been approved by the Engineer. One written

program may be submitted encompassing grouting operations or separate written programs may be submitted for each grouting operation. Each written program shall include, but not be limited to:

1. A list of personnel to be used in this project outlining their experience with compaction grouting;
2. Grout mix design together with grout material specifications;
3. Equipment and methods for measuring and recording stroke and back pressures, including pressure surges, at the top of the injection point;
4. Equipment and methods for measuring and recording pumping rates and grout volumes with calibration procedures and calibration certification of the equipment;
5. Complete description of the materials, equipment, including size and type, and methods to be used in each grouting operation, including inclination and depth of grout pipes, and increments in which the grout pipes will be withdrawn;
6. Sample forms for drilling logs, grouting logs and monitoring logs;
7. Detailed description of the proposed monitoring program for ground surface movement and distress to related freeway and light rail facilities such as pavement, storm drains, light rail tracks and utility conduits.

The Engineer will have 10 working days to review the written grouting programs. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit 3 copies of the written grouting programs. The Engineer will have 5 working days to review the revisions. Upon the Engineer's approval of the written grouting programs, 3 approved copies of the written grouting programs, incorporating the required changes, shall be submitted to the Engineer. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by any reason of the Engineer's delay in completing the review, the Contractor will be compensated for resulting losses, and an extension of time will be granted, in the same manner as provided in Section 8-1.09 "Right of Way Delays," of the Standard Specifications.

Full compensation for submittals shall be considered as included in the contract price paid per cubic meter for "Compaction Grouting" and no additional compensation will be allowed therefor.

MATERIALS

The mix shall be a combination of Portland cement, fine aggregate, coarse aggregate, and water.

Portland cement shall be Type I or II and shall conform to the provisions in Section 90-2.02, "Portland Cement," of the Standard Specifications. The cement content of the grout shall not be less than 110 kilograms per cubic meter of grout.

Fine aggregate shall conform to the requirements of Section 90-2.02, "Aggregates," of the Standard Specifications. Fine aggregate shall be well graded and have between 10 and 30 percent passing the No. 75 micrometers sieve and a minimum of 85 percent of content passing the No. 2.36 millimeters sieve. Fine aggregate shall be graded to eliminate sand blocking at the grout working pressures specified elsewhere in these special provisions.

Coarse aggregate shall conform to the requirements of Section 90-2.02, "Aggregates," of the Standard Specifications. Coarse aggregate shall be no larger than 9.5 millimeters and shall comprise less than 15 percent of the total aggregate.

Water shall comply with the provisions in Section 90-2.03, "Water," of the Standard Specifications. Water shall be added to the grout mix in an amount to provide a stiff slump (0-50 mm) as determined by ASTM C143. Slump testing shall be performed once for every 10 cubic meters of grout injected, at any change in mix design, and at least twice during each grout shift.

Materials shall be accurately proportioned and thoroughly mixed and agitated to provide grout of uniform consistency.

EQUIPMENT

Equipment used to mix and pump compaction grout shall be specifically designed for that purpose.

The mixer shall be only batch type and equipped with suitable water meters. Sufficient mixer power shall be provided to blend the ingredients into zero slump consistencies.

The pump shall be capable of displacing zero slump grout and shall be able to maintain pressures from 0 to 4.1 Megapascals (MN/mm^2) and rates of displacement as low as 8,500 cubic centimeters per minute. Controls shall be provided to enable the operator to vary the rate of displacement over its entire range uniformly while continuously pumping.

Grout pipes shall be 50.8 to 76.2 millimeter steel casing with adequate strength to withstand the required jacking and pumping pressures.

The pumping system shall be equipped with suitable automatic recording devices that continuously measure and record grout pressures (stroke, back, and surge) at the top injection point, pumping rates, and grout take for each hole and total grout take per work shift. The Contractor shall calibrate instruments for measuring pressures, pumping rate, and volume as determined necessary by the Engineer. Two copies of the complete automatic records shall be submitted to the Engineer at the end of each working day.

CONSTRUCTION PROCEDURES

The Contractor will be provided with a surveyed baseline in each work zone in which his work will be carried out. The Contractor shall determine the position on the ground surface of each grout injection point and the elevation of each injection stage.

The Contractor shall perform coring of the pavement, at the locations shown on the plans and as directed by the Engineer. The coring holes shall be cored by methods that will not shatter or damage the concrete adjacent to them. Holes in the pavement and unpaved embankment shall be cored no more than 72 hours prior to grout injection. Drilled holes shall not remain open when precipitation is predicted within the following 72-hour period. The National Weather Service forecast shall be used. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer.

Water for core drilling operations shall be from a local domestic water supply. Water used for coring shall not contain more than 1000 parts per million of chlorides as Cl, nor more than 1300 parts per million of sulfates as SO_4, nor shall it contain any impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.

The Contractor may push, drive, or drill the grout pipe to the specified depth of grouting; however, there shall be no voids between the grout pipe and the surrounding soil in order to prevent grout leakage and premature upward movement of the grout pipes during grouting. If the grout hole is drilled to full depth and subsequently the grout pipe cannot be advanced to the full depth of grouting, the grout hole shall be cleaned and drilled again until the grout pipe can be advanced to the target depth. If the grout hole tends to collapse during drilling, the grout injection pipe shall be advanced simultaneously with the drilling operation.

At each grout point grout pipes shall be advanced to the elevation shown on the plans or as directed by the Engineer. If refusal is encountered before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves, that grout injection point shall be rejected and backfilled with hydraulic cement grout, complete in place and a new grout injection point shall be drilled adjacent to the rejected hole and the grout pipe advanced to the depth shown in the plans. Grouting shall be conducted in stages as the grout pipe is withdrawn. The interval between stages shall not exceed 0.6 meters. The grout injection hole shall not be greater than 1.0 centimeter in diameter than the outside diameter of the casing. Once grouting of a hole is started it shall be completed in one continuous operation during one shift. If grouting is terminated for any reason before the full depth is grouted, that grout point shall be rejected. A new grout injection point shall be drilled adjacent to the rejected hole and the grout pipe advanced to the depth shown in the plans.

Residue from grouting operations shall not be allowed to flow across shoulders or lanes occupied by traffic, to flow into gutters or other drainage facilities, to flow beyond the highway right of way approved construction staging area, or to be left on the surface of the pavement or embankment. Residue from grouting operations shall become the property of the Contractor and shall be disposed of outside the highway right of way in accordance with Section 7-1.13. "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The rate of grout injection shall not exceed 0.3 cubic meters per minute at an individual grout injection point. However, multiple grout injections may be conducted simultaneously.

The grout points shall be designated as alternating rows of primary and secondary grout points. Two adjacent primary rows of grout points shall be completely grouted before grouting the intermediate secondary row. Compaction grouting cut-off criteria (criteria by which to determine when to stop the injection of grout at any one stage) is as follows, or as directed by the Engineer:

Grout shall be injected at a stage depth until one of the following occurs:

1. Grout flow ceases at the header pressure reading of 6200 kPa (900 psi).
2. Surface ground heave of 3 mm is observed.
3. An injection grout volume equal to 15 percent of the soil volume being treated by that injection stage is reached.

During the grouting operation, the Contractor shall monitor the existing freeway and light rail facilities including, but not limited to, concrete pavement, barriers, storm drains, light rail tracks, unpaved embankment soils, for indications of movement or distress. The Contractor shall establish and monitor a minimum of 10 reference points on the freeway pavement. Overhead poles, electroliers, overhead catenary system poles, and structures within 15 meters of active grout points shall be monitored for movement. Reference points shall be monitored for movement with a laser level system with an accuracy of 0.019 mm at a distance of 30.5 meters.

The Contractor shall provide access to the Engineer for inspection to ascertain the Contractor's work and monitoring of the existing light rail and freeway facilities for movement in accordance with Section 5-1.08, "Inspection," of the Standard Specifications.

The Contractor shall monitor and record the interior of storm drain for signs of distress such as deflection, heaving, or cracking. Distress to the storm drainage pipe shall trigger grout cut-off at any stage. When grouting stage within 3 meters of storm drains, grout pressure shall not exceed 1.7 Megapascals (N/mm^2) unless otherwise directed by the Engineer. Contractor shall inspect all storm drains within 20 meters of compaction grouting by color television inspection camera before and after compaction grouting as specified in “Vitrified Clay Pipe” elsewhere in these special provisons.

The inspection shall be recorded in true color in Beta Max II or VHS ("SP") Cassette format with on-screen footage readout on the lower part of the screen.

A written log in shall accompany the recorded cassette with the following information accompanying the recorded cassette:

1. Date
2. Tape Number
3. Location
4. Pipe Material and Size
5. Name of Equipment Operator
6. Name of Firm Performing the Inspection
7. All deficiencies in the storm drain shall be noted and their location referenced to their on-screen footage readout

The recorded cassette and accompanying report shall be delivered to the Engineer not later than 24 hours after completion of the inspection. The cassette and report shall become the property of the State. The Engineer will review the recorded television inspection and will notify the Contractor whether the review revealed any damage to the storm drain that was not present prior to compaction grouting activities

The following deficiencies in the storm drains due to compaction grouting activities shall be corrected by the Contractor at no cost to the State:

1. Joint separation
2. Offset joints
3. Infiltration points
4. Grout in the line
5. Cracks or broken storm drain
6. Deflections in joints
7. Sagging or heaving

The State will not accept a credit, maintenance bond, or any other form of compensation in lieu of corrective measures that may be required to correct any Contractor damaged sections of storm drain. In addition, should repairs of the storm drains be accomplished by the use of any unauthorized materials or procedure, the Engineer will require replacement of those substandard portions or repairs made to conform to the requirements of these special provisions.

Upon completion of repairs the storm drain main shall be TV inspected and the recorded TV inspection will be reviewed by the Engineer. This process shall be repeated until the review of the recorded television inspection reveals a satisfactory installation.

The Contractor shall monitor and record data at each grout point including location, pumping rate, grout elevation, minimum and maximum grout pressure at each stage, and grout "take" (volume of grout pumped) at each stage.

After compaction grouting is complete, voids in the structural section created by the coring operation shall be cleaned and filled with hydraulic cement grout conforming to ASTM Designation: C1107. At the Contractor's option the grout shall be extended with clean pea gravel by an amount not exceeding that which is printed on the grout's packaging. After placement of the hydraulic cement grout, the material, while still plastic, shall be trowelled smooth to match the pavement surface. The backfill material shall not exhibit any evidence of depressions or surplus material above the level surface of the pavement.

Contractor submittals shall refer to specific field locations by station and offset from baseline as determined by suitable and accurate survey techniques.

Two copies of complete recorded data for drilling and grouting at each grout injection point shall be submitted to the Engineer. One copy shall be submitted to the Engineer immediately upon completion of drilling and grouting at each individual grout injection point.

The Engineer may delete sections or locations from the grouting program should naturally acceptable soil conditions be encountered, should conditions not appropriate for grouting be encountered, or should unacceptable grouting results be obtained, such as performance criteria not being satisfied.

Full compensation for monitoring condition of existing facilities, including maintaining daily records, shall be considered to be included in the contract prices paid for the various contract items requiring monitoring condition of existing facilities and no separate payment will be made therefor.

PERFORMANCE CRITERIA

Compaction grouting shall achieve the following acceptance criteria in the in situ soil between the injection points:

1. Post-grouting average, corrected Standard Penetration Test N-Value exceeding 30 blows per 300 millimeters (ASTM Designation: D1586) or equivalent cone penetrometer tip resistance as determined by the Engineer. Locations to be agreed upon between the grouting contractor and the Engineer. Averaging shall be with values above and below each value.
2. The Contractor will retain an independent soil testing firm to perform testing as directed by the Engineer. Test sections shall be performed before and after compaction grouting.
3. The test locations will be agreed upon by the Engineer within the treatment area. A test shall be performed for at least every sixteen (16) grout injection points. The test shall be performed at the center of the sixteen grout injection points.
4. Regardless of the method selected, the same test method shall be utilized both before and after the compaction grouting.
5. If the test results indicate that the required ground improvement has not been achieved, the Contractor shall revise the grouting program and retest.

MEASUREMENT AND PAYMENT

Compaction grouting shall be measured and paid for by the cubic meter of pumped grout. The State will not pay for volumes of wasted grout or rejected holes.The contract price paid per cubic meter for compaction grouting shall include full compensation for furnishing all labor, materials (including, but not limited to, grout, water, and concrete patch for grout injection points), tools, equipment, and incidentals, and for doing all the work involved in injection and compacting the soil with grout, including the control and disposal of water and other materials from core drilling and backfilling injection points (holes) with hydraulic cement grout, complete in place, including providing submittals, verifying all field utilities, furnishing grout injection points, testing, establish survey reference points, and monitoring the condition of existing facilities, calibrating equipment, and protecting, restoring, repairing, or replacing facilities damaged from the Contractor's work as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

10-1.38 MATERIAL CONTAINING AERIALLY DEPOSITED LEAD

Earthwork involving materials containing aerially deposited lead shall conform to the provisions in "Earthwork" and this section "Material Containing Aerially Deposited Lead" of these special provisions.

Attention is directed to "Aerially Deposited Lead" of these special provisions.

LEAD COMPLIANCE PLAN

The Contractor shall prepare a project specific Lead Compliance Plan to prevent or minimize worker exposure to lead while handling material containing aerially deposited lead. Attention is directed to Title 8, California Code of Regulations, Section 1532.1, “Lead,” for specific Cal-OSHA requirements when working with lead.

The Lead Compliance Plan shall contain the elements listed in Title 8, California Code of Regulations, Section 1532.1(e)(2)(B). Before submission to the Engineer, the Lead Compliance Plan shall be approved by an Industrial Hygienist certified in Comprehensive Practice by the American Board of Industrial Hygiene. The Plan shall be submitted to the Engineer for review and acceptance at least 15 days prior to beginning work in areas containing aerially deposited lead.

The Lead Compliance Plan shall include perimeter air monitoring incorporating upwind and downwind locations as shown on the plans or as approved by the Engineer. Monitoring shall be by personal air samplers using National Institute of Safety and Health (NIOSH) Method 7082. Sampling shall achieve a detection limit of $0.05\mu g/m^3$ of air per day. Daily monitoring shall take place while the Contractor clears and grubs and performs earthwork operations. A single representative daily sample shall be analyzed for lead. Results shall be analyzed and provided to the Engineer within 24 hours. Average lead concentrations shall not exceed $1.5\mu g/m^3$ of air per day. If concentrations exceed this level the Contractor shall stop work and modify the work to prevent release of lead. Monitoring shall be done under the direction of and data reviewed by and signed by a Certified Industrial Hygienist.

The Contractor shall not work in areas containing aerially deposited lead within the project limits, unless authorized in writing by the Engineer, until the Engineer has accepted the Lead Compliance Plan.

Prior to performing work in areas containing aerially deposited lead, personnel who have no prior training or are not current in their training status, including State personnel, shall complete a safety training program provided by the Contractor. The safety training program shall meet the requirements of Title 8, California Code of Regulations, Section 1532.1, "Lead."

Personal protective equipment, training, and washing facilities required by the Contractor's Lead Compliance Plan shall be supplied to State personnel by the Contractor. The number of State personnel will be 5.

The Engineer will notify the Contractor of acceptance or rejection of any submitted or revised Lead Compliance Plan not more than 10 days after submittal of the plan.

The contract lump sum price paid for Lead Compliance Plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in preparing the Lead Compliance Plan, including paying the Certified Industrial Hygienist, and for providing personal protective equipment, training and medical surveillance, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

DUST CONTROL

Excavation, transportation, placement, and handling of materials containing aerially deposited lead shall result in no visible dust migration. The Contractor shall have a water truck or tank on the job site at all times while clearing and grubbing and performing earthwork operations in work areas containing aerially deposited lead.

PAYMENT

Full compensation for conforming to the requirements of this section, except as specifically provided elsewhere in these special provisions, shall be considered as included in the prices paid for various contract items involved and no additional compensation will be allowed therefor.

10-1.39 EROSION CONTROL (BLANKET)

Erosion control (blanket) shall conform to the details shown on the plans, the provisions in Section 20-3, "Erosion Control," of the Standard Specifications and these special provisions.

Erosion control (blanket) work shall consist of applying seed, compost and fiber and installing erosion control blanket to unlined gutters.

MATERIALS

Materials shall conform to the provisions in Section 20-2, "Materials," of the Standard Specifications and these special provisions.

Seed

Seed shall conform to the provisions in Section 20-2.10, "Seed," of the Standard Specifications. Individual seed species shall be measured and mixed in the presence of the Engineer.

Seed not required to be labeled under the California Food and Agricultural Code shall be tested for purity and germination by a seed laboratory certified by the Association of Official Seed Analysts or by a seed technologist certified by the Society of Commercial Seed Technologists.

Seed shall have been tested for purity and germination not more than one year prior to application of seed.

Results from testing seed for purity and germination shall be furnished to the Engineer prior to applying seed.

Seed shall be delivered to the job site in unopened separate containers with the seed tag attached. Containers without a seed tag will not be accepted.

A sample of approximately 30 g of seed will be taken from each seed container by the Engineer.

Non-Legume Seed

Non-legume seed shall consist of the following:

NON-LEGUME SEED

Botanical Name (Common Name)	Percent Germination (Minimum)	Kilograms Pure Live Seed Per Hectare (Slope Measurement)
Vulpia microtachys (Three weeks fescue)	35	5.0
Festuca Idahoensis (Idaho Fescue)	45	17.0
Hordeum California Prostrate (California Barley Prostrate)	45	15.0

Erosion Control Blanket

Erosion control blanket shall consist of straw and coconut or wood excelsior mats secured in place with wire staples and shall conform to one of the following:

A. Excelsior blanket material shall consist of machine produced mats of curled wood excelsior with 80 percent of the fiber 150 mm or longer. The erosion control blanket shall be of consistent thickness and the wood fiber shall be evenly distributed over the entire area of the blanket. The top surface of the blanket shall be covered with a photo-

degradable extruded plastic mesh. The blanket shall be smolder resistant without the use of chemical additives and shall be non-toxic and non-injurious to plant and animal life. Erosion control blanket shall be furnished in rolled strips, 1220 mm ± 25 mm in width, and shall have an average mass of 0.5-kg/m^2 ± 10 percent at the time of manufacture.

B. Straw and coconut/coir blanket shall be machine produced mats of 70 percent straw and a minimum of 30 percent coconut or coir fiber. . The top and bottom surface of the blanket shall be covered with a lightweight photodegradable extruded plastic mesh. The straw and coconut/coir erosion control blanket shall be of consistent thickness with the straw and coconut/coir evenly distributed over the entire area of the blanket. Straw and coconut/coir erosion control blanket shall be furnished in rolled strips with a minimum width of 1.8 meters, minimum length of 20 meters (+/-one meter) and a minimum weight of 0.27 to 0.38-kg/m^2.

C. Staples for erosion control blankets shall be made of 11-gage minimum steel wire and shall be U-shaped with 200-mm legs and 50-mm crown.

APPLICATION

Erosion control (blanket) materials shall be placed as shown on the plans in separate applications as follows:

Seed, fiber and compost shall be applied at the rates indicated in the following table. Hydro-seeding equipment shall be used to apply seed and the mixture shall be applied within 30 minutes after the seed has been added to the mixture.

Material	Kilograms Per Hectare (Slope Measurement)
Fiber	320
Compost	940
Non-Legume Seed	60.0

The second application shall consist of installing the erosion control blanket over the seed, fiber and compost application. Erosion control (blanket) materials shall be placed in unlined ditches as shown on the plans and as follows:

Erosion control blanket strips shall be placed loosely along the unlined gutters with the longitudinal joints parallel to the centerline of the unlined gutters. Longitudinal and transverse joints of blankets shall be overlapped according to the manufacturer's recommendations and stapled. Staples shall be driven perpendicular to the slope face, and shall be located and spaced in conformance with the manufacturer's instructions. Ends of the blankets shall be secured in place in conformance with the manufacturer's instructions.

MEASUREMENT AND PAYMENT

The quantity of erosion control (blanket) will be determined by the square meter from actual slope measurement of the area covered by the erosion control blanket.

The contract price paid per square meter for erosion control (blanket) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing erosion control blanket, complete in place, including furnishing and applying pure live seed, fiber, compost, and the materials for the erosion control blanket, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.40 MOVE-IN/MOVE-OUT (EROSION CONTROL)

Move-in/move-out (erosion control) shall include moving onto the project when an area is ready to receive erosion control as determined by the Engineer, setting up all required personnel and equipment for the application of erosion control materials and moving out all personnel and equipment when erosion control in that area is completed.

When areas are ready to receive applications of erosion control (Types D), as determined by the Engineer, the Contractor shall begin erosion control work in that area within 5 working days of the Engineer’s notification to perform the erosion control work.

Attention is directed to the requirements of erosion control (Types D) elsewhere in these special provisions.

Quantities of move-in/move-out (erosion control) will be determined as units from actual count as determined by the Engineer. For measurement purposes, a move-in followed by a move-out will be considered as one unit.

The contract unit price paid for move-in/move-out (erosion control) shall include full compensation for furnishing all labor, materials (excluding erosion control materials), tools, equipment, and incidentals and for doing all the work involved in moving in and removing from the project all personnel and equipment necessary for application of erosion control (Types D), as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

No adjustment of compensation will be made for any increase or decrease in the quantities of move-in/move-out (erosion control) required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to the item of move-in/move-out (erosion control).

10-1.41 EROSION CONTROL (TYPE D)

Erosion control (Type D) shall conform to the provisions in Section 20-3, "Erosion Control," of the Standard Specifications and these special provisions and shall consist of applying erosion control materials to embankment and excavation slopes and other areas disturbed by construction activities.

Erosion control (Type D) shall be applied when an area is ready to receive erosion control as determined by the Engineer and in conformance with the provisions in "Move-in/Move-out (Erosion Control)" of these special provisions.

Prior to installing erosion control materials, soil surface preparation shall conform to the provisions in Section 19-2.05, "Slopes," of the Standard Specifications, except that rills and gullies exceeding 50 mm in depth or width shall be leveled. Vegetative growth, temporary erosion control materials, and other debris shall be removed from areas to receive erosion control.

MATERIALS

Materials shall conform to the provisions in Section 20-2, "Materials," of the Standard Specifications and these special provisions.

Seed

Seed shall conform to the provisions in Section 20-2.10, "Seed," of the Standard Specifications. Individual seed species shall be measured and mixed in the presence of the Engineer.

Seed shall be delivered to the project site in unopened separate containers with the seed tag attached. Containers without a seed tag attached will not be accepted.

A sample of approximately 30 g of seed will be taken from each seed container by the Engineer.

Legume Seed

Legume seed shall be pellet-inoculated or industrial-inoculated and shall conform to the following:

A. Inoculated seed shall be inoculated in conformance with the provisions in Section 20-2.10, "Seed," of the Standard Specifications.
B. Inoculated seed shall have a calcium carbonate coating.
C. Industrial-inoculated seed shall be inoculated with Rhizobia and coated using an industrial process by a manufacturer whose principal business is seed coating and seed inoculation.
D. Industrial-inoculated seed shall be sown within 180 calendar days after inoculation.
E. Legume seed shall consist of the following:

LEGUME SEED

Botanical Name (Common Name)	Percent Germination (Minimum)	Kilograms Pure Live Seed Per Hectare (Slope Measurement)
Lotus Purshianus (Purshing's Lotus)	60	3.0
Lupinus Bicolor (Miniature Lupine)	49	3.0

Non-Legume Seed

Non-legume seed shall consist of the following:

NON-LEGUME SEED

Botanical Name (Common Name)	Percent Germination (Minimum)	Kilograms Pure Live Seed Per Hectare (Slope Measurement)
Eschscholzia Caespitosa (Dwarf California Poppy)	50	1.0
Festuca Idahoensis (Idaho Fescue)	45	17.0
Nassella Iepida (Foothill Needlegrass)	70	3.0
Poa Secunda (Pine Bluegrass)	40	17.0
Vulpia microstachys (Three weeks fescue)	35	5.0

Straw

Straw shall conform to the provisions in Section 20-2.06, "Straw," of the Standard Specifications and these special provisions.

Wheat and barley straw shall be derived from irrigated crops.

Prior to delivery of wheat or barley straw to the project site, the Contractor shall provide the name, address and telephone number of the grower.

Straw shall be derived from wheat or barley.

Compost

At the option of the Contractor, compost may be either A, B, or any combination of both:

A. Green material consisting of chipped, shredded, or ground vegetation; or clean processed recycled wood products.
B. Class A , exceptional quality biosolids composts, conforming to the requirements in United States Environmental Protection Agency (EPA) regulation 40 CFR, Part 503c.

Compost shall not contain paint, petroleum products, herbicides, fungicides or other chemical residues harmful to plant or animal life. Other deleterious material, plastic, glass, metal or rock shall not exceed 0.1-percent by weight or volume.

Compost shall be thermophilically processed for 15 days. During this process, the compost shall be maintained at minimum internal temperature of 55˚C and be thoroughly turned at least 5 times. A 90-day curing period shall follow the thermophilic process.

Compost shall be screened through a screen no larger than 12 mm.

Compost shall measure at least 6 on the maturity and stability scale with a Solvita test kit.

A Certificate of Compliance for compost shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall state the Solvita maturity and stability scale test result of the compost.

Stabilizing Emulsion

Stabilizing emulsion shall conform to the provisions in Section 20-2.11, "Stabilizing Emulsion," of the Standard Specifications and these special provisions.

Stabilizing emulsion shall be in a dry powder form, may be reemulsifiable, and shall be a processed organic adhesive derivative of Plantago ovata used as a soil tackifier.

APPLICATION

Erosion control materials shall be applied in separate applications in the following sequence:

A. The following mixture in the rates indicated shall be applied with hydro-seeding equipment within 30 minutes after the seed has been added to the mixture:

Material	Kilograms Per Hectare (Slope Measurement)
Fiber	320
Compost	940
Non-Legume Seed	6.0
Legume Seed	35

B. Straw shall be applied at the rate of 4 tonnes per hectare based on slope measurements. Incorporation of straw will not be required. Straw shall be distributed evenly without clumping or piling.
C. The following mixture in the rates indicated shall be applied with hydro-seeding equipment:

Material	Kilograms Per Hectare (Slope Measurement)
Fiber	320
Compost	940
Stabilizing Emulsion (Solids)	140

The ratio of total water to total stabilizing emulsion in the mixture shall be as recommended by the manufacturer.

Once straw work is started in an area, stabilizing emulsion applications shall be completed in that area on the same working day.

The rates of erosion control materials may be changed by the Engineer to meet field conditions.

MEASUREMENT AND PAYMENT

Compost (erosion control) will be measured by the kilogram or tonne, whichever unit is designated in the Engineer's Estimate The weight will be as determined by the Engineer from marked mass and sack count or from scale weighings.

The contract price paid per kilogram or tonne for compost (erosion control) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying compost for erosion control, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.42 FIBER ROLLS

Fiber rolls shall conform to the details shown on the plans and these special provisions.

MATERIALS

Fiber rolls shall consist of one of the following:

A. Fiber rolls shall be constructed with manufactured blankets consisting of one material or a combination of materials consisting of wood excelsior, rice or wheat straw, or coconut fibers. Blankets shall measure approximately 2.0 m to 2.4m wide by 20 m to 29 m in length. Wood excelsior material shall have individual fibers, 80 percent of which shall be 150 mm or longer in fiber length. Blankets shall have a biodegradable jute, sisal or coir fiber netting on at least one side. The blanket shall be rolled on the blanket's width and secured with jute twine spaced 2 m apart along the roll for the full length and 150 mm from each end of the individual rolls. The finished roll diameter shall be a minimum of 200 mm and a maximum of 250 mm and shall weigh not less than 0.81 kg/m. Overlapping of more than one blanket may be required to achieve the finished roll diameter. When overlapping is required, blankets shall be longitudinally overlapped 150 mm along the length of the fabric.
B. Fiber rolls shall be pre-manufactured rice or wheat straw, wood excelsior or coconut fiber rolls encapsulated within a biodegradable jute, sisal or coir fiber netting. Each roll shall be a minimum of 200 mm and a maximum of 250 mm in diameter, 3 m to 6 m in length and shall weigh not less than 1.6 kg/m. The netting shall have a minimum durability of one year after installation. The netting shall be secured tightly at each end of the individual rolls.
C. Stakes shall be fir or pine and shall be a minimum of 19 mm x 38 mm x 450 mm in length.

INSTALLATION

Fiber rolls shall be joined tightly together to form a single linear roll that is installed as shown on the plans. Fiber rolls shall be installed prior to the application of other erosion control materials.

Furrows shall be constructed at a slight angle to the slope contour as shown on the plans, to a depth of 50 mm to 100 mm, and at a sufficient width to hold the fiber rolls.

Rolls shall be installed uniformly along the slope a maximum of 6 m apart (measured along the slope) in the furrows with the first row installed 1.5 m above the toe of slope and top row a maximum of 2 m below the grading conform of slope. Individual rolls shall be placed with adjacent ends butted firmly to each other to create a continuous linear roll.

Stakes shall be installed 1.2 m apart along the total length of the rolls and 125 mm from the end of each individual roll. Stakes shall be driven flush or a maximum of 50 mm above the roll.

MEASUREMENT AND PAYMENT

Fiber rolls will be measured by the meter from end to end along the centerline of the installed rolls.

The contract price paid per meter for fiber rolls shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing fiber rolls, complete in place, including stakes, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.43 IRRIGATION CROSSOVERS

Irrigation crossovers shall conform to the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications and these special provisions.

Attention is directed to “Hazardous, Restricted and Non-Hazardous Material, General,” and “Naturally Occurring Asbestos Material-General,” elsewhere in these special provisions.

Conduits shall be placed in open trenches in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

Conduits shall be bituminous coated corrugated steel pipe.

Conduits shall be corrugated high density polyethylene (CHDPE) pipe. Corrugated high density polyethylene pipe shall conform to the requirements in ASTM Designation: F 405 or F 667, or AASHTO Designation: M 252 or M 294 and shall be Type S. Couplings and fittings shall be as recommended by the pipe manufacturer.

Conduits shall be alternate conduits and, at the option of the Contractor, shall be one of the following:

A. Bituminous coated corrugated steel pipe,
B. Corrugated aluminum pipe,
C. Acrylonitrile-butadiene-styrene (ABS) composite pipe,
D. Corrugated high density polyethylene (CHDPE) pipe conforming to the requirements in ASTM Designation: F 405 or F 667, or AASHTO Designation: M 252 or M 294 and shall be Type S. Couplings and fittings for CHDPE pipe shall be as recommended by the pipe manufacturer.

Water line crossovers shall conform to the provisions in Section 20-5.03C, "Water Line Crossovers," of the Standard Specifications.

Sprinkler control crossovers shall conform to the provisions in Section 20-5.027D, "Sprinkler Control Crossovers," of the Standard Specifications.

Installation of pull boxes shall conform to the provisions in Section 20-5.027I, "Conductors, Electrical Conduit and Pull Boxes," of the Standard Specifications. When no conductors are installed in electrical conduits, pull boxes for irrigation crossovers shall be installed on a foundation of compacted soil.

Conduits shall be installed under existing paving by jacking or drilling methods in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

10-1.44 EXTEND IRRIGATION CROSSOVERS

Extend existing irrigation crossovers shall conform to the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications and these special provisions.

Attention is directed to “Hazardous, Restricted and Non-Hazardous Material, General,” and “Naturally Occurring Asbestos Material-General,” elsewhere in these special provisions.

Extend irrigation crossovers shall include conduit, water line crossover, and sprinkler control crossover extensions and appurtenances, locating existing irrigation crossovers and pressure testing existing and new water line crossovers. The sizes of conduit, water line crossover, and sprinkler control crossover extensions shall be as shown on the plans.

Before work is started in an area where an existing irrigation crossover conduit is to be extended, the existing conduit shall be located by the Contractor. When exploratory holes are used to locate the existing conduit, the exploratory holes shall be excavated in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

If debris is encountered in the ends of conduits to be extended, the debris shall be removed prior to extending conduits. Removal of debris within the first meter in the conduits shall be at the Contractor's expense. If debris is encountered in the conduit more than one meter from the ends of the conduits to be extended, the additional debris shall be removed as directed

by the Engineer and will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Prior to installation of water line crossover extensions, the existing water lines shall be pressure tested for leakage in conformance with the provisions in Section 20-5.03H, "Pressure Testing," of the Standard Specifications. Repairs to the existing water line crossover, when ordered by the Engineer, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Conduit extensions shall be corrugated high density polyethylene (CHDPE) pipe.

Water line crossover extensions shall be plastic pipe (PR 315) (supply line).

Sprinkler control crossover extensions shall be Type 3 electrical conduit.

Conductors shall be removed from existing sprinkler control crossovers to be extended.

After installation of the sprinkler control crossover extensions, new conductors shall be installed without splices in existing and extended sprinkler control crossovers. New conductors shall match the removed conductors in color and size and shall be spliced to the existing conductors in adjacent pull boxes. After the new conductors are installed, the conductors shall be tested in the same manner specified for traffic signal, sign illumination, and lighting circuits in conformance with the provisions in Section 86-2.14B, "Field Testing," of the Standard Specifications.

After water line crossover extensions have been installed, existing and extended water line crossovers shall be retested for leakage in conformance with the provisions in Section 20-5.03H, "Pressure Testing," of the Standard Specifications. Leaks that develop shall be repaired at the Contractor's expense and the water line crossovers shall be retested until a satisfactory pressure test is achieved.

10-1.45 AGGREGATE SUBBASE

Aggregate subbase shall be Class 4 and shall conform to the provisions in Section 25, "Aggregate Subbases," of the Standard Specifications and these special provisions.

The restriction that the amount of reclaimed material included in Class 4 aggregate subbase not exceed 50 percent of the total volume of the aggregate used shall not apply. Aggregate for Class 4 aggregate subbase may include or consist of materials processed from reclaimed asphalt concrete, Portland Cement Concrete, lean concrete base, cement treated base, reclaimed glass or a combination of any of these materials . Aggregate subbase incorporating reclaimed glass shall not be placed at locations where surfacing will not be placed over the aggregate subbase.

The percentage composition by mass of Class 4 aggregate subbase shall conform to the following grading requirements:

Grading Requirements (Percentage Passing)

Sieve Sizes	Operating Range	Contract Compliance
63-mm	100	100
4.75-mm	30-65	25-70
75-µm	0-15	0-18

Class 4 aggregate subbase shall also conform to the following quality requirements:

Quality Requirements

Test	Operating Range	Contract Compliance
Sand Equivalent	21 Min.	18 Min.
Resistance (R-value)	----	50 Min.

The provisions of the last 4 paragraphs in Section 25-1.02A, "Class 1, Class 2, and Class 3 Aggregate Subbases," of the Standard Specifications shall apply to Class 4 aggregate subbase.

At the option of the Contractor, Class 2 aggregate subbase conforming to the grading and quality requirements in Section 25-1.02A, may be used in place of Class 4 aggregate subbase. The restriction that the amount of reclaimed material included in Class 2 aggregate subbase not exceed 50 percent of the total volume of the aggregate used shall not apply. Aggregate for Class 2 aggregate subbase may include reclaimed glass. Aggregate subbase incorporating reclaimed glass shall not be placed at locations where surfacing will not be placed over the aggregate subbase. Once a class of aggregate subbase is selected, the class shall not be changed without written approval of the Engineer.

Regardless of the class of aggregate subbase supplied under the provisions of this section, payment for all aggregate subbase will be made as Class 4 aggregate subbase.

10-1.46 AGGREGATE BASE

Aggregate base shall be Class 3 and shall conform to the provisions in Section 26, "Aggregate Bases," of the Standard Specifications and these special provisions.

The restriction that the amount of reclaimed material included in Class 3 aggregate base not exceed 50 percent of the total volume of the aggregate used shall not apply. Aggregate for Class 3 aggregate base may include or consist of material process from reclaimed asphalt concrete, Portland cement concrete, lean concrete base, cement treated base, glass or combination of any of these materials. Aggregate base incorporating reclaimed glass shall not be placed at locations where surfacing will not be placed over the aggregate base.

Aggregate for Class 3 aggregate base shall conform to the following requirements:

Grading Requirements (Percentage Passing)

	19 mm Maximum		37.5 mm Maximum	
Sieve Sizes	Operating Range	Contract Compliance	Operating Range	Contract Compliance
50-mm			100	100
37.5-mm			90-100	87-100
25-mm	100	100	----	----
19-mm	90-100	87-100	50-85	45-90
4.75-mm	35-60	30-65	25-45	20-50
600-µm	10-30	5-35	10-25	6-29
75-µm	2-11	0-14	2-11	0-14

Quality Requirements

Tests	Operating Range	Contract Compliance
Sand Equivalent	25 min.	22 min.
Resistance (R-value)	---	78 min.
Durability	---	35 min.

The aggregate shall not be treated with lime, cement or other chemical material before the Durability Index test is performed. Untreated reclaimed asphalt concrete and portland cement concrete will not be considered to be treated with lime, cement or other chemical material for purposes of performing the Durability Index test.

10-1.47 CEMENT TREATED BASE

Cement treated base shall conform to the provisions in Section 27, "Cement Treated Bases," of the Standard Specifications and these special provisions.

The portland cement content of the cement treated base shall be 5 percent by mass of the dry aggregate.

A Class 2 plant may be used for batch mixing material that is specified to be plant-mixed.

The aggregate for Class A cement treated base shall conform to the following grading requirements:

Grading Requirements (Percentage Passing)

Sieve Sizes	Operating Range	Contract Compliance
25-mm	100	100
19-mm	90 - 100	87 - 100
4.75-mm	35 - 55	30 - 60
600-µm	10 - 30	5 - 35
75-µm	2 - 9	0 - 12

The aggregate for Class A cement treated base shall conform to the following quality requirements:

Quality Requirements

Test	Operating Range	Contract Compliance
Sand Equivalent	31 Min.	28 Min.

The coarse aggregate material retained on the 4.75-mm sieve shall consist of material of which at least 25 percent by mass shall be crushed particles as determined by California Test 205.

10-1.48 TREATED PERMEABLE BASE

Treated permeable base shall be asphalt treated and shall conform to the provisions in Section 29, "Treated Permeable Bases," of the Standard Specifications.

10-1.49 ASPHALT CONCRETE

Asphalt concrete shall be Type _A_ and shall conform to the provisions in Section 11-1, "Quality Control / Quality Assurance" of these special provisions.

Surfacing of miscellaneous areas with asphalt concrete shall conform to the provisions in "Asphalt Concrete (Miscellaneous Areas)" of these special provisions.

A prime coat of liquid asphalt, Grade SC-7, shall be applied, where shown on the plans.

Paint binder (tack coat) shall be applied to existing surfaces to be surfaced and between layers of asphalt concrete, except when eliminated by the Engineer.

Paint binder (tack coat) shall be paving asphalt conforming to the provisions in Section 39-8.02 of Section 11-1, "Quality Control / Quality Assurance," of these special provisions, and the provisions in Section 94, "Asphalts," of the Standard Specifications. The grade of paving asphalt to be used as paint binder will be determined by the Engineer. Paving asphalt shall be applied at a temperature of not less than 140°C or more than 175°C.

Paint binder (tack coat) shall be applied in the liter per square meter range limits specified for the surfaces to receive asphalt concrete in the tables below. The exact application rate within the range will be determined by the Engineer.

Application Rates for Asphaltic Emulsion Paint Binder (Tack Coat) on Asphalt Concrete (except Open Graded) and on Portland Cement Concrete Pavement (PCCP)		
Type of surface to receive Paint binder (tack coat)	Slow-Setting Asphaltic Emulsion L/m^2 (Note A)	Rapid-Setting Asphaltic Emulsion L/m^2 (Note B)
Dense, compact surfaces, between layers, and on PCCP	0.20 – 0.35	0.10 – 0.20
Open, textured or dry, Aged surfaces	0.35 – 0.90	0.20 – 0.40

Note A: Slow-setting asphaltic emulsion is asphaltic emulsion diluted with additional water. Water shall be added and mixed with the asphaltic emulsion (containing up to 43 percent water) so the resulting mixture contains one part asphaltic emulsion and not more than one part added water. The water shall be added by the emulsion producer or at a facility that has the capability to mix or agitate the combined blend.

Note B: Undiluted rapid-setting asphaltic emulsion

Application Rates for Paint Binder (Tack Coat) on Asphalt Concrete (except Open Graded) and on Portland Cement Concrete Pavement (PCCP)	
Type of surface to receive paint binder (tack coat)	Paving Asphalt L/m^2
Dense, compact surfaces, between layers, and on PCCP	0.05 – 0.10
Open, textured or dry, aged surfaces	0.10 – 0.25

The Contractor may obtain a copy of the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete" at www.dot.ca.gov/hq/construc/qcqa.html.

The aggregate for Type A asphalt concrete shall conform to the 19-mm maximum coarse grading specified in Section 39-2.02, "Aggregate," in Section 11-1, "Quality Control / Quality Assurance," of these special provisions.

In addition to the provisions in Section 39-9.01, "Spreading Equipment," in Section 11-1, "Quality Control / Quality Assurance," of these special provisions, asphalt paving equipment shall be equipped with automatic screed controls and a sensing device or devices.

When placing asphalt concrete to lines and grades established by the Engineer, the automatic controls shall control the longitudinal grade and transverse slope of the screed. Grade and slope references shall be furnished, installed, and maintained by the Contractor. Should the Contractor elect to use a ski device, the minimum length of the ski device shall be 9 m. The ski device shall be a rigid one piece unit and the entire length shall be utilized in activating the sensor.

When placing the initial mat of asphalt concrete on existing pavement, the end of the screed nearest the centerline shall be controlled by a sensor activated by a ski device not less than 9 m long. The end of the screed farthest from centerline shall be controlled manually.

When paving contiguously with previously placed mats, the end of the screed adjacent to the previously placed mat shall be controlled by a sensor that responds to the grade of the previously placed mat and will reproduce the grade in the new mat within a 3 mm tolerance. The end of the screed farthest from the previously placed mat shall be controlled in the same manner the screed was controlled when placing the initial mat.

If the methods and equipment furnished by the Contractor fail to produce a layer of asphalt concrete conforming to the provisions, including straightedge tolerance, in Section 39-10.04, "Compacting," in Section 11-1, "Quality Control / Quality

Assurance," of these special provisions, the paving operations shall be discontinued and the Contractor shall modify the equipment or methods, or furnish substitute equipment.

If the automatic screed controls fail to operate properly during a day's work, the Contractor may use manual control of the spreading equipment for the remainder of that day. However, the equipment shall be corrected or replaced with alternative automatically controlled equipment conforming to the requirements in this section before starting another day's work.

If the finished surface of the asphalt concrete on Route 87 traffic lanes does not meet the specified surface tolerances, the finished surface shall be brought within tolerance by either (1) abrasive grinding (with fog seal coat applied on the areas which have been ground), (2) removal and replacement, or (3) placing an overlay of asphalt concrete. The method will be selected by the Engineer. The corrective work shall be at the Contractor's expense.

If abrasive grinding is used to bring the finished surface to specified surface tolerances, additional grinding shall be performed as necessary to extend the area ground in each lateral direction so that the lateral limits of grinding are at a constant offset from, and parallel to the nearest lane line or pavement edge, and in each longitudinal direction so that the grinding begins and ends at lines normal to the pavement centerline, within a ground area. Ground areas shall be neat rectangular areas of uniform surface appearance. Abrasive grinding shall conform to the provisions in the first paragraph and the last 4 paragraphs in Section 42-2.02, "Construction," of the Standard Specifications.

The area to which paint binder has been applied shall be closed to public traffic. Care shall be taken to avoid tracking binder material onto existing pavement surfaces beyond the limits of construction.

A vertical longitudinal joint of more than 45 mm will not be allowed at any time between adjacent lanes open to public traffic.

Where the existing pavement is to be widened by constructing a new structural section adjacent to the existing pavement, the new structural section, on both sides of the existing pavement, shall be completed to match the elevation of the edge of the existing pavement for the entire length of the project prior to spreading and compacting asphalt concrete over the adjacent existing pavement.

10-1.50 ASPHALT CONCRETE (MISCELLANEOUS AREAS)

Surfacing of miscellaneous areas with asphalt concrete shall conform to the provisions for miscellaneous areas in Section 39, "Asphalt Concrete," of the Standard Specifications and these special provisions.

Asphalt concrete placed in miscellaneous areas may be produced in conformance with the requirements for asphalt concrete placed on the traveled way in Section 11-1, "Quality Control / Quality Assurance," of these special provisions.

The amount of asphalt binder used in asphalt concrete placed in dikes, gutters, gutter flares, overside drains, and aprons at the ends of drainage structures shall be increased one percent by mass of the aggregate over the amount of asphalt binder determined for use in asphalt concrete placed on the traveled way.

Aggregate for asphalt concrete dikes shall conform to the 9.5-mm maximum grading specified in Section 39-2.02, "Aggregate," of the Standard Specifications.

The miscellaneous areas to be paid for at the contract price per square meter for place asphalt concrete (miscellaneous area) in addition to the prices paid for the materials involved shall be limited to the areas listed on the plans.

Asphalt concrete placed in miscellaneous areas will be paid for at the contract price per tonne for asphalt concrete in conformance with the provisions in Section 11-1, "Quality Control / Quality Assurance," of these special provisions. Section 39-11.02, "Statistical Evaluation and Determination of Pay Factor," in Section 11-1, "Quality Control / Quality Assurance," of these special provisions, shall not apply to asphalt concrete placed in miscellaneous areas. Payment for placing asphalt concrete in miscellaneous areas and dikes will be in conformance with the provisions in Section 39-8.02, "Payment," of the Standard Specifications.

10-1.51 CONCRETE PAVEMENT

GENERAL

Portland cement concrete pavement shall be constructed in conformance with the provisions in Section 40, "Portland Cement Concrete Pavement," of the Standard Specifications and these special provisions, and as shown on the plans.

Insert method for forming joints in pavement shall not be used.

PREPAVING CONFERENCE

Supervisory personnel of the Contractor and subcontractors who are to be involved in the concrete paving work shall meet with the Engineer at a prepaving conference, at a mutually agreed time, to discuss methods of accomplishing the paving work.

The Contractor shall provide a facility for the prepaving conference within 5 km of the construction site or at a nearby location agreed to by the Engineer. Attendance at the prepaving conference is mandatory for the Contractor's project superintendent, paving construction foreman, subcontractor's workers, including foremen and personnel performing saw cutting, joint sealing, concrete plant manager, and concrete plant operator. Conference attendees shall sign an attendance

sheet provided by the Engineer. Production and placement shall not begin nor proceed unless the above-mentioned personnel have attended the mandatory prepaving conference.

JUST-IN-TIME TRAINING

Attending a 4-hour Just-In-Time Training (JITT) shall be mandatory, and consist of a formal joint training class on portland cement concrete and paving techniques. Construction operations for portland cement concrete paving shall not begin until the Contractor's and the Engineer's personnel have completed the mandatory JITT. The Contractor's personnel included in the list of participants for the prepaving conference as well as the Engineer's representatives shall attend JITT. JITT shall be in addition to the prepaving conference.

The JITT class will be conducted for not less than 4 hours on portland cement concrete pavement and paving techniques. The training class may be an extension of the prepaving conference and shall be conducted at a project field location convenient for both the Contractor and the Engineer. The JITT class shall be completed at least 15 days, not including Saturdays, Sundays or holidays, prior to the start of portland cement concrete paving operations. The class shall be held during normal working hours.

The JITT instructor shall be experienced in the construction methods, materials, and test methods associated with construction of portland cement concrete pavement and paving techniques. The instructor shall not be an employee of the Contractor or a member of the Engineer's field staff. A copy of the course syllabus, handouts, and presentation material shall be submitted to the Engineer at least 7 days before the day of the training. The Contractor and the Engineer shall mutually agree to course instructor, the course content, and training site. The instructor shall issue a certificate of completion to the participants upon completion of the class. The certificate of completion shall include the course title, date and location of the class, the name of the participant, instructor's name, location and telephone number.

The Contractor's or Engineer's personnel involved with portland cement concrete paving operations will not be required to attend JITT if they have completed equivalent training within the previous 12 months of the date of the JITT for this project. The Contractor shall provide a certificate of class completion as described above for each staff member to be excluded from the JITT class. The Engineer will provide the final determination for exclusion of staff member's participation. Attendees of the JITT shall complete, and submit to the Engineer, an evaluation of the training. The Engineer will provide the course evaluation form.

Just-In-Time Training shall not relieve the Contractor of responsibility under the contract for the successful completion of the work in conformance with the requirements of the plans and specifications.

MATERIALS

Concrete

Attention is directed to Section 90, "Portland Cement Concrete," of the Standard Specifications, regarding mix proportions for concrete being determined by the Contractor.

Primary aggregate gradings shall conform to the gradation requirements of Section 90-3, "Aggregate Gradings," of the Standard Specifications. When combined in the proportions determined by the Contractor, the percent passing the 9.5 mm sieve and retained on the 2.36 mm sieve shall not be less than 16 percent of the total aggregate.

The cementitious material shall not exceed 400 kg/m^3.

Tie Bars

Tie bars shall be deformed reinforcing steel bars conforming to the requirements of ASTM Designation: A 615/A 615M, Grade 300 or 420; ASTM Designation: A 616/A 616M, Grade 350 or 400; or ASTM Designation: A 706/A 706M. Tie bars shall be epoxy-coated in conformance with the requirements in ASTM Designation: A 934/A 934M or A 775/A 775M and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement," of the Standard Specifications, except the epoxy-coating thickness after curing shall be between 175 to 400 micrometers (7 and 16 mils). Fabrication, sampling and jobsite handling shall conform to the requirements in ASTM Designation: D 3963 and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement", of the Standard Specifications, except the two samples shall be 750 mm long. Epoxy-coated tie bars shall not be bent.

Epoxy (Drill and Bond)

Epoxy for bonding tie bars to portland cement concrete shall be a two-component, epoxy-resin, conforming to the requirements of ASTM Designation: C 881, Type V, Grade 3 (Non-Sagging), Class A, B or C. The class used shall be dependent on the internal temperature of the hardened concrete at the time the epoxy is to be applied. Class A shall be used when the internal temperature is below 4.5°C, but not lower than recommended by the manufacturer. Class B shall be used when the internal temperature is from 4.5°C to 15.5°C. Class C shall be used when the internal temperature is above 15.5°C, but not higher than recommended by the manufacturer. A Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished with the epoxy. A copy of the

manufacturer's recommended installation procedure shall be provided to the Engineer at least 7 days prior to the start of work.

Dowels

Dowels shall be smooth, round, epoxy-coated steel conforming to the requirements in ASTM Designation: A 615/A 615M, Grade 300 or 420, the details shown on the plans and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement," of the Standard Specifications. Epoxy coating of dowels shall conform to the provisions in ASTM Designation: A 884/A 884M, Class A, Type 1 or Type 2, except that the bend test shall not apply. Fabrication, sampling and jobsite handling shall conform to the requirements in ASTM Designation: D 3963 and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement," of the Standard Specifications, except the two samples shall be 460 mm long.

Dowels shall be plain, smooth, round bars. Dowels shall be free from burrs or other deformations detrimental to free movement of the bars in the concrete.

Bond Breaker

Dowels shall be lubricated with a bond breaker over the entire bar. A bond breaker application of petroleum paraffin based lubricant or white-pigmented curing compound shall be used to coat the dowels completely prior to placement. Oil and asphalt based bond breakers shall not be used. Paraffin based lubricant shall be Dayton Superior DSC BB-Coat or Valvoline Tectyl 506 or an approved equal. Paraffin based lubricant shall be factory applied. White pigmented curing compound shall conform to the requirements of ASTM Designation: C 309, Type 2, Class A, and shall contain 22 percent minimum nonvolatile vehicles consisting of at least 50 percent paraffin wax. Curing compound shall be applied in two separate applications, the last application not more than 8 hours prior to placement of the dowel bars. Each application of curing compound shall be applied at the approximate rate of one liter per 3.7 m^2.

Load Transfer Assemblies (Dowel Basket)

Load transfer assemblies shall be manufactured with a minimum welded wire gage number of 3/0 (9.2 mm). Assemblies shall be either U-frame or A-frame shape. J-frame shapes shall not be used. Assemblies shall be fabricated in conformance with the requirements in ASTM Designation: A 82. Welding of assemblies shall conform to the requirements in AASHTO Designation: M 254. A broken weld will be a cause for rejection of the assembly. Assemblies shall be Class A, Type 1 epoxy-coated in conformance with the requirements in ASTM Designation: A 884/A 884M. Fabrication and job-site handling shall conform to the requirements in ASTM Designation: D 3963 and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement," of the Standard Specifications, except that sampling of epoxy-coated wire reinforcement will not be required. A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished for each shipment of epoxy-coated wire reinforcement certifying that the coated bars conform to the requirements in ASTM Designation: A 884/A 884M and the provisions in Section 52-1.02B, "Epoxy-coated Bar Reinforcement," of the Standard Specifications. The Certificate of Compliance shall include the certifications specified in ASTM Designation: A 884/A 884M and a statement that the coating material has been pre-qualified by acceptance testing performed by the Valley Forge Laboratories, Inc., Devon, Pennsylvania.

Concrete fasteners shall be used for anchoring dowel bar assemblies to lean concrete base or asphalt concrete base. Concrete fasteners shall be driven fasteners (concrete nails), used specifically for fastening to hardened concrete, conforming to the requirements of ASTM Designation: F 1667. Shank diameter shall be a minimum of 4 mm with a minimum shank length of 64 mm. Clips shall be commercial quality manufactured for use with dowel assemblies.

The surface of concrete fasteners, and clips shall be either zinc electroplated or galvanized with a minimum coating thickness of 0.005-mm.

Silicone Joint Sealant

Low modulus silicone joint sealant shall be furnished in a one-part silicone formulation. Acid cure sealant shall not be used. The compound shall be compatible with the surface to which it is applied and shall conform to the following requirements:

Property	Test Method	Requirement
Tensile stress, 150% elongation, 7-day cure at 25°± 1°C and 45% to 55% R.H.[e]	ASTM D 412 (Die C)	310 kPa max.
Flow at 25° ± 1°C	ASTM C 639[a]	Shall not flow from channel
Extrusion Rate at 25° ± 1°C	ASTM C 603[b]	75-250 g/min.
Specific Gravity	ASTM D 792 Method A	1.01 to 1.51
Durometer Hardness, at –18°C, Shore A, cured 7 days at 25° ± 1°C	ASTM C 661	10 to 25
Ozone and Ultraviolet Resistance, after 5000 hours	ASTM C 793	No chalking, cracking or bond loss
Tack free at 25° ± 1°C and 45% to 55% R.H.[e]	ASTM C 679	Less than 75 minutes
Elongation, 7 day cure at 25° ± 1°C and 45% to 55% R.H.[e]	ASTM D 412 (Die C)	500 percent min.
Set to Touch, at 25° ± 1°C and 45% to 55% R.H.[e]	ASTM D 1640	Less than 75 minutes
Shelf Life, from date of shipment	—	6 months min.
Bond, to concrete mortar-concrete briquettes, air cured 7 days at 25° ± 1°C	AASHTO T 132[c]	345 kPa min.
Movement Capability and Adhesion, 100% extension at –18°C after, air cured 7 days at 25° ± 1°C, and followed by 7 days in water at 25° ± 1°C	ASTM C 719[d]	No adhesive or cohesive failure after 5 cycles

Notes:

a. ASTM Designation: C 639 Modified (15 percent slope channel A).

b. ASTM Designation: C 603, through 3-mm opening at 345 kPa.

c. Mold briquettes in conformance with AASHTO Designation: T 132, sawed in half and bonded with a 1.5 mm maximum thickness of sealant and tested in conformance with AASHTO Designation: T 132. Briquettes shall be dried to constant mass at 100 ± 5° C.

d. Movement Capability and Adhesion: Prepare 305 mm x 25 mm x 75 mm concrete blocks in conformance with ASTM Designation: C 719. A sawed face shall be used for bond surface. Seal 50 mm of block leaving 12.5 mm on each end of specimen unsealed. The depth of sealant shall be 9.5 mm and the width 12.5-mm.

e. R.H. equals relative humidity.

The silicone joint sealant shall be formulated to cure rapidly enough to prevent flow after application on grades of up to 15 percent.

A Certificate of Compliance for the silicone sealant shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate shall also be accompanied with a certified test report of the results of the required tests performed on the sealant material within the previous 12 months prior to proposed use. The Certificate and accompanying test report shall be provided for each lot of silicone joint sealant prior to use on the project.

Backer Rods

Backer rods shall have a diameter prior to placement at least 25 percent greater than the width of the sawcut and shall be expanded, crosslinked, closed-cell polyethylene foam that is compatible with the joint sealant so that no bond or adverse reaction occurs between the rod and sealant. Hot pour sealant that will melt the backer rod shall not be used. The Contractor shall submit a manufacturer's data sheet verifying that the backer rod is compatible with the sealant to be used.

SUBMITTALS

If load transfer assemblies are used, the Contractor shall submit working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The working drawings shall contain details and a materials list with name, address, and telephone number of the supplier of concrete nails, and clips. The Contractor shall submit the working drawings 14 days prior to constructing the initial test strip. The Engineer will have 14 days to approve the working drawings. Should the Engineer fail to complete the review of the working drawings within the time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the working drawings, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

PAVEMENT CONCRETE MIX PROPORTIONS

The minimum cementitious materials content or the maximum water to cementitious materials ratio shall be determined in conformance with the requirements in California Test 559. Trial mixtures shall be made no more than 24 months before field qualification. The maximum water to cementitious materials ratio or minimum cementitious material content shall be that determined from the trial mixtures curve to produce a minimum flexural strength of 4.5 MPa at 42 days age.

At least 14 days prior to field qualification, the Contractor shall submit the proposed pavement concrete mix proportions with laboratory test reports. Laboratory test reports shall include modulus of rupture determined for each trial mixture at ages of 7, 14, 28 and 42 days in conformance with the applicable portions of California Test 559.

Field Qualification

Field qualification of proposed mix proportions will be required prior to placement of paving concrete. The Contractor shall perform field qualification and submit certified test data to the Engineer. Field qualification data shall be based upon the proposed use of materials, mix proportions, mixing equipment, procedures and size of batch.

A concrete mix design will be field qualified when the test results of five beams from a single batch of concrete indicate the average modulus of rupture is at least 3.9 MPa with no single beam lower than 3.8 MPa at an age of the Contractor's choice but not latter than 28 days. Beams shall be tested for modulus of rupture at a minimum of 7, 14, 28 and 42 days of age. Test specimens shall be fabricated and tested in conformance with the requirements in California Test 523.

The certified field qualification test data reports shall include the following:

A. Date of mixing,
B. Mixing equipment and procedures used,
C. Volume of batch in cubic meters and the mass or volume,
D. Type and source of ingredients used,
E. Penetration and slump of the concrete,
F. The air content of the concrete, and
G. The age at time of testing and strength of concrete specimens tested.

Field qualification test data reports shall be signed by a certified representatives in charge of the laboratory that performed the tests.

If the Contractor changes a source of supply or proportions, the Contractor shall submit a new proposed mix design and furnish samples from the new source, or sources, at least 60 days prior to their intended use. The new mix proportions shall be trial batched and field qualified, unless, the Engineer determines the change is not substantive. No extension of contract time will be allowed for the time required to perform the sampling, testing, preparing and qualifying new mix proportions for new aggregate sources proposed by the Contractor.

INSTALLING TIE BARS

Tie bars shall be installed at longitudinal contact joints and longitudinal weakened plane joints as shown on the plans. Consecutive width of new portland cement concrete pavement tied together with tie bars shall not exceed 15 meters. Tie bars shall not be used at a joint where portland cement concrete and asphalt concrete pavements abut.

Tie bars shall be installed at longitudinal joints by one of the following methods:

A. Drilling and bonding tie bars with two-component, epoxy-resin that conforms to this section. Drilled holes shall be cleaned in conformance with the epoxy manufacturer's instructions and shall be dry at the time of placing the epoxy and tie bars. Tie bars will be rotated 180º while being inserted into the epoxy filled holes. Immediately after inserting the tie bars into the epoxy, the tie bars shall be supported as necessary to prevent movement during curing and shall remain undisturbed until the epoxy has cured as specified by the manufacturer instructions. Tie bars that are improperly placed or bonded, as determined by the Engineer, will be rejected. If rejected, new holes shall be drilled and new tie bars shall be placed and securely bonded to the concrete. Rejected tie bars shall be cut flush with the joint face. Exposed ends of tie bars shall be epoxy coated. The center of the new holes shall be offset 75 mm horizontally from the center of the rejected hole to maintain the minimum clearance to the dowel bar. Work necessary to correct improperly bonded tie bars shall be performed at the Contractor's expense.
B. Inserting tie bars into the plastic slipformed concrete before finishing the concrete. Inserted tie bars shall have full contact between the bar and the concrete. When tie bars are inserted through the pavement surface, the concrete over the tie bars shall be reworked and refinished so that there is no evidence on the surface of the completed pavement that there has been an insertion performed. Loose tie bars shall be replaced by drilling and bonding as described in A above, at the Contractor's expense.
C. Using threaded dowel splice couplers fabricated from deformed bar reinforcement material, free of external welding or machining. Threaded dowel splice couplers shall be accompanied by a Certificate of Compliance in conformance

with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications, and shall be accompanied with installation instructions. Installation of threaded dowel splice couplers shall conform to the requirements of the manufacturer's recommendations.

D. Using tie bar assemblies or chairs that conforms with the requirements of these special provisions.

DOWEL PLACEMENT

Dowels shall be centered on the joint within a tolerance of ±50 mm in the longitudinal direction directly over the contact joint or sawcut for the transverse weakened plane joints, as shown on the plans. Prior to placement of the dowels, the Contractor shall submit to the Engineer a written procedure to identify the transverse weakened plane joint locations relative to the middle of the dowel bars and the procedure for consolidating concrete around the dowels. The Contractor's procedure for dowel bar alignment, and concrete consolidation shall be verified by coring in conformance with the requirements in "Core Drilling for Dowel Placement Alignment Assurance Testing" in this section.

Dowels shall be placed at transverse weakened plane joints within shoulder areas.

Dowels shall be placed by using load transfer assemblies (dowel baskets) or by mechanical insertion. Dowels shall be oriented parallel with the pavement lane centerline and surface of the pavement at mid-slab depth. Dowel alignment shall be ±6 mm per 300 mm of dowel length in both horizontal and vertical planes.

When dowels are placed by mechanical insertion, the concrete over the dowel bars shall be reworked and refinished so that there is no evidence on the surface of the completed pavement that there has been any insertion performed.When load transfer assemblies (dowel baskets) are used, they shall be securely anchored firmly to the base to hold the dowel bars at the specified depth and alignment during concrete placement without displacement. A minimum of 8 alternating, equally spaced, concrete fasteners with clips shall be used to anchor each 3.6 m assembly (4 per lower runner wire). At least 10 concrete fasteners shall be used for assembly sections greater than 3.6 m and less than or equal to 4.9 m. Temporary spacer wires connecting load transfer assemblies shall be cut or removed after the assemblies are anchored into position prior to concrete placement. Paving shall be suspended when approved assemblies are not in place at least 60 m in advance of the concrete placement operation. The Engineer may waive this requirement upon written request by the Contractor, in areas, where access is restricted, or other construction limitations are encountered.

Approval of the initial placement of load transfer assemblies shall not constitute acceptance of the final position of the dowel bars.

CORE DRILLING FOR DOWEL PLACEMENT ALIGNMENT ASSURANCE TESTING

Coring, to confirm dowel bar placement and position, shall be provided by the Contractor throughout the project, at locations determined by the Engineer. Each day's paving shall be cored within 2 days by performing one test for every 1670 square meters of doweled pavement or fraction thereof. One test shall consist of drilling two cores, one on each end of a dowel bar to expose both ends and allow measurement for proper alignment. If the cores indicate that dowel bars are not within the allowable tolerances or if air voids exist surrounding the dowel bars, additional cores will be required to determine the limits and severity of unacceptable work.

The holes shall be cored by methods that will not damage the concrete adjacent to the holes. Immediately after coring, the concrete cores shall be submitted to the Engineer for inspection, and the cores shall be identified by the Contractor with a location description.

After removal of cores, core hole voids in concrete pavement shall be cleaned and filled with hydraulic cement grout (non-shrink). After placement of hydraulic cement grout, the material while still plastic shall be finished and textured to match the adjacent pavement surface. The backfill material shall be the same level as the pavement surface.

Water for core drilling operations shall be from a local domestic water supply, and shall contain not more than 1000 parts per million of chlorides as CL, nor more than 1300 parts per million of sulfates as SO_4, nor shall it contain impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.

Water from core drilling operations shall not be permitted to fall on public traffic, to flow across shoulders or lanes occupied by public traffic, or to flow into gutters or other drainage facilities.

Dowel alignment shall be within the specified tolerances. If dowels are found to be installed improperly, the paving operations shall not continue until the Contractor has demonstrated to the Engineer that the problem which caused the improper dowel positioning has been corrected.

Dowels in rejected joints shall be replaced by the Contractor by saw cutting on each side of the rejected joint a minimum of 0.9-m, lifting out concrete to be removed, installing new dowels at the new transverse joints, installing dowel bars and preformed sponge rubber expansion joint filler along the longitudinal joints, placing concrete, and installing new joints. Preformed sponge rubber expansion joint filler shall conform to the requirements in ASTM Designation: D 1752. New dowel holes shall be drilled, not more than 3 mm greater than the dowel bar diameter, by the use of an automatic dowel-drilling rig for the dowels to be installed at the contact joints. Dowels shall be placed, as shown on the plans, for the 2 new transverse contact joints. Original exposed tie bars, located within the slab replacement area, shall be cut flush with the lane or pavement edge and dowel bars shall be installed to replace the tie bars at an offset of 75 mm, horizontally from the tie

bar location. Holes for dowels to be placed along the longitudinal joint shall be drilled, not more than 3 mm greater than the dowel bar diameter, by the use of an automatic dowel-drilling rig for the dowels to be installed at the contact joints

When requested by the Contractor and approved by the Engineer, dowel bars which are more than ±50 mm but less than ±75 mm from being centered directly over the sawcut for the transverse weakened plane joint, may remain in place, and the Contractor shall pay to the State the amount of $32.30 per square meter for the quantity of concrete pavement panels represented by the cores indicating incorrect dowel alignment or improper concrete consolidation around dowels. The quantity of concrete pavement area used to determine the amount payment to the State will be calculated using the panel dimensions for panels adjacent to and inclusive of the joints with incorrect dowel alignment or improper concrete consolidation around dowels. The Department will reduce compensation from moneys due, or that may become due to the Contractor under the contract. This reduced compensation shall be in addition to other adjustments for pavement thickness deficiency in conformance with the provisions in Section 40-1.135, "Pavement Thickness," of the Standard Specifications and in addition to other adjustments for deficient Cleanness Value and coarse aggregate grading; and for deficient Sand Equivalent and fine aggregate grading in conformance with the provisions in Section 90-2.02, "Aggregate," of the Standard Specifications.

LIQUID JOINT SEALANT INSTALLATION

The joint sealant detail for transverse and longitudinal joints, as shown on the plans, shall apply only to weakened plane joints. Weakened plane joints shall be constructed by the sawing method. Should grinding or grooving be required over or adjacent to joints after sealant has been placed, the joint materials shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications, and replaced at the Contractor's expense.

At the Contractor's option, transverse weakened plane joints shall be either Type DSC or Type SSC as shown on the plans. Longitudinal weakened plane joints shall be Type SSC.

Seven days after the concrete pavement placement and not more than 4 hours before placing backer rods and joint sealant materials, the joint walls shall be cleaned by the dry sand blast method and other means as necessary to remove from the joint objectionable material such as soil, asphalt, curing compound, paint and rust. After cleaning the joint, traces of sand, dust and loose material shall be removed from and near the joint for a distance along the pavement surfaces of at least 50 mm on each side of the joint by the use of a vacuum device. Surface moisture shall be removed at the joints by means of compressed air or moderate hot compressed air or other means approved by the Engineer. Drying procedures that leave a residue or film on the joint wall shall not be used. Sandblasting equipment shall have a maximum nozzle diameter size of 6 ± 1-mm and a minimum pressure of 0.62-MPa.

Backer rods shall be installed when the temperature of the portland cement concrete pavement is above the dew point of the air and when the air temperature is 4°C or above. Backer rod shall be installed when the joints to be sealed have been properly patched, cleaned and dried, as determined by the Engineer. Methods of placing backer rod that leave a residue or film on joint walls shall not be used.

Immediately after placement of the backer rod, joint sealant shall be placed in the clean, dry, prepared joints as shown on the plans. The joint sealant shall be applied using a mechanical device with a nozzle shaped to fit inside the joint to introduce the sealant from inside the joint. Adequate pressure shall be applied to the sealant to ensure that the sealant material is extruded evenly and that full continuous contact is made with the joint walls. After application of the sealant, the surface of the sealant shall be recessed as shown on the plans.

Failure of the joint material in either adhesion or cohesion will be cause for rejection of the joint. The finished surface of joint sealant shall conform to the dimensions and allowable tolerances shown on the plans. Rejected joint materials or joint material whose finished surface does not conform to the dimensions shown on the plans, as determined by the Engineer, shall be repaired or replaced, at the Contractor's expense, with joint material that conforms to the requirements.

After each joint is sealed, surplus joint sealer on the pavement surface shall be removed. Traffic shall not be permitted over the sealed joints until the sealant is tack free and set sufficiently to prevent embedment of roadway debris into the sealant.

CONSTRUCTING TRANSVERSE CONTACT JOINTS

A transverse contact (construction) joint shall be constructed, including dowel bars, at the end of each day's work or where concrete placement is interrupted for more than 30 minutes, to coincide with the next weakened plane joint location.

If sufficient concrete has not been mixed to form a slab to match the next weakened plane joint, when an interruption occurs, the excess concrete shall be removed and disposed of back to the last preceding joint. The cost of removing and disposing of excess concrete shall be at the Contractor's expense. Excess material shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

A metal or wooden bulkhead (header) shall be used to form the joint. The bulkhead shall be designed to accommodate the installation of dowel bars.

PROFILE INDEX

The pavement surface shall be profiled, by the Contractor not more than 10 days following concrete placement, in the presence of the Engineer, using a California Profilograph or equivalent in conformance with the requirements in California Test 526, except a blanking band of zero (null) shall be used to determine the Profile Index. Two profiles shall be made within each traffic lane, one meter from and parallel with each lane line.

Profiled pavement shall conform to the following Profile Index requirements:

A. Pavement on tangent alignment and pavement on horizontal curves having a centerline radius of curve 600 m or more shall have a Profile Index of 64 mm or less for each 0.1-km.
B. Pavement on horizontal curves having a centerline radius of curve 300 m or more but less than 600 m and pavement within the superelevation transition of those curves shall have a Profile Index of 128 mm or less for each 0.1-km.

Individual high points in excess of 7.5 mm, as determined by measurements of the profilogram in conformance with the requirements in California Test 526, except using a blanking band of zero (null), shall be reduced by grinding in conformance with the requirements in Section 40-1.10, "Final Finishing," of the Standard Specifications until the high points as indicated by reruns of the profilograph do not exceed 7.5 mm.

Pavement grinding shall not be performed before 10 days have elapsed after concrete placement, nor before the concrete has developed a modulus of rupture of at least 3.8 MPa.

MEASUREMENT AND PAYMENT

The contract price paid per meter for seal pavement joint shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in sealing pavement joints complete in place, including sawing, cleaning and preparing the joints in the concrete pavement, furnishing and installing backer rod, repairing and patching spalled or raveled sawed joints, and replacing or repairing rejected joints, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Concrete pavement will be measured by the cubic meter in conformance with the provisions in Section 40-1.13, "Measurement," of the Standard Specifications. No deduction will be made for the volume of epoxy-coated dowel bars, epoxy-coated tie bars and, when used, tie bar assemblies or chairs with fasteners and dowel assemblies with fasteners, in the concrete pavement.

The contract price paid per cubic meter for concrete pavement shall include full compensation for furnishing all labor, materials (including cementitious material in the amount determined by the Contractor), tools, equipment, and incidentals, and for doing all the work involved in constructing the portland cement concrete pavement complete in place, including furnishing and placing epoxy-coated dowel bars, epoxy-coated tie bars and, when used, any dowel assemblies with fasteners, submittal to the Engineer all test data for determination of mix proportions of concrete for concrete pavement and for providing the facility, Contractor personnel and all the work involved in arranging and holding the prepaving conference, for constructing and repairing all joints; for performing all profile checks for Profile Index and furnishing final profilograms to the Engineer; for grooving and grinding required for final finishing; and for removing, and replacing pavement for deficient thickness, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for drilling holes and bonding tie bars with epoxy resin shall be considered as included in the contract price paid per cubic meter for concrete pavement and no additional compensation will be allowed therefor.

Costs for providing JITT will be determined in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications, except no markups shall be added, and the Contractor will be paid for one half of the JITT cost. Costs for providing JITT shall include training materials, class site, and the JITT instructor including the JITT instructor's travel, lodging, meals and presentation materials. All costs incurred by the Contractor or Engineer for attending JITT shall be borne by the party incurring the costs.

Full compensation for core drilling for dowel bar alignment and backfilling with hydraulic cement grout shall be considered as included in the contract price per cubic meter for concrete pavement and no additional compensation will be allowed therefor.

If the initial cores show the dowels are out of alignment and the Engineer orders additional dowel coring, full compensation for drilling the additional cores shall be considered as included in the contract price per cubic meter for concrete pavement and no additional compensation will be allowed therefor.

If the initial cores show that the dowels are within alignment tolerances and the Engineer orders more dowel coring than the one test for every 1670 square meters of doweled pavement, the additional cores will be paid for as extra work in conformance with the provisions in Section 4-1.03D, "Extra Work," of the Standard Specifications.

10-1.52 PILING

GENERAL

Piling shall conform to the provisions in Section 49, "Piling," of the Standard Specifications, and these special provisions.

Attention is directed to “Hazardous, Restricted and Non-Hazardous Material, General,” and “Naturally Occurring Asbestos Material-General,” elsewhere in these special provisions.

Unless otherwise specified, welding of any work performed in conformance with the provisions in Section 49, "Piling," of the Standard Specifications, shall be in conformance with the requirements in AWS D1.1.

Foundation recommendations are included in the "Information Handout" available to the Contractor as provided for in Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications.

Attention is directed to "Welding" of these special provisions.

Alternative "X" type piles shall have a dimension, T, not less than 355 mm.

Jetting

Jetting to obtain the specified penetration in conformance with the provisions in Section 49-1.05, "Driving Equipment," of the Standard Specifications shall not be used for driven type piles.

Predrilled Holes

Piles shall be driven in oversized drilled holes in conformance with the provisions in Section 49-1.06, "Predrilled Holes," of the Standard Specifications at the locations and to the corresponding bottom of hole elevations listed in the following table:

Bridge Name or Number	Abutment Number		Elevation of Bottom of Hole
Almaden Overhead (WIDEN)	1 and 4		37
Alma Avenue UC (WIDEN)	1 and 2		34
Alma Station PUC (WIDEN)	1 and 2		34
Alma Station Separate (WIDEN)	1 and 4		33
Willow Street Viaduct (WIDEN)	1 and 5		32

CAST-IN-DRILLED-HOLE CONCRETE PILES

Cast-in-drilled-hole concrete piling shall conform to the provisions in Section 49-4, "Cast-In-Place Concrete Piles," of the Standard Specifications and these special provisions.

Attention is directed to “Hazardous, Restricted and Non-Hazardous Material, General,” and “Naturally Occurring Asbestos Material-General,” elsewhere in these special provisions.

The provisions of "Welding" of these special provisions shall not apply to temporary steel casings.

Cast-in-drilled-hole concrete piles 600 mm in diameter or larger may be constructed by excavation and depositing concrete under slurry.

Materials

Concrete deposited under slurry shall have a nominal penetration equal to or greater than 90 mm. Concrete shall be proportioned to prevent excessive bleed water and segregation.

Concrete deposited under slurry shall contain not less than 400 kg of cementitious material per cubic meter.

The combined aggregate grading used in concrete for cast-in-drilled-hole concrete piling shall be either the 25-mm maximum grading, the 12.5-mm maximum grading, or the 9.5-mm maximum grading and shall conform to the requirements in Section 90-3 "Aggregate Gradings," of the Standard Specifications.

Mineral Slurry

Mineral slurry shall be mixed and thoroughly hydrated in slurry tanks, and slurry shall be sampled from the slurry tanks and tested before placement in the drilled hole.

Slurry shall be recirculated or continuously agitated in the drilled hole to maintain the specified properties.

Recirculation shall include removal of drill cuttings from the slurry before discharging the slurry back into the drilled hole. When recirculation is used, the slurry shall be sampled and tested at least every 2 hours after beginning its use until tests show that the samples taken from the slurry tank and from near the bottom of the hole have consistent specified properties. Subsequently, slurry shall be sampled at least twice per shift as long as the specified properties remain consistent.

Slurry that is not recirculated in the drilled hole shall be sampled and tested at least every 2 hours after beginning its use. The slurry shall be sampled midheight and near the bottom of the hole. Slurry shall be recirculated when tests show that the samples taken from midheight and near the bottom of the hole do not have consistent specified properties.

Slurry shall also be sampled and tested prior to final cleaning of the bottom of the hole and again just prior to placing concrete. Samples shall be taken from midheight and near the bottom of the hole. Cleaning of the bottom of the hole and placement of the concrete shall not start until tests show that the samples taken from midheight and near the bottom of the hole have consistent specified properties.

Mineral slurry shall be tested for conformance to the requirements shown in the following table:

MINERAL SLURRY		
PROPERTY	REQUIREMENT	TEST
Density (kg/m^3) - before placement in the drilled hole - during drilling - prior to final cleaning - immediately prior to placing concrete	1030* to 1110* 1030* to 1200*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) bentonite attapulgite	29 to 53 29 to 42	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8 to 10.5	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning - immediately prior to placing concrete	less than or equal to 4.0	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m^3. Slurry temperature shall be at least 4 degrees Celsius when tested.		

Any caked slurry on the sides or bottom of hole shall be removed before placing reinforcement. If concrete is not placed immediately after placing reinforcement, the reinforcement shall be removed and cleaned of slurry, the sides of the drilled hole cleaned of caked slurry, and the reinforcement again placed in the hole for concrete placement.

Synthetic Slurry

Synthetic slurries shall be used in conformance with the manufacturer's recommendations and these special provisions. The following synthetic slurries may be used:

PRODUCT	MANUFACTURER
SlurryPro CDP	KB Technologies Ltd. 3648 FM 1960 West Suite 107 Houston, TX 77068 (800) 525-5237
Super Mud	PDS Company c/o Champion Equipment Company 8140 East Rosecrans Ave. Paramount, CA 90723 (562) 634-8180
Shore Pac GCV	CETCO Drilling Products Group 1350 West Shure Drive Arlington Heights, IL 60004 (847) 392-5800

Inclusion of a synthetic slurry on the above list may be obtained by meeting the Department's requirements for synthetic slurries. The requirements can be obtained from the Office of Structure Design, P.O. Box 942874, Sacramento, CA 94274-0001.

Synthetic slurries listed may not be appropriate for a given site.

Synthetic slurries shall not be used in holes drilled in primarily soft or very soft cohesive soils as determined by the Engineer.

A manufacturer's representative, as approved by the Engineer, shall provide technical assistance for the use of their product, shall be at the site prior to introduction of the synthetic slurry into a drilled hole, and shall remain at the site until released by the Engineer.

Synthetic slurries shall be sampled and tested at both mid-height and near the bottom of the drilled hole. Samples shall be taken and tested during drilling as necessary to verify the control of the properties of the slurry. Samples shall be taken and tested when drilling is complete, but prior to final cleaning of the bottom of the hole. When samples are in conformance with the requirements shown in the following tables for each slurry product, the bottom of the hole shall be cleaned and any loose or settled material removed. Samples shall be obtained and tested after final cleaning and immediately prior to placing concrete.

SlurryPro CDP synthetic slurries shall be tested for conformance to the requirements shown in the following table:

SLURRYPRO CDP KB Technologies Ltd.		
PROPERTY	REQUIREMENT	TEST
Density (kg/m^3) - during drilling - prior to final cleaning - just prior to placing concrete	 less than or equal to 1075* less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling - prior to final cleaning - just prior to placing concrete	 53 to 127 less than or equal to 74	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	6 to 11.5	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning - just prior to placing concrete	 less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m^3. Slurry temperature shall be at least 4 degrees Celsius when tested.		

Super Mud synthetic slurries shall be tested for conformance to the requirements shown in the following table:

SUPER MUD PDS Company		
PROPERTY	REQUIREMENT	TEST
Density (kg/m^3) - prior to final cleaning - just prior to placing concrete	less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling - prior to final cleaning - just prior to placing concrete	34 to 64 less than or equal to 64	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8 to 10.0	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m^3. Slurry temperature shall be at least 4 degrees Celsius when tested.		

Shore Pac GCV synthetic slurries shall be tested for conformance to the requirements shown in the following table:

Shore Pac GCV CETCO Drilling Products Group		
PROPERTY	REQUIREMENT	TEST
Density (kg/m^3) - prior to final cleaning - just prior to placing concrete	less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling - prior to final cleaning - just prior to placing concrete	35 to 78 less than or equal to 60	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8.0 to 11.0	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m^3. Slurry temperature shall be at least 4 degrees Celsius when tested.		

Water Slurry

At the option of the Contractor water may be used as slurry when casing is used for the entire length of the drilled hole. Water slurry shall be tested for conformance to the requirements shown in the following table:

WATER SLURRY		
PROPERTY	REQUIREMENT	TEST
Density (kg/m^3) - prior to final cleaning - just prior to placing concrete	1017 *	Mud Weight (Density) API 13B-1 Section 1
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, salt water slurry may be used, and the allowable densities may be increased up to 32 kg/m^3.		

Construction

The Contractor shall submit a placing plan to the Engineer for approval prior to producing the test batch for cast-in-drilled-hole concrete piling and at least 10 working days prior to constructing piling. The plan shall include complete descriptions, details, and supporting calculations as listed below:

A. Requirements for all cast-in-drilled hole concrete piling:

1. Concrete mix design, certified test data, and trial batch reports.
2. Drilling or coring methods and equipment.
3. Proposed method for casing installation and removal when necessary.
4. Plan view drawing of pile showing reinforcement and inspection pipes, if required.
5. Methods for placing, positioning, and supporting bar reinforcement.
6. Methods and equipment for accurately determining the depth of concrete and actual and theoretical volume placed, including effects on volume of concrete when any casings are withdrawn.
7. Methods and equipment for verifying that the bottom of the drilled hole is clean prior to placing concrete.
8. Methods and equipment for preventing upward movement of reinforcement, including the Contractor's means of detecting and measuring upward movement during concrete placement operations.

B. Additional requirements when concrete is placed under slurry:

1. Concrete batching, delivery, and placing systems, including time schedules and capacities therefor. Time schedules shall include the time required for each concrete placing operation at each pile.
2. Concrete placing rate calculations. When requested by the Engineer, calculations shall be based on the initial pump pressures or static head on the concrete and losses throughout the placing system, including anticipated head of slurry and concrete to be displaced.
3. Suppliers' test reports on the physical and chemical properties of the slurry and any proposed slurry chemical additives, including Material Safety Data Sheet.
4. Slurry testing equipment and procedures.
5. Methods of removal and disposal of excavation, slurry, and contaminated concrete, including removal rates.
6. Methods and equipment for slurry agitating, recirculating, and cleaning.

In addition to compressive strength requirements, the consistency of the concrete to be deposited under slurry shall be verified before use by producing a test batch. The test batch shall be produced and delivered to the project under conditions

and in time periods similar to those expected during the placement of concrete in the piles. Concrete for the test batch shall be placed in an excavated hole or suitable container of adequate size to allow for testing as specified herein. Depositing of test batch concrete under slurry will not be required. In addition to meeting the specified nominal penetration, the test batch shall meet the following requirements:

A. For piles where the time required for each concrete placing operation, as submitted in the placing plan, will be 2 hours or less, the test batch shall demonstrate that the proposed concrete mix design achieves either a penetration of at least 50 mm or a slump of at least 125 mm after twice that time has elapsed.
B. For piles where the time required for each concrete placing operation, as submitted in the placing plan, will be more than 2 hours, the test batch shall demonstrate that the proposed concrete mix design achieves either a penetration of at least 50 mm or a slump of at least 125 mm after that time plus 2 hours has elapsed.

The time period shall begin at the start of placement. The concrete shall not be vibrated or agitated during the test period. Penetration tests shall be performed in conformance with the requirements in California Test 533. Slump tests shall be performed in conformance with the requirements in ASTM Designation: C 143. Upon completion of testing, the concrete shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The concrete deposited under slurry shall be carefully placed in a compact, monolithic mass and by a method that will prevent washing of the concrete. Concrete deposited under slurry need not be vibrated. Placing concrete shall be a continuous operation lasting not more than the time required for each concrete placing operation at each pile, as submitted in the placing plan, unless otherwise approved in writing by the Engineer. The concrete shall be placed with concrete pumps and delivery tube system of adequate number and size to complete the placing of concrete in the time specified. The delivery tube system shall consist of one of the following:

A. A tremie tube or tubes, each of which are at least 250 mm in diameter, fed by one or more concrete pumps.
B. One or more concrete pump tubes, each fed by a single concrete pump.

The delivery tube system shall consist of watertight tubes with sufficient rigidity to keep the ends always in the mass of concrete placed. If only one delivery tube is utilized to place the concrete, the tube shall be placed near the center of the drilled hole. Multiple tubes shall be uniformly spaced in the hole. Internal bracing for the steel reinforcing cage shall accommodate the delivery tube system. Tremies shall not be used for piles without space for a 250-mm tube.

Spillage of concrete into the slurry during concrete placing operations shall not be allowed. Delivery tubes shall be capped with a watertight cap, or plugged above the slurry level with a good quality, tight fitting, moving plug that will expel the slurry from the tube as the tube is charged with concrete. The cap or plug shall be designed to be released as the tube is charged. The pump discharge or tremie tube shall extend to the bottom of the hole before charging the tube with concrete. After charging the delivery tube system with concrete, the flow of concrete through a tube shall be induced by slightly raising the discharge end. During concrete placement, the tip of the delivery tube shall be maintained as follows to prevent reentry of the slurry into the tube. Until at least 3 m of concrete has been placed, the tip of the delivery tube shall be within 150 mm of the bottom of the drilled hole, and then the embedment of the tip shall be maintained at least 3 m below the top surface of the concrete. Rapid raising or lowering of the delivery tube shall not be permitted. If the seal is lost or the delivery tube becomes plugged and must be removed, the tube shall be withdrawn, the tube cleaned, the tip of the tube capped to prevent entrance of the slurry, and the operation restarted by pushing the capped tube 3 m into the concrete and then reinitiating the flow of concrete.

When slurry is used, a fully operational standby concrete pump, adequate to complete the work in the time specified, shall be provided at the site during concrete placement. The slurry level shall be maintained within 300 mm of the top of the drilled hole.

A log of concrete placement for each drilled hole shall be maintained by the Contractor when concrete is deposited under slurry. The log shall show the pile location, tip elevation, dates of excavation and concrete placement, total quantity of concrete deposited, length and tip elevation of any casing, and details of any hole stabilization method and materials used. The log shall include a 215 mm x 280 mm sized graph of the concrete placed versus depth of hole filled. The graph shall be plotted continuously throughout placing of concrete. The depth of drilled hole filled shall be plotted vertically with the pile tip oriented at the bottom and the quantity of concrete shall be plotted horizontally. Readings shall be made at least at each 1.5 m of pile depth, and the time of the reading shall be indicated. The graph shall be labeled with the pile location, tip elevation, cutoff elevation, and the dates of excavation and concrete placement. The log shall be delivered to the Engineer within one working day of completion of placing concrete in the pile.

After placing reinforcement and prior to placing concrete in the drilled hole, if drill cuttings settle out of the slurry, the bottom of the drilled hole shall be cleaned. The Contractor shall verify that the bottom of the drilled hole is clean.

If temporary casing is used, concrete placed under slurry shall be maintained at a level at least 1.5 m above the bottom of the casing. The withdrawal of casings shall not cause contamination of the concrete with slurry.

Acceptance Testing and Mitigation

Vertical inspection pipes for acceptance testing shall be provided in all cast-in-drilled-hole concrete piles that are 600 mm in diameter or larger, except when the holes are dry or when the holes are dewatered without the use of temporary casing to control ground water.

Inspection pipes shall be Schedule 40 polyvinyl chloride pipes with a nominal inside diameter of 50 mm. Each inspection pipe shall be capped top and bottom and shall have watertight couplers to provide a clean, dry and unobstructed 50-mm diameter clear opening from 1.0 m above the pile cutoff down to the bottom of the reinforcing cage.

Inspection pipes shall be placed around the pile, inside the outermost spiral or hoop reinforcement, and 75 mm clear of the vertical reinforcement, at a uniform spacing not exceeding 840 mm measured along the circle passing through the centers of inspection pipes. A minimum of 2 inspection pipes per pile shall be used. When the vertical reinforcement is not bundled and each bar is not more than 26 mm in diameter, inspection pipes may be placed 50 mm clear of the vertical reinforcement. The inspection pipes shall be placed to provide the maximum diameter circle that passes through the centers of the inspection pipes while maintaining the clear spacing required herein. The pipes shall be installed in straight alignment, parallel to the main reinforcement, and securely fastened in place to prevent misalignment during installation of the reinforcement and placing of concrete in the hole.

The Contractor shall log the location of the inspection pipe couplers with respect to the plane of pile cut off, and these logs shall be delivered to the Engineer upon completion of the placement of concrete in the drilled hole.

After placing concrete and before requesting acceptance tests, each inspection pipe shall be tested by the Contractor in the presence of the Engineer by passing a 48.3-mm diameter rigid cylinder 610 mm long through the complete length of pipe. If the 48.3-mm diameter rigid cylinder fails to pass any of the inspection pipes, the Contractor shall attempt to pass a 32.0-mm diameter rigid cylinder 1.375 m long through the complete length of those pipes in the presence of the Engineer. If an inspection pipe fails to pass the 32.0-mm diameter cylinder, the Contractor shall immediately fill all inspection pipes in the pile with water.

The Contractor shall replace each inspection pipe that does not pass the 32.0-mm diameter cylinder with a 50.8-mm diameter hole cored through the concrete for the entire length of the pile. Cored holes shall be located as close as possible to the inspection pipes they are replacing and shall be no more than 150 mm inside the reinforcement. Coring shall not damage the pile reinforcement. Cored holes shall be made with a double wall core barrel system utilizing a split tube type inner barrel. Coring with a solid type inner barrel will not be allowed. Coring methods and equipment shall provide intact cores for the entire length of the pile concrete. The coring operation shall be logged by an Engineering Geologist or Civil Engineer licensed in the State of California and experienced in core logging. Coring logs shall include complete descriptions of inclusions and voids encountered during coring, and shall be delivered to the Engineer upon completion. Concrete cores shall be preserved, identified with the exact location the core was recovered from within the pile, and made available for inspection by the Engineer.

Acceptance tests of the concrete will be made by the Engineer, without cost to the Contractor. Acceptance tests will evaluate the homogeneity of the placed concrete. Tests will include gamma-gamma logging. Tests may also include crosshole sonic logging and other means of inspection selected by the Engineer. The Contractor shall not conduct operations within 8.0 m of the gamma-gamma logging operations. The Contractor shall separate reinforcing steel as necessary to allow the Engineer access to the inspection pipes to perform gamma-gamma logging or other acceptance testing. After requesting acceptance tests and providing access to the piling, the Contractor shall allow 3 weeks for the Engineer to conduct these tests and make determination of acceptance if the 48.3-mm diameter cylinder passed all inspection pipes, and 4 weeks if only the 32.0-mm diameter cylinder passed all inspection pipes. Should the Engineer fail to complete these tests within the time allowance, and if in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in inspection, the delay will be considered a right of way delay as specified in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

All inspection pipes and cored holes in a pile shall be dewatered and filled with grout after notification by the Engineer that the pile is acceptable. Placement and removal of water in the inspection pipes shall be at the Contractor’s expense. Grout shall conform to the provisions in Section 50-1.09, "Bonding and Grouting," of the Standard Specifications. The inspection pipes and holes shall be filled using grout tubes that extend to the bottom of the pipe or hole or into the grout already placed.

If acceptance testing performed by the Engineer determines that a pile does not meet the requirements of the specifications, then that pile will be rejected and all depositing of concrete under slurry or concrete placed using temporary casing for the purpose of controlling groundwater shall be suspended until written changes to the methods of pile construction are approved in writing by the Engineer.

The Contractor shall submit to the Engineer for approval a mitigation plan for repair, supplementation, or replacement for each rejected cast-in-drilled-hole concrete pile, and this plan shall conform to the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. Prior to submitting this mitigation plan, the Engineer will hold a repair feasibility meeting with the Contractor to discuss the feasibility of repairing rejected piling. The Engineer will consider the

size of the defect, the location of the defect, and the design information and corrosion protection considerations for the pile. This information will be made available to the Contractor, if appropriate, for the development of the mitigation plan. If the Engineer determines that it is not feasible to repair the rejected pile, the Contractor shall not include repair as a means of mitigation and shall proceed with the submittal of a mitigation plan for replacement or supplementation of the rejected pile.

If the Engineer determines that a rejected pile does not require mitigation due to structural, geotechnical, or corrosion concerns, the Contractor may elect to 1) repair the pile per the approved mitigation plan, or 2) not repair anomalies found during acceptance testing of that pile. For such unrepaired piles, the Contractor shall pay to the State, $400 per cubic meter for the portion of the pile affected by the anomalies. The volume, in cubic meters, of the portion of the pile affected by the anomalies, shall be calculated as the area of the cross-section of the pile affected by each anomaly, in square meters, as determined by the Engineer, multiplied by the distance, in meters, from the top of each anomaly to the specified tip of the pile. If the volume calculated for one anomaly overlaps the volume calculated for additional anomalies within the pile, the calculated volume for the overlap shall only be counted once. In no case shall the amount of the payment to the State for any such pile be less than $400. The Department may deduct the amount from any moneys due, or that may become due the Contractor under the contract.

Pile mitigation plans shall include the following:

A. The designation and location of the pile addressed by the mitigation plan.
B. A review of the structural, geotechnical, and corrosion design requirements of the rejected pile.
C. A step by step description of the mitigation work to be performed, including drawings if necessary.
D. An assessment of how the proposed mitigation work will address the structural, geotechnical, and corrosion design requirements of the rejected pile.
E. Methods for preservation or restoration of existing earthen materials.
F. A list of affected facilities, if any, with methods and equipment for protection of these facilities during mitigation.
G. The State assigned contract number, bridge number, full name of the structure as shown on the contract plans, District-County-Route-Kilometer Post, and the Contractor's (and Subcontractor's if applicable) name on each sheet.
H. A list of materials, with quantity estimates, and personnel, with qualifications, to be used to perform the mitigation work.
I. The seal and signature of an engineer who is licensed as a Civil Engineer by the State of California.

For rejected piles to be repaired, the Contractor shall submit a pile mitigation plan that contains the following additional information:

A. An assessment of the nature and size of the anomalies in the rejected pile.
B. Provisions for access for additional pile testing if required by the Engineer.

For rejected piles to be replaced or supplemented, the Contractor shall submit a pile mitigation plan that contains the following additional information:

A. The proposed location and size of additional piling.
B. Structural details and calculations for any modification to the structure to accommodate the replacement or supplemental piling.

All provisions for cast-in-drilled-hole concrete piling shall apply to replacement piling.

The Contractor shall allow the Engineer 3 weeks to review the mitigation plan after a complete submittal has been received.

Should the Engineer fail to review the complete pile mitigation submittal within the time specified, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the pile mitigation plan, an extension of time commensurate with the delay in completion of the work thus caused will be granted in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

When repairs are performed, the Contractor shall submit a mitigation report to the Engineer within 10 days of completion of the repair. This report shall state exactly what repair work was performed and quantify the success of the repairs relative to the submitted mitigation plan. The mitigation report shall be stamped and signed by an engineer that is licensed as a Civil Engineer by the State of California. The mitigation report shall show the State assigned contract number, bridge number, full name of the structure as shown on the contract plans, District-County-Route-Kilometer Post, and the Contractor (and Subcontractor if applicable) name on each sheet. The Engineer will be the sole judge as to whether a mitigation proposal is acceptable, the mitigation efforts are successful, and to whether additional repairs, removal and replacement, or construction of a supplemental foundation is required.

MEASUREMENT AND PAYMENT (PILING)

Measurement and payment for the various types and classes of piles shall conform to the provisions in Sections 49-6.01, "Measurement," and 49-6.02, "Payment," of the Standard Specifications and these special provisions.

Payment for cast-in-place concrete piling shall conform to the provisions in Section 49-6.02, "Payment," of the Standard Specifications and these special provisions except that, when the diameter of cast-in-place concrete piling is shown on the plans as 600 mm or larger, reinforcement in the piling will be paid for by the kilogram as bar reinforcing steel (bridge).

Full compensation for slurry, depositing concrete under slurry, test batches, inspection pipes, filling inspection holes and pipes with grout, drilling oversized cast-in-drilled-hole concrete piling, filling cave-ins and oversized piles with concrete, and redrilling through concrete, shall be considered as included in the contract prices paid per meter for cast-in-drilled-hole concrete piling of the types and sizes listed in the Engineer's Estimate, and no additional compensation will be allowed therefor.

10-1.53 PRESTRESSING CONCRETE

Prestressing concrete shall conform to the provisions in Section 50, "Prestressing Concrete," of the Standard Specifications and these special provisions.

The number of working drawings to be submitted for initial review shall be 6 sets.

The details shown on the plans for cast-in-place prestressed box girder bridges are based on a bonded full length draped tendon prestressing system. For these bridges the Contractor may, in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications, propose an alternative prestressing system utilizing bonded partial length tendons provided the proposed system and associated details meet the following requirements:

A. The proposed system and details shall provide moment and shear resistances at least equal to those used for the design of the structure shown on the plans.
B. The concrete strength shall not be less than that shown on the plans.
C. Not less than 35 percent of the total prestressing force at any section shall be provided by full length draped tendons.
D. Anchorage blocks for partial length tendons shall be located so that the blocks will not interfere with the placement of the utility facilities shown on the plans or of any future utilities to be placed through openings shown on the plans.
E. Temporary prestressing tendons, if used, shall be detensioned, and the temporary ducts shall be filled with grout before completion of the work. Temporary tendons shall be either removed or fully encased in grout before completion of the work.
F. All details of the proposed system, including supporting checked calculations, shall be included in the drawings submitted in conformance with the provisions in Section 50-1.02, "Drawings," of the Standard Specifications.

Moments and shears for loads used in the design shown on the plans will be made available to the Contractor upon written request to the Engineer.

10-1.54 CONCRETE STRUCTURES

Portland cement concrete structures shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Attention is directed to "Precast Concrete Quality Control" of these special provisions.

Shotcrete shall not be used as an alternative construction method for reinforced concrete members unless otherwise specified.

When a roughened concrete surface is shown on the plans, the existing concrete surface shall be roughened to a full amplitude of approximately 6 mm by abrasive blasting, water blasting, or mechanical equipment.Forms used to support the deck of cast-in-place box girders or to form the voids of precast members for the following structures may remain in place, provided the portions of the forms which obstruct access openings or conflict with utility facilities are removed, the forming system employed leaves no sharp projections into the cells or voids, and forms between hinges and 1.5 m beyond access openings adjacent to hinges are removed:

Alma Overhead (Widen)
Alma Station PUC
Alma Station Separation (Widen)
Willow Street Viaduct (Widen)

Plastic pipe located at vertical drains used behind retaining walls, including horizontal or sloping drains down slopes and across sidewalk areas, shall be polyvinyl chloride (PVC) plastic pipe, Schedule 80, conforming to the provisions for pipe for

edge drains and edge drain outlets in Section 68-3.02, "Materials," of the Standard Specifications. The vertical drain pipe shall be rigidly supported in place during backfilling operations.

Vertical, horizontal, radial, or normal dimensions shown on the Typical Section in the plans are for zero percent cross-slope. At the Contractor's option, the Typical Section of superelevated concrete box girder structures with 1) sloping exterior girders, 2) a straight uninterrupted cross slope between edges of deck, and 3) a single profile grade line, may be rotated around the profile grade line in superelevation areas. The horizontal distances between the profile grade line and the edges of deck shall remain unchanged. The planned girder widths and slab thicknesses shall remain unchanged and the interior girder stems shall remain vertical at the planned locations.

FALSEWORK

Falsework shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Falsework for bent caps at Almaden Road Undercrossing (widen) shall not be released before 7 days after the deck slab concrete has been placed.

Temporary lateral bracing shall be provided for girders located over Almaden Road at the Almaden Road Undercrossing (Widen) bridge. The bracing shall be installed at each end of the girder and shall remain in place until 2 days after the concrete diaphragms and bent caps have been placed. At least 5 days shall elapse after bent cap placing before the top deck slab shall be placed.

Attention is directed to “Relations with Santa Clara Valley Water District” of these special provisions for additional requirements for falsework over Guadalupe River.

In addition to the provisions in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications, the time to be provided for the Engineer's review of the working drawings for specific structures, or portions thereof, shall be as follows:

Structure or Portion of Structure	Total Review Time - Weeks
Almaden Road Undercrossing (Widen)	3
Alma Overhead (Widen)	3
Alma Avenue Undercrossing (Widen)	3
Alma Station Pedestrian Overcrossing (Widen)	3
Alma Station Separation (Widen)	3
Willow Street Viaduct (Widen)	6

Temporary crash cushion modules, as shown on the plans and conforming to the provisions in "Temporary Crash Cushion Module" of these special provisions, shall be installed at the approach end of temporary railings which are located less than 4.6 m from the edge of a traffic lane. For 2-way traffic openings, temporary crash cushion modules shall be installed at the departing end of temporary railings which are located less than 1.8 m from the edge of a traffic lane.

Welding and Nondestructive Testing

Welding of steel members, except for previously welded splices and except for when fillet welds are used where load demands are less than or equal to 175 N/mm for each 3 mm of fillet weld, shall conform to AWS D1.1 or other recognized welding standard. The welding standard to be utilized shall be specified by the Contractor on the working drawings. Previously welded splices for falsework members are defined as splices made prior to the member being shipped to the project site.

Splices made by field welding of steel beams at the project site shall undergo nondestructive testing (NDT). At the option of the Contractor, either ultrasonic testing (UT) or radiographic testing (RT) shall be used as the method of NDT for each field weld and any repair made to a previously welded splice in a steel beam. Testing shall be performed at locations selected by the Contractor. The length of a splice weld where NDT is to be performed, shall be a cumulative weld length equal to 25 percent of the original splice weld length. The cover pass shall be ground smooth at the locations to be tested. The acceptance criteria shall conform to the requirements of AWS D1.1, Section 6, for cyclically loaded nontubular connections subject to tensile stress. If repairs are required in a portion of the weld, additional NDT shall be performed on the repaired sections. The NDT method chosen shall be used for an entire splice evaluation including any required repairs.

For all field welded splices, the Contractor shall furnish to the Engineer a letter of certification which certifies that all welding and NDT, including visual inspection, are in conformance with the specifications and the welding standard shown on the approved working drawings. This letter of certification shall be signed by an engineer who is registered as a Civil Engineer in the State of California and shall be provided prior to placing any concrete for which the falsework is being erected to support.

For previously welded splices, the Contractor shall determine and perform all necessary testing and inspection required to certify the ability of the falsework members to sustain the stresses required by the falsework design. This welding certification shall be in writing, shall be signed by an engineer who is registered as a Civil Engineer in the State of California, and shall be provided prior to placing any concrete for which the falsework is being erected to support.

The Contractor's engineer who signs the falsework drawings shall also certify in writing that the falsework is constructed in conformance with the approved drawings and the contract specifications prior to placing concrete. This certification shall include performing any testing necessary to verify the ability of the falsework members to sustain the stresses required by the falsework design. The engineer who signs the drawings may designate a representative to perform this certification. Where falsework contains openings for railroads, vehicular traffic, or pedestrians, the designated representative shall be qualified to perform this work, shall have at least three years of combined experience in falsework design or supervising falsework construction, and shall be registered as a Civil Engineer in the State of California. For other falsework, the designated representative shall be qualified to perform this work and shall have at least three years of combined experience in falsework design or supervising falsework construction. The Contractor shall certify the experience of the designated representative in writing and provide supporting documentation demonstrating the required experience if requested by the Engineer.

COST REDUCTION INCENTIVE PROPOSALS FOR CAST-IN-PLACE PRESTRESSED BOX GIRDER BRIDGES

Except as provided herein, cast-in-place prestressed box girder bridges shall be constructed in conformance with the details shown on the plans and the provisions in Section 50, "Prestressing Concrete," and Section 51, "Concrete Structures," of the Standard Specifications.

If the Contractor submits cost reduction incentive proposals for cast-in-place prestressed box girder bridges, the proposals shall be in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications and these special provisions.

The Engineer may reject any proposal which, in the Engineer's judgment, may not produce a structure which is at least equivalent to the planned structure.

At the time the cost reduction incentive proposal (CRIP) is submitted to the Engineer, the Contractor shall also submit 4 sets of the proposed revisions to the contract plans, design calculations, and calculations from an independent checker for all changes involved in the proposal, including revisions in camber, predicted deck profile at each construction stage, and falsework requirements to the Office of Structure Design, Documents Unit, P.O. Box 942874, Sacramento, CA 94274-0001 (1801 30th Street, Sacramento, CA 95816), telephone (916) 227-8230. When notified in writing by the Engineer, the Contractor shall submit 12 sets of the CRIP plan revisions and calculations to the Office of Structure Design for final approval and use during construction. The calculations shall verify that all requirements are satisfied. The CRIP plans and calculations shall be signed by an engineer who is registered as a Civil Engineer in the State of California.

The CRIP plans shall be either 279 mm x 432 mm, or 559 mm x 864 mm in size. Each CRIP plan sheet and calculation sheet shall include the State assigned designations for the contract number, bridge number, full name of the structure as shown on the contract plans, and District-County-Route-Kilometer Post. Each CRIP plan sheet shall be numbered in the lower right hand corner and shall contain a blank space in the upper right hand corner for future contract sheet numbers.

Within 3 weeks after final approval of the CRIP plan sheets, one set of the corrected good quality prints on 75-g/m^2 (minimum) bond paper, 559 mm x 864 mm in size, of all CRIP plan sheets prepared by the Contractor for each CRIP shall be furnished to the Office of Structure Design, Documents Unit.

Each CRIP shall be submitted prior to completion of 25 percent of the contract working days and sufficiently in advance of the start of the work that is proposed to be revised by the CRIP to allow time for review by the Engineer and correction by the Contractor of the CRIP plans and calculations without delaying the work. The Contractor shall allow a minimum of 10 weeks for the review of a CRIP. In the event that several CRIPs are submitted simultaneously, or an additional CRIP is submitted for review before the review of a previously submitted CRIP has been completed, the Contractor shall designate the sequence in which the CRIPs are to be reviewed. In this event, the time to be provided for the review of any proposal in the sequence shall be not less than the review time specified herein for that proposal, plus 2 weeks for each CRIP of higher priority which is still under review.

Should the review not be complete by the date specified in the Contractor's CRIP, or such other date as the Engineer and Contractor may subsequently have agreed to in writing and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review of CRIP plans and calculations, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications except that the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications shall not apply.

Permits and approvals required of the State have been obtained for the structures shown on the plans. Proposals which result in a deviation in configuration may require new permits or approvals. The Contractor shall be responsible for obtaining the new permits and approvals before the Engineer will reach a decision on the proposal. Delays in obtaining permits and approvals will not be reason for granting an extension of contract time.

All proposed modifications shall be designed in conformance with the bridge design specifications and procedures currently employed by the Department. The proposal shall include all related, dependent or incidental changes to the structure and other work affected by the proposal. The proposal will be considered only when all aspects of the design changes are included for the entire structure. Changes, such as but not limited to, additional reinforcement and changes in location of reinforcement, necessary to implement the CRIP after approval by the Engineer, shall be made at the Contractor's expense.

Modifications may be proposed in (1) the thickness of girder stems and deck slabs, (2) the number of girders, (3) the deck overhang dimensions as specified herein, (4) the amount and location of reinforcing steel, (5) the amount and location of prestressing force in the superstructure, and (6) the number of hinges, except that the number of hinges shall not be increased. The strength of the concrete used may be increased but the strength employed for design or analysis shall not exceed 42 MPa.

Modifications proposed to the minimum amount of prestressing force which must be provided by full length draped tendons are subject to the provisions in "Prestressing Concrete" of these special provisions.

No modifications will be permitted in (1) the foundation type, (2) the span lengths or (3) the exterior dimensions of columns or bridge superstructure, except that the overhang dimension from face of exterior girder to the outside edge of roadway deck may be uniformly increased or decreased by 25 percent on each side of the box girder section. Fixed connections at the tops and bottoms of columns shown on the plans shall not be eliminated.

The Contractor shall be responsible for determining construction camber and obtaining the final profile grade as shown on the plans.

The Contractor shall reimburse the State for the actual cost of investigating CRIPs for cast-in-place prestressed box girder bridges submitted by the Contractor. The Department will deduct this cost from any moneys due, or that may become due the Contractor under the contract, regardless of whether or not the proposal is approved or rejected.

DECK CLOSURE POURS

Where a deck closure pour is shown on the plans, reinforcement protruding into the closure space and forms for the closure pour shall conform to the following:

A. During the time of placement of concrete in the deck, other than for the closure pour itself, reinforcing steel which protrudes into the closure space shall be completely free from any connection to the reinforcing steel, concrete, or other attachments of the adjacent structure, including forms. The reinforcing steel shall remain free of any connection for a period of not less than 24 hours following completion of the pour.
B. Forms for the closure pour shall be supported from the superstructure on both sides of the closure space.

SLIDING JOINTS

Sliding joints consisting of a neoprene strip lubricated with grease and covered with sheet metal shall conform to the following requirements:

A. Neoprene strip shall conform to the requirements for neoprene in Section 51-1.14, "Waterstops," of the Standard Specifications.
B. Grease shall conform to the requirements of Military Specification: MIL-S-8660. A uniform film of grease shall be applied to the upper surface of the neoprene strip prior to placing the sheet metal.
C. Sheet metal shall be commercial quality galvanized sheet steel. The sheet metal shall be smooth and free of kinks, bends, or burrs. Joints in the sheet metal shall be butt joints sealed with plastic duct sealing tape.
D. Construction methods and procedures shall prevent grout or concrete seepage into the sliding joint assembly.
E. The concrete surfaces on which the neoprene strips will be placed shall be floated to a level plane and finished with a steel trowel.

SLIDING BEARINGS

Sliding bearings consisting of elastomeric bearing pads lubricated with grease and covered with sheet metal shall conform to the following requirements:

A. Grease shall conform to the requirements of Military Specification: MIL-S-8660. A uniform film of grease shall be applied to the upper surface of the pads prior to placing the sheet metal.
B. Sheet metal shall be commercial quality galvanized sheet steel. The sheet metal shall be smooth and free of kinks, bends, or burrs.
C. Construction methods and procedures shall prevent grout or concrete seepage into the sliding bearing assembly.

ELASTOMERIC BEARING PADS

Elastomeric bearing pads shall conform to the provisions in Section 51-1.12H, "Elastomeric Bearing Pads," of the Standard Specifications and these special provisions.

DECK CRACK TREATMENT

The Contractor shall use all means necessary to minimize the development of shrinkage cracks.

The Contractor shall remove all equipment and materials from the deck and clean the surface as necessary for the Engineer to measure the surface crack intensity. Surface crack intensity will be determined by the Engineer after completion of concrete cure, before prestressing, and before the release of falsework. In any 50-m^2 portion of deck within the limits of the new concrete deck, should the intensity of cracking be such that there are more than 5 m of cracks whose width at any location exceeds 0.5-mm, the deck shall be treated with methacrylate resin. The area of deck to be treated shall have a width that extends for the entire width of new deck inside the concrete barriers and a length that extends at least 1.5 m beyond the furthest single continuous crack outside the 50-m^2 portion, measured from where that crack exceeds 0.5-mm in width, as determined by the Engineer.

The above work shall be performed at the widen portions only.

Deck crack treatment shall consist of test sealing, and furnishing and applying methacrylate resin in conformance with the requirements of these special provisions. If grinding operation is required, deck treatment shall take place before grinding.

Before the start of deck treatment work, the Contractor shall submit for approval by the Engineer, a program for public safety associated with the use of methacrylate resin. The program shall identify materials, equipment, and methods to be used. The Contractor shall not perform deck treatment work, other than that specifically authorized in writing by the Engineer, until the program has been approved.

If the measures being taken by the Contractor are inadequate to provide for public safety associated with use of methacrylate resin, the Engineer will direct the Contractor to revise the operations and the public safety program. Directions for revisions will be in writing and will specify the items in which the Contractor's program is inadequate. No further deck treatment shall be performed until public safety measures are adequate, and a revised program for public safety has been approved.

The Engineer will notify the Contractor of the approval or rejection of any submitted or revised program for public safety associated with the use of methacrylate resin within 10 working days of receipt of the final submitted program.

The State will not be liable to the Contractor for failure to approve all or any portion of an originally submitted or revised program for public safety associated with the use of methacrylate resin, nor for any delays to the work due to the Contractor's failure to submit an acceptable program for public safety associated with the use of methacrylate resin. If the Engineer does not review or approve the program submitted by the Contractor within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the program for public safety, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Materials

The material used for treating the deck shall be a low odor, high molecular weight methacrylate resin. Before adding initiator, the resin shall have a maximum volatile content of 30 percent when tested in conformance with the requirements in ASTM Designation: D 2369, and shall conform to the following:

PROPERTY	TEST METHOD	REQUIREMENT
Viscosity Pa·s, maximum, (Brookfield RVT with UL adaptor, 50 RPM at 25°C)	ASTM D 2196	0.025
Specific Gravity minimum, at 25°C	ASTM D 1475	0.90
Flash Point °C, minimum	ASTM D 3278	82
Vapor Pressure mm Hg, maximum, at 25°C	ASTM D 323	1.0
Tack-free time minutes, maximum at 25°C	California Test 551	400
PCC Saturated Surface-Dry Bond Strength MPa, minimum at 24 hours and 21±1°C	California Test 551	3.5
* Test shall be performed before adding initiator.		

A Material Safety Data Sheet shall be furnished before use for each shipment of high molecular weight methacrylate resin.

The promoter and initiator, if supplied separately from the resin, shall not be mixed directly with each other. Containers of promoters and initiators shall not be stored together in a manner that will allow leakage or spillage from one to contact the containers or material of the other.

Testing

The Contractor shall allow 14 days for sampling and testing by the Engineer of the high molecular weight methacrylate resin before proposed use.

The Contractor shall treat a test area within the project limits of approximately 50 m^2 at a location approved by the Engineer. Conditions during the test treatment shall be similar to those expected on the deck. Equipment used in the test shall be similar to those used for the deck treating operations. If the test area is on the traveled way, traffic shall not be allowed on the treated test area until (1) the treated surface is tack free (non-oily), (2) the sand cover adheres sufficiently to resist brushing by hand, and (3) the coefficient of friction of the deck is at least 0.35 when tested in conformance with the requirements in California Test 342.

Should the above requirements for traffic use not be met, the Contractor shall suspend treating of bridge decks until another test area is treated and complies with the requirements.

Construction

Before deck treatment with methacrylate resin, the bridge deck surface shall be cleaned by abrasive blasting and all loose material shall be blown from visible cracks using high-pressure air. Concrete curing seals shall be cleaned from the deck surface to be treated, and the deck shall be dry when blast cleaning is performed. If the deck surface becomes contaminated at any time before placing the penetrating sealer, the deck surface shall be cleaned by abrasive blasting.

Equipment shall be fitted with suitable traps, filters, drip pans, or other devices as necessary to prevent oil or other deleterious material from being deposited on the deck.

Where abrasive blasting is being performed within 3 m of a lane occupied by public traffic, the residue including dust shall be removed immediately after contact between the abrasive and the surface being treated. The removal shall be by a vacuum attachment operating concurrently with the abrasive blasting operation.

The relative humidity shall be less than 90 percent at time of treatment.

A compatible promoter/initiator system shall be capable of providing a resin gel time of not less than 40 minutes nor more than 1.5 hours at the temperature of application. Gel time shall be adjusted to compensate for the changes in temperature throughout treatment application.

The quantity of resin mixed with promoter and initiator shall be limited to 20 L at a time for manual application.

Machine application of the resin shall be performed by using a two-part resin system using a promoted resin for one part and an initiated resin for the other part. This two-part resin system shall be combined at equal volumes to the spray bars through separate positive displacement pumps. Combining of the 2 components shall be by either static in-line mixers or by external intersecting spray fans. The pump pressure at the spray bars shall not be great enough to cause appreciable atomization of the resin. Compressed air shall not be used to produce the spray. A shroud shall be used to enclose the spray bar apparatus. Hand held spray apparatus shall not be used.

The Contractor shall allow methacrylate resin to be applied only to the specified area. Barrier rails, joints, and drainage facilities shall be adequately protected to prevent contamination by the treatment material. Contaminated items shall be repaired at the Contractor's expense.

The prepared area shall be dry and the surface temperature shall be less than or equal to 38°C when the resin is applied. The rate of application of promoted/initiated resin shall be approximately 2.5 square meters per liter, ± 0.1 square meter per liter.

The deck surfaces to be treated shall be flooded with resin, allowing penetration into the concrete and filling of all cracks. The treatment shall be applied within 5 minutes after complete mixing. A significant increase in viscosity shall be cause for rejection. Excess material shall be redistributed by squeegees or brooms within 10 minutes after application.

After the resin has been applied, at least 20 minutes shall elapse before applying sand. The sand shall be commercial quality dry blast sand. Ninety-five percent of the sand shall pass the 2.36-mm sieve, and 95 percent shall be retained on the 850-µm sieve. The sand shall be applied at a rate of one kilogram per square meter, ± 0.1 kilogram per square meter.

Excess sand shall be removed from the deck surface by vacuuming or sweeping before opening to traffic.

Traffic shall not be allowed on the treated area until (1) the treated surface is tack free (non-oily), (2) the sand cover adheres sufficiently to resist brushing by hand, and (3) the coefficient of friction of the deck is at least 0.35 when tested in conformance with the requirements in California Test 342.

PRECAST PRESTRESSED CONCRETE BRIDGE MEMBERS

The top surface of the member shall be given a coarse texture by brooming with a stiff bristled broom or by other suitable devices that will result in uniform transverse scoring, in advance of curing operations.

The requirements of the seventh paragraph of Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications shall not apply.

The anticipated deflection and method of accommodation of deflection of precast prestressed concrete girders, prior to the time the deck concrete is placed, shall be shown on the working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The deflection shall include the following:

A. Anticipated upward deflection caused by the prestressing forces.
B. Downward deflection caused by the dead load of the girder.
C. Deflection caused by the creep and shrinkage of the concrete for the time interval between the stressing of the girders and the planned placement of the deck.

Such deflection shall be substantiated by calculations that consider the ages of the girder concrete at the time of stressing and the Contractor's planned placement of the deck. All deflection calculations shall be based on the concrete producer's estimate of the modulus of elasticity at the applicable concrete age.

Adjustments to accommodate girder deflections, which occur prior to the time the deck concrete is placed, may include revisions in bearing seat elevations, but any such adjustments shall be limited by the following conditions:

A. The minimum permanent vertical clearance under the structure as shown on the plans shall not be reduced.
B. The profile grade and cross slope of the deck shall not be changed.
C. A minimum of 25 mm of deck slab concrete between the top of the precast girders and the deck slab reinforcement shall be maintained.

Girders with unanticipated girder deflection and which cannot comply with conditions A, B, and C will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials," of the Standard Specifications.

Adjustments to accommodate girder deflections will not be considered a change in dimensions. Full compensation for increases in the cost of construction, including increases in the quantity of deck or bearing seat concrete, resulting from adjustments to accommodate girder deflections shall be considered as included in the contract price paid for the various items of work involved and no additional compensation will be allowed therefor.

Temporary lateral bracing shall be provided for girders located over Almaden Road at the Almaden Road Undercrossing (Widen) bridge. The bracing shall be installed at each end of each girder, except notched ends, prior to the release of the erection equipment from the girder and shall remain in place until 2 days after the concrete diaphragms and bent caps have been placed. At least 5 days shall elapse after the bent cap placing before the top deck slab shall be placed. The bracing shall

be adequate to prevent overturning of the girders prior to completion of the work and as a minimum shall be capable of resisting a lateral force of 720 Pa of girder side area applied laterally in either direction to the top of the girder. Girder erection shall not be started until the temporary lateral bracing proposed for use by the Contractor has been approved by the Engineer.

MEASUREMENT AND PAYMENT

Measurement and payment for concrete in structures shall conform to the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for roughening existing concrete surfaces to a full amplitude of approximately 6 mm, where shown on the plans, shall be considered as included in the contract price paid per cubic meter for structural concrete, bridge and no separate payment will be made therefor.

Full compensation for furnishing and installing access opening covers in soffits of new cast-in-place box girder bridges shall be considered as included in the contract price paid per cubic meter for structural concrete, bridge and no separate payment will be made therefor.

Full compensation for furnishing and installing plastic pipe located at vertical drains used behind retaining walls and bridge abutments, including horizontal or sloping drains down slopes and across sidewalk areas, including excavation and backfill involved in placing the plastic pipe, shall be considered as included in the contract price paid per cubic meter for the various items of concrete work involved and no separate payment will be made therefor.

Full compensation for deck crack treatment, including a program for public safety and airborne monitoring, shall be considered as included in the contract price paid per cubic meter for structural concrete, bridge and no additional compensation will be allowed therefor.

10-1.55 STRUCTURE APPROACH SLABS (Type N)

This work shall consist of constructing reinforced concrete approach slabs, sleeper slabs, structure approach drainage system, and treated permeable base at structure approaches in conformance with the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

GENERAL

Attention is directed to "Engineering Fabrics" of these special provisions.

STRUCTURE APPROACH DRAINAGE SYSTEM

Geocomposite Drain

Geocomposite drain shall consist of a manufactured core not less than 6.35 mm thick nor more than 50 mm thick with one or both sides covered with a layer of filter fabric that will provide a drainage void. The drain shall produce a flow rate, through the drainage void, of at least 25 liters per minute per meter of width at a hydraulic gradient of 1.0 and a minimum externally applied pressure of 168 kPa.A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for the geocomposite drain certifying that the drain produces the required flow rate and complies with these special provisions. The Certificate of Compliance shall be accompanied by a flow capability graph for the geocomposite drain showing flow rates and the externally applied pressures and hydraulic gradients. The flow capability graph shall be stamped with the verification of an independent testing laboratory.

Filter fabric for the geocomposite drain shall conform to the provisions for fabric for underdrains in Section 88, "Engineering Fabrics," of the Standard Specifications.

The manufactured core shall be either a preformed grid of embossed plastic, a mat of random shapes of plastic fibers, a drainage net consisting of a uniform pattern of polymeric strands forming 2 sets of continuous flow channels, or a system of plastic pillars and interconnections forming a semirigid mat.

The core material and filter fabric shall be capable of maintaining the drainage void for the entire height of geocomposite drain. Filter fabric shall be integrally bonded to the side of the core material with the drainage void. Core material manufactured from impermeable plastic sheeting having nonconnecting corrugations shall be placed with the corrugations approximately perpendicular to the drainage collection system.

The geocomposite drain shall be installed with the drainage void and the filter fabric facing the embankment. The fabric facing the embankment side shall overlap a minimum of 75 mm at all joints and wrap around the exterior edges a minimum of 75 mm beyond the exterior edge. If additional fabric is needed to provide overlap at joints and wrap-around at edges, the added fabric shall overlap the fabric on the geocomposite drain at least 150 mm and be attached thereto.

Should the fabric on the geocomposite drain be torn or punctured, the damaged section shall be replaced completely or repaired by placing a piece of fabric that is large enough to cover the damaged area and provide a 150-mm overlap.

Plastic Pipe

Plastic pipe shall conform to the provisions for pipe for edge drains and edge drain outlets in Section 68-3, "Edge Drains," of the Standard Specifications.

Drainage Pads

Concrete for use in drainage pads shall be minor concrete, except the concrete shall contain not less than 300 kilograms of cement per cubic meter.

Treated Permeable Base At Bottom Of Geocomposite Drains

Treated permeable base to be placed around the slotted plastic pipe at the bottom of geocomposite drains shall conform to the provisions in "Treated Permeable Base Under Approach Slabs." If asphalt treated permeable base is used, it shall be placed at a temperature of not less than 82°C nor more than 110°C.

The filter fabric to be placed over the treated permeable base at the bottom of geocomposite drains shall conform to the provisions for filter fabric for edge drains in Section 88, "Engineering Fabrics," of the Standard Specifications.

ENGINEERING FABRICS

Filter fabric to be placed between the structure approach embankment material and the treated permeable base shall conform to the provisions for filter fabric for edge drains in Section 88, "Engineering Fabrics," of the Standard Specifications and these special provisions.

The subgrade to receive the filter fabric, immediately prior to placing, shall conform to the compaction and elevation tolerance specified for the material involved.

Filter fabric shall be aligned, handled, and placed in a wrinkle-free manner in conformance with the manufacturer's recommendations.

Adjacent borders of the filter fabric shall be overlapped from 300 to 450 mm or stitched. The preceding roll shall overlap the following roll in the direction the material is being spread or shall be stitched. When the fabric is joined by stitching, it shall be stitched with yarn of a contrasting color. The size and composition of the yarn shall be as recommended by the fabric manufacturer. The number of stitches per 25 mm of seam shall be 5 to 7.

Equipment or vehicles shall not be operated or driven directly on the filter fabric.

Woven tape fabric to be placed between the treated permeable base and the approach slab shall be a fabric made of woven strips or tapes and shall conform to the following:

Specification	ASTM Designation	Requirement
Weight, grams per square meter, min.	D 3776	100
Grab Tensile Strength, kilonewtons, min.	D 4632	0.22
Elongation, percent, max.	D 4632	35
Toughness, kilonewtons, min. (Percent elongation times grab tensile strength)	----	5

Woven tape fabric shall be treated to provide a minimum of 70 percent breaking strength retention after 500 hours exposure when tested in conformance with the requirements in ASTM Designation: D 4355. The Contractor shall notify the Engineer, in writing, of the source of woven tape fabric at least 45 days prior to use.

TREATED PERMEABLE BASE UNDER APPROACH SLAB

Treated permeable base under structure approach slabs shall consist of constructing either an asphalt treated permeable base or a cement treated permeable base in accordance with Section 29, "Treated Permeable Bases," of the Standard Specifications and these special provisions.

The type of treatment, asphalt or cement, to be used shall be at the option of the Contractor.

The Contractor shall notify the Engineer in writing, not less than 30 days prior to the start of placing the treated permeable base, which type of treated permeable base will be furnished. Once the Contractor has notified the Engineer of the selection, the type to be furnished shall not be changed without a prior written request to do so and approval thereof in writing by the Engineer.

Asphalt treated permeable base shall be placed at a temperature of not less than 93°C nor more than 121°C. Material stored in excess of 2 hours shall not be used in the work.

Asphalt treated permeable base material may be spread in one layer. The base material shall be compacted with a vibrating shoe type compactor or rolled with a roller weighing at least 1.3 tonnes but no more than 4.5 tonnes. Rolling shall begin as soon as the mixture has cooled sufficiently to support the weight of the rolling equipment without undue displacement.

Cement treated permeable base material may be spread in one layer. The base material shall be compacted with either a vibrating shoe type compactor or with a steel-drum roller weighing at least 1.3 tonnes but no more than 4.5 tonnes. Compaction shall follow within one-half hour after the spreading operation and shall consist of 2 complete coverages of the treated material.

APPROACH SLABS

Concrete for use in approach slabs and sleeper slabs shall contain not less than 400 kilograms of cementitious material per cubic meter.

Steel components of abutment ties including plates, nuts, washers, and rods shall conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

Bar reinforcement that has an unbonded portion shall be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing," of the Standard Specifications.

The steel angle at the concrete barrier joint shall conform to the provision in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

Structure approach slabs and sleeper slabs shall be cured for not less than 5 days prior to opening to public traffic, unless, at the option of the Contractor, the structure approach slabs and sleeper slabs are constructed using concrete with a non-chloride Type C chemical admixture conforming to these special provisions.

Portland cement for use in concrete using a non-chloride Type C chemical admixture shall be Type II Modified, Type II Prestress, or Type III. Type II Modified and Type III cement shall conform to the provisions in Section 90-2.01, "Cement," of the Standard Specifications. Type II Prestress cement shall conform to the requirements of Type II Modified cement, except the mortar containing the portland cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not contract in air more than 0.053-percent.

The non-chloride Type C chemical admixture, approved by the Engineer, shall conform to the requirements in ASTM Designation: C 494 and Section 90-4, "Admixtures," of the Standard Specifications.

The concrete with non-chloride Type C chemical admixture shall be prequalified prior to placement in conformance with the provisions for prequalification of concrete specified by compressive strength in Section 90-9.01, "General," of the Standard Specifications and the following:

A. Immediately after fabrication of the 5 test cylinders, the cylinders shall be stored in a temperature medium of 21 ± 1.5°C until the cylinders are tested.
B. The 6-hour average strength of the 5 test cylinders shall not be less than 5.85 MPa. No more than 2 test cylinders shall have a strength of less than 5.5 MPa.

Building paper shall be commercial quality No. 30 asphalt felt.

Polyvinyl chloride (PVC) conduit used to encase the abutment tie rod shall be of commercial quality.

The top surface of approach slabs and sleeper slabs shall be finished in conformance with the provisions in Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications. Edges of slabs shall be edger finished.

Approach slabs and sleeper slabs shall be cured with pigmented curing compound (1) in conformance with the provisions for curing structures in Section 90-7.01B, "Curing Compound Method," of the Standard Specifications.

Structure approach slabs and sleeper slabs constructed using concrete with a non-chloride Type C chemical admixture shall be cured for not less than 6 hours prior to opening to public traffic. The curing period shall be considered to begin at the start of discharge of the last truck load of concrete to be used in the slab.

If the ambient temperature is below 18°C during the curing period for approach slabs and sleeper slabs using concrete with a non-chloride Type C chemical admixture, an insulating layer or blanket shall be used to cover the surface. The insulating layer or blanket shall have an R-value rating given in the table below. At the Contractor's option, a heating tent may be used in lieu of or in combination with the insulating layer or blanket.

Temperature range during curing period	R-value, minimum
13°C to 18°C	1
7°C to 13°C	2
4°C to 7°C	3

JOINTS

Hardboard and expanded polystyrene shall conform to the provisions in Section 51-1.12D, "Sheet Packing, Preformed Pads and Board Fillers," of the Standard Specifications.

Type AL joint seals shall conform to the provisions in Section 51-1.12F, "Sealed Joints" of the Standard Specifications. The sealant may be mixed by hand-held power-driven agitators and placed by hand methods.

The pourable seal between the steel angle and concrete barrier shall conform to the requirements for Type A and AL seals in Section 51-1.12F(3), "Materials and Installation," of the Standard Specifications. The sealant may be mixed by hand-held power-driven agitators and placed by hand methods. Immediately prior to placing the seal, the joint shall be thoroughly cleaned, including abrasive blast cleaning of the concrete surfaces, so that all foreign material and concrete spillage are removed from all joint surfaces. Joint surfaces shall be dry at the time the seal is placed.

Sliding joint for the sleeper slab shall conform to the provisions for sliding joints in "Concrete Structures" of these special provisions.

MEASUREMENT AND PAYMENT

Structural concrete, approach slab (Type N) will be measured and paid for in conformance with the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for the structure approach drainage system including geocomposite drain, plastic pipe, and drainage pads, treated permeable base, filter fabric, woven tape fabric, miscellaneous metal, pourable seals, drill and bond dowel transverse joint seals at sleeper slabs, waterstops, and sliding joints shall be considered as included in the contract price paid per cubic meter for structural concrete, approach slab of the type shown in the Engineer's Estimate, and no additional compensation will be allowed therefor.

10-1.56 STRUCTURE APPROACH SLABS (TYPE R)

Structure approach slabs (Type R) shall consist of removing portions of existing structures, existing pavement and base including reinforced concrete approach slabs, asphalt concrete surfacing, portland cement concrete pavement, subsealing material, and cement treated base and constructing new reinforced concrete approach slabs at structure approaches as shown on the plans and in conformance with these special provisions.

GENERAL

The thickness shown on the plans for structure approach slabs is the minimum thickness. The thickness will vary depending on the thickness of the pavement and base materials removed.

Where pavement subsealing has been performed under existing approach slabs, the subsealing material shall be removed for its full depth. Where removal of cement treated base is required to construct the approach slab, the entire thickness of the cement treated base shall be removed.

Voids between the new reinforced structure approach slab and the base material remaining in place that are caused by removal of subsealing material or cement treated base shall be filled, at the option of the Contractor, with aggregate base (approach slab) or structure approach slab concrete.

The Contractor shall establish a grade line for new approach slabs which shall provide a smooth profile grade. The profile grade will be subject to the approval of the Engineer.

The Contractor shall schedule his operations so that the pavement and base materials removed during a work period shall be replaced, in that same work period, with approach slab concrete that shall be cured for at least 6 hours prior to the time the lane is to be opened to public traffic as designated in "Maintaining Traffic" of these special provisions. In the event the existing pavement and base materials are removed and the Contractor is unable to construct, finish, and cure the new approach slab by the time the lane is to be opened to public traffic, the excavation shall be filled with a temporary roadway structural section as specified in this section, "Structure Approach Slabs (Type R)."

At locations where the removal of existing materials and approach slab construction is not required to be completed within the same work period, the requirements for "Temporary Roadway Structural Section" shall not apply. The Contractor shall have the option of:

A. Curing the approach slab concrete for not less than 5 days prior to opening to public traffic, or
B. Constructing the approach slab using concrete with a non-chloride Type C chemical admixture and curing the approach slab concrete at least 6 hours prior to opening to public traffic.

TEMPORARY ROADWAY STRUCTURAL SECTION

A standby quantity of asphalt concrete and aggregate base, equal to the quantity of pavement removed during the work shift, shall be provided at the project site for construction of a temporary roadway structural section where existing approaches to structures are being replaced. The temporary structural section shall be maintained and later removed as a first order of work when the Contractor is able to construct and cure the approach slab within the prescribed time limit. The temporary structural section shall consist of 90-mm thick layer of asphalt concrete over aggregate base.

The aggregate base for the temporary structural section shall conform to the requirements specified under "Aggregate Base (Approach Slab)" of these special provisions.

The asphalt concrete for the temporary structural section shall be produced from commercial quality aggregates and asphalt binder. The grading of the aggregate shall conform to the 19-mm maximum medium grading in Section 39-2.02, "Aggregate," of the Standard Specifications and the asphalt binder shall conform to the requirements of liquid asphalt SC-800 in Section 93, "Liquid Asphalts," of the Standard Specifications. The amount of asphalt binder to be mixed with the aggregate shall be approximately 0.3-percent less than the optimum bitumen content as determined by California Test 367.

Aggregate base and asphalt concrete for the temporary structural section shall be spread and compacted by methods that will produce a well-compacted, uniform base, free from pockets of coarse or fine material and a surfacing of uniform smoothness, texture, and density. The aggregate base and the asphalt concrete may each be spread and compacted in one layer. The finished surface of the asphalt concrete shall not vary more than 15 mm from the lower edge of a 3.6-m straightedge placed parallel with the centerline and shall match the elevation of the existing concrete pavement and structure along the joints between the existing pavement and structure and the temporary surfacing.

The material from the removed temporary structural section shall be disposed of in conformance with Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications except that removed aggregate base may be stockpiled at the project site and reused for construction of another temporary structural section. When no longer required, standby material or stockpiled material for construction of temporary structural sections shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

REMOVING PORTIONS OF EXISTING STRUCTURES

Attention is directed to "Existing Highway Facilities" of these special provisions.

REMOVING EXISTING PAVEMENT AND BASE MATERIALS

The outline of portland cement concrete to be removed shall be sawed full depth with a power-driven concrete saw.

The outlines of excavations in asphalt concrete shall be cut on a neat line to a minimum depth of 75 mm with a power-driven concrete saw or wheel-type rock cutting excavator before any asphalt concrete material is removed. These excavations shall be permanently or temporarily backfilled to conform to the grade of the adjacent pavement prior to opening the lane to public traffic. Surplus excavated material may be used as temporary backfill material.

Regardless of the type of equipment used to remove concrete within the sawed outline, the surface of the concrete to be removed shall not be impacted within 0.5-m of the pavement to remain in place. Removing existing pavement and base materials shall be performed without damage to the adjacent structure or pavement that is to remain in place. Damage to the structure or to the pavement that is to remain in place shall be repaired in conformance with the provisions in Section 7-1.11, "Preservation of Property," of the Standard Specifications.

Materials removed shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The base material remaining in-place, after removing the existing pavement and base materials to the required depth, shall be graded uniformly, watered, and compacted. The finished surface of the base material at any point shall not extend above the grade approved by the Engineer.

Areas of the base material that are low as a result of over excavation shall be filled, at the Contractor's expense, with structure approach slab concrete at the time and in the same operation that the new concrete is placed.

AGGREGATE BASE (APPROACH SLAB)

The aggregate base (approach slab) for filling voids below the reinforced structure approach slab concrete shall be produced from commercial quality aggregates consisting of broken stone, crushed gravel or natural rough-surfaced gravel, and sand, or any combination thereof. The grading of the aggregate base shall conform to the 19-mm maximum grading specified in Section 26-1.02A, "Class 2 Aggregate Base," of the Standard Specifications.

Aggregate base (approach slab) for filling voids below the reinforced structure approach slab concrete shall be spread and compacted by methods that will produce a well-compacted, uniform base, free from pockets of coarse or fine material. The aggregate base shall be watered and compacted to the grade approved by the Engineer. Where the required thickness of aggregate base is 200 mm or less, the base may be spread and compacted in one layer. Where the required thickness of aggregate base is more than 200 mm, the base shall be spread and compacted in 2 or more layers of approximately equal thickness. The maximum compacted thickness of any one layer shall not exceed 200 mm. The finished surface of the base material at any point shall not extend above the grade approved by the Engineer. Areas of the base material that are lower than the grade approved by the Engineer, shall be filled with structure approach slab concrete at the time and in the same operation that the new concrete is placed.

STRUCTURE APPROACH SLAB

Reinforced concrete approach slabs shall conform to the provisions for approach slabs in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Concrete for use in approach slabs shall contain not less than 400 kg of cementitious material per cubic meter.

Steel components of abutment ties including plates, nuts, washers, and rods shall conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

The steel angles at the concrete barrier joint shall conform to the provision in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

Approach slab concrete that requires a minimum curing period of 6 hours shall be constructed using a non-chloride Type C chemical admixture. Mineral admixture will not be required in this concrete.

Portland cement for use in concrete using a non-chloride Type C chemical admixture shall be Type II Modified, Type II Prestress, or Type III. Type II Modified and Type III cement shall conform to the provisions in Section 90-2.01, "Cement," of the Standard Specifications. Type II Prestress cement shall conform to the requirements of Type II Modified cement, except the mortar containing the portland cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not contract in air more than 0.053-percent.

The non-chloride Type C chemical admixture shall be approved by the Engineer and shall conform to the requirements in ASTM Designation: C 494 and Section 90-4, "Admixtures," of the Standard Specifications.

The concrete with non-chloride Type C chemical admixture shall be prequalified prior to placement in conformance with the provisions for prequalification of concrete specified by compressive strength in Section 90-9.01, "General," of the Standard Specifications and the following:

A. Immediately after fabrication of the 5 test cylinders, the cylinders shall be stored in a temperature medium of 21 ± 1.5°C until the cylinders are tested.
B. The 6-hour average strength of the 5 test cylinders shall not be less than 5.85 MPa. No more than 2 test cylinders shall have a strength of less than 5.5 MPa.

Building paper shall be commercial quality No. 30 asphalt felt.

Polyvinyl chloride (PVC) conduit used to encase the abutment tie rod shall be commercial quality.

Bar reinforcement or abutment tie rods in drilled holes shall be bonded in conformance with the provisions for drilling and bonding dowels in Section 83-2.02D(1), "General," of the Standard Specifications.

If reinforcement is encountered during drilling before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole to the depth shown on the plans.

The top surface of approach slabs shall be finished in conformance with the provisions in Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications. The finished top surface shall not vary more than 6 mm from the lower edge of a 3.6-m straightedge placed parallel with the centerline. Edges of slabs shall be edger finished.

The surface of the approach slab will not be profiled and the Profile Index requirements shall not apply.

Approach slabs shall be cured with pigmented curing compound (1) in conformance with the provisions for curing structures in Section 90-7.01B, "Curing Compound Method," of the Standard Specifications. The minimum curing period as specified herein shall be considered to begin at the start of discharge of the last truck load of concrete to be used in the slab. Fogging of the surface with water after the curing compound has been applied will not be required. Should the film of curing compound be damaged from any cause before the approach slab is opened to public traffic, the damaged portion shall be repaired immediately with additional compound, at the Contractor's expense. Damage to the curing compound after the approach slab is opened to public traffic shall not be repaired.

If the ambient temperature is below 18°C during the curing period, an insulating layer or blanket shall cover the surface. The insulation layer or blanket shall have an R-value rating given in the table below. At the Contractor's option, a heating tent may be used in lieu of or in combination with the insulating layer or blanket:

Temperature range during curing period	R-value, minimum
13°C to 18°C	1
7°C to 13°C	2
4°C to 7°C	3

Tests to determine the coefficient of friction of the final textured surface will be made only if the Engineer determines by visual inspection that the final texturing may not have produced a surface having the specified coefficient of friction. Tests to determine the coefficient of friction will be made after the approach slab is opened to public traffic, but not later than 5 days after concrete placement. The coefficient of friction will be measured by California Test 342. Portions of completed concrete surfaces that are found to have a coefficient of friction less than 0.35 shall be ground or grooved parallel to the center line in conformance with the provisions for bridge decks in Section 42, "Groove and Grind Pavement," of the Standard Specifications.

JOINTS

Hardboard and expanded polystyrene shall conform to the provisions in Section 51-1.12D, "Sheet Packing, Preformed Pads and Board Fillers," of the Standard Specifications.

Type AL joint seals shall conform to the provisions in Section 51-1.12F, "Sealed Joints," of the Standard Specifications. The sealant may be mixed by hand-held power-driven agitators and placed by hand methods.

The pourable seal between the steel angle and concrete barrier shall conform to the requirements for Type A and AL seals in Section 51-1.12F(3), "Materials and Installation," of the Standard Specifications. The sealant may be mixed by hand-held power-driven agitators and placed by hand methods. Immediately prior to placing the seal, the joint shall be thoroughly cleaned, including abrasive blast cleaning of the concrete surfaces, so that all foreign material and concrete spillage are removed from all joint surfaces. Joint surfaces shall be dry at the time the seal is placed.

MEASUREMENT AND PAYMENT

Structural concrete, approach slab (Type R) will be measured and paid for in conformance with the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for removing and disposing of portions of existing structures and pavement materials, and for furnishing and placing miscellaneous metal, Type AL joint seals, and pourable seals shall be considered as included in the contract price paid per cubic meter for structural concrete, approach slab (Type R) and no separate payment will be made therefor.

The quantity of aggregate base (approach slab) to be paid for shall include the actual volume of aggregate base (approach slab) used to fill voids below the reinforced structure approach slab concrete, except for the volume of areas low as a result of over excavation. The volume to be paid for will be calculated on the basis of the constructed length, width, and thickness of the filled voids. Structure approach slab concrete used to fill voids lower than the approved grade of the base, except for the areas low as a result of over excavation by the Contractor, will be measured and paid for by the cubic meter as aggregate base (approach slab).

The contract price paid per cubic meter for aggregate base (approach slab) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing aggregate base (approach slab), complete in place, including excavation and removing and disposing of base and subsealing materials, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for furnishing, stockpiling, and disposing of standby material for construction of temporary structural sections; and for constructing, maintaining, removing, and disposing of temporary structural sections shall be considered as included in the contract price paid per cubic meter for structural concrete, approach slab (Type R) and no separate payment will be made therefor.

Full compensation for drilling and bonding of bar reinforcement or abutment tie rods shall be considered as included in the contract price paid per cubic meter for structural concrete, approach slab (Type R) and no separate payment will be made therefor.

10-1.57 PAVING NOTCH EXTENSION

This work shall consist of extending existing paving notches in conformance with the details shown on the plans and these special provisions.

Concrete for the paving notch extensions shall conform to the provisions for structure approach slab concrete of these special provisions.

At least 12 hours shall elapse between the time of placing concrete for the paving notch extension and placing concrete for the structure approach slab.

The construction joint between the paving notch extension and the existing abutment shall conform to the provisions for horizontal construction joints in Section 51-1.13, "Bonding," of the Standard Specifications. Concrete shall be placed in the spalled portions of the existing paving notch concurrently with the concrete for the paving notch extension.

Attention is directed to "Reinforcement" of these special provisions.

Structure excavation and backfill shall conform to the provisions in Section 19-3, "Structure Excavation and Backfill," of the Standard Specifications, except for payment.

Drilling of holes and bonding of reinforcing steel dowels shall conform to the provisions for drilling and bonding dowels in Section 83-2.02D(1), "General," of the Standard Specifications. If reinforcement is encountered during drilling before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole to the depth shown on the plans.

The quantity of concrete for paving notch extension will be measured by the cubic meter as determined in conformance with the dimensions shown on the plans or other dimensions that may be ordered in writing by the Engineer.

The contract price paid per cubic meter for paving notch extension shall include full compensation for furnishing all labor, materials (including concrete for the paving notch spalled areas), tools, equipment, and incidentals, and for doing all the work involved in constructing the paving notch extension, complete in place, including structure excavation and backfill, reinforcement, and drilling and bonding dowels, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.58 SOUND WALL

DESCRIPTION

This work shall consist of constructing sound walls of masonry block. Sound walls shall be supported on concrete barriers as shown on the plans.

The Contractor shall select a sound wall type from the alternates shown on the plans. Types of sound wall shall not be mixed in any one installation.

The Contractor shall submit 2 sets of elevation and plan layout drawings to the Engineer, as provided in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The drawings shall be to scale and shall show the proposed top and bottom elevation lines. The top and bottom elevation lines shown on the plans are minimum and shall be fully contained in the proposed layout drawings. The drawings shall include, within the limits shown on the plans, the panel sizes, pile spacing, post spacing, footing steps, aesthetic features, locations of expansion joints, and access gates. The Contractor shall allow 2 weeks after complete drawings are submitted for review.

SOUND WALL (MASONRY BLOCK)

Sound wall (masonry block), consisting of a reinforced hollow unit masonry block stem, shall be constructed in conformance with the provisions in Sections 19, "Earthwork," 52, "Reinforcement," and 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

Sound wall masonry unit stems shall be constructed with joints of portland cement mortar. Wall stems shall be constructed with hand laid block. Wall stems shall not be constructed with preassembled panels.

Concrete for sound wall footings, pile caps, and grade beams, if required, shall be minor concrete.

Concrete masonry units shall be hollow, load bearing, conforming to the requirements in ASTM Designation: C 90, medium weight classification, Type II. The mass of each unit shall not exceed 17.2 kg. Standard or open end units may be used. Open end units, if used, shall not reduce the spacing of the bar reinforcement as shown on the plans.

The masonry units shall be nominal size and texture and of uniform color. The color shall be light tan and dark tan, selected from the manufacturer's standards. The color and texture shall match the existing Soundwall No. 1.

When high strength concrete masonry units with f'm=17.2 MPa are shown on the plans, the high strength masonry units shall have a minimum compressive strength of 26 MPa based on net area. Each high strength concrete masonry unit shall be identified with a groove embedded in an interior corner. The groove shall extend from a mortar surface for a length of about 50 mm and shall have a depth of about 5 mm.

Expansion joint filler shall conform to the requirements in ASTM Designation: D 1751 or ASTM Designation: D 2000 2AA-805.

Portland cement mortar shall be colored to match the units. Coloring shall be chemically inert, fade resistant mineral oxide or synthetic type.

Portland cement for wall stems shall conform to the provisions in Section 90-2.01, "Portland Cement," of the Standard Specifications.

Hydrated lime shall conform to the requirements in ASTM Designation: C 207, Type S.

Mortar sand shall be commercial quality.

Mortar for laying masonry units shall consist, by volume, of one part portland cement, zero to 0.5 part hydrated lime, and 2.25 to 3 parts mortar sand. Sufficient water shall be added to make a workable mortar. Each batch of mortar shall be accurately measured and thoroughly mixed. Mortar shall be freshly mixed as required. Mortar shall not be retempered more than one hour after mixing.

Prepackaged mortar materials and mortar containing admixtures may be used when approved in writing by the Engineer, provided the mortar shall not contain more than 0.05-percent soluble chlorides when tested in conformance with California Test 422 nor more than 0.25-percent soluble sulfates, as SO_4, when tested in conformance with California Test 417.

Before laying masonry units using prepackaged mortar materials or mortar containing admixtures, the Contractor shall submit to the Engineer the proposed sources of the materials together with test data from an independent testing laboratory for mortar tested in conformance with California Test 551. The test data shall be from specimens having a moist cure, except, the sample shall not be immersed in lime water. The average 28-day compressive strength of the mortar shall be not less than 17.2 MPa.

Aggregate for grout used to fill masonry units shall consist of fine aggregate and coarse aggregate conforming to the provisions in Section 90-2.02, "Aggregates," of the Standard Specifications. At least 20 percent of the aggregate shall be

coarse aggregate. The Contractor shall determine the grading except that 100 percent of the combined grading shall pass the 12.5-mm sieve.

At the option of the Contractor, grout for filling masonry units may be proportioned either by volume or mass. Grout shall contain only enough water to cause the grout to flow and fill the voids without segregation. The maximum amount of free water shall not exceed 0.7 times the weight of the cement for regular strength masonry. The maximum amount of free water shall not exceed 0.6 times the mass of the cement for high strength masonry.

Grout proportioned by volume for regular strength masonry shall consist of at least one part portland cement and 4.5 parts aggregate. Grout proportioned by volume for high strength masonry shall consist of at least one part portland cement and 3.5 parts aggregate. Aggregate volumes shall be based on a loose, air-dry condition.

Grout proportioned by mass for regular strength masonry shall contain not less than 325 kilograms of portland cement per cubic meter. Grout proportioned by mass for high strength masonry shall contain not less than 400 kilograms of portland cement per cubic meter.

Reinforced concrete masonry unit wall stems shall be constructed with portland cement mortar joints in conformance with the following:

A. Concrete masonry unit construction shall be true and plumb in the lateral direction and shall conform to the grade shown on the plans in the longitudinal direction. Bond beam units or recesses for horizontal reinforcement shall be provided.
B. Mortar joints shall be approximately 10 mm wide. Walls and cross webs forming cells to be filled with grout shall be full bedded in mortar to prevent leakage of grout. All head and bed joints shall be solidly filled with mortar for a distance in from the face of the wall or unit not less than the thickness of the longitudinal face shells. Head joints shall be shoved tight.
C. Mortared joints around cells to be filled shall be placed so as to preserve the unobstructed vertical continuity of the grout filling. Any overhanging mortar or other obstruction or debris shall be removed from the inside of such cells.
D. Reinforcement shall be securely held in position at top and bottom with either wire ties or spacing devices and at intervals not exceeding 192 bar diameters before placing any grout. Wire shall be 16-gage (1.57 mm) or heavier. Wooden, aluminum, or plastic spacing devices shall not be used.
E. Splices in vertical reinforcement shall be made only at the locations shown on the plans.
F. Only those cells containing reinforcement shall be filled solidly with grout. All grout in the cells shall be consolidated at the time of placement by vibrating, and reconsolidated after excess moisture has been absorbed, but before plasticity is lost. Grout shall not be sliced with a trowel.
G. Walls shall be constructed in 1.2-m maximum height lifts. Grouting of each lift shall be completed before beginning masonry unit construction for the next lift. The top course of each lift shall consist of a bond beam.
H. A construction joint shall be constructed at the top of the top course to permit placement of the mortar cap. The mix design for the mortar cap shall be as approved by the Engineer.
I. Construction joints shall be made when the placing of grout, in grout filled cells, is stopped for more than one hour. The construction joint shall be approximately 12 mm below the top of the last course filled with grout.
J. Bond beams shall be continuous. The top of unfilled cells under horizontal bond beams shall be covered with metal or plastic lath.
K. When fresh masonry joins masonry that is partially or totally set, the contact surface shall be cleaned, roughened, and lightly wetted.
L. Surfaces of concrete on which the masonry walls are to be constructed shall be roughened and cleaned, exposing the aggregate, and shall be flushed with water and allowed to dry to a surface dry condition immediately before laying the masonry units.
M. Where cutting of masonry units is necessary, all cuts shall be made with a masonry saw to neat and true lines. Masonry units with cracking or chipping of the finished exposed surfaces will not be acceptable.
N. Masonry shall be protected in the same manner specified for concrete structures in Section 90-8, "Protecting Concrete," of the Standard Specifications and these special provisions.
O. During erection, all cells shall be kept dry in inclement weather by covering partially completed walls. The covering shall be waterproof fabric, plastic or paper sheeting, or other approved material. Wooden boards and planks shall not be used as covering materials. The covering shall extend down each side of masonry walls approximately 0.6-m.
P. Splashes, stains or spots on the exposed faces of the wall shall be removed.

ACCESS GATES

Access gates shall conform to the details shown on the plans and these special provisions.

Timber members shall be tongue and groove Douglas fir sub-flooring free of knotholes. The location of knots of adjoining boards shall be staggered. The construction of the gate shall be with the tongue placed in the up position. The tongue of the top board and the groove of the bottom board shall be removed.

Timber members, steel frames, channels, anchorage devices, mounting hardware, gate rollers, corrugated steel pipe, nylon washers, and neoprene tubing shall be of commercial quality.

The 25-mm round ladder rungs with non-skid surface shall consist of No. 25 deformed, diamond pattern, bar reinforcing steel of commercial quality.

Gate rollers shall be rigid casters with self-lubricating bearings and hard rubber wheels.

All metal parts and hardware shall be hot-dip galvanized.

Timber surfaces of the access gates shall be primed and then stained with 2 coats of stain to match the adjacent sound wall. Primer and stain shall be of the top grade primer and stain from an established manufacturer. An established manufacturer is one who has manufactured industrial paints and stains to meet custom specifications for at least 10 years.

Where the back side of the masonry wall is to be split faced, or rough surface blocks, the bond beam above the gate opening upon which the upper gate guide is to be mounted shall have smooth sided blocks.

Material from excavation may be used for backfill outside of the pipe landings. Aggregate filling inside the pipe landings shall be a coarse concrete aggregate of commercial quality. Compacting of the aggregate will not be required.

MEASUREMENT AND PAYMENT

Sound walls of the types designated in the Engineer's Estimate will be measured by the square meter of the area of wall projected on a vertical plane between the elevation lines shown on the plans and length of wall (including the exposed posts, back up wall for access openings, and access gates).

The contract price paid per square meter for sound wall of the types designated in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the sound wall, complete in place, including all supports (except barriers, and barrier supports), anchorages, access gates, ladders, existing pile removal, slurry cement backfill and reinforcement, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer. Concrete barrier, and barrier supports supporting sound walls (barrier) will be measured and paid for as separate items of work.

10-1.59 DRILL AND BOND DOWEL (EPOXY CARTRIDGE)

Drilling and bonding dowels with epoxy cartridges shall conform to the details shown on the plans and these special provisions.

Reinforcing steel dowels shall conform to the provisions in "Reinforcement" of these special provisions.

Threaded rods used as dowels shall conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications. The threaded rods shall be installed in conformance with these requirements for dowels specified herein.

The Contractor shall select an epoxy cartridge system which has passed the testing requirements of the International Conference of Building Officials (ICBO) document - AC58 and additional test requirements as specified in the Caltrans Augmentation/Revisions to ICBO AC58. Testing shall be performed by an independent testing facility and the results will be reviewed and approved by the Transportation Laboratory. The Caltrans Augmentation/Revisions to ICBO AC58 document may be obtained by contacting the Transportation Laboratory, telephone: (916) 227-7000.

The epoxy cartridge system used shall be appropriate for the ambient concrete temperature and installation conditions at the time of installation in conformance with the manufacturer's specifications.

Epoxy cartridges shall be accompanied by a Certificate of Compliance as provided in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The certificate shall state that the material complies in all respects to the requirements of ICBO AC58 and Caltrans Augmentation/Revisions to ICBO AC58.

Each epoxy cartridge shall be clearly and permanently marked with the manufacturer's name, model number of the epoxy cartridge system, manufacturing date, and lot number. Each carton of epoxy cartridges shall contain the manufacturer's recommended installation procedures, minimum cure time, and such warning or precautions concerning the contents as may be required by State or Federal Laws and Regulations.

The holes shall be drilled by methods that will not shatter or damage the concrete adjacent to the holes. If reinforcement is encountered during drilling, before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves, in writing, coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole to the depth recommended by the manufacturer.

The drilled holes shall be cleaned in conformance with the manufacturer's instructions and shall be dry at the time of placing the epoxy cartridge bonding material and the steel dowels. The bonding material shall be a 2-component epoxy system contained in a cartridge having 2 separate chambers and shall be inserted into the hole using a dispensing gun and replaceable mixing nozzle approved by the manufacturer. Unless otherwise specified, the depth of hole and the installation

procedure shall be as recommended by the manufacturer. A copy of the manufacturer's recommended installation procedure shall be provided to the Engineer at least 2 days prior to the start of work.

Immediately after inserting the dowels into the epoxy, the dowels shall be supported as necessary to prevent movement during curing and shall remain undisturbed until the epoxy has cured a minimum time as specified by the manufacturer. Dowels that are improperly bonded, as determined by the Engineer, will be rejected. Adjacent new holes shall be drilled, and new dowels shall be placed and securely bonded to the concrete. All work necessary to correct improperly bonded dowels shall be performed at the Contractor's expense.

Unless otherwise provided, dowels to be bonded into drilled holes will be measured and paid for as bar reinforcing steel (bridge).

Full compensation for drilling holes, including coring through reinforcement when approved by the Engineer, and bonding dowels with epoxy cartridges shall be considered as included in the contract price paid per cubic meter for structural concrete, bridge and no additional compensation will be allowed therefor.

10-1.60 DRILL AND BOND DOWELS

Drilling and bonding dowels shall conform to the details shown on the plans, the provisions in Section 83-2.02D(1), "General," of the Standard Specifications, and these special provisions.

Dowels shall conform to the provisions for bar reinforcement in "Reinforcement" of these special provisions.

If reinforcement is encountered during drilling before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole to the depth shown on the plans.

Unless otherwise provided, dowels to be bonded into drilled holes will be paid for as bar reinforcing steel (bridge).

Unless otherwise provided, drilling and bonding dowels will be measured and paid for by the meter determined by the number and the required depth of holes as shown on the plans or as ordered by the Engineer.

The contract price paid per meter for drill and bond dowel shall include full compensation for furnishing all labor, materials (except reinforcing steel dowels), tools, equipment, and incidentals, and for doing all the work involved in drilling the holes, including coring through reinforcement when approved by the Engineer, and bonding the dowels, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.61 CORE CONCRETE

Coring concrete shall consist of coring holes through reinforced concrete bridge members as shown on the plans and in conformance with these special provisions.

The holes shall be cored by methods that will not shatter or damage the concrete adjacent to the holes.

Water for core drilling operations shall be from the local domestic water supply or shall not contain more than 1000 parts per million of chlorides as Cl, nor more than 1300 parts per million of sulfates as SO_4, nor shall the water contain any impurities in a sufficient amount that would cause discoloration of the concrete or produce etching of the surface.

Water from core drilling operations shall not be permitted to fall on public traffic, to flow across shoulders or lanes occupied by public traffic, or to flow into gutters or other drainage facilities.

Coring concrete will be measured by the meter as core concrete of the sizes listed in the Engineer's Estimate. The cored concrete will be measured along the centerline of the hole without deduction for expansion joints.

The contract price paid per meter for core concrete of the sizes listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in coring the holes, including control of water from core drilling and repairing any damaged reinforcement, as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

10-1.62 SEALING JOINTS

Joints in concrete bridge decks and joints between concrete structures and concrete approach slabs shall be sealed in conformance with the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

Where polyurethane seals are shown on the plans, a silicone sealant conforming to the provisions in Section 51–1.12F, "Sealed Joints," of the Standard Specifications may be used.

When ordered by the Engineer, a joint seal larger than called for by the Movement Rating shown on the plans shall be furnished and installed. Payment to the Contractor for furnishing the larger seal and for saw cutting the increment of additional depth of groove required will be determined as provided in Section 4-1.03, "Changes," of the Standard Specifications.

Saw cutting of grooves will not be required at existing joints that are to be sealed with Type A joint seal unless ordered by the Engineer. The Contractor shall make saw cuts as ordered by the Engineer and the saw cutting will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

The contract price paid per meter for joint seals shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in removal and replacement of existing joint seals, complete in place, including removing existing joint seals, repairing and cleaning joints, and installing joint seals as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.63 ARCHITECTURAL SURFACE (TEXTURED CONCRETE)

Architectural texture for concrete surfaces shall conform to the details shown on the plans and the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Architectural textures listed below are required at concrete surfaces shown on the plans:

A. Fractured fin texture

The fractured fin texture shall be an architectural texture simulating the appearance of straight ribs of concrete with a fractured concrete texture imparted to the raised surface between the ribs. Grooves between ribs shall be continuous with no apparent curves or discontinuities. Variation of the groove from straightness shall not exceed 6 mm for each 3 m of groove. The architectural texture shall have random shadow patterns. Broken concrete at adjoining ribs and groups of ribs shall have a random pattern. The architectural texture shall not have secondary patterns imparted by shadows or repetitive fractured surfaces.

TEST PANEL

A test panel at least 1.25 m x 1.25 m in size shall be successfully completed at a location approved by the Engineer before beginning work on architectural textures. The test panel shall be constructed and finished with the materials, tools, equipment and methods to be used in constructing the architectural texture. If ordered by the Engineer, additional test panels shall be constructed and finished until the specified finish, texture and color are obtained, as determined by the Engineer.

The test panel approved by the Engineer shall be used as the standard of comparison in determining acceptability of architectural texture for concrete surfaces.

FORM LINERS

Form liners shall be used for textured concrete surfaces and shall be installed in conformance with the manufacturer's recommendations, unless other methods of forming textured concrete surfaces are approved by the Engineer. Form liners shall be manufactured from an elastomeric material or a semi-elastomeric polyurethane material by a manufacturer of commercially available concrete form liners. No substitution of other types of formliner material will be allowed. Form liners shall leave crisp, sharp definition of the architectural surface. Recurring textural configurations exhibited by repeating, recognizable shadow patterns shall be prevented by proper casting of form liner patterns. Textured concrete surfaces with such recurring textural configurations shall be reworked to remove such patterns as approved by the Engineer or the concrete shall be replaced.

Form liners shall have the following properties:

Description	ASTM Designation:	Range
Elastomeric material		
Shore A hardness	D 2240	20 to 65
Tensile strength (MPa)	D 412	0.9 to 6.2
Semi-elastomeric polyurethane		
Shore D hardness	D 2240	55 to 65
Tensile strength (MPa)	D 2370	18 minimum

Cuts and tears in form liners shall be sealed and repaired in conformance with the manufacturer's recommendations. Form liners that are delaminated from the form shall not be used. Form liners with deformations to the manufactured surface caused by improper storage practices or any other reason shall not be used.

Form liners shall extend the full length of texturing with transverse joints at 2.5 m minimum spacing. Small pieces of form liners shall not be used. Grooves shall be aligned straight and true. Grooves shall match at joints between form liners. Joints in the direction of grooves in grooved patterns shall be located only in the depressed portion of the textured concrete. Adjoining liners shall be butted together without distortion, open cracks or offsets at the joints. Joints between liners shall be cleaned before each use to remove any mortar in the joint.

Adhesives shall be compatible with the form liner material and with concrete. Adhesives shall be approved by the liner manufacturer. Adhesives shall not cause swelling of the liner material.

RELEASING FORM LINERS

Products and application procedures for form release agents shall be approved by the form liner manufacturer. Release agents shall not cause swelling of the liner material or delamination from the forms. Release agents shall not stain the concrete or react with the liner material. For reliefs simulating fractured concrete or wood grain surfaces the application method shall include the scrubbing method using a natural bristle scrub brush in the direction of grooves or grain The release agent shall coat the liner with a thin film. Following application of form release agent, the liner surfaces shall be cleaned of excess amounts of agent using compressed air. Buildup of form release agent caused by the reuse of a liner shall be removed at least every 5 uses.

Form liners shall release without leaving particles or pieces of liner material on the concrete and without pulling or breaking concrete from the textured surface. The concrete surfaces exposed by removing forms shall be protected from damage.

CURING

Concrete surfaces with architectural texture shall be cured only by the forms-in-place or water methods. Seals and curing compounds shall not be used.

MEASUREMENT AND PAYMENT

Architectural texture will be measured and paid for by the square meter.

The contract price paid per square meter for architectural texture of the types listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in architectural texture, complete in place, including test panels, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.64 REINFORCEMENT

Reinforcement shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and these special provisions.

The Department's mechanical splices prequalified list can be found at the following internet site:

http://www.dot.ca.gov/hq/esc/approved_products_list/

The provisions of "Welding Quality Control" of these special provisions shall not apply to resistance butt welding.

When joining new reinforcing bars to existing reinforcement, sample splices shall be made using only the deformation pattern of the new reinforcement to be spliced.

At the option of the Contractor, any splices in CIDH pile vertical reinforcement may be encased in concrete prior to having the QCM review, approve, and forward each Production Test Report to the Engineer. Should the Contractor exercise this option, it is expressly understood that the Contractor will not be relieved of the Contractor's responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection.

Bar reinforcement shown on the plans to be galvanized shall be galvanized in conformance with the provisions in Section 75-1.05,"Galvanizing," of the Standard Specifications.

MEASUREMENT AND PAYMENT

Measurement and payment for reinforcement in structures shall conform to the provisions in Section 52-1.10, "Measurement," and Section 52-1.11, "Payment," of the Standard Specifications and these special provisions.

Full compensation for galvanizing the steel reinforcing bars shall be considered as included in the prices paid for the various items of work involved and no additional compensation will be allowed therefor.

10-1.65 HEADED BAR REINFORCEMENT

Headed bar reinforcement shall consist of bar reinforcement with heads attached to one or both ends. The type of headed bar reinforcement to be used on this project shall be on the Department's current prequalified list prior to use, and shall conform to the provisions of Section 52, "Reinforcement," of the Standard Specifications, the details shown on the plans, and these special provisions.

The Department maintains a list of prequalified headed bar reinforcement types. The prequalified list can be obtained by contacting the Transportation Laboratory and is available at the Department's internet site at:

http://www.dot.ca.gov/hq/esc/approved_products_list/

GENERAL

Prior to manufacturing, the Contractor shall submit to the Engineer the manufacturer's Quality Control (QC) manual for the fabrication of headed bar reinforcement. As a minimum, the QC manual shall include the following:

A. The pre-production procedures for the qualification of materials and equipment.
B. The methods and frequencies for performing QC procedures during production.
C. The calibration procedures and calibration frequency for all equipment.
D. A system for the identification and tracking of all friction welds. The system shall have provisions for permanently identifying each weld and the parameters used to perform it.
E. The welding procedure specification (WPS) for friction welded headed bar reinforcement.
F. A system for marking headed bar reinforcement.

The provisions of "Welding Quality Control" of these special provisions shall not apply to headed bar reinforcement.

The Contractor shall perform inspection and testing prior to, during, and after manufacturing headed bar reinforcement and as necessary to ensure that materials and workmanship conform to the requirements of the specifications.

A daily production log for the manufacture of headed bar reinforcement shall be maintained by the manufacturer for each production lot. The log shall clearly indicate the production lot numbers, the heats of bar material and head material used in the manufacture of each production lot, the number of bars in each production lot, and manufacturing records, including tracking and production parameters for welds or forgings. The data from the daily production log shall be available to the Engineer upon request.

A production lot of headed bar reinforcement is defined as 150 reinforcing bars, or fraction thereof, of the same bar size, with heads of the same size and type, and manufactured by the same method, produced from bar material of a single heat number and head material of a single heat number. If one reinforcing bar has a head on both ends, it will be counted as two reinforcing bars for the purposes of establishing and testing production lots. A new production lot shall be started if the heat number of either the bar material or the head material changes before the maximum production lot size of 150 is reached.

The Contractor shall furnish Certificates of Compliance accompanied by a copy of the mill test report, the Production Tests Reports specified herein, and the corresponding daily production logs to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each shipment of headed bar reinforcement delivered to the jobsite.

Welding, welder qualifications, and inspection of welding shall conform to the requirements for friction welding in ANSI/AWS C6.1.

Equipment used to perform friction welding shall be fitted with an effective in-process monitoring system to record essential production parameters that describe the process of welding the head onto the reinforcement. The parameters to be recorded shall include friction welding force, forge force, rotational speed, friction upset distance and time, and forge upset distance and time. The data from this in-process monitoring shall be recorded and preserved by the manufacturer until acceptance of the contract and shall be provided to the Engineer upon request.

PRODUCTION TESTS

Production tests shall be performed at the Contractor's expense, at an independent qualified testing laboratory, and in the presence of the Engineer, unless otherwise directed in writing. The independent qualified testing laboratory used to perform the testing of headed bar reinforcement samples shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors who will provide other services or materials for the project, and shall have the following:

A. A tensile testing machine capable of breaking the largest size of reinforcing bar to be tested.
B. Operators who have received formal training for performing the testing requirements of ASTM Designation: A 970/A 970M.

C. A record of annual calibration of testing equipment performed by an independent third party that has 1) standards that are traceable to the National Institute of Standards and Technology, and 2) a formal reporting procedure, including published test forms.

The Engineer shall be notified in writing when any lots of headed bar reinforcement are ready for testing. The notification shall include the number of lots to be tested and the location where the tests are to be conducted. After notification has been received, test samples will be randomly selected by the Engineer from each production lot of headed bar reinforcement which is ready for shipment to the jobsite. If epoxy coating is required, test samples will be taken after the headed bar reinforcement has been prepared for epoxy coating. The Engineer will be at the testing site within a maximum of one week after receiving written notification that the samples are at the testing site and ready for testing. In the event the Engineer fails to be present at the testing site within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by failure of the Engineer to be present at the testing site, the Contractor will be compensated for any resulting loss in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

A minimum of 3 samples from each production lot shall be tested. One tensile test shall be conducted on each sample.

Tensile tests shall conform to the requirements specified in ASTM Designation: A 970/A 970M, Section 7, except that at rupture, there shall be visible signs of necking in the reinforcing bar 1) at a minimum distance of one bar diameter away from the head to bar connection for friction welded headed bar reinforcement, or 2) outside the affected zone for integrally forged headed bar reinforcement.

The affected zone for integrally forged headed bar reinforcement is the portion of the reinforcing bar where any properties of the bar, including the physical, metallurgical, or material characteristics, have been altered during the manufacturing process.

If one of the test specimens fails to meet the specified requirements, one retest shall be performed on one additional sample, selected by the Engineer, from the same production lot. If the additional test specimen, or if more than one of the original test specimens fail to meet these requirements, all headed bar reinforcement in the lot represented by the tests will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials," of the Standard Specifications.

A Production Test Report for all testing performed on each lot shall be prepared by the independent testing laboratory and submitted to the Engineer as specified herein. The report shall be signed by an engineer who represents the laboratory and is registered as a Civil Engineer in the State of California. The report shall include the following information for each set: contract number, bridge number, lot number, bar size, type of headed bar reinforcement, physical conditions of test sample, any notable defects, limits of affected zone, location of visible necking area, and the ultimate strength of each headed bar.

Each unit of headed bar reinforcement in a production lot to be shipped to the site shall be tagged in a manner such that production lots can be accurately identified at the jobsite. All unidentified headed bar reinforcement received at the jobsite will be rejected.

MEASUREMENT AND PAYMENT

Bar reinforcement to be used in the manufacture of headed bar reinforcement will be measured and paid for as specified in Section 52, "Reinforcement," of the Standard Specifications.

Full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing heads and friction welding or integrally forging heads onto bar reinforcement, including conformance with all testing requirements and for placing the completed headed bar reinforcement into the work, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer shall be considered as included in the contract price paid per kilogram for the bar reinforcement involved and no additional compensation will be allowed therefor.

10-1.66 TREAT BRIDGE DECKS

Treating bridge decks shall consist of test sealing, and furnishing and applying a penetrating sealer as shown on the plans and as specified in these special provisions.

The following bridges shall be treated:

Almaden Road Undercrossing (Widen) Br. No. 37-366L
Alma Overhead (Widen) Br. No. 37-420L
Alma Avenue Undercrossing (Widen) Br. No. 37-368L
Alma Station PUC (Widen) Br. No. 37-434L
Alma Station Separation (Widen) Br. No. 37-421L
Willow Street Viaduct (Widen) Br. No. 37-422L

The surfaces to be treated include existing bridge decks. Prior to treating bridge decks, the deck surface shall be cleaned as specified in “Clean Bridge Decks” of these special provisions.

Prior to the start of deck treatment work, the Contractor shall submit for approval by the Engineer, a program for public safety associated with the use of methacrylate resin. The program shall identify materials, equipment, and methods to be used. The Contractor shall not perform deck treatment work, other than that specifically authorized in writing by the Engineer, until the program has been approved.

If the measures being taken by the Contractor are inadequate to provide for public safety associated with the use of methacrylate resin, the Engineer will direct the Contractor to revise the operations and the public safety program. Directions for revisions will be in writing and will specify the items in which the Contractor's program is inadequate. No further deck treatment shall be performed until public safety measures are adequate, and a revised program for public safety has been approved.

The Engineer will notify the Contractor of the approval or rejection of any submitted or revised program for public safety associated with the use of methacrylate resin within 10 working days of receipt of the program.

The State will not be liable to the Contractor for failure to approve all or any portion of an originally submitted or revised program for public safety associated with the use of methacrylate resin, nor for any delays to the work due to the Contractor's failure to submit an acceptable program for public safety associated with the use of methacrylate resin. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

MATERIALS

The material used for treating the concrete shall be a low odor, high molecular weight methacrylate resin. Prior to adding initiator, the resin shall have a maximum volatile content of 30 percent, when tested in conformance with the requirements in ASTM Designation: D 2369, and shall conform to the following:

PROPERTY	TEST METHOD	REQUIREMENT
* Viscosity Pa·s, maximum, (Brookfield RVT with UL adaptor, 50 RPM at 25°C)	ASTM D 2196	0.025
* Specific Gravity minimum, at 25°C	ASTM D 1475	0.90
* Flash Point °C, minimum	ASTM D 3278	82
* Vapor Pressure mm Hg, maximum, at 25°C	ASTM D 323	1.0
Tack-free Time minutes, maximum at 25°C	California Test 551	400
PCC Saturated Surface-Dry Bond Strength MPa, minimum at 24 hours and 21±1°C	California Test 551	3.5
* Test shall be performed prior to adding initiator.		

A Material Safety Data Sheet shall be furnished prior to use for each shipment of high molecular weight methacrylate resin.

The promoter and initiator, if supplied separately from the resin, shall not be mixed directly with each other. Containers of promoters and initiators shall not be stored together in a manner that will allow leakage or spillage from one to contact the containers or material of the other.

TESTING

The Contractor shall allow 14 working days for sampling and testing by the Engineer of the high molecular weight methacrylate resin prior to proposed use.

The Contractor shall treat a test area within the project limits of approximately 50 m^2 at a location approved by the Engineer. Conditions during the test treatment shall be similar to those expected on the deck. Equipment used in the test shall be similar to those used for the deck treating operations. If the test area is on the traveled way, traffic shall not be allowed on the treated test area until (1) the treated surface is tack free (non-oily), (2) the sand cover adheres sufficiently to resist brushing by hand, and (3) the coefficient of friction of the deck is at least 0.35 when tested in conformance with the requirements in California Test 342.

Should the above requirements for traffic use not be met, the Contractor shall suspend treating of bridge decks until another test area is treated and complies with the requirements.

CONSTRUCTION

Prior to treating bridge decks, the deck surface shall be cleaned as specified in "Clean Bridge Deck" of these special provisions.

Equipment shall be fitted with suitable traps, filters, drip pans, or other devices as necessary to prevent oil or other deleterious material from being deposited on the deck.

The relative humidity shall be less than 90 percent at time of treatment.

A compatible promoter/initiator system shall be capable of providing a resin gel time of not less than 40 minutes nor more than 1.5 hours at the temperature of application. Gel time shall be adjusted to compensate for the changes in temperature throughout treatment application.

The quantity of resin mixed with promoter and initiator shall be limited to 20 L at a time for manual application.

Machine application of the resin shall be performed by using a two-part resin system using a promoted resin for one part and an initiated resin for the other part. This two-part resin system shall be combined at equal volumes to the spray bars through separate positive displacement pumps. Combining of the 2 components shall be by either static in-line mixers or by external intersecting spray fans. The pump pressure at the spray bars shall not be great enough to cause appreciable atomization of the resin. Compressed air shall not be used to produce the spray. A shroud shall be used to enclose the spray bar apparatus. Hand held spray apparatus shall not be used.

The Contractor shall apply methacrylate resin only to the specified area. Concrete barriers, joints, and drainage facilities shall be adequately protected to prevent contamination by the treatment material. Contaminated items shall be repaired at the Contractor's expense.

The prepared area shall be dry and the surface temperature shall not exceed 38°C when the resin is applied. The rate of application of promoted/initiated resin shall be approximately 2.5 square meter per liter; the exact rate shall be determined by the Engineer.

The deck surfaces to be treated shall be flooded with resin, allowing penetration into the concrete and filling of all cracks. The treatment shall be applied within 5 minutes after complete mixing. A significant increase in viscosity shall be cause for rejection. Excess material shall be redistributed by squeegees or brooms within 10 minutes after application.

After the resin has been applied, at least 20 minutes shall elapse before applying sand. The sand shall be commercial quality dry blast sand. Ninety-five percent of the sand shall pass the 2.36-mm sieve, and 95 percent shall be retained on the 850-µm sieve. The sand shall be applied at a rate of approximately one kilogram per square meter.

Excess sand shall be removed from the deck surface by vacuuming or sweeping prior to opening to traffic.

Traffic shall not be allowed on the treated area until (1) the treated surface is tack free (non-oily), (2) the sand cover adheres sufficiently to resist brushing by hand, and (3) the coefficient of friction of the deck is at least 0.35 when tested in conformance with the requirements in California Test 342.

MEASUREMENT AND PAYMENT

Treating bridge deck surfaces will be measured by the square meter based on plan dimensions and will be paid for as treat bridge deck. Furnishing the high molecular weight methacrylate resin will be measured by the liter of mixed material actually placed and will be paid for as furnish bridge deck treatment material. No payment will be made for material wasted or not used in the work.

The contract price paid per square meter for treat bridge deck shall include full compensation for furnishing all labor, materials, (including sand, but excluding treatment material), tools, equipment, and incidentals, and for doing all the work involved in test sealing, applying treatment material and removing excess sand, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract price paid per liter for furnish bridge deck treatment material shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals necessary to furnish the bridge deck treatment material to the site of the work, ready for application, as specified in the Standard Specifications and these special provisions and as directed by the Engineer.

10-1.67 SIGN STRUCTURES

Sign structures and foundations for overhead signs shall conform to the provisions in Section 56-1, "Overhead Sign Structures," of the Standard Specifications and these special provisions.

Attention is directed to "Hazardous, Restricted and Non-Hazardous Material, General," and "Naturally Occurring Asbestos Material-General," elsewhere in these special provisions.

Before commencing fabrication of sign structures, the Contractor shall submit 2 sets of working drawings to the Engineer in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The working drawings shall include sign panel dimensions, span lengths, post heights, anchorage layouts, proposed splice locations, a snugging and tensioning pattern for anchor bolts and high strength bolted connections, and details for permanent steel anchor bolt templates. The working drawings shall be supplemented with a written quality control program that includes methods, equipment, and personnel necessary to satisfy the requirements specified herein and in the special provisions.

Working drawings shall be 559 mm x 864 mm or 279 mm x 432 mm in size and each drawing and calculation sheet shall include the State assigned designations for the contract number, sign structure type and reference as shown on the contract plans, District-County-Route-Kilometer Post, and contract number.

The Engineer shall have 20 working days to review the sign structure working drawings after a complete submittal has been received. No fabrication or installation of sign structures shall be performed until the working drawings are approved in writing by the Engineer.

Should the Engineer fail to complete the review within the time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the sign structure working drawings, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

A permanent steel template shall be used to maintain the proper anchor bolt spacing.

One top nut, one leveling nut, and 2 washers shall be provided for the upper threaded portion of each anchor bolt.

Surfaces of base plates which are to come in contact with concrete, grout, or washers and leveling nuts shall be flat to within 3 mm tolerance in 305 mm, and to within 5 mm tolerance overall. Faying surfaces of plates in high-strength bolted connections including flange surfaces of field splices, chord joints, and frame junctures, and contact surfaces of plates used for breakaway slip base assemblies shall be flat to within 2 mm tolerance in 305 mm, and within 3 mm tolerance overall.

Thermally cut holes made in tubular members of sign supports, other than holes in base and flange plates, shall initially be made a minimum of 2 mm undersized, and then be mechanically enlarged by reaming or grinding to the final required size and shape. All edges shall have a surface roughness of not greater than 6.35 μm. Round holes may be drilled to the exact final diameter. No holes shall be made in members unless the holes are shown on the plans or are approved in writing by the Engineer.

Steel members used for overhead sign structures shall receive nondestructive testing (NDT) in conformance with AWS D1.1 and the following:

A.

Weld Location	Weld Type	Minimum Required NDT
Welds for butt joint welds in tubular sections, nontubular sections, and posts	CJP groove weld with backing ring	100% UT or RT
Longitudinal seam welds*	PJP groove weld	25% MT
	CJP groove weld	100% UT or RT
Welds for base plate, flange plate, or end cap to post or mast arm	CJP groove weld	25% UT or RT
	Fillet weld	25% MT
* Longitudinal seam welds shall have 60% minimum penetration, except that within 150 mm of any circumferential weld, longitudinal seam welds shall be CJP groove welds.		

B. A written procedure approved by the engineer shall be used when performing UT on material less than 8 mm thick. Contoured shoes shall be used when performing UT on round tubular sections under 1270 mm in diameter.

C. When less than 100 percent of a weld is specified for NDT, and if defects are found during this inspection, additional NDT shall be performed. This additional NDT shall be performed on 25 percent of the total weld for all similar welds, as determined by the Engineer, produced for sign structures in the project. If any portion of the additional weld inspected is found defective, 100 percent of all similar welds produced for sign structures in the project, as determined by the Engineer, shall be tested.

Circumferential welds and base plate to post welds may be repaired only one time without written permission from the Engineer.

Full compensation for furnishing anchor bolt templates and for testing of welds shall be considered as included in the contract price paid per kilogram for furnish sign structure and no additional compensation will be allowed therefor.

10-1.68 ROADSIDE SIGNS

Roadside signs shall be installed at the locations shown on the plans or where designated by the Engineer and in conformance with the provisions in Section 56-2, "Roadside Signs," of the Standard Specifications and these special provisions.

Attention is directed to "Hazardous, Restricted and Non-Hazardous Material, General," and "Naturally Occurring Asbestos Material-General," elsewhere in these special provisions.

Wood posts shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications with creosote, creosote coal tar solution, creosote petroleum solution (50-50), pentachlorophenol in hydrocarbon solvent, copper naphthenate, ammoniacal copper arsenate, or ammoniacal copper zinc arsenate. In addition to the preservatives listed above, Southern yellow pine may also be pressure treated with chromated copper arsenate. When other than one of the creosote processes is used, blocks shall have a minimum retention of 6.4 kg/m^3, and need not be incised.

Roadside signs mounted on barriers will be measured by the kilogram as metal (barrier mounted sign) for quantity of steel (including pipe posts, base plates, anchorage assemblies and other metal parts, except sign panels and sign panel fastening hardware). The pay quantities will be determined as provided in Section 55-4.01, "Measurement" of the Standard Specifications.

Roadside signs mounted on soundwalls will be measured by the kilogram as metal (soundwall mounted sign) for quantity of steel (including pipe posts, base plates, anchorage assemblies and other metal parts, except sign panels and sign panel fastening hardware). The pay quantities will be determined as provided in Section 55-4.01, "Measurement" of the Standard Specifications.

10-1.69 INSTALL FRAMED SIGN PANEL

Framed sign panels shall be installed on existing sign structures as shown on the plans and in conformance with the provisions in Section 56-1, "Overhead Sign Structures," of the Standard Specifications and these special provisions.

Sign panels will be furnished by the State as provided under "Materials" of these special provisions.

Installing framed sign panels will be measured by the unit as determined from actual count in place. A unit shall consist of one removable sign panel frame with sign panels attached.

The contract unit price paid for installing framed sign panel shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in install framed sign panel, complete in place as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.70 INSTALL SIGN OVERLAY

Sign overlays shall be installed on existing signs as shown on the plans and in conformance with these special provisions.

Sign overlay panels will be furnished by the State as provided under "Materials" of these special provisions.

Self plugging blind rivets for installing sign overlays shall have a 4.8-mm x 15.9-mm shank. A No. 10 drill shall be used for drilling the rivet holes. If the overlay is not pre-punched, maximum rivet spacing shall be 400 mm.

Where the existing sign panel is porcelain enameled steel, a diamond bit shall be used for drilling rivet holes. Exposed metal around the hole shall be covered with a thin coat of silicone adhesive conforming to the provisions in "Adhesive for Bonding Reflex Reflectors to Porcelain Enamel Traffic Signs" of these special provisions.

Installing sign overlays will be measured by the square meter.

The contract price paid per square meter for install sign overlay shall include full compensation for furnishing all labor, materials (except sign overlays), tools, equipment, and incidentals, and for doing all the work involved in installing sign overlay panels on existing signs (including fastening hardware), as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.71 CLEAN AND PAINT STRUCTURAL STEEL

Exposed new metal surfaces and connections to existing steel, except where galvanized, shall be cleaned and painted in conformance with the provisions in Section 59-2, "Painting Structural Steel," and Section 91, "Paint," of the Standard Specifications and these special provisions.

Whenever the Standard Specifications refer to "Steel Structures Painting Council," the reference shall be replaced with "SSPC: The Society for Protective Coatings."

Prior to performing any painting or paint removal, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate Painting Quality Work Plan (PQWP) for each item of work for which painting or paint removal is to be performed. As a minimum, each PQWP shall include the following:

A. The name of each Contractor or subcontractor to be used.
B. One copy each of all current "SSPC: The Society for Protective Coatings" specifications or qualification procedures which are applicable to the painting or paint removal to be performed. These documents shall become the permanent property of the Department.
C. Proposed methods and equipment to be used for any paint application.

The Engineer shall have 2 weeks to review the PQWP submittal after a complete plan has been received. No painting or paint removal shall be performed until the PQWP for that work is reviewed by the Engineer. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the PQWP, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The existing paint systems consist of materials listed in "Existing Highway Facilities" of these special provisions.

CLEANING

Exposed new metal surfaces and new metal surfaces of high strength bolted connections to existing steel, except where galvanized, shall be dry blast cleaned in conformance with the requirements in Surface Preparation Specification No. 10, "Near White Blast Cleaning," of the "SSPC: The Society for Protective Coatings." Blast cleaning shall leave surfaces with a dense, uniform, angular anchor pattern of no less than 40 µm nor more than 86 µm as measured in conformance with the requirements in ASTM Designation: D 4417.

Existing contact surfaces of high strength bolted connections, including the inside surfaces of new and existing bolt holes when required, shall be cleaned in conformance with the requirements in Surface Preparation Specification No. 1, "Solvent Cleaning," of the "SSPC: The Society for Protective Coatings."

PAINTING

Blast cleaned surfaces shall receive a single undercoat consisting of a waterborne inorganic zinc coating conforming to the requirements in AASHTO Designation M 300, Type II, except that: 1) the first 3 sentences of Section 4.7, "Primer Field Performance Requirements," and the entire Section 4.7.1 shall not apply, and 2) zinc dust shall be Type II in conformance with the requirements in ASTM Designation: D 520. The inorganic zinc coating shall be listed on the qualified products list which may be obtained from the Transportation Laboratory.

Inorganic zinc coating shall be used within 12 hours of initial mixing.

Application of inorganic zinc coating shall conform to provisions for applying zinc-rich coating in Section 59-2.13, "Application of Zinc-Rich Primer," of the Standard Specifications.

Inorganic zinc coating shall not be applied when the atmospheric or surface temperature is less than 7°C nor more than 29°C, nor when the relative humidity exceeds 85 percent.

The single undercoat of inorganic zinc coating shall be applied to the required dry film thickness in 2 or more applications within 4 hours after blast cleaning.

The total dry film thickness of all applications of the inorganic zinc undercoat, including the surfaces of outside existing members within the grip under bolt heads, nuts and washers, shall be not less than 100 µm nor more than 200 µm, except that the total dry film thickness on each faying (contact) surface of high strength bolted connections shall be between 25 µm and the maximum allowable dry film thickness for Class B coatings as determined by certified testing in conformance with Appendix A of the "Specification for Structural Joints Using ASTM A325 or A490 Bolts" of the Research Council on Structural Connections (RCSC Specification). Unless otherwise stated, all inorganic zinc coatings used on faying surfaces shall meet the slip coefficient requirements for a Class B coating on blast-cleaned steel, as specified in the RCSC Specification. The Contractor shall provide results of certified testing showing the maximum allowable dry film thickness for the Class B coating from the qualifying tests for the coating he has chosen, and shall maintain the coating thickness on actual faying surfaces of the structure at or below this maximum allowable coating thickness.

Areas where mudcracking occurs in the inorganic zinc coating shall be blast cleaned and repainted with inorganic zinc coating to the specified thickness.

Dry spray, or overspray, as defined in the Steel Structures Painting Manual, Volume 1, "Good Painting Practice," of the "SSPC: The Society for Protective Coatings," shall be removed prior to application of subsequent coats or final acceptance. Removal of dry spray shall be by screening or other methods that minimize polishing of the inorganic zinc surface. The dry film thickness of the coating after removal of dry spray shall be in conformance with the provisions for applying the single undercoat, as specified herein.

MEASUREMENT AND PAYMENT

Full compensation for clean and paint structural steel shall include furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in cleaning and painting the exposed surfaces of the new structural steel and shall be considered as included in the contract price per kilogram for Miscellaneous Metal (Restrainer–Pipe Type) or (Restrainer–Bar Type) and no separate payment will be made therefor.

10-1.72 ALTERNATIVE PIPE

Alternative pipe culverts shall conform to the provisions in Section 62, "Alternative Culverts," of the Standard Specifications and these special provisions.

Attention is directed to "Relations with Santa Clara Valley Transportation Authority" elsewhere in these special provisions, regarding requirements in the Light Rail right-of-way.

SPIRAL RIB PIPE

Spiral rib pipe shall conform to the provisions in "Corrugated Metal Pipe" of these special provisions, except for profile and fabrication requirements.

Spiral rib pipe shall, at the option of the Contractor, consist of either (1) three rectangular ribs spaced midway between seams with ribs 19 mm wide by 19 mm high at a maximum rib pitch of 191 mm, (2) two rectangular ribs and one half-circle rib equally spaced between seams with ribs 19 mm wide by 25 mm high at a maximum rib pitch of 292 mm. The half-circle rib diameter shall be spaced midway between the rectangular ribs or (3) two rectangular ribs equally spaced between seams with ribs 19 mm wide by 25 mm high at a maximum rib pitch of 213 mm. Rib pitch measured at right angles to the direction of the ribs may vary ±13 mm.

Corrugated steel spiral rib pipe shall be fabricated by a continuous helical lock seam fabricated in conformance with the provisions in Section 66-3.03C(1), "Fabrication by Continuous Lock Seam," of the Standard Specifications.

Corrugated aluminum spiral rib pipe shall be fabricated by a continuous helical lock seam fabricated in conformance with the provisions in Section 66-2.03B, "Fabrication by Continuous Helical Lock Seam," of the Standard Specifications.

Coupling bands for spiral rib pipe shall conform to the provisions in Section 66-1.07, "Coupling Bands," of the Standard Specifications. A coupling band shown on the plans or approved by the Engineer in conformance with the provisions in Section 61-1.02, "Performance Requirements for Culvert and Drainage Pipe Joints," of the Standard Specifications, for use on a pipe corrugation of 68 mm x 13 mm for corrugated metal pipe may be used on spiral rib pipe having 68 mm x 13 mm rerolled annular ends. The width of band (W) for hat bands for pipe sizes larger than 1200 mm in diameter shall be 95 mm.

Concrete backfill for alternative culverts shall be constructed in conformance with the provisions in Section 66-1.045, "Concrete Backfill," of the Standard Specifications and will be measured and paid for in conformance with the provisions in Section 66-4, "Measurement and Payment," of the Standard Specifications and the following:

A. The quantity of concrete backfill to be paid for, regardless of the kind of culvert and wall thickness of the culvert installed, will be based on the dimensions shown on the plans and the installation of corrugated steel pipe.

10-1.73 PLASTIC PIPE

Plastic pipe shall conform to the provisions in Section 64, "Plastic Pipe," of the Standard Specifications.

10-1.74 REINFORCED CONCRETE PIPE

Reinforced concrete pipe shall conform to the provisions in Section 65, "Reinforced Concrete Pipe," of the Standard Specifications and these special provisions.

Where embankment will not be placed over the top of the pipe, a relative compaction of not less than 85 percent shall be required below the pipe spring line for pipe installed using Method 1 backfill in trench, as shown on Standard Plan A62D. Where the pipe is to be placed under the traveled way, a relative compaction of not less than 90 percent shall be required unless the minimum distance between the top of the pipe and the pavement surface is the greater of 1.2 m or one half of the outside diameter of the pipe.

Except as otherwise designated by classification on the plans or in the specifications, joints for culvert and drainage pipes shall conform to the plans or specifications for standard joints.

When reinforced concrete pipe is installed in conformance with the details shown on Revised Standard Plan A62DA, the fifth paragraph of Section 19-3.04, "Water Control and Foundation Treatment," of the Standard Specifications shall not apply.

When solid rock or other unyielding material is encountered at the planned elevation of the bottom of the bedding, the material below the bottom of the bedding shall be removed to a depth of 1/50 of the height of the embankment over the top of the culvert, but not less than 150 mm nor more than 300 mm. The resulting trench below the bottom of the bedding shall be

backfilled with structure backfill material in conformance with the provisions in Section 19-3.06, "Structure Backfill," of the Standard Specifications.

The excavation and backfill below the planned elevation of the bottom of the bedding will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

The Outer Bedding shown on Revised Standard Plan A62DA shall not be compacted prior to placement of the pipe.

10-1.75 JACKED REINFORCED CONCRETE PIPE

Jacked reinforced concrete pipe shall conform to the provisions in Section 65-1.05, “Jacking Pipe”, of the Standard Specifications and these special provisions.

Attention is directed to “Hazardous, Restricted and Non-Hazardous Material, General,” and “Naturally Occurring Asbestos Material-General,” elsewhere in these special provisions.

Attention is directed to “Relations with Santa Clara Valley Transportation Authority” elsewhere in these special provisions, regarding requirements in the Light Rail right-of-way.

At least four weeks prior to starting the jacking work, the Contractor shall submit drawings of, but not limited to, the jacking pit bracing, the conduit, jacking head proposed to be used, and details for securing headway in an emergency. Drawings shall be of a size and scale to show clearly all necessary details and shall be in accordance with Section 5-1.02, “Plans and Working Drawings,” of the Standard Specifications.

Unless otherwise specified, the methods and equipment used in jacking the reinforced concrete pipe shall be optional with the Contractor, provided the proposed method is approved by the Engineer. Such approval, however, shall in no way relieve the Contractor of the responsibility for making a satisfactory installation meeting the criteria set forth herein.

Unless otherwise approved by the Engineer, once the jacking of the reinforced concrete pipe has commenced, the Contractor shall continue the operation until the pipe has been jacked into its final location as shown on the plans.

Variations from theoretical alignment and grade at the time of completion of jacking shall not exceed one tenth of one percent of the distance from the jacking point.

A survey grid shall be set over the centerline of the RCP and 1.5m and 3m out from the centerline on each side. Surface elevations shall be established 3m on center along the survey grid lines. Survey readings shall be performed prior to the beginning of work, during the jacking operation as each grid point is reached, and after the project is complete. As each grid point is reached, its surface elevation shall be compared to the initial grid point reading. Any differential amount (heave or settlement in pavement) shall not exceed 30mm. Copies of the survey notes shall be submitted to the Engineer. The details for corrective actions to be taken should settlement or heaving of the pavement be detected must be included in the working drawings submitted by the Contractor for approval.

Dewatering for jacking shall conform to Section 19-3.04, “Water Control and Foundation Treatment,” of the Standard Specifications. All water encountered during the jacking operation shall be discharged to closed top, water tight, transportable holding tanks. The water in the holding tanks shall be treated and discharged as directed by the Engineer. Handling, transportation storage, treatment and discharging of such water as directed by the Engineer will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Upon completion of jacking the reinforced concrete pipe and backfilling the jacking pits, the area shall be graded smooth and compacted to conform with adjacent areas.

10-1.76 CORRUGATED METAL PIPE

Corrugated steel pipe culverts shall conform to the provisions in Section 66, "Corrugated Metal Pipe," of the Standard Specifications and these special provisions.

Slotted corrugated steel pipe shall have tapered spacers as shown on the plans.

10-1.77 UNDERDRAIN

Perforated plastic pipe underdrains shall conform to the provisions in Section 68-1, "Underdrains," of the Standard Specifications and these special provisions.

Traffic pull boxes for underdrains shall conform to the provision in Section 86-2.07, “Traffic Pull Boxes,” of the Standard Specifications and these special provisions. Pull box covers shall be marked as “Caltrans”.

Attention is directed to “Relations with Santa Clara Valley Transportation Authority” elsewhere in these special provisions, regarding requirements in the Light Rail right-of-way.

Full compensation for traffic pull boxes for underdrains shall be considered as included in the contract price per meter for the items of work involved and no separate payment will be made therefor.

10-1.78 EDGE DRAIN

Edge drains shall conform to the provisions in Section 68-3, "Edge Drains," of the Standard Specifications .

10-1.79 PERMEABLE MATERIAL (BLANKET)

Permeable material blanket shall be constructed in conformance with the details shown on the plans and these special provisions.

Permeable material for permeable material blanket shall be Class 3 and shall conform to the provisions in Section 68-1, "Underdrains," of the Standard Specifications, except for payment.

Class 3 permeable material shall conform to the following grading requirements:

Grading Requirements

Sieve Sizes	Percentage Passing
37.5-mm	100
25-mm	88-100
19-mm	52-85
9.5-mm	15-38
4.75-mm	0-16
2.36-mm	0-6

Class 3 permeable material shall have a Durability Index of not less than 40.

At least 90 percent by mass of Class 3 permeable material shall be crushed particles as determined by California Test 205.

Filter fabric for use with permeable material blanket shall conform to the provisions for filter fabric for underdrain trenches in Section 88, "Engineering Fabrics," of the Standard Specifications and the following:

A. The subgrade to receive the filter fabric, immediately prior to placing, shall conform to the compaction and elevation tolerance specified for the material involved.
B. Filter fabric shall be handled and placed in conformance with the manufacturer's recommendations.
C. The fabric shall be aligned and placed in a wrinkle-free manner.
D. Adjacent borders of the fabric shall be overlapped from 300 mm to 450 mm or stitched. The preceding roll shall overlap the following roll in the direction the material is being spread or shall be stitched. When the fabric is joined by stitching, the fabric shall be stitched with yarn of a contrasting color. The size and composition of the yarn shall be as recommended by the fabric manufacturer. The stitches shall number 5 to 7 per 25 mm of seam.
E. Within 24 hours after the filter fabric has been placed, the fabric shall be covered with the planned thickness of permeable material or aggregate subbase material as shown on the plans.
F. During spreading and compaction of the permeable material and aggregate subbase material, a minimum of 150 mm of the material shall be maintained between the fabric and the Contractor's equipment. Where embankment material is to be placed on the filter fabric, a minimum of 450 mm of embankment material shall be maintained between the fabric and the Contractor's equipment. Equipment or vehicles shall not be operated or driven directly on the filter fabric.

Class 3 permeable material (blanket) will be measured by the cubic meter. Quantities of permeable material to be paid for as permeable material (blanket) will be determined from the dimensions shown on the plans or such other dimensions as may be ordered in writing by the Engineer. Permeable material blanket constructed in excess of these dimensions will not be paid for.

The contract price paid per cubic meter for Class 3 permeable material (blanket) shall include full compensation for furnishing all labor, materials (including filter fabric), tools, equipment, and incidentals, and for doing all the work involved in constructing a permeable material (blanket) and placing filter fabric, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.80 OVERSIDE DRAIN

Metal pipe downdrain anchor assemblies, and corrugated steel pipe downdrains shall conform to the provisions in Section 69, "Overside Drains," of the Standard Specifications and these special provisions.

Steel entrance tapers and pipe downdrains shall be fabricated from zinc-coated steel sheet.

Plastic pipe for overside drains shall be Type S corrugated high density polyethylene or ribbed polyvinyl chloride pipe conforming to the provisions in Section 64, "Plastic Pipe," of the Standard Specification.

Plastic pipe joints shall conform to the provisions in Section 61-1.02, "Performance Requirements for Culvert and Drainage Pipe Joints," of the Standard Specifications for downdrain joints, except that the alternatives selected for plastic pipe joint restrainer assemblies shown on the plans shall serve in lieu of the tensile strength requirements. The joint overlap requirements for integral joints shall conform to the requirements for positive joints.

Plastic pipe joint restrainer assembly, Alternative A, when used shall be installed immediately below the pipe bell.

Polyvinyl chloride pipe shall not be used unless the overside drain is covered for the entire length of the overside drain.

Plastic pipe overside drains shall be installed with the bell end of the pipe facing uphill.

10-1.81 MISCELLANEOUS FACILITIES

Flared end sections, automatic drainage gates, and precast concrete pipe manholes shall conform to the provisions in Section 70, "Miscellaneous Facilities," of the Standard Specifications and these special provisions.

Manhole bases for precast concrete manholes in City streets shall be cast in place. Precast manhole bases will not be allowed.

10-1.82 WELDED STEEL PIPE CASING (BRIDGE)

Welded steel pipe casings through bridges and under approach slabs shall be of the size shown and shall conform to the provisions in Section 70, "Miscellaneous Facilities," of the Standard Specifications and these special provisions.

Unless otherwise shown on the project plans, casings shall be installed at each abutment, and casings shall be extended to the greater of: (1) 1.5 m beyond the approach slab, (2) 1.5 m beyond the end of the adjacent wingwall or (3) 6 m beyond the abutment.

WORKING DRAWINGS

Working drawings for temporary support of casing pipe at the abutments shall be submitted for approval in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings" of the Standard Specifications.

MATERIALS

Casing pipe

Casing pipe shall be welded steel pipe conforming to the provisions in Section 70-1.02B, "Welded Steel Pipe," of the Standard Specifications, except that the pipe shall be treated in accordance with the following requirements, prior to shipping. Exterior surfaces of welded steel pipe shall be cleaned and coated in conformance with the requirements in ANSI/AWWA C213 or at the option of the Contractor, cleaned, primed, and coated in accordance with specifications of ANSI/AWWA C214.

Pipe wrapping tape

Wrapping tapes for pipe in contact with the ground shall be a pressure sensitive polyvinyl chloride or polyethylene tape having thickness of 1.27 mm, minimum.

All steel cover platesshall be suitable for the type and size of the welded steel pipe casing and conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

Concrete pipe supports and pipe stops shall conform to the dimensions shown on the plans and shall be constructed of commercial quality concrete not less than 325 kg of portland cement per cubic meter, commercial quality wire mesh and reinforcement. The concrete pipe supports and pipe stops shall be moist cured for not less than 3 days.

CONSTRUCTION

If a blockout is provided in the bridge abutment wall for casing pipe, the space between the casing pipe and bridge abutment wall shall be filled with portland cement mortar conforming to the provisions in Section 51-1.135, "Mortar," of the Standard Specifications.

Openings for utilities through bridge superstructure concrete shall either be formed or shall consist of pipe sleeves.

Wrapping and coating pipe

Damaged coating on steel pipe casing in contact with earth shall be wrapped as follows:

A. Pipe to be wrapped shall be thoroughly cleaned and primed as recommended by the tape manufacturer.
B. Tapes shall be tightly applied with 1/2 uniform lap, free from wrinkles and voids to provide not less than 2.5 mm thickness.
C. Field joints and fittings for wrapped pipe shall be covered by double wrapping 1.27 mm thick tape. Wrapping at joints shall extend a minimum of 150 mm over adjacent pipe coverings. Width of tape for wrapping fittings shall not exceed 50 mm. Adequate tension shall be applied so tape will conform closely to contours of joint.

Where a welded steel pipe casing passes through the abutment wall, the welded steel pipe casing shall be additionally wrapped with 2 layers of No. 15 asphalt-felt building paper, securely taped or wired in place.

MEASUREMENT AND PAYMENT

Measurement and payment for welded steel pipe casing for each size listed in the Engineers Estimate shall conform to the provisions in Sections 70-1.04, "Measurement," and 70-1.05, "Payment," of the Standard Specifications.

Full compensation for furnishing and installing steel cover plates, mortar and building paper, wrapping and coating , shall be considered as included in the contract prices paid per meter for the sizes of welded steel pipe casing involved and no additional compensation will be allowed therefor.

10-1.83 AUTOMATIC DRAINAGE GATE

Automatic drainage gates shall conform to the provisions in Section 70, "Miscellaneous Facilities," of the Standard Specifications and these special provisions.

The gates shall be designed to operate under 3 m of head face pressure measured from the center of the gate cover to the highest water level. The gate shall provide a free outflow, but shall prevent backflow. The gate shall be attached to the required pipe size or anchored to a concrete wall.

The gate shall be complete with cover, spigot-back seat, gate links, bushings, bolts, and nuts.

The gate cover and spigot-back seat shall be manufactured of cast iron conforming to the requirements in ASTM Designation: A 126, Class B. The gate links shall be manufactured of steel conforming to the requirements in ASTM Designation: A 36/A 36M. The bushings shall be manufactured of commercial quality bronze. The assembly bolts, or anchor bolts when required, and nuts shall conform to the requirements in ASTM Designation: A 307, Grade A. The gate links, bolts, and nuts shall be galvanized in conformance with the requirements in ASTM Designation: A 153.

The gate cover shall be ribbed or domed and of ample section to withstand the face pressure. The seating surfaces of the cover and spigot-back seat shall be machined or ground to fit together within a tolerance of not more than 0.10-mm throughout the circumference of the seating surfaces.

The gate cover shall be hinged from the spigot-back seat by 2 supporting links, one on each side of the gate, pivotally connected at the top of the seat and at the bottom to the cover above the center of gravity. Bushings of suitable length and diameter shall be provided at the 4 hinge points.

The gate shall be assembled in the shop and cast iron parts shall be given a shop coat of commercial quality asphaltic paint furnished by the manufacturer.

The cover of the gate, when installed, shall fit tight against the seat when there is no pressure on the cover face.

The cover shall be equipped with an eye bolt at the bottom for opening the gate under pressure.

10-1.84 PVC WATERLINE

PVC waterline shall conform to the provisions in Section 64, "Plastic Pipe," of the Standard Specifications and these special provisions.

PVC waterline shall be polyvinyl chloride (PVC) with smooth interior and exterior walls.

Service interruption of waterline shall be limited to four (4) weeks.

GENERAL

Waterline shall be tested for pressure and leakage prior to acceptance by Engineer.

Testing of water line shall be in accordance with AWWA Standards. The Contractor shall notify the Engineer no less than twenty-four (24) hours in advance of the actual time of testing so that the Engineer may observe the procedure.

PRESSURE TESTING

Pressure testing for leakage shall conform to Section 20.503H, “Pressure Testing,” of the Standard Specifications.

MEASUREMENT AND PAYMENT

The contract price paid per meter for PVC waterline shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing PVC waterline, complete in place, including structure excavation and structure backfill, connecting to new or existing water facilities, and pressure testing, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.85 REINFORCED CONCRETE PIPE CASING

Reinforced concrete pipe casing shall conform to reinforced concrete pipe as per the provisions in Section 65, "Reinforced Concrete Pipe," of the Standard Specifications.

10-1.86 VITRIFIED CLAY PIPE

This section includes specifications for furnishing, installing, and testing the sanitary sewer system as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

Trenching, bedding, and backfilling for pipelines are specified in "Earthwork," of these special provisions.

MATERIALS

Pipe shall be vitrified clay pipe, ASTM C700, extra strength. Joints and gaskets shall be flexible compression joints and couplings conforming to ASTM C425.

LAYING PIPE

Trenches shall be excavated at each joint, if necessary, to provide full length barrel support of the pipe and to prevent point loading at the bells or couplings.

Fill material or trench subgrade beneath the pipe shall be graded and shaped to provide a uniform and continuous support beneath the pipe at all points between the bell holes or pipe joints.

Unless directed by the Engineer, all pipe shall be laid straight between changes in grade.

At all times groundwater and surface runoff shall be controlled to maintain the trench in a stable condition during construction. At the time of laying pipe, the prepared trench shall be in a firm and dry condition. If the trench is not in such condition, the Contractor shall furnish and operate such pumps or other devices as may be necessary for removing ground water from trenches during the construction of the pipeline system.

When ordered by the Engineer, a filter fabric of pervious material or permeable material shall be placed in accordance to the dimensions shown on the plans or to a depth ordered by the Engineer. If the filter blanket is ordered by the Engineer, it will be paid for as extra work as provided in Section 4-1.03D, “Extra Work,” of the Standard Specifications.

Pervious backfill material

Sieve analysis of mineral aggregate to be used as pervious will be tested in accordance with California Test 202. That portion of pervious back fill material passing the No. 4 sieve shall have a sand equivalent of not less than 60, as determined in accordance with California Test 217.

Permeable backfill material

Minimum durability index shall be 40, when tested in accordance with California Test No. 229 Minimum San Equivalent of permeable materials shall be 75 when tested in accordance with California Test 217. Original has no test value.

Pipe will be inspected in the field before and after laying. If any cause for rejection is discovered in a pipe after it has been laid, it shall be subject to rejection. All corrective work shall be approved by the Engineer and shall be at no cost to the State.

When connections are to be made to any existing pipe, conduit, or other appurtenances, the actual elevation or position of which cannot be determined without excavation, the Contractor shall excavate for, and expose, the existing improvement before laying any pipe. The Engineer shall be given the opportunity to inspect the existing pipe before connection is made. Any adjustments in line or grade which may be necessary to accomplish the intent of the plans shall be made, and the Contractor will be paid for any additional work resulting from such change in line or grade as extra work as provided in Section 4-1.03D, “Extra Work,” of the Standard Specifications.

FIELD JOINING OF PIPE

Pipe joints shall be handled and assembled in accordance with the following general requirements:

Care shall be taken to avoid dragging the spigot on the ground or allowing it to be damaged by contact with gravel, crushed stone or other hard objects, Joining of pipe sections shall be in accordance with manufacturer’s or industry recommendations for the type of joints used and specified herein. All joints shall be so formed that when the pipe sections are drawn together the system shall be continuous, uniform, and watertight.

JOINTS

Vitrified clay pipe shall be joined as herein specified with either premolded resilient compression joints or compression couplings.

Resilient Compression Joints

The mating components of premolded resilient compression joints shall be wiped clean of dirt and other foreign matter, and the surfaces coated with an approved lubricant. The spigot end of the pipe to be installed shall be positioned in the bell end of the pipe previously laid and shoved home. For large diameter pipe, a lever attachment or bar cushioned by a wooden

block shall be used to mate the pipes. In no case shall a bar be used on the unprotected bell of the pipe. The mating of surfaces of the pipes shall be in tight contact with each other upon completion of the joining installation.

Compression Couplings

Pipe shall be delivered to the job site with the sleeve attached to one end of each pipe section. The spigot end of the pipe to be joined shall be inserted in the sleeve and the steel compression banc shall be tightened immediately.

TEMPORARY DIVERSION SYSTEM

Existing sanitary sewer lines shall remain live by providing a diversion system until the permanent system is constructed and functional.

TESTS

This work shall consist of testing sewers for leakage, and for furnishing all necessary materials and equipment required as specified in these special provisions, and as directed by the Engineer.

The air pressure test shall be the referee method used to determine watertight integrity of all sewers. The hydrostatic leakage test method will only be used when specifically ordered by the Engineer in writing.

Leakage test shall be performed on the entire sewer main installed, with the length of each test section limited to the pipe segment between manholes.

Prior to performing leakage test for acceptance, the sewer system installation shall be completed (laid, backfilled, and compacted) and cleaned. Cleaning of the sewer system shall be performed after the pipeline has been installed and the trench backfill has been completed. The Contractor shall flush and clean the sewer main to be free of debris.

Air pressure test shall be in accordance with APWA Section 306-1.4.4, "Air Pressure Test."

When the hydrostatic leakage test, in lieu of air test, is ordered by the Engineer, the Contractor shall furnish all water, material and labor necessary to make the test. All testing shall be done in the presence of the Engineer and accordance with the procedures as specified herein.

Each section of the sewer main to be tested shall be sealed by inserting stoppers in the lower end of the sewer segment, the inlet of the pipe of the upper manhole, and any side sewers at intervening manholes. The pipe and upstream manhole shall be filled with water to a point not less than 5 feet above the invert of the pipe or prevailing ground water elevation, which ever is higher. The line segment shall be filled approximately 4 hours prior to testing. The line shall be tested for at least two hours, maintained the head specified above by measured additions of water. The sum of the additions of water added shall be the amount of leakage for the test period. When the amount of leakage, in a section tested, exceeds the maximum allowable, the Contractor shall locate the source of the leak or leaks and correct such leaks to the satisfaction of the Engineer. After the leak or leaks have been corrected, and the trench backfilled and compacted, the section of line shall than be retested to compliance.

The maximum allowable leakage tolerance for sewers is 500 gallons per inch diameter per mile of pipe per day, (0.066 gallons per minute per inch diameter per 1000 feet of pipe).

TELEVISION INSPECTION

After all testing specified in this section has been satisfactorily completed, the entire tested sewer shall be given a television inspection.

The Contractor shall inspect internal sanitary sewer mains by color television camera and the inspection shall be recorded in magnetic medium, as specified hereinafter.

Television inspection shall be performed before and after installation of the sewer. Cleaning of the existing sanitary sewer shall be performed prior to the television inspection by a separate operation.

The inspection shall be recorded in true color in Beta Max II or VHS ("SP") Cassette format with on-screen footage readout on the lower part of the screen.

A written log in City of San Jose Standard Television Inspection format (available from the Engineer) shall accompany the recorded cassette. Including the following information shall accompany the recorded cassette:

1. Date
2. Tape Number
3. Location
4. Pipe Material and Size
5. Name of Equipment Operator
6. Name of Firm Performing the Inspection
7. All deficiencies in the sewer installation shall be noted and their location referenced to their on-screen footage readout

The recorded cassette and accompanying report shall be delivered to the Engineer not later than 24 hours after completion of the inspection. The cassette and report shall become the property of the State. The Engineer will review the recorded television inspection and will notify the contractor whether:

1. The review revealed a satisfactory installation, or
2. The review revealed deficiencies

The Contractor may review the recorded television inspection by requesting and arranging the review with the Engineer.

The following deficiencies in sanitary sewer liner installation shall be corrected by the Contractor at no cost to the State:

1. Joint separation (if applicable)
2. Offset joints (if applicable)
3. Infiltration points
4. Debris in the line

The State will not accept a credit, maintenance bond, or any other form of compensation in lieu of corrective measures that may be required to correct any sections of sewer that are improperly installed or do not meet the requirements of these specifications. In addition, should repairs of the sewers be accomplished by the use of any unauthorized materials or procedure, the Engineer will require replacement of those substandard portions or repairs made to conform to the requirements of these special provisions.

Upon completion of repairs the sewer main shall be TV inspected and the recorded TV inspection will be reviewed by the engineer. This process shall be repeated until the review of the recorded television inspection reveals a satisfactory installation.

MEASUREMENT AND PAYMENT

The contract price paid per meter for vitrified clay pipe shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing sanitary sewer pipe and laterals, complete in place, including structure excavation and structure backfill, bedding material, connecting to new or existing sewer facilities, concrete collars, diverting the sanitary sewer temporarily, testing including television inspection, and pavement removal and replacement, as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

10-1.87 SLOPE PROTECTION

Slope protection shall be placed or constructed in conformance with the provisions in Section 72, "Slope Protection," of the Standard Specifications and these special provisions.

Concrete (gutter lining) shall conform to the provisions in Section 72, "Slope Protection," of the Standard Specifications.

Welded wire fabric shall conform to Section 52, "Reinforcement," of the Standard Specifications.

Full compensation for welded wire fabric in concrete (gutter lining) shall be considered as included in the contract price paid per cubic meter for concrete (gutter lining) and no separate payment allowed therefor.

Rock slope protection fabric shall be woven or nonwoven type fabric, Type A or Type B, at the option of the Contractor.

10-1.88 SLOPE PAVING

Slopes under the ends of bridges, where shown on the plans, shall be paved in conformance with the provisions in Section 72-6, "Slope Paving," of the Standard Specifications and these special provisions.

Concrete for curbs at slope paving locations will be paid for at the contract price per cubic meter for slope paving (concrete).

Areas of slope paving shown on the plans to have an exposed aggregate finish shall be constructed and finished in conformance with the following requirements.

A. Slope paving shall match the slope paving on the existing bridges being widened of this project.
B. Coarse aggregate shall conform to the provisions for 25-mm x 4.75-mm primary size coarse aggregate in Section 90-3.02, "Coarse Aggregate Grading," of the Standard Specifications.
C. Shotcrete shall not be used for the construction of exposed aggregate concrete.
D. Coarse aggregates shall be exposed to a depth of approximately 5 mm to 10 mm. Exposed aggregate surfaces shall be uniform in appearance.
E. At the option of the Contractor, a concrete set retarder may be applied to the surface of the concrete after placing, consolidating, and finishing of the concrete has been completed. The concrete set retarder shall be commercial

quality, manufactured specifically for use on the top surface of concrete and shall be applied in accordance with the manufacturer's recommendations. The retarder shall effectively retard the setting time of the cement and fine aggregate matrix deep enough and long enough to permit exposing the aggregates.

F. Care shall be taken in placing and consolidating the concrete such that the coarse aggregate remains uniformly distributed throughout the concrete.

G. When the mass of the concrete has set sufficiently to permit removing the matrix of cement and fine aggregate, the coarse aggregate shall be exposed with a water spray, coarse brooming, abrasive blasting, or a combination of these procedures. Removal methods shall not dislodge or loosen the coarse aggregate from embedment in the cement mortar.

H. Immediately after the cement mortar has hardened sufficiently to resist further removal, all cement film and other loose material shall be cleaned from the exposed aggregate and all other surfaces with stiff brooms and water.

I. Except when operations for exposing the aggregate are underway, concrete shall be cured by the water method or with Type (6) curing compound in conformance with the provisions in Section 90-7.01B, "Curing Compound Method," of the Standard Specifications. Areas of concrete where curing compounds are removed during the cure period shall be kept continuously wet until the end of the cure period or until the curing compound is replaced.

The location of construction joints shall be subject to the approval of the Engineer. Placement of slope paving shall be scheduled so that the work, including placement, finishing, and application of curing, is completed in any section bounded by permissible construction joints on the same day that the work is started in that section.

Areas of slope paving shown on the plans to have a grooved finish shall be scored by dragging a finishing tool over the struck-off surface or by any other means which will result in a surface conforming to the details shown on the plans.

Prior to placing the permanent slope paving, the Contractor shall construct a test panel at least 1.2 m by 1.8 m at the site for approval by the Engineer. The test panel shall be constructed of the same materials as are proposed for the permanent work and shall be finished and cured as specified for the permanent work. Additional test panels shall be constructed as necessary until a panel is produced which conforms to the requirements herein, before constructing other slope paving.

Precast Slope Paving Panel

Precast slope paving panel consisting of reinforced precast concrete panels and anchor dowels, shall conform to the details shown on the plans, the provisions in Sections 19, "Earthwork," 51, "Concrete Structures," 52, "Reinforcement," 75, "Miscellaneous Metal," and 90, "Portland Cement Concrete," of the Standard Specifications, and these special provisions.

Precast slope paving panel shall be laid and embedded in approximately 100 mm thick sand. The panels shall be shoved tight so that the faces are flush and the joints are locked.

Precast slope paving panel and architectural arrangement shall match the existing precast slope paving panels.

Sand bedding shall be free from clay or organic material, suitable for the purpose intended, and shall be of such size that 90 percent to 100 percent will pass a 4.75-mm sieve and not more than 5 percent will pass a 75-□m sieve.

Anchor dowels shall be unthreaded galvanized steel rods placed in holes in the precast slope paving panels. Anchor dowels to be placed in holes shall conform to the provisions for " Section 75: Miscellaneous Metal" of the Standard Specifications.

The precast concrete panels shall be cured in conformance with the provisions in Section 90-7.04, "Curing Precast Concrete Members," of the Standard Specifications or, at the option of the Contractor, the precast concrete panels may be cured with a curing compound conforming to the requirements in ASTM Designation: C 309 Type 1, Class B.

The cast side (down) of the precast panels shall be formed using a formliner with a texture of smooth and patterned surface to match the existing panels. The formliner shall be installed so that no form joints show in the finished surface.

The Contractor shall construct a test panel, demonstrating the construction procedure that will be used to obtain the final finish and color that complies with the plans and specifications, as determined by the Engineer. If so ordered by the Engineer, additional test panels shall be constructed and finished until a satisfactory finish, on each side of the panel, and color is obtained. The test panel approved by the Engineer shall then be the standard of comparison for the remaining panels.

The contract price paid per cubic meter for slope paving (precast panel) shall include full compensation for furnishing all labor, materials (including formliner, bar reinforcing steel, reinforcing steel anchors, welded wire fabric, precast panel, sand bedding, gravel backfill, anchor dowels, and timber spacers), tools, equipment and incidentals, and for doing all the work involved in constructing the slope paving, complete in place (including excavation, backfill, concrete curb and installing timber spacers, precast panels and anchor dowels), as shown on the plans, as specified in the specifications and these special provisions, and as directed by the Engineer

10-1.89 MINOR CONCRETE (GUTTER)

The gutter behind the retaining walls shall conform to the provisions in Section 73, "Concrete Curbs and Sidewalks," of the Standard Specifications and these special provisions.

Minor concrete (gutter) will be measured and paid for by the meter.

The contract price paid per meter for minor concrete (gutter) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the gutter, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.90 MISCELLANEOUS CONCRETE CONSTRUCTION

Curbs, sidewalks, driveways, gutter depressions, median paving, driveway, and modified depression aprons shall conform to the provisions in Section 73, "Concrete Curbs and Sidewalks," of the Standard Specifications and these special provisions.

Welded wire fabric, of the size and type shown on the plans and conforming to the provisions in Section 52, "Reinforcement," of the Standard Specifications, shall be placed in the concrete gutter depressions, and modified depression apron as shown on the plans.

Full compensation for welded wire fabric, shall be considered as included in the contract price paid per cubic meter for minor concrete (miscellaneous construction) and no separate payment will be made therefor.

10-1.91 MINOR CONCRETE (BACKFILL)

Concrete backfill for encasement of electrical, water, and telephone conduits shall conform to the provisions in Section 66-1.045, "Concrete Backfill," of the Standard Specifications and will be measured and paid for in conformance with the provisions in Section 66-4, "Measurement and Payment," of the Standard Specifications and these special provisions.

The quantity of concrete backfill to be paid for will be based on the dimensions shown on the plans and the installation of conduits.

MEASUREMENT AND PAYMENT

The contract price paid per cubic meter for minor concrete (backfill), shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing concrete backfill for conduits, as shown on the plans, as specified in the contract documents and the Standard Specifications, and as directed by the Engineer.

10-1.92 MISCELLANEOUS IRON AND STEEL

Miscellaneous iron and steel shall conform to the provisions in Section 75, "Miscellaneous Metal," of the Standard Specification.

10-1.93 MISCELLANEOUS METAL (BRIDGE)

Miscellaneous metal (bridge) shall conform to the provisions for miscellaneous bridge metal in Section 75, "Miscellaneous Metal," of the Standard Specifications and these special provisions.

Miscellaneous metal (bridge) shall consist of the miscellaneous bridge metal items listed in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications, and the following:

A. Soffit access opening covers
B. Deck drains

Deck drains shall be installed in the existing concrete deck by completely filling the entire void between the drain and the cored hole with grout within the limits shown on the plans. Grout shall conform to the provisions in Section 50-1.09, “Bonding and Grouting,” of the Standard Specifications. Filler material and seals shall be provided along the sides of the pipe to be grouted, to prevent grout from leaving the cored hole.

Full compensation for coring and grouting deck drains in place shall be considered as included in the contract price paid per kilogram for miscellaneous metal (bridge) and no additional compensation will be allowed therefor.

Self-tapping screws used for sleeve connections shall be hex-head stainless steel, installed in holes drilled to fit the self-tapping screws, conforming to the requirements of ASTM Designation: A 276, Type 304.

10-1.94 MISCELLANEOUS METAL (RESTRAINER-PIPE TYPE)

Miscellaneous metal (restrainer-pipe type) shall consist of bridge joint pipe restrainers with double extra strong steel pipe and associated hardware as shown on the plans and in conformance with the provisions in Section 75-1.035, "Bridge Joint Restrainer Units," of the Standard Specifications and in these special provisions.

The Contractor shall submit working drawings with the method of grouting the pipe restrainers in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications.

Double extra strong steel pipe shall conform to the requirements of:

Bridge	Designation
Almaden Road Undercrossing (Widen)	API X52 (F_y =52 ksi)

Pipe restrainers shall be filled with grout within the limits shown on the plans. Grout shall conform to the provisions in Section 50-1.09, "Bonding and Grouting," of the Standard Specifications. .

Miscellaneous metal (restrainer-pipe type) will be measured and paid for by the kilogram in the same manner specified for miscellaneous metal (restrainer) in Sections 75-1.06, "Measurement," and 75-1.07, "Payment," of the Standard Specifications.

Full compensation for filling pipe restrainers with grout shall be considered as included in the contract price paid per kilogram for miscellaneous metal (restrainer-pipe type) and no additional compensation will be allowed therefor.

10-1.95 MISCELLANEOUS METAL (RESTRAINER-BAR TYPE)

Miscellaneous metal (restrainer-bar type) units consisting of high strength bars, bearing plates, couplers, anchorage devices, and incidentals shall conform to the details shown on the plans and the provisions in Section 75-1.035, "Bridge Joint Restrainer Units," of the Standard Specifications and in these special provisions.

Bar assemblies shall conform to the materials and sampling provisions for prestressing steel in Section 50, "Prestressing Concrete," of the Standard Specifications and the following:

A. The high strength bars shall conform to the requirements of ASTM Designation: A 722, including all supplementary requirements.
B. All new metal surfaces of restrainer-bar type units shall be cleaned and painted in conformance with the provisions in Sections 59-2, "Painting Structural Steel," and 91, "Paint," of the Standard Specifications, and "Clean and Paint Structural Steel" of these special provisions.
C. Anchorage devices and couplers, conforming to the requirements specified herein, shall be of a type selected by the Contractor and shall include locking devices to prevent turning or loosening.
D. The anchorage device and coupler shall develop the specified minimum ultimate tensile strength of the steel bar.
E. The Contractor shall be responsible for determining the required lengths of the bar assemblies.
F. The bar assemblies shall be shipped as a complete unit including anchorage device and coupler.

Bearing plates shall conform to the requirements of ASTM Designation: A 36/A 36M.

New concrete adjacent to restrainers shall be placed prior to installing restrainers.

Elastomeric pads shall be bonded to bearing plates with adhesive conforming to the requirements in Federal Specification MMM-A-121.

Miscellaneous metal (restrainer-bar type) will be measured and paid for by the kilogram in the same manner specified for miscellaneous metal (restrainer) in Sections 75-1.06, "Measurement," and 75-1.07, "Payment," of the Standard Specifications.

Certification in conformance with the requirements in SSPC-QP 1, SSPC-QP 2, and SSPC-QP 3 of the "SSPC: The Society for Protective Coatings" will not be required for restrainer-bar type units.

Full compensation for cleaning and painting of bar type restrainer units shall be considered as included in the contract price paid per kilogram for miscellaneous metal (restrainer-bar type) and no additional compensation will be allowed therefor.

10-1.96 CHAIN LINK FENCE

Chain link fence shall be Type (CL-1.2, Vinyl-clad), (CL-1.2, Barrier Mounted), (CL-1.5, Vinyl-clad), and (CL-1.8) and shall conform to the provisions in Section 80, "Fences," of the Standard Specifications.

Chain link fabric for Vinyl-clad shall be vinyl coated as specified in Section 83-1.02I, "Chain Link Railing," of the Standard Specifications. The color shall be black.

All posts, braces, fittings, tension wires, tie wires, post clips and appurtenances for Vinyl-clad shall be vinyl coated as specified for fabric.

Where necessary to conform to curvature, either horizontal or vertical, the fabric shall be reworked and fitted so as to present a smooth, neat, and workmanlike appearance.

Where applicable, the space between the end of sound wall and the chain link fence shall be no greater than 100 mm.

Where shown chain link fence shall be installed in concrete barrier as shown on the plans.

10-1.97 CHAIN LINK WALK GATE

Chain link walk gates shall be Type CL-1.8 conforming to the provisions in Section 80, "Fences," of the Standard Specifications and these special provisions.

Gates shall be installed in existing fences at the locations shown on the plans. Gate installations shall be complete with gate post, latch post, concrete footings, braces, truss rods, and hardware. Gate and latch posts shall be braced to the next existing line post as shown on the plans.

At each gate location, an existing line post shall be removed and the new gate installed so that the gate is centered on the post hole of the removed post. Holes resulting from the removal of line posts shall be backfilled.

Gate mounting and latching hardware shall not contain open-end slots for the fastening bolts.

Chain link fabric for gates shall be of the same mesh size as the existing fence in which the gates are installed.

Openings made in existing fences for installation of gates shall be closed during the working day in which the openings are made and when work is not in progress. Temporary closures shall be made with the existing fence fabric or with additional 1.83-m chain link fabric as directed by the Engineer.

Full compensation for making the openings in existing fences, for temporary closing of the openings (including furnishing additional fence fabric if necessary), and for new posts, footings, hardware, braces, and truss rods shall be considered as included in the contract unit price paid for the various sizes of chain link gate (Type CL-1.8) involved and no additional compensation will be allowed therefor.

10-1.98 SECURITY FENCE AND GATE

Security fence and gate, as shown on the plans, shall conform to the provisions in Section 80, "Fences," of the Standard Specifications and these special provisions.

Fence post, rails and pickets shall be galvanized steel.

Painting shall match color of existing fence and shall conform to Section 86-2.16, “Painting,” of the Standard Specifications.

Contractor shall conform to the provisions in Section 55-3.17, “Welding,” of the Standard Specifications.

Gates shall be installed at the locations shown on the plans. Gate installations shall be complete with gate post, concrete footing, dead lock, and hardware.

The contract price paid per meter for the security fence, shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing security fence complete in place, including welding, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract unit price paid for security gate, shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing security gate complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.99 MARKERS

Markers shall conform to the provisions in Section 82, "Markers and Delineators," of the Standard Specifications and these special provisions.

Markers on flexible posts shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Flexible posts shall be made from a flexible white plastic which shall be resistant to impact, ultraviolet light, ozone, and hydrocarbons. Flexible posts shall resist stiffening with age and shall be free of burns, discoloration, contamination, and other objectionable marks or defects which affect appearance or serviceability.

Retroreflective sheeting for metal and flexible target plates shall be the retroreflective sheeting designated for channelizers, and markersconforming to the requirements in ASTM Designation: D 4956-95 and in conformance with the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

10-1.100 METAL BEAM GUARD RAILING

Metal beam guard railing shall be constructed in conformance with the provisions in Section 83-1, "Railings," of the Standard Specifications and these special provisions.

Attention is directed to "Order of Work" of these special provisions.

Line posts and blocks shall be wood.

Full compensation for guard railing delineator shall be considered as included in the contract price paid per meter for metal beam guard railing and no separate payment allowed therefor.

TERMINAL SYSTEM (TYPE SRT)

Terminal system (Type SRT) shall be furnished and installed as shown on the plans and in conformance with these special provisions.

Terminal system (Type SRT) shall be a SRT-350 Slotted Rail Terminal (8 post system) as manufactured by Trinity Industries, Inc., and shall include all the items detailed for terminal system (Type SRT) shown on the plans.

The 5 mm x 44 mm x 75 mm plate washer shown on the elevation view and in Section D-D at Wood Post No. 1 shall be omitted.

Arrangements have been made to insure that any successful bidder can obtain the SRT-350 Slotted Rail Terminal (8 post system) from the manufacturer, Trinity Industries, Inc., P.O. Box 99, 950 West 400S, Centerville, UT 84014, Telephone 1-800-772-7976. The price quoted by the manufacturer for the SRT-350 Slotted Rail Terminal (8 post system), FOB Centerville, Utah is $895.00 , not including sales tax.

The above price will be firm for orders placed on or before July 29, 2005, provided delivery is accepted within 90 days after the order is placed.

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall certify that terminal systems (Type SRT) conform to the contract plans and specifications, conform to the prequalified design and material requirements and were manufactured in conformance with the approved quality control program.

The terminal system (Type SRT) shall be installed in conformance with the manufacturer's installation instructions and these requirements. The steel foundation tubes with soil plates attached, shall be, at the Contractor's option, either driven, with or without pilot holes, or placed in drilled holes. Space around the steel foundation tubes shall be backfilled with selected earth, free of rock, placed in layers approximately 100 mm thick and each layer shall be moistened and thoroughly compacted. Wood terminal posts shall be inserted into the steel foundation tubes by hand. Before the wood terminal posts are inserted, the inside surfaces of the steel foundation tubes to receive the wood posts shall be coated with a grease which will not melt or run at a temperature of 65°C or less. The edges of the wood terminal posts may be slightly rounded to facilitate insertion of the post into the steel foundation tubes.

Surplus excavated material remaining after the terminal system (Type SRT) has been constructed shall be disposed of in a uniform manner along the adjacent roadway where designated by the Engineer.

A Type L object marker shall be placed at the approach end of the terminal system (Type SRT).

10-1.101 CHAIN LINK RAILING

Chain link railing shall conform to the provisions in Section 83-l, "Railings," of the Standard Specifications and these special provisions.

The chain link fabric shall be 9-gage (3.76 mm), Type IV, Class B, bonded vinyl coated fabric, conforming to the requirements in AASHTO Designation: M 181.

The strength of the bond between the coating material and steel of the bonded vinyl coated chain link fabric shall be equal to or greater than the cohesive strength of the polyvinyl chloride (PVC) coating material.

Chain link vinyl coated fabric color shall be black.

All posts, braces, fittings, tension wires, tie wires, post clips and appurtenances shall be vinyl coated as specified for fabric.

10-1.102 CONCRETE BARRIER

Concrete barriers shall conform to the provisions in Section 83-2, "Barriers," of the Standard Specifications and these special provisions.

If reinforcement is encountered during drilling before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole to the depth shown on the plans.

Concrete barriers shall be constructed on a layer of Asphalt Concrete (Type A) as shown on the plans. Asphalt concrete shall conform to the provisions in " Asphalt Concrete" of these special provisions. When concrete barriers are to be constructed on asphalt concrete, the height of the barriers shall be adjusted to compensate for irregularities in the surface of the finished asphalt concrete. The amount of adjustment will be determined by the Engineer and will be ordered before the concrete is placed.

The provisions of the third paragraph in Section 83-2.02D(4), "Finishing," of the Standard Specifications shall not apply.

Concrete barrier markers shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. At those locations shown on the plans, concrete barrier markers shall be cemented to the barrier in conformance with the manufacturer's recommendations.

The Contractor's attention is directed to the provisions in paragraph 4 of Section 83-2.01, "Description," of the Standard Specifications regarding closure of any gap between the reinstalled barrier and the barrier being installed. Barrier or railing placed to close the gap in accordance with these provisions will not be measured and paid for.

Concrete barrier transitions shall be measured and paid for as the various types of concrete barrier shown on the plans.

Full compensation for concrete barrier marker shall be considered as included in the contract price paid per meter of concrete barrier and no additional compensation will be allowed therefore.

10-1.103 CRASH CUSHION (ADIEM)

Crash cushion shall be furnished and installed as shown on the plans and in conformance with the provisions in the Standard Specifications and these special provisions.

Crash cushion shall be an ADIEM II-350 as manufactured by Trinity Industries, Inc., and shall include the items detailed for crash cushion shown on the plans.

The successful bidder can obtain the crash cushion from the manufacturer, Trinity Industries, Inc., P.O. Box 99, 950 West 400S, Centerville, Utah 84014, telephone 1-800-772-7976.

The price quoted by the manufacturer for ADIEM II-350, FOB Centerville, Utah is $11,500.00 , not including sales tax.

The above price will be firm for orders placed on or before July 29, 2005, provided delivery is accepted within 90 days after the order is placed.

The Contractor shall furnish the Engineer one copy of the manufacturer's plan and parts list.

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall certify that the crash cushion conforms to the contract plans and specifications, conforms to the prequalified design and material requirements, and was manufactured in conformance with the approved quality control program.

Crash cushion shall be installed in conformance with the manufacturer's installation instructions.

Surplus excavated material remaining after the crash cushion has been installed shall be disposed of in a uniform manner along the adjacent roadway where designated by the Engineer.

Crash cushion (ADIEM) will be measured by the unit as determined from actual count in place in the completed work.

The contract unit price paid for crash cushion (ADIEM) shall include full compensation for furnishing all labor, materials (including anchor bolts, nuts, washers, and marker panels), tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing the ADIEM type crash cushion, complete in place, including structure excavation, structure backfill, and disposing of surplus material, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.104 CRASH CUSHION (Quadguard)

Crash cushion (Quadguard) shall be furnished and installed as shown on the plans and in conformance with the provisions in the Standard Specifications and these special provisions.

The successful bidder can obtain the crash cushion from the following sources:

1. Southern California: Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, California 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.
2. Northern California: Traffic Control Service, Inc., 8585 Thys Court, Sacramento, California 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734.

The price quoted by the manufacturer for Crash Cushion (Quadguard), FOB Pell City, Alabama is $15,292, not including sales tax. This system includes the basic Quadguard system, one (1) transition panel suitable for reverse direction impacts and one (1) set of wheel deflectors.

The above prices will be firm for orders placed within 30 days of contract award, and provided delivery is accepted within 90 days after the order is placed.

The prices quoted do not include the concrete anchor slab.

Crash cushion shall be installed in conformance with the manufacturer's recommendations.

Concrete anchorage devices used for attaching the crash cushion to the base slab shall be limited to those provided by the manufacturer

The concrete anchor slab shall conform to the provisions in Section 51, "Concrete Structures," and Section 52, "Reinforcement," of the Standard Specifications and these special provisions.

The concrete anchor slab shall be constructed of concrete containing not less than 350 kg {590 pounds} of cement per cubic meter {cubic yard}.

.The Contractor shall furnish the Engineer five copies of the manufacturer's plans and instructions in accordance with Section 5-1.02 “Plans and Working Drawings” of the Standard Specifications. Plans and instructions shall be submitted not less than fifteen working days in advance of installation.

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall certify that crash cushion conforms to the contract plans and specifications; conforms to the prequalified design and material requirements, and was manufactured in accordance with a quality control program certified in accordance with the ISO 9000 series of Standards.

Crash cushion will be measured by the unit as determined from actual count in place in the completed work.

The contract unit prices paid for crash cushion (Quadguard) shall include full compensation for furnishing all labor, materials (including anchor bolts, nuts, washers, and marker panels), tools, equipment, and incidentals, and for doing all the work involved in furnishing, installing and removing the crash cushions, complete in place, including structure excavation, structure backfill, bar reinforcing steel, concrete for backup block and anchor slab, transition plate, W-beam connector, and

for furnishing high strength bolts and plate washers, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.105 THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING

Thermoplastic traffic stripes (traffic lines) and pavement markings shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Thermoplastic material shall be free of lead and chromium, and shall conform to the requirements in State Specification PTH-02ALKYD.

Retroreflectivity of the thermoplastic traffic stripes and pavement markings shall conform to the requirements in ASTM Designation: D 6359-99. White thermoplastic traffic stripes and pavement markings shall have a minimum initial retroreflectivity of 250 $mcd \cdot m^{-2} \cdot lx^{-1}$. Yellow thermoplastic traffic stripes and pavement markings shall have a minimum initial retroreflectivity of 150 $mcd \cdot m^{-2} \cdot lx^{-1}$.

Where striping joins existing striping, as shown on the plans, the Contractor shall begin and end the transition from the existing striping pattern into or from the new striping pattern a sufficient distance to ensure continuity of the striping pattern.

Thermoplastic material for traffic stripes shall be applied at a minimum thickness of 2.0 mm.

At the option of the Contractor, permanent traffic striping and pavement marking tape conforming to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be placed instead of the thermoplastic traffic stripes and pavement markings specified herein. Permanent tape, if used, shall be installed in conformance with the manufacturer's specifications.

If permanent tape is placed instead of thermoplastic traffic stripes and pavement markings, the tape will be measured and paid for by the meter as thermoplastic traffic stripe and by the square meter as thermoplastic pavement marking.

10-1.106 PAINT PAVEMENT MARKING

Painted pavement markings shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Traffic stripe and pavement marking paint shall conform to the requirements in State Specification No. PTWB-01.

The color of the painted traffic stripes and pavement markings shall conform to the requirements in ASTM Designation: D 6628-01.

Retroreflectivity of the paint pavement markings shall conform to the requirements in ASTM Designation: D 6359-99. White painted pavement markings shall have a minimum initial retroreflectivity of 250 $mcd \cdot m^{-2} \cdot lx^{-1}$. Yellow painted pavement markings shall have a minimum initial retroreflectivity of 150 $mcd \cdot m^{-2} \cdot lx^{-1}$.

At the option of the Contractor, permanent pavement marking tape conforming to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be placed instead of painted pavement markings. Permanent tape, if used, shall be placed in conformance with the manufacturer's specifications.

If permanent tape is placed instead of painted pavement markings, the tape will be measured and paid for by the square meter as paint pavement marking of the number of coats designated in the Engineer's Estimate.

Post-mile markings shall be painted on concrete barriers in conformance to Section 84-3, “Painted Traffic Stripes and Pavement Markings” of the Standard Specifications and as directed by the Engineer.

10-1.107 PAVEMENT MARKERS

Pavement markers shall be placed in conformance with the provisions in Section 85, "Pavement Markers," of the Standard Specifications and these special provisions.

Attention is directed to "Traffic Control System For Lane Closure" of these special provisions regarding the use of moving lane closures during placement of pavement markers with bituminous adhesive.

The Contractor shall furnish the Engineer certificates of compliance for the pavement markers in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Retroreflective pavement markers shall be marked as abrasion resistant on the body of the markers.

SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS

10-2.01 GENERAL

The work performed in connection with highway planting and irrigation systems shall conform to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications and these special provisions.

The Contractor shall notify the Engineer not less than 72 hours prior to requiring initial access to the existing irrigation controllers. When the Engineer determines that access to the controllers is required at other times, arrangements will be made to provide this access.

When fluctuations of water pressure and water supply are encountered during normal working hours, plants shall be watered at other times, as often, and in sufficient amounts as conditions may require to keep the soil and plant roots moist during the life of the contract.

Full compensation for watering plants outside normal working hours shall be considered as included in the contract lump sum prices paid for maintain existing planted areas and no additional compensation will be allowed therefor.

PROGRESS INSPECTIONS

Progress inspections will be performed by the Engineer for completed highway planting and irrigation system work at designated stages during the life of the contract.

Progress inspections will not relieve the Contractor of responsibility for installation in conformance with the special provisions, plans and Standard Specifications. Work within an area shall not progress beyond each stage until the inspection has been completed, corrective work has been performed, and the work is approved, unless otherwise permitted by the Engineer.

The requirements for progress inspections will not preclude additional inspections of work by the Engineer at other times during the life of the contract.

The Contractor shall notify the Engineer, in writing, at least 4 working days prior to completion of the work for each stage of an area and shall allow a minimum of 3 working days for the inspection.

Progress inspections will be performed at the following stages of work:

A. During pressure testing of the pipelines on the supply side of control valves.
B. During testing of low voltage conductors.
C. After all sprinkler heads to remain have been placed in operation and adjusted to provide full coverage to existing plantings that are to remain.
D. Within 10 working day of completion of contract work.

10-2.02 EXISTING HIGHWAY PLANTING

MAINTAIN EXISTING PLANTED AREAS

Existing planted areas, designated on the plans to be maintained, shall be maintained throughout the life of the contract in conformance with these special provisions.

Attention is directed to "Preservation of Property" of these special provisions.

Existing plants shall be watered in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Existing planted areas to be maintained shall be inspected for deficiencies by the Contractor in the presence of the Engineer. Deficiencies requiring corrective action shall include weeds; dead, diseased, or unhealthy plants; missing plant stakes and tree ties; inadequate plant basins; and other deficiencies needing corrective action to promote healthy plant life. The inspection shall be completed within 10 working days after the start of work.

Deficiencies found during the inspection shall be corrected within 10 working days after the inspection ends. Correction of deficiencies, as directed by the Engineer, will be paid for as extra work in conformance with the provisions in Section 4-1.03D, "Extra Work," of the Standard Specifications.

After deficiencies have been corrected, the Contractor shall perform work to maintain existing planted areas in a neat appearance and to promote healthy plant growth. The work shall include the following:

A. Weeds shall be killed before the weeds reach the seed stage of growth or exceed 150 mm in length.
B. Trash, debris and weeds shall be removed from existing planted areas. Weeds shall be killed prior to removal. Trash, debris and weed removal in ground cover areas shall extend beyond the outer limits of ground cover areas to the adjacent edges of paving, fences and proposed plants and planting areas, and a 2-m diameter area centered at each existing tree and shrub outside of existing ground cover areas.
C. Existing plant basins shall be kept well-formed and free of silt. If existing plant basins require repairs, and the plant basins contain mulch, the mulch shall be replaced after the plant basins have been repaired.
D. When a portion of a new automatic irrigation system is completed, the existing plants to be watered by that portion of the irrigation system shall be watered automatically.
E. Pesticides for maintaining existing planted areas shall conform to the provisions in "Pesticides" of these special provisions.

The contract lump sum price paid for maintain existing planted areas shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in maintain existing planted areas,

complete in place, as shown on the plans, as specified in the standard specifications and these special provisions, and as directed by the Engineer.

10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES

The work performed in connection with the various existing highway irrigation system facilities shall conform to the provisions in "Existing Highway Facilities," of these special provisions.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

LOCATE EXISTING CROSSOVERS AND CONDUITS

Existing crossovers and conduits shown on the plans to be incorporated in the new work shall be located in conformance with the provisions for locating conduits in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

Unless otherwise directed by the Engineer, existing crossovers and conduits shown on the plans to be incorporated in the new work shall be located prior to performing work on irrigation systems.

If debris is encountered in the ends of conduits, the debris shall be removed prior to performing other work in the conduits. Removal of debris within the first one meter in these conduits shall be at the Contractor's expense. If debris is encountered in the conduits more than one meter from the ends of the conduits, the additional debris shall be removed as directed by the Engineer and the removal work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

MEASUREMENT AND PAYMENT

Full compensation for locating existing crossovers and conduits shall be considered as included in the contract unit price for the various items of work involved and no additional compensation will be allowed therefor.

CHECK AND TEST EXISTING IRRIGATION FACILITIES

Existing irrigation facilities that are to remain or to be relocated, and that are within those areas where clearing and grubbing or earthwork operations are to be performed, shall be checked for missing or damaged components and proper operation prior to performing clearing and grubbing or earthwork operations. Existing irrigation facilities outside of work areas that are affected by the construction work shall also be checked for proper operation.

A written list of existing irrigation system deficiencies shall be submitted to the Engineer within 5 working days after checking the existing facilities.

Deficiencies found during checking of the existing facilities shall be corrected as directed by the Engineer. Corrective work ordered by the Engineer will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

When existing irrigation facilities are checked, existing backflow preventers shall be tested for proper operation in conformance with the provisions in Section 20-5.03J, "Check and Test Backflow Preventers," of the Standard Specifications.

Length of watering cycles for use of potable water from water meters for checking or testing existing irrigation facilities shall be as determined by the Engineer.

Additional repairs required for the existing irrigation system as ordered by the Engineer, except as otherwise provided for in "Maintain Existing Irrigation Facilities" of these special provisions, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Full compensation for checking and testing existing irrigation facilities, including testing existing backflow preventers, shall be considered as included in the contract lump sum price for maintain existing irrigation facilities and no additional compensation will be allowed therefor.

MAINTAIN EXISTING IRRIGATION FACILITIES

Existing irrigation facilities shall be maintained throughout the life of the contract. Prior to the start of maintaining existing irrigation facilities work, the facilities shall be checked for proper operation, and repaired in conformance with the provisions in "Check and Test Existing Irrigation Facilities" of these special provisions.

After the existing facilities have been checked and repaired, the Contractor shall be responsible for the routine maintenance of existing irrigation systems. The work shall include, but not limited to, checking irrigation systems for proper operation and adjusting, repairing or replacing valves, valve boxes, sprinklers, risers, swing joints, wye strainers, valve assembly units, and filter assembly units.

The Contractor will not be responsible for maintaining existing water meters, underground pipe supply lines, control and neutral conductors, and electrical conduits. Except as otherwise specified in "Existing Highway Irrigation Facilities" of these

special provisions, repair work to these facilities ordered by the Engineer will be paid for as extra work as provided in Section 4-l.03D, "Extra Work," of the Standard Specifications.

Existing automatic irrigation systems shall be operated automatically during the life of the contract, except manual operation will be allowed for the work during plant replacement, fertilization, weed germination, and the repair of irrigation facilities.

Irrigation controllers shall be programmed by the Contractor for seasonal water requirements. During winter seasons irrigation systems shall be operated automatically a minimum of 2 minutes every 2 weeks.

Irrigation systems and facilities shall be checked for proper operation at least once every 30 days. When required, as determined by the Engineer, adjusting, repairing or replacing irrigation facilities shall be completed within 5 working days after checking the irrigation systems. Except as provided in these special provisions, repair and replacement of irrigation facilities shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Except as provided in these special provisions, the contract lump sum price paid for maintain existing irrigation facilities shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in maintaining existing irrigation facilities, complete in place, including checking irrigation facilities, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

REMOVE EXISTING IRRIGATION FACILITIES

Existing irrigation facilities where shown on the plans to be removed, shall be removed. Facilities that are more than 150 mm below finished grade, excluding facilities to be salvaged, may be abandoned in place.

Attention is directed to “Hazardous, Restricted and Non-Hazardous Material, General,” and “Naturally Occurring Asbestos Material-General,” elsewhere in these special provisions.

Immediately after disconnecting an existing irrigation facility to be removed or abandoned from an existing facility to remain, the remaining facility shall be capped or plugged, or shall be connected to a new or existing irrigation facility.

Existing sprinklers, where shown on the plans to be removed, shall be salvaged.

The Engineer shall be given written notification of the intent to salvage existing irrigation facilities a minimum of 72 hours prior to salvaging these facilities.

Salvaged irrigation facilities shall remain the property of the State and shall be delivered to 500 Queens Lane , San Jose, CA, 95035, 408-452-7129.

A list of salvaged facilities, including the quantity and size of each item salvaged, shall be included with each delivery.

Facilities to be removed, excluding facilities to be salvaged, shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The contract lump sum price paid for remove existing irrigation facilities shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in removing existing irrigation facilities, complete in place, including removing and disposing, backfilling, abandoning and disconnecting controller lines and capping irrigation lines, and salvaging existing sprinklers as shown on the plans, as specified in the contract documents and the Standard Specifications, and as directed by the Engineer.

PESTICIDES

Pesticides used to control weeds shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specifications. Except as otherwise provided in these special provisions, pesticide use shall be limited to the following materials:

Diquat
Diquat Glyphosate Isoxaben (Preemergent)
Oryzalin (Preemergent)
Pendimethalin (Preemergent)
Trifluralin (Preemergent)

Glyphosate shall be used to kill stolon type weeds.

If the Contractor elects to request the use of other pesticides on the project, the request shall be submitted, in writing, to the Engineer not less than 15 days prior to the intended use of the other pesticides. Except for the pesticides listed in these special provisions, no pesticides shall be used or applied without prior written approval of the Engineer.

Prior to the application of preemergents, ground cover plants shall have been planted a minimum of 3 days and shall have been thoroughly watered.

A minimum of 100 days shall elapse between applications of preemergents.

Except for ground cover plants, preemergents shall not be applied within 450 mm of plants or within wild flower seeding areas.

Growth regulators shall not be applied within 2 m of trees, shrubs or vines.

Ammonium sulfate and magnesium chloride shall be used only in areas planted to Carpobrotus or Delosperma. Ammonium sulfate and magnesium chloride shall not be applied in a manner that allows the pesticides to come in contact with trees or shrubs.

If the Contractor elects to request the use of other pesticides on this project, the request shall be submitted, in writing, to the Engineer not less than 15 days prior to the intended use of the other pesticides. Except for the pesticides listed in these special provisions, no pesticides shall be used or applied without prior written approval of the Engineer.

Pesticides shall not be applied within the limits of the plant basins. Pesticides shall not be applied in a manner that allows the pesticides to come in contact with the foliage and woody parts of the plants.

SECTION 10-3. SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS

10-3.01 DESCRIPTION

Modifying traffic signals lighting, sign illumination, electric service , ramp metering systems and communication conduit shall conform to the provisions in Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications and these special provisions.

Work to be performed within the City of San Jose's right of way shall conform to the additional or different requirements described in "City of San Jose Electrical Special Provisions" elsewhere in these special provisions. In the event the special provisions for the City or the Standard Specifications Department of Public Works San Jose do not cover a particular item, the Standard Specifications and these special provisions. shall be applicable.

Electrical work for Traffic Operation Systems (County) shall conform to the details shown on the plans and the provisions in Section 86. "Signals, Lighting and Electrical Systems," of the Standard Specifications and these special provisions.

Electrical work for Power and Communication (VTA) shall conform to the details shown on the plans and the provisions in Section 86. "Signals, Lighting and Electrical Systems," of the Standard Specifications and these special provisions.

Locations of traffic monitoring installations are shown on the lighting plans.

Lighting equipment is included in the following structures:

A. Retaining Wall No. 1
B. Almaden Road UC (Br. No. 37-0366L)
C. Retaining Wall No. 3
D. Retaining Wall No. 4
E. Retaining Wall No. 5
F. Retaining Wall No. 6
G. Retaining Wall No. 7
H. Retaining Wall No. 8
I. Retaining Wall No. 10
J. Retaining Wall No. 14
K. Soundwall No. 1
L. Alma Station UC (Br. No. 37-0121L)
M. Willow Street Viaduct (Br. No. 37-0422L)

Ramp metering work shall be performed at the following locations:

A. NB Rte 87 Onramp at Curtner Ave (CR1M 82+11.5)
B. NB Rte 87 Onramp at Lelong St. (AR1M 103+80)
C. NB Rte 87 to SB Rte 280 connector (GR2M 113+90)

Traffic signal work shall be performed at the following locations:

A. Almaden Road and Willow Glen Way (City)

10-3.02 COST BREAK-DOWN

Cost break-downs shall conform to the provisions in Section 86-1.03, "Cost Break-Down," of the Standard Specifications and these special provisions.

The Engineer shall be furnished a cost break-down for each contract lump sum item of work described in this Section 10-3.

The cost break-down shall be submitted to the Engineer for approval within __ days after the contract has been approved. The cost break-down shall be approved, in writing, by the Engineer before any partial payment for the items of electrical work will be made.

10-3.03 EQUIPMENT LIST AND DRAWINGS

The controller cabinet schematic wiring diagram and intersection sketch shall be combined into one drawing, so that, when the cabinet door is fully open, the drawing is oriented with the intersection.

A maintenance manual shall be furnished for all controller units, auxiliary equipment, and vehicle detector sensor units, control units, and amplifiers. The maintenance manual and operation manual may be combined into one manual. The maintenance manual or combined maintenance and operation manual shall be submitted at the time the controllers are delivered for testing or, if ordered by the Engineer, prior to purchase. The maintenance manual shall include, but need not be limited to, the following items:

A. Specifications
B. Design characteristics
C. General operation theory
D. Function of all controls
E. Trouble shooting procedure (diagnostic routine)
F. Block circuit diagram
G. Geographical layout of components
H. Schematic diagrams

10-3.04 MAINTAINING EXISTING AND TEMPORARY ELECTRICAL SYSTEMS

Traffic signal system shutdowns shall be limited to periods between the hours of 9 a.m. and 3 p.m.

All existing and operational Traffic Operational System (TOS) and Ramp Metering equipment must be kept operational through all phases of construction. Any TOS/Ramp Metering equipment that are affected or damaged, as a result of the Contractor's operations shall be repaired by the Contractor, at the Contractor's expense, to the satisfaction of the Engineer.

10-3.05 FOUNDATIONS

Reinforced cast-in-drilled-hole concrete pile foundations for traffic signal and lighting standards shall conform to the provisions in "Piling" of these special provisions.

Where cast-in-drilled-hole concrete pile foundations are to be constructed in slag aggregate embankments, the diameter of the pile shall be increased to provide a minimum of 75 mm of concrete cover over the reinforcing steel.

Sleeve nuts shall be used on Type 1-B standards. Foundations for Type 1-B standards shall conform to the details on ES-7B, "Anchor Bolts with Sleeve Nuts," except that the bottom of the base plate shall be flush with the finished grade.

10-3.06 STANDARDS, STEEL PEDESTALS AND POSTS

Standards, steel pedestals and posts for traffic signal and lighting standards shall conform to the provisions in "Steel Structures" of these special provisions.

Where the plans refer to the side tenon detail at the end of the signal mast arm, the applicable tip tenon detail may be substituted.

The sign mounting hardware shall be installed at the locations shown on the plans.

The sign panels will be State-furnished in conformance with the provisions in "Materials" of these special provisions.

Type 1 standards shall be assembled and set with the handhole on the downstream side of the pole in relation to traffic or as shown on the plans.

All ferrous metal parts of tubular sign structures shall be galvanized and shall not be painted.

10-3.07 CONDUIT

Conduit to be installed underground shall be Type 1 or Type 3 unless otherwise specified. Detector termination conduits shall be Type 3.

Attention is directed to "Santa Clara Valley Transportation Authority - Encroachment Procedures Within Light Rail Right of Way" elsewhere in these special provisions regarding requirements in the Light Rail right-of-way.

Attention is directed to "Hazardous, Restricted and Non-Hazardous Material, General," and "Naturally Occurring Asbestos Material-General," elsewhere in these special provisions.

The conduit in a foundation and between a foundation and the nearest pull box shall be Type 1.

Conduit sizes shown on the plans and specified in the Standard Specifications and these special provisions are referenced to metallic type conduit. When rigid non-metallic conduit is required or allowed, the nominal equivalent industry size shall be used as shown in the following table:

Size Designation for Metallic Type Conduit	Equivalent Size for Rigid Non-metallic Conduit
21	20
27	25
41	40
53	50
63	65
78	75
103	100

When Type 3 conduit is placed in a trench (not in pavement or under portland cement concrete sidewalk), after the bedding material is placed and the conduit is installed, the trench shall be backfilled with commercial quality concrete, containing not less than 250 kg of portland cement per cubic meter, to not less than 100 mm above the conduit before additional backfill material is placed.

Conduit runs shown on the plans to be located behind curbs may be installed in the street, within 0.9-m of, and parallel with the face of the curb, by the "Trenching in Pavement Method" in conformance with the provisions in Section 86-2.05C, "Installation," of the Standard Specifications. Pull boxes shall be located behind the curb or at the locations shown on the plans.

After conductors have been installed, the ends of conduits terminating in pull boxes, service equipment enclosures, and controller cabinets shall be sealed with an approved type of sealing compound.

At those locations where conduit is required to be installed under pavement and existing underground facilities require special precautions in conformance with the provisions in "Obstructions" of these special provisions, conduit shall be placed by the "Trenching in Pavement Method" in conformance with the provisions in Section 86-2.05C, "Installation," of the Standard Specifications.

At the option of the Contractor, the final 0.6-m of conduit entering a pull box in a reinforced concrete structure may be Type 4.

10-3.08 PULL BOXES

Grout shall not be placed in the bottom of pull boxes.

10-3.09 CONDUCTORS AND WIRING

Splices shall be insulated by "Method B" or, at the Contractor's option, splices of conductors shall be insulated with heat-shrink tubing of the appropriate size after thoroughly painting the spliced conductors with electrical insulating coating.

The minimum insulation thickness, at any point, for Type USE, RHH or RHW wire shall be 1.0 mm for conductor sizes No. 14 to No. 10, inclusive, and 1.3 mm for No. 8 to No. 2, inclusive. The minimum insulation thickness, at any point, for Type THW and TW wires shall be 0.69 mm for conductor sizes No. 14 to No. 10, inclusive, 1.02 mm for No. 8, and 1.37 mm for No. 6 to No. 2, inclusive.

TELEPHONE CABLE

The telephone cable (TC) shall consist of 6 pairs of No. 19 solid copper conductors. Conductors shall be twisted in pairs. Each conductor shall be insulated with a high molecular weight, heat stabilized, color-coded polyethylene material. The insulation shall be 0.44 mm nominal.

Color code for TC cable shall be as follows:

White/Blue
White/Orange
White/Green
White/Brown
White/Gray
Red/Blue

The core shall be protected by non-hygroscopic polyester film with a single longitudinally applied 0.12 mm thick corrugated copper shield (or 0.19 mm thick plastic coated aluminum shield). A moisture barrier of petrolatum-polyethylene compound shall be applied over the core tape and over and under the cable shield to fill all cable interstices.

The cable shall be provided with an outer jacket of extruded, black, high molecular weight, heat stabilized polyethylene material. The outer jacket shall have a thickness of 1.5 mm nominal.

Splices will not be allowed, except where shown on the plans.

10-3.10 BONDING AND GROUNDING

Bonding and grounding shall conform to the provisions in Section 86-2.10, "Bonding and Grounding," of the Standard Specifications and these special provisions.

Bonding jumpers in standards with handholes and traffic pull box lid covers shall be attached by a UL listed lug using 4.5-mm diameter or larger brass or bronze bolts and shall run to the conduit or bonding wire in the adjacent pull box. The grounding jumper shall be visible after the standard has been installed and the mortar pad and cap have been placed on the foundation.

Standards without handholes shall have bonding accomplished by jumpers attached to UL listed ground clamps on each anchor bolt.

For slip base standards or slip base inserts, bonding shall be accomplished by jumpers attached to UL listed ground clamps on each anchor bolt, or a UL listed lug attached to the bottom slip base plate with a 4.5-mm diameter or larger brass or bronze bolt.

Equipment bonding and grounding conductors are required in conduits, except when the conduits contain combinations of loop lead-in cable, fiber optic cable, or signal interconnect cable. A No. 8 minimum, bare copper wire shall run continuously in circuits, except for series lighting circuits, where No. 6 bare copper wire shall run continuously. The bonding wire size shall be increased to match the circuit breaker size in conformance with the Code, or shall be as shown on the plans. Conduits to be installed for future conductors, may omit the copper wire.

Bonding of metallic conduits in metal pull boxes shall be by means of bonding bushings and bonding jumpers connected to the bonding wire running in the conduit system.

10-3.11 SERVICE

Continuous welding of exterior seams in service equipment enclosures is not required.

Type III service equipment enclosures shall be the aluminum type.

Circuit breakers shall be the cable-in/cable-out type, mounted on non-energized clips. All circuit breakers shall be mounted vertically with the up position of the handle being the "ON" position.

The neutral conductor shall run from the service equipment enclosure to the controller cabinet without splicing to any other neutral conductor.

The bottom of the lowest circuit breaker shall be 600 mm above the bottom of the service equipment enclosure.

10-3.12 SIGN DISCONNECTS

Sign disconnects shall be fused switches.

10-3.13 NUMBERING ELECTRICAL EQUIPMENT

The placement of numbers on electrical equipment will be done by others.

10-3.14 VEHICLE SIGNAL FACES AND SIGNAL HEADS

Light emitting diode modules for vehicular traffic signal units (except programmed visibility type) will be State-furnished in conformance with the provisions in "Materials" of these special provisions.

Type SV-1-T mountings with 5 sections and SV-2-TD mountings shall be bolted to the standard through the upper pipe fitting in the same manner shown for bolting the terminal compartment.

10-3.15 PEDESTRIAN SIGNALS

Light emitting diode modules for Type A pedestrian signals will be State-furnished in conformance with the provisions in “Materials” of these special provisions..

10-3.16 PROGRAMMED VISIBILITY VEHICLE TRAFFIC SIGNAL HEADS

Lamps shall be furnished by the Contractor.

A signal technician qualified to program the programmed visibility signal heads shall be present at the time the signal heads are placed in operation.

Lamps for the signal units shall be 150-W, 120 V(ac), incandescent lamps with a minimum average rated life of 6000 hours. The lamp and socket shall be the 3-prong type.

10-3.17 DETECTORS

Loop detector sensor units will be State-furnished in conformance with the provisions in "Materials" of these special provisions.

Loop wire shall be Type 2.

Loop detector lead-in cable shall be Type B .

Slots shall be filled with elastomeric sealant or hot-melt rubberized asphalt sealant.

Slots in portland cement concrete shall be filled with elastomeric sealant or hot-melt rubberized asphalt sealant, or shall be filled with an epoxy sealant conforming to the provisions in Section 95-2.09, "Epoxy Sealant for Inductive Loops (State Specification 8040-06)," of the Standard Specifications.

Where one traffic signal detector consists of a sequence of 4 loops in a single lane, the front loop closest to the limit line or crosswalk shall be located 0.3 m from this line. All 4 loops in each lane shall be connected in series.

Where one ramp metering demand (D) detector consists of a sequence of 3 loops in a single lane, all 3 loops in each lane shall be connected in series.

The Contractor shall provide two reports per location on the status of each detector loop replacement showing continuity and insulation resistance readings. The reports shall be submitted to the Engineer, one before starting work and the other after work has been completed at each location.

10-3.18 LONG LEAD-IN LOOP DETECTOR (LLLD)

General

The Long Lead-in cable Loop Detector (LLLD) shall comply with the following:

1. Chapter 5 of the Transportation Electrical Equipment Specifications (TEES), November 19, 1999.
2. Section 86-5.01 of the July 1999 Standard Specifications.
3. The enhancements as specified in this specification.

Sensitivity

The LLLD shall have a sensitivity based on delta L threshold rather than delta L (only). There shall be 8 threshold levels ranging from 8 nanohenries to 1024 nanohenries (8, 16, 32, 64, 128, 256, 512, 1024). The LLLD shall be capable of detecting Agency licensed vehicles over the following configurations:

1. Single Type A, B, Q or round Loop with a 1,000 meter lead-in-cable
2. Single Type A, B, Q or round Loops connected in series with a 1,000-meter lead-in-cable.

Variations

The LLLD shall be permitted the following exceptions to the TEES and Standard Specifications:

1. Three frequency settings maximum.
2. The operating frequency of 40 KHz is not required as long as FCC rules are adhered to.
3. The minimum Q requirement of 5 is not required if all other functional requirements are met.
4. Pulse mode requirements may vary from TEES but are subject to the approval of the Engineer.

Certificate of Compliance

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in accordance with the provisions of Section 6-1.07, “Certificates of Compliance” of the Standard Specifications for all of the LLLD furnished for the project.

Warranty

The LLLD shall have a complete manufacturer’s warranty of at least 1-year parts.

10-3.19 LUMINAIRES

Ballasts shall be the lag or lead regulator.

10-3.20 SOFFIT AND WALL LUMINAIRES

A No. 7 pull box shall be installed adjacent to each soffit luminaire as shown on the plans.

10-3.21 INTERNALLY ILLUMINATED SIGNS

The "METER ON" sign shall be a Type A pedestrian signal modified so that the reflector shall be a single chamber with 2 incandescent lamps.

The message shall be white "METER ON" as shown on the plans. White color shall be in conformance with the provisions in Section 86-4.06, "Pedestrian Signal Faces," of the Standard Specifications.

Lenses shall be 4.8-mm, minimum thickness, clear acrylic or polycarbonate plastic or 3-mm nominal thickness glass fiber reinforced plastic, with molded, one piece, neoprene gasket. Message lettering for "METER" shall be "Series C," 113 mm high, with uniform 13-mm stroke, and for "ON" shall be "Series C," 150 mm high, with uniform 25-mm stroke. Letters shall be clear, transparent or translucent, with black opaque background silk screened on to the second surface of the lens.

10-3.22 VIDEO IMAGE PROCESSING SYSTEM

This specification describes the physical and functional properties of a video detection system. This system shall be capable of monitoring all licensed vehicles on the roadway, providing complete intersection detection. The system shall include a video image sensor assembly (camera & lens) with environmental housing and mast arm mount. These assemblies shall interface with the Model 282 adapter to provide an integral operating video detection system.

HARDWARE

1. The system shall be modular by design and housed in either a self-contained stand-alone unit or a standard 170 style input file. The system shall control from 1 to 8 Video Input Processor Boards (VIP). One or more modules per camera, add only as needed.
2. The system shall be designed to operate reliably in the adverse environment of roadside cabinets and shall meet or exceed all NEMA TS-1 and TS-2, as well as Type 170/179 environmental specifications.
3. Ambient operating temperature shall be from -35 to + 75°C at 0 to 95% relative humidity non-condensing.
4. The system shall be powered by 95-135 VAC, 60 Hz, single phase and draw less than 0.4 ampere, or by 190-270 VAC, 50 Hz, single phase and draw less than 0.2 ampere.
5. A 3-wire removable computer style plug shall provide power to the stand-a-lone unit. The rack mounted model (170 input file) shall utilize 24VDC from the cabinet power supply.
6. Surge ratings shall be set forth in the NEMA TS-1 and TS-2 Specifications.
7. Serial communications shall be through an RS-232 or RS-485 serial port. These ports can be used for communications to a modem, laptop, traffic controller, etc.
8. The system shall have one video input (RS-170 NTSC or CCIR composite video) per VIP board and one spare video input.
9. Each VIP board shall have 8 opto-isolated open collector outputs. The outputs shall be programmed for signaling the presence, the arrival or the departure of vehicles in up to 32 detection zones. Outputs shall be brought out via screw connectors.
10. Each VIP board shall have error detection. An output contact will open if the video signal is bad or the VIP board is not functioning properly.
11. The system shall have the capability of accepting an image compression board. This board allows still frames to be transmitted via a modem over standard telephone lines to control center where the still frame can be decompressed and displayed and/or stored.
12. The VIP module shall have separate light emitting diodes (LED) that indicate,

Power	Red to verify power supply
Video	Red to confirm the presence of video input 75 Ohm l V peak-to-peak
RX/TX	Red to indicate communications via the serial port
L1... L8	Green if the corresponding detection group is active

FUNCTIONAL CAPABILITIES

1. Real Time Detection:

1.1 Each VIP board shall be capable of processing the video signal of one camera. The video signal shall be analyzed "in real time".

1.2 The system shall be expandable up to 8 VIP boards that may be connected to different cameras, and programmed independently.

1.3 Each VIP board will detect within the view of the connected camera the presence of vehicles in user defined zones and count the number of vehicles passing over user definable lines.

1.4 Each VIP board shall have 8 detection zones.

1.5 Each VIP board shall have the capability of a pulse mode. A pulse shall be generated at the arrival or the departure of a vehicle in a defined window.
1.6 The pulse width shall be programmable between 20ms and 100 ms in 20ms increments.
1.7 The set-up parameters shall be kept on the VIP board in non-volatile memory.
1.8 The system shall have the capability of up-loading and down-loading set-up parameters via a PC directly or via a communication network.

2. Vehicle Detection Zone:

2.1 The detection zone placement shall be simple and flexible.
2.2 The detection zones shall be defined using a simple keyboard and monitor, or by using a laptop PC with appropriate software.
2.3 Each detection zone shall consist of different lines of detection that are generated automatically in the defined zone.
2.4 When a vehicle is within a detection zone and approaching from the proper direction, the detection zone will change color between white, gray, and black.
2.5 Each detection zone shall have an auto adaptive sensitivity system. No adjustments are needed.
2.6 Each detection zone shall be able to detect the presence of vehicles during day and night periods. Based on proper camera position and sensitivity, the minimum accuracy during normal conditions shall be 98% and 96% during adverse (fog, rain, snow, sleet, etc.) conditions.

IMAGE SENSOR:

1. The video system shall use the signal from a medium or high resolution color or black and white CCD camera.
2. The camera shall produce a noise free signal at scene luminance of 0.15 lux.
3. The image sensor shall have an automatic gain control, automatic iris and black level clamping.
4. The video signal arriving at the VIP board shall have a 1V peak to peak level with noise below 100 mV.
5. The camera shall be housed, as a minimum, in a NEMA-4 water-resistant, dust proof enclosure.

MODEL 282 - ADAPTER

The Model 282 Adapter is utilized to interface the Video Detection Module to Input Files currently supplied with "170 style" cabinets. The plug-in unit directly replaces standard Model 222 and 224 Vehicle Detector Amplifiers, without the need to modify, replace, or rearrange cabinet sub-assemblies.

Features.--

Fits all "170 style" input files
Each adapter occupies only two file slots
All inputs and outputs terminated on backside of file
Eight separate programmable VIP3 outputs
No separate power supply required, powered from cabinet 24VDC
On-board fail-safe, monitors video signal loss and power supply failure
Programmable output and fail-safe matrix
High efficiency low heat generating DC to DC converter
Power line filter to prevent noise feedback
Torrid power inductor for low magnetic radiation
Power "On" LED located on front panel
Power On / Off switch located on front panel

SPECIFICATIONS

A) Video Image Processor specification

Temperature range	-34 to +74 °C, 0 to 95% relative humidity non-condensing
Power input	+5 volts DC +/- 5% @ 450 mA
Outputs	8 opto-isolated open collector circuits
Pulse mode	Pulse width selectable from 20 ms to 100 ms in 20 ms increments
Error detection	Open error contact at the absence of the video signal or malfunction of the VIP board
Front panel connectors	Analog video output with detection lines
Front panel connectors	RS 232 communication port for service and installation
Indicator lights	A separate red LED for power, to confirm video input, and to indicate (RX/TX) active RS-232 communication port. Green LED for each active detection Ll --L8
Memory	Non-volatile for storing setup parameters
Functional operation	VIP module will detect within the view of the connected camera the presence of all licensed vehicles in up to eight user defined zones

B) The Video Image Sensor Assembly specification

Temperature range	-30 to + 55°C, 0 to 95% relative humidity non-condensing
Dimensions and weight	182 x 63 x 53 mm, 810 gr
Camera mounts	1/4-20, top and bottom
Connectors	Video out and sync in: BNC Power in- screw terminals Auto iris: 6 pin
Finish	Off-white semigloss polyurethane
Construction	All metal housing
Rated input voltage	24 volts AC, 60 Hertz
Voltage range	21 to 30 volts AC
Nominal power	4 watts
Imager	Interline transfer CCD, 1/2 inch image format
Imager spectral response	100% @ 550nm; 30% @ 400 nm and 800 nm
Sync system	EIR RS-170
Active picture elements	768 H X 494 V
Horizontal resolution	576 TVL
Sensitivity (scene illumination with fl.4 lens @ 75% highlight reflectance)	0.11 x usable picture @ 2856 K
Front panel connectors	Analog video output with detection lines
Front panel connectors	RS 232 communication port for service and installation
Indicator lights	A separate red LED for power, to confirm video input, and to indicate (RX/TX) active RS-232 communication port. Green LED for each active detection Ll --L8
Memory	Non-volatile for storing setup parameters
Functional operation	VIP module will detect within the view of the connected camera the presence of all licensed vehicles in up to eight user defined zones

C) The Video Image Sensor environmental housing specification

Temperature range	-40 to +50°C - shall maintain internal temperature between -20 to +55°C
Dimensions and weight	449 x 96 x 111 mm at 1350 gr
Housing mounting	Three 1/4-20 tapped holes
Camera mounting	Removable cradle assembly with hole pattern for mounting camera/lens assembly. Cradle may be rotated through 360 degrees
Cable entry	Three liquid-tight fittings will accept cable diameters: one fitting 2 to 7 mm - two fittings 3 to 10 mm
Finish	Off-white semigloss polyurethane
Construction	Extruded aluminum housing, aluminum rear-end cap, aluminum front cap with glass faceplate, and aluminum cradle. A sunshield shall be included.
Window	3 mm thick glass. Includes thermostatically-controlled window heater-defogger
Rated input voltage	115 VAC 50/60 Hz
Voltage range	108 to 132 VAC
Output voltage	24 VAC 50/60 Hz
Nominal power	30 watts
Enclosure protection	Designed to NEMA-4, IP65, Enclosure Type 3

D) Model 282 Adapter Specifications

Model 282 adapter shall fit spaces of two file slots.

Height	129 mm
Width	58 mm
Depth	205 mm
Voltage Input	9 to 40 VDC
Voltage Output	+5 VDC at 3 Amperes
Temperature Range	-35 To +75°C 0% to 95% relative humidity non-condensing
Fail-safe	On-board fail-safe relay
Outputs	8 separate (programmable)
Indicator	Power "ON" LED
Switch	Power "ON" "OFF" front panel
Filter	Line filter to prevent noise feedback

PIN ASSIGNMENTS (TYPICAL)		
VIPS CONNECTION	INPUT FILE CONNECTION J2 (SLOT 2)	FUNCTION
d-32	A	DC-GND
z-32	B	+ 24 VDC
z-28	c	ALARM OUT
z-14	D	DETECTOR 5 OUT
d-14	E	DETECTOR 6 OUT
z-10	F	DETECTOR 1 OUT
N/C	H	LOGIC GROUND
z-18	i	+ RS 485
z-20	K	- RS 485
N/C	L	EQUIPMENT GROUND
N/C	m	AC-
N/C	N	AC+
z-16	p	DETECTOR 7 OUT
d-16	R	DETECTOR 8 OUT
z-12	s	DETECTOR 3 OUT
b-12	T	LOGIC GROUND
d-2	u	VIDEO INPUT - SIGNAL
d-4	v	VIDEO INPUT - SIGNAL
d-10	w	DETECTOR 2 OUTPUT
b-14	x	LOGIC GROUND
d-12	y	DETECTOR 4 OUTPUT
d-16	z	LOGIC GROUND
x	TB2	TB1
SP	1 SPARE	2 SPARE
F	2 DET. #1 OUT	2 DET. #3 OUT
W	3DET. #2 OUT	3 DET. #4 OUT
D	4 DET. #5 OUT	4 DET. #7 OUT
E	5 DET. #6 OUT	5 DET. #8 OUT
i	6 +RS 485	6 VIDEO INPUT -SIGNAL
K	7 -RS 485	7 VIDEO INPUT -SIGNAL
L	8 EQ. GND.	8 EQ. GND.

E) Video Control Power Cable Specification

The video control power cable (VCP) shall be a 3 No. 14 AWG conductor cable (120VAC, AC-, Equipment Gnd) with individually insulated, stranded, copper conductors in conformance with Section 86-2.08, "Conductors" of the Standard Specifications. The conductors shall be color coded black, white and green, respectively.

F) Video Control Cable Specification

The video control cable (VCC) shall consist of an RG-6/U coaxial cable. The cable shall be provided with a solid No. 18 copper clad steel center conductor and shall conform to the following requirements:

Electrical	VCC
Capacitance (picofarads/m nominal)	54.1
Impedance (ohms-nominal)	75
Velocity of propagation (nominal)	84%
D.C. loop resistance (ohms/100 m)	11.7

Attenuation at 20˚C:

Frequency (MHz)	VCC (Nominal dB/ 100 m)
5.0	1.90
30	3.64
108	6.40

Physical Specifications	VCC Nominal O.D. (mm)
Copper-clad steel center conductor	1.00
Foam polyethylene dielectric	4.57
Sealed APA tape with 1.6 mm overlap	4.75
Woven aluminum braid	5.39
Sealed APA tape with 1.6 mm overlap	5.49
Woven aluminum braid	6.12
Flooding compound	
PVC outer jacket	7.55

(APA = Aluminum polyolefin and aluminum with adhesive)

The VCC shall be terminated with BNC plug connector at both ends.

COAXIAL CABLE CONNECTORS

Coaxial cable connectors for attaching shall meet the following requirements:

1. Electrical:

Impedance	75 Ω nominal
Return loss	30 dB minimum (5 MHz to 300 MHz)
Rated working voltage	500 V rms

2. Mechanical:

Type of construction	Integral sleeve BNC
Method of attachment	Crimp-crimp
Composition	Bodies - alloy Finish - chromate conversion, silver plating, or other corrosion resistant metal

3. Environmental:

Temperature	-10˚C to +50˚C
Moisture	Weather resistance design

TESTING

Testing of the cable and connectors shall be performed in accordance with provisions in Section 86-2.14B, "Field Testing" of the Standard Specifications and these special provisions.

Cable lengths found to have faults shall be replaced and retested. The removed faulty cable shall be disposed of by the Contractor.

Prior to the beginning of work, each length of coaxial cable shall be tested for attenuation and faults to ensure compliance with specifications contained herein using a time domain reflectometer (TDR). For the purpose of these special provisions, a fault in a long length of cable is defined by one or more of the following:

a. Return loss measurements indicating that attenuation exceeds 3 dB at 5 MHz to 30 MHz in a portion of cable less than 3 m long.
b. A return loss measurement indicating that there is a short in the cable.
c. A return loss measurement indicating a cut or open circuit in the cable.
d. A visual inspection which reveals exposure of or damage to the cable shielding.

INSTALLATION AND TRAINING

A certified representative of the video detection system supplier shall be available to advise the Contractor and State personnel concerning proper camera selection and site installation. Upon request, the representative shall be available to supervise the installation of the camera equipment.

The certified representative shall do the initial set-up for the detection zones and testing of the system.

The certified representative shall be responsible for the training of Contractor and State personnel.

The video detection supplier shall provide three sets of all documentation necessary to maintain and operate the system.

WARRANTY

The video detection system shall be warranted against manufacturing defects in materials and workmanship for a minimum period of one year from the date of shipment from the supplier. Specific contracts or regional specifications may vary or alter the warranty terms and conditions.

The video detection supplier shall stock the necessary replacement of products to maintain the operability of the system for a period of at least 5 years.

10-3.23 ABBREVIATIONS

CTSS	Caltrans Standard Specifications (July 1999)
CTSP	Caltrans Standard Plans (July 1999)
SPDPWSJ	Standard Plans Department of Public Works San Jose (July 1992)
SSDPWSJ	Standard Specifications Department of Public Works San Jose (July 1992)

Copies of the City of San Jose's Standard Plans and Standard Specifications may be obtained at the director of the public works San Jose City Hall, Rm. 323 on payment of the prescribed purchase price.

10-3.24 CITY OF SAN JOSE ELECTRICAL SPECIAL PROVISIONS

MAINTAINING EXISTING CITY TRAFFIC SIGNAL AND STREET LIGHTING SYSTEMS

The Contractor shall notify the Engineer and the Streets and Traffic Department of the City of San Jose, Phone (408) 277-5515, at least five days prior to performing any work on their existing street lighting system. All splicing of new to existing conductors or disconnection of existing conductors shall be done in the presence of the Engineer, the City Engineer and as directed.

Disconnection of any existing street lighting shall not be permitted except as directed by the Engineer.

At least 20 working days prior to performing any work on existing electrical systems located at various locations, the Contractor shall notify City of San Jose, Phone No. (408) 277-5515 and the Engineer.

Full compensation for maintaining existing traffic signal and street lighting in operation at various locations shall be considered as included in the contract lump sum price paid for signal and lighting at said location and no additional compensation will be allowed therefor.

REGULATIONS AND CODE

Electrical equipment shall also conform to the following additional standards wherever applicable: The International Municipal Signal Association (IMSA); The Insulated Power Cable Engineers Association (IPCEA); The National Electrical Code as amended by the City of San Jose (CSJ) Municipal Code.

EQUIPMENT LIST AND DRAWINGS

Equipment list and Drawings shall conform to CTSS Section 86-1.03 "Equipment List and Drawings" except paragraphs 2 and 3 of section 86-1.03 of the CTSS shall not apply.

MAINTAINING EXISTING AND TEMPORARY ELECTRICAL SYSTEMS

Existing electrical systems, including traffic signals, traffic signal vehicle and pedestrian detection facilities. traffic signal communication and monitoring facilities, street lighting facilities, flashing beacons and sign illumination facilities, or approved temporary replacements thereof, shall be kept in effective operation for the benefit of the traveling public during the progress of the work, except when shutdown is permitted to allow for alterations or final removal of the systems.

The Contractor shall give a 24 hours notice to Electrical Maintenance Supervisor at (408) 277-5515 of the City of San Jose Traffic Operations Department and the Engineer before beginning any work on the existing City traffic signals and City lighting system, including any work which may take vehicle detectors or pedestrian push-buttons out of service, or may

reroute traffic off of existing vehicle detectors, so that signals can be changed to fixed time operations and lighting systems can be turned off.

The Contractor shall notify the Engineer at least 24 hours prior to any operational shutdown of traffic signals, street lighting or other electrical systems or facilities.

Police officers shall be provided, at the Contractor's expense, to direct traffic during the shutdown of a traffic signal system. The Contractor shall arrange for police officer traffic control at least 24 hours prior to the shutdown of a traffic signal system. Traffic signal shutdowns shall be limited to Monday through Thursday excluding holidays, from 9:00 AM to 3:00 PM, or as specified in the special provisions.

Where a facility requires continuous lighting the shutdown time shall be limited to one-half hour as scheduled by the Engineer, unless otherwise permitted by the Engineer. The shutdown of lighting systems shall not interfere with the regular lighting schedule, unless otherwise permitted by the Engineer.

Vehicle detectors and pedestrian push-buttons shall remain in effective operation at all times during the progress of the work on an existing actuated traffic signal system, except as indicated in the special provisions or as provided herein.

Vehicle detectors or pedestrian push buttons taken out of service shall be repaired or replaced within 72 hours. New vehicle detectors for rerouted traffic shall be installed within 72 hours. Where work conditions do not permit the installation of permanent vehicle detectors shall be installed at the Contractor's expense, as directed by the Engineer. Permanent vehicle detectors shall be installed as shown on the plans as soon as worksite conditions permit.

SCHEDULING OF WORK

"Hot cutovers" will not be allowed for electrical circuits, wiring, or equipment involving any traffic signals, streetlights and other electrical systems. The traffic signals and streetlights shall be shutdown for "cutovers" and the Contractor shall provide police officers for traffic control at the Contractor's expense. All work requiring shutdowns shall he performed in accordance with CTSS Section 86-1.05 "Maintaining Existing and Temporary Electrical Systems."

24-hour notice shall be given to the Telephone Company and/or Pacific Gas and Electric Company before the beginning of any operation involving their facilities or systems.

Traffic signal activation shall follow the Public Works procedures for "Signal Activation," or shall be as specified in the Special Provisions. The Signal Activation procedure is available from the City upon request.

INSPECTION

Prior to backfilling of conduit trenches or the pouring of concrete foundations, the Contractor shall notify the Engineer and City Inspector and request inspection of all conduits and foundation forms.

All conduits, conduit couplings, conduit bends and ground bushings shall be in place and tightened and all anchor rods/bolts and ground rods shall be in place in the foundation form prior to the request for inspection. Wire shall not be pulled in conduits until inspection backfilling and pouring of foundations are completed. Stub ends of all conduits shall have approved caps and ground bushings installed prior to backfilling or pouring of foundations.

The Contractor shall not backfill, enclose or otherwise cover up any electrical work prior to inspection and/or testing. Should any of the work be backfilled, enclosed or covered up, the Contractor shall, at his expense, expose such work for such inspection and/or testing.

EXCAVATION AND BACKFILLING

The trenches shall be straight and true to line and grade, and the bottom shall be smooth and even.

REMOVING AND REPLACING IMPROVEMENTS

Whenever a part of a square or slab of existing concrete sidewalk, curb, gutter, driveway or driveway approach is broken or damaged, the entire square section or slab from score line to score line shall be removed and the concrete reconstructed as specified in CTSS Section 73, "Concrete Curbs and Sidewalks."

All areas of Portland cement concrete sidewalks driveways and driveway approaches and asphalt and/or concrete pavements to be removed shall be cut to a minimum depth of 0.05 m with an abrasive type saw prior to removal. Cut, be neat and true along score lines.

FOUNDATIONS

Foundations shall be the type and constructed to the lines, dimensions and configurations as shown on the plans.

Foundations shall be installed at the locations shown on the plans or as designated by the Engineer.

Unless otherwise specified or shown on the plans, foundations not to be reused shall be removed or abandoned.

When a foundation abandoned the top of foundation, anchor bolts, and conduits shall be removed to a depth of not less than 0.3 m below surface of sidewalk or unimproved ground and 0.3 m below the pavement structure in street areas. The resulting hole shall be backfilled with material equivalent to the surrounding material and the surface areas restored in kind,

or as directed by the Engineer. Where obstructions prevent the construction of a planned foundation, the Contractor shall consult with the Engineer to determine an effective resolution.

Unless otherwise specified by the Engineer, posts and standards shall be erected within 10 calendar days after commencement of excavation of the foundation, but not until the foundation has set at least 7 calendar days. They shall be plumbed or raked as directed by the Engineer. Plumbing of posts and standards shall be accomplished before the foundation is finished to final grade and/or before placing the mortar between the base plate and the foundation cap or structure.

Conduit shall enter the foundation at the locations as shown on the plans or as directed by the Engineer. Conduit elbows shall be integrally cast with the foundation.

Forms for foundation caps shall be rigid, at least 0.09 m in width, and shall be accurately placed and secured. The elevation or grade of the foundation cap shall conform to existing surrounding grades or as directed by the Engineer.

The top portion of the foundation or cap shall not be constructed until after the post, standard or pedestal is set in proper position and other improvement constructed, unless otherwise directed.

Mortar shall be placed between the base plate and foundation cap or structure. The thickness of mortar for signal standards shall be at least 0.030 m and not more than 0.091 m. The thickness of mortar for streetlighting standards shall be a maximum of 0.048 m. The mortar shall be struck off and brushed smooth to present a neat appearance.

In paved areas, the top of foundation shall be at least 31 mm but not more than 101 mm below finished grade. Mortar, topping slab, or pavers shall be placed after the post or standard is in proper position. Mortar shall conform to provisions of CTSS Section 51-1.135, "Mortar."

In unpaved areas posts and standards without adjacent pull boxes shall have a foundation cap formed a minimum of 0.60 mm square. When posts or standards are within of other finished concrete work, finish foundation cap shall extend to existing adjacent surfaces.

In unpaved areas posts and standards with adjacent pull boxes shall have a foundation cap constructed to include the pull box.

In unpaved areas, cabinets shall be provided with a raised pad of portland cement concrete in front of the doors: a minimum 90 mm thick, 91 mm long and 1.2 m wide, or as indicated.

Anchor bolts shall be of the sizes and lengths as shown on the plans.

Anchor bolts 15 mm through 31 mm shall have cut threads; rolled threads are not permitted.

Bending of anchor bolts will not be permitted. For traffic signal standards, anchor bolts shall extend a minimum of three full threads, but no more than 50 mm above the top nut. For streetlight standards, anchor bolts shall extend a minimum of three full threads above the top nut, but shall not extend so as to interfere with the installation of the ornamental leaf design nut cover.

All anchor bolts, nuts, and washers shall be galvanized. Anchor bolts with reinforcing bars or plates shall be set in a bolt circle using a template and securely attached to the foundation forms. The anchor bolts shall be set so that the exposed threads will accommodate the thickness of the foundation cap, mortar, base plate, locking nuts and washers.

If anchor bolts require extension, Contractor shall provide structural details to the Engineer for approval prior to start of work.

Ground rods when installed in foundations of standards shall be located to either side of the handhold opening with top of ground rod even with bottom of handhold opening.

STANDARDS, STEEL PEDESTAL AND POSTS

Standards, steel pedestals, and posts shall be of the type indicated on the plans.

The mast arm(s) signal equipment, luminaire and other devices may be assembled and attached to a standard prior to its being erected and set.

After erection, standards and posts shall be plumbed or raked as directed by the engineer. Plumbing or raking of standards and posts shall be accomplished by adjusting the leveling nuts before the foundation cap is placed. The use of shims or other similar devices for plumbing or raking of standards and posts is not acceptable.

Signal equipment shall be plumbed and aimed and luminaires shall be leveled after the standard has been erected and set.

Guard posts shall be installed when the axis of a standard is located within 0.92 m of a driveway approach to protect the standard from damage by moving vehicles or as directed by the Engineer. Guard posts shall be galvanized standard pipe conforming to the specifications of ASTM Designation: A53 or A120.

Existing standards to be relocated or reused in place shall be repaired as directed by the Engineer. Holes shall be welded closed, large dents shall be removed, shafts shall be straightened, and portions, which are in poor condition due to rust, corrosion or damage, shall be replaced. Repaired areas shall be ground smooth and primed for application of finish.

Existing standards having a painted finish which are modified, relocated, repaired or upon which equipment is altered by the Contractor shall be repainted.

The Contractor shall apply pressure-sensitive identification number labels to all lighting standards and all signal standards with luminaires, as directed by the Engineer. Labels shall Stick-On type, yellow reflectorized numbers and letters on black background measuring 35mm wide and 48 mm high, installed vertically arranged with space on either side of the

middle letter. Bottom height of the number shall at 2.13 m (min.) from ground. The City will provide their identification number for each luminaire.

SIGNAL STANDARDS

Signal equipment and other devices shall be secured to signal standards using cadmium plated threaded bolts and/or screws. Signal standards shall be drilled and tapped as required to accept such bolts and/or screws. The use of "through-bolts" with nuts to secure equipment to standards is not acceptable.

Signal mast arms shall have the end signal head mounting tenon located on the side of the mast arm, rather than at the tip.

Drilling, tapping and machining of signal standards shall be performed on the job site. Holes in standards shall be cut using drills or hole saws. The use of a cutting torch for the purpose of producing holes in standards will not be permitted unless authorized by the Engineer prior to performing the work.

When modifying signal or lighting equipment on existing signal standards the Contractor shall de-energize and remove circuit conductors prior to drilling, cutting, welding and/or tapping the pole. When performing this work, the Contractor shall schedule a system shutdown in accordance with CTSS Section 86-1.05 "Maintaining Existing and Temporary Electrical Systems."

CONDUIT

Conduit shall be of the sizes and types as shown on the plans or as specified in the specifications or these special provisions.

a. Material.

Conduit and conduit fittings shall be UL or ETL listed and shall be of one of the following types:

1. Galvanized Rigid Steel (GRS)-GRS conduit shall conform to the requirements of UL Publication UL6 for Rigid Metallic Conduit. The zinc coating shall be applied by the hot-dip process and shall conform to the requirements of ASTM Designation: A239.
2. Plastic Coated Galvanized Rigid Steel (PCGRS)-PCGRS conduit shall conform to (1) above and shall have an external coating of polyvinyl chloride. Thermoplastic coating shall have a minimum thickness 40 mils.
3. Rigid Non-Metallic Polyvinyl Chloride (PVC)-PV conduit shall conform to the requirements of the U Standard for Rigid Non-Metallic Conduit Publication 651.

GRS and PCGRS conduit shall be terminated and insulated bonding type ground bushings. PVC conduit shall be terminated with end bell fittings.

All fittings used for installing, supporting, joining and connecting on conduit shall be specifically designed and manufactured for electrical use.

All metal conduit couplings shall have straight non-tapered threads and shall be marked by the manufacturer with an "E" to identify them as being of electrical grade. Tapered plumbing type couplings and couplings with slip joint set screws or running threads will not be permitted for joining conduits.

Conduit that is installed underground or in concrete foundations shall be Schedule 40 PVC or PCGRS. Conduit that is installed as a service riser shall be schedules 80 PVC and shall conform to the requirements of the Pacific Gas and Electric Company. Conduit that is installed in exposed locations or in structures shall be GRS.

Exposed conduit installed on a painted structure shall be painted the same color as the structure as specified in CTSP Section 86-2.16, "Painting."

Conduit runs shall be continuous and uniform in kind and diameter. The existing conduit runs are to be modified or extended, new conduit shall match existing in kind. Reducing couplings shall not be permitted.

Conduit diameter shall be as indicated on the plans or, if not specified, shall be a minimum of the following:

1. 41 mm between an electrolier and pull box.
2. 27 mm between a pedestrian push button post and pull box.
3. 53 mm between a signal standard and pull box.
4. 53 mm for detector lead-in cable runs.
5. 78 mm between a type "M" controller cabinet and pull box.
6. 78 mm (two conduits) between type "P" controller cabinet and pull box.
7. 27 mm between the detector loop termination at the lip-of-gutter and pull box.
8. 78 mm for traffic signal conduits between pull boxes where conduit crosses a roadway.
9. 41 mm for Street lighting systems.
10. 53 mm for traffic signal systems.

b. Installation.

Conduit installed underground shall be installed in open trenches, unless approved otherwise by the Engineer. Trenches for conduit shall be straight and uniform in depth, free of ridges and depressions. Conduit shall not be covered until the installation has been approved by the Engineer.

Trench-laid conduit shall have a minimum of 457 mm of cover in non-roadway area and 610 mm of cover (below finished grade) in roadway areas, including driveways, unless otherwise indicated or approved by the Engineer. Conduit depth shall not apply at locations where conduit slopes upward to pull box or standard.

The minimum cover requirements for trench-laid conduit may be reduced if the conduit is protected in a portland cement concrete encasement. Revisions to the minimum conduit depth requirements will be at the Contractor's expense and will require written approval from the Engineer, prior to conduit placement.

Conduit less than 457 mm below the surface and not encased in concrete or less than 3 meters above the finished surface shall be PCGRS or GRS conduit unless specifically indicated otherwise on the Plans or allowed by the Engineer.

Parallel conduit runs installed in a common trench without concrete encasement shall have a minimum 152 mm of separation between conduits. Where parallel conduit runs installed in a common trench are encased in concrete, a minimum of 152 mm of separation shall be maintained between the conduits and the trench walls and floor and between individual conduits. Conduit spacers and anchors shall be installed as required to ensure a complete and uniform flow of concrete around the conduit. Distances between conduit spacers and between anchors shall not exceed 1.5 m.

Where an underground obstruction is encountered which prevents the installation of a conduit run as shown on the plans the alignment of the conduit run may be revised and/or additional pull box(es) may be installed as required to avoid the obstruction. Such revisions to the conduit alignment and pull box layout will be at Contractor's expense and will require the prior written approval of the Engineer.

Contractor shall at the request of the Engineer, open inspection holes as required to determine compliance with the requirements for trench-laid conduit depth and alignment. Inspection holes shall not be backfilled until the conduit installation has been approved by the Engineer. Upon completion of inspection, inspection holes shall be filled to the satisfaction of the Engineer. The opening and filling of inspection holes shall be at the expense of the Contractor.

Backfilling, compaction and restoration of the surface of trenches shall be in accordance with the provisions of the applicable section of these Specifications.

In traffic signal installations GRS or PCGRS conduit runs may be laid on top of existing pavement within curbed median islands that are to have Portland cement concrete surfacing.

Conduit runs for Streetlighting shall be installed either parallel to or perpendicular to the curb, unless otherwise approved by the Engineer prior to placement. Conduit at an oblique angle to the curb will not be permitted. Conduit runs parallel to the curb shall be located not more than 685 mm not less than 152 mm behind the face of curb, unless otherwise indicated on the Plans or approved by the Engineer.

Conduit shall not be installed by the "impact driving" method.

With the approval of the Engineer, conduit may be installed by either the jacking or drilling method. When a conduit jacking or drilling pit is to be left open overnight, it shall be covered in accordance with the requirements set forth by the Engineer, and/or the American Railway Engineering Association (AREA) Standard Specifications, for railroad crossings.

Conduit installed under a roadway by jacking or drilling shall not be less than 610 mm nor more than 1220 mm below the flow line of the gutter or edge-of-pavement grade where no gutter exists.

Where conduit is installed under a roadway by the drilling method, any excessive voids shall be filled to the satisfaction of the Engineer.

Conduit bends shall be avoided wherever possible and where required shall be of the largest possible radius. Where underground conduit changes direction long radius sweeps shall be used instead of short radius bends.

The radius of conduit bends and elbows entering foundations shall not be less than 12 times the internal conduit diameter. Unless specified otherwise, other conduit heads and elbows shall not have a radius less than 762 mm.

PVC conduit elbows shall be factory manufactured. Field bending of PVC is not permitted.

Conduit bends and elbows shall be free of flattening, kinks and indentations.

No single conduit bend or elbow shall exceed an angle of 90 degrees.

Unless otherwise approved by the Engineer, there shall be no more than the equivalent of :

1. 135 degrees of bends in a conduit run from a pull box to a foundation.
2. 90 degrees of bends in a conduit run from a pull box to a pull box where the conduit is installed parallel to and on the sidewalk side of curb.
3. 270 degrees of bends in a conduit run from a pull box to a pull box where the conduit is installed parallel to and on the streetside of the curb.
4. 180 degrees of bends in a conduit run from a pull box to a pull box where the conduit is installed perpendicular to the curb.

PVC conduit, elbows, coupling and fittings shall be welded. Solvent weld cement shall conform to the requirements of ASTM D2564. In solvent welding of PVC conduit and components, the Contractor shall thoroughly coat the mating surfaces of the joint with cement and, after insertion, shall twist the joint 180 degrees to insure a complete bond.

Conduit in the foundation of a standard or an enclosure shall terminate no more than 53 mm and not less than 27 mm above the top surface of the foundation.

The uppermost 203 mm of conduit terminating in a standard or an enclosure shall be straight and shall be so positioned in the foundation that its prolongation would pass through the handhole opening.

Any conduit elbow stub leaving a foundation shall extend a minimum of 152 mm from the face of the foundation and shall have at least 457 mm of cover. The elbow stub shall exit the foundation in the direction indicated on the Plans and shall be capped until conduit is attached or a bushing is installed.

Conduit between a foundation and an adjacent pull box shall be continuous without couplings from the elbow stub at the foundation to the elbow into the pull box. The conduits entering foundation shall be PVC schedule 40 or PCGRS.

Conduit shall enter a concrete pull box through the short side and shall so positioned that the prolongation of the conduit would pass through the top opening of the pull box. Conduit shall not enter from the bottom or from the long pull box unless otherwise approved by the Engineer. Conduit shall enter a pull box in the direction of the conduit run. Conduit shall terminate not more than 53 mm and not less than 25 mm from the inside wall or bottom of the pull box.

Where a new pull box is installed in an existing metallic conduit run, the conduit shall be cut, threaded, fitted with grounding bushings and bonded. The exterior surface of conduit which will be partially or completely imbedded in concrete structures shall be cleaned before the concrete is placed.

Conduit installed in the structure shall be galvanized rigid steel (GRS), the size as indicated on the plans. All conduit running transversely the bridge deck shall be placed in the running transversely to the side walk will be placed in the rail through the deck. All conduit running longitudely on the bridge shall be laid on top of the deck under the sidewalk or in the cell compartment, where there is no sidewalk. All conduit extending more than 2 m in the cell compartment shall be supported in the cell.

The installation of conduit into a manhole, vault or pull box of the Pacific Gas and Electric Company, Southwestern Bell Corporation or other agency shall conform to the requirements of the respective agency. The Contractor shall contact representatives of those organizations for instructions regarding the preferred location of entry and termination method of such conduit. The conduit shall project into the manhole, vault and/or pull box only far enough for a bushing to be placed on the conduit end. The opening around the conduit shall be carefully and completely filled with mortar and neatly finished.

A pull rope shall be installed in all conduits which are designated for future use. The pull rope shall be nylon or polypropylene with a minimum tensile strength of 227 kg. At least 0.60 m of pull rope shall be doubled back into the conduit at each termination.

Prior to the installation of conductors or cables in either existing or newly installed conduit, the Contractor shall prove and clean the conduit by pulling a mandrel or wire brush through the conduit or by rodding, then blowing out the conduit with compressed air.

Rodding shall be performed by simultaneously pushing and turning a straight steel or wooden rod through the conduit, taking care not to damage the conduit walls.

The cost of proving conduit shall be considered as included in the price paid for electrical installations and no extra payment shall be made therefor.

Pull Boxes.

Except as noted below, pull boxes shall be installed at the locations shown on the Plans and shall be of the sizes specified. To facilitate his work, the Contractor may at his option and expense, install additional pull boxes or pull boxes of a larger standard size than those shown or specified. The locations additional Pull boxes shall be established by the Engineer.

a. Materials.

Pull boxes extensions and covers for installation in the ground or sidewalk areas shall be constructed of pre-cast reinforced concrete. Pull boxes shall be of the sizes shown on the plans . Pull boxes shall have gray plastic coated rims. Each pull box cover shall be secured with two 6.35 mm brass hold down bolts with brass washers and nuts. Nuts shall be recessed below the surface of the cover.

Pull boxes and extension for installation in areas subject to traffic loads shall be constructed of pre-cast reinforced concrete. Traffic pull boxes shall be of the sizes shown on the plans . Each traffic pull box shall be provided with a checkered steel plate cover, a minimum of 6.35 mm thick conforming to the design indicated on the plans. The steel cover shall be electrically grounded by means of a one meter length of copper braid equivalent to a Number 8 AWG or larger copper conductor. The copper braid shall be attached to a suitable grounding lug welded to the underside of the traffic cover and shall be bonded to the service grounding electrode.

Pull boxes and covers for installation in structures shall be of the sizes and details shown on the plans. In lieu of the structure pull box shown on the plans the Contractor may use a telescoping steel pull box, with interior dimensions conduit entrances and cast iron cover conforming to the details shown on the plans. The design of the steel pull box shall be submitted to the Engineer for approval prior to fabrication.

The covers for pull boxes except ceiling pull boxes shall be clearly marked with a legend that identifies the electrical system served by the pull box. Pull box cover legends shall be as follows:

CSJ TRAFFIC SIGNAL: for traffic signal systems with or without streetlighting systems
CSJ STREET LIGHTING: for street lighting systems only
CSJ COMMUNICATIONS: for traffic signal communications only
CSJ SPRINKLER CONTROL: for sprinkler control systems only
CSJ SERVICE: for service laterals to utility facilities termination Point only
CSJ ELECTRICAL: for combined electrical systems or Miscellaneous systems not mentioned above.

The pull box cover legend shall be formed of capital block letters between 25.4 mm to 76.2 mm in height. The legend may be parallel to either the long or short side of the cover.

Concrete pull box covers shall have the legend cast into the cover at the time of manufacture. The lettering of the legend shall be sharply defined, uniform in depth, evenly spaced and neatly aligned.

Steel pull box covers shall have the legend applied to the cover prior to galvanizing using one of the following methods:

(1) Cast iron strips at least 7 mm thick with the letters raised a minimum 1.58 mm. Strips shall be fastened to covers with 7 mm flathead stainless steel bolts and nuts. Bolts shall be peened after tightening
(2) Sheet steel strips at least 22 Gage with the letters raised a minimum of 1.58 mm above the surrounding surface of the strips. Strips shall be fastened to the covers by spot welding, tack welding, brazing, with 7 mm stainless steel rivets or 7 mm, roundhead stainless steel machine bolts and nuts. Bolts shall be peened after tightening.
(3) Bead welding the letters on the covers. The letters shall be raised at least 2.4 mm.

b. Installation and Use.

Pull boxes shall be installed at the locations shown on the plans. Pull boxes shall not be spaced at intervals over 60 m whether indicated on the plans or not, unless otherwise directed by the Engineer. Pull boxes shall be installed in roadways, driveways, driveway approaches, gutters, or wheelchair ramps.

The bottoms of pull boxes installed in the ground or in sidewalk areas, shall be bedded in washed river drain rock as shown on the plan details, and shall be grouted prior to the installation of conductors. The grout shall be between 25 mm and 50 mm thick and shall be sloped toward the drain hole. One layer of roofing paper shall be placed between the grout and the rock sump. A 25 mm diameter drain hole shall be provided in the center of the pull box through the grout and the roofing paper.

Existing pull boxes disturbed by the Contractor's operations shall, at Contractor's expense, have drain rock sumps and grouped bottoms installed and shall be reconstructed in conformance with these Specifications, or as directed by the Engineer. Pull boxes shall be CSJ Number 5 minimum for lighting systems traffic signal systems or other systems, unless otherwise specified.

Pull boxes shall be installed with the long dimension parallel to the main conduit run. In the vicinity of curbs, pull boxes shall be placed adjacent to the back of curb. In the vicinity of standards, pull boxes shall be placed alongside the foundation as indicated in the plans. The top of the pull box shall be flush with the surrounding grade or top of adjacent curb unless otherwise indicated.

Where pull boxes are placed in areas subject to traffic loads, (when permitted by the Engineer), they shall be installed on suitable concrete footings.

Conductors.

Conductors shall be copper of the gage shown on the plans, unless specified otherwise.

The minimum wire gages for streetlighting systems shall be as follows: Number 8 AWG for service and feeder conductors from service point to the main disconnect and branch circuits. Number 12 AWG for branch circuits from feeder to lamp ballasts, and Number 14 AWG for control circuits from photoelectric-unit (PEU) to contactor.

Copper wire shall conform to-the specifications of ASTM Designations: B3 and B8.

Wire sizes, other than conductors used in loop detector lead-in cable, shall be based on American Wire Gage (AWG), Conductor diameter shall be not less than 98 percent of the specified AWG diameter. Conductors used in loop detector lead-in cable shall conform to the specifications of ASTM Designation: B 286.

Conductors shall be UL or ETL listed and rated for 600-V operation. The insulation for traffic signal conductors installed between a traffic signal controller and related traffic signal appurtenances shall conform to one of the following:

(1) Type UF, with a minimum insulation thickness of 1.5 mm at any point. for conductor sizes Number 14 AWG through Number 10 AWG.
(2) Type THW or UF. with a minimum insulation thickness of 1.5 mm at any point, for conductor sizes Number 8 AWG and larger.

The insulation for all conductors other than traffic signal conductors as specified above shall conform to one of the following:

(1) Type THW, with a minimum insulation thickness of 1.2 mm at any point, for conductor sizes Number 14 AWG through Number 10 AWG.
(2) Type THW or UF with a minimum insulation thickness of 1.5 mm at any point, for conductor sizes Number 8 AWG and larger.
(3) Type THW polyvinyl chloride conductor insulation shall conform to the requirements of ASTM Designation: D 2220.

a. Conductor Identification.

Conductor identification shall be as follows:

CONDUCTOR TABLE					
		IDENTIFICATION			
		INSULATION COLOR			
CONDUCTOR USE	SIGNAL PHASE OR FUNCTION	BASE	STRIPE	LABEL DESIG-NATION	CONDUCTOR SIZE
Vehicle Signals	2,6	Re,Ye,Brn	Black	2.6	14
	4,8	"	Orange	4,7	14
	1,5	"	None	1,5	14
	3,7	"	Purple	3,7	14
	Overlaps	"	Note 1	OL#	14
Pedestrian Signals	2p, 6p	Red, Brown	Black	2p, 6p	14
	4p, 8p	"	Orange	4p, 8p	14
	1p, 5p	"	None	1p, 5p	14
	3p, 7p	"	Purple	3p, 7p	14
Pedestrian push Buttons	2p, 6p	Blue	Black	pb2, pb6	14
	4p, 8p	"	Orange	pb4, pb8	14
	1p , 5p	"	None	Pb1, pb5	14
	3p, 7p	"	Purple	pb3, pb7	14
Traffic signal Controller Center	Ungrounded-line 1 Grounded-Neutral	Black White	None	CN1 CNN	As req'd
Streetlighting	Ungrounded-Line1 Ungrounded-Line2 Grounded-Neutral	Black Red White	None None none	SL1 SL2 SLN	As req'd
Lighting Control	Ungrounded to Photoelectric Unit (PEU) Switched leg from PEU unit Grounded-neutral	Black Red White	None None None	C1 C2 C3	14 14 14
Irrigation Control	Undergrounded-Line 1 Grounded-Neutral	Black White	None None	IR1 IR2	As req'd
Service	Undergrounded-Line 1 Undergrounded Line2 Grounded-Neutral	Black Red White	None None None	SR1 SR2 SR3	As req'd

CONDUCTOR TABLE (Cont'd)					
		IDENTIFICATION			
		INSULATION COLOR			
CONDUCTOR USE	SIGNAL PHASE OR FUNCTION	BASE	STRIPE	LABEL DESIG-NATION	CONDUCTOR SIZE
Sign Lighting	Undergrounded - Line1 Undergrounded-Line2	Black Red	None None	SN1 SN2	12 12
Flashing Beacons	Undergrounded between flashing Beacons Grounded Neutral	Red or Yellow White	None None	Flasher Location FLN	14 14
Logic Common	Pedestrian Push buttons	White	Black	None	14
Grounded Neutral	Traffic Signals	White	Black	None	14
Traffic Signal Communication	As Req'd	As req'd	As req'd	Per Sect. 86-2.08	As req'd
Rail Road Pre-emption	As Req'd	Black	None	RR	14
Emergency Vehicle Pre-emption	As Req'd	Black or as req'd	None	EV#1,2,3 as req'd	14 or as req'd
Spares	Traffic Signal Spares	Black	None	None	14
Inductive Loop Detector Circuits	Vehicle Detection	As Req'd	none	Per Sect. 86-5.01A (5)	As req'd

Notes:

1. Conductors for overlap traffic signal shall have their insulation striped for the first signal phase in the designation. For example, a phase (2+3) overlap conductor shall have its insulation striped as phase 2.
2. Conductors for overlap traffic signal phases and other special functions shall be labeled accordingly.

b. Circuitry.

The "common" for pedestrian push button circuits shall be a separate conductor and shall not be used for any other purpose.

c. Installation.

Conductors shall not be pulled into conduits until after pull boxes are set to grade, drain rock sumps installed, conduit grouted in place, bottoms of concrete boxes grouted, and the conduits bonded.

The conduit system shall be complete and approved by the Engineer before any conductors are installed in conduits. All conductors shall be run in conduit except overhead installations or where conductors are installed by means which will not any way damage the conductors or its insulation. Conductors entering conduits shall be carefully fed and positioned to avoid "tangles" and "crossovers." All conductors shall be installed simultaneously.

Conductors and cables in all pull boxes shall be grouped and arranged in a workmanlike manner. Conductors and cables in manholes shall be supported by strapping to the side wall.

A UL or ETL listed inert lubricant such as powdered soapstone or talc shall be used in placing conductors in conduit.

Conductors shall be pulled into conduit by hand. Use of wrenches or other power actuated pulling equipment will not be permitted.

When conductors are to be added to existing conductors in a conduit, all conductors shall be removed; the conduit shall be cleaned as provided in CTSS Section 86-2.05C, "Installation" and all conductors shall be pulled into the conduit as a unit. Traffic signal and streetlighting conductors receiving power from different service points shall not be installed in the same standard, conduit, pull boxes or other enclosures. Service conductors shall not be installed in traffic signal or streetlighting conduits.

Temporary conductors less than 3 m above grade shall be enclosed in flexible or rigid metal conduit.

At least 0.60 m of slack shall be left in traffic signal conductors at each signal or combined lighting/signal standard, where a pull box is not adjacent to the standard and/or there is more than one conduit in the base of the standard. Slack shall be measured by removing the handhole cover on the standard and extending the wire horizontally beyond the handhole opening.

At least 0.60 m of slack shall be left in lighting conductors at each standard to facilitate the removal of fused spliced connectors. Slack shall be measured by removing the handhole cover on the standard and extending the conductors horizontally beyond the handhole opening.

At least 0.92 m of conductor slack shall be left in all conductors, at each pull box. Slack shall be measured by removing the pull box lid and extending the conductors vertically above the pull box grade.

Conductors shall be permanently identified as to function (vehicle signal phase, pedestrian signal phase, streetlight circuit, streetlight controls, irrigation circuit) as detailed in the "Conductor Table" "Conductor Identification." Identification shall be means of encircling individual conductors/cables or functional groups of conductors with a permanent identification label in each pull box and at the termination of the conductors/cables. Labels shall be fastened in such a manner that they will not move along the conductors/cables.

d. Connectors and Terminals.

Conductors shall be joined by means of approved spring-type pressure connectors, crimp style terminal lugs, or by other methods approved by the Engineer. Crimp style terminals shall have continuous barrels or scams shall brazed so they shall not separate during crimping.

Finished connections and terminals shall comply with all UL requirements.

All stranded conductors smaller than number 14 AWG shall be termination in crimp style terminal lugs.

Crimp tools shall be of the type that necessitates a crimp pressure of manufacturer's required value before tool will unlock. Where splices are required to be soldered, they shall be soldered using the hot iron method with rosin core solder. Soldering with open flame will not be allowed.

All joints shall be covered with insulation equivalent to the voltage and temperature rating of the insulation on the conductors as shown on plans.

Split bolt connectors shall not be used except where specifically authorized by the Engineer.

Connectors and terminals for use with aluminum conductors shall be approved for aluminum-to-aluminum or aluminum-to-copper as required, and shall comply with all UL requirements unless otherwise approved by the Engineer.

e. Splicing.

Unless specified otherwise or permitted by the Engineer, splices shall conform to the plans. Conductor splices will not be permitted in controller cabinets. Use of terminal compartments or terminal block on standards shall not be permitted.

Splices will be permitted only in the following types of circuits at the following locations:

1. Grounded conductors and branch signal light neutrals in pull boxes.
2. Pedestrian push button conductors in pull boxes.
3. Multiple lighting and power conductors shall be spliced in a pull box adjacent to the standard.
4. Traffic signal conductors shall be spliced in pull boxes on at location shown on the plans.

Ungrounded traffic signal conductors to a signal head on a standard shall be spliced to through conductors of the same phase in the pull box adjacent to the standard.

f. Splice Insulation.

Splice insulation shall be done as shown on the plans. Low voltage tape shall be UL or ETL listed and shall be as follows:

1. Self-fusing, oil and flame-resistant synthetic rubber.
2. Pressure-sensitive, adhesive polyvinyl chloride, 0.17 mm minimum thickness.

Where polyvinyl chloride tape is used for a final layer, an electrical insulating coating, compatible with the tape, shall be used. It shall be fast drying, resistant to oil, acid, alkalis and corrosive atmospheric conditions.

The Contractor may elect to use, with approval of the Engineer, one of the following splice insulation methods:

1. A minimum of 2 thickness of electrical insulating pad, posed of a laminate of 2.15 mm thickness of electrical grade polyvinyl chloride and a 3.175 mm of butyl splicing compound with removable liner. Pads Shall be applied to the splice in accordance with the manufacturer's recommendations. The applied pad shall be wrapped with polyvinyl chloride tape half lapped over the conductor insulation.

2. Heat shrinkable insulating tubing shall be applied after completing the splicing procedure shown on the plans. Insulation over the connector shall consist of a heat shrinkable, mastic lined, heavy wall polyolefin cable sleeve, or cover, to which heat shall be applied at a temperature greater than 120˚C until the sleeve or cover, shrinks and covers the connector and the mastic material has flowed completely around the cable to form a waterproof insulation.

Where splices are below grade or exposed overhead, the insulation and taping shall be applied between the conductors in such a manner as to provide a watertight joint. The splice shall be capable of satisfactory operation under continuous submersion in water.

Multi-conductor cables shall be spliced and insulated to provide watertight joint and to prevent absorption of moisture by the cable.

g. Fused Splice Connector.

Fused splice connector shall conform with the following:

Fused disconnect splice connectors with fuses shall be installed as shown on the plans.

BONDING AND GROUNDING

Metallic cable sheaths, metal pull box covers, metal conduit, equipment grounding conductors, ballast and transformer cases, service equipment, sign switches, anchor bolts, metal poles and pedestals shall be made mechanically and electrically secure to form a continuous system, and shall be effectively grounded.

Bonding and grounding jumpers shall be Number 8 AWG or larger copper wire o copper braid, except where bonding and grounding wire is provided as an integer part of manufacturer's splice kit and is in conformance with the Code. Equipment grounding conductors shall be color coded to Code requirements or may be bare.

Bonding of standards and pedestals with handholes shall be by means of a 9.5 mm or larger non corrosive grounding lug installed in the lower portion of the pole shaft as indicated in the plans. Standards without handholes shall be bonded by a Number 8 AWG minimum jumper, attached to all anchor bolts and run to the conduit or bonding wire in the adjacent pull box. The grounding jumper shall be visible after tile foundation cap has been placed on the foundation.

Where a pull box is located adjacent to the standard the grounding electrode shall be driven in the pull box. Grounding electrodes in foundations shall be set obliquely through the foundation and shall extend above the finish foundation sufficiently to attach a ground clamp and bare copper wire ground conductor. Ground rod identifying marks shall be visible. Both the bolt and ground rod clamp shall be visible from the door or handhole.

Grounding of metal conduit, service equipment and the grounded conductor at service point shall be accomplished as required by the Code and the serving utility except that the grounding electrode conductor shall be Number 6 AWG minimum for Type III service cabinets and Number 8 AWG minimum for all other service types.

Bonding to grounding electrodes shall be by use of UL approved ground clamps or as approved by the Engineer.

A Number 8 AWG or larger stranded copper equipment grounding conductor shall be provided in all conduits carrying traffic signal and/or streetlight conductors. The equipment grounding conductor shall not be required under the following conditions:

(1) Where a conduit is to be left empty for future use, provided that the conduit is terminated in pull box(es) that do not have metallic covers or components.
(2) Where a conduit contains only detector lead-in cable(s) and/or signal communication cable(s) provided that the conduit is terminated in pull box(es) that do not have metallic covers or components.

The equipment grounding conductors shall be bonded in accordance with the Plans. At each multiple service point and at each pole or within 3 m of each pole a grounding electrode shall be furnished and installed.

Grounding electrodes shall be 15 mm round x 3 m copper clad or 19 mm x 3 m galvanized steel rod; resistance to ground shall not exceed 25 Ω. Grounding electrodes shall be installed in accordance with the provisions of the Code.

On wood poles, all metallic equipment mounted less than 2.43 m above ground surface shall be grounded.

Bonding of metallic conduit shall be by means of galvanized or bronze grounding bushings and bonding jumpers.

Bonding of metallic conduit in steel pull boxes shall be by means of lockouts one inside and one outside of the box.

SERVICE

The conductors between the service equipment and the utility company service connection point shall be continuous and shall not be spliced. When these conductors pass through pull boxes, they shall be looped one complete loop in the pull box following the perimeter of the pull box tightly before exiting.

The Contractor shall install pull boxes, conduit and conductors between the utility company service point and the service equipment. Where the service point is a utility-owned pole, the Contractor shall install a 53 mm service conduit riser up the pole 254 mm above grade in the quadrant assigned by the serving utility company and shall also install a pull box at the base of the utility pole in accordance with the utility company requirements.

Service cabinets and related equipment shall be UL listed as suitable for use as service equipment.

Service equipment enclosures shall be "Type III M" (metered), suitable for outdoor installation, NEMA 3R construction and shall conform to the provisions of CTSS Section 86-1.02. "Regulations and Code." Equipment enclosures shall be fabricated from cold rolled sheet steel, 12 gauge exterior, 14 gauge interior, welded by the wire fed inert gas process. All welds shall be around smooth. Doors shall be padlockable and vandal resistant. Door hinges shall be continuous stainless steel piano type. No screws, rivets, or bolts shall be visible outside the enclosure. Measurements of the enclosure shall conform to those shown on the plans. Inside dead-front door and back panel shall be white.

Service Cabinet Painting.

All controller cabinets shall be painted City of San Jose approved white.

The controller cabinets shall have a minimum of 0.08 mm of an aliphatic urethane self priming color coat followed by a minimum of 0.03 mm aliphatic urethane Wasser Mc-Antigraffiti clear coating or an approved equivalent. Use over a phosphatized treated or abraded surface. All coatings shall be compliant to the current VOC requirements.

Each service equipment enclosure shall be factory pre-wired conforming to the plans and specifications and delivered to the job site ready to bolt to the foundation and connect to service and load wires. The Contractor shall furnish 3 sets of wiring diagrams showing location and describing components and wiring connections. One set shall be scaled in plastic and attached to the inside of the cabinet door.

Circuit breakers shall be installed in dead-front panels. For service cabinets, which have both unmetered and metered sections, provide a separate main disconnect means for the metered and the unmetered service sections of the cabinet. Service disconnecting means shall be designed to disconnect all undergrounded conductors simultaneously.

Service equipment enclosure wiring shall conform to NEMA class II C. Wiring troughs shall be provided in the enclosure as necessary. Control wiring shall be 7 strand copper, Number 14 AWG with type TW insulation, except for hinge wiring, which shall be 19 strand copper, Number 14 AWG with type THWN insulation. Wiring shall be arranged so that any piece of apparatus. All wiring shall be marked with permanent clip sleeve wire markers, felt, pencil, or stick back marker will not be acceptable.

The nameplates shall be phenolic, black background with white lettering except main breaker(s) which shall be red with white lettering. If an alternate design is proposed for the service equipment enclosure, plans of such design shall be submitted to the Engineer for review and approval.

For service cabinets which have both unmetered and metered sections, provide a separate main disconnect means for the metered and unmetered service sections of the cabinet. Service disconnecting means shall be designed to disconnect all ungrounded conductor simultaneously.

PAINTING

All service and controller cabinets shall be painted.

Two applications of painting shall be applied to the equipment mentioned above.

Reused equipment previously finished as specified in CTSS Section 86-2.16 except for galvanized standards shall be given a spot finishing application on newly primed areas, followed by one finishing application over the entire surface.

Equipment number shall be applied to standards through the use of adhesive labels in accordance with the details indicated in "Standards" elsewhere in these special provisions, after all finish painting or galvanizing has been formed. The number designation will be by the Engineer.

CONTROLLER ASSEMBLIES

Traffic Signal Controller/Cabinet Assemblies

The Contractor shall furnish the controller/cabinet assemblies required on this project.

The traffic signal controller/cabinet assemblies shall be IDC Traconex Multisonics Model 28025225-004 or an approved equivalent. Assemblies shall conform to the specifications contained herein.

If the Contractor proposes to supply IDC Traconex MulitsonicsModel 28025225-004 traffic signal controller/cabinet assemblies, all required assemblies shall, within 60 calendar days of the award of contract, be delivered to the Department of Transportation Signal Maintenance Section located at 1404 Mabury Road.

If the Contractor proposes to supply traffic signal controller/cabinet assemblies other than IDC Traconex Multisonics Model 28025225-004, City approval will be required. In such event, the Contractor shall, within 60 calendar days of the award of contract, deliver to the Department of Transportation's Signal Maintenance Section a sample assembly for

evaluation. The City will notify the Engineer and the Contractor of the results of its evaluation of the sample assembly within 15 calendar days of its receipt by the City.

Should the sample assembly be approved by the City, the Contractor shall, within 60 calendar days of notification, deliver to the City the balance of the assemblies required under the contract.

Should the sample assembly not be approved by the City, it will be returned to the Contractor. The Engineer may then, require the Contractor to submit an alternative sample assembly. This procedure may be repeated as many times as necessary until an approved assembly is submitted.

Full compensation for submitting sample traffic signal controller assembles shall be considered as included in the contract lump sum price for Signal and lighting (city street location 1) and no separate payment will be made therefor.

When all required traffic signal controller and cabinet assemblies have been received, the City will test the assemblies and prepare them for installation as outlined below.

The Contractor shall furnish anchor bolts and shall construct the foundations for the cabinets. The Contractor shall, upon notification of completion of testing, pick up the cabinets (minus controllers and auxiliary equipment) from the Department of Transportation's Signal Maintenance Section. The Contractor shall deliver the cabinets to the job site, install them on the foundations and make all field wiring connections to the terminal blocks. City forces will, immediately prior to signal activation, deliver the controllers and auxiliary equipment to the job site and install them in the cabinets.

TYPE 'P' CABINET SPECIFICATIONS

Description of Cabinets

The traffic signal controller cabinets shall be wired for eight phases, such that they are compatible with NEMA Type 90 controllers. Cabinets shall be provided with all auxiliary equipment necessary for eight-phase operation including conflict monitor, flasher, flash relays, detectors and load switches. Typical cabinets can be inspected by contacting the Engineer and the City of San Jose Electrical Maintenance Foreman, at (408) 277-5515.

Cabinet wiring shall conform to all applicable parts of section 86 of the State of California 1988 Standard Specifications and these Special Provisions. In the event of a conflict between the Standard Specifications and these Special Provisions, these Special Provisions shall apply.

Component designations refer to the City of San Jose "P" cabinet Load Bay Assembly drawing. All wiring shall be in accordance with this drawing, except as required for system interface termination panel.

Each cabinet shall be furnished with a system interface termination panel installed as described in these Special Provisions.

Wiring

Flat ribbon type cable shall not be used in lieu of individual conductors for any of the cabinet wiring.

All conductors used in the cabinet shall be at least No. 22 AWG, with a minimum of 19 wire strands. These conductors shall meet military specification MIL-W-16878D type BN. Conductors larger than No. 14 AWG may be UL type THHN, with a minimum of 7 copper strands.

Two No. 10 AWG conductors will supply AC power to the load switch sockets.

The load switch sockets shall be supplied alternately (every other socket) by each conductor.

All cabling and wiring shall be neat, firm and routed to minimize electrical interference. Whenever possible, DC signal conductors shall be separate from AC wiring.

All unsoldered terminations shall be labeled with the proper terminal number.

Whenever more than two unsoldered terminations occur at the same point, appropriate stacking terminals shall be used.

All termination points on the terminal blocks shall be labeled with the designation on the cabinet wiring drawing. This can be done by either engraved strips mounted on the terminal blocks or silk-screening these designations next to the terminal blocks. All labeling shall be visible after wiring is installed.

All conductors, terminals or parts which could be electrically hazardous to maintenance personnel shall be protected with suitable insulating material.

There shall be no conflict monitor disabling switch installed.

Each cabinet shall have a separate door-actuated switch (SW24) that will monitor and report to the controller the status of the cabinet door, open or closed.

SUB-ASSEMBLIES

General

All wiring and harnesses entering or leaving these sub-assemblies shall be jacketed in cloth or other suitable material.

All terminal strips shall be mounted on metal plates of a minimum 3.3 mm thickness. All terminal strips, with the exception of the feed-thru for terminals 249-260, shall be the dual-inline barrier-type with two terminal positions and a shorting bar per pole.

All dual in-line terminal strips, except for those noted on the print with solid black dots, shall have links between the A and B sides.

Power Sub-Assembly

Material:

1). 1 ea. 50 Amp Circuit Breaker (CB-1)
2). 1 ea. 15 Amp Circuit Breaker (CB-2)
3). 1 ea. 50 Amp Suppressor (RIS)
4). 1 ea. Mercury Contactor (MC)
5). 1 ea. Surge Suppressor
6). 1 ea. MOV, GE-v130LA, 20 Amp
7). 2 ea. Copper Bus (GB-1,GB-2)

GB-1 shall be insulated from the panel and the controller cabinet. GB-2 shall be bonded to the cabinet. Both bus bars shall be 170 mm x 12.7 mm x 6.35 mm solid copper. Bus bars shall be drilled and tapped to accept a minimum of 12, 10/32X25 mm truss head screws. These screws shall be provided as part of the sub-assembly.

The Power Panel and associated components shall have a transparent, easily removable cover over the face, top and sides to prevent accidental contact with energized electrical parts. The cover shall be at least 3.75 mm thick. The cover shall not interfere with the normal operation of any components and shall not inhibit visual confirmation of the operational status of the breakers.

All wire terminations shall be visible for maintenance inspection without the removal of any components or covers.

All breakers shall have a minimum interrupting capacity of 10,000 amperes, RMS.

Fan and Light Sub-Assembly

Material:

1). 1 ea. Terminal Block, 4 position, medium duty
2). 1 ea. Dual Fuse Block
3). 2 ea. 1 Amp Fuse, AGC-1
4). 1 ea. Thermostat, Therm-O-Disk AF-1 or equivalent
5). 2 ea. RC Network, Rifa PMR-2022 or equivalent
6). 1 ea. 15 watt Fluorescent Fixture, with rapid start lamp and ballast.
7). 1 ea. Fan, Rotron # 028-021 or equivalent
8). 1 ea. Pushbutton Door Switch (SW23)

The cabinet light fixture shall be located so that the detector amplifiers on the top shelf of the controller cabinet are accessible and easily removed.

The door switch (SW23) shall be mounted on the cabinet so that complete closure of the cabinet door shall actuate it, turning off the cabinet light.

The fan shall be located on the mountings provided in the cabinet. The fan shall be positioned such that air will be exhausted from the cabinet.

Test/Police Panel Sub-Assembly

Material:

1). 16 ea. Pushbutton Switches (SW7-22)
2). 2 ea. SPDT Switch, on-on (SW4-5)
3). 1 ea. DPDT Switch, on-on (SW2)
4). 1 ea. SPST Switch, on-off-on (SW3)
5). 1 ea. DPDT Signals Switch, on-off (SW1)
6). 2 ea. SPST Door Switch, Momentary Normally Closed (SW23-24)

The following switches shall be rated at a minimum of 6 amps at 125 volts: SW7-22, SW3.

The following switches shall be rated at a minimum of 15 amps at 250 volts: SW1-2, SW4-5.

The following switches shall be rated at a minimum of 6 amps at 125 volts and shall have a minimum of 6 mm overtravel: SW23, SW24.

The Test/Police panel sub-assembly shall be located directly behind the cabinet police door. All devices shall be labeled with the identification on the load bay assembly print using epoxy ink silk-screening.

All switches in the police and maintenance panel shall be individual switches. They shall be hand wired and the wires shall be directly soldered to the switches.

Detector Panel Sub-Assembly

Material:

1). 9 ea. 12 position terminal strip, Marathon #1512DJ or equivalent
2). 1 ea. Copper Bus (GB-3)

GB-3 shall be mounted on the lowest detector terminal panel. A No. 12 AWG copper conductor shall be used to connect GB-2 with GB-3. GB-3 shall be constructed the same as GB-1 and GB-2.

Detector Rack Sub-Assembly

All Detectors shall be rack mounted NEMA type TS1-1989 Section 15.2.28.3 and shall conform to the rest of NEMA standards for Traffic Control Systems, Publication TS1- 1989 Section 15.

Each "P" cabinet shall be capable of a minimum of 36 channels of detection, (24 vehicle detectors and 12 system detectors). This shall be accomplished through three detector racks. Detector racks No. 1 & 2 shall be for vehicle call detectors and pedestrian calls. Detector rack No. 3 shall be for system detectors and pre-emption .

The racks shall be securely mounted on the top cabinet shelf, in the following order viewed from the front of the cabinet, from left to right, detector rack No. 1 - 2 - 3.

Each detector rack shall be constructed and wired to accommodate any arrangement of two and four channel detector modules totaling a minimum of 12 detector channels. Also racks No. 1 & 2 shall have 4 channels for pedestrian calls. And rack No. 3 shall have two channels of pre-emption, one for RR1 and one for EV1.

Detector racks No. 1 & 2 shall be wired to accommodate phase green signal conditioning as required by delay or extension timing type detectors.

All the wiring to the detector racks shall be plug removable.

Detector rack sockets shall be hand wired and not printed circuit board mounted. The wires between the terminal block and the sockets shall have a minimum of three twists per foot to eliminate interference.

The connectors for the programming card, detectors, 244 isolation module, 252 isolation module, shall mate with a 44 terminal, double row, 0.156 inch contact spacing, Cinch-Jones card edge connector #50-44a-30M, or equivalent.

The card guides shall conform to the State of California Standard Specifications section 86-3.09. In detector racks No. 1 & 2 the extreme right position in the rack as viewed from the front shall be constructed and wired for a 244 four channel DC isolation module. The four channels shall be wired to the following.

RACK NO. 1

Channel 1 = Ped call phase 2
Channel 2 = Ped call phase 4
Channel 3 = Ped call phase 6
Channel 4 = Ped call phase 8

RACK NO. 2

Channel 1 = Ped call phase 1
Channel 2 = Ped call phase 3
Channel 3 = Ped call phase 5
Channel 4 = Ped call phase 7

In detector rack No. 3 the extreme right position in the rack as viewed from the front shall be constructed and wired for a 252 two channel AC isolation module. The two channels shall be wired to the following.

RACK NO. 3

Channel 1 = RR1
Channel 2 = EV1

A detector programming card shall be provided and used in detector racks No. 1 & 2. The program card shall occupy the extreme left (Slot No. 1) position in each rack as viewed from the front.

The program card shall be constructed so any of the detector outputs for the detector rack can be wired to any of the controller vehicle detector inputs by installing soldered wire jumpers on the program card. In addition, any detector channel's Delay/Extension enabling input shall be able to be wired to any vehicle phase green output driver from the controller by installing soldered wire jumpers on the program card.

DETECTOR RACKS No. 1 & 2 PROGRAM CARD PIN USAGE

Pin – Functions:

1. Controller phase 1 vehicle call detector input
2. Controller phase 2 vehicle call detector input
3. Controller phase 3 vehicle call detector input
4. Controller phase 4 vehicle call detector input
5. Controller phase 5 vehicle call detector input
6. Controller phase 6 vehicle call detector input
7. Controller phase 7 vehicle call detector input
8. Controller phase 8 vehicle call detector input
9. Phase 2 vehicle green output driver from controller
10. Phase 6 vehicle green output driver from controller
11. Detector rack slot 2 channel 1 DEL/EXT enable input
12. Detector rack slot 2 channel 2 DEL/EXT enable input
13. Detector rack slot 3 channel 1 DEL/EXT enable input
14. Detector rack slot 3 channel 2 DEL/EXT enable input
15. Detector rack slot 4 channel 1 DEL/EXT enable input
16. Detector rack slot 4 channel 2 DEL/EXT enable input
17. Detector rack slot 5 channel 1 DEL/EXT enable input
18. Detector rack slot 5 channel 2 DEL/EXT enable input
19. Detector rack slot 6 channel 1 DEL/EXT enable input
20. Detector rack slot 6 channel 2 DEL/EXT enable input
21. Detector rack slot 7 channel 1 DEL/EXT enable input
22. Detector rack slot 7 channel 2 DEL/EXT enable input

A. Detector rack slot 2 channel 1 detector output
B. Detector rack slot 2 channel 2 detector output
C. Detector rack slot 3 channel 1 detector output
D. Detector rack slot 3 channel 2 detector output
E. Detector rack slot 4 channel 1 detector output
F. Detector rack slot 4 channel 2 detector output
H. Detector rack slot 5 channel 1 detector output
J. Detector rack slot 5 channel 2 detector output
K. Detector rack slot 6 channel 1 detector output
L. Detector rack slot 6 channel 2 detector output
M. Detector rack slot 7 channel 1 detector output
N. Detector rack slot 7 channel 2 detector output
P. Unassigned
R. Unassigned
S. Unassigned
T. Unassigned
U. Phase 1 vehicle green output driver from controller
V. Phase 3 vehicle green output driver from controller
W. Phase 4 vehicle green output driver from controller
X. Phase 5 vehicle green output driver from controller
Y. Phase 7 vehicle green output driver from controller
Z. Phase 8 vehicle green output driver from controller

The program card shall be compatible in regard to the physical dimensions and card connector pin usage with the program cards presently used by the City of San Jose. The following is a list of the Program Card Pin Usage.

In detector rack No. 3, no program card shall be required. Instead, the detector outputs shall be wired to the system interface termination panel as follows:

Detector Rack Position - System Detector Number:

Slot 2/Channel 1	1
Slot 2/Channel 2	2
Slot 3/Channel 1	3
Slot 3/Channel 2	4
Slot 4/Channel 1	5
Slot 4/Channel 2	6
Slot 5/Channel 1	7
Slot 5/Channel 2	8
Slot 6/Channel 1	9
Slot 6/Channel 2	10
Slot 7/Channel 1	11
Slot 7/Channel 2	12

DETECTOR RACK AUXILIARY POWER SUPPLY

The power supply shall be plug removable and shall have a MS3106A-18-1P connector.

Pin Assignments:

A	Chassis ground
B	-24 VDC logic ground
C	AC + 120 volts, Hot
G	+24 VDC output
H	AC - 120 volts, Neutral

The power supply shall be series-regulating type. It shall provide positive 24 (+ 0.5) volts DC output with one (1) % regulation or better over an AC line voltage variation from 95 to 135 volts and from no-load to full-load. Current capability shall be a minimum of four (4) amperes continuous, and with less than 0.5 volts peak-to-peak ripple. It shall be fused and the fuse shall be located on the power supply. It shall be possible to replace the fuse without removing the case.

Loadbay Sub-Assembly

Material:

1) 9 ea. 20-Position feed-thru terminal strip, Kulka #601-2104-20 or equivalent
2) 4 ea. 12-Position terminal strip, Marathon #1512DJ or equivalent
3) 1 ea. 12-Position feed-thru terminal strip, Kulka #601-2104-12 or equivalent
4) 1 ea. 12-Position feed-thru single line terminal strip, Kulka #1691A
5) 14 ea. 12-Position socket, Beau #S-4412AB or equivalent
6) 5 ea. 8-Position socket, Beau #S-4408AB or equivalent
7) 1 ea. 6-Position socket, Beau #S-4406AB or equivalent
8) 2 ea. 8-Position round socket, for KRP type relay
9) 1 ea. RC Network, Rifa PMR-2022 or equivalent

Controller cabinet Type P shall have a minimum of 14 load switch positions.

The loadbay sub-assembly shall be mounted in the cabinet so as to allow easy access to the back of the panel. The loadbay shall be fastened with hinges near the bottom rear of its point of attachment to the cabinet. It shall be possible, by removing no more than two fasteners at the top of the loadbay, to swing the loadbay downward and gain access to the rear of the loadbay and its wiring.

A support for the 14 load switches and flasher shall be provided. The controller and conflict monitor harnesses shall have the appropriate connectors for a standard NEMA Type 90 controller (A,B,C) and NEMA Type 12 conflict monitor (CM-1,CM-2).

All controller harnesses shall be wired to terminal blocks on the loadbay assembly. All wiring, with the exception of the field wiring shall be done on the rear of the assembly.

The conflict monitor (Green, Yellow, Red, Walk) wiring shall be wired to the field wiring terminals.

All equipment connecting cables shall have full length conductors on each connector pin, and all unused or spare conductors shall be labeled with the connector origin and appropriate pin designation.

Convenience Receptacle

The convenience receptacle shall be a duplex receptacle GFCI 20 amp specification grade minimum. The receptacle shall be mounted in a readily accessible location inside the right lower half of the cabinet.

Filter

Filter size shall be 300 mm x 400 mm x 25 mm. The filter media shall be self-extinguishing non-woven cotton and synthetic fibers. The media shall be bonded to a 28 gauge corrosion resistant, expanded metal support grid with a 95% open face area.

The media grid shall be bonded to the "high wet strength" beverage board frame. There shall be a minimum of 12 pleats per 305 mm, and shall contain not less than 149 square millimeters of effective filtering media per 305 mm of face area.

Filters shall have a rated efficiency of 30 to 35% and an average arrestance of 90-93%.

Cabinet Construction and Painting

All controller cabinets shall be aluminum and shall be painted City of San Jose approved white.

The controller cabinets shall have a minimum of 0.08 mm of an aliphatic urethane self priming color coat followed by a minimum of 0.03 mm aliphatic urethane Wasser Mc-Antigraffiti clear coating or an approved equivalent. Use over a phosphatized treated or abraded surface. All coatings shall be compliant to the current VOC requirements.

Prints

Each cabinet shall be supplied with two complete sets of cabinet prints and necessary drawings, schematics and manuals. After the completion of testing and the installation of the cabinets, the contractor shall supply two complete corrected sets of cabinet prints, drawings, schematics and manuals of any of the changes made to any of the equipment. The contractor shall supply a mylar master of the corrected cabinet prints.

SYSTEM INTERFACE TERMINATION PANEL SPECIFICATIONS

General

Facilities shall be provided in each controller cabinet for termination of communications and interface connections as required for system operation. These terminations shall be made on a separate panel which shall be furnished and installed in cabinets provided under this contract.

Each termination panel provided shall include all wiring harnesses necessary for connection to the controller's system interface connector(s), and any other wiring from the controller that is not part of the standard NEMA A, B, and C harnesses.

A panel layout indicating all required facilities and panel size is shown in Figure 1. Prior to fabrication of these panels, shop drawings shall be submitted by the Contractor and approved by the City.

System Interface Terminations

The termination panel shall have provisions for termination of all interface signals external to the controller. These shall include, but not be limited to, the following:

System Detector 1	System Detector 2
System Detector 3	System Detector 4
System Detector 5	System Detector 6
System Detector 7	System Detector 8
System Detector 9	System Detector 10
System Detector 11	System Detector 12
System Special Function 1 (In)	System Special Function 1 (Out)
System Special Function 2 (In)	System Special Function 2 (Out)
Modem Transmit (Tip)	Modem Transmit (Ring)
Modem Receive (Tip)	Modem Receive (Ring)
Modem Transmit Data	Modem Receive Data
Modem Request-to-Send	Modem Clear-to-Send
Modem Carrier Detect	Local Special Function 1
Local Special Function 2	Local Special Function 3
Cabinet Door Switch	Cabinet Flash Monitor
Conflict Flash Monitor	Logic Common (Gnd)

Communication Terminations

In addition to the system interface terminations, the panel shall have provisions for communications terminations. The panel shall include a 50-position 66-block for communications cable termination/splicing, surge protection for the active data and voice pairs, barrier strip termination of all active pairs, and two voice jacks.

CONSTRUCTION

Panel

The termination panel backplate shall be constructed of 5052 sheet aluminum alloy with a minimum thickness of 3.7 mm. The backplate shall be prepared from a single sheet of material. No seams or joints of any kind will be permitted. All edges and holes shall be smooth and free of burrs. The backplate shall be painted as described for the cabinet interior elsewhere in these Special Provisions. The backplate will be drilled as necessary to mount the barrier strips and other attachments.

Screw-Type Terminal Blocks

All system interface terminations shall be made on terminal blocks mounted on the termination panel. The terminal blocks shall be dual in-line barrier type, with two terminal positions and a shorting bar per pole. All terminal blocks shall be provided with nickel, silver or cadmium plated brass binder head screw terminals on 10 mm centers. All terminal blocks shall have a closed back design to prevent accidental contact with the panel backplate.

Quick-Clip Terminal Blocks

The communications cable terminal block shall be a 66-type connecting block with quick clip connections. The block shall have side mounting ears to minimize the height of the block. The block shall be sized 50 rows by 6 clips, with the clips split electrically and mechanically into two sets of three clips in each row

Fifty (50) bridging clips shall be supplied with each block (not installed).

Surge Protection Modules

The surge protection modules shall be the EDCO PC-642 or approved equivalent with associated mounting sockets. Each module shall provide protection for two pair. One module shall be provided the active data communications pairs and one module shall be provided for the voice pairs.

The data pair modules shall provide two-stage protection with a clamp voltage of 8 volts and a line-to-line second stage clamp. The voice pair modules shall provide single-stage gas tube protection with a clamp voltage of 240 volts.

The surge protector mounting bases shall be wired on the panel for the appropriate terminal, harness, and voice jack connections.

Voice Communication Jacks

Two voice communications jacks shall be provided on each panel. The jacks shall accept standard 6.25 mm phone plugs and shall have silver-plated contacts. The jacks shall be mounted such that the tip and ring of each jack are isolated from ground. The jacks shall be enclosed with a molded body. The jacks shall be prewired to the appropriate terminals for connection to the surge-protected voice pairs.

Terminal Identification

All terminals shall be labeled as to signal and/or function, using black enamel in a silk-screen process upon a properly prepared panel surface. The legends shall be in alignment with the terminal strips, and shall consist of block letters at least 3 mm in height.

Wiring Specifications

All wiring used on the termination panel and in the harnesses shall comply with the minimum requirements for cabinet wiring contained elsewhere in these specifications.

SIGNAL CONTROLLER SPECIFICATIONS

Solid State Traffic Actuated Controllers

Solid state traffic actuated controller units shall conform to the Standard Specifications and these special provisions.

A. Integrated circuit components, excepting those on the front panel of the controller unit, shall be socket mounted. Direct mounting of these components to any other printed circuit board is not acceptable. All IC mounting sockets

shall be machined, not stamped. All printed circuit boards shall be conformal coated. Solder mask is not acceptable as "conformal coating."

B. Circuits, components and software shall exist in the unit to allow for full expansionability, including, but not limited to, internal coordination, internal time based coordination, internal preemption, detector data acquisition from up to 16 local detectors.

C. The unit shall incorporate and include an internal 202, 1200 Baud rate, two channel communications modem. Both channels of communication will be active during normal controller operation.

D. Printed circuit board connectors shall be of the DIN type and conform to Mil C 55302. They shall be located so that it shall not be possible to insert the module upside down.

E. The controller housing shall consist of a two-piece die cast "NORYL" high impact plastic case separable by use of a screwdriver.

F. The controller shall be capable of providing the following on a per phase basis:

a. All NEMA intervals and operations.
b. Conditional Service.
c. Four programmable overlaps.
d. Soft recall, dimming by color, by phase, and by selectable percentages.
e. Two Separate Max timings per phase plus conditional minimum timing during conditional service, plus coordination MAX timing during coordination.
f. Dynamic Split Adjustment (DSA)
g. Front panel selectable NEMA overlaps with auxiliary timing.
h. Detector delay or extension functions as well as system detector disconnect functions shall be internally programmable in the controller.

G. The controller shall have the following capabilities when operating as a local controller in a system mode:

a. The unit shall revert to standby back-up coordination which will be enabled after two consecutive invalid commands from the master.
b. The back-up coordination parameters will be stored in the time of day plans, (TOD).
c. The unit shall revert back to system control upon receipt of two valid commands from the master.

H. The controller shall have an integral traffic surveillance capability as a standard feature.

I. The controller shall be capable of monitoring the operation of system detectors and storing the failure data for system retrieval.

J. Controller unit shall have a selectable feature that shall enable termination of a phase by NEMA phase maximum timer rather than by phase split division while operating in coordinated mode.

TRAFFIC SIGNAL FACES AND FITTINGS

Traffic Signal Equipment.

Traffic signal equipment shall include the traffic signal head (vehicular and pedestrian) consisting of an assembly containing one or more signal faces together with optical units, the assembly housing, mountings, and other appurtenant devices.

Signal assemblies shall meet the requirements of the latest edition of FM Publication "Adjustable Face Vehicular Traffic Control Signal Heads," in addition to the requirements contained herein.

Vehicle Signal Faces.

The type of mountings to be used shall be as indicated on the Plans.

Signal sections shall be metal. Plastic signal sections shall not be allowed. Vehicle signal heads mounted on mastarms shall have 300 mm sections. Vehicle signal heads for left turn indications shall have all 300 mm arrows.

Signal faces shall be the adjustable, colored light, vertical type with the number and type of lights (faces) shown on the plans. Each signal face shall provide an indication in one direction only.

Optical Units.

Each reflector, lens, and hood shall be designed in such a manner as to reduce sun phantom to a minimum. The lens design shall produce high illumination transmission, and outward and downward distribution, with minimum of light distributed above the horizontal. Lamp receptacle openings in reflectors shall be designed so that there will be no dark spots cast on the lens.

LED Modules and lamps for signal assemblies shall be State-furnished as provided under "Materials" of these special provisions.

Signal Sections.

Each signal section housing shall be either die-cast or permanent mold-cast aluminum conforming to ANSI Standard: D-10.1. Plastic signal sections shall not be used.

Each signal section shall be constructed in such a manner that structural failure of the housing will not occur with a wind load pressure of 70 kg per square meter on the projected area of the complete signal face housing, including back plate and visors.

A sample, consisting of a complete signal section assembly, with the optical unit. shall be submitted for testing prior to acceptance of any design or fabrication method not previously tested and accepted by the City.

The signal face housing, or case shall consist of an assembly of separate interchangeable sections, expansible type for vertical mounting without tie rods, substantially secured together in a water tight manner to form a unit. Each section shall house an individual optical unit.

Each section shall be complete with a one-piece, hinged door mounting for the lens and other parts of the optical system, watertight gaskets, and simple door locking device. The optical system shall be so mounted that the various parts may be swung open for ready access or removal. The sections shall be interchangeable and so constructed that sections can be removed or added.

Electrical Components.

Lamp receptacles shall have a heat resistant molded phenolic housing and shall be designed to accommodate standard traffic signal lamps, ANSI Designation A21 or P25. The lamp receptacle shall be capable of positioning the lamp at the exact focal point of the reflector. The lamp receptacle shall provide proper lamp filament orientation without affecting lamp focus.

The lamp receptacle conductors shall be connected to the shell of the lamp receptacle by an approved mechanical method. Solder shall not be used for the only means of conductor attachment to the lamp receptacle shell.

Visors.

Each signal section shall be provided with a removable metal visor conforming to ANSI Standard D-10.1. Plastic visors shall not be used.

Backplates.

Metal backplates shall be furnished and installed on all vehicle signal faces. Plastic backplates shall not be used.

Backplates shall be constructed of 5052-H32 aluminum alloy sheet 1.3 mm minimum thickness, and of the dimensions shown on the plans.

Pedestrian Signal Faces.

Pedestrian signal faces shall be type A. Type B and C shall not be used.

a. Type A.--Each message plate shall be one piece and shall be made of 4.7 mm tempered glass. Polycarbonate plastic shall not be used. Lamps for pedestrian signal assemblies shall be incandescent, ANSI Designation A21, suitable for horizontal operation with medium base, 130-volt, 8,000 hour rated life, clear traffic signal lamps with an initial rated output of 685 lumens.
b. Front Screen.--A front screen shall be provided on each Type A signal face. The front screen shall be of the 41 mm deep eggcrate or Z-crate type. Aluminum honeycomb screens shall not be used. The screen and frame shall be fabricated from aluminum anodized flat black or finished with flat black enamel Flat black plastic shall not be used.

LED modules and lamps for pedestrian signal assemblies shall be State-furnished as provided under “Materials” of these special provisions.

Signal Mounting Assemblies.

Signal mounting assemblies shall conform to CTSS 86-4.06 Signal Mounting Assemblies. All mounting assemblies shall be painted as specified in "Painting" elsewhere in these specifications.

DETECTORS

Vehicle Detectors.

Circuitry shall be solid state including the output circuit. Relays shall not be used. The detector delay/extension enable circuit, when activated with a "low" state voltage, shall inhibit the delay detector operation.

Splices shall be insulated by Type C handcrafted insulation. Methods A and B shall not be used.

Detector lead-in cables shall be continuous without splices, from the controller cabinet detector panel terminal block to the loop termination pull box.

Construction Materials.

Conductors for inductive detector shall be continuous and unspliced and shall be Type 1 loop wire. Type 2 loop wire shall not be used. Loop detector lead in-cables shall be Type B, unless specified otherwise.

Installation Details.

Installation and testing shall conform to the details and notes shown in the plans, CTSS Section 86-2.14 "Testing " and these specifications.

Unless specified otherwise, each loop shall consist of the number of turns of conductor as shown in the plans and shall be constructed of the material as specified in CTSS Section 86-5.O1A(4), "Construction Materials."

All detectors to be installed in the structure, shall be preformed loops.

For detectors to be installed in the ground, sawcut slots shall be cut into the pavement to the depth and width shown on the plans and at the location laid out by the Engineer. Sawcuts shall be overlapped at all corners so that slots are full depth at the corners. The bottom of the sawcut slots shall be smooth and even.

After conductors are installed in the slots cut in the pavement, 4 mm strips of diameter foam backer rod shall be inserted in the slot over the loop wires, spaced as necessary, but not more than 1.52 meters apart to prevent the loop wires from rising up in the slot when the slots are being filled with sealant. The slots shall be filled with sealant to within 3.1 mm of the pavement surface. The sealant shall be a minimum of 35 mm thick above the top conductor in the slot. Conductors in asphalt concrete pavement and within 1.2 meters of the lip of the gutter shall have a minimum cover of 78 mm. Before setting, surplus sealant shall be removed from the adjacent road surfaces without the use of solvents. The sealant for filling slots shall conform to the following:

a. Elastomeric Sealant.--Elastomeric Sealant shall conform to the requirements of CTSS Section 86-5.01A(5) "Installation Details". Elastomeric sealant shall be used only in Portland Cement concrete.
b. Asphaltic Emulsion Sealant.--Asphaltic Emulsion Sealant shall conform to the requirements of CTSS Section 86-5.01A(5), "Installation Details".

Loop conductors shall be installed without splices and shall terminate in the pull box indicated on the Plans. The loop conductors shall be spliced to the lead-in cables in the termination pull box adjacent to the loops. Each loop shall be provided with its own detector lead-in cable. Detector lead-in cables shall be continuous without splices between the loop termination pull box and detector panel terminal block in the controller cabinet. The shield and drain wire of the detector lead-in cable shall be grounded in the traffic signal controller cabinet only.

The start (S) and finish (F) conductors of each loop shall be permanently labeled with a (S) on the start conductor and a (F) on the finish conductor and then grouped together as a pair. The start (S) loop conductor shall be spliced to the black conductor in the lead-in cable and the finish (F) loop conductor to the white conductor in the lead-in cable. Each loop pair and lead-in cable shall be identified as to direction lane and signal phase in all pull boxes and in controller cabinets. Labeling shall conform to the provisions in CTSS Section 86-2.09B, "Installation."

The end of the lead-in cable shall be taped and waterproofed prior to installing in conduit to prevent moisture from entering the cable. Where loop conductors are not immediately to be spliced to a lead-in cable, the ends of both the loop conductors and lead-in cable shall be taped and waterproofed with an electrical insulating coating. If the ends of the loop and lead-in cable are left not taped and waterproofed for more than 24 hours the loop and the lead-in cable shall both be replaced at the Contractors expense.

All adjacent loops shall be wound in the same direction. No more than 4 loop conductors (2 twisted pairs) shall be installed in one home-run slot. Loop conductors for more than one signal phase shall not be combined in a common home-run slot.

Loops shall be set back 0.60 m from stop bar and shall be centered in lanes except for curb lanes greater than 3.6 meters where they shall be installed 9 mm from the lane line, unless specified otherwise. The distance between the side of the loop and the home-run saw cut from the adjacent loops shall be 6 meters minimum. The distance between home-run saw cuts shall be 152 mm minimum. Loop conductors shall be installed a minimum of 9 mm from any metal obstacles in the street such as metal manhole covers unless otherwise approved by the Engineer prior to installation.

If loops are to be installed in asphalt concrete pavement, the loop conductors may, at the Contractor's discretion, be installed either in the finished surface layer of asphalt concrete or in the compacted layer of asphalt concrete immediately below the uppermost layer.

Before installing loop conductors in the sawed slots, the slots shall be thoroughly washed with water and then blown out with compressed air and allowed to dry thoroughly.

The loop conductor shall be installed into the slot using a 1.8 mm to 6.35 mm thick wood paddle or roller designed and approved for the purpose. The conductors shall be carefully installed in the sawcut slots to prevent insulation damage. The loop conductors shall be loosely installed around the sawcut slot comers to prevent tension from being placed on the conductors at the corners.

The loop shall be wound in accordance with the plans unless otherwise specified.

1.22 meters of loop conductor slack for each loop, shall be left in the loop termination pull box.

The loop conductor home-run for each loop shall have its start (S) and finish (F) conductors twisted together into a pair (at least 3 turns per 0.3 m) before being placed in the home-run slot, conduit, and termination pull box.

Each loop shall be tested at the termination pull box before the slots are filled with sealant. Each loop shall not exceed 0.5 Ω circuit resistance and shall not measure less than 200 MΩ insulation resistance as measured with a 500 VDC megohmmeter.

The loop conductors shall be spliced to the detector lead-in cables using non-insulated crimp style butt splice connectors and soldered in accordance CTSS Section 86-2.09C "Connectors and Terminals."

In the loop termination pull box the outer jacket of detector lead-in cable shall be removed a maximum of 100 mm. The loop conductor to lead-in cable splices and the lead-in cable conductors back to and over to the lead-in cable jacket ending point shall be taped and water-proofed in accordance with Type C splice. The tape and waterproofing shall overlap the ending point of the outer jacket of the lead-in cable a minimum of 51 mm.

In the controller cabinet the outer jacket of the detector lead-in cable be removed between the cable termination point on the detector panel to the bottom of the controller cabinet.

Care shall be taken not to nick or otherwise damage the detector lea cable conductor insulation while removing the outer jacket.

The detector lead-in cable drain wire shall be terminated on the detector panel ground bus using spade lug terminals. Only one drain wire shall connected to each spade lug terminal.

All detector loop circuits shall be tested for circuit resistance, insulation resistance, and inductance at the controller cabinet with the drain wires terminate before final termination of the detector lead-in cable to detector panel terminal blocks.

The detector loop circuit resistance shall not exceed 0.5 Ω plus 0.35 Ω per 30 m of lead-in cable. The complete detector loop circuit insulation resistance shall not be lower than 100 meg-ohms between any conductor and ground. The complete detector loop circuit inductance shall be between 250 and 450 micro-henries for Type "C" loops and between 150 and 300 micro-henries Type "Q" loops.

The detector lead-in cables shall be terminated in the controller cabinet using non-insulated crimp style spade lugs and then soldered in accordance with CTSS Section 86-2.09C "Connectors and Terminals." The detector lead-in cable conductors shall be twisted together into a pair (at least 3 turns per 0.3 m) before termination on the detector panel terminal blocks.

Pedestrian Push Buttons.

Pedestrian push buttons shall be Type B as shown in CTSP. Types A and C shall not be used.

Pedestrian push buttons signs shall be porcelain enameled metal. Structural plastic signs shall not be used.

Pedestrian push-button housings shall be either die-cast or permanent mold cast aluminum. They shall be installed in sidewalk areas at the height of 1 meter. Where installed on the raised island with wheelchair openings, they shall be mounted .76 meter above the base of the pole.

LIGHTING

Low Pressure Sodium Luminaires.

All luminaires shall conform to ANSI performance standards and the provisions as specified herein.

Low pressure sodium luminaires shall be completely assembled and shall consist of a housing, reflector, refractor or lens, lamp socket, lamp support, integral ballast and removable ballast tray, terminal block, slip fitter and lamp.

Luminaires shall be of the enclosed type with a horizontal burning lamp. Luminaries shall be the semi cut-off type as classified by the IES, with a minimum total downward coefficient of utilization of 67 percent for 55 W luminaires and 59 percent for 90 W luminaires.

Luminaires shall be manufactured by a manufacturer who is now regularly engaged in the manufacture of street fighting luminaires.

Housing shall be of corrosion resistant die cast aluminum 1.6 mm minimum thickness, corrosion resistant aluminum sheet and plate with concealed continuous welds, or acrylonitrile butadiene styrene sheet material 2.38 mm minimum wall

thickness, in a cast aluminum frame that provides mounting for all electrical components and slipfitter. The housing shall be divided into optical and power compartments that are individually accessible for service and maintenance. Positioning and clamping of the luminaire to the pipe tenon shall be accomplished by tightening mounting bolts.

Housings shall be painted with a fused coating of electrostatically applied polyester powder paint or other ultraviolet inhibiting film. Color shall be aluminum gray.

A high temperature neoprene, or equal, sealing ring shall be installed in the pipe tenon opening to prevent entry of water and insects into the power and optical compartments.

Access to the power unit assembly shall be through a weathertight hinged cover secured with spring type latches or captive screws to the luminaire housing.

Hardware shall be stainless steel or cadmium plated. Machine screws or bolts shall be used to secure removable components. Sheet metal screws shall not be used.

Reflectors shall have a minimum reflection factor of 88 percent.

Refractors or lenses shall be one piece polycarbonate of 2.38 mm minimum thickness constructed to rigid maintain its shape, and hinged and secured to the luminaire housing with captive latches.

The refractor shall be capable of producing the light pattern and optical characteristics specified. The optical system shall produce the maximum usable light with minimum glare. Light distribution obtainable shall conform to IES standards.

Conductor insulations shall be a high temperature formulation suitable for use in street lighting luminaires.

All wiring connections shall be at terminals or made with quick-disconnect plugs that are polarized or keyed to prevent incorrect connections.

All luminaires shall have wiring diagrams, voltage ratings, lamp wattage and all other pertinent electrical data prominently and permanently displayed on a durable label in each luminaire. The label shall be conspicuous when the luminaire is open for servicing.

All parts shall be smooth and free of sharp edges. All mating parts shall fit together easily and without strain and wiring shall be neatly arranged.

No lurminaire supplied under this specification shall have appearance incompatible with those already in use in San Jose nor shall it have any feature making it impractical, unsafe or expensive to use and maintain.

Lamp socket of high temperature flame retardant material with self-wiping silver plated copper alloy contacts, shall be rated for 660 watts and 1,000 volts.

Lamp support shall maintain Positive lamp retention and position.

Terminal block shall be mounted to the inner support frame within the ballast compartment, pre-wired to the ballast and other integral controls if required and provide for quick disconnect for the removal of the integral ballast tray.

Integral ballast tray shall be removable and replaceable without the use of tools, and provide a single multi-circuit connector for quick and easy disconnection of the ballast tray.

Slipfitter shall mount onto standard 35 mm to 53 mm diameter by 172 mm long tenon and provide plus or minus 5 degree leveling with positive mounting lamps.

Low Pressure Sodium Lamp Ballasts.

Each ballast shall be designed for the type, characteristics and wattage of the lamp it is to operate and shall provide the proper starting and operating waveforms, voltage and current.

Ballasts shall be autotransformer or high reactance type. Ballast shall be multi-tap type for different voltage ranges. Ballast shall be an integral part of the luminaire and held securely in place with devices that allow easy and safe removal and replacement in the field without the necessity of removing the luminaire from the bracket arm.

The Power factor shall not be less than 90 percent when the ballast is operated at nominal line voltage.

Lamp wattage regulation shall not vary by more than plus or minus 6 percent for plus or minus 10 percent input voltage variation.

Lamp current crest factor shall not exceed 1.8 at line voltage.

Low Pressure Sodium Lamps.

Low Pressure Sodium shall conform to the applicable ANSI Standard for Lamp Designation L74-RF 135.

Lamps shall be:

55 W with minimum initial output of 8 000 lumens, or
90 W with minimum initial Output of 13,500 lumens or
135 W with minimum initial Output of 22,500 lumens
180 W minimum initial output of 33,500 lumens

Lamps shall have an average rated life of 18,000 hours operating a minimum of 10 hours per start. Lamp depreciation over life shall not exceed 2 percent.

Operating Position shall be horizontal plus or minus 20 degree.

Photoelectric Controls.

Streetlighting systems shall be switched as indicated on the plans. The control circuit wiring between the photoelectric unit and the contactor shall be installed as indicated on the plans. The photoelectric unit shall be normally oriented north or as directed by the Engineer.

Photoelectric Unit.

The supply voltage rating shall be 60 Hz, 105-130, 210-240 volts as specified or as required.

Contactor.

The contactor shall have 4 normally open poles rated to switch the breaking any specified lighting load rated 600 V, 60 Hz industrial duty or as indicated. The contacts shall be rated to switch the actual connected load, and not less than 30 A per contact. Contractors shall be capable of making and breaking any load within its rating without the assistance of auxiliary arcing contacts; arcing contacts are not permitted. All contacts must be removable without disturbing line or load wiring.

Contactor shall be electrically held with coil operating on 120 V and rated for continuous load. The contactor coil shall be fully encapsulated.

10-3.25 REMOVING, REINSTALLING OR SALVAGING ELECTRICAL EQUIPMENT

Salvaged electrical materials shall be hauled to Caltrans Electrical Maintenance Station, 30 Rickard Street, San Francisco, CA 94134 (415) 330-6509, and stockpiled.

The Contractor shall provide the equipment, as necessary, to safely unload and stockpile the material. A minimum of 2 working days' notice shall be given prior to delivery.

All salvaged equipment for traffic signal modification (City) shall be delivered to the San Jose Central Stores Warehouse, 1608 Las Plumas Avenue. Contact the Engineer and the City of San Jose Department of Transportation at (408) 277-5515, 48 hours prior to delivery of salvaged equipment.

10-3.26 PAYMENT

The contract lump sum price or prices paid for signal and lighting (City) shall include highway lighting at intersections in connection with signals only.

Full compensation for hauling and stockpiling electrical materials shall be considered as included in the contract price paid for the item requiring the material to be salvaged and no additional compensation will be allowed therefor.

The contract lump sum price paid for Lighting (City street) at various locations shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing Lighting (City street) at various locations, complete in place, as shown on the plans, as specified in the Standard Specifications and these Special Provisions.

The contract lump sum price paid for Lighting and Sign Illumination shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing Lighting and Sign Illumination, complete in place, as shown on the plans, as specified in the Standard Specifications and these Special Provisions.

The contract lump sum price paid for Traffic Operation System (TOS) at various locations shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing Traffic Operation System at various locations, complete in place, as shown on the plans, as specified in the Standard Specifications and these Special Provisions.

The contract lump sum price paid for Traffic Operation Systems (Stage Construction) shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing Traffic Operation Systems (Stage Construction), in place, including maintenance, removal and disposal of the temporary Traffic Operation Systems when no longer required, and potholing work prior to installation of temporary poles, as shown on the plans, as specified in the Standard Specifications and these Special Provisions.

The contract lump sum price paid for Traffic Operation Systems (County) shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing Traffic Operation Systems (County), complete in place, as shown on the plans, as specified in the Standard Specifications and these Special Provisions.

The contract lump sum price paid for Power and Communication (Santa Clara Valley Transportation Authority) shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing Power and Communication (Santa Clara Valley Transportation Authority), in place, including

maintenance, removal and disposal of temporary Power and Communication (Santa Clara Valley Transportation Authority) when no longer required, as shown on the plans, as specified in the Standard Specifications and these Special Provisions.

The contract lump sum price paid for Lighting (Stage Construction) shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing Lighting (Stage Construction), in place, including maintenance, removal and disposal of the temporary lighting when no longer required, and potholing work prior to installation of temporary poles, as shown on the plans, as specified in the Standard Specifications and these Special Provisions.

10-3.27 REMOVING, REINSTALLING OR SALVAGING ELECTRICAL EQUIPMENT

Salvaged electrical materials shall be hauled to Caltrans Electrical Maintenance Station, 30 Rickard Street, San Francisco, CA 94134, (415) 330-6509 and stockpiled.

The Contractor shall provide the equipment, as necessary, to safely unload and stockpile the material. A minimum of 2 working days' notice shall be given prior to delivery.

SECTION 11. MODIFIED STANDARD SPECIFICATION SECTIONS

SECTION 11-1. QUALITY CONTROL / QUALITY ASSURANCE

Asphalt concrete shall conform to the provisions in this Section 11-1, "Quality Control / Quality Assurance," and the section entitled "Asphalt Concrete" in Section 10-1, "General," of these special provisions. Section 39, "Asphalt Concrete," of the Standard Specifications shall not apply to Type A and Type B asphalt concrete.

SECTION 39: ASPHALT CONCRETE

39-1 GENERAL

39-1.01 DESCRIPTION

This work shall consist of furnishing and mixing aggregate and asphalt binder at a central mixing plant, transporting, spreading and compacting the mixture, and furnishing and placing pavement reinforcing fabric, in conformance with this Section 11-1, "Quality Control / Quality Assurance," and with "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

The Contractor shall be responsible for controlling the quality of the asphalt concrete product entering the work, including aggregate, asphalt binder, additives, and asphalt concrete mixture; for controlling the quality of the work performed, including mix design, and mixing, transporting, spreading, and compacting the asphalt concrete; for controlling the quality of the finished roadway surface; and for developing, implementing, and maintaining a quality control program. The Contractor shall be responsible for the inspection, sampling, and testing required to control the quality of the asphalt concrete and the work performed.

The inspection, sampling, and testing required to control the quality of the workmanship and the asphalt concrete shall conform to this Section 11-1. Sampling shall be in conformance with the requirements of this Section 11-1 and with California Test 125. Testing shall be performed using California Tests unless otherwise directed by the Engineer or this Section 11-1.

Asphalt concrete is designated as Type A or Type B. The type of asphalt concrete will be shown on the plans or specified in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

39-2 MATERIALS

39-2.01 ASPHALTS

Asphalt binder to be mixed with aggregate shall be steam-refined paving asphalt conforming to the provisions in Section 92, "Asphalts," of the Standard Specifications. Asphalt binder shall be Grade AR-4000 unless the grade is designated in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Liquid asphalt for prime coat shall conform to the provisions in Section 93, "Liquid Asphalts," of the Standard Specifications and shall be the grade designated by the contract item or conform to the provisions in "Asphalt Concrete," in Section 10-1, "General," of these special provisions.

Asphalt emulsion for paint binder (tack coat) shall conform to the provisions in Section 94, "Asphaltic Emulsions," of the Standard Specifications for the rapid-setting or slow-setting type and grade approved by the Engineer.

Paving asphalt to be used as a binder for pavement reinforcing fabric shall be a steam-refined paving asphalt conforming to the provisions in Section 92, "Asphalts," of the Standard Specifications, and shall be Grade AR-4000, unless otherwise ordered by the Engineer or designated in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

39-2.02 AGGREGATE

Aggregate and combined aggregate shall conform to the quality and gradation provisions in this Section 11-1, "Quality Control / Quality Assurance," for the asphalt concrete types and sizes conforming to the provisions in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Aggregates shall be clean and free from decomposed or organic materials and other deleterious substances. Coarse aggregate is material retained on the 4.75-mm sieve, fine aggregate is material passing the 4.75-mm sieve, and supplemental fine aggregate is added fine material passing the 600-µm sieve, including, but not limited to, cement and stored fines from dust collectors.

The target value for the percent passing each designated sieve size for the aggregate blend used in the proposed asphalt concrete mix design shall fall within the "Target Value Limits" of the following table:

Table 39-1 - AGGREGATE GRADATION
Type A and Type B Asphalt Concrete
Percentage Passing

19-mm Maximum, Coarse		19-mm Maximum, Medium	
Sieve Sizes	Target Value Limits	Sieve Sizes	Target Value Limits
25-mm	100	25-mm	100
19-mm	90-100	19-mm	90-100
9.5-mm	60-75	9.5-mm	65-80
4.75-mm	45-50	4.75-mm	49-54
2.36-mm	32-36	2.36-mm	36-40
600-µm	15-18	600-µm	18-21
75-µm	3-7	75-µm	3-8

12.5-mm Maximum, Coarse		12.5-mm Maximum, Medium	
Sieve Sizes	Target Value Limits	Sieve Sizes	Target Value Limits
19-mm	100	19-mm	100
12.5-mm	95-100	12.5-mm	95-100
9.5-mm	75-90	9.5-mm	80-95
4.75-mm	55-61	4.75-mm	59-66
2.36-mm	40-45	2.36-mm	43-49
600-µm	20-25	600-µm	22-27
75-µm	3-7	75-µm	3-8

During asphalt concrete production, aggregate gradation shall be within the limits specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Conformance with the grading requirements shall be determined by California Test 202, modified by California Test 105, when there is a difference in specific gravity of 0.2 or more between the coarse and fine portions of the aggregate or between the blends of the different aggregates. The percent passing the 75-µm sieve shall be reported to the first decimal place (tenths).

The combined aggregate shall conform to the following quality requirements prior to the addition of the asphalt binder:

Table 39-2 - AGGREGATE QUALITY REQUIREMENTS

Quality	California Test	Asphalt Concrete Type A	Asphalt Concrete Type B
Percent of Crushed Particles	205		
Coarse Aggregate (Min.)		90%	25%
Fine Aggregate (Passing 4.75-mm, Retained on 2.36-mm) (Min.)		70%	20%
Los Angeles Rattler	211		
Loss at 100 Rev. (Max.)		12%	
Loss at 500 Rev. (Max.)		45%	50%
Sand Equivalent (Min.)[1]	217	47	42
Kc Factor (Max.)	303	1.7	1.7
Kf Factor (Max.)	303	1.7	1.7

Note:
1. Reported value shall be the average of 3 tests split from a single sample.

39-2.03 ASPHALT CONCRETE MIXTURE

The asphalt concrete mixture, composed of the proposed aggregate blend and the proposed asphalt binder content as determined by California Test 367, shall conform to the following requirements:

Table 39-3 - ASPHALT CONCRETE MIXTURE REQUIREMENTS

Design Parameters	California Test	Asphalt Concrete Type and Location: Coast and Valley Type A	Coast and Valley Type B	Desert (per Engineer) Type A	Desert (per Engineer) Type B
Hveem Stabilometer Value (Min.)	367[1, 2]	37	35	37	35
Percent air voids (Mix Design)	367[1]	3-5[3]	3-5[3]	4-6[4]	4-6[4]
(Start-Up Production Evaluation)		Design Value ±1.0			
Swell [5] (mm) (Max)	305	0.76	0.76	0.76	0.76

Notes:
1. Reported value shall be the average of 3 tests from a single split sample.
2. If the range of stability for the 3 briquettes is more than 12 points, the briquettes shall be discarded and new samples shall be fabricated.
3. Modify California Test 367, paragraph C5, to "most nearly 4%."
4. Modify California Test 367, paragraph C5, to "most nearly 5%."
5. Measured at Mix Design only.

During production and placement, the asphalt concrete mixture shall conform to the requirements of Table 39-4, "Minimum Process Control Requirements," and Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Changes in cold feed or hot bin proportions to conform to the aggregate grading requirements shall not be considered changes in the mix design.

Whenever asphalt concrete production has been suspended for longer than 30 days, the Contractor, on the first day of resumption of production, shall sample and test the asphalt concrete to demonstrate conformance with the requirements of Table 39-3, "Asphalt Concrete Mixture Requirements," Table 39-4, "Minimum Process Control Requirements," and Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1.

The target value for asphalt content may be changed by as much as ± 0.2 percent during the production start-up evaluation specified in Section 39-10.02A, "Production Start-Up Evaluation," of this Section 11-1 or after production start-up evaluation and before the first day of regular production with the Engineer's approval. The Contractor shall demonstrate that asphalt concrete that has been produced through the plant using the modified target value for asphalt content is in conformance with this Section 11-1 by submitting test results for samples obtained from the first 500 tonnes of production. Stability and percent air voids shall be determined using 3 briquettes constructed from a single sample taken from 4 locations across the mat in conformance with the requirements of California Test 125.

Changes from one mix design to another shall not be made during the progress of the work, unless approved by the Engineer. Changes in asphalt content, other than those allowed during the start-up evaluation process, or in aggregate grading target values shall be considered to be a change in the asphalt concrete mixture and shall require a new mix design proposal. Changes in the asphalt content or aggregate grading target values approved by the Engineer will not be applied retroactively for acceptance or payment.

39-2.04 PAVEMENT REINFORCING FABRIC

Pavement reinforcing fabric shall conform to the provisions in Section 88, "Engineering Fabrics," of the Standard Specifications and these special provisions.

39-3 ASPHALT CONCRETE MIX DESIGN PROPOSAL AND REVIEW

39-3.01 CONTRACTOR MIX DESIGN PROPOSAL

The Contractor shall submit for the Engineer's review a proposed asphalt concrete mix design for each asphalt concrete mixture to be used at least 14 days prior to production of that asphalt concrete mixture. The asphalt concrete mix design shall be prepared by a laboratory (or laboratories) whose proficiency has been reviewed and qualified in conformance with the Department's Quality Assurance Program. Aggregate quality and asphalt concrete mix design test results shall be no more than one year old when production of the asphalt concrete mixture starts. For projects of more than one year's duration, asphalt concrete may be produced using the asphalt concrete mix design that was reviewed and accepted at the start of the project provided the asphalt concrete mixture continues to conform to the provisions of this Section 11-1, "Quality Control / Quality Assurance."

The Contractor shall submit a mix design letter that indicates the target values proposed for gradation, asphalt content, and percent air voids. This submittal shall include test results for aggregate and asphalt mixture quality; plots of the combined gradings showing the production tolerances; plots of unit weight, stability, and percent air voids versus asphalt content for the asphalt contents considered in the design process. In addition, this submittal shall include test results for stability, percent air voids, and swell for 3 briquettes constructed using the submitted aggregate and asphalt blended at the proposed target values for each asphalt concrete mixture to be used.

The Contractor shall submit the following for each asphalt concrete mixture proposed:

A. Aggregate and mineral filler:

1. Target values for percent passing each sieve size for the aggregate blend;
2. Results of tests for aggregate quality requirements;
3. Source of each aggregateto be used including producer, location, and California Mine Identification number;
4. Percentage of each aggregate stockpile, cold feed or hot bin to be used;
5. Gradation of each aggregate stockpile, cold feed or hot bin to be used; and
6. Samples that are representative of the aggregate to be used. Minimum sample sizes shall be as follows:

60 kg of each coarse aggregate;
40 kg of each fine aggregate; and
5 kg of each supplemental fine aggregate.

B. Asphalt binder:

1. Asphalt binder source and target value;
2. Four one-liter samples of the asphalt binder;
3. Results of the asphalt binder quality tests conforming to the provisions in Section 92, "Asphalts," of the Standard Specifications; and
4. Material Safety Data Sheets.

C. Antistrip additives**,** when applicable:

1. A 5-kg sample of the dry additive or a one-liter sample of the liquid antistrip additive, including name of product, manufacturer, manufacturer's designation and proposed rate, location, and method of addition; and
2. Material Safety Data Sheets.

The proposed asphalt concrete mix design submittal will be considered complete only when the mix design letter, test results, plots, and samples have been received by the Engineer.

39-3.02 ENGINEER REVIEW OF ASPHALT CONCRETE MIX DESIGN

The Engineer will review the proposed aggregate and asphalt concrete mixture for conformance with this Section 11-1, "Quality Control / Quality Assurance." The proposed asphalt concrete mixture will be reviewed at the proposed target values for aggregate grading and asphalt content. The Engineer will have 14 days to review each submittal of a proposed mix

design. Production of asphalt concrete shall not begin until written notification has been received from the Engineer that the aggregates and proposed mix design meet the quality requirements of this Section 11-1.

The Engineer will reject a proposed asphalt concrete mixture that, during review, fails to meet the quality requirements of Table 39-2, "Aggregate Quality Requirements," and Table 39-3, "Asphalt Concrete Mixture Requirements," of this Section 11-1. The Contractor shall resubmit a mix design letter providing new test results, plots, and material samples.

Disagreements in mix design review shall be resolved in conformance with Section 39-6, "Dispute Resolution," of this Section 11-1. The Contractor shall use a mix design on the project only after the Engineer concurs that the aggregate and asphalt concrete represented by the proposed mix design conforms to the provisions ofthis Section 11-1.

The Engineer will review one proposed asphalt concrete mix design for each asphalt concrete type and aggregate size from each plant proposed for use on this project at the State's expense. Costs for additional reviews due to failure to conform to the quality requirements of this Section 11-1 and for reviewing other proposed asphalt concrete mix designs will be deducted from moneys due or to become due the Contractor. The cost for each review will be $1,500. Costs for reviewing changes in a mix design that are initiated by the Engineer will be waived. Contractor's retesting due to errors in the Engineer's testing will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Costs for reviewing mix designs not used in this project will be deducted from moneys due or to become due the Contractor.

39-4 CONTRACTOR QUALITY CONTROL

39-4.01 GENERAL

The Contractor shall be responsible for the quality of the asphalt concrete entering into the work and of the work performed. In addition, the Contractor shall be responsible for the quality of asphalt concrete or ingredients procured from subcontractors or vendors. A quality control system shall be established, maintained, and modified, if needed, that will provide assurance that materials and completed work conform to contract requirements.

At least 14 days prior to the start of production of asphalt concrete, the Contractor shall submit a written Quality Control Plan. At the request of the Engineer or the Contractor, the Contractor shall discuss the Quality Control Plan with the Engineer.

39-4.02 QUALITY CONTROL PLAN

The Quality Control Plan shall describe the organization and procedures that will be used to administer the quality control system including the procedures used to control the production process, the procedures used to determine when changes to the production process are needed, and the procedures proposed to be used to implement the required changes. The Quality Control Plan shall meet the minimum standards set forth in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete," available as specified in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Asphalt concrete production and placement shall not begin until the Quality Control Plan has been approved by the Engineer. Approval of the Quality Control Plan does not imply a warranty by the Engineer that adherence to the plan will result in production of asphalt concrete that complies with this Section 11-1. It shall remain the responsibility of the Contractor to demonstrate such compliance.

The Quality Control Plan shall include the name and qualifications of a Quality Control Manager. The Quality Control Manager shall be responsible for the administration of the Quality Control Plan, including compliance with the plan and plan modifications. The Quality Control Manager shall be responsible to the Contractor, shall have the authority to make decisions concerning quality of the work or product, and shall be available to the project within less than 3 hours during paving. Except in cases of emergency and with the approval of the Engineer, the Quality Control Manager cannot be a foreman, member of the production or paving crew, an inspector or tester on this project during pavement production and placement.

The Quality Control Plan shall identify personnel, equipment and documentation required for a complete inspection, sampling and testing program. The Quality Control Plan shall include, but not be limited to, a list of inspectors, samplers and testers, their duties, their certifications if required, and their experience if no certification is required. It shall also list the name and location of laboratories that shall be providing information to the Engineer, the testers who conducted the tests and their certifications and the name of the Laboratory Quality Control Manager responsible for oversight of the testing program. It shall also show examples of the test result forms (if different from those in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete"), the roadway and plant inspection forms, the Quality Control Manager's daily summary form, and the compliance charts. It shall include the method by which random sampling shall be determined, a list of the testing and sampling equipment to be used and the current calibration dates and calibration charts, and copies of nuclear gauge licenses.

The Quality Control Plan shall include the name and certification of a testing consultant to be an Independent Third Party in dispute resolution. By mutual agreement during dispute resolution, the Independent Third Party may be a District Independent Assurance Sampler and Tester, the testing consultant or both. The proficiency of the testing consultant shall be

reviewed and certified in conformance with the requirements of the Department's Quality Assurance Program before the test consultant participates in dispute resolution. Attention is directed to Section 39-6, "Dispute Resolution," of this Section 11-1.

The Quality Control Plan may be modified as work progresses. A supplement shall be submitted whenever there are changes to quality control procedures or personnel. Asphalt concrete production and placement shall not resume or continue until revisions to the Quality Control Plan or quality control personnel have been approved by the Engineer.

39-4.03 CONTRACTOR QUALITY CONTROL INSPECTION, SAMPLING, AND TESTING

The Contractor shall perform process and quality control sampling and testing, provide inspection, and exercise management control to ensure that asphalt concrete production and placement conforms to the provisions of this Section 11-1. Staffing for process and quality control shall meet the minimum requirements outlined in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete."

Process and quality control, sampling, testing, and inspection shall be provided during the asphalt concrete work. Sampling, testing, and inspection shall be performed at a rate sufficient to ensure that asphalt concrete conforms to the provisions of this Section 11-1.

A roadway inspector shall be provided while asphalt concrete paving operations are in progress. The roadway inspector shall ensure that asphalt concrete placement conforms to industry standards and to the spreading, compacting, and finishing requirements of this Section 11-1, "Quality Control / Quality Assurance." Plant inspection shall be performed as necessary to maintain control of the asphalt concrete production.

Minimum sampling and testing requirements for process and quality control are specified in Table 39-4, "Minimum Process Control Requirements," and Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Sampling shall be statistically based and random.

During production start-up evaluation, the Contractor shall sample and test in conformance with the provisions in Section 39-10.02A, "Production Start-Up Evaluation," of this Section 11-1.

A testing laboratory and personnel shall be provided for the performance of process and quality control testing. The Engineer shall have unrestricted access to mix design, sampling, and testing.

The proficiency of testing laboratories and sampling and testing personnel shall be reviewed, qualified, and certified by the Department's Independent Assurance Sampler and Tester before providing services to the project. Inspectors shall meet the standards set forth in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete."

39-4.04 CONTRACTOR PROCESS CONTROL

Process control sampling and testing shall be performed and control shall be exercised to ensure that asphalt concrete production conforms with this Section 11-1.

Minimum process control sampling and testing shall be performed in compliance with the following:

Table 39-4 - MINIMUM PROCESS CONTROL REQUIREMENTS

Quality Characteristic	Action Limit	California Test	Minimum Sampling and Testing Frequency	Point of Sampling ‡	Reporting Time Allowance
Sand Equivalent (Min)	47 (Type A) 42 (Type B)	217	One sample per 2500 tonnes	Batch plant - from hot bins. Drum plant - from cold feed.	24 hours
		(Reported value shall be the average of 3)[1]	Not less than one sample per 2 days		
Stability	37 (Type A) 35 (Type B)	366[2]	See Note 4	Mat behind paver	48 hours
		(Reported value shall be the average of 3)[1,3,5]	Not less than one sample per 5 days		

Notes:

‡ In conformance with the requirements of California Test 125.

1. Samples used for the 3 tests to be averaged shall be from a single split sample.
2. Reheat for sample preparation shall be 2 hours maximum.
   Do not place sample or briquette in oven for 15-hour cure.
3. Briquettes shall be fabricated from a single, combined sample obtained from at least 4 locations across the mat behind the paver in conformance with the requirements of California Test 125.
   If the range of stability for the three briquettes is more than 12 points, the samples shall be discarded and new samples shall be obtained before the end of the following shift of paving and tested in conformance with the requirements of Table 39-3, "Asphalt Concrete Mixture Requirements."
4. Asphalt concrete will be sampled and tested each of the first 5 days of production and may be decreased to one for each 5 days thereafter unless stability falls below the action limit.
   When stability falls below the action limit, sampling will be increased to one sample for each of the first 5 days of production and may be decreased to one for each 5 days thereafter.
   The sequence of the first 5 test results shall not be broken by more than 7 days of suspended operations.
5. During production start-up evaluation, a correlation factor for cured vs. uncured specimens shall be established in conformance with the requirements of Section 39-10.02A, "Production Start-Up Evaluation."

The process control test results shall be plotted on specification compliance charts indicating the action limits for the quality characteristic. When one test result falls below the action limit for an individual measurement, the Contractor shall notify the Engineer, take corrective action, and sample and test within the next 500 tonnes of production. When 2 consecutive test results for an individual characteristic fall below the action limit, the asphalt concrete represented by the 2 tests shall be considered not in compliance. When 2 consecutive test results for an individual characteristic fall below the action limit, the Contractor shall suspend production, notify the Engineer, and take corrective action. With the approval of the Engineer, up to 1000 tonnes of asphalt concrete may be placed to demonstrate that the asphalt concrete is once again in compliance with the provisions of this Section 11-1. Production shall begin only after the Engineer has received test results confirming compliance.

Asphalt concrete that has 2 consecutive stability test results less than or equal to 26 for Type A asphalt concrete or less than or equal to 24 for Type B asphalt concrete shall be removed at the Contractor's expense. Asphalt concrete placed to demonstrate compliance that does not meet the provisions of this Section 11-1 shall be removed at the Contractor's expense.

39-4.05 CONTRACTOR QUALITY CONTROL

Quality control, sampling, testing, and inspection shall be provided during asphalt concrete work. Sampling, testing, and inspection shall be performed at a rate sufficient to ensure that the asphalt concrete product conforms to the requirements in this Section 11-1. Sampling for testing to be reported to the Engineer shall be performed at the minimum frequency specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1, "Quality Control / Quality Assurance."

Quality control samples of aggregates and asphalt concrete mixture shall be obtained and split. One split portion of each sample shall be used for quality control testing and the other portion shall be reserved for possible retest during dispute resolution, in conformance with Section 39-6, "Dispute Resolution," of this Section 11-1. Quality control samples shall be stored in a location listed in the Quality Control Plan until disposal has been approved by the Engineer.

The Contractor shall obtain a one-liter sample of the asphalt binder in conformance with Section 39-7.01C, "Asphalt Binder Storage," of this Section 11-1 for each day of asphalt concrete production. The sample containers shall be labeled as shown in the "Manual for Quality Control and Quality Assurance for Asphalt Concrete" and shall be sent by the Contractor to the Transportation Laboratory on a weekly basis, except for modified asphalts that shall be shipped daily. A copy of the transmittal form shall be attached to the daily report of inspection.

When test results for a single quality characteristic deviate beyond the limits specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1 the Contractor shall take corrective action and shall bring the asphalt concrete within the specification limits. The corrective action taken shall be documented in the records of inspection in conformance with Section 39-4.06B, "Records of Inspection and Testing," of this Section 11-1. When a single quality characteristic deviates 3 consecutive times beyond the limits specified in Table 39-9, "Minimum Quality Control Test Requirements," of this Section 11-1, the Contractor shall suspend production, shall notify the Engineer, and shall take corrective action. With the approval of the Engineer, up to 1000 tonnes of asphalt concrete may be placed and the requirements of Section 39-10.02A, "Production Start-Up Evaluation," of this Section 11-1 shall be used to demonstrate that the asphalt concrete is once again in compliance with this Section 11-1. Production of asphalt concrete shall start only after the Engineer has received test results confirming compliance. When an individual quality characteristic deviates 3 consecutive times beyond the specification limits and production of asphalt concrete has been suspended, the lot shall be terminated.

If an ignition oven is used for asphalt content in conformance with the requirements of California Test 382, gradations of the remaining aggregates shall be provided for each 5000 tonnes of production. Testing of the aggregates shall be in conformance with the requirements of California Test 202, Sections F and G, "Sieve Analysis of Fine and Coarse Aggregates." Test results from these gradings shall be provided prior to completion of the project. Gradings from the aggregates recovered from the ignition oven will not be used in the statistical analysis for quality or for pay. Payment for these gradings will be made as extra work as provided in Section 4-1.03D of the Standard Specifications at the rate of $150 per test result for the cost of the additional testing.

39-4.06 CHARTS AND RECORDS

The Contractor shall record sampling and testing results for both process control and for quality control on forms as provided in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete" or on forms approved by the Engineer. Complete testing records shall be maintained and posted in the Contractor's laboratory. Models of forms that are different from those in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete," locations of postings, and times and means of submissions shall be provided in the Quality Control Plan.

For every 5000 tonnes of asphalt concrete produced, the Contractor shall provide an electronic copy of the process and quality control test results using the Department's statistical evaluation program "ACPay" available as specified in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Compliance charts and inspection and testing records, except stability test results used for process control, shall be submitted within 24 hours after completion of that shift of asphalt concrete production. If the record is incomplete or in error, a copy of the record will be returned with the deficiencies noted by the Engineer. The Contractor shall correct deficiencies and return the updated record by the start of the following working day. When errors or omissions in the inspection or testing records repeatedly occur, asphalt concrete production and placement shall be suspended and the procedures by which the records are produced shall be corrected before production and placement will be restarted.

39-4.06A Compliance Charts

The Contractor shall develop and maintain time linear specification compliance charts. The compliance charts shall identify the project, test number, test parameter, applicable upper and lower specification limits, and test results.

Compliance charts shall be kept current and shall be posted at a location designated in the Quality Control Plan. Compliance charts shall be updated each day of asphalt concrete production, and up-to-date copies shall be included in the submittals to the Engineer of each day's test results.

39-4.06B Records of Inspection and Testing

For each day of asphalt concrete production, the Contractor shall prepare an "Asphalt Concrete Construction Daily Record of Inspection," on forms provided in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete." A form shall be submitted for inspection at the plant and at the roadway.

For each day of asphalt concrete production, the Contractor shall prepare an "Asphalt Concrete Inspection and Testing Summary" on a form provided in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete." Plant and roadway inspection forms documenting the day's plant production and roadway placement shall be completed. Deviations from the specifications or the Contractor's regular practice shall be listed and explained. Individual inspection forms shall be signed by the inspector and initialed by the Quality Control Manager and attached to the summary at submittal. Test forms documenting test results shall be complete, signed by the tester, checked and initialed by the Quality

Control Manager, and attached to the summary at submittal. Sampling and testing data and calculations that support a test result shall be made available to the Engineer within 48 hours when requested.

The "Asphalt Concrete Inspection and Testing Summary" shall include the following certification signed by the Quality Control Manager:

> It is hereby certified that the information contained in this record is accurate, and that information, tests or calculations documented herein comply with the requirements of the contract and the standards set forth in the testing procedures. Exceptions to this certification are documented as a part of this record.

39-5 ENGINEER QUALITY ASSURANCE

39-5.01 GENERAL

The Engineer will assure conformance to contract specifications by review of the Contractor's mix design proposal, by inspection of the Contractor's procedures, by oversight of the Contractor's quality control inspection and records, by splitting and testing samples with the Contractor during evaluation of the plant production start-up and the nuclear density test strip, and by independent verification sampling and testing of the asphalt concrete and aggregates during asphalt concrete production.

The Contractor may witness assurance sampling and testing. However, the Engineer will not be required to notify the Contractor of anticipated sampling schedules or locations and will not delay sampling or testing if the Contractor is unable to attend. The Contractor shall not use samples taken for assurance testing for testing and submittal as a quality control test result.

The Engineer will provide the Contractor with copies of the assurance test results not more than 2 working days after receipt of the results. Sampling and testing data and calculations that support a test result shall be made available to the Contractor within 48 hours when requested.

The Engineer may test the asphalt, aggregates or asphalt concrete mixture to determine conformance with this Section 11-1, "Quality Control / Quality Assurance," whenever an asphalt concrete mixture or ingredient appears defective or inconsistent or whenever a test result indicates a change in the characteristics of the asphalt concrete mixture or an ingredient. Asphalt, aggregates or asphalt concrete that does not conform with this Section 11-1 will be rejected in conformance with Section 39-11, "Acceptance of Work," of this Section 11-1.

The Contractor, when directed by the Engineer, shall obtain representative samples of the asphalt concrete mixture or ingredients that appear defective or inconsistent. The samples shall be split into 4 portions. The Contractor shall retain 1 portion for testing if the Contractor chooses and 3 portions shall be delivered to the Engineer. The asphalt concrete or ingredient need not be sampled if the Contractor elects to remove and replace the asphalt concrete, at the Contractor's expense, or if the Contractor uses a method of correcting the situation that has been approved by the Engineer. Test results from these additional samples shall not be used as a basis for a calculated pay factor.

39-5.02 SAMPLING AND TESTING FOR VERIFICATION

Independent of the Contractor's quality control testing, the Engineer will obtain random samples of the aggregate and asphalt concrete mixture and test for in-place density.

Samples of aggregates and asphalt concrete will be obtained during asphalt concrete production and placement, and will be split into at least 4 portions. One of the split portions will be tested by the Engineer and used to verify quality control test results, one portion will be provided to the Contractor, and 2 portions will be reserved and stored for testing in conformance with the provisions in Section 39-6, "Dispute Resolution," of this Section 11-1. When verifying the relative compaction, the Engineer will obtain a sample of a sample of asphalt concrete from the mat behind the paver, will split the sample and apportion the sample as described above, and will test the sample for test maximum density.

The Engineer will test for material quality characteristics specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Verification tests will be at a frequency of not less than 10 percent of the minimum quality control sampling and testing frequency and will be performed in conformance with the test methods specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Verification tests will be performed using the same test methods used for quality control testing.

During the Engineer's verification of the relative compaction, the Engineer will determine the location of 500 tonnes of asphalt concrete to be tested using a random number, will obtain an asphalt concrete sample from within this location for determination of the test maximum density, and will determine the relative compaction of the in-place asphalt concrete as specified in California Test 375. The Contractor shall obtain one of the split samples of asphalt concrete for determination of test maximum density and shall determine the relative compaction of the 500 tonnes of asphalt tested by the Engineer using the same testing sites determined by the Engineer. The results of this common testing will be compared to the allowable testing difference defined in Table 39-6, "Allowable Testing Differences," of this Section 11-1. If the test maximum density or the relative compaction does not comply with the allowable testing difference, then the Engineer and Contractor will use

the first 500 tonnes of the next day's production to re-correlate the nuclear gauges used in testing as defined by California Test 375.

During production start-up evaluation, the Engineer will witness the sampling of asphalt concrete and aggregates and will perform tests on the materials in conformance with Section 39-10.02A, "Production Start-Up Evaluation," of this Section 11-1.

39-5.03 VERIFICATION

The Engineer will determine the acceptability of the quality control test results by using the *t*-test for sample means to test whether or not the means of the quality control test results and verification test results are within an allowable testing difference. Quality control test results and verification test results for each indexed quality characteristic will be used in the verification process.

The *t*-value of the group of test data to be verified is computed as follows:

$$t = \frac{\left|\overline{X_c} - \overline{X_v}\right|}{S_p\sqrt{\frac{1}{n_c} + \frac{1}{n_v}}} \quad \text{and} \quad S_p^2 = \frac{S_c^2(n_c - 1) + S_v^2(n_v - 1)}{n_c + n_v - 2}$$

where:

n_c	=	Number of Contractor's quality control tests (minimum of 2 required)
n_v	=	Number of Verification tests (minimum of 1 required)
$\overline{X}_c$	=	Mean of the Contractor's quality control tests
$\overline{X}_v$	=	Mean of the Verification tests
S_p	=	Pooled standard deviation (When $n_v = 1$, $S_p = S_c$)
S_c	=	Standard deviation of the Contractor's quality control tests
S_v	=	Standard deviation of the Verification tests (when $n_v > 1$)

The comparison of quality control test results and verification test results will be considered at a level of significance, $\alpha = 0.01$. Compute *t* using the equation above and compare to the critical *t*-value, t_{crit} , from the following table:

Table 39-5 - CRITICAL t-VALUE FOR VERIFICATION OF QUALITY CONTROL TESTING

degrees of freedom (nc+nv-2)	t_{crit} (for $\alpha = 0.01$)	degrees of freedom (nc+nv-2)	t_{crit} (for $\alpha = 0.01$)
1	63.657	18	2.878
2	9.925	19	2.861
3	5.841	20	2.845
4	4.604	21	2.831
5	4.032	22	2.819
6	3.707	23	2.807
7	3.499	24	2.797
8	3.355	25	2.787
9	3.250	26	2.779
10	3.169	27	2.771
11	3.106	28	2.763
12	3.055	29	2.756
13	3.012	30	2.750
14	2.977	40	2.704
15	2.947	60	2.660
16	2.921	120	2.617
17	2.898	∞	2.576

Quality control test results are verified if the *t*-value computed is less than or equal to t_{crit} ($t \le t_{crit}$), and the difference between the means of the quality control test results and verification test results are within an allowable testing difference.

Quality control test results are not verified if the t-value computed is greater than t_{crit} ($t > t_{crit}$), and the difference between the means exceeds the allowable testing difference. The allowable testing difference shall be as follows:

Table 39-6 - ALLOWABLE TESTING DIFFERENCE

Quality	California Test	Allowable Testing Difference
Sand Equivalent (min.)	217	8
Hveem Stabilometer Value (min.)	366	10
Percent Air Voids	367	1.5
Asphalt Content	379 or 382	0.3%
Gradation	202	
19 or 12.5 mm		2
9.5 mm		4
4.75 mm		3
2.36 mm		2
600 µm		2
75 µm		1.0
Relative Compaction	375	0.8%
Test Maximum Density		0.03 g/cc

If quality control test results are not verified, the Contractor will be notified of the difference. The Engineer will sample asphalt concrete production at a more frequent interval. Resolution of the problem shall be in conformance with the provisions in Section 39-6, "Dispute Resolution," of this Section 11-1.

39-6 DISPUTE RESOLUTION

39-6.01 GENERAL

The Contractor and the Engineer shall work together to avoid potential conflicts and to resolve differences that may arise from a disagreement regarding test result comparisons.

Should the results of the testing fail to meet the criteria of the stage at which the disagreement arose, production shall be suspended. Production shall not start or resume nor shall asphalt concrete be accepted until the differences have been resolved and the Engineer is assured that the asphalt concrete conforms to this Section 11-1, "Quality Control / Quality Assurance."

When the Engineer and the Contractor, together or separately, are unable to determine the source of error, an Independent Third Party shall act as witness and referee.

In disagreements, if the Engineer's testing process meets the requirements of this Section 11-1, costs related to the review shall be borne by the Contractor. The Contractor's sampling and testing program shall be modified as necessary. New test results shall be submitted to the Engineer. Test results judged to be in error shall be removed from consideration and the new test results shall be substituted. If split samples are not available and retesting is not possible, that portion of the asphalt concrete produced or placed prior to and during the disagreement will be evaluated based on the results of the Engineer's verification test results.

In disagreements, if the Engineer's testing process fails to meet the requirements of this Section 11-1, costs related to the review shall be borne by the State. The Engineer's sampling and testing program will be modified as necessary. Test results judged to be in error shall be removed from consideration and the new test results shall be substituted. Contractor's retesting due to errors in the Engineer's testing will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. If, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of delays or errors in the Engineer's testing, the delay will be considered a right of way delay as provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

In disagreements, if both the Contractor's and the Engineer's testing processes have failed to meet the requirements of this Section 11-1 or if the cause cannot be determined, each party will bear the costs related to their own review. When appropriate, the Contractor's and the Engineer's sampling and testing programs shall be modified as necessary, split samples of the Contractor's quality control samples or the Engineer's verification samples shall be retested, and the new quality control test results shall be submitted to the Engineer. Test results judged to be in error shall be removed from consideration and the new test results shall be substituted. If split samples of aggregates or asphalt concrete mixture from the Contractor's testing are not available where retesting is required, that portion of the asphalt concrete produced prior to and during the disagreement will be evaluated based on the results of the Engineer's verification test results.

39-6.02 DURING THE ASPHALT CONCRETE MIX DESIGN REVIEW

During the asphalt concrete mix design review, if the Engineer's review does not confirm that one or more of the aggregate or the asphalt concrete mixture qualities comply with this Section 11-1, "Quality Control / Quality Assurance," both parties will review their sampling, testing, and test results and shall share their findings. Testers and laboratories shall be made available for witnessing. Calculations and test results shall be made available for review. If an error in the Contractor's testing is detected during this review, the Contractor shall, as is appropriate, recalculate or retest. The new test results shall be submitted to the Engineer. If an error in the Engineer's testing is detected, the Engineer will, as is appropriate, recalculate or retest.

If the Contractor's and Engineer's review does not reveal the source of conflict, the Contractor's and the Engineer's sampling and testing processes shall be witnessed by the Independent Third Party. Testing to resolve the dispute in results for the mix design shall be performed using samples that were obtained and split while being witnessed by the Independent Third Party. Review of sample preparation and testing will be performed at both the Contractor's and the Engineer's laboratory on a portion of the split material while being witnessed by the Independent Third Party. The resulting mix design shall be used for production.

39-6.03 DURING THE PRODUCTION START-UP EVALUATION

When the Contractor's and Engineer's test results during production start-up fail to meet the provisions in Section 39-10.02, "Production Start-Up Evaluation and Nuclear Density Test Strips," both parties will review their sampling, testing, and test results, and shall share their findings. Testers and laboratories shall be made available for witnessing. Calculations and test results shall be made available for review. If an error in the Contractor's testing is detected during this review, the Contractor shall, as is appropriate, recalculate or retest. The new test results shall be submitted to the Engineer. If an error in the Engineer's testing is detected, the Engineer will, as is appropriate, recalculate or retest.

If the Contractor's and the Engineer's review does not resolve the differences, the Contractor's and the Engineer's testing processes shall be witnessed by the Independent Third Party using the 2 remaining portions of the split samples. If necessary, a 250-tonne to 500-tonne quantity of asphalt concrete shall be placed at a location agreed to by the Engineer to provide asphalt concrete and ingredients for sampling and testing for the Independent Third Party review.

If an error in the Contractor's testing is detected by the Independent Third Party, the Contractor shall take corrective action and, as appropriate, recalculate or retest the split portion of the trial quantity of asphalt concrete in question. The new test results shall be submitted to the Engineer. If an error in the Engineer's testing is detected by the Independent Third Party, the Engineer will take corrective action and, as appropriate, recalculate or retest the split portion of the first trial quantity.

Production shall not start nor shall asphalt concrete be accepted until the differences have been resolved and the test results meet the provisions in Section 39-10.02, "Production Start-Up Evaluation and Nuclear Density Test Strips," of this Section 11-1.

39-6.04 DURING PRODUCTION

When it is determined that the quality control test results could not be verified, both parties will review their sampling, testing, and test results, and shall share their findings. Testers and laboratories will be made available for witnessing. Calculations and results will be made available for review.

If an error in the quality control sampling or testing is detected during the Contractor's or the Engineer's review, the Contractor shall either recalculate or, if appropriate, retest using the reserved split portions of the quality control samples. These new test results shall be submitted to the Engineer. If an error in the verification sampling or testing is detected, the Engineer will recalculate or, if appropriate, retest using a reserved split portion of the verification samples. Using the new test results, the Engineer will repeat the calculation of the *t*-test and will determine if the means of the quality control tests and the verification test results are within the allowable testing difference as specified in Section 39-5.03, "Verification," of this Section 11-1.

When the verification test results do not verify the quality control test results 3 consecutive times, both the Contractor's and the Engineer's testers shall be witnessed by the Independent Third Party while sampling, splitting, and testing samples from the production unit or from the mat . The Contractor may produce and place up to 1000 tonnes of asphalt concrete to provide materials and sampling opportunities. Production and placement of asphalt concrete will be suspended until the Independent Third Party has completed the review of the Contractor's and the Engineer's sampling and testing and resolved the differences.

If an error in the Contractor's testing is detected by the Independent Third Party, the Contractor shall take corrective action and, as appropriate, recalculate or retest the split portion of the quality control samples. The new test results shall be submitted to the Engineer. If an error in the Engineer's testing is detected by the Independent Third Party, the Engineer will take corrective action and, as appropriate, recalculate or retest a split portion of the verification samples. When the error has been detected and corrected, production shall resume and the services of the Independent Third Party will be discontinued.

If a problem is not identified during the Independent Third Party review, the Independent Third Party shall be retained for the duration of the project or until a problem has been identified. Until all asphalt concrete has been produced and placed,

the Contractor shall sample and split quality control samples in the presence of the Independent Third Party. One portion of each sample shall be tested by the Contractor in conformance with the intervals specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1, and the other portion shall be delivered to the Engineer by the Independent Third Party. The Engineer will test at least one of every 5 of the split samples for verification purposes. A new lot will be designated for asphalt concrete produced since the Independent Third Party was consulted. The pay factor for this lot will be determined in conformance with Section 39-11.02, "Statistical Evaluation and Determination of Pay Factor," of this Section 11-1 with the exception that both the Contractor's quality control test results and the Engineer's verification test results will be combined and will be the basis for acceptance of that portion of the work. The pay factor for the lot of asphalt concrete which brought about the dispute resolution shall be determined in conformance with Section 39-11.02, "Statistical Evaluation and Determination of Pay Factor," of this Section 11-1 with the exception that both the Contractor's quality control test results and the Engineer's verification test results will be combined and will be the basis for acceptance of that portion of the work.

39-7 STORING, PROPORTIONING AND MIXING MATERIALS

39-7.01 STORAGE

The Contractor shall store the aggregate for asphalt concrete so that separately sized aggregates will not be intermingled and shall store asphalt binder so that different grades of asphalt will not be intermingled. Aggregate that has been intermingled with aggregate of another size shall be removed by the Contractor and replaced with aggregate of specified grading.

When the Contractor adds supplemental fine aggregate, each supplemental fine aggregate used shall be stored separately and kept thoroughly dry.

The measurement and storage provisions of this Section shall not apply to the dust collected in skimmers and expansion chambers (knock-out boxes) or to the dust collected in centrifugal (cyclone) collectors. Dust from these collectors may be returned to the aggregate without being measured or stored separately, provided the dust is returned uniformly at a point in advance of the sampling device in batch-mixing plants or is returned at or before mixing in continuous mixing plants.

Aggregate and asphalt binder shall be stored in conformance with the following requirements.

39-7.01A Aggregate Cold Storage

Material shall be fed from storage with a mechanical feeder. Before being fed to the drier, aggregate shall be separated into 3 or more sizes and stored separately.

39-7.01B Aggregate Hot Storage

Aggregate for asphalt concrete to be mixed in batch mixing plants shall be stored, after being dried, in conformance with the following requirements:

1. Aggregates for asphalt concrete shall be separated into 3 or more sizes.
2. After the aggregate is separated, each size shall be stored in a separate bin, and shall be recombined in conformance with the provisions in Section 39-7.03A, "Proportioning for Batch Mixing," of this Section 11-1 in order to conform to the gradings specified in Section 39-2, "Materials," of this Section 11-1. Storage bins shall be provided with chutes to prevent overflow into adjacent bins.

39-7.01C Asphalt Binder Storage

Asphalt to be used as a binder for asphalt concrete shall be stored in heated tanks.

A suitable sampling device shall be provided in asphalt feed lines connecting plant storage tanks to the asphalt weighing system or spray bar. The sampling device shall consist of a valve with a nominal diameter between 10 mm and 20 mm, constructed in such a manner that a one-liter sample may be slowly withdrawn during plant operations. The valve shall be maintained in good condition and, if the valve fails to function properly, the valve shall be replaced. The sampling device shall be readily accessible and in an area free of dangerous obstructions and shall be between 600 mm and 750 mm above the platform. A drainage receptacle shall be provided for flushing the device prior to sampling.

The discharge end of the asphalt binder circulating pipe shall be maintained below the surface of the asphalt binder in the storage tank to prevent discharging hot asphalt binder into open air.

A temperature sensing device shall be installed in the asphalt feed line. The device shall measure the temperature of the asphalt and shall be accurate to 5˚C increments. An automatic, continuous recording device shall be provided and used to maintain accurate records of the asphalt temperature during production. Where the plant controller has the capability of capturing production data electronically, including ingredient temperatures, and when this data represents the temperature at the time of production and is captured at intervals of not greater than 5 minutes, this process will be considered to be

continuous recording. Captured data shall be retained for the duration of the contract and shall be submitted to the Engineer on request.

39-7.02 DRYING

Aggregate shall be fed directly to a drier-drum mixer or to a drier at a uniform rate.

Aggregate shall be dried such that, at the time of spreading, the moisture content of the completed asphalt concrete mixture shall not exceed 1.0 percent and the minimum and maximum asphalt concrete mixture temperatures are not exceeded. Moisture content will be determined in conformity with the requirements of California Test 370.

The drier or drier-drum mixer shall be provided with a device that senses the temperature of the material leaving the drier or the drier-drum mixer. The temperature-sensing device shall be accurate to the nearest 5˚C. The indicator shall be located and maintained at the point where the proportioning operations are controlled. An automatic continuous recording device shall be provided and used to maintain accurate records of the temperatures during production. Where the plant controller has the capability of capturing production data electronically, including ingredient temperatures, and when this data represents the temperature at the time of production and is captured at intervals of not greater than 5 minutes, this process will be considered to be continuous recording. Captured data shall be retained for the duration of the contract and shall be submitted to the Engineer on request.

The burner used for heating the aggregate shall achieve complete combustion of the fuel.

39-7.03 PROPORTIONING

Proportioning shall be either by hot-feed control or cold-feed control. Hot-feed control and cold-feed control indicate the location of the measuring devices or controls.

The Contractor's mixing equipment shall be equipped with a suitable, safe sampling device that will provide a sample, representative of actual production, of the aggregate being incorporated into the asphalt concrete. The delivery point of samples shall be safe and convenient. When samples are taken from a location above ground level, a means shall be provided for lowering the aggregate samples to the ground.

39-7.03A Proportioning for Batch Mixing

When the Contractor elects to use batch mixing equipment, each aggregate hot storage bin shall be equipped with a sampling device that will provide a sample of the aggregate discharged into the weigh hopper.

Fine material collected in dust control systems, other than centrifugal collectors or knock-out boxes, shall be considered to be supplemental fine aggregate. When supplemental fine aggregate is used, it shall be proportioned by mass.

A sampling device for supplemental fine aggregate shall be installed in each feed line or surge tank preceding the weigh hopper.

39-7.03A(1) Batching Tolerances

Aggregate and asphalt shall be proportioned by mass as follows:

A. The zero tolerance for aggregate scales shall be 0.5-percent of the total batch mass of the aggregate. The zero tolerance for separate scales for weighing supplemental fine aggregate or asphalt binder shall be 0.05-percent of the total batch mass of the aggregate.
B. Unless otherwise approved by the Engineer, the indicated mass of material drawn from storage shall not vary from the preselected scale setting as defined by target values of the approved mix design by more than the following percentages of the total batch mass of the aggregate:

    1. Aggregate shall be within one percent, except that when supplemental fine aggregate is used and is weighed cumulatively with the aggregate, the draft of aggregate drawn immediately before the supplemental fine aggregate shall be within 0.5-percent.
    2. Supplemental fine aggregate shall be within 0.5-percent.
    3. Asphalt binder shall be within 0.1-percent.

The asphalt binder shall be measured by a tank scale.

39-7.03A(2) Automatic Controls

Batch proportioning shall be by an automatic plant controller. The proportioning devices shall be automatic to the extent that the only manual operation required for proportioning materials for one batch shall be a single operation of a switch or starter.

Proportioning devices shall be of a type in which materials discharged from the several bins are controlled by gates or by mechanical conveyors. The batching devices shall be so interlocked that no new batch may be started until weigh hoppers are empty, the scales are at zero, and the discharge gates are closed. The means of withdrawal from the bins and of discharge from the weigh box shall be interlocked so that not more than one bin can discharge onto a given scale at one time, and so that the weigh box cannot be tripped until the required quantity from each of the bins has been deposited therein. In addition, automatic proportioning devices shall be interlocked so that the weighing cycle will be interrupted whenever the amount of material drawn from storage varies from the pre-selected amount by more than the tolerances specified in this Section 11-1. Whenever the weighing cycle is interrupted, that specific batch shall not be used in the work unless it can be manually adjusted to meet the specified tolerances based on the total mass of the batch. When partial batches are batched, the interlock tolerances, except the zero tolerance, shall apply to the total mass of aggregate in the partial batch.

Proportioning devices shall be operated so that all mass increments required for a batch are preset at the same time. Controls shall be designed so that these settings may be changed without delay and the order of discharge from the several bins can be changed.

Proportioning controls shall be equipped with the means for inspection of the interlock tolerance settings. Instructions for performing the inspection shall be available at the point of operation.

The necessary means shall be provided to check the mass of various proportioned amounts on a separate vehicle scale located at the plant site.

39-7.03B Proportioning for Continuous Mixing

Asphalt binder shall be introduced into the mixer through a meter conforming to the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications. The asphalt meter shall automatically compensate for changes in the asphalt temperature, unless the meter is the mass flow, coriolis effect, type. The system shall be capable of varying the rate of delivery of binder proportionate with the delivery of aggregate. During a day's run, the temperature of asphalt binder shall not vary more than 30˚C. The meter and lines shall be heated and insulated. The binder storage shall be equipped with a device for automatic plant cut-off when the level of binder is lowered sufficiently to expose the pump suction line.

When supplemental fine aggregate is used, it shall be proportioned by a method that uniformly feeds the material within 2 percent of the required amount. Supplemental fine aggregate shall be discharged from the proportioning device directly into the mixer.

The supplemental fine aggregate proportioning system shall function with a degree of accuracy such that, when operated between 30 percent and 100 percent of maximum operating capacity, the average difference between the indicated mass of material delivered and the actual mass delivered shall not exceed one percent of the actual mass for three individual 15-minute runs. For the 3 individual 15-minute runs, the indicated mass of material delivered shall not vary from the actual mass delivered by more than 2 percent of the actual mass.

The fine material collected in dust control systems may be returned to the aggregate production stream without proportioning if returned at a rate commensurate with overall plant production, and if returned at or before the mixer. A return rate of less than 100 percent of the collection rate shall be metered as specified above for supplemental fine aggregate.

The asphalt feeder, each of the aggregate feeders, the supplemental fine aggregate feeder, if used, and the combined aggregate feeder shall be equipped with devices by which the rate of feed can be determined while the plant is in full operation.

The combined aggregate shall be weighed using a belt scale. The belt scale shall be of such accuracy that, when the plant is operating between 30 percent and 100 percent of belt capacity, the average difference between the indicated mass of material delivered and the actual mass delivered shall not exceed one percent of the actual mass for three individual 3-minute runs. For the 3 individual 3-minute runs, the indicated mass of material delivered shall not vary from the actual mass delivered by more than 2 percent of the actual mass.

The actual mass of material delivered for proportioning device calibrations shall be determined by a vehicle scale located at the plant site conforming to the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications. The vehicle scale shall be error checked within 24 hours of checking the plant's proportioning devices. The plant shall be equipped so that this accuracy check can be made prior to the first production operation for a project and at other times when requested by the Engineer.

The belt scale for the combined aggregate, the proportioning devices for supplemental fine aggregate, if used, and the asphalt proportioning meter shall be interlocked so that the rates of feed of the aggregates and asphalt will be adjusted automatically (at all production rates and production rate changes) to maintain the asphalt ratio (kilograms of asphalt per 100 kg of dry aggregate including supplemental fine aggregate, if used) designated in the mix design in conformance with the provisions in Section 39-2.03, "Asphalt Concrete Mixture," of this Section 11-1. The plant shall not be operated unless this automatic system is functioning and in good working condition.

Asphalt meters and aggregate belt scales used for proportioning aggregates and asphalt shall be equipped with rate-of-flow indicators to show the rates of delivery of asphalt and aggregate. Meters and scales shall be equipped with resettable totalizers so that the total amounts of asphalt and aggregate introduced into the asphalt concrete mixture can be

determined. Rate-of-flow indicators and totalizers for like materials shall be accurate within one percent when compared directly. The asphalt cement totalizer shall not register when the asphalt metering system is not delivering material to the mixer.

The bin or bins containing the fine aggregate and supplemental fine aggregate, if used, shall be equipped with vibrating units or other equipment that will prevent hang-up of material while the plant is operating. Each belt feeder shall be equipped with a device to monitor the depth of aggregate between the troughing rollers. The device for monitoring depth of aggregate shall automatically shut down the plant whenever the depth of aggregate is less than 70 percent of the target depth. To avoid erroneous shut down by normal fluctuations, a delay between sensing less than 70 percent flow and shutdown of the plant will be permitted, as determined by the Engineer, at the time of the initial California Test 109. A second device shall be located either in the stream of aggregate beyond the belt or where it will monitor movement of the belt by detecting revolutions of the tail pulley on the belt feeder. The device for monitoring no-flow or belt movement, as the case may be, shall stop the plant automatically and immediately when there is no flow. The plant shall not be operated unless both low-flow and no-flow monitoring devices are in good working condition and functioning properly.

For continuous pugmill mixing plants, an aggregate sampling device that will provide a 25-kg to 40-kg sample of the combined aggregate while the plant is in full operation shall be provided in advance of the point where the aggregate enters the mixer.

For drier-drum mixing plants, an aggregate sampling device that will provide a 25-kg to 40-kg sample of the combined aggregate while the plant is in full operation shall be provided in advance of the point where the aggregate enters the drier-drum mixer.

When supplemental fine aggregate is used, a sampling device shall be installed in each feed line or surge tank preceding the proportioning device for the supplemental fine aggregate.

39-7.04 (BLANK)

39-7.05 MIXING

Aggregate, supplemental fine aggregate, and asphalt binder shall be mixed in a batch mixer, continuous mixing pugmill mixer, or continuous mixing drier-drum. The charge in a batch mixer, or the rate of feed to a continuous mixer, shall not exceed that which will permit complete mixing of the material. Dead areas in the mixer, in which the material does not move or is not sufficiently agitated, shall be corrected by a reduction in the volume of material or by other adjustments.

Asphalt binder shall be at a temperature of not less than 120°C nor more than 190°C when added to the aggregate.

The temperature of the aggregate before adding the binder shall not be more than 165°C.

39-7.05A Batch Mixing

When asphalt concrete is produced by batch mixing, the mixer shall be equipped with a sufficient number of paddles of a type and arrangement so as to produce a properly mixed batch.

The binder shall be introduced uniformly into the mixer along the center of the mixer parallel to the mixer shafts, or by pressure spraying. When a pan is used, it shall be equipped with movable vanes in order that the flow of binder may be directed across the width of the pan, as desired. The vanes shall be equipped with a means for quick adjustment, and a positive lock to prevent shifting.

The mixer platform shall be of ample size to provide safe and convenient access to the mixer and other equipment. The mixer housing and weighbox housing shall be equipped with gates of ample size to permit ready sampling of the discharge of aggregate from each of the plant bins and from each feed line or surge tank of supplemental fine aggregate, if used. The Contractor shall provide a sampling device capable of delivering a representative sample of sufficient size to permit the required tests.

The mixer shall be equipped with a timing device that will indicate by a definite audible or visual signal the expiration of the mixing period. The device shall measure the time of mixing within 2 seconds.

The time of mixing a batch shall begin on the charging stroke of the weighhopper dumping mechanism and shall end when discharge is started. Mixing shall continue until a homogeneous asphalt concrete mixture of uniformly distributed and properly coated aggregates of unchanging appearance is produced. The time of mixing shall be not less than 30 seconds.

An interval timer shall control the time of mixing. The interval timer shall be interlocked so that the mixer cannot be discharged until the materials have been mixed for the full amount of time specified.

39-7.05B Continuous Mixing

Continuous mixing plants shall utilize pugmill or drier-drum mixers.

When asphalt concrete is produced by pugmill mixing, the mixer shall be equipped with paddles of a type and arrangement to provide sufficient mixing action and movement to the asphalt concrete mixture to produce properly mixed asphalt concrete. The combined aggregate shall be fed directly from the drier to the mixer at a uniform and controlled rate.

Mixing shall continue until a homogeneous asphalt concrete mixture of thoroughly and uniformly coated aggregates of unchanging appearance is produced at the discharge point from the mixer.

The temperature of the completed asphalt concrete mixture shall not exceed 165°C upon discharge from the mixer.

The mixer shall discharge into a storage silo with a capacity of not less than that specified in Section 39-7.06, "Asphalt Concrete Storage," of this Section 11-1. The Contractor shall provide a means of diverting the flow of asphalt concrete away from the silo to prevent incompletely mixed portions of the asphalt concrete mixture from entering the silo.

39-7.06 ASPHALT CONCRETE STORAGE

When asphalt concrete is stored, it shall be stored only in silos. Asphalt concrete shall not be stockpiled. The minimum quantity of asphalt concrete in a silo during mixing shall be 18 tonnes except for the period immediately following a shut-down of the plant of 2 hours or more. A means shall be provided to indicate that storage in each silo is being maintained as required.

Storage silos shall be equipped with a surge-batcher sized to hold a minimum of 1800 kg of material. A surge-batcher consists of equipment placed at the top of the storage silo that catches the continuous delivery of the completed asphalt concrete mix and changes it to individual batch delivery to prevent the segregation of product ingredients as the completed asphalt concrete mix is placed into storage. The surge-batcher shall be center loading and shall be constructed to prevent material buildup. Rotary chutes shall not be used as surge-batchers.

The surge-batcher shall be independent and distinct from conveyors or chutes used to collect or direct the completed asphalt concrete mixture being discharged into storage silos and shall be the last device to handle the material before it enters the silo. Multiple storage silos shall be served by an individual surge-batcher for each silo. Material handling shall be free of oblique movement between the highest elevation (conveyor outfall) and subsequent placement in the silo. Discharge gates on surge-batchers shall be automatic in operation and shall discharge only after a minimum of 1800 kg of material has been collected and shall close before the last collected material leaves the device. Discharge gate design shall prevent the deflection of material during the opening and closing operation.

Asphalt concrete stored in excess of 18 hours shall not be used in the work. Asphalt concrete mixture containing hardened lumps shall not be used. A storage facility that contained the material with the hardened lumps shall not be used for further storage until the cause of the lumps is corrected.

39-7.07 ASPHALT CONCRETE PLANTS

Plants, including commercial plants, that produce asphalt concrete subject to these specifications shall conform to the provisions in Section 7-1.01F, "Air Pollution Control," of the Standard Specifications, and shall be equipped with a wet-tube dust washer or equal and other devices that will reduce the dust emission to the degree that adjacent property is not damaged. The washer and other equipment shall function efficiently when the plant is in operation.

During production, petroleum products such as diesel fuel and kerosene shall not be used as a release agent on belts, conveyors, hoppers, or hauling equipment.

Plants shall be equipped with an inspection dock constructed so that a quality control technician or inspector standing on the dock can inspect the completed asphalt concrete mixture and take samples, as necessary, from the hauling vehicle before the vehicle leaves the plant site. This inspection dock shall allow the hauling vehicle to pull alongside and shall meet applicable safety requirements of the California Division of Occupational Safety and Health. Haul vehicle drivers shall be instructed to stop at the dock whenever a quality control technician or inspector is on the dock and to remain there until directed to leave by that individual.

39-8 SUBGRADE, PRIME COAT, PAINT BINDER (TACK COAT), AND PAVEMENT REINFORCING FABRIC

39-8.01 SUBGRADE

Immediately prior to applying prime coat or paint binder (tack coat), or immediately prior to placing the asphalt concrete when a prime coat or paint binder (tack coat) is not required, the subgrade to receive asphalt concrete shall conform to the compaction requirement and elevation tolerances specified for the material involved and shall be free of loose or extraneous material. If the asphalt concrete is to be placed on an existing base or pavement that was not constructed as part of the contract, the surface shall be cleaned by sweeping, flushing or other means to remove loose particles of paving, dirt, and other extraneous material immediately before applying the prime coat or paint binder (tack coat).

39-8.02 PRIME COAT AND PAINT BINDER (TACK COAT)

A prime coat of liquid asphalt shall be applied to the areas to be surfaced when there is a contract item for the work or when the work is required in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Prime coat shall be applied only to those areas designated by the Engineer.

Prime coat shall be applied at the approximate total rate of 1.15 L per square meter of surface covered. The exact rate and number of applications will be determined by the Engineer.

Prime coat shall be applied at a temperature conforming to the range of temperatures specified in Section 93-1.03, "Mixing and Applying," of the Standard Specifications for distributor application of the grade of liquid asphalt being used.

Prime coat or paint binder (tack coat) shall be applied in advance of placing the surfacing only as far as shall be approved by the Engineer. When asphaltic emulsion is used as paint binder (tack coat), asphalt concrete shall not be placed until the applied asphaltic emulsion has completely changed color from brown to black.

Immediately in advance of placing asphalt concrete, additional prime coat or paint binder (tack coat) shall be applied as directed by the Engineer to areas where the prime coat or paint binder (tack coat) has been damaged. Loose or extraneous material shall be removed and no additional compensation will be allowed therefor.

39-8.03 PAVEMENT REINFORCING FABRIC

Pavement reinforcing fabric shall be placed on existing pavement to be surfaced or between layers of asphalt concrete when such work is shown on the plans, or specified in "Asphalt Concrete" in Section 10-1, of these special provisions, or ordered by the Engineer.

Immediately prior to placing binder, pavement reinforcing fabric, and asphalt concrete surfacing, the pavement shall be cleaned of loose and extraneous materials such as, but not limited to, vegetation, sand, dirt, gravel and water.

Before placing the pavement reinforcing fabric, a binder of paving asphalt Grade AR-8000 shall be applied uniformly to the surface to receive the pavement reinforcing fabric at a rate of not less than 1.15 L per square meter of surface covered. Pavement reinforcing fabric shall not be placed in areas of conform tapers when the thickness of the overlying asphalt concrete will be 40 mm or less. When pavement reinforcing fabric is placed in areas of conform tapers the binder shall be spread at the approximate rate of 1.4 L per square meter of surface covered. The exact rate will be determined by the Engineer. The binder shall be applied to a width equal to the width of the fabric mat plus 75 mm on each side.

Asphaltic emulsion shall not be substituted for paving asphalt binder for pavement reinforcing fabric.

Before applying binder, large cracks, spalls, and depressions in existing pavement shall be repaired as directed by the Engineer and, if not included in the item, the repair work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

The pavement reinforcing fabric shall be aligned and placed with no wrinkles that lap. The test for lapping shall be made by gathering together the pavement reinforcing fabric in a wrinkle. If the height of the doubled portion of extra fabric is 15 mm or more, the fabric shall be cut to remove the wrinkle, then lapped in the direction of paving. Lap in excess of 50 mm shall be removed.

If manual laydown methods are used, the pavement reinforcing fabric shall be unrolled, aligned, and placed in increments of approximately 9 m.

Adjacent borders of the pavement reinforcing fabric shall be lapped 50 mm to 100 mm. The preceding roll shall be lapped 50 mm to 100 mm over the following roll in the direction of paving at ends of rolls or at a break. At pavement reinforcing fabric overlays, both the binder and the fabric shall overlap previously placed fabric by the same amount.

Seating of the pavement reinforcing fabric with rolling equipment after placing will be permitted. Turning of the paving machine and other vehicles shall be gradual and kept to a minimum to avoid damage to the fabric.

A small quantity of asphalt concrete, to be determined by the Engineer, may be spread over the pavement reinforcing fabric immediately in advance of placing asphalt concrete surfacing in order to prevent fabric from being damaged by construction equipment.

Pavement reinforcing fabric shall not be exposed to public traffic, Contractor's equipment or elements that will damage the fabric prior to placement of asphalt concrete surfacing, as determined by the Engineer. Public access cross traffic may be allowed to cross the fabric under traffic control after the Contractor has placed a small quantity of asphalt concrete over the fabric.

Care shall be taken to avoid tracking binder material onto the pavement reinforcing fabric or distorting the fabric during seating of the fabric with rolling equipment. If necessary to protect the pavement reinforcing fabric, exposed binder material may be covered lightly with sand.

39-9 SPREADING AND COMPACTING EQUIPMENT

39-9.01 SPREADING EQUIPMENT

Asphalt pavers shall be self-propelled mechanical spreading and finishing equipment provided with a screed or strike-off assembly capable of distributing the material to not less than the full width of a traffic lane unless otherwise approved by the Engineer. Screed action shall include cutting, crowding or other practical action that is effective on the asphalt concrete mixture without tearing, shoving or gouging and that produces a surface texture of uniform appearance. The screed shall be adjustable to the required section and thickness. The screed shall be provided with a suitable full width compacting device.

Pavers that leave ridges, indentations or other marks in the surface shall not be used unless the ridges, indentations or marks are eliminated by rolling or prevented by adjustment in the operation.

When end dump haul vehicles are used, the asphalt paver shall operate independently of the vehicle being unloaded or shall be capable of propelling the vehicle being unloaded. The load of the haul vehicle shall be limited to that which will insure satisfactory spreading. While being unloaded, the haul vehicle shall be in contact with the machine and the brakes on the haul vehicle shall not be depended upon to maintain contact between the vehicle and the machine.

No portion of the mass of hauling or loading equipment, other than the connection, shall be supported by the asphalt paver. No vibrations or other motions of the loader that could have a detrimental effect on the riding quality of the completed pavement shall be transmitted to the paver.

When asphalt concrete is placed directly upon asphalt treated permeable base, the asphalt concrete shall be placed in a manner and with equipment that will not disturb or displace the asphalt treated permeable base.

39-9.02 COMPACTING EQUIPMENT

A sufficient number of rollers shall be provided to obtain the specified compaction and surface finish required by this Section 11-1. Rollers shall be sized to achieve the required results.

Rollers shall be equipped with pads and water systems that prevent sticking of the asphalt concrete mixtures to the pneumatic or steel-tired wheels. A parting agent that will not damage the asphalt concrete mixture may be used to aid in preventing the asphalt concrete mixture from sticking to the wheels.

39-10 SPREADING AND COMPACTING

39-10.01 GENERAL REQUIREMENTS

Asphalt concrete shall be handled, spread, and compacted in a manner which is in conformance with this Section 11-1, "Quality Control / Quality Assurance."

Asphalt concrete shall be placed in such a manner that cracking, shoving, and displacement will be avoided.

Type A and Type B asphalt concrete shall be placed only when the ambient temperature is above 10°C.

Asphalt concrete shall not be placed when the underlying layer or surface is frozen or not dry or when weather conditions will prevent proper handling, finishing or compaction of the mixture.

Asphalt concrete shall be spread and compacted in the layers and thicknesses indicated in the following table:

Asphalt Concrete Layers and Thickness

Total Thickness Shown on the Plans*	Number of Layers	Top Layer Thickness (Millimeters)		Next Lower Layer Thickness (Millimeters)		All Other Lower Layers Thickness (Millimeters)	
		Min.	Max.	Min.	Max.	Min.	Max.
75 mm or less	1	----	-----	----	----	----	----
76 through 89 mm	2	35	45	35	45	----	----
90 through 135 mm	2	45	60	45	75	—	—
136 mm or more	**	45	60	45	75	45	120

Notes:
*When pavement reinforcing fabric is shown to be placed between layers of asphalt concrete, the thickness of asphalt concrete above the pavement reinforcing fabric shall be considered to be the "Total Thickness Shown on the Plans" for the purpose of spreading and compacting the asphalt concrete above the pavement reinforcing fabric.
**At least 3 layers if total thickness is more than 135 mm and less than 255 mm. At least 4 layers if total thickness is 255 mm or more.

A layer shall not be placed over a layer that exceeds 75 mm in compacted thickness until the temperature of the layer being covered is less than 70°C at mid-depth unless approved by the Engineer.

Asphalt concrete to be placed on shoulders, and on other areas off the traveled way having a width of 1.50 m or more, shall be spread in the same manner as specified above.

The completed mixture shall be deposited on the roadbed at a uniform quantity per linear meter, as necessary to provide the required compacted thickness without resorting to spotting, picking-up or otherwise shifting the mixture. During transporting, spreading and compacting, petroleum products such as diesel fuel and kerosene shall not be used as a release agent on trucks, spreaders or compactors in contact with the asphalt concrete.

Segregation shall be avoided. Surfacing shall be free from pockets of coarse or fine material. Asphalt concrete containing hardened lumps shall not be used.

Longitudinal joints in the top layer of Type A or Type B asphalt concrete shall correspond with the edges of planned traffic lanes. Longitudinal joints in other layers shall be offset not less than 150 mm alternately each side of the edges of traffic lanes.

Unless otherwise provided herein or approved by the Engineer, the top layer of asphalt concrete for shoulders, tapers, transitions, road connections, private drives, curve widenings, chain control lanes, turnouts, left-turn pockets, and other areas shall not be spread before the top layer of asphalt concrete for the adjoining through lane has been spread and compacted. At locations where the number of lanes is changed, the top layer for the through lanes shall be paved first. When existing pavement is to be surfaced and the specified thickness of asphalt concrete to be spread and compacted on the existing pavement is 75 mm or less, the shoulders or other adjoining areas may be spread simultaneously with the through lane provided the completed surfacing conforms to the requirement of this Section 11-1. Tracks or wheels of spreading equipment shall not be operated on the top layer of asphalt concrete until final compaction has been completed.

At those locations shown on the plans, as specified in "Asphalt Concrete" in Section 10-1, "General," of these special provisions, or as directed by the Engineer, the asphalt concrete shall be tapered or feathered to conform to existing surfacing or to other highway and non-highway facilities.

At locations where the asphalt concrete is to be placed over areas inaccessible to spreading and rolling equipment, the asphalt concrete shall be spread by practical means to obtain the specified results and shall be compacted thoroughly to the required lines, grades, and cross sections by means of pneumatic tampers or by other methods that will produce the same degree of compaction as pneumatic tampers.

39-10.02 PRODUCTION START-UP EVALUATION AND NUCLEAR DENSITY TEST STRIPS

The Contractor shall demonstrate that the proposed asphalt concrete mixture is being produced and placed on the roadway in conformance with this Section 11-1, "Quality Control / Quality Assurance." The production start-up evaluation shall demonstrate that the aggregates and asphalt concrete mixture conform to the requirements of Table 39-3, "Asphalt Concrete Mixture Requirements," and of Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1 when produced using the plant proposed for this project. The nuclear density test strip serves to provide the Contractor with a location to develop a correlation between cores taken from the test strip and the Contractor's and Engineer's nuclear density gage readings taken from the same locations on the test strip and for the Contractor to demonstrate the ability to achieve a minimum of 96 percent relative compaction.

Production start-up evaluation and the nuclear density test strip may be constructed separately or at the same time to serve both purposes. Asphalt concrete used in the nuclear density test strip shall be representative of the asphalt concrete that shall be placed in the project.

Should the test results or testing program fail to meet these criteria, production will be suspended and the Contractor shall resolve the problem in conformance with the provisions in Section 39-6, "Dispute Resolution," of this Section 11-1.

Attention is directed to longitudinal and transverse construction joint requirements specified in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Test data used for the production start up evaluation and the nuclear gage test strips shall not be included with the test data used for acceptance of the work in conformance with the provisions in Section 39-11, "Acceptance of Work," of this Section 11-1.

A production start-up evaluation and a nuclear density test strip shall be used when production of asphalt concrete has been resumed following a suspension of production due to unsatisfactory material quality as specified in Section 39-4.04, "Contractor Process Control," Section 39-4.05, "Contractor Quality Control," and Section 39-11.02A, "General" of this Section 11-1.

39-10.02A Production Start-Up Evaluation

Before or on the first day of asphalt concrete production, the Contractor shall produce a trial quantity of between 250 tonnes and 500 tonnes of asphalt concrete to demonstrate that asphalt concrete produced for this project conforms to the quality characteristics of this Section 11-1. The location of the production start-up evaluation shall be approved by the Engineer.

Asphalt concrete shall be produced by production procedures intended for the entire project. Production of asphalt concrete shall stop after placement of the trial quantity of asphalt concrete. Asphalt concrete production and placement may resume after the quality characteristics of the asphalt concrete mixture have been tested and found to be in conformance with the quality requirements of this Section 11-1.

The Contractor shall randomly obtain 3 aggregate samples from the plant and 3 asphalt concrete mixture samples from the mat behind the paver. Each sample from the plant shall be split into 4 portions; each sample from the mat shall be split into 4 portions. One portion of each sample shall be tested by the Contractor and one portion of each sample shall be provided to the Engineer for testing. The remaining portions shall be delivered to the Engineer and stored for dispute resolution should the test results not conform to this Section 11-1. The Contractor and the Engineer shall evaluate the samples for conformance to the requirements for sand equivalent, stability, percent air voids, and the quality characteristics

designated in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. The percent air voids of the asphalt concrete mixture shall be within ± 1.0 percent of the percent air voids designated in the Contractor's mix design.

The trial quantity of asphalt concrete will be accepted if:

A. Not more than 3 of the test results from the combined 6 test results from the Contractor's and Engineer's samples for quality characteristics indexed 2, 3, 4, and 5 in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1 are outside the specified limits.
B. Not more than one of the test results from the combined 6 test results from the Contractor's and the Engineer's samples for sand equivalent, stability, percent air voids or critical start-up characteristics designated in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1 are outside the specified limits.

If the test results from the combined 6 test results fail to meet the conditions above, corrective action shall be taken, and a new trial quantity of asphalt concrete shall be placed and evaluated in conformance with the provisions in this section to demonstrate conformance. If the test results from the combined 6 test results fail to meet the requirements above, then the trial quantity of asphalt concrete will be rejected.

The testing program will be considered adequate only if the average of the Contractor's test results and the average of the Engineer's test results for sand equivalent, stability, percent air voids, and the quality characteristics designated in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1 are within the allowable testing difference designated in Table 39-6, "Allowable Testing Difference," of this Section 11-1.

The Contractor shall not proceed to regular production until the requirements of this Section 39-10.02A, "Production Start-Up Evaluation" have been met. At the request of the Contractor, the Engineer may elect to leave the asphalt concrete which does not meet the requirements of this Section 39-10.02A in place if mitigation at the Contractor's expense can be agreed to. If this quantity of asphalt concrete is left in place, the Contractor will be paid 75 percent of the contract price paid per tonne for asphalt concrete.

The Contractor shall establish a correlation factor for stability of cured versus uncured briquettes. From a single split sample of asphalt concrete, 6 briquettes shall be fabricated. Three of the 6 briquettes shall be cured for 15 hours in conformance with the requirements of California Test 366 and 3 briquettes shall not be cured. The difference between the average stability value determined for the cured and the uncured specimens shall be considered the correlation factor, and shall be applied to stability values determined on uncured samples throughout the life of the project. The correlation factor may range from zero to 4. If the correlation factor is less than zero, a factor of zero shall be applied. If the factor is greater than 4, the correlation factor shall be approved by the Engineer.

39-10.02B Nuclear Density Test Strip

On the first day of placement of each layer of asphalt concrete the Contractor shall place a test strip in conformance with the requirements of California Test 375. The purpose of the test strip is to determine a correlation between cores taken from the test strip and the nuclear density gage readings taken at the core locations and to demonstrate that the asphalt concrete can be placed and compacted to the standards of this Section 11-1, "Quality Control / Quality Assurance." Asphalt concrete used in the nuclear density test strip shall be representative of the asphalt concrete that shall be placed in the project. The location for the nuclear density test strip shall be approved by the Engineer.

The Contractor shall place nuclear density test strips until conditions of the test method and this Section 11-1 have been met. The requirements of this section and the test method shall apply for the correlation of each gage that is used to determine relative compaction for this project. Relative compaction results will not be accepted if they have been determined using a nuclear gage that has not been correlated using a test strip.

Asphalt concrete in test strips may be left in place under the following conditions:

A. If the relative compaction for the test strip is determined to be 96 percent or greater, the Contractor will be paid at the contract price per tonne of asphalt concrete.
B. If the relative compaction for the test strip is determined to be less than 96 percent but greater than 93 percent, the Contractor will be paid at 75 percent of the contract price per tonne of asphalt concrete. A new test strip will be required, and mitigation measures shall be at Contractor's expense.

Asphalt concrete in test strips will be rejected when the relative compaction for the test strip is below 93 percent. Production and placement shall not begin until the Contractor has demonstrated the ability to achieve 96 percent relative compaction in conformance with this Section 11-1.

39-10.03 SPREADING

Layers shall be spread with an asphalt paver, unless otherwise specified or approved by the Engineer. Asphalt pavers shall be operated in such a manner as to insure continuous and uniform movement of the paver.

In advance of spreading asphalt concrete over an existing base, surfacing or bridge deck, if there is a contract item for asphalt concrete (leveling) or if ordered by the Engineer, asphalt concrete shall be spread by mechanical means that will produce a uniform smoothness and texture. Asphalt concrete (leveling) shall include, but not be limited to, the filling and leveling of irregularities and ruts. Asphalt concrete used to change the cross slope or profile of an existing surface shall not be considered as asphalt concrete (leveling).

Paint binder (tack coat) shall be applied to each layer in advance of spreading the next layer.

Before placing the top layer adjacent to cold transverse construction joints, the joints shall be trimmed to a vertical face on a neat line. Transverse joints shall be tested with a 3.6-m ± 0.06-m straightedge and shall be cut back for surface smoothness as required in conformance with Section 39-10.04, "Compacting," of this Section 11-1. Connections to existing surfacing shall be feathered to conform to the requirements for smoothness. Longitudinal joints shall be trimmed to a vertical face and on a neat line if the edges of the previously laid surfacing are, in the opinion of the Engineer, in such a condition that the quality of the completed joint will be affected.

39-10.04 COMPACTING

Compacting equipment shall conform to the provisions in Section 39-9.02, "Compacting Equipment," of this Section 11-1, "Quality Control / Quality Assurance."

Rolling shall commence at the lower edge and shall progress toward the highest portion. When compacting layers that exceed 75 mm in compacted thickness, rolling shall commence at the center and shall progress outwards.

Asphalt concrete shall be compacted to a relative compaction of not less than 96 percent and shall be finished to the lines, grades, and cross sections shown on the plans. In-place density of asphalt concrete will be determined prior to opening the pavement to public traffic. No rolling will be permitted after the asphalt concrete temperature is below 60°C.

Asphalt concrete placed in dig outs, as a leveling course, for slope correction, for detours not included in the finished roadway prism, in areas where in the judgment of the Engineer compaction or compaction measurement by conventional methods is impeded or on the uppermost lift of shoulders with rumble strips shall be compacted by a method approved by the Engineer.

Relative compaction shall be determined in conformance with the requirements of California Test 375 except that only a nuclear gauge with thin lift capability shall be used for asphalt concrete layer of 30 mm to 59 mm in thickness. Laboratory specimens shall be compacted in conformance with the requirements of California Test 304. Test locations will be established for asphalt concrete areas to be tested, as specified in California Test 375. If the Contractor compacts the asphalt concrete in any form or quantity after sites for testing have been chosen in conformance with the requirements of California Test 375 or after California Test 375 has begun, the quality control tester shall choose a new set of random numbers for locating test sites.

Upon completion of rolling operations, if ordered by the Engineer, the asphalt concrete shall be cooled by applying water. Applying water shall conform to the provisions in Section 17, "Watering," of the Standard Specifications.

The completed surfacing shall be thoroughly compacted, smooth, and free from ruts, humps, depressions, or irregularities. Ridges, indentations or other objectionable marks left in the surface of the asphalt concrete by blading or other equipment shall be eliminated by rolling or other suitable means. The use of equipment that leaves ridges, indentations or other objectionable marks in the asphalt concrete shall be discontinued.

When a straightedge 3.6 m ± 0.06-m long is laid on the finished surface and parallel with the centerline, the surface shall not vary more than 3-mm from the lower edge of the straightedge. The transverse slope of the finished surface shall be uniform to a degree such that no depressions greater than 6 mm are present when tested with a straightedge 3.6 m ± 0.06-m long in a direction transverse to the centerline and extending from edge to edge of a 3.6-m traffic lane.

Pavement within 15 m of a structure or approach slab shall conform to the smoothness tolerances specified in Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications.

39-11 ACCEPTANCE OF WORK

39-11.01 GENERAL

The Engineer shall select the procedure used to determine the quantities of asphalt concrete for acceptance and payment determination in conformance with the provisions of this Section 11-1, "Quality Control / Quality Assurance."

Quality control test results that have been verified shall form the basis for statistical evaluation of the work in conformance with Section 39-11.02, "Statistical Evaluation and Determination of Pay Factor," of this Section 11-1. The quality requirements on which statistical evaluation will be based are specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1.

Work determined to be in conformance with the provisions of this Section 11-1 will be accepted and paid for at the contract price per tonne for asphalt concrete and may be subject to compensation adjustment in conformance with Section 39-11.02C, "Pay Factor Determination and Compensation Adjustment," of this Section 11-1.

Work that is not in compliance with the provisions of this Section 11-1 may be rejected by the Engineer and shall be removed and replaced at the Contractor's expense.

When there are fewer than 5 verified quality control tests, the work will be accepted or rejected based on whether the individual test results meet the quality requirements specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Section 39-11.02, "Statistical Evaluation and Pay Factor Determination," of this Section 11-1 shall not apply.

Aggregates, asphalt binder, and asphalt concrete mixtures that do not conform to this Section 11-1 shall not be used.

The Engineer may reject a quantity of material that is determined to be defective based on visual inspection or noncompliance with the provisions of this Section 11-1.

39-11.02 STATISTICAL EVALUATION AND DETERMINATION OF PAY FACTOR

Statistical evaluation of the work shall be used to verify the Contractor's quality control test results to determine compliance with this Section 11-1, "Quality Control / Quality Assurance."

39-11.02A General

The quality characteristics to be evaluated and the specification limits are specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Asphalt content, aggregate gradation (600-µm and 75-µm sieves), and relative compaction shall be considered for purposes of this Section 11-1 to be critical quality characteristics.

A lot represents the total quantity of asphalt concrete placed. More than one lot will occur if changes in the target values, material sources or mix design are requested by the Contractor and made in conformance with this Section 11-1 or if production of asphalt concrete is suspended due to unsatisfactory performance. However, asphalt concrete placed in dig outs, as a leveling course, for slope correction, for detours not to be included in the finished roadway prism, in areas where in the judgment of the Engineer compaction or compaction measurement by conventional methods is impeded or on the uppermost lift of shoulders with rumble strips shall be considered as a separate lot from other asphalt concrete. In addition, a new lot may be designated by the Engineer if the production and placement have been suspended for longer than 30 days due to seasonal suspension of phases of work.

A minimum of 5 samples shall be required to perform a statistical evaluation. The maximum obtainable pay factor with the 5 samples shall be 1.01. A minimum of 8 samples shall be required to obtain a pay factor of 1.05. If the sampling frequencies and quantity of work would otherwise result in fewer than 8 samples, the Contractor may submit a written request to increase the sampling frequency to provide a minimum of 8 samples. The request shall be included in the Quality Control Plan.

The lot will be accepted and a final pay factor determined when the Contractor's sampling, inspection, and test results are completed, have been submitted and evaluated, and the Engineer has visually inspected the pavement. Quality control test results shall be verified using the *t*-test in conformance with the provisions of Section 39-5.03, "Verification," of this Section 11-1 before the results will be used in considering the acceptance of asphalt concrete.

If the current composite pay factor of a lot is greater than 0.90, the lot will be accepted, provided the lowest single pay factor is not within the reject portion of Table 39-8, "Pay Factors," of this Section 11-1. If the lowest single pay factor is within the reject portion of Table 39-8, "Pay Factors," of this Section 11-1, the lot will be rejected. Rejected asphalt concrete shall be removed from the project site at the Contractor's expense.

If the current composite pay factor of a lot is less than 0.90, production of asphalt concrete shall be terminated and corrective action taken. Upon approval of the Engineer, up to 1000 tonnes of asphalt concrete may be placed to demonstrate that the asphalt concrete is once again in conformance with this Section 11-1. Production of asphalt concrete shall not start until the Engineer has received test results confirming conformance with this Section 11-1. A new lot will be established when production resumes.

If a pay factor for a critical quality characteristic designated in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1 is less than 0.90 for the lot or is within the rejection range for the last 5 tests, production of asphalt concrete shall be terminated and corrective action taken. Upon approval of the Engineer, up to 1000 tonnes of asphalt concrete may be placed to demonstrate that the asphalt concrete is once again in conformance with this Section 11-1. Production of asphalt concrete shall not start until the Engineer has received test results confirming conformance with this Section 11-1. A new lot will be established when production resumes.

Defective asphalt concrete may be voluntarily removed and replaced with new asphalt concrete to avoid a low pay factor. New material will be sampled, tested, and evaluated in conformance with this Section 11-1.

39-11.02B Statistical Evaluation

The Variability-Unknown/Standard Deviation Method will be used to determine the estimated percentage of the lot that is outside specification limits. The number of significant figures used in the calculations will be in conformance with the requirements of AASHTO Designation R-11, Absolute Method.

The estimated percentage of work that is outside of the specification limits for each quality characteristic will be determined as follows:

1. Calculate the arithmetic mean ($\overline{X}$) of the test values;

$$\overline{X} = \frac{\Sigma x}{n}$$

where:

$\sum$	=	summation of
x	=	individual test values
n	=	total number of test values

2. Calculate the standard deviation (s);

$$s = \sqrt{\frac{n\Sigma (x^2)-(\Sigma x)^2}{n(n-1)}}$$

where:

$\sum(x^2)$	=	summation of the squares of individual test values
$(\sum x)^2$	=	summation of the individual test values squared
n	=	total number of test values

3. Calculate the upper quality index (Q_u);

$$Q_u = \frac{USL - \overline{X}}{s}$$

where:

USL	=	upper specification limit
s	=	standard deviation
$\overline{X}$	=	arithmetic mean

(Note: The USL is equal to the upper specification limit or the target value plus the production tolerance.)

4. Calculate the lower quality index (Q_L);

$$Q_L = \frac{\overline{X} - LSL}{s}$$

where:

LSL=		lower specification limit or target value minus production tolerance
s	=	standard deviation
$\overline{X}$	=	arithmetic mean

5. From Table 39-7, "Estimated Percent of Work Outside Specification Limits," of this Section 11-1, determine P_U ;

where:

P_U = the estimated percentage of work outside the USL.
(P_U = 0, when USL is not specified.)

6. From Table 39-7, "Estimated Percent of Work Outside Specification Limits," of this Section 11-1, determine P_L;

where:

P_L = the estimated percentage of work outside the LSL.

(P_L = 0, when LSL is not specified.)

7. Calculate the total estimated percentage of work outside the USL and LSL, Percent Defective;

   Percent Defective = $P_U + P_L$

   where:
   P_U = the estimated percentage of work outside the USL
   P_L = the estimated percentage of work outside the LSL

8. Repeat Steps 1 through 7 for each quality characteristic listed for acceptance.

39-11.02C Pay Factor Determination and Compensation Adjustment

The pay factor and compensation adjustment for a lot will be determined as follows:

1. From Table 39-8, "Pay Factors," of this Section 11-1, determine the pay factor for each quality characteristic, (PF_{QC}), using the total number of test result values and the total estimated percentage outside the specification limits ($P_U + P_L$) from Step 7 in Section 39-11.02B, "Statistical Evaluation," of this Section 11-1.
2. The pay factor for the lot is a composite of single pay factors determined for each quality characteristic designated in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. The following formula is used:

$$PF_C = \sum_{i=1}^{8} w_i \, PF_{QC_i}$$

   where:
   PF_C = the composite pay factor for the lot,
   PF_{QC} = the pay factor for the individual quality characteristic,
   w = the weighting factor listed in Table 39-9, and
   i = the quality characteristic index number in Table 39-9.
3. Payment to the Contractor for the lot of asphalt concrete will be subject to a compensation adjustment. The Compensation Adjustment Factor (CAF) will be determined as follows:

   $CAF = PF_C - 1$

4. The amount of the compensation adjustment will be calculated as the product of:

   a. the Compensation Adjustment Factor (CAF)
   b. the total tonnes represented in the lot, and
   c. the contract price paid per tonne for the item of asphalt concrete involved.

If the compensation adjustment is a negative value, the compensation adjustment will be deducted from moneys due, or that may become due, the Contractor under the contract. If the compensation adjustment is a positive value, the compensation adjustment will be added to moneys due, or that may become due, the Contractor under the contract.

Table 39-7.—ESTIMATED PERCENT OF WORK OUTSIDE SPECIFICATION LIMITS

P_U and/or P_L	Sample Size (n)												
	5	6	7	8	9	10-11	12-14	15-17	18-22	23-29	30-42	43-66	>66
	Upper Quality Index Q_U or Lower Quality Index Q_L												
0	1.72	1.88	1.99	2.07	2.13	2.20	2.28	2.34	2.39	2.44	2.48	2.51	2.56
1	1.64	1.75	1.82	1.88	1.91	1.96	2.01	2.04	2.07	2.09	2.12	2.14	2.16
2	1.58	1.66	1.72	1.75	1.78	1.81	1.84	1.87	1.89	1.91	1.93	1.94	1.95
3	1.52	1.59	1.63	1.66	1.68	1.71	1.73	1.75	1.76	1.78	1.79	1.80	1.81
4	1.47	1.52	1.56	1.58	1.60	1.62	1.64	1.65	1.66	1.67	1.68	1.69	1.70
5	1.42	1.47	1.49	1.51	1.52	1.54	1.55	1.56	1.57	1.58	1.59	1.59	1.60
6	1.38	1.41	1.43	1.45	1.46	1.47	1.48	1.49	1.50	1.50	1.51	1.51	1.52
7	1.33	1.36	1.38	1.39	1.40	1.41	1.41	1.42	1.43	1.43	1.44	1.44	1.44
8	1.29	1.31	1.33	1.33	1.34	1.35	1.35	1.36	1.36	1.37	1.37	1.37	1.38
9	1.25	1.27	1.28	1.28	1.29	1.29	1.30	1.30	1.30	1.31	1.31	1.31	1.31
10	1.21	1.23	1.23	1.24	1.24	1.24	1.25	1.25	1.25	1.25	1.25	1.26	1.26
11	1.18	1.18	1.19	1.19	1.19	1.19	1.20	1.20	1.20	1.20	1.20	1.20	1.20
12	1.14	1.14	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15
13	1.10	1.10	1.10	1.10	1.10	1.10	1.11	1.11	1.11	1.11	1.11	1.11	1.11
14	1.07	1.07	1.07	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
15	1.03	1.03	1.03	1.03	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02
16	1.00	0.99	0.99	0.99	0.99	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
17	0.97	0.96	0.95	0.95	0.95	0.95	0.94	0.94	0.94	0.94	0.94	0.94	0.94
18	0.93	0.92	0.92	0.92	0.91	0.91	0.91	0.91	0.90	0.90	0.90	0.90	0.90
19	0.90	0.89	0.88	0.88	0.88	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87
20	0.87	0.86	0.85	0.85	0.84	0.84	0.84	0.83	0.83	0.83	0.83	0.83	0.83
21	0.84	0.82	0.82	0.81	0.81	0.81	0.80	0.80	0.80	0.80	0.80	0.80	0.79
22	0.81	0.79	0.79	0.78	0.78	0.77	0.77	0.77	0.76	0.76	0.76	0.76	0.76
23	0.77	0.76	0.75	0.75	0.74	0.74	0.74	0.73	0.73	0.73	0.73	0.73	0.73
24	0.74	0.73	0.72	0.72	0.71	0.71	0.70	0.70	0.70	0.70	0.70	0.70	0.70
25	0.71	0.70	0.69	0.69	0.68	0.68	0.67	0.67	0.67	0.67	0.67	0.67	0.66

Table continues below

Table 39-7 (cont.).—ESTIMATED PERCENT OF WORK OUTSIDE SPECIFICATION LIMITS

P_U and/or P_L	Sample Size (n)												
	5	6	7	8	9	10-11	12-14	15-17	18-22	23-29	30-42	43-66	>66
	Upper Quality Index Q_U or Lower Quality Index Q_L												
26	0.68	0.67	0.67	0.65	0.65	0.65	0.64	0.64	0.64	0.64	0.64	0.64	0.63
27	0.65	0.64	0.63	0.62	0.62	0.62	0.61	0.61	0.61	0.61	0.61	0.61	0.60
28	0.62	0.61	0.60	0.59	0.59	0.59	0.58	0.58	0.58	0.58	0.58	0.58	0.57
29	0.59	0.58	0.57	0.57	0.56	0.56	0.55	0.55	0.55	0.55	0.55	0.55	0.54
30	0.56	0.55	0.54	0.54	0.53	0.53	0.52	0.52	0.52	0.52	0.52	0.52	0.52
31	0.53	0.52	0.51	0.51	0.50	0.50	0.50	0.49	0.49	0.49	0.49	0.49	0.49
32	0.50	0.49	0.48	0.48	0.48	0.47	0.47	0.47	0.46	0.46	0.46	0.46	0.46
33	0.47	0.48	0.45	0.45	0.45	0.44	0.44	0.44	0.44	0.43	0.43	0.43	0.43
34	0.45	0.43	0.43	0.42	0.42	0.42	0.41	0.41	0.41	0.41	0.41	0.41	0.40
35	0.42	0.40	0.40	0.39	0.39	0.39	0.38	0.38	0.38	0.38	0.38	0.38	0.38
36	0.39	0.38	0.37	0.37	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36
37	0.36	0.35	0.34	0.34	0.34	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.32
38	0.33	0.32	0.32	0.31	0.31	0.31	0.30	0.30	0.30	0.30	0.30	0.30	0.30
39	0.30	0.30	0.29	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28
40	0.28	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25
41	0.25	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23
42	0.23	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20
43	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18
44	0.16	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15
45	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13
46	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10
47	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08
48	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05
49	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03
50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Notes:

1. If the value of Q_U or Q_L does not correspond to a value in the table, use the next lower value.
2. If Q_U or Q_L are negative values, P_U or P_L is equal to 100 minus the table value for P_U or P_L.

Table 39-8.—PAY FACTOR

Pay Factor	Sample Size (n)												
	5	6	7	8	9	10-11	12-14	15-17	18-22	23-29	30-42	43-66	>66
	Maximum Allowable Percent of Work Outside Specification Limits for A Given Pay Factor ($P_U + P_L$)												
1.05				0	0	0	0	0	0	0	0	0	0
1.04			0	1	3	5	4	4	4	3	3	3	3
1.03		0	2	4	6	8	7	7	6	5	5	4	4
1.02		1	3	6	9	11	10	9	8	7	7	6	6
1.01	0	2	5	8	11	13	12	11	10	9	8	8	7
1.00	22	20	18	17	16	15	14	13	12	11	10	9	8
0.99	24	22	20	19	18	17	16	15	14	13	11	10	9
0.98	26	24	22	21	20	19	18	16	15	14	13	12	10
0.97	28	26	24	23	22	21	19	18	17	16	14	13	12
0.96	30	28	26	25	24	22	21	19	18	17	16	14	13
0.95	32	29	28	26	25	24	22	21	20	18	17	16	14
0.94	33	31	29	28	27	25	24	22	21	20	18	17	15
0.93	35	33	31	29	28	27	25	24	22	21	20	18	16
0.92	37	34	32	31	30	28	27	25	24	22	21	19	18
0.91	38	36	34	32	31	30	28	26	25	24	22	21	19
0.90	39	37	35	34	33	31	29	28	26	25	23	22	20
0.89	41	38	37	35	34	32	31	29	28	26	25	23	21
0.88	42	40	38	36	35	34	32	30	29	27	26	24	22
0.87	43	41	39	38	37	35	33	32	30	29	27	25	23
0.86	45	42	41	39	38	36	34	33	31	30	28	26	24
0.85	46	44	42	40	39	38	36	34	33	31	29	28	25
0.84	47	45	43	42	40	39	37	35	34	32	30	29	27
0.83	49	46	44	43	42	40	38	36	35	33	31	30	28
0.82	50	47	46	44	43	41	39	38	36	34	33	31	29
0.81	51	49	47	45	44	42	41	39	37	36	34	32	30
0.80	52	50	48	46	45	44	42	40	38	37	35	33	31
0.79	54	51	49	48	46	45	43	41	39	38	36	34	32
0.78	55	52	50	49	48	46	44	42	41	39	37	35	33
0.77	56	54	52	50	49	47	45	43	42	40	38	36	34
0.76	57	55	53	51	50	48	46	44	43	41	39	37	35
0.75	58	56	54	52	51	49	47	46	44	42	40	38	36
	60	57	55	53	52	51	48	47	45	43	41	40	37
	61	58	56	55	53	52	50	48	46	44	43	41	38
Reject	62	59	57	56	54	53	51	49	47	45	44	42	39
	63	61	58	57	55	54	52	50	48	47	45	43	40
	64	62	60	58	57	55	53	51	49	48	46	44	41
Reject Values Greater Than Those Shown Above													

Notes:

1. To obtain a pay factor when the estimated percent outside specification limits from Table 39-7, "Estimated Percent of Work Outside Specification Limits," does not correspond to a value in the table, use the next larger value.
2. The maximum obtainable pay factor is 1.05 (with a minimum of 8 test values).

Table 39-9.—MINIMUM QUALITY CONTROL REQUIREMENTS

Index (i)	Quality Characteristic	Specification Limits	Weighting Factor (w)	California Test	Minimum Sampling and Testing Frequency	Point of Sampling
1	**Asphalt Content** [2,3]	TV ± 0.5%	0.30	379 or 382	One sample per 500 tonnes or part thereof Not less than one sample per day	Mat behind paver
	Gradation			202	One sample per 500 tonnes or part thereof Not less than one sample per day	Batch Plant - from hot bins Drum Plant - from cold feed
2	19 or 12.5 mm [4]	TV ± 5	0.01			
3	9.5 mm	TV ± 6	0.01			
4	4.75 mm	TV ± 7	0.05			
5	2.36 mm	TV ± 5	0.05			
6	600 µm [2,3]	TV ± 4	0.08			
7	75 µm [2]	TV ± 2	0.10			
8	**Relative Compaction** [2]	96%	0.40	375 [5]	One sample per 500 tonnes or part thereof Not less than one test per day	Finished mat after final rolling
	Test Maximum Density			375	Per Test Method	Mat behind the paver
9	**Mix Moisture Content**	≤1%		370	One sample per 1000 tonnes or part thereof Not less than one sample per day	
	Asphalt and Mix Temperature	120ºC to 190ºC (Asphalt) ≤165ºC (Mix)			Continuous using an automated recording device	Plant

Notes:
1. TV = Target Value from contractor's proposed mix design.
2. Depending on aggregate gradation specified.
3. Quality characteristics 1, 6, 7, and 8 are defined as critical quality characteristics in the verification testing process.
4. Quality characteristics 1, 6, and 7 are defined as critical start-up characteristics in the Production Start-Up Evaluation.
5. California Test 375, Part 3, Section B, "Testing Frequency," is revised to change 450 tonnes to 500 tonnes and 45 tonnes to 50 tonnes.

39-12 MEASUREMENT AND PAYMENT

39-12.01 MEASUREMENT

Asphalt concrete will be measured by mass. The quantity to be paid for will be the combined mass of the mixture for the various types of asphalt concrete, as designated in the Engineer's Estimate.

The mass of the materials will be determined in conformance with the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications.

Quantities of paving asphalt, liquid asphalt, and asphaltic emulsion to be paid for as contract items of work will be determined in conformance with the methods provided in Section 92, "Asphalts," Section 93, "Liquid Asphalts," or Section 94, "Asphaltic Emulsions," of the Standard Specifications, as the case may be.

When recorded batch masses are printed automatically, these masses may be used for determining pay quantities provided the following requirements are complied with:

A. Total aggregate and supplemental fine aggregate mass per batch shall be printed. When supplemental fine aggregate is weighed cumulatively with the aggregate, the total batch mass of aggregate shall include the supplemental fine aggregate.
B. The total bitumen mass per batch shall be printed.

C. Zero-tolerance mass shall be printed prior to weighing the first batch and after weighing the last batch of each truckload.
D. The time, date, mix number, load number, and truck identification shall be correlated with the load slip.
E. A copy of the recorded batch masses shall be certified by a licensed weighmaster and submitted to the Engineer.

Pavement reinforcing fabric will be measured and paid for by the square meter for the actual pavement area covered.

39-12.02 PAYMENT

Asphalt concrete placed in the work, unless otherwise specified, will be paid for at the contract price per tonne for asphalt concrete of the types designated in the Engineer's Estimate.

Compensation adjustment for asphalt concrete will be in conformance with Section 39-11.02C, "Pay Factor Determination and Compensation Adjustment," of this Section 11-1, "Quality Control / Quality Assurance."

When there is a contract item for asphalt concrete (leveling), quantities of asphalt concrete placed for leveling will be paid for at the contract price per tonne for asphalt concrete (leveling). When there is no contract item for asphalt concrete (leveling), and leveling is ordered by the Engineer, asphalt concrete so used will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

For asphalt concrete placed in dig outs, as a leveling course, for slope correction, for detours not included in the finished roadway prism, in areas where in the judgment of the Engineer compaction or compaction measurement by conventional methods is impeded or on the uppermost lift of shoulders with rumble strips the relative compaction provisions of Section 39-11.02, "Statistical Evaluation and Determination of Pay Factor," of this Section 11-1, shall not apply. In the computation of the composite pay factor (PF_C) for the lot composed of this asphalt concrete, an individual pay factor of 1.0 for the relative compaction (PF_{QC8}) shall be used.

Full compensation for the Contractor's Quality Control Plan, including furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in developing, implementing, modifying, and fulfilling the requirements of the Quality Control Plan shall be considered as included in the contract price paid per tonne for asphalt concrete of the types designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

Full compensation for Contractor sampling, testing, inspection, testing facilities, and preparation and submission of results shall be considered as included in the contract price paid per tonne for asphalt concrete of the types designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

Quantities of pavement reinforcing fabric placed and paving asphalt applied as a binder for the pavement reinforcing fabric will be paid for at the contract price per square meter for pavement reinforcing fabric and per tonne for paving asphalt (binder-pavement reinforcing fabric). Full compensation for furnishing and spreading sand to cover exposed binder material, if necessary, shall be considered as included in the contract price paid per tonne for paving asphalt (binder-pavement reinforcing fabric) and no separate payment will be made therefor.

Small quantities of asphalt concrete placed on pavement reinforcing fabric to prevent the fabric from being displaced by construction equipment or to allow public traffic to cross over the fabric shall be considered as part of the layer of asphalt concrete to be placed over the fabric and will be measured and paid for by the tonne as asphalt concrete of the types designated in the Engineer's Estimate.

When there is a contract item for liquid asphalt (prime coat), the quantity of prime coat will be paid for at the contract price per tonne for the designated grade of liquid asphalt (prime coat). When there is no contract item for liquid asphalt (prime coat) and the special provisions require the application of a prime coat, full compensation for furnishing and applying the prime coat shall be considered as included in the contract price paid per tonne for asphalt concrete of the types designated in the Engineer's Estimate and no separate payment will be made therefor.

When there is a contract item for asphaltic emulsion (paint binder), the quantity of asphaltic emulsion or paving asphalt used as paint binder (tack coat) will be paid for at the contract price per tonne for asphaltic emulsion (paint binder). When there is no contract item for asphaltic emulsion (paint binder), full compensation for furnishing and applying paint binder (tack coat) shall be considered as included in the contract price paid per tonne for asphalt concrete of the types designated in the Engineer's Estimate and no separate payment will be made therefor.

Fog seal coat will be paid for as provided in Section 37-1, "Seal Coats," of the Standard Specifications.

No adjustment of compensation will be made for an increase or decrease in the quantities of paint binder (tack coat) or fog seal coat required, regardless of the reason for such increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to the items of paint binder or fog seal coat.

The above contract prices and payments shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in placing asphalt concrete, complete in place, as shown on the plans, as specified in this Section 11-1, "Quality Control / Quality Assurance," and "Asphalt Concrete" in Section 10-1, "General," of these special provisions, and as directed by the Engineer.

SECTION 12. (BLANK)

SECTION 13. RELATIONS WITH RAILROAD

13-1.0101 GENERAL

The Contractor's attention is directed to the crossing of tracks and right-of-way of the Joint Powers Board at the Fuller Underpass (PM 4.7), on State Route 87 in San Jose, hereinafter referred to as "Railroad", within the limits of the project.

In accordance with the provisons in Section 7-1.12, "Indemnification and Insurance," of the Standard Specifications, the Contractor shall be responsible for all damages to Railroad's track and equipment operating on such track, resulting from operations.

The Contractor shall conduct his operation in a manner that will prevent debris or any material from falling onto the tracks and right of way of the Railroad.

Attention is directed to Section 7-1.11, "Preservation of Property," and Section 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The Contractor shall not allow any personnel or equipment on Railroads' tracks. The Contractor shall not encroach upon the railroad right of way without first obtaining a permit from the Joint Powers Board. The partial list of the conditions, the permit application, permit application fee amount are in the Materials Information Handout available for review by the Contractor.

Full compensation for obtaining and conforming to the requirements in the Joint Powers Board permit shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

SECTION 14 FEDERAL REQUIREMENTS FOR FEDERAL-AID CONSTRUCTION PROJECTS

GENERAL.—The work herein proposed will be financed in whole or in part with Federal funds, and therefore all of the statutes, rules and regulations promulgated by the Federal Government and applicable to work financed in whole or in part with Federal funds will apply to such work. The "Required Contract Provisions, Federal-Aid Construction Contracts, "Form FHWA 1273, are included in this Section 14. Whenever in said required contract provisions references are made to "SHA contracting officer," "SHA resident engineer," or "authorized representative of the SHA," such references shall be construed to mean "Engineer" as defined in Section 1-1.18 of the Standard Specifications.

PERFORMANCE OF PREVIOUS CONTRACT.—In addition to the provisions in Section II, "Nondiscrimination," and Section VII, "Subletting or Assigning the Contract," of the required contract provisions, the Contractor shall comply with the following:

The bidder shall execute the CERTIFICATION WITH REGARD TO THE PERFORMANCE OF PREVIOUS CONTRACTS OR SUBCONTRACTS SUBJECT TO THE EQUAL OPPORTUNITY CLAUSE AND THE FILING OF REQUIRED REPORTS located in the proposal. No request for subletting or assigning any portion of the contract in excess of $10,000 will be considered under the provisions of Section VII of the required contract provisions unless such request is accompanied by the CERTIFICATION referred to above, executed by the proposed subcontractor.

NON-COLLUSION PROVISION.—The provisions in this section are applicable to all contracts except contracts for Federal Aid Secondary projects.

Title 23, United States Code, Section 112, requires as a condition precedent to approval by the Federal Highway Administrator of the contract for this work that each bidder file a sworn statement executed by, or on behalf of, the person, firm, association, or corporation to whom such contract is to be awarded, certifying that such person, firm, association, or corporation has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with the submitted bid. A form to make the non-collusion affidavit statement required by Section 112 as a certification under penalty of perjury rather than as a sworn statement as permitted by 28, USC, Sec. 1746, is included in the proposal.

PARTICIPATION BY MINORITY BUSINESS ENTERPRISES IN SUBCONTRACTING.—Part 23, Title 49, Code of Federal Regulations applies to this Federal-aid project. Pertinent sections of said Code are incorporated in part or in its entirety within other sections of these special provisions.

Schedule B—Information for Determining Joint Venture Eligibility

(This form need not be filled in if all joint venture firms are minority owned.)

1. Name of joint venture _____
2. Address of joint venture _____
3. Phone number of joint venture _____
4. Identify the firms which comprise the joint venture. (The MBE partner must complete Schedule A.) _____
   _____

   a. Describe the role of the MBE firm in the joint venture. _____
      _____
   b. Describe very briefly the experience and business qualifications of each non-MBE joint venturer: _____
      _____

5. Nature of the joint venture's business _____
   _____
6. Provide a copy of the joint venture agreement.
7. What is the claimed percentage of MBE ownership? _____
8. Ownership of joint venture: (This need not be filled in if described in the joint venture agreement, provided by question 6.).

   a. Profit and loss sharing.
   b. Capital contributions, including equipment.

c. Other applicable ownership interests.

9. Control of and participation in this contract. Identify by name, race, sex, and "firm" those individuals (and their titles) who are responsible for day-to-day management and policy decision making, including, but not limited to, those with prime responsibility for:

a. Financial decisions _____

b. Management decisions, such as:

(1) Estimating _____

(2) Marketing and sales _____

(3) Hiring and firing of management personnel _____

_____

(4) Purchasing of major items or supplies _____

_____

c. Supervision of field operations _____

Note.—If, after filing this Schedule B and before the completion of the joint venture's work on the contract covered by this regulation, there is any significant change in the information submitted, the joint venture must inform the grantee, either directly or through the prime contractor if the joint venture is a subcontractor.

Affidavit

"The undersigned swear that the foregoing statements are correct and include all material information necessary to identify and explain the terms and operation of our joint venture and the intended participation by each joint venturer in the undertaking. Further, the undersigned covenant and agree to provide to grantee current, complete and accurate information regarding actual joint venture work and the payment therefor and any proposed changes in any of the joint venture arrangements and to permit the audit and examination of the books, records and files of the joint venture, or those of each joint venturer relevant to the joint venture, by authorized representatives of the grantee or the Federal funding agency. Any material misrepresentation will be grounds for terminating any contract which may be awarded and for initiating action under Federal or State laws concerning false statements."

Name of Firm	Name of Firm
Signature	Signature
Name	Name
Title	Title
Date	Date

Date _____

State of _____

County of _____

On this ____ day of _____, 20___, before me appeared (Name) _____, to me personally known, who, being duly sworn, did execute the foregoing affidavit, and did state that he or she was properly authorized by (Name of firm) _____ to execute the affidavit and did so as his or her free act and deed.

Notary Public _____

Commission expires _____

[Seal]

Date _____

State of _____

County of _____

On this ___ day of _____, 20___, before me appeared (Name) _____ to me personally known, who, being duly sworn, did execute the foregoing affidavit, and did state that he or she was properly authorized by (Name of firm) _____ to execute the affidavit and did so as his or her free act and deed.

Notary Public _____

Commission expires _____

[Seal]

REQUIRED CONTRACT PROVISIONS
FEDERAL-AID CONSTRUCTION CONTRACTS

I. GENERAL

1. These contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

2. Except as otherwise provided for in each section, the contractor shall insert in each subcontract all of the stipulations contained in these Required Contract Provisions, and further require their inclusion in any lower tier subcontract or purchase order that may in turn be made. The Required Contract Provisions shall not be incorporated by reference in any case. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with these Required Contract Provisions.

3. A breach of any of the stipulations contained in these Required Contract Provisions shall be sufficient grounds for termination of the contract.

4. A breach of the following clauses of the Required Contract Provisions may also be grounds for debarment as provided in 29 CFR 5.12:

   Section I, paragraph 2;
   Section IV, paragraphs 1, 2, 3, 4, and 7;
   Section V, paragraphs 1 and 2a through 2g.

5. Disputes arising out of the labor standards provisions of Section IV (except paragraph 5) and Section V of these Required Contract Provisions shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the U.S. Department of Labor (DOL) as set forth in 29 CFR 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the DOL, or the contractor's employees or their representatives.

6. Selection of Labor - During the performance of this contract, the contractor shall not:

   a. discriminate against labor from any other State, possession, or territory of the United States (except for employment preference for Appalachian contracts, when applicable, as specified in Attachment A), or

   b. employ convict labor for any purpose within the limits of the project unless it is labor performed by convicts who are on parole, supervised release, or probation.

II. NONDISCRIMINATION

(Applicable to all Federal-aid construction contracts and to all related subcontracts of $10,000 or more.)

1. **Equal Employment Opportunity:** Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, and 41 CFR 60) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The Equal Opportunity Construction Contract Specifications set forth under 41 CFR 60-4.3 and the provisions of the American Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:

   a. The contractor will work with the State highway agency (SHA) and the Federal Government in carrying out EEO obligations and in their review of his/her activities under the contract.

   b. The contractor will accept as his operating policy the following statement:

      "It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action

shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job training."

2. **EEO Officer:** The contractor will designate and make known to the SHA contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so.

3. **Dissemination of Policy:** All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:

   a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.

   b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.

   c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minority group employees.

   d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.

   e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

4. **Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minority groups in the area from which the project work force would normally be derived.

   a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minority group applicants. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority group applicants may be referred to the contractor for employment consideration.

   b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he is expected to observe the provisions of that agreement to the extent that the system permits the contractor's compliance with EEO contract provisions. (The DOL has held that where implementation of such agreements have the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Executive Order 11246, as amended.)

   c. The contractor will encourage his present employees to refer minority group applicants for employment. Information and procedures with regard to referring minority group applicants will be discussed with employees.

5. **Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:

   a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.

b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.

c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.

d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with his obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of his avenues of appeal.

6. **Training and Promotion:**

a. The contractor will assist in locating, qualifying, and increasing the skills of minority group and women employees, and applicants for employment.

b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision.

c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.

d. The contractor will periodically review the training and promotion potential of minority group and women employees and will encourage eligible employees to apply for such training and promotion.

7. **Unions:** If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the contractor either directly or through a contractor's association acting as agent will include the procedures set forth below:

a. The contractor will use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority group members and women for membership in the unions and increasing the skills of minority group employees and women so that they may qualify for higher paying employment.

b. The contractor will use best efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.

c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the SHA and shall set forth what efforts have been made to obtain such information.

d. In the event the union is unable to provide the contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The DOL has held that it shall be no excuse that the union with which the contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the SHA.

8. **Selection of Subcontractors, Procurement of Materials and Leasing of Equipment:** The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.

   a. The contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.

   b. Disadvantaged business enterprises (DBE), as defined in 49 CFR 23, shall have equal opportunity to compete for and perform subcontracts which the contractor enters into pursuant to this contract. The contractor will use his best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority group and female representation among their employees. Contractors shall obtain lists of DBE construction firms from SHA personnel.

   c. The contractor will use his best efforts to ensure subcontractor compliance with their EEO obligations.

9. **Records and Reports:** The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the SHA and the FHWA.

   a. The records kept by the contractor shall document the following:

      (1) The number of minority and non-minority group members and women employed in each work classification on the project;

      (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women;

      (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and

      (4) The progress and efforts being made in securing the services of DBE subcontractors or subcontractors with meaningful minority and female representation among their employees.

   b. The contractors will submit an annual report to the SHA each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data.

III. NONSEGREGATED FACILITIES

(Applicable to all Federal-aid construction contracts and to all related subcontracts of $10,000 or more.)

a. By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement or purchase order, as appropriate, the bidder, Federal-aid construction contractor, subcontractor, material supplier, or vendor, as appropriate, certifies that the firm does not maintain or provide for its employees any segregated facilities at any of its establishments, and that the firm does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The firm agrees that a breach of this certification is a violation of the EEO provisions of this contract. The firm further certifies that no employee will be denied access to adequate facilities on the basis of sex or disability.

b. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, time clocks, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive, or are, in fact, segregated on the basis of race, color, religion, national origin, age or disability, because of habit, local custom, or otherwise. The only exception will be for the disabled when the demands for accessibility override (e.g. disabled parking).

c. The contractor agrees that it has obtained or will obtain identical certification from proposed subcontractors or material suppliers prior to award of subcontracts or consummation of material supply agreements of $10,000 or more and that it will retain such certifications in its files.

IV. PAYMENT OF PREDETERMINED MINIMUM WAGE

(Applicable to all Federal-aid construction contracts exceeding $2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural minor collectors, which are exempt.)

1. **General:**

a. All mechanics and laborers employed or working upon the site of the work will be paid unconditionally and not less often than once a week and without subsequent deduction or rebate on any account [except such payroll deductions as are permitted by regulations (29 CFR 3)] issued by the Secretary of Labor under the Copeland Act (40 U.S.C. 276c) the full amounts of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment. The payment shall be computed at wage rates not less than those contained in the wage determination of the Secretary of Labor (hereinafter "the wage determination") which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor or its subcontractors and such laborers and mechanics. The wage determination (including any additional classifications and wage rates conformed under paragraph 2 of this Section IV and the DOL poster (WH-1321) or Form FHWA-1495) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers. For the purpose of this Section, contributions made or costs reasonably anticipated for bona fide fringe benefits under Section 1(b)(2) of the Davis-Bacon Act (40 U.S.C. 276a) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of Section IV, paragraph 3b, hereof. Also, for the purpose of this Section, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraphs 4 and 5 of this Section IV.

b. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein, provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.

c. All rulings and interpretations of the Davis-Bacon Act and related acts contained in 29 CFR 1, 3, and 5 are herein incorporated by reference in this contract.

2. **Classification:**

a. The SHA contracting officer shall require that any class of laborers or mechanics employed under the contract, which is not listed in the wage determination, shall be classified in conformance with the wage determination.

b. The contracting officer shall approve an additional classification, wage rate and fringe benefits only when the following criteria have been met:

(1) the work to be performed by the additional classification requested is not performed by a classification in the wage determination;

(2) the additional classification is utilized in the area by the construction industry;

(3) the proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination; and

(4) with respect to helpers, when such a classification prevails in the area in which the work is performed.

c. If the contractor or subcontractors, as appropriate, the laborers and mechanics (if known) to be employed in the additional classification or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be

sent by the contracting officer to the DOL, Administrator of the Wage and Hour Division, Employment Standards Administration, Washington, D.C. 20210. The Wage and Hour Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

d. In the event the contractor or subcontractors, as appropriate, the laborers or mechanics to be employed in the additional classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. Said Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary

e. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 2c or 2d of this Section IV shall be paid to all workers performing work in the additional classification from the first day on which work is performed in the classification.

3. **Payment of Fringe Benefits:**

a. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor or subcontractors, as appropriate, shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly case equivalent thereof.

b. If the contractor or subcontractor, as appropriate, does not make payments to a trustee or other third person, he/she may consider as a part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided, that the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

4. **Apprentices and Trainees (Programs of the U.S. DOL) and Helpers:**

a. Apprentices:

(1) Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the DOL, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau, or if a person is employed in his/her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State apprenticeship agency (where appropriate) to be eligible for probationary employment as an apprentice.

(2) The allowable ratio of apprentices to journeyman-level employees on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate listed in the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor or subcontractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman-level hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

(3) Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman-level hourly rate specified in

the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator for the Wage and Hour Division determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

(4) In the event the Bureau of Apprenticeship and Training, or a State apprenticeship agency recognized by the Bureau, withdraws approval of an apprenticeship program, the contractor or subcontractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the comparable work performed by regular employees until an acceptable program is approved.

b. Trainees:

(1) Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the DOL, Employment and Training Administration.

(2) The ratio of trainees to journeyman-level employees on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

(3) Every trainee must be paid at not less than the rate specified in the approved program for his/her level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman-level wage rate on the wage determination which provides for less than full fringe benefits for apprentices, in which case such trainees shall receive the same fringe benefits as apprentices.

(4) In the event the Employment and Training Administration withdraws approval of a training program, the contractor or subcontractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Helpers**:**

Helpers will be permitted to work on a project if the helper classification is specified and defined on the applicable wage determination or is approved pursuant to the conformance procedure set forth in Section IV.2. Any worker listed on a payroll at a helper wage rate, who is not a helper under an approved definition, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed.

5. **Apprentices and Trainees (Programs of the U.S. DOT):**
Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

6. **Withholding:**
The SHA shall upon its own action or upon written request of an authorized representative of the DOL withhold, or cause to be withheld, from the contractor or subcontractor under this contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage

requirements which is held by the same prime contractor, as much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the SHA contracting officer may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

7. **Overtime Requirements:**
No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen, or guards (including apprentices, trainees, and helpers described in paragraphs 4 and 5 above) shall require or permit any laborer, mechanic, watchman, or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman, or guard receives compensation at a rate not less than one-and-one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

8. **Violation:**
Liability for Unpaid Wages; Liquidated Damages: In the event of any violation of the clause set forth in paragraph 7 above, the contractor and any subcontractor responsible thereof shall be liable to the affected employee for his/her unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory) for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman, or guard employed in violation of the clause set forth in paragraph 7, in the sum of $10 for each calendar day on which such employee was required or permitted to work in excess of the standard work week of 40 hours without payment of the overtime wages required by the clause set forth in paragraph 7.

9. **Withholding for Unpaid Wages and Liquidated Damages:**
The SHA shall upon its own action or upon written request of any authorized representative of the DOL withhold, or cause to be withheld, from any monies payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 8 above.

V. STATEMENTS AND PAYROLLS

(Applicable to all Federal-aid construction contracts exceeding $2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural collectors, which are exempt.)

1. **Compliance with Copeland Regulations (29 CFR 3):**

The contractor shall comply with the Copeland Regulations of the Secretary of Labor which are herein incorporated by reference.

2. **Payrolls and Payroll Records:**

a. Payrolls and basic records relating thereto shall be maintained by the contractor and each subcontractor during the course of the work and preserved for a period of 3 years from the date of completion of the contract for all laborers, mechanics, apprentices, trainees, watchmen, helpers, and guards working at the site of the work.

b. The payroll records shall contain the name, social security number, and address of each such employee; his or her correct classification; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalent thereof the types described in Section 1(b)(2)(B) of the Davis Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. In addition, for Appalachian contracts, the payroll records shall contain a notation indicating whether the employee does, or does not, normally reside in the labor area as defined in Attachment A, paragraph 1. Whenever the Secretary of Labor, pursuant to Section IV, paragraph 3b, has found that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in Section 1(b)(2)(B) of the Davis Bacon Act, the contractor and each subcontractor shall maintain records which show

that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, that the plan or program has been communicated in writing to the laborers or mechanics affected, and show the cost anticipated or the actual cost incurred in providing benefits. Contractors or subcontractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprentices and trainees, and ratios and wage rates prescribed in the applicable programs.

c. Each contractor and subcontractor shall furnish, each week in which any contract work is performed, to the SHA resident engineer a payroll of wages paid each of its employees (including apprentices, trainees, and helpers, described in Section IV, paragraphs 4 and 5, and watchmen and guards engaged on work during the preceding weekly payroll period). The payroll submitted shall set out accurately and completely all of the information required to be maintained under paragraph 2b of this Section V. This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal stock number 029-005-0014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors.

d. Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his/her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:

(1) that the payroll for the payroll period contains the information required to be maintained under paragraph 2b of this Section V and that such information is correct and complete;

(2) that such laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR 3;

(3) that each laborer or mechanic has been paid not less that the applicable wage rate and fringe benefits or cash equivalent for the classification of worked performed, as specified in the applicable wage determination incorporated into the contract.

e. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 2d of this Section V.

f. The falsification of any of the above certifications may subject the contractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 231.

g. The contractor or subcontractor shall make the records required under paragraph 2b of this Section V available for inspection, copying, or transcription by authorized representatives of the SHA, the FHWA, or the DOL, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the SHA, the FHWA, the DOL, or all may, after written notice to the contractor, sponsor, applicant, or owner, take such actions as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

VI. RECORD OF MATERIALS, SUPPLIES, AND LABOR

1. On all Federal-aid contracts on the National Highway System, except those which provide solely for the installation of protective devices at railroad grade crossings, those which are constructed on a force account or direct labor basis, highway beautification contracts, and contracts for which the total final construction cost for roadway and bridge is less than $1,000,000 (23 CFR 635) the contractor shall:

a. Become familiar with the list of specific materials and supplies contained in Form FHWA-47, "Statement of Materials and Labor Used by Contractor of Highway Construction Involving Federal Funds," prior to the commencement of work under this contract.

b. Maintain a record of the total cost of all materials and supplies purchased for and incorporated in the work, and also of the quantities of those specific materials and supplies listed on Form FHWA-47, and in the units shown on Form FHWA-47.

c. Furnish, upon the completion of the contract, to the SHA resident engineer on Form FHWA-47 together with the data required in paragraph 1b relative to materials and supplies, a final labor summary of all contract work indicating the total hours worked and the total amount earned.

2. At the prime contractor's option, either a single report covering all contract work or separate reports for the contractor and for each subcontract shall be submitted.

VII. SUBLETTING OR ASSIGNING THE CONTRACT

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the State. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635).

   a. "Its own organization" shall be construed to include only workers employed and paid directly by the prime contractor and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor, assignee, or agent of the prime contractor.

   b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract as a whole and in general are to be limited to minor components of the overall contract.

2. The contract amount upon which the requirements set forth in paragraph 1 of Section VII is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.

3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the SHA contracting officer determines is necessary to assure the performance of the contract.

4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the SHA contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the SHA has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

VIII. SAFETY - ACCIDENT PREVENTION

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the SHA contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.

2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of

compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

IX. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, the following notice shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

Notice To All Personnel Engaged On Federal-Aid Highway Projects

18 U.S.C. 1020 READS AS FOLLOWS:

"Whoever being an officer, agent, or employee of the United States, or any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined not more that $10,000 or imprisoned not more than 5 years or both."

X. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

(Applicable to all Federal-aid construction contracts and to all related subcontracts of $100,000 or more.)

By submission of this bid or the execution of this contract, or subcontract, as appropriate, the bidder, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any facility that is or will be utilized in the performance of this contract, unless such contract is exempt under the Clean Air Act, as amended (42 U.S.C. 1857 et seq., as amended by Pub.L. 91-604), and under the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251 et seq., as amended by Pub.L. 92-500), Executive Order 11738, and regulations in implementation thereof (40 CFR 15) is not listed, on the date of contract award, on the U.S. Environmental Protection Agency (EPA) List of Violating Facilities pursuant to 40 CFR 15.20.

2. That the firm agrees to comply and remain in compliance with all the requirements of Section 114 of the Clean Air Act and Section 308 of the Federal Water Pollution Control Act and all regulations and guidelines listed thereunder.

3. That the firm shall promptly notify the SHA of the receipt of any communication from the Director, Office of Federal Activities, EPA, indicating that a facility that is or will be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.

4. That the firm agrees to include or cause to be included the requirements of paragraph 1 through 4 of this Section X in every nonexempt subcontract, and further agrees to take such action as the government may direct as a means of enforcing such requirements.

XI. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

1. **Instructions for Certification - Primary Covered Transactions:**
(Applicable to all Federal-aid contracts - 49 CFR 29)

a. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.

b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.

c. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.

d. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.

e. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the department or agency to which this proposal is submitted for assistance in obtaining a copy of those regulations.

f. The prospective primary participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.

g. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," provided by the department or agency entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the nonprocurement portion of the "Lists of Parties Excluded From Federal Procurement or Nonprocurement Programs" (Nonprocurement List) which is compiled by the General Services Administration.

i. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

j. Except for transactions authorized under paragraph f of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

2. **Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion — Primary Covered Transactions:**

a. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:

(1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;

(2) Have not within a 3-year period preceding this proposal been convicted of or had a civil judgement rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;

(3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1b of this certification; and

(4) Have not within a 3-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.

b. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

3. **Instructions for Certification - Lower Tier Covered Transactions:**
(Applicable to all subcontracts, purchase orders and other lower tier transactions of $25,000 or more - 49 CFR 29)

a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.

b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.

d. The terms "covered transaction," "debarred," "suspended," "ineligible," "primary covered transaction," "participant," "person," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.

e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.

f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.

h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

4. **Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion — Lower Tier Covered Transactions:**

a. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

b. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

XII. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

(Applicable to all Federal-aid construction contracts and to all related subcontracts which exceed $100,000 - 49 CFR 20)

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than $10,000 and not more than $100,000 for each such failure.

3. The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed $100,000 and that all such recipients shall certify and disclose accordingly.

FEDERAL-AID FEMALE AND MINORITY GOALS

In accordance with Section II, "Nondiscrimination," of "Required Contract Provisions Federal-aid Construction Contracts" the following are the goals for female utilization:

Goal for Women (applies nationwide).....(percent) 6.9

The following are goals for minority utilization:

CALIFORNIA ECONOMIC AREA

		Goal (Percent)
174	**Redding, CA:**	
	Non-SMSA Counties	6.8
	CA Lassen; CA Modoc;CA Plumas;CA Shasta; CA Siskiyou; CA Tehama.	
175	**Eureka, CA**	
	Non-SMSA Counties	6.6
	CA Del Norte; CA Humboldt; CA Trinity.	
176	**San Francisco-Oakland-San Jose, CA:**	
	SMSA Counties:	
	7120 Salinas-Seaside-Monterey, CA	28.9
	CA Monterey.	
	7360 San Francisco-Oakland	25.6
	CA Alameda; CA Contra Costa; CA Marin; CA San Francisco; CA San Mateo.	
	7400 San Jose, CA	19.6
	CA Santa Clara.	
	7485 Santa Cruz, CA.	14.9
	CA Santa Cruz.	
	7500 Santa Rosa, CA	9.1
	CA Sonoma.	
	8720 Vallejo-Fairfield- Napa, CA	17.1
	CA Napa; CA Solano	
	Non-SMSA Counties	23.2
	CA Lake; CA Mendocino; CA San Benito	
177	**Sacramento, CA**:	
	SMSA Counties:	
	6920 Sacramento, CA	16.1
	CA Placer; CA Sacramento; CA Yolo.	
	Non-SMSA Counties	14.3
	CA Butte; CA Colusa; CA El Dorado; CA Glenn; CA Nevada; CA Sierra; CA Sutter; CA Yuba.	
178	**Stockton-Modesto, CA:**	
	SMSA Counties:	
	5170 Modesto, CA	12.3
	CA Stanislaus.	
	8120 Stockton, CA	24.3
	CA San Joaquin.	
	Non-SMSA Counties	19.8
	CA Alpine; CA Amador; CA Calaveras; CA Mariposa;CA Merced; CA Tuolumne.	

		Goal (Percent)
179	**Fresno-Bakersfield, CA**	
	SMSA Counties:	
	0680 Bakersfield, CA	19.1
	CA Kern.	
	2840 Fresno, CA	26.1
	CA Fresno.	
	Non-SMSA Counties	23.6
	CA Kings; CA Madera; CA Tulare.	
180	**Los Angeles, CA:**	
	SMSA Counties:	
	0360 Anaheim-Santa Ana-Garden Grove, CA	11.9
	CA Orange.	
	4480 Los Angeles-Long Beach, CA	28.3
	CA Los Angeles.	
	6000 Oxnard-Simi Valley-Ventura, CA	21.5
	CA Ventura.	
	6780 Riverside-San Bernardino-Ontario, CA.	19.0
	CA Riverside; CA San Bernardino.	
	7480 Santa Barbara-Santa Maria-Lompoc, CA	19.7
	CA Santa Barbara.	
	Non-SMSA Counties	24.6
	CA Inyo; CA Mono; CA San Luis Obispo.	
181	**San Diego, CA:**	
	SMSA Counties	
	7320 San Diego, CA.	16.9
	CA San Diego.	
	Non-SMSA Counties	18.2
	CA Imperial.	

In addition to the reporting requirements set forth elsewhere in this contract the Contractor and subcontractors holding subcontracts, not including material suppliers, of $10,000 or more, shall submit for every month of July during which work is performed, employment data as contained under Form FHWA PR-1391 (Appendix C to 23 CFR, Part 230), and in accordance with the instructions included thereon.

FEDERAL REQUIREMENT TRAINING SPECIAL PROVISIONS

As part of the Contractor's equal employment opportunity affirmative action program, training shall be provided as follows:

The Contractor shall provide on-the-job training to develop full journeymen in the types of trades or job classification involved.

The goal for the number of trainees or apprentices to be trained under the requirements of this special provision will be 24.

In the event the Contractor subcontracts a portion of the contract work, he shall determine how many, if any, of the trainees or apprentices are to be trained by the subcontractor, provided however, that the Contractor shall retain the primary responsibility for meeting the training requirements imposed by this special provision. The Contractor shall also insure that this Training Special Provision is made applicable to such subcontract. Where feasible, 25 percent of trainees or apprentices in each occupation shall be in their first year of apprenticeship or training.

The number of trainees or apprentices shall be distributed among the work classifications on the basis of the Contractor's needs and the availability of journeymen in the various classifications within a reasonable area of recruitment. Prior to commencing work, the Contractor shall submit to the Department for approval the number of trainees or apprentices to be trained in each selected classification and training program to be used. Furthermore, the Contractor shall specify the starting time for training in each of the classifications. The Contractor will be credited for each trainee or apprentice employed by him on the contract work who is currently enrolled or becomes enrolled in an approved program and will be reimbursed for such trainees or apprentices as provided hereinafter.

Training and upgrading of minorities and women toward journeymen status is a primary objective of this Training Special Provision. Accordingly, the Contractor shall make every effort to enroll minority and women trainees or apprentices (e.g., by conducting systematic and direct recruitment through public and private sources likely to yield minority and women trainees or apprentices) to the extent such persons are available within a reasonable area of recruitment. The Contractor will be responsible for demonstrating the steps that he has taken in pursuance thereof, prior to a determination as to whether the Contractor is in compliance with this Training Special Provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a minority group or not.

No employee shall be employed as a trainee or apprentice in any classification in which he has successfully completed a training course leading to journeyman status or in which he has been employed as a journeyman. The Contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used the Contractor's records should document the findings in each case.

The minimum length and type of training for each classification will be as established in the training program selected by the Contractor and approved by both the Department and the Federal Highway Administration. The Department and the Federal Highway Administration will approve a program if it is reasonably calculated to meet the equal employment opportunity obligations of the Contractor and to qualify the average trainee or apprentice for journeyman status in the classification concerned by the end of the training period. Furthermore, apprenticeship programs registered with the U.S. Department of Labor, Bureau of Apprenticeship and Training, or with the State of California, Department of Industrial Relations, Division of Apprenticeship Standards recognized by the Bureau and training programs approved but not necessarily sponsored by the U.S. Department of Labor, Manpower Administration, Bureau of Apprenticeship and Training shall also be considered acceptable provided it is being administered in a manner consistent with the equal employment obligations of Federal-aid highway construction contracts. Approval or acceptance of a training program shall be obtained from the State prior to commencing work on the classification covered by the program. It is the intention of these provisions that training is to be provided in the construction crafts rather than clerk-typists or secretarial-type positions. Training is permissible in lower level management positions such as office engineers, estimators, timekeepers, etc., where the training is oriented toward construction applications. Training in the laborer classification may be permitted provided that significant and meaningful training is provided and approved by the division office. Some offsite training is permissible as long as the training is an integral part of an approved training program and does not comprise a significant part of the overall training.

Except as otherwise noted below, the Contractor will be reimbursed 80 cents per hour of training given an employee on this contract in accordance with an approved training program. As approved by the Engineer, reimbursement will be made for training of persons in excess of the number specified herein. This reimbursement will be made even though the Contractor receives additional training program funds from other sources, provided such other source does not specifically prohibit the Contractor from receiving other reimbursement. Reimbursement for offsite training indicated above may only be made to the Contractor where he does one or more of the following and the trainees or apprentices are concurrently employed on a Federal-aid project; contributes to the cost of the training, provides the instruction to the trainee or apprentice or pays the trainee's or apprentice's wages during the offsite training period.

No payment shall be made to the Contractor if either the failure to provide the required training, or the failure to hire the trainee or apprentice as a journeyman, is caused by the Contractor and evidences a lack of good faith on the part of the Contractor in meeting the requirements of this Training Special Provision. It is normally expected that a trainee or apprentice

will begin his training on the project as soon as feasible after start of work utilizing the skill involved and remain on the project as long as training opportunities exist in his work classification or until he has completed his training program. It is not required that all trainees or apprentices be on board for the entire length of the contract. A Contractor will have fulfilled his responsibilities under this Training Special Provision if he has provided acceptable training to the number of trainees or apprentices specified. The number trained shall be determined on the basis of the total number enrolled on the contract for a significant period.

Only trainees or apprentices registered in a program approved by the State of California's State Administrator of Apprenticeship may be employed on the project and said trainees or apprentices shall be paid the standard wage specified under the regulations of the craft or trade at which they are employed.

The Contractor shall furnish the trainee or apprentice a copy of the program he will follow in providing the training. The Contractor shall provide each trainee or apprentice with a certification showing the type and length of training satisfactorily completed.

The Contractor will provide for the maintenance of records and furnish periodic reports documenting his performance under this Training Special Provision.