

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that Caltrans does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders and non-bidder packages, write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone and fax number, P.O. Box and street address so that you can receive addenda.

Note: Addenda information is NOT included with the electronic documents available via electronic file transfer. Only bidder or non-bidder package holders listed with the Caltrans Plans and Bid Documents section as described above will receive addenda information.



STATE OF CALIFORNIA

DEPARTMENT OF TRANSPORTATION

**NOTICE TO CONTRACTORS
AND**

SPECIAL PROVISIONS

FOR CONSTRUCTION ON STATE HIGHWAY IN

**MONTEREY COUNTY AT PRUNEDALE ON ROUTE 101 FROM 0.1 km SOUTH TO 0.4 km NORTH OF
ROUTE 156/101 SEPARATION AND ON ROUTE 156 FROM MCGUFFIE ROAD TO ROUTE 156/101
SEPARATION**

DISTRICT 05, ROUTE 101,156

**For Use in Connection with Standard Specifications Dated JULY 1999, Standard Plans Dated JULY 1999, and Labor
Surcharge and Equipment Rental Rates.**

CONTRACT NO. 05-0161U4

05-Mon-101,156-153.5/153.9,T7.7/T8.3

**Federal Aid Project
ACNH-X053(020)E**

**Bids Open: August 7, 2001
Dated: June 25, 2001**

**QCQA
OSD**

IMPORTANT SPECIAL NOTICES

- The Special Provisions for Federal-aid projects (with and without DBE goals) have been revised to incorporate changes made by new regulations governing the DBE Program (49 CFR Part 26).

Sections 2 and 5 incorporate the changes. Bidders should read these sections to become familiar with them. Attention is directed to the following significant changes:

Section 2, "Disadvantaged Business Enterprise (DBE)" revises the counting of participation by DBE primes, and the counting of trucking performed by DBE firms. The section also revises the information that must be submitted to the Department in order to receive credit for trucking.

Section 2, "Submission of DBE Information" revises the information required to be submitted to the Department to receive credit toward the DBE goal. It also revises the criteria to demonstrate good faith efforts.

- Attention is directed to Section 4, "Beginning of Work, Time of Completion and Liquidated Damages," of these Special Provisions regarding beginning of work restrictions.

Section 5, "Subcontractor and DBE Records" revises the information required to be reported at the end of the project, and information related to trucking that must be submitted throughout the project.

Section 5, "DBE Certification Status" adds new reporting requirements related to DBE certification.

Section 5, "Subcontracting" describes the efforts that must be made in the event a DBE subcontractor is terminated or fails to complete its work for any reason.

Section 5, "Prompt Progress Payment to Subcontractors" requires prompt payment to all subcontractors.

Section 5, "Prompt Payment of Withheld Funds to Subcontractors" requires the prompt payment of retention to all subcontractors.

- The specifications for this project include Quality Control / Quality Assurance provisions for the contract item "Asphalt Concrete" in the Special Provisions. Asphalt concrete shall conform to the provisions in Section 11-1, "Quality Control / Quality Assurance," and the section entitled "Asphalt Concrete" in Section 10-1, "General," of the Special Provisions. Section 39, "Asphalt Concrete," of the Standard Specifications shall not apply to Type A and Type B asphalt concrete.

- **Payment Bonds**

Attention is directed to Section 5 of the Special Provisions, regarding contract bonds. The payment bond shall be in a sum not less than one hundred percent of the total amount payable by the terms of the contract.

- Attention is directed to Section 11-2, "Portland Cement Concrete," of these Special Provisions which contains Section 90, "Portland Cement Concrete," of the Standard Specifications.
- Attention is directed to "Miscellaneous Metal," in Section 8-1, "Miscellaneous," of these Special Provisions for new requirements for miscellaneous metal.

TABLE OF CONTENTS

NOTICE TO CONTRACTORS.....	1
COPY OF ENGINEER'S ESTIMATE	3
SPECIAL PROVISIONS	11
SECTION 1. SPECIFICATIONS AND PLANS.....	11
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS.....	11
2-1.01 GENERAL.....	11
2-1.015 FEDERAL LOBBYING RESTRICTIONS.....	11
2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE).....	12
2-1.02A DBE GOAL FOR THIS PROJECT.....	14
2-1.02B SUBMISSION OF DBE INFORMATION	14
SECTION 3. AWARD AND EXECUTION OF CONTRACT.....	15
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES	15
SECTION 5. GENERAL	16
SECTION 5-1. MISCELLANEOUS	16
5-1.01 PLANS AND WORKING DRAWINGS	16
5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK	16
5-1.012 DIFFERING SITE CONDITIONS.....	16
5-1.015 LABORATORY	16
5-1.017 CONTRACT BONDS	17
5-1.018 EXCAVATION SAFETY PLANS	17
5-1.019 COST REDUCTION INCENTIVE.....	17
5-1.02 LABOR NONDISCRIMINATION.....	17
5-1.03 INTEREST ON PAYMENTS	18
5-1.031 FINAL PAYMENT AND CLAIMS.....	18
5-1.04 PUBLIC SAFETY	18
5-1.05 SURFACE MINING AND RECLAMATION ACT.....	20
5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES.....	20
5-1.07 YEAR 2000 COMPLIANCE.....	20
5-1.075 BUY AMERICA REQUIREMENTS.....	20
5-1.08 SUBCONTRACTOR AND DBE RECORDS	20
5-1.083 DBE CERTIFICATION STATUS	21
5-1.086 PERFORMANCE OF DBE SUBCONTRACTORS AND SUPPLIERS	21
5-1.09 SUBCONTRACTING.....	21
5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS	22
5-1.102 PROMPT PAYMENT OF WITHHELD FUNDS TO SUBCONTRACTORS	22
5-1.11 PARTNERING.....	22
5-1.114 VALUE ANALYSIS	23
5-1.12 FORCE ACCOUNT PAYMENT.....	23
5-1.13 CLAIMS SUBMITTAL	24
5-1.14 COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS.....	24
5-1.15 AREAS FOR CONTRACTOR'S USE.....	25
5-1.16 PAYMENTS.....	25
5-1.17 SOUND CONTROL REQUIREMENTS.....	26
5-1.18 RELATIONS WITH ARMY CORP OF ENGINEERS	26
5-1.19 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD	26
5-1.20 RELATIONS WITH CALIFORNIA DEPARTMENT OF FISH AND GAME	27
5-1.21 ENVIRONMENTALLY SENSITIVE AREA (ESA).....	27
5-1.22 FIRE PLAN	27
SECTION 6. (BLANK).....	29
SECTION 7. (BLANK).....	29
SECTION 8. MATERIALS	29
SECTION 8-1. MISCELLANEOUS	29
8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS	29
8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS	35

8-1.03 STATE-FURNISHED MATERIALS	40
8-1.04 ENGINEERING FABRICS.....	40
8-1.05 MISCELLANEOUS METAL	41
SECTION 8-2. CONCRETE.....	43
8-2.01 PORTLAND CEMENT CONCRETE.....	43
8-2.02 CEMENT AND WATER CONTENT	43
SECTION 8-3. WELDING	43
8-3.01 WELDING.....	43
GENERAL.....	43
WELDING QUALITY CONTROL	45
PAYMENT	47
SECTION 9. DESCRIPTION OF BRIDGE WORK.....	48
SECTION 10. CONSTRUCTION DETAILS.....	48
SECTION 10-1. GENERAL	48
10-1.00 CONSTRUCTION PROJECT INFORMATION SIGNS	48
10-1.01 ORDER OF WORK.....	49
10-1.02 WATER POLLUTION CONTROL (STORM WATER POLLUTION PREVENTION PLAN)	50
STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND AMENDMENTS	51
COST BREAK-DOWN	53
SWPPP IMPLEMENTATION	54
MAINTENANCE	55
PAYMENT	55
10-1.03 TEMPORARY CULVERTS	57
10-1.04 TEMPORARY OUTLET PROTECTION	57
10-1.05 TEMPORARY DRAINAGE INLET	57
10-1.06 TEMPORARY OVERSIDE DRAIN	58
10-1.07 TEMPORARY METAL BEAM GUARD RAILING.....	58
10-1.08 TEMPORARY FENCE (TYPE ESA).....	59
10-1.09 PRESERVATION OF PROPERTY	59
10-1.10 DAMAGE REPAIR.....	60
10-1.11 RELIEF FROM MAINTENANCE AND RESPONSIBILITY.....	60
10-1.12 COOPERATION	60
10-1.13 PROGRESS SCHEDULE (CRITICAL PATH METHOD).....	60
DEFINITIONS.....	60
GENERAL REQUIREMENTS	61
COMPUTER SOFTWARE	62
NETWORK DIAGRAMS, REPORTS AND DATA.....	63
PRE-CONSTRUCTION SCHEDULING CONFERENCE	64
BASELINE SCHEDULE	64
UPDATE SCHEDULE.....	64
TIME IMPACT ANALYSIS.....	65
FINAL UPDATE SCHEDULE	65
RETENTION.....	65
PAYMENT	66
10-1.14 OVERHEAD	66
10-1.15 OBSTRUCTIONS	68
10-1.16 MOBILIZATION	69
10-1.17 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES	69
10-1.18 CONSTRUCTION AREA SIGNS	69
10-1.19 MAINTAINING TRAFFIC.....	70
10-1.20 CLOSURE REQUIREMENTS AND CONDITIONS	75
CLOSURE SCHEDULE	75
CONTINGENCY PLAN	75
LATE REOPENING OF CLOSURES	75
COMPENSATION	75
10-1.21 CONSTRUCTION ZONE ENHANCED ENFORCEMENT	76
10-1.22 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE.....	76
STATIONARY LANE CLOSURE	77

MOVING LANE CLOSURE	77
PAYMENT	78
10-1.23 TEMPORARY PAVEMENT DELINEATION	78
GENERAL	78
TEMPORARY LANELINE AND CENTERLINE DELINEATION	78
TEMPORARY EDGELINE DELINEATION	79
TEMPORARY TRAFFIC STRIPE (TAPE)	79
TEMPORARY PAVEMENT MARKING (TAPE)	80
TEMPORARY PAVEMENT MARKERS	80
MEASUREMENT AND PAYMENT	80
10-1.24 BARRICADE	81
10-1.25 PORTABLE CHANGEABLE MESSAGE SIGN	81
10-1.26 TEMPORARY RAILING	81
10-1.27 CHANNELIZER	81
10-1.28 TEMPORARY CRASH CUSHION MODULE	82
10-1.29 EXISTING HIGHWAY FACILITIES	83
REPAIR EXISTING ROADBED	83
REMOVE FENCE	83
REMOVE PAVEMENT MARKER	83
REMOVE PAINTED TRAFFIC STRIPE AND PAINTED PAVEMENT MARKING	83
REMOVE DRAINAGE FACILITY	83
REMOVE ASPHALT CONCRETE DIKE	83
REMOVE ROADSIDE SIGN	84
RECONSTRUCT METAL BEAM GUARD RAILING	84
RELOCATE ROADSIDE SIGN	84
ADJUST INLET	84
REMOVE BASE AND SURFACING	84
COLD PLANE ASPHALT CONCRETE PAVEMENT	84
CAP INLET	85
EXISTING HIGHWAY IRRIGATION FACILITIES	85
REMOVE CONCRETE	86
10-1.30 CLEARING AND GRUBBING	86
10-1.31 EARTHWORK	86
10-1.32 EARTH RETAINING STRUCTURES	89
EARTHWORK	90
CONCRETE	91
REINFORCEMENT	91
GALVANIZING	91
DRAINAGE SYSTEM	91
STATE-DESIGNED EARTH RETAINING STRUCTURES	92
MECHANICALLY STABILIZED EMBANKMENT	92
PROPRIETARY EARTH RETAINING SYSTEMS	92
MEASUREMENT AND PAYMENT	93
10-1.33 CONTROLLED LOW STRENGTH MATERIAL	93
10-1.34 SHOULDER BACKING	94
10-1.35 EROSION CONTROL (BLANKET) (TYPE 1)	94
MATERIALS	95
APPLICATION	96
MEASUREMENT AND PAYMENT	96
10-1.36 EROSION CONTROL (BLANKET) (TYPE 2)	97
MATERIALS	97
APPLICATION	97
MEASUREMENT AND PAYMENT	98
10-1.37 EROSION CONTROL (TYPE D)	98
MATERIALS	98
APPLICATION	99
10-1.38 MOVE-IN/MOVE-OUT (EROSION CONTROL)	99
10-1.39 IRRIGATION CROSSOVERS	99
10-1.40 FINISHING ROADWAY	100

10-1.41	AGGREGATE BASE.....	100
10-1.42	SOIL TREATMENT	100
10-1.43	ASPHALT CONCRETE	100
10-1.44	ASPHALT CONCRETE (MISCELLANEOUS AREAS)	102
10-1.45	PILING	103
	GENERAL.....	103
	MEASUREMENT AND PAYMENT (PILING)	104
10-1.46	PRESTRESSING CONCRETE.....	105
10-1.47	CONCRETE STRUCTURES.....	105
	GENERAL.....	105
	FALSEWORK	106
	COST REDUCTION INCENTIVE PROPOSALS FOR CAST-IN-PLACE PRESTRESSED BOX GIRDER BRIDGES	112
	SLIDING BEARINGS.....	113
	ELASTOMERIC BEARING PADS.....	113
	MEASUREMENT AND PAYMENT	114
10-1.48	STRUCTURE APPROACH SLABS (TYPE N) AND (TYPE EQ)	114
	GENERAL.....	114
	STRUCTURE APPROACH DRAINAGE SYSTEM	114
	ENGINEERING FABRICS.....	115
	TREATED PERMEABLE BASE UNDER APPROACH SLAB	115
	APPROACH SLABS.....	115
	JOINTS	116
	MEASUREMENT AND PAYMENT	116
10-1.49	SEALING JOINTS	117
10-1.50	ARCHITECTURAL SURFACE (TEXTURED CONCRETE)	117
	REFEREE SAMPLE	117
	TEST PANEL	117
	FORM LINERS	117
	RELEASING FORM LINERS	118
	CURING	118
	MEASUREMENT AND PAYMENT	118
	PAYMENT	119
10-1.51	MINOR CONCRETE (INVERT PAVING).....	119
10-1.52	REINFORCEMENT.....	119
10-1.53	SIGN STRUCTURES.....	120
10-1.54	ROADSIDE SIGNS.....	122
10-1.55	ALTERNATIVE PIPE	122
	SPIRAL RIB PIPE.....	122
10-1.56	REINFORCED CONCRETE PIPE	122
10-1.57	CORRUGATED METAL PIPE	123
10-1.58	OVERSIDE DRAIN.....	123
10-1.59	MISCELLANEOUS FACILITIES.....	123
10-1.60	SLOPE PAVING	123
10-1.61	MISCELLANEOUS CONCRETE CONSTRUCTION	124
10-1.62	MINOR CONCRETE (GUTTER).....	124
10-1.63	MISCELLANEOUS IRON AND STEEL.....	124
10-1.64	MISCELLANEOUS METAL (BRIDGE).....	124
10-1.65	TYPE BW FENCE	125
10-1.66	MONUMENTS.....	125
10-1.67	MARKERS AND DELINEATORS.....	125
10-1.68	METAL BEAM GUARD RAILING	125
	TERMINAL SYSTEM (TYPE SRT).....	126
10-1.69	CABLE RAILING	126
10-1.70	CONCRETE BARRIER.....	126
10-1.71	CRASH CUSHION (REACT).....	126
10-1.72	THERMOPLASTIC PAVEMENT MARKING	127
10-1.73	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE).....	127
10-1.74	PAVEMENT MARKERS	128

SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS	128
10-2.01 GENERAL.....	128
PROGRESS INSPECTIONS.....	128
COST BREAK-DOWN	129
10-2.02 EXISTING HIGHWAY PLANTING	132
PRUNE EXISTING PLANTS.....	132
10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES.....	132
LOCATE EXISTING WATER SUPPLY LINE.....	132
CHECK AND TEST EXISTING IRRIGATION FACILITIES.....	132
10-2.04 HIGHWAY PLANTING.....	132
HIGHWAY PLANTING MATERIALS.....	132
ROADSIDE CLEARING.....	133
PESTICIDES.....	133
PREPARING PLANTING AREAS	134
PLANTING.....	134
LINER PLANTS (PLANT GROUP M).....	134
10-2.05 WILLOW CUTTINGS (PLANT GROUP W).....	134
ROOT PROTECTOR.....	135
PLANT ESTABLISHMENT WORK.....	135
10-2.06 IRRIGATION SYSTEMS.....	136
VALVE BOXES.....	136
IRRIGATION SYSTEMS FUNCTIONAL TEST	136
PIPE.....	136
SPRINKLERS.....	136
FINAL IRRIGATION SYSTEM CHECK.....	136
SECTION 10-3. SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS.....	137
10-3.01 DESCRIPTION.....	137
10-3.02 COST BREAK-DOWN.....	137
10-3.03 MAINTAINING EXISTING AND TEMPORARY ELECTRICAL SYSTEMS.....	137
10-3.04 STANDARDS, STEEL PEDESTALS AND POSTS.....	137
10-3.05 CONDUIT.....	138
10-3.06 CONDUCTORS AND WIRING.....	138
SIGNAL INTERCONNECT CABLE.....	138
10-3.07 SERVICE.....	138
10-3.08 NUMBERING ELECTRICAL EQUIPMENT.....	138
10-3.09 DETECTORS.....	138
10-3.10 LUMINAIRES.....	138
10-3.11 REMOVING, REINSTALLING OR SALVAGING ELECTRICAL EQUIPMENT.....	139
10-3.12 PAYMENT.....	139
SECTION 11. MODIFIED STANDARD SPECIFICATION SECTIONS	140
SECTION 11-1. QUALITY CONTROL / QUALITY ASSURANCE	140
SECTION 39: ASPHALT CONCRETE.....	140
39-1 GENERAL.....	140
39-1.01 DESCRIPTION.....	140
39-2 MATERIALS.....	140
39-2.01 ASPHALTS.....	140
39-2.02 AGGREGATE.....	140
39-2.03 ASPHALT CONCRETE MIXTURE.....	142
39-2.04 PAVEMENT REINFORCING FABRIC.....	142
39-3 ASPHALT CONCRETE MIX DESIGN PROPOSAL AND REVIEW	143
39-3.01 CONTRACTOR MIX DESIGN PROPOSAL.....	143
39-3.02 ENGINEER REVIEW OF ASPHALT CONCRETE MIX DESIGN	143
39-4 CONTRACTOR QUALITY CONTROL.....	144
39-4.01 GENERAL.....	144
39-4.02 QUALITY CONTROL PLAN.....	144
39-4.03 CONTRACTOR QUALITY CONTROL INSPECTION, SAMPLING, AND TESTING.....	145
39-4.04 CONTRACTOR PROCESS CONTROL.....	146
39-4.05 CONTRACTOR QUALITY CONTROL.....	147
39-4.06 CHARTS AND RECORDS.....	147

39-4.06A	Compliance Charts.....	147
39-4.06B	Records of Inspection and Testing.....	148
39-5	ENGINEER QUALITY ASSURANCE.....	148
39-5.01	GENERAL.....	148
39-5.02	SAMPLING AND TESTING FOR VERIFICATION.....	148
39-5.03	VERIFICATION.....	149
39-6	DISPUTE RESOLUTION.....	151
39-6.01	GENERAL.....	151
39-6.02	DURING THE ASPHALT CONCRETE MIX DESIGN REVIEW.....	151
39-6.03	DURING THE PRODUCTION START-UP EVALUATION.....	151
39-6.04	DURING PRODUCTION.....	152
39-7	STORING, PROPORTIONING AND MIXING MATERIALS.....	153
39-7.01	STORAGE.....	153
39-7.01A	Aggregate Cold Storage.....	153
39-7.01B	Aggregate Hot Storage.....	153
39-7.01C	Asphalt Binder Storage.....	153
39-7.02	DRYING.....	153
39-7.03	PROPORTIONING.....	154
39-7.03A	Proportioning for Batch Mixing.....	154
39-7.03B	Proportioning for Continuous Mixing.....	155
39-7.04	(BLANK).....	156
39-7.05	MIXING.....	156
39-7.05A	Batch Mixing.....	156
39-7.05B	Continuous Mixing.....	157
39-7.06	ASPHALT CONCRETE STORAGE.....	157
39-7.07	ASPHALT CONCRETE PLANTS.....	157
39-8	SUBGRADE, PRIME COAT, PAINT BINDER (TACK COAT), AND PAVEMENT REINFORCING FABRIC.....	157
39-8.01	SUBGRADE.....	157
39-8.02	PRIME COAT AND PAINT BINDER (TACK COAT).....	158
39-8.03	PAVEMENT REINFORCING FABRIC.....	158
39-9	SPREADING AND COMPACTING EQUIPMENT.....	159
39-9.01	SPREADING EQUIPMENT.....	159
39-9.02	COMPACTING EQUIPMENT.....	159
39-10	SPREADING AND COMPACTING.....	159
39-10.01	GENERAL REQUIREMENTS.....	159
39-10.02	PRODUCTION START-UP EVALUATION AND NUCLEAR DENSITY TEST STRIPS.....	160
39-10.02A	Production Start-Up Evaluation.....	161
39-10.02B	Nuclear Density Test Strip.....	161
39-10.03	SPREADING.....	162
39-10.04	COMPACTING.....	162
39-11	ACCEPTANCE OF WORK.....	163
39-11.01	GENERAL.....	163
39-11.02	STATISTICAL EVALUATION AND DETERMINATION OF PAY FACTOR.....	163
39-11.02A	General.....	163
39-11.02B	Statistical Evaluation.....	164
39-11.02C	Pay Factor Determination and Compensation Adjustment.....	165
39-12	MEASUREMENT AND PAYMENT.....	170
39-12.01	MEASUREMENT.....	170
39-12.02	PAYMENT.....	170
	SECTION 11-2. PORTLAND CEMENT CONCRETE.....	171
	SECTION 12. (BLANK).....	195
	SECTION 13. (BLANK).....	195
	SECTION 14 FEDERAL REQUIREMENTS FOR FEDERAL-AID CONSTRUCTION PROJECTS.....	196
	FEDERAL REQUIREMENT TRAINING SPECIAL PROVISIONS.....	216

STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Abbreviations
A10B	Symbols
A20A	Pavement Markers and Traffic Lines, Typical Details
A20B	Pavement Markers and Traffic Lines, Typical Details
A20C	Pavement Markers and Traffic Lines, Typical Details
A20D	Pavement Markers and Traffic Lines, Typical Details
A24A	Pavement Markings - Arrows
A24B	Pavement Markings - Arrows
A24C	Pavement Markings - Symbols and Numerals
A24D	Pavement Markings - Words
A24E	Pavement Markings - Words and Crosswalks
A62A	Excavation and Backfill - Miscellaneous Details
A62B	Limits of Payment for Excavation and Backfill - Bridge Surcharge and Wall
A62C	Limits of Payment for Excavation and Backfill - Bridge
A62D	Excavation and Backfill - Concrete Pipe Culverts
RSP A62DA	Excavation and Backfill - Concrete Pipe Culverts
A62E	Excavation and Backfill - Cast-In-Place Reinforced Concrete Box and Arch Culverts
A62F	Excavation and Backfill - Metal and Plastic Culverts
A73B	Markers
RSP A73C	Delineators, Channelizers and Barricades
A74	Survey Monuments
A76A	Concrete Barrier Type 60
A77A	Metal Beam Guard Railing – Typical Wood Post With Wood Block
A77B	Metal Beam Guard Railing - Standard Hardware
A77C	Metal Beam Guard Railing – Wood Post and Wood Block Details
A77D	Metal Beam Guard Railing – Typical Layouts
A77F	Metal Beam Guard Railing – Typical Embankment Widening for End Treatments
A77FA	Metal Beam Guard Railing – Typical Line Post Installation
A77H	Metal Beam Guard Railing - Anchor Cable and Anchor Plate Details
A77J	Metal Beam Guard Railing Connections to Bridge Railings, Retaining Walls and Abutments
RSP A77L	Metal Beam Guard Railing and Single Faced Barrier Railing Terminal System - End Treatments
A82C	Crash Cushion (Type REACT 9CBB)
A82CA	Crash Cushion (Type REACT 9CBB) – Backup Block Details
A82CB	Crash Cushion (Type REACT 9CBB) – Concrete Barrier Transition Details
A82D	Crash Cushion (Type REACT 9SCBS)
A82DA	Crash Cushion (Type REACT 9SCBS) – Connection to Concrete Barrier
A86	Barbed Wire and Wire Mesh Fences
A87	Curbs, Dikes and Driveways
A90	Accessible Parking
D73	Drainage Inlets
D74C	Drainage Inlet Details
D75B	Pipe Inlets
D75C	Pipe Inlets

D77A	Grate Details
D77B	Bicycle Proof Grate Details
D79	Precast Reinforced Concrete Pipe - Direct Design Method
D80	Cast-in-Place Reinforced Concrete Single Box Culvert
D81	Cast-in-Place Reinforced Concrete Double Box Culvert
RSP D82	Cast-in-Place Reinforced Concrete Culvert Miscellaneous Details
RSP D84	Box Culvert Wingwalls - Types A, B and C
D85	Box Culvert Wingwalls - Types D and E
D87A	Corrugated Metal Pipe Downdrain Details
D87B	Plastic Pipe Downdrain Details
D87D	Overside Drains
D88	Construction Loads On Culverts
RSP D89	Pipe Headwalls
D94A	Metal and Plastic Flared End Sections
D94B	Concrete Flared End Sections
D97A	Corrugated Metal Pipe Coupling Details No. 1 - Annular Coupling Band Bar and Strap and Angle Connectors
D97B	Corrugated Metal Pipe Coupling Details No. 2 - Hat Band Coupler and Flange Details
D97C	Corrugated Metal Pipe Coupling Details No. 3 - Helical and Universal Couplers
D97D	Corrugated Metal Pipe Coupling Details No. 4 - Hugger Coupling Bands
D97E	Corrugated Metal Pipe Coupling Details No. 5 - Standard Joint
D97G	Corrugated Metal Pipe Coupling Details No. 7 - Positive Joints and Downdrains
D97H	Reinforced Concrete Pipe or Non-Reinforced Concrete Pipe - Standard and Positive Joints
H1	Planting and Irrigation - Abbreviations
H2	Planting and Irrigation - Symbols
H3	Planting and Irrigation Details
H4	Planting and Irrigation Details
H5	Planting and Irrigation Details
H6	Planting and Irrigation Details
H7	Planting and Irrigation Details
H8	Planting and Irrigation Details
T1A	Temporary Crash Cushion, Sand Filled (Unidirectional)
T1B	Temporary Crash Cushion, Sand Filled (Bidirectional)
RSP T2	Temporary Crash Cushion, Sand Filled (Shoulder Installations)
T3	Temporary Railing (Type K)
T7	Construction Project Funding Identification Signs
T10	Traffic Control System for Lane Closure On Freeways and Expressways
T10A	Traffic Control System for Lane and Complete Closures On Freeways and Expressways
T13	Traffic Control System for Lane Closure On Two Lane Conventional Highways
T14	Traffic Control System for Ramp Closure
T15	Traffic Control System for Moving Lane Closure On Multilane Highways
T17	Traffic Control System for Moving Lane Closure On Two Lane Highways
B0-1	Bridge Details
RSP B0-3	Bridge Details
B0-5	Bridge Details
B0-13	Bridge Details
B2-5	Pile Details-Class 400 and Class 625
B2-8	Pile Details-Class 900 and Class 900C
RSP B3-1	Retaining Wall Type 1 - H=1200 Through 9100 mm
RSP B3-8	Retaining Wall Details No. 1
B3-9	Retaining Wall Details No. 2
B6-21	Joint Seals (Maximum Movement Rating = 50 mm)
B7-1	Box Girder Details
B7-7	Deck Drain - Type D-3
B7-10	Utility Opening - Box Girder
B11-47	Cable Railing

RS1	Roadside Signs, Typical Installation Details No. 1
RS2	Roadside Signs - Wood Post, Typical Installation Details No. 2
RS3	Roadside Signs - Laminated Wood Box Post Typical Installation Details No. 3
RS4	Roadside Signs, Typical Installation Details No. 4
S9	Overhead Signs - Walkway Details No. 1
S10	Overhead Signs - Walkway Details No. 2
RSP S11	Overhead Signs - Walkway Safety Railing Details
S40N	Overhead Signs- Tubular, Instructions and Examples
S40P	Overhead Signs - Tubular, Single Post Type, Layout and Pipe Selection
S40R	Overhead Signs - Tubular, Structural Frame Details No. 1
RSP S40S	Overhead Signs - Tubular, Structural Frame Details No. 2
RSP S40T	Overhead Signs - Tubular, Base Plate and Anchorage Details
RSP S40U	Overhead Signs - Tubular, Foundation Details
ES-1A	Signal, Lighting and Electrical Systems - Symbols and Abbreviations
ES-1B	Signal, Lighting and Electrical Systems - Symbols and Abbreviations
ES-2A	Signal, Lighting and Electrical Systems - Service Equipment
ES-2C	Signal, Lighting and Electrical Systems - Service Equipment Notes, Type III Series
ES-2E	Signal, Lighting and Electrical Systems - Service Equipment and Typical Wiring Diagram Type III-B Series
ES-4A	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-4B	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-4C	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-4D	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-4E	Signal, Lighting and Electrical Systems - Signal Heads and Mountings
ES-5A	Signal, Lighting and Electrical Systems - Detectors
ES-5B	Signal, Lighting and Electrical Systems - Detectors
ES-5C	Signal, Lighting and Electrical Systems - Detectors
ES-5E	Signal, Lighting and Electrical Systems - Detectors
RSP ES-6A	Lighting Standards - Types 15, 21 and 22
RSP ES-6B	Lighting Standards - Types 15 AND 21, Barrier Rail Mounted Details
RSP ES-6C	Lighting Standards - Type 15 Slip Base Insert
ES-6E	Lighting Standards - Types 30 and 31
RSP ES-6F	Lighting Standards - Type 30 and 31 Base Plate Details
ES-7B	Signal and Lighting Standards - Type 1 Standards and Equipment Numbering
ES-7M	Signal and Lighting Standards - Details No. 1
ES-7N	Signal and Lighting Standards - Details No. 2
ES-8	Signal, Lighting and Electrical Systems - Pull Box Details
ES-9A	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9B	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9C	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9D	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9E	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9F	Signal, Lighting and Electrical Systems - Flush Soffit Luminaire Modification Details, Structure Installations
ES-10	Signal, Lighting and Electrical Systems - Isolux Diagrams
ES-11	Signal, Lighting and Electrical Systems - Foundation Installations
ES-13A	Signal, Lighting and Electrical Systems - Splicing Details
ES-13B	Signal, Lighting and Electrical Systems - Wiring Details and Fuse Ratings
ES-15A	Sign Illumination - Mercury Vapor Sign Illumination Equipment
ES-15C	Sign Illumination - Sign Illumination Equipment
ES-15D	Sign Illumination - Sign Illumination Control

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

CONTRACT NO. 05-0161U4

05-Mon-101,156-153.5/153.9,T7.7/T8.3

Sealed proposals for the work shown on the plans entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR CONSTRUCTION ON STATE HIGHWAY IN MONTEREY COUNTY AT PRUNEDALE ON ROUTE 101 FROM 0.1 km SOUTH TO 0.4 km NORTH OF ROUTE 156/101 SEPARATION AND ON ROUTE 156 FROM MCGUFFIE ROAD TO ROUTE 156/101 SEPARATION

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on August 7, 2001, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR CONSTRUCTION ON STATE HIGHWAY IN MONTEREY COUNTY AT PRUNEDALE ON ROUTE 101 FROM 0.1 km SOUTH TO 0.4 km NORTH OF ROUTE 156/101 SEPARATION AND ON ROUTE 156 FROM MCGUFFIE ROAD TO ROUTE 156/101 SEPARATION

General work description: Interchange to be modified by grading and constructing asphalt concrete pavement on aggregate base and on existing surfacing; constructing 2 reinforced concrete box girder bridges, a prestressed concrete box girder bridge, 2 reinforced concrete retaining walls, and a mechanically stabilized embankment earth retaining structure; performing highway planting; and installing highway lighting and modifying highway signal and lighting.

This project has a goal of 13 percent disadvantaged business enterprise (DBE) participation.
No prebid meeting is scheduled for this project.

THIS PROJECT IS SUBJECT TO THE "BUY AMERICA" PROVISIONS OF THE SURFACE TRANSPORTATION ASSISTANCE ACT OF 1982 AS AMENDED BY THE INTERMODAL SURFACE TRANSPORTATION EFFICIENCY ACT OF 1991.

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A license or a combination of Class C licenses which constitutes a majority of the work.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

The Caltrans Central Region Construction Office is located at 850 L Street, Fresno CA 93721-2615. The District Duty Senior for this project can be reached at (805)549-3481, or by fax at (805)549-3523. The Department will consider bidder inquiries only when a completed Bidder Inquiry Form is submitted. The Bidder Inquiry Form is available on the Internet at <http://www.dot.ca.gov/dist6/construction>. To the extent feasible and at the discretion of the Department, completed Bidder Inquiry Forms submitted for consideration will be investigated, and responses will be posted on the Internet at <http://www.dot.ca.gov/dist6/construction>.

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

Cross sections for this project are available at the office of the District Director of Transportation of the district in which the work is situated in paper copy format.

The successful bidder shall furnish a payment bond and a performance bond.

The Department of Transportation hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full opportunity to submit bids in response to this invitation.

The U.S. Department of Transportation (DOT) provides a toll-free "hotline" service to report bid rigging activities. Bid rigging activities can be reported Mondays through Fridays, between 8:00 a.m. and 5:00 p.m., eastern time, Telephone No. 1-800-424-9071. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report these activities. The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' Internet Web Site at: <http://www.dir.ca.gov>. The Federal minimum wage rates for this project as predetermined by the United States Secretary of Labor are set forth in the books issued for bidding purposes entitled "Proposal and Contract," and in copies of this book that may be examined at the offices described above where project plans, special provisions, and proposal forms may be seen. Addenda to modify the Federal minimum wage rates, if necessary, will be issued to holders of "Proposal and Contract" books. Future effective general prevailing wage rates which have been predetermined and are on file with the California Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

Attention is directed to the Federal minimum wage rate requirements in the books entitled "Proposal and Contract." If there is a difference between the minimum wage rates predetermined by the Secretary of Labor and the general prevailing wage rates determined by the Director of the California Department of Industrial Relations for similar classifications of labor, the Contractor and subcontractors shall pay not less than the higher wage rate. The Department will not accept lower State wage rates not specifically included in the Federal minimum wage determinations. This includes "helper" (or other classifications based on hours of experience) or any other classification not appearing in the Federal wage determinations. Where Federal wage determinations do not contain the State wage rate determination otherwise available for use by the Contractor and subcontractors, the Contractor and subcontractors shall pay not less than the Federal minimum wage rate which most closely approximates the duties of the employees in question.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated June 25, 2001

RMY/TH

Contract No. «Dist»-«Contract_No»

COPY OF ENGINEER'S ESTIMATE
(NOT TO BE USED FOR BIDDING PURPOSES)
05-0161U4

Item	Item Code	Item	Unit of Measure	Estimated Quantity
1	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM
2	070018	TIME-RELATED OVERHEAD	WDAY	400
3 (S)	021586	TEMPORARY FENCE (TYPE ESA)	M	400
4	073028	450 MM TEMPORARY CULVERT	M	38
5	021587	TEMPORARY DRAINAGE INLET	EA	2
6	021588	200 MM TEMPORARY ENTRANCE TAPER	EA	6
7	021589	200 MM TEMPORARY ANCHOR ASSEMBLY	EA	28
8	021590	200 MM TEMPORARY PIPE DOWNDRAIN	M	87
9	021591	450 MM TEMPORARY PIPE DOWNDRAIN	M	33
10	021592	450 MM TEMPORARY ANCHOR ASSEMBLY	EA	11
11	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM
12	074020	WATER POLLUTION CONTROL	LS	LUMP SUM
13 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
14 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
15 (S)	120120	TYPE III BARRICADE	EA	40
16 (S)	120151	TEMPORARY TRAFFIC STRIPE (TAPE)	M	7110
17 (S)	120152	TEMPORARY PAVEMENT MARKING (TAPE)	M2	23
18 (S)	120165	CHANNELIZER (SURFACE MOUNTED)	EA	210
19 (S)	120166	CHANNELIZER (SURFACE MOUNTED) (LEFT IN PLACE)	EA	18
20 (S)	120300	TEMPORARY PAVEMENT MARKER	EA	720

Item	Item Code	Item	Unit of Measure	Estimated Quantity
21 (S)	121140	TEMPORARY METAL BEAM GUARD RAILING	M	16
22 (S)	121148	TEMPORARY TERMINAL SECTION (TYPE B)	EA	1
23 (S)	121150	TEMPORARY END SECTION	EA	1
24 (S)	021593	TEMPORARY TERMINAL SYSTEM (TYPE SRT)	EA	2
25 (S)	128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	LUMP SUM
26	129000	TEMPORARY RAILING (TYPE K)	M	1830
27 (S)	129100	TEMPORARY CRASH CUSHION MODULE	EA	150
28 (S)	150711	REMOVE PAINTED TRAFFIC STRIPE	M	3180
29 (S)	150712	REMOVE PAINTED PAVEMENT MARKING	M2	8
30 (S)	150722	REMOVE PAVEMENT MARKER	EA	2000
31	150742	REMOVE ROADSIDE SIGN	EA	42
32	150771	REMOVE ASPHALT CONCRETE DIKE	M	52
33	150806	REMOVE PIPE	M	140
34	150821	REMOVE HEADWALL	EA	2
35 (S)	151572	RECONSTRUCT METAL BEAM GUARD RAILING	M	30
36	152390	RELOCATE ROADSIDE SIGN	EA	4
37	152430	ADJUST INLET	EA	2
38 (S)	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	M2	1620
39	153210	REMOVE CONCRETE	M3	17
40	155003	CAP INLET	EA	1

Item	Item Code	Item	Unit of Measure	Estimated Quantity
41	160101	CLEARING AND GRUBBING	LS	LUMP SUM
42	190101	ROADWAY EXCAVATION	M3	40 800
43	190185	SHOULDER BACKING	STA	4
44 (F)	192003	STRUCTURE EXCAVATION (BRIDGE)	M3	1760
45 (F)	192037	STRUCTURE EXCAVATION (RETAINING WALL)	M3	1370
46 (F)	193003	STRUCTURE BACKFILL (BRIDGE)	M3	1069
47 (F)	193013	STRUCTURE BACKFILL (RETAINING WALL)	M3	1040
48 (F)	193030	PERVIOUS BACKFILL MATERIAL	M3	76
49 (F)	193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	M3	95
50 (F)	197020	EARTH RETAINING STRUCTURE	M2	193
51	198001	IMPORTED BORROW	M3	26 500
52 (S)	200001	HIGHWAY PLANTING	LS	LUMP SUM
53 (S)	021594	EROSION CONTROL (BLANKET) (TYPE 1)	M2	2000
54 (S)	021595	EROSION CONTROL (BLANKET) (TYPE 2)	M2	200
55 (S)	203003	STRAW (EROSION CONTROL)	TONN	11
56 (S)	203014	FIBER (EROSION CONTROL)	KG	6000
57 (S)	203026	MOVE IN OR MOVE OUT (EROSION CONTROL)	EA	3
58 (S)	203045	PURE LIVE SEED (EROSION CONTROL)	KG	150
59 (S)	203056	COMMERCIAL FERTILIZER (EROSION CONTROL)	KG	450
60 (S)	203061	STABILIZING EMULSION (EROSION CONTROL)	KG	600

Item	Item Code	Item	Unit of Measure	Estimated Quantity
61 (S)	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM
62 (S)	208000	IRRIGATION SYSTEM	LS	LUMP SUM
63 (S)	208732	250 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	M	180
64 (S)	208800	300 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	37
65	220101	FINISHING ROADWAY	LS	LUMP SUM
66	260201	CLASS 2 AGGREGATE BASE	M3	6200
67	390152	ASPHALT CONCRETE	TONN	12 600
68	394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	M2	130
69	394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	M	500
70	394044	PLACE ASPHALT CONCRETE DIKE (TYPE C)	M	130
71	394048	PLACE ASPHALT CONCRETE DIKE (TYPE E)	M	1470
72	394049	PLACE ASPHALT CONCRETE DIKE (TYPE F)	M	84
73	397001	ASPHALTIC EMULSION (PAINT BINDER)	TONN	13
74	490696	FURNISH PILING (CLASS 900)	M	397
75 (S)	490697	DRIVE PILE (CLASS 900)	EA	26
76	490753	FURNISH PILING (CLASS 625)	M	1559
77 (S)	490754	DRIVE PILE (CLASS 625)	EA	133
78 (S)	500001	PRESTRESSING CAST-IN-PLACE CONCRETE	LS	LUMP SUM
79 (F)	510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	M3	188
80 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	M3	945

Item	Item Code	Item	Unit of Measure	Estimated Quantity
81 (F)	510060	STRUCTURAL CONCRETE, RETAINING WALL	M3	480
82 (F)	510085	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ)	M3	25
83 (F)	510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	M3	94
84 (F)	021596	CLASS 2 CONCRETE	M3	677
85 (F)	510413	CLASS 1 CONCRETE (BOX CULVERT)	M3	3
8 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	6
87 (F)	510510	MINOR CONCRETE (INVERT PAVING)	M3	11
88 (F)	511035	ARCHITECTURAL TREATMENT	M2	672
89 (S)	519120	JOINT SEAL (MR 15 MM)	M	36
90 (S)	519144	JOINT SEAL (MR 50 MM)	M	35
91 (S-F)	520101	BAR REINFORCING STEEL	KG	73 312
92 (S-F)	520102	BAR REINFORCING STEEL (BRIDGE)	KG	125 380
93 (S-F)	520103	BAR REINFORCING STEEL (RETAINING WALL)	KG	48 940
94 (S-F)	520107	BAR REINFORCING STEEL (BOX CULVERT)	KG	250
95 (F)	560203	FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	KG	1067
96 (S-F)	560204	INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	KG	1067
97 (F)	560208	FURNISH SIGN STRUCTURE (TUBULAR)	KG	3510
98 (S-F)	560209	INSTALL SIGN STRUCTURE (TUBULAR)	KG	3510
99 (S)	561010	1070 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	13
100	566011	ROADSIDE SIGN - ONE POST	EA	46

Item	Item Code	Item	Unit of Measure	Estimated Quantity
101	566012	ROADSIDE SIGN - TWO POST	EA	13
102	568001	INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	1
103	568023	INSTALL ROADSIDE SIGN (LAMINATED WOOD BOX POST)	EA	3
104	620909	450 MM ALTERNATIVE PIPE CULVERT	M	55
105	620913	600 MM ALTERNATIVE PIPE CULVERT	M	110
106	664009	300 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	10
107	664014	450 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	10
108	664019	600 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	2
109	664032	900 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	6
110	692086	200 MM ENTRANCE TAPER	EA	10
111	692382	200 MM ANCHOR ASSEMBLY	EA	49
112	698084	200 MM ALTERNATIVE PIPE DOWNDRAIN	M	150
113	705334	300 MM ALTERNATIVE FLARED END SECTION	EA	1
114	705336	450 MM ALTERNATIVE FLARED END SECTION	EA	2
115	705337	600 MM ALTERNATIVE FLARED END SECTION	EA	6
116	707133	900 MM PRECAST CONCRETE PIPE INLET	M	3
117	719300	MANHOLE	EA	1
118 (F)	721810	SLOPE PAVING (CONCRETE)	M3	88
119	731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	M3	18
120 (F)	731517	MINOR CONCRETE (GUTTER)	M	70

Item	Item Code	Item	Unit of Measure	Estimated Quantity
121 (F)	750001	MISCELLANEOUS IRON AND STEEL	KG	954
122 (F)	750501	MISCELLANEOUS METAL (BRIDGE)	KG	300
123 (S)	800002	FENCE (TYPE BW, WOOD POST)	M	4.4
124	810111	SURVEY MONUMENT (TYPE A)	EA	6
125	820107	DELINEATOR (CLASS 1)	EA	45
126	820135	OBJECT MARKER (TYPE R)	EA	1
127 (S)	832003	METAL BEAM GUARD RAILING (WOOD POST)	M	120
128 (F)	833187	CONCRETE BARRIER (TYPE 27 MODIFIED)	M	390
129 (S-F)	839521	CABLE RAILING	M	45
130 (S)	839551	TERMINAL SECTION (TYPE B)	EA	7
131 (S)	839553	END SECTION	EA	3
132 (S)	839565	TERMINAL SYSTEM (TYPE SRT)	EA	10
133 (S)	839604	CRASH CUSHION (REACT 9CBB)	EA	1
134 (S)	839605	CRASH CUSHION (REACT 9SCBS)	EA	1
135	839701	CONCRETE BARRIER (TYPE 60)	M	12
136 (F)	839704	CONCRETE BARRIER (TYPE 60D)	M	162
137 (S)	840515	THERMOPLASTIC PAVEMENT MARKING	M2	230
138 (S)	840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	M	7500
139 (S)	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	430
140 (S)	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	730

Item	Item Code	Item	Unit of Measure	Estimated Quantity
141 (S)	860401	LIGHTING	LS	LUMP SUM
142 (S)	861501	MODIFY SIGNAL AND LIGHTING	LS	LUMP SUM
143	999990	MOBILIZATION	LS	LUMP SUM

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISIONS

Annexed to Contract No. 05-0161U4

SECTION 1. SPECIFICATIONS AND PLANS

The work embraced herein shall conform to the provisions in the Standard Specifications dated July 1999, and the Standard Plans dated July 1999, of the Department of Transportation insofar as the same may apply, and these special provisions.

Amendments to the Standard Specifications set forth in these special provisions shall be considered as part of the Standard Specifications for the purposes set forth in Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications and Special Provisions," of the Standard Specifications. Whenever either the term "Standard Specifications is amended" or the term "Standard Specifications are amended" is used in the special provisions, the indented text or table following the term shall be considered an amendment to the Standard Specifications. In case of conflict between such amendments and the Standard Specifications, the amendments shall take precedence over and be used in lieu of the conflicting portions.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and shall be used in lieu of the conflicting portions.

SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS

2-1.01 GENERAL

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the Proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in conformance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, each proposal shall have listed therein the portion of work that will be performed by each subcontractor listed.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

Submit request for substitution of an "or equal" item, and the data substantiating the request to the Department of Transportation, Central Region Construction, P.O. Box 12616, Fresno, CA 93778, so that the request is received by the Department by close of business on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

The contractor, sub recipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate. Each subcontract signed by the bidder must include this assurance.

2-1.015 FEDERAL LOBBYING RESTRICTIONS

Section 1352, Title 31, United States Code prohibits Federal funds from being expended by the recipient or any lower tier subrecipient of a Federal-aid contract to pay for any person for influencing or attempting to influence a Federal agency or Congress in connection with the awarding of any Federal-aid contract, the making of any Federal grant or loan, or the entering into of any cooperative agreement.

If any funds other than Federal funds have been paid for the same purposes in connection with this Federal-aid contract, the recipient shall submit an executed certification and, if required, submit a completed disclosure form as part of the bid documents.

A certification for Federal-aid contracts regarding payment of funds to lobby Congress or a Federal agency is included in the Proposal. Standard Form - LLL, "Disclosure of Lobbying Activities," with instructions for completion of the Standard Form is also included in the Proposal. Signing the Proposal shall constitute signature of the Certification.

The above-referenced certification and disclosure of lobbying activities shall be included in each subcontract and any lower-tier contracts exceeding \$100,000. All disclosure forms, but not certifications, shall be forwarded from tier to tier until received by the Engineer.

The Contractor, subcontractors and any lower-tier contractors shall file a disclosure form at the end of each calendar quarter in which there occurs any event that requires disclosure or that materially affects the accuracy of the information contained in any disclosure form previously filed by the Contractor, subcontractors and any lower-tier contractors. An event that materially affects the accuracy of the information reported includes:

- A. A cumulative increase of \$25,000 or more in the amount paid or expected to be paid for influencing or attempting to influence a covered Federal action; or
- B. A change in the person(s) or individual(s) influencing or attempting to influence a covered Federal action; or,
- C. A change in the officer(s), employee(s), or Member(s) contacted to influence or attempt to influence a covered Federal action.

2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE)

This project is subject to Part 26, Title 49, Code of Federal Regulations entitled "Participation by Disadvantaged Business Enterprises in Department of Transportation Financial Assistance Programs." The Regulations in their entirety are incorporated herein by this reference.

Bidders shall be fully informed respecting the requirements of the Regulations and the Department's Disadvantaged Business Enterprise (DBE) program developed pursuant to the Regulations; particular attention is directed to the following matters:

- A. A DBE must be a small business concern as defined pursuant to Section 3 of U.S. Small Business Act and relevant regulations promulgated pursuant thereto.
- B. A DBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, vendor of material or supplies, or as a trucking company.
- C. A DBE bidder, not bidding as a joint venture with a non-DBE, will be required to document one or a combination of the following:
 - 1. The bidder will meet the goal by performing work with its own forces.
 - 2. The bidder will meet the goal through work performed by DBE subcontractors, suppliers or trucking companies.
 - 3. The bidder, prior to bidding, made adequate good faith efforts to meet the goal.
- D. A DBE joint venture partner must be responsible for specific contract items of work, or portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DBE joint venture partner must share in the capital contribution, control, management, risks and profits of the joint venture. The DBE joint venturer must submit the joint venture agreement with the proposal or the DBE Information form required in the Section entitled "Submission of DBE Information" of these special provisions.
- E. A DBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
- F. DBEs must be certified by either the California Department of Transportation, or by a participating State of California or local agency which certifies in conformance with Title 49, Code of Federal Regulations, Part 26, as of the date of bid opening. It is the Contractor's responsibility to verify that DBEs are certified. Listings of DBEs certified by the Department are available from the following sources:
 - 1. The Department's DBE Directory, which is published quarterly. This Directory may be obtained from the Department of Transportation, Materiel Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520.

2. The Department's Electronic Information Bulletin Board Service, which is accessible by modem and is updated weekly. The Bulletin Board may be accessed by first contacting the Department's Business Enterprise Program at Telephone: (916) 227-8937 and obtaining a user identification and password.
3. The Department's web site at <http://www.dot.ca.gov/hq/bep/index.htm>.
4. The organizations listed in the Section entitled "DBE Goal for this Project" of these special provisions.

G. Credit for materials or supplies purchased from DBEs will be as follows:

1. If the materials or supplies are obtained from a DBE manufacturer, 100 percent of the cost of the materials or supplies will count toward the DBE goal. A DBE manufacturer is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications.
2. If the materials or supplies are purchased from a DBE regular dealer, 60 percent of the cost of the materials or supplies will count toward the DBE goal. A DBE regular dealer is a firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications and required under the contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business. To be a DBE regular dealer, the firm must be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question. A person may be a DBE regular dealer in such bulk items as petroleum products, steel, cement, gravel, stone, or asphalt without owning, operating, or maintaining a place of business as provided in this paragraph G.2. if the person both owns and operates distribution equipment for the products. Any supplementing of regular dealers' own distribution equipment shall be by a long-term lease agreement and not on an ad hoc or contract-by-contract basis. Packagers, brokers, manufacturers' representatives, or other persons who arrange or expedite transactions are not DBE regular dealers within the meaning of this paragraph G.2.
3. Credit for materials or supplies purchased from a DBE which is neither a manufacturer nor a regular dealer will be limited to the entire amount of fees or commissions charged for assistance in the procurement of the materials and supplies, or fees or transportation charges for the delivery of materials or supplies required on a job site, provided the fees are reasonable and not excessive as compared with fees charged for similar services.

H. Credit for DBE trucking companies will be as follows:

1. The DBE must be responsible for the management and supervision of the entire trucking operation for which it is responsible on a particular contract, and there cannot be a contrived arrangement for the purpose of meeting the DBE goal.
2. The DBE must itself own and operate at least one fully licensed, insured, and operational truck used on the contract.
3. The DBE receives credit for the total value of the transportation services it provides on the contract using trucks its owns, insures, and operates using drivers it employs.
4. The DBE may lease trucks from another DBE firm, including an owner-operator who is certified as a DBE. The DBE who leases trucks from another DBE receives credit for the total value of the transportation services the lessee DBE provides on the contract.
5. The DBE may also lease trucks from a non-DBE firm, including an owner-operator. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement. The DBE does not receive credit for the total value of the transportation services provided by the lessee, since these services are not provided by a DBE.
6. For the purposes of this paragraph H, a lease must indicate that the DBE has exclusive use of and control over the truck. This does not preclude the leased truck from working for others during the term of the lease with the consent of the DBE, so long as the lease gives the DBE absolute priority for use of the leased truck. Leased trucks must display the name and identification number of the DBE.

- I. Noncompliance by the Contractor with the requirements of the regulations constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.
- J. Bidders are encouraged to use services offered by financial institutions owned and controlled by DBEs.

2-1.02A DBE GOAL FOR THIS PROJECT

The Department has established the following goal for Disadvantaged Business Enterprise (DBE) participation for this project:

Disadvantaged Business Enterprise (DBE): 13 percent

Bidders may use the services of the following firms to contact interested DBEs. These firms are available to assist DBEs in preparing bids for subcontracting or supplying materials.

The following firms may be contacted for projects in the following locations:

<p>Districts 04, 05 (except San Luis Obispo and Santa Barbara Counties), 06 (except Kern County) and 10:</p> <hr/> <p>Triaxial Management Services, Inc. - Oakland</p> <p>1545 Willow Street, 1st Floor Oakland, CA 94607 Telephone - (510) 286-1313 FAX No. - (510) 286-6792</p>	<p>Districts 08, 11 and 12:</p> <hr/> <p>Triaxial Management Services, Inc. - San Diego 2725 Congress Street, Suite 1-D San Diego, CA 92110 Telephone - (619) 543-5109 FAX No. - (619) 543-5108</p>
<p>Districts 07 and 08; in San Luis Obispo and Santa Barbara Counties in District 05; and in Kern County in District 06:</p> <hr/> <p>Triaxial Management Services, Inc. - Los Angeles 2594 Industry Way, Suite 101 Lynwood, CA 90262 Telephone - (310) 537-6677 FAX No. - (310) 637-0128</p>	<p>Districts 01, 02, 03 and 09:</p> <hr/> <p>Triaxial Management Services, Inc. - Sacramento 930 Alhambra Blvd., #205 Sacramento, CA 95816 Telephone - (916) 553-4172 FAX No. - (916) 553-4173</p>

2-1.02B SUBMISSION OF DBE INFORMATION

The required DBE information shall be submitted on the "CALTRANS BIDDER - DBE INFORMATION" form included in the Proposal. If the DBE information is not submitted with the bid, the DBE Information form shall be removed from the documents prior to submitting the bid.

It is the bidder's responsibility to make enough work available to DBEs and to select those portions of the work or material needs consistent with the available DBEs to meet the goal for DBE participation or to provide information to establish that, prior to bidding, the bidder made adequate good faith efforts to do so.

If DBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit DBE information to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. DBE information sent by U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Failure to submit the required DBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DBE information unless requested to do so by the Department.

The bidder's DBE information shall establish that good faith efforts to meet the DBE goal have been made. To establish good faith efforts, the bidder shall demonstrate that the goal will be met or that, prior to bidding, adequate good faith efforts to meet the goal were made.

Bidders are cautioned that even though their submittal indicates they will meet the stated DBE goal, their submittal should also include their adequate good faith efforts information along with their DBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DBE information shall include the names, addresses and phone numbers of DBE firms that will participate, with a complete description of work or supplies to be provided by each, the dollar value of each DBE transaction, and a written confirmation from the DBE that it is participating in the contract. A copy of the DBE's quote will serve as written confirmation that the DBE is participating in the contract. When 100 percent of a contract item of work is not to be performed or furnished by a DBE, a description of the exact portion of that work to be performed or furnished by that DBE shall be included in the DBE information, including the planned location of that work. The work that a DBE prime contractor has committed to performing with its own forces as well as the work that it has committed to be performed by DBE subcontractors, suppliers and trucking companies will count toward the goal.

The information necessary to establish the bidder's adequate good faith efforts to meet the DBE goal should include:

- A. The names and dates of each publication in which a request for DBE participation for this project was placed by the bidder.
- B. The names and dates of written notices sent to certified DBEs soliciting bids for this project and the dates and methods used for following up initial solicitations to determine with certainty whether the DBEs were interested.
- C. The items of work which the bidder made available to DBE firms, including, where appropriate, any breaking down of the contract work items (including those items normally performed by the bidder with its own forces) into economically feasible units to facilitate DBE participation. It is the bidder's responsibility to demonstrate that sufficient work to meet the DBE goal was made available to DBE firms.
- D. The names, addresses and phone numbers of rejected DBE firms, the firms selected for that work, and the reasons for the bidder's choice.
- E. Efforts made to assist interested DBEs in obtaining bonding, lines of credit or insurance, and any technical assistance or information related to the plans, specifications and requirements for the work which was provided to DBEs.
- F. Efforts made to assist interested DBEs in obtaining necessary equipment, supplies, materials, or related assistance or services, excluding supplies and equipment the DBE subcontractor purchases or leases from the prime contractor or its affiliate.
- G. The names of agencies contacted to provide assistance in contacting, recruiting and using DBE firms.
- H. Any additional data to support a demonstration of good faith efforts.

SECTION 3. AWARD AND EXECUTION OF CONTRACT

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DBE participation or has demonstrated, to the satisfaction of the Department, adequate good faith efforts to do so. Meeting the goal for DBE participation or demonstrating, to the satisfaction of the Department, adequate good faith efforts to do so is a condition for being eligible for award of contract.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 31 percent of payments due the contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Attention is directed to the provisions in Sections 8-1.03, "Beginning of Work," 8-1.06, "Time of Completion," 8-1.07, "Liquidated Damages," and 20-4.08, "Plant Establishment Work," of the Standard Specifications and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation or on December 3rd, 2001, whichever occurs later.

The work (except plant establishment work) shall be diligently prosecuted to completion before the expiration of **400 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract or beginning on December 3rd, 2001, whichever occurs later.

The Contractor shall pay to the State of California the sum of \$700 per day, for each and every calendar day's delay in finishing the work (except plant establishment work) in excess of the number of working days prescribed above.

The Contractor shall diligently prosecute all work (including plant establishment) to completion before the expiration of **650 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract or beginning on December 3rd, 2001, whichever occurs later.

The Contractor shall pay to the State of California the sum of \$250 per day, for each and every calendar day's delay in completing the work in excess of the number of working days prescribed above.

In no case will liquidated damages of more than \$700 per day be assessed.

SECTION 5. GENERAL

SECTION 5-1. MISCELLANEOUS

5-1.01 PLANS AND WORKING DRAWINGS

When the specifications require working drawings to be submitted to the Division of Structure Design, the drawings shall be submitted to: Division of Structure Design, Documents Unit, Mail Station 9, 1801 30th Street, Sacramento, CA 95816, Telephone 916 227-8252.

5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK

The second paragraph of Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications is amended to read:

- Where the Department has made investigations of site conditions, including subsurface conditions in areas where work is to be performed under the contract, or in other areas, some of which may constitute possible local material sources, bidders or Contractors may, upon written request, inspect the records of the Department as to those investigations subject to and upon the conditions hereinafter set forth.

Attention is directed to "Differing Site Conditions" of these special provisions regarding physical conditions at the site which may differ from those indicated in "Materials Information," log of test borings or other geotechnical information obtained by the Department's investigation of site conditions.

5-1.012 DIFFERING SITE CONDITIONS

Attention is directed to Section 5-1.116, "Differing Site Conditions," of the Standard Specifications.

During the progress of the work, if subsurface or latent conditions are encountered at the site differing materially from those indicated in the "Materials Information," log of test borings, other geotechnical data obtained by the Department's investigation of subsurface conditions, or an examination of the conditions above ground at the site, the party discovering those conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

The Contractor will be allowed 15 days from the notification of the Engineer's determination of whether or not an adjustment of the contract is warranted, in which to file a notice of potential claim in conformance with the provisions of Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and as specified herein; otherwise the decision of the Engineer shall be deemed to have been accepted by the Contractor as correct. The notice of potential claim shall set forth in what respects the Contractor's position differs from the Engineer's determination and provide any additional information obtained by the Contractor, including but not limited to additional geotechnical data. The notice of potential claim shall be accompanied by the Contractor's certification that the following were made in preparation of the bid: a review of the contract, a review of the "Materials Information," a review of the log of test borings and other records of geotechnical data to the extent they were made available to bidders prior to the opening of bids, and an examination of the conditions above ground at the site. Supplementary information, obtained by the Contractor subsequent to the filing of the notice of potential claim, shall be submitted to the Engineer in an expeditious manner.

5-1.015 LABORATORY

When a reference is made in the specifications to the "Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

5-1.017 CONTRACT BONDS

Attention is directed to Section 3-1.02, "Contract Bonds," of the Standard Specifications and these special provisions.

The payment bond shall be in a sum not less than one hundred percent of the total amount payable by the terms of the contract.

5-1.018 EXCAVATION SAFETY PLANS

Section 5-1.02A, "Trench Excavation Safety Plans," of the Standard Specifications is amended to read:

5-1.02A Excavation Safety Plans

- The Construction Safety Orders of the Division of Occupational Safety and Health shall apply to all excavations. For all excavations 1.5 m or more in depth, the Contractor shall submit to the Engineer a detailed plan showing the design and details of the protective systems to be provided for worker protection from the hazard of caving ground during excavation. The detailed plan shall include any tabulated data and any design calculations used in the preparation of the plan. Excavation shall not begin until the detailed plan has been reviewed and approved by the Engineer.
- Detailed plans of protective systems for which the Construction Safety Orders require design by a registered professional engineer shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California, and shall include the soil classification, soil properties, soil design calculations that demonstrate adequate stability of the protective system, and any other design calculations used in the preparation of the plan.
- No plan shall allow the use of a protective system less effective than that required by the Construction Safety Orders.
- If the detailed plan includes designs of protective systems developed only from the allowable configurations and slopes, or Appendices, contained in the Construction Safety Orders, the plan shall be submitted at least 5 days before the Contractor intends to begin excavation. If the detailed plan includes designs of protective systems developed from tabulated data, or designs for which design by a registered professional engineer is required, the plan shall be submitted at least 3 weeks before the Contractor intends to begin excavation.
- Attention is directed to Section 7-1.01E, "Trench Safety."

The third paragraph of Section 19-1.02, "Preservation of Property," of the Standard Specifications is amended to read:

- In addition to the provisions in Sections 5-1.02, "Plans and Working Drawings," and 5-1.02A, "Excavation Safety Plans," detailed plans of the protective systems for excavations on or affecting railroad property will be reviewed for adequacy of protection provided for railroad facilities, property, and traffic. These plans shall be submitted at least 9 weeks before the Contractor intends to begin excavation requiring the protective systems. Approval by the Engineer of the detailed plans for the protective systems will be contingent upon the plans being satisfactory to the railroad company involved.

5-1.019 COST REDUCTION INCENTIVE

Attention is directed to Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

Prior to preparing a cost reduction proposal, the Contractor shall request a meeting with the Engineer to discuss the proposal in concept and to determine the merit of the cost reduction proposal. Items of discussion will also include permit issues, impact on other projects, impact on the project schedule, peer reviews, and review times required by the Department and other agencies.

5-1.02 LABOR NONDISCRIMINATION

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM

(GOV. CODE, SECTION 12990)

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5000 or more.

5-1.03 INTEREST ON PAYMENTS

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments, and claim payments as follows:

- A. Unpaid progress payments, payment after acceptance, and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
- B. Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in conformance with the provisions in Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
- C. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and extra work payments shall be 10 percent per annum.
- D. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

5-1.031 FINAL PAYMENT AND CLAIMS

Attention is directed to Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications.

If the Contractor files a timely written statement of claims in response to the proposed final estimate, the District that administers the contract will submit a claim position letter to the Contractor by hand delivery or deposit in the U.S. mail within 135 days of acceptance of the contract. The claim position letter will delineate the District's position on the Contractor's claims. If the Contractor disagrees with the claim position letter, the Contractor shall submit a written notification of its disagreement to be received by the District not later than 15 days after the Contractor's receipt of the claim position letter. The written notification of disagreement shall set forth the basis for the Contractor's disagreement and be submitted to the office designated in the claim position letter. The Contractor's failure to provide a timely, written notification of disagreement shall constitute the Contractor's acceptance and agreement with the determinations provided in the claim position letter and with final payment pursuant to the claim position letter.

If the Contractor files a timely notification of disagreement with the District claim position letter, the board of review designated by the District Director to review claims that remain in dispute will meet with the Contractor within 45 days after receipt by the District of the notification of disagreement. Attendance by the Contractor at the board of review meeting shall be mandatory.

If the District fails to submit a claim position letter to the Contractor within 135 days after the acceptance of the contract and the Contractor has claims that remain in dispute, the Contractor may request a meeting with the board of review designated by the District Director to review claims that remain in dispute. The Contractor's request for a meeting shall identify the claims that remain in dispute. If the Contractor files a request for a meeting, the board of review will meet with the Contractor within 45 days after the District receives the request for the meeting. Attendance by the Contractor at the District Director's board of review meeting shall be mandatory.

Failure of the Contractor to file a timely written statement of claims in response to the proposed final estimate, or to file a timely notification of disagreement with the District claim position letter, or to attend the District Director's board of review meeting shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract and shall be a bar to arbitration in conformance with the requirements in Section 10240.2 of the California Public Contract Code.

5-1.04 PUBLIC SAFETY

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations.—The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
 - 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
 - 2. Excavations less than 0.3-m deep.
 - 3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
 - 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
 - 5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
 - 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles.—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas.—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications. Temporary railing (Type K), conforming to the details shown on 1999 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.05 SURFACE MINING AND RECLAMATION ACT

Attention is directed to the Surface Mining and Reclamation Act of 1975, commencing in Public Resources Code, Mining and Geology, Section 2710, which establishes regulations pertinent to surface mining operations, and to California Public Contract Code Section 10295.5.

Material from mining operations furnished for this project shall only come from permitted sites in compliance with California Public Contract Code Section 10295.5.

The requirements of this section shall apply to materials furnished for the project, except for acquisition of materials in conformance with the provisions in Section 4-1.05, "Use of Materials Found on the Work," of the Standard Specifications.

5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

5-1.07 YEAR 2000 COMPLIANCE

This contract is subject to Year 2000 Compliance for automated devices in the State of California.

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year 2000 is recognized and processed as a leap year. The product shall operate accurately in the manner in which the product was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all automated devices furnished for the project.

5-1.075 BUY AMERICA REQUIREMENTS

Attention is directed to the "Buy America" requirements of the Surface Transportation Assistance Act of 1982 (Section 165) and the Intermodal Surface Transportation Efficiency Act of 1991 (ISTEA) Sections 1041(a) and 1048(a), and the regulations adopted pursuant thereto. In conformance with the law and regulations, all manufacturing processes for steel and iron materials furnished for incorporation into the work on this project shall occur in the United States; with the exception that pig iron and processed, pelletized and reduced iron ore manufactured outside of the United States may be used in the domestic manufacturing process for such steel and iron materials. The application of coatings, such as epoxy coating, galvanizing, painting, and other coatings that protect or enhance the value of steel or iron materials shall be considered a manufacturing process subject to the "Buy America" requirements.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for steel and iron materials. The certificates, in addition to certifying that the materials comply with the specifications, shall specifically certify that all manufacturing processes for the materials occurred in the United States, except for the above exceptions.

The requirements imposed by the law and regulations do not prevent a minimal use of foreign steel and iron materials if the total combined cost of the materials used does not exceed one-tenth of one percent (0.1 percent) of the total contract cost or \$2500, whichever is greater. The Contractor shall furnish the Engineer acceptable documentation of the quantity and value of the foreign steel and iron prior to incorporating the materials into the work.

5-1.08 SUBCONTRACTOR AND DBE RECORDS

The Contractor shall maintain records showing the name and business address of each first-tier subcontractor. The records shall also show the name and business address of every DBE subcontractor, DBE vendor of materials and DBE trucking company, regardless of tier. The records shall show the date of payment and the total dollar figure paid to all of these firms. DBE prime contractors shall also show the date of work performed by their own forces along with the corresponding dollar value of the work.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 (F) and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer. The form shall be furnished to the Engineer within 90 days from the date of contract acceptance. \$10,000 will be withheld from payment until the Form CEM-2402 (F) is submitted. The amount will be returned to the Contractor when a satisfactory Form CEM-2402 (F) is submitted.

Prior to the fifteenth of each month, the Contractor shall submit documentation to the Engineer showing the amount paid to DBE trucking companies listed in the Contractor's DBE information. This monthly documentation shall indicate the portion of the revenue paid to DBE trucking companies which is claimed toward DBE participation. The Contractor shall also obtain and submit documentation to the Engineer showing the amount paid by DBE trucking companies to all firms, including owner-operators, for the leasing of trucks. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement. The records must confirm that the amount of credit claimed toward DBE participation conforms with Section 2-1.02, "Disadvantaged Business Enterprise," of these special provisions.

The Contractor shall also obtain and submit documentation to the Engineer showing the truck number, owner's name, California Highway Patrol CA number, and if applicable, the DBE certification number of the owner of the truck for all trucks used during that month for which DBE participation will be claimed. This documentation shall be submitted on Form CEM-2404 (F).

5-1.083 DBE CERTIFICATION STATUS

If a DBE subcontractor is decertified during the life of the project, the decertified subcontractor shall notify the Contractor in writing with the date of decertification. If a subcontractor becomes a certified DBE during the life of the project, the subcontractor shall notify the Contractor in writing with the date of certification. The Contractor shall furnish the written documentation to the Engineer.

Upon completion of the contract, Form CEM-2403 (F) indicating the DBE's existing certification status shall be signed and certified correct by the Contractor. The certified form shall be furnished to the Engineer within 90 days from the date of contract acceptance.

5-1.086 PERFORMANCE OF DBE SUBCONTRACTORS AND SUPPLIERS

The DBEs listed by the Contractor in response to the provisions in Section 2-1.02B, "Submission of DBE Information," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to use other forces or sources of materials may be requested for the following reasons:

- A. The listed DBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when such written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of such subcontractor's or supplier's written bid, is presented by the Contractor.
- B. The listed DBE becomes bankrupt or insolvent.
- C. The listed DBE fails or refuses to perform the subcontract or furnish the listed materials.
- D. The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DBE subcontractor fails or refuses to meet the bond requirements of the Contractor.
- E. The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial conformance with the plans and specifications, or the subcontractor is substantially delaying or disrupting the progress of the work.
- F. It would be in the best interest of the State.

The Contractor shall not be entitled to any payment for such work or material unless it is performed or supplied by the listed DBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

5-1.09 SUBCONTRACTING

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, and Section 2, "Proposal Requirements and Conditions," and Section 3, "Award and Execution of Contract," of these special provisions.

Pursuant to the provisions of Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

<http://www.dir.ca.gov/DLSE/Debar.html>.

The provisions in the third paragraph of Section 8-1.01, "Subcontracting," of the Standard Specifications, that the Contractor shall perform with the Contractor's own organization contract work amounting to not less than 50 percent of the original contract price, is not changed by the Federal Aid requirement specified under "Required Contract Provisions Federal-Aid Construction Contracts" in Section 14 of these special provisions that the Contractor perform not less than 30 percent of the original contract work with the Contractor's own organization.

Each subcontract and any lower tier subcontract that may in turn be made shall include the "Required Contract Provisions Federal-Aid Construction Contracts" in Section 14 of these special provisions. This requirement shall be enforced as follows:

- A. Noncompliance shall be corrected. Payment for subcontracted work involved will be withheld from progress payments due, or to become due, until correction is made. Failure to comply may result in termination of the contract.

In conformance with the Federal DBE regulations Sections 26.53(f)(1) and 26.53(f)(2) Part 26, Title 49 CFR:

- A. The Contractor shall not terminate for convenience a DBE subcontractor listed in response to Section 2-1.02B, "Submission of DBE Information," and then perform that work with its own forces, or those of an affiliate without the written consent of the Department, and
- B. If a DBE subcontractor is terminated or fails to complete its work for any reason, the Contractor will be required to make good faith efforts to substitute another DBE subcontractor for the original DBE subcontractor, to the extent needed to meet the contract goal.

The requirement in Section 2-1.02, "Disadvantaged Business Enterprise (DBE)," of these special provisions that DBEs must be certified on the date bids are opened does not apply to DBE substitutions after award of the contract.

5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code and Section 7108.5 of the Business and Professions Code concerning prompt payment to subcontractors.

5-1.102 PROMPT PAYMENT OF WITHHELD FUNDS TO SUBCONTRACTORS

The Contractor shall return all moneys withheld in retention from the subcontractor within 30 days after receiving payment for work satisfactorily completed, even if the other contract work is not completed and has not been accepted in conformance with Section 7-1.17, "Acceptance of Contract," of the Standard Specifications. This requirement shall not be construed to limit or impair any contractual, administrative, or judicial remedies otherwise available to the Contractor or subcontractor in the event of a dispute involving late payment or nonpayment by the Contractor or deficient subcontract performance or noncompliance by a subcontractor.

5-1.11 PARTNERING

The State will promote the formation of a "Partnering" relationship with the Contractor in order to effectively complete the contract to the benefit of both parties. The purpose of this relationship is to maintain a cooperative communication and to mutually resolve conflicts at the lowest responsible management level.

The Contractor may request the formation of a "Partnering" relationship by submitting a request in writing to the Engineer after approval of the contract. If the Contractor's request for "Partnering" is approved by the Engineer, scheduling of a "Partnering Workshop," selecting the "Partnering" facilitator and workshop site, and other administrative details shall be as agreed to by both parties. If agreed to by the parties, additional "Partnering Workshops" will be conducted as needed throughout the life of the contract.

The costs involved in providing the "Partnering Workshop" facilitator and workshop site will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost in providing the "Partnering Workshop" facilitator and workshop site in conformance with the provisions in Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor one-half of that cost, except no markups will be allowed.

All other costs associated with "Partnering Workshops" will be borne separately by the party incurring the costs, such as wages and travel expenses, and no additional compensation will be allowed therefor.

The establishment of a "Partnering" relationship will not change or modify the terms and conditions of the contract and will not relieve either party of the legal requirements of the contract.

5-1.114 VALUE ANALYSIS

The Contractor may submit to the Engineer, in writing, a request for a "Value Analysis" workshop. The purpose for having a workshop is to identify value enhancing opportunities and to consider modifications to the plans and specifications that will reduce either the total cost, time of construction or traffic congestion, without impairing, in any manner, the essential functions or characteristics of the project including, but not limited to, service life, economy of operation, ease of maintenance, benefits to the travelling public, desired appearance, or design and safety standards.

To maximize the potential benefits of a workshop, the request should be submitted to the Engineer early in the project after approval of the contract. If the Contractor's request for a "Value Analysis" workshop is approved by the Engineer, scheduling of a workshop, selecting the facilitator and workshop site, and other administrative details shall be determined cooperatively by the Contractor and the Engineer.

The workshop shall be conducted in conformance with the methodology described in the Department's "Value Analysis Team Guide" available at the Department's web site at:

<http://www.dot.ca.gov/hq/oppd/value/>

The facilitator shall be a Certified Value Specialist (CVS) as recognized by the Society of American Value Engineers (SAVE) International, which may be contacted as follows:

SAVE International, 60 Revere Drive, Northbrook, IL 60062
Telephone 1-847-480-1730, FAX 1-847-480-9282

The Contractor may submit recommendations resulting from a "Value Analysis" workshop for approval by the Engineer as cost reduction incentive proposals in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

The costs involved in providing the "Value Analysis" facilitator and workshop site will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost in providing the "Value Analysis" facilitator and workshop site in conformance with the provisions in Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor one-half of that cost, except no markups will be allowed.

All other costs associated with the "Value Analysis" workshop will be borne separately by the party incurring the costs, such as wages and travel expenses, and no additional compensation will be allowed therefor.

5-1.12 FORCE ACCOUNT PAYMENT

The second, third and fourth paragraphs of Section 9-1.03A, "Work Performed by Contractor," in the Standard Specifications, shall not apply.

Attention is directed to "Overhead" of these special provisions.

To the total of the direct costs for work performed on a force account basis, computed as provided in Sections 9-1.03A(1), "Labor," 9-1.03A(2), "Materials," and 9-1.03A(3), "Equipment Rental," of the Standard Specifications, there will be added the following markups:

Cost	Percent Markup
Labor	28
Materials	10
Equipment Rental	10

The above markups shall be applied to all work performed on a force account basis, regardless of whether the work revises the current contract completion date.

The above markups, together with payments made for time-related overhead pursuant to "Overhead" of these special provisions, shall constitute full compensation for all overhead costs for work performed on a force account basis. These overhead costs shall be deemed to include all items of expense not specifically designated as cost or equipment rental in conformance with the provisions in Sections 9-1.03A(1), "Labor," 9-1.03A(2), "Materials," and 9-1.03A(3), "Equipment Rental," of the Standard Specifications. The total payment made as provided above and in the first paragraph of Section 9-1.03A, "Work Performed by Contractor," of the Standard Specifications shall be deemed to be the actual cost of the work performed on a force account basis, and shall constitute full compensation therefor. Full compensation for all overhead costs for work performed on a force account basis, and for which no adjustment is made to the quantity of time-related overhead pursuant to "Overhead" of these special provisions, shall be considered as included in the markups specified above, and no additional compensation will be allowed therefor.

When extra work to be paid for on a force account basis is performed by a subcontractor, approved in conformance with the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, an additional markup of 7 percent will be added to the total cost of that extra work including all markups specified in this section "Force Account Payment". The additional 7 percent markup shall reimburse the Contractor for additional administrative costs, and no other additional payment will be made by reason of performance of the extra work by a subcontractor.

5-1.13 CLAIMS SUBMITTAL

Claims submittal may be made on work completed, except for plant establishment work, upon receiving relief from maintenance and responsibility for the completed work in lieu of acceptance by the Director as specified in Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. Claims submitted upon granting of relief from maintenance and responsibility will be processed in conformance with the provisions in Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications and these special provisions.

Upon the request of the Contractor, relief from maintenance and responsibility for work completed in conformance with the requirements of the contract and to the satisfaction of the Engineer may be granted in conformance with the provisions in Section 7-1.15, "Relief From Maintenance and Responsibility," of the Standard Specifications. Within 90 days of granting relief from maintenance and responsibility, the Engineer will issue to the Contractor, in writing, a final progress pay estimate showing the completed items of work. Within 30 days after receiving the final progress pay estimate, the Contractor may submit to the Engineer a written statement of the claims arising under the contract exclusive of plant establishment work. No claim arising from work for which relief of maintenance and responsibility were granted will be considered unless it was included in the written statement of claims.

The proposed final estimate for the contract will be submitted to the Contractor after acceptance of the work, including plant establishment. After submittal of the proposed final estimate, no claim will be considered except for those arising from plant establishment work or additional work ordered by the Engineer during the plant establishment period of the contract.

The process for resolution of the contract claims, including plant establishment work, by arbitration shall not begin until acceptance of the work by the Engineer and shall be in conformance with the provisions in Section 9-1.10, "Arbitration," of the Standard Specifications.

5-1.14 COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS

The provisions of this section shall apply only to the following contract item:

ITEM CODE	ITEM
390152	ASPHALT CONCRETE

The compensation payable for asphalt concrete will be increased or decreased in conformance with the provisions of this section for paving asphalt price fluctuations exceeding 5 percent (Iu/Ib is greater than 1.05 or less than 0.95) which occur during performance of the work.

The adjustment in compensation will be determined in conformance with the following formulae when the item of asphalt concrete is included in a monthly estimate:

- A. Total monthly adjustment = AQ
- B. For an increase in paving asphalt price index exceeding 5 percent:

$$A = 0.90 (1.1023) (Iu/Ib - 1.05) Ib$$

- C. For a decrease in paving asphalt price index exceeding 5 percent:

$$A = 0.90 (1.1023) (Iu/Ib - 0.95) Ib$$

- D. Where:

- A = Adjustment in dollars per tonne of paving asphalt used to produce asphalt concrete rounded to the nearest \$0.01.
- Iu = The California Statewide Paving Asphalt Price Index which is in effect on the first business day of the month within the pay period in which the quantity subject to adjustment was included in the estimate.
- Ib = The California Statewide Paving Asphalt Price Index for the month in which the bid opening for the project occurred.
- Q = Quantity in tonnes of paving asphalt that was used in producing the quantity of asphalt concrete shown under "This Estimate" on the monthly estimate using the amount of asphalt determined by the Engineer.

The adjustment in compensation will also be subject to the following:

- A. The compensation adjustments provided herein will be shown separately on payment estimates. The Contractor shall be liable to the State for decreased compensation adjustments and the Department may deduct the amount thereof from moneys due or that may become due the Contractor.
- B. Compensation adjustments made under this section will be taken into account in making adjustments in conformance with the provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.
- C. The total price adjustment for price index increases of paving asphalt on this project shall not exceed \$68,000.
- D. In the event of an overrun of contract time, adjustment in compensation for paving asphalt included in estimates during the overrun period will be determined using the California Statewide Paving Asphalt Price Index in effect on the first business day of the month within the pay period in which the overrun began.

The California Statewide Paving Asphalt Price Index is determined each month on the first business day of the month by the Department using the median of posted prices in effect as posted by Chevron, Mobil, and Unocal for the Buena Vista, Huntington Beach, Kern River, Long Beach, Midway Sunset, and Wilmington fields.

In the event that the companies discontinue posting their prices for a field, the Department will determine an index from the remaining posted prices. The Department reserves the right to include in the index determination the posted prices of additional fields.

5-1.15 AREAS FOR CONTRACTOR'S USE

Attention is directed to the provisions in Section 7-1.19, "Rights in Land and Improvements," of the Standard Specifications and these special provisions.

The highway right of way shall be used only for purposes that are necessary to perform the required work. The Contractor shall not occupy the right of way, or allow others to occupy the right of way, for purposes which are not necessary to perform the required work.

No State-owned parcels adjacent to the right of way are available for the exclusive use of the Contractor within the contract limits. The Contractor shall secure, at the Contractor's own expense, areas required for plant sites, storage of equipment or materials, or for other purposes.

No area is available within the contract limits for the exclusive use of the Contractor. However, temporary storage of equipment and materials on State property may be arranged with the Engineer, subject to the prior demands of State maintenance forces and to other contract requirements. Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk, and the State shall not be held liable for damage to or loss of materials or equipment located within such areas.

5-1.16 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount set forth for the contract items of work hereinafter listed shall be deemed to be the maximum value of the contract item of work which will be recognized for progress payment purposes:

- A. Clearing and Grubbing \$45,000
- B. Progress Schedule (Critical Path Method) \$15,000

After acceptance of the contract pursuant to the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, payable for a contract item of work in excess of the maximum value for progress payment purposes hereinabove listed for the item, will be included for payment in the first estimate made after acceptance of the contract.

In determining the partial payments to be made to the Contractor, only the following listed materials will be considered for inclusion in the payment as materials furnished but not incorporated in the work:

- A. Bar Reinforcing Steel
- B. Earth Retaining Structure
- C. Pipe (Irrigation Systems)
- D. Piling
- E. Joint Seals

- F. Culvert Pipe and Appurtenances
- G. Overside Drains and Appurtenances
- H. Railings and Appurtenances
- I. Crash Cushions
- J. Lighting fixtures
- K. Signal and lighting standards
- L. Luminaires
- M. Signal heads and mounting brackets

5-1.17 SOUND CONTROL REQUIREMENTS

Sound control shall conform to the provisions in Section 7-1.01I, "Sound Control Requirements," of the Standard Specifications and these special provisions.

The noise level from the Contractor's operations, between the hours of 9:00 p.m. and 6:00 a.m., shall not exceed 86 dBA at a distance of 15 m. This requirement shall not relieve the Contractor from responsibility for complying with local ordinances regulating noise level.

The noise level requirement shall apply to the equipment on the job or related to the job, including but not limited to trucks, transit mixers or transient equipment that may or may not be owned by the Contractor. The use of loud sound signals shall be avoided in favor of light warnings except those required by safety laws for the protection of personnel.

Full compensation for conforming to the requirements of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

5-1.18 RELATIONS WITH ARMY CORP OF ENGINEERS

A portion of this project is located within the jurisdiction of the Army Corp of Engineers. This project is under the requirements of Army Corp of Engineers Nationwide Permits 14 and 33. The Contractor shall be fully informed of the requirements of these permits as well as rules, regulations, and conditions that may govern the Contractor's operations in these areas and shall conduct the work accordingly.

Copies of the permits may be obtained at the Department of Transportation, Plans and Bid Documents Section, MS 26, 1120 N Street, Room 200, Sacramento, CA 95814, Telephone 916-654-4490, and are available for inspection at the office of the District Director of Transportation at 50 Higuera Street, San Luis Obispo, CA 93401.

Attention is directed to Sections 7-1.01, "Laws to be Observed," 7-1.01G, "Water Pollution," and 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

Modifications to the permits between the Department of Transportation and the Army Corp of Engineers which are proposed by the Contractor shall be submitted in writing to the Engineer for transmittal to the Army Corp of Engineers for their consideration.

When the Contractor is notified by the Engineer that a modification to the permits is under consideration, no work shall be performed which is inconsistent with the original agreement or proposed modification until the Departments take action on the proposed modifications. Compensation for delay will be determined in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The provisions of this section shall be made a part of every subcontract executed pursuant to this contract.

Modifications to the Army Corp of Engineers' permits will be fully binding on the Contractor. The provisions of this section shall be made a part of every subcontract executed pursuant to this contract.

5-1.19 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD

The location of the Routes 101/156 interchange improvement and concrete box culvert replacement is within an area controlled by the Regional Water Quality Control Board. Regional Water Quality Control Board Letter of Certification has been issued covering work to be performed under this contract. The Contractor shall be fully informed of rules, regulations, and conditions that may govern the Contractor's operations in the areas and shall conduct the work accordingly.

Copies of the Letter of Certification may be obtained at the Department of Transportation, Plans and Bid Documents Section, MS 26, 1120 N Street, Room 200, Sacramento, CA 95814, Telephone 916-654-4490, and are available for inspection at the office of the District Director of Transportation at 50 Higuera Street, San Luis Obispo, CA 93401.

Attention is directed to Section 7-1.11, "Preservation of Property," and Section 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

Changes in the conditions of the Letter of Certification proposed by the Contractor shall be submitted to the Engineer for transmittal to the Regional Water Quality Control Board for their approval. Changes shall not be implemented until approved in writing by the Regional Water Quality Control Board.

Attention is directed to Section 8-1.06, "Time of Completion," of the Standard Specifications. Days when the Contractor's operations are restricted by the requirements of this section shall not be considered to be nonworking days whether or not the controlling operation is delayed.

5-1.20 RELATIONS WITH CALIFORNIA DEPARTMENT OF FISH AND GAME

A portion of this project is located within the jurisdiction of the California Department of Fish and Game. An agreement regarding a stream or lake has been entered into by the Department of Transportation and the Department of Fish and Game. The Contractor shall be fully informed of the requirements of this agreement as well as rules, regulations, and conditions that may govern the Contractor's operations in these areas and shall conduct the work accordingly.

Copies of the agreement may be obtained at the Department of Transportation, Plans and Bid Documents Section, MS 26, 1120 N Street, Room 200, Sacramento, CA 95814, Telephone 916-654-4490, and are available for inspection at the office of the District Director of Transportation at 50 Higuera Street, San Luis Obispo, CA 93401.

It is unlawful for any person to divert, obstruct or change the natural flow of the bed, channel or bank of a stream, river or lake without first notifying the Department of Fish and Game, unless the project or activity is noticed and constructed in conformance with conditions imposed under Fish and Game Code Section 1601.

Attention is directed to Sections 7-1.01, "Laws to be Observed," 7-1.01G, "Water Pollution," and 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

Modifications to the agreement between the Department of Transportation and the Department of Fish and Game which are proposed by the Contractor shall be submitted in writing to the Engineer for transmittal to the Department of Fish and Game for their consideration.

When the Contractor is notified by the Engineer that a modification to the agreement is under consideration, no work shall be performed which is inconsistent with the original agreement or proposed modification until the Departments take action on the proposed modifications. Compensation for delay will be determined in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The provisions of this section shall be made a part of every subcontract executed pursuant to this contract.

Modifications to any agreement between the Department of Transportation and the Department of Fish and Game will be fully binding on the Contractor. The provisions of this section shall be made a part of every subcontract executed pursuant to this contract.

5-1.21 ENVIRONMENTALLY SENSITIVE AREA (ESA)

The Contractor's attention is directed to the areas designated on the plans as "Environmentally Sensitive Areas" and to State and Federal regulations which may pertain to such areas. These areas are protected. The Contractor shall take measures to ensure that his forces do not disturb these areas, including giving written notice to his employees and subcontractors, except as necessary to construct highway planting and irrigation facilities.

Attention is directed to "Temporary Fence (Type ESA)" of these special provision regarding placement of temporary fence.

If archeological materials or human remains are encountered anywhere within the entire project limits during project construction the Contractor shall immediately notify the Engineer. Work shall be stopped in the area of discovery until the site is evaluated by the Department of Transportation Archaeologist. If, in the opinion of the Engineer, the Contractor's operations are delayed or interfered with by reason of such archaeological discovery, the State will compensate the Contractor for such delays to the extent provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Full compensation for conforming to the provisions in this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

5-1.22 FIRE PLAN

The Contractor shall cooperate with local fire prevention authorities in eliminating hazardous fire conditions and shall implement the following fire plan under the direction of the Engineer:

A. The Contractor shall be responsible for:

1. obtaining the phone number of the nearest fire suppression agency and providing this phone number to the Engineer as a first order of work,
2. immediately reporting to the nearest fire suppression agency fires occurring within the limits of the project,
3. preventing project personnel from setting open fires not part of the work, unless the Engineer determines that the fire hazard is negligible,
4. preventing the escape of fires caused directly or indirectly as a result of project operations and extinguishing these fires.

- B. Except for motor trucks, truck tractors, buses and passenger vehicles, the Contractor shall equip all hydro-carbon fueled engines, both stationary and mobile, including motorcycles, with spark arresters that meet United States Forest Service Standards as specified in the Forest Service Spark Arrester Guide and shall maintain the spark arresters in good operating condition. Spark arresters are not required by the State Department of Forestry or the United States Forest Service on equipment powered by properly maintained exhaust-driven turbo-charged engines or when equipped with scrubbers with properly maintained water levels. The Forest Service Spark Arrester Guide is available at the District Offices of the Department of Transportation.
- C. Toilets shall have a metal receptacle, at least 150 mm in diameter by 200 mm deep, half-filled with sand for ashes and discarded smokes, and within easy reach of anyone utilizing the facility.
- D. Equipment service areas, parking areas and gas and oil storage areas shall be located so that there is no flammable material within a radius of at least 15 m of these areas. Small mobile or stationary engine sites shall be cleared of flammable material for a radius of at least 4.6 m from the engine.
- E. The areas to be cleared and grubbed shall be cleared, and kept clear of, flammable material such as dry grass, weeds, brush, downed trees, oily rags and waste, paper, cartons, and plastic waste. The first order of work shall be to clear a fire break at the outer limits of the areas to be cleared and grubbed.
- F. The Contractor shall furnish each piece of equipment with the following:
 - 1. one shovel and one fully charged fire extinguisher UL rated at 4 B:C or more on each truck, personnel vehicle tractor, grader or other heavy equipment,
 - 2. one shovel and one back-pack 20-L water-filled tank with pump for each welder,
 - 3. one shovel or one chemical pressurized fire extinguisher, fully charged, for each gasoline-powered tool, including but not limited to chain saws, soil augers, rock drills, etc. The required fire tools shall, at no time, be farther than 8 m from the point of operation of the power tool. Fire extinguishers shall be of the type and size required by the California Public Resource Code, Section 4431, and the California Administrative Code, Title 14, Section 1234,
 - 4. shovels shall be size "O" or larger and shall be not less than 1.2 m in length.
- G. The Contractor shall furnish a pickup truck and driver that will be available for fire control during working hours and as specified herein.
 - 1. The truck shall be equipped with 2 shovels, and 2 back-pack 20-L water-filled tanks with pumps, or other fire tools substituted on a one to one basis at the option of the Contractor and approved by the Engineer.
 - 2. In addition to being available at the site of the work, the truck and operator shall patrol the area of construction for not less than one-half hour after the shutdown of the work.

Full compensation for conforming to the provisions herein shall be considered as included in the prices paid for the various contract items of work and no separate payment will be made therefor.

SECTION 6. (BLANK)
SECTION 7. (BLANK)
SECTION 8. MATERIALS
SECTION 8-1. MISCELLANEOUS

8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the United States Standard Measures which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

- A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.
- B. Before other non-metric materials and products will be considered for use, the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.
- C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details, the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The plans and working drawings shall be submitted at least 7 days before the Contractor intends to begin the work involved.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS
 ASTM Designation: A 325M

METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT

ASTM Designation: A 82

METRIC SIZE SHOWN ON THE PLANS mm ²	SIZE TO BE SUBSTITUTED inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

SUBSTITUTION TABLE FOR BAR REINFORCEMENT

METRIC BAR DESIGNATION NUMBER ¹ SHOWN ON THE PLANS	BAR DESIGNATION NUMBER ² TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

¹Bar designation numbers approximate the number of millimeters of the nominal diameter of the bars.

²Bar numbers are based on the number of eighths of an inch included in the nominal diameter of the bars.

No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

SUBSTITUTION TABLE FOR SIZES OF:

(1) STEEL FASTENERS FOR GENERAL APPLICATIONS (ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55), and

(2) HIGH STRENGTH STEEL FASTENERS (ASTM Designation: A 325 or A 449)

METRIC SIZE SHOWN ON THE PLANS mm	SIZE TO BE SUBSTITUTED inch
6 or 6.35	1/4
8 or 7.94	5/16
10 or 9.52	3/8
11 or 11.11	7/16
13 or 12.70	1/2
14 or 14.29	9/16
16 or 15.88	5/8
19 or 19.05	3/4
22 or 22.22	7/8
24, 25, or 25.40	1
29 or 28.58	1-1/8
32 or 31.75	1-1/4
35 or 34.93	1-3/8
38 or 38.10	1-1/2
44 or 44.45	1-3/4
51 or 50.80	2
57 or 57.15	2-1/4
64 or 63.50	2-1/2
70 or 69.85	2-3/4
76 or 76.20	3
83 or 82.55	3-1/4
89 or 88.90	3-1/2
95 or 95.25	3-3/4
102 or 101.60	4

SUBSTITUTION TABLE FOR NOMINAL THICKNESS OF SHEET METAL

UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS (GALVANIZED)	
METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch	METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269	-----	-----
0.61	0.0239	-----	-----
0.53	0.0209	-----	-----
0.45	0.0179	-----	-----
0.42	0.0164	-----	-----
0.38	0.0149	-----	-----

SUBSTITUTION TABLE FOR WIRE

METRIC THICKNESS SHOWN ON THE PLANS mm	WIRE THICKNESS TO BE SUBSTITUTED inch	GAGE NO.
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

SUBSTITUTION TABLE FOR PIPE PILES

METRIC SIZE SHOWN ON THE PLANS mm x mm	SIZE TO BE SUBSTITUTED inch x inch
PP 360 x 4.55	NPS 14 x 0.179
PP 360 x 6.35	NPS 14 x 0.250
PP 360 x 9.53	NPS 14 x 0.375
PP 360 x 11.12	NPS 14 x 0.438
PP 406 x 12.70	NPS 16 x 0.500
PP 460 x T	NPS 18 x T"
PP 508 x T	NPS 20 x T"
PP 559 x T	NPS 22 x T"
PP 610 x T	NPS 24 x T"
PP 660 x T	NPS 26 x T"
PP 711 x T	NPS 28 x T"
PP 762 x T	NPS 30 x T"
PP 813 x T	NPS 32 x T"
PP 864 x T	NPS 34 x T"
PP 914 x T	NPS 36 x T"
PP 965 x T	NPS 38 x T"
PP 1016 x T	NPS 40 x T"
PP 1067 x T	NPS 42 x T"
PP 1118 x T	NPS 44 x T"
PP 1219 x T	NPS 48 x T"
PP 1524 x T	NPS 60 x T"

The thickness in millimeters (T) represents an exact conversion of the thickness in inches (T").

SUBSTITUTION TABLE FOR STRUCTURAL TIMBER AND LUMBER

METRIC MINIMUM DRESSED DRY, SHOWN ON THE PLANS mm x mm	METRIC MINIMUM DRESSED GREEN, SHOWN ON THE PLANS mm x mm	NOMINAL SIZE TO BE SUBSTITUTED inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

SUBSTITUTION TABLE FOR NAILS AND SPIKES

METRIC COMMON NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC BOX NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC SPIKE, SHOWN ON THE PLANS Length, mm Diameter, mm	SIZE TO BE SUBSTITUTED Penny-weight
50.80 2.87	50.80 2.51	————	6d
63.50 3.33	63.50 2.87	————	8d
76.20 3.76	76.20 3.25	76.20 4.88	10d
82.55 3.76	82.55 3.25	82.55 4.88	12d
88.90 4.11	88.90 3.43	88.90 5.26	16d
101.60 4.88	101.60 3.76	101.60 5.72	20d
114.30 5.26	114.30 3.76	114.30 6.20	30d
127.00 5.72	127.00 4.11	127.00 6.68	40d
————	————	139.70 7.19	50d
————	————	152.40 7.19	60d

SUBSTITUTION TABLE FOR IRRIGATION
COMPONENTS

METRIC WATER METERS, TRUCK LOADING STANDPIPES, VALVES, BACKFLOW PREVENTERS, FLOW SENSORS, WYE STRAINERS, FILTER ASSEMBLY UNITS, PIPE SUPPLY LINES, AND PIPE IRRIGATION SUPPLY LINES SHOWN ON THE PLANS DIAMETER NOMINAL (DN) mm	NOMINAL SIZE TO BE SUBSTITUTED inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

Unless otherwise specified, substitutions of United States Standard Measures standard structural shapes corresponding to the metric designations shown on the plans and in conformance with the requirements in ASTM Designation: A 6/A 6M, Annex 2, will be allowed.

8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS

The Department maintains the following list of Prequalified and Tested Signing and Delineation Materials. The Engineer shall not be precluded from sampling and testing products on the list of Prequalified and Tested Signing and Delineation Materials.

The manufacturer of products on the list of Prequalified and Tested Signing and Delineation Materials shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

For those categories of materials included in the list of Prequalified and Tested Signing and Delineation Materials, only those products shown within the listing may be used in the work. Other categories of products, not included in the list of Prequalified and Tested Signing and Delineation Materials, may be used in the work provided they conform to the requirements of the Standard Specifications.

Materials and products may be added to the list of Prequalified and Tested Signing and Delineation Materials if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

PAVEMENT MARKERS, PERMANENT TYPE

Retroreflective

- A. Apex, Model 921 (100 mm x 100 mm)
- B. Ray-O-Lite, Models SS (100 mm x 100 mm), RS (100 mm x 100 mm) and AA (100 mm x 100 mm)
- C. Stimsonite, Models 88 (100 mm x 100 mm), 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- D. 3M Series 290 (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

- A. Apex, Model 921AR (100 mm x 100 mm)
- B. Ray-O-Lite "AA" ARS (100 mm x 100 mm)
- C. Stimsonite, Models 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- D. 3M Series 290 (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

(Used for recessed applications)

- A. Stimsonite, Model 948 (58 mm x 119 mm)
- B. Ray-O-Lite, Model 2002 (58 mm x 117 mm)
- C. Stimsonite, Model 944SB (51 mm x 100 mm)*
- D. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)*

*For use only in 114 mm wide (older) recessed slots

Non-Reflective For Use With Epoxy Adhesive, 100 mm Round

- A. Apex Universal (Ceramic)
- B. Highway Ceramics, Inc. (Ceramic)

Non-Reflective For Use With Bitumen Adhesive, 100 mm Round

- A. Alpine Products, "D-Dot" and "ANR" (ABS)
- B. Apex Universal (Ceramic)
- C. Apex Universal, Model 929 (ABS)
- D. Elgin Molded Plastics, "Empco-Lite" Model 900 (ABS)
- E. Highway Ceramics, Inc. (Ceramic)
- F. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
- G. Interstate Sales, "Diamond Back" (ABS) and (Polypropylene)
- H. Novabrite Models Adot-w (White) Adot-y (Yellow), (ABS)
- I. Road Creations, Model RCB4NR (Acrylic)
- J. Zumar Industries, "Titan TM40A" (ABS)

PAVEMENT MARKERS, TEMPORARY TYPE

Temporary Markers For Long Term Day/Night Use (6 months or less)

- A. Apex Universal, Model 924 (100 mm x 100 mm)
- B. Elgin Molded Plastics, "Empco-Lite" Model 901 (100 mm x 100 mm)
- C. Road Creations, Model R41C (100 mm x 100 mm)
- D. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

Temporary Markers For Short Term Day/Night Use (14 days or less)

(For seal coat or chip seal applications, clear protective covers are required)

- A. Apex Universal, Model 932
- B. Davidson Plastics, Models T.O.M., T.R.P.M., and "HH" (High Heat)
- C. Hi-Way Safety, Inc., Model 1280/1281

STRIPING AND PAVEMENT MARKING MATERIAL

Permanent Traffic Striping and Pavement Marking Tape

- A. Advanced Traffic Marking, Series 300 and 400
- B. Brite-Line, Series 1000
- C. Brite-Line "DeltaLine XRP"
- D. Swarco Industries, "Director 35" (For transverse application only)
- E. Swarco Industries, "Director 60"
- F. 3M, "Stamark" Series 380 and 5730
- G. 3M, "Stamark" Series 420 (For transverse application only)

Temporary (Removable) Striping and Pavement Marking Tape (6 months or less)

- A. Advanced Traffic Marking, Series 200
- B. Brite-Line, Series 100
- C. P.B. Laminations, Aztec, Grade 102
- D. Swarco Industries, "Director-2"
- E. 3M, "Stamark," Series 620
- F. 3M Series A145 Removable Black Line Mask
(Black Tape: For use only on Asphalt Concrete Surfaces)
- G. Advanced Traffic Marking Black "Hide-A-Line"
(Black Tape: For use only on Asphalt Concrete Surfaces)
- H. Brite-Line "BTR" Black Removable Tape
(Black Tape: For use only on Asphalt Concrete Surfaces)

Preformed Thermoplastic (Heated in place)

- A. Flint Trading, "Premark" and "Premark 20/20 Flex"
- B. Pavemark, "Hotape"

Removable Traffic Paint

- A. Belpro, Series 250/252 and No. 93 Remover

Ceramic Surfacing Laminate, 150 mm x 150 mm

- A. Safeline Industries/Highway Ceramics, Inc.

CLASS 1 DELINEATORS

One Piece Driveable Flexible Type, 1700 mm

- A. Carsonite, Curve-Flex CFRM-400
- B. Carsonite, Roadmarker CRM-375
- C. Davidson Plastics, "Flexi-Guide Models 400 and 566"
- D. FlexStake, Model 654 TM
- E. GreenLine Models HWD1-66 and CGD1-66
- F. J. Miller Industries, Model JMI-375 (with soil anchor)

Special Use Flexible Type, 1700 mm

- A. Carsonite, "Survivor" (with 450 mm U-Channel base)
- B. FlexStake, Model 604
- C. GreenLine Models HWD and CGD (with 450 mm U-Channel base)
- D. Safe-Hit with 200 mm pavement anchor (SH248-GP1)
- E. Safe-Hit with 380 mm soil anchor (SH248-GP2) and with 450 mm soil anchor (SH248-GP3)

Surface Mount Flexible Type, 1200 mm

- A. Bent Manufacturing Company, Masterflex Model MF-180EX-48
- B. Carsonite, "Super Duck II"
- C. FlexStake, Surface Mount, Models 704 and 754 TM

CHANNELIZERS

Surface Mount Type, 900 mm

- A. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
- B. Carsonite, "Super Duck" (Flat SDF-436, Round SDR-336)
- C. Carsonite, "Super Duck II" Model SDCF203601MB "The Channelizer"
- D. Davidson Plastics, Flex-Guide Models FG300LD and FG300UR
- E. FlexStake, Surface Mount, Models 703 and 753 TM
- F. GreenLine, Model SMD-36
- G. Hi-Way Safety, Inc. "Channel Guide Channelizer" Model CGC36
- H. The Line Connection, "Dura-Post" Model DP36-3 (Permanent)
- I. The Line Connection, "Dura-Post" Model DP36-3C (Temporary)
- J. Repo, Models 300 and 400
- K. Safe-Hit, Guide Post, Model SH236SMA

CONICAL DELINEATORS, 1070 mm

(For 700 mm Traffic Cones, see Standard Specifications)

- A. Bent Manufacturing Company "T-Top"
- B. Plastic Safety Systems "Navigator-42"
- C. Roadmaker Company "Stacker"
- D. Traffix Devices "Grabber"

OBJECT MARKERS

Type "K", 450 mm

- A. Carsonite, Model SMD-615
- B. FlexStake, Model 701 KM
- C. Repo, Models 300 and 400
- D. Safe-Hit, Model SH718SMA
- E. The Line Connection, Model DP21-4K

Type "K-4" / "Q" Object Markers, 600 mm

- A. Bent Manufacturing "Masterflex" Model MF-360-24
- B. Carsonite, Super Duck II
- C. FlexStake, Model 701KM
- D. Repo, Models 300 and 400
- E. Safe-Hit, Models SH8 24SMA_WA and SH8 24GP3_WA
- F. The Line Connection, Model DP21-4Q

TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS

Impactable Type

- A. ARTUK, "FB"
- B. Davidson Plastics, Model PCBM-12
- C. Duraflex Corp., "Flexx 2020" and "Electriflexx"
- D. Hi-Way Safety, Inc., Model GMKRM100

Non-Impactable Type

- A. ARTUK, JD Series
- B. Stimsonite, Model 967 (with 83 mm Acrylic cube corner reflector)
- C. Stimsonite, Model 967LS
- D. Vega Molded Products, Models GBM and JD

THREE BEAM BARRIER MARKERS

(For use to the left of traffic)

- A. Duraflex Corp., "Railrider"
- B. Davidson Plastics, "Mini" (75 mm x 254 mm)

CONCRETE BARRIER DELINEATORS, 400 mm

(For use to the right of traffic. When mounted on top of barrier, places top of reflective element at 1200 mm)

- A. Davidson Plastics, Model PCBM T-16
- B. Safe-Hit, Model SH216RBM
- C. Sun-Lab Technology, "Safety Guide Light, Model TM," 130 mm x 130 mm x 80 mm

CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)

- A. Stinson Equipment Company "SaddleMarker"

SOUND WALL DELINEATOR

(Applied vertically. Place top of 75 mm x 300 mm reflective element at 1200 mm above roadway)

- A. Davidson Plastics, PCBM S-36
- B. Sun-Lab Technology, "Safety Guide Light, Model SM12," 130 mm x 130 mm x 80 mm

GUARD RAILING DELINEATOR

(Top of reflective element at 1200 mm above plane of roadway)

Wood Post Type, 686 mm

- A. Carsonite, Model 427
- B. Davidson Plastics FG 427 and FG 527
- C. FlexStake, Model 102 GR
- D. GreenLine GRD 27
- E. J.Miller Model JMI-375G
- F. Safe-Hit, Model SH227GRD

Steel Post Type

- A. Carsonite, Model CFGR-327 with CFGRBK300 Mounting Bracket

RETROREFLECTIVE SHEETING

Channelizers, Barrier Markers, and Delineators

- A. 3M, High Intensity
- B. Reflexite, PC-1000 Metalized Polycarbonate
- C. Reflexite, AC-1000 Acrylic
- D. Reflexite, AP-1000 Metalized Polyester
- E. Reflexite, AR-1000 Abrasion Resistant Coating
- F. Avery Dennison T-6500 Series (Formerly Stimsonite, Series 6200) (For rigid substrate devices only)

Traffic Cones, 330 mm Sleeves

- A. Reflexite SB (Polyester), Vinyl or "TR" (Semi-transparent)

Traffic Cones, 100 mm and 150 mm Sleeves

- A. 3M Series 3840
- B. Reflexite Vinyl, "TR" (Semi-transparent) or "Conformalite"

Barrels and Drums

- A. Reflexite, "Super High Intensity" or "High Impact Drum Sheeting"
- B. 3M Series 3810

Barricades: Type I, Engineer Grade

- A. American Decal, Adcolite
- B. Avery Dennison, T-1500 and T-1600
- C. 3M, Scotchlite, Series CW

Barricades: Type II, Super Engineer Grade

- A. Avery Dennison, T-2500 Series
- B. Kiwalite Type II
- C. Nikkalite 1800 Series

Signs: Type II, Super Engineer Grade

- A. Avery Dennison, T-2500 Series
- B. Kiwalite, Type II
- C. Nikkalite 1800 Series

Signs: Type III, High-Intensity Grade

- A. 3M Series 3800
- B. Nippon Carbide, Nikkalite Brand Ultralite Grade II

Signs: Type IV, High-Intensity Prismatic Grade

- A. Avery Dennison T-6500 (Formerly Stimsonite Series 6200)

Signs: Type VII, High-Intensity Prismatic Grade

- A. 3M Series 3900

Signs: Type VI, Roll-Up Signs

- A. Reflexite, Vinyl (Orange)
- B. Reflexite "SuperBright" (Fluorescent orange)
- C. Reflexite "Marathon" (Fluorescent orange)
- D. 3M Series RS34 (Orange) and RS20 (Fluorescent orange)

SPECIALTY SIGN (All Plastic)

- A. All Sign Products, STOP Sign, 750 mm

SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS

Aluminum

Fiberglass Reinforced Plastic (FRP)

- A. Sequentia, "Polyplate"
- B. Fiber-Brite

8-1.03 STATE-FURNISHED MATERIALS

Attention is directed to Section 6-1.02, "State-Furnished Materials," of the Standard Specifications and these special provisions.

The following materials will be furnished to the Contractor:

- A. Sign panels for roadside signs and overhead sign structures.
- B. Laminated wood box posts with metal caps for roadside signs.
- C. Disks for survey monuments.
- D. Lamps for vehicular traffic signal units

8-1.04 ENGINEERING FABRICS

Engineering fabrics shall conform to the provisions in Section 88, "Engineering Fabrics," of the Standard Specifications and these special provisions.

Filter fabric for this project shall be ultraviolet (UV) ray protected.

8-1.05 MISCELLANEOUS METAL

The table in the tenth paragraph of Section 75-1.02, "Miscellaneous Iron and Steel," of the Standard Specifications is amended to read:

Material	Specification
Steel bars, plates and shapes	ASTM Designation: A 36/A 36M or A 575, A 576 (AISI or M Grades 1016 through 1030 except Grade 1017)
Steel fastener components for general applications:	
Bolts and studs	ASTM Designation: A 307
Headed anchor bolts	ASTM Designation: A 307, Grade B, including S1 supplementary requirements
Nonheaded anchor bolts	ASTM Designation: A 307, Grade C, including S1 supplementary requirements and S1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements
High-strength bolts and studs, threaded rods, and nonheaded anchor bolts	ASTM Designation: A 449, Type 1
Nuts	ASTM Designation: A 563, including Appendix X1*
Washers	ASTM Designation: F 844
Components of high-strength steel fastener assemblies for use in structural steel joints:	
Bolts	ASTM Designation: A 325, Type 1
Tension control bolts	ASTM Designation: F 1852, Type 1
Nuts	ASTM Designation: A 563, including Appendix X1*
Hardened washers	ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements
Direct tension indicators	ASTM Designation: F 959, Type 325, zinc-coated
Stainless steel fasteners (Alloys 304 & 316) for general applications:	
Bolts, screws, studs, threaded rods, and nonheaded anchor bolts	ASTM Designation: F 593 or F 738M
Nuts	ASTM Designation: F 594 or F 836M
Washers	ASTM Designation: A 240/A 240M and ANSI B 18.22M
Carbon-steel castings	ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1
Malleable iron castings	ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010
Gray iron castings	ASTM Designation: A 48, Class 30B
Ductile iron castings	ASTM Designation: A 536, Grade 65-45-12
Cast iron pipe	Commercial quality
Steel pipe	Commercial quality, welded or extruded
Other parts for general applications	Commercial quality

* Zinc-coated nuts that will be tightened beyond snug or wrench tight shall be furnished with a dyed dry lubricant conforming to Supplementary Requirement S2 in ASTM Designation: A 563.

The table in the eighteenth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Stud Diameter (millimeters)	Sustained Tension Test Load (kilonewtons)
29.01-33.00	137.9
23.01-29.00	79.6
21.01-23.00	64.1
* 18.01-21.00	22.2
15.01-18.00	18.2
12.01-15.00	14.2
9.01-12.00	9.34
6.00-9.00	4.23

* Maximum stud diameter permitted for mechanical expansion anchors.

The table in the nineteenth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Stud Diameter (millimeters)	Ultimate Tensile Load (kilonewtons)
30.01-33.00	112.1
27.01-30.00	88.1
23.01-27.00	71.2
20.01-23.00	51.6
16.01-20.00	32.0
14.01-16.00	29.4
12.00-14.00	18.7

The table in the twenty-second paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Installation Torque Values, (Newton meters)

Stud Diameter (millimeters)	Shell Type Mechanical Expansion Anchors	Integral Stud Type Mechanical Expansion Anchors	Resin Capsule Anchors and Cast-in-Place Inserts
29.01-33.00	—	—	540
23.01-29.00	—	—	315
21.01-23.00	—	—	235
18.01-21.00	110	235	200
15.01-18.00	45	120	100
12.01-15.00	30	65	40
9.01-12.00	15	35	24
6.00-9.00	5	10	—

SECTION 8-2. CONCRETE

8-2.01 PORTLAND CEMENT CONCRETE

Portland cement concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

References to Section 90-2.01, "Portland Cement," of the Standard Specifications shall mean Section 90-2.01, "Cement," of the Standard Specifications.

Mineral admixture shall be combined with cement in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures," of the Standard Specifications for the concrete materials specified in Section 56-2, "Roadside Signs," of the Standard Specifications.

The requirements of Section 90-4.08, "Required Use of Mineral Admixture," of the Standard Specifications shall not apply to Section 19-3.025C, "Soil Cement Bedding," of the Standard Specifications.

The Contractor will be permitted to use Type III portland cement for concrete used in the manufacture of precast concrete members.

8-2.02 CEMENT AND WATER CONTENT

The amount of free water used in concrete for deck slabs of bridges and structure approach slabs shall not exceed 195 kg/m³, plus 20 kg for each required 100 kg of cementitious material in excess of 400 kg/m³.

SECTION 8-3. WELDING

8-3.01 WELDING

GENERAL

Flux core welding electrodes conforming to the requirements of AWS A5.20 E6XT-4 or E7XT-4 shall not be used to perform any type of welding for this project.

Wherever reference is made to the following AWS welding codes in the Standard Specifications, on the plans, or in these special provisions, the year of adoption for these codes shall be as listed:

AWS Code	Year of Adoption
D1.1	2000
D1.4	1992
D1.5	1995
D1.5 (metric only)	1996

Requirements of the AWS welding codes shall apply unless specified otherwise in the Standard Specifications, on the plans, or in these special provisions. Wherever the abbreviation AWS is used, it shall be equivalent to the abbreviations ANSI/AWS or ANSI/AASHTO/AWS.

Sections 6.1.2 through 6.1.4.3 of AWS D 1.1, Sections 7.1.1 and 7.1.2 of AWS D 1.4, and Sections 6.1.1.1 through 6.1.3.3 of AWS D 1.5 are replaced with the following:

Quality Control (QC) shall be the responsibility of the Contractor. As a minimum, the Contractor shall perform inspection and testing prior to welding, during welding, and after welding as specified in this section and additionally as necessary to ensure that materials and workmanship conform to the requirements of the contract documents.

The QC Inspector shall be the duly designated person who acts for and on behalf of the Contractor for inspection, testing, and quality related matters for all welding.

Quality Assurance (QA) is the prerogative of the Engineer. The QA Inspector is the duly designated person who acts for and on behalf of the Engineer.

Each QC Inspector shall be responsible for quality control acceptance or rejection of materials and workmanship, and shall be currently certified as an AWS Certified Welding Inspector (CWI) in conformance with the requirements in AWS QC1, "Standard and Guide for Qualification of Welding Inspectors."

The QC Inspector may be assisted by an Assistant QC Inspector provided that this individual is currently certified as an AWS Certified Associate Welding Inspector (CAWI) in conformance with the requirements in AWS QC1, "Standard and Guide for Qualification of Welding Inspectors," or has equivalent qualifications. The QC Inspector shall monitor the Assistant QC Inspector's work, and shall be responsible for signing all reports.

When the term "Inspector" is used without further qualification, it shall refer to the QC Inspector.

Section 6.14.6, "Personnel Qualification," of AWS D 1.1, Section 7.7.6, "Personnel Qualification," of AWS D 1.4, and Section 6.1.3.4, "Personnel Qualification," of AWS D 1.5 are replaced with the following:

Personnel performing nondestructive testing (NDT) shall be qualified in conformance with the requirements of the American Society for Nondestructive Testing (ASNT) Recommended Practice No. SNT-TC-1A and the Written Practice of the NDT firm. The Written Practice of the NDT firm shall meet or exceed the requirements of the ASNT Recommended Practice No. SNT-TC-1A. Only individuals who are 1) qualified for NDT Level II, or 2) Level III technicians who have been directly certified by the ASNT and are authorized to perform the work of Level II technicians, shall perform NDT, review the results, and prepare the written reports.

Section 6.5.4, "Scope of Examination," of AWS D 1.1 and Section 7.5.4 of AWS D 1.4 are replaced with the following:

The QC Inspector shall inspect and approve the joint preparation, assembly practice, welding techniques, and performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved welding procedure specification (WPS) are met.

Section 6.5.4 of AWS D 1.5 is replaced with the following:

The QC Inspector shall inspect and approve the joint preparation, assembly practice, welding techniques, and performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved WPS are met. The QC Inspector shall examine the work to make certain that it meets the requirements of Sections 3 and 9.21. The size and contour of welds shall be measured using suitable gages. Visual inspection for cracks in welds and base metal, and for other discontinuities should be aided by strong light magnifiers, or such other devices as may be helpful. Acceptance criteria different from those specified in this code may be used when approved by the Engineer.

Section 6.6.5, "Nonspecified Nondestructive Testing Other Than Visual," of AWS D 1.1, Section 6.6.5 of AWS D 1.4 and Section 6.6.5 of AWS D 1.5 shall not apply.

For any welding, the Engineer may direct the Contractor to perform NDT that is in addition to the visual inspection or NDT specified in the AWS welding codes, in the Standard Specifications, or in these special provisions. Additional NDT required by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Should any welding deficiencies be discovered by this additional NDT, the cost of the testing will not be paid for as extra work but shall be at the Contractor's expense.

Required repair work to correct welding deficiencies, whether discovered by the required visual inspection or NDT, or by additional NDT directed by the Engineer, and any associated delays or expenses caused to the Contractor by performing these repairs, shall be at the Contractor's expense.

The Engineer shall have the authority to verify the qualifications or certifications of any welder, QC Inspector, or NDT personnel to specified levels by retests or other means.

A sufficient number of QC Inspectors shall be provided to ensure continuous inspection when any welding is being performed. Continuous inspection, as a minimum, shall include (1) having QC Inspectors continually present when any welding operation is being performed, or (2) having a QC Inspector within such close proximity of all welding operations that inspections by the QC Inspector of each operation, at each welding location, shall not lapse for a period exceeding 30 minutes.

Inspection and approval of the joint preparation, assembly practice, welding techniques, and performance of each welder, welding operator, and tack welder shall be documented by the QC Inspector on a daily basis for each day that welding is performed.

When joint details that are not prequalified by the applicable AWS codes are proposed for use in the work, welders using these details shall perform a qualification test plate using the approved WPS variables and the joint detail to be used in production. The test plate shall be the maximum thickness to be used in production. The test plate shall be mechanically or radiographically tested as directed by the Engineer. Mechanical and radiographic testing and acceptance criteria shall be as specified in the applicable AWS codes.

The period of effectiveness for a welder's or welding operator's qualification shall be a maximum of 3 years for the same weld process, welding position, and weld type. A valid qualification at the beginning of work on a contract will be acceptable for the entire period of the contract, as long as the welder's work remains satisfactory.

WELDING QUALITY CONTROL

Welding quality control shall conform to the requirements in the AWS welding codes, the Standard Specifications, and these special provisions.

Unless otherwise specified, welding quality control shall apply when any work is welded in conformance with the provisions in Section 49, "Piling," Section 52, "Reinforcement," Section 55, "Steel Structures," Section 56-1, "Overhead Sign Structures," Section 75-1.035, "Bridge Joint Restrainer Units," or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

The welding of fracture critical members (FCMs) shall conform to the provisions specified in the Fracture Control Plan (FCP) and herein.

The Contractor shall designate in writing a welding Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for the quality of welding, including materials and workmanship, performed by the Contractor and subcontractors.

The QCM shall be the sole individual responsible to the Contractor for submitting, receiving, and approving all correspondence, required submittals, and reports to and from the Engineer.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

Welding inspection personnel or NDT firms to be used in the work shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project, except for the following conditions:

- A. The welding is performed at a permanent fabrication facility which is certified under the AISC Quality Certification Program, Category Cbr, Major Steel Bridges.
- B. The welding is performed at a permanent fabrication facility which is certified under the AISC Quality Certification Program, Category Sbd, Conventional Steel Building Structures. This condition shall apply only for work welded in conformance with the provisions in Section 56-1, "Overhead Sign Structures" or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

For welding performed at such certified facilities, the inspection personnel or NDT firms may be employed or compensated by the fabrication facility performing the welding.

Prior to submitting the Welding Quality Control Plan (WQCP) required herein, a pre-welding meeting between the Engineer, Contractor, and any entity performing welding for this project, shall be held to discuss the requirements for the WQCP.

Except for work that is welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, prior to performing any welding, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate WQCP for each item of work for which welding is to be performed.

Prior to furnishing materials welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate WQCP for each fabrication facility supplying these materials or proof of previous Engineer approval of a WQCP for such a facility no more than one year prior to the delivery of materials for inspection.

As a minimum, each WQCP shall include the following:

- A. The name of the welding firm and any required NDT firms;
- B. A manual prepared by the NDT firm that shall include equipment, testing procedures, code of safe practices, the Written Practice of the NDT firm, and the names, qualifications, and documentation of certifications for all personnel to be used;
- C. The name of the QCM and the names, qualifications, and documentation of certifications for all QC Inspectors and Assistant QC Inspectors to be used;
- D. An organizational chart showing all QC personnel and their assigned QC responsibilities;
- E. The methods and frequencies for performing all required quality control procedures, including QC inspection forms to be used, as required by the specifications including:
 - 1. all visual inspections;
 - 2. all NDT including radiographic geometry, penetrometer and shim selection, film quality, film processing, radiograph identification and marking system, and film interpretation and reports; and

3. calibration procedures and calibration frequency for all NDT equipment;
- F. A system for the identification and tracking of all welds, NDT, and any required repairs, and a procedure for the reinspection of repaired welds. The system shall have provisions for 1) permanently identifying each weld and the person who performed the weld, 2) placing all identification and tracking information on each radiograph, 3) a method of reporting nonconforming welds to the Engineer, and 4) a method of documentation of repairs and reinspection of nonconforming welds;
 - G. Standard procedures for performing noncritical repair welds. Noncritical repair welds are defined as welds to deposit additional weld beads or layers to compensate for insufficient weld size and to fill limited excavations that were performed to remove unacceptable edge or surface discontinuities, rollover or undercut. The depth of these excavations shall not exceed 65 percent of the specified weld size;
 - H. The WPS, including documentation of all supporting Procedure Qualification Record (PQR) tests performed, and the name of the testing laboratory who performed the tests, to verify the acceptability of the WPS. The submitted WPS shall be within the allowable period of effectiveness;
 - I. Documentation of all certifications for welders for each weld process and position that will be used. Certifications shall list the electrodes used, test position, base metal and thickness, tests performed, and the witnessing authority. All certifications shall be within the allowable period of effectiveness;
 - J. One copy each of all AWS welding codes and the FCP which are applicable to the welding to be performed. These codes and the FCP shall become the permanent property of the Department; and
 - K. Forms to be used for Certificates of Compliance, daily production logs, and daily reports.

The Engineer shall have 10 working days to review the WQCP submittal after a complete plan has been received. Except for work that is welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, no welding shall be performed until the WQCP is approved in writing by the Engineer. No materials welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, shall be incorporated into the work until the WQCP is approved in writing by the Engineer. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the WQCP, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

An amended WQCP or addendum shall be submitted to, and approved in writing by the Engineer, for proposed revisions to the approved WQCP. An amended WQCP or addendum will be required for revisions to the WQCP, including but not limited to a revised WPS, additional welders, changes in NDT firms or procedures, QC, or NDT personnel, or updated systems for tracking and identifying welds. The Engineer shall have 3 working days to complete the review of the amended WQCP or addendum. Work that is affected by any of the proposed revisions shall not be performed until the amended WQCP or addendum has been approved. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the amended WQCP or addendum, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

After final approval of the WQCP, amended WQCP, or addendum, the Contractor shall submit 7 copies to the Engineer of each of these approved documents.

It is expressly understood that the Engineer's approval of the Contractor's WQCP shall not relieve the Contractor of any responsibility under the contract for the successful completion of the work in conformity with the requirements of the plans and specifications. The Engineer's approval shall not constitute a waiver of any requirement of the plans and specifications nor relieve the Contractor of any obligation thereunder, and defective work, materials, and equipment may be rejected notwithstanding approval of the WQCP.

A daily production log for welding shall be kept by the QCM for each day that welding is performed. The log shall clearly indicate the locations of all welding, except partial penetration longitudinal seam welds performed in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications. The log shall include the welders' names, amount of welding performed, any problems or deficiencies discovered, and any testing or repair work performed, at each location. The daily report from each QC Inspector shall also be included in the log.

The following items shall be included in a Welding Report that is to be submitted to the Engineer within 7 days following the performance of any welding. For work welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, the following items shall be included in a Welding Report that is to be submitted to the Engineer 48 hours prior to the Contractor furnishing a Certificate of Compliance for the material:

- A. Reports of all visual weld inspections and NDT;
- B. Radiographs and radiographic reports, and other required NDT reports;
- C. Documentation that the Contractor has evaluated all radiographs and other nondestructive tests and corrected all rejectable deficiencies, and all repaired welds have been reexamined by the required NDT and found acceptable; and
- D. Daily production log.

Radiographic envelopes shall have clearly written on the outside of the envelope the following information: name of the QCM, name of the nondestructive testing firm, name of the radiographer, date, contract number, complete part description, and all included weld numbers or a report number, as detailed in the WQCP. In addition, all innerleaves shall have clearly written on them the part description and all included weld numbers, as detailed in the WQCP.

Reports regarding NDT, including radiographs, shall be signed by both the NDT technician and the person that performed the review, and then submitted directly to the QCM for review and signature prior to submittal to the Engineer. Corresponding names shall be clearly printed or typewritten next to all signatures.

The Engineer will review the Welding Report to determine if the Contractor is in conformance with the WQCP. Unless otherwise specified, the Engineer shall be allowed 7 working days to review the report and respond in writing after a complete Welding Report has been received. Prior to receiving notification from the Engineer of the Contractor's conformance with the WQCP, the Contractor may encase in concrete or cover welds for which a Welding Report has been submitted. However, should the Contractor elect to encase or cover those welds prior to receiving notification from the Engineer, it is expressly understood that the Contractor shall not be relieved of the responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase or cover welds pending notification by the Engineer, and should the Engineer fail to complete the review and provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in notification, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The QC Inspector shall provide reports to the QCM on a daily basis for each day that welding is performed.

Except for noncritical weld repairs, the Engineer shall be notified immediately in writing when welding problems, deficiencies, base metal repairs, or any other type of repairs not submitted in the WQCP are discovered and also of the proposed repair procedures to correct them. The Engineer shall have 5 working days to review these procedures. No remedial work shall begin until the repair procedures are approved in writing by the Engineer. Should the Engineer fail to complete the review within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the proposed repair procedures, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The QCM shall sign and furnish to the Engineer, a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each item of work for which welding was performed. The certificate shall state that all of the materials and workmanship incorporated in the work, and all required tests and inspections of this work, have been performed in conformance with the details shown on the plans and the provisions of the Standard Specifications and these special provisions.

PAYMENT

Full compensation for conforming to the requirements of this section shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

SECTION 9. DESCRIPTION OF BRIDGE WORK

The bridge work consists, in general, of constructing 3 new single-span bridges, 2 new retaining walls and 1 earth retaining structure of mechanically stabilized embankment, as shown on the plans and briefly described below.

PRUNEDALE OVERCROSSING

Bridge No. 44-0276Y

A single-span structure with cast-in-place reinforced concrete box girder superstructure, approximately 21 meters long and 17 meters wide, supported on Class 625 precast prestressed concrete pile foundations.

S101 - W156 CONNECTOR UNDERCROSSING

Bridge No. 44-0277F

A single-span structure with cast-in-place reinforced concrete box girder superstructure, approximately 26 meters long and 8 meters wide, supported on spread footings.

PRUNEDALE UNDERCROSSING

Bridge No. 44-0278

A single-span structure with cast-in-place prestressed concrete box girder superstructure, approximately 32 meters long and 15 meters to 19 meters wide, supported on spread footings.

PRUNEDALE RETAINING WALL NO. 1

Bridge No. 44-0280M

An earth retaining structure of mechanically stabilized embankment approximately 100 meters long with design height approximately from 1.8 meters to 3 meters.

PRUNEDALE RETAINING WALL NO. 2

Bridge No. 44-RW2

A reinforced concrete retaining wall supported on Class 625 precast prestressed concrete pile foundation approximately 88 meters long with design height approximately from 2.4 meters to 8 meters.

PRUNEDALE RETAINING WALL NO. 3

Bridge No. 44-RW3

A reinforced concrete retaining wall approximately 54 meters long with design height approximately from 1.8 meters to 3 meters.

SECTION 10. CONSTRUCTION DETAILS

SECTION 10-1. GENERAL

10-1.00 CONSTRUCTION PROJECT INFORMATION SIGNS

Before any major physical construction work readily visible to highway users is started on this contract, the Contractor shall furnish and erect two Type 1 and one Type 2 Construction Project Information signs at the locations designated by the Engineer.

The signs and overlays shall be of a type and material consistent with the estimated time of completion of the project and shall conform to the details shown on the plans.

The sign letters, border and the Department's construction logos shall conform to the colors (non-reflective) and details shown on the plans, and shall be on a white background (non-reflective). The colors blue and orange shall conform to PR Color Number 3 and Number 6, respectively, as specified in the Federal Highway Administration's Color Tolerance Chart.

The sign message to be used for fund types shall consist of the following, in the order shown:

FEDERAL HIGHWAY TRUST FUNDS
STATE HIGHWAY FUNDS

The sign message to be used for type of work shall consist of the following:

HIGHWAY CONSTRUCTION

The sign message to be used for the Year of Completion of Project Construction will be furnished by the Engineer. The Contractor shall furnish and install the "Year" sign overlay within 10 working days of notification of the year date to be used.

The letter sizes to be used shall be as shown on the plans. The information shown on the signs shall be limited to that shown on the plans.

The signs shall be kept clean and in good repair by the Contractor.

Upon completion of the work, the signs shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications.

Full compensation for furnishing, erecting, maintaining, and removing and disposing of the construction project information signs shall be considered as included in the contract lump sum price paid for construction area signs and no additional compensation will be allowed therefor.

10-1.01 ORDER OF WORK

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

Attention is directed to "Environmentally Sensitive Area (ESA)" elsewhere in these special provisions regarding archeological materials, and the placement of "Temporary Fence (Type ESA)".

Attention is directed to various Sections for "Erosion Control" elsewhere in these special provisions regarding order of work.

Attention is directed to "Move In/Move Out (Erosion Control)" elsewhere in these special provisions regarding application of erosion control which may require several move ins/move outs of erosion control equipment.

Attention is directed to "Architectural Surface (Textured Concrete)" of these special provisions regarding constructing a 1.25 m x 1.25 m test panel prior to constructing the concrete structures with architectural surface.

Attention is directed to "Fire Plan" of these special provisions regarding cooperating with local fire prevention authorities and implementing the fire plan established for this project.

Temporary railing (Type K) and temporary crash cushions shall be secured in place prior to commencing work for which the temporary railing and crash cushions are required.

Attention is directed to "Overhead", "Maintaining Traffic" and "Temporary Pavement Delineation" of these special provisions and to the stage construction sheets of the plans.

Attention is directed to "Progress Schedule (Critical Path Method)" of these special provisions regarding the submittal of a general time-scaled logic diagram within 10 days after approval of the contract. The diagram shall be submitted prior to performing any work that may be affected by any proposed deviations to the construction staging of the project.

Attention is directed to "Shoulder Backing" of these special provisions regarding placement of signs and portable delineators until shoulder backing is completed.

The Contractor shall remove park and ride facility, construct Route 156 detour, Prunedale Overcrossing (Bridge No. 44-0276Y), Prunedale Undercrossing (Bridge No. 44-0278), Prunedale Road/Route 156 connector and temporary north end profile, and a portion of Retaining Wall No. 2 from Station 7+76 to Station 8+29 during Stage 1 and Stage 2 prior to any construction along Route 101 except construction of the approach slab at the end of Prunedale Overcrossing bridge which is to be completed during Stage 6 of construction; and the excavation and completion of Prunedale Undercrossing bridge which is to be completed during Stage 5 of construction.

The work shall be performed in conformance with the stages of construction shown on the plans. Nonconflicting work in subsequent stages may proceed concurrently with work in preceding stages, provided satisfactory progress is maintained in the preceding stages of construction.

In each stage, after completion of the preceding stage, the first order of work shall be the removal of existing pavement delineation as directed by the Engineer. Pavement delineation removal shall be coordinated with new delineation so that lane lines are provided at all times on traveled ways open to public traffic.

Before obliterating any pavement delineation that is to be replaced on the same alignment and location, as determined by the Engineer, the pavement delineation shall be referenced by the Contractor, with a sufficient number of control points to reestablish the alignment and location of the new pavement delineation. The references shall include the limits or changes in striping pattern, including one- and 2-way barrier lines, limit lines, crosswalks and other pavement markings. Full compensation for referencing pavement delineation shall be considered as included in the contract prices paid for new pavement delineation and no additional compensation will be allowed therefor.

At the end of each working day if a difference in excess of 45 mm exists between the elevation of the existing pavement and the elevation of excavations within 1.5 m of the traveled way, material shall be placed and compacted against the vertical cuts adjacent to the traveled way. During excavation operations, native material may be used for this purpose; however, once placing of the structural section commences, structural material shall be used. The material shall be placed to the level of the elevation of the top of existing pavement and tapered at a slope of 1:4 (vertical:horizontal) or flatter to the bottom of the excavation. Full compensation for placing the material on a 1:4 slope, regardless of the number of times the material is required, and subsequent removing or reshaping of the material to the lines and grades shown on the plans shall be considered as included in the contract price paid for the materials involved and no additional compensation will be allowed therefor. No payment will be made for material placed in excess of that required for the structural section.

At those locations exposed to public traffic where guard railings are to be constructed, reconstructed, or removed and replaced, the Contractor shall schedule operations so that at the end of each working day there shall be no post holes open nor shall there be any railing posts installed without the blocks and rail elements assembled and mounted thereon.

Within 15 days after the contract has been approved, the Contractor shall furnish the Engineer a statement from the vendor that the order for the plants required for this contract, including inspection plants, has been received and accepted by the vendor. The statement from the vendor shall include the names, sizes, and quantities of plants ordered and the anticipated date of delivery.

The Contractor shall place orders for replacement plants with the vendor at the appropriate time so that the roots of the replacement plants are not in a root-bound nor underdeveloped condition.

Within 15 days after the contract has been approved, the Contractor shall furnish the Engineer a statement from the vendor that the order for the seed required for this contract has been received and accepted by the vendor. The statement from the vendor shall include the names and quantity of seed ordered and the anticipated date of delivery.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions, regarding restrictions for erosion control and planting operations.

Attention is directed to "Locate Existing Water Supply Line" of these special provisions regarding locating existing irrigation water supply line shown on the plans to be incorporated in the new work. Existing irrigation water supply line shall be located prior to performing work on the irrigation system.

Unless otherwise shown on the plans or specified in these special provisions, conduits to be jacked or drilled or installed by the open trench method for water line crossovers and sprinkler control crossovers shall be installed prior to the installation of other pipe supply lines.

Clearing, grubbing, and earthwork operations shall not be performed in areas where existing irrigation facilities are to remain in place until existing irrigation facilities have been checked for proper operation in conformance with the provisions in "Highway Planting and Irrigation Systems" of these special provisions.

Attention is directed to Section 20-5.027B, "Wiring Plans and Diagrams," of the Standard Specifications regarding submittal of working drawings.

When embankment settlement periods or surcharge embankment settlement periods are specified, the settlement periods and the deferment of portions of the work shall comply with the provisions in Section 19-6.025, "Settlement Period," of the Standard Specifications and in "Earthwork" of these special provisions.

10-1.02 WATER POLLUTION CONTROL (STORM WATER POLLUTION PREVENTION PLAN)

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications and these special provisions.

This project lies within the boundaries of the Region 3 - Central Coast - Regional Water Quality Control Board and shall conform to the requirements of the National Pollutant Discharge Elimination System (NPDES) Permit for General Construction Activities No. CAS000002, Order No, 99-08-DWQ, and the NPDES Permit for the State of California Department of Transportation Properties, Facilities, and Activities, No. CAS000003, Order No, 99-06-DWQ issued by the State Water Resources Control Board. These permits, hereafter referred to as the "Permits," regulate storm water discharges associated with construction activities.

Water pollution control work shall conform to the requirements in the "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual" and the "Construction Site Best Management Practices (BMPs) Manual," and addenda thereto issued up to, and including, the date of advertisement of the project, hereafter referred to respectively as the "Preparation Manual" and the "Construction Site BMP Manual" and collectively as the "Manuals." Copies of the Manuals and the Permits may be obtained from the Department of Transportation, Material Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520. Copies of the Manuals may also be obtained from the Department's Internet Web Site at: <http://www.dot.ca.gov/hq/construc/stormwater.html>.

The Contractor shall know and fully comply with the applicable provisions of the Manuals, Permits, and Federal, State, and local regulations that govern the Contractor's operations and storm water discharges from both the project site and areas of disturbance outside the project limits during construction. The Contractor shall maintain copies of the Permits at the project site and shall make the Permits available during construction.

Unless arrangements for disturbance or use of areas outside the project limits are made by the Department and made part of the contract, it is expressly agreed that the Department assumes no responsibility for the Contractor or property owner with respect to any arrangements made between the Contractor and property owner. The Contractor shall implement, inspect and maintain all necessary water pollution control practices to satisfy all applicable Federal, State, and Local laws and regulations that govern water quality for areas used outside of the highway right-of-way or areas arranged for the specific use of the Contractor for this project. Installing, inspecting, and maintaining water pollution control practices on areas outside the highway right-of-way not specifically arranged for and provided for by the Department for the execution of this contract will not be paid for.

The Contractor shall be responsible for the costs and for liabilities imposed by law as a result of the Contractor's failure to comply with the provisions set forth in this section "Water Pollution Control", including but not limited to, compliance with the applicable provisions of the Manuals, Permits and Federal, State and local regulations. Costs and liabilities include, but are not limited to, fines, penalties, and damages whether assessed against the State or the Contractor, including those levied under the Federal Clean Water Act and the State Porter Cologne Water Quality Act.

In addition to the remedies authorized by law, money due the Contractor under the contract, in an amount determined by the Department, may be retained by the State of California until disposition has been made of the costs and liabilities.

When a regulatory agency or other third party identifies a failure to comply with the permit or any other local, State, or federal requirement, the Engineer may retain money due the Contractor, subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
- B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications.
- C. If the Department has retained funds and it is subsequently determined that the State is not subject to the costs and liabilities in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained for the period of the retention, and the rate of interest payable shall be 6 percent per annum.

Conformance with the provisions of this section "Water Pollution Control" shall not relieve the Contractor from the Contractor's responsibilities, as provided in Section 7, "Legal Relations and Responsibilities," of the Standard Specifications.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor or otherwise access the project site or the Contractor's records pertaining to water pollution control work.

STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND AMENDMENTS

As part of the water pollution control work, a Storm Water Pollution Prevention Plan, hereafter referred to as the "SWPPP," is required for this contract. The SWPPP shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, the requirements in the Manuals, the requirements of the Permits, and these special provisions. Upon the Engineer's approval of the SWPPP, the SWPPP shall be considered to fulfill the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications for development and submittal of a Water Pollution Control Program.

No work having potential to cause water pollution, as determined by the Engineer, shall be performed until the SWPPP has been approved by the Engineer.

The Contractor shall designate a Water Pollution Control Manager. The Water Pollution Control Manager shall be responsible for the preparation of the SWPPP and any required modifications or amendments and shall be responsible for the implementation and adequate functioning of the various water pollution control practices employed. The Water Pollution Control Manager shall serve as the primary contact for all issues related to the SWPPP or its implementation. The Contractor shall submit to the Engineer a statement of qualifications, describing the training, previous work history and expertise of the individual selected by the Contractor to serve as Water Pollution Control Manager. The Engineer will reject the Contractor's submission of a Water Pollution Control Manager if the submitted qualifications are deemed to be inadequate.

Within 30 days after the approval of the contract, the Contractor shall submit 3 copies of the draft SWPPP to the Engineer. The Engineer will have 15 days to review the SWPPP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the SWPPP within 10 days of receipt of the Engineer's comments. The Engineer will have 10 days to review the revisions. Upon the Engineer's approval of the SWPPP, 4 approved copies of the SWPPP, incorporating the required changes, shall be submitted to the Engineer. In order to allow construction activities to proceed, the Engineer may conditionally approve the SWPPP while minor revisions are being completed. If the Engineer does not review or approve the SWPPP within the time specified, compensation will be made in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The SWPPP shall apply to all areas that are directly related to construction including, but not limited to, staging areas, storage yards, material borrow areas, and access roads within or outside of the highway right-of-way.

The SWPPP shall incorporate water pollution control practices in the following six categories:

- A. Soil stabilization;
- B. Sediment control;
- C. Wind erosion control;
- D. Tracking control;
- E. Non-storm water control; and
- F. Waste management and material pollution control.

The Contractor shall develop a Water Pollution Control Schedule that shall describe the timing of grading or other work activities that could affect water pollution. The Water Pollution Control Schedule shall be updated by the Contractor to reflect any changes in the Contractor's operations that would affect the necessary implementation of water pollution control practices.

The Contractor shall incorporate the "Minimum Requirements" presented in the Preparation Manual into the SWPPP. In addition to the "Minimum Requirements" presented in the Preparation Manual, the Contractor shall complete the BMP Consideration Checklist presented in the Preparation Manual. The Contractor shall identify and incorporate into the SWPPP the water pollution control practices selected by the Contractor or as directed by the Engineer.

The SWPPP shall include, but not be limited to, the items described in the Manuals, Permits and related information contained in the contract documents. In addition the SWPPP shall include a copy of the following: Notification of Construction, Department of Fish and Game Permit, and U.S. Army Corp of Engineers' Permit.

The Contractor shall prepare an amendment to the SWPPP when there is a change in construction activities or operations which may affect the discharge of pollutants to surface waters, ground waters, municipal storm drain systems, or when the Contractor's activities or operations violate any condition of the Permits, or when directed by the Engineer. Amendments shall show additional water pollution control practices or revised operations, including those areas or operations not shown in the initially approved SWPPP. Amendments to the SWPPP shall be prepared, and submitted for review and approval in the same manner as specified for the SWPPP approval. Subsequent amendments shall be submitted within a time approved by the Engineer, but in no case longer than the time specified for the initial submittal and review of the SWPPP. At a minimum, the SWPPP shall be amended annually and submitted to the Engineer 25 days prior to the defined rainy season.

The Contractor shall keep one copy of the approved SWPPP and approved amendments at the project site. The SWPPP shall be made available upon request of a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency or the local storm water management agency. Requests by the public shall be directed to the Engineer.

COST BREAK-DOWN

The Contractor shall submit to the Engineer a cost break-down for the contract lump sum item of water pollution control, together with the SWPPP.

The cost break-down shall be completed and furnished in the format shown in the example of the cost break-down included in this section. Unit descriptions and quantities shall be designated by the Contractor, except for the specified special requirements shown in the example. The units and quantities given in the example, if provided, are special requirements specified for the SWPPP, and shall be included in the cost break-down furnished to the Engineer. The Contractor shall verify the estimated quantities of the special requirements and submit revised quantities in the cost break-down.

The Contractor shall determine the quantities required to complete the work of water pollution control. The quantities and their values shall be included in the cost break-down submitted to the Engineer for approval. The Contractor shall be responsible for the accuracy of the quantities and values used in the cost break-down submitted for approval. The cost break-down shall not include water pollution control practices which are shown on the plans and for which there is a separate contract item.

The sum of the amounts for the units of work listed in the cost break-down shall be equal to the contract lump sum price bid for water pollution control. Profit shall be included in each individual unit listed in the cost break-down. The cost break-down shall be submitted and approved within the same times specified for the SWPPP. Partial payment for the item of water pollution control will not be made until the cost break-down is approved, in writing, by the Engineer. Attention is directed to "Overhead" of these special provisions.

Adjustments in the items of work and quantities listed in the approved cost break-down shall be made when required to address amendments to the SWPPP, except when the adjusted items are paid for as extra work.

No adjustment in compensation will be made in the contract lump sum price paid for water pollution control due to differences between the quantities shown in the approved cost break-down and the quantities required to complete the work as shown on the approved SWPPP. No adjustment in compensation will be made for ordered changes to correct SWPPP work resulting from the Contractor's own operations or from the Contractor's negligence.

The approved cost break-down will be used to determine partial payments during the progress of the work and as the basis for calculating the adjustment in compensation for the item of water pollution control due to increases or decreases of quantities ordered by the Engineer. When an ordered change increases or decreases the quantities of an approved cost break-down item, the adjustment in compensation will be determined in the same manner specified for increases and decreases in the quantity of a contract item of work in conformance with the provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications. If an ordered change requires a new item not on the approved cost break-down, the adjustment in compensation will be determined in the same manner specified for extra work in conformance with Section 4-1.03D, "Extra Work," of the Standard Specifications.

If requested by the Contractor and approved by the Engineer, changes to the water pollution control practices listed in the approved cost break-down, including the addition of new water pollution control practices, will be allowed. The changes shall be included in an approved amendment to the SWPPP. If the changes to the water pollution control practices requested by the Contractor would result in a net cost increase to the lump sum price for water pollution control, an adjustment in compensation will be made without change to the item of water pollution control. The net cost increase to the item of water pollution control resulting from changes requested by the Contractor will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

WATER POLLUTION CONTROL COST BREAK-DOWN

Contract No. 05-0161U4

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT

TOTAL _____

SWPPP IMPLEMENTATION

Upon approval of the SWPPP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, maintaining, removing and disposing of the water pollution control practices included in the SWPPP and any amendments. Unless otherwise directed by the Engineer, the Contractor's responsibility for SWPPP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Requirements for installation, construction, inspection, maintenance, removal, and disposal of water pollution control practices are specified in the Manuals and these special provisions.

If the Contractor or the Engineer identifies a deficiency in any aspect of the implementation of the approved SWPPP or amendments, the deficiency shall be corrected immediately. The deficiency may be corrected at a later date and time if requested by the Contractor and approved by the Engineer in writing, but not later than the onset of precipitation. If the Contractor fails to correct the identified deficiency by the date agreed or prior to the onset of precipitation the project shall be in noncompliance. Attention is directed to Section 5-1.01, "Authority of the Engineer," of the Standard Specifications and the payment sections of these special provisions for possible noncompliance penalties.

If the Contractor fails to conform to the provisions of "Water Pollution Control," the Engineer may order the suspension of construction operations which create water pollution.

Implementation of water pollution control practices may vary by season. The Construction Site BMP Manual and these special provisions shall be followed for control practice selection of year round, rainy season and non-rainy season water pollution control practices.

Year-Round Implementation Requirements

The Contractor shall have a year-round program for implementing, inspecting and maintaining water pollution control practices for wind erosion control, tracking control, non-storm water control, and waste management and materials pollution control.

The National Weather Service weather forecast shall be monitored and used by the Contractor on a daily basis. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted, the necessary water pollution control practices shall be deployed prior to the onset of the precipitation.

Disturbed soil areas shall be considered active whenever the soil disturbing activities have occurred, continue to occur or will occur during the ensuing 21 days. Non-active areas shall be protected as prescribed in the Construction Site BMP Manual within 14 days of cessation of soil disturbing activities or prior to the onset of precipitation, whichever occurs first.

In order to provide effective erosion control the Contractor may be directed to apply permanent erosion control in small or multiple units as disturbed soil areas are deemed substantially complete by the Engineer. The Contractor's attention is directed to various Sections for "Erosion Control" and "Move-In/Move-Out (Erosion Control)" of these special provisions.

Rainy Season Requirements

Soil stabilization and sediment control practices conforming to the requirements in the Special Requirements and applicable Preparation Manual Minimum Requirements, shall be provided throughout the rainy season, defined as between October 15 and April 15.

An implementation schedule of required soil stabilization and sediment control practices for disturbed soil areas shall be completed not later than 20 days prior to the beginning of each rainy season. The implementation schedule shall identify the soil stabilization and sediment control practices to be implemented and the dates on which the implementation will be 25 percent, 50 percent and 100 percent complete, respectively. Construction activities beginning during the rainy season shall implement applicable soil stabilization and sediment control practices.

Throughout the defined rainy season, the active disturbed soil area of the project site shall be not more than 2 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active disturbed soil area limit. Soil stabilization and sediment control materials shall be maintained on site sufficient to protect the unprotected disturbed soil area. A detailed plan for the mobilization of sufficient labor and equipment shall be maintained to deploy the water pollution control practices required to protect the project site prior to the onset of precipitation events.

Non-Rainy Season Requirements

The non-rainy season shall be defined as all days outside the defined rainy season. The Contractor's attention is directed to the Construction Site BMP Manual for soil stabilization and sediment control implementation requirements on disturbed soil areas during the non-rainy season. Disturbed soil areas within the project shall be protected in conformance with the requirements in the Construction Site BMP Manual with an effective combination of soil stabilization and sediment control.

MAINTENANCE

To ensure the proper implementation and functioning of water pollution control practices, the Contractor shall regularly inspect and maintain the construction site for the water pollution control practices identified in the SWPPP. The construction site shall be inspected by the Contractor as follows:

- A. Prior to a forecast storm;
- B. After a precipitation event which causes site runoff;
- C. At 24 hour intervals during extended precipitation events;
- D. Routinely, a minimum of once every two weeks outside of the defined rainy season;
- E. Routinely, a minimum of once every week during the defined rainy season.

The Contractor shall use the Storm Water Quality Construction Site Inspection Checklist provided in the Preparation Manual or an alternative inspection checklist provided by the Engineer. One copy of each site inspection record shall be submitted to the Engineer within 24 hours of completing the inspection.

REPORTING REQUIREMENTS

Report of Discharges, Notices or Orders

If the Contractor identifies any discharge into receiving waters in a manner causing, or potentially causing, a condition of pollution, or if the project receives a written notice or order from any regulatory agency, the Contractor shall immediately inform the Engineer. The Contractor shall submit a written report to the Engineer within 7 days of the discharge event, notice, or order. The report shall include the following information:

- A. The date, time, location, nature of the operation, and type of discharge, including the cause or nature of the notice or order.
- B. The water pollution control practices deployed before the discharge event, or prior to receiving the notice or order.
- C. The date of deployment and type of water pollution control practices deployed after the discharge event, or after receiving the notice, or order, including additional measures installed or planned to reduce or prevent reoccurrence.
- D. An implementation and maintenance schedule for any affected water pollution control practices.

Report of First-Time Non-Storm Water Discharge

The Contractor shall notify the Engineer at least 3 days in advance of each first-time non-storm water discharge event, excluding exempted discharges. The Contractor shall notify the Engineer of each different operation causing a non-storm water discharge and shall obtain field approval for each first-time non-storm water discharge. Non-storm water discharges shall be monitored at each first-time occurrence and routinely thereafter.

Annual Certifications

By June 15 of each year, the Contractor shall complete and submit an Annual Construction Activity Certification as contained in the Preparation Manual to the Engineer.

PAYMENT

The contract lump sum price paid for prepare storm water pollution prevention plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in developing, preparing, obtaining approval of, revising, and amending the SWPPP, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Attention is directed to Section 9-1.06, "Partial Payments," and Section 9-1.07, "Payment After Acceptance," of the Standard Specifications. Payments for prepare storm water pollution prevention plan will be made as follows:

- A. After the SWPPP has been approved by the Engineer, 75 percent of the contract item price for prepare storm water pollution prevention plan will be included in the monthly partial payment estimate; and
- B. After acceptance of the contract in conformance with the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, payment for the remaining 25 percent of the contract item price for prepare storm water pollution prevention plan will be made in conformance with the provisions in Section 9-1.07.

The contract lump sum price paid for water pollution control shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing, constructing, removing, and disposing of water pollution control practices, including non-storm water and waste management and materials pollution water pollution control practices except those shown on the plans and for which there is a contract item of work, and excluding developing, preparing, obtaining approval of, revising, and amending the SWPPP, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The cost of maintaining the temporary water pollution control practices shall be divided equally by the State and the Contractor as follows:

Soil Stabilization

All temporary water pollution control practices except:
SS-1 Scheduling
SS-2 Preservation of Existing Vegetation

Sediment Control

All temporary water pollution control practices.

Tracking Control

All temporary water pollution control practices except:
SC-7 Street Sweeping and Vacuuming

Wind Erosion Control

All temporary water pollution control practices.

Non-Storm Water Control

No sharing of maintenance costs will be allowed.

Waste Management & Material Control

No sharing of maintenance costs will be allowed.

The division of cost will be made by determining the cost of maintaining temporary water pollution control practices in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications and paying to the Contractor one-half of that cost. Clean-up, repair, removal, disposal, improper installation, and replacement of temporary water pollution control practices damaged by the Contractor's negligence shall not be considered as included in the cost for performing maintenance and no additional compensation will be allowed therefor.

The provisions for sharing maintenance costs shall not relieve the Contractor from the responsibility for providing appropriate maintenance on those items where maintenance costs are not shared.

Full compensation for maintenance costs of water pollution control practices not shared, as specified in these special provisions, shall be considered as included in the contract lump sum price paid for water pollution control and no additional compensation will be allowed therefor.

Those water pollution control practices which are shown on the plans and for which there is a contract item of work will be measured and paid for as that contract item of work.

The Engineer will retain an amount equal to 25 percent of the estimated value of the contract work performed during estimate periods in which the Contractor fails to conform to the provisions of this section "Water Pollution Control," as determined by the Engineer.

Retention for failure to conform to the provisions in this section "Water Pollution Control" shall be in addition to the other retention provided for in the contract. The amounts retained for failure of the Contractor to conform to the provisions in this section will be released for payment on the next monthly estimate for partial payment following the date that an approved SWPPP has been implemented and maintained, and water pollution is adequately controlled, as determined by the Engineer.

10-1.03 TEMPORARY CULVERTS

Temporary culverts shall be furnished, installed, maintained, and later removed as shown on the plans, as specified in these special provisions and as directed by the Engineer.

The type of temporary culvert to be installed at each location shall be at the option of the Contractor; however, the culvert shall be capable of sustaining the intended load and of discharging a quantity of water equivalent to the size of culvert shown on the plans. Adequacy as to equivalent strength and capacity shall be subject to approval, in writing, by the Engineer.

Used materials may be installed provided the used materials are good, sound and are suitable for the purpose intended, as determined by the Engineer.

Excavation and backfill for temporary culverts shall be performed in a manner that will provide adequate support for the culvert with a firm, nonsettling foundation for the roadbeds to be constructed over the culverts.

Temporary culverts that are damaged from any cause during the progress of the work shall be repaired or replaced by the Contractor at the Contractor's expense.

When no longer required for the work as determined by the Engineer, temporary culverts shall be removed. Removed facilities shall become the property of the Contractor and shall be removed from the site of the work, except as otherwise provided in this section.

Removed temporary culverts that are not damaged may be installed in the permanent work provided the culverts conform to the requirements specified for the permanent work and the culverts are new when installed as temporary culverts.

Trenches and pits caused by the removal of temporary culverts shall be backfilled in conformance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

Regardless of the kinds of temporary culverts installed, temporary culverts will be measured and paid for by the meter for the sizes of temporary culverts shown on the plans and listed in the Engineer's Estimate in the same manner specified for corrugated metal pipe in Section 66-4.01, "Measurement," and Section 66-4.02, "Payment," of the Standard Specifications.

Full compensation for maintaining, removing and disposing of temporary culverts shall be considered as included in the contract prices paid per meter for the various sizes of temporary culverts and no additional compensation will be allowed therefor.

10-1.04 TEMPORARY OUTLET PROTECTION

Temporary outlet protection shall be furnished, installed, maintained, and later removed as shown on the plans, as specified in these special provisions and as directed by the Engineer.

Rock slope protection shall be placed or constructed in conformance with the provisions in Section 72, "Slope Protection," of the Standard Specifications.

Rock slope protection fabric shall be woven or nonwoven type fabric, Type A or Type B, at the option of the Contractor.

Used materials may be installed provided the used materials are good, sound and are suitable for the purpose intended, as determined by the Engineer.

Temporary outlet protection that are damaged from any cause during the progress of the work shall be repaired or replaced by the Contractor at the Contractor's expense.

When no longer required for the work as determined by the Engineer, temporary outlet protection shall be removed. Removed facilities shall become the property of the Contractor and shall be removed from the site of the work, except as otherwise provided in this section.

Trenches and pits caused by the removal of temporary outlet protection shall be backfilled in conformance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

Full compensation for temporary outlet protection including excavation and backfill shall be considered as included in the contract prices paid per meter for temporary pipe downdrains of the sizes designated in the Engineer's Estimate and no separate payment will be made therefor.

10-1.05 TEMPORARY DRAINAGE INLET

Temporary drainage inlets shall be furnished, installed, maintained, and later removed as shown on the plans, as specified in these special provisions and as directed by the Engineer.

Used materials may be installed provided the used materials are good, sound and are suitable for the purpose intended, as determined by the Engineer.

Excavation and backfill for temporary drainage inlets shall be performed in a manner that will provide adequate support for the drainage inlets with a firm, nonsettling foundation for the roadbeds to be constructed over the culverts.

Temporary drainage inlets that are damaged from any cause during the progress of the work shall be repaired or replaced by the Contractor at the Contractor's expense.

When no longer required for the work as determined by the Engineer, temporary drainage inlets shall be removed. Removed facilities shall become the property of the Contractor and shall be removed from the site of the work, except as otherwise provided in this section.

Removed temporary drainage inlets that are not damaged may be installed in the permanent work provided the drainage inlets conform to the requirements specified for the permanent work and the drainage inlets are new when installed as temporary drainage inlets.

Trenches and pits caused by the removal of temporary drainage inlets shall be backfilled in conformance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

Temporary drainage inlets will be measured for payment by the unit.

The contract unit price paid for temporary drainage inlet shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary drainage inlets, complete in place, including excavation and backfill and maintaining, removing and disposing temporary drainage inlets, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.06 TEMPORARY OVERSIDE DRAIN

Temporary entrance taper, metal pipe downdrain anchor assemblies, and pipe downdrains shall be furnished, installed, maintained, and later removed as shown on the plans, as specified in these special provisions and as directed by the Engineer.

The type of temporary entrance taper, metal pipe downdrain anchor assemblies, and pipe downdrains to be installed at each location shall be at the option of the Contractor; however, the entrance taper, metal pipe downdrain anchor assemblies, and pipe downdrains shall be capable of sustaining the intended load. Adequacy as to equivalent strength and capacity shall be subject to approval, in writing, by the Engineer.

Used materials may be installed provided the used materials are good, sound and are suitable for the purpose intended, as determined by the Engineer.

Excavation and backfill shall be performed in a manner that will provide adequate support for the entrance taper, metal pipe downdrain anchor assemblies, and pipe downdrains with a firm, nonsettling foundation for the roadbeds to be constructed over the culverts.

Temporary entrance taper, metal pipe downdrain anchor assemblies, and pipe downdrains that are damaged from any cause during the progress of the work shall be repaired or replaced by the Contractor at the Contractor's expense.

When no longer required for the work as determined by the Engineer, temporary entrance taper, metal pipe downdrain anchor assemblies, and pipe downdrains shall be removed. Removed facilities shall become the property of the Contractor and shall be removed from the site of the work, except as otherwise provided in this section.

Removed temporary entrance taper, metal pipe downdrain anchor assemblies, and pipe downdrains that are not damaged may be installed in the permanent work provided they conform to the requirements specified for the permanent work and the entrance taper, metal pipe downdrain anchor assemblies, and pipe downdrains are new when installed as temporary entrance taper, metal pipe downdrain anchor assemblies, and pipe downdrains.

Regardless of the kinds of temporary entrance taper, metal pipe downdrain anchor assemblies, and pipe downdrains installed, temporary entrance taper, metal pipe downdrain anchor assemblies, and pipe downdrains will be measured and paid for as listed in the Engineer's Estimate in the same manner specified for overside drains in Section 69-1.05, "Measurement," and Section 69-1.06, "Payment," of the Standard Specifications.

Full compensation for maintaining, removing and disposing of temporary entrance taper, metal pipe downdrain anchor assemblies, and pipe downdrains shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

10-1.07 TEMPORARY METAL BEAM GUARD RAILING

Temporary metal beam guard railing shall be furnished, constructed, maintained, and later removed as shown on the plans, as specified in these special provisions and as directed by the Engineer.

Except as otherwise specified in this section, temporary metal beam guard railing work shall conform to the plan details and the specifications for permanent metal beam guard railing as provided in "Metal Beam Guard Railing" of these special provisions.

Used materials may be installed provided the used materials are good, sound and are suitable for the purpose intended, as determined by the Engineer.

Galvanizing of steel items will not be required.

Treating wood with a wood preservative will not be required.

Steel posts, plates, foundation tubes, soil plates, hardware, threaded rods, and anchor bolts, except high strength bolts, may be commercial quality material.

Temporary metal beam guard railing facilities that are damaged during the progress of the work shall be repaired or replaced by the Contractor at the Contractor's expense.

When no longer required for the work as determined by the Engineer, temporary metal beam guard railing materials (including footings and anchors) shall be completely removed. Removed facilities shall become the property of the Contractor and shall be removed from the site of the work, except as otherwise provided in this section.

Removed temporary metal beam guard railing materials that are not damaged may be reused in the permanent work provided the materials conform to the requirements specified for the permanent work and the materials are new when used for the temporary metal beam guard railing.

Holes and pits caused by the removal of temporary metal beam guard railing facilities shall be backfilled in conformance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

Temporary metal beam guard railing, temporary terminal system (Type SRT), temporary end sections, and temporary terminal sections will be measured and paid for in the same manner specified for corresponding items for permanent metal beam guard railing work as provided in "Metal Beam Guard Railing" of these special provisions.

Full compensation for maintaining, removing and disposing of temporary metal beam guard railing materials shall be considered as included in the prices paid for the various contract items for temporary metal beam guard railing work and no additional compensation will be allowed therefor.

10-1.08 TEMPORARY FENCE (TYPE ESA)

Temporary fence (Type ESA) shall be furnished, constructed, maintained, and later removed and disposed of as shown on the plans, as specified in these special provisions and as directed by the Engineer.

Except as otherwise specified in this section, temporary fence (Type ESA) shall conform to the plan details and the specifications for permanent fence of similar character as provided in Section 80, "Fences," of the Standard Specifications.

Used materials may be installed provided the used materials are good, sound and are suitable for the purpose intended, as determined by the Engineer.

Materials may be commercial quality provided the dimensions and sizes of the materials are equal to, or greater than, the dimensions and sizes shown on the plans or specified herein. Temporary fences (Type ESA) shall be at least 1.2 meters in height. Temporary fence (Type ESA) fabric shall consist of orange colored, ultraviolet stabilized polypropylene or polyethylene polymer fabric, in a biaxial grid.

Posts shall be either metal or wood at the Contractor's option.

Galvanizing and painting of steel items will not be required.

Treating wood with a wood preservative will not be required.

Concrete footings for metal posts will not be required.

Temporary fence (Type ESA) shall be constructed a sufficient distance from plants to enclose all of the foliage canopy and visible roots of the plants. Temporary fence (Type ESA) shall not be attached to tree trunks or any other vegetation. Temporary fence (Type ESA) that is damaged during the progress of the work shall be repaired or replaced by the Contractor at the Contractor's expense.

When no longer required for the work, as determined by the Engineer, temporary fence (Type ESA) shall be removed. Removed facilities shall become the property of the Contractor and shall be removed from the site of the work, except as otherwise provided in this section.

Holes caused by the removal of temporary fence (Type ESA) shall be backfilled in conformance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

The temporary fence (Type ESA) will be measured for payment in the same manner specified for permanent fence of similar character as provided in Section 80, "Fences," of the Standard Specifications.

The contract price paid per meter for temporary fence (Type ESA) shall include full compensation for providing, installing, maintaining, removing, and disposing of temporary fence, and for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in temporary fence (Type ESA), complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.09 PRESERVATION OF PROPERTY

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications and these special provisions.

Existing trees, shrubs and other plants, that are not to be removed as shown on the plans or specified in these special provisions, and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree replacement shall be No. 15 container at a ratio of 5:1 and the minimum size of shrub replacement shall be No. 15 container at a ratio of 3:1. Replacement ground cover plants shall be from flats and shall be planted 300 mm on center. Replacement of Carpobrotus ground cover plants shall be from cuttings and shall be planted 300 mm on center. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips. The chipped material shall be spread within the highway right of way at locations designated by the Engineer.

Replacement planting of injured or damaged trees, shrubs, and other plants shall be completed prior to the start of the plant establishment period. Replacement planting shall conform to the provisions in Section 20-4.05, "Planting," of the Standard Specifications. Replacement plants shall be maintained in accordance with Section 20-4.08, "Plant Establishment," of the Standard Specifications and "Plant Establishment Work" of these special provisions.

10-1.10 DAMAGE REPAIR

Attention is directed to Section 7-1.16, "Contractor's Responsibility for the Work and Materials," and Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications and these special provisions.

When as a result of freezing conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacement work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. A freezing condition, for the purpose of this specification, occurs when the temperature at or near the affected area has been officially recorded below 0°C and plants have been killed or damaged to the degree described above.

When the provisions in Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications are applicable, the provisions above for payment of costs for repair of damage due to rain, freezing conditions and drought shall not apply.

10-1.11 RELIEF FROM MAINTENANCE AND RESPONSIBILITY

The Contractor may be relieved of the duty of maintenance and protection for those items not directly connected with plant establishment work, except highway planting and irrigation systems in conformance with the provisions in Section 7-1.15, "Relief From Maintenance and Responsibility," of the Standard Specifications.

10-1.12 COOPERATION

Attention is directed to Section 7-1.14, "Cooperation," and Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

It is anticipated that work by another contractor (Contract No. 05-016174) to construct the San Miguel Canyon Road Interchange in Monterey County near Salinas on Route 101 from 0.3 km North of Route 101/156 Separation to 2.4 km North of Route 101/156 Separation (KP 153.8 to KP 155.9) may be in progress adjacent to or within the limits of this project during progress of the work on this contract.

10-1.13 PROGRESS SCHEDULE (CRITICAL PATH METHOD)

The Contractor shall submit to the Engineer practicable critical path method (CPM) progress schedules in conformance with these special provisions. Whenever the term "schedule" is used in this section it shall mean CPM progress schedule.

Attention is directed to "Payments" of Section 5 of these special provisions.

The provisions in Section 8-1.04, "Progress Schedule," of the Standard Specifications shall not apply.

DEFINITIONS

The following definitions shall apply to this section:

- A. **ACTIVITY.**—A task, event or other project element on a schedule that contributes to completing the project. Activities have a description, start date, finish date, duration and one or more logic ties.
- B. **BASELINE SCHEDULE.**—The initial schedule representing the Contractor's work plan on the first working day of the project.
- C. **CONTRACT COMPLETION DATE.**—The current extended date for completion of the contract shown on the weekly statement of working days furnished by the Engineer in conformance with the provisions in Section 8-1.06, "Time of Completion," of the Standard Specifications.
- D. **CRITICAL PATH.**—The longest continuous chain of activities for the project that has the least amount of total float of all chains. In general, a delay on the critical path will extend the scheduled completion date.
- E. **CRITICAL PATH METHOD (CPM).**—A network based planning technique using activity durations and the relationships between activities to mathematically calculate a schedule for the entire project.

- F. DATA DATE.—The day after the date through which a schedule is current. Everything occurring earlier than the data date is "as-built" and everything on or after the data date is "planned."
- G. EARLY COMPLETION TIME.—The difference in time between an early scheduled completion date and the contract completion date.
- H. FLOAT.—The difference between the earliest and latest allowable start or finish times for an activity.
- I. MILESTONE.—An event activity that has zero duration and is typically used to represent the beginning or end of a certain stage of the project.
- J. NARRATIVE REPORT.—A document submitted with each schedule that discusses topics related to project progress and scheduling.
- K. NEAR CRITICAL PATH.—A chain of activities with total float exceeding that of the critical path but having no more than 10 working days of total float.
- L. SCHEDULED COMPLETION DATE.—The planned project finish date shown on the current accepted schedule.
- M. STATE OWNED FLOAT ACTIVITY.—The activity documenting time saved on the critical path by actions of the State. It is the last activity prior to the scheduled completion date.
- N. TIME IMPACT ANALYSIS.—A schedule and narrative report developed specifically to demonstrate what effect a proposed change or delay has on the current scheduled completion date.
- O. TOTAL FLOAT.—The amount of time that an activity or chain of activities can be delayed before extending the scheduled completion date.
- P. UPDATE SCHEDULE.—A current schedule developed from the baseline or subsequent schedule through regular monthly review to incorporate as-built progress and any planned changes.

GENERAL REQUIREMENTS

The Contractor shall submit to the Engineer baseline, monthly update and final update schedules, each consistent in all respects with the time and order of work requirements of the contract. The project work shall be executed in the sequence indicated on the current accepted schedule.

Schedules shall show the order in which the Contractor proposes to carry out the work with logical links between time-scaled work activities, and calculations made using the critical path method to determine the controlling operation or operations. The Contractor is responsible for assuring that all activity sequences are logical and that each schedule shows a coordinated plan for complete performance of the work.

The Contractor shall produce schedules using computer software and shall furnish compatible software for the Engineer's exclusive possession and use. The Contractor shall furnish network diagrams, narrative reports, tabular reports and schedule data as parts of each schedule submittal.

Schedules shall include, but not be limited to, activities that show the following that are applicable to the project:

- A. Project characteristics, salient features, or interfaces, including those with outside entities, that could affect time of completion.
- B. Project start date, scheduled completion date and other milestones.
- C. Work performed by the Contractor, subcontractors and suppliers.
- D. Submittal development, delivery, review and approval, including those from the Contractor, subcontractors and suppliers.
- E. Procurement, delivery, installation and testing of materials, plants and equipment.
- F. Testing and settlement periods.
- G. Utility notification and relocation.
- H. Erection and removal of falsework and shoring.
- I. Major traffic stage switches.
- J. Finishing roadway and final cleanup.
- K. State-owned float as the predecessor activity to the scheduled completion date.

Schedules shall have not less than 50 and not more than 500 activities, unless otherwise authorized by the Engineer. The number of activities shall be sufficient to assure adequate planning of the project, to permit monitoring and evaluation of progress, and to do an analysis of time impacts.

Schedule activities shall include the following:

- A. A clear and legible description.
- B. Start and finish dates.
- C. A duration of not less than one working day, except for event activities, and not more than 20 working days, unless otherwise authorized by the Engineer.

- D. At least one predecessor and one successor activity, except for project start and finish milestones.
- E. Required constraints.
- F. Codes for responsibility, stage, work shifts, location and contract pay item numbers.

The Contractor may show early completion time on any schedule provided that the requirements of the contract are met. Early completion time shall be considered a resource for the exclusive use of the Contractor. The Contractor may increase early completion time by improving production, reallocating resources to be more efficient, performing sequential activities concurrently or by completing activities earlier than planned. The Contractor may also submit for approval a cost reduction incentive proposal in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications that will reduce time of construction.

The Contractor may show a scheduled completion date that is later than the contract completion date on an update schedule, after the baseline schedule is accepted. The Contractor shall provide an explanation for a late scheduled completion date in the narrative report that is included with the schedule.

State-owned float shall be considered a resource for the exclusive use of the State. The Engineer may accrue State-owned float by the early completion of review of any type of required submittal when it saves time on the critical path. The Contractor shall prepare a time impact analysis, when requested by the Engineer, to determine the effect of the action in conformance with the provisions in "Time Impact Analysis" specified herein. The Engineer will document State-owned float by directing the Contractor to update the State-owned float activity on the next update schedule. The Contractor shall include a log of the action on the State-owned float activity and include a discussion of the action in the narrative report. The Engineer may use State-owned float to mitigate past, present or future State delays by offsetting potential time extensions for contract change orders.

The Engineer may adjust contract working days for ordered changes that affect the scheduled completion date, in conformance with the provisions in Section 4-1.03, "Changes," of the Standard Specifications. The Contractor shall prepare a time impact analysis to determine the effect of the change in conformance with the provisions in "Time Impact Analysis" specified herein, and shall include the impacts acceptable to the Engineer in the next update schedule. Changes that do not affect the controlling operation on the critical path will not be considered as the basis for a time adjustment. Changes that do affect the controlling operation on the critical path will be considered by the Engineer in decreasing time or granting an extension of time for completion of the contract. Time extensions will only be granted if the total float is absorbed and the scheduled completion date is delayed one or more working days because of the ordered change.

The Engineer's review and acceptance of schedules shall not waive any contract requirements and shall not relieve the Contractor of any obligation thereunder or responsibility for submitting complete and accurate information. Schedules that are rejected shall be corrected by the Contractor and resubmitted to the Engineer within 5 working days of notification by the Engineer, at which time a new review period of one week will begin.

Errors or omissions on schedules shall not relieve the Contractor from finishing all work within the time limit specified for completion of the contract. If, after a schedule has been accepted by the Engineer, either the Contractor or the Engineer discover that any aspect of the schedule has an error or omission, it shall be corrected by the Contractor on the next update schedule.

COMPUTER SOFTWARE

The Contractor shall submit to the Engineer for approval a description of proposed software before delivery. The software shall be the current version of Primavera SureTrak Project Manager for Windows, or equal, and shall be compatible with Windows NT (version 4.0) operating system. If software other than SureTrak is proposed, it shall be capable of generating files that can be imported into SureTrak.

The Contractor shall furnish schedule software and all original software instruction manuals to the Engineer with submittal of the baseline schedule. The furnished schedule software shall become the property of the State and will not be returned to the Contractor. The State will compensate the Contractor in conformance with the provisions in Section 4-1.03, "Extra Work," of the Standard Specifications for replacement of software which is damaged, lost or stolen after delivery to the Engineer.

The Contractor shall instruct the Engineer in the use of the software and provide software support until the contract is accepted. Within 20 working days of contract approval, the Contractor shall provide a commercial 8-hour training session for 2 Department employees in the use of the software at a location acceptable to the Engineer. It is recommended that the Contractor also send at least 2 employees to the same training session to facilitate development of similar knowledge and skills in the use of the software. If software other than SureTrak is furnished, then the training session shall be a total of 16-hours for each Department employee.

NETWORK DIAGRAMS, REPORTS AND DATA

The Contractor shall include the following for each schedule submittal:

- A. Two sets of originally plotted, time-scaled network diagrams.
- B. Two copies of a narrative report.
- C. Two copies of each of 3 sorts of the CPM software-generated tabular reports.
- D. One 1.44-megabyte 90 mm (3.5 inch) floppy diskette containing the schedule data.

The time-scaled network diagrams shall conform to the following:

- A. Show a continuous flow of information from left to right.
- B. Be based on early start and early finish dates of activities.
- C. Clearly show the primary paths of criticality using graphical presentation.
- D. Be prepared on E-size sheets, 860 mm x 1120 mm (34 inch x 44 inch).
- E. Include a title block and a timeline on each page.

The narrative report shall be organized in the following sequence with all applicable documents included:

- A. Contractor's transmittal letter.
- B. Work completed during the period.
- C. Identification of unusual conditions or restrictions regarding labor, equipment or material; including multiple shifts, 6-day work weeks, specified overtime or work at times other than regular days or hours.
- D. Description of the current critical path.
- E. Changes to the critical path and scheduled completion date since the last schedule submittal.
- F. Description of problem areas.
- G. Current and anticipated delays:
 - 1. Cause of delay.
 - 2. Impact of delay on other activities, milestones and completion dates.
 - 3. Corrective action and schedule adjustments to correct the delay.
- H. Pending items and status thereof:
 - 1. Permits
 - 2. Change orders
 - 3. Time adjustments
 - 4. Non-compliance notices
- I. Reasons for an early or late scheduled completion date in comparison to the contract completion date.

Tabular reports shall be software-generated and provide information for each activity included in the project schedule. Three different reports shall be sorted by (1) activity number, (2) early start and (3) total float. Tabular reports shall be 215 mm x 280 mm (8 1/2 inch x 11 inch) in size and shall include, as a minimum, the following applicable information:

- A. Data date
- B. Activity number and description
- C. Predecessor and successor activity numbers and descriptions
- D. Activity codes
- E. Scheduled, or actual and remaining durations (work days) for each activity
- F. Earliest start (calendar) date
- G. Earliest finish (calendar) date
- H. Actual start (calendar) date
- I. Actual finish (calendar) date
- J. Latest start (calendar) date
- K. Latest finish (calendar) date
- L. Free float (work days)
- M. Total float (work days)

- N. Percentage of activity complete and remaining duration for incomplete activities.
- O. Lags
- P. Required constraints

Schedule submittals will only be considered complete when all documents and data have been provided as described above.

PRE-CONSTRUCTION SCHEDULING CONFERENCE

The Contractor shall schedule and the Engineer will conduct a pre-construction scheduling conference with the Contractor's project manager and construction scheduler within 10 working days of the approval of the contract. At this meeting the Engineer will review the requirements of this section of the special provisions with the Contractor.

The Contractor shall submit a general time-scaled logic diagram displaying the major activities and sequence of planned operations and shall be prepared to discuss the proposed work plan and schedule methodology that comply with the requirements of these special provisions. If the Contractor proposes deviations to the construction staging of the project, then the general time-scaled logic diagram shall also display the deviations and resulting time impacts. The Contractor shall be prepared to discuss the proposal.

At this meeting, the Contractor shall additionally submit the alphanumeric coding structure and the activity identification system for labeling the work activities. To easily identify relationships, each activity description shall indicate its associated scope or location of work by including such terms as quantity of material, type of work, bridge number, station to station location, side of highway (such as left, right, northbound, southbound), lane number, shoulder, ramp name, ramp line descriptor or mainline.

The Engineer will review the logic diagram, coding structure, and activity identification system, and provide any required baseline schedule changes to the Contractor for implementation.

BASELINE SCHEDULE

Beginning the week following the pre-construction scheduling conference, the Contractor shall meet with the Engineer weekly until the baseline schedule is accepted by the Engineer to discuss schedule development and resolve schedule issues.

The Contractor shall submit to the Engineer a baseline schedule within 20 working days of approval of the contract. The Contractor shall allow 3 weeks for the Engineer's review after the baseline schedule and all support data are submitted. In addition, the baseline schedule submittal will not be considered complete until the computer software is delivered and installed for use in review of the schedule.

The baseline schedule shall include the entire scope of work and how the Contractor plans to complete all work contemplated. The baseline schedule shall show the activities that define the critical path. Multiple critical paths and near-critical paths shall be kept to a minimum. A total of not more than 50 percent of the baseline schedule activities shall be critical or near critical, unless otherwise authorized by the Engineer.

The baseline schedule shall not extend beyond the number of working days specified in these special provisions. The baseline schedule shall have a data date of the first working day of the contract and not include any completed work to date. The baseline schedule shall not attribute negative float or negative lag to any activity.

If the Contractor submits an early completion baseline schedule that shows contract completion in less than 85 percent of the working days specified in these special provisions, the baseline schedule shall be supplemented with resource allocations for every task activity and include time-scaled resource histograms. The resource allocations shall be shown to a level of detail that facilitates report generation based on labor crafts and equipment classes for the Contractor and subcontractors. The Contractor shall use average composite crews to display the labor loading of on-site construction activities. The Contractor shall optimize and level labor to reflect a reasonable plan for accomplishing the work of the contract and to assure that resources are not duplicated in concurrent activities. The time-scaled resource histograms shall show labor crafts and equipment classes to be utilized on the contract. The Engineer may review the baseline schedule activity resource allocations using Means Productivity Standards or equivalent to determine if the schedule is practicable.

UPDATE SCHEDULE

The Contractor shall submit an update schedule and meet with the Engineer to review contract progress, on or before the first day of each month, beginning one month after the baseline schedule is accepted. The Contractor shall allow 2 weeks for the Engineer's review after the update schedule and all support data are submitted, except that the review period shall not start until the previous month's required schedule is accepted. Update schedules that are not accepted or rejected within the review period will be considered accepted by the Engineer.

The update schedule shall have a data date of the twenty-first day of the month or other date established by the Engineer. The update schedule shall show the status of work actually completed to date and the work yet to be performed as planned. Actual activity start dates, percent complete and finish dates shall be shown as applicable. Durations for work that has been completed shall be shown on the update schedule as the work actually occurred, including Engineer submittal review and Contractor resubmittal times.

The Contractor may include modifications such as adding or deleting activities or changing activity constraints, durations or logic that do not (1) alter the critical path(s) or near critical path(s) or (2) extend the scheduled completion date compared to that shown on the current accepted schedule. The Contractor shall state in writing the reasons for any changes to planned work. If any proposed changes in planned work will result in (1) or (2) above, then the Contractor shall submit a time impact analysis as described herein.

TIME IMPACT ANALYSIS

The Contractor shall submit a written time impact analysis (TIA) to the Engineer with each request for adjustment of contract time, or when the Contractor or Engineer consider that an approved or anticipated change may impact the critical path or contract progress.

The TIA shall illustrate the impacts of each change or delay on the current scheduled completion date or internal milestone, as appropriate. The analysis shall use the accepted schedule that has a data date closest to and prior to the event. If the Engineer determines that the accepted schedule used does not appropriately represent the conditions prior to the event, the accepted schedule shall be updated to the day before the event being analyzed. The TIA shall include an impact schedule developed from incorporating the event into the accepted schedule by adding or deleting activities, or by changing durations or logic of existing activities. If the impact schedule shows that incorporating the event modifies the critical path and scheduled completion date of the accepted schedule, the difference between scheduled completion dates of the two schedules shall be equal to the adjustment of contract time. The Engineer may construct and utilize an appropriate project schedule or other recognized method to determine adjustments in contract time until the Contractor provides the TIA.

The Contractor shall submit a TIA in duplicate within 15 working days of receiving a written request for a TIA from the Engineer. The Contractor shall allow the Engineer 2 weeks after receipt to approve or reject the submitted TIA. All approved TIA schedule changes shall be shown on the next update schedule.

If a TIA submitted by the Contractor is rejected by the Engineer, the Contractor shall meet with the Engineer to discuss and resolve issues related to the TIA. If agreement is not reached, the Contractor will be allowed 15 days from the meeting with the Engineer to give notice in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications. The Contractor shall only show actual as-built work, not unapproved changes related to the TIA, in subsequent update schedules. If agreement is reached at a later date, approved TIA schedule changes shall be shown on the next update schedule. The Engineer will withhold remaining payment on the schedule contract item if a TIA is requested by the Engineer and not submitted by the Contractor within 15 working days. The schedule item payment will resume on the next estimate after the requested TIA is submitted. No other contract payment will be retained regarding TIA submittals.

FINAL UPDATE SCHEDULE

The Contractor shall submit a final update, as-built schedule with actual start and finish dates for the activities, within 30 days after completion of contract work. The Contractor shall provide a written certificate with this submittal signed by the Contractor's project manager and an officer of the company stating, "To my knowledge and belief, the enclosed final update schedule reflects the actual start and finish dates of the actual activities for the project contained herein." An officer of the company may delegate in writing the authority to sign the certificate to a responsible manager.

RETENTION

The Department will retain an amount equal to 25 percent of the estimated value of the work performed during each estimate period in which the Contractor fails to submit an acceptable schedule conforming to the requirements of these special provisions as determined by the Engineer. Schedule retentions will be released for payment on the next monthly estimate for partial payment following the date that acceptable schedules are submitted to the Engineer or as otherwise specified herein. Upon completion of all contract work and submittal of the final update schedule and certification, any remaining retained funds associated with this section, "Progress Schedule (Critical Path Method)", will be released for payment. Retentions held in conformance with this section shall be in addition to other retentions provided for in the contract. No interest will be due the Contractor on retention amounts.

PAYMENT

Progress schedule (critical path method) will be paid for at a lump sum price. The contract lump sum price paid for progress schedule (critical path method) shall include full compensation for furnishing all labor, material, tools, equipment, and incidentals, including computer software, and for doing all the work involved in preparing, furnishing, and updating schedules, and instructing and assisting the Engineer in the use of computer software, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Payments for the progress schedule (critical path method) contract item will be made progressively as follows:

- A. A total of 25 percent of the item amount or a total of 25 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon achieving all of the following:
 1. Completion of 5 percent of all contract item work.
 2. Acceptance of all schedules and TIAs required to the time when 5 percent of all contract item work is complete.
 3. Delivery of schedule software to the Engineer.
 4. Completion of required schedule software training.
- B. A total of 50 percent of the item amount or a total of 50 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon completion of 25 percent of all contract item work and acceptance of all schedules and TIAs required to the time when 25 percent of all contract item work is complete.
- C. A total of 75 percent of the item amount or a total of 75 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon completion of 50 percent of all contract item work and acceptance of all schedules and TIAs required to the time when 50 percent of all contract item work is complete.
- D. A total of 100 percent of the item amount or a total of 100 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon completion of all contract item work, acceptance of all schedules and TIAs required to the time when all contract item work is complete, and submittal of the certified final update schedule.

If the Contractor fails to complete any of the work or provide any of the schedules required by this section, the Engineer shall make an adjustment in compensation in conformance with the provisions in Section 4-1.03C, "Changes in Character of Work," of the Standard Specifications for the work not performed. Adjustments in compensation for schedules will not be made for any increased or decreased work ordered by the Engineer in furnishing schedules.

10-1.14 OVERHEAD

Overhead shall conform to these special provisions. The Contractor will be compensated for time-related overhead in conformance with these special provisions.

Attention is directed to "Force Account Payment" and "Progress Schedule (Critical Path Method)" of these special provisions.

The provisions in Section 9-1.08, "Adjustment of Overhead Costs," of the Standard Specifications shall not apply.

Time-related overhead shall consist of those overhead costs, including field and home office overhead, that are in proportion to the time required to complete the work. Time-related overhead shall not include costs that are not related to time, including but not limited to, mobilization, licenses, permits, and any other charges incurred only once during the contract.

Field office overhead expenses include time-related costs associated with the normal and recurring operations of the construction project, and shall not include costs directly attributable to any of the work of the contract. Such time-related costs include, but are not limited to, the salaries and benefits of project managers, general superintendents, field office managers and other field office staff assigned to the project, and rent, utilities, maintenance, security, supplies and equipment costs of the project field office.

Home office overhead or general and administrative expenses refer to the fixed costs of operating the Contractor's business. These costs include, but are not limited to, general administration, insurance, personnel and subcontract administration, purchasing, accounting, and project engineering and estimating. The rate of home office overhead shall exclude expenses specifically related to other contracts or other businesses of the Contractor, equipment coordination, material deliveries, and consultant and legal fees.

The quantity of time-related overhead to be paid will be measured by the working day, as specified in the Engineer's Estimate as WDAY. The estimated amount will be based on the number of working days, excluding any days for plant establishment, as specified in "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions. In the event an early completion progress schedule, as defined in "Progress Schedule (Critical Path Method)" of these special provisions, is submitted by the Contractor and approved by the Engineer, the quantity of time-related overhead eligible for payment will be based on the total number of working days as specified in "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions, rather than the Contractor's early completion progress schedule. The quantity of time-related overhead, as measured above, will be adjusted only as a result of suspensions and adjustments of time which revise the current contract completion date and which are also any of the following:

- A. Suspensions of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications, except:
 - 1. Suspensions ordered due to weather conditions being unfavorable for the suitable prosecution of the controlling operation or operations; or
 - 2. Suspensions ordered due to the failure on the part of the Contractor to carry out orders given, or to perform any provision of the contract; or
 - 3. Any other suspensions mutually agreed upon between the Engineer and the Contractor.
- B. Extensions of time granted by the State in conformance with the provisions in the fifth paragraph in Section 8-1.07, "Liquidated Damages," of the Standard Specifications; or
- C. Reductions in contract time set forth in approved contract change orders, in conformance with the provisions in Section 4-1.03, "Changes," of the Standard Specifications.

In the event a cost reduction proposal is submitted by the Contractor, and is subsequently approved by the Engineer, which provides for a reduction in contract time, the contract amount of time-related overhead associated with the reduction in contract time shall be considered as a net savings in the total cost of time-related overhead. The Contractor will be paid 50 percent of the estimated net savings of the time-related overhead, in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

If the quantity of time-related overhead, measured as specified in this special provision, exceeds 149 percent of the number of working days specified in the Engineer's Estimate, the Contractor shall, within 60 days of the Engineer's written request, submit to the Engineer an audit examination and report performed by an independent Certified Public Accountant of the Contractor's actual overhead costs. The independent Certified Public Accountant's audit examination shall be performed in conformance with the requirements of the American Institute of Certified Public Accountants Attestation Standards. The audit examination and report shall depict the Contractor's project and company-wide financial records and shall specify the actual overall average daily rates for both field and home office overhead for the entire duration of the project, and whether the costs have been properly allocated. The rates of field and home office overhead shall exclude all unallowable costs as determined in the Federal Acquisition Regulations, 48 CFR, Chapter 1, Part 31. The audit examination shall determine if the rates of field and home office overhead:

- A. are allowable in conformance with the requirements of the Federal Acquisition Regulations, 48 CFR, Chapter 1, Part 31;
- B. are adequately supported by reliable documentation; and
- C. related solely to the project under examination.

Upon the Engineer's written request, the Contractor shall make its financial records available for audit by the State for the purpose of verifying the actual rate of time-related overhead specified in the audit submitted by the Contractor. The actual rate of time-related overhead specified in the audit, submitted by the Contractor, will be subject to approval by the Engineer.

If the Engineer elects, or if requested in writing by the Contractor, contract item payments for time-related overhead, in excess of 149 percent of the number of working days designated in the Engineer's Estimate, will be adjusted to reflect the actual rate.

The cost of performing an audit examination and submitting the report, requested by the Engineer, will be borne equally by the State and the Contractor. The division of the cost will be made by determining the cost of providing an audit examination in conformance with the provisions of Section 9-1.03B, "Work performed by Special Forces or Other Special Services" of the Standard Specifications, and paying to the Contractor one-half of that cost.

The contract price paid per working day for time-related overhead shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in time-related overhead, complete in place, including all field and home office overhead costs incurred by the Contractor and by any joint venture partner, subcontractor, supplier or other party associated with the Contractor, and the Contractor's share of costs of audits of overhead costs requested by the Engineer, as specified in these special provisions, and as directed by the Engineer. The provisions in Sections 4-1.03B, "Increased or Decreased Quantities," 4-1.03C, "Changes in Character of the Work," of the Standard Specifications shall not apply to time-related overhead.

Full compensation for additional overhead costs involved in the performance of extra work at force account shall be considered as included in the markups specified in "Force Account Payment," of these special provisions.

Full compensation for additional overhead cost involved in performing additional contract item work that is not a controlling operation and for all overhead, other than the time-related overhead measured and paid for as specified in this section "Overhead", shall be considered as included in the various items of work involved, and no additional compensation will be allowed therefor.

For the purpose of making partial payments pursuant to the provisions in Section 9-1.06, "Partial Payments," of the Standard Specifications, the number of working days to be paid for time-related overhead in each monthly partial payment will be the number of working days, specified above to be measured for payment, that occurred during that monthly estimate period. The amount earned per working day for time-related overhead shall be either the contract item price, or 20 percent of the original total contract amount divided by the number of working days specified in "Beginning of Work, Time of Completion and Liquidated Damages," of these special provisions, whichever is the lesser.

After all work has been completed, except plant establishment work, as provided in Section 20-4.08, "Plant Establishment Work," of the Standard Specifications, the amount, if any, of the total contract item price for time-related overhead not yet paid will be included for payment in the first estimate made after completion of all roadway construction work, in conformance with the provisions in Section 9-1.06, "Partial Payments," of the Standard Specifications.

10-1.15 OBSTRUCTIONS

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

It is anticipated that the following utility facilities will be relocated prior to the profile adjustment of Prunedale North Road and to the dates shown:

Utility	Location	Date
100-mm steel gas line	8695 Prunedale Road, Salinas, CA 93901	June 2003

Installation of the following utility facilities will require coordination with the Contractor's operations. The Contractor shall make the necessary arrangements with the utility company, through the Engineer, and shall submit a schedule of work, verified by a representative of the utility company, to the Engineer. The schedule of work shall provide not less than the following number of working days, as defined in Section 8-1.06, "Time of Completion," of the Standard Specifications for the utility company to complete their work:

Utility (address)	Location	Working Days
PG&E P. O. Box 81171 Salinas, CA 93912-1171	8695 Prunedale Road	35

In the event that the utility facilities mentioned above are not removed or relocated by the date specified and, if in the opinion of the Engineer, the Contractor's operations are delayed or interfered with by reason of the utility facilities not being removed or relocated by the date specified, the State will compensate the Contractor for the delays to the extent provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications, and not otherwise, except as provided in Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

10-1.16 MOBILIZATION

Mobilization shall conform to the provisions in Section 11, "Mobilization," of the Standard Specifications.

10-1.17 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES

Flagging, signs, and all other traffic control devices furnished, installed, maintained, and removed when no longer required shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Category 1 traffic control devices are defined as those devices that are small and lightweight (less than 45 kg), and have been in common use for many years. The devices shall be known to be crashworthy by crash testing, crash testing of similar devices, or years of demonstrable safe performance. Category 1 traffic control devices include traffic cones, plastic drums, portable delineators, and channelizers.

If requested by the Engineer, the Contractor shall provide written self-certification for crashworthiness of Category 1 traffic control devices. Self-certification shall be provided by the manufacturer or Contractor and shall include the following: date, Federal Aid number (if applicable), expenditure authorization, district, county, route and kilometer post of project limits; company name of certifying vendor, street address, city, state and zip code; printed name, signature and title of certifying person; and an indication of which Category 1 traffic control devices will be used on the project. The Contractor may obtain a standard form for self-certification from the Engineer.

Category 2 traffic control devices are defined as those items that are small and lightweight (less than 45 kg), that are not expected to produce significant vehicular velocity change, but may otherwise be potentially hazardous. Category 2 traffic control devices include: barricades and portable sign supports.

Category 2 devices purchased on or after October 1, 2000 shall be on the Federal Highway Administration (FHWA) Acceptable Crashworthy Category 2 Hardware for Work Zones list. This list is maintained by FHWA and can be located at the following internet address: <http://safety.fhwa.dot.gov/fourthlevel/hardware/listing.cfm?code=workzone>. The Department maintains a secondary list at the following internet address: <http://www.dot.ca.gov/hq/traffops/signtech/signdel/pdf/htm>.

Category 2 devices that have not received FHWA acceptance, and were purchased before October 1, 2000, may continue to be used until they complete their useful service life or until January 1, 2003, whichever comes first. Category 2 devices in use that have received FHWA acceptance shall be labeled with the FHWA acceptance letter number and the name of the manufacturer by the start of the project. The label shall be readable. After January 1, 2003, all Category 2 devices without a label shall not be used on the project.

If requested by the Engineer, the Contractor shall provide a written list of Category 2 devices to be used on the project at least 5 days prior to beginning any work using the devices. For each type of device, the list shall indicate the FHWA acceptance letter number and the name of the manufacturer.

Full compensation for providing self-certification for crashworthiness of Category 1 traffic control devices and for providing a list of Category 2 devices used on the project and labeling Category 2 devices as specified shall be considered as included in the prices paid for the various contract items of work requiring the use of the Category 1 or Category 2 traffic control devices and no additional compensation will be allowed therefor.

10-1.18 CONSTRUCTION AREA SIGNS

Construction area signs shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels.

Attention is directed to "Construction Project Information Signs" of these special provisions regarding the number and type of construction project information signs to be furnished, erected, maintained, and removed and disposed of.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes.

Sign substrates for stationary mounted construction area signs may be fabricated from fiberglass reinforced plastic as specified under "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

10-1.19 MAINTAINING TRAFFIC

Attention is directed to Sections 7-1.08, "Public Convenience," 7-1.09, "Public Safety," and 12, "Construction Area Traffic Control Devices," of the Standard Specifications and to the provisions in "Public Safety" of these special provisions and these special provisions. Nothing in these special provisions shall be construed as relieving the Contractor from the responsibilities specified in Section 7-1.09.

Lane closures shall conform to the provisions in section "Traffic Control System for Lane Closure" of these special provisions.

Personal vehicles of the Contractor's employees shall not be parked on the traveled way or shoulders including any section closed to public traffic.

The Contractor shall notify local authorities of the Contractor's intent to begin work at least 5 days before work is begun. The Contractor shall cooperate with local authorities relative to handling traffic through the area and shall make arrangements relative to keeping the working area clear of parked vehicles.

Whenever vehicles or equipment are parked on the shoulder within 1.8 m of a traffic lane, the shoulder area shall be closed as shown on the plans.

Lanes shall be closed only during the hours shown on the charts included in this section "Maintaining Traffic." Except work required under Sections 7-1.08 and 7-1.09, work that interferes with public traffic shall be performed only during the hours shown for lane closures.

Designated legal holidays are: January 1st, the third Monday in February, the last Monday in May, July 4th, the first Monday in September, November 11th, Thanksgiving Day, and December 25th. When a designated legal holiday falls on a Sunday, the following Monday shall be a designated legal holiday. When November 11th falls on a Saturday, the preceding Friday shall be a designated legal holiday.

Minor deviations from the requirements of this section concerning hours of work which do not significantly change the cost of the work may be permitted upon the written request of the Contractor, if in the opinion of the Engineer, public traffic will be better served and the work expedited. These deviations shall not be adopted by the Contractor until the Engineer has approved the deviations in writing. All other modifications will be made by contract change order.

Chart No. 1 Multilane Lane Requirements																										
Location: On Route 101 Northbound from KP 152.8 to 154.1 (PM 95.4/95.7)																										
FROM HOUR TO HOUR	a.m.												p.m.													
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	
Mondays through Thursdays	1	1	1	1	1																		1	1	1	1
Fridays	1	1	1	1	1																					
Saturdays																										
Sundays																									1	1
Day before designated legal holiday	1	1	1	1	1																					
Designated legal holidays																										

Chart No. 3																									
Multilane Lane Requirements																									
Location: On Route 101 Southbound from KP 152.8 to 154.1 (PM 95.4/95.7)																									
FROM HOUR TO HOUR	a.m.											p.m.													
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1	1																	1	1	1
Fridays	1	1	1	1	1	1																			
Saturdays																									
Sundays																								1	1
Day before designated legal holiday	1	1	1	1	1	1																			
Designated legal holidays																									

Legend:

1 One lane open in direction of travel

No lane closure allowed

REMARKS: This lane closure chart is applicable the Tuesday after Memorial Day until the Tuesday after Labor Day.

Chart No. 4																									
Multilane Lane Requirements																									
Location: On Route 101 Southbound from KP 152.8 to 154.1 (PM 95.4/95.7)																									
FROM HOUR TO HOUR	a.m.											p.m.													
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1	1																1	1	1	1
Fridays	1	1	1	1	1	1																			
Saturdays																									
Sundays																							1	1	1
Day before designated legal holiday	1	1	1	1	1	1																			
Designated legal holidays																									

Legend:

1 One lane open in direction of travel

No lane closure allowed

REMARKS: This lane closure chart is applicable the Tuesday after Labor Day until the Tuesday after Memorial Day.

Chart No. 5																									
Two-Lane Conventional Highway Lane Requirements																									
Location: On Route 156 Eastbound and Westbound from KP 23.6 to 24.3 (PM 14.78/15.21)																									
FROM HOUR TO HOUR	a.m.											p.m.													
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	R	R	R	R	R	R																		R	R
Fridays	R	R	R	R	R	R																			
Saturdays																									
Sundays	R	R	R	R	R	R																			R
Day before designated legal holiday																									
Designated legal holidays																									

Legend:

R	A minimum of one paved traffic lane, not less than 3.3 m wide, shall be open for use by public traffic. (Reversing Control).
	No work that interferes with public traffic will be allowed

REMARKS: This lane closure chart is applicable the Tuesday after Memorial Day until the Tuesday after Labor Day.

Chart No. 6																									
Two-Lane Conventional Highway Lane Requirements																									
Location: On Route 156 Eastbound and Westbound from KP 23.6 to 24.3 (PM 14.78/15.21)																									
FROM HOUR TO HOUR	a.m.											p.m.													
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	R	R	R	R	R																			R	R
Fridays	R	R	R	R	R																				
Saturdays																									
Sundays	R	R	R	R	R																				R
Day before designated legal holiday																									
Designated legal holidays																									

Legend:

R	A minimum of one paved traffic lane, not less than 3.3 m wide, shall be open for use by public traffic. (Reversing Control).
	No work that interferes with public traffic will be allowed

REMARKS: This lane closure chart is applicable the Tuesday after Labor Day until the Tuesday after Memorial Day.

Chart No. 7																									
Two-Lane Conventional Highway Lane Requirements																									
Location: Prunedale North and Prunedale South																									
FROM HOUR TO HOUR	a.m.												p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	R	R	R	R	R	R			R	R	R	R	R	R	R	R					R	R	R	R	R
Fridays	R	R	R	R	R	R			R	R	R	R													
Saturdays																									
Sundays	R	R	R	R	R	R			R	R	R	R												R	R
Day before designated legal holiday																									
Designated legal holidays																									

Legend:

<input checked="" type="checkbox"/>	A minimum of one paved traffic lane, not less than 3.3 m wide, shall be open for use by public traffic. (Reversing Control).
<input type="checkbox"/>	No work that interferes with public traffic will be allowed

REMARKS: This lane closure chart is applicable year round. Maximum allowable travel delay of 15 minutes and a maximum queue length of 2.4 km. For daytime lane closures, monitor delay and queue length. Implement contingency plan for lane closure pick-ups if delay or queue length criteria is exceeded.

Chart No. 8																									
Ramp Lane Requirements																									
Location: On Route 101 Northbound and Southbound KP 152.8 to 154.1 (PM 95.4/95.7)																									
FROM HOUR TO HOUR	a.m.												p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	X	X	X	X	X	X																	X	X	X
Fridays	X	X	X	X	X	X																			
Saturdays																									
Sundays																							X	X	
Day before designated legal holiday	X	X	X	X	X	X																			
Designated legal holidays																									

Legend:

<input checked="" type="checkbox"/>	Ramp may be closed
<input type="checkbox"/>	No work that interferes with public traffic will be allowed

REMARKS: This chart is applicable year round. Only one ramp may be closed at any given time. Coordinate ramp closures with highway and ramp closures for Contract No. 05-016174 (San Miguel Canyon Road Interchange). Adjacent ramps in the same direction of travel shall not be closed at the same time.

10-1.20 CLOSURE REQUIREMENTS AND CONDITIONS

Lane closures shall conform to the provisions in "Maintaining Traffic" of these special provisions and these special provisions.

The term closure, as used herein, is defined as the closure of a traffic lane or lanes, including ramp or connector lanes, within a single traffic control system.

CLOSURE SCHEDULE

By noon Monday, the Contractor shall submit a written schedule of planned closures for the following week period, defined as Friday noon through the following Friday noon.

The Closure Schedule shall show the locations and times when the proposed closures are to be in effect. The Contractor shall use the Closure Schedule request forms furnished by the Engineer. Closure Schedules submitted to the Engineer with incomplete, unintelligible or inaccurate information will be returned for correction and resubmittal. The Contractor will be notified of disapproved closures or closures that require coordination with other parties as a condition of approval.

Amendments to the Closure Schedule, including adding additional closures, shall be submitted to the Engineer, in writing, at least 3 working days in advance of a planned closure. Approval of amendments to the Closure Schedule will be at the discretion of the Engineer.

The Contractor shall confirm, in writing, all scheduled closures by no later than 8:00 a.m. 3 working days prior to the date on which the closure is to be made. Approval or denial of scheduled closures will be made no later than 4:00 p.m. 2 working days prior to the date on which the closure is to be made. Closures not confirmed or approved will not be allowed.

Confirmed closures that are cancelled due to unsuitable weather may be rescheduled at the discretion of the Engineer for the following working day.

CONTINGENCY PLAN

The Contractor shall prepare a contingency plan for reopening closures to public traffic. The Contractor shall submit the contingency plan for a given operation to the Engineer within one working day of the Engineer's request.

LATE REOPENING OF CLOSURES

If a closure is not reopened to public traffic by the specified time, work shall be suspended in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. The Contractor shall not make any further closures until the Engineer has accepted a work plan, submitted by the Contractor, that will insure that future closures will be reopened to public traffic at the specified time. The Engineer will have 2 working days to accept or reject the Contractor's proposed work plan. The Contractor will not be entitled to any compensation for the suspension of work resulting from the late reopening of closures.

For each 10-minute interval, or fraction thereof past the time specified to reopen the closure, the Department will deduct \$1,800 per interval from moneys due or that may become due the Contractor under the contract.

COMPENSATION

The Contractor shall notify the Engineer of any delay in the Contractor's operations due to the following conditions, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of those conditions, and the Contractor's loss due to that delay could not have been avoided by rescheduling the affected closure or by judicious handling of forces, equipment and plant, the delay will be considered a right of way delay within the meaning of Section 8-1.09, "Right of Way Delays," and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09:

- A. The Contractor's proposed Closure Schedule is denied and his planned closures are within the time frame allowed for closures in "Maintaining Traffic" of these special provisions, except that the Contractor will not be entitled to any compensation for amendments to the Closure Schedule that are not approved.
- B. The Contractor is denied a confirmed closure.

Should the Engineer direct the Contractor to remove a closure prior to the time designated in the approved Closure Schedule, any delay to the Contractor's schedule due to removal of the closure will be considered a right of way delay within the meaning of Section 8-1.09, "Right of Way Delays," and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09.

10-1.21 CONSTRUCTION ZONE ENHANCED ENFORCEMENT

Construction zone enhanced enforcement will be provided by the State as directed by the Engineer and in conformance with these special provisions. Construction zone enhanced enforcement shall consist of the presence of the California Highway Patrol (CHP) within and near the limits of construction during specified stages of work to control the movement of public traffic within the work zone. A total of 1400 hours of California Highway Patrol support is available.

Construction zone enhanced enforcement will be required during the performance of any night work that interferes with public traffic.

In addition to the night work requiring CHP presence, the Engineer will provide additional CHP support as deemed appropriate by the Engineer.

The Contractor shall submit a schedule to the Engineer at least 15 days prior to the performance of work requiring construction zone enhanced enforcement. The schedule shall include all activities requiring construction zone enhanced enforcement and the estimated hours of CHP support required for each activity. The work shall be performed within the number of hours allocated for CHP support.

The Contractor may request additional CHP support for other times and in support of other work activities. The Contractor shall bear the costs and expenses for additional CHP support. The CHP shall be compensated at an agreed rate of \$55 per hour per CHP Officer. The agreed rate shall be considered full compensation for each hour, or portion thereof, that a CHP Officer is performing construction area enhanced enforcement. There will be no markup applied to any expenses connected with CHP support. The costs and expenses for requested additional CHP support will be deducted from moneys due to the Contractor.

The Engineer shall make all arrangements with the CHP for scheduled and requested additional construction zone enhanced enforcement.

CHP support shall be scheduled in compliance with the provisions in "Closure Requirements and Conditions" of these special provisions. The Contractor will be notified in writing of assigned CHP support when the Contractor is informed of the approval of requested closures.

Cancellations to previously approved closures scheduled to include construction zone enhancement enforcement shall be submitted in writing to the Engineer at least 36 hours prior to the time when the closure is to be in place. Written notices of cancellation for a closure shall be delivered to the Engineer between the hours of 7:00 a.m. and 3:00 p.m., Monday through Friday, excluding designated legal holidays.

Cancellations with less than the 36-hour written notice may result in charges from the CHP. The Contractor shall bear any costs and expenses resulting from cancellations with less than the 36 hour written notice, except cancellations due to weather or circumstances beyond the control of the Contractor, as determined by the Engineer. The CHP shall be compensated not less than \$50.00 per hour and no greater than 4 hours of overtime pay per CHP Officer scheduled to participate in the construction zone enhancement enforcement that is cancelled. The costs and expenses incurred for late cancellations will be deducted from moneys due or that may become due the Contractor.

The presence of the California Highway Patrol will not relieve the Contractor of responsibility of providing for the safety of the public in conformance with the requirements in Section 7-1.09, "Public Safety," nor relieve the Contractor from the responsibility for damage in conformance with the requirements in Section 7-1.12, "Responsibility for Damage," of the Standard Specifications.

10-1.22 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE

A traffic control system shall consist of closing traffic lanes and ramps in conformance with the details shown on the plans, the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, the provisions under "Maintaining Traffic" and "Construction Area Signs" of these special provisions, and these special provisions.

The provisions in this section will not relieve the Contractor from the responsibility to provide additional devices or take measures as may be necessary to comply with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications.

During traffic stripe operations and pavement marker placement operations using bituminous adhesive, traffic shall be controlled, at the option of the Contractor, with either stationary or moving lane closures. During other operations, traffic shall be controlled with stationary lane closures. Attention is directed to the provisions in Section 84-1.04, "Protection From Damage," and Section 85-1.06, "Placement," of the Standard Specifications.

If components in the traffic control system are displaced or cease to operate or function as specified, from any cause, during the progress of the work, the Contractor shall immediately repair the components to the original condition or replace the components and shall restore the components to the original location.

STATIONARY LANE CLOSURE

When lane and ramp closures are made for work periods only, at the end of each work period, all components of the traffic control system, except portable delineators placed along open trenches or excavation adjacent to the traveled way, shall be removed from the traveled way and shoulder. If the Contractor so elects, the components may be stored at selected central locations designated by the Engineer within the limits of the highway right of way.

Each vehicle used to place, maintain and remove components of a traffic control system on multilane highways shall be equipped with a Type II flashing arrow sign which shall be in operation when the vehicle is being used for placing, maintaining or removing the components. Vehicles equipped with Type II flashing arrow sign not involved in placing, maintaining or removing the components when operated within a stationary type lane closure shall only display the caution display mode. The sign shall be controllable by the operator of the vehicle while the vehicle is in motion. The flashing arrow sign shown on the plans shall not be used on the vehicles which are doing the placing, maintaining and removing of components of a traffic control system and shall be in place before a lane closure requiring the sign's use is completed.

One-way traffic shall be controlled through the project in conformance with the plan entitled "Traffic Control System for Lane Closure on Two Lane Conventional Highways" and these special provisions.

Utilizing a pilot car will be at the option of the Contractor. If the Contractor elects to use a pilot car, the cones shown along the centerline on the plan need not be placed. The pilot car shall have radio contact with personnel in the work area. The maximum speed of the pilot car through the traffic control zone shall be 40 kilometers per hour (25 mph).

MOVING LANE CLOSURE

Flashing arrow signs used in moving lane closures shall be truck-mounted. Flashing arrow signs shall be in the caution display mode when used on 2-lane highways. Changeable message signs used in moving lane closure operations shall conform to the provisions in Section 12-3.12, "Portable Changeable Message Signs," of the Standard Specifications, except the signs shall be truck-mounted. The full operation height of the bottom of the sign may be less than 2.1 m above the ground, but should be as high as practicable.

Truck-mounted attenuators (TMA) for use in moving lane closures shall be any of the following approved models, or equal:

- A. Hexfoam TMA Series 3000, Alpha 1000 TMA Series 1000 and Alpha 2001 TMA Series 2001, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076, Telephone (312) 467-6750.
 - 1. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX (916) 387-9734.
 - 2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274.
- B. Cal T-001 Model 2 or Model 3, manufacturer and distributor; Hexcel Corporation, 11711 Dublin Boulevard, P.O. Box 2312, Dublin, CA 94568, Telephone (510) 828-4200.
- C. Renco Rengard Model Nos. CAM 8-815 and RAM 8-815, manufacturer and distributor, Renco Inc., 1582 Pflugerville Loop Road, P.O. Box 730, Pflugerville, TX 78660-0730, Telephone 1-800-654-8182.

Each TMA shall be individually identified with the manufacturer's name, address, TMA model number, and a specific serial number. The names and numbers shall each be a minimum 13 mm high and located on the left (street) side at the lower front corner. The TMA shall have a message next to the name and model number in 13 mm high letters which states, "The bottom of this TMA shall be ____ mm \pm ____ mm above the ground at all points for proper impact performance." A TMA which is damaged or appears to be in poor condition shall not be used unless recertified by the manufacturer. The Engineer shall be the sole judge whether used TMAs supplied under this contract need recertification. Each unit shall be certified by the manufacturer to meet the requirements for TMAs in conformance with the standards established by the Transportation Laboratory.

Approvals for new TMA designs proposed as equal to the above approved models shall be in conformance with the procedures (including crash testing) established by the Transportation Laboratory. For information regarding submittal of new designs for evaluation contact: Transportation Laboratory, 5900 Folsom Boulevard, Sacramento, CA 95819.

New TMAs proposed as equal to approved TMAs or approved TMAs determined by the Engineer to need recertification shall not be used until approved or recertified by the Transportation Laboratory.

PAYMENT

The contract lump sum price paid for traffic control system shall include full compensation for furnishing all labor (except for flagging costs), materials (including signs), tools, equipment, and incidentals, and for doing all the work involved in placing, removing, storing, maintaining, moving to new locations, replacing, and disposing of the components of the traffic control system and for furnishing and operating the pilot car, (including driver, radios, other equipment, and labor required), as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer. Flagging costs will be paid for as provided in Section 12-2.02, "Flagging Costs," of the Standard Specifications.

The adjustment provisions in Section 4-1.03, "Changes," of the Standard Specifications shall not apply to the item of traffic control system. Adjustments in compensation for traffic control system will be made only for increased or decreased traffic control system required by changes ordered by the Engineer and will be made on the basis of the cost of the increased or decreased traffic control necessary. The adjustment will be made on a force account basis as provided in Section 9-1.03, "Force Account Payment," of the Standard Specifications for increased work, and estimated on the same basis in the case of decreased work.

Traffic control system required by work which is classed as extra work, as provided in Section 4-1.03D of the Standard Specifications, will be paid for as a part of the extra work.

10-1.23 TEMPORARY PAVEMENT DELINEATION

Temporary pavement delineation shall be furnished, placed, maintained, and removed in conformance with the provisions in Section 12-3.01, "General," of the Standard Specifications and these special provisions. Nothing in these special provisions shall be construed as reducing the minimum standards specified in the Manual of Traffic Controls published by the Department or as relieving the Contractor from the responsibilities specified in Section 7-1.09, "Public Safety," of the Standard Specifications.

GENERAL

Whenever the work causes obliteration of pavement delineation, temporary or permanent pavement delineation shall be in place prior to opening the traveled way to public traffic. Laneline or centerline pavement delineation shall be provided at all times for traveled ways open to public traffic. On multilane roadways (freeways and expressways) edgeline delineation shall be provided at all times for traveled ways open to public traffic.

The Contractor shall perform the work necessary to establish the alignment of temporary pavement delineation, including required lines or marks. Surfaces to receive temporary pavement delineation shall be dry and free of dirt and loose material. Temporary pavement delineation shall not be applied over existing pavement delineation or other temporary pavement delineation. Temporary pavement delineation shall be maintained until superseded or replaced with a new pattern of temporary pavement delineation or permanent pavement delineation.

Temporary pavement markers, including underlying adhesive, and removable traffic tape which are applied to the final layer of surfacing or existing pavement to remain in place or which conflicts with a subsequent or new traffic pattern for the area shall be removed when no longer required for the direction of public traffic, as determined by the Engineer.

TEMPORARY LANELINE AND CENTERLINE DELINEATION

Whenever lanelines or centerlines are obliterated and temporary pavement delineation to replace the lines is not shown on the plans, the minimum laneline and centerline delineation to be provided for that area shall be temporary pavement markers placed at longitudinal intervals of not more than 7.3 m. The temporary pavement markers shall be the same color as the laneline or centerline the pavement markers replace. Temporary pavement markers shall be, at the option of the Contractor, one of the temporary pavement markers listed for short term day/night use (14 days or less) or long term day/night use (6 months or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. The temporary pavement markers shall be placed in conformance with the manufacturer's instructions. Temporary pavement markers for long term day/night use (6 months or less) shall be cemented to the surfacing with the adhesive recommended by the manufacturer, except epoxy adhesive shall not be used to place the temporary pavement markers in areas where removal of the temporary pavement markers will be required.

Temporary laneline or centerline delineation consisting entirely of temporary pavement markers listed for short term day/night use (14 days or less), shall be placed on longitudinal intervals of not more than 7.3 m and shall be used for a maximum of 14 days on lanes opened to public traffic. Prior to the end of the 14 days the permanent pavement delineation shall be placed. If the permanent pavement delineation is not placed within the 14 days, the Contractor shall replace the temporary pavement markers and provide additional temporary pavement delineation and shall bear the cost thereof. The additional temporary pavement delineation to be provided shall be equivalent to the pattern specified for the permanent pavement delineation for the area, as determined by the Engineer.

Full compensation for furnishing, placing, maintaining, and removing the temporary pavement markers for those areas where temporary lane and centerline delineation is not shown on the plans and for providing equivalent patterns of permanent traffic lines for those areas when required, shall be considered as included in the contract prices paid for the items of work that obliterated the lane and centerline pavement delineation and no separate payment will be made therefor.

TEMPORARY EDGELINE DELINEATION

On multilane roadways (freeways and expressways), whenever edgelines are obliterated and temporary pavement delineation to replace those edgelines is not shown on the plans, the edgeline delineation to be provided for those areas adjacent to lanes open to public traffic shall be as follows:

- A. Temporary pavement delineation for right edgelines shall, at the option of the Contractor, consist of either a solid 100-mm wide traffic stripe of the same color as the stripe the temporary edgeline delineation replaces, or traffic cones, portable delineators or channelizers placed at longitudinal intervals not to exceed 30 m.
- B. Temporary pavement delineation for left edgelines shall, at the option of the Contractor, consist of either solid 100-mm wide traffic stripe of the same color as the stripe the temporary edgeline delineation replaces, traffic cones, portable delineators or channelizers placed at longitudinal intervals not to exceed 30 m or temporary pavement markers placed at longitudinal intervals of not more than 1.8 m. Temporary pavement markers used for temporary left edgeline delineation shall be one of the types of temporary pavement markers listed for short term day/night use (14 days or less) or long term day/night use (6 months or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Traffic stripe (100-mm wide) placed as temporary edgeline delineation which will require removal shall conform to the provisions of "Temporary Traffic Stripe (Tape)" of these special provisions. The quantity of temporary traffic stripe (tape) used for this temporary edgeline delineation will not be included in the quantities of tape to be paid for.

The lateral offset for traffic cones, portable delineators or channelizers used for temporary edgeline delineation shall be as determined by the Engineer. If traffic cones or portable delineators are used as temporary pavement delineation for edgelines, the Contractor shall provide personnel to remain at the project site to maintain the cones or delineators during the hours of the day that the portable delineators are in use.

Channelizers used for temporary edgeline delineation shall be the surface mounted type and shall be orange in color. Channelizer bases shall be cemented to the pavement in the same manner provided for cementing pavement markers to pavement in "Pavement Markers" of these special provisions, except epoxy adhesive shall not be used to place channelizers on the top layer of pavement. Channelizers shall be, at the Contractor's option, one of the surface mount types (900 mm) listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Temporary edgeline delineation shall be removed when no longer required for the direction of public traffic as determined by the Engineer.

The quantity of channelizers used as temporary edgeline delineation will not be included in the quantity of channelizers to be paid for. Full compensation for furnishing, placing, maintaining and removing temporary edgeline delineation for those areas where temporary edgeline delineation is not shown on the plans shall be considered as included in the contract prices paid for the items of work that obliterated the edgeline pavement delineation and no separate payment will be made therefor.

TEMPORARY TRAFFIC STRIPE (TAPE)

Temporary traffic stripe consisting of removable traffic stripe tape shall be applied at the locations shown on the plans. The temporary traffic stripe tape shall be complete in place at the location shown prior to opening the traveled way to public traffic.

Removable traffic stripe tape shall be the temporary removable traffic stripe tape listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Removable traffic stripe tape shall be applied in conformance with the manufacturer's installation instructions and shall be rolled slowly with a rubber tired vehicle or roller to ensure complete contact with the pavement surface. Traffic stripe tape shall be applied straight on tangent alignment and on a true arc on curved alignment. Traffic stripe tape shall not be applied when the air or pavement temperature is less than 10°C, unless the installation procedures to be used are approved by the Engineer, prior to beginning installation of the tape.

When removable traffic stripe tape is specified for temporary left edgeline delineation, temporary pavement markers placed at longitudinal intervals of not more than 1.8 m may be used in place of the temporary traffic stripe tape. Temporary pavement markers shall be one of the types of temporary pavement markers listed for long term day/night use (6 months or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. When temporary pavement markers are used in place of tape, payment for those temporary pavement markers will be made on the basis of the theoretical length of the temporary traffic stripe (tape) required for the left edgeline which the temporary pavement markers replace.

TEMPORARY PAVEMENT MARKING (TAPE)

Temporary pavement marking consisting of removable pavement marking tape shall be applied at the locations shown on the plans. The temporary pavement marking tape shall be complete in place at the location shown, prior to opening the traveled way to public traffic.

Removable pavement marking tape shall be the temporary removable type pavement marking tape listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions and shall be applied and removed in conformance with the provisions specified for applying and removing the temporary traffic stripe tape.

TEMPORARY PAVEMENT MARKERS

Temporary pavement markers shall be applied at the locations shown on the plans. The pavement markers shall be applied complete in place at the locations shown prior to opening the traveled way to public traffic.

Temporary pavement markers shown on the plans shall be, at the option of the Contractor, one of the temporary pavement markers for long term day/night use (6 months or less) listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Temporary pavement markers shall be placed in conformance with the manufacturer's instructions and shall be cemented to the surfacing with the adhesive recommended by the manufacturer, except epoxy adhesive shall not be used in areas where removal of the pavement markers will be required.

Where the temporary pavement delineation shown on the plans for lanelines or centerlines consists entirely of a pattern of broken traffic stripe and pavement markers, the Contractor may use groups of the temporary pavement markers for long term day/night use (6 months or less) in place of the temporary traffic stripe tape. The groups of pavement markers shall be spaced as shown on the plans for a similar pattern of permanent traffic line, except pavement markers shown to be placed in the gap between the broken traffic stripe shall be placed as part of the group to delineate the pattern of broken temporary traffic stripe. The kind of laneline and centerline delineation selected by the Contractor shall be continuous within a given location. Payment for those temporary pavement markers used in place of temporary traffic stripe will be made on the basis of the theoretical length of the patterns of temporary traffic stripe (tape).

Retroreflective pavement markers conforming to the provisions in "Pavement Markers" of these special provisions may be used in place of temporary pavement markers for long term day/night use (6 months or less) except to simulate patterns of broken traffic stripe. Placement of the retroreflective pavement markers used for temporary pavement markers shall conform to the provisions in "Pavement Markers" of these special provisions except the waiting period provisions before placing the pavement markers on new asphalt concrete surfacing as specified in Section 85-1.06, "Placement," of the Standard Specifications shall not apply and epoxy adhesive shall not be used to place pavement markers in areas where removal of the pavement markers will be required.

MEASUREMENT AND PAYMENT

Temporary traffic stripe (tape) will be measured and paid for by the meter, measured along the line of the stripe, with deductions for gaps in broken traffic stripes. Double and 200-mm temporary traffic stripes, shown on the plans as tape, will be measured as 2 temporary traffic stripes (tape). Temporary pavement marking (tape) will be measured and paid for by the square meter for actual area of the pavement marking that receives tape.

Temporary pavement markers, shown on the plans, will be measured and paid for by the unit in the same manner specified for retroreflective pavement markers in Section 85-1.08, "Measurement," and Section 85-1.09, "Payment," of the Standard Specifications. Temporary pavement markers used for temporary laneline and centerline delineation for areas which are not shown on the plans will not be included in the quantities of temporary pavement markers to be paid for. Full compensation for removing temporary pavement markers, when no longer required, shall be considered as included in the contract unit price paid for temporary pavement marker and no separate payment will be made therefor.

The contract price paid per meter for temporary traffic stripe (tape) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying, maintaining and removing temporary traffic stripe tape, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract price paid per square meter for temporary pavement marking (tape) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying, maintaining and removing temporary pavement marking tape, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.24 BARRICADE

Barricades shall be furnished, placed and maintained at the locations shown on the plans, specified in the Standard Specifications or in these special provisions or where designated by the Engineer. Barricades shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to "Prequalified and Tested Signing and Delineation Materials" of these special provisions regarding retroreflective sheeting for barricades.

Construction area sign and marker panels conforming to the provisions in Section 12-3.06, "Construction Area Signs," of the Standard Specifications shall be installed on barricades in a manner determined by the Engineer at the locations shown on the plans.

Sign panels for construction area signs and marker panels installed on barricades shall conform to the provisions in Section 12-3.06A, "Stationary Mounted Signs," of the Standard Specifications.

Full compensation for furnishing, installing, maintaining, and removing construction area signs and marker panels on barricades shall be considered as included in the contract unit price paid for the type of barricade involved and no separate payment will be made therefor.

Barricades shown on the plans as part of a traffic control system will be paid for as provided in "Traffic Control System for Lane Closure" of these special provisions and will not be included in the count for payment of barricades.

10-1.25 PORTABLE CHANGEABLE MESSAGE SIGN

Two portable changeable message signs shall be furnished, placed, operated, and maintained for each freeway lane closure and one for each ramp closure at locations designated by the Engineer, and placed at locations shown on the plans, and shall conform to the provisions of Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

For one-way reversing lane closures, a portable changeable message sign shall be placed for each direction of travel. The exact locations will be designated by the Engineer.

All portable changeable message signs will be paid for on a lump sum basis.

The contract lump sum price paid for portable changeable message sign shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing, placing, operating, maintaining, repairing, replacing, transporting from location to location, and removing the portable changeable message signs, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.26 TEMPORARY RAILING

Temporary railing (Type K) shall be placed as shown on the plans, as specified in the Standard Specifications or these special provisions or where ordered by the Engineer and shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Reflectors on temporary railing (Type K) shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Temporary railing (Type K) shall conform to the details shown on Standard Plan T3. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Attention is directed to "Public Safety" and "Order of Work" of these special provisions.

Temporary railing (Type K) placed in conformance with the provisions in "Public Safety" of these special provisions will be neither measured nor paid for.

10-1.27 CHANNELIZER

Channelizers shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Channelizers shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

At the time of completion of the project, certain channelizers shall be left in place as determined by the Engineer. In addition to the contract unit price paid for channelizer (surface mounted), the cost of leaving the channelizers in place will be paid for at the contract unit price for channelizer (surface mounted) (left in place).

When no longer required for the work as determined by the Engineer, channelizers (except channelizers to be left in place) and underlying adhesive used to cement the channelizer bases to the pavement shall be removed. Removed channelizers and adhesive shall become the property of the Contractor and shall be removed from the site of work.

10-1.28 TEMPORARY CRASH CUSHION MODULE

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety" and "Order of Work" of these special provisions.

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 4.6 m or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

At the Contractor's option, the modules for use in sand filled temporary crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or Traffix Sand Barrels manufactured after March 31, 1997, or equal:

- A. Energite III and Fitch Inertial Modules, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076. Telephone 1-312-467-6750, FAX 1-800-770-6755
 - 1. Distributor (North): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828. Telephone 1-800-884-8274, FAX 1-916-387-9734
 - 2. Distributor (South): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805. Telephone 1-800-222-8274, FAX 1-714-937-1070
- B. Traffix Sand Barrels, manufactured by Traffix Devices, Inc., 220 Calle Pintoresco, San Clemente, CA 92672. Telephone 1-949 361-5663, FAX 1-949 361-9205
 - 1. Distributor (North): United Rentals, Inc., 1533 Berger Drive, San Jose, CA 95112. Telephone 1-408 287-4303, FAX 1-408 287-1929
 - 2. Distributor (South): Statewide Safety & Sign, Inc., P.O. Box 1440, Pismo Beach, CA 93448. Telephone 1-800-559-7080, FAX 1-805 929-5786

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in kilograms for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

Temporary crash cushion modules shall be placed on movable pallets or frames conforming to the dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 3.6 m of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

Temporary crash cushion modules will be measured by the unit as determined from the actual count of modules used in the work or ordered by the Engineer at each location. Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions and modules placed in excess of the number specified or shown will not be measured nor paid for.

Repairing modules damaged by public traffic will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Modules damaged beyond repair by public traffic, when ordered by the Engineer, shall be removed and replaced immediately by the Contractor. Modules replaced due to damage by public traffic will be measured and paid for as temporary crash cushion module.

If the Engineer orders a lateral move of the sand filled temporary crash cushions and the repositioning is not shown on the plans, moving the sand filled temporary crash cushion will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications and these temporary crash cushion modules will not be counted for payment in the new position.

The contract unit price paid for temporary crash cushion module shall include full compensation for furnishing all labor, materials (including sand, pallets or frames and marker panels), tools, equipment, and incidentals, and for doing all the work involved in furnishing, installing, maintaining, moving, and resetting during a work period for access to the work, and removing from the site of the work when no longer required (including those damaged by public traffic) sand filled temporary crash cushion modules, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.29 EXISTING HIGHWAY FACILITIES

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

REPAIR EXISTING ROADBED

Where shown on the plans or designated by the Engineer, broken, failed or other unsatisfactory portions of the existing roadbed shall be removed and disposed of and the resulting hole shall be backfilled as directed by the Engineer.

Removing and replacing existing pavement will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

REMOVE FENCE

Existing fence, where shown on the plans to be removed, shall be removed and disposed of.

Existing concrete anchors shall be completely removed and disposed of.

Full compensation for remove fence shall be considered as included in the contract price paid per cubic meter for roadway excavation and no separate payment will be made therefor.

REMOVE PAVEMENT MARKER

Existing pavement markers, including underlying adhesive, when no longer required for traffic lane delineation as determined by the Engineer, shall be removed and disposed of.

REMOVE PAINTED TRAFFIC STRIPE AND PAINTED PAVEMENT MARKING

Traffic stripes and pavement markings to be removed shall be removed at the locations shown on the plans and at the locations designated by the Engineer.

REMOVE DRAINAGE FACILITY

Existing pipe and headwalls, where shown on the plans to be removed, shall be completely removed and disposed of.

REMOVE ASPHALT CONCRETE DIKE

Existing asphalt concrete dike, where shown on the plans to be removed, shall be removed.

Prior to removing the dike, the outside edge of the asphalt concrete to remain in place shall be cut on a neat line to a minimum depth of 50 mm.

The dike shall be removed in such a manner that the surfacing which is to remain in place is not damaged.

The dike may be buried in embankments in the same manner provided for burying concrete in embankments in Section 15-3, "Removing Concrete," of the Standard Specifications.

REMOVE ROADSIDE SIGN

Existing roadside signs, at those locations shown on the plans to be removed, shall be removed and disposed of.

Existing roadside signs shall not be removed until replacement signs have been installed or until the existing signs are no longer required for the direction of public traffic, unless otherwise directed by the Engineer.

RECONSTRUCT METAL BEAM GUARD RAILING

Existing metal beam guard railing, where shown on the plans to be reconstructed, shall be reconstructed.

Attention is directed to "Order of Work" of these special provisions regarding the reconstruction of metal beam guard railing at those locations exposed to public traffic.

Cable anchor assemblies or terminal anchor assemblies, including concrete anchors and steel foundation tubes, shall be completely removed and disposed of.

New posts, blocks, and hardware shall be furnished and used to reconstruct metal beam guard railing. New posts and blocks shall conform to the provisions in Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications.

Posts, blocks, and other components of the removed metal beam guard railing, including terminal sections, that are not used in the reconstruction work shall be disposed of.

Full compensation for furnishing and installing new posts, blocks, and hardware; for connecting reconstructed metal beam guard railing to existing structures, other flat concrete surfaces or terminal systems; and for removing and disposing of anchor assemblies shall be considered as included in the contract price paid per meter for reconstruct metal beam guard railing and no separate payment will be made therefor.

Terminal System (Type SRT) for connection to reconstructed metal beam guard railing will be measured and paid for separately in conformance with the provisions in "Terminal System (Type SRT)" of these special provisions.

RELOCATE ROADSIDE SIGN

Existing roadside signs shall be removed and relocated to the new locations shown on the plans.

Each roadside sign shall be installed at the new location on the same day that the sign is removed from its original location.

Two holes shall be drilled in each existing post as required to provide the breakaway feature shown on the plans.

ADJUST INLET

Existing drainage inlets shall be adjusted as shown on the plans.

Portland cement concrete shall be minor concrete or may be produced from commercial quality concrete containing not less than 350 kilograms of cement per cubic meter.

Adjustment of inlets shall be performed prior to paving and shall be limited to the area to be paved or surfaced during the working day in which the adjustment is performed. The top of the inlet grate or cover shall be protected from the asphalt concrete during paving operations by means of heavy plywood covers, steel plate covers or by other methods approved by the Engineer. Excess paving material shall be removed prior to rolling.

REMOVE BASE AND SURFACING

Existing base and bituminous surfacing shown on the plans to be removed, shall be removed to a depth of at least 150 mm below the grade of the existing surfacing. Resulting holes and depressions shall be backfilled with earthy material selected from excavation to the lines and grade established by the Engineer.

Removing base and surfacing will be measured and paid for as roadway excavation.

COLD PLANE ASPHALT CONCRETE PAVEMENT

Existing asphalt concrete pavement shall be cold planed at the locations and to the dimensions shown on the plans.

Planing asphalt concrete pavement shall be performed by the cold planing method. Planing of the asphalt concrete pavement shall not be done by the heater planing method.

Cold planing machines shall be equipped with a cutter head not less than 750 mm in width and shall be operated so that no fumes or smoke will be produced. The cold planing machine shall plane the pavement without requiring the use of a heating device to soften the pavement during or prior to the planing operation.

The depth, width, and shape of the cut shall be as shown on the typical cross sections or as designated by the Engineer. The final cut shall result in a uniform surface conforming to the typical cross sections. The outside lines of the planed area shall be neat and uniform. Planing asphalt concrete pavement operations shall be performed without damage to the surfacing to remain in place.

Planned widths of pavement shall be continuous except for intersections at cross streets where the planing shall be carried around the corners and through the conform lines. Following planing operations, a drop-off of more than 45 mm will not be allowed between adjacent lanes open to public traffic.

Where transverse joints are planed in the pavement at conform lines no drop-off shall remain between the existing pavement and the planed area when the pavement is opened to public traffic. If asphalt concrete has not been placed to the level of existing pavement before the pavement is to be opened to public traffic a temporary asphalt concrete taper shall be constructed. Asphalt concrete for temporary tapers shall be placed to the level of the existing pavement and tapered on a slope of 1:30 (Vertical: Horizontal) or flatter to the level of the planed area.

Asphalt concrete for temporary tapers shall be commercial quality and may be spread and compacted by any method that will produce a smooth riding surface. Temporary asphalt concrete tapers shall be completely removed, including the removal of loose material from the underlying surface, before placing the permanent surfacing. The removed material shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Operations shall be scheduled so that not more than 7 days shall elapse between the time when transverse joints are planed in the pavement at the conform lines and the permanent surfacing is placed at the conform lines.

The material planed from the roadway surface, including material deposited in existing gutters or on the adjacent traveled way, shall be removed and stockpiled, as directed by the Engineer, for later use as shoulder backing. Removal operations of cold planed material shall be concurrent with planing operations and follow within 15 m of the planer, unless otherwise directed by the Engineer.

When shoulder backing operations begin, the cold planing residue shall be removed from stockpiles and deposited in the area of shoulder backing. Planed material used for shoulder backing shall be broken down so that it shall have a maximum size of 25 mm in its greatest diameter.

Cold plane asphalt concrete pavement will be measured by the square meter. The quantity to be paid for will be the actual area of surface cold planed irrespective of the number of passes required to obtain the depth shown on the plans.

The contract price paid per square meter for cold plane asphalt concrete pavement shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in cold planing asphalt concrete surfacing, including furnishing the asphalt concrete for and constructing, maintaining, removing, and disposing of temporary asphalt concrete tapers and for stockpiling cold planing residue, and once shoulder backing operations begin, for excavating, loading, hauling, and depositing cold planing residue in the areas of shoulder backing, as specified in the Standard Specifications and these special provisions and as directed by the Engineer.

CAP INLET

Existing drainage inlets, where shown on the plans to be capped, shall be capped and the bottoms of the inlets shall be rounded with portland cement concrete as shown on the plans.

Portland cement concrete shall be minor concrete or may be produced from commercial quality aggregates and cement containing not less than 350 kg of cement per cubic meter.

Inlets shall be removed to a depth of at least 0.3-m below the grading plane.

Concrete removal shall be performed without damage to portions of the inlet that are to remain in place. Damage to existing concrete, which is to remain in place, shall be repaired by the Contractor to a condition equal to that existing prior to the beginning of removal operations. The repair of existing concrete damaged by the Contractor's operations shall be at the Contractor's expense.

Existing reinforcement that is to be incorporated in the new work shall be protected from damage and shall be thoroughly cleaned of adhering material before being embedded in the new concrete.

The quantity of capping inlets will be determined as units from actual count.

The contract unit price paid for cap inlet shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in capping inlets, including removing portions of inlets, rounding bottoms of inlets, bar reinforcing steel, and structure excavation and structure backfill, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

EXISTING HIGHWAY IRRIGATION FACILITIES

Existing irrigation facilities within the limits of work shall remain in place. Irrigation facilities that are damaged by the Contractor's operation shall be reported immediately to the Engineer.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

REMOVE CONCRETE

Concrete, where shown on the plans to be removed, shall be removed.

The pay quantities of concrete to be removed will be measured by the cubic meter, measured before and during removal operations.

Where no joint exists between concrete to be removed and concrete to remain in place, the concrete shall be cut on a neat line to a minimum depth of 50 mm with a power driven saw before the concrete is removed.

Where concrete has been removed outside the roadway prism, the backfilled areas shall be graded to drain and blend in with the surrounding terrain.

10-1.30 CLEARING AND GRUBBING

Clearing and grubbing shall conform to the provisions in Section 16, "Clearing and Grubbing," of the Standard Specifications and these special provisions.

Vegetation shall be cleared and grubbed only within the excavation and embankment slope lines.

At locations where there is no grading adjacent to a bridge or other structure, clearing and grubbing of vegetation shall be limited to 1.5 m outside the physical limits of the bridge or structure.

Existing vegetation outside the areas to be cleared and grubbed shall be protected from injury or damage resulting from the Contractor's operations.

Activities controlled by the Contractor, except cleanup or other required work, shall be confined within the graded areas of the roadway.

Nothing herein shall be construed as relieving the Contractor of the Contractor's responsibility for final cleanup of the highway as provided in Section 4-1.02, "Final Cleaning Up," of the Standard Specifications.

10-1.31 EARTHWORK

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

Attention is directed to "Remove Fence" of these special provisions regarding compensation for removing fence.

Prior to placing embankment on Prunedale North Road, existing pavement shall be scarified into pieces no larger than 300 mm in greatest dimensions before the remainder of the roadbed is scarified, watered, graded, and rolled as provided in Section 19-6.01, "Placing," of the Standard Specifications.

Where shown on the plans as "Grade to Drain," the Contractor shall grade the terrain as necessary to ensure proper drainage.

Fill slopes steeper than 1:2 shall have fill material conforming to the following specifications:

Maximum Sand Equivalent	5
Maximum Plastic Index	20
Minimum Plastic Index	12

For detour embankment, where shown on the plans, relative compaction of not less than 95 percent shall be obtained for a minimum depth of 0.8 m below finished grade for the width between the outer edges of shoulders, whether in excavation or embankment.

Full compensation for grading existing and revised terrain to drain shall be considered as included in the contract price paid per cubic meter for roadway excavation and no additional compensation will be allowed therefor.

The grading plane of embankments beneath structure approach slabs shall not project above the grade established by the Engineer.

Surplus excavated material shall become the property of the Contractor and shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Where a portion of the existing surfacing is to be removed, the outline of the area to be removed shall be cut on a neat line with a power-driven saw to a minimum depth of 50 mm before removing the surfacing. Full compensation for cutting the existing surfacing shall be considered as included in the contract price paid per cubic meter for roadway excavation and no additional compensation will be allowed therefor.

The portion of imported borrow placed within 1.5 m of the finished grade shall have a Resistance (R-Value) of not less than 50.

Imported borrow will be measured and paid for by the cubic meter and the quantity to be paid for will be computed in the following manner:

- A. The total quantity of embankment will be computed in conformance with the provisions for roadway excavation in Section 19-2.08, "Measurement," of the Standard Specifications, on the basis of the planned or authorized cross section for embankments as shown on the plans and the measured ground surface.
- B. The Contractor, at the Contractor's option, may compact the ground surface on which embankment is to be constructed before placing any embankment thereon. If the compaction results in an average subsidence exceeding 75 mm, the ground surface will be measured after completion of the compaction. The Engineer shall be allowed the time necessary to complete the measurement of an area before placement of embankment is started in that area.
- C. The quantities of roadway excavation, structure excavation and ditch excavation, which have been used in the embankment, will be adjusted by multiplying by a grading factor to be determined in the field by the Engineer. No further adjustment will be made in the event that the grading factor determined by the Engineer does not equal the actual grading factor.
- D. The quantity of imported borrow to be paid for will be that quantity remaining after deducting the adjusted quantities of excavation from the total embankment quantity. No adjustment will be made for subsidence.
- E. The Contractor may propose a plan whereby the Contractor would be paid on the basis of measured settlement in lieu of the allowance specified above. The proposal shall include complete details of the subsidence-measuring devices and a detailed plan of each installation. If the proposed plan is approved by the Engineer, the Contractor, at the Contractor's expense, shall provide, install and maintain the subsidence-measuring devices. The Engineer will take necessary readings to determine the progress of subsidence, if any, and the Contractor shall provide necessary assistance to make the readings.
- F. Installed devices which are determined by the Engineer to have been damaged will not be used for the determination of subsidence for the area the devices represent in the pattern of approved installations. The subsidence of the area represented by that installation shall be considered zero, regardless of the subsidence measured at other installations.
- G. The volumes required as a result of subsidence will be computed by the average-end-area method from the original measurements and the final measurements, including zero subsidence at all points and for all areas as provided herein. It shall be understood and agreed that the subsidence at the point of intersection of the side slopes (and end slopes at structures) with the ground line as established by the original cross sections shall be considered as zero. Unless otherwise agreed to by the Engineer, the subsidence shall be considered as zero at the points on the cross sections 15 m beyond the beginning and ending of the instrumented area. The computed volumes for such subsidence will be added to the quantities of embankment measured as specified herein.
- H. Detachable elements of the subsidence-measuring devices which can be salvaged without damage to the work shall remain the property of the Contractor and shall be removed from the highway right of way after final measurements are made.

Settlement periods are required for the retaining wall and bridge approach embankments at the bridge listed in the following table.

At the retaining wall and bridge abutments listed in the following table, excavation for the footings or driving the foundation piles at each location shall not begin until the expiration of the settlement period.

Surcharge embankments shall be constructed above the grading plane where listed in the following table:

Bridge Name or Number: Prunedale Overcrossing (Br. No. 44-0276Y)			
Abutment Number	Bent Number	Surcharge Height, Meters	Settlement Period, Days
Abut 1 and Abut 2	---	1.5	30

Settlement periods are required for the roadway embankments at the retaining wall listed in the following table. Surcharge embankments shall be constructed above the grading plane where listed in the following table.

Retaining Wall: Prunedale Retaining Wall No. 2 (Bridge No. 44-RW2)		
Locations	Surcharge Height, Meters	Settlement Period, Days
Wall 2A	1.5	30

The duration of the required settlement period at each location will be determined by the Engineer and will not exceed the number of days listed in the tables of settlement data.

The removal of surplus embankment material placed as a settlement or surcharge embankment, including material removed to conform to the finished slope lines shown on the plans, will be paid for at the contract price per cubic meter for roadway excavation.

At the locations and to the limits shown on the plans, material below the bottom of bridge footings at S101 - W156 Connector Undercrossing (Br. No. 44-0277F) and Prunedale Undercrossing (Br. No. 44-0278) shall be removed and replaced with Class 2 aggregate base material in conformance with the placing and compacting requirements for structure backfill. The relative compaction shall be not less than 95 percent. Removal of the material will be measured and paid for by the cubic meter as structure excavation (bridge) and furnishing, placing, and compacting the replacement material will be measured and paid for by the cubic meter as structure backfill (bridge).

At the locations and to the limits shown on the plans, material below the bottom of leveling pad of mechanically stabilized embankment at the Prunedale Retaining Wall No. 1 (Br. No. 44-0280M) and material below the bottom of retaining wall footings at Prunedale Retaining Wall No. 3 shall be removed and replaced with Class 2 aggregate base material in conformance with the placing and compacting requirements for structure backfill. The relative compaction shall be not less than 95 percent. Removal of the material will be measured and paid for by the cubic meter as structure excavation (retaining wall) and furnishing, placing, and compacting the replacement material will be measured and paid for by the cubic meter as structure backfill (retaining wall).

At the footings where material is removed and replaced, as described herein, a relative compaction of not less than 95 percent shall be obtained for a minimum depth of 600 mm below the bottom of footings at S101 - W156 Connector Undercrossing (Br. No. 44-0277F), Prunedale Undercrossing (Br. No. 44-0278) and Prunedale Retaining Wall No. 3, and a minimum depth of 300 mm below the leveling pad of mechanically stabilized embankment at the Prunedale Retaining Wall No. 1 (Br. No. 44-0280M).

If the Contractor elects to use the "Weep Hole and Geocomposite Drain" alternative where permitted on the plans, the geocomposite drain shall conform to the details shown on the plans and the following:

- A. Attention is directed to "Engineering Fabrics" under "Materials" of these special provisions.
- B. Geocomposite drain shall consist of a manufactured core not less than 6.35 mm thick nor more than 50 mm thick with one or both sides covered with a layer of filter fabric that will provide a drainage void. The drain shall produce a flow rate, through the drainage void, of at least 25 liters per minute per meter of width at a hydraulic gradient of 1.0 and a minimum externally applied pressure of 168 kPa.
- C. A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for the geocomposite drain certifying that the drain produces the required flow rate and complies with these special provisions. The Certificate of Compliance shall be accompanied by a flow capability graph for the geocomposite drain showing flow rates for externally applied pressures and hydraulic gradients. The flow capability graph shall be stamped with the verification of an independent testing laboratory.
- D. Filter fabric for the geocomposite drain shall conform to the provisions for fabric for underdrains in Section 88, "Engineering Fabrics," of the Standard Specifications.
- E. The manufactured core shall be either a preformed grid of embossed plastic, a mat of random shapes of plastic fibers, a drainage net consisting of a uniform pattern of polymeric strands forming 2 sets of continuous flow channels, or a system of plastic pillars and interconnections forming a semirigid mat.
- F. The core material and filter fabric shall be capable of maintaining the drainage void for the entire height of geocomposite drain. Filter fabric shall be integrally bonded to the side of the core material with the drainage void. Core material manufactured from impermeable plastic sheeting having nonconnecting corrugations shall be placed with the corrugations approximately perpendicular to the drainage collection system.
- G. The geocomposite drain shall be installed with the drainage void and the filter fabric facing the embankment. The fabric facing the embankment side shall overlap a minimum of 75 mm at all joints and wrap around the exterior edges a minimum of 75 mm beyond the exterior edge. If additional fabric is needed to provide overlap at joints and wrap-around at edges, the added fabric shall overlap the fabric on the geocomposite drain at least 150 mm and be attached thereto.
- H. Should the fabric on the geocomposite drain be torn or punctured, the damaged section shall be replaced completely or repaired by placing a piece of fabric that is large enough to cover the damaged area and provide a minimum 150-mm overlap.
- I. Plastic pipe shall conform to the provisions for edge drain pipe and edge drain outlets in Section 68-3, "Edge Drains," of the Standard Specifications.
- J. Treated permeable base to be placed around the slotted plastic pipe at the bottom of the geocomposite drain shall be cement treated permeable base conforming to the provisions for cement treated permeable base in Section 29, "Treated Permeable Bases," of the Standard Specifications and these special provisions.

- K. The treated permeable base shall be enclosed with a high density polyethylene sheet or PVC geomembrane, not less than 250 µm thick, which is bonded with a suitable adhesive to the concrete and geocomposite drain. Surfaces to receive the polyethylene sheet shall be cleaned before applying the adhesive. The treated permeable base shall be compacted with a vibrating shoe type compactor.

If structure excavation or structure backfill involved in bridges is not otherwise designated by type, and payment for the structure excavation or structure backfill has not otherwise been provided for in the Standard Specifications or these special provisions, the structure excavation or structure backfill will be paid for at the contract price per cubic meter for structure excavation (bridge) or structure backfill (bridge).

10-1.32 EARTH RETAINING STRUCTURES

Earth retaining structures shall be constructed at the locations and in conformance with the details shown on the plans and these special provisions.

The earth retaining structure to be constructed shall be mechanically stabilized embankment (MSE) as shown on the plans.

At the Contractor's option, one of the following acceptable alternative earth retaining systems may be constructed:

Proprietary Earth Retaining System	Address and Phone Number
Reinforced Earth	The Reinforced Earth Company 25651 Atlantic Ocean Drive, Suite A-13 Lake Forest, CA 92630 (949) 587-3060
Retained Earth (1.52-meter square concrete face panels)	Foster Geotechnical 1660 Hotel Circle North - Suite 304 San Diego, CA 92108 (619) 688-2400
MSE Plus	SSL 4740 Scotts Valley Drive, Suite "E" Scotts Valley, CA 95066 (831)430-9300

Attention is directed to the section, "Engineering Fabrics" of these special provisions.

Only one type of earth retaining system shall be used at any one location.

The above list of acceptable alternative earth retaining systems has been selected from the Department's current list of prequalified earth retaining systems and is limited only to those systems determined to have characteristics suitable for this project. Among the alternatives shown, some systems may be proprietary.

The list of prequalified earth retaining systems has been developed from data previously furnished by suppliers or manufacturers of each system. Approval of additional earth retaining systems is contingent on the system meeting the full range of parameters for which prequalification is required. The prequalification requirements can be obtained from the Office of Structure Design, Mail Station 9, 1801 30th Street, Sacramento, CA 95816.

If the Contractor elects to use a proprietary earth retaining system from the list of acceptable alternative systems, the Contractor shall submit complete working drawings for each installation of the system to the Office of Structure Design (OSD) in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. For initial review, 4 sets of drawings shall be submitted. After review, between 6 and 12 sets, as requested by the Engineer, shall be submitted to OSD for final approval and use during construction.

Working drawings shall be 279 mm x 432 mm in size and each drawing and calculation sheet shall include the State assigned designations for the contract number, bridge number, full name of the structure as shown on the contract plans, and District-County-Route-Kilometer Post. The design firm's name, address, and phone number shall be shown on the working drawings. Each sheet shall be numbered in the lower right hand corner and shall contain a blank space in the upper right hand corner for future contract sheet numbers.

The Contractor shall verify the existing ground elevations at the site before preparing the working drawings. The working drawings shall contain all information required for the proper construction of the system at each location including existing ground line at face of wall as verified at the site and any required revisions or additions to drainage systems or other facilities. The working drawings shall be supplemented as necessary with calculations for the particular installation. The working drawings and calculations shall be stamped and signed by an engineer who is registered as a Civil Engineer in the State of California. The Contractor shall allow the Engineer 4 weeks to review the drawings after a complete set has been received.

One set of the corrected prints on 90-g/m² (minimum) bond paper, 279 mm x 432 mm in size, of all working drawings prepared by the Contractor for each earth retaining structure shall be furnished to OSD within 3 weeks after final working drawing approval.

The top of wall profile of alternative earth retaining systems shall conform to that of mechanically stabilized embankment shown on the plans. The top of leveling pad elevations shall be at or below the elevations shown on the plans. The height and length to be used for any system shall be the minimums for that system that will effectively retain the earth behind the structure for the loading conditions and the contours, profile or slope lines shown on the plans. The length of soil reinforcement for any system shall be not less than that shown on the plans. In addition, if the plans or special provisions indicate limiting parameters for alternative systems, the system shall conform to those parameters.

EARTHWORK

Excavation and backfill shall conform to the details shown on the plans, the provisions in Section 19, "Earthwork," of the Standard Specifications, and these special provisions.

Structure backfill for earth retaining structures with metallic soil reinforcement shall consist of material free from organic material and substantially free of shale or other soft, poor durability particles; shall not contain slag aggregate or recycled materials, such as glass, shredded tires, portland cement concrete rubble, asphaltic concrete rubble, or other unsuitable material as determined by the Engineer; and shall meet the following requirements:

Gradation Requirements

Sieve Size	Percentage Passing	California Test
159-mm	100	202
75-mm	78 - 100	202
4.75-mm	----	202
600-_m	0 - 60	202
75-_m	0 - 25	202

Property Requirements

Test	Requirement	California Test
Sand Equivalent	12 min.	217
Plasticity Index	10 max.	204
Minimum Resistivity	1500 ohm-cm min.	643
Chlorides	500 ppm max.	422
Sulfates	2000 ppm max.	417
pH	5.5 to 10.0	643

If 12 percent or less passes the No. 75-_m sieve and 50 percent or less passes the No. 4.75-mm sieve, the Sand Equivalent and Plasticity Index requirements shall not apply.

Permeable material shall be used for the portion of the structure backfill for earth retaining structures with soil reinforcement within the limits shown on the plans. Permeable material shall be placed in layers not exceeding 0.6 meters in thickness. Permeable material shall be Class 1, Type B, conforming to the provisions in Section 68-1.025, "Permeable Material," of the Standard Specifications and the following requirements:

Property Requirements

Test	Requirement	California Test
Minimum Resistivity	1500 ohm-cm min.	643
Chlorides	500 ppm max.	422
Sulfates	2000 ppm max.	417
pH	5.5 to 10.0	643

Structure backfill for earth retaining structures with soil reinforcement shall be compacted to a relative compaction of not less than 90 percent except that when the backfill is within 50 meters of a bridge abutment or for a minimum depth of one meter below the grading plane for the width between the outer edges of shoulders, the backfill shall be compacted to a relative compaction of not less than 95 percent.

A relative compaction of not less than 95 percent shall be obtained for embankment under earth retaining structures with soil reinforcement within the limits established by inclined planes sloping 1:1.5 (vertical:horizontal) out and down from lines 0.3-m outside the bottom limits of structure backfill including permeable material, when required.

Structure backfill material shall be placed and compacted simultaneously with the erection of the facing panels. Placement and compaction shall be accomplished without distortion of the soil reinforcement or displacement of facing panels. Structure backfill at the front of the wall shall be completed prior to backfilling more than 4 m above the bottom of the lowermost face element.

Sheepsfoot or grid-type rollers shall not be used for compacting material within the limits of the soil reinforcement. Hand-held or hand-guided compacting equipment shall be used to compact structure backfill material within one meter of the facing panels.

At each level of the soil reinforcement, the structure backfill shall be constructed to a plane 45 mm above the elevation of the soil reinforcement connection, and shall start one meter from the back of the face panel and extend for at least the remaining length of soil reinforcement. This grading shall be complete before placing the next layer of soil reinforcement.

Water used for earthwork or dust control within 150 meters of any portion of earth retaining structures with metallic soil reinforcement shall conform to the provisions for water in conventionally reinforced concrete work in Section 90-2.03, "Water," of the Standard Specifications.

CONCRETE

Concrete used in precast and cast-in-place reinforced concrete members of earth retaining structures shall conform to the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

The concrete leveling pads shall conform to the provisions in Section 90-10, "Minor Concrete," of the Standard Specifications. Concrete for the leveling pads shall be placed at least 24 hours prior to erecting face panels.

REINFORCEMENT

Reinforcing steel shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and to the provisions in "Reinforcement" of these special provisions.

GALVANIZING

Soil reinforcement, connecting elements, and other steel components that are in contact with the earth shall be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing," of the Standard Specifications.

DRAINAGE SYSTEM

The drainage system shall conform to the details shown on the plans and these special provisions.

Corrugated steel pipe shall conform to the provisions in Section 66, "Corrugated Metal Pipe," of the Standard Specifications.

Perforated steel pipe underdrains and underdrain outlets and risers shall conform to the provisions in Section 68-1, "Underdrains," of the Standard Specifications.

The class of rock used for rock slope protection at drain pipe outlets shall be No. 3 Backing, and shall conform to the provisions in Section 72-2, "Rock Slope Protection," of the Standard Specifications.

Permeable material shall be Class 1, Type B, conforming to the provisions in Section 68-1.025, "Permeable Material," of the Standard Specifications and these special provisions.

Permeable material and filter fabric shall be placed along with structure backfill as shown on the plans. Compaction of the permeable material for the drainage system outside the limits of the soil reinforcement is not required, and equipment shall not be operated directly on the permeable material or filter fabric. If a sloped layer of permeable material is placed to facilitate the work or to satisfy safety considerations, the vertical limits of permeable material shall remain unchanged and the thickness of the layer of permeable material shall be measured normal to the slope.

Filter fabric shall conform to the provisions for fabric for underdrains in Section 88-1.03, "Filter Fabric," of the Standard Specifications and shall be placed at the locations and in conformance with the details shown on the plans and these special provisions.

Immediately prior to placing, the subgrade to receive the filter fabric shall conform to the compaction and elevation tolerance specified for the material involved and shall be free of loose or extraneous material and sharp objects that may damage the filter fabric during installation.

Filter fabric shall be handled and placed in conformance with the manufacturer's recommendations.

The fabric shall be stretched, aligned, and placed in a wrinkle-free manner.

Adjacent borders of the fabric shall be overlapped from 300 mm to 450 mm or stitched. The preceding roll shall overlap the following roll in the direction the material is being spread or shall be stitched. When the fabric is joined by stitching, it shall be stitched with yarn of a contrasting color. The size and composition of the yarn shall be as recommended by the fabric manufacturer. The stitches shall number 2 to 3 per centimeter of seam.

Should the fabric be damaged during placing, the torn or punctured section shall be repaired by placing a piece of fabric that is large enough to cover the damaged area and which meets the overlap requirement.

During spreading of the permeable material a minimum of 150 mm of the material shall be maintained between the fabric and the Contractor's equipment. Where structure backfill material is to be placed on the filter fabric, a minimum of 450 mm of structure backfill material shall be maintained between the fabric and the Contractor's equipment. Equipment or vehicles shall not be operated or driven directly on the filter fabric.

Adhesive for bonding filter fabric to concrete panels shall conform to the requirements in Federal Specification MMM-A-121.

Concrete panel surfaces which are to receive filter fabric shall be dry and thoroughly cleaned of dust and deleterious materials.

STATE-DESIGNED EARTH RETAINING STRUCTURES

If the Contractor elects to construct one of the earth retaining structures shown on the plans, the structure shall be constructed to the lines and grades and the details shown on the plans, in conformance with these special provisions and the following:

MECHANICALLY STABILIZED EMBANKMENT

This work shall consist of constructing earth retaining structures of mechanically stabilized embankments with concrete face panels in conformance with the details shown on the plans and these special provisions.

Resin bonded cork for horizontal joints shall conform to the requirements in ASTM Designation: D 1752, Type II with a compressive load of not less than 690 kPa.

Pipe for the pipe pin shall conform to the requirements in ASTM Designation: A 53, Standard weight, except the amount of the zinc coating per square meter of actual surface shall average not less than 610 g and no individual specimen shall show less than 550 g.

The button on the button-headed wires shall conform to the provisions in Section 50-1.05, "Prestressing Steel," of the Standard Specifications.

The coupler at the mat connection shall be a seamless steel sleeve. The coupler shall be applied over the button-headed wires and swaged by means of a hydraulic press. The coupler shall develop the minimum tensile strength of the wire without exceeding a total slip of the wires of 5 mm.

Splicing of the welded wire mat along its length shall be by a mechanical coupler which will develop the minimum tensile strength of the wire. The mechanical coupler shall be approved by the Engineer.

MW70 and MW130 steel wire shall conform to the requirements in ASTM Designation: A 82. The welded wire mat shall conform to the requirements in ASTM Designation: A 185.

MD70 and MD130 deformed steel wire may be substituted for MW70 and MW130 steel wire, respectively. The welded wire mat utilizing deformed steel wire shall conform to the requirements in ASTM Designation: A 497.

PROPRIETARY EARTH RETAINING SYSTEMS

If the Contractor elects to construct one of the acceptable proprietary alternative earth retaining systems, the structure shall be constructed to the lines and grades shown on the plans. The construction shall include a drainage system as shown on the plans, and conform to the details shown on the approved working drawings, these special provisions, approved proprietary system details and special provisions, and the following:

The location of the top level of soil reinforcement, assuming no leveling pad settlement, shall be placed parallel to the top of wall and at a distance below the top of wall as shown on the plans within a maximum tolerance of plus 40 mm.

The top of top face panels, assuming no leveling pad settlement, shall be parallel to the top of the wall at the distance below the top of wall as shown on the plans within a maximum tolerance of plus 40 mm.

MEASUREMENT AND PAYMENT

Earth retaining structures will be measured and paid for by the square meter. Regardless of the type of earth retaining structure actually constructed, the square meter area for payment will be based on the vertical height and length of each section of mechanically stabilized embankment shown on the plans which was or would have been constructed. The vertical height of each section will be taken as the difference in elevation on the outer face from the bottom of the lowermost face element to the top of wall profile.

The contract price paid per square meter for earth retaining structure at each location shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the earth retaining structure and inspection elements, including earthwork, leveling pad, barrier slab, and drainage systems, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions and as directed by the Engineer.

Full compensation for revisions to the barrier support, drainage system, or other facilities made necessary by the use of an alternative earth retaining system shall be considered as included in the contract price paid per square meter for earth retaining structure and no separate payment will be made therefor.

10-1.33 CONTROLLED LOW STRENGTH MATERIAL

Controlled low strength material shall consist of a workable mixture of aggregate, cementitious materials, and water and shall conform to the provisions for slurry cement backfill in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications and these special provisions.

At the option of the Contractor, controlled low strength material may be used as structure backfill for pipe culverts, except that controlled low strength material shall not be used as structure backfill for aluminum and aluminum-coated culverts nor for culverts having a diameter or span greater than 6.1 m.

When controlled low strength material is used for structure backfill, the width of the excavation shown on the plans may be reduced so that the clear distance between the outside of the pipe and the side of the excavation, on each side of the pipe, is a minimum of 300 mm. This minimum may be reduced to 150 mm when the height of cover is less than or equal to 6.1 m or the pipe diameter or span is less than 1050 mm.

Controlled low strength material in new construction shall not be permanently placed higher than the basement soil. For trenches in existing pavements, permanent placement shall be no higher than the bottom of the existing pavement permeable drainage layer. If a drainage layer does not exist, permanent placement in existing pavements shall be no higher than 25 mm below the bottom of the existing asphalt concrete surfacing or no higher than the top of base below the existing portland cement concrete pavement. The minimum height that controlled low strength material shall be placed, relative to the culvert invert, is 0.5 diameter or 0.5 height for rigid culverts and 0.7 diameter or 0.7 height for flexible culverts.

When controlled low strength material is proposed for use, the Contractor shall submit a mix design and test data to the Engineer for approval prior to excavating the trench for which controlled low strength material is proposed for use. The test data and mix design shall provide for the following:

- A. A 28-day compressive strength between 345 kPa and 690 kPa for pipe culverts having a height of cover of 6.1 m or less and a minimum 28-day compressive strength of 690 kPa for pipe culverts having a height of cover greater than 6.1 m. Compressive strength shall be determined in conformance with the requirements in ASTM Designation: D 4832.
- B. When controlled low strength material is used as structure backfill for pipe culverts, the sections of pipe culvert in contact with the controlled low strength material shall conform to the requirements of Chapter 850 of the Highway Design Manual using the minimum resistivity, pH, chloride content, and sulfate content of the hardened controlled low strength material. Minimum resistivity and pH shall be determined in conformance with the requirements of California Test 643. The chloride content shall be determined in conformance with the requirements of California Test 422 and the sulfate content shall be determined in conformance with the requirements of California Test 417.
- C. Cement shall be any type of portland cement conforming to the requirements in ASTM Designation: C 150; or any type of blended hydraulic cement conforming to the requirements in ASTM Designation: C 595M or the physical requirements in ASTM Designation: C 1157M. Testing of cement will not be required.
- D. Admixtures may be used in conformance with the provisions in Section 90-4, "Admixtures," of the Standard Specifications. Chemical admixtures containing chlorides as Cl in excess of one percent by mass of admixture, as determined in conformance with the requirements of California Test 415, shall not be used. If an air-entraining admixture is used, the maximum air content shall be limited to 20 percent. Mineral admixtures shall be used at the Contractor's option.

Materials for controlled low strength material shall be thoroughly machine-mixed in a pugmill, rotary drum or other approved mixer. Mixing shall continue until the cementitious material and water are thoroughly dispersed throughout the material. Controlled low strength material shall be placed in the work within 3 hours after introduction of the cement to the aggregates.

When controlled low strength material is to be placed within the traveled way or otherwise to be covered by paving or embankment materials, the material shall achieve a maximum indentation diameter of 76 mm prior to covering and opening to public traffic. Penetration resistance shall be measured in conformance with the requirements in ASTM Designation: D 6024.

Controlled low strength material used as structure backfill for pipe culverts will be considered structure backfill for compensation purposes.

10-1.34 SHOULDER BACKING

This work shall consist of constructing shoulder backing adjacent to the edge of the new surfacing in conformance with the details shown on the plans and these special provisions.

Material for shoulder backing shall consist of native material or surplus material from planned excavation and cold planed material. Surplus material from planned excavation and cold planed material shall be utilized to the maximum extent for shoulder backing. The material shall be bladed or graded from areas adjacent to the shoulder backing as determined by the Engineer or as shown on the plans.

If the quantity of native material along the roadway or surplus material from planned excavation and cold planed material is insufficient, as determined by the Engineer, to complete construction of the shoulder backing, imported material, as ordered by the Engineer, shall be furnished. Furnishing, hauling, and depositing this imported material, if required, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

The areas where shoulder backing is to be constructed shall be cleared of weeds, grass, and debris. Removed weeds and grass shall be disposed of uniformly over adjacent slope areas and removed debris shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Shoulder backing material shall be thoroughly mixed with the basement material by scarifying or blading and then watered and rolled to form a smooth, firmly compacted surface. Watering shall conform to the provisions in Section 17, "Watering," of the Standard Specifications.

Shoulder backing material shall not be deposited on the new surfacing prior to placing the material in the final position, nor shall the material be deposited onto the new surfacing during mixing, watering, and blading operations.

Shoulder backing construction shall be completed along the edges of any portion of new surfacing within 5 days after completion of that portion of the new surfacing. Prior to opening a lane adjacent to uncompleted shoulder backing to uncontrolled public traffic, the Contractor shall furnish, place, and maintain portable delineators and C31 (Low Shoulder) signs off of and adjacent to the new surfacing. Portable delineators shall be placed at the beginning and along the drop-off of the edge of pavement, in the direction of travel, at successive maximum intervals of 150 meters on tangents and 60 meters on curves. C31 signs shall be placed at the beginning and along the drop-off at successive maximum intervals of 600 meters. The portable delineators and C31 signs shall be maintained in place at each location until the shoulder backing is completed at that location. Portable delineators and signs shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, except the signs may be set on temporary portable supports or on barricades.

Shoulder backing will be measured by the station along each edge of surfacing where shoulder backing is constructed. A station shall be considered to be 100 meters. The length of shoulder backing to be paid for will be determined from actual measurement or calculated from centerline stationing or kilometer post distance determined by the Engineer.

The contract price paid per station for shoulder backing shall include full compensation for furnishing all labor, materials (except imported material), tools, equipment, and incidentals, and for doing all the work involved in constructing shoulder backing, complete in place, including furnishing, placing, maintaining, and removing portable delineators, C31 signs, and temporary supports or barricades for the signs, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.35 EROSION CONTROL (BLANKET) (TYPE 1)

Erosion control (blanket) (Type 1) shall conform to the details shown on the plans, the provisions in Section 20-3, "Erosion Control," of the Standard Specifications and these special provisions.

Erosion control (blanket) (Type 1) work shall consist of applying seed and commercial fertilizer and installing erosion control blanket to embankment slopes and excavation slopes 1:2 and steeper and other areas designated by the Engineer. Erosion control blanket shall be placed after irrigation has been installed and before planting begins.

MATERIALS

Materials shall conform to the provisions in Section 20-2, "Materials," of the Standard Specifications and these special provisions.

Seed

Seed shall conform to the provisions in Section 20-2.10, "Seed," of the Standard Specifications. Individual seed species shall be measured and mixed in the presence of the Engineer.

Seed not required to be labeled under the California Food and Agricultural Code shall be tested for purity and germination by a seed laboratory certified by the Association of Official Seed Analysts or by a seed technologist certified by the Society of Commercial Seed Technologists.

Seed shall have been tested for purity and germination not more than one year prior to application of seed.

Results from testing seed for purity and germination shall be furnished to the Engineer prior to applying seed.

Seed shall be delivered to the job site in unopened separate containers with the seed tag attached. Containers without a seed tag will not be accepted.

A sample of approximately 30 g of seed will be taken from each seed container by the Engineer.

Legume Seed

Legume seed shall be pellet-inoculated or industrial-inoculated and shall conform to the following:

- A. Pellet-inoculated seed shall be inoculated in conformance with the provisions in Section 20-2.10, "Seed," of the Standard Specifications.
- B. Inoculated seed shall have a calcium carbonate coating.
- C. Pellet-inoculated seed shall be sown within 90 days after inoculation.
- D. Industrial-inoculated seed shall be inoculated with Rhizobia and coated using an industrial process by a manufacturer whose principal business is seed coating and seed inoculation.
- E. Industrial-inoculated seed shall be sown within 180 calendar days after inoculation.
- F. Legume seed shall consist of the following:

LEGUME SEED

Botanical Name (Common Name)	Percent Germination (Minimum)	Kilograms Pure Live Seed Per Hectare (Slope Measurement)
Lupinus densiflorus (Golden Lupine)	65	2

Non-Legume Seed

Non-legume seed shall consist of the following:

NON-LEGUME SEED

Botanical Name (Common Name)	Percent Germination (Minimum)	Kilograms Pure Live Seed Per Hectare (Slope Measurement)
Clarkia bottae (Showy Farewell to Spring)	65	3
Eschscholtzia californica (California Poppy)	75	2
Festuca idahoensis (Idaho Fescue)	75	20
Festuca rubra 'Molate' (Molate Fescue)	75	20
Penstemon centranthifolius (Scarlett Bugler)	55	3

Commercial Fertilizer

Commercial fertilizer shall conform to the provisions in Section 20-2.02, "Commercial Fertilizer," of the Standard Specifications and shall have a guaranteed chemical analysis of 23 percent nitrogen, 5 percent phosphoric acid and 10 percent water soluble potash.

Erosion Control Blanket

Erosion control blanket (Type 1) shall consist of straw and coconut mats secured in place with wire staples and shall conform to the following:

- A. Straw and coconut blanket shall be machine produced mats of straw and coconut fiber with a lightweight photo-degradable netting on top. The straw shall be adhered to the netting with biodegradable thread or glue strip. The straw and coconut erosion control blanket shall be of consistent thickness and the straw and coconut fiber shall be evenly distributed over the entire area of the blanket. Straw and coconut erosion control blanket shall be furnished in rolled strips with a minimum width of 2 m, minimum length of 25 m ± one m and a minimum mass of 0.27-kg/m².
- B. Staples for erosion control blankets shall be made of 11-gage minimum steel wire and shall be U-shaped with 200-mm legs and 50-mm crown.

APPLICATION

Prior to placing erosion control blanket (Type 1), the surface upon which blanket is to be placed shall be free of loose or extraneous material and sharp objects that may damage the blanket during installation or prevent intimate contact with the soil. Erosion control (blanket) materials shall be placed in separate applications as follows:

- A. The first application shall consist of applying seed and commercial fertilizer at the following rates and in the following sequence:
 - 1. Seed and commercial fertilizer shall be applied at the rates indicated in the following table. If hydro-seeding equipment is used to apply seed and commercial fertilizer, the mixture shall be applied within 60 minutes after the seed has been added to the mixture.

Material	Kilograms Per Hectare (Slope Measurement)
Seed	50
Commercial Fertilizer	150

- B. The second application shall consist of installing the erosion control blanket over the seed and commercial fertilizer application.
- Erosion control blanket strips shall be placed loosely on the slope with the longitudinal joints perpendicular to the slope contour lines. Longitudinal and transverse joints of blankets shall be butted snugly against adjacent strips or overlapped according to the manufacturer's recommendations and stapled. Staples shall be driven perpendicular to the slopes, and shall be located and spaced in conformance with the manufacturer's instructions. Ends of the blankets shall be secured in place in conformance with the manufacturer's instructions. Once seed work is started in an area, erosion control blanket applications shall be completed in that area on the same working day.
- A slit shall be made in the erosion control blanket parallel to the fall of the slope, at each plant location sufficient to receive the root ball. Erosion control blanket shall be placed so that the blanket does not come in contact with the plant stem. Edges of each slit shall be secured with a minimum of two staples.

MEASUREMENT AND PAYMENT

The quantity of erosion control (blanket) (Type 1) will be determined by the square meter from actual slope measurement of the area covered by the erosion control blanket.

The contract price paid per square meter for erosion control (blanket) (Type 1) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing erosion control blanket, complete in place, including furnishing and applying pure live seed, commercial fertilizer, and the materials for the erosion control blanket, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.36 EROSION CONTROL (BLANKET) (TYPE 2)

Erosion control (blanket) shall conform to the details shown on the plans, the provisions in Section 20-3, "Erosion Control," of the Standard Specifications and these special provisions.

Erosion control (blanket) (Type 2) work shall consist of applying seed and commercial fertilizer and installing erosion control blanket to areas shown on the plans and other areas designated by the Engineer. Erosion control blanket shall be placed after irrigation has been installed and before planting begins.

MATERIALS

Materials shall conform to the provisions in Section 20-2, "Materials," of the Standard Specifications and these special provisions.

Seed

Seed for erosion control (blanket) shall conform to the provisions specified for seed under "Erosion Control Blanket (Type 1)" of these special provisions.

Commercial Fertilizer

Commercial fertilizer shall conform to the provisions in Section 20-2.02, "Commercial Fertilizer," of the Standard Specifications and shall have a guaranteed chemical analysis of 23 percent nitrogen, 5 percent phosphoric acid and 10 percent water soluble potash.

Erosion Control Blanket

Erosion control blanket shall consist of polypropylene mats secured in place with wire staples and shall conform to the following:

- A. Polypropylene blanket shall be machine produced mats of UV stabilized, polypropylene fiber matrix sewn between heavy duty, UV stabilized plastic mesh, top and bottom, 50-mm or less on center. The polypropylene erosion control blanket shall be of consistent thickness and the fiber shall be evenly distributed over the entire area of the blanket. Polypropylene erosion control blanket shall be furnished in rolled strips with a minimum width of 2 m, minimum length of 25 m ± one m and a minimum mass of 0.27-kg/m². The blanket shall be capable of withstanding flows of 6 meters per second.
- B. Staples for erosion control blankets shall be made of 8-gage minimum steel wire and shall be U-shaped with 200-mm legs and 50-mm crown.

APPLICATION

Prior to placing erosion control blanket, the surface upon which blanket is to be placed shall be free of loose or extraneous material and sharp objects that may damage the blanket during installation or prevent intimate contact with the soil. Erosion control (blanket) (Type 2) materials shall be placed in separate applications as follows:

- A. The first application shall consist of applying seed and commercial fertilizer at the following rates and in the following sequence:
 - 1. Seed, and commercial fertilizer shall be applied at the rates indicated in the following table. If hydro-seeding equipment is used to apply seed and commercial fertilizer, the mixture shall be applied within 60 minutes after the seed has been added to the mixture.

Material	Kilograms Per Hectare (Slope Measurement)
Seed	50
Commercial Fertilizer	150

- B. The second application shall consist of installing the erosion control blanket (Type 2) over the seed and commercial fertilizer application.

- Erosion control blanket strips shall be placed loosely on the slope with the longitudinal joints perpendicular to the slope contour lines. Longitudinal and transverse joints of blankets shall be butted snugly against adjacent strips or overlapped according to the manufacturer's recommendations and stapled. Staples shall be driven perpendicular to the slopes, and shall be located and spaced in conformance with the manufacturer's instructions. Ends of the blankets shall be secured in place in conformance with the manufacturer's instructions. Once seed work is started in an area, erosion control blanket (Type 2) applications shall be completed in that area on the same working day.
- Erosion control blanket (Type 2) shall be handled and placed along drainage ditch and other areas, in accordance with the manufacturer's recommendations for channel liners and as directed by the Engineer. Where erosion control blanket (Type 2) overlaps erosion control blanket (Type 1) it shall be secured to erosion control blanket (Type 1) such that coverage is continuous.

MEASUREMENT AND PAYMENT

The quantity of erosion control (blanket) (Type 2) will be determined by the square meter from actual slope measurement of the area covered by the erosion control blanket.

The contract price paid per square meter for erosion control (blanket) (Type 2) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing erosion control blanket, complete in place, including furnishing and applying pure live seed, commercial fertilizer, and the materials for the erosion control blanket, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.37 EROSION CONTROL (TYPE D)

Erosion control (Type D) shall conform to the provisions in Section 20-3, "Erosion Control," of the Standard Specifications and these special provisions and shall consist of applying erosion control materials to embankment and excavation slopes and other areas disturbed by construction activities.

Erosion control (Type D) shall be applied when an area is ready to receive erosion control as determined by the Engineer and in conformance with the provisions in "Move-in/Move-out (Erosion Control)" of these special provisions.

Prior to installing erosion control materials, soil surface preparation shall conform to the provisions in Section 19-2.05, "Slopes," of the Standard Specifications, except that rills and gullies exceeding 50 mm in depth or width shall be leveled. Vegetative growth, temporary erosion control materials, and other debris shall be removed from areas to receive erosion control.

MATERIALS

Materials shall conform to the provisions in Section 20-2, "Materials," of the Standard Specifications and these special provisions.

Seed

Seed for erosion control (Type D) shall conform to the provisions specified for seed in "Erosion Control (Blanket)" of these special provisions.

Commercial Fertilizer

Commercial fertilizer for erosion control (Type D) shall conform to the provisions specified for commercial fertilizer in "Erosion Control (Blanket)" of these special provisions.

Straw

Straw shall conform to the provisions in Section 20-2.06, "Straw," of the Standard Specifications and these special provisions.

Straw shall be derived from rice.

Stabilizing Emulsion

Stabilizing emulsion shall conform to the provisions in Section 20-2.11, "Stabilizing Emulsion," of the Standard Specifications and these special provisions.

Stabilizing emulsion shall be in a dry powder form, may be reemulsifiable, and shall be a processed organic adhesive used as a soil tackifier.

APPLICATION

Erosion control materials shall be applied in separate applications in the following sequence:

- A. The following mixture in the proportions indicated shall be applied with hydro-seeding equipment within 60 minutes after the seed has been added to the mixture:

Material	Kilograms Per Hectare (Slope Measurement)
Fiber	600
Seed	50

- B. Straw shall be applied at the rate of 3.5 tonnes per hectare based on slope measurements. Incorporation of straw will not be required. Straw shall be distributed evenly without clumping or piling.
- C. The following mixture in the proportions indicated shall be applied with hydro-seeding equipment:

Material	Kilograms Per Hectare (Slope Measurement)
Fiber	1400
Commercial Fertilizer	150
Stabilizing Emulsion (Solids)	200

The ratio of total water to total stabilizing emulsion in the mixture shall be as recommended by the manufacturer.

Once work is started in an area, stabilizing emulsion applications shall be completed in that area on the same working day.

The proportions of erosion control materials may be changed by the Engineer to meet field conditions.

10-1.38 MOVE-IN/MOVE-OUT (EROSION CONTROL)

Move-in/move-out (erosion control) shall include moving onto the project when an area is ready to receive erosion control as determined by the Engineer, setting up all required personnel and equipment for the application of erosion control materials and moving out all personnel and equipment when erosion control in that area is completed.

When areas are ready to receive applications of erosion control (Types D or Blanket), as determined by the Engineer, the Contractor shall begin erosion control work in that area within 5 working days of the Engineer's notification to perform the erosion control work.

Attention is directed to the requirements of erosion control (Types D or Blanket) elsewhere in these special provisions.

Quantities of move-in/move-out (erosion control) will be determined as units from actual count as determined by the Engineer. For measurement purposes, a move-in followed by a move-out will be considered as one unit.

The contract unit price paid for move-in/move-out (erosion control) shall include full compensation for furnishing all labor, materials (excluding erosion control materials), tools, equipment, and incidentals and for doing all the work involved in moving in and removing from the project all personnel and equipment necessary for application of erosion control (Types D or Blanket), as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

No adjustment of compensation will be made for any increase or decrease in the quantities of move-in/move-out (erosion control) required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to the item of move-in/move-out (erosion control).

10-1.39 IRRIGATION CROSSOVERS

Irrigation crossovers shall conform to the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications and these special provisions.

Conduits placed in open trenches shall be placed in open trenches in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications. Conduits installed under existing paving shall be installed under existing paving by jacking or drilling methods in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

Conduits installed under existing paving shall be welded steel pipe as shown on the plans. Conduits placed in open trenches shall be corrugated high density polyethylene (CHDPE) pipe. Corrugated high density polyethylene pipe shall conform to the requirements in ASTM Designation: F 405 or F 667, or AASHTO Designation: M 252 or M 294 and shall be Type S. Couplings and fittings shall be as recommended by the pipe manufacturer.

Water line crossovers shall conform to the provisions in Section 20-5.03C, "Water Line Crossovers," of the Standard Specifications.

Sprinkler control crossovers shall conform to the provisions in Section 20-5.027D, "Sprinkler Control Crossovers," of the Standard Specifications.

Installation of pull boxes shall conform to the provisions in Section 20-5.027I, "Conductors, Electrical Conduit and Pull Boxes," of the Standard Specifications.

10-1.40 FINISHING ROADWAY

Finishing roadway shall conform to the provisions in Section 22, "Finishing Roadway," of the Standard Specifications.

10-1.41 AGGREGATE BASE

Aggregate base shall be Class 2 and shall conform to the provisions in Section 26, "Aggregate Bases," of the Standard Specifications and these special provisions.

The restriction that the amount of reclaimed material included in Class 2 aggregate base not exceed 50 percent of the total volume of the aggregate used shall not apply. Aggregate for Class 2 aggregate base may include reclaimed glass. Aggregate base incorporating reclaimed glass shall not be placed at locations where surfacing will not be placed over the aggregate base.

10-1.42 SOIL TREATMENT

Soil shall be treated in maintenance vehicle pullouts to be surfaced with asphalt concrete in conformance with these special provisions.

Pesticides used for soil treatment shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specification, except recommendations from a Pest Control Adviser will not be required.

Soil under areas to be surfaced shall be graded to a neat and smooth surface. Where surfacing is to be placed adjacent to curbs, the subgrade shall be graded so that after the surfacing is placed, the top of the surfacing will be flush with the top of the curb.

Immediately prior to treatment, the soil shall be scarified to a minimum depth of 75 mm and rocks, large lumps of earth, weeds, and other debris shall be removed and disposed of. Removed material shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. The loosened material shall then be brought to as finely divided condition as the material will permit.

After scarification, the soil shall be sterilized with one of the following pesticides applied at the maximum label rate unless otherwise directed by the Engineer:

- A. Trifluralin emulsifiable concentrate.

Pesticides shall be mixed in conformance with the manufacturer's recommendations and shall be applied by a device approved by the Engineer. Pesticides shall not be applied more than 8 hours prior to placing asphalt concrete surfacing. Pesticides shall not be applied more than 300 mm beyond the areas to be surfaced.

Treated areas shall be thoroughly compacted by use of power rollers. When power rollers cannot be operated in certain areas due to the shape or size of the areas, compaction shall be obtained by hand rollers, impactors or other methods approved by the Engineer.

Full compensation for treating soil shall be considered as included in the contract price paid per tonne for asphalt concrete and no additional compensation will be allowed therefor.

10-1.43 ASPHALT CONCRETE

Asphalt concrete shall be Type B and shall conform to the provisions in Section 11-1, "Quality Control / Quality Assurance," of these special provisions and these special provisions.

Surfacing of miscellaneous areas with asphalt concrete shall conform to the provisions in "Asphalt Concrete (Miscellaneous Areas)" of these special provisions.

The aggregate for Type B asphalt concrete shall conform to the 19-mm maximum, medium grading specified in Section 39-2.02, "Aggregate," in Section 11-1, "Quality Control / Quality Assurance," of these special provisions.

In addition to the provisions in Section 39-9.01, "Spreading Equipment," in Section 11-1, "Quality Control / Quality Assurance," of these special provisions, asphalt paving equipment shall be equipped with automatic screed controls and a sensing device or devices.

When placing asphalt concrete to lines and grades established by the Engineer, the automatic controls shall control the longitudinal grade and transverse slope of the screed. Grade and slope references shall be furnished, installed, and maintained by the Contractor. Should the Contractor elect to use a ski device, the minimum length of the ski device shall be 9 m. The ski device shall be a rigid one piece unit and the entire length shall be utilized in activating the sensor.

When placing the initial mat of asphalt concrete on existing pavement, the end of the screed nearest the centerline shall be controlled by a sensor activated by a ski device not less than 9 m long. The end of the screed farthest from centerline shall be controlled manually.

When paving contiguously with previously placed mats, the end of the screed adjacent to the previously placed mat shall be controlled by a sensor that responds to the grade of the previously placed mat and will reproduce the grade in the new mat within a 3-mm tolerance. The end of the screed farthest from the previously placed mat shall be controlled in the same manner the screed was controlled when placing the initial mat.

If the methods and equipment furnished by the Contractor fail to produce a layer of asphalt concrete conforming to the provisions, including straightedge tolerance, in Section 39-10.04, "Compacting," in Section 11-1, "Quality Control / Quality Assurance," of these special provisions, the paving operations shall be discontinued and the Contractor shall modify the equipment or methods, or furnish substitute equipment.

If the automatic screed controls fail to operate properly during a day's work, the Contractor may use manual control of the spreading equipment for the remainder of that day. However, the equipment shall be corrected or replaced with alternative automatically controlled equipment conforming to the requirements in this section before starting another day's work.

In addition to the straightedge requirements in Section 39-10.04, "Compacting," in Section 11-1, "Quality Control / Quality Assurance," of these special provisions, asphalt concrete pavement shall conform to the surface tolerances specified herein.

The top surface of the uppermost layer of asphalt concrete surfacing shall be profiled, in the presence of the Engineer, using a California Profilograph or equivalent in conformance with California Test 526 and as specified in these special provisions. Prior to beginning profiles, the profilograph shall be calibrated in the presence of the Engineer. Profiles shall be made on the traveled way one meter from and parallel to each edge of traveled way and at the approximate location of the planned lane lines.

Pavement so profiled shall conform to the following Profile Index requirements:

- A. Pavement on tangent alignment and pavement on horizontal curves having a centerline radius curve of 600 m or more shall have a Profile Index of 80 mm per kilometer or less for each 160-m section profiled.
- B. Pavement on horizontal curves having a centerline radius curve of 300 m or more but less than 600 m including the pavement within the superelevation transition of such curves, shall have a Profile Index of 160-mm per kilometer or less for each 160-m section profiled.
- C. Pavement shall not have individual deviations in excess of 8 mm, as determined by California Test 526. The location of the profiles for determining deviations shall be designated by the Engineer.

Checking the following areas of pavement surface with the California Profilograph or equivalent will not be required:

- A. Pavement on horizontal curves having a centerline radius curve of less than 300 m and pavement within the superelevation transition of such curves.
- B. Pavement with a total thickness of 61 mm or less, or pavement with extensive grade correction which does not receive advance leveling operations as specified in Section 39-10.03, "Spreading," in Section 11-1, "Quality Control / Quality Assurance," in these special provisions, or where the edge of asphalt concrete conforms to curbs or gutters with a Profile Index greater than 80 mm per kilometer.
- C. Pavement for ramps and connectors with steep grades and high rates of superelevation and short sections of city or county streets and roads.
- D. Pavement within 15 m of a transverse joint that separates the pavement from an existing pavement not constructed under the contract.
- E. Shoulders and miscellaneous areas.

The Contractor shall schedule paving operations such that final rolling of asphalt concrete pavement is completed and initial runs of the profilograph are completed prior to opening new pavement to public traffic. Scheduling of these operations shall conform to the provisions for lane closures in "Maintaining Traffic" of these special provisions. In the event that initial profiles are not made prior to opening the pavement to public traffic, the initial profilograph runs shall be made the next day that traffic control is permitted for the area to be profiled.

The top surface of the uppermost layer of asphalt concrete surfacing that does not meet specified surface tolerances shall be brought within tolerance by abrasive grinding. Areas which have been subject to abrasive grinding shall receive a fog seal coat. Deviations in excess of 8 mm which cannot be brought into specified surface tolerances by abrasive grinding shall be corrected by either (1) removal and replacement or (2) placing an overlay of asphalt concrete. The corrective method for each area shall be selected by the Contractor and shall be as approved by the Engineer prior to beginning the corrective work. Replacement or overlay pavement not meeting specified tolerances shall be corrected by the methods specified above. Corrective work shall be at the Contractor's expense except that flagging costs will be paid for in conformance with the provisions in Section 12-2, "Flagging," of the Standard Specifications.

After abrasive grinding has been completed to reduce individual deviations in excess of 8 mm, additional grinding or corrections to the surface as specified above shall be performed as necessary to reduce the Profile Index of the pavement to the specified Profile Index value required for the area. The Contractor shall run profilograms of areas that have been subject to abrasive grinding or corrective work until the final profilograms indicate the Profile Index of the area is within the specified tolerance.

When abrasive grinding is used to bring the top surface of the uppermost layer of asphalt concrete surfacing within specified surface tolerances, additional abrasive grinding shall be performed as necessary to extend the area ground in each lateral direction so that the lateral limits of grinding are at a constant offset from, and parallel to the nearest lane line or pavement edge, and in each longitudinal direction so that the grinding begins and ends at lines normal to the pavement centerline, within any ground area. Ground areas shall be neat rectangular areas of uniform surface appearance.

Abrasive grinding shall conform to the provisions in the first paragraph and the last 4 paragraphs in Section 42-2.02, "Construction," of the Standard Specifications, except that the grinding residue shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The original of final profilograms that indicate the pavement surface is within the Profile Index specified shall become the property of the State and shall be delivered to the Engineer prior to acceptance of the contract.

Full compensation for performing all profile checks for Profile Index and furnishing final profilograms to the Engineer, for performing corrective work to the pavement surface including abrasive grinding, removing and replacing asphalt concrete or placing asphalt concrete overlay to bring the surface within the tolerance specified shall be considered as included in the contract price paid per tonne for asphalt concrete and no separate payment will be made therefor.

The area to which paint binder has been applied shall be closed to public traffic. Care shall be taken to avoid tracking binder material onto existing pavement surfaces beyond the limits of construction.

The Contractor shall schedule his paving operations such that each layer of asphalt concrete is placed on contiguous lanes of a traveled way each work shift. At the end of each work shift, the distance between the ends of the layers of asphalt concrete on adjacent lanes shall not be greater than 3 m nor less than 1.5 m. Additional asphalt concrete shall be placed along the transverse edge at the end of each lane and along the exposed longitudinal edges between adjacent lanes, hand raked, and compacted to form temporary conforms. Kraft paper, or other approved bond breaker, may be placed under the conform tapers to facilitate the removal of the taper when paving operations resume.

Where the existing pavement is to be widened by constructing a new structural section adjacent to the existing pavement, the new structural section, on both sides of the existing pavement, shall be completed to match the elevation of the edge of the existing pavement at each location prior to spreading and compacting asphalt concrete over the adjacent existing pavement.

Shoulders or median borders adjacent to a lane being paved shall be surfaced prior to opening the lane to public traffic.

Shoulder conform tapers, as shown on the plans, shall be placed concurrently with the paving of the adjacent lane.

Additional asphalt concrete surfacing material shall be placed along the edge of the surfacing at road connections and private drives, hand raked, if necessary, and compacted to form smooth tapered conforms. Full compensation for furnishing all labor and tools and doing all the work necessary to hand rake said conforms shall be considered as included in the contract prices paid per tonne for the various contract items of asphalt concrete surfacing involved and no additional compensation will be allowed therefor.

10-1.44 ASPHALT CONCRETE (MISCELLANEOUS AREAS)

Surfacing of miscellaneous areas with asphalt concrete shall conform to the provisions for miscellaneous areas in Section 39, "Asphalt Concrete," of the Standard Specifications and these special provisions.

Asphalt concrete placed in miscellaneous areas may be produced in conformance with the requirements for asphalt concrete placed on the traveled way in Section 11-1, "Quality Control / Quality Assurance," of these special provisions.

The amount of asphalt binder used in asphalt concrete placed in dikes, gutters, gutter flares, overside drains, and aprons at the ends of drainage structures shall be increased one percent by mass of the aggregate over the amount of asphalt binder determined for use in asphalt concrete placed on the traveled way.

Aggregate for asphalt concrete dikes shall conform to the 9.5-mm maximum grading specified in Section 39-2.02, "Aggregate," of the Standard Specifications.

Transitions between new and existing asphalt concrete dike will be measured and paid for as new dike of the type involved. Transitions between 2 types of new dike will be measured and paid for as the type with the largest cross sectional area.

The miscellaneous areas to be paid for at the contract price per square meter for place asphalt concrete (miscellaneous area) in addition to the prices paid for the materials involved shall be limited to the areas listed on the plans.

Asphalt concrete placed in miscellaneous areas will be paid for at the contract price per tonne for asphalt concrete in conformance with the provisions in Section 11-1, "Quality Control / Quality Assurance," of these special provisions. Section 39-11.02, "Statistical Evaluation and Determination of Pay Factor," in Section 11-1, "Quality Control / Quality Assurance," of these special provisions, shall not apply to asphalt concrete placed in miscellaneous areas. Payment for placing asphalt concrete in miscellaneous areas and dikes will be in conformance with the provisions in Section 39-8.02, "Payment," of the Standard Specifications.

10-1.45 PILING

GENERAL

Piling shall conform to the provisions in Section 49, "Piling," of the Standard Specifications, and these special provisions.

Unless otherwise specified, welding of any work performed in conformance with the provisions in Section 49, "Piling," of the Standard Specifications, shall be in conformance with the requirements in AWS D1.1.

Foundation recommendations are included in the "Information Handout" available to the Contractor as provided for in Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications.

Section 49-1.05, "Driving Equipment," of the Standard Specifications is amended by adding the following paragraph after the seventh paragraph:

- The use of followers or underwater hammers for driving piles will be permitted if authorized in writing by the Engineer. When a follower or underwater hammer is used, its efficiency shall be verified by furnishing the first pile in each bent or footing sufficiently long and driving the pile without the use of a follower or underwater hammer.

The first and second paragraphs of Section 49-4.01, "Description," of the Standard Specifications are amended to read:

- Cast-in-place concrete piles shall consist of one of the following:
 - A. Steel shells driven permanently to the required bearing value and penetration and filled with concrete.
 - B. Steel casings installed permanently to the required penetration and filled with concrete.
 - C. Drilled holes filled with concrete.
 - D. Rock sockets filled with concrete.
- The drilling of holes shall conform to the provisions in these specifications. Concrete filling for cast-in-place concrete piles is designated by compressive strength and shall have a minimum 28-day compressive strength of 25 MPa. At the option of the Contractor, the combined aggregate grading for the concrete shall be either the 25-mm maximum grading, the 12.5-mm maximum grading, or the 9.5-mm maximum grading. Concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," and Section 51, "Concrete Structures." Reinforcement shall conform to the provisions in Section 52, "Reinforcement."

Alternative "X" type piles shall have a dimension, T, not less than 355 mm at Prunedale Overcrossing (Br. No. 44-0276Y) and Prunedale Retaining Wall No. 2 (Br. No. 44-RW2), as shown on the plans.

Jetting and Drilling

Jetting to obtain the specified penetration in conformance with the provisions in Section 49-1.05, "Driving Equipment," of the Standard Specifications shall not be used for driven type piles.

Drilling to obtain the specified penetration in conformance with the provisions in Section 49-1.05, "Driving Equipment," of the Standard Specifications shall only be used for driven type piles when hard driving is demonstrated and upon approval of the Engineer, at the locations and to the bottom of hole elevations listed in the following table. Materials resulting from drilling holes shall be disposed of in conformance with the provisions in Section 19-2.06, "Surplus Material," of the Standard Specifications.

Bridge Name or Number	Abutment Number	Bent Number	Elevation of Bottom of Hole
Prunedale Overcrossing	Abut 1 and Abut 2	---	17

Predrilled Holes

Piles at Retaining Wall No. 2 shall not be driven within one meter of the proposed culvert unless the culvert is constructed after piles are driven. When piles are required within one meter of the finished culvert, they shall be driven in predrilled, cased holes with the bottom of casing at elevation shown on plans. The said predrilled holes shall be in conformance with the provisions in Section 49-1.06, "Predrilled Holes," and Section 49-6.02, "Payment," of the Standard Specifications. The casing, at the Contractor's option, may be temporary. The casing shall be furnished and placed tight in the hole where shown on the plans to prevent quick soil conditions or caving of the hole. The casing shall be of sufficient strength to withstand the loads from installation, removal, and earth pressure.

Full compensation for furnishing, installing and removing the casings shall be considered as included in the contract unit price paid for drive pile (Class 900) and no additional compensation will be allowed therefor.

MEASUREMENT AND PAYMENT (PILING)

Measurement and payment for the various types and classes of piles shall conform to the provisions in Sections 49-6.01, "Measurement," and 49-6.02, "Payment," of the Standard Specifications and these special provisions.

The first paragraph of Section 49-6.02, "Payment," of the Standard Specifications is amended to read:

- Timber, steel, and precast prestressed concrete piles, and cast-in-place concrete piles consisting of driven shells filled with concrete, will be paid for at the contract price per meter for furnish piling and the contract unit price for drive pile.

The third paragraph of Section 49-6.02, "Payment," of the Standard Specifications is amended to read:

- The contract price paid per meter for cast-in-drilled-hole concrete piling shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in drilling holes, disposing of material resulting from drilling holes, temporarily casing holes and removing water when necessary, furnishing and placing concrete and reinforcement, and constructing reinforced concrete extensions, complete in place, to the required penetration, as shown on the plans, as specified in these specifications and in the special provisions, and as directed by the Engineer.

Full compensation for furnishing and placing additional testing reinforcement, for load test anchorages, and for cutting off test piles as specified, shall be considered as included in the contract price paid for piling of the type or class shown in the Engineer's Estimate, and no additional compensation will be allowed.

No additional compensation or extension of time will be made for additional foundation investigation, installation and testing of indicator piling, cutting off piling and restoring the foundation investigation and indicator pile sites, and review of request by the Engineer.

The seventh paragraph of Section 49-6.02, "Payment," of the Standard Specifications is amended to read:

- The contract unit price paid for drive pile shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in driving timber, concrete, and steel piles, driving steel shells for cast-in-place concrete piles, placing filling materials for cast-in-place concrete piles, and cutting off piles, all complete in place to the required bearing and penetration, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

10-1.46 PRESTRESSING CONCRETE

Prestressing concrete shall conform to the provisions in Section 50, "Prestressing Concrete," of the Standard Specifications and these special provisions.

The tenth paragraph of Section 50-1.05, "Prestressing Steel," of the Standard Specifications is amended to read:

- Prestressing steel for post-tensioning which is installed in members prior to placing and curing of the concrete, shall be continuously protected against rust or other corrosion, until grouted, by means of a corrosion inhibitor placed in the ducts or applied to the steel in the duct. The corrosion inhibitor shall conform to the provisions in Section 50-1.05, "Prestressing Steel," of the Standard Specifications.

The third paragraph of Section 50-1.08, "Prestressing," of the Standard Specifications is amended to read:

- Working force and working stress will be considered as the force and stress remaining in the prestressing steel after all losses, including creep and shrinkage of concrete, elastic compression of concrete, creep of steel, losses in post-tensioned prestressing steel due to sequence of stressing, friction and take up of anchorages, and all other losses peculiar to the method or system of prestressing have taken place or have been provided for.

The details shown on the plans for cast-in-place prestressed box girder bridges are based on a bonded full length draped tendon prestressing system. For these bridges the Contractor may, in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications, propose an alternative prestressing system utilizing bonded partial length tendons provided the proposed system and associated details meet the following requirements:

- A. The proposed system and details shall provide moment and shear resistances at least equal to those used for the design of the structure shown on the plans.
- B. The concrete strength shall not be less than that shown on the plans.
- C. Not less than 35 percent of the total prestressing force at any section shall be provided by full length draped tendons.
- D. Anchorage blocks for partial length tendons shall be located so that the blocks will not interfere with the placement of the utility facilities shown on the plans or of any future utilities to be placed through openings shown on the plans.
- E. Temporary prestressing tendons, if used, shall be detensioned, and the temporary ducts shall be filled with grout before completion of the work. Temporary tendons shall be either removed or fully encased in grout before completion of the work.
- F. All details of the proposed system, including supporting checked calculations, shall be included in the drawings submitted in conformance with the provisions in Section 50-1.02, "Drawings," of the Standard Specifications.

Moments and shears for loads used in the design shown on the plans will be made available to the Contractor upon written request to the Engineer.

10-1.47 CONCRETE STRUCTURES

Portland cement concrete structures shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

GENERAL

Shotcrete shall not be used as an alternative construction method for reinforced concrete members unless otherwise specified.

Neoprene strip shall be furnished and installed at abutment backwall joint protection in conformance with the details shown on the plans, the provisions in the Standard Specifications, and these special provisions.

Furnishing and installing neoprene strip shall conform to the requirements for strip waterstops as provided in Section 51-1.145, "Strip Waterstops," of the Standard Specifications, except that the protective board will not be required.

Vertical, horizontal, radial or normal dimensions shown on the Typical Section in the plans, are for zero percent cross-slope. At the Contractor's option, the Typical Section of superelevated concrete box girder structures with (1) sloping exterior girders, (2) a straight uninterrupted cross slope between edges of deck, and (3) a single profile grade line, may be rotated around the profile grade line in superelevation areas. The horizontal distances between the profile grade line and the edges of deck shall remain unchanged. The planned girder widths and slab thicknesses shall remain unchanged and the interior girder stems shall remain vertical at the planned locations.

The first paragraph of Section 51-1.20, "Sidewalks, Curbs and Stairways on Structures," of the Standard Specifications is amended to read:

Contract No. <Dist>-<Contract_No>

- The concrete shall be finished in conformance with the provisions for finishing surfaces in Section 73-1.06, "Sidewalk, Gutter Depression, Island Paving, Curb Ramp (Wheelchair Ramp), and Driveway Construction," except that surfaces shall not be marked.

FALSEWORK

Falsework shall be designed and constructed in conformance with the requirements in Section 51-1.06, "Falsework," of the Standard Specifications and these special provisions.

Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications is amended to read:

51-1.06A Falsework Design and Drawings

- The Contractor shall submit to the Engineer working drawings and design calculations for falsework proposed for use at bridges. For bridges where the height of any portion of the falsework, as measured from the ground line to the soffit of the superstructure, exceeds 4.25 m; or where any individual falsework clear span length exceeds 4.85 m; or where provision for vehicular, pedestrian, or railroad traffic through the falsework is made; the drawings shall be signed by an engineer who is registered as a Civil Engineer in the State of California. Six sets of the working drawings and 2 copies of the design calculations shall be furnished. Additional working drawings and design calculations shall be submitted to the Engineer when specified in "Railroad Relations and Insurance" of the special provisions.
- The falsework drawings shall include details of the falsework erection and removal operations showing the methods and sequences of erection and removal and the equipment to be used. The details of the falsework erection and removal operations shall demonstrate the stability of all or any portions of the falsework during all stages of the erection and removal operations.
- Attention is directed to Section 5-1.02, "Plans and Working Drawings."
- For falsework over railroads, approval by the Engineer of the falsework drawings will be contingent upon the drawings being satisfactory to the railroad company involved.
- Except for placement of foundation pads and piles, the construction of any unit of falsework shall not start until the Engineer has reviewed and approved the drawings for that unit.
- Except as otherwise provided in the special provisions, the Contractor shall allow 3 weeks after complete drawings and all support data are submitted, for the review of any falsework plan.
- In the event that several falsework plans are submitted simultaneously, or an additional plan is submitted for review before the review of a previously submitted plan has been completed, the Contractor shall designate the sequence in which the plans are to be reviewed. In such event, the time to be provided for the review of any plan in the sequence shall be not less than the review time specified above for that plan, plus 2 weeks for each plan of higher priority which is still under review. A falsework plan submittal shall consist of plans for a single bridge, or portion thereof, or a single frame of a multi-frame bridge.
- Should the Engineer fail to complete the review within the time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in falsework plan review, the delay will be considered a right of way delay as specified in Section 8-1.09, "Right of Way Delays."
- The Contractor may revise approved falsework drawings provided sufficient time is allowed for the Engineer's review and approval before construction is started on the revised portions. The additional time will not be more than that which was originally allowed.
- If structural composite lumber is proposed for use, the falsework drawings shall clearly identify the structural composite lumber members by grade (E value), species, and type. The Contractor shall provide technical data from the manufacturer showing the tabulated working stress values of the composite lumber. The Contractor shall furnish a certificate of compliance as specified in Section 6-1.07, "Certificates of Compliance," for each delivery of structural composite lumber to the project site.
- The falsework drawings shall include a superstructure placing diagram showing the concrete placing sequence and construction joint locations. When a schedule for placing concrete is shown on the contract plans, no deviation will be permitted.
- The maximum length of falsework spans used to support T-beam girder bridges shall not exceed 4.3 m plus 8.5 times the depth of the T-beam girder.
- When footing type foundations are to be used, the Contractor shall determine the bearing value of the soil and shall show the values assumed in the design of the falsework on the falsework drawings.
- When pile type foundations are to be used, the falsework drawings shall show the maximum horizontal distance that the top of a falsework pile may be pulled in order to position the falsework pile under its cap. The falsework plans shall also show the maximum allowed deviation of the top of the pile, in its final position, from a vertical line through the point of fixity of the pile.

- For falsework piles with a calculated loading capacity greater than 900 kN, the falsework piles shall be designed by an engineer who is registered as either a Civil Engineer or a Geotechnical Engineer in the State of California, and the calculations shall be submitted to the Engineer.
- Anticipated total settlements of falsework and forms shall be shown on the falsework drawings. These should include falsework footing settlement and joint take-up. Anticipated settlements shall not exceed 25 mm. Falsework supporting deck slabs and overhangs on girder bridges shall be designed so that there will be no differential settlement between the girders and the deck forms during placement of deck concrete.
- Falsework footings shall be designed to carry the load imposed upon the footings without exceeding the estimated soil bearing values and anticipated settlements.
- Foundations for individual steel towers where the maximum leg load exceeds 130 kN shall be designed and constructed to provide uniform settlement under all legs of each tower under all loading conditions.
- The support systems for form panels supporting concrete deck slabs and overhangs on girder bridges shall also be considered to be falsework and designed as such.
- Temporary bracing shall be provided, as necessary, to withstand all imposed loads during erection, construction, and removal of any falsework. The falsework drawings shall show provisions for the temporary bracing, or methods to be used to conform to this requirement during each phase of erection and removal. Wind loads shall be included in the design of the bracing or methods.
- The falsework design calculations shall show the stresses and deflections in load supporting members.
- The design of falsework will not be approved unless it is based on the use of loads and conditions which are no less severe than those described in Section 51-1.06A(1), "Design Loads," and based on the use of stresses and deflections which are no greater than those described in Section 51-1.06A(2), "Design Stresses, Loadings, and Deflections." The Contractor is responsible for the proper evaluation of the falsework materials and design of the falsework to safely carry the actual loads imposed.

Section 51-1.06A(1), "Design Loads," of the Standard Specifications is amended to read:

51-1.06A(1) Design Loads

- The design load for falsework shall consist of the sum of dead and live vertical loads, and an assumed horizontal load. The minimum total design load for any falsework, including members that support walkways, shall be not less than 4800 N/m² for the combined live and dead load regardless of slab thickness.
- Dead loads shall include the loads due to the mass of concrete, reinforcing steel, forms, and falsework. The loads due to the mass of concrete, reinforcing steel, and forms shall be assumed to be not less than 25 kN/m³ for normal concrete and not less than 20 kN/m³ for lightweight concrete.
- Live loads shall consist of the actual load of any equipment to be supported by falsework applied as concentrated loads at the points of contact, and a uniform load of not less than 960 N/m² applied over the area supported, plus 1100 N/m applied at the outside edge of deck overhangs.
- The assumed horizontal load to be resisted by the falsework bracing system shall be the sum of the actual horizontal loads due to equipment, construction sequence, or other causes, and an allowance for wind, but in no case shall the assumed horizontal load to be resisted in any direction be less than 2 percent of the total dead load. The falsework shall be designed so that it will have sufficient rigidity to resist the assumed horizontal load without considering the load due to the concrete.
- The minimum horizontal load to be allowed for wind on heavy-duty steel shoring or steel pipe column falsework having a vertical load carrying capacity exceeding 130 kN per leg or column shall be the sum of the products of the wind impact area, shape factor, and applicable wind pressure value for each height zone. The wind impact area is the total projected area of all the elements in the tower face or falsework bent normal to the direction of the applied wind. The shape factor shall be taken as 2.2 for heavy-duty shoring and 1.0 for pipe column falsework. Wind pressure values shall be determined from the following table:

Height Zone (Meters above ground)	Wind Pressure Value (Pa)	
	Shores or Columns Adjacent to Traffic	At Other Locations
0-9	960	720
9-15	1200	960
15-30	1440	1200
over 30	1675	1440

- The minimum horizontal load to be allowed for wind on all other types of falsework, including falsework supported on heavy-duty shoring or pipe column falsework, shall be the sum of the products of the wind impact area and applicable wind pressure value for each height zone. The wind impact area is the gross projected area of the falsework and any unrestrained portion of the permanent structure, excluding the areas between falsework bents or towers where diagonal bracing is not used. Wind pressure values shall be determined from the following table:

Height Zone (Meters above ground)	Wind Pressure Value (Pa)	
	For Members Over and Bents Adjacent to Traffic Opening	At Other Locations
0 to 9	2.0 Q	1.5 Q
9 to 15	2.5 Q	2.0 Q
15 to 30	3.0 Q	2.5 Q
Over 30	3.5 Q	3.0 Q

$Q = 48 + 31.4 W$; but shall not be more than 479 Pa.

W = width of the falsework system, in meters, measured in the direction of the wind force being considered.

- The entire superstructure cross-section, except railing, shall be considered to be placed at one time except as provided herein. Girder stems and connected bottom slabs, if placed more than 5 days prior to the top slab, may be considered to be self supporting between falsework posts at the time the top slab is placed provided that the distance between falsework posts does not exceed 4 times the depth of the portion of the girder placed in the first pour.
- In addition to the minimum requirements specified in this Section 51-1.06A, falsework for box girder structures with internal falsework bracing systems using flexible members capable of withstanding tensile forces only, shall be designed to include the vertical effects caused by the elongation of the flexible member and the design horizontal load combined with the dead and live loads imposed by concrete placement for the girder stems and connected bottom slabs. Falsework comprised of individual steel towers with bracing systems using flexible members capable of withstanding tensile forces only to resist overturning, shall be exempt from these additional requirements.
- If the concrete is to be prestressed, the falsework shall be designed to support any increased or readjusted loads caused by the prestressing forces.

Section 51-1.06A(2), "Design Stresses, Loadings, and Deflections," of the Standard Specifications is amended to read:

51-1.06A(2) Design Stresses, Loadings, and Deflections

- The maximum allowable design stresses and loadings listed in this Section 51-1.06A(2), are based on the use of undamaged, high-quality materials, and such stresses and loadings shall be reduced by the Contractor if lesser quality materials are to be used.
- The maximum allowable stresses, loadings, and deflections used in the design of the falsework shall be as follows:

Timber:

Compression perpendicular to the grain	3.1 MPa
Compression parallel to the grain	$3310 \div (L/d)^2$ MPa; not to exceed 11 MPa
Flexural stress	12.4 MPa; 10.3 MPa for members with a nominal depth of 205 mm or less
Horizontal shear	1.0 MPa
Axial tension	8.3 MPa
Deflection due to concrete loading only	0.0042 of the span, irrespective of deflection compensated for by camber strips
Modulus of elasticity (E)	11×10^3 MPa
Timber piles	400 kN

L = unsupported length (mm).

d = least dimension of a square or rectangular column, or the width of a square of equivalent cross-sectional area for round columns (mm).

- Timber connections shall be designed in conformance with the procedures, stresses, and loads permitted in the

Falsework Manual as published by the Department of Transportation.

Steel:

- For identified grades of steel, design stresses, except stresses due to flexural compression, shall not exceed those specified in the Manual of Steel Construction as published by the AISC.
- When the grade of steel cannot be positively identified, design stresses, except stresses due to flexural compression, shall not exceed either those specified in the AISC Manual for ASTM Designation: A 36/A 36M steel or the following:

Tension, axial and flexural	152 MPa
Compression, axial	110 $300-2.62(L/r)^2$ kPa; except L/r shall not exceed 120
Shear on gross section of web of rolled shapes	100 MPa
Web crippling for rolled shapes	186 MPa

- For all grades of steel, design stresses and deflections shall not exceed the following:

Compression, flexural	83 000 MPa, but not to exceed 152 MPa for unidentified steel or steel conforming to the requirements in ASTM Designation: A 36/A 36M nor $0.6F_y$ for other identified steel
Deflection due to concrete loading only	0.0042 of the span, irrespective of deflection compensated for by camber strips

- In the foregoing formulas, L is the unsupported length; d is the least dimension of rectangular columns, or the width of a square of equivalent cross-sectional area for round columns, or the depth of beams; b is the width and t is the thickness of the compression flange; and r is the radius of gyration of the member. All dimensions are expressed in millimeters. F_y is the specified minimum yield stress, in MPa, for the grade of steel used.
- The modulus of elasticity (E) used for steel shall be 20.7×10^4 MPa.

Manufactured Assemblies:

- The maximum loadings and deflections used on jacks, brackets, columns, joists, and other manufactured devices shall not exceed the manufacturer's recommendations except that the dead load deflection of the joists used at locations other than under deck slabs between girders shall not exceed 0.0042 of their spans. If requested by the Engineer, the Contractor shall furnish engineering data from the manufacturer verifying the manufacturer's recommendations, or shall perform tests as necessary to demonstrate the adequacy of the devices proposed for use.

Welding and Nondestructive Testing

Welding of steel members, except for when fillet welds are used where load demands are less than or equal to 175 N/mm for each 3 mm of fillet weld, shall conform to AWS D1.1 or other recognized welding standard. The welding standard to be utilized shall be specified by the Contractor on the working drawings.

Splices made by field welding of steel beams at the project site shall undergo nondestructive testing (NDT). At the option of the Contractor, either ultrasonic testing (UT) or radiographic testing (RT) shall be used as the method of NDT for each field weld and any repair made to a previously welded splice in a steel beam. Testing shall be performed at locations selected by the Contractor. The length of a splice weld where NDT is to be performed, shall be a cumulative weld length equal to 25 percent of the original splice weld length. The cover pass shall be ground smooth at the locations to be tested. The acceptance criteria shall conform to the requirements of AWS D1.1, Section 6, for cyclically loaded nontubular connections subject to tensile stress. If repairs are required in a portion of the weld, additional NDT shall be performed on the repaired sections. The NDT method chosen shall be used for an entire splice evaluation including any required repairs.

For all field welded splices and previously welded splices, the Contractor shall furnish to the Engineer a letter of certification which certifies that all welding and NDT, including visual inspection, are in conformance with the specifications and the welding standard shown on the approved working drawings. The letter of certification shall be signed by an engineer who is registered as a Civil Engineer in the State of California and shall be provided prior to placing any concrete for which the falsework is being erected to support.

Section 51-1.06A(3), "Special Locations," of the Standard Specifications is amended to read:

51-1.06A(3) Special Locations

- In addition to the minimum requirements specified in this Section 51-1.06A, falsework over or adjacent to roadways or railroads which are open to traffic shall be designed and constructed so that the falsework will be stable if subjected to impact by vehicles. Falsework posts which support members that cross over a roadway or railroad shall be considered as adjacent to roadways or railroads. Other falsework posts shall be considered as adjacent to roadways or railroads only if they are located in the row of falsework posts nearest to the roadway or railroad, and the horizontal distance from the traffic side of the falsework to the edge of pavement, or to a point 3 m from the centerline of track, is less than the total height of the falsework and forms. The Contractor shall provide any additional features for the work needed to ensure that falsework will be stable if subjected to impact by vehicles and to comply with the provisions in Section 7-1.09, "Public Safety." The falsework design at these locations shall include, but not be limited to, the following minimum provisions:

The vertical load used for the design of falsework posts and towers, but not footings, which support the portion of the falsework over openings, shall be the greater of the following:

- (1) 150 percent of the design load calculated in conformance with the provisions for design load previously specified but not including any increased or readjusted loads caused by the prestressing forces, or
- (2) the increased or readjusted loads caused by the prestressing forces.

Falsework posts adjacent to roadways or railroads shall consist of either steel with a minimum section modulus about each axis of $156 \times 10^3 \text{ mm}^3$, or sound timbers with a minimum section modulus about each axis of $4.1 \times 10^6 \text{ mm}^3$.

Each falsework post adjacent to roadways or railroads shall be mechanically connected to its supporting footing at its base, or otherwise laterally restrained, so as to withstand a force of not less than 9 kN applied at the base of the post in any direction except toward the roadway or railroad track. The posts also shall be mechanically connected to the falsework cap or stringer. The mechanical connection shall be capable of resisting a load in any horizontal direction of not less than 4.5 kN.

For falsework spans over roadways, all exterior falsework stringers, and stringers adjacent to the ends of discontinuous caps, the stringer or stringers over points of minimum vertical clearance and every fifth remaining stringer, shall be mechanically connected to the falsework cap or framing. The mechanical connections shall be capable of resisting a load in any direction, including uplift on the stringer, of not less than 2.2 kN. The connections shall be installed before traffic is allowed to pass beneath the span. For falsework spans over railroads, all falsework stringers shall be so connected to caps.

When timber members are used to brace falsework bents which are located adjacent to roadways or railroads, all connections for the timber bracing shall be of the bolted type using 16-mm diameter or larger bolts.

The falsework shall be located so that falsework footings or piles are at least 75 mm clear of railing posts and barriers, and all other falsework members are at least 0.3-m clear of railing members and barriers.

Falsework bents within 6 m of the center line of a railroad track shall be sheathed solid in the area between 1 m and 5 m above the track elevation on the side facing the track. Sheathing shall consist of plywood not less than 16-mm thick or lumber not less than 19-mm thick. Bracing on these bents shall be adequate so that the bent will resist the required assumed horizontal load or 22 kN, whichever is greater.

The dimensions of the clear openings to be provided through falsework for roadways shall be as specified in "Maintaining Traffic," of the special provisions.

The dimensions of clear openings to be provided through the falsework for railroads shall be as specified in "Railroad Relations and Insurance," of the special provisions.

Section 51-1.06B, "Falsework Construction," of the Standard Specifications is amended to read:

51-1.06B Falsework Construction

- The falsework shall be constructed to substantially conform to the falsework drawings. The materials used in the falsework construction shall be of the quality necessary to sustain the stresses required by the falsework design. When manufactured assemblies are used in falsework, the Contractor shall furnish to the Engineer a letter of certification which certifies that all components of these manufactured assemblies are used in conformance with the

manufacturer's recommendations. The workmanship used in falsework construction shall be of such quality that the falsework will support the loads imposed on the falsework without excessive settlement or take-up beyond that shown on the falsework drawings.

- Falsework shall be founded on a solid footing safe against undermining, protected from softening, and capable of supporting the loads imposed on the falsework. When requested by the Engineer, the Contractor shall demonstrate by suitable load tests that the soil bearing values assumed for the design of the falsework do not exceed the supporting capacity of the soil.
- When falsework is supported on piles, the piles shall be driven and the actual bearing value assessed in conformance with the provisions in Section 49, "Piling."
- For falsework piles with a calculated loading capacity greater than 900 kN, the Contractor shall conduct dynamic monitoring of pile driving and conduct penetration and bearing analyses based on a wave equation analysis. These analyses shall be signed by an engineer who is registered as a Civil Engineer in the State of California and submitted to the Engineer prior to completion of falsework erection.
- When falsework is over or adjacent to roadways or railroads, all details of the falsework system which contribute to horizontal stability and resistance to impact, except for bolts in bracing, shall be installed at the time each element of the falsework is erected and shall remain in place until the falsework is removed.
- Prior to the placement of falsework members above the stringers, the final bracing system for the falsework shall be installed.
- Temporary railing (Type K), conforming to the provisions in Section 12-3, "Traffic-Handling Equipment and Devices," shall be installed on both sides of all vehicular openings through falsework and, when ordered by the Engineer, at all other falsework less than 3.6 m from the edge of a traffic lane. Temporary railings shall begin approximately 46 m in advance of the falsework and shall extend past the falsework, in the direction of adjacent traffic flow. For 2-way traffic openings, the temporary railing shall extend at least 18 m past the falsework, in the direction of adjacent traffic flow. The location and length of railing and the type of flare to be used shall be as ordered by the Engineer. The clear vehicular opening between temporary railings shall be not less than that specified in the special provisions.
- The installation of temporary railing shall be complete before falsework erection is begun. Temporary railing at falsework shall not be removed until the removal is approved by the Engineer.
- Temporary railing (Type K) installed as specified above will be measured and paid for as provided in Section 12-4, "Measurement and Payment," except that when the Engineer's Estimate does not include a contract item for temporary railing (Type K), full compensation for furnishing, placing, maintaining, repairing, replacing, and removing the temporary railing at falsework locations as specified in this Section 51-1.06B, shall be considered as included in the contract prices paid for the various items of work requiring falsework, and no separate payment will be made therefor.
- Camber strips shall be used where directed by the Engineer to compensate for falsework deflection, vertical alignment, and anticipated structure deflection. The Engineer will furnish to the Contractor the amount of camber to be used in constructing the falsework.
- The Contractor shall provide tell-tales attached to the soffit forms and readable from the ground in enough systematically placed locations to determine the total settlement of the entire portion of the structure where concrete is being placed.
- Deck slab forms between girders shall be constructed with no allowance for settlement relative to the girders.
- Dead loads, other than those due to forms and reinforcing steel, shall not be applied to any falsework until authorized by the Engineer.
- Should unanticipated events occur, including settlements that deviate by more than ± 10 mm from those indicated on the falsework drawings, which in the opinion of the Engineer would prevent obtaining a structure conforming to the requirements of these specifications, the placing of concrete shall be discontinued until corrective measures satisfactory to the Engineer are provided. In the event satisfactory measures are not provided prior to initial set of the concrete in the affected area, the placing of concrete shall be discontinued at a location determined by the Engineer. All unacceptable concrete shall be removed.

Section 51-1.06C, "Removing Falsework," of the Standard Specifications is amended to read:

51-1.06C Removing Falsework

- Falsework supporting any span of a simple span bridge shall not be released before 10 days after the last concrete, excluding concrete above the bridge deck, has been placed. Unless otherwise permitted by the Engineer, falsework supporting any span of a continuous or rigid frame bridge shall not be released before 10 days after the last concrete, excluding concrete above the bridge deck, has been placed in that span and in the adjacent portions of each adjoining span for a length equal to at least one-half the length of the span where falsework is to be released.
- Falsework for cast-in-place prestressed portions of structures shall not be released until after the prestressing

steel has been tensioned.

- Falsework supporting any span of a continuous or rigid frame bridge shall not be removed until all required prestressing has been completed in that span and in the adjacent portions of each adjoining span for a length equal to at least one-half the length of the span where falsework is to be released.
- Falsework for arch bridges shall be removed uniformly and gradually, beginning at the crown and working toward the springing, to permit the arch to take its load slowly and evenly. Falsework for adjacent arch spans shall be struck simultaneously.
- Falsework supporting overhangs, deck slabs between girders, and girder stems which slope 45 degrees or more off vertical shall not be released before 7 days after the deck concrete has been placed.
- Falsework supporting the sides of the girder stems which slope less than 45 degrees off vertical may be removed prior to placing deck slab concrete, providing a reshoring system is installed. The reshoring system shall consist of lateral supports which are designed to resist all rotational forces acting on the stem, including those caused by the placement of deck slab concrete. The lateral supports shall be installed immediately after each form panel is removed and prior to the release of supports for the adjacent form panel.
- Falsework for bent caps which will support steel or precast concrete girders shall not be released before 7 days after the cap concrete has been placed. Girders shall not be erected onto the bent caps until the concrete in the cap has attained a compressive strength of 18 MPa or 80 percent of the specified strength, whichever is higher.
- Unless otherwise specified, removing falsework supporting any span of structural members subject to bending, shall conform to the requirements for removing falsework supporting any span of a simple span bridge.
- In addition to the above requirements, no falsework for bridge spans shall be released until the supported concrete has attained a compressive strength of 18 MPa or 80 percent of the specified strength, whichever is higher.
- Falsework for box culverts and other structures with decks lower than the roadway pavement and with span lengths of 4.25 m or less shall not be released until the last placed concrete has attained a compressive strength of 11 MPa, provided that curing of the concrete is not interrupted. Falsework removal for other box culverts shall conform to the requirements for release of bridge falsework.
- Falsework for arch culverts shall not be released before 40 hours after the supported concrete has been placed.
- The falsework removal operation shall be conducted in such a manner that any portion of the falsework not yet removed remains in a stable condition at all times.
- All falsework materials shall be completely removed. Falsework piling shall be removed at least 0.6-m below the surface of the original ground or original streambed. When falsework piling is driven within the limits of ditch or channel excavation areas, the falsework piling within those areas shall be removed to at least 0.6-m below the bottom and side slopes of the excavated areas.
- All debris and refuse resulting from the work shall be removed and the premises left in a neat and presentable condition.

COST REDUCTION INCENTIVE PROPOSALS FOR CAST-IN-PLACE PRESTRESSED BOX GIRDER BRIDGES

Except as provided herein, cast-in-place prestressed box girder bridges shall be constructed in conformance with the details shown on the plans and the provisions in Section 50, "Prestressing Concrete," and Section 51, "Concrete Structures," of the Standard Specifications.

If the Contractor submits cost reduction incentive proposals for cast-in-place prestressed box girder bridges, the proposals shall be in conformance with the provisions in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications and these special provisions.

The Engineer may reject any proposal which, in the Engineer's judgment, may not produce a structure which is at least equivalent to the planned structure.

At the time the cost reduction incentive proposal (CRIP) is submitted to the Engineer, the Contractor shall also submit 4 sets of the proposed revisions to the contract plans, design calculations, and calculations from an independent checker for all changes involved in the proposal, including revisions in camber, predicted deck profile at each construction stage, and falsework requirements to the Office of Structure Design, Documents Unit, P.O. Box 942874, Sacramento, CA 94274-0001 (1801 30th Street, Sacramento, CA 95816), telephone (916) 227-8230. When notified in writing by the Engineer, the Contractor shall submit 12 sets of the CRIP plan revisions and calculations to the Office of Structure Design for final approval and use during construction. The calculations shall verify that all requirements are satisfied. The CRIP plans and calculations shall be signed by an engineer who is registered as a Civil Engineer in the State of California.

The CRIP plans shall be either 279 mm x 432 mm, or 559 mm x 864 mm in size. Each CRIP plan sheet and calculation sheet shall include the State assigned designations for the contract number, bridge number, full name of the structure as shown on the contract plans, and District-County-Route-Kilometer Post. Each CRIP plan sheet shall be numbered in the lower right hand corner and shall contain a blank space in the upper right hand corner for future contract sheet numbers.

Within 3 weeks after final approval of the CRIP plan sheets, one set of the corrected good quality prints on 75-g/m²

(minimum) bond paper, 559 mm x 864 mm in size, of all CRIP plan sheets prepared by the Contractor for each CRIP shall be furnished to the Office of Structure Design, Documents Unit.

Each CRIP shall be submitted prior to completion of 25 percent of the contract working days and sufficiently in advance of the start of the work that is proposed to be revised by the CRIP to allow time for review by the Engineer and correction by the Contractor of the CRIP plans and calculations without delaying the work. The Contractor shall allow a minimum of 4 weeks for the review of a CRIP. In the event that several CRIPs are submitted simultaneously, or an additional CRIP is submitted for review before the review of a previously submitted CRIP has been completed, the Contractor shall designate the sequence in which the CRIPs are to be reviewed. In this event, the time to be provided for the review of any proposal in the sequence shall be not less than the review time specified herein for that proposal, plus 2 weeks for each CRIP of higher priority which is still under review.

Should the review not be complete by the date specified in the Contractor's CRIP, or such other date as the Engineer and Contractor may subsequently have agreed to in writing and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review of CRIP plans and calculations, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications except that the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications shall not apply.

Permits and approvals required of the State have been obtained for the structures shown on the plans. Proposals which result in a deviation in configuration may require new permits or approvals. The Contractor shall be responsible for obtaining the new permits and approvals before the Engineer will reach a decision on the proposal. Delays in obtaining permits and approvals will not be reason for granting an extension of contract time.

All proposed modifications shall be designed in conformance with the bridge design specifications and procedures currently employed by the Department. The proposal shall include all related, dependent or incidental changes to the structure and other work affected by the proposal. The proposal will be considered only when all aspects of the design changes are included for the entire structure. Changes, such as but not limited to, additional reinforcement and changes in location of reinforcement, necessary to implement the CRIP after approval by the Engineer, shall be made at the Contractor's expense.

Modifications may be proposed in (1) the thickness of girder stems and deck slabs, (2) the number of girders, (3) the deck overhang dimensions as specified herein, (4) the amount and location of reinforcing steel, (5) the amount and location of prestressing force in the superstructure, and (6) the number of hinges, except that the number of hinges shall not be increased. The strength of the concrete used may be increased but the strength employed for design or analysis shall not exceed 42 MPa.

Modifications proposed to the minimum amount of prestressing force which must be provided by full length draped tendons are subject to the provisions in "Prestressing Concrete" of these special provisions.

No modifications will be permitted in (1) the foundation type, (2) the span lengths or (3) the exterior dimensions of columns or bridge superstructure, except that the overhang dimension from face of exterior girder to the outside edge of roadway deck may be uniformly increased or decreased by 25 percent on each side of the box girder section. Fixed connections at the tops and bottoms of columns shown on the plans shall not be eliminated.

The Contractor shall be responsible for determining construction camber and obtaining the final profile grade as shown on the plans.

The Contractor shall reimburse the State for the actual cost of investigating CRIPs for cast-in-place prestressed box girder bridges submitted by the Contractor. The Department will deduct this cost from any moneys due, or that may become due the Contractor under the contract, regardless of whether or not the proposal is approved or rejected.

SLIDING BEARINGS

Sliding bearings consisting of elastomeric bearing pads lubricated with grease and covered with sheet metal shall conform to the following requirements:

- A. Grease shall conform to the requirements of Military Specification: MIL-S-8660. A uniform film of grease shall be applied to the upper surface of the pads prior to placing the sheet metal.
- B. Sheet metal shall be commercial quality galvanized sheet steel. The sheet metal shall be smooth and free of kinks, bends, or burrs.
- C. Construction methods and procedures shall prevent grout or concrete seepage into the sliding bearing assembly.

ELASTOMERIC BEARING PADS

Elastomeric bearing pads shall conform to the provisions in Section 51-1.12H, "Elastomeric Bearing Pads," of the Standard Specifications and these special provisions.

The table in the ninth paragraph of Section 51-1.12H(1), "Plain and Fabric Reinforced Elastomeric Bearing Pads," of the Standard Specifications is amended to read:

Tensile strength, percent	-15
Elongation at break, percent	-40; but not less than 300% total elongation of the material
Hardness, points	+10

MEASUREMENT AND PAYMENT

Measurement and payment for concrete in structures shall conform to the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for concrete removal, as shown on the plans, for existing double reinforced concrete box culvert below the Prunedale Retaining Wall No. 1 (Br. No. 44-0280M), shall be considered as included in the contract price paid per cubic meter for Class 1 concrete (box culvert) and no separate payment will be made therefor.

10-1.48 STRUCTURE APPROACH SLABS (Type N) and (Type EQ)

This work shall consist of constructing reinforced concrete approach slabs, structure approach drainage system, and treated permeable base at structure approaches in conformance with the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

GENERAL

Attention is directed to the section "Engineering Fabrics" of these special provisions.

STRUCTURE APPROACH DRAINAGE SYSTEM

Geocomposite Drain

Geocomposite drain shall consist of a manufactured core not less than 6.35 mm thick nor more than 50 mm thick with one or both sides covered with a layer of filter fabric that will provide a drainage void. The drain shall produce a flow rate, through the drainage void, of at least 25 liters per minute per meter of width at a hydraulic gradient of 1.0 and a minimum externally applied pressure of 168 kPa.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for the geocomposite drain certifying that the drain produces the required flow rate and complies with these special provisions. The Certificate of Compliance shall be accompanied by a flow capability graph for the geocomposite drain showing flow rates and the externally applied pressures and hydraulic gradients. The flow capability graph shall be stamped with the verification of an independent testing laboratory.

Filter fabric for the geocomposite drain shall conform to the provisions for fabric for underdrains in Section 88, "Engineering Fabrics," of the Standard Specifications.

The manufactured core shall be either a preformed grid of embossed plastic, a mat of random shapes of plastic fibers, a drainage net consisting of a uniform pattern of polymeric strands forming 2 sets of continuous flow channels, or a system of plastic pillars and interconnections forming a semirigid mat.

The core material and filter fabric shall be capable of maintaining the drainage void for the entire height of geocomposite drain. Filter fabric shall be integrally bonded to the side of the core material with the drainage void. Core material manufactured from impermeable plastic sheeting having nonconnecting corrugations shall be placed with the corrugations approximately perpendicular to the drainage collection system.

The geocomposite drain shall be installed with the drainage void and the filter fabric facing the embankment. The fabric facing the embankment side shall overlap a minimum of 75 mm at all joints and wrap around the exterior edges a minimum of 75 mm beyond the exterior edge. If additional fabric is needed to provide overlap at joints and wrap-around at edges, the added fabric shall overlap the fabric on the geocomposite drain at least 150 mm and be attached thereto.

Should the fabric on the geocomposite drain be torn or punctured, the damaged section shall be replaced completely or repaired by placing a piece of fabric that is large enough to cover the damaged area and provide a 150-mm overlap.

Plastic Pipe

Plastic pipe shall conform to the provisions for pipe for edge drains and edge drain outlets in Section 68-3, "Edge Drains," of the Standard Specifications.

Treated Permeable Base At Bottom Of Geocomposite Drains

Treated permeable base to be placed around the slotted plastic pipe at the bottom of geocomposite drains shall conform to the provisions in "Treated Permeable Base Under Approach Slabs." If asphalt treated permeable base is used, it shall be placed at a temperature of not less than 82°C nor more than 110°C.

The filter fabric to be placed over the treated permeable base at the bottom of geocomposite drains shall conform to the provisions for filter fabric for edge drains in Section 88, "Engineering Fabrics," of the Standard Specifications.

ENGINEERING FABRICS

Filter fabric to be placed between the structure approach embankment material and the treated permeable base shall conform to the provisions for filter fabric for edge drains in Section 88, "Engineering Fabrics," of the Standard Specifications and these special provisions.

The subgrade to receive the filter fabric, immediately prior to placing, shall conform to the compaction and elevation tolerance specified for the material involved.

Filter fabric shall be aligned, handled, and placed in a wrinkle-free manner in conformance with the manufacturer's recommendations.

Adjacent borders of the filter fabric shall be overlapped from 300 to 450 mm or stitched. The preceding roll shall overlap the following roll in the direction the material is being spread or shall be stitched. When the fabric is joined by stitching, it shall be stitched with yarn of a contrasting color. The size and composition of the yarn shall be as recommended by the fabric manufacturer. The stitches shall number 5 to 7 per 25 mm of seam.

Equipment or vehicles shall not be operated or driven directly on the filter fabric.

Woven tape fabric shall be treated to provide a minimum of 70 percent breaking strength retention after 500 hours exposure when tested in conformance with the requirements in ASTM Designation: D 4355. The Contractor shall notify the Engineer, in writing, of the source of woven tape fabric at least 45 days prior to use.

TREATED PERMEABLE BASE UNDER APPROACH SLAB

Treated permeable base under structure approach slabs shall consist of constructing either an asphalt treated permeable base or a cement treated permeable base in accordance with Section 29, "Treated Permeable Bases," of the Standard Specifications and these special provisions.

The type of treatment, asphalt or cement, to be used shall be at the option of the Contractor.

Not less than 30 days prior to the start of placing the treated permeable base, the Contractor shall notify the Engineer, in writing, which type of treated permeable base will be furnished. Once the Contractor has notified the Engineer of the selection, the type to be furnished shall not be changed without a prior written request to do so and approval thereof in writing by the Engineer.

Asphalt treated permeable base shall be placed at a temperature of not less than 93°C nor more than 121°C. Material stored in excess of 2 hours shall not be used in the work.

Asphalt treated permeable base material may be spread in one layer. The base material shall be compacted with a vibrating shoe type compactor or rolled with a roller weighing not less than 1.3 tonnes nor more than 4.5 tonnes. Rolling shall begin as soon as the mixture has cooled sufficiently to support the weight of the rolling equipment without undue displacement.

Cement treated permeable base material may be spread in one layer. The base material shall be compacted with either a vibrating shoe type compactor or with a steel-drum roller weighing not less than 1.3 tonnes nor more than 4.5 tonnes. Compaction shall follow within one-half hour after the spreading operation and shall consist of 2-complete coverages of the treated material.

APPROACH SLABS

Concrete for use in approach slabs shall contain not less than 400 kilograms of cement per cubic meter.

Miscellaneous steel parts and all steel components of abutment ties including plates, nuts, washers, and rods shall conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

Structure approach slabs shall be cured for not less than 5 days prior to opening to public traffic, unless, at the option of the Contractor, the structure approach slabs are constructed using concrete with a non-chloride Type C chemical admixture conforming to these special provisions.

Except as listed herein, structure approach slabs shall be cured for not less than 5 days prior to opening to public traffic, unless, at the option of the Contractor, the structure approach slabs are constructed using concrete with a non-chloride Type C chemical admixture.

At the following locations, structure approach slabs shall be constructed using concrete with a non-chloride Type C chemical admixture conforming to these special provisions:

Northern Approach of Prunedale Overcrossing (Br. No. 44-0276Y)

Portland cement for use in concrete using a non-chloride Type C chemical admixture shall be Type II Modified, Type II Prestress, or Type III. Type II Modified and Type III cement shall conform to the provisions in Section 90-2.01, "Portland Cement," of the Standard Specifications. Type II Prestress cement shall conform to the requirements of Type II Modified cement, except the mortar containing the portland cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not contract in air more than 0.053-percent.

The non-chloride Type C chemical admixture, approved by the Engineer, shall conform to the requirements in ASTM Designation: C 494 and Section 90-4, "Admixtures," of the Standard Specifications.

The concrete with non-chloride Type C chemical admixture shall be prequalified prior to placement in conformance with the provisions for prequalification of concrete specified by compressive strength in Section 90-9.01, "General," of the Standard Specifications and the following:

- A. Immediately after fabrication of the 5 test cylinders, the cylinders shall be stored in a temperature medium of $21 \pm 1.5^{\circ}\text{C}$ until the cylinders are tested.
- B. The 6-hour average strength of the 5 test cylinders shall not be less than 5.85 MPa. No more than 2 test cylinders shall have a strength of less than 5.5 MPa.

Building paper shall be commercial quality No. 30 asphalt felt.

Polyvinyl chloride (PVC) conduit used to encase the abutment tie rod shall be of commercial quality.

The top surface of approach slabs shall be finished in conformance with the provisions in Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications. Edges of slabs shall be edger finished.

Approach slabs shall be cured with pigmented curing compound (1) in conformance with the provisions for curing structures in Section 90-7.01B, "Curing Compound Method," of the Standard Specifications.

Structure approach slabs constructed using concrete with a non-chloride Type C chemical admixture shall be cured for not less than 6 hours prior to opening to public traffic. The curing period shall be considered to begin at the start of discharge of the last truck load of concrete to be used in the slab.

If the ambient temperature is below 18°C during the curing period for approach slabs using concrete with a non-chloride Type C chemical admixture, an insulating layer or blanket shall cover the surface. The insulation layer or blanket shall have an R-value rating given in the table below. At the Contractor's option, a heating tent may be used in lieu of or in combination with the insulating layer or blanket.

Temperature range during curing period	R-value, minimum
13°C to 18°C	1
7°C to 13°C	2
4°C to 7°C	3

JOINTS

Hardboard and expanded polystyrene shall conform to the provisions in Section 51-1.12D, "Sheet Packing, Preformed Pads and Board Fillers," of the Standard Specifications.

Type AL joint seals shall conform to the provisions in Section 51-1.12F, "Sealed Joints" of the Standard Specifications. The sealant may be mixed by hand-held power-driven agitators and placed by hand methods.

The pourable seal between the steel angle and concrete barrier shall conform to the requirements for Type A and AL seals in Section 51-1.12F(3), "Materials and Installation," of the Standard Specifications. The sealant may be mixed by hand-held power-driven agitators and placed by hand methods. Immediately prior to placing the seal, the joint shall be thoroughly cleaned, including abrasive blast cleaning of the concrete surfaces, so that all foreign material and concrete spillage are removed from all joint surfaces. Joint surfaces shall be dry at the time the seal is placed.

MEASUREMENT AND PAYMENT

Structural concrete, approach slab (Type N) and structural concrete, approach slab (Type EQ) will be measured and paid for in conformance with the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for the structure approach drainage system including geocomposite drain, plastic pipe, treated permeable base, filter fabric, woven tape fabric, miscellaneous metal, pourable seals, waterstops, and sliding joints shall be considered as included in the contract price paid per cubic meter for structural concrete, approach slab of the type shown in the Engineer's Estimate and no additional compensation will be allowed therefor.

10-1.49 SEALING JOINTS

Joints in concrete bridge decks and joints between concrete structures and concrete approach slabs shall be sealed in conformance with the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

Where polyurethane seals are shown on the plans, a silicone sealant conforming to the provisions in Section 51-1.12F, "Sealed Joints," of the Standard Specifications may be used.

When ordered by the Engineer, a joint seal larger than called for by the Movement Rating shown on the plans shall be furnished and installed. Payment to the Contractor for furnishing the larger seal and for saw cutting the increment of additional depth of groove required will be determined as provided in Section 4-1.03, "Changes," of the Standard Specifications.

10-1.50 ARCHITECTURAL SURFACE (TEXTURED CONCRETE)

Architectural texture for concrete surfaces shall conform to the details shown on the plans and the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Architectural textures listed below are required at concrete surfaces shown on the plans:

Field Stone Texture

Field stone texture shall be an architectural texture with a random shadow stone pattern and maximum relief of 20-mm as shown on the plans.

REFEREE SAMPLE

The architectural texture shall match the texture and pattern of the referee sample available for inspection by bidders at the Office of Transportation Architecture, Bridge Architecture and Aesthetics Section, Third Floor, 1801 30th Street, Sacramento, California.

TEST PANEL

A test panel at least 1.25 m x 1.25 m in size shall be successfully completed at a location approved by the Engineer before beginning work on architectural textures. The test panel shall be constructed and finished with the materials, tools, equipment and methods to be used in constructing the architectural texture. If ordered by the Engineer, additional test panels shall be constructed and finished until the specified finish, texture and color are obtained, as determined by the Engineer.

The test panel approved by the Engineer shall be used as the standard of comparison in determining acceptability of architectural texture for concrete surfaces.

FORM LINERS

Form liners shall be used for textured concrete surfaces and shall be installed in conformance with the manufacturer's recommendations, unless other methods of forming textured concrete surfaces are approved by the Engineer. Form liners shall be manufactured from an elastomeric material or a semi-elastomeric polyurethane material by a manufacturer of commercially available concrete form liners. No substitution of other types of formliner material will be allowed. Form liners shall leave crisp, sharp definition of the architectural surface. Recurring textural configurations exhibited by repeating, recognizable shadow patterns shall be prevented by proper casting of form liner patterns. Textured concrete surfaces with such recurring textural configurations shall be reworked to remove such patterns as approved by the Engineer or the concrete shall be replaced.

Form liners shall have the following properties:

Description	ASTM Designation:	Range
Elastomeric material		
Shore A hardness	D 2240	20 to 65
Tensile strength (MPa)	D 412	0.9 to 6.2
Semi-elastomeric polyurethane		
Shore D hardness	D 2240	55 to 65
Tensile strength (MPa)	D 2370	18 minimum

Cuts and tears in form liners shall be sealed and repaired in conformance with the manufacturer's recommendations. Form liners that are delaminated from the form shall not be used. Form liners with deformations to the manufactured surface caused by improper storage practices or any other reason shall not be used.

Form liners shall extend the full length of texturing with transverse joints at 2.5 m minimum spacing. Small pieces of form liners shall not be used. Grooves shall be aligned straight and true. Grooves shall match at joints between form liners. Joints in the direction of grooves in grooved patterns shall be located only in the depressed portion of the textured concrete. Adjoining liners shall be butted together without distortion, open cracks or offsets at the joints. Joints between liners shall be cleaned before each use to remove any mortar in the joint.

Adhesives shall be compatible with the form liner material and with concrete. Adhesives shall be approved by the liner manufacturer. Adhesives shall not cause swelling of the liner material.

RELEASING FORM LINERS

Products and application procedures for form release agents shall be approved by the form liner manufacturer. Release agents shall not cause swelling of the liner material or delamination from the forms. Release agents shall not stain the concrete or react with the liner material. For reliefs simulating fractured concrete or wood grain surfaces the application method shall include the scrubbing method using a natural bristle scrub brush in the direction of grooves or grain. The release agent shall coat the liner with a thin film. Following application of form release agent, the liner surfaces shall be cleaned of excess amounts of agent using compressed air. Buildup of form release agent caused by the reuse of a liner shall be removed at least every 5 uses.

Form liners shall release without leaving particles or pieces of liner material on the concrete and without pulling or breaking concrete from the textured surface. The concrete surfaces exposed by removing forms shall be protected from damage.

CURING

Concrete surfaces with architectural texture shall be cured only by the forms-in-place or water methods. Seals and curing compounds shall not be used.

MEASUREMENT AND PAYMENT

Architectural treatment will be measured and paid for by the square meter.

The contract price paid per square meter for architectural treatment shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in architectural texture, complete in place, including test panels, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

PAYMENT

Full compensation for architectural treatment on face of concrete barrier (Type 27 Modified) shall be considered as included in the contract price paid per meter for concrete barrier (Type 27 Modified) and no separate payment will be made therefor.

10-1.51 MINOR CONCRETE (INVERT PAVING)

This work consists of paving the invert of existing structural steel plated pipe (SSPP) culverts with reinforced concrete in accordance with the details shown on the plans and the provisions of the Standard Specifications and these special provisions.

MATERIALS.—Concrete shall conform to Section 90-10, "Minor Concrete," of the Standard Specifications and shall contain not less than 400 kg of portland cement per cubic meter. The maximum size of concrete aggregate shall not exceed 13 mm.

Welded wire fabric reinforcement shall conform to Section 52, "Reinforcement," of the Standard Specifications.

PREPARATION.—All loose rust, scale, sediment, vegetation, deteriorated lining, and other foreign materials shall be removed from the culvert invert prior to placing reinforcement and concrete. Removed debris shall be disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

PLACEMENT.—At the Contractor's option, invert paving may be constructed in accordance with the requirements in Section 53, "Shotcrete," of the Standard Specifications.

Prior to placing invert paving at any location, all voids beneath the culvert shall be filled with cement mortar as directed by the Engineer. Filling voids will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Immediately prior to placing concrete, the invert shall be damp, but all accumulations of water shall be removed.

The fresh concrete shall be immediately tamped and troweled in order to provide a smooth, dense surface finish.

The invert paving shall be cured by sealing off the circulation of air from both ends of the culvert after trapping enough water in the culvert to maintain a moist atmosphere for 48 hours. Curing shall begin between 2 and 4 hours after finish troweling of the invert. Water will not be permitted to flow over new invert paving during the curing period.

MEASUREMENT.—Minor concrete (invert paving) will be measured and paid for by the cubic meter.

PAYMENT.—The contract price paid per cubic meter for minor concrete (invert paving) shall include full compensation for furnishing all labor, materials (including welded wire fabric reinforcement), tools, equipment, and incidentals and for doing all the work involved in invert paving, complete in place, including cleaning culvert invert and disposing of debris, and for controlling water, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.52 REINFORCEMENT

Reinforcement shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and these special provisions.

The third paragraph of Section 52-1.04, "Inspection," of the Standard Specifications is amended to read:

- A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall also be furnished for each shipment of epoxy-coated bar reinforcement or wire reinforcement certifying that the coated reinforcement conforms to the requirements in ASTM Designation: A 775/A 775M or A 884/A 884M, respectively, and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement," of the Standard Specifications. The Certificate of Compliance shall include all of the certifications specified in ASTM Designation: A 775/A 775M or A 884/A 884M respectively, and a statement that the coating material has been prequalified by acceptance testing performed by the Valley Forge Laboratories, Inc., Devon, Pennsylvania.

The third paragraph of Section 52-1.08C, "Mechanical Butt Splices," of the Standard Specifications is amended to read:

- The total slip of the reinforcing bars within the splice sleeve after loading in tension to 200 MPa and relaxing to 20 MPa shall not exceed the values listed in the following table. The slip shall be measured between gage points that are clear of the splice sleeve.

Reinforcing Bar Number	Total Slip (µm)
13	250
16	250
19	250
22	350
25	350
29	350
32	450
36	450
43	600
57	750

The first paragraph of Section 52-1.08C(5), "Sleeve-Lockshear Bolt Mechanical Butt Splices," of the Standard Specifications is amended to read:

- The sleeve-lockshear bolt type of mechanical butt splices shall consist of a seamless steel sleeve, center hole with centering pin, and bolts that are tightened until the bolt heads shear off with the bolt ends left embedded in the reinforcing bars. The seamless steel sleeve shall be either formed into a V configuration or shall have 2 serrated steel strips welded to the inside of the sleeve.

Section 52-1.08F, "Nondestructive Splice Tests," of the Standard Specifications is amended by deleting the seventh paragraph.

Individual hoops, made continuous with butt welded splices, which are substituted for spiral reinforcement, shall conform to the requirements for "Ultimate Butt Splices" of these special provisions.

10-1.53 SIGN STRUCTURES

Sign structures and foundations for overhead signs shall conform to the provisions in Section 56-1, "Overhead Sign Structures," of the Standard Specifications and these special provisions.

Before commencing fabrication of sign structures, the Contractor shall submit 2 sets of working drawings to the Engineer in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings." The working drawings shall include sign panel dimensions, span lengths, post heights, anchorage layouts, proposed splice locations, a snugging and tensioning pattern for anchor bolts and high strength bolted connections, and details for permanent steel anchor bolt templates. The working drawings shall be supplemented with a written quality control program that includes methods, equipment, and personnel necessary to satisfy the requirements specified herein and in the special provisions.

Working drawings shall be 559 mm x 864 mm or 279 mm x 432 mm in size and each drawing and calculation sheet shall include the State assigned designations for the contract number, sign structure type and reference as shown on the contract plans, District-County-Route-Kilometer Post, and contract number.

The Engineer shall have 20 working days to review the sign structure working drawings after a complete submittal has been received. No fabrication or installation of sign structures shall be performed until the working drawings are approved in writing by the Engineer.

Should the Engineer fail to complete the review within the time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the sign structure working drawings, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays."

The third paragraph of Section 56-1.01, "Description," of the Standard Specifications shall not apply.

A permanent steel template shall be used to maintain the proper anchor bolt spacing.

One top nut, one leveling nut, and 2 washers shall be provided for the upper threaded portion of each anchor bolt.

Section 56-1.03, "Fabrication," of the Standard Specifications is amended by adding the following 2 paragraphs after the third paragraph:

- Surfaces of base plates which are to come in contact with concrete, grout, or washers and leveling nuts shall be flat to within 3 mm tolerance in 305 mm, and to within 5 mm tolerance overall. Faying surfaces of plates in high-strength bolted connections including flange surfaces of field splices, chord joints, and frame junctures, and contact surfaces of plates used for breakaway slip base assemblies shall be flat to within 2 mm tolerance in 305 mm, and within 3 mm tolerance overall.
- Thermally cut holes made in tubular members of sign supports, other than holes in base and flange plates, shall initially be made a minimum of 2 mm undersized, and then be mechanically enlarged by reaming or grinding to the final required size and shape. All edges shall have a surface roughness of not greater than 6.35 μm . Round holes may be drilled to the exact final diameter. No holes shall be made in members unless the holes are shown on the plans or are approved in writing by the Engineer.

The sixth through the thirteenth paragraphs in Section 56-1.03, "Fabrication," of the Standard Specifications are amended to read:

- High-strength bolted connections, where shown on the plans, shall conform to the provisions in Section 55-3.14, "Bolted Connections," except that only fastener assemblies consisting of a high-strength bolt, nut, hardened washer, and direct tension indicator shall be used.
- High-strength fastener assemblies, and any other bolts, nuts, and washers attached to sign structures shall be zinc-coated by the mechanical deposition process.
- An alternating snugging and tensioning pattern for anchor bolts and high-strength bolted splices shall be used. Once tensioned, high-strength fastener components and direct tension indicators shall not be reused.
- For bolt diameters less than 10 mm, the diameter of the bolt hole shall be not more than 0.80-mm larger than the nominal bolt diameter. For bolt diameters greater than or equal to 10 mm, the diameter of the bolt hole shall be not more than 1.6 mm larger than the nominal bolt diameter.
- Sign structures shall be fabricated into the largest practical sections prior to galvanizing.
- Ribbed sheet metal panels for box beam closed truss sign structures shall be fastened to the truss members by cap screws or bolts as shown on the plans, or by 4.76 mm stainless steel blind rivets conforming to Industrial Fasteners Institute, Standard IFI-114, Grade 51. The outside diameter of the large flange rivet head shall be not less than 15.88 mm in diameter. Web splices in ribbed sheet metal panels may be made with similar type blind rivets of a size suitable for the thickness of material being connected.
- Spalling or chipping of concrete structures shall be repaired by the Contractor at the Contractor's expense.
- Overhead sign supports shall have an aluminum identification plate permanently attached near the base, adjacent to the traffic side on one of the vertical posts, using either stainless steel rivets or stainless steel screws. As a minimum, the information on the plate shall include the name of the manufacturer, the date of manufacture and the contract number.

Steel members used for overhead sign structures shall receive nondestructive testing (NDT) in conformance with AWS D1.1 and the following:

A.

Weld Location	Weld Type	Minimum Required NDT
Welds for butt joint welds in tubular sections, nontubular sections, and posts	CJP groove weld with backing ring	100% UT or RT
Longitudinal seam welds*	PJP groove weld	25% MT
	CJP groove weld	100% UT or RT
Welds for base plate, flange plate, or end cap to post or mast arm	CJP groove weld	25% UT or RT
	Fillet weld	25% MT
* Longitudinal seam welds shall have 60% minimum penetration, except that within 150 mm of any circumferential weld, longitudinal seam welds shall be CJP groove welds.		

B. A written procedure approved by the engineer shall be used when performing UT on material less than 8 mm thick. Contoured shoes shall be used when performing UT on round tubular sections under 1270 mm in diameter.

- C. When less than 100 percent of a weld is specified for NDT, and if defects are found during this inspection, additional NDT shall be performed. This additional NDT shall be performed on 25 percent of the total weld for all similar welds, as determined by the Engineer, produced for sign structures in the project. If any portion of the additional weld inspected is found defective, 100 percent of all similar welds produced for sign structures in the project, as determined by the Engineer, shall be tested.

Circumferential welds and base plate to post welds may be repaired only one time without written permission from the Engineer.

Full compensation for furnishing anchor bolt templates and for testing of welds shall be considered as included in the contract price paid per kilogram for furnish sign structure and no additional compensation will be allowed therefor.

10-1.54 ROADSIDE SIGNS

Roadside signs shall be installed at the locations shown on the plans or where designated by the Engineer and in conformance with the provisions in Section 56-2, "Roadside Signs," of the Standard Specifications and these special provisions.

Wood posts shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications with creosote, creosote coal tar solution, creosote petroleum solution (50-50), pentachlorophenol in hydrocarbon solvent, copper naphthenate, ammoniacal copper arsenate, or ammoniacal copper zinc arsenate. In addition to the preservatives listed above, Southern yellow pine may also be pressure treated with chromated copper arsenate. When other than one of the creosote processes is used, blocks shall have a minimum retention of 6.4 kg/m^3 , and need not be incised.

Type N marker panels mounted on a post with a roadside sign shall be considered to be sign panels and will not be paid for as markers.

10-1.55 ALTERNATIVE PIPE

Alternative pipe culverts shall conform to the provisions in Section 62, "Alternative Culverts," of the Standard Specifications and these special provisions.

Reinforced concrete pipe shall conform to the provisions in "Reinforced Concrete Pipe," elsewhere in these special provisions.

Corrugated steel pipe culverts shall conform to the provisions in "Corrugated Metal Pipe," elsewhere in these special provisions.

SPIRAL RIB PIPE

Spiral rib pipe shall conform to the provisions in "Corrugated Metal Pipe" of these special provisions, except for profile and fabrication requirements.

Spiral rib pipe shall, at the option of the Contractor, consist of either (1) three rectangular ribs spaced midway between seams with ribs 19 mm wide by 19 mm high at a maximum rib pitch of 191 mm, (2) two rectangular ribs and one half-circle rib equally spaced between seams with ribs 19 mm wide by 25 mm high at a maximum rib pitch of 292 mm. The half-circle rib diameter shall be spaced midway between the rectangular ribs or (3) two rectangular ribs equally spaced between seams with ribs 19 mm wide by 25 mm high at a maximum rib pitch of 213 mm. Rib pitch measured at right angles to the direction of the ribs may vary ± 13 mm.

Corrugated steel spiral rib pipe shall be fabricated by a continuous helical lock seam fabricated in conformance with the provisions in Section 66-3.03C(1), "Fabrication by Continuous Lock Seam," of the Standard Specifications.

Coupling bands for spiral rib pipe shall conform to the provisions in Section 66-1.07, "Coupling Bands," of the Standard Specifications. A coupling band shown on the plans or approved by the Engineer in conformance with the provisions in Section 61-1.02, "Performance Requirements for Culvert and Drainage Pipe Joints," of the Standard Specifications, for use on a pipe corrugation of 68 mm x 13 mm for corrugated metal pipe may be used on spiral rib pipe having 68 mm x 13 mm rolerolled annular ends. The width of band (W) for hat bands for pipe sizes larger than 1200 mm in diameter shall be 95 mm.

10-1.56 REINFORCED CONCRETE PIPE

Reinforced concrete pipe shall conform to the provisions in Section 65, "Reinforced Concrete Pipe," of the Standard Specifications and these special provisions.

Where embankment will not be placed over the top of the pipe, a relative compaction of not less than 85 percent shall be required below the pipe spring line for pipe installed using Method 1 backfill in trench, as shown on Standard Plan A62D. Where the pipe is to be placed under the traveled way, a relative compaction of not less than 90 percent shall be required unless the minimum distance between the top of the pipe and the pavement surface is the greater of 1.2 m or one half of the outside diameter of the pipe.

Except as otherwise designated by classification on the plans or in the specifications, joints for culvert and drainage pipes shall conform to the plans or specifications for standard joints.

When reinforced concrete pipe is installed in conformance with the details shown on Revised Standard Plan A62DA, the fifth paragraph of Section 19-3.04, "Water Control and Foundation Treatment," of the Standard Specifications shall not apply.

When solid rock or other unyielding material is encountered at the planned elevation of the bottom of the bedding, the material below the bottom of the bedding shall be removed to a depth of 1/50 of the height of the embankment over the top of the culvert, but not less than 150 mm nor more than 300 mm. The resulting trench below the bottom of the bedding shall be backfilled with structure backfill material in conformance with the provisions in Section 19-3.06, "Structure Backfill," of the Standard Specifications.

The excavation and backfill below the planned elevation of the bottom of the bedding will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

The Outer Bedding shown on Revised Standard Plan A62DA shall not be compacted prior to placement of the pipe.

10-1.57 CORRUGATED METAL PIPE

Corrugated steel pipe culverts shall conform to the provisions in Section 66, "Corrugated Metal Pipe," of the Standard Specifications and these special provisions.

Asphaltic mastic coating or polymeric sheet coating substituted for bituminous coating shall be placed on the outside and inside surfaces of the pipe.

Corrugated steel pipe shall be fabricated from zinc-coated steel sheet.

10-1.58 OVERSIDE DRAIN

200-mm entrance tapers, metal pipe downdrain anchor assemblies, 200-mm alternative pipe downdrains and asphalt concrete overside shall conform to the provisions in Section 69, "Overside Drains," of the Standard Specifications and these special provisions.

Steel entrance tapers and pipe downdrains shall be fabricated from zinc-coated steel sheet.

Plastic pipe for overside drains shall be Type S corrugated high density polyethylene or ribbed polyvinyl chloride pipe conforming to the provisions in Section 64, "Plastic Pipe," of the Standard Specification.

Plastic pipe joints shall conform to the provisions in Section 61-1.02, "Performance Requirements for Culvert and Drainage Pipe Joints," of the Standard Specifications for downdrain joints, except that the alternatives selected for plastic pipe joint restrainer assemblies shown on the plans shall serve in lieu of the tensile strength requirements. The joint overlap requirements for integral joints shall conform to the requirements for positive joints.

Plastic pipe joint restrainer assembly, Alternative A, when used shall be installed immediately below the pipe bell.

Polyvinyl chloride pipe shall not be used unless the overside drain is covered for the entire length of the overside drain.

Plastic pipe overside drains shall be installed with the bell end of the pipe facing uphill.

10-1.59 MISCELLANEOUS FACILITIES

Alternative flared end sections, manhole and 900-mm precast concrete pipe inlet shall conform to the provisions in Section 70, "Miscellaneous Facilities," of the Standard Specifications and these special provisions.

Manhole will be measured and paid for as units determined from actual count of manholes in place.

The contract unit price paid for manhole shall include full compensation for furnishing all labor, materials (including flat slab lid and metal frame and cover), tools, equipment, and incidentals, and for doing all the work involved in constructing manhole, including structure excavation and structure backfill, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.60 SLOPE PAVING

Slopes under the ends of bridges, where shown on the plans, shall be paved in conformance with the provisions in Section 72-6, "Slope Paving," of the Standard Specifications and these special provisions.

The slope paving shall be colored in conformance with the provisions in Section 72-6.03, "Materials," of the Standard Specifications.

Areas of slope paving shown on the plans to have an exposed aggregate finish shall be constructed and finished in conformance with the following requirements.

1. Coarse aggregate shall conform to the provisions for 25-mm x 4.75-mm primary size coarse aggregate in Section 90-3.02, "Coarse Aggregate Grading," of the Standard Specifications.
2. Shotcrete shall not be used for the construction of exposed aggregate concrete.

3. Coarse aggregates shall be exposed to a depth of approximately 5 mm to 10 mm. Exposed aggregate surfaces shall be uniform in appearance.
4. At the option of the Contractor, a concrete set retarder may be applied to the surface of the concrete after placing, consolidating, and finishing of the concrete has been completed. The concrete set retarder shall be commercial quality, manufactured specifically for use on the top surface of concrete and shall be applied in accordance with the manufacturer's recommendations. The retarder shall effectively retard the setting time of the cement and fine aggregate matrix deep enough and long enough to permit exposing the aggregates.
5. Care shall be taken in placing and consolidating the concrete such that the coarse aggregate remains uniformly distributed throughout the concrete.
6. When the mass of the concrete has set sufficiently to permit removing the matrix of cement and fine aggregate, the coarse aggregate shall be exposed with a water spray, coarse brooming, abrasive blasting, or a combination of these procedures. Removal methods shall not dislodge or loosen the coarse aggregate from embedment in the cement mortar.
7. Immediately after the cement mortar has hardened sufficiently to resist further removal, all cement film and other loose material shall be cleaned from the exposed aggregate and all other surfaces with stiff brooms and water.
8. Except when operations for exposing the aggregate are underway, concrete shall be cured by the water method or with Type (6) curing compound in conformance with the provisions in Section 90-7.01B, "Curing Compound Method," of the Standard Specifications. Areas of concrete where curing compounds are removed during the cure period shall be kept continuously wet until the end of the cure period or until the curing compound is replaced.

10-1.61 MISCELLANEOUS CONCRETE CONSTRUCTION

Concrete driveways, curbs and sidewalks shall conform to the provisions in Section 73, "Concrete Curbs and Sidewalks," of the Standard Specifications.

10-1.62 MINOR CONCRETE (GUTTER)

The gutter behind the retaining wall shall conform to the provisions in Section 73, "Concrete Curbs and Sidewalks," of the Standard Specifications and these special provisions.

Minor concrete (gutter) will be measured and paid for by the meter.

The contract price paid per meter for minor concrete (gutter) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the gutter, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.63 MISCELLANEOUS IRON AND STEEL

Miscellaneous iron and steel shall conform to the provisions in Section 75, "Miscellaneous Metal," of the Standard Specifications.

10-1.64 MISCELLANEOUS METAL (BRIDGE)

Miscellaneous metal (bridge) shall conform to the provisions for miscellaneous bridge metal in Section 75, "Miscellaneous Metal," of the Standard Specifications and these special provisions.

Self-tapping screws used for sleeve connections shall be hex-head stainless steel, installed in holes drilled to fit the self-tapping screws, conforming to the requirements of ASTM Designation: A 276, Type 304.

At the Contractor's option, fiberglass pipes and fittings with the same diameter and minimum bend radius as those shown on the plans, may be substituted for welded steel pipe in deck drain systems.

Fiberglass pipe and fittings shall conform to the requirements in ASTM Designation: D 2996, and shall have a minimum short-term rupture strength of 207 MPa. The adhesive type recommended by the manufacturer shall be used for joining pipe and fittings. Fiberglass pipe not enclosed in a box girder cell or encased in concrete shall be manufactured from ultraviolet-resistant resin pigmented with concrete-gray color, or be coated with a concrete-gray resin-rich exterior coating. Paint shall not be used. Fiberglass pipe treated with ultraviolet protection shall withstand a minimum of 2500 hours of accelerated weathering when tested in conformance with the requirements in ASTM Designation: G 154. Lamps shall be UV-B (313 nm wavelength). The resting cycle shall be 4 hours of ultraviolet (UV) exposure at 60°C, and then 4 hour of condensate exposure at 50°C. After testing, the surface of the pipe shall exhibit no fiber exposure, crazing, or checking, and only a slight chalking or color change.

Support spacing for fiberglass pipe shall be the same as shown on the plans for welded steel pipe. Pipe supports shall have a width of not less than 38 mm.

A Certificate of Compliance for fiberglass pipe and fittings shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall include all laboratory test results conforming to the provisions specified herein.

For drainage piping NPS 8 or smaller, which is: (1) enclosed in a box girder cell and exposed for a length not greater than 6 m within the cell, or (2) encased in concrete, the Contractor shall have the option of substituting polyvinyl chloride (PVC) plastic pipe and fittings, with the same diameter and minimum bend radius as shown on the plans, for welded steel pipe.

The PVC plastic pipe and fittings shall be Schedule 40 conforming to the requirements of ASTM Designations: D 1785. The maximum support spacing for PVC plastic pipe shall be 2 m.

Couplings used to connect fiberglass pipe to steel shall be threaded or flanged. The sleeve connections shown on the plans shall not be used for fiberglass pipe.

If fiberglass pipe is substituted for welded steel pipe, the quantity of drainage piping will be computed on the basis of the dimensions and details shown on the plans, and no change in the quantities to be paid for will be made because of the use of fiberglass pipe.

10-1.65 TYPE BW FENCE

Type BW fence shall conform to the provisions in Section 80, "Fences," of the Standard Specifications and these special provisions.

The fence material shall be fastened to wood posts.

10-1.66 MONUMENTS

Survey monuments shall be constructed in conformance with the provisions in Section 81, "Monuments," of the Standard Specifications and these special provisions.

Concrete shall be Class 3 or minor concrete at the option of the Contractor.

The cast steel and gray cast iron frames and covers, including hardware, shall conform to the provisions in Section 55-2, "Materials," of the Standard Specifications.

10-1.67 MARKERS AND DELINEATORS

Markers and delineators shall conform to the provisions in Section 82, "Markers and Delineators," of the Standard Specifications and these special provisions.

Markers and delineators on flexible posts shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Flexible posts shall be made from a flexible white plastic which shall be resistant to impact, ultraviolet light, ozone, and hydrocarbons. Flexible posts shall resist stiffening with age and shall be free of burns, discoloration, contamination, and other objectionable marks or defects which affect appearance or serviceability.

Retroreflective sheeting for metal and flexible target plates shall be the retroreflective sheeting designated for channelizers, markers, and delineators conforming to the requirements in ASTM Designation: D 4956-95 and in conformance with the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

10-1.68 METAL BEAM GUARD RAILING

Metal beam guard railing shall be constructed in conformance with the provisions in Section 83-1, "Railings," of the Standard Specifications and these special provisions.

Attention is directed to "Order of Work" of these special provisions.

Line posts and blocks shall be wood.

Delete the ninth and eleventh paragraphs in Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications.

The grades and species of wood posts and blocks shall be No. 1 timbers (also known as No. 1 structural) Douglas fir or No. 1 timbers Southern yellow pine. Wood posts and blocks shall be graded in conformance with the provisions in Section 57-2, "Structural Timber," of the Standard Specifications, except allowances for shrinkage after mill cutting shall in no case exceed 5 percent of the American Lumber Standards minimum sizes, at the time of installation.

Wood posts and blocks shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications with creosote, creosote coal tar solution, creosote petroleum solution (50-50), pentachlorophenol in hydrocarbon solvent, copper naphthenate, ammoniacal copper arsenate, or ammoniacal copper zinc arsenate. In addition to the preservatives listed above, Southern yellow pine may also be pressure treated with chromated copper arsenate. When other than one of the creosote processes is used, blocks shall have a minimum retention of 6.4 Kg/m³, and need not be incised.

Nested metal beam guard railing will be measured and paid for as metal beam guard railing (wood post).

TERMINAL SYSTEM (TYPE SRT)

Terminal system (Type SRT) shall be furnished and installed as shown on the plans and in conformance with these special provisions.

Terminal system (Type SRT) shall be a SRT-350 Slotted Rail Terminal (8 post system) as manufactured by Trinity Industries, Inc., and shall include all the items detailed for terminal system (Type SRT) shown on the plans.

The 5 mm x 44 mm x 75 mm plate washer shown on the elevation view and in Section D-D at Wood Post No. 1 shall be omitted.

Arrangements have been made to insure that any successful bidder can obtain the SRT-350 Slotted Rail Terminal (8 post system) from the manufacturer, Trinity Industries, Inc., P.O. Box 99, 950 West 400S, Centerville, UT 84014, Telephone 1-800-772-7976. The price quoted by the manufacturer for the SRT-350 Slotted Rail Terminal (8 post system), FOB Centerville, Utah is \$845.00, not including sales tax.

The above price will be firm for orders placed on or before July 31, 2002, provided delivery is accepted within 90 days after the order is placed.

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall certify that terminal systems (Type SRT) conform to the contract plans and specifications, conform to the prequalified design and material requirements and were manufactured in conformance with the approved quality control program.

The terminal system (Type SRT) shall be installed in conformance with the manufacturer's installation instructions and these requirements. The steel foundation tubes with soil plates attached, shall be, at the Contractor's option, either driven, with or without pilot holes, or placed in drilled holes. Space around the steel foundation tubes shall be backfilled with selected earth, free of rock, placed in layers approximately 100 mm thick and each layer shall be moistened and thoroughly compacted. Wood terminal posts shall be inserted into the steel foundation tubes by hand. Before the wood terminal posts are inserted, the inside surfaces of the steel foundation tubes to receive the wood posts shall be coated with a grease which will not melt or run at a temperature of 65°C or less. The edges of the wood terminal posts may be slightly rounded to facilitate insertion of the post into the steel foundation tubes.

Surplus excavated material remaining after the terminal system (Type SRT) has been constructed shall be disposed of in a uniform manner along the adjacent roadway where designated by the Engineer.

10-1.69 CABLE RAILING

Cable railing shall conform to the provisions in Section 83-1, "Railings," of the Standard Specifications.

10-1.70 CONCRETE BARRIER

Concrete barriers shall conform to the provisions in Section 83-2, "Barriers," of the Standard Specifications and these special provisions.

Field stone texture shall be applied on face of concrete barrier Type 27 (MOD), and shall conform to the details shown on the plans and the provisions in Section 51, "Concrete Structures," of the Standard Specifications and "Architectural Surface (Textured Concrete)" of these special provisions.

Type 27A (Modified) concrete barriers will be measured and paid for as concrete barrier (Type 27 Modified).

Type 60 concrete barrier transition will be measured and paid for as concrete barrier (Type 60).

10-1.71 CRASH CUSHION (REACT)

Crash cushion (REACT) shall be furnished and installed as shown on the plans and in conformance with the provisions in the Standard Specifications and these special provisions.

Crash cushion (REACT) shall be a multiple recoverable type, manufactured by Roadway Safety Service, Inc. Crash cushion (REACT) and additional components shall conform to the descriptions as follows:

Contract Item Description	Manufacturer's Product Description
Crash Cushion (REACT 9SCBS)	REACT 350.9 Self Contained
Crash Cushion (REACT 9CBB)	REACT 350.9 Concrete Side Mount

The successful bidder can obtain the crash cushion from the following source:

- A. Manufacturer: Roadway Safety Service, Inc., One East Wacker Drive, Suite 3000, Chicago, Illinois 60601.
- B. Distributors:

1. Southern California: Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, California 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.
2. Northern California: Traffic Control Services, Inc., 8585 Thys Court, Sacramento, California 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734.

The price quoted by the manufacturer for Crash Cushion (REACT 9CBB), FOB Channelview, Texas is \$27,602, not including sales tax. The price quoted by the manufacturer for Crash Cushion (REACT 9SCBS), FOB Channelview, Texas is \$27,527, not including sales tax.

The above prices will be firm for orders placed on or before June 30, 2002, provided delivery is accepted within 90 days after the order is placed.

The prices quoted do not include the concrete backup block, concrete anchor slab or the W-Beam connection to barrier.

Crash cushion shall be installed in conformance with the manufacturer's recommendations.

Concrete anchorage devices used for attaching the crash cushion to the base slab shall be limited to those which have been proven satisfactory for such application by previous testing.

The concrete anchor slab and backup block shall conform to the provisions in Section 51, "Concrete Structures," and Section 52, "Reinforcement," of the Standard Specifications and these special provisions.

The concrete anchor slab and backup block shall be constructed of concrete containing not less than 350 kg of cement per cubic meter.

The W-Beam connections to barrier shall conform to the provisions in Section 83-1, "Railings," of the Standard Specifications.

High strength bolts and nuts for W-Beam connections to barrier shall conform to the requirements in ASTM Designation: A 325 or A 325M and A 563 or A 563M, respectively.

The Contractor shall furnish the Engineer one copy of the manufacturer's plan and parts list for each model installed.

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall certify that crash cushion conforms with the contract plans and specifications, conforms to the prequalified design and material requirements, and was manufactured in conformance with the approved quality control program.

Crash cushion will be measured by the unit as determined from actual count in place in the completed work.

The contract unit prices paid for crash cushion (REACT 9CBB) and crash cushion (REACT 9SCBS) shall include full compensation for furnishing all labor, materials (including anchor bolts, nuts, washers, and marker panels), tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing the crash cushions, complete in place, including structure excavation, structure backfill, bar reinforcing steel, concrete for backup block and anchor slab, transition plate, W-beam connector, and for furnishing high strength bolts and plate washers, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.72 THERMOPLASTIC PAVEMENT MARKING

Thermoplastic pavement markings shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Thermoplastic material for traffic stripes shall be applied at a minimum thickness of 2.0 mm.

At the option of the Contractor, permanent pavement marking tape conforming to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be placed instead of the thermoplastic pavement markings specified herein. Permanent tape, if used, shall be installed in conformance with the manufacturer's specifications. If permanent tape is placed instead of thermoplastic pavement markings, the tape will be measured and paid for by the square meter as thermoplastic pavement marking.

10-1.73 THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)

Sprayable thermoplastic traffic stripes (traffic lines) shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Sprayable thermoplastic material shall conform to the requirements of the Department of Transportation Specification PTH 392B, for Thermoplastic Traffic Striping Material, Sprayable, White and Yellow.

Sprayable thermoplastic material for traffic stripes shall be applied by spray methods in a single uniform layer at the minimum thickness of 1.0-mm.

Sprayable thermoplastic material shall be applied to the pavement at a temperature between 177°C and 205°C, unless a different temperature is recommended by the manufacturer.

At the option of the Contractor, permanent traffic striping and pavement marking tape conforming to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be placed instead of the sprayable thermoplastic traffic stripes specified herein. Permanent tape, if used, shall be installed in conformance with the manufacturer's specifications. If permanent tape is placed instead of sprayable thermoplastic traffic stripes, the tape will be measured and paid for by the meter as thermoplastic traffic stripe (sprayable).

Sprayable thermoplastic traffic stripes will be measured by the meter along the line of the traffic stripes, without deductions for gaps in broken traffic stripes. A double traffic stripe, consisting of two, 100 mm wide yellow stripes will be measured as one traffic stripe.

The contract price paid per meter for thermoplastic traffic stripe (sprayable) shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in applying sprayable thermoplastic traffic stripes (regardless of the number, widths, and patterns of individual stripes involved in each traffic stripe) including establishing alignment for stripes, and layout work, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.74 PAVEMENT MARKERS

Pavement markers shall be placed in conformance with the provisions in Section 85, "Pavement Markers," of the Standard Specifications and these special provisions.

Attention is directed to "Traffic Control System For Lane Closure" of these special provisions regarding the use of moving lane closures during placement of pavement markers with bituminous adhesive.

Retroreflective pavement markers shall comply with the specific intensity provisions for reflectance after abrading the lens surface in conformance with the "Steel Wool Abrasion Procedure" specified for pavement markers placed in pavement recesses in Section 85-1.05, "Retroreflective Pavement Markers," of the Standard Specifications.

SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS

10-2.01 GENERAL

The work performed in connection with highway planting and irrigation systems shall conform to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications and these special provisions.

The Contractor shall notify the Engineer not less than 72 hours prior to requiring initial access to the existing irrigation controllers. When the Engineer determines that access to the controllers is required at other times, arrangements will be made to provide this access.

When fluctuations of water pressure and water supply are encountered during normal working hours, plants shall be watered at other times, as often, and in sufficient amounts as conditions may require to keep the soil and plant roots moist during the life of the contract.

Full compensation for watering plants outside normal working hours shall be considered as included in the contract lump sum prices paid for highway planting and plant establishment work and no additional compensation will be allowed therefor.

PROGRESS INSPECTIONS

Progress inspections will be performed by the Engineer for completed highway planting and irrigation system work at designated stages during the life of the contract.

Progress inspections will not relieve the Contractor of responsibility for installation in conformance with the special provisions, plans and Standard Specifications. Work within an area shall not progress beyond each stage until the inspection has been completed, corrective work has been performed, and the work is approved, unless otherwise permitted by the Engineer.

The requirements for progress inspections will not preclude additional inspections of work by the Engineer at other times during the life of the contract.

The Contractor shall notify the Engineer, in writing, at least 4 working days prior to completion of the work for each stage of an area and shall allow a minimum of 3 working days for the inspection.

Progress inspections will be performed at the following stages of work:

- A. During pressure testing of the pipelines on the supply side of control valves.
- B. During testing of low voltage conductors.
- C. Before planting begins and after completion of the work specified for planting in Section 20-4.03, "Preparing Planting Areas," of the Standard Specifications.

- D. Before plant establishment work begins and after completion of the work specified for planting in Section 20-4.05, "Planting," of the Standard Specifications.
- E. At intervals of one month during the plant establishment period.

COST BREAK-DOWN

The Contractor shall furnish the Engineer a cost break-down for the contract lump sum items of highway planting and irrigation system.

Cost break-downs shall be completed and furnished in the format shown in the samples of the cost break-downs included in this section. Unit descriptions of work shown in the samples are the minimum to be submitted. Additional unit descriptions of work may be designated by the Contractor. If the Contractor elects to designate additional unit descriptions of work, the quantity, value and amount for those units shall be completed in the same manner as for the unit descriptions shown in the samples. The units and quantities given in the samples are to show the manner of preparing the cost break-downs to be furnished by the Contractor.

The Contractor shall determine the quantities required to complete the work shown on the plans. The quantities and their values shall be included in the cost break-downs submitted to the Engineer for approval. The Contractor shall be responsible for the accuracy of the quantities and values used in the cost break-downs submitted for approval.

No adjustment in compensation will be made in the contract lump sum prices paid for highway planting and irrigation system due to differences between the quantities shown in the cost break-downs furnished by the Contractor and the quantities required to complete the work as shown on the plans and as specified in these special provisions.

The sum of the amounts for the units of work listed in each cost break-down for highway planting and irrigation system work shall be equal to the contract lump sum price bid for the work. Overhead and profit shall be included in each individual unit listed in each cost break-down. Cost break-downs shall be submitted to the Engineer for approval within 15 working days after the contract has been approved. Cost break-downs shall be approved, in writing, by the Engineer before a partial payment for the items of highway planting and irrigation system will be made.

Approved cost break-downs will be used to determine partial payments during the progress of the work and as the basis of calculating the adjustment in compensation for the items of highway planting and irrigation system due to changes ordered by the Engineer. When an ordered change increases or decreases the quantities of an approved cost break-down, the adjustment in compensation will be determined in the same manner specified for increases and decreases in the quantity of a contract item of work in conformance with the provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.

HIGHWAY PLANTING COST BREAK-DOWN

Contract No. 05-0161U4

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT
ROADSIDE CLEARING	LS	1		
MULCH	M3	153		
COMMERCIAL FERTILIZER (TABLET)	EA	2554		
ROOT PROTECTOR	EA	680		
PLANT GROUP (A)	EA	566		
PLANT GROUP (M)	EA	1400		
PLANT GROUP (U)	EA	394		
PLANT GROUP (W)	EA	168		
AMENDMENT	M ³	8.4		
IRON SULFATE	Kg	126		

TOTAL _____

IRRIGATION SYSTEM COST BREAK-DOWN

Contract No. 05-0161U4

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT
CONTROL AND NEUTRAL CONDUCTORS	LS	1		
32mm ELECTRIC REMOTE CONTROL VALVE	EA	11		
40mm ELECTRIC REMOTE CONTROL VALVE	EA	8		
25 MM PLASTIC PIPE (PR200)(SUPPLY LINE)	M	2390		
32 MM PLASTIC PIPE (PR200)(SUPPLY LINE)	M	800		
40 MM PLASTIC PIPE (PR200)(SUPPLY LINE)	M	320		
50 MM PLASTIC PIPE (PR200)(SUPPLY LINE)	M	890		
SPRINKLER (TYPE A-1)	EA	78		
SPRINKLER (TYPE B-2)	EA	47		
SPRINKLER (TYPE C-2)	EA	201		
24 STATION IRRIGATION CONTROLLER	EA	1		
50 MM GATE VALVE	EA	4		
CHECK AND TEST	LS	LUMP SUM		

TOTAL _____

10-2.02 EXISTING HIGHWAY PLANTING

In addition to the provisions in Section 20 of the Standard Specifications, work performed in connection with existing highway planting shall be in conformance with the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Replacement planting shall conform to the requirements specified under "Preservation of Property" of these special provisions.

PRUNE EXISTING PLANTS

Existing plants, as determined by the Engineer, shall be pruned. Pruning of the existing plants, except as otherwise provided in these special provisions, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES

The work performed in connection with the various existing highway irrigation system facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

LOCATE EXISTING WATER SUPPLY LINE

Existing water supply line shown on the plans to be incorporated in the new work shall be located in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

Unless otherwise directed by the Engineer, existing water supply line shown on the plans to be incorporated in the new work shall be located prior to performing work on irrigation systems.

If debris is encountered in the ends of water supply line, the debris shall be removed prior to performing other work in the water supply line. Removal of debris within the first one meter in the water supply line shall be at the Contractor's expense. If debris is encountered in the water supply line more than one meter from the ends of the water supply line, the additional debris shall be removed as directed by the Engineer and the removal work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

CHECK AND TEST EXISTING IRRIGATION FACILITIES

Existing irrigation facilities that are to remain, and that are to be part of the new irrigation system, shall be checked for missing or damaged components, and for proper operation prior to performing irrigation system work.

A written list of existing irrigation system deficiencies shall be submitted to the Engineer within 5 working days after checking the existing facilities.

Deficiencies found during checking of the existing facilities shall be corrected as directed by the Engineer. Corrective work ordered by the Engineer will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Length of watering cycles for checking or testing existing irrigation facilities shall be as determined by the Engineer.

Repairs to the existing irrigation facilities ordered by the Engineer after checking and testing the facilities, and further repairs required thereafter as ordered by the Engineer, except as otherwise provided under "Existing Highway Irrigation Facilities" of these special provisions, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

10-2.04 HIGHWAY PLANTING

The work performed in connection with highway planting shall conform to the provisions in Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

HIGHWAY PLANTING MATERIALS

Mulch

Mulch shall be wood chips or tree bark or a combination of both. Wood chips produced from tree trimmings may contain leaves and small twigs.

Commercial Fertilizer

Commercial fertilizer (tablet) shall be slow release and shall be in tablet or packet form. Each tablet, as shown in the Plant List of the plans, shall have a mass of 21 g ± 1 g, and shall have the following guaranteed chemical analysis:

Ingredient	Percentage
Nitrogen	20
Phosphoric Acid	10
Water Soluble Potash	5

At the option of the Contractor, two 10.5-g tablets or two 10-g packets may be used in place of each 21-g tablet designated on the plans or specified in these special provisions. Regardless of the tablet or packet size used, each tablet or packet shall be the slow release type and shall have the same guaranteed chemical analysis as specified for the 21-g tablets. Each 10.5-g tablet shall have a mass of 10.5 g ± 0.5-g or each 10-g packet shall have a mass of 10 g ± 0.5-g.

ROADSIDE CLEARING

Prior to preparing planting areas, or commencing irrigation trenching operations for planting areas, trash and debris shall be removed from these areas and a distance of 3 m beyond the edges of those areas. At locations where proposed planting areas are 3.6 m or more from the edges of dikes, curbs, sidewalks, fences, walls, paved shoulders and existing planting to remain or to be maintained, the clearing limit shall be 2 m beyond the outer limits of the proposed planting area.

In addition to removing trash and debris, the project area shall be cleared as specified herein:

- A. Weeds shall be killed and removed within an area 2 m in diameter centered at each plant .
- B. Weeds shall be killed and removed within an area 0.6-m in diameter centered at each liner plant location.
- C. Disposal of weeds killed during the initial roadside clearing will be required. Weeds shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

After the initial roadside clearing is complete, additional roadside clearing work shall be performed as necessary to maintain the areas, as specified above, in a neat appearance until the start of the plant establishment period. This work shall include the following:

- A. Trash and debris shall be removed.
- B. Rodents shall be controlled.
- C. Weed growth shall be killed before the weeds reach the seed stage of growth or exceed 150 mm in length.
- D. Weeds in plant basins, including basin walls, shall be removed by hand pulling, after the plants have been planted.

Weed Control

Weed control shall also conform to the following:

- A. Stolon type weeds shall be killed with glyphosate.
- B. Removed weeds shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Roadside clearing work shall not include work required to be performed as clearing and grubbing as specified in Section 16, "Clearing and Grubbing," of the Standard Specifications.

PESTICIDES

Pesticides used to control weeds shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specifications. Except as otherwise provided in these special provisions, pesticide use shall be limited to the following materials:

- Glyphosate
- Oxadiazon - 50 percent WP (Preemergent)
- Oryzalin (Preemergent)
- Pendimethalin (Preemergent)
- Trifluralin (Preemergent)

Pesticides approved for use near water shall be used to kill stolon type weeds.

Prior to the application of preemergents, ground cover plants shall have been planted a minimum of 3 days and shall have been thoroughly watered.

A minimum of 100 days shall elapse between applications of preemergents.

Except for ground cover plants, preemergents shall not be applied within 450 mm of plants.

If the Contractor elects to request the use of other pesticides on this project, the request shall be submitted, in writing, to the Engineer not less than 15 days prior to the intended use of the other pesticides. Except for the pesticides listed in these special provisions, no pesticides shall be used or applied without prior written approval of the Engineer.

Pesticides shall not be applied within the limits of the plant basins. Pesticides shall not be applied in a manner that allows the pesticides to come in contact with the foliage and woody parts of the plants.

PREPARING PLANTING AREAS

Plants adjacent to drainage ditches shall be located so that after construction of the basins, no portion of the basin walls shall be less than the minimum distance shown on the plans for each plant involved.

The location of plants to be planted in areas with an irrigation system shall be adjusted as necessary to match the area wetted by the sprinklers.

PLANTING

Commercial fertilizer and iron sulfate shall be applied or placed at the time of planting and at the rates shown on the plans.

Mulch will not be required in the plant basins as shown on the Plant List for the plants to be planted in areas with erosion control blanket.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions regarding functional tests of the irrigation systems. Planting shall not be performed in an area until the functional test has been completed for the irrigation system serving that area.

LINER PLANTS (PLANT GROUP M)

Liner plants shall be furnished in containers with a minimum size of 200 mm deep and 35 mm wide. Liner plant containers made of biodegradable material shall not be used. All liner plants shall be removed from their containers at the time of planting.

At the option of the Contractor, seedling plants may be furnished in lieu of liner plants. Seedling plants shall be bare root.

Liner plants shall not be planted until the soil is moist to a minimum depth of 200 mm.

Planting holes for liner plants shall be large enough to accommodate the total length and width of the root ball, and fertilizer tablet.

10-2.05 WILLOW CUTTINGS (PLANT GROUP W)

Willow cutting work shall consist of obtaining, transporting and planting willow cuttings in conformance with the provisions in Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

Willow cuttings shall not be planted until the soil is moist to a minimum depth of 200 mm.

The Contractor shall notify the Engineer, in writing, at least 10 working days prior to gathering willow cuttings. The cuttings shall be taken only from the areas designated by the Engineer.

Willow cuttings shall be taken at random from healthy, vigorous plants. Not more than 50 percent of the plants in a designated area shall be cut. Not more than 25 percent of each individual plant shall be cut. Cuts shall be made with sharp, clean tools.

Willow cuttings shall be reasonably straight, 400 mm to 500 mm in length, and 20 mm to 40 mm in diameter at the base of the cutting. The top of each willow cutting shall be cut square above a leaf bud, and the base of each willow cutting shall be cut below a leaf bud at an angle of approximately 45 degrees. Willow cuttings shall have leaves and branches trimmed off flush with the stem. Pruned branches and trimmings shall be spread in the designated willow cutting areas so that no areas are left unsightly.

Willow cuttings shall be planted within 48 hours after cutting and shall be kept wet until planted. Willow cuttings not planted within 48 hours after cutting, or allowed to dry out, shall not be used. Willow cuttings not used shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

A root stimulant shall be applied to the willow cuttings immediately prior to planting. The stimulant shall be applied in conformance with the printed instructions of the root stimulant manufacturer. A copy of the instructions shall be furnished to the Engineer prior to applying the stimulant.

Planting holes shall be made perpendicular to the ground line and shall be formed with a steel bar or excavated by use of an auger, post hole digger or similar tools. Plant holes shall be large enough to receive the willow cuttings in order that the willow cuttings may be planted to the proper depths without damage to the bark. Where rock or other hard material prohibits holes from being excavated as specified, new holes shall be excavated and the abandoned holes backfilled.

If the soil in and around the plant hole is not wet prior to planting, the soil shall be watered and maintained in a wet state until the willow cuttings are planted.

The base of willow cuttings shall be planted from 300 mm to 400 mm deep (approximately one-half the willow cutting's length) and shall have from 3 to 5 bud scars exposed above the plant hole. Cuttings with more than 5 bud scars exposed shall have excess scars removed by pruning. After planting, the plant holes shall be backfilled with excavated material. The excavated material shall be distributed evenly within the hole without clods, lumps or air pockets and compacted without damage to the willow cutting's bark. Compaction shall be adequate to prevent the willow cutting from being easily removed from the soil.

ROOT PROTECTOR

Root protectors shall be installed in conformance with the details shown on the plans, the provisions in Section 20-2.13B, "Root Protector," and Section 20-4, "Highway Planting," of the Standard Specifications.

PLANT ESTABLISHMENT WORK

The plant establishment period shall be Type 2 and shall be not less than 250 working days.

Attention is directed to "Relief From Maintenance and Responsibility" in these special provisions regarding relief from maintenance and protection.

The center to center spacing of replacement plants for unsuitable ground cover plants shall be determined by the number of completed plant establishment working days at the time of replacement and the original spacing in conformance with the following:

ORIGINAL SPACING (Millimeters)	SPACING OF REPLACEMENT GROUND COVER PLANTS (Millimeters)		
	Number of Completed Plant Establishment Working Days		
	1-125	126-190	191-End of Plant Establishment
2000	2000	1000	500

During the plant establishment period, a watering schedule shall be submitted in writing to the Engineer for use during the plant establishment period.

Weeds within plant basins, including basin walls and ground cover, shall be controlled by hand pulling.

Weeds within ground cover areas and outside of plant basins shall be controlled by killing.

Weeds outside of plant basins, ground cover, the median, and paved areas shall be controlled by mowing.

Weeds within median areas, pavement, curbs, sidewalk, and other surfaced areas shall be controlled by killing.

Except as specified in these special provisions, disposal of mowed material will not be required unless ordered by the Engineer. Disposal of mowed material, as directed by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

At the option of the Contractor, plants of a larger container size than those originally specified may be used for replacement plants during the first 125 working days of the plant establishment period. The use of plants of a larger container size than those originally specified for replacement plants shall be at the Contractor's expense.

After 125 working days of the plant establishment period have been completed, replacement of plants, except for ground cover plants, shall be No. 1 size for seedlings, pot and liner size plants; No. 5 size for No. 1 size plants; No. 15 size for No. 5 size plants; and other plant replacement plants shall be the same size as originally specified.

When ordered by the Engineer, one application of a preemergent pesticide conforming to the provisions in "Pesticides" of these special provisions, shall be applied between 40 and 50 working days prior to completion of the plant establishment period. This work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Wye strainers shall be cleaned at least 15 days prior to the completion of the plant establishment period.

The final inspection shall be performed in conformance with the provisions in Section 5-1.13, "Final Inspection," of the Standard Specifications and shall be completed a minimum of 20 working days before the estimated completion of the contract.

10-2.06 IRRIGATION SYSTEMS

Irrigation systems shall be furnished and installed in conformance with the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications, except materials containing asbestos fibers shall not be used.

Attention is directed to the provisions in "Obstructions" of these special provisions, regarding work over or adjacent to existing underground facilities. Excavation for proposed irrigation facilities shall not be started until the existing underground facilities have been located.

Pipe supply lines shall be pressure tested in conformance with the provisions in Section 20-5.03H, "Pressure Testing," of the Standard Specifications, except the pipe (supply line) on the discharge side of the control valve shall be tested by Method B as specified in Section 20-5.03H(2), "Method B," of the Standard Specifications.

VALVE BOXES

Valve boxes shall conform to the provisions in Section 20-2.24, "Valve Boxes," of the Standard Specifications, except as otherwise provided herein.

Valve boxes shall be fiberglass or reinforced plastic.

Covers for plastic valve boxes shall be glass fiber reinforced plastic or plastic. Covers shall be hinged and include a bolt to secure the cover to the box.

Valve boxes shall be identified on the top surface of the covers by labels containing the appropriate abbreviation for the irrigation facility contained in the valve box as shown on the plans. Valve boxes that contain remote control valves shall be identified by the appropriate letters and numbers (controller and station numbers). Labels for valve boxes shall conform to the provisions in Section 20-5.03F, "Valves and Valve Boxes," of the Standard Specifications.

Label material shall be polyurethane.

IRRIGATION SYSTEMS FUNCTIONAL TEST

Functional tests for the irrigation controllers and associated automatic irrigation systems shall conform to the provisions in Section 20-5.027J, "Testing," of the Standard Specifications and these special provisions.

Tests shall demonstrate to the Engineer, through one complete cycle of the irrigation controllers in the automatic mode, that the associated automatic components of the irrigation systems operate properly. If automatic components of the irrigation systems fail a functional test, these components shall be repaired at the Contractor's expense and the testing repeated until satisfactory operation is obtained.

Associated automatic components shall include, but not be limited to, pump systems, remote control valve actuator systems, and remote control valves.

Upon completion of work on an irrigation system, including correction of deficiencies and satisfactory functional tests for the systems involved, the plants to be planted in the area watered by the irrigation system may be planted provided the planting areas have been prepared as specified in these special provisions and erosion control has been applied.

PIPE

Plastic Pipe

Plastic pipe supply lines shall be polyvinyl chloride (PVC) 1120 or 1220 pressure rated pipe with the minimum pressure rating (PR) shown on the plans.

Plastic pipe supply lines shall have solvent cemented type joints. Primers shall be used on the solvent cemented type joints.

SPRINKLERS

Sprinklers shall conform to the type, pattern, material, and operating characteristics listed in the "Sprinkler Schedule" shown on the plans.

FINAL IRRIGATION SYSTEM CHECK

A final check of existing and new irrigation facilities shall be performed not more than 20 working days prior to acceptance of the contract.

The length of watering cycles for the final check of irrigation facilities will be determined by the Engineer.

Remote control valves connected to existing and new irrigation controllers shall be checked for automatic performance when the controllers are in automatic mode.

Unsatisfactory performance of irrigation facilities installed or modified by the Contractor shall be repaired and rechecked at the Contractor's expense until satisfactory performance is obtained, as determined by the Engineer.

Repair or replacement of existing irrigation facilities due to unsatisfactory performance shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Nothing in this section "Final Irrigation System Check" shall relieve the Contractor of full responsibility for making good or repairing defective work or materials found before the formal written acceptance of the entire contract by the Director.

Full compensation for checking the irrigation systems prior to the acceptance of the contract shall be considered as included in the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

SECTION 10-3. SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS

10-3.01 DESCRIPTION

Modifying traffic signals, lighting, and sign illumination shall conform to the provisions in Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications and these special provisions.

Lighting equipment is included in the following structures:

- A. Prunedale Overcrossing, Bridge No. 44-0276Y.
- B. Prunedale Undercrossing, Bridge No. 44-0278.
- C. Prunedale Retaining Wall No. 1, Bridge No. 44-0280M.
- D. Prunedale Retaining Wall No. 2, Bridge No. 44-RW2.

Traffic signal work shall be performed at the following locations:

- A. Route 156 / Prunedale North Road Connector.
- B. SB 101 off-ramp / Prunedale North Road.

10-3.02 COST BREAK-DOWN

Cost break-downs shall conform to the provisions in Section 86-1.03, "Cost Break-Down," of the Standard Specifications and these special provisions.

The Engineer shall be furnished a cost break-down for each contract lump sum item of work described in this Section 10-3.

The cost break-down shall be submitted to the Engineer for approval within 15 days after the contract has been approved. The cost break-down shall be approved, in writing, by the Engineer before any partial payment for the items of electrical work will be made.

The cost breakdown shall include the following items in addition to those listed in the Standard Specifications:

- A. Span wire, guy wire, anchor plate, and hardware.
- B. Sign lighting fixture and hardware.
- C. Straps, seal and saddle brackets (for sign mounting).

10-3.03 MAINTAINING EXISTING AND TEMPORARY ELECTRICAL SYSTEMS

Traffic signal system shutdowns shall be limited to periods between the hours of 9:00 a.m. and 2:00 p.m.

10-3.04 STANDARDS, STEEL PEDESTALS AND POSTS

The sign panels will be State-furnished in conformance with the provisions in "Materials" of these special provisions.

Mast arm mounted street name signs shall be installed on signal mast arms at the locations shown on the plans. The street name signs and mounting hardware (except straps, seals and saddle brackets) will be State-furnished in conformance with the provisions in "Materials" of these special provisions. The State-furnished hanger assembly will be similar to that shown for internally illuminated street name signs. The mounting hardware and sign shall be assembled. The assembly shall be attached to the mast arm using a 19 mm x 0.53 mm stainless steel strap in a manner similar to the strap and saddle bracket method shown on the plans. The band shall be wrapped at least twice around the mast arm, tightened, and secured with a stainless strap seal in the same manner shown for strap and saddle bracket sign mounting. Straps, seals and saddle brackets shall be furnished by the Contractor. The sign panel shall be leveled and hardware securely tightened.

Type 1 standards shall be assembled and set with the handhole on the downstream side of the pole in relation to traffic or as shown on the plans.

10-3.05 CONDUIT

Conduit to be installed underground shall be Type 1 or Type 3 unless otherwise specified. Detector termination conduits shall be Type 3 or Type 4.

The conduit in a foundation and between a foundation and the nearest pull box shall be Type 1.

Conduit sizes shown on the plans and specified in the Standard Specifications and these special provisions are referenced to metallic type conduit. When rigid non-metallic conduit is required or allowed, the nominal equivalent industry size shall be used as shown in the following table:

Size Designation for Metallic Type Conduit	Equivalent Size for Rigid Non-metallic Conduit
21	20
27	25
41	40
53	50
63	65
78	75
103	100

When a standard coupling cannot be used for joining Type 1 conduit, a UL listed threaded union coupling conforming to the provisions in Section 86-2.05C, "Installation," of the Standard Specifications, or a concrete-tight split coupling, or concrete-tight set screw coupling shall be used.

When Type 3 conduit is placed in a trench (not in pavement or under portland cement concrete sidewalk), after the bedding material is placed and the conduit is installed, the trench shall be backfilled with commercial quality concrete, containing not less than 250 kg of portland cement per cubic meter, to not less than 100 mm above the conduit before additional backfill material is placed.

After conductors have been installed, the ends of conduits terminating in pull boxes, service equipment enclosures, and controller cabinets shall be sealed with an approved type of sealing compound.

10-3.06 CONDUCTORS AND WIRING

Splices shall be insulated by "Method B" by using "C" shaped compression cramp connectors or, at the Contractor's option, splices of conductors shall be insulated with heat-shrink tubing of the appropriate size after thoroughly painting the spliced conductors with electrical insulating coating.

The minimum insulation thickness, at any point, for Type USE, RHH or RHW wire shall be 1.0 mm for conductor sizes No. 14 to No. 10, inclusive, and 1.3 mm for No. 8 to No. 2, inclusive. The minimum insulation thickness, at any point, for Type THW and TW wires shall be 0.69 mm for conductor sizes No. 14 to No. 10, inclusive, 1.02 mm for No. 8, and 1.37 mm for No. 6 to No. 2, inclusive.

SIGNAL INTERCONNECT CABLE.

Signal Interconnect Cable (SIC) shall be the 6-pair type.

10-3.07 SERVICE

Type III service equipment enclosures shall be the aluminum type.

Circuit breakers used as service disconnect equipment shall have a minimum interrupting capacity of 42 000 A, rms, for 120/240 V(ac) services and 30 000 A, rms, for 480 V(ac) services.

10-3.08 NUMBERING ELECTRICAL EQUIPMENT

The placement of numbers on electrical equipment will be done by the Contractor as directed by the Engineer.

10-3.09 DETECTORS

Loop wire shall be Type 2.

Loop detector lead-in cable shall be Type B.

Slots shall be filled with hot-melt rubberized asphalt sealant.

10-3.10 LUMINAIRES

Ballasts shall be the lag or lead regulator type.

10-3.11 REMOVING, REINSTALLING OR SALVAGING ELECTRICAL EQUIPMENT

Salvaged electrical materials shall be hauled to 850 Elvee Drive, Salinas, CA 93901 and stockpiled.

The Contractor shall provide the equipment, as necessary, to safely unload and stockpile the material. A minimum of 2 working days' notice shall be given prior to delivery.

10-3.12 PAYMENT

The contract lump sum price paid for modify signal and lighting shall include highway lighting at intersections in connection with signals only.

Other roadway lighting on the project shall be considered as included in the contract lump sum price paid for lighting.

Full compensation for hauling and stockpiling electrical materials (including removal of signal system at Prunedale Road Off-Ramp / WB Route 156 On-Ramp) shall be considered as included in the contract price paid for the item requiring the material to be salvaged and no additional compensation will be allowed therefor.

SECTION 11. MODIFIED STANDARD SPECIFICATION SECTIONS

SECTION 11-1. QUALITY CONTROL / QUALITY ASSURANCE

Asphalt concrete shall conform to the provisions in this Section 11-1, "Quality Control / Quality Assurance," and the section entitled "Asphalt Concrete" in Section 10-1, "General," of these special provisions. Section 39, "Asphalt Concrete," of the Standard Specifications shall not apply to Type A and Type B asphalt concrete.

SECTION 39: ASPHALT CONCRETE

39-1 GENERAL

39-1.01 DESCRIPTION

This work shall consist of furnishing and mixing aggregate and asphalt binder at a central mixing plant, transporting, spreading and compacting the mixture, and furnishing and placing pavement reinforcing fabric, in conformance with this Section 11-1, "Quality Control / Quality Assurance," and with "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

The Contractor shall be responsible for controlling the quality of the asphalt concrete product entering the work, including aggregate, asphalt binder, additives, and asphalt concrete mixture; for controlling the quality of the work performed, including mix design, and mixing, transporting, spreading, and compacting the asphalt concrete; for controlling the quality of the finished roadway surface; and for developing, implementing, and maintaining a quality control program. The Contractor shall be responsible for the inspection, sampling, and testing required to control the quality of the asphalt concrete and the work performed.

The inspection, sampling, and testing required to control the quality of the workmanship and the asphalt concrete shall conform to this Section 11-1. Sampling shall be in conformance with the requirements of this Section 11-1 and with California Test 125. Testing shall be performed using California Tests unless otherwise directed by the Engineer or this Section 11-1.

Asphalt concrete is designated as Type A or Type B. The type of asphalt concrete will be shown on the plans or specified in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

39-2 MATERIALS

39-2.01 ASPHALTS

Asphalt binder to be mixed with aggregate shall be steam-refined paving asphalt conforming to the provisions in Section 92, "Asphalts," of the Standard Specifications. Asphalt binder shall be Grade AR-4000 unless the grade is designated in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Liquid asphalt for prime coat shall conform to the provisions in Section 93, "Liquid Asphalts," of the Standard Specifications and shall be the grade designated by the contract item or conform to the provisions in "Asphalt Concrete," in Section 10-1, "General," of these special provisions.

Asphalt emulsion for paint binder (tack coat) shall conform to the provisions in Section 94, "Asphaltic Emulsions," of the Standard Specifications for the rapid-setting or slow-setting type and grade approved by the Engineer.

Paving asphalt to be used as a binder for pavement reinforcing fabric shall be a steam-refined paving asphalt conforming to the provisions in Section 92, "Asphalts," of the Standard Specifications, and shall be Grade AR-4000, unless otherwise ordered by the Engineer or designated in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

39-2.02 AGGREGATE

Aggregate and combined aggregate shall conform to the quality and gradation provisions in this Section 11-1, "Quality Control / Quality Assurance," for the asphalt concrete types and sizes conforming to the provisions in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Aggregates shall be clean and free from decomposed or organic materials and other deleterious substances. Coarse aggregate is material retained on the 4.75-mm sieve, fine aggregate is material passing the 4.75-mm sieve, and supplemental fine aggregate is added fine material passing the 600- μ m sieve, including, but not limited to, cement and stored fines from dust collectors.

The target value for the percent passing each designated sieve size for the aggregate blend used in the proposed asphalt concrete mix design shall fall within the "Target Value Limits" of the following table:

Table 39-1 - AGGREGATE GRADATION
Type A and Type B Asphalt Concrete
Percentage Passing

19-mm Maximum, Coarse		19-mm Maximum, Medium	
Sieve Sizes	Target Value Limits	Sieve Sizes	Target Value Limits
25-mm	100	25-mm	100
19-mm	90-100	19-mm	90-100
9.5-mm	60-75	9.5-mm	65-80
4.75-mm	45-50	4.75-mm	49-54
2.36-mm	32-36	2.36-mm	36-40
600-µm	15-18	600-µm	18-21
75-µm	3-7	75-µm	3-8

12.5-mm Maximum, Coarse		12.5-mm Maximum, Medium	
Sieve Sizes	Target Value Limits	Sieve Sizes	Target Value Limits
19-mm	100	19-mm	100
12.5-mm	95-100	12.5-mm	95-100
9.5-mm	75-90	9.5-mm	80-95
4.75-mm	55-61	4.75-mm	59-66
2.36-mm	40-45	2.36-mm	43-49
600-µm	20-25	600-µm	22-27
75-µm	3-7	75-µm	3-8

During asphalt concrete production, aggregate gradation shall be within the limits specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Conformance with the grading requirements shall be determined by California Test 202, modified by California Test 105, when there is a difference in specific gravity of 0.2 or more between the coarse and fine portions of the aggregate or between the blends of the different aggregates. The percent passing the 75-µm sieve shall be reported to the first decimal place (tenths).

The combined aggregate shall conform to the following quality requirements prior to the addition of the asphalt binder:

Table 39-2 - AGGREGATE QUALITY REQUIREMENTS

Quality	California Test	Asphalt Concrete	
		Type A	Type B
Percent of Crushed Particles	205		
Coarse Aggregate (Min.)		90%	25%
Fine Aggregate (Passing 4.75-mm, Retained on 2.36-mm) (Min.)		70%	20%
Los Angeles Rattler	211		
Loss at 100 Rev. (Max.)		12%	
Loss at 500 Rev. (Max.)		45%	50%
Sand Equivalent (Min.) ¹	217	47	42
Kc Factor (Max.)	303	1.7	1.7
Kf Factor (Max.)	303	1.7	1.7

Note:

1. Reported value shall be the average of 3 tests split from a single sample.

39-2.03 ASPHALT CONCRETE MIXTURE

The asphalt concrete mixture, composed of the proposed aggregate blend and the proposed asphalt binder content as determined by California Test 367, shall conform to the following requirements:

Table 39-3 - ASPHALT CONCRETE MIXTURE REQUIREMENTS

Design Parameters	California Test	Asphalt Concrete Type and Location			
		Coast and Valley		Desert (per Engineer)	
		Type A	Type B	Type A	Type B
Hveem Stabilometer Value (Min.)	367 ^{1,2}	37	35	37	35
Percent air voids (Mix Design) (Start-Up Production Evaluation)	367 ¹	3-5 ³	3-5 ³	4-6 ⁴	4-6 ⁴
		Design Value ±1.0			
Swell ⁵ (mm) (Max)	305	0.76	0.76	0.76	0.76

Notes:

1. Reported value shall be the average of 3 tests from a single split sample.
2. If the range of stability for the 3 briquettes is more than 12 points, the briquettes shall be discarded and new samples shall be fabricated.
3. Modify California Test 367, paragraph C5, to "most nearly 4%."
4. Modify California Test 367, paragraph C5, to "most nearly 5%."
5. Measured at Mix Design only.

During production and placement, the asphalt concrete mixture shall conform to the requirements of Table 39-4, "Minimum Process Control Requirements," and Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Changes in cold feed or hot bin proportions to conform to the aggregate grading requirements shall not be considered changes in the mix design.

Whenever asphalt concrete production has been suspended for longer than 30 days, the Contractor, on the first day of resumption of production, shall sample and test the asphalt concrete to demonstrate conformance with the requirements of Table 39-3, "Asphalt Concrete Mixture Requirements," Table 39-4, "Minimum Process Control Requirements," and Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1.

The target value for asphalt content may be changed by as much as ± 0.2 percent during the production start-up evaluation specified in Section 39-10.02A, "Production Start-Up Evaluation," of this Section 11-1 or after production start-up evaluation and before the first day of regular production with the Engineer's approval. The Contractor shall demonstrate that asphalt concrete that has been produced through the plant using the modified target value for asphalt content is in conformance with this Section 11-1 by submitting test results for samples obtained from the first 500 tonnes of production. Stability and percent air voids shall be determined using 3 briquettes constructed from a single sample taken from 4 locations across the mat in conformance with the requirements of California Test 125.

Changes from one mix design to another shall not be made during the progress of the work, unless approved by the Engineer. Changes in asphalt content, other than those allowed during the start-up evaluation process, or in aggregate grading target values shall be considered to be a change in the asphalt concrete mixture and shall require a new mix design proposal. Changes in the asphalt content or aggregate grading target values approved by the Engineer will not be applied retroactively for acceptance or payment.

39-2.04 PAVEMENT REINFORCING FABRIC

Pavement reinforcing fabric shall conform to the provisions in Section 88, "Engineering Fabrics," of the Standard Specifications.

39-3 ASPHALT CONCRETE MIX DESIGN PROPOSAL AND REVIEW

39-3.01 CONTRACTOR MIX DESIGN PROPOSAL

The Contractor shall submit for the Engineer's review a proposed asphalt concrete mix design for each asphalt concrete mixture to be used at least 14 days prior to production of that asphalt concrete mixture. The asphalt concrete mix design shall be prepared by a laboratory (or laboratories) whose proficiency has been reviewed and qualified in conformance with the Department's Quality Assurance Program. Aggregate quality and asphalt concrete mix design test results shall be no more than one year old when production of the asphalt concrete mixture starts. For projects of more than one year's duration, asphalt concrete may be produced using the asphalt concrete mix design that was reviewed and accepted at the start of the project provided the asphalt concrete mixture continues to conform to the provisions of this Section 11-1, "Quality Control / Quality Assurance."

The Contractor shall submit a mix design letter that indicates the target values proposed for gradation, asphalt content, and percent air voids. This submittal shall include test results for aggregate and asphalt mixture quality; plots of the combined gradings showing the production tolerances; plots of unit weight, stability, and percent air voids versus asphalt content for the asphalt contents considered in the design process. In addition, this submittal shall include test results for stability, percent air voids, and swell for 3 briquettes constructed using the submitted aggregate and asphalt blended at the proposed target values for each asphalt concrete mixture to be used.

The Contractor shall submit the following for each asphalt concrete mixture proposed:

A. Aggregate and mineral filler:

1. Target values for percent passing each sieve size for the aggregate blend;
2. Results of tests for aggregate quality requirements;
3. Source of each aggregate to be used including producer, location, and California Mine Identification number;
4. Percentage of each aggregate stockpile, cold feed or hot bin to be used;
5. Gradation of each aggregate stockpile, cold feed or hot bin to be used; and
6. Samples that are representative of the aggregate to be used. Minimum sample sizes shall be as follows:

60 kg of each coarse aggregate;
40 kg of each fine aggregate; and
5 kg of each supplemental fine aggregate.

B. Asphalt binder:

1. Asphalt binder source and target value;
2. Four one-liter samples of the asphalt binder;
3. Results of the asphalt binder quality tests conforming to the provisions in Section 92, "Asphalts," of the Standard Specifications; and
4. Material Safety Data Sheets.

C. Antistrip additives, when applicable:

1. A 5-kg sample of the dry additive or a one-liter sample of the liquid antistrip additive, including name of product, manufacturer, manufacturer's designation and proposed rate, location, and method of addition; and
2. Material Safety Data Sheets.

The proposed asphalt concrete mix design submittal will be considered complete only when the mix design letter, test results, plots, and samples have been received by the Engineer.

39-3.02 ENGINEER REVIEW OF ASPHALT CONCRETE MIX DESIGN

The Engineer will review the proposed aggregate and asphalt concrete mixture for conformance with this Section 11-1, "Quality Control / Quality Assurance." The proposed asphalt concrete mixture will be reviewed at the proposed target values for aggregate grading and asphalt content. The Engineer will have 14 days to review each submittal of a proposed mix design. Production of asphalt concrete shall not begin until written notification has been received from the Engineer that the aggregates and proposed mix design meet the quality requirements of this Section 11-1.

The Engineer will reject a proposed asphalt concrete mixture that, during review, fails to meet the quality requirements of Table 39-2, "Aggregate Quality Requirements," and Table 39-3, "Asphalt Concrete Mixture Requirements," of this Section 11-1. The Contractor shall resubmit a mix design letter providing new test results, plots, and material samples.

Disagreements in mix design review shall be resolved in conformance with Section 39-6, "Dispute Resolution," of this Section 11-1. The Contractor shall use a mix design on the project only after the Engineer concurs that the aggregate and asphalt concrete represented by the proposed mix design conforms to the provisions of this Section 11-1.

The Engineer will review one proposed asphalt concrete mix design for each asphalt concrete type and aggregate size from each plant proposed for use on this project at the State's expense. Costs for additional reviews due to failure to conform to the quality requirements of this Section 11-1 and for reviewing other proposed asphalt concrete mix designs will be deducted from moneys due or to become due the Contractor. The cost for each review will be \$1,500. Costs for reviewing changes in a mix design that are initiated by the Engineer will be waived. Contractor's retesting due to errors in the Engineer's testing will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Costs for reviewing mix designs not used in this project will be deducted from moneys due or to become due the Contractor.

39-4 CONTRACTOR QUALITY CONTROL

39-4.01 GENERAL

The Contractor shall be responsible for the quality of the asphalt concrete entering into the work and of the work performed. In addition, the Contractor shall be responsible for the quality of asphalt concrete or ingredients procured from subcontractors or vendors. A quality control system shall be established, maintained, and modified, if needed, that will provide assurance that materials and completed work conform to contract requirements.

At least 14 days prior to the start of production of asphalt concrete, the Contractor shall submit a written Quality Control Plan. At the request of the Engineer or the Contractor, the Contractor shall discuss the Quality Control Plan with the Engineer.

39-4.02 QUALITY CONTROL PLAN

The Quality Control Plan shall describe the organization and procedures that will be used to administer the quality control system including the procedures used to control the production process, the procedures used to determine when changes to the production process are needed, and the procedures proposed to be used to implement the required changes. The Quality Control Plan shall meet the minimum standards set forth in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete," available as specified in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Asphalt concrete production and placement shall not begin until the Quality Control Plan has been approved by the Engineer. Approval of the Quality Control Plan does not imply a warranty by the Engineer that adherence to the plan will result in production of asphalt concrete that complies with this Section 11-1. It shall remain the responsibility of the Contractor to demonstrate such compliance.

The Quality Control Plan shall include the name and qualifications of a Quality Control Manager. The Quality Control Manager shall be responsible for the administration of the Quality Control Plan, including compliance with the plan and plan modifications. The Quality Control Manager shall be responsible to the Contractor, shall have the authority to make decisions concerning quality of the work or product, and shall be available to the project within less than 3 hours during paving. Except in cases of emergency and with the approval of the Engineer, the Quality Control Manager cannot be a foreman, member of the production or paving crew, an inspector or tester on this project during pavement production and placement.

The Quality Control Plan shall identify personnel, equipment and documentation required for a complete inspection, sampling and testing program. The Quality Control Plan shall include, but not be limited to, a list of inspectors, samplers and testers, their duties, their certifications if required, and their experience if no certification is required. It shall also list the name and location of laboratories that shall be providing information to the Engineer, the testers who conducted the tests and their certifications and the name of the Laboratory Quality Control Manager responsible for oversight of the testing program. It shall also show examples of the test result forms (if different from those in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete"), the roadway and plant inspection forms, the Quality Control Manager's daily summary form, and the compliance charts. It shall include the method by which random sampling shall be determined, a list of the testing and sampling equipment to be used and the current calibration dates and calibration charts, and copies of nuclear gauge licenses.

The Quality Control Plan shall include the name and certification of a testing consultant to be an Independent Third Party in dispute resolution. By mutual agreement during dispute resolution, the Independent Third Party may be a District Independent Assurance Sampler and Tester, the testing consultant or both. The proficiency of the testing consultant shall be reviewed and certified in conformance with the requirements of the Department's Quality Assurance Program before the test consultant participates in dispute resolution. Attention is directed to Section 39-6, "Dispute Resolution," of this Section 11-1.

The Quality Control Plan may be modified as work progresses. A supplement shall be submitted whenever there are changes to quality control procedures or personnel. Asphalt concrete production and placement shall not resume or continue until revisions to the Quality Control Plan or quality control personnel have been approved by the Engineer.

39-4.03 CONTRACTOR QUALITY CONTROL INSPECTION, SAMPLING, AND TESTING

The Contractor shall perform process and quality control sampling and testing, provide inspection, and exercise management control to ensure that asphalt concrete production and placement conforms to the provisions of this Section 11-1. Staffing for process and quality control shall meet the minimum requirements outlined in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete."

Process and quality control, sampling, testing, and inspection shall be provided during the asphalt concrete work. Sampling, testing, and inspection shall be performed at a rate sufficient to ensure that asphalt concrete conforms to the provisions of this Section 11-1.

A roadway inspector shall be provided while asphalt concrete paving operations are in progress. The roadway inspector shall ensure that asphalt concrete placement conforms to industry standards and to the spreading, compacting, and finishing requirements of this Section 11-1, "Quality Control / Quality Assurance." Plant inspection shall be performed as necessary to maintain control of the asphalt concrete production.

Minimum sampling and testing requirements for process and quality control are specified in Table 39-4, "Minimum Process Control Requirements," and Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Sampling shall be statistically based and random.

During production start-up evaluation, the Contractor shall sample and test in conformance with the provisions in Section 39-10.02A, "Production Start-Up Evaluation," of this Section 11-1.

A testing laboratory and personnel shall be provided for the performance of process and quality control testing. The Engineer shall have unrestricted access to mix design, sampling, and testing.

The proficiency of testing laboratories and sampling and testing personnel shall be reviewed, qualified, and certified by the Department's Independent Assurance Sampler and Tester before providing services to the project. Inspectors shall meet the standards set forth in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete."

39-4.04 CONTRACTOR PROCESS CONTROL

Process control sampling and testing shall be performed and control shall be exercised to ensure that asphalt concrete production conforms with this Section 11-1.

Minimum process control sampling and testing shall be performed in compliance with the following:

Table 39-4 - MINIMUM PROCESS CONTROL REQUIREMENTS

Quality Characteristic	Action Limit	California Test	Minimum Sampling and Testing Frequency	Point of Sampling ‡	Reporting Time Allowance
Sand Equivalent (Min)	47 (Type A) 42 (Type B)	217	One sample per 2500 tonnes	Batch plant - from hot bins. Drum plant - from cold feed.	24 hours
		(Reported value shall be the average of 3) ¹	Not less than one sample per 2 days		
Stability	37 (Type A) 35 (Type B)	366 ²	See Note 4	Mat behind paver	48 hours
		(Reported value shall be the average of 3) ^{1,3,5}	Not less than one sample per 5 days		

Notes:

- ‡ In conformance with the requirements of California Test 125.
- 1. Samples used for the 3 tests to be averaged shall be from a single split sample.
- 2. Reheat for sample preparation shall be 2 hours maximum.
Do not place sample or briquette in oven for 15-hour cure.
- 3. Briquettes shall be fabricated from a single, combined sample obtained from at least 4 locations across the mat behind the paver in conformance with the requirements of California Test 125.
If the range of stability for the three briquettes is more than 12 points, the samples shall be discarded and new samples shall be obtained before the end of the following shift of paving and tested in conformance with the requirements of Table 39-3, "Asphalt Concrete Mixture Requirements."
- 4. Asphalt concrete will be sampled and tested each of the first 5 days of production and may be decreased to one for each 5 days thereafter unless stability falls below the action limit.
When stability falls below the action limit, sampling will be increased to one sample for each of the first 5 days of production and may be decreased to one for each 5 days thereafter.
The sequence of the first 5 test results shall not be broken by more than 7 days of suspended operations.
- 5. During production start-up evaluation, a correlation factor for cured vs. uncured specimens shall be established in conformance with the requirements of Section 39-10.02A, "Production Start-Up Evaluation."

The process control test results shall be plotted on specification compliance charts indicating the action limits for the quality characteristic. When one test result falls below the action limit for an individual measurement, the Contractor shall notify the Engineer, take corrective action, and sample and test within the next 500 tonnes of production. When 2 consecutive test results for an individual characteristic fall below the action limit, the asphalt concrete represented by the 2 tests shall be considered not in compliance. When 2 consecutive test results for an individual characteristic fall below the action limit, the Contractor shall suspend production, notify the Engineer, and take corrective action. With the approval of the Engineer, up to 1000 tonnes of asphalt concrete may be placed to demonstrate that the asphalt concrete is once again in compliance with the provisions of this Section 11-1. Production shall begin only after the Engineer has received test results confirming compliance.

Asphalt concrete that has 2 consecutive stability test results less than or equal to 26 for Type A asphalt concrete or less than or equal to 24 for Type B asphalt concrete shall be removed at the Contractor's expense. Asphalt concrete placed to demonstrate compliance that does not meet the provisions of this Section 11-1 shall be removed at the Contractor's expense.

39-4.05 CONTRACTOR QUALITY CONTROL

Quality control, sampling, testing, and inspection shall be provided during asphalt concrete work. Sampling, testing, and inspection shall be performed at a rate sufficient to ensure that the asphalt concrete product conforms to the requirements in this Section 11-1. Sampling for testing to be reported to the Engineer shall be performed at the minimum frequency specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1, "Quality Control / Quality Assurance."

Quality control samples of aggregates and asphalt concrete mixture shall be obtained and split. One split portion of each sample shall be used for quality control testing and the other portion shall be reserved for possible retest during dispute resolution, in conformance with Section 39-6, "Dispute Resolution," of this Section 11-1. Quality control samples shall be stored in a location listed in the Quality Control Plan until disposal has been approved by the Engineer.

The Contractor shall obtain a one-liter sample of the asphalt binder in conformance with Section 39-7.01C, "Asphalt Binder Storage," of this Section 11-1 for each day of asphalt concrete production. The sample containers shall be labeled as shown in the "Manual for Quality Control and Quality Assurance for Asphalt Concrete" and shall be sent by the Contractor to the Transportation Laboratory on a weekly basis, except for modified asphalts that shall be shipped daily. A copy of the transmittal form shall be attached to the daily report of inspection.

When test results for a single quality characteristic deviate beyond the limits specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1 the Contractor shall take corrective action and shall bring the asphalt concrete within the specification limits. The corrective action taken shall be documented in the records of inspection in conformance with Section 39-4.06B, "Records of Inspection and Testing," of this Section 11-1. When a single quality characteristic deviates 3 consecutive times beyond the limits specified in Table 39-9, "Minimum Quality Control Test Requirements," of this Section 11-1, the Contractor shall suspend production, shall notify the Engineer, and shall take corrective action. With the approval of the Engineer, up to 1000 tonnes of asphalt concrete may be placed and the requirements of Section 39-10.02A, "Production Start-Up Evaluation," of this Section 11-1 shall be used to demonstrate that the asphalt concrete is once again in compliance with this Section 11-1. Production of asphalt concrete shall start only after the Engineer has received test results confirming compliance. When an individual quality characteristic deviates 3 consecutive times beyond the specification limits and production of asphalt concrete has been suspended, the lot shall be terminated.

If an ignition oven is used for asphalt content in conformance with the requirements of California Test 382, gradations of the remaining aggregates shall be provided for each 5000 tonnes of production. Testing of the aggregates shall be in conformance with the requirements of California Test 202, Sections F and G, "Sieve Analysis of Fine and Coarse Aggregates." Test results from these gradings shall be provided prior to completion of the project. Gradings from the aggregates recovered from the ignition oven will not be used in the statistical analysis for quality or for pay. Payment for these gradings will be made as extra work as provided in Section 4-1.03D of the Standard Specifications at the rate of \$150 per test result for the cost of the additional testing.

39-4.06 CHARTS AND RECORDS

The Contractor shall record sampling and testing results for both process control and for quality control on forms as provided in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete" or on forms approved by the Engineer. Complete testing records shall be maintained and posted in the Contractor's laboratory. Models of forms that are different from those in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete," locations of postings, and times and means of submissions shall be provided in the Quality Control Plan.

For every 5000 tonnes of asphalt concrete produced, the Contractor shall provide an electronic copy of the process and quality control test results using the Department's statistical evaluation program "ACPay" available as specified in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Compliance charts and inspection and testing records, except stability test results used for process control, shall be submitted within 24 hours after completion of that shift of asphalt concrete production. If the record is incomplete or in error, a copy of the record will be returned with the deficiencies noted by the Engineer. The Contractor shall correct deficiencies and return the updated record by the start of the following working day. When errors or omissions in the inspection or testing records repeatedly occur, asphalt concrete production and placement shall be suspended and the procedures by which the records are produced shall be corrected before production and placement will be restarted.

39-4.06A Compliance Charts

The Contractor shall develop and maintain time linear specification compliance charts. The compliance charts shall identify the project, test number, test parameter, applicable upper and lower specification limits, and test results.

Compliance charts shall be kept current and shall be posted at a location designated in the Quality Control Plan. Compliance charts shall be updated each day of asphalt concrete production, and up-to-date copies shall be included in the submittals to the Engineer of each day's test results.

39-4.06B Records of Inspection and Testing

For each day of asphalt concrete production, the Contractor shall prepare an "Asphalt Concrete Construction Daily Record of Inspection," on forms provided in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete." A form shall be submitted for inspection at the plant and at the roadway.

For each day of asphalt concrete production, the Contractor shall prepare an "Asphalt Concrete Inspection and Testing Summary" on a form provided in the Department's "Manual for Quality Control and Quality Assurance for Asphalt Concrete." Plant and roadway inspection forms documenting the day's plant production and roadway placement shall be completed. Deviations from the specifications or the Contractor's regular practice shall be listed and explained. Individual inspection forms shall be signed by the inspector and initialed by the Quality Control Manager and attached to the summary at submittal. Test forms documenting test results shall be complete, signed by the tester, checked and initialed by the Quality Control Manager, and attached to the summary at submittal. Sampling and testing data and calculations that support a test result shall be made available to the Engineer within 48 hours when requested.

The "Asphalt Concrete Inspection and Testing Summary" shall include the following certification signed by the Quality Control Manager:

It is hereby certified that the information contained in this record is accurate, and that information, tests or calculations documented herein comply with the requirements of the contract and the standards set forth in the testing procedures. Exceptions to this certification are documented as a part of this record.

39-5 ENGINEER QUALITY ASSURANCE

39-5.01 GENERAL

The Engineer will assure conformance to contract specifications by review of the Contractor's mix design proposal, by inspection of the Contractor's procedures, by oversight of the Contractor's quality control inspection and records, by splitting and testing samples with the Contractor during evaluation of the plant production start-up and the nuclear density test strip, and by independent verification sampling and testing of the asphalt concrete and aggregates during asphalt concrete production.

The Contractor may witness assurance sampling and testing. However, the Engineer will not be required to notify the Contractor of anticipated sampling schedules or locations and will not delay sampling or testing if the Contractor is unable to attend. The Contractor shall not use samples taken for assurance testing for testing and submittal as a quality control test result.

The Engineer will provide the Contractor with copies of the assurance test results not more than 2 working days after receipt of the results. Sampling and testing data and calculations that support a test result shall be made available to the Contractor within 48 hours when requested.

The Engineer may test the asphalt, aggregates or asphalt concrete mixture to determine conformance with this Section 11-1, "Quality Control / Quality Assurance," whenever an asphalt concrete mixture or ingredient appears defective or inconsistent or whenever a test result indicates a change in the characteristics of the asphalt concrete mixture or an ingredient. Asphalt, aggregates or asphalt concrete that does not conform with this Section 11-1 will be rejected in conformance with Section 39-11, "Acceptance of Work," of this Section 11-1.

The Contractor, when directed by the Engineer, shall obtain representative samples of the asphalt concrete mixture or ingredients that appear defective or inconsistent. The samples shall be split into 4 portions. The Contractor shall retain 1 portion for testing if the Contractor chooses and 3 portions shall be delivered to the Engineer. The asphalt concrete or ingredient need not be sampled if the Contractor elects to remove and replace the asphalt concrete, at the Contractor's expense, or if the Contractor uses a method of correcting the situation that has been approved by the Engineer. Test results from these additional samples shall not be used as a basis for a calculated pay factor.

39-5.02 SAMPLING AND TESTING FOR VERIFICATION

Independent of the Contractor's quality control testing, the Engineer will obtain random samples of the aggregate and asphalt concrete mixture and test for in-place density.

Samples of aggregates and asphalt concrete will be obtained during asphalt concrete production and placement, and will be split into at least 4 portions. One of the split portions will be tested by the Engineer and used to verify quality control test results, one portion will be provided to the Contractor, and 2 portions will be reserved and stored for testing in conformance with the provisions in Section 39-6, "Dispute Resolution," of this Section 11-1. When verifying the relative compaction, the Engineer will obtain a sample of a sample of asphalt concrete from the mat behind the paver, will split the sample and apportion the sample as described above, and will test the sample for test maximum density.

The Engineer will test for material quality characteristics specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Verification tests will be at a frequency of not less than 10 percent of the minimum quality control sampling and testing frequency and will be performed in conformance with the test methods specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Verification tests will be performed using the same test methods used for quality control testing.

During the Engineer's verification of the relative compaction, the Engineer will determine the location of 500 tonnes of asphalt concrete to be tested using a random number, will obtain an asphalt concrete sample from within this location for determination of the test maximum density, and will determine the relative compaction of the in-place asphalt concrete as specified in California Test 375. The Contractor shall obtain one of the split samples of asphalt concrete for determination of test maximum density and shall determine the relative compaction of the 500 tonnes of asphalt tested by the Engineer using the same testing sites determined by the Engineer. The results of this common testing will be compared to the allowable testing difference defined in Table 39-6, "Allowable Testing Differences," of this Section 11-1. If the test maximum density or the relative compaction does not comply with the allowable testing difference, then the Engineer and Contractor will use the first 500 tonnes of the next day's production to re-correlate the nuclear gauges used in testing as defined by California Test 375.

During production start-up evaluation, the Engineer will witness the sampling of asphalt concrete and aggregates and will perform tests on the materials in conformance with Section 39-10.02A, "Production Start-Up Evaluation," of this Section 11-1.

39-5.03 VERIFICATION

The Engineer will determine the acceptability of the quality control test results by using the *t*-test for sample means to test whether or not the means of the quality control test results and verification test results are within an allowable testing difference. Quality control test results and verification test results for each indexed quality characteristic will be used in the verification process.

The *t*-value of the group of test data to be verified is computed as follows:

$$t = \frac{|\bar{X}_c - \bar{X}_v|}{S_p \sqrt{\frac{1}{n_c} + \frac{1}{n_v}}} \quad \text{and} \quad S_p^2 = \frac{S_c^2(n_c - 1) + S_v^2(n_v - 1)}{n_c + n_v - 2}$$

where:

- n_c = Number of Contractor's quality control tests (minimum of 2 required)
- n_v = Number of Verification tests (minimum of 1 required)
- \bar{X}_c = Mean of the Contractor's quality control tests
- \bar{X}_v = Mean of the Verification tests
- S_p = Pooled standard deviation
(When $n_v = 1$, $S_p = S_c$)
- S_c = Standard deviation of the Contractor's quality control tests
- S_v = Standard deviation of the Verification tests (when $n_v > 1$)

The comparison of quality control test results and verification test results will be considered at a level of significance, _____ Computing the equation above and compare to the critical t -value, t_{crit} , from the following table:

Table 39-5 - CRITICAL t -VALUE FOR VERIFICATION OF QUALITY CONTROL TESTING

degrees of freedom (nc+nv-2)	t_{crit} (for $\alpha = 0.01$)	degrees of freedom (nc+nv-2)	t_{crit} (for $\alpha = 0.01$)
1	63.657	18	2.878
2	9.925	19	2.861
3	5.841	20	2.845
4	4.604	21	2.831
5	4.032	22	2.819
6	3.707	23	2.807
7	3.499	24	2.797
8	3.355	25	2.787
9	3.250	26	2.779
10	3.169	27	2.771
11	3.106	28	2.763
12	3.055	29	2.756
13	3.012	30	2.750
14	2.977	40	2.704
15	2.947	60	2.660
16	2.921	120	2.617
17	2.898		2.576

Quality control test results are verified if the t -value computed is less than or equal to t_{crit} ($t \leq t_{crit}$), and the difference between the means of the quality control test results and verification test results are within an allowable testing difference. Quality control test results are not verified if the t -value computed is greater than t_{crit} ($t > t_{crit}$), and the difference between the means exceeds the allowable testing difference. The allowable testing difference shall be as follows:

Table 39-6 - ALLOWABLE TESTING DIFFERENCE

Quality	California Test	Allowable Testing Difference
Sand Equivalent (min.)	217	8
Hveem Stabilometer Value (min.)	366	10
Percent Air Voids	367	1.5
Asphalt Content	379 or 382	0.3%
Gradation	202	
19 or 12.5 mm		2
9.5 mm		4
4.75 mm		3
2.36 mm		2
600 μ m		2
75 μ m		1.0
Relative Compaction Test Maximum Density	375	0.8% 0.03 g/cc

If quality control test results are not verified, the Contractor will be notified of the difference. The Engineer will sample asphalt concrete production at a more frequent interval. Resolution of the problem shall be in conformance with the provisions in Section 39-6, "Dispute Resolution," of this Section 11-1.

39-6 DISPUTE RESOLUTION

39-6.01 GENERAL

The Contractor and the Engineer shall work together to avoid potential conflicts and to resolve differences that may arise from a disagreement regarding test result comparisons.

Should the results of the testing fail to meet the criteria of the stage at which the disagreement arose, production shall be suspended. Production shall not start or resume nor shall asphalt concrete be accepted until the differences have been resolved and the Engineer is assured that the asphalt concrete conforms to this Section 11-1, "Quality Control / Quality Assurance."

When the Engineer and the Contractor, together or separately, are unable to determine the source of error, an Independent Third Party shall act as witness and referee.

In disagreements, if the Engineer's testing process meets the requirements of this Section 11-1, costs related to the review shall be borne by the Contractor. The Contractor's sampling and testing program shall be modified as necessary. New test results shall be submitted to the Engineer. Test results judged to be in error shall be removed from consideration and the new test results shall be substituted. If split samples are not available and retesting is not possible, that portion of the asphalt concrete produced or placed prior to and during the disagreement will be evaluated based on the results of the Engineer's verification test results.

In disagreements, if the Engineer's testing process fails to meet the requirements of this Section 11-1, costs related to the review shall be borne by the State. The Engineer's sampling and testing program will be modified as necessary. Test results judged to be in error shall be removed from consideration and the new test results shall be substituted. Contractor's retesting due to errors in the Engineer's testing will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. If, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of delays or errors in the Engineer's testing, the delay will be considered a right of way delay as provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

In disagreements, if both the Contractor's and the Engineer's testing processes have failed to meet the requirements of this Section 11-1 or if the cause cannot be determined, each party will bear the costs related to their own review. When appropriate, the Contractor's and the Engineer's sampling and testing programs shall be modified as necessary, split samples of the Contractor's quality control samples or the Engineer's verification samples shall be retested, and the new quality control test results shall be submitted to the Engineer. Test results judged to be in error shall be removed from consideration and the new test results shall be substituted. If split samples of aggregates or asphalt concrete mixture from the Contractor's testing are not available where retesting is required, that portion of the asphalt concrete produced prior to and during the disagreement will be evaluated based on the results of the Engineer's verification test results.

39-6.02 DURING THE ASPHALT CONCRETE MIX DESIGN REVIEW

During the asphalt concrete mix design review, if the Engineer's review does not confirm that one or more of the aggregate or the asphalt concrete mixture qualities comply with this Section 11-1, "Quality Control / Quality Assurance," both parties will review their sampling, testing, and test results and shall share their findings. Testers and laboratories shall be made available for witnessing. Calculations and test results shall be made available for review. If an error in the Contractor's testing is detected during this review, the Contractor shall, as is appropriate, recalculate or retest. The new test results shall be submitted to the Engineer. If an error in the Engineer's testing is detected, the Engineer will, as is appropriate, recalculate or retest.

If the Contractor's and Engineer's review does not reveal the source of conflict, the Contractor's and the Engineer's sampling and testing processes shall be witnessed by the Independent Third Party. Testing to resolve the dispute in results for the mix design shall be performed using samples that were obtained and split while being witnessed by the Independent Third Party. Review of sample preparation and testing will be performed at both the Contractor's and the Engineer's laboratory on a portion of the split material while being witnessed by the Independent Third Party. The resulting mix design shall be used for production.

39-6.03 DURING THE PRODUCTION START-UP EVALUATION

When the Contractor's and Engineer's test results during production start-up fail to meet the provisions in Section 39-10.02, "Production Start-Up Evaluation and Nuclear Density Test Strips," both parties will review their sampling, testing, and test results, and shall share their findings. Testers and laboratories shall be made available for witnessing. Calculations and test results shall be made available for review. If an error in the Contractor's testing is detected during this review, the Contractor shall, as is appropriate, recalculate or retest. The new test results shall be submitted to the Engineer. If an error in the Engineer's testing is detected, the Engineer will, as is appropriate, recalculate or retest.

If the Contractor's and the Engineer's review does not resolve the differences, the Contractor's and the Engineer's testing processes shall be witnessed by the Independent Third Party using the 2 remaining portions of the split samples. If necessary, a 250-tonne to 500-tonne quantity of asphalt concrete shall be placed at a location agreed to by the Engineer to provide asphalt concrete and ingredients for sampling and testing for the Independent Third Party review.

If an error in the Contractor's testing is detected by the Independent Third Party, the Contractor shall take corrective action and, as appropriate, recalculate or retest the split portion of the trial quantity of asphalt concrete in question. The new test results shall be submitted to the Engineer. If an error in the Engineer's testing is detected by the Independent Third Party, the Engineer will take corrective action and, as appropriate, recalculate or retest the split portion of the first trial quantity.

Production shall not start nor shall asphalt concrete be accepted until the differences have been resolved and the test results meet the provisions in Section 39-10.02, "Production Start-Up Evaluation and Nuclear Density Test Strips," of this Section 11-1.

39-6.04 DURING PRODUCTION

When it is determined that the quality control test results could not be verified, both parties will review their sampling, testing, and test results, and shall share their findings. Testers and laboratories will be made available for witnessing. Calculations and results will be made available for review.

If an error in the quality control sampling or testing is detected during the Contractor's or the Engineer's review, the Contractor shall either recalculate or, if appropriate, retest using the reserved split portions of the quality control samples. These new test results shall be submitted to the Engineer. If an error in the verification sampling or testing is detected, the Engineer will recalculate or, if appropriate, retest using a reserved split portion of the verification samples. Using the new test results, the Engineer will repeat the calculation of the *t*-test and will determine if the means of the quality control tests and the verification test results are within the allowable testing difference as specified in Section 39-5.03, "Verification," of this Section 11-1.

When the verification test results do not verify the quality control test results 3 consecutive times, both the Contractor's and the Engineer's testers shall be witnessed by the Independent Third Party while sampling, splitting, and testing samples from the production unit or from the mat. The Contractor may produce and place up to 1000 tonnes of asphalt concrete to provide materials and sampling opportunities. Production and placement of asphalt concrete will be suspended until the Independent Third Party has completed the review of the Contractor's and the Engineer's sampling and testing and resolved the differences.

If an error in the Contractor's testing is detected by the Independent Third Party, the Contractor shall take corrective action and, as appropriate, recalculate or retest the split portion of the quality control samples. The new test results shall be submitted to the Engineer. If an error in the Engineer's testing is detected by the Independent Third Party, the Engineer will take corrective action and, as appropriate, recalculate or retest a split portion of the verification samples. When the error has been detected and corrected, production shall resume and the services of the Independent Third Party will be discontinued.

If a problem is not identified during the Independent Third Party review, the Independent Third Party shall be retained for the duration of the project or until a problem has been identified. Until all asphalt concrete has been produced and placed, the Contractor shall sample and split quality control samples in the presence of the Independent Third Party. One portion of each sample shall be tested by the Contractor in conformance with the intervals specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1, and the other portion shall be delivered to the Engineer by the Independent Third Party. The Engineer will test at least one of every 5 of the split samples for verification purposes. A new lot will be designated for asphalt concrete produced since the Independent Third Party was consulted. The pay factor for this lot will be determined in conformance with Section 39-11.02, "Statistical Evaluation and Determination of Pay Factor," of this Section 11-1 with the exception that both the Contractor's quality control test results and the Engineer's verification test results will be combined and will be the basis for acceptance of that portion of the work. The pay factor for the lot of asphalt concrete which brought about the dispute resolution shall be determined in conformance with Section 39-11.02, "Statistical Evaluation and Determination of Pay Factor," of this Section 11-1 with the exception that both the Contractor's quality control test results and the Engineer's verification test results will be combined and will be the basis for acceptance of that portion of the work.

39-7 STORING, PROPORTIONING AND MIXING MATERIALS

39-7.01 STORAGE

The Contractor shall store the aggregate for asphalt concrete so that separately sized aggregates will not be intermingled and shall store asphalt binder so that different grades of asphalt will not be intermingled. Aggregate that has been intermingled with aggregate of another size shall be removed by the Contractor and replaced with aggregate of specified grading.

When the Contractor adds supplemental fine aggregate, each supplemental fine aggregate used shall be stored separately and kept thoroughly dry.

The measurement and storage provisions of this Section shall not apply to the dust collected in skimmers and expansion chambers (knock-out boxes) or to the dust collected in centrifugal (cyclone) collectors. Dust from these collectors may be returned to the aggregate without being measured or stored separately, provided the dust is returned uniformly at a point in advance of the sampling device in batch-mixing plants or is returned at or before mixing in continuous mixing plants.

Aggregate and asphalt binder shall be stored in conformance with the following requirements.

39-7.01A Aggregate Cold Storage

Material shall be fed from storage with a mechanical feeder. Before being fed to the drier, aggregate shall be separated into 3 or more sizes and stored separately.

39-7.01B Aggregate Hot Storage

Aggregate for asphalt concrete to be mixed in batch mixing plants shall be stored, after being dried, in conformance with the following requirements:

1. Aggregates for asphalt concrete shall be separated into 3 or more sizes.
2. After the aggregate is separated, each size shall be stored in a separate bin, and shall be recombined in conformance with the provisions in Section 39-7.03A, "Proportioning for Batch Mixing," of this Section 11-1 in order to conform to the gradings specified in Section 39-2, "Materials," of this Section 11-1. Storage bins shall be provided with chutes to prevent overflow into adjacent bins.

39-7.01C Asphalt Binder Storage

Asphalt to be used as a binder for asphalt concrete shall be stored in heated tanks.

A suitable sampling device shall be provided in asphalt feed lines connecting plant storage tanks to the asphalt weighing system or spray bar. The sampling device shall consist of a valve with a nominal diameter between 10 mm and 20 mm, constructed in such a manner that a one-liter sample may be slowly withdrawn during plant operations. The valve shall be maintained in good condition and, if the valve fails to function properly, the valve shall be replaced. The sampling device shall be readily accessible and in an area free of dangerous obstructions and shall be between 600 mm and 750 mm above the platform. A drainage receptacle shall be provided for flushing the device prior to sampling.

The discharge end of the asphalt binder circulating pipe shall be maintained below the surface of the asphalt binder in the storage tank to prevent discharging hot asphalt binder into open air.

A temperature sensing device shall be installed in the asphalt feed line. The device shall measure the temperature of the asphalt and shall be accurate to 5°C increments. An automatic, continuous recording device shall be provided and used to maintain accurate records of the asphalt temperature during production. Where the plant controller has the capability of capturing production data electronically, including ingredient temperatures, and when this data represents the temperature at the time of production and is captured at intervals of not greater than 5 minutes, this process will be considered to be continuous recording. Captured data shall be retained for the duration of the contract and shall be submitted to the Engineer on request.

39-7.02 DRYING

Aggregate shall be fed directly to a drier-drum mixer or to a drier at a uniform rate.

Aggregate shall be dried such that, at the time of spreading, the moisture content of the completed asphalt concrete mixture shall not exceed 1.0 percent and the minimum and maximum asphalt concrete mixture temperatures are not exceeded. Moisture content will be determined in conformity with the requirements of California Test 370.

The drier or drier-drum mixer shall be provided with a device that senses the temperature of the material leaving the drier or the drier-drum mixer. The temperature-sensing device shall be accurate to the nearest 5°C. The indicator shall be located and maintained at the point where the proportioning operations are controlled. An automatic continuous recording device shall be provided and used to maintain accurate records of the temperatures during production. Where the plant controller has the capability of capturing production data electronically, including ingredient temperatures, and when this data represents the temperature at the time of production and is captured at intervals of not greater than 5 minutes, this process will be considered to be continuous recording. Captured data shall be retained for the duration of the contract and shall be submitted to the Engineer on request.

The burner used for heating the aggregate shall achieve complete combustion of the fuel.

39-7.03 PROPORTIONING

Proportioning shall be either by hot-feed control or cold-feed control. Hot-feed control and cold-feed control indicate the location of the measuring devices or controls.

The Contractor's mixing equipment shall be equipped with a suitable, safe sampling device that will provide a sample, representative of actual production, of the aggregate being incorporated into the asphalt concrete. The delivery point of samples shall be safe and convenient. When samples are taken from a location above ground level, a means shall be provided for lowering the aggregate samples to the ground.

39-7.03A Proportioning for Batch Mixing

When the Contractor elects to use batch mixing equipment, each aggregate hot storage bin shall be equipped with a sampling device that will provide a sample of the aggregate discharged into the weigh hopper.

Fine material collected in dust control systems, other than centrifugal collectors or knock-out boxes, shall be considered to be supplemental fine aggregate. When supplemental fine aggregate is used, it shall be proportioned by mass.

A sampling device for supplemental fine aggregate shall be installed in each feed line or surge tank preceding the weigh hopper.

39-7.03A(1) Batching Tolerances

Aggregate and asphalt shall be proportioned by mass as follows:

- A. The zero tolerance for aggregate scales shall be 0.5-percent of the total batch mass of the aggregate. The zero tolerance for separate scales for weighing supplemental fine aggregate or asphalt binder shall be 0.05-percent of the total batch mass of the aggregate.
- B. Unless otherwise approved by the Engineer, the indicated mass of material drawn from storage shall not vary from the preselected scale setting as defined by target values of the approved mix design by more than the following percentages of the total batch mass of the aggregate:
 1. Aggregate shall be within one percent, except that when supplemental fine aggregate is used and is weighed cumulatively with the aggregate, the draft of aggregate drawn immediately before the supplemental fine aggregate shall be within 0.5-percent.
 2. Supplemental fine aggregate shall be within 0.5-percent.
 3. Asphalt binder shall be within 0.1-percent.

The asphalt binder shall be measured by a tank scale.

39-7.03A(2) Automatic Controls

Batch proportioning shall be by an automatic plant controller. The proportioning devices shall be automatic to the extent that the only manual operation required for proportioning materials for one batch shall be a single operation of a switch or starter.

Proportioning devices shall be of a type in which materials discharged from the several bins are controlled by gates or by mechanical conveyors. The batching devices shall be so interlocked that no new batch may be started until weigh hoppers are empty, the scales are at zero, and the discharge gates are closed. The means of withdrawal from the bins and of discharge from the weigh box shall be interlocked so that not more than one bin can discharge onto a given scale at one time, and so that the weigh box cannot be tripped until the required quantity from each of the bins has been deposited therein. In addition, automatic proportioning devices shall be interlocked so that the weighing cycle will be interrupted whenever the amount of material drawn from storage varies from the pre-selected amount by more than the tolerances specified in this Section 11-1. Whenever the weighing cycle is interrupted, that specific batch shall not be used in the work unless it can be manually adjusted to meet the specified tolerances based on the total mass of the batch. When partial batches are batched, the interlock tolerances, except the zero tolerance, shall apply to the total mass of aggregate in the partial batch.

Proportioning devices shall be operated so that all mass increments required for a batch are preset at the same time. Controls shall be designed so that these settings may be changed without delay and the order of discharge from the several bins can be changed.

Proportioning controls shall be equipped with the means for inspection of the interlock tolerance settings. Instructions for performing the inspection shall be available at the point of operation.

The necessary means shall be provided to check the mass of various proportioned amounts on a separate vehicle scale located at the plant site.

39-7.03B Proportioning for Continuous Mixing

Asphalt binder shall be introduced into the mixer through a meter conforming to the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications. The asphalt meter shall automatically compensate for changes in the asphalt temperature, unless the meter is the mass flow, coriolis effect, type. The system shall be capable of varying the rate of delivery of binder proportionate with the delivery of aggregate. During a day's run, the temperature of asphalt binder shall not vary more than 30°C. The meter and lines shall be heated and insulated. The binder storage shall be equipped with a device for automatic plant cut-off when the level of binder is lowered sufficiently to expose the pump suction line.

When supplemental fine aggregate is used, it shall be proportioned by a method that uniformly feeds the material within 2 percent of the required amount. Supplemental fine aggregate shall be discharged from the proportioning device directly into the mixer.

The supplemental fine aggregate proportioning system shall function with a degree of accuracy such that, when operated between 30 percent and 100 percent of maximum operating capacity, the average difference between the indicated mass of material delivered and the actual mass delivered shall not exceed one percent of the actual mass for three individual 15-minute runs. For the 3 individual 15-minute runs, the indicated mass of material delivered shall not vary from the actual mass delivered by more than 2 percent of the actual mass.

The fine material collected in dust control systems may be returned to the aggregate production stream without proportioning if returned at a rate commensurate with overall plant production, and if returned at or before the mixer. A return rate of less than 100 percent of the collection rate shall be metered as specified above for supplemental fine aggregate.

The asphalt feeder, each of the aggregate feeders, the supplemental fine aggregate feeder, if used, and the combined aggregate feeder shall be equipped with devices by which the rate of feed can be determined while the plant is in full operation.

The combined aggregate shall be weighed using a belt scale. The belt scale shall be of such accuracy that, when the plant is operating between 30 percent and 100 percent of belt capacity, the average difference between the indicated mass of material delivered and the actual mass delivered shall not exceed one percent of the actual mass for three individual 3-minute runs. For the 3 individual 3-minute runs, the indicated mass of material delivered shall not vary from the actual mass delivered by more than 2 percent of the actual mass.

The actual mass of material delivered for proportioning device calibrations shall be determined by a vehicle scale located at the plant site conforming to the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications. The vehicle scale shall be error checked within 24 hours of checking the plant's proportioning devices. The plant shall be equipped so that this accuracy check can be made prior to the first production operation for a project and at other times when requested by the Engineer.

The belt scale for the combined aggregate, the proportioning devices for supplemental fine aggregate, if used, and the asphalt proportioning meter shall be interlocked so that the rates of feed of the aggregates and asphalt will be adjusted automatically (at all production rates and production rate changes) to maintain the asphalt ratio (kilograms of asphalt per 100 kg of dry aggregate including supplemental fine aggregate, if used) designated in the mix design in conformance with the provisions in Section 39-2.03, "Asphalt Concrete Mixture," of this Section 11-1. The plant shall not be operated unless this automatic system is functioning and in good working condition.

Asphalt meters and aggregate belt scales used for proportioning aggregates and asphalt shall be equipped with rate-of-flow indicators to show the rates of delivery of asphalt and aggregate. Meters and scales shall be equipped with resettable totalizers so that the total amounts of asphalt and aggregate introduced into the asphalt concrete mixture can be determined. Rate-of-flow indicators and totalizers for like materials shall be accurate within one percent when compared directly. The asphalt cement totalizer shall not register when the asphalt metering system is not delivering material to the mixer.

The bin or bins containing the fine aggregate and supplemental fine aggregate, if used, shall be equipped with vibrating units or other equipment that will prevent hang-up of material while the plant is operating. Each belt feeder shall be equipped with a device to monitor the depth of aggregate between the troughing rollers. The device for monitoring depth of aggregate shall automatically shut down the plant whenever the depth of aggregate is less than 70 percent of the target depth. To avoid erroneous shut down by normal fluctuations, a delay between sensing less than 70 percent flow and shutdown of the plant will be permitted, as determined by the Engineer, at the time of the initial California Test 109. A second device shall be located either in the stream of aggregate beyond the belt or where it will monitor movement of the belt by detecting revolutions of the tail pulley on the belt feeder. The device for monitoring no-flow or belt movement, as the case may be, shall stop the plant automatically and immediately when there is no flow. The plant shall not be operated unless both low-flow and no-flow monitoring devices are in good working condition and functioning properly.

For continuous pugmill mixing plants, an aggregate sampling device that will provide a 25-kg to 40-kg sample of the combined aggregate while the plant is in full operation shall be provided in advance of the point where the aggregate enters the mixer.

For drier-drum mixing plants, an aggregate sampling device that will provide a 25-kg to 40-kg sample of the combined aggregate while the plant is in full operation shall be provided in advance of the point where the aggregate enters the drier-drum mixer.

When supplemental fine aggregate is used, a sampling device shall be installed in each feed line or surge tank preceding the proportioning device for the supplemental fine aggregate.

39-7.04 (BLANK)

39-7.05 MIXING

Aggregate, supplemental fine aggregate, and asphalt binder shall be mixed in a batch mixer, continuous mixing pugmill mixer, or continuous mixing drier-drum. The charge in a batch mixer, or the rate of feed to a continuous mixer, shall not exceed that which will permit complete mixing of the material. Dead areas in the mixer, in which the material does not move or is not sufficiently agitated, shall be corrected by a reduction in the volume of material or by other adjustments.

Asphalt binder shall be at a temperature of not less than 120°C nor more than 190°C when added to the aggregate.

The temperature of the aggregate before adding the binder shall not be more than 165°C.

39-7.05A Batch Mixing

When asphalt concrete is produced by batch mixing, the mixer shall be equipped with a sufficient number of paddles of a type and arrangement so as to produce a properly mixed batch.

The binder shall be introduced uniformly into the mixer along the center of the mixer parallel to the mixer shafts, or by pressure spraying. When a pan is used, it shall be equipped with movable vanes in order that the flow of binder may be directed across the width of the pan, as desired. The vanes shall be equipped with a means for quick adjustment, and a positive lock to prevent shifting.

The mixer platform shall be of ample size to provide safe and convenient access to the mixer and other equipment. The mixer housing and weighbox housing shall be equipped with gates of ample size to permit ready sampling of the discharge of aggregate from each of the plant bins and from each feed line or surge tank of supplemental fine aggregate, if used. The Contractor shall provide a sampling device capable of delivering a representative sample of sufficient size to permit the required tests.

The mixer shall be equipped with a timing device that will indicate by a definite audible or visual signal the expiration of the mixing period. The device shall measure the time of mixing within 2 seconds.

The time of mixing a batch shall begin on the charging stroke of the weighhopper dumping mechanism and shall end when discharge is started. Mixing shall continue until a homogeneous asphalt concrete mixture of uniformly distributed and properly coated aggregates of unchanging appearance is produced. The time of mixing shall be not less than 30 seconds.

An interval timer shall control the time of mixing. The interval timer shall be interlocked so that the mixer cannot be discharged until the materials have been mixed for the full amount of time specified.

39-7.05B Continuous Mixing

Continuous mixing plants shall utilize pugmill or drier-drum mixers.

When asphalt concrete is produced by pugmill mixing, the mixer shall be equipped with paddles of a type and arrangement to provide sufficient mixing action and movement to the asphalt concrete mixture to produce properly mixed asphalt concrete. The combined aggregate shall be fed directly from the drier to the mixer at a uniform and controlled rate.

Mixing shall continue until a homogeneous asphalt concrete mixture of thoroughly and uniformly coated aggregates of unchanging appearance is produced at the discharge point from the mixer.

The temperature of the completed asphalt concrete mixture shall not exceed 165°C upon discharge from the mixer.

The mixer shall discharge into a storage silo with a capacity of not less than that specified in Section 39-7.06, "Asphalt Concrete Storage," of this Section 11-1. The Contractor shall provide a means of diverting the flow of asphalt concrete away from the silo to prevent incompletely mixed portions of the asphalt concrete mixture from entering the silo.

39-7.06 ASPHALT CONCRETE STORAGE

When asphalt concrete is stored, it shall be stored only in silos. Asphalt concrete shall not be stockpiled. The minimum quantity of asphalt concrete in a silo during mixing shall be 18 tonnes except for the period immediately following a shut-down of the plant of 2 hours or more. A means shall be provided to indicate that storage in each silo is being maintained as required.

Storage silos shall be equipped with a surge-batcher sized to hold a minimum of 1800 kg of material. A surge-batcher consists of equipment placed at the top of the storage silo that catches the continuous delivery of the completed asphalt concrete mix and changes it to individual batch delivery to prevent the segregation of product ingredients as the completed asphalt concrete mix is placed into storage. The surge-batcher shall be center loading and shall be constructed to prevent material buildup. Rotary chutes shall not be used as surge-batchers.

The surge-batcher shall be independent and distinct from conveyors or chutes used to collect or direct the completed asphalt concrete mixture being discharged into storage silos and shall be the last device to handle the material before it enters the silo. Multiple storage silos shall be served by an individual surge-batcher for each silo. Material handling shall be free of oblique movement between the highest elevation (conveyor outfall) and subsequent placement in the silo. Discharge gates on surge-batchers shall be automatic in operation and shall discharge only after a minimum of 1800 kg of material has been collected and shall close before the last collected material leaves the device. Discharge gate design shall prevent the deflection of material during the opening and closing operation.

Asphalt concrete stored in excess of 18 hours shall not be used in the work. Asphalt concrete mixture containing hardened lumps shall not be used. A storage facility that contained the material with the hardened lumps shall not be used for further storage until the cause of the lumps is corrected.

39-7.07 ASPHALT CONCRETE PLANTS

Plants, including commercial plants, that produce asphalt concrete subject to these specifications shall conform to the provisions in Section 7-1.01F, "Air Pollution Control," of the Standard Specifications, and shall be equipped with a wet-tube dust washer or equal and other devices that will reduce the dust emission to the degree that adjacent property is not damaged. The washer and other equipment shall function efficiently when the plant is in operation.

During production, petroleum products such as diesel fuel and kerosene shall not be used as a release agent on belts, conveyors, hoppers, or hauling equipment.

Plants shall be equipped with an inspection dock constructed so that a quality control technician or inspector standing on the dock can inspect the completed asphalt concrete mixture and take samples, as necessary, from the hauling vehicle before the vehicle leaves the plant site. This inspection dock shall allow the hauling vehicle to pull alongside and shall meet applicable safety requirements of the California Division of Occupational Safety and Health. Haul vehicle drivers shall be instructed to stop at the dock whenever a quality control technician or inspector is on the dock and to remain there until directed to leave by that individual.

39-8 SUBGRADE, PRIME COAT, PAINT BINDER (TACK COAT), AND PAVEMENT REINFORCING FABRIC

39-8.01 SUBGRADE

Immediately prior to applying prime coat or paint binder (tack coat), or immediately prior to placing the asphalt concrete when a prime coat or paint binder (tack coat) is not required, the subgrade to receive asphalt concrete shall conform to the compaction requirement and elevation tolerances specified for the material involved and shall be free of loose or extraneous material. If the asphalt concrete is to be placed on an existing base or pavement that was not constructed as part of the contract, the surface shall be cleaned by sweeping, flushing or other means to remove loose particles of paving, dirt, and other extraneous material immediately before applying the prime coat or paint binder (tack coat).

39-8.02 PRIME COAT AND PAINT BINDER (TACK COAT)

A prime coat of liquid asphalt shall be applied to the areas to be surfaced when there is a contract item for the work or when the work is required in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Prime coat shall be applied only to those areas designated by the Engineer.

Prime coat shall be applied at the approximate total rate of 1.15 L per square meter of surface covered. The exact rate and number of applications will be determined by the Engineer.

Prime coat shall be applied at a temperature conforming to the range of temperatures specified in Section 93-1.03, "Mixing and Applying," of the Standard Specifications for distributor application of the grade of liquid asphalt being used.

A paint binder (tack coat) of asphaltic emulsion shall be furnished and applied in conformance with the provisions in Section 94, "Asphaltic Emulsions," of the Standard Specifications and shall be applied to vertical surfaces of existing pavement, curbs, gutters, and construction joints in the surfacing against which additional material is to be placed, to a pavement to be surfaced, and to other surfaces designated in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Paint binder (tack coat) shall be applied in one application at a rate of from 0.10-L to 0.45-L per square meter of surface covered. The exact rate of application will be determined by the Engineer.

At the Contractor's option, paving asphalt may be used for paint binder (tack coat) instead of asphaltic emulsion. If paving asphalt is used, the grade to be used and the rate of application will be determined by the Engineer. The paving asphalt shall be applied at a temperature of not less than 140°C or more than 175°C.

Prime coat or paint binder (tack coat) shall be applied in advance of placing the surfacing only as far as shall be approved by the Engineer. When asphaltic emulsion is used as a paint binder (tack coat), the asphalt concrete shall not be placed until the asphaltic emulsion has cured.

Immediately in advance of placing asphalt concrete, additional prime coat or paint binder (tack coat) shall be applied as directed by the Engineer to areas where the prime coat or paint binder (tack coat) has been damaged. Loose or extraneous material shall be removed and no additional compensation will be allowed therefor.

39-8.03 PAVEMENT REINFORCING FABRIC

Pavement reinforcing fabric shall be placed on existing pavement to be surfaced or between layers of asphalt concrete when such work is shown on the plans, or specified in "Asphalt Concrete" in Section 10-1, of these special provisions, or ordered by the Engineer.

Before placing the pavement reinforcing fabric, a binder of paving asphalt shall be applied to the surface to receive the pavement reinforcing fabric at an approximate rate of 1.15 L per square meter of surface covered. The exact rate will be determined by the Engineer. The binder shall be applied to a width equal to the width of the fabric mat plus 75 mm on each side.

Before applying binder, large cracks, spalls, and depressions in existing pavement shall be repaired as directed by the Engineer and, if not included in the item, the repair work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

The fabric shall be aligned and placed with no wrinkles that lap. The test for lapping shall be made by gathering together the fabric in a wrinkle. If the height of the doubled portion of extra fabric is 15 mm or more, the fabric shall be cut to remove the wrinkle, then lapped in the direction of paving. Lap in excess of 50 mm shall be removed. Pavement reinforcing fabric shall not be placed in areas of conform tapers where the thickness of the overlying asphalt concrete is 30 mm or less.

If manual laydown methods are used, the fabric shall be unrolled, aligned, and placed in increments of approximately 9 m.

Adjacent borders of the fabric shall be lapped 50 mm to 100 mm. The preceding roll shall be lapped 50 mm to 100 mm over the following roll in the direction of paving at ends of rolls or at a break. At fabric overlays, both the binder and the fabric shall overlap previously placed fabric by the same amount.

Seating of the fabric with rolling equipment after placing will be permitted. Turning of the paving machine and other vehicles shall be gradual and kept to a minimum to avoid damage to the fabric.

A small quantity of asphalt concrete, to be determined by the Engineer, may be spread over the fabric immediately in advance of placing asphalt concrete surfacing in order to prevent fabric from being damaged by construction equipment.

Public traffic shall not be allowed on the bare reinforcing fabric, except that public cross traffic may be allowed to cross the fabric under traffic control after the Contractor has placed a small quantity of asphalt concrete over the fabric.

Care shall be taken to avoid tracking binder material onto the pavement reinforcing fabric or distorting the fabric during seating of the fabric with rolling equipment. If necessary to protect the pavement reinforcing fabric, exposed binder material may be covered lightly with sand.

39-9 SPREADING AND COMPACTING EQUIPMENT

39-9.01 SPREADING EQUIPMENT

Asphalt pavers shall be self-propelled mechanical spreading and finishing equipment provided with a screed or strike-off assembly capable of distributing the material to not less than the full width of a traffic lane unless otherwise approved by the Engineer. Screed action shall include cutting, crowding or other practical action that is effective on the asphalt concrete mixture without tearing, shoving or gouging and that produces a surface texture of uniform appearance. The screed shall be adjustable to the required section and thickness. The screed shall be provided with a suitable full width compacting device. Pavers that leave ridges, indentations or other marks in the surface shall not be used unless the ridges, indentations or marks are eliminated by rolling or prevented by adjustment in the operation.

When end dump haul vehicles are used, the asphalt paver shall operate independently of the vehicle being unloaded or shall be capable of propelling the vehicle being unloaded. The load of the haul vehicle shall be limited to that which will insure satisfactory spreading. While being unloaded, the haul vehicle shall be in contact with the machine and the brakes on the haul vehicle shall not be depended upon to maintain contact between the vehicle and the machine.

No portion of the mass of hauling or loading equipment, other than the connection, shall be supported by the asphalt paver. No vibrations or other motions of the loader that could have a detrimental effect on the riding quality of the completed pavement shall be transmitted to the paver.

When asphalt concrete is placed directly upon asphalt treated permeable base, the asphalt concrete shall be placed in a manner and with equipment that will not disturb or displace the asphalt treated permeable base.

39-9.02 COMPACTING EQUIPMENT

A sufficient number of rollers shall be provided to obtain the specified compaction and surface finish required by this Section 11-1. Rollers shall be sized to achieve the required results.

Rollers shall be equipped with pads and water systems that prevent sticking of the asphalt concrete mixtures to the pneumatic or steel-tired wheels. A parting agent that will not damage the asphalt concrete mixture may be used to aid in preventing the asphalt concrete mixture from sticking to the wheels.

39-10 SPREADING AND COMPACTING

39-10.01 GENERAL REQUIREMENTS

Asphalt concrete shall be handled, spread, and compacted in a manner which is in conformance with this Section 11-1, "Quality Control / Quality Assurance."

Asphalt concrete shall be placed in such a manner that cracking, shoving, and displacement will be avoided.

Type A and Type B asphalt concrete shall be placed only when the ambient temperature is above 10°C.

Asphalt concrete shall not be placed when the underlying layer or surface is frozen or not dry or when weather conditions will prevent proper handling, finishing or compaction of the mixture.

Asphalt concrete shall be spread and compacted in the layers and thicknesses indicated in the following table:

Asphalt Concrete Layers and Thickness

Total Thickness Shown on the Plans*	Number of Layers	Top Layer Thickness (Millimeters)		Next Lower Layer Thickness (Millimeters)		All Other Lower Layers Thickness (Millimeters)	
		Min.	Max.	Min.	Max.	Min.	Max.
75 mm or less	1	----	-----	----	----	----	----
76 through 89 mm	2	35	45	35	45	----	----
90 through 135 mm	2	45	60	45	75	—	—
136 mm or more	**	45	60	45	75	45	120

Notes:

*When pavement reinforcing fabric is shown to be placed between layers of asphalt concrete, the thickness of asphalt concrete above the pavement reinforcing fabric shall be considered to be the "Total Thickness Shown on the Plans" for the purpose of spreading and compacting the asphalt concrete above the pavement reinforcing fabric.

**At least 3 layers if total thickness is more than 135 mm and less than 255 mm. At least 4 layers if total thickness is 255 mm or more.

A layer shall not be placed over a layer that exceeds 75 mm in compacted thickness until the temperature of the layer being covered is less than 70°C at mid-depth unless approved by the Engineer.

Asphalt concrete to be placed on shoulders, and on other areas off the traveled way having a width of 1.50 m or more, shall be spread in the same manner as specified above.

The completed mixture shall be deposited on the roadbed at a uniform quantity per linear meter, as necessary to provide the required compacted thickness without resorting to spotting, picking-up or otherwise shifting the mixture. During transporting, spreading and compacting, petroleum products such as diesel fuel and kerosene shall not be used as a release agent on trucks, spreaders or compactors in contact with the asphalt concrete.

Segregation shall be avoided. Surfacing shall be free from pockets of coarse or fine material. Asphalt concrete containing hardened lumps shall not be used.

Longitudinal joints in the top layer of Type A or Type B asphalt concrete shall correspond with the edges of planned traffic lanes. Longitudinal joints in other layers shall be offset not less than 150 mm alternately each side of the edges of traffic lanes.

Unless otherwise provided herein or approved by the Engineer, the top layer of asphalt concrete for shoulders, tapers, transitions, road connections, private drives, curve widenings, chain control lanes, turnouts, left-turn pockets, and other areas shall not be spread before the top layer of asphalt concrete for the adjoining through lane has been spread and compacted. At locations where the number of lanes is changed, the top layer for the through lanes shall be paved first. When existing pavement is to be surfaced and the specified thickness of asphalt concrete to be spread and compacted on the existing pavement is 75 mm or less, the shoulders or other adjoining areas may be spread simultaneously with the through lane provided the completed surfacing conforms to the requirement of this Section 11-1. Tracks or wheels of spreading equipment shall not be operated on the top layer of asphalt concrete until final compaction has been completed.

At those locations shown on the plans, as specified in "Asphalt Concrete" in Section 10-1, "General," of these special provisions, or as directed by the Engineer, the asphalt concrete shall be tapered or feathered to conform to existing surfacing or to other highway and non-highway facilities.

At locations where the asphalt concrete is to be placed over areas inaccessible to spreading and rolling equipment, the asphalt concrete shall be spread by practical means to obtain the specified results and shall be compacted thoroughly to the required lines, grades, and cross sections by means of pneumatic tampers or by other methods that will produce the same degree of compaction as pneumatic tampers.

39-10.02 PRODUCTION START-UP EVALUATION AND NUCLEAR DENSITY TEST STRIPS

The Contractor shall demonstrate that the proposed asphalt concrete mixture is being produced and placed on the roadway in conformance with this Section 11-1, "Quality Control / Quality Assurance." The production start-up evaluation shall demonstrate that the aggregates and asphalt concrete mixture conform to the requirements of Table 39-3, "Asphalt Concrete Mixture Requirements," and of Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1 when produced using the plant proposed for this project. The nuclear density test strip serves to provide the Contractor with a location to develop a correlation between cores taken from the test strip and the Contractor's and Engineer's nuclear density gage readings taken from the same locations on the test strip and for the Contractor to demonstrate the ability to achieve a minimum of 96 percent relative compaction.

Production start-up evaluation and the nuclear density test strip may be constructed separately or at the same time to serve both purposes. Asphalt concrete used in the nuclear density test strip shall be representative of the asphalt concrete that shall be placed in the project.

Should the test results or testing program fail to meet these criteria, production will be suspended and the Contractor shall resolve the problem in conformance with the provisions in Section 39-6, "Dispute Resolution," of this Section 11-1.

Attention is directed to longitudinal and transverse construction joint requirements specified in "Asphalt Concrete" in Section 10-1, "General," of these special provisions.

Test data used for the production start up evaluation and the nuclear gage test strips shall not be included with the test data used for acceptance of the work in conformance with the provisions in Section 39-11, "Acceptance of Work," of this Section 11-1.

A production start-up evaluation and a nuclear density test strip shall be used when production of asphalt concrete has been resumed following a suspension of production due to unsatisfactory material quality as specified in Section 39-4.04, "Contractor Process Control," Section 39-4.05, "Contractor Quality Control," and Section 39-11.02A, "General" of this Section 11-1.

39-10.02A Production Start-Up Evaluation

Before or on the first day of asphalt concrete production, the Contractor shall produce a trial quantity of between 250 tonnes and 500 tonnes of asphalt concrete to demonstrate that asphalt concrete produced for this project conforms to the quality characteristics of this Section 11-1. The location of the production start-up evaluation shall be approved by the Engineer.

Asphalt concrete shall be produced by production procedures intended for the entire project. Production of asphalt concrete shall stop after placement of the trial quantity of asphalt concrete. Asphalt concrete production and placement may resume after the quality characteristics of the asphalt concrete mixture have been tested and found to be in conformance with the quality requirements of this Section 11-1.

The Contractor shall randomly obtain 3 aggregate samples from the plant and 3 asphalt concrete mixture samples from the mat behind the paver. Each sample from the plant shall be split into 4 portions; each sample from the mat shall be split into 4 portions. One portion of each sample shall be tested by the Contractor and one portion of each sample shall be provided to the Engineer for testing. The remaining portions shall be delivered to the Engineer and stored for dispute resolution should the test results not conform to this Section 11-1. The Contractor and the Engineer shall evaluate the samples for conformance to the requirements for sand equivalent, stability, percent air voids, and the quality characteristics designated in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. The percent air voids of the asphalt concrete mixture shall be within ± 1.0 percent of the percent air voids designated in the Contractor's mix design.

The trial quantity of asphalt concrete will be accepted if:

- A. Not more than 3 of the test results from the combined 6 test results from the Contractor's and Engineer's samples for quality characteristics indexed 2, 3, 4, and 5 in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1 are outside the specified limits.
- B. Not more than one of the test results from the combined 6 test results from the Contractor's and the Engineer's samples for sand equivalent, stability, percent air voids or critical start-up characteristics designated in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1 are outside the specified limits.

If the test results from the combined 6 test results fail to meet the conditions above, corrective action shall be taken, and a new trial quantity of asphalt concrete shall be placed and evaluated in conformance with the provisions in this section to demonstrate conformance. If the test results from the combined 6 test results fail to meet the requirements above, then the trial quantity of asphalt concrete will be rejected.

The testing program will be considered adequate only if the average of the Contractor's test results and the average of the Engineer's test results for sand equivalent, stability, percent air voids, and the quality characteristics designated in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1 are within the allowable testing difference designated in Table 39-6, "Allowable Testing Difference," of this Section 11-1.

The Contractor shall not proceed to regular production until the requirements of this Section 39-10.02A, "Production Start-Up Evaluation" have been met. At the request of the Contractor, the Engineer may elect to leave the asphalt concrete which does not meet the requirements of this Section 39-10.02A in place if mitigation at the Contractor's expense can be agreed to. If this quantity of asphalt concrete is left in place, the Contractor will be paid 75 percent of the contract price paid per tonne for asphalt concrete.

The Contractor shall establish a correlation factor for stability of cured versus uncured briquettes. From a single split sample of asphalt concrete, 6 briquettes shall be fabricated. Three of the 6 briquettes shall be cured for 15 hours in conformance with the requirements of California Test 366 and 3 briquettes shall not be cured. The difference between the average stability value determined for the cured and the uncured specimens shall be considered the correlation factor, and shall be applied to stability values determined on uncured samples throughout the life of the project. The correlation factor may range from zero to 4. If the correlation factor is less than zero, a factor of zero shall be applied. If the factor is greater than 4, the correlation factor shall be approved by the Engineer.

39-10.02B Nuclear Density Test Strip

On the first day of placement of each layer of asphalt concrete the Contractor shall place a test strip in conformance with the requirements of California Test 375. The purpose of the test strip is to determine a correlation between cores taken from the test strip and the nuclear density gage readings taken at the core locations and to demonstrate that the asphalt concrete can be placed and compacted to the standards of this Section 11-1, "Quality Control / Quality Assurance." Asphalt concrete used in the nuclear density test strip shall be representative of the asphalt concrete that shall be placed in the project. The location for the nuclear density test strip shall be approved by the Engineer.

The Contractor shall place nuclear density test strips until conditions of the test method and this Section 11-1 have been met. The requirements of this section and the test method shall apply for the correlation of each gage that is used to determine relative compaction for this project. Relative compaction results will not be accepted if they have been determined using a nuclear gage that has not been correlated using a test strip.

Asphalt concrete in test strips may be left in place under the following conditions:

- A. If the relative compaction for the test strip is determined to be 96 percent or greater, the Contractor will be paid at the contract price per tonne of asphalt concrete.
- B. If the relative compaction for the test strip is determined to be less than 96 percent but greater than 93 percent, the Contractor will be paid at 75 percent of the contract price per tonne of asphalt concrete. A new test strip will be required, and mitigation measures shall be at Contractor's expense.

Asphalt concrete in test strips will be rejected when the relative compaction for the test strip is below 93 percent. Production and placement shall not begin until the Contractor has demonstrated the ability to achieve 96 percent relative compaction in conformance with this Section 11-1.

39-10.03 SPREADING

Layers shall be spread with an asphalt paver, unless otherwise specified or approved by the Engineer. Asphalt pavers shall be operated in such a manner as to insure continuous and uniform movement of the paver.

In advance of spreading asphalt concrete over an existing base, surfacing or bridge deck, if there is a contract item for asphalt concrete (leveling) or if ordered by the Engineer, asphalt concrete shall be spread by mechanical means that will produce a uniform smoothness and texture. Asphalt concrete (leveling) shall include, but not be limited to, the filling and leveling of irregularities and ruts. Asphalt concrete used to change the cross slope or profile of an existing surface shall not be considered as asphalt concrete (leveling).

Paint binder (tack coat) shall be applied to each layer in advance of spreading the next layer.

Before placing the top layer adjacent to cold transverse construction joints, the joints shall be trimmed to a vertical face on a neat line. Transverse joints shall be tested with a 3.6-m ± 0.06-m straightedge and shall be cut back for surface smoothness as required in conformance with Section 39-10.04, "Compacting," of this Section 11-1. Connections to existing surfacing shall be feathered to conform to the requirements for smoothness. Longitudinal joints shall be trimmed to a vertical face and on a neat line if the edges of the previously laid surfacing are, in the opinion of the Engineer, in such a condition that the quality of the completed joint will be affected.

39-10.04 COMPACTING

Compacting equipment shall conform to the provisions in Section 39-9.02, "Compacting Equipment," of this Section 11-1, "Quality Control / Quality Assurance."

Rolling shall commence at the lower edge and shall progress toward the highest portion. When compacting layers that exceed 75 mm in compacted thickness, rolling shall commence at the center and shall progress outwards.

Asphalt concrete shall be compacted to a relative compaction of not less than 96 percent and shall be finished to the lines, grades, and cross sections shown on the plans. In-place density of asphalt concrete will be determined prior to opening the pavement to public traffic. No rolling will be permitted after the asphalt concrete temperature is below 60°C.

Asphalt concrete placed in dig outs, as a leveling course, for slope correction, for detours not included in the finished roadway prism, in areas where in the judgment of the Engineer compaction or compaction measurement by conventional methods is impeded or on the uppermost lift of shoulders with rumble strips shall be compacted by a method approved by the Engineer.

Relative compaction shall be determined in conformance with the requirements of California Test 375 except that only a nuclear gauge with thin lift capability shall be used for asphalt concrete layer of 30 mm to 59 mm in thickness. Laboratory specimens shall be compacted in conformance with the requirements of California Test 304. Test locations will be established for asphalt concrete areas to be tested, as specified in California Test 375. If the Contractor compacts the asphalt concrete in any form or quantity after sites for testing have been chosen in conformance with the requirements of California Test 375 or after California Test 375 has begun, the quality control tester shall choose a new set of random numbers for locating test sites.

Upon completion of rolling operations, if ordered by the Engineer, the asphalt concrete shall be cooled by applying water. Applying water shall conform to the provisions in Section 17, "Watering," of the Standard Specifications.

The completed surfacing shall be thoroughly compacted, smooth, and free from ruts, humps, depressions, or irregularities. Ridges, indentations or other objectionable marks left in the surface of the asphalt concrete by blading or other equipment shall be eliminated by rolling or other suitable means. The use of equipment that leaves ridges, indentations or other objectionable marks in the asphalt concrete shall be discontinued.

When a straightedge 3.6 m ± 0.06 m long is laid on the finished surface and parallel with the centerline, the surface shall not vary more than 3-mm from the lower edge of the straightedge. The transverse slope of the finished surface shall be uniform to a degree such that no depressions greater than 6 mm are present when tested with a straightedge 3.6 m ± 0.06-m long in a direction transverse to the centerline and extending from edge to edge of a 3.6-m traffic lane.

Pavement within 15 m of a structure or approach slab shall conform to the smoothness tolerances specified in Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications.

39-11 ACCEPTANCE OF WORK

39-11.01 GENERAL

The Engineer shall select the procedure used to determine the quantities of asphalt concrete for acceptance and payment determination in conformance with the provisions of this Section 11-1, "Quality Control / Quality Assurance."

Quality control test results that have been verified shall form the basis for statistical evaluation of the work in conformance with Section 39-11.02, "Statistical Evaluation and Determination of Pay Factor," of this Section 11-1. The quality requirements on which statistical evaluation will be based are specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1.

Work determined to be in conformance with the provisions of this Section 11-1 will be accepted and paid for at the contract price per tonne for asphalt concrete and may be subject to compensation adjustment in conformance with Section 39-11.02C, "Pay Factor Determination and Compensation Adjustment," of this Section 11-1.

Work that is not in compliance with the provisions of this Section 11-1 may be rejected by the Engineer and shall be removed and replaced at the Contractor's expense.

When there are fewer than 5 verified quality control tests, the work will be accepted or rejected based on whether the individual test results meet the quality requirements specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Section 39-11.02, "Statistical Evaluation and Pay Factor Determination," of this Section 11-1 shall not apply.

Aggregates, asphalt binder, and asphalt concrete mixtures that do not conform to this Section 11-1 shall not be used.

The Engineer may reject a quantity of material that is determined to be defective based on visual inspection or noncompliance with the provisions of this Section 11-1.

39-11.02 STATISTICAL EVALUATION AND DETERMINATION OF PAY FACTOR

Statistical evaluation of the work shall be used to verify the Contractor's quality control test results to determine compliance with this Section 11-1, "Quality Control / Quality Assurance."

39-11.02A General

The quality characteristics to be evaluated and the specification limits are specified in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. Asphalt content, aggregate gradation (600-µm and 75-µm sieves), and relative compaction shall be considered for purposes of this Section 11-1 to be critical quality characteristics.

A lot represents the total quantity of asphalt concrete placed. More than one lot will occur if changes in the target values, material sources or mix design are requested by the Contractor and made in conformance with this Section 11-1 or if production of asphalt concrete is suspended due to unsatisfactory performance. However, asphalt concrete placed in dig outs, as a leveling course, for slope correction, for detours not to be included in the finished roadway prism, in areas where in the judgment of the Engineer compaction or compaction measurement by conventional methods is impeded or on the uppermost lift of shoulders with rumble strips shall be considered as a separate lot from other asphalt concrete. In addition, a new lot may be designated by the Engineer if the production and placement have been suspended for longer than 30 days due to seasonal suspension of phases of work.

A minimum of 5 samples shall be required to perform a statistical evaluation. The maximum obtainable pay factor with the 5 samples shall be 1.01. A minimum of 8 samples shall be required to obtain a pay factor of 1.05. If the sampling frequencies and quantity of work would otherwise result in fewer than 8 samples, the Contractor may submit a written request to increase the sampling frequency to provide a minimum of 8 samples. The request shall be included in the Quality Control Plan.

The lot will be accepted and a final pay factor determined when the Contractor's sampling, inspection, and test results are completed, have been submitted and evaluated, and the Engineer has visually inspected the pavement. Quality control test results shall be verified using the *t*-test in conformance with the provisions of Section 39-5.03, "Verification," of this Section 11-1 before the results will be used in considering the acceptance of asphalt concrete.

If the current composite pay factor of a lot is greater than 0.90, the lot will be accepted, provided the lowest single pay factor is not within the reject portion of Table 39-8, "Pay Factors," of this Section 11-1. If the lowest single pay factor is within the reject portion of Table 39-8, "Pay Factors," of this Section 11-1, the lot will be rejected. Rejected asphalt concrete shall be removed from the project site at the Contractor's expense.

If the current composite pay factor of a lot is less than 0.90, production of asphalt concrete shall be terminated and corrective action taken. Upon approval of the Engineer, up to 1000 tonnes of asphalt concrete may be placed to demonstrate that the asphalt concrete is once again in conformance with this Section 11-1. Production of asphalt concrete shall not start until the Engineer has received test results confirming conformance with this Section 11-1. A new lot will be established when production resumes.

If a pay factor for a critical quality characteristic designated in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1 is less than 0.90 for the lot or is within the rejection range for the last 5 tests, production of asphalt concrete shall be terminated and corrective action taken. Upon approval of the Engineer, up to 1000 tonnes of asphalt concrete may be placed to demonstrate that the asphalt concrete is once again in conformance with this Section 11-1. Production of asphalt concrete shall not start until the Engineer has received test results confirming conformance with this Section 11-1. A new lot will be established when production resumes.

Defective asphalt concrete may be voluntarily removed and replaced with new asphalt concrete to avoid a low pay factor. New material will be sampled, tested, and evaluated in conformance with this Section 11-1.

39-11.02B Statistical Evaluation

The Variability-Unknown/Standard Deviation Method will be used to determine the estimated percentage of the lot that is outside specification limits. The number of significant figures used in the calculations will be in conformance with the requirements of AASHTO Designation R-11, Absolute Method.

The estimated percentage of work that is outside of the specification limits for each quality characteristic will be determined as follows:

1. Calculate the arithmetic mean (\bar{X}) of the test values;

$$\bar{X} = \frac{\sum x}{n}$$

where:

$\sum x$ = summation of individual test values
 n = total number of test values

2. Calculate the standard deviation (s);

$$s = \sqrt{\frac{\sum (x^2) - (\sum x)^2}{n(n-1)}}$$

where:

$\sum (x^2)$ = summation of the squares of individual test values
 $(\sum x)^2$ = summation of the individual test values squared
 n = total number of test values

3. Calculate the upper quality index (Q_u);

$$Q_u = \frac{USL - \bar{X}}{s}$$

where:

USL = upper specification limit
 s = standard deviation
 \bar{X} = arithmetic mean

(Note: The USL is equal to the upper specification limit or the target value plus the production tolerance.)

- Calculate the lower quality index (Q_L);

$$Q_L = \frac{\bar{X} - LSL}{s}$$

where:

LSL = lower specification limit or target value minus production tolerance
 s = standard deviation
 \bar{X} = arithmetic mean

- From Table 39-7, "Estimated Percent of Work Outside Specification Limits," of this Section 11-1, determine P_U ;

where:

P_U = the estimated percentage of work outside the USL.
 ($P_U = 0$, when USL is not specified.)

- From Table 39-7, "Estimated Percent of Work Outside Specification Limits," of this Section 11-1, determine P_L ;

where:

P_L = the estimated percentage of work outside the LSL.
 ($P_L = 0$, when LSL is not specified.)

- Calculate the total estimated percentage of work outside the USL and LSL, Percent Defective;

$$\text{Percent Defective} = P_U + P_L$$

where:

P_U = the estimated percentage of work outside the USL
 P_L = the estimated percentage of work outside the LSL

- Repeat Steps 1 through 7 for each quality characteristic listed for acceptance.

39-11.02C Pay Factor Determination and Compensation Adjustment

The pay factor and compensation adjustment for a lot will be determined as follows:

- From Table 39-8, "Pay Factors," of this Section 11-1, determine the pay factor for each quality characteristic, (PF_{QC}), using the total number of test result values and the total estimated percentage outside the specification limits ($P_U + P_L$) from Step 7 in Section 39-11.02B, "Statistical Evaluation," of this Section 11-1.
- The pay factor for the lot is a composite of single pay factors determined for each quality characteristic designated in Table 39-9, "Minimum Quality Control Requirements," of this Section 11-1. The following formula is used:

$$PF_C = \sum_{i=1}^8 w_i PF_{QC_i}$$

where:

PF_C = the composite pay factor for the lot,
 PF_{QC} = the pay factor for the individual quality characteristic,
 w = the weighting factor listed in Table 39-9, and
 i = the quality characteristic index number in Table 39-9.

- Payment to the Contractor for the lot of asphalt concrete will be subject to a compensation adjustment. The Compensation Adjustment Factor (CAF) will be determined as follows:

$$CAF = PF_C - 1$$

4. The amount of the compensation adjustment will be calculated as the product of:

- a. the Compensation Adjustment Factor (CAF)
- b. the total tonnes represented in the lot, and
- c. the contract price paid per tonne for the item of asphalt concrete involved.

If the compensation adjustment is a negative value, the compensation adjustment will be deducted from moneys due, or that may become due, the Contractor under the contract. If the compensation adjustment is a positive value, the compensation adjustment will be added to moneys due, or that may become due, the Contractor under the contract.

Table 39-7.—ESTIMATED PERCENT OF WORK OUTSIDE SPECIFICATION LIMITS

P _U and/or P _L	Sample Size (n)												
	5	6	7	8	9	10-11	12-14	15-17	18-22	23-29	30-42	43-66	>66
Upper Quality Index Q _U or Lower Quality Index Q _L													
0	1.72	1.88	1.99	2.07	2.13	2.20	2.28	2.34	2.39	2.44	2.48	2.51	2.56
1	1.64	1.75	1.82	1.88	1.91	1.96	2.01	2.04	2.07	2.09	2.12	2.14	2.16
2	1.58	1.66	1.72	1.75	1.78	1.81	1.84	1.87	1.89	1.91	1.93	1.94	1.95
3	1.52	1.59	1.63	1.66	1.68	1.71	1.73	1.75	1.76	1.78	1.79	1.80	1.81
4	1.47	1.52	1.56	1.58	1.60	1.62	1.64	1.65	1.66	1.67	1.68	1.69	1.70
5	1.42	1.47	1.49	1.51	1.52	1.54	1.55	1.56	1.57	1.58	1.59	1.59	1.60
6	1.38	1.41	1.43	1.45	1.46	1.47	1.48	1.49	1.50	1.50	1.51	1.51	1.52
7	1.33	1.36	1.38	1.39	1.40	1.41	1.41	1.42	1.43	1.43	1.44	1.44	1.44
8	1.29	1.31	1.33	1.33	1.34	1.35	1.35	1.36	1.36	1.37	1.37	1.37	1.38
9	1.25	1.27	1.28	1.28	1.29	1.29	1.30	1.30	1.30	1.31	1.31	1.31	1.31
10	1.21	1.23	1.23	1.24	1.24	1.24	1.25	1.25	1.25	1.25	1.25	1.26	1.26
11	1.18	1.18	1.19	1.19	1.19	1.19	1.20	1.20	1.20	1.20	1.20	1.20	1.20
12	1.14	1.14	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15
13	1.10	1.10	1.10	1.10	1.10	1.10	1.11	1.11	1.11	1.11	1.11	1.11	1.11
14	1.07	1.07	1.07	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
15	1.03	1.03	1.03	1.03	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02
16	1.00	0.99	0.99	0.99	0.99	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
17	0.97	0.96	0.95	0.95	0.95	0.95	0.94	0.94	0.94	0.94	0.94	0.94	0.94
18	0.93	0.92	0.92	0.92	0.91	0.91	0.91	0.91	0.90	0.90	0.90	0.90	0.90
19	0.90	0.89	0.88	0.88	0.88	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87
20	0.87	0.86	0.85	0.85	0.84	0.84	0.84	0.83	0.83	0.83	0.83	0.83	0.83
21	0.84	0.82	0.82	0.81	0.81	0.81	0.80	0.80	0.80	0.80	0.80	0.80	0.79
22	0.81	0.79	0.79	0.78	0.78	0.77	0.77	0.77	0.76	0.76	0.76	0.76	0.76
23	0.77	0.76	0.75	0.75	0.74	0.74	0.74	0.73	0.73	0.73	0.73	0.73	0.73
24	0.74	0.73	0.72	0.72	0.71	0.71	0.70	0.70	0.70	0.70	0.70	0.70	0.70
25	0.71	0.70	0.69	0.69	0.68	0.68	0.67	0.67	0.67	0.67	0.67	0.67	0.66

Table continues below

Table 39-7 (cont.).—ESTIMATED PERCENT OF WORK OUTSIDE SPECIFICATION LIMITS

P _U and/or P _L	Sample Size (n)												
	5	6	7	8	9	10-11	12-14	15-17	18-22	23-29	30-42	43-66	>66
Upper Quality Index Q _U or Lower Quality Index Q _L													
26	0.68	0.67	0.67	0.65	0.65	0.65	0.64	0.64	0.64	0.64	0.64	0.64	0.63
27	0.65	0.64	0.63	0.62	0.62	0.62	0.61	0.61	0.61	0.61	0.61	0.61	0.60
28	0.62	0.61	0.60	0.59	0.59	0.59	0.58	0.58	0.58	0.58	0.58	0.58	0.57
29	0.59	0.58	0.57	0.57	0.56	0.56	0.55	0.55	0.55	0.55	0.55	0.55	0.54
30	0.56	0.55	0.54	0.54	0.53	0.53	0.52	0.52	0.52	0.52	0.52	0.52	0.52
31	0.53	0.52	0.51	0.51	0.50	0.50	0.50	0.49	0.49	0.49	0.49	0.49	0.49
32	0.50	0.49	0.48	0.48	0.48	0.47	0.47	0.47	0.46	0.46	0.46	0.46	0.46
33	0.47	0.48	0.45	0.45	0.45	0.44	0.44	0.44	0.44	0.43	0.43	0.43	0.43
34	0.45	0.43	0.43	0.42	0.42	0.42	0.41	0.41	0.41	0.41	0.41	0.41	0.40
35	0.42	0.40	0.40	0.39	0.39	0.39	0.38	0.38	0.38	0.38	0.38	0.38	0.38
36	0.39	0.38	0.37	0.37	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36
37	0.36	0.35	0.34	0.34	0.34	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.32
38	0.33	0.32	0.32	0.31	0.31	0.31	0.30	0.30	0.30	0.30	0.30	0.30	0.30
39	0.30	0.30	0.29	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28
40	0.28	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25
41	0.25	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23
42	0.23	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20
43	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18
44	0.16	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15
45	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13
46	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10
47	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08
48	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05
49	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03
50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Notes:

1. If the value of Q_U or Q_L does not correspond to a value in the table, use the next lower value.
2. If Q_U or Q_L are negative values, P_U or P_L is equal to 100 minus the table value for P_U or P_L.

Table 39-8.—PAY FACTOR

Pay Factor	Sample Size (n)												
	5	6	7	8	9	10-11	12-14	15-17	18-22	23-29	30-42	43-66	>66
	Maximum Allowable Percent of Work Outside Specification Limits for A Given Pay Factor ($P_U + P_L$)												
1.05			0	0	0	0	0	0	0	0	0	0	0
1.04			0	1	3	5	4	4	4	3	3	3	3
1.03		0	2	4	6	8	7	7	6	5	5	4	4
1.02		1	3	6	9	11	10	9	8	7	7	6	6
1.01	0	2	5	8	11	13	12	11	10	9	8	8	7
1.00	22	20	18	17	16	15	14	13	12	11	10	9	8
0.99	24	22	20	19	18	17	16	15	14	13	11	10	9
0.98	26	24	22	21	20	19	18	16	15	14	13	12	10
0.97	28	26	24	23	22	21	19	18	17	16	14	13	12
0.96	30	28	26	25	24	22	21	19	18	17	16	14	13
0.95	32	29	28	26	25	24	22	21	20	18	17	16	14
0.94	33	31	29	28	27	25	24	22	21	20	18	17	15
0.93	35	33	31	29	28	27	25	24	22	21	20	18	16
0.92	37	34	32	31	30	28	27	25	24	22	21	19	18
0.91	38	36	34	32	31	30	28	26	25	24	22	21	19
0.90	39	37	35	34	33	31	29	28	26	25	23	22	20
0.89	41	38	37	35	34	32	31	29	28	26	25	23	21
0.88	42	40	38	36	35	34	32	30	29	27	26	24	22
0.87	43	41	39	38	37	35	33	32	30	29	27	25	23
0.86	45	42	41	39	38	36	34	33	31	30	28	26	24
0.85	46	44	42	40	39	38	36	34	33	31	29	28	25
0.84	47	45	43	42	40	39	37	35	34	32	30	29	27
0.83	49	46	44	43	42	40	38	36	35	33	31	30	28
0.82	50	47	46	44	43	41	39	38	36	34	33	31	29
0.81	51	49	47	45	44	42	41	39	37	36	34	32	30
0.80	52	50	48	46	45	44	42	40	38	37	35	33	31
0.79	54	51	49	48	46	45	43	41	39	38	36	34	32
0.78	55	52	50	49	48	46	44	42	41	39	37	35	33
0.77	56	54	52	50	49	47	45	43	42	40	38	36	34
0.76	57	55	53	51	50	48	46	44	43	41	39	37	35
0.75	58	56	54	52	51	49	47	46	44	42	40	38	36
Reject	60	57	55	53	52	51	48	47	45	43	41	40	37
	61	58	56	55	53	52	50	48	46	44	43	41	38
	62	59	57	56	54	53	51	49	47	45	44	42	39
	63	61	58	57	55	54	52	50	48	47	45	43	40
	64	62	60	58	57	55	53	51	49	48	46	44	41
Reject Values Greater Than Those Shown Above													

Notes:

1. To obtain a pay factor when the estimated percent outside specification limits from Table 39-7, "Estimated Percent of Work Outside Specification Limits," does not correspond to a value in the table, use the next larger value.
2. The maximum obtainable pay factor is 1.05 (with a minimum of 8 test values).

Table 39-9.—MINIMUM QUALITY CONTROL REQUIREMENTS

Index (i)	Quality Characteristic	Specification Limits	Weighting Factor (w)	California Test	Minimum Sampling and Testing Frequency	Point of Sampling
1	Asphalt Content ^{2,3}	TV ± 0.5%	0.30	379 or 382	One sample per 500 tonnes or part thereof Not less than one sample per day	Mat behind paver
2	Gradation 19 or 12.5 mm ⁴	TV ± 5	0.01	202	One sample per 500 tonnes or part thereof	Batch Plant - from hot bins
3	9.5 mm	TV ± 6	0.01		Not less than one sample per day	Drum Plant - from cold feed
4	4.75 mm	TV ± 7	0.05			
5	2.36 mm	TV ± 5	0.05			
6	600 µm ^{2,3}	TV ± 4	0.08			
7	75 µm ²	TV ± 2	0.10			
8	Relative Compaction ²	96%	0.40	375 ⁵	One sample per 500 tonnes or part thereof Not less than one test per day	Finished mat after final rolling
	Test Maximum Density			375	Per Test Method	Mat behind the paver
9	Mix Moisture Content	1%		370	One sample per 1000 tonnes or part thereof Not less than one sample per day	
	Asphalt and Mix Temperature	120°C to 190°C (Asphalt) 165°C (Mix)			Continuous using an automated recording device	Plant

Notes:

1. TV = Target Value from contractor's proposed mix design.
2. Depending on aggregate gradation specified.
3. Quality characteristics 1, 6, 7, and 8 are defined as critical quality characteristics in the verification testing process.
4. Quality characteristics 1, 6, and 7 are defined as critical start-up characteristics in the Production Start-Up Evaluation.
5. California Test 375, Part 3, Section B, "Testing Frequency," is revised to change 450 tonnes to 500 tonnes and 45 tonnes to 50 tonnes.

39-12 MEASUREMENT AND PAYMENT

39-12.01 MEASUREMENT

Asphalt concrete will be measured by mass. The quantity to be paid for will be the combined mass of the mixture for the various types of asphalt concrete, as designated in the Engineer's Estimate.

The mass of the materials will be determined in conformance with the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications.

Quantities of paving asphalt, liquid asphalt, and asphaltic emulsion to be paid for as contract items of work will be determined in conformance with the methods provided in Section 92, "Asphalts," Section 93, "Liquid Asphalts," or Section 94, "Asphaltic Emulsions," of the Standard Specifications, as the case may be.

When recorded batch masses are printed automatically, these masses may be used for determining pay quantities provided the following requirements are complied with:

- A. Total aggregate and supplemental fine aggregate mass per batch shall be printed. When supplemental fine aggregate is weighed cumulatively with the aggregate, the total batch mass of aggregate shall include the supplemental fine aggregate.
- B. The total bitumen mass per batch shall be printed.
- C. Zero-tolerance mass shall be printed prior to weighing the first batch and after weighing the last batch of each truckload.
- D. The time, date, mix number, load number, and truck identification shall be correlated with the load slip.
- E. A copy of the recorded batch masses shall be certified by a licensed weighmaster and submitted to the Engineer.

Pavement reinforcing fabric will be measured and paid for by the square meter for the actual pavement area covered.

39-12.02 PAYMENT

Asphalt concrete placed in the work, unless otherwise specified, will be paid for at the contract price per tonne for asphalt concrete of the types designated in the Engineer's Estimate.

Compensation adjustment for asphalt concrete will be in conformance with Section 39-11.02C, "Pay Factor Determination and Compensation Adjustment," of this Section 11-1, "Quality Control / Quality Assurance."

When there is a contract item for asphalt concrete (leveling), quantities of asphalt concrete placed for leveling will be paid for at the contract price per tonne for asphalt concrete (leveling). When there is no contract item for asphalt concrete (leveling), and leveling is ordered by the Engineer, asphalt concrete so used will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

For asphalt concrete placed in dig outs, as a leveling course, for slope correction, for detours not included in the finished roadway prism, in areas where in the judgment of the Engineer compaction or compaction measurement by conventional methods is impeded or on the uppermost lift of shoulders with rumble strips the relative compaction provisions of Section 39-11.02, "Statistical Evaluation and Determination of Pay Factor," of this Section 11-1, shall not apply. In the computation of the composite pay factor (PF_c) for the lot composed of this asphalt concrete, an individual pay factor of 1.0 for the relative compaction (PF_{QC8}) shall be used.

Full compensation for the Contractor's Quality Control Plan, including furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in developing, implementing, modifying, and fulfilling the requirements of the Quality Control Plan shall be considered as included in the contract price paid per tonne for asphalt concrete of the types designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

Full compensation for Contractor sampling, testing, inspection, testing facilities, and preparation and submission of results shall be considered as included in the contract price paid per tonne for asphalt concrete of the types designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

Quantities of pavement reinforcing fabric placed and paving asphalt applied as a binder for the pavement reinforcing fabric will be paid for at the contract price per square meter for pavement reinforcing fabric and per tonne for paving asphalt (binder-pavement reinforcing fabric). Full compensation for furnishing and spreading sand to cover exposed binder material, if necessary, shall be considered as included in the contract price paid per tonne for paving asphalt (binder-pavement reinforcing fabric) and no separate payment will be made therefor.

Small quantities of asphalt concrete placed on pavement reinforcing fabric to prevent the fabric from being displaced by construction equipment or to allow public traffic to cross over the fabric shall be considered as part of the layer of asphalt concrete to be placed over the fabric and will be measured and paid for by the tonne as asphalt concrete of the types designated in the Engineer's Estimate.

When there is a contract item for liquid asphalt (prime coat), the quantity of prime coat will be paid for at the contract price per tonne for the designated grade of liquid asphalt (prime coat). When there is no contract item for liquid asphalt (prime coat) and the special provisions require the application of a prime coat, full compensation for furnishing and applying the prime coat shall be considered as included in the contract price paid per tonne for asphalt concrete of the types designated in the Engineer's Estimate and no separate payment will be made therefor.

When there is a contract item for asphaltic emulsion (paint binder), the quantity of asphaltic emulsion or paving asphalt used as paint binder (tack coat) will be paid for at the contract price per tonne for asphaltic emulsion (paint binder). When there is no contract item for asphaltic emulsion (paint binder), full compensation for furnishing and applying paint binder (tack coat) shall be considered as included in the contract price paid per tonne for asphalt concrete of the types designated in the Engineer's Estimate and no separate payment will be made therefor.

Fog seal coat will be paid for as provided in Section 37-1, "Seal Coats," of the Standard Specifications.

No adjustment of compensation will be made for an increase or decrease in the quantities of paint binder (tack coat) or fog seal coat required, regardless of the reason for such increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to the items of paint binder or fog seal coat.

The above contract prices and payments shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in placing asphalt concrete, complete in place, as shown on the plans, as specified in this Section 11-1, "Quality Control / Quality Assurance," and "Asphalt Concrete" in Section 10-1, "General," of these special provisions, and as directed by the Engineer.

SECTION 11-2. PORTLAND CEMENT CONCRETE

11-2.01 GENERAL

Portland cement concrete shall conform to the provisions in this Section 11-2, "Portland Cement Concrete," and the section entitled "Portland Cement Concrete" in Section 8, "Materials," of these special provisions. Section 90, "Portland Cement Concrete," of the Standard Specifications is deleted. Section 90, "Portland Cement Concrete," of the Standard Specifications is amended to read as follows.

SECTION 90: PORTLAND CEMENT CONCRETE

90-1 GENERAL

90-1.01 DESCRIPTION

- Portland cement concrete shall be composed of cementitious material, fine aggregate, coarse aggregate, admixtures if used, and water, proportioned and mixed as specified in these specifications.

- The Contractor shall determine the mix proportions for all concrete except pavement concrete. The Engineer will determine the mix proportions for pavement concrete. Concrete for which the mix proportions are determined either by the Contractor or the Engineer shall conform to the requirements of this Section 90.

- Unless otherwise specified, cementitious material shall be a combination of cement and mineral admixture. Cementitious material shall be either:

1. "Type IP (MS) Modified" cement; or
2. A combination of "Type II Modified" portland cement and mineral admixture; or
3. A combination of Type V portland cement and mineral admixture.

- Type III portland cement shall be used only as allowed in the special provisions or with the approval of the Engineer.

- Class 1 concrete shall contain not less than 400 kg of cementitious material per cubic meter.
- Class 2 concrete shall contain not less than 350 kg of cementitious material per cubic meter.
- Class 3 concrete shall contain not less than 300 kg of cementitious material per cubic meter.
- Class 4 concrete shall contain not less than 250 kg of cementitious material per cubic meter.
- Minor concrete shall contain not less than 325 kg of cementitious material per cubic meter unless otherwise specified in these specifications or the special provisions.

- Unless otherwise designated on the plans or specified in these specifications or the special provisions, the amount of cementitious material used per cubic meter of concrete in structures or portions of structures shall conform to the following:

Use	Cementitious Material Content (kg/m ³)
Concrete designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min., 475 max.
Roof sections of exposed top box culverts	400 min., 475 max.
Other portions of structures	350 min., 475 max.
Concrete not designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min.
Roof sections of exposed top box culverts	400 min.
Prestressed members	400 min.
Seal courses	400 min.
Other portions of structures	350 min.
Concrete for precast members	350 min., 550 max.

- Whenever the 28-day compressive strength shown on the plans is greater than 25 MPa, the concrete shall be designated by compressive strength. If the plans show a 28-day compressive strength that is 28 MPa or greater, an additional 14 days will be allowed to obtain the specified strength. The 28-day compressive strengths shown on the plans that are 25 MPa or less are shown for design information only and are not a requirement for acceptance of the concrete.
 - Concrete designated by compressive strength shall be proportioned such that the concrete will attain the strength shown on the plans or specified in the special provisions.
 - Before using concrete for which the mix proportions have been determined by the Contractor, or in advance of revising those mix proportions, the Contractor shall submit in writing to the Engineer a copy of the mix design.
 - Compliance with cementitious material content requirements will be verified in conformance with procedures described in California Test 518 for cement content. For testing purposes, mineral admixture shall be considered to be cement. Batch proportions shall be adjusted as necessary to produce concrete having the specified cementitious material content.
 - If any concrete has a cementitious material, portland cement, or mineral admixture content that is less than the minimum required, the concrete shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State \$0.55 for each kilogram of cementitious material, portland cement, or mineral admixture that is less than the minimum required. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract. The deductions will not be made unless the difference between the contents required and those actually provided exceeds the batching tolerances permitted by Section 90-5, "Proportioning." No deductions will be made based on the results of California Test 518.
 - The requirements of the preceding paragraph shall not apply to minor concrete or commercial quality concrete.

90-2 MATERIALS

90-2.01 CEMENT

- Unless otherwise specified, cement shall be either "Type IP (MS) Modified" cement, "Type II Modified" portland cement or Type V portland cement.
 - "Type IP (MS) Modified" cement shall conform to the requirements for Type IP (MS) cement in ASTM Designation: C 595, and shall be comprised of an intimate and uniform blend of Type II cement and not more than 35 percent by mass of mineral admixture. The type and minimum amount of mineral admixture used in the manufacture of "Type IP (MS) Modified" cement shall be in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."
 - "Type II Modified" portland cement shall conform to the requirements for Type II portland cement in ASTM Designation: C 150.

- In addition, "Type IP (MS) Modified" cement and "Type II Modified" portland cement shall conform to the following requirements:

- A. The cement shall not contain more than 0.60 percent by mass of alkalis, calculated as the percentage of Na₂O plus 0.658 times the percentage of K₂O, when determined by either direct intensity flame photometry or by the atomic absorption method. The instrument and procedure used shall be qualified as to precision and accuracy in conformance with the requirements in ASTM Designation: C 114;
- B. The autoclave expansion shall not exceed 0.50 percent; and
- C. Mortar, containing the cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not expand in water more than 0.010 percent and shall not contract in air more than 0.048 percent, except that when cement is to be used for precast prestressed concrete piling, precast prestressed concrete members, or steam cured concrete products, the mortar shall not contract in air more than 0.053 percent.

- Type III and Type V portland cements shall conform to the requirements in ASTM Designation: C 150 and the additional requirements listed above for "Type II Modified" portland cement, except that when tested in conformance with California Test 527, mortar containing Type III portland cement shall not contract in air more than 0.075 percent.

- Cement used in the manufacture of cast-in-place concrete for exposed surfaces of like elements of a structure shall be from the same cement mill.

- Cement shall be protected from exposure to moisture until used. Sacked cement shall be piled to permit access for tally, inspection, and identification of each shipment.

- Adequate facilities shall be provided to assure that cement meeting the provisions specified in this Section 90-2.01 shall be kept separate from other cement in order to prevent any but the specified cement from entering the work. Safe and suitable facilities for sampling cement shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper, in conformance with California Test 125.

- If cement is used prior to sampling and testing as provided in Section 6-1.07, "Certificates of Compliance," and the cement is delivered directly to the site of the work, the Certificate of Compliance shall be signed by the cement manufacturer or supplier of the cement. If the cement is used in ready-mixed concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.

- Cement furnished without a Certificate of Compliance shall not be used in the work until the Engineer has had sufficient time to make appropriate tests and has approved the cement for use.

90-2.02 AGGREGATES

- Aggregates shall be free from deleterious coatings, clay balls, roots, bark, sticks, rags, and other extraneous material.
- Natural aggregates shall be thoroughly and uniformly washed before use.

- The Contractor, at the Contractor's expense, shall provide safe and suitable facilities, including necessary splitting devices for obtaining samples of aggregates, in conformance with California Test 125.

- Aggregates shall be of such character that it will be possible to produce workable concrete within the limits of water content provided in Section 90-6.06, "Amount of Water and Penetration."

- Aggregates shall have not more than 10 percent loss when tested for soundness in conformance with the requirements in California Test 214. The soundness requirement for fine aggregate will be waived, provided that the durability index, D_f , of the fine aggregate is 60, or greater, when tested for durability in conformance with California Test 229.

- If the results of any one or more of the Cleanness Value, Sand Equivalent, or aggregate grading tests do not meet the requirements specified for "Operating Range" but all meet the "Contract Compliance" requirements, the placement of concrete shall be suspended at the completion of the current pour until tests or other information indicate that the next material to be used in the work will comply with the requirements specified for "Operating Range."

- If the results of either or both the Cleanness Value and coarse aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete that is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State \$4.60 per cubic meter for paving concrete and \$7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

- If the results of either or both the Sand Equivalent and fine aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete which is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State \$4.60 per cubic meter for paving concrete and \$7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

- The 2 preceding paragraphs apply individually to the "Contract Compliance" requirements for coarse aggregate and fine aggregate. When both coarse aggregate and fine aggregate do not conform to the "Contract Compliance" requirements, both paragraphs shall apply. The payments specified in those paragraphs shall be in addition to any payments made in conformance with the provisions in Section 90-1.01, "Description."

- No single Cleanness Value, Sand Equivalent or aggregate grading test shall represent more than 250 m³ of concrete or one day's pour, whichever is smaller.

- Aggregates specified for freeze-thaw resistance shall pass the freezing and thawing test, California Test 528.

- The Contractor shall notify the Engineer of the proposed source of freeze-thaw resistant concrete aggregates at least 4 months before intended use. Should the Contractor later propose a different source of concrete aggregates, the Contractor shall again notify the Engineer at least 4 months before intended use. Blending of fine or coarse aggregates from untested sources with acceptable aggregates will not be permitted. Provisions for the time of submission of samples as provided in Section 40-1.015, "Cement Content," are superseded by the foregoing.

- Concurrently with notification of proposed sources of freeze-thaw resistant concrete aggregates, the Contractor shall furnish samples in the quantity ordered by the Engineer. The samples shall be secured under the direct supervision of the Engineer. Samples from existing stockpiles of processed aggregate shall be taken from washed materials and shall be visibly damp. Samples from materials in place in a material source shall be taken at depths from the existing surface that will ensure the presence of the full quantity of ground water. Excavations for the purpose of securing samples shall be made to the full depth of intended source operations. Samples shall be protected against loss of contained water until they are delivered to the Engineer.

- The Engineer will waive the above freeze-thaw test and the 4-month advance notice, required in this Section, provided aggregates are to be obtained from sources that have previously passed this test and test results are currently applicable.

- No extension of contract time will be allowed for the time required to perform the freezing and thawing test.

- When the source of an aggregate is changed, except for pavement concrete, the Contractor shall adjust the mix proportions and submit in writing to the Engineer a copy of the mix design before using the aggregates. When the source of an aggregate is changed for pavement concrete, the Engineer shall be allowed sufficient time to adjust the mix, and the aggregates shall not be used until necessary adjustments are made.

90-2.02A Coarse Aggregate

- Coarse aggregate shall consist of gravel, crushed gravel, crushed rock, crushed air-cooled iron blast furnace slag or combinations thereof. Crushed air-cooled blast furnace slag shall not be used in reinforced or prestressed concrete.

- Coarse aggregate shall conform to the following quality requirements:

Tests	California Test	Requirements
Loss in Los Angeles Rattler (after 500 revolutions)	211	45% max.
Cleanness Value		
Operating Range	227	75 min.
Contract Compliance	227	71 min.

- In lieu of the above Cleanness Value requirements, a Cleanness Value "Operating Range" limit of 71, minimum, and a Cleanness Value "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the coarse aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

1. coarse aggregate sampled at the completion of processing at the aggregate production plant had a Cleanness Value of not less than 82 when tested by California Test 227; and
2. prequalification tests performed in conformance with the requirements in California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.02B Fine Aggregate

- Fine aggregate shall consist of natural sand, manufactured sand produced from larger aggregate or a combination thereof. Manufactured sand shall be well graded.
- Fine aggregate shall conform to the following quality requirements:

Test	California Test	Requirements
Organic Impurities	213	Satisfactory ^a
Mortar Strengths Relative to Ottawa Sand	515	95%, min.
Sand Equivalent:		
Operating Range	217	75, min.
Contract Compliance	217	71, min.

a Fine aggregate developing a color darker than the reference standard color solution may be accepted if it is determined by the Engineer, from mortar strength tests, that a darker color is acceptable.

- In lieu of the above Sand Equivalent requirements, a Sand Equivalent "Operating Range" limit of 71 minimum and a Sand Equivalent "Contract Compliance" limit of 68 minimum will be used to determine the acceptability of the fine aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

1. fine aggregate sampled at the completion of processing at the aggregate production plant had a Sand Equivalent value of not less than 82 when tested by California Test 217; and
2. prequalification tests performed in conformance with California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.03 WATER

- In conventionally reinforced concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 1000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1300 parts per million of sulfates as SO₄, when tested in conformance with California Test 417. In prestressed concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 650 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1300 parts per million of sulfates as SO₄, when tested in conformance with California Test 417. In no case shall the water contain an amount of impurities that will cause either: 1) a change in the setting time of cement of more than 25 percent when tested in conformance with the requirements in ASTM Designation: C 191 or ASTM Designation: C 266 or 2) a reduction in the compressive strength of mortar at 14 days of more than 5 percent, when tested in conformance with the requirements in ASTM Designation: C 109, when compared to the results obtained with distilled water or deionized water, tested in conformance with the requirements in ASTM Designation: C 109.

- In non-reinforced concrete work, the water for curing, for washing aggregates and for mixing shall be free from oil and shall not contain more than 2000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, or more than 1500 parts per million of sulfates as SO₄, when tested in conformance with California Test 417.

- In addition to the above provisions, water for curing concrete shall not contain impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.

- Water reclaimed from mixer wash-out operations may be used in mixing concrete. The water shall not contain coloring agents or more than 300 parts per million of alkalis (Na₂O + 0.658 K₂O) as determined on the filtrate. The specific gravity of the water shall not exceed 1.03 and shall not vary more than ±0.010 during a day's operations.

90-2.04 ADMIXTURE MATERIALS

- Admixture materials shall conform to the requirements in the following ASTM Designations:

- A. Chemical Admixtures—ASTM Designation: C 494.
- B. Air-entraining Admixtures—ASTM Designation: C 260.
- C. Calcium Chloride—ASTM Designation: D 98.

D. Mineral Admixtures—Coal fly ash; raw or calcined natural pozzolan as specified in ASTM Designation: C618; silica fume conforming to the requirements in ASTM Designation: C1240, with reduction of mortar expansion of 80 percent, minimum, using the cement from the proposed mix design.

- Unless otherwise specified in the special provisions, mineral admixtures shall be used in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."

90-3 AGGREGATE GRADINGS

90-3.01 GENERAL

- Before beginning concrete work, the Contractor shall submit in writing to the Engineer the gradation of the primary aggregate nominal sizes that the Contractor proposes to furnish. If a primary coarse aggregate or the fine aggregate is separated into 2 or more sizes, the proposed gradation shall consist of the gradation for each individual size, and the proposed proportions of each individual size, combined mathematically to indicate one proposed gradation. The proposed gradation shall meet the grading requirements shown in the table in this section, and shall show the percentage passing each of the sieve sizes used in determining the end result.

- The Engineer may waive, in writing, the gradation requirements in this Section 90-3.01 and in Sections 90-3.02, "Coarse Aggregate Grading," 90-3.03, "Fine Aggregate Grading," and 90-3.04, "Combined Aggregate Gradings," if, in the Engineer's opinion, furnishing the gradation is not necessary for the type or amount of concrete work to be constructed.

- Gradations proposed by the Contractor shall be within the following percentage passing limits:

Primary Aggregate Nominal Size	Sieve Size	Limits of Proposed Gradation
37.5-mm x 19-mm	25-mm	19 - 41
25-mm x 4.75-mm	19-mm	52 - 85
25-mm x 4.75-mm	9.5-mm	15 - 38
12.5-mm x 4.75-mm	9.5-mm	40 - 78
9.5-mm x 2.36-mm	9.5-mm	50 - 85
Fine Aggregate	1.18-mm	55 - 75
Fine Aggregate	600-µm	34 - 46
Fine Aggregate	300-µm	16 - 29

- Should the Contractor change the source of supply, the Contractor shall submit in writing to the Engineer the new gradations before their intended use.

90-3.02 COARSE AGGREGATE GRADING

- The grading requirements for coarse aggregates are shown in the following table for each size of coarse aggregate:

Sieve Sizes	Percentage Passing Primary Aggregate Nominal Sizes							
	37.5-mm x 19-mm		25-mm x 4.75-mm		12.5-mm x 4.75-mm		9.5-mm x 2.36-mm	
	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance
50-mm	100	100	—	—	—	—	—	—
37.5-mm	88-100	85-100	100	100	—	—	—	—
25-mm	x ± 18	X ± 25	88-100	86-100	—	—	—	—
19-mm	0-17	0-20	X ± 15	X ± 22	100	100	—	—
12.5-mm	—	—	—	—	82-100	80-100	100	100
9.5-mm	0-7	0-9	X ± 15	X ± 22	X ± 15	X ± 22	X ± 15	X ± 20
4.75-mm	—	—	0-16	0-18	0-15	0-18	0-25	0-28
2.36-mm	—	—	0-6	0-7	0-6	0-7	0-6	0-7

- In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

- Coarse aggregate for the 37.5-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," shall be furnished in 2 or more primary aggregate nominal sizes. Each primary aggregate nominal size may be separated into 2 sizes and stored separately, provided that the combined material conforms to the grading requirements for that particular primary aggregate nominal size.
- When the 25-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," is to be used, the coarse aggregate may be separated into 2 sizes and stored separately, provided that the combined material shall conform to the grading requirements for the 25-mm x 4.75-mm primary aggregate nominal size.

90-3.03 FINE AGGREGATE GRADING

- Fine aggregate shall be graded within the following limits:

Sieve Sizes	Percentage Passing	
	Operating Range	Contract Compliance
9.5-mm	100	100
4.75-mm	95-100	93-100
2.36-mm	65-95	61-99
1.18-mm	X ± 10	X ± 13
600-µm	X ± 9	X ± 12
300-µm	X ± 6	X ± 9
150-µm	2-12	1-15
75-µm	0-8	0-10

- In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."
- In addition to the above required grading analysis, the distribution of the fine aggregate sizes shall be such that the difference between the total percentage passing the 1.18-mm sieve and the total percentage passing the 600-µm sieve shall be between 10 and 40, and the difference between the percentage passing the 600-µm and 300-µm sieves shall be between 10 and 40.
- Fine aggregate may be separated into 2 or more sizes and stored separately, provided that the combined material conforms to the grading requirements specified in this Section 90-3.03.

90-3.04 COMBINED AGGREGATE GRADINGS

- Combined aggregate grading limits shall be used only for the design of concrete mixes. Concrete mixes shall be designed so that aggregates are combined in proportions that shall produce a mixture within the grading limits for combined aggregates as specified herein. Within these limitations, the relative proportions shall be as ordered by the Engineer, except as otherwise provided in Section 90-1.01, "Description."
- The combined aggregate grading used in portland cement concrete pavement shall be the 37.5-mm, maximum grading.

- The combined aggregate grading used in concrete for structures and other concrete items, except when specified otherwise in these specifications or the special provisions, shall be either the 37.5-mm, maximum grading, or the 25-mm, maximum grading, at the option of the Contractor.

Grading Limits of Combined Aggregates

Sieve Sizes	Percentage Passing			
	37.5-mm Max.	25-mm Max.	12.5-mm Max.	9.5-mm Max.
50-mm	100	—	—	—
37.5-mm	90-100	100	—	—
25-mm	50-86	90-100	—	—
19-mm	45-75	55-100	100	—
12.5-mm	—	—	90-100	100
9.5-mm	38-55	45-75	55-86	50 - 100
4.75-mm	30-45	35-60	45-63	45 - 63
2.36-mm	23-38	27-45	35-49	35 - 49
1.18-mm	17-33	20-35	25-37	25 - 37
600-µm	10-22	12-25	15-25	15 - 25
300-µm	4-10	5-15	5-15	5 - 15
150-µm	1-6	1-8	1-8	1 - 8
75-µm	0-3	0-4	0-4	0 - 4

- Changes from one grading to another shall not be made during the progress of the work unless permitted by the Engineer.

90-4 ADMIXTURES

90-4.01 GENERAL

- Admixtures used in portland cement concrete shall conform to and be used in conformance with the provisions in this Section 90-4 and the special provisions. Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option as provided herein.
 - Chemical admixtures and air-entraining admixtures containing chlorides as Cl in excess of one percent by mass of admixture, as determined by California Test 415, shall not be used in prestressed or reinforced concrete.
 - Calcium chloride shall not be used in concrete containing steel reinforcement or other embedded metals.
 - Mineral admixture used in concrete for exposed surfaces of like elements of a structure shall be from the same source and of the same percentage.
 - Admixtures shall be uniform in properties throughout their use in the work. Should it be found that an admixture as furnished is not uniform in properties, its use shall be discontinued.
 - If more than one admixture is used, the admixtures shall be compatible with each other so that the desirable effects of all admixtures used will be realized.

90-4.02 MATERIALS

- Admixture materials shall conform to the provisions in Section 90-2.04, "Admixture Materials."

90-4.03 ADMIXTURE APPROVAL

- No admixture brand shall be used in the work unless it is on the Department's current list of approved brands for the type of admixture involved.
 - Admixture brands will be considered for addition to the approved list if the manufacturer of the admixture submits to the Transportation Laboratory a sample of the admixture accompanied by certified test results demonstrating that the admixture complies with the requirements in the appropriate ASTM Designation and these specifications. The sample shall be sufficient to permit performance of all required tests. Approval of admixture brands will be dependent upon a determination as to compliance with the requirements, based on the certified test results submitted, together with tests the Department may elect to perform.

- When the Contractor proposes to use an admixture of a brand and type on the current list of approved admixture brands, the Contractor shall furnish a Certificate of Compliance from the manufacturer, as provided in Section 6-1.07, "Certificates of Compliance," certifying that the admixture furnished is the same as that previously approved. If a previously approved admixture is not accompanied by a Certificate of Compliance, the admixture shall not be used in the work until the Engineer has had sufficient time to make the appropriate tests and has approved the admixture for use. The Engineer may take samples for testing at any time, whether or not the admixture has been accompanied by a Certificate of Compliance.

- If a mineral admixture is delivered directly to the site of the work, the Certificate of Compliance shall be signed by the manufacturer or supplier of the mineral admixture. If the mineral admixture is used in ready-mix concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.

90-4.04 REQUIRED USE OF CHEMICAL ADMIXTURES AND CALCIUM CHLORIDE

- When the use of a chemical admixture or calcium chloride is specified or ordered by the Engineer, the admixture shall be used at the dosage specified or ordered, except that if no dosage is specified or ordered, the admixture shall be used at the dosage normally recommended by the manufacturer of the admixture.

- Calcium chloride shall be dispensed in liquid, flake, or pellet form. Calcium chloride dispensed in liquid form shall conform to the provisions for dispensing liquid admixtures in Section 90-4.10, "Proportioning and Dispensing Liquid Admixtures."

90-4.05 OPTIONAL USE OF CHEMICAL ADMIXTURES

- The Contractor will be permitted to use Type A or F, water-reducing; Type B, retarding; or Type D or G, water-reducing and retarding admixtures as described in ASTM Designation: C 494 to conserve cementitious material or to facilitate any concrete construction application subject to the following conditions:

- A. When a water-reducing admixture or a water-reducing and retarding admixture is used, the cementitious material content specified or ordered may be reduced by a maximum of 5 percent by mass, except that the resultant cementitious material content shall be not less than 300 kilograms per cubic meter; and

- B. When a reduction in cementitious material content is made, the dosage of admixture used shall be the dosage used in determining approval of the admixture.

- Unless otherwise specified, a Type C accelerating chemical admixture conforming to the requirements in ASTM Designation: C 494, may be used in portland cement concrete. Inclusion in the mix design submitted for approval will not be required provided that the admixture is added to counteract changing conditions that contribute to delayed setting of the portland cement concrete, and the use or change in dosage of the admixture is approved in writing by the Engineer.

90-4.06 REQUIRED USE OF AIR-ENTRAINING ADMIXTURES

- When air-entrainment is specified or ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce a concrete having the specified air content as determined by California Test 504.

90-4.07 OPTIONAL USE OF AIR-ENTRAINING ADMIXTURES

- When air-entrainment has not been specified or ordered by the Engineer, the Contractor will be permitted to use an air-entraining admixture to facilitate the use of any construction procedure or equipment provided that the average air content, as determined by California Test 504, of 3 successive tests does not exceed 4 percent, and no single test value exceeds 5.5 percent. If the Contractor elects to use an air-entraining admixture in concrete for pavement, the Contractor shall so indicate at the time the Contractor designates the source of aggregate as provided in Section 40-1.015, "Cement Content."

90-4.08 REQUIRED USE OF MINERAL ADMIXTURES

- Unless otherwise specified, mineral admixture shall be combined with cement to make cementitious material.

- The calcium oxide content of mineral admixtures shall not exceed 10 percent and the available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 618.

- The amounts of cement and mineral admixture used in cementitious material shall be sufficient to satisfy the minimum cementitious material content requirements specified in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," and shall conform to the following:

- A. The minimum amount of cement shall not be less than 75 percent by mass of the specified minimum cementitious material content;
- B. The minimum amount of mineral admixture to be combined with cement shall be determined using one of the following criteria:
 1. When the calcium oxide content of a mineral admixture is equal to or less than 2 percent by mass, the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix;
 2. When the calcium oxide content of a mineral admixture is greater than 2 percent, the amount of mineral admixture shall not be less than 25 percent by mass of the total amount of cementitious material to be used in the mix;
 3. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," is used, the amount of mineral admixture shall not be less than 10 percent by mass of the total amount of cementitious material to be used in the mix
- C. The total amount of mineral admixture shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. Where Section 90-1.01, "Description," specifies a maximum cementitious content in kilograms per cubic meter, the total mass of cement and mineral admixture per cubic meter shall not exceed the specified maximum cementitious material content.

90-4.09 BLANK

90-4.10 PROPORTIONING AND DISPENSING LIQUID ADMIXTURES

- Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers for liquid admixtures shall have sufficient capacity to measure at one time the prescribed quantity required for each batch of concrete. Each dispenser shall include a graduated measuring unit into which liquid admixtures are measured to within ± 5 percent of the prescribed quantity for each batch. Dispensers shall be located and maintained so that the graduations can be accurately read from the point at which proportioning operations are controlled to permit a visual check of batching accuracy prior to discharge. Each measuring unit shall be clearly marked for the type and quantity of admixture.

- Each liquid admixture dispensing system shall be equipped with a sampling device consisting of a valve located in a safe and readily accessible position such that a sample of the admixture may be withdrawn slowly by the Engineer.

- If more than one liquid admixture is used in the concrete mix, each liquid admixture shall have a separate measuring unit and shall be dispensed by injecting equipment located in such a manner that the admixtures are not mixed at high concentrations and do not interfere with the effectiveness of each other. When air-entraining admixtures are used in conjunction with other liquid admixtures, the air-entraining admixture shall be the first to be incorporated into the mix.

- When automatic proportioning devices are required for concrete pavement, dispensers for liquid admixtures shall operate automatically with the batching control equipment. The dispensers shall be equipped with an automatic warning system in good operating condition that will provide a visible or audible signal at the point at which proportioning operations are controlled when the quantity of admixture measured for each batch of concrete varies from the preselected dosage by more than 5 percent, or when the entire contents of the measuring unit are not emptied from the dispenser into each batch of concrete.

- Unless liquid admixtures are added to premeasured water for the batch, their discharge into the batch shall be arranged to flow into the stream of water so that the admixtures are well dispersed throughout the batch, except that air-entraining admixtures may be dispensed directly into moist sand in the batching bins provided that adequate control of the air content of the concrete can be maintained.

- Liquid admixtures requiring dosages greater than 2.5 L/m^3 shall be considered to be water when determining the total amount of free water as specified in Section 90-6.06, "Amount of Water and Penetration."

- Special admixtures, such as "high range" water reducers that may contribute to a high rate of slump loss, shall be measured and dispensed as recommended by the admixture manufacturer and as approved by the Engineer.

90-4.11 STORAGE, PROPORTIONING, AND DISPENSING OF MINERAL ADMIXTURES

- Mineral admixtures shall be protected from exposure to moisture until used. Sacked material shall be piled to permit access for tally, inspection and identification for each shipment.
- Adequate facilities shall be provided to assure that mineral admixtures meeting the specified requirements are kept separate from other mineral admixtures in order to prevent any but the specified mineral admixtures from entering the work. Safe and suitable facilities for sampling mineral admixtures shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper.
- Mineral admixtures shall be incorporated into concrete using equipment conforming to the requirements for cement weigh hoppers, and charging and discharging mechanisms in ASTM Designation: C 94, in Section 90-5.03, "Proportioning," and in this Section 90-4.11.
- When concrete is completely mixed in stationary paving mixers, the mineral admixture shall be weighed in a separate weigh hopper conforming to the provisions for cement weigh hoppers and charging and discharging mechanisms in Section 90-5.03A, "Proportioning for Pavement," and the mineral admixture and cement shall be introduced simultaneously into the mixer proportionately with the aggregate. If the mineral admixture is not weighed in a separate weigh hopper, the Contractor shall provide certification that the stationary mixer is capable of mixing the cement, admixture, aggregates and water uniformly prior to discharge. Certification shall contain the following:

- A. Test results for 2 compressive strength test cylinders of concrete taken within the first one-third and 2 compressive strength test cylinders of concrete taken within the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;"
- B. Calculations demonstrating that the difference in the averages of 2 compressive strengths taken in the first one-third is no greater than 7.5 percent different than the averages of 2 compressive strengths taken in the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;" and
- C. The mixer rotation speed and time of mixing prior to discharge that are required to produce a mix that meets the requirements above.

90-5 PROPORTIONING

90-5.01 STORAGE OF AGGREGATES

- Aggregates shall be stored or stockpiled in such a manner that separation of coarse and fine particles of each size shall be avoided and also that the various sizes shall not become intermixed before proportioning.
- Aggregates shall be stored or stockpiled and handled in a manner that shall prevent contamination by foreign materials. In addition, storage of aggregates at batching or mixing facilities that are erected subsequent to the award of the contract and that furnish concrete to the project shall conform to the following:
 - A. Intermingling of the different sizes of aggregates shall be positively prevented. The Contractor shall take the necessary measures to prevent intermingling. The preventive measures may include, but are not necessarily limited to, physical separation of stockpiles or construction of bulkheads of adequate length and height; and
 - B. Contamination of aggregates by contact with the ground shall be positively prevented. The Contractor shall take the necessary measures to prevent contamination. The preventive measures shall include, but are not necessarily limited to, placing aggregates on wooden platforms or on hardened surfaces consisting of portland cement concrete, asphalt concrete, or cement treated material.
- In placing aggregates in storage or in moving the aggregates from storage to the weigh hopper of the batching plant, any method that may cause segregation, degradation, or the combining of materials of different gradings that will result in any size of aggregate at the weigh hopper failing to meet the grading requirements, shall be discontinued. Any method of handling aggregates that results in excessive breakage of particles shall be discontinued. The use of suitable devices to reduce impact of falling aggregates may be required by the Engineer.

90-5.02 PROPORTIONING DEVICES

- Weighing, measuring, or metering devices used for proportioning materials shall conform to the requirements in Section 9-1.01, "Measurement of Quantities," and this Section 90-5.02. In addition, automatic weighing systems shall comply with the requirements for automatic proportioning devices in Section 90-5.03A, "Proportioning for Pavement." Automatic devices shall be automatic to the extent that the only manual operation required for proportioning the aggregates, cement, and mineral admixture for one batch of concrete is a single operation of a switch or starter.

- Proportioning devices shall be tested at the expense of the Contractor as frequently as the Engineer may deem necessary to ensure their accuracy.

- Weighing equipment shall be insulated against vibration or movement of other operating equipment in the plant. When the plant is in operation, the mass of each batch of material shall not vary from the mass designated by the Engineer by more than the tolerances specified herein.

- Equipment for cumulative weighing of aggregate shall have a zero tolerance of ± 0.5 percent of the designated total batch mass of the aggregate. For systems with individual weigh hoppers for the various sizes of aggregate, the zero tolerance shall be ± 0.5 percent of the individual batch mass designated for each size of aggregate. Equipment for cumulative weighing of cement and mineral admixtures shall have a zero tolerance of ± 0.5 percent of the designated total batch mass of the cement and mineral admixture. Equipment for weighing cement or mineral admixture separately shall have a zero tolerance of ± 0.5 percent of their designated individual batch masses. Equipment for measuring water shall have a zero tolerance of ± 0.5 percent of its designated mass or volume.

- The mass indicated for any batch of material shall not vary from the preselected scale setting by more than the following:

- A. Aggregate weighed cumulatively shall be within 1.0 percent of the designated total batch mass of the aggregate. Aggregates weighed individually shall be within 1.5 percent of their respective designated batch masses; and
- B. Cement shall be within 1.0 percent of its designated batch mass. When weighed individually, mineral admixture shall be within 1.0 percent of its designated batch mass. When mineral admixture and cement are permitted to be weighed cumulatively, cement shall be weighed first to within 1.0 percent of its designated batch mass, and the total for cement and mineral admixture shall be within 1.0 percent of the sum of their designated batch masses; and
- C. Water shall be within 1.5 percent of its designated mass or volume.

- Each scale graduation shall be approximately 0.001 of the total capacity of the scale. The capacity of scales for weighing cement, mineral admixture, or cement plus mineral admixture and aggregates shall not exceed that of commercially available scales having single graduations indicating a mass not exceeding the maximum permissible mass variation above, except that no scale shall be required having a capacity of less than 500 kg, with 0.5-kg graduations.

90-5.03 PROPORTIONING

- Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cement, mineral admixture, and water as provided in these specifications. Aggregates shall be proportioned by mass.

- At the time of batching, aggregates shall have been dried or drained sufficiently to result in a stable moisture content such that no visible separation of water from aggregate will take place during transportation from the proportioning plant to the point of mixing. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry mass.

- Should separate supplies of aggregate material of the same size group, but of different moisture content or specific gravity or surface characteristics affecting workability, be available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another.

- Bulk "Type IP (MS) Modified" cement shall be weighed in an individual hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer.

- Bulk cement and mineral admixture may be weighed in separate, individual weigh hoppers or may be weighed in the same weigh hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer. If the cement and mineral admixture are weighed cumulatively, the cement shall be weighed first.

- When cement and mineral admixtures are weighed in separate weigh hoppers, the weigh systems for the proportioning of the aggregate, the cement, and the mineral admixture shall be individual and distinct from all other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and independent material weighing device. The cement and the mineral admixture shall be discharged into the mixer simultaneously with the aggregate.

- The scales and weigh hoppers for bulk weighing cement, mineral admixture, or cement plus mineral admixture shall be separate and distinct from the aggregate weighing equipment.
- For batches with a volume of one cubic meter or more, the batching equipment shall conform to one of the following combinations:

- A. Separate boxes and separate scale and indicator for weighing each size of aggregate.
- B. Single box and scale indicator for all aggregates.
- C. Single box or separate boxes and automatic weighing mechanism for all aggregates.

- In order to check the accuracy of batch masses, the gross mass and tare mass of batch trucks, truck mixers, truck agitators, and non-agitating hauling equipment shall be determined when ordered by the Engineer. The equipment shall be weighed at the Contractor's expense on scales designated by the Engineer.

90-5.03A Proportioning for Pavement

- Aggregates and bulk cement, mineral admixture, and cement plus mineral admixture for use in pavement shall be proportioned by mass by means of automatic proportioning devices of approved type conforming to these specifications.

- The Contractor shall install and maintain in operating condition an electronically actuated moisture meter that will indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched within a sensitivity of 0.5 percent by mass of the fine aggregate.

- The batching of cement, mineral admixture, or cement plus mineral admixture and aggregate shall be interlocked so that a new batch cannot be started until all weigh hoppers are empty, the proportioning devices are within zero tolerance, and the discharge gates are closed. The interlock shall permit no part of the batch to be discharged until all aggregate hoppers and the cement and mineral admixture hoppers or the cement plus mineral admixture hopper are charged with masses that are within the tolerances specified in Section 90-5.02, "Proportioning Devices."

- When interlocks are required for cement and mineral admixture charging mechanisms and cement and mineral admixtures are weighed cumulatively, their charging mechanisms shall be interlocked to prevent the introduction of mineral admixture until the mass of cement in the cement weigh hopper is within the tolerances specified in Section 90-5.02, "Proportioning Devices."

- The discharge gate on the cement and mineral admixture hoppers or the cement plus mineral admixture hopper shall be designed to permit regulating the flow of cement, mineral admixture, or cement plus mineral admixture into the aggregate as directed by the Engineer.

- When separate weigh boxes are used for each size of aggregate, the discharge gates shall permit regulating the flow of each size of aggregate as directed by the Engineer.

- Material discharged from the several bins shall be controlled by gates or by mechanical conveyors. The means of withdrawal from the several bins, and of discharge from the weigh box, shall be interlocked so that not more than one bin can discharge at a time, and so that the weigh box cannot be tripped until the required quantity from each of the several bins has been deposited therein. Should a separate weigh box be used for each size of aggregate, all may be operated and discharged simultaneously.

- When the discharge from the several bins is controlled by gates, each gate shall be actuated automatically so that the required mass is discharged into the weigh box, after which the gate shall automatically close and lock.

- The automatic weighing system shall be designed so that all proportions required may be set on the weighing controller at the same time.

90-6 MIXING AND TRANSPORTING

90-6.01 GENERAL

- Concrete shall be mixed in mechanically operated mixers, except that when permitted by the Engineer, batches not exceeding 0.25 m³ may be mixed by hand methods in conformance with the provisions in Section 90-6.05, "Hand-Mixing."

- Equipment having components made of aluminum or magnesium alloys that would have contact with plastic concrete during mixing, transporting, or pumping of portland cement concrete shall not be used.

- Concrete shall be homogeneous and thoroughly mixed, and there shall be no lumps or evidence of undispersed cement, mineral admixture, or cement plus mineral admixture.

- Uniformity of concrete mixtures will be determined by differences in penetration as determined by California Test 533, or slump as determined by ASTM Designation: C 143, and by variations in the proportion of coarse aggregate as determined by California Test 529.

- When the mix design specifies a penetration value, the difference in penetration, determined by comparing penetration tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed 10 mm. When the mix design specifies a slump value, the difference in slump, determined by comparing slump tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed the values given in the table below. Variation in the proportion of coarse aggregate will be determined by comparing the results of tests of 2 samples of mixed concrete from the same batch or truck mixer load and the difference between the 2 results shall not exceed 100 kg per cubic meter of concrete.

Average Slump	Maximum Permissible Difference
Less than 100-mm	25-mm
100-mm to 150-mm	38-mm
Greater than 150-mm to 225-mm	50-mm

- The Contractor, at the Contractor's expense, shall furnish samples of the freshly mixed concrete and provide satisfactory facilities for obtaining the samples.

90-6.02 MACHINE MIXING

- Concrete mixers may be of the revolving drum or the revolving blade type, and the mixing drum or blades shall be operated uniformly at the mixing speed recommended by the manufacturer. Mixers and agitators that have an accumulation of hard concrete or mortar shall not be used.

- The temperature of mixed concrete, immediately before placing, shall be not less than 10°C or more than 32°C. Aggregates and water shall be heated or cooled as necessary to produce concrete within these temperature limits. Neither aggregates nor mixing water shall be heated to exceed 65°C. If ice is used to cool the concrete, discharge of the mixer will not be permitted until all ice is melted.

- The batch shall be so charged into the mixer that some water will enter in advance of cementitious materials and aggregates. All water shall be in the drum by the end of the first one - fourth of the specified mixing time.

- Cementitious materials shall be batched and charged into the mixer by means that will not result either in loss of cementitious materials due to the effect of wind, in accumulation of cementitious materials on surfaces of conveyors or hoppers, or in other conditions that reduce or vary the required quantity of cementitious material in the concrete mixture.

- Paving and stationary mixers shall be operated with an automatic timing device. The timing device and discharge mechanism shall be interlocked so that during normal operation no part of the batch will be discharged until the specified mixing time has elapsed.

- The total elapsed time between the intermingling of damp aggregates and all cementitious materials and the start of mixing shall not exceed 30 minutes.

- The size of batch shall not exceed the manufacturer's guaranteed capacity.

- When producing concrete for pavement or base, suitable batch counters shall be installed and maintained in good operating condition at jobsite batching plants and stationary mixers. The batch counters shall indicate the exact number of batches proportioned and mixed.

- Concrete shall be mixed and delivered to the jobsite by means of one of the following combinations of operations:

- A. Mixed completely in a stationary mixer and the mixed concrete transported to the point of delivery in truck agitators or in non-agitating hauling equipment (central-mixed concrete).
- B. Mixed partially in a stationary mixer, and the mixing completed in a truck mixer (shrink-mixed concrete).
- C. Mixed completely in a truck mixer (transit-mixed concrete).
- D. Mixed completely in a paving mixer.

- Agitators may be truck mixers operating at agitating speed or truck agitators. Each mixer and agitator shall have attached thereto in a prominent place a metal plate or plates on which is plainly marked the various uses for which the equipment is designed, the manufacturer's guaranteed capacity of the drum or container in terms of the volume of mixed concrete and the speed of rotation of the mixing drum or blades.

- Truck mixers shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified.

- When shrink-mixed concrete is furnished, concrete that has been partially mixed at a central plant shall be transferred to a truck mixer and all requirements for transit-mixed concrete shall apply. No credit in the number of revolutions at mixing speed shall be allowed for partial mixing in a central plant.

90-6.03 TRANSPORTING MIXED CONCRETE

- Mixed concrete may be transported to the delivery point in truck agitators or truck mixers operating at the speed designated by the manufacturer of the equipment as agitating speed, or in non-agitating hauling equipment, provided the consistency and workability of the mixed concrete upon discharge at the delivery point is suitable for adequate placement and consolidation in place, and provided the mixed concrete after hauling to the delivery point conforms to the provisions in Section 90-6.01, "General."
- Truck agitators shall be loaded not to exceed the manufacturer's guaranteed capacity and shall maintain the mixed concrete in a thoroughly mixed and uniform mass during hauling.
- Bodies of non-agitating hauling equipment shall be constructed so that leakage of the concrete mix, or any part thereof, will not occur at any time.
- Concrete hauled in open-top vehicles shall be protected during hauling against rain or against exposure to the sun for more than 20 minutes when the ambient temperature exceeds 24°C.
- No additional mixing water shall be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer. If the Engineer authorizes additional water to be incorporated into the concrete, the drum shall be revolved not less than 30 revolutions at mixing speed after the water is added and before discharge is commenced.
- The rate of discharge of mixed concrete from truck mixer-agitators shall be controlled by the speed of rotation of the drum in the discharge direction with the discharge gate fully open.
- When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be completed within 1.5 hours or before 250 revolutions of the drum or blades, whichever occurs first, after the introduction of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, the time allowed may be less than 1.5 hours.
- When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be completed within one hour after the addition of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.
- Each load of concrete delivered at the jobsite shall be accompanied by a weighmaster certificate showing the mix identification number, non-repeating load number, date and time at which the materials were batched, the total amount of water added to the load, and for transit-mixed concrete, the reading of the revolution counter at the time the truck mixer is charged with cement. This weighmaster certificate shall also show the actual scale masses (kilograms) for the ingredients batched. Theoretical or target batch masses shall not be used as a substitute for actual scale masses.
- Weighmaster certificates shall be provided in printed form, or if approved by the Engineer, the data may be submitted in electronic media. Electronic media shall be presented in a tab-delimited format on a 90 mm diskette with a capacity of at least 1.4 megabytes. Captured data, for the ingredients represented by each batch shall be "line feed, carriage return" (LFCR) and "one line, separate record" with allowances for sufficient fields to satisfy the amount of data required by these specifications.
- The Contractor may furnish a weighmaster certificate accompanied by a separate certificate that lists the actual batch masses or measurements for a load of concrete provided that both certificates are imprinted with the same non-repeating load number that is unique to the contract and delivered to the jobsite with the load.
- Weighmaster certificates furnished by the Contractor shall conform to the provisions in Section 9-1.01, "Measurement of Quantities."

90-6.04 TIME OR AMOUNT OF MIXING

- Mixing of concrete in paving or stationary mixers shall continue for the required mixing time after all ingredients, except water and admixture, if added with the water, are in the mixing compartment of the mixer before any part of the batch is released. Transfer time in multiple drum mixers shall not be counted as part of the required mixing time.
- The required mixing time, in paving or stationary mixers, of concrete used for concrete structures, except minor structures, shall be not less than 90 seconds or more than 5 minutes, except that when directed by the Engineer in writing, the requirements of the following paragraph shall apply.
- The required mixing time, in paving or stationary mixers, except as provided in the preceding paragraph, shall be not less than 50 seconds or more than 5 minutes.
- The minimum required revolutions at the mixing speed for transit-mixed concrete shall not be less than that recommended by the mixer manufacturer, but in no case shall the number of revolutions be less than that required to consistently produce concrete conforming to the provisions for uniformity in Section 90-6.01, "General."

90-6.05 HAND-MIXING

- Hand-mixed concrete shall be made in batches of not more than 0.25 m³ and shall be mixed on a watertight, level platform. The proper amount of coarse aggregate shall be measured in measuring boxes and spread on the platform and the fine aggregate shall be spread on this layer, the 2 layers being not more than 0.3 meters in total depth. On this mixture shall be spread the dry cement and mineral admixture and the whole mass turned no fewer than 2 times dry; then sufficient clean water shall be added, evenly distributed, and the whole mass again turned no fewer than 3 times, not including placing in the carriers or forms.

90-6.06 AMOUNT OF WATER AND PENETRATION

- The amount of water used in concrete mixes shall be regulated so that the penetration of the concrete as determined by California Test 533 or the slump of the concrete as determined by ASTM Designation: C 143 is within the "Nominal" values shown in the following table. When the penetration or slump of the concrete is found to exceed the nominal values listed, the mixture of subsequent batches shall be adjusted to reduce the penetration or slump to a value within the nominal range shown. Batches of concrete with a penetration or slump exceeding the maximum values listed shall not be used in the work. When Type F or Type G chemical admixtures are added to the mix, the penetration requirements shall not apply and the slump shall not exceed 225 mm after the chemical admixtures are added.

Type of Work	Nominal		Maximum	
	Penetration (mm)	Slump (mm)	Penetration (mm)	Slump (mm)
Concrete Pavement	0-25	—	40	—
Non-reinforced concrete facilities	0-35	—	50	—
Reinforced concrete structures				
Sections over 300-mm thick	0-35	—	65	—
Sections 300-mm thick or less	0-50	—	75	—
Concrete placed under water	—	150-200	—	225
Cast-in-place concrete piles	65-90	130-180	100	200

- The amount of free water used in concrete shall not exceed 183 kg/m³, plus 20 kg for each required 100 kg of cementitious material in excess of 325 kg/m³.
- The term free water is defined as the total water in the mixture minus the water absorbed by the aggregates in reaching a saturated surface-dry condition.
- Where there are adverse or difficult conditions that affect the placing of concrete, the above specified penetration and free water content limitations may be exceeded providing the Contractor is granted permission by the Engineer in writing to increase the cementitious material content per cubic meter of concrete. The increase in water and cementitious material shall be at a ratio not to exceed 30 kg of water per added 100 kg of cementitious material per cubic meter. The cost of additional cementitious material and water added under these conditions shall be at the Contractor's expense and no additional compensation will be allowed therefor.
- The equipment for supplying water to the mixer shall be constructed and arranged so that the amount of water added can be measured accurately. Any method of discharging water into the mixer for a batch shall be accurate within 1.5 percent of the quantity of water required to be added to the mix for any position of the mixer. Tanks used to measure water shall be designed so that water cannot enter while water is being discharged into the mixer and discharge into the mixer shall be made rapidly in one operation without dribbling. All equipment shall be arranged so as to permit checking the amount of water delivered by discharging into measured containers.

90-7 CURING CONCRETE

90-7.01 METHODS OF CURING

- Newly placed concrete shall be cured by the methods specified in this Section 90-7.01 and the special provisions.

90-7.01A Water Method

- The concrete shall be kept continuously wet by the application of water for a minimum curing period of 7 days after the concrete has been placed.

- When a curing medium consisting of cotton mats, rugs, carpets, or earth or sand blankets is to be used to retain the moisture, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. The moisture from the nozzle shall not be applied under pressure directly upon the concrete and shall not be allowed to accumulate on the concrete in a quantity sufficient to cause a flow or wash the surface. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing mediums.

- When concrete bridge decks and flat slabs are to be cured without the use of a curing medium, the entire surface of the bridge deck or slab shall be kept damp by the application of water with an atomizing nozzle as specified in the preceding paragraph, until the concrete has set, after which the entire surface of the concrete shall be sprinkled continuously with water for a period of not less than 7 days.

90-7.01B Curing Compound Method

- Surfaces of the concrete that are exposed to the air shall be sprayed uniformly with a curing compound.
- Curing compounds to be used shall be as follows:

1. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B, except the resin type shall be poly-alpha-methylstyrene.
2. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B.
3. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class A.
4. Non-pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class B.
5. Non-pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class A.
6. Non-pigmented curing compound with fugitive dye conforming to the requirements in ASTM Designation: C 309, Type 1-D, Class A.

- The infrared scan for the dried vehicle from curing compound (1) shall match the infrared scan on file at the Transportation Laboratory.

- The loss of water for each type of curing compound, when tested in conformance with the requirements in California Test 534, shall not be more than 0.15-kg/m² in 24 hours or more than 0.45-kg/m² in 72 hours.

- The curing compound to be used will be specified elsewhere in these specifications or in the special provisions.

- When the use of curing compound is required or permitted elsewhere in these specifications or in the special provisions and no specific kind is specified, any of the curing compounds listed above may be used.

- Curing compound shall be applied at a nominal rate of 3.7 m²/L, unless otherwise specified.

- At any point, the application rate shall be within ± 1.2 m²/L of the nominal rate specified, and the average application rate shall be within ± 0.5 m²/L of the nominal rate specified when tested in conformance with the requirements in California Test 535. Runs, sags, thin areas, skips, or holidays in the applied curing compound shall be evidence that the application is not satisfactory.

- Curing compounds shall be applied using power operated spray equipment. The power operated spraying equipment shall be equipped with an operational pressure gage and a means of controlling the pressure. Hand spraying of small and irregular areas that are not reasonably accessible to mechanical spraying equipment, in the opinion of the Engineer, may be permitted.

- The curing compound shall be applied to the concrete following the surface finishing operation, immediately before the moisture sheen disappears from the surface, but before any drying shrinkage or craze cracks begin to appear. In the event of any drying or cracking of the surface, application of water with an atomizing nozzle as specified in Section 90-7.01A, "Water Method," shall be started immediately and shall be continued until application of the compound is resumed or started; however, the compound shall not be applied over any resulting freestanding water. Should the film of compound be damaged from any cause before the expiration of 7 days after the concrete is placed in the case of structures and 72 hours in the case of pavement, the damaged portion shall be repaired immediately with additional compound.

- At the time of use, compounds containing pigments shall be in a thoroughly mixed condition with the pigment uniformly dispersed throughout the vehicle. A paddle shall be used to loosen all settled pigment from the bottom of the container, and a power driven agitator shall be used to disperse the pigment uniformly throughout the vehicle.

- Agitation shall not introduce air or other foreign substance into the curing compound.

- The manufacturer shall include in the curing compound the necessary additives for control of sagging, pigment settling, leveling, de-emulsification, or other requisite qualities of a satisfactory working material. Pigmented curing compounds shall be manufactured so that the pigment does not settle badly, does not cake or thicken in the container, and does not become granular or curdled. Settlement of pigment shall be a thoroughly wetted, soft, mushy mass permitting the complete and easy vertical penetration of a paddle. Settled pigment shall be easily redispersed, with minimum resistance to the sideways manual motion of the paddle across the bottom of the container, to form a smooth uniform product of the proper consistency.

- Curing compounds shall remain sprayable at temperatures above 4°C and shall not be diluted or altered after manufacture.

- The curing compound shall be packaged in clean 210-L barrels or round 19-L containers or shall be supplied from a suitable storage tank located at the jobsite. The containers shall comply with "Title 49, Code of Federal Regulations, Hazardous Materials Regulations." The 210-L barrels shall have removable lids and airtight fasteners. The 19-L containers shall be round and have standard full open head and bail. Lids with bungholes shall not be permitted. On-site storage tanks shall be kept clean and free of contaminants. Each tank shall have a permanent system designed to completely redisperse settled material without introducing air or other foreign substances.

- Steel containers and lids shall be lined with a coating that will prevent destructive action by the compound or chemical agents in the air space above the compound. The coating shall not come off the container or lid as skins. Containers shall be filled in a manner that will prevent skinning. Plastic containers shall not react with the compound.

- Each container shall be labeled with the manufacturer's name, kind of curing compound, batch number, volume, date of manufacture, and volatile organic compound (VOC) content. The label shall also warn that the curing compound containing pigment shall be well stirred before use. Precautions concerning the handling and the application of curing compound shall be shown on the label of the curing compound containers in conformance with the Construction Safety Orders and General Industry Safety Orders of the State of California.

- Containers of curing compound shall be labeled to indicate that the contents fully comply with the rules and regulations concerning air pollution control in the State of California.

- When the curing compound is shipped in tanks or tank trucks, a shipping invoice shall accompany each load. The invoice shall contain the same information as that required herein for container labels.

- Curing compound will be sampled by the Engineer at the source of supply or at the jobsite or at both locations.

- Curing compound shall be formulated so as to maintain the specified properties for a minimum of one year. The Engineer may require additional testing before use to determine compliance with these specifications if the compound has not been used within one year or whenever the Engineer has reason to believe the compound is no longer satisfactory.

- Tests will be conducted in conformance with the latest ASTM test methods and methods in use by the Transportation Laboratory.

90-7.01C Waterproof Membrane Method

- The exposed finished surfaces of concrete shall be sprayed with water, using a nozzle that so atomizes the flow that a mist and not a spray is formed, until the concrete has set, after which the curing membrane shall be placed. The curing membrane shall remain in place for a period of not less than 72 hours.

- Sheeting material for curing concrete shall conform to the requirements in AASHTO Designation: M 171 for white reflective materials.

- The sheeting material shall be fabricated into sheets of such width as to provide a complete cover for the entire concrete surface. Joints in the sheets shall be securely cemented together in such a manner as to provide a waterproof joint. The joint seams shall have a minimum lap of 100 mm.

- The sheets shall be securely weighted down by placing a bank of earth on the edges of the sheets or by other means satisfactory to the Engineer.

- Should any portion of the sheets be broken or damaged before the expiration of 72 hours after being placed, the broken or damaged portions shall be immediately repaired with new sheets properly cemented into place.

- Sections of membrane that have lost their waterproof qualities or have been damaged to such an extent as to render them unfit for curing the concrete shall not be used.

90-7.01D Forms-In-Place Method

- Formed surfaces of concrete may be cured by retaining the forms in place. The forms shall remain in place for a minimum period of 7 days after the concrete has been placed, except that for members over 0.5-m in least dimension the forms shall remain in place for a minimum period of 5 days.

- Joints in the forms and the joints between the end of forms and concrete shall be kept moisture tight during the curing period. Cracks in the forms and cracks between the forms and the concrete shall be resealed by methods subject to the approval of the Engineer.

90-7.02 CURING PAVEMENT

- The entire exposed area of the pavement, including edges, shall be cured by the waterproof membrane method, or curing compound method using curing compound (1) or (2) as the Contractor may elect. Should the side forms be removed before the expiration of 72 hours following the start of curing, the exposed pavement edges shall also be cured. If the pavement is cured by means of the curing compound method, the sawcut and all portions of the curing compound that have been disturbed by sawing operations shall be restored by spraying with additional curing compound.

- Curing shall commence as soon as the finishing process provided in Section 40-1.10, "Final Finishing," has been completed. The method selected shall conform to the provisions in Section 90-7.01, "Methods of Curing."

- When the curing compound method is used, the compound shall be applied to the entire pavement surface by mechanical sprayers. Spraying equipment shall be of the fully atomizing type equipped with a tank agitator that provides for continual agitation of the curing compound during the time of application. The spray shall be adequately protected against wind, and the nozzles shall be so oriented or moved mechanically transversely as to result in the minimum specified rate of coverage being applied uniformly on exposed faces. Hand spraying of small and irregular areas, and areas inaccessible to mechanical spraying equipment, in the opinion of the Engineer, will be permitted. When the ambient air temperature is above 15°C, the Contractor shall fog the surface of the concrete with a fine spray of water as specified in Section 90-7.01A, "Water Method." The surface of the pavement shall be kept moist between the hours of 10:00 a.m. and 4:30 p.m. on the day the concrete is placed. However, the fogging done after the curing compound has been applied shall not begin until the compound has set sufficiently to prevent displacement. Fogging shall be discontinued if ordered in writing by the Engineer.

90-7.03 CURING STRUCTURES

- Newly placed concrete for cast-in-place structures, other than highway bridge decks, shall be cured by the water method, the forms-in-place method, or, as permitted herein, by the curing compound method, in conformance with the provisions in Section 90-7.01, "Methods of Curing."

- The curing compound method using a pigmented curing compound may be used on concrete surfaces of construction joints, surfaces that are to be buried underground, and surfaces where only Ordinary Surface Finish is to be applied and on which a uniform color is not required and that will not be visible from a public traveled way. If the Contractor elects to use the curing compound method on the bottom slab of box girder spans, the curing compound shall be curing compound (1).

- The top surface of highway bridge decks shall be cured by both the curing compound method and the water method. The curing compound shall be curing compound (1). The curing compound shall be applied progressively during the deck finishing operations immediately after finishing operations are completed on each individual portion of the deck. The water cure shall be applied not later than 4 hours after completion of deck finishing or, for portions of the decks on which finishing is completed after normal working hours, the water cure shall be applied not later than the following morning.

- Concrete surfaces of minor structures, as defined in Section 51-1.02, "Minor Structures," shall be cured by the water method, the forms-in-place method or the curing compound method.

- When deemed necessary by the Engineer during periods of hot weather, water shall be applied to concrete surfaces being cured by the curing compound method or by the forms-in-place method, until the Engineer determines that a cooling effect is no longer required. Application of water for this purpose will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

90-7.04 CURING PRECAST CONCRETE MEMBERS

- Precast concrete members shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing." Curing shall be provided for the minimum time specified for each method or until the concrete reaches its design strength, whichever is less. Steam curing may also be used for precast members and shall conform to the following provisions:

- A. After placement of the concrete, members shall be held for a minimum 4-hour presteaming period. If the ambient air temperature is below 10°C, steam shall be applied during the presteaming period to hold the air surrounding the member at a temperature between 10°C and 32°C.
- B. To prevent moisture loss on exposed surfaces during the presteaming period, members shall be covered as soon as possible after casting or the exposed surfaces shall be kept wet by fog spray or wet blankets.
- C. Enclosures for steam curing shall allow free circulation of steam about the member and shall be constructed to contain the live steam with a minimum moisture loss. The use of tarpaulins or similar flexible covers will be permitted, provided they are kept in good repair and secured in such a manner as to prevent the loss of steam and moisture.

- D. Steam at the jets shall be at low pressure and in a saturated condition. Steam jets shall not impinge directly on the concrete, test cylinders, or forms. During application of the steam, the temperature rise within the enclosure shall not exceed 22°C per hour. The curing temperature throughout the enclosure shall not exceed 65°C and shall be maintained at a constant level for a sufficient time necessary to develop the required transfer strength. Control cylinders shall be covered to prevent moisture loss and shall be placed in a location where temperature is representative of the average temperature of the enclosure.
- E. Temperature recording devices that will provide an accurate, continuous, permanent record of the curing temperature shall be provided. A minimum of one temperature recording device per 60 m of continuous bed length will be required for checking temperature.
- F. Members in pretension beds shall be detensioned immediately after the termination of steam curing while the concrete and forms are still warm, or the temperature under the enclosure shall be maintained above 15°C until the stress is transferred to the concrete.
- G. Curing of precast concrete will be considered completed after termination of the steam curing cycle.

90-7.05 CURING PRECAST PRESTRESSED CONCRETE PILES

- Newly placed concrete for precast prestressed concrete piles shall be cured in conformance with the provisions in Section 90-7.04, "Curing Precast Concrete Members," except that piles with a class designation ending in C (corrosion resistant) shall be cured as follows:

- A. Piles shall be either steam cured or water cured. If water curing is used, the piles shall be kept continuously wet by the application of water in conformance with the provisions in Section 90-7.01A, "Water Method."
- B. If steam curing is used, the steam curing provisions in Section 90-7.04, "Curing Precast Concrete Members," shall apply except that the piles shall be kept continuously wet for their entire length for a period of not less than 3 days, including the holding and steam curing periods.

90-7.06 CURING SLOPE PROTECTION

- Concrete slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

- Concreted-rock slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing," or with a blanket of earth kept wet for 72 hours, or by sprinkling with a fine spray of water every 2 hours during the daytime for a period of 3 days.

90-7.07 CURING MISCELLANEOUS CONCRETE WORK

- Exposed surfaces of curbs shall be cured by pigmented curing compounds as specified in Section 90-7.01B, "Curing Compound Method."

- Concrete sidewalks, gutter depressions, island paving, curb ramps, driveways, and other miscellaneous concrete areas shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

- Shotcrete shall be cured for at least 72 hours by spraying with water, or by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

- Mortar and grout shall be cured by keeping the surface damp for 3 days.

- After placing, the exposed surfaces of sign structure foundations, including pedestal portions, if constructed, shall be cured for at least 72 hours by spraying with water, or by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

90-8 PROTECTING CONCRETE

90-8.01 GENERAL

- In addition to the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," the Contractor shall protect concrete as provided in this Section 90-8.

- Concrete shall not be placed on frozen or ice-coated ground or subgrade nor on ice-coated forms, reinforcing steel, structural steel, conduits, precast members, or construction joints.

- Under rainy conditions, placing of concrete shall be stopped before the quantity of surface water is sufficient to damage surface mortar or cause a flow or wash of the concrete surface, unless the Contractor provides adequate protection against damage.

- Concrete that has been frozen or damaged by other causes, as determined by the Engineer, shall be removed and replaced by the Contractor at the Contractor's expense.

90-8.02 PROTECTING CONCRETE STRUCTURES

- Structure concrete and shotcrete used as structure concrete shall be maintained at a temperature of not less than 7°C for 72 hours after placing and at not less than 4°C for an additional 4 days. When required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

90-8.03 PROTECTING CONCRETE PAVEMENT

- Pavement concrete shall be maintained at a temperature of not less than 4°C for 72 hours. When required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

- Except as provided in Section 7-1.08, "Public Convenience," the Contractor shall protect concrete pavement against construction and other activities that abrade, scar, discolor, reduce texture depth, lower coefficient of friction, or otherwise damage the surface. Stockpiling, drifting, or excessive spillage of soil, gravel, petroleum products, and concrete or asphalt mixes on the surface of concrete pavement is prohibited unless otherwise specified in these specifications, the special provisions or permitted by the Engineer.

- When ordered by the Engineer or shown on the plans or specified in the special provisions, pavement crossings shall be constructed for the convenience of public traffic. The material and work necessary for the construction of the crossings, and their subsequent removal and disposal, will be paid for at the contract unit prices for the items of work involved and if there are no contract items for the work involved, payment for pavement crossings will be made by extra work as provided in Section 4-1.03D, "Extra Work.". Where public traffic will be required to cross over the new pavement, Type III portland cement may be used in concrete, if permitted in writing by the Engineer. The pavement may be opened to traffic as soon as the concrete has developed a modulus of rupture of 3.8 MPa. The modulus of rupture will be determined by California Test 523.

- No traffic or Contractor's equipment, except as hereinafter provided, will be permitted on the pavement before a period of 10 days has elapsed after the concrete has been placed, nor before the concrete has developed a modulus of rupture of at least 3.8 MPa. Concrete that fails to attain a modulus of rupture of 3.8 MPa within 10 days shall not be opened to traffic until directed by the Engineer.

- Equipment for sawing weakened plane joints will be permitted on the pavement as specified in Section 40-1.08B, "Weakened Plane Joints."

- When requested in writing by the Contractor, the tracks on one side of paving equipment will be permitted on the pavement after a modulus of rupture of 2.4 MPa has been attained, provided that:

- A. Unit pressure exerted on the pavement by the paver shall not exceed 135 kPa;
- B. Tracks with cleats, grousers, or similar protuberances shall be modified or shall travel on planks or equivalent protective material, so that the pavement is not damaged; and
- C. No part of the track shall be closer than 0.3-m from the edge of pavement.

- In case of visible cracking of, or other damage to the pavement, operation of the paving equipment on the pavement shall be immediately discontinued.

- Damage to the pavement resulting from early use of pavement by the Contractor's equipment as provided above shall be repaired by the Contractor at the Contractor's expense.

- The State will furnish the molds and machines for testing the concrete for modulus of rupture, and the Contractor, at the Contractor's expense, shall furnish the material and whatever labor the Engineer may require.

90-9 COMPRESSIVE STRENGTH

90-9.01 GENERAL

- Concrete compressive strength requirements consist of a minimum strength that shall be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or the special provisions or are shown on the plans.

- The compressive strength of concrete will be determined from test cylinders that have been fabricated from concrete sampled in conformance with the requirements of ASTM Designation: C 172. Test cylinders will be molded and initially field cured in conformance with California Test 540. Test cylinders will be cured and tested after receipt at the testing laboratory in conformance with the requirements of ASTM Designation: C 39. A strength test shall consist of the average strength of 2 cylinders fabricated from material taken from a single load of concrete, except that, if any cylinder should show evidence of improper sampling, molding, or testing, that cylinder shall be discarded and the strength test shall consist of the strength of the remaining cylinder.

- When concrete compressive strength is specified as a prerequisite to applying loads or stresses to a concrete structure or member, test cylinders for other than steam cured concrete will be cured in conformance with Method 1 of California Test 540. The compressive strength of concrete determined for these purposes will be evaluated on the basis of individual tests.

- When concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete strength to be used as a basis for acceptance of other than steam cured concrete will be determined from cylinders cured in conformance with Method 1 of California Test 540. If the result of a single compressive strength test at the maximum age specified or allowed is below the specified strength but is 95 percent or more of the specified strength, the Contractor shall, at the Contractor's expense, make corrective changes, subject to approval of the Engineer, in the mix proportions or in the concrete fabrication procedures, before placing additional concrete, and shall pay to the State \$14 for each in-place cubic meter of concrete represented by the deficient test. If the result of a single compressive strength test at the maximum age specified or allowed is below 95 percent of the specified strength, but is 85 percent or more of the specified strength, the Contractor shall make the corrective changes specified above, and shall pay to the State \$20 for each in place cubic meter of concrete represented by the deficient test. In addition, such corrective changes shall be made when the compressive strength of concrete tested at 7 days indicates, in the judgment of the Engineer, that the concrete will not attain the required compressive strength at the maximum age specified or allowed. Concrete represented by a single test that indicates a compressive strength of less than 85 percent of the specified 28-day compressive strength will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials."

- If the test result indicates that the compressive strength at the maximum curing age specified or allowed is below the specified strength, but is 85 percent or more of the specified strength, payments to the State as required above shall be made, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength of the concrete placed in the work meets or exceeds the specified 28-day compressive strength. If the test result indicates a compressive strength at the maximum curing age specified or allowed below 85 percent, the concrete represented by that test will be rejected, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength and quality of the concrete placed in the work are acceptable. If the evidence consists of tests made on cores taken from the work, the cores shall be obtained and tested in conformance with the requirements in ASTM Designation: C 42.

- No single compressive strength test shall represent more than 250 m³.

- When a precast concrete member is steam cured, the compressive strength of the concrete will be determined from test cylinders that have been handled and stored in conformance with Method 3 of California Test 540. The compressive strength of steam cured concrete will be evaluated on the basis of individual tests representing specific portions of production. When the concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete shall be considered to be acceptable whenever its compressive strength reaches the specified 28-day compressive strength provided that strength is reached in not more than the maximum number of days specified or allowed after the member is cast.

- When concrete is specified by compressive strength, prequalification of materials, mix proportions, mixing equipment, and procedures proposed for use will be required prior to placement of the concrete. Prequalification shall be accomplished by the submission of acceptable certified test data or trial batch reports by the Contractor. Prequalification data shall be based on the use of materials, mix proportions, mixing equipment, procedures, and size of batch proposed for use in the work.

- Certified test data, in order to be acceptable, shall indicate that not less than 90 percent of at least 20 consecutive tests exceed the specified strength at the maximum number of cure days specified or allowed, and none of those tests are less than 95 percent of specified strength. Strength tests included in the data shall be the most recent tests made on concrete of the proposed mix design and all shall have been made within one year of the proposed use of the concrete.

- Trial batch test reports, in order to be acceptable, shall indicate that the average compressive strength of 5 consecutive concrete cylinders, taken from a single batch, at not more than 28 days (or the maximum age allowed) after molding shall be at least 4 MPa greater than the specified 28-day compressive strength, and no individual cylinder shall have a strength less than the specified strength at the maximum age specified or allowed. Data contained in the report shall be from trial batches that were produced within one year of the proposed use of specified strength concrete in the project. Whenever air-entrainment is required, the air content of trial batches shall be equal to or greater than the air content specified for the concrete without reduction due to tolerances.

- Tests shall be performed in conformance with either the appropriate California Test methods or the comparable ASTM test methods. Equipment employed in testing shall be in good condition and shall be properly calibrated. If the tests are performed during the life of the contract, the Engineer shall be notified sufficiently in advance of performing the tests in order to witness the test procedures.

- The certified test data and trial batch test reports shall include the following information:

- A. Date of mixing.
- B. Mixing equipment and procedures used.
- C. The size of batch in cubic meters and the mass, type, and source of all ingredients used.
- D. Penetration of the concrete.
- E. The air content of the concrete if an air-entraining admixture is used.
- F. The age at time of testing and strength of all concrete cylinders tested.

- Certified test data and trial batch test reports shall be signed by an official of the firm that performed the tests.
- When approved by the Engineer, concrete from trial batches may be used in the work at locations where concrete of a lower quality is required and the concrete will be paid for as the type or class of concrete required at that location.
 - After materials, mix proportions, mixing equipment, and procedures for concrete have been prequalified for use, additional prequalification by testing of trial batches will be required prior to making changes that, in the judgment of the Engineer, could result in a strength of concrete below that specified.
 - The Contractor's attention is directed to the time required to test trial batches and the Contractor shall be responsible for production of trial batches at a sufficiently early date so that the progress of the work is not delayed.
 - When precast concrete members are manufactured at the plant of an established manufacturer of precast concrete members, the mix proportions of the concrete shall be determined by the Contractor, and a trial batch and prequalification of the materials, mix proportions, mixing equipment, and procedures will not be required.

90-10 MINOR CONCRETE

90-10.01 GENERAL

- Concrete for minor structures, slope paving, curbs, sidewalks and other concrete work, when designated as minor concrete on the plans, in the specifications, or in the contract item, shall conform to the provisions specified herein.
- The Engineer, at the Engineer's discretion, will inspect and test the facilities, materials and methods for producing the concrete to ensure that minor concrete of the quality suitable for use in the work is obtained.

90-10.02 MATERIALS

- Minor concrete shall conform to the following requirements:

90-10.02A Cementitious Material

- Cementitious material shall conform to the provisions in Section 90-1.01, "Description."

90-10.02B Aggregate

- Aggregate shall be clean and free from deleterious coatings, clay balls, roots, and other extraneous materials.
- The Contractor shall submit to the Engineer for approval, a grading of the combined aggregate proposed for use in the minor concrete. After acceptance of the grading, aggregate furnished for minor concrete shall conform to that grading, unless a change is authorized in writing by the Engineer.
 - The Engineer may require the Contractor to furnish periodic test reports of the aggregate grading furnished. The maximum size of aggregate used shall be at the option of the Contractor, but in no case shall the maximum size be larger than 37.5 mm or smaller than 19 mm.
 - The Engineer may waive, in writing, the gradation requirements in this Section 90-10.02B, if, in the Engineer's opinion, the furnishing of the gradation is not necessary for the type or amount of concrete work to be constructed.

90-10.02C Water

- Water used for washing, mixing, and curing shall be free from oil, salts, and other impurities that would discolor or etch the surface or have an adverse affect on the quality of the concrete.

90-10.02D Admixtures

- The use of admixtures shall conform to the provisions in Section 90-4, "Admixtures."

90-10.03 PRODUCTION

- Cementitious material, water, aggregate, and admixtures shall be stored, proportioned, mixed, transported, and discharged in conformance with recognized standards of good practice that will result in concrete that is thoroughly and uniformly mixed, that is suitable for the use intended, and that conforms to requirements specified herein. Recognized standards of good practice are outlined in various industry publications such as are issued by American Concrete Institute, AASHTO, or the Department.

- The cementitious material content of minor concrete shall conform to the provisions in Section 90-1.01, "Description."

- The amount of water used shall result in a consistency of concrete conforming to the provisions in Section 90-6.06, "Amount of Water and Penetration." Additional mixing water shall not be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer.

- Discharge of ready-mixed concrete from the transporting vehicle shall be made while the concrete is still plastic and before stiffening occurs. An elapsed time of 1.5 hours (one hour in non-agitating hauling equipment), or more than 250 revolutions of the drum or blades, after the introduction of the cementitious material to the aggregates, or a temperature of concrete of more than 32°C will be considered conditions contributing to the quick stiffening of concrete. The Contractor shall take whatever action is necessary to eliminate quick stiffening, except that the addition of water will not be permitted.

- The required mixing time in stationary mixers shall be not less than 50 seconds or more than 5 minutes.

- The minimum required revolutions at mixing speed for transit-mixed concrete shall be not less than that recommended by the mixer manufacturer, and shall be increased, if necessary, to produce thoroughly and uniformly mixed concrete.

- Each load of ready-mixed concrete shall be accompanied by a weighmaster certificate that shall be delivered to the Engineer at the discharge location of the concrete, unless otherwise directed by the Engineer. The weighmaster certificate shall be clearly marked with the date and time of day when the load left the batching plant and, if hauled in truck mixers or agitators, the time the mixing cycle started.

- A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished to the Engineer, prior to placing minor concrete from a source not previously used on the contract, stating that minor concrete to be furnished meets contract requirements, including minimum cementitious material content specified.

90-10.04 CURING MINOR CONCRETE

- Curing minor concrete shall conform to the provisions in Section 90-7, "Curing Concrete."

90-10.05 PROTECTING MINOR CONCRETE

- Protecting minor concrete shall conform to the provisions in Section 90-8, "Protecting Concrete," except the concrete shall be maintained at a temperature of not less than 4°C for 72 hours after placing.

90-10.06 MEASUREMENT AND PAYMENT

- Minor concrete will be measured and paid for in conformance with the provisions specified in the various sections of these specifications covering concrete construction when minor concrete is specified in the specifications, shown on the plans, or indicated by contract item in the Engineer's Estimate.

90-11 MEASUREMENT AND PAYMENT

90-11.01 MEASUREMENT

- Portland cement concrete will be measured in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.

- When it is provided that concrete will be measured at the mixer, the volume in cubic meters shall be computed as the total mass of the batch in kilograms divided by the density of the concrete in kilograms per cubic meter. The total mass of the batch shall be calculated as the sum of all materials, including water, entering the batch. The density of the concrete will be determined in conformance with the requirements in California Test 518.

90-11.02 PAYMENT

- Portland cement concrete will be paid for in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.

- Full compensation for furnishing and incorporating admixtures required by these specifications or the special provisions will be considered as included in the contract prices paid for the concrete involved and no additional compensation will be allowed therefor.
- Should the Engineer order the Contractor to incorporate any admixtures in the concrete when their use is not required by these specifications or the special provisions, furnishing the admixtures and adding them to the concrete will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."
- Should the Contractor use admixtures in conformance with the provisions in Section 90-4.05, "Optional Use of Chemical Admixtures," or Section 90-4.07, "Optional Use of Air-entraining Admixtures," or should the Contractor request and obtain permission to use other admixtures for the Contractor's benefit, the Contractor shall furnish those admixtures and incorporate them into the concrete at the Contractor's expense and no additional compensation will be allowed therefor.

SECTION 12. (BLANK)

SECTION 13. (BLANK)

SECTION 14 FEDERAL REQUIREMENTS FOR FEDERAL-AID CONSTRUCTION PROJECTS

GENERAL.—The work herein proposed will be financed in whole or in part with Federal funds, and therefore all of the statutes, rules and regulations promulgated by the Federal Government and applicable to work financed in whole or in part with Federal funds will apply to such work. The "Required Contract Provisions, Federal-Aid Construction Contracts, "Form FHWA 1273, are included in this Section 14. Whenever in said required contract provisions references are made to "SHA contracting officer", "SHA resident engineer", or "authorized representative of the SHA", such references shall be construed to mean "Engineer" as defined in Section 1-1.18 of the Standard Specifications.

PERFORMANCE OF PREVIOUS CONTRACT.—In addition to the provisions in Section II, "Nondiscrimination," and Section VII, "Subletting or Assigning the Contract," of the required contract provisions, the Contractor shall comply with the following:

The bidder shall execute the CERTIFICATION WITH REGARD TO THE PERFORMANCE OF PREVIOUS CONTRACTS OR SUBCONTRACTS SUBJECT TO THE EQUAL OPPORTUNITY CLAUSE AND THE FILING OF REQUIRED REPORTS located in the proposal. No request for subletting or assigning any portion of the contract in excess of \$10,000 will be considered under the provisions of Section VII of the required contract provisions unless such request is accompanied by the CERTIFICATION referred to above, executed by the proposed subcontractor.

NON-COLLUSION PROVISION.—The provisions in this section are applicable to all contracts except contracts for Federal Aid Secondary projects.

Title 23, United States Code, Section 112, requires as a condition precedent to approval by the Federal Highway Administrator of the contract for this work that each bidder file a sworn statement executed by, or on behalf of, the person, firm, association, or corporation to whom such contract is to be awarded, certifying that such person, firm, association, or corporation has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with the submitted bid. A form to make the non-collusion affidavit statement required by Section 112 as a certification under penalty of perjury rather than as a sworn statement as permitted by 28, USC, Sec. 1746, is included in the proposal.

PARTICIPATION BY MINORITY BUSINESS ENTERPRISES IN SUBCONTRACTING.—Part 23, Title 49, Code of Federal Regulations applies to this Federal-aid project. Pertinent sections of said Code are incorporated in part or in its entirety within other sections of these special provisions.

Schedule B—Information for Determining Joint Venture Eligibility

(This form need not be filled in if all joint venture firms are minority owned.)

1. Name of joint venture _____
2. Address of joint venture _____
3. Phone number of joint venture _____
4. Identify the firms which comprise the joint venture. (The MBE partner must complete Schedule A.) _____

 - a. Describe the role of the MBE firm in the joint venture. _____
 - b. Describe very briefly the experience and business qualifications of each non-MBE joint venturer: _____
5. Nature of the joint venture's business _____
6. Provide a copy of the joint venture agreement.
7. What is the claimed percentage of MBE ownership? _____
8. Ownership of joint venture: (This need not be filled in if described in the joint venture agreement, provided by question 6.).
 - a. Profit and loss sharing.
 - b. Capital contributions, including equipment.
 - c. Other applicable ownership interests.

9. Control of and participation in this contract. Identify by name, race, sex, and "firm" those individuals (and their titles) who are responsible for day-to-day management and policy decision making, including, but not limited to, those with prime responsibility for:

- a. Financial decisions _____
- b. Management decisions, such as:
 - (1) Estimating _____
 - (2) Marketing and sales _____
 - (3) Hiring and firing of management personnel _____
 - (4) Purchasing of major items or supplies _____
- c. Supervision of field operations _____

Note.—If, after filing this Schedule B and before the completion of the joint venture's work on the contract covered by this regulation, there is any significant change in the information submitted, the joint venture must inform the grantee, either directly or through the prime contractor if the joint venture is a subcontractor.

Affidavit

"The undersigned swear that the foregoing statements are correct and include all material information necessary to identify and explain the terms and operation of our joint venture and the intended participation by each joint venturer in the undertaking. Further, the undersigned covenant and agree to provide to grantee current, complete and accurate information regarding actual joint venture work and the payment therefor and any proposed changes in any of the joint venture arrangements and to permit the audit and examination of the books, records and files of the joint venture, or those of each joint venturer relevant to the joint venture, by authorized representatives of the grantee or the Federal funding agency. Any material misrepresentation will be grounds for terminating any contract which may be awarded and for initiating action under Federal or State laws concerning false statements."

Name of Firm	Name of Firm
Signature	Signature
Name	Name
Title	Title
Date	Date

Date _____

State of _____

County of _____

On this ____ day of _____, 19 __, before me appeared (Name) _____, to me personally known, who, being duly sworn, did execute the foregoing affidavit, and did state that he or she was properly authorized by (Name of firm) _____ to execute the affidavit and did so as his or her free act and deed.

Notary Public _____

Commission expires _____

[Seal]

Date _____

State of _____

County of _____

On this ____ day of _____, 19 __, before me appeared (Name) _____ to me personally known, who, being duly sworn, did execute the foregoing affidavit, and did state that he or she was properly authorized by (Name of firm) _____ to execute the affidavit and did so as his or her free act and deed.

Notary Public _____

Commission expires _____

[Seal]

**REQUIRED CONTRACT PROVISIONS
FEDERAL-AID CONSTRUCTION CONTRACTS**

I. GENERAL

1. These contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.
2. Except as otherwise provided for in each section, the contractor shall insert in each subcontract all of the stipulations contained in these Required Contract Provisions, and further require their inclusion in any lower tier subcontract or purchase order that may in turn be made. The Required Contract Provisions shall not be incorporated by reference in any case. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with these Required Contract Provisions.
3. A breach of any of the stipulations contained in these Required Contract Provisions shall be sufficient grounds for termination of the contract.
4. A breach of the following clauses of the Required Contract Provisions may also be grounds for debarment as provided in 29 CFR 5.12:

Section I, paragraph 2;
Section IV, paragraphs 1, 2, 3, 4, and 7;
Section V, paragraphs 1 and 2a through 2g.

5. Disputes arising out of the labor standards provisions of Section IV (except paragraph 5) and Section V of these Required Contract Provisions shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the U.S. Department of Labor (DOL) as set forth in 29 CFR 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the DOL, or the contractor's employees or their representatives.
6. **Selection of Labor:** During the performance of this contract, the contractor shall not:
 - a. discriminate against labor from any other State, possession, or territory of the United States (except for employment preference for Appalachian contracts, when applicable, as specified in Attachment A), or
 - b. employ convict labor for any purpose within the limits of the project unless it is labor performed by convicts who are on parole, supervised release, or probation.

II. NONDISCRIMINATION

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

1. **Equal Employment Opportunity:** Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, and 41 CFR 60) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The Equal Opportunity Construction Contract Specifications set forth under 41 CFR 60-4.3 and the provisions of the American Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:
 - a. The contractor will work with the State highway agency (SHA) and the Federal Government in carrying out EEO obligations and in their review of his/her activities under the contract.

- b. The contractor will accept as his operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job training."

2. **EEO Officer:** The contractor will designate and make known to the SHA contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so.
3. **Dissemination of Policy:** All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
- a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
 - b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
 - c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minority group employees.
 - d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
 - e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.
4. **Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minority groups in the area from which the project work force would normally be derived.
- a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minority group applicants. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority group applicants may be referred to the contractor for employment consideration.
 - b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he is expected to observe the provisions of that agreement to the extent that the system permits the contractor's compliance with EEO contract provisions. (The DOL has held that where implementation of such agreements have the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Executive Order 11246, as amended.)
 - c. The contractor will encourage his present employees to refer minority group applicants for employment. Information and procedures with regard to referring minority group applicants will be discussed with employees.

5. **Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:
 - a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
 - b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
 - c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
 - d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with his obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of his avenues of appeal.
6. **Training and Promotion:**
 - a. The contractor will assist in locating, qualifying, and increasing the skills of minority group and women employees, and applicants for employment.
 - b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision.
 - c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
 - d. The contractor will periodically review the training and promotion potential of minority group and women employees and will encourage eligible employees to apply for such training and promotion.
7. **Unions:** If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the contractor either directly or through a contractor's association acting as agent will include the procedures set forth below:
 - a. The contractor will use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority group members and women for membership in the unions and increasing the skills of minority group employees and women so that they may qualify for higher paying employment.
 - b. The contractor will use best efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
 - c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the SHA and shall set forth what efforts have been made to obtain such information.

- d. In the event the union is unable to provide the contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The DOL has held that it shall be no excuse that the union with which the contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the SHA.
- 8. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment:** The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.
- a. The contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.
 - b. Disadvantaged business enterprises (DBE), as defined in 49 CFR 23, shall have equal opportunity to compete for and perform subcontracts which the contractor enters into pursuant to this contract. The contractor will use his best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority group and female representation among their employees. Contractors shall obtain lists of DBE construction firms from SHA personnel.
 - c. The contractor will use his best efforts to ensure subcontractor compliance with their EEO obligations.
- 9. Records and Reports:** The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the SHA and the FHWA.
- a. The records kept by the contractor shall document the following:
 - (1) The number of minority and non-minority group members and women employed in each work classification on the project;
 - (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women;
 - (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and
 - (4) The progress and efforts being made in securing the services of DBE subcontractors or subcontractors with meaningful minority and female representation among their employees.
 - b. The contractors will submit an annual report to the SHA each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data.

III. NONSEGREGATED FACILITIES

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

- a. By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement or purchase order, as appropriate, the bidder, Federal-aid construction contractor, subcontractor, material supplier, or vendor, as appropriate, certifies that the firm does not maintain or provide for its employees any segregated facilities at any of its establishments, and that the firm does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The firm agrees that a breach of this certification is a violation of the EEO provisions of this contract. The firm further certifies that no employee will be denied access to adequate facilities on the basis of sex or disability.
- b. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, time clocks, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive, or are, in fact, segregated on the basis of race, color, religion, national origin, age or disability, because of habit, local custom, or otherwise. The only exception will be for the disabled when the demands for accessibility override (e.g. disabled parking).
- c. The contractor agrees that it has obtained or will obtain identical certification from proposed subcontractors or material suppliers prior to award of subcontracts or consummation of material supply agreements of \$10,000 or more and that it will retain such certifications in its files.

IV. PAYMENT OF PREDETERMINED MINIMUM WAGE

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural minor collectors, which are exempt.)

1. General:

- a. All mechanics and laborers employed or working upon the site of the work will be paid unconditionally and not less often than once a week and without subsequent deduction or rebate on any account [except such payroll deductions as are permitted by regulations (29 CFR 3)] issued by the Secretary of Labor under the Copeland Act (40 U.S.C. 276c) the full amounts of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment. The payment shall be computed at wage rates not less than those contained in the wage determination of the Secretary of Labor (hereinafter "the wage determination") which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor or its subcontractors and such laborers and mechanics. The wage determination (including any additional classifications and wage rates conformed under paragraph 2 of this Section IV and the DOL poster (WH-1321) or Form FHWA-1495) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers. For the purpose of this Section, contributions made or costs reasonably anticipated for bona fide fringe benefits under Section 1(b)(2) of the Davis-Bacon Act (40 U.S.C. 276a) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of Section IV, paragraph 3b, hereof. Also, for the purpose of this Section, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraphs 4 and 5 of this Section IV.
- b. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein, provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.
- c. All rulings and interpretations of the Davis-Bacon Act and related acts contained in 29 CFR 1, 3, and 5 are herein incorporated by reference in this contract.

2. Classification:

- a. The SHA contracting officer shall require that any class of laborers or mechanics employed under the contract, which is not listed in the wage determination, shall be classified in conformance with the wage determination.
- b. The contracting officer shall approve an additional classification, wage rate and fringe benefits only when the following criteria have been met:
 - (1) the work to be performed by the additional classification requested is not performed by a classification in the wage determination;
 - (2) the additional classification is utilized in the area by the construction industry;
 - (3) the proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination; and
 - (4) with respect to helpers, when such a classification prevails in the area in which the work is performed.
- c. If the contractor or subcontractors, as appropriate, the laborers and mechanics (if known) to be employed in the additional classification or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the DOL, Administrator of the Wage and Hour Division, Employment Standards Administration, Washington, D.C. 20210. The Wage and Hour Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- d. In the event the contractor or subcontractors, as appropriate, the laborers or mechanics to be employed in the additional classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. Said Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary
- e. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 2c or 2d of this Section IV shall be paid to all workers performing work in the additional classification from the first day on which work is performed in the classification.

3. Payment of Fringe Benefits:

- a. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor or subcontractors, as appropriate, shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly case equivalent thereof.
- b. If the contractor or subcontractor, as appropriate, does not make payments to a trustee or other third person, he/she may consider as a part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided, that the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

4. Apprentices and Trainees (Programs of the U.S. DOL) and Helpers:

a. Apprentices:

- (1) Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the DOL, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau, or if a person is employed in his/her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State apprenticeship agency (where appropriate) to be eligible for probationary employment as an apprentice.
- (2) The allowable ratio of apprentices to journeyman-level employees on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate listed in the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor or subcontractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman-level hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.
- (3) Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator for the Wage and Hour Division determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.
- (4) In the event the Bureau of Apprenticeship and Training, or a State apprenticeship agency recognized by the Bureau, withdraws approval of an apprenticeship program, the contractor or subcontractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the comparable work performed by regular employees until an acceptable program is approved.

b. Trainees:

- (1) Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the DOL, Employment and Training Administration.
- (2) The ratio of trainees to journeyman-level employees on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

- (3) Every trainee must be paid at not less than the rate specified in the approved program for his/her level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman-level wage rate on the wage determination which provides for less than full fringe benefits for apprentices, in which case such trainees shall receive the same fringe benefits as apprentices.
- (4) In the event the Employment and Training Administration withdraws approval of a training program, the contractor or subcontractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. **Helpers:**

Helpers will be permitted to work on a project if the helper classification is specified and defined on the applicable wage determination or is approved pursuant to the conformance procedure set forth in Section IV.2. Any worker listed on a payroll at a helper wage rate, who is not a helper under an approved definition, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed.

5. Apprentices and Trainees (Programs of the U.S. DOT):

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

6. Withholding:

The SHA shall upon its own action or upon written request of an authorized representative of the DOL withhold, or cause to be withheld, from the contractor or subcontractor under this contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage requirements which is held by the same prime contractor, as much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the SHA contracting officer may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

7. Overtime Requirements:

No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen, or guards (including apprentices, trainees, and helpers described in paragraphs 4 and 5 above) shall require or permit any laborer, mechanic, watchman, or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman, or guard receives compensation at a rate not less than one-and-one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

8. Violation:

Liability for Unpaid Wages; Liquidated Damages: In the event of any violation of the clause set forth in paragraph 7 above, the contractor and any subcontractor responsible thereof shall be liable to the affected employee for his/her unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory) for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman, or guard employed in violation of the clause set forth in paragraph 7, in the sum of \$10 for each calendar day on which such employee was required or permitted to work in excess of the standard work week of 40 hours without payment of the overtime wages required by the clause set forth in paragraph 7.

9. Withholding for Unpaid Wages and Liquidated Damages:

The SHA shall upon its own action or upon written request of any authorized representative of the DOL withhold, or cause to be withheld, from any monies payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 8 above.

V. STATEMENTS AND PAYROLLS

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural collectors, which are exempt.)

1. Compliance with Copeland Regulations (29 CFR 3):

The contractor shall comply with the Copeland Regulations of the Secretary of Labor which are herein incorporated by reference.

2. Payrolls and Payroll Records:

- a. Payrolls and basic records relating thereto shall be maintained by the contractor and each subcontractor during the course of the work and preserved for a period of 3 years from the date of completion of the contract for all laborers, mechanics, apprentices, trainees, watchmen, helpers, and guards working at the site of the work.
- b. The payroll records shall contain the name, social security number, and address of each such employee; his or her correct classification; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalent thereof the types described in Section 1(b)(2)(B) of the Davis Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. In addition, for Appalachian contracts, the payroll records shall contain a notation indicating whether the employee does, or does not, normally reside in the labor area as defined in Attachment A, paragraph 1. Whenever the Secretary of Labor, pursuant to Section IV, paragraph 3b, has found that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in Section 1(b)(2)(B) of the Davis Bacon Act, the contractor and each subcontractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, that the plan or program has been communicated in writing to the laborers or mechanics affected, and show the cost anticipated or the actual cost incurred in providing benefits. Contractors or subcontractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprentices and trainees, and ratios and wage rates prescribed in the applicable programs.
- c. Each contractor and subcontractor shall furnish, each week in which any contract work is performed, to the SHA resident engineer a payroll of wages paid each of its employees (including apprentices, trainees, and helpers, described in Section IV, paragraphs 4 and 5, and watchmen and guards engaged on work during the preceding weekly payroll period). The payroll submitted shall set out accurately and completely all of the information required to be maintained under paragraph 2b of this Section V. This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal stock number 029-005-0014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors.
- d. Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his/her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
 - (1) that the payroll for the payroll period contains the information required to be maintained under paragraph 2b of this Section V and that such information is correct and complete;

- (2) that such laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR 3;
 - (3) that each laborer or mechanic has been paid not less than the applicable wage rate and fringe benefits or cash equivalent for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.
- e. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 2d of this Section V.
 - f. The falsification of any of the above certifications may subject the contractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 231.
 - g. The contractor or subcontractor shall make the records required under paragraph 2b of this Section V available for inspection, copying, or transcription by authorized representatives of the SHA, the FHWA, or the DOL, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the SHA, the FHWA, the DOL, or all may, after written notice to the contractor, sponsor, applicant, or owner, take such actions as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

VI. RECORD OF MATERIALS, SUPPLIES, AND LABOR

- 1. On all Federal-aid contracts on the National Highway System, except those which provide solely for the installation of protective devices at railroad grade crossings, those which are constructed on a force account or direct labor basis, highway beautification contracts, and contracts for which the total final construction cost for roadway and bridge is less than \$1,000,000 (23 CFR 635) the contractor shall:
 - a. Become familiar with the list of specific materials and supplies contained in Form FHWA-47, "Statement of Materials and Labor Used by Contractor of Highway Construction Involving Federal Funds," prior to the commencement of work under this contract.
 - b. Maintain a record of the total cost of all materials and supplies purchased for and incorporated in the work, and also of the quantities of those specific materials and supplies listed on Form FHWA-47, and in the units shown on Form FHWA-47.
 - c. Furnish, upon the completion of the contract, to the SHA resident engineer on Form FHWA-47 together with the data required in paragraph 1b relative to materials and supplies, a final labor summary of all contract work indicating the total hours worked and the total amount earned.
- 2. At the prime contractor's option, either a single report covering all contract work or separate reports for the contractor and for each subcontract shall be submitted.

VII. SUBLETTING OR ASSIGNING THE CONTRACT

- 1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the State. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635).
 - a. "Its own organization" shall be construed to include only workers employed and paid directly by the prime contractor and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor, assignee, or agent of the prime contractor.

- b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract as a whole and in general are to be limited to minor components of the overall contract.
2. The contract amount upon which the requirements set forth in paragraph 1 of Section VII is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the SHA contracting officer determines is necessary to assure the performance of the contract.
4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the SHA contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the SHA has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

VIII. SAFETY: ACCIDENT PREVENTION

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the SHA contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).
3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

IX. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, the following notice shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

Notice To All Personnel Engaged On Federal-Aid Highway Projects

18 U.S.C. 1020 READS AS FOLLOWS:

"Whoever being an officer, agent, or employee of the United States, or any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined not more than \$10,000 or imprisoned not more than 5 years or both."

X. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$100,000 or more.)

By submission of this bid or the execution of this contract, or subcontract, as appropriate, the bidder, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any facility that is or will be utilized in the performance of this contract, unless such contract is exempt under the Clean Air Act, as amended (42 U.S.C. 1857 et seq., as amended by Pub.L. 91-604), and under the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251 et seq., as amended by Pub.L. 92-500), Executive Order 11738, and regulations in implementation thereof (40 CFR 15) is not listed, on the date of contract award, on the U.S. Environmental Protection Agency (EPA) List of Violating Facilities pursuant to 40 CFR 15.20.
2. That the firm agrees to comply and remain in compliance with all the requirements of Section 114 of the Clean Air Act and Section 308 of the Federal Water Pollution Control Act and all regulations and guidelines listed thereunder.
3. That the firm shall promptly notify the SHA of the receipt of any communication from the Director, Office of Federal Activities, EPA, indicating that a facility that is or will be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.
4. That the firm agrees to include or cause to be included the requirements of paragraph 1 through 4 of this Section X in every nonexempt subcontract, and further agrees to take such action as the government may direct as a means of enforcing such requirements.

XI. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

1. Instructions for Certification - Primary Covered Transactions:

(Applicable to all Federal-aid contracts - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.
- c. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.
- d. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.

- e. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the department or agency to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- f. The prospective primary participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," provided by the department or agency entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the nonprocurement portion of the "Lists of Parties Excluded From Federal Procurement or Nonprocurement Programs" (Nonprocurement List) which is compiled by the General Services Administration.
- i. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph f of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion — Primary Covered Transactions

1. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:
 - a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - b. Have not within a 3-year period preceding this proposal been convicted of or had a civil judgement rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
 - c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1b of this certification; and
 - d. Have not within a 3-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

2. Instructions for Certification - Lower Tier Covered Transactions:

(Applicable to all subcontracts, purchase orders and other lower tier transactions of \$25,000 or more - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
- d. The terms "covered transaction," "debarred," "suspended," "ineligible," "primary covered transaction," "participant," "person," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion — Lower Tier Covered Transactions

1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

XII. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

(Applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 - 49 CFR 20)

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:
 - a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
 - b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
3. The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

FEDERAL-AID FEMALE AND MINORITY GOALS

In accordance with Section II, "Nondiscrimination," of "Required Contract Provisions Federal-aid Construction Contracts" the following are the goals for female utilization:

Goal for Women (applies nationwide).....(percent) 6.9

The following are goals for minority utilization:

CALIFORNIA ECONOMIC AREA

		Goal (Percent)
174	Redding, CA: Non-SMSA Counties CA Lassen; CA Modoc; CA Plumas; CA Shasta; CA Siskiyou; CA Tehama.	6.8
175	Eureka, CA Non-SMSA Counties CA Del Norte; CA Humboldt; CA Trinity.	6.6
176	San Francisco-Oakland-San Jose, CA: SMSA Counties: 7120 Salinas-Seaside-Monterey, CA CA Monterey. 7360 San Francisco-Oakland CA Alameda; CA Contra Costa; CA Marin; CA San Francisco; CA San Mateo. 7400 San Jose, CA CA Santa Clara. 7485 Santa Cruz, CA. CA Santa Cruz. 7500 Santa Rosa, CA CA Sonoma. 8720 Vallejo-Fairfield- Napa, CA CA Napa; CA Solano Non-SMSA Counties CA Lake; CA Mendocino; CA San Benito	28.9 25.6 19.6 14.9 9.1 17.1 23.2
177	Sacramento, CA: SMSA Counties: 6920 Sacramento, CA CA Placer; CA Sacramento; CA Yolo. Non-SMSA Counties CA Butte; CA Colusa; CA El Dorado; CA Glenn; CA Nevada; CA Sierra; CA Sutter; CA Yuba.	16.1 14.3
178	Stockton-Modesto, CA: SMSA Counties: 5170 Modesto, CA CA Stanislaus. 8120 Stockton, CA CA San Joaquin. Non-SMSA Counties CA Alpine; CA Amador; CA Calaveras; CA Mariposa; CA Merced; CA Tuolumne.	12.3 24.3 19.8

	Goal (Percent)
179 Fresno-Bakersfield, CA	
SMSA Counties:	
0680 Bakersfield, CA CA Kern.	19.1
2840 Fresno, CA CA Fresno.	26.1
Non-SMSA Counties CA Kings; CA Madera; CA Tulare.	23.6
180 Los Angeles, CA:	
SMSA Counties:	
0360 Anaheim-Santa Ana-Garden Grove, CA CA Orange.	11.9
4480 Los Angeles-Long Beach, CA CA Los Angeles.	28.3
6000 Oxnard-Simi Valley-Ventura, CA CA Ventura.	21.5
6780 Riverside-San Bernardino-Ontario, CA. CA Riverside; CA San Bernardino.	19.0
7480 Santa Barbara-Santa Maria-Lompoc, CA CA Santa Barbara.	19.7
Non-SMSA Counties CA Inyo; CA Mono; CA San Luis Obispo.	24.6
181 San Diego, CA:	
SMSA Counties	
7320 San Diego, CA. CA San Diego.	16.9
Non-SMSA Counties CA Imperial.	18.2

In addition to the reporting requirements set forth elsewhere in this contract the Contractor and subcontractors holding subcontracts, not including material suppliers, of \$10,000 or more, shall submit for every month of July during which work is performed, employment data as contained under Form FHWA PR-1391 (Appendix C to 23 CFR, Part 230), and in accordance with the instructions included thereon.

FEDERAL REQUIREMENT TRAINING SPECIAL PROVISIONS

As part of the Contractor's equal employment opportunity affirmative action program, training shall be provided as follows:

The Contractor shall provide on-the-job training to develop full journeymen in the types of trades or job classification involved.

The goal for the number of trainees or apprentices to be trained under the requirements of this special provision will be 7.

In the event the Contractor subcontracts a portion of the contract work, he shall determine how many, if any, of the trainees or apprentices are to be trained by the subcontractor, provided however, that the Contractor shall retain the primary responsibility for meeting the training requirements imposed by this special provision. The Contractor shall also insure that this Training Special Provision is made applicable to such subcontract. Where feasible, 25 percent of trainees or apprentices in each occupation shall be in their first year of apprenticeship or training.

The number of trainees or apprentices shall be distributed among the work classifications on the basis of the Contractor's needs and the availability of journeymen in the various classifications within a reasonable area of recruitment. Prior to commencing work, the Contractor shall submit to the Department for approval the number of trainees or apprentices to be trained in each selected classification and training program to be used. Furthermore, the Contractor shall specify the starting time for training in each of the classifications. The Contractor will be credited for each trainee or apprentice employed by him on the contract work who is currently enrolled or becomes enrolled in an approved program and will be reimbursed for such trainees or apprentices as provided hereinafter.

Training and upgrading of minorities and women toward journeymen status is a primary objective of this Training Special Provision. Accordingly, the Contractor shall make every effort to enroll minority and women trainees or apprentices (e.g., by conducting systematic and direct recruitment through public and private sources likely to yield minority and women trainees or apprentices) to the extent such persons are available within a reasonable area of recruitment. The Contractor will be responsible for demonstrating the steps that he has taken in pursuance thereof, prior to a determination as to whether the Contractor is in compliance with this Training Special Provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a minority group or not.

No employee shall be employed as a trainee or apprentice in any classification in which he has successfully completed a training course leading to journeyman status or in which he has been employed as a journeyman. The Contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used the Contractor's records should document the findings in each case.

The minimum length and type of training for each classification will be as established in the training program selected by the Contractor and approved by both the Department and the Federal Highway Administration. The Department and the Federal Highway Administration will approve a program if it is reasonably calculated to meet the equal employment opportunity obligations of the Contractor and to qualify the average trainee or apprentice for journeyman status in the classification concerned by the end of the training period. Furthermore, apprenticeship programs registered with the U.S. Department of Labor, Bureau of Apprenticeship and Training, or with the State of California, Department of Industrial Relations, Division of Apprenticeship Standards recognized by the Bureau and training programs approved but not necessarily sponsored by the U.S. Department of Labor, Manpower Administration, Bureau of Apprenticeship and Training shall also be considered acceptable provided it is being administered in a manner consistent with the equal employment obligations of Federal-aid highway construction contracts. Approval or acceptance of a training program shall be obtained from the State prior to commencing work on the classification covered by the program. It is the intention of these provisions that training is to be provided in the construction crafts rather than clerk-typists or secretarial-type positions. Training is permissible in lower level management positions such as office engineers, estimators, timekeepers, etc., where the training is oriented toward construction applications. Training in the laborer classification may be permitted provided that significant and meaningful training is provided and approved by the division office. Some offsite training is permissible as long as the training is an integral part of an approved training program and does not comprise a significant part of the overall training.

Except as otherwise noted below, the Contractor will be reimbursed 80 cents per hour of training given an employee on this contract in accordance with an approved training program. As approved by the Engineer, reimbursement will be made for training of persons in excess of the number specified herein. This reimbursement will be made even though the Contractor receives additional training program funds from other sources, provided such other source does not specifically prohibit the Contractor from receiving other reimbursement. Reimbursement for offsite training indicated above may only be made to the Contractor where he does one or more of the following and the trainees or apprentices are concurrently employed on a Federal-aid project; contributes to the cost of the training, provides the instruction to the trainee or apprentice or pays the trainee's or apprentice's wages during the offsite training period.

No payment shall be made to the Contractor if either the failure to provide the required training, or the failure to hire the trainee or apprentice as a journeyman, is caused by the Contractor and evidences a lack of good faith on the part of the Contractor in meeting the requirements of this Training Special Provision. It is normally expected that a trainee or apprentice will begin his training on the project as soon as feasible after start of work utilizing the skill involved and remain on the project as long as training opportunities exist in his work classification or until he has completed his training program. It is not required that all trainees or apprentices be on board for the entire length of the contract. A Contractor will have fulfilled his responsibilities under this Training Special Provision if he has provided acceptable training to the number of trainees or apprentices specified. The number trained shall be determined on the basis of the total number enrolled on the contract for a significant period.

Only trainees or apprentices registered in a program approved by the State of California's State Administrator of Apprenticeship may be employed on the project and said trainees or apprentices shall be paid the standard wage specified under the regulations of the craft or trade at which they are employed.

The Contractor shall furnish the trainee or apprentice a copy of the program he will follow in providing the training. The Contractor shall provide each trainee or apprentice with a certification showing the type and length of training satisfactorily completed.

The Contractor will provide for the maintenance of records and furnish periodic reports documenting his performance under this Training Special Provision.