

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

TTY 711



*Flex your power!
Be energy efficient!*

November 21, 2011

05-SCr-1-R0.0/10.2

05-0M7504

Project ID 0500020234

ACNH-P001(561)E

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN SANTA CRUZ COUNTY IN WATSONVILLE AND APTOS FROM PAJARO RIVER BRIDGE TO NORTH APTOS UNDERPASS.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, December 7, 2011.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, the Bid book and the Federal Minimum Wages with Modification Number 40 dated 11/18/2011.

Project Plan Sheets 63, 87, 91 and 115 are revised. Copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 10-1.33, "HOT MIX ASPHALT OPEN GRADED FRICTION COURSE," subsection "MATERIALS," the first paragraph is revised as follows:

"The grade of asphalt binder mixed with aggregate for OGFC must be PG 58-34PM."

Addendum No. 3
Page 2
November 21, 2011

05-SCr-1-r0.0/10.2
05-0M7504
Project ID 0500020234
ACNH-P001(561)E

In the Bid book, in the "Bid Item List," Items 19, 23, 34, 95, and 96 are revised, Items 107 and 108 are added and Item 106 is deleted as attached.

To Bid book holders:

Replace pages 3, 4, 7 and 8 of the "Bid Item List" in the Bid book with the attached revised pages 3, 4, 7 and 8 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.


Inform subcontractors and suppliers as necessary.

This addendum, attachments and the modified wage rates are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/05/05-0M7504

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,


SHARRI BENDER EHLERT
Interim District Director
District 6 Central Region

Attachments

BID ITEM LIST

05-0M7504

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM	LUMP SUM	
2	070018	TIME-RELATED OVERHEAD	WDAY	120		
3	071325	TEMPORARY FENCE (TYPE ESA)	LF	1,150		
4	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
5	074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
6	074028	TEMPORARY FIBER ROLL	LF	46,400		
7	074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	240		
8	074041	STREET SWEEPING	LS	LUMP SUM	LUMP SUM	
9	074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	LUMP SUM	LUMP SUM	
10	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
11	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
12	120159	TEMPORARY TRAFFIC STRIPE (PAINT)	LF	16,800		
13	120165	CHANNELIZER (SURFACE MOUNTED)	EA	110		
14	120300	TEMPORARY PAVEMENT MARKER	EA	180		
15	121161	TEMPORARY TERMINAL SECTION (TYPE K)	EA	1		
16	128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	LUMP SUM	LUMP SUM	
17	129000	TEMPORARY RAILING (TYPE K)	LF	6,280		
18	129100	TEMPORARY CRASH CUSHION MODULE	EA	200		
19	021746	QUICKCHANGE MOVEABLE BARRIER SYSTEM	LF	4,600		
20	021747	REMOVE SINGLE THRIE BEAM BARRIER	LF	1,410		

BID ITEM LIST

05-0M7504

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	021748	REMOVE DOUBLE THRIE BEAM BARRIER	LF	50		
22	150662	REMOVE METAL BEAM GUARD RAILING	LF	5,120		
23	150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	46,500		
24	150744	REMOVE ROADSIDE SIGN (WOOD POST)	EA	1		
25	150771	REMOVE ASPHALT CONCRETE DIKE	LF	120,000		
26	150857	REMOVE ASPHALT CONCRETE SURFACING	SQFT	15,600		
27	151572	RECONSTRUCT METAL BEAM GUARD RAILING	LF	10,500		
28	152316	RESET ROADSIDE SIGN (ONE POST)	EA	14		
29	152423	ADJUST MONUMENT TO GRADE	EA	10		
30	152439	ADJUST FRAME AND GRATE TO GRADE	EA	240		
31	152440	ADJUST MANHOLE TO GRADE	EA	1		
32	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	168,000		
33	153210	REMOVE CONCRETE	CY	8		
34	153221	REMOVE CONCRETE BARRIER	LF	4,370		
35	156590	REMOVE CRASH CUSHION (SAND FILLED)	EA	1		
36	190101	ROADWAY EXCAVATION	CY	960		
37	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
38	198001	IMPORTED BORROW (CY)	CY	910		
39	198007	IMPORTED MATERIAL (SHOULDER BACKING)	TON	4,530		
40	203002	EROSION CONTROL (COMPOST BLANKET)	CY	410		

BID ITEM LIST

05-0M7504

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
81	021752	DOUBLE METAL BEAM GUARD RAILING (STEEL POST)	LF	25		
82	839303	SINGLE THRIE BEAM BARRIER (STEEL POST)	LF	1,090		
83	839312	DOUBLE THRIE BEAM BARRIER (STEEL POST)	LF	50		
84	839540	TRANSITION RAILING (TYPE STB)	EA	12		
85	839541	TRANSITION RAILING (TYPE WB)	EA	19		
86	839542	TRANSITION RAILING (TYPE DTB)	EA	1		
87	839576	END CAP (TYPE A)	EA	5		
88	839578	END CAP (TYPE TC)	EA	13		
89	839581	END ANCHOR ASSEMBLY (TYPE SFT)	EA	38		
90	839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	12		
91	839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	19		
92	021753	ALTERNATIVE CRASH CUSHION SYSTEM (TEST LEVEL 3)	EA	2		
93	021754	CONCRETE BARRIER (TYPE 60A MODIFIED)	LF	260		
94	021755	CONCRETE BARRIER (TYPE 60R)	LF	64		
95	839701	CONCRETE BARRIER (TYPE 60)	LF	2,450		
96	839703	CONCRETE BARRIER (TYPE 60C)	LF	1,600		
97	840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	8,370		
98	840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	LF	426,000		
99	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	10,900		
100	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	6,980		

BID ITEM LIST**05-0M7504**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
101	860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM	LUMP SUM	
102	860810	INDUCTIVE LOOP DETECTOR	LS	LUMP SUM	LUMP SUM	
103	021756	MODIFY WIRELESS VEHICLE DETECTION SYSTEM	LS	LUMP SUM	LUMP SUM	
104	021757	REMOVE EXISTING TRAFFIC MONITORING STATION	LS	LUMP SUM	LUMP SUM	
105	861503	MODIFY LIGHTING	LS	LUMP SUM	LUMP SUM	
106	BLANK					
107	150715	REMOVE THEROMOPLASTIC PAVEMENT MARKING	SQFT	6,910		
108	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID:

\$ _____